From: Matt Wilmot <mwilmot@atei97.com>
Sent: Tuesday, November 18, 2025 2:03 PM

To: Andres Targa
Cc: Ed vonDran

Subject: RE: Notice of Deficiency: 181766 398884 Raider Aggregates LLC **Attachments:** Raider Aggregates Draft Build Optimized mw 11.18.25 R1.pdf

Categories: GTG WCC

Attached is the altered and complete version of our entry.

Thank you for your attention to this matter.

Matt Wilmot, GIT



architecture engineering environment

Office: 210-930-2834 **Mobile**: 210-386-1474

Email: mwilmot@atei97.com

8626 Tesoro Drive Suite 810 San Antonio, TX 78217 www.atei97.com





TBPE F-8920; Arch BR-1889; TBPG 50647

This message and any attachments are intended only for the use of the addressee and may contain information that is privileged and confidential. If the reader of the message is not the intended recipient or an authorized representative of the intended recipient, you are hereby notified that any dissemination of this communication is strictly prohibited. If you have received this communication in error, notify the sender immediately by return email and delete the message and any attachments from your system.

From: Andres Targa < Andres. Targa@tceq.texas.gov>

Sent: Tuesday, November 18, 2025 1:51 PM **To:** Ed vonDran <evondran@atei97.com>

Cc: Matt Wilmot <mwilmot@atei97.com>; 90TRANSPORTATION@GMAIL.COM

Subject: Notice of Deficiency: 181766 398884 Raider Aggregates LLC

Dear Mr. Muniz:

Upon evaluation of the above-referenced application, we have determined that your application is deficient and Raider Aggregates Limited Liability Company must provide additional information to ensure that the requirements for obtaining a permit are met. Please furnish the following information within 5 days:

Air Quality Standard Permit Checklist for Permanent Rock and Concrete Crushers

• Based on your response regarding Maintenance Startup and Shutdown (MSS) emissions, please update your answer from "N/A" to "No" for condition (1)(P) to ensure that you are complying with MSS emissions.

TCEQ Form 20335

 Please update your response from "No" to "Yes" for rule 116.610(a)(3) to ensure that you are complying with Title 40 Code of Federal Regulations Part (CFR) 60, New Source Performance Standards.

After receipt of all the additional information, we will continue the review of your application. If the information furnished in response to this notice results in the need for further clarification or additional information, we will notify you. Please note that the applicant Raider Aggregates Limited Liability Company is required to furnish all information to demonstrate that the facility or source will comply with all applicable federal and state rules and statutes.

Failure to submit all of the requested information within 5 days of the date of this notification may result in a recommendation to void your application.

Sincerely,

Andres Targa Mallona

Mechanical New Source Review Environmental Permit Specialist Air Permits Division Texas Commission on Environmental Quality Mail Code: MC-163, PO Box 13087

Austin, Texas 78711-3087 Direct Line: (512) 239-6107



How are we doing? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey



November 18, 2025

Texas Commission on Environmental Quality Air Permits Initial Review Team, MC 161 12100 Park 35 Circle Building C, Third Floor Austin, Texas 78753

Subject: Claim of a Standard Permit under 30 TAC §116.611 to operate a Caliche Pit Facility

Reference: Raider Aggregates Limited Liability Company

To whom it may concern:

Please find attached supporting documentation for a Standard Permit application for Raider Aggregates, LLC. registering a Caliche Pit facility located off of Co Rd 421 in Whitsett Texas, 78075.

INTRODUCTION

RAIDER AGGREGATES, LLC is applying to authorize a Caliche Pit facility located in Live Oak County. Caliche based aggregates will be extracted from the site, crushed via impact crusher, and hauled away via transport truck. Facility layout and operational parameters are detailed in attached appendices.

New Source Review (NSR) Authorization

RAIDER AGGREGATES, LLC is proposing to authorize the Caliche Pit facility under 30 Texas Administrative Code (TAC) §116.611. In addition to the Caliche Pit facility meeting the claimed Standard Permit, the facility meets the general requirements of 30 TAC §116.611 (posted in STEERS with this supporting data).

RAIDER AGGREGATES, LLC is submitting this application for a Standard Air Permit to authorize operations at a proposed caliche pit located off of Co Rd 421 near Whitsett Texas. The site will be used for the extraction and processing of caliche material, which is commonly utilized in road base, construction, and other infrastructure projects.

The facility will involve activities such as excavation, stockpiling, material handling, and loading of caliche into transport trucks. Emission sources will primarily include fugitive dust from material handling and vehicle traffic, as well as emissions from any associated equipment such as screens or conveyors. Appropriate dust suppression methods, including water sprays and best management practices, will be employed to minimize particulate emissions and ensure compliance with applicable Texas Commission on Environmental Quality (TCEQ) regulations.

This application includes a detailed site layout, equipment specifications, emission calculations, and a demonstration of compliance with all applicable air quality standards under the TCEQ's Standard Permit for Rock and Concrete Crushers.

PROCESS DESCRIPTION AND CONTROL MEASURES

EPN 1 – Scania DC13 Diesel Engine Exhaust

The Trakpactor 550 is powered by a Scania DC13 Tier 4 Final diesel engine rated at 494 horsepower. This engine drives the crusher and associated hydraulic systems. Emissions from this source include nitrogen oxides (NOx), carbon monoxide (CO), volatile organic compounds (VOC), sulfur dioxide (SO₂), and particulate matter (PM). The unit is certified to meet Tier 4 Final standards under 40 CFR 60 Subpart IIII for nonroad compression-ignition engines and is equipped with selective catalytic reduction (SCR) and diesel oxidation catalyst (DOC) controls.





No MACT Subpart ZZZZ requirements apply because this is a portable engine that does not remain in one location for more than twelve months.

EPN 2 – Primary Feed Hopper

Material is delivered to the crusher via a steel hopper that receives caliche or aggregate from a front-end loader or excavator. The drop from the loader bucket into the hopper is a potential source of particulate emissions. Fugitive dust (PM₁₀ and PM_{2.5}) is controlled by a water spray bar positioned along the hopper lip and by minimizing drop height during loading operations. The hopper is designed with abrasion-resistant liners to reduce material buildup and associated dust generation.

EPN 3 - Vibrating Grizzly Feeder

The vibrating grizzly feeder transfers material from the hopper into the crusher while removing fine material prior to crushing. This process can generate minor dust emissions during agitation and material drop. A spray system positioned above the feeder maintains material moisture and prevents visible emissions. The feeder is subject to 40 CFR 60 Subpart OOO requirements for nonmetallic mineral processing plants.

EPN 4 – Impact Crusher (Trakpactor 550)

The main emission source at the site is the impact crusher itself. Material enters the crusher chamber and is broken down by a twin-apron, four-bar impactor. Crushing releases fine particulate matter (PM₁₀ and PM_{2.5}). These emissions are controlled by multiple atomizing spray nozzles mounted inside the crusher housing, flexible skirting around transfer points, and an optional enclosure. The unit operates under NSPS Subpart OOO for performance and opacity limits.

EPN 5 - Crusher Discharge Conveyor #1

After crushing, material is transferred from the crusher onto the first discharge conveyor. Dust emissions occur as material drops onto the belt and as it travels along the conveyor. Control measures include full-length belt skirting, covered transfer points, and water sprays installed at both loading and discharge ends of the belt. The conveyor system complies with Subpart OOO and AP-42 Section 11.19.2 emission guidance.

EPN 6 – Vibratory Screen #1 (Primary)

The first screening unit separates material by size into coarse and fine fractions. Screening activity generates fine dust from vibration and material agitation. Water spray bars located above each deck reduce airborne particulate. The screen is covered under 40 CFR 60 Subpart OOO and is limited to 10% opacity per NSPS standards. Maintenance logs are kept for each spray system inspection.

EPN 7 – Vibratory Screen #2 (Secondary/Fines)

The secondary screening deck further classifies material into finer product sizes. Emissions consist of PM₁₀ and PM_{2.5} from material agitation. Control measures mirror those of the primary screen, including active spray bars and belt skirting at feed and discharge points. All equipment is operated and maintained to ensure compliance with opacity limits.

EPN 8 – Transfer Conveyor #2

This conveyor moves screened material from the first to the second screen or to a different processing line. The main emissions occur from material falling onto and off the conveyor. These are minimized by skirting and misting systems that apply water directly at transfer points. Periodic inspections ensure adequate belt tension and spray operation.

EPN 9 – Final Product Conveyor #3







The final conveyor discharges finished crushed and screened product to the stockpile. Water spray bars positioned at the head pulley provide continuous wet suppression during active operation. Belt covers or partial enclosures may be installed to limit windblown dust. This point represents the last material transfer before storage.

EPN 10 - Stockpile Drop Point / Loading Area

Crushed material exits the conveyor and falls onto the finished product stockpile. This drop can generate dust emissions, particularly during dry conditions. Stockpile dust is controlled with continuous or intermittent spray systems at discharge points and with surface wetting. Stockpiles are built with low slope angles and may be stabilized using crusting agents or covered if inactive. Windbreaks can be used for added control.

EPN 11 – Pit Excavation and Loading Operations

The pit area generates dust during excavation, loading, and hauling of raw caliche or aggregate material to the crusher. Emissions are managed through watering disturbed areas, minimizing drop heights when loading trucks, and limiting disturbed acreage. Completed pit sections are stabilized when inactive to minimize dust emissions.

Non-EPN Fugitive Emission Sources – Unpaved Roads

Per TCEQ guidance, fugitive emissions from unpaved haul and access roads are not listed as individual EPNs because they are not considered discrete process emission points. These emissions are instead categorized as site-wide fugitive sources and addressed through best management practices. Dust from unpaved roads is controlled through the use of water trucks, speed limits of 15 mph, and, when necessary, environmentally safe dust suppressants. Watering frequency is adjusted according to traffic levels and weather conditions. Records of road watering and control maintenance are retained for compliance documentation but do not require individual EPN designation.

Control System Description (Not an EPN)

The water spray system serves as the primary control mechanism for dust suppression across all emission points. The system operates at 3 bar pressure and 24 liters per minute, feeding multiple atomizing nozzles positioned over the crusher, screens, conveyors, and transfer points. The water system includes frost protection, pump, and manifold assemblies. This system ensures compliance with visible emission and particulate standards under the TCEQ Standard Permit.

Recordkeeping and Monitoring

Daily logs are maintained for all watering events, suppressant applications, and equipment maintenance activities. Each emission point is visually inspected per shift to confirm effective dust control. Any failures in control systems are corrected immediately, and corrective actions are documented. All records are retained onsite for a rolling 24-month period and made available to the TCEQ upon request.

MAINTENANCE, START-UP, AND SHUTDOWN

Startup and shutdown emissions for the Powerscreen Trakpactor 550 crusher with Scania DC13 Tier 4 Final engine will not exceed emissions during normal production operations. The engine is equipped with SCR, EGR, DOC, and AMOX emission controls that function during all operating modes including startup and shutdown. Startup procedure involves:

1. Engine warm-up period (approximately 5-10 minutes)





- 2. Gradual increase to operating temperature
- 3. SCR system reaches operational temperature
- 4. No crushing activity occurs until engine reaches normal operating parameters

Engine will be shut off during maintenance.

Shutdown is controlled and emissions during shutdown are lower than production emissions as the engine idles down before shutoff.

No separate MSS authorization is required because emissions during maintenance, start-up, and shutdown will not exceed those of normal operations.

EMISSIONS CALCULATION METHODOLOGY

This section presents documentation of emissions calculations for the RAIDER AGGREGATES Caliche Pit facility. The facility has several pints of emissions as listed above including engine emissions from trucks, front end loaders, excavators, and the rock crusher. All calculations represent worst-case with respect to potential emissions.

Should you have any questions regarding this submittal, please contact me at (210) 326-6991.

Respectfully submitted,

Alpha Terra Engineering, Inc.

Harold E. von Dran, Jr., PE

Environmental Engineer (TX 92737 / F-8920)

Attachments:

1) Exhibit A – Emissions Calculations

2) Exhibit B – Facility Maps

3) Exhibit C – Process Flow Diagram and Description

4) Exhibit D – Crusher Info

5) Exhibit E – Tables and Forms






Exhibit A Emission Calculations


			AP-42 EF (lb/ton)	AP-42 EF (lb/hp-		*Engine Exhaust AP	-	
EPN#	EPN	Description	controlled1	hr) ¹	AP-42 EF (lb/VMT) ¹	42 ²	EF (g/kWh)	
EPN1	Engine Exhaust	Rock Crushing Activities		Various		Nox	0.4	
EPN2	Primary Feed Hopper	Material drop	0.002			CO	3.5	
EPN3	Vibrating Grizzly Feeder	Screen/feeder	0.002			NMHC	0.19	
EPN4	Impact Crusher	Crusher	0.0054			PM10	0.02	
EPN5	Conveyor #1	Conveyor transfer	0.0015					
						**Unpaved Roads	EF (Ib/VMT)	80%
EPN6	Primary Screen	Screen	0.0022			AP-42	uncontrolled	Controlled
EPN7	Conveyor #2	Conveyor transfer	0.0015			PM10	1.5	0.3
EPN8	Secondary Screen	Screen	0.0022			PM2.5	0.15	0.03
EPN9	Conveyor #3	Conveyor transfer	0.0015			TSP	4.90	0.98
EPN10	Stockpile Drop Points	Stockpile loading	0.0025					
EPN11	Pit Excavation & Loading	Pit/loading	0.002					
FUG (Non EPN)	Unpaved Roads	Roads that are unpaved			Various**			
hours operating per year		2640						
Facility Coordinates	Northing	28.62523	Easting	-98.312255	Elevation	214		
		¹ TCEQ Technical Guidance a		Section 11.19.2				
		From the State of California	a Resources Board					

EPN No	EPN Type	Description	NO _x	СО	NMHC	PM ₁₀	
1	Engine Exhaust	Exhaust from Crusher Generator or Engine	0.35	3.04	0.16	0.02	
2	Primary Feed Hopper	Material drop	0.00	0.00	0.00	0.53	
3	Vibrating Grizzly Feeder	Screen/feeder	0.00	0.00	0.00	0.53	
4	Impact Crusher	Crusher	0.00	0.00	0.00	1.43	
5	Conveyor #1	Conveyor transfer	0.00	0.00	0.00	0.40	
6	Primary Screen	Screen	0.00	0.00	0.00	0.58	
7	Conveyor #2	Conveyor transfer	0.00	0.00	0.00	0.40	
8	Secondary Screen	Screen	0.00	0.00	0.00	0.58	
9	Conveyor #3	Conveyor transfer	0.00	0.00	0.00	0.40	
10	Stockpile Drop Points	Stockpile loading	0.00	0.00	0.00	0.66	Total EPN Emissions (tons/yr)
11	Pit Excavation & Loading	Pit/loading	0.00	0.00	0.00	0.53	9.58
FUG	Unpaved Roads	Particulate Generated by use of Unpaved Roads	0.00	0.00	0.00	15.84	Total Emissions (tons/yr)
			0.35	3.04	0.16	21.88	25.42
							Uncontrolled EPN + 80%
	Conditions:						Controlled FUG*
		l on permit data and technical documentation for t ar) for your scenario— ~10 hours per day, 5 days p				_	ultra-low sulfur diesel
	PM10 Values for Crushing and suppression or similar control	d Screening based on a Powerscreen Trakpactor 55 s are in place.	0 operating at 20	00 tons/hour,	10 hours/day	, 5 days/we	eek assuming wet
	Unpaved Roads PM10 assume	es best practice dust mitigation (80%) and 0.25 mile	es of unpaved ro	ads assuming	transporting t	the maximu	um of 1716000 tons a year.

PM10 Calculations											1
Throughput (tons/hr) x E	F (lb/ton) =(lb/hr)/ (1to	n/2000 lb) = tons/h	ır x 2640 hr/vr	= tons/year							
Throughput (tons/fil) x El	(ID/ torry = (ID/ Tir/) (Tto	11/2000 10) = 10/13/1	11 X 20101117 yr	- toris/ year							
	Throughput	Emission Factor		Operaing Time							
	(Tons/hr)	(lb/ton)	One Ton (lbs)	Hrs/Yr	PM10	Formulas					
On other	200	E 400E 02	2000	2/40	1 407	DE+C	- /D-+				
Crushing	200	5.400E-03	2000	2640	1.426	=B2C	5/D5*E5				
Screening	200	2.200E-03	2000	2640	0.581	=B6*C	6/D6*E6				
<u>-</u>											
Total Tons = Trips per year ×											
Tons per trip											
Harandar Had DN 410 to a 6 m											
Uncontrolled PM10 ton/yr = Total Tons × EF/2000											
10tal 1013 × E172000											
Controlled PM10 tons/yr =											
Uncontrolled PM10 tons/yr ×											
(1 - Control Efficiency)											
Unpaved Roads											
- parentines											
Total Tons (ton/yr)	Trips per year	Tons per trip									
528000								-			
Uncontrolled DM410 + /	Emission Factor	lh/ton									
Uncontrolled PM10 ton/yr 79.2	(lb/VMT) 0.3	lb/ton 2000									-
17.2	0.3	2000									
Controlled PM10 (ton/yr)	(1-Control efficiency)	using 80%									
15.84	0.2										
F : : 01 :											
Emissions Sheet											
EPN-1 Emissions Calculation											
((Emission Factor											
(g/kWh)xEngine power											
(kw)xOperating hours											
(h))/1000000 (metric											
ton/g))x1.1023 (US											
tons/metric ton)											
					US						
	Emission Factor	Engine Power	Opperating	metric ton/g	tons/metric						
	(g/kWh)	(kW)	Hours	(1000Kg)	ton						
NOx	0.4	298		1,000,000	1.1023						
CO	3.5	298	2640	1,000,000	1.1023						
NMHC	0.19			1,000,000	1.1023						
PM10	0.02	298	2640	1,000,000	1.1023						
	Annual Emissions (US										
	tons)										
NOx	0.35										
CO	3.04						<u> </u>				
NMHC	0.16										
PM10	0.02										
EPN 2-11 Emissions											
Calculations							tons/hr				-
						Uncontrolled	tons/nr conversion			Uncontrolled	Controlled
EPN	Source	Process Type	Pollutant	TPH	EF (lb/ton)	lb/hr		tons/hr	Hours/yr		TPY 80%
					. (/						50,0
2	Primary Feed Hopper	Material drop	PM10	200	0.002	0.4	0.0005	0.0002	2640	0.528	0.1
	Vibrating Grizzly										
	Feeder	Screen/feeder	PM10	200		0.4		0.0002	2640		
	Impact Crusher	Crusher	PM10	200					2640		
	Conveyor #1	Conveyor transfer		200		0.3		0.00015	2640		
,	Primary Screen Conveyor #2	Screen Conveyor transfer	PM10 PM10	200				0.00022 0.00015	2640 2640		
			PM10	200					2640		
7	Secondary Screen	Screen				0.44				5.5550	
	Secondary Screen Conveyor #3	Screen Conveyor transfer	PM10	200		0.3	0.0005	0.00015	2640	0.396	0.0
						0.3	0.0005	0.00015	2640	0.396	0.0
7 8 9	Conveyor #3 Stockpile Drop Points	Conveyor transfer			0.0015	0.3		0.00015	2640 2640		
7 8 9 10	Conveyor #3 Stockpile Drop Points Pit Excavation &	Conveyor transfer	PM10	200	0.0015	0.5	0.0005		2640	0.66	0.1

Exhibit B Facility Maps





(Satellite Image (Hybrid Street)) AERIAL PHOTO SERIES (Satellite Image (Hybrid Street)) 098.333101°W U **topo** 098.255107° W + 028.648583° N (Satellite Image (Hybrid Street)) Distance to Nearest Place of Worship Exceeds 1 Mile 1.7179 Miles, 078.65° T River to Barn (Satellite Image (Hybrid Street)) (Satellite Image (Hybrid Street)) Excavaton Area Center of Excavation Area 028.625226° N 098.312255° W 449 Yards, 116.40° T Distance to multiple Barns 475 Yards, 122.60° T Distance to Distance to Nearest Public **HWY Exceeds 1 Mile** 441 Yards, 140.93° T 1.1046 Miles, 135.95° T 028.601028° N 098.333101° W 028.601028° N 098.255107° W (Satellite Image (Hybrid Street)) SCALE 1:25000 Declination (Satellite Image (Hybrid Street)) (Satellite Image (Hybrid Street)) Produced by Trimble Terrain Navigator Pro Topography based on USGS 1:12,000 Maps 28098-E3-TM-012

North American 1983 Datum (NAD83) To place on the predicted North American 1927 move the projection lines 29M N and 28M

CONTOUR INTERVAL UNKNOWN FT

WILLOW HOLLOW TANK, TX MAY 16, 2022


CONTOUR INTERVAL 10 FT

To place on the predicted North American 1927 move the projection lines 29M N and 28M

DEC 31, 1969

Exhibit C Process Flow Diagram

EPN FLOW DIAGRAM



Comprehensive EPN List - Trakpactor 550 Rock Crusher Project

Facility: Portable Rock Crusher (Powerscreen Trakpactor 550)

Permit Type: TCEQ Standard Permit for Rock and Concrete Crushers

Prepared For: Form PI-1S / Form 20335 Attachment – EPN Summary Table

EPN	Source Name / Description	Emission Type / Pollutant	Control Device / Method	Regulatory Reference
1	Scania DC13 Diesel Engine Exhaust (Tier 4F, 494 hp)	NOx, CO, VOC, PM, SO2	Built-in engine controls (SCR, DOC); Tier 4F compliant	40 CFR 60 Subpart IIII; Nonroad CI Engine Standards
2	Primary Feed Hopper	PM10, PM2.5 (Fugitive Dust)	Water sprays at hopper lip	AP-42 11.19.2; NSPS OOO
3	Vibrating Grizzly Feeder	PM10, PM2.5	Spray bar over feeder	AP-42 11.19.2; NSPS OOO
4	Impact Crusher (Trakpactor 550)	PM10, PM2.5	Internal water sprays, housing enclosure	AP-42 11.19.2; 40 CFR 60 Subpart OOO
5	Crusher Discharge Conveyor #1	PM10, PM2.5	Spray nozzles, belt skirting	AP-42 11.19.2; 40 CFR 60 Subpart OOO
6	Vibratory Screen #1 (Primary)	PM10, PM2.5	Spray bar at screen decks	AP-42 11.19.2; 40 CFR 60 Subpart OOO
7	Transfer Conveyor #2	PM10, PM2.5	Full skirting, spray bar	AP-42 11.19.2; 40 CFR 60 Subpart OOO
8	Vibratory Screen #2 (Secondary/Fines)	PM10, PM2.5	Spray bar at screen decks	AP-42 11.19.2; 40 CFR 60 Subpart OOO
9	Final Product Conveyor #3	PM10, PM2.5	Spray bar at discharge, skirting	AP-42 11.19.2; 40 CFR 60 Subpart OOO

EPN	Source Name / Description	Emission Type / Pollutant	Control Device / Method	Regulatory Reference
10	Stockpile Drop Point / Loading	PM10, PM2.5 (Fugitive)	Water sprays at conveyor discharge, surface wetting	AP-42 13.2.4 (Aggregate Handling)
11	Pit Excavation and Loading Operations	PM10, PM2.5 (Fugitive)	Watering disturbed areas, minimize drop heights	AP-42 13.2.2

Non-EPN Fugitive Emission Sources – Unpaved Roads

Per TCEQ guidance, fugitive emissions from **unpaved haul and access roads** are not listed as individual EPNs because they are not considered discrete process emission points. These emissions are treated as site-wide fugitive sources controlled through best management practices. Controls include water truck application, a 15 mph speed limit, and use of dust suppressants during dry periods. Records of watering and maintenance are retained for compliance documentation but do not require EPN designation.

Control System Description (Not an EPN)

The water spray system serves as the primary control mechanism for dust suppression across all emission points. Operating at 3 bar pressure and 24 L/min, it feeds multiple atomizing nozzles positioned over the crusher, screens, conveyors, and transfer points. The water system includes frost protection, pump, and manifold assemblies to maintain consistent performance.

Recordkeeping and Monitoring

Daily logs document watering events, suppressant applications, and equipment maintenance. Each emission point is visually inspected per shift to verify effective control. Any malfunction or failure is corrected immediately, and actions are recorded. Records are maintained for a rolling 24-month period and made available to TCEQ upon request.

Process Description

Material handling at the site begins with caliche or aggregate being loaded from the **pit** area (EPN 11) into the **primary feed hopper (EPN 2)** using a front-end loader or excavator. From the hopper, material passes over the **vibrating grizzly feeder (EPN 3)**, which removes finer material and regulates flow into the **impact crusher (EPN 4)**. The Trakpactor 550 impact crusher reduces the feed material to the desired size using a twin-apron, four-bar impactor system.

The crushed material exits the crusher onto the **first conveyor (EPN 5)**, which transfers material to the **primary screen (EPN 6)**. This screen separates the crushed aggregate into multiple size fractions. Oversized material may be recirculated through the system for additional crushing if required, while correctly sized material is transferred via the **second conveyor (EPN 7)** to the **secondary screen (EPN 8)** for further refinement.

The secondary screen produces the final graded product, which is conveyed by the **final product conveyor (EPN 9)** to the **stockpile drop points (EPN 10)**. Each conveyor and screen is equipped with water spray bars, belt skirting, and covered transfer points to control particulate emissions. Water spray systems operate continuously during production to minimize visible dust emissions.

Final products are temporarily stored in multiple **aggregate stockpiles** near the discharge points of each conveyor. The piles are sprayed or misted with water to minimize windblown dust and shaped with stable slopes. Material from the stockpiles is later loaded into trucks for off-site delivery. The single **Scania DC13 diesel engine (EPN 1)** powers the crusher and associated equipment. Dust from pit excavation and material loading (EPN 11) is minimized through water application and operational controls.

All material handling and crushing operations are conducted under the requirements of **40 CFR Part 60, Subpart OOO** (Standards of Performance for Nonmetallic Mineral Processing Plants). Fugitive emissions from unpaved haul roads are addressed through site-wide best management practices and are not designated as individual EPNs under TCEQ guidance.

Simplified Process Flow Sequence (EPN Reference)

- 1. **EPN 1** Scania DC13 Engine (Power Source)
- 2. **EPN 2** Feed Hopper
- 3. **EPN 3** Vibrating Grizzly Feeder
- 4. **EPN 4** Impact Crusher (Trakpactor 550)

- 5. **EPN 5** Conveyor #1 (Crusher Discharge)
- 6. **EPN 6** Primary Screen
- 7. **EPN 7** Conveyor #2 (Transfer to Secondary Screen)
- 8. **EPN 8** Secondary Screen
- 9. **EPN 9** Conveyor #3 (Final Product Transfer)
- 10. **EPN 10** Stockpile Drop Points / Finished Product Storage
- 11. **EPN 11** Pit Excavation and Material Loading

Exhibit D Crusher Info

POWERSCREEN® TRAKPACTOR 550



HORIZONTAL IMPACTOR





TECHNICAL SPECIFICATION - REV 4 01/02/2023



To use my interactive features I need to be opened in 'Adobe Acrobat Reader' click here to download





OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - ▶ OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS



SPECIFICATION

Total Weight PS: Tier 4F: 57,450kg (126,656lbs) Hopper extensions, bypass conveyor, single pole

magnet

Total Weight VGF: Tier 3: 54,850kg (120,924lbs) Hopper extensions, bypass conveyor, single pole

magnet, extended main conveyor

Transport Length 17.46m (57' 5") PS & Standard product conveyor

Height 3.8m (12' 6") **Width** 3m (9' 10")

Working Length 17.82m (58'6'') PS & Standard product conveyor

Height 5.15m (16' 10") **Width** 6.96m (22' 10")

Crusher Type: Twin apron 4 bar impact crusher, feed opening 1370mm x 911mm (54" x 36") **Power Unit** Tier 3 Caterpillar C13 328kW (440hp) or Tier 4F Scania DC13 368kW (494hp)

Plant Colour RAL 5021, RAL 7024, RAL 9005

APPLICATIONS



Aggregate

Blasted rock River rock



Recycling

C&D waste Foundry waste



Mining

Processed ores
Processed minerals









OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

PRODUCT CONVEYOR

Conveyor type: Fully removable modular unit with hydraulic raise

& lower facility to increase clearance & simplify rebar removal. Shallow troughed with winged rollers & fully tunnelled with minimal snag areas

Belt type: Ripstop EP500/3 8+2 with steel wire breaker ply

Belt width: 1200mm (3' 11")

Discharge height: 3.8m (12' 6") when fully raised

Stockpile volume: 101m³ (132 cu. yd.)

Feedboot: Fabricated steel with abrasion resistant steel liners

Impact area: Heavy duty under crusher impact bars

Skirting: Fully skirted in wear resistant rubber up to magnet

discharge area

Drive: Dual hydraulic motor direct to head drum

Lubrification: Centralised grease points for lubrication of shaft

bearings

Belt covers: Optional aluminium removable dust covers
Belt adjustment: Belt tensioning is by use of screw adjustment at

the head drum

Speed wheel: Designed to stop plant feed if the discharge

conveyor slows or stops

DUST SUPPRESSION SYSTEM

Spray bars with atomiser nozzles mounted over product conveyor & final conveyor discharge, piped to an inlet manifold for customer water supply or optional pump.

Type: Clean water multi atomising nozzles


Inlet: Single point on chassis

Inlet pressure: 3 bar (44psi)

Water supply: 24 litres (6.3 g) per minute min

Frost protection: Via system main valves

Pump: Optional









♠ OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

POWER UNIT & HYDRAULICS

Tier 3 Equivalent: Caterpillar C-13 ACERT, 6 cylinder, 328

kW (440hp)

Operating Conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected.

Operating rpm range: 1700 - 2100rpm **Emission control technique**: Not applicable

Plant drive: High quality tandem pumps driven via

engine PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Tier 4F / Stage V: Scania DC13 385A - 368kW (494hp)

Operating conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected

Operating rpm range: 1500 - 1900rpm

Emission control technique: Selective Catalytic Reduction (SCR)

Reductant tank size: 60 L (16 US Gal)

Plant drive: High quality pumps driven via clutch

PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Fuel tank capacity: 1000 L (264 US Gal)

Hydraulic tank capacity: 740 L (195 US Gal)

Crusher drive: Direct drive via wedge belts, clutch pulley diameter 425mm T4,

375mm T3

Crusher pulley diameter 800mm Terex

(39")

800mm with Hazemag chamber Crushing performance can be tuned, by changing engine speed via the PLC.

Chruscer drive tensioning: VEE belt tensioner system









OVERVIEW

- **FEATURES & BENEFITS**
- **CRUSHER**
 - **CRUSHER SPECIFICATION**
 - **CRUSHER FEATURES**
- **HOPPER**
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- **POWER UNIT & HYDRAULICS**
- **TRACKS**
- **PLANT CONTROLS & OTHER**
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- **OPTIONS**
 - **OPTIONS 2**
 - **OPTIONS 3**
- POWERSCREEN® PULSE
- **DIMENSIONS**



HAZEMAG CRUSHER SPECIFICATION

1360mm x 800mm (54" x 32") Feed opening:

500mm³ (20in³) / 860mm (34") diagonally/ Max lump size*:

1000 x 1000 x 200mm (39 x 39 x 8") slab

*depending on material blow bar specification

1340mm (53") Rotor width: Rotor diameter: 1200mm (47")

Number of aprons:

Maximum clearance: 273mm (11") on both aprons

Maximum OSS setting: 200mm (8") upper apron, 100mm (4") lower

Minimum CSS setting: 75mm (3") upper apron, 35mm (1.4") lower

Number of blow bars: 4

Blow bar removal: Vertically

Blow bar configuration: 2 full & 2 half (optional 4 full)

Setting adjustment: Hydraulic assist Overload protection: Hydraulic

Rotor speeds: 540 - 630rpm (34 - 40m/s) (111 - 131ft/s)

Demolition / recycling / quarry Applications:

14,855kg (32,750lbs) Crusher weight:

Full blow bar weight: 410kg (904lbs)

Side Liners: 20mm thick, abrasive resistant steel










♠ OVERVIEW


- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - ▶ CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- ► HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS


DIMENSIONS

Figure 1: Trakpactor 550 - Pre-screen, Standard Product Conveyor

Working Position









SCANIA CV AB

EXECUTIVE ORDER U-R-024-0034 New Off-Road Compression-Ignition Engines

Pursuant to the authority vested in the Air Resources Board by Sections 43013, 43018, 43101, 43102, 43104 and 43105 of the Health and Safety Code; and

Pursuant to the authority vested in the undersigned by Sections 39515 and 39516 of the Health and Safety Code and Executive Order G-14-012;

IT IS ORDERED AND RESOLVED: That the following compression-ignition engine and emission control system produced by the manufacturer are certified as described below for use in off-road equipment. Production engines shall be in all material respects the same as those for which certification is granted.

MODEL YEAR	ENGINE FAMILY	DISPLACEMENT (liters)	FUEL TYPE USEFUL (hours				
2018	JY9XL12.7DAA	12.7	Diesel 8000				
SPECIAL	FEATURES & EMISSION (CONTROL SYSTEMS	TYPICAL EQUIPMENT APPLICATION				
Cooler, Module, D DC1308	ic Direct Injection, Turboo Exhaust Gas Recirculatio iesel Oxidation Catalyst (5A), Smoke Puff Limiter, action-Urea, Ammonia Ox	on, Engine Control Except Engine Code Selective Catalytic	Crane, Loader, Tractor, Dozer, Pump, Cor	npressor, Generator			

The engine models and codes are attached.

The following are the exhaust certification standards (STD) and certification levels (CERT) for non-methane hydrocarbon (NMHC), oxides of nitrogen (NOx), or non-methane hydrocarbon plus oxides of nitrogen (NMHC+NOx), carbon monoxide (CO), and particulate matter (PM) in grams per kilowatt-hour (g/kw-hr), and the opacity-of-smoke certification standards and certification levels in percent (%) during acceleration (Accel), lugging (Lug), and the peak value from either mode (Peak) for this engine family (Title 13, California Code of Regulations, (13 CCR) Section 2423):

RATED	EMISSION			E	OPACITY (%)					
POWER CLASS	STANDARD CATEGORY		NMHC	NOx	NMHC+NOx	co	PM	ACCEL	LUG	PEAK
130 ≤ KW ≤ 560	Tier 4 Final	STD	0.19	0.40	N/A	3.5	0.02	N/A	N/A	N/A
		CERT	0.08	0.19		0.2	0.02			

BE IT FURTHER RESOLVED: That for the listed engine models, the manufacturer has submitted the information and materials to demonstrate certification compliance with 13 CCR Section 2424 (emission control labels), and 13 CCR Sections 2425 and 2426 (emission control system warranty).

Engines certified under this Executive Order must conform to all applicable California emission regulations.

This Executive Order is only granted to the engine family and model-year listed above. Engines in this family that are produced for any other model-year are not covered by this Executive Order.

Executed at El Monte, California on this ___

_ day of February 2018.

Annette Hebert, Chief

Emissions Compliance, Automotive Regulations and Science Division

ATTACHMENTIOFI Engine ModelsEZ U-R-024-0034 1/17/2018

Engine Family	Code	2.Engine Model	3.Dis- placement	4.Power kW @RPM	mm/stroke @ peak HP	6.Fuel Rate: (lbs/hr) @ peak HP	7.Torque Nm @ RPM	8.Fuel Rate: mm/stroke@ peak torque	9.Fuel Rate: (lbs/hr)@ peak torque	10 Emission Control Davice
Y9XL12.7DAA	DC13 084A	2133500	12.7	294 @ 2100	198	140	2157 @ 1200	290	117	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 084A	2133501	12.7	331 @ 2100	222	157	2255 @ 1300	307	134	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133502	12.7	368 @ 2100	245	173	2373 @ 1300	325	142	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133503	12.7	405 @ 1900	344	243	2373 @ 1300	394	172	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245984	12.7	257 @ 1800	193	117	1638 @ 1300	219	96	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2258254	12.7	257 @ 2100	175	124	1720 @ 1300	232	102	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245985	12.7	283 @ 1800	211	149	1765 @ 1300	238	104	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 089A	2245986	12.7	257 @ 1800	193	117	1600 @ 1300	215	94	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
JY9XL12.7DAA	DC13 089A	2245987	12.7	283 @ 1800	211	128	1780 @ 1300	240	105	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX

Exhibit E Tables and Forms



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for	r Submissi	ion (If other is checked	please describe	e in space pro	vided.)						
New Pern	nit, Registra	ation or Authorization (Core Data Forn	n should be si	ubmitted	with the pr	ogram applic	ation.)			
Renewal	(Core Data	Form should be submit	ted with the rei	newal form)			Other				
2. Customer	Reference	Number (if issued)		Follow this lin	nk to sear	<u>ch</u> 3. I	3. Regulated Entity Reference Number (if issued)				
CN 6064023	45			for CN or RN Central Re			N 11228116				
0.1 000 1020											
SECTIO	N II:	Customer	Inform	<u>nation</u>							
4. General Cu	istomor li	oformation.	r reference	Data for Cu	stomor l	nform of	un lindatos	////-			10/6/2025
4. General Co	istomer ir	normation	5. Effective	Date for Cu	stomeri	mormauc	on Opuates	(mm/aa/	уууу)		10/6/2025
New Custon			pdate to Custor				nange in Regu		ity Owne	ership	
Change in L	egal Name	(Verifiable with the Tex	as Secretary of	State or Texa	is Comptr	oller of Pub	olic Accounts)				
		ubmitted here may l	•	utomatically	y based	on what is	s current an	d active	with th	ne Texas Seci	retary of State
(SOS) or Texa	s Comptro	oller of Public Accou	nts (CPA).								
6. Customer	Legal Nan	ne (If an individual, prii	nt last name firs	st: eg: Doe, Jo	ohn)		If new Co	ustomer, o	enter pre	evious Custom	er below:
Raider Aggrega	ites LLC.										
7. TX SOS/CP	A Filing N	umber	8. TX State 1	Tax ID (11 di	gits)		9. Fede	ral Tax II	D	10. DUNS	Number (if
806016326			32099991542	2			(9 digits))		applicable)	
							3209999	915			
						1			Π		
11. Type of C						Indi	vidual		Partne	rship: 🗌 Gen	neral Limited
Government: [City 🔲	County Federal	Local 🗌 State	Other		Sole	e Proprietorsh	nip	Otl	her:	
12. Number	of Employ	rees					13. Ind	epender	ntly Ow	ned and Ope	erated?
☑ 0-20 □	21-100 [101-250 251-	500 🗌 501 a	and higher			Yes	[□ No		
14. Customer	r Role (Pro	posed or Actual) – as i	t relates to the I	Regulated En	tity listed	on this for	n. Please che	ck one of	the follo	wing	
Owner		Operator	Ow	ner & Operat	tor		Г	7 Othori			
Occupation	al Licensee	Responsible Par	ty 🔲 V	/CP/BSA Appl	licant		L	Other:			
15. Mailing	1221 Hig	hway 72									
Address:											
	City	Three Rivers		State	TX	ZIP	78071			ZIP + 4	2609
16. Country I	Mailing In	formation (if outside	USA)	1	:	17. E-Mail	Address (if	applicabl	e)	I	

TCEQ-10400 (11/22) Page 1 of 3

(361) 449-6979							()	-		
ECTION III:	Regul	ated Fnt	ity Infori	mation	<u> </u>					
21. General Regulated Er						pplica	tion is also	required.)		
New Regulated Entity	Update to	o Regulated Entity	Name Update	e to Regulated	Entity I	nform	ation			
The Regulated Entity Nai	me suhmitti	ed may he unda	ted in order to m	eet TCFO Co	re Dati	a Stai	ndards (ri	emoval of a	organizatio	nal endinas such
as Inc, LP, or LLC).	ne submeet	ca may ac apaa	icu, iii oruci io iii	000 7014 00		<i>a</i>		emovar of c	n gamzatio	ur cugs suc
22. Regulated Entity Nan	ne (Enter nan	ne of the site wher	e the regulated action	on is taking pl	ace.)					
S Jolander Ranch										
23. Street Address of										
the Regulated Entity:										
(No PO Boxes)	City		State		ZIP				ZIP + 4	
24. County										
	1	If no Stre	et Address is prov	rided, fields	25-28 a	are re	quired.			
25. Description to	US 281 S, T	urn west at whitse	ett Take CR 421 SSW	2.2 mi, RT 0.5	5 mi on	Calich	ie Rd, LT fo	or 0.67 mi, R1	for 0.48 mi.	. Enter through rand
Physical Location:	gate Whits	ett 78075								
26. Nearest City							State		Ne	arest ZIP Code
Whisett							TX		780)75
Latitude/Longitude are r	equired and	d may be added,	/updated to meet	TCEQ Core	Data Si	tanda	ırds. (Ged	coding of t	the Physica	l Address may be
used to supply coordinat	es where no	one have been p	rovided or to gair	n accuracy).						
27. Latitude (N) In Decim	al:	28.625226		28. L	ongitu	ide (V	V) In Deci	imal:	-98.3122	255
Degrees	Minutes		Seconds	Degr	ees		ı	Minutes		Seconds
29. Primary SIC Code	30	. Secondary SIC	Code	31. Prima	-	CS Co	de	32. Sec	ondary NA	ICS Code
(4 digits)	(4	digits)		(5 or 6 dig	its)			(5 or 6 d	igits)	
1442				212321						
33. What is the Primary	Business of	this entity? (De	o not repeat the SIC	or NAICS desc	ription.))				
Caliche mining for road base										
24 Mailie	6217 Hwy	/ 281 PO Box 383								
34. Mailing										
Address:	City	Three Rivers	State	Тх	Z	IP.	78071		ZIP + 4	
35. E-Mail Address:	901	transportation@g	mail.com				1			
36. Telephone Number			37. Extension o	r Code		38. F	ax Numb	er (if applica	able)	
(361)449-6979						() -			
						•	•			

19. Extension or Code

20. Fax Number (if applicable)

18. Telephone Number

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	Districts	Edwards Aquifer		Emissions Inventory Air	☐ Industrial Hazardous Was
17-10-17-18-18-18-18-18-18-18-18-18-18-18-18-18-	Districts	Edwards Aquiler		J Ellissions inventory All	Industrial nazardous was
Municipal Solid W	√aste	OSSF		Petroleum Storage Tank	☐ PWS
Sludge	Storm Water	Title V Air		Tires	Used Oil
☐ Voluntary Cleanu	p 🔲 Wastewater	☐ Wastewater Agri	culture	Water Rights	Other:
2. Telephone Num	ber 43. Ext./Code	44. Fax Number	45. E-Mail	Address	
210) 326-6991		() -	evondran@	atei97.com	
ECTION V By my signature belo	w. I certify, to the best of my ehalf of the entity specified in Alpha Terra Engineering Inc.	Signature knowledge, that the informations	ation provided in t	his form is true and comple	
ECTION V By my signature below this form on b	ow, I certify, to the best of my ehalf of the entity specified in	Signature knowledge, that the informations	ation provided in t required for the u	his form is true and comple pdates to the ID numbers id	entified in field 39.



Texas Commission on Environmental Quality Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

The following checklist has been developed to help the Texas Commission Environmental Quality (TCEQ), Air Permits Division (APD) confirm that the permanent rock or concrete crusher meets the standard permit requirements. Please read all questions and check "YES," "NO," or "N/A" or give specific information for the facility. If the permanent rock or concrete crusher plant does not meet all conditions of this standard permit, it will not be allowed to operate under the standard permit and must apply for a case-by-case preconstruction permit as required under Title 30 Texas Administrative Code § 116.111 (30 TAC § 116.111).

Please Che	ck The Type of Facility: Rock Crusher Concrete	Crusher
CONDITIO	ON NUMBER AND DESCRIPTION	
(1)(B)	If crushing concrete, will the concrete crushing facility be operated at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship at the time this application is filed?	☐ YES☐ NO☑ N/A
	(The measurement of distance shall be taken from the point on the concrete crushing facility that is nearest to the residence, school, or place of worship toward the point on the building in use as a residence, school, or place of worship that is nearest the concrete crushing facility.)	
(1)(C)(ii)	In lieu of meeting the distance requirements of (1)(B), will the structure(s) within 440 yards of the concrete crushing facilities be occupied or used solely by the owner of the facility or the owner of the property upon which the facility is located?	☐ YES ☐ NO 🗹 N/A
(1)(D)	In lieu of meeting the distance requirements in (1)(B), will all the following occur:	
(1)(D)(i)	Will this plant be engaged in crushing concrete and other materials resulting from the demolition of a structure on this site and will the concrete and other materials being crushed be used primarily at this site?	☐ YES ☐ NO 🗹 N/A
(1)(D)(ii)	Will this plant operate onsite for one period of 180 calendar days or less?	☐ YES ☐ NO 🗹 N/A
(1)(D)(iii)	Will all applicable conditions stated in commission rules, including operating conditions be met?	☐ YES ☐ NO 🗹 N/A
(1)(D)(iv)	Will the plant be located in a county with a population of 2.4 million or more persons, or in a county adjacent to such a county?	☐ YES ☐ NO 🗹 N/A
(1)(E)	Do you intend to apply for an authorization under Texas Health and Safety Code (THSC) § 382.0518, Preconstruction Permit, for any other crushing facility to be located at the same site within 12 months from the date of this authorization?	☐ YES ☑ NO ☐ N/A



Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

Please Check The Type of Facility:		
	Have you withdrawn, within the previous 12 months, an application for authorization of a crushing facility under (THSC) § 382.0518, Preconstruction Permit, at this site?	☐ YES ☑ NO ☐ N/A
(1)(G)	Are the current registration form PI-1S entitled, "Registration for an Air Standard Permit", Table 17 and supporting information attached or mailed to the TCEQ, including Table 29 (if applicable), control devices and methods explanation, process flow diagram, process description, plot plan, and area map?	YES NO N/A
	Is the company's compliance history rating poor?	☐ YES ✓ NO ☐ N/A
(1)(H)	Has construction and/or operation begun on the facility?	☐ YES ✓ NO ☐ N/A
	Is there a non operational crusher stored onsite?	☐ YES ☑ NO ☐ N/A
(1)(I)	In accordance with 30 TAC § 116.614, Standard Permit Fees, was a \$900 fee sent to TCEQ Revenue Section?	YES NO N/A
(1)(J)	Will all facilities associated with this application for a standard permit comply with the conditions of Title 40 Code of Federal Regulations (40 CFR) Part 60, Subpart A, General Provisions and Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants?	✓ YES ☐ NO ☐ N/A
(1)(K)	Will these crushing facilities only process nonmetallic minerals or a combination of nonmetallic minerals as described in 40 CFR Part 60, Subpart OOO?	✓ YES □ NO □ N/A
(1)(L)	Is 30 TAC Chapter 101, Subchapter H, Division 3, Mass Emissions Cap and Trade Program; or 30 TAC Chapter 117, Control of Air Pollution from Nitrogen Compounds applicable to this plant?	☐ YES ☐ NO 🗹 N/A
(1)(M)	Will written records be kept for a rolling 24-month period at the site and made available at the request of any personnel from the TCEQ or any air pollution control program having jurisdiction?	✓ YES □ NO □ N/A
	Will these written records be maintained onsite to show daily hourly operations and hourly throughput; road and work area cleaning and dust suppression logs; and stockpile dust suppression logs?	YES NO N/A



Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

Please Cho	eck The Type of Facility: Rock Crusher Concrete C	Crusher
CONDITI	ON NUMBER AND DESCRIPTION (continued)	
(1)(N)	Will this crushing operation and related activities comply with applicable requirements of 30 TAC Chapter 101, Subchapter F, Emission Events and Scheduled Maintenance, Startup, and Shutdown Activities?	✓ YES □ NO □ N/A
(1)(P)	Have maintenance emissions been authorized? (Maintenance emissions are not included in this permit and must be approved under separate authorization.)	☐ YES 🗹 NO ☐ N/A
	Have start-up and shutdown emissions been authorized? (Start-up and shutdown emissions that will exceed those expected during production operations must be approved under separate authorization.)	☐ YES ✓ NO ☐ N/A
	Will start-up and shutdown emissions exceed those expected during production operations?	☐ YES ✓ NO ☐ N/A
(1)(Q)	Do you intend to authorize any facilities located at the same site as this rock crusher, by 30 TAC Chapter 106, Subchapter E, Aggregate and Pavement or 30 TAC § 106.512, Stationary Engines and Turbines?	☐ YES 🗹 NO ☐ N/A
PUBLIC N	NOTICE REQUIREMENTS - Detailed Public Notice Information will be Determination of Technical Completeness	
(2)(B)(i)	Will public notice be published no later than 30 days after the application is determined to be technically complete?	YES NO N/A
OPERATI	IONAL REQUIREMENTS	
(3)(A)	Will the primary crusher throughput exceed 200 tons per hour?	☐ YES ✓ NO ☐ N/A
(3)(B)	Will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located less than 200 feet from the nearest property line, as measured from the point on the facility nearest the property line?	☐ YES ✓ NO ☐ N/A
(3)(C)	At the time this application is filed, will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship?	✓ YES ☐ NO ☐ N/A
	(Distance shall be measured from the point on the facility nearest the residence, school, or place of worship to the point on the residence, school, or place of worship nearest the facility).	



Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

Please Check The Type of Facility:							
OPERAT	TIONAL REQUIREMENTS (continued)						
(3)(D)	Will the crushing facilities (not including associated sources) be located at least 550 feet from any other rock crusher, concrete crusher, concrete batch plant, or hot mix asphalt plant?	☐ YES ☐ NO 🗹 N/A					
	Will the crusher operate at the same time as any other rock crusher, concrete batch plant, or hot mix asphalt plant within a 550 feet radius?	☐ YES ☐ NO 🗹 N/A					
(3)(E)	Will all associated sources, including but not limited to work areas, stockpiles, and roads (except for incidental traffic and the entrance and exit to the site), be located at least 100 ft. from the property line?	✓ YES ☐ NO ☐ N/A					
(3)(F)	Will this crushing operation consist of any additional facilities other than one primary crusher, one secondary crusher, one vibrating grizzly, two screens, any conveyors, and one internal combustion engine (or combination of engines) of no more than 1,000 total horsepower?	☐ YES ☑ NO ☐ N/A					
	(Equipment that is not a source of emissions does not require authorization.)						
(3)(G)	Will any of the crushers, associated facilities, and/or associated sources (excluding stockpiles) exceed 2,640 operating hours in any rolling 12-month period?	☐ YES ☑ NO ☐ N/A					
(3)(H)	Will any of the rock crusher/ concrete crusher or associated facilities operate during any time between one hour after official sunset to one hour before official sunrise?	☐ YES ☑ NO ☐ N/A					
(3)(I)	Will all crushers be equipped with runtime meters and will the runtime meters be operating during crushing operations?	YES NO N/A					
(3)(J)	Will permanently mounted spray bars be installed at the inlet and outlet of all crushers, at all shaker screens, and at all material transfer points and used as necessary to maintain compliance with all TCEQ rules and regulations?	✓ YES □ NO □ N/A					
(3)(K)	Will opacity of emissions from any transfer point on belt conveyors or any screen exceed 10 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES ✓ NO ☐ N/A					
	Will opacity of emissions from any crusher exceed 15 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES ✓ NO ☐ N/A					
(3)(L)	Will visible emissions leave the property for more than 30 seconds in duration in any six-minute period from the crusher(s), associated facilities, associated sources, and in-plant roads associated with the plant as determined using EPA Test Method 22?	☐ YES ☑ NO ☐ N/A					



Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

Please Che	Please Check The Type of Facility:						
OPERATI	ONAL REQUIREMENTS (continued)						
(3)(M)	Will all in-plant roads and active work are operation of the crusher, associated faciliti treated at all times with any of the following	es, and associated sources be					
(3)(M)(i)	Covered with a material such as, but not littire chips?	mited to roofing shingles or	☐ YES ☑ NO ☐ N/A				
(3)(M)(ii)	Dust-suppressant chemicals?	✓ YES ☐ NO ☐ N/A					
(3)(M)(iii)	Water?		✓ YES ☐ NO ☐ N/A				
(3)(M)(iv)	Paved with a cohesive hard surface that is n	maintained intact and cleaned?	☐ YES 🗹 NO ☐ N/A				
(3)(N)	Will all stockpiles be sprinkled with water or covered, as necessary, to minimize dust		YES NO N/A				
(3)(O)	Will raw material and product stockpile he	eights exceed 45 ft?	☐ YES ✓ NO ☐ N/A				
(3)(P)	Will the crusher be equipped with a weigh accurately determines the mass of material		YES NO N/A				
(3)(Q)	Will the crusher remain at least 440 yards school, or place of worship when moving t	•	YES NO N/A				
		Print Form	Reset Form				



Texas Commission on Environment Quality

Table 17 Rock Crushers

Does the facility operate at night?									
Does the facility operate at night?	Please Complete the Follo	wing							
Maximum Plant Production Rates: Primary Crusher Type: Trakpactor 550 200 tons/hour 520000 tons/hour Secondary Crusher(s) Type: tons/hour tons/hour Tertiary Crusher(s) Type: tons/hour tons/hour Tertiary Crusher(s) Type: tons/hour tons/hour The Following Pieces of Equipment will be Controlled as Shown:	Maximum operating schedu	ıle: 10	hour	s/day	5	da	ys/week	52	weeks/year
⊠ Primary Crusher Type: Trakpactor 550 200 tons/hour 520000 tons/hour □ Secondary Crusher(s) Type: tons/hour tons/hour tons/hour □ Tertiary Crusher(s) Type: tons/hour tons/hour The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter of Baghouse □ Other: □ Sulter Spray □ Sulter □ Spray □ Sulter Spray □ Sulter Spray □ Sulter Spray □ Spray □ Sulter Spray □ Spray	Does the facility operate at	night?						•	☐ YES 🗵 NO
Secondary Crusher(s) Type: tons/hour tons/ Tertiary Crusher(s) Type: tons/hour tons/ The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None ⊠ Water Spray Suction to Baghouse Other: All Belt Transfer Points: None ⊠ Water Spray Suction to Baghouse Other: Inlet of all Crushers: None ⊠ Water Spray Suction to Baghouse Other: Outlet of all Crushers: None ⊠ Water Spray Suction to Baghouse Other: All Shaker Screens: None ⊠ Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None ⊠ Water Chemic	Maximum Plant Producti	on Rates:							
Trettiary Crusher(s) Type: tons/hour tons/ The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: Outlet of all Crushers: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Inlet of Baghouse Other: Other: Water Spray Suction to Baghouse Other: Other: Water Sprays are used, Other: Suction to Baghouse Other: Suction to Baghouse Other: Water Sprays are used, Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None	➤ Primary Crusher	Type: Tra	akpactor 550		200	tons/ho	ur 52000	00	tons/year
The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None Water Spray Suction to Baghouse Other: All Belt Transfer Points: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: Outlet of all Crushers: None Water Spray Suction to Baghouse Other: All Shaker Screens: None Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Secondary Crusher(s)	Type:				tons/hou	r		tons/year
Feed Hoppers:	Tertiary Crusher(s)	Type:				tons/hou	r		tons/year
Feed Hoppers:	The Following Pieces of E	quipment	will be Controlle	d as S	hown:		l .		-
All Belt Transfer Points: None	3		I —			Baghouse	Othe	r:	
Outlet of all Crushers: None	All Belt Transfer Points:	None None	➤ Water Spray		uction to	Baghouse	Othe	r:	
All Shaker Screens: None	Inlet of all Crushers:	None			uction to	Baghouse	Othe	r:	
If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: _ None _ X Water _ Chemic	Outlet of all Crushers:	None	■ Water Spray		uction to	Baghouse	Othe	r:	
Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: _ \Box None _ \X Water _ \Box Chemic	All Shaker Screens:	None			uction to	Baghouse	Othe	r:	
Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	If Water Sprays are used,	Provide t	he Following Data	a:					
Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls:	Water Flow Rate (gpm): 8	-19							
If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Water Pressure at the Nozz	le (psi): 2	00						
Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Number of Nozzles at each	location:	2-3						
Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: □ None ☒ Water □ Chemic	If baghouse is used, attach	a Table 11	"Fabric Filters."						
Stockpiles have the following controls: None Water Chemic									
In-plant roads will be: Daved and Vacuumed Daved and Swent Oiled	Stockpiles have the following controls: None Water Chemical								
In-plant loads will be. I aved and vacuumed I aved and 5 wept I oned									
Sprinkled with Water and/or Chemicals Other:									

PRINT FORM

RESET FORM

Texas Commission on Environmental Quality Table 29 Reciprocating Engines

I. Engine Data	I. Engine Data									
Manufacturer:	Manufacturer: Model No. Serial No. Manufact				ture Date:					
Scania	cania DC13 Tier 4f Unkown									
Rebuilds Date: No. of Cylinders: Compre				Compress	ion Ratio): I	EPN:			
		6			17.5:1			DC13 08	85A	
Application: X	Gas Compi	ression	Electric	Generati	on Re	frigeratio	n 🗌 En	nergency/	Stand by	
■ 4 Stroke Cycle										
➤ Diesel Nat	turally Asp	irated	Blower	/Pump So	cavenged	Turbo	Charged a	nd I.C.	X Turbo C	Charged
Intercooled		I.C. Wate	er Temperat	ture [Lean Bu	rn		Rich I	Burn	
Ignition/Injection	Timing:	Fixed:				Vari	able: It is v	ariable a	nd not publi	С
Manufacture Horse	power Rat	ing: 500			Proposed	Horsepo	wer Rating:	500		
			Di	ischarge	Parameter	s				
Stack Height (1			Diameter ((Feet)	Stack T	'emperat	ure (°F)	Exit	Velocity (FPS)
16 feet 9 inches		0.5 feet			900			150		
II. Fuel Data										
Type of Fuel:	Field Gas		andfill Gas			Natural	Gas 🔲 🛚	Digester C	Bas 🗵 Dies	sel
Fuel Consumption	(BTU/bhp-	hr): 2879	He	eating Va	lue: 19400	BTU/lb	Lowe	er Heating	g Value: 18	300 BTL
Sulfur Content (gra	ins/100 sct	f - weight	%): <1.7							
III. Emission Fa	ctors (Bef	ore Cont	rol)		ı		ı			
NO _X	CC)	SO	2	vo	C	Formalo	lehyde	PM	10
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.298 17.29	2.61	151.38	<0.002	<1	0.1417	8.22	<0.001	<0.1	0.0149	0.86
Source of Emission	Factors:	Manı Manı	ıfacturer Da	ata	AP-42 ×	Other (sp	ecify): Stat	e of Calif	ornia, Title	13
IV. Emission Fa	ctors (Pos	t Control	l)		1		1			
NO _X	CC)	SO	2	VO	C	Formalo	lehyde	PM	10
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.142 8.22	0.149	8.65		<1	0.05597	3.46	<0.001	<0.1	0.0149	0.86
Method of Emissio			•		an Operatio			djustmen	ıt	
Stratified Charg			C Catalyst		her (Specify					
Note: Must submit		•		ntrol info	ormation the	at demons	strates cont	rol efficie		
Is Formaldehyde included in the VOCs? ☐ Yes ☒ No										
V. Federal and State Standards (Check all that apply)										
NSPS JJJJ ☐ MACT ZZZZ ☒ NSPS IIII ☐ Title 30 Chapter 117 - List County:										
VI. Additional Information										
1. Submit a copy										.1.
2. Submit a typical percent of cons	_	anarysis, i	meruaing si	unur cont	ent and nea	ung vaiu	e. For gase	ous ruers,	provide inc	ле
3. Submit descrip		fuel ratio	control sys	tem (man	ufacturer ir	nformatio	n is accepta	ıble).		

Reset Form

Print Form

Texas Commission on Environmental Quality Air Quality Standard Permits General Requirements Checklist Title 30 Texas Administrative Code §§116.610-116.615

Check the most appropriate answer and include any additional information in the spaces provided. If additional space is needed, please include an extra page and reference the rule number. The SP forms, tables, checklists, and guidance documents are available from the TCEQ, Air Permits Division web site at: www.tceq.texas.gov/permitting/air/nav/standard.html.

Most Standard Permits require registration with the commission's Office of Permitting, Remediation, and Registration in Austin. The facilities and/or changes to facilities can be registered by completing a Form PI-1S, "Registration for Air Standard Permit." This checklist should accompany the registration form to expedite any registration review.

CHECK THE MOST APPROPRIATE ANSWERS AND FILL IN THE REQUESTED INFORMATION							
Rule	Questions/Description	Response					
116.610(a)(1)	Are there net emissions increases associated with this registration?	X YES ☐ NO					
	If "YES," will net emission increases of air contaminants from the project, other than those for which a National Ambient Air Quality Standard (NAAQS) has been established, meet the emission limits of § 106.261 or § 106.262?	X YES NO					
	If "NO," does the specific standard permit exempt emissions from this limit?	☐ YES ☐ NO					
Attach emissions	summary and calculations:						
116.610(a)(3)	Do any of the Title 40 Code of Federal Regulations Part (CFR) 60, New Source Performance Standards apply to this registration?	X YES □ NO					
If "YES," list sub	parts:						
116.610 (a)(4)	Do any Hazardous Air Pollutant requirements apply to this registration?	☐ YES 🔀 NO					
If "YES," list sub	parts						
116.610 (a)(5)	Do any maximum achievable control technology (MACT) standards as listed under 40 CFR Part 63 or Chapter 113, Subchapter C (National Emissions Standard for Hazardous Air for Source Categories) apply to this registration?	YES NO					
If "YES," list sub	parts:						
116.610(a)(6)	Will additional emission allowances under Chapter 101, Subchapter H, Division 3, Emissions Banking and Trading, need to be obtained following this registration?	☐ YES ☒ NO					
116.611(a)(1-6)	Is the following documentation included with this registration:	X YES ☐ NO					
	Emissions calculations including the basis of the calculations?	X YES ☐ NO					
	Quantification of all emission increases and/or decreases associated with this project?	ĭ YES ☐ NO					
	Sufficient information demonstrating that this project does not trigger PSD or NNSR review?	X YES NO					
	Description of efforts to minimize collateral emissions increases associated with this project?	ĭ YES □ NO					
	Process descriptions including related processes?	X YES ☐ NO					
	Description of any equipment being installed?	X YES ☐ NO					

Texas Commission on Environmental Quality Air Quality Standard Permits General Requirements Checklist Title 30 Texas Administrative Code §§116.610-116.615

Rule	Questi	on/Description			Response		
116.614		Are the required fee and a copy of the check or money order provided with the application?					
116.615(1)	regulat	missions from the facility compions of the commission adopted at 382, and with the intent of the	ĭ YES ☐ NO				
116.615(2)	operati	u understand that all represent: ng procedures, and maximum e conditions upon which the fa	on	X YES ☐ NO			
116.615(3)	incorpo	understand that all changes a prated into the facility's permit §116.110 (relating to Applicab		ĭ YES □ NO			
List all related permit	numbers	s:					
116.615(9)617(e)(1)		l air pollution emission capture ined in good working order?	X YES NO				
116.615(10)	TCEQ,	Will the facility comply with all applicable rules and regulations of the TCEQ, the Texas Health and Safety Code, Chapter 382, and the Texas Clean Air Act?					

Save Form Reset Form Print Form

From: Ed vonDran <evondran@atei97.com>
Sent: Monday, November 10, 2025 12:39 PM

To: Andres Targa

Cc: Matt Wilmot; 90TRANSPORTATION@GMAIL.COM

Subject: 181766 398884 Raider Aggregates LLC

Attachments: Raider Aggregates Draft Build Optimized EvD 11-10-25 R1.pdf

Importance: High

Categories: GTG WCC

Good Day,

Please find attached the updated version of the Raider Aggregate application.

If you find any additional issues, please don't hesitate to contact me.

Ed von Dran, P.E.

President / Chief Engineer



architecture engineering environment

8626 Tesoro Dr., Suite 810 San Antonio, TX 78217 Phone (210) 930-2834 x 12 Cell (210) 326-6991 evondran@atei97.com

www.atei97.com

A Service Disabled Veteran Owned Small Business

Please consider whether it is necessary to print this e-mail



TBPE F-8920; Arch BR-1889

This message and any attachments are intended only for the use of the addressee and may contain information that is privileged and confidential. If the reader of the message is not the intended recipient or an authorized representative of the intended recipient, you are hereby notified that any dissemination of this communication is strictly prohibited. If you have received this communication in error, notify the sender immediately by return email and delete the message and any attachments from your system.

From: Andres Targa < Andres. Targa@tceq.texas.gov>

Sent: Tuesday, November 4, 2025 11:43 AM **To:** Ed vonDran <evondran@atei97.com>

Cc: Matt Wilmot <mwilmot@atei97.com>; 90TRANSPORTATION@GMAIL.COM

Subject: RE: Notice of Deficiency: 181766 398884 Raider Aggregates LLC

Good morning,

The referenced notice of deficiency's timeframe is 5 business days, so it is due by COB next Monday, November 10th, 2025.

Sincerely,

Andres Targa Mallona

Mechanical New Source Review Environmental Permit Specialist Air Permits Division Texas Commission on Environmental Quality

Mail Code: MC-163, PO Box 13087

Austin, Texas 78711-3087 Direct Line: (512) 239-6107



How are we doing? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey

From: Ed vonDran < evondran@atei97.com>
Sent: Tuesday, November 4, 2025 11:24 AM
To: Andres Targa < Andres. Targa@tceq.texas.gov>

Cc: Matt Wilmot <<u>mwilmot@atei97.com</u>>; <u>90TRANSPORTATION@GMAIL.COM</u>

Subject: RE: Notice of Deficiency: 181766 398884 Raider Aggregates LLC

Good day Andres,

We are on it! When does your 5 day time period expire by your count?

Ed von Dran, P.E.

President / Chief Engineer

ALPHA

TERRA

architecture engineering environment 8626 Tesoro Dr., Suite 810 San Antonio, TX 78217 Phone (210) 930-2834 x 12 Cell (210) 326-6991 evondran@atei97.com

www.atei97.com

A Service Disabled Veteran Owned Small Business

Please consider whether it is necessary to print this e-mail



TBPE F-8920; Arch BR-1889

This message and any attachments are intended only for the use of the addressee and may contain information that is privileged and confidential. If the reader of the message is not the intended recipient or an authorized representative of the intended recipient, you are hereby notified that any dissemination of this communication is strictly prohibited. If you have received this communication in error, notify the sender immediately by return email and delete the message and any attachments from your system.

From: Andres Targa < Andres. Targa@tceq.texas.gov >

Sent: Tuesday, November 4, 2025 9:56 AM **To:** Ed vonDran <evondran@atei97.com>

Cc: Matt Wilmot <mwilmot@atei97.com>; 90TRANSPORTATION@GMAIL.COM

Subject: Notice of Deficiency: 181766 398884 Raider Aggregates LLC

Some people who received this message don't often get email from andres.targa@tceq.texas.gov. Learn why this is important

Dear Mr. Muniz:

Upon evaluation of the above-referenced application, we have determined that your application is deficient and Raider Aggregates Limited Liability Company must provide additional information to ensure that the requirements for obtaining a permit are met. Please furnish the following information within 5 days:

General Requirements

- Please provide an updated Core Data Form with accurate latitude and longitude coordinates that represent the exact location of the proposed facility. There is a discrepancy between current coordinates and the area map provided.
- Please complete the following form along with updated representations: <u>TCEQ</u> <u>Form 20335</u>.
- There appears to be two residences inside the proposed property boundaries. Please confirm both houses are currently not occupied by residents.

Air Quality Standard Permit Checklist for Permanent Rock and Concrete Crushers

• Please clarify your response "Yes" on condition (1)(B) from Section I General Requirements. Based on the type of facility that is being proposed, this Checklist is only marked as "rock crusher" rather than "concrete crusher". If concrete will also be crushed at the site, please provide an updated Checklist with the correct type of facility marked at the top of each page; additionally, if both concrete and rock are being crushed, please make sure that you are complying with the requirements applicable to both types of facilities.

- Based on your updated representations from above, please explain your response for condition (1)(c)(ii).
- Please explain how Maintenance Startup and Shutdown Activities will be authorized based on your responses to condition (1)(P).

Emission Point Numbers (EPNs)

- Please note "unpaved roads" are not Emission Point Numbers; EPNs originate from sources, which refer to point(s) of origin of air contaminants, usually from stationary sources such as buildings, structures, facility, or any installation that emits or may emit any air pollutant subject to regulation. EPNs for rock crushers include one primary crusher, one secondary crusher, one vibrating grizzly, two screens, any conveyors, and one internal combustion engine (or combination of engines) of no more than 1,000 total horsepower. Please update your proposed EPNs based on this information.
- Additionally, please ensure the same number of EPNs is being represented consistently and match across supporting permit documents. For example, your emissions calculations contain 4 EPNs, whereas your process description contains 5 EPNs and discusses 11 processes throughout the description.

Area Map

- Please provide a more detailed area map along with the updated application; this
 requires an up-to-date area map that clearly depicts property boundaries, a north
 arrow, accurate scale, and includes the distance from the facility to the nearest
 residence, school, and/or place of worship.
- Additionally, please make sure to include a 3,000-foot radius that extends from the property boundary line.
- Please clarify why the proposed location for "Area 2" extends beyond the property boundary.

Plot Plan

- Please provide a detailed plot plan that clearly shows an accurate scale, a north arrow, all property lines, emission points, buildings, tanks, process vessels, other process equipment, and two benchmark locations (benchmark locations should represent accurate stationary corner property boundaries or site entrances). The drawing should be of a size that results in a drawing that is easy to read. Labeling of and identification of emission points, buildings, tanks, etc., must be consistent with other representations in the permit application.
- Please include setback distances showing compliance with standard permit requirements; additionally, based on your current area map: please confirm that if equipment is moved within property boundaries, it will continue to comply with setback distance requirements.

Flow Diagram & Process Description

 Please provide a Process Flow Diagram and Process Description to verify all technical information regarding the affected facility. The process flow diagram should be sufficiently descriptive so the reviewer can determine the raw materials to be used in the process; all major processing steps and major equipment items; individual emission points associated with each process step; the location and identification of all emission abatement devices; and the location and identification of all waste streams (including wastewater streams that may have associated air emissions). Block flow diagrams generally are not sufficient except for very simple facilities such as boilers. Alternate material flows and changes in routing of emissions during periods of planned MSS should be depicted as well as any alternate emission control devices that will be used during these periods.

- To assure that all potential sources of air contaminants are identified and to ensure that the emissions are characterized properly, a detailed process description is requested. Each step in each process should be discussed. The process description should include how materials are received (in bulk, cans, drums, totes, etc.), where they are stored, how they are introduced into the process (mixing, blending, pouring, spraying, brushing, pneumatic conveying, etc.). The description should also discuss the process equipment used, process rates, emission reduction techniques, emission control devices such as baghouses. Finally, the discussion should cover parts and equipment preparation during and between process steps and end of process operations such as product testing, equipment cleanup, and waste storage and disposal.
- The flow diagram needs to be as detailed as possible to match the process description; please refer to the examples attached for reference.

After receipt of all the additional information, we will continue the review of your application. If the information furnished in response to this notice results in the need for further clarification or additional information, we will notify you. Please note that the applicant Raider Aggregates Limited Liability Company is required to furnish all information to demonstrate that the facility or source will comply with all applicable federal and state rules and statutes.

Failure to submit all of the requested information within 5 days of the date of this notification may result in a recommendation to void your application.

Sincerely,

Andres Targa Mallona

Mechanical New Source Review Environmental Permit Specialist Air Permits Division Texas Commission on Environmental Quality Mail Code: MC-163, PO Box 13087

Austin, Texas 78711-3087 Direct Line: (512) 239-6107



How are we doing? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey



November 7, 2025

Texas Commission on Environmental Quality Air Permits Initial Review Team, MC 161 12100 Park 35 Circle Building C, Third Floor Austin, Texas 78753

Subject: Claim of a Standard Permit under 30 TAC §116.611 to operate a Caliche Pit Facility

Reference: Raider Aggregates Limited Liability Company

To whom it may concern:

Please find attached supporting documentation for a Standard Permit application for Raider Aggregates, LLC. registering a Caliche Pit facility located off of Co Rd 421 in Whitsett Texas, 78075.

INTRODUCTION

RAIDER AGGREGATES, LLC is applying to authorize a Caliche Pit facility located in Live Oak County. Caliche based aggregates will be extracted from the site, crushed via impact crusher, and hauled away via transport truck. Facility layout and operational parameters are detailed in attached appendices.

New Source Review (NSR) Authorization

RAIDER AGGREGATES, LLC is proposing to authorize the Caliche Pit facility under 30 Texas Administrative Code (TAC) §116.611. In addition to the Caliche Pit facility meeting the claimed Standard Permit, the facility meets the general requirements of 30 TAC §116.611 (posted in STEERS with this supporting data).

RAIDER AGGREGATES, LLC is submitting this application for a Standard Air Permit to authorize operations at a proposed caliche pit located off of Co Rd 421 near Whitsett Texas. The site will be used for the extraction and processing of caliche material, which is commonly utilized in road base, construction, and other infrastructure projects.

The facility will involve activities such as excavation, stockpiling, material handling, and loading of caliche into transport trucks. Emission sources will primarily include fugitive dust from material handling and vehicle traffic, as well as emissions from any associated equipment such as screens or conveyors. Appropriate dust suppression methods, including water sprays and best management practices, will be employed to minimize particulate emissions and ensure compliance with applicable Texas Commission on Environmental Quality (TCEQ) regulations.

This application includes a detailed site layout, equipment specifications, emission calculations, and a demonstration of compliance with all applicable air quality standards under the TCEQ's Standard Permit for Rock and Concrete Crushers.

PROCESS DESCRIPTION AND CONTROL MEASURES

EPN 1 – Scania DC13 Diesel Engine Exhaust

The Trakpactor 550 is powered by a Scania DC13 Tier 4 Final diesel engine rated at 494 horsepower. This engine drives the crusher and associated hydraulic systems. Emissions from this source include nitrogen oxides (NOx), carbon monoxide (CO), volatile organic compounds (VOC), sulfur dioxide (SO₂), and particulate matter (PM). The unit is certified to meet Tier 4 Final standards under 40 CFR 60 Subpart IIII for nonroad compression-ignition engines and is equipped with selective catalytic reduction (SCR) and diesel oxidation catalyst (DOC) controls.





No MACT Subpart ZZZZ requirements apply because this is a portable engine that does not remain in one location for more than twelve months.

EPN 2 – Primary Feed Hopper

Material is delivered to the crusher via a steel hopper that receives caliche or aggregate from a front-end loader or excavator. The drop from the loader bucket into the hopper is a potential source of particulate emissions. Fugitive dust (PM₁₀ and PM_{2.5}) is controlled by a water spray bar positioned along the hopper lip and by minimizing drop height during loading operations. The hopper is designed with abrasion-resistant liners to reduce material buildup and associated dust generation.

EPN 3 - Vibrating Grizzly Feeder

The vibrating grizzly feeder transfers material from the hopper into the crusher while removing fine material prior to crushing. This process can generate minor dust emissions during agitation and material drop. A spray system positioned above the feeder maintains material moisture and prevents visible emissions. The feeder is subject to 40 CFR 60 Subpart OOO requirements for nonmetallic mineral processing plants.

EPN 4 – Impact Crusher (Trakpactor 550)

The main emission source at the site is the impact crusher itself. Material enters the crusher chamber and is broken down by a twin-apron, four-bar impactor. Crushing releases fine particulate matter (PM₁₀ and PM_{2.5}). These emissions are controlled by multiple atomizing spray nozzles mounted inside the crusher housing, flexible skirting around transfer points, and an optional enclosure. The unit operates under NSPS Subpart OOO for performance and opacity limits.

EPN 5 - Crusher Discharge Conveyor #1

After crushing, material is transferred from the crusher onto the first discharge conveyor. Dust emissions occur as material drops onto the belt and as it travels along the conveyor. Control measures include full-length belt skirting, covered transfer points, and water sprays installed at both loading and discharge ends of the belt. The conveyor system complies with Subpart OOO and AP-42 Section 11.19.2 emission guidance.

EPN 6 – Vibratory Screen #1 (Primary)

The first screening unit separates material by size into coarse and fine fractions. Screening activity generates fine dust from vibration and material agitation. Water spray bars located above each deck reduce airborne particulate. The screen is covered under 40 CFR 60 Subpart OOO and is limited to 10% opacity per NSPS standards. Maintenance logs are kept for each spray system inspection.

EPN 7 – Vibratory Screen #2 (Secondary/Fines)

The secondary screening deck further classifies material into finer product sizes. Emissions consist of PM₁₀ and PM_{2.5} from material agitation. Control measures mirror those of the primary screen, including active spray bars and belt skirting at feed and discharge points. All equipment is operated and maintained to ensure compliance with opacity limits.

EPN 8 – Transfer Conveyor #2

This conveyor moves screened material from the first to the second screen or to a different processing line. The main emissions occur from material falling onto and off the conveyor. These are minimized by skirting and misting systems that apply water directly at transfer points. Periodic inspections ensure adequate belt tension and spray operation.

EPN 9 – Final Product Conveyor #3







The final conveyor discharges finished crushed and screened product to the stockpile. Water spray bars positioned at the head pulley provide continuous wet suppression during active operation. Belt covers or partial enclosures may be installed to limit windblown dust. This point represents the last material transfer before storage.

EPN 10 - Stockpile Drop Point / Loading Area

Crushed material exits the conveyor and falls onto the finished product stockpile. This drop can generate dust emissions, particularly during dry conditions. Stockpile dust is controlled with continuous or intermittent spray systems at discharge points and with surface wetting. Stockpiles are built with low slope angles and may be stabilized using crusting agents or covered if inactive. Windbreaks can be used for added control.

EPN 11 – Pit Excavation and Loading Operations

The pit area generates dust during excavation, loading, and hauling of raw caliche or aggregate material to the crusher. Emissions are managed through watering disturbed areas, minimizing drop heights when loading trucks, and limiting disturbed acreage. Completed pit sections are stabilized when inactive to minimize dust emissions.

Non-EPN Fugitive Emission Sources – Unpaved Roads

Per TCEQ guidance, fugitive emissions from unpaved haul and access roads are not listed as individual EPNs because they are not considered discrete process emission points. These emissions are instead categorized as site-wide fugitive sources and addressed through best management practices. Dust from unpaved roads is controlled through the use of water trucks, speed limits of 15 mph, and, when necessary, environmentally safe dust suppressants. Watering frequency is adjusted according to traffic levels and weather conditions. Records of road watering and control maintenance are retained for compliance documentation but do not require individual EPN designation.

Control System Description (Not an EPN)

The water spray system serves as the primary control mechanism for dust suppression across all emission points. The system operates at 3 bar pressure and 24 liters per minute, feeding multiple atomizing nozzles positioned over the crusher, screens, conveyors, and transfer points. The water system includes frost protection, pump, and manifold assemblies. This system ensures compliance with visible emission and particulate standards under the TCEQ Standard Permit.

Recordkeeping and Monitoring

Daily logs are maintained for all watering events, suppressant applications, and equipment maintenance activities. Each emission point is visually inspected per shift to confirm effective dust control. Any failures in control systems are corrected immediately, and corrective actions are documented. All records are retained onsite for a rolling 24-month period and made available to the TCEQ upon request.

MAINTENANCE, START-UP, AND SHUTDOWN

Startup and shutdown emissions for the Powerscreen Trakpactor 550 crusher with Scania DC13 Tier 4 Final engine will not exceed emissions during normal production operations. The engine is equipped with SCR, EGR, DOC, and AMOX emission controls that function during all operating modes including startup and shutdown. Startup procedure involves:

1. Engine warm-up period (approximately 5-10 minutes)





- 2. Gradual increase to operating temperature
- 3. SCR system reaches operational temperature
- 4. No crushing activity occurs until engine reaches normal operating parameters

Engine will be shut off during maintenance.

Shutdown is controlled and emissions during shutdown are lower than production emissions as the engine idles down before shutoff.

No separate MSS authorization is required because emissions during maintenance, start-up, and shutdown will not exceed those of normal operations.

EMISSIONS CALCULATION METHODOLOGY

This section presents documentation of emissions calculations for the RAIDER AGGREGATES Caliche Pit facility. The facility has several pints of emissions as listed above including engine emissions from trucks, front end loaders, excavators, and the rock crusher. All calculations represent worst-case with respect to potential emissions.

Should you have any questions regarding this submittal, please contact me at (210) 326-6991.

Respectfully submitted,

Alpha Terra Engineering, Inc.

Harold E. von Dran, Jr., PE

Environmental Engineer (TX 92737 / F-8920)

Attachments:

1) Exhibit A – Emissions Calculations

2) Exhibit B – Facility Maps

3) Exhibit C – Process Flow Diagram and Description

4) Exhibit D – Crusher Info

5) Exhibit E – Tables and Forms






Exhibit A Emission Calculations


			AP-42 EF (lb/ton)	AP-42 EF (lb/hp-	-	*Engine Exhaust AP	-	
EPN#	EPN	Description	controlled1	hr) ¹	AP-42 EF (lb/VMT) ¹	42 ²	EF (g/kWh)	
EPN1	Engine Exhaust	Rock Crushing Activities		Various		Nox	0.4	
EPN2	Primary Feed Hopper	Material drop	0.002			CO	3.5	
EPN3	Vibrating Grizzly Feeder	Screen/feeder	0.002			NMHC	0.19	
EPN4	Impact Crusher	Crusher	0.0054			PM10	0.02	
EPN5	Conveyor #1	Conveyor transfer	0.0015					
						**Unpaved Roads	EF (Ib/VMT)	80%
EPN6	Primary Screen	Screen	0.0022			AP-42	uncontrolled	Controlled
EPN7	Conveyor #2	Conveyor transfer	0.0015			PM10	1.5	0.3
EPN8	Secondary Screen	Screen	0.0022			PM2.5	0.15	0.03
EPN9	Conveyor #3	Conveyor transfer	0.0015			TSP	4.90	0.98
EPN10	Stockpile Drop Points	Stockpile loading	0.0025					
EPN11	Pit Excavation & Loading	Pit/loading	0.002					
FUG (Non EPN)	Unpaved Roads	Roads that are unpaved			Various**			
hours operating per year		2640	0					
Facility Coordinates	Northing	28.62523	Easting	-98.312255	Elevation	214		
		1 TCEQ Technical Guidance a	nnd U.S. EPA AP-42, S	Section 11.19.2				
		From the State of California	a Resources Board					

EPN No	EPN Type	Description	NO _x	CO	NMHC	PM ₁₀	
1	Engine Exhaust	Exhaust from Crusher Generator or Engine	0.35	3.04	0.16	0.02	
2	Primary Feed Hopper	Material drop	0.00	0.00	0.00	0.53	
3	Vibrating Grizzly Feeder	Screen/feeder	0.00	0.00	0.00	0.53	
4	Impact Crusher	Crusher	0.00	0.00	0.00	1.43	
5	Conveyor #1	Conveyor transfer	0.00	0.00	0.00	0.40	
6	Primary Screen	Screen	0.00	0.00	0.00	0.58	
7	Conveyor #2	Conveyor transfer	0.00	0.00	0.00	0.40	
8	Secondary Screen	Screen	0.00	0.00	0.00	0.58	
9	Conveyor #3	Conveyor transfer	0.00	0.00	0.00	0.40	
10	Stockpile Drop Points	Stockpile loading	0.00	0.00	0.00	0.66	Total EPN Emissions (tons/yr)
11	Pit Excavation & Loading	Pit/loading	0.00	0.00	0.00	0.53	6.04
FUG	Unpaved Roads	Particulate Generated by use of Unpaved Roads	0.00	0.00	0.00	15.84	Total Emissions (tons/yr)
			0.35	3.04	0.16	21.88	25.42
							Uncontrolled EPN + 80%
	Conditions:						Controlled FUG*
		d on permit data and technical documentation for t ear) for your scenario— ~10 hours per day, 5 days p					ultra-low sulfur diesel
	PM10 Values for Crushing and suppression or similar contro	d Screening based on a Powerscreen Trakpactor 55 Is are in place.	0 operating at 20	00 tons/hour,	10 hours/day	, 5 days/we	eek assuming wet
	Unpaved Roads PM10 assume	es best practice dust mitigation (80%) and 0.25 mile	es of unpaved roa	ads assuming	transporting t	the maximu	um of 1716000 tons a year.
	Throughput (tons/hr) x EF (lb.	/ton) = lb/hr*1ton/2000 lb = tons/hr x2640 hr/yr =	tons/year				

PM10 Calculations											
Throughput (tons/hr) x EF	(lb/ton) =(lb/hr)/ (1to	n/2000 lb) = tons/h	r x 2640 hr/yr	= tons/year							
	Throughput (Tons/hr)	Emission Factor (lb/ton)	One Ton (lbs)	Operaing Time	PM10	Formulas					
	(1013/11)	(ib/ tori)	One for (ibs)	111 37 11	110110	Torridias					
Crushing	200	5.400E-03	2000	2640	1.426	=B5*C5	5/D5*E5				
Screening	200	2.200E-03	2000	2640	0.581	_B6*C4	5/D6*E6				
3ci ceriirig	200	2.200L-03	2000	2040	0.361	-B0 C0	57 DO E0				
Total Tons = Trips per year ×											
Tons per trip											
Uncontrolled PM10 ton/yr =											
Total Tons × EF/2000											
Controlled PM10 tons/yr =											
Uncontrolled PM10 tons/yr ×											
(1 - Control Efficiency)											
Unpaved Roads											
Total Tons (ton/yr) 528000	Trips per year 26400	Tons per trip 20									
528000	20400	20									
	Emission Factor										
Uncontrolled PM10 ton/yr	(lb/VMT)	lb/ton									
79.2	0.3	2000									
Controlled PM10 (ton/yr)	(1-Control efficiency)	using 80%									
15.84	0.2										
Emissions Sheet											
EPN-1 Emissions Calculation											
((Emission Factor (g/kWh)xEngine power											
(kw)xOperating hours											
(h))/1000000 (metric											
ton/g))x1.1023 (US											
tons/metric ton)											
					US						
	Emission Factor	Engine Power		metric ton/g	tons/metric						
NOx	(g/kWh) 0.4	(kW) 298	Hours 2640	(1000Kg) 1,000,000	ton 1.1023						
CO	3.5		2640	1,000,000	1.1023						
NMHC	0.19		2640	1,000,000	1.1023						
PM10	0.02	298	2640	1,000,000	1.1023						
	Annual Emissions (US										
	tons)										
NOx	0.35										
CO NMHC	3.04 0.16										
PM10	0.02										
EPN 2-11 Emissions											
Calculations							tons/hr				
						Uncontrolled	conversion			Uncontrolled	Controlled
EPN	Source	Process Type	Pollutant	TPH	EF (lb/ton)	lb/hr		tons/hr	Hours/yr		TPY 80%
า	Primary Feed Hopper	Material drep	PM10	200	0.002	0.4	0.0005	0.0002	2640	0.528	0.1
2	Vibrating Grizzly	iviaterial drop	FIVITO	200	0.002	0.4	0.0003	0.0002	2040	0.320	U.
	Feeder	Screen/feeder	PM10	200			0.0005	0.0002	2640		
	Impact Crusher	Crusher	PM10	200					2640		
	Conveyor #1 Primary Screen	Conveyor transfer Screen	PM10 PM10	200 200			0.0005 0.0005	0.00015 0.00022	2640 2640		
	Conveyor #2		PM10	200			0.0005	0.00022	2640		
	Secondary Screen	Screen	PM10	200	0.0022	0.44	0.0005	0.00022	2640	0.5808	0.1
					0.0015	0.3	0.0005	0.00015	2640	0.396	0.0
	Conveyor #3	Conveyor transfer	PM10	200	0.0015	0.3	0.0003	0.00013	2010	0.370	-
9	Conveyor #3	,									
9		,	PM10 PM10	200		0.5		0.00025	2640		

Exhibit B Facility Maps





(Satellite Image (Hybrid Street)) AERIAL PHOTO SERIES (Satellite Image (Hybrid Street)) 098.333101°W U **topo** 098.255107° W + 028.648583° N (Satellite Image (Hybrid Street)) Distance to Nearest Place of Worship Exceeds 1 Mile 1.7179 Miles, 078.65° T River to Barn (Satellite Image (Hybrid Street)) (Satellite Image (Hybrid Street)) Excavaton Area Center of Excavation Area 028.625226° N 098.312255° W 449 Yards, 116.40° T Distance to multiple Barns 475 Yards, 122.60° T Distance to Distance to Nearest Public **HWY Exceeds 1 Mile** 441 Yards, 140.93° T 1.1046 Miles, 135.95° T 028.601028° N 098.333101° W 028.601028° N 098.255107° W (Satellite Image (Hybrid Street)) SCALE 1:25000 Declination (Satellite Image (Hybrid Street)) (Satellite Image (Hybrid Street)) Produced by Trimble Terrain Navigator Pro Topography based on USGS 1:12,000 Maps 28098-E3-TM-012

North American 1983 Datum (NAD83) To place on the predicted North American 1927 move the projection lines 29M N and 28M

CONTOUR INTERVAL UNKNOWN FT

WILLOW HOLLOW TANK, TX MAY 16, 2022


CONTOUR INTERVAL 10 FT

To place on the predicted North American 1927 move the projection lines 29M N and 28M

DEC 31, 1969

Exhibit C Process Flow Diagram

EPN FLOW DIAGRAM



Comprehensive EPN List – Trakpactor 550 Rock Crusher Project

Facility: Portable Rock Crusher (Powerscreen Trakpactor 550)

Permit Type: TCEQ Standard Permit for Rock and Concrete Crushers

Prepared For: Form PI-1S / Form 20335 Attachment – EPN Summary Table

EPN	Source Name / Description	Emission Type / Pollutant	Control Device / Method	Regulatory Reference
1	Scania DC13 Diesel Engine Exhaust (Tier 4F, 494 hp)	NOx, CO, VOC, PM, SO2	Built-in engine controls (SCR, DOC); Tier 4F compliant	40 CFR 60 Subpart IIII; Nonroad CI Engine Standards
2	Primary Feed Hopper	PM10, PM2.5 (Fugitive Dust)	Water sprays at hopper lip	AP-42 11.19.2; NSPS OOO
3	Vibrating Grizzly Feeder	PM10, PM2.5	Spray bar over feeder	AP-42 11.19.2; NSPS OOO
4	Impact Crusher (Trakpactor 550)	PM10, PM2.5	Internal water sprays, housing enclosure	AP-42 11.19.2; 40 CFR 60 Subpart OOO
5	Crusher Discharge Conveyor #1	PM10, PM2.5	Spray nozzles, belt skirting	AP-42 11.19.2; 40 CFR 60 Subpart OOO
6	Vibratory Screen #1 (Primary)	PM10, PM2.5	Spray bar at screen decks	AP-42 11.19.2; 40 CFR 60 Subpart OOO
7	Transfer Conveyor #2	PM10, PM2.5	Full skirting, spray bar	AP-42 11.19.2; 40 CFR 60 Subpart OOO
8	Vibratory Screen #2 (Secondary/Fines)	PM10, PM2.5	Spray bar at screen decks	AP-42 11.19.2; 40 CFR 60 Subpart OOO
9	Final Product Conveyor #3	PM10, PM2.5	Spray bar at discharge, skirting	AP-42 11.19.2; 40 CFR 60 Subpart OOO

EPN	Source Name / Description	Emission Type / Pollutant	Control Device / Method	Regulatory Reference
10	Stockpile Drop Point / Loading	PM10, PM2.5 (Fugitive)	Water sprays at conveyor discharge, surface wetting	AP-42 13.2.4 (Aggregate Handling)
11	Pit Excavation and Loading Operations	PM10, PM2.5 (Fugitive)	Watering disturbed areas, minimize drop heights	AP-42 13.2.2

Non-EPN Fugitive Emission Sources – Unpaved Roads

Per TCEQ guidance, fugitive emissions from **unpaved haul and access roads** are not listed as individual EPNs because they are not considered discrete process emission points. These emissions are treated as site-wide fugitive sources controlled through best management practices. Controls include water truck application, a 15 mph speed limit, and use of dust suppressants during dry periods. Records of watering and maintenance are retained for compliance documentation but do not require EPN designation.

Control System Description (Not an EPN)

The water spray system serves as the primary control mechanism for dust suppression across all emission points. Operating at 3 bar pressure and 24 L/min, it feeds multiple atomizing nozzles positioned over the crusher, screens, conveyors, and transfer points. The water system includes frost protection, pump, and manifold assemblies to maintain consistent performance.

Recordkeeping and Monitoring

Daily logs document watering events, suppressant applications, and equipment maintenance. Each emission point is visually inspected per shift to verify effective control. Any malfunction or failure is corrected immediately, and actions are recorded. Records are maintained for a rolling 24-month period and made available to TCEQ upon request.

Process Description

Material handling at the site begins with caliche or aggregate being loaded from the **pit** area (EPN 11) into the **primary feed hopper (EPN 2)** using a front-end loader or excavator. From the hopper, material passes over the **vibrating grizzly feeder (EPN 3)**, which removes finer material and regulates flow into the **impact crusher (EPN 4)**. The Trakpactor 550 impact crusher reduces the feed material to the desired size using a twin-apron, four-bar impactor system.

The crushed material exits the crusher onto the **first conveyor (EPN 5)**, which transfers material to the **primary screen (EPN 6)**. This screen separates the crushed aggregate into multiple size fractions. Oversized material may be recirculated through the system for additional crushing if required, while correctly sized material is transferred via the **second conveyor (EPN 7)** to the **secondary screen (EPN 8)** for further refinement.

The secondary screen produces the final graded product, which is conveyed by the **final product conveyor (EPN 9)** to the **stockpile drop points (EPN 10)**. Each conveyor and screen is equipped with water spray bars, belt skirting, and covered transfer points to control particulate emissions. Water spray systems operate continuously during production to minimize visible dust emissions.

Final products are temporarily stored in multiple **aggregate stockpiles** near the discharge points of each conveyor. The piles are sprayed or misted with water to minimize windblown dust and shaped with stable slopes. Material from the stockpiles is later loaded into trucks for off-site delivery. The single **Scania DC13 diesel engine (EPN 1)** powers the crusher and associated equipment. Dust from pit excavation and material loading (EPN 11) is minimized through water application and operational controls.

All material handling and crushing operations are conducted under the requirements of **40 CFR Part 60, Subpart OOO** (Standards of Performance for Nonmetallic Mineral Processing Plants). Fugitive emissions from unpaved haul roads are addressed through site-wide best management practices and are not designated as individual EPNs under TCEQ guidance.

Simplified Process Flow Sequence (EPN Reference)

- 1. **EPN 1** Scania DC13 Engine (Power Source)
- 2. **EPN 2** Feed Hopper
- 3. **EPN 3** Vibrating Grizzly Feeder
- 4. **EPN 4** Impact Crusher (Trakpactor 550)

- 5. **EPN 5** Conveyor #1 (Crusher Discharge)
- 6. **EPN 6** Primary Screen
- 7. **EPN 7** Conveyor #2 (Transfer to Secondary Screen)
- 8. **EPN 8** Secondary Screen
- 9. **EPN 9** Conveyor #3 (Final Product Transfer)
- 10. **EPN 10** Stockpile Drop Points / Finished Product Storage
- 11. **EPN 11** Pit Excavation and Material Loading

Exhibit D Crusher Info

POWERSCREEN® TRAKPACTOR 550



HORIZONTAL IMPACTOR





TECHNICAL SPECIFICATION - REV 4 01/02/2023



To use my interactive features I need to be opened in 'Adobe Acrobat Reader' click here to download





OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - ▶ OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS



SPECIFICATION

Total Weight PS: Tier 4F: 57,450kg (126,656lbs) Hopper extensions, bypass conveyor, single pole

magnet

Total Weight VGF: Tier 3: 54,850kg (120,924lbs) Hopper extensions, bypass conveyor, single pole

magnet, extended main conveyor

Transport Length 17.46m (57' 5") PS & Standard product conveyor

Height 3.8m (12' 6") **Width** 3m (9' 10")

Working Length 17.82m (58'6'') PS & Standard product conveyor

Height 5.15m (16' 10") **Width** 6.96m (22' 10")

Crusher Type: Twin apron 4 bar impact crusher, feed opening 1370mm x 911mm (54" x 36") **Power Unit** Tier 3 Caterpillar C13 328kW (440hp) or Tier 4F Scania DC13 368kW (494hp)

Plant Colour RAL 5021, RAL 7024, RAL 9005

APPLICATIONS



Aggregate

Blasted rock River rock



Recycling

C&D waste Foundry waste



Mining

Processed ores
Processed minerals









OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

PRODUCT CONVEYOR

Conveyor type: Fully removable modular unit with hydraulic raise

& lower facility to increase clearance & simplify rebar removal. Shallow troughed with winged rollers & fully tunnelled with minimal snag areas

Belt type: Ripstop EP500/3 8+2 with steel wire breaker ply

Belt width: 1200mm (3' 11")

Discharge height: 3.8m (12' 6") when fully raised

Stockpile volume: 101m³ (132 cu. yd.)

Feedboot: Fabricated steel with abrasion resistant steel liners

Impact area: Heavy duty under crusher impact bars

Skirting: Fully skirted in wear resistant rubber up to magnet

discharge area

Drive: Dual hydraulic motor direct to head drum

Lubrification: Centralised grease points for lubrication of shaft

bearings

Belt covers: Optional aluminium removable dust covers
Belt adjustment: Belt tensioning is by use of screw adjustment at

the head drum

Speed wheel: Designed to stop plant feed if the discharge

conveyor slows or stops

DUST SUPPRESSION SYSTEM

Spray bars with atomiser nozzles mounted over product conveyor & final conveyor discharge, piped to an inlet manifold for customer water supply or optional pump.

Type: Clean water multi atomising nozzles


Inlet: Single point on chassis

Inlet pressure: 3 bar (44psi)

Water supply: 24 litres (6.3 g) per minute min

Frost protection: Via system main valves

Pump: Optional









♠ OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

POWER UNIT & HYDRAULICS

Tier 3 Equivalent: Caterpillar C-13 ACERT, 6 cylinder, 328

kW (440hp)

Operating Conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected.

Operating rpm range: 1700 - 2100rpm **Emission control technique**: Not applicable

Plant drive: High quality tandem pumps driven via

engine PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Tier 4F / Stage V: Scania DC13 385A - 368kW (494hp)

Operating conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected

Operating rpm range: 1500 - 1900rpm

Emission control technique: Selective Catalytic Reduction (SCR)

Reductant tank size: 60 L (16 US Gal)

Plant drive: High quality pumps driven via clutch

PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Fuel tank capacity: 1000 L (264 US Gal)

Hydraulic tank capacity: 740 L (195 US Gal)

Crusher drive: Direct drive via wedge belts, clutch pulley diameter 425mm T4,

375mm T3

Crusher pulley diameter 800mm Terex

(39")

800mm with Hazemag chamber Crushing performance can be tuned, by changing engine speed via the PLC.

Chruscer drive tensioning: VEE belt tensioner system









OVERVIEW

- **FEATURES & BENEFITS**
- **CRUSHER**
 - **CRUSHER SPECIFICATION**
 - **CRUSHER FEATURES**
- **HOPPER**
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- **POWER UNIT & HYDRAULICS**
- **TRACKS**
- **PLANT CONTROLS & OTHER**
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- **OPTIONS**
 - **OPTIONS 2**
 - **OPTIONS 3**
- POWERSCREEN® PULSE
- **DIMENSIONS**



HAZEMAG CRUSHER SPECIFICATION

1360mm x 800mm (54" x 32") Feed opening:

500mm³ (20in³) / 860mm (34") diagonally/ Max lump size*:

1000 x 1000 x 200mm (39 x 39 x 8") slab

*depending on material blow bar specification

1340mm (53") Rotor width: Rotor diameter: 1200mm (47")

Number of aprons:

Maximum clearance: 273mm (11") on both aprons

Maximum OSS setting: 200mm (8") upper apron, 100mm (4") lower

Minimum CSS setting: 75mm (3") upper apron, 35mm (1.4") lower

Number of blow bars: 4

Blow bar removal: Vertically

Blow bar configuration: 2 full & 2 half (optional 4 full)

Setting adjustment: Hydraulic assist

Overload protection: Hydraulic

Rotor speeds: 540 - 630rpm (34 - 40m/s) (111 - 131ft/s)

Demolition / recycling / quarry Applications:

14,855kg (32,750lbs) Crusher weight:

Full blow bar weight: 410kg (904lbs)

Side Liners: 20mm thick, abrasive resistant steel










♠ OVERVIEW


- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - ▶ CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS


DIMENSIONS

Figure 1: Trakpactor 550 - Pre-screen, Standard Product Conveyor

Working Position









SCANIA CV AB

EXECUTIVE ORDER U-R-024-0034 New Off-Road Compression-Ignition Engines

Pursuant to the authority vested in the Air Resources Board by Sections 43013, 43018, 43101, 43102, 43104 and 43105 of the Health and Safety Code; and

Pursuant to the authority vested in the undersigned by Sections 39515 and 39516 of the Health and Safety Code and Executive Order G-14-012;

IT IS ORDERED AND RESOLVED: That the following compression-ignition engine and emission control system produced by the manufacturer are certified as described below for use in off-road equipment. Production engines shall be in all material respects the same as those for which certification is granted.

MODEL YEAR	ENGINE FAMILY	DISPLACEMENT (liters)	FUEL TYPE USEFUL LI (hours)					
2018	JY9XL12.7DAA	12.7	Diesel 800					
SPECIAL	FEATURES & EMISSION (CONTROL SYSTEMS	TYPICAL EQUIPMENT APPLICATION					
Cooler, Module, D DC1308	ic Direct Injection, Turboo Exhaust Gas Recirculation iesel Oxidation Catalyst (5A), Smoke Puff Limiter, action-Urea, Ammonia Ox	on, Engine Control Except Engine Code Selective Catalytic	Crane, Loader, Tractor, Dozer, Pump, Cor	npressor, Generator				

The engine models and codes are attached.

The following are the exhaust certification standards (STD) and certification levels (CERT) for non-methane hydrocarbon (NMHC), oxides of nitrogen (NOx), or non-methane hydrocarbon plus oxides of nitrogen (NMHC+NOx), carbon monoxide (CO), and particulate matter (PM) in grams per kilowatt-hour (g/kw-hr), and the opacity-of-smoke certification standards and certification levels in percent (%) during acceleration (Accel), lugging (Lug), and the peak value from either mode (Peak) for this engine family (Title 13, California Code of Regulations, (13 CCR) Section 2423):

RATED	EMISSION			E	KHAUST (g/kw-hi	7)		OP	ACITY (%	6)
POWER CLASS	STANDARD CATEGORY		NMHC	NOx	NMHC+NOx	co	PM	ACCEL	LUG	PEAK
130 ≤ KW ≤ 560	Tier 4 Final	STD	0.19	0.40	N/A	3.5	0.02	N/A	N/A	N/A
		CERT	0.08	0.19		0.2	0.02			

BE IT FURTHER RESOLVED: That for the listed engine models, the manufacturer has submitted the information and materials to demonstrate certification compliance with 13 CCR Section 2424 (emission control labels), and 13 CCR Sections 2425 and 2426 (emission control system warranty).

Engines certified under this Executive Order must conform to all applicable California emission regulations.

This Executive Order is only granted to the engine family and model-year listed above. Engines in this family that are produced for any other model-year are not covered by this Executive Order.

Executed at El Monte, California on this ___

_ day of February 2018.

Annette Hebert, Chief

Emissions Compliance, Automotive Regulations and Science Division

ATTACHMENTIOFI Engine ModelsEZ U-R-024-0034 1/17/2018

Engine Family	Code	2.Engine Model	3.Dis- placement	4.Power kW @RPM	mm/stroke @ peak HP	6.Fuel Rate: (lbs/hr) @ peak HP	7.Torque Nm @ RPM	8.Fuel Rate: mm/stroke@ peak torque	9.Fuel Rate: (lbs/hr)@ peak torque	10 Emission Control Davice
Y9XL12.7DAA	DC13 084A	2133500	12.7	294 @ 2100	198	140	2157 @ 1200	290	117	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 084A	2133501	12.7	331 @ 2100	222	157	2255 @ 1300	307	134	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133502	12.7	368 @ 2100	245	173	2373 @ 1300	325	142	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133503	12.7	405 @ 1900	344	243	2373 @ 1300	394	172	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245984	12.7	257 @ 1800	193	117	1638 @ 1300	219	96	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2258254	12.7	257 @ 2100	175	124	1720 @ 1300	232	102	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245985	12.7	283 @ 1800	211	149	1765 @ 1300	238	104	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 089A	2245986	12.7	257 @ 1800	193	117	1600 @ 1300	215	94	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
JY9XL12.7DAA	DC13 089A	2245987	12.7	283 @ 1800	211	128	1780 @ 1300	240	105	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX

Exhibit E Tables and Forms



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for	r Submissi	i on (If other is checked	please describe	e in space pro	vided.)							
New Pern	nit, Registra	ation or Authorization (Core Data Forn	n should be st	ubmitted v	with the prog	ram application.)					
Renewal	(Core Data	Form should be submit	ted with the re	newal form)			ther					
2. Customer	Reference	Number (if issued)		Follow this lin	nk to searc	<u>ch</u> 3. Re	3. Regulated Entity Reference Number (if issued)					
CN 6064023	245			for CN or RN Central Re			RN 112281167					
CIV 0004023						IXIV.	112201107					
SECTIO	N II:	Customer	Inform	<u>nation</u>								
4. General Cu	ustomer Ir	nformation	5. Effective	Date for Cus	stomer I	nformation	Updates (mm/dd/	уууу)		10/6/2025		
New Custon			pdate to Custo				nge in Regulated Ent	ity Own	ership			
Change in L	egal Name	(Verifiable with the Tex	as Secretary of	State or Texa	s Comptro	oller of Public	: Accounts)					
The Custome	r Name su	ubmitted here may l	be updated a	utomatically	y based o	on what is c	urrent and active	with th	ne Texas Secr	retary of State		
(SOS) or Texa	is Comptro	oller of Public Accou	nts (CPA).									
6. Customer	Legal Nan	ne (If an individual, pri	nt last name fir.	st: eg: Doe, Jo	ohn)		If new Customer, enter previous Customer below:					
Raider Aggrega	ates LLC.											
7. TX SOS/CP	A Filing N	umber	8. TX State	Tax ID (11 dig	gits)		9. Federal Tax I	D	10. DUNS	Number (if		
806016326			32099991542	2			(9 digits)					
							320999915					
11 Tune of C		M Cornerat	ion			☐ Indivi	dual	Dartno	orchin: \square Con	oral 🗆 Limitad		
11. Type of C		☐ Corporat		Othor			roprietorship	Ot		neral Limited		
12. Number			Local State	Other		Sole P	13. Independer			erated?		
								_	nea ana opt	crutcu.		
☑ 0-20 ☐ :	21-100 [101-250 251-	500 🔲 501	and higher			Yes	∐ No				
14. Customer	r Role (Pro	posed or Actual) – as i	t relates to the	Regulated En	tity listed	on this form.	Please check one of	the follo	owing			
Owner		Operator		ner & Operat			Other:					
Occupation	al Licensee	Responsible Par	rty \ \ \	VCP/BSA Appl	icant							
15 Mailina	1221 Highway 72											
15. Mailing												
Address:	City	Three Rivers		State	TX	ZIP	78071		ZIP + 4	2609		
				3.3.0			1.00.1					
16. Country I	Mailing In	formation (if outside	USA)		1	.7. E-Mail A	ddress (if applicabl	e)				

TCEQ-10400 (11/22) Page 1 of 3

(361) 449-6979							()	-		
ECTION III:	Regul	ated Fnt	ity Infori	mation	<u> </u>					
21. General Regulated Er						pplica	tion is also	required.)		
New Regulated Entity	Update to	o Regulated Entity	Name Update	e to Regulated	Entity I	nform	ation			
The Regulated Entity Na	me suhmitti	ed may he unda	ted in order to m	eet TCFO Co	re Dati	a Stai	ndards (ri	emoval of a	organizatio	nal endinas such
as Inc, LP, or LLC).	ne submeet	ca may ac apaa	icu, iii oruci io iii	000 7014 00		<i>a</i>		emovar of c	n gamzatio	ur cugs suc
22. Regulated Entity Nan	ne (Enter nan	ne of the site wher	e the regulated action	on is taking pl	ace.)					
S Jolander Ranch										
23. Street Address of										
the Regulated Entity:										
(No PO Boxes)	City		State		ZIP				ZIP + 4	
24. County										
	1	If no Stre	et Address is prov	rided, fields	25-28 a	are re	quired.			
25. Description to	US 281 S, T	urn west at whitse	ett Take CR 421 SSW	2.2 mi, RT 0.5	5 mi on	Calich	ie Rd, LT fo	or 0.67 mi, R1	for 0.48 mi.	. Enter through rand
Physical Location:	gate Whits	ett 78075								
26. Nearest City							State		Ne	arest ZIP Code
Whisett							TX		780)75
Latitude/Longitude are r	equired and	d may be added,	/updated to meet	TCEQ Core	Data Si	tanda	ırds. (Ged	coding of t	the Physica	l Address may be
used to supply coordinat	es where no	one have been p	rovided or to gair	n accuracy).						
27. Latitude (N) In Decim	al:	28.625226		28. L	ongitu	ide (V	V) In Deci	imal:	-98.3122	255
Degrees	Minutes		Seconds	Degr	ees		ı	Minutes		Seconds
29. Primary SIC Code	30	. Secondary SIC	Code	31. Prima	-	CS Co	Code 32. Secondary NAICS Code			
(4 digits)	(4	digits)		(5 or 6 dig	its)			(5 or 6 d	igits)	
1442				212321						
33. What is the Primary	Business of	this entity? (De	o not repeat the SIC	or NAICS desc	ription.))				
Caliche mining for road base	!									
24 Mailie	6217 Hwy 281 PO Box 383									
-	4. Mailing									
Address:	City	Three Rivers	State	Тх	Z	IP.	78071		ZIP + 4	
35. E-Mail Address:	901	transportation@g	mail.com				1			
36. Telephone Number			37. Extension o	r Code		38. F	ax Numb	er (if applica	able)	
(361)449-6979						() -			
						•	•			

19. Extension or Code

20. Fax Number (if applicable)

18. Telephone Number

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	Districts	Edwards Aquifer		Emissions Inventory Air	☐ Industrial Hazardous Wast	
17-10-17-18-18-18-18-18-18-18-18-18-18-18-18-18-	Districts	Edwards Aquiler		J Ellissions inventory All	Industrial nazardous was	
☐ Municipal Solid Waste Review Air		OSSF		Petroleum Storage Tank	□ PWS	
☐ Sludge ☐ Storm Water		Title V Air		Tires	Used Oil	
☐ Voluntary Cleanup ☐ Wastewat		☐ Wastewater Agri	culture	Water Rights	Other:	
2. Telephone Number 43. Ext./Code 44. Fax Number 210) 326-6991 () -			45. E-Mail	Address		
210) 326-6991		() -	evondran@	atei97.com		
ECTION V By my signature belo	w. I certify, to the best of my ehalf of the entity specified in Alpha Terra Engineering Inc.	Signature knowledge, that the informations	ation provided in t	his form is true and comple		
ECTION V By my signature below this form on b	ow, I certify, to the best of my ehalf of the entity specified in	Signature knowledge, that the informations	ation provided in t required for the u	his form is true and comple pdates to the ID numbers id	entified in field 39.	



Texas Commission on Environmental Quality Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

The following checklist has been developed to help the Texas Commission Environmental Quality (TCEQ), Air Permits Division (APD) confirm that the permanent rock or concrete crusher meets the standard permit requirements. Please read all questions and check "YES," "NO," or "N/A" or give specific information for the facility. If the permanent rock or concrete crusher plant does not meet all conditions of this standard permit, it will not be allowed to operate under the standard permit and must apply for a case-by-case preconstruction permit as required under Title 30 Texas Administrative Code § 116.111 (30 TAC § 116.111).

Please Che	Please Check The Type of Facility:							
CONDITIO	CONDITION NUMBER AND DESCRIPTION							
(1)(B)	If crushing concrete, will the concrete crushing facility be operated at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship at the time this application is filed?	☐ YES☐ NO☑ N/A						
	(The measurement of distance shall be taken from the point on the concrete crushing facility that is nearest to the residence, school, or place of worship toward the point on the building in use as a residence, school, or place of worship that is nearest the concrete crushing facility.)							
(1)(C)(ii)	In lieu of meeting the distance requirements of (1)(B), will the structure(s) within 440 yards of the concrete crushing facilities be occupied or used solely by the owner of the facility or the owner of the property upon which the facility is located?	☐ YES ☐ NO 🗹 N/A						
(1)(D)	In lieu of meeting the distance requirements in (1)(B), will all the following occur:							
(1)(D)(i)	Will this plant be engaged in crushing concrete and other materials resulting from the demolition of a structure on this site and will the concrete and other materials being crushed be used primarily at this site?	☐ YES ☐ NO 🗹 N/A						
(1)(D)(ii)	Will this plant operate onsite for one period of 180 calendar days or less?	☐ YES ☐ NO 🗹 N/A						
(1)(D)(iii)	Will all applicable conditions stated in commission rules, including operating conditions be met?	☐ YES ☐ NO 🗹 N/A						
(1)(D)(iv)	Will the plant be located in a county with a population of 2.4 million or more persons, or in a county adjacent to such a county?	☐ YES ☐ NO 🗹 N/A						
(1)(E)	Do you intend to apply for an authorization under Texas Health and Safety Code (THSC) § 382.0518, Preconstruction Permit, for any other crushing facility to be located at the same site within 12 months from the date of this authorization?	☐ YES ☑ NO ☐ N/A						



Please Check The Type of Facility: Rock Crusher Concrete Crusher							
CONDITION NUMBER AND DESCRIPTION (continued)							
(1)(F)	Is there a rock crusher (or concrete crusher) authorized under Texas Health and Safety Code (THSC) § 382.0518, Preconstruction Permit, at this site?	☐ YES 🗹 NO ☐ N/A					
	Have you withdrawn, within the previous 12 months, an application for authorization of a crushing facility under (THSC) § 382.0518, Preconstruction Permit, at this site?	☐ YES 🗹 NO ☐ N/A					
(1)(G)	Are the current registration form PI-1S entitled, "Registration for an Air Standard Permit", Table 17 and supporting information attached or mailed to the TCEQ, including Table 29 (if applicable), control devices and methods explanation, process flow diagram, process description, plot plan, and area map?	YES NO N/A					
	Is the company's compliance history rating poor?	☐ YES ✓ NO ☐ N/A					
(1)(H)	Has construction and/or operation begun on the facility?	☐ YES ☑ NO ☐ N/A					
	Is there a non operational crusher stored onsite?	☐ YES ✓ NO ☐ N/A					
(1)(I)	In accordance with 30 TAC § 116.614, Standard Permit Fees, was a \$900 fee sent to TCEQ Revenue Section?	✓ YES ☐ NO ☐ N/A					
(1)(J)	Will all facilities associated with this application for a standard permit comply with the conditions of Title 40 Code of Federal Regulations (40 CFR) Part 60, Subpart A, General Provisions and Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants?	YES NO N/A					
(1)(K)	Will these crushing facilities only process nonmetallic minerals or a combination of nonmetallic minerals as described in 40 CFR Part 60, Subpart OOO?	✓ YES NO N/A					
(1)(L)	Is 30 TAC Chapter 101, Subchapter H, Division 3, Mass Emissions Cap and Trade Program; or 30 TAC Chapter 117, Control of Air Pollution from Nitrogen Compounds applicable to this plant?	☐ YES ☐ NO 🗹 N/A					
(1)(M)	Will written records be kept for a rolling 24-month period at the site and made available at the request of any personnel from the TCEQ or any air pollution control program having jurisdiction?	✓ YES NO N/A					
	Will these written records be maintained onsite to show daily hourly operations and hourly throughput; road and work area cleaning and dust suppression logs; and stockpile dust suppression logs?	✓ YES NO N/A					



Please Chec	ck The Type of Facility:	Crusher							
CONDITIO	CONDITION NUMBER AND DESCRIPTION (continued)								
(1)(N)	Will this crushing operation and related activities comply with applicable requirements of 30 TAC Chapter 101, Subchapter F, Emission Events and Scheduled Maintenance, Startup, and Shutdown Activities?	✓ YES NO N/A							
(1)(P)	Have maintenance emissions been authorized? (Maintenance emissions are not included in this permit and must be approved under separate authorization.)	☐ YES ☐ NO 🗹 N/A							
	Have start-up and shutdown emissions been authorized? (Start-up and shutdown emissions that will exceed those expected during production operations must be approved under separate authorization.)	☐ YES ☐ NO 🗹 N/A							
	Will start-up and shutdown emissions exceed those expected during production operations?	☐ YES ✓ NO ☐ N/A							
(1)(Q)	Do you intend to authorize any facilities located at the same site as this rock crusher, by 30 TAC Chapter 106, Subchapter E, Aggregate and Pavement or 30 TAC § 106.512, Stationary Engines and Turbines?	☐ YES ✓ NO ☐ N/A							
PUBLIC N	OTICE REQUIREMENTS - Detailed Public Notice Information will be Determination of Technical Completeness								
(2)(B)(i)	Will public notice be published no later than 30 days after the application is determined to be technically complete?	YES NO N/A							
OPERATIO	ONAL REQUIREMENTS								
(3)(A)	Will the primary crusher throughput exceed 200 tons per hour?	☐ YES ✓ NO ☐ N/A							
(3)(B)	Will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located less than 200 feet from the nearest property line, as measured from the point on the facility nearest the property line?	☐ YES ☑ NO ☐ N/A							
(3)(C)	At the time this application is filed, will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship?	✓ YES ☐ NO ☐ N/A							
	(Distance shall be measured from the point on the facility nearest the residence, school, or place of worship to the point on the residence, school, or place of worship nearest the facility).								



Please Ch	Please Check The Type of Facility:							
OPERAT	OPERATIONAL REQUIREMENTS (continued)							
(3)(D)	Will the crushing facilities (not including associated sources) be located at least 550 feet from any other rock crusher, concrete crusher, concrete batch plant, or hot mix asphalt plant?	☐ YES ☐ NO 🗹 N/A						
	Will the crusher operate at the same time as any other rock crusher, concrete batch plant, or hot mix asphalt plant within a 550 feet radius?	☐ YES ☐ NO ☑ N/A						
(3)(E)	Will all associated sources, including but not limited to work areas, stockpiles, and roads (except for incidental traffic and the entrance and exit to the site), be located at least 100 ft. from the property line?	✓ YES □ NO □ N/A						
(3)(F)	Will this crushing operation consist of any additional facilities other than one primary crusher, one secondary crusher, one vibrating grizzly, two screens, any conveyors, and one internal combustion engine (or combination of engines) of no more than 1,000 total horsepower?	☐ YES ☑ NO ☐ N/A						
	(Equipment that is not a source of emissions does not require authorization.)							
(3)(G)	Will any of the crushers, associated facilities, and/or associated sources (excluding stockpiles) exceed 2,640 operating hours in any rolling 12-month period?	☐ YES ☑ NO ☐ N/A						
(3)(H)	Will any of the rock crusher/ concrete crusher or associated facilities operate during any time between one hour after official sunset to one hour before official sunrise?	☐ YES ☑ NO ☐ N/A						
(3)(I)	Will all crushers be equipped with runtime meters and will the runtime meters be operating during crushing operations?	✓ YES □ NO □ N/A						
(3)(J)	Will permanently mounted spray bars be installed at the inlet and outlet of all crushers, at all shaker screens, and at all material transfer points and used as necessary to maintain compliance with all TCEQ rules and regulations?	✓ YES □ NO □ N/A						
(3)(K)	Will opacity of emissions from any transfer point on belt conveyors or any screen exceed 10 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES ✓ NO ☐ N/A						
	Will opacity of emissions from any crusher exceed 15 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES 🗹 NO ☐ N/A						
(3)(L)	Will visible emissions leave the property for more than 30 seconds in duration in any six-minute period from the crusher(s), associated facilities, associated sources, and in-plant roads associated with the plant as determined using EPA Test Method 22?	☐ YES 🗹 NO ☐ N/A						



Please Check The Type of Facility:							
OPERATIONAL REQUIREMENTS (continued)							
(3)(M)	Will all in-plant roads and active work are operation of the crusher, associated facilititreated at all times with any of the following	es, and associated sources be					
(3)(M)(i)	Covered with a material such as, but not litire chips?	☐ YES ✓ NO ☐ N/A					
(3)(M)(ii)	Dust-suppressant chemicals?	✓ YES ☐ NO ☐ N/A					
(3)(M)(iii)	Water?	✓ YES ☐ NO ☐ N/A					
(3)(M)(iv)	Paved with a cohesive hard surface that is a	maintained intact and cleaned?	☐ YES ☑ NO ☐ N/A				
(3)(N)	Will all stockpiles be sprinkled with water or covered, as necessary, to minimize dust		YES NO N/A				
(3)(O)	Will raw material and product stockpile he	eights exceed 45 ft?	☐ YES ✓ NO ☐ N/A				
(3)(P)	Will the crusher be equipped with a weigh accurately determines the mass of materia		YES NO N/A				
(3)(Q)	Will the crusher remain at least 440 yards school, or place of worship when moving	YES NO N/A					
		Print Form	Reset Form				



Texas Commission on Environment Quality

Table 17 Rock Crushers

Does the facility operate at night?									
Does the facility operate at night?	Please Complete the Follo	wing							
Maximum Plant Production Rates: Primary Crusher Type: Trakpactor 550 200 tons/hour 520000 tons/hour Secondary Crusher(s) Type: tons/hour tons/hour Tertiary Crusher(s) Type: tons/hour tons/hour Tertiary Crusher(s) Type: tons/hour tons/hour The Following Pieces of Equipment will be Controlled as Shown:	Maximum operating schedu	ıle: 10	hour	s/day	5	da	ys/week	52	weeks/year
⊠ Primary Crusher Type: Trakpactor 550 200 tons/hour 520000 tons/hour □ Secondary Crusher(s) Type: tons/hour tons/hour tons/hour □ Tertiary Crusher(s) Type: tons/hour tons/hour The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter of all Crushers: □ None □ Water Spray □ Suction to Baghouse □ Other: □ Sulter Spray □ Sulter of None □ Sulter Spray □ Sulter Other: □ Sulter Spray □ Sulter of None □ Sulter Spray □ Spray □ Sulter □ Spray □ Sulter Spray □ Sulter □ Spray □ Sulter Spray □ Sulter □	Does the facility operate at	night?						•	☐ YES 🗵 NO
Secondary Crusher(s) Type: tons/hour tons/ Tertiary Crusher(s) Type: tons/hour tons/ The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None ⊠ Water Spray Suction to Baghouse Other: All Belt Transfer Points: None ⊠ Water Spray Suction to Baghouse Other: Inlet of all Crushers: None ⊠ Water Spray Suction to Baghouse Other: Outlet of all Crushers: None ⊠ Water Spray Suction to Baghouse Other: All Shaker Screens: None ⊠ Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None ⊠ Water Chemic	Maximum Plant Producti	on Rates:							
Trettiary Crusher(s) Type: tons/hour tons/ The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: Outlet of all Crushers: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Inlet of Baghouse Other: Other: Water Spray Suction to Baghouse Other: Other: Water Sprays are used, Other: Suction to Baghouse Other: Suction to Baghouse Other: Water Sprays are used, Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None	➤ Primary Crusher	Type: Tra	akpactor 550		200	tons/ho	ur 52000	00	tons/year
The Following Pieces of Equipment will be Controlled as Shown: Feed Hoppers: None Water Spray Suction to Baghouse Other: All Belt Transfer Points: None Water Spray Suction to Baghouse Other: Inlet of all Crushers: None Water Spray Suction to Baghouse Other: Outlet of all Crushers: None Water Spray Suction to Baghouse Other: All Shaker Screens: None Water Spray Suction to Baghouse Other: If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Secondary Crusher(s)	Type:				tons/hou	r		tons/year
Feed Hoppers:	Tertiary Crusher(s)	Type:				tons/hou	r		tons/year
Feed Hoppers:	The Following Pieces of E	quipment	will be Controlle	d as S	hown:		l .		-
All Belt Transfer Points: None	3		I —			Baghouse	Othe	r:	
Outlet of all Crushers: None	All Belt Transfer Points:	None None	➤ Water Spray		uction to	Baghouse	Othe	r:	
All Shaker Screens: None	Inlet of all Crushers:	None			uction to	Baghouse	Othe	r:	
If Water Sprays are used, Provide the Following Data: Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: _ None _ X Water Chemic	Outlet of all Crushers:	None	■ Water Spray		uction to	Baghouse	Othe	r:	
Water Flow Rate (gpm): 8-19 Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: _ \Box None _ \X Water _ \Box Chemic	All Shaker Screens:	None			uction to	Baghouse	Othe	r:	
Water Pressure at the Nozzle (psi): 200 Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	If Water Sprays are used,	Provide t	he Following Data	a:					
Number of Nozzles at each location: 2-3 If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls:	Water Flow Rate (gpm): 8	-19							
If baghouse is used, attach a Table 11 "Fabric Filters." Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Water Pressure at the Nozz	le (psi): 2	00						
Average material moisture content (%): Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: None Water Chemic	Number of Nozzles at each	location:	2-3						
Maximum acreage covered by stockpiles (acres): 1 Stockpiles have the following controls: □ None ☒ Water □ Chemic	If baghouse is used, attach	a Table 11	"Fabric Filters."						
Stockpiles have the following controls: None Water Chemic	Average material moisture	content (%):						
	Maximum acreage covered	by stockp	iles (acres): 1						
In-plant roads will be: Daved and Vacuumed Daved and Swent Oiled									
In-plant loads will be. I aved and vacuumed I aved and 5 wept I oned	In-plant roads will be: Paved and Vacuumed Paved and Swept Oiled								
Sprinkled with Water and/or Chemicals Other:									

PRINT FORM

RESET FORM

Texas Commission on Environmental Quality Table 29 Reciprocating Engines

I. Engine Data	l									
Manufacturer:		Model N	0.		Serial No.			Manufac	ture Date:	
Scania		DC13 Tie	er 4f		Unkown					
Rebuilds Date:		No. of C	ylinders:		Compress	ion Ratio): I	EPN:		
		6			17.5:1			DC13 08	85A	
Application: X	Gas Compi	ression	Electric	Generati	on Re	frigeratio	n 🗌 En	nergency/	Stand by	
✓ 4 Stroke Cycle	2 Stro	ke Cycle	Carb	ureted	Spark Ig	gnited [Dual Fue	l F	uel Injected	
☑ Diesel ☐ Naturally Aspirated ☐ Blower /Pump Scavenged ☐ Turbo Charged and I.C. ☑ Turbo Charged										
☐ Intercooled ☐ I.C. Water Temperature ☐ Lean Burn ☐ Rich Burn										
Ignition/Injection	Timing:	Fixed:			T	Vari	able: It is v	ariable a	nd not publi	С
Manufacture Horse	power Rat	ing: 500			Proposed	Horsepo	wer Rating:	500		
			Di	ischarge	Parameter	s				
Stack Height (1			Diameter ((Feet)	Stack T	'emperat	ure (°F)	Exit	Velocity (FPS)
16 feet 9 inches		0.5 feet			900			150		
II. Fuel Data										
Type of Fuel:	Field Gas		andfill Gas			Natural	Gas 🔲 🛚	Digester C	Bas 🗵 Dies	sel
Fuel Consumption	(BTU/bhp-	hr): 2879	He	eating Va	lue: 19400	BTU/lb	Lowe	er Heating	g Value: 18	300 BTL
Sulfur Content (gra	ins/100 sct	f - weight	%): <1.7							
III. Emission Fa	ctors (Bef	ore Cont	rol)				ı			
NO _X	CC)	SO	2	VOC Form		Formalo	lehyde	PM_{10}	
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.298 17.29	2.61	151.38	<0.002	<1	0.1417	8.22	<0.001	<0.1	0.0149	0.86
Source of Emission	Factors:	Manı Manı	ıfacturer Da	ata	AP-42 ×	Other (sp	ecify): Stat	e of Calif	ornia, Title	13
IV. Emission Fa	ctors (Pos	t Control	l)				1			
NO _X	CC)	SO	2	VO	C	Formalo	lehyde	PM ₁₀	
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.142 8.22	0.149	8.65		<1	0.05597	3.46	<0.001	<0.1	0.0149	0.86
Method of Emissio			•		an Operatio			djustmen	ıt	
Stratified Charg			C Catalyst		ner (Specify					
Note: Must submit		•		ntrol info	rmation the	at demons	strates cont	rol efficie		
Is Formaldehyde in									Yes X	No
V. Federal an			-		•					
☐ NSPS JJJJ ☐	MACT ZZ		NSPS IIII	Title	e 30 Chapte	er 117 - L	ist County:			
VI. Additional										
1. Submit a copy										.1.
2. Submit a typical percent of cons	_	anarysis, i	meruaing si	unur cont	ent and nea	ung vaiu	e. For gase	ous ruers,	provide inc	ле
3. Submit descrip		fuel ratio	control sys	tem (man	ufacturer ir	nformatio	n is accepta	ıble).		

Reset Form

Print Form

Texas Commission on Environmental Quality Air Quality Standard Permits General Requirements Checklist Title 30 Texas Administrative Code §§116.610-116.615

Check the most appropriate answer and include any additional information in the spaces provided. If additional space is needed, please include an extra page and reference the rule number. The SP forms, tables, checklists, and guidance documents are available from the TCEQ, Air Permits Division web site at: www.tceq.texas.gov/permitting/air/nav/standard.html.

Most Standard Permits require registration with the commission's Office of Permitting, Remediation, and Registration in Austin. The facilities and/or changes to facilities can be registered by completing a Form PI-1S, "Registration for Air Standard Permit." This checklist should accompany the registration form to expedite any registration review.

CHECK THE MOST APPROPRIATE ANSWERS AND FILL IN THE REQUESTED INFORMATION						
Rule	Questions/Description	Response				
116.610(a)(1)	Are there net emissions increases associated with this registration?	X YES ☐ NO				
	If "YES," will net emission increases of air contaminants from the project, other than those for which a National Ambient Air Quality Standard (NAAQS) has been established, meet the emission limits of § 106.261 or § 106.262?	X YES □ NO				
	If "NO," does the specific standard permit exempt emissions from this limit?	☐ YES ☐ NO				
Attach emissions	summary and calculations:					
116.610(a)(3)	Do any of the Title 40 Code of Federal Regulations Part (CFR) 60, New Source Performance Standards apply to this registration?	YES X NO				
If "YES," list sub	parts:					
116.610 (a)(4)	Do any Hazardous Air Pollutant requirements apply to this registration?	☐ YES 🗵 NO				
If "YES," list sub	parts					
116.610 (a)(5)	Do any maximum achievable control technology (MACT) standards as listed under 40 CFR Part 63 or Chapter 113, Subchapter C (National Emissions Standard for Hazardous Air for Source Categories) apply to this registration?	YES X NO				
If "YES," list sub	parts:					
116.610(a)(6)	Will additional emission allowances under Chapter 101, Subchapter H, Division 3, Emissions Banking and Trading, need to be obtained following this registration?	☐ YES ☒ NO				
116.611(a)(1-6)	Is the following documentation included with this registration:	X YES NO				
	Emissions calculations including the basis of the calculations?	X YES NO				
	Quantification of all emission increases and/or decreases associated with this project?	ĭ YES ☐ NO				
	Sufficient information demonstrating that this project does not trigger PSD or NNSR review?	ĭ YES ☐ NO				
	Description of efforts to minimize collateral emissions increases associated with this project?	ĭ YES ☐ NO				
	Process descriptions including related processes?	X YES ☐ NO				
	Description of any equipment being installed?	X YES NO				

Texas Commission on Environmental Quality Air Quality Standard Permits General Requirements Checklist

Title 30 Texas Administrative Code §§116.610-116.615

Rule	Question/Description	Response						
116.614	Are the required fee and a copy of the check or money order provided with the application?	ĭ YES ☐ NO						
116.615(1)	Will emissions from the facility comply with all applicable rules and regulations of the commission adopted under Texas Health and Safety Code, Chapter 382, and with the intent of the Texas Clean Air Act?	⊠ YES □ NO						
116.615(2)	Do you understand that all representations with regard to construction plans, operating procedures, and maximum emission rates in this registration become conditions upon which the facility will be constructed and operated?							
116.615(3)	Do you understand that all changes authorized by this registration need to be incorporated into the facility's permit if the facility is currently permitted under §116.110 (relating to Applicability)?							
List all related permit	numbers:							
116.615(9)617(e)(1)	Will all air pollution emission capture and abatement equipment be maintained in good working order?							
116.615(10)	Will the facility comply with all applicable rules and regulations of the TCEQ, the Texas Health and Safety Code, Chapter 382, and the Texas Clean Air Act?	X YES □ NO						

Save Form Reset Form Print Form

From: Ed vonDran <evondran@atei97.com>
Sent: Monday, October 27, 2025 5:41 PM

To: Andres Targa; 90TRANSPORTATION@GMAIL.COM; Matt Wilmot

Cc: Kimberly Cunningham

Subject: Re: Update for 181766 398884 Raider Aggregates Air Permit and Public

Notice

Categories: GTG WCC

Thank you Andres, we look forward to working with you. Please don't hesitate to contact us through the process with any questions you may have.

Get Outlook for iOS

From: Andres Targa < Andres. Targa@tceq.texas.gov>

Sent: Monday, October 27, 2025 3:38:23 PM

To: 90TRANSPORTATION@GMAIL.COM <90TRANSPORTATION@GMAIL.COM>; Matt Wilmot

<mwilmot@atei97.com>; Ed vonDran <evondran@atei97.com>
Cc: Kimberly Cunningham <Kimberly.Cunningham@tceq.texas.gov>

Subject: RE: Update for 181766_398884 Raider Aggregates Air Permit and Public Notice

You don't often get email from andres.targa@tceq.texas.gov. <u>Learn why this is</u> important

Good afternoon,

Please clarify who is the technical contact for the referenced standard permit application. I reached out to Mr. Harold E Von Dran on 10/14/2025 with my contact information in case you have any questions regarding the technical review portion of this permit application. Please note the technical contact is responsible for communicating with me during the technical review process.

Sincerely,

Andres Targa Mallona

Mechanical New Source Review Environmental Permit Specialist Air Permits Division Texas Commission on Environmental Quality Mail Code: MC-163, PO Box 13087

Austin, Texas 78711-3087 Direct Line: (512) 239-6107





How are we doing? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey

From: Kimberly Cunningham < Kimberly. Cunningham@tceq.texas.gov>

Sent: Monday, October 27, 2025 3:06 PM

To: Andres Targa < Andres. Targa@tceq.texas.gov>

Subject: Update for 181766_398884 Raider Aggregates Air Permit and Public Notice

Andres,

Below is my correspondence with Mr. Wilmont. (He had my info from a previous project.) He would like an update on the permanent rock crusher project.

Thanks, Kimberly Cunningham

From: Kimberly Cunningham < Kimberly.Cunningham@tceq.texas.gov

Sent: Monday, October 27, 2025 3:03 PM **To:** Matt Wilmot <mwilmot@atei97.com>

Cc: Ed vonDran <>

Subject: Raider Aggregates Air Permit and Public Notice

Mr. Wilmont,


I'm sorry I missed your phone call. Thank you for emailing as a follow-up.

The technical team work on your permit now. Below is a general timeline for rock crushers.

I will forward your update request to the technical team.

Thanks, Kimberly Cunningham

Rock/Concrete Crusher Standard Permit



Note: Registration will be approved or denied no later than the 30th day after the end of th

From: Matt Wilmot < mwilmot@atei97.com>
Sent: Monday, October 27, 2025 2:38 PM

To: Kimberly Cunningham < Kimberly. Cunningham@tceq.texas.gov>

Cc: Ed vonDran < evondran@atei97.com>

Subject: Raider Aggregates Air Permit and Public Notice

Good afternoon, Kimberly

I'm sending this email as a follow up to a message I just left on your answering machine.

We are requesting an update as a follow-up for the permit application that was submitted at the beginning of October and would like to know how soon we should expect a decision. Additionally, how soon should we expect to receive the public notice package?

For your reference the permit number is 181766 (Raider Aggregates Limited Liability Company, S Jolander Ranch). At this time it is considered Administratively Complete.

Thank you in advance for any info you can provide.

Matt Wilmot, GIT



architecture engineering environment

Office: 210-930-2834 **Mobile**: 210-386-1474

Email: <u>mwilmot@atei97.com</u>

8626 Tesoro Drive Suite 810 San Antonio, TX 78217

www.atei97.com





TBPE F-8920; Arch BR-1889; TBPG 50647

This message and any attachments are intended only for the use of the addressee and may contain information that is privileged and confidential. If the reader of the message is not the intended recipient or an authorized representative of the intended recipient, you are hereby notified that any dissemination of this communication is strictly prohibited. If you have received this communication in error, notify the sender immediately by return email and delete the message and any attachments from your system.

From: Andres Targa

Sent: Tuesday, October 14, 2025 10:08 AM

To: EVONDRAN@ATEI97.COM

Subject: 181766 398884 Raider Aggregates LLC.

Categories: GTG WCC

Good morning,

My name is Andres Targa, and I am the Permit Reviewer assigned to review the technical portion of this application.

If you have any questions regarding the status of your application, please let me know. Once I complete the review I will be reaching out with the next steps.

Sincerely,

Andres Targa Mallona

Mechanical New Source Review
Environmental Permit Specialist
Air Permits Division
Texas Commission on Environmental Quality

Mail Code: MC-163, PO Box 13087

Austin, Texas 78711-3087 Direct Line: (512) 239-6107





How are we doing? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey

From: Miguel Gallegos

Sent: Thursday, October 9, 2025 3:49 PM

To: Joe Nicosia

Subject: New Project Assignment - Currently in Initial Review Process - 181766_398884

181766_398884 is located at APD 398884s *Mechanical-Coatings*\Team Leader. Please assign a reviewer and move the project folder to APD 398884s *Mechanical-Coatings*\Assigned Reviewer's Folder.

Thank you!

Texas Commission on Environmental Quality

Standard Permit New Registration

Site Information (Regulated Entity)

What is the name of the site to be authorized?

S JOLANDER RANCH

Does the site have a physical address?

Because there is no physical address, describe how to locate this site: Located off of Co Rd 421 1.74 miles

west of Whitsett, Texas

City Whitsett

 State
 TX

 ZIP
 78075

 County
 LIVE OAK

 Latitude (N) (##.#####)
 28.624099

 Longitude (W) (-###.######)
 -98.31008

Primary SIC Code 1442

Secondary SIC Code

Primary NAICS Code 212321

Secondary NAICS Code

Regulated Entity Site Information

What is the Regulated Entity's Number (RN)? RN112281167

What is the name of the Regulated Entity (RE)?

RAIDER AGGREGATES

Does the RE site have a physical address?

Yes

Physical Address

Number and Street 1221 HIGHWAY 72
City THREE RIVERS

State TX
ZIP 78071
County LIVE OAK

Latitude (N) (##.#####) Longitude (W) (-###.######)

Facility NAICS Code 212321

What is the primary business of this entity?

Customer (Applicant) Information

How is this applicant associated with this site?

Owner

What is the applicant's Customer Number (CN)?

CN606402345

Type of Customer

Corporation

Full legal name of the applicant:

Legal Name Raider Aggregates Limited Liability

Company

Texas SOS Filing Number 806016326

Federal Tax ID

State Franchise Tax ID 32099991542

State Sales Tax ID Local Tax ID

DUNS Number

Number of Employees 0-20
Independently Owned and Operated? Yes
I certify that the full legal name of the entity applying for this permit has Yes

I certify that the full legal name of the entity applying for this permit has been provided and is legally authorized to do business in Texas.

Responsible Authority Contact

Organization Name Raider Aggregates Limited Liability

Company

Prefix MR
First Matthew

Middle

Last Muniz

Suffix

Credentials

Title Owner

Responsible Authority Mailing Address

Enter new address or copy one from list:

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable) 1221 HIGHWAY 72

Routing (such as Mail Code, Dept., or Attn:)

City THREE RIVERS

State TX ZIP 78071

Phone (###-###-) 3614496979

Extension

Alternate Phone (###-###-###)

Fax (###-###-###)

E-mail 90transportation@gmail.com

Responsible Official Contact

Person TCEQ should contact for questions about this application:

Same as another contact? CN606402345, Raider Aggregates

Limited Liability Company

Organization Name Raider Aggregates Limited Liability

Company

Prefix MR
First Matthew

Middle

Last Muniz

Suffix

Credentials

Title Owner

Enter new address or copy one from list:

Mailing Address

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable) 1221 HIGHWAY 72

Routing (such as Mail Code, Dept., or Attn:)

City THREE RIVERS

State TX ZIP 78071

Phone (###-####) 3614496979

Extension

Alternate Phone (###-###-###)

Fax (###-###-###)

E-mail 90transportation@gmail.com

Technical Contact

Person TCEQ should contact for questions about this application:

Same as another contact?

Organization Name Alpha Terra Engineering

Prefix MR
First Harold
Middle E
Last von Dran

Suffix JR Credentials PE

Title President/Chief Engineer

Enter new address or copy one from list:

Mailing Address

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable) 8626 TESORO DR STE 810

Routing (such as Mail Code, Dept., or Attn:)

City SAN ANTONIO

State TX ZIP 78217

Phone (###-###) 2103266991

Extension

Alternate Phone (###-###-###)

Fax (###-###-###)

E-mail evondran@atei97.com

Standard Permit General Information- New Reg Sites

1) Is this facility permanent or temporary? Permanent

2) Will the proposed facility meet all of the requirements of the standard

Yes

permit?

3) Select the type of unit that is being registered: PERMANENT ROCK AND CONCRETE

CRUSHERS

3.1) Select the rule associated to the unit specified. 6013

Standard Permit Attachments

Please attach all required documents including PI-1S, Table 17, Process Description, Process Flow Diagram, Standard Permit Checklist, Rock Crusher Checklist, and the Site Map.

[File Properties]

File Name Raider Air Permit Package 10.6.25.pdf

Hash C3EFDC6E6784393BA1C151BE79E8A2F7B360544808641910273B80C1EC23D6E6

MIME-Type application/pdf

Confidential

Please attach any other necessary information needed to complete the registration.

Expedite

Per Texas Health and Safety Code, Section 382.05155, does the applicant want to expedite the processing of this application?

No

Certification

The electronic signature below indicates that the Responsible Official has knowledge of the facts herein set forth and that the same are true, accurate, and complete to the best of my knowledge and belief. By this signature, the maximum emission rates listed on this certification reflect the maximum anticipated emissions due to the operation of this facility and all representations in this certification of emissions are conditions upon which the facilities and sources will operate. It is understood that it is unlawful to vary from these representations unless the certification is first revised. The signature certifies that to the best of the Responsible Officials knowledge and belief, the project will satisfy the conditions and limitations of the indicated exemption or permit by rule and the facility will operated in compliance with all regulations of the Texas Commission on Environmental Quality and with Federal U.S. Environmental Protection Agency regulations governing air pollution. The signature below certifies that, based on information and belief formed after reasonable inquiry, the statements and information above and contained in the attached document(s) are true, accurate, and complete. If you questions on how to fill out this form or about air quality permits. Please call (512) 239-1250. Individuals are entitled to request and review their personal information that the agency gathers on its forms.

- 1. I am Ed Vondran, the owner of the STEERS account ER031280.
- 2. I have the authority to sign this data on behalf of the applicant named above.
- 3. I have personally examined the foregoing and am familiar with its content and the content of any attachments, and based upon my personal knowledge and/or inquiry of any individual responsible for information contained herein, that this information is true, accurate, and complete.
- 4. I further certify that I have not violated any term in my TCEQ STEERS participation agreement and that I have no reason to believe that the confidentiality or use of my password has been compromised at any time.
- 5. I understand that use of my password constitutes an electronic signature legally equivalent to my written signature.
- 6. I also understand that the attestations of fact contained herein pertain to the implementation, oversight and enforcement of a state and/or federal environmental program and must be true and complete to the best of my knowledge.
- 7. I am aware that criminal penalties may be imposed for statements or omissions that I know or have reason to believe are untrue or misleading.
- 8. I am knowingly and intentionally signing Standard Permit New Registration.
- 9. My signature indicates that I am in agreement with the information on this form, and authorize its submittal to the TCEQ.

OWNER Signature: Ed Vondran OWNER

CN606402345 **Customer Number:**

Legal Name: Raider Aggregates Limited Liability Company

FR031280 Account Number: Signature IP Address: 108.80.68.185 Signature Date: 2025-10-06

16A64252F5E3FA6ADF5CD04AC99559DA5D34F3183FC0F0ED6E6819C53A99ADE9 Signature Hash: Form Hash Code at time of

Signature:

66B4A57CDFF026F3F45D6C80B34CF6F9C54C14CA8CEDA63FC826176F923E0499

Fee Payment

Transaction by: The application fee payment transaction was made by ER031280/Ed Vondran Paid by:

The application fee was paid by HAROLD E **VONDRAN**

Fee Amount: \$900.00

Paid Date: The application fee was paid on 2025-10-06

Transaction/Voucher number: The transaction number is 582EA000687920 and

the voucher number is 786527

Submission

Reference Number: The application reference number is 822185

Submitted by: The application was submitted by ER031280/Ed

Vondran

Submitted Timestamp: The application was submitted on 2025-10-06 at

16:19:29 CDT

Submitted From: The application was submitted from IP address

108.80.68.185

Confirmation Number: The confirmation number is 683186

Steers Version: The STEERS version is 6.93

Additional Information

Application Creator: This account was created by Matthew E Wilmot



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for	r Submissi	ion (If other is checked	please describ	e in space pro	vided.)						
New Pern	nit, Registra	ation or Authorization (Core Data Forr	n should be st	ubmitted (with the prog	ram application.)				
Renewal	(Core Data	Form should be submit	ted with the re	newal form)			Other				
2. Customer	Reference	Number (if issued)		Follow this lin	nk to sear	<u>ch</u> 3. Re	gulated Entity Re	ference	Number (if i	issued)	
CN 6064023	245			for CN or RN Central Re		_	 112281167				
CIV 0004023						KIV	112201107				
SECTIO	N II:	Customer	Inform	<u>nation</u>							
4. General Cu	4. General Customer Information 5. Effective				stomer I	nformation	Updates (mm/dd/	уууу)		10/6/2025	
New Custon			pdate to Custo				nge in Regulated Ent	ity Own	ership		
Change in L	egal Name	(Verifiable with the Tex	as Secretary of	f State or Texa	is Comptro	oller of Publi	c Accounts)				
The Custome	r Name sı	ubmitted here may l	be updated a	utomatically	y based o	on what is c	urrent and active	with th	ne Texas Secr	retary of State	
(SOS) or Texa	s Comptr	oller of Public Accou	nts (CPA).								
6. Customer	Legal Nan	ne (If an individual, pri	nt last name fir	st: eg: Doe, Jo	ohn)		If new Customer,	enter pre	evious Custom	er below:	
Raider Aggrega	ites LLC.										
7. TX SOS/CP	A Filing N	umber	8. TX State	Tax ID (11 dig	gits)		9. Federal Tax ID 10. DUNS Number (if			Number (if	
806016326			32099991542	(9 digits) applicable)							
							320999915				
11. Type of C	ustomer		ion			☐ Indivi	☐ Individual Partnership:			p: General Limited	
		County Federal		Other			roprietorship Other:			iciai 🗀 Eiiiitea	
12. Number				Отпел		30.61	13. Independer			erated?	
		☐ 101-250 ☐ 251-	500 🗌 501	and higher				, □ No	·		
14. Customer	r Role (Pro	posed or Actual) – as i	t relates to the	Regulated En	tity listed	on this form.	 Please check one of	the follo	owing		
Owner		Operator	Ow	ner & Operat	tor		Othor:				
Occupation	al Licensee	Responsible Par	rty 🔲 '	VCP/BSA Appl	licant		Other:				
15. Mailing	1221 Hig	hway 72									
Address:											
Addiess.	City	Three Rivers		State	TX	ZIP	78071		ZIP + 4	2609	
16. Country I	Mailing In	formation (if outside	USA)		1	L7. E-Mail A	ddress (if applicabl	e)	1		

TCEQ-10400 (11/22) Page 1 of 3

(361) 449-6979						() -		
ECTION III: I	Regula	ated Ent	ity Inforn	nation		l			
21. General Regulated En	tity Informa	tion (If 'New Reg	gulated Entity" is selec	ted, a new pe	rmit appli	cation is a	also required.)		
New Regulated Entity [Update to	Regulated Entity	Name	o Regulated	Entity Info	rmation			
The Regulated Entity Nan as Inc, LP, or LLC).	ne submitte	d may be upda	ted, in order to me	et TCEQ Cor	e Data Si	tandards	(removal of o	rganization	nal endings such
22. Regulated Entity Nam	e (Enter name	e of the site wher	e the regulated action	is taking pla	ce.)				
S Jolander Ranch									
23. Street Address of the Regulated Entity:									
(No PO Boxes)	City		State		ZIP			ZIP + 4	
24. County		1							
		If no Stre	et Address is provid	led, fields 2	5-28 are	required	l .		
25. Description to Physical Location:	US 281 S, Tu gate Whitse		ett Take CR 421 SSW 2.	2 mi, RT 0.55	mi on Cal	iche Rd, L	Γ for 0.67 mi, RT	for 0.48 mi.	Enter through ranch
26. Nearest City						State	1	Nea	rest ZIP Code
Whisett						TX		780	75
Latitude/Longitude are re used to supply coordinate	-	=	-		ata Stan	dards. (C	Geocoding of th	ne Physical	Address may be
27. Latitude (N) In Decima	al:	28.618588	28. Longitude (V			(W) In D	ecimal:	-98.2990	88
Degrees	Minutes		Seconds	Degrees			Minutes		Seconds
29. Primary SIC Code (4 digits)		Secondary SIC	Code	31. Prima (5 or 6 digit	•	Code	32. Seco (5 or 6 dig	ndary NAI	CS Code
1442				212321					
33. What is the Primary B	susiness of t	his entity? (De	o not repeat the SIC or	NAICS descr	ption.)		I		
Caliche mining for road base									
34. Mailing	6217 Hwy	281 PO Box 383							
Address:									
	City	Three Rivers	State	Tx	ZIP	7807	71	ZIP + 4	
35. E-Mail Address:	90tr	ansportation@g	mail.com						
36. Telephone Number			37. Extension or	Code	38	. Fax Nui	mber (if applical	ole)	
(361) 449-6979					() -			

19. Extension or Code

20. Fax Number (if applicable)

18. Telephone Number

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	Districts	Edwards Agui	for	☐ Emis	sions Inventory Air	Industrial Hazardous Was			
17-10-17-18-18-18-18-18-18-18-18-18-18-18-18-18-		Edwards Aqui	iei			Industrial Hazardous was			
Municipal Solid W	√aste	e		Petro	leum Storage Tank	☐ PWS			
Sludge	Storm Wat	er Title V Air		Tires		Used Oil			
☐ Voluntary Cleanu	p \Box Wastewate	er Wastewater A	griculture	ure Water Rights		Other:			
2. Telephone Num	ber 43. Ext./Code	44. Fax Number	45. E-N	Tail Addr	44. Fax Number 45. E-Mail Address () - evondran@atei97.com				
210) 326-6991		() -	evondra	n@atei97	.com				
ECTION V By my signature belo	Authorized ow, I certify, to the best of mehalf of the entity specified Alpha Terra Engineering Inc.	I Signature y knowledge, that the info	rmation provided	in this for he updates	m is true and complet				
ECTION V By my signature below this form on b	ow, I certify, to the best of mehalf of the entity specified	I Signature y knowledge, that the info	rmation provided as required for t	in this for he updates	m is true and complet s to the ID numbers id	entified in field 39.			

Form PI-1S Registrations for Air Standard Permit (Page 1)

I.	Registrant Information
A.	Company or Other Legal Customer Name:
Raider	Aggregates LLC.
B.	Company Official Contact Information:
	⊠ Mr.
	☐ Mrs.
	☐ Ms.
	☐ Other:
Name:	Matt Muniz
Title: C	Owner Company of the
Mailing	Address: 6217 Hwy 281 PO Box 383
City: T	hree Rivers
State:	TX
ZIP Co	ode: 78071
Teleph	one Number: 361-449-6979
Fax Nu	umber:
Email /	Address: 90transportation@gmail.com
All per	mit correspondence will be sent via email.
C.	Technical Contact Information
	⊠ Mr.
	☐ Mrs.
	☐ Ms.
	Other:
Name:	Harold E. von Dran
Title: F	resident/Chief Engineer
Compa	any Name: Alpha Terra Engineering Inc.
Mailing	Address: 8626 Tesoro Dr Ste 810
City: S	an Antonio
State:	TX
ZIP Co	de: 78217

Form PI-1S Registrations for Air Standard Permit (Page 2)

I.	Registrant Information (continued)
C.	Technical Contact Information (continued)
Teleph	none Number: 210-326-6991
Fax N	umber:
Email	Address: evondran@atei97.com
II.	Facility and Site Information
A.	Name and Type of Facility
Facility	y Name: S. Jolander Ranch / Raider Aggregates Caliche Pit
Туре	of Facility:
	□ Permanent
	☐ Temporary
For po	ortable units, please provide the serial number of the equipment being authorized below.
Serial	No(s):
B.	Facility Location Information
Street	Address:
	e is no street address, provide written driving directions to the site and provide the closest city or town, v, and ZIP code for the site (attach description if additional space is needed).
US 281 S	, Turn west at whitsett Take CR 421 SSW 2.2 mi, RT 0.55 mi on Caliche Rd, LT for 0.67 mi, RT for 0.48 mi. Enter through ranch gate
City: V	Vhitsett
Count	y: Live Oak
ZIP Co	ode: 78075
C.	Core Data Form (required for Standard Permits 6006, 6007, and 6013).
Is the	Core Data Form (TCEQ Form 10400) attached?
	⊠ Yes □ No
Custo	mer Reference Number (CN): 606402345
Regula	ated Entity Number (RN): 112281167
D.	CEQ Account Identification Number (if known):

Form PI-1S Registrations for Air Standard Permit (Page 3)

II. Facility and Site Information (continued)
E. Type of Action
☐ Change to Registration
Renewal
Renewal Certification
For Change to Registration, Renewal, or Renewal Certification actions provide the following:
Registration Number:
Expiration Date:
F. Standard Permit Claimed:
G. Previous Standard Exemption or PBR Registration Number:
Is this authorization for a change to an existing facility previously authorized under a standard exemption or PBR?
☐ Yes
If "Yes," enter previous standard exemption number(s) and PBR registration number(s) and associated effective date in the spaces provided below.
Standard Exemption Number(s):
PBR Registration Number(s):
H. Other Facilities at this Site Authorized by Standard Exemption, PBR, or Standard Permit
Are there any other facilities at this site that are authorized by an Air Standard Exemption, PBR, or Standard Permit?
☐ Yes
If "Yes," enter standard exemption number(s), PBR registration number(s), Standard Permit Registration Number(s), and associated effective date in the spaces provided below.
Standard Exemption Number(s):
PBR Registration Number(s):
Standard Permit Registration Number(s):

Form PI-1S Registrations for Air Standard Permit (Page 4)

II. Facility and Site Information <i>(continued)</i>
I. Other Air Preconstruction Permits
Are there any other air preconstruction permits at this site?
☐ Yes ⊠ No
If "Yes," enter permit number(s) in the spaces provided below.
J. Affected Air Preconstruction Permits
Does the standard permit directly affect any permitted facility?
☐ Yes
If "Yes," enter permit number(s) in the spaces provided below.
K. Federal Operating Permit (FOP) Requirements
Is this facility located at a site that is required to obtain a FOP pursuant to 30 TAC Chapter 122?
☐ Yes ☐ No ☐ To Be Determined
Check the requirements of 30 TAC Chapter 122 that will be triggered if this standard permit is approved (check all that apply).
☐ Initial Application for a FOP
☐ Significant Revision for a SOP
☐ Minor Revision for a SOP
☐ Operational Flexibility/Off Permit Notification for a SOP
☐ Revision for a GOP
☐ To be Determined
⊠ None
Identify the type(s) of FOP issued and/or FOP application(s) submitted/pending for the site. (check all that apply)
□SOP
SOP application/revision (submitted or under APD review)
□GOP
☐ GOP application/revision (submitted or under APD review)
⊠ N/A

Form PI-1S Registrations for Air Standard Permit (Page 5)

III.	Fee Information (go to www.tceq.texas.gov/epay to pay online)
A.	Fee Amount: \$900
B.	Voucher number from ePay: Payment through STEERS
IV.	Public Notice (if applicable)
A.	Responsible Person
	⊠ Mr.
	☐ Mrs.
	☐ Ms.
	Other:
Name	: Jerry Pogue
Title: S	Sr. Consultant
Comp	any: Calidad Consulting LLC.
Mailing	g Address: PO Box 64
City: F	ischer ischer
State:	Texas
ZIP Co	ode: 78623
Teleph	none No.: 361-813-7225
Fax N	o.:
Email	Address: jpogue@calidadco.com
B.	Technical Contact
	⊠ Mr.
	☐ Mrs.
	☐ Ms.
	Other:
Name	: Harold (Ed) von Dran
Title: F	President and Chief Engineer
Comp	any: Alpha Terra Engineering
Mailing	g Address: 8626 Tesoro Dr. Ste 810
City: S	San Antonio
State:	Texas
ZIP Co	ode: 78217

Form PI-1S Registrations for Air Standard Permit (Page 6)

Texas Commission on Environmental Quality

IV. Public Notice (if applicable)
B. Technical Contact
Telephone Number: 210-930-2834
Fax Number:
Email Address: evondran@atei97.com
C. Bilingual Notice
Is a bilingual program required by the Texas Education Code in the School District?
☐ Yes ⊠ No
Are the children who attend either the elementary school or the middle school closest to your facility eligible to be enrolled in a bilingual program provided by the district?
☐ Yes ⊠ No
If "Yes," list which language(s) are required by the bilingual program below?
Language(s):
Language(s):
D. Small Business Classification and Alternate Public Notice
Does this company (including parent companies and subsidiary companies) have fewer than 100 employees or less than \$6 million in annual gross receipts?
⊠ Yes □ No
Is the site a major source under 30 TAC Chapter 122, Federal Operating Permit Program?
☐ Yes ⊠ No
Are the site emissions of any individual regulated air contaminant equal to or greater than 50 tpy?
☐ Yes ⊠ No
Are the site emissions of all regulated air contaminant combined equal to or greater than 75 tpy?
☐ Yes ⊠ No

Form PI-1S Registrations for Air Standard Permit (Page 7)

Texas Commission on Environmental Quality

٧.	Renewal Certi	fication Option
A.		itted facility emit an air contaminant on the Air Pollutant Watch List, and is the permitted in an area on the watch list?
	☐ Yes	⊠ No
B.	highly reactive	rticipating in the Houston/Galveston/Brazoria area (HGB) cap and trade program for VOCs (HRVOCs), do the HRVOCs need to be speciated on the maximum allowable table (MAERT)?
	☐ Yes [⊠ No
C.	Does the comp	any and/or site have an unsatisfactory compliance history?
	☐ Yes	⊠ No
D.	Are there any a	applications currently under review for this standard permit registration?
	☐ Yes	⊠ No
E.		maintenance, startup, or shutdown emissions required to be included in the standard ion at this time?
	☐ Yes	⊠ No
F.	Are any of the f	following actions being requested at the time of renewal:
	☐ Yes	⊠ No
1.	•	acilities that have been permanently shut down that are proposed to be removed from ermit registration?
	☐ Yes ☐	⊠ No
2.		eed to be made to the standard permit registration in order to remain in compliance?
3.		facilities that have always been present and represented, but never identified in the tregistration, proposed to be included with this renewal?
	☐ Yes	⊠ No
4.	Are there any o	changes to the current emission rates table being proposed?
	☐ Yes	⊠ No
certific	ation option and	of the questions in Section V. Renewal Certification Option are "No," use the I skip to Section VII. of this form. If the answers to any of the questions in Section V. Option are "Yes," the certification option cannot be used.
		and comments are received in response to the public notice, the application does not certification option.

Form PI-1S Registrations for Air Standard Permit (Page8) Texas Commission on Environmental Quality

VI.	Technical Inf	ormation Including State and Federal Regulatory Requirements								
Note: A	Any technical c	to the appropriate box to indicate what you have included in your submittal. or essential information needed to confirm that facilities are meeting the requirements of must be provided. Not providing key information could result in an automatic deficiency oject.								
A.	Standard Permit requirements (Checklists are optional; however, your review will go faster if you provide applicable checklists.)									
Did you	u demonstrate	that the general requirements in 30 TAC§§116.610 and 116.615 are met?								
		□ No								
Did you	u demonstrate	that the individual requirements of the specific standard permit are met?								
		□ No								
B.	Confidential Ir	nformation (All pages properly marked "CONFIDENTIAL").								
		□ No								
C.	Process Flow	Diagram.								
		□ No								
D.	Process Desc	cription.								
		□ No								
E.	Maximum Em	issions Data and Calculations.								
		□ No								
F.	Plot Plan.									
	⊠ Yes	□ No								
G.	Projected Sta	rt of Construction Date, Start of Operation Date, and Length of Time at Site:								
		□ No								
Project	ed Start of Co	nstruction (provide date): October 15, 2025								
Project	ed Start of Op	eration (provide date): November 15, 2025								
Length	of Time at the	e Site: 7 years								

Form PI-1S Registrations for Air Standard Permit (Page 9) Texas Commission on Environmental Quality

VII. Delinquent Fees and Penalties

This form **will not be processed** until all delinquent fees and/or penalties owed to TCEQ or the Office of the Attorney General on behalf of TCEQ are paid in accordance with the Delinquent Fee and Penalty Protocol. For more information regarding Delinquent Fees and Penalties, go to the TCEQ website at: www.tceq.texas.gov/agency/financial/fees/delin/index.html

VIII. Signature Requirements

The signature below confirms that I have knowledge of the facts included in this application and that these facts are true and correct to the best of my knowledge and belief. I further state that to the best of my knowledge and belief, the project for which application is made will not in any way violate any provision of the Texas Water Code (TWC), Chapter 7; the Texas Health and Safety Code (THSC), Chapter 382, the Texas Clean Air Act (TCAA) the air quality rules of the Texas Commission on Environmental Quality; or any local governmental ordinance or resolution enacted pursuant to the TCAA. I further state that I understand my signature indicates that this application meets all applicable nonattainment, prevention of significant deterioration, or major source of hazardous air pollutant permitting requirements. The signature further signifies awareness that intentionally or knowingly making or causing to be made false material statements or representations in the application is a criminal offense subject to criminal penalties.

Name (printed): Harold E. von Dran, PE

Signature (original signature required):

IX. Copies of the Registration

The Form PI-1S application must be submitted through ePermits. No additional copies need to be sent to the Regional Office or local Air Pollution Control Program(s). The link to ePermits can be found here: www3.tceq.texas.gov/steers/.



July 31, 2025

Texas Commission on Environmental Quality Air Permits Initial Review Team, MC 161 12100 Park 35 Circle Building C, Third Floor Austin, Texas 78753

Subject: Claim of a Standard Permit under 30 TAC §116.611 to operate a Caliche Pit Facility

Reference: Raider Aggregates Limited Liability Company

To whom it may concern:

Please find attached supporting documentation for a Standard Permit application for Raider Aggregates, LLC. registering a Caliche Pit facility located off of Co Rd 421 in Whitsett Texas, 78075

INTRODUCTION

RAIDER AGGREGATES, LLC is applying to authorize a Caliche Pit facility located in Live Oak County. Caliche based aggregates will be extracted from the site and hauled away via transport truck.

Facility layout and operational parameters are detailed in attached appendices.

New Source Review (NSR) Authorization

RAIDER AGGREGATES, LLC is proposing to authorize the Caliche Pit facility under 30 Texas Administrative Code (TAC) §116.611. In addition to the Caliche Pit facility meeting the claimed Standard Permit, the facility meets the general requirements of 30 TAC §116.611 (posted in STEERS with this supporting data).

INTRODUCTION

RAIDER AGGREGATES, LLC is submitting this application for a Standard Air Permit to authorize operations at a proposed caliche pit located off of Co Rd 421 near Whitsett Texas. The site will be used for the extraction and processing of caliche material, which is commonly utilized in road base, construction, and other infrastructure projects.

The facility will involve activities such as excavation, stockpiling, material handling, and loading of caliche into transport trucks. Emission sources will primarily include fugitive dust from material handling and vehicle traffic, as well as emissions from any associated equipment such as screens or conveyors. Appropriate dust suppression methods, including water sprays and best management practices, will be employed to minimize particulate emissions and ensure compliance with applicable Texas Commission on Environmental Quality (TCEQ) regulations.

This application includes a detailed site layout, equipment specifications, emission calculations, and a demonstration of compliance with all applicable air quality standards under the TCEQ's Standard Permit for Rock and Concrete Crushers.

PROCESS DESCRIPTION AND CONTROL MEASURES

EPN1 – Unpaved haul and access roads are utilized to allow access for empty trucks coming onsite and filled trucks moving off site. Road emissions are controlled by periodic watering using water trucks. Frequency of watering is determined by traffic and weather, with a once daily minimum. Speed limits are to be set at 15 mph to reduce dust. Environmentally approved dust suppressants may be utilized on high use sections of the roads, or during drought.





EPN2 – Pit operations include removal of overburden (topsoil), blasting (if necessary) and retrieval of coarse caliche ore, and loading of ores into transportation trucks for delivery to the rock crusher. Pit emissions are controlled by periodic water spraying to reduce dust levels, minimizing drop heights when dumping caliche into haul trucks, minimizing disturbed areas during mining, and where feasible, stabilizing completed portions of the pit.

EPN3 – The rock crusher is a Power screen Trakpactor 550 utilizing a Scania DC13 engine. After hauling trucks are loaded with coarse caliche ore it is transported a short distance to the rock crusher. The crusher breaks the ore down into smaller pieces which are screened by size. The crusher is equipped with a spray system for watering to reduce dust emissions. Water sprayers will be well maintained and checked upon each use. Crusher may be equipped with flexible skirting or partial enclosure to further reduce dust escape.

EPN4 – The stockpile is where the final product is stored temporarily after being screened and sorted, where it is made ready for transport. Stockpiles will be watered and formed with low slope angles to reduce windblow dust. Windbreaks may be installed to shield stockpiles, and any inactive stockpiles may be stabilized using crusting agents or temporary covers.

EPN5 – The finish product is transported by front end loader or excavator into hauling trucks for transport off site. Spray or fog systems will operate at the truck loading areas during active loading events. Loaders should minimize the height of material dropped into trucks to limit dust cloud formation. Trucks should be covered to reduce dust during transport.

Daily logs will also be kept for all water applications, suppressant uses, and equipment maintenance. Each EPN will be visually inspected per shift for effective dust control. Any failures in control systems will be addressed immediately and each corrective action documented.

All written records should be kept for a rolling 24-month period and be available at the request of TCEQ or any other air pollution control program upon request. Records should show daily hourly operations and hourly throughput: road dust suppression logs; and stockpile dust suppression logs.

EMISSIONS CALCULATION METHODOLOGY

This section presents documentation of emissions calculations for the RAIDER AGGREGATES Caliche Pit facility. The facility has several pints of emissions as listed above including engine emissions from trucks, front end loaders, excavators, and the rock crusher. All calculations represent worst-case with respect to potential emissions.

Should you have any questions regarding this submittal, please contact me at (210) 326-6991.

Respectfully submitted,

Alpha Terra Engineering, Inc.

Harold E. von Dran, Jr., PE

Environmental Engineer (TX 92737 / F-8920)

Attachments:

1) Exhibit A – Emissions Calculations

2) Exhibit B – Facility Maps

3) Exhibit C – Process Flow Diagram and Description

4) Exhibit D – Crusher Info

5) Exhibit E – Tables and Forms





Exhibit A Emission Calculations

System Parameters

EPN#	EPN	Description	AP-42 EF (lb/ton) controlled ¹	AP-42 EF (lb/hp-hr) ¹		
EPN1	Crusher	Rock Crushing Activities	5.400E-03			
EPN2	Screening	Sorting of aggregates by size	2.200E-03			
EPN3	Engine Exhaust	Engine or generator exhaust		Various*		
EPN4	Unpaved Roads	Roads that are unpaved				
hours per year			8760			
Facility Coordinates	Northing	28.62255	Easting	-98.300657		
		¹ TCEQ Technical Guidance and U.S. EPA Al	TCEQ Technical Guidance and U.S. EPA AP-42, Section 11.19.2			
		² From the State of California Resources Bo	oard			

System Parameters

AP-42 EF (lb/VMT) ¹		*Engine Exhaust AP-42 ²	EF (g/kWh)	
		Nox	0.4	
		CO	3.5	
		NMHC	0.19	
Various**		PM10	0.02	
		**Unpaved Roads AP-42	EF (lb/VMT) uncontrolled	80% Controlled
		PM10	1.5	0.3
		PM2.5	0.15	0.03
		TSP	4.90	0.98
Elevation	214			


System Parameters

EPN	Description	NO_x	CO	NMHC	PM_{10}	
Crushing	Rock Crushing Activities	0.00	0.00	0.00	1.43	
Screening	Sorting of Aggregates by Size	0.00	0.00	0.00	0.58	
Engine Exhaust	Exhaust from Crusher Generator or Engine	0.35	3.04	0.16	0.02	
Unpaved Roads	Particulate Generated by use of Unpaved Roads	0.00	0.00	0.00	15.84	Total Emissions (tons/yr)
		0.35	3.04	0.16	17.86	21.41
Conditions:						
	Based on permit data and technical documentation for the per year) for your scenario— ~10 hours per day, 5 days per technical documentation for the per year).					
PM10 Values for Crushi suppression or similar c	ng and Screening based on a Powerscreen Trakpactor 550 ontrols are in place.	operating at 2	00 tons/hour,	10 hours/da	y, 5 days/w	L eek assuming wet
	ssumes best practice dust mitigation (80%) and 0.25 miles	s of unpaved ro	l pads assuming	 transporting	the maxim	L um of 1716000 tons a yea
	EF (lb/ton) = lb/hr/ 1ton/2000 lb = tons/hr x2640 hr/yr = 1					

Calculations


PM10 Calculations						
Throughput (tons/hr) x EF (lb/to	on) =(lb/hr)/ (1ton/2000 lb) = tons/hr x 2640 hr/yr = toi	ns/year			
	Throughput (Tons/hr)	Emission Factor (lb/ton)	One Ton (lbs)	-	PM10	Formulas
Crushing	200		2000			=B5*C5/D5*E5
Screening	200	2.200E-03	2000	2640	0.581	=B6*C6/D6*E6
Total Tons = Trips per year × To	ins per trip					
Uncentralled DM10 ten/ur. To	tal Tana - FF/2000					
Uncontrolled PM10 ton/yr = To	ital Tons × EF/2000					
Controlled PM10 tons/yr = Unc	ontrolled PM10 tons/vr × (1 - Control Efficiency)				
OSTAL SHOW FIVE TO LOTIST YE - OTIC	ond oned i wild tolis/ yl ^ (- Control Efficiency)				
Unpaved Roads						
·						
Total Tons (ton/yr)	Trips per year	Tons per trip				
528000	26400	20				
		lb/ton				
79.2	0.3	2000				
	(1-Control efficiency)	using 80%				
15.84	0.2					
Emissions Sheet						
Emissions sneet						
((Emission Factor (g/kWh)xEngi	ine nower (kw)xOnerating	 	nn/a))x1 1023 (HS t	ons/metric ton)		
((LITIISSIOTE deter (g/KVVII)/KLIIGI	ine power (kw/koperating)	iodis (iijji 1000000 (iiletiic t	511, g//x 1. 1025 (05 t	ons, metric torij		
	Emission Factor (g/kWh)	Engine Power (kW)	Opperating Hours	metric ton/g (1000Kg)	US tons/met	ric ton
NOx	0.4	298			1.1023	
CO	3.5	298			1.1023	
NMHC	0.19	298	2640		1.1023	
PM10	0.02	298	2640	1,000,000	1.1023	
	Annual Emissions (US tons)					
NOx	0.35					
CO	3.04					
NMHC	0.16					
PM10	0.02					

Exhibit B Facility Maps



(Satellite Image (Hybrid Street))

SATELLITE IMAGE (HYBRID STREET) QUADRANGLE **TEXAS** (Satellite Image (Hybrid AERIAL PHOTO SERIES 098.258095° W + 028.646264° N Street))



(Satellite Image (Hybrid Street))

Produced by Trimble Terrain Navigator Pro Topography based on USGS 1:12,000 Maps

North American 1983 Datum (NAD83)

To place on the predicted North American 1927 move the projection lines 29M N and 28M W $\,$

Declination GN 0.34° E MN 3.96° E (Satellite Image (Hybrid Street)) SCALE 1:28000 2000

CONTOUR INTERVAL UNKNOWN FT


Printed: Thu Jul 03, 2025

(Satellite Image (Hybrid Street))

28098-F3-TM-012 WHITSETT, TX MAY 16, 2022


(WHITSETT)






CONTOUR INTERVAL 10 FT

Exhibit C Process Flow Diagram





Process Description:

- 1. Empty trucks arrive at the mining facility and travel along an unpaved road towards the operation.
- 2. Bulldozers remove the overburden (topsoil) covering the caliche deposit.
- 3. Controlled explosives fracture the caliche ore into manageable sizes suitable for excavation (if needed).
- 4. Excavators, front end loaders, or shovels load the blasted material into off road haul trucks.
- 5. Loaded haul trucks transport the coarse caliche ore to a designated processing area where a crusher is located.
- 6. The coarse caliche material enters a primary crusher, reducing it to smaller fragments.
- 7. The smaller fragments are screened by size.
- 8. The sorted caliche is loaded into off road haulers and deposited in a stockpile.
- 9. The final product is stockpiled by size and made ready for transport.
- 10. Outbound trucks are loaded with the final product.
- 11. Loaded trucks are checked for weight and proceed off site for delivery to construction projects, plants, or other end users.

Design: EvD	Caliaba Dit	Sheet: 1
Dwg: EvD	Caliche Pit	Dwg#: B
Ck:	Example Process Flow Diagram	Date07/15/2025
Appr: EvD	Example i rocess i low blagram	

Exhibit D Crusher Info

POWERSCREEN® TRAKPACTOR 550



HORIZONTAL IMPACTOR





TECHNICAL SPECIFICATION - REV 4 01/02/2023



To use my interactive features I need to be opened in 'Adobe Acrobat Reader' click here to download





OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- ▶ POWERSCREEN® PULSE
- DIMENSIONS



SPECIFICATION

Total Weight PS: Tier 4F: 57,450kg (126,656lbs) Hopper extensions, bypass conveyor, single pole

magnet

Total Weight VGF: Tier 3: 54,850kg (120,924lbs) Hopper extensions, bypass conveyor, single pole

magnet, extended main conveyor

Transport Length 17.46m (57' 5") PS & Standard product conveyor

Height 3.8m (12' 6")
Width 3m (9' 10")

Working Length 17.82m (58'6'') PS & Standard product conveyor

Height 5.15m (16' 10") **Width** 6.96m (22' 10")

Crusher Type: Twin apron 4 bar impact crusher, feed opening 1370mm x 911mm (54" x 36") **Power Unit** Tier 3 Caterpillar C13 328kW (440hp) or Tier 4F Scania DC13 368kW (494hp)

Plant Colour RAL 5021, RAL 7024, RAL 9005

APPLICATIONS



Aggregate

Blasted rock River rock



Recycling

C&D waste Foundry waste



Mining

Processed ores
Processed minerals









OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - ► HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

PRODUCT CONVEYOR

Conveyor type: Fully removable modular unit with hydraulic raise

& lower facility to increase clearance & simplify rebar removal. Shallow troughed with winged rollers & fully tunnelled with minimal snag areas

Belt type: Ripstop EP500/3 8+2 with steel wire breaker ply

Belt width: 1200mm (3' 11")

Discharge height: 3.8m (12' 6") when fully raised

Stockpile volume: 101m³ (132 cu. yd.)

Feedboot: Fabricated steel with abrasion resistant steel liners

Impact area: Heavy duty under crusher impact bars

Skirting: Fully skirted in wear resistant rubber up to magnet

discharge area

Drive: Dual hydraulic motor direct to head drum

Lubrification: Centralised grease points for lubrication of shaft

bearings

Belt covers: Optional aluminium removable dust covers
Belt adjustment: Belt tensioning is by use of screw adjustment at

the head drum

Speed wheel: Designed to stop plant feed if the discharge

conveyor slows or stops

DUST SUPPRESSION SYSTEM

Spray bars with atomiser nozzles mounted over product conveyor & final conveyor discharge, piped to an inlet manifold for customer water supply or optional pump.

Type: Clean water multi atomising nozzles


Inlet: Single point on chassis

Inlet pressure: 3 bar (44psi)

Water supply: 24 litres (6.3 g) per minute min

Frost protection: Via system main valves

Pump: Optional









♠ OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - ► HAZEMAG CRUSHER FEATURES
- OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS

POWER UNIT & HYDRAULICS

Tier 3 Equivalent: Caterpillar C-13 ACERT, 6 cylinder, 328

kW (440hp)

Operating Conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected.

Operating rpm range: 1700 - 2100rpm **Emission control technique**: Not applicable

Plant drive: High quality tandem pumps driven via

engine PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Tier 4F / Stage V: Scania DC13 385A - 368kW (494hp)

Operating conditions: Ambient temp. $+30^{\circ}$ C to -5° C

(86°F to 23°F) at altitudes up to 2000m (6562ft) above sea level - For applications outside this range please consult with Powerscreen as the plant performance /

reliability may be affected

Operating rpm range: 1500 - 1900rpm

Emission control technique: Selective Catalytic Reduction (SCR)

Reductant tank size: 60 L (16 US Gal)

Plant drive: High quality pumps driven via clutch

PTO's

Clutch type: DESCH REVOX 14" WET CLUTCH

Fuel tank capacity: 1000 L (264 US Gal)

Hydraulic tank capacity: 740 L (195 US Gal)

Crusher drive: Direct drive via wedge belts, clutch pulley diameter 425mm T4,

375mm T3

Crusher pulley diameter 800mm Terex

(39")

800mm with Hazemag chamber Crushing performance can be tuned, by changing engine speed via the PLC.

Chruscer drive tensioning: VEE belt tensioner system









♠ OVERVIEW

- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- ▶ OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS



HAZEMAG CRUSHER SPECIFICATION

Feed opening: 1360mm x 800mm (54" x 32")

Max lump size*: 500mm³ (20in³) / 860mm (34") diagonally/

1000 x 1000 x 200mm (39 x 39 x 8") slab

*depending on material blow bar specification

Rotor width: 1340mm (53")
Rotor diameter: 1200mm (47")

Number of aprons: 2

Maximum clearance: 273mm (11") on both aprons

Maximum OSS setting: 200mm (8") upper apron, 100mm (4") lower

apron

Minimum CSS setting: 75mm (3") upper apron, 35mm (1.4") lower

apron

Number of blow bars: 4

Blow bar removal: Vertically

Blow bar configuration: 2 full & 2 half (optional 4 full)

Setting adjustment: Hydraulic assist **Overload protection**: Hydraulic

Rotor speeds: 540 - 630rpm (34 - 40m/s) (111 - 131ft/s)

Applications: Demolition / recycling / quarry

Crusher weight: 14,855kg (32,750lbs)

Full blow bar weight: 410kg (904lbs)

Side Liners: 20mm thick, abrasive resistant steel










♠ OVERVIEW


- FEATURES & BENEFITS
- CRUSHER
 - CRUSHER SPECIFICATION
 - ▶ CRUSHER FEATURES
- HOPPER
- VIBRATING GRIZZLY FEEDER
- PRODUCT CONVEYOR
- POWER UNIT & HYDRAULICS
- TRACKS
- PLANT CONTROLS & OTHER
- ► HAZEMAG IMPACT CRUSHER
 - HAZEMAG CRUSHER SPEC
 - HAZEMAG CRUSHER FEATURES
- ▶ OPTIONS
 - OPTIONS 2
 - OPTIONS 3
- POWERSCREEN® PULSE
- DIMENSIONS




Figure 1: Trakpactor 550 - Pre-screen, Standard Product Conveyor

Working Position











SCANIA CV AB

EXECUTIVE ORDER U-R-024-0034 New Off-Road Compression-Ignition Engines

Pursuant to the authority vested in the Air Resources Board by Sections 43013, 43018, 43101, 43102, 43104 and 43105 of the Health and Safety Code; and

Pursuant to the authority vested in the undersigned by Sections 39515 and 39516 of the Health and Safety Code and Executive Order G-14-012;

IT IS ORDERED AND RESOLVED: That the following compression-ignition engine and emission control system produced by the manufacturer are certified as described below for use in off-road equipment. Production engines shall be in all material respects the same as those for which certification is granted.

MODEL YEAR	ENGINE FAMILY	DISPLACEMENT (liters)	FUEL TYPE	USEFUL LIFE (hours)		
2018	JY9XL12.7DAA	12.7	Diesel	8000		
SPECIAL	FEATURES & EMISSION (CONTROL SYSTEMS	TYPICAL EQUIPMENT APPLICATION			
Cooler, Module, D DC1308	ic Direct Injection, Turboo Exhaust Gas Recirculatio iesel Oxidation Catalyst (5A), Smoke Puff Limiter, action-Urea, Ammonia Ox	on, Engine Control Except Engine Code Selective Catalytic	Crane, Loader, Tractor, Dozer, Pump, Cor	npressor, Generator		

The engine models and codes are attached.

The following are the exhaust certification standards (STD) and certification levels (CERT) for non-methane hydrocarbon (NMHC), oxides of nitrogen (NOx), or non-methane hydrocarbon plus oxides of nitrogen (NMHC+NOx), carbon monoxide (CO), and particulate matter (PM) in grams per kilowatt-hour (g/kw-hr), and the opacity-of-smoke certification standards and certification levels in percent (%) during acceleration (Accel), lugging (Lug), and the peak value from either mode (Peak) for this engine family (Title 13, California Code of Regulations, (13 CCR) Section 2423):

RATED				E	KHAUST (g/kw-hi	7)		OP	ACITY (%	6)
POWER CLASS	STANDARD CATEGORY		NMHC	NOx	NMHC+NOx	co	PM	ACCEL	LUG	PEAK
130 ≤ KW ≤ 560	Tier 4 Final	STD	0.19	0.40	N/A	3.5	0.02	N/A	N/A	N/A
		CERT	0.08	0.19		0.2	0.02			

BE IT FURTHER RESOLVED: That for the listed engine models, the manufacturer has submitted the information and materials to demonstrate certification compliance with 13 CCR Section 2424 (emission control labels), and 13 CCR Sections 2425 and 2426 (emission control system warranty).

Engines certified under this Executive Order must conform to all applicable California emission regulations.

This Executive Order is only granted to the engine family and model-year listed above. Engines in this family that are produced for any other model-year are not covered by this Executive Order.

Executed at El Monte, California on this ___

_ day of February 2018.

Annette Hebert, Chief

Emissions Compliance, Automotive Regulations and Science Division

ATTACHMENTIOFI Engine ModelsEZ U-R-024-0034 1/17/2018

Engine Family	Code	2.Engine Model	3.Dis- placement	4.Power kW @RPM	mm/stroke @ peak HP	6.Fuel Rate: (lbs/hr) @ peak HP	7.Torque Nm @ RPM	8.Fuel Rate: mm/stroke@ peak torque	9.Fuel Rate: (lbs/hr)@ peak torque	10 Emission Control Davice
Y9XL12.7DAA	DC13 084A	2133500	12.7	294 @ 2100	198	140	2157 @ 1200	290	117	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 084A	2133501	12.7	331 @ 2100	222	157	2255 @ 1300	307	134	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133502	12.7	368 @ 2100	245	173	2373 @ 1300	325	142	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 085A	2133503	12.7	405 @ 1900	344	243	2373 @ 1300	394	172	DDI, ECM, TC, CAC, EGR, SPL, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245984	12.7	257 @ 1800	193	117	1638 @ 1300	219	96	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2258254	12.7	257 @ 2100	175	124	1720 @ 1300	232	102	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 087A	2245985	12.7	283 @ 1800	211	149	1765 @ 1300	238	104	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
Y9XL12.7DAA	DC13 089A	2245986	12.7	257 @ 1800	193	117	1600 @ 1300	215	94	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX
JY9XL12.7DAA	DC13 089A	2245987	12.7	283 @ 1800	211	128	1780 @ 1300	240	105	DDI, ECM, TC, CAC, EGR, SPL, DOC, SCR, AMOX

Exhibit E Tables and Forms



Texas Commission on Environmental Quality Air Quality Standard Permit for Permanent Rock and Concrete Crushers Registration Checklist

The following checklist has been developed to help the Texas Commission Environmental Quality (TCEQ), Air Permits Division (APD) confirm that the permanent rock or concrete crusher meets the standard permit requirements. Please read all questions and check "YES," "NO," or "N/A" or give specific information for the facility. If the permanent rock or concrete crusher plant does not meet all conditions of this standard permit, it will not be allowed to operate under the standard permit and must apply for a case-by-case preconstruction permit as required under Title 30 Texas Administrative Code § 116.111 (30 TAC § 116.111).

Please Check The Type of Facility: Rock Crusher Concrete Crusher									
CONDITION NUMBER AND DESCRIPTION									
(1)(B)	If crushing concrete, will the concrete crushing facility be operated at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship at the time this application is filed?	YES NO N/A							
	(The measurement of distance shall be taken from the point on the concrete crushing facility that is nearest to the residence, school, or place of worship toward the point on the building in use as a residence, school, or place of worship that is nearest the concrete crushing facility.)								
(1)(C)(ii)	In lieu of meeting the distance requirements of (1)(B), will the structure(s) within 440 yards of the concrete crushing facilities be occupied or used solely by the owner of the facility or the owner of the property upon which the facility is located?	☐ YES ☐ NO 🗹 N/A							
(1)(D)	In lieu of meeting the distance requirements in (1)(B), will all the following occur:								
(1)(D)(i)	Will this plant be engaged in crushing concrete and other materials resulting from the demolition of a structure on this site and will the concrete and other materials being crushed be used primarily at this site?	☐ YES ☐ NO 🗹 N/A							
(1)(D)(ii)	Will this plant operate onsite for one period of 180 calendar days or less?	☐ YES ☐ NO ☑ N/A							
(1)(D)(iii)	Will all applicable conditions stated in commission rules, including operating conditions be met?	☐ YES ☐ NO 🗹 N/A							
(1)(D)(iv)	Will the plant be located in a county with a population of 2.4 million or more persons, or in a county adjacent to such a county?	☐ YES ☐ NO 🗹 N/A							
(1)(E)	Do you intend to apply for an authorization under Texas Health and Safety Code (THSC) § 382.0518, Preconstruction Permit, for any other crushing facility to be located at the same site within 12 months from the date of this authorization?	☐ YES ☑ NO ☐ N/A							



Please Check The Type of Facility: Rock Crusher Concrete Crusher						
CONDITION NUMBER AND DESCRIPTION (continued)						
(1)(F)	Is there a rock crusher (or concrete crusher) authorized under Texas Health and Safety Code (THSC) § 382.0518, Preconstruction Permit, at this site?	☐ YES ☑ NO ☐ N/A				
	Have you withdrawn, within the previous 12 months, an application for authorization of a crushing facility under (THSC) § 382.0518, Preconstruction Permit, at this site?	☐ YES ☑ NO ☐ N/A				
(1)(G)	Are the current registration form PI-1S entitled, "Registration for an Air Standard Permit", Table 17 and supporting information attached or mailed to the TCEQ, including Table 29 (if applicable), control devices and methods explanation, process flow diagram, process description, plot plan, and area map?	✓ YES ☐ NO ☐ N/A				
	Is the company's compliance history rating poor?	☐ YES ✓ NO ☐ N/A				
(1)(H)	Has construction and/or operation begun on the facility?	☐ YES ☑ NO ☐ N/A				
	Is there a non operational crusher stored onsite?	☐ YES ✓ NO ☐ N/A				
(1)(I)	In accordance with 30 TAC § 116.614, Standard Permit Fees, was a \$900 fee sent to TCEQ Revenue Section?	✓ YES ☐ NO ☐ N/A				
(1)(J)	Will all facilities associated with this application for a standard permit comply with the conditions of Title 40 Code of Federal Regulations (40 CFR) Part 60, Subpart A, General Provisions and Subpart OOO, Standards of Performance for Nonmetallic Mineral Processing Plants?	✓ YES ☐ NO ☐ N/A				
(1)(K)	Will these crushing facilities only process nonmetallic minerals or a combination of nonmetallic minerals as described in 40 CFR Part 60, Subpart OOO?	✓ YES ☐ NO ☐ N/A				
(1)(L)	Is 30 TAC Chapter 101, Subchapter H, Division 3, Mass Emissions Cap and Trade Program; or 30 TAC Chapter 117, Control of Air Pollution from Nitrogen Compounds applicable to this plant?	☐ YES ☐ NO 🗹 N/A				
(1)(M)	Will written records be kept for a rolling 24-month period at the site and made available at the request of any personnel from the TCEQ or any air pollution control program having jurisdiction?	✓ YES NO N/A				
	Will these written records be maintained onsite to show daily hourly operations and hourly throughput; road and work area cleaning and dust suppression logs; and stockpile dust suppression logs?	YES NO N/A				



Please Che	eck The Type of Facility: Rock Crusher Concrete C	Crusher			
CONDITION NUMBER AND DESCRIPTION (continued)					
(1)(N)	Will this crushing operation and related activities comply with applicable requirements of 30 TAC Chapter 101, Subchapter F, Emission Events and Scheduled Maintenance, Startup, and Shutdown Activities?	YES NO N/A			
(1)(P)	Have maintenance emissions been authorized? (Maintenance emissions are not included in this permit and must be approved under separate authorization.)	☐ YES ☐ NO 🗹 N/A			
	Have start-up and shutdown emissions been authorized? (Start-up and shutdown emissions that will exceed those expected during production operations must be approved under separate authorization.)	☐ YES ☐ NO 🗹 N/A			
	Will start-up and shutdown emissions exceed those expected during production operations?	☐ YES ✓ NO ☐ N/A			
(1)(Q)	Do you intend to authorize any facilities located at the same site as this rock crusher, by 30 TAC Chapter 106, Subchapter E, Aggregate and Pavement or 30 TAC § 106.512, Stationary Engines and Turbines?	☐ YES 🗹 NO ☐ N/A			
PUBLIC N	NOTICE REQUIREMENTS - Detailed Public Notice Information will be Determination of Technical Completeness				
(2)(B)(i)	Will public notice be published no later than 30 days after the application is determined to be technically complete?	YES NO N/A			
OPERATI	IONAL REQUIREMENTS				
(3)(A)	Will the primary crusher throughput exceed 200 tons per hour?	☐ YES ✓ NO ☐ N/A			
(3)(B)	Will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located less than 200 feet from the nearest property line, as measured from the point on the facility nearest the property line?	☐ YES ✓ NO ☐ N/A			
(3)(C)	At the time this application is filed, will the crusher and all associated facilities, including engines and/or generator sets, but not including associated sources, be located at least 440 yards from any building which is in use as a single or multi-family residence, school, or place of worship?	✓ YES ☐ NO ☐ N/A			
	(Distance shall be measured from the point on the facility nearest the residence, school, or place of worship to the point on the residence, school, or place of worship nearest the facility).				



Please Check The Type of Facility:						
	Will the crusher operate at the same time as any other rock crusher, concrete batch plant, or hot mix asphalt plant within a 550 feet radius?	☐ YES ☐ NO 🗹 N/A				
(3)(E)	Will all associated sources, including but not limited to work areas, stockpiles, and roads (except for incidental traffic and the entrance and exit to the site), be located at least 100 ft. from the property line?	✓ YES □ NO □ N/A				
(3)(F)	Will this crushing operation consist of any additional facilities other than one primary crusher, one secondary crusher, one vibrating grizzly, two screens, any conveyors, and one internal combustion engine (or combination of engines) of no more than 1,000 total horsepower?	☐ YES ☑ NO ☐ N/A				
	(Equipment that is not a source of emissions does not require authorization.)					
(3)(G)	Will any of the crushers, associated facilities, and/or associated sources (excluding stockpiles) exceed 2,640 operating hours in any rolling 12-month period?	☐ YES ☑ NO ☐ N/A				
(3)(H)	Will any of the rock crusher/ concrete crusher or associated facilities operate during any time between one hour after official sunset to one hour before official sunrise?	☐ YES ☑ NO ☐ N/A				
(3)(I)	Will all crushers be equipped with runtime meters and will the runtime meters be operating during crushing operations?	YES NO N/A				
(3)(J)	Will permanently mounted spray bars be installed at the inlet and outlet of all crushers, at all shaker screens, and at all material transfer points and used as necessary to maintain compliance with all TCEQ rules and regulations?	✓ YES □ NO □ N/A				
(3)(K)	Will opacity of emissions from any transfer point on belt conveyors or any screen exceed 10 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES ☑ NO ☐ N/A				
	Will opacity of emissions from any crusher exceed 15 percent, averaged over a six-minute period as determined using EPA Test Method 9?	☐ YES 🗹 NO ☐ N/A				
(3)(L)	Will visible emissions leave the property for more than 30 seconds in duration in any six-minute period from the crusher(s), associated facilities, associated sources, and in-plant roads associated with the plant as determined using EPA Test Method 22?	☐ YES 🗹 NO ☐ N/A				



Please Check The Type of Facility: Rock Crusher Concrete Crusher						
OPERATIONAL REQUIREMENTS (continued)						
(3)(M)	Will all in-plant roads and active work are operation of the crusher, associated facility treated at all times with any of the following	ies, and associated sources be				
(3)(M)(i)	Covered with a material such as, but not litire chips?	☐ YES ✓ NO ☐ N/A				
(3)(M)(ii)	Dust-suppressant chemicals?	✓ YES ☐ NO ☐ N/A				
(3)(M)(iii)	Water?	✓ YES ☐ NO ☐ N/A				
(3)(M)(iv)	Paved with a cohesive hard surface that is a	☐ YES ✓ NO ☐ N/A				
(3)(N)	Will all stockpiles be sprinkled with water or covered, as necessary, to minimize dust	✓ YES ☐ NO ☐ N/A				
(3)(O)	Will raw material and product stockpile he	eights exceed 45 ft?	☐ YES ☑ NO ☐ N/A			
(3)(P)	Will the crusher be equipped with a weigh accurately determines the mass of materia	✓ YES ☐ NO ☐ N/A				
(3)(Q)	Will the crusher remain at least 440 yards school, or place of worship when moving	✓ YES ☐ NO ☐ N/A				
		Print Form	Reset Form			



Texas Commission on Environment Quality

Table 17 Rock Crushers

	veeks/year NO tons/year					
Does the facility operate at night? Maximum Plant Production Rates:	× NO tons/year					
Maximum Plant Production Rates:	tons/year					
✓ Primary Crusher Type: Trakpactor 550 200 tons/hour 520000						
	4 /					
Secondary Crusher(s) Type: tons/hour	tons/year					
Tertiary Crusher(s) Type: tons/hour	tons/year					
The Following Pieces of Equipment will be Controlled as Shown:						
Feed Hoppers: None X Water Spray Suction to Baghouse Other:						
All Belt Transfer Points: None X Water Spray Suction to Baghouse Other:						
Inlet of all Crushers: None Water Spray Suction to Baghouse Other:						
Outlet of all Crushers: None 🗵 Water Spray 🗌 Suction to Baghouse 🔲 Other:						
All Shaker Screens: None 🗵 Water Spray 🗌 Suction to Baghouse 🔲 Other:						
If Water Sprays are used, Provide the Following Data:						
Water Flow Rate (gpm): 8-19						
Water Pressure at the Nozzle (psi): 200						
Number of Nozzles at each location: 2-3						
If baghouse is used, attach a Table 11 "Fabric Filters."						
Average material moisture content (%):						
Maximum acreage covered by stockpiles (acres): 1						
Stockpiles have the following controls: None Water Ch	emical					
In-plant roads will be: Paved and Vacuumed Paved and Swept Oiled						
Sprinkled with Water and/or Chemicals						

PRINT FORM

RESET FORM

Texas Commission on Environmental Quality Table 29 Reciprocating Engines

I. Engine Data	l									
Manufacturer:	Model No.			Serial No.			Manufacture Date:			
Scania DC13			er 4f	Unkown						
Rebuilds Date:		No. of C	ylinders:		Compress	ion Ratio): I	EPN:		
		6			17.5:1			DC13 08	85A	
Application: X	Application: □ Gas Compression □ Electric Generation □ Refrigeration □ Emergency/Stand by									
■ 4 Stroke Cycle										
☑ Diesel ☐ Naturally Aspirated ☐ Blower /Pump Scavenged ☐ Turbo Charged and I.C. ☑ Turbo Charged										
☐ Intercooled ☐ I.C. Water Temperature ☐ Lean Burn ☐ Rich Burn										
Ignition/Injection	Timing:	Fixed:				Vari	able: It is v	ariable a	nd not publi	С
Manufacture Horse	power Rat	ing: 500			Proposed	Horsepo	wer Rating:	500		
			Di	ischarge	Parameter	s				
Stack Height (Diameter ((Feet)	Stack Temperature (°F) Exi			Exit	Velocity (FPS)
16 feet 9 inches		0.5 feet			900			150		
II. Fuel Data										
Type of Fuel:	Field Gas		andfill Gas			Natural	Gas 🔲 🛚	Digester C	Gas 🗵 Dies	sel
Fuel Consumption	(BTU/bhp-	hr): 2879	He	eating Va	lue: 19400	BTU/lb	Lowe	er Heating	g Value: 18	300 BTL
Sulfur Content (gra	ins/100 sct	f - weight	%): <1.7							
III. Emission Fa	III. Emission Factors (Before Control)									
NO _X	CC)	SO	2	VOC Formalde		lehyde	PM_{10}		
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.298 17.29	2.61	151.38	<0.002	<1	0.1417	8.22	<0.001	<0.1	0.0149	0.86
Source of Emission	Factors:	Manı Manı	ıfacturer Da	ata	AP-42 ×	Other (sp	ecify): Stat	e of Calif	ornia, Title	13
IV. Emission Fa	ctors (Pos	t Control	l)		1		1			
NO _X	CC)	SO	2	VO	C	Formalo	lehyde	PM_{10}	
g/hp-hr ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv	g/hp-hr	ppmv
0.142 8.22	0.149	8.65		<1	0.05597	3.46	<0.001	<0.1	0.0149	0.86
Method of Emissio			•		an Operatio			djustmen	ıt	
Stratified Charg			C Catalyst		her (Specify					
Note: Must submit a copy of any manufacturer control information that demonstrates control efficiency.										
Is Formaldehyde included in the VOCs? ☐ Yes ☒ No										
V. Federal and State Standards (Check all that apply)										
NSPS JJJJ ☐ MACT ZZZZ ☒ NSPS IIII ☐ Title 30 Chapter 117 - List County:										
VI. Additional Information										
 Submit a copy of the engine manufacturer's site rating or general rating specification data. Submit a typical fuel gas analysis, including sulfur content and heating value. For gaseous fuels, provide mole 										
2. Submit a typical percent of cons	_	anarysis, i	meruaing si	unur cont	ent and nea	ung vaiu	e. For gase	ous ruers,	provide inc	ле
3. Submit description of air/fuel ratio control system (manufacturer information is acceptable).										

Reset Form

Print Form