Plain Language Summary for Concrete Batch Plant Standard Permit Application for Concrete Batch Plant Standard Permit Registration Number 184640L001

The following summary is provided for this pending air permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 3. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

Van Eaton Ready Mix, Inc. (CN *604258707*) has submitted an application to register a *temporary* concrete batch plant under the Air Quality Standard Permit for Concrete Batch Plants for registration number 184640L001. The concrete batch plant (*RN112486741*) will be located *4.7 miles southeast of the intersection of Highway 287 and HWY 6 S (Main St) in Quanah, Hardeman* County.

This registration will authorize the concrete batch plant to have a maximum production rate of *200* cubic yards per hour of concrete and operate up to *1,300* hours per year. Particulate matter will be emitted from the handling of aggregate, cement, and flyash. Roads and traffic areas will be controlled by *watering them* to control dust. Dust from stockpiles will be minimized by *watering*. Enclosures and baghouses will be used to control cement and flyash dust.