

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited.**
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: QuikTrip 4160				2. Regulated Entity No.:						
3. Customer Name: QT South LLC				4. Customer No.: 605786011						
5. Project Type: (Please circle/check one)		New <input checked="" type="checkbox"/>		Modification		Extension		Exception		
6. Plan Type: (Please circle/check one)		WPAP <input checked="" type="checkbox"/>	CZP	SCS	UST <input checked="" type="checkbox"/>	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)		Residential		Non-residential <input checked="" type="checkbox"/>			8. Site (acres):		1.89	
9. Application Fee:		\$7,250		10. Permanent BMP(s):				1		
11. SCS (Linear Ft.):		0		12. AST/UST (No. Tanks):				5		
13. County:		Williamson		14. Watershed:				North Fork San Gabriel River		

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	✓
Region (1 req.)	—	—	✓
County(ies)	—	—	✓
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input checked="" type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Rachel Roberts

Print Name of Customer/Authorized Agent

Rachel Roberts

04/21/2023

Signature of Customer/Authorized Agent

Date

****FOR TCEQ INTERNAL USE ONLY****

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Rachel Roberts

Date: 04/21/2023

Signature of Customer/Agent:



Project Information

1. Regulated Entity Name: QT 4160
2. County: Williamson
3. Stream Basin: Unnamed Creek to Unnamed Tributary 1 to Middle Fork San Gabriel River
4. Groundwater Conservation District (If applicable): N/A
5. Edwards Aquifer Zone:
 - Recharge Zone
 - Transition Zone
6. Plan Type:
 - WPAP
 - SCS
 - Modification
 - AST
 - UST
 - Exception Request

7. Customer (Applicant):

Contact Person: Kyla Rudd
Entity: QT South, LLC
Mailing Address: 4705 South 129th East Avenue
City, State: Tulsa, Oklahoma Zip: 74134
Telephone: 918-615-7233 FAX: _____
Email Address: krudd@quiktrip.com

8. Agent/Representative (If any):

Contact Person: Rachel Roberts
Entity: Kimley-Horn
Mailing Address: 10101 Reunion Place, Suite 400
City, State: San Antonio, Texas Zip: 78216
Telephone: 210-762-5289 FAX: _____
Email Address: rachel.roberts@kimley-horn.com

9. Project Location:

- The project site is located inside the city limits of _____.
- The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of Leander, Texas
- The project site is not located within any city's limits or ETJ.

10. The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.
The approximate 1.89-acre site is located southeast of Highway 29 and Kauffman Loop, in Leander, Texas.
The site is currently undeveloped.

11. **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.

12. **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached.
The map(s) clearly show:

- Project site boundaries.
- USGS Quadrangle Name(s).
- Boundaries of the Recharge Zone (and Transition Zone, if applicable).
- Drainage path from the project site to the boundary of the Recharge Zone.

Drainage path follows San Gabriel River through Recharge Zone.

13. **The TCEQ must be able to inspect the project site or the application will be returned.**
Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

Survey staking will be completed by this date: _____

14. **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- Area of the site
- Offsite areas
- Impervious cover
- Permanent BMP(s)
- Proposed site use
- Site history
- Previous development
- Area(s) to be demolished

15. Existing project site conditions are noted below:

- Existing commercial site
- Existing industrial site
- Existing residential site
- Existing paved and/or unpaved roads
- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Uncleared)
- Other: _____

Prohibited Activities

16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:


- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.


Administrative Information

18. The fee for the plan(s) is based on:

- For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
 - For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
 - For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
 - A request for an exception to any substantive portion of the regulations related to the protection of water quality.
 - A request for an extension to a previously approved plan.
19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:
- TCEQ cashier
 - Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
 - San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)
20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.



Legend
 Property_Boundary



1	DATE:	01/20/2023
	DESIGN:	OG
	DRAWN:	OG
	CHECKED:	AN
	KHA NO.:	069304941


Vicinity Map

SITE INVESTIGATION
 REPORT
 QT 4160
 7601 W SH 29
 GEORGETOWN, TX, 78628



Kimley»Horn

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.




UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

STATE OF TEXAS
TEXAS WATER DEVELOPMENT BOARD

LEANDER NE QUADRANGLE
TEXAS-WILLIAMSON CO
7.5 MINUTE SERIES (TOPOGRAPHIC)

Mapped, edited, and published by the Geological Survey
Control by USGS and NGS/NOAA
Topography by photogrammetric methods from aerial photographs
taken 1962; photo corrected 1962
Polyconic projection: 1877 North American Datum
10,000-foot grid based on Texas coordinate system,
vertical axis
1000-meter Universal Transverse Mercator grid ticks, zone 14,
shown in blue
The difference between 1927 North American Datum and North
American Datum of 1983 (NAD 83) for 7.5 minute intersections is
given in USGS Bulletin 1876. The NAD 83 is shown by dashed
corner ticks
Map photorevised 1976
No major culture or drainage changes observed



ROAD CLASSIFICATION
Heavy duty ——— Light duty - - - - -
Medium duty ——— Unimproved dirt - - - - -
U.S. Route ——— State Route ———
LEANDER NE, TEX.
9000' 7.5' E 004
1967
PHOTOREVISED 1976
DMA 6448 III RIF-SERIES 1982




Regulatory Zones
30 TAC Chapter 213- Edwards Aquifer
Effective May 1985

This map was produced by the Groundwater Planning and Assessment Team of the Texas Commission on Environmental Quality to detail the boundaries of the regulatory zones of the Edwards Aquifer Protection Program, as described in Texas Administrative Code Title 30, Part 1, §213.3. No other claims are made to the accuracy or completeness of the data or to its suitability for a particular use. For more information about the Edwards Aquifer Protection Program, please contact the TCEQ Regional Offices in San Antonio or Austin. Printed June 2006.

Project Description

The approximate 1.89-acre site is located southeast of Highway 29 and Kauffman Loop outside the city limits but inside the ETJ of Leander, Texas. The site is currently undeveloped. The proposed use is a retail gas station development with associated parking, access drive, and utility improvements. A detention pond is required since the site proposes an increase in impervious cover and increased developed flow rates compared to existing drainage conditions. A "jellyfish" water quality structure is proposed onsite to treat stormwater from the site. A proposed series of curb inlets and underground storm sewer system will divert stormwater captured from drainage areas on the site to an inlet in the R.O.W. The runoff volume for the site has been designed utilizing Atlas 14 rainfall depths. No portion of the site is located in the 100-year or 500-year floodplain according to the Federal Emergency Management Agency's (FEMA) Flood Map, FIRM number 48491C0275E, revised September 26, 2008. The site lies within pressure plane 1200 of the City of Leander service area for water and wastewater service. The site's water service connection is proposed from the existing 18" waterline located along Kauffman Loop. Wastewater service is proposed to connect to the existing force main line at the northwest corner of the site at the intersection of Highway 29 and Kauffman Loop. The site also lies within the service area of Pedernales Electric Cooperative (PEC). No overhead power lines are proposed to be relocated. The site is over the Edwards Aquifer Recharge Zone; a Geological Assessment was conducted and is in the following section of this report.



Geologic Assessment of QT 4160, 1.89-Acre Tract, Leander, Williamson County, Texas

MARCH 2023

PREPARED FOR

Kimley-Horn

PREPARED BY

SWCA Environmental Consultants

Texas Board of Professional Geoscientists, Firm Registration No. 50159

**GEOLOGIC ASSESSMENT
OF QT 4160, 1.89-ACRE TRACT, LEANDER, WILLIAMSON
COUNTY, TEXAS**

Prepared for


Kimley-Horn

10101 Reunion Place, Suite 400
San Antonio, Texas 78216

Prepared by

Philip Pearce, P.G.

Kenadi Sutton



SWCA Environmental Consultants

Texas Board of Professional Geoscientists, Firm Registration No. 50159
4949 N. Loop 1604 W, Suite 235
San Antonio, Texas 78249
www.swca.com

SWCA Project No. 79521

March 2023

This page intentionally left blank.

CONTENTS

1	Introduction	1
2	Methodology.....	1
3	Results.....	1
3.1	Project Overview	1
3.2	Geology	3
3.3	Soils	3
3.4	Site Hydrogeologic Assessment	5
4	References	6

Appendices

Appendix A	Texas Commission on Environmental Quality (TCEQ) Forms
	Attachment A – Geologic Assessment Table
	Attachment B – Stratigraphic Column
	Attachment C – Narrative Description of Site Geology
	Attachment D – Site Geologic Map

Figures

Figure 1.	Project Site location map.....	2
Figure 2.	Project Site soils map.....	4

Tables

Table 1.	Project Site Soils Detail	3
Table 2.	Water Levels at Nearby Water Wells	5

This page intentionally left blank.

1 INTRODUCTION

SWCA Environmental Consultants (SWCA) was contracted to conduct a geologic assessment of a 1.89-acre commercial tract of land at the southeast corner of SH-29 and Kauffman Loop in Leander, Williamson County, Texas, the Project Site. The Project Site is a parcel developed as pastureland, zoned for commercial use. The Project Site is wholly within the limits of the Edwards Aquifer Recharge Zone (EARZ).

This narrative geologic assessment accompanies the Texas Commission on Environmental Quality (TCEQ) geologic assessment form TCEQ-0585 completed for the Project in Leander, Williamson County, Texas (Figure 1).

2 METHODOLOGY

Prior to conducting fieldwork, SWCA Environmental Consultants (SWCA) scientists studied documents pertaining to known caves within the vicinity of the Project Site in an attempt to gather information related to documented caves (unpublished data related to SWCA et al. 2008 and other area projects). SWCA also examined aerial photography, mapped fault lines, and Project Site geology prior to fieldwork commencement.

SWCA scientists conducted a field survey on March 2, 2023. The pedestrian survey was completed by walking parallel transects spaced approximately 50 feet apart as directed by the TCEQ in the *Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones* (Rev. 10-01-04). Closer spacing was used where vegetation inhibited clear observation. The SWCA scientist carefully examined all potential karst features for subsurface extent; including depressions, holes, and animal burrows. SWCA used several techniques for this effort, including probing with a digging implement to determine the thickness and consistency of fill material and feeling for air flow, which may indicate the presence of a sub-surface void space. Other techniques included recording notable feature characteristics, such as vegetation types or a semi-circular burrow mound produced by small mammal activity.

3 RESULTS

3.1 Project Overview

The Project Site lies within the Recharge Zone of the Northern Segment of the Edwards Aquifer (TCEQ 2021). The Project Site lies approximately 1.75 miles north of The South Fork of the San Gabriel River. The Project Site elevation is approximately 980-990 feet above mean sea level.




Figure 1. Project Site location map.

3.2 Geology

The Project Site lies within the Edwards Limestone. The geology of the Project Site has been mapped most recently at a useful scale by Collins (2005) and SWCA finds this interpretation of the geology to be generally accurate. A stratigraphic column is included in **Appendix A, Attachment B**.

The Project Site occurs along the Balcones Fault Zone (BFZ) within the Edwards Aquifer Recharge Zone (EARZ). Structural down-warping occurred with the Gulf of Mexico’s ancestral formation during the middle Tertiary. The earth’s crust was stretched in response and the BFZ formed along a zone of weakness, which currently marks the boundary between the Edwards Plateau and the Gulf Coastal Plain in central Texas. This zone is characterized by a series of northeast-trending, predominantly normal, nearly vertical, en echelon faults. No faults are mapped crossing the Project Site (Collins 2005).

Recharge into the Edwards Aquifer primarily occurs in areas where the Edwards Limestone and Georgetown Formation are exposed at the surface. Most recharge is from direct infiltration via precipitation and streamflow loss. Recharge occurs predominantly along secondary porosity features such as faults, fractures, and karst features (caves, solution cavities, sinkholes, etc.). Karst features commonly form along joints, fractures, and bedding plane surfaces in the Edwards Limestone and Georgetown Formation.

3.3 Soils

The Natural Resources Conservation Service (2023) identifies the following two soil unit within the Project Site (**Table 1**):

Table 1. Project Site Soils Detail

Soil Name	Hydric	Hydrologic Soil Group*	Drainage Class	Thickness (inches)
Crawford clay, 1 to 3 percent slopes (CfB)	No	D	Well drained	20-40
Fairlie clay, 0 to 1 percent slopes (FaA)			Moderately well drained	

Data Source: Natural Resources Conservation Service 2023.

* Group D – Soils had very slow infiltration rates when thoroughly wetted and exhibit the highest potential for runoff.




Figure 2. Project Site soils map.

3.4 Site Hydrogeologic Assessment

SWCA identified no manmade or geologic features (including faults) within the Project Site. Due to the lack of naturally occurring geologic or karst features, the overall potential for fluid migration to the Edwards Aquifer within the Project Site appears low compared to background infiltration rates. Based on water levels measured in a nearby water well, the depth to water is approximately 150 feet below the ground surface in the vicinity of the Project Site (**Table 2**) (Texas Water Development Board 2023).

Table 2. Water Levels at Nearby Water Wells

Water Well	Depth to Water (feet)	Groundwater Elevation	Year Measured	Distance from Project (feet)
58-18-802	150	820	1970	5900/6170 SE

Source: Texas Water Development Board 2023

No springs or streams were identified within the limits of the Project Site.

4 REFERENCES

- Collins, E.W., 2005, Geologic Map of the West Half of the Taylor, Texas, 30 X 60 Minute Quadrangle: Central Texas Urban Corridor, Encompassing Round Rock, Georgetown, Salado, Briggs, Liberty Hill, and Leander, University of Texas at Austin, Bureau of Economic Geology, Miscellaneous Map 43, 1:100,000.
- Natural Resource Conservation Service (NRCS). 2023. Soil Survey Staff, Natural Resources Conservation Service, U.S. Department of Agriculture. Web Soil Survey. Available at: <http://websoilsurvey.nrcs.usda.gov/>. Accessed February 2023.
- SWCA Environmental Consultants (SWCA), Smith, Robertson, Elliott, Glen, Klein, & Bell, LLP, Prime Strategies, Inc., Texas Perspectives, Inc. 2008. Williamson County Regional Habitat Conservation Plan. Prepared for Williamson County Conservation Foundation and The Honorable Lisa Birkman.
- Texas Commission on Environmental Quality (TCEQ). 2023. Edwards Aquifer Viewer v3.8. Available at: <http://tceq.maps.arcgis.com/apps/webappviewer/index.html?id=2e5afa3ba8144c30a49d3dc1ab49edcd>. Accessed February 2023.
- Texas Commission on Environmental Quality. (TCEQ). Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones. TCEQ-0585-Instructions (Rev. 10-01-04).
- Texas Water Development Board (TWDB). 2023. Water Data Interactive, interactive GIS database. Available at: <http://www2.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer>. Accessed February 2023.

This page intentionally left blank.

APPENDIX A

Texas Commission on Environmental Quality (TCEQ) Forms

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Philip Pearce, P.G.

Telephone: 210.877.2847

Fax: 210.877.2848

Date: 3/21/2023

Representing: SWCA Environmental Consultants (TBPG Firm Registration #50159) (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



Regulated Entity Name: QT 4160

Project Information

1. Date(s) Geologic Assessment was performed: 3/2/2023


2. Type of Project:

- WPAP
 SCS

- AST
 UST

3. Location of Project:

- Recharge Zone
 Transition Zone



Contributing Zone within the Transition Zone

4. **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

Soil Name	Group*	Thickness(feet)

Soil Name	Group*	Thickness(feet)
Crawford clay, 1 to 3 percent slopes (CfB)	D	1.6-3.6
Fairlie clay, 0 to 1 percent slopes (FaA)	D	1.6-3.6

* Soil Group Definitions (Abbreviated)

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6. **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7. **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
8. **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'
 Applicant's Site Plan Scale: 1" = 30'
 Site Geologic Map Scale: 1" = 30'
 Site Soils Map Scale (if more than 1 soil type): 1" = 83.3'

9. Method of collecting positional data:

- Global Positioning System (GPS) technology.
 Other method(s). Please describe method of data collection: _____

10. The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11. Surface geologic units are shown and labeled on the Site Geologic Map.
12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
- Geologic or manmade features were not discovered on the project site during the field investigation.
13. The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
- There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
- The wells are not in use and have been properly abandoned.
- The wells are not in use and will be properly abandoned.
- The wells are in use and comply with 16 TAC Chapter 76.
- There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A

Geologic Assessment Table

ATTACHMENT B
Stratigraphic Column

Stratigraphic Column

Upper Cretaceous	Upper Confining Units	Navarro and Taylor Groups, undivided; 600 feet thick
		Austin Group; 325–420 feet thick
		Eagle Ford Group; 25–65 feet thick
		Buda Limestone; 40–50 feet thick
		Del Rio Clay; 40–70 feet thick
Lower Cretaceous	Edwards Aquifer	Georgetown Formation; 30–80 feet thick
		Edwards Limestone; Up to 200 feet thick
		Comanche Peak Formation; 80 feet thick
	Lower Confining Units	Walnut Formation; Up to 120 feet thick
		Upper member of Glen Rose Limestone; 500 feet thick

Note: The shaded areas represent the lithology that outcrops in the Project Site.

ATTACHMENT C

Narrative Description of Site Geology

PLEASE REFER TO SECTION 3.2 OF THIS REPORT FOR GEOLOGIC NARRATIVE DESCRIPTION


ATTACHMENT D

Site Geologic Map





 Ked - Edwards Limestone

 Project Site



Williamson County, TX
USGS 7.5' Quadrangle:
Leander NE, TX, 30097-F7
NAD 1983 UTM Zone 14N
30.637°N 97.817°W



1" = 30'

Base Map: ESRI ArcGIS Online, accessed
March 2023
Updated: 3/6/2023
Project No. 79521
Layout: 79521 Geologic Map 17 x 22
Aprx: 79521_qt4160GeologicAssessment



Underground Storage Tank Facility Plan Application

Texas Commission on Environmental Quality

for Storage on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.5(d), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. All components used for this facility are U.L. listed or certified by a 3rd party and are compatible and will function pursuant to 30 TAC §213.5(d) and 30 TAC Chapter 334 Subchapter C. This **Underground Storage Tank Facility Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Rachel Roberts

Date: 04/21/2023

Signature of Customer/Agent:



Regulated Entity Name: Kimley-Horn

Underground Storage Tank (UST) System Information

- Attachment A – Detailed Narrative of UST Facility.** A detailed narrative description of the proposed UST Facility is attached. Note: Example descriptions are provided in the instructions (TCEQ-0583-Instructions)
- Tanks and substance to be stored:

Table 1 - Tanks and Substances Stored

UST Number	Size(Gallons)	Substance to be Stored	Double-wall Tank Material
1	15,000	Unleaded E10	Fiberglass Reinforced Plastic

<i>UST Number</i>	<i>Size(Gallons)</i>	<i>Substance to be Stored</i>	<i>Double-wall Tank Material</i>
2	15,000	Unleaded E10	Fiberglass Reinforced Plastic
3	15,000	Unleaded E0	Fiberglass Reinforced Plastic
4	15,000	Premium	Fiberglass Reinforced Plastic
5	15,000	Diesel	Fiberglass Reinforced Plastic

3. Tanks:

- Attachment B – Manufacturer Information for Tanks.** New or replacement systems for the underground storage of static hydrocarbons or hazardous substances must be double-walled or provide an equivalent method of protection approved by the executive director. Tanks must comply with technical standards as required by 30 TAC 334.45(b) relating to technical standards for new tanks. Manufacturer information is attached.
- Attachment C – Alternative Design and Protection Method for Tanks.** Information required by 30 TAC 334.43, relating to variances and alternative procedures is attached.

4. Piping:

- Attachment D – Manufacturer Information for Piping.** Piping must comply with technical standards as required by 30 TAC 334.45(c) relating to technical standards for new piping. Manufacturer information is attached.
 - Attachment E – Alternative Design and Protection Method for Piping.** Information required by 30 TAC 334.43, relating to variances and alternative procedures is attached.
5. Any new underground storage tank system that does not incorporate a method for tertiary containment shall be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature as required by 30 TAC §213.5(d)(1)(B).
- The UST system(s) will not be installed within 150 feet of a domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
 - Attachment F - Tertiary Containment Method.** The UST system(s) will be required to have tertiary containment provided. A description of the method proposed to provide tertiary containment is attached.
6. Corrosion protection equipment to be installed or type of non-corrodible materials:

Table 2 - Corrosion Protection

<i>Equipment</i>	<i>Corrosion Protection (Method)</i>
Tanks	Fiberglass
Product Delivery Piping	Fiberglass

Equipment	Corrosion Protection (Method)
Vapor Recovery Piping	Fiberglass
Submersible Pumps	Powder Coated, E-coated, and stainless steel
Flex Connector (dispenser end)	Stainless steel
Flex Connector (pump end)	Stainless steel
Riser	Fiberglass

7. Overfill protection equipment to be installed:
- Overfill prevention restrictor positioned at 90% capacity.
 - Overfill prevention valve positioned at 95% capacity.
 - Overfill audible and visual alarm positioned at 90% capacity.
8. Methods for detecting leaks in the inside wall of a double-walled system must be included in the facility's design and construction. The leak detection system must provide continuous monitoring of the system and must be capable of immediately alerting the system's owner of possible leakages. Release detection equipment to be installed: (Check all that apply)
- Central on-site monitor
 - Interstitial tank probes
 - Automatic tank gauge
 - Pump/manway sump probes
 - Observation well probes
 - Mechanical line leak detectors (for pressurized lines only)
 - Automatic (electronic) line leak detectors

Excavation and Backfill

9. The depth of the tank excavation will be sufficient to accommodate piping fall requirements, tank diameter, bedding, and a minimum cover of three (3) feet [30 TAC §334.46].
- The depth of the tank excavation will be 4 to 6 feet.
10. The minimum thickness of the tank bedding will conform to 30 TAC §334.46(a)(5)(C and D).
- The tank bedding thickness will be 12 inches.
11. The material to be used as backfill will conform to 30 TAC §334.46(a)(5)(A and B) and will consist of:
- Clean washed non-corrosive sand
 - Pea gravel
 - Crushed rock
 - Other: _____

12. The slope of the product delivery line(s) will conform to 30 TAC §334.46(c)(2) and will be 1/8" per ft (1/8" per foot minimum).

Site Plan Requirements

Items 13 - 24 must be included on the Site Plan.

13. The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = 30'.
14. 100-year floodplain boundaries:
- The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): DFIRM PANEL 48491C0275E, Dated 9/26/2008
 - Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
 - No part of the project site is located within the 100-year floodplain.
15. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Show lots, recreation centers, buildings, roads, etc.
- The layout of the development is shown with existing contours. Finished topographic contours will not differ from the existing topographic configuration and are not shown.
16. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):
- There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)
 - The wells are not in use and have been properly abandoned.
 - The wells are not in use and will be properly abandoned.
 - The wells are in use and comply with 16 TAC §76.
 - There are no wells or test holes of any kind known to exist on the project site.
17. Geologic or manmade features which are on the site:
- All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.
 - No sensitive geologic or manmade features were identified in the Geologic Assessment.
 - Attachment G - Exception to the Geologic Assessment.** A request and justification for an exception to a portion of the Geologic Assessment is attached.
18. The drainage patterns and approximate slopes anticipated after major grading activities.
19. Areas of soil disturbance and areas which will not be disturbed.
20. Locations of major structural and nonstructural controls. These are the temporary best management practices.
21. Locations where soil stabilization practices are expected to occur.

22. Surface waters (including wetlands).
 N/A
23. Locations where stormwater discharges to surface water or sensitive features.
 There will be no discharges to surface water or sensitive features.
24. Legal boundaries of the site are shown.

UST System Profiles

25. **Attachment H - Profile Drawing(s)**. A profile drawing(s) of the proposed UST system with all components shown and labeled is attached.

Best Management Practices

26. **Attachment I - Initial and Continuing Training**. A description of the initial and continuing training of on-site personnel for operation of release detection equipment is attached. The description should include how personnel will respond to warning and alarm conditions of the leak detection monitoring system.
27. **Attachment J - Release Detection Maintenance**. A description of the program and schedule for maintaining release detection and cathodic protection equipment is attached. Any such equipment should be operated and maintained in accordance with the manufacturer's specifications and instructions.

Administrative Information

28. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.
- The WPAP application for this project was approved by letter dated _____. A copy of the approval letter is attached at the end of this application.
 - The WPAP application for this project was submitted to the TCEQ on 3/22/2023, but has not been approved.
 - A WPAP application is required for an associated project, but it has not been submitted.
 - There will be no building or structure associated with this project. In the event a building or structure is needed in the future, the required WPAP will be submitted to the TCEQ.
 - The proposed UST is located on the **Transition Zone** and a WPAP is not required. Information requested in 30 TAC 213.5 subsection (b)(4)(B) and (C) and (5) is provided with this application. (Forms TCEQ-0600 Permanent Stormwater Section and TCEQ-0602 Temporary Stormwater Section or Stormwater Pollution Prevention Plan/SW3P).
29. UST systems must be installed by a person possessing a valid certificate of registration in accordance with the requirements of 30 TAC Chapter 334 Subchapter I.

30. This facility is subject to and must meet the requirements of 30 TAC Chapter 334, including but not limited to the 30 day construction notification and reporting and cleanup of surface spills and overfills.
31. Upon completion of the tankhold excavation, a geologist must certify that the excavation was inspected for the presence of sensitive features. The certification must be submitted to the appropriate regional office. If sensitive features are found, then excavation near the feature may not proceed until the methods to protect the Edwards Aquifer are reviewed and approved by the executive director.
32. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
33. Any modification of this UST application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

QT #4160 Leander, TX

The proposed new underground storage tank system will consist of five new 15,000 gallon double-walled fiberglass-reinforced plastic (FRP) tanks for the storage of gasoline fuels. Each tank will be equipped with a 4 horsepower, 4-inch diameter submersible pump. Overfill prevention for each tank will be provided by an automatic shut-off valve which will be installed in the tank below the full tube and must be set to shut off flow into the tank when the volume of liquid in the tank reaches no more than 95% of the tank capacity. Spill protection for each tank will be provided by a spill containment manhole which will be fitted on the fill tube of each tank.

Product and vent piping will be U.L. listed fiberglass-reinforced plastic piping. Product lines for unleaded, E0, and premium will be of double-wall construction and will consist of a 2-inch diameter primary pipe with a 3-inch diameter secondary containment. Product lines for diesel will be of double-wall construction and will consist of a 2-inch diameter primary pipe with a 4-inch diameter secondary containment. Vent lines will be 2-inch diameter single-wall pipe for E0 and Diesel products. Vent lines for Unleaded and Premium will be manifolded into a 3-inch diameter single-wall pipe. Sump vent lines will be 4-inch diameter single-wall pipe with an air fan supplying outside air to maintain tank sumps dry. A safety shear valve will be installed on each product line at the dispenser island surface level to assure automatic shut-off of product flow during emergencies. In addition, stainless steel braid flexible connector will be installed at both ends of each product line to connect to the dispenser until and the submersible pump.

The submersible pump housing and pump-end flexible connectors will be installed within a liquid-tight fiberglass-reinforced plastic sump which will provide isolation from the corrosive elements of the backfill material while also providing secondary containment for any leaks from these components. The dispenser-end flexible connector will be similarly isolated by enclosure within a flexible isolation sleeve. The vapor recovery riser, the fill tube riser, and the riser for the automatic tank gauging system will be 4-inch diameter primary fiberglass-reinforced plastic.

The proposed tanks and piping will be monitored for leaks by means of inventory, leak detection, and a line pressure pressured monitor. Each tank will be brined filled with a discrimination sensor which will be installed in the in the interstitial space between the walls of the double-wall tanks. Each of the product piping system will be monitored by pressurized line leak detector which will be installed adjacent to the submersible pump in the tank sump. Two 6-inch diameter and one 12-inch slotted PVC observations well will be installed in the corners of the tank pit excavation. Each tank will also be equipped with an automatic tank gauging probe which will automatically inventory the product volume in the tank. Each product piping line will be equipped with an electronic positive flow shut off that is designed to stop product flow in the even a leak in the product line is detected. The probes and sensors from all tanks, piping, and observation wells will be connected to a programmable control unit to be

located in the store building. This central monitoring unit is designed to provide visual and audible alarms when fuel products, fuel vapors, or any liquid is detected.

ZCL | XERXES®
making a **lasting** difference®

Fiberglass Underground Storage Tanks





ZCL | XERXES

RELIABLE, CORROSION-RESISTANT TANKS

OVER **200,000** FIBERGLASS STORAGE TANKS MANUFACTURED AND SHIPPED IN NORTH AMERICA



A history of **innovation** in the **fuel industry**

When ZCL Composites Inc. and Xerxes Corporation joined in 2007, it brought together North America's two leading fiberglass tank brands: ZCL (founded in 1987) and Xerxes (founded in 1979). Today, ZCL | Xerxes is one of the world's leading innovators in composite tank engineering. Nearly 40 years of manufacturing experience and more than 200,000 tanks manufactured and shipped stand as proof of the reliability and quality of our products.

This solid track record provides our customers with peace of mind, which is why petroleum equipment distributors, fuel marketers and commercial accounts rely on our double-wall tanks for safe underground storage of fuel products. We have provided customers with durable and sustainable products that protect the environment for decades. Our proven track record along with our financial strength assures customers that we will be around to support our industry-leading products and warranties. Currently, 29 of the 30 top c-store marketers¹ choose E15-, E85- and ULSD-compatible, corrosion-resistant fiberglass storage tanks from industry leaders like ZCL | Xerxes.

¹ CSP's Convenience Top 101, <http://www.cspdailynews.com/industry-news-analysis/top-convenience-stores/archive/2015>

Our history of **storage solutions** includes:

- developing the first UL-listed double-wall fiberglass tank
- incorporating our factory-installed hydrostatic monitoring system (TRUCHEK®)
- incorporating our unique 3D glass fabric (Parabeam®) into our tank design



WHY CHOOSE A FIBERGLASS TANK?

Best Product Investment

Fiberglass tanks have rapidly grown in popularity since they were first introduced more than 50 years ago as the corrosion-resistant alternative to underground steel tanks that were rusting, leaking and creating serious environmental damage. Major oil companies and large fuel marketers were the first to realize the benefits of fiberglass over steel for underground tanks. Today, a large majority of North American fuel marketers choose fiberglass, and the preference for fiberglass reaches all segments of the market, including industrial, commercial and government accounts who specify, install and own underground storage tanks. The growing understanding of fiberglass' benefits goes well beyond external corrosion protection with the recognition that fiberglass is corrosion-resistant, both inside and out.

FIBERGLASS OUTPERFORMS STEEL CORROSION RESISTANCE

It's now common knowledge that fiberglass tanks are protected from external rusting due to corrosive soil environments. Today, the widespread use of ethanol-blended gasoline (E10, E15, E85), biodiesel fuels and ultra-low sulfur diesel (ULSD) has shifted the concern about corrosion to include internal protection. Most significantly, new ethanol-blended fuels raise questions about the compatibility of storage tank materials with stored fuel. When today's buyers compare fiberglass and steel tanks they see the clear advantage of our fiberglass tanks, which are not vulnerable to aggressive internal corrosion caused by storage of today's biofuels. The fact that fiberglass tanks are corrosion-resistant both inside and out give them a distinct advantage over steel tanks.

FUEL COMPATIBILITY

Customers today want to be confident that they are choosing a tank material that is compatible with the new fuels as well as traditional fuels. Our UL-listed (1316) and ULC-listed (S615) double-wall fiberglass tanks are UL-compatible with 0-100 percent ethanol storage. They are also warranted for the full range of ethanol-blended gasoline. The correlating UL listing (58) for steel fuel tanks does not require testing for ethanol compatibility. This third-party compatibility verification for fiberglass tanks – that steel tanks do not have – makes fiberglass the clear and superior choice for fuel tanks.






OUR FIBERGLASS TANKS PROVIDE **UNMATCHED BENEFITS**

The ZCL | Xerxes Advantage

ZCL | Xerxes double-wall underground storage tanks offer customers several significant design and performance differences that make them a superior choice to both steel tanks and other fiberglass tanks.



RIB DESIGN FOR STRUCTURAL INTEGRITY

As engineers, system designers and customers compare products, the rib geometry of our tanks is an important consideration in their analysis. Our uniform, high-profile ribs are fabricated directly into the tank cylinder. In some other tanks, ribs are incorporated as a separate step in the manufacturing process. Integrally constructed ribs increase the overall strength of the tank and create a structurally superior product.

30-YEAR WARRANTY

ZCL | Xerxes offers a 30-year limited warranty with no restrictions regarding water-bottom monitoring and removal. In contrast, many steel tank manufacturers now have a 10-year rather than 30-year warranty, and make ongoing maintenance and water-bottom removal a condition of warranty coverage.

PARABEAM®

Our proprietary 3D glass fabric, Parabeam®, also enhances the overall structural integrity of our tank by creating a bond between the tank walls, while providing a free-flowing interstitial space for monitoring capabilities. This technology also eliminates the potential for false alarms (created by fluctuating reservoir levels) that can occur in other hydrostatically monitored tanks.

MAINTENANCE-FREE

The presence of water in the bottom of fuel tanks is a common condition. Maintenance to remove it can be frequent and expensive. The requirement to do so, which is found in most steel-tank warranties, can leave a steel-tank owner vulnerable to a denied warranty claim should the tank corrode internally.

TRUCHEK® CONTINUOUS LEAK DETECTION

Our patented TRUCHEK® hydrostatic tank monitoring system for double-wall tanks is an easy, reliable method for true continuous leak detection and tank-tightness testing. Hydrostatic monitoring – now the industry standard for continuous monitoring – gives tank owners greater peace of mind than with a simple liquid sensor, which can fail to detect an outer-wall breach. (See p. 10 for more information.)



ZCL | XERXES STORAGE TANK SOLUTIONS

Today, double-wall tanks are the industry standard in fuel applications. To meet the needs of our customers we also offer several other fiberglass tank options for a variety of applications and requirements. Our tank options include: double-wall tanks, multicompartment tanks, triple-wall tanks, diesel exhaust fluid tanks and oil-water separators. We also have a tank upgrade system when tank replacement is not viable.

DOUBLE-WALL TANKS

Tank owners and system designers of underground fuel systems need tanks that provide secure storage of fuel over time. ZCL | Xerxes fiberglass double-wall tanks are an excellent solution because they are corrosion-resistant, both inside and out. Our tanks have a proven record of compatibility with traditional petroleum fuel as well as with new biofuels, which are increasing in use. Our double-wall fiberglass tanks are not vulnerable to the corrosion problems inherent in storing ethanol-blended fuels (E10, E15, E85), biodiesel fuels and ultra-low sulfur diesel (ULSD). Nor are they vulnerable to rust caused by corrosive soil environments. Options such as protective coatings and cathodic protection don't guard entirely against external corrosion and rust. This makes ZCL | Xerxes fiberglass double-wall tanks a superior choice for a wider range of fuel applications.

FEATURES

- UL-listed (1316) & ULC-listed (S615) for alcohol fuels
- Secondary containment around full tank circumference
- Dry & hydrostatic monitoring options
- Capacities up to 50,000 gal. (USA)
- Capacities up to 155,000 L (Canada)

MULTICOMPARTMENT TANKS

These tanks are a popular choice among retail gasoline marketers and fleet fueling owners. The ability to store two or three grades or types of fuel in a single tank is particularly appealing when the amount of onsite space makes multiple tanks impossible or difficult. Customers may also find installation and insurance cost savings with a multicompartment tank.

The ZCL | Xerxes double-wall multicompartment tank comes standard with a double-wall bulkhead, while some other tank manufacturers require an upgrade to a double-wall bulkhead. Tanks are available in a wide range of capacities and in diameters of 6 to 10 feet.

FEATURES

- UL-Listed (1316) & ULC-listed (S615) for alcohol fuels
- Secondary containment around full tank circumference
- Dry & hydrostatic monitoring options
- Two- & three-compartment models
- Capacities up to 40,000 gal. (USA)
- Capacities up to 155,000 L (Canada)



TRIPLE-WALL TANKS

Some customers and regulatory agencies now require protection beyond secondary containment. Site conditions that could lead to a requirement for tertiary containment are the following: the presence of sensitive groundwater aquifers, lakes or streams. Our UL-listed triple-wall tank, with an additional Parabeam® interstice, is the innovative and cost-effective answer for this level of containment.

FEATURES

- UL-listed (1316) for alcohol fuels
- Tertiary containment around full tank circumference
- Dry & hydrostatic monitoring options
- Capacities up to 50,000 gal. (USA)
- Capacities up to 155,000 L (Canada)

DIESEL EXHAUST FLUID TANKS

ZCL | Xerxes has become a leading provider of diesel exhaust fluid (DEF) tanks in truck stops and vehicle fleet fuel facilities in the relatively short time DEF has been in demand in North America. Many fueling facilities now need to add bulk storage of DEF to meet the growing number of vehicles with diesel engines that require diesel exhaust fluid. A fiberglass underground storage tank has a number of benefits over the alternatives.

Since DEF cannot be exposed to carbon steel, a tank constructed of fiberglass is the clear choice. Using our fiberglass underground tank avoids the need for protective coatings or linings to protect the integrity of the product.

Underground storage of DEF has clear advantages over aboveground storage, in part because of the product's specific temperature requirements. An underground DEF tank also allows for storage of larger capacities than an aboveground tank and avoids an unsightly, space-consuming aboveground installation.

FEATURES

- Single-wall & double-wall models
- UL label available for future product storage flexibility
- Extensive third-party compatibility testing
- Capacities up to 50,000 gal. (USA)
- Capacities up to 155,000 L (Canada)

OIL-WATER SEPARATORS

With a fiberglass underground tank at the heart of the design, a ZCL | Xerxes oil-water separator incorporates unique refinements within the vessel to create a separator that removes free-floating oils and settleable solids from oil-water mixtures.

A properly sized coalescer is designed to produce effluent quality acceptable to most regulatory requirements for water runoff. Our oil-water separator is an excellent choice for managing water runoff from parking lots or equipment washdown stations.

This product is also available as a UL-listed (2215) and ULC-listed (S656) model.

FEATURES

- UL-listed (2215) & ULC-listed (S656) models available
- Single-wall & double-wall models
- Flexible design options
- Coalescer & gravity-flow models available
- Capacities up to 30,000 gal. (USA)
- Capacities up to 113,000 L (Canada)



ZCL | XERXES STORAGE TANK SOLUTIONS



TANK UPGRADE SYSTEM

In a growing number of situations, secondary containment needs to be added to single-wall tanks, and site challenges make removal of existing tanks either cost-prohibitive or difficult. In instances where tanks are covered or surrounded by buildings, roads or rail lines, adding secondary containment to a single-wall fiberglass or steel tank can be accomplished with our Phoenix System®.

This upgrade system consists of two corrosion-resistant laminates with the proprietary Parabeam® glass fabric between the laminates creating an interstitial space. The interstice can be either dry or hydrostatically monitored. The Phoenix System®, applied onsite by trained installers, is compatible with biofuels, including ethanol-blended fuels and biodiesels.

FEATURES

- ULC/ORD-listed (C58)
- Corrosion-resistant fiberglass system
- Viable alternative in difficult tank replacement situations
- Suitable for both fiberglass & steel tanks



ZCL | XERXES FUEL TANK ACCESSORIES

Your Complete Solution

Today's retail and commercial fueling facilities are sophisticated systems that are installed in a highly regulated environment. While the storage tank is the critical component in an underground fuel system, other important accessories are necessary to provide spill containment, tank anchoring, secondary pipe-drain collection, leak detection and other important functions. ZCL | Xerxes engineers have designed innovative, complementary products that provide system designers and installers with cost-effective, easy-to-install accessories. Very few tank manufacturers provide the wide range of accessories that we can supply. This is yet another example of how our innovative spirit benefits customers.

Installation & Technical Support

ZCL | Xerxes provides a comprehensive Installation Manual and Operating Guidelines (IMOG) document that outlines the proper – yet easy – steps necessary for a successful installation.

LEARN MORE ONLINE

Search our online database (zcl.com) for hundreds of resources for our fuel tanks and accessories, including:

- a pdf version of the Installation Manual
- a video of our Installation Manual
- technical drawings (available in CAD, DWG & BIM)
- guide specifications
- typical installation drawings

CONTAINMENT SUMPS AND COLLARS

Sumps and collars are common accessories found on virtually all double-wall tanks installed today. ZCL | Xerxes offers factory-installed containment collars that provide secondary containment around tank fittings and manways.

Designed to be a custom-match to the collar, our containment sump comes in a variety of models and sizes, all engineered to accommodate different customer preferences and needs. Our sumps and collars are also available in double-wall models, which are growing in popularity given changes to tank regulations.

FEATURES

- Flat-sided & round models for various piping layouts
- Watertight or friction-fit cover & open top options
- Diameters of 42 & 48 inches
- Heights of 36-72 inches
- Field-adjustable heights
- Custom options



ANCHORING SYSTEM

Site-specific installation conditions generally dictate whether a tank-anchoring system is necessary. Some customers choose to anchor all their tanks.

ZCL | Xerxes offers a complete tank-anchoring system, including reinforced precast concrete deadmen (designed to American Concrete Institute standards), fiberglass anchoring straps and galvanized turnbuckles.

Each component is engineered to specific tank sizes and for ease of installation. In most cases, concrete deadmen can be delivered on the same trailer as the tank, which minimizes the shipping cost and assures that deadmen are ready when the tank is set.

FEATURES

- Deadmen sizes for tank diameters 6-12 feet
- Corrosion-resistant anchor straps
- Optional man-out-of-hole straps available
- Galvanized turnbuckles

TRUCHEK® CONTINUOUS MONITORING

TRUCHEK® is the ideal solution to the growing regulatory interest in leak-detection methods that provide true continuous leak detection. Unlike dry interstitial monitoring methods, TRUCHEK® is able to monitor both walls of a tank 24/7 in all installation conditions.


When you order our double-wall tank with the TRUCHEK® option, the interstice is filled at the factory with a calcium-chloride fluid that also partially fills a reservoir, creating an interstitial hydrostatic pressure. An electronic probe placed in the tank's reservoir alarms when the fluid level falls below or rises above the acceptable level.

FEATURES


- 24/7 continuous tank monitoring regardless of installation conditions
- UL-verified as meeting the EPA criteria for tank-tightness testing
- Designed for dry-hole & wet-hole installations

How TRUCHEK® Works


Primary-Tank Leak in Wet Hole or Dry Hole



Secondary-Tank Leak in Dry Hole



Secondary-Tank Leak in Wet Hole



TANK-TIGHTNESS TESTING

Besides providing true continuous monitoring of both tank walls – regardless of site conditions – TRUCHEK® also provides a simple and precise method to perform tank-tightness tests. A 10-hour tightness-test procedure meets the strict NFPA329 criteria. A 4-hour test (while product is dispensing) exceeds EPA's criteria for a tank-tightness test.

Underground Double-Wall Tank Data

	Nominal Capacity (gallons)	Tank Length (feet/inches)	Nominal Shipping Weights (lbs) (dry interstitial)	Nominal Shipping Weights (lbs) (wet interstitial)	Number of Anchor Straps Required	Nominal Capacity (liters)	Tank Length (mm)	Nominal Shipping Weights(Kg) (dry interstitial)	Nominal Shipping Weights (Kg) (wet interstitial)	Number of Anchor Straps Required
4'	600	7'-3 1/2"	900	1,100	2	2,500	2,303	400	500	2
	1,000	11'-7 1/2"	1,100	1,300	2	3,900	3,395	500	600	2
	2,000	22'-3 5/8"	2,800	3,400	2	5,000	4,380	600	700	2
6'	2,500	13'-5 3/4"	2,200	2,800	2	10,000	4,520	900	1,100	2
	3,000	16'-4 1/4"	2,600	3,300	2	15,000	6,604	1,300	1,600	4
	4,000	20'-8"	3,600	4,400	2	20,000	8,465	1,700	2,000	4
	5,000	26'-5"	4,300	5,200	4	25,000	10,420	2,200	2,500	4
	6,000	30'-8 3/4"	5,000	6,100	4					
8'	4,000	15'- 1/2"	2,700	3,600	2	15,000	3,994	900	1,100	2
	5,000	17'-8 1/2"	3,200	4,200	2	20,000	5,137	1,200	1,500	2
	6,000	20'-6 1/2"	3,700	4,900	2	25,000	6,090	1,400	1,700	2
	8,000	26'- 1/2"	4,800	6,200	4	30,000	7,264	1,700	2,100	4
	10,000	31'-6 1/2"	5,900	7,500	4	35,000	8,185	2,000	2,300	4
	12,000	37'- 1/2"	7,000	8,800	4	40,000	9,392	2,300	2,700	4
	15,000	46'- 9"	9,100	11,200	6	45,000	10,363	2,500	3,000	4
						50,000	11,328	2,700	3,200	4
10'	10,000	21'-5 1/4"	4,900	6,400	4	50,000	7,449	2,900	3,300	4
	12,000	24'- 1/4"	5,600	7,200	4	55,000	8,280	3,200	3,600	4
	15,000	29'-5 3/4"	7,000	8,900	4	60,000	8,827	3,300	3,800	5
	20,000	37'-8 3/4"	9,000	11,300	6	65,000	9,576	3,600	4,200	5
	25,000	47'-6 3/4"	11,800	14,600	8	70,000	10,395	3,900	4,500	6
	30,000	55'-9 3/4"	14,000	17,200	10	75,000	10,903	4,100	4,700	6
	35,000	64'- 3/4"	16,500	20,100	12	80,000	11,582	4,400	4,900	6
	40,000	73'-8 1/4"	19,000	23,100	14	85,000	12,268	4,700	5,300	7
						90,000	13,068	5,000	5,600	7
						100,000	14,345	5,400	6,100	8
12'	20,000	29'- 4"	14,000	16,700	6	110,000	15,723	5,900	6,700	9
	25,000	35'- 7"	16,600	19,700	8					
	30,000	43'- 1"	19,900	23,500	10					
	35,000	49'- 4"	22,500	26,500	12					
	40,000	54'- 4"	24,600	28,900	12					
	45,000	60'- 7"	27,400	32,100	16					
	48,000	65'- 7"	29,500	34,500	18					
	50,000	68'- 1"	30,500	35,700	18					


Notes:

1. Tank data for multicompartment tank models is available at www.zcl.com.
2. Actual height of the tank may be greater than the actual diameter due to fittings and accessories. Load height during shipping may vary due to tank placement on the shipping trailer.
3. If an overflow-protection device is installed in the tank, the actual capacity will be reduced.

Multiple Facilities

Customers Can Rely on Timely Manufacturing and Delivery of Tanks and Accessories.

With six manufacturing facilities – four in the United States and two in Canada – no matter where customers need fiberglass tanks and accessories shipped, a ZCL | Xerxes manufacturing facility is not far away. No other tank producer offers this kind of manufacturing capability in North America. All our facilities are either UL-listed or ULC-listed.



Contact Us

We're ready to design a double-wall tank, multi-compartment tank, triple-wall tank, diesel exhaust fluid tank or oil-water separator for your next project.

On the Web:
www.zcl.com

Technical Support:
1.800.661.8265
USA: 952.887.1890
Email: eng.support@zcl.com

Corporate Head Office

ZCL Composites Inc.
1420 Parsons Road SW
Edmonton, AB T6X 1M5

US Office

Xerxes Corporation
7901 Xerxes Avenue S
Minneapolis, MN 55431

Manufacturing Facilities:

Canada
Edmonton, AB
Drummondville, QC

USA
Anaheim, CA
Seguin, TX
Tipton, IA
Williamsport, MD

Dualoy™ 3000/L Fiberglass Pipe

(Product Data)



Applications

- Service Station
- Vent/Vapor Recovery
- Bulk Plant Terminals
- Fueling Terminals
- Central Fuel Oil Systems
- Marinas Terminals
- Ethanol Fuel Blends
- Diesel Exhaust Fluid
- UL/ULC Systems that require MV, HB, CT, A&M Fuels

Materials and Construction

Filament-wound fiberglass reinforced epoxy pipe with integral epoxy liner and exterior coating. When classified in accordance with ASTM D2310 and ASTM D2996, the pipe meets the following cell limits: RTRP 11CXF1-5420. The operating pressure of the pipe is up to 200 psig (13.8 bar) with continuous operating temperature to 150°F (66°C).

Dualoy 3000/L is Listed with Underwriters Laboratories Standard 971-2004 for nonmetallic underground piping for motor vehicle (MV), high blend (HB), concentrated (CT) and aviation and marine (A&M) fuels (File MH9162). Dualoy 3000/L pipe and fittings are

also Listed with Underwriters Laboratories of Canada (File CMH 715). In Great Britain the Dualoy 3000/L system has been tested and accepted by the London Fire and Civil Defence Authority. Dualoy 3000/L has been issued a Certificate of Compliance to the Institute of Petroleum (IP) Specification by ERA Technology, Ltd.

Performance

Individual system components may not have the same ratings as the pipe. Refer to the detailed product information for the specific components to determine the pressure rating for the system as a whole.

Fittings

Compression-molded and filament-wound fiberglass reinforced epoxy.

For dimensions of fittings, consult publication Dualoy 3000/L Fittings Dimensions.

Pressure ratings of fittings without UL listing are available on request

Joining System

- **Bell & Spigot** - The primary joining method for fitting joints.

Nominal Dimensional Data

Pipe Size		Inside Diameter		Outside Diameter ⁽¹⁾		Wall Thickness				Capacity		Weight		Max. Deflection per 20 ft Joint	Min. Length Req. for 10° Change		Stiffness Factor ⁽²⁾	
						Total		Structural										
in	mm	in	mm	in	mm	in	mm	in	mm	gal/ft	l/m	lb/ft	kg/m	deg	ft	m	lb•in ³ /in ²	N•m
2	50	2.21	56	2.37	60	0.080	2.03	0.060	1.5	0.20	2.50	0.47	0.70	15	13	4	45	5.1
3	80	3.32	84	3.50	89	0.085	2.16	0.065	1.6	0.45	5.60	0.72	1.07	9	22	7	75	8.5
4	100	4.33	110	4.50	114	0.087	2.21	0.070	1.8	0.77	2.92	1.00	1.49	7.5	27	8	60	6.8
6	150	6.39	162	6.63	168	0.120	3.10	0.100	2.5	1.67	6.35	2.10	3.13	5	40	12	275	31.1

⁽¹⁾ Typical outside diameters of 2 through 6-inch pipe are within API, ASTM and ANSI fiberglass and steel pipe dimensions.

⁽²⁾ At 5% deflection.

View of Joint Illustrations (Joint illustration only depicts type of connection available, not type of pipe featured in data sheet)



Bell & Spigot

Typical Pipe Performance

Nominal Pipe Size		Pressure Rating ⁽¹⁾		Ultimate Internal Pressure ⁽¹⁾		Ultimate Collapse Pressure ⁽²⁾	
in	mm	psig	MPa	psig	MPa	psig	MPa
2	50	200	2.07	3200	22.1	153	1.05
3	80	200	1.38	2400	16.5	90	0.62
4	100	175	1.21	2000	13.8	39	0.27
6	150	175	1.21	2000	13.8	38	0.26

⁽¹⁾ At 80°F (27°C).

⁽²⁾ At 80°F (27°C). For continuous service do not exceed 75% of these values.

Typical Mechanical Properties

Pipe Property ⁽¹⁾	Method		
Tensile Strength			
Longitudinal	35,000 psi	241.3 MPa	ASTM D2105
Circumferential	70,000 psi	482.7 MPa	ASTM D1599
Poisson's Ratio $v_{ha}^{(2)} - v_{ha}^{(3)}$	0.16 - 0.26		FGSTM
Tensile Modulus			
Longitudinal	25,000 psi	172.4 Mpa	ASTM D2105
Circumferential	38,000 psi	262.0 MPa	FGSTM
Compressive Strength			
Longitudinal	24,500 psi	168.9 MPa	FGSTM
Compressive Modulus			
Longitudinal	26,000 psi	179.3 MPa	FGSTM
Cyclic	8,000 psi	55.2 MPa	ASTM D2992 Procedure A

Typical Physical Properties

Pipe Property	Value	Value	Method
Thermal Conductivity	1.7 BTU-in/hr·ft ² ·°F	7.6 W/m·°C	ASTM C177
Thermal Expansion	8.5 x 10 ⁻⁶ in/in·°F	15.3 x 10 ⁻⁶ cm/cm·°C	ASTM D696
Friction Factor	Hazen-Williams 150.0		-
Absolute Roughness	0.00021 in	0.00053 mm	
Specific Gravity	1.8		ASTM D792
Barcol Hardness	65.0 (Impressor 934-1)		ASTM D2583

⁽¹⁾ Based on structural wall thickness.

⁽²⁾ v_{ha} = The ratio of axial strain to hoop strain resulting from stress in the hoop direction.

⁽³⁾ v_{ah} = The ratio of hoop strain to axial strain resulting from stress in the axial direction.

Pipe Length

Size		Standard		Random	
in	mm	ft	m	ft	m
2-6	50-150	20	6.1	17-21	5.2 - 6.4

Minimum Bending Radius

Size		Minimum Bending Radius ⁽¹⁾	
in	mm	ft	m
2	50	75	23
3	80	100	38
4	100	150	46
6	150	200	61

⁽¹⁾ At rated pressure. Sharper bends may create excessive stress concentrations. Do not bend pipe until adhesive has cured.

National Oilwell Varco has produced this brochure for general information only, and it is not intended for design purposes. Although every effort has been made to maintain the accuracy and reliability of its contents, National Oilwell Varco in no way assumes responsibility for liability for any loss, damage or injury resulting from the use of information and data herein nor is any warranty expressed or implied. Always cross-reference the bulletin date with the most current version listed at the web site noted in this literature.

Fiber Glass Systems

17115 San Pedro Avenue, Ste 200
 San Antonio, Texas 78232 USA
 Phone: 210 477 7500
 Fax: 210 477 7560

Dualoy® 3000/L Secondary Containment Pipe and Fittings

Uses and Applications

- Service station product, vent and vapor recovery piping
- Bulk plant terminals and fueling terminals
- Central fuel oil systems
- Marinas and marine terminals (onshore only)
- All piping systems requiring UL or ULC Listing for MV, HB, CT and A&M fuels
- Containment piping for all of the above

Description

Dualoy 3000/L secondary containment systems require pipe one size larger than the primary and specially designed fittings. The system provides complete enclosure of UL- and ULC-Listed Dualoy primary piping used in product lines and vapor recovery lines from the sump at the product storage tank to the shear valve connector at the dispenser, and vent lines from the tank. Dualoy containment systems have been sized for close make-up and ease of installation.

Features of Dualoy 3000/L containment systems include:

- Filament-wound, fiberglass-reinforced pipe with integral liner;
- Compact fittings dimensions to minimize trench excavation;
- Smooth exterior pipe surface that eliminates the need for special end preparation tools;
- Ready accessibility to and complete inspectability of primary fittings prior to closure of the containment;
- Complete testability during installation and at any time thereafter;
- Rapid joint makeup with pre-inserted nuts and ambient cure adhesive.

Listings

Dualoy 3000/L is Listed in the United States with Underwriters Laboratories Standard 971-2004 for nonmetallic underground piping for motor vehicle (MV), high blend (HB), concentrated (CT) and aviation and marine (A&M) fuels for both primary and contained piping systems (File MH9162). Dualoy 3000/L pipe and fittings are also Listed with Underwriters' Laboratories of Canada (File CMH715). In Great Britain the Dualoy/3000L system has been tested and accepted by the London Fire and Civil Defense Authority. Dualoy 3000/L has been issued a Certificate of Compliance to the Institute of Petroleum (IP) Specification by ERA Technology, Ltd.

Performance

Operating pressures to 100 psig

Continuous operating temperatures to 150°F (66°C)

Individual system components may not have the same ratings as the pipe. Refer to the detailed product information for the specific components to determine the pressure rating for the system as a whole.

Secondary employs full-performance pipe — Many contained fuel handling systems employ materials in the secondary that fall far short of the primary piping in regard to chemical resistance and mechanical strength. By contrast, Dualoy 3000/L systems are manufactured with the same high-performance fiberglass-reinforced pipe in the secondary as in the primary. Thus, Dualoy 3000/L containment systems easily withstand both high external loads from backfill and traffic as well as internal pressures as high as 100 psig.

Compact containment fittings — Dualoy 3000/L containment fittings are compact clamshell-type closure pieces. Crossovers can be made with the same centerline-to-centerline dimension as single-wall system.

Piping System Characteristics


Precision pipe exterior eliminates scarfing — Dualoy pipe is manufactured in a proprietary continuous winding process that provides an extremely precise, consistent outside diameter. Light sanding of the pipe end to remove the surface gloss and obtain a suitable bonding surface is the only end prep required, although the scarfing feature of tapering tools can be used.

Easy containment fitting assembly — Dualoy 3000/L containment fitting clamshells are supplied in matched pairs. One half of each pair is fitted with pre-inserted propeller nuts, allowing the fitting to be assembled from one side, using the bolts provided.

Complete retestability — Dualoy 3000/L containment employs rigid-wall pipe and fittings that maintain their slope during the entire service life of the station. When installed with isolating penetration fittings (see page 3), Dualoy 3000/L containment piping can be repeatedly retested whenever desired.

Convenient repair capability — Contained piping systems are occasionally damaged after installation. Damage is generally caused by paving or excavation operations. Dualoy3000/L contained piping systems are designed so that only the damaged section need be replaced instead of the entire line. The 2-inch Dualoy repair coupling is sized so that it can be contained within 4-inch Dualoy 3000/L containment pipe.

Two-inch primary pipe contained within 3-inch containment pipe can be repaired with a UL-listed 2-inch repair coupling. The containment is restored by replacement of a section of the existing containment pipe with a 4-inch containment nipple. The 4-inch replacement nipple is then joined to the existing containment pipe with Dualoy reducing couplings.




Containment Pipe and Fittings Dimensions

Pipe


Nominal Pipe Size		A	B	C	X ₂	No. of Bolt Holes	Wt. lb
in	mm	in	in	in	in		
3	80	3.50	3.32	—	—	—	0.72
4	100	4.50	4.33	—	—	—	1.00
6	150	6.63	6.39	—	—	—	2.10

90° Elbows




3	80	4.28	7.28	—	1.50	5	1.1
4	100	4.77	8.25	—	1.50	5	1.3
6	150	5.62	10.53	—	2.00	8	1.5

45° Elbows




3	80	3.50	6.00	—	1.50	5	0.8
4	100	3.75	7.00	—	1.50	5	1.2
6	150	6.32	9.75	—	2.00	8	1.5

Tees




Nominal Pipe Size		A	B	C	X ₂	No. of Bolt Holes	Wt. lb
in	mm	in	in	in	in		
3	80	4.28	7.24	8.56	1.50	5	1.2
4	100	4.78	8.25	9.58	1.50	5	1.6
6	150	5.72	10.67	11.65	2.00	6	1.7

Couplings



2	50	14.00	4.00	—	1.50	8	1.3
3	80	14.00	6.00	—	1.50	8	1.7
4	100	14.00	7.00	—	1.50	8	2.0
6	150	5.37	9.75	—	4.00	10	2.0

Reducers, Plain and with 3/4 inch NPT Outlet




3 x 1½	80 x 40	6.25	4.48	6.10	1.50	4	0.6
3 x 1½	80 x 40	6.25	4.47	6.10	1.50	4	1.1 ⁽¹⁾
3 x 2	80 x 50	6.25	4.90	6.10	1.00	4	0.7
3 x 2	80 x 50	6.25	4.90	6.10	1.00	4	1.1 ⁽¹⁾
4 x 3	100 x 80	7.00	6.00	7.00	1.50	4	0.9
4 x 3	100 x 80	7.00	6.00	7.00	1.50	4	2.0 ⁽¹⁾
6 x 4	150 x 100	7.17	7.62	9.74	2.00	6	1.0

(1) Ported reducer

Sump Penetration Fittings

Sump penetrations are designed for use at turbine sumps and dispenser pans. Plain sump penetration fittings permit the annular space between the primary and secondary lines to communicate with the interior of the sump or pan. Penetration fittings with factory-installed centralizers, sleeve couplings and monitoring ports may be used to isolate the pipe annular space from the sump or pan. When the annular space is so isolated, the secondary containment line can be retested at any time and as often as desired.



National Oilwell Varco has produced this brochure for general information only, and it is not intended for design purposes. Although every effort has been made to maintain the accuracy and reliability of its contents, National Oilwell Varco in no way assumes responsibility for liability for any loss, damage or injury resulting from the use of information and data herein nor is any warranty expressed or implied. Always cross-reference the bulletin date with the most current version listed at the web site noted in this literature.

North America

17115 San Pedro Ave. Suite 200
San Antonio, Texas 78232 USA
Phone: 210 477 7500

South America

Avenida Fernando Simoes
Recife, Brazil 51020-390
Phone: 55 31 3326 69020

Europe

P.O. Box 6, 4190 CA
Geldermalsen, The Netherlands
Phone: 31 346 587 587

Asia Pacific

No. 7A, Tuas Avenue 3
Jurong, Singapore 639407
Phone: 65 6861 6118

Middle East

P.O. Box 17324
Dubai, UAE
Phone: 971 4881 3566

www.fgspipe.com • fgspipe@nov.com

NOV Fiber Glass Systems

©2013 National Oilwell varco. All rights reserved.
FH3510 March 2013

GASOLINE SYSTEM, TANK & DISPENSER PIPING GENERAL NOTES

GENERAL NOTE:

A. IT IS REQUIRED THAT ONLY "CERTIFIED INSTALLERS" BE USED FOR INSTALLATION OF THE PIPING SYSTEM TO INSURE THAT PROPER PIPE FABRICATION, COUPLING AND INSTALLATION PERFORMED. "CERTIFIED INSTALLERS" ARE EQUIPPED WITH FACTORY MANUFACTURED COUPLING EQUIPMENT AND INSTALLATION TOOLS AND HAVE RECEIVED FACTORY TRAINING BY AMERON REPRESENTATIVE ON THE PROPER INSTALLATION AND TESTING PROCEDURES.

THIS ENVIRONMENTALLY SAFE FRP UNDERGROUND PIPING SYSTEM PROVIDES PIPING RUNS BETWEEN USTS AND THE PRODUCT DISPENSERS.

B. ALL PRODUCT PIPING IS TO BE PRIMARY FUEL OF SPECIFIED DIAMETER IN SECONDARY PIPING OF SPECIFIED DIAMETER. PIPING TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

C. WHERE FLEX CONNECTORS ARE COMPLETELY CONTAINED (NOT IN CONTACT WITH GROUND WATER, NATIVE SOIL OR BACKFILL MATERIAL), STAINLESS STEEL CONNECTORS ARE ACCEPTABLE. WHERE FLEX CONNECTORS ARE NOT COMPLETELY CONTAINED ISOLATION BOOTS OR PRIME AND WARP SHALL BE USED TO SEPARATE CONNECTOR FROM COMING INTO CONTACT WITH GROUND WATER, NATIVE SOIL OR BACKFILL MATERIAL. ALL FLEX CONNECTORS SHALL BE INSTALLED AS STRAIGHT AS POSSIBLE.

D. THE GENERAL CONTRACTOR ACCEPTS FULL RESPONSIBILITY FOR PROPER HANDLING AND INSTALLATION OF PIPING SYSTEM. THE GENERAL CONTRACTOR SHALL INSURE THAT GOOD WORKMANSHIP AND CONSTRUCTION PROCEDURES ARE FOLLOWED THROUGHOUT THE INSTALLATION, REGARDLESS OF INCLUSION OR OMISSION OF ANY APPLICABLE SUGGESTION IN THESE INSTRUCTIONS OR ON THE DRAWINGS.

E. UNKNOWN SITUATIONS OR CONDITIONS NOT COVERED IN THESE INSTRUCTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR. MANUFACTURERS SPECIALISTS ARE AVAILABLE FOR CONSULTATION. THE PRESENCE OF THE OWNER'S OR MANUFACTURERS REPRESENTATIVE AT AN INSTALLATION SITE DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR A PROPER INSTALLATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER SAFEGUARDING OF THE INSTALLATION AND MATERIALS AND EQUIPMENT STORED ON THE SITE TO PREVENT THEFT, VANDALISM OR DAMAGE.

RESPONSIBILITY NOTE:

FUEL CONTRACTOR RESPONSIBLE FOR DISPENSER AND SYSTEM START-UP AND CALIBRATION.

CONCRETE NOTE:

ALL CONCRETE SHALL BE 4" THICK, 4000PSI @ 28 DAY READY MIX WITH MAXIMUM 4" SLUMP. FINISH SHALL BE HOOD FLOAT WITH MEDIUM BROOM FINISH.

A MEDIUM BROOM FINISH IS REQUIRED ON THE CONCRETE PAVING LOCATED BETWEEN THE GASOLINE ISLANDS AND THE SIDEWALK IN FRONT OF THE QUIKTRIP BUILDING. CONTRACTOR TO PROVIDE TEST AREA FOR QUIKTRIP REPRESENTATIVE APPROVAL.

SETTLEMENT NOTE:

CAUTION NOTE SETTLEMENT, TANK DISTORTION, OR MOVEMENT IN CONCRETE COVER SLAB CANNOT BE TOLERATED AND IF SPECIFIED MATERIALS ARE USED AND SPECIFIED PROCEDURES ARE FOLLOWED, NO INSTALLATION FAILURE SHOULD OCCUR. THEREFORE, IF ANY MOVEMENT, SETTLEMENT OR DISTORTION OCCURS, IT WILL BE PRESUMED THE CONTRACTOR HAS NOT FOLLOWED THE SPECIFIED INSTRUCTIONS AND PROCEDURES AND THE CONTRACTOR SHALL IMMEDIATELY UNDERTAKE, AT HIS SOLE EXPENSE, ANY NECESSARY CORRECTIVE MEASURES, AS MAY BE APPROVED BY THE QUIKTRIP FIELD REPRESENTATIVE, UP TO AND INCLUDING COMPLETE REMOVAL AND RESETTLEMENT OF ALL UNDERGROUND TANKAGE AT THE SITE. IF IT IS DETERMINED THAT MOVEMENT, SETTLEMENT OR DISTORTION HAS BEEN CAUSED BY FACTORS BEYOND THE CONTRACTOR'S CONTROL, THE COST OF REMEDIAL MEASURES WILL BE BORNE BY OTHERS. THROUGH ACCEPTANCE OF THE GAS CONTRACT, THE GAS INSTALLATION CONTRACTOR DOES HEREBY AGREE TO GUARANTEE THE UNDERGROUND TANKAGE INSTALLATION AGAINST FAILURE AS OUTLINED HEREIN ABOVE, FOR A PERIOD OF ONE (1) YEAR FROM DATE OF FINAL ACCEPTANCE.

TANK BACKFILL REQUIREMENTS

POLICY 2.22.0 - TANK (FIBERGLASS UST) BACKFILL MATERIAL REQUIREMENTS AND COMPLIANCE TO STANDARDS

POLICY

IN ORDER TO ASSURE COMPLIANCE TO UST MANUFACTURER'S REQUIREMENTS FOR UST BACKFILL MATERIALS, PROCEDURES WILL BE FOLLOWED TO MONITOR APPROVAL BY MANUFACTURER, VERIFICATION THAT APPROVED MATERIAL HAS BEEN DELIVERED TO THE SITE, AND DOCUMENTATION ON THE CONSISTENCY OF MATERIAL PLACED IN THE UST EXCAVATION.

PROCEDURE SPECIFICATIONS FOR ACCEPTABLE MATERIALS TO BE USED AS STRUCTURAL SUPPORT FOR FIBERGLASS USTS:

ROUNDED GRAVEL WHEN USING ROUNDED GRAVEL, THE MATERIAL IS TO BE A MIX OF ROUNDED PARTICLES, SIZES BETWEEN 1/8" AND 3/4". THE ROUNDED GRAVEL MUST CONFORM TO THE SPECIFICATIONS OF ASTM C-33, PARAGRAPH 9.1, SIZES 6, 67, OR 7. NO MORE THAN 10% (BY WEIGHT) OF THE BACKFILL MAY PASS THROUGH A #20 SIEVE. THE MATERIAL IS TO BE WASHED, FREE-FLOWING, AND FREE OF ICE, SNOW AND DEBRIS.

CRUSHED STONE WHEN USING CRUSHED STONE, THE MATERIAL IS TO BE A MIX OF ANGULAR PARTICLES, SIZES BETWEEN 1/8" AND 1/2". THE CRUSHED STONE MUST CONFORM TO THE SPECIFICATIONS OF ASTM C-33, PARAGRAPH 9.1, SIZES 7 OR 8. NO MORE THAN 10% (BY WEIGHT) OF THE BACKFILL MAY PASS THROUGH A #20 SIEVE. THE MATERIAL IS TO BE WASHED, FREE-FLOWING, AND FREE OF ICE, SNOW AND DEBRIS.

APPROVAL PROCESS

ROUNDED GRAVEL A SAMPLE CONSISTING OF THREE (3) SEPARATE RANDOM INTERIOR STOCKPILE SAMPLES SHALL BE TAKEN AT THE QUARRY BY THE MATERIALS TESTING COMPANY. CLEAN ONE GALLON SIZED BUCKETS (APPROXIMATE) CAN BE USED FOR SAMPLING.

THE MATERIALS TESTING COMPANY SHALL COMPLETE A SIEVE ANALYSIS ON THIS MATERIAL AS IT HAS BEEN COMBINED. IF THIS MATERIAL MEETS THE ASTM C-33 SPECIFICATIONS, THE ANALYSIS SHALL BE SUBMITTED TO THE TANK MANUFACTURER FOR APPROVAL. THE TANK MANUFACTURER WILL ISSUE AN APPROVAL ON THAT SAMPLE AS REFERENCED TO A SPECIFIC QUARRY. THIS PROCESS SHOULD TAKE ABOUT TWO DAYS.

WITH ROUNDED GRAVEL ONLY, IT WILL NOT BE NECESSARY TO OBTAIN A NEW SAMPLE ON EACH INSTALLATION AS LONG AS THE QUARRY REMAINS THE SAME. AN APPROVAL FROM THE TANK MANUFACTURER WILL ONLY BE NEEDED ONCE TO DOCUMENT THE APPROVAL OF THE ROCK. IT WILL NOT BE NECESSARY TO ASK FOR APPROVAL ON ADDITIONAL INSTALLATIONS, UNLESS THE QUARRY LOCATION CHANGES.

IT WILL BE THE TANK INSTALLATION CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT ANY MATERIAL THAT HAS BEEN APPROVED BY THE TANK MANUFACTURER ALWAYS COMES FROM THE SAME QUARRY, AND REMAINS CONSISTENT.

POLICY 2.22.0 - CONTINUED

CRUSHED STONE

A SAMPLE CONSISTING OF THREE (3) SEPARATE RANDOM INTERIOR STOCKPILE SAMPLES SHALL BE TAKEN AT THE QUARRY BY THE MATERIALS TESTING COMPANY. CLEAN ONE GALLON (APPROXIMATE) SIZED BUCKETS CAN BE USED FOR SAMPLING.

THE MATERIALS TESTING COMPANY SHALL COMPLETE A SIEVE ANALYSIS ON THIS MATERIAL AS IT HAS BEEN COMBINED. IF THIS MATERIAL MEETS THE ASTM C-33 SPECIFICATIONS WITH NO VARIATION, IT WILL NOT BE NECESSARY TO SUBMIT A SIEVE ANALYSIS FOR APPROVAL BY THE TANK MANUFACTURER. IT IS NOT UNCOMMON TO RECEIVE AN ANALYSIS THAT INDICATES MATERIAL SIZES OUTSIDE OF THE ASTM-33 STANDARD. THESE VARIABLE REPORTS WILL NEED TO BE SUBMITTED TO THE TANK MANUFACTURER FOR APPROVAL. THIS PROCESS SHOULD TAKE ABOUT TWO DAYS.

A NEW SAMPLE AND SIEVE ANALYSIS WILL BE REQUIRED FOR EVERY LOCATION AS WELL AS AN APPROVAL FROM THE TANK MANUFACTURER.

- QUIKTRIP WILL REQUIRE AN ON-SITE INSPECTION AND DOCUMENTATION BY THE TESTING COMPANY AS TO THE CONSISTENCY OF THE MATERIAL DELIVERED TO THE SITE AND ITS SIMILARITY TO THE MATERIAL APPROVED BY THE TANK MANUFACTURER. QUIKTRIP WILL ALSO REQUIRE TESTING COMPANY DOCUMENTATION TO VERIFY THAT THE MATERIAL PLACED IN THE TANK EXCAVATION REMAINS CONSISTENT THROUGHOUT THE BACKFILL PROCESS. DOCUMENTATION SHALL BE PROVIDED TO QUIKTRIP. MATERIAL DISCOVERED ON SITE THAT DOES NOT MEET THE ASTM C-33 SPECIFICATION, FOR ANY REASON, WILL BE REMOVED AND REPLACED AT THE UST INSTALLER'S EXPENSE. ANY LIMESTONE MATERIAL USED SHALL ONLY BE PROVIDED FROM A D.O.T. APPROVED QUARRY. DOCUMENTATION OF APPROVAL SHALL BE PROVIDED TO QUIKTRIP.

BEDDING AND BACKFILL

- MATERIAL SHALL CONFORM TO THE SPECIFICATIONS OF ASTM C-33 GRADING REQUIREMENTS FOR COARSE AGGREGATES. MATERIAL MUST BE FROM A TESTED AND APPROVED STATE DEPARTMENT OF TRANSPORTATION SUPPLIER OR SOURCE. CONTRACTOR SHALL PROVIDE THE FOLLOWING TESTING RESULTS WHICH HAVE BEEN PERFORMED WITHIN THE PRIOR 12 MONTHS OR MORE FREQUENT AS REQUIRED BY THE STATE DEPARTMENT OF TRANSPORTATION OF JURISDICTION, FORM THE SUPPLIER OR SOURCE PRIOR TO FUEL TANK INSTALLATION: I. SIEVE ANALYSIS II. DELETERIOUS SUBSTANCES III. SOUNDNESS. MATERIALS SHALL MEET GRADUATION REQUIREMENTS LISTED IN CURRENT MANUFACTURE'S INSTALLATION MANUAL. ADHERENCE TO ALL INSTALLATION METHODS AND PRE-CAUTIONS AS INDICATED BY THE MANUFACTURER IS REQUIRED. SUBMIT 5 SAMPLE TO QUIKTRIP'S TESTING AGENCY FOR SIEVE ANALYSIS PRIOR TO FUEL TANK INSTALLATION.

TANK AND DISPENSER NOTE:

- SPECIFIC SITE PLAN AND SPECIFICATIONS WILL GOVERN THE EXACT LOCATION, NUMBER, SIZE, AND TYPE OF EQUIPMENT TO BE INSTALLED AND INSTALLATION TO BE FOLLOWED. PLANS AND SPECIFICATIONS REPRESENT MINIMUM REQUIREMENTS. CONTRACTOR SHALL MAKE THE INSTALLATION IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, FEDERAL, STATE, AND LOCAL ORDINANCES WHEN SUCH ORDINANCES EXCEED THESE MINIMUMS. CONTRACTOR SHALL SECURE, ARRANGE FOR AND PAY FOR ALL NECESSARY PERMITS, INSPECTIONS AND TESTS AND INCLUDE THE COST IN THEIR BID (UNLESS SPECIFIED DIFFERENTLY IN SCOPE OF WORK). THE SCOPE OF WORK OR SPECIFICATIONS WILL LIST MATERIAL AND EQUIPMENT TO BE FURNISHED BY QUIKTRIP. CONTRACTOR SHALL STORE, SAFEGUARD AND FURNISH ALL OTHER MATERIALS REQUIRED TO COMPLETE INSTALLATION. MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION AND OPERATIONAL TESTING OF DISPENSERS SHALL BE FOLLOWED TO AVOID POSSIBILITY OF DAMAGE TO EQUIPMENT. ALL INSTALLATIONS SHALL INCLUDE THE INSTALLATION OF STAGE I VAPOR RECOVERY. CONTRACTOR SHALL PLACE ALL UNDERGROUND PIPING WHERE AND AS SHOWN WITH A MINIMUM NUMBER OF BENDS AND CONTINUOUSLY PITCHED TO PROVIDE MAXIMUM SLOPE FROM RISER TO THE LOW POINT AT THE CONNECTION. MINIMUM SLOPE OF 1/8" PER FOOT. INSTALL ALL PRODUCT AND VENT LINES IN A COMMON TRENCH. ALL PRODUCT AND VENT LINES (UNDERGROUND) SHALL BE FIBERGLASS UNLESS OTHERWISE NOTED. ALL PRODUCT LINES SHALL BE 3" / 2" FIBERGLASS. THE MANUFACTURE TO BE DETERMINED BY QUIKTRIP REPRESENTATIVE.

- CONTRACTOR SHALL IDENTIFY UNDERGROUND PIPING, AND VENT PIPING ONCE IT HAS BEEN BACKFILLED AND COVERED UP SO FINISH GRADING AND CONCRETE CONTRACTOR KNOW WHERE UNDERGROUND PIPING IS LOCATED.

PIPE TRENCH LINER NOTE:

PIPING TRENCH LINERS SHALL BE 6oz NON-WOVEN GEOTECH FABRIC - OVERLAP TOP COURSE. CONTACT LOCAL QUIKTRIP REPRESENTATIVE FOR LOCAL REQUIREMENTS.

CERAMIC TILE NOTE:

CERAMIC TILE SHALL BE "CONTINENTAL SLATE C553 ASIAN BLACK 6X6 WITH LATICRETE PERMACOLOR BLACK 22 GROUT". TILE MUST BE CENTERED ON THE ISLAND IN BOTH DIRECTIONS.

FINISH NOTE:

(ALL PRODUCTS ARE SHERWIN-WILLIAMS)

- EXPOSED STEEL: 1 COAT KEM KROMIK METAL PRIMER ISLAND FORMS: DEVTHANE 3TRUVA ALIPHATIC URETHANE GLOSS ENAMEL VENT PIPE: GLOSS BLACK VENT PIPE: AMARILLO WHITE (PHOENIX ONLY)

- EXPOSED STEEL: 1 COAT KEM KROMIK METAL PRIMER GUARD POSTS (ALL DIVISIONS EXCEPT PHOENIX): 2 COATS INDUSTRIAL ENAMEL.

COLOR: SAFETY YELLOW GUARD POST (PHOENIX ONLY): ROLL BRUSH, A100 LATEX FLAT COLOR: B54-N101, Y-60 / 32, R2-2 / 32, B1-40 / 32

- EXPOSED METAL COMPONENTS IN SUMPS: 2 COATS OF OIL RESISTANT, SPRAY CAN ENAMEL, BLUE IN COLOR

CANOPY NOTE:

CANOPY IS A PREFAB STEEL STRUCTURE. CONTACT QUIKTRIP REPRESENTATIVE FOR NAME OF MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR STRUCTURAL DESIGN AND INSTALLATION INFORMATION. SEE ARCHITECTURAL SITE PLAN FOR LOCATION OF CANOPY AND GAS ISLANDS. THE GASOLINE CANOPY STRUCTURE IS FINISHED AND INSTALLED BY QUIKTRIP.

INSURANCE NOTE:

SEE LOCAL REPRESENTATIVE FOR REQUIREMENTS.

INSTALLATION NOTE:

CANOPY, TANKS AND BUILDING TO BE INSTALLED AT THE SAME TIME. THESE PLANS MUST BE USED IN COORDINATION WITH SEPARATE SITE, BUILDING AND CANOPY PLANS.

CONTRACTOR NOTE:

- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW ALL OF THE DRAWINGS AND SPECIFICATIONS ASSOCIATED WITH THIS PROJECT WORK SCOPE PRIOR TO THE INITIATION OF CONSTRUCTION. SHOULD THE CONTRACTOR FIND A CONFLICT WITH THE DOCUMENTS RELATIVE TO THE SPECIFICATIONS OR APPLICABLE CODES, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE PROJECT ENGINEER OF RECORD IN WRITING PRIOR TO THE START OF CONSTRUCTION. FAILURE BY THE CONTRACTOR TO NOTIFY THE PROJECT ENGINEER SHALL CONSTITUTE ACCEPTANCE OF FULL RESPONSIBILITY BY THE CONTRACTOR TO COMPLETE THE SCOPE OF WORK AS DEFINED BY THE DRAWINGS AND IN FULL CONFORMANCE WITH LOCAL REGULATIONS AND CODES. THE CONTRACTOR ACCEPTS FULL RESPONSIBILITY FOR PROPER HANDLING AND INSTALLATION OF THE GASOLINE USTS AND SHALL INSURE THAT GOOD WORKMANSHIP PRACTICES AND CONSTRUCTION PROCEDURES ARE FOLLOWED REGARDLESS OF THE INCLUSION OR OMISSION OF ANY INSTRUCTION. UNKNOWN SITUATIONS OR CONDITIONS NOT COVERED IN THESE AND THE MANUFACTURER'S INSTRUCTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR. MANUFACTURER'S SPECIALISTS ARE AVAILABLE FOR CONSULTATION. THE PRESENCE OF THE MANUFACTURER OR OBSERVER AT AN INSTALLATION SITE DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY FOR THE PROPER INSTALLATION OF THE TANKS. QUESTIONS REGARDING INSTALLATION PROCEDURES OR TANK REPAIRS SHOULD BE DIRECTED TO THE QUIKTRIP FIELD REPRESENTATIVE. GASOLINE UNDERGROUND TANKS MUST BE INSTALLED ACCORDING TO THESE INSTRUCTIONS, THE MANUFACTURER'S INSTRUCTIONS AND NFPA 30 AND 30A UL471. LOCAL CODES MAY APPLY AND MUST BE ADHERED TO. FAILURE TO FOLLOW THESE INSTALLATION INSTRUCTIONS WILL VOID THE WARRANTY AND WILL RESULT IN TANK FAILURE. PROPER INSTALLATION OF GASOLINE USTS HELP PREVENT TANK DAMAGE AND SHOULD INSURE LONG-TERM CORROSION-PROOF SERVICE. IT IS IMPERATIVE TO READ, UNDERSTAND AND FOLLOW THESE INSTRUCTIONS. THESE SPECIFICATIONS ARE SUPPLEMENTED BY THE RESPECTIVE TANK MANUFACTURER'S SPECIFICATIONS. THE INSTALLATION PROCEDURE SHALL COMPLY WITH BOTH SETS OF INSTRUCTIONS AND SPECIFICATIONS. IF, IN THE CONTRACTOR'S JUDGEMENT, THERE APPEARS TO BE A CONFLICT IN THESE SPECIFICATIONS AND THE TANK MANUFACTURER'S INSTRUCTIONS, CONTACT THE LOCAL QUIKTRIP REPRESENTATIVE FOR CLARIFICATION AND GUIDANCE. CONTRACTOR SHALL SECURE, ARRANGE FOR AND PAY FOR ALL NECESSARY PERMITS, INSPECTIONS AND TESTS AND INCLUDE THE COST IN HIS BID (UNLESS SPECIFIED DIFFERENTLY IN SCOPE OF WORK). CONTRACTOR SHALL INSPECT AND CONFIRM ALL PIPING TO BE CLEAR OF ALL BEDDING MATERIAL, TRASH, ANY TYPE OF LIQUID OR DEBRIS PRIOR TO AND AFTER INSTALLATION. TANK AND PRODUCT LINE TESTING AND REPORTING REQUIRED. COORDINATE REQUIREMENTS WITH QUIKTRIP REPRESENTATIVE. XERXES TRUCHECK TANK TIGHTNESS TESTING PROCEDURES SHALL BE FOLLOWED FOR ALL TANK BEING INSTALLED. TRUCHECK DATA LOG SHALL BE COMPLETED BY THE CONTRACTOR AND SUBMITTED TO THE QUIKTRIP REPRESENTATIVE AFTER TESTING IS COMPLETE. CONTRACTOR SHALL ALSO RETAIN A COPY AS PART OF THE TANK RECORDS THAT MAY BE REQUIRED BY FEDERAL, STATE AND/OR LOCAL REGULATIONS OR CODES. SUMP VENTILATION SYSTEM SHALL BE INSTALLED AND TESTED BY CONTRACTOR TO PROVIDE CONTINUOUS AIR MOVEMENT BETWEEN SUMPS. REFER TO SHEET XF410 AND DIRECTION FROM THE QUIKTRIP REPRESENTATIVE. CONTRACTOR SHALL PROVIDE TANK EXCAVATION HOLE PROTECTION AT ALL TIMES UNTIL PAVING IS IN PLACE PER OSHA STANDARD 1910. COVERS AND/OR GUARDRAILS SHALL BE PROVIDED TO PROTECT PERSONNEL FROM THE HAZARDS OF OPEN PITS, TANKS, VATS, DITCHES, ETC. ALL TANK, TRANSITION, AND DISPENSER SUMPS SHALL BE COVERED DURING CONSTRUCTION TO PREVENT DEBRIS AND WATER FROM ACCUMULATING. ANY ACCUMULATION SHALL BE REMOVED AND SUMPS KEEP CLEAN. CONTRACTOR TO CONTACT QUIKTRIP REPRESENTATIVE AND QUIKTRIP ENVIRONMENTAL FOR TANK TESTING REQUIREMENTS. ALL UNDERGROUND STORAGE TANKS SHALL BE BALLASTED WITH CLEAN WATER AT TIME OF TANK INSTALLATION PER MANUFACTURER INSTALLATION INSTRUCTIONS. THE PRACTICE OF BALLASTING WITH PRODUCT IS STRICTLY PROHIBITED AND NOT ALLOWED BY QUIKTRIP. CONTRACTOR SHALL PERFORM ALL REQUIRED TANK TIGHTNESS TESTING WITH WATER ONLY. THE USE OF PRODUCT FOR THESE TEST IS STRICTLY PROHIBITED AND NOT ALLOWED BY QUIKTRIP.

FIRE CODE NOTES:

- FUEL TANKS TO BE VERIFIED FOR UL LISTING AND SHIPPING PRESSURE BY THE FIRE CODE OFFICIAL PRIOR TO PLACEMENT INTO THE GROUND. UNDERGROUND PIPING TO BE HYDROSTATIC TESTED AND VERIFIED BY THE FIRE CODE OFFICIAL. FINAL INSPECTION OF ALL FUEL DISPENSERS TO BE CONDUCTED BY THE FIRE CODE OFFICIAL PRIOR TO DELIVERY OF PRODUCT.


FUEL SHEET INDEX

Table with 2 columns: Description and Sheet Number. Includes entries for GASOLINE SYSTEM TANK AND DISPENSER PIPING GENERAL NOTES (XF101), TEXAS NEW STORE UST INSTALL CHECKLIST (XF101.1), SITE PLAN (XF102), DISPENSER PLAN (XF201), DISPENSER PLAN, SECTION 4 DETAILS (XF202), UST PLAN & SECTIONS (XF203), OBSERVATION WELL DETAILS (XF204), UST DEADMAN & BURIAL DETAILS (XF205), UST DEADMAN & BURIAL DETAILS (XF206), ISLAND DETAILS AND INSTALLATION NOTES (XF207), UST AREA SUB-BASE PREP PLAN AND SECTIONS (XF208), ELECTRICAL SITE PLAN (XF300), UST AREA CONDUIT LAYOUT (XF301), CONDUIT GENERAL INFORMATION & DETAILS (XF302), DISPENSER CONDUIT LAYOUT & SECTION (XF303), CANOPY CONDUIT LAYOUT (XF303.1), DISPENSER CONDUIT LAYOUT & DETAILS (XF304), UST CONDUIT LAYOUT & DETAILS (XF305), UST CONDUIT LAYOUT & DETAILS (XF306), VEEDER ROOT SCHEMATIC & DETAILS (XF307), VEEDER ROOT SCHEDULE & DETAILS (XF308), SENSOR NUMBERING PLAN (XF309), NEC CLASSIFIED AREAS (XF310), ELECTRICAL DETAILS (XF311), ELECTRICAL DETAILS (XF312), ELECTRICAL DETAILS (XF313), UNDERGROUND PIPING SYSTEM PLAN (XF401), UST SECTIONS (XF402), TANK TOP EQUIPMENT DETAILS (XF403), DISPENSER & ISLAND DETAILS (XF404), DISPENSER & ISLAND SECTION (XF405), UST, TRANSITION SUMP & MISCELLANEOUS DETAILS (XF406), UST, TRANSITION SUMP & MISCELLANEOUS DETAILS (XF406.1), UST & PIPING DETAILS (XF407), DISPENSER & PIPING DETAILS (XF408), DISPENSER & PIPING DETAILS (XF409), VAPOR, VENT DETAILS (XF410), BILL OF MATERIALS (XF600), BILL OF MATERIALS (XF601)



CORESTATES, INC. CERTIFICATE OF AUTHORIZATION #0349 EXPIRES 07-31-2023

SIGNATURE DATE:



QuikTrip No. 4160

7601 W SH 29 GEORGETOWN, TEXAS



© QUINCY CORPORATION 2011. ALL RIGHTS RESERVED. THIS DOCUMENT IS THE PROPERTY OF QUINCY CORPORATION. IT IS TO BE USED ONLY FOR THE PROJECT IDENTIFIED HEREIN.

PROTOTYPE P-110 DIVISION AUSTIN VERSION G3SE DATE 05-01-2022

Revision table with columns: REV, DATE, DESCRIPTION. Row 1: 09/19/22, CITY COMMENTS.

SHEET TITLE: GASOLINE SYSTEM TANK AND DISPENSER PIPING GENERAL NOTES

SHEET NUMBER: XF101

TEXAS NEW STORE UST INSTALL CHECKLIST


30-DAY NOTIFICATION (TCEQ-0495 FORM) FOR SENT TO THE TCEQ CENTRAL OFFICE IN AUSTIN, ALSO SEND RECEIPT OF SUBMISSION TO QTENVIRO@QUIKTRIP.COM - FUEL INSTALLER RESPONSIBLE

PROPER 24-HOUR NOTIFICATIONS TO BE MADE TO THE LOCAL TCEQ OFFICE FOR SETTING THE TANKS, COMPLETING THE PIPING INSTALLATION, AND THE FINAL INSPECTION. - FUEL INSTALLER RESPONSIBLE

TANK REGISTRATION APPLICATION - TCEQ-0724 FORM- FUEL INSTALLER RESPONSIBLE


REQUIRED DOCUMENTATION FOR NEW UST SYSTEMS:

1. 3RD PARTY VAPOR RECOVERY TESTING - INCLUDES A PRESSURE DECAY TEST, TIE-TANK TEST, AND PRESSURE/VACUUM (P/V) VENT VALVE TEST.(TX)- FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
2. 50 PSI PRIMARY AND FUTURE LINE AND 5 PSI SECONDARY LINE PRESSURE TEST COMPLETED PRIOR TO SYSTEM GOING IN SERVICE. TESTER TO DOCUMENT THAT PRESSURE WAS HOLDING ON SECONDARY LINES AT PROJECT COMPLETION. THE TEST RESULTS FOR CAN BE DOCUMENTED ON THE PRODUCT PIPING MANUFACTURER CHECKLIST FOR EACH TYPE OF PIPE OR CONTRACTOR FORM. (QT) FUEL INSTALLER RESPONSIBLE
3. 3RD PARTY TANK TIGHTNESS TESTING (MUST TEST WITH WATER PRIOR TO FUEL DELIVERY)(QT,TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
4. 3RD PARTY LINE TIGHTNESS TESTING (QT,TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
5. 3RD PARTY MANUAL/FORCED LINE LEAK DETECTOR OPERABILITY TEST FOLLOWING MANUFACTURERS GUIDELINES TO SIMULATE 3.0 GPH LEAK (QT,TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
6. TRUCKET OR HYDROSTATIC STAND PIPE TANK TEST FOR EACH TANK (QT) FUEL INSTALLER RESPONSIBLE
7. 3RD PARTY DISPENSER CALIBRATION RESULTS (QT) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
8. 3RD PARTY SENSOR FUNCTIONALITY TESTING (TX)
 - NEED SENSOR STATUS PRINTOUT WITH ALL SENSORS IN NORMAL STATUS
 - NEED LEAK DETECTION CONSOLE PRINTOUT DOCUMENTING THE FUNCTIONALITY OF EACH INTERSTITIAL SENSOR. THE SENSOR FUNCTIONALITY TEST IS CONDUCTED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN GUIDELINES AND SHOULD CONSIST OF PRINTOUTS DOCUMENTING THE STATUS OF EACH SENSOR BEFORE, DURING, AND AFTER THE FUNCTIONALITY TEST. SENSOR STATUS PRINTOUTS BEFORE AND AFTER THE TEST SHOULD INDICATE A STATE OF NON-ALARM, SUCH AS A "NORMAL" OR "OK". (TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
9. 3RD PARTY REMOTE FILL PRESSURE (IF APPLICABLE) (QT REQUIRED TEST FORM) (QT) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
10. OVERFILL OPERABILITY TESTING/VERIFICATION (TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
11. 3RD PARTY SUMP HYDROSTATIC TEST RESULTS (TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
12. 3RD PARTY SPILL BUCKET HYDROSTATIC OR VACUUM TEST RESULTS (TX) - FUEL INSTALLER TO COORDINATE WITH QT ENV FOR APPROVED TESTING VENDOR (QTENVIRO@QUIKTRIP.COM)
13. TANK CHART FOR EACH TANK (QT) FUEL INSTALLER RESPONSIBLE
14. TANK WEIGHT AT DELIVERY (IF POSSIBLE). PLEASE WRITE ON UST MANUFACTURER CHECKLIST OR USE CONTRACTOR FORM. (QT) FUEL INSTALLER RESPONSIBLE
15. UST MANUFACTURER CHECKLIST (TX) 16. PRODUCT PIPING MANUFACTURER CHECKLIST FOR EACH TYPE OF PIPE (QT) FUEL INSTALLER RESPONSIBLE
16. PRODUCT PIPING MANUFACTURER CHECKLIST FOR EACH TYPE OF PIPE (QT) FUEL INSTALLER RESPONSIBLE



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023

SIGNATURE DATE:



QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS



© QUIKTRIP CORPORATION 2011
ALL RIGHTS RESERVED. REPRODUCTION, PUBLICATION, DISTRIBUTION OR
USE IN ANY MANNER IS PROHIBITED.




PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
**TEXAS NEW STORE
UST INSTALL
CHECKLIST**

SHEET NUMBER:
XF101.1



CORESTATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023



QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© QUIKTRIP CORPORATION 2022
 ALL RIGHTS RESERVED. QTR, QUIKTRIP, QUIKTRIP LOGO, QUIKTRIP STORE, QUIKTRIP STORE DESIGN, QUIKTRIP STORE DESIGN AND ALL OTHER TRADE NAMES ARE TRADE NAMES OF QUIKTRIP CORPORATION.

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE
B2	03/27/23	COORDINATION


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 SITE PLAN

SHEET NUMBER:
 XF102


REFER TO CIVIL PLAN SET
 FOR PLACEMENT OF ALL
 FUEL RELATED STRUCTURES
 AND EQUIPMENT.

A1 SITE PLAN (REFERENCE ONLY - NOT FOR CONSTRUCTION) B2




NOTE:

- DISPENSER SUMPS TO BE SET IN PLACE AND USED AS A FORM TO POUR CONCRETE AROUND.
- ALL EQUIPMENT INSTALLATIONS MUST COMPLY WITH MANUFACTURER'S SPECIFICATIONS.
- ALL EQUIPMENT AND CONSTRUCTION ARE NEW AND FACILITY IS TO BE SELF-SERVICE.
- FOUNDATION AND SUBGRADE PREPARATION DETAILS IN ACCORDANCE WITH SOIL REPORT AND CIVIL DRAWINGS.
- SEE CIVIL PLANS FOR ORIENTATION ON SITE, AND FOR TRAFFIC FLOW.
- REFER TO CANOPY MANUFACTURERS DRAWINGS FOR SPECIFIC CANOPY FOOTING OPTIONS.
- DISPENSER LAYOUT FOR EQUIPMENT LOCATION AND CONFIGURATION. SEE CIVIL DRAWINGS FOR CONCRETE SPECIFICATIONS, REINFORCING, CANOPY DETAILS, SLOPES & GRADES, SIGNAGE AND ADDITIONAL SITE REQUIREMENTS.



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023



QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT

© QUIKTRIP CORPORATION 2011. ALL RIGHTS RESERVED. NO REPRODUCTION, PUBLICATION, DISTRIBUTION OR SALE IN WHOLE OR IN PART, IS PERMITTED WITHOUT PERMISSION.

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022


REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 DISPENSER PLAN


SHEET NUMBER:
 XF201

A1 DISPENSER PLAN
 1/8" = 1'-0"




J1 CANOPY FRONT ELEVATION

1/8"=1'-0" A1-XF201




A1 CANOPY SECTION DETAILED CROSS SECTION

1/4"=1'-0" A1-XF201



A11 DISPENSER PLAN

3/16"=1'-0" A1-XF201



CORESTATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023

SIGNATURE DATE:

1000 Industrial Loop, Suite B
Georgetown, TX 78626
Phone: (797) 886-4480
Fax: (797) 886-4020

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS

© QUIKTRIP CORPORATION 2011
ALL DIMENSIONS ARE APPROXIMATE. PUBLICATION, DISTRIBUTION OR SALE OF THIS DRAWING IS PROHIBITED.

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
DISPENSER PLAN,
SECTIONS & DETAILS


SHEET NUMBER:
XF202

PAINT COLOR SPECIFICATIONS
 PETROLEUM RESISTANT PAINT, INDUSTRIAL ENAMEL, (PROTECTIVE & MARINE COATINGS)

I. FUEL MANHOLE COVERS, VAPOR RECOVERY MANWAYS, PRODUCT FILL COVERS, STICK PORT COVERS.

A. PREMIUM UNLEADED - SAFETY RED B65R550.
 B. UNLEADED PLUS - BLUE B65L550
 C. UNLEADED - WHITE B65W550
 D. UNLEADED W/ NO ETHANOL - WHITE B65W550 WITH BLACK "X"
 E. UNLEADED E15 - HALF BLUE B65L550 AND HALF WHITE B65W550
 F. VAPOR RECOVER CONNECTION - SAFETY ORANGE S44083
 G. PRODUCT X TANK WHEN FILLED WITH WATER - GRAY S44031
 H. OBSERVATION WELLS - WHITE B65W550 WITH DIAMOND BLOCK
 I. DIESEL ALL GRADE ULTRA LOW SULFUR - BRIGHT YELLOW B65Y1W52
 J. DIESEL EXHAUST FLUID - LASER BLUE S44074
 K. STICK PORT - MATCH PRODUCT FILL

FIBRELITE COVER NOTE:
 1. ENSURE THAT THE SEAL AND SEALING FACES OF THE COVER ARE CLEAN
 2. APPLY SILICONE TO THE COVER SEAL
 3. LEAVE SILICONE CAN IN SUMP FOR FUTURE USE



NOTE: OBSERVATION WELLS SHALL BE LOCATED IN PAVED AREA. VERIFY LOCATIONS PRIOR TO PLACEMENT.

NOTE: RE: CIVIL DRAWINGS FOR CONCRETE TANK SLAB

TANK TOP EQUIPMENT PAINT REQUIREMENTS
 PAINT SHALL BE PETROLEUM RESISTANT

MANHOLE COVER	COLOR
UNLEADED	WHITE
UNLEADED W/NO ETHANOL	WHITE W/BLACK "X"
UNLEADED PLUS	BLUE
PREMIUM	RED
DIESEL	YELLOW
VAPOR RECOVERY	ORANGE
PRODUCT X	BLACK
PROBE	GRAY
ANNULAR / INTERSTITIAL	GRAY
OBSERVATION WELL	WHITE W/BLACK DIAMOND
STICK PORT	MATCH PRODUCT FILL

TANK NUMBERING

TANK #1	15K UNLEADED 1
TANK #2	15K UNLEADED 2
TANK #3	15K EO
TANK #4	15K PREMIUM
TANK #5	15K DIESEL

CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023

SIGNATURE DATE:

1700 Industrial Loop, Suite B
 Houston, TX 77058
 Phone: (713) 886-4400
 Fax: (713) 886-4400

QuikTrip No. 4160

7601 W SH 29
 GEORGETOWN, TEXAS

© QUIKTRIP CORPORATION 2011
 ALL RIGHTS RESERVED. NO REPRODUCTION, PUBLICATION, DISTRIBUTION OR USE IN ANY MANNER IS PERMITTED WITHOUT EXPRESS WRITTEN PERMISSION.

PROTOTYPE: P-110
 DIVISION: AUSTIN
 VERSION: G3SE
 DATE: 05-01-2022

REV	DATE	DESCRIPTION
001	09/21/22	TANK UPDATE


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 UST PLAN & SECTIONS



SHEET NUMBER:
XF203

A1 TANK APRON PLAN


- NOTES:
- OBSERVATION WELL SHALL CONSIST OF 6 INCH DIA. SCHEDULE 40 PVC THREADED WELL MATERIAL.
 - WELL SHALL BE CONSTRUCTED WITH SCREEN TO WITHIN 2'-0" OF SURFACE W/ FACTORY MANUFACTURED SLOT WIDTH OF .020.
 - THE REMAINDER OF THE WELL SHALL BE CONSTRUCTED OR 6" THREADED SCHED. 40 SOLID PVC RISER MATERIAL.
 - WELL SHALL EXTEND FROM 4" BELOW FINISH GRADE TO THE 12" PAST THE BOTTOM OF THE UST BASIN.
 - THE BOTTOM OF THE WELL SHALL BE PLUGGED USING 6" ϕ . SCHEDULE 40 PVC END PLUG OR CAP.
 - THE WELL SHALL BE CAPPED USING AN INTERNAL TYPE EXPANDING WELL CAP.
 - THE WELL SHALL BE FINISHED USING AT MINIMUM AN 12" ϕ . FLUSH MOUNT MANWAY COVER.
 - THE WELL SHALL BE COMPLETELY SURROUNDED BY GRAVEL BACK FILL MATERIAL. AT NO TIME SHALL THE WELL BE PLACED INTO OR FILLED BY SOIL MATERIAL.
 - OBSERVATION WELLS SHALL BE PLACED IN PAVED AREA. VERIFY LOCATION PRIOR TO PLACEMENT.



- NOTES:
- OBSERVATION WELL SHALL CONSIST OF 12" ϕ . SCHEDULE 40 PVC THREADED WELL MATERIAL.
 - WELL SHALL BE CONSTRUCTED WITH ONE 5'X 12" SCREEN AT BOTTOM WITH A FACTORY MANUFACTURED SLOT WIDTH OF .020.
 - THE REMAINDER OF THE WELL SHALL BE CONSTRUCTED OF 12" THREADED SCHEDULE 40 SOLID PVC RISER MATERIAL.
 - WELL SHALL EXTEND FROM 4" BELOW FINISH GRADE TO THE 12" PAST THE BOTTOM OF THE UST BASIN.
 - THE BOTTOM OF THE WELL SHALL BE PLUGGED USING 12" ϕ SCHEDULE 40 PVC END PLUG OR CAP.
 - THE WELL SHALL BE CAPPED USING AN INTERNAL TYPE EXPANDING WELL CAP.
 - THE WELL SHALL BE FINISHED USING AT MINIMUM AN 18" ϕ FLUSH MOUNT MANWAY COVER.
 - THE WELL SHALL BE COMPLETELY SURROUNDED BY GRAVEL BACK FILL MATERIAL. AT NO TIME SHALL THE WELL BE PLACED INTO OR FILLED BY SOIL MATERIAL.
 - OBSERVATION WELLS SHALL BE PLACED IN PAVED AREA. VERIFY LOCATION PRIOR TO PLACEMENT.



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
OBSERVATION WELL DETAILS

SHEET NUMBER:
XF204


A1 6" OBSERVATION WELL DETAIL

A9 12" OBSERVATION WELL DETAIL



H1 TANK AND DEADMAN PLAN

1/4" = 1'-0"



CONTRACTOR SHALL PROVIDE TANK EXCAVATION HOLE PROTECTION AT ALL TIMES UNTIL PAVING IS IN PLACE PER OSHA STANDARD 1910. COVERS AND/OR GUARDRAILS SHALL BE PROVIDED TO PROTECT PERSONNEL FROM THE HAZARDS OF OPEN PITS, TANKS, VATS, DITCHES, ETC.

1. DEPTH MAY VARY, CONSULT PLANS FOR ACTUAL DEPTH OF TANK SHELF.
2. SEE PAVING PLAN AND ASSOCIATED DETAILS FOR PAVEMENT AND BASE DEPTH.
3. LINE EXCAVATION W/6 OZ NON-WOVEN GEOTECH FABRIC - OVERLAP TOP COURSE.
4. EXTEND GEOTECH FABRIC 5'-0" BEYOND EDGE OF TANK PIT AND COVER W/AGGREGATE BASE.
5. PLATE COMPACT FILL MATERIAL WHEN AT SUB GRADE.

NOTES:

A. THE CONTRACTOR SHALL PROVIDE APPROPRIATE EXCAVATION SUPPORT (i.e. ENGINEERED SHEETING AND SHORING) TO FURNISH SAFE CONDITIONS.

B. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL UNDERGROUND FRP STORAGE TANKS BE INSTALLED ACCORDING TO LOCAL, STATE AND FEDERAL REGULATIONS AND MANUFACTURER'S SPECIFICATIONS.

GEOTECHNICAL CONSTRUCTION NOTE

SEE GEOTECHNICAL SOIL REPORT FOR SUBGRADE PREPARATION RECOMMENDATIONS FOR FOOTINGS, TRENCHES, APRONS, TANKS AND SURFACE TREATMENTS.

A1 TANK ANCHORING PLAN

1/4" = 1'-0"

QuikTrip No. 4160


7601 W SH 29
GEORGETOWN, TEXAS

PROTOTYPE: P-110
DIVISION: AUSTIN
VERSION: G3SE
DATE: 05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

SHEET TITLE:
UST DEADMAN & BURIAL DETAILS

SHEET NUMBER:
XF205




NOTE:
ALL EXPOSED METAL ON ANCHORING SYSTEM AND TURNBUCKLES MUST BE GALVANIZED TO PROTECT AGAINST CORROSION.

NOTES:


- MECHANICAL TANK ANCHORING IS REQUIRED FOR ALL TANK INSTALLATIONS. ANCHORS/DEADMEN TO BE DESIGNED BY TANK MANUFACTURER AND ARE TO BE INSTALLED PER TANK MANUFACTURER'S SPECIFICATIONS.
- DEADMAN TO BE PROVIDED BY GENERAL CONTRACTOR OR PROVIDED BY QUIKTRIP AT GENERAL CONTRACTORS REQUEST. GENERAL CONTRACTOR TO COORDINATE WITH QUIKTRIP REPRESENTATIVE.
- USE ONLY TANK MANUFACTURER'S SPECIFIED ANCHOR STRAPS. NUMBER AND LOCATION IN ACCORDANCE WITH TANK MANUFACTURER'S INSTALLATION INSTRUCTIONS.
- ALL HOLD-DOWN STRAPS MUST BE UNIFORMLY TIGHTENED. STRAPS MUST BE TIGHTENED UNTIL SNUG, BUT CAUSE NO DEFLECTION OF THE TANK.
- WIRE ROPE ANCHORS OVER THE TANKS ARE NOT ACCEPTABLE AS A MEANS OF ANCHORING TANKS. UNLESS WRITTEN CONFIRMATION IS RECEIVED FROM TANK MANUFACTURER AND OWNER AS AN ALTERNATIVE METHOD.

ALL EXPOSED METAL ON ANCHORING SYSTEM AND TURNBUCKLES MUST BE GALVANIZED TO PROTECT AGAINST CORROSION.


ULTIMATE STRENGTH
WORKING STRENGTH
SAFETY FACTOR OF 5.0 REQUIRED




G12 TANK ANCHORING HARDWARE
1" = 1'-0" A1-XF206



A12 TANK ANCHORING HARDWARE EDGE OF TANK
1" = 1'-0" G12-XF206



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS




PROTOTYPE P-110
DIVISION AUSTIN
VERSION G3SE
DATE 05-01-2022

REV	DATE	DESCRIPTION

SHEET TITLE:
UST DEADMAN & BURIAL DETAILS



SHEET NUMBER:
XF206



H1 ISLAND SUPPORT FRAME
1 1/2"=1'-0"

H7 ISLAND FINISH DETAIL
3/4"=1'-0"

H13 ISLAND SECTION DETAIL
3"=1'-0" A1-XF207



PIPE:
FIBERGLASS PIPE TO BE AMERON PRODUCTS (BRANDS MAY NOT BE MIXED, INSTALL PER MANUFACTURER'S RECOMMENDATIONS). STEEL PIPE TO BE SCH. 40. ALL PIPING AND GLUE TO BE ALCOHOL COMPATIBLE, WHERE REQUIRED.

ALL PIPING SHALL BE INSPECTED/CONFIRMED TO BE CLEAR OF ALL BEDDING MATERIAL, TRASH, ANY TYPE OF LIQUID OR DEBRIS PRIOR TO AND AFTER INSTALLATION.

PIPE JOINT SEAL:
UL CLASSIFIED PIPE THREAD SEALANT FOR USE ON ALL STEEL PIPE FITTINGS AND THREADED METAL CONNECTIONS. NON-HARDENING, NON-TOXIC, COMPATIBLE WITH ALL SPECIFIED PIPING. RESISTANT TO GASOLINE, ETHANOL BLENDED GASOLINE UP TO E85, DIESEL FUEL, & PETROLEUM SOLVENTS. TEMPERATURE RANGE SHALL BE -100°F TO 600°F. PRESSURE RANGE: UP TO 10,000 PSI WHEN SEALING LIQUIDS AND UP TO 3,000 PSI WITH GASES.

TANK VENTS:
ALL TANK VENTS SHALL BE 2" MIN.

SLOPE:
ALL PRODUCT PIPING MUST BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND PER SPECIFIC STATE REQUIREMENTS.
VENT LINE MUST SLOPE 1/8" PER FOOT TOWARDS TANK.
ALL PRODUCT PIPING MUST SLOPE 1/8" PER FOOT TOWARD TANK, DISPENSER SUMP OR A COLLECTION SUMP.
OKLAHOMA ONLY - PRODUCT LINES TO BE SLOPED TO THE TANK FARM FROM THE NEAREST DISPENSER TO THE TANKS.

PIPE TESTING:
ALL PRIMARY AND SECONDARY, & VENT FRP PIPING SHALL BE PRESSURIZED AND TESTED PER MANUFACTURER'S REQUIREMENTS. PRESSURE SHALL BE MAINTAINED AFTER THE TESTING IS COMPLETE FOR THE DURATION OF THE PROJECT TO INSURE SYSTEM REMAINS TIGHT.

BACKFILL:
BACKFILL OVER PRODUCT AND VENT LINES IN TRENCH SHALL BE CLEAN COMPACTED PEA GRAVEL, CRUSHED GRAVEL OR APPROVED CLEAN SAND. PIPING SHALL BE LAID AND CONTINUOUSLY SUPPORTED ON 6" OF COMPACTED APPROVED MATERIAL. NO PIPING SHALL BE SUPPORTED BY BLOCKS, PLANKS OR OTHER DEBRIS.

CONCRETE:
CONCRETE USED SHALL MEET QUIKTRIP STANDARD SPECS. SEE CIVIL DRAWINGS FOR DETAILS.

SUMP UNITS:
TURBINE ENCLOSURE/TANK SUMPS ARE TO BE SEALED PER MANUFACTURER'S INSTALLATION INSTRUCTIONS.

GENERAL INSTALLATION:

- PEA GRAVEL OR CRUSHED GRAVEL BACKFILL. ALL OTHER MATERIAL MUST BE APPROVED BY TANK MANUFACTURER AND OWNER'S FIELD REPRESENTATIVE.
- RIGID STYROFOAM BOARD FIELD CUT TO SUPPORT MANKAY DURING INSTALLATION.
- PRODUCT LINE & VENT LINE FIBERGLASS PIPE AND FITTINGS TO BE AMERON. FITTINGS MANUFACTURERS MAY NOT BE MIXED.
- REINFORCING BARS TO BE A MAXIMUM OF 3" FROM TOP OF CONCRETE.
- SEAL AND PLUG UNUSED OPENINGS.
- OBSERVATION WELL DEPTH SHALL BE TO THE BOTTOM OF TANK EXCAVATION UNLESS OTHERWISE NOTED. WELLS SHALL BE PLACED IN PAVED AREA.
- PROVIDE 6" CLEARANCE BETWEEN MANKAY LID AND TOP OF RISER FOR TANK GAUGE.
- PROVIDE 6" CLEARANCE BETWEEN TOP OF MONITORING/OBSERVATION WELL CAP PLUG AND GRADE.
- ALL PENETRATIONS MUST BE PERPENDICULAR TO CONTAINMENT SUMPS.
- CUT AND POSITION FILL TUBE WITH ANGLE AWAY FROM SUBMERSIBLE PUMP.
- INTERIOR OF FIBERGLASS CONTAINMENT SUMP TO BE CLEAR OF PEA GRAVEL, TRASH, ANY TYPE OF LIQUID AND OTHER DEBRIS.
- REAM ALL RISERS FOR FULL PIPE BORE.
- 4" RISER FOR UNLEADED GASOLINE & ETHANOL BLENDS STORAGE TANKS SHALL BE SCHEDULE 40 GALVANIZED. 4" RISERS FOR STORAGE TANKS CONTAINING DIESEL SHALL BE SCHEDULE 40 BLACK IRON. ALL RISERS TO BE PRIMED AND WRAPPED.
- ANNULAR SPACE RISER: AMERON 4" LCX FRP PIPING.
- CONCRETE DEADMAN, TURNBUCKLES, AND OTHER ANCHORING HARDWARE SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH TANK MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS AS SHOWN. (IF REQUIRED) SEE QUIKTRIP REPRESENTATIVE FOR DIRECTION.
- INSTALLER MUST SAND DOWN GEL COAT BEFORE GLUING FIBERGLASS ENTRY FITTING TO SUMPS FOR PROPER ADHESION.
- CENTRALIZERS SHALL BE PLACED 6" FROM EACH END AND 4'-0" ON CENTER IN ALL PIPING RUNS.

A1 ISLAND SECTION
1 1/2"=1'-0"

A12 INSTALLATION NOTES

CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023

SIGNATURE DATE:

CORE STATES GROUP

1700 West Loop South, Suite B
Houston, TX 77056
Phone: (713) 866-4400
Fax: (713) 866-4400

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS

QUICKTRIP CORPORATION 2022
ALL RIGHTS RESERVED. NO REPRODUCTION, DISTRIBUTION OR SALE OF THIS DOCUMENT IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF QUICKTRIP CORPORATION.

PROTOTYPE: P-110
DIVISION: AUSTIN
VERSION: G3SE
DATE: 05-01-2022



REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE: 8/22/2022


SHEET TITLE:
ISLAND DETAILS AND INSTALLATION NOTES

SHEET NUMBER:
XF207


J1 NOT USED



A1 STANDARD TANK BACKFILL SECTION



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS




PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022


REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

SHEET TITLE:
UST AREA SUB-BASE
PREP PLAN AND
SECTIONS

SHEET NUMBER:
XF208



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023





QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE
B2	03/27/23	COORDINATION
ORIGINAL ISSUE DATE: 8/22/2022		


SHEET TITLE:
ELECTRICAL SITE PLAN

SHEET NUMBER:
XF300



LAYOUT BRANCH CIRCUIT WIRING AND ARRANGEMENT OF HOME RUNS FOR MAXIMUM ECONOMY AND EFFICIENCY. INCREASE WIRE SIZE IF VOLTAGE DROP EXCEEDS 3% OR 100 FEET OF LENGTH.

PROVIDE IN EVERY CIRCUIT A SEPARATE EQUIPMENT GROUND WIRE TO SOURCE PANEL AND BOND EVERY EQUIPMENT AND/OR LIGHT FIXTURE TO METAL STRUCTURE PER NEC 514.16.



FUEL TANKS - REFER TO SEPARATE FUEL PLANS FOR MORE INFORMATION.

REFER TO SHEET EQ02 FOR GAS CANOPY LIGHTING.



REFER TO SHEET EQ03 FOR SECURITY CAMERA CONDUIT LAYOUT.

REFER TO CIVIL PLAN SET FOR PLACEMENT OF ALL FUEL RELATED STRUCTURES AND EQUIPMENT.

- 1 CLASS 1, DIVISION 2 AREA WITHIN 18" OF ANY EDGE OF THE DISPENSER TO GRADE AND FROM GRADE TO 18" ABOVE GRADE WITHIN 20' OF ANY EDGE OF THE DISPENSER.
- 2 CLASS 1, DIVISION 1 AREA WITHIN THE DISPENSER ENCLOSURE AND WITHIN THE PIT BELOW THE DISPENSER. (TYP)
- 3 CLASS 1, DIVISION 2 AREA WITHIN 10'-0" OF PUMPS OR FILL OPENINGS FROM GRADE TO 18" ABOVE GRADE.
- 4 SEAL EACH CONDUIT ENTERING THE CLASS 1 (DIVISION 1 OR 2) LOCATION AT THE POINT WHERE IT EXITS THE GROUND. (BOTH ENDS)
- 5 EMERGENCY FUEL SHUTOFF WITHIN 100' OF DISPENSERS. REFER TO DETAIL A9-XF311. PROVIDE PERMANENT WHITE ALUMINUM LABEL WITH 1" HIGH RED LETTERING ON WHITE BACKGROUND ON COLUMN ABOVE SWITCH THAT SAYS, "EMERGENCY PUMP SHUT-OFF SWITCH". (LOCATION SHOWN IS OPTIONAL - COORDINATE WITH QT REP)
- 6 SUMP VENTILATION FAN FURNISHED BY OTHERS. VERIFY EXACT LOCATION WITH FUEL SYSTEM DRAWINGS. PROVIDE NEMA-3R MOTOR STARTER/DISCONNECT SWITCH FOR 3/4 HP, 208V/1PH FAN ON CANOPY ROOF. MAKE ELECTRICAL CONNECTIONS AS REQUIRED. CIRCUIT TO SHUT DOWN WITH E-STOP SYSTEM, SENSOR IN ALARM, AND PLLD IN ALARM.
- 7 PROVIDE (1) SEPARATE #12 GROUND WIRE FROM BUILDING GROUND BUS TO EACH PLLD IN A NON-INTRINSICALLY SAFE CONDUIT. PROVIDE (1) GROUNDING KIT #330020-285 FOR EACH PLLD. REFER TO G1-XF313 AND VEEDER-ROOT MANUAL NO. 5TT1014-012 FOR ADDITIONAL INFORMATION.

A1 ELECTRICAL SITE PLAN

A13 PLAN NOTES




TANK NUMBERING	
TANK #1	15K UNLEADED 1
TANK #2	15K UNLEADED 2
TANK #3	15K EO
TANK #4	15K PREMIUM
TANK #5	15K DIESEL

RETAIL/GASOLINE CONDUIT SCHEDULE			
NUMBER	DESCRIPTION (TRADE SIZE)	WIRE COUNT PER CONDUIT	TERMINATES TO
1 TO 12 (8 TOTAL)	DISPENSER POWER (3/4") (HOME RUN)	(2)#12, (1)#12G - DISPENSER POWER @ ALL LOCATIONS (5)#12 STP CONTROLLER WIRES TOTAL @ ALL LOCATIONS (2) FUTURE @3+0 / (1) FUTURE @3+1	MAIN ELEC. TROUGH MAIN ELEC. TROUGH
13 TO 24 (8 TOTAL)	DISPENSER DATA (3/4") (HOME RUN)	WINDY CITY WIRE: TWO TWISTED PAIR (VIOLET/BROWN) #036020-1012GT (ORANGE/YELLOW) #036013-1012GT	L.V. ELEC. TROUGH
25 TO 30 (6 TOTAL)	DISPENSER SUMP SENSORS (3/4") (HOME RUN)	(1) #18 WINDY CITY 18 AWG SHIELDED CABLE	I/S WIRING TROUGH
31 TO 40 (2 TOTAL)	DISPENSER INTERCOM (1" HR - 1" LOOP) (3 DISPENSERS MAX)	(UP TO 6) BELDEN 6502FE (1 PER DISPENSER)	L.V. ELEC. TROUGH
41 TO 45 (5 TOTAL)	STP CTRL/POWER- (3/4") UNLEADED #1 UNLEADED #2 EO PREMIUM DIESEL (HOME RUN)	(3) #10 STP POWER, (1) #10 GROUND	DEDICATED CONDUIT BACK TO STP CONTROLLERS
46 TO 51 (5 TOTAL)	PLLD / (1) SUMP SENSOR (3/4") (1) CONDUIT PER TANK (HOME RUN)	(2) WINDY CITY 18 AWG SHIELDED CABLE	I/S WIRING TROUGH
52	HYDROSTATIC RESERVOIR SENSOR (3/4")	(4) 18 WINDY CITY 18 AWG SHIELDED CABLE	I/S WIRING TROUGH
53 TO 56 (5 TOTAL)	UST ATG PROBE (3/4")	(1) WINDY CITY 18 AWG SHIELDED CABLE	I/S WIRING TROUGH
57	CANOPY LIGHTING CONDUITS (1")	CANOPY LIGHTING = RE: ARCH MEP	MAIN ELEC. TROUGH
58 TO 59 (2 TOTAL)	FUTURE POWER CONDUITS (1") (ROUTE TO JBOX @TOP OF CANOPY)	FULL STRING TO DECK	MAIN ELEC. TROUGH
60 TO 61 (2 TOTAL)	FUTURE LOW VOLTAGE CONDUITS (1") (ROUTE TO PULL BOX)	FULL STRING TO PULL BOX	I/S WIRING TROUGH
62 TO 63 (2 TOTAL)	FUTURE DATA CONDUITS (1") (ROUTE TO PULL BOX)	FULL STRING TO PULL BOX	L.V. ELEC. TROUGH
64	CANOPY GROUND WIRE (1-1/4") (ROUTE TO JBOX @TOP OF CANOPY)	FIELD DETERMINED	MAIN ELEC. "I" PANEL
65	SUMP VENT CIRCULATION FAN	FAN = (3) #12 POWER, (1) #12 GROUND	MAIN ELEC. TROUGH
66	TRANSITION SUMP SENSOR (3/4")	(1) #18 WINDY CITY 18 AWG SHIELDED CABLE	I/S WIRING TROUGH
67	OBSERVATION WELL SPARE (3/4")	FULL STRING	I/S WIRING TROUGH
68	EMERGENCY SHUTOFF (3/4")	FIELD DETERMINED (RE ARCH)	MAIN ELEC. TROUGH
69	CANOPY LIGHTING CONDUITS (1") (HOME RUN)	CANOPY LIGHTING = RE: ARCH MEP	MAIN ELEC. TROUGH
70 TO 71 (2 TOTAL)	SECURITY CAMERA HOMERUN (1")	FIELD DETERMINED	FIELD DETERMINED

NOTE: ALL FUTURE USE CONDUITS SHALL EXTEND 12 INCHES ABOVE CANOPY DECK AND BE SEALED WITH WEATHER PROOF JUNCTION BOX.

NOTE: WINDY CITY WIRE CONTACT INFORMATION: KIMBERLY DePAOLA 1.800.374.1191 KDEPAOLA@SMARTWIRE.COM



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023

SIGNATURE DATE:

CORE STATES GROUP

1700 W. SH 29, Suite B
Georgetown, TX 77626
Phone: (714) 888-4440
Fax: (714) 888-4440

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS

QT	
PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
UST AREA CONDUIT LAYOUT

SHEET NUMBER:
XF301

A1 CONDUIT LAYOUT - UST (TANK) AREA


A10 ELECTRICAL CONDUIT SCHEDULE



NOTE:
ANY EXPOSED PVC COATED RIGID STEEL CONDUIT SHALL BE COATED WITH PLASTI-BOND EPOXY TOUCH UP COMPOUND AT CONNECTIONS.

CONDUITS CONDITIONS
 1. **STP/TURBINE POWER:**
 STP POWER CONDUITS: PVC COATED RIGID STEEL CONDUIT SHALL BE USED FOR THE FIRST PIECE OF EXPOSED CONDUIT WITHIN THE BUILDING, TRANSITIONING TO SCH. 40 PVC TO WITHIN 10' OF THE STP SUMPS, WHERE THE CONDUIT SHALL TRANSITION TO PVC COATED RIGID STEEL FOR THE PENETRATIONS.
 2. **TANK FARM AREA:**
 FOR TANK FARM EQUIPMENT. PVC COATED RIGID STEEL CONDUIT SHALL BE USED FOR THE FIRST PIECE OF EXPOSED CONDUIT WITHIN THE BUILDING, TRANSITIONING TO SCH. 40 PVC TO WITHIN 10' OF THE TANK FARM EQUIPMENT WHERE THE CONDUIT SHALL TRANSITION TO PVC COATED RIGID STEEL FOR THE PENETRATIONS OR CONNECTION TO JBOX.
 3. **DISPENSER AREA:**
 FOR DISPENSERS, PVC COATED RIGID STEEL CONDUIT SHALL BE USED FOR THE FIRST PIECE OF EXPOSED CONDUIT WITHIN THE BUILDING, TRANSITIONING TO SCH. 40 PVC TO WITHIN 10' OF THE DISPENSER AND/OR TRANSITION SUMPS, WHERE THE CONDUIT SHALL TRANSITION TO PVC COATED RIGID STEEL FOR THE PENETRATIONS.
 4. **CANOPY AREA:**
 FOR CANOPY, PVC COATED RIGID STEEL CONDUIT SHALL BE USED FOR THE FIRST PIECE OF EXPOSED CONDUIT WITHIN THE BUILDING, TRANSITIONING TO SCH. 40 PVC TO WITHIN 10' OF THE CANOPY WHERE THE CONDUIT SHALL TRANSITION TO PVC COATED RIGID STEEL FOR ALL CONNECTIONS TO THE CANOPY.

H1 CONDUIT STUB-UP DETAIL
N.T.S.



WHEN PLACING ELECTRICAL CONDUITS FROM THE TANK PIT TO THE BUILDING, THIS SPECIFICATION SHALL BE FOLLOWED TO INSURE RUNOFF IS NOT INTRODUCED INTO THE TANK PIT, OR OUT OF THE TANK PIT AND TOWARD THE BUILDING.

CONTRACTOR NOTE: CONTRACTOR TO SEPARATE HIGH AND LOW VOLTAGE CONDUITS WITHIN THE CONDUIT TRENCH.

CONTRACTOR NOTE: ELECTRICAL CONDUIT TRENCH FILTER FABRIC NOT NEEDED IF AGG BASE IS USED FOR THE ENTIRE BACKFILL.

A1 ELECTRICAL CONDUIT TRENCH SECTION FROM TANK PIT TO BUILDING
N.T.S.

GENERAL INFORMATION


1. SITE PREPARATION :
 A. CONTRACTOR IS TO ENSURE ALL EXISTING UTILITIES ARE LOCATED AND MARKED PRIOR TO ANY DEMOLITION, CONSTRUCTION OR EXCAVATION ON THE SITE.
 B. THE WIRE SIZES SHALL BE INCREASED IF NECESSARY AS REQUIRED BY NEC. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING REVISED CONDUIT SIZE.
 C. CONDUIT :
 A. FOR EACH ELECTRICAL RACEWAY SYSTEM INDICATED, PROVIDE A COMPLETE ASSEMBLY OF CONDUIT WITH FITTINGS, INCLUDING, BUT NOT NECESSARILY LIMITED TO, CONNECTORS, NIPPLES, COUPLINGS, EXPANSION FITTINGS, BUSHINGS LOCKOUTS, OTHER COMPONENTS AND ACCESSORIES AS NEEDED TO FORM A COMPLETE SYSTEM OF THE TYPE INDICATED, AND AS REQUIRED BY THE NEC.
 B. ALL CONDUIT WITHIN CLASS I AREA SHALL BE PVC COATED HEAVY WALL STEEL EXCEPT AS NOTED OTHERWISE ON THE DRAWINGS. PVC CONDUIT IS ACCEPTABLE FOR USE OUTSIDE CLASS I DIV I AREA. CONTRACTOR MAY SWITCH TO PVC CONDUIT OUTSIDE OF CLASS I AREA PROVIDED ALL INSTALLATIONS COMPLY WITH THE NATIONAL ELECTRICAL CODE AND NFPA 30A. ALL TRANSITION FITTINGS ARE TO BE UL APPROVED FOR DIRECT BURIAL. ALL CONDUIT SHALL BE FREE OF FOREIGN MATTER FROM OBSTRUCTING THE CONDUIT. ALL WIRING AND FITTINGS SHALL BE CLASS I, GROUP O, AS REQUIRED BY CODE. ALL REQUIRED SEAL-OFF FITTINGS SHALL BE PROPERLY SEALED. SEAL SHALL BE Poured AFTER TESTING PROCEDURES ARE COMPLETE.
 C. CONDUIT RUNS EXCEEDING 25 FEET IN LENGTH SHALL BE EQUIPPED WITH SUITABLE WIRE INSERT TO ENABLE THE PULLING OF A FISH TAPE FOR ADDITIONAL WIRING.
 D. WHERE APPLICABLE ALL CONDUIT SHALL BE RIGIDLY SUPPORTED FROM STRUCTURAL MEMBERS WITH MALLEABLE IRON CONDUIT CLAMPS. NOT TO EXCEED 8 FEET ON CENTER. ALL THREAD IS NOT ACCEPTABLE FOR MOUNTING, USE U-BOLTS INSTEAD.
 E. PROVIDE CONDUIT AND FITTINGS AS INDICATED.
 1. PVC COATED RIGID STEEL CONDUIT.
 2. RIGID STEEL CONDUIT FITTINGS : ANSI C80.4.
 3. FLEXIBLE METAL CONDUIT :
 A. LIQUID-TIGHT FLEXIBLE METAL CONDUIT : LIQUID-TIGHT FLEXIBLE METAL CONDUIT COMPRISED OF SINGLE STRIP, CONTINUOUS, FLEXIBLE, INTERLOCKED, DOUBLE-WRAPPED STEEL, GALVANIZED INSIDE AND OUTSIDE, FORMING SMOOTH INTERNAL WIRING CHANNEL WITH LIQUID-TIGHT JACKET OF FLEXIBLE PVC.
 B. LIQUID-TIGHT FLEXIBLE METAL CONDUIT FITTINGS: LIQUID-TIGHT, ZINC COATED STEEL. PROVIDE FITTINGS BY CROUSE-HINDS, APPLETON OR EQUAL. FITTINGS SHALL HAVE RUBBER OR NEOPRENE GASKETS WHERE INSTALLED IN DAMP AREAS. FITTINGS INSTALLED IN HAZARDOUS AREA SHALL COMPLY WITH NEC AND UL 885.
 F. ALL PENETRATIONS THROUGH RATED WALL AND ROOF ASSEMBLIES MUST CONFORM TO UL STANDARD PENETRATION DETAIL, (SYSTEM #F-C-5010), NEC, AND ALL APPLICABLE LOCAL CODES.

2. EQUIPMENT :
 A. ALL EQUIPMENT INSTALLATIONS MUST COMPLY WITH MANUFACTURER'S SPECIFICATIONS AND BE INSTALLED IN ACCORDANCE WITH THE PROVISIONS OF N.E.C. LATEST EDITION AND NFPA 30A. ALL COMPONENTS FOR ELECTRICAL INSTALLATIONS MUST BE UL RATED, BEAR THE UL SEAL, AND COMPLY WITH N.E.C. ARTICLE 110-3, 514-3 AND 514-4. ALL WORKING CLEARANCES IN FRONT OF PANELS AND EQUIPMENT SHALL BE MAINTAINED.
 B. ALL PENETRATIONS THROUGH RATED SLAB ASSEMBLIES MUST CONFORM TO UL STANDARD PENETRATION DETAIL, (SYSTEM #C-AJ-1064), NEC, AND ALL APPLICABLE LOCAL CODES.
 H. MAGNETIC SAFETY TAPE SHALL BE INSTALLED ABOVE ALL UNDERGROUND PRODUCT PIPING AND ELECTRICAL CONDUIT.
 I. ALL CONDUIT LAYOUTS SHOWN ARE FOR REFERENCE ONLY. ACTUAL FIELD INSTALLATION MAY VARY DUE TO MECHANICAL PIPING INTERFERENCE.


3. CABLE AND WIRE CONNECTORS :
 A. WIRE AND CABLE: PROVIDE FACTORY-FABRICATED WIRE AND CABLE OF THE SAME SIZE RATING, MATERIAL AND TYPE AS INDICATED FOR EACH USE, AS SPECIFIED OR UNLESS NOTED OTHERWISE.
 B. CONDUCTORS: PROVIDE SOFT OR ANNEALED COPPER WIRES MEETING, BEFORE STRANDING, THE REQUIREMENTS OF ASTM B-3, STANDARD SPECIFICATIONS FOR SOFT OR ANNEALED COPPER WIRE FOR ELECTRICAL PURPOSES, LATEST EDITION.
 1. CONDUCTORS FOR POWER AND CONTROL WIRING SHALL BE STRANDED COPPER.
 NO ALUMINUM OR COPPER CLAD ALUMINUM WIRING IS PERMITTED.
 2. THE MINIMUM SIZE FOR POWER WIRING IS #12 AWG UNLESS STATED OTHERWISE ON THE DRAWINGS.
 C. INSTALLATION SHALL MEET OR EXCEED THE REQUIREMENTS OF UL 83, STANDARD FOR THERMOPLASTIC INSULATION WIRES.
 1. INSULATION FOR CONDUCTORS SIZED NO. 18 AWG THROUGH NO. 16 AWG SHALL BE UL TYPE TFFN GASOLINE AND OIL RESISTANT AND BE SO MARKED.
 2. INSULATION FOR CONDUCTORS SIZED NO. 14 AWG THROUGH NO. 8 AWG SHALL BE UL TYPE THHN/THWN GASOLINE AND OIL RESISTANT AND BE SO MARKED.
 3. ALL WIRING INSIDE LIGHTING FIXTURES SHALL BE TEMPERATURE RATED PER THE NEC.
 D. CONNECTORS FOR BUILDING WIRE AND CABLE: PROVIDE FACTORY-FABRICATED, METAL CONNECTORS OF THE SIZE, RATING, MATERIAL TYPE, AND CLASS REQUIRED FOR EACH USE.
 1. TERMINAL LUGS ARE TO BE USED WHENEVER POSSIBLE. CONNECTORS FOR CONDUCTORS UP TO A MAXIMUM OF NO. 6 AWG WIRE WITH TWO NO. 8 AWG WIRES MAY USE TWIST-ON PRESSURE CONNECTORS OF REQUIRED SIZE. LUG/BOLTED CONNECTIONS ARE REQUIRED FOR ALL CONDUCTORS LARGER THAN #6 AWG.
 2. ALL MOTOR LEADS, #10 AWG OR LARGER, SHALL BE CONNECTED USING PRESSURE FITTED LUGS AND BOLTED.
 3. SPLICES ARE NOT PERMITTED IN FEEDERS, MOTOR LEADS, OR COMMUNICATION/DATA WIRING.
 4. THE USE OF TERMINAL STRIPS FOR WIRING CONNECTIONS IS ENCOURAGED EXCEPT WHEN IN CONFLICT WITH #3 ABOVE.

5. WIRING NOTES :
DISPENSER POWER SUPPLY WIRING :
 A. CONDUCTOR: #14 AWG (MINIMUM), USE WIRES RATED AT LEAST 90 C (194 F)
 B. VOLTAGE RATING: MAXIMUM OPERATING VOLTAGE OF 600V
 C. ENVIRONMENTAL: GAS AND OIL RESISTANT, UL LISTED WIRE; SUITABLE FOR WET OR DRY LOCATIONS

A7 GENERAL INFORMATION
N.T.S.



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023



QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION


SHEET TITLE:
 CONDUIT GENERAL INFORMATION & DETAILS

SHEET NUMBER:
XF302



F1 DISPENSER SUMP CONDUIT - PLAN

3/8"=1'-0" A1-XF303



A1 DISPENSER CONDUIT SECTION

3/8"=1'-0" F1-XF303

CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023

SIGNATURE DATE:

CORE STATES GROUP

1700 West Loop South, Suite B
 Houston, TX 77056
 Phone: (713) 866-4400
 Fax: (713) 866-4400

QuikTrip No. 4160

7601 W SH 29
 GEORGETOWN, TEXAS

© QUIKTRIP CORPORATION 2022
 ALL RIGHTS RESERVED. NO REPRODUCTION, DISTRIBUTION, OR TRANSMISSION IN ANY FORM OR BY ANY MEANS IS PERMITTED.



PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 DISPENSER CONDUIT LAYOUT & SECTION

SHEET NUMBER:
XF303



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023
 SIGNATURE DATE:
CORE STATES GROUP
 7601 W SH 29
 GEORGETOWN, TEXAS
 PH: (409) 886-4640
 FAX: (409) 886-4640

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© QUIKTRIP CORPORATION 2021
 ALL RIGHTS RESERVED. NO REPRODUCTION, DISTRIBUTION OR SALE OF THIS DOCUMENT IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF QUIKTRIP CORPORATION.
 PROTOTYPE P-110
 DIVISION AUSTIN
 VERSION G3SE
 DATE 05-01-2022


REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
CANOPY CONDUIT LAYOUT


SHEET NUMBER:
XF303.1

A1 DISPENSER CONDUIT SECTION




H1 DISPENSER CONDUIT ELEVATION

3/8"=1'-0" F1-XF303



- (7) DISPENSER CONDUIT (TOTAL):
- DISPENSER POWER, 3/4" (BEYOND) (FROM BLDG)
 - FUTURE, 3/4" (BEYOND) (ROUTE TO FULL BOX)
 - FUTURE, 3/4" (BEYOND) (ROUTE TO FULL BOX)
 - (1) DISPENSER INTERCOM, 3/4" (FROM BLDG OR DISPENSER)
 - (1) DISPENSER INTERCOM LOOP, 3/4" (DISPENSER TO DISPENSER)
 - DISPENSER DATA, 3/4" (FROM BLDG)
 - DISPENSER SUMP SENSOR, 3/4" (FROM BLDG)



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023
 SIGNATURE DATE:
CORE STATES GROUP
 10000 Katy Freeway, Suite B
 Houston, TX 77054
 Phone: (281) 888-4840
 Fax: (281) 888-4840

QuikTrip No. 4160

7601 W SH 29
 GEORGETOWN, TEXAS

QT

© QUIKTRIP CORPORATION 2022
 ALL RIGHTS RESERVED. NO REPRODUCTION, DISTRIBUTION OR SALE OF THIS DOCUMENT IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF QUIKTRIP CORPORATION.

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
(B2)	09/21/22	TANK UPDATE


ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
DISPENSER CONDUIT LAYOUT & DETAILS

SHEET NUMBER:
XF304



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS




PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE


SHEET TITLE:
UST CONDUIT LAYOUT & DETAILS

SHEET NUMBER:
XF305

K1 NOT USED
1/4" = 1'-0"



E1 15K UNLEADED TANK ELECTRICAL SECTION
1/4" = 1'-0"



A1 15K EO/PREMIUM/DIESEL TANK ELECTRICAL SECTION
1/4" = 1'-0"

NOTE:


- REQUIRED FOR DOUBLE WALL FIBERGLASS TANK INSTALLATIONS ONLY.
- SETTING BRINE LEVEL IN RISER PIPE WILL CAUSE FALSE ALARMS!!!!
- SET BRINE LEVEL IN ACCORDANCE WITH XERXES INSTALLATION INSTRUCTIONS AS FOLLOWS:


PROBE INSTALLATION

- IF THE TANK CONTAINS PRODUCT, STICK THE TANK AND SET THE MONITORING-FLUID LEVEL BASED ON THE PRODUCT LEVEL.
- IF THE TANK IS BETWEEN EMPTY AND 1/4 FULL, SET THE MONITORING-FLUID LEVEL AT ABOUT 1 - 1 1/2 INCHES BELOW THE MIDPOINT OF THE PROBE.
- IF THE PRODUCT LEVEL IS BETWEEN 1/4 AND 1/2 FULL, SET THE MONITORING-FLUID LEVEL TO THE MIDPOINT OF THE PROBE.
- IF THE PRODUCT LEVEL IS BETWEEN 1/2 FULL AND FULL, SET THE MONITORING-FLUID LEVEL TO ABOUT 1 - 1 1/2 INCHES ABOVE THE MIDPOINT OF THE PROBE.
- IF THERE IS NO BRINE VISIBLE IN THE RESERVOIR WHEN THE TANK ARRIVES, IMMEDIATELY CONTACT XERXES

TANK SIZE	LIQUID LEVEL MEASUREMENT (L) WHEN TANK IS EMPTY	LIQUID LEVEL MEASUREMENT (L) WHEN TANK IS FULL
8' (24M)	3 1/2"	5"
10' (20M)	4"	6 1/2"

FOR COMPARTMENT TANKS, USE TOTAL VOLUME OF ALL COMPARTMENTS TO DETERMINE TANK SIZE.





K1 AUTOMATIC TANK GAUGE

K6 OBSERVATION WELL


K9 NOT USED

K12 TANK SUMP ELECTRICAL ELEVATION (B2)

1/2" = 1'-0"
A9/U9-XF203 A1/E1-XF305 A1/J1-XF402 A1-XF412

N.T.S.
E1/J1-XF305

3/4" = 1'-0"
A1/E1-XF305



ALL CONDUIT ENTRY POINTS TO BE AS CLOSE TO CORNER OF SUMP AS POSSIBLE.

SENSOR WIRE FOR MULTI-PORT SHALL BE ROUTED TO J-BOX AT TANK MONITOR. EXPOXY PACK TERMINATIONS TO BE MADE IN TANK MONITOR J-BOX TO ALLOW FOR FUTURE REMOVAL/REPLACEMENT OF SENSOR WITHOUT DISASSEMBLY OF MULTI-PORT.

A1 TANK & TRANSITION SUMP ELECTRICAL PLAN (B2)

1/2" = 1'-0"

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
(B2)	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 9/22/2022

SHEET TITLE:
UST CONDUIT LAYOUT & DETAILS



SHEET NUMBER:
XF306

WIRING NOTE:
 - IN ORDER TO ENSURE THE BEST OPERATING SYSTEMS AVAILABLE, VEEDER-ROOT REQUIRES THE USE OF SHIELDED CABLE FOR ALL PROBES AND SENSORS, REGARDLESS OF CONDUIT MATERIAL OR APPLICATION. IN THESE INSTALLATIONS, SHIELDED CABLE MUST BE RATED LESS THAN 100 PICOFARADS PER FOOT AND BE MANUFACTURED WITH A MATERIAL SUITABLE FOR THE ENVIRONMENT.
 - ALL WIRING MUST BE INSTALLED IN ACCORDANCE WITH CLASS 1, DIV 1 SPECIFICATIONS.
 - ANY SPLICED CONNECTIONS FOR PROBES OR SENSORS SHOULD BE ENCLOSED IN PLASTIC BAG FILLED WITH EPOXY SEALANT.
 - CONTRACTOR TO PROVIDE SEALING FITTINGS ON ALL CONDUITS ENTERING OR LEAVING DISPENSER SUMPS.


NOTE:
 VEEDER ROOT CONSOLE TO BE EQUIPPED WITH MODULES TO ALLOW FOR SHUTDOWN OF SUBMERSIBLE PUMPS UPON SUMP SENSOR ACTIVATION IN EITHER COMMERCIAL/DIESEL OR RETAIL/GASOLINE SYSTEM.

NOTE:
 PROGRAM UNIT AS PER QUIKTRIP SPECIFICATIONS. COORDINATE WITH QUIKTRIP REPRESENTATIVE FOR SPECIFIC REQUIREMENTS.

SENSOR WIRE FOR MULTI-PORT SHALL BE ROUTED TO J-BOX AT TANK MONITOR. EPOXY PACK TERMINATIONS TO BE MADE IN TANK MONITOR J-BOX TO ALLOW FOR FUTURE REMOVAL/REPLACEMENT OF SENSOR WITHOUT DISASSEMBLY OF MULTI-PORT.



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023



QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© QUikTRIP CORPORATION 2011
 ALL RIGHTS RESERVED. NO REPRODUCTION, DISTRIBUTION, OR SALE OF THIS DOCUMENT IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF QUikTRIP CORPORATION.

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 VEEDER ROOT SCHEMATIC & DETAILS

SHEET NUMBER:
XF307

SENSING OPTIONS

VEEDER ROOT CONSOLE TLS 450 c/w PRINTER		VR-860090-100		
QTY	MODULE MODEL #	SENSOR/PROBE MODEL #	MODEL NUMBER	QTY
2	UNIVERSAL SENSOR/PROBE MODULE VR-332812-001	NON-DISCRIMINATING INTERSTITIAL SENSOR FOR STEEL TANKS	794380-460	5
		NON-DISCRIMINATING DISPENSER PAN AND CONTAINMENT SUMP SENSORS	794380-208 (w/12' CABLE) 794380-209 (w/30' CABLE)	-
		MAG PLUS MAGNETOSTRICTIVE TANK LEVEL MONITOR PROBE	846396-109 (10') USE ON 10'-0"Ø TANK 846396-111 (11') USE ON 10'-6"Ø TANK 846396-112 (12') USE ON 11'-6"Ø TANK	5
		NOT USED	NOT USED	-
1	UNIVERSAL INPUT/OUTPUT MODULE VR-332813-001	PLLD LINE LEAK SENSOR	859080-001 (F.E. PETRO PUMPS)	5

COMMUNICATIONS OPTIONS


RISK MGMT LEAK DETECTION PLLD	VR-32912-008	1
USB/ETHERNET DUAL MODULE	INCLUDED w/TLS 450 CONSOLE	-
RS-232 DUAL INTERFACE MODULE	INCLUDED w/TLS 450 CONSOLE	-
PRINTER INTERFACE	INCLUDED w/TLS 450 CONSOLE	-

HARDWARE/SOFTWARE

PROBE INSTALLATION KITS (GASOLINE)	849800-000	4
PROBE INSTALLATION KITS (DIESEL)	849800-001	1
4" COMPOSITE CAP AND RING KIT (MAG PROBES)	312020-282	-
SUMP SENSOR MOUNTING KIT	330020-012	-
4" METAL CAP AND RING KIT (MAG PROBES)	312020-952	5


H1 SCHEDULES

NTS.




MAGNETOSTRICTIVE TANK LEVEL MONITOR PROBE

DESCRIPTION: NON-DISCRIMINATING SENSORS FOR SENSING WATER AND PETROLEUM IN SUMPS.



NON-DISCRIMINATING DISPENSER PAN AND CONTAINMENT SUMP SENSORS

DESCRIPTION: FOR MONITORING BRINE LEVELS IN DOUBLE WALL FRP BRINE MONITORED TANKS.




HYDROSTATIC RESERVOIR SENSORS (BRINE)

A1 VEEDER DETAILS

NTS.


L8 STP SUMP SENSOR

1" = 1'-0"




F8 DISPENSER SUMP SENSOR

1" = 1'-0"




A8 TRANSITION SUMP SENSOR

1" = 1'-0"



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS




PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
VEEDER ROOT
SCHEDULE & DETAILS

SHEET NUMBER:
XF308



N.E.C. HAZARDOUS AREA NOTES

- A** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (UNDERGROUND TANK - FILL OPENING)
EXTENT OF CLASS 1, GROUP D, DIVISION 1 LOCATION:
ANY PIT, BOX, OR SPACE BELOW GRADE LEVEL, ANY PART OF WHICH IS WITHIN THE DIVISION 1 OR 2 CLASSIFIED LOCATION.
- B** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (UNDERGROUND TANK - VENT DISCHARGING UPWARD)
EXTENT OF CLASS 1, GROUP D, DIVISION 1 LOCATION:
WITHIN 5 FEET OF OPEN END OF VENT, EXTENDING IN ALL DIRECTIONS.
- C** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (REMOTE PUMP - OUTDOOR)
EXTENT OF CLASS 1, GROUP D, DIVISION 1 LOCATION:
ANY PIT, BOX, OR SPACE BELOW GRADE LEVEL IF ANY PART IS WITHIN A HORIZONTAL DISTANCE OF 10 FEET FROM ANY EDGE OF PUMP.
- D** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (DISPENSING DEVICE - PITS)
EXTENT OF CLASS 1, GROUP D, DIVISION 1 LOCATION:
ANY PIT, BOX, OR SPACE BELOW GRADE LEVEL, ANY PART OF WHICH IS WITHIN THE DIVISION 1 OR 2 CLASSIFICATION LOCATION.
- E** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (DISPENSING DEVICE - DISPENSER)
EXTENT OF CLASS 1, GROUP D, DIVISION 1 LOCATION:
SPACE CLASSIFICATION INSIDE THE DISPENSER ENCLOSURE IS COVERED IN ANSIIUL 87, "POWER OPERATED DISPENSING DEVICES FOR PETROLEUM PRODUCTS."
- F** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (DISPENSING DEVICE - DISPENSER)
EXTENT OF CLASS 1, GROUP D, DIVISION 2 LOCATION:
WITHIN 18 INCHES HORIZONTALLY IN ALL DIRECTIONS EXTENDING TO GRADE FROM (1) THE DISPENSER ENCLOSURE OR (2) THAT PORTION OF THE DISPENSER ENCLOSURE CONTAINING LIQUID HANDLING COMPONENTS. SPACE CLASSIFICATION INSIDE THE DISPENSER ENCLOSURE IS COVERED IN ANSIIUL 87, "POWER OPERATED DISPENSING DEVICES FOR PETROLEUM PRODUCTS."
- G** TYPICAL N.E.C. ARTICLE 514 CLASS 1 LOCATION (DISPENSING DEVICE - OUTDOOR)
EXTENT OF CLASS 1, GROUP D, DIVISION 2 LOCATION:
UP TO 18 INCHES ABOVE GRADE LEVEL WITHIN 20 FEET HORIZONTALLY OF ANY EDGE OF ENCLOSURE.






CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023



K1 NEC CLASSIFIED AREA AT GROUND LEVEL

K10 NEC HAZARDOUS AREA NOTES



A1 NEC CLASSIFIED AREA AT DISPENSERS

A6 NEC CLASSIFIED SIDE ELEVATION

A12 NEC CLASSIFIED FRONT ELEVATION

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE

SHEET TITLE:
NEC CLASSIFIED AREAS


SHEET NUMBER:
XF310

ELECTRICAL EQUIPMENT LIST AND CONNECTION SCHEDULE

TAG #	DESCRIPTION	MAKE & MODEL	VOLTAGE / PHASE / WIRE	LOAD AMPS	TYPE OF CONNECTION	WIRE AND CONDUIT	MOUNTING HEIGHT (AFF)	FURNISHED BY	ITEM REMARKS
302	EMERGENCY GASOLINE SHUT-OFF SWITCH	PILLA #FSI20M0GRYCLMXD	24VAC/2W	-	HARDWIRED		*	GC	*SEE DETAIL A9/XF311



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023





QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION

SHEET TITLE:
 DETAILS

SHEET NUMBER:
 XF311



SUMMARY OF INTEGRATED HV AND LV DISCONNECT SYSTEM:
 FULL NEC 514 COMPLIANCE INTEGRATED HV AND LV DISCONNECTING MEANS

SYSTEM INCORPORATES A FUEL CONTROL PANEL THAT IS INTEGRATED INTO THE PREMANUFACTURED CABINET, FORMER E-STOP BOX AND CONTACTORS, ALONG WITH THE F.E. PETRO DHI RELAY FUNCTIONS ARE ALL INTEGRATED INTO THE CONTROL PANEL. SYSTEM AND COMPONENTS SHALL BE PRE-WIRED TO THE EXTENT POSSIBLE WITHIN THE CABINET, INCLUDING ALL LOW VOLTAGE COMMUNICATION CABLES TO THE PANEL SYSTEM OR LINE SIDE OF THE LOW VOLTAGE WIRING TERMINALS.


ON-OFF SWITCH(ES) SHALL BE PROVIDED BY GENERAL CONTRACTOR AS SCHEDULED, WIRED AS INDICATED AND PER MFR INSTALLATION INSTRUCTIONS.

RE: XF 300 FOR LOCATIONS.

1. SYSTEM SHALL PRE WIRE FOR STP POWER, DISPENSER POWER AND COMMUNICATIONS ON A TERMINAL BLOCK FOR TERMINATION OF FIELD WIRING.
2. SYSTEM SHALL PRE-WIRE HOOK SIGNALS IN A COLOR CODED ROW OF TERMINALS ALL SIDE BY SIDE AT THE BOTTOM OF THE PANEL.
3. CONTROL PANEL DESIGN SHALL INCLUDE A "DIESEL" TERMINAL BLOCK FOR ANY DISPENSER WIRED AS A SPARE.
4. CONTROL PANEL DESIGN SHALL BE FULLY COMPLIANT WITH 514-11 AND 514-13. THE EMERGENCY SHUTOFF SHALL BE SET UP SUCH THAT ANY ONE KILL SWITCH WILL SHUT DOWN THE ENTIRE SYSTEM, INCLUDING OPENING ALL LINE VOLTAGE AND LOW VOLTAGE WIRES TO THE DISPENSERS AND FUEL PUMPS. A MANUAL RESET BUTTON LOCATED IN THE ELECTRICAL CABINET ACCESSIBLE TO AUTHORIZED PERSONNEL SHALL BE REQUIRED FOR RE-ENERGIZING THE SYSTEM.
5. IN ADDITION, A SINGLE DISCONNECTING SWITCH SHALL BE LOCATED ON THE CONTROL PANEL TO ALLOW SERVICING TO ANY SINGLE DISPENSER BY DISCONNECTING BOTH THE DISPENSER POWER AND COMMUNICATIONS/DATA TO THAT DISPENSER ONLY WHILE LEAVING THE REMAINDER OF THE LOCATION UP AND RUNNING.

A1 MULTI CONTROLLER WIRING DIAGRAM

A9 EMERGENCY FUEL CUTOFF DIAGRAM



I. GENERAL NOTE:

THE CONTRACTOR ACCEPTS FULL RESPONSIBILITY FOR PROPER HANDLING AND INSTALLATION OF THE GASOLINE UNDERGROUND STORAGE TANKS AND SHALL INSURE THAT GOOD WORKMANSHIP PRACTICES AND CONSTRUCTION PROCEDURES ARE FOLLOWED REGARDLESS OF THE INCLUSION OR OMISSION OF ANY INSTRUCTION.

UNKNOWN SITUATIONS OR CONDITIONS NOT COVERED IN THESE AND THE MANUFACTURER'S INSTRUCTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR. MANUFACTURER'S SPECIALISTS ARE AVAILABLE FOR CONSULTATION. THE PRESENCE OF THE MANUFACTURER OR OBSERVER AT AN INSTALLATION SITE DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY FOR THE PROPER INSTALLATION OF THE TANKS.


QUESTIONS REGARDING INSTALLATION PROCEDURES OR TANK REPAIRS SHOULD BE DIRECTED TO THE QUIKTRIP FIELD REPRESENTATIVE.

GASOLINE UNDERGROUND TANKS MUST BE INSTALLED ACCORDING TO THESE INSTRUCTIONS, THE MANUFACTURER'S INSTRUCTIONS AND NFPA 30 AND 30A. LOCAL CODES MAY APPLY AND MUST BE ADHERED TO. FAILURE TO FOLLOW THESE INSTALLATION INSTRUCTIONS WILL VOID THE WARRANTY AND WILL RESULT IN TANK FAILURE. PROPER INSTALLATION OF GASOLINE UNDERGROUND STORAGE TANKS HELPS PREVENT TANK DAMAGE AND SHOULD INSURE LONG-TERM CORROSION-PROOF SERVICE. IT IS IMPERATIVE TO READ, UNDERSTAND AND FOLLOW THESE INSTRUCTIONS.

THESE SPECIFICATIONS ARE SUPPLEMENTED BY THE RESPECTIVE TANK MANUFACTURER'S SPECIFICATIONS. THE INSTALLATION PROCEDURE SHALL COMPLY WITH BOTH SETS OF INSTRUCTIONS AND SPECIFICATIONS. IF, IN THE CONTRACTOR'S JUDGMENT, THERE APPEARS TO BE A CONFLICT IN THESE SPECIFICATIONS AND THE TANK MANUFACTURER'S INSTRUCTIONS, CONTACT THE LOCAL QUIKTRIP REPRESENTATIVE FOR CLARIFICATION AND GUIDANCE.

1. ALL PRODUCT LINES ARE SECONDARILY CONTAINED.
2. EVERY TANK CONTAINMENT SUMP AND DISPENSER CONTAINMENT SUMP SHALL CONTAIN A LIQUID SENSING PROBE.
3. PERPENDICULAR PENETRATIONS OF THE CONTAINMENT SUMPS ARE PREFERRED. 5° IS THE MAXIMUM ALLOWABLE PENETRATION ANGLE.
4. SPARE ELECTRICAL CONDUITS MUST BE SEALED.
5. SEE ELECTRICAL SHEETS FOR ELECTRICAL CONDUIT LAYOUT.
6. FILL, VENT/VAPOUR AND AUTOMATIC TANK GAUGE RISER MUST BE SCHEDULE 40 PRIMED AND WRAPPED PIPE. EACH RISER MUST BE PRIMED AND WRAPPED IF BACK FILL IS TOUCHING THE RISER.
7. AMERON ADHESIVE EPOXY KIT SHALL BE USED ON ALL PIPE CONNECTION FITTINGS, STP SUMP ENTRY FITTINGS AND TRANSITION SUMP ENTRY FITTINGS.

K1 TRANSITION SUMP ISOMETRIC VIEW



HYDROSTATIC SUMP TESTING STANDARD
NEW STORE

HYDROSTATIC TESTING OF ALL DISPENSER, TANK TOP, AND TRANSITION SUMPS WILL BE MANDATORY. ALL PETROLEUM PRODUCT, AND DIESEL EXHAUST FLUID SUMPS IN ALL MARKETS ARE TO BE INCLUDED.

DURING THE CONSTRUCTION PROCESS, ALL SUMPS SHOULD BE PROTECTED FROM STORMWATER, AND DEBRIS. CORROSION OF METALLIC PARTS PRIOR TO PLACING THE SITE INTO SERVICE SHOULD BE KEPT TO A MINIMUM.

PRIOR TO TESTING SUMPS THE FOLLOWING WORK WILL NEED TO BE COMPLETED.

- ALL EQUIPMENT INSTALLATION HAS BEEN COMPLETED WITHIN SUMPS, ALL BOOTS IN PLACE
- JUMPER TUBES CONNECTED WITHIN SUMP
- SUMPS HAVE BEEN CLEANED OF DIRT, AND DEBRIS
- ALL ELECTRICAL WORK HAS BEEN COMPLETED, AND INSPECTED

ALL TESTING WILL BE PERFORMED, AND PASSED PRIOR TO THE INTRODUCTION OF PETROLEUM, OR OTHER PRODUCTS TO TANKS, OR LINES.

TEST PROCESS:

- TESTS TO BE PERFORMED USING CLEAN MUNICIPALLY TREATED WATER.
- TEMPORARY CAPS TYPICALLY USED IN PLUMBING SYSTEMS WILL NEED TO BE USED TO SEAL ALL OPEN 4 INCH VENTILATION LINES IN TANK SUMPS.
- MAINTAIN 5 PSI OF PRESSURE ON SECONDARY PIPING UNTIL A PASSING RESULT IS OBTAINED
- TEST ALL SUMPS AT AN ELEVATION OF APPROX. 2 INCHS ABOVE THE HIGHEST SEALED PENETRATION.
- FOR THE PURPOSE OF CONSISTENCY QUIKTRIP WILL REQUIRE THE USE OF A "CALDWELL SUMP TESTER" AVAILABLE THROUGH CALDWELL INSTRUMENTS. PHONE #(916)259-4567.
- A PASSING TEST WILL REQUIRE NO MOVEMENT IN THE TEST DEVICE INDICATOR FOR A TERM OF ONE HOUR. A PRE-TEST MAY BE ADVISED TO DETERMINE THE EXISTENCE OF HIGH VOLUME LEAKS
- QUIKTRIP WILL REQUIRE THE REMOVAL OF ALL WATER IN SUMPS IMMEDIATELY AFTER PASSING TEST RESULTS ARE DOCUMENTED. THE REMOVAL OF CLEAN SYSTEM WATER SHOULD NOT REQUIRE ANY TYPE OF DISPOSAL CONSIDERATIONS.
- THE PROCESS FOR TESTING SUMPS, AND DISPOSING OF WATER ON FACILITIES THAT HAVE BEEN PLACED INTO OPERATION SHALL BE COORDINATED WITH QUIKTRIP REPRESENTATIVE PRIOR TO TESTING FOR APPROVAL FROM QUIKTRIP ENVIRONMENTAL GROUP.
- ALL SUMPS MUST PASS THIS TEST PRIOR TO THE INTRODUCTION OF MOTOR FUEL PRODUCTS INTO THE TANKS, OR LINES
- THIS TESTING PROCESS IS INTENDED TO COMPLY WITH QUIKTRIP'S DESIRE TO VERIFY THAT ALL SUMPS ARE LIQUID TIGHT PRIOR TO OPERATING ANY SYSTEM. THIS TESTING PROCESS MAY NEED TO BE MODIFIED IN ORDER TO COMPLY WITH STATE BY STATE REQUIREMENTS.
- REPORTING WILL BE REQUIRED BY SITE, AND BY SUMP. DOCUMENTATION SHALL BE FORWARDED TO THE QUIKTRIP ENVIRONMENTAL GROUP ALONG WITH OTHER REQUIRED FUEL SYSTEM DOCUMENTATION.

TANK NUMBERING:

TANK #1	15K UNLEADED #1
TANK #2	15K UNLEADED #2
TANK #3	15K EO
TANK #4	15K PREMIUM
TANK #5	15K DIESEL

CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#0349
EXPIRES 07-31-2023

SIGNATURE DATE:

CORE STATES GROUP

10000 Highway 190, Suite B
Houston, TX 77058
Phone: (281) 888-4440
Fax: (281) 888-4440

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS


PROTOTYPE: P-110
DIVISION: AUSTIN
VERSION: G3SE
DATE: 05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE
03	03/27/23	COORDINATION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
UNDERGROUND PIPING SYSTEM PLAN

SHEET NUMBER:
XF401



CORE STATES GROUP
 1700 W. SH 29, Suite B
 Georgetown, TX 78626
 Phone: (714) 888-4840
 Fax: (714) 888-4840

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS


PROTOTYPE: P-110
 DIVISION: AUSTIN
 VERSION: G3SE
 DATE: 05-01-2022

REV	DATE	DESCRIPTION
(B2)	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
 TANK TOP EQUIPMENT DETAILS

SHEET NUMBER:
 XF403



NOTES:

- ALL METAL PIPING COMPONENTS AND RISERS INSIDE THE TANK SUMPS SHALL BE BLACK IRON COAT/PRIME PER SPEC RE: XF101 UNLESS OTHERWISE NOTED.
- PRESET PUMP SETTING PER MANUFACTURERS INSTRUCTIONS

NOTES:


- INSTALL CENTRALIZERS PER MANUFACTURES RECOMMENDATION AND 6" FROM END OF PIPING RUN.

NOTE:
LOCATION OF SUMP PENETRATION WILL VARY. THE INTENT OF THIS DRAWING IS TO ILLUSTRATE THE CORRECT PLACEMENT AND CONNECTION OF PIPING WITHIN THE SUMP.





- ALL BALL VALVES TO BE SEALED WITH RECTORSEAL #5 PIPE THREAD SEALANT WITH TEFLON.
- ELECTRICAL CONDUITS NOT SHOWN FOR CLARITY
- ALL PIPING SHALL BE INSPECTED/CONFIRMED TO BE CLEAR OF ALL BEDDING MATERIAL, TRASH, ANY TYPE OF LIQUID OR DEBRIS PRIOR TO AND AFTER INSTALLATION.
- PREP SUMP FOR ALL FITTINGS WITH BRAVO SAND KIT #T-FF-SAND-FX (BY G.C.).
- COAT ALL FITTING AND PIPE PER MANUFACTURES INSTALLATION INSTRUCTION. INSURE ALL RAW FIBERGLASS AREAS HAVE BEEN NEATLY COATED WITH ADHESIVE.

INTELLIGENT PUMP CONTROL CONFIGURATIONS:

- DS 7 OR LESS WITH 3 UNLEADED TANKS
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 1 - UNLEADED 2= SATELLITE STP #2
 - SEGMENT 1 - UNLEADED 3= SATELLITE STP #2
- DS 7 OR LESS WITH 4 UNLEADED TANKS
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 1 - UNLEADED 2= SATELLITE STP #1
 - SEGMENT 1 - UNLEADED 3= SATELLITE STP #2
 - SEGMENT 1 - UNLEADED 4= SATELLITE STP #3
- DS 8 OR GREATER WITH 3 UNLEADED TANKS
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 2 - UNLEADED 2= SATELLITE STP #1
 - SEGMENT 2 - UNLEADED 3= SATELLITE STP #2
 - SEGMENT 2 - UNLEADED 4= SATELLITE STP #2
- DS 8 OR GREATER WITH 4 UNLEADED TANKS
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 1 - UNLEADED 2= SATELLITE STP #1
 - SEGMENT 1 - UNLEADED 3= SATELLITE STP #2
 - SEGMENT 1 - UNLEADED 4= SATELLITE STP #3
- VERTICAL WITH 3 UNLEADED TANKS (REMOTE OR OFFSET TANK LOCATION).
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 1 - UNLEADED 2= SATELLITE STP #1
 - SEGMENT 1 - UNLEADED 3= SATELLITE STP #2
- VERTICAL WITH 4 UNLEADED TANKS (REMOTE OR OFFSET TANK LOCATION).
 - SEGMENT 1 - UNLEADED 1 = MASTER STP #1
 - SEGMENT 1 - UNLEADED 2= SATELLITE STP #1
 - SEGMENT 1 - UNLEADED 3= SATELLITE STP #2
 - SEGMENT 1 - UNLEADED 4= SATELLITE STP #3



GC TO COORDINATE TRANSITION SUMP BALL VALVE OPEN/CLOSE POSITIONS WITH QT CONSTRUCTION MANAGER. BALL VALVE HANDLES TO BE REMOVED IN TRANSITION SUMPS ONLY AND GIVEN TO QT CONSTRUCTION MANAGER AFTER OPEN/CLOSE POSITIONS ARE VERIFIED.



CORE STATES, INC.
CERTIFICATE OF AUTHORIZATION
#3349
EXPIRES 07-31-2023



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022



REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 9/22/2022


SHEET TITLE:
UST, TRANSITION SUMP AND MISCELLANEOUS DETAILS

SHEET NUMBER:
XF406

A1 TANK AND TRANSITION SUMP DETAILED PLAN



CORE STATES, INC.
 CERTIFICATE OF AUTHORIZATION
 #0349
 EXPIRES 07-31-2023



QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS






PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE

SHEET TITLE:
 UST, TRANSITION SUMP
 AND MISCELLANEOUS
 DETAILS

SHEET NUMBER:
XF406.1




A1 NOT USED
 3/4" = 1'-0"



H1 UNLEADED TANK SIPHON ONLY DETAILS

H8 PIPE SUPPORT IN TRANSITION SUMP DETAIL

H12 SIPHON GAUGE DETAIL



A1 DOUBLE WALL PIPE COUPLING DETAIL

A5 UNDERGROUND PIPING TRENCH AND COVER DETAIL

A12 FIBERGLASS PIPING FITTING AND CONNECTION TYPICAL DETAILS

CORE STATES GROUP

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS


PROTOTYPE: P-110
DIVISION: AUSTIN
VERSION: G3SE
DATE: 05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
UST & PIPING DETAILS


SHEET NUMBER:
XF407



K1 NOT USED


K7 3+1 DIESEL GASOLINE DISPENSER ELEVATION

K12 3+1 EO GASOLINE DISPENSER ELEVATION




E1 NOT USED


E4 DISPENSER FOOTPRINT 3+1




E8 PRODUCT CONNECTION END OF PIPING RUN (SECTION)




E12 SHEAR VALVE DETAIL (FOR ADA ISLANDS)




A1 END OF PIPING RUN (PLAN)



A4 PRODUCT CONNECTION AT ISLANDS THROUGH DETAIL



A8 PRODUCT CONNECTION



A12 SHEAR VALVE DETAIL (NON-ADA)

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS




QT	
PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
DISPENSER & PIPING
DETAILS



SHEET NUMBER:
XF408



L1 FUTURE PRODUCT PIPING CONNECTION SHOWN ONLY (B2)
1 1/2" = 1'-0"



L6 SHEAR VALVE INSTALLATION
1" = 1'-0"

L11 DIESEL CROSSOVER (B2)
1 1/2" = 1'-0"



F1 NOT USED

F6 SUMP DIMENSION DETAIL (B2)
1" = 1'-0"



A1 3+1 DISPENSER SUMP SECTION (B2)
1" = 1'-0"

A6 NOT USED
1-1/2" = 1'-0"

A11 TEST TUBE DETAIL (B2)
1 1/2" = 1'-0"

CORE STATES GROUP
7601 W SH 29
GEORGETOWN, TEXAS

QuikTrip No. 4160


PROTOTYPE	P-110
DIVISION	AUSTIN
VERSION	G3SE
DATE	05-01-2022

REV	DATE	DESCRIPTION
(B2)	09/21/22	TANK UPDATE

ORIGINAL ISSUE DATE: 9/22/2022

SHEET TITLE:
DISPENSER & PIPING DETAILS

SHEET NUMBER:
XF409




L1 VENT CONFIGURATION
3/16" = 1'-0"

L5 SUMP VENTILATION INLET DETAIL
3/16" = 1'-0"

L9 SUMP VENTILATION DISCHARGE DETAIL
3/16" = 1'-0"

L13 SUMP SECTION
3/4" = 1'-0"



A1 VENT/DUCT PIPING ENLARGED DETAIL (B2 X B4)
1/4" = 1'-0"

A15 SWING JOINT DETAIL
1" = 1'-0"

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT

PROTOTYPE: P-110
DIVISION: AUSTIN
VERSION: G3SE
DATE: 05-01-2022

REV	DATE	DESCRIPTION
B2	09/21/22	TANK UPDATE
B4	03/27/23	COORDINATION

ORIGINAL ISSUE DATE: 8/22/2022

SHEET TITLE:
VAPOR, VENT DETAILS

SHEET NUMBER:
XF410

LEGEND			
EQUIPMENT LOCATION ON SITE			
ABBREVIATION	INSTALLATION LOCATION IN SYSTEM		
U.A.	UST AREA		
D.A.	DISPENSER AREA		
U.S.	UST SUMP		
T.S.	TRANSITION SUMP		
D.S.	DISPENSER SUMP		
T.T.E.	TANK TOP EQUIPMENT		
S.B.	STORE BUILDING		
COUNTY / AREA SENSITIVE EQUIPMENT			
ABBREVIATION	FACILITY LOCATION	STATE	VAPOR RECOVERY REQUIRED
(ATL)	ATLANTA AREA	GEORGIA	STAGE I
(DAL)	DALLAS AREA	TEXAS	STAGE I
(OMA)	OMAHA AREA	NEBRASKA	STAGE I
(IWA)	IOWA AREA	IOWA	STAGE I
(STL)	ST. LOUIS AREA	MISSOURI	STAGE I
(PHX)	PHOENIX AREA	ARIZONA	STAGE I
(KC)	KANSAS CITY AREA	KANSAS	STAGE I
(WIC)	WICHITA AREA	KANSAS	STAGE I
(TUL)	TULSA AREA	OKLAHOMA	STAGE I
(TUC)	TUCSON AREA	ARIZONA	STAGE I
(NC)	CHARLOTTE AREA	N. CAROLINA	STAGE I
(SC)	SOUTH CAROLINA AREA	S. CAROLINA	STAGE I
PARTS LISTED IN BILL OF MATERIAL WITHOUT ADDED ABBREVIATION IN THE EQUIPMENT DESCRIPTION ARE STANDARD			

GENERAL EQUIPMENT					
TAG	EQUIPMENT DESCRIPTION	PROVIDED	MFG MODEL #	LOCATION	QUANTITY
101	20,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANKS.	OWNER	660-219-00	U.A.	-
102	12,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANKS	OWNER	660-216-00	U.A.	-
103	TANK HOLD DOWN STRAPS	OWNER	10 FOOT STRAP 8 FOOT STRAP	U.A.	20 0
104	TURNBUCKLE - GALVANIZED	OWNER	10 FOOT TURNBUCKLE 8 FOOT TURNBUCKLE	U.A.	40 0
105	CONCRETE DEADMAN CAST IN PLACE. SEE QUIKTRIP REPRESENTATIVE FOR REQUIREMENTS	CONTRACTOR	-	U.A.	-
106	NUMBER CURRENTLY NOT USED	-	-	-	-
107	STEEL ISLAND FORMS 2'-8"x5'-0"	OWNER	#RS-2.8X513 GALV	D.A.	4
	STEEL ISLAND FORMS 2'-8"x5'-0" (ADA)	-	#RS-1632051309GF	-	4
108	NUMBER CURRENTLY NOT USED	-	-	-	-
109	DEEP BURY TANK STICK 3 PC 20"	OWNER	B6-3520	U.A.	1
110	NUMBER CURRENTLY NOT USED	-	-	-	-
111	FIRE EXTINGUISHER MIN. SIZE AS PER LOCAL INSPECTOR	OWNER	SUPPLIED LOCALLY	D.A.	2
112	SAMSON IND. FIRE EXTINGUISHER CABINET WHITE W/ HAMMER AND CHAIN. SURFACE MOUNT OR EQUAL	CONTRACTOR	#9263230	D.A.	2
113	WASHER BUCKET W/QT GRAPHICS.	OWNER	DC-5WBC-6H	D.A.	16
114	NUMBER CURRENTLY NOT USED	-	-	-	-
115	12" DIA MONITOR/OBSERVATION WELL MANKAY	OWNER	OPW 104A0W-1200	U.A.	2
116	6 INCH DIA MONITOR/OBSERVATION WELL CAP	OWNER	GRAINGER- 270261	U.A.	2
117	6 INCH FACTORY SLOTTED PVC PIPE, 2" SLOTS OR PER LOCAL REQUIREMENTS W/ CAPPED BOTTOM. ATLANTIC SCREEN OR EQUIV.	CONTRACTOR	-	U.A.	-
118	18" DIA MONITOR/OBSERVATION WELL MANKAY	OWNER	OPW 104A0W-1800	U.A.	1
119	12" DIA MONITOR/OBSERVATION WELL CAP	OWNER	TITAN CAP-12	U.A.	1
120	12" FACTORY SLOTTED PVC PIPE, 2" SLOTS OR PER LOCAL REQUIREMENTS W/ CAPPED BOTTOM. ATLANTIC SCREEN OR EQUIV.	CONTRACTOR	-	U.A.	-
121	STEEL BOLLARD W/ CAP AND SLEEVE BY S4M- SCH40 (END PAINTED ORANGE)	OWNER	E823240	D.A.	16
122	STEEL BOLLARD W/ CAP AND SLEEVE BY S4M- SCH80 (END PAINTED GREEN)	OWNER	E826216	D.A.	16
123	BACKFILL SHIELD MATERIAL APPROVED BY SITE REPRESENTATIVE	CONTRACTOR	-	U.A.	-
124	20,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANKS.	OWNER	660-225-00	U.A.	-
125	19,500 GALLON, COMPARTMENTAL DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK, 10/4500 SPLIT, PREMIUM / PRODUCT X	OWNER	660-226-00	U.A.	-
126	12,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANKS.	OWNER	660-223-00	U.A.	-
127	NUMBER CURRENTLY NOT USED	-	-	-	-
128	19,500 GALLON, COMPARTMENTAL DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK, 10/4500 SPLIT, PREMIUM / PRODUCT X	OWNER	660-221-00	U.A.	-
129	12,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK (10' DIAMETER)	OWNER	660-224-00	U.A.	-
130	15,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK (10' DIAMETER)	OWNER	658-546-01	U.A.	5
131	12,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK (10' DIAMETER)	OWNER	660-217-00	U.A.	-
132	20,000 GALLON DOUBLE WALL FIBERGLASS UNDERGROUND STORAGE TANK (10' DIAMETER)(SQUARE SUMP)	OWNER	660-802-00	U.A.	-
133	GAS DISPENSER FILTER (PETRO CLEAR)	OWNER	PF-40510P-AD	D.A.	-
134	AUTO DIESEL FILTER (PETRO CLEAR)	OWNER	PF-40530P-AD	D.A.	-

SUBMERSIBLE PUMP OPTIONS	
VERTICAL 6-8 LAYOUTS	DOUBLE STACKED 9-12 LAYOUTS
4HP PUMP FOR UNLEADED 1	4HP PUMP FOR UNLEADED 1
4HP PUMP FOR UNLEADED 2	4HP PUMP FOR UNLEADED 2
4HP PUMP FOR PREMIUM (IF <500' OF PIPING)	4HP PUMP FOR PREMIUM (IF <500' OF PIPING)
4HP PUMP FOR DIESEL (IF <500' OF PIPING)	4HP PUMP FOR DIESEL (IF <500' OF PIPING)
4HP PUMP FOR EO/FLEX FUEL (IF <500' OF PIPING)	4HP PUMP FOR EO/FLEX FUEL (IF <500' OF PIPING)
VERTICAL 9-12 LAYOUT	DOUBLE STACKED 14 LAYOUTS
4HP PUMP FOR UNLEADED 1	(2)4HP PUMP IN TANDEM FOR UNLEADED 1
4HP PUMP FOR UNLEADED 2	(2)4HP PUMP IN TANDEM FOR UNLEADED 2
4HP PUMP FOR PREMIUM (IF <500' OF PIPING)	4HP PUMP FOR PREMIUM (IF <500' OF PIPING)
4HP PUMP FOR DIESEL (IF <500' OF PIPING)	4HP PUMP FOR DIESEL (IF <500' OF PIPING)
4HP PUMP FOR EO/FLEX FUEL (IF <500' OF PIPING)	4HP PUMP FOR EO/FLEX FUEL (IF <500' OF PIPING)
DOUBLE STACKED 6-8 LAYOUTS	
4HP PUMP FOR UNLEADED 1	
4HP PUMP FOR UNLEADED 2	
4HP PUMP FOR PREMIUM (IF <500' OF PIPING)	
4HP PUMP FOR DIESEL (IF <500' OF PIPING)	
4HP PUMP FOR EO/FLEX FUEL (IF <500' OF PIPING)	

ELECTRICAL EQUIPMENT					
TAG	EQUIPMENT DESCRIPTION	PROVIDED	MFG MODEL #	LOCATION	QUANTITY
201	NUMBER CURRENTLY NOT USED	-	-	-	-
202	NUMBER CURRENTLY NOT USED	-	-	-	-
203	NUMBER CURRENTLY NOT USED	-	-	-	-
204	NUMBER CURRENTLY NOT USED	-	-	-	-
205	F.E. PETRO 2/4HP VFC PUMP CONTROL BOX	OWNER	MODEL FE-MAG-VFC	S.B.	5
206	NUMBER CURRENTLY NOT USED	-	-	-	-
207	ISLAND EMERGENCY SHUTDOWN SWITCH - PILLA ELECTRICAL PRODUCTS INC. - SURFACE MOUNT NEMA	CONTRACTOR	FS120M0 GRYCLM	D.A.	-
208	E-STOP BUTTON (INSTALLED AT RETAIL CASHIER)	CONTRACTOR	20C794	S.B.	-
209	NUMBER CURRENTLY NOT USED	-	-	-	-
210	WEATHER-PROOF JUNCTION BOX (INTRINSICALLY SAFE WIRING COMPONENTS)	CONTRACTOR	-	D.A./D.S./U.S./T.S.	-
211	EXPLOSION PROOF JUNCTION BOX	CONTRACTOR	-	-	-
212	SEAL FITTING (SIZE TO SUIT)	CONTRACTOR	-	-	-
213	UNION (SIZE TO SUIT)	CONTRACTOR	-	-	-
214	VEEDER-ROOT: T15 450 CONSOLE W/PRINTER INCLUDES: USB/ETHERNET DUAL MODULE RS-232 DUAL INTERFACE MODULE UNIVERSAL SENSOR/PROBE MODULE UNIVERSAL INPUT/OUTPUT MODULE RISK MGMT LEAK DETECT - PLD INTELLIGENT PUMP CONTROL SOFTWARE	OWNER	VEEDER-ROOT: VR-860040-301 VR-332913-001 VR-332868-001 VR-332812-001 VR-332813-001 VR-332912-008 VR-332912-028	S.B.	1
215	VEEDER-ROOT MAGNETOSTRICTIVE TANK PROBE (8')	OWNER	VR-846396-107	T.T.E.	-
216	VEEDER-ROOT MAGNETOSTRICTIVE TANK PROBE (10')	OWNER	VR-846396-109	T.T.E.	5
217	VEEDER-ROOT DUAL-POINT SINGLE FLOAT HYDROSTATIC SENSOR	OWNER	VR-744380-303	T.T.E.	5
218	VEEDER-ROOT SUMP SENSOR (4/12' CABLE)	OWNER	VR-744380-208	D.S./U.S./T.S.	15
	VEEDER-ROOT SUMP SENSOR (4/30' CABLE)	-	VR-744380-209	-	-
219	VEEDER-ROOT 4 INCH DIESEL FLOAT KIT W/10' CABLE	OWNER	VR-846400-011	T.T.E.	1
	VEEDER-ROOT PHASE SEP GAS FLOAT KIT W/10' CABLE	-	VR-886100-010	-	4
220	4" ATG CAP & ADAPTER	OWNER	305 XPA-1100AK EVR	T.T.E.	5
221	VEEDER-ROOT ELECTRONIC LINE LEAK DETECTOR	OWNER	VR-859080-001	U.S.	5
222	GILBARCO UNIVERSAL DISTRIBUTION BOX	OWNER	-	S.B.	1
223	3M INTERCOM 20 STATION COMM CONTROLLER MODEL 3M 4 STATION I/O CARD 3M COMBO STATION SELECTOR 3M CEILING SPEAKER, CEILING T-BAR SUPPORT, ANS AMPLIFIER (10 WATT),	OWNER	ES-941-0064 ES-941-0063 ES-941-0061 78-6911-1530-3 78-6911-1503-TB B6-220	S.B.	1 3 3 1
224	2" INTERSTITIAL SENSOR CAP & ADAPTOR	OWNER	VR-312020-928	T.T.E.	-
225	NUMBER CURRENTLY NOT USED	-	-	-	-
227	PIPE TRACING TAPE - HANSON CO	OWNER	16632	-	1000 FT
230	ALTERNATIVE FLUIDS MAG PLUS PROBE - 10' TANK	OWNER	VR-846397-409	-	-
231	VEEDER-ROOT E85 FLOAT KIT-10' CABLE	OWNER	VR-846400-014	-	-
232	WINNY CITY - 18 AWG 2-CONDUCTOR SHIELDED CABLE	OWNER	FEP-18-02-0A5	-	10
233	CINCINNATI FAN (CANOPY) 3/4 HP SINGLE PHASE, 60HZ, 115/208-230V 200CFM. 3450 RPM WITH WEATHER COVER, VIBRATION ISOLATOR MOUNT AND SLIDE GATE DAMPENER. INTAKE SCREEN	OWNER	PB-10A E820006 SIDE DRAFT	-	1
234	CINCINNATI FAN (GROUND) 3/4 HP SINGLE PHASE, 60HZ, 115/208-230V 200CFM. 3450 RPM WITH WEATHER COVER, VIBRATION ISOLATOR MOUNT AND SLIDE GATE DAMPENER. INTAKE SCREEN	OWNER	PB-10A E820005 DOWN DRAFT	-	-
235	FERNCO 4" BOOT FOR CANOPY FAN	OWNER	1051-44	-	1
236	GALVANIZED SCREEN FAN ENCLOSURE	OWNER	E822810	-	1
237	GROUND MOUNTED FAN CAGE	OWNER	E811542	-	-
238	MULTIPORT SENSOR HOLDER	OWNER	AH-650450	-	-
239	VEEDER-ROOT MAGNETOSTRICTIVE TANK PROBE (11')	OWNER	VR-846396-111	T.T.E.	-
240	VEEDER-ROOT MAGNETOSTRICTIVE TANK PROBE (12')	OWNER	VR-846396-112	T.T.E.	-
241	KIT,ENG SIDE CONDUIT ENTRY HARDWARE	OWNER	MOT838K001	D.S./D.A.	48


NOTE: ALL EQUIPMENT INSTALLED BY CONTRACTOR UNLESS SPECIFIED OTHERWISE BY MANUFACTURER OR FIELD CONSTRUCTION MANAGER.

NOTE: THIS MATERIALS EQUIPMENT SCHEDULE IS NOT A COMPLETE LIST OF MATERIALS. CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND INSTALLING ALL MISCELLANEOUS EQUIPMENT, FITTINGS, MATERIALS AND DEVICES NECESSARY TO PROVIDE A COMPLETE AND OPERABLE SYSTEM. CONTRACTOR TO COORDINATE MATERIALS DELIVERY SCHEDULE AND VERIFY EQUIPMENT COUNTS. CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT ALL EQUIPMENT ARRIVES AT SITE IN UNDAMAGED CONDITION. CONTRACTOR AND/OR SUBCONTRACTOR RESPONSIBLE TO CONFIRM ACTUAL QUANTITIES OF MATERIALS/EQUIPMENT NECESSARY FOR COMPLETE AND OPERABLE SYSTEM.


QUIKTRIP SUPPLIED / INSTALLED SUMMARY

AREA AND ITEM DESCRIPTION	SUPPLIED BY OWNER / VENDOR	RECEIVED BY OWNER / VENDOR	INSTALLED BY OWNER / VENDOR	SUPPLIED BY CONTRACTOR	RECEIVED BY CONTRACTOR	INSTALLED BY CONTRACTOR	FINAL CONNECTIONS & TESTING BY CONTRACTOR
T UNDERGROUND TANKS							
1 GASOLINE TANKS	●				●	●	●
2 TANK ANCHORING EQUIPMENT	●				●	●	●
3 TANK TOP EQUIPMENT	●				●	●	●
4 SUBMERSIBLE PUMPS	●				●	●	●
G GAS CANOPY							
1 GAS CANOPY (NO LIGHTS)	●	●	●				
2 CANOPY SIGNAGE	●	●	●				
3 CANOPY ANCHOR BOLTS	●				●	●	●
4 DISPENSERS	●				●	●	●
5 DISPENSER NUMBERS, SIGNAGE & DECALS	●				●	●	●
6 PAPER TOWEL HOLDERS	●				●	●	●
7 FIRE EXTINGUISHERS & CABINETS				●	●	●	●
8 TRASH CANS	●				●	●	●
9 BUG BUCKETS/SQUEEGEES	●				●	●	●
10 COMMUNICATION	●	●	●				
11 E-STOPS				●	●	●	●
12 FITTINGS AND PIPING	●				●	●	●
13 HOSES AND NOZZLES	●				●	●	●
14 CANOPY DRAINS AND DRAIN LINES				●	●	●	●
15 CANOPY LIGHTS	●				●	●	●
16 CAMERAS	●	●				●	●
17 INTERCOM SYSTEM	●				●	●	●
18 WIRING (POWER, DATA, & INTERCOM)				●	●	●	●
19 VEEDER ROOT SYSTEM	●				●	●	●
20 VEEDER ROOT WIRING (BELDEN 8760)	●				●	●	●
21 FUEL EQUIPMENT, DATA BOXES, GSM, PAM, ETC.	●				●	●	●
22 FUEL PRE- MANUFACTURED PANELS, TRANSFORMERS, UPS UNITS, & ISOLATION BOXES	●				●	●	●
23 CERAMIC TILE (CONTINENTAL SLATE C553 "ASIAN BLACK" 6X6, LATICRETE PERMACOLOR "BLACK" 22 GROUT)	●				●	●	●

A1 BILL OF MATERIALS



QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



REV	DATE	DESCRIPTION
02	09/21/22	TANK UPDATE

SHEET TITLE:
BILL OF MATERIALS

SHEET NUMBER:
XF600

Attachment I: Initial and Continuing Training

The automatic tank gauging and release detection system at this facility will be continuously monitored by an offsite certified monitoring firm, Warren Rogers. Qualified, trained technicians monitoring the system will generate and distribute work orders for alarms and/or fuel variances that trained QuikTrip Facility Support technicians will investigate. Monitoring, work order generation/distribution, and investigations are conducted 24 hours per day, 7 days per week, 365 days per year.

QuikTrip store employees typically do not respond to UST system alarms, and when they do it is under the guidance of one of the technicians from Warren Rogers or QuikTrip Facility Support. Store employees are usually the first responders to surface spills that may occur at the facility. QuikTrip store employees receive training on emergency response procedures, spill response procedures, and familiarization with UST monitoring system upon initial hire.

A copy of the VeederRoot alarm system troubleshooting guide that is kept at each site for reference has been included as part of this Plan.

QuikTrip UST System, Leak Prevention, and Emergency Response

Introduction: QuikTrip has a state-of-the-art UST system that includes several leak prevention systems and procedures. We also have in place a sophisticated network which notifies us real time should a leak occur within our piping system. We also track our fuel inventory daily to determine if we are possibly losing fuel from our system. The following information provides a brief overview of QuikTrip's UST standards for leak prevention, monitoring, detection, and emergency response.

(1) UST System Design: QuikTrip utilizes a unique UST system design that has been developed and refined over the past twenty years to maximize leak prevention and detection. The current design is a result of lessons learned from previous designs, input from in-house engineers and scientists, and input from third-party experts. Some components of the fuel system are below:

(A) Doublewall Steel Tanks with Brine filled Interstice and Sensors

(B) Doublewall XP Pipe (3" and 4")

(C) Fiberglass Sumps with Sensors (i.e. Tank, Dispenser)

(D) Transition Sumps: This unique design ensures all subsurface fuel piping connections are contained in a sump.

(E) Doublewall Spill Buckets with Sensors

(F) Variable Speed FE Petro Submersible Turbine Pumps: These pumps allow the gas system to operate at the lowest possible pressure thus minimizing the potential for leaks. The alternative is to utilize fixed speed pumps which operate at maximum pressure at all times when fuel is being dispensed.

(2) UST System Monitoring: QuikTrip monitors all stores using technology developed both externally and internally by systems experts. The monitoring includes real-time remote system monitoring, daily inventory management, periodic site inspections, and annual third-party operability testing.

(A) Veeder Root TLS-450: This unit monitors the fuel system for pressure drops which indicates a possible leak in the system. Sump and interstitial sensors are also connected to the TLS-450. All of these units are programmed automatically to shut down the fuel system if a leak is indicated. These units are monitored remotely by a 24/7 Help Desk.

(B) In-House Remote System Monitoring: QuikTrip has developed a computer program that monitors all TLS-450's. A message is sent to the 24/7 Help Desk, the Environmental Department, and QuikTrip's Maintenance Department in the

event of an alarm. The Help Desk enters a work order in the tracking system and a trained employee is dispatched to the site to investigate the alarm.

(C) Daily Inventory Variance Monitoring: QuikTrip has developed a program to monitor daily inventory records for each tank in the company. If certain criteria are triggered, an email alarm is sent to the Help Desk, Environmental Department, and the Maintenance Department. The Help Desk investigates the inventory variance. If the variance is unable to be reconciled, the Environmental Department will investigate the issue and ensure that a leak has not occurred.

(D) Semi-Annual Site Checks: A QuikTrip Environmental Technician performs a thorough site check of the UST system every six months. Any system issues are identified, tracked, and repaired.

(E) Annual Leak Detection System Testing: QuikTrip has a third-party contractor inspect and test the line leak detectors at each store on an annual basis.

(3) Regulatory Compliance: Federal and state regulations require at least one recognized method of release detection to be utilized when operating a fuel system. QuikTrip's redundant methods of release detection are presented below:

(A) Continuous in Tank Leak Detection System (CITLDS): QuikTrip utilizes a third-party certified consultant, Warren Rogers Associates (WRA), to monitor all fuel systems for leaks in "real time". With the completion of every fueling transaction, a simultaneous observation of elapsed sales and associated tank system product volumes and temperatures are recorded. WRA identifies operational problems as they occur.

(B) Automatic Tank Gauge (ATG)/Line Leak Detection: All stores have a Veeder Root TLS-450 Leak Detection System that is capable of detecting a leak as small as 0.1 GPH.

(C) Interstitial Monitoring: The fuel systems at QuikTrip stores are installed with sensors capable of detecting a leak in any portion of our system.

(4) Emergency Response: QuikTrip maintains a 24/7 emergency response system. Store Operations and store personnel are trained in the identification of and the response to spills and leaks. Store employees will notify the 24/7 Help Desk, as well as take appropriate measures on-site to prevent the migration of any spilled fuel. The Help Desk notifies the Environmental Department and/or the Environmental Consultant to respond to the site. The Environmental Consultant will clean-up the spill or contact the Emergency Response Contractor to assist in the clean-up. The Environmental Consultant will also conduct any necessary follow-up at the site.

Veeder-Root TLS-350/450 Alarm Troubleshooting Guidelines

PLLD Gross Test (3.0 GPH) Fail Alarm – Priority 0 **PLLD Shutdown Alarm – Priority 0**

Alarm occurs when a drop in Pump-Off line pressure or low Pump-Off line pressure is detected (Gross Test starts after dispensing stops).

Probable Causes:

1. Large line leak.
2. Tank is empty.
3. Power to submersible (STP) is off.
4. Partially clogged functional element (Red Jacket).*
5. STP contactor relay is not closing or sticking.*
6. Faulty check valve.*
7. Line length or type programmed incorrectly.
8. Packer-Discharge Seal is leaking (Red Jacket).
9. Dispenser leak (External - filter, connections; Internal – solenoid valve leaking into nozzle, blender valve leaking).*
10. Air in the line.
11. Low or no STP pressure (bad STP or starting capacitor).
12. Incorrect wiring of pump control or transducer.*
13. No STP request signal from dispenser.*

* The most common intermittent failures.

Troubleshooting Guidelines:

- A. Perform a quick site check – inspect visible areas of piping, dispensers, and STP for visible signs of leak.
- B. Retest the failed line to determine if the failure is repeatable or intermittent.
- C. If line fails again, close the product sheer-valve to each affected dispenser and retest line. If the test passes, the leak is probably in a dispenser(s).

PLLD Low Pressure Alarm – Priority 0

Indicates a Low Pressure condition (10 psi or less) was detected while dispensing.

Probable Causes:

1. Large line leak.
2. Tank is empty.
3. Low or no STP pressure (bad STP or starting capacitor).
4. STP contactor relay is not closing or sticking.
5. Power to submersible (STP) is off.

Troubleshooting Guidelines:

- A. Perform a quick site check – inspect visible areas of piping, dispensers, and STP for signs of leakage.
- B. Check tank for fuel.
- C. Check for bad starting capacitor or bad STP.
- D. Clean contactor relay contacts or replace.
- E. Check STP breaker, wiring, etc.

PLLD Sensor Open Alarm – Priority 0

Alarm indicating that a pressure transducer is not connected properly.

Probable Causes:

1. Open condition in the field wiring.
2. Incorrect field wiring.
3. Reversed wiring on the pressure transducer.
4. Bad transducer.
5. Bad PLLD Interface Module.

Troubleshooting Guidelines:

- A. Check wiring continuity.
- B. Check wiring polarity.
- C. Check wiring is connected to PLLD Interface Module (diagnostics displaying 0 pressure).

PLLD High Pressure Alarm – Priority 2

Alarm indicating excessive line pressure when STP is off.

Probable Causes:

-

1. Sticking/ Stuck contactor relay.
2. Clogged functional element (Red Jacket STP)
3. Faulty pressure transducer.
4. Incorrect or incorrectly adjusted check valve relief (FE Petro STP).
5. Faulty check valve.
6. Functional element relief valve has not been disabled (Red Jacket STP).
7. Vent closing screw on functional element not fully retracted.
8. STP is being switched on by another device not detected by the console.
9. Cross-wired transducers.

Troubleshooting Guidelines:

- A. Switch on STP for 10 seconds to pressurize the line. Turn STP off, wait 5 seconds, then measure the line side pressure. Normally, pressure should be less than 27 psi.
 - B. If greater than 27 psi, troubleshoot for causes 1, 2, 3, 4, 6, 7, and 9.
 - C. If less than 27 psi, problem is likely intermittent. Troubleshoot for causes 1, 5, 8, and 9.
-

PLLD Periodic Test (.20 GPH) Fail Alarm – Priority 2
PLLD Annual Test (.10 GPH) Fail Alarm – Priority 4

Pump-On pressures indicate a Periodic or Annual line leak test has failed.

Probable Causes:

1. The line is leaking.
2. A Check valve is leaking.
3. The Packer-Discharge seal needs replaced (Red Jacket).
4. Dispenser leak (external - filter, connections; internal – solenoid valve leaking into nozzle, blender valve leaking).
5. The console is not programmed for the correct line length or line type.

Troubleshooting Guidelines:

- A. Switch STP on and inspect all visible areas of pipeline, dispenser piping, and STP for leakage.
- B. Check dispenser solenoid valves for leakage by squeezing each nozzle with STP switched ON and dispenser switched OFF.

- C. Check for blend valve leakage by looking for meter movement while STP is on but not dispensing.
- D. Retest the line to confirm failure – if it passes without any repairs, problem is intermittent. Troubleshoot causes 2 and 4.
- E. If retest fails, close dispenser emergency shuts-off valves (sheer valves) and retest again. If test fails, troubleshoot causes 1, 2, and 3.
- F. If retest passes, problem is in one of the dispensers. Open shut-off valves one at a time or in groups and retest until dispenser is identified.

* Note: .20 GPH test takes a minimum of 30 minutes. .10 GPH test takes a minimum of 45 minutes.

PLLD Sensor Short Alarm – Priority 2

Alarm indicating that Pump-On and Pump-Off pressures are the same and are within a range of 5-15 psi.

Probable Causes:

- 1. STP did not switch on.
- 2. Low STP pump pressure.
- 3. Bad transducer.
- 4. Bad PLLD Interface Module.

Troubleshooting Guidelines:

- A. Check STP breaker, wiring, etc.
- B. Check/ replace transducer.

PLLD Continuous Handle On Alarm – Priority 2

Alarm indicating a continuous Pump-On (handle raised) signal for 16 hours.

Probable Causes:

- 1. Dispenser handle switch is faulty.
- 2. Excessive dispenser leakage (handle feedback) voltage.
- 3. Dispenser internal board faulty.

Troubleshooting Guidelines:

- A. Check dispenser handle switch integrity.
- B. Check handle switch wiring is intact.
- C. Check dispenser line-in voltage. Greater than 30VAC is excessive. Isolation relay between dispenser and PLLD Controller Module is needed or defective.

PLLD Line Equipment Alarm – Priority 2

Alarm indicating a fault with the pressure measurement system.

Probable Causes:

- 1. Faulty Pressure Transducer.
- 2. Faulty PLLD Interface Module.
- 3. Incorrectly wired transducer.

Troubleshooting Guidelines:

- A. For steps B and C, **Turn Off** the power to the STP.
- B. Vent the product line to drop the line pressure to zero psi.
- C. Reconnect the product line.
- D. Restore power to the STP.
- E. In the PLLD Diagnostic Menu, run the pressure measurement offset test.
 - 1.) Press the MODE to display Diagnostic Mode.
 - 2.) Press FUNCTION until "Pressure Line Leak Diag" is displayed.
 - 3.) Press STEP until "PLLD Number X" is displayed (X = line).
 - 4.) Press ENTER and the results of the last test displays.
 - 5.) Press STEP and ENTER to start the test. "Measuring" is displayed.
 - 6.) The Pressure Offset result is displayed when the test is finished "Done – Offset: +XX.X PSI".
- F. If the test result is greater than 5 psi, re-run the test again. If still greater than 5 psi, check the transducer wiring.
- G. If transducer wiring is good and correct, then the transducer is likely bad.
- H. Re-run the pressure measurement offset test following all repairs.
- I. Run a Gross Line test to clear any active alarms.

Sensor Fuel Alarm – Priority 0

Alarm indicating fuel, fuel vapor, or liquid is present in area being monitored.

Troubleshooting Guidelines:

Fuel/ Liquid:

1. Perform site check for visible signs of fuel or liquid in area being monitored.
2. Determine source of fuel or liquid in area (isolated leak, water run off, etc.) and resolve.
3. Check sensor for correct location and proper function.

Vapor:

1. Check Vapor Sensor Setup in console programming for correct threshold value (established during System Setup).
2. Check Vapor Diagnostic for sensor status and PPM (parts per million) conversion.
 - a.) $< 200 = \text{Short}$
 - b.) $200 - \text{threshold value} = \text{Normal}$
 - c.) $> 1.05 \text{ times the threshold value for } +24 \text{ hours} = \text{Fuel}$
 - d.) $> 4 \text{ times the threshold value} = \text{Fuel}$
3. If fuel vapor is smelled at vault exhaust fans, the sensor is likely working correctly and fuel is present in the vault.
4. If no fuel vapor is smelled at exhaust fans, vapor sensor is likely saturated and needs replaced.

Sensor Out Alarm – Priority 2

Alarm indicating a sensor is defective, disconnected, or the sensor setup was performed incorrectly.

Troubleshooting Guidelines:

1. Check and validate correct sensor programming (configuration, location, type, and category).
 2. Check sensor wiring circuit for disconnected or broken wires.
 3. Connect sensor directly to console to verify function.
 4. Verify sensor wiring polarity is correct.
 5. Replace defective sensor.
-

Sensor Short Alarm – Priority 2

Alarm indicating a short circuit has occurred in the sensor or sensor wiring.

Troubleshooting Guidelines:

1. Verify sensor is good/ bad by connecting directly to the interface module.
2. Perform continuity test on sensor wiring.
3. Perform continuity test on sensor wiring to ground (conduit).

Sensor High Liquid Alarm – Priority 2

Indicates an increase in the brine solution level of a double-walled fuel tank.

Probable Causes:

1. A hole on the inside wall of the tank is allowing fuel into the interstitial space (fuel level is higher than brine level).
2. The sensor is malfunctioning.
3. Water is entering the interstitial space from an outside source.

Troubleshooting Guidelines:

1. Check the sensor for proper function and installation.
2. Manually check the level of brine solution.
3. Check the EPA Book history for volume variances (loss) in the tank.

Sensor Low Liquid Alarm – Priority 2

Indicates a decrease in the brine solution level of a double-walled fuel tank.

Probable Causes:

1. A hole on the exterior wall of the tank is allowing brine solution to leak out.
2. A hole on the inside wall of the tank is allowing brine to leak into the tank (tank level is less than brine level).
3. The sensor is malfunctioning.

Troubleshooting Guidelines:

1. Check the sensor for proper function and installation.

2. Manually check level of brine solution.
3. Check tank gauging for high water.
4. Check the EPA Book history for volume variances (gains) in the tank.
5. Add brine or water (when tank is full) and check level regularly.

PLLD / Sensor Setup Data Warning – Priority 4

Alarm indicates an error in programming.

Troubleshooting Guidelines:

1. Double check PLLD and/or Sensor programming is correct.
2. Default line length is 501 feet and must be changed to actual line length. Also ensure line type is also entered correctly.
3. Check for probe out on startup.

PLLD Periodic Test Needed Alarm – Priority 4

Alarm indicating the system has not completed or passed a Periodic (.20 GPH) test.

Probable Causes:

1. Periodic test failures.
2. Pump-On pressure readings are less than 22 psi.
3. The line is not venting when the pump is shut off (should be a 2 psi difference between Pump-On pressure and Pump-Off pressure).
4. The site is too busy for testing to complete.

Troubleshooting Guidelines:

1. Follow procedures for troubleshooting Annual and Periodic Test Fail alarms (page 3).
 2. Check for stuck relays, incorrect or incorrectly adjusted check valves (FE Petro), or functional element not disabled (Red Jacket).
 3. Site or line(s) may need to be shut down in order for test to complete – minimum 30 minutes per line for test to pass/fail.
-

Attachment J: Release Detection Maintenance

The automatic tank gauging and release detection system and cathodically-protected equipment at this facility will be routinely inspected and maintained by qualified, trained QuikTrip Facility Support technicians or certified contractors. Inspections, routine maintenance, and preventative maintenance will be performed according to the manufacturer's specifications and recommended schedules. Copies of these relevant maintenance programs and schedules are included as part of this Plan.

Semi-Annual Site Check Inspection

- *Complete Environmental Site Checklist
- *Be sure to complete all "checks" on the work order
- *Complete any routine repairs as part of this Site Check
- *Do Not open additional Work Orders for these repairs

Additional work orders may only be opened if you are not able to complete the repairs while on site.

Note: Ensure you replace any nozzles with expired dates on them!!!

ATG/Line Leak Detector Check:

- Check ATG for fuel and water levels and verify ATG and stick readings are not off by more than 2".
- Check ATG for correctly programmed tank limits (High Water Warning and Alarm)

Tank Pit Observation Well:

- Check surface lid, well cap condition.
- Indicate the depth to groundwater (in inches or dry)

- Check all observation wells onsite.
- Apply fuel finding paste to the bottom 3" of the fuel sampler to check for presence of fuel. Is fuel present in the well? If so, notify EPM or ECM and FS Supervisor immediately.
- If fuel is present, use a sampler to collect a sample from the well to measure fuel thickness.

Piping Trench Observation Well (DFW ONLY):

- Check surface lid, well cap condition.
- Check all observation wells onsite.
- Apply fuel finding paste to the bottom 3" of the fuel sampler to check for presence of fuel. Is fuel present in the well? If so, notify EPM or ECM and FS Supervisor immediately.
- If fuel is present, use a duel sampler to collect a sample from the well to measure fuel thickness.

ATG Probe Port:

- Cap/grommet water tight?

Spill Buckets (fill and vapor):

- Are there any issues with the spill bucket (holes, cracks, dents, liquid, lid seals, etc.)?
- Are Spill Bucket lids water tight?
- Did you clean the spill bucket?

Condensate Trap:

- Is there liquid in the condensate trap?

Submersible Pump Containment Area (Sump):

- Are there any issues to report with the sumps?
- Are Blueline boots present?
- What is the condition of the Blueline boot?
- Is water present? If so what is the thickness in inches?
- Is fuel present in well? If so, notify EPM immediately.
- Clean Silt ring.

Dispensers:

- Are there any leaks/issues to report?
- Are there any issues to report with the sumps?
- Are Blueline boots present?
- What is the condition of the Blueline boot?
- Is fuel present? If so, notify EPM immediately.
- Are there any nozzles with expired date codes?

Copper Piping Splice Sump:

- Are there any leaks/issues to report?

Fuel Piping:

- Are there any leaks/issues to report?
- What is the type of fuel piping from the submersible to 1st dispenser?
- What is the type of fuel piping under the dispensers?

Sensors:

- Are the submersible pump containment (sump) sensors present, programmed correctly & installed at proper depth?
- Are the dispenser sumps present, programmed correctly & installed at proper depth?
- Are the diesel filter sump sensors present, programmed correctly & installed at proper depth?
- Are the transition sump sensors present, programmed correctly & installed at proper depth?

TC Only - Travel Center Diesel Filter Pods (Sumps):

- Are there any issues to report with the sumps?

- Is water present? If so what is the thickness in inches?
- Is fuel present? If so, notify EPM immediately.

Vault (AZ only):

- Is water present in the vaults?
- Is fuel present in the vaults? If so, contact EPM immediately.
- Product vapor present in vaults?

Remote Fills:

- Are there any issues with the remote fill tank entry and sump (water/fuel present, condition of lid)?
- Are there any issues with the remote fill spill bucket (holes, cracks, dents, liquid, etc.)?

Stick Port and Bucket (former fill):

- Are there any issues with the bucket/lid condition?
- Is any fuel present? If so, contact EPM immediately
- Is water present? If so what is the thickness in inches?

Transition Sump:

- Are there any issues to report with the sumps?
- Are Blueline boots present?
- What is the condition of the Blueline boot?
- Is water present? If so what is the thickness in inches?
- Is fuel present? If so, notify EPM immediately.

AZ Only - Drywell System (Envibro or DW Guardian):

- Check if the inlet grate and the chambers are clear of trash/debris/sediment

DFW Only - 60 Day Spill Bucket Inspection Log

- Complete the 60-day Spill Bucket Inspection Log and return to the Vapor Binder in the store.



ANNUAL SUMP SENSOR TEST FORM

FACILITY NAME: QuikTrip #4160
FACILITY ADDRESS:
TCEQ FACILITY ID #:

A. Results of Annual Leak Monitoring Test - Complete the following checklist using: Y = Yes, N = No, N/A = Not Applicable.

1. Leak monitor (ATG) manufacturer's name and model number Veeder – Root TLS – ___ 350 ___ 450 (Check one) Comments:	
2. ATG console assignments are correctly programmed and labeled for all sensors. Print and attach set up report. Comments:	
3. ALL Tank secondary containment sensor is positioned per manufacturer's requirements Comments:	
4. Brine level of the tank interstitial space is within the manufacturer's operating range. Comments:	
5. Q1 Unleaded Submersible Pump Sump Sensors are positioned per manufacturer's requirements. Comments:	
6. Q2 Unleaded Submersible Pump Sump Sensors are positioned per manufacturer's requirements. Comments:	
7. Q3 Premium Submersible Pump Sump Sensors are positioned per manufacture's requirements. Comments:	
8. Q4 Diesel Submersible Pump Sump Sensors are positioned per manufacture's requirements. Comments:	
9. _____	
10. Dispenser Sump Sensors are positioned per manufacture's requirements. Comments:	
11. Transition Sump Sensors are positioned per manufacture's requirements. Comments:	
12. All secondary containment Sumps are liquid tight and free of debris, water and regulated substance Comments:	
12. All Sensors were visually inspected, manually tested, confirmed operational and reset. Attach printouts that document system shut down or alarmed when tested Comments:	
13. The ATG console Audible and Visual Alarms are confirmed operational and cleared and reset after testing. Comments:	

14. Alarms active and present upon arrival. See attached printout. Comments:	None
15. Additional Comments:	

B. Verification: I hereby verify that the equipment identified in this document was tested for proper operation in performance of the original design function in accordance with the manufacturer's requirements. Attached to this form is information (if available, system set-up reports, alarm history, sensor status) necessary to verify that this information is correct.

TEST COMPANY NAME TEST COMPANY ADDRESS CITY/STATE/ZIP PHONE

TECHNICIAN NAME TECHNICIAN PHONE TECHNICIAN SIGNATURE DATE OF TEST

Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Rachel Roberts

Date: 04/21/2023

Signature of Customer/Agent:



Regulated Entity Name: Kimley-Horn

Regulated Entity Information

1. The type of project is:

- Residential: Number of Lots: _____
- Residential: Number of Living Unit Equivalents: _____
- Commercial
- Industrial
- Other: _____

2. Total site acreage (size of property): 1.89

3. Estimated projected population: N/A

4. The amount and type of impervious cover expected after construction are shown below:

Table 1 - Impervious Cover Table

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	5,312	÷ 43,560 =	0.12
Parking	8,847	÷ 43,560 =	0.20
Other paved surfaces	41,598	÷ 43,560 =	0.95
Total Impervious Cover	55,757	÷ 43,560 =	1.28

Total Impervious Cover 1.28 ÷ Total Acreage 1.89 X 100 = 67.72% Impervious Cover

5. **Attachment A - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
6. Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

7. Type of project:
- TXDOT road project.
 - County road or roads built to county specifications.
 - City thoroughfare or roads to be dedicated to a municipality.
 - Street or road providing access to private driveways.
8. Type of pavement or road surface to be used:
- Concrete
 - Asphaltic concrete pavement
 - Other: _____
9. Length of Right of Way (R.O.W.): _____ feet.
 Width of R.O.W.: _____ feet.
 L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.
10. Length of pavement area: _____ feet.
 Width of pavement area: _____ feet.
 L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.
 Pavement area _____ acres ÷ R.O.W. area _____ acres x 100 = _____% impervious cover.
11. A rest stop will be included in this project.
 A rest stop will not be included in this project.

12. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

13. **Attachment B - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

14. The character and volume of wastewater is shown below:

_____ % Domestic	_____ Gallons/day
_____ % Industrial	_____ Gallons/day
_____ % Commingled	_____ Gallons/day
TOTAL gallons/day _____	

15. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

Attachment C - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

Sewage Collection System (Sewer Lines):

Private service laterals from the wastewater generating facilities will be connected to an existing SCS.

Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.

The SCS was previously submitted on _____.

The SCS was submitted with this application.

The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

The sewage collection system will convey the wastewater to the Liberty Hill (name) Treatment Plant. The treatment facility is:

- Existing.
 Proposed.

16. All private service laterals will be inspected as required in 30 TAC §213.5.

Site Plan Requirements

Items 17 – 28 must be included on the Site Plan.

17. The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 30 '.

18. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): DFIRM PANEL 48491C0275E, Dated 9/26/2008

19. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.

20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)

The wells are not in use and have been properly abandoned.

The wells are not in use and will be properly abandoned.

The wells are in use and comply with 16 TAC §76.

There are no wells or test holes of any kind known to exist on the project site.

21. Geologic or manmade features which are on the site:

All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.

No sensitive geologic or manmade features were identified in the Geologic Assessment.

Attachment D - Exception to the Required Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached.

- 22. The drainage patterns and approximate slopes anticipated after major grading activities.
- 23. Areas of soil disturbance and areas which will not be disturbed.
- 24. Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 25. Locations where soil stabilization practices are expected to occur.
- 26. Surface waters (including wetlands).
 - N/A
- 27. Locations where stormwater discharges to surface water or sensitive features are to occur.
 - There will be no discharges to surface water or sensitive features.
- 28. Legal boundaries of the site are shown.

Administrative Information

- 29. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 30. Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Attachment A – Factors Affecting Surface Water Quality

Factors that could affect the quality of the water discharges for ultimate land use are:

- Oil, grease, and fuel from vehicle drippings;
- Dirt from vehicles;
- Trash and litter;
- Hydrocarbons from asphalt paving operations.

Attachment B- Volume and Character of Stormwater

Stormwater runoff will decrease due to the development of this site. The site will produce a decrease of 3.35 cfs for the 25-year development. The weighted C-value for the site would be 0.88 after development. C-value was obtained from the City of Roundrock Rain and Roundrock Determination of Storm.

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Rachel Roberts

Date: 04/21/2023

Signature of Customer/Agent:



Regulated Entity Name: Kimley-Horn

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: 5 Underground Storage Tanks

These fuels and/or hazardous substances will be stored in:

- Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2. **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

- 5. **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: North Fork San Gabriel River

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

- 7. **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
 - A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
 - A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
 - A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
 - There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- N/A
12. **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A – Spill Report Actions

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of the materials and substances described above to storm water runoff.

Education

- (1) Be aware that different materials pollute in different amounts. Make sure that each employee knows what a “significant spill” is for each material they use, and what is the appropriate response for “significant” and “insignificant” spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
- (2) Educate employees and subcontractors on potential danger to humans and the environment from spills and leaks.
- (3) Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- (4) Establish a continuing education program to indoctrinate new employees.
- (5) Have contractor’s superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

- (1) To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110, 117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- (2) Store hazardous materials and wastes in covered containers and protect from vandalism.
- (3) Place a stockpile of spill cleanup materials where it will be readily accessible.
- (4) Train employees in spill prevention and cleanup.
- (5) Designate responsible individuals to oversee and enforce control measures.
- (6) Spills should be covered and protected from stormwater run-on during rainfall to the extent that it doesn’t compromise cleanup activities.
- (7) Do not bury or wash spills with water.
- (8) Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.

- (9) Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- (10) Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- (11) Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- (12) Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, cover, and liners should be repaired or replaced as needed to maintain proper function.

Cleanup

- (1) Clean up leaks and spills immediately.
- (2) Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- (3) Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- (1) Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- (2) Use absorbent materials on small spills rather than hosing down or burying the spill.
- (3) Absorbent materials should be promptly removed and disposed of properly.
- (4) Follow the practice below for a minor spill:
- (5) Contain the spread of the spill.
- (6) Recover spilled materials.
- (7) Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills – can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities. Spills should be cleaned up immediately:

- (1) Contain spread of the spill.
- (2) Notify the project foreman immediately.
- (3) If the spill occurs on paved or impermeable surfaces, clean up using “dry” methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- (4) If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- (5) If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- (1) Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor’s responsibility to have all emergency phone numbers at the construction site.
- (2) For spills of federal reportable quantities, in conformance with the requirements on 40 CFR parts 110, 119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- (3) Notification should first be made by telephone and followed up with a written report.
- (4) The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- (5) Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- (6) The Reportable Quantities table can be found in the following link https://www.tceq.texas.gov/response/spills/spill_rq.html

Vehicle and Equipment Maintenance

- (1) If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runoff of stormwater and runoff of spills.
- (2) Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- (3) Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite
- (4) Always use secondary containment, such as drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- (5) Place drip pans or absorbent materials under paving equipment when not in use.
- (6) Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
- (7) Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- (8) Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about oil filters.
- (9) Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think the acid had drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

Vehicle and Equipment Fueling

- (1) If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runoff of stormwater and the runoff of spills.
- (2) Discourage "topping off" of fuel tanks.
- (3) Always use secondary containment, such as a drain pan, when fueling to catch spills/leaks.

ATTACHMENT B – Potential Sources of Contamination

Sources of contamination during construction that could potentially affect surface and groundwater quality are as follows:

Potential Source	Preventative Measure
Asphalt Products used on this project	After placement of Asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The Contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain event.
Oil, grease, fuel and Hydraulic fluid drippings	Vehicle maintenance when possible will be performed within the construction staging area.
Miscellaneous trash and litter	Trash containers will be placed throughout the site to encourage proper trash disposal.
Construction Debris	Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addresses on a case-by-case basis

ATTACHMENT C – Sequence of Major Events

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site.

The sequence of major construction activities will be as follows. Approximate acreage to be disturbed is listed in parentheses next to each activity.

1. Install all temporary erosion controls. (1.89 acres)
2. Clear and grub strip topsoil. (1.89 acres)
3. Grading (1.89 acres)
4. Rough Cut Drive Aisles and building pads (1.89 acres)
5. Install wet/dry utilities (1.89 acres)
6. Install paving improvements (1.89 acres)
7. Complete restoration of site vegetation. (No additional area will be disturbed by this activity)
8. Remove and dispose of temporary erosion controls when restoration has been accepted.

Maximum total construction time is not expected to exceed 12 months.

ATTACHMENT D – Temporary Best Management Practices and Measures

Also refer to the TCEQ Site Plan for details of TBMP's.

Silt fencing will be installed prior to the commencement of construction to prohibit runoff of sediment. The silt fence shall be placed perpendicular to direction of flow, where feasible, to maximize efficiency. If there are any, potentially sensitive features, a silt fence will surround the site as specified by TCEQ Guidance Manual Chapter 5.

Bagged gravel inlet filters will be used and maintained in a condition to prevent runoff of sediment from flowing into drains during construction.

Stabilized construction entrance will be installed prior to the commencement of construction and will be used and maintained in a condition that will prevent tracking or flowing of sediment onto public roadway.

a.) Silt fence will not be placed on the upstream side of the site because stormwater drainage to the site from upgradient will be captured in an inlet and bypassed to the existing channel in Kauffman Loop. The inlet will have filter protection during construction activity.

b.) Silt fencing and bagged gravel inlet filters will be used on-site to filter out pollutants and restrict sediment from leaving the site. Silt fencing will be placed in existing and proposed channels and downstream of flow on site. Bagged gravel inlet filters will be placed around proposed inlets to capture any suspended solids.

c.) Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. Silt Fencing, bagged gravel inlet filters and construction entrance measures prevent sediment and pollution by filtering and routing water. These filtered pollutants are then removed and prevented from entering surface streams, sensitive features, or the aquifer.

d.) BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMP's. Silt fencing and bagged gravel inlet filters will be placed to intercept and detain water with sediment or pollution from entering or leaving the site to any unprotected areas. The BMP's will filter out sediment and pollution while allowing filtered water to flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.



ATTACHMENT F – Structural Practices

The structural practices that will be used to divert and store flows, and limit runoff discharge or pollutants will be the use of silt fences, inlet protection, and construction entrance stabilization.

FILE LOCATION: S:\SMA_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-DMM EX.dwg TAB NAME: PRE-DEVELOPED DRAINAGE MAP USER: rscargano SAVED: 1/27/2023 1:04 PM PLOTTED: 4/21/2023 10:28 AM

TIME OF CONCENTRATION CALCULATIONS					
SHEET FLOW		SHALLOW CONCENTRATED FLOW		CHANNEL FLOW	
EX-1					
n=	0.150 paved?	no paved?		v(fps)=	
S (ft/ft)=	0.010	S (ft/ft)=	0.003	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	790	L (ft)=	
T ₁₀ =	11.478	T ₁₀ =	16.219	T ₁₀ =	0.000
Total TC = 27.70 minutes					
SHEET FLOW		SHALLOW CONCENTRATED FLOW		CHANNEL FLOW	
EX-2					
n=	0.150 paved?	no paved?		v(fps)=	
S (ft/ft)=	0.010	S (ft/ft)=	0.021	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	758	L (ft)=	
T ₁₀ =	11.478	T ₁₀ =	5.389	T ₁₀ =	0.000
Total TC = 16.87 minutes					

EXISTING DRAINAGE AREA CALCULATIONS													
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
EX-1	7.21	0%	98	100%	80	80.0	27.70	13.00	19.30	25.50	33.70	40.70	48.30
EX-2	7.24	0%	98	100%	80	80.0	11.48	19.40	28.70	37.70	49.80	60.10	71.10
HEC-HMS VERSION 4.1 AND CITY OF LEANDER ATLAS 14 VALUES WERE USED FOR THIS CALCULATION													
POA - A							20.50	31.50	42.50	57.60	70.70	85.00	



PROJECT NO.: 06304941
 DATE: 04/21/2023
Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10110 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888
 WWW.KIMLEY-HORN.COM
 TX REG. PROFESSIONAL ENGINEER NO. 137894

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS


© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.
 PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
 PRE-DEVELOPED DRAINAGE MAP
 SHEET NUMBER:
C121

ORIGINAL ISSUE DATE:


FILE LOCATION: S:\Swa_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-D\DM PR.dwg TAB NAME: POST-DEVELOPED DRAINAGE MAP USER: Rochelle.Roberts SAVED: 4/20/2023 6:29 PM PLOTTED: 4/21/2023 10:29 AM



PROPOSED DRAINAGE AREA CALCULATIONS													
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
DA-1*	1.34	100%	98	0%	80	98.0	5.00	7.56	9.56	11.40	13.95	16.12	18.47
DA-2	0.38	33%	98	67%	80	85.9	9.10	1.35	1.86	2.35	3.01	3.58	4.18
DA-3	0.76	65%	98	35%	80	91.7	12.34	0.29	0.38	0.46	0.58	0.68	0.78
DA-4*	0.08	100%	98	0%	80	98.0	5.00	0.45	0.57	0.68	0.83	0.96	1.10
OFF-1	6.76	0%	98	100%	80	80.0	31.62	11.41	16.91	22.31	29.53	35.71	42.33
OFF-2	5.46	0%	98	100%	80	80.0	23.06	10.83	16.06	21.11	27.90	33.73	39.95
HEC-HMS VERSION 4.1 AND CITY OF LEANDER ATLAS 14 VALUES WERE USED FOR THIS CALCULATION							POA - A	17.86	28.05	38.52	52.59	64.63	77.51
*THESE DRAINAGE AREAS ARE CAPTURED BY THE UNDERGROUND DETENTION SYSTEM													

TIME OF CONCENTRATION CALCULATIONS					
SHEET FLOW	SHALLOW CONCENTRATED FLOW	SHALLOW CONCENTRATED FLOW	CHANNEL FLOW		
DA-1*					
n=	0.015 paved?		paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	S (ft/ft)=		L (ft)=
L (ft)=	39	L (ft)=			
T ₁₁ =	0.856	T ₁₂ =	0.000	T ₁₃ =	0.000
T ₁₄ =					1.233
Total TC = 5.00 minutes					
DA-2					
n=	0.240 paved?		yes paved?		v(fps)=
S (ft/ft)=	0.045	S (ft/ft)=	0.01	S (ft/ft)=	L (ft)=
L (ft)=	97	L (ft)=	20	L (ft)=	
T ₁₁ =	8.939	T ₁₂ =	0.164	T ₁₃ =	0.000
T ₁₄ =					0.000
Total TC = 9.10 minutes					
DA-3					
n=	0.240 paved?		no paved?		v(fps)=
S (ft/ft)=	0.033	S (ft/ft)=	0	S (ft/ft)=	L (ft)=
L (ft)=	123	L (ft)=	0	L (ft)=	30
T ₁₁ =	12.237	T ₁₂ =	0.000	T ₁₃ =	0.000
T ₁₄ =					0.100
Total TC = 12.34 minutes					
DA-4*					
n=	0.015 paved?		paved?		v(fps)=
S (ft/ft)=	0.032	S (ft/ft)=		S (ft/ft)=	L (ft)=
L (ft)=	77	L (ft)=		L (ft)=	
T ₁₁ =	0.921	T ₁₂ =	0.000	T ₁₃ =	0.000
T ₁₄ =					0.000
Total TC = 5.00 minutes					
OFF-1					
n=	0.240 paved?		no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.003	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	790	L (ft)=	
T ₁₁ =	16.717	T ₁₂ =	14.899	T ₁₃ =	0.000
T ₁₄ =					0.000
Total TC = 31.62 minutes					
OFF-2					
n=	0.240 paved?		no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.021	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	890	L (ft)=	
T ₁₁ =	16.717	T ₁₂ =	6.344	T ₁₃ =	0.000
T ₁₄ =					0.000
Total TC = 23.06 minutes					

Point of Analysis	Storm Event	Existing Runoff (cfs)	Developed Runoff (cfs)	Is Developed \leq Existing?
A	2	20.50	17.86	YES
	10	42.50	38.52	YES
	25	57.60	52.59	YES
	100	85.00	77.51	YES



Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10100 W. BRIDLE TRAIL, SUITE 200
 SAN ANTONIO, TX 78258
 PHONE: 210-544-1888 FAX: 210-544-1889
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
 POST-DEVELOPED DRAINAGE MAP

SHEET NUMBER:
C122



ORIGINAL ISSUE DATE:

ATTACHMENT I – Inspection and Maintenance for BMP’s

PROJECT NAME: QuikTrip 4160
ADDRESS: 7601 W SH 29
CITY, STATE: Leander ETJ, Williamson County, TX

TEMPORARY BMP’S

SILT FENCE

- Inspections: Inspect all fencing weekly, and after any rainfall.
- Sediment Removal: Remove sediment when buildup reaches 6 inches.
- Replace any torn fabric or install a second line of fencing parallel to the torn section.
- Replace or repair any section crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.

When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

BAGGED GRAVEL INLET FILTER

- Inspections: Should be made weekly, and after each rainfall. Repair or replacement should be made promptly as needed by the contractor.
- Sediment Removal: Remove sediment when buildup reaches 3 inches. Removed sediment should be deposited in a suitable area and in such a manner that it will not erode.
- Check placement of device to prevent gaps between device and curb.
- Inspect filter fabric and patch or replace if torn or missing.
- Structures should be removed and the area stabilized only after the remaining drainage area has been properly stabilized

STABILIZED CONSTRUCTION ENTRANCE

- The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public roadways. This may require periodic top dressing with additional stone as conditions demand, as well as repair and clean out of any measure devices used to trap sediment.
- All sediment that is spilled, dropped, washed or tracked onto public roadway must be removed immediately by contractor.

The stabilized construction entrance will be removed once the driveway to the proposed site is complete. Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

Maintenance records shall be kept on the installation, maintenance, or removal of items necessary for the proper operation of the facilities.

All inspections shall be documented.

An amended copy of this document will be provided to the Texas Commission on Environmental Quality within thirty (30) days of any changes in the following information.

This Maintenance Plan is based on TCEQ Maintenance Guidelines.

**EDWARDS AQUIFER CONTRIBUTING ZONE
STORMWATER QUALITY MAINTENANCE PLAN**

INSTALLATION		MAINTENANCE		REMOVAL	
DATE	CONTROL TYPE	DATE	CONTROL TYPE	DATE	CONTROL TYPE

Note: Reference Contributing Zone Application Attachment N Maintenance Plan and Schedule for BMP's

ATTACHMENT J – Schedule of Interim and Permanent Soil Stabilization Practices

Stabilization measures shall be initiated as soon as possible in portions of the site where construction activities have ceased, temporarily or permanently, but in no case more than 14 days after the construction activity in that portion of the site concluded. Where the initiation of stabilization measures by the 14th day after construction activity temporary or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

SOIL STABILIZATION PRACTICES:

- HYDROMULCHING
- TEMPORARY SEEDING
- PERMANENT PLANTING, SODDING, OR SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- BUFFER ZONES
- PRESERVATION OF NATURAL RESOURCES

OTHER: Disturbed areas, in which construction activity has ceased temporarily or permanently, shall be stabilized within 14 days unless activities are scheduled to resume and done within 21 days.

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(li), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Rachel Roberts

Date: 04/21/2023

Signature of Customer/Agent



Regulated Entity Name: Kimley-Horn

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

- Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.
 N/A
- These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____

N/A

3. Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

N/A

4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

The site will be used for low density single-family residential development but has more than 20% impervious cover.

The site will not be used for low density single-family residential development.

5. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

Attachment A - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.

The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.

The site will not be used for multi-family residential developments, schools, or small business sites.

6. **Attachment B - BMPs for Upgradient Stormwater.**

- A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
 - No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
 - Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7. **Attachment C - BMPs for On-site Stormwater.**
- A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
 - Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8. **Attachment D - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
- N/A
9. The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
- The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.
 - Attachment E - Request to Seal Features.** A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10. **Attachment F - Construction Plans.** All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
- Design calculations (TSS removal calculations)
 - TCEQ construction notes
 - All geologic features
 - All proposed structural BMP(s) plans and specifications
- N/A

11. **Attachment G - Inspection, Maintenance, Repair and Retrofit Plan.** A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
- Prepared and certified by the engineer designing the permanent BMPs and measures
 - Signed by the owner or responsible party
 - Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
 - A discussion of record keeping procedures
- N/A
12. **Attachment H - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- N/A
13. **Attachment I - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
- N/A

Responsibility for Maintenance of Permanent BMP(s)

Responsibility for maintenance of best management practices and measures after construction is complete.


14. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- N/A
15. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
- N/A

Attachment B – BMPs for Upgradient Stormwater

Flows generated upgradient are captured in an inlet and conveyed through a storm pipe to the existing earthen channel in Kauffman Loop. Permanent soil stabilization will be incorporated to reduce the volume runoff, improve water quality, prevent erosion, and remove sediment from runoff. The runoff volume for the site has been designed utilizing Atlas 14 rainfall depths. No portion of the site is located in the 100-year or 500-year floodplain according to the Federal Emergency Management Agency's (FEMA) Flood Map, FIRM number 48491C0275E, revised September 26, 2008.

Attachment C – BMPs for On-site Stormwater

A detention pond is required since the site proposes an increase in impervious cover and increased developed flow rates compared to existing drainage conditions. A “jellyfish” water quality structure is proposed onsite to treat stormwater from the site. A proposed series of curb inlets and underground storm sewer system will divert stormwater captured from drainage areas on the site to an existing underground storm system in the R.O.W. The runoff volume for the site has been designed utilizing Atlas 14 rainfall depths. No portion of the site is located in the 100-year or 500-year floodplain according to the Federal Emergency Management Agency’s (FEMA) Flood Map, FIRM number 48491C0275E, revised September 26, 2008.



04/21/2023

Project Name: **QuikTrip No. 4160 - Leander TX**
Date Prepared: **2/16/2023**

1. The Required Load Reduction for the total project:

Calculations from RG-348 Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$
Pages 3-27 to 3-30

$L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Williamson**
Total project area included in plan * = **1.89** acres
Predevelopment impervious area within the limits of the plan * = **0.00** acres
Total post-development impervious area within the limits of the plan* = **1.83** acres
Total post-development impervious cover fraction * = **0.97**
P = **32** inches
 $L_{M \text{ TOTAL PROJECT}}$ = **1593** lbs.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **1**

Total drainage basin/outfall area = **1.32** acres
Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
Post-development impervious area within drainage basin/outfall area = **1.32** acres
Post-development impervious fraction within drainage basin/outfall area = **1.00**
 $L_{M \text{ THIS BASIN}}$ = **1149** lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **JF** abbreviation
Removal efficiency = **86** percent

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7:
 $LR = (\text{BMP efficiency}) \times P \times (A_I \times 34.6 + A_P \times 0.54)$

A_C = Total On-Site drainage area in the BMP catchment area
 A_I = Impervious area proposed in the BMP catchment area
 A_P = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **1.32** acres
 A_I = **1.32** acres
 A_P = **0.00** acres
 L_R = **1257** lbs.

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **1149** lbs.
F = **0.91**

6. Calculate Treated Flow required by the BMP Type for this drainage basin / outfall area.

Offsite area draining to BMP = **0.08** acres
Offsite impervious cover draining to BMP = **0.08** acres

Calculations from RG-348
Pages Section 3.2.22

Rainfall Intensity = **1.15** inches per hour
Effective Area = **1.26** acres
Cartridge Length = **54** inches



Peak Treatment Flow Required = **1.46** cubic feet per second

7. Jellyfish


Designed as Required in RG-348
Section 3.2.22

Flow Through Jellyfish Size

Jellyfish Size for Flow-Based Configuration = **JFPD0806-8-2**
Jellyfish Treatment Flow Rate = **1.60** cfs



PLAN VIEW
(TOP SLAB NOT SHOWN FOR CLARITY)



ELEVATION VIEW

RIM
ELEV. = 987.59'

TOP OF STRUCTURE
ELEV. = 985.82'

WEIR ELEV. = 981.65'

INLET INV. ELEV. = 980.65'

OUTLET INV. ELEV. = 980.15'


STRUCTURE INV.
ELEV. = 973.65'

BOTTOM OF STRUCTURE
ELEV. = 972.98'

JELLYFISH DESIGN NOTES

JELLYFISH TREATMENT CAPACITY IS A FUNCTION OF THE CARTRIDGE LENGTH AND THE NUMBER OF CARTRIDGES. THE STANDARD PEAK DIVERSION STYLE WITH PRECAST TOP SLAB IS SHOWN. ALTERNATE OFFLINE VAULT AND/OR SHALLOW ORIENTATIONS ARE AVAILABLE. PEAK CONVEYANCE CAPACITY TO BE DETERMINED BY ENGINEER OF RECORD

CARTRIDGE LENGTH	54"
OUTLET INVERT TO STRUCTURE INVERT (A)	6'-6"
FLOW RATE HI-FLO / DRAINDOWN (CFS) (PER CART)	0.178 / 0.089
MAX. TREATMENT (CFS)	1.96
DECK TO INSIDE TOP (MIN) (B)	5.00



FRAME AND COVER
(DIAMETER VARIES)
N.T.S.

SITE SPECIFIC DATA REQUIREMENTS	
STRUCTURE ID	WQU
WATER QUALITY FLOW RATE (cfs)	1.60
PEAK FLOW RATE (cfs)	14.56
RETURN PERIOD OF PEAK FLOW (yrs)	25
# OF CARTRIDGES REQUIRED (HF / DD)	7 / 2
CARTRIDGE LENGTH	54"
PIPE DATA:	I.E. MAT'L DIA SLOPE % HGL
INLET #1	980.65' HDPE 24" * *
INLET #2	* * * * *
OUTLET	980.15' HDPE 24" * *
SEE GENERAL NOTES 6-7 FOR INLET AND OUTLET HYDRAULIC AND SIZING REQUIREMENTS.	
RIM ELEVATION	987.59'
ANTI-FLOTATION BALLAST	WIDTH HEIGHT
	* *
NOTES/SPECIAL REQUIREMENTS:	
* PER ENGINEER OF RECORD	

- GENERAL NOTES:**
- CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
 - FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS REPRESENTATIVE. www.ContechES.com
 - JELLYFISH WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
 - STRUCTURE SHALL MEET AASHTO HS-20 OR PER APPROVING JURISDICTION REQUIREMENTS, WHICHEVER IS MORE STRINGENT, ASSUMING EARTH COVER OF 0' - 10', AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306 LOAD RATING AND BE CAST WITH THE CONTECH LOGO.
 - STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-857, ASTM C-918, AND AASHTO LOAD FACTOR DESIGN METHOD.
 - OUTLET PIPE INVERT IS EQUAL TO THE CARTRIDGE DECK ELEVATION.
 - THE OUTLET PIPE DIAMETER FOR NEW INSTALLATIONS IS RECOMMENDED TO BE ONE PIPE SIZE LARGER THAN THE INLET PIPE AT EQUAL OR GREATER SLOPE.
 - NO PRODUCT SUBSTITUTIONS SHALL BE ACCEPTED UNLESS SUBMITTED 10 DAYS PRIOR TO PROJECT BID DATE, OR AS DIRECTED BY THE ENGINEER OF RECORD.

- INSTALLATION NOTES**
- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
 - CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE.
 - CONTRACTOR WILL INSTALL AND LEVEL THE STRUCTURE, SEALING THE JOINTS, LINE ENTRY AND EXIT POINTS (NON-SHRINK GROUT WITH APPROVED WATERSTOP OR FLEXIBLE BOOT).
 - CARTRIDGE INSTALLATION, BY CONTECH, SHALL OCCUR ONLY AFTER SITE HAS BEEN STABILIZED AND THE JELLYFISH UNIT IS CLEAN AND FREE OF DEBRIS. CONTACT CONTECH TO COORDINATE CARTRIDGE INSTALLATION WITH SITE STABILIZATION.



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING: U.S. PATENT NO. 8,287,726; 8,221,618; US 8,123,935; OTHER INTERNATIONAL PATENTS PENDING

CONTECH
ENGINEERED SOLUTIONS LLC
www.ContechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

8' x 6' JELLYFISH - 715972- 010
QUIKTRIP 4160 GEORGETOWN
LEANDER, TX
SITE DESIGNATION: WQU

I:\MERLIN\PROJECT\ACTIVE\715900\715972\715972-10-JELLYFISH\DRAWINGS\PROPOSAL\715972-010-JFPD0806-PRO.DWG 2/16/2023 4:49 PM

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009



Additional information is provided for cells with a red triangle in the upper right corner
Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG
Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will impact the results.

1. The Required Load Reduction for the total project:

Calculations from RG-348

$$\text{Page 3-29 Equation 3.3: } L_M = 27.2(A_N \times P)$$

where:

$L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal result

A_N = Net increase in impervious area

P = Average annual precipitation

Site Data: Determine Required Load Removal Based on the Entire Project

County =	Williamson	
Total project area included in plan *	14.54	acres
Predevelopment impervious area within the limits of the plan *	0.00	acres
Total post-development impervious area within the limits of the plan *	1.94	acres
Total post-development impervious cover fraction *	0.13	
P =	32	inches

$$L_{M \text{ TOTAL PROJECT}} = \mathbf{1689} \text{ lbs.}$$

* The values entered in these fields should be for the total project area.


Number of drainage basins / outfalls areas leaving the plan area = **2**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =	2	
Total drainage basin/outfall area =	0.29	acres
Predevelopment impervious area within drainage basin/outfall area =	0.00	acres
Post-development impervious area within drainage basin/outfall area =	0.29	acres
Post-development impervious fraction within drainage basin/outfall area =	1.00	
$L_{M \text{ THIS BASIN}}$ =	255	lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
Removal efficiency = **85** percent



04/21/2023

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_I \times C$

where:

A_C = Total On-Site drainage area
 A_I = Impervious area proposed in
 A_P = Pervious area remaining in th
 L_R = TSS Load removed from this

A_C = **0.29** acres
 A_I = **0.29** acres
 A_P = **0.00** acres
 L_R = **276** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area


Desired $L_{M \text{ THIS BASIN}}$ = **276** lbs.
 F = **1.00**

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Rainfall Depth = **4.00** inches
Post Development Runoff Coefficient = **0.82**
On-site Water Quality Volume = **3473** cubic feet

Calculations from RG-348

Off-site area draining to BMP = **0.00** acres
Off-site Impervious cover draining to BMP = **0.00** acres
Impervious fraction of off-site area = **0**
Off-site Runoff Coefficient = **0.00**
Off-site Water Quality Volume = **0** cubic feet



Storage for Sediment = 695

Total Capture Volume (required water quality volume(s) x 1.20) = 4167 cubic feet

The following sections are used to calculate the required water quality volume(s) for the selected BMP
The values for BMP Types not selected in cell C45 will show NA.

16. Vegetated Filter Strips

Designed as Required in RG

There are no calculations required for determining the load or size of vegetative filter strips. The 80% removal is provided when the contributing drainage area does not exceed 72 feet (direction of the sheet flow leaving the impervious cover is directed across 15 feet of engineered filter strips with 15 feet across 50 feet of natural vegetation with a maximum slope of 10%. There can be a break in grade as long as the vegetative filter strip is continuous.

If vegetative filter strips are proposed for an interim permanent BMP, they may be sized as described in the RG.

SEE SHEETS C100, C110, & C120 FOR VEGETATED FILTER STRIP LOCATIONS, DIMENSIONS AND GRADING. SEE SHEET C122 FOR PAVEMENT AREA TREATED BY VFS.

**Texas Commission on Environmental Quality
Water Pollution Abatement Plan
General Construction Notes**

Edwards Aquifer Protection Program Construction Notes – Legal Disclaimer

The following/listed “construction notes” are intended to be advisory in nature only and do not constitute an approval or conditional approval by the Executive Director (ED), nor do they constitute a comprehensive listing of rules or conditions to be followed during construction. Further actions may be required to achieve compliance with TCEQ regulations found in Title 30, Texas Administrative Code (TAC), Chapters 213 and 217, as well as local ordinances and regulations providing for the protection of water quality. Additionally, nothing contained in the following/listed “construction notes” restricts the powers of the ED, the commission or any other governmental entity to prevent, correct, or curtail activities that result or may result in pollution of the Edwards Aquifer or hydrologically connected surface waters. The holder of any Edwards Aquifer Protection Plan containing “construction notes” is still responsible for compliance with Title 30, TAC, Chapters 213 or any other applicable TCEQ regulation, as well as all conditions of an Edwards Aquifer Protection Plan through all phases of plan implementation. Failure to comply with any condition of the ED’s approval, whether or not in contradiction of any “construction notes,” is a violation of TCEQ regulations and any violation is subject to administrative rules, orders, and penalties as provided under Title 30, TAC § 213.10 (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. The following/listed “construction notes” in no way represent an approved exception by the ED to any part of Title 30 TAC, Chapters 213 and 217, or any other TCEQ applicable regulation

1. A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any regulated activities. This notice must include:
 - the name of the approved project;
 - the activity start date; and
 - the contact information of the prime contractor.
2. All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
3. If any sensitive feature(s) (caves, solution cavity, sink hole, etc.) is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. Construction activities may not be resumed until the TCEQ has reviewed and approved the appropriate protective measures in order to protect any sensitive feature and the Edwards Aquifer from potentially adverse impacts to water quality.
4. No temporary or permanent hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
5. Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
6. Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features, etc.
7. Sediment must be removed from the sediment traps or sedimentation basins not later than

when it occupies 50% of the basin's design capacity.

8. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
9. All spoils (excavated material) generated from the project site must be stored on-site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the other site.
10. If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.
11. The following records shall be maintained and made available to the TCEQ upon request:
 - the dates when major grading activities occur;
 - the dates when construction activities temporarily or permanently cease on a portion of the site; and
 - the dates when stabilization measures are initiated.
12. The holder of any approved Edward Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
 - A. any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
 - B. any change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
 - C. any development of land previously identified as undeveloped in the original water pollution abatement plan.

Austin Regional Office 12100 Park 35 Circle, Building A Austin, Texas 78753-1808 Phone (512) 339-2929 Fax (512) 339-3795	San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329
--	---

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

GENERAL NOTES:

- IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. ANY CONSTRUCTION OBSERVATION BY THE ENGINEER OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES, IN, ON OR NEAR THE CONSTRUCTION SITE.
- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL NECESSARY PERMITS HAVE BEEN OBTAINED FROM THE GOVERNING AGENCIES AND COORDINATING ALL GOVERNING AGENCY INSPECTIONS REQUIRED THROUGHOUT THE DURATION OF THE PROJECT.
- CONTRACTOR SHALL BE RESPONSIBLE FOR RAZING AND REMOVAL OF THE EXISTING STRUCTURES, RELATED UTILITIES, PAVING, AND ANY OTHER EXISTING IMPROVEMENTS AS NOTED. REFERENCE SITE WORK SPECIFICATIONS.
- CONTRACTOR IS TO REMOVE AND DISPOSE OF ALL DEBRIS, RUBBISH AND OTHER MATERIALS RESULTING FROM PREVIOUS AND CURRENT DEMOLITION OPERATIONS. DISPOSAL WILL BE IN ACCORDANCE WITH ALL LOCAL, STATE AND/OR FEDERAL REGULATIONS GOVERNING SUCH OPERATIONS.
- THE CONTRACTOR WILL BE HELD SOLELY RESPONSIBLE FOR DAMAGE TO ADJACENT PROPERTIES AND NEW CONSTRUCTION IN PLACE DURING THE CONSTRUCTION PHASES OF THIS PROJECT. ANY DISTURBED IMPROVEMENTS SHALL BE REPLACED IN KIND AT THE CONTRACTORS EXPENSE.
- ANY QUANTITIES PROVIDED ON THESE PLANS ARE FOR GENERAL REFERENCE PURPOSES ONLY. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE QUANTITIES REQUIRED FOR CONSTRUCTION.
- THE EXISTING FEATURES SHOWN ON THESE PLANS ARE THOSE NOTED IN THE FIELD AND THOSE TAKEN FROM RECORD DRAWINGS. THERE IS NO GUARANTEE THAT ALL FEATURES (ABOVE OR BELOW GROUND) ARE SHOWN ON THE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL EXISTING FEATURES PRIOR TO BIDDING THE PROJECT.
- THE CONTRACTOR SHALL LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION BY CONTACTING THE LOCAL UTILITY COMPANIES AND/OR UTILIZING THE LOCAL ONE-CALL SYSTEM. ANY DAMAGE DONE TO EXISTING UTILITIES (THAT ARE TO REMAIN IN PLACE) DURING CONSTRUCTION OPERATIONS WILL BE THE CONTRACTOR'S RESPONSIBILITY AND REPAIRED AT THE CONTRACTOR'S EXPENSE.
- ALL SITE WORK FOR THIS PROJECT SHALL MEET OR EXCEED THE OWNERS CONTRACT DOCUMENTS AND SPECIFICATIONS. ALL WORK SHALL MEET OR EXCEED THE RELEVANT UTILITY COMPANIES AND REGULATORY AGENCIES, CONTRACT DOCUMENTS AND SPECIFICATIONS. ALL WORK WITHIN PUBLIC AND STATE RIGHT OF WAY SHALL BE IN ACCORDANCE WITH THE GOVERNING AGENCIES STANDARDS AND SPECIFICATIONS.
- TRAFFIC CONTROL SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), CURRENT EDITION. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE PROPER TRAFFIC CONTROL IS IN PLACE FOR EACH PHASE OF CONSTRUCTION. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROPERLY MAINTAINING TRAFFIC CONTROL DEVICES THROUGHOUT THE DURATION OF THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING TRAFFIC CONTROL PLANS TO THE CITY AND DEPARTMENT OF TRANSPORTATION AS REQUIRED.
- THE STORMWATER TREATMENT SYSTEM (CONTECH JELLYFISH) IS TO BE PRIVATELY MAINTAINED.
- THE WILLIAMSON COUNTY CERTIFICATE OF COMPLIANCE PERMIT NUMBER IS _____.
- THE CONTRACTOR SHALL OBTAIN A "NOTICE OF PROPOSED INSTALLATION OF UTILITY LINE" PERMIT FROM WILLIAMSON COUNTY FOR ANY WORK PERFORMED IN THE EXISTING COUNTY RIGHT-OF-WAY (DRIVEWAY APRON, WATER MAIN TIE-IN, ETC.) THIS PERMIT APPLICATION WILL REQUIRE A LIABILITY AGREEMENT, A CONSTRUCTION COST ESTIMATE FOR WORK WITHIN THE RIGHT-OF-WAY INCLUDING PAVEMENT REPAIR (IF NEEDED), A PERFORMANCE BOND, CONSTRUCTION PLANS AND, IF NECESSARY, A TRAFFIC CONTROL PLAN. AN INSPECTION FEE, AND A PRE-CONSTRUCTION MEETING MAY ALSO BE REQUIRED, DEPENDING ON THE SCOPE OF WORK. THE PERMIT WILL BE REVIEWED AND APPROVED BY THE COUNTY ENGINEER, AND MUST BE APPROVED BY THE WILLIAMSON COUNTY COMMISSIONERS COURT IF ANY ROAD CLOSURE IS INVOLVED.
- DRAINAGE FOR THIS DEVELOPMENT HAS BEEN DESIGNED SUCH THAT THERE WILL BE NO ADVERSE IMPACTS ON THE CAPACITY, FUNCTION OR INTEGRITY OF TEXAS DEPARTMENT OF TRANSPORTATION RIGHT OF WAY DRAINAGE FACILITIES.

WETLANDS NOTICE:

ANY DEVELOPMENT, EXCAVATION, CONSTRUCTION, OR FILLING IN A U.S. CORPS OF ENGINEERS DESIGNATED WETLAND IS SUBJECT TO LOCAL, STATE AND FEDERAL APPROVALS. THE CONTRACTOR SHALL COMPLY WITH ALL PERMIT REQUIREMENTS AND/OR RESTRICTIONS AND ANY VIOLATION WILL BE SUBJECT TO FEDERAL PENALTY. THE CONTRACTOR SHALL HOLD THE OWNER/ DEVELOPER, THE ENGINEER AND THE LOCAL GOVERNING AGENCIES HARMLESS AGAINST SUCH VIOLATION.

WARRANTY/DISCLAIMER:

THE DESIGNS REPRESENTED IN THESE PLANS ARE IN ACCORDANCE WITH ESTABLISHED PRACTICES OF CIVIL ENGINEERING FOR THE DESIGN FUNCTIONS AND USES INTENDED BY THE OWNER AT THIS TIME. HOWEVER, NEITHER THE ENGINEER NOR ITS PERSONNEL CAN OR DO WARRANT THESE DESIGNS OR PLANS AS CONSTRUCTED EXCEPT IN THE SPECIFIC CASES WHERE THE ENGINEER INSPECTS AND CONTROLS THE PHYSICAL CONSTRUCTION ON A CONTEMPORARY BASIS AT THE SITE.

NOTICE TO BIDDERS:

ALL QUESTIONS REGARDING THE PREPARATION OF THE GENERAL CONTRACTOR'S BID SHALL BE DIRECTED TO THE OWNER'S CONSTRUCTION REPRESENTATIVE. SUBCONTRACTORS MUST DIRECT THEIR QUESTIONS THROUGH THE GENERAL CONTRACTOR. THE CONSULTING ARCHITECT AND/OR THE CONSULTING ENGINEER SHALL NOT BE CONTACTED DIRECTLY WITHOUT PRIOR AUTHORIZATION FROM THE OWNER/DEVELOPER.



FLOOD CERTIFICATION:

THIS PROPERTY DOES NOT LOCATE WITHIN ANY PRESENTLY ESTABLISHED 100-YEAR FLOOD PLAIN, AS SHOWN BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, FLOOD INSURANCE RATE MAP FOR THE WILLIAMSON COUNTY OF LEANDER, TEXAS, COMMUNITY PANEL NUMBER 48491C0275E EFFECTIVE DATE SEPTEMBER 26, 2008.

BENCHMARKS:

- BM-100 SCRIBED "X" ON TOP OF CONCRETE, BEARS N 62°23'07" W 3.26' FROM THE WESTERN MOST NORTHWEST CORNER OF THE SUBJECT TRACT. ELEVATION=983.80'
- BM-101 COTTON SPINDLE SET IN POWER POLE, BEARS N 70°40'03" E, 299.23' FROM THE NORTHEAST CORNER OF THE SUBJECT TRACT. ELEVATION=986.48' NOT GRAPHICALLY SHOWN HERON

SITE DEVELOPMENT PLANS FOR QUIKTRIP STORE #4160 7601 W SH 29 GEORGETOWN, TX 78628 LEANDER ETJ, WILLIAMSON COUNTY, TEXAS



EMERGENCY SERVICES DISTRICT	DATE
REVIEWED FOR COMPLIANCE WITH COUNTY REQUIREMENTS	
WILLIAMSON COUNTY	DATE
WILLIAMSON COUNTY DRIVEWAY PERMIT NO. _____	DATE
TXDOT DRIVEWAY PERMIT NO. _____	DATE

MUNICIPAL CONTACT LIST:


WATER UTILITY CITY OF LEANDER 105 N BRUSHY ST LEANDER, TEXAS, 78641 TEL:(512) 259-1142	TRANSPORTATION DEPARTMENT WILLIAMSON COUNTY 3151 S.E. INNER LOOP, SUITE B GEORGETOWN, TEXAS, 78626 TEL:(512) 943-3330	WASTE WATER PROVIDER: CITY OF LIBERTY HILL 100 FORREST ST PO BOX 1920 LIBERTY HILL, TEXAS 78642 TEL:(512) 548-5519
WILLIAMSON COUNTY ESD NO.4 LIBERTY HILL FIRE DEPARTMENT 301 LOOP 332 LIBERTY HILL, TEXAS, 78642 TEL:(512) 515-5165	GAS COMPANY ATMOS ENERGY 3110 N IH 35 ROUND ROCK, TEXAS, 78681 TEL:(512) 310-3850 CONTACT: MARTIN PEREZ	TELEPHONE COMPANY AT&T 1395 US HWY 183, SUITE 110 LEANDER, TEXAS, 78641 TEL:(281) 549-2135
ELECTRIC COMPANY PEDERNALES ELECTRIC COOPERATIVE INC 1949 W WHITESTONE BLVD CEDAR PARK, TEXAS, 78613 TEL:(512) 331-8883		

PROJECT CONTACT LIST:

SURVEYOR OF RECORD MATKIN HOOVER KYLE PRESSLER 3303 SHELL ROAD, SUITE 3 GEORGETOWN, TEXAS, 78628 TEL:(512) 868-2244	QT REAL ESTATE PROJECT MANAGER QUIKTRIP CORPORATION ROBERT COSTELLO 2007 SAM BASS ROAD, SUITE 100 ROUND ROCK, TEXAS, 78681 TEL:(512) 814-4326
ENGINEER OF RECORD KIMLEY-HORN DEVIN KING, P.E. 5301 SOUTHWEST PARKWAY, SUITE 100, BUILDING 3 AUSTIN, TEXAS, 78735 TEL:(512) 787-8638	QT CIVIL PROJECT MANAGER QUIKTRIP CORPORATION WADE RICHARDSON 4705 SOUTH 129TH EAST AVE TULSA, OK 74134 TEL: (918) 615-7942

ODS QUANTITIES:	
LOT SIZE	___ SF
DEVELOPED SITE (LOD)	___ SF
QT SPEC CONCRETE	___ SF
ALTERNATE:	
QT SPEC ASPHALT/CONCRETE	___ SF/ ___ SF
UG DETENTION	___ CF
SOD OR DECOMPOSED GRANITE AREA	___ SF
ALL OTHER NON-OT SPEC PAVING	___ SF
MASONRY CANOPY	YES/NO
MASONRY CANOPY	YES/NO
WATER QUALITY UNIT	YES/NO
-UNIT TYPE:	e.g. CRYSTAL STREAM

THE QUANTITIES ABOVE ARE INTENDED FOR INTERNAL TRACKING PURPOSES ONLY. THEY ARE NOT REPRESENTATIVE OF THE QUANTITIES FOR BIDDING PURPOSES. THE CONTRACTOR IS RESPONSIBLE FOR CALCULATING THEIR OWN QUANTITIES.



PROJECT NO.: 069304941
Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10101 WILLOW CREEK DR., SUITE 100
SAN ANTONIO, TX 78216
PHONE: 210-544-1888 FAX: 210-544-1889
WWW.KIMLEY-HORN.COM
TYPE: FIRM NO. 028

SHEET INDEX

NO.	TITLE
C001	COVER SHEET
C002	CITY OF LEANDER GENERAL NOTES
C003	KHA GENERAL NOTES
C004	TCEQ GENERAL NOTES
C005	FINAL PLAT
C020	SURVEY 1 OF 5
C021	SURVEY 2 OF 5
C022	SURVEY 3 OF 5
C023	SURVEY 4 OF 5
C024	SURVEY 5 OF 5
C030	DEMOLITION PLAN
C100	SITE PLAN
C101	FIRE PROTECTION PLAN
C110	GRADING PLAN
C111	BUILDING & DETAILED GRADING PLANS
C112	CANOPY & DETAILED GRADING PLANS
C113	ADA COMPLIANCE REFERENCE PLAN
C120	STORM SEWER PLAN
C121	PRE-DEVELOPED DRAINAGE MAP
C122	POST-DEVELOPED DRAINAGE MAP
C123	INLET DRAINAGE AREA MAP
C124	DETENTION POND PLAN
C125	TXDOT DRIVEWAY CULVERT DRAINAGE AREA MAP
C130A	ASPHALT PAVING PLAN
C130B	CONCRETE PAVING PLAN
C131	BUILDING PAVING PLAN
C140	EROSION CONTROL PLAN - PHASE 1
C141	EROSION CONTROL PLAN - PHASE 2
C150	UTILITY PLAN
C151	UTILITY PROFILE
C152	UTILITY VERIFICATION PLAN
C160	PHOTOMETRIC SITE PLAN
C500	MISCELLANEOUS SITE DETAILS I
C501	MISCELLANEOUS SITE DETAILS II
C502	MISCELLANEOUS SITE DETAILS III
C503	EROSION CONTROL DETAILS
C510	ADA DETAILS I
C511	ADA DETAILS II
C520	PAVING DETAILS I
C521	PAVING DETAILS II
C522	PAVING DETAILS III
C523	PAVING DETAILS IV
C524	PAVING DETAILS V
C530	TRENCHING DETAILS I
C531	TRENCHING DETAILS II
C540	DRAINAGE DETAILS
C541	CONTECH DRAINAGE DETAILS 1 OF 2
C542	CONTECH DRAINAGE DETAILS 2 OF 2
C550	UTILITY DETAILS I
C551	UTILITY DETAILS II
C552	KEEN GRINDER PUMP DETAILS
L100	LANDSCAPE PLAN
L110	IRRIGATION PLAN
L500	LANDSCAPE DETAILS
L511	IRRIGATION DETAILS

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.
PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
COVER SHEET

SHEET NUMBER:
C001

FILE LOCATION: \\S:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-CORR.dwg
 TAB NAME: COVER SHEET
 USER: rdesor-garcia
 SAVED: 10/20/23 5:49 PM
 PLOTTED: 4/21/2023 10:50 AM

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Q	GENERAL NOTES REVISED JUNE 22, 2022 ANY CHANGES TO THESE NOTES SHOULD BE CLOUDED ON THE PLAN SET. CITY CONTACTS: ENGINEERING MAIN LINE: 512-528-2766 PLANNING DEPARTMENT: 512-528-2750 PUBLIC WORKS MAIN LINE: 512-259-2640 STORMWATER INSPECTIONS: 512-285-0055 UTILITIES MAIN LINE: 512-259-1342 UTILITIES OR CALL: 512-509-4700 UTILITY LOCATE REQUESTS: locates@leandertx.gov														
P	1. THE CONTRACTOR SHALL VERIFY ALL DEPTHS AND LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES WITH CONSTRUCTION PLANS FOUND IN THE FIELD SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER. 2. THE CONTRACTOR SHALL CONTACT THE TEXAS EXCAVATION SYSTEM AT 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS 48 HOURS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES THAT ARE TO BE EXTENDED, TIED TO, CROSSED, OR ALTERED; OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS. 3. CONTACT THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT FOR EXISTING WATER AND WASTEWATER LOCATIONS 48 HOURS PRIOR TO CONSTRUCTION. a. LOCATE REQUESTS MUST INCLUDE A COPY OF YOUR 811 TICKET. THE CITY OF LEANDER IS ALLOWED UP TO 48 HOURS TO COMPLY WITH YOUR REQUEST, EXCLUDING WEEKENDS AND DESIGNATED CITY HOLIDAYS. b. REFRESH ALL LOCATES BEFORE 14 DAYS - LOCATE REFRESH REQUESTS MUST INCLUDE A COPY OF YOUR 811 TICKET. SUBMIT ALL REQUESTS TO LOCATES@LEANDERTX.GOV. TEXAS PIPELINE DAMAGE PREVENTION LAWS REQUIRE THAT A LOCATE REFRESH REQUEST BE SUBMITTED BEFORE 14 DAYS, OR IF LOCATION MARKERS ARE NO LONGER VISIBLE. c. REPORT PIPELINE DAMAGE IMMEDIATELY - IF YOU WITNESS OR EXPERIENCE PIPELINE EXCAVATION DAMAGE, PLEASE CONTACT THE CITY OF LEANDER BY PHONE AT 512-259-2640. 4. ANY CHANGES OR REVISIONS TO THESE PLANS MUST FIRST BE SUBMITTED TO THE CITY BY THE DESIGN ENGINEER FOR REVIEW AND WRITTEN APPROVAL PRIOR TO CONSTRUCTION OF THE REVISION. 5. A TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, SHALL BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO ANY PARTIAL OR COMPLETE ROADWAY CLOSURES. TRAFFIC CONTROL PLANS SHALL BE SITE SPECIFIC AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER. LANE CLOSURES ON ARTERIALS AND ANY FULL ROAD CLOSURES REQUIRE MESSAGE BOARDS NOTIFYING THE PUBLIC ONE WEEK PRIOR TO THE CLOSURE. 6. NO WORK IS TO BE PERFORMED BETWEEN THE HOURS OF 9:00 P.M. AND 7:00 A.M. THE CITY INSPECTOR RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO UNCOVER ALL WORK PERFORMED WITHOUT INSPECTION FURTHER, THERE IS A NOISE ORDINANCE IN EFFECT FOR CONSTRUCTION ACTIVITY BETWEEN THE HOURS OF 9:00 PM AND 7:00 AM. REQUESTS FOR EXCEPTIONS TO THE ORDINANCE MUST BE MADE TO LEANDER CITY COUNCIL. 7. CONTACT THE CITY INSPECTOR 4 DAYS PRIOR TO WORK TO SCHEDULE ANY INSPECTIONS ON WEEKENDS OR CITY HOLIDAYS. 8. NO STREET LIGHTS OR SIGNS OF ANY KIND ARE TO BE PLACED WITHIN ANY SIDEWALKS. 9. NO BLASTING IS ALLOWED. 10. ANY EXISTING UTILITIES, PAVEMENT, CURBS, SIDEWALKS, STRUCTURES, TREES, ETC., THAT ARE DAMAGED OR REMOVED SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. 11. THE CONTRACTOR SHALL GIVE THE CITY OF LEANDER 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION. CONTACT ASSIGNED CITY INSPECTOR. 12. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT AND THE CITY OF LEANDER REPRESENTATIVES PRIOR TO INSTALLATION OF EROSION/SEDIMENTATION CONTROLS AND TREE PROTECTION MEASURES AND PRIOR TO BEGINNING ANY WORK. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER PLANNING DEPARTMENT PLANNING COORDINATOR AT LEAST THREE (3) DAYS PRIOR TO THE MEETING DATE. 13. THE CONTRACTOR AND ENGINEER SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE ENGINEER SHALL FURNISH THE CITY OF LEANDER ACCURATE "RECORD DRAWINGS" FOLLOWING THE COMPLETION OF ALL CONSTRUCTION. THESE "RECORD DRAWINGS" SHALL MEET THE SATISFACTION OF THE ENGINEERING DEPARTMENTS PRIOR TO FINAL ACCEPTANCE 14. WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS, THE CONTRACTOR SHALL CONFINE HIS WORK TO WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. PRIOR TO ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT EASEMENTS. CLEANUP SHALL BE TO THE SATISFACTION OF THE ENGINEER. 15. CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS AND PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO OWNER. 16. THE CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. IN THE EVENT THAT A FENCE MUST BE REMOVED, THE CONTRACTOR SHALL REPLACE SAID FENCE OR PORTION THEREOF WITH THE SAME TYPE OF FENCING TO A QUALITY OF EQUAL OR BETTER THAN THE ORIGINAL FENCE. 17. ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA). OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE. INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 1033 LA POSADA DR. SUITE 375, AUSTIN, TEXAS 78752-3832. 18. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT WHERE NOT SPECIFICALLY COVERED IN THE PROJECT SPECIFICATIONS SHALL CONFORM TO ALL CITY OF LEANDER DETAILS AND CITY OF AUSTIN STANDARD SPECIFICATIONS. 19. PROJECT SPECIFICATIONS TAKE PRECEDENCE OVER PLANS AND SPECIAL CONDITIONS GOVERN OVER TECHNICAL SPECIFICATIONS. 20. HOT MIX ASPHALTIC CONCRETE PAVEMENT SHALL BE MINIMUM THICKNESS OF 2 INCHES WITH NO RECYCLED ASPHALT SHINGLES CONTENT. 21. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY QUESTIONS THAT MAY RISE CONCERNING THE INTENT, PLACEMENT, OR LIMITS OF DIMENSIONS OR GRADES NECESSARY FOR THE CONSTRUCTION OF THIS PROJECT. 22. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT. 23. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COORDINATION BETWEEN HIMSELF AND OTHER CONTRACTORS AND UTILITIES IN THE VICINITY OF THE PROJECT. THIS INCLUDES GAS, WATER, WASTEWATER, ELECTRICAL, TELEPHONE, CABLE TV AND STREET DRAINAGE WORK. ONCE THE CONTRACTOR BECOMES AWARE OF A POSSIBLE CONFLICT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE ENGINEER WITHIN TWENTY-FOUR (24) HOURS. 24. THE CONTRACTOR MUST OBTAIN A CONSTRUCTION WATER METER FOR ALL WATER USED DURING CONSTRUCTION. A COPY OF THIS PERMIT MUST BE CARRIED AT ALL TIMES BY ALL WHO USE WATER. 25. CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ROADS AND DRIVES ADJACENT TO AND NEAR THE SITE FREE FROM SOIL, SEDIMENT AND DEBRIS. CONTRACTOR WILL NOT REMOVE SOIL, SEDIMENT OR DEBRIS FROM ANY AREA OR VEHICLE BY MEANS OF WATER. ONLY SHOVELING AND SWEEPING WILL BE ALLOWED. CONTRACTOR WILL BE RESPONSIBLE FOR DUST CONTROL FROM THE SITE. 26. THE CITY OF LEANDER SHALL NOT BE PETITIONED FOR ACCEPTANCE UNTIL ALL NECESSARY EASEMENT DOCUMENTS HAVE BEEN SIGNED AND RECORDED. 27. AN ENGINEER'S CONCURRENCE LETTER AND RECORD DRAWINGS SHALL BE SUBMITTED TO THE ENGINEERING DEPARTMENT PRIOR TO THE ISSUANCE OF CERTIFICATE OF COMPLETION OR SUBDIVISION ACCEPTANCE. THE ENGINEER AND CONTRACTOR SHALL VERIFY THAT ALL FINAL REVISIONS AND CHANGES HAVE BEEN MADE TO THE DIGITAL COPY PRIOR TO CITY SUBMITTAL. RECORD CONSTRUCTION DRAWINGS, INCLUDING ROADWAY AND ALL UTILITIES SHALL BE PROVIDED TO THE CITY IN DIGITAL FORMAT AS AUTOCAD ".DWG" FILES, MICROSTATION ".DGN" FILES OR ESRI ".SHP" FILES ON CD ROM. LINE WEIGHTS, LINE TYPES AND TEXT SIZE SHALL BE SUCH THAT IF HALF-SIZE PRINTS (11"x17") WERE PRODUCED, THE														
N	PLANS WOULD STILL BE LEGIBLE. ALL REQUIRED DIGITAL FILES SHALL CONTAIN A MINIMUM OF TWO CONTROL POINTS REFERENCED TO THE STATE PLANE GRID COORDINATE SYSTEM - TEXAS CENTRAL ZONE (4203), IN US SURVEY FEET AND SHALL INCLUDE ROTATION INFORMATION AND SCALE FACTOR REQUIRED TO REDUCE SURFACE COORDINATES TO GRID COORDINATES IN US SURVEY FEET. 28. TREES IN EXISTING ROW SHOULD BE PROTECTED OR NOTED IN THE PLANS TO BE REMOVED. CONSTRUCTION SEQUENCE NOTES 1. INSTALL STABILIZED CONSTRUCTION ENTRANCE, EROSION CONTROLS AND TREE PROTECTION FENCING FOR EACH PHASE PRIOR TO CLEARING AND GRUBBING AND PER APPROVED EROSION AND SEDIMENTATION CONTROL/TREE PROTECTION PLAN. 2. THE CONTRACTOR SHALL ARRANGE AND COORDINATE ACCEPTABLE MEETING TIMES FOR AN ON-SITE PRE-CONSTRUCTION MEETING WITH THE OWNER, PROJECT ENGINEER, RELEVANT CONTRACTORS, RELEVANT UTILITY REPRESENTATIVES, AND THE CITY ENGINEER. AT THIS MEETING, THE CITY SHALL VERIFY THAT ALL EROSION AND SEDIMENT CONTROLS AND TREE PROTECTION ARE IN PLACE. THAT CONSTRUCTION DRAWINGS AND THE SWPPP ARE LOCATED ON SITE, AND THAT THE SWPPP PERMITS HAVE BEEN ISSUED. THE CITY MAY THEN ISSUE THE SUBDIVISION IMPROVEMENT PERMIT. 3. BEGIN SITE CLEARING. 4. CLEAR AND GRUB AND STRIP TOPSOIL. STOCKPILE TOPSOIL FOR LATER USE. 5. ROUGH SUBGRADE SITE IN ACCORDANCE WITH PLANS AND SPECIFICATIONS. 6. CONSTRUCT WET AND DRY UTILITIES. 7. FINAL SUBGRADE PREPARATION. 8. INSTALL BASE MATERIALS. 9. INSTALL CONCRETE (FOUNDATIONS, CURBS, FLATWORK). 10. CONSTRUCT BUILDINGS. 11. INSTALL PAVEMENTS. 12. TOPSOIL, IRRIGATION, AND LANDSCAPING. 13. PROJECT ENGINEER INSPECTS JOB AND SUBMITS THE ENGINEER'S CONCURRENCE LETTER. 14. CITY VISITS SITE AND ISSUES CERTIFICATE OF ACCEPTANCE ONLY IF ALL CONSTRUCTION IS IN SUBSTANTIAL CONFORMANCE TO THE PLANS. 15. SITE CLEANUP AND REMOVAL OF TEMPORARY BMP'S. 16. FOLLOWING THE COMPLETION OF THE PROJECT THE CONTRACTOR SHALL REMOVE ANY SEDIMENT BUILDUP IN THE WET POND FROM CONSTRUCTION ACTIVITIES. EROSION CONTROL NOTES 1. THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE PROTECTIVE FENCING PRIOR TO ANY WORK (CLEARING, GRUBBING OR EXCAVATION). CONTACT STORMWATER INSPECTOR FOR ON SITE INSPECTION PRIOR TO BEGINNING CONSTRUCTION. 2. THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES. 3. THE TEMPORARY SPOILS DISPOSAL SITE IS TO BE SHOWN IN THE EROSION CONTROL MAP. 4. ANY ON-SITE SPOILS DISPOSAL SHALL BE REMOVED PRIOR TO ACCEPTANCE UNLESS SPECIFICALLY ALLOWED ON THE PLANS. THE DEPTH OF SPOIL SHALL NOT EXCEED 10 FEET IN ANY AREA. 5. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE RESTORED WITH A MINIMUM OF 6 INCHES OF TOPSOIL AND COMPOST BLEND. TOPSOIL ON SINGLE FAMILY LOTS MAY BE INSTALLED WITH HOME CONSTRUCTION. THE TOPSOIL AND COMPOST BLEND SHALL CONSIST OF 75% TOPSOIL AND 25% COMPOST. 6. SEEDING FOR REESTABLISHING VEGETATION SHALL COMPLY WITH THE AUSTIN GROW GREEN GUIDE OR WILLIAMSON COUNTY'S PROTOCOL FOR SUSTAINABLE ROADSIDES (SPEC 164-WOOD). SEEDING FOR EROSION CONTROL. RESEEDING VARIETIES OF BERMUDA SHALL NOT BE USED. 7. STABILIZED CONSTRUCTION ENTRANCE IS REQUIRED AT ALL POINTS WHERE CONSTRUCTION TRAFFIC IS EXITING THE PROJECT ONTO EXISTING PAVEMENT. LINEAR CONSTRUCTION PROJECTS MAY REQUIRE SPECIAL CONSIDERATION. ROADWAYS SHALL REMAIN CLEAR OF SILT AND MUD. 8. TEMPORARY STOP SIGNS SHOULD BE INSTALLED AT ALL CONSTRUCTION ENTRANCES WHERE A STOP CONDITION DOES NOT ALREADY EXIST. 9. IN THE EVENT OF INCLEMENT WEATHER THAT MAY RESULT IN A FLOODING SITUATION, THE CONTRACTOR SHALL REMOVE INLET PROTECTION MEASURES UNTIL SUCH TIME AS THE WEATHER EVENT HAS PASSED. WATER AND WASTEWATER NOTES 1. PRESSURE TAPS SHALL BE IN ACCORDANCE WITH CITY OF LEANDER STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL PERFORM ALL EXCAVATION, ETC. AND SHALL FURNISH, INSTALL AND AIR TEST THE SLEEVE AND VALVE. A CITY OF LEANDER INSPECTOR MUST BE PRESENT WHEN THE CONTRACTOR MAKES A TAP, AND/OR ASSOCIATED TESTS. A MINIMUM OF TWO (2) WORKING DAYS NOTICE IS REQUIRED. "SIZE ON SIZE" TAPS WILL NOT BE PERMITTED UNLESS MADE BY THE USE OF AN APPROVED FULL-CIRCLE GASKETED TAPPING SLEEVE. CONCRETE BLOCKING SHALL BE PLACED BEHIND AND UNDER ALL TAP SLEEVES A MINIMUM OF 24 HOURS PRIOR TO THE BRANCH BEING PLACED INTO SERVICE. BLOCKING SHALL BE INSPECTED PRIOR TO BACKFILL. 2. FIRE HYDRANTS ON MAINS UNDER CONSTRUCTION SHALL BE SECURELY WRAPPED WITH A BLACK POLY WRAP BAG AND TAPED INTO PLACE. THE POLY WRAP SHALL BE REMOVED WHEN THE MAINS ARE ACCEPTED AND PLACED INTO SERVICE. 3. CURVILINEAR WASTEWATER DESIGN LAYOUT IS NOT PERMITTED. 4. THRUST BLOCKING OR RESTRAINTS SHALL BE IN ACCORDANCE WITH THE WILLIAMSON COUNTY ESD NO. 4 STANDARD SPECIFICATIONS AND REQUIRED AT ALL FITTINGS PER DETAIL OR MANUFACTURER'S RECOMMENDATION. ALL FITTINGS SHALL HAVE BOTH THRUST BLOCKING AND RESTRAINTS. 5. MANDREL TESTING WILL BE REQUIRED ON ALL WASTEWATER PIPE. PER TCEQ, THIS TEST MUST BE CONDUCTED AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS. 6. ALL NEWLY INSTALLED PIPES AND RELATED PRODUCTS MUST CONFORM TO AMERICAN NATIONAL STANDARDS INSTITUTE/NATIONAL SANITATION FOUNDATION (ANSI/NSF) STANDARD 61 AND MUST BE CERTIFIED BY AND ORGANIZATION ACCREDITED BY ANSI. 7. DURING PERIODS OF EXTENDED DRY WEATHER, TRENCH BACKFILL MUST BE COMPACTED BY FLOODING THE TRENCHES AS DIRECTED BY THE CITY ENGINEER. 8. ALL WATER SERVICE, WASTEWATER SERVICE AND VALVE LOCATIONS SHALL BE APPROPRIATELY STAMPED AS FOLLOWS: WATER SERVICE "W" ON TOP OF CURB WASTEWATER SERVICE "S" ON TOP OF CURB VALVE "V" ON TOP OF CURB 9. TOOLS FOR STAMPING THE CURBS SHALL BE PROVIDED BY THE CONTRACTOR. OTHER APPROPRIATE MEANS OF STAMPING SERVICE AND VALVE LOCATIONS SHALL BE PROVIDED IN AREAS WITHOUT CURBS. SUCH MEANS OF STAMPING SHALL BE SPECIFIED BY THE ENGINEER AND ACCEPTED BY THE CITY OF LEANDER. 10. ALL PLASTIC PIPES FOR USE IN PUBLIC WATER SYSTEMS MUST BEAR THE NATIONAL SANITATION FOUNDATION SEAL OF APPROVAL (NSF-PW) AND HAVE AN ASTM DESIGN PRESSURE RATING OF AT LEAST 200 PSI. 11. NO PIPE OR FITTING WHICH HAS BEEN USED FOR ANY PURPOSE OTHER THAN THE CONVEYANCE OF DRINKING WATER SHALL BE ACCEPTED OR RELOCATED FOR USE IN ANY PUBLIC DRINKING WATER SUPPLY. 12. TYPICAL DEPTH OF COVER FOR ALL WASTEWATER LINES SHALL BE 48" MINIMUM. WATER LINES SHALL BE 36" MINIMUM UNDER BOTH PAVED AND NATURAL GROUND. STORM SEWER SHALL BE 24" MINIMUM UNDER NATURAL GROUND. 13. THE HYDROSTATIC LEAKAGE RATE SHALL NOT EXCEED THE AMOUNT ALLOWED OR RECOMMENDED BY AWWA FORMULAS. 14. ALL WATER MAINS, DISTRIBUTION LINES AND SERVICE LINES SHALL BE INSTALLED IN ENCASEMENT PIPE UNDERNEATH EXISTING STREETS AND OTHER PAVED SURFACES UNLESS APPROVED WITH PLANS. 15. ALL MECHANICAL RESTRAINTS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. 16. ALL DEAD-END WATER MAINS SHALL HAVE THRUST RESTRAINTS INSTALLED ON THE LAST THREE PIPE LENGTHS (STANDARD 20' LAYING LENGTH). AT MINIMUM, AND THRUST BLOCKS INSTALLED ON THE PLUS. ADDITIONAL THRUST RESTRAINTS MAY BE REQUIRED BASED UPON THE MANUFACTURER'S RECOMMENDATIONS AND/OR CALCULATIONS BY THE ENGINEER OF RECORD. 17. WHERE WATER LINES CROSS WASTEWATER LINES AND THERE IS LESS THAN 9 FEET CLEARANCE BETWEEN LINES, THE WASTEWATER LINE SHALL BE PLACED SO THAT THE WASTEWATER PIPE SECTION IS CENTERED ON THE WATER LINE AND CONSTRUCTED IN ACCORDANCE WITH TCEQ CHAPTERS 217.53(b) AND 290.44(e). 18. PIPE MATERIAL FOR WATER MAINS SHALL BE PVC (AWWA C900-16 MIN. 235 PSI PRESSURE RATING). WATER SERVICES (2" OR LESS) SHALL BE POLYETHYLENE TUBING (BLACK, 200PSI, SDR-91). DUCTILE IRON PIPE (AWWA C115/C151, MIN. PRESSURE CLASS 250) MAY BE USED FOR WATER MAINS WITH THE EXPRESS APPROVAL OF CITY OF LEANDER ENGINEERING. 19. PIPE FOR PRESSURE WASTEWATER MAINS SHALL BE PVC (AWWA C900-16), GREEN AND MARKED FOR SEWER. PIPE MATERIAL FOR GRAVITY WASTEWATER MAINS SHALL BE PVC (ASTM D2241, D3034 MAX. SDR-26 OR PS115 1679) OR FIBERGLASS WITH PIPE STIFFNESS OF 72 PSI PER COA SP. U.W.-509. 20. ALL FIRE HYDRANT LEADS SHALL BE DUCTILE IRON PIPE (AWWA C115/C151 PRESSURE CLASS 350). 21. INTERIOR SURFACES OF ALL DUCTILE IRON POTABLE OR RECLAIMED WATER PIPE SHALL BE CEMENT-MORTAR LINED AND SEAL COATED AS REQUIRED BY AWWA C104. 22. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH MINIMUM 8-MIL POLYETHYLENE. 23. THE CONTRACTOR SHALL CONTACT THE ENGINEERING DEPARTMENT INSPECTOR AT 528-2700 AT LEAST 48 HOURS PRIOR TO CONNECTING TO THE EXISTING WATER LINES. 24. ALL MANHOLES SHALL BE CONCRETE WITH CAST IRON RING AND COVER. TAPPING OF FIBERGLASS MANHOLES SHALL NOT BE ALLOWED. 25. EXISTING MANHOLES MODIFIED BY CONSTRUCTION ACTIVITY SHALL BE TESTED FOR LEAKAGE BY VACUUM. ANY EXISTING MANHOLE WHICH FAILS TO PASS THE VACUUM TEST SHALL BE CLOSELY EXAMINED BY THE INSPECTOR AND THE CONTRACTOR TO DETERMINE IF THE MANHOLE CAN BE REPAIRED. THEREAFTER, THE CONTRACTOR SHALL EITHER REPAIR OR REMOVE AND REPLACE THE MANHOLE AS DIRECTED. 26. PIPE CONNECTIONS TO EXISTING MANHOLES AND JUNCTION BOXES SHALL BE CONSTRUCTED IN ACCORDANCE WITH CITY OF AUSTIN SPECIFICATION 506.5.F. 27. LINE FLUSHING OR ANY ACTIVITY USING A LARGE QUANTITY OF WATER MUST BE COORDINATED WITH THE PUBLIC WORKS DEPARTMENT. 28. THE CONTRACTOR, AT HIS EXPENSE, SHALL PERFORM STERILIZATION OF ALL CONSTRUCTED POTABLE WATER LINES AND SHALL PROVIDE ALL EQUIPMENT (INCLUDING TEST GAUGES), SUPPLIES (INCLUDING CONCENTRATED CHLORINE DISINFECTING MATERIAL), AND NECESSARY LABOR REQUIRED FOR THE STERILIZATION PROCEDURE. THE STERILIZATION PROCEDURE SHALL BE MONITORED BY CITY OF LEANDER PERSONNEL. WATER SAMPLES WILL BE COLLECTED BY THE CITY OF LEANDER TO VERIFY EACH TREATED LINE HAS ATTAINED AN INITIAL CHLORINE CONCENTRATION OF 50 PPM. WHERE MEANS OF FLUSHING IS NECESSARY, THE CONTRACTOR, AT HIS EXPENSE, SHALL PROVIDE FLUSHING DEVICES AND REMOVE SAID DEVICES PRIOR TO FINAL ACCEPTANCE BY THE CITY OF LEANDER. 29. SAMPLING TAPS SHALL BE BROUGHT UP TO 3 FEET ABOVE GRADE AND SHALL BE EASILY ACCESSIBLE FOR CITY PERSONNEL. AT THE CONTRACTORS' REQUEST, AND IN HIS PRESENCE, SAMPLES FOR BACTERIOLOGICAL TESTING WILL BE COLLECTED BY THE CITY OF LEANDER NOT LESS THAN 24 HOURS AFTER THE TREATED LINE HAS BEEN FLUSHED OF THE CONCENTRATED CHLORINE SOLUTION AND CHARGED WITH WATER APPROVED BY THE CITY. 30. TESTING SHALL BE PERFORMED FOR ALL WASTEWATER PIPE INSTALLED AND PRESSURE PIPE HYDROSTATIC TESTING OF ALL WATER LINES CONSTRUCTED. THE OWNER'S CONTRACTOR SHALL PROVIDE ALL EQUIPMENT (INCLUDING PUMPS AND GAUGES), SUPPLIES AND LABOR NECESSARY TO PERFORM THE TESTS. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER ENGINEERING DEPARTMENT NO LESS THAN 48 HOURS PRIOR TO PERFORMING STERILIZATION, QUALITY TESTS, OR PRESSURE TESTS. A CITY OF LEANDER INSPECTOR SHALL BE PRESENT FOR ALL TESTS AND SHALL BE PAID FOR BY THE OWNER/CONTRACTOR. THESE SERVICES ARE PAID FOR AT THE TIME OF CONSTRUCTION PLAN SUBMITTAL. 31. THE CONTRACTOR SHALL NOT OPEN OR CLOSE ANY VALVE UNLESS AUTHORIZED BY THE CITY OF LEANDER. 32. ALL VALVE BOXES AND COVERS SHALL BE CAST IRON. 33. ALL WATER VALVE COVERS ARE TO BE PAINTED BLUE. 34. ALL WATER METER BOXES SHALL BE: a. SINGLE, 1" METER AND BELOW DFV37F-12-1CA, OR EQUAL b. DUAL, 1" METERS AND BELOW DFV39F-12-1CA, OR EQUAL c. 1.5" SINGLE METER DFV65F-14-1CA, OR EQUAL d. 2" SINGLE METER DFV1730F-12-1CA, OR EQUAL 35. SAND, AS DESCRIBED IN AUSTIN SPECIFICATION ITEM 510 PIPE, SHALL NOT BE USED AS BEDDING FOR WATER AND WASTEWATER LINES. ACCEPTABLE BEDDING MATERIALS ARE PIPE BEDDING STONE, PEA GRAVEL AND IN LIEU OF SAND, A NATURALLY OCCURRING OR MANUFACTURED STONE MATERIAL CONFORMING TO ASTM C33 FOR STONE QUALITY AND MEETING THE FOLLOWING GRADATION SPECIFICATION: SIEVE SIZE PERCENT RETAINED BY WEIGHT 1/2" 0 3/8" 0 #4 40-85 #10 95-100 36. THE CONTRACTOR IS HEREBY NOTIFIED THAT CONNECTING TO, SHUTTING DOWN, OR TERMINATING EXISTING UTILITY LINES MAY HAVE TO OCCUR AT OFF-PEAK HOURS. SUCH HOURS ARE USUALLY OUTSIDE NORMAL WORKING HOURS AND POSSIBLY BETWEEN 12 AM AND 6 AM. 37. ALL WASTEWATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) REGULATIONS, 30 TAC CHAPTER 213 AND 30 TAC CHAPTER 217, AS APPLICABLE. WHENEVER TCEQ AND CITY OF LEANDER SPECIFICATION CONFLICT, THE MORE STRINGENT SHALL APPLY. 38. MANHOLES SHALL BE COATED PER CITY OF AUSTIN SPL VW-511 (RAVEN 405 OR SPRAYWALL). 39. DENSITY TESTING FOR TRENCH BACKFILL LOCATED WITHIN THE LIMITS OF THE PAVED AREA IS TO BE DONE IN 12" LIFTS EVERY 500' AND AT LEAST ONCE PER LINE SEGMENT. 40. ALL GRAVITY WASTEWATER MAINS TO BE TESTED BY CAMERA AND PAID FOR BY THE CONTRACTOR. CAMERA TESTING FOR WASTEWATER LINES IN ROADWAY SHALL OCCUR BEFORE PAVING. CONTRACTOR SHALL PROVIDE THE CITY WITH A DVD COPY OF THE FULL CAMERA INSPECTION. 41. RECLAIMED AND RECYCLED WATER LINE SHALL BE CONSTRUCTED OF "PURPLE PIPE." ALL RECLAIMED AND RECYCLED WATER VALVE COVERS SHALL BE SQUARE AND PAINTED PURPLE. STREET AND DRAINAGE NOTES 1. ALL SIDEWALKS SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT. THE CITY OF LEANDER HAS NOT REVIEWED THESE PLANS FOR COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT, OR ANY OTHER ACCESSIBILITY LEGISLATION, AND DOES NOT WARRANT OR APPROVE THESE PLANS FOR ANY ACCESSIBILITY STANDARDS. 2. PRIOR TO ACCEPTANCE THE ENGINEER SHALL SUBMIT DOCUMENTATION THAT THE IMPROVEMENTS WERE INSPECTED BY TDR OR A REGISTERED ACCESSIBILITY SPECIALIST (RAS) AND ARE IN COMPLIANCE WITH THE REQUIREMENTS OF THE TABA. 3. CONTRACTOR SHALL PROVIDE QUALITY TESTING FOR ALL INFRASTRUCTURES TO BE ACCEPTED AND MAINTAINED BY THE CITY OF LEANDER AFTER COMPLETION. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER ENGINEERING DEPARTMENT AT 528-2700 NO LESS THAN 48 HOURS PRIOR TO ANY TESTING. 4. BACKFILL BEHIND THE CURB SHALL BE COMPACTED TO OBTAIN A MINIMUM OF 95% MAXIMUM DENSITY TO WITHIN 6" OF TOP OF CURB. MATERIAL USED SHALL BE PRIMARILY GRANULAR WITH NO ROCKS LARGER THAN 6" IN THE GREATEST DIMENSION. THE REMAINING 6" SHALL BE CLEAN TOPSOIL FREE FROM ALL CLODS AND SUITABLE FOR SUSTAINING PLANT LIFE 5. A MINIMUM OF 6" OF TOPSOIL SHALL BE PLACED BETWEEN THE CURB AND RIGHT-OF-WAY AND IN ALL DRAINAGE CHANNELS EXCEPT CHANNELS CUT IN STABLE ROCK. 6. DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT, INCLUDING GAS, ELECTRIC TELEPHONE, CABLE TV, ETC., SHALL BE A MINIMUM OF 36" BELOW SUBGRADE. 7. STREET RIGHT-OF-WAY SHALL BE GRADED AT A SLOPE OF 1/4" PER FOOT TOWARD THE CURB UNLESS OTHERWISE INDICATED. HOWEVER, IN NO CASE SHALL THE WIDTH OF RIGHT-OF-WAY AT 1/4" PER FOOT SLOPE BE LESS THAN 10 FEET UNLESS A SPECIFIC REQUEST FOR AN ALTERNATE GRADING SCHEME IS MADE TO AND ACCEPTED BY THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT. 8. BARRICADES BUILT TO THE CITY OF LEANDER STANDARDS SHALL BE ERECTED ON ALL DEAD-END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB AND PUBLIC SAFETY.														
M	TRENCH SAFETY NOTES 1. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT ARE DESCRIBED IN ITEM 509S "TRENCH SAFETY SYSTEMS" OF THE CITY OF AUSTIN STANDARD SPECIFICATIONS AND SHALL BE IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U.S. OCCUPATION SAFETY AND HEALTH ADMINISTRATION REGULATIONS. GRADING NOTES 1. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT TO ALLOW ANY PONDING OF WATER. 2. THE CONTRACTOR SHALL CONSTRUCT EARTHEN EMBANKMENTS WITH SLOPES NO STEEPER THAN 3:1 AND COMPACT SOIL TO 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD SPECIFICATIONS. 3. AREAS OF SOIL DISTURBANCE ARE LIMITED TO GRADING AND IMPROVEMENTS SHOWN. ALL OTHER AREAS WILL NOT BE DISTURBED. BENCHMARK NOTES 1. (PROVIDE LOCATION DESCRIPTION)														
L	KIMLEY-HORN & ASSOCIATES, INC. 137894 04/21/2023 PROJECT NO.: 069304941 KIMLEY-HORN & ASSOCIATES, INC. 2023 KIMLEY-HORN AND ASSOCIATES, INC. 10101 W. HIGHTWAY 190, SUITE 400, SAN ANTONIO, TX 78216 PHONE: 710-544-1800 FAX: 710-544-8909 WWW.KIMLEY-HORN.COM E-MAIL: INFO@KIMLEY-HORN.COM TIME PERM NO. 028														
K	QuikTrip No. 4160 7601 W SH 29 GEORGETOWN, TEXAS														
J	QT														
H	© COPYRIGHT QUIKTRIP CORPORATION 2011 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.														
G	PROTOTYPE: P-112 (11/18/22) DIVISION: VERSION: 001 DESIGNED BY: OHW DRAWN BY: OHW REVIEWED BY: RMR														
F	DESCRIPTION														
E	REV DATE														
D	ORIGINAL ISSUE DATE:														
C	SHEET TITLE: CITY OF LEANDER GENERAL NOTES														
B	SHEET NUMBER: C002														
A	FILE LOCATION: \\hkr\Share\Civil\069304941\Plan Sheets\C-NOTE.dwg TAB NAME: CITY OF LEANDER GENERAL NOTES USER: rrc@leandertx.gov SAVED: 4/10/2023 5:49 PM PLOTTED: 4/21/2023 10:27 AM														

FILE LOCATION: S:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-NOTE.dwg TAB NAME: TCEQ GENERAL NOTES USER: oregonc USER: oregonc PLOTTED: 4/21/2023 10:27 AM

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Q														Q
P														P
N														N
M														M
L														L
K														K
J														J
H														H
G														G
F														F
E														E
D														D
C														C
B														B
A														A
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15

**Texas Commission on Environmental Quality
Water Pollution Abatement Plan
General Construction Notes**

Edwards Aquifer Protection Program Construction Notes – Legal Disclaimer

The following listed "construction notes" are intended to be advisory in nature only and do not constitute an approval or conditional approval by the Executive Director (ED), nor do they constitute a comprehensive listing of rules or conditions to be followed during construction. Further actions may be required to achieve compliance with TCEQ regulations found in Title 30, Texas Administrative Code (TAC), Chapters 213 and 217, as well as local ordinances and regulations providing for the protection of water quality. Additionally, nothing contained in the following listed "construction notes" restricts the powers of the ED, the commission or any other governmental entity to prevent, correct, or curtail activities that result or may result in pollution of the Edwards Aquifer or hydrologically connected surface waters. The holder of any Edwards Aquifer Protection Plan containing "construction notes" is still responsible for compliance with Title 30, TAC, Chapters 213 or any other applicable TCEQ regulation, as well as all conditions of an Edwards Aquifer Protection Plan through all phases of plan implementation. Failure to comply with any condition of the ED's approval, whether or not in contradiction of any "construction notes," is a violation of TCEQ regulations and any violation is subject to administrative rules, orders, and penalties as provided under Title 30, TAC § 213.10 (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. The following listed "construction notes" in no way represent an approved exception by the ED to any part of Title 30 TAC, Chapters 213 and 217, or any other TCEQ applicable regulation.

- A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any regulated activities. This notice must include:
 - the name of the approved project;
 - the activity start date; and
 - the contact information of the prime contractor.
- All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
- If any sensitive feature(s) (caves, solution cavity, sink hole, etc.) is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. Construction activities may not be resumed until the TCEQ has reviewed and approved the appropriate protective measures in order to protect any sensitive feature and the Edwards Aquifer from potentially adverse impacts to water quality.
- No temporary or permanent hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
- Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features, etc.
- Sediment must be removed from the sediment traps or sedimentation basins not later than

TCEQ-0592 (Rev. July 15, 2015)

Page 1 of 2

when it occupies 50% of the basin's design capacity.


- Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
- All spoils (excavated material) generated from the project site must be stored on-site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the other site.
- If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.
- The following records shall be maintained and made available to the TCEQ upon request:
 - the dates when major grading activities occur;
 - the dates when construction activities temporarily or permanently cease on a portion of the site; and
 - the dates when stabilization measures are initiated.
- The holder of any approved Edwards Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
 - any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
 - any change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
 - any development of land previously identified as undeveloped in the original water pollution abatement plan.

Austin Regional Office 12100 Park 35 Circle, Building A Austin, Texas 78753-1808 Phone (512) 339-2929 Fax (512) 339-3795	San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329
--	---

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.


TCEQ-0592 (Rev. July 15, 2015)

Page 2 of 2



04/21/2023
PROJECT NO.: 069304941
Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10110 W. BRIDLE TRAIL, SUITE 400
SAN ANTONIO, TX 78250
PHONE: 210-544-1808 FAX: 210-544-1869
WWW.KIMLEY-HORN.COM
TYPE: FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
TCEQ GENERAL NOTES

SHEET NUMBER:
C004

QUIKTRIP #4160 SHORT FORM FINAL PLAT

A 1.86 ACRE TRACT OF LAND LOCATED IN THE GRADING PLAT SURVEY ABSTRACT 8, WILLAMSON COUNTY, TEXAS AND BEING A PORTION OF A CALLED 1801 ACRES TRACT OF LAND AS SHOWN AND CONVEYED BY RECORD IN DOCUMENT NO. 222208 OF THE OFFICIAL PUBLIC RECORDS OF WILLAMSON COUNTY, TEXAS

PROJECT INFORMATION

PROPERTY OWNER:
OF SOUTH LLC
2027 SAM BASS RD., SUITE 100
ROUND ROCK, TX 78681


DEVELOPER:
ROBERT CORTELLI
OF SOUTH LLC
2027 SAM BASS ROAD, SUITE 100
ROUND ROCK, TX 78681

ENGINEER (DEVELOPER'S AGENT):
RACHEL M. ROBERTS, P.E.
KIMLEY HORN AND ASSOCIATES, INC.
10701 RESEARCH TOWER #100
SAN ANTONIO, TX 78248
210-544-1888

SURVEYOR:
WILEY TRUSSLER, P.L.L.C.
MATTAN HOOVER ENGINEERING & SURVEYING
3 SPANCRACK RD., STE 300
ROCKFORD, TX 76087

THESE PLANS WERE FILED ON 07/09/2022.

VICINITY MAP



GRAPHIC SCALE IN MILES
1" = 1.0000'

SHEET INDEX


SHEET	DESCRIPTION
1	COVER SHEET
2	SHORT FORM FINAL PLAT
3	SIGNATURES & PLAT NOTES

LOT SUMMARY

TOTAL NUMBER OF LOTS: 1
TOTAL LOT AREA: 1.86
PROPOSED USE: RETAIL

STREET FRONTAGE

WEST STATE HIGHWAY 29 351 LF
KAUFFMAN LOOP 227 LF



10701 RESEARCH TOWER #100
SAN ANTONIO, TX 78248 TEL: 210-544-1888
SUITE 100 SAN ANTONIO, TX 78248 FAX: 210-544-8989
WWW.KHORN.COM
1" = 1.0000' 1 OF 3

QUIKTRIP #4160 SHORT FORM FINAL PLAT

A 1.86 ACRE TRACT OF LAND LOCATED IN THE GRADING PLAT SURVEY ABSTRACT 8, WILLAMSON COUNTY, TEXAS AND BEING A PORTION OF A CALLED 1801 ACRES TRACT OF LAND AS SHOWN AND CONVEYED BY RECORD IN DOCUMENT NO. 222208 OF THE OFFICIAL PUBLIC RECORDS OF WILLAMSON COUNTY, TEXAS

LEGEND

B.M. #1
1" x 1" SET ON TOP OF CONCRETE BENCH MARK 4' x 4' x 3" FROM THE WESTERN CORNER OF SUBJECT TRACT.
ELEVATION: 888.9'

BENCHMARK

B.M. #2
1" x 1" SET ON TOP OF POWER POLE BENCHMARK OF 18" x 18" x 3" FROM THE NORTHEAST CORNER OF SUBJECT TRACT.
ELEVATION: 888.9'


BEARINGS BASED ON THE TEXAS COORDINATE SYSTEM (TICS) ZONE 18, ALL USE OF ANGLE MEASUREMENTS SHALL BE TO THE NEAREST TENTH OF A DEGREE.


SURVEY TIES ADJACENT INTERSECTING

B.M. #1
1" x 1" SET ON TOP OF CONCRETE BENCH MARK 4' x 4' x 3" FROM THE WESTERN CORNER OF SUBJECT TRACT.
ELEVATION: 888.9'

B.M. #2
1" x 1" SET ON TOP OF POWER POLE BENCHMARK OF 18" x 18" x 3" FROM THE NORTHEAST CORNER OF SUBJECT TRACT.
ELEVATION: 888.9'

GRAPHIC SCALE IN FEET
1" = 100'





10701 RESEARCH TOWER #100
SAN ANTONIO, TX 78248 TEL: 210-544-1888
SUITE 100 SAN ANTONIO, TX 78248 FAX: 210-544-8989
WWW.KHORN.COM
1" = 1.0000' 2 OF 3

QUIKTRIP #4160 SHORT FORM FINAL PLAT

A 1.86 ACRE TRACT OF LAND LOCATED IN THE GRADING PLAT SURVEY ABSTRACT 8, WILLAMSON COUNTY, TEXAS AND BEING A PORTION OF A CALLED 1801 ACRES TRACT OF LAND AS SHOWN AND CONVEYED BY RECORD IN DOCUMENT NO. 222208 OF THE OFFICIAL PUBLIC RECORDS OF WILLAMSON COUNTY, TEXAS

GENERAL PLAT NOTES

1. THE SUBDIVISION SHALL CONFORM WITH THE EXISTING JURISDICTION OF THE CITY OF LEANDER, TEXAS.

2. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO THE CITY OF LEANDER WATER DISTRIBUTION AND CITY OF LEANDER WASTEWATER COLLECTION SYSTEMS.

3. NO UNDESIRABLE STRUCTURE, CONSTRUCTION OR OTHER STRUCTURE NOT PERMITTED BY THE LEANDER WATER DEPARTMENT SHALL BE CONSTRUCTED OR EXIST ON ANY LOT IN THIS SUBDIVISION WITHOUT THE APPROVAL OF THE CITY OF LEANDER WATER DEPARTMENT.

4. ALL UTILITIES SHALL BE DEEPER THAN ANY EXISTING UTILITIES THAT ARE TO REMAIN AND SHALL BE DEEPER THAN ANY EXISTING UTILITIES THAT ARE TO BE REMOVED.

5. ALL EASEMENTS OR RIGHTS OF WAY SHALL BE MAINTAINED BY THE PROPERTY OWNER AND SHALL BE IN ACCORDANCE WITH THE TERMS OF THE EASEMENT OR RIGHT OF WAY.

6. ALL UTILITIES SHALL BE DEEPER THAN ANY EXISTING UTILITIES THAT ARE TO REMAIN AND SHALL BE DEEPER THAN ANY EXISTING UTILITIES THAT ARE TO BE REMOVED.

7. PORTION OF THIS TRACT IS WITHIN A FLOOD HAZARD AREA AS SHOWN ON THE FLOOD HAZARD RATE MAP PANEL ANNEX C FOR LEANDER, TEXAS. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR OBTAINING NECESSARY PERMITS AND APPROVALS FROM THE CITY OF LEANDER FOR DEVELOPMENT IN THIS AREA.

8. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR OBTAINING NECESSARY PERMITS AND APPROVALS FROM THE CITY OF LEANDER FOR DEVELOPMENT IN THIS AREA.

9. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR OBTAINING NECESSARY PERMITS AND APPROVALS FROM THE CITY OF LEANDER FOR DEVELOPMENT IN THIS AREA.

10. THE PROPERTY OWNER SHALL BE RESPONSIBLE FOR OBTAINING NECESSARY PERMITS AND APPROVALS FROM THE CITY OF LEANDER FOR DEVELOPMENT IN THIS AREA.

DONOR'S SIGNATURE BLOCK

STATE OF TEXAS)
COUNTY OF WILLAMSON)
I, ROBERT CORTELLI, being a duly qualified and authorized agent of the above named donor, hereby certify that the above described land is owned by the above named donor and that the donor hereby conveys the same to the above named grantees for the purposes and to the uses herein expressed.

BY: ROBERT CORTELLI DATE: _____

ENGINEER'S CERTIFICATION

STATE OF TEXAS)
COUNTY OF WILLAMSON)
I, RACHEL M. ROBERTS, a duly qualified and authorized engineer under the laws of the State of Texas, do hereby certify that the above described land is owned by the above named donor and that the donor hereby conveys the same to the above named grantees for the purposes and to the uses herein expressed.

BY: RACHEL M. ROBERTS DATE: _____


PLANNING AND ZONING COMMISSION

PRESENT NAME: _____
OFFICE ADDRESS: _____
CITY: _____


WILLAMSON COUNTY RECORDING STATEMENT

STATE OF TEXAS)
COUNTY OF WILLAMSON)
I, WILEY TRUSSLER, being a duly qualified and authorized surveyor under the laws of the State of Texas, do hereby certify that the above described land is owned by the above named donor and that the donor hereby conveys the same to the above named grantees for the purposes and to the uses herein expressed.


BY: WILEY TRUSSLER DATE: _____



10701 RESEARCH TOWER #100
SAN ANTONIO, TX 78248 TEL: 210-544-1888
SUITE 100 SAN ANTONIO, TX 78248 FAX: 210-544-8989
WWW.KHORN.COM
1" = 1.0000' 3 OF 3




PROJECT NO.: 069304941



© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10701 RESEARCH TOWER #100
SAN ANTONIO, TX 78248
PHONE: 210-544-1888 FAX: 210-544-8989
WWW.KHORN.COM
TYPE: FIRM NO. 028

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION

SHEET TITLE:


FINAL PLAT

SHEET NUMBER:

C005

ORIGINAL ISSUE DATE: _____

FILE LOCATION: \\S:\Swa_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-DIMC.dwg IAB NAME: Site USER: Oscar.garcia SAVED: 4/21/2023 10:15 AM PLOTTED: 4/21/2023 10:27 AM



SITE LEGEND

- BOUNDARY LINE
- CONCRETE CURB AND GUTTER
- MOUNTABLE CURB W/RADIUS PROTECTOR
- PARKING SPACE INDICATOR
- AREA LIGHT
- MULTIPLE PRODUCT DISPENSER WITH CANOPY COLUMNS AND BOLLARDS
- TRANSFORMER
- FUEL SYSTEM ACCESS MANWAY

MISCELLANEOUS SITE PLAN NOTES

1. MAXIMUM OF 70% IMPERVIOUS COVER PER LOT. OTHERWISE STORMWATER MANAGEMENT CONTROLS SHALL BE DESIGNED, CONSTRUCTED AND MAINTAINED BY OWNER. IF IMPERVIOUS COVER IS PROPOSED TO EXCEED MAXIMUM PERCENTAGE ALLOWED, CONTACT WILLIAMSON COUNTY FLOODPLAIN ADMINISTRATION TO REVIEW THE STORMWATER MANAGEMENT CONTROLS PROPOSED ON LOT.

SITE DATA TABLE

Site Area	1.89	AC
	82,328.40	SF
Parking Provided	50	
ADA Parking Required	2	
ADA Parking Provided	2	
Impervious Cover	69%	
	56,806.60	SF

SITE LIGHTING FIXTURE TABLE

TYPE	HEIGHT	QUANTITY
	22'	8
	22'	4
	22'	1
	22'	0
BREAK AWAY BASES REQUIRED		0
LOW VOLTAGE POLES		0

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 RICHMOND AVE., SUITE 100
 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 LICENSE NO. 137894
 PROJECT NO.: 069304941

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT
 © COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE:

SHEET TITLE:
 SITE PLAN

SHEET NUMBER:
 C100



SITE LEGEND	
	BOUNDARY LINE
	CONCRETE CURB AND GUTTER
	FIRE LANE
	FIRE TRUCK HOSE LAY
	HAND HOSE LAY
	PROPOSED FIRE HYDRANT

NOTE:
 FIRE LANE SHOWN FOR REFERENCE ONLY.
 NO STRIPING PROPOSED.
 CONTRACTOR TO INSTALL FIRE LANE SIGNAGE PER
 WILLIAMSON COUNTY SPECIFICATIONS AND DETAILS

FILE LOCATION: \\hkr\hkr\SWA_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-FIRE.dwg USER: Olivia.Watts TAB NAME: Site SHEETS: 10/2023 1:48 PM PLOTTED: 4/21/2023 10:27 AM

PROJECT NO.: 069304941

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10110 N. MICHIGAN AVE., SUITE 400
 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888 FAX: 210-541-8999
 WWW.KIMLEY-HORN.COM TXBE FIRM NO. 208

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS


© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION



SHEET TITLE:
FIRE PROTECTION PLAN

SHEET NUMBER:
C101



STATE HIGHWAY 29
 VARIABLE WIDTH R.O.W.
 TxDOT AUS033701002 SH29 0458
 PAGES 1-4

FILE LOCATION: \\SVA-Civil\HW29\Cad\UT\Plan Sheets\C-GRA\dwg TAB NAME: Grading USR: Rchiva\Watts SAVED: 4/13/2023 3:44 PM PLOTTED: 4/21/2023 10:27 AM



GRADING LEGEND

ST	STORM PIPE (≤ 10" NEW)
ST	STORM PIPE (≥ 12" NEW)
ST	STORM PIPE (≥ 12" EXISTING)
FD	FRENCH DRAIN
CD	BACK OF CURB DRAIN
ADA	ADA PATH OF TRAVEL
XXXX	MAJOR CONTOUR (NEW)
XXXX	MINOR CONTOUR (NEW)
XXX	MAJOR CONTOUR (EXISTING)
XXX	MINOR CONTOUR (EXISTING)
---	LIMITS OF DISTURBANCE
TC XXXX.XX	TOP OF CURB ELEVATION (NEW)
G XXXX.XX	GUTTER ELEVATION (NEW)
FG XXXX.XX	FINISHED GRADE ELEVATION (NEW)
FG XXXX.XX	SPOT ELEVATION (EXISTING)
SG	STORM GRATE (NEW)

- MISCELLANEOUS GRADING NOTES**
- GAS CANOPY INSTALLER SHALL INSTALL THE CANOPY COLUMN DRAIN PIPE AND OVERFLOW FITTING. THE STORM WATER INSTALLER SHALL CONNECT THEIR PIPING TO THE GAS INSTALLER'S OVERFLOW FITTING.
 - WHEN PLAN GRADES DEPICT RUNOFF TO BE DIRECTED AWAY FROM THE CURB, USE DRAIN AWAY CURB ALTERNATE. (RE: "CURB DETAIL-BARRIER" PDD09A00X DETAIL)

Kimley-Horn
 RACHEL M. ROBERTS
 137894
 REGISTERED PROFESSIONAL ENGINEER
 PROJECT NO.: 069304941
 DATE: 04/21/2023
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 W. HUNTERS LANE, SUITE 200
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-8888 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT
 © COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.



PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION


ORIGINAL ISSUE DATE:

SHEET TITLE:
 GRADING PLAN

SHEET NUMBER:
 C110



FILE LOCATION: S:\a_civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-Detailed\Grading\Grading.dwg
 USER: RChivis\Watts
 DATE: 3/10/2023 3:55 PM
 PLOTTED: 4/21/2023 10:28 AM



F1 FUEL CANOPY GRADING DETAIL
 1"=10'

GRADING LEGEND

ST	STORM PIPE (≤ 10" NEW)
ST	STORM PIPE (≥ 12" NEW)
ST	STORM PIPE (≥ 12" EXISTING)
FD	FRENCH DRAIN
CD	BACK OF CURB DRAIN
ADA	ADA PATH OF TRAVEL
XXXX	MAJOR CONTOUR (NEW)
XXXX	MINOR CONTOUR (NEW)
XXXX	MAJOR CONTOUR (EXISTING)
XXXX	MINOR CONTOUR (EXISTING)
---	LIMITS OF DISTURBANCE
TC XXXX.XX	TOP OF CURB ELEVATION (NEW)
G XXXX.XX	GUTTER ELEVATION (NEW)
FG XXXX.XX	FINISHED GRADE ELEVATION (NEW)
FG XXXX.XX	SPOT ELEVATION (EXISTING)
SG	STORM GRATE (NEW)

- MISCELLANEOUS GRADING NOTES**
- GAS CANOPY INSTALLER SHALL INSTALL THE CANOPY COLUMN DRAIN PIPE AND OVERFLOW FITTING. THE STORM WATER INSTALLER SHALL CONNECT THEIR PIPING TO THE GAS INSTALLER'S OVERFLOW FITTING.
 - WHEN PLAN GRADES DEPICT RUNOFF TO BE DIRECTED AWAY FROM THE CURB, USE DRAIN AWAY CURB ALTERNATE. (RE: "CURB DETAIL-BARRIER" PDC09A00X DETAIL)

BENCHMARKS


BM-100 SCRIBED "X" ON TOP OF CONCRETE, BEARS N 62°23'07" W 3.26' FROM THE WESTERN MOST NORTHWEST CORNER OF THE SUBJECT TRACT.
 ELEVATION=983.80'

BM-101 COTTON SPINDLE SET IN POWER POLE, BEARS N 70°40'03" E, 299.23' FROM THE NORTHEAST CORNER OF THE SUBJECT TRACT.
 ELEVATION=986.48'
 NOT GRAPHICALLY SHOWN HERON

Rachel M. Roberts
 RACHEL M. ROBERTS
 137894
 REGISTERED PROFESSIONAL ENGINEER
 PROJECT NO.: 069304941
 04/21/2023

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10100 WILSON ROAD, SUITE 100
 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888
 FAX: 210-541-8899
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR


REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE:


SHEET TITLE:
 CANOPY & DETAILED GRADING PLANS

SHEET NUMBER:
C112





STORM SEWER GENERAL NOTES
STORM SEWER INSTALLATION CONSIDERATIONS
 PRIOR TO THE CONSTRUCTION OF, OR CONNECTION TO ANY STORM DRAIN OR ANY OTHER ELEVATION SENSITIVE UTILITY, THE CONTRACTOR SHALL EXCAVATE, VERIFY AND CALCULATE ALL POINTS OF CONNECTIONS AND ALL UTILITY CROSSINGS. THE CONTRACTOR SHALL INFORM THE ENGINEER AND THE OWNER OF ANY CONFLICT OR REQUIRED DEVIATIONS FROM THE PLAN. THE ENGINEER AND OWNER WILL BE HELD HARMLESS IN THE EVENT THE ENGINEER AND OWNER ARE NOT NOTIFIED OF A DESIGN CONFLICT.



PROJECT NO.: 069304941
Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 W. WILLOW CREEK, SUITE 200
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-8888
 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 LICENSE NO. 208

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
STORM SEWER PLAN

SHEET NUMBER:
C120




FILE LOCATION: \\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-STORM.dwg USER: Rachel.Roberts DATE: 4/21/2023 10:37 AM PLOTTED: 4/21/2023 4:46 PM

FILE LOCATION: S:\SMA_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-DMM EX.dwg TAB NAME: PRE-DEVELOPED DRAINAGE MAP USER: rscargano SAVED: 1/27/2023 1:04 PM PLOTTED: 4/21/2023 10:28 AM

TIME OF CONCENTRATION CALCULATIONS					
SHEET FLOW	SHALLOW CONCENTRATED FLOW		SHALLOW CONCENTRATED FLOW	CHANNEL FLOW	
EX-1					
n=	0.150 paved?		no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.003	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	790	L (ft)=	
T ₁₀ =	11.478	T ₁₀ =	16.219	T ₁₀ =	0.000
Total TC = 27.70 minutes					
SHEET FLOW	SHALLOW CONCENTRATED FLOW		SHALLOW CONCENTRATED FLOW	CHANNEL FLOW	
EX-2					
n=	0.150 paved?		no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.021	S (ft/ft)=	L (ft)=
L (ft)=	100	L (ft)=	758	L (ft)=	
T ₁₀ =	11.478	T ₁₀ =	5.389	T ₁₀ =	0.000
Total TC = 16.87 minutes					

EXISTING DRAINAGE AREA CALCULATIONS													
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
EX-1	7.21	0%	98	100%	80	80.0	27.70	13.00	19.30	25.50	33.70	40.70	48.30
EX-2	7.24	0%	98	100%	80	80.0	11.48	19.40	28.70	37.70	49.80	60.10	71.10
HEC-HMS VERSION 4.1 AND CITY OF LEANDER ATLAS 14 VALUES WERE USED FOR THIS CALCULATION													
POA - A							20.50	31.50	42.50	57.60	70.70	85.00	



04/21/2023
PROJECT NO.: 069304941
Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10101 SAN ANTONIO, TX 78216
PHONE: 210-541-8888
FAX: 210-541-8889
WWW.KIMLEY-HORN.COM
TX REG. ENG. NO. 137894

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR


REV	DATE	DESCRIPTION

SHEET TITLE:
PRE-DEVELOPED DRAINAGE MAP

SHEET NUMBER:
C121

ORIGINAL ISSUE DATE:


FILE: LOCATION\K12_S12A_C12.dwg | HWY29\Case\UT\Plan Sheets\C-DM PR.dwg | TAB: NAME:POST-DEVELOPED DRAINAGE MAP | USER:Rochelle.Roberts | SAVED:4/20/2023 6:29 PM | PLOTTED:4/21/2023 1:58 PM



PROPOSED DRAINAGE AREA CALCULATIONS													
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₅ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₅₀ (CFS)	Q ₁₀₀ (CFS)
DA-1*	1.34	100%	98	0%	80	98.0	5.00	7.56	9.56	11.40	13.95	16.12	18.47
DA-2	0.38	33%	98	67%	80	85.9	9.10	1.35	1.86	2.35	3.01	3.58	4.18
DA-3	0.76	65%	98	35%	80	91.7	12.34	0.29	0.38	0.46	0.58	0.68	0.78
DA-4*	0.08	100%	98	0%	80	98.0	5.00	0.45	0.57	0.68	0.83	0.96	1.10
OFF-1	6.76	0%	98	100%	80	80.0	31.62	11.41	16.91	22.31	29.53	35.71	42.33
OFF-2	5.46	0%	98	100%	80	80.0	23.06	10.83	16.06	21.11	27.90	33.73	39.95
HEC-HMS VERSION 4.1 AND CITY OF LEANDER ATLAS 14 VALUES WERE USED FOR THIS CALCULATION							POA - A	17.86	28.05	38.52	52.59	64.63	77.51
*THESE DRAINAGE AREAS ARE CAPTURED BY THE UNDERGROUND DETENTION SYSTEM													

TIME OF CONCENTRATION CALCULATIONS				
SHEET FLOW	SHALLOW CONCENTRATED FLOW	SHALLOW CONCENTRATED FLOW	CHANNEL FLOW	
DA-1*				
n=	0.015 paved?		paved?	v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	S (ft/ft)=	L (ft)=
L (ft)=	39	L (ft)=		
T ₁₁ =	0.856	T ₁₂ =	0.000	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	5.00 minutes			
DA-2				
n=	0.240 paved?	yes paved?		v(fps)=
S (ft/ft)=	0.045	S (ft/ft)=	0.01	S (ft/ft)=
L (ft)=	97	L (ft)=	20	L (ft)=
T ₁₁ =	8.939	T ₁₂ =	0.164	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	9.10 minutes			
DA-3				
n=	0.240 paved?	no paved?		v(fps)=
S (ft/ft)=	0.033	S (ft/ft)=	0	S (ft/ft)=
L (ft)=	123	L (ft)=	0	L (ft)=
T ₁₁ =	12.237	T ₁₂ =	0.000	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	12.34 minutes			
DA-4*				
n=	0.015 paved?		paved?	v(fps)=
S (ft/ft)=	0.032	S (ft/ft)=		S (ft/ft)=
L (ft)=	77	L (ft)=		L (ft)=
T ₁₁ =	0.921	T ₁₂ =	0.000	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	5.00 minutes			
OFF-1				
n=	0.240 paved?	no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.003	S (ft/ft)=
L (ft)=	100	L (ft)=	790	L (ft)=
T ₁₁ =	16.717	T ₁₂ =	14.899	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	31.62 minutes			
OFF-2				
n=	0.240 paved?	no paved?		v(fps)=
S (ft/ft)=	0.010	S (ft/ft)=	0.021	S (ft/ft)=
L (ft)=	100	L (ft)=	890	L (ft)=
T ₁₁ =	16.717	T ₁₂ =	6.344	T ₁₃ =
T ₁₄ =			0.000	T ₁₅ =
Total TC =	23.06 minutes			

Point of Analysis	Storm Event	Existing Runoff (cfs)	Developed Runoff (cfs)	Is Developed \leq Existing?
A	2	20.50	17.86	YES
	10	42.50	38.52	YES
	25	57.60	52.59	YES
	100	85.00	77.51	YES



Kimley-Horn
 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10100 W. HUNTERS TRAIL, SUITE 200
 SAN ANTONIO, TEXAS 78258
 PHONE: 210-544-1888 FAX: 210-544-1889
 WWW.KIMLEY-HORN.COM
 LICENSE NO. 208

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
 POST-DEVELOPED
 DRAINAGE MAP

SHEET NUMBER:
C122

ORIGINAL ISSUE DATE:



Peak Flow Calculation - Rational					RUNOFF COEFFICIENT (C)				RAINFALL INTENSITY (I)								
DRAINAGE AREA	AREA (ACRES)	Pervious Cover (ACRES)	Impervious Cover (ACRES)	Impervious Cover %	C 2-YEAR	C 10-YEAR	C 25-YEAR	C 100-YEAR	Tc (min)	I 2-YEAR	I 10-YEAR	I 25-YEAR	I 100-YEAR	Q 2-YEAR	Q 10-YEAR	Q 25-YEAR	Q 100-YEAR
DA-1	0.28	0.00	0.28	100%	0.75	0.83	0.88	0.97	5	6.13	9.19	11.30	15.00	1.43	2.14	2.79	4.08
DA-2	0.22	0.00	0.22	98%	0.74	0.82	0.87	0.96	5	6.13	9.19	11.30	15.00	1.11	1.66	2.16	3.17
DA-3	0.22	0.00	0.22	98%	0.74	0.82	0.87	0.96	5	6.13	9.19	11.30	15.00	1.11	1.66	2.17	3.17
DA-4	0.70	0.00	0.70	100%	0.75	0.83	0.88	0.97	5	6.13	9.19	11.30	15.00	3.56	5.34	6.96	10.19
DA-5	3.90	3.90	0.00	0%	0.29	0.35	0.39	0.46	5	6.13	9.19	11.30	15.00	8.37	12.54	17.19	26.91

Formulas:
 Q=CIA
 Q=Peak Factor Runoff
 C=Weighted Runoff Coefficient
 I=Rainfall Intensity
 A=Drainage Area


Hydrologic Runoff Coefficients (Table 2-3 Austin Rational Method Runoff)

	2yr	10yr	25yr	100yr
Impervious C (Concrete)	0.75	0.83	0.88	0.97
Pervious C (Good, Average)	0.29	0.35	0.39	0.46

Curb Inlet Table

Equations: Weir (Unsubmerged) $Q = 3.0h^{1.5}L$ Clogging Factor = 10% (Grate inlets in Sump)


Inlet # or Area #	Q100 (cfs)	Required Q to Pass (w/ 10% clogging factor)	INLET (FT)	Available Weir Length (ft)	Required Min. 'h' (ft.)	Provided 'h' (ft.)	Provided Capacity (cfs)
DA-1	4.08 cfs	4.53 cfs	5' CURB	5'	0.45'	0.50'	4.77 cfs
DA-2	3.17 cfs	3.52 cfs	5' CURB	5'	0.38'	0.50'	4.77 cfs
DA-3	3.17 cfs	3.52 cfs	5' CURB	5'	0.38'	0.50'	4.77 cfs
DA-4	10.19 cfs	11.32 cfs	10' CURB	12'	0.46'	0.53'	12.50 cfs



PROJECT NO.: 069304941

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 7601 W SH 29, GEORGETOWN, TEXAS 75426
 PHONE: 214-341-1888 FAX: 214-341-8989
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
 INLET DRAINAGE AREA MAP

SHEET NUMBER:
C123



FILE LOCATION: S:\SVA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-D\M IN.dwg TAB NAME: INLET DRAINAGE AREA MAP USER: dlv@kimley-horn.com PLOTTED: 4/21/2023 10:29 AM

FILE LOCATION: S:\a_civil\069304941 - QT 4160 Kauffman Loop & HWY29\Ca\UT\Plan Sheets\C-POND.dwg TAB NAME: DETENTION POND PLAN USER: oingwa User: oingwa Date: 04/21/2023 10:29 AM
 SAVED: 3/22/2023 12:56 PM







Table 1 - Atlas 14 DDF Data for Leander (Replaces Table 2-3 in the Austin DCM)

Duration	Depth-Duration-Frequency Table								
	Depth of Precipitation (inches)								
	Average recurrence interval (years)								
	1	2	5	10	25	50	100	200	500
5-min	0.422	0.511	0.646	0.766	0.943	1.09	1.25	1.41	1.64
10-min	0.672	0.814	1.03	1.23	1.51	1.75	2	2.26	2.6
15-min	0.848	1.02	1.29	1.53	1.88	2.17	2.48	2.8	3.25
30-min	1.2	1.44	1.81	2.14	2.62	3.01	3.44	3.89	4.54
60-min	1.55	1.88	2.37	2.82	3.47	4.01	4.59	5.24	6.17
2-hr	1.84	2.3	2.96	3.58	4.51	5.3	6.19	7.19	8.68
3-hr	2	2.54	3.31	4.05	5.18	6.15	7.27	8.55	10.5
6-hr	2.29	2.97	3.93	4.85	6.28	7.52	8.97	10.6	13.2
12-hr	2.65	3.43	4.53	5.6	7.23	8.65	10.3	12.2	15.2
24-hr	3.05	3.92	5.17	6.36	8.16	9.72	11.5	13.6	16.9

Table 2 - Atlas 14 IDF Data for Leander (Replaces Table 2-4 in the Austin DCM)

Duration	Intensity-Duration-Frequency Table								
	Intensity of Precipitation (Inches Per Hour)								
	Average Recurrence Interval (years)								
	1	2	5	10	25	50	100	200	500
5-min	5.06	6.13	7.75	9.19	11.3	13.1	15	17	19.7
10-min	4.03	4.88	6.19	7.35	9.05	10.5	12	13.5	15.6
15-min	3.39	4.1	5.16	6.12	7.51	8.68	9.92	11.2	13
30-min	2.4	2.88	3.62	4.28	5.24	6.03	6.88	7.79	9.07
60-min	1.55	1.88	2.37	2.82	3.47	4.01	4.59	5.24	6.17
2-hr	0.921	1.15	1.48	1.79	2.25	2.65	3.09	3.6	4.34
3-hr	0.665	0.845	1.1	1.35	1.72	2.05	2.42	2.85	3.48
6-hr	0.383	0.495	0.655	0.81	1.05	1.26	1.5	1.78	2.2
12-hr	0.22	0.285	0.376	0.464	0.6	0.718	0.855	1.02	1.26
24-hr	0.127	0.164	0.215	0.265	0.34	0.405	0.48	0.568	0.703



PROVIDED DETENTION POND VOLUME

STAGE STORAGE TABLE PROVIDED BY CONTECH

ELEVATION (FT)	CUMULATIVE VOLUME (CUBIC FT)	CUMULATIVE VOLUME (AC-FT)
979.8	0	0
980.3	506	0.01
980.8	1371	0.03
981.3	2402	0.06
981.8	3506	0.08
982.3	4610	0.11
982.8	5641	0.13
983.3	6506	0.15
983.8	7012	0.16

DRAINAGE GENERAL NOTES

1. HEC-HMS VERSION 4.1 HAS BEEN UTILIZED FOR DETENTION POND SIZING.

POND AND OUTLET CONTROL CALCULATIONS

RETURN PERIOD (YR)	OUTFLOW (CFS)	VOLUME (AC-FT)	MAX WSEL (FT)
2	6.17	0.04	980.97
10	8.37	0.07	981.53
25	9.68	0.09	981.94
100	11.92	0.13	982.78

PROFESSIONAL ENGINEER
 RACHEL M. ROBERTS
 137894
 PROJECT NO.: 069304941
 04/21/2023

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10100 W. SAM HOUSTON BLVD., SUITE 400
 HOUSTON, TEXAS 77066
 PHONE: 281-416-1800 FAX: 281-416-1899
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
 DETENTION POND MAP

SHEET NUMBER:
C124

HYDROLOGIC CALCULATIONS:

TIME OF CONCENTRATION CALCULATIONS			
SHEET FLOW	SHALLOW CONCENTRATED FLOW	SHALLOW CONCENTRATED FLOW	CHANNEL FLOW
n=	0.300 paved?	no paved?	v(fps)=
S (ft/ft)=	0.050 S (ft/ft)=	0.008 S (ft/ft)=	L (ft)=
L (ft)=	300 L (ft)=	115 L (ft)=	L (ft)=
T ₁₂ =	20.000 T ₁₂ =	1.328 T ₁₂ =	0.000 T ₁₂ =
Total TC =	21.33 minutes		


Driveway 1	
Drainage Area	3.04 ac
TC Calculation	21.33 min
Impervious Cover	0.49 ac
Pervious Cover	2.55 ac
Runoff Coefficient (10 yr)	0.43
Intensity (CORR Brushy Creek Table 3)	9.00
10 yr Flow (Q=CIA)	11.69 cfs

HYDRAULIC CALCULATIONS:



TxDOT Driveway Culvert

Invert Elev Dn (ft)	= 983.32
Pipe Length (ft)	= 100.00
Slope (%)	= 0.83
Invert Elev Up (ft)	= 984.15
Rise (in)	= 18.0
Shape	= Circular
Span (in)	= 18.0
No. Barrels	= 1
n-Value	= 0.013
Culvert Type	= Circular Concrete
Culvert Entrance	= Groove end projecting (C)
Coeff. K,M,c,Y,x	= 0.0045, 2, 0.0317, 0.69, 0.2
Embankment	
Top Elevation (ft)	= 986.70
Top Width (ft)	= 35.00
Crest Width (ft)	= 50.00

Calculations	
Q _{min} (cfs)	= 11.69
Q _{max} (cfs)	= 11.69
Tailwater Elev (ft)	= 0.00
Highlighted	
Q _{total} (cfs)	= 11.69
Q _{pipe} (cfs)	= 11.69
G _{overtop} (cfs)	= 0.00
Veloc _{DN} (ft/s)	= 7.18
Veloc _{UP} (ft/s)	= 6.62
HGL Dn (ft)	= 984.62
HGL Up (ft)	= 985.93
Hw Elev (ft)	= 989.97
HwD (ft)	= 1.61
Flow Regime	= Inlet Control




FILE LOCATION: \\S:\A\Civil\Q1\Construction Plans\02-4160\Civil.dwg TAG NAME: TXDOT Driveway Culvert Exhibit USER: Rachel.Roberts SAVED: 4/21/2023 11:28 AM PLOTTED: 4/21/2023 11:30 AM



Kimley»Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 101 E. SAN ANTONIO, TX 78216
 PHONE: 210-441-8888 FAX: 210-541-9899
 TX REG. NO. 003

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




PROTOTYPE: P-110 (05/01/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
 TXDOT DRIVEWAY CULVERT
 DRAINAGE AREA MAP

SHEET NUMBER:
C125


ORIGINAL ISSUE DATE:



PAVING LEGEND

	ISOLATION - DOWEL
	ISOLATION - NO DOWEL
	CONSTRUCTION - TIED
	CONSTRUCTION - DOWEL
	CONSTRUCTION - NO DOWEL
	THICKENED EDGE
	"DRAIN-AWAY CURB" OR "D.A."
	DRAIN AWAY CURB
	CONCRETE PAVING
	ASPHALT PAVING
	REINFORCED PANEL
	RADIUS PROTECTOR
	MOUNTABLE CURB
	SECTION DETAIL
	BLOWUP DETAIL

- ### PAVING GENERAL NOTES
- DURING CONSTRUCTION, CONTRACTION JOINTS SHALL BE REPLACED BY CONSTRUCTION JOINTS AS DETERMINED AND AGREED UPON BY THE GC AND OT CONSTRUCTION MANAGER BASED ON THE PROJECT SCHEDULE FOR CONCRETE PAVING PLACEMENT. CONSTRUCTION JOINTS SHALL BE CONSTRUCTED PER DETAIL XX-XXX.
 - AT THE GC'S PREFERENCE, CURB MAY BE CONSTRUCTED AS SEPARATELY FORMED OR MONOLITHICALLY POURED WITH THE SITE PAVING SECTIONS. THE CONSTRUCTION OF THE CURB SHALL BE CONSISTENT THROUGHOUT THE SITE, WITH THE EXCEPTION OF MONOLITHIC CURB NEAR THE TANK PIT WHEN NOTED ON THE PLANS, AND THE STORE FRONT ISLANDS WHICH MUST HAVE ISOLATION JOINTS. FOR SEPARATELY FORMED CURB, A 3 SIDED FORM IS REQUIRED. FOR MONOLITHIC CURB, A 2 SIDED FORM IS REQUIRED.
 - FOR JOINT LOCATIONS WITHIN ADA LOCATIONS, RE: ADA COMPLIANCE REFERENCE SHEET C113.
 - FOR CONSTRUCTION TOLERANCES OF SEALANT PLACEMENT IN JOINTS, RE: C521-L1.



PROJECT NO.: 069304941
Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10110 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS




© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	D01
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR



REV	DATE	DESCRIPTION

SHEET TITLE:
 ASPHALT PAVING PLAN

SHEET NUMBER:
C130A



FILE LOCATION: S:\Swa_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-Paving.dwg TAB NAME: CONCRETE PAVING PLAN USER: ROLIVIA.WATTS SAVED: 3/22/2023 1:15 PM PLOTTED: 4/21/2023 10:30 AM



PAVING LEGEND

- ISOLATION - DOWEL
- ISOLATION - NO DOWEL
- CONSTRUCTION - TIED
- CONSTRUCTION - DOWEL
- CONTRACTION - NO DOWEL

- ||||| THICKENED EDGE
- ====="DRAIN-AWAY CURB" OR "D.A."====
- DRAIN AWAY CURB
- CONCRETE PAVING
- ASPHALT PAVING
- R ----- REINFORCED PANEL
- RADIUS PROTECTOR
- MOUNTABLE CURB
- SECTION DETAIL
- BLOWUP DETAIL

- ### PAVING GENERAL NOTES
- DURING CONSTRUCTION, CONTRACTION JOINTS SHALL BE REPLACED BY CONSTRUCTION JOINTS AS DETERMINED AND AGREED UPON BY THE GC AND QT CONSTRUCTION MANAGER BASED ON THE PROJECT SCHEDULE FOR CONCRETE PAVING PLACEMENT. CONSTRUCTION JOINTS SHALL BE CONSTRUCTED PER DETAIL XX-XXX.
 - AT THE GC'S PREFERENCE, CURB MAY BE CONSTRUCTED AS SEPARATELY FORMED OR MONOLITHICALLY POURED WITH THE SITE PAVING SECTIONS. THE CONSTRUCTION OF THE CURB SHALL BE CONSISTENT THROUGHOUT THE SITE, WITH THE EXCEPTION OF MONOLITHIC CURB NEAR THE TANK PIT WHEN NOTED ON THE PLANS, AND THE STORE FRONT ISLANDS WHICH MUST HAVE ISOLATION JOINTS. FOR SEPARATELY FORMED CURB, A 3 SIDED FORM IS REQUIRED. FOR MONOLITHIC CURB, A 2 SIDED FORM IS REQUIRED.
 - FOR JOINT LOCATIONS WITHIN ADA LOCATIONS, RE: ADA COMPLIANCE REFERENCE SHEET C113.
 - FOR CONSTRUCTION TOLERANCES OF SEALANT PLACEMENT IN JOINTS, RE: C521-L1.

Rachel M. Roberts

RACHEL M. ROBERTS
137894
REGISTERED PROFESSIONAL ENGINEER

04/21/2023
PROJECT NO.: 069304941

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10101 W. WOODBRIDGE BLVD., SUITE 400
SAN ANTONIO, TX 78216
PHONE: 210-541-8888 FAX: 210-541-8899
WWW.KIMLEY-HORN.COM WTBSE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR



REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE:

SHEET TITLE:
CONCRETE PAVING PLAN

SHEET NUMBER:
C130B


FILE LOCATION: S:\a_civil\06304941 - QT 4160 Kauffman Loop & HWY29\Case\QT\Plan Sheets\C-P\01.dwg TAB NAME: BUILDING PAVING PLAN USER: Rmiller Date: 2/22/2023 1:14 PM PLOTTED: 2/21/2023 10:30 AM



PAVING LEGEND

- ISOLATION - DOWEL
- ISOLATION - NO DOWEL
- CONSTRUCTION - TIED
- CONSTRUCTION - DOWEL
- CONSTRUCTION - NO DOWEL
- THICKENED EDGE
- "DRAIN AWAY CURB" OR "D.A."
- DRAIN AWAY CURB
- CONCRETE PAVING
- ASPHALT PAVING
- REINFORCED PANEL
- RADIUS PROTECTOR
- MOUNTABLE CURB
- SECTION DETAIL
- BLOWUP DETAIL


- PAVING GENERAL NOTES**
- DURING CONSTRUCTION, CONTRACTION JOINTS SHALL BE REPLACED BY CONSTRUCTION JOINTS AS DETERMINED AND AGREED UPON BY THE GC AND QT CONSTRUCTION MANAGER BASED ON THE PROJECT SCHEDULE FOR CONCRETE PAVING PLACEMENT. CONSTRUCTION JOINTS SHALL BE CONSTRUCTED PER DETAIL XX-XXX.
 - AT THE GC'S PREFERENCE, CURB MAY BE CONSTRUCTED AS SEPARATELY FORMED OR MONOLITHICALLY POURED WITH THE SITE PAVING SECTIONS. THE CONSTRUCTION OF THE CURB SHALL BE CONSISTENT THROUGHOUT THE SITE, WITH THE EXCEPTION OF MONOLITHIC CURB NEAR THE TANK PIT WHEN NOTED ON THE PLANS, AND THE STORE FRONT ISLANDS WHICH MUST HAVE ISOLATION JOINTS. FOR SEPARATELY FORMED CURB, A 3 SIDED FORM IS REQUIRED. FOR MONOLITHIC CURB, A 2 SIDED FORM IS REQUIRED.
 - FOR JOINT LOCATIONS WITHIN ADA LOCATIONS, RE: ADA COMPLIANCE REFERENCE SHEET C113.
 - FOR CONSTRUCTION TOLERANCES OF SEALANT PLACEMENT IN JOINTS, RE: C521-1.1.



PROJECT NO.: 069304941

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10110 SAN ANTONIO, TX 78216
PHONE: 210-541-8888 FAX: 210-541-8889
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS




© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR


REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
BUILDING PAVING PLAN

SHEET NUMBER:
C131



FILE LOCATION: \\SNA_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-Erosion-Phase 1 USER: rhu.watts SAVED: 3/10/2023 4:49 PM PLOTTED: 4/21/2023 10:30 AM



ACREAGE SUMMARY	
IMPERVIOUS AREA	±0.00 ACRES
LANDSCAPE AREA	±3.09 ACRES
TOTAL DISTURBED	±3.09 ACRES

OWNERSHIP / CONTRACTOR SUMMARY	
OWNER/DEVELOPER:	QUIKTRIP CORPORATION 742 NW LOOP 410, STE 102 SAN ANTONIO, TEXAS, 78216 TEL: (469) 766-8331
SITE OPERATOR/GENERAL CONTRACTOR:	TBD
SUPERINTENDENT:	TBD

EROSION CONTROL PHASE 1 LEGEND	
---XXX---	MAJOR CONTOUR (EXISTING)
- - - - -	MINOR CONTOUR (EXISTING)
---	SILT FENCE
---	LIMITS OF DISTURBANCE
---	DRIVE ENTRANCE BARRICADE
[Pattern]	INLET PROTECTION
[Pattern]	TEMPORARY STABILIZED CONSTRUCTION ENTRANCE



Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 742 NW LOOP 410, STE 102
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-8888 FAX: 210-541-8899
 WWW.KIMLEY-HORN.COM
 TXBEE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT	
© COPYRIGHT QUIKTRIP CORPORATION 2011 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.	
PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR


REV	DATE	DESCRIPTION

SHEET TITLE:	EROSION CONTROL PLAN - PHASE 1
SHEET NUMBER:	C140



ORIGINAL ISSUE DATE:

FILE LOCATION: \\S:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\C-EROS PH2.dwg USER: chwa.watts SAVED: 3/22/2023 3:25 PM PLOTTED: 4/21/2023 10:31 AM



ACREAGE SUMMARY

IMPERVIOUS AREA	±1.97 ACRES
LANDSCAPE AREA	±1.12 ACRES
TOTAL DISTURBED	±3.09 ACRES

OWNERSHIP / CONTRACTOR SUMMARY

OWNER/DEVELOPER:
 QUIKTRIP CORPORATION
 742 NW LOOP 410, STE 102
 SAN ANTONIO, TEXAS, 78216
 TEL: (469) 766-8331

SITE OPERATOR/GENERAL CONTRACTOR:
 TBD

SUPERINTENDENT:
 TBD

EROSION CONTROL PHASE 1 LEGEND

---	MAJOR CONTOUR (EXISTING)
- - -	MINOR CONTOUR (EXISTING)
XXX	MAJOR CONTOUR (PROPOSED)
xxx	MINOR CONTOUR (PROPOSED)
---	SILT FENCE
---	LIMITS OF DISTURBANCE
---	DRIVE ENTRANCE BARRICADE
[Pattern]	INLET PROTECTION
[Pattern]	TEMPORARY STABILIZED CONSTRUCTION ENTRANCE

Rachel M. Roberts
 RACHEL M. ROBERTS
 137894
 REGISTERED PROFESSIONAL ENGINEER
 PROJECT NO.: 069304941

Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 742 NW LOOP 410, STE 102
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-8888 FAX: 210-541-8899
 WWW.KIMLEY-HORN.COM
 TXBPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION


SHEET TITLE:
EROSION CONTROL PLAN - PHASE 2

SHEET NUMBER:
C141



ORIGINAL ISSUE DATE:

STATE HIGHWAY 29
 VARIABLE WIDTH R.O.W.
 TxDOT AUS033701002 SH29 0458
 PAGES 1-4

FILE LOCATION: \\S:\A_Civil\06304941 - QT 4160 Kauffman Loop & HWY29\Ca\UTV\Plan Sheets\C-UTIL.dwg TBS NAME: Utility USER: chiva.watts SAVED: 3/27/2023 10:51 AM PLOTTED: 4/21/2023 10:31 AM



UTILITY GENERAL NOTES
UTILITY INSTALLATION CONSIDERATIONS
 PRIOR TO THE CONSTRUCTION OF, OR CONNECTION TO ANY STORM DRAIN, SANITARY SEWER, OR ANY OTHER ELEVATION SENSITIVE UTILITY, THE CONTRACTOR SHALL EXCAVATE, VERIFY AND CALCULATE ALL POINTS OF CONNECTIONS AND ALL UTILITY CROSSINGS. THE CONTRACTOR SHALL INFORM THE ENGINEER AND THE OWNER OF ANY CONFLICT OR REQUIRED DEVIATIONS FROM THE PLAN. THE ENGINEER AND OWNER WILL BE HELD HARMLESS IN THE EVENT THE ENGINEER AND OWNER ARE NOT NOTIFIED OF A DESIGN CONFLICT.
 AS POSSIBLE, ALL PROPOSED UTILITIES SHALL BE ROUTED THROUGH PERVIOUS AREAS - SPECIFICALLY AVOIDING ON-SITE PAVED AREAS DESIGNATED FOR PARKING, ACCESS, AND VEHICULAR TRAFFIC FLOW.
 REFER TO THIS SHEET FOR LOCATION, AND SHEETS #### THRU #### FOR TRENCHING, BACKFILL, AND PLACEMENT DETAILS.



Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 W. BRIDLE TRAIL, SUITE 400
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-8888 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)

DIVISION:

VERSION: 001

DESIGNED BY: OHW

DRAWN BY: OHW

REVIEWED BY: RMR

REV	DATE	DESCRIPTION


SHEET TITLE:

UTILITY PLAN


SHEET NUMBER:

C150

ORIGINAL ISSUE DATE:



FILE LOCATION: S:\SWA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-UTIL PROFILE.dwg TAB NAME: UTILITY PROFILE USER: R010160.Watts SAVER: 3/21/2023 5:55 PM PLOTTED: 4/21/2023 10:31 AM



HORIZONTAL SCALE 1" = 40'
VERTICAL SCALE 1" = 4'

HORIZONTAL SCALE 1" = 40'
VERTICAL SCALE 1" = 4'

UTILITY LEGEND (NEW)

- WTR — WATER LINE
- SS — SANITARY SEWER LINE
- UGET — UNDERGROUND ELECTRIC LINE
- UGT — UNDERGROUND TELEPHONE LINE
- ST — STORM PIPE (8" 10")
- ST — STORM PIPE (12")
- XXX — MAJOR CONTOUR
- XXX — MINOR CONTOUR
- — CONCRETE CURB AND GUTTER
- — LIGHT POLE - 6' MIN. CLEAR FROM F/C (TRAVEL CENTER PARKING - 15' MIN. CLEAR)



Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10110 SAN ANTONIO, TX 78216
PHONE: 210-541-8888 FAX: 210-541-8899
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
UTILITY PROFILE

SHEET NUMBER:
C151

FILE LOCATION: \\hkr\swa\swa\csw\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\C-UTIL VERIFICATION.dwg TAB NAME: Utility Verification USER: oiw\wats SAVETIME: 3/9/2023 6:22 PM PLOTTED: 4/21/2023 10:31 AM




- POTHOLE GENERAL NOTES**
1. IN AREAS TO BE EXCAVATED, EXCAVATE TO A DEPTH NECESSARY TO IDENTIFY ALL UTILITIES SHOWN AND/OR LOCATED BY THE UTILITY OWNER OR THE STATE ONE-CALL SYSTEM.
 2. ALL UTILITIES ARE TO BE IDENTIFIED BY UTILITY TYPE, SIZE, MATERIAL, AND DEPTH ON A FIELD STAKE, PLACED AT THE EXACT LOCATE, FOR THE SURVEYOR TO FIELD LOCATE AFTER POTHOLING OPERATIONS. POT-HOLE CONTRACTOR TO ALSO KEEP RECORDS OF LOCATES FOR CROSS CHECK WITH SURVEYOR OBTAINED FIELD DATA.
 3. SURVEYOR TO PROVIDE POTHOLE RESULTS TO THE CIVIL ENGINEER IN AN AUTOCAD FILE WHICH CLEARLY LABELS ALL ITEMS REQUIRED IN ITEM 2 ABOVE.
 4. UTILITIES SHOWN HAVE BEEN FIELD VERIFIED, HOWEVER, CAUTION SHOULD BE USED WHEN EXCAVATING IN CASE OTHER UTILITIES ARE PRESENT.



PROJECT NO.: 069304941

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10101 W. WOODWAY
SAN ANTONIO, TX 78216
PHONE: 210-541-8888
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS




© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
UTILITY VERIFICATION PLAN


SHEET NUMBER:
C152




STATE HIGHWAY 29
VARIABLE WIDTH R.O.W.
TxDOT AUS033701002 SH29 0458
PAGES 1-4

ORIGINAL ISSUE DATE:


FILE LOCATION: K:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS MISC. SITE.dwg TAB NAME: SITE DETAIL SHEET 1 USER: 01/16/2023 5:32 PM PLOTTED: 4/21/2023 10:32 AM




L1	GEN III SIGN PAD DETAIL	L11	NOT USED
NTS	SN: SD015A005	NTS	SN:




F1	WOODEN FENCE - SINGLE SIDED	F6	NOT USED
NTS	SN: SD012A005	NTS	SN:




A1	CLEANOUT SECTION DETAIL	A6	CLEANOUT SECTION DETAIL (ASPHALT)
NTS	SN: SD016B007	NTS	SN: SD016A007




A6	CLEANOUT SECTION DETAIL (ASPHALT)	A11	NOT USED
NTS	SN: SD016A007	NTS	SN:



L11	NOT USED
NTS	SN:



F11	NOT USED
NTS	SN:



A11	NOT USED
NTS	SN:

Rachel M. Roberts

RACHEL M. ROBERTS
137894

REGISTERED PROFESSIONAL ENGINEER

04/21/2023

PROJECT NO.: 069304941

Kimley-Horn

KIMLEY-HORN AND ASSOCIATES, INC.
10110 N. CENTRAL EXPRESSWAY, SUITE 200
DALLAS, TEXAS 75243
PHONE: 214-343-8888 FAX: 214-343-8899
WWW.KIMLEY-HORN.COM
EPA TYPE FIRM NO. 025

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:


SHEET TITLE:
MISCELLANEOUS SITE DETAILS I

SHEET NUMBER:
C500


FILE LOCATION: K:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\OT\Plan Sheets\DETAILS MISC. SITE.dwg TAB NAME: MISCELLANEOUS SITE DETAILS II USER: dlm\dwg DATE: 4/21/2023 10:52 AM




L1 OUTDOOR BACKFLOW PREVENTION ASSEMBLY
NTS SN: SD029A002




F1 PEX DETAIL - WATER METER & BFP @ STREET
NTS SN: SD023A004



A1 LOT SCRUBBER CLEANOUT IN PAVING SECTION A-A
NTS SN: SD018A007




L6 NOT USED
NTS SN:




F11 CONCRETE COLLAR DETAIL
NTS SN: SD017A003



A6 NOT USED
NTS SN:



L11 UNDERGROUND STORAGE TANK (UST) SLURRY CAP DETAIL
NTS SN: SD020A008



F11 CONCRETE COLLAR DETAIL
NTS SN: SD017A003



A11 NOT USED
NTS SN:

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
1010 SAN ANTONIO, TX 78216
PHONE: 210-541-1888 FAX: 210-541-8989
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT
© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION

SHEET TITLE:
MISCELLANEOUS SITE
DETAILS II

SHEET NUMBER:
C501

ORIGINAL ISSUE DATE:

MANHOLE ASSEMBLY WITH LOCK

EST. WT.
COVER: 86 LBS 38kg
RING: 95 LBS 43kg
TOTAL: 181 LBS 82kg

EAST JORDAN IRON WORKS
PRODUCT NO. 35505205 OR APPROVED EQUAL

OPEN AREA: N/A
COVER: GRAY IRON ASTM A48 CL35B
FRAME: GRAY IRON ASTM A48 CL35B

LOAD RATING: **NON-Traffic**

City of Leander, Texas
DETAIL #107-2
STORM SEWER INLET COVER (LOCKING)

Wagner S. White
02/04/14

FIRE HYDRANTS LACKING INTEGRAL STORZ CONNECTOR SHALL BE REJECTED (NO STORZ ADAPTERS ALLOWED)

1. FIRE HYDRANT BRAND AND MODEL SHALL BE APPROVED BY THE LOCAL WATER AUTHORITY...
2. LOCAL WATER AUTHORITY...
3. HYDRANT SHALL BE PAINTED...
4. ALL HYDRANTS SHALL BE EQUIPPED WITH A BREAKAWAY FLANG...
5. AFTER COMPLETION OF FIRE HYDRANT INSTALLATION...
6. ALL HYDRANTS SHALL BE PAINTED...
7. INTERSECTIONS...
8. SET F.A. ON LOT LINE...
9. F.A. SHALL BE NO CLOSER THAN 18 INCHES FROM EXISTING OR PROPOSED SIDEWALK...
10. F.A. LOCATED AT STREET INTERSECTIONS...
11. NO OBSTRUCTIONS...
12. 1.5-INCH STORZ PUMPER NOZZLE SHALL FACE THE FIRE LANE OR TRAVEL WAY...
13. SECTION C102-2 INSULATION...
14. FIRE HYDRANTS MUST BE INSTALLED WITH THE CENTER OF THE FIVE (5) INCH STEEL OPENING AT LEAST 18 INCHES ABOVE FINISHED GRADE...
15. FIRE HYDRANT DESIGN SHALL BE 2"-2 1/2" NET OUTLETS, 1" - 5/8" STORZ CONNECTION WITH A CAP TO INCLUDE A HEX NUT TO FIT A HYDRANT WRENCH...
16. STANDARD FIRE HYDRANT ASSEMBLY INCLUDES ALL COMPONENTS SHOWN HEREIN...
17. WILLIAMSON COUNTY EMERGENCY SERVICE DISTRICT NO. 4
18. STANDARD FIRE HYDRANT ASSEMBLY

CITY OF AUSTIN DEPARTMENT OF PUBLIC WORKS TYPE II DRIVEWAY

STANDARD NO. 4335-2 1 OF 2

2/29/16 ADOPTED

THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.

ALLOWABLE GRADES

DRIVEWAY VOLUME (ADT)	D=GRADE CHANGE	STD.	MAX.
>1500		0%	3%
500-1500		3%	6%
<500		6%	15%

NOTES:
1. ALL TYPE II DRIVEWAYS SHALL HAVE RADIUS ENDS.
2. DRIVEWAY WIDTHS AND RADIUS REQUIREMENTS, ON-TWO-WAY TRAVEL REQUIREMENTS, AND GEOMETRIC LAY-OUT ARE HIGHLY VARIABLE...
3. THE DRIVEWAY EDGE SHALL BE SMOOTHLY TRANSITIONED INTO THE SIDEWALK TIE-IN LOCATION BEGINNING AT THE RADIUS P.C. LINE.
4. "ZERO" CURB AT PT OR SIDEWALK EDGE, WHICHEVER IS ENCOUNTERED FIRST.
5. PLACE AN EXPANSION JOINT DOWN THE CENTER OF DRIVEWAY ALL DRIVEWAYS.
6. IF DIMENSION IS LESS THAN 1.5 METERS (5 FEET), REMOVE CURB AND GUTTER TO EXISTING JOINT AND FOUR MONOLITHICALLY WITH DRIVEWAY.
7. IF THE BASE IS OVER-EXCAVATED WHERE THE CURB RETURN OF A STREET INTERSECTION.
8. TYPE II DRIVEWAYS ARE TO BE LOCATED NO CLOSER TO THE CORNER OF INTERSECTING RIGHT OF WAY THAN 60% OF PARCEL FRONTAGE AT 30 METERS (100 FEET); WHICHEVER IS LESS.
9. DRIVEWAY SHALL NOT BE CONSTRUCTED WITHIN THE CURB RETURN OF A STREET INTERSECTION.
10. WHILE THE PROPERTY OWNER REMAINS RESPONSIBLE FOR GRADE BREAKS WITHIN PRIVATE PROPERTY...
11. USE 12 MM (1/2") ASPHALT BOARD OR OTHER APPROVED MATERIAL FOR CURB AND GUTTER EXPANSION JOINTS...
12. SEE TRANSPORTATION CRITERIA MANUAL, SECTION 5 FOR OTHER DRIVEWAY REQUIREMENTS.
13. THE SIDEWALK REGARDLESS OF ITS LOCATION WITH RESPECT TO THE CURB OR PROPERTY LINE, SHALL BE CONNECTED TO THE DRIVEWAY AT THESE LOCATIONS.
14. WATER METER BOXES AND WASTEWATER CLEAN OUTS ARE PROHIBITED FROM BEING LOCATED IN DRIVEWAYS.

CITY OF AUSTIN DEPARTMENT OF PUBLIC WORKS TYPE II DRIVEWAY

STANDARD NO. 4335-2 2 OF 2

2/29/16 ADOPTED

THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.

ALLOWABLE GRADES

DRIVEWAY VOLUME (ADT)	D=GRADE CHANGE	STD.	MAX.
>1500		0%	3%
500-1500		3%	6%
<500		6%	15%

NOTES:
1. ALL TYPE II DRIVEWAYS SHALL HAVE RADIUS ENDS.
2. DRIVEWAY WIDTHS AND RADIUS REQUIREMENTS, ON-TWO-WAY TRAVEL REQUIREMENTS, AND GEOMETRIC LAY-OUT ARE HIGHLY VARIABLE...
3. THE DRIVEWAY EDGE SHALL BE SMOOTHLY TRANSITIONED INTO THE SIDEWALK TIE-IN LOCATION BEGINNING AT THE RADIUS P.C. LINE.
4. "ZERO" CURB AT PT OR SIDEWALK EDGE, WHICHEVER IS ENCOUNTERED FIRST.
5. PLACE AN EXPANSION JOINT DOWN THE CENTER OF DRIVEWAY ALL DRIVEWAYS.
6. IF DIMENSION IS LESS THAN 1.5 METERS (5 FEET), REMOVE CURB AND GUTTER TO EXISTING JOINT AND FOUR MONOLITHICALLY WITH DRIVEWAY.
7. IF THE BASE IS OVER-EXCAVATED WHERE THE CURB RETURN OF A STREET INTERSECTION.
8. TYPE II DRIVEWAYS ARE TO BE LOCATED NO CLOSER TO THE CORNER OF INTERSECTING RIGHT OF WAY THAN 60% OF PARCEL FRONTAGE AT 30 METERS (100 FEET); WHICHEVER IS LESS.
9. DRIVEWAY SHALL NOT BE CONSTRUCTED WITHIN THE CURB RETURN OF A STREET INTERSECTION.
10. WHILE THE PROPERTY OWNER REMAINS RESPONSIBLE FOR GRADE BREAKS WITHIN PRIVATE PROPERTY...
11. USE 12 MM (1/2") ASPHALT BOARD OR OTHER APPROVED MATERIAL FOR CURB AND GUTTER EXPANSION JOINTS...
12. SEE TRANSPORTATION CRITERIA MANUAL, SECTION 5 FOR OTHER DRIVEWAY REQUIREMENTS.
13. THE SIDEWALK REGARDLESS OF ITS LOCATION WITH RESPECT TO THE CURB OR PROPERTY LINE, SHALL BE CONNECTED TO THE DRIVEWAY AT THESE LOCATIONS.
14. WATER METER BOXES AND WASTEWATER CLEAN OUTS ARE PROHIBITED FROM BEING LOCATED IN DRIVEWAYS.

CROSS PIPE LENGTHS, REQUIRED PIPE SIZES, & RIPRAP QUANTITIES

Nominal Culvert I.D.	CORP Riprap (cu yd)	Single Barrel (cu yd)	Multi-Barrel (cu yd)	Conditions for use of Cross Pipes	Cross Pipe Size
12"	0.6	9"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
15"	0.7	11"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
18"	0.8	13"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
21"	0.9	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
24"	0.9	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
27"	1.0	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
30"	1.1	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
33"	1.2	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
36"	1.3	14"	N/A	2' - 3' - 1"	3" x 5" (15,500' O.D.)
42"	1.5	24"	4'-11"	5'-11"	All Pipe Culverts (14,900' O.D.)
48"	1.7	24"	5'-5"	6'-5"	All Pipe Culverts (14,900' O.D.)
54"	2.0	31"	5'-11"	7'-6"	All Pipe Culverts (15,561' O.D.)
60"	2.2	31"	6'-5"	7'-6"	All Pipe Culverts (15,561' O.D.)
66"	2.4	31"	6'-11"	7'-10"	All Pipe Culverts (15,561' O.D.)
72"	2.7	31"	7'-6"	8'-1"	All Pipe Culverts (15,561' O.D.)

GENERAL NOTES:
1. The proper installation of the first Cross Pipe is of critical importance...
2. The top of the first Cross Pipe must be placed at no more than 8" above the flow line...
3. The first bottom pipe, shall be set as shown in the Pipe Size Table...
4. The third Cross Pipe from the bottom of the Culvert shall always be installed using a bolted connection...
5. The fourth Cross Pipe from the bottom of the Culvert shall be taken to ensure that Riprap concrete does not flow into the Cross Pipe...
6. The fifth Cross Pipe from the bottom of the Culvert shall be taken to ensure that Riprap concrete does not flow into the Cross Pipe...
7. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".
8. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".
9. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".

SAFETY END TREATMENT FOR 12" DIA TO 72" DIA PIPE CULVERTS TYPE II - PARALLEL DRAINAGE

SETP-PD

TABLE OF DIMENSIONS AND REINFORCING STEEL

TABLE OF WINGWALL REINFORCING

WING DIMENSION FORMULAS:

TABLE OF ESTIMATED CULVERT TOWALL QUANTITIES

GENERAL NOTES:
1. The proper installation of the first Cross Pipe is of critical importance...
2. The top of the first Cross Pipe must be placed at no more than 8" above the flow line...
3. The first bottom pipe, shall be set as shown in the Pipe Size Table...
4. The third Cross Pipe from the bottom of the Culvert shall always be installed using a bolted connection...
5. The fourth Cross Pipe from the bottom of the Culvert shall be taken to ensure that Riprap concrete does not flow into the Cross Pipe...
6. The fifth Cross Pipe from the bottom of the Culvert shall be taken to ensure that Riprap concrete does not flow into the Cross Pipe...
7. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".
8. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".
9. Riprap placed beyond the limits shown will be paid on concrete Riprap in accordance with Item 432, "Riprap".

Kimley-Horn & Associates, Inc.
REGISTERED PROFESSIONAL ENGINEERS
137894
04/21/2023
PROJECT NO. 069304941

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT








© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY PROHIBITED.

PROTOTYPE: P-112 (11/18/22)
DIVISION: DESIGN: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

ORIGINAL ISSUE DATE:

SHEET TITLE: MISCELLANEOUS SITE DETAILS III
SHEET NUMBER: C502

FILE LOCATION: \\Swa_Civil\HW29\Cad\UT\Plan Sheets\C - Erosion Control Details.dwg USER: rina.watts DATE: 08/21/15



Kimley-Horn
 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 137894
 78216
 SAN ANTONIO, TEXAS 78216
 PHONE: 210-541-1888 FAX: 210-541-8989
 WWW.KIMLEY-HORN.COM
 LICENSE NO. 0000000000

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS


QT
 © COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

SHEET TITLE:
 EROSION CONTROL DETAILS

SHEET NUMBER:
C503

ORIGINAL ISSUE DATE:



L1 DOUBLE STALL ADA PARKING STRIPING DETAIL


NTS

SN: AD001A009

L6 NOT USED

NTS


SN:



L11 ADA SIGN IN BOLLARD

NTS


SN: AD003C0011




F1 AIR SERVICE INSTALL PLAN (LEFT HAND INSTALL)

NTS

SN: AD004B015




1. REQUIRED FOR ALL PRIVATE PROPERTY INTERIOR LOCATIONS.
2. RE: PROJECT SPECS FOR PRODUCT COLOR & TYPE.
3. PRODUCT SHOULD BE APPLIED PER MANUFACTURER'S SPECIFICATIONS.
4. PREPARATION OF THE SURFACE SHALL CONSIST OF A MINIMUM OF TWO APPLICATIONS OF POWER WASHING.
5. TWO APPLICATIONS OF PRODUCT SHALL BE ROLLED ON.



F11 RAMP - CURB TRANSITION PAINTING DETAIL

NTS


SN: AD015A002



A1 ADA ACCESS RAMP AT DRIVE

NTS

SN: AD006A013



A11 NOT USED

NTS

SN:



PROJECT NO.: 069304941

Kimley-Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 10110 SAN ANTONIO, TX 78203
PHONE: 710-541-8800 FAX: 710-541-8809
WWW.KIMLEY-HORN.COM

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION


SHEET TITLE:
ADA DETAILS I

SHEET NUMBER:
C510

ORIGINAL ISSUE DATE:

FILE LOCATION: \\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS ADA.dwg TAB NAME: ADA DETAILS 1 USER: rmc\watts SAVED: 2/15/2023 5:03 PM PLOTTED: 4/21/2023 10:33 AM

FILE LOCATION: K:\SNA_Civil\069304941 - 01 4160 Kauffman Loop & HWY29\Cad\OT\Plan Sheets\DETAILS ADA.dwg TAB NAME: ADA DETAILS II USER: rhdw\wats SAV: 2/15/2023 5:03 PM PLOTTED: 4/21/2023 10:33 AM



L1	CURB RAMP ADJACENT TO PUBLIC STREET CURB & GUTTER	L6	SIDEWALK TRANSITION WEDGE DETAIL	L11	NOT USED
NTS	SN: AD010A007	NTS	SN: AD013A002	NTS	SN:

F1	PARKING LOT CURB RAMP @ ADA CROSSING	F11	ISLAND - BARRIER CURB PAINTING DETAIL (NON-LANDSCAPED)
NTS	SN: AD012A007	NTS	SN: AD016A001

A1	NOT USED	A6	NOT USED	A11	NOT USED
NTS	SN:	NTS	SN:	NTS	SN:

Kimley-Horn
 RACHEL M. ROBERTS
 137894
 REGISTERED PROFESSIONAL ENGINEER
 04/21/2023
 PROJECT NO.: 069304941
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 KIMLEY-HORN DRIVE, SUITE 400
 SAN ANTONIO, TX 78216
 PHONE: 210-544-8800 FAX: 210-544-8899
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT
 © COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE:	P-112 (11/18/22)
DIVISION:	
VERSION:	001
DESIGNED BY:	OHW
DRAWN BY:	OHW
REVIEWED BY:	RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
 ADA DETAILS II


SHEET NUMBER:
 C511

FILE LOCATION: \\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS PAVING.DWG TAB NAME: Paving Detail Sheet 1 USER: rchivw@watts SAVED: 3/10/2023 6:01 PM PLOTTED: 4/21/2023 10:33 AM



L1 PAVING SECTION THROUGH SITE AT BUILDING


SN: PD001C015



CONCRETE PAVING SECTION 2 - STORE SIDE

NTS


SN: PD055B005



F1 UST/RUT PROTECTOR SECTION

NTS


SN: PD060A006



F6 SIDEWALK SECTION ABUTTING CURB & GUTTER

NTS


SN: PD002A010



F11 CURB DETAIL - TEMPORARY

NTS


SN: PD011A006



A1 PAVING JOINT - TIED

NTS


SN: PD004A009



A6 PAVING JOINT - ISOLATION

NTS

SN: PD005A011



A11 PAVING JOINT - CONSTRUCTION (PVR SITE)

NTS

SN: PD006B010

Kimley-Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 10101 KIMLEY-HORN DRIVE, SAN ANTONIO, TX 78216
PHONE: 710-541-8888 FAX: 710-541-8899
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

PROJECT NO.: 069304941

04/21/2023

RACHEL M. ROBERTS
REGISTERED PROFESSIONAL ENGINEER
137894

QuikTrip No. 4160

7601 W SH 29
GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:


SHEET TITLE:
PAVING DETAILS I

SHEET NUMBER:
C520


FILE LOCATION: \\SNA_Civil\069304941 - 01 4160 Kauffman Loop & HWY29\Cad\OT\Plan Sheets\DETAILS PAVING.DWG TAB NAME: Paving Detail Sheet 2 USER: rhwa\watts SAVED: 3/10/2023 6:01 PM PLOTTED: 4/21/2023 10:33 AM




L1 PAVING JOINT - CONTRACTION (PVR SITE)
NTS SN: PD007B013




L6 THICKENED EDGE SECTION
NTS SN: PD008A008




L11 CURB DETAIL - BARRIER (PVR SITE)
NTS SN: PD009D016




F1 CURB DETAIL - ROLLOVER / MOUNTABLE
NTS SN: PD010A014




F6 RADIUS PROTECTOR PLAN
NTS SN: PD016A006




F11 STANDARD RADIUS PROTECTOR SECTION
NTS SN: PD017A013



A1 TYPICAL JOINT LAYOUT - AT RADIUS AND ANGLES
NTS SN: PD019A007



A6 GAS ISLAND JOINTING - (G3S DS STEEL)
NTS SN: PD021A004



A11 TYPICAL MANHOLE / FUEL MANWAY JOINT LAYOUTS
NTS SN: PD021A003

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10110 KIMLEY-HORN BLVD.
SAN ANTONIO, TX 78216
PHONE: 710-541-8800 FAX: 710-541-8809
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT
© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR


REV	DATE	DESCRIPTION

SHEET TITLE:
PAVING DETAILS II


SHEET NUMBER:
C521

ORIGINAL ISSUE DATE:


FILE LOCATION: K:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS PAVING.DWG TAB NAME: Paving Detail Sheet 3 USER: rchris.watts SAVED: 3/10/2023 6:01 PM PLOTTED: 4/21/2023 10:33 AM




L1 FIBERLITE LID DETAIL
NTS SN: PD071A003




L6 GREASE TRAP PAVEMENT DETAIL
NTS SN: PD076A003




L11 ISLAND SECTION B-B-PAVED ISLAND
NTS SN: PD024A009




F1 DISPENSER ISLAND FORM - CONCRETE FILL & JOINTING DETAIL
NTS SN: PD047A003




F6 ASPHALT TO CONCRETE TRANSITION PAVING SECTION
NTS SN: PD073A004




F11 TYPE A ISLAND JOINT DETAIL
NTS SN: PD035A014



A1 DOWELED EXPANSION JOINTS AT BOLLARD PAVEMENT SECTION
NTS SN: PD036A004



A6 G3S BUILDING SIDEWALK TRANSITION DETAIL
NTS SN: PD069A004



SECTION A-A

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10115 SAN ANTONIO, TX 78203
PHONE: 710-541-8800 FAX: 710-541-8899
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT
© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR



REV	DATE	DESCRIPTION

SHEET TITLE:
PAVING DETAILS III

SHEET NUMBER:
C522

ORIGINAL ISSUE DATE:

FILE LOCATION: \\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS PAVING.DWG TAB NAME: Paving Detail Sheet 4 USER: rhwa\watts SAVED: 3/10/2023 6:01 PM PLOTTED: 4/21/2023 10:33 AM



Kimley-Horn
 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 SAN ANTONIO, TX 78201-4001
 PHONE: 710-541-8800 FAX: 710-541-8809
 WWW.KIMLEY-HORN.COM
 TYPE FIRM NO. 028

PROJECT NO.: 069304941

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS

QT

© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR


REV	DATE	DESCRIPTION

ORIGINAL ISSUE DATE:

SHEET TITLE:
 PAVING DETAILS IV

SHEET NUMBER:
C523

FILE LOCATION: K:\SNA_Civil\069304941 - QT 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS PAVING.DWG TAB NAME: Paving Detail Sheet 5 USER: Olivia.Watts SAVED: 3/10/2023 6:01 PM PLOTTED: 4/21/2023 10:33 AM



L1	NOT USED	L6	DELINEATED CROSSWALK JOINTING SECTION DETAIL	L11	G3S SIDEWALK REINFORCING AT SIDE DOORS
NTS	SN:	NTS	SN: PD050A002	NTS	SN: RD078A003
F1	NOT USED	F6	NOT USED	F11	NOT USED
NTS	SN:	NTS	SN:	NTS	SN:
A1	NOT USED	A6	NOT USED	A11	NOT USED
NTS	SN:	NTS	SN:	NTS	SN:

PROJECT NO.: 069304941

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10115 SAN ANTONIO, TX 78248
PHONE: 710-541-8868 FAX: 710-541-8869
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:


SHEET TITLE:
PAVING DETAILS V

SHEET NUMBER:
C524


FILE LOCATION: \\S:\A\Civil\066304941 - 01 4160 Kauffman Loop & HWY29\Cad\QT\Plan Sheets\DETAILS TRENCHING.dwg TAB NAME: Trenching Detail Sheet 1 USER: Olivia.Watts SWED/2/15/2023 5:05 PM PLOTTED: 4/21/2023 10:33 AM




L1 NOT USED
NTS SN: TD005A007




F1 BUILDING OR CANOPY DRAINAGE TRENCH SECTION (NON PAVED)
NTS SN: TD007A002




A1 PRIMARY ELECTRICAL & TELEPHONE CONDUIT TRENCH SECTION (NON PAVED)
NTS SN: TD011A003




L6 ON-SITE WATER LINE TRENCH SECTION (PAVED)
NTS SN: TD005A007




F6 ON-SITE WATER LINE TRENCH SECTION (NON PAVED)
NTS SN: TD008A003




A6 1" Ø OR SMALLER ELECTRICAL CONDUIT TRENCH SECTION (PAVED)
NTS SN: TD012A005



L11 BUILDING OR CANOPY DRAINAGE TRENCH SECTION (PAVED)
NTS SN: TD006A005



F11 PRIMARY ELECTRICAL & TELEPHONE CONDUIT TRENCH SECTION (PAVED)
NTS SN: TD010A005



A11 1" Ø OR SMALLER ELECTRICAL CONDUIT TRENCH SECTION (UNPAVED)
NTS SN: TD013A003

Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10101 KIMLEY-HORN DRIVE, SUITE 400
SAN ANTONIO, TX 78216
PHONE: 210-541-8800 FAX: 210-541-8899
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028

QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT
© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.


PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR

REV	DATE	DESCRIPTION


SHEET TITLE:
TRENCHING DETAILS I

SHEET NUMBER:
C530

FILE LOCATION: S:\SNA_Civil\069304941 - 01 4160 Kauffman Loop & HWY29\Cad\UT\Plan Sheets\DETAILS TRENCHING.dwg TAB NAME: Trenching Details Sheet 2 USER: rchwa\watts SAVED: 2/15/2023 5:05 PM PLOTTED: 4/21/2023 10:33 AM




L1 EXCAVATION BENCHING DETAIL
NTS SN: TD014A002




F1 GEOTECH FABRIC IN SUB-SURFACE DRAIN
NTS SN: TD017A003

A1 NOT USED
NTS SN:




L6 TYPICAL IRRIGATION PIPING TRENCH SECTION (PAVED)
NTS SN: TD015A006




F6 12" DIAMETER OR LARGER STORM DRAIN (PAVED)
NTS SN: TD018A001

A6 NOT USED
NTS SN:



L11 TYPICAL IRRIGATION PIPING TRENCH SECTION (NON PAVED)
NTS SN: TD016A002



F11 12" DIAMETER OR LARGER STORM DRAIN (NON PAVED)
NTS SN: TD018B001

A11 NOT USED
NTS SN:

Rachel M. Roberts
REGISTERED PROFESSIONAL ENGINEER
PROJECT NO.: 069304941
Kimley-Horn
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.
10110 SAN ANTONIO, TX 78203
PHONE: 710-541-8868 FAX: 710-541-8869
WWW.KIMLEY-HORN.COM
TYPE FIRM NO. 028


QuikTrip No. 4160
7601 W SH 29
GEORGETOWN, TEXAS

QT
© COPYRIGHT QUIKTRIP CORPORATION 2011
ANY UNAUTHORIZED USE, REPRODUCTION,
PUBLICATION, DISTRIBUTION, OR SALE IN
WHOLE OR IN PART, IS STRICTLY FORBIDDEN.
PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR


REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
TRENCHING DETAILS II
SHEET NUMBER:
C531


FILE LOCATION: \\SVA-Civil\HW29\Cad\UT\Plan Sheets\DETAILS\DRAINAGE.dwg TAB NAME: Drainage Detail Sheet 1 USER: rchiva.watts SAVED: 2/15/2023 5:06 PM PLOTTED: 4/21/2023 10:33 AM





L1	BACKFILL FOR UGD PIPE
NTS	SN: DD026A003





L6	RIP-RAP PLACEMENT DETAIL
NTS	SN: DD023A002



L11	NOT USED
NTS	SN:




A1	CATCH BASIN INLET DETAIL (SINGLE)
NTS	SN: DD001A010



A1	CATCH BASIN INLET DETAIL (SINGLE)
NTS	SN: DD001A010



F11	NOT USED
NTS	SN:



A11	NOT USED
NTS	SN:

PROJECT NO.: 069304941

Kimley-Horn

 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.

 10101 KIMLEY-HORN BLVD.

 SAN ANTONIO, TX 78216

 PHONE: 210-544-8888 FAX: 210-544-8899

 WWW.KIMLEY-HORN.COM

 TYPE FIRM NO. 028

QuikTrip No. 4160

 7601 W SH 29

 GEORGETOWN, TEXAS

© COPYRIGHT QUIKTRIP CORPORATION 2011. ANY UNAUTHORIZED USE, REPRODUCTION, PUBLICATION, DISTRIBUTION, OR SALE IN WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
DIVISION:
VERSION: 001
DESIGNED BY: OHW
DRAWN BY: OHW
REVIEWED BY: RMR


REV	DATE	DESCRIPTION

SHEET TITLE:
DRAINAGE DETAILS



SHEET NUMBER:
C540

ORIGINAL ISSUE DATE:


FILE: LOCATION\hck\Swm_Civil\069304941 - UT - 4160 Kaufman Loop & HWY29\Cad\UT\Plan Sheets\C - Utility Details.dwg TAB: NAME:UTILITY DETAILS 1 - USE: Civil\hck\Swm_Civil\069304941 - UT - 4160 Kaufman Loop & HWY29\Cad\UT\Plan Sheets\C - Utility Details.dwg SAVES: 3/27/2023 5:43 PM PLOTTED: 4/21/2023 10:34 AM




City of Leander, Texas
 DETAIL #101-
 WATER SERVICE CONNECTIONS
 Wayne S. Miller
 10/20/15




CITY OF AUSTIN AUSTIN WATER		TYPICAL GATE VALVE 4" - 16"	
RECORD COPY SIGNED BY KATHI L FLOWERS	05/18/2016 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. 511-AW-01 1 OF 4



CITY OF AUSTIN AUSTIN WATER		TYPICAL GATE VALVE 4" - 16"	
RECORD COPY SIGNED BY KATHI L FLOWERS	05/18/2016 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. 511-AW-01 2 OF 4




CITY OF AUSTIN AUSTIN WATER		TYPICAL GATE VALVE 4" - 16"	
RECORD COPY SIGNED BY KATHI L FLOWERS	05/18/2016 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. 511-AW-01 3 OF 4



PROJECT NO.: 069304941
Kimley-Horn
 © 2023 KIMLEY-HORN AND ASSOCIATES, INC.
 10101 W. BRIDLE TRAIL, SUITE 400
 SAN ANTONIO, TX 78216
 PHONE: 210-541-8888
 FAX: 210-541-8889
 WWW.KIMLEY-HORN.COM
 LICENSE NO. 005

QuikTrip No. 4160
 7601 W SH 29
 GEORGETOWN, TEXAS



© COPYRIGHT QUIKTRIP CORPORATION 2011
 ANY UNAUTHORIZED USE, REPRODUCTION,
 PUBLICATION, DISTRIBUTION, OR SALE IN
 WHOLE OR IN PART, IS STRICTLY FORBIDDEN.

PROTOTYPE: P-112 (11/18/22)
 DIVISION:
 VERSION: 001
 DESIGNED BY: OHW
 DRAWN BY: OHW
 REVIEWED BY: RMR

REV	DATE	DESCRIPTION	ORIGINAL ISSUE DATE:

SHEET TITLE:
 UTILITY DETAILS I

SHEET NUMBER:
C550

Inspection, Maintenance, Repair, and Retrofit Plan

MAINTENANCE

The Jellyfish Unit is a proprietary BMP manufactured by Contech Engineered Solutions and placed in line with the storm drainage system. The upstream facilities of the storm drainage system, including the combo inlets, HDPE pipes, and ADS detention system must be maintained to properly maintain and inspect the Jellyfish unit. The inlets and pipes should be checked regularly for signs of clogging or other defects in the system. The Jellyfish maintenance includes the removal of pollutants such as oil, trash, and debris, the removal of collected sediments, rinsing and re-installing the filters, and the replacement of the filters as needed. The inspection activities include observing for standing water, physical damage to the deck or cartridge lid, and the amount of debris in the Maintenance Access Wall or inlet bay for vault systems.

Jellyfish Maintenance

Requirements Sediment removal for depths reaching 12 inches or greater, or within 3 years of the most recent sediment cleaning, whichever occurs sooner. Floatable trash, debris, and oil removal. Deck cleaned and free from sediment. Filter cartridges rinsed and re-installed as required by the most recent inspection results, or within 12 months of the most recent filter rinsing, whichever occurs sooner. Replace tentacles if rinsing does not restore adequate hydraulic capacity, remove accumulated sediment, or if damaged or missing. It is recommended that tentacles should remain in service no longer than 5 years before replacement. Damaged or missing cartridge deck components must be repaired or replaced as indicated by results of the most recent inspection. The unit must be cleaned out and filter cartridges inspected immediately after an upstream oil, fuel, or chemical spill. Filter cartridge tentacles should be replaced if damaged or compromised by the spill.

Procedure Provide traffic control measures as necessary. Open all covers and hatches. Use ventilation equipment as required. To access the cartridge deck for filter cartridge service, descend into the structure and step directly onto the deck. Caution: Do not step onto the maintenance access wall (MAW) or backwash pool weir, as damage may result. Note that the cartridge deck may be slippery. Maximum weight of maintenance crew and equipment on the cartridge deck not to exceed 450 lbs.

Filter Cartridge Removal Remove a cartridge lid. Remove cartridges from the deck using the lifting loops in the cartridge head plate. Rope should be used. Replace and secure the cartridge lid on the exposed empty receptacle as a safety precaution. Do not expose more than one empty cartridge receptacle at a time.

Filter Cartridge Rinsing Remove all tentacles from the cartridge head plate. Position tentacles in a container (or over the MAW), with the threaded connector (open end) facing down, so rinse water is flushed through the membrane and captured in the container. Using a low-pressure garden hose sprayer, direct water spray onto the tentacle membrane, sweeping from top to bottom along the length of the tentacle. Rinse until all sediment is removed from the membrane.

Sediment and Floatables Extraction Perform vacuum cleaning of the Jellyfish Filter only after filter cartridges have been removed from the system. Access the lower chamber for vacuum cleaning only through the maintenance access wall (MAW) opening. Do not lower the vacuum wand through a cartridge receptacle, as damage to the receptacle will result. Vacuum floatable trash, debris, and oil,

from the MAW opening or inlet bay. Alternatively, floatable solids may be removed by a net or skimmer. Pressure wash cartridge deck and receptacles to remove all sediment and debris. Sediment should be rinsed into the sump area. Remove water from the sump area. Vacuum or pump equipment should only be introduced through the MAW or inlet bay. Remove the sediment from the bottom of the unit through the MAW or inlet bay opening.

Chemical Spills Caution: If a chemical spill has been captured, do not attempt maintenance. Immediately contact the local hazard response agency and contact Contech.

Material Disposal The accumulated sediment must be handled and disposed of in accordance with regulatory protocols. Sediments and water must be disposed of in accordance with all applicable waste disposal regulations. When scheduling maintenance, consideration must be made for the disposal of solid and liquid wastes. This requires coordination with a local landfill for solid waste disposal. For liquid waste disposal a number of options are available including a municipal vacuum truck decant facility, local wastewater treatment plant or on-site treatment and discharge.

Contech Storage System Maintenance

Underground detention vaults are similar in function as open detention basins. They have moderate to high maintenance requirements, depending on the extent to which future maintenance needs are anticipated during the design stage. Responsibilities for both routine and non-routine maintenance tasks need to be clearly understood and enforced. If regular maintenance and inspections are not undertaken, the basin will not achieve its intended purposes.

Inspections. Storage vaults should be inspected at least twice a year (once during or immediately following wet weather) to evaluate facility operation. When possible, inspections should be conducted during wet weather to determine if the vault is meeting the target detention times. In particular, the vault's flow control device should be regularly inspected for evidence of clogging, or conversely, for too rapid a release. If the design drawdown times are exceeded by more than 24 hours, then repairs should be scheduled immediately.

Debris and Litter Removal. Debris and litter will accumulate near the vault's flow control device. Particular attention should be paid to floating debris that can eventually clog the control device or riser or orifice.

Structural Repairs and Replacement. With each inspection, any damage to the structural elements of the system (pipes, concrete drainage structures, etc.) should be identified and repaired immediately.

Nuisance Control. Standing water within the bottom of the basin can create nuisance conditions for nearby residents. Odors, mosquitoes, and litter are all occasionally perceived to be problems. Most of these problems are generally a sign that regular inspections and maintenance are not being performed.

Sediment Removal. When properly designed, storage vaults will accumulate quantities of sediment over time. Sediment accumulation is a serious maintenance concern in vaults for several reasons. First, the sediment gradually reduces available stormwater management storage capacity within the vault. Second sediment tends to accumulate around the control device. Sediment deposition increases the risk that the orifice will become clogged, and gradually reduces storage capacity reserved for pollutant removal. Sediment can also be re-suspended if allowed to accumulate over time. For these reasons, accumulated sediment needs to be removed from the lower stage when sediment buildup fills 20% of the volume of the vault or at least every 10 years.

INSPECTION

Inspection Timing A minimum of quarterly inspections during the first year of operation to assess the sediment and floatable pollutant accumulation, and to ensure proper functioning of the system. Minimum frequency should be once per year after first year. Inspection is recommended after each major storm event. Inspection is required immediately after an upstream oil, fuel or other chemical spill.

Procedure Provide traffic control measures as necessary. Inspect the MAW or inlet bay for floatable pollutants such as trash, debris, and oil sheen. Measure oil and sediment depth in several locations, by lowering a sediment probe until contact is made with the floor of the structure. Record sediment depth, and presences of any oil layers. Inspect cartridge lids. Missing or damaged cartridge lids to be replaced. Inspect the MAW (where appropriate), cartridge deck and receptacles, and backwash pool weir, for damaged or broken components.

Dry weather inspections Inspect the cartridge deck for standing water, and/or sediment on the deck. There is no standing water under normal operating conditions. Standing water inside the backwash pool, but not outside the backwash pool, indicates that the filter cartridges need to be rinsed. Standing water outside the backwash pool is not anticipated and may indicate a backwater condition caused by high water elevation in the receiving water body, or possibly a blockage in downstream infrastructure. Any appreciable sediment ($\geq 1/16"$) accumulated on the deck surface should be removed.

Wet weather inspections Observe the rate and movement of water in the unit. Note the depth of water above deck elevation within the MAW or inlet bay. Less than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges (i.e. cartridges located outside the backwash pool). Greater than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges and each of the hi-flow cartridges (i.e. cartridges located inside the backwash pool), and water should be overflowing the backwash pool weir. 18 inches or greater and relatively little flow is exiting the cartridge lids and outlet pipe, this condition indicates that the filter cartridges need to be rinsed.

REPAIR, REPLACEMENTS & RETROFITS

Filter Cartridge Reinstallation and Replacement Cartridges should be installed after the deck has been cleaned. It is important that the receptacle surfaces be free from grit and debris. Remove cartridge lid from deck and carefully lower the filter cartridge into the receptacle until head plate gasket is seated squarely in receptacle. Replace the cartridge lid and check to see that both male threads are properly seated before rotating approximately 1/3 of a full rotation until firmly seated. If rinsing is ineffective in removing sediment from the tentacles, or if tentacles are damaged, provisions must be made to replace the spent or damaged tentacles with new tentacles. Contact Contech to order replacement tentacles.

In the event that the Jellyfish vault or other unit components need to be repaired or retrofit, the responsible party shall reach out to Contech Engineered Solutions to determine the best course of action.

RECORDKEEPING PROCEDURES

The attached Inspection and Maintenance Log should be used to monitor the status of the Jellyfish.

Responsible Party: Kyla Rudd, Environmental Project Manager

Kyla Rudd
Signature of Responsible Party

3/21/2023
Date

Design Engineer: Rachel Roberts, P.E.

Rachel Roberts
Signature of Design Engineer

03/21/2023
Date

(this space is intentionally left blank)

SIGNATURE PAGE:

Kyla Rudd
Applicant's Signature

3/21/2023
Date

THE STATE OF Oklahoma §
County of Tulsa §

BEFORE ME, the undersigned authority, on this day personally appeared Kyla Rudd known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 21 day of March, 2023.



Paige Hefflin
NOTARY PUBLIC

Paige Hefflin
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 11/06/24

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: QT 4160

Regulated Entity Location: Georgetown, Texas

Name of Customer: QT South LLC

Contact Person: Kyla Rudd

Phone: 918-615-7233

Customer Reference Number (if issued):CN _____

Regulated Entity Reference Number (if issued):RN _____

Austin Regional Office (3373)

Hays

Travis

Williamson

San Antonio Regional Office (3362)

Bexar

Medina

Uvalde

Comal

Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

Austin Regional Office

San Antonio Regional Office

Mailed to: TCEQ - Cashier

Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

Site Location (Check All That Apply):

Recharge Zone

Contributing Zone

Transition Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	1.89 Acres	\$ 4,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	5 Tanks	\$ 3,250
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: 

Date: 04/21/2023

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

<i>Project</i>	<i>Project Area in Acres</i>	<i>Fee</i>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

<i>Project</i>	<i>Cost per Linear Foot</i>	<i>Minimum Fee- Maximum Fee</i>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

<i>Project</i>	<i>Cost per Tank or Piping System</i>	<i>Minimum Fee- Maximum Fee</i>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

<i>Project</i>	<i>Fee</i>
Exception Request	\$500

Extension of Time Requests

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150



TCEQ Use Only

TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission <i>(If other is checked please describe in space provided.)</i>		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization <i>(Core Data Form should be submitted with the program application.)</i>		
<input type="checkbox"/> Renewal <i>(Core Data Form should be submitted with the renewal form)</i>	<input type="checkbox"/> Other	
2. Customer Reference Number <i>(if issued)</i>	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number <i>(if issued)</i>
CN 605786011		RN

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)		
<input type="checkbox"/> New Customer <input type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership <input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)				
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>				
6. Customer Legal Name <i>(if an individual, print last name first: eg: Doe, John)</i>			<i>If new Customer, enter previous Customer below:</i>	
QT South, LLC				
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID	10. DUNS Number <i>(if applicable)</i>	
12299906	17306753751	(9 digits) 73-0675375		
11. Type of Customer:		<input checked="" type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		<input type="checkbox"/> Other:
12. Number of Employees			13. Independently Owned and Operated?	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input checked="" type="checkbox"/> 501 and higher			<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – <i>as it relates to the Regulated Entity listed on this form. Please check one of the following</i>				
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input checked="" type="checkbox"/> Owner & Operator <input type="checkbox"/> Other: <input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant				
15. Mailing Address:		QT South, LLC		
		4705 South 129 th East Avenue		
City	Tulsa	State	OK	ZIP 74134 ZIP + 4
16. Country Mailing Information <i>(if outside USA)</i>			17. E-Mail Address <i>(if applicable)</i>	
			krudd@quiktrip.com	
18. Telephone Number		19. Extension or Code		20. Fax Number <i>(if applicable)</i>

{ 918 } 615-7233

() -

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If "New Regulated Entity" is selected, a new permit application is also required.)

New Regulated Entity Update to Regulated Entity Name Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

QT 4160

23. Street Address of the Regulated Entity:

7601 W SH 29

(No PO Boxes)

City	Georgetown	State	TX	ZIP	78628	ZIP + 4	
-------------	------------	--------------	----	------------	-------	----------------	--

24. County

Williamson

If no Street Address is provided, fields 25-28 are required.

25. Description to Physical Location:

1.89-acre property located southeast of Highway 29 and Kauffman Loop outside the city limits but inside the ETJ of Leander, Texas

26. Nearest City

State

Nearest ZIP Code

Leander

TX

78628

Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).

27. Latitude (N) In Decimal:

30.637127

28. Longitude (W) In Decimal:

-97.817061

Degrees

Minutes

Seconds

Degrees

Minutes

Seconds

29. Primary SIC Code

30. Secondary SIC Code

31. Primary NAICS Code

32. Secondary NAICS Code

(4 digits)

(4 digits)

(5 or 6 digits)

(5 or 6 digits)

5541

447110

33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)

Gas Station with convenience store

34. Mailing Address:

7601 W SH 29

Address:

City	Georgetown	State	TX	ZIP	78628	ZIP + 4	
-------------	------------	--------------	----	------------	-------	----------------	--

35. E-Mail Address:

krudd@quiktrip.com

36. Telephone Number

37. Extension or Code

38. Fax Number (if applicable)

{ 918 } 615-7233

() -

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name:	Rachel Roberts	41. Title:	Project Engineer
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(210) 762-5289		() -	Rachel.Roberts@kimley-horn.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	QT South, LLC	Job Title:	Environmental Project Manager
Name (In Print):	Kyla Rudd	Phone:	(918) 615- 7233
Signature:		Date:	3/21/2023