CONTRIBUTING ZONE PLAN

THE SHOPS AT BAGDAD SQUARE NEC NORTH BAGDAD & MUNICIPAL DRIVE LEANDER, WILLIAMSON COUNTY, TEXAS

Prepared For:

BAGDAD RD. LEANDER LLC

3000 Polar Lane, Suite 404 Cedar Park, TX 78813 973-723-4862

Prepared By: KIMLEY-HORN AND ASSOCIATES, INC.

260 East Davis Street, Suite 100 McKinney, TX 75069 469-352-2959



Firm No. 928 KHA Project No. 064585101

3/27/2023

TABLE OF CONTENTS

Edwards Aquifer Application Cover Page	Section 1
EDWARDS AQUIFER APPLICATION COVER PAGE	TCEQ-20705
	0
	SECTION 3
Road Map	Attachment A
USGS Quadrangle Map	Attachment B
Project Narrative	Attachment C
Factors Affecting Surface Water Quality	Attachment D
Volume and Character of Stormwater	Attachment E
Suitability Letter from Authorized Agent	Attachment F
Alternative Secondary Containment Methods	Attachment G
AST Containment Structure Drawings	Attachment H
20% or Less Impervious Cover Waiver	Attachment I
BMPs for Upgradient Stormwater	Attachment J
BMPs for On-site Stormwater	Attachment K
BMPs for Surface Streams	Attachment L
Construction Plans	Attachment M
Inspection, Maintenance, Repair and Retrofit Plan	Attachment N
Pilot-Scale Field Testing Plan	Attachment O
Measures for Minimizing Surface Stream Contamination	Attachment P
ADDITIONAL FORMS	Section 4
AGENT AUTHORIZATION FORM	
APPLICATION FEE FORM	
Check Pavable to the "Texas Commission on Environmental Quality"	
CORE DATA FORM	

Kimley **»Horn**

SECTION 1: EDWARDS AQUIFER APPLICATION COVER PAGE

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the

alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: The Shops at Bagdad Square				2. Regulated Entity No.: Click here to enter text.					
3. Customer Name: Bagdad Rd. Leander		nder l	der LLC		4. Customer No.: Click here to enter text.				
5. Project Type: (Please circle/check one)	New⊠		Mod	ificatio	on	Exter	nsion	Exception	
6. Plan Type: (Please circle/check one)	WPAP	⊠ CZP	SCS	UST	AST	EXP	EXT	Technical Clarificatio	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Resider	ntial	Non-residentia		al 8. Sit		e (acres):	4.67	
9. Application Fee:	\$4,000		10. Permanent		BMP	(s):	Partial Sed/I	Fil Pond	
11. SCS (Linear Ft.):	0		12. AST/UST (N		12. AST/UST (No. Tanks):		0		
13. County:	William	nson	14. V	Vater	shed:			Turkey Creel	k-Brushy Creek

Application Distribution

Г

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)		_	_X_
Region (1 req.)			_X_
County(ies)			_X_
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	_Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin Cedar Park Florence Georgetown Jerrell X Leander Liberty Hill Pflugerville Round Rock

	Si	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)		_			
Region (1 req.)					
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Michael Doggett, P.E.

Print Name of Customer/Authorized Agent Ł Signature of Customer/Authorized Agent

3/27/2023

Date

FOR TCEQ INTERNAL USE ONLY				
Date(s)Reviewed:	Date Adn	Date Administratively Complete:		
Received From:	Correct N	Jumber of Copies:		
Received By:	Distribut	ion Date:		
EAPP File Number:	Complex			
Admin. Review(s) (No.):	No. AR R	ounds:		
Delinquent Fees (Y/N):	Review T	ime Spent:		
Lat./Long. Verified:	SOS Cust	omer Verification:		
Agent Authorization Complete/Notarized (Y/N):		Payable to TCEQ (Y/N):		
Core Data Form Complete (Y/N):	Fee Check:	Signed (Y/N):		
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):		

Kimley **»Horn**

SECTION 2: CONTRIBUTING ZONE PLAN APPLICATION

Contributing Zone Plan Application

Texas Commission on Environmental Quality for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: <u>Michael Doggett, P.E.</u>

Date: <u>3/27/2023</u>

Signature of Customer/Agent:

Regulated Entity Name: _ The Shops at Bagdad Square ____

Project Information

- 1. County: <u>Williamson</u>
- 2. Stream Basin: <u>Turkey Creek-Brushy Creek</u>
- 3. Groundwater Conservation District (if applicable): <u>Edwards Aquifer</u>
- 4. Customer (Applicant):

Contact Person: __Praveen GuduruEntity: _Bagdad Rd. Leander LLCMailing Address: _3000 Polar Lane, Suite 404City, State: _Cedar Park, TXZip: _78813Telephone: _973-723-4862Email Address: _pguduru@yahoo.com

5. Agent/Representative (If any):

Contact Person:Michael Doggett, P.E.Entity:Kimley-Horn and Associates, Inc.Mailing Address:260 East Davis Street, Suite 100City, State:McKinney, TXTelephone:469-352-2959Email Address:michael.doggett@kimley-horn.com

6. Project Location:

The project site is located inside the city limits of _____LEANDER_____.

The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of <u>Leander</u>.

- The project site is not located within any city's limits or ETJ.
- 7. X The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation. NEC North Bagdad & Municipal Drive
- 8. Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
- 9. \square **Attachment B USGS Quadrangle Map**. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:

Project site boundaries.USGS Quadrangle Name(s).

- 10. Attachment C Project Narrative. A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:
 - \square Area of the site
 - Offsite areas
 - Impervious cover
 - Permanent BMP(s)
 - Proposed site use
 - Site history
 - Previous development
 - \square Area(s) to be demolished
- 11. Existing project site conditions are noted below:
 - Existing commercial site
 - Existing industrial site
 - Existing residential site

	 Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Not cleared) Other:
12.	The type of project is:
	 Residential: # of Lots: Residential: # of Living Unit Equivalents: Commercial Industrial Other:
13.	Total project area (size of site): <u>4.67</u> Acres
	Total disturbed area: <u>4.67</u> Acres
14.	Estimated projected population: <u>NA</u>

15. The amount and type of impervious cover expected after construction is complete is shown below:

Table 1 - Impervious Cover

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	51,196	÷ 43,560 =	1.18
Parking	82,778	÷ 43,560 =	1.90
Other paved surfaces	19,207	÷ 43,560 =	0.44
Total Impervious Cover	153,181	÷ 43,560 =	3.52

Total Impervious Cover <u>3.49</u> ÷ Total Acreage <u>4.67</u> X 100 = <u>75.4%</u> Impervious Cover

16. Attachment D - Factors Affecting Surface Water Quality. A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. 🛛 Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

For Road Projects Only

Complete questions 18 - 23 if this application is exclusively for a road project.

N/A 18. Type of project:

TCEQ-10257 (Rev. 02-11-15)

19.	 TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways. Type of pavement or road surface to be used:
	Concrete Asphalt concrete pavement Other:
20.	Right of Way (R.O.W.):
	Length o f R .O.W.:feet.
	Width o f R .O.W.:feet. L x W =Ft ² \div 43,560 Ft ² /Acre =acres.
21.	Pavement Area:
	Length o f R .O.W.:feet.
	Width o f R .O.W.:feet. L x W =Ft ² ÷ 43,560 Ft ² /Acre =acres. Pavement areaacres ÷ R .O.W. a reaacres x 100 =% impervious cover.
22.	A rest stop will be included in this project.
23.	 A rest stop will not be included in this project. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1)

existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

24. Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

25. Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC§213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

🛛 N/A

26. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

Attachment F - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.
 Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30

TAC Chapter 285.

Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the <u>Leander Wastewater</u> <u>Treatment Plant</u> (name) Treatment Plant. The treatment facility is:

Existing. Proposed.

Permanent Aboveground Storage Tanks (ASTs) ≥ 500 Gallons

Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.

🛛 N/A

27. Tanks and substance stored:

Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1			
2			
3			
4			
5			
		Tata	v d E - Collona

Total x 1.5 = _____ Gallons

28. The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

Attachment G - Alternative Secondary Containment Methods. Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

Table 3 - Secondary Containment

Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons
	•		Tot	al: Gallons

30. Piping:

All piping, hoses, and dispensers will be located inside the containment structure.

Some of the piping to dispensers or equipment will extend outside the containment structure.

The piping will be aboveground

The piping will be underground

- 31. The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of:
- 32. Attachment H AST Containment Structure Drawings. A scaled drawing of the containment structure is attached that shows the following:
 - Interior dimensions (length, width, depth and wall and floor thickness).
 - Internal drainage to a point convenient for the collection of any spillage.

Tanks clearly labeled

Piping clearly labeled

Dispenser clearly labeled

33. Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

In the event of a spill, any s	pillage will be removed from the containment structure
within 24 hours of the spill	and disposed of properly.

In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

Site Plan Requirements

Items 34 - 46 must be included on the Site Plan.

34. \square The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = ____40___'.

- 35. 100-year floodplain boundaries:
 - Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
 - No part of the project site is located within the 100-year floodplain. The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): <u>48491C0455F Dated December 20, 2019</u>.
- 36. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

- 37. \square A drainage plan showing all paths of drainage from the site to surface streams.
- 38. 🖂 The drainage patterns and approximate slopes anticipated after major grading activities.
- 39. \boxtimes Areas of soil disturbance and areas which will not be disturbed.
- 40. 🔀 Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 41. 🛛 Locations where soil stabilization practices are expected to occur.
- 42. Surface waters (including wetlands).
 - N/A
- 43. Locations where stormwater discharges to surface water.

There will be no discharges to surface water.

44. Temporary aboveground storage tank facilities.

Temporary aboveground storage tank facilities will not be located on this site.

45. Permanent aboveground storage tank facilities.

Permanent aboveground storage tank facilities will not be located on this site.

46. \square Legal boundaries of the site are shown.

Permanent Best Management Practices (BMPs)

Practices and measures that will be used during and after construction is completed.

47. Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.

N/A

- 48. These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 - The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site. (Phase 1)
 - A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____
 - N/A
- 49. Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

N/A

50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

The site will be used for low density single-family residential development but has more than 20% impervious cover.

 \square The site will not be used for low density single-family residential development.

51. The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

-	-
	 Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. The site will not be used for multi-family residential developments, schools, or small business sites.
52. 🔀	Attachment J - BMPs for Upgradient Stormwater.
	 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
53. 🔀	Attachment K - BMPs for On-site Stormwater.
	 A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
54.	Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.
X	N/A
55.	Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

56. 🔀	Attachment N - Inspection, Maintenance, Repair and Retrofit Plan . A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
	 Prepared and certified by the engineer designing the permanent BMPs and measures Signed by the owner or responsible party Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit. Contains a discussion of record keeping procedures N/A
57. 🗌	Attachment O - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
58.	Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.

N/A

Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.

- 59. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- 60. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

Administrative Information

- 61. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
 - The Temporary Stormwater Section (TCEQ-0602) is included with the application.

064585101 - THE SHOPS AT BAGDAD SQUARE CONTRIBUTING ZONE PLAN MODIFICATION

ROAD MAP



LEGEND	
	CONSTRUCTION SITE 4.67 ACRES

APPENDIX	DATE
•	DESIGNED BY
Δ	DRAWN BY
/ \	CHECKED BY
	KHA PROJECT NO.

ROAD MAP

01/25/2023

SLT

SLT

MTD

064585101

THE SHOPS AT BAGDAD LEANDER, TEXAS WILLIAMSON COUNTY

° | ••



USGS QUADRANGLE MAP



U.S. DEPARTMENT OF THE INTERIOR U.S. GEOLOGICAL SURVEY



LEANDER QUADRANGLE TEXAS 7.5-MINUTE SERIES





Produced by the United States Geological Survey North American Datum of 1983 (NAD83) World Geodetic System of 1984 (WGS84). Projection and 1 000-meter grid:Universal Transverse Mercator, Zone 14R This map is not a legal document. Boundaries may be generalized for this map scale. Private lands within government reservations may not be shown. Obtain permission before entering private lands.

Imagery.... Roads..... Names..... Hydrography..... Contours..... Boundaries.....Mu ..FWS National Wetlands Inventory Not Available Wetlands....

____0°36′ ____11 MILS



ROAD CLASSIFICATION Local Connector Expressway Local Road Secondary Hwy 🗕 _ Ramp 4WD _____ US Route State Route lnterstate Route

LEANDER, TX

2022



PROJECT NARRATIVE

The Shops at Bagdad Square, located at the NEC of Bagdad Road and Municipal Lane in Leander, Texas consists of one Lot that is 4.67 acres in size. The entire site is within the City of Leander City Limits and is subject to their municipal watershed regulations.

The proposed site consists of four single-story retail buildings and associated parking. A detention pond and a biofiltration and sedimentation pond serve the site's drainage requirements.

A Water Quality Drainage Area Map is provided within the Civil Plans. This plan shows there is approximately 2.41 acres of undeveloped property to the South of the Subject Tract (labeled "Offsite") that is currently sheet flowing across this site. A public storm will be extended across the rear of the Subject Site for the "Offsite" portion to drain in the future. The "Offsite" tract must provide their own detention and water quality requirements upon development. The total acreage included in the plan is 4.67 acres. The proposed water quality pond is sized to treat 4.67 acres. This equates to an on-site water quality volume required of 18242 cubic feet of storage. This plan assumes that adequate water quality volume has been provided for all upstream areas.

The site will be served by an existing 8" water line and 8" sewer line along the east side of Bagdad Road.

This site is located in the Turkey Creek-Brushy Creek Watershed and entirely in the Edwards Aquifer Contributing Zone as defined by maps prepared by the Texas Commission on Environmental Quality.

No portion of the property is within the limits of the 100-year floodplain as shown on FIRM Panel No. 48491C0455F, dated December 20, 2019.

FACTORS AFFECTING SURFACE WATER QUALITY ROAD MAP

Surface water quality can be affected by disturbance during construction and by development after construction. Soil disturbance from clearing and grubbing and cut / fill operations can lead to discharge of sediment unless adequate temporary erosion control measures are in place. For this project, the use of silt fence and rock berms will prevent sediment from leaving the site. The existing water quality pond and proposed grassy swale will provide sedimentation during construction. Siltation collected by the control measures will be cleaned from fences, berms, etc. on a routine schedule.

During construction, surface water quality may also be affected by a spill of hydrocarbons or other hazardous substances used in construction. The most likely instances of a spill of hydrocarbons or hazardous substances are:

- 1. Refueling construction equipment.
- 2. Performing operator-level maintenance, including adding petroleum, oils, or lubricants.
- 3. Unscheduled or emergency repairs, such as hydraulic fluid leaks.

Every effort will be taken to be cautious and prevent spills. In the event of a fuel or hazardous substance spill as defined by the Reportable Quantities Table 1 (page 3) of the TCEQ's Small-Business Handbook for Spill Response (RG-285, June 1997), the contractor is required to clean up the spill and notify the TCEQ as required in RG-285. During business hours report spills to the TCEQ's Austin Regional Office at (512) 339-2929, after business hours call 1-800-832-8224, the Environmental Response Hotline or (512) 463-7727, the TCEQ Spill Reporting Hotline, which is also answered 24 hours a day.

After construction is complete, impervious cover for the tract of land is the major reason for degradation of water quality. Impervious cover includes the building foundation, parking lot pavement and concrete sidewalks. Oil and fuel discharge from vehicles is anticipated. A partial sedimentation/filtration pond and grassy swale will mitigate these factors.

VOLUME AND CHARACTER OF STORMWATER

On-Site Drainage

The onsite drainage is collected through a pipe conveyance system with grate inlets and curb inlets collecting the drainage at low points on the site. The drainage is conveyed to a proposed biofiltration and sedimentation pond. The runoff then drains to the detention pond where it is then released through an outlet structure to an outlet pipe that discharges into an existing floodplain.

The detention pond is designed to hold the 100-year storm event. The 100-year water surface elevation is 1012.92-feet and hold 24,371 CF (cubic feet) of water.

Calculations for the water quality surface area are included in the Civil Plans.

Off-Site Drainage

The site to the south of the proposed site is undeveloped. Evaluation of the existing contours shows the drainage from the southern property sheet flows to the southeast corner of the subject site. A proposed drop inlet collects the drainage from the southern property and pipes the drainage into the existing floodplain. Upon development of the Off-Site area, water quality and detention must be provided.

SUITABILITY LETTER FROM AUTHORIZED AGENT

ALTERNATIVE SECONDARY CONTAINMENT STRUCTURE DESIGN ROAD MAP

AST CONTAINMENT STRUCTURE DRAWINGS

20% OR LESS IMPERVIOUS COVER WAIVER

BMPs FOR UPGRADIENT STORMWATER

BMPs FOR ON-SITE STORMWATER

A partial filtration and sedimentation pond will be utilized on the site. The size of the pond and each component within the pond have been calculated based on the existing grades on the site as well as the total drainage area the pond will treat.

Silt fence will be utilized around the site during construction to avoid additional erosion from the site.

Inlet protection covers will be utilized once the storm infrastructure has been constructed. This will aid in avoiding additional sediment from running through the storm system.

BMPs FOR SURFACE STREAMS

Silt fence will be utilized as the temporary BMP along a few key locations within the site. As shown in the approved E&S plan, silt fence will be placed along or near almost the entire property line to filter offsite runoff. The storm water runoff typically runs parallel to the proposed silt fence to provide the most effective capture of runoff silt.

CONSTRUCTION PLANS

SITE DEVELOPMENT PLANS FOR THE SHOPS AT BAGDAD SQUARE BLOCK A, LOT 1 **ZONING: LOCAL COMMERCIAL** IN THE CITY OF LEANDER WILLIAMSON COUNTY, TEXAS CITY PROJECT NO. 23-SD-XXX

NOTES:

- THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURAC REGULATORY COMPLIANCE, AND ADEQUACY OF THESE PLANS AND/OR SPECIFICATIONS WHETHER OR NOT THE PLANS AND/OR SPECIFICATIONS WERE REVIEWED BY THE CITY ENGINEER(S
- THIN THE DESIGNATED FLOOD HAZARD AREA AS SHOWN ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP (FIRM) #48491C0455F CITY OF LEANDER, TX BOTH DATED DECEMBER 20, 2019
- CONTRACTOR TO NOTIFY DIGTESS PRIOR TO COMMENCING CONSTRUCTION AT 1-800-DIGTES
- THIS SITE IS LOCATED WITHIN EDWARDS AQUIFER CONTRIBUTING ZONE, HOWEVER REGIONAL WATE QUALITY WILL BE PROVIDED
- 5. THE CITY OF LEANDER STANDARD CONSTRUCTION NOTES SHALL APPLY AND TAKE PRECEDENCE. FOR INSTANCES WHERE THEY CONFLICT WITH KIMLEY-HORN NOTES OR APPLICABLE TCEQ REQUIREMENTS, THEN THE MORE RESTRICTIVE SHALL APPLY.

SUBMITTAL DATE: 02/06/2023

ZONING: LC-2-B

SITE AREA: 4.672 AC

TOTAL IMPERVIOUS COVER: 164.844 SF (81%)

FUTURE LAND USE: MULTI-USE CORRIDOR

LEGAL DESCRIPTION:

SHOPS AT BAGDAD SQUARE, LOT 1, BLOCK A

ENGINEER: Kimley-Horn and Associates, Inc.

260 East Davis Street, Suite 100 McKinney, Texas 75069 Tel. No. (469) 301-2580 Contact: Michael T. Doggett, P.E.



Firm Registration No. F-928 260 East Davis Street, Suite 100 McKinney, Texas 75069 Tel. No. (469) 301-2580

DEVELOPER:

Baghdad Rd. Leander LLC 3000 Polar Lane, Suite 404 Cedar Park, TX Phone: (973) 723-4862 Contact: Praveen Guduru

ARCHITECT:

MAT Studios 14618 Mansfield Dam Ct 19 Austin, TX 78734 Phone: (469) 951-0614 Contact: Monika Arora

SURVEYOR

The Altum Group P.O Box 6493 Round Rock, TX 78683 Phone: (760) 346-4750 Contact: Dewayne Hendriex

	PROPERTY ID: R519003	
	WILLIAMSON COUNTY TEXAS	
	APPROVED BY:	
	ROBIN M. GRIFFIN, AICP, EXECUTIVE DIRECTOR OF DEVELOPMENT SERVICES DATE	
	EMILY TRUMAN, P.E., CFM, CITY ENGINEER DATE	
	GINA ELLISON, P.E., PUBLIC WORKS DIRECTOR DATE	
	MARK TUMMONS, CPRP, PARKS & RECREATION DIRECTOR DATE	
	CHIEF JOSHUA DAVIS, FIRE MARSHAL DATE THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY, REGULAT ADEQUACY OF THESE PLANS AND/OR SPECIFICATIONS WHETHER OR NOT THE PLANS AND/OR SPECIFIC BY THE CITY ENGINEER(S)	ORY COMPLIANCE, AND CATIONS WERE REVIEWED
REVISION #	DESCRIPTION	APPROVAL

APRIL 2023

THE SHOPS AT BAGDAD SQUARE BLOCK A, LOT 1

SHEET INDEX			
SHEET NO.	Sheet Title		
01	COVER SHEET		
02	CITY OF LEANDER NOTES		
03	KIMLEY-HORN GENERAL NOTES		
04	PLAT (1 OF 3)		
05	PLAT (2 OF 3)		
06	PLAT (3 OF 3)		
07	DEMO PLAN		
08	EROSION CONTROL PLAN		
09	EROSION CONTROL DETAILS		
10	GRADING PLAN		
11	EXISTING DRAINAGE AREA MAP		
12	DRAINAGE AREA MAP		
13	DRAINAGE CALCULATIONS		
14	SITE PLAN		
15	DIMENSION CONTROL PLAN		
16	PAVING PLAN		
17	PAVING DETAILS		
18	STORM PLAN		
19	STORM PROFILES		
20	DETENTION POND PLAN		
21	DRAINAGE DETAILS		
22	WATER QUALITY PLAN		
23	WATER QUALITY CALCULATION		
24	WATER QUALITY DETAILS		
25	WATER AND SANITARY SEWER PLAN		
26	UTILITY DETAILS (1 OF 2)		
27	UTILITY DETAILS (2 OF 2)		
28	LANDSCAPE PLAN - L1		
29	LANDSCAPE PLAN - L2		



APPROVAL

LEANDER NO ЦО CITY 01 OF 29

23-SD-XXX

GENERAL NOTES REVISED JUNE 22, 2022 ANY CHANGES TO THESE NOTES SHOULD BE CLOUDED ON THE PLAN SET. CITY CONTACTS: ENGINEERING MAIN LINE: 512-528-2766 PLANNING DEPARTMENT: 512-528-2750 PUBLIC WORKS MAIN LINE: 512-259-2640 STORMWATER INSPECTIONS: 512-285-0055 UTILITIES MAIN LINE: 512-259-1142 UTILITIES ON-CALL: 512-690-4760 UTILITY LOCATE REQUESTS locates@leandertx.gov

GENERAL NOTES:

1. THE CONTRACTOR SHALL VERIFY ALL DEPTHS AND LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES WITH CONSTRUCTION PLANS FOUND IN THE FIELD SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER. 2. THE CONTRACTOR SHALL CONTACT THE TEXAS EXCAVATION SYSTEM AT 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS 48 HOURS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES THAT ARE TO BE EXTENDED, TIED TO, CROSSED, OR ALTERED; OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS. 3. CONTACT THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT FOR EXISTING WATER AND

WASTEWATER LOCATIONS 48 HOURS PRIOR TO CONSTRUCTION. a. LOCATE REQUESTS MUST INCLUDE A COPY OF YOUR 811 TICKET. THE CITY OF LEANDER IS ALLOWED UP TO 48 HOURS TO COMPLY WITH YOUR REQUEST, EXCLUDING

WEEKENDS AND DESIGNATED CITY HOLIDAYS. b. REFRESH ALL LOCATES BEFORE 14 DAYS – LOCATE REFRESH REQUESTS MUST INCLUDE A COPY OF YOUR 811 TICKET. SUBMIT ALL REQUESTS TO LOCATES@LEANDERTX.GOV. TEXAS PIPELINE DAMAGE PREVENTION LAWS REQUIRE THAT A LOCATE REFRESH REQUEST BE SUBMITTED BEFORE 14 DAYS, OR IF LOCATION MARKERS ARE NO LONGER VISIBLE.

c. REPORT PIPELINE DAMAGE IMMEDIATELY – IF YOU WITNESS OR EXPERIENCE PIPELINE EXCAVATION DAMAGE, PLEASE CONTACT THE CITY OF LEANDER BY PHONE AT 512-259-2640.

4. ANY CHANGES OR REVISIONS TO THESE PLANS MUST FIRST BE SUBMITTED TO THE CITY BY THE DESIGN ENGINEER FOR REVIEW AND WRITTEN APPROVAL PRIOR TO CONSTRUCTION OF THE REVISION.

5. A TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, SHALL BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO ANY PARTIAL OR COMPLETE ROADWAY CLOSURES. TRAFFIC CONTROL PLANS SHALL BE SITE SPECIFIC AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER. LANE CLOSURES ON ARTERIALS AND ANY FULL ROAD CLOSURES REQUIRE MESSAGE BOARDS NOTIFYING THE PUBLIC ONE WEEK PRIOR TO THE CLOSURE.

6. NO WORK IS TO BE PERFORMED BETWEEN THE HOURS OF 9:00 P.M. AND 7:00 A.M. THE CITY INSPECTOR RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO UNCOVER ALL WORK PERFORMED WITHOUT INSPECTION FURTHER, THERE IS A NOISE ORDINANCE IN EFFECT FOR CONSTRUCTION ACTIVITY BETWEEN THE HOURS OF 9:00 PM AND 7:00 AM. REQUESTS FOR EXCEPTIONS TO THE ORDINANCE MUST BE MADE TO LEANDER CITY COUNCIL. 7. CONTACT THE CITY INSPECTOR 4 DAYS PRIOR TO WORK TO SCHEDULE ANY INSPECTIONS ON WEEKENDS OR CITY HOLIDAYS.

8. NO STREET LIGHTS OR SIGNS OF ANY KIND ARE TO BE PLACED WITHIN ANY SIDEWALKS. 9. NO BLASTING IS ALLOWED. 10. ANY EXISTING UTILITIES, PAVEMENT, CURBS, SIDEWALKS, STRUCTURES, TREES, ETC., THAT

ARE DAMAGED OR REMOVED SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER.

11. THE CONTRACTOR SHALL GIVE THE CITY OF LEANDER 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION. CONTACT ASSIGNED CITY INSPECTOR. 12. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT AND THE CITY OF LEANDER REPRESENTATIVES PRIOR TO INSTALLATION OF EROSION/SEDIMENTATION CONTROLS AND TREE PROTECTION MEASURES AND PRIOR TO BEGINNING ANY WORK. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER PLANNING DEPARTMENT PLANNING COORDINATOR AT LEAST THREE (3) DAYS PRIOR TO THE MEETING DATE.

13. THE CONTRACTOR AND ENGINEER SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE ENGINEER SHALL FURNISH THE CITY OF LEANDER ACCURATE "RECORD DRAWINGS" FOLLOWING THE COMPLETION OF ALL CONSTRUCTION. THESE "RECORD DRAWINGS" SHALL MEET THE SATISFACTION OF THE ENGINEERING DEPARTMENTS PRIOR TO FINAL ACCEPTANCE

14. WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS, THE CONTRACTOR SHALL CONFINE HIS WORK TO WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. PRIOR TO ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT EASEMENTS. CLEANUP SHALL BE TO THE SATISFACTION OF THE ENGINEER.

15. CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS AND PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO OWNER.

16. THE CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. IN THE EVENT THAT A FENCE MUST BE REMOVED. THE CONTRACTOR SHALL REPLACE SAID FENCE OR PORTION THEREOF WITH THE SAME TYPE OF FENCING TO A QUALITY OF EQUAL OR BETTER THAN THE ORIGINAL FENCE.

17. ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA). OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE; INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 1033 LA POSADA DR. SUITE 375, AUSTIN, TEXAS 78752-3832.

18. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT WHERE NOT SPECIFICALLY COVERED IN THE PROJECT SPECIFICATIONS SHALL CONFORM TO ALL CITY OF LEANDER DETAILS AND CITY OF AUSTIN STANDARD SPECIFICATIONS. 19. PROJECT SPECIFICATIONS TAKE PRECEDENCE OVER PLANS AND SPECIAL CONDITIONS GOVERN OVER TECHNICAL SPECIFICATIONS.

20. HOT MIX ASPHALTIC CONCRETE PAVEMENT SHALL BE MINIMUM THICKNESS OF 2 INCHES WITH NO RECYCLED ASPHALT SHINGLES CONTENT. 21. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY QUESTIONS THAT MAY

RISE CONCERNING THE INTENT, PLACEMENT, OR LIMITS OF DIMENSIONS OR GRADES NECESSARY FOR THE CONSTRUCTION OF THIS PROJECT.

22. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT. 23. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COORDINATION BETWEEN HIMSELF AND OTHER CONTRACTORS AND UTILITIES IN THE VICINITY OF THE PROJECT. THIS INCLUDES GAS, WATER, WASTEWATER, ELECTRICAL, TELEPHONE, CABLE TV AND STREET DRAINAGE WORK. ONCE THE CONTRACTOR BECOMES AWARE OF A POSSIBLE CONFLICT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE ENGINEER WITHIN TWENTY-FOUR (24) HOURS.

24. THE CONTRACTOR MUST OBTAIN A CONSTRUCTION WATER METER FOR ALL WATER USED DURING CONSTRUCTION. A COPY OF THIS PERMIT MUST BE CARRIED AT ALL TIMES BY ALL WHO USE WATER

25. CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ROADS AND DRIVES ADJACENT TO AND NEAR THE SITE FREE FROM SOIL, SEDIMENT AND DEBRIS. CONTRACTOR WILL NOT REMOVE SOIL, SEDIMENT OR DEBRIS FROM ANY AREA OR VEHICLE BY MEANS OF WATER. ONLY SHOVELING AND SWEEPING WILL BE ALLOWED. CONTRACTOR WILL BE RESPONSIBLE FOR DUST CONTROL FROM THE SITE.

26. THE CITY OF LEANDER SHALL NOT BE PETITIONED FOR ACCEPTANCE UNTIL ALL NECESSARY EASEMENT DOCUMENTS HAVE BEEN SIGNED AND RECORDED.

27. AN ENGINEER'S CONCURRENCE LETTER AND RECORD DRAWINGS SHALL BE SUBMITTED TO THE ENGINEERING DEPARTMENT PRIOR TO THE ISSUANCE OF CERTIFICATE OF COMPLETION OR SUBDIVISION ACCEPTANCE. THE ENGINEER AND CONTRACTOR SHALL VERIFY THAT ALL FINAL REVISIONS AND CHANGES HAVE BEEN MADE TO THE DIGITAL COPY PRIOR TO CITY SUBMITTAL. RECORD CONSTRUCTION DRAWINGS, INCLUDING ROADWAY AND ALL UTILITIES SHALL BE PROVIDED TO THE CITY IN DIGITAL FORMAT AS AUTOCAD ".DWG" FILES, MICROSTATION ".DGN" FILES OR ESRI ".SHP" FILES ON CD ROM. LINE WEIGHTS, LINE TYPES AND TEXT SIZE SHALL BE SUCH THAT IF HALF-SIZE PRINTS (11"X17") WERE PRODUCED, THE PLANS WOULD STILL BE LEGIBLE. ALL REQUIRED DIGITAL FILES SHALL CONTAIN A MINIMUM

OF TWO CONTROL POINTS REFERENCED TO THE STATE PLANE GRID COORDINATE SYSTEM -TEXAS CENTRAL ZONE (4203), IN US SURVEY FEET AND SHALL INCLUDE ROTATION

INFORMATION AND SCALE FACTOR REQUIRED TO REDUCE SURFACE COORDINATES TO GRID COORDINATES IN US SURVEY FEET 28. TREES IN EXISTING ROW SHOULD BE PROTECTED OR NOTED IN THE PLANS TO BE REMOVED.

CONSTRUCTION SEQUENCE NOTES:

1. INSTALL STABILIZED CONSTRUCTION ENTRANCE, EROSION CONTROLS AND TREE PROTECTION FENCING FOR EACH PHASE PRIOR TO CLEARING AND GRUBBING AND PER APPROVED EROSION AND SEDIMENTATION CONTROL/TREE PROTECTION PLAN. 2. THE CONTRACTOR SHALL ARRANGE AND COORDINATE ACCEPTABLE MEETING TIMES FOR AN ON-SITE PRE-CONSTRUCTION MEETING WITH THE OWNER, PROJECT ENGINEER, RELEVANT CONTRACTORS, RELEVANT UTILITY REPRESENTATIVES, AND THE CITY ENGINEER. AT THIS MEETING, THE CITY SHALL VERIFY THAT ALL EROSION AND SEDIMENT CONTROLS AND TREE PROTECTION ARE IN PLACE. THAT CONSTRUCTION DRAWINGS AND THE SWPPP ARE LOCATED ON SITE. AND THAT THE SWPPP PERMITS HAVE BEEN ISSUED. THE CITY MAY THEN ISSUE THE SUBDIVISION IMPROVEMENT PERMIT.

3. BEGIN SITE CLEARING.

- 4. CLEAR AND GRUB AND STRIP TOPSOIL. STOCKPILE TOPSOIL FOR LATER USE.
- 6. CONSTRUCT WET AND DRY UTILITIES.
- 7. FINAL SUBGRADE PREPARATION. 8. INSTALL BASE MATERIALS.
- 9. INSTALL CONCRETE (FOUNDATIONS, CURBS, FLATWORK).
- 10. CONSTRUCT BUILDINGS.
- 11. INSTALL PAVEMENTS.
- 12. TOPSOIL, IRRIGATION, AND LANDSCAPING.
- SUBSTANTIAL CONFORMANCE TO THE PLANS.
- 15. SITE CLEANUP AND REMOVAL OF TEMPORARY BMP'S.

BUILDUP IN THE WET POND FROM CONSTRUCTION ACTIVITIES.

EROSION CONTROL NOTES:

1. THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE PROTECTIVE FENCING PRIOR TO ANY WORK (CLEARING, GRUBBING OR EXCAVATION). CONTACT STORMWATER INSPECTOR FOR ON SITE INSPECTION PRIOR TO BEGINNING CONSTRUCTION. 2. THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES. 3. THE TEMPORARY SPOILS DISPOSAL SITE IS TO BE SHOWN IN THE EROSION CONTROL MAP. 4. ANY ON-SITE SPOILS DISPOSAL SHALL BE REMOVED PRIOR TO ACCEPTANCE UNLESS SPECIFICALLY SHOWN ON THE PLANS. THE DEPTH OF SPOIL SHALL NOT EXCEED 10 FEET IN ANY AREA.

5. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE RESTORED WITH A MINIMUM OF 6 INCHES OF TOPSOIL AND COMPOST BLEND. TOPSOIL ON SINGLE FAMILY LOTS MAY BE INSTALLED WITH HOME CONSTRUCTION. THE TOPSOIL AND COMPOST BLEND SHALL CONSIST OF 75% TOPSOIL AND 25% COMPOST. 6. SEEDING FOR REESTABLISHING VEGETATION SHALL COMPLY WITH THE AUSTIN GROW GREEN GUIDE OR WILLIAMSON COUNTY'S PROTOCOL FOR SUSTAINABLE ROADSIDES (SPEC 164--WC001 SEEDING FOR EROSION CONTROL). RESEEDING VARIETIES OF BERMUDA SHALL NOT BE USED. 7. STABILIZED CONSTRUCTION ENTRANCE IS REQUIRED AT ALL POINTS WHERE CONSTRUCTION TRAFFIC IS EXITING THE PROJECT ONTO EXISTING PAVEMENT. LINEAR CONSTRUCTION PROJECTS MAY REQUIRE SPECIAL CONSIDERATION. ROADWAYS SHALL REMAIN CLEAR OF SILT AND MUD. 8. TEMPORARY STOP SIGNS SHOULD BE INSTALLED AT ALL CONSTRUCTION ENTRANCES WHERE A STOP CONDITION DOES NOT ALREADY EXIST. 9. IN THE EVENT OF INCLEMENT WEATHER THAT MAY RESULT IN A FLOODING SITUATION. THE CONTRACTOR SHALL REMOVE INLET PROTECTION MEASURES UNTIL SUCH TIME AS THE WEATHER EVENT HAS PASSED.

WATER AND WASTEWATER NOTES:

1. PRESSURE TAPS SHALL BE IN ACCORDANCE WITH CITY OF LEANDER STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL PERFORM ALL EXCAVATION, ETC. AND SHALL FURNISH, INSTALL AND AIR TEST THE SLEEVE AND VALVE. A CITY OF LEANDER INSPECTOR MUST BE PRESENT WHEN THE CONTRACTOR MAKES A TAP, AND/OR ASSOCIATED TESTS. A MINIMUM OF TWO (2) WORKING DAYS NOTICE IS REQUIRED. "SIZE ON SIZE" TAPS WILL NOT BE PERMITTED UNLESS MADE BY THE USE OF AN APPROVED FULL-CIRCLE GASKETED TAPPING SLEEVE. CONCRETE BLOCKING SHALL BE PLACED BEHIND AND UNDER ALL TAP SLEEVES A MINIMUM OF 24 HOURS PRIOR TO THE BRANCH BEING PLACED INTO SERVICE. BLOCKING SHALL BE INSPECTED PRIOR 10

BACKFILL. 2. FIRE HYDRANTS ON MAINS UNDER CONSTRUCTION SHALL BE SECURELY WRAPPED WITH A BLACK POLY WRAP BAG AND TAPED INTO PLACE. THE POLY WRAP SHALL BE REMOVED WHEN THE MAINS ARE ACCEPTED AND PLACED INTO SERVICE.

3. CURVILINEAR WASTEWATER DESIGN LAYOUT IS NOT PERMITTED. 4. THRUST BLOCKING OR RESTRAINTS SHALL BE IN ACCORDANCE WITH THE CITY OF LEANDER STANDARD SPECIFICATIONS AND REQUIRED AT ALL FITTINGS PER DETAIL OR MANUFACTURER'S

RECOMMENDATION. ALL FITTINGS SHALL HAVE BOTH THRUST BLOCKING AND RESTRAINTS. 5. MANDREL TESTING WILL BE REQUIRED ON ALL WASTEWATER PIPE. PER TCEQ, THIS TEST MUST BE CONDUCTED AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS.

6. ALL NEWLY INSTALLED PIPES AND RELATED PRODUCTS MUST CONFORM TO AMERICAN NATIONAL STANDARDS INSTITUTE/NATIONAL SANITATION FOUNDATION (ANSI/NSF) STANDARD

61 AND MUST BE CERTIFIED BY AND ORGANIZATION ACCREDITED BY ANSI 7. DURING PERIODS OF EXTENDED DRY WEATHER, TRENCH BACKFILL MUST BE COMPACTED BY

FLOODING THE TRENCHES AS DIRECTED BY THE CITY ENGINEER.

STAMPED AS FOLLOWS:

WATER SERVICE "W" ON TOP OF CURB WASTEWATER SERVICE "S" ON TOP OF CURB VALVE "V" ON TOP OF CURB

9. TOOLS FOR STAMPING THE CURBS SHALL BE PROVIDED BY THE CONTRACTOR. OTHER APPROPRIATE MEANS OF STAMPING SERVICE AND VALVE LOCATIONS SHALL BE PROVIDED IN AREAS WITHOUT CURBS. SUCH MEANS OF STAMPING SHALL BE SPECIFIED BY THE ENGINEER AND ACCEPTED BY THE CITY OF LEANDER 10. ALL PLASTIC PIPES FOR USE IN PUBLIC WATER SYSTEMS MUST BEAR THE NATIONAL SANITATION FOUNDATION SEAL OF APPROVAL (NSF-PW) AND HAVE AN ASTM DESIGN PRESSURE RATING OF AT LEAST 200 PSI.

11. NO PIPE OR FITTING WHICH HAS BEEN USED FOR ANY PURPOSE OTHER THAN THE CONVEYANCE OF DRINKING WATER SHALL BE ACCEPTED OR RELOCATED FOR USE IN ANY PUBLIC DRINKING WATER SUPPLY.

12. TYPICAL DEPTH OF COVER FOR ALL WASTEWATER LINES SHALL BE 48" MINIMUM, WATER LINES SHALL BE 36" MINIMUM UNDER BOTH PAVEMENT AND NATURAL GROUND. STORM SEWER SHALL BE 24" MINIMUM UNDER NATURAL GROUND

13. THE HYDROSTATIC LEAKAGE RATE SHALL NOT EXCEED THE AMOUNT ALLOWED OR RECOMMENDED BY AWWA FORMULAS. 14. ALL WATER MAINS, DISTRIBUTION LINES AND SERVICE LINES SHALL BE INSTALLED IN ENCASEMENT PIPE UNDERNEATH EXISTING STREETS AND OTHER PAVED SURFACES UNLESS

APPROVED WITH PLANS. 15. ALL MECHANICAL RESTRAINTS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.

16. ALL DEAD-END WATER MAINS SHALL HAVE THRUST RESTRAINTS INSTALLED ON THE LAST THREE PIPE-LENGTHS (STANDARD 20' LAYING LENGTH), AT MINIMUM, AND THRUST BLOCKS INSTALLED ON THE PLUG. ADDITIONAL THRUST RESTRAINTS MAY BE REQUIRED BASED UPON THE MANUFACTURER'S RECOMMENDATIONS AND/OR CALCULATIONS BY THE ENGINEER OF RECORD

17. WHERE WATER LINES CROSS WASTEWATER LINES AND THERE IS LESS THAN 9 FEET CLEARANCE BETWEEN LINES, THE WASTEWATER LINE SHALL BE PLACED SO THAT THE WASTEWATER PIPE SECTION IS CENTERED ON THE WATER LINE AND CONSTRUCTED IN ACCORDANCE WITH TCEQ CHAPTERS 217.53(b) AND 290.44(e).

18. PIPE MATERIAL FOR WATER MAINS SHALL BE PVC (AWWA C900-16 MIN. 235 PSI PRESSURE RATING). WATER SERVICES (2" OR LESS) SHALL BE POLYETHYLENE TUBING (BLACK, 200PSI, SDR-(9)). DUCTILE IRON PIPE (AWWA C115/C151, MIN. PRESSURE CLASS 250) MAY BE USED FOR WATER MAINS WITH THE EXPRESS APPROVAL OF CITY OF LEANDER ENGINEERING. 19. PIPE FOR PRESSURE WASTEWATER MAINS SHALL BE PVC (AWWA C900-16), GREEN AND MARKED FOR SEWER. PIPE MATERIAL FOR GRAVITY WASTEWATER MAINS SHALL BE PVC (ASTM D2241, D3034 MAX. SDR-26 OR PS115 F679) OR FIBERGLASS WITH PIPE STIFFNESS OF 72 PSI PER

COA SPL WW-509. 20. ALL FIRE HYDRANT LEADS SHALL BE DUCTILE IRON PIPE (AWWA C115/C151 PRESSURE CLASS 350).

5. ROUGH SUBGRADE SITE IN ACCORDANCE WITH PLANS AND SPECIFICATIONS.

13. PROJECT ENGINEER INSPECTS JOB AND SUBMITS THE ENGINEER'S CONCURRENCE LETTER. 14. CITY VISITS SITE AND ISSUES CERTIFICATE OF ACCEPTANCE ONLY IF ALL CONSTRUCTION IS IN

16. FOLLOWING THE COMPLETION OF THE PROJECT THE CONTRACTOR SHALL REMOVE ANY SEDIMENT

8. ALL WATER SERVICE, WASTEWATER SERVICE AND VALVE LOCATIONS SHALL BE APPROPRIATELY

21. INTERIOR SURFACES OF ALL DUCTILE IRON POTABLE OR RECLAIMED WATER PIPE SHALL BE CEMENT-MORTAR LINED AND SEAL COATED AS REQUIRED BY AWWA C104.

22. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH MINIMUM 8-MIL POLYETHYLENE. 23. THE CONTRACTOR SHALL CONTACT THE ENGINEERING DEPARTMENT INSPECTOR AT 528-2700 AT LEAST 48 HOURS PRIOR TO CONNECTING TO THE EXISTING WATER LINES.

24. ALL MANHOLES SHALL BE CONCRETE WITH CAST IRON RING AND COVER. TAPPING OF FIBERGLASS MANHOLES SHALL NOT BE ALLOWED. 25. EXISTING MANHOLES MODIFIED BY CONSTRUCTION ACTIVITY SHALL BE TESTED FOR LEAKAGE

BY VACUUM. ANY EXISTING MANHOLE WHICH FAILS TO PASS THE VACUUM TEST SHALL BE CLOSELY EXAMINED BY THE INSPECTOR AND THE CONTRACTOR TO DETERMINE IF THE MANHOLE CAN BE REPAIRED. THEREAFTER, THE CONTRACTOR SHALL EITHER REPAIR OR REMOVE AND REPLACE THE MANHOLE AS DIRECTED.

26. PIPE CONNECTIONS TO EXISTING MANHOLES AND JUNCTION BOXES SHALL BE CONSTRUCTED IN ACCORDANCE WITH CITY OF AUSTIN SPECIFICATION 506.5.F. 27. LINE FLUSHING OR ANY ACTIVITY USING A LARGE QUANTITY OF WATER MUST BE COORDINATED WITH THE PUBLIC WORKS DEPARTMENT.

28. THE CONTRACTOR, AT HIS EXPENSE, SHALL PERFORM STERILIZATION OF ALL CONSTRUCTED POTABLE WATER LINES AND SHALL PROVIDE ALL EQUIPMENT (INCLUDING TEST GAUGES), SUPPLIES (INCLUDING CONCENTRATED CHLORINE DISINFECTING MATERIAL), AND NECESSARY LABOR REQUIRED FOR THE STERILIZATION PROCEDURE. THE STERILIZATION PROCEDURE SHALL BE MONITORED BY CITY OF LEANDER PERSONNEL. WATER SAMPLES WILL BE COLLECTED BY THE CITY OF LEANDER TO VERIFY EACH TREATED LINE HAS ATTAINED AN INITIAL CHLORINE CONCENTRATION OF 50 PPM. WHERE MEANS OF FLUSHING IS NECESSARY, THE CONTRACTOR, AT HIS EXPENSE, SHALL PROVIDE FLUSHING DEVICES AND REMOVE SAID DEVICES PRIOR TO FINAL ACCEPTANCE BY THE CITY OF LEANDER.

29. SAMPLING TAPS SHALL BE BROUGHT UP TO 3 FEET ABOVE GRADE AND SHALL BE EASILY ACCESSIBLE FOR CITY PERSONNEL. AT THE CONTRACTORS' REQUEST, AND IN HIS PRESENCE, SAMPLES FOR BACTERIOLOGICAL TESTING WILL BE COLLECTED BY THE CITY OF LEANDER NOT LESS THAN 24 HOURS AFTER THE TREATED LINE HAS BEEN FLUSHED OF THE CONCENTRATED CHLORINE SOLUTION AND CHARGED WITH WATER APPROVED BY THE CITY. 30. TESTING SHALL BE PERFORMED FOR ALL WASTEWATER PIPE INSTALLED AND PRESSURE PIPE HYDROSTATIC TESTING OF ALL WATER LINES CONSTRUCTED. THE OWNER'S CONTRACTOR SHALL PROVIDE ALL EQUIPMENT (INCLUDING PUMPS AND GAUGES), SUPPLIES AND LABOR NECESSARY TO PERFORM THE TESTS. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER ENGINEERING DEPARTMENT NO LESS THAN 48 HOURS PRIOR TO PERFORMING STERILIZATION. QUALITY TESTS, OR PRESSURE TESTS. A CITY OF LEANDER INSPECTOR SHALL BE PRESENT FOR ALL TESTS AND SHALL BE PAID FOR BY THE OWNER/CONTRACTOR. THESE SERVICES ARE PAID

FOR AT THE TIME OF CONSTRUCTION PLAN SUBMITTAL. 31. THE CONTRACTOR SHALL NOT OPEN OR CLOSE ANY VALVE UNLESS AUTHORIZED BY THE CITY OF LEANDER.

32. ALL VALVE BOXES AND COVERS SHALL BE CAST IRON.

33. ALL WATER VALVE COVERS ARE TO BE PAINTED BLUE. 34. ALL WATER METER BOXES SHALL BE:

a. SINGLE, 1" METER AND BELOW DFW37F-12-1CA, OR EQUAL

b. DUAL, 1" METERS AND BELOW DFW39F-12-1CA, OR EQUAL

c. 1.5" SINGLE METER DFW65C-14-1CA, OR EQUAL d. 2" SINGLE METER DFW1730F-12-1CA, OR EQUAL

35. SAND, AS DESCRIBED IN AUSTIN SPECIFICATION ITEM 510 PIPE, SHALL NOT BE USED AS BEDDING FOR WATER AND WASTEWATER LINES. ACCEPTABLE BEDDING MATERIALS ARE PIPE BEDDING STONE, PEA GRAVEL AND IN LIEU OF SAND, A NATURALLY OCCURRING OR MANUFACTURED STONE MATERIAL CONFORMING TO ASTM C33 FOR STONE QUALITY AND MEETING THE FOLLOWING GRADATION SPECIFICATION: SIEVE SIZE PERCENT RETAINED BY WEIGHT

1/2" 0 3/8" 0-2

#4 40-85

#10 95-100

36. THE CONTRACTOR IS HEREBY NOTIFIED THAT CONNECTING TO, SHUTTING DOWN, OR TERMINATING EXISTING UTILITY LINES MAY HAVE TO OCCUR AT OFF-PEAK HOURS. SUCH HOURS ARE USUALLY OUTSIDE NORMAL WORKING HOURS AND POSSIBLY BETWEEN 12 AM AND 6 AM

37. ALL WASTEWATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) REGULATIONS. 30 TAC CHAPTER 213 AND 30 TAC CHAPTER 217, AS APPLICABLE. WHENEVER TCEQ AND CITY OF LEANDER SPECIFICATION CONFLICT, THE MORE STRINGENT SHALL APPLY.

38. MANHOLES SHALL BE COATED PER CITY OF AUSTIN SPL WW-511 (RAVEN 405 OR SPRAYWALL). 39. DENSITY TESTING FOR TRENCH BACKFILL LOCATED WITHIN THE LIMITS OF THE PAVED AREA IS TO BE DONE IN 12" LIFTS EVERY 500' AND AT LEAST ONCE PER LINE SEGMENT 40. ALL GRAVITY WASTEWATER MAINS TO BE TESTED BY CAMERA AND PAID FOR BY THE CONTRACTOR. CAMERA TESTING FOR WASTEWATER LINES IN ROADWAY SHALL OCCUR BEFORE PAVING. CONTRACTOR SHALL PROVIDE THE CITY WITH A DVD COPY OF THE FULL CAMERA

INSPECTION 41. RECLAIMED AND RECYCLED WATER LINE SHALL BE CONSTRUCTED OF "PURPLE PIPE." ALI RECLAIMED AND RECYCLED WATER VALVE COVERS SHALL BE SQUARE AND PAINTED PURPLE.

STREET AND DRAINAGE NOTES:

1. ALL SIDEWALKS SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT. THE CITY OF LEANDER HAS NOT REVIEWED THESE PLANS FOR COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT, OR ANY OTHER ACCESSIBILITY LEGISLATION, AND DOES NOT WARRANTY OR APPROVE THESE PLANS FOR ANY ACCESSIBILITY STANDARDS

2. PRIOR TO ACCEPTANCE THE ENGINEER SHALL SUBMIT DOCUMENTATION THAT THE IMPROVEMENTS WERE INSPECTED BY TDLR OR A REGISTERED ACCESSIBLITY SPECIALIST (RAS) AND ARE IN COMPLIANCE WITH THE REQUIREMENTS OF THE TABA.

3. CONTRACTOR SHALL PROVIDE QUALITY TESTING FOR ALL INFRASTRUCTURES TO BE ACCEPTED AND MAINTAINED BY THE CITY OF LEANDER AFTER COMPLETION. THE CONTRACTOR SHALL NOTIFY THE CITY OF LEANDER ENGINEERING DEPARTMENT AT 528-2700 NO LESS THAN 48 HOURS PRIOR TO ANY TESTING.

4. BACKFILL BEHIND THE CURB SHALL BE COMPACTED TO OBTAIN A MINIMUM OF 95% MAXIMUM DENSITY TO WITHIN 6" OF TOP OF CURB. MATERIAL USED SHALL BE PRIMARILY GRANULAR WITH NO ROCKS LARGER THAN 6" IN THE GREATEST DIMENSION. THE REMAINING 6" SHALL BE CLEAN TOPSOIL FREE FROM ALL CLODS AND SUITABLE FOR SUSTAINING PLANT LIFE

5. A MINIMUM OF 6" OF TOPSOIL SHALL BE PLACED BETWEEN THE CURB AND RIGHT-OF-WAY AND IN ALL DRAINAGE CHANNELS EXCEPT CHANNELS CUT IN STABLE ROCK. 6. DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT, INCLUDING GAS, ELECTRIC TELEPHONE, CABLE TV, ETC., SHALL BE A MINIMUM OF 36" BELOW SUBGRADE.

7. STREET RIGHT-OF-WAY SHALL BE GRADED AT A SLOPE OF 1/4" PER FOOT TOWARD THE CURB UNLESS OTHERWISE INDICATED. HOWEVER, IN NO CASE SHALL THE WIDTH OF RIGHT-OF-WAY AT 1/4" PER FOOT SLOPE BE LESS THAN 10 FEET UNLESS A SPECIFIC REQUEST FOR AN ALTERNATE GRADING SCHEME IS MADE TO AND ACCEPTED BY THE CITY OF LEANDER PUBLIC WORKS DEPARTMENT.

8. BARRICADES BUILT TO THE CITY OF LEANDER STANDARDS SHALL BE ERECTED ON ALL DEAD-END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB AND PUBLIC SAFETY. 9. ALL REINFORCED CONCRETE PIPE SHALL BE MINIMUM CLASS III OF TONGUE AND GROOVE OR O-RING JOINT DESIGN.

10. THE CONTRACTOR IS TO NOTIFY THE ENGINEERING INSPECTOR 48 HOURS PRIOR TO THE FOLLOWING TESTING: PROOF ROLLING SUB-GRADE AND EVERY LIFT OF ROADWAY EMBANKMENT, IN-PLACE DENSITY TESTING OF EVERY BASE COURSE, AND ASPHALT CORES. ALL OF THIS TESTING MUST BE WITNESSED BY A CITY OF LEANDER REPRESENTATIVE.

11. THE CONTRACTOR MUST PROVIDE A PNEUMATIC TRUCK PER TXDOT SPEC FOR PROOF ROLLING. 12. AT INTERSECTIONS WHICH HAVE VALLEY DRAINAGE, THE CROWNS OF THE INTERSECTING STREETS WILL CULMINATE IN A DISTANCE OF 40 FEET FROM INTERSECTING CURB LINE UNLESS OTHERWISE NOTED.

13. AT THE INTERSECTION OF TWO 44' STREETS OR LARGER, THE CROWNS OF THE INTERSECTING STREETS WILL CULMINATE IN A DISTANCE OF 40 FEET FROM INTERSECTING CURB LINE UNLESS OTHERWISE NOTED.

14. A CURB LAYDOWN IS REQUIRED AT ALL POINTS WHERE THE PROPOSED SIDEWALK INTERSECTS THE CURB.

15. ALL STRIPING, WITH THE EXCEPTION OF STOP BARS, CROSS WALKS, WORDS AND ARROWS, IS TO BE TYPE II (WATER BASED). STOP BARS, CROSS WALKS, WORDS AND ARROWS REQUIRE TYPE I THERMOPLASTIC.

16. MANHOLE FRAMES, COVERS, VALVES, CLEAN-OUTS, ETC. SHALL BE RAISED TO GRADE PRIOR TO FINAL PAVEMENT CONSTRUCTION. 17. CONTRACTOR SHALL NOTIFY THE LEANDER ENGINEERING DEPARTMENT AT 528-2700 AT LEAST 48 HOURS PRIOR TO THE INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE

EASEMENT OR STREET ROW. THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S ROW MUST BE APPROVED PRIOR TO THE START OF BACKFILL OPERATIONS. 18. A STOP BAR SHALL BE PLACED AT ALL STOP SIGN LOCATIONS.

19. A MINIMUM OF SEVEN DAYS OF CURE TIME IS REQUIRED FOR HMAC PRIOR TO THE INTRODUCTION OF PUBLIC VEHICULAR TRAFFIC TO ANY STREETS.

WATER.

20. THE GEOTECHNICAL ENGINEER SHALL INSPECT THE SUBGRADE FOR COMPLIANCE WITH THE DESIGN ASSUMPTIONS MADE DURING PREPARATION OF THE SOILS REPORT. ANY ADJUSTMENTS THAT ARE REQUIRED SHALL BE MADE THROUGH REVISIONS OF THE CONSTRUCTION PLANS.

21. GEOTECHNICAL INVESTIGATION INFORMATION AND PAVEMENT RECOMMENDATIONS WERE PROVIDED BY BRUAN INTERTEC. PAVEMENT RECOMMENDATIONS ARE SHOWN ON SHEET 16

TRENCH SAFETY NOTES:

1. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT ARE DESCRIBED IN ITEM 509S "TRENCH SAFETY SYSTEMS" OF THE CITY OF AUSTIN STANDARD SPECIFICATIONS AND SHALL BE IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U.S. OCCUPATION SAFETY AND HEALTH ADMINISTRATION REGULATIONS. GRADING NOTES

1. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT TO ALLOW ANY PONDING OF

2. THE CONTRACTOR SHALL CONSTRUCT EARTHEN EMBANKMENTS WITH SLOPES NO STEEPER THAN 3:1 AND COMPACT SOIL TO 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD SPECIFICATIONS.

3. AREAS OF SOIL DISTURBANCE ARE LIMITED TO GRADING AND IMPROVEMENTS SHOWN. ALL OTHER AREAS WILL NOT BE DISTURBED.

> THE CITY OF LEANDER STANDARD CONSTRUCTION NOTES SHALL APPLY AND TAKE PRECEDENCE. FOR INSTANCES WHERE THEY CONFLICT WITH KIMLEY-HORN GENERAL NOTES OR APPLICABLE TCEQ REQUIREMENTS, THEN THE MORE RESTRICTIVE SHALL APPLY.




NOTIFY THE ENGINEER

- ENCIRCLING THE AREA WITH AN APPROPRIATE BARRIER.
- ALL TIMES FOR ALL INGRESS/EGRESS
- REMOVED IMMEDIATELY RESULT OF THE CONSTRUCTION, AS REQUESTED BY OWNER AND CITY. AT A MINIMUM, THIS SHOULD OCCUR ONCE PER DAY FOR THE
- OFF-SITE ROADWAYS. STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP BMP.
- PLANS, THEN THE CONTRACTOR SHALL ARRANGE FOR AN APPROPRIATE DESIGN TO BE PROVIDED.
- 22.CONTRACTOR SHALL FOLLOW GOOD HOUSEKEEPING PRACTICES DURING CONSTRUCTION, ALWAYS CLEANING UP DIRT, LOOSE MATERIAL, AND TRASH AS CONSTRUCTION PROGRESSES. PAVEMENT, OR A UNIFORM PERENNIAL VEGETATIVE COVER.
- CONSTRUCTION SHALL BE DREDGED, AND THE SEDIMENT GENERATED BY THE PROJECT SHALL BE REMOVED AND DISPOSED IN ACCORDANCE WITH APPLICABLE REGULATIONS.
- STORM WATER DISCHARGE AUTHORIZATION POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000
- RECEIVING DISCHARGE FROM THE SITE. 4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF
- BY THE TCEQ AND EPA (E.G. NOI).
- 6. A COPY OF THE SWPPP, INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATIONS, AND ANY REVISIONS, SHALL BE SUBMITTED TO
- THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.

- AND REMOVED FROM THE SITE
- PROCESS FOR THE REMOVAL OF THEIR FACILITIES.

- IMPLEMENTING THE DEMOLITION PLAN a. ENVIRONMENTAL SITE ASSESSMENT PROVIDED BY THE OWNER. . ASBESTOS BUILDING INSPECTION REPORT(S) PROVIDED BY THE OWNER, c. GEOTECHNICAL REPORT PROVIDED BY THE OWNER.
- d. OTHER REPORTS THAT ARE APPLICABLE AND AVAILABLE. 5 CONTRACTOR SHALL CONTACT THE OWNER TO VERIEV WHETHER ADDITIONAL REPORTS OR AMENDMENTS TO THE ABOVE CITED
- STARTING ANY WORK ON THE SITE.

- SHOWING ALL ITEMS THAT WILL NEED TO BE DEMOLISHED AND REMOVED. FOUNDATIONS OR WALLS. THAT ARE ALSO TO BE REMOVED.
- ANY DISCREPANCIES
- 2. CONTRACTOR SHALL OBTAIN ANY REQUIRED GRADING PERMITS FROM THE CITY ELEVATION.
- 4. PROPOSED SPOT ELEVATIONS AND CONTOURS OUTSIDE THE PAVEMENT ARE TO TOP OF FINISHED GRADE. DISCREPANCY. ALL FINISHED GRADES SHALL TRANSITION UNIFORMLY BETWEEN THE FINISHED ELEVATIONS SHOWN
- PAVEMENT SECTION
- 3. NO REPRESENTATIONS OF EARTHWORK QUANTITIES OR SITE BALANCE ARE MADE BY THESE PLANS. THE CONTRACTOR SHAL SUBSEQUENT ADDENDA.
- CONTRACTOR AT NO ADDITIONAL EXPENSE
- REQUIREMENTS.
- GRADE CONTROL POINTS RELATED TO EARTHWORK. 13. CONTRACTOR TO DISPOSE OF ALL EXCESS EXCAVATION MATERIALS IN A MANNER THAT ADHERES TO LOCAL, STATE AND FEDERAL THE RECEIVING LANDOWNER'S APPROVAL TO DO SO.
- 14. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF TOPSOIL AT THE COMPLETION OF FINE GRADING. CONTRACTOR
- DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. REASON OR ANY LENGTH OF TIME, UNLESS THESE PLANS SPECIFICALLY INDICATE THIS IS REQUIRED. 17. TEMPORARY CULVERTS MAY BE REQUIRED IN SOME LOCATIONS TO CONVEY RUN-OFF.
- 18. REFER TO DIMENSION CONTROL PLAN, AND PLAT FOR HORIZONTAL DIMENSIONS. PI ACEMENT
- AGENCY
- CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS.
- IN THE BUILDING PAD.
- FLATWORK AD JACENT TO THE BUILDING. IF NONE IS CURRENTLY EXISTING. SPRINKLING WATER. OR BY OTHER MEANS APPROVED BY THE CITY. AT NO ADDITIONAL COST TO THE OWNER.
- INFORMATION IN THE FIELD THAT AFFECT THE GRADING PLAN TO THE CIVIL ENGINEER. PRESERVATION PLAN BY THE LANDSCAPE ARCHITECT PRIOR TO COMMENCING THE WORK.

EFFECTIVELY CONTROL EROSION AND PREVENT SEDIMENTATION FROM WASHING OFF THE SITE, THEN THE CONTRACTOR SHALL

11. OFF-SITE SOIL BORROW. SPOIL, AND STORAGE AREAS (IF APPLICABLE) ARE CONSIDERED AS PART OF THE PROJECT SITE AND MUST ALSO COMPLY WITH THE EROSION CONTROL REQUIREMENTS FOR THIS PROJECT. THIS INCLUDES THE INSTALLATION OF BMP'S TO CONTROL EROSION AND SEDIMENTATION AND THE ESTABLISHMENT OF PERMANENT GROUND COVER ON DISTURBED AREAS PRIOR TO FINAL APPROVAL OF THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP AND EROSION CONTROL PLAN TO INCLUDE BMPS FOR ANY OFF-SITE THAT ARE NOT ANTICIPATED OR SHOWN ON THE EROSION CONTROL PLAN. 12. ALL STAGING, STOCKPILES, SPOIL, AND STORAGE SHALL BE LOCATED SUCH THAT THEY WILL NOT ADVERSELY AFFECT STORM WATER QUALITY. PROTECTIVE MEASURES SHALL BE PROVIDED IF NEEDED TO ACCOMPLISH THIS REQUIREMENT, SUCH AS COVERING OR

13. CONTRACTORS SHALL INSPECT ALL EROSION CONTROL DEVICES, BMPS, DISTURBED AREAS, AND VEHICLE ENTRY AND EXIT AREAS WEEKLY AND WITHIN 24 HOURS OF ALL RAINFALL EVENTS OF 0.5 INCHES OR GREATER. AND KEEP A RECORD OF THIS INSPECTION IN THE SWPPP BOOKLET IF APPLICABLE. TO VERIFY THAT THE DEVICES AND EROSION CONTROL PLAN ARE FUNCTIONING PROPERLY 14. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT ALL PRIMARY POINTS OF ACCESS IN ACCORDANCE WITH CITY SPECIFICATIONS. CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION TRAFFIC USES THE STABILIZED ENTRANCE AT

15. SITE ENTRY AND EXITS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING AND FLOWING OF SEDIMENT AND 16. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL SILT AND DEBRIS FROM THE AFFECTED OFF-SITE ROADWAYS THAT ARE A

17. WHEN WASHING OF VEHICLES IS REQUIRED TO REMOVE SEDIMENT PRIOR TO EXITING THE SITE, IT SHALL BE DONE IN AN AREA

18. CONTRACTOR SHALL INSTALL A TEMPORARY SEDIMENT BASIN FOR ANY ON-SITE DRAINAGE AREAS THAT ARE GREATER THAN 10 ACRES, PER TCEQ AND CITY STANDARDS. IF NO ENGINEERING DESIGN HAS BEEN PROVIDED FOR A SEDIMENTATION BASIN ON THESE

19 ALL FINES IMPOSED FOR SEDIMENT OR DIRT DISCHARGED FROM THE SITE SHALL BE PAID BY THE RESPONSIBLE CONTRACTOR 20. WHEN SEDIMENT OR DIRT HAS CLOGGED THE CONSTRUCTION ENTRANCE VOID SPACES BETWEEN STONES OR DIRT IS BEING TRACKED ONTO A ROADWAY, THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASH-DOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL SEDIMENTATION. PERIODIC RE-GRADING OR NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFECTIVENESS OF THE CONSTRUCTION ENTRANCE. 21. TEMPORARY SEEDING OR OTHER APPROVED STABILIZATION SHALL BE INITIATED WITHIN 14 DAYS OF THE LAST DISTURBANCE OF ANY AREA, UNLESS ADDITIONAL CONSTRUCTION IN THE AREA IS EXPECTED WITHIN 21 DAYS OF THE LAST DISTURBANCE.

23. UPON COMPLETION OF FINE GRADING, ALL SURFACES OF DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED. STABILIZATION IS ACHIEVED WHEN THE AREA IS EITHER COVERED BY PERMANENT IMPERVIOUS STRUCTURES, SUCH AS BUILDINGS, SIDEWALK, 24.AT THE CONCLUSION OF THE PROJECT, ALL INLETS, DRAIN PIPE, CHANNELS, DRAINAGEWAYS AND BORROW DITCHES AFFECTED BY THE

CONTRACTOR SHALL COMPLY WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION REQUIREMENTS 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS

3. THE CONTRACTOR SHALL ENSURE THAT ALL PRIMARY OPERATORS SUBMIT A NOI TO TCEQ AT LEAST SEVEN DAYS PRIOR TO COMMENCING CONSTRUCTION (IF APPLICABLE), OR IF UTILIZING ELECTRONIC SUBMITTAL, PRIOR TO COMMENCING CONSTRUCTION. ALL PRIMARY OPERATORS SHALL PROVIDE A COPY OF THE SIGNED NOI TO THE OPERATOR OF ANY MS4 (TYPICALLY THE CITY)

APPLICABLE, INCLUDING POSTING SITE NOTICE, INSPECTIONS, DOCUMENTATION, AND SUBMISSION OF ANY INFORMATION REQUIRED ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICES RELATED TO THE SWPPP SHALL SIGN THE REQUIRED CONTRACTOR CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS SPECIFIED IN THE SWPPP.

THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION. 7. A NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO TCEQ BY ANY PRIMARY OPERATOR WITHIN 30 DAYS AFTER ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND A UNIFORM VEGETATIVE COVER HAS BEEN ESTABLISHED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY STRUCTURES, A TRANSFER OF OPERATIONAL CONTROL HAS OCCURRED, OR THE OPERATOR HAS OBTAINED ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT. A COPY OF THE NOT SHALL BE PROVIDED TO

. KH IS NOT RESPONSIBLE FOR THE MEANS AND METHODS EMPLOYED BY THE CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS PRELIMINARY DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACT THAT ARE TO BE DEMOLISHED

2. KH DOES NOT WARRANT OR REPRESENT THAT THE PLAN. WHICH WAS PREPARED BASED ON SURVEY AND UTILITY INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY, OR THAT THE UTILITIES SHOWN CAN BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING ITS OWN SITE RECONNAISSANCE TO SCOPE ITS WORK AND TO CONFIRM WITH THE OWNERS OF IMPROVEMENTS AND UTILITIES THE ABILITY AND 3. THIS PLAN IS INTENDED TO GIVE A GENERAL GUIDE TO THE CONTRACTOR, NOTHING MORE. THE GOAL OF THE DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT. REMOVAL OR PRESERVATION OF IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL ARE THE RESPONSIBILITY OF THE CONTRACTOR. 4. CONTRACTOR IS STRONGLY CAUTIONED TO REVIEW THE FOLLOWING REPORTS DESCRIBING SITE CONDITIONS PRIOR TO BIDDING AND

REPORTS HAVE BEEN PREPARED AND TO OBTAIN/REVIEW/AND COMPLY WITH THE RECOMMENDATION OF SUCH STUDIES PRIOR TO

6. CONTRACTOR SHALL COMPLY WITH ALL LOCAL STATE AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO REVIEW THE SITE DETERMINE THE APPLICABLE REGULATIONS RECEIVE THE REGULERED PERMITS AND ALITHORIZATIONS AND COMPLY . KH DOES NOT REPRESENT THAT THE REPORTS AND SURVEYS REFERENCED ABOVE ARE ACCURATE, COMPLETE, OR COMPREHENSIVE 8. SURFACE PAVEMENT INDICATED MAY OVERLAY OTHER HIDDEN STRUCTURES, SUCH AS ADDITIONAL LAYERS OF PAVEMENT

1. THE CONTRACTOR AND GRADING SUBCONTRACTOR SHALL VERIFY THE SUITABILITY OF EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE START OF CONSTRUCTION. THE CIVIL ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF

3. UNLESS OTHERWISE NOTED, PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN IN PAVED AREA REFLECT TOP OF PAVEMENT SURFACE. IN LOCATIONS ALONG A CURB LINE, ADD 6-INCHES (OR THE HEIGHT OF THE CURB) TO THE PAVING GRADE FOR TOP OF CURB

5. PROPOSED CONTOURS ARE APPROXIMATE. PROPOSED SPOT ELEVATIONS AND DESIGNATED GRADIENT ARE TO BE USED IN CASE OF

7. CONTOURS AND SPOT GRADES SHOWN ARE ELEVATIONS OF TOP OF THE FINISHED SURFACE. WHEN PERFORMING THE GRADING OPERATIONS, THE CONTRACTOR SHALL PROVIDE AN APPROPRIATE ELEVATION HOLD-DOWN ALLOWANCE FOR THE THICKNESS OF PAVEMENT SIDEWALK TOPSOIL MULCH STONE LANDSCAPING RIP-RAP AND ALL OTHER SURFACE MATERIALS THAT WILL CONTRIBUTE TO THE TOP OF FINISHED GRADE. FOR EXAMPLE, THE LIMITS OF EARTHWORK IN PAVED AREAS IS THE BOTTOM OF THE

PROVIDE THEIR OWN EARTHWORK CALCULATION TO DETERMINE THEIR CONTRACT QUANTITIES AND COST. ANY SIGNIFICANT VARIANCE FROM A BALANCED SITE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CIVIL ENGINEER. 9. ALL GRADING AND EARTHWORK SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING

10. ALL EXCAVATION IS UNCLASSIFIED AND SHALL INCLUDE ALL MATERIALS ENCOUNTERED. UNUSABLE EXCAVATED MATERIAL AND ALL WASTE RESULTING FROM SITE CLEARING AND GRUBBING SHALL BE REMOVED FROM THE SITE AND APPROPRIATELY DISPOSED BY THE 11. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START OF GRADING. REFERENCE EROSION CONTROL PLAN, DETAILS, GENERAL NOTES, AND SWPPP FOR ADDITIONAL INFORMATION AND 12.BEFORE ANY EARTHWORK IS PERFORMED, THE CONTRACTOR SHALL STAKE OUT AND MARK THE LIMITS OF THE PROJECT'S PROPERTY LINE AND SITE IMPROVEMENTS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY ENGINEERING AND SURVEYING FOR LINE AND

LAWS AND REGULATIONS. THE CONTRACTOR SHALL KEEP A RECORD OF WHERE EXCESS EXCAVATION WAS DISPOSED, ALONG WITH

SHALL REFER TO LANDSCAPE ARCHITECTURE PLANS FOR SPECIFICATIONS AND REQUIREMENTS FOR TOPSOIL 15. CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING 16.NO EARTHWORK FILL SHALL BE PLACED IN ANY EXISTING DRAINAGE WAY, SWALE, CHANNEL, DITCH, CREEK, OR FLOODPLAIN FOR ANY

19. THE CONTRACTOR SHALL CLEAR AND GRUB THE SITE AND PLACE, COMPACT, AND CONDITION FILL PER THE PROJECT GEOTECHNICAL ENGINEER'S SPECIFICATIONS. THE FILL MATERIAL TO BE USED SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO

20.CONTRACTOR IS RESPONSIBLE FOR ALL SOILS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL SOILS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND SHALL COMPLY WITH CITY STANDARD SPECIFICATIONS AND THE GEOTECHNICAL REPORT. SOILS TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING SOILS. THE OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR SOILS TESTING. 21.ALL COPIES OF SOILS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING

22.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE SOILS, THAT THE WORK 23. THE SCOPE OF WORK FOR CIVIL IMPROVEMENT SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT AND STRUCTURAL PLANS AND SPECIFICATIONS FILL, CONDITIONING, AND PREPARATION

24.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO

OF THE PROPOSED BUILDING(S) DURING GRADING OPERATIONS AND IN THE FINAL CONDITION. IF THE CONTRACTOR OBSERVES THAT THIS WILL NOT BE ACHIEVED, THE CONTRACTOR SHALL CONTACT THE ENGINEER TO REVIEW THE LOCATION 26. THE CONTRACTOR SHALL TAKE ALL AVAILABLE PRECAUTIONS TO CONTROL DUST. CONTRACTOR SHALL CONTROL DUST BY

27. CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES FOR ANY REQUIRED UTILITY ADJUSTMENTS AND/OR RELOCATIONS NEEDED FOR GRADING OPERATIONS AND TO ACCOMMODATE PROPOSED GRADE, INCLUDING THE UNKNOWN UTILITIES NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL REFER TO THE GENERAL NOTES "OVERALL" SECTION THESE PLANS FOR ADDITIONAL

28.EXISTING TREE LOCATIONS SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL REPORT ANY DISCREPANCIES FOUND 29. CONTRACTOR SHALL FIELD VERIFY ALL PROTECTED TREE LOCATIONS, INDIVIDUAL PROTECTED TREE CRITICAL ROOT ZONES, AND

PROPOSED SITE GRADING, AND NOTIFY THE CIVIL ENGINEER AND LANDSCAPE ARCHITECT OF ANY CONFLICTS WITH THE TREE 30. TREE PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE CITY STANDARD TREE PROTECTION DETAILS AND THE

APPROVED TREE PRESERVATION PLANS BY THE LANDSCAPE ARCHITECT. 31.CONTRACTOR SHALL REFER TO THE LANDSCAPING AND TREE PRESERVATIONS PLANS FOR ALL INFORMATION AND DETAILS

- REGARDING EXISTING TREES TO BE REMOVED AND PRESERVED. 32.NO TREE SHALL BE REMOVED UNLESS A TREE REMOVAL PERMIT HAS BEEN ISSUED BY THE CITY, OR CITY HAS OTHERWISE CONFIRMED IN WRITING THAT ONE IS NOT NEEDED FOR THE TREE(S)
- 33.NO TREE SHALL BE REMOVED OR DAMAGED WITHOUT PRIOR AUTHORIZATION OF THE OWNER OR OWNER'S REPRESENTATIVE EXISTING TREES SHALL BE PRESERVED WHENEVER POSSIBLE AND GRADING IMPACT TO THEM HELD TO A MINIMUM 34.AFTER PLACEMENT OF SUBGRADE AND PRIOR TO PLACEMENT OF PAVEMENT, CONTRACTOR SHALL TEST AND OBSERVE PAVEMENT AREAS FOR EVIDENCE OF PONDING AND INADEQUATE SLOPE FOR DRAINAGE. ALL AREAS SHALL ADEQUATELY DRAIN TOWARDS THE INTENDED STRUCTURE TO CONVEY STORMWATER RUNOFF. CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND ENGINEER IF ANY
- AREAS OF POOR DRAINAGE ARE DISCOVERED. 35. CONTRACTOR FIELD ADJUSTMENT OF PROPOSED SPOT GRADES IS ALLOWED, IF THE APPROVAL OF THE CIVIL ENGINEER IS OBTAINED.
- . RETAINING WALLS SHOWN ARE FOR SITE GRADING PURPOSES ONLY, AND INCLUDE ONLY LOCATION AND SURFACE SPOT ELEVATIONS AT THE TOP AND BOTTOM OF THE WALL. 2. RETAINING WALL TYPE OR SYSTEM SHALL BE SELECTED BY THE OWNER
- DIRT ONTO OFF-SITE ROADWAYS. ALL SEDIMENT AND DIRT FROM THE SITE THAT IS DEPOSITED ONTO AN OFF-SITE ROADWAY SHALL BE 3. RETAINING WALL DESIGN SHALL BE PROVIDED BY OTHERS AND SHALL FIT IN THE WALL ZONE OR LOCATION SHOWN ON THESE PLANS. STRUCTURAL DESIGN AND PERMITTING OF RETAINING WALLS, RAILINGS, AND OTHER WALL SAFETY DEVICES SHALL BE PERFORMED BY A LICENSED ENGINEER AND ARE NOT PART OF THIS PLAN SET. 4. RETAINING WALL DESIGN SHALL MEET THE INTENT OF THE GRADING PLAN AND SHALL ACCOUNT FOR ANY INFLUENCE ON ADJACENT
 - BUILDING FOUNDATIONS, UTILITIES, PROPERTY LINES AND OTHER CONSTRUCTABILITY NOTES. RETAINING WALL ENGINEER SHALL CONSULT THESE PLANS AND THE GEOTECHNICAL REPORT FOR POTENTIAL CONFLICTS.
 - 1. ALL PAVING MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THESE PLANS. THE CITY STANDARD DETAILS AND SPECIFICATIONS, THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA, AND COMMONLY ACCEPTED CONSTRUCTION
 - STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION/DETAIL SHALL BE FOLLOWED 2. ALL PRIVATE ON-SITE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST
 - EDITION), INCLUDING ALL ADDENDA. 3. ALL FIRELANE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARDS AND DETAILS. IF THESE ARE DIFFERENT THAN THOSE IN THE GEOTECHNICAL REPORT. THEN THE MORE RESTRICTIVE SHALL BE FOLLOWED
 - 4. ALL PUBLIC PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS 5. CONTRACTOR IS RESPONSIBLE FOR ALL PAVING AND PAVING SUBGRADE TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL PAVING AND PAVING SUBGRADE TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING PAVING AND SUBGRADE. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR PAVING AND PAVING SUBGRADE TESTING
 - 6. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE PAVING AND PAVING SUBGRADE, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 7. DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO
 - FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING. 8. CURB RAMPS ALONG PUBLIC STREETS AND IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED BASED ON THE CITY STANDARD
 - CONSTRUCTION DETAIL AND SPECIFICATIONS 9. PRIVATE CURB RAMPS ON THE SITE (I.E. OUTSIDE PUBLIC STREET RIGHT-OF-WAY) SHALL CONFORM TO ADA AND TAS STANDARDS AND SHALL HAVE A DETECTABLE WARNING SURFACE THAT IS FULL WIDTH AND FULL DEPTH OF THE CURB RAMP. NOT INCLUDING FLARES 10. ALL ACCESSIBLE RAMPS, CURB RAMPS, STRIPING, AND PAVEMENT MARKINGS SHALL CONFORM TO ADA AND TAS STANDARDS, LATEST
 - EDITION. 11. ANY COMPONENTS OF THE PROJECT SUBJECT TO RESIDENTIAL USE SHALL ALSO CONFORM TO THE FAIR HOUSING ACT, AND COMPLY WITH THE FAIR HOUSING ACT DESIGN MANUAL BY THE US DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT. 12 CONTRACTOR SHALL CONSTRUCT PROPOSED PAVEMENT TO MATCH EXISTING PAVEMENT WITH A SMOOTH, FLUSH, CONNECTION
 - 13.CONTRACTOR SHALL FURNISH AND INSTALL ALL PAVEMENT MARKINGS FOR FIRE LANES, PARKING STALLS, HANDICAPPED PARKING SYMBOLS, AND MISCELLANEOUS STRIPING WITHIN PARKING LOT AND AROUND BUILDING AS SHOWN ON THE PLANS. ALL PAINT AND PAVEMENT MARKINGS SHALL ADHERE TO CITY AND OWNER STANDARDS. 14. REFER TO GEOTECHNICAL REPORT FOR PAVING JOINT LAYOUT PLAN REQUIREMENTS FOR PRIVATE PAVEMENT.
 - 15. REFER TO CITY STANDARD DETAILS AND SPECIFICATIONS FOR JOINT LAYOUT PLAN REQUIREMENTS FOR PUBLIC PAVEMENT 16. ALL REINFORCING STEEL SHALL CONFORM TO THE GEOTECHNICAL REPORT, CITY STANDARDS, AND ASTM A-615, GRADE 60, AND SHALL BE SUPPORTED BY BAR CHAIRS. CONTRACTOR SHALL USE THE MORE STRINGENT OF THE CITY AND GEOTECHNICAL STANDARDS. 17. ALL JOINTS SHALL EXTEND THROUGH THE CURB. 18. THE MINIMUM LENGTH OF OFFSET JOINTS AT RADIUS POINTS SHALL BE 2 FEET.
 - 19. CONTRACTOR SHALL SUBMIT A JOINTING PLAN TO THE ENGINEER AND OWNER PRIOR TO BEGINNING ANY OF THE PAVING WORK. 20.ALL SAWCUTS SHALL BE FULL DEPTH FOR PAVEMENT REMOVAL AND CONNECTION TO EXISTING PAVEMENT. 21.FIRE LANES SHALL BE MARKED AND LABELED AS A FIRELANE PER CITY STANDARDS
 - 22.UNLESS THE PLANS SPECIFICALLY DICTATE TO THE CONTRARY, ON-SITE AND OTHER DIRECTIONAL SIGNS SHALL BE ORIENTED SO THEY ARE READILY VISIBLE TO THE ONCOMING TRAFFIC FOR WHICH THEY ARE INTENDED. 23.CONTRACTOR IS RESPONSIBLE FOR INSTALLING NECESSARY CONDUIT FOR LIGHTING. IRRIGATION. ETC. PRIOR TO PLACEMENT OF PAVEMENT. ALL CONSTRUCTION DOCUMENTS (CIVIL, MEP, LANDSCAPE, IRRIGATION, AND ARCHITECT) SHALL BE CONSULTED. 24.BEFORE PLACING PAVEMENT, CONTRACTOR SHALL VERIFY THAT SUITABLE ACCESSIBLE PEDESTRIAN ROUTES (PER ADA, TAS, AND
 - FHA) EXIST TO AND FROM EVERY DOOR AND ALONG SIDEWALKS, ACCESSIBLE PARKING SPACES, ACCESS AISLES, AND ACCESSIBLE ROUTES. IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL. IN NO CASE SHALL SIDEWALK CROSS SLOPE EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPE EXCEED 5.0 PERCENT. ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL NOT EXCEED 2.0 PERCENT SLOPE IN ANY DIRECTION
 - 25. CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA/TAS SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA AND TAS SLOPE COMPLIANCE ISSUES.

- 1. ALL STORM SEWER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS
- 2. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE STORM SEWER 3. THE CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING STORM
- SEWER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY STORM SEWER, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.
- 4. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF CURB INLETS AND GRATE INLETS AND ALL UTILITIES CROSSING THE STORM SEWER. 5. FLOW LINE, TOP-OF-CURB, RIM, THROAT, AND GRATE ELEVATIONS OF PROPOSED INLETS SHALL BE VERIFIED WITH THE GRADING PLAN NO
- AND FIELD CONDITIONS PRIOR TO THEIR INSTALLATION. 6. ALL PUBLIC STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD
- DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 7. ALL PRIVATE STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE.
- CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. ALL PVC TO RCP CONNECTIONS AND ALL STORM PIPE CONNECTIONS ENTERING STRUCTURES OR OTHER STORM PIPES SHALL HAVE A CONCRETE COLLAR AND BE GROUTED TO ASSURE THE CONNECTION IS WATERTIGHT.
- 9. ALL PUBLIC STORM SEWER LINES SHALL BE MINIMUM CLASS III RCP. PRIVATE STORM SEWER LINES 18-INCHES AND GREATER SHALL BE CLASS III RCP OR OTHER APPROVED MATERIAL 10. WHERE COVER EXCEEDS 20-FEET OR IS LESS THAN 2-FEET, CLASS IV RCP SHALL BE USED.
- 11.IF CONTRACTOR PROPOSES TO USE HDPE OR PVC IN LIEU OF RCP FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPE AND PVC SHALL BE WATERTIGHT. 12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL STORM SEWER LINES.
- 13. EMBEDMENT FOR ALL STORM SEWER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS.
- 14. ALL WYE CONNECTIONS AND PIPE BENDS ARE TO BE PREFABRICATED AND INSTALLED PER MANUFACTURERS SPECIFICATIONS. 15. USE 4 FOOT JOINTS WITH BEVELED ENDS IF RADIUS OF STORM SEWER IS LESS THAN 100 FEET. 16. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN. PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 17. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

ANY PONDS THAT ARE INTENDED TO HOLD WATER INDEFINITELY SHALL BE CONSTRUCTED WATERTIGHT

- 2. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR POND LINER SPECIFICATIONS
- 3. A GEOTECHNICAL ENGINEER SHALL REVIEW AND APPROVE ALL POND LINER MATERIAL, PLACEMENT PROCEDURES, AND PROVIDE TESTING TO ENSURE THE POND LINER MATERIAL PLACED IS WATERTIGHT.
- 4. STORM SEWER PIPES AND HEADWALLS THAT CONNECT TO A POND INTENDED TO HOLD WATER INDEFINITELY SHALL BE INSTALLED WITH WATERTIGHT JOINTS TO AT LEAST 1-FOOT ABOVE THE NORMAL POOL WATER SURFACE ELEVATION. 5. ANY GRAVEL OR OTHER PERVIOUS EMBEDMENT AROUND PIPES OR OUTFALL STRUCTURES NEAR THE POND SHALL BE ELIMINATED FOR TCEQ
- AT LEAST 20-FEET FROM THE POND SO NO ROUTE FOR WATER TO LEAK THROUGH THE EMBEDMENT MATERIAL IS PROVIDED. BACKFILL IN THESE AREAS SHALL BE OF IMPERVIOUS MATERIAL. 6. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE WATER LEVEL FOLLOWING COMPLETION AND FILLING OF THE POND
- SHALL BE MONITORED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO OBSERVE WATER INFLOW, OUTFLOW, AND CALCULATE EVAPORATION TO VERIFY THAT THE POND IS WATERTIGHT 7. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE POND WATER LEVEL SHALL ALSO BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION SO THAT IT REMAINS FULL TO ITS DESIGN WATER LEVEL, AND IS NOT LOWERED.

WATER AND WASTEWATER

AS THIS MAY DRY-OUT THE POND LINER AND RISK ITS WATERTIGHT PROPERTIES.

- 1. ALL WATER AND WASTEWATER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS 2. CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER AND WASTEWATER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY WATER OR WASTEWATER CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.
- 3. CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITY SERVICES ENTERING THE BUILDING. 4. THE CONTRACTOR SHALL FIELD VERIFY THE ELEVATION OF ALL UTILITY CROSSINGS PRIOR TO THE INSTALLATION OF ANY PIPE
- 5. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE WATER AND WASTEWATER IMPROVEMENTS. 6. ALL PUBLIC WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.
- 7. ALL PRIVATE WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. FIRE SPRINKLER LINES SHALL BE DESIGNED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR, AND COMPLY TO THE APPLICABLE CODES AND INSPECTIONS REQUIRED. THESE PLANS WERE PREPARED WITHOUT THE BENEFIT OF THE FIRE SPRINKLER
- DESIGN. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES. 9. EMBEDMENT FOR ALL WATER AND WASTEWATER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS 10. CONTRACTOR SHALL TAKE REQUIRED SANITARY PRECAUTIONS, FOLLOWING ANY CITY, TCEQ, AND AWWA STANDARDS, TO KEEP
- WATER PIPE AND FITTINGS CLEAN AND CAPPED AT TIMES WHEN INSTALLATION IS NOT IN PROGRESS 11. CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL WATER AND WASTEWATER LINES
- 25.CONTRACTOR SHALL ENSURE THAT SUFFICIENT POSITIVE SLOPE AWAY FROM THE BUILDING, UNLESS NOTED OTHERWISE 12. ALL WATER AND WASTEWATER SERVICES SHALL TERMINATE 5-FEET OUTSIDE THE BUILDING, UNLESS NOTED OTHERWISE 13. CONTRACTOR SHALL COMPLY WITH CITY REQUIREMENTS FOR WATER AND WASTEWATER SERVICE DISRUPTIONS AND THE AMOUNT OF PRIOR NOTICE THAT IS REQUIRED, AND SHALL COORDINATE DIRECTLY WITH THE APPROPRIATE CITY DEPARTMENT.
 - 14. CONTRACTOR SHALL SEQUENCE WATER AND WASTEWATER CONSTRUCTION TO AVOID INTERRUPTION OF SERVICE TO SURROUNDING PROPERTIES 15. CONTRACTOR SHALL MAINTAIN WATER SERVICE AND WASTEWATER SERVICE TO ALL CUSTOMERS THROUGHOUT CONSTRUCTION (IF
 - NECESSARY, BY USE OF TEMPORARY METHODS APPROVED BY THE CITY AND OWNER). THIS WORK SHALL BE CONSIDERED SUBSIDIARY TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 16. THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL WATER AND WASTEWATER LINES CROSSING THE PROJECT. THE CONTRACTOR
 - SHALL REPAIR ALL DAMAGED LINES IMMEDIATELY. ALL REPAIRS OF EXISTING WATER MAINS, WATER SERVICES, SEWER MAINS, AND SANITARY SEWER SERVICES ARE SUBSIDIARY TO THE WORK, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 17. VALVE ADJUSTMENTS SHALL BE CONSTRUCTED SUCH THAT THE COVERS ARE AT FINISHED SURFACE GRADE OF THE PROPOSED PAVEMENT
 - 18. THE ENDS OF ALL EXISTING WATER MAINS THAT ARE CUT, BUT NOT REMOVED, SHALL BE PLUGGED AND ABANDONED IN PLACE. THIS WORK SHALL BE CONSIDERED AS A SUBSIDIARY COST TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.



FINAL PLAT OF SHOPS AT BAGDAD SQUARE 4.672 ACRES TRACT OF LAND DESCRIBED IN DEED RECORDED UNDER DOCUMENT NUMBER 2021122871 SITUATED IN THE ELIJAH D HARMOND SURVEY, ABSTRACT NUMBER 6 IN WILLIAMSON COUNTY, TEXAS



OWNER:

BAGDAD RD LEANDER LLC PRAVEEN GUDURU 3000 POLAR LN SUITE 404 CEDAR PARK, TX 78613 (973) 723-4862

SURVEYOR:

RICHARD G. LANTIS, R.P.L.S. THE ALTUM GROUP 10421 GULFDALE STREET SAN ANTONIO, TX 78216 (760) 346-4750

ENGINEER:

MICHEAL T. DOGGETT, P.E. KIMLEY-HORN 260 EAST DAVIS STREET, SUITE 100 McKINNEY, TX 75069 (214) 803-1099

LAND USE:

TOTAL ACREAGE: 4.672 AC TOTAL NUMBER OF BLOCKS: 1 TOTAL COMMERCIAL LOT: 1

SURVEY:

ELIJAH D HARMOND SURVEY, ABSTRACT NO. 6

INDEX	SHEET
COVER SHEET	1 of 3
FINAL PLAT LAYOUT	2 of 3
NOTES & SIGNATURES	3 of 3





TEXAS FIRM NUMBER 10194593

NO.	DATE	R	REVISIONS		BY
DRA	WN BY: VE	}	SURVEYED BY:	KT	
DAT	E: APRIL 14	, 2023	APPROVED BY:	RGL	
PRO	JECT NO.	C1631	SHEET 1 OF 3		

04 OF 29



FINAL PLAT OF SHOPS AT BAGDAD SQUARE 4.672 ACRES TRACT OF LAND DESCRIBED IN DEED RECORDED UNDER DOCUMENT NUMBER 2021122871 SITUATED IN THE ELIJAH D HARMOND SURVEY, ABSTRACT NUMBER 6 IN WILLIAMSON COUNTY, TEXAS

LEGEND:

0	SET 1/2" IRON ROD SET IRON WITH AN ORANGE PLASTIC CAP STAMPED "TAG 10194593"
٠	FOUND IRON ROD
	ADJOINER LINE
	ATLAS 14 100 YEAR
	OVERALL BOUNDARY
	EASEMENT LINE
	FLOOD ZONE LINE
	ROAD CENTERLINE

ABBREVIATIONS:

- R.O.W. RIGHT-OF-WAY
- O.P.R.W.C.T. OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS
- WD WARRANTY DEED
- GWD GENERAL WARRANTY DEED
- SWD SPECIAL WARRANTY DEED
- W/VL DEED WITH VENDOR'S LIEN
- SQ. FT. SQUARE FEET

BLANKET EASEMENTS

- 1. ELECTRIC UTILITY EASEMENT PEDERNALES ELECTIC COOPERTIVE, INC. VOLUME 635, PAGE 323 - O.P.R.W.C.T. (NOT SHOWN ON PLAT)
- 2. ELECTRIC UTILITY EASEMENT PEDERNALES ELECTIC COOPERTIVE, INC. DOCUMENT NUMBER 2008086509 - O.P.R.W.C.T. (NOT SHOWN ON PLAT)
- 3. WATERLINE EASEMENT LEANDER WATER SUPPLY CORPORATION VOLUME 734, PAGE 656 - O.P.R.W.C.T. (NOT SHOWN ON PLAT)
- 4. WATERLINE EASEMENT LEANDER WATER SUPPLY CORPORATION VOLUME 939, PAGE 682 - O.P.R.W.C.T (NOT SHOWN ON PLAT)



10421 Gulfdale Street San Antonio, TX 78216 t.760.346.4750 f. 760.340.0089 TheAltumGroup.com

ENGINEERING | PLANNING | SURVEY | ENVIRONMENTAL

TEXAS FIRM NUMBER 10194593	

NO.	DATE	R	EVISIONS		ΒY
DRA	WN BY: VE	3	SURVEYED BY:	KT	-
DATE	E: APRIL 14	1, 2023	APPROVED BY:	RGL	
PRO	JECT NO.	C1631	SHEET 2 OF 3		

05 OF 29

STATE OF TEXAS § COUNTY OF WILLIAMSON §	FINAL PLA SHOPS AT BAGD
THAT PRAVEEN GUDURU AS THE OWNER OF BAGDAD RD LEANDER LLC, BEING THAT CERTAIN 4.672 ACRE TRACT RECORDED IN DOCUMENT NUMBER 2021122871 OF THE OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS, DC CERTIFY THAT THERE ARE NO LIEN HOLDERS AND DEDICATES TO THE PUBLIC FOREVER USE OF ALL ADDITIONAL ALLEYS, EASEMENTS, PARKS, AND ALL OTHER LANDS INTENDED FOR PUBLIC DEDICATION, OR WHEN THE SUBDIV PROVISION FOR PERPETUAL MAINTENANCE THEREOF, TO THE INHABITANTS OF THE SUBDIVISION AS SHOWN HE KNOWN AS SHOPS AT BAGDAD SQUARE.	OF LAND DES HEREBY4.672 ACRES TRAROW, STREETS, VIDER HAS MADE REON TO BEDESCRIBED IN DEED R DOCUMENT NUMBI SITUATED IN THE ELIJ SURVEY. ABSTRAC
PRAVEEN GUDURUDATE3000 POLAR LN SUITE 404EDAR PARK, TX 78613	IN WILLIAMSON CO
STATE OF TEXAS § COUNTY OF WILLIAMSON §	GENER
BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED PRAVEEN GUDURU, KNOWN THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THA THE SAME FOR THE PURPOSES AND CONSIDERATION THEREIN EXPRESSED, IN THE CAPACITY THEREIN STATED.	1. TH AT HE EXECUTED 2. TH
GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS DAY OF20	3. NC CC
NOTARY PUBLIC-STATE OF	4. A E TH
PRINTED NAME:	5. NC TH
MY COMMISSION EXPIRES:	6. PR
	OF
STATE OF TEXAS § COUNTY OF WILLIAMSON §	7. AL 8. IN
THAT I, MICHAEL T. DOGGETT, AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS TO PRACTICE THE PROFESSION OF ENGINEERING, AND DO HEREBY STATE THAT THIS PLAT CONFORMS WITH THE APPLICABLE ORD	
THE CITY OF LEANDER, TEXAS	9. NC
	10. BU RE
MICHEAL T. DOGGETT, P.E. DATE REGISTERED PROFESSIONAL ENGINEER 98628 STATE OF TEXAS	11. SIE INE DR
STATE OF TEXAS § COUNTY OF WILLIAMSON §	DC Wł
THAT I, RICHARD G. LANTIS, AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS TO PRACTICE THE	12. AL
ON-THE-GROUND SURVEYING AND HEREBY STATE THAT TPREPARED THIS PLAT FROM AN ACTUAL AND ACC ON-THE-GROUND SURVEY OF THE LAND AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPER UNDER MY PERSONAL SUPERVISION. IN ACCORDANCE WITH ALL CITY OF LEANDER ORDINANCE AND CODES. AND	LY PLACED D THAT ALL 14. AP
EXISTING EASEMENTS OF RECORD AS FOUND ON THE TITLE POLICY PROVIDED BY STEWART TITLE GUARANTY C NO.1233561 ISSUED APRIL 22, 2021 HAVE BEEN SHOWN OR NOTED HERON.	OMPANY, FILE 15. AL
CISTES T	AL 16 NC
REGISTERED PROFESSIONAL LAND SURVEYOR REGISTRATION NO. 6908 10421 GULFDALE STREET SAN ANTONIO, TX 78216 TEXAS FIRM NO. 10194593	LO
APPROVED THIS THE DAY OF, 20 A.D. AT A PUBLIC MEETING OF THE PLANNING AND ZONING COMMISSION OF THE CITY OF LEANDER, TEXAS AND AUTHORIZED TO BE FILED FOR RECORD BY THE COUNTY CLERK OF WILLIAMSON COUNTY.	
EMILY TRUMAN, P.E., CITY ENGINEER ATTEST: DARA CRABTREE, CITY SECRETARY	STATE OF TEXAS § COUNTY OF WILLIAMSON §
CITY OF LEANDER, TEXAS CITY OF LEANDER, TEXAS BASED UPON THE ABOVE REPRESENTATIONS OF THE ENGINEER OR SURVEYOR WHOSE SEAL IS AFFIXED HERET AND AFTER A REVIEW OF THE SURVEY AS REPRESENTED BY THE SAID ENGINEER OR SURVEYOR, I FIND THAT TH PLAT COMPLIES WITH THE REQUIREMENTS OF THE EDWARDS AQUIFER REGULATIONS FOR WILLIAMSON COUNTY AND THE WILLIAMSON COUNTY ON-SITE SEWERAGE FACILITY REGULATIONS. THIS CERTIFICATION IS MADE SOLELY UPON SUCH REPRESENTATIONS AND SHOULD NOT BE RELIED UPON FOR VERIFICATIONS OF THE FACTS ALLEGED. THE WILLIAMSON COUNTY AND CITIES HEALTH DISTRICT (WCCHD) AND WILLIAMSON COUNTY DISCLAIM ANY RESPONSIBILITY TO ANY MEMBER OF THE PUBLIC FOR INDEPENDENT VERIFICATION OF THE REPRESENTATIONS, FACTUAL OR OTHERWISE, CONTAINED IN THE PLAT AND THE DOCUMENTS ASSOCIATED WIT	I, NANCY RISTER, CLERK O THE FOREGOING INSTRUM FILED FOR RECORD IN MY O'CLOCK,M., AND O'CLOCK,M., IN THE C ` TO CERTIFY WHICH, WITNE MY OFFICE IN GEORGETOV NANCY RISTER, CLERK COL
J. TERRON EVERTSON, PE, DR, CFM DATE COUNTY ENGINEER	BY:

AT OF DAD SQUARE ACT OF LAND RECORDED UNDER SER 2021122871 JAH D HARMOND CT NUMBER 6 OUNTY, TEXAS

RAL PLAT NOTES:

HIS SUBDIVISION IS WHOLLY CONTAINED WITHIN THE CURRENT CORPORATE LIMITS OF THE CITY OF LEANDER, TEXAS.

HIS SUBDIVISION IS WHOLLY CONTAINED WITH THE EXTRA TERRITORIAL JURISDICTION OF THE CITY OF LEANDER, TEXAS.

O LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO THE CITY OF LEANDER WATER DISTRIBUTION AND WASTEWATER OLLECTION FACILITIES.

BUILDING PERMIT IS REQUIRED FROM THE CITY OF LEANDER PRIOR TO CONSTRUCTION OF ANY BUILDING OR SITE IMPROVEMENTS ON ANY LOT IN HIS SUBDIVISION.

O BUILDINGS, FENCES, LANDSCAPING OR OTHER STRUCTURES ARE PERMITTED WITHIN DRAINAGE EASEMENTS SHOWN EXCEPT AS APPROVED BY HE CITY OF LEANDER PUBLIC WORKS DEPARTMENT.

ROPERTY OWNER SHALL PROVIDE FOR ACCESS TO DRAINAGE EASEMENTS AS MAY BE NECESSARY AND SHALL NOT PROHIBIT ACCESS BY THE CITY F LEANDER.

LL EASEMENTS ON PRIVATE PROPERTY SHALL BE MAINTAINED BY THE PROPERTY OWNER OR HIS OR HER ASSIGNS.

ADDITION TO THE EASEMENT SHOWN HEREON, A TEN (10') FOOT WIDE PUBLIC UTILITY EASEMENT IS DEDICATED ALONG AND ADJACENT TO ALL GHT-OF-WAY AND A TWO AND A HALF (2.5') FOOT WIDE PUBLIC UTILITY EASEMENT IS DEDICATED ALONG ALL SIDE LOT LINES.

O PORTION OF THIS TRACT IS WITHIN A FLOOD HAZARD AREA AS SHOWN ON THE FLOOD INSURANCE RATE MAP PANEL # 48491C0455F FOR ILLIAMSON CO., EFFECTIVE DECEMBER 20, 2019.

JILDING SETBACKS NOT SHOWN HEREON SHALL COMPLY WITH THE MOST CURRENT ZONING ORDINANCE OF THE CITY OF LEANDER. ADDITIONAL ESIDENTIAL GARAGE SETBACKS MAY BE REQUIRED AS LISTED IN THE CURRENT ZONING ORDINANCE.

DEWALK SHALL BE INSTALLED ON THE EAST SIDE OF BAGDAD ROAD. THOSE SIDEWALKS NOT ABUTTING A RESIDENTIAL, COMMERCIAL OR DUSTRIAL LOT (INCLUDING SIDEWALKS ALONG STREET FRONTAGES OF LOTS PROPOSED FOR SCHOOLS, CHURCHES, PARK LOTS, DETENTION LOTS, RAINAGE LOTS, LANDSCAPE LOTS, OR SIMILAR LOTS), SIDEWALKS ON ARTERIAL STREETS TO WHICH ACCESS IS PROHIBITED, SIDEWALKS ON OUBLE FRONTAGE LOTS ON THE SIDE TO WHICH ACCESS IS PROHIBITED, AND ALL SIDEWALKS ON SAFE SCHOOL ROUTES SHALL BE INSTALLED 'HEN THE ADJOINING STREET IS CONSTRUCTED.

LL UTILITY LINES MUST BE LOCATED UNDERGROUND.

HIS PLAT CONFORMS TO THE PRELIMINARY PLAT APPROVED BY THE PLANNING & ZONING COMMISSION ON APRIL 14, 2023.

PPROVAL OF THIS FINAL PLAT DOES NOT CONSTITUTE THE APPROVAL OF VARIANCES OR WAIVERS TO ORDINANCE REQUIREMENTS.

LL DRIVE LANES, FIRE LANES, AND DRIVEWAYS WITHIN THIS SUBDIVISION SHALL PROVIDE FOR RECIPROCAL ACCESS FOR INGRESS AND EGRESS TO LL OTHER LOTS WITHIN THE SUBDIVISION AND TO ADJACENT PROPERTIES.

D DRIVEWAY SHALL BE CONSTRUCTED CLOSER THAN 50' OR 60% OF PARCEL FRONTAGE, WHICHEVER IS LESS, TO THE ROW OF AN INTERSECTING DCAL OR COLLECTOR STREET OR 100' OR 60% OF PARCEL FRONTAGE, WHICHEVER IS LESS, TO THE ROW OF AN INTERSECTING ARTERIAL STREET.

2

OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT MENT IN WRITING, WITH ITS CERTIFICATE OF AUTHENTICATION WAS OFFICE ON THE _____ DAY OF _____, 20____ A.D., AT D DULY RECORDED THIS THE DAY OF _____ 20___ A.D., AT ____ OFFICIAL PUBLIC RECORDS OF SAID COUNTY IN INSTRUMENT NO.

ESS MY HAND AND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT WN, TEXAS, THE DATE LAST SHOWN ABOVE WRITTEN.

OUNTY COURT OF WILLIAMSON COUNTY, TEXAS

_____, DEPUTY



10421 Gulfdale Street San Antonio, TX 78216 t.760.346.4750 f. 760.340.0089 TheAltumGroup.com

ENGINEERING | PLANNING | SURVEY | ENVIRONMENTAL TEXAS FIRM NUMBER 10194593

NO.	DATE	R	REVISIONS		BY	
						∣⊲
						р М
						Ġ
DRA	WN BY: VE	3	SURVEYED BY:	KT		5003
DATI	E: APRIL 14	4, 2023	APPROVED BY:	RGL		6/61
PRO	JECT NO.	C1631	SHEET 3 OF 3			· 4

06 OF 29



ES Vricinity Map: -S xSurv:xBrdr:xEstet -SAVED 4/18/2023 10:50 AM TED BY LOPEZ, GARY 4/18/2023 11:00 AM TPD BY LOPEZ, GARY 4/18/2023 11:00 AM TPATH %KIMLEY-UNDK COMYTZ_MKNMKN_CIVIL\064585101-LEANDER BAGE NAME



xStrm : 4/18/202 LOPEZ, \KIMLEY EROSIO IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH DWG NAME



XBrar 4/18/202 LOPEZ, \KIMLE IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH DWG NAME



CITY OF AUSTIN WATERCHED PROTECTION DEPARTMENT	SILT FENCE	
Muy b. My 9/1/2011 ADOPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	STANDARD NO. 642S-1





X5trm : X5trv : XUtil : XBrdr : X5lte 418:203 10:22 AM SY LOPEZ, GARY 418:203 11:01 AM I WIMLEY-HORNZ MKNMIKN_CIVIL\064585101-LEANDER BAGDAD RETAIL\CAD\PLAN I WIMLEY-HORN.Z0M17X_MKNMIKN_CIVIL\064585101-LEANDER BAGDAD RETAIL\CAD\PLAN

IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH



IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH DWG NAME

		DF	RAINAGE ARE	A TABLE		
NAGE EA D.	AREA (ac)	RUNOFF COEFFICIENT "C"	TIME OF CONCENTRATION (minutes)	RAINFALL INTENSITY "I"100 (in/hr)	TOTAL FLOW Q100 (cfs)	COLLECTION POINT
١	4.66	0.54	15	10.21	25.7	EX. SPILLWAY
5	2.41	0.54	15	10.21	13.3	EX. SPILLWAY
	1					



xDAM : xStrm : xS 4/18/2023 10:24 AM LOPEZ, GARY 4/18, \\KIMLEY-HORN.CC DRAINAGE AREA M IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH DWG NAME

				2	4	0		DATE BY
-				GRAF	40' PHIC SCALE 40'	80'		REVISIONS
			A-1 30.32 AC 37.542	ARE. Q100 PRO DRA FLOV	A DESIGNATOR (A IN ACRES) FLOW IN CFS PERTY LINE INAGE DIVIDE W DIRECTION		OTD V, TX 75069	20 No.
			721 721	EXIS	TING 1-FOOT CC	ONTOUR ATION PATH	Kimley-HORN AND ASSOCIATES 260 EAST DAVIS STREET, SUITE 100, MCKINNE	PHONE: 469-301-2580 FAX: 972-239-38 WWW.KIMLEY-HORN.COM TX F-928
DRAINAGE AREA NO. A1	AREA (ac) 0.58	RUNOFF COEFFICIENT "C" 0.97	DRAINAGE ARE	EA TABLE RAINFALL INTENSITY "I"100 (in/hr) 15.00	TOTAL FLOW Q100 (cfs) 8.4	COLLECTION POINT CURB INLET	KHA PROJECT 064585101 DATE MARCH 2023 ALE AS SHOWN SALE AS SHOWN CALE AS	Tawn BY ADB 25 24 ADB 26 26 ADB 26 AD
B1 B2 B3 B4 B5 C-1 DET POND EX. B OFFSITE-1 OFFSITE-2 SED POND	0.93 0.05 0.39 1.22 0.28 0.30 0.30 2.41 0.13 0.41 0.09	0.97 0.97 0.97 0.97 0.97 0.97 0.97 0.97	5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	15.24 15.24 15.24 15.00 15.00 15.00 15.24 10.21 15.24 15.24 15.24 15.00	13.7 0.8 5.8 17.8 4.0 4.3 4.4 13.3 1.9 6.0 1.3	GRATE INLET GRATE INLET GRATE INLET CURB INLET CURB INLET WYE INLET CURB INLET CURB INLET CURB INLET SEDIMENT POND	E SHOPS AT DAD SQUARE	EANDER, TEXAS
				Know w Ca	what's belo	DW. you dig.	BAGI	
							DRAINAGE AREA MAP	
							SHEET NUMB	^{ER} 29

IMAGES XBrdr XREFS XBrdr LAST SAVED 4/18/2023 10:26 AM PLOTTED BY LOPEZ, GARY 4/18/2023 11:02 AM PLOTTED BY UCPEZ, GARY 4/18/2023 11:02 AM DWG PATH WKIMLEY-HORN.COMTX MKNMKN_CIVIL/064585101-LEANDER BAGDAD RETAIL/CADIPLA DWG NAME DRAINAGE CALCULATIONS.DWG , [DRAINAGE CALCULATIONS]

						1								S		AIN HYDRA			IS TABLE				1				
FROM	ТО			NAGE AREA				TOTAL						Q5			Q	PIPE		Cf		GL				3 CALCULA	
		LENGTH				UUEFF.	MENTAL	"CA"								BY PASS (CES)			n			U/S Elev		V2(001)	V1^2/2g	V2/2/2g	<u> </u>
1	2	3	A	5	6	7	8	<u> </u>	10	11	<u> </u>	13	14	15	16	17	18	(11)	20	21	<u>22</u>	<u>23</u>	24	25	26	27	28
		0	•	0	0		0	0	10		12	10		10	10	17	10	10	20	<i>L</i> 1		20	21	20	20		
1+11 42	1+33 54	22 12	A1	0 580	0 580	0.85	0 493	0 493	10.00	0.00	10 00	5 99	10 74	2 95	5 30	0.00	5 30	15	0.013	0.0100	1016 57	1016 79	0.00	5 29	0.00	0 44	1 25
1+08.87	1+11.42	2.55	,		0.580	0.85		0.493	10.00	0.07	10.07	5.98	10.72	-	-	0.00	5.28	15	0.013	0.0100	1016.39	1016 42	5.29	5.28	0.44	0.43	0.35
0+32.11	1+08.87	76.76			0.580	0.85		0.493	10.00	0.08	10.08	5.98	10.72	_	-	0.00	5.28	15	0.013	0.0100	1015.63	1016.39	5.28	5.28	0.43	0.43	0.35
0+17.56	0+32.11	14.55			0.580	0.85		0.493	10.00	0.32	10.32	5.92	10.64	-	-	0.00	5.24	15	0.013	0.0100	1015.63	1015.77	5.28	5.24	0.43	0.43	0.35
0+16.15	0+17.56	1.41			0.580	0.85		0.493	10.00	0.37	10.37	5.91	10.62	-	-	0.00	5.24	15	0.013	0.0100	1015.47	1015.48	5.24	5.23	0.43	0.43	0.35
0+08.58	0+16.15	7.57			0.580	0.85		0.493	10.00	0.37	10.37	5.91	10.62	-	-	0.00	5.24	27	0.013	0.0100	1015.35	1015.42	5.23	4.99	0.43	0.39	0.10
0+00.00	0+08.58	8.58	B1-B5	2.890	3.470	0.85	2.457	2.950	10.00	0.40	10.40	5.91	10.61	14.51	26.07	0.00	31.30	27	0.013	0.0100	1014.54	1014.63	4.99	7.87	0.39	0.96	0.75
		I I								1					1										1	L	
LINE B																											
5+46.62	5+60.84	14.22	B5	0.280	0.280	0.85	0.238	0.238	10.00	0.00	10.00	5.99	10.74	1.43	2.56	0.00	2.56	18	0.013	0.0006	1018.26	1018.26	0.00	1.45	0.00	0.03	1.25
5+35.62	5+46.62	11.00			0.280	0.85		0.238	10.00	0.16	10.16	5.96	10.69	-	-	0.00	2.54	18	0.013	0.0006	1018.15	1018.16	1.45	1.44	0.03	0.03	0.35
3+48.65	5+35.62	186.97			0.280	0.85		0.238	10.00	0.29	10.29	5.93	10.65	-	-	0.00	2.53	18	0.013	0.0060	1016.93	1018.05	1.44	3.49	0.03	0.19	0.35
3+47.13	3+48.65	1.52			0.280	0.85		0.238	10.00	1.18	11.18	5.75	10.36	-	-	0.00	2.47	24	0.013	0.0001	1018.92	1018.92	3.49	0.78	0.19	0.01	0.10
3+43.56	3+47.13	3.57			0.280	0.85		0.238	10.00	1.22	11.22	5.74	10.35	-	-	0.00	2.46	24	0.013	0.0001	1018.82	1018.82	0.78	0.78	0.01	0.01	0.35
2+94.90	3+43.56	48.66	B4	1.220	1.500	0.85	1.037	1.275	10.00	1.29	11.29	5.73	10.32	5.94	10.71	0.00	13.17	24	0.013	0.0034	1018.45	1018.62	0.78	4.19	0.01	0.27	0.75
2+09.76	2+94.90	85.14			1.500	0.85		1.275	10.00	1.49	11.49	5.69	10.27	-	-	0.00	13.09	24	0.013	0.0033	1018.07	1018.35	4.19	4.17	0.27	0.27	0.35
1+60.15	2+09.76	49.61	B3	0.390	1.890	0.85	0.332	1.607	10.00	1.83	11.83	5.63	10.16	1.87	3.37	0.00	16.46	24	0.013	0.0053	1017.59	1017.85	4.17	5.24	0.27	0.43	0.50
1+37.59	1+60.15	22.56	B2	0.050	1.940	0.85	0.043	1.649	10.00	1.98	11.98	5.60	10.12	0.24	0.43	0.00	16.89	24	0.013	0.0056	1017.13	1017.25	5.24	5.38	0.43	0.45	0.75
0+61.79	1+37.59	75.80			1.940	0.85		1.649	10.00	2.05	12.05	5.59	10.09	-	-	0.00	16.65	24	0.013	0.0054	1016.56	1016.97	5.38	5.30	0.45	0.44	0.35
0+56.79	0+61.79	5.00			1.940	0.85		1.649	10.00	2.29	12.29	5.54	10.03	-	-	0.00	16.53	27	0.013	0.0028	1016.32	1016.34	5.30	4.16	0.44	0.27	0.10
0+11.07	0+56.79	45.72	B1	0.910	2.850	0.85	0.774	2.423	10.00	2.31	12.31	5.54	10.02	4.29	7.75	0.00	24.28	27	0.013	0.0060	1015.62	1015.89	4.16	6.11	0.27	0.58	0.75
0+00.00	0+11.07	11.07			2.850	0.85		2.423	10.00	2.44	12.44	5.52	9.98	-	-	0.00	24.18	27	0.013	0.0060	1015.35	1015.41	6.11	6.08	0.58	0.57	0.35
LAT B1						_			-				_							_		_	_		_		
0+27.47	0+35.42	7.95	B1	0.910	0.910	0.85	0.774	0.774	10.00	0.00	10.00	5.99	10.74	4.63	8.31	0.00	8.31	15	0.013	0.0165	1017.28	1017.41	0.00	6.77	0.00	0.71	1.25
0+06.29	0+27.47	21.18			0.910	0.85		0.774	10.00	0.02	10.02	5.99	10.74	-	-	0.00	8.30	15	0.013	0.0165	1016.68	1017.03	6.77	6.77	0.71	0.71	0.35
0+00.00	0+06.29	6.29			0.910	0.85		0.774	10.00	0.07	10.07	5.98	10.72	-	-	0.00	8.29	15	0.013	0.0165	1016.32	1016.43	6.77	6.76	0.71	0.71	0.35
	1																										
LAT B2		г – г			-	-	1	1			1	1	-	1	1					1		1	I		1		
0+34.80	0+85.00	50.20	B2	0.050	0.050	0.85	0.043	0.043	10.00	0.00	10.00	5.99	10.74	0.25	0.46	0.00	0.46	12	0.010	0.0382	1016.51	1018.43	0.00	5.63	0.00	0.49	1.25
0+00.00	0+34.80	34.80			0.050	0.85		0.043	10.00	0.15	10.15	5.96	10.69	-	-	0.00	0.45	12	0.010	0.0001	1017.59	1017.59	5.63	0.58	0.49	0.01	0.35
 .																											
LAT B3	0.01-0			4 6 6 6				4.00-	(0.00		40.00									0.0.00	4044 = 1						
0+00.00	0+24.58	24.58	B4	1.220	1.220	0.85	1.037	1.037	10.00	0.00	10.00	5.99	10.74	6.21	11.14	0.00	11.14	15	0.013	0.0432	1014.54	1018.14	0.00	11.13	0.00	1.93	1.25
	1																										
							0.055	0.055	40.00	0.00	40.00	5 00	40.74	4 50		0.00				0.0400	404451	4044 77	0.00	4.40	0.00		
0+00.00	0+21.19	21.19	C1	0.300	0.300	0.85	0.255	0.255	10.00	0.00	10.00	5.99	10.74	1.53	2.74	0.00	2.74	15	0.013	0.0100	1014.54	1014.75	0.00	4.46	0.00	0.31	1.25

NVERTELEV T/C COMMENTS (FT) (FT) (FT) (FT) (FT) 1014.68 1021.77 45° BEND 31<014.52 1014.68 1021.77 45° BEND 33<1015.77 1015.78 1021.30 46° BEND 33<1015.77 1015.78 1021.46 46° WYE B3 21<015.45 1017.40 1023.28 46° BEND B3 31<015.77 1021.57 HO21.86 46° BEND B3 31<014.51 1014.65 1021.46 46° WYE B3 31<014.51 1014.65
N INVERT ELEV. T/C COMMENTS (FR) (FR) (FR) (FR) (FR) 32 33 34 (FR) (FR) (FR) 32 33 34 (FR) (FR) (FR) (FR) 32 33 34 (FR) (FR) (FR) (FR) 32 33 34 (FR) (FR) (FR) (FR) 31 1014.54 1021.87 45° BEND (FR) (FR) (FR) 33 1014.52 1014.63 1021.77 45° BEND (FR) (FR) (FR) 33 1014.52 1012.13 45° BEND (FR) (FR) (FR) 33 1015.77 1015.78 1021.96 PIPE SIZE CHANGE (FR) (FR) (FR) 21 1015.75 1015.77 1021.47 45° BEND (FR) (FR) (FR) (FR) 33 1014.51 1015.77 1021.47 45° BEND (F
32 33 34 44 1015.47 1015.69 1021.94 CURB INLET 57 1015.44 1015.47 1021.85 45° BEND 99 1014.68 1015.44 1021.77 45° BEND 33 1014.53 1021.77 45° BEND 33 1014.52 1014.68 1021.77 45° BEND 33 1014.52 1014.53 1021.27 PIPE SIZE CHANGE 55 1013.35 1013.44 1021.13 45° BEND 77 1015.45 1017.46 1023.28 45° BEND 55 1016.28 1017.40 1023.28 45° BEND 56 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 52 1015.45 1015.77 1021.47 45° BEND 51 1015.77 1021.47 45° BEND 9802 52 1015.45 1015.75 1022.20 CURB INLET 9802 52 1015.75 1021.46 45° WYE B2 31 51 1014.94 1022.43 GRATE INLET 9802<
44 1015.47 1015.69 1021.94 CURB INLET 77 1015.44 1015.47 1021.85 45° BEND 99 1014.68 1015.44 1021.77 45° BEND 33 1014.52 1014.68 1021.77 45° BEND 33 1014.52 1014.53 1021.27 PIPE SIZE CHANGE 35 1013.35 1013.44 1021.13 45° WYE B 46 1017.46 1017.46 1023.18 45° BEND 55 1016.28 1017.40 1023.28 45° BEND 33 1015.77 1015.75 1021.96 PIPE SIZE CHANGE 20 1015.75 1015.75 1021.47 45° BEND 33 1015.77 1015.78 1021.46 45° WYE B3 32 1015.45 1015.75 1022.08 45° BEND 98628 70 1014.65 1021.85 45° WYE B2 33 1014.06 1014.51 1021.70 45° BEND 70 1013.50 1013.78 1021.85 45° WYE B1 3001.90 <
70 1013.44 1013.47 1021.85 45° BEND 99 1014.68 1015.44 1021.77 45° BEND 33 1014.53 1014.53 1021.30 45° BEND 33 1014.52 1014.68 1021.77 45° BEND 33 1014.52 1014.53 1021.27 PIPE SIZE CHANGE 35 1013.35 1013.44 1021.13 45° WYE, ** B 36 1017.46 1017.40 1023.28 45° BEND 98 33 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 98 31 1015.75 1015.77 1021.47 45° BEND 98 32 1015.75 1015.77 1021.47 45° BEND 98 32 1015.75 1015.75 1021.47 45° BEND 98 98 33 1014.94 1022.43 GRATE INLET 98
33 1014.53 1014.68 1021.77 45° BEND 33 1014.52 1014.53 1021.30 45° BEND 33 1014.52 1014.53 1021.27 PIPE SIZE CHANGE 35 1013.35 1013.44 1021.27 PIPE SIZE CHANGE 35 1013.35 1017.46 1023.28 45° BEND 36 1017.40 1017.46 1023.28 45° BEND 33 1015.77 1015.78 1021.97 MCHAEL 33 1015.77 1015.78 1021.91 45° BEND 32 1015.75 1013.78 1021.47 45° BEND 33 1014.65 1017.40 1023.28 45° WYE, B3 34 1015.75 1021.47 45° BEND 98628 32 1015.45 1021.53 45° WYE, B3 35 1014.94 1022.43 GRATE INLET 98628 33 1014.65 1021.70 45° BEND 98628 36 1013.78 1013.81 1021.23 PIPE SIZE CHANGE 1000000000000000000000000000000000000
17 1013.44 1013.52 1021.27 PIPE SIZE CHANGE 35 1013.35 1013.44 1021.13 45° WYE, ~ B 36 1017.46 1017.55 1022.92 CURB INLET 36 1017.40 1017.46 1023.18 45° BEND 35 1016.28 1017.40 1023.28 45° BEND 33 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 32 1015.75 1015.77 1021.47 45° BEND 32 1015.45 1015.75 1021.53 45° BEND 32 1014.51 1021.53 45° BEND 33 1014.06 1014.51 1022.08 45° WYE, ~ B2 33 1014.06 1014.51 1021.70 45° BEND 32 1013.50 1013.78 1021.85 45° WYE, ~ B1 32 1013.50 1013.78 1021.85 45° WYE, ~ B1 32 1013.50 1013.78 1021.91 45° BEND 32 1013.43 1013.50 1021.91 45° BEND
36 1017.46 1017.55 1022.92 CURB INLET 36 1017.40 1017.46 1023.18 45° BEND 55 1016.28 1017.40 1023.28 45° BEND 33 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 32 1015.75 1015.77 1021.47 45° BEND 32 1015.45 1015.75 1021.46 45° BEND 32 1015.45 1015.75 1021.46 45° BEND 32 1014.94 1015.45 1021.53 45° BEND 33 1014.06 1014.51 1021.70 45° BEND 33 1014.06 1014.51 1021.23 PIPE SIZE CHANGE 32 1013.50 1013.78 1021.85 45° WYE, ** B2 33 1014.06 1014.51 1021.23 PIPE SIZE CHANGE 10 32 1013.50 1013.78 1021.85 45° WYE, ** B1 32 1013.50 1021.91 45° BEND 10 10 32 1013.43 1013.50 1021.91 45° BEND<
36 1017.46 1017.55 1022.92 CURB INLET 26 1017.40 1017.46 1023.18 45° BEND 25 1016.28 1017.40 1023.28 45° BEND 33 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 32 1015.75 1015.77 1021.47 45° BEND 32 1015.45 1015.75 1021.47 45° BEND 32 1014.45 1014.94 1022.43 GRATE INLET 39 1014.51 1014.65 1022.08 45° WYE, B2 33 1014.06 1014.51 1021.70 45° BEND 36 1013.78 1021.85 45° WYE, B1 B1 32 1013.50 1013.78 1021.85 45° WYE, B1 32 1013.50 1013.78 1021.85 45° WYE, B1 32 1013.50 1021.91 45° BEND
26 1017.40 1017.46 1023.18 45° BEND 5 1016.28 1017.40 1023.28 45° BEND 03 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 02 1015.75 1015.77 1021.47 45° BEND 02 1015.45 1015.75 1021.46 45° WYE, B3 15 1014.94 1015.45 1021.53 45° BEND 07 1014.65 1014.94 1022.08 45° WYE, B2 13 1014.06 1014.51 1021.70 45° BEND 06 1013.78 1021.85 45° WYE, B1 B1 02 1013.50 1021.91 45° BEND 1020.85 04 1021.70 45° BEND 1014.94 1021.70 05 1013.78 1021.85 45° WYE, B1 1000000000000000000000000000000000000
03 1015.77 1015.78 1021.96 PIPE SIZE CHANGE 02 1015.75 1015.77 1021.47 45° BEND 03 1015.45 1015.75 1021.46 45° WYE B3 05 1014.94 1015.45 1021.53 45° BEND 07 1014.65 1014.94 1022.43 GRATE INLET 09 1014.51 1014.65 1021.70 45° BEND 04 1013.78 1013.81 1021.23 PIPE SIZE CHANGE 04 1013.78 1013.78 1021.85 45° WYE B1 05 1013.43 1013.50 1021.91 45° BEND
1015.75 1015.77 1021.47 45° BEND 102 1015.45 1015.75 1021.46 45° WYE, *** B3 15 1014.94 1015.45 1021.53 45° BEND 15 1014.65 1014.94 1022.43 GRATE INLET 10 1014.65 1021.70 45° BEND 10 1014.65 1021.70 45° BEND 10 1014.65 1021.70 45° BEND 10 1014.65 1021.23 PIPE SIZE CHANGE 10 1013.78 1021.85 45° WYE, *** B1 10 1013.78 1021.91 45° BEND
1014.94 1015.45 1021.53 45° BEND 07 1014.65 1014.94 1022.43 GRATE INLET 09 1014.51 1014.65 1022.08 45° WYE, *** B2 13 1014.06 1014.51 1021.70 45° BEND 66 1013.78 1013.81 1021.23 PIPE SIZE CHANGE 102 1013.78 1021.85 45° WYE, *** B1 1013.70 1013.78 1021.91 45° BEND 1013.43 1013.50 1021.91 45° BEND
39 1014.51 1014.65 1022.08 45° WYE, B2 3 1014.06 1014.51 1021.70 45° BEND 36 1013.78 1013.81 1021.23 PIPE SIZE CHANGE 32 1013.50 1013.78 1021.91 45° BEND 32 1013.43 1013.50 1021.91 45° BEND
3 1014.06 1014.51 1021.70 45° BEND 36 1013.78 1013.81 1021.23 PIPE SIZE CHANGE 32 1013.50 1013.78 1021.85 45° WYE, 56 B1 32 1013.43 1013.50 1021.91 45° BEND 1000 Horizon 1000 Horizon 33 1013.43 1013.50 1021.91 45° BEND 1000 Horizon 1000 Horizon
32 1013.50 1013.78 1021.85 45° WYE, B1 52 1013.43 1013.50 1021.91 45° BEND
7 1013.43 1013.30 1071.31 42, REND AS AS<
30 1015.54 1015.91 1020.38 GRATEINLET
X8 1014.57 1015.54 1020.35 45° BEND X8 1014.28 1014.57 1020.00 45° DEND
0 1014.20 1014.3/ 1020.90 45° BEND
05 1016.35 1018.27 1022.27 GRATE INLET
51 1015.02 1016.35 1022.60 45° BEND
DS 1016.12 1017.18 1021.81 CURB INLET







LENGTH (FEET)	WIDTH (FEET)	TURNAROUNDS REQUIRED
0-150	20	NONE REQUIRED
151-500	20	120-FOOT HAMMERHEAD, 60-FOOT "Y" OR 96-FOOT DIAMETER CUL-DE-SAC
501-750	26	120-FOOT HAMMERHEAD, 60-FOOT "Y" OR 96-FOOT DIAMETER CUL-DE-SAC
OVER 750		SPECIAL APPROVAL REQUIRED

xBrdr : oStm 4/18/2023 10:40 AM LOPEZ, GARY 4/18/ \\KIMLEY-HORN.CO STORM PROFILES.I IMAGES XREFS LAST SAVED PLOTTED BY DWG PATH DWG NAME

FILL TO BE COMPACTED TO 95% STD PROCTOR DENSITY OR PER GEOTECH

xStrm : xSurv : xU 4/18/2023 10:40 AM LOPEZ, GARY 4/18, \KIMLEY-HORN.CC BES FS - SAVED TTED BY B PATH B NAME

DN	POND CA	LCULAT	IONS	
unty:	Leander	Li	do Unusod Collo	
alue:	0.97	H	de Unused Cells	
Area:	4.100		1	
Line:	1009.00		Unhide Cells	
ents:	4			
vent	Q _{max}	WSE	STORAGE (cu-ft)	STORAGE (ac-ft)
	22.60	1012.92	24,371	0.56
	17.04	1012.23	18,185	0.42
	13.84	1011.82	14,671	0.34
	9.25	1011.19	9,686	0.22
	Storm Event	Existing Flow	iSWM Ra	infall Data
		Rate	а	106.00
	100 Year	22.6 cfs	b c	9.460 0.7320
L	TOTAL CFS	TOTAL FLOW	OUTFLOW	STORAGE
(ac)				
0	59.65	17895	6780	11115
0	48.00	28798	13561	15237
0	40.60	36539	1695 <mark>1</mark>	19588
)	35.43	42517	20341	22176
)	28.61	51493	27122	24371
)	24.25	58194	33902	24292
C	21.19	63570	40682	22887
)	18.91	68079	47463	20616
0	11.99	86320	88145	-1825
0	9.07	97981	128827	-30846
)	5.56	120187	250874	-130688
)	3.38	146093	494968	-348876
)	2.05	176755	983156	-806401
Dete	ention Storage	Required (cu	bic feet) =	24,371
			C ()	

Detention Storage Required (acre feet) = 0.56 100 Year Water Surface Elevation =

	Storm Event	Existing Flow	iSWM Ra	infall Data			
		Rate	а	89.00			
	25 Voor	17.04 of o	b	10.160			
	25 fear	17.04 CIS	C	0.7590			
TOTAL	TOTAL CFS	TOTAL FLOW	OUTFLOW	STORAGE			
REA (ac)							
4.100	44.96	13487	5112	8376			
4.100	36.21	21726	10223	11503			
4.100	30.61	27545	12779	14767			
4.100	26.67	32007	15335	16672			
4.100	21.46	38631	20446	18185			
4.100	18. <mark>1</mark> 3	43510	25558	17952			
4.100	15.79	47378	30669	16708			
4.100	14.05	50590	35781	14810			
4.100	8.79	63298	66450	-3152			
4.100	6.59	71206	97119	-25913			
4.100	3.98	85900	189126	-103226			
4.100	2.37	102588	373140	-270553			
4.100	1.41	121883	741169	-619286			
Dete	ention Storage	Required (cubi	c feet) =	18,185			
De	tention Storag	e Required (acr	refeet) =	0.42			
	25 Year W	ater Surface Ele	evation =	1012.23			

	o. – .	Existing Flow	iSWM Ra	infall Data
	Storm Event	Rate	а	77.000
	10 \/a a #	12.04.05	b	10.530
	10 Year	13.84 CIS	C	0.7750
TOTAL	TOTAL CFS	TOTAL FLOW	OUTFLOW	STORAGE
REA (ac)				
4.100	36.55	10965	4153	<mark>681</mark> 2
4.100	29.44	17664	8305	9359
4.100	24.86	22378	10382	11997
4.100	21.65	25976	12458	135 <mark>1</mark> 8
4.100	17.38	31282	16611	14671
4.100	14.65	35157	20763	14393
4.100	12.74	38207	24916	13291
4.100	11.31	40725	29069	11656
4.100	7.02	50548	53984	-3437
4.100	5.24	56559	78900	-22342
4.100	3.13	67556	153648	-86092
4.100	1.85	79838	303143	-223305
4.100	1.09	93838	602134	-508297
Det	ention Storage	Required (cubi	ic feet) =	14,671
De	tention Storag	e Required (acr	refeet) =	0.34
	10 Year W	ater Surface Ele	evation =	1011 82

	Storm Event	Existing Flow	Existing Flow iSWM Rainfall Data Rate a 58.	
	Storm Event	Rate		
		0.25 of a	b	11.270
	2 rear	9.25 CIS	C	0.8050
TOTAL	TOTAL CFS	TOTAL FLOW	OUTFLOW	STORAGE
REA (ac)				
4.100	24.42	7327	2774	4553
4.100	19.68	11811	5547	6263
4.100	16. <mark>61</mark>	14947	6934	8013
4.100	14.43	17322	8321	9000
4.100	11.55	20781	11095	9686
4.100	9.69	23268	13869	9399
4.100	8.40	25198	16642	8556
4.100	7.44	26773	19416	7357
4.100	4.55	32749	36058	-3310
4.100	3.36	36281	52701	-16419
4.100	1.97	42544	102627	-60084
4.100	1.14	49304	202481	-153177
4.100	0.66	56792	402188	-345396
Dete	ention Storage	Required (cubi	c feet) =	9,686
De	tention Storage	e Required (acr	refeet) =	0.22
	2 Year W	ater Surface Ele	evation =	1011.19

Know what's **below. Call** before you dig.

ES =S TED BY PATH NAME

XBrar 4/18/20 LOPEZ \KIMLE

	d Load Deduction for the tetal unstate			Dears 0.07	- <u>-</u>					645851	01 CASE #		
The Require	d Load Reduction for the total project: Calculations	rom RG-348		Pages 3-27 t	o 3-30				R-3, Partial Sedime	ntation Filtration Po	nd Water Quality Co	ontrol Provided/R-Ta	able [
	Degree 2.20 Equation 2.2: $L = 27.2(A \times D)$,				
	Page 3-29 Equation 3.3. $L_M = 27.2(A_N \times P)$						DRAINAGE AREA DA	TA:					
where.	M TOTAL PROJECT = Required TSS	removal resultin	a from the proposed de	evelopment =	80% of incr	eased loa	Drainage Area to Co	ntrol (DA)			4.39	ac.	
intere.	$A_{M} = Net increase$	n impervious are	a for the project	liophion		oucou lou	Drainage Area Impe	rvious Cover	+c)		81.00%	%	
	P = Average annu	al precipitation i	nches				SOS Required Cantu	re Denth			NO		
								NTROL DATA SEDI	MENTATION /FILTRAT				
Site Data:	Determine Required Load Removal Based on the Entire Project						25-year Peak Flow R	ate to Control (02	5)		30.21	cfs	
	County = Williamson						100-year Peak Flow	Rate to Control (Q	100)		34.04	cfs	
	Total project area included in plan $* = 4.66$	acres											
Total pos	st-development impervious area within the limits of the plan [*] = 3.55	acres					Water Quality Volur	ne (Provided)			20265.75	5 cf	
Total po	Total post-development impervious cover fraction * = 0.76	40103					Sedimentation Pond	d Area (Provided)			1247	sf	
	P = 32	inches					Sedimentation Pond	l Volume (Provide	d)		6547	cf	
							Filtration Pond Area	(Provided)			1738	sf	
	LM TOTAL PROJECT = 3090	lbs.					Filtration Pond Volu	me (Provided)			10428	cf	
							Water Quality Eleva	tion (Provided)			1019.00	ft. (MSL)	
Nur	ber of drainage basins / outfalls areas leaving the plan area = 1	•					Elevation of Splitter	/Overflow Weir (F	rovided)		1019.00	ft. (MSL)	
I VUII							Height of Gabion Wa	all/Top of periphe	ral wall (elev) (Provid	ed)	1018.50	ft. (MSL)	
							Top of Sand/Biofiltr	ation Bed Elevatio	n/Floor of Pond (Pro v	vided)	1013.00	ft. (MSL)	
Drainaga Ba	cin Parameters (This information should be provided for each basin):						Maximum Ponding I	Depth above Sand,	Biofiltration Bed (H)		6.00	ft.	
Bramaye Ba	and analistic of the mornation should be provided for each pasin):						Length of Splitter W	eir (Provided)			90	ft.	
	Drainage Basin/Outfall Area No. = A	•					Top of Water Qualit	y Pond/ Top of Wa	II Minimum Required		1019.54	ft. (MSL)	
							Top of Water Qualit	y Pond/ Top of Wa	II (Provided)		1019.65	ft. (MSL)	
	Total drainage basin/outfall area = 4.39	acres					Required Head to Pa	ass Q_{100} ; Assumed	Rectangular Weir w/	C=3.36	0.233	ft.	
Predev	velopment impervious area within drainage basin/outfall area = 0.00	acres					Pond Freeboard Pro	vided to Pass Q_{100}			0.417	ft.	
Post-dev	Velopment impervious area within drainage basin/outfall area = 3.55	acres					Filled Height				6.233	ft.	
Post-develo	opment impervious fraction within drainage basin/outfall area = 0.81	lba					5% of fill Height				0.312	ft.	
	L _{M THIS BASIN} = 3090	IDS.					Capability of Water	Quality Control In	let to Safely Convey 2	25 Yr. Storm			
Indicate the	proposed BMP Code for this basin						Type of Inlet contro				Orifice		
mulcale the							Elevation of Weir/O	rifice Flowline			1013.30	ft. (MSL)	
	Proposed BMP = Sand Filter	•					Head above Inlet/Sp	litter Elevation			5.70	ft.	
	Removal efficiency = 89	percent											
Calculate Ma	aximum TSS Load Removed (L _R) for this Drainage Basin by the select	ed BMP Type.											
							Orifice Type				Rectangul	ar	
	RG-348 Page 3-33 Equation 3.7: $L_R = (BMP \text{ efficien})$	су) х Р х (А _I х З4	4.6 + A _P x 0.54)				Number of orifices				10		
											Н	W	
where:	$A_c = 10$ tai On-Site	drainage area in	the BIMP catchment a	rea			Rectangular orifice of	opening			0.5	1	
	$A_1 = $ Impervious an	ea proposed in tr		a									
	$A_{P} = Pervious area$	remaining in the	BMP catchment area				$C_{r} = orifice coefficie$	nt (use 0.6)			0.60		
	L _R = TSS Load rer	noved from this c	atchment area by the p	proposed BMI	P						5.00	-f-	
							Cinlet (cfs)				54.90	CIS fine	
	$A_{\rm C} = 4.39$	acres									109.798	ips	
	$A_1 = 3.55$	acres					A? Hour Drawdown	Time Orifice Open	ing diameter (inches)	IND DATA:	1.25	lin	
	A _P = 0.84	acres					Filtration Pond Out	et Flowline (ft. (M	(inclies)		1.25	ft (MSL)	
	L _R = 3511	lbs					H. Head over filtrat	ion pond bottom/	owest flowling (refe	ranca R_2 UU/2	8 20	ft	
Calculate Er	ection of Annual Dunoff to Treat the drainage basin / outfall area	•					Drawdown Time CO		min 48 hrs) Ba'd Per	Code	-) 8.20 68.4	hrs	
	action of Annual Runoli to Treat the drainage basin / outail area						Diawdown nine co	A calc. Avg. fiedd		Code	00.4	1113.	
	Desired IM THIS PASIN = 3090	lbs					Sedimentation/Forba	y Pond/Retention	ond/Cistern/Raingar	den			
							Stage (ft msl)	Pond Depth	Cumulative Pond Dept	h Area	Volume C	Cumulative	
	F = 0.88	•					1013.50	0.00	0.00	0.00	0	0	
							1014.00	0.50	0.50	1247.00	312	312	
Calculate Ca	pture Volume required by the BMP Type for this drainage basin / out	all area.	Calculations from RG	-348	Pages 3-3	4 to 3-36	1015.00	1.00	1.50	1247.00	1,247	1,559	
							1016.00	1.00	2.50	1247.00 1247.00	1,24/	2,806 4,053	
		•					1017.00	1.00	4.50	1247.00	1,247	5,300	
	Rainfall Depth = 1.50	Inches					1019.00	1.00	5.50	1247.00	1,247	6,547	
	On-site Water Quality Volume = 15202	cubic feet											
							Filtration/Main Pool P	ond					
							Stage (ft msl)	Pond Depth (ft)	Cumulative Pond Dept	h Area	Volume C	Cumulative	Combin
	Calculations	rom RG-348	Pages 3-36 to 3-37				1013.00	0.00	0.00	1738.00	0.00	0.00	0.
		N					1014.00	1.00	1.00	1738.00	1,738	1,738	2,04
	Off-site area draining to BMP = 0.00	acres					1015.00	1.00	2.00	1738.00	1,738	3,476 5,214	5,03
	OIT-site impervious cover draining to BMP = 0.00	acres					1017.00	1.00	4.00	1738.00	1,738	6,952	8,01 11.0
	$\Omega = \mathbf{U}$						1018.00	1.00	5.00	1738.00	1,738	8,690	13,9
	Off-site Water Quality Volume = 0	cubic feet					1019.00	1.00	6.00	1738.00	1,738	10,428	16,9
	Storage for Sediment = 3040												
Total Car	oture Volume (required water quality volume(s) x 1.20) = 18242	cubic feet											
Filter area fo	Designed as	Required in RG-3	348	Pages 3-58 t	0 3-63								
	9B. Partial Sedimentation and Filtration System												
	Water Quality Volume for combined basins = 18242	cubic feet											
	IVIInimum filter basin area = 1520	square feet											
	Maximum a dimension has in success 2004	oquara faat	For minimum water	denth of 94	feet								
		SUIND											
	Minimum sedimentation basin area = 6081 Minimum sedimentation basin area = 380	square feet	For maximum water	r depth of 8	feet								

DRAINAGE AREA DATA:					
Drainage Area to Control (DA)		4.39	ac.		
Drainage Area Impervious Cover		81.00%			
Capture Depth (CD)		1.110	in		
WATER QUALITY CONTROL CALCULATIONS:		Required		Provided	
The Water Quality Control is to be PARTIAL SEDIME	NTATI	ON FILTRATION			
25-year Peak Flow Rate to Control (Q25)	2	30.21	cfs	54.90	cfs
100-year Peak Flow Rate to Control (Q100)		34.04	cfs		
Water Quality Volume (WQV=CD * DA* 3630)		17689	cf	20266	cf
Maximum Ponding Depth above Sand Bed (H)				6.00	ft
Sedimentation Pond Area					sf
Sedimentation Pond Volume (≥20%WQV)	≥	4053.15	cf	6547	cf
Filtration Pond Area (WQV/(4+1.33*H))	2	1692	sf	1738	sf
Filtration Pond Volume				10428	cf
Water Quality Elevation				1019.00	ft ms
Elevation of Splitter/Overflow Weir	2	1019.00	ft msl	1019.00	ft ms
Height of Gabion Wall		1018.50	ft msl	1018.50	ft ms
Gabion Wall under 6 ft (check)	≤	6.00	ft (max)	5.50	ft
Length of Splitter Weir				90.00	ft
Required Head to Pass Q ₁₀₀		1.00	ft (max)	0.233	ft
Pond Freeboard Provided to Pass Q_{100} \geq 0.312				0.417	ft
48 Hour Drawdown Time Orifice Opening diameter	(inche	es)		1.25	in
Drawdown Time COA Calc. Avg. Head (min 48 hrs)	≥	48	hrs	68.41	hrs

				-					
						ΒY			
						DATE			
						SIONS			
						REVIS			
						No			
			8	69					
				γ, TX 750	20				
					'2-239-38 ТХ F-928				
		$\widehat{\black}$		TE 100, N	N.COM				
				EET, SUI	.301-2580 LEY-НОF				
				VIS STRE	NE: 469- WW.KIM				
				EAST DA	OH A A				
			i I	2601					
	1				2				
ľ		TATE				7			
	MI	CHAEL	T. D	OGGE	TT ≈				
	NRO,	ESSION	ENS	P GI	AA AA	•			
		<u>4/17</u>	7 <u>2(</u> ₹	<u>)23</u> E	DB	TD			
	35101 85101	\ТЕ 2023	VOHS SY	N N N	A	M			
	KHA P 0645	D/ MARCH	CALE /	ESIGNED	RAWN BY	HECKED E			
			S			U			
		F	ЦЦ	ļ					
	S AT NUAF								
		ЮН	С У. С))		JER, TE			
		Щ П	DAI	Ì		LEAN			
		Ĕ	BAG	2 5					
		≻		Ζ					
	QUA LATI								
		с С		CO					
		T T T		,АL					
	í i		5 (J			1		
		5	>						
		5	>						
		SHEE	> T NU	IMBE	R				

IMAGES XStrm : xSurv : XUtil : xBrdr : xSite LAST SAVED 4/18/2023 10:44 AM PLOTTED BY LOPEZ, GARY 4/18/2023 11:04 AM DWG PATH WKIMLEY-HORN COMITX, MKNMKN, CIVIL\064585101-LEANDER BAGDAD RETAIL\CADIPLAI DWG NAME WATER QUALITY PLAN.DWG , [WATER QUALITY DETAILS]

INSPECTION, MAINTENANCE, REPAIR AND

RETROFIT PLAN

The inspection and maintenance plan outlines the procedures necessary to maintain the performance of the Permanent Best Management Practices for this project. It should be noted that the plan provides guidelines that may have to be adjusted dependent on site specific and weather-related conditions.

It is the responsibility of the owner to provide the inspections and maintenance as outlined in the plan for the duration of the project. The owner will maintain this responsibility until it is assumed or transferred to another entity in writing. If the property is leased or sold, the responsibility for the maintenance will be required to be transferred through the lease agreement, binding covenants, closing documents, or other binding legal instrument.

Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

Maintenance records shall be kept on the installation, maintenance, or removal of items necessary for the proper operation of the facilities. All inspections shall be documented.

An amended copy of this document will be provided to the Texas Commission on Environmental Quality within thirty (30) days of any changes in the following information.

Responsible Party:	Bagdad Rd., Leander LLC		
Mailing Address:	3000 Polar Lane, Suite 404		
City, State:	Cedar Park, Texas	Zip:78813	

Telephone: <u>973-723-4862</u> Fax: <u>N/A</u>

I, the owner, have read and understand the requirements of the attached Inspection and Maintenance Plan for the proposed Permanent Best Management Practices for my project. I acknowledge that I will maintain responsibility for the implementation and execution of the plan until the responsibility is transferred to or assumed by another party in writing through a binding legal instrument.

Date 05/24/23 Signature of Responsible Party _

This Maintenance Plan is based on City of Austin Environmental Criteria Manual.

By:

Date 5/18/2023

Michael Doggett, P.E.

Inspection and Maintenance For BMPs

SAND FILTER SYSTEM

- Inspections. The BMP facilities must be inspected semi-annually (once during or immediately after wet weather) and repairs should be made if necessary.
- Sediment Removal. Remove sediment from inlet structure and sedimentation chamber at least annually, or when depth reaches 6 inches, or proper functioning is impaired; remove sediment from basin at least every 5 years.
- Media Replacement. More extensive maintenance of the filter media is required when the drawdown time begins to exceed the target time of 48 hours. When this occurs, the upper layer of sand should be removed and replaced with new material meeting the original specifications. Any discolored sand should also be removed and replaced. In filters that have been regularly maintained, this should be limited within the top 2 to 3 inches.
- Debris and Litter Removal. Accumulated paper, trash and debris should be removed during regular mowing operations and inspections, or as necessary.
- Filter Underdrain. Clean underdrain piping network to remove any sediment buildup as needed to maintain design drawdown time.
- Mowing. Grass areas in and around basins must be mowed at least twice annually to limit vegetation height to 18 inches. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and removed.
- Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

Inspection Schedule

The primary operator is required to choose one of the two inspections listed below.

Option 1: Once every seven calendar days. If this alternative schedule is developed, then the inspection must occur regardless of whether or not there has been a rainfall event since the previous inspection.
 Option 2: Once every 14 calendar days and within 24 hours of the end of a

Option 2: Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).

If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded. Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized;
- areas used for storage of materials that are exposed to precipitation;
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system);
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly); and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking).

Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

Inspection Report Forms

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

Corrective Action

Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

Corrective Action Forms

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.

Schedule of Interim and Permanent Soil Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, Sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a) The dates when major grading activities occur;
- b) The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c) The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more that fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.

Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

Maintenance

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)
- Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.
- Silt fence will be inspected for depth of sediment, tears, to see of the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Straw bale dike will be inspected and repaired as necessary.
- Diversion dike will be inspected and any breaches promptly repaired.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must to work with the owner or operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

• Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of storm water controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.

Inspector Qualifications Log*

Inspector Name:
Qualifications (Check as appropriate and provide description):
Training Course
Supervised Experience
Other
Inspector Name [.]
Qualifications (Check as appropriate and provide description):
□ Training Course
Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
Training Course
Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
□ Training Course
Supervised Experience
Other
Inspector Name [.]
Qualifications (Check as appropriate and provide description):
□ Training Course
Supervised Experience
Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
Training Course
Supervised Experience

* The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.

No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

Amendment Log

Construction Activity Sequence Log

Name of Operator	Projected dates Month/year	Activity Disturbing Soil clearing, excavation, etc.	Location on-site where activity will be conducted	Acreage being disturbed

*Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.

Stormwater Control Installation and Removal Log

Stormwater Control	Location On-Site	Installation Date	Removal Date

Stabilization Activities Log

Date Activity Initiated	Description of Activity	Description of Stabilization Measure and Location	Date Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures Initiated

Stabilization and erosion control practices may include, but are not limited to: establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.

512 418 1771

Date	Frequency Schedule and Reason for Change			

Inspection Frequency Log

Rain	Gauge	Log
------	-------	-----

Date	Location of Rain Gauge	Gauge Reading

General Information						
Name of Project			Tracking No.		Inspection Date	
Inspector Name, Titl Information	e & Contact					
Present Phase of Co	nstruction					
Inspection Location (if multiple inspections are required, specify location where this inspection is being conducted)						
Inspection Frequency Weekly Every 14 days and within 24 hours of a 0.25" rain Increased Frequency: Every 7 days and within 24 hours of a 0.25" rain Reduced Frequency: Every 7 days and within 24 hours of a 0.25" rain Once per month (for stabilized areas) Once per month and within 24 hours of a 0.25" rain (for arid, semi-arid, or drought-stricken areas during seasonally dry periods or during drought) Once per month (for frozen conditions where earth-disturbing activities are being conducted)						
Was this inspection triggered by a 0.25" storm event? Yes No If yes, how did you determined whether a 0.25" storm event has occurred? Rain gauge on site Weather station representative of site. Specify weather station source: Total rainfall amount that triggered the inspection (in inches): Image: No						
Unsafe Conditions for Inspection Did you determine that any portion of your site was unsafe for inspection? Yes No If "yes", complete the following: - Describe the conditions that prevented you from conducting the inspection in this location:						
- Location(s) where conditions were found:						

512 418 1771
	Condition and Effectiveness of Erosion and Sediment (E&S) Controls					
Type/Location of E&S Control	Repairs or Other Maintenance Needed?	Corrective Action Required?	Date on Which Maintenance or Corrective Action First Identified?	Notes		
1.	□Yes □No	□Yes □No				
2.	□Yes □No	□Yes □No				
3.	□Yes □No	□Yes □No				
4.	□Yes □No	□Yes □No				
5.	□Yes □No	□Yes □No				
6.	□Yes □No	□Yes □No				
7.	□Yes □No	□Yes □No				
8.	□Yes □No	□Yes □No				
9.	□Yes □No	☐Yes ☐No				
10.	□Yes □No	□Yes □No				

512 418 1771

	Condition and Effectiveness of Pollution Prevention (P2) Practices					
Type/Location of P2 Practices	Repairs or Other Maintenance Needed?	Corrective Action Required?	Identification Date	Notes		
1.	□Yes □No	□Yes □No				
2.	□Yes □No	□Yes □No				
3.	□Yes □No	□Yes □No				
4.	□Yes □No	□Yes □No				
5.	□Yes □No	□Yes □No				
6.	□Yes □No	□Yes □No				
7.	□Yes □No	∐Yes ∏No				
8.	□Yes □No	□Yes □No				
9.	□Yes □No	□Yes □No				
10.	Yes No	□Yes □No				

512 418 1771

Stabilization of Exposed Soil				
Stabilization Area	Stabilization Method	Have You Initiated Stabilization?	Notes	
1.		YES NO If yes, provide date:		
2.		YES NO If yes, provide date:		
3.		YES NO If yes, provide date:		
4.		YES NO If yes, provide date:		
5.		YES NO If yes, provide date:		
	Description of D	Discharges		
Was a stormwater discharge or other If "yes", provide the following info	discharge occurring from any part of ye ormation for each point of discharge:	our site at the time of the inspection?]Yes 🗌 No	
Discharge Location	Observations			
1.	Describe the discharge:			
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:			
2.	Describe the discharge:			
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:			
3.	Describe the discharge:			
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:			

Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Contractor or Subcontractor:

Date:

Printed Name and Affiliation:

Certification and Signature by Permittee

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Permittee of	
"Duly Authorized Representative":	 Date:

Signature of Dermittee or

Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)					
Name of Project	Tracking No.			Today's Date	
Date Problem First Disco	vered		Time Problem Firs	t Discovered	
Name and Contact Inform Form	nation of Individual Completing this				
What site conditions trigg A required stormwate The stormwater contr A prohibited discharg	gered the requirement to conduct corr or control was never installed, was inst ols that have been installed and main e has occurred or is occurring	ective action: alled incorrectly ained are not e	y, or not in accordan ffective enough for th	ce with the requirements in Part 2 he discharge to meet applicable wa	2 and/or 3 ater quality standards
Provide a description of t	he problem:				
Deadline for completing o infeasible to complete wo	corrective action (Enter date that is ei ork within the first 7 days, enter the d	ther: (1) no mo ate that is as so	re than 7 calendar d on as practicable fol	ays after the date you discovered lowing the 7th day):	l the problem, or (2) if it is
If your estimated date of date you have established	completion falls after the 7-day deadli l for making the new or modified storn	ne, explain (1) v nwater control o	vhy you believe it is i operational is the soc	nfeasible to complete work withir onest practicable timeframe:	1 7 days, and (2) why the
	Sect (Complete this section <u>no later than 7</u>	ion B – Corre calendar days afte	ctive Action Progr er discovering the condi	ess tion that triggered corrective action)	
Section B.1 – Why the	Problem Occurred				
Cause(s) of Problem (Add	l an additional sheet if necessary)		How This Was Det	ermined and the Date You Deterr	nined the Cause
1.			1.		
2.			2.		
3.			3.		
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem					
List of Stormwater Contro Problem (Add an addition	ol Modification(s) Needed to Correct nal sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes	
1.			□Yes □No Date:		
2.			□Yes □No Date:		
3.			☐Yes ☐No Date:		

Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)					
Name of Project Tracking N	Tracking No.		Today's Date		
Date Problem First Discovered		Time Problem Firs	t Discovered		
Name and Contact Information of Individual Completing this Form					
What site conditions triggered the requirement to conduct correct A required stormwater control was never installed, was instand The stormwater controls that have been installed and mainter A prohibited discharge has occurred or is occurring	What site conditions triggered the requirement to conduct corrective action: A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3 The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards A prohibited discharge has occurred or is occurring 				
Provide a description of the problem:					
Deadline for completing corrective action (Enter date that is eit infeasible to complete work within the first 7 days, enter the da	her: (1) no moi te that is as soo	re than 7 calendar d on as practicable fol	ays after the date you discovered lowing the 7th day):	l the problem, or (2) if it is	
If your estimated date of completion falls after the 7-day deadlin date you have established for making the new or modified storm	e, explain (1) w water control o	why you believe it is i operational is the soc	nfeasible to complete work within onest practicable timeframe:	1 7 days, and (2) why the	
Section (Complete this section <u>no later than 7 c</u>	on B – Corree alendar days afte	ctive Action Progr r discovering the condi	ess tion that triggered corrective action)		
Section B.1 – Why the Problem Occurred					
Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Det	ermined and the Date You Deterr	nined the Cause	
1.		1.			
2.		2.			
3.		3.			
Section B.2 – Stormwater Control Modifications to be l	mplemented	to Correct the Pr	oblem		
List of Stormwater Control Modification(s) Needed to Correct Problem (Add an additional sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes		
1.		□Yes □No Date:			
2.		□Yes □No Date:			
3.		□Yes □No Date:			

Contractor or Subcontractor Certification and Signature			
kimley-horn.com	10814 Jollyville Road, Avallon IV, Suite 300, Austin, TX 78759	512 418 1771	

"I certify under penalty of law that this document and all attachments were prepared under my direction or su assure that qualified personnel properly gathered and evaluated the information submitted. Based on my i system, or those persons directly responsible for gathering the information, the information submitted is, to the and complete. I am aware that there are significant penalties for submitting false information, including the violations."	pervision in accordance with a system designed to nquiry of the person or persons who manage the he best of my knowledge and belief, true, accurate, e possibility of fine and imprisonment for knowing
Signature of Contractor or Subcontractor:	Date:
Printed Name and Affiliation:	
Certification and Signature by Permittee	
"I certify under penalty of law that this document and all attachments were prepared under my direction or su assure that qualified personnel properly gathered and evaluated the information submitted. Based on my i system, or those persons directly responsible for gathering the information, the information submitted is, to the and complete. I am aware that there are significant penalties for submitting false information, including the violations."	pervision in accordance with a system designed to inquiry of the person or persons who manage the ne best of my knowledge and belief, true, accurate, e possibility of fine and imprisonment for knowing
Signature of Permittee or "Duly Authorized Representative": Date:	:
Printed Name and Affiliation:	

Г

PILOT-SCALE FIELD TESTING PLAN

MEASURES FOR MINIMIZING SURFACE STREAM

CONTAMINATION

During construction, standard erosion measures will be used as shown in the construction plans. Runoff from the construction site will be contained by a silt fence until construction is complete. Entry and exit from the site will be through a stabilized construction entrance.

After completion of the project, temporary erosion and sedimentation measures (silt fence and rock berm) will remain in place until vegetative cover is established. Details concerning the erosion/sedimentation protection plan can be found on the Erosion & Sedimentation Control Plans of the construction drawings.

SECTION 4: Additional Forms

Storm Water Pollution Prevention Plan

Agent Authorization Form

For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

I	Praveen Guduru	,
	Print Name	
	President	3
	Title - Owner/President/Other	
of	Bagdad Rd. Leander LLC Corporation/Partnership/Entity Name	,
have authorized	Michael Doggett, P.E.	
	Print Name of Agent/Engineer	
of	Kimley-Horn and Associates, Inc.	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Applicant's Signature

05 24 2023

THE STATE OF N.T §

County of Mildleser §

BEFORE ME, the undersigned authority, on this day personally appeared Project and known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 21 day of May , 2023

NOTARY PUBLIC

Naser 3.J.h. Typed or Printed Name of Notary

MY COMMISSION EXPIRES: ______/24/24/24/2

NASER R . BATAH NOTARY PUBLIC, STATE OF NEW JERSEY COMMISSION # 50132485 MY COMMISSION EXPIRES JULY 24, 2025

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Praveen Gulun

Date: 05/24/2023

Signature of Customer/Agent:

Regulated Entity Name: Shops at Bagdad Square

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
 Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ

prior to moving the tanks onto the project.

Fuels and hazardous substances will not be stored on the site.

2. Attachment A - Spill Response Actions. A site specific description of the measures to be None taken to contain any spill of hydrocarbons or hazardous substances is attached.

3. Temporary aboveground storage tank systems of 250 gallons or more cumulative

None storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.

4. Attachment B - Potential Sources of Contamination. A description of any activities or None processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.

6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>Bushy Creek</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site
	 A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. A description of how BMPs and measures will prevent pollutants from entering
	 A description of now BMPs and measures will prevent politicants from entering surface streams, sensitive features, or the aquifer. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	 Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. 🗹 None	Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. 🗹	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
	 For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided. For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used
	 For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be
	used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

- 11. Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
 - N/A
- 12. Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

SPILL RESPONSE ACTIONS

POTENTIAL SOURCES OF CONTAMINATION

SEQUENCE OF MAJOR ACTIVITIES

Phase A – Grading

- 1. Construct temporary construction entrance, silt fence, dike, and tree protection fence according to the approximate location and shown on grading and erosion control plan notes and detail sheet.
- 2. Begin clearing and grading of site.
- 3. Seed and revegetate slopes where shown.

Phase B – Utilities

- 1. Keep all storm water pollution prevention measures in place.
- 2. Install storm drains, sanitary sewer, and water as specified on plan sheets.

Phase C – Paving

- 1. Keep all storm water pollution prevention measures in place. Remove as needed to pave.
- 2. Stabilize subgrade.
- 3. Pave streets and sidewalks as specified on plan sheets.
- 4. Re-install any storm water pollution prevention measures removed for paving operations.

Phase D – Landscaping and soil stabilization

- 1. Revegetate lot and parkways
- 2. Landscape contractor shall revegetate all areas reserves for landscape vegetative covers.
- 3. Remove erosion control devices when minimum 70% ground cover is established.
- 4. Vegetation must be established before structure controls removed.

TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

- Silt fence will be utilized around the site during construction to avoid additional erosion from the site.
- Inlet protection covers will be utilized once the storm infrastructure has been constructed. This will aid in avoiding additional sediment from running through the storm system.

REQUEST TO TEMPORARILY SEAL A FEATURE

STRUCTURAL PRACTICES

064585101 - THE SHOPS AT BAGDAD SQUARE CONTRIBUTING ZONE PLAN MODIFICATION

DRAINAGE AREA MAP

TEMPORARY SEDIMENT POND(S) PLANS AND

CALCULATIONS

INSPECTION AND MAINTENANCE FOR BMPS

SAND FILTER SYSTEM

- Inspections. The BMP facilities must be inspected semi-annually (once during or immediately after wet weather) and repairs should be made if necessary.
- Sediment Removal. Remove sediment from inlet structure and sedimentation chamber at least annually, or when depth reaches 6 inches, or proper functioning is impaired; remove sediment from basin at least every 5 years.
- Media Replacement. More extensive maintenance of the filter media is required when the draw-downtime begins to exceed the target time of 48 hours. When this occurs, the upper layer of sand should be removed and replaced with new material meeting the original specifications. Any discolored sand should also be removed and replaced. In filters that have been regularly maintained, this should be limited within the top 2 to 3 inches.
- Debris and Litter Removal. Accumulated paper, trash and debris should be removed during regular mowing operations and inspections, or as necessary.
- Filter Underdrain. Clean underdrain piping network to remove any sediment buildup as needed to maintain design drawdown time.
- Mowing. Grass areas in and around basins must be mowed at least twice annually to limit vegetation height to 18 inches. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and removed.
- Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

SCHEDULE OF INTERIM AND PERMANENT SOIL

STABILIZATION PRACTICES

The operator is responsible for the installation and maintenance of permanent stormwater control measures prior to final stabilization of the site. The following measures will be installed and designed during construction to control runoff after construction is complete:

- 1. Seeding, sodding, or hydro mulch will be installed after final grading phase where soil has been disturbed to control erosion.
- 2. Landscaped areas within all unpaved disturbed areas will continue to provide soil stabilization.
- 3. A storm drain system may be completed at the completion of the project, as noted in civil plans, to collect storm runoff.
- 4. Vegetated swales, diversion dikes, or natural depressions may be established at the complete for the project, per the civil plans, to divert run-off from the site.
- 5. Soil will be stabilized if construction on that portion of the site will not be disturbed for a period exceeding fourteen calendar days.

Application Fee Form

Texas Commission on Environme Name of Proposed Regulated Entity Regulated Entity Location: <u>NEC No</u> Name of Customer: <u>Bagdad Rd. Lea</u> Phone: <u>973-723-4862</u> Customer Regulated Entity Reference Number Austin Regional Office (3373)	ntal Quality <u>The Shops at Bagda</u> <u>orth Bagdad & Municipa</u> <u>under LLC</u> Contact Pe Reference Number (if i (if issued):RN Click he	ad Square al Drive rson: <u>Praveen Gudur</u> ssued):CN _Click here ere to enter text.	u e to enter text
☐ Hays	Travis	🖂 Will	iamson
San Antonio Regional Office (3362	2)		
☐ Bexar ☐ Comal	☐ Medina ☐ Kinney	🗌 Uva	llde
Application fees must be paid by Commission on Environmental Qu must be submitted with your fee p	check, certified check u ality . Your canceled payment. This paymer	k, or money order, pa check will serve as you nt is being submitted to	ayable to the Texas ur receipt. This form o:
 Austin Regional Office Mailed to: TCEQ - Cashier Revenues Section Mail Code 214 P.O. Box 13088 Austin, TX 78711-3088 Site Location (Check All That App 	 	San Antonio Regional Overnight Delivery to: 12100 Park 35 Circle Building A, 3rd Floor Austin, TX 78753 (512)239-0357	Office TCEQ - Cashier
Recharge Zone	\square Contributing Zone	🗌 Tra	nsition Zone
Type of Plan	1	Size	Fee Due
Water Pollution Abatement Plan Plan: One Single Family Resident	n, Contributing Zone ial Dwelling	Acres	\$
Water Pollution Abatement Plan Plan: Multiple Single Family Resid	n, Contributing Zone lential and Parks	Acres	
Water Pollution Abatement Plar Plan: Non-residential	n, Contributing Zone	4.67 Acres	\$ 4,000
Sewage Collection System		L.F.	\$
Lift Stations without sewer lines		Acres	\$
Underground or Aboveground Sto	rage Tank Facility	Tanks	\$
Piping System(s)(only)		Each	\$
Exception		Each	\$
Extension of Time		Each	\$
ALIAN			J

Signature:

Date: <u>3/27/2023</u> Application Fee Schedule

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5 5 < 10 10 < 40 40 < 100 100 < 500 ≥ 500	\$1,500 \$3,000 \$4,000 \$6,500 \$8,000 \$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1 1 < 5 5 < 10 10 < 40 40 < 100 ≥ 100	\$3,000 \$4,000 \$5,000 \$6,500 \$8,000 \$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee		
Sewage Collection Systems	\$0.50	\$650 - \$6,500		

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150

Check Payable to the "Texas Commission on Environmental Quality"

Core Data Form

Additional Forms TCEQ-10400 (Rev. 04-15)



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)								
New Permit, Registration or Authorization (<i>Core Data Form should be submitted with the program application.</i>)								
Renewal (Core Data Form should be submitted with the renewal form) Other								
2. Customer Reference Number (if issued)	Follow this link to search	3. Regulated Entity Reference Number (if issued)						
CN	<u>Central Registry**</u>	RN						

SECTION II: Customer Information

4. General Cu	4. General Customer Information 5. Effective Date for Customer Information Updates (mm/dd/yyyy)												
New Customer Update to Customer Information Change in Regulated Entity Ownership Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)													
The Custome	The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State												
(SOS) or Texas Comptroller of Public Accounts (CPA).													
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John) <u>If new Customer, enter previous Customer below:</u>													
Bagdad Rd, Lea	inder LLC								Previo	ous Custome	er		
7. TX SOS/CP	A Filing N	lumber		8. TX State	Tax ID (11 d	ligits)			9. Fe	deral Tax I	D	10. DUNS	Number (if
08040	48365								(9 dig	its)		applicable)	
	10000	, 											
11 Type of Curtomer: X Corporation Queries General Queries General Queries								eral 🗌 Limited					
Government:	City 🗌	County	Federal	Local 🗌 State	e 🗌 Other			Sole Pi	roprieto	rship	🗌 Otl	her:	
12. Number	of Employ	vees			_				13. lı	ndepender	ntly Ow	ned and Ope	erated?
⊠ 0-20 □	21-100	101-25	i0 🗌 251-	500 🗌 501	and higher			🖾 Yes 🗌 No					
14. Custome	r Role (Pro	oposed or	Actual) – <i>as i</i>	t relates to the	Regulated E	ntity lisi	ted o	n this form.	Please o	check one of	the follo	owing	
Owner	al Licensee	Ope	erator esponsible Pa	nty 🗌 Ov	vner & Opera VCP/BSA App	ator olicant				Other:			
15. Mailing	3000 Pol	lar Lane, S	uite 404										
Address:													
, luu cool	City	Cedar F	Park		State	ТΧ	TX ZIP 78813 ZIP + 4						
16. Country I	Mailing In	formatio	on (if outside	USA)			17. E-Mail Address (if applicable)						
							pguduru@yahoo.com						
18. Telephone Number 19. Extension of			on or C	20. Fax Number (if applicable)									

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)								
New Regulated Entity Dpdate to Regulated Entity Name Dpdate to Regulated Entity Information								
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).								
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)								
Shops at Bagdad Square								
23. Street Address of	ΝΑ							
the Regulated Entity:								
<u>(No PO Boxes)</u>	City	Leander	State	ТХ	ZIP	78641	ZIP + 4	
24. County	Williamson							

If no Street Address is provided, fields 25-28 are required.

25. Description to Physical Location:	NEC North	Bagdad Road & Mu	unicipal Drive						
26. Nearest City						State		Nea	rest ZIP Code
Leander						ТХ		7864	1
Latitude/Longitude are n used to supply coordinat	equired and es where n	d may be added/ one have been pi	updated to meet T rovided or to gain o	CEQ Core D accuracy).	ata Standa	ards. (Geoc	oding of th	e Physical	Address may be
27. Latitude (N) In Decimal: 30.572158 28. Longitude (W) In Decimal: -97.869233							33		
Degrees	Minutes		Seconds	Degre	es	Mi	nutes	-	Seconds
29. Primary SIC Code (4 digits)	Jode30. Secondary SIC Code (4 digits)31. Primary NAICS Code (5 or 6 digits)32. Secondary NAICS Code (5 or 6 digits)						CS Code		
5331				455 <i>′</i>	110				
33. What is the Primary E	Business of	this entity? (Do	o not repeat the SIC or	NAICS descri	iption.)				
Retail, Restuarant									
34. Mailing	3000 Pola	ar Lane Suite 404							
Address:						-			
	City	Cedar Park	State	тх	ZIP	78813		ZIP + 4	
35. E-Mail Address:	pg	uduru@yahoo.com	1						•
36. Telephone Number			37. Extension or	Code	38. F	ax Numbe	r (if applicab	ole)	
(973-723-4862 () -									

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

Dam Safety	Districts	Edwards Aquifer	Emissions Inventory Air	Industrial Hazardous Waste
Municipal Solid Waste	☐ New Source Review Air	OSSF	Petroleum Storage Tank	D PWS
Sludge	Storm Water	🗌 Title V Air	Tires	Used Oil
Voluntary Cleanup	U Wastewater	Wastewater Agriculture	Water Rights	Other:

SECTION IV: Preparer Information

40. Name:	40. Name: Michael Doggett			41. Title:	Project Manager	
42. Telephone	Number	43. Ext./Code	44. Fax Number	45. E-Mail Address		
(469)352-2959			() -	michael.dog	gett@kimley-horn.com	

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Kimley-Horn	Job Title: Project Ma			anager		
Name (In Print):	Micheal Doggett			Phone:	(469) 352- 2959		
Signature:	Millight			Date:	1/25/2023		