CONTRIBUTING ZONE PLAN MODIFICATION APPLICATION

FOR

PEC OAK HILL (PEDERNALES ELECTRIC COOPERATIVE SERVICE CENTER)

9115 Circle Drive Austin, Texas, 78736

Prepared For:

PEDERNALES ELECTRIC COOPERATIVE, INC 201 S. AVENUE F AUSTIN, TEXAS 78736

P.O. Box 1 Johnson City, Texas 78636 (registered mailing address)

Prepared By:



Sandlin Services, LLC TBPE Firm # 21356 P: (806) 679-7303

June 15, 2023





TABLE OF CONTENTS

Edwards Aquifer Application Cover Page (TCEQ-20705)

Modification of a Previously Approved Contributing Zone Plan form (TCEQ-10259)

Attachment A - Original Approval Letter and Approved Modification Letters

Attachment B – Narrative of Proposed Modification

Attachment C – Current Site Plan of the Approved Project

Contributing Zone Plan Application (TCEQ-10257)

Attachment A – Road Map

Attachment B – USGS Quadrangle Map

Attachment C – Project Narrative

Attachment D - Factors Affecting Surface Water Quality

Attachment E – Volume and Character of Stormwater

Attachment F – Suitability Letter from Authorized Agent (if OSSF is proposed)

Attachment G – Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)

Attachment H – AST Containment Structure Drawing (if AST is proposed)

Attachment I -20% or Less Impervious Cover Declaration (if project is multi-family residential, a school, or a small business and 20% or less impervious cover is proposed for the site)

Attachment J – BMPs for Upgradient Stormwater

Attachment K – BMPs for On-site Stormwater

Attachment L – PMTs for Surface Streams

Attachment M – Construction Plans

Attachment N – Inspection, Maintenance, Repair and Retrofit Plan

Attachment O – Pilot-Scale Field Testing Plan, if BMPs not based on Complying with the Edwards

Aguifer Rules: Technical Guidance for BMPs

Attachment P – Measures for Minimizing Surface Stream Contamination

Temporary Stormwater Section (TCEQ-0602)

Attachment A – Spill Response Actions

Attachment B – Potential Sources of Contamination

Attachment C – Sequence of Major Activities

Attachment D – Temporary Best Management Practices and Measures

Attachment E – Request to Temporarily Seal a Feature, if sealing a feature

Attachment F – Structural Practices

Attachment G – Drainage Area Map

Attachment H – Temporary Sediment Pond(s) Plans and Calculations

Attachment I – Inspection and maintenance for BMPs

Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices

Copy of Notice of Intent (NOI)





Agent Authorization Form (TCEQ-0599)

Application Fee Form (TCEQ-0574)

Check Payable to the "Texas Commission on Environmental Quality"

Core Data Form (TCEQ-10400)



Edwards Aquifer Application Cover Page (TCEQ-20705)

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: PEC Oak Hill				2. Regulated Entity No.: 104895438				
3. Customer Name: Pedernales Electric Cooperative, Inc.			4. Customer No.: 601327927					
5. Project Type: (Please circle/check one)	New	Modification		Extension		Exception		
6. Plan Type: (Please circle/check one)	WPAP CZP	SCS U	JST AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures	
7. Land Use: (Please circle/check one)	Residential	Non-residential		>	8. Sit	e (acres):	20.6	
9. Application Fee:	\$7,800	10. Permanent B		EXISTING Existing-		Existing- no ch	;- no change	
11. SCS (Linear Ft.):	0	12. AST/UST (No. 7		o. Tar	. Tanks): 1			
13. County:	Travis	14. Watershed:			Onion Creek			

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region				
County:	Hays	Travis	Williamson	
Original (1 req.)	_	_1_	_	
Region (1 req.)	_	_1_	_	
County(ies)		_1_	_	
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	_x_Barton Springs/ Edwards Aquifer	NA	
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	_x_AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrellLeanderLiberty HillPflugerville Round Rock	

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)	_				
County(ies)			_		
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks Ranch _Helotes _Hill Country Village _Hollywood Park _San Antonio (SAWS) _Shavano Park	BulverdeFair Oaks RanchGarden RidgeNew BraunfelsSchertz	NA	San Antonio ETJ (SAWS)	NA


I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Nick Sandlin, P.E. (Sandlin Services, LLC)

Print Name of Customer/Authorized Agent

Nive Sept. 6/15/2023
Signature of Customer/Authorized Agent Date

FOR TCEQ INTERNAL USE ON	LY			
Date(s)Reviewed:		Date Adn	ninistratively Comple	ete:
Received From:		Correct Number of Copies:		•
Received By:		Distribut	ion Date:	
EAPP File Number:		Complex	:	
Admin. Review(s) (No.):		No. AR R	tounds:	
Delinquent Fees (Y/N):		Review Time Spent:		
Lat./Long. Verified:		SOS Cust	comer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee	Payable to TCEQ (Y	T/N):
Core Data Form Complete (Y/N):		Check: Signed (Y/N):		
Core Data Form Incomplete Nos.:			Less than 90 days o	ld (Y/N):





Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

Modification of a Previously Approved Contributing Zone Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Modification of a Previously Approved Contributing Zone Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Date: <u>6/15/2023</u>

Signature of Customer/Agent:

Project Information

1. Current Regulated Entity Name: PEC Oak Hill

Original Regulated Entity Name: Pedernales Electric Cooperative Service Center; Along Hwy

290 West and Circle Drive, Austin E.T.J., Texas
Assigned Regulated Entity Number(s) (RN): 104895438

Edwards Aquifer Protection Program ID Number(s): 11-06030101

- The applicant has not changed and the Customer Number (CN) is: 601327927
- The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
- 2. Attachment A: Original Approval Letter and Approved Modification Letters. A copy of the original approval letter and copies of any modification approval letters are attached.
- 3. A modification of a previously approved plan is requested for (check all that apply):

1 of 3

6/19/2023

	Any physical or operational modification of any best management practices or structure(s), including but not limited to temporary or permanent ponds, dams, berms, silt fences, and diversionary structures;
	Any change in the nature or character of the regulated activity from that which was originally approved;
	 A change that would significantly impact the ability to prevent pollution of the Edwards Aquifer and hydrologically connected surface water; or
	Any development of land previously identified in a contributing zone plan as undeveloped.
4.	Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

CZP Modification	Approved Project	Proposed Modification
Summary		
Acres	20.6	<u>N/A</u>
Type of Development	<u>Industrial</u>	<u>N/A</u>
Number of Residential	<u>0</u>	N/A
Lots		
Impervious Cover (acres)	5.08	<u>N/A</u>
Impervious Cover (%)	<u>24.6</u>	<u>N/A</u>
Permanent BMPs	Retention/Irr. Pond	<u>N/A</u>
Other		
AST Modification	Approved Project	Proposed Modification
Summary		
Number of ASTs	<u>0</u>	<u>2</u>
Other		
UST Modification	Approved Project	Proposed Modification
Summary		
Number of USTs		
Other		

5.	Attachment B: Narrative of Proposed Modification. A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved, including previous modifications, and how this proposed modification will change the approved plan.
6.	Attachment C: Current Site Plan of the Approved Project. A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere. The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired. The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved. The approved construction has commenced and has been completed. Attachment C
	 illustrates that the site was not constructed as approved. The approved construction has commenced and has not been completed. Attachment C illustrates that, thus far, the site was constructed as approved. The approved construction has commenced and has not been completed. Attachment C illustrates that, thus far, the site was not constructed as approved.
7.	Acreage has not been added to or removed from the approved plan. Acreage has been added to or removed from the approved plan and is discussed in Attachment B: Narrative of Proposed Modification.
8.	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.



Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

Attachment A: Original Approval Letter and Approved Modification Letters Kathleen Hartnett White, Chairmb R. B. "Ralph" Marquez, Commissioner Larry R. Soward, Commissioner Glenn Shankle, Executive Director

MAY 1 0 2006

Cunningham-Allen, Inc.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

May 4, 2006

Ms. Jeanell Davis, Operations Manager Pedernales Electric Cooperative, Inc. P.O. Box 1 Johnson City, TX 78636

Edwards Aquifer, Travis County Re:

NAME OF PROJECT: Pedernales Electric Cooperative Service Center; Along

Hwy 290 West and Circle Drive, Austin E.T.J., Texas

TYPE OF PLAN: Request for Approval of a Contributing Zone Plan (CZP); 30 Texas Administrative Code (TAC) Chapter 213 Subchapter B Edwards Aquifer

Edwards Aquifer Protection Program ID No.: 11-06030101; Investigation No.:

464566

Dear Ms. Davis:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the CZP application for the referenced project submitted to the Austin Regional Office by Cunningham Allen, Inc. on behalf of the Pedernales Electric Cooperative, Inc. on March 1, 2006. Final review of the CZP submittal was completed after additional material was received on April 27, 2006. As presented to the TCEQ, the Temporary and Permanent Best Management Practices (BMPs) and construction plans were prepared by a Texas Licensed Professional Engineer and appear to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed, and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Contributing Zone Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10% of the construction has commenced on the project or an extension of time has been requested.

REPLY TO: REGION 11 ● 1921 CEDAR BEND DR., STE. 150A ● AUSTIN, TEXAS 78758-5327 ● 512/339-2929 ● FAX 512/339-3795

PROJECT DESCRIPTION

The site consists of 20.6 acres of undisturbed property located on the Slaughter Creek stream basin. Proposed improvements include a 6,902 square foot office building, a 7,525 square foot warehouse building, a caliche-based parking/storage area, asphalt roads and parking, sidewalks, and associated appurtenances for a total of 5.08 acres of impervious cover (24.6%).

As described in the CZP application, the facility will serve as a service operations center for the Pedernales Electric Cooperative, including customer service and bill payment, storage of power poles, transformers, other utility construction and maintenance materials, and equipment.

Temporary best management practices (BMPs) consisting of silt fence, rock berms, two stabilized construction entrances, and a temporary sediment basin will be implemented to treat and control stormwater runoff during construction activities. Project wastewater will be disposed of by conveyance to an on-site sewage facility (OSSF/Septic Tank).

PERMANENT POLLUTION ABATEMENT MEASURES

A retention/irrigation system will be constructed as a permanent best management practice (BMP) to treat stormwater runoff. The required load removal for the site appears to be 4,145 pounds. The retention/irrigation system will have a water quality volume of 47,156 cubic feet and will irrigate 2.72 acres. According to the CZP, the approved measures meet the required 80 percent removal of the increased load in total suspended solids caused by the project.

SPECIAL CONDITIONS

- I. Intentional discharges of sediment laden stormwater during construction are not allowed. If dewatering excavated areas and/or areas of accumulated stormwater becomes necessary, the discharge shall be filtered through appropriately selected temporary best management practices. These may include vegetative filter strips, sediment traps, rock berms, silt fence rings, etc.
- II. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 3 below.

STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.

Prior to Commencement of Construction:

- 2. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved Contributing Zone Plan and this notice of approval shall be maintained at the project until all regulated activities are completed.
- 3. Any modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.
- 4. The applicant must provide written notification of intent to commence construction of the referenced project. Notification must be submitted to the Austin Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the name of the approved plan and ID number for the regulated activity, the date on which the regulated activity will commence, and the name of the prime contractor with the name and telephone number of the contact person.
- 5. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved Storm Water Pollution Prevention Plan (SWPPP) must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established and the construction area is stabilized. The water quality pond shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

- 6. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
- 7. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been significantly reduced. Litter, construction debris, and construction chemicals exposed to stormwater shall be

Ms. Jeanell Davis, Operations Manager Page 4 May 4, 2006

prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

- 8. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 9. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

- 10. Owners of permanent BMPs and measures must insure that the BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the Austin Regional Office within 30 days of site completion.
- 11. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through the Austin Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
- 12. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Contributing Zone Plan. If the new owner intends to commence any new regulated activity on the site, a new Contributing Zone Plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.
- 13. A Contributing Zone Plan approval or extension will expire and no extension will be granted if more than 50% of the total construction has not been completed within ten years from the initial approval of a plan. A new Contributing Zone Plan must be submitted to the Austin Regional Office with the appropriate fees

Ms. Jeanell Davis, Operations Manager Page 5 May 4, 2006

for review and approval by the executive director prior to commencing any additional regulated activities.

At project locations where construction is initiated and abandoned, or not 14. completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

If you have any questions or require additional information, please contact Mr. Gene Muller of the Edwards Aquifer Protection Program of the Austin Regional Office at (512) 339-2929.

Sincerely,

Glenn Shankle **Executive Director**

GS/ghm

Enclosure:

Change in Responsibility for Maintenance on Permanent BMPs-Form

TCEQ-10263

cc: Mr. Elias G. Haddad, P.E., 3103 Bee Cave Rd, Ste 202, Austin, Texas 78746

The Honorable Samuel T. Biscoe, County Judge, Travis County

Mr. Joseph G. Pantalion, P.E., Director, Watershed Protection & Development

Review Department, City of Austin

Mr. David Lopez, Austin-Travis County Health Dept., Environmental Health Unit Mr. Kirk Holland, P.G., General Manager, Barton Springs/Edwards Aquifer Conservation District

TCEQ Central Records



Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

Attachment B: Narrative of Proposed Modification

The proposed 0.15 AC development is the addition of an Excell Aboveground Storage Tank (AST) fuel island on the existing caliche-based parking/storage area. The fueling system will be backed up by one backup generator (150-gallon diesel). The proposed fuel island will include the following:


- 1. One (1) 10,000 Gallon double-walled AST split 7,000 gal Diesel/3,000 gal Gas UL 2085 Fireguard tank with rod ladder and e-vents
- 2. Two (2) 20-Gallon remote spill basins with 3" fill piping, 3" ball valves and 3" quick fill connections
- 3. Two (2) 2" X 3" overfill devices set at 90%
- 4. Two (2) DEF blue boxes with pulse output with external filters and 5-minute timers
- 5. Three (3) Centeron Cell Monitors with 500 call block
- 6. Franklin DEF nozzle and hose
- 7. One (1) Fuelmaster 6-hose FMS with network capable
- 8. One (1) 4' 500-Gallon DEF Poly Tank

The proposed construction will not change the existing Impervious Cover (IC). Therefore, the CZP Modification request does not require additional Permanent BMPs. The existing CZP (Edwards Aquifer Protection Program ID No.: 11-06030101 approval letter dated May 4, 2006) included a retention/irrigation system Permanent BMP for stormwater water quality control. The retention/irrigation system BMP was designed to meet the required 80% removal of the increased load in total suspended solids of the original project in 2006. The proposed modification does not increase the Impervious Cover (IC) at the site. The existing retention/irrigation system BMP will continue to meet requirements to treat stormwater runoff at the site.



Modification of a Previously Approved Contributing Zone Plan (TCEQ-10259)

Attachment C: Current Site Plan of the Approved Project





Contributing Zone Plan Application (TCEQ-10257)

Contributing Zone Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Date: <u>6/15/2023</u>

Signature of Customer/Agent:

Regulated Entity Name: PEC Oak Hill

Project Information

1. County: Travis

2. Stream Basin: Colorado River

3. Groundwater Conservation District (if applicable): Edwards Aquifer/Barton Springs

4. Customer (Applicant):

Contact Person: Bud Collora

Entity: Pedernales Electric Cooperative, Inc.

Mailing Address: P.O. Box 1

City, State: <u>Johnson City, Texas</u> Zip: <u>78636</u> Telephone: Fax:

Email Address: bud.collora@peci.com

6/19/2023

5.	Agent/Representative (If any):
	Contact Person: Nick Sandlin, P.E. Entity: Sandlin Services, LLC Mailing Address: 8500 N. Mopac Expy Suite 820 City, State: Austin, Texas Zip: 78759 Telephone: 806-679-7303 Fax: Email Address: nick@sandlinservices.com
6.	Project Location:
	 ☐ The project site is located inside the city limits of ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of <u>Austin, TX</u>. ☐ The project site is not located within any city's limits or ETJ.
7.	The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.
	9115 Circle Dr, Austin, TX 78736
8.	Attachment A - Road Map. A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
9.	Attachment B - USGS Quadrangle Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:
	☑ Project site boundaries.☑ USGS Quadrangle Name(s).
10.	Attachment C - Project Narrative. A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application an contains, at a minimum, the following details:
	 ✓ Area of the site ✓ Offsite areas ✓ Impervious cover ✓ Permanent BMP(s) ✓ Proposed site use ✓ Site history ✓ Previous development ✓ Area(s) to be demolished
11.	Existing project site conditions are noted below:
	Existing commercial site Existing industrial site Existing residential site

Existing paved and/or unpaved roadsUndeveloped (Cleared)Undeveloped (Undisturbed/Not cleared)Other:
12. The type of project is:
Residential: # of Lots: Residential: # of Living Unit Equivalents: Commercial Industrial Other:
13. Total project area (size of site): <u>20.6</u> Acres
Total disturbed area: <u>0.15</u> Acres
14. Estimated projected population: <u>N/A</u>
15. The amount and type of impervious cover expected after construction is complete is show below:
Table 1 - Impervious Cover

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	14,427	÷ 43,560 =	0.33
Parking	206,684	÷ 43,560 =	4.74
Other paved surfaces		÷ 43,560 =	
Total Impervious Cover	221,111	÷ 43,560 =	5.08

Total Impervious Cover $5.08 \div$ Total Acreage $20.6 \times 100 = 24.6 \%$ Impervious Cover

16. 🔀	Attachment D - Factors Affecting Surface Water Quality. A detailed description of all
	factors that could affect surface water quality is attached. If applicable, this includes the
	location and description of any discharge associated with industrial activity other than
	construction.

17. Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

For Road Projects Only

Complete questions 18 - 23 if this application is exclusively for a road project.

∇Z	B I / A
$I \times I$	NI/A
\sim \sim	14//

18. Ty	pe of project:
	 TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways.
19. Ty _l	pe of pavement or road surface to be used:
	Concrete Asphaltic concrete pavement Other:
20. Rig	ght of Way (R.O.W.):
Wi	ngth of R.O.W.: feet. idth of R.O.W.: feet.
21. Pa	vement Area:
Wi L x	ngth of pavement area: feet. idth of pavement
22.	A rest stop will be included in this project.
	A rest stop will not be included in this project.
23.	Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.
Stor	rmwater to be generated by the Proposed Project
24. 🔀	Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.
Was	stewater to be generated by the Proposed Project
	Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied. N/A

26. Wastewater will be disposed of by:		
On-Site Sewage Facility (OSSF/Septic Tank):		
 ■ Attachment F - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities. ■ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285. 		
Sewage Collection System (Sewer Lines): The sewage collection system will convey the wastewater to the (name) Treatment Plant. The treatment facility is:		
Existing. Proposed.		
⊠ N/A		
Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons		
Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.		
□N/A		
27. Tanks and substance stored:		

Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1	10,000	Diesel/Gas	A36 MILD CARBON STEEL (UL 2085, DOUBLE WALLED)
2	500	Diesel Exhaust Fluid	POLY
3			
4			
5			

Total x 1.5 = <u>15,750</u> Gallons

one-half (1 one tank sy	I be placed within a 1/2) times the stora stem, the containmental transfer cannulative storage cannulative	nge capacity of the sent structure is size	system. For facilitie d to capture one ar	es with more than
for providin	t G - Alternative Sec ng secondary contair for the Edwards Aqu	nment are proposed		
	ons and capacity of o		ure(s):	
Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons
			_	otal: Gallons
Some of the structure. The piping was the piping was a structure.	noses, and dispenser e piping to dispenser will be aboveground will be underground	rs or equipment wil	l extend outside the	e containment
	s) being stored. The		•	
_	t H - AST Containme nt structure is attach		_	ring of the
☐ Internal ☐ Tanks cle ☐ Piping c	dimensions (length, drainage to a point early labeled learly labeled er clearly labeled			
storage tan	nust be directed to a k facilities must be r ours of the spill.	=		

 In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly. In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.
Site Plan Requirements
tems 34 - 46 must be included on the Site Plan.
34. \boxtimes The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = <u>30</u> '.
35. 100-year floodplain boundaries:
 Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled. No part of the project site is located within the 100-year floodplain. The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s):
36. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. $igotimes$ A drainage plan showing all paths of drainage from the site to surface streams.
38. \boxtimes The drainage patterns and approximate slopes anticipated after major grading activities.
39. 🔀 Areas of soil disturbance and areas which will not be disturbed.
40. \(\simega\) Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. 🔀 Locations where soil stabilization practices are expected to occur.
42. Surface waters (including wetlands).
⊠ N/A
43. Locations where stormwater discharges to surface water.
There will be no discharges to surface water.
14. Temporary aboveground storage tank facilities.

	Temporary aboveground storage tank facilities will not be located on this site.
45.	Permanent aboveground storage tank facilities.
	Permanent aboveground storage tank facilities will not be located on this site.
46.	☐ Legal boundaries of the site are shown.
Pe	ermanent Best Management Practices (BMPs)
Pra	actices and measures that will be used during and after construction is completed.
47.	 □ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction. □ N/A
48.	These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
	 The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site. A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is:
	⊠ N/A
49.	Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
	⊠ N/A
50.	Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	 The site will be used for low density single-family residential development and has 20% or less impervious cover. The site will be used for low density single-family residential development but has more than 20% impervious cover.

	$igstyle{igstyle}$ The site will not be used for low density single-family residential development.
51.	The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	 Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. □ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. □ The site will not be used for multi-family residential developments, schools, or small business sites.
52.	Attachment J - BMPs for Upgradient Stormwater.
	 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
53.	Attachment K - BMPs for On-site Stormwater.
	A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
54.	<u> </u>
	that prevent pollutants from entering surface streams is attached.
	⊠ N/A
55.	Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and 9 of 11

		dated. Construction plans for the proposed permanent BMPs and measures are attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.
[N/A
56.		Attachment N - Inspection, Maintenance, Repair and Retrofit Plan . A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
		 Prepared and certified by the engineer designing the permanent BMPs and measures Signed by the owner or responsible party Outlines specific procedures for documenting inspections, maintenance, repairs,
		and, if necessary, retrofit. Contains a discussion of record keeping procedures
[\boxtimes	N/A
57.		Attachment O - Pilot-Scale Field Testing Plan . Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
[\boxtimes	N/A
58.		Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
	\times	N/A
	_	oonsibility for Maintenance of Permanent BMPs and sures after Construction is Complete.
59.		The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60.		A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a

multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

Administrative Information

61. 🔀	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
62. 🔀	Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
63. 🗌	The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
\boxtimes	The Temporary Stormwater Section (TCEQ-0602) is included with the application.




Contributing Zone Plan Application (TCEQ-10257)

Attachment A: Road Map



Source: Google Earth Pro (accessed June 5, 2023)








Contributing Zone Plan Application (TCEQ-10257)

Attachment B: USGS Quadrangle Map FEMA FIRM Map




Source: Portion of USGS Quadrangle Map (TX_Signal_Hill_20220808_TM_geo)

U.S. DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY







NU

Grid Zone Designation

PU


This map is not a legal document. Boundaries may be generalized for this map scale. Private lands within government reservations may not be shown. Obtain permission before

entering private lands.

Hydrography..... Contours.... Boundaries....

Imagery.... Roads..... Names.....

Wetlands...



This map was produced to conform with the National Geospatial Program US Topo Product Standard.


QUADRANGLE LOCATION 2 3 1 Shingle Hills 2 Bee Cave 3 Austin West 5 AUSTIN West
4 Dripping Springs
5 Oak Hill
6 Driftwood
7 Mountain City
8 Buda ADJOINING QUADRANGLES




SIGNAL HILL, TX

2022






FEMA FIRMette Map Panel 48453C0560J (Effective Date: January 22, 2020)



FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR DRAFT FIRM PANEL LAYOUT



Limit of Study

Jurisdiction Boundary

OTHER

FEATURES

NOTES TO USERS

For information and questions about this Flood Insurance Rate Map (FIRM), available products associated with this FIRM, including historic versions, the current map date for each FIRM panel, how to order products, or the National Flood Insurance Program (NFIP) in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Flood Map Service Center website at https://msc.fema.gov. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report,

and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website.

Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well

as the current FIRM Index. These may be ordered directly from the Flood Map Service Center at the number

listed above. For community and countywide map dates, refer to the Flood Insurance Study Report for this jurisdiction.

To determine if flood insurance is available in this community, contact your Insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

Basemap information shown on this FIRM was provided in digital format by the United States Geological Survey (USGS). The basemap shown is the USGS National Map: Orthoimagery. Last refreshed October, 2020.

This map was exported from FEMA's National Flood Hazard Layer (NFHL) on 6/5/2023 1:59 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time. For additional information, please see the Flood Hazard Mapping Updates Overview Fact Sheet at https://www.fema.gov/media-library/assets/documents/118418

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards. This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date.

SCALE

Map Projection: GCS, Geodetic Reference System 1980; Vertical Datum: NAVD88 For information about the specific vertical datum for elevation features, datum conversions, or vertical monuments used to create this map, please see the Flood

	Ins	urance Stu	dy (FIS) R	Report	for your con	nmunity at https://	msc.fema.gov
	1	inch =	1,000	feet		1:12,0	000
	0	500	1,000		2,000	3,000	4,000
N I						Meters	Feet
1	0	105 210) 4	-20	630	840	

NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

PANEL 560 of 730

COMMUNITY TRAVIS COUNTY VILLAGE OF BEAR

CITY OF AUSTIN

National Flood Insurance Program **Panel Contains:**

NUMBER **PANEL** 481026 0560 481679 0560 480624 0560

> MAP NUMBER 48453C0560J **EFFECTIVE DATE** January 22, 2020



Attachment C: Project Narrative

Proposed Development

The project site is 0.15 AC within the developed caliche-based parking storage area of the developed 20.6 AC site located at 9115 Circle Drive, Austin, Texas. The previously developed 20.6 AC area is part of the 66.437 AC tract owned by Pedernales Electric Cooperative, Inc. (Special Warranty Deed Document # 2006098055). The property is located inside the Austin 2 Mile ETJ in Travis County. The southern portion of the 66.437 AC tract is undeveloped. The northern site area is developed land, including an existing 6,902 SF office building, 7,525 SF warehouse building, and caliche-based parking/storage area. The facility currently serves as an operations center for the Pedernales Electric Cooperative, including customer service and bill payment, storage of power poles, transformers, other utility construction and maintenance materials, and equipment.

The proposed development is the addition of an Excell Aboveground Storage Tank (AST) fuel island on the existing caliche-based parking/storage area and one backup generator (150-gallon diesel). The fuel island will include the following:

- 1. One (1) 10,000 Gallon double-walled AST split 7,000 gal Diesel/3,000 gal Gas UL 2085 Fireguard tank with rod ladder and e-vents
- 2. Two (2) 20-Gallon remote spill basins with 3" fill piping, 3" ball valves and 3" quick fill connections
- 3. Two (2) 2" X 3" overfill devices set at 90%
- 4. Two (2) DEF blue boxes with pulse output with external filters and 5-minute timers
- 5. Three (3) Centeron Cell Monitors with 500 call block
- 6. Franklin DEF nozzle and hose
- 7. One (1) Fuelmaster 6-hose FMS with network capable
- 8. One (1) 4' 500-Gallon DEF Poly Tank

The fueling system will be backed up by a 150 gal. diesel generator.

The property is within the Edwards Aquifer Contributing Zone. The existing Contributing Zone Plan (CZP) included a retention/irrigation system Permanent BMP for stormwater water quality control. The retention/irrigation system BMP was designed to meet the required 80% removal of the increased load in total suspended solids of the original project in 2006. The requested project modification does not increase the Impervious Cover (IC) at the site. The existing retention/irrigation system Permanent BMP continues to treat stormwater runoff at the site.

PEC Oak Hill CONTRIBUTING ZONE PLAN MODIFICATION



Site Description and History

The 20.6 AC project site is located at 9115 Circle Drive, Austin, Texas, and is part of the 66.437 AC tract owned by Pedernales Electric Cooperative, Inc. (Special Warranty Deed Document # 2006098055 dated May 24, 2006). The property includes a Restrictive Covenant (document # 006096133) requiring compliance with the Integrated Pest Management (IPM) Plan of record and the Source Control Plan of record (O.P.-06-0508B). Legal description of the property is LOT 1 BLK A PEDERNALES ELECTRIC COOPERATIVE CIRCLE DRIVE AUSTIN SUBD.

The project site (20.6 AC) is on land with 0% - 15% slopes. Elevation at the project site is between 1080 ft and 1084 ft. There is no vegetation at the project site, as proposed construction is located on an existing parking lot area.

Access

Existing access to the project site is at 9115 Circle Drive, Austin, TX.

Impervious Cover (IC)

Total existing area of impervious cover is approximately 5.08 AC associated with existing buildings, driveways and caliche-based parking and storage area. The construction of a fueling island on the existing caliche-based parking and storage area will not change the existing IC. No change is proposed to the existing permanent BMP at the site.

Watershed and FEMA Floodplain Information

The project site is within the Onion Creek-Colorado River Watershed, which drains to the Colorado River Basin. No surface streams run across the property. Drainage is generally to the south, toward Slaughter Creek segment 1427A, which is approximately 2.0 miles southeast of the project site. Slaughter Creek flows to the southeast and eventually joins Onion Creek.

The 0.15 AC project site is in Zone X of FEMA FIRM Map No. 48453C0560J (effective 1/22/2020).

No additional permanent BMPs are proposed for stormwater drainage and water quality at the developed project site. After the proposed construction of the AST fueling island, total impervious cover (IC) at the property will remain approximately 24.6%.

Temporary Best Management Practices (BMPs)

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site.

PEC Oak Hill CONTRIBUTING ZONE PLAN MODIFICATION



Prior to soil disturbing construction activity, temporary BMPs will be installed. Silt fencing will be installed along the down-gradient sides of the property to intercept and detain waterborne sediment from unprotected areas. The fiber roll shall remain in place until the disturbed area is permanently stabilized.

Permanent Best Management Practices (BMPs)

The existing approved retention/irrigation BMP for stormwater drainage and water quality at the developed site will continue to provide required 80% reduction in stormwater sediments. Total impervious cover (IC) at the property will not change as a result of the proposed construction of an AST and fueling island in the existing caliche-based parking/storage area.

The existing retention/irrigation BMP is maintained according to the approved CZP document No: 11-06030101 approved May 4, 2006.

Offsite Areas

No offsite areas are anticipated to be affected by pre and post construction activities at the site. Temporary BMPs will minimize any anticipated effects of the proposed construction activities. The proposed development will not change the IC at the site. The existing permanent BMP will address stormwater issues at the developed site.



Attachment D: Factors Affecting Surface Water Quality

No surface streams cross the property. The Slaughter Creek segment 147A is approximately 2.0 miles southeast of the project site. No surface water quality impacts are expected.



Attachment E: Volume and Character of Stormwater

The proposed AST fueling site includes a double-walled AST fuel tank for secondary containment, and the fueling island is covered by a permanent constructed canopy. No change in the volume and character of stormwater at the site is expected.



Attachment F:
Suitability Letter from Authorized Agent (if OSSF is proposed)
NOT APPLICABLE




Attachment G: Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)


The 10,000-gallon AST is a double-walled, split 10/3 UL 2085 Fireguard tank with rod ladder and e-vents. The double-walled tank construction provides the required secondary containment.



Attachment H: AST Containment Structure Drawings



- 1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.
- 3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.
- 4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF CONSTRUCTION.
- 5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.
- 6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.
- 7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.
- 8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.
- 9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA FOR 14 DAYS.
- 10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.
- 11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.
- 12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.
- 13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL.




LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION . FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE**



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.




DRAINAGE AREA BOUNDARY

DRAINAGE AREA DESIGNATION AND AREA DRAINED



FLOW ARROW



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

EROSION CONTROL AND DRAINAGE PLAN


SHEET 7 OF 9


P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS


SANDLIN

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2: AUSTIN, TX 78727






PROPERTY KEY MAP



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE





SANDLIN

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727

Table of contents:

- 1.) Site plan, TCEQ Notifications & tank schematic
- 2.) Gasboy Dispenser & Containment
- 3.) Hanging hardware and hose retractor
- 4.) Red Jacket submersible pump
- 5.) Diesel exhaust fluid equipment
- 6.) Emergency valves
- 7.) Remote fill connection and basin
- 8.) Product piping and flex connector
- 9.) FuelMaster fuel management unit
- 10.) NFPA Placards
- 11.) Emergency Stop button







FLEET & COMMERCIAL

FUELING



CONTENTS

Gasboy Overview			
9853 Electronic High Flow.			
9850 Electronic Ultra-Hi .			. 4
9216 Satellite			. (
9862 Electronic DEF			. 8
9872 Electronic E85			. 10
Atlas PRIME			. 12
9153 Mechanical High Flow			.]
9823 ASTRA Electronic AST			. 10
Model List			. 18
Features and Options			. 20

ATLAS SERIES

FUELING EQUIPMENT

Gasboy has been producing refueling equipment since the 1920's. The Atlas Series is the latest generation in a long line of fleet-fueling equipment and is the workhorse for the tough Fleet and Commercial environment. It's compatible with the Gasboy PLUS Fuel Management System or a wide range of third-party controllers.

The Atlas Platform Offers:

- A wide range of models and flow rates
- Sophisticated electronics or simple mechanical registers which cover all requirements
- Use in Underground Tanks (UST) or Aboveground Tanks (AST) applications

Common Features in the Atlas Platform Include:

- Rugged and welded G90 galvanized-steel frame
- Structural foam bezel with a clear polycarbonate window, and a backscreen polycarbonate dialface
- Field-wiring junction box for easy installation
- Replaceable sheathing painted or optional 304 embossed stainless steel
- Standard hydraulics compatible with traditional motor fuels such as Biodiesel (up to B20) and Ethanol (up to E15); custom models are available for E85, B100 or DEF
- Safety listed and with NTEP CoC for W&M sealing for fuel resale application
- Optional High Retrievers and Catlow's hanging hardware to complete your fleet fueling equipment



ATLAS 9853K

ELECTRONIC HIGH FLOW

Basic High Flow

The 9853K Series Basic High Flow Atlas has electronic displays. Available in a complete range of pump or dispenser style models. Versatile for most high-flow fleet fueling applications.

EASY USE	Large 1" LCD display with LED backlight and capacitor back up. LED lighting to identify fuel grade and illuminate the front panel.
FAST	High-flow rated at 22 gpm with side load or optional front load nozzle positions.
INTEGRATED	RS485 or Pulse Output interface for connectivity to Gasboy PLUS or other third-party site controllers.
DURABLE	Four-piston CFT meter with flow-through center chamber for harsh fuels. Large 1" internal piping for high flow rates in a variety of site conditions. Steel internal tubing on most models. 10-vane suction pump with 1-HP motor.
OPTIONS	Satellite piping option can turn your Atlas into a master / satellite fueling position.



•

ATLAS MODELS

G A S B O Y M O D E L S

Model Number	Description	Туре	Hoses	Products	Register	Flow Rating
9153K						
9153K	Hi-flow Single Pump	Pump	1	1	Mech	22 gpm
9152KTW1	Std-flow Twin 1 Pump	Pump	2	1	Mech	15 gpm
9153KTW1M	Hi-flow Twin 1 Pump	Pump	2	1	Mech	22 gpm
9153KTW2	Hi-flow Twin 2 Pump	Pump	2	2	Mech	22 gpm
9153KX	Hi-flow Single Dispenser	Dispenser	1		Mech	22 gpm
9153KXTW1	Hi-flow Twin 1 Dispenser	Dispenser	2	1	Mech	22 gpm
9153KXTW2	Hi-flow Twin 2 Dispenser	Dispenser	2	2	Mech	22 gpm
9853K						
9853K	Hi-flow Single Pump	Pump	1	1	Elec	22 gpm
9852KTW1	Std-flow Twin 1 Pump	Pump	2	1	Elec	15 gpm
9853KTW1M	Hi-flow Twin 1 Pump	Pump	2	1	Elec	22 gpm
9853KTW2	Hi-flow Twin 2 Pump	Pump	2	2	Elec	22 gpm
9853KX	Hi-flow Single Dispenser	Dispenser	1	1	Elec	22 gpm
9853KXTW1	Hi-flow Twin 1 Dispenser	Disnenser	2	1	Flec	22 anm
9853KXTW2	Hi-flow Twin 2 Dispenser	Dispenser	2	2	Elec	22 gpm
9040K						
9840K	Super-hi Single Pump	Pump	1	1	Elec	40 gpm
9840KX	Super-hi Single Dispenser	Dispenser	1	1	Elec	40 gpm

Model Number Description		Туре	Hoses	Products	Register	Flow Rating
9850K						
9850K	Ultra-hi Flow Single Pump	Pump	1	1	Elec	50 gpm
9850KTW3	Ultra-hi Flow Combo Pump	Pump Combo	2	1	Elec	50 gpm
9850KX	Ultra-hi Flow Single Disp	Dispenser	1	1	Elec	50 gpm
9850KXTW1	Ultra-hi-Flow Twin 1 Disp	Dispenser	2	1	Elec	50 gpm
9850KXTW2	Ultra-hi Flow Itwin 2 Disp	Dispenser	2	2	Elec	50 gpm
9850KXTW3	Ultra-hi Flow Combo Disp	Disp Combo	2	1	Elec	50 gpm
9862K						
9862KX—Z	DEF — Cold Weather	Dispenser	1	1	Elec	
9862KX—WW	DEF — Warm Weather	Dispenser	1	1	Elec	
9862KX—ZWW	DEF — Warm Weather	Dispenser	1	1	Elec	
9872K						
9872KX	E85 — Single	Dispenser	1	1	Elec	15 gpm
9872KXTW1	E85 — Twin 1	Dispenser	2	1	Elec	15 gpm
9823K						
9823K	ASTRA Split AST Pump	Pump	1	1	Elec	21 gpm
9216K						
9216K	Satellite	Satellite	1	1	None	
9216KTW	Satellite	Satellite	2	1	None	

ATLAS FEATURES

G A S B O Y M O D E L S

Feature	Short Description	9853	9840	9850	9823	9872	9862 CW	9862 WW	9153	9216
	Safety: UL and cUL Listed	S	S	S	S	S	MET	MET	S	S
Approvals	W&M: NCWM, Measurement Canada (MC)	S	S	S	S	S	S	S	S	S
Working Pressure	50 psi maximum	S	S	S	S	S	S	S	S	S
Operating Temp	-30°C to +55°C	S	S	S	S	S	S	-11°C	S	S
Unit of Measure	Gallons (liters optional)	S	S	S	S	S	S	S	S	_
	Gilbarco 4 piston PD CFT Meter	S	S	_	S	S	_	_	S	_
Meter	Liquid controls 6 step rotary PD Meter	_	_	S	_	_	_	_	_	_
	Coriolis Mass Flow Meter	_	_	_	_	_	S	S	_	_
	1 HP CD — 115V/60Hz (230V/50Hz optional)	S	S	_	S	_	-	-	S	_
Motors/Voltages	1½ HP CD — 115V/60Hz (230V/50Hz optional)	_	_	S	_	_	_	_	_	_
	3/4 HP CD 380V/50Hz/3-phase	0	0	_	0	_	_	_	0	_
	10 vane rotary w/air separator	S	S	_	S	_	_	_	S	_
Pump Models	High speed rotary vane w/air separator	_	_	S	_	_	_	_	_	_
Solenoid Valve	2-stage valve for Preset Operation (PP)]"	1½"	1½"]"]"	3/4"	3/4"]"	1½"
Filters	Internal spin-on style (F)	S	S	Strainer	S	S	Strainer	Strainer	S	_
1111612	External Canister Type	0	0	0	0	_	_	_	0	0
Piping	Internal Fuel Piping	1"	1½"	1½"	1"	1"	3/4"	3/4"	1"	1½"
Discharge	Hose Connection — NPT	1"	11/4"	11/4"	1"	3/4"	1" BSPP	1" BSPP	1"	11/4"
Satellite Piping	Satellite piping connection (S) — disp only	0	0	0	_	_	-	-	0	_
Inlet	Island Connection — NPT	1½"	2"	2"	1½"	1½"	1" BSPP	1" BSPP	1½"	1½"
Junction Box	Field Wiring Junction Box	S	S	S	S	S	S	S	S	S
Housing	G90 Galvanized Steel	13 GA	13 GA	13 GA	11 GA	13 GA	13 GA	13 GA	13 GA	13 GA
Panels	Lockable removable — Painted Galvanized Steel (std) — gauge	20	20	20	16	20	20	20	20	20
i uilGis	Lockable removable — Kooline Stainless Steel — 22 gauge	0	0	0	_	0	_	0	0	0
Sheathing	Replaceable — Painted G60 Galvanized Steel (std) — gauge	20	20	20	16	20	20	20	20	20
Juganing	Replaceable — Kooline Stainless Steel — 22 gauge	0	0	0	_	0	0	0	0	0

Feature	Short Description	9853	9840	9850	9823	9872	9862 CW	9862 WW	9153	9216
Computer/Register	Electronic Register — Volume only display	S	S	S	S	S	S	S	-	_
Component Register	Mechanical Register — VR10 volume only	_	_	_	_	_	_	_	S	_
Electronic Display	1" LCD w/LED Backlight & Capacitor Backup	S	S	S	S	S	S	S	-	_
	Pulser — 10:1 or 100:1 volume (CC or CX)	_	-	_	-	-	_	-	0	_
Interface Options	RS-485 — Gasboy CFN, Islander, or TopKat	0	0	0	0	0	0	0	_	_
illieriace opiiolis	Pulse Output I/F	0	0	0	0	0	0	0	_	_
	DC conduit and junction box (D)	S	S	S	_	S	S	S	_	_
	Keytrol (EK)	_	_	_	_	_	_	_	0	_
TopKAT PLUS	TopKAT PLUS with Ethernet conduit (factory install)	0	0	0	_	0	0	0	_	_
Brand Panel Lighting	LED Lighted brand panel (L)	0	0	0	_	0	0	0	0	_
	Electronic	S	S	S	S	S	S	S	_	_
Totalizers	Non-resettable Electro-mechanical	0	0	_	_	0	0	0	_	_
	Non-resettable mechanical	_	_	0	0	_	_	_	S	_
Namela Daggara	Side load	S	S	S	_	S	_	S	S	_
Nozzle Position	Front load (Z)	0	0	0	S	0	S	0	_	S
	Internal hose retractor (I)	0	0	_	_	_	_	_	0	_
Hose Retractors	Internal hose reel	_	_	_	_	_	S	_	_	_
	High hose retractor — external post mounted	0	0	0	0	0	_	0	0	0
ACT A . P	Pressure Regulating Valve Model 52A — suction pumps only	0	_	_	0	_	_	_	0	_
AST Applications	9850 Above Ground Tank Kit — suction pumps only	_	_	0	_	_	_	_	_	_
W	12 month — Parts and labor	S	S	S	S	S	S	S	S	S
Warranty	Extended — 2, 3, 4 or 5 years	0	0	0	0	0	_	_	0	0
	ATC (Canada only)	0	0	0	_	_	_	_	_	_
	Hand crank (K)	_	_	_	_	_	-	_	0	_
	Power reset	_	_	_	_	_	-	_	S	_
II	Display power fail backup	S	S	S	S	S	S	S	_	_
Miscellaneous	Internal cabinet heater (DEF only)	_	_	_	_	_	S	_	_	_
	Balanced vapor recovery	0	_	_	0	_	_	_	0	_
	Healy Universal Kit compatible	0	_	_	_	_	_	_	0	_
	Hose, nozzle, swivel, breakaway	0	0	0	0	0	0	0	0	0

S = Standard; 0 = Optional; -= not available

21



www.gasboy.com

P-7080 | 022217 | Gilbarco Veeder-Root | 7300 W. Friendly Ave., Greensboro, NC 27410

Model 434 Dispenser Pedestal

SPECIFICATION SHEET

Application

Dispenser pedestals serve as a raised platform for piping and installing dispensers/pumps in aboveground fueling systems.

Features and Details

- · Provides containment for small leaks in dispenser piping
- AST pedestal sold with a dispenser specific mounting platform
- Dispenser pedestal less entry penetrations for desired placement in the field
- · Pre-drilled anchor holes
- Dispenser mounting platform overhangs the pedestal base minimizing the ability for water penetration
- · Stabilizer bar kits included
- · Connection boots available
- Water tested liquid tight to the 6" level (18 gallon capacity)

Materials of Construction

434

12 gauge steel, powder coated black

434S

• 12 gauge 304 stainless steel

Certifications and Listings

Florida DEP EQ-823







434CB-0075 1B (3/4") through 434CB-02001B (2")



Specific item numbers and model details on next page.







Item Number	Description	Single (S) or Dual (D) Products	Opening Size (L x W)	Dispenser/Pedestal selection guide	Weight (lbs)
43412001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	14½" x 10"	Gasboy 215/216A	140.0
43412002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	14½" x 10"	Gasboy 215/216A	140.0
43414001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	125.70
43414002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	134.87
43417001 AK	AST pedestal base, platform, & 1 stabilizer bar kit	S	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	122.20
43417002 AK	AST pedestal base, platform, & 2 stabilizer bar kits	D	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	131.37
434S-14001 AK	SS AST pedestal base, platform, & 1 stabilizer bar kit	S	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	125.7
434S-14002 AK	SS AST pedestal base, platform, & 2 stabilizer bar kits	D	22¼" x 12"	Gasboy Atlas 8700K, 8800K, 9100K, 9800K; Bennett Big Squirt/Big Fueler 3000 series (Pre August 2017)	134.87
434S-17001 AK	SS AST pedestal base, platform, & 1 stabilizer bar kit	S	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	122.2
434S-17002 AK	SS AST pedestal base, platform, & 2 stabilizer bar kits	D	28" x 15"	Wayne Century 3/G2200, Reliance G5200 and G6200, Select 3/G7200	131.37

Accessories

	Item Number	Size	Description	Weight (lbs)	
	434CB-0075 1B	3/,"	Connection boot	0.22	A
	434CB-0100 1B	1"	Connection boot	0.22	
	434CB-0150 1B	1½"	Connection boot	0.61	
	434CB-0200 1B	2"	Connection boot	0.62	1
	434CBB0001 1B		Bonder, connection bond*		
	434CBBA001 1A		Bond applicator, connection boot		
	434SB-0100 AK		AST pedestal stabilizer bar kit		
	434SSB0100 AK		AST pedestal stabilizer bar kit; stainless steel		
_	434VB-0100 AK		Valve mounting bracket for Tok-52 / F- 664 valve		

*One tube of bonder will cover three (3) connection boots.



Product Catalog



Magnetic Breakaway





CATLOW

www.catlow.com

This series of automatic nozzles establishes a new standard for vehicle refueling. The lightweight construction produces a smooth working, rugged nozzle designed for endurance.

The Elite Prepay is specifically designed for self-service or card-lock systems. The no-pressure/no-flow feature enables the station operator to control the dispensing of fuel while the customer has the convenience of a one hand hold-open mechanism for effortless dispensing.

FEATURES and BENEFITS:

- *UL/ULC Listed
- *Automatic shut off
- *Splash shield included with each new nozzle
- *Mates with all standard 5/8" & 3/4" hoses
- *BSPT and BSPP threads available upon request
- *Available in self serve upon request (S)
- *Available with an Attitude Device at an additional charge
- *Full cover provided for added protection
- *Spout assembly easily replaced
- *Completely rebuildable
- * Custom logo available upon request
- * 1 year warranty

MATERIALS:

- *3/4" Single body, sand cast aluminum
- *Lever & handguard is Super-Tuff Glass Filled Nylon
- *O-rings and Seals are Viton
- *Unleaded Spout Assembly 13/16" OD
- *Leaded Spout Assembly 15/16" OD
- *Weight 2.2 lbs.

CATLOW
2750 US RT 40
TIPP CITY, OHIO 45371 USA
Phone (800) 222-8569 Fax (937) 898-8631
www.catlow.com



ORDERING SPECIFICATIONS

PART NUMBER	DESCRIPTION
NENL	NEW, UNLEADED
NEL	NEW, LEADED
NEPNL	NEW, PREPAY UNLEADED
NEPL	NEW, PREPAY LEADED
RENL	REBUILT, UNLEADED
REL	REBUILT, LEADED
REPNL	REBUILT, PREPAY UNLEADED
REPL	REBUILT, PREPAY LEADED

Accessories

PART NUMBER	DESCRIPTION
PART NUIVIDER	DESCRIPTION
CNLS	ELITE UNLEADED SPOUT ASSEMBLY
CLS	ELITE LEADED SPOUT ASSEMBLY
CNLSP	PREPAY UNLEADED SPOUT ASSEMBLY
CLSP	PREPAY LEADED SPOUT ASSEMBLY
CFCxx	ELITE COVER xx
C11Bxx	ELITE PREPAY COVER xx
C376xx	ROUND SPLASH SHIELD XX



CAM TWIST MAGNETIC

In-Line Breakaway



www.catlow.com

The CAM TWIST Breakaway is the only breakaway that gives you the option to easily disconnect, inspect and reconnect while installed. With a twist the breakaway can be taken apart and inspected for damage, corrosion, and wear without removing the breakaway from service.

Designed to be installed between the dispenser and the nozzle. It is simple to inspect the unit. Our unique design seals the internal components before a separation is complete, thus reducing any exposure to product and any environmental impact. With the CAM TWIST alignment and reconnection is easy. Align the two halves together & let the magnets do the work while pushing the unit back together. It's that easy!

CATLOW'S CAM TWIST MAGNETIC IN-LINE DESIGN IS THE FUTURE OF BREAKAWAY TECHNOLOGY!

As a cost saving feature, Catlow has designed a replacement lower half unit so in the event of a drive off, you only have to replace the lower half!

FEATURES and BENEFITS:

- *Inspectable, No "Remove-By" date
- * Patented Magnetic Snap-back Technology
- * Resists "Hydraulic Hammer" problems
- * UL/ULC Listed, CARB Certified, Meets NFPA 30A Codes
- *BSPP & BSPT threads available upon request
- * Separation force designed at 230 or 300 lbs.
- * Durable plastic cover prevents damage during a driveoff
- * Replacement "Lower" half of Breakaway available
- * Reduces Environmental Impact. No need to drain assemblies to change nozzle
- * One year warranty

MATERIALS:

- * Body is Aluminum
- * O-ring & Seals are Viton
- * Cover is Nylon

CATLOW 2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com



ORDERING SPECIFICATIONS

PART NUMBER	DESCRIPTION
CTM75	3/4" NPT (230 LBS PULL FORCE)
CTM100	1" NPT (300 LBS PULL FORCE)
CTMVA	VAC-ASSIST M34 X 1.5 (230 LBS PULL FORCE)
CTM75-HD	3/4" NPT (300 LBS PULL FORCE)
CTM75-L	3/4" LOWER UNIT
CTM75HD-L	3/4" LOWER UNIT, HEAVY DUTY
CTM100-L	1" LOWER UNIT
CTMVA-L	VAC-ASSIST LOWER UNIT

Accessories

PART NUMBER	DESCRIPTION	
A13-SW	8" WHIP HOSE FOR CTM75 or HD	
B9-SW	12" WHIP HOSE FOR CTM100	
V1012-1-SW	12" WHIP HOSE FOR CTMVA	
2976	O'RING KIT CTM75	
2978	O'RING KIT CTM75-HD/CTM100	
2977	O'RING KIT CTMVA	





www.catlow.com

The Twister Swivel from Catlow raises the level of swivel flexibility with two (2) high flow 360 degree rotating swivel ends. Special seals protect this heavy duty swivel from extreme cold weather conditions and is designed for blended fuels.

Its high tech engineering, durable construction and economical price will not only "Twist & Turn" your hoses, but your profits as well.

FEATURES and BENEFITS:

- *Lightweight and maintenance free
- *UL/ULC listed
- *360 degree swivel rotation in middle joint & male end
- *Mates with all standard and diesel hoses
- *Fluorosilicone seals perform to -40 degree F
- *Does not affect existing hose length
- *BSPP & BSPT threads available upon request
- *Minimal flow restriction
- *Both swivel joints have double o-rings
- * 1 year warranty


MATERIALS:

- *Swivel elbow Cast Aluminum
- *Swivel body Cast ZA-12 Zamak
- *Bearing is Acetal

CATLOW

*Seals are Viton and Fluorosilicone

C720-3/4 SWIVEL



C720


Twister Swivels



ORDERING SPECIFICATIONS

	PART NUMBER	DESCRIPTION		
	C720 3/4	3/4"M x 3/4"F		
	C720 1x3/4	1"M x 3/4"F		
>	C720 1x1	1"M x 1"F		
	C720 1X1B100	1"M X 1"F 100% BIO DIESEL FUEL		
	C720 1X1BP	1"M X 1"F BRITISH THREAD		
	C720 3/4BP	3/4"M X 3/4"F BRITISH THREAD		
	C720 3/4E85	3/4"M X 3/4"F E85 FUEL		
	C720 1X1E85	1"M X 1"F E85 FUEL		

C720-1 SWIVEL



2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com





www.catlow.com

The MAX 1 Hi-flow diesel nozzle is designed for durability. This heavy-duty nozzle can be used in high volume truckstop applications as well as high volume service stations.


Available as a standard or prepay (no pressure/no flow) nozzle. The prepay nozzle is specifically designed for unattended self service and cardlock refueling locations. The prepay feature enables the station operator to control the dispensing of fuel.

FEATURES and BENEFITS:

- *Available as full serve or self serve
- *Rugged heavy duty design
- *Automatic shut-off
- *UL/ULC Listed
- *Custom logo available upon request
- *BSPP and BSPT threads available upon request
- *Attitude Device available upon request (AD)
- *Spout assembly easily replaced
- *Full Cover provided for added protection
- *Longer spout with Anchor Bushing available upon request (AR)
- *One-hand, hold open mechanism for effortless operation
- *Mates with all standard hardwall or softwall 1" hoses
- *Completely rebuildable
- * One year warranty

MATERIALS:

- * Body is Sand cast Aluminum
- *Lever/Handguard Super-Tuff glass filled Nylon
- *Seals are Viton
- *Spout is 1-3/16" OD Aluminum Spout
- *Weight 4 lbs.



CATLOW 2750 US RT 40 TIPP CITY, OHIO 45371 USA Phone (800) 222-8569 Fax (937) 898-8631 www.catlow.com



MAX1

ORDERING SPECIFICATIONS

PART NUMBER	DESCRIPTION
NM1	NEW, DIESEL
NM1P	NEW, DIESEL PREPAY
NM1S	NEW, DIESEL SELF SERVE
NM1PS	NEW, DIESEL SELF SERVE, PREPAY
RM1	REBUILT, DIESEL
RM1P	REBUILT, DIESEL PREPAY

Accessories

PART NUMBER	DESCRIPTION		
BS	DIESEL SPOUT ASSEMBLY		
BS-P	DIESEL SPOUT ASSEMBLY PREPAY		
C180 xx	COVER xx identifies color i.e. BK Black		
C076 xx	SPLASH SHIELD xx identifies color i.e. BK		





TERMS AND WARRANTY

Rebuilt Nozzles:

Rebuilt Nozzles are invoiced at exchange price, and terms: Net 30 Days from invoice date. A separate invoice will be issued for core charges. Nozzle cores may be returned within sixty (60) days from invoice date to receive full credit against the core charge invoice.

Terms and Service Charge:

The terms for approved accounts: Net 30 Days on all orders. Terms for core charges: 60 Days Net. A service charge of 1 1/2% per month - 18% annual rate - will be added to all past due accounts.

Freight:

Freight is prepaid when net order to one destination is greater than: \$2,500 All shipments within the continental USA \$3,000 All International & Canadian shipments

Minimum Purchase: (Repair parts are an exception)

\$100.00 per order: All shipments within the continental USA \$500.00 per order: All International & Canadian shipments

Remittance Address:

Please use this address for Remittance ONLY

VEEDER ROOT COMPANY P.O. Box 99502 Chicago, IL 60693-9502

Limited Warranty:

CATLOW expressly warrants that its products shall be free from defects in materials and workmanship for a period of one year from the date of manufacture. This warranty is limited to repair or replacement by CATLOW upon return of the product to the CATLOW factory. This warranty does not apply in the event of any misuse or neglect of the product. The foregoing warranty is the exclusive remedy of purchasers of CATLOW products. CATLOW expressly disclaims any warranties, other than the foregoing express warranty, including the implied warranties of merchantability and fitness for a particular purpose, and disclaims any and all liability for consequential damages resulting from the use of its products.

Warranty Procedure:

All nozzles returned under warranty within 60 days, will be replaced with a new product. If the nozzle is dated beyond 60 days, it will be replaced with a rebuilt nozzle that carries the same warranty. The only exceptions are vapor recovery nozzles. If the nozzle returned to us was originally purchased as a new or rebuilt, that is what will be sent as a replacement.

Vapor recovery nozzles must have the "Nozzle Warranty Tag" completed and returned with the nozzle for the warranty to be honored. VERY IMPORTANT You must include the replacement serial number on the tag for the warranty to be honored. Without the tag, the warranty will not be honored. In addition to this, the vapor recovery nozzle replacement serial number will replace the serial number of the nozzle sent to us under warranty. We will be prorating the remaining warranty on the replacement nozzle.

Returned Goods:

Resalable material of standard manufacture must not be returned without first receiving a Return Goods Authorization number. Products accepted for return must be in first class condition, resalable as new and shipping charges prepaid. Minimum handling charge is 20% deducted from the price paid by the customer, or current price, whichever is lower.

All items shipped to Catlow must have a Returned Goods Authorization number (RGA).



C

OSE RETRIEVER

HOSE RETRACTOR - COUNTERWEIGHT

Application -

Keeping conventional and Stage II vapor recovery coaxial hoses raised to prevent traps in the vapor line. Potential accidents are reduced. Hose life is greatly extended.

Part Number - 880/882





Only from Universal! - Our better looking profile blends in with today's modern dispensers.

Α

Features -

- ✓ Easy to install and maintain
- Adaptable to most dispensers
- ✓ Corrosion resistant construction
- ✓ Plastic bushing minimizes cable wear
- ✓ Compatible with E-85

Construction -

- Aluminum Post (2"x2")
- Cast iron counterweight
- Plastic bushings
- Black polyester cable
- · Includes both side and bottom mounting brackets

Model	Weight (lbs.)	A	В	С	Counter Weight
880	29	78-3/4"	5-1/2"	2-1/4	20lbs
882	38	92"	5-1/2"	2-1/4"	27lbs

Replacement Parts

Part Numbers	Description		<u>† [·]</u>
880-5	Cover Pulley	880-MBC	Square Bracket
880-8	Bushing	880-WA	Weight Assembly (1-1/2" x 1-1/2")
880-8A	Black Nylon Rope	880-WA-2	Weight Assembly (882) (1-3/4" x 1-3/4")
880-A	Body	880-AC	Body Assembly
880-B	Base	880-CA	Cover Assembly
880-C	Cover		

^{*}Custom heights and counterweights available. Call for options.

Notice: Universal Valve Co., products must be used in compliance with applicable federal, state, and local laws and regulations. Product selection should be based on physical specifications and limitations and compatibility with the environment and material to be handled. Universal Valve Co., makes no warranty of fitness for a particular use. All illustrations and specifications in this literature are based on the latest production information available at the time of publication. Prices, materials, and specification are subject to change at any time, and models may be discontinued at any time, in either case, without notice or obligation.













The Red Jacket Submersible Turbine Pump

Key Features:

- Industry's newest motor design
- Track record of unsurpassed reliability
- Designed to maximize safety and ease installation

The cornerstone of your fueling infrastructure. The Red Jacket series submersible turbine pump is the foundation model that sets the standard for high throughput, high reliability fueling applications.

Specifications:

Fuel Compatibility

- 100% Diesel
- 100% Gasoline
- Methanol concentrations up to 20%
- Ethanol concentrations up to 20%
- MTBE, ETBE, or TAME concentrations up to 20%

Designed for Hazardous Locations

• Class 1, Group D atmospheres

Fits installations from 3 $\frac{1}{2}$ to 19' in depth

4 Motor Sizes Available:

- ¾ HP, 60 Hz, 1 phase
- 1 ½ HP, 60 Hz, 1 phase
- X3 1 $\frac{1}{2}$ HP, 60 Hz, 1 phase, high pressure
- 2 HP, 60 Hz, 1 phase

All models available with floating suction adapter

Automatic electrical disconnect plus fuel drain to assist in safe servicing

Siphon Ports:

- 2 available, 1/4" NPT
- Vacuums generated up to 25 in Hg.

Compatible with check valve housing models:

- Standard VR ready check valve for PLLD (410152-001)
- High pressure check valve for high pressure applications (410152-002)

Line Pressure Port: 1 Available, 1/4" NPT

Vent Port: 1 Available, 1/4"NPT

UL Listings:

- 100% Diesel
- 100% Gasoline
- Gasoline and up to: 10% Ethanol, 15% Methanol, 20% MTBE, 20% ETBE, 20% TAME

Other Agency Listings: cUL

Optional stainless steel trapper intake screen blocks corroded tank debris from clogging dispenser filters



Quick Set Final Assemblies (Adjustable)

Horsepower	KW	Length	Floating Suction Adapter	Model Number	Part Number
0.75	0 56	72" - 102"		P75111 R11	410140-001
0.75	0.56	102" - 162"		P75U1 RJ2	410140-002
0./5	0.56	107 - 777		P75UI KJ3	410140-003
0.75	0.56	74.3" - 104.3" *	•	P75U1 RJ1 FSA	410140-004
0.75	0.56	104.3" - 164.3" *	•	P75U1 RJ2 FSA	410140-005
0.75	0.56	164.3" - 224.3" *	•	P75U1 RJ3 FSA	410140-006
1.5	1.13	74.5" - 105"		P150U1 RJ1	410141-001
1.5	1.13	104.5" - 165"		P150U1 RJ2	410141-002
1.5	1.13	164.5" - 225"		P150U1 RJ3	410141-003
1.5	1.13	76.8" - 107.3"	•	P150U1 RJ1 FSA	410141-004
1.5	1.13	106.8" - 167.3"	•	P150U1 RJ2 FSA	410141-005
1.5	1.13	166.8" - 227.3"	•	P150U1 RJ3 FSA	410141-006
1.5	1.13	75.5" - 105.5"		X3P150U1 RJ1	410143-001
1.5 볼	1.13	105.5" - 165.5"		X3P150U1 RJ2	410143-002
1.5	1.13	165.5" - 225.5"		X3P150U1 RJ3	410143-003
1.5 HS 1.	1.13	77.8" - 107.8"	•	X3P150U1 RJ1 FSA	410143-004
1.5 星	1.13	107.8" - 167.8"	•	X3P150U1 RJ2 FSA	410143-005
1.5	1.13	167.8" - 227.8"	•	X3P150U1 RJ3 FSA	410143-006
2	1.5	78.5" - 108.5"		P200U1-3 RJ1	410142-001
2	1.5	108.5" - 168.5"		P200U2-3 RJ1	410142-002
2	1.5	168.5" - 228.5"		P200U3-3 RJ1	410142-003
2	1.5	80.8" - 110.8"	•	P200U1-3 RJ1 FSA	410142-004
2	1.5	110.8" - 170.8"	•	P200U1-3 RJ2 FSA	410142-005
2	1.5	170.8" - 230.8"	•	P200U1-3 RJ3 FSA	410142-006

Fixed-Speed, single phase STP assemblies. Length measured from the top of the eyebolt to the bottom of the motor inlet. All 208/230 Volts.

Fixed Length Final Assemblies (Non-Adjustable)

Horsepower	KW	Length	Floating Suction Adapter	Model Number	Part Number
0.75	0.56	42" - 132"		P75U1 RJ	410166-001
0.75	0.56	133" - 168"		P75U2 RJ	410166-002
0.75	0.56	169" - 222"		P75U3 RJ	410166-003
0.75	0.56	44.3" - 134.3"	•	P75U1 RJ FSA	410166-019
0.75	0.56	135.3" - 168.2"	•	P75U1 RJ FSA	410166-020
0.75	0.56	171.3" - 224.3"	•	P75U1 RJ FSA	410166-021
1.5	1.13	45" - 135"		P150U1 RJ	410173-001
1.5	1.13	136" - 171"		P150U1 RJ	410173-002
1.5	1.13	172" - 225"		P150U1 RJ	410173-003
1.5	1.13	47.3" - 137.3"	•	P150U1 RJ FSA	410173-019
1.5	1.13	138.3" - 173.3"	•	P150U1 RJ FSA	410173-020
1.5	1.13	174.3" - 227.3"	•	P150U1 RJ FSA	410173-021
1.5	1.13	46" - 135"		X3P150U1 RJ	410175-001
1.5 볼	1.13	136" - 171"		X3P150U1 RJ	410175-002
1.5 H 1.5 L 1.5 H 1.5 H	1.13	172" - 225"		X3P150U1 RJ	410175-003
1.5	1.13	48.3" - 137.3"	•	X3P150U1 RJ FSA	410175-019
1.5 🖺	1.13	138.3" - 173.3."	•	X3P150U1 RJ FSA	410175-020
1.5	1.13	174.3" - 227.3"	•	X3P150U1 RJ FSA	410175-021
2	1.5	49" - 138"		P200U1-3 RJ	410174-001
2	1.5	139" - 174"		P200U1-3 RJ	410174-002
2	1.5	175" - 228"		P200U1-3 RJ	410174-003
2	1.5	51.3" - 140.3"	•	P200U1-3 RJ FSA	410174-019
2	1.5	141.3" - 176.3"	•	P200U1-3 RJ FSA	410174-020
2	1.5	177.3" - 230.3"	•	P200U1-3 RJ FSA	410174-021

Fixed length pumps may not be returned to stock.















METERED NOZZLES



DEF BLUE BOX PEDESTAL

FEATURES

- EASY TO INSTALL
- READY TO USE
- · BUILT-IN LOCK

The PIUSI DEF Blue Box Pedestal is specifically designed for wall or tank installation, or can be mounted atop an optional pedestal. It is covered by a lockable metal container which protects the pump when not in use.

PERFORMANCE


9 GPM

FLOW RATE

AC V./Hz
120/60
VOLTAGE
POWER

± 1%

20 MIN





DEF BLUE BOX PEDESTAL (FULLY ASSEMBLED)

PACKAGING (BLUE BOX)										
PART#	WE	GHT	PACKAGING							
PARI#	KG	LBS	мм	INCH	PCS/BOX					
R1611800A	25	55.1	575X32OX6O7	22.6X23.9	1					



































SUZZARABLUE AC 10.6 7.93 00 2.64 2.64 2.725 14.5 21.7 29

P = TOTAL PRESSURE (PSI)

VARIOUS COMPONENTS

- BLUE BOX (R1611800A)
- · SB PRO KIT (PAGE 20)
- MOUNTING PLATE (F20300000)
- PEDESTAL (OPTIONAL) (F1270800)

DETAILS








TEMPERATURE

TYPE OF FLUID WATER

68 °F





MATERIALS

• PUMP:

SUZZARABLUE PUMP AC

PG. 28

• METER:

K24 METER

PG. 46

· NOZZLE:

SUZZARABLUE A6O PG. 64

TECHNIC	AL DATA									
PART #	DESCRIPTION	FI LUDG TVDF	FLOW RATE		VOLTAGE			METER	NOZZLE	HOSE
PARI#	DESCRIPTION	FLUIDS TYPE	L/MIN	GPM	AC V./HZ DC VOLT	POWER WATT	AMP. MAX.	MOD.	TYPE	LENGTH
DEFPEDESTAL	DEF BLUE BOX PEDESTAL TANK KIT	(D) W	34	9	120/60	400	1.95	K24	SUZZARABLUE NOZZLE A6O	20 FT
R1611800A	KIT COMPLETE BOX FOR SUZZARABLUE BOX	-	-	-	-	-	-	-	-	-



DURADEFT NOZZLE

For DEF/AdBlue®

The FLEX-ING™ brand DuraDEF™ nozzle features a specially encapsulated aluminium casting that makes it lightweight yet completely compatible with DEF (Diesel Exhaust Fluid)/ AdBlue®. This nozzle provides the performance and construction specifications required for DEF/AdBlue® delivery with a lightweight, more user-friendly design.

HIGHLIGHTS

- High strength aluminium body and stainless steel spout.
- Protective vinyl scuff guard available in green, yellow, red, blue, black and light blue to match station branding.
- Available with or without hold-open clip.
- Internal components are manufactured from stainless steel or plastic for full DEF/AdBlue® compatibility.
- Sealed in a plastic bag to ensure no contamination.
- Meets all required specifications set by ISO 22241 for DEF/AdBlue® delivery.

SPECIFICATIONS

• Inlet: ¾" BSPP

Spout: 19mm stainless steelSeals and poppet disc: Viton® A

• Packing: PTFE

• Weight / length / height: 2.5 Lbs. / 13.5" / 9"

Body casting: Coated aluminiumHandguard and vac cap: Nylon

• Lever: Electroless nickel plated steel & nylon

Scuff guard: VinylBody cap: Coated zinc

ORDERING INFORMATION

FLDEF A B C D - E - F

- FLDEF = DEF/AdBlue® Hose
- B = Hose Diameter
- $02 = \frac{3}{4}$ "
- C = Hose Length Feet
- Use three-digit format
- D = Hose Length Inches
- Use two-digit format
- E & F = End Fitting Options
- 2N = ¾" NPT
- 2P = 34" BSPP
- 3P = 1" BSPP

Model	Description
DURADEF-LB	Light Blue DuraDEF nozzle with locking clip
DURADEF-LB-O	Light Blue DuraDEF nozzle without locking clip



HOSE For DEF/AdBlue®

FLEX-INGTM brand diesel exhaust fluid hose features a specially formulated low-extraction EPDM rubber tube making it completely compatible with DEF/AdBlue®. The flexible softwall construction provides superior handling for both standard and reel applications. Each curb hose length features dual anit-kink sleeves at each end to protect the hose from accelerated wear and kinking. The anti-kink sleeves are factory installed over the end fitting ferrule to ensure maximum wear protection.

HIGHLIGHTS

- Peroxide cured tube provides superior extraction levels and significantly reduces contamination.
- Premium polyester braided construction reduces volumetric expansion.
- Integrated static wire.
- All curb hoses over 2' in length are outfitted with factory installed anti-kink sleeves on both ends.
- BSPP outlets include a fluoroelastomer flat seal to ensure compression tightness.

SPECIFICATIONS

- Tube: Specially formulated low-extraction EPDM rubber, peroxide cured
- Reinforcement: Polyester braid
- Cover: Specially formulated EPDM
- Temperature: -40 °F to 257 °F (-40 °C to 125 °C)

Approvals

 Meets ISO 22241 standard ensuring desirable characteristics of AUS 32 (DEF) are met, such as quality, safety, reliability and contamination.

ORDERING INFORMATION

FLDEF A B C - D - E

- FLDEF = DEF/AdBlue® Hose
- A = Hose Diameter
- 2 = ³/₄"
- B = Hose Length Feet
- · Use three-digit format
- C = Hose Length Inches
- Use two-digit format
- D & E = End Fitting Options
- 2N = ¾" NPT
- 2P = 3/4" BSPP
- 3P = 1" BSPP
- 3PF = 1" BSPP Female Swivel

Example: FLDEF200906-2N-2N = Def/Adblue® hose, %" diameter, 9 feet 6 inches length, %" NPT fitting on both ends.











SWIVEL BREAK AWAY

For DFF/AdRlue®

FLEX-INGTM brand diesel exhaust fluid swivel break aways provide in-line protection for hanging hardware in the event of a drive off. These break aways feature a stainless steel body that makes them extremely durable and completely compatible with DEF/AdBlue®. The break away design ensures proper drive-off protection and allows for easy installation directly between the nozzle and hose. The integrated swivel action provides easy nozzle rotation during vehicle filling while also helping to reduce hose wear and kinking.

HIGHLIGHTS

- High strength stainless steel body with internal components that are completely compatible with DEF/ AdBlue®.
- Break away valves separate with axial or up to 30° angular force.
- Fluid release limited to less than 10 ml upon break away valve separation.
- Atmospheric inner seal protects from corrosion.
- Integrated swivel action provides easy nozzle rotation during vehicle filling while also helping to reduce hose wear and kinking.
- Available with either ¾" NPT and ¾" BSPP nozzle outlet and standard 1" BSPP female inlet.
- BSPP nozzle outlet includes a fluoroelastomer flat seal to ensure compression tightness between the break away and the nozzle inlet.

SPECIFICATIONS

- Body: Stainless steel
- Separation force: Between 180 Lbs. and 340 Lbs. force (800 N and 1,500 N force)
- Temperature rating: -22 °F to 131 °F (-30 °C to 55 °C)
- Internal pressure: Factory tested to 76.8 PSI (5.3 bar)
- Electric conductivity: Factory tested to < 100k Ohm
- Nozzle flow rate compatibility: Up to 21 gpm (80 lpm)
- Working pressures compatibility: 0.5 bar up to 3.5 bar

ORDERING INFORMATION Model Description OMNIDEF1X34N %" NPT nozzle outlet, 1" BSPP female inlet DEF swivel break away OMNIDEF1X34P %" BSPP nozzle outlet, 1" BSPP female inlet DEF swivel break away OMNIDEF1PXM34 M34 (metric) nozzle outlet, 1" BSPP female inlet DEF swivel break away

Model 9095AA 3" Overfill Prevention Valve

NEW PRODUCT ANNOUNCEMENT

Application

The 9095AA series overfill prevention valve is designed to prevent the overfilling of liquid storage tanks by providing a positive shut-off during a pressurized fill.

Features and Details

- Installs on tank top by threading onto a 6" male NPT riser
- Direct fill adaptor has 3" male quick disconnect
- Remote adaptor has 3" female NPT inlet threads for piping to remote fill point
- · Full flow until shut-off point
- · 1.23" of float height adjustment
- · Integral pressure relief
- · Integral anti-siphon function
- Optional test mechanism
- Drop tube adaptor accepts 3" drop fill tubes (Morrison 419)

Materials of Construction

- · Direct fill adaptor... passivated aluminum
- Remote adaptor... ductile iron, powder coated
- Body... passivated aluminum
- Shaft, linkage, and hardware... stainless steel
- · Lower pipe... e-coated steel
- · Drop tube adaptor... passivated aluminum

Operational Criteria

- Minimum 5 PSI flow requirements
- Maximum operating pressure is 100 PSI
- Maximum viscosity of 300 centistokes
- A tight fill connection is required for the valve to operate
- The estimated flow rate is 560 GPM at 10 PSI pressure drop (See flow curve)

Code Compliance

ULC-S661-10 listed, NFPA 30, 30A, UFC, IFC, PEI/ RP200, PEI/RP 600, and Florida DEP EQ-851. California EVR models available



For use on clean liquids only.


Item numbers and flow curve on next page.





EVR EVR

Item Number	Size	Description	Weight (lbs)	List Price
9095AA0300 AV	3"	AST overfill prevention valve, aluminum body, with 3" male quick disconnect x 6" female threads	21	\$1,277.92
9095AA3300AVEVR	3"	AST overfill prevention valve, aluminum body with 3" female threaded x 6" Female threaded connections; CARB EVR approved	30	\$1,277.92
9095AA9300AVEVR	3"	AST overfill prevention valve, aluminum body, less top connection; CARB EVR approved	14.4	\$1,174.65
9095ATM0100 AM	2" & 3"	Mechanical test mechanism kit	1	\$114.31







A0060 Shear Valve

 Beefier Castings for Rugged Reliability ATEX & UL Approved*

Mounting Bolts Included






Stainless Steel Versions for E85, DEF, Ultra Low Sulfur Diesel & Biodiesel Blends up to B100


EMCO WHEATON RETAIL CORPORATION

2300 Industrial Park Drive • Wilson, North Carolina 27893 252-243-0150 • 252-243-4603 (fax) • www.emcoretail.com



A0060 **Emergency Shear Valve**





Materials

Body: Cast Iron or Stainless Steel

Spring: Stainless Steel Viton® Seal:

Viton® is a registered trademark of The Chemours Company

<u>Approvals</u>

ATEX FTZÚ14ATEX0204





Guide Specification: Emergency shut off valve for installation under gasoline dispensing units. Incorporates a replaceable shear section and a heat sensitive fusible link assembly. Valve can be manually operated to facilitate dispenser maintenance and incorporates a 3/8" test port. Closing poppet assembly is positioned out of the fuel flow path to minimize pressure drop. The A0060 utilizes a standard three boss mounting arrangement. Available in single poppet and double poppet configurations. Cast iron versions are powdered coated.

Model No. Cast Iron	Model No. Stainless Steel	Description	Inlet	Outlet	Cast Iron Lbs.	SST Lbs.	Α	В
A0060-002	A0060-002S	I ¹ /2" Single Poppet	Female	Male	5.7	6.4	6.9"	2.2"
A0060-003	A0000-0033	1 1/2 Single Poppet	remaie	remaie	5.6	6.3	0./	1./
A0060-015	A0060-015S	I 1/2" Single Poppet	Female BSPT	Male BSPT	5.7	6.4	7.9"	3.2"
A0060-016	A0060-016S	I 1/2" Single Poppet	Female BSPT	Female BSPT	5.6	6.3	6.9"	2.2"
A0060-022	A0060-022S	I ¹ /2" Double Poppet	Female	Male	5.8	6.7	7.9"	3.2"
A0060-023	A0060-023S	I 1/2" Double Poppet	Female	Female	5.7	6.4	6.9"	2.2"
A0060-025	A0060-025S	I ¹ /2" Double Poppet	Female BSPT	Male BSPT	5.8	6.7	7.9"	3.2"
A0060-026	A0060-026S	I 1/2" Double Poppet	Female BSPT	Female BSPT	5.7	6.4	6.9"	2.2"

Replacement Parts

•							
Part No.	For	Part No.	For	I	l	Cast Iron	SST
Cast Iron	Use On	Stainless Steel	Use on	Description	Outlet	Lbs.	Lbs.
492938	A0060-002	492938S	A0060-002S	/ ₂ " Replacement Top; Poppet	Male	2.2	2.5
492939	A0060-003	492939S	A0060-003S	/2" Replacement Top; Poppet	Female	2.3	2.6
493885	A0060-016	493885S	A0060-016S	I ¹ /2" Replacement Top; I Poppet	Female BSPT	1.4	1.6
493886	A0060-015	493886S	A0060-015S	I ¹ /2" Replacement Top; I Poppet	Male BSPT	1.6	1.8
493887	A0060-022	493887S	A0060-022S		Male	2.7	3.0
493888	A0060-023	493888S	A0060-023S		Female	2.7	3.0
493889	A0060-025	493889S	A0060-025S		Male BSPT	1.6	1.8
493890	A0060-026	493890S	A0060-026S		Female BSPT	1.6	1.8
492963K				Fusible Link Kit		0.2	
564036				Control Arm			
A0065-001				A0060 Stabilizer Bar Mounted Kit		3.8	



Emco Wheaton Retail Corporation

2300 Industrial Park Drive • Wilson, North Carolina 27893 252-243-0150 • 252-243-4603 (fax) • www.emcoretail.com

© 2020 Emco Wheaton Retail Corporation V-1000



Model 76DI & 78DI Expansion Relief Valves

SPECIFICATION SHEET

Application

Expansion Relief Valves are used on AST piping for relief of excess pressure caused by thermal expansion of liquid. The Valve allows product to return back to the storage tank.

076DI...Specify 25 or 50 PSI. Primarily for use with line leak detection systems. Use Fig. 76DI anytime you need to maintain precise pressures in the piping system.

078DI...Specify 25, 40 or 100 PSI. Pressure settings are approximate.

Materials of Construction

076DI

- · Body... Ductile iron
- · Cap... Stainless steel
- · Relief fitting... Stainless steel with FKM

078DI


- · Body... Ductile iron
- Cap... Stainless steel
- Spring... Stainless steel
- Ball... Stainless steel



Item Number	Α	В	С	D	E	F	G	Weight	
076DI-0100 AV	1/2"	25	DI	SS	SS/P	NA	NA	0.75	
076DI-0200 AV	1/2"	50	DI	SS	SS/P	NA	NA	0.75	
078DI-0100 AV	1/2"	25	DI	SS	NA	SS	SS	0.75	
078DI-0200 AV	1/2"	40	DI	SS	NA	SS	SS	0.75	
078DI-0300 AV	1/2	100	וט	55	NA	55	55	0.75	7

SPECIFICATION OPTIONS:

- A—Size (inches)
- **B**—PSI setting
- **C—**Body material: DI (Ductile Iron)
- D—Cap material: SS (Stainless Steel)
- E—Expansion relief Valve Material: SS/TF (Stainless Steel/PTFE), NA (Not Applicable)
- F—Spring material: SS (Stainless Steel), NA (Not Applicable)
- G—Check ball material: SS (Stainless Steel), NA (Not Applicable)
- Weight—Shipping weight (lbs)



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028

www.morbros.com

Model 710 Solenoid Valve (Normally Closed)

Application

Normally closed solenoid valves are used to help prevent the accidental siphoning of a product from a tank in the event of a leak downstream below the liquid level. They are generally installed on the dispensing side of a fuel system pipeline. The valve opens upon the receipt of an electronic signal such as when a dispenser or pump is switched to the 'on' position.

Features and Details

- · Normally closed, hung piston design
- Operates at 120 volts AC (24, 208, 220, 240, & 480 volts AC, and 12, 24, and 48 volts DC also available)
- Minimum operating temperature is -40°F
- Includes a continuous duty Class H standard coil. Other options are available
- Install in a horizontal pipeline in the upright vertical position
- · Zero pressure differential
- Integral thermal relief allows the valve to relieve expansion pressure in the opposite direction of flow
- Enclosure is watertight and rated for hazardous locations—NEMA 3, 4X, 7 and 9; groups C and D
- · Several optional coil voltages available
- Recommended for use with liquids having a maximum viscosity of 60 centistokes
- A strainer with a 100 mesh screen is recommended at the valve inlet
- 710 has a cast bronze body
- 710MO has manual override feature. Available in sizes ranging from ³/₄" to 2" for operation during a power outage
- 710SS has a stainless steel body

Materials of Construction

 Solenoid housed in an integral, watertight, explosion-proof shell


Certifications and Listings

CSA listed (File No. 108921, Model Z1314); Class I, Groups C and D; Class II, Groups E, F and G; Class III; T3C










Item numbers, dimensions, and water flow vs. pressure drop chart on next page.





SPECIFICATION SHEET

Item Number	Size (NPT)	Seal Material	Orifice Size (inches)	cv	Diffe	Pressure rential (P.S.I) Max	Fluid Temp. (Max) (Deg. F.)	Power Consumption (Watt)	Ship Weight (lbs)	A	Gen. Dim (inch B		D
710-0075 1V	3/4"	FKM	3/4"	7	0	105	302	30	11.0	4.0"	5.90"	1.5"	4.38"
710-0100 1V	1"	FKM	1"	12	0	105	302	30	13.0	4.8"	6.25"	1.75"	4.38"
710-0150 1V	1½"	FKM	11/4"	17	0	105	302	30	16.0	5.40"	6.90"	2.0"	4.38"
710-0200 1V	2"	FKM	1½"	27	0	105	302	30	21.0	5.90"	7.0"	2.25"	4.38"
710-0300 1V	3"	FKM	3"	94	0	45	302	48	44.0	8.80"	9.50"	4.50"	4.38"
710MO-0075 1V	3/4"	FKM	3/4"	7	0	105	302	30	12.0	4.0"	5.90"	1.50"	4.38"
710MO-0100 1V	1"	FKM	1"	12	0	105	302	30	14.0	4.80"	6.25"	1.75"	4.38"
710MO-0150 1V	1½"	FKM	11/4"	17	0	105	302	30	17.0	5.40"	6.90"	2.00"	4.38"
710MO-0200 1V	2"	FKM	1½"	27	0	105	302	30	22.0	5.90"	7.0"	2.25"	4.38"
710SS-2075 1V	3/4"	PTFE	3/,"	7	0	105	356	30	13.0	4"	5.90"	1.50"	4.38"
710SS-2100 1V	1"	PTFE	1"	12	0	105	356	30	15.0	4.80"	6.25"	1.75"	4.38"
710SS-2150 1V	1½"	PTFE	11/4"	17	0	105	356	30	16.0	5.40"	6.90"	2.0"	4.38"
710SS-2200 1V	2"	PTFE	1½"	26	0	105	356	30	21.0	5.90"	7.0"	2.25"	4.38"
710SS-3300 1V	3"	PTFE	3"	93.60	0	45	356	48	44.0	8.80"	9.50"	4.50"	4.38"
710SS-0300 1V	3"	PTFE	3"	93.60	0	45	302	48	44.0	8.80"	9.50"	4.50"	4.38"





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com



SPECIFICATION SHEET

Application

Pressure vacuum vents are installed on the top of underground and low volume aboveground storage tank vent pipes. Vent allows tank to "breathe" during filling and discharging operations. Pressure and vacuum poppets seal vapors in tank when pressure is equalized. Settings are approximate.

The 749T provides the same functions as the 749 and is designed for use on underground and low volume aboveground tanks storing Diesel Exhaust Fluid (DEF) and other products requiring PTFE and stainless construction.

Features and Details

- Screen protects the tank from debris and insects
- Integrated internal drain port channels water away from the tank
- Vent vapors up and outward per NFPA 30
- · Conserves fuel
- Certified SCFH ratings

Materials of Construction

- Body and hood... anodized aluminum (749T—is PTFE coated aluminum)
- Pressure poppet... anodized aluminum (749T—is HDPE)
- Vacuum poppet... brass vacuum (749T—is stainless steel)
- Body seal... Buna-N (749T—is FKM)
- Screen... 40 mesh stainless steel
- · Springs... stainless steel
- Set screws... Zinc-plated steel (749T—is Nylon)
 *HDPE = High density polyethelene

Certifications and Listings

CARB 95-14 (749CRB0500 model); CARB 95-15 (749CRB0600 model); CARB 96-19 (749CRBS0600 model); 749CRB Pressure Vacuum Vents (models 749CRB0600 AV, 749CRB1600 AV, 749CRBS0600 AV and 749CRBS1600 AV), meet the requirements of EPA 40 CFR part 63 for Gasoline Dispensing Facilities



WARNING

749T

Fig. 749 P/V vent must only be used in conjunction with motor fueling and/or low capacity flow. Fluid handling in lines larger than that used for retail service stations can cause tank to rupture or implode.

WARNING: DO NOT FILL OR UNLOAD FUEL FROM A STORAGE TANK UNLESS IT IS CERTAIN THAT THE TANK VENTS WILL OPERATE PROPERLY. Morrison tank vents are designed only for use on shop fabricated atmospheric tanks which have been built and tested in accordance with UL 142, NFPA 30 & 30A, and API 650 and in accordance with all applicable local, state, and federal laws. In normal operation, dust and debris can accumulate in vent openings and block air passages. Certain atmospheric conditions such as a sudden drop in temperature, below freezing temperatures, and freezing rain can cause moisture to enter the vent and freeze which can restrict internal movement of vent mechanisms and block air passages. All storage tank vent air passages must be completely free of restriction and all vent mechanisms must have free movement in order to insure proper operation. Any restriction of airflow can cause excessive pressure or vacuum to build up in the storage tank, which can result in structural damage to the tank, fuel spillage, property damage, fire, injury, and death. Monthly inspection, and immediate inspection during freezing conditions, by someone familiar with the proper operation of storage tank vents, is required to insure venting devices are functioning properly before filling or unloading a tank.





Item Number	Α	В	С	D	E	SCFH	Height	Weight
7490100 AV	2N	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
7490200 AV	2N	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
7491100 AV	3N	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	5.91	1.55
7491200 AV	3N	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	5.91	1.55
749S0100 AV	2S	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
749S0200 AV	2S	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
749S1100 AV	3S	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	6.28	1.65
749S1200 AV	3S	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	6.28	1.65
749CRB0500 AV	2N	8.0 oz	5.0 oz	V	Υ	6200 @ 20oz./in.sq.	4.33	1.45
749CRB0600 AV	2N	3" W.C.	8" W.C.	V	Υ	3800 @ 8.2" H2O	4.33	1.95
749CRB1500 AV	3N	8.0 oz	5.0 oz	V	N	6200 @ 20oz./in.sq.	5.91	1.65
749CRB1600 AV	3N	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	5.91	1.65
749CRBS600 AV	2S	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	4.33	1.45
749CRBS1600 AV	3S	3" W.C.	8" W.C.	V	N	3800 @ 8.2" H2O	6.28	1.95
749BSP0100 AV	2B	8.0 oz	0.50 oz	М	N	6200 @ 20oz./in.sq.	4.33	1.0
749BSP0200 AV	2B	12.0 oz	0.50 oz	М	N	7500 @ 25oz./in.sq.	4.33	1.0
749T0200 AV	2S	8.0 oz	0.50 oz	V	N	7500 @ 25oz./in.sq.	4.33	1.0

SPECIFICATION OPTIONS:

A— Body connection: 2" NPSM (2N), 2" Slip-on style (2S), 2" BSP (2B), 3" NPSM (3N), or 3" Slip-on style (3S)

B—Pressure setting: oz = oz/sq inch, wc = water column

C—Vacuum setting: oz = oz/sq inch, wc = water column

D—Pressure seal: metal-to-metal seat (M) or metal/FKM o-ring seat (V)

E—C.A.R.B. approval: yes or no (Y/N) **Height**—Dimension from base to top of vent

Weight—Shipping weight (lbs)

SPECIFICATION SHEET

Application

Atmospheric updraft vents are installed on the top of storage tank vent pipes on underground and aboveground fuel storage tanks.

Features and Details

- Directs vapors outward and upward in accordance with NFPA 30
- Protects the vent line from debris and insects
- · Water-resistant rain cap sheds water away from the vent line
- Slip-on design with set screws for easy installation
- Internal drain channels water penetration out through weep hole
- 354T is compatible with DEF

Materials of Construction

354

- Body and cap... aluminum die cast
- · Screen... 40 mesh stainless steel

354T

- Body and cap... PTFE coated black aluminum
- · Screen... 40 mesh stainless steel

Certifications and Listings

CARB 89-12 (1½" and 2" 354 models)

Item Number	Size (slip-on)	Weight (lbs)	Venting Capacity (SCFH) (@ 2.5 PSI)
3540100 AV	1½"	0.75	27,650
3540200 AV	2"	0.75	27,650
3540300 AV	3"	1.50	59,000
3540400 AV	4"	2.25	116,900
0547 0000 414	0,4	0.75	07.050
354T0200 AV	2"	0.75	27,650
354T0300 AV	3"	1.50	59,000





NOTE

Open vents will allow unrestricted evaporation of product.

WARNING: DO NOT FILL OR UNLOAD FUEL FROM A STORAGE TANK UNLESS IT IS CERTAIN THAT THE TANK VENTS WILL OPERATE PROPERLY. Morrison tank vents are designed only for use on shop fabricated atmospheric tanks which have been built and tested in accordance with UL 142, NFPA 30 & 30A, and API 650 and in accordance with all applicable local, state and federal laws. In normal operation, dust and debris can accumulate in vent openings and block air passages. Certain atmospheric conditions such as a sudden drop in temperature, below freezing temperatures, and freezing rain can cause moisture to enter the vent and freeze which can restrict internal movement of vent mechanisms and block air passages. All storage tank vent air passages must be completely free of restriction and all vent mechanisms must have free movement in order to insure proper operation. Any restriction of airflow can cause excessive pressure or vacuum to build up in the storage tank, which can result in structural damage to the tank, fuel spillage, property damage, fire, injury, and death. Monthly inspection, and immediate inspection during freezing conditions, by someone familiar with the proper operation of storage tank vents, is required to insure venting devices are functioning properly before filling or unloading a tank. Normal vents such as pressure vacuum and updraft vents for aboveground storage tanks should be sized according to NFPA 30 (2008) 21.4.3

MORRISON BROS. CO.

570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

1519 Mechanical Tank Top Gauge with Relay Output

SPECIFICATION SHEET

Application

Designed for installation on top of horizontal and vertical tanks up to 25' in height, the 1519 mechanical tank gauge provides a readout in feet and inches and includes a single liquid level set point to activate an external alarm box.

Features and Details

- Viewable up to 25' in tank height
- · Readout in feet and inches
- Easy to read from wide viewing angle
- · Easy to install and calibrate
- Installs through 2" schedule 40 pipe or 2" tank bung (drop tube float models require a 4" tank opening)
- Vapor tight to allow for standard tank pressure testing and sealing up to 5 PSI
- Vapor is contained from viewing area to prevent lens fogging
- 1519M...metric versions available to mount on top of horizontal and vertical tanks up to 7 meters (23') in height, providing readouts in centimeters

Gauge with Relay Output

- Desired alarm level is set within gauge head
- Alarm level setting can be verified
- The level alarm relay output wiring from the gauge has to be connected to an external alarm box (sold separately). Options include the 918 series and 918AC series alarm boxes.

Battery Power Module

- Can be installed in any convenient location
- One 3.6 volt lithium AA replaceable battery
- Anticipated battery life is 4 years
- Low battery light indicator

Alpha Wire 77112 (required cable for connecting gauge to Battery Power Module)*

- 5 Conductors
- 22 AWG (7/30 Stranded) tinned copper
- · Foil shield with drain wire
- Temperature range: -50 to 150C

*Wire needs to be purchased to connect a 1519 gauge to the Battery Power Module.

Separate wire is required from the gauge to external alarm. See external alarm specifications for wire requirements.









1519 Mechanical Tank Top Gauge with Relay Output (continued)

Materials of Construction

- Body... Cast aluminum
- · Gears and gear cogs... Acetal
- Hardware (including captive screws on front cover)... Stainless steel
- Float... Stainless steel
- · Cable... Stainless steel
- Spring... 301 stainless steel
- Shaft bushing... Stainless steel
- O-ring... FKM
- Lens cover... Acrylic
- · Power module enclosure... Polyester fiberglass


Code Compliance

UL/cUL 913

Item Number	Description	Float	Length	
15192500 AG	Mechanical tank top gauge with alarm relay, angled face	Standard	0-25'	
15192550 AG	192550 AG Mechanical tank top gauge with alarm relay, vertical face			
15192510 AG	192515 AG Mechanical tank top gauge with alarm relay output, vertical face 19M-7000 AG Metric mechanical tank top gauge with alarm relay, angled face 19M-7050 AG Metric mechanical tank top gauge with alarm relay, vertical face 19M-7010 AG Metric mechanical tank top gauge with alarm relay, angled face		0-25'	
15192515 AG			0-25'	
1519M-7000 AG			0-700 CM	
1519M-7050 AG			0-700 CM	
1519M-7010 AG			0-700 CM	
1519M-7015 AG			0-700 CM	

Alpha Wire 77112 (required cable)

Item Number	Description	Length		
15190015 CC	Five-conductor shielded cable	15'		
15190025 CC	Five-conductor shielded cable	25'		
15190050 CC	Five-conductor shielded cable	50' (spool)		
15190100 CC	Five-conductor shielded cable	100' (spool)		
15190200 CC	Five-conductor shielded cable	200' (spool)		





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

The Morrison 715 Series remote fill box is a simple 10-gallon capacity cabinet that provides containment of small spills during tank filling operations. Each unit is supplied with tank mount brackets for easy installation on storage tanks.

Features

- 10-gallon (37.85 liter) capacity
- 2" or 3" male NPT threaded or 150# raised face flange top connection
- Vented and weatherproof
- · Hinged door is lockable with a padlock
- Bottom sloped (right to left) toward drain and pump mounting location; drains on left side
- Vapor recovery mounting bracket integrated into the cabinet exterior
- · Vapor recovery adaptor, cap, and u-bolt kits are available
- Available with hand pump assembly, ball valve, quick disconnect check valve coupler/adaptor, dry disconnect adaptor, and dust cap/ plug in 2" or 3" configuration
- All connection assemblies are factory installed and tested prior to shipping
- DEF, Aviation, and E-85 models are available
- Post mount kits and four-leg stands are available in powder coated steel
- · Four-leg stands are also available in stainless steel

Construction Details

- Box and door are 14-gauge steel, powder coated white, or 304 stainless steel
- Ball valve is Morrison 691 series brass or 691BSS series stainless steel
- Quick disconnect coupler and plug are aluminum, anodized aluminum, or stainless steel
- Quick disconnect adaptor and cap are anodized aluminum
- · Dry disconnect adaptor and cap are aluminum, anodized aluminum, or stainless steel

Vapor recovery kit

- Vapor recovery adaptor is aluminum with FKM
- · Vapor recovery cap is aluminum, powder coated orange
- Hand pump is steel construction, PTFE seals with FKM o-rings, or stainless steel with PTFE and FKM

Box dimensions

Width = 24.38"

Height = 28.88" (34.8" including flange)

Depth = 19.19''

Approvals

CAN-ULC-S663-11; Florida DEP EQ-787







SPECIFICATION SHEET


Item Number	Size	Description	Weight		
715T00-0000-0	3″—10 gal.	Top connection w/ no outlets	101 lbs		
715-TT3-0000-0	3"—10 gal.	Top connection w/ no internal components	135 lbs		
715TT3-000B-0	3"—10 gal.	Top connection w/ hand pump			
715TT3-2QBB-0	3"—10 gal.	Top connection w/2" AL female QD coupler, BR ball valve, hand pump			
715-TT3-2MBB-0	3"—10 gal.	Top connection w/2" AL remaie QD adaptor, BR ball valve, hand pump	141 lbs		
715TT3-3QBB-0	3"—10 gal.		144 lbs		
715TT3-3QBB-0	3'—10 gal.	Top connection w/3" AL female QD coupler, BR ball valve, hand pump			
		Top connection w/3" AL male QD adaptor, BR ball valve, hand pump			
715TT3-2DBB-0	3"—10 gal.	op connection w/2" AL dry disc adaptor, BR ball valve, hand pump			
715TT3-3DBB-0	3"—10 gal.	op connection w/3" AL dry disc adaptor, BR ball valve, hand pump			
715TT3-2MB0-0	3"—10 gal.	Top connection w/2" AL male QD adaptor, BR ball valve			
715TT3-3MB0-0	3"—10 gal.	Fop connection w/3" AL male QD adaptor, BR ball valve			
715TT3-2QB0-0	3"—10 gal.	Top connection w/2" AL female QD coupler, BR ball valve			
715TT3-2DS0-0	3"—10 gal.	Top connection w/2" AL dry disc adaptor, SS ball valve			
715TT3-2DSE-0	3″—10 gal.	Top connection w/2" AL dry disc adaptor, SS ball valve, E85 hand pump			
715S-TT3-0000-0	3″—10 gal.	SS top connection w/ no internal components	135 lbs		
715S-TT3-2QBB-0	3″—10 gal.	SS top connection w/2" AL female QD coupler, BR ball valve, hand pump	132 lbs		
715S-TT3-2MBB-0	3″—10 gal.	SS top connection w/2" AL male QD adaptor, BR ball valve, hand pump	132 lbs		
715S-TT3-3QBB-0	3″—10 gal.	SS top connection w/3" AL female QD coupler, BR ball valve, hand pump	144 lbs		
715S-TT3-3MBB-0	3″—10 gal.	SS top connection w/3" AL male QD adaptor, BR ball valve, hand pump			
715S-TT3-2DBB-0	3″—10 gal.	SS top connection w/2" AL dry disc adaptor, BR ball valve, hand pump			
715S-TT3-3DBB-0	3″—10 gal.	SS top connection w/3" AL dry disc adaptor, BR ball valve, hand pump			
715S-TT3-2DS0-0	3″—10 gal.	SS top connection w/2" AL dry disc adaptor, SS ball valve			
715S-TT3-3DS0-0	3″—10 gal.	SS top connection w/3" AL dry disc adaptor, SS ball valve			
715S-TT3-2DSE-0	3″—10 gal.	SS top connection w/2" AL dry disc adaptor, SS ball valve, E85 hand pump			
715S-TT3-2MBE-0	3″—10 gal.	SS top connection w/2" AL male QD adaptor, BR ball valve, E85 hand pump			
715S-TT3-3DSE-0	3″—10 gal.	SS top connection w/3" AL dry disc adaptor, SS ball valve, E85 hand pump			
715S-TT3-2ES0-0	3″—10 gal.	SS top connection w/2" SS dry disc adaptor, SS ball valve			
715S-TT3-2ESS-0	3″—10 gal.	SS top connection w/2" SS dry disc adaptor, SS ball valve, SS hand pump			
715S-TT3-2SS0-0	3″—10 gal.	SS top connection w/2" SS female QD coupler, SS ball valve			
715S-TT3-2SSS-0	3″—10 gal.	SS top connection w/2" SS female QD coupler, SS ball valve, SS hand pump			
715S-TT3-3SS0-0	3″—10 gal.	SS top connection w/3" SS female QD coupler, SS ball valve			
715S-TT3-3SSE-0	3"—10 gal.	SS top connection w/3" SS female QD coupler, SS ball valve, E85 hand pump			
715TF4-0000-0	2"—10 gal.	Flanged top connection w/ no outlets			
715S-TF4-0000-0	2"—10 gal.	SS flanged top connection w/ no outlets			
		Flanged ten connection w/ no outlets			
715TF5-0000-0 715S-TF5-0000-0	3"—10 gal.	Flanged top connection w/ no outlets			
/ 135-175-0000-0	3"—10 gal.	SS flanged top connection w/ no outlets			
715VR30 AK		3" Vapor recovery kit			
715VR40 AK		4" Vapor recovery kit			
715P060 AK		Post mount kit - 3" x 60" post with clamps and base			
715S400 AS		Four-leg stand for 715 fill box, powder coated steel			
715SS400 AS		Four-leg stand for 715 fill box, stainless steel			
7150373 AK		Mounting plate assembly kit			


^{*}Please consult Price List for additional options.



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com








715 Part Numbering System

How to "Build-a-Box"

To order, simply select desired option from each category and insert the corresponding letter or number in the appropriate space below.



S

M

dust cap

Additional Options:

- 60" Post mount kit: 715---P060 AK
- Mounting Plate: 715---0373 2PPW (not compatible with in-wall models)
- Stand: 715---S400 AS (4-leg stand, powder coated steel)
- Stand: 715S--S400 AS (4-leg stand, stainless steel)
- Vapor recovery kits: 715---VR30 AK (3") and 715---VR40 AK (4")



For a complete listing of 715 item numbers, please refer to the Morrison Price List.

90° quick disconnect stainless steel coupler with check

stainless steel check valve, FKM seals, and aluminum

90° quick disconnect aluminum male adaptor with

valve, FKM seals, and aluminum dust plug

570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028

www.morbros.com

MORRISON BROS. CO.



Model 73590CA Check Valve Adaptor

Application

The 73590CA cam and groove adaptor with check valve is used in specialized applications where it is necessary and/or convenient to be able to connect and disconnect tank filling components quickly and cleanly.

Features and Details

- Male quick connect adaptor mates with traditional quick disconnect fill couplers
- Integrated check valve and fill adaptor reduces product loss at disconnect
- Space saving 90° design saving design fits into small spaces such as Morrison model 715 remote fill boxes

Materials of Construction

- Hard coated aluminum body
- Stainless steel plunger
- Viton® disc

Item Number	Size	Description	Weight (lbs)
73590CA0200 AV	2"	90° check valve; male adaptor; female threads	2.0
73590CA0300 AV	3"	90° check valve; male adaptor; female threads	5.0

Optional dust caps:



,	Item Number	Size	Description
	735DCA2000ACEVR	2"	Anodized aluminum dust cap; EVR approved
	735DCA3000ACEVR	3"	Anodized aluminum dust cap: EVR approved





570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028 www.morbros.com

Model 927/928/735DC Series

Application

The Morrison 927 dry disconnect adaptor is installed at the fill point in the fill line of a fuel storage tank system. The internal spring loaded poppet assembly remains closed providing a liquid-tight seal when not connected to a dry disconnect coupler.

The Morrison 928 dry disconnect coupler is installed on the end of delivery vehicle hose. When coupled, the 927 and 928 provide a liquid-tight connection enabling a dry connection and a dry disconnection.

The 735DC dust cap serves as a protective cover for the 927 adaptor when not in use.

927 models mate with PT Maxi-Dry® and OPW Kamvalok® couplers.

Code Compliance

EVR

EVR

735DC models meet California EVR VR-402 and US Military CID A-A-59326D; some 927 and 928 models meet CARB Phase 1 EVR VR-402

Item Number	Size	Description	A	В	С	D	E	Cap Size	Weight (lbs)
9270150 1A	1½"	Dry disconnect adaptor	1N	2"	Α	F	N	2"	1.63
9270200AAEVR	2"	Dry disconnect adaptor	2N	21/2"	А	F	Υ	2½"	1.98
9270300AAEVR	3"	Dry disconnect adaptor	3N	4"	А	F	Υ	4"	3.50
9270400AAEVR	4"	Dry disconnect adaptor	4N	4"	Α	F	Υ	4"	3.50
9095A5201AAEVR	4" x 2"	Dry disconnect adaptor	4N	2½"	Α	F	Υ	2½"	2.50
927B0200 AA	2"	Dry disconnect adaptor	2N	21/2"	В	F	N	2½"	3.05
927S0150 1A	1½"	Dry disconnect adaptor	1N	2"	SS	F	N	2"	3.80
927S0200 1A	2"	Dry disconnect adaptor	2N	21/2"	SS	F	N	2½"	5.90
927S0300 1A	3"	Dry disconnect adaptor	3N	4"	SS	F	N	4"	18.25
9280150 1C	1½"	Dry disconnect coupler	1N	2"	А	F	N	N/A	4.40
9280150ACEVR	1½"	Dry disconnect coupler	1N	2"	Α	F	Υ	N/A	4.40
9280200 1C	2"	Dry disconnect coupler	2N	21/2"	Α	F	N	N/A	6.0
9280200ACEVR	2"	Dry disconnect coupler	2N	2½"	А	F	Υ	N/A	6.0
9280300 1C	3"	Dry disconnect coupler	3N	4"	Α	F	N	N/A	12.60
9280300ACEVR	3"	Dry disconnect coupler	3N	4"	Α	F	Υ	N/A	12.60
928S0150 1C	11/2"	Dry disconnect coupler	1N	2"	SS	F	N	N/A	
928S0200 1C	2"	Dry disconnect coupler	2N	2½"	SS	F	N	N/A	
928S0300 1C	3"	Dry disconnect coupler	3N	4"	SS	F	N	N/A	
735DC-2000ACEVR	2"	Dust cap, use w/ 1½" 927 adaptors	N/A	N/A	А	В	Υ	N/A	1.0
735DCA2000ACEVR	2"	Dust cap, use w/ 1½" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	1.0
735DC-2500ACEVR	21/2"	Dust cap, use w/ 2" 927 adaptors	N/A	N/A	Α	В	Υ	N/A	1.25
735DCA2500ACEVR	21/2"	Dust cap, use w/ 2" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	1.25
735DC-3000ACEVR	3"	Dust cap, use w/ 3" adaptors	N/A	N/A	Α	В	Υ	N/A	1.50
735DCA3000ACEVR	3"	Dust cap, use w/ 3" adaptors	N/A	N/A	AA	В	Υ	N/A	1.50
735DC-4000ACEVR	4"	Dust cap, use w/ 3" & 4" 927 adaptors	N/A	N/A	Α	В	Υ	N/A	2.50
735DCA4000ACEVR	4"	Dust cap, use w/ 3" & 4" 927 adaptors	N/A	N/A	AA	В	Υ	N/A	2.50

SPECIFICATION SHEET





SPECIFICATION OPTIONS:

A—Female threads: 1½" NPT (1N); 2" NPT (2N); 2" NPS (2S); 3" NPT (3N); 4" NPT (4N)

B—Coupler size

C—Body: Hard coated aluminum (A); Anodized aluminum (AA); Brass (B); Stainless steel (SS)

D—Seals: FKM (F); Buna-N (B) **E**—EVR: Yes (Y); No (N)

Cap size—In inches
Weight—Shipping weight



570 E. 7th Street, P.O. Box 238 | Dubuque, IA 52004-0238 t. 563.583.5701 | 800.553.4840 | f. 563.583.5028



Southland is a leader in precision-made steel, red brass and malleable iron pipe, nipples, fittings and related products. Manufactured in our North American facilities and threaded to industry specifications to provide a secure and trusted fit, Southland products are the trusted choice for plumbing, OEM, oil, gas and steam applications. Durable and highly resistant to rust and corrosion, every Southland pipe, nipple and fitting is 100% inspected and quality tested.



Piping will be 1-1/2" piping and 3" black piping.

Steel Pipe & Ready Cut Pipe

Our extensive line of welded black steel and galvanized steel pipe meets rigid industry standards and is backed by one of the most trusted names in the industry. Available in 1/4" to 4" diameters and offered in various lengths including 10-foot or 21 foot cut lengths, our steel pipes offer a choice of plain, threaded or coupled ends.

Product Highlights:

- · Available from 1/8" 4" Diameters
- · Available in Black & Galvanized
- · Available in Ready Cut Pipe Assortments
- . Pipes supplied in lengths from 10ft to 21ft
- Produced by Electric Resistance Welded (ERW) process

Specifications:

- Welded steel pipe schedule 40 (1/2) through 6") and 80 (1/2" to 2") complies with:
- -Galvan zed P pe ASTM A-53 standard
- -Black Pipe ASTM A-53 and API 5L standards
- -Threads ASME ANSI B1 20/1 standard

- ·Produced in a stretched-reduced mill to ensure full body normalized pipe
- · Hot dip galvanizing process according to ASTM standards
- · Galvanized Products meet Californ a Lead Plumbing Law
- Seamless steel pipe schedule 40, 80, 160 in diameters from 1/8" to 4"complies with:
- Black pipe ASTM A-106 grade B
- Threads ASME /ANS! B1:20:1 standard
- Welded Steel Ready Cut Pipe
- Schedule 40 and 80 in sizes from 1/2" to 4"
 - *Galvanized Steel ASTM A-53
 - *Black Steel ASTM A-53 / API 5L



Steel Nipples

We manufacture both black and gal vanized welded steel nipples in 11 diameters from 1 "to 4" and in 14 different length s ranging up to 12 ". Available individually or in pre-packaged assortments, we also offer a full selection of pre-cut welded steel pipes in the same diameters and lengths.

Product Highlights:

- · Ava lab le from 1 8 " -4" Diameters
- •Ava lab e in Lengths from C bsed 12 "
- Ava lab e in Black & Ga van zed Schedu e 40 and 80 Pipe Nipples
- Ava lab e in Black & Ga van zed Schedu e 4 Q 80, 160 & XXHvy Seamless Nipples
- NAFTA approved

Specifications:

- · Welded Steel Pipe Nipples Black and Ga van zed Schedules 40 and 80 in sizes from 1/8" through 6"
 - ASTM A-733 , ASM EANSI B1 20 1 and ASTM A-53
- •We also have available Merchant Couplings, Chrome Plated Nipples, Stainless Steel
- Nipples & Conduit Nipples
- Color coded product labels
- *Preferred industry pack quantities
- Galvanized Products meet California Lead Plumbing Law
- Seamless Steel Pipe Nipples
- Schedule 40 and 80 in sizes from 1/8" to 4"
- Black Steel ASTM A-733, ASME/ANSI B1.20.1 and A-106 grade B







Fittings will 1-1/2" and 3" black steel fittings as needed.

Malleable Iron Fittings


We offer one of the most extensive selections of black and galvanized malleable iron fittings in the industry. Available in 13 diameters from 1/8" to 6", every fitting is produced to exact specifications. All galvanized products are zinc-coated for water applications and meet all low-lead requirements. In addition, all of our iron fittings undergo our rigorous testing and quality inspection.

Product Highlights:

- . Stocked in most figures from 1/8" to 6"
- · Available in Black finish for oil and gas fluid applications
- · Available in Galvanized finish for water, air and steam installations
- Available for servicing 150 psi and 300 psi applications
- Hot dip galvanizing process according to ASTM A-153 standard
- · Galvanized Products meet California Lead Plumbing Law

Specifications:

- Threaded ends meeting with ANSI/ASME B1.20.1 standard
- Material meeting with ASTM A-197 standard
- Dimensions meet the following:
- Threaded Fittings with ASME B16.3 standard
- Unions with ASME B16.39 standard
- Bushing Reducer and Plugs with ASME B16.14 standard



Red Brass Fittings & Nipples

Our Red Brass Fittings and Nipples are carefully produced and threaded to industry specifications to provide a secure and trusted fit. While primarily developed for carrying water in commercial plumbing and OEM applications, they are also used in oil, gas and steam applications. Durable and highly resistant to rust and corrosion, every red brass fitting and nipple is 100% inspected and quality tested.

Product Highlights:

- · Made with Class 125lb Red Brass
- Nipples Available in Lengths from Close to 12*
- · Available in Schedule 40 diameters from 1/8" to 4"

Specifications:

- Red Brass Nipples meets ASTM B43-96 specifications
- · All threads meet ASME/ANSI B1.20.1 standards
- . Meets ASTM B-687 standards





FIREFLEX FLEXIBLE CONNECTORS

Since their introduction in 1995, FLEX-ING™ FIREFLEX Flexible Connectors have quickly become the industry standard and benchmark for quality as a means to easily connect one pipework system to other systems' components such as submersible pumps or shear valves. The benefit of their use is undeniable. They have quickly become an integral part of any installation. Installers love their ease of installation while station owners have come to depend on their durability and how easy they make regular maintenance. With tons of available options, Franklin Fueling Systems has the right connector to fit any application.



Highlights

- The corrugated fuel contact layers feature a 25% thicker metal construction and gain flexibility from having more corrugations per foot rather than thinner walls.
- Enclosing the corrugated fuel contact layer is a stainless steel braid that is manufactured from only high-grade stainless steel.
- Available in a multitude of end connections to ensure the right fit for any application - including tees, elbows, and FRP transitions
- The EZ FIT union style coupling system is specifically designed to make connections in confined spaces simple and tight.
- Each EZ FIT union style coupling comes complete with couplers and gaskets.


Specifications

- USA NFPA 30-A fire rated
- All metal construction means one flexible connector for both above and below ground applications
- An 18-8 alloy outer shell, 321 Stainless Steel inner core provides a long service life
- Thick, schedule 80 hex end fittings protect against deformation of the ends
- 100% pressure tested to assure quality
- UL 2039 approved for 50 psi working pressure
- EZ FIT clamp and gasket are included with each assembly

Approvals

 UL 2039 listed for above and below ground installation for use with gasoline, gas alcohol blends (up to E85), diesel, and biodiesel.





Ordering Information

Use these diagrams below along with the Ordering Guide at the bottom of the page to help you build your flexible connector model numbers.

Ordering Options Diagram

Use the options and descriptions in the Ordering Guide along with this diagram to assist in building your

model numbers.



End Fitting Options

Use the options and descriptions in the Ordering Guide along with the diagrams below to select your end fitting types (two total).



Ordering Guide

ABXCDXE

A = Product Type

FF = If either of the end connections are any type of swivel, this option must be selected.

FFUL = If both end connections are fixed (non-swivel), this option must be selected.

B = Hose Diameter

07 = 3/4"

10 = 1"

15 = 1½"

20 = 2"

30 = 3"

40 = 4"

C = Overall Length in Inches

Use two-digit format

D & E = End Fitting Options

EZ = EZ FIT flange only

EZM = EZ FIT male NPT (Each EZ FIT union style coupling comes complete with couplers and gaskets)

EZF = EZ FIT female NPT (Each EZ FIT union style coupling comes complete with couplers and gaskets)

EZFG = EZ FIT fiberglass glue pipe (Each EZ FIT union style coupling comes complete with couplers and gaskets)

M346 = Male swivel NPT

F346 = Female swivel NPT

HM = Hex male fixed NPT

HF = Hex female fixed NPT

BT = Hex male fixed BSPT

BTS = Male swivel BSPT

MS90 = 90° with male swivel NPT

Example: FF20X18M346XHM = FIREFLEX flexible connector with swivel end fitting(s), 2" hose diameter, 18" overall length, with one male swivel end fitting and one fixed hex male end fitting.

Flexible Connectors with Differing Hose and End Fitting Diameters

All end fittings are, by default, the same diameter as the hose. If you require a flexible connector where the end fitting diameter does not match the hose diameter, the size must be indicated numerically in front of the corresponding fitting as in the following example.

Example: FFUL15X18HMX2HM = FIREFLEX flexible connector with fixed end fittings, 1½" hose diameter, 18" overall length, with one 1½" hex male fixed end fitting, and one 2" hex male fixed end fitting.

Rules:

- 1) End fitting diameters can not be smaller than hose diameters.
- 2) Only one hose fitting per flexible connector can be of a different diameter than the hose diameter.
- 3) End fitting diameter must only be one size larger than hose (1" hose could use 1½" fitting, 1½" hose could use 2" fitting, etc.)



MASTER YOUR



MANAGEMENT

AUTOMATE YOUR FUELING PROCESS

FMU-2500 & 3505 SERIES

- Built to military specifications
- Modular design and backward capability
- Ease of maintenance
- World class support



"FUELMAS"





FMU-2500 & 3505 SERIES

CUSTOMIZE YOUR FUEL MANAGEMENT NEEDS

The FMU-2500Plus and FMU-3505Plus are the industry leaders in commercial fleet and retail fueling automation. The passive fueling automation of the 3505 Series compliments the interactive automation of the 2500 Series using our state of the art patented RFID 2.4 technology.

Note: All FMU-2500Plus units can be easily upgraded to include passive automated features found in the 3505 Series at the fuel island.

FEATURES & BENEFITS

- Handles up to 8 hoses
- Communicates with up to 8 satellite FMU, each handling 8 hoses, for a total of 72 hoses per master FMU
- Fueling process initiated by keypad; PROKEE®; smartcard; proximity card; or AIM module
- FMU can be equipped to read fleet, aviation, and standard credit cards. Contact us for a current list
 of available networks
- · Works with mechanical and electronic dispensers, both retail and commercial
- Windows based software and operates on a SQL platform
- · Transactional data can be exported to most fleet maintenance or accounting programs
- · Communicates with a Tank Monitor Unit/Tank Gauge interface from a variety of manufacturers
- Supports Automatic/Manual Operation
- 24/7 Live customer support call center
- Customer Training provided at no cost
- All product research and development completed within our on-site Engineering Department







CONTACT US TO LEARN MORE

800.888.9136 850.878.2558

www.MyFuelMaster.com Marketing@MyFuelMaster.com Syntech Systems, Inc. 100 Four Points Way, Tallahassee, FL 32305



Labeling Guidelines for:

NFPA 704 PLACARDS AND LABELS

The NFPA 704 Placard

The NFPA 704 Diamond ("NFPA Diamond" or "fire diamond") is a standard placard that identifies the level of chemical hazard at fixed locations, such as production facilities, warehouses, storage tanks, and storage sheds. It is required by the California Fire Code and meets requirements under the Hazard Communication Act ("Right to Know")

The NFPA 704 diamond (shown at right) is divided into four colored quadrants. Each quadrant provides information about the materials inside:

- Blue represents health hazard.
- **Red** represents flammability.
- Yellow represents reactivity.
- White provides information about special precautions.


Fire Hazard Health Reactivity Hazard Hazard Specia Hazard

Within each quadrant is a number from 0 to 4 indicating the degree of risk associated with the material. The higher the number, the higher the risk. For some materials, the white

quadrant contains symbols indicating special hazards. (See NFPA Indicator Key, page 2)

Proper Hazard indicators (numbers) can be found on the product MSDS.

If more than one chemical is present at a facility, the NFPA diamond indicates overall hazard at that location, *not* the hazard posed by a particular chemical. It shows the highest of each of the four hazards present. For example, it may be that one chemical poses the highest health hazard while another poses the highest fire hazard.



INSIDE BUILDING, CONTENTS

OUTSIDE PLACARD

Labels meeting NFPA 704 standards and the "Right to Know" can very in format but consistently are the same in content.



RTK Label



HMIS Tag



NFPA Label

To meet Hazcom "Right to Know" act, labels must include:

- Manufacture
- Chemical name
- Common name
- Hazards

NFPA INDICATOR KEY

HEALTH HAZARD	FLAMMABILITY	REACTIVITY	SPECIAL
4 - Materials which on very short exposure could cause death or major residual injury even through prompt medical treatment were given.	4 - Materials which will rapidly or completely vaporize at atmospheric pressure and normal ambient temperature, and which will burn. FLASH POINT < 73	4 - Materials which are readily capable of detonation or of explosive decomposition or reaction at normal temperatures and pressures.	Specific chemical hazards, special information and personal protective equipment will be noted in this section. Specific hazards and their symbols are as follows:
3 - Materials which on short exposure could cause serious temporary or residual injury even though prompt medical treatment were given.	3 - Liquids and solids that can be ignited under almost all ambient temperature conditions. FLASH POINT< 100	3 -Materials that can detonate or explode but require a strong initiating source, or must be heated under confinement before initiation, or react explosively with water.	OX- Oxidizer ACID - Acid ALK - Alkali COR- Corrosive -W- No Water Radioactive
2 -Materials which on intense exposure could cause possible residual injury unless prompt medical treatment is given.	2 -Materials that must be moderately heated or exposed to relatively high ambient temperatures before igniting. FLASH > 100 < 200	2 -Materials that are normally unstable and readily undergo violent chemical changes but do not detonate; also materials that may react violently with water.	HMIS A=Safety glasses B=Safety glasses, Gloves C=Glasses, gloves Protective apron D=Face shield, Gloves, apron E=Glasses, gloves
1 -Materials which on exposure would cause irritation but only minor residual injury even if no treatment is given.	1 -Materials that must be preheated before ignition can occur. FLASH POINT > 200	1 -Materials that are normally stable, but can become unstable at high temp. and pressures, or may react with water with some release of energy.	Dust respirator F=glasses, gloves Respirator, apron G=Glasses, gloves Vapor respirator H=Goggles, gloves Apron, respirator I =glasses, gloves APR
0 -Materials which on exposure under fire conditions would offer no hazard beyond that of ordinary combustibles.	0 -Materials that will not burn.	0 -Materials that are normally stable even under fire explosive conditions, and that are not reactive with water.	K=supplied air, Mask or hood Suit and boots Or symbols may be used

Emergency Stop Solutions for Fueling Sites

Emergency Stop Controls are required by the National Electrical Code at <u>ALL</u> fueling facilities. Power Integrity offers a full line of emergency stop operators to meet your site requirements.





IA-ESOCA Emergency Stop Operator with Cover & Alarm

Emergency Stop Operators

- Available in momentary, twist-to-reset, key-to-reset, and break glass configurations
- Clear tamperproof cover protects against accidental activation, damage, and vandalism
- Optional alarm protects against nuisance activation
- Standard operator includes (1) NO and (1) NC contact
- Custom labeling available

Cashier Control Stations

- Allow employees to activate emergency stop system without leaving the cashier area
- Standard configuration includes
 - Emergency stop pushbutton
 - Emergency stop system reset pushbutton
- Available with optional lighting bypass switch
- Custom configurations available including
 - Product status lights
 - o Timed lighting override
 - Individual dispenser shut-down




IA-ESORS
Cashier Control Station with
Protective Shroud




Power • Control • Protect



Typical Emergency Stop Installation





Attaching to Recessed Junction Box

Attaching to Surface Mount Junction Box

Emergency Stop	Operators - Outdoor Rated		
IA-ESOC	Emergency stop operator with lift-up clear cover		
IA-ESOCA	Emergency stop operator with lift-up clear cover and alarm		
IA-ESOC/T	Emergency stop operator, twist to release with lift-up clear cover		
IA-ESOCA/T	Emergency stop operator, twist to release with lift-up clear cover and alarm		
IA-ESOCK	Emergency stop operator, keyed reset with lift-up clear cover		
IA-ESOG	Emergency stop operator with "Break Glass", hammer, and (5) replacement discs		
Emergency Stop	Operator Accessories		
IA-ESPLATE	Emergency stop operator mounting plate with "emergency fuel shutoff" nameplate		
IA-BREAKTAB	-BREAKTAB Locking mechanism block with (5) one-time use breakaway seals		
Cashier Control	Stations - Indoor Rated		
	Cashier control with emergency stop button with shroud to prevent accidental		
IA-ESORS	pressing, and reset button		
	Cashier control with emergency stop button with shroud to prevent accidental		
IA-ESORLS	pressing, reset button, and light control bypass switch		
Emergency Stop Operator Lift-Up Covers			
IA-PBCOVSA	Small lift-up clear cover with alarm for e-stop operators, 5.5"W x 7.0"H (Yellow)		
IA-PBCOVS	Small lift-up clear cover for e-stop operators, 5.5"W x 7.0"H (Yellow)		
IA-PBCOVLAR	Large lift-up clear cover with alarm for e-stop operators 7.0"W x 9.0"H (Red)		

www.powerintegritycorp.com





Attachment I:

20% or Less Impervious Cover Declaration (if project is multifamily residential, a school, or a small business and 20% or less impervious cover is proposed for the site)

(NOT APPLICABLE)



Attachment J: BMPs for Upgradient Stormwater

Existing retention/irrigation Permanent BMP continues to address any upgradient stormwater. The proposed project does not increase the IC at the site.



Attachment K: BMPs for On-Site Stormwater

The proposed project will not increase impervious cover (IC) and the volume of potential on-site stormwater. The existing and approved retention/irrigation permanent BMP was designed to capture and will continue to mitigate potential onsite stormwater flows.

Runoff from the developed site and proposed fueling island will convey to the existing approved retention/irrigation permanent BMP that is designed to capture and detain the required water quality volume. For additional information, see the original approved calculations.



Attachment L: **BMPs** for Surface Streams (NOT APPLICABLE)

No surface streams flow across the property.



Attachment M: Construction Plans

PROJECT CONTACTS

OWNER: PEC

9115 CIRCLE DR. AUSTIN, TX 78736

ENGINEER:
SANDLIN SERVICES, LLC
4501 WHISPERING VALLEY DR. UNIT#27
AUSTIN, TEXAS 78727
806-679-7303

CONTRACTOR: EXCELL FUELING SYSTEMS, INC 549 S LOOP 4 BUDA, TEXAS 78610 (512)280-5230

DATE OF SUBMITTAL: 6/15/2022

APPROVALS:

SURVEY AND BENCHMARK

ALL ELEVATIONS SHOWN HEREON ARE BASED ON THE FOLLOWING BENCHMARKS AND INFORMATION.

CONTRACTOR TO PROVIDE FIELD SURVEY AND BENCHMARK

BEARINGS ARE BASED ON THE TEXAS STATE PLAN COORDINATE SYSTEM OF 1983, TEXAS CENTRAL ZONE (NAD 83)

LEGAL DESCRIPTION

LOT 1 BLOCK A OF PEDERNALES ELECTRIC COOPERATIVE CIRCLE DRIVE AUSTIN SUBDIVISION SEE PLAT SHEET

ZONING AND USE

JURISDICTION: ZONING: EXISTING LAND USE:

PROPOSED LAND USE:

EDWARDS AQUIFER

BARTON SPRINGS OVERLAY

ELECTRIC SERVICE PROVIDER UNCHANGED

WATERSHED

WATERSHED:

SLAUGHTER CREEK

THIS PROJECT LIES WITHIN THE EDWARDS AQUIFER CONTRIBUTING ZONE AS DEFINED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ)

FLOODPLAIN NOTE


THE 100-YEAR FLOODPLAIN IS NOT LOCATED WITHIN THE LIMITS OF CONSTRUCTION OF THIS PLAN. A PORTION OF THIS TRACT LIES WITHIN THE BOUNDARIES OF THE 100-YEAR FLOODPLAIN ACCORDING TO THE NATIONAL FLOOD INSURANCE FEMA MAP COMMUNITY PANEL #48453C0560J, DATED JANUARY 22, 2020 AND LOCATED WITHIN AN EXISTING DRAINAGE EASEMENT

REVISION RECORD


PEDERNALES ELECTRIC COOP CONTRIBUTING ZONE & ABOVE GROUND STORAGE TANK PLANS

ADDRESS: 9115 CIRCLE DR, AUSTIN, TX 78736

SHEET INDEX		
NUMBER	TITLE	
1	COVER PAGE	
2	CONSTRUCTION NOTES (1 OF 2)	
3	CONSTRUCTION NOTES (2 OF 2)	
4	FINAL PLAT (1 OF 3)	
5	FINAL PLAT (2 OF 3)	
6	FINAL PLAT (3 OF 3)	
7	EROSION CONTROL AND DRAINAGE PLAN	
8	AST TANK LAYOUT PLAN	
9	EROSION CONTROL DETAILS	



PROJECT LOCATION MAP N.T.S.



CONTRACTOR GENERAL NOTES

- 1. THE CONTRACTOR SHALL OBTAIN A "NOTICE OF PROPOSED INSTALLATION OF UTILITY LINE" PERMIT FROM THE COUNTY FOR ANY WORK PERFORMED IN THE EXISTING COUNTY RIGHT-OF-WAY (DRIVEWAY APRON, WATER MAIN TIE-IN, ETC.) THIS PERMIT APPLICATION WILL REQUIRE A LIABILITY AGREEMENT, A CONSTRUCTION COST ESTIMATE FOR WORK WITHIN THE RIGHT-OF-WAY INCLUDING PAVEMENT REPAIR (IF NEEDED), A PERFORMANCE BOND, CONSTRUCTION PLANS AND, IF NECESSARY, A TRAFFIC CONTROL PLAN. AN INSPECTION FEE, AND A PRE-CONSTRUCTION MEETING MAY ALSO BE REQUIRED, DEPENDING ON THE SCOPE OF WORK. THE PERMIT WILL BE REVIEWED AND APPROVED BY THE COUNTY ENGINEER, AND MUST ALSO BE APPROVED BY THE COUNTY COMMISSIONERS COURT IF ANY ROAD CLOSURE IS INVOLVED.
- 2. BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE, HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.
- 3. THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT THE AUSTIN AREA "ONE CALL" SYSTEM 1-800-245-4545, OR THE OWNER OF EACH INDIVIDUAL UTILITY, FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.
- 4. THE CONTRACTOR OR SURVEYOR WILL OBTAIN A DIGITAL COPY OF THE CAD FILES THAT REPRESENT THESE IMPROVEMENTS; SANDLIN SERVICES, LLC AND IT'S ASSOCIATES TAKE NO RESPONSIBILITY FOR THE LOCATION OF THESE IMPROVEMENTS IN ANY COORDINATE SYSTEM. DIGITAL FILES USED TO PRODUCE THESE PLANS WERE PARTIALLY CREATED BY PARTIES OTHER THAN SANDLIN SERVICES, LLC AND ARE NOT INTENDED FOR USE IN CONSTRUCTION STAKING. VERTICAL AND HORIZONTAL DATA SHALL BE INDEPENDENTLY VERIFIED BY CONTRACTOR'S R.P.L.S.
- 5. SANDLIN SERVICES, LLC HAS ENDEAVORED TO DESIGN THESE PLANS COMPLIANT WITH ADA/TDLR AND OTHER ACCESSIBILITY REQUIREMENTS. HOWEVER, THE CONTRACTOR SHALL NOT BE RELIEVED OF ANY RESPONSIBILITY FOR CONSTRUCTING THESE IMPROVEMENTS COMPLIANT WITH ALL APPLICABLE ACCESSIBILITY STANDARDS. IF THE CONTRACTOR NOTICES ANY DISCREPANCIES BETWEEN THESE PLANS AND ACCESSIBILITY LAWS/RULES, HE IS TO STOP WORK IN THE AREA OF CONFLICT AND NOTIFY THE ENGINEER IMMEDIATELY FOR A RESOLUTION AND/OR REVISION TO THESE PLANS. SANDLIN SERVICES, LLC SHALL NOT BE HELD RESPONSIBLE FOR CONSTRUCTING THIS SITE COMPLIANT WITH ACCESSIBILITY LAWS/RULES REGARDLESS OF WHAT IS SHOWN IN THESE PLANS.

COVER PAGE

SHEET 1 OF 9

P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN SERVICES, LLC

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727


TEXAS COMMISSION ON ENVIRONMENTAL QUALITY CONTRIBUTING ZONE PLAN GENERAL CONSTRUCTION NOTES

- 1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY GROUND DISTURBANCE OR CONSTRUCTION ACTIVITIES. THIS NOTICE MUST INCLUDE:
 - THE NAME OF THE APPROVED PROJECT;
 - THE ACTIVITY START DATE; AND
 - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- 2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT SHOULD BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED CONTRIBUTING ZONE PLAN (CZP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTOR(S) SHOULD KEEP COPIES OF THE APPROVED PLAN AND APPROVAL LETTER ONSITE.
- NO HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
- 4. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
- 5. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
- 6. SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
- 7. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
- 8. ALL EXCAVATED MATERIAL THAT WILL BE STORED ON-SITE MUST HAVE PROPER E&S CONTROLS.
- 9. IF PORTIONS OF THE SITE WILL HAVE A CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
- 10. THE FOLLOWING RECORDS SHOULD BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
 - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
- THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
 - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
- 11. THE HOLDER OF ANY APPROVED CZP MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
 - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY BEST MANAGEMENT PRACTICES (BMPS) OR STRUCTURE(S), INCLUDING BUT NOT LIMITED TO TEMPORARY OR PERMANENT PONDS, DAMS, BERMS, SILT FENCES, AND DIVERSIONARY STRUCTURES;
 - B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED;
 - C. ANY CHANGE THAT WOULD SIGNIFICANTLY IMPACT THE ABILITY TO PREVENT POLLUTION OF THE EDWARDS AQUIFER: OR
- D. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE APPROVED CONTRIBUTING ZONE PLAN.

AUSTIN REGIONAL OFFICE 12100 PARK 35 CIRCLE, BUILDING A AUSTIN, TEXAS 78753-1808 PHONE (512) 339-2929 FAX (512) 339-3795

SAN ANTONIO REGIONAL OFFICE 14250 JUDSON ROAD SAN ANTONIO, TEXAS 78233-4480 PHONE (210) 490-3096 FAX (210) 545-4329

REVISION RECORD



PRE-CONSTRUCTION NOTES:

- 1. PRIOR TO SCHEDULING THE PRE—CONSTRUCTION MEETING ENSURE THAT ALL REQUIRED NOTICES AND PERMITS ARE POSTED AND THE CERTIFIED INSPECTOR FOR YOUR SITE HAS UPLOADED A SWP3 INSPECTION REPORT TO YOUR ACCOUNT THAT CONFIRMS THAT THE FIRST PHASE OF TEMPORARY ESC HAVE BEEN INSTALLED PER PLANS AND SPECIFICATIONS.
- 2. FAILURE TO FOLLOW THE PRE-CONSTRUCTION MEETING REQUIREMENTS MAY RESULT IN WORK STOPPAGE AND ADDITIONAL PERMIT FEES.
- 3. PROVIDE 48 HR. MINIMUM NOTICE TO SCHEDULE THE PRE—CONSTRUCTION MEETING.
- 4. PROVIDE A ½ SIZE SET OF PLANS FOR THE INSPECTOR AT THE PRE-CONSTRUCTION.
- 5. PROVIDE AN ANTICIPATED CONSTRUCTION SCHEDULE AT THE PRE-CONSTRUCTION.
- 6. BRING YOUR SWP3 FOR COMPLETENESS CHECK AT THE PRE-CONSTRUCTION.
- 7. ALL DEVELOPMENT SHALL BE IN ACCORDANCE WITH THE PLANS APPROVED BY TRAVIS COUNTY.
- 8. SCHEDULE YOUR PROJECTS PRE-CONSTRUCTION MEETING THROUGH THE MYPERMITNOW.ORG ACCOUNT AFTER THE INITIAL 3RD PARTY SWP3 INSPECTION REPORT HAS BEEN UPLOADED AND ALL PERMITS AND NOTICES HAVE BEEN POSTED, THEN FOLLOW UP WITH EMAILS TO THE ENVIRONMENTAL INSPECTOR AT ENV-INSPECTION@TRAVISCOUNTYTX.GOV

CONSTRUCTION NOTES (1 OF 2)

SHEET 2 OF 9

P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN SERVICES, LLC

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727

GENERAL NOTES:

1. THE INFORMATION SHOWN ON THESE DRAWINGS INDICATING TYPE AND LOCATION OF UNDERGROUND, SURFACE, AND AERIAL UTILITIES IS NOT GUARANTEED TO BE EXACT OR COMPLETE. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXACT TYPE AND LOCATION OF ALL UTILITIES AFFECTED BY CONSTRUCTION FOR THIS PROJECT IN ORDER TO AVOID DAMAGING THOSE UTILITIES. THE CONTRACTOR SHALL a) IMMEDIATELY ARRANGE FOR REPAIR AND RESTORATION OF CONTRACTOR—DAMAGED UTILITIES, AND b) PAY FOR SAME AT NO EXTRA COST TO THE OWNER.

2. CONTRACTOR SHALL TELEPHONE "ONE-CALL" SYSTEM @ 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS BEFORE BEGINNING CONSTRUCTION.

- 3. BEFORE BEGINNING ACTUAL EXCAVATION AND CONSTRUCTION OPERATION THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES HAVING FACILITIES IN THE AREA SO THESE COMPANIES CAN DETERMINE IF THE PROPOSED CONSTRUCTION WILL CONFLICT WITH THEIR FACILITIES. CONTRACTOR SHALL CONTACT THE FOLLOWING UTILITIES AT A MINIMUM:
 - 1. CITY OF AUSTIN WATER AND WASTEWATER UTILITY
 - 2. CITY OF AUSTIN ELECTRIC UTILITY
 - 3. AUSTIN GAS COMPANY
 - 4. AT&T TELEPHONE COMPANY
- 4. ALL EXCAVATION FOR THIS PROJECT SHALL BE UNCLASSIFIED.
- 5. THE BIDDER (CONTRACTOR AFTER AWARD) SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY UNREPORTED OBSTACLES OR DISCREPENCIES THAT MAY IMPEDE OR PREVENT THE PROPER CONSTRUCTION OF THIS PROJECT.
- 6. THE CONTRACTOR SHALL MAINTAIN CLEAR PASSAGE FOR LOCAL TRAFFIC AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- 7. ALL WORK AND MATERIAL MUST MEET THE APPLICABLE CITY OF AUSTIN STANDARD SPECIFICATIONS AND CITY OF AUSTIN STANDARDS, LATEST REVISIONS.
- 8. CONTRACTOR/REPAIR CREW MUST NOTIFY CITY INSPECTOR AT LEAST TEWNTYFOUR (24) HOURS PRIOR TO BEGINNING PERMANENT BACK FILL OPERATIONS.
- 9. BACK FILL DENSITY SHALL BE AS SPECIFIED IN ITEM 510 OF THE STANDARD SPECIFICATIONS. TEST METHODS SHALL BE AS SPECIFIED IN THE CITY STANDARD SPECIFICATIONS UNLESS INDICATED OTHERWISE IN WRITING BY THE ENGINEER.
- 10. HOT MIX ASPHALTIC CONCRETE (H.M.A.C.), WHEN REQUIRED, SHALL BE FURNISHED AND PLACED IN ACCORDANCE WITH ITEM 340 OF THE STANDARD SPECIFICATIONS. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE PROVISIONS OF THE CITY OF AUSTIN STANDARD SPECIFICATIONS FOR CUTS IN PUBLIC RIGHT OF WAY.
- 11. FLEXIBLE BASE SHALL BE FURNISHED AND INSTALLED IN COMPLIANCE WITH ITEM 210 OF THE STANDARD SPECIFICATIONS AND IN COMPLIANCE WITH THE CITY OF AUSTIN STANDARDS AND STANDARD SPECIFICATIONS FOR CUTS IN PUBLIC RIGHT OF WAY.
- 12. CONTRACTOR SHALL NOT ALLOW TRAFFIC ON NEWLY PLACED CONCRETE FOR AT LEAST 72 HOURS UNLESS OTHERWISE APPROVED IN ADVANCE BY THE ENGINEER.
- 13. CONSTRUCTION OPERATIONS SHALL BE CONDUCTED IN SUCH A MANNER AS TO PROTECT ROADWAY FACILITIES AT ALL TIMES.
- 14. WHERE REMOVAL OF BASE AND PAVEMENT IS NECESSARY FOR THIS PROJECT ALL BASE AND PAVEMENT SHALL BE REPLACED IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS, CITY'S STANDARD SPECIFICATIONS AND STANDARD SPECIFICATIONS FOR CUTS IN PUBLIC RIGHT OF WAY. ALL PAVEMENT CUTS SHALL BE SAW CUT PRIOR TO PLACEMENT OF H.M.A.C.
- 15. ALL WATER AND WASTEWATER SYSTEM IMPROVEMENTS, UTILITY CHANGES AND UTILITY RELOCATIONS MUST BE IN ACCORDANCE TO CITY OF AUSTIN WATER AND WASTEWATER SYSTEM DESIGN CRITERIA AND SPECIFICATIONS. ALL WATER AND WASTEWATER PLANS MUST BE PRESENTED TO THE CITY OF AUSTIN WATER AND WASTEWATER UTILITY FOR REVIEW AND APPROVAL. ALL WATER AND WASTEWATER CONSTRUCTION MUST BE INSPECTED BY THE CITY OF AUSTIN.
- 16. CONTRACTOR SHALL PROVIDE TEMPORARY DRIVEWAY ACCESS FOR ALL PROPERTY OWNERS ADJACENT TO CONSTRUCTION AREAS EXCEPT DURING PERIODS WHEN CONSTRUCTION IN THE AREA WOULD MAKE ACCESS UNSAFE. EMERGENCY ACCESS SHALL BE IMMEDIATELY PROVIDED TO DRIVEWAYS DURING CONSTRUCTION ON AN AS-NEEDED BASIS.
- 17. SLOPES OF ROADWAY CUTS AND EMBANKMENTS DAMAGED BY ANY OPERATION OF THE CONTRACTOR DURING THE EXECUTION OF THIS PROJECT SHALL BE REPAIRED AND RESTORED TO THE ORIGINAL PRE—CONSTRUCTION CONDITION IN ACCORDANCE WITH ALL APPLICABLE PROVISIONS OF THE STANDARD SPECIFICATIONS. BACK FILL AND FILL PLACED DURING REMEDIAL GRADING SHALL BE COMPACTED TO A DENSITY EQUAL TO OR GREATER THAN THAT OF THE ORIGINAL CONDITIONS AND TO THE SATISFACTION OF THE ENGINEER AND GOVERNING AUTHORITIES.
- 18. NO EXPLOSIVES SHALL BE USED FOR THIS PROJECT WITHOUT A BLASTING PERMIT FROM THE CITY OF AUSTIN.
- 19. CONTRACTOR SHALL MAINTAIN THE JOB SITE IN A SAFE, NEAT AND WORKMANLIKE MANNER AT ALL TIMES. JOB SITE SAFETY SHALL NOT BE COMPROMISED. ANY UNATTRACTIVE NUISANCE SHALL BE REMOVED OR CAMOUFLAGED BY CONTRACTOR WHEN DIRECTED BY THE OWNER OR ENGINEER.
- 20. CONTRACTOR SHALL NOTIFY CONSTRUCTION INSPECTION DIVISION OF THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION AT 974-7180 TO A) ARRANGE A PRE-CONSTRUCTION MEETING NOT LESS THAN FOURTEEN (14) DAYS PRIOR TO BEGINNING CONSTRUCTION, B) NOTIFY INSPECTOR FORTY-EIGHT (48) HOURS IN ADVANCE OF BEGINNING ANY CONSTRUCTION IN THE R.O.W. OR IN EASEMENTS, C) NOTIFY INSPECTOR TWENTY-FOUR (24) HOURS IN ADVANCE OF MAKING ANY SUPPLEMENTARY CONNECTION OR CLOSING OFF ANY WATER AND WASTEWATER SERVICES TO PROPERTY OWNER.
- 21. BEFORE DISCONNECTING ANY WATER LINE OR GAS LINE, CONTRACTOR MUST PROVIDE TWENTY—FOUR (24) HOUR NOTICE TO THE OWNER EXCEPT IN THE CASE OF A BONA FIDE EMERGENCY.
 22. ALL TRAFFIC CONTROL DEVICES, SIGNS, BARRICADES, WARNING SIGNS, AND FLAG MEN OPERATIONS SHALL BE PLACED, CONSTRUCTED, EXECUTED AND MAINTAINED IN ACCORDANCE WITH THE
 TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUDTC), THE CITY OF AUSTIN STANDARD SPECIFICATION SERIES 800, AND THE CITY OF AUSTIN TRANSPORTATION CRITERIA MANUAL. IF A
 CONFLICT ARISES, THEN THE SERIES 800 SPECIFICATIONS SHALL CONTROL UNLESS OTHERWISE INSTRUCTED BY THE ENGINEER.
- 23. WHERE PORTABLE SIGNS REQUIRE THE USE OF WEIGHTS, SANDBAGS SHALL BE USED. THE USE OF SOLID OBJECTS SUCH AS CONCRETE, ROCKS, IRON, ETC. SHALL NOT BE PERMITTED.
 24. INSTALLATION OF CONSTRUCTION BARRICADING AND SIGNING SHALL BE COORDINATED THROUGH THE TRANSPORTATION ENGINEERING AND SIGNALS DIVISION OF THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION AT 974-7024.
- 25. ALL TRAFFIC CONTROL SIGNS SHALL REMAIN IN PLACE UNLESS OTHERWISE SHOWN ON THE PLANS. IF SIGNS REQUIRE RELOCATION, CONTRACTOR SHALL CONTACT THE TRANSPORTATION ENGINEERING AND SIGNALS DIVISION OF THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION AT 974-7024.
- 26. CONTRACTOR MUST RESTORE ALL PAVEMENT MARKINGS DISTURBED DURING CONSTRUCTION. CONTRACTOR SHALL OBSERVE ALL APPLICABLE MATERIALS, SPECIFICATIONS, AND INSTALLATION REQUIREMENTS INCLUDING SPECIAL ATTENTION TO MAINTAINING PROPER DIMENSIONS AND ALIGNMENT.
- 27. ALL HOLES, TRENCHES, AND OTHER HAZARDOUS AREAS SHALL BE ADEQUATELY PROTECTED BY BARRICADES, FENCING, LIGHTS, AND/OR OTHER PROTECTIVE DEVICES AT ALL TIMES.
- 28. CONTRACTOR SHALL NOTIFY ALL APPLICABLE AUTHORITIES PRIOR TO EXCAVATION
- 29. REMOVAL OF EXCAVATED MATERIALS AND DAILY CLEANUP OPERATIONS SHALL BE PERFORMED TO THE SPECIFICATIONS AND TO THE SATISFACTION OT THE OWNER AND ENGINEER.
- 30. UNATTENDED TRENCHES MUST BE COVERED WITH STEEL PLATES CAPABLE OF SUPPORTING VEHICULAR TRAFFIC. THESE STEEL PLATES MUST BE ADEQUATELY ANCHORED TO PREVENT THEM FROM BECOMING DISLODGED.
- 31. ALL CONSTRUCTION AND TRENCHING OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA). COPIES OF OSHA STANDARDS MAY BE PURCHASED FROM THE U.S. GOVERNMENT PRINTING OFFICE.
- 32. CONTRACTOR SHALL MAINTAIN A SUPERINTENDENT UPON THE PROJECT AT ALL TIMES WORK IS IN PROGRESS.
- 33. CONTRACTOR SHALL COMPLY WITH CONSTRUCTION SEQUENCING WHICH IS SPECIFIED ELSEWHERE IN THE PLANS.
- 34. FOR CONSTRUCTION IN THE RIGHT OF WAY, A CONCRETE PERMIT IS REQUIRED.

NICHOLAS R. SANDLIN

124404

CENSE

SONAL ENGINE

CONSTRUCTION NOTES (2 OF 2)


SHEET 3 OF 9


P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS



REVISION RECORD





FINAL PLAT (1 OF 3)


SHEET 4 OF 9

P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN
SERVICES, LLC

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727



FINAL PLAT OF PEDERNALES ELECTRIC CIRCLE DRIVE AUSTIN COOPERATIVE SUBDIVISION

PLAT, THE COMMISSIONERS COURT OF TRANS (
O OBLIGATION TO BUILD THE STREET'S, ROADS, ARES SHOWN ON THIS PLAT OR ANY BRIDGES OF THE STREET'S, ROAD SPOUGHARES SHOWN ON THIS OF THE STAND ALL BROCKSPARES SHOWN ON THIS OFFICE AND ALL BROCKSPARES SHOWN ON THIS OFFICE SHOWN OF THE SHOWN OF THIS OFFICE SHOWN OF THE SHOWN OF THE SHOWN OF THE SHOWN OF TH

STATE OF TEXAS! COUNTY OF TRAV

and do hereby dedicate to the public the use of all streets. Easements shown hereon, subject to any and all easements. Restrictions heretofore granted and not released. ON THE DATE WRIT Cay KRIL

BEFORE ME. THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY INCHES OF A PERSONALLY INCHES OF A PERSONALLY INCHES OF A PERSONAL OF A PERSONAL

"AUTHORIZED FOR RECORD, UNDER SECTION
AAVINS COULDINGS, BY THE
SPORTATION AND NATURAL, RESOURCES, TRANS
DAY OF WAN

THIS PLAT BY THE COMMISSIONERS OF STREAMS FOR MAINTENANCE BY TRANSPECT IN THE SUBDINISION DOES NOT REET NAME SIGNS OR EBECT TRAFFIC OF STOP SIGNS, AND MELD SIGNS, WHICH PER STOP SIGNS, AND MELD SIGNS, WHICH SIGNS, WHICH SIGNS, WHICH SIGNS, WHICH SIGNS, WHICH SIGNS, WHICH SIGNS SIGNS, WHICH SIGNS SIGNS, WHICH SIGNS SI

5/19/06 DATE

GIVEN UNDER MY HAND AND SEAL OF OFFICE

KELLY 12/28 Manus Miles Killy PUBLIC IN MID FOR TRANS COUNTY, TEXAS NAMW NIXON PRINT OR STAMP NAME HERE MY COMM

MINIMUM FINISHED FLOOR ELEVATION FOR ALL AFFECTED STRUCTURE. SHALL BE ONE (1) FOOT ABOVE THE ELEVATION OF THE 100—YEAR FLOOD PLAIN AS SHOWN HEREON: 1019 M.S.L. I, ELJAS G, HADDO, HERBY CRETPY THAT THE PROPANTION AND CALCILLATIONS SUBMITTED ARE COPRECT TO THE BEST OF MY KNOWEDGE. AND ARE IN COMPLIANCE WITH THE TENNS AND REQUIREMENTS OF THE APPLICABLE PROVISIONS OF CHAPTER 30 OF THE AUSTIN OTTY CODE, EXCEPT WHERE VARIANCES ARE APPRICED. THE 100 YEAR FLOODPLAIN IS CONTAINED WITHIN THE DRAINEGE EASEMENT AS SHOWN HERRON. A PORTINO OF THIS YEACT! S WITHIN THE DESIGNATED FLOOD HAZARD AREA AS SHOWN ON THE FEDERAL BENEBERORSON MANABEMENT AGENCY (FLOOD INSURANCE RATE MAY (FIRM)), #4845XC03300 E, TRANS. COUNTY, TEXAS, DATED JUNE 16, 1995, COMMUNITY # 481026.

5. 11. 06 DATE CLOS Addact
ELIAS G. HADDO P.E. 8720
CUNNINGHAM ALLEN, INC.
3103 BEE CAPE ROAD, SUITE 202
AUSTIN, TEXAS "78746
(PHONE) 512–327–2946 (FAX) 51

I, DANA DEBEAUVOIR. CLERK OF TRÂNS COUNT THE FORECOND INSTRUMENT OF WRITHING AND AUTHEN PARTON WAS FILED FOR RECORDED ON RECORDED ON THE TOWN OF THE T

STATE OF TEXAS: COUNTY OF TRAVIS

MITNESSAM HAND AND SEAL OF OFFICE OF

DAY OF

20

A.D.

I, FREDDIE E. DIPPEL, JR., AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAST OF PACINGE. THE PROFESSION OF SIRVEY MELLAD PORTIONS OF THE AUSTIN COMPLES WITH THE SURVEY RELLAD PORTIONS OF THE AUSTIN CITY CODE. OF DECEMBER 2003 EXCEPTING THE 30–2–131 MIS SUBMETAL, IS TIME AND CORRECT TO THE REST OF MY KNOWEDGE AND WAS PREPARED FROM AN ACTUAL SIRVEY OF THE PROPERTY MADE BY WE OR UNDER MY SURVEY OF THE PROPERTY MADE BY WE OR UNDER MY SURVEY OF THE RROUND. FREDE E. DIPPEI REGISTERED PRO CUNINGHAM-ALL 3103 BEE CAVE A AUSTIN, TEXAS 78 (PHONE) 512–327

SON THE SE

DANA DEBEAUVOR, COUNTY CLERK
TRANS COUNTY TEXAS
DEPUT

5-11-06 DATE NO. 2988 PEL, JR. ROFESSIONAL LAND SURVE

3 COMIN

66.437 ACRES о П LINEAR FEET OF TOTAL AREA:

2-21-2006 C8J-06-0024.0A SUBMITTAL DATE:

3103 Bee Cave Road, Suite 202 Austin. Texas 78746-6819

Tel.: (512) 327-2946 Fax: (512) 327-2973

. AL STREETS, DRANAGE, SIDEWALKS, EROSION CONTROL, AND WATER LINES IN THAN SUBDIVISION SHALL BE CONSTRUCTED AND INSTALLED TO CITY OF AUSTIN THAN SARBONS.

A TRAVIS COUNTY DEVELOPMENT PERMIT IS REQUIRED PRIOR TO ANY SITE VALOPMENT. SION TO BE FURNISHED BY PEDER 3. ELECTRIC SERVICE FOR THIS SUB-ELECTRIC COOPERATIVE. 4. NO OBJECTS, INCLUDING BUT NOT LIMITED TO BUILDINGS, FENCES OR LALIVINGSAPHING SHALLE BE ALLOWED IN PREMINGE AND CONSERVATION EASER EXCEPT AS APPROVED BY THE CITY OF AUSTIN AND TRAMS COUNTY.

5. THE OWNER OT THIS SUBDIVISION, MAIN HIS OR HER SUCCESSORS AND ASSIGNS, ASSUMES RESPONSIBILITY FOR PLANS FOR CONSTRUCTION OF SUBDIVISION MARKOVERINTS WHICH COMPLY WITH APPLICABLE CODES AND REQUIREMENTS OF THE CONFINE THE OWNER'S WIDERSTANDS AND AGKNOWEDIGS THAT PLAT VACATION OR REPARTING MAY BE REQUIRED. AT THE OWNER'S SOLE EXPENSE, IF PLANS TO CONSTRUCT THIS SUBDIVISION DO NOT COMPLY WITH SUCH CODES AND REQUIREMENTS.

6. ALL DRAINAGE FACILITIES WILL BE LOCATED WITHIN DRAINAGE EASEMENTS.

7. WATER QUALITY CONTROLS ARE REQUIRED FOR ALL DEVELOPMENT PURSUANT TO TITLE 30, SECTION 30–5–211A.

9. PRIOR TO CONSTRUCTON, EXCEPT DETACHED SINGLE-FAMILY ON ANY LOT IN THIS SUBDIVISION, A SITE DEVELOPMENT PERMIT MUST BE OBTAINED FROM THE CITY OF AUSTIN. B. EROSION/SEDIMENTATION CONTROLS ARE REQUIRED FOR ALL CONSTRUCTION PURSOLY TO EACH LOT INCLUDING SINGLE FAMILY AND DIDELY CONSTRUCTION PURSOLY OF EACH OF SECTION 30-5-161, AND THE ENVIRONMENTAL CRITERA MANULAL. 10. ALL DRAINAGE EASEMENTS ON PRIVATE PROPERTY SHALL BE MAINTHE PROPERTY OWNER OR ASSIGNS.

12 PEDERNALES ELECTRIC COOPERATIVE HAS THE RIGHT TO PRUNE AND /OR REMOVE THESES, SHAMBBERY AND ONEN DESISTANCIONEN TO THE EXTENT HE EXPENTIS CLEAR. THE UTILITY MILL PERFORM ALL THE WORK IN CAMPLANCE WITH CAMPLER 25—8, SUBCHAPTER B, OF THE OTF ALL AND THE LAND EVELLOPMENT CODE. 11. PROPERTY OWNER SHALL PROVIDE FOR ACCESS TO DRAINAGE EASEMENTS AS MAY BE NECESSARY AND SHALL NOT PROHIBIT ACCESS BY GOVERNMENT AUTHORITIES.

13. THE OWNER/DEVELOPER OF THIS SUBDIVISION/LOT SHALL PROVIDE PEDERALESE BLECTRIC COOPERATIVE WITH ANY ESABERINTS MAD/OR ACCESS MONIORED, IN ADDITION TO THOSE INICIATED, FOR THE INSTALLATION AND ONGOINED, IN ANNITRANIC OF OVERHEAD AND UNICIATED, FOR THE INSTALLATION AND SEE EASEMENTS AND OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING, AND WILL NOT BE LOCATED SO AS TO CAUSE. THE STEP DE OUT OF COMPLIANCE WITH CHAPTER 25—8 OF THE CITY OF AUSTINIAND DEVELOPMENT CODE.

14, FOR A MINIMUM TRAVEL DISTANCE OF 25' FROM THE ROADWAY, GRADES MAY, NOT EXCECT OF 14, % ONLY, WITH SPECIAR APPROVAL OF SURFACE AND GEOMETRIC DEPARTMENT OF AUSTIN.

THIS SUBBANSON PLATAS LOCATED MITHIN THE TWO MILE EXTRA TERRIT JURISDICITION OF THE OTHER OF AUSTIN, ON THIS THE 12th DAY OF APPROVED AND AUTHORISED FOR RECORD OF THE DIRECTOR WITESHED PROPEDIATION & DEVELOPMENT REVIEW DEPARTMENT, GITY OF COUNTY OF TRAVEY, THIS THE 14th DAY OF CACA.

16. BY APPROVING THIS PLAT, THE CITY OF AUSTIN ASSUMES NO OBLICATION TO CONSTRUCT ANY INTRASPRICTURE IN CONNECTION WITH THIS SUBDIVISION, ANY SUBDIVISION HER DEVELOPMENT OF THE LOTS IN THE SUBDIVISION SHE PERSONSBILD TO THE DEVELOPMENT OF THE LOTS IN WHISTS OF THE LOTS. FAILURE TO CONSTRUCT ANY REQUIRED INFRASTRICTE TO CITY STANDARDS MAY BE AUST CAUSE FOR THE CITY TO DENY APPLICATIONS FOR APPROVALS, AND/OR CERTIFICATES OF DEVELOPMENT SITE PLAN

16. WATERSHED STATUS: THIS PROJECT IS LOCATED IN THE SLAUGHTER OREEK WATERSHED, IS CLASSHED AS BATKING SPRINGS 200E, AND SHALL BE LOCATED AND WAITAINED IN CONFEDNANCE WITH THE TERM OF CHAPTER 25–2 AND CHAPTER 25–8 OF THE CITY OF AUSTRALL CONFEDNANCE WITH STATUS CONFIDENCE 200F. THE PROJECT IS IN THE EDWARDS AQUIFER TO THE PROJECT IS IN THE EDWARDS AQUIFER TO THE CITY OF AUSTRALL CONFIDENCE 200F.

17. PUBLIC SDEWALKS BUILT TO THE CITY OF AUSTIN STANDARDS, ARE REQUIRED FACE OF THIS POLICIANIS STREETS AND AS SHOWN BY A DOTTON TO THE OLD WHO, STREETS AND AS SHOWN BY A DOTTON THE IN PACE PROFICE OF THIS PACE. PROFICE THESE SIDEWALKS SHALL BE IN PACE PROFICE TO THE OLD THE OL

16" THE WATER UTILITY SYSTEM SERVING THE SUBDIVISION MUST BE IN ACCORDANCE WITH THE OFFICER, ON SPECIFICATIONS. THE WATER CONTINEY BLANK MUST BE REVIEWED AND APPROVED BY THE AUSTIN WATER UTILITY. THE WATER UTILITY CONSTRUCTION MUST BE INSPECTED BY THE CITY. PROVIDED BY AN ON SITE WASTEWATER 19. WASSEWATER FOR LOT 1 WILL BE DISPOSAL SYSTEM.

IN ON LOTS IN THIS SUBDIVISION, DRAINAGE PLANS CITY OF ALISTIN FOR REVIEW, RAINFALL RUNOFF MOUNT EXISTING AT UNDERDEVELOPED STATUS BY THEMMENDOS. 22. WATCH WE BE FROMED BY THE CITY OF ADSIRY.

23. WATCH OF AUSTIN WAITS UTILITY SYSTEM AND AN APPROVED DNSITE SEPTIOL OF AUSTIN WAITS UTILITY SYSTEM AND AN APPROVED DNSITE SEPTIOL SYSTEM.

22. PROOF AUSTIN WAITS UTILITY SYSTEM AND AN APPROVED DNSITE SEPTIOL SYSTEM.

WILL BE SHEMITTO THE GITY OF AUSTIN FOR REVIEW, RAINFALL BROWDER SHALL BE SHEMITTO THE GITY OF AUSTIN FOR REVIEW, RAINFALL BROWDER PROVINCE OF A PROPERTY OF AUSTIN FOR REVIEW. RAINFALL BROWDER PROVINCE OF A PROPERTY RESIDENCE AT UNDERDEVELOPED STATUS BY

CITY OF AUSTIN BRASS DISK IN SOUTH R.G.W. O EAST OF THE INTERSECTION OF PITTER PAT LAN ELEVATION = 1083.07 "L" CUT ® CENTERLINE OF CULVERT HEAD 715' +/- EAST OF THE INTERSECTION OF ELEVATION = 1086.02' BENCHMARK REFERENCE: LCRA | ELEVATION = 1032.05 BEARING BASIS: GRIF NAD83 (CORS) CENTI

NO STRUCTURE IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO PUBLIC SEWER SYSTEM OR A PRIVATE ON-SITE WASTEWALER DISPOSAL SYSTEM PPROVED BY THE TRANS COUNTY ON-SITE WASTEWATER PROGRAM. 5. ALL DEVELOPMENT ON ALL LOTS IN THIS SUBDIVISION MUST BE IN ACCORDANCE WITH THE IMMINION RECORDERENENTS OF TEXAS ADMINISTRATIVE CODE CHAPPIER 285 AND TRAVES COUNTY CODE CHAPPIER 48. 4. NO CONSTRUCTION MAY BEGIN ON A LOT IN THIS SUBDIVISION UNTIL PLANS STORED THE STRAYE IN-VERT EMPORAL SYSTEM, ARE SUBMITTED TO THE TRAYS COUNT ON-SITE WASTEMATER PROGRAM. 3. NO ON-SIT. WASTEWATER DISPOSAL SYSTEM MAY BE INSTALLED WITHIN 100 FFEET OF A PROVINE WAITER WELL LOW MAY AN ONE-SITE WASTEW ARE LOW SYSTEM BE INSTALLED WITHIN 150 FEET OF A PUBLIC WATER WELL. 2. NO STRUCTURE IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONI TO A POTABLE WATER SUPPLY FROM AN APPROVED WATER SYSTEM.

FALL THINGS
BYOSOM MAKER
PLANNING AND ENGINEERING SERVIC
THR- TRANS COUNTY

NICHOLAS R. SANDLIN
124404
CENSEO 6/19/2023


SHEET 6 OF P.E.C. OAK HILL EAPP **EXCELL FUELING SYSTEMS**

FINAL PLAT (3 OF 3)


TBPELS FIRM #21356 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727

SANDLIN

REVISION RECORD



- 1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.
- 3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.
- 4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF CONSTRUCTION.
- 5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.
- 6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.
- 7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.
- 8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.
- 9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA FOR 14 DAYS.
- 10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.
- 11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.
- 12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.
- 13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL.




LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION . FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE**



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.




DRAINAGE AREA BOUNDARY

DRAINAGE AREA DESIGNATION AND AREA DRAINED



FLOW ARROW



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

EROSION CONTROL AND DRAINAGE PLAN


SHEET 7 OF 9


P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS


SANDLIN

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2: AUSTIN, TX 78727






PROPERTY KEY MAP




IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE



SANDLIN

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727



- STONE SIZE: 75-125 mm (3-5") OPEN GRADED ROCK.
- LENGTH: AS EFFECTIVE BUT NOT LESS THAN 15 m (50').
- THICKNESS: NOT LESS THAN 200 mm (8").

CITY OF AUSTIN

WATERSHED PROTECTION DEPARTMENT

REVISION RECORD

RECORD COPY SIGNED
5/23/00
PATRICK MURPHY

- WIDTH: NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS/EGRESS WASHING: WHEN NECESSARY, VEHICLE WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE AND DRAINS INTO AN APPROVEI TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.
- SIORM DRAIN, BICH OF WALER-COURSE USING APPROVED METHODS.

 MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC ROADWAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AS WELL AS REPAIR AND CLEAN OUT OF ANY MEASURE DEVICES USED TO TRAP SEDIMENT. ALL SEDIMENTS THAT IS SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADWAY MUST BE REMOVED IMMEDIATELY.

STABILIZED CONSTRUCTION ENTRANCE

DRAINAGE: ENTRANCE MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.

		.4 m (8') SPACING
SILT FENCE F	ABRIE	2" x 4" WELDED WIRE BACKING SUPPORT FOR FABRIC (12.5 GA. WIRE)
		600 mm
	FLOW	150 mm— (6") MIN.
	FABRIC TOE-IN TRENCH (BACKFILLED)	
STANDARD SYMBOL FOR SILT FENCE (SF)		150 mm —— T
		TRENCH CROSS SECTION
	TS WHICH SUPPORT THE	SILT FENCE SHALL BE INSTALLED ON

-STEEL OR WOOD FENCE POSTS

A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 300 mm (12 INCHES). IF WOOD POSTS CANNOT ACHIEVE

2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.

inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.

4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE , WHICH IS IN TURN ATTACHED TO THE STEEL OR

5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.

6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

09/01/201

ADOPTED

SILT FENCE

THE ARCHITECT/ENGINEER ASSUMES STANDARD NO. RESPONSIBILITY FOR APPROPRIATE USE 6425-1

CITY OF AUSTIN

RECORD COPY SIGNED BY MORGAN BYARS

POSTS POSTS POSTS A FT SPACING (BOTH SIDES)	ANCHOR POSTS OR ANCHOR MULCH MATERIAL TO FILL SEAM BETWEEN ANCHORS GROUND MILCH MATERIAL TO FILL SEAM BETWEEN THE SOCK AND THE GROUND MIN. 24*
0 0	MULCH SOCK MATERIAL USE UNTREATED WOOD CHIPS PRODUCED FROM A 3 (THREE) INCH MINUS SCREENING PROCESS (EQUIVALENT TO TXDOT
MULCH SOCK MULCH SOCK O O MINIMUM 12" (300 mm)	ITEM 161, COMPOST, SECTION 1.6.2.B, WOOD CHIP REQUIREMENTS). MULCH CONSISTS PRIMARILY OF ORGANIC MATERIAL, SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE:
OVERLAP DO NOT STACK MULCH SOCKS	SHREDDED BARK, STUMP GRINDINGS, OR COMPOSTED BARK. LARGE PORTIONS OF SILT. CLAYS. OR FINE SANDS ARE NOT

NOTES:


1. STEEL OR WOOD POSTS WHICH SUPPORT THE MULCH SOCK SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 600mm (24 inches). IF WOOD POSTS CANNOT ACHIEVE 600mm (24 inches) DEPTH, USE STEEL POSTS. EARTH

ACCEPTABLE IN THE MULCH.

- 2. THE TOE OF THE MULCH SOCK SHALL BE PLACED SO THAT THE MULCH SOCK IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. IN ORDER TO PREVENT WATER FROM FLOWING BETWEEN THE JOINTS OF ADJACENT ENDS OFMULCH SOCKS, LAP THE ENDS OF ADJACENT MULCH SOCKS A MINIMUM
- MULCH MATERIAL MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH; IT IS NOT ACCEPTABLE FOR THE MULCH MATERIAL TO CONTAIN GROUND CONSTRUCTION DEBRIS, BIOSOLIDS, OR MANURE.
- SOCK MATERIAL WILL BE 100% BIODEGRADABLE, PHOTODEGRADABLE, OR RECYCLABLE SUCH AS BURLAP, TWINE, UV PHOTOBIODEGRADABLE PLASTIC, POLYESTER, OR ANY OTHER ACCEPTABLE
- MULCH SOCKS SHOULD BE USED AT THE BASE OF SLOPES NO STEEPER THAN 2:1 AND SHOULD NOT EXCEED THE MAXIMUM SPACING CRITTERIA PROVIDED IN CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL TABLE 1.4.5.F.1 FOR A GIVEN SLOPE CATEGORY.
- ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.


CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	MULCH SOCK	
RECURD CUPY SIGNED BY 08/24/2010 ADDPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE US OF THIS STANDARD.	standard nd. #6485-1





EXCAVATED WASHOUT STRUCTURE

ONSITE CONCRETE WASHOUT STRUCTURE OR APPROVED EQUAL




CAN BE TWO STACKED NOTE: BALES OR PARTIALLY EXCAVATED TO REACH 3 FT DEPTH

WASHOUT STRUCTURE WITH STRAW BALES

CONSTRUCTION SPECIFICATIONS

"642S-1

- 1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FFFT AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS, WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION
- SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3
- 3. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER, FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY OF THE MATERIAL.
- 4. PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY.
- 5. KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS. REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UP, FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL STRUCTURE IS REMOVED.



WASHOUT STRUCTURE WITH WOOD PLANKS

EROSION CONTROL DETAILS SHEET 9 OF 9 P.E.C. OAK HILL EAPP **EXCELL FUELING SYSTEMS**

SANDLIN TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2 AUSTIN, TX 78727



Attachment N: Inspection, Maintenance, Repair and Retrofit Plan NOT APPLICABLE

As no additional IC is proposed for the site, the existing and approved WPAP 11-06030101 (approved May 4, 2006) BMP inspection, maintenance, repair and retrofit plan is still in effect. No changes are needed.



Attachment O:

Pilot-Scale Field Testing Plan, if BMPs not based on complying with Edwards Aquifer Rules: Technical Guidance for BMPs (NOT APPLICABLE)

A pilot-scale field testing plan is not applicable. All BMP design and calculations were based on and comply with Edwards Aquifer Technical Guidance for Edwards Aquifer Rules (RG-348, revised July 2005).



Attachment P: Measures for Minimizing Surface Stream Contamination

No surface streams flow across the property. The property drains southeast toward the Slaughter Creek segment 1427A, located approximately 2.0 miles to the southeast. The existing retention/irrigation BMP will continue to address onsite water quality and stormwater drainage to mitigate and minimize offsite surface stream contamination.



Temporary Stormwater Section (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

Date: 6/15/2023

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Nick Sandlin, P.E. (Sandlin Services, LLC)

Signature of Customer/Agent:

Nice State Control of Customer/Agent:

Regulated Entity Name: PEC Oak Hill

Project Information

Potential Sources of Contamination


Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1.	Fuels for construction equipment and hazardous substances which will be used during construction:
	The following fuels and/or hazardous substances will be stored on the site:
	These fuels and/or hazardous substances will be stored in:
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
	igstyle igstyle Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
S	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6.	Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Slaughter Creek
T	emporary Best Management Practices (TBMPs)
sta co ba	osion control examples: tree protection, interceptor swales, level spreaders, outlet abilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized instruction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment sins. Please refer to the Technical Guidance Manual for guidelines and specifications. All ructural BMPs must be shown on the site plan.
7.	Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to

retain sediment on site to the extent practicable. The following information is attached:

	 ☑ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site. ☑ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. ☑ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer. ☑ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or
8.	construction. The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	 ■ Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. ■ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map . A drainage area map supporting the following requirements is attached:
	 □ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided. □ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used. □ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. □ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.



- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



Temporary Stormwater Section (TCEQ-0602)

Attachment A: Spill Response Actions

Spill Response Actions

In the event of an accidental spill, immediate action shall be undertaken by the General Contractor to contain and remove the spilled material. All hazardous materials, including contaminated soil and liquid concrete waste (if applicable), shall be disposed of by the Contractor in the manner specified by Federal, State and Local regulations and by the manufacturer of such products. As soon as possible, the spill shall be reported to the appropriate agencies. As required under the provisions of the Clean Water Act, any spill or discharge entering waters of the United States shall be properly reported. The General Contractor shall prepare a written record of any spill and associated clean-up activities of petroleum products or hazardous materials in excess of 1 gallon or reportable quantities, whichever is less. The General Contractor shall provide notice to the Owner immediately upon identification of a reportable spill.

All spills of petroleum products or hazardous materials in excess of Reportable Quantities as defined by EPA or the State or Local agency regulations, shall be immediately reported within 24 hours to the EPA National Response Center (1-800-424-8802), TCEQ (1-800-832-8224), and local Fire Department (911).

The reportable quantity for hazardous materials can be found in 40 CFR 302:

Reportable Quantities			
Material	Media Released to	Reportable Quantities	
Engine Oil, Fuel, Hydraulic & Brake Fluid	Land	25 gallons	
Engine Oil, Fuel, Hydraulic & Brake Fluid	Water	Visible sheen	
Antifreeze	Land	100 lbs (13 gal.)	
Battery Acid	Land, Water	100 lbs	
Refrigerant	Air	1 lb	
Gasoline	Air, Land, Water	100 lbs	
Engine Degreasers	Air, Land, Water	100 lbs	

For more information, please visit https://www.tceq.texas.gov/response/spills/spill_rq.html

In order to minimize the potential for a spill of petroleum product or hazardous materials to come in contact with stormwater, the following steps shall be implemented.



- a) All materials with hazardous properties (such as pesticides, petroleum products, fertilizers, detergents, construction chemicals, acids paints, paint solvents, additives for soil stabilization, concrete curing compounds and additives, etc.) shall be stored in a secure location, under cover and in appropriate, tightly sealed containers when not in use.
- b) The minimum practical quantity of all such materials shall be kept on the job site and scheduled for delivery as close to time of use as practical. Post Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- c) A spill control and containment kit (containing for example: absorbent material such as kitty litter or sawdust, acid neutralizing agent, brooms, dust pans, mops, rags, gloves, goggles, plastic and metal trash containers, etc.) shall be provided on the construction site and construction employees shall be trained in when and how to use spill containment materials.
- d) The contractor personnel will immediately clean up any oil, fuel or hydraulic fluid if observed being released from equipment or vehicles. Vehicles or equipment will cease operation until required repairs are made to the equipment.
- e) All of the product in a container shall be used before the container is disposed of. All such containers shall be triple rinsed with water prior to disposal. The rinse water used in these containers shall be disposed of in a manner in compliance with State and Federal regulations and shall not be allowed to mix with stormwater discharges.
- f) All products shall be stored in and used from the original container with the original product label.
- g) All products shall be used in strict compliance with instructions on the product label.
- h) The disposal of the excess or used products shall be in strict compliance with instructions on the products label.

Spill Prevention and Control

Education

- 1.) Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
- 2.) Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.



- 3.) Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- 4.) Establish a continuing education program to indoctrinate new employees.
- 5.) Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

- 1.) To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- 2.) Store hazardous materials and wastes in covered containers and protect from vandalism.
- 3.) Place a stockpile of spill cleanup materials where it will be readily accessible.
- 4.) Train employees in spill prevention and cleanup.
- 5.) Designate responsible individuals to oversee and enforce control measures.
- 6.) Spills should be covered and protected from stormwater runon during rainfall to the extent that it doesn't compromise cleanup activities.
- 7.) Do not bury or wash spills with water.
- 8.) Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- 9.) Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- 10.) Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- 11.) Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- 12.) Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.



Cleanup

- 1.) Clean up leaks and spills immediately.
- 2.) Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- 3.) Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- 1.) Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- 2.) Use absorbent materials on small spills rather than hosing down or burying the spill.
- 3.) Absorbent materials should be promptly removed and disposed of properly.
- 4.) Follow the practice below for a minor spill:
- 5.) Contain the spread of the spill.
- 6.) Recover spilled materials.
- 7.) Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities. Spills should be cleaned up immediately:

- 1.) Contain spread of the spill.
- 2.) Notify the project foreman immediately.
- 3.) If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- 4.) If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- 5.) If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.



Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- 1.) Notify the TCEQ by telephone as soon as possible and within 24 hours at 512- 339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- 2.) For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- 3.) Notification should first be made by telephone and followed up with a written report.
- 4.) The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- 5.) Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

More information on spill rules and appropriate responses is available on the TCEQ website at: http://www.tnrcc.state.tx.us/enforcement/emergency_response.html.

Vehicle and Equipment Maintenance

- 1.) If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- 2.) Regularly inspect onsite vehicles and equipment for leaks and repair immediately.
- 3.) Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- 4.) Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- 5.) Place drip pans or absorbent materials under paving equipment when not in use.
- 6.) Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
- 7.) Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.



- 8.) Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- 9.) Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

Vehicle and Equipment Fueling

- 1.) If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- 2.) Discourage "topping off" of fuel tanks.
- 3.) Always use secondary containment, such as a drain pan, when fueling to catch spills/leaks.

SPILL REPORT FORM

Notes to General Contractor:

- Control and contain the spill.
- Contact the appropriate regulatory agencies if the spill exceeds the applicable reportable quantity.
- Clean up the spill and dispose of waste according to federal, state and local regulations.
- Complete the Spill Report Form in full for each spill that exceeds the applicable reportable quantity and submit to the Owner.
- Call the Owner.
- Resolve as appropriate and as required by regulatory authorities.



THE GOVERNING AGENCY

DATE.

SPILL REPORT FORM

PROJECT: PROJECT ADDRESS:		
Spill Reported By:		
Date / Time of Spill:		
Describe spill location and events leading to spill:		
Material Spilled:		
Source of Spill:		
Amount Spilled:		
Amount Spilled to Waterway (Name Waterway):		
Containment or Clean up Action:		
Approximate depth (yards) of soil excavation:		
List injuries or Personal Contamination:		
Action to be taken to prevent future spills:		
Agencies notified of spill:		
Contractor Signature and Printed Name	Date	
AFTER NOTIFYING GOVERNING AUTHORITIES, IM	MEDIATELY COMPLETE TI	HIS FORM

Sandlin Services, LLC | TBPE Firm # 21356 | P. (806) 679-7303 | www.SandlinServices.com

AND CONTACT THE OWNER IF THE SPILL EXCEEDS THE REPORTABLE QUANTITY FOR



Temporary Stormwater Section (TCEQ-0602)

Attachment B: **Potential Sources of Contamination**

Potential Sources of Contamination and Preventive Measures:

Potential Source: Concrete and concrete products used on-site during construction.

Preventive Measures: Concrete washout structure will be used if necessary.

Potential Source: Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle

dripping.

Preventative Measures: Vehicle maintenance will be performed at a local maintenance shop.

Potential Source: Miscellaneous trash and litter from construction workers and material wrappings.

Preventative Measures: Trash containers will be placed throughout the site to encourage proper disposal of trash.

Potential Source: Silt leaving the site

Preventative Measures: Contractor will install all temporary best management practices prior to start of construction

including the stabilized construction entrance to prevent tracking onto adjoining streets.

Potential Source: Construction debris

Preventative Measures: Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

Potential Source: Soil and mud from construction vehicle tires as they leave the site.

Preventative Measures: a stabilized construction exit shall be utilized as vehicles leave the site. And soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

Potential Source: Sediment from soil, sand, gravel, and excavated materials stockpiled on site.

Preventative Measures: Fiber roll shall be installed on the down gradient side of the stockpiled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

Potential Source: Portable toilet spill

Preventative Measures: Toilets on the site will be emptied on a regular basis by the contracted toilet company.



Attachment C: Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage (AC)to be disturbed is listed in parentheses next to each activity. Maximum total construction time is not expected to exceed 3 months.

Intended Schedule or Sequence of Major Activities:

- 1. Submit written notice of construction to TCEQ regional office at least 48 hours prior to the start of any regulated activities. (See Permanent Stormwater Section Attachment F)
- 2. A pre-construction conference prior to commencement of construction. All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
- 3. Contractors must follow requirements as outlined in TCEQ General Construction Notes for the Contributing Zone Plan (CZP). CZP Construction Notes are listed in the Construction Plans (Attachment M of the Contributing Zone Plan Application section).
- 4. Prior to beginning any construction activity, all temporary erosion and sedimentation BMPs and control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications (0.15 Acres).
- 5. Evaluate temporary erosion control installation. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- 6. Review construction schedule and the Contributing Zone Plan (CZP) requirements.
- 7. Install the AST (0.15 Acres).
- 8. Piping and ancillary equipment installation.
- 9. Install tank fittings and other associated equipment.
- 10. Site cleanup and removal of temporary erosion/sedimentation BMP controls. (0.15 Acres)



Attachment D: **Temporary Best Management Practices and Measures**

- 1. There is approximately 0.0 AC of storm water that originate up gradient from the site and flow across the site through an onsite BMP.
- 2. Temporary BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property and limits of construction to prevent silt from escaping the construction area during permanent BMP construction.
- 3. A concrete washout pit may be used to collect all excess concrete during construction, if needed.
- 4. Temporary BMPs for this project will protect surface water or groundwater from turbid water, phosphorus, sediment, oil and other contaminants, which may mobilize in stormwater flows by slowing the flow of runoff to allow sediment and suspended solids to settle out of the runoff.
- 5. Practices may also be implemented on site for interim and permanent stabilization. Stabilization practices may include but are not limited to establishment of temporary vegetation; establishment of permanent vegetation; mulching; geotextiles; sod stabilization; vegetative buffer strips; protection of existing trees and vegetation; and other similar measures.
- 6. There are no sensitive features or surface streams within the boundaries of the project that would require temporary BMPs. The temporary onsite BMPs will be used to treat stormwater runoff before it leaves the project and prevent pollutants from entering into surface streams or any sensitive features down gradient of the site.



Attachment E: Request to Temporarily Seal a Feature (NOT APPLICABLE)



Attachment F: Structural Practices

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets. A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck washout pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all structural temporary BMPs are shown within the Site Plans.

Description of Temporary BMPs

Fiber Roll:

The purpose of a fiber roll is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Fiber rolls are used during the period of construction near the perimeter of a disturbed area to intercept sediment, reduce flow velocity, and release runoff as sheet flow. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

Triangular Sediment Filter Dikes

Triangular sediment filter dikes (18"x18"x18" filter material with 6" square folded wire mesh frame) will be installed downgradient of the AST construction area with filter cloth placed over any existing stormwater collection drains. The dike and filter cloth will be held in place with cloth sandbags. The facility existing topography will not change as the AST will be placed on existing crushed rock.

Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:






- Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
- Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.




Attachment G: Drainage Area Map

Drainage will remain unaffected by the AST installations



- 1. THIS PROJECT IS SUBMITTED WITHOUT PHASING. 2.ALL EXISTING IMPERVIOUS COVER AND DRAINAGE PATTERNS WILL REMAIN UNCHANGED POST-DEVELOPMENT.
- 3.CONTRACTOR TO CUT AND REMOVE CONCRETE AS NECESSARY TO REMOVE ALL EXISTING PIPING. REFER TO PLANS BY OTHERS FOR EXACT LOCATION OF DISPENSERS AND PIPING.
- 4.ALL REQUIRED NOTICES AND PERMITS MUST BE PLACED IN A HIGHLY VISIBLE LOCATION ONSITE BEFORE THE COMMENCEMENT OF CONSTRUCTION.
- 5.ALL EROSION AND SEDIMENTATION CONTROLS (ESC) MUST BE INSTALLED PRIOR TO ANY DISTURBANCE TO THE PROJECT SITE.
- 6.ALL ESC USED ONSITE MUST BE REGULARLY MONITORED AND MAINTAINED AS NEEDED.
- 7.THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING ONTO THE PUBLIC ROADWAY ON AN ONGOING/REGULAR BASIS. MUD AND OR DIRT TRACKÉD INTO THE ROADWAY MUST BE IMMEDIATELY REMOVED UPON DISCOVERY.
- 8.INLET PROTECTION SHALL BE INSTALLED IMMEDIATELY UPON INLET INSTALLATION.
- 9.INITIATE TEMPORARY STABILIZATION WHEN CONSTRUCTION CEASES IN A DISTURBED AREA FOR 14 DAYS.
- 10. INITIATE PERMANENT STABILIZATION IMMEDIATELY ONCE WORK HAS CEASED AND FINAL GRADE HAS BEEN ACHIEVED.
- 11. ALL DISTURBED/BARE AREAS WILL REQUIRE PERMANENT STABILIZATION BEFORE FINAL ACCEPTANCE CAN BE ACHIEVED. AVOID DISTURBING AREAS OF THE PROJECT THAT ARE NOT NECESSARY FOR CONSTRUCTION.
- 12. TEMPORARY ESC'S SHALL REMAIN IN PLACE IN ALL DISTURBED AREAS UNTIL ADEQUATE STABILIZATION HAS BEEN ACHIEVED.
- 13. THE TECHNICAL SPECS OF ESC DEVICES AND BEST MANAGEMENT PRACTICES (BMP) MEET OR EXCEED THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL.




LEGEND

PROPOSED PROPERTY/ PROJECT BOUNDARY LINE EXISTING R.O.W./PROPERTY LINE EXISTING EASEMENT LINE PROPOSED CURB & GUTTER —LOC—LOC—LOC— LIMITS OF CONSTRUCTION .00000000 FIBER ROLL (MULCH) STAGING & TEMPORARY SPOILS AREA STABILIZED CONSTRUCTION **ENTRANCE**



CONCRETE WASHOUT

NOTE: ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.




DRAINAGE AREA BOUNDARY

DRAINAGE AREA DESIGNATION AND AREA DRAINED



FLOW ARROW



IF DRAWING BAR DOES NOT MEASURE 2" THIS PRINT IS NOT TO SCALE

EROSION CONTROL AND DRAINAGE PLAN

SHEET 7 OF 9

P.E.C. OAK HILL EAPP

EXCELL FUELING SYSTEMS

SANDLIN

TBPELS FIRM #21356 4501 WHISPERING VALLEY DRIVE #2: AUSTIN, TX 78727



Attachment H: Temporary Sediment Pond(s) Plans and Calculations (NOT APPLICABLE)



Attachment I: Inspection and Maintenance for BMPs

Inspection and Maintenance Guidelines for Construction BMPs

Fiber Rolls – Section 1.4.14

- (1) Inspect and verify that activity based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly to verify continued BMP implementation.
- (2) Inspect BMPs subject to non-stormwater discharges daily while non-stormwater discharges occur.
- (3) Unit-specific maintenance requirements are included with the description of each technology.
- (4) Sediment removed during the maintenance of a dewatering device may be either spread onsite and stabilized or disposed of at a disposal site.
- (5) Sediment that is commingled with other pollutants must be disposed of in accordance with all applicable laws and regulations.

Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

Inspection Schedule

The primary operator is required to choose one of the two inspections listed below.

☐ Option 1: Once every seven calendar days. If this alternative schedule is developed, then the
inspection must occur regardless of whether or not there has been a rainfall event since the previous
inspection.

□ Option 2: Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).



If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded.

Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized
- areas used for storage of materials that are exposed to precipitation
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system)
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly), and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking)

Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g., site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

Inspection Report Forms

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are



modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.



Corrective Action

Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

Corrective Action Forms

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.



Inspector Qualifications Log*

Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
☐ Training Course
☐ Supervised Experience
□ Other
Inspector Name: Overlife actions (Check as a propriets and provide description):
Qualifications (Check as appropriate and provide description):
Training Course
Supervised Experience
□ Other
Inspector Name:
Inspector Name:
☐ Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
Training Course
□ Supervised Experience
□ Other



*The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.



Amendment Log

No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

Construction Activity Sequence Log*

Name of Operator	Projected Dates Month/Year	Activity Disturbing Soil clearing, excavation, etc.	Location on-site where activity will be conducted	Acreage being disturbed

^{*}Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.

Stormwater Control Installation and Removal Log

Stormwater Control	Location On-Site	Installation Date	Removal Date

Stabilization Activities Log*

Date Activity Initiated	Description of Activity	Description of Stabilization Measure and Location	Date Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures Initiated

^{*}Stabilization and erosion control practices may include, but are not limited to, establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.

Inspection Frequency Log

Date	Frequency



Rain Gauge Log

Date	Location of Rain Gauge	Gauge Reading

General Information					
Name of Project		Tracking Number		Inspection Date	
Inspector Name, Title & Contact				·	
Information					
Present Phase of Construction					
Inspection Location (if multiple					
inspections are required, specify location					
where this inspection is being conducted)					
Inspection Frequency					
Standard Frequency: Week	kly □Every 14 days and within 2	24 hours of a 0.25" rain			
	ry 7 days and within 24 hours of a	0.25" rain			
Reduced Frequency:					
☐ Once per month (for s	stabilized areas)				
☐ Once per month and v	within 24 hours of a 0.25" rain (for	arid, semi-arid, or drou	ght-stricken areas during	seasonally dry periods or during	
drought)	`		5	, , ,	
~ ·	frozen conditions where earth-dist	urbing activities are bein	g conducted)		
Was this inspection triggered by a 0.25"		0	0 /		
If yes, how did you determine whether a		?			
	er station representative of site. Spe		rce		
Rain gauge on site	of station representative of site. Spo	cerry weather station sou	rcc.		
Total rainfall amount that trigge	ered the inspection (in inches):				
Unsafe Conditions for Inspection					
Did you determine that any port	tion of your site was unsafe for	inspection? ☐ Yes	\square No		
If "yes," complete the following: O Describe the conditions that prevented you from conducting the inspection in this location:					
Location(s) where conditions were found:					



	Condition and Effectiveness of Erosion and Sediment (E&S) Controls					
Type / Location of E&S Control	Repairs or Other Maintenance Needed?	Corrective Action Required?	Date on Which Maintenance of Corrective Action First Identified?	Notes		
1.	□ Yes □ No	□ Yes □ No				
2.	□ Yes □ No	□ Yes □ No				
3.	□ Yes □ No	□ Yes □ No				
4.	□ Yes □ No	□ Yes □ No				
5.	□ Yes □ No	□ Yes □ No				
6.	□ Yes □ No	□ Yes □ No				
7.	□ Yes □ No	□ Yes □ No				
8.	□ Yes □ No	□ Yes □ No				
9.	□ Yes □ No	□ Yes □ No				



Condition and Effectiveness of Pollution Prevention (P2) Practices				
Type / Location of P ₂ Practices	Repairs or Other Maintenance Needed?	Corrective Action Required?	Identification Date	Notes
1.	□ Yes □ No	□ Yes □ No		
2.	□ Yes □ No	□ Yes □ No		
3.	□ Yes □ No	□ Yes □ No		
4.	□ Yes □ No	□ Yes □ No		
5.	□ Yes □ No	□ Yes □ No		
6.	□ Yes □ No	□ Yes □ No		
7.	□ Yes □ No	□ Yes □ No		
8.	□ Yes □ No	□ Yes □ No		
9.	□ Yes □ No	□ Yes □ No		



Stabilization of Exposed Soil					
Stabilization Area	Stabilization Method	Have you Initiated Stabilization?	Notes		
1.		□ YES □ NO			
		If yes, provide date:			
2.		□ YES □ NO			
		If yes, provide date:			
3.		□ YES □ NO			
		If yes, provide date:			
4.		□ YES □ NO			
		If yes, provide date:			
	Description	of Discharges			
If "YES," provide the fol	arge or other discharge occurring from any part of your lowing information for each point of discharge:	our site at the time of the inspection? \Box	YES □ NO		
Discharge Locations	Observations				
1.	Describe the discharge:				
	At asints of discharge and the changes and house of surface maters in the immediate visitity are those and the changes and the changes and the changes and the changes are the control of the changes and the changes are the				
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and /				
	or sediment accumulation that can be attributed to your discharge? YES. NO If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance,				
	or corrective action is needed to resolve the issue:				
2.	Describe the discharge:				
	A		1		
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and /				
	or sediment accumulation that can be attributed to your discharge? YES. NO				
	If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:				
3.	Describe the discharge:				
	8				
	At points of discharge and the channels and banks of	surface waters in the immediate vicinity, are t	there any visible signs of erosion and /		
	or sediment accumulation that can be attributed to you				
	If yes, describe what you see, specify the location(s) who	here these conditions were found, and indica	te whether modification, maintenance,		
	or corrective action is needed to resolve the issue:				



Contractor or Subcontractor Certification and Signature			
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."			
Signature of Contractor or Subcontractor: Date:			
Printed Name and Affiliation:			
Certification and Signature by Permittee			
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations." Signature of Permittee or "Duly Authorized Representative":			
Printed Name and Affiliation:			



Section A – Initial Report				
(Complete this section within 24 hours of discovering the condition that triggered corrective action.)				
Name of Project:		Tracking Nu	ımber:	Today's Date
Date Problem First Discovered:			m First Discovered:	
Name of Individual Completing this Form:	.•	Contact Info	ormation:	
What site conditions triggered the requirement to conduct corrective ac				
☐ A required stormwater control was never installed, was installed inco		_		
☐ The stormwater controls that have been installed and maintained are	e not effective enough	n for the discharge to mee	t applicable water qual	ity standards
☐ A prohibited discharge has occurred or is occurring				
D 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1				
Provide a description of the problem:				
Deadline for completing corrective action (Enter date that is either: (1)	no more than 7 calen	dar days after the date you	discovered the proble	om or (2) if it is infeasible to complete work
within the first 7 days, enter the date that is as soon as practicable follow		dar days after the date you	discovered the proble	em, or (2) if it is inteasible to complete work
within the first / days, effect the date that is as soon as praedeaste follow	ving the / day).			
If your estimated date of completion falls after the 7-day deadline, expla	in (1) why you believ	e it is infeasible to comple	te work within 7 days,	and (2) why the date you have established
for making the new or modified stormwater control operational is the se			, ,	,
		- Corrective Action Pr		
(Complete this section no late	er than 7 calendar d	lays after discovering th	e condition that trig	gered corrective action.)
Section B.1 – Why the Problem Occurred				
Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Determined and the Date You Determined the Cause		
1.		1.		
2.		2.		
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem				
			137	
List of Stormwater control Modification(s) Needed to Correct Problem (Add an additional sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes	
1.				
1.		☐ Yes ☐ No		
		Date:		
2.		☐ Yes ☐ No		
		Date:		



Section A – Initial Report (Complete this section within 24 hours of discovering the condition that triggered corrective action.)				
Name of Project:		Tracking Nu		Today's Date
Date Problem First Discovered:		Time Proble	m First Discovered:	1
Name of Individual Completing this Form:		Contact Info	ormation:	
What site conditions triggered the requirement to conduct corrective act	tion:			
☐ A required stormwater control was never installed, was installed income	rrectly, or not in acco	ordance with the requireme	ents in Part 2 and/or	Part 3
☐ The stormwater controls that have been installed and maintained are	not effective enough	for the discharge to meet	applicable water qual	ity standards
☐ A prohibited discharge has occurred or is occurring				
Provide a description of the problem: Deadline for completing corrective action (Enter date that is either: (1) no more than 7 calendar days after the date you discovered the problem, or (2) if it is infeasible to complete work within the first 7 days, enter the date that is as soon as practicable following the 7th day): If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe: Section B – Corrective Action Progress (Complete this section no later than 7 calendar days after discovering the condition that triggered corrective action.)				
Section B.1 – Why the Problem Occurred				
Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Determined and the Date You Determined the Cause		
1.		1.		
2.		2.		
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem				
List of Stormwater control Modification(s) Needed to Correct	Completion Date	SWPPP Update	Notes	
Problem (Add an additional sheet if necessary)		Necessary?		
1.		☐ Yes ☐ No Date:		
2.		☐ Yes ☐ No		
		Date:		



Contractor or Subcontractor Certification and Signature			
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."			
Signature of Contractor or Subcontractor:	Date:		
Printed Name and Affiliation:			
Certification and Signature by Permittee			
"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information, submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am, aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."			
Signature of Permittee or "Duly Authorized Representative":	Date:		
Printed Name and Affiliation:			



Attachment J: Schedule of Interim and Permanent Soil Stabilization Practices

Interim V egetative Stabilization

Interim soil stabilization will not be required.

Permanent Vegetative Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project, the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- 1. The dates when major grading activities occur,
- 2. The dates when construction activities temporarily or permanently cease on a portion of the site, and
- 3. The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.



Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.



Copy of Notice of Intent (NOI)



Agent Authorization Form (TCEQ-0599)

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I Bud Collora	
	Print Name
PEC Project Manager	
	Title Overser/Dressident/Others
	Title - Owner/President/Other
ofPedernal	es Electric Cooperative, Inc. (PEC)
	Corporation/Partnership/Entity Name
have authorized	Nick Sandlin, P.E.
	Print Name of Agent/Engineer
of	Sandlin Services, LLC
	Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:	
Applicant's Signature	Bal alla
Date:	<u>June 19, 2023</u>
THE STATE OF lexas §	
County of Planco §	
to me to be the person whose name that (s)he executed same for the pu	nority, on this day personally appeared But Collora known is subscribed to the foregoing instrument and acknowledged to me urpose and consideration therein expressed. office on this Aday of June 2003.
GIVEN under my hand and seal of o	office on this C day of Jone 2005.
· ·	Hanse Caballage
RENEE OELSCHLEGER Notary Public, State of Texas Notary ID# 1159996-9 My Commission Expires	Typed or Printed Name of Notary
MARCH 4, 2024	MY COMMISSION EXPIRES: March 4, 2024



Application Fee Form (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality Name of Proposed Regulated Entity: PEC Oak Hill Regulated Entity Location: 9115 Circle Drive, Austin, TX 78736 Name of Customer: Pedernales Electric Cooperative, Inc. Phone: 830-868-6056 Contact Person: Bud Collora Customer Reference Number (if issued):CN 601327927 Regulated Entity Reference Number (if issued):RN 104895438 **Austin Regional Office (3373)** Travis Hays Williamson San Antonio Regional Office (3362) Medina Uvalde Bexar Comal Kinney Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: Austin Regional Office San Antonio Regional Office Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier **Revenues Section** 12100 Park 35 Circle Mail Code 214 Building A, 3rd Floor P.O. Box 13088 Austin, TX 78753 Austin, TX 78711-3088 (512)239-0357 Site Location (Check All That Apply): Contributing Zone **Transition Zone** Recharge Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	21.636 Acres	\$ 6,500
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	2 Tanks	\$ 1,300
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature _

Date: <u>6/15/2023</u>

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6 <i>,</i> 500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	< 1	\$3,000
institutional, multi-family residential, schools, and	1 < 5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



Check Payable to the "Texas Commission on Environmental Quality"



Core Data Form (TCEQ-10400)

TCEQ Use Only



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (*If other is checked please describe in space provided.*)

New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)

Renewal (Core Data Form should be submitted with the renewal form)					Other						
2. Customer Reference Num	_	ollow this link or CN or RN n			3. Regulated Entity Reference Nur			Number (if i	ssued)		
CN 601327927	100	Central Reg			RN 1	RN 104895438					
SECTION II: Cu											
4. General Customer Information 5. Effective Date for Customer Information						mation l	Update	es (mm/dd/)	ууу)		
New Customer ☑ Update to Customer Information ☐ Change in Regulated Entity Ownership ☐ Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)											
	The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).										
6. Customer Legal Name (If o	an individual, print la	ıst name first:	eg: Doe, Joh	n)			<u>If nev</u>	v Customer, e	enter pre	evious Custom	er below:
PEDERNALES ELECTRIC COOPER	ATIVE, INC										
7. TX SOS/CPA Filing Number	er 8.	TX State Ta	x ID (11 digi	ts)						10. DUNS	Number (if
0007336401	7408284127					(9 digits)					
11. Type of Customer:					[Individ	ual Partnership: General Limited			eral 🔲 Limited	
Government: City County	y 🗌 Federal 🗌 Loca	al 🗌 State 🗀	Other			☐ Sole Pr	Proprietorship				
12. Number of Employees							13. Independently Owned and Operated?				
☐ 0-20 ☐ 21-100 ☑ 101-250 ☐ 251-500 ☐ 501 and higher						⊠ Yes □ No					
14. Customer Role (Proposed	or Actual) – as it rel	ates to the Re	gulated Enti	ty liste	d on ti	his form. F	Please (check one of	the follo	wing	
□ Owner □ Operator □ Owner & Operator □ Occupational Licensee □ Responsible Party □ VCP/BSA Applicant						Other:					
P.O. BOX 1 15. Mailing											
Address:											
City John	State	TX		ZIP	ZIP 78636			ZIP + 4			
16. Country Mailing Information (if outside USA)				17. E	7. E-Mail Address (if applicable)						
18. Telephone Number 19. Extens				or Co	de	de 20. Fax Number (if applicable)					

TCEQ-10400 (11/22) Page 1 of 3

SECTION III:	Regula	ted Ent	ity 1	<u>Inform</u>	ation						
21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)											
☐ New Regulated Entity ☐ Update to Regulated Entity Name ☐ Update to Regulated Entity Information											
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).											
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)											
PEC Oak Hill											
23. Street Address of the Regulated Entity:	9115 CIRCLE DR										
(No PO Boxes)		T						1			T
(NOTO BOXES)	City	AUSTIN	S	itate	TX	ZIP	•	78736	736 ZIP + 4		7911
24. County	TRAVIS										
		If no Stre	et Addr	ess is provid	ed, fields 2	5-28	are red	quired.			
25. Description to											
Physical Location:											
26. Nearest City	26. Nearest City State Nearest ZIP Code										rest ZIP Code
Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).											
27. Latitude (N) In Decima	al:	30.237618			28. Lo	ongit	ude (W	/) In Deci	imal:	-77.91786	58
Degrees	Minutes		Second	S	Degre	Degrees			Minutes		Seconds
30	:	14		15.4248		77		55		4.3242	
29. Primary SIC Code	30.	Secondary SIC	Code		31. Primar		ICS Co	de	32. Seco	ndary NAIC	S Code
(4 digits)	(4 digits) (5 or 6 digits) (5 or 6 digits)										
4911					221122						
33. What is the Primary B	Business of t	his entity? (D	o not rep	peat the SIC or	NAICS descri	iption	.)		<u> </u>		
PEC operations center											
	P.O. Box 1										
34. Mailing											
Address:	City	Johnson City		State	тх	:	ZIP	78636		ZIP + 4	
35. E-Mail Address:		1				ı		1			1
36. Telephone Number			37. Ex	xtension or C	Code		38. Fa	ax Numb	er (if applicat	ole)	
() -							()	-			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

Dam Safety	Districts	☑ Edwards Aquifer	Emissions Inventory Air	☐ Industrial Hazardous Waste
		11-06030101		
Municipal Solid Waste	New Source Review Air	OSSF	Petroleum Storage Tank	PWS
			93194 (pending)	
Sludge	Storm Water	☐ Title V Air	Tires	Used Oil
☐ Voluntary Cleanup	☐ Wastewater	☐ Wastewater Agriculture	☐ Water Rights	Other:
SECTION IV: Pr	eparer Inf	<u>ormation</u>		

40. Name:	Nick Sandlin, P.E. (Sandlin Services, LLC)				Principal / Professional Engineer
42. Telephone Number 43. Ext./Code 44. Fax Number			44. Fax Number	45. E-Mail A	Address
(806) 679-7303		() -	nick@sandlir	nservices.com	

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	SANDLIN SERVICES, LLC	/ PRIFESSIONAL ENGINEER			
Name (In Print):	NICK SANDLIN, P.E.	Phone:	(806) 679- 7303		
Signature:	Nine Dorr			Date:	6/15/2023

TCEQ-10400 (11/22) Page 3 of 3