Texas Commission on Environmental Quality Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with <u>30 TAC 213</u>.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity N Subdivision	ame: Riv	very Co	ommei	rcial		2. Re	egulat	ed Entity No.:	RN111699997
3. Customer Name: F	PDC WILL	IAMS	PLAZ	A LTD)	4. Ci	istom	er No.: CN606:	119360 & 606165801
5. Project Type: (Please circle/check one)	New		Mod	ificat	ion	Exter	nsion	Exception	
6. Plan Type: (Please circle/check one)	<u>WPAP</u>	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Resident	ial	<u>Non-</u>	<u>resid</u>	entia	1	8. Site (acres):		12.69 AC
9. Application Fee:	\$6,500		10. P	erma	nent	BMP	(s):	Batch Detention	n
11. SCS (Linear Ft.):	N/A		12. A Tank	ST/U (s):	ST (N	0.		N/A	
13. County:	Williams	son	14. V	Vater	shed:			San Gabriel	

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

	Austin Region					
County:	Hays	Travis	Williamson			
Original (1 req.)	_		_ <u>X</u> _			
Region (1 req.)	_		_ <u>X_</u>			
County(ies)			<u>_X</u>			
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA			
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin Cedar Park Florence _X_Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock			

	Sa	n Antonio Region			
County:	Bexar	Comal	Kinney	Medina	U
Original (1 req.)			_		
Region (1 req.)					
County(ies)			_		
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EA Uv
	Castle Hills				

County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)					
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Hollis Scheffler, P.E.

Print Name of Customer/Authorized Agent

Signature of Customer/Authorized Agent

8/22/2023 Date

Date(s)Reviewed:	Date Adr	ninistratively Complete:	
Received From:	Correct 1	Number of Copies:	
Received By:	Distribut	ion Date:	
EAPP File Number:	Complex	:	
Admin. Review(s) (No.):	No. AR F	Rounds:	
Delinquent Fees (Y/N):	Review T	'ime Spent:	
Lat./Long. Verified:	SOS Cus	tomer Verification:	
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):	
Core Data Form Complete (Y/N):	Check:	Signed (Y/N):	
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):	

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:


Print Name of Customer/Agent: Hollis Scheffler, P.E.

Date: <u>8/22/2023</u>

Signature of Customer/Agent:

Project Information

- 1. Regulated Entity Name: <u>Rivery Commercial Subdivision</u>
- 2. County: Williamson
- 3. Stream Basin: San Gabriel River
- 4. Groundwater Conservation District (If applicable): N/A
- 5. Edwards Aquifer Zone:



6. Plan Type:

WPAP	AST
SCS	UST
Modification	Exception Request

7. Customer (Applicant):

Contact Person: Julie Ward Entity: PDC WILLIAMS PLAZA LTD Mailing Address: 1313 Williams Drive City, State: Georgetown, TX Zip: 78628 Telephone: 713-822-1758 FAX: N/A Email Address: julie.ward@partnersrealestate.com

8. Agent/Representative (If any):

Contact Person: Hollis Scheffler, P.E.Entity: Westwood Professional ServicesMailing Address: 8701 N. Mopac Expw., Ste. 320City, State: Austin, TXZip: 78759Telephone: 512-485-0831FAX: N/AEmail Address: hollis.scheffler@westwoodps.com

9. Project Location:

The project site is located inside the city limits of <u>Georgetown</u>.

The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.

- The project site is not located within any city's limits or ETJ.
- 10. The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

The property is located at the NE corner of Williams Drive and Rivery Boulevard

- 11. Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
- 12. Attachment B USGS / Edwards Recharge Zone Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:

 \boxtimes Project site boundaries.

USGS Quadrangle Name(s).

Boundaries of the Recharge Zone (and Transition Zone, if applicable).

] Drainage path from the project site to the boundary of the Recharge Zone.

- 13. The TCEQ must be able to inspect the project site or the application will be returned. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.
 - Survey staking will be completed by this date: 1/1/2023

- 14. Attachment C Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
 - Area of the site
 Offsite areas
 Impervious cover
 Permanent BMP(s)
 Proposed site use
 Site history
 Previous development
 - \boxtimes Area(s) to be demolished
- 15. Existing project site conditions are noted below:
 - Existing commercial site
 Existing industrial site
 Existing residential site
 Existing paved and/or unpaved roads
 Undeveloped (Cleared)
 Undeveloped (Undisturbed/Uncleared)
 Other: _____

Prohibited Activities

- 16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
 - (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
 - (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
 - (4) The use of sewage holding tanks as parts of organized collection systems; and
 - (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
 - (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.
- 17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
 - (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

- 18. The fee for the plan(s) is based on:
 - For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
 - For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
 - For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
 - A request for an exception to any substantive portion of the regulations related to the protection of water quality.
 - A request for an extension to a previously approved plan.
- 19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:


 Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
 San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

- 20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

Attachment A – Road Map



Attachment B – USGS / Edwards Recharge Zone Map



RIVERY COMMERCIAL SUBDIVISION

Attachment C – Project Description

The Novak GISD Multifamily portion of the Rivery Commercial Subdivision will include the development of a multifamily building with associated drive aisles, parking, and utilities. The total impervious cover on the Novak GISD property is 4.64 acres and are to be treated by the existing batch detention pond. The proposed site is located at 1201, 1205, and 1301 Williams Drive and 1900 Rivery Boulevard in Georgetown, Texas 78628 in the General Commercial Jurisdiction. The existing site consists of some existing pavement pads and some Class D soil classification. According to FEMA Map 48491C0293F (Dated 12/20/2019), the subject site does not fall within a regulatory floodplain. The entire site consists of 12.69 acres with 5.669 acres being developed with this WPAP modification.

The site generally slopes at $\pm 0.5\%$ from the northwest of the site to the southeast. The adjacent properties include medical offices to the north, east and south of the site, residences to the northeast, as well as commercial businesses to the west.

As included in our demolition plans, we will first be removing the existing fences throughout the property in order to have the space open for construction. The existing concrete and asphalt pavement throughout the site will be demolished for the design of the new proposed buildings.



Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: <u>Russell C Ford</u>

Telephone: 512 442-1122

Date: 3/27/18

Fax:

AST

UST

Representing: <u>Terracon Consultants, Inc.</u> (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:

Regulated Entity Name: Former McCoy Elementary School Tract, Williams Drive, Georgetown, Texas

Project Information

- 1. Date(s) Geologic Assessment was performed: 3/19/18
- 2. Type of Project:

\times	WPAP
	SCS

3. Location of Project:



- Transition Zone
- Contributing Zone within the Transition Zone



TCEQ-0585 (Rev.02-11-15)

- 4. X Attachment A Geologic Assessment Table. Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
- Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Soil Name	Group*	Thickness(feet)
GsB	D	0-3
	. 6	

Table 1 - Soil Units, InfiltrationCharacteristics and Thickness

- * Soil Group Definitions (Abbreviated)
 - A. Soils having a high infiltration rate when thoroughly wetted.
 - B. Soils having a moderate infiltration rate when thoroughly wetted.
 - C. Soils having a slow infiltration rate when thoroughly wetted.
 - D. Soils having a very slow infiltration rate when thoroughly wetted.
- 6. Attachment B Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
- 7. X Attachment C Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
- 8. X Attachment D Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale: $1" = _'$ Site Geologic Map Scale: $1" = \underline{100}'$ Site Soils Map Scale (if more than 1 soil type): $1" = _$

9. Method of collecting positional data:

Global Positioning System (GPS) technology.

Other method(s). Please describe method of data collection:

- 10. 🕅 The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
- 11. 🔀 Surface geologic units are shown and labeled on the Site Geologic Map.

- 12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
 - Geologic or manmade features were not discovered on the project site during the field investigation.
- 13. 🔀 The Recharge Zone boundary is shown and labeled, if appropriate.
- 14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
 - There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
 - The wells are not in use and have been properly abandoned.
 - The wells are not in use and will be properly abandoned.
 - The wells are in use and comply with 16 TAC Chapter 76.
 - $\overline{\mathbf{X}}$ There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

28 3 4 5 5 6 7 6 6 7 6 7 7 200 Toewnick Term Teema	4 5 5 5 7 8A 8B 10 11 Ensence (FEE) ORE ORE NELINE NELINE NELINE Content Y Z 10 NELINE NELINE NELINE Content Exercise Y Z 10 NELINE NELINE NELINE NELINE Content Y Z 10 NELINE NELINE NELINE NELINE Content N N Z 10 Z Z Z Z Z M None, exposed bedrock Contrast contracted clayrics, leaves, sticks, dark colors Z Z Z M None, exposed bedrock Costrast contracted clayrics, leaves, sticks, dark colors Z Z Z M None, exposed bedrock Costrast contracted clayrics, leaves, sticks, dark colors Z Z Z M None, exposed bedrock Costrast contracted clayrich sediment, soil profile, gray or red colors Z Z Z M None, exposed bedrock Costrast contracted clayrich sediment, soil profile, gray or red colors Z Z Z M None, exposed bedrock Costrast contracted clayrich sediment, soil profile, gray or red colors Z	+ 5 Av 6 7 0A 88 10 11 ENSINGE Time Time Description Time Description Time Description ENSINGE Time Time Time Time Time Time Time TV Z 10 Time Time Time Time Time TV Z 10 Time Time Time Time Time TV Z 10 Time Time Time Time None, exposed Mail Time Time Time Time A INFILLING None, exposed bedrock Correst Time Time Time A NFILLING None, exposed bedrock Correst Time Time Time A None, exposed bedrock Correst Time Time Time A None, exposed bedrock None, exposed bedrock Time Time Time A None, exposed bedrock Locase or soft mud or soil, organics, leaves, sticks, dark colors Time Time Y V Vegetation. Give details in narrative description File Time Time Y Othor materials Time Time		+					chool 1 ract,	Willian EVAL	Williams Drive, G EVALUATION	PROJECT NAME: Former McCoy Elementary School Tract, Williams Drive, Georgetown, Texas CS EVALUATION PHYSICAL SE	Texas VL SETTING
Froewnork Diversions Tension Tension Tension Tension Contraction r <t< td=""><td>In the second se</td><td>Construction A BAN A BAN A BAN A Cares A 1.6 A 1.6</td><td>FORMATION</td><td></td><td></td><td></td><td>7</td><td>8A</td><td>88</td><td></td><td>10</td><td>1</td><td></td></t<>	In the second se	Construction A BAN A BAN A BAN A Cares A 1.6 A 1.6	FORMATION				7	8A	88		10	1	
x y z to to 40 24 c45 245 x y z y z y z y z x y z y z y z z z z x y	x y z In	x y z 10 a0 216 216 216 2B POINTS A INFILLING a1	⊢			NOVEL			RELATIVE INFLTRATION RATE		SENSITIVITY	CATCHM ENT AREA (ACRES)	Торозични
2B POINTS A INFILLING 2D POINTS A INFILLING 30 N None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 21 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 22 V Vegetation. Give details in narrative description 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F ToPOGRAPHY 30 Cliff, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 Cliff, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 Cliff, Hiltop, Hillside, Drainage, Floodplain, Streambed	ZB POINTS A INFILLING ZB POINTS BA INFILLING 30 None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - conpacted clay-rich sediment, soil profile, grav or red colors 21 V vegetation. Give details in narrative description 22 V vegetation. Give details in narrative description 23 F Flowstome, cements, cave deposits 20 C tother materials 21 Other materials 22 Cliff. Hilltop, Hillistide, Drainage, Floodplain, Streambed 23 Liff. Hilltop, Hillistide, Drainage, Floodplain, Streambed 24 Cliff. Hilltop, Hillistide, Drainage, Floodplain, Streambed 25 Cliff. Hilltop, Hillistide, Drainage, Floodplain, Streambed 26 Clif	2B POINTS BA INFILLING 2B POINTS BA INFILLING 2D None, exposed bedrock 2D C coarse - cobbles, breakdown, sand, gravel 2D D Loose or soft mud or soil, organics, leaves, stick, dark colors 2D V Vegetation. Give details in narrative description 2D V Vegetation. Give details in narrative description 2D Z Other materials 2D Z Context materials 2D Z C CopoGRAPH-V 2D Z Z C 2D Z Z C 2D Z Z Z </td <td></td> <td>┝</td> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>		┝	10								
2B POINTS 8A INFILLING 2B POINTS 8A INFILLING 20 N None, exposed bedrock 20 C Coarse - cobbles, breakdown, sand, gravel 20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colons 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 21 1 22 1 23 1 20 1 20 2 21 1 22 1 23 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20 1 20	ZB POINTS At INFILLING 20 Nonre, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C bose or soft mud or soil, organics, leaves, sticks, dark colors 20 V vegetation. Give details in narrative description 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 F Fines, compacted clay-rich sediment, scave deposits 20 I trave follower, cernents, cave deposits 20 C Other materials 20 I trave follower, tantal Resource Conservation Commission's Instructions to Geologists. The total due complies with that document and is a true representation of the conditions observed in the field.	2B POINTS 2A INFILLING 2B A INFILLING 30 N none, exposed bedrock 20 C coarse - cobles, breakdown, sand, gravel 20 Loose or soft mud or soil, organics, leaves, sticks, dark colors 21 V vegetation. Give details in narrative description 22 V vegetation. Give details in narrative description 23 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 24 V vegetation. Give details in narrative description 25 F Iowstone, cernents, cave deposits 26 Z Other materials 27 Other materials 28 Z other materials 29 Z iff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 20 C iff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 20 C iff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 20 C iff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 21 C iff. Hilltop, Hilliside, Drainage, Floodplain, Streambed											
2B POINTS RA INFILLING 20 N none, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 V Vegetation. Give details in narrative description 30 FS Flowstone, cernents, cave deposits 31 FS Flowstone, cernents, cave deposits 32 Intron, Hilliside, Drainage, Floodplain, Streambed 32 Cliff, Hillton, Hilliside, Drainage, Floodplain, Streambed	2B POINTS 8A INFILLING 2B POINTS 8A INFILLING 30 N None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 E Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 FS Flowstone, cements, cave deposits 31 X 32 Other materials 33 I2 TOPOGRAPHY 34 Ciff, Hilltop, Hillislide, Drainage, Floodplain, Streambed 35 Ciff, Hilltop, Hillislide, Drainage, Floodplain, Streambed 36 have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The other complies with that document and is a true representation of the conditions observed in the field.	2B POINTS 8A INFILLING 30 N None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soli, organics, leaves, sticks, dark colors 20 C coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soli, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soli profile, gray or red colors 21 V Vegetation. Give details in narrative description 32 FS Flowstone, carnents, cave deposits 33 FS Flowstone, carnents, cave deposits 20 Z 21 Other materials 22 I.2 TOPOGRAPHY 33 FS Flowstone, carnents, cave deposits 24 X 25 Cliff, Hillton, Hilliside, Drainage, Floodplain, Streambed 30 I.2 TOPOGRAPHY 31 I.2 TOPOGRAPHY 32 Cliff, Hillton, Hilliside, Drainage, Floodplain, Streambed 32 Cliff, Hillton, Hilliside, Drainage, Floodplain, Streambed 33 Liff, Hillton, Hillton, Hillton, Hilliside, Drainage, Floodplain, Streambed 34 <td></td> <td></td> <td>+</td> <td>_</td> <td>_</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>			+	_	_						
2B POINTS 8A INFILLING 30 N None, exposed bedrock 20 C Coarse - cobbles, breakdown, sand, gravel 20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 1 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 31 FS Flowstone, cements, cave deposits 32 X Other materials 33 X Other materials 30 I:12 TOPOGRAPHY I:12 TOPOGRAPHY 30 I:12 Hillton, Hilliside, Drainage, Floodplain, Streambed 30 I:18 Hillton, Hilliside, Drainage, Floodplain, Streambed	2B POINTS 8A INFILLING 30 N None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C Coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 C Coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 21 V Vegetation. Give details in narrative description 22 Y Vegetation. Give details in narrative description 23 F F inex, compacted clay-rich sediment, soil profile, gray or red colors 24 V Vegetation. Give details in narrative description 25 F F inex, profiles, prainage, Floodplain, Streambed 20 Ciff, Hilltop, Hillislide, Drainage, Floodplain, Streambed Inthe followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The hild have followed the Texas Natural Resource Conservation of the conditions observed in the field.	2B POINTS BA INFILLING 30 N None, exposed bedrock 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 C coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soli, organics, leaves, sticks, dark colors 20 D Loose or soft mud or soli, organics, leaves, sticks, dark colors 20 V Vegetation. Give details in narrative description 30 FS 21 V Vegetation. Give details in narrative description 30 FS 21 Z 22 X 23 X 24 Cother materials 25 II TOPOGRAPHY 30 II TOPOGRAPHY 31 X 32 Ciff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 32 III TOPOGRAPHY 33 III TOPOGRAPHY 34 Ciff. Hilltop, Hilliside, Drainage, Floodplain, Streambed 33 III Topodet the Jexas Natural Resource Conservation Commission's Instructions to Geologists. The strood, and I have followed the Jexas Natural Resource Conservation Commission's Instructions to Geologists. The steat ti an quantified as a geologist as defined by 30 TAC 213											
 None, exposed bedrock C Coarse - cobbles, breakdown, sand, gravel C Coarse - cobbles, breakdown, sand, gravel C Coarse - cobbles, breakdown, sand, gravel D Loose or soft mud or soil, organics, leaves, sticks, dark colors F Fines, compacted clay-rich sediment, soil profile, gray or red colors V Vegetation. Give details in narrative description F Fines, compacted clay-rich sediment, soil profile, gray or red colors V Vegetation. Give details in narrative description F Fines, compacted clay-rich sediment, soil profile, gray or red colors V Vegetation. Give details in narrative description S (12 TOPOGRAPHY Cliff, Hiltop, Hillslide, Drainage, Floodplain, Streambed I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The 	30 N None, exposed bedrock 20 C Coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 P Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 I.2 TOPOGRAPHY I.2 TOPOGRAPHY 30 Ciff, Hilltop, Hillslide, Drainage, Floodplain, Streambed I.atve followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The teretore with that document and is a true representation of the conditions observed in the field.	30 N None, exposed bedrock 20 C Coarse - cobbles, breakdown, sand, gravel 20 C Loose or soft mud or sol, organics, leaves, sticks, dark colors 20 D Loose or soft mud or sol, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 V Vegetation. Give deteals in narrative description 30 FS Flowstone, cements, cave deposits 30 FS Flowstone, cements, cave deposits 30 FS Flowstone, cements, cave deposits 30 X Other materials 30 X Other materials 31 12 TOPOGRAPHY 32 12 TOPOGRAPHY 33 12 TOPOGRAPHY 30 12 TOPOGRAPHY 30 12 TOPOGRAPHY 30 12 TOPOGRAPHY 30 12 TOPOGRAPHY 31 12 TOPOGRAPHY 32 12 TOPOGRAPHY 33 12 TOPOGRAPHY 34 Instruction to the conditions observed in the field.		A INFILLING									
20 C Coarse - coblets, breakdown, sand, gravel 20 D Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 K V vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 30 X Other materials 31 12 TOPOGRAPHY Iteration 32 Cliff, Hilltop, Lillislde, Drainage, Floodplain, Streambed Jteratocd, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	20 C Coarse - cobbles, breakdown, sand, gravel 20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 Ciff, Hiltop, Hillslide, Drainage, Floodplain, Streambed Itake followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The hiltop that document and is a true representation of the conditions observed in the field.	20 C Coarse - cobbles, breakdown, sand, gravel 20 D Loose or soft mud or soli, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 30 FS Flowstone, cements, cave deposits 30 FS Flowstone, cements, cave deposits 30 X Other materials 30 I:2 TOPOGRAPHY 30 I:2 TOPOGRAPHY 31 I:2 Cliff, Hilliole, Drainage, Floodplain, Streambed 32 Cliff, Hillion, Hilliole, Drainage, Floodplain, Streambed 32 Cliff, Hillion, Hilliole, Drainage, Floodplain, Streambed 33 Liff, Hillion, Hilliole, Drainage, Floodplain, Streambed 34 Liff, Hillion, Hillion, Million, Streambed 35 Cliff, Hillion, Hillion, Million, Streambed 36 Es that I agree of the Texas Natural Resource Conservation of the conditions observed in the field. 36 Field here complies with that document and is a true representation of the conditions observed in the field. 37 Material			osed bec	drock							
 20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors V Vegetation. Give details in narrative description 30 K Other materials 30 12 TOPOGRAPHY 30 12 TOPOGRAPHY 12 TOPOGRAPHY and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The 	20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 I2 OpOGRAPHY 5 Other materials I2 20 Clift, Hilltop, Hilliside, Drainage, Floodplain, Streambed Introductions to Geologists. The entroduction and is a true representation of the conditions observed in the field.	20 0 Loose or soft mud or soil, organics, leaves, sticks, dark colors 20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 31 X Other materials 20 Clift, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 Clift, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 Clift, Hiltop, Hillside, Drainage, Floodplain, Streambed 31 Late complies with that document and is a true representation of the conditions observed in the field. 32 Mathed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The field the complies with that document and is a true representation of the conditions observed in the field.			cobbles,	breakd	own, sand,	gravel					
20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 12 TOPOGRAPHY 30 11 Hilltop, Hilliside, Drainage, Floodplain, Streambed 31 13 TopoGraPhY	20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 5 V Vegetation. Give details in narrative description 30 FS Flowstome, cements, cave deposits 30 FS Flowstome, cements, cave deposits 20 FS Flowstome, cements, cave deposits 20 Ciff, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 L12 TOPOGRAPHY 30 Ciff, Hiltop, Hillside, Drainage, Floodplain, Streambed 30 Inter followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The restored and it have followed the Texas Natural Resource Conservation of the conditions observed in the field.	20 F Fines, compacted clay-rich sediment, soil profile, gray or red colors 5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 K Other materials 30 X Other materials 20 12 TOPOGRAPHY 30 12 TOPOGRAPHY 30 X Other materials 20 12 TopOGRAPHY 30 12 TopOGRAPHY 31 1 Tareal resource Conservation Commission's Instructions to Geologists. The test test test test test test as a geologist as defined by 30 TAC 213 30 30 50			soft mud	or soil,	organics, lt	eaves, sti	icks, dark co	lors			
5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 12 TOPOGRAPHY 30 12 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 30 and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	5 V Vegetation. Give details in narrative description 30 FS Flowstome, cements, cave deposits 30 X Other materials 30 X Other materials 20 20 12 TOPOGRAPHY 30 12 TOPOGRAPHY Streambed 30 12 TOPOGRAPHY Streambed 30 14 hiltop, Hilliside, Drainage, Floodplain, Streambed Streambed 30 and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The stroad, and I have followed the Texas Natural Resource Conservation of the conditions observed in the field.	5 V Vegetation. Give details in narrative description 30 FS Flowstone, cements, cave deposits 30 X Other materials 20 12 TOPOGRAPHY 30 I.2 TOPOGRAPHY 20 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 30 I.2 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 30 and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The get here complies with that document and is a true representation of the conditions observed in the field. as that I am qualified as a geologist as defined by 30 TAC 213 Date Xee/field		_	npacted	clay-ric.	h sediment	, soil prof	file, gray or n	ed color	s		
 B FS Flowstone, cements, cave deposits X Other materials 12 TOPOGRAPHY Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed ad I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The 	 FS Flowstone, cements, cave deposits X Other materials I12 TOPOGRAPHY I2 TOPOGRAPHY I2 TOPOGRAPHY I12 TOPOGRAPHY	30 FS Flowstome, cements, cave deposits 30 X Other materials 20 12 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 4 texture followed the Jexas Natural Resource Conservation Commission's Instructions to Geologists. The field here complies with that document and is a true representation of the conditions observed in the field. 4 texture 1 ann qualified as a geologist as defined by 30 TAC 213 Date 3 3	5 <	Vegetatio	n. Give d	letails in	narrative c	descriptio	ç				
30 X Other materials 20 12 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed rstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	30 X Other materials 20 12 TOPOGRAPHY 30 12 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed Instructions to Geologists. The finate for the reverse Natural Resource Conservation Commission's Instructions to Geologists. The field here complies with that document and is a true representation of the conditions observed in the field.	30 X Other materials 20 12 <topography< td=""> 30 12<topography< td=""> 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 12<topography< td=""> Instructions to Geologists. The control of the conditions observed in the field. 13 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed 14 Inave followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The field here complies with that document and is a true representation of the conditions observed in the field. 15 Image: True followed the Texas Natural Resource Conservation of the conditions observed in the field. 15 Image: True followed the Texas Natural Resource Conservation of the conditions observed in the field.</topography<></topography<></topography<>			з, сетет	ts, cave	eposits						
20 5 12 TOPOGRAPHY 30 Cliff, Hillkole, Juainage, Floodplain, Streambed arstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	20 5 12 TOPOGRAPHY 30 Cliff, Hittop, Hilliside, Drainage, Floodplain, Streambed arstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The Apple here complies with that document and is a true representation of the conditions observed in the field.	20 5 12 TOPOGRAPHY 30 Cliff. Hiltrop. Hillside, Drainage, Floodplain, Streambed arstood, and I have followed the Jexas Natural Resource Conservation Commission's Instructions to Geologists. The ted here complies with that document and is a true representation of the conditions observed in the field. fies that I amountified as a declogist as defined by 30 TAC 213 Date 30 Valle			terials								
5 12 TOPOGRAPHY 30 Cliff, Hittop, Hillside, Drainage, Floodplain, Streambed erstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	5 12 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed erstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	5 12 TOPOGRAPHY 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed arstood, and I have followed the Jexas Natural Resource Conservation Commission's Instructions to Geologists. The ted here complies with that document and is a true representation of the conditions observed in the field. fies that I amqualified as a geologist as defined by 30 TAC 213 Date 3/21/6	20				2			_			
30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed Jerstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed lerstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The typed here complies with that document and is a true representation of the conditions observed in the field.	20 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed erstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The ted here complies with that document and is a true representation of the conditions observed in the field. fies that I gurdualified as a geologist as defined by 30 TAC 213 Date 3 27/5		2 TOPOGRAP	₹								
Jerstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The	lerstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The typed here complies with that document and is a true representation of the conditions observed in the field.	erstood, and I have followed the Texas Natural Resource Conservation Commission's Instructions to Geologists. The the field here complies with that document and is a true representation of the conditions observed in the field. The field field that a geologist as defined by 30 TAC 213 Date 3 27/5		JIII, Hilltop, Hil	Iside, Dr	ainage,	Floodplain,	Streaml	bed				
	nted here complies with that document and is a true representation of the conditions observed in the field.	ted here complies with that document and is a true representation of the conditions observed in the field. Res that I am qualified as a geologist as defined by 30 TAC 213 Date $3727/3$	derstood, and I have fol	ligwed the Te	cas Natur	ral Reso	ource Cons	ervation	Commission	's Instru	ctions to Ge	eologists. Th	Ð
My signature continues that i amount the day ageologist as defined by 30 TAC 213 Date $3/27/3$									Sheet	đ			

Attachment B Stratigraphic Column Former McCoy Elementary School Tract Williams Drive, Georgetown, Texas

HYDROGEOLOGIC STIRDIVISION	FORMATION	THICKNESS (feet)	TITHOLOGY
Edwards Aquifer	Edwards Limestone	150	Mudstone to packstone, crystalline limestone, wackestone

Source: Senger, Collins and Kreitler, 1990





Attachment C

SITE-SPECIFIC GEOLOGY


The Geologic Assessment (GA) of the Former McCoy Elementary School Tract was performed by Mr. Russell C. Ford, P.G., of Terracon on March 19, 2018. The site is located on the north corner of Williams Drive and Park Lane in Georgetown, Texas. The site is approximately 16.161-acres in size and is developed with the former McCoy Elementary School buildings.


Exhibit 1 (attached) is a site location map depicting the site in relation to the surrounding area. The areas immediately surrounding the site are a mix of residential and commercial properties. The site is characterized as gently sloping to the south and east. Site elevation ranges from about 760 feet above mean sea level (msl) to 750 feet above msl. The North Fork of the San Gabriel River is located offsite to the south.


The surficial geologic unit present at the site has been identified as the Edwards Limestone. Exhibit 2 (attached) is a geologic map of the site. The Edwards consists of massive to thin bedded limestones and dolostones. The formation is characterized by honeycomb textures, collapse breccias and cavern systems, which account for most of the significant porosity within the strata that compose most of the aquifer. The site is located entirely within the recharge zone of the Edwards Aquifer and the recharge zone boundary is located about 500 feet to the south of the site corresponding to the location of the San Gabriel River. Table 1 (attached) is a stratigraphic column prepared for the site. Exposure of this unit onsite is obscured by the existing soil cover and vegetation present. No faulting was observed on the site and the nearest mapped fault is located approximately 1,000 feet east of the site. The fault, which trends toward the northeast, is associated with the Balcones Fault zone which represents the dominant structural trend in the vicinity of the site. The completed Geologic Assessment form is attached.

No geologic features were observed on the site. Due to the lack of any significant sensitive recharge features observed on the site, the potential for fluid movement to the Edwards aquifer beneath the project is considered low.

No streams or springs were observed onsite. A review of the site maps contained in the City of Georgetown Ordinance 2015-14 indicated there are no known springs occupied by the Georgetown Salamander on the site and the nearest known occupied site is located approximately one mile east of the site (San Gabriel Spring).







LEGEND



----- Site Boundary Ked Edwards Formation

> SITE GEOLOGIC MAP McCoy Elementary School Tract Williams Drive Georgetown, Williamson County, Texas

EXHIBIT

2

Modification of a Previously Approved Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This request for a **Modification of a Previously Approved Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Hollis Scheffler, P.E.

Date: <u>8/22/2023</u> Signature of Customer/Agent:

Project Information

1. Current Regulated Entity Name: <u>Rivery Commercial Subdivision</u> Original Regulated Entity Name: <u>Rivery Commercial Subdivision</u> Regulated Entity Number(s) (RN): <u>111699997</u>

Edwards Aquifer Protection Program ID Number(s): <u>11003538</u>

- The applicant has not changed and the Customer Number (CN) is: <u>606119360</u> & <u>606165801</u>
- The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
- 2. Attachment A: Original Approval Letter and Approved Modification Letters. A copy of the original approval letter and copies of any modification approval letters are attached.

3. A modification of a previously approved plan is requested for (check all that apply):

Physical or operational modification of any water pollution abatement structure(s)
including but not limited to ponds, dams, berms, sewage treatment plants, and
diversionary structures;

- Change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
- Development of land previously identified as undeveloped in the original water pollution abatement plan;

] Physical modification of the approved organized sewage collection system;

Physical modification of the approved underground storage tank system;

Physical modification of the approved aboveground storage tank system.

4. Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

WPAP Modification	Approved Project	Proposed Modification
Summary		
Acres	<u>12.69</u>	<u>12.69</u>
Type of Development	<u>Commercial</u>	Commercial & Multifamily
Number of Residential	<u>N/A</u>	<u>N/A</u>
Lots		
Impervious Cover (acres)	<u>3.07</u>	<u>7.78</u>
Impervious Cover (%	<u>24.19</u>	<u>61.31</u>
Permanent BMPs	Credit & Batch Det	Batch Detention
Other	<u>N/A</u>	<u>N/A</u>
SCS Modification	Approved Project	Proposed Modification
Summary		
Linear Feet	<u>N/A</u>	<u>N/A</u>
Pipe Diameter	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>

AST Modification	Approved Project	Proposed Modification
Summary		
Number of ASTs	<u>N/A</u>	<u>N/A</u>
Volume of ASTs	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>
UST Modification	Approved Project	Proposed Modification
UST Modification Summary	Approved Project	Proposed Modification
-	Approved Project N/A	Proposed Modification
Summary		

- 5. Attachment B: Narrative of Proposed Modification. A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved, including any previous modifications, and how this proposed modification will change the approved plan.
- 6. Attachment C: Current Site Plan of the Approved Project. A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.
 - The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was **not** constructed as approved.

The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was constructed as approved.

- The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was **not** constructed as approved.
- 7. The acreage of the approved plan has increased. A Geologic Assessment has been provided for the new acreage.
 - Acreage has not been added to or removed from the approved plan.
- 8. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

Attachment A – Original Approval Letter

Jon Niermann, *Chairman* Emily Lindley, *Commissioner* Bobby Janecka, *Commissioner* Kelly Keel, *Interim Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

August 4, 2023

Ms. Julie Ward PDC Williams Plaza Ltd. 1313 Williams Dr. Georgetown, Texas 78628

Re: Approval of a Water Pollution Abatement Plan (WPAP) Rivery Commercial Subdivision; Located Southeast of Rivery Blvd. and Williams Dr.; Georgetown, Williamson County, Texas Edwards Aquifer Protection Program ID: 11003538; Regulated Entity No. RN111699997

Dear Ms. Ward:

The Texas Commission on Environmental Quality (TCEQ) has completed its review on the application for the above-referenced project submitted to the Edwards Aquifer Protection Program (EAPP) by Westwood Professional Services on behalf of the applicant, PDC Williams Plaza Ltd. on March 16, 2023. Final review of the application was completed after additional material was received on June 1, 2023, June 9, 2023, June 27, 2023, July 18, 2023, and July 25, 2023.

As presented to the TCEQ, the application was prepared in general compliance with the requirements of 30 Texas Administrative Codes (TAC) Chapter §213. The permanent best management practices (BMPs) and measures represented in the application were prepared by a Texas licensed professional engineer (PE). All construction plans and design information were sealed, signed, and dated by a Texas licensed PE. Therefore, the application for the construction of the proposed project and methods to protect the Edwards Aquifer are **approved**, subject to applicable state rules and the conditions in this letter.

This approval expires two years from the date of this letter, unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been officially requested. This approval or extension will expire, and no extension will be granted if more than 50 percent of the project has not been completed within ten years from the date of this letter.

The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer protection plan. A motion for reconsideration must be filed in accordance with 30 TAC §50.139.

This approval letter supersedes and replaces the prior approval letter dated July 19, 1995, for the Raye McCoy Elementary School WPAP (EAPP ID No. 11-95071201), which shall hereafter be void and of no effect.

TCEQ Region 11 · P.O. Box 13087 · Austin, Texas 78711-3087 · 512-339-2929 · Fax 512-339-3795

Ms. Julie Ward Page 2 August 4, 2023

PROJECT DESCRIPTION

The proposed commercial project will have an area of approximately 12.69 acres. The project will include three commercial buildings with associated grading, utilities, parking, sidewalks, a public roadway, water quality facilities, and associated appurtenances. The impervious cover will be 3.07 acres (24.19 percent). Project wastewater will be disposed of by conveyance to the existing Brushy Creek West Wastewater Treatment Plant.

PERMANENT POLLUTION ABATEMENT MEASURES

This commercial development received 3.07 acres of pre-rule impervious cover credit for this project. No permanent BMPs are required.

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, a batch detention basin, designed using the TCEQ technical guidance, *RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices,* will be constructed to treat stormwater runoff for future development.

The permanent BMPS shall be operational prior to occupancy or use of future projects. A request for Modification of an Approved Water Pollution Abatement Plan (WPAP-MOD) and approval will be required prior to the construction of associated impervious cover. Inspection, maintenance, repair, and retrofit of the permanent BMPs shall be in accordance with the approved application.

GEOLOGY

According to the Geologic Assessment (GA) included with the application, the surficial unit of the site is Edwards Limestone. No sensitive geologic features were identified in the GA. The site assessment conducted on May 15, 2023, by TCEQ staff determined the site to be generally as described by the GA.

SPECIAL CONDITIONS

I. Additional development outside the scope of this project is ineligible for pre-rule impervious cover credit. All impervious cover in addition to the 3.07 acres approved in this project will be required to meet the 80 percent removal of the increased load in total suspended solids (TSS).

STANDARD CONDITIONS

- 1. The plan holder (applicant) must comply with all provisions of 30 TAC Chapter §213 and all technical specifications in the approved plan. The plan holder should also acquire and comply with additional and separate approvals, permits, registrations or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, Dam Safety, Underground Injection Control) as required based on the specifics of the plan.
- 2. In addition to the rules of the Commission, the plan holder must also comply with state and local ordinances and regulations providing for the protection of water quality as applicable.

Prior to Commencement of Construction:

3. Within 60 days of receiving written approval of an Edwards Aquifer protection plan, the plan holder must submit to the EAPP proof of recordation of notice in the county deed records, with the volume and page number(s) of the county record. A description of the

property boundaries shall be included in the deed recordation in the county deed records. TCEQ form, Deed Recordation Affidavit (TCEQ-0625), may be used.

- 4. The plan holder of any approved Edwards Aquifer protection plan must notify the EAPP and obtain approval from the executive director prior to initiating any modification to the activities described in the referenced application following the date of the approval.
- 5. The plan holder must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the EAPP no later than 48 hours prior to commencement of the regulated activity. Notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person.
- 6. Temporary erosion and sedimentation (E&S) controls as described in the referenced application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.
- 7. All borings with depths greater than or equal to 20 feet must be plugged with non-shrink grout from the bottom of the hole to within three (3) feet of the surface. The remainder of the hole must be backfilled with cuttings from the boring or gravel. All borings less than 20 feet must be backfilled with cuttings from the boring. All borings must be backfilled or plugged within four (4) days of completion of the drilling operation.

During Construction:

- 8. This approval does not authorize the installation of temporary or permanent aboveground storage tanks on this project that will have a total storage capacity of five hundred gallons or more of static hydrocarbons or hazardous substances without prior approval of an Aboveground Storage Tank facility application.
- 9. If any sensitive feature is encountered during construction, replacement, or rehabilitation on this project, all regulated activities must be **immediately** suspended near it and notification must be made to TCEQ EAPP staff. Temporary BMPs must be installed and maintained to protect the feature from pollution and contamination. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality.
- 10. All water wells, including injection, dewatering, and monitoring wells shall be identified in the geologic assessment and must be in compliance with the requirements of the Texas Department of Licensing and Regulation 16 TAC Chapter §76 and all other locally applicable rules, as appropriate.
- 11. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
- 12. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge must be filtered through appropriately selected BMPs.

Ms. Julie Ward Page 4 August 4, 2023

- 13. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 14. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

- 15. Owners of permanent BMPs and temporary measures must ensure that the BMPs and measures are constructed and function as designed. A Texas licensed PE must certify in writing that the **permanent** BMPs or measures were constructed as designed. The certification letter must be submitted to the EAPP within 30 days of site completion.
- 16. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or the ownership of the property is transferred to the entity. A copy of the transfer of responsibility must be filed with the executive director through the EAPP within 30 days of the transfer. TCEQ form, Change in Responsibility for Maintenance on Permanent BMPs and Measures (TCEQ-10263), may be used.

The holder of the approved Edwards Aquifer protection plan is responsible for compliance with Chapter §213 and any condition of the approved plan through all phases of plan implementation. Failure to comply with any condition within this approval letter is a violation of Chapter §213 and is subject to administrative rule or orders and penalties as provided under §213.10 of this title (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. Upon legal transfer of this property, the new owner is required to comply with all terms of the approved Edwards Aquifer protection plan.

This action is taken as delegated by the executive director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Ms. Betsy Yockey of the Edwards Aquifer Protection Program at 512-239-7014 or the regional office at 512-339-2929.

Sincerely. Lillian Butter

Lillian Butler, Section Manager Edwards Aquifer Protection Program Texas Commission on Environmental Quality

LIB/bmy

cc: Ms. Hollis Scheffler, P.E., Westwood Professional Services

Attachment B – Narrative of Proposed Modification

The intent of this Water Pollution Abatement Plan (WPAP) Modification is to update the impervious cover for the project. PDC Williams Plaza Ltd. and Novak GISD Multifamily, LLC are developing this project in conjunction. The pre-rule existing impervious cover was used for the PDC Williams Plaza site, and the batch detention pond is sized for the Novak GISD Multifamily portion of the property.


The WPAP approved on August 4, 2023, allowed 3.07 acres of impervious cover (24.19%) to be developed using pre-rule impervious cover. In addition, the batch detention pond was approved with the WPAP to treat the Novak GISD portion of the property, but no impervious cover was proposed at the time of application. The existing batch detention pond had water quality volume to account for 5.08 acres of impervious cover. This modification to the approved WPAP will use 4.71 acres of 5.08 pre-planned impervious cover of the batch detention pond. The total impervious cover being proposed is now 7.78 acres of impervious cover (61.3%).


The volume calculations for the pond have remained the same since the pond was already designed for the impervious cover being proposed.



Attachment C – Current Site Plan of the Approved Project







PK-4670-21.455EROS_PH1.DWG

Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Hollis Scheffler, P.E.

Date: <u>8/22/2023</u>

Signature of Customer/Agent:

Regulated Entity Name: Rivery Commercial Subdivision

Regulated Entity Information

1. The type of project is:

Residential: Number of Lots:____

- $\underline{\checkmark}$ Commercial
- Industrial

__ Other:____

- 2. Total site acreage (size of property): 12.69
- 3. Estimated projected population: 425
- 4. The amount and type of impervious cover expected after construction are shown below:

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	156,855	÷ 43,560 =	3.60
Parking	72,433	÷ 43,560 =	1.66
Other paved surfaces	109,535	÷ 43,560 =	2.51
Total Impervious Cover	338,823	÷ 43,560 =	7.78

Table 1 - Impervious Cover Table

Total Impervious Cover 7.78 ÷ Total Acreage 12.69 X 100 = 61.3% Impervious Cover

- 5. Attachment A Factors Affecting Surface Water Quality. A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
- 6. Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

7. Type of project:

TXDOT road project.

County road or roads built to county specifications.

City thoroughfare or roads to be dedicated to a municipality.

Street or road providing access to private driveways.

8. Type of pavement or road surface to be used:

Concrete
Asphaltic concrete pavement
Other:

9. Length of Right of Way (R.O.W.): _____ feet.

Width of R.O.W.: _____ feet. L x W = _____ Ft² \div 43,560 Ft²/Acre = _____ acres.

10. Length of pavement area: _____ feet.

Width of pavement area:feet.L x W = $Ft^2 \div 43,560 Ft^2/Acre =$ acres.Pavement areaacres ÷ R.O.W. areaacres x 100 =% impervious cover.

11. A rest stop will be included in this project.

A rest stop will not be included in this project.

12. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

13. Attachment B - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

14. The character and volume of wastewater is shown below:

<u>100</u> % Domestic	<u>81,376</u> Gallons/day
% Industrial	Gallons/day
% Commingled	Gallons/day
TOTAL gallons/day <u>81,376</u>	

15. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

Attachment C - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

Sewage Collection System (Sewer Lines):

- Private service laterals from the wastewater generating facilities will be connected to an existing SCS.
- Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.

The SCS was previously submitted on_____.

-] The SCS was submitted with this application.
- The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

The sewage collection system will convey the wastewater to the <u>San Gabriel</u> <u>Wastewater</u> (name) Treatment Plant. The treatment facility is:

imes	Existing.
	Proposed

16. \square All private service laterals will be inspected as required in 30 TAC §213.5.

Site Plan Requirements

Items 17 – 28 must be included on the Site Plan.

17. \square The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1'' = 40' and 50'.

18. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): <u>FEMA Firm Panel 48491C0293F effective December 20, 2019.</u>

19. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.

20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)

The wells are not in use and have been properly abandoned.

The wells are not in use and will be properly abandoned.

] The wells are in use and comply with 16 TAC §76.

There are no wells or test holes of any kind known to exist on the project site.

21. Geologic or manmade features which are on the site:

All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.

No sensitive geologic or manmade features were identified in the Geologic Assessment.

Attachment D - Exception to the Required Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached.

- 22. The drainage patterns and approximate slopes anticipated after major grading activities.
- 23. 🖂 Areas of soil disturbance and areas which will not be disturbed.
- 24. 🔀 Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 25. 🛛 Locations where soil stabilization practices are expected to occur.
- 26. Surface waters (including wetlands).

🖂 N/A

- 27. Locations where stormwater discharges to surface water or sensitive features are to occur.
 - There will be no discharges to surface water or sensitive features.
- 28. 🛛 Legal boundaries of the site are shown.

Administrative Information

- 29. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 30. Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Attachment A – Factors Affecting Surface Water Quality

The following are potential sources of surface and groundwater contamination from construction activities:

- Clearing and grubbing
- Grading and site excavation
- Vehicle tracking
- Topsoil stripping and stockpiling
- Landscaping operations
- Staging and storage area
- Paving (including curb and gutter)
- Building Construction
- Concrete washout area



Attachment B – Volume and Character of Stormwater


The existing site generates approximately 43.2 cfs flowing over 5.67 acres primarily northwest to southeast over 75% grass cover at roughly 2%. The curve number utilized for the existing site was 80.

The proposed development generates an approximate 55.9 cfs and has a required TCEQ TSS removal of 80%. The runoff from the site is generated from the streets, building roof, driveways, parking, and other paved and impervious surfaces. The curve number utilized for the proposed development is 98. Flow is directed from the previously listed impervious structures and sent into catch basins. From there, the flow is directed into the existing batch detention pond that is sized to treat this development.



Site Plan





Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Hollis Scheffler, P.E.

Date: <u>8/22/2023</u>

Signature of Customer/Agent:

Regulated Entity Name: Rivery Commercial Subdivision

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2. Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

- For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>San Gabriel</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. X Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	 A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
	A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
	I There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area
	disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect
	down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be
	disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

- 11. Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
 - 🗌 N/A
- 12. Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. 🖂 Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. \square All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

Attachment A – Spill Response Actions

In accordance with the Edwards Aquifer Technical Guidance on Best Management Practices Operators, the following actions will be followed to ensure appropriate measures are taken in the case of a spill:

<u>Education</u>

- Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
- Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees.
- Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

Westwood

- To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and wastes in covered containers and protect from vandalism.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from stormwater run on during rainfall to the extent that it doesn't compromise cleanup activities.
- Do not bury or wash spills with water.
- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

<u>Cleanup</u>

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
- Contain the spread of the spill.
- Recover spilled materials.
- Clean the contaminated area and properly dispose of contaminated materials.

<u>Semi-Significant Spills</u>

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.



Spills, Discharges, and Releases

- Report an environmental emergency, discharge, spill, or air release. Links to rules, law, technical assistance, waste management, State Emergency Response Commission.
- Please contact TCEQ emergencies for reportable quantities using the link below: <u>https://www.tceq.texas.gov/response/spills/spill_rq.html</u>

To report and environmental emergency, discharge, spill, or air release, control:

<u>State</u>

- State of Texas Spill-Reporting Hotline and the SERC: 1-800-832-8224 --- 24 hours a day
- TCEQ Regional Office, Monday-Friday, 8 a.m. 5 p.m.

<u>Federal</u>

• National Response Center: 1-800-424-8802 (notifying the NRC does not constitute to the state)



Attachment B – Potential Sources of Contamination

The following are potential sources of surface and groundwater contamination from construction activities:

- Clearing and grubbing
- Grading and site excavation
- Vehicle tracking
- Topsoil stripping and stockpiling
- Landscaping operations
- Staging and storage area
- Paving (including curb and gutter)
- Building Construction
- Concrete washout area



Attachment C – Sequence of Major Activities

The following sequence of construction is included in the construction plans:

- Temporary erosion controls, silt fencing and tree protection fencing to be installed. Estimated area disturbed = 12.69 ac Estimated timing = 1 week
- Pre-construction meeting to be held on-site.
 Estimated area disturbed = n/a ac
 Estimated timing = 1 day
- Demolition of existing materials.
 Estimated area disturbed = 12.69 ac
 Estimated timing = 6 weeks
- Site staking and rough grading.
 Estimated area disturbed = 12.69 ac
 Estimated timing = 6 weeks
- Storm sewers to be installed.
 Estimated area disturbed = 12.69 ac
 Estimated timing = 8 weeks
- Water, wastewater and paving improvements to begin. Estimated area disturbed = 12.69 ac Estimated timing = 8 weeks
- Temporary erosion control measures to be inspected on a regular basis; any sediment buildup to be removed.
 Estimated area disturbed = n/a
 Estimated timing = 1 week
- Site to be cleaned up and revegetated.
 Estimated area disturbed = 12.69 ac
 Estimated timing = 6 weeks
- Temporary erosion controls to be removed after permanent restoration of site is established.
 Estimated area disturbed = n/a
 Estimated timing = 1 week



Attachment D – Temporary Best Management Practices and Measures

The following temporary best management practices will be conducted to prevent pollution of surface water, groundwater, and stormwater in accordance with the Edwards Aquifer Technical Guidance on Best Management Practices.

Temporary Vegetation

Vegetation will be used as a temporary stabilization technique for areas disturbed by construction, but not covered by pavement, buildings, or other structures. As a temporary control, vegetation will be used to stabilize stockpiles and barren areas that are inactive for long periods of time.

Dust Control

Dust control will prevent blowing and movement of dust from exposed soil surfaces, reduce on and off-site damage, health hazards and improve traffic safety. This practice is applicable to areas subject to dust blowing and movement where on and off-site damage is likely without treatment.

Temporary Construction Entrance/Exit

The temporary gravel construction entrance will provide a stable entrance/exit condition from the construction site and keep mud and sediment off public roads. A stabilized construction entrance is a stabilized pad of crushed stone located at any point traffic will be entering or leaving the construction site from a public right-of way, street, alley, sidewalk or parking area. The stabilized construction entrance will reduce or eliminate the tracking or flowing of sediment onto public rights of-way. This practice should be used at all points of construction ingress and egress.

Silt Fence

A silt fence is a barrier consisting of geotextile fabric supported by metal posts to prevent soil and sediment loss from a site. Proposed silt fences will be highly effective at controlling sediment from disturbed areas. They cause runoff to pond, allowing heavier solids to settle out.

Inlet Protection

All proposed inlets that may receive storm runoff from disturbed areas should be protected. Temporary inlet protection is a series of different measures that provide protection against silt transport or accumulation in storm sewer systems. This clogging can greatly reduce or completely stop the flow in the pipes. The different measures are used for different site conditions and inlet types. Filter barrier protection using silt fence is appropriate when the drainage area is less than one acre, and the basin slope is less than five percent. This type of protection is not applicable in paved areas. Block and gravel protection is used when flows exceed 0.5 cubic feet per second, and it is necessary to allow for overtopping to prevent flooding. This form of protection is used when flows exceed 0.5 cubic feet per second and construction traffic may occur over the inlet. This form of protection may be used with both curb and drop inlets.



Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes: • Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.

- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.

For onsite washout:

- Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
- Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.



Attachment F – Structural Practices

Stormwater will be routed through the proposed silt fence and inlet protection for pollutant removal. The proposed permanent BMP is to be constructed as to intercept stormwater flowing from the parking lots, streets, building roofs, and other impervious areas. The flow proposed with this WPAP can bypass the water quality treatment due to the fact that the site has predevelopment impervious cover that has negated the requirement for treatment. The silt fence will provide temporary sedimentation control during construction prior to the permanent BMP being finalized. No part of the site or placement of the structural practices will be encumbered by floodplain as shown on FEMA #48491C0293F.



Attachment G – Drainage Area Map



Project: Rise 1900 Simulation Run: EX 2-YR SCS
 Start of Run:
 09Apr2020, 00:00
 Basin Model:
 Existing

 End of Run:
 10Apr2020, 00:00
 Meteorologic Model:
 CoA SCS 2 Yr 24 Hr

 Compute Time:DATA CHANGED, RECOMPUTE
 Control Specifications: 24 Hours
 Volume Units: 🗿 IN 🔿 ACRE-FT Show Elements: All Elements ~ Sorting: Hydrologic 🗸 Drainage Area Peak Discharge Time of Peak Hydrologic Volume Element (MI2) (CFS) (IN) 0.009798 11.4 09Apr2020, 12:12 BASIN A 2.33

End of R	Run: 09Apr2020, 00:00 un: 10Apr2020, 00:00 Time:DATA CHANGED, R	Meteoro		Existing CoA SCS 10 Y :24 Hours	'r 24 Hr
how Elements: All El	ements 🚽	Volume Units: O 🕅 🔿	ACRE-FT	Sor	ting: Hydrologi
how Elements: All El Hydrologic Element	Drainage Area (MI2)	Volume Units: OIN C Peak Discharge (CFS)	ACRE-FT		ting: Hydrologi Volume (IN)

		Project: Rise 1	1900 Simulation Run:	EX 25-YR SCS	
Show Elements:	End of Run: Compute Time	09Apr2020, 00: 10Apr2020, 00: :16May2023, 11 V	00 Meteorologi	c Model: CoA SCS 25 Y cifications: 24 Hours	r 24 Hr Sorting: Hydrologic N
Hydrologic Element	Dra	iinage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
BASIN A	0	0.009798	31.1	09Apr2020, 12:11	6,22


Project: Rise 1900 Simulation Run: EX 100-YR SCS Start of Run: 09Apr2020, 00:00 End of Run: 10Apr2020, 00:00 Compute Time:DATA CHANGED, RECOMPUTE Basin Model: Existing Meteorologic Model: CoA SCS 100 Yr 24 Hr Control Specifications:24 Hours Volume Units: O IN O ACRE-FT Show Elements: All Elements Sorting: Hydrologic Peak Discharge Hydrologic Drainage Area Time of Peak Volume Element (IN) (MI2) (CFS) 0.009798 43.2 09Apr2020, 12:11 8.70 BASIN A

WARNING! There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.	
NO	

							Se	lect RCN fro	om Table 2-7 of DCM																							
									Lawn																							
					Building	Pavement			(Good)					Time of Conce	ntration																	
			Hydro	logic Soil Group [%]	1	98 98	91	87	78 80	84 8	9					5	Sheet				Shallow Conce	entrated -	Unpaved		Shallow C	oncentrated	- Paved		Channe	el/Storm Dr	rain	Total
Basin	Area [s.f.]	Area [ac.] Area	[sq. mi.] A B	C D % Ch	eck IC-1 [s.f	.] IC-2[s.f.]	IC-3 [s.f.] IC-4 [s.	F.] PC-1[s.	f.] PC-2 [s.f.] PC-3 [s.	.f.] PC-4 [s.f.] Total IC [s.f.] Total IC	% % Chec	ck Composite RCN	Elev-Start [ft]	Elev-Stop [ft]	L[ft]	n P[in]] s [ft/ft]	Tt-sheet [min] E	Elev-Start [ft]	Elev-Stop [ft]	L [ft]	s [ft/ft] Tt-SCFu [min	Elev-Start [ft] Elev-Stop [ft] L[ft]	s [ft/ft] Tt-SCFp [r	nin] L [ft]	Q [cfs] A [ft^2] W	p [ft] V [ft/	t/s] Tt-channel [min]	Tc [min] Tlag
Existing A	27316	5 6.27	0.009798 0% 0%	0% 100% OK		0 110,043	0	0	0 163,122	0	0 110043 40.289	% ок	80.0	757	755.7	150	0.13 4	4.2 0.008667	7 14.74	755.7	7 754	184	0.009 1.9	8 7	754 75	4 0	0.000	0.00 0	0 0	0	5 0.00	16.72

	NO.	REVISION	BY	DATE	DLP
					DESIGNED BY:
THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION					АМК
ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR					DRAWN BY:
SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.					
					CHECKED BY:
					APPROVED BY:

.4







2023-16-SDF

Project: Rise 1900 Simulation Run: PR 2-YR SCS

Start of Run: 09Apr2020, 00:00 Basin Model: Proposed

Show Elemen


	End of Run: Compute Time		영양 귀엽 감정 것이 다 같아요	Meteorologic Model: Control Specification		
ow Elements:	All Elements \sim	2	Volume Units	:: 🔿 🖪 🔿 ACRE-FT	r Sortir	ng: Hydrologic
Hydrologic Element	Dra	inage Area (MI2)		ischarge Tin (FS)	ne of Peak	Volume (IN)

Element	(MI2)	(CFS)		(IN)
ASIN A	0.005063	9.8	09Apr2020, 12:05	3.37
ASIN B	0.003015	5,9	09Apr2020, 12:05	3.39
ASIN C	0.001689	3.1	09Apr2020, 12:07	3.37

1	Start of Run: 0 End of Run: 1 Compute Time:0	10Apr2020, 00: 13Aug2023, 11:	00 Meteorolo	gic Model: ecifications			Hydrologic ~
						253	
Hydrologic Element	Contraction of the second s	age Area MI2)	Peak Discharge (CFS)		ne of Peak		Volume (IN)
Element	0	S70 (1997)	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Tir			3.53.600.000
	0.0	MI2)	(CFS)	Tir 09Ap	ne of Peak		(IN)

		Project: Rise	1900 Simulation Run	PR 25-YR SCS	
Show Elements:	End of Run: Compute Time	:03Aug2023, 11	:00 Meteorolog	ic Model: CoA SCS 2 ecifications:24 Hours	5 Yr 24 Hr Sorting: Hydrologic ~
Hydrologic	Dra	ainage Area	Peak Discharge	Time of Peak	Volume
Element		(MI2)	(CFS)		(IN)
Constanting of the	((MI2) 0.005063	(CFS) 21.9	09Apr2020, 12:03	(IN)
Element BASIN A BASIN B				09Apr2020, 12:0 09Apr2020, 12:0	(IN) 5 7.57

Show Elements:	Compute Time	10Apr2020, 00: :03Aug2023, 11:	00 Basin Model: 00 Meteorologic	Proposed Model: CoA SCS ifications:24 Hours	100 Yr 24 Hr	Hydrologic ~
			Coldinic Collication and and	COMPANIES IN COMPANY	Sol ung.	Hydrologic V
Hydrologic Element		ainage Area (MI2)	Peak Discharge (CFS)	Time of Pea		Volume (IN)
Hydrologic Element	: Dr	ainage Area	Peak Discharge	1	k	Volume
Hydrologic	Dr	ainage Area (MI2)	Peak Discharge (CFS)	Time of Pea	k 2:05	Volume (IN)




THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.

NO.	REVISION	BY	DATE	DLP	
				DESIGNED BY:	DAT
				АМК	
				DRAWN BY:	DATI
				CHECKED BY:	DAT
				APPROVED BY:	DAT

Attachment H – Temporary Sediment Pond Plans and Calculations


A rough-cut water quality pond will be utilized for the temporary sedimentation removal on-site and is to be graded in accordance with the following plan sheet provided. Revegetation or placement of underdrain piping shall not be carried out until the site construction phase is complete.




Stage Storage Table						
Water Surface Elevations	Peak Discharge (cfs)	Stage (ft msl)*	Area (sf)	Incremental Volume (cf)	Storage (cf)	
		750.30	13,444.24	95.46	90.74	
		751.00	14,794.50	1,469.64	9,971.18	
		752.00	16,800.30	3,319.30	25,762.04	
WQE		752.20	17,211.13	1,710.82	29,163.18	
		753.00	18,886.75	1,878.06	43,598.99	
2 Y R - WSE CFS	21.3	753.90	20,833.52	2,072.38	61,468.27	
		754.00	21,053.86	2,094.37	63,562.64	
10 Y R - WSE CFS	39.1	755.00	23,301.62	2,318.74	20,145.38	
25 Y R - WSE CFS	49.2	755.50	24,455.75	4,844.74	32,084.00	
		756.00	25,630.04	2,551.18	44,604.72	
100 YR - WSE CFS	62.9	756.40	26,584.00	2,646.42	55,047.17	
		756.50	26,824.50	2,670.43	57,717.59	
		756.60	27,065.81	2,694.52	60,412.11	
		756.70	27,307.93	2,718.69	63,130.80	
		756.80	27,550.85	2,742.94	65,873.73	

					2 YEAR	STORM	10 YEAI	RSTORM	25 YEAI	RSTORM	100 YEA	RS
Drainage					Runoff Per	Routed	Runoff Per	Routed	Runoff Per	Routed	Runoff Per	
Area Basin	Drainage	Base Curve		Impervious	Drainage	Cumulative	Drainage	Cumulative	Drainage	Cumulative	Drainage	c
Designation	Area	Number CN	Lag Time	Cover	Area	Runoff	Area	Runoff	Area	Runoff	Area	
	(ac)		(min)	%	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	
EX 1	3.717	80	9.67	10.00%	10.40		18.50		23.90		32.70	
EX 2	2.875	80	12.92	80.00%	9.60		15.10		18.70		24.70	
EX 3	6.100	80	10.87	27.50%	16.30		30.40		39.90		55.40	
HEC-HMS SUM	MARY: DEVEL	OPED CONDITO	NS			2 YEAR	STORM	10 YEAR	STORM	25 YEAR	STORM	
Drainage						RunoffPer		Runoff Per		Runoff Per		\vdash
Area Basin	Drainage	Base Curve		Cumulative	Impervious	Drainage	Detention	Drainage	Detention	Drainage	Detention	
	Area	Number CN	Lag Time	Area	Cover	Area	Release	Area	Release	Area	Release	
Designation		-			_					1		4
Designation	(ac)		(min)	(ac)	%	(cfs)	cfs)	(cfs)	(cfs)	(cfs)	(cfs)	
Designation DA 1	(ac) 12.69	80	(min) 3.60	(ac)	% 65.78%	(cfs) 39.20	(cfs)	(cfs) 71.10	(cfs)	(cfs) 88.40	(cfs)	


/23/2023 10:07 AM \DWG-46\4670-21.455\DWG\CIVIL C3D 2018\SWP\4670-21.455POND.DWG





		Į				
0	25	50	10	00	150	
	GRAF	PHIC S	CALE IN	FEET		
		G				
G <u>EL</u> <u>TW</u>	B. EM© PP• LS WMO WV& ICV& FH CO MHO TSC I TSP• TELE I FP• SIGN IRS (C.M.) A OHL - 612.33 C 612.33 C 613.60 C 614.00 M.C.		BOLLARD ELECTRIC M POWER POL LIGHT STAN WATER MET WATER MET WATER VAL RRIGATION FIRE HYDRA CLEANOUT MANHOLE TRAFFIC SIG TRAFFIC SIG TRAFFI	IETER IDARD ER IDARD ER CONTROL ANT GNAL CON GNAL CON GNAL POL BOX IT GN IT CON ROD CO KOCH" IG IT IN IN IN IN IN IN IN IN IN IN	ITROL E CAP SET MENT INE ON ELEVATION CURB ELEVA ELEVATION WALL ELEVA ELEVATION WALL ELEVA	ATION ATION ECTION

PROPERTY	TEST METHOD	UNIT	SPECIFICATION
			<u>,</u>
PERMEABILITY	ASTM D-2434	CM/SEC	1 x 10 ⁻⁶
PLASTICITY INDEX OF CLAY	ASTM D-423 & D-424	%	NOT LESS THAN 15
LIQUID LIMIT OF CLAY	ASTM D-2216	%	NOT LESS THAN 30
CLAY PARTICLES PASSING	ASTM D-422	%	NOT LESS THAN 30
CLAY COMPACTION	ASTM D-2216	%	95% OF STANDARD PROCTOR DENSITY



PK-4670-21.455POND.DWG

9 OF 16

Attachment I – Inspection and Maintenance for BMPs

The following inspection and maintenance guidelines for the temporary best management practices will be followed in accordance with the Edwards Aquifer Technical Guidance on Best Management Practices. Inspections of the Temporary BMPs will be documented in an inspection report. Inspection reports will document maintenance activities, sediment removal and modifications to the sediment and erosion controls.

Temporary Vegetation

- 1. Temporary vegetation should be inspected weekly and after each rain event to locate and repair any erosion.
- 2. Erosion from storms or other damage should be repaired as soon as practical by regrading the area and applying new seed.
- 3. If the vegetated cover is less than 80%, the area should be reseeded.

Dust Control

1. When dust is evident during dry weather, reapply dust control BMPs.

Temporary Construction Entrance/Exit

- 1. The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment.
- 2. All sediment spilled, dropped, washed, or tracked onto public rights-of-way should be removed immediately by contractor.
- 3. When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
- 4. When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
- 5. All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

<u>Silt Fence</u>

- 1. Inspect all fencing weekly, and after any rainfall.
- 2. Remove sediment when buildup reaches 6 inches.
- 3. Replace any torn fabric or install a second line of fencing parallel to the torn section.
- 4. Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
- 5. When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

Inlet Protection

Westwood

- 1. Inspection should be made weekly and after each rainfall. Repair or replacement should be made promptly as needed by the contractor.
- 2. Remove sediment when buildup reaches a depth of 3 inches. Removed sediment should be deposited in a suitable area and in such a manner that it will not erode.
- 3. Check placement of device to prevent gaps between device and curb.

- 4. Inspect filter fabric and patch or replace if torn or missing.
- 5. Structures should be removed and the area stabilized only after the remaining drainage area has been properly stabilized.

Concrete Washout Area

When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.



Inspection / Maintenance Completion - Summary

Company Name:
Company Address:
City/State/Zip:
Phone:
Engineer:
Engineers Address:
City/State/Zip:
Phone:
Property Owner:

Batch Detention Pond

Westwood

Monitoring / Maintenance Table

	Jan	Feb	Mar	Apr	May	Jun	July	Aug	Sep	Oct	Nov	Dec
Structural Repairs and Replacement												
Seasonal Mowing and Lawn Care (in)												
Debris and Litter Removal												
Sediment Removal												
Logic Controller												
Erosion Control												
Nuisance Control												
Completed By												
Date												

I hereby certify that the monitoring and maintenance of the Batch Detention Pond unit was completed in accordance with the directions of Batch Detention Pond inspection and maintenance plan.

(Signed by property owner or designee)

Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices

Seeding of the disturbed areas will be on-going after completion of the rough grading process. Temporary seeding will be utilized until permanent landscaping is installed. Seeding will occur on any areas that are undisturbed for a period of 14 days. If construction progress is stopped for a period of 14 days, soil stabilization practices must be initiated by the contractor. Permanent landscaping will be provided as soon as final grades are achieved and the final paving and building operations are completed. Bare soils should be seeded or otherwise stabilized within 14 calendar days after final grading or where construction activity has temporarily ceased for more than 21 days.



Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(Ii), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Hollis Scheffler, P.E.

Date: 8/22/2023

Signature of Customer/Agent

Regulated Entity Name: Rivery Commercial Subdivision

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

1. Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.



- 2. These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 - The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____

N/A

3. Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

_____N/A

- 4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
 - The site will be used for low density single-family residential development and has 20% or less impervious cover.
 - The site will be used for low density single-family residential development but has more than 20% impervious cover.
 - The site will not be used for low density single-family residential development.
- 5. The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
 - Attachment A 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
 - The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
 - The site will not be used for multi-family residential developments, schools, or small business sites.
- 6. Attachment B BMPs for Upgradient Stormwater.

		 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7.	\boxtimes	Attachment C - BMPs for On-site Stormwater.
		 A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8.		Attachment D - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
		N/A
9.	\boxtimes	The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
		 The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed. Attachment E - Request to Seal Features. A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10.		Attachment F - Construction Plans. All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
		 Design calculations (TSS removal calculations) TCEQ construction notes All geologic features All proposed structural BMP(s) plans and specifications

11. 🔀	Attachment G - Inspection, Maintenance, Repair and Retrofit Plan. A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
	Prepared and certified by the engineer designing the permanent BMPs and measures
	 Signed by the owner or responsible party Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
	A discussion of record keeping procedures
	N/A
12. 🗌	Attachment H - Pilot-Scale Field Testing Plan . Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
\boxtimes	N/A
13.	Attachment I -Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused

degradation. N/A

Responsibility for Maintenance of Permanent BMP(s)

by the regulated activity, which increase erosion that results in water quality

Responsibility for maintenance of best management practices and measures after construction is complete.

14. 🖂 The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.

N/A

15. \square A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

N/A

Attachment B – BMPs for Upgradient Stormwater

There will be no upstream surface waters running onto the site and will not be treated with the proposed pond. The proposed batch detention basin and all associated ESC practices are designed for the subject site. The proposed primary batch detention WQ Pond will be used to receive some onsite flows from stormwater coming from the proposed site. The proposed flow is able to bypass the water quality treatment due to the fact that the site has predevelopment impervious cover that has negated the requirement for treatment.

Attachment C – BMPs for On-site Stormwater

The Novak GISD Multifamily development within the Rivery Commercial Subdivision Entity is contributing to the existing primary batch detention basin based on 12.69 acres of contributing area, encompassing 61.3% of impervious cover across the site. The stormwater is diverted through impervious structures and sent into catch basins. From there, the flow is either directed into the existing batch detention pond that is sized to treat this development. The batch detention basin has a designated ultimate outfall along Park Lane. The batch detention basin has adequate existing water quality storage to account for this Novak GIS Multifamily proposed development within the 12.69 acres.



Attachment D – BMPs for Surface Streams

The Novak GISD Multifamily development within the Rivery Commercial Subdivision Entity is contributing to the existing primary batch detention basin based on 12.69 acres of contributing area, encompassing 61.3% of impervious cover across the site. The stormwater is diverted through impervious structures and sent into catch basins. From there, the flow is either directed into the existing batch detention pond that is sized to treat this development. The batch detention basin has a designated ultimate outfall along Park Lane. The batch detention basin has adequate existing water quality storage to account for this Novak GIS Multifamily proposed development within the 12.69 acres. No surface streams or sensitive features are located on the site.



Attachment F – Construction Plans

SITE DEVELOPMENT PLAN (2023-16-SDP) **RISE 1900 AT THE COMMONS AT RIVERY 1900 RIVERY BOULEVARD** DAVID L. PLAT CITY OF GEORGETOWN Sheet Index WILLIAMSON COUNTY, TEXAS

PROJECT INFORMATION

SITE ADDRESS:	1900 Rivery Boulevard Georgetown, TX 78628
OWNER:	Novak Brothers Development 1500 Rivery Boulevard, Suite 2200 Georgetown, TX 78628 512-943-4703 novakbros.com
ARCHITECT:	HEDK Architects 4595 Excel Parkway Addison, TX 75001 214-520-8878 hedk.com info@hedk.com
CIVIL ENGINEER/SURVEYOR:	Steger Bizzell 1978 S. Austin Avenue Georgetown, TX 78626 512-930-9412 Stegerbizzell.com info@stegerbizzell.com
MEP:	Jordan & Skala Engineers 6201 W. Plano Parkway, Suite 250 Plano, TX 75093 469-385-1616 jordanskala.com
LANDSCAPE ARCHITECT:	Covey Landscape Architects 800 S. Austin Avenue Georgetown, TX 78626 512-887-5311 coveylandscape.com info@coveylandscape.com
ZONING DISTRICT:	C-3, McCoy School Site PUD, 2022-75
ACREAGE:	6.251 Acres
EXISTING IMPERVIOUS COVER:	2.50 Acres (40.1%)
PROPOSED IMPERVIOUS COVER:	4.64 Acres (74.2%)
LIMITS OF CONSTRUCTION:	6.15 Acres
LEGAL DESCRIPTION:	6.251 acres known as Lot 1, Block A, Rivery Commercial Subdivision, a subdivision in Williamson County, Texas according to plat as recorded in Document No. 2023052449 of the official public records of Williamson County, Texas.
PROPOSED USE:	Multi-Family, Attached
UTILITY PROVIDERS:	Water, Wastewater, and Electric: City of Georgetown Utility Systems 300-1 Industrial Ave. Georgetown, Texas 78626 512-930-3640 https://gus.georgetown.org/
ORIGINAL DATE:	March 20, 2023
REVISION DATE:	
ERAL NOTES:	

GENERAL NOTES:

- 1. It is the responsibility of the property owner, and successors to the current property owner, to ensure the subject property and any improvements are maintained in conformance with this Site Development Plan.
- 2. This development shall comply with all standards of the McCoy School Site PUD, the Unified Development Code (UDC), the City of Georgetown Construction Standards and Specifications Manual, the Development Manual and all other applicable City standards.
- This Site Development Plan shall meet the UDC Stormwater requirements. 4. All signage requires a separate application and approval from the Inspection Services Department. No
- signage is approved with the Site Development Plan.
- Sidewalks shall be provided in accordance with the UDC.
- Driveways will require approval by the Development Engineer of the City of Georgetown. 6 7. Outdoor lighting shall comply with Section 7.04 of the UDC.
- 8. Screening of mechanical equipment, dumpsters and parking shall comply with Chapter 8 of the UDC. The screening is shown on the Landscape and Architectural Plans, as applicable.
- 9. The companion Landscape Plan has been designed and plant materials shall be installed to meet all requirements of the UDC.
- 10. All maintenance of required landscape shall comply with the maintenance standards of Chapter 8 of the UDC. 11. A separate Irrigation Plan shall be required at the time of building permit application.
- 12. Fire flow requirements of 1,500 gallons per minute are being met by this plan.
- 13. Any Heritage Tree noted on this Site Development Plan is subject, in perpetuity, to the maintenance, care, pruning and removal requirements of the McCoy School Site PUD.
- 14. The construction portion of these plans were prepared, sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the construction plans for construction of the proposed project are hereby approved subject to the Standard Construction Specifications and Details Manual and all other applicable City, State and Federal Requirements and Codes
- 15. This project is subject to all City Standard Construction Specifications and Details in effect at the time of submittal of the project to the City.
- 16. Where no existing overhead infrastructure exists, underground electric utility lines shall be located along the street and within the site. Where overhead infrastructure is to be relocated, it shall be re-installed underground and the existing facilities shall be removed at the discretion of the Development Engineer
- 17. All electric and communication infrastructure shall comply with UDC Section 13.06. THESE COTIFATE COMPARE ANALYSISE (EEA) PREPARED ANALYSIS (EEA) PREPARED ANALYSIS (EEA) PREPARED ANALYSIS (EEA) PREPARED ANALYSIS (EEA) PREPARED ANALYSISTI (EEA) PREPARED ANALYSISTI (EEA) PREPARED ANALYSISTI (EEA) PREPARED
- THE REQUIREMENDED TO THE REQUIRE SUBJECT OF THE AREA TO THE REPORT OF TH ABATEMED & OVER OWER DWARDS AQUIFER. CONTRACTOR
- SHA20CONTCETOFEENASUSES FRENCIPILIECONDENESS FRENCED POILER CONTRACT PROVIDENCE AND A CONTRACT P CONSTRUCTION PLANS PRIOR TO CONSTRUCTION AND A Pril 19, 2021. Any springs and streams as identified in the Geologic Assessment are shown herein

NOTE:

CONTRACTOR SHALL UNCOVER AND VERIFY LOCATIONS, BOTH HORIZONTALLY AND VERTICALLY, OF ALL EXISTING UTILITIES ALONG THE PROPOSED ROUTE. IF A CONFLICT EXISTS BETWEEN THE PROPOSED PROJECT AND ANY EXISTING UTILITY, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT CAN BE RESOLVED.




Location Map APPROX. 1" = 2000'



TEXAS ONE-CALL 800-344-8377

NOTE TO CONTRACTOR:

CONTRACTOR IS TO FURNISH A SET OF CONSTRUCTION PLANS BACK TO THE ENGINEER AT THE END OF THE PROJECT WITH ALL DEVIATIONS NOTED IN RED INK ON THE PLAN SHEETS. CONTRACTOR SHALL NOT RECEIVE FINAL PAYMENT UNTIL COMPLETE "AS-BUILT" SET IS RETURNED TO ENGINEER.



	STE	GER	BIZZ	ZELL
ADDRESS	1978 S. AUSTIN	AVENUE	GEORGETOWN,	TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINE TBLS FIRM NO. 10		WEB STEGERBIZZELL.COM
SERVICES		>>ENGINEERS >>PLANNERS	S >>SURVEYOR	S

ITE TRIP GENERATION:

AM PEAK TRIPS RESIDENTIAL = 100 TRIPS (26 ENTRY, 74 EXIT)

PM PEAK TRIPS RESIDENTIAL = 110 TRIPS (66 ENTRY, 44 EXIT)

AVERAGE DAILY TRIPS RESIDENTIAL = 1,339 TRIPS (670 ENTRY, 669 EXIT

BENCHMARKS:

3M #1:	SCRIBED "+" ON INLET GRID NORTHING: 10210728.14 GRID EASTING: 3130639.90 ELEV: 752.25 (NAVD 88)
3M #2:	SCRIBED "+" ON INLET GRID NORTHING: 10210516.67 GRID EASTING: 3130334.428 ELEV: 755.49 (NAVD 88)
3M #3:	SCRIBED "+" ON INLET GRID NORTHING: 10211137.15 GRID EASTING: 3129960.465 ELEV: 755.84
3M #4:	SCRIBED "+" GRID NORTHING: 10211573.68 GRID EASTING: 3130076.157 ELEV: 759.79
3M #5:	SCRIBED "+" ON INLET GRID NORTHING: 10211812.17 GRID EASTING: 3130515.349 ELEV: 755.07

Warning! There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary. 2023-08-20

	Sheet #	Sheet Title
	01	COVER
	02	GENERAL NOTES
	03	PLAT (1 OF 2)
	04	PLAT (2 OF 2)
	05	EROSION & SEDIMENTATION CONTROL PLAN
	06	EROSION & SEDIMENTATION CONTROL DETAILS
	07	TREE MITIGATION PLAN
	08	TREE MITIGATION NOTES & DETAILS
	09	DEMO PLAN
	10	SITE PLAN
	11	WATER PLAN
	12	FIRE PLAN
	12	WATER & FIRE DETAILS
	13	WATER & FIRE DETAILS (CONT.)
		SEWER PLAN
	15	
	16	SEWER DETAILS
	17	SEWER DETAILS (CONT.)
	18	EXISTING DRAINAGE MAP
	19	DEVELOPED DRAINAGE MAP
	20	STORM SEWER PLAN (1 OF 3)
	21	STORM SEWER PLAN (2 OF 3)
	22	STORM SEWER PLAN (3 OF 3)
	23	STRM-A1 PLAN & PROFILE - STA. 0+00 TO 5+50
	24	STRM-A1 PLAN & PROFILE - STA. 5+50 TO END
	25	STRM-B1 PLAN & PROFILE - STA. 0+00 TO END
	26	PAVING, STRIPING, & SIGNAGE PLAN
	27	GARAGE PARKING
	28	DRAINAGE, PAVING, STRIPING, & SIGNAGE DETAILS
	29	DRAINAGE, PAVING, STRIPING, & SIGNAGE DETAILS (CONT.)
	30	DETAILED GRADING PLAN
	31	TRAFFIC CONTROL PLAN
	ARCH	
	A4-00	BUILDING ELEVATIONS
(IT)	A4-01	BUILDING ELEVATIONS
	A4-01	BUILDING ELEVATIONS
	A4-02 A4-03	BUILDING ELEVATIONS
	A4-03 A4-04	BUILDING ELEVATIONS
		BUILDING ELEVATIONS BUILDING ELEVATIONS
	A4-05	
	A4-06	BUILDING ELEVATIONS
	A4-07	BUILDING ELEVATIONS
	A4-08	BUILDING ELEVATIONS
	A4-09	BUILDING ELEVATIONS
	A4-10	BUILDING ELEVATIONS
	A4-11	BUILDING ELEVATIONS
	A4-12	BUILDING ELEVATIONS
	A4-13	BUILDING ELEVATIONS
	A4-14	BUILDING ELEVATIONS
	A4-15	BUILDING ELEVATIONS
	A4-16	BUILDING ELEVATIONS 2"x3" SPACE RESERVED FOR CITY APPROVAL STAMP
	A4-17	BUILDING ELEVATIONS
	MEP	
	E1-01	SITE POWER PLAN
	E1-02	SITE LIGHTING PLAN
	E1-03	PHOTOMETRIC PLAN
	LA	
	LS 1.0	REFERENCE PLAN AND CALCULATIONS
. I	LS 1.1	LANDSCAPE SITEWORK PLAN
le	LS 1.2	LANDSCAPE SITEWORK PLAN
И	LS 1.3	LANDSCAPE SITEWORK PLAN
И	LS 1.4	LANDSCAPE SITEWORK PLAN COG Project Number: 2023-16-SDP
И	LS 1.5	SCHEDULES AND DETAILS Project Number: 22897
<u> </u>		Shoot 01 OF 31

-16-SDP Sheet 01 OF 31

HANDICAP ACCESSIBILITY NOTES:

. TEXTURES SHALL CONSIST OF EXPOSED CRUSHED STONE AGGREGATE ROUGHENED CONCRETE, RUBBER, RAISED ABRASIVE STRIPS, OR GROOVES EXTENDING THE FULL WIDTH AND DEPTH OF THE CURB RAMP. SURFACES THAT ARE RAISED, ETCHED, OR GROOVED IN A WAY THAT WOULD ALLOW WATER TO ACCUMULATE ARE PROHIBITED.

2. FOR PURPOSES OF WARNING, THE FULL WIDTH AND DEPTH OF CURB RAMPS SHALL HAVE A LIGHT REFLECTIVE VALUE AND TEXTURE THAT SIGNIFICANTLY CONTRASTS WITH THAT OF ADJOINING PEDESTRIAN ROUTES.

3. ACCESSIBLE PARKING SPACES SHALL BE AT LEAST 8 FEET WIDE.

4. PARKING SPACES AND AISLES SHALL BE LEVEL WITH SURFACE SLOPES NOT EXCEEDING 1:50 (2%) IN ALL DIRECTIONS.

5. ACCESSIBLE AISLES SHALL BE A MINIMUM OF 5 FEET WIDE. VAN ACCESSIBLE AISLES SHALL BE A MINIMUM OF 8 FEET WIDE.

6. ADDITIONAL INFORMATION ON CURB RAMPS, PARKING SPACES AND AISLES 5. No pipe which has been used for any purpose other than the conveyance of drinking water shall MAY BE FOUND IN THE CURRENT ADDITION OF TEXAS ACCESSIBILITY STANDARDS (TAS) PREPARED AND ADMINISTERED BY THE T.D.L.R.

7. ANY PART OF THE ACCESSIBLE ROUTE WITH A SLOPE GRATER THAN 1:20 (5%) 6. Water transmission and distribution lines shall be installed in accordance with the SHALL BE CONSIDERED A RAMP. IF A RAMP HAS A RISE GREATER THAN 6 INCHES OR A HORIZONTAL PROJECTION GREATER THAN 72 INCHES, THEN IT SHALL HAVE HANDRAILS ON BOTH SIDES. THE ONLY EXCEPTION IS AT CURB RAMPS. HANDRAILS ARE NOT REQUIRED ON CURB RAMPS. CURB RAMPS SHALL BE PROVIDED WHERE EVER AN ACCESSIBLE ROUTE CROSSES (PENETRATES) A CURB. CURB RAMPS ARE GENERALLY INTERPRETED AS ONLY THE PORTION TYING DIRECTLY INTO THE ROADWAY.

8. ALL SIDEWALK CROSS-SLOPES SHALL NOT EXCEED 1:50, UNLESS A VARIANCE IS PROVIDED BY TDLR.

9. UNDER NO CIRCUMSTANCE, REGARDLESS OF WHAT IS SHOWN IN THESE PLANS, IS THE CONTRACTOR RELIEVED OF HIS SOLE RESPONSIBILITY FOR COMPLIANCE WITH ALL ACCESSIBILITY LAWS AND/OR RULES BY THE ADA, TDLR OR OTHER REGULATORY AGENCY. SEE GENERAL NOTES SHEET FOR ADDITIONAL INFO

ACCESSIBILITY NOTES

- Project shall be constructed in full compliance with the Texas Accessibility Standards (TAS) 2012.
- Slopes in the direction of pedestrian travel shall not exceed 5% (1:20) or have a cross slope greater than 2% (1:48). This shall include routes that cross-vehicular ways including but not limited pedestrian/ vehicular ways such as street intersections.
- A. Exception: Per TAS 405.8 and 68.102 (1) grades at the new sidewalks parallel to the streets shall be equal to, or less than, the street grade. Should the new sidewalks exceed the street grade, and the new sidewalk 405 are required at these conditions.
- Curb Ramps:
- A. Curb ramps shall not exceed 8.3% (1:12) in the direction of pedestrian
- B. Curb ramps flares (wings) shall not exceed 1:10.
- C. Minimum width of a curb ramp is 36". 48"deep.
- E. When truncated domes are used, the truncated dome system shall extend the full width of the curb ramp and for a minimum depth of 24" at the bottom of the curb ramp.
- Returned curb ramps shall only be used where the adjacent surface on one or both sides of the curb ramp do not allow pedestrian travel such as but not limited to stop lights, stop signs and permanently mounted waste receptacles.
- There shall be no changes in level greater than ¹/₄" on any accessible route or $\frac{1}{2}$ " with a 1:2 bevel.
- Decomposed granite surfaces, or similar Engineer-approved surfaces shall be compacted tight and maintained by the Owner at all times.
- Provide directional signage using the international symbol of accessibility when not all routes are accessible. Signage shall be placed at the beginning of the route to avoid a patron from proceeding on a non-accessible route.
- Verify that no plantings or other site elements on circulation paths would be protruding objects based on TAS 307 (protrudes more 4" and is higher than 27" from the surface and less than 80" from the surface).

Contractor shall notify the Engineer before proceeding with any Work, which is in conflict with the Texas Accessibility Standards. Contractor is financially responsible for proceeding with any Work without written direction on any clarification from the Engineer.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
WATER DISTRIBUTION SYSTEM
GENERAL CONSTRUCTION NOTES

- 1. This water distribution system must be constructed in accordance with the current Texas Commission on Environmental Quality (TCEQ) Rules and Regulations for Public Water Systems 30 Texas Administrative Code (TAC) Chapter 290 Subchapter D. When conflicts are noted with local standards, the more stringent requirement shall be applied. Construction for public water systems must always, at a minimum, meet TCEQ's "Rules and Regulations for Public Water
- 2. An appointed engineer shall notify in writing the local TCEQ's Regional Office when construction will start. Please keep in mind that upon completion of the water works project, the engineer or owner shall notify the commission's Water Supply Division, in writing, as to its completion and attest to the fact that the work has been completed essentially according to the plans and change orders on file with the commission as required in 30 TAC §290.39(h)(3).
- 3. All newly installed pipes and related products must conform to American National Standards Institute/National Sanitation Foundation (ANSI/NSF) Standard 61-G and must be certified by an organization accredited by ANSI, as required by 30 TAC §290.44(a)(1).
- 4. Plastic pipe for use in public water systems must bear the National Sanitation Foundation Seal of Approval (NSF pw-G) and have an ASTM design pressure rating of at least 150 psi or a standard dimension ratio of 26 or less, as required by 30 TAC §290.44(a)(2).
- be accepted or relocated for use in any public drinking water supply, as required by 30 TAC §290.44(a)(3).
- manufacturer's instructions. However, the top of the water line must be located below the frost line and in no case shall the top of the water line be less than 24 inches below ground surface, as required by 30 TAC §290.44(a)(4).
- 7. Pursuant to 30 TAC §290.44(a)(5), the hydrostatic leakage rate shall not exceed the amount allowed or recommended by the most current AWWA formulas for PVC pipe, cast iron and ductile iron pipe. Include the formulas in the notes on the plans.
- o The hydrostatic leakage rate for polyvinyl chloride (PVC) pipe and appurtenances shall not exceed the amount allowed or recommended by formulas in America Water Works Association (AWWA) C-605 as required in 30 TAC §290.44(a)(5). Please ensure that the formula for this calculation is correct and most current formula is in use;

 $LD\sqrt{P}$

 $Q = \frac{1}{148,000}$

• Q = the quantity of makeup water in gallons per hour,

Where:

Where:

- L = the length of the pipe section being tested, in feet,
- D = the nominal diameter of the pipe in inches, and P = the average test pressure during the hydrostatic test in pounds per square inch (psi).
- The hydrostatic leakage rate for ductile iron (DI) pipe and appurtenances shall not exceed the amount allowed or recommended by formulas in America Water Works Association (AWWA) C-600 as required in 30 TAC \$290.44(a)(5). Please ensure that the formula for this calculation is correct and most current formula is in use;

 $SD\sqrt{P}$ $L = \frac{1}{148,000}$

- L = the quantity of makeup water in gallons per hour,
- S = the length of the pipe section being tested, in feet,
- D = the nominal diameter of the pipe in inches, and • P = the average test pressure during the hydrostatic test in pounds per square inch (psi).
- grades exceed 5% in the direction of travel, ramps complying with TAS 8. Projects constructed on or after January 4, 2014 must comply with changes to the Safe Drinking Water Act that reduce the maximum allowable lead content of pipes, pipe fittings, plumbing fittings, and fixtures to 0.25 percent.
 - 9. The system must be designed to maintain a minimum pressure of 35 psi at all points within the distribution network at flow rates of at least 1.5 gallons per minute per connection. When the system is intended to provide firefighting capability, it must also be designed to maintain a minimum pressure of 20 psi under combined fire and drinking water flow conditions as required by 30 TAC §290.44(d).
- D. Top of the curb ramp must be 2% in all directions for an area 36" wide and 10. The contractor shall install appropriate air release devices in the distribution system at all points where topography or other factors may create air locks in the lines. All vent openings to the atmosphere shall be covered with 16-mesh or finer, corrosion resistant screening material or an acceptable equivalent as required by 30 TAC §290.44(d)(1).
 - 11. Pursuant to 30 TAC §290.44(d)(4), accurate water meters shall be provided. Service connections and meter locations should be shown on the plans
 - 12. Pursuant to 30 TAC §290.44(d)(5), sufficient valves and blowoffs to make repairs. The
 - 13. Pursuant to 30 TAC §290.44(d)(6), the system shall be designed to afford effective circulation of water with a minimum of dead ends. All dead-end mains shall be provided with acceptable flush valves and discharge piping. All dead-end lines less than two inches in diameter will not require flush valves if they end at a customer service. Where dead ends are necessary as a stage in the growth of the system, they shall be located and arranged to ultimately connect the ends to provide circulation.
 - 14. The contractor shall maintain a minimum separation distance in all directions of nine feet between the proposed waterline and wastewater collection facilities including manholes and septic tank drainfields. If this distance cannot be maintained, the contractor must immediately notify the project engineer for further direction. Separation distances, installation methods, and materials utilized must meet 30 TAC §290.44(e)(1-4) of the current rules.
 - 15. Pursuant to 30 TAC §290.44(e)(5), the separation distance from a potable waterline to a wastewater main or lateral manhole or cleanout shall be a minimum of nine feet. Where the nine-foot separation distance cannot be achieved, the potable waterline shall be encased in a joint of at least 150 psi pressure class pipe at least 18 feet long and two nominal sizes larger than the new conveyance. The space around the carrier pipe shall be supported at five-foot intervals with spacers or be filled to the springline with washed sand. The encasement pipe shall be centered on the crossing and both ends sealed with cement grout or manufactured sealant.
 - 16. Pursuant to 30 TAC §290.44(e)(6), fire hydrants shall not be installed within nine feet vertically or horizontally of any wastewater line, wastewater lateral, or wastewater service line regardless of construction.
 - 17. Pursuant to 30 TAC §290.44(e)(7), suction mains to pumping equipment shall not cross wastewater mains, wastewater laterals, or wastewater service lines. Raw water supply lines shall not be installed within five feet of any tile or concrete wastewater main, wastewater lateral, or wastewater service line.
 - 18. Pursuant to 30 TAC §290.44(e)(8), waterlines shall not be installed closer than ten feet to septic tank drainfields
 - 19. Pursuant to 30 TAC §290.44(f)(1), the contractor shall not place the pipe in water or where it can be flooded with water or sewage during its storage or installation.
 - 20. Pursuant to 30 TAC §290.44(f)(2), when waterlines are laid under any flowing or intermittent stream or semi-permanent body of water the water main shall be installed in a separate watertight pipe encasement. Valves must be provided on each side of the crossing with facilities to allow the underwater portion of the system to be isolated and tested.
 - 21. The contractor shall disinfect the new water mains in accordance with AWWA Standard C-651 and then flush and sample the lines before being placed into service. Samples shall be collected for microbiological analysis to check the effectiveness of the disinfection procedure which shall be repeated if contamination persists. A minimum of one sample for each 1,000 feet of completed water line will be required or at the next available sampling point beyond 1,000 feet as designated by the design engineer, in accordance with 30 TAC \$290.44(f)(3).

THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL	
THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION	
ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR	
SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED	L .
CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.	⊢

cables and other above and below ground utilities in the vicinity

contact the Engineer who shall revise the design as necessary.

companies prior to any construction in the area and determine if

There are existing water pipelines, underground telephone

of this project. The Contractor shall contact all appropriate

any conflicts exist. If so, the Contractor shall immediately

WARNING!

	NO.	REVISION	BY	DATE	DLP	
					DESIGNED BY:	DATE
ILL					АМК	
					DRAWN BY:	DATE
					CHECKED BY:	DATE
					APPROVED BY:	DATE
					ATTROVED DT.	DATE

GENERAL CONSTRUCTION NOTES

All construction shall be in accordance with the latest City of Georgetown Technical Specifications and Details.

Prior to beginning construction, the Owner or his authorized representative shall convene a Pre-Construction Conference between the City of Georgetown, Engineer, Contractor, County Engineer (if applicable), Texas Commission on Environmental Quality Field Office, and any other affected parties. Notify all such parties at least 48 hours prior to the time of the conference and 48 hours prior to beginning construction. Written construction notification must be given to the appropriate TCEQ regional office no later than 48 hours prior to commencement of the regulated activity. Information must include the date on which the regulated activity will commence, the name of the approved plan for the regulated activity, the name of the prime contractor and the name and telephone number of the contact person.

3. The Contractor shall give the City a minimum of 48 hours notice before beginning each phase of construction. call 512-930-3555.

4. No blasting will be permitted on this project.

- 5. Any existing utilities, pavement, curbs, and/or sidewalks damaged or removed will be repaired by the Contractor at his expense before acceptance of the project.
- 6. The location of any existing water and/or wastewater lines shown on the plans must be verified by the Georgetown Utility Systems Department.

7. Manhole frames, covers, water valve covers, etc., shall be raised to finished pavement grade at the Contractor's expense by a qualified contractor with City inspection. All utility adjustments shall be completed prior to final paving construction.

- 8. The Contractor is responsible for any damages to any public improvements.
- 9. Replace all destructed CMP culverts with CMP of equal size.

SEQUENCE OF CONSTRUCTION

Note: Other contractors could be working on this site. Coordinate all activities with the activities of others.

- 1. Call all affected parties at least 48 hours prior to beginning any construction to schedule a pre-construction conference and secure all required permits.
- Install temporary erosion controls prior to any clearing and grubbing. Notify the City of Georgetown when installed.
- Clear and grub site.
- 4. Install all utility mains & services.
- 5. Ensure that all underground utility installations are complete
- 6. Complete construction of driveways, parking, and buildings.
- Complete final site grading and revegetation.
- Remove and dispose of temporary erosion controls.

Complete any necessary final dress-up. PERMANENT EROSION CONTROL NOTES

- 1. All disturbed areas shall be restored as noted below: 1.a. A minimum of six inches of imported sandy loam topsoil or approved equal shall be placed in all drainage channels (except rock) and on all cleared areas. The seeding for permanent erosion control shall be applied over areas 1.b.
- disturbed by construction as follows, unless specified elsewhere: From September 15 to March 1, seeding shall be with a combination of 1 1.b.a. pound per 1,000 square feet of unhulled Bermuda and 7 pounds per 1.000 square feet of Winter Rve with a purity of 95% with 90% germination.
- From March 2 to September 14, seeding shall be with hulled Bermuda at 1.b.b. a rate of 3 pounds per 1,000 square feet with a purity of 95% with 85% germination.
- 1.c. Fertilizer shall be slow release granular or pelleted type and shall have an analysis of 15-15-15 and shall be applied at the rate of 23 pounds per acre once at the time of planting and again once during the time of establishment. 1.d. The planted area shall be irrigated or sprinkled in a manner that will not erode
- the top soil, but will sufficiently soak the soil to a depth of six inches. The irrigation shall occur at ten-day intervals during the first two months. Rainfall occurrences of 1/2 inch or more shall postpone the watering schedule for one
- Mulch type used shall be Mulch, applied at a rate of 1,500 pounds per acre. 1.e.

TEMPORARY EROSION CONTROL NOTES

1. The Contractor shall install erosion/sedimentation controls and tree protective fencing prior to any site preparation work (clearing, grubbing or excavation).

- 2. The placement of erosion/sedimentation controls shall be in accordance with the PLANS.
- Any significant variation in materials or locations of controls or fences from those shown on the approved plans must be approved by the City Engineer.

4. The Contractor is required to inspect all controls and fences at weekly intervals and after significant rainfall events to insure that they are functioning properly. The person(s) responsible for maintenance of controls and fences shall immediately make any necessary repairs to damaged areas. Silt accumulation at controls must be removed when the depth reaches six (6) inches.

Prior to final acceptance, haul roads and waterway crossings constructed for temporary Contractor access must be removed, accumulated sediment removed from the waterway, and the area restored to the original grade and revegetated. All land clearing debris shall be disposed of in approved spoil disposal sites.


6. Field revisions to the EROSION & SEDIMENTATION CONTROL PLANS may be required by the Engineer or field inspector with the Texas Commission on Environmental Quality (TCEQ) during the course of construction to correct control inadequacies. Major revisions must be approved by the TCEQ.

CITY OF GEORGETOWN HERITAGE TREE PROTECTION DURING CONSTRUCTION

- Prior to the commencement of any development, a tree protection fence constructed of approved 1. materials shall encompass the Critical Root Zone (CRZ) of any Heritage Tree. Said tree protection fence must be maintained throughout the construction process, and must also comply with Chapter 11 of this Code.
- During construction, no materials including but not limited to excess soil, vehicles, equipment, liquids, trash, or construction debris may be placed inside of the tree protection fence, nor shall the tree protection fence be altered in any way so as to increase the encroachment of the construction.
- Excavation, grading, soil deposit, impervious covering, drainage and leveling within the CRZ of Heritage Trees is prohibited unless approved by the Urban Forester. Any impervious cover proposed within the CRZ of a Heritage Tree will be reviewed on a case by case basis by the Urban Forester upon field inspections and or plan reviews. In any case, generally no more than 50% of the CRZ of any Heritage Tree can be covered with impervious cover. Any protective fencing being used around Heritage Trees may only be reduced while impervious cover activity is being done. The remainder of the protective fencing must stay intact for the duration of the project.
- Disposal or depositing of oil, gasoline, chemicals, paints, solvents or other materials is prohibited within the CRZ of Heritage Trees.
- 5. The attachment of wires, signs and ropes to any Heritage Tree is prohibited.
- 6. The location of utility service and irrigation lines inside the CRZ of Heritage Trees is only allowed when approved by the Urban Forester. If boring is used to provide underground utility access, the minimum length of the bore shall be the width of the tree's mature canopy. The minimum depth of the bore shall be specified by the Urban Forester, but in no event be less than 24" below the natural grade existing prior to any development activity within the CRZ..
- Soil disturbance or other injurious and detrimental activity within the CRZ of Heritage Trees is prohibited. At applicant's expense, an ISA Certified Arborist or their employee(s) shall be present whenever activities occur which will pose a potential threat to the health of the Heritage Tree such as pruning, or whenever any work needs to be done within the CRZ of such tree.
- Should the area within the CRZ become compacted during excavation or grading, the affected area shall be aerated. The Urban Forester shall be notified whenever any Damage or injury occurs to a Heritage Tree during construction so that proper treatment may be administered.
- 10. The Urban Forester shall be notified whenever any Damage or injury occurs to a Heritage Tree during construction so that proper treatment may be administered.
- 11. Contact the City of Georgetown's Urban Forester (512-930-6113) when tree protection is installed and prior to any fencing being removed.

CITY OF GEORGETOWN GENERAL NOTES

- These Construction plans were prepared, sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore based on the engineer's concurrence of compliance, the construction plans for construction of the proposed project are hereby approved subject to the standard Construction Specifications and Details Manual and all other applicable City, State, and Federal Requirements and Codes
- 2. This project is subject to all City Standard Specifications and Details in effect at the time of submittal of the project to the City.
- 3. The site construction plans shall meet all requirements of the approved site plan.
- 4. Wastewater mains and service lines shall be SDR-26 PVC.
- 5. Wastewater mains shall be installed without horizontal or vertical bends.
- 6. Maximum distance between wastewater manholes is 500 feet.
- 7. Wastewater mains shall be low pressure air tested and mandrel tested by the contractor according to City of Georgetown and TCEQ requirements.
- 8. Wastewater manholes shall be vacuum tested and coated by the contractor according to City of Georgetown and TCEQ requirements.
- 9. Wastewater mains shall be camera tested by the contractor and submitted to the City on DVD format prior to paving the streets.
- 10. Private water system fire lines shall be tested by the contractor to 200 psi for 2 hours.
- 11. Private water system fire lines shall be ductile iron piping from the water main to the building sprinkler system, and 200 psi C900 DR-18 PVC for all others.
- 12. Public water system mains shall be 150 psi C900 DR-18 PVC and tested by the contractor at 150 psi for 4 hours.
- 13. All bends and changes in direction on water mains shall be restrained and thrust blocked.
- 14. Fire hydrant leads shall be restrained.
- 15. All water lines are to be bacteria tested by the contractor according to the City standards and specifications
- 16. Water and Sewer main crossings shall meet all requirements of the TCEQ and the City.
- 17. Flexible base material for public streets shall be TXDOT Type A Grade 1.
- 18. Hot mix asphaltic concrete pavement shall be Type D unless otherwise specified and shall be a minimum of 2 inches thick on public streets and roadways.
- 19. All sidewalk ramps are to be installed with the public infrastructure.
- 20. A maintenance bond is required to be submitted to the City prior to acceptance of the public improvements. This bond shall be established for 2 years in the amount of 10% of the cost of the public improvements and shall follow the City format.
- 21. Record drawings of the public improvements shall be submitted to the City by the design engineer prior to acceptance of the project. These drawings shall be submitted on a flash drive or emailed through a cloud source.
- 22. Prior to the start of construction, the City shall be provided with a WPAP approval letter, WPAP recordation receipt, NOI, approved SWPPP, and contact information of the compliance inspector.
- 23. During construction, all compliance inspections and resolutions shall be copied to the City inspector upon receipt
- 24. At the completion of construction, Engineer's letter of concurrence and Notice of Termination shall be provided.
- 25. Prior to construction above the slab, Contractor to provide an all-weather drive surface of asphalt, concrete, or chip seal placed onto base material engineered to withstand 75,000 lbs. An acceptance inspection by Fire Inspections is required. 2012 IFC 503 and D102.1.



1978 S. AUSTIN AVENUE GEORGETOWN, TX 78626 TEXAS REGISTERED ENGINEERING FIRM F-181 TBPLS FIRM No.10003700 STEGERBIZZELL.COM 512.930.9412 SERVICES >>ENGINEERS >>PLANNERS >>SURVEYORS

STEGER BIZZELL

11

Texas Commission on Environmental Quality Water Pollution Abatement Plan General Construction Notes

Edwards Aquifer Protection Program Construction Notes – Legal Disclaimer

The following/listed "construction notes" are intended to be advisory in nature only and do not constitute an approval or conditional approval by the Executive Director (ED), nor do they constitute a comprehensive listing of rules or conditions to be followed during construction. Further actions may be required to achieve compliance with TCEQ regulations found in Title 30, Texas Administrative Code (TAC), Chapters 213 and 217, as well as local ordinances and regulations providing for the protection of water quality. Additionally, nothing contained in the following/listed "construction notes" restricts the powers of the ED, the commission or any other governmental entity to prevent, correct, or curtail activities that result or may result in pollution of the Edwards Aquifer or hydrologically connected surface waters. The holder of any Edwards Aquifer Protection Plan containing "construction notes" is still responsible for compliance with Title 30, TAC, Chapters 213 or any other applicable TCEQ regulation, as well as all conditions of an Edwards Aquifer Protection Plan through all phases of plan implementation. Failure to comply with any condition of the ED's approval, whether or not in contradiction of any "construction notes," is a violation of TCEQ regulations and any violation is subject to administrative rules, orders, and penalties as provided under Title 30, TAC § 213.10 (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. The following/listed "construction notes" in no way represent an approved exception by the ED to any part of Title 30 TAC, Chapters 213 and 217, or any other TCEQ applicable regulation

A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any regulated activities. This notice must include: - the name of the approved project;

> - the activity start date; and - the contact information of the prime contractor.

- All contractors conducting regulated activities associated with this project must be provided 2. with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
- If any sensitive feature(s) (caves, solution cavity, sink hole, etc.) is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. Construction activities may not be resumed until the TCEQ has reviewed and approved the appropriate protective measures in order to protect any sensitive feature and the Edwards Aquifer from potentially adverse impacts to water quality.
- No temporary or permanent hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
- Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features,
- Sediment must be removed from the sediment traps or sedimentation basins not later than when it occupies 50% of the basin's design capacity.
- Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
- All spoils (excavated material) generated from the project site must be stored on-site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the other site.
- 10. If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.
 - The following records shall be maintained and made available to the TCEQ upon request: - the dates when major grading activities occur; - the dates when construction activities temporarily or permanently cease on a portion
 - of the site: and - the dates when stabilization measures are initiated.
- 12. The holder of any approved Edward Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
 - A. any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
- any change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
- any development of land previously identified as undeveloped in the original water pollution abatement plan.

Austin Regional OniceSan Antonio Regional Onice12100 Park 35 Circle, Building A14250 Judson RoadAustin, Texas 78753-1808San Antonio, Texas 78233-4480Phone (512) 339-2929Phone (210) 490-3096Fax(512) 339-3795Fax	Austin, Texas 78753-1808 Phone (512) 339-2929	San Antonio, Texas 78233-4480 Phone (210) 490-3096
---	--	--

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

TCEQ-0592 (Rev. July 15, 2015)


GENERAL NOTES

2023-16-SD **Project No** 22897

Page 2 of 2

SHEET 02 of 31

RISE 1900 AT THE COMMONS AT RIVERY 1900 RIVERY BOULEVARD City of Georgetown, Williamson County, Texas




 protein grint in and system and circitation in heim depections jurisdication. Then the tray of congressment of the training of conversion of the addition of the parties in the first Flooding day. In particular, my change ensures of the training of conversion of the addition of the constration of the constration of the addition of the constration of the constration of the constration of the constration of the addition of the constration of the constration of the constration of the addition of the constration of the constration of the constration of the addition of the constration of the addition of the constration of the constration of the constration of the constration of the addition of the constration of the cons	
66*15'48'' W 112.35' to a corner of said Lot 1, said corner being marked with a set stake; and 56*2718'' W 112.56' to the west corner of said Lot 1, said corner being marked with a found sr e along said southerly boundary. F N 335-39' 4'' E 70.53' along the northwest boundary of said Lot 1 to the southerly boundary at along said southerly boundary of Rivery Boulevard as follows: B a correct terming to the right with an arc length of 336.33' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , and a curve turning to the left with an arc length of 235.32' , with a radius of 546.07' , if a boing marked with a set stake; and a set aclaw; and a curve turning to the northeast boundary of said Lot 1, said corner being marked with a set stake. 53''10''8'' E 143.05' to the point for not with allumitum cap marked with a set stake. 53''10''8'' E 143.05' to the point of the southwest boundary of said Gabriel Heig 66'0''4'' E 53.01' , i add corner being marked with a set stake. 55''10''5'' 53.01 , to a corner of said Lot 1, said corner being marked with a found <i>Y''</i> iron rod 66'''4'' E 53.01' a state. 55''' 54.35''' 55'''''''''''''''''''''''''''''''	of said Lot 1 and the southeast boundary of said Block 4 of Gabriely Heing marked with a set states. NEWER along the nonthwest line of said Lot 1 as follows: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 12324 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103346 ha a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103345 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103345 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103345 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103345 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB39F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30F E 103341 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30A1 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30A1 to a cormer of said Lot 1, said cormer being marked with a set states: NEWTB30A1 to a c
PLAT (1 OF 2) for LOOD AT THE COMMONS AT R 1900 RIVERY BOULEVARD of Georgetown, Williamson County,	03

P:\22000-22999\22897 Novak Williams Plaza\CAD\Plans\PLAT (2 OF 2).dwg, PLAT (2 OF 2), 8/20/2023 2:21:35 PM	WARNING! There are existing water pipelines, underground teleph cables and other above and below ground utilities in the of this project. The Contractor shall contact all approp companies prior to any construction in the area and de any conflicts exist. If so, the Contractor shall immediat contact the Engineer who shall revise the design as perior.	ne vicinity riate etermine if tely
000-22999\22897 Novak Williams Plaza\CAD\Plans\F	THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.	NO.

NO.	REVISION	BY	DATE	DLP	
				DESIGNED BY:	DATE
				АМК	
				DRAWN BY:	DATE
				CHECKED BY:	DATE
				APPROVED BY:	DATE

		Dor# 202305244A
OWNER'S CERTIFICATE	SURVEYOR'S CERTIFICATE	PLANNING DIRECTOR
STATE OF TEXAS {	STATE OF TEXAS	I, SOFIA NELSON, PLANNING DIRECTOR OF THE CITY OF GEORGETOWN, TEXAS, DO HEREBY CERTIFY THIS IN A THEADDOLOGY FOR THING OF A THEADDOLOGY FOR THEADDOLOGY FOR THING OF A THEADDOLOGY FOR
KNOW ALL MEN BY THESE PRESENTS COUNTY OF WILLIAMSON {	COUNTY OF TRAVIS	FLATER REFERENCE FOR FILING OF RECORD WITH THE COUNTY CLERK OF WILLIAMSON COUNTY, LEXAS.
I, PDC WILLIAMS PLAZA, LTD. ACTING BY AND THROUGH MARK ANDREW PAPPAS, MANAGER, SOLE OWNER OF THOSE CERTAIN 2.010 ACRE AND REMAINING PORTION OF 12.693 ACRE TRACTS OF LAND SHOWN	I, MICHAEL JACK NEEDHAM, A REGISTERED PROFESSIONAL LAND SURVEYOR, LICENSED BY THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECTLY MADE FROM AN ACTUAL SURVEY	SOFIAINESON. PLANNING DIRECTOR






PLAT (2 OF 2) for RISE 1900 AT THE COMMONS AT RIVERY 1900 RIVERY BOULEVARD City of Georgetown, Williamson County, Texas




Project No: 22897

2023-16-SDF



TYPE OF STRUCTURE	REACH LENGTH
SILT FENCE	N/A
	200 FEET
	100 FEET
	50 FEET
TRIANGLE FILTER DIKE	100 FEET
	50 FEET
ROCK BERM *, **	500 FEET


responsibility for appropriate





Project No 22897

2023-16-SD



	- E	
0	1	50 100
	SCAL	E: 1" = 50'
	LEG	GEND
- W		PROPOSED WATER LINE
- WW	/L -	PROPOSED SEWER LINE
— SD) —	PROPOSED STORM SEWER LINE
— SD) —	PROPOSED STORM SEWER LINE (BY OTHERS)
- W		EXISTING WATER LINE
- \\\\	/∟ -	EXISTING SEWER LINE
-123	3 –	PROPOSED CONTOUR
123	3∙ –	EXISTING CONTOUR
		ACCESSIBLE ROUTE
		GATE VALVE

SITE DATA:

LAND AREA:	272,294 S.F. (6.251 AC.)
LOT BUILDING COVERAGE:	44.8% (122,056 S.F./272,294 S.F.)
EXISTING IMPERVIOUS COVER:	40.1% (109,061 S.F./272,294 S.F.)
PROPOSED IMPERVIOUS COVER:	74.2% (201,932 S.F./272,294 S.F.)
MAX. IMPERVIOUS COVER:	80% per ORD 2022-75 (2021-12-PUD)
TOTAL G.F.A.:	256,105 S.F.
BUILDING TYPE:	V-A (Residences) w/ Fire Walls & I-A (Parking Garage)

PARKING REQUIREMENTS

RESIDENTIAL			
BUILDING UNIT # BR	1-BR	2-BR	3-BR
TOTAL # OF UNITS	188	107	0
MULTIPLIER	1.5 SP.	2 SP.	2.5 SP.
PARKING SPACES (REQ.)	282 SP.	214 SP.	0 SP.
5% ADDITIONAL USE	14 SP.	11 SP.	0 SP.
TOTAL	296 SP.	225 SP.	0 SP.

10% MIXED-USE REDUCTION PER ORD 2022-75 (2021-12-PUD) = 521 SP. * 10% = 52 SP.

TOTAL RESIDENTIAL PARKING SP. (REQ.) = 296 SP. + 225 SP.+ 0 SP. - 52 SP. = 469 SP.

PARKING PROVIDED: 80 - 9'x18' PARKING SP. 504 - 9'x18' PARKING GARAGE SP. 584 TOTAL SP.

PER SECTION 6.06.020 OF UDC

TOTAL # OF DWELLING UNITS = 295 UNITS

MINIMUM # OF AMENITIES REQUIRED = 5 TOTAL # OF AMENITIES PROVIDED = 5 (SWIMMING POOL, PRIVATE FITNESS FACILITY, CLUBHOUSE AREA, DOG PARK, SPORT COURT)

DIMENSIONAL SITE PLAN NOTES:

- All lighting fixtures shall be designed to completely conceal and fully shield, within an opaque housing, the light source from visibility from any street right-of-way. The cone of light shall not cross any adjacent property line. The illumination shall not exceed two (2) foot candles at a height of three (3) feet at the property line. Only incandescent, fluorescent, color-corrected high-pressure sodium or metal halide may be used. All vehicle or pedestrian access shall be sufficiently lighted to ensure security of property and persons.
- All roof, wall and ground mounted mechanical equipment must be screened in accordance with Chapter 8 of the UDC. If roof and wall mounted equipment of any type including duct work and large vents is proposed, it shall be shown on the Site Plan and screening identified. Screening of mechanical equipment shall result in the mechanical equipment blending in with the primary building and not appearing separate from the building and shall be screened from view from any rights-of-way or adjoining properties.
- Per Chapter 8, the dumpster enclosures must be one (1) foot above the height of the waste container. Use protective poles in corners and at impact areas. Fence posts shall be of rust protected metal or concrete. A minimum 6" slab is required and must be sloped to drain. The enclosure must have steel framed gates with spring loaded hinges and fasteners to keep closed. Screening must be on all four (4) sides by masonry wall or approved fence or screening with opaque gates.

SITE PLAN RISE 1900 AT THE COMMONS AT RIVERY **1900 RIVERY BOULEVARD** City of Georgetown, Williamson County, Texas





Project: Rise 1900 Simulation Run: EX 2-YR SCS
 Start of Run:
 09Apr2020, 00:00
 Basin Model:
 Existing

 End of Run:
 10Apr2020, 00:00
 Meteorologic Model:
 CoA SCS 2 Yr 24 Hr

 Compute Time:DATA CHANGED, RECOMPUTE
 Control Specifications: 24 Hours
 Volume Units: 🗿 IN 🔿 ACRE-FT Show Elements: All Elements ~ Sorting: Hydrologic 🗸 Drainage Area Peak Discharge Time of Peak Hydrologic Volume Element (MI2) (CFS) (IN) 0.009798 11.4 09Apr2020, 12:12 BASIN A 2.33

End of R	Run: 09Apr2020, 00:00 un: 10Apr2020, 00:00 Time:DATA CHANGED, R	Meteoro		Existing CoA SCS 10 Y :24 Hours	'r 24 Hr
how Elements: All El	ements 🚽	Volume Units: O 🕅 🔿	ACRE-FT	Sor	ting: Hydrologi
how Elements: All El Hydrologic Element	Drainage Area (MI2)	Volume Units: OIN C Peak Discharge (CFS)	ACRE-FT		ting: Hydrologi Volume (IN)

		Project: Rise 1	1900 Simulation Run:	EX 25-YR SCS	
Show Elements:	End of Run: Compute Time	09Apr2020, 00: 10Apr2020, 00: :16May2023, 11 V	0:00 Basin Model: Existing 0:00 Meteorologic Model: CoA SCS 25 Yr 24 Hr 11:18:47 Control Specifications:24 Hours	r 24 Hr Sorting: Hydrologic N	
Hydrologic Element	Dra	iinage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
BASIN A	0	0.009798	31.1	09Apr2020, 12:11	6,22


Project: Rise 1900 Simulation Run: EX 100-YR SCS Start of Run: 09Apr2020, 00:00 End of Run: 10Apr2020, 00:00 Compute Time:DATA CHANGED, RECOMPUTE Basin Model: Existing Meteorologic Model: CoA SCS 100 Yr 24 Hr Control Specifications:24 Hours Volume Units: O IN O ACRE-FT Show Elements: All Elements Sorting: Hydrologic Peak Discharge Hydrologic Drainage Area Time of Peak Volume Element (IN) (MI2) (CFS) 43.2 09Apr2020, 12:11 8.70 BASIN A 0.009798

WARNING! There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.	
NO	

					Sele	ct RCN from Table 2-7	of DCM																					
						Lawn																						
				Building Pavement		(Good)					Time of Conce	ntration																
			Hydrologic Soil Group [%]	98 98	91 8	7 78 80	84 8	Э					Sheet				Shallow Concentr	trated - Unp	paved		Shallow Concer	trated - Pave	ed		Channel	Storm Drain		Tote
Basin	Area [s.f.]	Area [ac.] Area [sq. mi.]	A B C D % Chec	k IC-1[s.f.] IC-2[s.f.] I	C-3 [s.f.] IC-4 [s.f.]	PC-1[s.f.] PC-2[s.f.]	PC-3[s.f.] PC-4[s.f] Total IC [s.f.]	Total IC % % Check	Composite RCN	Elev-Start [ft]	Elev-Stop [ft]	L[ft] n	P[in] s	ft/ft] Tt-sheet [n	nin] Elev-Start [f	ft] Elev-Stop [ft] L	L [ft] s [f	ft/ft] Tt-SCFu [min]	Elev-Start [ft] Elev-Stop [ft] L	[ft] s [ft/	/ft] Tt-SCFp [n	in] L[ft] Q[r	fs] A [ft^2] Wp	[ft] V [ft/s] Tt-ch	nnel [min] Tc	[c [min] T
kisting A	27316	6.27 0.009798 C	% 0% 0% 100% OK	0 110,043	0 (0 163,122	0	110043	3 40.28% OK	80.0	757	755.7	150 (.13 4.2 0.	08667 1	1.74 755	5.7 754	184	0.009 1.98	8 75	4 754	0 0	0.000	0 00.0	0 0	0 5	0.00	16.72

	NO.	REVISION	BY	DATE	DLP	
					DESIGNED BY:	DAT
THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION					AMK	
ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR					DRAWN BY:	DAT
SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.						
					CHECKED BY:	DAT
					APPROVED BY:	<u></u>
					ATTROVED DT.	DAT

.4







2023-16-SDF

Project: Rise 1900 Simulation Run: PR 2-YR SCS

Start of Run: 09Apr2020, 00:00 Basin Model: Proposed

Show Elemen


	End of Run: Compute Time		영양 귀엽 감정 것이 다 같아요	Meteorologic Model: Control Specification		
ow Elements:	All Elements \sim	2	Volume Units	:: 🔿 🖪 🔿 ACRE-FT	r Sortir	ng: Hydrologic
Hydrologic Element	Dra	inage Area (MI2)	8	ischarge Tin (FS)	ne of Peak	Volume (IN)

Element	(MI2)	(CFS)		(IN)
ASIN A	0.005063	9.8	09Apr2020, 12:05	3.37
ASIN B	0.003015	5,9	09Apr2020, 12:05	3.39
ASIN C	0.001689	3.1	09Apr2020, 12:07	3.37

1	Start of Run: 0 End of Run: 1 Compute Time:0	10Apr2020, 00: 13Aug2023, 11:	00 Meteorolo	gic Model: ecifications			Hydrologic ~
						253	
Hydrologic Element	Contraction of the second s	age Area MI2)	Peak Discharge (CFS)		ne of Peak		Volume (IN)
Element	0	S70 (1997)	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Tir			3.53.600.000
	0.0	MI2)	(CFS)	Tir 09Ap	ne of Peak		(IN)


		Project: Rise	1900 Simulation Run	PR 25-YR SCS		
Start of Run: 09Apr2020, 00:00 Basin Model: Proposed End of Run: 10Apr2020, 00:00 Meteorologic Model: CoA SCS 25 Yr 24 Hr Compute Time:03Aug2023, 11:23:19 Control Specifications:24 Hours Show Elements: All Elements Volume Units: Image: Control Specification Start Sorting: Hydrologic						
Hydrologic	Dra	ainage Area	Peak Discharge	Time of Peak	Volume	
Element		(MI2)	(CFS)		(IN)	
Constanting of the	((MI2) 0.005063	(CFS) 21.9	09Apr2020, 12:03	(IN)	
Element BASIN A BASIN B				09Apr2020, 12:0 09Apr2020, 12:0	(IN) 5 7.57	

Show Elements:	Compute Time	10Apr2020, 00: :03Aug2023, 11:	00 Basin Model: 00 Meteorologic	Proposed Model: CoA SCS ifications:24 Hours	100 Yr 24 Hr	Hydrologic ~
			Coldinic Collication and and	COMPANY 1 1	Sol ung.	Hydrologic V
Hydrologic Element		ainage Area (MI2)	Peak Discharge (CFS)	Time of Pea		Volume (IN)
Hydrologic Element	: Dr	ainage Area	Peak Discharge	1	k	Volume
Hydrologic	Dr	ainage Area (MI2)	Peak Discharge (CFS)	Time of Pea	k 2:05	Volume (IN)




THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.

NO.	REVISION	BY	DATE	DLP	
				DESIGNED BY:	DAT
				АМК	
				DRAWN BY:	DATI
				CHECKED BY:	DAT
				APPROVED BY:	DAT



<u> </u>	
ctly p	
stric	
C. is	
⊇ ບົ	
ERIN	
IGINE	
LL EN	
IZZE	
ж Ш	
EGER	
of ST	
ion	
rmissi	
n pe	
writte	
out v	
with	
part	
or in	
ole	
ň	
ngs ir	
drawir	
ese	
of the	
euse c	
or rei	
noi	
oduc	
Repr	
.	
prepared.	
wer	
they	
/hich	
for wh	
Ę.	
site fo	
nal site	
original site	
o the original site	
to the original site	
cted to the original site	
by restricted to the original site	
y restricted to the original site	
is hereby restricted to the original site	
awings is hereby restricted to the original site	
drawings is hereby restricted to the original site	
these drawings is hereby restricted to the original site	
of these drawings is hereby restricted to the original site	
ne use of these drawings is hereby restricted to the original site	
The use of these drawings is hereby restricted to the original site	
, INC. The use of these drawings is hereby restricted to the original site	
, INC. The use of these drawings is hereby restricted to the original site	
RING, INC. The use of these drawings is hereby restricted to the original site	
L ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
ZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
& BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
EGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
f STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
ty of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
f STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
roperty of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
ole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
ngs are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	
awings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site	

WARNING! There are existing water pipelines, underground telephones and other above and below ground utilities in the of this project. The Contractor shall contact all appropriation of this project. The Contractor shall contact all appropriation of this project. The Contractor shall contact all appropriation of this project. The Contractor shall contact all appropriation of the project. The Contractor shall contact all appropriation of the project. The Contractor shall contact all appropriation of the project. The Contractor shall contact all appropriation of the project. The Contractor shall revise the design as necessary contact the Engineer who shall revise the design as necessary.	vicinity ate ermine i ly				Image: Second
	NO.	REVISION	BY	DATE	
THESE CONSTRUCTION PLANS HAVE BEEN PREPARED TO FULFILL THE REQUIREMENTS FOR THE TCEQ FOR WATER POLLUTION ABATEMENT OVER THE EDWARDS AQUIFER. CONTRACTOR SHALL CONTACT THE ENGINEER FOR ADDITIONAL DETAILED	A	OWNER COMMENTS - ADDED STORM SEWER SHEET	DLP	7/28/23	DLP DESIGNED BY: AMK DRAWN BY:
CONSTRUCTION PLANS PRIOR TO CONSTRUCTION.					CHECKED BY:
	1				






STORM SEWER PLAN (2 OF 3) RISE 1900 AT THE COMMONS AT RIVERY **1900 RIVERY BOULEVARD** City of Georgetown, Williamson County, Texas

2023-16-SD Project No: 22897

> SHEET 21 of 31




STORM SEWER PLAN (3 OF 3) for RISE 1900 AT THE COMMONS AT RIVERY 1900 RIVERY BOULEVARD City of Georgetown, Williamson County, Texas



2023-16-SD

Project No: 22897





rohibitec
trictly p
. is s
ING, INC
IGINEER
ELL EN
& BIZZ
STEGER
on of S
ermissi
ritten p
hout w
part wit
or in p
whole
vings in
iese drawi
of thes
reuse
ction or
Reproduc
ed. R
prepare
y were
ich they
for which
ial site
he origin
to t
estricted
iereby re
gs is he
drawinç
these
use of
C. The
ING, INC.
GINEERI
ZELL EN
& BIZZ
STEGER
ty of
prope
the sole
js are t
drawing
These


WARNING! There are existing water pipelines, underground telephor cables and other above and below ground utilities in the of this project. The Contractor shall contact all appropria companies prior to any construction in the area and dete any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as nece	vicinity te rmine if y	N THE REAL PROPERTY IN THE REAL PROPERTY INTERNAL PROPERT
	NO.	

	RUCTION PLANS H		
ABATEMENT	OVER THE EDWAR	DS AQUIFER. CO	NTRACTOR
	CT THE ENGINEER ON PLANS PRIOR T		


NO.	REVISION	BY	DATE	DLP	
				DESIGNED BY:	DATE
				АМК	
				DRAWN BY:	DATE
				CHECKED BY:	DATE
				APPROVED BY:	DATE








SHEET **23** of 31






SHEET 24 of 31


2023-16-SD


Project No: 22897






2023-16-SD









		Stage Storage	Table		
Water Surface Elevations	Peak Discharge (cfs)	Stage (ft msl)*	Area (sf)	Incremental Volume (cf)	Storage (cf)
		750.30	13,444.24	95.46	90.74
		751.00	14,794.50	1,469.64	9,971.18
		752.00	16,800.30	3,319.30	25,762.04
WQE		752.20	17,211.13	1,710.82	29,163.18
		753.00	18,886.75	1,878.06	43,598.99
2 Y R - WSE CFS	21.3	753.90	20,833.52	2,072.38	61,468.27
		754.00	21,053.86	2,094.37	63,562.64
10 Y R - WSE CFS	39.1	755.00	23,301.62	2,318.74	20,145.38
25 Y R - WSE CFS	49.2	755.50	24,455.75	4,844.74	32,084.00
		756.00	25,630.04	2,551.18	44,604.72
100 YR - WSE CFS	62.9	756.40	26,584.00	2,646.42	55,047.17
		756.50	26,824.50	2,670.43	57,717.59
		756.60	27,065.81	2,694.52	60,412.11
		756.70	27,307.93	2,718.69	63,130.80
		756.80	27,550.85	2,742.94	65,873.73

					2 YEAR	STORM	10 YEAI	RSTORM	25 YEAI	RSTORM	100 YEA	RS
Drainage					Runoff Per	Routed	Runoff Per	Routed	Runoff Per	Routed	Runoff Per	
Area Basin	Drainage	Base Curve		Impervious	Drainage	Cumulative	Drainage	Cumulative	Drainage	Cumulative	Drainage	c
Designation	Area	Number CN	Lag Time	Cover	Area	Runoff	Area	Runoff	Area	Runoff	Area	
	(ac)		(min)	%	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	(cfs)	
EX 1	3.717	80	9.67	10.00%	10.40		18.50		23.90		32.70	
EX 2	2.875	80	12.92	80.00%	9.60		15.10		18.70		24.70	
EX 3	6.100	80	10.87	27.50%	16.30		30.40		39.90		55.40	
HEC-HMS SUM	MARY: DEVEL	OPED CONDITO	NS			2 YEAR	STORM	10 YEAR	STORM	25 YEAR	STORM	
Drainage						RunoffPer		Runoff Per		Runoff Per		\vdash
Area Basin	Drainage	Base Curve		Cumulative	Impervious	Drainage	Detention	Drainage	Detention	Drainage	Detention	
	Area	Number CN	Lag Time	Area	Cover	Area	Release	Area	Release	Area	Release	
Designation		-			-					1		4
Designation	(ac)		(min)	(ac)	%	(cfs)	cfs)	(cfs)	(cfs)	(cfs)	(cfs)	
Designation DA 1	(ac) 12.69	80	(min) 3.60	(ac)	% 65.78%	(cfs) 39.20	(cfs)	(cfs) 71.10	(cfs)	(cfs) 88.40	(cfs)	


/23/2023 10:07 AM \DWG-46\4670-21.455\DWG\CIVIL C3D 2018\SWP\4670-21.455POND.DWG






		Į				
0	25	50	10	00	150	
	GRAF	PHIC S	CALE IN	FEET		
		G				
G <u>EL</u> <u>TW</u>	B. EM© PP• LS WMO WV& ICV& FH CO MHO TSC I TSP• TELE I FP• SIGN IRS (C.M.) A OHL - 612.33 C 612.33 C 613.50 C 614.00 M.C.		BOLLARD ELECTRIC M POWER POL LIGHT STAN WATER MET WATER MET WATER VAL RRIGATION FIRE HYDRA CLEANOUT MANHOLE TRAFFIC SIG TRAFFIC SIG TRAFFI	IETER IDARD ER IDARD ER CONTROL ANT GNAL CON GNAL CON GNAL POL BOX IT GN IT CON ROD CO KOCH" IG IT IN IN IN IN IN IN IN IN IN IN	ITROL E CAP SET MENT INE ON ELEVATION CURB ELEVA TION EVATION WALL ELEVA ELEVATION ALL ADE	ATION ATION ECTION

PROPERTY	TEST METHOD	UNIT	SPECIFICATION
			<u>,</u>
PERMEABILITY	ASTM D-2434	CM/SEC	1 x 10 ⁻⁶
PLASTICITY INDEX OF CLAY	ASTM D-423 & D-424	%	NOT LESS THAN 15
LIQUID LIMIT OF CLAY	ASTM D-2216	%	NOT LESS THAN 30
CLAY PARTICLES PASSING	ASTM D-422	%	NOT LESS THAN 30
CLAY COMPACTION	ASTM D-2216	%	95% OF STANDARD PROCTOR DENSITY



PK-4670-21.455POND.DWG


9 OF 16



023 10:08 AM -46\4670-21.455\DWG\CIVIL C3D 2018\SWP\4670-21.455P

JASOMERA 8/23/2023 1 M.\DMC_46\


PK-4670-21.455POND.DWG



	DOCU SUPERV 108900 OF A PROPE RESPC OFFE	WILLIAMS PLAZA	REVISIONS	SNC	,	
S ET NO	LAYTI SEAL / MENT ISION OF SEALEI RENSIBLE NSE NC	1201. 1205. 1301 WILLIAMS DRIVE	NO. DATE DE	DESCRIPTION	BY	
1	WAS CLAY /24/2 D DOO DTIFIC/ ENO NDEF					a Westwood company
1	ARIN AUTH TON J. GINEL CUMEL ATION GINEL	GEORGETOWN, WILLIAMSON COUNTY, TX			87	8701 N. MOPAC EXPY = STE. 320 = AUSTIN. TX 78759 = 512.485.0831
OF	G CO HORI STR ALT T E R E I				;	TX RFG FNGINFFRING FIRM F-469
MA 202 - 16	DN TI ZEDE OLLE, ERAT WITHO O IS EXA CT.	BATCH POND DETAILS 1 OF 3				TX REG SURVEYING FIRM I S-10008000
23	BY P.E. ION JUT THE AN S					

2022-25-SWP

PK-4670-21.455POND.DWG



3RUCE 24/2023 4:17 PM DWG-46/4670-21 455/DWG/CIVII C3D 2018/SI

M: \DWG-46

WILLIAMS PLAZA
1201, 1205, 1301 WILLIAMS DRIVE
GEORGETOWN, WILLIAMSON COUNTY, TX

2022-25-SWP

PK-4670-21.455POND.DWG

smartPOND Valve SPECIFICATION Continuously Monitored Automated Stormwater System with Valve

1. Introduction

The following specifications describe the components, general functions, and applications of a smartPOND Continuously Monitored Automated Stormwater System (C-MASS) with Valve. The system functions as an electronically controlled, solar powered stormwater management device, providing precision management capabilities and real-time data. Using sensors, solar power, an electronic actuator, and an internet-based control interface, the smartPOND valve connects to a specialized perforated riser inside the stormwater impoundment to enable managers to precisely control water retention and detention automatically or in real time.

2. smartPOND Valve Applications in Stormwater Management

The smartPOND value is a device for active Stormwater management. As opposed to passive devices such as floating skimmers or stationary weirs, active water management dramatically increases the efficiency and effectiveness of a detention or retention pond. Where a passive stormwater detention system allows water to leave immediately upon collection, the smartPOND valve can detain newly caught Stormwater and allow it to settle for a programmed period before automatically dewatering the impoundment completely. For stormwater retention systems, it is possible to manage the treatment volume while maintaining a specified amount of capacity for flood storage or other use.

2.1 Pre-Programmed Control

Many functions can be pre-programmed without any human interactions, leaving the valve to automatically receive commands based on environmental conditions and respond as programmed.

2.1.1 Batch Detention Function for Stormwater Quality

The smartPOND valve meets TCEQ Batch Detention specifications for a 91% Total Suspended Solid removal rate. The function proceeds as follows. With the valve in the closed position and the impoundment dry, the system will stand by and wait for a water collection event. At the first sign of water collection, the unit will begin a 12-hour detention timer. At the end of the 12-hour detention period, the valve will open and release all of the water that has been collected. After the water level drops to 0", the valve will remain open for an additional 2 hours to facilitate final drainage, then return to the closed position to stand by for the next water collection event.

2.1.2 Predevelopment Hydrograph Function for Flood Control

The smartPOND valve predevelopment hydrograph function takes in site specific variables to determine a maximum release rate based on predevelopment conditions. The valve reads water depth in the pond every 15 minutes to determine the maximum release rate desirable to ensure the impoundment neither overtops, nor exceeds its maximum release based on predevelopment flows.

2.1.3 Hazmat Function for Spill Containment

smartPOND when specified for hazmat spill containment can be equipped with pollutant specific sensors that when triggered automatically close the valve until the command is overridden.

2.2 Real Time Monitoring

smartPOND comes standard with telemetry available on each unit and access to the user app available at no additional cost for 1 year. This option allows for real time monitoring of the unit and the data that comes along with it. From the real time monitoring app, a user can:

- Control the valve, either open or close See the water level
- See if trash or debris is surrounding the inlet
- Get maintenance alerts (Low Battery, Valve Failure, Etc.)
- Maintain specified water level

3. Components

The smartPOND valve may be implemented either above or below ground, and is comprised of the following components:

3.1 Hardware and Configuration

The standard smartPOND valve features a cast 6" valve. An extended spool and mounting flange on each side of the valve allows it to be attached to the outfall pipe in various configurations. The valve is actuated with an electric motor connected by an extendable drive shaft for underground applications.

For above ground applications, the entire system including all necessary components for operation assemble into one kit and are housed under a single lockable steel enclosure with the solar panel mounted on top. In this configuration, the unit can be installed on a stable, level pad and be bolted onto the back of the outfall pipe with six $\frac{3}{4}$ " bolts and then switched to the "ON" position.

For underground applications, the valve is installed in a vault or concrete encasement as needed. An extended drive shaft connects between the underground valve and the rest of the components, including the motor and all electronics, which are housed in the lockable steel enclosure directly above ground.

3.2 Electronics and Software Specifications

- Main board The main board of the smartPOND valve's electronics box serves as the main connection terminal for all sensors and additional control boards • Motor Controller Board - The motor controller board of the smartPOND valve regulates the connection between the battery and the motor and receives inputs from the main
- board to control motor direction. It also powers the main board. • Motor - The smartPOND valve's motor operates on 12-volts and has two wires connecting to the motor controller board. It is mounted on a bracket and connects to the directly to the valve with a driveshaft.
- Battery The smartPOND value is powered by a 12-volt, 30 amp/hour gel battery. Two terminals at the top connect the power wires to the motor controller board and the solar charge controller to the battery.
- Solar Panel The solar panel of the smartPOND value is 12-volts with 15 watt charging capability. It connects to a solar charge controller which regulates the voltage and current before connecting with two wires to the positive and negative battery terminals.
- Sensors • Pressure Transducer - The water level sensor is a pressure transducer sensor capable of staying submersed in water indefinitely. It mounts on the side of the smartPOND valve's center spool.
- Valve position sensor A proximity sensor senses the position of the valve's drive shaft in order to control and determine the position of the valve. (Optional)
 - Cell data modem A cellular data modem will be required for real time control and alert options as well as predevelopment hydrograph functions. • Hydrocarbon Sensor - This optional sensor may be fitted to the smartPOND valve to perform specific functions based on the presence of hydrocarbon contamination.

4. Real Time Monitoring Interface (optional)

If the real time monitoring option is selected, the smartPOND valve may be monitored in real time through the Autoflow app. Live and historical data from each unit may be viewed in the app, as well as alerts (detailed in section 5).

4.1 Accessing unit data

To access live and historical data in the Autoflow app, select the unit of interest on the home page by clicking on the unit's name. From there, select the "Data" button, and the data page for that unit will be displayed.

4.2 Sending a command

To send a remote-control command to the SmartPOND valve, click the "Send New Command" button on the unit's home page. The unit's current position will be displayed at the top. To change the unit's position, simply select "OPEN" or "CLOSE". Within 1-3 minutes, the unit will move to the new position and update its status in the app.

5. Alerts

- The smartPOND valve will indicate the following alerts by illuminating an exteriorly visible red LED light
- Low battery
 - Loss of function Valve malfunction
 - Hydrocarbon contamination (optional)
- If the telemetry option is selected, the unit will upload the above alerts to the Autoflow app and notify the operator via text or email.

6. In Case of Failure

To bypass the smartPOND valve's normal automated functions and control the valve position in case of failure:

6.1 Removal of motor and manual direct control

In case of a total electronic or motor failure, the motor and motor bracket can be uninstalled together by removing the two bolts at the bottom of the motor bracket. With the motor and motor bracket removed, the output shaft on the butterfly valve can be manually controlled with a socket wrench, or any other tool that can grip the output shaft.

7. Additional Components List

7.1 Perforated Riser

The smartPOND valve system includes a stackable perforated steel riser which installs on the inlet side of the outfall pipe within the impoundment area. The perforated riser features an 8-inch steel perforated square tube within a 24" round steel mesh tube. At the bottom of the 8-inch square tube, there is a female threaded fitting for a six inch PVC outfall pipe to connect. The steel tube is perforated with 1-inch holes every 4" on center to the height of the impoundment.

7.2 Trash Cage

The trash cage attaches to the perforated riser with a coupling and calder pin. The trash cage will be comprised of steel banding and a 1.5" x 1.5" mesh to prevent floatable's and other contaminants from entering and clogging the perforated riser. The trash cage will sit 0.5" above the bottom of the impoundment to allow the last 0.5" out of the impoundment.

7.3 Valve Stem Extension

The drive shaft/valve stem of the smartPOND system may be extended to any length necessary for instances where the valve will be in an underground vault or manhole. The valve stem will connect the valve to the above ground controls.

8. Maintenance

8.1 Grease The smartPOND valve includes a grease fitting on the valve itself which should be greased twice per year. It is also recommended that a thick, mildly heat-resistant grease be used to avoid grease melting out of the groove in warmer temperatures.

8.2 Flange Bolts

There are 6 bolts connecting the smartPOND valve's flange to the outfall pipe or fixture. During routine maintenance intervals, these bolts should be checked for tightness. All bolts should be tightened evenly.

8.3 Perforated Riser

Silt, sediment, and debris can build up around the perforated riser with time. An annual inspection of the unit is necessary to ensure that excess debris or sediment has not limited the drainage capacity of the perforated riser. To access the perforated riser for maintenance, lift the trash cage off of the riser, dig out any accumulated sediment, and clear all perforations.

8.4 Trash Cage

As a part of routine maintenance, it is advisable to remove trash and debris that has accumulated on the trash cage and properly dispose.

8.5 Solar Panel

On all inspection visits, it is necessary to confirm that the solar panel is facing south and is well secured. The solar panel is commonly utilized by birds and insects. It is important to keep the surface clean of bird litter, insect nests and debris in order to maintain optimal performance.

8.6 Battery

Over time, battery terminals may corrode. Check annually for corrosion and clean as needed. The battery should be replaced every 4 to 6 years.

8.7 Storage The smartPOND valve is shipped in a near-fully assembled configuration and should be stored likewise. The systems are transported and stored on pallets and must remain secured via straps or steel bands to said pallet at all times. The solar panel is not installed at times of transport or storage and should not be installed until the unit is ready to begin operation. The battery may be stored inside the electronics box and if removed, should never be stored on a concrete surface.

9. Installation

The smartPOND valve can be installed in a near-completely assembled configuration. Only the solar panel should be removed during the installation process. There are several ways to install the smartPOND valve with the key being structured support.

9.1 Structural Support

If the smartPOND valve is mounted to a steel pipe in an above ground/fully assembled configuration, the weight of the unit may be supported by the steel pipe. For plastic or concrete pipes, it is recommended that the weight of the unit be supported by either a concrete pad or steel frame. For below ground installations, the upper unit (electronics and actuator) should be fastened to the surface of the concrete vault. For vault installations, see design details for standard vault design.

10. Important Safety Information and Warnings:

- Always keep hands clear of the valve and motor when unit is in operation.
- Turn the power switch off when doing any electrical work.
- Do not enter the water when the device is actively draining water
- Always use proper PPE and confined space protocol when servicing a valve beneath ground.

11. PRODUCTS

Manufacturer/Supplier/Reseller shall be an established stormwater company that has at least 5 installations of automated stormwater management devices that have been in use and functional for the past 3 or more years.

A. Acceptable smartPOND Valve


"smartBATCH" Automated Batch Detention System "smartPOND" Automated Detention System

B. Acceptable System Supplier Convergent Water Technologies, Inc.

- (800)711-5428 www.convergentwater.com
- C. Authorized Value Added Reseller Construction EcoServices
- (800)456-1000 www.ecosvs.com

12. Quality Assurance and Performance Specifications

The quality of all system components and all other appurtenances and their assembly process shall be subject to inspection upon delivery of the system to the work site. Installation is to be performed only by skilled work people with satisfactory record of performance on earthworks, pipe, welding, chamber, or pond/landfill construction projects of comparable size and quality.



PK-4670-21.455POND.DWG

13 OF 16

Attachment G – Inspection, Maintenance, Repair and Retrofit Plan

Batch Detention

Westwood

- Batch detention. Basins may have somewhat higher maintenance requirements than an extended detention basin since they are active stormwater controls. The maintenance activities are identical to those of extended detention basins with the addition of maintenance and inspections of the automatic controller and the valve at the outlet.
- Inspections. Inspections should take place a minimum of twice a year. One inspection should take place during wet weather to determine if the basin is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. The remaining inspections should occur between storm events so that manual operation of the valve and controller can be verified. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. The outlet structure and the trash screen should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet{s} as described in previous sections. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately.
- Mowing. The basin, basin side-slopes, and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas
- Litter and Debris Removal, Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for possible Clogging or obstructions and any debris removed
- *Erosion control*. The basin side slopes and embankment all may periodically suffer from slumping and erosion. To correct these problems, corrective action, such as regrading and revegetation, may be necessary. Correction of erosion control should take place whenever required based on the periodic inspections.
- Nuisance Control. Standing water or soggy conditions may occur in the basin. Some standing water may occur after a storm event since the valve may close with 2 to 3 inches of water in the basin. Some flow into the basin may also occur between storms due to spring flow and residential water use that enters the storm sewer system. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.).
- Structural Repairs and Replacement. With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, retaining walls, etc.) should be identified and repaired immediately. An example of this type of repair can include patching of cracked concrete, sealing of voids, removal of vegetation from cracks and joints. The various inlet/outlet structures in a basin will eventually deteriorate and must be replaced.
- Sediment Removal, A properly designed batch detention basin will accumulate quantities of sediment over time. The accumulated sediment can detract from the appearance of the facility and reduce the pollutant removal performance of the facility. The sediment also tends to accumulate near the outlet structure and can interfere with

the level sensor operation. Sediment shall be removed from the basin at least every 5 years, when sediment depth exceeds 6 inches, when the sediment interferes with the level sensor or when the basin does not drain within 48 hours. Care should be taken not to compromise the basin lining during maintenance.

• Logic Controller. The Logic Controller should be inspected as part of the twice yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris, The solar panel should be inspected and any dust or debris on the panel should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. At the end of the inspection, the controller should be reset.

Engineer Signature

Hollis Scheffler, P.E. Printed Name

<u>Senior Project Manager</u> Title

_11/10/2022

Date

Printed Name Maner 2020

Date



	Agent Authorization Form For Required Signature Edwards Aquifer Protection Program Relating to <u>3</u> 0 TAC Chapter 213 Effective June 1, 1999	
Marek Andrei	W Pappas Print Name	,
Mangger	Title - Owner/President/Other	,
of	PDC Williams Plaza, LTD. Corporation/Partnership/Entity Name	,
have authorized	Hollis Scheffler, P.E. Print Name of Agent/Engineer	
of	Westwood Professional Services Print Name of Firm	

to represent and act on the behalf of the above-named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.


SIGNATURE PAGE: Signature pplieant

2023

THE STATE OF County of Harris §

BEFORE ME, the undersigned authority, on this day personally appeared <u>Marele Andrew</u> Known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this <u>1</u> day of <u>November</u> 2.8 22



NOTARY PUBLIC

201 Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 6/8/2025

Agent Authorization Form For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

,
,
,

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

TCEQ-0599 (Rev.04/01/2010)

Page 1 of 2

SIGNATURE PAGE:

t's Signature

07/27/2023

Date

THE STATE County of

BEFORE ME, the undersigned authority, on this day personally appeared <u>HMY HAVA</u> known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this day of 07 TE M 0 TTE M 0 T NO Typed or Printed Name of Notary 3-16-2024 **MY COMMISSION EXPIRES**

TCEQ-0599 (Rev.04/01/2010)

Application Fee Form

Texas Commission on Environmer Name of Proposed Regulated Entit		Subdivision	
Regulated Entity Location: <u>1313 W</u>		505011131011	
Name of Customer: <u>PDC WILLIAMS</u>			
Contact Person: Julie Ward		ne: <u>713-822-1758</u>	
Customer Reference Number (if iss			
Regulated Entity Reference Number	·	9997	
Austin Regional Office (3373)			
Hays	Travis	⊠w	illiamson
San Antonio Regional Office (3362	2)		
Bexar	Medina		valde
Comal	Kinney		
Application fees must be paid by c	heck, certified check, d	or money order, payab	le to the Texas
Commission on Environmental Qu	heck will serve as you	r receipt. This	
form must be submitted with you	r fee payment . This p	ayment is being submi	itted to:
🔀 Austin Regional Office	S	an Antonio Regional O	office
Mailed to: TCEQ - Cashier	C	Vernight Delivery to: 1	TCEQ - Cashier
Revenues Section	1	2100 Park 35 Circle	
Mail Code 214	В	uilding A, 3rd Floor	
P.O. Box 13088	ustin, TX 78753		
Austin, TX 78711-3088	(!	512)239-0357	
Site Location (Check All That Appl	y):		
🔀 Recharge Zone	Contributing Zone	Transi	tion Zone
Type of Plan	Size	Fee Due	
Water Pollution Abatement Plan, C			
Plan: One Single Family Residentia	Acres	\$	
Water Pollution Abatement Plan, C			
Plan: Multiple Single Family Reside	Acres	\$	
Water Pollution Abatement Plan, C		4	
Plan: Non-residential		12.69 Acres	\$ 6,500
Sewage Collection System		L.F.	\$
Lift Stations without sewer lines		Acres	\$
Underground or Aboveground Stor	rage Tank Facility	Tanks	\$
Piping System(s)(only)		Each	\$
Exception Extension of Time		Each	\$ \$
		Each	Ş

Signature:

Date: <u>8/22/2023</u>

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

	Project	Fee
Exception Request		\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

	10 0 01		iuuioii									
1. Reason fo	or Submis	sion (If other is c	hecked pleas	e descr	ribe in a	space	orovide	əd.)				
🛛 New Per	mit, Regis	tration or Authori	zation (Core I	Data Fo	orm she	ould be	e subm	itted wi	th the p	rogram applicatio	n.)	
🗌 Renewa	l (Core Da	ta Form should b	e submitted v	vith the	renew	al form)		Other			
2. Customer	2. Customer Reference Number (if issued) Follow this link to see						3. Reg	gulated	Entity Reference	e Number (if issued)	
CN N/A	CN N/A					numbe egistry*		RN	RN N/A			
SECTION	II: Cu	stomer Info	ormation									
4. General C	ustomer li	nformation	5. Effective	e Date f	or Cu	stome	r Infor	mation	Updat	es (mm/dd/yyyy)		
New Cust		ne (Verifiable wit		Update Secretar					roller of	Change in Public Accounts)	•	Entity Ownership
The Custo	mer Nan	ne submitted	here may	be up	dated	l auto	matio	cally k	ased	on what is cu	rrent and	active with the
Texas Sec	retary of	f State (SOS)	or Texas C	Compt	roller	r of Pu	ublic	Acco	unts (CPA).		
6. Customer	Legal Nar	me (If an individua	l, print last nam	e first: e	eg: Doe,	, John)		<u>lf</u>	new Cu	stomer, enter previ	ious Custom	er below:
Novak GI	SD Mul	tifamily, LL	С									
7. TX SOS/CI	PA Filing	Number	8. TX State	Tax ID (11 digits)				9. Federal Tax ID (9 digits)			S Number (if applicable)	
				ļ			9	921260100				
11. Type of C	ustomer:	Corporat	ion			Individ	lual	Partnership: 🔲 General 🔲 Limited				
Government:	City 🗌 🤇	County 🔲 Federal 🛛	🛾 State 🔲 Othe	r		Sole P	ropriet	torship		Other:		
12. Number of					1				13. Independently Owned and Operated?			
⊠ 0-20 □] 21-100	101-250	251-500		501 aı	nd high	ler	Yes No				
14. Custome	r Role (Pro	oposed or Actual) -	- as it relates to	the Reg	gulated	Entity li	isted or	n this for	m. Plea	se check one of the	following	
⊠Owner		🗌 Opera				wner 8	•					
	nal License	ee 🗌 Respo	onsible Party			oluntar	y Clea	nup Ap	plicant	Other:		
	1500 F	Rivery Blvd.,	Suite 220	0								
15. Mailing Address:												
Address.	City	Georgetowi	1	S	tate	TX		ZIP	7862	28	ZIP + 4	3065
16. Country Mailing Information (if outside USA) 17. E-Mail Address (if applicable)												
	Ŭ									. ,, /		
18. Telephon	e Numbei	1		19. E	xtensi	on or (Code			20. Fax Numbe	r (if applical	ole)
(512)94	3-4703									()	-	
L				1						1		

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected below this form should be accompanied by a permit application)

 New Regulated Entity
 Update to Regulated Entity Name

 Update to Regulated Entity
 Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

Rivery Commerical Subdivision

23. Street Address of the Regulated Entity:	1313 W	1313 Williams Drive								
(No PO Boxes)	City	Georgetown	State	TX	ZIP	78628	ZIP + 4			
24. County										
	E	nter Physical Locat	tion Descripti	on if no st	reet addre	ss is provided.				
25. Description to Physical Location:		The property is located right off the existing I-35 Service road and is on the corner of Williams Drive and Rivery Boulevard								
26 Nearest City						State	Nearest	7ID Code		

20. Nearest Oily	. Nearest City										
27. Latitude (N) In Decir	nal:	30.65361	5° N		28. Longitude (W) In Decimal:				-97.681398°W		
Degrees	Minutes		Seconds		Degrees	Degrees					Seconds
30		39	13.0	97			40			53.0	
29. Primary SIC Code (4 digits) 30. Secondary SIC Code (4 dig					Primary or 6 digits)	NAICS Coo	de	32. S (5 or 6	econdary digits)	NAI	CS Code
33. What is the Primary	Business	of this entity?	(Do not repeat the SI	C or NA	AICS descrip	tion.)					
General retail.											
					1313 Willi	iams Drive	•				
34. Mailing											
Address:	City	Georgeto	wn State		ТХ	ZIP	786	628	ZIP ·	+ 4	
35. E-Mail Address											
36. Teleph	36. Telephone Number		37. Extens	37. Extension or Code			38. Fax Number (if applicable)			cable)	
() -								() -		

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

Dam Safety	Districts Edwards Aquifer		Emissions Inventory Air	Industrial Hazardous Waste
		n/a		
Municipal Solid Waste	New Source Review Air	OSSF 0	Petroleum Storage Tank	PWS
Sludge	Storm Water	Title V Air	Tires	Used Oil
Voluntary Cleanup	U Waste Water	U Wastewater Agriculture	U Water Rights	Other:

SECTION IV: Preparer Information

40. Name:					Senior Project Manager			
	42. Telephone 43. Ext./Code 44. Fax Number				Address			
(512)	485-0831		() -	hollis.scheffler@westwoodps.com				

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Westwood Professional Services	Senior Pr	roject Manage	r	
Name (In Print):	Hollis Scheffler			Phone:	(512) 485- 0831

Signature:	Aut	Date:	7/27/2023



TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

SECTION	I: Gel	ierai inform	Tation									
1. Reason fo	or Submis	sion (If other is c	hecked pleas	e desc	ribe in	space	provide	ed.)				
🛛 New Per	rmit, Regi	stration or Authori	zation (Core	Data F	orm sh	ould be	e subm	itted n	ith the p	program applicatio	n.)	
Renewa	I (Core Da	ata Form should b	e submitted w	vith the	e renew	al form	1)		Other			
2. Customer	Reference	ce Number <i>(if iss</i>	ued)		w this lir			3. Re	gulated	Entity Reference	e Number (if issued)
CN N/A					N or RN entral R			RN N/A				
SECTION	II: Cu	stomer Info	rmation									
4. General C	ustomer l	nformation	5. Effective	e Date	for Cu	stome	r Inform	matio	n Updat	es (mm/dd/yyyy)		
New Cust		me (Verifiable wit		•	e to Cu arv of St				troller o	Change in f Public Accounts)	•	Entity Ownership
		· · ·			· · · · · · · · · · · · · · · · · · ·			· · ·				active with the
		f State (SOS)										
6. Customer	Legal Na	me (If an individua	l, print last nam	ne first:	eg: Doe,	John)		<u> 1</u>	new Cu	stomer, enter prev	ious Custom	er below:
PDC Willi	iams Pl	aza, LTD.										
7. TX SOS/CI	PA Filing	Number	8. TX State	Tax II) (11 digi	ts)		9	. Feder	al Tax ID (9 digits)	10. DUN	S Number (if applicable)
08042716	82		3208143	9310)			87-3114931				
11. Type of C	ustomer	: Corporati	on			Individ	lual	Partnership: 🗖 General 🛛 Limited				
Government:	City	County 🔲 Federal	State 🔲 Othe	r		Sole F	Propriet	etorship 🔲 Other:				
12. Number o	of Employ] 21-100	/ees	251-500] 501 ar	nd high	ner	13. Independently Owned and Operated? □ Yes				
14. Custome	r Role (Pr	oposed or Actual) -	- as it relates to	the Re	gulated	Entity I	isted on	this fo	rm. Plea	se check one of the	following	
Owner	nal Licens	ee Respo	tor nsible Party				opera y Clear		oplicant	⊠Other:		
	1360]	Post Oak Blv	d.									
15. Mailing Address:	Ste. 19	900										
Address.	City	Houston		:	State	TX		ZIP	770	56	ZIP + 4	
16. Country I	Mailing In	formation (if outsi	de USA)			-	17. E	-Mail	Addres	s (if applicable)		
	andrew.pappas@partnersrealestate.com											
18. Telephon	e Numbe	r		19. E	xtensi	on or (Code					
(713)629-0500 () -												

SECTION III: Regulated Entity Information

 21. General Regulated Entity Information (If 'New Regulated Entity" is selected below this form should be accompanied by a permit application)

 ☑ New Regulated Entity
 □ Update to Regulated Entity Name
 □ Update to Regulated Entity Information

 The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

Williams Plaza

23. Street Address of the Regulated Entity: (No PO Boxes)	1313 W	/illams Dr.							
	City	Georgetow	n State	TX	ZIP	78628	ZIP + 4		
24. County	Willian								
	E	Inter Physical Lo	cation Descr	ription if no st	reet addre	ess is provided.			
25. Description to Physical Location:	4.74					1, FL	9		
26. Nearest City						State	Nea	rest ZIP Code	
27. Latitude (N) In Deci	mal:			28 1	ongitude	(W) In Decimal:			
Degrees	Minutes	S	econds	Degre	and the second second second	Minutes		Seconds	
30		39	09		97	2	10	52	
29. Primary SIC Code (4 digits) 30. Secondary SIC Cod			Code (4 digits)				Secondary NAICS Code		
5999				459999	459999				
33. What is the Primary	Business o	f this entity? (I	Do not repeat the	SIC or NAICS des	cription.)				
Mixed Use / Comn	nerical Re	etail							
34. Mailing Address:	1360 Post Oak Blvd. Suite 1900								
	City	Houston	State	ТХ	ZIP	77056	ZIP + 4		
35. E-Mail Address	:		6	andrew.pappa	s@partne	rsrealestate.com			
36. Teleph	one Numbei	r		ision or Code			nber <i>(if appli</i>	cable)	
(713)	629-500					() -			
TCEQ Programs and II n. See the Core Data Form	D Numbers (instructions fo	Check all Programs r additional quidanc	and write in the	e permits/registra	tion number	rs that will be affected	by the updates	submitted on this	
Dam Safety	Districts		Edwards Aquifer		Emiss	Emissions Inventory Air		Industrial Hazardous Waste	
Municipal Solid Waste	New Source Review Air				Petroleum Storage Tank				
Sludge	Storm Water		Title V Air		Tires		Used Oil		
Voluntary Cleanup 🗌 Waste Water		Wastewater Agriculture		Water Rights		Other:			
ECTION IV: Pre	narer In	formation							
0	fler, P.E.			41. Title:	Soni	Senior Project Manager			

SECTION V: Authorized Signature

(

)

-

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

hollis.scheffler@westwoodps.com

Company:	Westwood Professional Services Job Title: S		Senior P	Senior Project Manager			
Name (In Print):	Hollis Scheffler			Phone:	(512) 485- 0831		

Number

(512) 485-0831

Signature:	Al	Date:	2/28/2023