## **Texas Commission on Environmental Quality**

# **Edwards Aquifer Application Cover Page**

#### **Our Review of Your Application**

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

## **Administrative Review**

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
  - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <a href="http://www.tceq.texas.gov/field/eapp">http://www.tceq.texas.gov/field/eapp</a>.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
  - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

#### **Technical Review**

- When an application is deemed administratively complete, the technical review period begins. The regional
  office will distribute copies of the application to the identified affected city, county, and groundwater
  conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
  to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

#### **Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: South Lake Raw Water Facilities and Intake				2. Regulated Entity No.:						
3. Customer Name: City of Georgetown				4. Customer No.: 600412043						
5. Project Type: (Please circle/check one)	New		Modification Extension		Exception					
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures	
7. Land Use: (Please circle/check one)	Resider	ntial	Non-r	Non-residential 8.3		8. Site (acres): 3.594		3.594		
9. Application Fee:	\$4,000		10. P	10. Permanent BMP(s):			s):			
11. SCS (Linear Ft.):			12. A	12. AST/UST (No. Tanks):			ıks):			
13. County:	Willian	ison	14. W	14. Watershed:				San Gabriel River		

## **Application Distribution**

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field\_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region				
County:	Hays	Travis	Williamson	
Original (1 req.)	_		_1_	
Region (1 req.)	_	_	_1_	
County(ies)	_		_1_	
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA	
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorence _1_GeorgetownJerrellLeanderLiberty HillPflugervilleRound Rock	

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	_		_	_	_
Region (1 req.)	_	_	_		_
County(ies)			_		
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the appliapplication is hereby submitted to TCEQ for administra	
Ellyn Weimer, PE	
Print Name of Customer/Authorized Agent	
Glyn Neiner	10-30-2023
Signature of Customer/Authorized Agent	Date

**FOR TCEQ INTERNAL USE ONLY**				
Date(s)Reviewed:	Date	Date Administratively Complete:		
Received From:	Corr	rrect Number of Copies:		
Received By:	Distr	tribution Date:		
EAPP File Number:	Com	Complex:		
Admin. Review(s) (No.):	No. A	No. AR Rounds:		
Delinquent Fees (Y/N):	Revi	view Time Spent:		
Lat./Long. Verified:	SOS	S Customer Verification:		
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):		
Core Data Form Complete (Y/N):	nta Form Complete (Y/N):  Check: Signed (Y/N):			
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):		

## **General Information Form**

**Texas Commission on Environmental Quality** 

Print Name of Customer/Agent: Ellyn Weimer, PE

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

## Signature

Date: 10-30-2023

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Sig	Signature of Customer/Agent:	
4	Ellyn Weiner	
Pi	Project Information	
1.	1. Regulated Entity Name: South Lake Raw Water Facilities and Intake	
2.	2. County: Williamson	
3.	3. Stream Basin: San Gabriel River	
4.	4. Groundwater Conservation District (If applicable):	
5.	5. Edwards Aquifer Zone:	
	Recharge Zone Transition Zone	
6.	6. Plan Type:	
	WPAP ☐ AST   SCS ☐ UST   Modification ☐ Exception Request	


7.	'. Customer (Applicant):	
(		p: <u>78626</u> AX: <u>(512) 930-3559</u>
8.	. Agent/Representative (If any):	
		<u>250</u> p: <u>78731</u> AX:
9.	. Project Location:	
	<ul> <li>☐ The project site is located inside the city limits of </li> <li>☐ The project site is located outside the city limits by jurisdiction) of</li> <li>☐ The project site is not located within any city's lim</li> </ul>	ut inside the ETJ (extra-territorial
10.	O.  The location of the project site is described below. detail and clarity so that the TCEQ's Regional staff boundaries for a field investigation.	
	The South Lake Raw Water Electrical and Chemica Breaks Road, Georgetown, Texas, 78628.	l Facilities is located at 2044 Cedar
11.	<ol> <li>Attachment A – Road Map. A road map showing a project site is attached. The project location and s the map.</li> </ol>	
12.	2. Attachment B - USGS / Edwards Recharge Zone N USGS Quadrangle Map (Scale: 1" = 2000') of the Ed The map(s) clearly show:	
	<ul> <li>☑ Project site boundaries.</li> <li>☑ USGS Quadrangle Name(s).</li> <li>☑ Boundaries of the Recharge Zone (and Transiti</li> <li>☑ Drainage path from the project site to the bou</li> </ul>	
13.	3. The TCEQ must be able to inspect the project site Sufficient survey staking is provided on the project the boundaries and alignment of the regulated act features noted in the Geologic Assessment.	t to allow TCEQ regional staff to locate


	vey staking will be completed by this date: <u>April 9, 2018 (Please contact City of orgetown for access to site before inspection)</u>
nar	rative description of the proposed project. The project description is consistent oughout the application and contains, at a minimum, the following details:
	Area of the site Offsite areas Impervious cover Permanent BMP(s) Proposed site use Site history Previous development Area(s) to be demolished
15. Existing	project site conditions are noted below:
	Existing commercial site Existing industrial site Existing residential site Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Uncleared) Other: Raw Water Electrical and Chemical Facilities
Prohib	ited Activities
	n aware that the following activities are prohibited on the Recharge Zone and are not posed for this project:
	Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
(2)	New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
(3)	Land disposal of Class I wastes, as defined in 30 TAC §335.1;
(4)	The use of sewage holding tanks as parts of organized collection systems; and
, ,	New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
	New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.
	n aware that the following activities are prohibited on the Transition Zone and are proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

## **Administrative Information**

18. The	e fee for the plan(s) is based on:
	For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.  For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.  For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.  A request for an exception to any substantive portion of the regulations related to the protection of water quality.  A request for an extension to a previously approved plan.
19.	Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:
	TCEQ cashier  Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)  San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)
20.	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regiona office.
21. 🔀	No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.





## **City of Georgetown**

#### South Lake Raw Water Facilities and Intake

#### **Water Pollution Abatement Plan**

The South Lake Raw Water Facilities and Intake project will provide chemical and electrical buildings and associated tanks that will aid the raw water intake and piping that runs from Lake Georgetown to the South Lake Water Treatment Plant. The Intake is located solely on the contributing zone and is less than 5 acres of soil disturbance and is exempt from permitting. The associated 42-inch raw water line and electrical conduit is also exempt over the recharge zone as it is not deemed a regulated activity. The South Lake Water Treatment Plant is already permitted and under construction (EAPP ID 11002763). The electrical and chemical facility is located at 2044 Cedar Breaks Road, adjacent to the existing Round Rock Lake Georgetown Pump Station. The site is 3.594 acres. The impervious cover of the proposed site is 0.23 acres (6%). Permanent best management practices (BMPs) for the site include revegetating and hydroseeding disturbed areas that will act as linear vegetation filter strips in the long term.



# GEOLOGIC ASSESSMENT FOR THE APPROXIMATELY 0.09-ACRE SOUTH LAKE RAW WATER FACILITIES AND INTAKE

Williamson County, Texas

September 2023

## Submitted to:

CDM Smith, Inc. 9430 Research Blvd., Suite 1-200 Austin, Texas 78759

## Prepared by:

aci Group, LLC 1001 Mopac Circle Austin, Texas 78746 TBPG Firm License No. 50260

aci project #: 05-20-006

# **Geologic Assessment**

## **Texas Commission on Environmental Quality**

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Pri	nt Name of Geologist: <u>Mark T. Adams</u>	Telephone: <u>(512) 347-9000</u>
Da	te: <u>9/19/2023</u>	Fax: (512) 306-0974
	gistration number)	No.150250 Name of Company and TBPG or TBPE
Re	nature of Geologist.	OLOGY D. 1835 ENSE ater Facilities and Intake
1.		rmed: <u>08/10/2021</u>
2.	Type of Project:	
3.	WPAP SCS Location of Project:	☐ AST ☐ UST
	Recharge Zone Transition Zone	

Contributing Zone within the Transition Zone

		ologic Assessmen able) is attached.		Completed Geo	ologic Asses	sment Table
Hydrolo 55, App	ogic Soil Gro endix A, Soi	oject site is summups* (Urban Hydr I Conservation Se Dweach soil type	ology for	or Small Watersl 986).  If there is	neds, Techr more than	nical Release No. one soil type on
Table 1 - Soil Characteristi	=			Soil Name	Group*	Thickness(feet)
Soil Name	Group*	Thickness(feet)				
Eckrant-Rock outcrop association, 8 to 30 percen slopes (ErG)	B t D	0-1.6	* Soil Group Definitions (Abbrev A. Soils having a high infiltr rate when thoroughly we B. Soils having a moderate infiltration rate when the			
eckrant-Rock outcrop association, 2 to 10 percen slopes (ErE)	1	6.66	wetted. C. Soils having a slow infiltration rate when thoroughly wetted. D. Soils having a very slow infiltration rate when thorough wetted.			oughly wetted. ery slow
member top of the strain function for the strain function for the strain function for the strain function for the strain function function for the strain function function function for the strain function funct	ers, and thick the stratigrantigraphic coment C – Site and any featural for fluid n	atigraphic Colum knesses is attache phic column. Oth dumn. e Geology. A narra res identified in the novement to the formal sis attached.	d. The o erwise, ative de ne Geolo	outcropping unit the uppermost scription of the ogic Assessment	t, if present unit should site specifi Table, a di	, should be at the be at the top of geology scussion of the
the app Applica Site Ge	olicant's Site nt's Site Pla ologic Map S	e Geologic Map(s Plan. The minimum on Scale: 1" = <u>10'</u> Scale: 1" = <u>10'</u> e (if more than 1 s	um scale	e is 1": 400'	p must be t	he same scale as
9. Method of	collecting p	ositional data:				
		System (GPS) tech lease describe me		data collection	:	2 of 3

$10.$ $igselow{1}$ The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11. $igsquare$ Surface geologic units are shown and labeled on the Site Geologic Map.
12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
Geologic or manmade features were not discovered on the project site during the field investigation.
13. 🔀 The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
<ul> <li>□ There are (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)</li> <li>□ The wells are not in use and have been properly abandoned.</li> <li>□ The wells are not in use and will be properly abandoned.</li> <li>□ The wells are in use and comply with 16 TAC Chapter 76.</li> <li>☑ There are no wells or test holes of any kind known to exist on the project site.</li> </ul>
Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.



# TABLE OF CONTENTS

1.0	INTRODUCTION	2
2.0	PROJECT INFORMATION	
3.0	INVESTIGATION METHODS	
4.0	SOILS AND GEOLOGY	
5.0	SUMMARY OF FINDINGS	
6.0	REFERENCES	
	LIST OF ATTACHMENTS	
ATT	ГАСНМЕNT A	8
	Site Maps (Figures 1-4)	
ATT	TACHMENT B	13
	Geologic Table	
	Geologic and Manmade Feature Maps (Figures 5.1 & 5.2)	
	Feature Descriptions and Recommendations	
ATT	TACHMENT C	19
	Historic Aerial Photographs	



## September 2023

Geologic Assessment for the South Lake Raw Water Facilities and Intake located in Williamson County, Texas

#### 1.0 INTRODUCTION

The Texas Commission on the Environmental Quality (TCEQ) regulates activities that have the potential to pollute the Edwards Aquifer through the Edwards Aquifer Protection Program. Projects meeting a certain criterion over the Edwards Aquifer Recharge Zone must submit an Edwards Aquifer Protection Plan (EAPP).

The purpose of this report is to identify all potential pathways for contaminant movement to the Edwards Aquifer and provide sufficient geologic information so that the appropriate Best Management Practices (BMPs) can be proposed in the EAPP. This report complies with the requirements of Title 30, Texas Administrative Code (TAC) Chapter 213 relating to the protection of the Edwards Aquifer Recharge Zone. Per the Rules, the Geologic Assessment must be completed by a Geologist licensed according to the Texas Geoscience Practice Act.

### 2.0 PROJECT INFORMATION

The South Lake Raw Water Facilities and Intake project consists of the Raw Water Intake Pump Station (IPS) and Electrical and Chemical Substation (ECS). These buildings are located east of Cedar Breaks Road, along the proposed Raw Water Alignment, in the City of Georgetown Full Purpose jurisdiction, in Williamson County, Texas (**Attachment A**, **Figure 1**). Pedestrian investigations of the 0.06-acre ECS and 0.03-acre IPS areas were performed on August 10, 2021, by Marcos Cardenas, Sarah King, Andrew Marlow, and Erin Mathison, under the supervision of Mark Adams, P.G. with **aci consulting**.

This report is intended to satisfy the requirements for a Geologic Assessment, which shall be included as a component of a Water Pollution Abatement Plan (WPAP). The site is approximately 0.09 acres in total. The proposed site use is for the development of the South Lake Raw Water project. The scope of the report consists of a site reconnaissance, field survey, and review of existing data and reports. Features identified during the field

aci Proiect No.: 05-20-006



survey were ranked utilizing the TCEQ matrix for Edwards Aquifer Recharge Zone features. The ranking of the features will determine their viability as "sensitive" features.

#### 3.0 INVESTIGATION METHODS

The following investigation methods and activities were used to develop this report:

- Review of existing files and literature to determine the regional geology and any known caves associated with the project area;
- Review of past geological field reports, cave studies, and correspondence regarding the existing geologic features on the project area, if available;
- Site reconnaissance by a registered professional geologist to identify and examine caves, recharge features, and other significant geological structures;
- Evaluation of collected field data and a ranking of features using the TCEQ Ranking Table 0585 for the Edwards Aquifer Recharge Zone; and
- Review of historic aerial photographs to determine if there are any structural features present, and to determine any past disturbances on the subject property.

#### 4.0 SOILS AND GEOLOGY

The following includes a site-specific description of the soils, geologic stratigraphy, geologic structure, and karstic characteristics as they relate to the Edwards aquifer. Also included in this section is a review of historic aerials for presence of geologic changes or changes to manmade features in bedrock.

## Soils

According to the United States Department of Agriculture (USDA) Natural Resource Conservation Service (NRCS) Web Soil Survey (2023), two soil units occur within the project alignment (**Attachment A, Figure 2**):

• ErG—Eckrant-Rock outcrop association, 8 to 30 percent slopes
The Eckrant component makes up 65 percent of the map unit. Slopes are 8 to 30 percent.
This component is on ridges on dissected plateaus. The parent material consists of residuum weathered from limestone. Depth to a root restrictive layer, bedrock, lithic, is 4 to 20 inches. The natural drainage class is well drained. Water movement in the most restrictive layer is moderately low. Available water to a depth of 60 inches (or restricted

aci Project No.: 05-20-006



depth) is very low. Shrink-swell potential is moderate. This soil is not flooded or ponded. There is no zone of water saturation within a depth of 72 inches. Organic matter content in the surface horizon is about 6 percent. This soil does not meet hydric criteria. Hydric Soil Group: D

Rock outcrop (27%), Brackett (4%), Kerrville (2%), Krum (1%), and Tarpley (1%) make up the remaining 35% of the soil map unit.

## ErE—Eckrant-Rock outcrop association, 1 to 10 percent slopes

The Eckrant component makes up 58 percent of the map unit. Slopes are 1 to 10 percent. This component is found on ridges of dissected plateaus. The parent material consists of residuum weathered from limestone. Depth to a root restrictive layer, bedrock, lithic, is 4 to 20 inches. The natural drainage class is well drained. Water movement in the most restrictive layer is moderately low. Available water to a depth of 60 inches (or restricted depth) is very low. Shrink-swell potential is moderate. This soil is not flooded or ponded. There is no zone of water saturation within a depth of 72 inches. Organic matter content in the surface horizon is about 6 percent. This soil does not meet hydric criteria. Hydrologic Soil Group: D.

Rock outcrop (16%), Tarpley (11%), Real (6%), Brackett (5%), and Pratley (4%) components make up the remaining 42% of the map unit.

## Geologic Stratigraphy

According to the *Geologic Map of the Georgetown Quadrangle, Texas*, one geologic unit, Edwards Limestone (Ked) occurs within the project alignment (**Attachment A, Figure 3**). A description of the Edwards Limestone (Ked) unit by Collins (1997) is as follows:

## • Edwards Limestone (Ked)

"Limestone, dolomitic limestone and marl. Massive to thin beds, chert, and fossiliferous; fossils include rudistids. Shallow subtidal to tidal-flat cycles. Honeycomb textures, voids in collapsed breccias, and cavern systems. Accounts for most of the Edwards aquifer strata. Thickness is between 100ft to 300ft; thins northward."

aci Project No.: 05-20-006



## Site-Specific Stratigraphic Column

Formation	Members	Thickness (Collins, 1997)
Edwards Limestone	Edwards Limestone	Approximately 80-130 feet (mapped from contours)

## Geologic Structure

The geologic strata associated with the Edwards Aquifer include the Georgetown Limestone Formation of the Washita Group, the Edwards Limestone Group, which is interfingered with the Comanche Peak Formation, followed by the Walnut formation, and finally the Glen Rose Formation of the Trinity Group. These Groups dip gently to the southeast and are a characterized by the Balcones Fault Escarpment, a zone of en echelon normal faults downthrown to the southeast. Locally, the dominant structural trend of faults within the area is 15°, as evidenced by the mapped fault patterns (**Attachment A**, **Figure 4**). Thus, all features that have a trend ranging from 0° to 30° are considered "on trend" and were awarded the additional 10 points in the Geologic Assessment Table.

The geology on the site and surrounding tracts up to the border of Lake Georgetown is all Edwards Limestone (Ked), however the Comanche Peak (Kc) is present along the border of Lake Georgetown, suggesting the site is within the lower section of the Edwards Limestone (Collins 1997).

#### **Karstic Characteristics**

In limestone landscapes, karst is expressed by erratically developed cavernous porosity from dissolution of bedrock as water combined with weak acids moves through the subsurface. Karst terrains are typical of the Edwards Limestone, occurring across a vast region of Central Texas, including the Balcones Fault Escarpment. The features produced by karst processes include, but are not limited to, sinkholes, solution cavities, solution enlarged fractures, and caves. These features can eventually provide conduits for fluid movement such as surface water runoff, as "point recharge" to the Edwards Aquifer. Faults and manmade features within bedrock can also provide conduits for point recharge in many cases.

aci Project No.: 05-20-006



According to Edwards aquifer zone map produced by the TCEQ (2005), the entire subject area is within the northern segment of the Edwards Aquifer Recharge Zone (**Attachment A, Figure 3**). Thus, all karst features identified as sensitive within the project limits have the potential to be point recharge features into the Edwards Aquifer.

### Review of Historic Aerials

Aerial photographs from 1941, 1953, 1962, 1974, 1981, 1988, 1995, 2004, 2010, 2016, and 2020. The general area appeared to be undeveloped or used for agricultural purposes since before the first aerial image dated 1941 (**Attachment C**). Minor changes in vegetation occur on and surrounding the site between the 1941 and 1962 aerial images. In the 1962 aerial, an easement of some sort appears to the north of the site. Lake Georgetown and Cedar Breaks Park first appears to the north and east of the site in the 1981 aerial. Minor changes to the existing structures, roads, and Cedar Breaks Park are visible between the 1981 and 2020 aerials, including changes in the water level of Lake Georgetown.

#### 5.0 SUMMARY OF FINDINGS

This report documents the findings of a geologic assessment conducted by **aci consulting** personnel on August 10, 2021. A total of two features were identified within the limits of the project. Both features identified are manmade features in bedrock. Comprehensive descriptions for each feature can be found in **Attachment B**. The manmade features in bedrock are associated with infrastructure for the existing water utilities and have been designated as sensitive to call the attention of the project engineers.

aci Project No.: 05-20-006



#### **6.0 REFERENCES**

- Collins, E.W., 1997. *Geologic Map of the Georgetown Quadrangle, Texas*. Bureau of Economic Geology. Austin, Texas.
- (SCS) Soil Conservation Survey. 1983. Soil Survey of Williamson County, Texas. United States Department of Agriculture. Texas Agriculture Experiment Station.
- (TCEQ) Texas Commission on Environmental Quality. 2004. Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones. October 1, 2004. Austin, Texas.
- (TCEQ) Texas Commission on Environmental Quality. 2005. "Edwards Aquifer Protection Program, Chapter 213 Rules Recharge Zone, Transition Zone, Contributing Zone, and Contributing Zone within the Transition Zone." Map. Digital data. September 1, 2005. Austin, Texas.
- (TWDB) Texas Water Development Board. 2023. Water Data Interactive Groundwater Data Viewer. Accessed on September 18, 2023. Available at: http://www2.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer
- (USDA NRCS) U.S. Department of Agriculture Natural Resources Conservation Service. 2023. WebSoilSurvey.com. Soil Survey Area: Williamson County, Texas. Date accessed: September 18, 2023.

aci Project No.: 05-20-006



## ATTACHMENT A

Site Maps

aci Project No.: 05-20-006



South Lake Raw Water Facilities and Intake

aci Project No.: 05-20-006




South Lake Raw Water Facilities and Intake

aci Project No.: 05-20-006



South Lake Raw Water Facilities and Intake Figure 3: Site Geology Map

aci Project No.: 05-20-006



South Lake Raw Water Facilities and Intake

Figure 4: Regional Trend Map

aci Project No.: 05-20-006



## **ATTACHMENT B**

Geologic Table Geologic and Manmade Feature Maps (Figures 5.1 & 5.2) Feature Descriptions and Recommendations

aci Project No.: 05-20-006

GEOLOG	SIC ASSES	SMENT TAE	3LE			PR	OJE	CT N	IAME:	So	uth L	ake R	aw Wat	er Facili	ities a	and	Inta	ke		
	LOCATION	1				F	EAT	JRE (	CHARAC	TEF	RISTIC	S			EVAL	UAT	ΓΙΟΝ	PHY	SICA	L SETTING
1A	1B *	1C*	2A	2B	3		4		5	5A	6	7	8A	8B	9		10	1	11	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIME	NSIONS (	(FEET)	TREND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	SENS	SITIVITY		ENT AREA RES)	TOPOGRAPHY
						Х	Υ	Z		10						<40	<u>&gt;40</u>	<1.6	<u>&gt;1.6</u>	
RWL-07	30.6669306	-97.7345278	MB	30	Ked	8	8	?	-	-	-	-	X	10	40		Χ	Χ		Floodplain
RWL-08	30.6669306	-97.7345889	MB	30	Ked	2	2	?	-	-	-	-	Χ	10	40		Х	Χ		Floodplain
•			•																	
											_									

\* DATUM: NAD 1983 State Plane 4203

2A TYPE	TYPE	2B POINTS
С	Cave	30
SC	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
0	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
SW	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

	8A INFILLING
Ν	None, exposed bedrock
С	Coarse - cobbles, breakdown, sand, gravel
0	Loose or soft mud or soil, organics, leaves, sticks, dark colors
F	Fines, compacted clay-rich sediment, soil profile, gray or red colors
V	Vegetation. Give details in narrative description
FS	Flowstone, cements, cave deposits
Х	Other materials

12 TOPOGRAPHY Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed


I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined as TAC Chapter 213.

9/19/2023 Date

Sheet 1 out of 1

TCEQ-0585-Table (Rev. 10-01-04)





South Lake Raw Water Facilities and Intake Figure 5.2 Geologic and Manmade Feature Map



**RWL-07** 

GPS: 30.666931, -97.734528

This feature is a manmade feature in bedrock, a raw water pipeline within the proposed ECS boundary. A manhole and metal water valve cover were located within an approximately 8 ft diameter concrete pad. A water line tie in is located directly adjacent to the concrete structure. The feature is within the floodplain (FEMA Flood Hazard Zone A) in the Edwards Limestone Formation. The infill material beneath the feature was not determined during the inspection. The depth of the manhole and pipeline was not determined during inspection; however, this feature has been designated as sensitive in order to call the attention of the project engineers.

**Recommendation:** This feature does not require any protective setbacks but should be brought to the attention of the engineer.



View of RWL 07.



**RWL-08** 

GPS: 30.666931, -97.734589

This feature is a manmade feature in bedrock, a pad mounted automatic gate motor and associated underground electrical wires within the proposed ECS boundary. This motor is located above a 2 ft by 2 ft concrete pad with underground electrical utilities adjacent to the pad. The feature is within the floodplain (FEMA Flood Hazard Zone A) in the Edwards Limestone Formation. The infill material beneath the feature was not determined during the inspection. The depth of the concrete pad or the electric utilities was not determined during the inspection; however, this feature has been designated as sensitive in order to call the attention of the project engineers.

**Recommendation:** This feature does not require any protective setbacks but should be brought to the attention of the engineer.



View of RWL-08.



## ATTACHMENT C

Historic Aerial Photographs

aci Project No.: 05-20-006

#### Prepared for:

**ACI CONSULTING** 1001 Mopac Circle Austin, TX 78746




# Historical South Lake Georgetown Water Project TX Photographs

Williamson County

PO #: 05-20-006

Wednesday, March 9, 2022



Date: 2020 Source: USDA


Feet 1,000 0 250 500












Source: USDA








Source: USGS













Source: USGS






Source: USGS









# **AERIAL SOURCE DEFINITIONS**

Acronym	Agency
NASA	National Aeronautics & Space Administration
AMS	Army Mapping Service
ASCS	Agricultural Stabilization & Conservation Service
SCS	Soil Conservation Service
USBR	United States Bureau of Reclamation
Fairchild	Fairchild Aerial Surveys
TXDOT	Texas Department of Transportation
BLM	Bureau of Land Management
USAF	United States Air Force
USCOE	United States Corps of Engineers
USDA	United States Department of Agriculture
USGS	United States Geological Survey
WALLACE	Wallace-Zingery Aerial Surveys
TNRIS	Texas Natural Resources Information System



# COPYRIGHT POLICY & DISCLAIMER

This report is solely for the limited use of the client and its customers. Banks Environmental Data, Inc. makes no warranties as to accuracy, validity, completeness, merchantability, quality, condition, suitability or fitness for a particular use or purpose in respect to this report and any information contained herein. All risk is assumed by the user. Banks Environmental Data, Inc. assumes no liability to any party for loss or damage whether rising out of errors or omissions, negligence, accident, or any other cause. In no event shall Banks Environmental Data, Inc., its affiliates or agents, be liable to anyone for special incidental, consequential or exemplary damages.

# **Water Pollution Abatement Plan Application**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aguifer. This Water Pollution Abatement Plan Application Form is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Regulated Entity Information
Regulated Entity Name: South Lake Raw Water Facilities and Intake
Ellyn Weiner
Signature of Customer/Agent:
Date: <u>10-30</u> -2023
Print Name of Customer/Agent: Ellyn Weimer, PE
review and Executive Director approval. The form was prepared by.

 The type of project is:
Residential: Number of Lots:
Residential: Number of Living Unit Equivalents:
Commercial
Industrial
Other: Raw Water Electrical and Chemical Facilities

- 2. Total site acreage (size of property):3.594
- 3. Estimated projected population:NA
- 4. The amount and type of impervious cover expected after construction are shown below:

**Table 1 - Impervious Cover Table** 

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	5,403	÷ 43,560 =	0.124
Parking		÷ 43,560 =	
Other paved surfaces	4,606	÷ 43,560 =	0.106
Total Impervious Cover	10,009	÷ 43,560 =	0.23

Total Impervious Cover  $\underline{0.23}$  ÷ Total Acreage  $\underline{3.594}$  X 100 =  $\underline{6}$ % Impervious Cover

5.	Attachment A - Factors Affecting Surface Water Quality. A detailed description of all
	factors that could affect surface water and groundwater quality that addresses ultimate
	land use is attached.

6. Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

# For Road Projects Only


Complete questions 7 - 12 if this application is exclusively for a road project.

7.	Type of project:
	TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways.
8.	Type of pavement or road surface to be used:
	Concrete Asphaltic concrete pavement Other:
9.	Length of Right of Way (R.O.W.): feet.
	Width of R.O.W.: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$
10.	Length of pavement area: feet.
	Width of pavement area: feet. L x W = $Ft^2 \div 43,560 \ Ft^2/Acre = acres.$ Pavement area acres $\div$ R.O.W. area acres x $100 = $ % impervious cover.
11.	A rest stop will be included in this project.
	A rest stop will not be included in this project.

TCEQ Executive Director. Modific	ng roadways that do not require approval from the ations to existing roadways such as widening more than one-half (1/2) the width of one (1) existing the TCEQ.
Stormwater to be genera	ted by the Proposed Project
volume (quantity) and character occur from the proposed project quality and quantity are based or	racter of Stormwater. A detailed description of the (quality) of the stormwater runoff which is expected to is attached. The estimates of stormwater runoff in the area and type of impervious cover. Include the both pre-construction and post-construction conditions
Wastewater to be genera	ted by the Proposed Project
14. The character and volume of wastew	ater is shown below:
% Domestic % Industrial % Commingled TOTAL gallons/day <u>NA</u>	Gallons/day Gallons/day Gallons/day
15. Wastewater will be disposed of by:	
On-Site Sewage Facility (OSSF/Se	otic Tank):
will be used to treat and disposition in the land is suitable for the use the requirements for on-site sewage Fa Each lot in this project/developsize. The system will be designed.	tter from Authorized Agent. An on-site sewage facility ose of the wastewater from this site. The appropriate sed agent) written approval is attached. It states that e of private sewage facilities and will meet or exceed sewage facilities as specified under 30 TAC Chapter 285 cilities.  Opment is at least one (1) acre (43,560 square feet) in gned by a licensed professional engineer or registered icensed installer in compliance with 30 TAC Chapter
Sewage Collection System (Sewer	· Lines):
to an existing SCS.	he wastewater generating facilities will be connected he wastewater generating facilities will be connected
<ul><li>The SCS was previously submit the SCS was submitted with the SCS will be submitted at a be installed prior to Executive</li></ul>	his application. a later date. The owner is aware that the SCS may not

The sewage collection system will convey the wastewater to the (ratherent Plant. The treatment facility is:	name)
Existing. Proposed.	
16. All private service laterals will be inspected as required in 30 TAC §213.5.	
Site Plan Requirements	
Items 17 – 28 must be included on the Site Plan.	
17. $\square$ The Site Plan must have a minimum scale of 1" = 400'.	
Site Plan Scale: $1'' = 10'$ .	
18. 100-year floodplain boundaries:	
<ul> <li>Some part(s) of the project site is located within the 100-year floodplain. is shown and labeled.</li> <li>No part of the project site is located within the 100-year floodplain. The 100-year floodplain boundaries are based on the following specific (inclumaterial) sources(s): FEMA FIRM 48491C0290E Effective 9/26/2008</li> </ul>	·
19. The layout of the development is shown with existing and finished contou appropriate, but not greater than ten-foot contour intervals. Lots, recreation buildings, roads, open space, etc. are shown on the plan.	
The layout of the development is shown with existing contours at approp greater than ten-foot intervals. Finished topographic contours will not di existing topographic configuration and are not shown. Lots, recreation ce buildings, roads, open space, etc. are shown on the site plan.	iffer from the
20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes	s, etc.):
There are (#) wells present on the project site and the locations are labeled. (Check all of the following that apply)	e shown and
<ul> <li>The wells are not in use and have been properly abandoned.</li> <li>The wells are not in use and will be properly abandoned.</li> <li>The wells are in use and comply with 16 TAC §76.</li> </ul>	
igstyle There are no wells or test holes of any kind known to exist on the project	site.
21. Geologic or manmade features which are on the site:	
<ul> <li>All sensitive geologic or manmade features identified in the Geologic shown and labeled.</li> <li>No sensitive geologic or manmade features were identified in the Geologic Assessment.</li> </ul>	
Attachment D - Exception to the Required Geologic Assessment. A regular justification for an exception to a portion of the Geologic Assessment	=

22. 🔀	The drainage patterns and approximate slopes anticipated after major grading activities
23. 🔀	Areas of soil disturbance and areas which will not be disturbed.
24. 🔀	Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
25. 🔀	Locations where soil stabilization practices are expected to occur.
26.	Surface waters (including wetlands).
$\boxtimes$	N/A
27.	Locations where stormwater discharges to surface water or sensitive features are to occur.
$\boxtimes$	There will be no discharges to surface water or sensitive features.
28. 🔀	Legal boundaries of the site are shown.
Adn	ninistrative Information
29. 🔀	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
30. 🔀	Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.



# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

The construction activities associated with the South Lake Raw Water Facilities and Intake project have the potential to create additional total suspended solids (TSS) loadings during the construction. This potential increase in loading will be mitigated with the use of silt fencing and rock berms that will be placed downgradient of the active construction areas and placement of a stabilized construction entrance (SCE) at the entrance of the construction area. Silt fencing will also be placed around storm drain inlets when installed. These measures will help minimize TSS impacts during storm events.

The Electrical and Chemical Facilities site's overall impervious cover will be 0.23 acres (6%) due to the construction of electrical and chemical facilities. **Table 1** below shows a breakdown of the impervious cover calculations. Currently, there is no impervious cover on the site due to it being undeveloped land. Post-construction stormwater controls will include loaming, hydroseeding, and re-vegetation that acts as a vegetated filter strip in the long term. The total removal of TSS due to the impervious cover is 85% and these measures will protect surface water quality before discharging offsite to Lake Georgetown and the San Gabriel Watershed. See Attachment B – Volume and Character of Stormwater for TSS loading calculations.

Table 1. Impervious Cover Summary – Raw Water Electrical and Chemical Facilities

	Area (sq. ft.)	Area (acres)
Total Site:	156,554	3.594
Pavement	4,028	0.092
Chemical Facility	1,037	0.024
Electrical Building	2,647	0.061
Generators	1,345	0.031
Transformers	374	0.009
Gravel Sidewalk	578	0.013
Total IC:	10,009	0.230

#### South Lake Raw Water Facilities and Intake

#### Water Pollution Abatement Plan

The South Lake Raw Water Facilities and Intake site is currently undeveloped land. The project site is on relatively flat land and high elevation ground. The site's topography and site boundaries minimize the potential for off-site runoff to flow onto and across the project site.

The project construction will add 0.23 acres (6%) impervious cover to the site. This increase will be due to the construction of the chemical and electrical building and pavement associated with the project.

Site-generated runoff that discharges from the site will generally flow in a northeast direction through a vegetated area acting as vegetated filter strips thence offsite to dense vegetation and thence to Lake Georgetown.

#### Impervious Cover Impact

The South Lake Raw Water Facilities and Intake site is 3.594 acres. The proposed project will add 0.23 acres of impervious cover to the site.

#### Water Quality Impacts (Post Development)

The volume of on-site generated stormwater runoff is determined from the size of the drainage area, average annual rainfall, and percent impervious cover.

#### $Pv = DA \times Pd \times Rv$

Where: Pv = annual runoff volume (cubic feet)

DA = drainage area (sq ft)

Pd = average annual precipitation depth (in)

 $Rv = runoff coefficient = 0.546(IC)^2 + 0.328(IC) + 0.030$ 

#### Runoff Coefficients (Rv):

 $Rv = 0.546 (0)^2 + 0.328 (0) + 0.030 = 0.030$  (pre-development)

 $Rv = 0.546 (0.06)^2 + 0.328 (0.06) + 0.030 = 0.052 (post-development)$ 

#### **Existing Annual Runoff Volume (PreV)**

 $Pv = 3.594*(43,560) \times 32/12 \times 0.030 = 12,524 \text{ cf/yr}$ 

#### <u>Proposed Annual Runoff Volume (PostV)</u>

 $Pv = 3.594*(43,560) \times 32/12 \times 0.052 = 21,709 \text{ cf/yr}$ 

#### Increase in annual runoff volume is:

 $(21,709 - 12,524)/12,524 \times 100 = 73.3\%$  increase

#### **Water Quality Impacts**

#### Required Load Reduction

L=27.2\*(An\*P)

P=Precipitation (inches)
An=Net Increase in Impervious Area (acres)

Total Required Load Reduction L = 27.2\*(0.23\*32) = 200.2 lbs/yr TSS

The project's design calculations estimate the water quantity and water quality impacts that will be caused by the proposed project's construction. These impacts will be addressed through adequate best management practices (BMPs) including revegetating and hydroseeding disturbed areas that will act as linear vegetated filter strips in the long run.

# **Temporary Stormwater Section**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Ellyn Weimer, PE
Date: <u>10-30</u> -2023
Signature of Customer/Agent:
Allyn Weiner

Regulated Entity Name: South Lake Raw Water Facilities and Intake

#### **Project Information**

#### **Potential Sources of Contamination**

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1.	Fuels for construction equipment and hazardous substances which will be used during construction:
	The following fuels and/or hazardous substances will be stored on the site:
	These fuels and/or hazardous substances will be stored in:
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

	<ul> <li>Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.</li> <li>Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.</li> </ul>
	igotimes Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
S	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	<ul> <li>For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.</li> <li>For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.</li> </ul>
6.	Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: stormwater will flow from the

### Temporary Best Management Practices (TBMPs)

project site to Lake Georgetown thence to the San Gabriel River.

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
	A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
	There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	<b>Attachment F - Structural Practices</b> . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	<b>Attachment G - Drainage Area Map</b> . A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not
	attainable, but other TBMPs and measures will be used in combination to protect
	down slope and side slope boundaries of the construction area.
	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. 🗌	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
$\boxtimes$	N/A
12. 🔀	<b>Attachment I - Inspection and Maintenance for BMPs.</b> A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. 🔀	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. 🔀	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. 🔀	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. 🔀	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

#### Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

#### Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

#### **South Lake Raw Water Facilities and Intake**

#### **Water Pollution Abatement Plan**

No hazardous substances or hydrocarbons will be stored or used in excess on the construction site. Reportable contaminant quantities will be determined and based on 30 TAC §327. In the event of any spill of hydrocarbon products or hazardous substances of reportable quantities the following spill response actions will be taken:

- 1. The nature and extent of the spill will be assessed, and measures will be taken to protect self and all personnel.
- 2. City of Georgetown Fire Department will be notified of the nature and extent of the spill via telephone (911 or 512-930-3600).
- 3. TCEQ Spill Reporting 24-hour Hotline will be notified of the nature and extent of the spill via telephone (800-832-8224).
- 4. The source of the spill will be stopped and confined before spill response cleanup activities take place.
- 5. Spills will be reported prior to any spill response activities.
- 6. Absorbent materials will be used to contain small scale spill incidents immediately.
- 7. Absorbent containment booms will be used to contain the discharge of larger scale spill incidents immediately.
- 8. Any spill response action will follow applicable OSHA health and safety regulations.
- 9. Any water materials generated by spill response actions will be properly stored and disposed in accordance with local, state, and federal regulations.

# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

Potential sources of contamination related to this project include:

- Sediment from spoil piles transported during stormwater events
- Accidental leakage of fuels from vehicles or equipment during construction activities

All necessary actions to minimize impacts of contamination will be taken before, during, and after the proposed project and in coordination with Attachment A, Spill Response Actions. Other than a potential incidental leak from construction vehicles or equipment, all additional runoff will be from natural sources.

#### South Lake Raw Water Facilities and Intake

#### **Water Pollution Abatement Plan**

The sequence for the construction of the proposed South Lake Raw Water Facilities and Intake site is planned as follows:

- Following issuance of notice-to-proceed, Contractor installs silt fencing, tree protection, and stabilized construction entrance.
- Contractor clears site areas and prepares site for construction. (3.594 acres)
- Contractor constructs temporary construction access roads.
- Contractor performs excavation for buildings and concrete pads
- Contractor constructs the buildings, concrete slabs and pads.
- Contractor installs yard piping.
- Contractor installs all the process mechanical equipment, piping and electrical improvements in the buildings and structures.
- Contractor installs concrete pavement.
- Contractor completes site construction and initiates site clean-up. (3.594 acres)
- Contractor inspects and maintains temporary erosion and sedimentation controls throughout the term of the project.
- Contractor restores disturbed soil areas with loaming and hydro-seeding

# South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

Temporary erosion and sedimentation control measures will include:

- Silt fencing;
- Rock berms;
- Concrete wash down area;
- Tree protection;
- Stabilized Construction Entrance (SCE);

Silt fencing shall be placed downgradient from the proposed site areas to control and filter any stormwater that may be generated from the proposed project site. Silt fencing shall also be placed around the perimeter of any storm drain inlets located on or downgradient of the proposed project area when installed. No significant runon from upgradient stormwater flows are anticipated due to the silt fencing. The silt fencing will further serve to control any stormwater generated by the proposed project site before it is allowed to discharge as stormwater-sediment flow from the site.

Rock berms shall be placed downgradient of proposed site areas to control and filter any concentrated stormwater that may be generated from the proposed project site.

A concrete wash out area will be placed on site in order to wash out trucks onto a designated area and not into storm drains or streams. It will also prevent excess concrete to be dumped onsite.

Tree protection will be placed around the critical root zone (CRZ) of protected trees on the proposed project site. This control measure will prevent erosion near the roots and protect the roots from being damaged by construction activities.

A stabilized construction entrance will be installed at the entrance of the construction area to minimize the tracking of sediments from the project site. All access to the construction site will use this SCE.

The area will remain vegetated where possible.

These temporary erosion and sedimentation control measures are indicated on the site drawings and will be put in place before the start of construction and shall remain in place for the duration of site construction activities.


# South Lake Raw Water Facilities and Intake

### **Water Pollution Abatement Plan**

Structural Practices that will be used to limit the runoff discharge of sediments and pollutants from exposed areas of the proposed project include the following practices:

- Silt fencing;
- Rock berms;
- Concrete wash down area;
- Stabilized Construction Entrance (SCE);

These practices are described in Attachment D, Temporary BMPs and Measures. No temporary structural facilities, such as sedimentation ponds, will be constructed or used during construction activities.



#### South Lake Raw Water Facilities and Intake

#### **Water Pollution Abatement Plan**

Silt fencing, rock berms, and the stabilized construction entrance shall be inspected once per week and following every significant rainfall event (of at least 0.1 inch or greater). If such inspections reveal that additional measurements are needed to prevent movement of sedimentation to offsite areas, the Contractor shall promptly install additional erosion control devices as may be required.

Silt fences shall be maintained and repaired as follows:

- Remove accumulated sediment once build up reaches 6 inches
- Replace torn or damaged filter fabric
- Make any other repairs or adjustments, as needed, to ensure the silt fencing is functioning properly

Rock berms shall be maintained and repaired as follows:

- Remove accumulated sediment once build up reaches 6 inches
- Repair any loose wire sheathing or reshape as needed
- Make any other repairs or adjustments, as needed, to ensure the rock berm is functioning properly

The stabilized construction entrance will also be inspected following precipitation events and stone will be replaced if silt accumulation is found to hinder the role of this BMP to minimize the off-site tracking of sediment.

Concrete washout areas shall be inspected daily and after every significant rainfall event (of at least 0.1 inch or greater) to check for leaks, identify any plastic linings and sidewalls have been damaged by construction activities or if they are over 75% capacity. When the washout area is over 75% capacity the wash water shall be removed or allowed to evaporate to avoid overflows. The hardened cement solids shall be removed and recycled.

# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

Temporary soil stabilization practices will include minimizing soil disturbance during construction and hydroseeding of temporary vegetation in disturbed areas. These temporary soil stabilization practices will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. These interim measures will be inspected, maintained, and will remain in place for the duration of the construction phase of the project. These control measures will be planned and implemented in accordance with the Edwards Aquifer Technical Guidance Manual.

Permanent soil stabilization and site restoration will occur prior to project completion. Permanent soil stabilization measures will include the loaming, hydroseeding, and re-vegetation of the disturbed areas using a native grass mix that is properly monitored and managed, eventually resembling linear vegetation filter strips in the long term.

# **Permanent Stormwater Section**

**Texas Commission on Environmental Quality** 

Print Name of Customer/Agent: Ellyn Weimer, PE

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(Ii), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

#### Signature

Data: 10-30-2023

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

υa	ite: 10-50-2020				
Sig	nature of Customer/Agent				
	allyn Weiner				
	Regulated Entity Name: South Lake Raw Water Facilities and Intake				
P	ermanent Best Management Practices (BMPs)				
	rmanent best management practices and measures that will be used during and after nstruction is completed.				
1.	Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.				
	⊠ N/A				
2.	These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.				
	☐ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.				

	A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is:
	⊠ N/A
3.	Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
	⊠ N/A
4.	Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	<ul> <li>□ The site will be used for low density single-family residential development and has 20% or less impervious cover.</li> <li>□ The site will be used for low density single-family residential development but has more than 20% impervious cover.</li> <li>□ The site will not be used for low density single-family residential development.</li> </ul>
5.	The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	<ul> <li>Attachment A - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.</li> <li>□ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.</li> <li>□ The site will not be used for multi-family residential developments, schools, or small</li> </ul>
6.	business sites.  Attachment B - BMPs for Upgradient Stormwater.

		<ul> <li>A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.</li> <li>No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.</li> <li>Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.</li> </ul>
7.		Attachment C - BMPs for On-site Stormwater.
		<ul> <li>□ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.</li> <li>□ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.</li> </ul>
8.		<b>Attachment D - BMPs for Surface Streams</b> . A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
	$\boxtimes$	N/A
9.		The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
		<ul> <li>The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.</li> <li>Attachment E - Request to Seal Features. A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.</li> </ul>
10	. 🔲	<b>Attachment F - Construction Plans</b> . All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
		<ul> <li>Design calculations (TSS removal calculations)</li> <li>TCEQ construction notes</li> <li>All geologic features</li> <li>All proposed structural BMP(s) plans and specifications</li> </ul>
	$\boxtimes$	N/A

11. Attachment G - Inspection, Maintenance, Repair and Retrofit Plan. A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
Prepared and certified by the engineer designing the permanent BMPs and measures
<ul> <li>☐ Signed by the owner or responsible party</li> <li>☐ Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit</li> <li>☐ A discussion of record keeping procedures</li> </ul>
N/A
12. Attachment H - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
⊠ N/A
13. Attachment I -Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
□ N/A
Responsibility for Maintenance of Permanent BMP(s)
Responsibility for maintenance of best management practices and measures after construction is complete.
14. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
⊠ N/A
15. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
⊠ N/A

# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

The South Lake Raw Water Facilities and Intake site is currently undeveloped land. The project site is on relatively flat land and high elevation ground. The site's topography and site boundaries minimize the potential for off-site runoff to flow onto and across the project site. The stormwater flows discharge towards Lake Georgetown thence to the San Gabriel River Watershed. Temporary and permanent erosion and sedimentation controls specified by this Water Pollution Abatement Plan will provide adequate treatment of upgradient and on-site stormwater flows.

# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

There is a small potential for stormwater flows from the South Lake Raw Water Facilities and Intake construction. Site-generated runoff that discharges from the site will generally flow in a northeast direction through a vegetated area acting as vegetated filter strips thence offsite to dense vegetation and thence to Lake Georgetown. There is a 6% increase in impervious cover and the loaming that will act as a linear vegetated filter strip will be sufficient as an added water quality benefit for the site. The onsite stormwater will be filtered by silt fence as the main temporary BMPs to protect the San Gabriel Watershed during construction. Re-vegetation and hydroseeding disturbed areas that will act as a linear vegetation filter strip in the long terms will serve as the primary permanent stormwater control.

# City of Georgetown South Lake Raw Water Facilities and Intake Water Pollution Abatement Plan

There is a potential for stormwater from the proposed construction area to reach Lake Georgetown and thence the San Gabriel River after leaving the site. Areas will be hydroseeded and re-vegetated and will act as a linear vegetation strip in the long run that will provide erosion and sediment control. The project will add 6% impervious cover to the site. The permanent BMPs described will provide sufficient reduction in erosion, runoff velocities, and TSS loading to surface streams.

#### Agent Authorization Form

For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

	Chris Pousson
	Print Name
	CIP Manager
	Title - Owner/President/Other
of	City of Georgetown
	Corporation/Partnership/Entity Name
have authorized _	Ellyn Weimer, PE
	Print Name of Agent/Engineer
of	CDM Smith
	Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

#### I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

#### SIGNATURE PAGE:

42	9-23-22
Applicant's Signature	Date
THE STATE OF TEXES §	
County of Williamson §	
to me to be the person whose name	ority, on this day personally appeared <u>W15 Pousson</u> known e is subscribed to the foregoing instrument, and acknowledged to purpose and consideration therein expressed.
GIVEN under my hand and seal of c	office on this $\frac{23}{}$ day of $\frac{\text{Sept.}}{}$ , $\frac{2022}{}$
	Coudy Gilbert NOTARY PUBLIC
CINDY GILBERT  Notary ID #2953478  My Commission Expires  January 21, 2023	Typed or Printed Name of Notary
	MY COMMISSION EXPIRES: 1/21/2023

# **Application Fee Form**

#### **Texas Commission on Environmental Quality**

lame of Proposed Regulated Entity: South Lake Raw Water Facilities and Intake					
legulated Entity Location: 2044 Cedar Breaks Road, Georgetown, Texas 78628					
Name of Customer: <u>City of Georg</u>	<u>etown</u>				
Contact Person: <u>Chris Pousson</u>	ontact Person: Chris Pousson Phone: (512) 930-8162				
Customer Reference Number (if is					
Regulated Entity Reference Numb	per (if issued):RN				
Austin Regional Office (3373)					
☐ Hays	Travis	Williamson     ■ Market			
San Antonio Regional Office (336	52)				
Bexar	Medina	Uvalde			
Comal	Kinney				
Application fees must be paid by	check, certified check, or m	noney order, payable to the <b>Texa</b> s			
		ck will serve as your receipt. <b>This</b>			
orm must be submitted with yo	orm must be submitted with your fee payment. This payment is being submitted to:				
🔀 Austin Regional Office	San A	Antonio Regional Office			
Mailed to: TCEQ - Cashier	Over	night Delivery to: TCEQ - Cashier			
Revenues Section	1210	00 Park 35 Circle			
Mail Code 214	Build	ling A, 3rd Floor			
P.O. Box 13088	Aust	in, TX 78753			
Austin, TX 78711-3088	(512	)239-0357			
Site Location (Check All That Apply):					
X Recharge Zone	Contributing Zone	Transition Zone			

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	3.594 Acres	\$ 4,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: <u>Uyn Weiner</u> Date: <u>10-30</u>-2023

## **Application Fee Schedule**

**Texas Commission on Environmental Quality** 

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

#### Water Pollution Abatement Plans and Modifications

**Contributing Zone Plans and Modifications** 

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

# Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

**Exception Requests** 

Project	Fee
Exception Request	\$500

**Extension of Time Requests** 

Project	Fee
Extension of Time Request	\$150



# **TCEQ Core Data Form**

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

### **SECTION I: General Information**

1. Reason for Submission (If other is checked please describe in space provided.)

New Pern	nit, Registra	ition or Authorization	(Core Data Form	should be s	submitted	with the prog	gram ap	olication.)			
Renewal	Core Data	Form should be subm	itted with the ren	ewal form)			Other				
2. Customer	Reference	Number (if issued)	_	ollow this li		CII	gulated	d Entity Re	ference	Number (if i	ssued)
CN 6004120	43		-		Registry**	RN					
ECTIO	N II:	Customer	Inform	<u>ation</u>	1						
4. General Cu	istomer In	formation	5. Effective D	Date for Cu	ustomer I	nformation	Update	es (mm/dd/	уууу)		
☐ New Custor ☐Change in Le		િ (Verifiable with the Te	Jpdate to Custom exas Secretary of S			<del></del>	-	egulated Ent	ity Owne	ership	
The Custome	r Name su	ıbmitted here may	be updated au	tomaticall	ly based (	on what is c	urrent	and active	with th	e Texas Seci	etary of State
(SOS) or Texa	s Comptro	oller of Public Acco	unts (CPA).								
6. Customer I	Legal Nam	e (If an individual, pr	int last name first	t: eg: Doe, J	lohn)		<u>If nev</u>	v Customer,	enter pre	evious Custom	er below:
City of Georget	own										
7. TX SOS/CP	A Filing N	umber	8. TX State Ta	<b>ax ID</b> (11 d	ligits)			deral Tax I	D	10. DUNS applicable)	Number (if
							(9 dig	000974		89592372	
						1			1		
11. Type of C		Corpora				Indivi	dual		Partne	rship: 🔲 Ger	ieral 🗌 Limited
		County  Federal	Local  State [	Other		Sole P			Otl		
12. Number o	of Employ	ees					13. I	ndepender	ntly Ow	ned and Ope	erated?
0-20 2	21-100	101-250 251	-500 🛚 501 a	nd higher			⊠ Ye	es	☐ No		
14. Customer	Role (Pro	posed or Actual) – as	it relates to the R	egulated Er	ntity listed	on this form.	Please (	check one of	the follo	wing	
⊠Owner ☐Occupationa	al Licensee	Operator Responsible Pa		ner & Opera CP/BSA App				Other:			
45 84-11	300-1 Inc	lustrial Ave									
15. Mailing											
Address:	City	Georgetown		State	TX	ZIP	7862	6		ZIP + 4	8445
16. Country N	Mailing Inf	ormation (if outside	· USA)		1	L7. E-Mail A	ddress	(if applicabl	e)		
18. Telephon	e Number		10	9. Extensio	on or Cod	e		20. Fax N	umher	(if applicable)	

TCEQ-10400 (11/22) Page 1 of 3

( 512 ) 930-3555	( 512 ) 930-3559
( 312 / 330-3333	( 312 ) 330-3333

## **SECTION III: Regulated Entity Information**

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity" is selected, a new permit application is also required.)											
New Regulated Entity	Update to	Regulated Entity	Name  Update	to Regulated	Entity Inform	ation					
The Regulated Entity Nar as Inc, LP, or LLC).	ne submitte	d may be upda	ted, in order to m	eet TCEQ Coi	e Data Stai	ndards (rer	noval of o	rganizatior	nal endings such		
22. Regulated Entity Nam	<b>ie</b> (Enter nam	e of the site wher	re the regulated action	on is taking plo	ice.)						
South Lake Raw Water Facilit	ies and Intake	2									
23. Street Address of the Regulated Entity:	2044 Cedar	Breaks Road									
(No PO Boxes)	City	Georgetown	State	TX	ZIP	78628		ZIP + 4			
24. County	Williamson	<u> </u>									
	If no Street Address is provided, fields 25-28 are required.										
25. Description to  The South Lake Raw Water Electrical and Chemical Facility is located along Cedar Breaks Road approximately 610 feet south of the intersection of Cedar Breaks and Crockett Gardens Road.											
26. Nearest City State Nearest ZIP Code											
Georgetown TX											
Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).											
27. Latitude (N) In Decim	al:	30.6671	28. Longitude			V) In Decin	nal:	-97.7347			
									Seconds		
Degrees	Minutes		Seconds	Degre	es	Mi	nutes		Seconds		
				Degre	ees	Mi					
29. Primary SIC Code (4 digits)	30.	Secondary SIC igits)			ry NAICS Co			ndary NAI			
29. Primary SIC Code	30.			31. Prima	ry NAICS Co		32. Seco	•			
29. Primary SIC Code (4 digits)	<b>30.</b> (4 d	igits)	Code	<b>31. Prima</b> (5 or 6 digi	ry NAICS Co		32. Seco	•			
29. Primary SIC Code (4 digits) 4941	<b>30.</b> (4 d	igits)	Code	<b>31. Prima</b> (5 or 6 digi	ry NAICS Co		32. Seco	•			
29. Primary SIC Code (4 digits) 4941 33. What is the Primary E	<b>30.</b> (4 d	igits)	Code	<b>31. Prima</b> (5 or 6 digi	ry NAICS Co		32. Seco	•			
29. Primary SIC Code (4 digits) 4941  33. What is the Primary E Raw Water Facility	<b>30.</b> (4 d	igits)	Code	<b>31. Prima</b> (5 or 6 digi	ry NAICS Co		32. Seco	•			
29. Primary SIC Code (4 digits) 4941 33. What is the Primary B Raw Water Facility 34. Mailing	30. (4 d	igits)	Code	<b>31. Prima</b> (5 or 6 digi	ry NAICS Co		32. Seco	gits)			
29. Primary SIC Code (4 digits) 4941 33. What is the Primary E Raw Water Facility  34. Mailing Address:	30. (4 d	igits)	Code	31. Prima (5 or 6 digi	ry NAICS Co		<b>32. Seco</b> (5 or 6 dig	ziP+4			
29. Primary SIC Code (4 digits) 4941 33. What is the Primary E Raw Water Facility 34. Mailing Address: 35. E-Mail Address:	30. (4 d	igits)	Code To not repeat the SIC  State	31. Prima (5 or 6 digi	ry NAICS Cots)  ription.)  ZIP  38. F	de	<b>32. Seco</b> (5 or 6 dig	ziP+4			

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	,	Districts	Edwards Aquifer			Emissions Inventory Air	☐ Industrial Hazardous Waste		
☐ Municipal S	Solid Waste	New Source Review Air	OSSF			Petroleum Storage Tank	☐ PWS		
☐ Sludge ☐ Storm Wat		Storm Water	☐ Title V Air		Tires		Used Oil		
☐ Voluntary (	☐ Voluntary Cleanup ☐ Wastewater		☐ Wastewater Agriculture		☐ Water Rights		Other:		
SECTION IV: Preparer Information									
40. Name:	Samantha Agnie	l		41. Title:		Environmental Engineer			
42. Telephone	2. Telephone Number 43. Ext./Code 44. Fax Number 45. E-Mail Address								

40. Name:	Samantha Agn	iel		41. Title: Environmental Engineer				
42. Telephone	Number	43. Ext./Code	44. Fax Number	45. E-Mail Address				
(713)423-7340	1		( ) -	agnielsj@cdr	nsmith.com			

## **SECTION V: Authorized Signature**

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	CDM Smith, Inc.	Job Title:	Water Res	sources Engineer			
Name (In Print):	Ellyn Weimer, PE		Phone:	( 512 ) 652- <b>5329</b>			
Signature:	allyn Weiner			Date:	10-30-2023		

TCEQ-10400 (11/22) Page 3 of 3

#### Weimer, Ellyn J.

From: Karamalegos, Ana

**Sent:** Wednesday, October 11, 2023 2:53 PM

**To:** Weimer, Ellyn J.; Woelke, Allen

**Subject:** Fwd: [EXTERNAL] Update on South Shore WTP

Follow Up Flag: Follow up Flag Status: Flagged

From: Blank, Scott W CIV USARMY CESWF (USA) <Scott.W.Blank@usace.army.mil>

Sent: Wednesday, October 11, 2023 1:54 PM

**To:** Chris Pousson <chris.pousson@georgetown.org> **Subject:** [EXTERNAL] Update on South Shore WTP

**[EXTERNAL EMAIL]** This email originated from outside of City of Georgetown. DO NOT click links or open attachments unless you recognize and/or trust the sender.

I have been told to let you know that everything is approved and that they are working on the temporary construction easement and they should have it out NLT 27 October 2023. Hope this helps.

Scott W. Blank Lake Manager Lake Georgetown U.S. Army Corps of Engineers 500 Lake Overlook Drive Georgetown, Texas 78633 Office: 512/819-9046

Fax: 512/863-4769

Remember to be SAFE and wear a LIFEJACKET!!

Official Sites: <a href="https://www.swf-wc.usace.army.mil/georgetown">https://www.swf-wc.usace.army.mil/georgetown</a>

Facebook: <a href="http://www.facebook.com/pages/Fort-Worth-District-US-Army-Corps-of-Engineers/188083711219308">http://www.facebook.com/pages/Fort-Worth-District-US-Army-Corps-of-Engineers/188083711219308</a>

County:

Williamson

Parcel:

Parcel 1 Easement

Project:

Wood Avant Investments, Ltd (South Lake)

# EXHIBIT \_\_\_\_\_ PROPERTY DESCRIPTION

DESCRIPTION OF A 0.107 ACRE (4,655 SQUARE FOOT) PARCEL OF LAND SITUATED IN THE JOSEPH FISH SURVEY, ABSTRACT NO. 232 IN WILLIAMSON COUNTY, TEXAS, BEING A PORTION OF THE REMAINDER OF THAT CALLED 2,139.32 ACRE TRACT OF LAND DESCRIBED IN A SPECIAL WARRANTY DEED TO WOOD AVANT INVESTMENTS, LTD RECORDED IN DOCUMENT NO. 2020167463 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS, SAID 0.107 ACRE (4,655 SQUARE FOOT) PARCEL OF LAND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

**BEGINNING** at a calculated point, (Grid Coordinates determined as N=10,215,748.14 E=3,111,987.77), in the northerly boundary line of said remainder of the 2,139.32 acre tract, being the southerly boundary line of that called 18.522 acre tract of land described in a Special Warranty Deed to City of Georgetown recorded in Document No. 2018097168 of the Official Public Records of Williamson County, Texas, same being the northerly boundary line of that called 11.99 acre 80' wide Road Easement (Parcel 8) described in Volume 715, Page 121 of the Deed Records of Williamson County, Texas, for the northwesterly corner and **POINT OF BEGINNING** of the herein described parcel and from which a capped iron rod with plastic cap stamped "Inland-5050" found, being an angle point in the common boundary line of said 18.522 acre tract and said remainder of the 2,139.32 acre tract bears S 50°22'34" W, at a distance of 4.62 feet;

 THENCE, with the common boundary line of said 18.522 acre tract and said remainder of the 2,139.32 acre tract, same being said northerly Road Easement line, N 50°22'34" E for a distance of 25.00 feet to a calculated point;

**THENCE**, departing said 18.522 acre tract, through the interior of said remainder of the 2,139.32 acre tract, the following two (2) courses:

- S 39°49'26 E for a distance of 55.31 feet to a calculated angle point;
- 3) N 50°24'42" E for a distance of 110.08 feet to a calculated point, in the easterly boundary line of said remainder of the 2,139.32 acre tract, same being the easterly line of said 11.99 acre Road Easement, also being the westerly boundary line of that called 249.00 acre tract of land (Schedule "A" Tract No. 105-1) described in a Declaration of Taking to United States of America recorded in Volume 550, Page 553 of the Deed Records of Williamson County, Texas, same being the westerly line of that called 11.158 acre (120' wide Road Easement Exhibit "A" Tract "A") described in Document No. 2015073475, of the Official Public Records of Williamson County, Texas, for the northeasterly corner of the herein described parcel, and from which a nail in cedar post found, being the common corner of said 18.522 acre tract and said remainder of the 2,139.32 acre tract, same being in the westerly boundary line of said 249.00 acre tract bears N 22°29'46" W at a distance of 57.94 feet;
- 4) **THENCE**, with the common boundary line of said 249.00 acre tract and said remainder of the 2,139.32 acre tract, **S 22°29'46" E** for a distance of **26.12** feet to a 60d nail found in the southerly line of said 80 foot wide road easement, for the southeasterly corner of the herein described parcel;

**THENCE**, departing said 249.00 acre tract, through the interior of said remainder of the 2,139.32 acre tract, the following two (2) courses:

County:

Williamson

Parcel:

Parcel 1 Easement

Project:

Wood Avant Investments, Ltd (South Lake)

- 5) with said southerly line of 80 foot wide road easement, S 50°24'42" W for a distance of 127.22 feet to the calculated southwesterly corner hereof;
- 6) departing said road easement, N 39°52'47" W for a distance of 80.26 feet to the POINT OF BEGINNING, containing 0.107 acres (4,655 square feet) of land, more or less.

**NOTE:** This parcel is accompanied by a 4,202 Square Foot, 30' wide T.C.E. (Temporary Construction Easement) being coincident with, and northerly and westerly of the above described course 2 through 3 as shown on the accompanying sketch.

This property description is accompanied by a separate parcel plat.

All bearings recited herein are based on the Texas State Plane Coordinate System, Central Zone No. 4203, NAD 83.

THE STATE OF TEXAS

§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF WILLIAMSON

88

That I, M. Stephen Truesdale, a Registered Professional Land Surveyor, do hereby certify that the above description is true and correct to the best of my knowledge and belief and that the property described herein was determined by a survey made on the ground under my direct supervision.

WITNESS MY HAND AND SEAL at Round Rock, Williamson County, Texas.

M. Stephen Truesdale

Registered Professional Land Surveyor No. 4933

Licensed State Land Surveyor

Inland Geodetics, LLC


Firm Registration No: 100591-00 1504 Chisholm Trail Road, Suite 103

Round Rock, TX 78681

Date

M. STEPHEN TRUESDALE 1

S:\CDM-SMITH PROJECTS\SOUTH LAKE WATER TREATMENT PLANT\PARCEL\PARCEL 1-WOOD AVANT INVESTMENTS\CDM-SMITH-WOOD-AVANT-SOUTH LAKE -EASEMENT PARCEL 1-rev.doc



Deed Report Wed Apr 06 11:51:14 2022

Deed Name: PARCEL 1-WOOD-AVANT-DESC-REV

Starting Coordinates: Northing 10218411.55, Easting 3111415.80

Distance	Type	Radius	Arc Len	Delta	Tangent	Description
25.00	LINE					
55.31	LINE					
110.08	LINE					
26.12	LINE					
127.22	LINE					
80.26	LINE					
	Distance 25.00 55.31 110.08 26.12 127.22 80.26	55.31 LINE 110.08 LINE 26.12 LINE 127.22 LINE	25.00 LINE 55.31 LINE 110.08 LINE 26.12 LINE 127.22 LINE			

Ending Coordinates: Northing 10218411.55, Easting 3111415.80

Area: 4654.57 S.F., 0.1069 Acres Total Perimeter Distance> 423.99

Closure Error Distance> 0.0027 Error Bearing> S 82°20'58" W

Closure Precision> 1 in 158804.6

Wed Apr 06 09:31:48 2022

Deed Report
Deed Name: PARCEL 1-WOOD-AVANT-SKETCH-REV

Starting Coordinates: Northing 10218073.25, Easting 3111562.56

Bearing	Distance	Type	Radius	Arc Len	Delta	Tangent	Description
N 50°22'34" E	25.00	LINE					
S 39°49'26" E	55.31	LINE					
N 50°24'42" E	110.08	LINE					
S 22°29'46" E		LINE					
s 50°24'42" W	127.22	LINE					
N 39°52'47" W	80.26	LINE					

Ending Coordinates: Northing 10218073.25, Easting 3111562.57

Area: 4654.57 S.F., 0.1069 Acres
Total Perimeter Distance> 423.99
Closure Error Distance> 0.0027 Error Bearing> S 82°20'58" W
Closure Precision> 1 in 158804.6

County:

Williamson

Parcel:

Parcel 2 Easement

Project:

United States of America (South Lake)

# EXHIBIT \_\_\_\_\_PROPERTY DESCRIPTION

DESCRIPTION OF A 3.594 ACRE (156,563 SQUARE FOOT) PARCEL OF LAND SITUATED IN THE JOSEPH FISH SURVEY, ABSTRACT NO. 232 IN WILLIAMSON COUNTY, TEXAS, BEING A PORTION OF THAT CALLED 249.00 ACRE TRACT OF LAND (SCHEDULE "A" TRACT NO. 105-1) DESCRIBED IN A DECLARATION OF TAKING TO UNITED STATES OF AMERICA RECORDED IN VOLUME 550, PAGE 553 OF THE DEED RECORDS OF WILLIAMSON COUNTY, TEXAS, AND ALSO BEING A PORTION OF THAT CALLED 333.00 ACRE TRACT OF LAND DESCRIBED IN A GENERAL WARRANTY DEED TO UNITED STATES OF AMERICA RECORDED IN VOLUME 516, PAGE 349 OF THE DEED RECORDS OF WILLIAMSON COUNTY, TEXAS, SAID 3.594 ACRE (156,563 SQUARE FOOT) PARCEL OF LAND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

**BEGINNING** at a calculated point, (Grid Coordinates determined as N=10,215,791.75 E=3,112,127.26), being in the westerly boundary line of said 249.00 acre tract and the westerly line of a 1.07 acre 80 foot wide road easement recorded in Volume 715, Page 110 of the Deed Records of Williamson County, Texas, same being the easterly boundary line of the remainder of that called 2,139.32 acre tract of land described in a Special Warranty Deed to Wood Avant Investments, LTD recorded in Document No. 2020167463 of the Official Public Records of Williamson County, Texas, and from which a nail in cedar post found, being the common corner of that called 18.522 acre tract described in a Special Warranty Deed to City of Georgetown recorded in Document No. 2018097168 of the Official Public Records of Williamson County, Texas, and said remainder of the 2,139.32 acre tract, same being in the westerly boundary line of said 249.00 acre tract bears N 22°29'46" W at a distance of 57.94 feet;

**THENCE,** departing the easterly boundary line of said remainder of the 2,139.32 acre tract, being said westerly line of the 80 foot wide road easement, through the interior of said 249.00 acre tract, and said 333.00 acre tract, the following thirty one (31) courses:

- 1) N 50°24'42" E for a distance of 657.96 feet to a calculated angle point;
- 2) \$ 39°14'20" E for a distance of 25.00 feet to a calculated point of curvature to the left;
- along said curve to the left, having a delta angle of 31°28'23", a radius of 642.26 feet, an arc length of 352.80 feet and a chord which bears S 46°10'31" E, for a distance of 348.38 feet a calculated point of non tangency;
- 4) N 49°59'56" E for a distance of 66.19 feet to a calculated angle point;
- 5) **S** 85°00'04" **E** for a distance of **619.81** feet to a calculated angle point;
- 6) N 46°03'03" E for a distance of 39.88 feet to a calculated point of curvature to the right;
- 7) along said curve to the right, having a delta angle of 09°13'32", a radius of 1,090.00 feet, an arc length of 175.51 feet and a chord which bears N 39°10'45" E, for a distance of 175.32 feet a calculated point of non tangency;
- 8) N 43°47'31" E for a distance of 246.66 feet to a calculated point of curvature to the right;
- along said curve to the right, having a delta angle of 19°35'48", a radius of 860.00 feet, an arc length of 294.14 feet and a chord which bears N 53°35'25" E, for a distance of 292.71 feet a calculated point of non tangency;
- 10) N 63°23'19" E for a distance of 828.65 feet to a calculated ell corner;

Page 2 of 5 Rev: 04-05-22

County:

Williamson

Parcel:

Parcel 2 Easement

Project:

United States of America (South Lake)

- 11) N 26°36'05" W for a distance of 44.62 feet to a calculated angle point;
- 12) N 51°59'35" E for a distance of 300.36 feet to the calculated northeasterly corner of the herein described parcel (currently inundated);
- 13) S 37°51'41" E for a distance of 60.14 feet to the calculated angle point (currently inundated);
- 14) **S 26°35'59"** E for a distance of **74.99** feet to the calculated southeasterly corner of the herein described parcel (currently inundated);
- 15) S 63°23'19" W for a distance of 242.87 feet to a calculated angle point;
- 16) S 26°36'41" E for a distance of 5.00 feet to a calculated angle point;
- 17) S 63°23'19" W for a distance of 891.95 feet to a calculated point of curvature to the left;
- 18) along said curve to the left, having a delta angle of 19°35'48", a radius of 825.00 feet, an arc length of 282.17 feet and a chord which bears \$ 53°35'25" W, for a distance of 280.80 feet a calculated point of non tangency;
- 19) S 43°47'31" W for a distance of 246.66 feet to a calculated point of curvature to the left;
- 20) along said curve to the left, having a delta angle of 14°11'37", a radius of 1,053.96 feet, an arc length of 261.09 feet and a chord which bears S 36°42'08" W, for a distance of 260.43 feet a calculated point of non tangency;
- 21) S 29°36'40" W for a distance of 25.98 feet to a calculated angle point,
- 22) N 85°00'04" W for a distance of 214.70 feet to a calculated angle point;
- 23) N 04°59'57" E for a distance of 38.00 feet to a calculated angle point;
- 24) N 85°00'04" W for a distance of 167.67 feet to a calculated angle point;
- 25) N 04°59'56" E for a distance of 10.00 feet to a calculated angle point;
- 26) N 85°00'04" W for a distance of 209.42 feet to a calculated angle point;
- 27) S 49°59'56" W for a distance of 52.04 feet to a calculated angle point;
- 28) N 63°24'51" W for a distance of 26.11 feet to a calculated angle point;
- 29) S 49°59'56" W for a distance of 10.89 feet to a calculated point of curvature to the right;
- 30) along said curve to the right, having a delta angle of 29°37'13", a radius of 742.47 feet, an arc length of 383.84 feet and a chord which bears N 47°13'01" W, for a distance of 379.58 feet a calculated point of non tangency;
- 31) **S 50°24'42 W**, in part with the southerly line of said 1.07 acre roadway easement, for a distance of **639.89** feet to a 60d nail found, being in the common boundary line of said remainder of the 2,139.32 acre tract and said 249.00 acre tract, for the southwesterly corner of said 80 foot wide road easement and of the herein described parcel;

County:

Williamson

Parcel:

Parcel 2 Easement

Project:

United States of America (South Lake)

32) **THENCE**, with said common boundary line, **N 22°29'46" W** for a distance of **26.12** feet to the **POINT OF BEGINNING**, containing 3.594 acres (156,563 square feet) of land, more or less.

NOTE: This parcel is accompanied by 3 T.C.E.'s (Temporary Construction Easement):

- 1. A 19,603 Square Foot, 30' wide easement being coincident with, parallel, and northerly of the above described course 1 as shown on the accompanying sketch.
- 2. A 50,268 Square Foot, 20' wide easement being coincident with, parallel, and northerly of the above described in part course 5, through 11 and in part course 12 as shown on the accompanying sketch.
- 3. And A 15,760 Square Foot, 40' wide easement being coincident with, parallel, and westerly of the above described course 30 as shown on the accompanying sketch.

This property description is accompanied by a separate parcel plat.

All bearings recited herein are based on the Texas State Plane Coordinate System, Central Zone No. 4203, NAD 83.

THE STATE OF TEXAS

Ş

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF WILLIAMSON

That I, M. Stephen Truesdale, a Registered Professional Land Surveyor, do hereby certify that the above description is true and correct to the best of my knowledge and belief and that the property described herein was determined by a survey made on the ground under my direct supervision.

WITNESS MY HAND AND SEAL at Round Rock, Williamson County, Texas.

M. Stephen Truesdale

Registered Professional Land Surveyor No. 4933

Licensed State Land Surveyor

Inland Geodetics, LLC


Firm Registration No: 100591-00 1504 Chisholm Trail Road, Suite 103

Round Rock, TX 78681

Date


M STEPHEN TRUESDALE

S:\CDM-SMITH PROJECTS\SOUTH LAKE WATER TREATMENT PLANT\PARCEL\PARCEL 1-WOOD AVANT INVESTMENTS\CDM-SMITH-USA-SOUTH LAKE -EASEMENT PARCEL 2-rev.doc



S:\CDM-SMITH PROJECTS\SOUTH LAKE WATER TREATMENT PLANT\PARCEL\PARCEL 2-UNITED STATES OF EMERICA\CDM-SMITH-USA-SOUTH LAKE WATER TREATMENT PLANT-W-ESNT-PG1.dwg

4



I) ALL BEARINGS SHOWN HEREON ARE BASED ON GRID BEARING. ALL DISTANCES ARE SURFACE VALUES BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, NAD 83, CENTRAL ZONE.

JOSEPH FISH SURVEY ABSTRACT NO. 232

UNITED STATES OF AMERICA

<u></u>

(333.00 AC.) OL. 516, PG. 349 D.R.W.C.T.

THERE MAY BE OTHER INSTRUMENTS OF RECORD THAT AFFECT THIS TRACT 2) THIS SURVEY WAS PERFORMED WITHOUT BENEFIT OF A TITLE ABSTRACT. NOT DEPICTED HEREON

THE PROPERTY SHOWN HEREON WAS DETERMINED BY A SURVEY MADE ON THE GROUND UNDER MY DIRECT SUPERVISION. HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECT AND THAT

M. STEPHEN TRUESDALE 2 DATE

1504 CHISHOLM TRAIL ROAD, SUITE 103

ROUND ROCK, TEXAS 78681 FIRM REGISTRATION NO. 100591-00 REGISTERED PROFESSIONAL LAND SURVEYOR NO. 4933 INLAND GEODETICS, LLC

246.66	S43°47'31"W	LI3
5.00'	S26°36'41"E	딛
74.99'	S26°35'59"E	Ξ
60.14	S37°51'41"E	등
44.62	N26°36'05"W	L9
246.66	N43°47'31"E	6
DISTANCE	DIRECTION	NO.

(

1/2 " IRON ROD W/ PLASTIC CALCULATED POINT

LEGEND

0

CORPS OF ENGINEERS MONUMENT

60d NAIL FOUND CAP FOUND (AS NOTED)



O.P.R.W.C.T. OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS

DISTANCE BREAK

OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS DEED RECORDS OF WILLIAMSON COUNTY, TEXAS

D.R.W.C.T. O.R.W.C.T.

RECORD INFORMATION

PROPERTY LINE

PARCEL PLAT SHOWING PROPERTY OF

# UNITED STATES OF AMERICA

CITY OF GEORGETOWN WATER TREATMENT PLANT PROJECT

PROFESSIONAL LAND SURVEYORS 1504 CHISHOLM TRAIL RD, STE. 103 ROUND ROCK, TX. 78681 PH. (512) 238-1200, FAX (512) 238-1251 PHRM REGISTRATION NO. 100591-00

1"=200' SCALE GEODETICS I INLANDO

3.594 156,563 EASEMENT ACRES SQ. F

REV: 04-05-2022

PAGE 5 OF U

WILLIAMSON COUNTY

S:\CDM-SMITH PROJECTS\SOUTH LAKE WATER TREATMENT PLANT\PARCEL\PARCEL 2-UNITED STATES OF EMERICA\CDM-SMITH-USA-SOUTH LAKE WATER TREATMENT PLANT-W-ESMT-PG2.dwg

Deed Report

Deed Name: PARCEL 2-USA-SKETCH

Starting Coordinates: Northing 10225047.10, Easting 3116349.02

```
Arc Len Delta
                                                              Tangent Description
                                Radius
Bearing
               Distance Type
N 50°24'42" E 657.96
                        LINE
S 39°14'20" E
               25.00
                        LINE
                                         352.80
                                                  31°28'23"
                                                              180.97
S 46°10'31" E
               348.38
                        CURVE L 642.26
                                Rad-In: N 59°33'41" E Rad-Out: N 28°05'18" E
N 49°59'56" E
               66.19
                        LINE
S 85°00'04" E
               619.81
                        LINE
N 46°03'03" E
               39.88
                        LINE
                        CURVE R 1090.00 175.51
                                                  9°13'32"
N 39°10'45" E
               175.32
                                Rad-In: S 55°26'01" E Rad-Out: S 46°12'29" E
N 43°47'31" E
               246.66
                        LINE
                                                  19°35'48" 148.52
N 53°35'25" E
               292.71
                        CURVE R 860.00
                                         294.14
                                Rad-In: S 46°12'29" E Rad-Out: S 26°36'41" E
N 63°23'19" E
               828.65
                        LINE
N 26°36'05" W
               44.62
                        LINE
N 51°59'35" E
               300.36
                        LINE
S 37°51'41" E
               60.14
                        LINE
               74.99
S 26°35'59" E
                        LINE
S 63°23'19" W
               242.87
                        LINE
S 26°36'41" E
               5.00
                        LINE
s 63°23'19" W
               891.95
                        LINE
                                                  19°35'48" 142.48
s 53°35'25" W
                        CURVE L 825.00 282.17
               280.80
                                Rad-In: S 26°36'41" E Rad-Out: S 46°12'29" E
s 43°47'31" W
               246.66
                        LINE
                                                  14°11'37" 131.22
                                        261.09
                        CURVE L 1053.96
S 36°42'08" W
               260.43
                                Rad-In: S 46°12'03" E Rad-Out: S 60°23'40" E
S 29°36'40" W
               25.98
                        LINE
N 85°00'04" W
               214.70
                        LINE
N 04°59'57" E
               38.00
                        LINE
N 85°00'04" W
               167.67
                        LINE
N 04°59'56" E
               10.00
                        LINE
N 85°00'04" W
               209.42
                        LINE
S 49°59'56" W
               52.04
                        LINE
               26.11
N 63°24'51" W
                        LINE
S 49°59'56" W
               10.89
                        LINE
                        CURVE R 742.47 383.84 29°37'13" 196.31
N 47°13'01" W
               379.58
                                Rad-In: N 27°58'23" E Rad-Out: N 57°35'36" E
S 50°24'42" W
               639.89
                        LINE
N 22°29'46" W
               26.12
                        LINE
```

Ending Coordinates: Northing 10225047.09, Easting 3116349.02

Area: 156563.46 S.F., 3.5942 Acres
Total Perimeter Distance> 7521.11
Closure Error Distance> 0.0150 Error Bearing> N 01°46'38" E
Closure Precision> 1 in 500618.9

Deed Report

Deed Name: PARCEL 2-USA-DESC

Starting Coordinates: Northing 10220085.45, Easting 3121666.20

```
Tangent Description
                                          Arc Len Delta
Bearing
               Distance Type
                                Radius
N 50°24'42" E
              657.96
                        LINE
S 39°14'20" E
               25.00
                        LINE
                                                   31°28'23"
                                          352.80
                                                              180.97
S 46°10'31" E
               348.38
                        CURVE L 642.26
                                 Rad-In: N 59°33'41" E Rad-Out: N 28°05'18" E
N 49°59'56" E
               66.19
                        LINE
S 85°00'04" E
               619.81
                        LINE
N 46°03'03" E
               39.88
                        LINE
N 39°10'45" E
               175.32
                        CURVE R 1090.00 175.51
                                                   9°13'32"
                                                              87.94
                                Rad-In: S 55°26'01" E Rad-Out: S 46°12'29" E
N 43°47'31" E
               246.66
                        LINE
                                                   19°35'48" 148.52
N 53°35'25" E
                        CURVE R 860.00
                                          294.14
               292.71
                                Rad-In: S 46°12'29" E Rad-Out: S 26°36'41" E
N 63°23'19" E
               828.65
                        LINE
N 26°36'05" W
               44.62
                        LINE
N 51°59'35" E
               300.36
                        LINE
S 37°51'41" E
               60.14
                        LINE
S 26°35'59" E
               74.99
                        LINE
s 63°23'19" W
               242.87
                        LINE
S 26°36'41" E
               5.00
                        LINE
S 63°23'19" W
               891.95
                        LINE
                        CURVE L 825.00 282.17
                                                   19°35'48" 142.48
s 53°35'25" W
               280.80
                                Rad-In: S 26°36'41" E Rad-Out: S 46°12'29" E
s 43°47'31" W
               246.66
                        LINE
                                                   14°11'37" 131.22
                        CURVE L 1053.96 261.09
S 36°42'08" W
               260.43
                                Rad-In: S 46°12'04" E Rad-Out: S 60°23'41" E
S 29°36'40" W
               25.98
                        LINE
N 85°00'04" W
               214.70
                        LINE
N 04°59'57" E
               38.00
                        LINE
N 85°00'04" W
               167.67
                        LINE
N 04°59'56" E
               10.00
                        LINE
N 85°00'04" W
               209.42
                        LINE
S 49°59'56" W
               52.04
                        LINE
N 63°24'51" W
               26.11
                        LINE
S 49°59'56" W
               10.89
                        LINE
                        CURVE R 742.47 383.84 29°37'13" 196.31
N 47°13'01" W
               379.58
                                Rad-In: N 27°58'22" E Rad-Out: N 57°35'35" E
S 50°24'42" W
               639.89
                        LINE
N 22°29'46" W
               26.12
                        LINE
```

Ending Coordinates: Northing 10220085.44, Easting 3121666.20

Area: 156563.45 S.F., 3.5942 Acres
Total Perimeter Distance> 7521.11
Closure Error Distance> 0.0150 Error Bearing> N 01°46'22" E
Closure Precision> 1 in 500674.1



# CITY OF GEORGETOWN, TEXAS

# PACKAGE 1: SOUTH LAKE WATER TREATMENT PLANT

CITY COUNCIL

**MAYOR** 

JOSH SCHROEDER

CITY COUNCIL MEMBERS

AMANDA PARR

DISTRICT 1

**DISTRICT 2** 

SHAWN HOOD

MIKE TRIGGS

DISTRICT 3

STEVE FOUGHT

DISTRICT 4

**KEVIN PITTS** 

MAYOR PRO TEM / DISTRICT 5

VACANT

**DISTRICT 6** 

TOMMY GONZALEZ

DISTRICT 7

CITY MANAGER

**DAVID MORGAN** 

ASSISTANT CITY MANAGERS

LAURIE BREWER
WAYNE NERO

WATER SERVICES UTILITY DIRECTOR

CHELSEA SOLOMON, P.E.

SYSTEMS ENGINEERING DIRECTOR

WESLEY WRIGHT, P.E.


**UTILITY ENGINEER** 

DAVID MUNK, P.E.

PROJECT No PRJ000101

BID NO. 202203 CONTRACT ID NO. 22-0018-CIP

OCTOBER 2021



**LOCATION PLAN** 



AUSTIN, TEXAS

Transportation

CONFORMED DRAWINGS

VOLUME I OF III

THY OF GEORGETOWN, CIP MANAGER

DATE

CITY OF GEORGETOWN, SYSTEM ENGINEERING DIRECTOR

CIP/2C/2/
DATE

SARAH ALBERS STEWART

Energy

Couch X- Sauch

TEXAS REGISTRATION NUMBER F-3043

10-26-202/

PREPARED BY:

- - :::::: - -

Water

Environment

Facilities

**VOLUME I of III** PLAN AND PROFILE STA 20+00 TO STA 25+00 RAW WATER LINE RAW WATER ELECTRICAL BUILDING ELEVATIONS AM-3 CP-7 PLAN AND PROFILE STA 25+00 TO STA 30+00 RAW WATER LINE RAW WATER ELECTRICAL BUILDING BUILDING SECTIONS AM-4 GENERAL CP-8 PLAN AND PROFILE STA 30+00 TO STA 34+79.21 RAW WATER LINE AM-5 RAW WATER ELECTRICAL BUILDING WALL SECTIONS G-0 COVER SHEET CZ-1 STANDARD CIVIL DETAILS I RAW WATER CHEMICAL BUILDING LIFE SAFETY PLAN AND CODE KEY DETERMINATIONS AN-1 SHEET INDEX I STANDARD CIVIL DETAILS II CZ-2 RAW WATER CHEMICAL BUILDING FLOOR PLAN AND ROOF PLAN SHEET INDEX II G-2 CZ-3 STANDARD CIVIL DETAILS III RAW WATER CHEMICAL BUILDING ELEVATIONS AN-3 SHEET INDEX III CZ-4 STANDARD CIVIL DETAILS IV AN-4 RAW WATER CHEMICAL BUILDING BUILDING SECTIONS G-4 OVERALL CONTRACT DELINEATION CZ-5 STANDARD CIVIL DETAILS V AN-5 RAW WATER CHEMICAL BUILDING WALL SECTIONS OVERALL PACKAGE 1 PLAN CZ-6 STANDARD CIVIL DETAILS VI AZ-1 ARCHITECTURAL DOOR DETAILS I GENERAL LEGEND AND NOTES I CZ-7 STANDARD CIVIL DETAILS VII ARCHITECTURAL DOOR, WINDOW, AND LOUVER DETAILS AZ-2 GENERAL LEGEND AND NOTES II CZ-8 STANDARD CIVIL DETAILS VIII AZ-3 ARCHITECTURAL WALL DETAILS STANDARD ABBREVIATIONS CZ-9 ARCHITECTURAL ROOF DETAILS - I STANDARD CIVIL DETAILS IX AZ-4 PROCESS FLOW DIAGRAM LIQUIDS STANDARD CIVIL DETAILS X CZ-10 AZ-5 ARCHITECTURAL ROOF DETAILS - II G-10 PROCESS FLOW DIAGRAM SOLIDS CZ-11 STANDARD CIVIL DETAILS XI AZ-6 ARCHITECTURAL MISCELLANEOUS AND ROOF DETAILS - III WATER / MASS BALANCE STANDARD CIVIL DETAILS XIII CZ-12 AZ-7 ARCHITECTURAL DUMPSTER ENCLOSURE AND ROADSIDE SIGNAGE HYDRAULIC PROFILE - RAW WATER PUMP STATION G-12A CZ-13 STANDARD CIVIL DETAILS XIII HYDRAULIC PROFILE - TREATMENT CZ-14 STANDARD CIVIL DETAILS XIV G-13 HYDRAULIC PROFILE - RESIDUALS **VOLUME II of III** CZ-15 STANDARD CIVIL DETAILS XV G-14 DESIGN CRITERIA TABLES I **STRUCTURAL** CZ-16 STANDARD CIVIL DETAILS XVI DESIGN CRITERIA TABLES II CZ-17 STANDARD CIVIL DETAILS XVII STRUCTURAL DESIGN CRITERIA AND GENERAL NOTES AREA CLASSIFICATION AND MATERIALS SCHEDULE G-16 CZ-18 STANDARD CIVIL DETAILS XVIII S-2 STRUCTURAL GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS PIPE SCHEDULE STRUCTURAL SPECIAL INSPECTIONS I S-3 CONSTRUCTION SEQUENCING PLAN STRUCTURAL SPECIAL INSPECTIONS II WATER TREATMENT PLANT SITE PROFILE **ARCHITECTURAL** TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 OVERALL PLAN ABBREVIATIONS, SYMBOLS, LEGENDS AND NOTES TREATMENT STRUCTURE TRAINS 1 AND 2 FOUNDATION PLAN A-2 ACCESSIBILITY STANDARDS I SA-3 TREATMENT STRUCTURE TRAINS 1 AND 2 TOP PLAN ACCESSIBILITY STANDARDS II A-3 GENERAL CIVIL NOTES SA-4 TREATMENT STRUCTURE TRAINS 3 AND 4 FOUNDATION PLAN A-4 DOOR SCHEDULE OVERALL PROJECT CIVIL PLAN TREATMENT STRUCTURE TRAINS 3 AND 4 TOP PLAN WINDOW SCHEDULE A-5 C-3 WATER TREATMENT PLANT OVERALL SITE PLAN TREATMENT STRUCTURE TRAINS 1 AND 2 ENLARGED FOUNDATION PLAN I FINISH SCHEDULE WATER TREATMENT PLANT EXISTING SITE PLAN AND CONTROL PLAN TREATMENT STRUCTURE TRAINS 1 AND 2 ENLARGED FOUNDATION PLAN II TREATMENT STRUCTURE LIFE SAFETY PLAN AND CODE KEY DETERMINATIONS AA-1 WATER TREATMENT PLANT TEMPORARY EROSION AND SEDIMENTATION CONTROL PLAN SA-8 TREATMENT STRUCTURE TRAINS 1 AND 2 ENLARGED TOP PLAN I TREATMENT STRUCTURE PARTIAL FLOOR AND ROOF PLANS I AA-2 WATER TREATMENT PLANT SITE CLEARING AND TREE PROTECTION PLAN SA-9 TREATMENT STRUCTURE TRAINS 1 AND 2 ENLARGED TOP PLAN II AA-3 TREATMENT STRUCTURE PARTIAL FLOOR AND ROOF PLANS II WATER TREATMENT PLANT SITE STAKING AND FENCING PLAN AND BORING PLAN TREATMENT STRUCTURE TRAINS 3 AND 4 ENLARGED FOUNDATION PLAN TREATMENT STRUCTURE ELEVATIONS AA-4 RAW WATER OVERALL SITE LAYOUT, CONTROL AND BORING PLAN SA-11 TREATMENT STRUCTURE TRAINS 3 AND 4 ENLARGED FOUNDATION PLAN II TREATMENT STRUCTURE ELECTRICAL AND BLOWER BUILDING SECTIONS AND WALL SECTIONS RAW WATER PUMP STATION PROPOSED SITE PLAN SA-12 TREATMENT STRUCTURE TRAINS 3 AND 4 ENLARGED TOP PLAN I AA-6 TREATMENT STRUCTURE CONTROL BOOTH RAW WATER PUMP STATION SITE CLEARING AND TEMPORARY EROSION AND SEDIMENTATION CONTROL PLAN SA-13 TREATMENT STRUCTURE TRAINS 3 AND 4 ENLARGED TOP PLAN I AF-1 CHEMICAL FACILITY LIFE SAFETY PLAN AND CODE KEY DETERMINATIONS RAW WATER PUMP STATION SITE STAKING AND FENCING PLAN SA-14 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 DETAILS I CHEMICAL FACILITY FLOOR PLAN RAW WATER ELECTRICAL AND CHEMICAL BUILDINGS PROPOSED SITE PLAN SA-15 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 DETAILS II CHEMICAL FACILITY ROOF PLAN RAW WATER ELECTRICAL AND CHEMICAL BUILDINGS SITE CLEARING, DEMOLITION AND TEMPORARY EROSION AND SEDIMENTATION CONTROL AF-3 SA-16 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 DETAILS III CHEMICAL FACILITY ELEVATIONS I TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTIONS RAW WATER ELECTRICAL AND CHEMICAL BUILDINGS SITE STAKING AND FENCING PLAN AF-5 CHEMICAL FACILITY ELEVATIONS II SA-18 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTION II CR-1 WATER TREATMENT PLANT OVERALL PAVING, PERMANENT EROSION/SEDIMENTATION CONTROL AND GRADING KEY PLAN AF-6 CHEMICAL FACILITY BUILDING SECTIONS SA-19 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTION III WATER TREATMENT PLANT PAVING AND GRADING DETAILS I DEWATERING BUILDING LIFE SAFETY PLAN AND CODE KEY DETERMINATIONS TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTION IV WATER TREATMENT PLANT PAVING AND GRADING DETAILS II **DEWATERING BUILDING FLOOR PLAN** AH-2 SA-21 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTIONS  ${\sf V}$ CR-4 WATER TREATMENT PLANT PAVING AND GRADING DETAILS III DEWATERING BUILDING ROOF PLAN TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTION VI SA-22 WATER TREATMENT PLANT PAVING AND GRADING DETAILS IV **DEWATERING BUILDING ELEVATIONS** AH-4 SA-23 TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTIONS VII CR-6 WATER TREATMENT PLANT PAVING AND GRADING DETAILS V AH-5 **DEWATERING BUILDING ELEVATIONS II** TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SECTION VIII SA-24 WATER TREATMENT PLANT PLANT ROAD PROFILE I DEWATERING BUILDING SECTIONS FREATMENT STRUCTURE TRAINS 1,2,3 AND 4 STAIR PLAN DETAILS AND SECTIONS WATER TREATMENT PLANT PLANT ROAD PROFILE II DEWATERING BUILDING WALL SECTIONS TREATMENT STRUCTURE TRAINS 1,2,3 AND 4 SLUDGE VAULT PLANS AND SECTION RAW WATER PUMP STATION PAVING AND GRADING PLAN DEWATERING BUILDING WALL SECTIONS II TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 OVERALL PLAN RAW WATER ELECTRICAL AND CHEMICAL BUILDINGS PAVING AND GRADING PLAN ADMINISTRATION BUILDING LIFE SAFTEY AND CODE KEY DETERMINATIONS TRANSFER PUMP STATION 1 AND DISINFECTION BASIN 1 FOUNDATION PLAN CR-11 TYPICAL ROAD SECTIONS AND PAVING DETAILS SB-3 TRANSFER PUMP STATION 1 AND DISINFECTION BASIN 1 TOP PLAN DRAINAGE AREA MAP ADMINISTRATION BUILDING ROOF PLAN SB-4 TRANSFER PUMP STATION 2 AND DISINFECTION BASIN 2 FOUNDATION PLAN CR-13 DRAINAGE CALCULATIONS ADMINISTRATION BUILDING REFLECTED CEILING PLAN AI-4 TRANSFER PUMP STATION 2 AND DISINFECTION BASIN 2 TOP PLAN CR-14 WATER QUALITY POND STORM SEWER PROFILES ADMINISTRATION BUILDING ELEVATIONS DISINFECTION BASINS 1 & 2 PIPE SUPPORT SLAB PLAN SB-6 CR-15 WATER QUALITY POND PLAN AND DETAILS AI-6 ADMINISTRATION BUILDING BUILDING SECTIONS SB-7 TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 SECTIONS I CR-16 WATER QUALITY POND CROSS SECTIONS I AI-7 ADMINISTRATION BUILDING WALL SECTIONS SB-8 TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 SECTIONS II WATER QUALITY POND CROSS SECTIONS II AI-8 ADMINISTRATION BUILDING WALL SECTIONS II SB-9 TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 SECTIONS III CR-18 WATER TREATMENT PLANT ROAD DRAINAGE DETAIL AI-9 ADMINISTRATION BUILDING WALL SECTIONS III SB-10 TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 DETAILS I WATER TREATMENT PLANT YARD PIPING KEY PLAN CY-1 ADMINISTRATION BUILDING CONTROL ROOM ENLARGED PLAN AND INTERIOR ELEVATIONS SB-11 TRANSFER PUMP STATIONS 1 & 2 AND DISINFECTION BASINS 1 & 2 STAIR DETAILS AND SECTIONS CY-2 WATER TREATMENT PLANT YARD PIPING PLAN DETAILS I ADMINISTRATION BUILDING CONFERENCE ROOM ENLARGED PLAN AND INTERIOR ELEVATIONS AI-11 SD-1 HIGH SERVICE PUMP STATION STRUCTURAL PLANS CY-3 WATER TREATMENT PLANT YARD PIPING PLAN DETAILS II AI-12 ADMINISTRATION BUILDING LABORATORY ENLARGED PLAN AND INTERIOR ELEVATIONS SD-2 FILTER BACKWASH PUMP STATION STRUCTURAL PLANS AND SECTIONS CY-4 WATER TREATMENT PLANT YARD PIPING PARTIAL PLAN DETAILS III ADMINISTRATION BUILDING LABORATORY INTERIOR ELEVATIONS AI-13 SD-3 HIGH SERVICE PUMP STATION STRUCTURAL SECTIONS CY-5 WATER TREATMENT PLANT 8" FILTRATE WATER / 12" SANITARY SEWER PROFILE 1 ADMINISTRATION BUILDING BREAK ROOM ENLARGED PLAN AND INTERIOR ELEVATIONS Al-14 SE-1 FILTRATE LIFT STATION STRUCTURAL PLANS CY-6 WATER TREATMENT PLANT 48" FILTERED WATER PROFILE 2 ADMINISTRATION BUILDING RESTROOM ENLARGED PLAN, ELEVATION AND TOILET ACCESSORIES LEGEND AI-15 SE-2 FILTRATE LIFT STATION STRUCTURAL SECTION CY-7 WATER TREATMENT PLANT 42" FINISHED WATER PROFILE 3 AND 48" FINISHED WATER PROFILE 4 AI-16 ADMINISTRATION BUILDING RESTROOM INTERIOR ELEVATIONS SF-1 CHEMICAL FACILITY STRUCTURAL FOUNDATION PLAN CY-8 WATER TREATMENT PLANT 30" BACKWASH WATER PROFILE 6 AI-17 ADMINISTRATION BUILDING INTERIOR ELEVATIONS SF-2 CHEMICAL FACILITY STRUCTURAL SECTIONS CY-9 WATER TREATMENT PLANT 36" RECYCLE WATER PROFILE 7, 30" WASTE BACKWASH WATER PROFILE 8, AND 16" RCW PROFILE 9 AI-18 ADMINISTRATION BUILDING MILLWORKS SECTIONS AND DETAILS SF-3 CHEMICAL FACILTY STRUCTURAL SECTIONS CY-10 WATER TREATMENT PLANT 12" RECYCLE WATER PROFILE 10 ADMINISTRATION BUILDING PARTITION TYPES AND PLAN DETAILS Al-19 SG-1 GRAVITY THICKENER STRUCTURAL FOUNDATION PLAN CY-11 WATER TREATMENT PLANT 12" SLUDGE PROFILE 12 AND 18" DRAIN PROFILE 13 ADMINISTRATION BUILDING FINISH FLOOR PLAN SG-2 GRAVITY THICKENER STRUCTURAL TOP PLAN WATER TREATMENT PLANT 12" POTABLE WATER LINE PROFILE 14 STATION -60+00 TO STA 10+00 AJ-1 STORAGE BUILDING LIFE SAFTEY PLAN AND CODE KEY DETERMINATIONS SG-3 **GRAVITY THICKENER STRUCTURAL SECTIONS** WATER TREATMENT PLANT 12" POTABLE WATER LINE PROFILE 14 STATION 10+00 TO STA 20+00 CY-13 AJ-2 STORAGE BUILDING FLOOR PLAN & ROOF PLAN SG-4 GRAVITY THICKENER & WASHWATER RECOVERY BASIN STRUCTURAL STAIR PLANS & SECTIONS CY-14 WATER TREATMENT PLANT 12" SUPERNATANT PROFILE 15 AND 8" SL PROFILE 16 AJ-3 STORAGE BUILDING ELEVATIONS SG-5 WASHWATER RECOVERY BASIN STRUCTURAL FOUNDATION PLAN CY-15 WATER TREATMENT PLANT 42" / 30" PLANT RAW WATER LINE PROFILE 17 AND 30" RAW WATER LINE PROFILE 17A AJ-4 STORAGE BUILDING BUILDING SECTIONS SG-6 WASHWATER RECOVERY BASIN STRUCTURAL TOP PLAN CY-16 WATER TREATMENT PLANT 36" RCW PROFILE 18 AND 12" SLUDGE PROFILE 19 AJ-5 STORAGE BUILDING WALL SECTIONS I SG-7 WASHWATER RECOVERY BASIN STRUCTURAL SECTIONS WATER TREATMENT PLANT 12" DRAIN LINE TO FILTRATE PUMP STATION PROFILE 20 AJ-6 STORAGE BUILDING WALL SECTIONS II SG-8 DECANT BASIN STRUCTURAL FOUNDATION PLAN WATER TREATMENT PLANT 60" FINISHED WATER PROFILE 21 CY-18 AK-1 ELECTRICAL BUILDING LIFE SAFTEY PLAN AND CODE KEY DETERMINATIONS \* SG-9 DECANT BASIN STRUCTURAL TOP PLAN CHEMICAL INJECTION VAULT DETAIL AND SECTION AK-2 ELECTRICAL BUILDING FLOOR PLAN AND ROOF PLAN SG-10 DECANT BASIN STRUCTURAL SECTIONS AND DETAILS CP-1 RAW WATERLINE KEY PLAN AK-3 **ELECTRICAL BUILDING ELEVATIONS** ANDREW BROWER SG-11 WASHWATER COLLECTION BOX STRUCTURAL PLANS AND SECTION CP-2 PLAN AND PROFILE STA 0+00 TO STA 5+00 RAW WATER LINE **ELECTRICAL BUILDING BUILDING SECTIONS** 118931 SG-12 SLUDGE PUMP STATION STRUCTURAL PLANS PLAN AND PROFILE STA 5+00 TO STA 10+00 RAW WATER LINE AK-5 ELECTRICAL BUILDING WALL SECTIONS SG-13 SLUDGE PUMP STATION STRUCTURAL SECTION CP-4 PLAN AND PROFILE STA 10+00 TO STA 15+00 RAW WATER LINE AM-1 RAW WATER ELECTRICAL BUILDING LIFE SAFETY PLAN AND CODE KEY DETERMINATIONS SG-14 WASHWATER RECYCLE PUMP STATION STRUCTURAL PLANS CP-5 PLAN AND PROFILE STA 15+00 TO STA 20+00 RAW WATER LINE AM-2 RAW WATER ELECTRICAL BUILDING FLOOR PLAN AND ROOF PLAN PROJECT NO. 2048—24892 ESIGNED BY: CITY OF GEORGETOWN, TEXAS FILE NAME: GOO1NFIN.DW K. REESE S. STEWART SHEET NO. SOUTH LAKE SHEET INDEX I ROSS CHK'D BY: A. KARAMALEGOS G-1 WATER TREATMENT PLANT 1/19/22 JBF AKM CONFORMED DRAWINGS 9430 RESEARCH BLVD., SUITE 1-200 S. STEWART Austin, TX 78759 DATE DRWN CHKD REMARKS DECEMBER 202 Tel: (512) 346-1100

TBPE Firm Registration No. F-3043


\H\

B

 $\overline{A}$ 


					I E	7	F/ J	7
SG-15	WASHWATER RECYCLE PUMP STATION STRUCTURAL SECTIONS AND DETAILS		MD-3	BACKWASH PUMP STATION SECTIONS		HZ-1	HVAC DETAILS I	
SH-1	DEWATERING BUILDING STRUCTURAL FOUNDATION PLAN		MD-4	HIGH SERVICE PUMP STATION SECTIONS		HZ-2	HVAC DETAILS II	
SH-2	DEWATERING BUILDING STRUCTURAL DETAIL PLANS		ME-1	FILTRATE LIFT STATION UPPER AND LOWER MECHANICAL PLANS		HZ-3	HVAC DETAILS III	
SH-3	DEWATERING BUILDING STRUCTURAL ROOF PLANS		ME-2	FILTRATE LIFT STATION MECHANICAL SECTION				
SH-4	DEWATERING BUILDING STRUCTURAL SECTIONS AND DETAILS I		MF-1	CHEMICAL FACILITY OVERALL PLAN		PLUMBING		
SH-5	DEWATERING BUILDING STRUCTURAL SECTIONS AND DETAILS II		MF-2	CHEMICAL FACILITY ENLARGED PLAN I		PL-1	PLUMBING LEGENDS, ABBREVIATIONS, SYMBOLS AND NOTES	
SI-1	ADMINISRATION BUILDING STRUCTURAL FOUNDATION AND FLOOR PLAN		MF-3A	CHEMICAL FACILTY SECTIONS I		PL-2	PLUMBING SCHEDULES	
SI-2	ADMINISTRATION BUILDING STRUCTURAL FOUNDATION SECTIONS AND DETAILS		MF-3B	CHEMICAL FACILTY SECTIONS II		PLF-1	CHEMICAL FACILITY PLUMBING PLAN	
SJ-1	STORAGE BUILDING STRUCTURAL FOUNDATION PLAN		MF-4	CHEMICAL FACILTY SECTIONS III		PLF-2	CHEMICAL FACILITY PLUMBING ISOMETRIC	
SJ-2	STORAGE BUILDING STRUCTURAL FOUNDATION SECTIONS AND DETAILS		MF-5A	CHEMICAL FACILITY ENLARGED PLAN II		PLH-1	DEWATERING BUILDING PLUMBING PLAN AND ISOMETRIC	
SK-1	ELECTRICAL BUILDING STRUCTURAL FOUNDATION PLAN		MF-5B	CHEMICAL FACILITY MISCELLANEOUS SECTIONS		PLI-1	ADMINISTRATION BULDING PLUMBING BELOW SLAB FLOOR PLAN	
SK-2	ELECTRICAL BUILDING STRUCTURAL FOUNDATION SECTIONS AND DETAILS		MF-6	CHEMICAL FACILTY SECTIONS III		PLI-2	ADMINISTRATION BULDING PLUMBING FLOOR PLAN	
SK-3	DIESEL ENGINE-DRIVEN GENERATOR G-1 FOUNDATION PLAN AND SECTION		MF-7	CHEMICAL FACILTY SECTIONS IV		PLI-3	ADMINISTRATION BUILDING PLUMBING ENLARGED PLAN	
SK-4	DIESEL ENGINE-DRIVEN GENERATOR G-2 FOUNDATION PLAN AND SECTION		MF-8	CHEMICAL FACILITY BASE AREA TANK NOZZLE SCHEDULES		PLI-4	ADMINISTRATION BUILDING PLUMBING ISOMETRICS	
SK-5	DIESEL ENGINE-DRIVEN GENERATOR G-3 FOUNDATION PLAN AND SECTION		MF-9	CHEMICAL FACILITY ACID AREA TANK NOZZLE SCHEDULES I		PLN-1	RAW WATER CHEMICAL BUILDING PLUMBING PLAN AND ISOMETRIC	
SK-6	TRANSFORMER FOUNDATION PLAN, SECTION, AND DETAILS		MF-10	CHEMICAL FACILITY ACID AREA TANK NOZZLE SCHEDULES II		PLZ-1	PLUMBING DETAILS I	
SI <sub>-</sub> 1	RAW WATER PUMP STATION STRUCTURAL PLAN		MF-11	CHEMICAL FACILITY SODIUM HYPOCHLORITE FILL STATION DETAILS		PLZ-2	PLUMBING DETAILS II	
SL-1	RAW WATER PUMP STATION TOP DECK STRUCTURAL PLAN		MF-12	CHEMICAL FACILITY POLYMER AND LAS FILL STATION DETAILS				
	RAW WATER PUMP STATION SECTIONS		MF-13	CHEMICAL FACILTY ALUM FILL STATION DETAILS		FIRE PROTE		
SL-3				GRAVITY THICKENER MECHANICAL PLAN		FIRE PROTE		
SM-1	RAW WATER ELECTRICAL BUILDING STRUCTURAL FOUNDATION PLAN		MG-1			F-1	FIRE PROTECTION LEGEND AND DETAILS	
SM-2	RAW WATER ELECTRICAL BUILDING STRUCTURAL FOUNDATION SECTIONS AND DETAILS		MG-2	GRAVITY THICKENER MECHANICAL SECTION		FF-1	CHEMICAL FACILITY FIRE PROTECTION ZONE DIAGRAM	
SM-3	DIESEL ENGINE-DRIVEN GENERATOR FOUNDATION PLAN AND SECTION		MG-3	WASHWATER RECOVERY BASIN MECHANICAL PLAN		FI-1	ADMINISTRATION BUILDING FIRE PROTECTION ZONE DIAGRAM	
SM-4	TRANSFORMER FOUNDATION PLAN, SECTION, AND DETAILS		MG-4	WASHWATER RECOVERY BASIN MECHANICAL SECTION				
SN-1	STRUCTURAL RAW WATER CHEMICAL BUILDING FOUNDATION PLANS		MG-5	WASHWATER COLLECTION BOX UPPER AND LOWER MECHANICAL PLA	NS AND SECTIONS	VOLUME III	of III	
SN-2	STRUCTURAL RAW WATER CHEMICAL BUILDING SECTIONS AND DETAILS		MG-6	DECANT BASIN MECHANICAL PLAN			<del></del>	
SR-1	WATER QUALITY POND RETAINING WALL STRUCTURAL PLAN		MG-7	DECANT BASIN MECHANICAL SECTION		ELECTRICAI	ELECTRICAL LECENTS:	
SR-2	WATER QUALITY POND RETAINING WALL STRUCTURAL SECTIONS AND DETAILS		MG-8	SLUDGE PUMP STATION UPPER AND LOWER MECHANICAL PLANS		E-1	ELECTRICAL LEGEND I	
SY-1	RAW WATER FLOW METER VAULT STRUCTURAL PLAN AND SECTION		MG-9	SLUDGE PUMP STATION MECHANICAL SECTION		E-2	ELECTRICAL LEGEND II	
SY-2	WASH WATER RECYCLE FLOW METER VAULT STRUCTURAL PLAN AND SECTION		MG-10	WASHWATER RECYCLE PUMP STATION UPPER AND LOWER MECHANI	CAL PLANS	E-3	ELECTRICAL GENERAL NOTES	
SY-3	FINISHED WATER FLOW METER VAULT STRUCTURAL PLANS		MG-11	WASHWATER RECYCLE PUMP STATION MECHANICAL SECTION		E-4	SOUTH LAKE WATER TREATMENT PLANT ELECTRICAL SITE PLAN	
SY-4	FINISHED WATER FLOW METER VAULT STRUCTURAL SECTION		MH-1	BFP FEED PUMP STATION MECHANICAL PLAN		E-5	SOUTH LAKE WATER TREATMENT PLANT ELECTRICAL LIGHTING SITE PLAN	
SY-4 SZ-1	STRUCTURAL STANDARD DETAILS I		MH-2	BFP FEED PUMP STATION MECHANICAL SECTION		E-6	OVERALL PROJECT ELECTRICAL SITE PLAN	
			MH-3	DEWATERING BUILDING MECHANICAL PLAN		E-7	OVERALL SOUTH LAKE RWPS ELECTRICAL DISTRIBUTION ONE-LINE DIAGRAM	
SZ-2	STRUCTURAL STANDARD DETAILS II		MH-3 MH-4	DEWATERING BUILDING MECHANICAL PLAN  DEWATERING BUILDING ENLARGED BFP AREA MECHANICAL PLAN AN	SECTIONS	E-8	OVERALL SOUTH LAKE WTP ELECTRICAL DISTRIBUTION ONE-LINE DIAGRAM	
SZ-3	STRUCTURAL STANDARD DETAILS III					F-9	LIGHTING FIXTURE SCHEDULE	
SZ-4	STRUCTURAL STANDARD DETAILS IV		MH-5	DEWATERING BUILDING ENLARGED POLYMER AREA MECHANICAL PLA	N AND SECTIONS	F-10	MEDIUM VOLTAGE ELECTRICAL DUCTBANK SCHEDULE I	
SZ-5	STRUCTURAL STANDARD DETAILS V		MH-6	DEWATERING BUILDING MECHANICAL SECTIONS AND DETAILS		E-11	MEDIUM VOLTAGE ELECTRICAL DUCTBANK SCHEDULE II	
SZ-6	STRUCTURAL STANDARD DETAILS VI		ML-1	RAW WATER PUMP STATION INTAKE PLAN AND PROFILE		E 12	MEDIUM VOLTAGE ELECTRICAL DUCTBANK SCHEDULE III	
SZ-7	STRUCTURAL STANDARD DETAILS VII		ML-2	RAW WATER PUMP STATION INTAKE MECHANICAL PLAN		E-12		
SZ-8	STRUCTURAL STANDARD DETAILS VIII		ML-3	RAW WATER PUMP STATION INTAKE MECHANICAL SECTIONS I		E-13	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE I	
SZ-9	STRUCTURAL STANDARD DETAILS IX		ML-4	RAW WATER PUMP STATION INTAKE MECHANICAL SECTIONS II		E-14	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE II	
SZ-10	STRUCTURAL STANDARD DETAILS X		ML-5	RAW WATER PUMP STATION INTAKE MECHANICAL DETAILS		E-15	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE III	
			MN-1	RAW WATER CHEMICAL BUILDING PLAN		E-16	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE IV	
PROCESS N	MECHANICAL		MN-2	RAW WATER CHEMICAL BUILDING SECTIONS I		E-17	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE V	
			MN-3	RAW WATER CHEMICAL BUILDING SECTIONS II		E-18	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE VI	
M-1	MECHANICAL LEGEND		MN-4	RAW WATER CHEMICAL BUILDING PERMANGANATE AREA TANK NOZZ	E SCHEDULE	E-19	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE VII	
MA-1	OVERALL TREATMENT STRUCTURE PLAN		MN-5	RAW WATER CHEMCIAL BUILDING FILL STATION DETAILS		E-20	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE VIII	
MA-2	TREATMENT STRUCTURE UPPER PLAN TRAINS 1 AND 2, FILTERS 1 THROUGH 7		MY-1	RAW WATER FLOW METER VAULT MECHANICAL PLAN AND SECTION		E-21	LOW VOLTAGE ELECTRICAL DUCTBANK SCHEDULE IX	
MA-3	TREATMENT STRUCTURE LOWER PLAN TRAINS 1 AND 2, FILTERS 1 THROUGH 7		MY-2	WASHWATER RECYCLE FLOW METER VAULT MECHANICAL PLAN AND	SECTION	EA-1	SWITCHGEAR SWGR-A-1 ONE-LINE DIAGRAM	
MA-4	TREATMENT STRUCTURE UPPER PLAN TRAINS 3 AND 4, FILTERS 8 THROUGH 13		MY-3	FINISHED WATER FLOW METER VAULT MECHANICAL PLAN	SECTION	EA-2	MOTOR CONTROL CENTER MCC-A1 ONE-LINE DIAGRAM	
MA-5	TREATMENT STRUCTURE LOWER PLAN TRAINS 3 AND 4, FILTERS 8 THROUGH 13					EA-3	MOTOR CONTROL CENTER MCC-A2 ONE-LINE DIAGRAM	
MA-6	OVERALL TREATMENT STRUCTURE SECTIONS		MY-4	FINISHED WATER FLOW METER VAULT MECHANICAL SECTION	FOLIANION PLAN AND OF STICK	FA-4	MOTOR CONTROL CENTER MCC-A3 ONE-LINE DIAGRAM	
MA-7	INFLUENT BOX - FLOCCULATORS, TRAINS 1 AND 2, PLAN SECTION AND DETAILS		MY-5	POTABLE WATER FLOW METER AND PRESSURE REDUCING VALVES N	ECHANICAL PLAN AND SECTION	EA-5	TREATMENT STRUCTURE TRAIN 1 AND 2 ELECTRICAL BLOWER ROOM POWER AND CONTROL PLAN	
MA-8	INFLUENT BOX - FLOCCULATORS, TRAINS 3 AND 4, PLAN SECTION AND DETAILS		MZ-1	STANDARD MECHANICAL DETAILS I		EA-6	TREATMENT STRUCTURE TRAIN 1 AND 2 ELECTRICAL ROOM GROUNDING AND CONTROL PLAN	
MA-9	INFLUENT BOX AND SEDIMENTATION BASIN TRAINS 1 AND 2 SECTIONS		MZ-2	STANDARD MECHANICAL DETAILS II		LA-0	TREATMENT STRUCTURE TRAIN 1 AND 2 FLOCCULATION AND SEDIMENTATION POWER PLAN	
MA-10	INFLUENT BOX AND SEDIMENTATION BASIN TRAINS 3 AND 4 SECTIONS		MZ-3	STANDARD MECHANICAL DETAILS III		EA-7		
MA-11	SEDIMENTATION BASIN AND FILTER INFLUENT CHANNEL TRAINS 1 AND 2 SECTIONS		MZ-4	STANDARD MECHANICAL DETAILS IV		EA-8	TREATMENT STRUCTURE TRAIN 3 AND 4 FLOCCULATION AND SEDIMENTATION POWER PLAN	
MA-12	SEDIMENTATION BASIN AND FILTER INFLUENT CHANNEL TRAINS 3 AND 4 SECTIONS		MZ-5	STANDARD MECHANICAL DETAILS V		EA-9	TREATMENT STRUCTURE TRAIN 1 AND 2 LOWER FILTER AREA POWER PLAN	
MA-13	FILTERS 1 THROUGH 7 UPPER PLAN AND DETAILS		MZ-6	STANDARD MECHANICAL DETAILS VI		EA-10	TREATMENT STRUCTURE TRAIN 3 AND 4 LOWER FILTER AREA POWER PLAN	
			MZ-7	STANDARD MECHANICAL DETAILS VII		EA-11	TREATMENT STRUCTURE TRAIN 1 AND 2 UPPER FILTER AREA POWER PLAN	
MA-14	FILTERS 1 THROUGH 7 LOWER PLAN		MZ-8	STANDARD MECHANICAL DETAILS VIII		EA-12	TREATMENT STRUCTURE TRAIN 3 AND 4 UPPER FILTER AREA POWER PLAN	
MA-15	FILTERS 8 THROUGH 13 UPPER PLAN		MZ-9	STANDARD MECHANICAL DETAILS IX		EA-13	TREATMENT STRUCTURE TRAIN 1 AND 2 OVERALL LIGHTING AND RECEPTACLE PLAN	
MA-16	FILTERS 8 THROUGH 13 LOWER PLAN		MZ-10	STANDARD MECHANICAL DETAILS X		EA-14	TREATMENT STRUCTURE TRAIN 3 AND 4 OVERALL LIGHTING AND RECEPTACLE PLAN	
MA-17	FILTER SECTIONS		MZ-11	STANDARD MECHANICAL DETAILS XI		EA-15	TREATMENT STRUCTURE TRAIN 1 AND 2 ELECTRICAL AND BLOWER ROOM LIGHTING, HVAC AND RECEPTACLE PLAN	
MA-18	FILTERS 1 THROUGH 7, SECTIONS AND DETAILS		.v.⊆=1.1			EA-16	TREATMENT STRUCTURE TRAIN 1 AND 2 FLOCCULATION AND SEDIMENTATION CONTROL PLAN	
MA-19	FILTERS 1 THROUGH 7, SECTIONS AND DETAILS II		DV/AC			EA-17	TREATMENT STRUCTURE TRAIN 3 AND 4 FLOCCULATION AND SEDIMENTATION CONTROL PLAN	
MA-20	FILTERS 8 THROUGH 13, SECTIONS AND DETAIL		HVAC	LIVAC LEGENDO ADDREVATIONO OVARROLO VIZZARIO		EA-18	TREATMENT STRUCTURE TRAIN 1 AND 2 LOWER FILTER AREA AND BLOWER ROOM CONTROL PLAN	
MB-1	DISINFECTION BASIN NO. 1 AND 2, TRANSFER PUMP STATION OVERALL PLAN		H-1	HVAC LEGENDS, ABBREVIATIONS, SYMBOLS AND NOTES			TREATMENT STRUCTURE TRAIN 1 AND 2 LOWER FILTER AREA AND BLOWER ROOM CONTROL PLAN  TREATMENT STRUCTURE TRAIN 3 AND 4 LOWER FILTER AREA CONTROL PLAN	
MB-2	DISINFECTION BASIN NO. 1 AND TRANSFER PUMP STATION UPPER PLAN		H-2	HVAC SCHEDULES I		EA-19		
MB-3	DISINFECTION BASIN NO 1. AND TRANSFER PUMP STATION LOWER PLAN		H-3	HVAC SCHEDULES II		EA-20	TREATMENT STRUCTURE TRAIN 1 AND 2 UPPER FILTER AREA CONTROL PLAN	
MB-4	DISINFECTION BASIN NO. 2 AND TRANSFER PUMP STATION UPPER PLAN		H-4	HVAC SCHEDULES III		EA-21	TREATMENT STRUCTURE TRAIN 3 AND 4 UPPER FILTER AREA CONTROL PLAN	
MB-5	DISINFECTION BASIN NO. 2 AND TRANSFER PUMP STATION LOWER PLAN		H-5	HVAC CONTROL DIAGRAMS I		EA-22	TREATMENT STRUCTURE TRAIN 1 AND 2 CABLE TRAY PLAN	
	DISINFECTION BASIN AND TRANSFER FUMP STATION SECTIONS I		H-6	HVAC CONTROL DIAGRAMS II		EA-23	TREATMENT STRUCTURE TRAIN 3 AND 4 CABLE TRAY PLAN	
DAID-T			HA-1	TREATMENT STRUCTURE HVAC FLOOR AND ROOF PLANS		EA-24	TREATMENT STRUCTURE TRAIN 1 AND 2 CABLE TRAY ISOMETRIC VIEW	
MB-6	DISINFECTION BASIN AND TRANSFER PUMP STATION SECTIONS II		HA-2	TREATMENT STRUCTURE PHASE II HVAC FLOOR AND ROOF PLANS		EA-25	TREATMENT STRUCTURE TRAIN 3 AND 4 CABLE TRAY ISOMETRIC VIEW	
MB-7	DIGINIFICATION DAGIN AND TRANSFER BUILD STATION BETALLS		HA-3	TREATMENT STRUCTURE HVAC ENLARGED PLANS I		EA-26	TREATMENT STRUCTURE PANELBOARD SCEHDULES I	
MB-7 MB-8	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS I			TREATMENT STRUCTURE PHASE II HVAC ENLARGED PLANS II		EA-27	TREATMENT STRUCTURE PANELBOARD SCHEDULES II	
MB-7 MB-8 MB-9	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II		HA-4			EA-28	TREATMENT STRUCTURE PANELBOARD SCHEUDLES III	1 1
MB-7 MB-8 MB-9 MC-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN			DEWATERING BUILDING HVAC PLAN		LA-20		// . //
MB-7 MB-8 MB-9 MC-1 MC-2	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN		HH-1	DEWATERING BUILDING HVAC PLAN ADMINISTRATION BUILDING HVAC FLOOR PLAN		EB-1	DISINFECTION BASIN 1 POWER AND CONTROL PLAN	
MB-7 MB-8 MB-9 MC-1 MC-2	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN		HH-1 HI-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN		EB-1 EB-2	DISINFECTION BASIN 1 POWER AND CONTROL PLAN DISINFECTION BASIN 2 POWER AND CONTROL PLAN	
MB-7 MB-8 MB-9 MC-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN		HH-1 HI-1 HI-2	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN		EB-1 EB-2 FR-3	DISINFECTION BASIN 2 POWER AND CONTROL PLAN	
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS		HH-1 HI-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS		EB-1 EB-2 EB-3	DISINFECTION BASIN 2 POWER AND CONTROL PLAN DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN	STE OF TEXT
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN		HH-1 HI-1 HI-2	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS		EB-1 EB-2 EB-3 EB-4	DISINFECTION BASIN 2 POWER AND CONTROL PLAN DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN	ANDREW BROWER
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN		HH-1 HI-1 HI-2	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS		EB-1 EB-2 EB-3	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN	ANDREW BROWER
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS		HH-1 HI-1 HI-2 HI-3 HI-4	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS		EB-1 EB-2 EB-3 EB-4	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN	ANDREW BROWER
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS		HH-1 HI-1 HI-2 HI-3 HI-4 HJ-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN		EB-1 EB-2 EB-3 EB-4	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN	ANDREW BROWEI
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS BACKWASH PUMP STATION PLAN		HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC ROOF PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN		EB-1 EB-2 EB-3 EB-4	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN	ANDREW BROWER
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS		HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN		EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN DISINFECTION BASIN 1 AND 2 GROUNDING PLAN CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN HIGH SERVICE PUMP STATION ELECTRICAL PLAN BACKWASH PUMP STATION ELECTRICAL PLAN	ANDREW BROWER  118931  October 10 10 10 10 10 10 10 10 10 10 10 10 10
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS BACKWASH PUMP STATION PLAN	ED BY: J. MAYER	HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN	CITY OF GEORGETOWN TEXAS	EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN  BACKWASH PUMP STATION ELECTRICAL PLAN	ANDREW BROWER  118931  CENSE  IO 16 1021  DJECT NO. 2048-
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS BACKWASH PUMP STATION PLAN HIGH SERVICE PUMP STATION PLAN  DESIGNE DRAWN		HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN	CITY OF GEORGETOWN, TEXAS	EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN  BACKWASH PUMP STATION ELECTRICAL PLAN	ANDREW BROWER  118931  CENSE  IO 16 1021  DJECT NO. 2048-
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II CLEARWELLS LOCATION PLAN CLEARWELL NO.1 FOUNDATION PLAN CLEARWELL NO.1 TOP PLAN AND DETAILS CLEARWELL NO.2 FOUNDATION PLAN CLEARWELL NO.2 TOP PLAN CLEARWELL MECHANICAL SECTIONS CLEARWELL MECHANICAL SECTIONS AND DETAILS CLEARWELL MECHANICAL MISCELLANEOUS DETAILS BACKWASH PUMP STATION PLAN HIGH SERVICE PUMP STATION PLAN  DESIGNE DRAWN		HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN		EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN  BACKWASH PUMP STATION ELECTRICAL PLAN  PROFILE	ANDREW BROWER  118931  CENSE  IO USIONAL EN  DJECT NO. 2048-
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1 MD-2	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II  CLEARWELLS LOCATION PLAN  CLEARWELL NO.1 FOUNDATION PLAN  CLEARWELL NO.2 FOUNDATION PLAN  CLEARWELL NO.2 TOP PLAN  CLEARWELL NO.2 TOP PLAN  CLEARWELL MECHANICAL SECTIONS  CLEARWELL MECHANICAL SECTIONS AND DETAILS  CLEARWELL MECHANICAL MISCELLANEOUS DETAILS  BACKWASH PUMP STATION PLAN  HIGH SERVICE PUMP STATION PLAN  DESIGNE  DRAWN IS  SHEET C	CHK'D BY: S. STEWART CHK'D BY: A. KARAMALEGOS	HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN	SOUTH LAKE	EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN  BACKWASH PUMP STATION ELECTRICAL PLAN	ANDREW BROWER  118931  CENSE  IOUIOUI  DJECT NO. 2048— E NAME: G001NF  SHEET NO.
MB-7 MB-8 MB-9 MC-1 MC-2 MC-3 MC-4 MC-5 MC-6 MC-7 MC-8 MD-1 MD-2  A 1/19/	DISINFECTION BASIN AND TRANSFER PUMP STATION DETAILS II  CLEARWELLS LOCATION PLAN  CLEARWELL NO.1 FOUNDATION PLAN  CLEARWELL NO.2 TOP PLAN AND DETAILS  CLEARWELL NO.2 TOP PLAN  CLEARWELL MECHANICAL SECTIONS  CLEARWELL MECHANICAL SECTIONS AND DETAILS  CLEARWELL MECHANICAL MISCELLANEOUS DETAILS  BACKWASH PUMP STATION PLAN  HIGH SERVICE PUMP STATION PLAN  DESIGNE  DRAWN II  SHEET C  CROSS (1222) JIBE AKM CONFORMED DRAWINGS	CHK'D BY: S. STEWART  CHK'D BY: A. KARAMALEGOS  VED BY: S. STEWART	HH-1 HI-2 HI-3 HI-4 HJ-1 HK-1 HM-1	ADMINISTRATION BUILDING HVAC FLOOR PLAN ADMINISTRATION BUILDING HVAC SECTIONS ADMINISTRATION BUILDING HVAC CONTROL DIAGRAMS STORAGE BUILDING HVAC PLAN ELECTRICAL BUILDING HVAC PLAN RAW WATER ELECTRICAL BUILDING HVAC PLAN RAW WATER CHEMICAL BUILDING HVAC PLAN  RAW WATER CHEMICAL BUILDING HVAC PLAN  RAW WATER CHEMICAL BUILDING HVAC PLAN		EB-1 EB-2 EB-3 EB-4 EB-5 EC-1 ED-1	DISINFECTION BASIN 2 POWER AND CONTROL PLAN  DISINFECTION BASIN 1 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 2 LIGHTING AND RECEPTACLE PLAN  DISINFECTION BASIN 1 AND 2 GROUNDING PLAN  CLEARWELLS NO.1 AND NO.2 POWER AND CONTROL ELECTRICAL PLAN  HIGH SERVICE PUMP STATION ELECTRICAL PLAN  BACKWASH PUMP STATION ELECTRICAL PLAN  PROFILE	JECT NO. 2048-


			<u>E</u>		F/ I	H
E-1 FILTRATE LIFT STATION UPPER AND LOWER ELECTRICAL PLANS	EK-20			EZ-2	ELECTRICAL STANDARD DETAILS II	
F-1 CHEMICAL FACILITY POWER PLAN I	EK-21			EZ-3	ELECTRICAL STANDARD DETAILS III	
2 CHEMICAL FACILITY POWER PLAN II	EL-1			EZ-4	ELECTRICAL STANDARD DETAILS IV	
3 CHEMICAL FACILITY LIGHTING AND RECEPTACLE PLAN	EL-2	RAW WATER PUMP STATION CARLE TRAY COULD U.S.		EZ-5	ELECTRICAL STANDARD DETAILS V	
4 CHEMICAL FACILITY CONTROL PLANT	EL-3	RAW WATER PUMP STATION CABLE TRAY SCHEDULE	DING CITE DI ANI	EZ-6	ELECTRICAL STANDARD DETAILS VI	
-5 CHEMICAL FACILITY CONTROL PLAN II	EM-1		DING SITE PLAN	EZ-/	ELECTRICAL STANDARD DETAILS VII	
CHEMICAL FACILITY PANELBOARD SCHEDULE	EM-1.			EZ-8	ELECTRICAL STANDARD DETAILS VIII	
G-1 GRAVITY THICKENER ELECTRICAL PLAN G-2 WASHWATER RECOVERY BASIN AND COLLECTION BOX ELECTRICAL PLAN	EM-1.		DAM			
	EM-2			INSTRUME	NTATION	
G-3 SLUDGE PUMP STATION POWER AND CONTROL PLAN G-4 WASHWATER RECYCLE PUMP STATION POWER AND CONTROL PLANS	EM-3			I-1	INSTRUMENTATION LEGEND I	
	EM-3.		ANSI FUNCTION DIAGRAM	I-2	INSTRUMENTATION LEGEND II	
	EM-3.			I-3	SYSTEM ARCHITECTURE OVERVIEW	
H-1 MOTOR CONTROL CENTER 'MCC-H-1' ONE-LINE DIAGRAM  H-2 MOTOR CONTROL CENTER 'MCC-H-2' ONE-LINE DIAGRAM	EM-3.			I-4	ADMINISTRATION BUILDING ELECTRICAL ROOM AND CHEMICAL FACILITY NETWORK ARCHITECTURE	
H-3 BFP FEED PUMP STATION POWER AND CONTROL ELECTRICAL PLAN	EM-3.			I-5	ELECTRICAL BUILDING NETWORK ARCHITECTURE	
H-4 DEWATERING BUILDING ELECTRICAL ROOM PLAN	EM-3.			I-6	TREATMENT STRUCTURE NETWORK ARCHITECTURE	
EH-5 DEWATERING BUILDING ELECTRICAL POWER PLAN	EM-3.			I-7	DEWATERING BUILDING NETWORK ARCHITECTURE	
H-6 DEWATERING BUILDING ELECTRICAL LIGHTING AND RECEPTACLE PLAN	EM-3.			I-8	STORAGE BUILDING NETWORK ARCHITECTURE	
1-7 DEWATERING BUILDING ELECTRICAL CONTROL PLAN	EM-3.			I-9	RAW WATER ELECTRICAL BUILDING AND PUMP STATION NETWORK ARCHITECTURE	
1-7 DEWATERING BUILDING ELECTRICAL CONTROL PLAN  1-8 DEWATERING BUILDING ELECTRICAL GROUNDING PLAN	EM-3.			I-10	SECURITY SYSTEM SITE PLAN	
H-9 DEWATERING BUILDING ELECTRICAL GROUNDING PLAN H-9 DEWATERING BUILDING ELECTRICAL SECURITY PLAN	EM-3.			I-11	RAW WATER BUILDING SECURITY SYSTEM SITE PLAN	
H-10 DEWATERING BUILDING ELECTRICAL SECURITY PLAN H-10 DEWATERING BUILDING PANELBOARD SCHEDULE	EM-3.			I-12	RAW WATER PUMP STATION SECURITY SYSTEM SITE PLAN	
1-10 DEWATERING BUILDING PANELBOARD SCHEDULE -1 ADMINISTRATION BUILDING ELECTRICAL ROOM PLAN	EM-3.			IA-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM RAPID MIXING AND FLOCCULATION BASINS 1 & 2	
2 ADMINISTRATION BUILDING ELECTRICAL ROOM PLAN 2 ADMINISTRATION BUILDING ELECTRICAL POWER AND RECEPTACLE PLAN		.13 TIE CIRCUIT BREAKER 52-11 CONTROL SCHEMATIC .14 TIE CIRCUIT BREAKER 52-T2 CONTROL SCHEMATIC		IA-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM RAPID MIXING AND FLOCCULATION BASINS 3 & 4	
			NTIAL CONTROL SCHEMATIC	IA-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SEDIMENTATION BASINS 1 & 2 AND SLUDGE VAULT	
	EM-3.			IA-4	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SEDIMENTATION BASINS 3 & 4 AND SLUDGE VAULT	
4 ADMINISTRATION BUILDING HVAC AND PLUMBING PLAN 5 ADMINISTRATION BUILDING ELECTRICAL GROUNDING PLAN	EM-3.			IA-5	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 1 THROUGH 3	
	EM-3.		5_1.5_1.01V.W	IA-6	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 4 AND 5	
-6 ADMINISTRATION BUILDING ELECTRICAL SECURITY AND COMMUNICATION PLAN -7 ADMINISTRATION BUILDING ROOF ELECTRICAL POWER PLAN	EM-3.			IA-7	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 6 AND 7	
-7 ADMINISTRATION BUILDING ROOF ELECTRICAL POWER PLAN -8 ADMINISTRATION BUILDING PANELBOARD SCHEDULES I	EM-3.		NE-LINE DIAGRAM	IA-8	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 8 AND 9	
9 AMMINISTRATION BUILDING PANELBOARD SCHEDULES II	EM-4 EM-5			IA-9	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 10 AND 11	
9 AMMINISTRATION BUILDING PANELBOARD SCHEDULES II -1 STORAGE BUILDING ELECTRICAL PLANS	EM-5			IA-10	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTERS 12 AND 13	
	EM-6		PTACLE PLAN	IA-11	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM BACKWASH AIR BLOWERS	
J-2 STORAGE BUILDING PANELBOARD SCHEDULES  K-1 PAD-MOUNTED SWITCHGEAR SWGR-1 ONE-LINE DIAGRAM	EM-7			IB-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM DISINFECTION BASIN 1	
4-1 PAD-MOUNTED SWITCHGEAR SWGR-T ONE-LINE DIAGRAM 4-2 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K1 ONE-LINE DIAGRAM	EM-9			IB-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM DISINFECTION BASIN 2	
K-2.1 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K1 ANSI FUNCTION DIAGRAM	EM-10		E CONDON NOOTING LEAN	IB-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM TRANSFER PUMP STATION NO. 1	
G-2.2 FEEDER CIRCUIT BREAKER 521-1 CONTROL SCHEMATIC	EM-11		V GRADE CONDUIT ROLITING AND GROLINDING PLAN	IB-4	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM TRANSFER PUMP STATION NO. 2	
(-2.3 FEEDER CIRCUIT BREAKER 521-2 CONTROL SCHEMATIC	EM-12			IC-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM CLEARWELLS	
(-2.4 FEEDER CIRCUIT BREAKER 521-3 CONTROL SCHEMATIC	EM-13			ID-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM BACKWASH PUMP STATION	
7-2.5 TIE CIRCUIT BREAKER 521-4 CONTROL SCHEMATIC	EM-14			ID-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM HIGH SERVICE PUMP STATION PUMPS 1 THROUGH 5	
-2.6 MAIN CIRCUIT BREAKER 52-M1 CONTROL SCHEMATIC	EM-15			ID-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM HIGH SERVICE PUMP STATION PUMPS 6 THROUGH 9	
K-2.7 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K1 DIFFERENTIAL CONTROL SCHEM	EM-16			ID-4	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM HIGH SERVICE PUMP STATION METER VAULT	
K-3 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K2 ONE-LINE DIAGRAM	EM-17			IE-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM FILTRATE LIFT STATION	
K-3.1 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K2 ONE-LINE DIAGRAM	EN-1		PLAN	IF-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SODIUM HYPOCHLORITE FEED SYSTEM 1	
K-3.2 FEEDER CIRCUIT BREAKER 522-1 CONTROL SCHEMATIC	EN-2			IF-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SODIUM HYPOCHLORITE FEED SYSTEM 2	
K-3.3 FEEDER CIRCUIT BREAKER 522-2 CONTROL SCHEMATIC	EX-1	FLOCCULATOR CONTROL SCHEMATICS I		IF-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM LAS FEED SYSTEM	
K-3.4 TIE CIRCUIT BREAKER 522-3 CONTROL SCHEMATIC	EX-2			I⊢-4 	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM ALUM FEED SYSTEM 1	
K-3.5 MAIN CIRCUIT BREAKER 52-M2 CONTROL SCHEMATIC	EX-3			I <b>⊦</b> -5	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM ALUM FEED SYSTEM 2	
K-3.6 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K2 DIFFERENTIAL CONTROL SCHEM	EX-4			I <b>⊦-</b> 6	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM POLYMER FEED SYSTEM 1	
K-4 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K3 ONE-LINE DIAGRAM	EX-5			IF-7	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM POLYMER FEED SYSTEM 2	
K-4.1 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K3 ANSI FUNCTION DIAGRAM	EX-6			IG-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SLUDGE PUMP STATION	
4.2 FEEDER CIRCUIT BREAKER 523-1 CONTROL SCHEMATIC	EX-7			IG-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM GRAVITY THICKENER	
4-4.3 FEEDER CIRCUIT BREAKER 523-2 CONTRAL SCHEMATIC	EX-8			IG-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM WASHWATER RECOVERY BASIN	
4-4.4 TIE CIRCUIT BREAKER 523-3 CONTRAL SCHEMATIC	EX-9			IG-4	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM WASHWATER RECYCLE PUMP STATION	
-4.5 MAIN CIRCUIT BREAKER 52-M3 CONTRAL SCHEMATIC	EX-10			IH-1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM BELT FILTER PRESS FEED PUMPS	
-4.6 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-K3 DIFFERENTIAL CONTROL SCHEM	EX-11			IH-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SLUDGE THICKENING POLYMER SYSTEM	
4-5 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-GEN ONE-LINE DIAGRAM	EX-12			IH-3	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM BELT FILTER PRESS	
-5.1 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-GEN ANSI FUNCTION DIAGRAM	EX-13			IL-T	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM RAW WATER PUMP STATION  PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM RAW WATER CHEMICAL INJECTION	
-5.2 GENERATOR CIRCUIT BREAKER 52-G1 CONTROL SCHEMATIC	EX-14			IL-2	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM RAW WATER CHEMICAL INJECTION  PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM CORRER ION GENERATION SYSTEM	
-5.3 GENERATOR CIRCUIT BREAKER 52-G2 CONTROL SCHEMATIC	EX-15			IN-T	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM COPPER ION GENERATION SYSTEM  PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SODIUM PERMANGANATE FEED SYSTEM	
G-5.4 GENERATOR CIRCUIT BREAKER 52-G3 CONTROL SCHEMATIC	EX-16			IN-2 I <i>7</i> -1	PROCESS MECHANICAL AND INSTRUMENTATION DIAGRAM SODIUM PERMANGANATE FEED SYSTEM  INSTALLATION DETAIL 1	
-5.5 TIE CIRCUIT BREAKER 52-G4 CONTROL SCHEMATIC	EX-17			IZ-1	INSTALLATION DETAIL 1 INSTALLATION DETAIL 2	
C-5.6 TIE CIRCUIT BREAKER 52-G5 CONTROL SCHEMATIC	EX-18			IZ-2 IZ-3	INSTALLATION DETAIL 2 INSTALLATION DETAIL 3	
-5.7 TIE CIRCUIT BREAKER 52-G6 CONTROL SCHEMATIC	EX-19	9 WASHWATER RECYCLE PUMP CONTROL SCHEMATICS II		17-4	INSTALLATION DETAIL 3  INSTALLATION DETAIL 4	
-5.8 FEEDER CIRCUIT BREAKER 52-G7 CONTROL SCHEMATIC	EX-20	0 WASHWATER RECYCLE PUMP CONTROL SCHEMATICS IN		1 <b>7-</b> 5	INSTALLATION DETAIL 4  INSTALLATION DETAIL 5	
5.9 METAL-CLAD PARALLELING SWITCHGEAR MVSWGR-GEN DIFFERENTIAL CONTROL SCH	C EX-21	1 GRAVITY THICKENER CONTROL SCHEMATICS		1 <i>7-</i> 6	INSTALLATION DETAIL 6	
2-5.10 PARALLELING SWITCHGEAR MVSWGR-GEN CONTROL RISER DIAGRAM	EX-22	2 FILTRATE PUMP CONTROL SCHEMATICS		3 17-7	INSTALLATION DETAIL 6  INSTALLATION DETAIL 7	
GENERATOR CONTROL PANEL MCP-1 DETAILS	EX-23	3 SLUDGE PUMP CONTROL SCHEMATICS		IZ-7	INSTALLATION DETAIL 7	
-5.12 GENERATOR CONTROL CONDUIT SCHEDULE	EX-24	WASHWATER SETTLING BASIN DRIVE CONTROL SCHEMA	TICS	0 17-9	INSTALLATION DETAIL 9	
6 MV MOTOR CONTROL CENTER MVMCC-1 ONE-LINE DIAGRAM	EX-25	TRANSFER PUMP CONTROL SCHEMATICS I		IZ-9	INSTALLATION DETAIL 9  INSTALLATION DETAIL 10	
7-7 MV MOTOR CONTROL CENTER MVMCC-2 ONE-LINE DIAGRAM	EX-26	6 TRANSFER PUMP CONTROL SCHEMATICS II		. <u> </u>	INSTALLATION DETAIL 10	
-8 MV MOTOR CONTROL CENTER MVMCC-3 ONE-LINE DIAGRAM	EX-27	7 TRANSFER PUMP CONTROL SCHEMATICS III		IZ-11	INSTALLATION DETAIL 12	
-9 SWITCHGEAR SWGR-K1 ONE-LINE DIAGRAM	EX-28	8 TRANSFER PUMP CONTROL SCHEMATICS IV		IZ-13	INSTALLATION DETAIL 13	
-10 MOTOR CONTROL CENTER MCC-K1 ONE-LINE DIAGRAM	EX-29	9 BACKWASH PUMP CONTROL SCHEMATICS I		IZ-14	INSTALLATION DETAIL 14	
4-11 MOTOR CONTROL CENTER MCC-K2 ONE-LINE DIAGRAM	EX-30	BACKWASH PUMP CONTROL SCHEMATICS II		IZ-15	INSTALLATION DETAIL 15	TEOFTE
-12 MOTOR CONTROL CENTER MCC-K3 ONE-LINE DIAGRAM	EX-31			IZ-16	INSTALLATION DETAIL 16	65. A
ELECTRICAL BUILDING POWER AND CONTROL PLAN	EX-32			IZ-17	INSTALLATION DETAIL 17	
ELECTRICAL BUILDING LIGHTING AND RECEPTACLE PLAN	EX-33			IZ-18	INSTALLATION DETAIL 18	SARAH ALBERS S
-15 ELECTRICAL BUILDING TRANSFORMER BELOW GRADE CONDUIT AND GROUNDING PLAN	EX-34			IZ-19	INSTALLATION DETAIL 19	· 3. 111102
2-16 ELECTRICAL BUILDING BELOW GRADE ROUTING PLAN	EY-1		LIGHTING, RECEPTACLE, POWER AND CONTROL ELECTRICAL PLANS	IZ-20	INSTALLATION DETAIL 20	CENSE!
C-17 ELECTRICAL BUILDING GROUNDING PLAN	EY-2					OS/ONAL E
4-18 ELECTRICAL BUILDING GENERATOR BELOW GRADE CONDUIT PLAN	EY-3		G VALVES ELECTRICAL PLAN			Cler ( X V)
ELECTRICAL BUILDING GENERATOR GROUNDING PLAN	EZ-1	ELECTRICAL STANDARD DETAILS I				1/19/2
	DESIGNED BY: J. MAYER					PROJECT NO. 2
	DESIGNED BY: J. MAYER  DRAWN BY: K. REESE	) <b>   </b>	CITY OF GEORGETOWN, TEXAS			FILE NAME: GO
	SHEET CHK'D BY: S. STEWART	mith			<b></b>	SHEET NO
	SHELL CHAD DI. S. SIEMWA		SOUTH LAKE		SHEET INDEX III	SHEET INC
	CROSS CHK'D BY: A. KARAMALEGOS				OHEET INDEX III	
1/19/22 FBF AKM CONFORMED DRAWINGS  /. DATE DRWN CHKD PEMARKS	CROSS CHK'D BY: A. KARAMALEGOS 9430 RE	ESEARCH BLVD., SUITE 1-200 TX 78759	WATER TREATMENT PLANT		OHEET INDEX III	G-3



B

 $\overline{A}$ 






# SECTION NUMBER SHEET WHERE SECTION IS LOCATED. IF THE SECTION IS SHOWN ON THE SAME

# DETAIL CALL OUT SYMBOLS

SHEET NUMBER IS REPLACED

WITH A DASH.

IS TAKEN \*




DETAIL LETTER -

IF MULTIPLE DETAILS REFER TO THE SAME AREA OF THE DRAWING, THE BUBBLES ARE STACKED SIDE BY SIDE.

DRAWING, SECTION & DETAIL TITLES SUBTITLE OR DESCRIPTION (AS REQ'D)

SUBTITLE OR DESCRIPTION (AS REQ'D)

### **ELEVATION** 1/4" = 1'-0"



\* IF SECTION, DETAIL, SCHEMATIC OR DIAGRAM IS DRAWN ON THE SAME SHEET THAT IT IS TAKEN FROM, THE SHEET NUMBER IS REPLACED WITH A HYPHEN. IF THE SECTION IS REFERENCED ON MULTIPLE SHEETS, THE SHEET NUMBER SHOWN INDICATES THE FIRST SHEET THE SECTION IS TAKEN FROM.

# MB-2- SEQUENTIAL SHEET NUMBER

A TREATMENT STRUCTURE

E FILTRATE LIFT STATION

I ADMINISTRATION BUILDING

RAW WATER PUMP STATION

N RAW WATER CHEMICAL FEED

M RAW WATER ELECTRICAL BUILDING

F CHEMICAL FACILITY

J STORAGE BUILDING K ELECTRICAL BUILDING

P RAW WATER PIPELINE

X ELECTRICAL SCHEMATICS

C CLEARWELLS

G RESIDUALS

R GRADING

Y YARD PIPING

FIRE PROTECTION NOTES

A SEPARATE PERMIT SHALL BE SUBMITTED, UNDER GROUND FIRE LINE SUPPLY.

BACKFLOW PROTECTION WILL BE PROVIDED IN ACCORDANCE WITH THE CITY OF GEORGETOWN REQUIREMENTS WHEN REQUIRED. BACKFLOW PROTECTION WILL BE INSTALLED IN ACCORDANCE WITH THE DETAIL PROVIDED IN THE UTILITY DRAWINGS.

IN ACCORDANCE WITH NFPA 24 INSTALLATION OF PRIVATE SERVICE MAINS AND

ALL UNDERGROUND SHALL REMAIN UNCOVERED UNTIL A VISUAL INSPECTION IS

CONDUCTED BY THE CITY OF GEORGETOWN FIRE MARSHAL'S OFFICE (FMO). ALL JOINT RESTRAINTS AND THRUST BLOCKING SHALL BE UNCOVERED FOR VISUAL

ALL UNDERGROUND SHALL PASS A HYDROSTATIC TEST WITNESSED BY GEORGETOWN

FMO. ALL JOINTS SHALL BE UNCOVERED FOR HYDROSTATIC TESTING. ALL PIPING

IS GREATER, AND SHALL MAINTAIN THE PRESSURE + OR - FOR 2 HOURS.

LICENSE REQUIREMENTS OF EITHER RME-U OR G. WHEN CONNECTING BY

FIRE HYDRANT MAINTENANCE SHALL BE IN ACCORDANCE WITH NFPA 291.

THE HYDRANT FLOW STANDARD IN AS FOLLOWS AT 20 PSI RESIDUAL

BLUE

RED

GREEN

ORANGE

8. FENCES, LANDSCAPING AND OTHER ITEMS WILL NOT BE INSTALLED WITHIN 3-FEET.

AND WHERE THEY OBSTRUCT VISIBILITY OR ACCESS TO HYDRANTS, OR REMOVE

OR VALVE WHERE THE PRIMARY PURPOSE OF WATER IS FOR FIRE PROTECTION

10. LA-507.5.7 CITY OF GEORGETOWN FIRE HYDRANT COLOR CODE SYSTEM. PRIVATE

ALL PRIVATE FIRE HYDRANTS SHOULD BE INSPECTED, MAINTAINED, AND FLOW

ALL PRIVATE HYDRANT BARRELS WILL BE PAINTED RED WITH THE BONNET PAINTED USING THE HYDRANT FLOW STANDARD IN PARAGRAPH C OF THIS SECTION TO

TESTED ANNUALLY, AND COLOR CODED TO INDICATE EXPECTED FLOW FROM THE

BY PAINTING THE BONNET THE APPROPRIATE COLOR FOR THE EXPECTED FLOW

HYDRANT FLOW CODING STANDARDS. PUBLIC HYDRANT BARRELS WILL BE PAINTED

SILVER, THE HYDRANTS WILL BE FLOW TESTED, AND THE BONNET PAINTED USING

BLACK OR BAGGED

AT THE CONCLUSION OF CONSTRUCTION, FIRE HYDRANTS SHALL BE FLOW TESTED AND COLOR CODED IN ACCORDANCE WITH THE CITY'S STANDARDS, AND RESULTS

SHALL BE EMAILED TO THE FIRE DEPARTMENT. IFC-LA-507.5.7 FIRE HYDRANT

HYDRANT DURING NORMAL OPERATION. SUCH COLOR APPLIED TO THE FIRE HYDRANT

INDICATE FLOW. IT WILL BE THE CUSTOMER'S RESPONSIBILITY TO TEST AND MAINTAIN

AND ATTACHMENTS SUBJECTED TO SYSTEM WORKING PRESSURE SHALL BE TESTED

AT 200 PSI, OR 50 PSI MORE THAN THE SYSTEM WORKING PRESSURE, WHICHEVER

UNDERGROUND TO THE WATER PURVEYOR'S MAIN FROM THE POINT OF CONNECTION

6. ALL UNDERGROUND SHALL BE FLUSHED PER THE REQUIREMENTS OF NFPA

STANDARD 24 AND WITNESSED BY GEORGETOWN FMO.

ALL TEES, PLUGS, CAPS, BENDS, REDUCERS, VALVES SHALL BE RESTRAINED

UNDERGROUND FIRE LINES. PRIOR TO INSTALLATION OF UNDERGROUND FIRE LINES,

ALL PRIVATE FIRE LINES AND WHAT THEY PROVIDE SERVICE TO WILL BE INSTALLED

AGAINST MOVEMENT. THRUST BLOCKING AND JOINT RESTRAINT WILL BE INSTALLED IN

APPROVAL OF THIS SITE PLAN DOES NOT IMPLY APPROVAL TO INSTALL

Z STANDARD DETAILS

H DEWATERING

AREA CODE

B DISINFECTION BASIN AND TRANSFER PUMP STATION

D HIGH SERVICE AND BACKWASH WATER PUMP STATIONS

DISCIPLINE -

M PROCESS MECHANICAL

GENERAL

A ARCHITECTURAL

F FIRE PROTECTION

INSTRUMENTATION

THEIR APPURTANCES.

ACCORDANCE WITH NFPA 24.

THEIR PRIVATE HYDRANTS(S).

GREATER THAN 1500 GPM

1000 - 1500 GPM

500 - 999 GPM LESS THAN 500 GPM

CONDITION

FLOW COLOR

NOT WORKING

SYSTEMS.

S STRUCTURAL

PL PLUMBING

PL PLUMBING

CIVIL

H HVAC

CONTRACTOR SHALL PROVIDE "AS BUILT" DRAWINGS TO THE ENGINEER SO THAT THE REPRODUCIBLE OF THE ENGINEERING DRAWINGS MAY BE CORRECTED TO REFLECT "RECORD DRAWING" CONDITIONS.

THE CONTRACTOR WILL BE REQUIRED TO PROVIDE AND MAINTAIN ALL NECESSARY WARNING AND SAFETY DEVICES TO PROTECT WORKMEN AND THE PUBLIC SAFETY AND HEALTH UNTIL THE WORK HAS BEEN COMPLETED AND ACCEPTED BY THE CITY.

THE LOCATIONS OF EXISTING UTILITIES & STRUCTURES SHOWN ON THESE DRAWINGS ARE APPROXIMATE & ALL MAY NOT BE SHOWN. IT IS THE RESPONSIBILIT OF THE CONTRACTOR TO LOCATE AND VERIFY IN THE FIELD THE LOCATION OF ALL EXISTING UTILITIES & STRUCTURES PRIOR TO ORDERING MATERIALS AND

BEGINNING CONSTRUCTION. AT LEAST 48 HOURS PRIOR TO BEGINNING CONSTRUCTION IN THE VICINITY OF UTILITIES, NOTIFY THE FOLLOWING AS APPLICABLE.

**GENERAL NOTES** 

 $\overline{H}$ 

CITY OF GEORGETOWN 512-930-3555 FRONTIER 512-869-2231 PEDERNALES ELECTRIC CO-OP 877-372-0391 CITY OF GEORGETOWN ELECTRIC ENGINEERING 512-930-3651

TREES NOT SHOWN TO BE REMOVED SHALL NOT BE REMOVED WITHOUT ENGINEER'S APPROVAL. TREES APPROVED BY THE ENGINEER TO BE TRIMMED, SHALL BE CUT USING PROPER TOOLS AND THE TREE CUT SHALL BE PROPERLY SEALED.

NO WORK SHALL BE PERFORMED ON SATURDAYS, SUNDAYS, OR CITY HOLIDAYS WITHOUT WRITTEN PERMISSION BY OWNER. THE SPECIFIED CONTRACT TIMES WERE ESTABLISHED ASSUMING NO WEEKEND OR HOLIDAY WORK. SATURDAYS, SUNDAYS, AND HOLIDAYS WILL BE COUNTED IN DETERMINING THE NUMBER OF CONSECUTIVE CALENDAR DAYS USED TO COMPLETE THE PROJECT. WORKING HOURS ARE LIMITED TO 7:00 AM TO 6:00 PM, MONDAY THROUGH FRIDAY.

ELECTRICAL LINES ARE LOCATED CLOSE TO THE PROJECT. THE ATTENTION OF THE CONTRACTOR IS DIRECTED TO THE STATE LAW (VERNON'S ANNOTATED TEXAS STATUTES, ARTICLE 1436(C)) CONCERNING OPERATIONS IN THE VICINITY OF ELECTRICAL LINES AND THE NEED FOR EFFECTIVE PRECAUTIONARY MEASURES.

811 OR 800-344-8377

CONTRACTOR SHALL PARTICIPATE IN A PRE-CONSTRUCTION MEETING WITH THE OWNER, ENGINEER, AND OTHER AFFECTED PARTIES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION.

NO BURNING OF TREES, BRUSH, RUBBISH, VEGETATION, OR OTHER OBJECTIONABLE MATTER WILL BE ALLOWED ON THE PROJECT SITE. ALL CLEARED AND GRUBBED MATERIAL SHALL BE DISPOSED OF IN A MANNER ACCEPTABLE TO THE CITY OF GEORGETOWN. ALL EXCESS EXCAVATED MATERIALS SHALL BE HAULED OFF-SITE.

NO BLASTING WILL BE ALLOWED.

TEXAS ONE CALL

10 ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.

11 CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF EACH SEDIMENTATION/EROSION CONTROL MEASURE ON THIS PROJECT.

12 UNSUITABLE MATERIAL, STUMPS, OR EXCESS EXCAVATED MATERIALS SHALL BE KNOWN AS "WASTE" AND SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND IT SHALL BECOME HIS SOLE RESPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE PROJECT IN AN ENVIRONMENTALLY SOUND & LEGALLY APPROVED MANNER. THE CONTRACTOR SHALL NOTIFY THE CITY OF GEORGETOWN PRIOR TO OFFSITE DISPOSAL. THIS NOTIFICATION SHALL INCLUDE THE DISPOSAL LOCATION AND COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL

3 THE CONTRACTOR SHALL GIVE THE OWNER A MINIMUM OF 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION. THE PHASES OF

CONSTRUCTION ARE AS FOLLOWS: INSTALL EROSION AND SEDIMENTATION CONTROL.

> INSTALL TREE PROTECTION. SITE VISIT BY OWNER'S INSPECTOR

AFTER INSPECTOR APPROVAL, BEGIN CONSTRUCTION. UPON CONSTRUCTION COMPLETION, RESTORE ALL DISTURBED AREAS.

ARRANGE FOR FINAL INSPECTION.

REMOVE TEMPORARY EROSION CONTROL MEASURES.

14 ALL EXISTING UTILITIES, STRUCTURES, AND PIPES SHALL BE PROTECTED BY CONTRACTOR

15 CARE SHALL BE TAKEN TO PROTECT EXISTING FACILITIES.

16 FINISHED GRADES SHALL SLOPE UNIFORMLY.

17 TRACK EQUIPMENT WILL NOT BE ALLOWED ON PAVED ROADWAYS WITHOUT APPROPRIATE PROTECTION FOR THE PAVEMENT AS APPROVED BY THE ENGINEER. 18 NOT USED.

19 SURVEY CONTROL POINTS ARE SHOWN ON CIVIL SHEETS. THIS INFORMATION SERVES AS ONE-TIME BENCHMARK INFORMATION. CONTRACTOR TO PROVIDE ADDITIONAL LINES AND GRADES AS REQUIRED.

20 ALL POTABLE WATER PIPING SHALL BE RESTRAINED PER AWWA GUIDELINES WITH A MINIMUM FACTOR OF SAFETY OF TWO. PROCESS PIPING RESTRAINED JOINTS SHALL BE PROVIDED AT ALL FITTINGS, AS DESCRIBED BELOW, UP TO THE FIRST JOINT OF PIPE WITHOUT A FITTING, AND SHALL BE DESIGNED PER AWWA GUIDELINES WITH A MINIMUM FACTOR OF SAFETY OF TWO. FITTINGS INCLUDE ALL VERTICAL AND HORIZONTAL CHANGES IN PIPE DIAMETER (REDUCERS), OR DIRECTION (E.G. TEES, BENDS, ELBOWS, AND CROSSES). PLUGS, VALVES, OTHER LOCATIONS SHOWN ON THE DRAWINGS, AND ON ALL BURIED PIPING HAVING FLEXIBLE JOINTS. JOINTS SHOULD BE DESIGNED TO PREVENT THE PIPE FROM MOVING WHEN SUBJECTED TO OPERATING AND TEST PRESSURES. RESTRAINED JOINTS SHALL HAVE CADMIUM PLATED OR OTHER APPROVED CORROSION RESISTANT BOLTS, NUTS, ETC. RESTRAINED JOINTS SHALL BE "FLEX-RING" OR "LOK-RING"BY AMERICAN CAST IRON PIPE COMPANY, TR FLEX BY U.S. PIPE COMPANY, OR AN APPROVED EQUAL".

21 ALL CONSTRUCTION MATERIAL/DEBRIS SHALL BE PLACED IN AN ON-SITE CONTAINER AND DISPOSED OF PROPERLY AT AN AUTHORIZED LANDFILL.

22 AT THE COMPLETION OF WORK AND IMMEDIATELY PRIOR TO FINAL INSPECTION, CLEANING OF THE ENTIRE PROJECT SHALL BE ACCOMPLISHED IN ACCORDANCE WITH SECTIONS CIP14, CIP17, G8, AND 01710.

23 CONTRACTOR SHALL FIELD VERIFY ALL EXISTING FACILITIES (SIGNS, UTILITIES, POLES, STRUCTURES, ETC). NOT ALL FACILITIES, ETC, ARE SHOWN.

24 ANY EXISTING PAVEMENT, CURBS, AND/OR SIDEWALKS DAMAGED OR REMOVED DURING CONSTRUCTION SHALL BE REPLACED OR REPAIRED AT THE CONTRACTOR'S EXPENSE.

25 ANY EXISTING FENCES, WALLS, AND FACILITIES DAMAGED OR REMOVED DURING CONSTRUCTION SHALL BE REPLACED OR REPAIRED AT THE CONTRACTOR'S

26 ALL DISTURBED AREAS SHALL BE GRADED, HYDROMULCHED OR SODDED, AS INDICATED ON THE DRAWINGS AND RESTORED AT THE CONTRACTOR'S EXPENSE.

27 CONTRACTOR SHALL FOLLOW SEQUENCE OF CONSTRUCTION SPECIFIED IN SECTION CIP3 AND SHALL NOT DEVIATE WITHOUT WRITTEN AUTHORIZATION FROM ENGINEER.

28 UNLESS OTHERWISE NOTED, ALL FLEXIBLE COUPLINGS, FLANGE COUPLING ADAPTERS, ETC, SHALL BE RESTRAINED PER SPECIFICATIONS & DETAILS.

29 WHEN MAKING CONNECTIONS TO NEW OR EXISTING PIPING, CONTRACTOR SHALL PROVIDE ALL FITTINGS, ADAPTERS, CONNECTING PIECES, SLEEVES, FLEXIBLE COUPLINGS, ETC REQUIRED TO MAKE THE CONNECTIONS IN A MANNER SATISFACTORY TO THE ENGINEER REGARDLESS OF WHETHER OR NOT THESE COMPONENTS ARE SHOWN ON THE DRAWINGS.

30 WHEN CONNECTING TO EXISTING MANHOLES, FIELD VERIFY EXISTING INVERT ELEVATIONS AND MODIFY PROPOSED INVERT ELEVATIONS TO ACHIEVE CONTINUOUS DOWNWARD SLOPE.

31 ALL CONNECTIONS BETWEEN NEW AND/OR EXISTING PIPING, VALVES, FITTINGS, ETC, WHERE DISSIMILAR METALS WILL BE IN CONTACT SHALL BE PROTECTED BY INSULATING SYSTEMS AS APPROVED BY THE ENGINEER.

32 ALL CAPS/PLUGS NOT SHOWN ON YARD PIPING PLAN SHEETS. CONTRACTOR IS RESPONSIBLE FOR ALL CAPS/PLUGS. ALL EXPOSED ENDS OF PIPES TO BE ABANDONED IN PLACE SHALL BE CAPPED/PLUGGED WITH CONCRETE OR MECHANICAL CAPS/PLUGS. RESTRAINED MECHANICAL CAPS OR PLUGS ARE REQUIRED FOR PIPES THAT WILL REMAIN IN SERVICE OR FOR FUTURE STUBOUTS.

33 PIPE ALIGNMENT BENDS OF LESS THAN MANUFACTURER'S PUBLISHED ACCEPTABLE DEFLECTION MAY BE MADE BY DEFLECTING THE JOINTS PER ENGINEER'S APPROVAL. BENDS OF MORE THAN MANUFACTURER'S PUBLISHED ACCEPTABLE DEFLECTION SHALL BE MADE WITH MANUFACTURER'S STANDARD FITTINGS PER ENGINEER'S APPROVAL

34 PIPE SUPPORTS ARE SHOWN FOR VISUALIZATION PURPOSES. FINAL TYPES, COUNTS, SIZING, ETC. ARE A DELEGATED DESIGN DELIVERABLE. SEE SPECIFICATION SECTION 400507, HANGERS AND SUPPORTS FOR PROCESS PIPING.

35 ALL PIPING UNDER STRUCTURES SHALL BE CONCRETE ENCASED, UNLESS SPECIFICALLY NOTED OTHERWISE.

36 CLEARING IS NOT ALLOWED BETWEEN MARCH 1ST AND SEPTEMBER 1ST.



				JGW		
					DESIGNED BY:	A. BRO
Α	1/19/22	JBF	AKM	CONFORMED DRAWINGS	DRAWN BY:	S.
2	11/16/21	JBF	AKM	REVISED PER ADDENDUM NO. 2	SHEET CHK'D BY:_	S. STEW
5	12/17/21	JBF	AKM	REVISED PER ADDENDUM NO. 5	CROSS CHK'D BY:	
7	1/14/22	JBF	AMK	REVISED FOR ADDENDUM NO. 7	APPROVED BY:	S. STEW
REV.	DATE	DRWN	CHKD	REMARKS	DATF:	DECEMBER 2




CITY OF GEORGETOWN, TEXAS

SOUTH LAKE WATER TREATMENT PLANT

GENERAL LEGEND AND NOTES I

PROJECT NO. 2048-24892 FILE NAME: GOO6NFGN.DW SHEET NO.

G-6



\F/

\G/

\H\

DATE DRWN CHKD

REMARKS

 $\overline{A}$ 

B

 $\sqrt{C}$ 

Tel: (512) 346-1100

TBPE Firm Registration No. F-3043

DECEMBER 202

	·		·	Y	·	ABBREVIATIONS	S	Y		Y	V	
ARE NOT TO BE USED, IN WHOLE OR PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CDM SMITH.  ARE NOT TO BE USED, IN WHOLE OR PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CDM SMITH.	TWO SPEED, TWO WINDING TWO SPEED, TWO WINDING AIR (COMPRESSED)  AP AMPERE AIR CONDITIONING AERATION AIR ANCHOR BOLT AEROBIC BASIN AERATOR ASBESTOS CEMENT ABANDON ACRYLONITE—BUTADIENE—STYRENE ABOVE AIR CONDITIONING CONDENSING UNIT AIR CUSHION CHECK VALVE ACOUSTICAL MASONRY UNIT ASBESTOS CEMENT PIPE ACOUSTICAL TILE AIR CONDITIONING UNIT ACCESS DOOR ADDITIONAL ADHESIVE ADJUSTABLE, ADJUST ADAPTER ADJUSTABLE, FREQUENCY DRIVE ABOVE FINISHED FLOOR ABOVE FINISHED FLOOR ABOVE FINISHED FLOOR ABOVE FINISHED GRADE AGGREGATE AIR HORSEPOWER AIR HANDLING UNIT ANALOG INPUT, AIR INSTRUMENT ALUMINUM T ALUM VENT ALUM SYSTEM ALTERNATE (ING) ALTITUDE ALUMINUM SULFATE ALUM (CHEMICAL) AMMONIA GAS AMMONIA LIQUID ANODIZE ANALOG OUTPUT ACCESS PANEL OX APPROXIMATE (LY) ACID RESISTANT ARCHITECT (URAL) (URE) AROUND AIR RELEASE VALVE ACTIVATED SURGEY ASPHALT C ASSOCIATION AMERICAN SOCIETY FOR TESTING MATERIALS AUTOMATIC TEMPERATURE CONTROL AUTOMATIC TRANSFER SWITCH AUTOMATIC	CGFB CGV CH AM CHAN CHKD CHR CI CIGL CIR CIR CIR CIS CIV CL2	CEMENTITIOUS GLASS FIBER BOARD CHLORINE GAS (VACUUM) CONCRETE HARDENER CHAMNEL CHECKERED CHLORINATOR CHLOROPRENE RUBBER (NEOPRENE) CAST IRON CAST IRON PIPE GLASS LINED CAST IRON PIPE GLASS LINED CAST IRON SOIL PIPE CAST IRON SOIL PIPE CAST IRON PIPE UNLINED CONSTRUCTION JOINT CIRCUIT CENTERLINE CHLORINE SYSTEM CHLORINE (GAS) CHLORINE (IQUID) CHLORINE SULUTION CHLORINE SOLUTION CHLORINE SULUTION CHLORINE VENT CURRENT LIMITING FUSE CEILING CONTROL JOINT CAULKING CLEAR CLARIFIED WATER (CLARIFIER EFFLUENT) CORRUGATED METAL PIPE CONCRETE MONUMENT CONCRETE MONUMENT CONDENSATE SUPPLY CLEAN OUT COLUMN COMBINATION COMBINATION COMBINATION COMBISSION COMPRESSIBLE COMPRESSION JOINT CONCRETE CONDUCTIVITY CONCRETE PRESSURE PIPE CONCRETE PRESSURE PIPE CONTROL POWER TRANSFORMER CHLORINE RESIDUAL CONTROL POLYVINYLCHLORIDE PIPE CONCRETE PRESSURE PIPE CONTROL POLYVINYLCHLORIDE PIPE CHLORINE RESIDUAL CONTROL RELAY COURSE (S) CARBON STEEL CONTROL SWITCH COUNTERSINK CONDITIONED SLUDGE CHLORINE SULPHONILE POLYETHYLENE (HYPALG CAUSTIC METERING PUMPS CASTING CERAMIC TILE	FB FLOOR BOX (BUSHING TYPE)  FBO FURNISHED BY OTHERS  FBR FULL VOLTAGE REVERSING	GRS GALVANIZED RIGID STEI GRTG GRATING GSC GRIT SCREEN GSKT GASKET GV GATE VALVE GYP GYPSUM  HAS HEADED ANCHOR STUD HB HOSE BIBB HC HEATING COIL HCL HYDROCHLORIC ACID HD HEAVY DUTY HDPE HIGH DENSITY POLYETH HDR HEADER HDWD HARDWOOD HDWR HARDWOOD HDWR HARDWARE HEX HEXAGON HFAC HARNESSED FLANGED HGR HANGER HGT HEIGHT HH HANDHOLE HM HOLLOW METAL HOA HAND—OFF—AUTO HOR HORIZONTAL HP HIGH POINT HP HORSE POWER HPA HIGH SERVICE HS HIGH SERVICE HS HIGH STRENGTH HSM HIGH SERVICE HS HIGH STRENGTH HWA HOPRABLE HOT WATER HWA HOPRABLE HOT WATER HWA HIGH WATER LEVEL HWR HOT WATER RETURN HWS HOT WATER SUPPLY HWW HIGH PRESSURE WASH HZ HERTZ H2O WATER  IA INSTRUMENT AIR IAW IN ACCORDANCE WITH ID INSIDE DIAMETER IE INVERT ELEVATION IF INSIDE FACE IFM INFLUENT FLOW METER IIR ISOBUTENE ISOPRENE	MATL MAU MAX MB MC MCC MC	MASONRY MATERIAL MAKE UP AIR UNIT MAXIMUM MACHINE BOLTS THOUSAND BTU PER HOUR MANUAL BAR SCREEN STEEL MISCELLANEOUS CHANNEL MOTOR CONTROL CENTER MASONRY CONTROL JOINT METHANOL MEASURE MECHANICAL MEMBRANE MOTORIZED EFFLUENT WEIRS MANUFACTURED MANUFACTURED MANUFACTURER MILLIGRAMS PER LITER MILLION GALLONS PER DAY MANHOLE METAL HOSE MINIMUM MECHANICAL INFLUENT SCREEN MISCELLANEOUS MECHANICAL JOINT MIXED LIQUOR MILLIMETER MASONRY OPENING MOTOR OPERATED DAMPER MONUMENT MOTOR MILES PER HOUR MOISTURE RESISTANT METAL REINFORCED PLASTIC PIPE MOTORIZED SLUICE GATES MOUNTED MOUNTED MOUNTING METAL MUD VALVE  NORTH NITROGEN SODIUM CHLORITE NITRILE RUBBER NORMALLY CLOSED NON—CLOG DRY PIT PUMP NATIONAL ELECTRIC CODE NEUTRAL NEAR FACE NOT IN CONTRACT NORMALLY OPEN OR NUMBER NOMINAL NATIONAL OCEANOGRAPHIC SURVEY NONIONIC POLYMER AMERICAN NATIONAL TAPER PIPE THREAD (NON—POTABLE) WATER NATIONAL RUBBER NON—RISING STEM NON—SHRINK GROUT NOT TO SCALE	PL PROPERTY LINE PLC PROGRAMMABLE LO PLK PLANK PLP POLYPHOSPHATE PLS PLASTIC LINED STE PLT PLANT PLW PLANT WATER PLYWD PLYWOOD PM PRESSED METAL PNL PANEL POJ PUSH ON JOINT POLYE POLYETHYLENE POLYP POLYPROPYLENE POM POLYOXYMETHYLEN POT POTASSIUM PERMA PP POWER POLE PPB PARTS PER BILLIOI PPM PARTS PER MILLIO PRESSED METAL POTH POTASSIUM PERMA PP POWER POLE PPB PARTS PER MILLIOI PR PAIR PR PRETREATED WATER PR PRESSURE PREST PRESSURE PREST PRESSURE PREST PRESSURE PREST PRESSURE TREATEI PRIM PRIMARY PRMLD PREMOLDED PRV PRESSURE RELIEF PRW PRESSURE WASTE PS PUMP STATION PSC PRIMARY SCUM PSF POUNDS PER SQU. PSI POUNDS PER SQU	SCL   SCR   SCV   SCV	SLAB CONTROL JOINT SCRUBBING LIQUID SCREENING DEVICE N SCREENING DEVICE N SCREENING DEVICE STORM DRAIN SUPPLY DIFFUSER SECONDARY SECONDARY SECONDS -1 PER SECOND T SECTION SECONDARY EFFLUENT SLAB EXPANSION JOINT SEAMLESS FLOORING SUPPLY FAN SILT FENCE SLUDGE FEED PUMP SYNTHETIC FIBER REINFORCED SLUICE GATE SUPPLY GRILLE C SLUICE GATE - MANUAL CRANK OPERATOR HW SLUICE GATE - MATUAL CRANK OPERATOR M SLUICE GATE - MOTOR OPERATOR I STRUCTURAL GLAZED FACING TILE SLUDGE GRINDER SHELDED SODIUM HYDROXIDE (CONCENTRATED) SODIUM HYDROXIDE (DILUTED) SODIUM HYDROXIDE (DILUTED) SODIUM HYDROXIDE (RECIRCULATED) SHEET SIMILAR SOLDERED JOINT SINK SLUEG GATE - MANUAL CRANK OPERATOR T SEALANT SLEEVE P SUMP PUMPS SOLID REATE - MOTOR T SEALANT SLEEVE P SUMP PUMPS SOLID REUTRAL OR SUPERNATANT L SODIUM FULORIDE SLIP ON JOINT N SOLUTION V SOLENGID VALVE SUBMERSIBLE PUMP C SPECIFICATION, SPECIFIED SAMPLE SAMPLE LINE SPRING SPRINKLER LINE SPRING SAMPLE SERVICE EQUIPMENT DRAIN SOULMS SILLOCATE SERVICE SINK	U HEAT TRANSFER COEFFI UC UNDERCUT UD UNDERCOUT UD UNDERGROUND UGND UNDERGROUND TELEPHO UH UNIT HEATER UL UNDERWRITERS LABORA' UN UNION UNO UNLESS NOTED OTHERW UPVC UN-PLASTICISED POLYV UR URINAL  V VOLTS VA VENT AIR VA-H HYDRAULIC VALVE OPER VA-B SOLENOID VALVE OPER VAC VACUUM VAR VARIOUS/VARIABLE VAV VARIABLE AIR VOLUME VB VALVE BOX VB VAPOR BARRIER VBR VACUUM BREAKER VC VICTAULIC COUPLING (S VC VITRIFIED CLAY PIPE VCT VINYL COMPOSITION TILL VD VOLUME DAMPER VE VACUUM EXHAUST VEL VELOCITY VERT VERTICAL VFD VARIABLE FREQUENCY IC VIB VIBRATION VIPA VIRGIN ISOPROPHYL ALC VND VARIABLE SPEED DRIVE VT VENT VTR VENT THRU ROOF  W WATER W WIDE W/ WITH W/A WHERE APPLICABLE W/O WITHOUT WAP WALL PIPE WAS WASTE BACKWASH WATE WC WATER CLOSET WD WINDOW WF WIDE FLANGE WG WASTE GAS WH WATER HEATER WATHOURD DEMANDO ME*	ONE CABLE  TORY  WISE VINYL CHLORIDE  RATOR PRATOR ATOR  SHOULDERED ENDS)  E  ORIVE  COHOL ATE
ED BY PROFESSIONAL SERVICE, INCORPORATED HEREIN, ARE THE PROPERTY OF CDM SMITH AND SAME THE PROPERTY OF CDM SMITH AND SAME THE PROFESSIONAL SERVICE, INCORPORATED HEREIN, ARE THE PROPERTY OF CDM SMITH AND SAME THE SAME THE PROPERTY OF CDM SMITH AND SAME THE SAME THE PROPERTY OF CDM SMITH AND SAME THE SAME THE PROPERTY OF CDM SMITH AND SAME THE SAME THE PROPERTY OF CDM SMITH AND SAME THE SAME	AMERICAN WIRE GAUGE AVERAGE WATER LEVEL CURRENT TRANSDUCER  B AVERAGE WATER LEVEL CURRENT TRANSDUCER  B BACK TO BACK BLOWER CONTROL PANEL BALL CHECK VALVE BOARD BACKDRAFT DAMPER BELOW BEVEL (ED) BLIND FLANGE BELT FILTER PRESS BUTTERFLY VALVE BURIED GEAR OPERATOR BRAKE HORSEPOWER BITUMINOUS BASELINE BUILDING BLOCK BLOCKING BENCHMARK BOTTOM BOOSTER PUMP BACK PRESSURE REGULATING VALVE BEARING BRICK BRASS BRONZE BLENDED SLUDGE BOTH SIDES BASEMENT BLACK STEEL PIPE BRITISH THERMAL UNIT BETWEEN BUILT UP ROOF (ING) BALL VALVE BACKWASH RETURN BACKWASH SUPPLY BACKWASH WATER BYPASS  C C CENTER TO CENTER COMPRESSED AIR	CT CTG CTR CTU CU CU CU FT CU YD CUH CVP CV CV-A CV-H CVR CW CW CWO CWS	CURRENT TRANSFORMER COATING CENTER (ED) CENTRAL TELEMETRY UNIT COPPER CUBIC CUBIC FOOT (FEET) CUBIC YARD CABINET UNIT HEATER COPPER PIPE CHECK VALVE (AIR CUSHION) CHECK VALVE (HYDRAULIC CUSHION) CONVECTOR CLOCKWISE POTABLE COLD WATER CLEARWELL OVERFLOW COOLING WATER RETURN COOLING WATER SUPPLY  PENNY DISSOLVED ALUM DIAPHRAGM AIR PURGE DIAPHRAGM AIR VENT DECIBEL DRY BULB DIRECT CURRENT DISTRIBUTED CONTROL UNIT DEMOLITION DEPARTMENT DETAIL DRINKING FOUNTAIN DIGESTER GAS DIGITAL OR DISCRETE INPUT DUCTILE IRON DIAMETER DIAGONAL DIFFUSER DUCTILE IRON GLASS LINED DIMENSION DUCTILE IRON PIPE	FC FAIL CLOSED FC FLEX CONNECTION FCA FLANGED COUPLING ADAPTOR FCC FILTER CONTROL CONSOLE FD FLOOR DRAIN FDMPR FIRE DAMPER FDN FOUNDATION FE FILTER EXTINGUISHER FE CL3 FERRIC CHLORIDE FES FERROUS SULFATE FF FACTORY FINISH FF FAR FACE FGL FIBERGLASS FH FIRE HYDRANT FHMS FLATHEAD MACHINE SCREW FHWS FLATHEAD WOOD SCREW FI FILTER INFLUENT FIG FIGURE FIN FINISH(ED) FINW FINISHED WATER FL FLASHING FL FLOOR FL FLASH MIXER FLP FAIL LAST POSITION FIRE FL FILLER FLW FILLER FLW FILLER FLW FILLER FLW FILLER FLW FILLER FLW FILLER FLY FLASH MIXER FLP FAIL LAST POSITION FOR FILLER FLW FILLER FLW FILLER FLW FILLER FLW FILLER FLW FILLER FLY FAIL LAST POSITION FOR FUEL OIL FOB FLAT ON BOTTOM FOR FUEL OIL FOB FLAT ON BOTTOM FOR FUEL OIL SUPPLY FOT FLAT ON TOP FOV FUEL OIL SUPPLY FOT FEMALE PIPE THREAD FR FRAME FRP FIBERGLASS REINFORCED PLASTIC FRR FLOORING RUBBER(viton) FS FINE SCREEN FSC FERRIC SULFATE (CONCENTRATED)	IN INCH INF INFLUENT INSTR INSTRUMENT (TATION) INSUL INSULATION INT INTERIOR IPB IRON PIPE BOUNDARY IRB IRON ROD BOUNDARY IRP INTERNAL RECYCLE PL IRR IRRIGATION LINE ISOL ISOLATOR, ISOLATION  JC JANITOR'S CLOSET JCT JUNCTION JT JOINT JT FLR JOINT FILLER  KGV KNIFE GATE VALVE KO KNOCKOUT  L LINE OR STRUCTURAL LA LIGHTNING ARRESTER LAB LABORATORY LAD LADDER LAM LAMINATED LAT LEAVING AIR TEMPERAT LAV LAVATORY LB POUND LBS POUNDS LCP LOCAL CONTROL PANEL LCW LABORATORY COLD WAT LE LEVEL ELEMENT LF LINEAR FEET LG LONG LHW LABORATORY HOT WATE LIME LIME, DRY LKR LOCKER LLH LONG LEG MEDITONIAL LANG LEG MEDIT	O2 OA OC OCB UMPS OCS OCW OD OE OF OF OF OF OF OF OF OF OF OP OPP OPP HD OPT OS OT OT OT OT OT OV OV OVF OVHD OZA OZE  ANGLE DESIGNATION PA PA PAC PACS PAG PB	OR EQUAL OXYGEN (GAS) OUTSIDE AIR ON CENTER OR ODOR CONTROL ODOR CONTROL BLOWER ODOR CONTROL SCRUBBER OZONE SYSTEM COOLING WATER OUTSIDE DIAMETER OVERHEAD ELECTRIC OUTSIDE FACE OFFICE OZONE OFF GAS OVERHEAD (DOOR) OVERLOAD OPERATOR OPPOSITE OPPOSITE OPPOSITE OPPOSITE OPPOSITE OPPOSITE OVERHEAD TELEVISION OVER OVERHEAD TELEVISION OVER OVERHEAD TOON OVERHEAD OZONATED AIR OZONE EXHAUST  PLANT AIR POLYAMIDE PLANT AIR COMPRESSOR POWDER ACTIVATED CARBON SLURRY AIRGAP PROTECTED WATER POLYBUTYLENE PUSHBUTTON PLASTIC BALL VALVE PECAN BRANCH TRANSFER PUMP STATION POINT OF CURVE (ATURE) POLYCARBONATE POINT OF COMPLEX CURVATURE PRESTRESSED CONCRETE CYLINDER PIPE POUND PER CUBIC FOOT POLYCHLOROTRIFLUORETHYLENE PRESSURE CONTROL VALVE PRESSURE CONTROL VALVE PUMP DISCHARGE PLAIN END	R RISER(S) R+S BACKER ROD & SI R/W RIGHT—OF—WAY RA RETURN AIR RAD RADIUS RAS RETURN ACTIVATED RB RUBBER BASE RC REINFORCED CONC RCC REINFORCED CONC RCP REINFORCED CONC RCW RECYCLE WATER RCWM RECLAIMED WATER RD ROOF DRAIN RDWD REDWOOD RECT RECEPTACLE RED REDUCER REF REFERENCE/REFER REF ROOF EXHAUST FA REG REGISTER REINF REINFORCE (D, INC REQD REQUIRED RESID RESIDUAL REV REVISION RF ROOF FAN RFG ROOFING RG RETURN GRILLE RGH ROUGH RH RELATIVE HUMIDITY RH RUBBER HOSE RIS RUBBER IN SHEAR RJ RESTRAINED JOINT RJ RUSTIFICATION JOIN RL RAIN LEADER RLCI RUBBER LINED CA: RLDI RUBBER LINED DU RLG RAILING RM ROOM RMS ROOT MEAN SQUAF RND ROUND RO ROUGH OPENING RO ROUGH OPENING ROT ROTAMETER RPM REVOLUTIONS PER RR RAILROAD RR RETURN REGISTER	SSL SST ST F STA STD STIF SLUDGE STIF STIR SLUDGE STL STOR STRU STOR STRU STOR STRU STRU STRU STRU STRU STRU STRU STR	STATION STANDARD STIFFENER STIRRUP (S) STEEL R STORAGE UC STRUCTURE (S, URAL) Y STAIRWAY T SUPERINTENDENT P SUSPENDED SWITCH D SWITCHBOARD SIDE WATER DEPTH R SWITCHGEAR SYMMETRICAL  TREAD(S) TOP AND BOTTOM TONGUE AND GROOVE TANGENCY THICKENED ACTIVATED SLUDGE TEMPERATURE DIFFERENCE TRENCH DRAIN TIME DELAY ON CLOSING TIME DELAY AFTER DEENERGIZATION—OFF DELAY TIME DELAY ON OPENING H TECHNICAL TELEPHONE P TEMPERATURE P TEMPERATURE P TEMPORARY TERNAZZO	WHDM WHDR WHDR WATTHOUR DEMAND ME WHM WATTHOUR DEMAND RE WHM WATTHOUR METER WIPA WASTE ISOPROPYL ALCO WJ WELDED JOINT WL WATER LEVEL WL WATER MAIN WM WATTMETER WNBA WASTE N. BUTYL ACETA WNC WASTE NON—CHLORINAT WOAS WASTE OXYGEN ACTIVAT WP WELDED PIPE WP WORKING POINT WPG WATER SURFACE OR WA WSD WASHWATER DRAIN WSEL WATER SURFACE ELEVA WSH WASHWATER WSL WASTE ACTIVATED SLUD WSV WALL SLEEVE WT WT WTHPRF WEATHERPROOF WTP WASTE ACTIVATED SLUD WSV WALL SLEEVE WT WT WEIGHT WTHPRF WEATHERPROOF WTP WATER TREATMENT PLAI WW WASTEWATER WWB WET WEATHER STORAGE WWF WELDED WIRE FABRIC WWP WASTEWATER WWB WET WEATHER PUMP WWTP WASTEWATER TREATMENT WX WASTEWATER TRANSFORMER XP YARD YARD YARD YARD YARD YARD YARD YEAR	CORDER OHOL  ATE TED TED SLUDGE  ATERSTOP TION OGE METER OGE PUMPS SIGNATION  NT E/EQUALIZATION BASIN  T PLANT
Imsmith-az02-pw.bentley.com:PW_EXT\2048\248929\04 Design Services NM_I CDM SMITH ALL RIGHTS RESERVED.  E OF DOCUMENTS: THESE DOCUMENTS AND DESIGNS PROVIDE  B OS 33 33 33 33 33 33 33 33 33 33 33 33 33	CABINET COMPRESSED AIR, DRIED CAPACITY COAGULANT AID POLYMER (CONCENTRATED) COAGULANT AID POLYMER (DILUTED) CARPET CABLE TV CATCH BASIN CIRCUIT BREAKER CLOSED LOOP COOLING SYSTEM COOLING COIL, CONTROL CONDUIT CENTRAL CONTROL CONSOLE CHLORINE CYLINDER SCALE COUNTER CLOCKWISE CONDENSATE DRAIN CLARIFIER DRIVE MECHANISMS CEMENT CENTRIFUGAL COMPRESSIBLE FILLER	DIR DISCH DISP DIV DIW DL DN DO DO DO DOI DP DR DR DR DRW DSCL DT DV DW DWG DWL DWTR	DIRECTION DISCHARGE DISPENSER DIVISION DEIONIZED WATER DEAD LOAD DOWN DISSOLVED OXYGEN DITTO DOOR INTERLOCK DAMPROOFING DRAIN DRIVE DECANT RETURN WATER DEWATERED SLUDGE CAKE DRAIN TANK DIAPHRAGM VALVE DISTILLED WATER DRAWING DOWEL DEWATER(ED)  DES  DRA  SHE CRO APP	FSC FERRIC SULFATE (CONCENTRATED)  FSD FERRIC SULFATE (DILUTED)  FT2 SQUARE FEET  FT FEET/FOOT  FTG FOOTING/FITTING  FTR FINNED TUBE RADIATION  FTW FILTER TO WASTE  G NATURAL GAS  GA GAGE  GALV GALVANIZED  GALVS GALVANIZED STEEL  GALVSP GALVANIZED STEEL PIPE  GAS GAS LINE  GC GROOVED COUPLING (SHOULDERED ENDS)  GCR GRIT CONCENTRATOR  GEC GROUNDING ELECTRODE CONDUCT  GEN GENERATOR  GFI GROUND FAULT INTERRUPTER  GI GALVANIZED IRON  GL GLASS  GLB GLASS BLOCK  GND GROUND  GOV GLOBE VALVE   SIGNED BY:  A. BROWER  AWN BY:  S. STEWART  DECEMBER 2021  TE:  DECEMBER 2021  TEE:  DECEMBER 2021  TEET CHK'D BY:  DECEMBER 2021  TEET CHICATOR  GET GROUND TRON  GESTAND  GESTAN	LLV LONG LEG VERTICAL LNTL LINTEL LOC LOCATION/LOCATED LONG LONGITUDINAL LP LIGHT POLE LP LOW POINT LP LOW PRESSURE LPA LOW PRESSURE AIR LPNL LIGHTING PANEL LPV LUBRICATED PLUG VALY LR LONG RADIUS LS LIFT STATION LSM LOW SERVICE MAIN LSYS LIME SYSTEM LT LEFT LT LIGHT (S) LV LIME VENT LVG LEAVING LW LIGHTWEIGHT LWA LOW WATER ALARM LWL LOW WATER TEMPE  , SUITE 1-200	PE PEFL PEP PEFF PERIM PF PERIM PF PF PFM PGA PGC PH PH PHC PHD PHW PI PINF PIP PJF PL PL PL PL CITY	PLAIN END PLANT EFFLUENT PRIMARY EFFLUENT PLANT EFFLUENT PUMP PERFORATED PERIMETER PHENOL—FORMALDEHYDE POWER FACTOR POWER FACTOR METER PURGE AIR (LIME SILOS) PISTA GRIT CHAMBERS HYDROGEN ION CONCENTRATION PHASE PHOSPHATE (CONCENTRATED) PHOSPHATE (DILUTED) PROTECTED HOT WATER POINT OF INTERSECTION PRIMARY INFLUENT POLYETHYLENE PIPE PREMOLDED JOINT FILLER PILOT LIGHT PLATE PLATE DESIGNATION  TOF GEORGETOWN, TEXAS  SOUTH LAKE R TREATMENT PLA	RS RAW SEWAGE RSL RAW SLUDGE RSM RETURN ACTIVATED RSP RETURN ACTIVATED RST RIGID STEEL RT RIGHT RT RUBBER TILE RT RUNNING TIME MET RTU REMOTE THERMAL RVNR REDUCE VOLTAGE RW RAW WATER RWL RAIN WATER LEADE  S SIGN S STEEL S—SHAPE D SO2G SULFUR DIOXIDE ( SO2S SULFUR DIOXIDE S SA SUPPLY AIR SAC SULFURIC ACID (CO SAN SANITARY SAT SUSPENDED ACOUS SB SEAMLESS BASE	SLUDGE PUMPS TOIL TOP- TOS ER JUNIT NON-REVERSING TPR TR TR TR TRN TRN TRN ESIGNATION TS ESIGNATION TOS OULTION TUB ONCENTRATED) TV TWA: TICAL TILE TYP	TELEMETER OR TIME  TOP OF BERM/BANK  TOP OF CURB/CONCRETE  TOILET  TO TOPPING  TOP OF SLAB  TOP OF WALL  TOP OF WALL  THICKENED OXIDIZED SLUDGE  TURNING POINT  THERMOPLASTIC REINFORCED PIPE  THICKENED PRIMARY SLUDGE  TRIANGULATION POINT  TRANSITION  TRANSITION  TRANSVERSE  STRUCTURAL TUBING (STEEL UNLESS NOTED)  TOP OF SLAB OR THICKENED SLUDGE	PROJECT FILE NAM	ANDREW BROWER  118931  (CENSE)  O/U/101  NO. 2048-248929

ERVICE ABBREVIATION	DESCRIPTION	PIPE MATERIAL	SPEC REFERENCE	ALTERNATE ALLOWED PIPE A MATERIAL BURIED (DIVISION 33, C- A	REFERENCE AND M-SHEETS)	OPERATING PRESSURE (PSIG)	TEST PRESSURE (PSIG)	MIN/MAX TEMPERATURE (F)	NOTES
RW	TRANSMISSION AND VAULTS	DUCTILE IRON	W1	NONE	N/A	75	112.5	50/77	
FLW	BENEATH FILTER GALLERY	DUCTILE IRON	W1	CARBON STEEL	330524.23	10	15	50/77	
FLW	TO DISINFECTION BASIN AND VAULTS	DUCTILE IRON	W1	NONE		10	15	50/77	
FINW	TRANSMISSION	DUCTILE IRON	W1	NONE		210	315	50/77	
FINW	HSPS PUMP STATION HEADER AND VAULTS	DUCTILE IRON	W1	NONE		210	315	50/77	
FINW	TPS DISCHARGE TO CLEARWELL	DUCTILE IRON	W1	NONE		20	30	50/77	
FINW	CLEARWELL TO HSPS	DUCTILE IRON	W1	NONE		20	30	50/77	
BWW	PUMP STATION TO FILTER GALLERY	DUCTILE IRON	W1	NONE		20	30	50/77	
BWW	PUMP STATION HEADER	DUCTILE IRON	W1	NONE		20	30	50/77	
14/014/	FROM BACKWASH GULLET TO WASHWATER	D. 10711 5 1D 0 11	14/4			10	4-	F0/77	
WBW	COLLECTION BOX	DUCTILE IRON	W1	NONE		10	15	50/77	
RCW	FROM WASHWATER COLLECTION BOX	DUCTILE IRON	W1	NONE		20	30	50/77	
RCW	PUMPED FROM RECYCLE PS	DUCTILE IRON	W1	PVC AWWA C900	W2	30	45	50/77	
DR	BENEATH STRUCTURES	DUCTILE IRON	W1	NONE		10	15	50/77	
DR	PROCESS, >14"	DUCTILE IRON	W1	PVC AWWA C900	W2	10	15	50/77	
DR	PROCESS, 4-12"	DUCTILE IRON	W1	PVC AWWA C900	W2	10	15	50/77	
DR	<4"	PVC SCH 80	400531	NONE		10	15	50/77	
DR	FOUNDATION DRAINS	PVC AWWA C900	W2	NONE		10	15	50/77	
SL	FROM SED BASINS TO SLUDGE BOXES	DUCTILE IRON	W1	NONE		20	30	50/77	
SL	12" FROM SLUDGE BOXES TO SLUDGE PS	DUCTILE IRON	W1	PVC AWWA C900	W2	20	30	50/77	
SL	PUMPED FROM SLUDGE PS TO GT	DUCTILE IRON	W1	NONE		20	30	50/77	
TSL		DUCTILE IRON	W1	NONE		40	60	50/77	
SUPN		DUCTILE IRON	W1	NONE		10	15	50/77	
PPW	4-12"	DUCTILE IRON	W1	PVC AWWA C900	W2	70	105	50/77	
PPW	<4"	HDPE	330533.23	NONE		70	105	50/77	
PW	4-12"	DUCTILE IRON	W1	PVC AWWA C900	W2	70	105	50/77	
PW	<4"	HDPE	330533.23	NONE		70	105	50/77	
SHC		DUAL CONTAINED	400531	NONE		30	45	50/77	SEE NOTE 4
LAS		DUAL CONTAINED	400531	NONE		30	45	50/77	SEE NOTE 4
ALC		DUAL CONTAINED	400531	NONE		60	90	50/77	SEE NOTE 4
POLD		DUAL CONTAINED	400531	NONE		60	90	50/77	SEE NOTE 4
SPC		DUAL CONTAINED	400531	NONE		110	165	50/77	SEE NOTE 4
CION		DOUBLE CONTAINED	400531	NONE		70	105	50/77	SEE NOTE 4
SAN		PVC AWWA C900	W2	PVC ASTM D3034 SDR 26	WW2	10	15	50/77	322110124
FLT	PUMPED FROM FILTRATE LS TO SANITARY	DUCTILE IRON	W1	PVC AWWA C900	W2	20	30	50/77	
SPL	TOWN ED THOM TIETHATE ES TO SAUTAUN	PVC SCH 80	400531	NONE		*	*	50/77	SEE NOTE 8
				ABOVE - GRADE (DIVISION 40,	, C- AND M-SHEETS)				
RW	PUMP HEADER IN VAULT	DUCTILE IRON	400519	NONE		75	112.5	50/77	
RW	UPSTREAM OF INFLUENT BOX	DUCTILE IRON	400519	NONE		100	150	50/77	
FLW	FILTER GALLERY	DUCTILE IRON	400519	CARBON STEEL	400524	10	15	50/77	
FINW	HSPS PUMP STATION HEADER	DUCTILE IRON	400519	NONE		210	315	50/77	
FINW	TPS PUMP STATION HEADER	DUCTILE IRON	400519	NONE		20	30	50/77	
BWW	PUMP STATION HEADER	DUCTILE IRON	400519	NONE		20	30	50/77	
BWW	FILTER GALLERY	DUCTILE IRON	400519	CARBON STEEL	400524	20	30	50/77	
WBW	FILTER GALLERY	DUCTILE IRON	400519	CARBON STEEL	400524	10	15	50/77	
RCW	PUMP STATION HEADER	DUCTILE IRON	400519	NONE		30	45	50/77	
DR	PROCESS, 4-12"	DUCTILE IRON	400519	NONE		10	15	50/77	
DR	<4"	GALVANIZED STEEL	400524	PVC SCH 80	400531	10	15	50/77	SEE NOTE 2
SL		DUCTILE IRON	400519	NONE		20	30	50/77	
SUPN		DUCTILE IRON	400519	NONE		10	15	50/77	
PPW	4-12"	DUCTILE IRON	400519	NONE		70	105	50/77	
PPW	<4"	GALVANIZED STEEL	400524	PVC SCH 80	400531	70	105	50/77	SEE NOTE 2
PW	4-12"	DUCTILE IRON	400519	NONE	<del></del>	70	105	50/77	
PW	<4"	GALVANIZED STEEL	400524	PVC SCH 80	400531	70	105	50/77	SEE NOTE 2
SHC	T**	PVC SCH 80	400531	DUAL CONTAINED	400531	30	45	50/77	SEE NOTES 4 AND
LAS		PVC SCH 80	400531	DUAL CONTAINED	400531	30	45	50/77	SEE NOTES 4 AND
ALC		PVC SCH 80	400531	DUAL CONTAINED	400531	60	90	50/77	SEE NOTES 4 AND
								50/77	
POLD		PVC SCH 80	400531	DUAL CONTAINED	400531	60	90	50/77	SEE NOTES 4 AND
POLC		PVC SCH 80	400531	DUAL CONTAINED	400531	60	90		SEE NOTES 4 AND
SPC		PVC SCH 80	400531	DUAL CONTAINED	400531	110	165	50/77	SEE NOTES 4 AND
CION		PVC SCH 80	400531	NONE		70	105	50/77	SEE NOTES 4 AND
LPA		SST	400523	NONE		10	15	50/250	SEE NOTE 12
FLT	PUMP STATION HEADER	DUCTILE IRON	400519	NONE		20	30	50/77	
SPL		GALVANIZED STEEL	400524	PVC SCH 80, SEE NOTE 2	400531	*	*	50/77	SEE NOTES 2 AND

|--|

- 1. SEE DIVISION 09 FOR PIPE PAINTING AND COATING REQUIREMENTS.
- 2. SEE CITY OF GEORGETOWN STANDARD SPECIFICATION CIP 12 FOR PIPE TESTING REQUIREMENTS.

\H/

- 3. PROVIDE AN INSULATED FLANGE DIELECTRIC ISOLATION KIT AND TRANSITION COUPLING AT EVERY LOCATION WHERE THERE ARE DISSIMILAR METALS DUE TO CONSTRUCTION MATERIAL CHANGE.
- 4. DUAL CONTAINED PVC REFERS TO SCHEDULE 80 PVC CONTAINMENT PIPE WITH PVC TUBING CARRIER. CHEMICAL PIPING SHALL BE DUAL CONTAINED WHERE INSTALLED IN ANY OF THE FOLLOWING LOCATIONS:
- a. BURIED.
   b. ABOVE GRADE OUTSIDE OF CONTAINMENT AREA.
   c. ABOVE 7-ft FROM FINISHED FLOOR IN CONTAINMENT AREA (EXCEPT FOR CHEMICAL FILL PIPE).
- 5. CHEMICAL PIPING DOES NOT REQUIRE DUAL CONTAINMENT IF INSTALLED IN CONTAINMENT AREA BELOW 7-FT FROM FINISHED FLOOR, AND ON CHEMICAL FILL LINES.
- 6. REFER TO PLUMBING DRAWINGS AND SPECIFICATIONS FOR PLUMBING PIPING REQUIREMENTS.
- 7. SEE SECTION 400507 REGARDING PIPE STRESS ANALYSIS AND DELEGATED DESIGN OF PIPE SUPPORT SYSTEMS.
- 8. WHERE A SAMPLE LINE IS CONNECTED TO ANOTHER PROCESS LINE, OPERATING AND TEST PRESSURE TO MATCH THE CONNECTED PROCESS LINE FROM WHICH THE SAMPLE IS TAKEN.
- 9. SEE PIPE SPECIFICATIONS FOR LINING REQUIREMENTS.
- 10. INSULATION AND HEAT TRACE REQUIREMENTS PER DRAWINGS AND SPECIFICATIONS.
- 11. MAXIMUM FLOW VELOCITY IN LPA PIPING IS 4000 FEET PER MINUTE.
- 12. PROVIDE JOINT TYPES AND FITTING TYPES AS INDICATED BELOW UNLESS OTHERWISE SHOWN ON THE DRAWINGS OR SPECIFICATIONS. PROVIDE FLANGED CONNECTIONS WHERE CONNECTING TO FLANGED VALVES OR EQUIPMENT.
- a. BELOW GRADE PIPING: AS INDICATED ON DRAWINGS AND SPECIFICATIONS.
- b. ABOVE GROUND DUCTILE IRON PIPE: PROVIDE FLANGED FITTINGS AND
- c. ABOVE GROUND STAINLESS STEEL PIPE: SEE SECTION 400523.00.
- d. ABOVE GROUND CARBON STEEL PIPE 2-INCHES OR LESS: THREADED JOINTS AND FITTINGS.
- e. ABOVE GROUND CARBON STEEL PIPE GREATER THAN 2-INCHES PROVIDE: FLANGED FITTINGS. WELDED MAINFOLD PIPING IS ACCEPTABLE.
- f. ABOVE GROUND GALVANIZED STEEL PIPE: THREADED FITTINGS AND JOINTS.
- g. ABOVE GROUND PVC PIPE: BELL END PIPE, SOLVENT WELDED.
- 13. DOUBLE CONTAINMENT PIPING REFERS TO PREMANUFACTURED DOUBLE WALLED PIPING. CONTAINED PIPING SHALL BE INSTALLED WHERE THE CION PIPING IS
- a. BURIED
- b. ABOVE GRADE OUTSIDE OF CONTAINMENT AREA

c. IN VAULTS DESIGNED TO DRAIN RAINWATER

4. PIPE SHALL BE PAINTED IN ACCORDANCE WITH TCEQ 290.42".

SARAH A STEWART
SARAH A STEWART
111102 GE
11102 GE
111102 GE
11110

ιώ							
DOCUMENTS:	В	NTP	JBF	AMK	FIELD ORDER NO. 1	DESIGNED BY:	A. BROWE
	Α	1/19/22	JBF	AMK	CONFORMED DRAWINGS	DRAWN BY:	S. RA
	2	11/16/21	JBF	AKM	REVISED PER ADDENDUM NO. 2	SHEET CHK'D BY:_	A. KUMAI
	5	12/17/21	JBF	AKM	REVISED PER ADDENDUM NO. 5		0 07511110
0F	6	1/06/22	JBF	AKM	REVISED PER ADDENDUM NO. 6	CROSS CHK'D BY:	A. BROWE
USE	REV.	DATE	DRWN	CHKD	REMARKS	APPROVED BY:	DECEMBER 202

\A/

CDM Smith	
9430 RESEARCH BLVD., SUITE 1-200	
Austin, TX 78759	
Tel: (512) 346-1100	
TBPE Firm Registration No. F-3043	

CITY OF GEORGETOWN, TEXAS

SOUTH LAKE WATER TREATMENT PLANT PIPE SCHEDULE

PROJECT NO.	2048-24892							
FILE NAME:	G017NFPS.DW							
SHEET NO.								

G-17

## GENERAL NOTES FOR YARD PIPING:

- FIELD VERIFY LOCATION, DEPTH, JOINT LOCATIONS AND TYPE, PIPE MATERIAL AND SIZE OF ALL KNOWN PIPES TO BE CONNECTED TO, CROSSED, ETC., PRIOR TO ORDERING MATERIAL OR DOING ANY NEW PIPE WORK
- 2. PIPELINE MATERIAL SHALL BE IN ACCORDANCE WITH PIPE SCHEDULE ON SHEET G-17.
- 3. ALL YARD PIPING SYSTEMS (EXCEPT GRAVITY DRAINS) SHALL BE RESTRAINED UNLESS OTHERWISE NOTED.
- PIPING THRUST RESTRAINT SHALL BE ACCOMPLISHED USING RESTRAINED JOINTS, RESTRAINED FITTINGS AND VALVES. RESTRAINED DUCTILE IRON PIPE SHALL MEET THE REQUIREMENTS OF SPECIFICATION W1, PARAGRAPH W1.05.E, UNLESS NOTED OTHERWISE. MEGA-LUG SERIES 1100 RESTRAINED JOINTS, OR ENGINEER APPROVED EQUAL, MAY BE USED AT ALL FITTINGS, VALVES. HYDRANTS. AND OTHER APPURTENANCES.
- CONCRETE THRUST BLOCKS MAY BE USED FOR SPECIAL CONDITIONS WHEN APPROVED OR DIRECTED BY THE ENGINEER. REFER TO DETAILS AND NOTES SHOWN ON SHEET CZ-11.
- 6. CONTRACTOR SHALL DESIGN, FURNISH, INSTALL, AND MAINTAIN EXCAVATION SAFETY SYSTEMS AS SPECIFIED IN SECTION CIP11.
- 7. ALL BURIED FITTINGS (VALVES, BENDS, TEES, HYDRANTS, ETC.) SHALL HAVE FACTORY RESTRAINTS, MECHANICAL JOINT OR RESTRAINED PUSH-ON CONNECTIONS.
- 8. ALL PIPELINE STATIONING IS FOR THE PIPELINE ITSELF.
- MINIMUM DISTANCE FROM CENTERLINE OF TAP TO NEAREST JOINT SHALL BE PER PIPE MANUFACTURER'S RECOMMENDATIONS. ADJUST TAP LOCATION AS NECESSARY TO COMPLY. PROVIDE ALL FITTINGS, ETC., TO ADJUST NEW PIPE ALIGNMENT.
- 10. CONTRACTOR SHALL REFER TO E/I DRAWINGS TO COORDINATE ELECTRICAL/INSTRUMENTATION CONDUITS AND DUCTS WITH YARD PIPING. CONTRACTOR SHALL ALSO COORDINATE CHEMICAL PIPING BANKS WITH E/I DUCT BANKS AND YARD PIPING.
- 11. SOIL BORING LOCATIONS ARE SHOWN ON SHEET C-7. THE BORING LOGS ARE INCLUDED IN SPECIFICATION SECTION CIP4 FOR THE CONTRACTOR'S USE. GEOTECHNICAL REPORTS ARE AVAILABLE UPON REQUEST FROM THE OWNER AND THE ENGINEER FOR THE CONTRACTOR'S USE.
- 12. UTILITIES AND PIPES TO BE DISTURBED BY NEW WORK SHALL BE PROTECTED.
- 13. CONTRACTOR SHALL REPAIR ALL PAVEMENT DAMAGED DURING CONSTRUCTION. DAMAGED PAVEMENT SHALL BE SAW CUT AND PATCHED IN A RECTANGULAR SHAPE PERPENDICULAR TO CURBS AND STRUCTURES TO MATCH EXISTING CONDITIONS WHICH EXISTED PRIOR TO CONSTRUCTION. SEE DETAILS ON CZ SHEETS. CURBS AND GUTTERS, ETC., THAT ARE DAMAGED OR NEED TO BE REMOVED AS PART OF TRENCH EXCAVATION SHALL BE SAW CUT AND REPLACED PER CIVIL DETAILS. IF SAW CUT LINE FALLS WITHIN 2 FEET OF CURB OR STRUCTURE, REMOVE AND REPLACE PAVEMENT TO CURB OR STRUCTURE.
- 14. CONTRACTOR SHALL REPAIR FENCING DAMAGED DURING CONSTRUCTION. DAMAGED FENCING SHALL RE REPAIRED TO MATCH EXISTING CONDITIONS PRIOR TO CONSTRUCTION. ANY REMOVED FENCING SHALL BE DISPOSED OF AS WASTE.
- 15. FINISHED GRADES SHALL SLOPE UNIFORMLY, LEAVING NO LOW AREAS TO POND WATER.
- 16. THE REQUIREMENT OF THE OWNER/ENGINEER IS TO HAVE PIPELINES INSTALLED TO THE DEPTHS SHOWN ON THE DRAWINGS. THE FLOWLINE ELEVATIONS AND THE PIPELINE PROFILES SHOWN ON THE DRAWINGS ARE SHOWN TO EMPHASIZE THAT NO DIPS. SAGS, HUMPS, OR OTHER IRREGULARITIES IN VERTICAL ALIGNMENT ARE ACCEPTABLE. THE PROFILES SHOWN ARE THE INTENDED PROFILES CONSIDERING TOPOGRAPHY, EXISTING KNOWN UTILITIES, AND OTHER KNOWN CONDITIONS. VARIANCES FROM PROFILES MAY BE NECESSARY IF OTHER UTILITIES OR OBSTRUCTIONS ARE ENCOUNTERED DURING WORK. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL KNOWN EXISTING UTILITIES PRIOR TO ORDERING MATERIALS AND INSTALLING THE PIPELINE SO THAT CONFLICTS CAN BE AVOIDED AND ACCEPTABLE PROFILES CAN BE ESTABLISHED PRIOR TO INSTALLATION OF THE PIPELINE. IF, FOR ANY REASON, THE PROFILE ELEVATIONS SHOWN OR THE NATURAL GROUND ELEVATIONS AT THE PIPE CENTERLINE WOULD RESULT IN LESS COVER THAN IS SHOWN, THE OWNER/ENGINEER RESERVES THE RIGHT TO MAKE REASONABLE ADJUSTMENTS IN THE PIPE PROFILES TO PROVIDE AN ACCEPTABLE COVER. NO PRICE ADJUSTMENTS WILL BE MADE FOR THESE SITUATIONS.
- 17. UNLESS OTHERWISE NOTED, ALL FLEXIBLE COUPLINGS, FLANGE COUPLING ADAPTERS, ETC., SHALL HAVE HARNESS PER DETAILS ON MZ-7 AND AWWA M11.
- 18. IN SITUATIONS WHERE THE PLANS INDICATE POSSIBLE SPACE CONFLICTS BETWEEN NEW BURIED PIPING AND EXISTING UTILITY PIPING, ELECTRICAL CONDUITS, ETC., INCLUDING LOCATIONS WHERE THE EXISTING PIPING WILL BE WITHIN THE LIMITS OF TRENCHING FOR THE NEW PIPE, THE CONTRACTOR SHALL DO THE FOLLOWING:
  - FIELD LOCATE EXISTING PIPING AND DETERMINE THE ACTUAL EXTENT AND NATURE OF CONFLICT, IF ANY
  - IF CONTRACTOR CAN "WORK AROUND" THE EXISTING PIPING. IN THE ENGINEER'S OPINION. THE EXISTING PIPING SHALL BE SUPPORTED AND PROTECTED AND KEPT IN SERVICE AS SPECIFIED ELSEWHERE
  - IF THERE IS AN UNWORKABLE CONFLICT, IN THE ENGINEER'S OPINION, THE CONTRACTOR SHALL PROPOSE A SOLUTION ACCEPTABLE TO THE ENGINEER AND ADJUST OR REROUTE THE NEW OR EXISTING PIPE AS NECESSARY TO ELIMINATE THE CONFLICT
  - THIS WORK WILL BE CONSIDERED TO BE PART OF THE BASIC CONTRACT WORK AND NO ADDITIONAL PAYMENT WILL BE MADE FOR ADJUSTMENTS/REROUTES FOR EXISTING PIPING SHOWN ON THE PLANS.
  - IN SITUATIONS SIMILAR TO THE ABOVE, BUT WHERE THE DRAWINGS DO NOT INDICATE A CONFLICT, SUCH AS IN THE CASE OF AN EXISTING LINE NOT SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL FOLLOW THE SAME PROCEDURE AS ABOVE. UNDER THIS SITUATION, PAYMENT WILL BE MADE TO THE CONTRACTOR IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- 20. ALL PROPOSED AND EXISTING PIPING CROSSINGS MAY NOT BE SHOWN ON PROFILE SHEETS. REFER TO PLAN SHEETS FOR LOCATIONS OF ALL PIPING CROSSINGS.
- 21. REFER TO VALVE SCHEDULE IN SECTION 400551 FOR VALVE OPERATOR REQUIREMENTS (MANUAL VERSUS MOTORIZED, ETC)
- 22. AT LOCATIONS WHERE A BUTTERFLY VALVE IS SHOWN TO BE INSTALLED NEXT TO A TEE, CROSS, ETC., THE BFV SHALL BE INSTALLED FAR ENOUGH AWAY FROM THE FITTING OR PLUG THAT THE BFV DISC DOES NOT EXTEND TO WITHIN 12 INCHES OF THE FITTING'S MAIN FLOWSTREAM OR WITHIN 12 INCHES OF THE PLUG WHEN THE BFV IS IN THE FULL-OPEN POSITION. CONTRACTOR SHALL FURNISH AND INSTALL SPOOL PIECES AS NECESSARY TO PROPERLY LOCATE THE BFV AWAY FROM THE FITTING OR PLUG AS SPECIFIED HEREIN.
- 23. YARD PIPING PROFILES ARE SET BY FLOWLINE (INVERT) ELEVATIONS. PROCESS MECHANICAL PIPING PROFILES/ELEVATIONS ARE GENERALLY SET BY PIPE CENTERLINE ELEVATIONS. WHERE YARD PIPING AND PROCESS MECHANICAL PIPING CONNECT. THE CONTRACTOR SHALL COORDINATE THE INTERFACE CONNECTION PROCESS SO THAT THERE WILL BE NO MISCONNECTS REQUIRING ADDITIONAL FITTINGS, ETC.
- 24. ALL YARD PIPELINES WITH LESS THAN 3 FEET OF COVER AND ALL CHEMICAL LINES IN THE YARD SHALL BE CONCRETE ENCASED BELOW THE ROAD PAVEMENT IN ACCORDANCE WITH DETAILS B AND C ON SHEET CZ-2 AND SIMILAR TO DETAIL A ON SHEET EZ-1, AS APPLICABLE.
- 25. CONTRACTOR SHALL INSTALL TRACER WIRE AND ASSOCIATED TEST STATIONS FOR ALL YARD PIPELINES, INCLUDING THE RAW WATER LINE FROM THE LAKE TO THE WATER TREATMENT PLANT, IN ACCORDANCE WITH THE CITY STANDARD DESIGN DETAILS.
- 26. PERFORM GEOPHYSICAL INVESTIGATION ACCORDING TO SECTION 31 20 00 EARTHWORK PRIOR TO BACKFILLING ANY FOUNDATION EXCAVATION.
- 27. FOR RAW WATER, ALL COMBINATION AIR VALVES SHALL BE SLOW-CLOSING, NON-SLAM TYPE (CAV2).

#### Construction General Permit TPDES General Permit TXR150000

The SWP3 must include, at a minimum, the information described in this section. 1. A site or project description, which includes the following information: (a) a description of the nature of the construction activity;

(c) a description of the intended schedule or sequence of activities that will disturb

for major portions of the site;

(d) the total number of acres of the entire property and the total number of acres construction activities will occur, including off—site material storage areas, overburden

and stockpiles of dirt, and borrow areas that are authorized under the permittee's

(f) a map showing the general location of the site (e.g. a portion of a city or county map);

water body or a municipal separate storm sewer system; and

(b) a list of potential pollutants and their sources;

(g) a detailed site map (or maps) indicating the following: i) drainage patterns and approximate slopes anticipated after major grading activities;

(ii) areas where soil disturbance will occur; (iii) locations of all major structural controls either planned or in place;

(e) data describing the soil or the quality of any discharge from the site;

(iv) locations where temporary or permanent stabilization practices are expected to be

(v) locations of construction support activities, including off—site activities, that are authorized under the permittee's NOI, including material, waste, borrow, fill, or equipment storage areas;

(vi) surface waters (including wetlands) either at, adjacent, or in close proximity to the site: (vii) locations where storm water discharges from the site directly to a surface

(viii) vehicle wash areas. . Where the amount of information required to be included on the map would result in a single map being difficult to read and interpret, the operator shall develop a series of maps that collectively include the required information.

(h) the location and description of support activities authorized under the permittee's NOI, including asphalt plants, concrete plants, and other activities providing support to the construction site that is authorized under this general permit;

(i) the name of receiving waters at or near the site that may be disturbed or that

receive discharges from disturbed areas of the project; (j) a copy of this TPDES general permit, and

(k) the notice of intent (NOI) and acknowledgement certificate for primary operators of large construction sites, and the site notice for small construction sites and for secondary operators of large construction sites.

2. A description of the best management practices (BMPs) that will be used to minimize pollution in runoff.

The description must identify the general timing or sequence for implementation. At a minimum, the description must include the following components: (a) General Requirements

(i) Erosion and sediment controls must be designed to retain sediment on—site to the extent practicable with consideration for local topography, soil type, and rainfall. (ii) Control measures must be properly selected, installed, and maintained

according to the manufacturer's or designer's specifications. (iii) Controls must be developed to minimize the offsite transport of litter, construction debris, and construction materials.

(b) Erosion Control and Stabilization Practices

The SWP3 must include a description of temporary and permanent erosion control and stabilization practices for the site, including a schedule of when the practices will be implemented. Site plans should ensure that existing vegetation is preserved where it is possible.

(i) Erosion control and stabilization practices may include but are not limited to: establishment of temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of existing trees and vegetation, slope texturing, temporary velocity dissipation devices, flow

diversion mechanisms, and other similar measures. (ii) The following records must be maintained and either attached to or referenced in the SWP3, and made readily available upon request to the parties listed in Part III.D.1

of this general permit: (A) the dates when major grading activities occur;

(B) the dates when construction activities temporarily or permanently

cease on a portion of the site; and

(C) the dates when stabilization measures are initiated. (iii) Erosion control and stabilization measures must be initiated as soon as practicable in portions of the site where construction activities have temporarily ceased. Stabilization measures that provide a protective cover

must be initiated as soon as practicable in portions of the site where construction activities have permanently ceased. Except as provided in (A) through (D) below, these measures must be initiated no more than 14 days

after the construction activity in that portion of the site has temporarily or permanently ceased.

#### Texas Commission on Environmental Quality Water Pollution Abatement Plan General Construction Notes

- 1. Written construction notification must be given to the appropriate TCEQ regional office no later than 48 hours prior to commencement of the regulated activity. Information must include the date on which the regulated activity will commence, the name of the approved plan for the regulated activity, and the name of the prime contractor and the name and telephone number of the contact person.
- 2. All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on—site copies of the approved plan and approval letter.
- 3. If any sensitive feature is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. The regulated activities near the sensitive feature may not proceed until the TCEQ has reviewed and approved the methods proposed to protect the sensitive feature and the Edwards Aquifer from any potentially adverse impacts to water quality.
- 4. No temporary aboveground hydrocarbon and hazardous substance storage tank system is installed within 150 feet of a domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 5. Prior to commencement of construction, all temporary erosion and sedimentation (E&S) control measures must be properly selected, installed, and maintained in accordance with the manufacturers specifications and good engineering practices. Controls specified in the temporary storm water section of the approved Edwards Aquifer Protection Plan are required during construction. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. The controls must remain in place until disturbed areas are revegetated and the areas have become permanently stabilized.
- 6. If sediment escapes the construction site, off—site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 7. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake must be provided that can indicate when the sediment occupies 50% of the basin volume.
- 8. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
- 9. All spoils (excavated material) generated from the project site must be stored on—site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the other site.
- 10. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporary or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.
- 11. The following records shall be maintained and made available to the TCEQ upon request: the dates when major grading activities occur; the dates when construction activities temporarily or permanently cease on a portion of the site; and the dates when stabilization measures are initiated.
- 12. The holder of any approved Edward Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
- A. any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures:
- B. any change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
- C. any development of land previously identified as undeveloped in the original water pollution abatement plan.

Austin Regional Office 12100 Park 35 Circle Austin, Texas 78753 Phone (512) 239-6731

Fax (512) 239-4390


THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

#### RESTRAINED JOINT SCHEDULE BEND ANGLE OR FITTING MINIMUM RESTRAINT LENGTH (FT) @ 4.0 FT BURIAL DEPTH FOR DI DESCRIPTION 150 PSI TEST PRESSURE 11.25° - 42" HORIZONTAL BEND 10 22.50° - 42" HORIZONTAL BEND 45.00° - 42" HORIZONTAL BEND 42 90.00° - 42" HORIZONTAL BEND 102 UPWARD DOWNWARD 11.25° - 42" VERTICAL BEND 10 45 22.50° - 42" VERTICAL BEND 21 91 20 DEAD END OR VALVE, 42" 456

RAW WATER	RESTRAINED
PIPE SE	CTIONS
STARTING	ENDING
STATION	STATION
0+00.00	0+86.57
7+56.57	7+96.57
9+45.06	9+85.06
11+05.06	11+45.06
16+14.36	17+30.45
20+34.36	20+74.36
22+40.52	24+42.74
25+42.74	25+82.74
26+84.92	28+73.99
34+23.00	WTP

# **THRUST RESTRAINT NOTES:**

- 1. THE DISTANCES SHOWN ABOVE INDICATE THE MINIMUM REQUIRED RESTRAINED LENGTHS FOR THE FINISHED INSTALLATION. ADDITIONAL RESTRAINTS ARE REQUIRED IF TEMPORARY PLUGS OR OTHER FITTINGS ARE USED FOR PIPELINE TESTING. NO SEPARATE PAY.
- 2. SEGMENTS OF PIPE IN VAULTS OR IN CASING PIPE DO NOT COUNT TOWARD THE REQUIRED RESTRAINED LENGTH.
- 3. ALL FITTINGS, VALVES, HYDRANTS, AND OTHER APPURTENANCES SHALL BE RESTRAINED.
- 4. THE END OF THE LINE SHALL BE RESTRAINED A MINIMUM DISTANCE EQUAL TO A DEAD
- 5. VALVE LOCATIONS SHALL BE RESTRAINED IN BOTH DIRECTIONS A MINIMUM DISTANCE EQUAL TO A DEAD END.
- 6. THE PRIMARY LENGTHS SHOWN ABOVE ARE BASED ON POLYETHYLENE ENCASED DUCTILE IRON PIPE WITH FOUR FEET OF COVER AND A FACTOR OF SAFETY OF 2.0 AT A PRESSURE OF 150 PSI.
- 7. FOR ANY GIVEN PIPE MATERIAL, THE CONTRACTOR MAY PROPOSE ALTERNATE RESTRAINED LENGTHS FOR THE ENGINEER'S CONSIDERATION BY FILING A WRITTEN REQUEST PREPARED BY THE PIPE MANUFACTURER AND SUPPORTED BY DETAILED CALCULATIONS PREPARED AND SEALED BY A LICENSED ENGINEER. ALL SUCH CALCULATIONS SHALL BE BASED ON THE APPLICABLE TEST PRESSURE AND A FACTOR OF SAFETY OF 2.0.



Ś							
Ĭ Z						DESIGNED BY:	A. KARAMALEGOS
DOCUMENT						DRAWN BY:	D. SANDEFUR
000						SHEET CHK'D BY:_	A. BROWER
0F [	Α	1/19/22	RSM	AMK	CONFORMED DRAWINGS	CROSS CHK'D BY:_	A. RHAMES
	2	11/16/21	DWS	SAS	ADDENDUM No 2	APPROVED BY:	A. KARAMALEGOS
EUSE	REV.	DATE	DRWN	CHKD	REMARKS	DATF:	DECEMBER 202

9430 RESEARCH BLVD., SUITE 1-200 Austin, TX 78759 Tel: (512) 346-1100

TBPE Firm Registration No. F-3043


SOUTH LAKE WATER TREATMENT PLANT

CITY OF GEORGETOWN, TEXAS

GENERAL CIVIL NOTES

PROJECT NO. 2048—24892 FILE NAME: C001YPN SHEET NO.

**し-** |




NOTES: COORDINATES ARE SURFACE VALUES BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, NAD 83, CENTRAL ZONE 4203. TO CONVERT COORDINATES AND DISTANCES TO GRID VALUES MULTIPLY BY A COMBINED SURFACE ADJUSTMENT FACTOR OF 0.9998673234. ELEVATIONS REPORTED ARE ORTHOMETRIC HEIGHTS BASED ON NAVD 88. EXISTING ROUND ROCK PERMANENT EASEMENT CONTROL LIST: 10217189.22 3113783.72 847.17 10218076.34 3115425.47 803.90 MON-CORR105A-BM TBM-A-SQ-CUT-LP-LVL
TBM-B-SQCUT-LVL
TBM-D-SQCUT-LVL
TBM-E-CGS-LVL 10217753.51 3114600.95 10404 


 10857
 10217595.61
 3112984.59
 892.50


 20043
 10217197.51
 3112522.41
 912.32


 RAW WATER PUMP STATION— ELECTRICAL BUILDING AND CHEMICAL BUILDING SITE MON-CORR105A-BM EL=847.17' SOUTH LAKE WATER TREATMENT PLANT-CONTRACTOR -PERMANENT SHARED LAYDOWN AREA **EASEMENT** EXISTING BCRUA PERMANENT EASEMENT EXISTING ROUND ROCK-PERMANENT EASEMENT COTTON GIN SPINDLE IN POWER POLE LAKE GEORGETOWN EL=912.32' CONSTRUCTION EASEMENT 42" RAW WATER LINE TEMPORARY CONSTRUCTION EASEMENT PERMANENT SHARED EASEMENT PERMANENT EASEMENT EXISTING BCRUA-PERMANENT EASEMENT 10404 TBM "B"
SQUARE CUT ON
CONCRETE COLLAR
OF MANHOLE
EL=824.56' CURB AT NOSE OF ISLAND EL=892.50' TBM "A"
SQUARE CUT IN
LIGHT POLE BASE
EL=803.90' LAKE GEORGETOWN PROJECT NO. CITY OF GEORGETOWN, TEXAS C008RWF D. SANDEFUR FILE NAME: RAW WATER A. KARAMALEGOS SHEET NO. SOUTH LAKE OVERALL SITE LAYOUT, C-8 WATER TREATMENT PLANT 9430 RESEARCH BLVD., SUITE 1-200 Austin, TX 78759 Tel: (512) 346-1100 TBPE Firm Registration No. F-3043 A. HINDS CONTROL AND BORING PLAN REMARKS


C:\cdmext\david@k2partners.com\d0489110\C008RWPL.dwg, C-8, 10/22/2021 2:24:16 F sandefurdw, DWG To PDF.












CHEMICAL PIPE VAULT NO. 4 (SIMILAR TO CHEMICAL PIPE VAULT NOS. 1 - 3)

**DETAIL** 1/2" = 1'-0"







1. THE YARD PIPING CHEMICAL SYSTEMS DRAWINGS (SHEET CY-1 AND CY-3) SHOW THE LOCATION OF THE CH VAULTS AS WELL AS THE SIZE AND ROUTING OF THE CHEMICAL FEED LINES. REFER TO SHEET CY-3 AND TO THE CY PROFILE SHEETS FOR THE ELEVATION OF THE CHEMICAL LINES.

\H/

- 2. THE CHEMICAL CONTAINMENT LINES SHALL BE CONTINUOUS BETWEEN VAULTS AND STRUCTURES IN ACCORDANCE WITH THE ELEVATIONS SHOWN ON THE YARD PIPING DRAWINGS. WHERE LOCAL INTERFERENCES OCCUR. THE CHEM PIPES CAN BE ADJUSTED TO MISS THE INTERFERENCE PROVIDED THAT CHEM PIPES REMAIN SELF-DRAINING BETWEEN VAULTS AND STRUCTURES.
- 3. SHALL HAVE A SHUTOFF VALVE AT EACH LOCATION WHERE EACH CHEM PIPE ENTERS AND EXITS THE VAULTS. VALVES SHALL BE BALL VALVES. EXCEPT FOR VALVES ON THE SODIUM HYPOCHLORITE PIPES. THE SODIUM HYPOCHLORITE PIPES SHALL HAVE DIAPHRAGM VALVES.
- 4. PROVIDE CAST IRON, FLUSH, HEAVY DUTY, SPRING-ASSISTED-TO-HOLD-OPEN, H-29 RATED HATCHES, W/ GASKETS AND T-HANDLE OPENER. PROVIDE 2" CLOSE CELL FORM INSIDE MH COVER.
- 5. FOR PRECAST VAULTS:

PROVIDE JOINTS AS NECESSARY FOR FABRICATION AND INSTALLATION. INSTALL NON-SHRINK GROUT OR RAM-NEK COMPOUND OR EQUAL TO MAKE ALL JOINTS WATER TIGHT.

PROVIDE REMOVABLE H-20 RATED CONCRETE OVER. PROVIDE GALV STL LIFTING EYES AT CORNER BALANCE POINTS FOR SLAB REMOVAL.

INSTALL CHEMICAL STORAGE COATING ON THE INTERIOR WALLS AND FLOOR IN ACCORDANCE WITH SPECIFICATION SECTION 099673.33. THE COATING PRODUCT SHALL BE BASED CHEMICAL ASSOCIATED WITH THE SPECIFIC MANHOLE.

n l							
Z I						DESIGNED BY:	A. KARAMALEGOS
OME						DRAWN BY:	D. SANDEFUR
						SHEET CHK'D BY:_	A. RHAMES
_						CROSS CHK'D BY:	A DDOWED
) )	Α	1/19/22	RSM	AMK	CONFORMED DRAWING	APPROVED BY:	A. KARAMALEGOS
JS	REV.	DATE	DRWN	CHKD	REMARKS	DATE:	DECEMBER 2021


CDM Smith 9430 RESEARCH BLVD., SUITE 1-200 Tel: (512) 346-1100 TBPE Firm Registration No. F-3043


CITY OF GEORGETOWN, TEXAS

SOUTH LAKE WATER TREATMENT PLANT

CHEMICAL INJECTION VAULT **DETAIL AND SECTION** 

FILE NAME:





Tel: (512) 346-1100

TBPE Firm Registration No. F-3043

\H/

XREFs: [CDMS\_2234-SouthLake, ANA-S\_TX-REV] Images: []
Last saved by: MESQUITARS Time: 3/17/2022 7:43:30 AM
pw:\lcdmsmith\_a702-pw henfley com:DW FXT/2048/248920\04 Desirn Servi

DATE DRWN CHKD

REMARKS

 $\overline{A}$ 

B

