



# Contributing Zone Plan

---

## Northgate Ranch Phase 3 Section 17

Prepared for: Trinity Oaks Land Partners, LLC

Prepared by: BGE, Inc.

TBPE Registered Firm #: 1046

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.



2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or if not withdrawn the application will be denied and the application fee will be forfeited.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available to you:

- You can withdraw your application, and your fees will be refunded or credited for a resubmittal.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the effected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> Northgate Ranch Phase 3 Section 17					<b>2. Regulated Entity No.:</b>				
<b>3. Customer Name:</b> River Oaks Land Partners II, LLC					<b>4. Customer No.:</b> 605909704				
<b>5. Project Type:</b> (Please circle/check one)	<input checked="" type="radio"/> New	<input type="radio"/> Modification			<input type="radio"/> Extension		<input type="radio"/> Exception		
<b>6. Plan Type:</b> (Please circle/check one)	<input checked="" type="radio"/> WPAP	<input checked="" type="radio"/> CZP	<input type="radio"/> SCS	<input type="radio"/> UST	<input type="radio"/> AST	<input type="radio"/> EXP	<input type="radio"/> EXT	<input type="radio"/> Technical Clarification	<input type="radio"/> Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	<input checked="" type="radio"/> Residential		<input type="radio"/> Non-residential			<b>8. Site (acres):</b>		26.918	
<b>9. Application Fee:</b>	\$4,000		<b>10. Permanent BMP(s):</b>				N/A		
<b>11. SCS (Linear Ft.):</b>			<b>12. AST/UST (No. Tanks):</b>						
<b>13. County:</b>	Williamson		<b>14. Watershed:</b>				North Fork San Gabriel River		

# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	<u>  X  </u>
Region (1 req.)	—	—	<u>  X  </u>
County(ies)	—	—	<u>  X  </u>
Groundwater Conservation District(s)	<u>  </u> Edwards Aquifer Authority <u>  </u> Barton Springs/ Edwards Aquifer <u>  </u> Hays Trinity <u>  </u> Plum Creek	<u>  </u> Barton Springs/ Edwards Aquifer	N/A
City(ies) Jurisdiction	<u>  </u> Austin <u>  </u> Buda <u>  </u> Dripping Springs <u>  </u> Kyle <u>  </u> Mountain City <u>  </u> San Marcos <u>  </u> Wimberley <u>  </u> Woodcreek	<u>  </u> Austin <u>  </u> Bee Cave <u>  </u> Pflugerville <u>  </u> Rollingwood <u>  </u> Round Rock <u>  </u> Sunset Valley <u>  </u> West Lake Hills	<u>  </u> Austin <u>  </u> Cedar Park <u>  </u> Florence <u>  </u> Georgetown <u>  </u> Jerrell <u>  </u> Leander <u>  </u> Liberty Hill <u>  </u> Pflugerville <u>  </u> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<u>  </u> Edwards Aquifer Authority <u>  </u> Trinity-Glen Rose	<u>  </u> Edwards Aquifer Authority	<u>  </u> Kinney	<u>  </u> EAA <u>  </u> Medina	<u>  </u> EAA <u>  </u> Uvalde
City(ies) Jurisdiction	<u>  </u> Castle Hills <u>  </u> Fair Oaks Ranch <u>  </u> Helotes <u>  </u> Hill Country Village <u>  </u> Hollywood Park <u>  </u> San Antonio (SAWS) <u>  </u> Shavano Park	<u>  </u> Bulverde <u>  </u> Fair Oaks Ranch <u>  </u> Garden Ridge <u>  </u> New Braunfels <u>  </u> Schertz	NA	<u>  </u> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Nathan D. Kelly, P.E.

Print Name of Customer/Authorized Agent

Signature of Customer/Authorized Agent

Date

10-10-2022

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# Contributing Zone Plan Application

## Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*


## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Nathan D. Kelly, P.E.

Date: 10-10-2022

Signature of Customer/Agent:



Regulated Entity Name: Northgate Ranch Phase 3 Section 17

## Project Information

1. County: Williamson
2. Stream Basin: North Fork San Gabriel
3. Groundwater Conservation District (if applicable): None
4. Customer (Applicant):

Contact Person: Grant Rollo

Entity: River Oaks Land Partners II, LLC

Mailing Address: 1404 West State Hwy 29, Suite 203

City, State: Liberty Hill, TX

Zip: 78642

Telephone: 512-657-2992

Fax: \_\_\_\_\_

Email Address: grollo@randolphtexas.com

5. Agent/Representative (If any):

Contact Person: Nathan D. Kelly, P.E.

Entity: BGE, Inc.

Mailing Address: 101 West Louis Henna Blvd. Suite 400

City, State: Austin, TX

Zip: 78728

Telephone: 512-879-0437

Fax: \_\_\_\_\_

Email Address: nkelly@bgeinc.com

6. Project Location:

- ☐ The project site is located inside the city limits of \_\_\_\_\_.
- ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.
- ☒ The project site is not located within any city's limits or ETJ.

7. ☒ The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

Approximately 2.5 miles north on CR 214 from Hwy 29 Intersection in Liberty Hill

8. ☒ **Attachment A - Road Map.** A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.

9. ☒ **Attachment B - USGS Quadrangle Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000") is attached. The map(s) clearly show:

- ☒ Project site boundaries.
- ☒ USGS Quadrangle Name(s).

10. ☒ **Attachment C - Project Narrative.** A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:

- ☒ Area of the site
- ☒ Offsite areas
- ☒ Impervious cover
- ☒ Permanent BMP(s)
- ☒ Proposed site use
- ☒ Site history
- ☒ Previous development
- ☒ Area(s) to be demolished

11. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site

- ☐ Existing paved and/or unpaved roads  
☐ Undeveloped (Cleared)  
☒ Undeveloped (Undisturbed/Not cleared)  
☐ Other: \_\_\_\_\_

12. The type of project is:

- ☒ Residential: # of Lots: 21  
☐ Residential: # of Living Unit Equivalents: \_\_\_\_\_  
☐ Commercial  
☐ Industrial  
☐ Other: \_\_\_\_\_

13. Total project area (size of site): 26.918 Acres

Total disturbed area: 23.188 Acres

14. Estimated projected population: 74

15. The amount and type of impervious cover expected after construction is complete is shown below:

**Table 1 - Impervious Cover**

<i><b>Impervious Cover of Proposed Project</b></i>	<i><b>Sq. Ft.</b></i>	<i><b>Sq. Ft./Acre</b></i>	<i><b>Acres</b></i>
Structures/Rooftops	122,000.00	÷ 43,560 =	2.801
Parking	0	÷ 43,560 =	0
Other paved surfaces	69,925.36	÷ 43,560 =	1.605
Total Impervious Cover	191,925.36	÷ 43,560 =	4.406

**Total Impervious Cover  $4.406 \div \text{Total Acreage } 26.918 \times 100 = 16.37\%$  Impervious Cover**

16. ☒ **Attachment D - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. ☐ Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

### ***For Road Projects Only***

***Complete questions 18 - 23 if this application is exclusively for a road project.***

☒ N/A

18. Type of project:

- ☐ TXDOT road project.
- ☐ County road or roads built to county specifications.
- ☐ City thoroughfare or roads to be dedicated to a municipality.
- ☐ Street or road providing access to private driveways.

19. Type of pavement or road surface to be used:

- ☐ Concrete
- ☐ Asphaltic concrete pavement
- ☐ Other: \_\_\_\_\_

20. Right of Way (R.O.W.):

Length of R.O.W.: \_\_\_\_\_ feet.

Width of R.O.W.: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

21. Pavement Area:

Length of pavement area: \_\_\_\_\_ feet.

Width of pavement area: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

Pavement area \_\_\_\_\_ acres  $\div$  R.O.W. area \_\_\_\_\_ acres  $\times 100 = \text{_____ \%}$  impervious cover.

22. ☐ A rest stop will be included in this project.

☐ A rest stop will not be included in this project.

23. ☐ Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

***Stormwater to be generated by the Proposed Project***

24. ☒ **Attachment E - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

***Wastewater to be generated by the Proposed Project***

25. ☐ Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

☒ N/A

26. Wastewater will be disposed of by:

☐ On-Site Sewage Facility (OSSF/Septic Tank):

☐ **Attachment F - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

☐ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

☒ Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the Northgate Ranch Phase 1 WWTP (name) Treatment Plant. The treatment facility is:

☒ Existing.

☐ Proposed.

☐ N/A

### ***Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons***

***Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.***

☒ N/A

27. Tanks and substance stored:

**Table 2 - Tanks and Substance Storage**

<b><i>AST Number</i></b>	<b><i>Size (Gallons)</i></b>	<b><i>Substance to be Stored</i></b>	<b><i>Tank Material</i></b>
1			
2			
3			
4			
5			

**Total x 1.5 = \_\_\_\_\_ Gallons**

28. ☐ The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than

5 of 11



one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

- ☐ **Attachment G - Alternative Secondary Containment Methods.** Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

**Table 3 - Secondary Containment**

<i>Length (L)(Ft.)</i>	<i>Width(W)(Ft.)</i>	<i>Height (H)(Ft.)</i>	<i>L x W x H = (Ft3)</i>	<i>Gallons</i>

**Total: \_\_\_\_\_ Gallons**

30. Piping:

- ☐ All piping, hoses, and dispensers will be located inside the containment structure.
- ☐ Some of the piping to dispensers or equipment will extend outside the containment structure.
- ☐ The piping will be aboveground
- ☐ The piping will be underground

31. ☐ The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of: \_\_\_\_\_.

32. ☐ **Attachment H - AST Containment Structure Drawings.** A scaled drawing of the containment structure is attached that shows the following:

- ☐ Interior dimensions (length, width, depth and wall and floor thickness).
- ☐ Internal drainage to a point convenient for the collection of any spillage.
- ☐ Tanks clearly labeled
- ☐ Piping clearly labeled
- ☐ Dispenser clearly labeled

33. ☐ Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

- ☐ In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.

- ☐ In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

## **Site Plan Requirements**

**Items 34 - 46 must be included on the Site Plan.**

34. ☒ The Site Plan must have a minimum scale of 1" = 400'.  
Site Plan Scale: 1" = 100'.
35. 100-year floodplain boundaries:
- ☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☒ No part of the project site is located within the 100-year floodplain.  
The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): 48491C0235F, Revised December 20, 2019.
36. ☒ The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
- ☐ The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. ☒ A drainage plan showing all paths of drainage from the site to surface streams.
38. ☒ The drainage patterns and approximate slopes anticipated after major grading activities.
39. ☒ Areas of soil disturbance and areas which will not be disturbed.
40. ☒ Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. ☒ Locations where soil stabilization practices are expected to occur.
42. ☐ Surface waters (including wetlands).  
☒ N/A
43. ☐ Locations where stormwater discharges to surface water.  
☒ There will be no discharges to surface water.
44. ☐ Temporary aboveground storage tank facilities.  
☒ Temporary aboveground storage tank facilities will not be located on this site.

45. ☐ Permanent aboveground storage tank facilities.  
☒ Permanent aboveground storage tank facilities will not be located on this site.
46. ☒ Legal boundaries of the site are shown.

### ***Permanent Best Management Practices (BMPs)***

#### ***Practices and measures that will be used during and after construction is completed.***

47. ☐ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.  
☒ N/A
48. ☐ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.  
☐ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.  
☐ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: \_\_\_\_\_.  
☒ N/A
49. ☐ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.  
☒ N/A
50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.  
☒ The site will be used for low density single-family residential development and has 20% or less impervious cover.  
☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.  
☐ The site will not be used for low density single-family residential development.

51. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

- ☐ **Attachment I - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.

52. ☒ **Attachment J - BMPs for Upgradient Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☐ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

53. ☒ **Attachment K - BMPs for On-site Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.

54. ☐ **Attachment L - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.

☒ N/A

55. ☒ **Attachment M - Construction Plans.** Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

☐ N/A

56. ☐ **Attachment N - Inspection, Maintenance, Repair and Retrofit Plan.** A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:

- ☐ Prepared and certified by the engineer designing the permanent BMPs and measures
- ☐ Signed by the owner or responsible party
- ☐ Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.
- ☐ Contains a discussion of record keeping procedures

☒ N/A

57. ☐ **Attachment O - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.

☒ N/A

58. ☒ **Attachment P - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.

☐ N/A


***Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.***

59. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60. ☒ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development,

or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### ***Administrative Information***

- 61. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. ☒ Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. ☐ The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
- ☒ The Temporary Stormwater Section (TCEQ-0602) is included with the application.



NORTHGATE RANCH PHASE 3 SECTION 17

LOCATION MAP

BROWN & GAY ENGINEERS, INC.  
101 W LOUIS HENNA BLVD, SUITE 400  
AUSTIN, TX 78728 TBPE Registration No.  
F-1046  
TEL: 512-879-0400 www.browngay.com










U.S. DEPARTMENT OF THE INTERIOR  
U.S. GEOLOGICAL SURVEY



LIBERTY HILL QUADRANGLE  
TEXAS  
7.5-MINUTE SERIES



Produced by the United States Geological Survey  
North American Datum of 1983 (NAD83)  
World Geodetic System of 1984 (WGS84) Projection and  
1 000-meter grid: Universal Transverse Mercator, Zone 14R  
10 000-foot ticks: Texas Coordinate System of 1983 (central  
zone)  
This map is not a legal document. Boundaries may be  
generalized for this map scale. Private lands within government  
reservations may not be shown. Obtain permission before  
entering private lands.  
Imagery.....NAIP, July 2014  
Roads.....U.S. Census Bureau, 2014  
Names.....GNIS, 2015  
Hydrography.....National Hydrography Dataset, 2014  
Contours.....National Elevation Dataset, 2004  
Boundaries.....Multiple sources; see metadata file 1972 - 2015  
Wetlands.....FWS National Wetlands Inventory 1977 - 2014



CONTOUR INTERVAL 10 FEET  
NORTH AMERICAN VERTICAL DATUM OF 1988  
This map was produced to conform with the  
National Geospatial Program US Topo Product Standard, 2011.  
A metadata file associated with this product is draft version 0.6.19



ROAD CLASSIFICATION			
Expressway	Local Connector	Local Road	4WD
Secondary Hwy	US Route	State Route	
Ramp			

1	2	3
4	5	6
7	8	

1 Joppa  
2 Ahomet  
3 Florence  
4 Bertram  
5 Leander NE  
6 Travis Peak  
7 Nameless  
8 Leander

LIBERTY HILL, TX  
2016



NSN 7 6 4 3 0 6 0 6 0 6 0 3 1



## Attachment C – Project Narrative

### **Area of the Site**

Northgate Ranch Phase 3 Section 17 is a proposed single-family development that will be developed on a 26.918-acre tract located east of San Gabriel Ranch Road and south of County Road 214 in Williamson County. The tract predominantly drains to the North Fork of the San Gabriel River. The proposed development will convert the previously undeveloped site into a single-family residential subdivision.

### **Offsite Areas**

Runoff from offsite areas contributing to this tract's drainage include upgradient undeveloped land and construction from Northgate Ranch Phase 3 Sections 14-16, all of which are incorporated into drainage capacity calculations.

### **Impervious Cover**

In total, 22.016 acres of the overall 26.918-acre tract will be disturbed by regulated activities (road construction, grading, home construction, and utility installation) and will be accounted for through proposed erosion controls. There is currently no existing impervious cover located within the project boundary. Northgate Ranch Phase 3 Section 15 contains a portion that drains into Section 17, however, impervious cover from Section 15 was accounted for in the approved Contributing Zone Plan for Northgate Ranch Phase 3 Sections 14-16 (approved 06 May 2022) and will not need to be treated in Section 17. In total, 4.406 acres of impervious cover are proposed for Section 17. This impervious cover is comprised of twenty-one (21) proposed single-family residences and the associated street and utility improvements. Note: The overall areas to be disturbed match the overall areas within the limits of construction to be controlled with silt fence and other erosion control measures.

### **Permanent BMPs**

The site's area is 26.918 acres and the proposed development results in 4.406 acres of impervious cover, yielding a 16.37% impervious cover percentage. Due to the proposed impervious cover being less than 20% and the site being a low-density single-family development, permanent BMPs are not required for this project. Captured runoff will ultimately pass through the site via standard storm pipes and culverts, then discharge to naturally existing tributaries of the North Fork San Gabriel River.

### **Proposed Site Use**

The site being considered for this review is a proposed single-family development consisting of twenty-one (21) Single-Family Units and the necessary infrastructure to adequately service these facilities.

### **Site History**

Northgate Ranch Phase 3 Section 17 is located within the Edward's Aquifer Contributing Zone. No proposed development is located within the FEMA 100-yr Floodplain in accordance with Flood Insurance Rate Map (FIRM) Panel No. 48491C0235F, effective date December 20, 2019. Additionally, an engineered 100-year floodplain, per a study by BGE dated September 2022, is shown on all plan sheets.

### **Previous Development & Areas to Be Demolished**

Northgate Ranch Phase 3 Section 17 is undeveloped and has no existing infrastructure in place. Consequently, there is nothing to be demolished within the area of consideration.

## Attachment D – Factors Affecting Surface Water Quality

Multiple factors have the potential of affecting surface water quality during construction. These include: oil, grease, gas, transmission fluids, and/or other vehicular fluids, as well as shifts in sediment that will occur during excavation and fill operations. Upon completion of construction, normal traffic on the site could be responsible for many of these same pollutants, as well as everyday activities, such as car washing and lawn watering.

## Attachment E – Volume and Character of Stormwater

Northgate Ranch Phase 3 Section 17 is exempt from treating stormwater runoff because the site contains less than 20% proposed impervious cover. Onsite runoff and upstream runoff from adjacent properties will be captured in inlets and culverts. This runoff ultimately drains untreated to tributaries of the North Fork San Gabriel River.

The overall proposed drainage area map and associated calculations are included in the construction plans included with this submittal (SHEETS 14-15). This project lies within the North Fork San Gabriel River Detention Exempt Stream Reach as defined by Williamson County and drains directly to three tributaries of the North Fork San Gabriel River. The project is exempt from detention requirements for the various storm events, and for this reason, no existing drainage area map is included.

## Attachment F – Suitability Letter from Authorized Agent

Not applicable to this project.

## Attachment G – Alternative Secondary Containment Methods

Not applicable to this project.

## Attachment H – AST Containment Structure Drawings

Not applicable to this project.

## Attachment I – 20% or Less Impervious Cover Declaration

The site's area is 26.918 acres and the proposed development results in 4.406 acres of impervious cover, yielding a 16.37% impervious cover percentage. Due to the proposed impervious cover being less than 20% and the site being a low-density single-family development, permanent BMPs are not required for this project. The drainage area calculations for this exemption are provided below in Table 1 and Table 2, as well as in the inlet capacity calculations of the attached construction plan set (SHEET 15). Captured runoff will ultimately pass through the site via standard storm pipes and culverts, then discharge to naturally existing tributaries of the North Fork San Gabriel River.

Table 1: Impervious Cover Calculations

	Area IC (SF)	Area IC (AC)
<b>Homes</b>	122,000.00	2.801
<b>Streets</b>	61,202.57	1.405
<b>Other</b>	8,731.79	0.200
<b>Total IC</b>	<b>191,934.36</b>	<b>4.406</b>

Table 2: Impervious Cover Percentage Calculation

ONSITE AREA (AC)	26.918
ONSITE IC (AC)	4.406
<b>% IC</b>	<b>16.37%</b>



## Attachment J – BMPs for Upgradient Stormwater

Upgradient stormwater can be characterized as flowing from adjacent properties which contain either no impervious cover or are being treated by existing BMPs. As no BMPs are required for this project, upgradient runoff will not be treated. The upgradient stormwater is being conveyed through the proposed site via standard storm pipes and culverts to naturally existing tributaries of the North Fork San Gabriel River.

## Attachment K – BMPs for On-Site Stormwater

Not applicable to this project.

## Attachment L – BMPs for Surface Streams

No BMPs are proposed specifically for surface streams. Proposed drainage systems are designed to maintain existing flow patterns.

## Attachment M – Construction Plans

Sheets detailing proposed storm improvements, erosion controls, and all associated calculations are included in the attached construction plans.

## Attachment N – Inspection, Maintenance, Repair, and Retrofit Plan

Not applicable to this project.

## Attachment O – Pilot-Scale Field Testing Plan

Not applicable to this project.

## Attachment P – Measures for Minimizing Surface Stream Contamination

The site will be stabilized using silt fence; all of the stabilization will be installed prior to construction and will be removed after construction has been completed. These methods will minimize any increases in erosion caused by construction activities.

# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Nathan D. Kelly, P.E.

Date: 10-10-2022

Signature of Customer/Agent:



Regulated Entity Name: Northgate Ranch Phase 3 Section 17

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.



- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: One unnamed tributary of the North Fork San Gabriel River

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- ☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- ☒ N/A
12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

## ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

- 20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## Attachment A – Spill Response Action

No spills of hydrocarbons or hazardous substances are expected. However, in the event that such an incidence does occur, the contractor should carefully follow the following TCEQ guidelines:

### **Cleanup:**

1. Clean up leaks and spill immediately.
2. Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
3. Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly.

### **Minor Spills:**

1. Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
2. Use absorbent materials on small spills rather than hosing down or burying the spill.
3. Absorbent materials should be promptly removed and disposed of properly.
4. Follow the practice below for a minor spill:
  - Contain the spread of the spill.
  - Recover spilled materials.
  - Clean the contaminated area and properly dispose of contaminated materials.

### **Semi-Significant Spills:**

Semi-significant spills can still be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities. Spills should be cleaned up immediately, using the following practices:

1. Contain spread of the spill.
2. Notify the project foreman immediately.
3. If the spill occurs on paved or impermeable surfaces, clean up using “dry” methods (absorbent materials, cat litter, and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
4. If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
5. If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

**Significant/Hazardous Spills:**

For highly toxic materials, the Reportable Quantity (RQ) > 25 gallons. For petroleum/hydrocarbon liquids, RQ > 250 gallons (on land) or any amount which creates a “sheen” on water. Only certified Haz-Mat teams will be responsible for handling the material at the site.

For significant or hazardous spills that are in reportable quantities:

1. Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor’s responsibility to have all emergency phone numbers at the construction site. Additionally, in the event of a hazardous material spill, local Williamson County and/or city of Liberty Hill police, fire, and potentially EMS should be contacted in order to initiate the hazardous material response team.
2. For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110, 191, and 302, the contractor should notify the National Response Center at (800) 424-8802.
3. Notification should first be made by telephone and followed up with a written report of which one copy is to be kept on-site in the report binder and one copy is to be provided to the TCEQ.
4. The services of a spill contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
5. Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sherriff’s Office, Fire Department, etc.

More information on spill rules and appropriate responses is available on the TCEQ website at:  
<http://www.tceq.state.tx.us/response/spills.html>

## Attachment B – Potential Sources of Contamination

No particular activity or process during construction of the project is anticipated to present a significant risk of being a potential source of contamination. However, during regular construction operations, several common and minor risks of contamination are anticipated. Should any unforeseen mishaps occur during construction, the contractor shall follow the guidelines set forth in “Attachment A – Spill Response Plan”.

### **Potential sources of sediment to stormwater runoff:**

- Clearing and grubbing
- Grading and excavation
- Vehicle tracking
- Topsoil stripping and stockpiling
- Landscaping

### **Potential pollutants and sources, other than sediment, to stormwater runoff:**

- Combined Staging Area – small fueling, minor equipment maintenance, sanitary facility.
- Materials Storage Area – solvents, adhesives, paving materials, aggregates, trash, etc.
- Construction Activities – paving, concrete pouring
- Concrete washout areas

### **Potential on-site pollutants:**

- Fertilizer
- Concrete
- Glue, adhesives
- Gasoline, diesel fuel, hydraulic fluids, antifreeze
- Sanitary toilets

## Attachment C – Sequence of Major Activities

1. Temporary erosion and sedimentation controls are to be installed as indicated on the approved subdivision construction plans and in accordance with the stormwater pollution prevention plan (SWPPP) that is required to be posted on the site. Install tree protection and initiate tree mitigation measures.
2. The environmental project manager, and/or site supervisor, and/or designated responsible party, and the general contractor will follow the storm water pollution prevention plan (SWPPP) posted on the site. Temporary erosion and sedimentation controls will be revised, if needed, to comply with city inspectors' directives, and revised construction schedule relative to the water quality plan requirements and the erosion and sedimentation plan.
3. Temporary erosion and sedimentation controls will be inspected and maintained in accordance with the storm water pollution prevention plan (SWPPP) posted on the site.
4. A sequence of major construction activities, as well as an estimated area of disturbance for each, is listed below:
  - I. Clearing and grubbing – 23.188 acres
  - II. Grading and excavation for roadway and lots – 23.188 acres
  - III. Excavation for utilities and storm sewer system – 2.287 acres
  - IV. Construction of utilities and storm sewer system – 2.287 acres
  - V. Paving, striping, etc. – 1.509 acres
  - VI. Re-vegetation – 6.956 acres
5. Upon completion of construction and re-vegetation, the design engineer shall submit an engineer's letter of concurrence to the City of Liberty Hill indicating that construction, including re-vegetation, is complete and in substantial conformity with the approved plans. After receiving this letter, a final inspection will be scheduled by the appropriate city inspector.
6. After construction is complete and all disturbed areas have been re-vegetated per plan to at least 90 percent established, remove the temporary erosion and sedimentation controls and complete any necessary final re-vegetation resulting from removal of the controls. Conduct any maintenance and rehabilitation of the permanent BMPs.



## Attachment D – Temporary Best Management Practices and Measures

Prior to the commencement of any construction activity, the contractor shall install silt fence, and construction entrances, per the Erosion and Sedimentation Control Plan. Once inlets are installed, inlet protections shall too be installed. All temporary BMPs are to be installed per TCEQ and local requirements.

As surface water flows from and through disturbed areas, the proposed temporary BMPs will prevent pollution by filtering the increased sediment loads and other pollutant sources (listed in “Attachment B – Potential Sources of Contamination”) prior to any runoff leaving the site. As shown in the attached site plan, silt fence will be utilized downstream of any grading and construction activities to remove debris and sediment from run-off in the area (activities here will primarily involve road grading and storm sewer excavation). Inlet protection will prevent sediment laden runoff from entering the storm sewer system during construction. Concrete washout basins will contain pollutants discharged when concrete trucks are washed out, and stabilized construction entrances will prevent the transport of sediment off-site.

In using the aforementioned treatment methods and maintaining natural drainage patterns downgradient of the proposed site, any flow to naturally occurring sensitive features, both known and unknown, will be maintained.

## Attachment E – Request to Temporarily Seal a Feature

Not applicable to this project.

## Attachment F – Structural Practices

The following temporary BMP structural practices will be employed on the site:

- A. Silt Fence – Used for sediment filtration along the downslope perimeter of portions of the project, as well as to prevent runoff from storage of excavated materials during utility construction. The fence retains sediment primarily by retarding flow and promoting deposition of sediment on the uphill side of the slope. Runoff is filtered as it passes through the geotextile.
- B. Inlet Protection – To be provided around all proposed storm sewer inlets during construction. Locations are indicated on attached site plan. The measures will trap and settle out sediment and debris prior to runoff entering the proposed storm sewer system.
- C. Construction Entrance – Stone pads will be constructed at entrances and exits to the project to prevent off-site transport of sediment by construction vehicles. The pads are a minimum of 50' long and 8" deep. They will be graded to prevent runoff from leaving the site.

## Attachment G – Drainage Area Map

Drainage area maps and associated calculations are shown in the attached construction plans (SHEETS 14 -15).

## Attachment H – Temporary Sediment Pond(s) Plans and Calculations

Not applicable to this project.

## Attachment I – Inspection and Maintenance for BMPs

The inspection and maintenance of temporary BMPs will be made according to TCEQ RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices.

### **Inspection Personnel:**

Inspections shall be conducted by qualified representatives of the contractor acting on behalf of the owner or a designated party, if hired separately by the owner. Each operator must delegate authority to the specifically described position or person performing inspections, as provided by 30 TAC 305.128, as an authorized person for signing reports and performing certain activities requested by the director or required by the TPDES general permit. This delegation of authority must be provided to the director of TCEQ in writing and a copy shall be kept along with the signed effective copy of the SWPPP.

### **Inspection Schedule and Procedures:**

An inspection shall occur weekly and after any rain event.

The authorized party shall inspect all disturbed areas of the site, areas used for storage of materials that exposed to precipitation, structural control measures, and locations where vehicles enter or exit the site.

Disturbed areas and areas used for storage of materials that are exposed to precipitation or within limits of the 1% annual chance (100 year) floodplain must be inspected for evidence of, or the potential for, pollutants entering the runoff from the site. Erosion and sediment control measures identified in the plan must be observed to ensure that they are operating correctly. Observations can be made during wet or dry weather conditions. Where discharge locations or points are accessible, they must be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters. This can be done by inspecting receiving waters to see where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

Based on the results of the inspection, the site description and the pollution prevention measures identified in the plan must be revised as soon as possible after an inspection that reveals inadequacies. The inspection and plan review process must provide for timely implementation of any changes to the plan within 7 calendar days of the inspection.

An inspection report shall be completed, which summarizes the scope of the inspection, name(s) and qualifications of personnel conducting the inspection, the date(s) of the inspection, and major observations relating to the implementation of the SWPPP. Major observations shall include, as a minimum, location of discharges of sediment or other pollutants from the site, location of BMPs that need to be maintained, location of BMPs that failed to operate as designed or proved inadequate for a particular location, and locations where BMPs are needed.

Actions taken as a result of the inspections must be described within, and retained as a part of, the SWPPP. Reports must identify any incidents of non-compliance. Where a report does not identify any incidents of non-compliance, the report must contain a certification that the facility or site is in compliance with the SWPPP and the TPDES general permit. The report must be signed by the authorized representative delegated by the operators in accordance with TAC 305.128.

**Maintenance and Corrective Actions** – Maintenance of erosion control facilities shall consist of the minimum requirements as follows:

- A. In ongoing construction areas inspect erosion control improvements to confirm facilities are in place and operable. Where facilities have been temporarily set aside or damaged due to construction activity, place facilities in service before leaving job site.
- B. If weather forecast predicts possibility of rain, check entire facilities throughout site to ensure that they are in place and operable. If job site weather conditions indicate high probability of rain, make special inspection of erosion control facilities.
- C. After rainfall events, review erosion control facilities as soon as site is accessible. Clean rock berms, construction entrances, and other structural facilities. Determine where additional facilities or alternative techniques are needed to control sediment leaving site.
- D. After portions of site have been seeded, review these areas on regular basis in accordance with project specifications to assure proper watering until grass is established. Re-seed areas where grass is not well-established.
- E. Spills are to be handled as specified by the manufacturer of the product in a timely and safe manner by qualified personnel. The site superintendent will be responsible for coordinating spill prevention and cleanup operations.
- F. Concrete trucks will discharge extra concrete or wash out drum only at an approved location on site. Residual product shall be properly disposed of.
- G. Inspect vehicle entrance and exits for evidence of off-site tracking and correct as needed.
- H. Remove sediment from traps/ponds no later than when the design capacity has been reduced by 50%.
- I. If sediment escapes the site, the contractor, where feasible and where access is available, shall collect and remove sedimentation material by appropriate non-damaging methods. Additionally, the contractor shall correct the condition causing discharges.
- J. If inspections or other information sources reveal a control has been used incorrectly, or that control is performing inadequately, the contractor must replace, correct, or modify the control as soon as practical after discovery of the deficiency.

## Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices

Silt fence will be used during the period of construction near the perimeter of the disturbed area to intercept sediment while allowing water to percolate through. Silt fencing will be installed prior to any site clearing. This silt fence will remain in place until the disturbed area is permanently stabilized. Tree protection fencing will be installed around all protected trees. A stabilized pad of crushed stone will be placed at the point where traffic will be entering and leaving the construction site to eliminate the tracking or flowing of sediment onto public rights-of-way. Once all site grading activities and landscaping plantings have been completed, all disturbed areas and exposed soil will be revegetated as needed. All controls will remain in place until the revegetated areas are permanently stabilized.

Should construction activities be interrupted for a period of at least 4 weeks of non-activity, Contractor shall revegetate all disturbed areas as required for permanent revegetation. Contractor shall keep all temporary BMPs in place until the disturbed areas become permanently stabilized.



**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I Grant Rollo,  
Print Name  
Vice President,  
Title - Owner/President/Other  
of River Oaks Land Partners II, LLC,  
Corporation/Partnership/Entity Name  
have authorized Nathan D. Kelly, P.E  
Print Name of Agent/Engineer  
of BGE, Inc.  
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Grant Rollo  
Applicant's Signature


10/17/22  
Date

THE STATE OF Texas §

County of Williamson §

BEFORE ME, the undersigned authority, on this day personally appeared Grant Rollo known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 17<sup>th</sup> day of October, 2022.



K Miller  
NOTARY PUBLIC  
Kaylee Miller  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 5/3/2026

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Northgate Ranch Phase 3 Section 17

Regulated Entity Location: Approx. 2.5 mi north on CR 214 from Hwy 29 Intersection

Name of Customer: Randolph Texas Development, LLC

Contact Person: Grant Rollo

Phone: (512) 657-2992

Customer Reference Number (if issued): CN 605909704

Regulated Entity Reference Number (if issued): RN \_\_\_\_\_

### Austin Regional Office (3373)

☐ Hays

☐ Travis

☒ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☐ Recharge Zone

☒ Contributing Zone

☐ Transition Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	26.918 Acres	\$ 4,000.00
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature:  10-10-2022

Date: \_\_\_\_\_

## Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

### ***Water Pollution Abatement Plans and Modifications***

#### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

#### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

#### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

#### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150



TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other
<b>2. Customer Reference Number (if issued)</b>	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a>	<b>3. Regulated Entity Reference Number (if issued)</b>
CN 605909704		RN

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)		7/9/2021	
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information		<input type="checkbox"/> Change in Regulated Entity Ownership	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>					
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)				If new Customer, enter previous Customer below:	
				River Oaks Land Partners II, LLC	
<b>7. TX SOS/CPA Filing Number</b>		<b>8. TX State Tax ID</b> (11 digits)		<b>9. Federal Tax ID</b> (9 digits)	
0803693221		32075125701		86-1862961	
<b>10. DUNS Number</b> (if applicable)					
<b>11. Type of Customer:</b>		<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual	
<input type="checkbox"/> Partnership: <input type="checkbox"/> General <input checked="" type="checkbox"/> Limited		<input type="checkbox"/> Sole Proprietorship		<input type="checkbox"/> Other:	
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other					
<b>12. Number of Employees</b>		<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<b>13. Independently Owned and Operated?</b>	
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No					
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input type="checkbox"/> Owner		<input type="checkbox"/> Operator		<input checked="" type="checkbox"/> Owner & Operator	
<input type="checkbox"/> Occupational Licensee		<input type="checkbox"/> Responsible Party		<input type="checkbox"/> Voluntary Cleanup Applicant <input type="checkbox"/> Other:	
<b>15. Mailing Address:</b>					
14001 West State HWY 29 Suite 203					
City		Liberty Hill		State TX ZIP 78642 ZIP + 4	
<b>16. Country Mailing Information</b> (if outside USA)				<b>17. E-Mail Address</b> (if applicable)	
				grollo@randolphtexas.com	
<b>18. Telephone Number</b>		<b>19. Extension or Code</b>		<b>20. Fax Number</b> (if applicable)	
( 512 ) 657-2992				( ) -	

## SECTION III: Regulated Entity Information

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)	
<input checked="" type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information	
<b>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</b>	
<b>22. Regulated Entity Name</b> (Enter name of the site where the regulated action is taking place.)	
Northgate Ranch Phase 3 Sections 17	

23. Street Address of the Regulated Entity: (No PO Boxes)							
	City		State		ZIP		ZIP + 4
24. County	Willamson						

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:	Approx. 2.5 miles north on CR 214 from Hwy 29 intersection										
26. Nearest City	Liberty Hill				State	TX		Nearest ZIP Code	78642		
27. Latitude (N) In Decimal:	30.700982			28. Longitude (W) In Decimal:	-97.891932						
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds						
30	42	3.53	-97	53	30.95						
29. Primary SIC Code (4 digits)	6552		30. Secondary SIC Code (4 digits)			31. Primary NAICS Code (5 or 6 digits)	236117		32. Secondary NAICS Code (5 or 6 digits)		
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)											
Single Family Residential											
34. Mailing Address:	13640 Briarwick Drive										
	Suite 170										
	City	Austin	State	TX	ZIP	78729	ZIP + 4				
35. E-Mail Address:	Nick.McIntyre@perryhomes.com										
36. Telephone Number	( 512 ) 848-1401		37. Extension or Code			38. Fax Number (if applicable)	( ) -				

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

#### SECTION IV: Preparer Information

40. Name:	Nathan D. Kelly, P.E.		41. Title:	Project Manager	
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address		
( 512 ) 879-0400		( ) -	nkelly@bgeinc.com		

#### SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	BGE, Inc.		Job Title:	Project Manager	
Name (In Print):	Nathan D. Kelly, P.E.			Phone:	( 512 ) 879- 0400
Signature:				Date:	10-10-2022



G:\TXC\Projects\Randolph Todd Col\0882-00-Northgate\_Ph3\_Sect7\LD01\_CADD\01\_Shts\0882-C-COVR.dwg Layout COVER Plotted: 10/17/2022 8:08:23 AM

SUMMARY NOTES

OWNER:	ENGINEER:
RIVER OAKS LAND PARTNERS II, LLC. 14001 WEST STATE HWY 29 SUITE 203 LIBERTY HILL, TX 78642 PHONE: 512-657-2992	BGE, INC. 101 WEST LOUIS HENNA BLVD. SUITE 400 AUSTIN, TX 78728 PHONE: 512-879-0400

LEGAL DESCRIPTION:

AW0312 AW0312 - HACKETT, J. SUR., ACRES 55.514

REVIEWED FOR COMPLIANCE WITH WILLIAMSON COUNTY REQUIREMENTS

WILLIAMSON COUNTY	DATE
-------------------	------

GEORGETOWN UTILITY SYSTEMS	DATE
----------------------------	------

WILLIAMSON COUNTY EMERGENCY SERVICE DISTRICT NO. 4	DATE
--	------

NORTH SAN GABRIEL MUD No. 1	DATE
-----------------------------	------

NOTES: REVIEW OF THE PLANS BY THE DISTRICT IS LIMITED TO WATER, WASTEWATER AND DRAINAGE AND DOES NOT INDICATE A REVIEW OF THE ADEQUACY OF THE DESIGN FOR THE FACILITIES. IN APPROVING THESE PLANS, THE DISTRICT MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.

NOTES:

- THIS PROJECT IS LOCATED WITHIN THE NORTH FORK SAN GABRIEL RIVER WATERSHED.
- THIS PROJECT IS LOCATED WITHIN THE EDWARDS AQUIFER CONTRIBUTING ZONE.
- NO PORTION OF THIS PLAN IS ENCROACHED BY SPECIAL FLOOD HAZARD AREAS INUNDATED BY THE 1% ANNUAL CHANCE FLOOD AS IDENTIFIED BY THE U.S. FEDERAL EMERGENCY MANAGEMENT AGENCY BOUNDARY MAP (FLOOD INSURANCE RATE MAP) COMMUNITY PANEL NUMBERS 48491C0235F, EFFECTIVE DATE DECEMBER 20, 2019 FOR WILLIAMSON COUNTY TEXAS.

BENCHMARK

TBM 1 – TEMPORARY BENCHMARK FOR THIS PROJECT IS A " " CHISEL MARK AT THE APPROXIMATE MIDDLE POINT OF THE CONCRETE HEADWALL ON THE EAST SIDE OF THE BOX CULVERTS CROSSING C.R. 214, ON THE WEST SIDE OF THE ESTATES AT NORTHGATE, PHASE 1, SECTION 1, AS RECORDED IN DOC. NO. 2018070591, OFFICIAL PUBLIC RECORDS, WILLIAMSON COUNTY, TEXAS.

ELEVATION 993.74 FEET  
GRID N. 10223889.38  
GRID E. 3057450.22  
NAVD 88 DATUM

TBM 64–60–1 – TEMPORARY BENCHMARK FOR THIS PROJECT IS A "X" CUT ON A CONCRETE CULVERT ON THE SOUTH SIDE OF THE DRIVE ENTRANCE JUST NORTH OF THE SUBJECT SITE ON THE WEST SIDE OF SAN GABRIEL RANCH ROAD, +/- 238' NORTHWEST OF THE MOST NORTHERLY DRIVE ENTRANCE TO THE SUBJECT SITE.

ELEVATION 979.69 FEET  
GRID N. 10228314.19  
GRID E. 3058670.76  
NAVD 88 DATUM

TBM 64–60–2 – TEMPORARY BENCHMARK FOR THIS PROJECT IS A COTTON GIN SPINDLE SET IN POWER POLE ALONG THE SOUTHEASTERLY RIGHT-OF-WAY LINE OF C.R. 214, +/- 129' SOUTHEAST OF THE INTERSECTION OF C.R. 214 AND SAN GABRIEL RANCH ROAD.


ELEVATION 976.22 FEET  
GRID N. 10226653.63  
GRID E. 3059288.51  
NAVD 88 DATUM

CONSTRUCTION PLANS FOR  
NORTHGATE RANCH  
PHASE 3 - SECTION 17  
WILLIAMSON COUNTY, TEXAS

NORTH SAN GABRIEL MUD NO. 1  
PAVING, WATER, WASTEWATER &  
DRAINAGE IMPROVEMENTS

OCTOBER 2022

VICINITY MAP



REVISIONS/CORRECTIONS					
SHEET LIST	DESCRIPTION	DATE	REVISE (R) ADD (A) VOID (V) SHEET NO.'S	ACCEPTED BY	APPROVAL DATE

Sheet List Table	
Sheet Number	Sheet Title
1	COVER
2	NOTES (SHEET 1 OF 2)
3	NOTES (SHEET 2 OF 2)
4	PRELIMINARY PLAT (SHEET 1 OF 5)
5	PRELIMINARY PLAT (SHEET 2 OF 5)
6	PRELIMINARY PLAT (SHEET 3 OF 5)
7	PRELIMINARY PLAT (SHEET 4 OF 5)
8	PRELIMINARY PLAT (SHEET 5 OF 5)
9	EROSION CONTROL PLAN
10	GRADING PLAN
11	RANDOLPH DRIVE (STA. 1+00 TO 9+00)
12	RANDOLPH DRIVE (STA. 9+00 TO END)
13	RANDOLPH COURT (STA. 1+00 TO END)
14	OVERALL STORM & DRAINAGE AREA MAP
15	STORM INLET CAPACITY CALCULATIONS
16	STORM SEWER LINE A (STA. 1+00 TO 5+00)
17	STORM SEWER LINE A (STA. 5+00 TO END)
18	CULVERT 1 & CULVERT 2
19	OVERALL WATER DISTRIBUTION PLAN
20	OVERALL WASTEWATER COLLECTION PLAN
21	WWL A (STA. 1+00 TO 7+00)
22	WWL A (STA. 7+00 TO END)
23	WWL B (STA. 1+00 TO END)
24	LIGHTING, SIGNAGE, & STRIPING PLAN
25	EROSION DETAILS (SHEET 1 OF 2)
26	EROSION DETAILS (SHEET 2 OF 2)
27	DRAINAGE DETAILS (SHEET 1 OF 4)
28	DRAINAGE DETAILS (SHEET 2 OF 4)
29	DRAINAGE DETAILS (SHEET 3 OF 4)
30	DRAINAGE DETAILS (SHEET 4 OF 4)
31	WATER DETAILS (SHEET 1 OF 4)
32	WATER DETAILS (SHEET 2 OF 4)
33	WATER DETAILS (SHEET 3 OF 4)
34	WATER DETAILS (SHEET 4 OF 4)
35	WASTEWATER DETAILS (SHEET 1 OF 2)
36	WASTEWATER DETAILS (SHEET 2 OF 2)
37	STREET DETAILS (SHEET 1 OF 3)
38	STREET DETAILS (SHEET 2 OF 3)
39	STREET DETAILS (SHEET 3 OF 3)



BGE, Inc.  
101 WEST LOUIS HENNA BLVD, Suite 400  
Austin, TX 78728  
Tel: 512-879-0400 • www.browngay.com  
TBPE Registration No. F-1046

SUBMITTED BY

*Nathan D. Kelly*  
NATHAN D. KELLY, P.E.  
10-17-22

BGE, INC. TBPE NO. F-1046  
101 WEST LOUIS HENNA BLVD.  
SUITE 400  
AUSTIN, TX 78728  
PHONE: 512-879-0400





GENERAL NOTES:

1. ALL ROADS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AS APPROVED BY THE COUNTY ENGINEER AND IN ACCORDANCE WITH THE SPECIFICATIONS FOUND IN THE CURRENT VERSION OF THE "TEXAS DEPARTMENT OF TRANSPORTATION MANUAL STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES".
2. ANY EXISTING UTILITIES, PAVEMENT, CURBS, SIDEWALKS, STRUCTURES, TREES, ETC., NOT PLANNED FOR DESTRUCTION OR REMOVAL THAT ARE DAMAGED OR REMOVED SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR SHALL VERIFY ALL DEPTHS AND LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES WITH THE CONSTRUCTION PLANS FOUND IN THE FIELD SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER WHO SHALL BE RESPONSIBLE FOR REVISING THE PLANS ARE APPROPRIATE.
4. MANHOLE FRAMES, COVERS, VALVES, CLEANOUTS, ETC. SHALL BE RAISED TO FINISHED GRADE PRIOR TO FINAL PAVING CONSTRUCTION.
5. THE CONTRACTOR SHALL GIVE THE WILLIAMSON COUNTY 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION. TELEPHONE (512) 943-3367 (ENGINEERING AND DEVELOPMENT SERVICES DEPARTMENT).
6. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE REVEGETATED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. REVEGETATION OF ALL DISTURBED OR EXPOSED AREAS SHALL CONSIST OF SODDING OR SEEDING. AT THE CONTRACTOR'S OPTION, HOWEVER, THE TYPE OF REVEGETATION MUST EQUAL OR EXCEED THE TYPE OF VEGETATION PRESENT BEFORE CONSTRUCTION.
7. THE CONTRACTOR AND THE ENGINEER SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE ENGINEER SHALL FURNISH WILLIAMSON COUNTY ACCURATE "AS-BUILT" DRAWINGS FOLLOWING COMPLETION OF ALL CONSTRUCTION. THESE "AS-BUILT" DRAWINGS SHALL MEET WITH THE SATISFACTION OF THE ENGINEERING AND DEVELOPMENT SERVICES DEPARTMENT PRIOR TO FINAL ACCEPTANCE.
8. WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS, THE CONTRACTOR SHALL CONFINE HIS WORK TO WITHIN THE PERMANENT AND ANY TEMPORARY EASEMENTS PRIOR TO FINAL ACCEPTANCE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. CLEAN-UP SHALL BE TO THE SATISFACTION OF THE CITY ENGINEER.
9. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL APPLY FOR AND SECURE ALL PROPER PERMITS FROM THE APPROPRIATE AUTHORITIES.

TRENCH SAFETY NOTES:

1. IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U. S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, ALL TRENCHES OVER 5 FEET IN DEPTH IN EITHER HARD AND COMPACT OR SOFT AND UNSTABLE SOIL SHALL BE SLOPED, SHORED, SHEETED, BRACED OR OTHERWISE PROTECTED. FURTHERMORE, ALL TRENCHES LESS THAN 5 FEET IN DEPTH SHOULD BE EFFECTIVELY PROTECTED WHEN HAZARDOUS GROUND MOVEMENT MAY BE EXPECTED. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT WILL BE PROVIDED BY THE CONTRACTOR; ARE ON SHEET \_\_\_\_\_, ETC.).
2. IN ACCORDANCE WITH THE U. S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, WHEN PERSONS ARE IN TRENCHES 4 FEET DEEP OR MORE, ADEQUATE MEANS OF EXIT, SUCH AS A LADDER OR STEPS, MUST BE PROVIDED AND LOCATED SO AS TO REQUIRE NO MORE THAN 25 FEET OF LATERAL REACH.
3. IF TRENCH SAFETY SYSTEM DETAILS WERE NOT PROVIDED IN THE PLANS BECAUSE TRENCHES WERE ANTICIPATED TO BE LESS THAN 5 FEET IN DEPTH AND DURING CONSTRUCTION IT IS FOUND THAT TRENCHES ARE IN FACT 5 FEET OR MORE IN DEPTH OR TRENCHES LESS THAN 5 FEET IN DEPTH ARE IN AN AREA WHERE HAZARDOUS GROUND MOVEMENT IS EXPECTED, ALL CONSTRUCTION SHALL CEASE, THE TRENCHED AREA SHALL BE BARRICADED AND THE ENGINEER IDENTIFIED. IDENTIFICATION SHALL BE IN THE FORM OF A SIGN OR SIGNAGE. TRENCH SAFETY SYSTEM DETAILS, AS DESIGNED BY A PROFESSIONAL ENGINEER, ARE RETAINED AND COPIES SUBMITTED TO WILLIAMSON COUNTY.

STREET AND DRAINAGE NOTES:

1. ALL TESTING SHALL BE DONE BY AN INDEPENDENT LABORATORY AT THE OWNER'S EXPENSE. ANY RETESTING SHALL BE PAID FOR BY THE CONTRACTOR. A CITY INSPECTOR SHALL BE PRESENT DURING ALL TESTS. TESTING SHALL BE COORDINATED WITH THE COUNTY INSPECTOR AND HE SHALL BE GIVEN A MINIMUM OF 24 HOURS ADVANCE NOTICE OF ANY TESTING. TELEPHONE (612) 943-3367 (INSPECTIONS)
2. BACKFILL BEHIND THE CURB SHALL BE COMPACTED TO OBTAIN A MINIMUM OF 95% MAXIMUM DENSITY TO WITHIN 3" OF TOP OF CURB. MATERIAL USED SHALL BE PRIMARILY GRANULAR WITH NO ROCKS LARGER THAN 6" IN THE GREATEST DIMENSION. THE REMAINING 3" SHALL BE CLEAN TOPSOIL, FREE FROM ALL CLODS AND SUITABLE FOR SUSTAINING PLANT LIFE.
3. DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT INCLUDING GAS, ELECTRIC, TELEPHONE, CABLE TV, WATER SERVICES, ETC., SHALL BE A MINIMUM OF 30" BELOW SURFACE.
4. BARRICADES BUILT TO CITY OF ROUND ROCK STANDARDS SHALL BE CONSTRUCTED ON ALL DEAD-END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB AND PUBLIC SAFETY.
5. ALL R.C.P. SHALL BE MINIMUM CLASS III.
6. SUBGRADE MATERIAL FOR THE STREETS SHOWN HEREIN WAS TESTED BY HOLT ENGINEERING AND THE PAVING SECTIONS DESIGNED IN ACCORDANCE WITH THE CURRENT CITY OF ROUND ROCK DESIGN CRITERIA. THE PAVING SECTIONS ARE TO BE CONSTRUCTED AS FOLLOWS:

CLASSIFICATION - LOCAL STREETS:  
RANDOLPH DRIVE, RANDOLPH COURT

<u>MATERIALS</u>	<u>THICKNESS</u>
CRUSHED LIMESTONE BASE	12.0 INCHES
HOT MIX ASPHALTIC CONCRETE	2.0 INCHES

SHOULD SOLID ROCK BE ENCOUNTERED PRIOR TO THE DEPTH NECESSARY FOR THE 12.0 INCHES AND 14.0 INCHES OF BASE MATERIAL SHOWN ABOVE, THE BASE MATERIAL THICKNESS MAY BE REDUCED TO 8.0 INCHES AND 10.0 INCHES, RESPECTIVELY, AND EXISTING MATERIAL SHALL BE EXCAVATED TO THE EXPOSED ROCK. IT SHOULD BE NOTED PER WILLIAMSON COUNTY SUBDIVISION REGULATIONS SOLID ROCK MUST BE INTACT, UNDISTURBED, AND CONTINUOUS LIMESTONE - WEATHERED LIMESTONE IS NOT CONSIDERED SOLID ROCK. THESE AREAS SHOULD BE DETERMINED IN THE FIELD AT THE DIRECTION OF A REPRESENTATIVE OF HOLT ENGINEERING, INC.

7. THE GEOTECHNICAL ENGINEER SHALL INSPECT THE SUBGRADE FOR COMPLIANCE WITH THE DESIGN ASSUMPTIONS MADE DURING PREPARATION OF THE SOILS REPORT. ANY ADJUSTMENTS THAT ARE REQUIRED SHALL BE MADE THROUGH REVISION OF THE CONSTRUCTION PLANS.
8. WHERE PI'S ARE OVER 20, SUBGRADES MUST BE STABILIZED UTILIZING A METHOD ACCEPTABLE TO THE COUNTY ENGINEER. THE GEOTECHNICAL ENGINEER SHALL RECOMMEND AN APPROPRIATE SUBGRADE STABILIZATION IF SULFATES ARE DETERMINED TO BE PRESENT.
9. ANY EXPANSIVE FILL ( $PI > 20$ ) PLACED IN THE SUBGRADE SHALL BE CONSIDERED EXPANSIVE SUBGRADE.
10. THE PRIMARY PAVEMENT DESIGN OPTION FOR AREAS WITH MORE THAN 2 FEET OF EXPANSIVE CLAY SHALL BE THE LOW PLASTICITY SUB-BASE OPTION. IF THE SUBGRADE IS NOT STABILIZED, THE DESIGN SHALL BE PROVIDED BY THE COUNTY ENGINEER FOR APPROVAL.
11. DELINEATION BETWEEN THESE DIFFERENT PAVEMENT THICKNESS SECTIONS SHOULD BE COMPLETED IN THE FIELD BY OBSERVATION OF OPEN UTILITIES, TRENCHES AND THE PAVEMENT SUBGRADE BY THE GEOTECHNICAL ENGINEER OR HIS DESIGNATE. GIVEN THE KNOWN VARIABILITY OF SURFACE SOILS AND THE PRESENCE OF FAULTS AT THIS SITE, THE GEOTECHNICAL ENGINEER MUST VERIFY THE SUBGRADE BEFORE INSTALLATION OF THE PAVEMENT SYSTEM CAN PROCEED. MULTIPLE SITE VISITS MAY BE REQUIRED DEPENDING UPON THE CONSTRUCTION SCHEDULE. FINALIZED DISTINCTION BETWEEN PAVEMENT SECTIONS SHALL BE PROVIDED AS ADDENDUMS TO THIS REPORT AS THESE OBSERVATIONS ARE COMPLETED. PLEASE CONTACT THE GEOTECHNICAL ENGINEER WHEN THE UTILITY TRENCHES ARE OPEN.
12. THE CITY OF AUSTIN RECOMMENDS A 50% INCREASE IN BASE COURSE OR 18 INCHES OF LOW PI SUB-BASE ( $4 < PI < 15$ ) TO COMPENSATE FOR THE TENDENCY OF MPFS TO UNDERESTIMATE MINIMUM PAVEMENT SECTIONS, WHICH IS ALREADY INCLUDED IN THE TABLE.
13. THE SUBGRADE IMPROVEMENT (LOW PLASTICITY SUB-BASE OR APPROVED ALTERNATE) SHOULD BE EXTENDED 3 FEET BEYOND THE BACK OF THE CURB LINE.
14. THESE PAVEMENT THICKNESS DESIGNS ARE INTENDED TO TRANSFER THE LOAD FROM THE ANTICIPATED TRAFFIC CONDITIONS.
15. THE RESPONSIBILITY OF ASSIGNING STREET CLASSIFICATION TO THE STREETS IN THIS PROJECT IS LEFT TO THE CIVIL ENGINEER.
16. IF PAVEMENT DESIGNS OTHER THAN THOSE LISTED ABOVE ARE DESIRED, PLEASE CONTACT HOLT ENGINEERING.
17. CONTRACTOR IS TO AVOID INSTALLATION OF UTILITIES, IRRIGATION LINES, PLANTINGS, ETC. IN THE BASE OVERBUILD.
18. THE BASE SHOULD EXTEND 18 INCHES BEHIND THE CURB LINE EXCEPT IN AREAS WHERE DEEPLY DEPOSITED HIGH PI SUBGRADE US ENCOUNTERED (B-08, B-13, B-50, AND B-59). IN THESE AREAS BASE SHOULD EXTEND 36 INCHES BEYOND THE CURB LINE.

TRAFFIC MARKING NOTES:

17. ALL PAVEMENT MARKINGS, MARKERS, PAINT, TRAFFIC BUTTONS, TRAFFIC CONTROLS AND SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH THE TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITIONS.

EROSION AND SEDIMENTATION CONTROL NOTES:

1. EROSION CONTROL MEASURES, SITE WORK AND RESTORATION WORK SHALL BE IN ACCORDANCE WITH THE CITY OF ROUND ROCK EROSION AND SEDIMENTATION CONTROL ORDINANCE.
2. ALL SLOPES SHALL BE SODDED OR SEEDED WITH APPROVED GRASS, GRASS MIXTURES OR GROUND COVER SUITABLE TO THE AREA AND SEASON IN WHICH THEY ARE APPLIED.
3. SILT FENCES, ROCK BERMS, SEDIMENTATION BASINS AND SIMILARLY RECOGNIZED TECHNIQUES AND MATERIALS SHALL BE EMPLOYED DURING CONSTRUCTION TO PREVENT POINT SOURCE SEDIMENTATION LOADING OF DOWNSTREAM FACILITIES. SUCH INSTALLATION SHALL BE REGULARLY INSPECTED BY WILLAMSON COUNTY FOR EFFECTIVENESS. ADDITIONAL MEASURES MAY BE REQUIRED IF, IN THE OPINION OF THE CITY ENGINEER, THEY ARE WARRANTED.
4. ALL TEMPORARY EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL FINAL INSPECTION AND APPROVAL OF THE PROJECT BY THE ENGINEER. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN ALL TEMPORARY EROSION CONTROL STRUCTURES AND TO REMOVE EACH STRUCTURE AS APPROVED BY THE ENGINEER.
5. ALL MUD, DIRT, ROCKS, DEBRIS, ETC., SPILLED, TRACKED OR OTHERWISE DEPOSITED ON EXISTING PAVED STREETS, DRIVES AND AREAS USED BY THE PUBLIC SHALL BE CLEANED UP IMMEDIATELY.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY CONTRIBUTING ZONE PLAN GENERAL CONSTRUCTION NOTES:

1. WRITTEN CONSTRUCTION NOTIFICATION SHOULD BE PROVIDED TO THE APPROPRIATE TCEQ REGIONAL OFFICE NO LATER THAN 48 HOURS PRIOR TO COMMENCEMENT OF THE REGULATED ACTIVITY. INFORMATION SHOULD INCLUDE THE DATE ON WHICH THE REGULATED ACTIVITY WILL COMMENCE, THE NAME OF THE APPROVED CONTRACTOR FOR THE REGULATED ACTIVITY, AND THE NAME OF THE PRIME CONTRACTOR WITH THE NAME AND TELEPHONE NUMBER OF THE CONTACT PERSON.
2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT SHOULD BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED CONTRIBUTING ZONE PLAN AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTOR(S) SHOULD KEEP COPIES OF THE APPROVED PLAN AND APPROVAL LETTER ON-SITE.
3. NO TEMPORARY ABOVEGROUND HYDROCARBON AND HAZARDOUS SUBSTANCE STORAGE TANK SYSTEM MAY BE INSTALLED WITHIN 150 FEET IF A DOMESTIC, INDUSTRIAL, OR PUBLIC WATER SUPPLY WELL IS PRESENT.
4. PRIOR TO COMMENCING CONSTRUCTION, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY SELECTED, INSTALLED, AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND GOOD ENGINEERING PRACTICES. CONTROLS SPECIFIED IN THE SWPPP SECTION OF THE APPROVED EDWARDS AQUIFER CONTRIBUTING ZONE PLAN ARE REQUIRED DURING CONSTRUCTION. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THE CONTROLS MUST BE REPLACED OR MODIFIED IN DISTURBED AREAS ARE REVEGETATED AND PERMANENTLY STABILIZED.
5. IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED AT A FREQUENCY SUFFICIENT TO MINIMIZE OFFSITE IMPACTS TO WATER QUALITY (E.G., FUGITIVE SEDIMENT IN STREET BEING WASHED INTO SURFACE STORMS OR SENSITIVE FEATURES BY THE NEXT RAIN).
6. SEDIMENT MUST BE REMOVED FROM SEDIMENT TRAPS OR SEDIMENTATION PONDS NOT LATER THAN WHEN DESIGN CAPACITY HAS BEEN REDUCED BY 50%. A PERMANENT POND MUST BE PROVIDED THAT CAN INDICATE WHEN THE SEDIMENT OCCUPIES 50% OF THE BASIN VOLUME.
7. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BECOMING A POLLUTANT SOURCE FOR STORMWATER DISCHARGES (E.G., SCREENING OUTFALLS, PICKED UP DAILY).
8. ALL SPILLS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE AND STORED ON-SITE MUST HAVE PROPER E&S CONTROLS INSTALLED.
9. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, AND CONSTRUCTION ACTIVITIES WILL NOT RESUME WITHIN 21 DAYS. WHEN THE INITIATION OF STABILIZATION MEASURES BY THE 14TH DAY IS PRECLUDED BY WEATHER CONDITIONS, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE.
10. THE FOLLOWING RECORDS SHOULD BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST: THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR; THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
11. THE HOLDER OF ANY APPROVED CONTRIBUTING ZONE PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
  - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY BEST MANAGEMENT PRACTICES OR STRUCTURE(S), INCLUDING BUT NOT LIMITED TO TEMPORARY OR PERMANENT POND, DAM, BERM, SILT FENCES, AND DIVERSITY STRUCTURES;
  - B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED;
  - C. ANY CHANGE THAT WOULD SIGNIFICANTLY IMPACT THE ABILITY TO PREVENT POLLUTION OF THE EDWARDS AQUIFER AND HYDROLOGICALLY CONNECTED SURFACE WATER; OR
  - D. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED IN A CONTRIBUTING ZONE PLAN AS UNDEVELOPED.

Austin Regional Office 2800 S. IH 35, Suite 100 Austin, Texas 78704-5712 Phone (512) 339-2929 Fax (512) 339-3795	San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329
---	--

## STORM WATER POLLUTION PREVENTION PLAN (SWP3) GENERAL NOTES

1. ALL CONSTRUCTION ACTIVITIES DISTURBING ONE ACRE AND GREATER MUST OBTAIN STORM WATER DISCHARGE AUTHORIZATION FROM THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ), THROUGH COMPLIANCE WITH TCEQ'S GENERAL PERMIT #TXR150000. THE PRIMARY CONSTRUCTION SITE OPERATOR(S) [PCSO] MUST PREPARE AND IMPLEMENT AN SWP3 THROUGHOUT CONSTRUCTION WHICH INCLUDES THE EROSION AND SEDIMENT CONTROL (ESC) PLAN AND OTHER BEST MANAGEMENT PRACTICES (BMPs) SPECIFIED IN THESE PLANS APPROVED BY TRAVIS COUNTY.
2. SMALL CONSTRUCTION ACTIVITIES DISTURBING BETWEEN ONE AND FIVE ACRES SHALL POST A TCEQ CONSTRUCTION SITE NOTICE (CSN) ON SITE PRIOR TO COMMENCING CONSTRUCTION. LARGE CONSTRUCTION ACTIVITIES DISTURBING FIVE ACRES OR GREATER SHALL SUBMIT A NOTICE OF INTENT (NOI) TO TCEQ AND POST THE NOI ON SITE AT LEAST SEVEN (7) DAYS PRIOR TO BEGINNING CONSTRUCTION. NOTICES POSTED MUST BE MAINTAINED THROUGHOUT CONSTRUCTION.
3. THE PCSO MUST REVISE THE SWP3 WHENEVER CHANGING SITE CONDITIONS, OR A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE HAS A SIGNIFICANT EFFECT ON THE DISCHARGE OF POLLUTANTS NOT PREVIOUSLY ADDRESSED; OR WHEN RESULTS OF INSPECTIONS BY SITE OPERATORS, TRAVIS COUNTY TCEQ, OR OTHER LOCAL AGENCY AUTHORIZED TO APPROVE ESC PLANS INDICATE THE SWP3 IS PROVING INEFFECTIVE IN ELIMINATING OR SIGNIFICANTLY MINIMIZING POLLUTANTS IN DISCHARGES FROM THE SITE.
4. TEMPORARY OR PERMANENT EROSION CONTROL AND STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE, AND AS SPECIFIED ON THE PLANS, IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. THESE MEASURES MUST BE INITIATED NO LATER THAN 14 DAYS AFTER CESSATION, UNLESS CONSTRUCTION ACTIVITIES WILL RESUME WITHIN 21 DAYS IN THE AREA.
5. UPON FINAL STABILIZATION OF THE ENTIRE SITE, INCLUDING COMPLETION OF ALL STABILIZATION REQUIREMENTS OF THE APPROVED PLANS AND PERMIT AS VERIFIED BY TRAVIS COUNTY, THE PCSO SHALL SUBMIT A NOTICE OF TERMINATION (NOT) TO TCEQ.

UTILITY COMPANY CONTACT NUMBERS:

<u>P.F.C.</u>	<u>AT&amp;T</u>
FOR PRE-CONSTRUCTION MEETINGS	FOR PRE-CONSTRUCTION MEETINGS
CALL 505-7649.	CALL 370-1000.
FOR UTILITY LINE LOCATION	FOR UTILITY LINE LOCATION
CALL 505-7542.	CALL 370-1000.
<u>TIME WARNER CABLE</u>	<u>NORTH SAN GABRIEL MUNICIPAL</u>
FOR PRE-CONSTRUCTION MEETINGS	UTILITY DISTRICT NO. 1
CALL 485-6342.	FOR PRE-CONSTRUCTION MEETINGS
FOR UTILITY LINE LOCATION	CALL 512-989-2200.
CALL 485-6356.	

WILLIAMSON COUNTY NOTES:

#### B4 CONSTRUCTION—GENERAL

- B.4.1 A PRECONSTRUCTION MEETING SHALL BE SCHEDULED PRIOR TO THE START OF CONSTRUCTION. THE DESIGN ENGINEER, OWNER, CONTRACTOR, SUBCONTRACTORS, AND COUNTY ENGINEER SHALL ATTEND THIS MEETING. ALL ROADS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE TEXAS DEPARTMENT OF TRANSPORTATION MANUAL STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES UNLESS OTHERWISE STATED ON THE CONSTRUCTION DOCUMENTS APPROVED BY THE COUNTY ENGINEER.
- B.4.2 ALL MATERIALS SHALL BE SAMPLED AND TESTED BY AN INDEPENDENT TESTING LABORATORY IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS. THE COUNTY ENGINEER SHALL REVIEW THE TESTING RESULTS AND SIGNIFY THE RESULTS AS PASS OR FAIL. THE COUNTY ENGINEER SHALL CERTIFIED COPIES OF THESE TEST RESULTS. THE COUNTY ENGINEER MUST APPROVE THE TEST RESULTS PRIOR TO CONSTRUCTING THE NEXT COURSE OF THE ROADWAY STRUCTURE. ANY MATERIAL WHICH DOES NOT MEET THE MINIMUM REQUIRED TEST SPECIFICATIONS SHALL BE REMOVED AND REJECTED MATERIAL SHALL BE ALTERNATELY USED IN WRITING FROM THE COUNTY ENGINEER.
- B.4.3 EXCEPT FOR ELECTRICAL LINES, ALL UNDERGROUND NONFERROUS UTILITIES WITHIN A RIGHT-OF-WAY OR EASEMENT MUST BE ACCOMPANIED BY FERROUS METAL LINES TO AID IN TRACING THE LOCATION OF SAID UTILITIES THROUGH THE USE OF A METAL DETECTOR.
- B.4.4 ALL PAYMENTS ARE TO BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER. THE DESIGN SHALL BE BASED ON A 20-YEAR DESIGN LIFE AND IN CONJUNCTION WITH RECOMMENDATIONS BASED UPON A SOILS REPORT OF SAMPLES TAKEN ALONG THE PROPOSED ROADWAYS. TEST BORINGS SHALL BE MADE TO A MAXIMUM DEPTH OF 10 FEET. THE SOILS REPORT AND PAVEMENT DESIGN SHALL BE SUBMITTED TO THE COUNTY ENGINEER FOR REVIEW. THE PAVEMENT DESIGN MUST BE APPROVED BY THE COUNTY ENGINEER PRIOR TO OR CONCURRENTLY WITH THE REVIEW AND APPROVAL OF THE SOILS REPORT. IN ADDITION TO THE SOILS REPORT, THE SOILS REPORT SHALL CONTAIN THE RESULTS OF SAMPLED AND TESTED SUBGRADE FOR PLASTICITY INDEX, PH, SULFATE CONTENT, AND MAXIMUM DENSITY.

B5 SUBGRADE

- B5.1 THE PREPARATION OF THE SUBGRADE SHALL FOLLOW GOOD ENGINEERING PRACTICES AS DIRECTED BY THE COUNTY ENGINEER IN CONJUNCTION WITH THE RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORT. WHEN THE PLASTICITY INDEX (PI) IS GREATER THAN 20, A SUFFICIENT AMOUNT OF LIME SHALL BE ADDED AS DESCRIBED IN ITEM 260.1. THE CURRENT EDITION OF THE TxDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION UNTIL THE PI IS LESS THAN 20. IF THE ADDITION OF LIME AS DESCRIBED IN ITEM 260 IS NOT FEASIBLE, AN ALTERNATE STABILIZING DESIGN SHALL BE PROPOSED AND SUBMITTED TO THE COUNTY ENGINEER FOR APPROVAL. THE SUBGRADE SHALL BE PREPARED AND COMPACTED TO ACHIEVE A DRY DENSITY PER TxDOT ITEM 132. IN ADDITION, PROOF ROLLING MAY BE REQUIRED BY THE COUNTY ENGINEER.
- B5.2 THE SUBGRADE SHALL BE INSPECTED AND APPROVED BY AN INDEPENDENT TESTING LABORATORY. A CERTIFIED COPY OF ALL INSPECTION REPORTS FURNISHED TO THE COUNTY ENGINEER WHO MUST APPROVE THE SUBGRADE. THE BASE MATERIAL, ALL DENSITY TEST REPORTS SHALL INCLUDE A COPY OF THE WORK SHEET SHOWING THE PERCENTAGE OF THE MAXIMUM DRY (PROCTOR) DENSITY, THE NUMBER AND LOCATION OF ALL SUBGRADE TESTS SHALL BE DETERMINED BY THE COUNTY ENGINEER.
- B6. BASE MATERIAL**
- B6.1 BASE MATERIAL SHALL CONFORM TO ITEM 247 OF THE CURRENT EDITION OF THE TxDOT STANDARD SPECIFICATION FOR CONSTRUCTION, FLEXIBLE BASE MATERIAL SHALL BE A GRADE 1, OR A GRADE 2, OR AS APPROVED BY THE COUNTY ENGINEER.
- B6.2 EACH LAYER OF BASE COURSE SHALL BE TESTED FOR IN-PLACE DRY DENSITY AND MEASURED FOR COMPACTED THICKNESS. THE NUMBER AND LOCATION OF ALL BASE TEST SAMPLES SHALL BE DETERMINED BY THE COUNTY ENGINEER.
- B6.3 THE BASE SHALL BE PREPARED AND COMPACTED TO ACHIEVE A MINIMUM OF 100% OF THE MAXIMUM (PROCTOR) DRY DENSITY OR AS APPROVED BY THE COUNTY ENGINEER UPON RECOMMENDATION BY THE TESTING LABORATORY. THE MAXIMUM LIFT SHALL NOT EXCEED SIX INCHES. THE BASE MUST BE INSPECTED AND APPROVED BY AN INDEPENDENT TESTING LABORATORY AND A CERTIFIED COPY OF THE TEST RESULTS FURNISHED TO THE COUNTY ENGINEER WHO MUST APPROVE THE BASE. THE CURRENT EDITION OF THE TxDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION UNTIL THE PERCENTAGE OF THE MAXIMUM DRY DENSITY OF THE STOCKPILE SHALL BE TESTED FOR THE SPECIFICATIONS FOUND IN ITEM 247 TABLE 1 AND THE RESULT FURNISHED TO THE COUNTY ENGINEER FOR APPROVAL.

## B7 BITUMINOUS PAVEMENT

- [illegible]

B9 CONCRETE - GENERAL

- B9.1 UNLESS OTHERWISE SPECIFIED, CONCRETE SHALL BE IN ACCORDANCE WITH ITEM 421 OF THE CURRENT EDITION OF THE TxDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION AND BE PLACED IN ACCORDANCE WITH THE APPLICABLE ITEM.
- B9.2 ALL CONCRETE SHALL BE TESTED FOR COMPRESSIVE STRENGTH. ONE SET OF THREE CONCRETE TEST CYLINDERS SHALL BE MOLDED FOR EVERY 500 CUBIC YARDS OF CONCRETE PLACED FOR EACH CLASS OF CONCRETE PER DAY, OR AT ANY OTHER INTERVAL AS DETERMINED BY THE COUNTY ENGINEER. A SLUMP TEST SHALL BE REQUIRED WITH EACH SET OF TEST CYLINDERS. ONE CYLINDER SHALL BE TESTED FOR COMPRESSIVE STRENGTH AT AN AGE OF SEVEN DAYS AND THE REMAINING TWO CYLINDERS SHALL BE TESTED AT 28 DAYS OF AGE.

## CITY OF GEORGETOWN - GENERAL NOTES

1. THESE CONSTRUCTION PLANS WERE PREPARED, SEALED, SIGNED AND DATED BY A TEXAS LICENSED PROFESSIONAL ENGINEER. THEREFORE BASED ON THE ENGINEER'S CONCURRENCE OF COMPLIANCE, THE CONSTRUCTION PLANS FOR CONSTRUCTION OF THE PROPOSED PROJECT ARE HEREBY APPROVED SUBJECT TO THE STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS MANUAL AND ALL OTHER APPLICABLE CITY, STATE AND FEDERAL REQUIREMENTS AND CODES.
2. THIS PROJECT IS SUBJECT TO ALL APPLICABLE CITY REGULATIONS, STANDARD SPECIFICATIONS AND DETAILS IN EFFECT AT THE TIME OF SUBMITTAL OF THE PROJECT TO THE CITY.
3. THE SITE CONSTRUCTION PLANS SHALL MEET ALL REQUIREMENTS OF THE APPROVED SITE PLAN.
4. PRIVATE WATER SYSTEM FIRE LINES SHALL BE TESTED BY THE CONTRACTOR TO 200 PSI FOR 2 HOURS.
5. PRIVATE WATER SYSTEM FIRE LINES SHALL BE DUCTILE IRON PIPING FROM THE WATER MAIN TO THE BUILDING SPRINKLER SYSTEM, AND 200 PSI C900 PVC FOR ALL OTHERS.
6. PUBLIC WATER SYSTEM MAINS SHALL BE 150 PSI C900 PVC AND TESTED BY THE CONTRACTOR AT 150 PSI FOR 4 HOURS.
7. ALL BENDS AND CHANGES IN DIRECTION ON WATER MAINS SHALL BE RESTRAINED AND THRUST BLOCKED.
8. LONG FIRE HYDRANT LEADS SHALL BE RESTRAINED.
9. ALL WATER LINES ARE TO BE BACTERIA TESTED BY THE CONTRACTOR ACCORDING TO THE CITY STANDARDS AND SPECIFICATIONS.
10. WATER AND SEWER MAIN CROSSINGS SHALL MEET ALL REQUIREMENTS OF THE TCEQ AND THE CITY.
11. ALL SIDEWALK RAMPS ARE TO BE INSTALLED WITH THE PUBLIC INFRASTRUCTURE.

RECORD DRAWINGS WILL BE REQUIRED.

TCEQ WATER DISTRIBUTION SYSTEM GENERAL CONSTRUCTION NOTES

1. THIS WATER DISTRIBUTION SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) RULES AND REGULATIONS FOR PUBLIC WATER SYSTEMS 30 TEXAS ADMINISTRATIVE CODE (TAC) CHAPTER 290 SUBCHAPTER D, WHEN CONFLICTS ARE NOTED WITH LOCAL STANDARDS, THE MORE STRINGENT REQUIREMENT SHALL BE APPLIED. CONSTRUCTION FOR PUBLIC WATER SYSTEMS MUST ALWAYS, AT A MINIMUM, COMPLY WITH RULES AND REGULATIONS FOR PUBLIC WATER SYSTEMS.
2. AN APPOINTED ENGINEER SHALL NOTIFY IN WRITING THE LOCAL TCEQ'S REGIONAL OFFICE WHEN CONSTRUCTION WILL START. PLEASE KEEP IN MIND THAT UPON COMPLETION OF THE WATER WORKS PROJECT, THE ENGINEER OR OWNER SHALL NOTIFY THE COMMISSION'S WATER SUPPLY DIVISION, IN WRITING, AS TO ITS COMPLETION AND ATTEST TO THE FACT THAT THE WORK HAS BEEN COMPLETED ESSENTIALLY ACCORDING TO THE PLANS AND CHANGE ORDERS ON FILE WITH THE COMMISSION AS REQUIRED IN 30 TAC §290.39(h)(3).
3. ALL NEWLY INSTALLED PIPES AND RELATED PRODUCTS MUST CONFORM TO AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)/NSF INTERNATIONAL STANDARD 61 AND MUST BE CERTIFIED BY AN ORGANIZATION ACCREDITED BY ANSI, AS REQUIRED BY 30 TAC §290.44(a)(1).
4. PLASTIC PIPE FOR USE IN PUBLIC WATER SYSTEMS MUST BEAR THE NSF INTERNATIONAL SEAL OF APPROVAL (NSF) AND HAVE AN ASTM DESIGNATION. FOR POLYETHYLENE GLYCOL (PE) OR STAINLESS STEEL PIPE, AS REQUIRED BY 30 TAC §290.44(a)(2).
5. NO PIPE WHICH HAS BEEN USED FOR ANY PURPOSE OTHER THAN THE CONVEYANCE OF DRINKING WATER SHALL BE ACCEPTED OR RELOCATED FOR USE IN ANY PUBLIC DRINKING WATER SUPPLY, AS REQUIRED BY 30 TAC §290.44(a)(3).
6. WATER TRANSMISSION AND DISTRIBUTION LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. HOWEVER, THE TOP OF THE WATER LINE MUST BE LOCATED BELOW THE FROST LINE AND IN NO CASE SHALL THE TOP OF THE WATER LINE BE LESS THAN 24 INCHES BELOW GROUND SURFACE, AS REQUIRED BY 30 TAC §290.44(a)(4). REVISED MARCH 4, 2015
7. PURSUANT TO 30 TAC §290.44(a)(5), THE HYDROSTATIC LEAKAGE RATE SHALL NOT EXCEED THE AMOUNT ALLOWED OR RECOMMENDED BY THE MOST CURRENT AWWA FORMULAS FOR PIPE, CAST IRON AND DUCTILE IRON PIPE. INCLUDE THE FORMULAS IN THE NOTES ON THE PLANS. TO THE HYDROSTATIC LEAKAGE RATE FOR POLYETHYLENE GLYCOL (PE) AND APPURTENANCES SHALL NOT EXCEED THE AMOUNT ALLOWED OR RECOMMENDED BY FORMULAS IN AMERICA WATER WORKS ASSOCIATION (AWWA) C-605 AS REQUIRED IN 30 TAC §290.44(a)(5). PLEASE ENSURE THAT THE FORMULA FOR THIS CALCULATION IS CORRECT AND MOST CURRENT FORMULA IS IN USE;

WHERE

- Q = THE QUANTITY OF MAKEUP WATER IN GALLONS PER HOUR,
- L = THE LENGTH OF THE PIPE SECTION BEING TESTED, IN FEET,
- D = THE NOMINAL DIAMETER OF THE PIPE IN INCHES, AND
- P = THE AVERAGE TEST PRESSURE DURING THE HYDROSTATIC TEST IN POUNDS PER SQUARE INCH (PSI).


O THE HYDROSTATIC LEAKAGE RATE FOR DUCTILE IRON (DI) PIPE AND APPURTENANCES SHALL NOT EXCEED THE AMOUNT ALLOWED OR RECOMMENDED BY FORMULAS IN AMERICA WATER WORKS ASSOCIATION (AWWA) C-600 AS REQUIRED IN 30 TAC §290.44(A)(5). PLEASE ENSURE THAT THE FORMULA FOR THIS CALCULATION IS CORRECT AND MOST CURRENT FORMULA IS IN USE;

$$L=(SD \cdot P)/148,000P$$

WHERE

- L = THE QUANTITY OF MAKEUP WATER IN GALLONS PER HOUR,
- S = THE LENGTH OF THE PIPE SECTION BEING TESTED, IN FEET,
- D = THE NOMINAL DIAMETER OF THE PIPE IN INCHES, AND
- P = THE AVERAGE TEST PRESSURE DURING THE HYDROSTATIC TEST IN POUNDS PER SQUARE INCH (PSI).

- THE MAXIMUM ALLOWABLE LEAD CONTENT OF PIPES, PIPE FITTINGS, PLUMBING FITTINGS, AND FIXTURES TO 0.25 PERCENT.
- THE SYSTEM MUST BE DESIGNED TO MAINTAIN A MINIMUM PRESSURE OF 35 PSI AT ALL POINTS WITHIN THE DISTRIBUTION NETWORK AT FLOW RATES OF AT LEAST 1.5 GALLONS PER MINUTE PER CONNECTION. WHEN THE SYSTEM IS INTENDED TO PROVIDE FIREFIGHTING CAPABILITY, IT MUST ALSO BE DESIGNED TO MAINTAIN A MINIMUM PRESSURE OF 20 PSI UNDER COMBINED FIRE AND DRINKING WATER FLOW CONDITIONS AS REQUIRED BY 30 AC §290.44(D), REVISED MARCH 4, 2015.
- THE CONTRACTOR SHALL INSTALL APPROPRIATE AIR RELEASE DEVICES IN THE DISTRIBUTION SYSTEM AT ALL POINTS WHERE TOPOGRAPHY OR OTHER FACTORS MAY CREATE AIR LOCKS IN THE LINES. ALL VENT OPENINGS TO THE ATMOSPHERE SHALL BE COVERED WITH 16-MESH OR FINER, CORROSION RESISTANT SCREENING MATERIAL OR AN ACCEPTABLE EQUIVALENT AS REQUIRED BY 30 AC §290.44(D)(1).
- PURSUANT TO 30 AC §290.44(D)(4), ACCURATE WATER METERS SHALL BE PROVIDED. SERVICE CONNECTIONS AND METER LOCATIONS SHOULD BE SHOWN ON THE PLANS.
- PURSUANT TO 30 AC §290.44(D)(5), SUFFICIENT VALVES AND BLOWOFFS TO MAKE REPAIRS. THE ENGINEERING REPORT SHALL ESTABLISH CRITERIA FOR THE DESIGN.
- PURSUANT TO 30 AC §290.44(D)(6), THE SYSTEM SHALL BE DESIGNED TO AFFORD EFFECTIVE CIRCULATION OF WATER WITH A MINIMUM OF DEAD ENDS. ALL DEAD-ENDS SHALL BE PROVIDED WITH ACCEPTABLE FLUSH VALVES AND DISCHARGE PIPING. ALL DEAD-END LINES LESS THAN TWO INCHES IN DIAMETER SHALL NOT REQUIRE FLUSH VALVES IF THEY END AT A CUSTOMER SERVICE. WHERE DEAD ENDS ARE NECESSARY AS A STAGE IN THE GROWTH OF THE SYSTEM, THEY SHALL BE LOCATED AND ARRANGED TO ULTIMATELY CONNECT THE ENDS TO PROVIDE CIRCULATION.
- THE CONTRACTOR SHALL MAINTAIN A MINIMUM SEPARATION DISTANCE IN ALL DIRECTIONS OF NINE FEET BETWEEN THE PROPOSED WATERLINE AND WASTEWATER COLLECTION FACILITIES INCLUDING MANHOLES AND SEPTIC TANK DRAINFIELDS. IF THIS DISTANCE CANNOT BE MAINTAINED, THE CONTRACTOR MUST NOTIFY THE PROJECT ENGINEER FOR FURTHER DIRECTION. SEPARATION DISTANCES, INSTALLATION METHODS, AND MATERIALS UTILIZED MUST MEET 30 AC §290.44(E)(1)-(OF THE CURRENT RULES).
- PURSUANT TO 30 AC §290.44(E)(5), THE SEPARATION DISTANCE FROM A POTABLE WATERLINE TO A WASTEWATER MAIN OR LATERAL MANHOLE OR CLEANOUT SHALL BE A MINIMUM OF NINE FEET. WHERE THE NINE-FOOT SEPARATION DISTANCE CANNOT BE ACHIEVED, THE POTABLE WATERLINE SHALL BE ENCASED IN A JOINT OF AT LEAST 150 PSI PRESSURE CLASS PIPE AT LEAST 18 FEET LONG AND TWO NOMINAL SIZES LARGER THAN THE NEW CONVEYANCE. THE SPACE AROUND THE CARRIER PIPE SHALL BE SUPPORTED AT FIVE-FOOT INTERVALS WITH SPACERS OR BE FILLED TO THE SPRINGLINE WITH WASHED THE 3/4" SAND. THE PIPE SHALL BE CENTERED ON THE CROSSING AND BOTH ENDS SEALED WITH GEMENT GROUT OR MANUFACTURED SEALANT.
- PURSUANT TO 30 AC §290.44(E)(6), FIRE HYDRANTS SHALL NOT BE INSTALLED WITHIN NINE FEET VERTICALLY OR HORIZONTALLY OF ANY WASTEWATER LINE. WASTEWATER LATERAL, OR WASTEWATER SERVICE LINE REGARDLESS OF CONSTRUCTION.
- PURSUANT TO 30 AC §290.44(E)(7), SUCTION MAINS TO PUMPING EQUIPMENT SHALL NOT CROSS WASTEWATER MAINS, WASTEWATER LATERALS, OR WASTEWATER SERVICE LINES. RAW WATER SUPPLY LINES SHALL NOT BE INSTALLED WITHIN FIVE FEET OF ANY TILE OR CONCRETE WASTEWATER MAIN, WASTEWATER LATERAL, OR WASTEWATER SERVICE LINE.
- PURSUANT TO 30 AC §290.44(E)(8), WATERLINES SHALL NOT BE INSTALLED CLOSER THAN TEN FEET TO SEPTIC TANK DRAINFIELDS. REVISED MARCH 4, 2015
- PURSUANT TO 30 AC §290.44(F)(1), THE CONTRACTOR SHALL NOT PLACE THE PIPE IN WATER OR WHERE IT CAN BE FLOODED WITH WATER OR SEWAGE DURING ITS STORAGE OR INSTALLATION.
- PURSUANT TO 30 AC §290.44(F)(2), WHEN WATERLINES ARE LAID UNDER ANY FLOWING OR INTERMITTENT STREAM OR SEMI-PERMANENT BODY OF WATER THE WATER MAIN SHALL BE INSTALLED IN A SEPARATE WATERTIGHT PIPE ENCASEMENT. VALVES MUST BE PROVIDED ON EACH SIDE OF THE CROSSING WITH FACILITIES TO ALLOW THE UNDERWATER PORTION OF THE SYSTEM TO BE ISOLATED AND TESTED.
- THE CONTRACTOR SHALL DISINFECT THE NEW WATER MAINS IN ACCORDANCE WITH AWWA STANDARD C-651 AND THEN FLUSH AND SAMPLE THE LINES BEFORE BEING PLACED INTO SERVICE. SAMPLES SHALL BE COLLECTED FOR MICROBIOLOGICAL ANALYSIS TO CHECK THE EFFECTIVENESS OF THE DISINFECTION PROCESS WHICH IS REQUIRED FOR CONTAMINATION PERSISTS. A MINIMUM OF ONE SAMPLE FOR EACH 1,000 FEET OF COMPLETED WATER LINE WILL BE REQUIRED OR AT THE NEXT AVAILABLE SAMPLING POINT BEYOND 1,000 FEET AS DESIGNATED BY THE DESIGN ENGINEER, IN ACCORDANCE WITH 30 AC §290.44(F)(3).

NORTHGATE RANCH PHASE 3 - SECTION 17 WILLIAMSON COUNTY, TEXAS	NOTES (SHEET 1 OF 2)		<p><b>BGE, INC.</b> 101 W. Loop West, Suite 400 AUSTIN, TX 78728 TEBE Registration No. F-1046 TEL: 512-879-0400 <a href="http://www.bgeinc.com">www.bgeinc.com</a></p>	DESIGNED BY:	MTC	△
				REVIEWED BY:	MTC	△
				DRAWN BY:	MTC	△
						△
						△
				DATE	APR	
				DESCRIPTION	REV	



G:\TXC\Projects\Randolph Todd Col 10882-00-Northgate\_Ph3\_Sect7\LD01\_CADD\01\_Sht10882-C-COVR.dwg    Layout NOTES (SHEET 2 OF 2)    Plotted: 10/17/2022 8:06:26 AM

CONSTRUCTION SEQUENCE OF EVENTS

1. CALL DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION, DEVELOPMENT ENGINEER CONSTRUCTION INSPECTION AND THE ENVIRONMENTAL AND CONSERVATION SERVICES DEPARTMENT 48 HOURS PRIOR TO BEGINNING ANY WORK. CALL THE ONE CALL CENTER FOR UTILITY LOCATIONS AND OBTAIN PERMIT FOR ANY WORK WITHIN THE CITY OF GEORGETOWN OR WILLIAMSON COUNTY R.O.W. TREE PROTECTION WILL ALSO BE INSTALLED.
2. INSTALL TEMPORARY EROSION CONTROL MEASURES AND STABILIZED CONSTRUCTION ENTRANCE IN ACCORDANCE WITH LOCATIONS AND DETAILS SHOWN ON THE PLANS. PRIOR TO CLEARING AND GRUBBING, NOTIFY CITY OF GEORGETOWN AND WILLIAMSON COUNTY INSPECTORS WHEN EROSION CONTROLS ARE INSTALLED.
3. HOLD PRE-CONSTRUCTION CONFERENCE ON SITE WITH THE CONTRACTOR, DESIGN ENGINEER, OWNERS REPRESENTATIVE AND THE CITY'S ENVIRONMENTAL INSPECTOR (UTILITY DEPARTMENT DEVELOPMENT ENGINEER, (512) 930-3582. REQUIRES 72 HOURS ADVANCE NOTICE) AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS AND PRIOR TO BEGINNING ANY WORK.
4. BEGIN CONSTRUCTION OF PROJECT AS FOLLOWS:
  - A. ROUGH CUT/GRADE STREET, CHANNELS, PONDS, DRAINAGE FACILITIES TO INSURE NO MAJOR DEVIATIONS TO PROPOSED DRAINAGE PATTERNS OCCUR DURING CONSTRUCTION.
  - B. INSTALL ALL UTILITIES
  - C. INSTALL ALL CROSSINGS WITHIN STREET RIGHT-OF-WAYS
  - D. PREPARE SUBGRADE
  - E. CONSTRUCT STREET BASE
  - F. INSTALL CURB AND GUTTER
  - G. COMPLETE ALL ROUGH GRADING AND UNDERGROUND UTILITIES IN STREET RIGHT-OF-WAYS
  - H. LAY FINAL BASE COURSE
  - I. LAY ASPHALT
  - J. COMPLETE ALL NECESSARY FINAL GRADING AND DRESS UP OF AREAS DISTURBED DURING CONSTRUCTION
5. HOLD OWNERS POST-CONSTRUCTION CONFERENCE ON SITE WITH THE CONTRACTOR, DESIGN ENGINEER, OWNER'S REPRESENTATIVE AND THE CITY'S ENVIRONMENTAL ENGINEER.
6. AFTER ACCEPTANCE OF REVEGETATION BY THE OWNER AND THE CITY'S INSPECTOR, REMOVE TEMPORARY SEDIMENTATION AND EROSION CONTROLS
7. FINAL INSPECTION BY COUNTY AND CITY WITH CONTRACTOR AND ENGINEER.

W.C.E.S.D #4 NOTES:

(2) SECTION C105.2 INSTALLATION

FIRE HYDRANTS MUST BE INSTALLED WITH THE CENTER OF THE FIVE (5) INCH STEAMER OPENING AT LEAST 18 INCHES ABOVE FINISHED GRADE. THE FIVE (5) INCH OPENING MUST FACE THE DRIVEWAY OR STREET AND MUST BE TOTALLY UNOBSTRUCTED TO THE STREET. FIRE HYDRANT DESIGN SHALL BE 2- 2.5" NST OUTLETS, 1 - 5.0" STORZ CONNECTION WITH A CAP TO INCLUDE A HEX NUT TO FIT A HYDRANT WRENCH ALONG WITH A REFLECTIVE BAND. THE FIRE HYDRANT SHALL BE PAINTED SILVER IN COLOR AND DESIGNATED BY A BLUE REFLECTOR IN THE CENTER OF THE STREET.

PEDERNALES ELECTRIC COMPANY NOTES:

1. A PRE-CONSTRUCTION SAFETY MEETING WITH PEDERNALES ELECTRIC COOPERATIVE, INC. ("PEC") IS REQUIRED 48 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION. FAILURE TO DO SO MAY RESULT IN THE PROJECT BEING SHUTDOWN. CALL MARSHA MOORE, AT 1-800-868-4791 EXT. 7161 TO SCHEDULE A PRE-CONSTRUCTION SAFETY MEETING.
2. BARRICADES MUST BE ERECTED 15 FEET FROM ELECTRIC TRANSMISSION STRUCTURES DURING CONSTRUCTION.
3. WARNING SIGNS MUST BE PLACED UNDER THE OVERHEAD ELECTRIC TRANSMISSION FACILITIES AS NOTIFICATION OF THESE ELECTRICAL FACILITIES. (THIS NOTE SHOULD ALSO BE SHOWN ON GRADING PLANS.)
4. FEDERAL, STATE AND LOCAL LAWS REGULATE THE ACTIVITIES OF THOSE WHO WORK NEAR OVERHEAD POWER LINES, INCLUDING MOVING EQUIPMENT, AND GOVERN MINIMUM ELECTRIC LINE CLEARANCE REQUIREMENTS FOR SUCH WORK. CRIMINAL PENALTIES MAY RESULT FOR ANY VIOLATIONS. CONSTRUCTION WILL BE WITHIN THE MOST RESTRICTIVE MINIMUM ELECTRIC LINE CLEARANCE.
5. PROPERTY OWNER SHALL NOT CONSTRUCT, LOCATE, OR CAUSE TO BE CONSTRUCTED OR LOCATED, ANY BUILDING, OR HABITABLE STRUCTURE WITHIN PEC'S EASEMENT AND RIGHT-OF-WAY. THE TERMS "BUILDING" AND "HABITABLE STRUCTURE" SHALL INCLUDE, BUT ARE NOT LIMITED TO, ANY HOUSE, APARTMENT, DWELLING, MOBILE HOME, GARAGE, OUT BUILDING, EQUIPMENT SHELTER, FARM OR LIVESTOCK FACILITIES, STORAGE BARNs, HUNTING STRUCTURES, OR STORAGE SHEDS. IT IS FURTHER EXPRESSLY UNDERSTOOD BY PROPERTY OWNER, AND PROPERTY OWNER FURTHER COVENANTS, THAT PROPERTY OWNER WILL NOT CONSTRUCT, LOCATE, OR CAUSE TO BE CONSTRUCTED OR LOCATED ANY ADDITION OR IMPROVEMENT TO ANY HOUSE, APARTMENT, DWELLING, MOBILE HOME, GARAGE, OUT BUILDING, EQUIPMENT SHELTER, FARM OR LIVESTOCK FACILITIES, STORAGE BARNs, HUNTING STRUCTURES, OR STORAGE SHEDS, WHICH ARE LOCATED IN THE VICINITY OF PEC'S EASEMENT IN SUCH A WAY THAT THE ADDITION OR IMPROVEMENT WILL BE LOCATED, EITHER IN WHOLE OR IN PART, WITHIN PEC'S EASEMENT.
6. DUMPSTERS, STAGING OF MATERIAL OR EQUIPMENT, AND SPOIL PILES ARE NOT PERMITTED WITHIN PEC'S EASEMENTS.
7. THE PROJECT SHALL NOT INTERFERE WITH PEC'S 24-HOUR ACCESS TO ELECTRIC FACILITIES AND EASEMENTS.
8. TEMPORARY OR PERMANENT SECURITY FENCING SHALL NOT PREVENT PEC'S ACCESS OR CROSSING OF THE TRANSMISSION EASEMENT(S). THE OWNER SHALL INSTALL GATE(S) WITH PEC COMPANY LOCK AS REQUIRED BY PEC TO MAINTAIN ACCESS.
9. PROPERTY OWNER IS RESPONSIBLE FOR DUST CONTROL TO PREVENT INSULATOR FLASHOVER DUE TO CONTAMINATION. PROPERTY OWNER IS RESPONSIBLE FOR ALL OUTAGES THAT PEC DETERMINES TO HAVE RESULTED OR ARISEN FROM DUST FROM THIS PROJECT.
10. PROPERTY OWNER WILL BE BILLED FOR ANY OUTAGES AND REPAIRS THAT PEC DETERMINES TO HAVE RESULTED OR ARISEN FROM THIS PROJECT.
11. PROPERTY OWNER IS RESPONSIBLE FOR ALL DAMAGES TO CURBING, SIDEWALKS, LANDSCAPING, WALLS, AND OTHER IMPROVEMENTS MADE WITHIN PEC'S ELECTRIC TRANSMISSION EASEMENT.

NORTH SAN GABRIEL MUNICIPAL UTILITIES DISTRICT NO.1

1. THE DISTRICT ENGINEER, JONES-HEROY & ASSOCIATES, INC. (KEN HEROY, PH. 512-989-2200) SHALL BE CONTACTED 48 HOURS PRIOR TO:
  - I) PRE-CONSTRUCTION MEETINGS;
  - II) BEGINNING EACH PHASE OF CONSTRUCTION;
  - III) TESTING OF WATER AND/OR WASTEWATER LINES; AND,
  - IV) FINAL WALK-THROUGH OF FACILITIES

STREET DESIGN TABLE									
STREET NAME	CLASSIFICATION	DESIGN SPEED	LENGTH	ROW WIDTH	PAVEMENT WIDTH	RURAL / URBAN	MAINTENANCE AUTHORITY	DRAINAGE TYPE	SIDEWALK
RANDOLPH DRIVE	LOCAL	25	1455.34'	50'	33' F-F	URBAN	PUBLIC	CURB & GUTTER	5' BOTH SIDES
RANDOLPH COURT	LOCAL	25	417.88'	50'	33' F-F	URBAN	PUBLIC	CURB & GUTTER	5' BOTH SIDES

DESIGNED PER AASHTO STANDARDS.

APR

DATE

DESCRIPTION

REV

DESIGNED BY: MTC

REVIEWED BY: MTC

DRAWN BY: MTC

BGE

BGE, INC.

101 W. Louis Henna Blvd, Suite 400

AUSTIN, TX 78728

TYPE Registration No. F-1046

TEL 512.679-0060 [www.bgeinc.com](http://www.bgeinc.com)

NORTHGATE RANCH PHASE 3 - SECTION 17

WILLIAMSON COUNTY, TEXAS

NOTES (SHEET 2 OF 2)

10-17-22

NATHAN D. KELLY

141451

LICENSED PROFESSIONAL ENGINEER

SHEET  
3 OF 39











G:\TXC\Projects\Randolph Todd Col 10892-00-Northgate\_Ph3\_Sect7\LD01\_CADD\LD01\_Sht10892-C-SP-STRM-OVRL.dwg Layout: 15 STORM INLET CAPACITY CALCULATIONS Plotted: 10/17/2022 8:12:21 AM

Drainage Basin	DRAINAGE AREA	AREA (SF)	AREA (Acres)	Home Impervious 7,000 SF IC	Home Impervious 5,000 SF IC	Home Impervious 3,500 SF IC	Additional Impervious (1000 SF)	5' Sidewalk (FT)	1/2 Street 33' F.F (LF)	Impervious Cover (Acres)	Offsite Pervious Cover (Acres)	Onsite Pervious Cover (Acres)	%IC	10 year								25 year								100 year							
														perv C offsite		perv C onsite		imp C		weighted C		perv C offsite		perv C onsite		imp C		weighted C		perv C offsite		perv C onsite		imp C		weighted C	
														C Value	C x A	C Value	C x A	C Value	C x A			C Value	C x A	C Value	C x A	C Value	C x A			C Value	C x A	C Value	C x A	C Value	C x A		
OUTFALL A	A0	66,999	1.54	0.50	1.00	0.00	0.0	391	409	0.400	0.000	1.138	25.99%	0.40	0.00	0.35	0.40	0.81	0.32	0.47		0.42	0.00	0.39	0.44	0.86	0.34	0.51		0.49	0.00	0.46	0.52	0.95	0.38	0.59	
	A1	125,558	2.88	0.50	3.00	0.00	0.0	249	249	0.550	0.000	2.332	19.10%	0.40	0.00	0.35	0.82	0.81	0.45	0.44		0.42	0.00	0.39	0.91	0.86	0.47	0.48		0.49	0.00	0.46	1.07	0.95	0.52	0.55	
	A2	142,746	3.28	0.00	2.25	0.00	0.0	1007	858	0.709	0.851	7.717	21.63%	0.40	0.34	0.35	0.60	0.81	0.57	0.46		0.42	0.36	0.39	0.67	0.86	0.61	0.50		0.49	0.42	0.46	0.79	0.95	0.67	0.57	
	A3	159,913	3.67	1.00	1.25	0.00	0.0	177	170	0.391	1.430	1.850	10.65%	0.40	0.57	0.35	0.65	0.81	0.32	0.42		0.42	0.60	0.39	0.72	0.86	0.34	0.45		0.49	0.70	0.46	0.85	0.95	0.37	0.52	
	A4.0	139,306	3.20	0.00	1.50	0.00	0.0	164	157	0.252	1.977	0.968	7.89%	0.40	0.79	0.35	0.34	0.81	0.20	0.42		0.42	0.83	0.39	0.38	0.86	0.22	0.45		0.49	0.97	0.46	0.45	0.95	0.24	0.52	
	A4.1	36,704	0.84	0.00	0.00	2.00	0.0	464	509	0.413	0.048	0.382	48.96%	0.40	0.02	0.35	0.13	0.81	0.33	0.58		0.42	0.02	0.39	0.15	0.86	0.35	0.62		0.49	0.02	0.46	0.18	0.95	0.39	0.70	
	A5.0	42,734	0.98	0.00	0.00	0.00	0.0	1240	1242	0.627	0.000	0.354	63.89%	0.40	0.00	0.35	0.12	0.81	0.51	0.64		0.42	0.00	0.39	0.14	0.86	0.54	0.69		0.49	0.00	0.46	0.16	0.95	0.60	0.77	
	A5.1	7,347	0.17	0.00		0.00	0.0	256	273	0.136	0.000	0.033	80.58%	0.40	0.00	0.35	0.01	0.81	0.11	0.72		0.42	0.00	0.39	0.01	0.86	0.12	0.77		0.49	0.00	0.46	0.02	0.95	0.13	0.85	
OFFSITE	OS-A	154,693	3.55	1.00	1.00	0.00	0.0	0	0	0.275	1.588	1.688	7.76%	0.40	0.64	0.35	0.59	0.81	0.22	0.41		0.42	0.67	0.39	0.66	0.86	0.24	0.44		0.49	0.78	0.46	0.78	0.95	0.26	0.51	
	OS-B	346,196	7.95	2.00	6.00	0.00	0.0	0	0	1.010	0.000	6.937	12.71%	0.40	0.00	0.35	2.43	0.81	0.82	0.41		0.42	0.00	0.39	2.71	0.86	0.87	0.45		0.49	0.00	0.46	3.19	0.95	0.96	0.52	
	OS-C	209,524	4.81	0.00	0.00	0.00	0.0	0	0	0.000	3.227	1.583	0.00%	0.40	1.29	0.35	0.55	0.81	0.00	0.38		0.42	1.36	0.39	0.62	0.86	0.00	0.41		0.49	1.58	0.46	0.73	0.95	0.00	0.48	

ONSITE AREA (AC)	26.918
ONSITE IC (AC)	4.406
% IC	16.37%

DRAINAGE AREA	AREA (acres)	COMPOSITE C			A-C <sub>10</sub>	A-C <sub>25</sub>	A-C <sub>100</sub>	SHEET FLOW				SHALLOW CONCENTRATED FLOW				STREET GUTTER FLOW					Cumulative Tc (min)	INTENSITY			DISCHARGE		
		C <sub>10</sub>	C <sub>25</sub>	C <sub>100</sub>				Length (ft)	Manning's (n)	Slope ft/ft	Tc (min)	Length (ft)	Paved? (YES/NO)	Slope ft/ft	Tc (min)	Length (ft)	Manning's (n)	Slope ft/ft	Velocity ft/s	Tc (min)		I 10yr (in/hr)	I 25yr (in/hr)	I 100yr (in/hr)	Q 10 (cfs)	Q 25 (cfs)	Q 100 (cfs)
ULTIMATE CONDITION DRAINAGE AREAS																											
A0	1.538	0.47	0.51	0.59	0.72	0.79	0.90	100	0.240	0.010	18.16	33	NO	0.010	0.339	395	0.015	0.025	6.1	1.1	19.58	5.7	6.6	8.2	4.1	5.2	7.4
A1	2.882	0.44	0.48	0.55	1.26	1.38	1.60	100	0.240	0.010	18.16	239	NO	0.010	2.466	249	0.015	0.005	2.7	1.5	22.15	5.4	6.3	7.7	6.8	8.7	12.4
A2	3.277	0.46	0.50	0.57	1.52	1.64	1.88	100	0.240	0.010	18.16	1193	NO	0.010	12.326	447	0.015	0.005	2.7	2.7	33.22	4.4	5.2	6.4	6.6	8.5	12.1
A3	3.671	0.42	0.45	0.52	1.54	1.66	1.92	100	0.240	0.010	18.16	1289	NO	0.010	13.314	262	0.015	0.043	8.0	0.5	32.02	4.5	5.3	6.5	6.9	8.8	12.6
A4.0	3.198	0.42	0.45	0.52	1.33	1.43	1.65	100	0.240	0.010	18.16	1065	NO	0.010	11.001	163	0.015	0.043	8.0	0.3	29.50	4.7	5.5	6.8	6.2	7.8	11.3
A4.1	0.843	0.58	0.62	0.70	0.49	0.52	0.59	100	0.240	0.015	15.44	166	NO	0.015	1.396	427	0.015	0.005	2.7	2.6	19.46	5.7	6.7	8.2	2.8	3.5	4.8
A5.0	0.981	0.64	0.69	0.77	0.63	0.68	0.76	17	0.015	0.030	0.30	0	NO	0.020	0.000	1240	0.015	0.043	8.0	2.6	5.00	8.6	9.8	11.9	5.5	6.7	9.0
A5.1	0.169	0.72	0.77	0.85	0.12	0.13	0.14	25	0.015	0.030	0.42	0	NO	0.020	0.000	257	0.015	0.005	2.7	1.6	5.00	8.6	9.8	11.9	1.1	1.3	1.7
OS-A	3.551	0.41	0.44	0.51	1.45	1.56	1.82	100	0.240	0.015	15.44	1272	NO	0.015	10.726	0	0.015	0.020	5.4	0.0	26.17	5.0	5.8	7.2	7.2	9.1	13.1
OS-B	7.948	0.41	0.45	0.52	3.25	3.57	4.15	100	0.240	0.015	15.44	307	NO	0.015	2.585	0	0.015	0.020	5.4	0.0	18.03	5.9	6.9	8.4	19.1	24.5	35.0
OS-C	4.810	0.38	0.41	0.48	1.84	1.97	2.31	100	0.240	0.015	15.44	1054	NO	0.015	8.888	0	0.015	0.020	5.4	0.0	24.33	5.1	6.0	7.4	9.5	11.9	17.2

STREET FLOW AND INLET CALCULATIONS  
25 YEAR STORM




Inlet No.	Inlet	Drainage	Q 25	Q pass	Q total	STREET CAPACITY						INLET ON GRADE CAPACITY										SUMP INLET CAPACITY							
						Street Width Face-of-Curb to Face-of-Curb	Gutter Slope	a	Z	Yo	Ponded Width	Reduction Factor	Qa/La	La	Length	L/La	a/Yo	Q/Qa	Qa (this is the capacity of your inlet)	Q pass	Pass To Inlet	Clogging Factor	Q total	Length	W	Opening Height	Cw	Co	h
	Type	Area	(cfs)	(cfs)	(cfs)	(ft)	(%)	(ft)		(ft)	(ft)	(%)		(ft)	(ft)			(cfs)	#	(%)	(cfs)	(ft)	(ft)	(ft)			(ft)		
A0	GRADE	1.54	5.23	0.00	5.23	33	2.50%	0.42	33	0.26	8.70	0%	0.72	7.23	10	1.38	1.59	0.72	7.2	0.00									
A1	GRADE	2.88	8.70	0.00	8.70	33	0.50%	0.42	33	0.43	14.25	0%	0.90	9.67	15	1.55	0.97	0.64	13.5	0.00									
A2	GRADE	3.28	8.49	0.00	8.49	33	0.50%	0.42	33	0.43	14.12	0%	0.90	9.47	15	1.58	0.98	0.63	13.4	0.00									
A3	GRADE	3.67	8.76	0.00	8.76	33	4.30%	0.42	33	0.29	9.54	0%	0.75	11.71	15	1.28	1.45	0.78	11.2	0.00									
A4.0	SUMP	3.20	7.85	0.00	7.85	33	4.30%	0.42	33	0.28	9.16										10%	11.3	15	3	0.583	2.3	0.67	0.28	
A4.1	SUMP	0.84	3.49	0.00	3.49	33	0.50%	0.42	33	0.31	10.11										10%	11.3	15	3	0.583	2.3	0.67	0.28	
A5.0	SUMP	0.98	6.66	0.00	6.66	33	4.30%	0.42	33	0.26	8.61										10%	7.9	10	3	0.583	2.3	0.67	0.40	
A5.1	SUMP	0.17	1.28	0.00	1.28	33	0.50%	0.42	33	0.21	6.94										10%	7.9	10	3	0.583	2.3	0.67	0.40	

STREET FLOW AND INLET CALCULATIONS  
100 YEAR STORM


Inlet No.	Inlet Type	Drainage Area (ac)	Q 100 (cfs)	Q pass (cfs)	Q total (cfs)	STREET CAPACITY						INLET ON GRADE CAPACITY										SUMP INLET CAPACITY		
-----------	------------	--------------------	-------------	--------------	---------------	-----------------	--	--	--	--	--	-------------------------	--	--	--	--	--	--	--	--	--	---------------------	--	--







G:\TXC\Projects\Randolph Todd Col 10892-00-Northgate\_Ph3\_Sect7\LD01\_CADD\01\_Shts\10892-C-SP-STRM.dwg Layout: 16 STORM SEWER LINE A (STA. 1+00 TO 5+00) Plotted: 10/17/2022 8:13:46 AM



- NOTES:
- ALL INLET WYE CONNECTIONS TO BE 45 DEGREES UNLESS OTHERWISE NOTED.
  - ALL STORM LATERALS TO BE 18" CLASS III RCP UNLESS OTHERWISE NOTED.



Curve Table: Alignments					
CURVE	DELTA ANGLE	RADIUS	ARC LENGTH	CHORD DIRECTION	CHORD DISTANCE
C1	60°29'26"	480.00'	506.78'	N48° 12' 31.52"E	483.55'



NORTHGATE RANCH PHASE 3 - SECTION 17  
WILLIAMSON COUNTY, TEXAS  
STORM SEWER LINE A (STA. 1+00 TO 5+00)






DESIGNED BY:	MTC
REVIEWED BY:	MTC
DRAWN BY:	MTC
DATE	APR
DESCRIPTION	

**BGE**





BGE, INC.  
101 W. Louis Henna Blvd. Suite 400  
AUSTIN, TX 78728  
TXPE Registration No. F-1046  
TEL 512.679.9060 www.bgeinc.com



G:\TXC\Projects\Randolph Todd Col 10862-00-Northgate\_Ph3\_Sect7\LD01\_CADD\01\_Shts\10862-C-SP-STRM.dwg Layout: 17 STORM SEWER LINE A (STA. 5+00 TO END) Plotted: 10/17/2022 8:14:06 AM



- NOTES:
- ALL INLET WYE CONNECTIONS TO BE 45 DEGREES UNLESS OTHERWISE NOTED.
  - ALL STORM LATERALS TO BE 18" CLASS III RCP UNLESS OTHERWISE NOTED.



NORTHGATE RANCH PHASE 3 - SECTION 17  
WILLIAMSON COUNTY, TEXAS  
STORM SEWER LINE A (STA. 5+00 TO END)





DATE	REV	DESCRIPTION
APR		




BGE, INC.  
101 W. Louis Harris Blvd. Suite 400  
AUSTIN, TX 78728  
TELEPHONE: (512) 590-0000  
WWW.BGE.COM





### LEGEND


- 
 PROPERTY BOUNDARY  
 PHASE BOUNDARY  
 EXISTING MINOR CONTOUR  
 EXISTING MAJOR CONTOUR  
 PROPOSED MINOR CONTOUR  
 PROPOSED MAJOR CONTOUR  
 STORM SEWER FLOW DIRECTION  
 BOX MANHOLE  
 MANHOLE  
 10' CURB INLET

NOTES:

1. ALL INLET WYE CONNECTIONS TO BE 45 DEGREES UNLESS OTHERWISE NOTED.
2. ALL STORM LATERALS TO BE 18" CLASS III RCP UNLESS OTHERWISE NOTED.

## PROFILE LEGEND

- 



△	REV	DESCRIPTION	DATE	APR
DESIGNED BY:	MTG			
REVIEWED BY:	MTG			
DRAWN BY:	MTG			



**BGE, INC.**  
101 W Louis Henna Blvd, Suite 400  
AUSTIN, TX 78728  
TBPE Registration No. F-1046  
TEL: 512-879-0400 [www.bgeinc.com](http://www.bgeinc.com)



G:\TxC\Projects\Randolph\_Todd\_Col\10892-00-Northgate\_Ph3\_Sec7\LD01\_CADD\01\_Shts\10892-C-EROS-DTEL.dwg Layout: 25 EROSION DETAILS (SHEET 1 OF 2) Plotted: 10/17/2022 8:10:17 AM

- ALL TREES NOT LOCATED WITHIN THE LIMITS OF CONSTRUCTION AND OUTSIDE OF DISTURBED AREAS SHALL BE PRESERVED. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING ALL TREES TO BE PRESERVED FROM HIS ACTIVITIES.
- ALL TREES SHOWN TO BE RETAINED WITHIN THE LIMITS OF CONSTRUCTION ON THE PLANS, SHALL BE PROTECTED DURING CONSTRUCTION WITH FENCING. SEE: TREE PROTECTION TREE WELLS (EC-02), TREE PROTECTION TREE LOCATION (EC-03) AND TREE PROTECTION FENCE-CHAIN LINK (EC-04).
- TREE PROTECTION FENCES SHALL BE ERECTED ACCORDING TO CITY STANDARDS FOR TREE PROTECTION, INCLUDING TYPES OF FENCING AND SIGNAGE.
- TREE PROTECTION FENCES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING, OR GRADING) AND SHALL BE MAINTAINED THROUGHOUT ALL PHASES OF THE CONSTRUCTION PROJECT.
- EROSION AND SEDIMENTATION CONTROL BARRIERS SHALL BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILD-UP WITHIN TREE DRIPLINES.
- FENCES SHALL COMPLETELY SURROUND THE TREE OR CLUSTERS OF TREES, LOCATED AT THE OUTERMOST LIMITS OF THE TREE BRANCHES (DRIPLINE) OR CRITICAL ROOT ZONE (CRZ), WHICHEVER IS GREATER, AND SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROJECT IN ORDER TO PREVENT THE FOLLOWING:
  - SOIL COMPACTION IN CRZ AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF EQUIPMENT OR MATERIAL.
  - CRZ DISTURBANCES DUE TO GRADE CHANGES OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE FORESTRY MANAGER.
  - WOUNDS TO EXPOSED ROOTS, TRUNK, OR LIMBS BY MECHANICAL EQUIPMENT.
  - OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CONCRETE TRUCK CLEANING, AND FIRES.
- EXCEPTIONS TO INSTALLING TREE FENCES AT THE TREE DRIPLINES OR CRZ, WHICHEVER IS GREATER, MAY BE PERMITTED IN THE FOLLOWING CASES:
  - WHERE THERE IS TO BE AN APPROVED GRADE CHANGE, IMPERMEABLE PAVING SURFACE, OR TREE WELL.
  - WHERE PERMEABLE PAVING IS TO BE INSTALLED, ERECT THE FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA.
  - WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE NO CLOSER THAN 6 FEET TO THE BUILDING.
  - WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE, OR OTHER SPECIAL REQUIREMENTS, CONTACT THE FORESTRY MANAGER TO DISCUSS ALTERNATIVES.
- WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE THAT IS CLOSER THAN 5 FEET TO A TREE TRUNK, THE TRUNK SHALL BE PROTECTED BY STRAPPED-ON PLANKING TO A HEIGHT OF 8 FEET (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING PROVIDED.
- WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN AREAS OF UNPROTECTED ROOT ZONES UNDER THE DRIPLINE OR CRZ, WHICHEVER IS GREATER, THOSE AREAS SHOULD BE COVERED WITH 4 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION.
- ALL GRADING WITHIN CRZ AREAS SHALL BE DONE BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE. PRIOR TO GRADING, RELOCATE PROTECTIVE FENCING TO 2 FEET BEHIND THE GRADE CHANGE AREA.
- ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL AND BACKFILLED WITH GOOD QUALITY TOP SOIL WITHIN TWO DAYS. IF EXPOSED ROOT AREAS CANNOT BE BACKFILLED WITHIN 2 DAYS, AN ORGANIC MATERIAL WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION SHALL BE PLACED TO COVER THE ROOTS UNTIL BACKFILL CAN OCCUR.
- PRIOR TO EXCAVATION OR GRADE CUTTING WITHIN TREE DRIPLINES, A CLEAN CUT SHALL BE MADE WITH A ROCK SAW OR SIMILAR EQUIPMENT, IN A LOCATION AND TO A DEPTH APPROVED BY THE FORESTRY MANAGER, TO MINIMIZE DAMAGE TO REMAINING ROOTS.
- TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES WILL BE WATERED DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. TREE CROWNS ARE TO BE SPRAYED WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON LEAVES.
- WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, A PLASTIC VAPOR BARRIER SHALL BE PLACED BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO THE CRZ.
- ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE.
- NO LANDSCAPE TOPSOIL DRESSING GREATER THAN FOUR (4) INCHES SHALL BE PERMITTED WITHIN THE DRIPLINE OR CRZ OF TREES, WHICHEVER IS GREATER. NO TOPSOIL IS PERMITTED ON ROOT FLARES OF ANY TREE.
- PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC, AND CONSTRUCTION EQUIPMENT SHALL TAKE PLACE BEFORE CONSTRUCTION BEGINS. ALL PRUNING MUST BE DONE ACCORDING TO CITY STANDARDS AND AS OUTLINED IN LITERATURE PROVIDED BY THE INTERNATIONAL SOCIETY OF ARBORICULTURE (ISA PRUNING TECHNIQUES).
- ALL OAK TREE CUTS, INTENTIONAL OR UNINTENTIONAL, SHALL BE SEALED WITH AN APPROVED PRUNING SEALER IMMEDIATELY (WITHIN 10 MINUTES). TREE PAINT MUST BE KEPT ON SITE AT ALL TIMES.
- THE FORESTRY MANAGER HAS THE AUTHORITY TO REQUIRE ADDITIONAL TREE PROTECTION BEFORE OR DURING CONSTRUCTION.
- TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED. REFER TO THE CITY OF ROUND ROCK TREE TECHNICAL MANUAL FOR APPROPRIATE REMOVAL METHODS.
- PRIOR TO CONSTRUCTION, ALL LOWER TREE LIMBS OVER ROADWAYS MUST BE PRUNED TO A HEIGHT OF 14 FEET USING THE TECHNIQUES DESCRIBED IN THE CITY OF ROUND ROCK TREE TECHNICAL MANUAL.
- DEVIATIONS FROM THE ABOVE REQUIREMENTS AND NEGLIGENT DAMAGE TO TREES MAY BE CONSIDERED AS ORDINANCE VIOLATIONS.


FOR QUESTIONS CONCERNING THIS DETAIL, PLEASE CONTACT THE FORESTRY MANAGER.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO. EC-01

### TREE PROTECTION NOTES



CROSS SECTION

#### NOTES:


- STONE SIZE SHALL BE 3" - 8" OPEN GRADED ROCK.
- THICKNESS OF CRUSHED STONE PAD TO BE NOT LESS THAN 8".
- LENGTH SHALL BE A MINIMUM OF 50' FROM ACTUAL ROADWAY, AND WIDTH NOT LESS THAN FULL WIDTH OF INGRESS/EGRESS.
- ENTRANCE SHALL BE PROPERLY GRADED TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
- THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS OF WAY MUST BE REMOVED IMMEDIATELY BY CONTRACTOR.
- AS NECESSARY, WHEELS MUST BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK



DRAWING NO. EC-09

### STABILIZED CONSTRUCTION ENTRANCE DETAIL



PERMANENT PROTECTIVE WALL

OPEN TREE WELL



TREE WELL WITH RAISED GRADE

#### NOTE:

LOCATION, TYPE, DEPTHS AND CONSTRUCTION SPECIFICATIONS OF FILL, DRAINS AND WALLS SHALL BE SUBJECT TO THE APPROVAL OF THE FORESTRY MANAGER.


FOR QUESTIONS CONCERNING THIS DETAIL, PLEASE CONTACT THE FORESTRY MANAGER.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK


DRAWING NO. EC-02

### TREE PROTECTION TREE WELLS



LINEAR CONSTRUCTION THROUGH TREES

TREES IN PAVING AREA




NATURAL AREAS

TREES NEAR CONSTRUCTION ACTIVITY

#### NOTE:

LIMITS OF MULCH AREAS AND DISTANCE FROM TRUNKS TO WORK/ PERMEABLE PAVING AREAS SHALL BE SUBJECT TO THE APPROVAL OF THE FORESTRY MANAGER.



INDIVIDUAL TREE

FENCING AT CRZ.

FENCING AT CRZ, (TYP.)

GROUP OF TREES


FOR QUESTIONS CONCERNING THIS DETAIL, PLEASE CONTACT THE FORESTRY MANAGER.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO. EC-03


### TREE PROTECTION FENCE LOCATIONS



TREE PROTECTION FENCE - CHAIN LINK

#### NOTE:

LIMITS OF WOOD CHIP MULCH AREA AND DISTANCE FROM TRUNK TO WORK AREA SHALL BE SUBJECT TO THE APPROVAL OF THE FORESTRY MANAGER.



TREE PROTECTION FENCE (MODIFIED) - CHAIN LINK


FOR QUESTIONS CONCERNING THIS DETAIL, PLEASE CONTACT THE FORESTRY MANAGER.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO. EC-04

### TREE PROTECTION FENCE CHAIN LINK



ISOMETRIC

CROSS SECTION

#### NOTES:


- USE ONLY OPEN GRADED ROCK (3 to 5") DIAMETER FOR ALL CONDITIONS.
- THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 1" OPENING AND MINIMUM WIRE DIAMETER OF 20 GAUGE.
- THE ROCK BERM SHALL BE INSPECTED DAILY OR AFTER EACH RAIN, AND THE STONE AND/ OR FABRIC CORE-WOVEN SHEATHING SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED, DUE TO SEDIMENT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
- IF SEDIMENT REACHES A DEPTH OF 6", THE SEDIMENT SHALL BE REMOVED AND DISPOSED OF ON AN APPROVED SITE AND IN A MANNER THAT WILL NOT CREATE A SEDIMENTATION PROBLEM.
- WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SEDIMENT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO. EC-12

### ROCK BERM DETAIL



ISOMETRIC

CROSS SECTION

#### NOTES:

- WHERE MINIMUM CLEARANCES CAUSE TRAFFIC TO DRIVE IN THE GUTTER, THE CONTRACTOR MAY SUBSTITUTE A 1" X 4" BOARD SECURED WITH CONCRETE NAILS 3" O.C. NAILED INTO THE GUTTER IN LIEU OF SANDBAGS TO HOLD THE FILTER DIKE IN PLACE. UPON REMOVAL, CLEAN ANY DIRT/DEBRIS FROM NAILING LOCATIONS, APPLY CHEMICAL SANDING AGENT AND APPLY NON-SHRINK GROUT FLUSH WITH SURFACE OF GUTTER.
- A SECTION OF FILTER FABRIC SHALL BE REMOVED AS SHOWN ON THIS DETAIL OR AS DIRECTED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR HOG RINGS AT THIS LOCATION.
- DAILY INSPECTION SHALL BE MADE BY THE CONTRACTOR AND SILT ACCUMULATION MUST BE REMOVED WHEN DEPTH REACHES 2".
- CONTRACTOR SHALL MONITOR THE PERFORMANCE OF INLET PROTECTION DURING EACH RAINFALL EVENT AND IMMEDIATELY REMOVE THE INLET PROTECTIONS IF THE STORM-WATER BEGINS TO OVERTOP THE CURB.
- INLET PROTECTIONS SHALL BE REMOVED AS SOON AS THE SOURCE OF SEDIMENT IS STABILIZED.

RECORD SIGNED COPY ON FILE AT PUBLIC WORKS
APPROVED
03-25-11
DATE
THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS DETAIL. (NOT TO SCALE)

CITY OF ROUND ROCK

DRAWING NO. EC-14

### CURB INLET PROTECTION DETAIL




NORTHGATE RANCH PHASE 3 - SECTION 17

WILLIAMSON COUNTY, TEXAS

EROSION DETAILS (SHEET 1 OF 2)







CONCRETE  
WASHOUT AREA


- | CONCRETE WASHOUT AREA INSTALLATION NOTES  | CONCRETE WASHOUT AREA MAINTENANCE NOTES  |
|---|--|
| 1. CONTRACTOR SHALL SELECT A SUITABLE LOCATION FOR CONCRETE WASHOUT AREA(S). (TO BE PLACED A MINIMUM OF 100' FROM DRAINAGEWAYS, BODIES OF WATER, AND INLETS.)   | 1. THE CONCRETE WASHOUT AREA SHALL BE REPAIRED AND ENLARGED OR CLEANED OUT AS NECESSARY TO MAINTAIN CAPACITY FOR WASTED CONCRETE.                                  |
| 2. LOCATION FOR CONCRETE WASHOUT SHALL BE ADDED TO APPROVED SWP3 KEPT ON SITE.  | 2. AT THE END OF CONSTRUCTION, ALL CONCRETE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN APPROVED WASTE SITE.  |
| 3. THE CONCRETE WASHOUT AREA SHALL BE INSTALLED PRIOR TO ANY CONCRETE PLACEMENT ON SITE.  | 3. WHEN THE CONCRETE WASHOUT AREA IS REMOVED, THE DISTURBED AREA SHALL BE DRILL SEEDED AND CRIMP MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE CITY. |
| 4. VEHICLE TRACKING CONTROL (DETAIL E-803) IS REQUIRED AT THE ACCESS POINT.   | 4. INSPECT WEEKLY, DURING AND AFTER ANY STORM EVENT.   |
| 5. SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE WASHOUT AREA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CONCRETE WASHOUT AREA TO OPERATORS OF CONCRETE TRUCKS AND PUMP RIGS. | 5. IMMEDIATELY REPAIR/REPLACE PLASTIC LINING IN THE EVENT OF TEARS, HOLES, OR OTHER DEFECTS THAT COMPROMISE IMPERMEABILITY.  |
| 6. EXCAVATED MATERIAL SHALL BE UTILIZED IN PERIMETER BERM CONSTRUCTION.   |  |

[illegible]



[illegible]









CITY OF AUSTIN	STANDARD HEADWALL AND
----------------	-----------------------

37

--	--	--	--



G:\TXC\Projects\Randolph Todd Col\10882-00-Northgate\_Ph3\_Sec7\LD01\_CADD\01\_Shts\10882-C-STRM-DET1.dwg Layout: DRAINAGE DETAILS (SHEET 2 OF 4) Plotted: 10/17/2022 8:20:22 AM



NORTHGATE RANCH PHASE 3 - SECTION 17

WILLIAMSON COUNTY, TEXAS


DRAINAGE DETAILS (SHEET 2 OF 4)






G:\TXC\Projects\Ranchgate Todd Col\10892-00-Northgate\_Ph3\_Sect7\LD01\_CADD\01\_Shts\10892-C-STRM-DET1.dwg Layout: DRAINAGE DETAILS (SHEET 3 OF 4) Plotted: 10/17/2022 8:20:29 AM

The Architect/Engineer assumes responsibility for appropriate use of this standard.




PERPENDICULAR CURB RAMPS

TYPE 1



TYPE 2




TYPE 3

PARALLEL CURB RAMPS



CITY OF GEORGETOWN  
CONSTRUCTION STANDARDS AND DETAILS  
SIDEWALK RAMP DETAILS  
TYPE 1-3

REVISION DATE: ADOPTED 6/21/2006	
DRAWING NAME: SD31	
SOURCE: NTS	DATE: 1/2003
DESIGNED BY: MRS	APPROVED BY: TRB




TRENCH WIDTHS  
\*PIPE LESS THAN 20" DIAMETER  
1'-0" + PIPE O.D.  
\*20" DIAMETER PIPE AND LARGER  
2'-0" + PIPE O.D.

The Architect/Engineer assumes responsibility for appropriate use of this standard.



CITY OF GEORGETOWN  
CONSTRUCTION STANDARDS AND DETAILS  
CONCRETE TRANCHE CAP DETAIL  
FOR STORM SEWER

REVISION DATE: ADOPTED 6/21/2006	
DRAWING NAME: SD39	
SOURCE: NTS	DATE: 1/2003
DESIGNED BY: MRS	APPROVED BY: TRB



TRENCH WIDTHS  
\*PIPE LESS THAN 20" DIAMETER  
1'-0" + PIPE O.D.  
\*20" DIAMETER PIPE AND LARGER  
2'-0" + PIPE O.D.


- NOTES:
1. REPLACED BASE MATERIAL OVER DITCH SHALL BE TWICE THE THICKNESS OF THE ORIGINAL BASE.
  2. BASE MATERIAL SHALL BE IN LIFTS NOT TO EXCEED 6" AND EACH LIFT THOROUGHLY ROLLED OR TAMPED TO SPECIFIED MAXIMUM DENSITY.
  3. ASPHALT CONCRETE PAVEMENT JOINTS SHALL BE MECHANICALLY SAWED.
  4. SURFACE MATERIAL WILL BE CONSISTENT WITH THE EXISTING SURFACE.
  5. DENSITY TESTS SHALL BE TAKEN IN ACCORDANCE WITH THE CITY OF GEORGETOWN CONSTRUCTION SPECIFICATIONS AND STANDARDS.
  6. CONTRACTOR OR ENGINEER MAY USE FLOWABLE BACKFILL AS AN ALTERNATE BACKFILL MATERIAL (SEE C9 FLOWABLE BACKFILL FOR THE SPECIFICATION).

The Architect/Engineer assumes responsibility for appropriate use of this standard.



CITY OF GEORGETOWN  
CONSTRUCTION STANDARDS AND DETAILS  
TRENCH, EMBEDMENT AND PAVEMENT  
REPLACEMENT DETAIL UNDER EXISTING  
ROADWAY FOR STORM SEWER

REVISION DATE: ADOPTED 6/21/2006	
DRAWING NAME: SD40	
SOURCE: NTS	DATE: 1/2003
DESIGNED BY: MRS	APPROVED BY: TRB



- NOTES:
1. DENSITY TESTS SHALL BE TAKEN IN ACCORDANCE WITH THE CITY OF GEORGETOWN CONSTRUCTION SPECIFICATIONS AND STANDARDS.
  2. CONTRACTOR OR ENGINEER MAY USE FLOWABLE BACKFILL AS AN ALTERNATE BACKFILL MATERIAL (SEE C9 FLOWABLE BACKFILL FOR THE SPECIFICATION).


TRENCH WIDTHS  
\*PIPE LESS THAN 20" DIAMETER  
1'-0" + PIPE O.D.  
\*20" DIAMETER PIPE AND LARGER  
2'-0" + PIPE O.D.

The Architect/Engineer assumes responsibility for appropriate use of this standard.



CITY OF GEORGETOWN  
CONSTRUCTION STANDARDS AND DETAILS  
TRENCH AND EMBEDMENT DETAIL  
UNDER PROPOSED ROADWAY  
FOR STORM SEWER

REVISION DATE: ADOPTED 6/21/2006	
DRAWING NAME: SD41	
SOURCE: NTS	DATE: 1/2003
DESIGNED BY: MRS	APPROVED BY: TRB



BEDDING SHALL BE REQUIRED AS PER TYPICAL BEDDING SPECIFICATIONS IN CITY OF GEORGETOWN CONSTRUCTION SPECIFICATIONS.


- NOTES
1. PIPE SHALL BE REINFORCED CONCRETE PIPE CLASS III UNLESS THE DEPTH OF PIPE REQUIRES A STRONGER CLASS.
  2. ALL FITTINGS AND WYES SHALL BE MANUFACTURED AND NOT CONSTRUCTED ON THE PROJECT WITHOUT PRIOR APPROVAL FROM THE CITY.
  3. ALL JOINTS SHALL BE WRAPPED WITH MARFI-140-N GEOTEXTILE FABRIC OR APPROVED EQUIVALENT. EACH JOINT SHALL BE WRAPPED WITH 18" WIDE FABRIC CENTERED ON THE JOINT.

The Architect/Engineer assumes responsibility for appropriate use of this standard.



CITY OF GEORGETOWN  
CONSTRUCTION STANDARDS AND DETAILS  
TRENCH AND EMBEDMENT DETAIL  
(PROFILE) FOR STORM SEWER

REVISION DATE: ADOPTED 6/21/2006	
DRAWING NAME: SD42	
SOURCE: NTS	DATE: 1/2003
DESIGNED BY: MRS	APPROVED BY: TRB



ENGINEERED VEGETATED FILTER STRIP DETAIL (TYP.)  
N.T.S.

V.F.S. NOTES (TCEQ RG348)

1. THE FILTER STRIP SHOULD EXTEND ALONG THE ENTIRE LENGTH OF THE CONTRIBUTING AREA AND THE SLOPE SHOULD NOT EXCEED 20%. THE MINIMUM DIMENSION OF THE FILTER STRIP (IN THE DIRECTION OF FLOW) SHOULD BE NO LESS THAN 15 FEET. THE MAXIMUM WIDTH (IN THE DIRECTION OF FLOW) OF THE CONTRIBUTING IMPERVIOUS AREA SHOULD NOT EXCEED 72 FEET. FOR ROADWAYS WITH A VEGETATED STRIP ALONG BOTH SIDES THE TOTAL WIDTH OF THE ROADWAY SHOULD NOT EXCEED 144 FEET (I.E., 72 FEET DRAINING TO EACH SIDE).
2. THE MINIMUM VEGETATED COVER FOR ENGINEERED STRIPS IS 80%.
3. THE AREA CONTRIBUTING RUNOFF TO A FILTER STRIP SHOULD BE RELATIVELY FLAT SO THAT THE RUNOFF IS DISTRIBUTED EVENLY TO THE VEGETATED AREA WITHOUT THE USE OF A LEVEL SPREADER.
4. THE AREA TO BE USED FOR THE STRIP SHOULD BE FREE OF GULLIES OR RILLS THAT CAN CONCENTRATE OVERLAND FLOW (SCHUELER, 1987).
5. THE TOP EDGE OF THE FILTER STRIP ALONG THE PAVEMENT WILL BE DESIGNED TO AVOID THE SITUATION WHERE RUNOFF WOULD TRAVEL ALONG THE TOP OF THE FILTER STRIP, RATHER THAN THROUGH IT.
6. TOP EDGE OF THE FILTER STRIP SHOULD BE LEVEL. OTHERWISE RUNOFF WILL TEND TO FORM A CHANNEL IN THE LOW SPOT. A LEVEL SPREADER SHOULD NOT BE USED TO DISTRIBUTE RUNOFF TO AN ENGINEERED FILTER STRIP.
7. FILTER STRIPS SHOULD BE LANDSCAPED AFTER OTHER PORTIONS OF THE PROJECT ARE COMPLETED.

NORTHGATE RANCH PHASE 3 - SECTION 17  
WILLIAMSON COUNTY, TEXAS  
DRAINAGE DETAILS (SHEET 3 OF 4)





