

# ORGANIZED SEWAGE COLLECTION SYSTEM

**EDGEWOOD PHASE 2, SECTION 2  
CR175 AND RR 2243  
LEANDER, WILLIAMSON COUNTY, TEXAS**

*Prepared For:*

**M/I HOMES OF AUSTIN, LLC**

7600 N. Capital of Texas Hwy.; Bldg. C, Suite 250  
Austin, TX 78731  
512-770-8503

*Prepared By:*

**KIMLEY-HORN AND ASSOCIATES, INC.**

501 S. Austin Ave, Suite 1310  
Georgetown, Texas 78626  
(512) 520-0768

Firm No. 928  
KHA Project No. 067783129

November 7th, 2023



*Alejandro E. Granados Rico*

11/07/2023

## Table of Contents

EDWARDS AQUIFER APPLICATION COVER PAGE .....	Section 1
GENERAL INFORMATION .....	Section 2
General Information Form .....	TCEQ-0587
Road Map .....	Attachment A
USGS / Edwards Recharge Zone Map .....	Attachment B
Project Description.....	Attachment C
GEOLOGIC ASSESSMENT .....	Section 3
Geologic Assessment Form .....	TCEQ-0585
Geologic Assessment Table .....	Attachment A
Soil Profile and Narrative of Soil Units.....	Attachment B
Stratigraphic Column .....	Attachment C
Narrative of Site Specific Geology .....	Attachment D
Site Soils Map.....	Attachment E
Features' Table .....	Attachment F
Organized Sewage Collection System .....	Section 4
Organized Sewage Collection System Application Form .....	TCEQ-0584
Engineer's Design Report .....	Attachment A
TEMPORARY STORMWATER .....	Section 5
Temporary Stormwater Form .....	TCEQ-0602
Spill Response Actions .....	Attachment A
Potential Sources of Contamination .....	Attachment B
Sequence of Major Activities .....	Attachment C
Temporary Best Management Practices and Measures.....	Attachment D
Request to Temporarily Seal a Feature.....	Attachment E
Structural Practices .....	Attachment F
Drainage Area Map .....	Attachment G
Temporary Sediment Pond(s) Plans and Calculations.....	Attachment H
Inspection and Maintenance for BMPs .....	Attachment I
Schedule of Interim and Permanent Soil Stabilization Practices .....	Attachment J
LIFT STATION/FORCE MAIN APPLICATION.....	TCEQ-0624
ADDITIONAL FORMS .....	Section 6
Agent Authorization Form.....	TCEQ-0599
Owner Authorization Form .....	TCEQ-XXXXX
Application Fee Form .....	TCEQ-0574
Check Payable to the "Texas Commission on Environmental Quality"	
Core Data Form.....	TCEQ-10400
EXHIBITS.....	Section 7
Civil Design Plan Set .....	Exhibit 1



# **SECTION 1: EDWARDS AQUIFER APPLICATION COVER PAGE**

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited.**
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> Edgewood Phase 2, Section 2					<b>2. Regulated Entity No.:</b> N/A				
<b>3. Customer Name:</b> M/I Homes of Austin, LLC					<b>4. Customer No.:</b> 604305250				
<b>5. Project Type:</b> (Please circle/check one)	<u>New</u>		Modification			Extension		Exception	
<b>6. Plan Type:</b> (Please circle/check one)	WPAP	CZP	<u>SCS</u>	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	<u>Residential</u>		Non-residential			<b>8. Site (acres):</b>		45.27	
<b>9. Application Fee:</b>	\$4,233.00		<b>10. Permanent BMP(s):</b>				Click or tap here to enter text.		
<b>11. SCS (Linear Ft.):</b>	8,466		<b>12. AST/UST (No. Tanks):</b>				N/A		
<b>13. County:</b>	Williamson		<b>14. Watershed:</b>				Brushy Creek		

# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	<u>X</u>
Region (1 req.)	—	—	<u>X</u>
County(ies)	—	—	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Barton Springs/ Edwards Aquifer <u>—</u> Hays Trinity <u>—</u> Plum Creek	<u>—</u> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<u>—</u> Austin <u>—</u> Buda <u>—</u> Dripping Springs <u>—</u> Kyle <u>—</u> Mountain City <u>—</u> San Marcos <u>—</u> Wimberley <u>—</u> Woodcreek	<u>—</u> Austin <u>—</u> Bee Cave <u>—</u> Pflugerville <u>—</u> Rollingwood <u>—</u> Round Rock <u>—</u> Sunset Valley <u>—</u> West Lake Hills	<u>—</u> Austin <u>—</u> Cedar Park <u>—</u> Florence <u>—</u> Georgetown <u>—</u> Jerrell <u>X</u> Leander <u>—</u> Liberty Hill <u>—</u> Pflugerville <u>—</u> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Trinity-Glen Rose	<u>—</u> Edwards Aquifer Authority	<u>—</u> Kinney	<u>—</u> EAA <u>—</u> Medina	<u>—</u> EAA <u>—</u> Uvalde
City(ies) Jurisdiction	<u>—</u> Castle Hills <u>—</u> Fair Oaks Ranch <u>—</u> Helotes <u>—</u> Hill Country Village <u>—</u> Hollywood Park <u>—</u> San Antonio (SAWS) <u>—</u> Shavano Park	<u>—</u> Bulverde <u>—</u> Fair Oaks Ranch <u>—</u> Garden Ridge <u>—</u> New Braunfels <u>—</u> Schertz	NA	<u>—</u> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Alejandro E. Granados Rico, P.E.

Print Name of Customer/Authorized Agent

*Alejandro E. Granados Rico*

11/7/2023

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# SECTION 2: GENERAL INFORMATION

# General Information Form

## Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Alejandro E. Granados Rico, P.E.

Date: November 7th, 2023

Signature of Customer/Agent:



---

## Project Information

1. Regulated Entity Name: Edgewood Phase 2, Section 2
2. County: Williamson
3. Stream Basin: Brushy Creek
4. Groundwater Conservation District (If applicable): N/A
5. Edwards Aquifer Zone:
  - ☒ Recharge Zone
  - ☐ Transition Zone
6. Plan Type:
  - ☐ WPAP
  - ☒ SCS

- ☐ Modification
- ☐ AST
- ☐ UST
- ☐ Exception Request



7. Customer (Applicant):

Contact Person: William Peckman

Entity: M/I Homes of Austin, LLC

Mailing Address: 7600 N. Capital of Texas Hwy.; Bldg. C, Suite 250

City, State: Austin, TX

Zip: 78731

Telephone: 512-770-8503

Fax: N/A

Email Address: kkriegel@mihomes.com

8. Agent/Representative (If any):

Contact Person: Alejandro E. Granados Rico, P.E.

Entity: Kimley-Horn

Mailing Address: 501 S. Austin Ave, Suite 1310

City, State: Georgetown, Texas

Zip: 78626

Telephone: 512-520-0768

Fax: N/A

Email Address: alex.granados@kimley-horn.com

9. Project Location:

- ☒ The project site is located inside the city limits of Leander.  
☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.  
☐ The project site is not located within any city's limits or ETJ.

10. ☒ The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation. South of RR 2243 along CR 175

11. ☒ **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.

12. ☒ **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:

- ☒ Project site boundaries.  
☒ USGS Quadrangle Name(s).  
☒ Boundaries of the Recharge Zone (and Transition Zone, if applicable).  
☒ Drainage path from the project site to the boundary of the Recharge Zone.

13. ☒ **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

- ☒ Survey staking will be completed by this date: 10/31/2023

14. ☒ **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- ☒ Area of the site
- ☒ Offsite areas
- ☒ Impervious cover
- ☒ Permanent BMP(s)
- ☒ Proposed site use
- ☒ Site history
- ☒ Previous development
- ☒ Area(s) to be demolished

15. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site
- ☐ Existing paved and/or unpaved roads
- ☐ Undeveloped (Cleared)
- ☒ Undeveloped (Undisturbed/Uncleared)
- ☐ Other: \_\_\_\_\_

### ***Prohibited Activities***

16. ☒ I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. ☒ I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.


## ***Administrative Information***

18. The fee for the plan(s) is based on:

- ☐ For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
  - ☒ For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
  - ☐ For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
  - ☐ A request for an exception to any substantive portion of the regulations related to the protection of water quality.
  - ☐ A request for an extension to a previously approved plan.
19. ☒ Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:
- ☐ TCEQ cashier
  - ☒ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
  - ☐ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)
20. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
21. ☒ No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.



## ***Road Map***



DIRECTIONS FROM TCEQ HEADQUARTERS TO PROJECT SITE

1. HEAD SOUTH ON PARK 35 CIRCLE, TURNING RIGHT ONTO S IH-35 FRONTAGE ROAD
2. MAKE A "U" TURN AT E. BRAKER LN, USE LEFT LANE TO TAKE RAMP ONTO IH-35
3. CONTINUE NORTH ON IH-35
4. TAKE EXIT 256 ONTO IH-35 FRONTAGE ROAD TOWARDS CEDAR PARK
5. STAY RIGHT TOWARDS UNIVERSITY BLVD AND TURN LEFT ONTO UNIVERSITY BLVD
6. CONTINUE ONTO RANCH RD 1431 W
7. TURN RIGHT ONTO CR 175 / SAM BASS RD
8. CONTINUE ON CR 175
9. SITE IS LOCATED ON THE RIGHT

SHEET

EX A

Scale:	1"=1000'
Designed by:	AMF
Drawn by:	AMF
Checked by:	AEG
Date:	NOVEMBER, 2023
Project No.	067783129


EDGEWOOD PH 2-2  
LEANDER, TEXAS

**Kimley»Horn**

501 S. AUSTIN AVENUE, SUITE 1310 GEORGETOWN, TX 78626  
PHONE: 512-520-0768  
WWW.KIMLEY-HORN.COM  
© 2021 KIMLEY-HORN AND ASSOCIATES, INC.  
TBPB Firm No. 928

***USGS/Edwards Recharge Zone Map***





SHEET 1  OF 1 SHEETS	Scale: 1:2000	USGS Quadrangle	Edgewood Ph. 2, Section 2 Leander, Williamson County, Texas		<p>         This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.       </p>
	Designed by: AMF				
	Drawn by: AMF				
	Checked by: AEG				
	Date: NOVEMBER, 2023 Project No. 067783129				

## Introduction

The subject site is a largely undeveloped 45.27 acre lot located on CR175 and RR 2243 and within the Full Purpose city limits of the City of Leander. The subject property is part of a larger development, Edgewood, which encompasses ±140 acres and will comprise of residential single-family. This is the last phase of the Edgewood Subdivision.

The site is not located in the Federal Emergency Management Agency's 100-year floodplain according to FIRM 48491Co460F, dated December 20, 2019. The site is located within the Edwards Aquifer Contributing and Recharge Zone according to TCEQ Edwards Aquifer Map.

## Current Tract Conditions

### Legal Description

The legal description is described as 45.27 acres of land out of the John T. Church Survey, Abstract No. 140 and the Milton Hicks Survey, Abstract No. 287 conveyed to Cannon 140 LP by deeds of record in document Nos. 2013049063 of the Official Public Records of Williamson County, Texas.

### Land Use

The lot is zoned for Single-Family Compact (SFC), Single-Family Suburban (SFS), and Single-Family Urban (SFU). The site resides within the Full Purpose city limits of the City of Leander in Williamson County, Texas.

## Existing Drainage Conditions

Under existing conditions, the site has two ridges to the east and west sending flow to one point at the southern property boundary. This flow then travels within a creek and off the property, eventually discharging into Brushy Creek.

## Proposed Development

The proposed Edgewood Phase 2-2 project includes the construction of 114 lots of single-family residential development. Water and wastewater lines will be designed according to City of Leander specifications and connect to City of Leander utility services. Access to the site will be through the proposed Edgewood Phase 2, Section 1 which connects to Edgewood Phase 1-2, and then to Edgewood Phase 1-1, which has two driveways along CR 175. The project proposes 15.02 acres (33.2%) of total impervious cover. Water will be treated according to TCEQ requirements through two on site Batch Detention Ponds and vegetative filter strips. The flow will be discharged to a point south of the site and then flow into Brushy Creek. Proposed flow conditions will not exceed existing conditions.



## **Drainage and Water Quality Analysis**

### **Floodplain Information**

According to the FEMA Flood Insurance Rate Map Panel No. 48491C0460F for Williamson County, effective December, 20, 2019, no portion of the development lies within the 100-yr floodplain (Zone A).

### **On-Site Drainage**

The proposed site will convey runoff through an underground storm pipe system into one Batch detention pond permitted in Phase 2-1 and into two batch detention ponds in Phase 2-2. One pond is permitted and will be built with Phase 2-1. Two ponds will be permitted and built with Edgewood Phase 2-2. Other portions of the site will overland flow over vegetative filter strips. The detention ponds will release the runoff at or below existing condition flow rates onto rock riprap which will then be conveyed south via an existing natural channel. Drainage area maps and calculations are included in the construction set included in the Exhibits Section.

### **Off-Site Drainage**

Under existing conditions, 27.17 acres of offsite water enters the site from the north. The off-site drainage from the north will not be interrupted by development. It will flow through an existing channel through the property and bypass any improvements.

In proposed conditions, once runoff is released from the detention ponds it will enter an existing channel that will eventually outfall into Brushy Creek.

### **Detention and Water Quality**

Water Quality Best Management Practices (BMP) for Edgewood Phase 2-2 will address the water quality requirements for the ultimate area disturbed within this phase. WQP-D (2-2) will be treated by a batch detention pond built with Edgewood Phase 2-1 (Pond B-C) approved with EAPP ID No. 11002983. WQP-C1 will be treated by a batch detention pond (C1) and WQP-C2 will be treated by a batch detention pond (C2). VFS-7, VFS-8, and VFS-9 will be treated by permanent vegetative filter strips. NT-1, NT-2 and NT-3 have a total of 1.70 acres of impervious cover. The NT areas will not be treated by any proposed BMPs. These drainage areas are to meet all water quality requirements per TCEQ requirements. See Permanent Stormwater Section – Attachment C for a breakdown on TSS calculations.

The detention pond requirements used for the purpose of this report are assumed to be based on the requirements outlined by the City of Austin Drainage Criteria Manual. To reduce the flow to pre-developed conditions, two detention ponds (Pond C1 and Pond C2) will be constructed as a part of this development phase to reduce flows to existing conditions.

### **Erosion and Sedimentation Controls**

Temporary erosion and sedimentation controls during construction are proposed on the Erosion Control Plan and include: silt fence, inlet protection, construction staging area, concrete washout, rock berm, and a stabilized construction entrance designed to City of Austin criteria. The land disturbed during construction, including the staging and stockpile areas, will drain into the proposed on-site storm sewer system where it will be conveyed to the proposed detention and water quality ponds located on-site. The detention ponds will discharge onto proposed rock rip rap into an existing drainage channel that cuts through the middle of the site.

## **Sewage Collection System**

The sewage collection system that is within the Edward's Aquifer Recharge Zone will consist of approximately 6,171 LF of 8" SDR 26 ASTM D3034 PVC, 10 LF of 6" SDR 26 ASTM D3034 PVC and 2,285 LF of 4" SDR 26 ASTM D3034 PVC for the force main. All wastewater in Phase 2-2 shall be conveyed via gravity line that ties to a proposed lift station, then pumped via dual 4" force main to the connection point at Phase 2-1. It will then be conveyed via gravity line to a 12" wastewater line built in Fulton Drive and an 8" wastewater line built in Waxahachie Road with the Edgewood Phase 1-2. The wastewater improvements in Phase 2-2 are designed to convey all LUEs associated with the Edgewood development and future offsite improvements. Please see the attached overall Edgewood Wastewater Exhibit below.

# SECTION 3: GEOLOGIC ASSESSMENT


**GEOLOGIC ASSESSMENT  
FOR THE  
APPROXIMATELY 140-ACRE CANNON TRACT PROJECT  
731 COUNTY ROAD 175  
LEANDER, WILLIAMSON COUNTY, TEXAS  
HJN 200183 GA**

**PREPARED FOR:**

**M/I HOMES OF AUSTIN  
AUSTIN, TEXAS**

**PREPARED BY:**

**HORIZON ENVIRONMENTAL SERVICES, INC.  
TBPG FIRM REGISTRATION NO. 50488**



**MARCH 2021**

## TABLE OF CONTENTS

**I. GEOLOGIC ASSESSMENT FORM (TCEQ-0585)**

**II. ATTACHMENTS:**

- A GEOLOGIC ASSESSMENT TABLE
- B STRATIGRAPHIC COLUMN
- C DESCRIPTION OF SITE GEOLOGY
- D SITE GEOLOGIC MAP
- E SUPPORTING INFORMATION
- F ADDITIONAL SITE MAPS
- G SITE PHOTOGRAPHS

# Geologic Assessment

## Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: James Killian



Telephone: 512-328-2430

Date: 2 March 2021

Fax: 512-328-1804

Representing: Horizon Environmental Services, Inc. and TBPG Form Registration No. 50488  
(Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



**Regulated Entity Name:** 140-acre Cannon Tract, 731 County Road 175, Leander, Williamson County, Texas

## Project Information

1. Date(s) Geologic Assessment was performed: 9, 12, 21, 22, and 23 December 2020; 22 and 23 February 2021

2. Type of Project:

☒ WPAP  
☒ SCS

☐ AST  
☐ UST

3. Location of Project:

☒ Recharge Zone  
☐ Transition Zone

☐ Contributing Zone within the Transition Zone

4. ☒ **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. ☒ Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups\* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

**Table 1 - Soil Units, Infiltration Characteristics and Thickness**

Soil Name	Group*	Thickness(feet)
Eckrant cobbly clay, 1-8% slopes (EaD)	D	0-1.0
Eckrant extremely stony clay, 0-3% slopes (EeB)	D	0-1.0
Fairlie clay, 1-2% slopes (FaB)	D	0-3.8

Soil Name	Group*	Thickness(feet)
Georgetown stony clay loam, 1-3% slopes (GsB)	D	0-3.0

*\* Soil Group Definitions (Abbreviated)*

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6. ☒ **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7. ☒ **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
8. ☒ **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale: 1" = 900'

Site Geologic Map Scale: 1" = 900'

Site Soils Map Scale (if more than 1 soil type): 1" = 1000'

9. Method of collecting positional data:

- ☒ Global Positioning System (GPS) technology.  
☐ Other method(s). Please describe method of data collection: \_\_\_\_\_

10. ☒ The project site and boundaries are clearly shown and labeled on the Site Geologic Map.

11. ☒ Surface geologic units are shown and labeled on the Site Geologic Map.

12. ☒ Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.

- ☐ Geologic or manmade features were not discovered on the project site during the field investigation.

13. ☒ The Recharge Zone boundary is shown and labeled, if appropriate.

14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.

- ☐ There are \_\_\_\_\_ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)

☐ The wells are not in use and have been properly abandoned.

☐ The wells are not in use and will be properly abandoned.

☐ The wells are in use and comply with 16 TAC Chapter 76.

- ☒ There are no wells or test holes of any kind known to exist on the project site.

### ***Administrative Information***

15. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.




**ATTACHMENT A**  
**GEOLOGIC ASSESSMENT TABLE**

* DATUM:			8A INFILLING	
2A TYPE	TYPE	2B POINTS		
C	Cave	30	N	None, exposed bedrock
SC	Solution cavity	20	C	Coarse - cobbles, breakdown, sand, gravel
SF	Solution-enlarged fracture(s)	20	O	Loose or soft mud or soil, organics, leaves, sticks, dark colors
F	Fault	20	F	Fines, compacted clay-rich sediment, soil profile, gray or red colors
O	Other natural bedrock features	5	V	Vegetation. Give details in narrative description
MB	Man-made feature in bedrock	30	FS	Flowstone, cements, cave deposits
SW	Swallow hole	30	X	Other materials:
SH	Sinkhole	20		
CD	Non-karst closed depression	5		
Z	Zone, clustered or aligned features	30		

12 TOPOGRAPHY	
Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed	



My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Sheet 1 of 1

TCEQ-0585-Table (Rev. 10-01-04)

**ATTACHMENT B  
STRATIGRAPHIC COLUMN**

Geologic Unit	Hydrologic Unit	Approx. Thickness at Project Site (ft)	Elevation (ft msl)	Depth (ft)
			1000	0
Edwards Limestone (Ked)	Edwards Aquifer	65		
Comanche Peak Limestone (Kc)		50	935	65
Keys Valley Marl (Kkv)		50	885	115
			835	165

**Note: Unit elevation and thickness given with respect to a ground surface elevation of 1000 feet near the southeastern corner of the subject site.**

**ATTACHMENT C  
DESCRIPTION OF SITE GEOLOGY**

Geologic information for the subject site obtained via literature review is provided in Attachment E, Supporting Information.

A geologic assessment of approximately 140 acres located at 731 County Road 175 in Leander, Williamson County, Texas, was conducted pursuant to Texas rules for regulated activities in the Edwards Aquifer Recharge Zone (EARZ) (30 TAC 213). The subject site consists of undeveloped land and an occupied single-family residence. Assessment findings were used to develop recommendations for site construction measures intended to be protective of water resources at the subject site and adjacent areas.


Most of the subject site is located within the Edwards Aquifer Recharge Zone (EARZ) as defined by the Texas Commission on Environmental Quality (TCEQ). The EARZ occurs where surface water enters the subsurface through exposed limestone bedrock containing faults, fractures, sinkholes, and caves (TCEQ, 2005). Approximately 30% of the subject site is in the Edwards Aquifer Contributing Zone. The Contributing Zone of the Edwards Aquifer includes all the watersheds that feed runoff into the rivers and streams that flow over the Recharge Zone (TCEQ, 2004). TCEQ rules regulate activities in the portions of the Contributing Zone that are within the counties already regulated by the Edwards Aquifer Rules. These areas are generally north and west of the Recharge Zone.

The subject site is underlain by the Keys Valley Marl (Kkv), Comanche Peak Limestone (Kc), and the Edwards Limestone (Ked) (USGS, 2006).

Eight naturally occurring geologic features and no man-made features were identified at the subject site. The geologic features and their locations are presented in Attachment D. Further details regarding each feature, as well as site photographs, are presented in Attachments A, E, and G.

**ATTACHMENT D  
SITE GEOLOGIC MAP**





	Date:	11/19/2021	<b>Legend</b> <ul style="list-style-type: none"><li>● Non-Sensitive Geologic Feature</li><li>● Sensitive Geologic Features</li><li>— 5-Foot Contour</li><li>□ Property</li><li>■ Edwards Limestone (Ked)</li><li>■ Comanche Peak Limestone (Kc)</li><li>■ Keys Valley Marl (Kkv)</li></ul>	<b>Attachment D</b> Site Geologic Map 140-Acre Cannon Property 731 County Road 175 Leander, Williamson County, Texas			
	Drawn:	KRS					
	HJN NO:	200183.001 GA					
	Source:	CAPCOG, 2007; Nearmap, 2021; UT-BEG, 1995					



**ATTACHMENT E  
SUPPORTING INFORMATION**

## **1.0 INTRODUCTION AND METHODOLOGY**

This report and any proposed abatement measures are intended to fulfill Texas Commission on Environmental Quality (TCEQ) reporting requirements (TCEQ, 2005). This geologic assessment includes a review of the subject site for potential aquifer recharge and documentation of general geologic characteristics for the subject site. Horizon Environmental Services, Inc. (Horizon) conducted the necessary field and literature studies according to TCEQ *Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones* (TCEQ, 2004).

Horizon walked transects spaced 50 feet apart, mapped the locations of features using a sub-foot accurate Trimble Geo HX handheld GPS, and posted processed data utilizing GPS Pathfinder Office software, topographic maps, and aerial photographs. Horizon also searched the area around any potential recharge features encountered to look for additional features. When necessary, Horizon removed loose rocks and soil (by hand) to preliminarily assess each feature's subsurface extent while walking transects. However, labor-intensive excavation was not conducted during this assessment. Features that did not meet the TCEQ definition of a potential recharge feature (per TCEQ, 2004), such as surface weathering, karren, or animal burrows, were evaluated in the field and omitted from this report.

The results of this survey do not preclude the possibility of encountering subsurface voids or abandoned test or water wells during the clearing or construction phases of the proposed project. If a subsurface void is encountered during any phase of the project, work should be halted until the TCEQ (or appropriate agency) is contacted and a geologist can investigate the feature.

## **2.0 ENVIRONMENTAL SETTING**

### **2.1 LOCATION AND GENERAL DESCRIPTION**

The subject site consists of approximately 140 acres of mostly undeveloped land located at 731 County Road 175, about 1 mile southeast of the intersection of County Road 175 and State Highway 2243 (Leander Road) in Williamson County, Texas (Appendix F, Figure 1). One single-family residence is located on the subject site, but no other previous use of the site was evident upon Horizon's site investigation.

### **2.2 LAND USE**

The subject site comprised mostly vacant rangeland and woodlands at the time of Horizon's site reconnaissance. One single-family residence is located on the site. County Road 175 borders the site to the west and the rest of the site is bounded by rangeland and woodlands. Surrounding lands are generally used for rural residences, farming, and raising livestock.

## 2.3 TOPOGRAPHY AND SURFACE WATER

The subject site is situated on gently sloping terrain within the Turkey Creek–Brushy Creek watershed (TPWD, 2021) (Appendix F, Figures 2 and 3). Surface elevations on the subject site vary from a minimum of approximately 895 feet above mean sea level (amsl) near the southwestern site boundary along County Road 175 to a maximum of approximately 1000 feet amsl near the north-central boundary of the subject site (CAPCOG, 2007). Drainage on the site occurs primarily by overland surface flow from northeast to southwest. In addition, 3 ephemeral tributaries bisect the western, central, and eastern portions of the subject site and drain from north to south.

## 2.4 EDWARDS AQUIFER ZONE

The subject site is found within the Edwards Aquifer Recharge Zone and Edwards Aquifer Contributing Zone (TCEQ, 2021) (Attachment F, Figure 2).

The Recharge Zone is the area where the stratigraphic units constituting the Edwards Aquifer are exposed at the surface and where water may filter into the aquifer through permeable features such as cracks, fissures, caves, and other openings in these layers (TCEQ, 2005). The Recharge Zone includes other geologic formations in proximity to the Edwards Aquifer where such features may create a potential for recharge of surface waters into the Edwards Aquifer.

The Contributing Zone of the Edwards Aquifer includes all the watersheds that feed runoff into the rivers and streams that flow over the Recharge Zone (TCEQ, 2004). Contributing Zones are usually north and west of the Recharge Zone. TCEQ Edwards Aquifer Rules (30 TAC 213) regulate activities within the Recharge and Contributing Zone and areas draining toward it. The TCEQ (and/or local jurisdiction) will require an approved Geologic Assessment as part of a Water Pollution Abatement Plan prior to land disturbance.

## 2.5 SURFACE SOILS

Four soil units are mapped within the subject site (NRCS, 2021) (Appendix F, Figure 4). The soil units are described in further detail below.

Eckrant cobbly clay, 1 to 8% slopes (EaD) consists of cobbly clay in the upper portion and fractured indurated limestone underneath. This soil is calcareous and moderately alkaline. Eckrant cobbly clay is well-drained with rapid runoff and moderate permeability. Typically, this soil is used as rangeland and suited to urban development due to the firm underlying limestone. Some of the limitations of this soil include the stones and cobbles on the surface and its sticky and slippery surface when wet; additionally, maintaining grass cover can be difficult due to a shallow soil depth (Werchan and Coker, 1983).

Eckrant extremely stony clay, 0 to 3% slopes (EeB) consists of nearly level to gently sloping soils found on broad ridges or shallow valleys in uplands. The upper layer of the soil is typically a very stony clay approximately 11 inches thick. This upper layer is roughly 25% limestone fragments on the surface. Underlying this layer is Indurated limestone. This soil is well-

drained and has rapid surface runoff with moderately slow permeability. The main use of Eckrant extremely stony clay is for rangeland. The soil is suited for development purposes due to the hard underlying limestone which can act as a stable footing for foundations, but blasting and cutting will be needed for construction of underground utility lines, foundations, roads, and streets (Werchan and Coker, 1983).

Fairlie clay, 1 to 2% slopes (FaB) is a gently sloping soil found along broad flats and on the edges of drainageways on uplands. Weakly cemented limestone interbedded with limy material underlies this soil. This soil is calcareous and moderately alkaline. Fairlie clay is moderately well-drained with medium runoff. This soil is known to crack extensively when dry and seal the cracks when wet, which prevents water from entering the soil rapidly. The main uses of this soil are for crops and small portions of tame pasture. Fairlie clay is suitable for urban uses. However, due to its high shrink-swell potential, this soil can cause cracks in paved streets and foundations. Corrosivity of underground steel utility lines is also a hazard associated with this soil (Werchan and Coker, 1983).

Georgetown stony clay loam, 1 to 3% slopes (GsB) is a gently sloping soil typically found on higher parts of uplands. This soil has an upper layer of brown stony clay loam that grades into an underlying layer of subsoil and indurated fractured limestone. This soil is well-drained with medium surface runoff and slow permeability. Georgetown stony clay loam is used as rangeland and is typically desirable for homesites due to the native post oak and high position on the landscape. Some of the limitations associated with this soil include corrosivity of buried pipelines due to the clayey subsoil and construction; installation of foundations and underground utilities can be difficult and costly due to the rock substratum (Werchan and Coker, 1983).

## 2.6 WATER WELLS

A review of TCEQ and Texas Water Development Board (TWDB) records revealed no water wells on the subject site and 1 well within 0.5 miles of the subject site (TCEQ, 2021; TWDB, 2021). According to TWDB records, off-site well no. 5826301 is reportedly completed in the Trinity Aquifer at a total depth of approximately 400 feet below the surface.

The results of this assessment do not preclude the existence of undocumented/abandoned wells on the site. If a water well or casing is encountered during construction, work should be halted near the feature until the TCEQ is contacted.

## 2.7 GEOLOGY

### Literature Review

The subject site is underlain by Keys Valley Marl (Kkv), Comanche Peak Limestone (Kc), and Edwards Limestone (Ked) (USGS, 2006).

Keys Valley Marl is only present on the western edge of the subject site. This member is predominantly composed of marl with some argillaceous limestone and limestone. Keys Valley is typically a soft white formation with marine megafossils like *Exogyra texana*, *Gryphaea*

*mucronata*, other pelecypods, ammonites, and gastropods. Keys Valley Marl is part of the Upper Walnut Formation, can be up to 50 feet thick, and begins to thin towards the south by the Williamson/Travis county line (Abbott, 1973; USGS, 2006).

Comanche Peak Limestone consists of both limestone and marl and conformably underlies the Edwards Formation. This formation is known to be nodular, fossiliferous, and thickens towards the north. The contact between the Edwards and the Comanche formations can be distinguished by the change from white nodular marly limestone to the massive carbonate beds of the Edwards. Comanche Peak Limestone is fine to very fine-grained with a light gray color that weathers white. This formation has been extensively burrowed. Large gastropods and pelecypods are common throughout the formation (Abbott, 1973; USGS, 2006).

Edwards Limestone consists of limestone, dolomite, and chert. Edwards Limestone is aphanitic to fine-grained, massive to thin-bedded, hard, brittle, and fossiliferous throughout. The limestone consists in part of rudistid biostromes and much milioid biosparite. This formation is also known to contain oysters and gastropods (Abbott, 1973). The dolomite within Edwards Limestone is fine to very fine-grained, porous, and medium gray to grayish-brown. The chert, with common nodules and plates, varies in amount from bed to bed, has some intervals free of chert, and is mostly white to light gray. In the zone of weathering, the Edwards Limestone is considerably recrystallized, "honeycombed," and cavernous, forming an aquifer; it forms flat areas and plateaus bordered by scarps.

The site Stratigraphic Column is provided as Attachment B, and the Site Geologic Map is Attachment D.

The subject site is located within the Balcones Fault Zone. According to mapping, no faults are present within the subject site boundaries. Available geologic reports indicate the nearest mapped fault outside of the subject site is located approximately 1 mile to the southeast trending northeast at N47E (USGS, 2006).

### Field Assessment

Please see Attachment C for a narrative description of geology observed on the subject site. The Site Geologic Map is provided as Attachment D. Horizon observed no man-made features and 8 naturally occurring geologic features on the subject site that meet the TCEQ definition of a potential recharge feature. The Geologic Assessment Table (Attachment A) describes those features observed on the subject site that meet the TCEQ definition of a potential recharge feature.

Geologic features on the subject site are described as follows:

Geologic feature F-1 is an upland sinkhole located in the southeastern corner of the subject site with a diameter of approximately 3 feet and a depth of 1 foot. F-1 was noted during the site investigation to have no air flow with one small, rock-choked, semi-open portal. This feature has been filled with cobbles, gravel, clay, and loose soil. Water infiltration of this feature is intermediate and has an apparent surface runoff catchment of less than 0.4 acres.

Geologic feature F-2 is a previously excavated solution-enlarged fracture located in Edwards Limestone and trending N314W. F-2 measures approximately 5 feet long by 0.25 feet wide by 2.5 feet deep. Previous apparent hand excavation dug the feature down to approximately 6 feet below the natural surface. Moderate airflow was noted along the fracture at the time of Horizon's reconnaissance. On 22 and 23 February 2021, the feature was mechanically excavated using a backhoe with hoe ram attachment. The feature was enlarged and dug down 11 feet below the surface. A low bedding plane void was encountered 9 feet below the surface that extended laterally along the eastern and southern walls of the excavation. The eastern portion of the bedding plane extends approximately 16 feet laterally, trending N45E before encountering a bedrock wall, and the southern portion extended toward the southeast for another 8 feet before ending at another bedrock wall. The largest opening was along the southern wall of the excavation, where bedding plane void ceiling heights were approximately 2 feet and lowered to only 0.5 feet to 1 foot in height. The eastern portion of the bedding plane void was less than 0.5 feet high at the back wall. This feature was determined to be a sensitive recharge feature and did not have enough human-sized passageways to be classified as a cave. The water infiltration rate of the feature is intermediate and has an apparent surface runoff catchment of less than 0.4 acres.

Geologic feature F-3 is a previously excavated solution cavity located near the northern boundary of the middle portion of the subject site. This feature is found in Edwards Limestone and is approximately 4 feet long by 4 feet wide with a depth of 4 feet. Slight air was noted at the opening during Horizon's site reconnaissance. The solution cavity was filled with cobbles, clay, dirt, and loose soil. The feature was noted to have an intermediate water infiltration rate and deemed to be a sensitive recharge feature with an apparent surface runoff catchment of less than 0.4 acres.

Geologic feature F-4 is a very small upland sinkhole that has a diameter of approximately 1.5 feet with negative relief of 1 foot. This feature is located in Edwards Limestone close to the northern site boundary, approximately 500 feet west of F-3. The feature had a small portal with no air flow that could have possibly been burrowed out by an animal. The sinkhole was filled with dirt, clay, gravel, and other material. Based on the infill of material within the sink, lack of air flow from the open portal, and very low water infiltration rate, this feature was deemed to be non-sensitive for groundwater recharge capability and therefore would not require TCEQ protective setback buffers.

Geologic feature F-5 is a small upland sinkhole that measures approximately 1.5 feet long by 1 foot wide by 1 foot deep. A small portal was noted in the floor of the sink with no air flow. The portal was surrounded by cobbles and filled with clay, dirt, and soil. The water infiltration rate of the feature was noted to be low-intermediate. The feature was deemed to be sensitive for groundwater recharge capability and would require TCEQ protective setback buffers.

Geologic feature F-6 is a closed depression that measures approximately 8 feet long by 4 feet wide by 1 foot deep. No open drainage portals or voids were observed along the floor of this feature. The depression has a clay-lined floor, making infiltration very low.

Geologic feature F-7 is a closed depression that measures 5 feet long by 3 feet wide by 1 foot deep. No open drainage portals or voids were observed along the floor of this feature. The depression has a clay-lined floor, making infiltration very low.

Geologic feature F-8 is a solution cavity found within Comanche Peak Limestone. The feature measures approximately 1.25 feet long by 0.6 feet wide by 1 foot deep. The feature is found in the side wall of a small tributary and was noted to have no air flow. The feature has a low infiltration rate due to the clay lining within the solution cavity and has been deemed to be non-sensitive.

### **3.0 CONCLUSIONS AND RECOMMENDATIONS**

Four geologic features (F-1, F-2, F-3, and F-5) were identified at the subject site that would require protection or mitigation pursuant to TCEQ rules for protection of the Edwards Aquifer (30 TAC 213). A sensitive feature would require a TCEQ setback buffer. In general, a protective buffer encompassing a sensitive feature is recommended to meet the TCEQ guidance for a setback of at least 50 feet in all directions from the feature's areal extent (perimeter), plus its watershed catchment up to 200 feet from the perimeter of the feature.

Four geologic features (F-4, F-6, F-7, and F-8) have been evaluated as non-sensitive for groundwater recharge capability and would therefore not require TCEQ protective setback buffers. No further action is recommended for these non-sensitive features.

Most of the site generally appears well-suited to development prospectuses. It should be noted that soil and drainage erosion would increase with ground disturbance. Native grasses and the cobbly content of the soil aid to prevent erosion. Soil and sedimentation fencing should be placed in all appropriate areas prior to any site disturbing activities.

Because the subject site is located over the Edwards Aquifer Recharge Zone, it is possible that subsurface voids underlie the site. If any subsurface voids are encountered during site development, work should halt immediately so that a geologist may assess the potential for the void(s) to provide meaningful contribution to the Edwards Aquifer.

#### 4.0 REFERENCES

- Abbott, P.L. *The Edwards Limestone in the Balcones Fault Zone, South-Central Texas*. Ph.D. dissertation, The University of Texas, Austin, Texas. 1973.
- (CAPCOG) Capital Area Council of Governments. 5-foot contours, CAPCOG Center for Regional Development, Austin, Texas. 2007.
- (Nearmap) Nearmap US PhotoMaps. Created by Nearmap\_Engineering. Imagery date 25 February 2021.
- (NRCS) Natural Resources Conservation Service (formerly the Soil Conservation Service) US Department of Agriculture, Engineering Division. *Soil Series and Hydrologic Soil Groups of Urban Hydrology for Small Watersheds*, Technical Release No. 55. January 1975.
- \_\_\_\_\_. Web Soil Survey, <<http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx>>. Soil map data layer updated 12 September 2019. Soil survey accessed 1 March 2021.
- (OSM) OpenStreetMap contributors. OpenStreetMap, <<http://www.openstreetmap.org>>. Available under the Open Database License ([www.opendatacommons.org/licenses/odbl](http://www.opendatacommons.org/licenses/odbl)). Accessed 24 March 2021.
- (TCEQ) Texas Commission on Environmental Quality. *Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones*. Revised October 2004.
- \_\_\_\_\_. RG-348, *Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices*. Revised July 2005.
- \_\_\_\_\_. *Optional Enhanced Measures for the Protection of Water Quality in the Edwards Aquifer (Revised)*. Appendix A to RG-348, *Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices*. September 2007.
- \_\_\_\_\_. Edwards Aquifer Protection Program. Edwards Aquifer Viewer, <<http://www.tceq.state.tx.us/field/eapp/viewer.html>>. Accessed 1 March 2021.
- (TPWD) Texas Parks and Wildlife Department. Texas Watershed Viewer, <<https://tpwd.maps.arcgis.com/apps/Viewer/index.html?appid=2b3604bf9ced441a98c500763b8b1048>>. Accessed 1 March 2021.
- (TWDB) Texas Water Development Board. Water Information Integration and Dissemination System. TWDB Groundwater Database, <<https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer>>. Accessed 1 March 2021.
- (TWSC) United States Geological Survey, Texas Water Science Center. Geologic Database of Texas, <<https://txpub.usgs.gov/txgeology/>>. Updated 1 February 2014; Accessed 2 March 2021.





(USGS) US Geological Survey. 7.5-minute series topographic maps, Leander, Texas, quadrangle. 1987.

\_\_\_\_\_. Stoeser, D.B., Shock, Nancy, Green, G.N., Dumonceaux, G.M., and heran, W.D. *Geologic map database of Texas*, NE quadrant, prepared in cooperation with the Texas Bureau of Economic Geology. 2006.

Wechan L.E., and J. L. Coker. Soil survey of Williamson County, Texas. US Department of Agriculture, Natural Resources Conservation Service (formerly Soil Conservation Service), in cooperation with the Texas Agricultural Experiment Station. 1983.

**ATTACHMENT F**  
**ADDITIONAL SITE MAPS**



#### Legend

Subject Site


**Horizon**  
Environmental Services, Inc.

Date:	03/04/2021
Drawn:	KRS
HJN NO:	200183.001 GA
Source:	OSM, 2021


#### Attachment F, Figure 1

Vicinity Map  
140-Acre Cannon Tract  
731 County Road 175  
Leander, Williamson County, Texas









**Horizon**  
Environmental Services, Inc.


Date:	03/04/2021
Drawn:	KRS
HJN NO:	200183.001GA
Source:	CAPCOG, 2007; Nearmap, 2021

**Attachment F, Figure 3**  
Site Topography Map  
140-Acre Cannon Tract  
731 County Road 175  
Leander, Williamson County, Texas



0 350 700  
Feet







**ATTACHMENT G**  
**SITE PHOTOGRAPHS**



**PHOTO 1**  
**Geologic feature F-1 (upland sinkhole), facing down**



**PHOTO 2**  
**Closer view of F-1, facing down**



**PHOTO 3**  
**Geologic feature F-2 (solution-enlarged fracture),  
previously hand excavated (by others) about 6 feet down**



**PHOTO 4**  
**View of F-2 after mechanical excavation, facing down**





**PHOTO 5**

**Geologic feature F-3 (solution cavity) previously excavated (by others) about 4 feet down**



**PHOTO 6**

**Closer view of F-3, facing down**



**PHOTO 9**

**Geologic feature F-4 (very small upland sinkhole), facing down**



**PHOTO 10**

**Geologic feature F-5 (small upland sinkhole), facing down**





**PHOTO 11**  
**Geologic feature F-6 (closed depression), facing down**



**PHOTO 12**  
**Geologic feature F-7 (closed depression), facing down**



**PHOTO 13**  
**Geologic feature F-8 (solution cavity) within side rock wall of tributary**



**PHOTO 14**  
**Closer view of F-8**

# **SECTION 4: ORGANIZED SEWAGE COLLECTION SYSTEM**

# Organized Sewage Collection System Application

## Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

**Regulated Entity Name:** Edgewood Phase 2, Section 2

1. ☒ **Attachment A – SCS Engineering Design Report.** This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

## Customer Information

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Kyle Kriegel

Entity: M/I Homes of Austin, LLC

Mailing Address: 7600 N. Capital of Texas Hwy.; Bldg. C, Suite 250

City, State: Austin, TX

Zip: 78731

Telephone: (512) 770-8524

Fax: N/A

Email Address: kkriegel@mihomes.com

***The appropriate regional office must be informed of any changes in this information within 30 days of the change.***

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: Alejandro E. Granados Rico, P.E.

Texas Licensed Professional Engineer's Number: 130084

Entity: Kimley-Horn

Mailing Address: 501 S. Austin Ave, Suite 1310

City, State: Georgetown, Texas

Zip: 78626

Telephone: (512) 520-0768

Fax: N/A

Email Address: alex.granados@kimley-horn.com

## Project Information

4. Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):

- ☒ Residential: Number of single-family lots: 114  
☐ Multi-family: Number of residential units: \_\_\_\_\_  
☐ Commercial \_\_\_\_\_  
☐ Industrial \_\_\_\_\_  
☐ Off-site system (not associated with any development) \_\_\_\_\_  
☐ Other: \_\_\_\_\_

5. The character and volume of wastewater is shown below:

<u>100</u> % Domestic	<u>27,930</u> gallons/day
_____ % Industrial	_____ gallons/day
_____ % Commingled	_____ gallons/day
Total gallons/day: <u>27,930</u>	

6. Existing and anticipated infiltration/inflow is 0 gallons/day. This will be addressed by: n/a.

7. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.

- ☐ The WPAP application for this development was approved by letter dated \_\_\_\_\_. A copy of the approval letter is attached.  
☒ The WPAP application for this development was submitted to the TCEQ on October 5th 2023, but has not been approved.  
☐ A WPAP application is required for an associated project, but it has not been submitted.  
☐ There is no associated project requiring a WPAP application.

8. Pipe description:

**Table 1 - Pipe Description**

<i>Pipe Diameter(Inches)</i>	<i>Linear Feet (1)</i>	<i>Pipe Material (2)</i>	<i>Specifications (3)</i>
8	6,171	PVC SDR-26	ASTM D-3034
6 (FM)	10	PVC SDR-26	ASTM D-3034
4 (FM)	2,285	PVC SDR-26	ASTM D-3034

**Total Linear Feet: 8,466**

(1) Linear feet - Include stub-outs and double service connections. Do not include private service laterals.

(2) Pipe Material - If PVC, state SDR value.

(3) Specifications - ASTM / ANSI / AWWA specification and class numbers should be included.

9. The sewage collection system will convey the wastewater to the Brushy Creek Wastewater (name) Treatment Plant. The treatment facility is:

- ☒ Existing  
☐ Proposed

10. All components of this sewage collection system will comply with:

- ☒ The City of Leander standard specifications.  
☐ Other. Specifications are attached.

11. ☒ No force main(s) and/or lift station(s) are associated with this sewage collection system.  
☐ A force main(s) and/or lift station(s) is associated with this sewage collection system and the **Lift Station/Force Main System Application** form (TCEQ-0624) is included with this application.

## ***Alignment***

12. ☒ There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.
13. ☒ There are no deviations from straight alignment in this sewage collection system without manholes.  
☐ **Attachment B - Justification and Calculations for Deviation in Straight Alignment without Manholes.** A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.  
☐ For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.

## ***Manholes and Cleanouts***

14. ☒ Manholes or clean-outs exist at the end of each sewer line(s). These locations are listed below: (Please attach additional sheet if necessary)

**Table 2 - Manholes and Cleanouts**

<i>Line</i>	<i>Shown on Sheet</i>	<i>Station</i>	<i>Manhole or Clean-out?</i>
WWL-A	47	1+00.00	Manhole
WWL-A	47	1+16.65	Manhole
WWL-A	47	1+33.52	Manhole
WWL-A	47	2+37.67	Manhole
WWL-A	47	2+80.12	Manhole
WWL-A	47	3+25.46	Manhole
WWL-A	47	5+08.47	Manhole
WWL-A	47	6+12.14	Manhole
WWL-A	47	7+22.84	Manhole
WWL-A	47	8+51.11	Manhole

<b><i>Line</i></b>	<b><i>Shown on Sheet</i></b>	<b><i>Station</i></b>	<b><i>Manhole or Clean-out?</i></b>
WWL-A	47	9+70.71	Manhole
WWL-A	47	10+42.09	Manhole
WWL-A	48	13+25.67	Manhole
WWL-A	48	15+49.41	Manhole
WWL-A	48	17+06.64	Manhole
WWL-B	49	2+25.91	Manhole
WWL-B	49	3+67.50	Manhole
WWL-B	49	4+34.60	Manhole
WWL-B	49	5+94.48	Manhole
WWL-B	49	8+29.51	Manhole
WWL-B	49	9+61.65	Manhole
WWL-B	50	12+44.05	Manhole
WWL-B	50	13+19.93	Manhole
WWL-B	50	13+95.07	Manhole
WWL-C	50	1+84.70	Manhole
WWL-C	50	2+95.30	Manhole
WWL-C	50	4+49.29	Manhole
WWL-D	51	2+74.97	Manhole
WWL-D	51	3+68.37	Manhole
WWL-D	51	5+35.94	Manhole
WWL-D	51	5+99.81	Manhole
WWL-D	51	7+62.56	Manhole
WWL-D	51	10+19.38	Manhole
WWL-E	52	1+91.88	Manhole
WWL-F	52	1+91.19	Manhole
WWL-F	52	3+84.49	Manhole
WWL-F	53	6+71.99	Manhole
WWL-F	53	9+687.26	Manhole

<b><i>Line</i></b>	<b><i>Shown on Sheet</i></b>	<b><i>Station</i></b>	<b><i>Manhole or Clean-out?</i></b>
WWL-F	53	11+32.32	Manhole
WWL-G	54	4+04.11	Manhole
WWL-G	54	5+38.94	Manhole
WWL-G	54	6+91.54	Manhole
WWL-G	54	9+03.47	Manhole
WWL-H	55	1+70.56	Manhole
FM-A	56	1+10.00	Cleanout
FM-A	56	1+76.94	Cleanout
FM-A	56	3+88.55	Cleanout
FM-A	56	9+06.73	Cleanout
FM-A	57	12+49.45	Cleanout
FM-B	58	1+07.07	Cleanout
FM-B	58	1+35.46	Cleanout
FM-B	58	1+70.50	Cleanout
FM-B	58	2+41.94	Cleanout
FM-B	58	2+65.68	Cleanout
FM-B	58	3+00.60	Cleanout
FM-B	58	5+27.83	Cleanout
FM-B	58	5+51.13	Cleanout
FM-B	58	6+49.66	Cleanout
FM-B	58	7+48.21	Cleanout
FM-B	58	8+25.37	Cleanout
FM-B	58	8+92.21	Cleanout
FM-B	58	9+48.89	Cleanout
FM-B	58	10+16.49	Cleanout
FM-B	59	11+79.93	Cleanout
FM-B	59	12+44.15	Cleanout



15. ☒ Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.
16. ☒ The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
≥54	2000

- ☐ **Attachment C – Justification for Variance from Maximum Manhole Spacing.** The maximum spacing between manholes on this project (for each pipe diameter used) is greater than listed in the table above. A justification for any variance from the maximum spacing is attached, and must include a letter from the entity which will operate and maintain the system stating that it has the capability to maintain lines with manhole spacing greater than the allowed spacing.
17. ☐ All manholes will be monolithic, cast-in-place concrete.
- ☒ The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

## ***Site Plan Requirements***

### ***Items 18 - 25 must be included on the Site Plan.***

18. ☒ The Site Plan must have a minimum scale of 1" = 400'.
- Site Plan Scale: 1" = 60'.
19. ☒ The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.
20. Lateral stub-outs:
- ☒ The location of all lateral stub-outs are shown and labeled.
- ☐ No lateral stub-outs will be installed during the construction of this sewer collection system.
21. Location of existing and proposed water lines:
- ☒ The entire water distribution system for this project is shown and labeled.
- ☒ If not shown on the Site Plan, a Utility Plan is provided showing the entire water and sewer systems.
- ☐ There will be no water lines associated with this project.
22. 100-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)
- ☐ After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

**Table 3 - 100-Year Floodplain**

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
n/a	n/a	n/a

23. 5-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concrete-lined channels constructed above sewer lines.)
- ☐ After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

**Table 4 - 5-Year Floodplain**

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
n/a	n/a	n/a

- 24. ☒ Legal boundaries of the site are shown.
- 25. ☒ The ***final plans and technical specifications*** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

### **Items 26 - 33 must be included on the Plan and Profile sheets.**

- 26. ☒ All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.
- ☐ There will be no water line crossings.
- ☐ There will be no water lines within 9 feet of proposed sewer lines.

**Table 5 - Water Line Crossings**

<i>Line</i>	<i>Station or Closest Point</i>	<i>Crossing or Parallel</i>	<i>Horizontal Separation Distance</i>	<i>Vertical Separation Distance</i>
WWL-A	9+70.71	CROSSING	N/A	2'
WWL-A	13+51.67	CROSSING	N/A	2.1'
WWL-A	15+75.41	CROSSING	N/A	1.7'
WWL-B	5+67.16	CROSSING	N/A	3.3'
WWL-B	12+70.12	CROSSING	N/A	7.9'
WWL-D	7+88.56	CROSSING	N/A	3.2'
WWL-F	9+94.26	CROSSING	N/A	6.4'
WWL-G	7+17.54	CROSSING	N/A	6.3'
FM-A	2+64.33	CROSSING	N/A	2.3'
FM-A	3+41.89	CROSSING	N/A	2.2'
FM-B	2+59.37	CROSSING	N/A	2.2'
FM-B	3+12.91	CROSSING	N/A	2.1'

**27. Vented Manholes:**

- ☒ **No part** of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.
- ☐ **A portion** of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.
- ☐ **A portion** of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.
- ☐ **A portion** of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.

**Table 6 - Vented Manholes**

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>
n/a	n/a	n/a	n/a

**28. Drop manholes:**

- ☐ There are no drop manholes associated with this project.
- ☒ Sewer lines which enter new or existing manholes or "manhole structures" higher than 24 inches above the manhole invert are listed in the table below and labeled on the appropriate profile sheets. These lines meet the requirements of 30 TAC §217.55(I)(2)(H).

**Table 7 - Drop Manholes**

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>
WWL-A	5'	1+16.65	47
WWL-A	5'	1+33.52	47
WWL-A	4'	2+80.12	47
WWL-B	4'	13+19.93	50
WWL-D	5'	2+74.97	51
WWL-F	4'	3+84.49	

29. Sewer line stub-outs (For proposed extensions):

- ☒ The placement and markings of all sewer line stub-outs are shown and labeled.  
☐ No sewer line stub-outs are to be installed during the construction of this sewage collection system.

30. Lateral stub-outs (For proposed private service connections):

- ☐ The placement and markings of all lateral stub-outs are shown and labeled.  
☒ No lateral stub-outs are to be installed during the construction of this sewage collection system.

31. Minimum flow velocity (From Appendix A)

- ☒ Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.

32. Maximum flow velocity/slopes (From Appendix A)

- ☒ Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.  
☐ **Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.** Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

**Table 8 - Flows Greater Than 10 Feet per Second**

<i>Line</i>	<i>Profile Sheet</i>	<i>Station to Station</i>	<i>FPS</i>	<i>% Slope</i>	<i>Erosion/Shock Protection</i>
n/a	n/a	n/a	n/a	n/a	n/a

33. Assuming pipes are flowing full, where flows are  $\geq 10$  feet per second, the provisions noted below have been made to protect against pipe displacement by erosion and/or shock under 30 TAC §217.53(l)(2)(B).

- ☐ Concrete encasement shown on appropriate Plan and Profile sheets for the locations listed in the table above.  
☐ Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on appropriate Plan and Profile sheets for the locations listed in the table above.  
☒ N/A

## Administrative Information

34. ☒ The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
35. ☒ Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

**Table 9 - Standard Details**

<b>Standard Details</b>	<b>Shown on Sheet</b>
Lateral stub-out marking <b>[Required]</b>	n/a
Manhole, showing inverts comply with 30 TAC §217.55(l)(2) <b>[Required]</b>	80
Alternate method of joining lateral to existing SCS line for potential future connections <b>[Required]</b>	n/a
Typical trench cross-sections <b>[Required]</b>	80
Bolted manholes <b>[Required]</b>	n/a
Sewer Service lateral standard details <b>[Required]</b>	81
Clean-out at end of line <b>[Required, if used]</b>	n/a
Baffles or concrete encasement for shock/erosion protection <b>[Required, if flow velocity of any section of pipe &gt;10 fps]</b>	n/a
Detail showing Wastewater Line/Water Line Crossing <b>[Required, if crossings are proposed]</b>	47-59
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) <b>[Required, if Flexible Pipe is used]</b>	n/a
Drop manholes <b>[Required, if a pipe entering a manhole is more than 24 inches above manhole invert]</b>	80

36. ☒ All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
37. ☒ All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
- ☒ Survey staking was completed on this date: 11/30/2023
38. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
39. ☒ Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: Alejandro E. Granados Rico P.E.

Date: 11/07/2023

Place engineer's seal here:



*Alejandro E. Granados Rico*

*Alejandro E. Granados Rico*

Signature of Licensed Professional Engineer:

---

## Appendix A-Flow Velocity Table

**Flow Velocity (Flowing Full)** All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

**Table 10 - Slope Velocity**

<i>Pipe Diameter(Inches)</i>	<i>% Slope required for minimum flow velocity of 2.0 fps</i>	<i>% Slope which produces flow velocity of 10.0 fps</i>
6	0.50	12.35
8	0.33	8.40
10	0.25	6.23
12	0.20	4.88
15	0.15	3.62
18	0.11	2.83
21	0.09	2.30
24	0.08	1.93
27	0.06	1.65
30	0.055	1.43
33	0.05	1.26
36	0.045	1.12
39	0.04	1.01
>39	*	*

*\*For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.*

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

**Figure 1 - Manning's Formula**

Where:

$v$  = velocity (ft/sec)

$n$  = Manning's roughness coefficient  
(0.013)

$R_h$  = hydraulic radius (ft)

$S$  = slope (ft/ft)

## ***Engineer's Design Report***

This Engineering Design Report has been prepared to comply with the Texas Commission on Environmental Quality Design Criteria for Domestic Wastewater Systems, 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable. Please note that throughout this application, the more stringent of AWU or TCEQ regulations shall apply.

## **Project Description**

### ***Introduction***

Edgewood Phase 2, Section 2 is an undeveloped 45.28 acre property located southeast of the intersection of RR 2243 and CR 175 and within the city limits of the Leander, Texas. The proposed Edgewood Phase 2, Section 2 project includes the construction of 114 single family homes with associated roadway, water, wastewater, and drainage improvements to support the project. This project proposes 14.74 acres (32.6%) of impervious cover.

This project is located within the Brushy Creek Watershed. The site is not located in the Federal Emergency Management Agency's 100-year floodplain according to FIRM 48491C0460F. The site is located within the Edwards Aquifer Recharge Zone and Contributing Zone according to the City of Austin and Edward's Aquifer GIS databases. There are no critical water quality zones and or critical environmental features located on-site. The site consists of 45.28 acres of undeveloped land.

On-site infrastructure is comprised of water, gas, electric, wastewater, and storm sewer lines. The wastewater service outlined in this report will consist of eight (8) lines that will convey wastewater to one lift station, proposed with Edgewood Phase 2 Section 2 and eventually will travel via two (2) dual 4" force mains to connect to a force main built in Phase 2-1. It will then travel via wastewater line through phases 2-1, 1-2, and 1-1 to an existing manhole that is built with an offsite line. The offsite line will gravity flow and be deposited at the Brushy Creek Regional Wastewater Treatment Plant to be treated. A Development Agreement between M/I Homes of Austin, LLC and the City of Leander recognizes the proposed flow from the Edgewood development and that the city will accept to treat it through the Brushy Creek Regional Wastewater Treatment Plant. All lines will consist of single and double service connections to homes that are proposed per this development. All proposed manholes shall be watertight, with watertight rings and covers. All proposed wastewater lines will be installed within the Edwards Aquifer Recharge Zone (EARZ) and Contributing Zone (EACZ).

## **Pipe Design**

### ***Flow Design Basis***

Service for the build-out of the 45.28 ac 114 single family homes, Phase 2-2 site, located at RR 2243 and CR 175, will be served by this wastewater system. This is the final phase of the Edgewood Subdivision. The City of Austin Utility Criteria Manual (UCM) was used to determine the parameters for the design of the wastewater line system. See Appendix B for the map illustrating the property to be served by this wastewater line system and Appendix C for the calculations (as approved by the City of Austin).

### ***Gravity Pipe and Joint Materials***

The proposed pipe to be used for the 6", 8" and 12" wastewater line will be ASTM D3034 SDR-26 PVC pipe (cell class 12454). The joints for this pipe shall meet the requirements of ASTM D3212. The pipe joints shall have an integral bell and rubber gasket seal with the locked-in type gasket.



## ***Separation Distances for Water and Wastewater***

A 26-foot minimum horizontal separation is maintained between all proposed wastewater infrastructure and proposed water lines. There are 12 water line crossings which do not meet the nine-foot minimum vertical separation. Cement-stabilized sand backfill has been provided at these locations. See Table 5 – Water Crossings for all water line crossings. It is not feasible to provide nine-feet of vertical separation at waterline crossings due to depth limitations. In most cases, the crossing water line would need to be above the finished grade, or approximately twenty-feet below grade in order to meet the nine-foot separation requirement.

## ***Service Connections***

Service connections have been included for each of the 114 proposed single-family homes.

## ***Boring and Tunneling of Crossings***

No boring or tunneling of crossings are proposed for this project.

## ***Corrosion Potential***

PVC pipe will be utilized for or all proposed wastewater lines. No deterioration of the proposed pipe or its associated components is anticipated in this application.

## ***Odor Control***

All flows contributing to the proposed wastewater lines are from single family developments generating domestic sewage. There is a lift station proposed with this phase of the Edgewood Subdivision. Odor control measures are proposed for this project.

## ***Active Geologic Faults***

Per the Geologic Assessment, no active geologic faults were located within the area of the project.

## ***Capacity Analysis***

The capacity of each proposed wastewater segment is calculated below based on Manning's Equation. The calculation for each segment is based on the minimum proposed slope.

$$Q = \frac{1.49}{n} * A * R^{0.67} * S^{0.5}$$

Where:

Q<sub>full</sub> = flow rate of fluid in pipe at full flow (ft<sup>3</sup>/s) (cfs)

Q<sub>90%</sub> = flow rate of fluid in pipe at 90% full flow (ft<sup>3</sup>/s) (cfs)

$$A = \text{area of pipe (ft}^2\text{)} = \frac{\pi * d^2}{4}$$

d = internal pipe diameter (ft) = D<sub>o</sub> – 2t

D<sub>o</sub> = outside diameter (in)

t = pipe wall thickness (in)

n = Manning's Roughness coefficient = 0.013

R<sub>full</sub> = hydraulic radius of pipe (full flow) = A/P = D/4 (ft)

R<sub>90%</sub> = hydraulic radius of pipe (90% full flow) = 0.9\*A/P = 0.9\*D/4 (ft)

P = wetted perimeter of pipe =  $\pi$  \*D (ft)

S = slope of energy line

Pipes	Length ft	Slope %	Slope ft/ft	Diameter		Pipe Material	Manning's	P ft	A sf	Rfull ft	R90% ft	Qfull cfs	Q90% cfs	Vfull fps	V90% fps
				in	ft										
A-1	17	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-2	17	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-3	104	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-4	42	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-5	45	5.00	0.050	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.69	2.42	7.72	6.94
A-6	183	5.00	0.050	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.69	2.42	7.72	6.94
A-7	104	2.00	0.020	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.70	1.53	4.88	4.39
A-8	111	2.00	0.020	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.70	1.53	4.88	4.39
A-9	128	2.00	0.020	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.70	1.53	4.88	4.39
A-10	120	2.00	0.020	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.70	1.53	4.88	4.39
A-11	71	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-12	284	1.25	0.013	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.35	1.21	3.86	3.47
A-13	224	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
A-14	157	1.00	0.010	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.20	1.08	3.45	3.11
B-1	126	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
B-2	142	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
B-3	67	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
B-4	160	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
B-5	235	0.90	0.009	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.14	1.03	3.27	2.95
B-6	132	0.90	0.009	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.14	1.03	3.27	2.95
B-7	282	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
B-8	76	1.45	0.015	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.45	1.31	4.15	3.74
B-9	75	1.00	0.010	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.20	1.08	3.45	3.11
C-1	85	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
C-2	111	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
C-3	154	1.00	0.010	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.20	1.08	3.45	3.11
D-1	175	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
D-2	93	4.00	0.040	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.41	2.17	6.90	6.21
D-3	168	4.00	0.040	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.41	2.17	6.90	6.21
D-4	64	3.00	0.030	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.09	1.88	5.98	5.38
D-5	163	3.00	0.030	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.09	1.88	5.98	5.38
D-6	257	2.00	0.020	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.70	1.53	4.88	4.39
E-1	92	1.50	0.015	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.48	1.33	4.23	3.80
F-1	91	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
F-2	193	3.04	0.030	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.10	1.89	6.02	5.41
F-3	288	1.50	0.015	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.48	1.33	4.23	3.80
F-4	296	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
F-5	164	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
G-1	304	0.50	0.005	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.85	0.77	2.44	2.20
G-2	135	0.60	0.006	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	0.93	0.84	2.67	2.41
G-3	153	1.50	0.015	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.48	1.33	4.23	3.80
G-4	212	1.25	0.013	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	1.35	1.21	3.86	3.47
H-1	71	3.90	0.039	8.00	0.67	PVC	0.013	2.09	0.35	0.17	0.15	2.38	2.14	6.81	6.13

Pipe Type	Minimum Velocity fps	Maximum Velocity fps
8" PVC	2.44	7.72

The proposed wastewater line installed at the slope specified provides capacity in excess of the calculated peak wet weather design flows at full flow and 90% full flow conditions.

## Structural Analysis

Flexible pipe is proposed on this project. Structural calculations are provided for the flexible pipe to be installed. The proposed collection system piping is designed to have a minimum structural life of 50 years. As previously mentioned, all proposed PVC pipe shall be cell class 12454 with a tensile strength of 7,000 psi.

*Live Load Calculations* – no significant live loads are anticipated on any segment of this project.

*Buckling Pressure* - the following equations utilized for the calculation of buckling pressure are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$P_{cr} = \frac{2 * E}{(1 - \nu^2) * (DR - 1)^3} \quad (\text{Equation 7.14})$$

$$P_b = 1.15 * \sqrt{P_{cr} * E} \quad (\text{Equation 7.18})$$

$$H = (P_b * 144) / w \quad (\text{Equation 6.7})$$

Where:

$P_{cr}$  = critical buckling pressure (psi)

$E$  = modulus of elasticity (psi) = 400,000 psi for PVC

$\nu$  = Poisson's Ratio = 0.38 for PVC

$DR$  = dimension ratio

$P_b$  = buckling pressure in soil (psi)

$E'$  = modulus of soil reaction (psi) = 2,000 psi for crushed rock compacted to greater than 95% relative density

$H$  = maximum allowable cover height of soil (ft)

$w$  = weight of soil (lbs/ft<sup>3</sup>) = 120 lbs/ft<sup>3</sup>

## **8" ASTM D3034 SDR-26**

$$P_{cr} = \frac{2 * 400,000}{(1 - 0.38^2) * (26 - 1)^3}$$

$$P_{cr} = 59.84 \text{ psi}$$

$$P_b = 1.15 * \sqrt{59.84 * 2,000}$$

$$P_b = 397.84 \text{ psi}$$

$$H = (397.84 * 144) / 120$$

**H = 477.41 ft height of soil to cause pipe buckling**

## **12" ASTM D3034 SDR-26**

$$P_{cr} = \frac{2 * 400,000}{(1 - 0.38^2) * (26 - 1)^3}$$

$$P_{cr} = 59.84 \text{ psi}$$

$$P_b = 1.15 * \sqrt{59.84 * 2,000}$$

$$P_b = 397.84 \text{ psi}$$

$$H = (397.84 * 144) / 120$$

**H = 477.41 ft height of soil to cause pipe buckling**

*Prism Load Calculations* - the following equations utilized for the calculation of prism loads are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$P = H * w \text{ (Equation 6.7)}$$

Where:

- P = prism load pressure due to soil weight (lbs/ft<sup>2</sup>)
- H = depth of pipe (ft)
- w = soil density (lbs/ft<sup>3</sup>) = 120 lbs/ft<sup>3</sup>

## **8" ASTM D3034 SDR-26**

$$P = 20 * 120$$

$$P = 2,400 \text{ lbs/ft}^2 \text{ or } 16.67 \text{ psi}$$

## **12" ASTM D3034 SDR-26**

$$P = 20 * 120$$

$$P = 2,400 \text{ lbs/ft}^2 \text{ or } 16.67 \text{ psi}$$

*Long Term Deflection Calculations* - the following equations utilized for the calculation of long term deflection are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$\Delta Y/D = \frac{DL * K * P + K * W_1}{[2E / (3(DR - 1)^3)] + 0.061 * E'} * 100 \quad (\text{Equation 7.10})$$

Where:

- $\Delta Y/D$  = long term deflection (%)
- DL = Deflection Lag Factor = 1.0 for prism load calculation
- K = bedding constant = 0.096 for 90°
- P = prism load pressure due to soil weight (lbs/ft<sup>2</sup>)
- W<sub>1</sub> = live load (psi) = 0 psi
- E = modulus of elasticity (psi) = 400,000 psi for PVC
- DR = dimension ratio
- E' = modulus of soil reaction (psi) = 2,000 psi for crushed rock bedding compacted to greater than 95% relative density

Note: Leonhardt's Zeta factor is assumed to equal 1, and thus is not required in the calculation.

This is a conservative assumption that results in a more conservatively calculated value for long term deflection.

## **8" ASTM D3034 SDR-26**

$$\Delta Y/D = \frac{1.0 * 0.096 * 16.67 + 0.096 * 0}{[2(400,000)/(3(26-1)^3)] + 0.061 * 2,000} * 100$$

$$\Delta Y/D = 1.15\%$$

## **12" ASTM D3034 SDR-26**

$$\Delta Y/D = \frac{1.0 * 0.096 * 16.67 + 0.096 * 0}{[2(400,000)/(3(26-1)^3)] + 0.061 * 2,000} * 100$$

$$\Delta Y/D = 1.15\%$$

*Wall Crushing Calculations* - the following equations utilized for the calculation of wall crushing are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$P_y = \frac{\Theta_c * 2 * A}{D} \quad (\text{Equation 7.20})$$

$$H = P_y / w \quad (\text{Equation 6.7})$$

Where:

- $P_y$  = pressure due to soil weight (psi)
- $\Theta_c$  = compressive stress (psi) = 4,000 psi for PVC pipe
- $A$  = surface area of the pipe wall (in<sup>2</sup>/in)
- $D$  = mean pipe diameter (in) =  $D_o - t$
- $t$  = pipe wall thickness (in)
- $H$  = maximum allowable height of cover (ft)
- $w$  = soil density (lbs/ft<sup>3</sup>) = 120 lbs/ft<sup>3</sup>

## **8" ASTM D3034 SDR-26**

$$D_o = 8.4 - 0.323 = 8.077 \text{ in}, A = 3.88 \text{ in}^2/\text{ft} (0.323 \text{ in} * 12 \text{ in/ft})$$

$$P_y = \frac{4,000 * 2 * (3.88/12)}{8.077}$$

$$P_y = 320.25 \text{ psi}$$

$$H = (320.25 * 144) / 120$$

$$H = 384.30 \text{ ft height of soil to cause wall crushing}$$

## **12" ASTM D3034 SDR-26**

$$D_o = 12.500 - 0.481 = 12.019 \text{ in}, A = 5.77 \text{ in}^2/\text{ft} (0.481 \text{ in} * 12 \text{ in/ft})$$

$$P_y = \frac{4,000 * 2 * (5.77 / 12)}{12.019}$$

$$P_y = 320.05 \text{ psi}$$

$$H = (320.05 * 144) / 120$$

**H = 384.06 ft height of soil to cause wall crushing**

*Strain Calculations* - the following equations utilized for the calculation of strain are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$\epsilon_h = \frac{P * D}{2 * t * E} \quad (\text{Equation 7.22})$$

$$\epsilon_f = \frac{t}{D} * \frac{[3 * \Delta Y / D]}{[1 - 2 * \Delta Y / D]} \quad (\text{Equation 7.24})$$

$$\epsilon = \epsilon_h + \epsilon_f \quad (\text{Equation 7.25})$$

Where:

$\epsilon_h$  = maximum strain in the pipe wall due to hoop stress (in/in)

P = prism load pressure due to soil weight (psi)

D = mean pipe diameter (in) =  $D_o - t$

t = pipe wall thickness (in)

E = modulus of elasticity (psi) = 400,000 psi for PVC

$\epsilon_f$  = maximum strain in the pipe due to ring deflection or flexure (in/in)

$\Delta Y / D$  = long term deflection

$\epsilon$  = maximum combined strain in pipe wall (in/in)

## **8" ASTM D3034 SDR-26**

$$\epsilon_h = \frac{16.67 * 8.077}{2 * 0.323 * 400,000}$$

$$\epsilon_h = 0.00052 \text{ in/in}$$

$$\epsilon_f = \frac{0.323}{8.077} * \frac{[3 * 0.0115]}{[1 - 2 * 0.0115]}$$

$$\epsilon_f = 0.0014 \text{ in/in}$$

$$\epsilon = 0.00035 + 0.0014$$

**APPLICATION SECTION**  
**ATTACHMENT A**



$$\epsilon = 0.00175 \text{ in/in}$$

## **12" ASTM D3034 SDR-26**

$$\epsilon_h = \frac{16.67 * 12.019}{2 * 0.481 * 400,000}$$

$$\epsilon_h = 0.00052 \text{ in/in}$$

$$\epsilon_f = \frac{0.481}{12.019} * \frac{[3 * 0.0115]}{[1 - 2 * 0.0115]}$$

$$\epsilon_f = 0.00141 \text{ in/in}$$

$$\epsilon = 0.00052 + 0.00141$$

$$\epsilon = 0.00193 \text{ in/in}$$

Per the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001), deflection test samples have experienced a pipe wall strain of up to 0.025 in/in and have not "showed any failures or cracks". The calculated strains for this project are significantly below this level, so no failure due to strain is anticipated.

*Pipe Stiffness Calculation* - the following equations utilized for the calculation of pipe stiffness are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$P_s = 4.47 * \frac{E}{(DR - 1)^3} \quad (\text{Equation 7.3})$$

Where:

$P_s$  = pipe stiffness (psi)

$DR$  = Dimensional Ratio =  $D_o / t$

$D_o$  = Outside diameter (in)

$t$  = pipe wall thickness (in)

$E$  = modulus of elasticity (psi) = 400,000 psi for PVC

## **8" ASTM D3034 SDR-26**

$$DR = 26$$

$$P_s = 4.47 * \frac{400,000}{(26 - 1)^3}$$

$$P_s = 115 \text{ psi}$$

## **12" ASTM D3034 SDR-26**

$$DR = 26$$

$$P_s = 4.47 * \frac{400,000}{(26 - 1)^3}$$

**Ps = 115 psi**

## **Criteria for Laying Pipe**

### ***Pipe Embedment***

Bedding and initial backfill material selection and installation will be carried out in accordance with applicable governing procedures contained within the *City of Austin Standard Specifications for Pipes and Appurtenances*, *TCEQ Chapter 217.54(a)*, and in accordance with the City of Leander Detail 104-1 on sheet 80. Bedding material shall be in accordance with City of Austin Standard Specification Item 510, Section 510.3(14). Compacted backfill, from a point one (1) foot above the pipe to the finished surface, will be comprised of suitable material removed during excavation, as described in Item 510, Section 510.2(6). Brush, debris, and junk shall not be utilized as a backfilling material.

### ***Compaction***

Trench compaction will be carried out in accordance with the *City of Austin Standard Specifications for Pipes and Appurtenances* and *TCEQ Chapter 217.54(b)*. Proper placement of the backfill and compaction per City of Austin requirements will not negatively impact the structural integrity of the pipe.

### ***Envelope Size***

Envelope size will be in accordance with *City of Austin Standard Specifications for Pipes and Appurtenances* and *TCEQ Chapter 217.54(c)*. Per the City of Leander Detail 104-1 on sheet 81, a minimum of 6-inch and maximum of 12-inch space shall be allowed between the outside diameter of the pipe and the trench wall and floor. In addition, a minimum of 6-inch and maximum of 12-inch space shall be allowed between the outside diameter of the pipe bell and the trench wall. The embedment and initial backfill must be installed to a minimum depth of 12 inches above the crown of the pipe.

### ***Trench Width***

Trench width will be in accordance with the City of Leander Detail 104-1 on sheet 80 and *TCEQ Chapter 217.54(d)*. Per the City of Leander Detail 104-1 on sheet 80, a minimum of 6-inch and maximum of 12-inch space shall be allowed between the outside diameter of the pipe and the trench wall and floor. In addition, a minimum of 6-inch and maximum of 12-inch space shall be allowed between the outside diameter of the pipe bell and the trench wall. These limits shall be maintained to protect the structural integrity of the pipe and will be sufficient for the placement of materials and use of compaction equipment in the pipe zone.

## **Manholes and Related Structures**

### ***Manhole and Appurtenance Placement***

Manholes are located at all points of change in alignment or grade and at the intersection of all pipes for this project.

## ***Manhole Stub Outs***

No manholes are being placed at the end of a line that may be extended in the future, so no stub outs are included on this project.

## ***Cleanouts***

No dead end lines are included in this project, so no cleanouts are proposed.

## ***Manhole Material***

Monolithic or precast manholes are acceptable for the contractor to utilize and are included in the City of Austin Detail 506S-10 on sheet 80. The use of bricks is not acceptable for the manhole or for cover adjustments.

## ***Manhole Spacing***

Manhole spacing meets the requirements of Table C.2 in *TCEQ Chapter 217.55*.

## ***Manholes within Waterways***

No manholes will be located within flow paths of waterways or in areas where water ponding is probable.

## ***Manhole Covers, Inlets, and Bases***

Per the COA detail 506S-10 sheet 80, the manhole covers shall have a 30-inch diameter clear opening. Manhole covers shall be constructed of cast iron and have no openings for water to infiltrate. No proposed manholes are located within the 100-year flood plain. All manholes shall be watertight, with watertight rings and covers, as shown per the City of Leander detail 107-3 on sheet 80.

As shown in the project details, the bottom of the manhole shall have a U-shaped channel to provide smooth continuation between the inlet and outlet pipes. For the proposed pipe, the manhole channel depth shall be equal to at least half the largest pipe diameter. Manholes with different pipe sizes shall have the tops of the pipes at the same elevation and flow channels in the invert sloped evenly from pipe to pipe. A bench will be provided above each manhole channel to slope at a minimum of 0.5 inches per foot.

## ***Manhole Steps***

No steps shall be allowed in any proposed manholes.

## ***Manhole Connections***

Manhole-pipe connections shall be watertight per City of Austin pipe to manhole connector SPL WW-146D. See detail 506S-10 on Sheet 80.

## ***Manhole Venting***

The proposed manholes are spaced at less than 1,500 foot intervals and none are located within the 100-year flood plain. Therefore, no vented manholes are proposed on this project.

## **Trenchless Pipe Installation**

There will be no trenchless pipe installation.

## **Testing Requirements for Gravity Pipes**

### ***Infiltration/Exfiltration and Low Pressure Air Test***

All testing will be in compliance with Texas Administrative Code title 30 Part 1 Chapter 217 Subchapter C 217.57 and 217.58. See TCEQ note on Sheet 3.

Infiltration and exfiltration or low pressure air testing in accordance with ASTM C828, C924 or F1417 are required for all proposed gravity wastewater pipe as specified in the project notes, Sheet 3. The requirements specified are in accordance with *TCEQ Chapter 217.57*.

### ***Deflection Testing***

For the proposed 8-inch and 12-inch wastewater line, deflection shall be measured with a rigid mandrel per the project detail on Sheet 3. The requirements specified are in accordance with *TCEQ Chapter 217.57*.

### ***Owner Inspection***

The Owner shall have an inspector onsite during construction of the project. A professional engineer registered in the state of Texas (Alejandro E. Granados Rico, P.E.) shall be present to witness the testing of the wastewater lines.

## **Testing Requirements for Manholes**

Manhole testing in accordance with *TCEQ Chapter 217.58* is specified in the project notes, sheet 3. Manholes will be tested after assembly and backfilling for leakage by either a hydrostatic test and/or a vacuum test.

For the vacuum test, all lift holes and exterior joints shall be plugged with an approved non-shrink grout and no grout shall be placed in horizontal joints before testing. All pipes entering the manhole shall be plugged, taking care to securely brace the plugs from being drawn into the manhole. Stubouts, manhole boots and pipe plugs shall be secured to prevent movement while the vacuum is drawn. A minimum 60-inch/lb torque wrench shall be used to tighten the external clamps that secure the test cover to the top of the manhole. The test head shall be placed at the inside of the top of the cone section and the seal inflated in accordance with the manufacturer's recommendation. A vacuum of 10 inches of mercury shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to 9 inches of mercury. The manhole shall pass if the time is greater than 2 minutes. If the manhole fails the initial test, necessary repairs shall be made with a non-shrink grout while the vacuum is still being drawn. If the manhole fails a second time, repairs should again be made and the manhole shall be tested by means of a hydrostatic test. If any manhole fails the hydrostatic test, after failing the vacuum test twice, the contractor should consider replacing that manhole. If the contractor chooses to attempt to repair that manhole, the manhole must be retested by means of the hydrostatic test until it passes.

Inspection will be provided during critical phases of construction by a qualified inspector under the direction of a P.E. (Alejandro E. Granados Rico, P.E.). Critical phases of construction are deemed at a minimum to include testing of pipe and manholes for leakage, and testing of flexible pipe for installed deflection.

TCEQ approval letters for plans and specifications review contain the requirement that once the project is completed, a P.E. registered in the state of Texas (Alejandro E. Granados Rico, P.E.) must certify that the construction was performed substantially in accordance with the approved plans and specifications.

## **Notification and Inspection**

*TCEQ Chapter 213* requires that the applicant must provide written notification to the Austin regional office at least 48 hours prior to commencing construction on the regulated activity. If any sensitive feature is discovered during construction then the work shall be suspended immediately and the Austin regional office shall be notified to then determine the appropriate course of action. All other notification and inspection requirements identified in *TCEQ Chapter 213.5(c)* shall be met.

# SECTION 5: TEMPORARY STORMWATER SECTION



# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Alejandro E. Granados Rico, P.E.

Date: November 7th, 2023

Signature of Customer/Agent:



---

Regulated Entity Name: Edgewood Phase 2, Section 2

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

- ☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: N/A

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☒ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

11. ☒ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.

☒ N/A

12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

## ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## Spill Response Actions

If there is an accidental spill on site, the contractor shall respond with appropriate action. The contractor will be required to contact the owner and in turn the owner will contact the TCEQ in the event of a spill on site. In addition to the following guidance, reference the latest version of TCEQ's Technical Guidance Manual (TGM) RG-348 Section 2.4.16.

### Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

### Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
  - Contain the spread of the spill.
  - Recover spilled materials.
  - Clean the contaminated area and properly dispose of contaminated materials.

### Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

### Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at (512)339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.



- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

## Potential Sources of Contamination

Potential Source: Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle dripping.

Preventative Measures: Vehicle maintenance will be performed within the construction staging area or a local maintenance shop.

Potential Source: Miscellaneous trash and litter from construction workers and material wrappings.

Preventative Measures: Trash containers will be placed throughout the site to encourage proper disposal of trash.

Potential Source: Silt leaving the site.

Preventative Measures: Contractor will install all temporary best management practices prior to start of construction including the stabilized construction entrance to prevent tracking onto adjoining streets.

Potential Source: Construction Debris.

Preventative Measures: Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

Potential Source: Soil and Mud from Construction Vehicle tires as they leave the site.

Preventative Measures: A stabilized construction exit shall be utilized as vehicles leave the site. Any soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

Potential Source: Sediment from soil, sand, gravel and excavated materials stock piled on site.

Preventative Measures: Silt fence shall be installed on the down gradient side of the stock piled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

Potential Source: Portable toilet spill.

Preventative Measures: Toilets on the site will be emptied on a regular basis by the contracted toilet company.

## Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage to be disturbed is listed in parentheses next to each activity.

### Intended Schedule or Sequence of Major Activities:

1. Construct Access (0.05 Acres)
2. Installation of Temporary BMPs (45.27 Acres)
3. Initiate Grubbing and Topsoil Stripping of Site (45.27 Acres)
4. Rough Subgrade Preparation (earthwork, grading, street and drainage excavation and embankment) (45.27 Acres)
5. Wet and Dry Utility Construction (6 Acres)
6. Final Subgrade Preparation (6 Acres)
7. Installation of Base Materials (5 Acres)
8. Concrete (foundations, curbs, flatwork) (4 Acres)
9. Building Construction (5 Acres)
10. Paving Activities (3.5 Acres)
11. Topsoil, Irrigation and Landscaping (45.27 Acres)
12. Site cleanup and Removal of Temporary BMPs (45.27 Acres)

Maximum total construction time is not expected to exceed 36 months.

# Temporary Best Management Practices and Measures

- A. No storm water originates up gradient that impacts the site. An upstream off-site area will bypass through an existing channel.
- B. Temporary BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed on site to reduce vehicle “tracking” onto adjoining streets. A concrete washout pit will be used to collect all excess concrete during construction.

BMPs for this project will protect surface water or groundwater from turbid water, phosphorus, sediment, oil, and other contaminants, which may mobilize in storm water flows by slowing the flow of runoff to allow sediment and suspended solids to settle out of the runoff.

Practices may also be implemented on site for interim and permanent stabilization. Stabilization practices may include but are not limited to: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of existing trees and vegetation, and other similar measures.

- C. There are three sensitive features located in Phase 2-2, as noted in the geologic assessment. A buffer will be provided for 50 feet in all directions. Any excavation within 50 feet of the feature will be avoided. We are not proposing and fill or covering of the sensitive features.

There are no surface streams within the boundaries of the project. The temporary onsite BMPs will be used to treat stormwater runoff before it leaves the project and prevent pollutants from entering into surface streams or any sensitive features down-gradient of the site.

- D. The BMPs for this project are designed to allow water to pass through after sedimentation has occurred. Existing flow patterns will be maintained to any naturally occurring sensitive features that are discovered during construction.

Temporary runoff protection measures will be installed according to the recommendations made in Chapter 1 of RG-348. Temporary erosion control will be placed as close to the site of construction soil disturbance as possible to minimize any disturbance with drainage areas. Frequent inspections of erosion controls will be warranted near the environmentally sensitive features, especially after every rainfall.

## Request To Temporarily Seal a Feature

The permanent sealing of or diversion of flow from a naturally-occurring “sensitive” or “possibly sensitive” feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed for any naturally occurring “sensitive” or “possibly sensitive” features on this site.



## Structural Practices

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets. A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck washout pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all structural temporary BMP's are shown on the erosion control plan sheet and details and specifications are provided on the erosion control details sheet which can be found at the end of this report under Section 8.

### Description of Temporary BMPs

#### Temporary Construction Entrance/Exit

The purpose of a temporary gravel construction entrance is to provide a stable entrance/exit condition from the construction site and keep mud and sediment off public roads. A stabilized construction entrance is a stabilized pad of crushed stone located at any point traffic will be entering or leaving the construction site from a public right-of-way, street, alley, sidewalk or parking area. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking or flowing of sediment onto public rights-of-way. This practice should be used at all points of construction ingress and egress.

Excessive amounts of mud can also present a safety hazard to roadway users. To minimize the amount of sediment loss to nearby roads, access to the construction site should be limited to as few points as possible and vegetation around the perimeter should be protected where access is not necessary. A rock stabilized construction entrance should be used at all designated access points.

Inspection and Maintenance Guidelines:

- (1) The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment.
- (2) All sediment spilled, dropped, washed, or tracked onto public rights-of-way should be removed immediately by contractor.
- (3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
- (4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
- (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

#### Silt Fence

The purpose of a silt fence is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Silt fence is used during the period of construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This fence should remain in place until the disturbed area is permanently stabilized. Silt fence should not be used where there is a concentration of water in a channel or drainage way. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

Silt fencing within the site may be temporarily moved during the day to allow construction activity provided it is replaced and properly anchored to the ground at the end of the day. Silt fences on the perimeter of the site or around drainage ways should not be moved at any time.

## Inspection and Maintenance Guidelines:

- (1) Inspect all fencing weekly, and after any rainfall.
- (2) Remove sediment when buildup reaches 6 inches.
- (3) Replace any torn fabric or install a second line of fencing parallel to the torn section.
- (4) Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
- (5) When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

## Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:
  - Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
  - Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.

Below grade concrete washout facilities are typical. These consist of a lined excavation sufficiently large to hold expected volume of washout material. Above grade facilities are used if excavation is not practical. Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this section, with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.

## Rock Berm

The purpose of a rock berm is to serve as a check dam in areas of concentrated flow, to intercept sediment-laden runoff, detain the sediment and release the water in sheet flow. The rock berm should be used when the contributing drainage area is less than 5 acres. Rock berms are used in areas where the volume of runoff is too great for a silt fence to contain. They are less effective for sediment removal than silt fences, particularly for fine particles, but are able to withstand higher flows than a silt fence. As such, rock berms are often used in areas of channel flows (ditches, gullies, etc.). Rock berms are most effective at reducing bed load in channels and should not be substituted for other erosion and sediment control measures further up the watershed.

### Inspection and Maintenance Guidelines:

- (1) Inspection should be made weekly and after each rainfall by the responsible party. For installations in streambeds, additional daily inspections should be made.
- (2) Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.
- (3) Repair any loose wire sheathing.
- (4) The berm should be reshaped as needed during inspection.
- (5) The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.
- (6) The rock berm should be left in place until all upstream areas are stabilized and accumulated silt removed.

## Inlet Protection

Storm sewers that are made operational prior to stabilization of the associated drainage areas can convey large amounts of sediment to natural drainage ways. In case of extreme sediment loading, the storm sewer itself may clog and lose a major portion of its capacity. To avoid these problems, it is necessary to prevent sediment from entering the system at the inlets. The following guidelines for inlet protection are based primarily on recommendations by the Virginia Dept. of Conservation and Recreation (1992) and the North Central Texas Council of Governments (NCTCOG, 1993b).

In developments for which drainage is to be conveyed by underground storm sewers (i.e., streets with curbs and gutters), all inlets that may receive storm runoff from disturbed areas should be protected. Temporary inlet protection is a series of different measures that provide protection against silt transport or accumulation in storm sewer systems. This clogging can greatly reduce or completely stop the flow in the pipes. The different measures are used for different site conditions and inlet types.

Care should be taken when choosing a specific type of inlet protection. Field experience has shown that inlet protection that causes excessive ponding in an area of high construction activity may become so inconvenient that it is removed or bypassed, thus transmitting sediment-laden flows unchecked. In such situations, a structure with an adequate overflow mechanism should be utilized.

It should also be noted that inlet protection devices are designed to be installed on construction sites and not on streets and roads open to the public. When used on public streets these devices will cause ponding of runoff, which can cause minor flooding and can present a traffic hazard. An example of appropriate siting would be a new subdivision where the storm drain system is installed before the area is stabilized and the streets open to the general public. When construction occurs adjacent to active streets, the sediment should be controlled on site and not on public thoroughfares. Occasionally, roadwork or utility installation will occur on public roads. In these cases, inlet protection is an appropriate temporary BMP.

The following inlet protection devices are for drainage areas of one acre or less. Runoff from larger disturbed areas should be routed to a temporary sediment trap or basin.

Filter barrier protection using silt fence is appropriate when the drainage area is less than one acre and the basin slope is less than five percent. This type of protection is not applicable in paved areas.

Block and gravel protection is used when flows exceed 0.5 cubic feet per second and it is necessary to allow for overtopping to prevent flooding. This form of protection is also useful for curb type inlets as it works well in paved areas.

Wire mesh and gravel protection is used when flows exceed 0.5 cubic feet per second and construction traffic may occur over the inlet. This form of protection may be used with both curb and drop inlets.

Excavated impoundment protection around a drop inlet may be used for protection against sediment entering a storm drain inlet. With this method, it is necessary to install weep holes to allow the impoundment to drain completely. If this measure is implemented, the impoundment should be sized such that the volume of excavation is 3,600 cubic feet per acre (equivalent to 1 inch of runoff) of disturbed area entering the inlet.

#### Inspection and Maintenance Guidelines:

- (1) Inspection should be made weekly and after each rainfall. Repair or replacement should be made promptly as needed by the contractor.
- (2) Remove sediment when buildup reaches a depth of 3 inches. Removed sediment should be deposited in a suitable area and in such a manner that it will not erode.
- (3) Check placement of device to prevent gaps between device and curb.
- (4) Inspect filter fabric and patch or replace if torn or missing.
- (5) Structures should be removed and the area stabilized only after the remaining drainage area has been properly stabilized.

## Drainage Area Map

There are two areas greater than 10 acres within a common drainage area that will be disturbed at one time. WQP-C1 and NT-1 are both greater than 10 acres and will be disturbed. An existing and proposed drainage area map is provided at the end of this report in Section 8 to support the aforementioned requirement.



# Temporary Sediment Pond(s) Plans and Calculations

A sedimentation basin is required, where feasible, for a common drainage location that serves an area with ten (10) or more acres disturbed at one time.

A sedimentation basin may be temporary or permanent and must provide sufficient storage to contain a calculated volume of runoff from a 2-year, 24-hour storm from each disturbed acre drained. When calculating the volume of runoff from a 2-year, 24-hour storm event, it is not required to include the flows from offsite areas and flow from onsite areas that are either undisturbed or have already undergone permanent stabilization, if these flows are diverted around both the disturbed areas of the site and the sediment basin.

Where rainfall data is not available or a calculation cannot be performed, the sedimentation basin must provide at least 3,600 cubic feet of storage per acre drained until final stabilization of the site.

If a sedimentation basin is not feasible, then the permittee shall provide equivalent control measures until final stabilization of the site. In determining whether installing a sediment basin is feasible, the permittee may consider factors such as site soils, slope, available area, public safety, precipitation patterns, site geometry, site vegetation, infiltration capacity, geotechnical factors, depth to groundwater, and other similar considerations. The permittee shall document the reason that the sediment basins are not feasible, and shall utilize equivalent control measures, which may include a series of smaller sediment basins.

## **Sites With Drainage Areas Less than Ten Acres**

Sediment traps and sediment basins may be used to control solids in storm water runoff for drainage locations serving less than ten (10) acres.

Alternatively, a sediment basin that provides storage for a calculated volume of runoff from a 2-year, 24-hour storm from each disturbed acre drained may be utilized. Where rainfall data is not available or a calculation cannot be performed, a temporary or permanent sediment basin providing 3,600 cubic feet of storage per acre drained may be provided.

## **Proposed Sedimentation Basin Calculations**

For Edgewood Phase 2, Section 2, the proposed onsite batch detention ponds will serve as a storage for on-site and off-site drainage. The basins will be designed to contain the 3,600 cubic feet per acre of disturbed area draining to the pond.

### **Temporary Sedimentation:**

Two batch detention pond will serve as storage for on-site and off-site drainage for Edgewood Phase 2, Section 2 (as shown on sheets 60 & 61 of the construction drawings) during the construction phase. Drainage area C-1 includes 15.72 acres and generates a volume of 55,592 ft<sup>3</sup>. The proposed detention pond (C-1) will contain a volume of 272,275 ft<sup>3</sup>, thus the constructed detention pond will be adequately sized for sedimentation purposed for drainage area C-1. Drainage area C-2 includes 9.33 acres and generates a volume of 33,588 ft<sup>3</sup>. The proposed detention pond (C-2) will contain a volume of 245,708 ft<sup>3</sup>, thus the constructed detention pond will be adequately sized for sedimentation purposed for drainage area C-2.

# Inspection and Maintenance for BMPs

## Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

## Inspection Schedule

The primary operator is required to choose one of the two inspections listed below.

- ☐ **Option 1:** Once every seven calendar days. If this alternative schedule is developed, then the inspection must occur regardless of whether or not there has been a rainfall event since the previous inspection.
- ☐ **Option 2:** Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of “dry” season and beginning of “wet” season).

If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded.

Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized;
- areas used for storage of materials that are exposed to precipitation;
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system);
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly); and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking).

## Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

## Inspection Report Forms

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

## ***Corrective Action***

### **Personnel Responsible for Corrective Actions**

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

### **Corrective Action Forms**

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.

## ***Schedule of Interim and Permanent Soil Stabilization***

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
2. Sodding and Wood Mulch: As per the project landscaping plan, Sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a) The dates when major grading activities occur;
- b) The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c) The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be

initiated no more that fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.

Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

## **Maintenance**

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)
- Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.
- Silt fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Straw bale dike will be inspected and repaired as necessary.
- Diversion dike will be inspected and any breaches promptly repaired.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must work with the owner or operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

- Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of storm water controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.

## Inspector Qualifications Log\*

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_  
Qualifications (Check as appropriate and provide description):  
☐ Training Course \_\_\_\_\_  
☐ Supervised Experience \_\_\_\_\_  
☐ Other \_\_\_\_\_

*\* The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.*



## Amendment Log

[illegible]

Construction Activity Sequence Log

Name of Operator	Projected dates Month/year	Activity Disturbing Soil clearing, excavation, etc.	Location on-site where activity will be conducted	Acreage being disturbed

\*Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.

## Stormwater Control Installation and Removal Log

[illegible]

## Stabilization Activities Log

[illegible]

Stabilization and erosion control practices may include, but are not limited to: establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.

## Inspection Frequency Log

[illegible]



## ***Rain Gauge Log***

[illegible]

General Information					
Name of Project		Tracking No.		Inspection Date	
Inspector Name, Title & Contact Information					
Present Phase of Construction					
Inspection Location (if multiple inspections are required, specify location where this inspection is being conducted)					
<b>Inspection Frequency</b> Standard Frequency: <input type="checkbox"/> Weekly <input type="checkbox"/> Every 14 days and within 24 hours of a 0.25” rain Increased Frequency: <input type="checkbox"/> Every 7 days and within 24 hours of a 0.25” rain Reduced Frequency: - <input type="checkbox"/> Once per month (for stabilized areas) - <input type="checkbox"/> Once per month and within 24 hours of a 0.25” rain (for arid, semi-arid, or drought-stricken areas during seasonally dry periods or during drought) - <input type="checkbox"/> Once per month (for frozen conditions where earth-disturbing activities are being conducted)					
<b>Was this inspection triggered by a 0.25” storm event?</b> <input type="checkbox"/> Yes <input type="checkbox"/> No <b>If yes, how did you determined whether a 0.25” storm event has occurred?</b> <input type="checkbox"/> Rain gauge on site <input type="checkbox"/> Weather station representative of site. Specify weather station source:  <b>Total rainfall amount that triggered the inspection (in inches):</b>					
<b>Unsafe Conditions for Inspection</b> <b>Did you determine that any portion of your site was unsafe for inspection?</b> <input type="checkbox"/> Yes <input type="checkbox"/> No <b>If “yes”, complete the following:</b> -        Describe the conditions that prevented you from conducting the inspection in this location:          -        Location(s) where conditions were found:					

Condition and Effectiveness of Erosion and Sediment (E&S) Controls				
Type/Location of E&S Control	Repairs or Other Maintenance Needed?	Corrective Action Required?	Date on Which Maintenance or Corrective Action First Identified?	Notes
1.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
2.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
3.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
4.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
5.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
6.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
7.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
8.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
9.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
10.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		

Condition and Effectiveness of Pollution Prevention (P2) Practices				
Type/Location of P2 Practices	Repairs or Other Maintenance Needed?	Corrective Action Required?	Identification Date	Notes
1.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
2.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
3.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
4.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
5.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
6.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
7.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
8.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
9.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
10.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		

Stabilization of Exposed Soil			
Stabilization Area	Stabilization Method	Have You Initiated Stabilization?	Notes
1.		<input type="checkbox"/> YES <input type="checkbox"/> NO If yes, provide date:	
2.		<input type="checkbox"/> YES <input type="checkbox"/> NO If yes, provide date:	
3.		<input type="checkbox"/> YES <input type="checkbox"/> NO If yes, provide date:	
4.		<input type="checkbox"/> YES <input type="checkbox"/> NO If yes, provide date:	
5.		<input type="checkbox"/> YES <input type="checkbox"/> NO If yes, provide date:	
Description of Discharges			
<b>Was a stormwater discharge or other discharge occurring from any part of your site at the time of the inspection?</b> <input type="checkbox"/> Yes <input type="checkbox"/> No <b>If “yes”, provide the following information for each point of discharge:</b>			
Discharge Location	Observations		
1.	Describe the discharge:  At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		
2.	Describe the discharge:  At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		
3.	Describe the discharge:  At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		

## Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

**Signature of Contractor or Subcontractor:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Printed Name and Affiliation:** \_\_\_\_\_

## Certification and Signature by Permittee

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

**Signature of Permittee or  
"Duly Authorized Representative":** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Printed Name and Affiliation:** \_\_\_\_\_



Section A – Initial Report				
(Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)				
Name of Project		Tracking No.		Today's Date
Date Problem First Discovered			Time Problem First Discovered	
Name and Contact Information of Individual Completing this Form				
<p>What site conditions triggered the requirement to conduct corrective action:</p> <p><input type="checkbox"/> A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3</p> <p><input type="checkbox"/> The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards</p> <p><input type="checkbox"/> A prohibited discharge has occurred or is occurring</p> <p>Provide a description of the problem:</p> <p>Deadline for completing corrective action (<i>Enter date that is either: (1) no more than 7 calendar days after the date you discovered the problem, or (2) if it is infeasible to complete work within the first 7 days, enter the date that is as soon as practicable following the 7th day</i>):</p> <p>If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe:</p>				
Section B – Corrective Action Progress				
(Complete this section <u>no later than 7 calendar days</u> after discovering the condition that triggered corrective action)				
Section B.1 – Why the Problem Occurred				
Cause(s) of Problem (Add an additional sheet if necessary)			How This Was Determined and the Date You Determined the Cause	
1.			1.	
2.			2.	
3.			3.	
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem				
List of Stormwater Control Modification(s) Needed to Correct Problem (Add an additional sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes	
1.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		
2.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		
3.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		

Section A – Initial Report				
(Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)				
Name of Project		Tracking No.		Today's Date
Date Problem First Discovered			Time Problem First Discovered	
Name and Contact Information of Individual Completing this Form				
<p>What site conditions triggered the requirement to conduct corrective action:</p> <p><input type="checkbox"/> A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3</p> <p><input type="checkbox"/> The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards</p> <p><input type="checkbox"/> A prohibited discharge has occurred or is occurring</p> <p>Provide a description of the problem:</p> <p>Deadline for completing corrective action (<i>Enter date that is either: (1) no more than 7 calendar days after the date you discovered the problem, or (2) if it is infeasible to complete work within the first 7 days, enter the date that is as soon as practicable following the 7th day</i>):</p> <p>If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe:</p>				
Section B – Corrective Action Progress				
(Complete this section <u>no later than 7 calendar days</u> after discovering the condition that triggered corrective action)				
Section B.1 – Why the Problem Occurred				
Cause(s) of Problem (Add an additional sheet if necessary)			How This Was Determined and the Date You Determined the Cause	
1.			1.	
2.			2.	
3.			3.	
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem				
List of Stormwater Control Modification(s) Needed to Correct Problem (Add an additional sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes	
1.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		
2.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		
3.		<input type="checkbox"/> Yes <input type="checkbox"/> No Date:		

## Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

**Signature of Contractor or Subcontractor:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Printed Name and Affiliation:** \_\_\_\_\_

## Certification and Signature by Permittee

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

**Signature of Permittee or  
"Duly Authorized Representative":** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Printed Name and Affiliation:** \_\_\_\_\_

# **SECTION 6:**

## **LIFT STATION/FORCE MAIN**

# Lift Station/Force Main System Application

Texas Commission on Environmental Quality

for Regulated Activities On the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c)(3)(B) and (c), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

Regulated Entity Name: Edgewood Phase 2, Section 2

## Customer Information

*(If different than customer information provided on core data form)*

1. The person(s) responsible for providing the engineering certification to the TCEQ pursuant to 30 TAC §213.5(f)(2)(C) during construction and 30 TAC §213.5 (c)(3)(D) upon completion of construction is:

Contact Person: Kyle Kriegel

Entity: M/I Homes of Austin, LLC

Mailing Address: 7600 N. Capital of Texas Hwy.; Bldg. C, Suite 250

City, State: Austin, Texas

Zip: 78731

Telephone: (512) 779-8524

Fax: N/A

Email Address: kkriegel@mihomes.com

2. The engineer responsible for the design of this lift station and force main:

Contact Person: Tara Raoof, P.E.

Entity: Kimley-Horn and Associates Inc.

Mailing Address: 10814 Jollyville Road, Campus IV, Suite 200

City, State: Austin, Texas

Zip: 78759

Telephone: (737) 270 7767

Fax: \_\_\_\_\_

Email Address: tara.raoof@kimley-horn.com

Texas Licensed Professional Engineer's Serial Number: 141851

## Project Information

3. This project is for the construction or replacement of:

☐ Lift Station only.

- ☐ Lift Station and Force Main system.  
☒ Lift Station, Force Main, and Gravity system.
4. The sewage collection system will convey the wastewater to the Brushy Creek Wastewater (name) Treatment Plant. The treatment facility is:
- ☒ Existing  
☐ Proposed
5. All components of this lift station/force main system will comply with:
- ☒ The City of Leander and Austin standard specifications.  
☐ Other. Specifications are attached.

### *Site Plan Requirements*

*Items 6-14 must be included on the Site Plan.*

6. ☒ The Site Plan must have a minimum scale of 1" = 400'.
- Site Plan Scale: 1" = 10'.
7. ☒ Lift station/force main system layout meets all requirements of 30 TAC Chapter 217.
8. Geologic or Manmade Features:
- ☐ No geologic or manmade features were identified in the Geologic Assessment.  
☒ All geologic or manmade features identified in the Geologic Assessment (caves, solution openings, sinkholes, fractures, joints, porous zones, etc.) which exist at the site of the proposed lift station and along the path(s) or within 50 feet of each side of a proposed force main line are shown on the Site Plan and are listed in the table below. Designs used to protect the integrity of the sewer line crossing each feature are described and labeled on the attached page. A detailed design drawing for each feature is shown on Plan Sheet N/A of N/A.  
☐ No Geologic Assessment is required for this project.

Table 1 - Geologic or Manmade Features

<i>Line</i>	<i>Station to Station</i>	<i>Type of Feature</i>
N/A	to	
	to	
	to	
	to	
	to	
	to	
	to	
	to	



9. ☒ Existing topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
10. ☒ Finished topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
- ☐ Finished topographic contours will not differ from the existing topographic configuration and are not shown.

11. 100-year floodplain boundaries

- ☒ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☐ No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA Floodplain Map Dated December 20<sup>th</sup>, 2019

12. 5-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above sewer lines.)
- ☐ After construction is complete, all sections of the force main located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 2 - 5-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station to Station</i>
N/A	of	to
	of	to
	of	to
	of	to

13. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

If applicable, this must agree with Item No. 15 on the Geologic Assessment Form.

- ☐ There are \_\_\_\_\_ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)
- ☐ The wells are not in use and have been properly plugged.
- ☐ The wells are not in use and will be properly plugged.
- ☐ The wells are in use and comply with 16 TAC Chapter 76.

☒ There are no wells or test holes of any kind known to exist on the project site.

14. ☒ Legal boundaries of the site are shown.

## Plan and Profile Sheets

*The construction drawings and technical specifications will not be considered for review unless they are the final plans and technical specifications which will be used by the contractor for bidding and construction.*

*Items 15 – 18 must be included on the Plan and Profile sheets.*

15. ☒ The equipment installation construction plans must have a minimum scale of 1" = 10'.  
Plan sheet scale: 1" = 10 '.
16. ☒ Locations, descriptions and elevations of all required equipment and piping for the lift station and force main are shown and labeled.
17. ☒ Air Release/Vacuum Valves will be provided at all peaks in elevation of the proposed force main. These locations are listed in the table below and labeled on the appropriate plan and profile sheets.

Table 3 - Air Release/Vacuum Valves

<i>Line</i>	<i>Station</i>	<i>Sheet</i>
FM-A	5+48.55	56 of 113
FM-B	5+20+00	58 of 113
		of
		of
		of
		of

18. ☒ The final plans and technical specifications are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
19. ☒ Attachment A - Engineering Design Report. An engineering design report with the following required items is attached:
- ☒ The report is dated, signed, and sealed by a Texas Licensed Professional Engineer.
  - ☒ Calculations for sizing system.
  - ☒ Pump head calculations, including, but not limited to, system head and pump capacity curves, head loss calculations, and minimum and maximum static head C values for normal and peak operational conditions.
  - ☒ 100-year and 25-year flood considerations.
  - ☒ Total lift station pumping capacity with the largest pump out of service.
  - ☐ Type of pumps, including standby units.
  - ☒ Type of pump controllers, including standby air supply for bubbler controllers, as applicable.

- ☒ Pump cycle time.
- ☒ Type of wet well ventilation; include number of air changes for mechanical ventilation.
- ☒ Minimum and maximum flow velocities for the force main.
- ☒ Lift station security.
- ☒ Lift station emergency provisions and reliability.

## ***Administrative Information***

- 20. ☒ Upon completion of the wet well excavation, a geologist must certify that the excavation was inspected for the presence of sensitive features and submit the signed, sealed, and dated certification to the appropriate regional office.
- 21. ☒ The TCEQ Lift Stations and Force Mains General Construction Notes (TCEQ-0591) are included on the General Notes Sheet of the Final Construction Plans for this lift station and/or force main system.
- 22. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 23. ☒ Any modification of this lift station/force main system application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

## ***Signature***

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Lift Station/Force Main System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c)(3)(C) and 30 TAC Chapter 217, and prepared by:

Print Name of Licensed Professional Engineer: Tara Raoof, P.E.

Place engineer's seal here:

Date: 11/16/2023

Signature of Licensed Professional Engineer:

T. Raoof 2023.11.16  
16:02:49-06'00'



# SECTION 7: ADDITIONAL FORMS

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I William Peckman  
Print Name  
Area President  
Title - Owner/President/Other  
of M/I HOMES OF AUSTIN  
Corporation/Partnership/Entity Name  
have authorized Alejandro E. Granados Rico, P.E.  
Print Name of Agent/Engineer  
of Kimley-Horn and Associates  
Print Name of Firm

to represent and act on the behalf of the above-named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

William C. Peckman  
Applicant's Signature

10/30/23  
Date


THE STATE OF TEXAS §

County of Williamson §  
TRAVIS

BEFORE ME, the undersigned authority, on this day personally appeared William Peckman known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 1 day of November.

Alison McMann  
NOTARY PUBLIC



ALISON MCMANN  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 09.29.2024



# Owner Authorization Form

Texas Commission on Environmental Quality

for Required Signature

Edwards Aquifer Protection Program

Relating to 30 TAC Chapter 213

Effective June 1, 1999

## Land Owner Authorization

I, Michael Love of Cannon 140, LP  
Land Owner Signatory Name Land Owner Name (Legal Entity or Individual)

am the owner of the property located at  
BEING 45.29 ACRES OF LAND OUT OF THE MILTON HICKS SURVEY AND J.T. CHURCH SURVEY

Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize M/I Homes of Austin, LLC  
Applicant Name (Legal Entity or Individual)

to conduct Installation and maintenance of all improvements associated with Edgewood Phase 2-2 Water Pollution Abatement Plan and Organized Sewage Collection System

Description of the proposed regulated activities

at 0.8 miles southeast of the intersection of RR2243 and CR175  
Precise location of the authorized regulated activities

## Land Owner Acknowledgement

I understand that Cannon 140, LP  
Land Owner Name (Legal Entity or Individual)

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

**Land Owner Signature**

Michael Love  
Land Owner Signature

12/18/23  
Date

THE STATE OF § Texas

County of § Harris

BEFORE ME, the undersigned authority, on this day personally appeared Michael Love known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 18<sup>th</sup> day of December 2023



Brandon Compton  
NOTARY PUBLIC

Brandon Compton  
Typed or Printed Name of Notary  
MY COMMISSION EXPIRES: 03-19-2024

Attached: (Mark all that apply)

- ☐ Lease Agreement
- ☐ Signed Contract
- ☐ Deed Recorded Easement
- ☐ Other legally binding document

## ***Applicant Acknowledgement***

I, William G. Peckman of MI Homes of Austin, LLC  
Applicant Signatory Name Applicant Name (Legal Entity or Individual)

acknowledge that Cannon 140, LP  
Land Owner Name (Legal Entity or Individual)

has provided MI Homes of Austin, LLC  
Applicant Name (Legal Entity or Individual)

with the right to possess and control the property referenced in the Edwards Aquifer protection plan.

I understand that MI Homes of Austin, LLC  
Applicant Name (Legal Entity or Individual)

is contractually responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation. I further understand that failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

## ***Applicant Signature***

William G. Peckman

Applicant Signature

12/19/2023

Date

THE STATE OF § TEXAS


County of § TRAVIS

BEFORE ME, the undersigned authority, on this day personally appeared William G. Peckman known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 19 day of DECEMBER, 2023

Alison McMann

NOTARY PUBLIC



ALISON MCMANN

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 09.29.24

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Edgewood Phase 2, Section 2

Regulated Entity Location: CR175 and RR 2243

Name of Customer: M/I Homes of Austin, LLC

Contact Person: William Peckman

Phone: 512-770-8503

Customer Reference Number (if issued): 604305250

Regulated Entity Reference Number (if issued): N/A

### Austin Regional Office (3373)

☐ Hays

☐ Travis

☒ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☒ Recharge Zone

☒ Contributing Zone

☐ Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	
Sewage Collection System	8,466 LF	\$4,233
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Alexander E. Gonzalez-Rivera

Date: November 7th, 2023

## ***Application Fee Schedule***

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

### **Water Pollution Abatement Plans and Modifications**

#### **Contributing Zone Plans and Modifications**

<i>Project</i>	<i>Project Area in Acres</i>	<i>Fee</i>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

#### **Organized Sewage Collection Systems and Modifications**

<i>Project</i>	<i>Cost per Linear Foot</i>	<i>Minimum Fee- Maximum Fee</i>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

#### **Underground and Aboveground Storage Tank System Facility Plans and Modifications**

<i>Project</i>	<i>Cost per Tank or Piping System</i>	<i>Minimum Fee- Maximum Fee</i>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

#### **Exception Requests**

<i>Project</i>	<i>Fee</i>
Exception Request	\$500

#### **Extension of Time Requests**

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150



***Core Data Form***



TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other
<b>2. Customer Reference Number (if issued)</b>	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a>	<b>3. Regulated Entity Reference Number (if issued)</b>
CN 604305250		RN

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)		11/7/2023	
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information		<input type="checkbox"/> Change in Regulated Entity Ownership	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>					
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)				<i>If new Customer, enter previous Customer below:</i>	
M/I Homes of Austin, LLC					
<b>7. TX SOS/CPA Filing Number</b>		<b>8. TX State Tax ID</b> (11 digits)		<b>9. Federal Tax ID</b> (9 digits)	
0801672376		32049298139			
<b>11. Type of Customer:</b>		<input checked="" type="checkbox"/> Corporation		<input type="checkbox"/> Individual	
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited	
<b>12. Number of Employees</b>		<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<b>13. Independently Owned and Operated?</b>	
				<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator					
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> Voluntary Cleanup Applicant <input type="checkbox"/> Other:					
<b>15. Mailing Address:</b>					
7600 N. Capital of Texas Hwy.; Bldg. C, Suite 250					
City		Austin		State	TX
ZIP		78731		ZIP + 4	
<b>16. Country Mailing Information</b> (if outside USA)				<b>17. E-Mail Address</b> (if applicable)	
<b>18. Telephone Number</b>		<b>19. Extension or Code</b>		<b>20. Fax Number</b> (if applicable)	
( 512 ) 770-8503				( ) -	

## SECTION III: Regulated Entity Information

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)	
<input checked="" type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information	
<b>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</b>	
<b>22. Regulated Entity Name</b> (Enter name of the site where the regulated action is taking place.)	
Edgewood Phase 2, Section 2	



23. Street Address of the Regulated Entity: (No PO Boxes)	CR 175 and RR 2243							
	City	Leander	State	TX	ZIP	78660	ZIP + 4	
24. County	Williamson							

**Enter Physical Location Description if no street address is provided.**

25. Description to Physical Location:	Southeast of the intersection of RR 2243 and CR 175								
26. Nearest City	Leander				State	TX		Nearest ZIP Code	78660
27. Latitude (N) In Decimal:	30.585446			28. Longitude (W) In Decimal:	-97.787923				
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds				
30	35	7.98	-97	47	16.85				
29. Primary SIC Code (4 digits)	30. Secondary SIC Code (4 digits)		31. Primary NAICS Code (5 or 6 digits)		32. Secondary NAICS Code (5 or 6 digits)				
6552			237210						
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)									
Single Family Homes									
34. Mailing Address:	7600 N. Capital of Texas Hwy., Bldg. C, Suite 250								
	City	Austin	State	TX	ZIP	78731	ZIP + 4		
35. E-Mail Address:	aevetts@mihomes.com								
36. Telephone Number		37. Extension or Code			38. Fax Number (if applicable)				
( 512 ) 770-8503					( ) -				

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

#### **SECTION IV: Preparer Information**

40. Name:	Alejandro E. Granados Rico		41. Title:	Project Manager
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address	
( 512 ) 782-0602		( ) -	alex.granados@kimley-horn.com	

#### **SECTION V: Authorized Signature**

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	M/I Homes of Austin, LLC	Job Title:	Area President
Name (In Print):	William C. Beckman	Phone:	(512) 770-8524
Signature:		Date:	10/30/23

# SECTION 8: EXHIBITS



PUBLIC IMPROVEMENT CONSTRUCTION PLANS  
PROJECT #PICP-23-0105

## EDGEWOOD - PHASE 2 SECTION 2







TEXAS COMMISSION ON ENVIRONMENTAL QUALITY WATER POLLUTION ABATEMENT PLAN  
GENERAL CONSTRUCTION NOTES:

1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
  - THE NAME OF THE APPROVED PROJECT;
  - THE ACTIVITY START DATE; AND
  - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.
3. IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SINK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCEQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES MAY NOT BE RESUMED UNTIL THE TCEQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.
4. NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY OR INADEQUATELY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
6. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
7. SEDIMENT MUST BE REMOVED FROM SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
8. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
9. ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARDS AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE OTHER SITE.
10. IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF BROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
11. THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
  - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
  - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
  - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
12. THE HOLDER OF ANY APPROVED EDWARD AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
  - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
  - B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
  - C. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

TCEQ REGION 11 OFFICE  
12100 PARK 35 CIRCLE,  
BUILDING A, RM 179  
AUSTIN, TEXAS 78753-3795  
PHONE: (512) 339-2929  
FAX: (512) 339-3795

TCEQ - SEWAGE COLLECTION SYSTEM PLAN NOTES

3. THIS ORGANIZED SEWAGE COLLECTION SYSTEM (SCS) MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.5(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S (TCEQ) EDWARDS AQUIFER RULES AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.
2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROPOSED REGULATED PROJECT MUST BE PROVIDED WITH COPIES OF THE SCS PLAN AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS MUST BE REQUIRED TO KEEP ON-SITE COPIES OF THE PLAN AND THE APPROVAL LETTER.
3. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
  - THE NAME OF THE APPROVED PROJECT;
  - THE ACTIVITY START DATE; AND
  - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
4. ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED SCS APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF AN SCS APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.
5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
6. IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERED. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING AND THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRENGTH OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE SENSITIVE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.
7. SEWER LINES LOCATED WITHIN OR CROSSING THE 5-YEAR FLOODPLAIN OF A DRAINAGE WAY WILL BE PROTECTED FROM INUNDATION AND STREAM VELOCITIES WHICH COULD CAUSE EROSION AND SCOURING OF BACKFILL. THE TRENCH MUST BE CAPPED WITH CONCRETE TO PREVENT SCOURING OF BACKFILL, OR THE SEWER LINES MUST BE ENCASED IN CONCRETE. ALL CONCRETE SHALL HAVE A MINIMUM THICKNESS OF 8 INCHES.
8. BLASTING PROCEDURES FOR PROTECTION OF EXISTING SEWER LINES AND OTHER UTILITIES WILL BE IN ACCORDANCE WITH THE NATIONAL FIRE PROTECTION ASSOCIATION CRITERIA. SAND IS NOT ALLOWED AS BEDDING OR BACKFILL IN TRENCHES THAT HAVE BEEN BLASTED. IF ANY EXISTING SEWER LINES ARE DAMAGED, THE LINES MUST BE REPAIRED AND RETESTED.
9. ALL MANHOLES CONSTRUCTED OR REHABILITATED ON THIS PROJECT MUST HAVE WATERIGHT SIZE ON SIZE RESILIENT CONNECTORS ALLOWING FOR DIFFERENTIAL SETTLEMENT. IF MANHOLES ARE CONSTRUCTED WITHIN THE 100-YEAR FLOODPLAIN, THE COVER MUST HAVE A GASKET AND BE BOLTED TO THE RING. WHERE GASKETED MANHOLE COVERS ARE REQUIRED FOR MORE THAN THREE MANHOLES IN SEQUENCE OR FOR MORE THAN 1500 FEET, ALTERNATE MEANS OF VENTING WILL BE PROVIDED. BRICKS ARE NOT AN ACCEPTABLE CONSTRUCTION MATERIAL FOR ANY PORTION OF THE MANHOLE.

THE DIAMETER OF THE MANHOLE MUST BE A MINIMUM OF FOUR FEET AND THE MANHOLE FOR ENTRY MUST HAVE A MINIMUM CLEAR OPENING DIAMETER OF 30 INCHES. THESE DIMENSIONS AND OTHER DETAILS SHOWING COMPLIANCE WITH THE COMMISSION'S RULES CONCERNING MANHOLES AND SEWER LINE/MANHOLE INVERTS DESCRIBED IN 30 TAC §217.55 ARE INCLUDED ON PLAN SHEET 109 OF 112

IT IS SUGGESTED THAT ENTRANCE INTO MANHOLES IN EXCESS OF FOUR FEET DEEP BE ACCOMPLISHED BY MEANS OF A PORTABLE LADDER. THE INCLUSION OF STEPS IN A MANHOLE IS PROHIBITED.

10. WHERE WATER LINES AND NEW SEWER LINE ARE INSTALLED WITH A SEPARATION DISTANCE CLOSER THAN NINE FEET (I.E., WATER LINES CROSSING WASTEWATER LINES, WATER LINES PARALLELING WASTEWATER LINES, OR WATER LINES NEXT TO MANHOLES) THE INSTALLATION MUST MEET THE REQUIREMENTS OF 30 TAC §217.53(D) (PIPE DESIGN) AND 30 TAC §290.44(E) (WATER DISTRIBUTION).
11. WHERE SEWERS LINES DEVIATE FROM STRAIGHT ALIGNMENT AND UNIFORM GRADE ALL CURVATURE OF SEWER PIPE MUST BE ACHIEVED BY THE FOLLOWING PROCEDURE WHICH IS RECOMMENDED BY THE PIPE MANUFACTURER: None

IF PIPE FLEXURE IS PROPOSED, THE FOLLOWING METHOD OF PREVENTING DEFLECTION OF THE JOINT MUST BE USED: NO FLEXURE  
PROPOSED

SPECIFIC CARE MUST BE TAKEN TO ENSURE THAT THE JOINT IS PLACED IN THE CENTER OF THE TRENCH AND PROPERLY BEDDED IN ACCORDANCE WITH 30 TAC §217.54.

12. NEW SEWAGE COLLECTION SYSTEM LINES MUST BE CONSTRUCTED WITH STUB OUTS FOR THE CONNECTION OF ANTICIPATED EXTENSIONS. THE LOCATION OF SUCH STUB OUTS MUST BE MARKED ON THE GROUND SUCH THAT THEIR LOCATION CAN BE EASILY DETERMINED AT THE TIME OF CONNECTION OF THE EXTENSIONS. SUCH STUB OUTS MUST BE MANUFACTURED WYES OR TEES THAT ARE COMPATIBLE IN SIZE AND MATERIAL WITH BOTH THE SEWER LINE AND THE EXTENSION. AT THE TIME OF ORIGINAL CONSTRUCTION, NEW STUB-OUTS MUST BE CONSTRUCTED SUFFICIENTLY TO EXTEND BEYOND THE END OF THE STREET PAVEMENT. ALL STUB-OUTS MUST BE SEALED WITH A MANUFACTURED CAP TO PREVENT LEAKAGE. EXTENSIONS THAT WERE NOT ANTICIPATED AT THE TIME OF ORIGINAL CONSTRUCTION OR THAT ARE TO BE CONNECTED TO AN EXISTING SEWER LINE NOT FURNISHED WITH STUB OUTS MUST BE CONNECTED USING A MANUFACTURED SADDLE AND IN ACCORDANCE WITH ACCEPTED PLUMBING TECHNIQUES.

IF NO STUB-OUT IS PRESENT AN ALTERNATE METHOD OF JOINING LATERALS IS SHOWN IN THE DETAIL ON PLAN SHEET N/A OF N/A (FOR POTENTIAL FUTURE LATERALS).

THE PRIVATE SERVICE LATERAL STUB-OUTS MUST BE INSTALLED AS SHOWN ON THE PLAN AND PROFILE SHEETS ON PLAN SHEET N/A OF N/A AND MARKED AFTER BACKFILLING AS SHOWN IN THE DETAIL ON PLAN SHEET N/A OF N/A.

13. TRENCHING, BEDDING AND BACKFILL MUST CONFORM WITH 30 TAC §217.54. THE BEDDING AND BACKFILL FOR FLEXIBLE PIPE MUST COMPLY WITH THE STANDARDS OF ASTM D-2321, CLASSES A, B, II, OR III. RIGID PIPE BEDDING MUST COMPLY WITH THE REQUIREMENTS OF ASTM C 12 (ANSI A 106.2) CLASSES A, B OR C.
14. SEWER LINES MUST BE TESTED FROM MANHOLE TO MANHOLE. WHEN A NEW SEWER LINE IS CONNECTED TO AN EXISTING STUB OR CLEAN-OUT, IT MUST BE TESTED FROM EXISTING MANHOLE TO NEW MANHOLE. IF A STUB OR CLEAN-OUT IS USED AT THE END OF THE PROPOSED SEWER LINE, NO PRIVATE SERVICE ATTACHMENTS MAY BE CONNECTED BETWEEN THE LAST MANHOLE AND THE CLEANOUT UNLESS IT CAN BE CERTIFIED AS CONFORMING WITH THE PROVISIONS OF 30 TAC §213.5(C)(3)(E).
15. ALL SEWER LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC §217.57. THE ENGINEER MUST RETAIN COPIES OF ALL TEST RESULTS WHICH MUST BE MADE AVAILABLE TO THE EXECUTIVE DIRECTOR UPON REQUEST. THE ENGINEER MUST CERTIFY IN WRITING THAT ALL WASTEWATER LINES HAVE PASSED ALL REQUIRED TESTING TO THE APPROPRIATE REGIONAL OFFICE WITHIN 30 DAYS OF TEST COMPLETION AND PRIOR TO USE OF THE NEW COLLECTION SYSTEM. TESTING METHOD WILL BE:
  - (A) FOR A COLLECTION SYSTEM PIPE THAT WILL TRANSPORT WASTEWATER BY GRAVITY FLOW, THE DESIGN MUST SPECIFY AN INFILTRATION AND EXFILTRATION TEST OR A LOW-PRESSURE AIR TEST. A TEST MUST CONFORM TO THE FOLLOWING REQUIREMENTS:
    - (1) LOW PRESSURE AIR TEST.
    - (A) A LOW PRESSURE AIR TEST MUST FOLLOW THE PROCEDURES DESCRIBED IN AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) C-898, ASTM C-924, OR ASTM F-1417 OR OTHER PROCEDURE APPROVED BY THE EXECUTIVE DIRECTOR, EXCEPT AS TO TESTING TIMES AS REQUIRED IN TABLE C.3 IN SUBPARAGRAPH (C) OF THIS PARAGRAPH OR EQUATION C.3 IN SUBPARAGRAPH (B)(ii) OF THIS PARAGRAPH.
    - (B) FOR SECTIONS OF COLLECTION SYSTEM PIPE LESS THAN 36 INCH AVERAGE INSIDE DIAMETER, THE FOLLOWING PROCEDURE MUST APPLY, UNLESS A PIPE IS TO BE TESTED AS REQUIRED BY PARAGRAPH (2) OF THIS SUBSECTION.
    - (i) A PIPE MUST BE PRESSURIZED TO 3.5 POUNDS PER SQUARE INCH (PSI) GREATER THAN THE PRESSURE EXERTED BY GROUNDWATER ABOVE THE PIPE.
    - (ii) ONCE THE PRESSURE IS STABILIZED, THE MINIMUM TIME ALLOWABLE FOR THE PRESSURE TO DROP FROM 3.5 PSI GAUGE TO 2.5 PSI GAUGE IS COMPUTED FROM THE FOLLOWING EQUATION:

- EQUATION C.3
- $$T = (0.085 \cdot D \cdot K) / Q$$
- WHERE:
- T = TIME FOR PRESSURE TO DROP 1.0 POUND PER SQUARE INCH GAUGE IN SECONDS  
Q = 0.000419 X D X L, BUT NOT LESS THAN 1.0  
D = AVERAGE INSIDE PIPE DIAMETER IN INCHES  
L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET  
L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET  
Q = RATE OF LOSS, 0.0015 CUBIC FEET PER MINUTE PER SQUARE FOOT INTERNAL SURFACE

WHERE:

T = TIME FOR PRESSURE TO DROP 1.0 POUND PER SQUARE INCH GAUGE, IN SECONDS  
K = 0.000419 X D X L, BUT NOT LESS THAN 1.0  
D = AVERAGE INSIDE PIPE DIAMETER IN INCHES  
L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET  
L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET  
Q = RATE OF LOSS, 0.0015 CUBIC FEET PER MINUTE PER SQUARE FOOT INTERNAL SURFACE

- (C) SINCE A K VALUE OF LESS THAN 1.0 MAY NOT BE USED, THE MINIMUM TESTING TIME FOR EACH PIPE DIAMETER IS SHOWN IN THE FOLLOWING TABLE C.3:

PIPE DIAMETER (IN)	MINIMUM TIME (SEC)	MAXIMUM LENGTH FOR MINIMUM TIME (FT)	TIME FOR 1" LONGER LENGTH (SEC)
6	340	99	2,000
8	420	120	2,000
10	500	140	2,000
12	580	160	2,000
14	660	180	2,000
16	740	200	2,000
18	820	220	2,000
20	900	240	2,000
22	980	260	2,000
24	1,060	280	2,000
26	1,140	300	2,000
28	1,220	320	2,000
30	1,300	340	2,000
32	1,380	360	2,000
34	1,460	380	2,000
36	1,540	400	2,000
38	1,620	420	2,000
40	1,700	440	2,000
42	1,780	460	2,000
44	1,860	480	2,000
46	1,940	500	2,000
48	2,020	520	2,000
50	2,100	540	2,000
52	2,180	560	2,000
54	2,260	580	2,000
56	2,340	600	2,000
58	2,420	620	2,000
60	2,500	640	2,000
62	2,580	660	2,000
64	2,660	680	2,000
66	2,740	700	2,000
68	2,820	720	2,000
70	2,900	740	2,000
72	2,980	760	2,000
74	3,060	780	2,000
76	3,140	800	2,000
78	3,220	820	2,000
80	3,300	840	2,000
82	3,380	860	2,000
84	3,460	880	2,000
86	3,540	900	2,000
88	3,620	920	2,000
90	3,700	940	2,000
92	3,780	960	2,000
94	3,860	980	2,000
96	3,940	1,000	2,000
98	4,020	1,020	2,000
100	4,100	1,040	2,000

- (E) AN OWNER MAY STOP A TEST IF NO PRESSURE LOSS HAS OCCURRED DURING THE FIRST 25% OF THE CALCULATED TESTING TIME.
- (E) IF ANY PRESSURE LOSS OR LEAKAGE HAS OCCURRED DURING THE FIRST 25% OF TESTING PERIOD, THEN THE TEST MUST CONTINUE FOR THE ENTIRE TEST DURATION AS OUTLINED ABOVE OR UNTIL FAILURE.
- (F) WASTEWATER COLLECTION SYSTEM PIPES WITH A 27 INCH OR LARGER AVERAGE INSIDE DIAMETER MAY BE AIR TESTED AT EACH JOINT INSTEAD OF FOLLOWING THE PROCEDURE OUTLINED IN THIS SECTION.
- (G) A TESTING PROCEDURE FOR PIPE WITH AN INSIDE DIAMETER GREATER THAN 33 INCHES MUST BE APPROVED BY THE EXECUTIVE DIRECTOR.
- (2) INFILTRATION/EXFILTRATION TEST.
- (A) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE.
- (B) AN OWNER SHALL USE AN INFILTRATION TEST IN LIEU OF AN EXFILTRATION TEST WHEN PIPES ARE INSTALLED BEFORE THE GROUNDWATER LEVEL.
- (C) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF TWO FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE, OR AT LEAST TWO FEET ABOVE EXISTING GROUNDWATER LEVEL, WHICHEVER IS GREATER.
- (D) FOR CONSTRUCTION WITHIN A 25-YEAR FLOOD PLAIN, THE INFILTRATION OR EXFILTRATION MUST NOT EXCEED 10 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT THE SAME MINIMUM TEST HEAD AS IN SUBPARAGRAPH (C) OF THIS PARAGRAPH.
- (E) IF THE QUANTITY OF INFILTRATION OR EXFILTRATION EXCEEDS THE MAXIMUM QUANTITY SPECIFIED, AN OWNER SHALL UNDERTAKE REMEDIAL ACTION IN ORDER TO REDUCE THE INFILTRATION OR EXFILTRATION TO AN AMOUNT WITHIN THE LIMITS SPECIFIED. AN OWNER SHALL RETEST A PIPE FOLLOWING A REMEDIATION ACTION.
- (B) IF A GRAVITY COLLECTION PIPE IS COMPOSED OF FLEXIBLE PIPE, DEFLECTION TESTING IS ALSO REQUIRED. THE FOLLOWING PROCEDURES MUST BE FOLLOWED:
- (1) FOR A COLLECTION PIPE WITH INSIDE DIAMETER LESS THAN 27 INCHES, DEFLECTION MEASUREMENT REQUIRES A RIGID MANDREL.
- (A) MANDREL SIZING.
- (I) A RIGID MANDREL MUST HAVE AN OUTSIDE DIAMETER (OD) NOT LESS THAN 85% OF THE BASE INSIDE DIAMETER (ID) OR AVERAGE ID OF A PIPE, AS SPECIFIED IN THE APPROPRIATE STANDARD BY THE ASTM'S, AMERICAN WATER WORKS ASSOCIATION, UNI-BELL, OR AMERICAN NATIONAL STANDARDS INSTITUTE, OR ANY RELATED APPENDIX.
- (II) IF A MANDREL SIZING DIAMETER IS NOT SPECIFIED IN THE APPROPRIATE STANDARD, THE MANDREL MUST HAVE AN OD EQUAL TO THE ID OF A PIPE, IN THIS CASE, THE ID OF THE PIPE, FOR THE PURPOSE OF DETERMINING THE OD OF THE MANDREL, MUST EQUAL BE THE AVERAGE OUTSIDE DIAMETER MINUS TWO MINIMUM WALL THICKNESSES FOR OD CONTROLLED PIPE AND THE AVERAGE INSIDE DIAMETER FOR ID CONTROLLED PIPE.
- (III) ALL DIMENSIONS MUST MEET THE APPROPRIATE STANDARD.
- (B) MANDREL DESIGN.
- (I) A RIGID MANDREL MUST BE CONSTRUCTED OF A METAL OR A RIGID PLASTIC MATERIAL THAT CAN WITHSTAND 200 PSI WITHOUT BEING DEFORMED.
- (II) A MANDREL MUST HAVE NINE OR MORE ODD NUMBER OF RUNNERS OR LEGS.
- (III) A BARREL SECTION LENGTH MUST EQUAL AT LEAST 75% OF THE INSIDE DIAMETER OF A PIPE.
- (IV) EACH SIZE MANDREL MUST USE A SEPARATE PROVING RING.
- (C) METHOD OPTIONS.
- (I) AN ADJUSTABLE OR FLEXIBLE MANDREL IS PROHIBITED.
- (II) A TEST MAY NOT USE TELEVISION INSPECTION AS A SUBSTITUTE FOR A DEFLECTION TEST.
- (III) IF REQUESTED, THE EXECUTIVE DIRECTOR MAY APPROVE THE USE OF A DEFLECTOMETER OR A MANDREL WITH REMOVABLE LEGS OR RUNNERS ON A CASE-BY-CASE BASIS.
- (2) FOR A GRAVITY COLLECTION SYSTEM PIPE WITH AN INSIDE DIAMETER 27 INCHES AND GREATER, OTHER TEST METHODS MAY BE USED TO DETERMINE VERTICAL DEFLECTION.
- (3) A DEFLECTION TEST METHOD MUST BE ACCURATE TO WITHIN PLUS OR MINUS 0.2% DEFLECTION.
- (4) AN OWNER SHALL NOT CONDUCT A DEFLECTION TEST UNTIL AT LEAST 30 DAYS AFTER THE FINAL BACKFILL.
- (5) GRAVITY COLLECTION SYSTEM PIPE DEFLECTION MUST NOT EXCEED FIVE PERCENT (5%).
- (6) IF A PIPE SECTION FAILS A DEFLECTION TEST, AN OWNER SHALL CORRECT THE PROBLEM AND CONDUCT A SECOND TEST AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS.
16. ALL MANHOLES MUST BE TESTED TO MEET OR EXCEED THE REQUIREMENTS OF 30 TAC §217.58.
- (A) ALL MANHOLES MUST PASS A LEAKAGE TEST.
- (A) AN OWNER SHALL TEST EACH MANHOLE (AFTER ASSEMBLY AND BACKFILLING) FOR LEAKAGE, SEPARATE AND INDEPENDENT OF THE COLLECTION SYSTEM PIPES, BY HYDROSTATIC EXFILTRATION TESTING, VACUUM TESTING, OR OTHER METHOD APPROVED BY THE EXECUTIVE DIRECTOR.
- (1) HYDROSTATIC TESTING.
- (A) THE MAXIMUM LEAKAGE FOR HYDROSTATIC TESTING OR ANY ALTERNATIVE TEST METHODS IS 0.025 GALLONS PER FOOT DIAMETER PER FOOT OF MANHOLE DEPTH PER HOUR.
- (B) TO PERFORM A HYDROSTATIC EXFILTRATION TEST, AN OWNER SHALL SEAL ALL WASTEWATER PIPES COMING INTO A MANHOLE WITH AN INTERNAL PIPE PLUG, FILL THE MANHOLE WITH WATER, AND MAINTAIN THE TEST FOR AT LEAST ONE HOUR.
- (C) A TEST FOR CONCRETE MANHOLES MAY USE A 24-HOUR WETTING PERIOD BEFORE TESTING TO ALLOW SATURATION OF THE CONCRETE.
- (2) VACUUM TESTING.
- (A) TO PERFORM A VACUUM TEST, AN OWNER SHALL PLUG ALL LIFT HOLES AND EXTERIOR JOINTS WITH A NON-SHRINK GROUT AND PLUG ALL PIPES ENTERING A MANHOLE.
- (B) NO GROUT MUST BE PLACED IN HORIZONTAL JOINTS BEFORE TESTING.
- (C) STUB-OUTS, MANHOLE BOOTS, AND PIPE PUGS MUST BE SECURED TO PREVENT MOVEMENT WHILE A VACUUM IS DRAWN.
- (D) AN OWNER SHALL USE A MINIMUM 60 INCHLB TORQUE WRENCH TO TIGHTEN THE EXTERNAL CLAMPS THAT SECURE A TEST COVER TO THE COVER OF A MANHOLE.
- (E) A TEST HEAD MUST BE PLACED AT THE INSIDE OF THE TOP OF A CONE SECTION, AND THE SEAL INFLATED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- (F) THERE MUST BE A VACUUM OF 10 INCHES OF MERCURY INSIDE A MANHOLE TO PERFORM A VALID TEST.

- (A) WASTEWATER COLLECTION SYSTEM PIPES WITH A 27 INCH OR LARGER AVERAGE INSIDE DIAMETER MAY BE AIR TESTED AT EACH JOINT INSTEAD OF FOLLOWING THE PROCEDURE OUTLINED IN THIS SECTION.
- (G) A TESTING PROCEDURE FOR PIPE WITH AN INSIDE DIAMETER GREATER THAN 33 INCHES MUST BE APPROVED BY THE EXECUTIVE DIRECTOR.
- (2) INFILTRATION/EXFILTRATION TEST
  - (A) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE.
  - (B) AN OWNER SHALL USE AN INFILTRATION TEST IN LIEU OF AN EXFILTRATION TEST WHEN PIPES ARE INSTALLED BELOW THE GROUNDWATER LEVEL.
  - (C) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE, OR AT LEAST 2.0 FEET ABOVE EXISTING GROUNDWATER LEVEL, WHICHEVER IS GREATER.
  - (D) FOR CONSTRUCTION WITHIN A 25-YEAR FLOOD PLAIN, THE INFILTRATION OR EXFILTRATION MUST NOT EXCEED 10 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT THE SAME MINIMUM TEST HEAD AS IN SUBPARAGRAPH (C) OF THIS PARAGRAPH.
- (3) IF THE QUANTITY OF INFILTRATION OR EXFILTRATION EXCEEDS THE MAXIMUM QUANTITY SPECIFIED, AN OWNER SHALL UNDERTAKE AN ACTION IN ORDER TO REDUCE THE INFILTRATION OR EXFILTRATION TO AN AMOUNT WITHIN THE LIMITS SPECIFIED. AN OWNER SHALL RETEST A PIPE FOLLOWING A REMEDIATION ACTION.
- (B) IF A GRAVITY COLLECTION PIPE IS COMPOSED OF FLEXIBLE PIPE, DEFLECTION TESTING IS ALSO REQUIRED. THE FOLLOWING PROCEDURES MUST BE FOLLOWED:
  - (1) FOR A COLLECTION PIPE WITH INSIDE DIAMETER LESS THAN 27 INCHES, DEFLECTION MEASUREMENT REQUIRES A RIGID MANDEL.
    - (A) MANDEL SIZING
      - (i) A RIGID MANDEL MUST HAVE AN OUTSIDE DIAMETER (OD) NOT LESS THAN 95% OF THE BASE INSIDE DIAMETER (ID) OR AVERAGE ID OF A PIPE, AS SPECIFIED IN THE APPROPRIATE STANDARD BY THE ASTM'S, AMERICAN WATER WORKS ASSOCIATION, UNI-BELL, OR AMERICAN NATIONAL STANDARDS INSTITUTE, OR ANY RELATED AGENCY.
      - (ii) IF A MANDEL SIZING DIAMETER IS NOT SPECIFIED IN THE APPROPRIATE STANDARD, THE MANDEL MUST HAVE AN OD EQUAL TO 85% OF THE ID OF A PIPE. THE ID OF THE PIPE, FOR THE PURPOSE OF DETERMINING THE OD OF THE MANDEL, MUST EQUAL THE AVERAGE OUTSIDE DIAMETER MINUS TWO MINIMUM WALL THICKNESSES FOR OD CONTROLLED PIPE AND THE AVERAGE INSIDE DIAMETER FOR ID CONTROLLED PIPE.
    - (iii) ALL DIMENSIONS MUST MEET THE APPROPRIATE STANDARD.
  - (B) MANDEL DESIGN
    - (i) A RIGID MANDEL MUST BE CONSTRUCTED OF A METAL OR A RIGID PLASTIC MATERIAL THAT CAN WITHSTAND 200 PSI WITHOUT BEING DEFORMED.
    - (ii) A MANDEL MUST HAVE NINE OR MORE ODD NUMBER OF RUNNERS OR LEGS.
    - (iii) A BARREL SECTION LENGTH MUST EQUAL AT LEAST 75% OF THE INSIDE DIAMETER OF A PIPE.
  - (iv) EACH SIZE MANDEL MUST USE A SEPARATE PROVING RING.
  - (C) METHOD OPTIONS
    - (i) AN ADJUSTABLE OR FLEXIBLE MANDEL IS PROHIBITED.
    - (ii) A TEST MAY NOT USE TELEVISION INSPECTION AS A SUBSTITUTE FOR A DEFLECTION TEST.
- (iii) IF REQUESTED, THE EXECUTIVE DIRECTOR MAY APPROVE THE USE OF A DEFLECTOMETER OR A MANDEL WITH REMOVABLE LEGS OR RUNNERS ON A CASE-BY-CASE BASIS.
- (2) FOR A GRAVITY COLLECTION SYSTEM PIPE WITH AN INSIDE DIAMETER 27 INCHES AND GREATER, OTHER TEST METHODS MAY BE USED TO DETERMINE VERTICAL DEFLECTION.
  - (3) A DEFLECTION TEST METHOD MUST BE ACCURATE TO WITHIN PLUS OR MINUS 0.2% DEFLECTION.
  - (4) AN OWNER SHALL NOT CONDUCT A DEFLECTION TEST UNTIL AT LEAST 30 DAYS AFTER THE FINAL BACKFILL.
  - (5) GRAVITY COLLECTION SYSTEM PIPE DEFLECTION MUST NOT EXCEED FIVE PERCENT (5%).
- (6) IF A PIPE SECTION FAILS A DEFLECTION TEST, THE OWNER SHALL CORRECT THE PROBLEM AND CONDUCT A SECOND TEST AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS.

- (A) ALL MANHOLES MUST BE TESTED TO MEET OR EXCEED THE REQUIREMENTS OF 30 TAC §217.58.
- (A) ALL MANHOLES MUST PASS A LEAKAGE TEST.
- (A) AN OWNER SHALL TEST EACH MANHOLE (AFTER ASSEMBLY AND BACKFILLING) FOR LEAKAGE, SEPARATE AND INDEPENDENT OF THE COLLECTION SYSTEM PIPES, BY HYDROSTATIC EXFILTRATION TESTING, VACUUM TESTING, OR OTHER METHOD APPROVED BY THE EXECUTIVE DIRECTOR.
- (1) HYDROSTATIC TESTING.
- (A) THE MAXIMUM LEAKAGE FOR HYDROSTATIC TESTING OR ANY ALTERNATIVE TEST METHODS IS 0.025 GALLONS PER FOOT DIAMETER PER FOOT OF MANHOLE DEPTH PER HOUR.
- (B) TO PERFORM A HYDROSTATIC EXFILTRATION TEST, AN OWNER SHALL SEAL ALL WASTEWATER PIPES COMING INTO A MANHOLE WITH AN INTERNAL PIPE PLUG, FILL THE MANHOLE WITH WATER, AND MAINTAIN THE TEST FOR AT LEAST ONE HOUR.
- (C) A TEST FOR CONCRETE MANHOLES MAY USE A 24-HOUR WETTING PERIOD BEFORE TESTING TO ALLOW SATURATION OF THE CONCRETE.
- (2) VACUUM TESTING.
- (A) TO PERFORM A VACUUM TEST, AN OWNER SHALL PLUG ALL LIFT HOLES AND EXTERIOR JOINTS WITH A NON-SHRINK GROUT AND PLUG ALL PIPES ENTERING A MANHOLE.
- (B) NO GROUT MUST BE PLACED IN HORIZONTAL JOINTS BEFORE TESTING.
- (C) STUB-OUTS, MANHOLE BOOTS, AND PIPE JOINTS MUST BE SECURED TO PREVENT MOVEMENT WHILE A VACUUM IS DRAWN.
- (D) AN OWNER SHALL USE A MINIMUM 60 INCH-LB TORQUE WRENCH TO TIGHTEN THE EXTERNAL CLAMPS THAT SECURE A TEST COVER TO THE TOP OF A MANHOLE.
- (E) A TEST HEAD MUST BE PLACED AT THE INSIDE OF THE TOP OF A CONE SECTION, AND THE SEAL INFLATED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- (F) THERE MUST BE A VACUUM OF 10 INCHES OF MERCURY INSIDE A MANHOLE TO PERFORM A VALID TEST.

- (G) A TEST DOES NOT BEGIN UNTIL AFTER THE VACUUM PUMP IS OFF.
- (H) A MANHOLE PASSES THE TEST IF AFTER 2.0 MINUTES AND WITH ALL VALVES CLOSED, THE VACUUM IS AT LEAST 9.0 INCHES OF MERCURY.

17. ALL PRIVATE SERVICE LATERAL MUST BE INSPECTED AND CERTIFIED IN ACCORDANCE WITH 30 TAC §213.5(C)(3)(ii). AFTER INSTALLATION OF, AND, PRIOR TO COVERING AND CONNECTING A PRIVATE SERVICE LATERAL TO AN EXISTING OVERSEW SEWAGE COLLECTION SYSTEM, A TEXAS LICENSED PROFESSIONAL ENGINEER, TEXAS REGISTERED SANITARIAN, OR APPROPRIATE CITY INSPECTOR MUST VISUALLY INSPECT THE PRIVATE SERVICE LATERAL, AND THE CONNECTION TO THE SEWAGE COLLECTION SYSTEM, AND CERTIFY THAT IT IS CONSTRUCTED IN CONFORMITY WITH THE APPLICABLE PROVISIONS OF THIS SECTION. THE OWNER OF THE COLLECTION SYSTEM MUST MAINTAIN SUCH CERTIFICATIONS FOR FIVE YEARS AND FORWARD COPIES TO THE APPROPRIATE REGIONAL OFFICE UPON REQUEST. CONNECTIONS MAY ONLY BE MADE TO AN APPROVED SEWAGE COLLECTION SYSTEM.

## BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
 BM-101: 'X' CUT IN CONCRETE ON NORTHWEST SIDE OF ELEVATED SUBJECT: 120.2358 ACRE TRACT FROM C.R.175: OUTSIDE GATE, NEAR KEYPAD.  
 N= 10186642.4550  
 E= 30959533.6490  
 ELEVATION: 915.036' (NAVD '88)  
 BM-103: 5/8 ROD SET IN CONCRETE NEAR GROUND SURFACE ON SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
 N= 10187908.0080  
 E= 3097998.0100  
 ELEVATION: 1002.490' (NAVD '88)



KHA PROJECT 067783129	DATE DECEMBER 2023	SCALE: AS SHOWN	DESIGNED BY: DPD	DRAWN BY: DPD	CHECKED BY: AEG
--------------------------	-----------------------	-----------------	------------------	---------------	-----------------

10/10/2010

1

TCEQ GENERAL  
NOTES

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS



SHEET NUMBER

OF 3


112



Plotted By: Duffy, Daniel Date: December 20, 2023 07:25:07am File Path: K:\AUS-Civil\067783129 - Canon 140 - MI Homes\PHASE 2-2\Cod Plan Sheets\C-Erosion Control Plan.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



#### EROSION CONTROL LEGEND




#### NOTES:

1. ALL EROSION SEDIMENTATION CONTROLS CALLED OUT AS "PHASE 2" ARE TO BE INSTALLED AFTER THE APPLICABLE IMPROVEMENT IS INSTALLED AND NOT WITH THE INITIAL EROSION SEDIMENTATION CONTROLS
2. GRADED AREAS MUST BE STABILIZED PRIOR TO ACCEPTANCE OR EROSION CONTROLS MUST BE IN PLACE TO PREVENT SEDIMENT FROM ENTERING THE ROADWAYS
3. NO LOTS SHOULD BE CLEARED OUTSIDE LIMITS OF CONSTRUCTION
4. THE CITY OF LEANDER ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD OR MODIFY EROSION/SEDIMENT CONTROLS ON SITE THROUGHOUT THE DURATION OF THE PROJECT
5. STOCKPILE TO BE REMOVED PRIOR TO ACCEPTANCE.
6. PONDS SHALL BE CLEARED FROM POLLUTION FROM CONSTRUCTION SEDIMENT FLOW BEFORE FINAL WALKTHROUGH.
7. CONTRACTOR SHALL NOTIFY ENGINEER IF A CREEK BED CONTAINS A BASE FLOW THAT AFFECTS THE CONSTRUCTION SEQUENCE OR SCHEDULE. THE CONTRACTOR SHALL NOT OBSTRUCT THE NATURAL FLOW OF WATER IN THE CREEK BED AND SHALL BE RESPONSIBLE FOR CONTAINING ALL SEDIMENT WITHIN THE LIMITS OF CLEARING. IF CREEK BASE FLOW IS PRESENT, THE CONTRACTOR SHALL REQUEST A DIVERSION PLAN FROM THE ENGINEER. THE ENGINEER SHALL PROVIDE A DIVERSION PLAN TO THE CONTRACTOR BEFORE CONSTRUCTION WITHIN CREEK LIMITS COMMENCES.

#### BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30959533.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)

#### TREE LEGEND



**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023  
ALEXANDRO E. GRAMADO RICO  
130084  
PROFESSIONAL ENGINEER  
Alfonso E. Rios-Lin  
KHA PROJECT 067783129  
DATE 2023  
SCALE AS SHOWN  
DESIGNED BY: DFD  
DRAWN BY: AID  
CHECKED BY: AEC

#### EROSION CONTROL PLAN


**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 10 112












- NOTES:
1. FINISHED LOT ELEVATIONS AT THE STREET R.O.W. SHALL BE GRADED UP FROM THE TOP OF CURB IN CONFORMANCE WITH THE STREET CROSS-SECTIONS SHOWN ON PAVING DETAIL SHEET.
  2. ALL BLOCK GRADING SHALL BE A MINIMUM OF 1.50% GRADE.
  3. ALL SLOPES TO BE 3:1 OR FLATTER.
  4. CONTRACTOR TO PROVIDE STRUCTURAL DESIGN FOR ANY RETAINING WALLS SHOWN.



ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1989 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2388 ACRE TRACT FROM C.R. 175 OUTSIDE GATE, NEAR KEYPAD.  
N = 10186642.4550  
E = 30959353.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND TO THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N = 10187908.0080  
E = 30979908.0100  
ELEVATION: 1002.490' (NAVD '88)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS












Plotted By: Duffy, Daniel Date: December 20, 2023 07:30:14am File Path: K:\AUS\_Civil\067783129 - Canon 140 - MI Homes\PHASE 2-2\CodPlanSheets\C-Proposed Drainage Area Map.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

Edgewood-Proposed  
Drainage Calculations - SCS Method

DRAINAGE AREA	AREA (sf)	AREA (Ac.)	IMPERVIOUS COVER (Ac.)	IMPERVIOUS COVER (%)	PERVIOUS CURVE NO.	WEIGHTED CURVE NO.	SHEET FLOW				SHALLOW CONCENTRATED FLOW				CHANNEL FLOW								TOTAL TC** (min)	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)			
							N	P-2yr/24hr			3.92	IN	L (ft)	V (fps)	S (ft/ft)	T (min)	L (ft)	V (fps)	S (ft/ft)	T (min)	L (ft)	V (fps)						n	S (ft/ft)	T (min)
								L (ft)	S (ft/ft)	T (min)													L (ft)	V (fps)	S (ft/ft)	T (min)	L (ft)			
PR-A1	1,059,515	24.33	0.00	0.00%	80.65	80.65	0.15	100	0.008	12.77	1530	2.98	0.034	8.57	576	5.0	0.035	0.036	1.92	0	8.0	0.013	0.010	0.00	23.26	47.03	90.17	120.28	171.63	
PR-A2	1,342,084	30.81	39.92	39.92%	80.00	87.19	0.15	100	0.030	7.53	352	2.60	0.026	2.26	0	5.0	0.035	0.012	0.00	1352	8.0	0.013	0.010	2.82	12.60	77.43	135.58	175.11	241.92	
PR-A3	129,809	2.98	0.28	9.40%	80.00	81.69	0.15	100	0.070	5.36	376	3.23	0.040	1.94	0	5.1	0.035	0.010	0.00	-	-	-	-	-	7.31	9.21	17.59	23.49	33.57	
PR-A4	760,558	17.46	7.16	41.01%	80.65	87.77	0.15	100	0.047	6.29	0	16.70	1.071	0.00	0	5.1	0.035	0.010	0.00	1542	8.0	0.013	0.010	3.21	9.50	65.16	110.55	141.26	193.24	
PR-A5	1,149,984	26.40	0.54	2.05%	81.71	82.04	0.15	100	0.015	9.93	1217	3.95	0.060	5.13	0	5.1	0.035	0.010	0.00	0	8.0	0.013	0.010	0.00	15.06	62.81	119.76	159.36	226.81	
PR-B1	2,785,226	63.94	1.20	1.88%	80.00	80.34	0.15	90	0.017	8.68	1869	2.50	0.024	12.48	1424	5.5	0.035	0.021	4.32	-	-	-	-	25.46	116.52	224.63	300.2	429.3		
PR-B2	684,763	15.72	8.07	50.76%	80.00	89.14	0.15	100	0.025	8.10	242	2.93	0.033	1.38	50	6.0	0.16	0.027	0.14	1416	8.0	0.013	0.010	2.85	12.56	66.56	92.98	117.54	159.11	
PR-B3	1,273,694	29.24	0.71	2.43%	80.00	80.44	0.15	100	0.010	11.68	321	4.84	0.090	1.11	1126	5.5	0.035	0.021	3.41	-	-	-	-	16.20	66.38	126.97	169.33	242.4		
PR-B4	469,577	10.78	4.88	45.27%	81.07	88.73	0.15	100	0.020	8.85	0	3.02	0.035	0.00	165	6.0	0.035	0.010	0.46	1389	8.0	0.0	0.0	2.89	12.21	36.25	60.57	77.08	105	
PR-B5	162,479	3.73	0.51	13.67%	80.53	82.92	0.15	100	0.038	6.85	100	5.00	0.096	0.33	213	5.1	0.035	0.010	0.70	-	-	-	-	7.88	13.26	23.66	30.78	42.85		
PR-C1	684,763	15.72	7.93	50.45%	80.00	89.08	0.15	100	0.034	7.16	38	2.60	0.026	0.24	74	5.0	0.035	0.019	0.25	1139	8.0	0.013	0.020	2.37	10.02	54.02	88.91	112.44	152.34	
PR-C2	406,415	9.33	3.84	41.16%	80.00	87.41	0.15	100	0.020	8.85	41	2.98	0.034	0.23	39	5.0	0.035	0.024	0.13	863	8.0	0.013	0.020	1.80	11.01	35.25	57.92	73.21	99.1	
PR-BP-C	537,095	12.33	1.89	15.33%	80.53	83.21	0.15	100	0.025	8.10	106	6.45	0.160	0.27	628	7.0	0.035	0.028	2.21	-	-	-	-	10.58	45.68	90.7	104.55	144.93		
OS-BP-C	1,160,003	26.63	0.68	2.55%	80.53	80.98	0.15	100	0.030	7.53	967	3.10	0.037	5.19	1810	8.5	0.035	0.032	3.55	-	-	-	-	16.27	64.59	122.52	162.74	231.19		



0 300' 600'  
GRAPHIC SCALE 300'

LEGEND

	POINT OF ANALYSIS
	AREA DESIGNATOR
	AREA IN ACRES
	INLET NUMBER
	PROPERTY LINE
	PROPOSED STORM SEWER LINE
	EXISTING STORM SEWER LINE
	PROPOSED STORM SEWER INLET
	PROPOSED STORM SEWER MANHOLE
	PROPOSED STORM SEWER HEADWALL
	PROPOSED FLOW DIRECTION
	PROPOSED CONTOUR
	EXISTING CONTOUR
	TIME OF CONCENTRATION PATH
	FEMA 100-YR FLOODPLAIN
	CALCULATED FULLY DEVELOPED 100-YR FLOODPLAIN

PROPOSED DRAINAGE CALCULATIONS - SCS METHOD\*  
(WITH PROPOSED DETENTION)  
\*Note: SCS Method was used for these areas to size required detention ponds

PROPOSED CONDITIONS

Point of Analysis	Total Drainage Area (Acres)	Total Impervious Cover Area (acres)	Impervious Area (%)	Storm Event	Developed Runoff (With Detention) (cfs)
A	101.98	20.28	19.89%	2	172.98
				10	329.63
				25	438.20
				100	632.19
B	123.41	15.28	12.38%	2	180.64
				10	379.63
				25	515.60
				100	745.57
C	64.01	14.34	22.40%	2	113.30
				10	220.16
				25	299.28
				100	429.53
PR OFFSITE (FOR OFFSITE ANALYSIS ONLY)	6.26	0.56	8.95%	2	15.84
				10	30.30
				25	40.49
				100	57.95

PROPOSED VS. EXISTING COMPARISON

Point of Analysis	Storm Event	Existing Runoff (cfs)	Developed Runoff (cfs)	Runoff Difference at Point of Analysis (cfs)	Is Developed $\leq$ Existing?
A	2	179.10	172.98	(6.12)	YES
	10	342.28	329.63	(12.65)	YES
	25	456.23	438.20	(18.03)	YES
	100	650.95	632.19	(18.76)	YES
B	2	208.04	180.64	(27.40)	YES
	10	402.63	379.63	(23.00)	YES
	25	535.94	515.60	(20.34)	YES
	100	770.89	745.57	(25.32)	YES
C	2	124.77	113.30	(11.47)	YES
	10	237.24	220.16	(17.08)	YES
	25	316.90	299.28	(17.62)	YES
	100	452.82	429.53	(23.29)	YES
OFFSITE	2	22.54	15.84	(6.70)	YES
	10	43.58	30.30	(13.28)	YES
	25	58.50	40.49	(18.01)	YES
	100	83.99	57.95	(26.04)	YES

Note: All detention runoff calculations were analyzed using the Soil Conservation Services Method as documented in the Technical Release 55. Pond Pack V8i was used to calculate the runoff and design the pond volume and outlet structure.

BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD 88) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.258 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30959363.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023  
ALEXANDRO E. GRANADOS RICO  
130084  
PROFESSIONAL ENGINEER  
Alfonso E. Rios-Lin  
KHA PROJECT 067783129  
DATE DECEMBER 2023  
SCALE: AS SHOWN  
DESIGNED BY: DPD  
DRAWN BY: DPD  
CHECKED BY: AEC

PROPOSED DRAINAGE  
AREA MAP


EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 22 112



Plotted By: Duffy, Daniel Date: December 20, 2023 07:32:07am File Path: K:\AUS-Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Code\PlanSheets\C-Inlet Drainage Area Map.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND

X-1

9.9 ac

A-1

—

—

---

---

—

—

—

—

—

—

AREA DESIGNATOR

AREA IN ACRES

PROPERTY LINE

PROPOSED STORM SEWER LINE

EXISTING STORM SEWER LINE

PROPOSED DRAINAGE DIVIDE

PROPOSED STORM SEWER INLET

PROPOSED STORM SEWER MANHOLE

PROPOSED STORM SEWER HEADWALL

PROPOSED FLOW DIRECTION

PROPOSED CONTOUR

EXISTING CONTOUR

100-YR ATLAS-14 FLOODPLAIN

BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.

N= 10186642.4550  
E= 30895933.6490  
ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.

N= 10187908.0080  
E= 3087998.0100  
ELEVATION: 1002.490' (NAVD '88)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 23 112

INLET DRAINAGE  
AREA MAP

KHA PROJECT  
067783129

DATE  
DECEMBER 2023

SCALE: AS SHOWN

DESIGNED BY: DPD

DRAWN BY: DPD

CHECKED BY: AEC

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM

12/06/2023

ALEXANDRO E. GRANADOS RICO

130084

PROFESSIONAL ENGINEER

*Alexandro E. Granados Rico*

REVISIONS

BY

DATE



























SD-A







OF	SHEET NUMBER	EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS	STORM PLAN & PROFILE - SD-A STA 10+50 - END	KHA PROJECT 067783129  DATE DECEMBER 2023  SCALE: AS SHOWN DESIGNED BY: DPD DRAWN BY: AUD CHECKED BY: AEG	 12/06/2023 	 © 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928	No. _____ REVISIONS _____ DATE _____ BY _____
----	--------------	---	--	--	--	---	--







Plotted By: Duff, Daniel Date: December 20, 2023 07:34:44am File Path: K:\AUS-Civil\067783129 - Cannon 140 - Wl Homes\PHASE 2-2\Cod Plans\Sheets\SD-C-Storm P&P.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



- STORM NOTES
- ALL DIMENSIONS ARE TO CENTERLINE OF PIPE UNLESS NOTED OTHERWISE.
  - CONTRACTOR TO FIELD VERIFY LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTACT ENGINEER IF FIELD CONDITIONS VARY.
  - CONTRACTOR TO PROVIDE CL IV RCP AT ALL LOCATIONS WITH LESS THAN 2.0' OF COVERAGE.
  - DEFLECTED PIPES SHALL BE PER AMERICAN CONCRETE PIPE ASSOCIATION DESIGN DATA 21 SPEC OR APPROVED EQUAL.

KHA PROJECT 067783129		DATE DECEMBER 2023		SCALE: AS SHOWN		DESIGNED BY: DPD		DRAWN BY: AD		CHECKED BY: AEC	
KIMLEY-HORN		KIMLEY-HORN AND ASSOCIATES, INC.		501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626		PHONE: 512-520-0768		FAX: 512-418-1791		WWW.KIMLEY-HORN.COM	
TEXAS REGISTERED ENGINEERING FIRM F-928		REVISIONS		BY		DATE					

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 28 112


STORM PLAN & PROFILE -  
SD-C

12/06/2023


STATE OF TEXAS  
ALEJANDRO E. GRANADOS RICO  
130084  
PROFESSIONAL ENGINEER

*Alejandro E. Granados Rico*





CURVE TABLE						
CURVE	RADIUS	LENGTH	CHORD BEARING	CHORD	DELTA	TANGENT
C5	295.00'	120.81'	N10°14'30"W	119.97'	23°27'49"	61.26'

















Plotted By: Duffy, Daniel Date: December 20, 2023 07:38:03am File Path: K:\AUS-Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Cad Files\Sheets\C-Storm P&P2.dwg  
This document, together with the concepts and designs presented herein, is an instrument of service, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



CULV-A


CULV-B



KHA PROJECT 067783129		DATE DECEMBER 2023		SCALE AS SHOWN		DESIGNED BY: DPD		DRAWN BY: AD		CHECKED BY: AEC	
<b>STORM PLAN &amp; PROFILE - CULV-A &amp; CULV-B</b>											
<b>EDGEWOOD PHASE 2, SECTION 2</b> CITY OF LEANDER WILLIAMSON COUNTY, TEXAS											
SHEET NUMBER 31 OF 112											
KIMLEY-HORN & ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928											
REVISIONS											
BY DATE											



Plotted By: Duff, Daniel    Date: December 20, 2023    07:40:33am    File Path: K:\AUS-Civil\067783129 - Canon 140 - MI Homes\PHASE 2-2\Cod\PlanSheets\C-Storm\_Lateral.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL

PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL

**BENCHMARKS**

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM '88 (NAVD '88) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: 1/2" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30859353.5490  
ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8" ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3087998.0100  
ELEVATION: 1002.490' (NAVD '88)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 32 112

STORM LATERAL  
PROFILES (SHEET 1 OF 3)

KHA PROJECT  
067783129

DATE  
DECEMBER 2023

SCALE: AS SHOWN

DESIGNED BY: DPD

DRAWN BY: AID

CHECKED BY: AEC





12/06/2023

Alejandro E. Granados Rocio

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928





# BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE SUBJECT 100.2658 ACRE TRACT FROM C.R. 176.5 OUTSIDE GATE, NEAR KEYPAD.

N: 10186642.4550  
E: 3098953.6490

BM-102: 935.03' (NAVD '88)


BM-103: 516.80' SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.

N: 10187908.0080  
E: 3087998.0100

ELEVATION: 1002.490' (NAVD '88)

OF	33	112
SHEET NUMBER		
<p><b>EDGEWOOD</b>  <b>PHASE 2, SECTION 2</b>          CITY OF LEANDER          WILLIAMSON COUNTY, TEXAS</p>		
<p><b>STORM LATERAL</b>  <b>PROFILES (SHEET 2 OF 3)</b></p>		
<p>KHA PROJECT          067783129</p>		
<p>DATE          DECEMBER 2023</p>		
<p>SCALE: AS SHOWN</p>		
<p>DESIGNED BY: DPD</p>		
<p>DRAWN BY: AJD</p>		
<p>CHECKED BY: AEG</p>		
<p><i>Alfonso E. Alfaro Kim</i></p>		
<p>12/06/2023</p>		
<p><b>Kimley»»Horn</b></p>		
<p>© 2023 KIMLEY-HORN AND ASSOCIATES, INC.          501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626          PHONE: 512-520-0768 FAX: 512-418-1791          WWW.KIMLEY-HORN.COM          TEXAS REGISTERED ENGINEERING FIRM F-928</p>		
No.	REVISIONS	DATE
BY		

Plotted By: Duff, Daniel Date: December 20, 2023 07:41:37am File Path: K:\AUS\_Civil\067783129 - Canon 140 - M Homes\PHASE 2-2\Cad\PlanSheets\C-Storm\_Lateral.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023

STATE OF TEXAS

ALEXANDRO E. GRANADOS RICO

130084

PROFESSIONAL ENGINEER

Alfonso E. Rico-Lin

KHA PROJECT  
067783129

DATE  
DECEMBER 2023

SCALE: AS SHOWN

DESIGNED BY: DPD

DRAWN BY: AD



CHECKED BY: AEC

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

STORM LATERAL  
PROFILES (SHEET 3 OF 3)

SHEET NUMBER  
OF 34 112





- ## WASTEWATER GENERAL NOTES
1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
  2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
  3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
  4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
  5. ALL WASTEWATER SERVICES ARE DUAL SERVICE UNLESS OTHERWISE NOTED. SINGLE SERVICES = ★

# BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1985 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 102.2358 ACRE TRACT FROM C.R. 175, OUTSIDE OF GATE, NEAR KEYPAD.

N= 10186642.4550  
E= 3095953.6490  
ELEVATION: 915.038' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GAVEL ROAD AND 1/4 CORNER OF THE 0.20 ACRE TRACT TRACT TO DONALD AND DOLORES GISH.




N= 10187908.0100  
E= 3087998.0100  
ELEVATION: 1002.490' (NAVD '88)









Plotted By: Darby, Daniel Date: December 20, 2023 07:45:15am File Path: K:\AUS\_Civil\067783129 - Canon 140 - M1 Homes\PHASE 2-2\Cad\PlanSheets\C-Wastewater Plan & Profile.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.








This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kinley-Horn and Associates, Inc. shall be without liability to Kinley-Horn and Associates, Inc.



OTHER LEGEND	
	PROPERTY LINE
	PROPOSED WASTE WATER LINE
	PROPOSED WATER LINE
	PROPOSED FORCE MAIN LINE
	PROPOSED WASTE WATER MANHOLE
	WASTE WATER FLOW DIRECTION
	PROPOSED FIRE HYDRANT
	EXISTING OVERHEAD POWER LINE
	EXISTING WATER LINE
	EXISTING WASTE WATER LINE
	EXISTING FORCE MAIN LINE
	EXISTING STORM SEWER LINE
	EXISTING POWER POLE
	EXISTING FIRE HYDRANT
	EXISTING WATER METER
	EXISTING WASTE WATER MANHOLE

- ## WASTEWATER GENERAL NOTES
1. WASTEWATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
  2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
  3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
  4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
  5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.




# BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2538 ACRES TRACT FROM R.R. 175, OFF OF STATE GATE, NEAR KEYPAD.  
N = 10186642.4550  
E = 30959353.6490  
ELEVATION: 915.038' (NAVD '88)




BM-103: 5/8 ROAD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.29 ACRES TRACT TO DONALD AND DOLORES GISH.  
N = 10187998.0100  
E = 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)































## UTILITY LEGEND

	PROPERTY LINE
	PROPOSED WASTE WATER LINE
	PROPOSED WATER LINE
	PROPOSED FORCE MAIN LINE
	PROPOSED WASTE WATER MANHOLE
	WASTE WATER FLOW DIRECTION
	PROPOSED FIRE HYDRANT
	EXISTING OVERHEAD POWER LINE
	EXISTING WATER LINE
	EXISTING WASTE WATER LINE
	EXISTING FORCE MAIN LINE
	EXISTING STORM SEWER LINE
	EXISTING POWER POLE
	EXISTING FIRE HYDRANT
	EXISTING WATER METER
	EXISTING WASTE WATER MANHOLE

## WASTEWATER GENERAL NOTES

1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.



## BENCHMARKS


ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 102.2388 ACRE TRACT FROM C.R. 17, OUTSIDE GATE, NEAR KEYPAD.

N= 10186642.4550  
E= 30959353.6490  
ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD, AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.

N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)

[illegible]

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
[WWW.KIMLEY-HORN.COM](http://WWW.KIMLEY-HORN.COM)

TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT 067783129	DATE DECEMBER 2023	SCALE: AS SHOWN	DESIGNED BY: DPD	DRAWN BY: AJD	CHECKED BY: AFG
--------------------------	-----------------------	-----------------	------------------	---------------	-----------------


WASTEWATER PLAN &  
PROFILE - WWL-B 10+50 -  
END & WWL-C

















**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
50

112







- |   |                              |
|---|------------------------------|
|  | PROPERTY LINE                |
|  | PROPOSED WASTE WATER LINE    |
|  | PROPOSED WATER LINE          |
|  | PROPOSED FORCE MAIN LINE     |
|  | PROPOSED WASTE WATER MANHOLE |
|  | WASTE WATER FLOW DIRECTION   |
|  | PROPOSED FIRE HYDRANT        |
|  | EXISTING OVERHEAD POWER LINE |
|  | EXISTING WATER LINE          |
|  | EXISTING WASTE WATER LINE    |
|  | EXISTING FORCE MAIN LINE     |
|  | EXISTING STORM SEWER LINE    |
|  | EXISTING POWER POLE          |
|  | EXISTING FIRE HYDRANT        |
|  | EXISTING WATER METER         |
|  | EXISTING WASTE WATER MANHOLE |

## WASTEWATER GENERAL NOTES

1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.



## BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRES TRACT FROM C.R. 175 OUTSIDE GATE, NEAR KEYPAD.


N= 101864642.50  
E= 30959533.6490  
ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRES TRACT TO ROAD AND DOLORES GISH.

N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)



KHA PROJECT 067783129	DATE DECEMBER 2023	SCALE: AS SHOWN	DESIGNED BY: DPD	DRAWN BY: AJD	CHECKED BY: AEG
--------------------------	-----------------------	-----------------	------------------	---------------	-----------------



WWL-D




1  
 2  
 3  
 4  
 5  
 6  
 7  
 8  
 9  
 10  
 11  
 12  
 13  
 14  
 15  
 16  
 17  
 18  
 19  
 20  
 21  
 22  
 23  
 24  
 25  
 26  
 27  
 28  
 29  
 30  
 31  
 32  
 33  
 34  
 35  
 36  
 37  
 38  
 39  
 40  
 41  
 42  
 43  
 44  
 45  
 46  
 47  
 48  
 49  
 50  
 51  
 52  
 53  
 54  
 55  
 56  
 57  
 58  
 59  
 60  
 61  
 62  
 63  
 64  
 65  
 66  
 67  
 68  
 69  
 70  
 71  
 72  
 73  
 74  
 75  
 76  
 77  
 78  
 79  
 80  
 81  
 82  
 83  
 84  
 85  
 86  
 87  
 88  
 89  
 90  
 91  
 92  
 93  
 94  
 95  
 96  
 97  
 98  
 99  
 100  
 101  
 102  
 103  
 104  
 105  
 106  
 107  
 108  
 109  
 110  
 111  
 112  
 113  
 114  
 115  
 116  
 117  
 118  
 119  
 120  
 121  
 122  
 123  
 124  
 125  
 126  
 127  
 128  
 129  
 130  
 131  
 132  
 133  
 134  
 135  
 136  
 137  
 138  
 139  
 140  
 141  
 142  
 143  
 144  
 145  
 146  
 147  
 148  
 149  
 150  
 151  
 152  
 153  
 154  
 155  
 156  
 157  
 158  
 159  
 160  
 161  
 162  
 163  
 164  
 165  
 166  
 167  
 168  
 169  
 170  
 171  
 172  
 173  
 174  
 175  
 176  
 177  
 178  
 179  
 180  
 181  
 182  
 183  
 184  
 185  
 186  
 187  
 188  
 189  
 190  
 191  
 192  
 193  
 194  
 195  
 196  
 197  
 198  
 199  
 200  
 201  
 202  
 203  
 204  
 205  
 206  
 207  
 208  
 209  
 210  
 211  
 212  
 213  
 214  
 215  
 216  
 217  
 218  
 219  
 220  
 221  
 222  
 223  
 224  
 225  
 226  
 227  
 228  
 229  
 230  
 231  
 232  
 233  
 234  
 235  
 236  
 237  
 238  
 239  
 240  
 241  
 242  
 243  
 244  
 245  
 246  
 247  
 248  
 249  
 250  
 251  
 252  
 253  
 254  
 255  
 256  
 257  
 258  
 259  
 260  
 261  
 262  
 263  
 264  
 265  
 266  
 267  
 268  
 269  
 270  
 271  
 272  
 273  
 274  
 275  
 276  
 277  
 278  
 279  
 280  
 281  
 282  
 283  
 284  
 285  
 286  
 287  
 288  
 289  
 290  
 291  
 292  
 293  
 294  
 295  
 296  
 297  
 298  
 299  
 300  
 301  
 302  
 303  
 304  
 305  
 306  
 307  
 308  
 309  
 310  
 311  
 312  
 313  
 314  
 315  
 316  
 317  
 318  
 319  
 320  
 321  
 322  
 323  
 324  
 325  
 326  
 327  
 328  
 329  
 330  
 331  
 332  
 333  
 334  
 335  
 336  
 337  
 338  
 339  
 340  
 341  
 342  
 343  
 344  
 345  
 346  
 347  
 348  
 349  
 350  
 351  
 352  
 353  
 354  
 355  
 356  
 357  
 358  
 359  
 360  
 361  
 362  
 363  
 364  
 365  
 366  
 367  
 368  
 369  
 370  
 371  
 372  
 373  
 374  
 375  
 376  
 377  
 378  
 379  
 380  
 381  
 382  
 383  
 384  
 385  
 386  
 387  
 388  
 389  
 390  
 391  
 392  
 393  
 394  
 395  
 396  
 397  
 398  
 399  
 400  
 401  
 402  
 403  
 404  
 405  
 406  
 407  
 408  
 409  
 410  
 411  
 412  
 413  
 414  
 415  
 416  
 417  
 418  
 419  
 420  
 421  
 422  
 423  
 424  
 425  
 426  
 427  
 428  
 429  
 430  
 431  
 432  
 433  
 434  
 435  
 436  
 437  
 438  
 439  
 440  
 441  
 442  
 443  
 444  
 445  
 446  
 447  
 448  
 449  
 450  
 451  
 452  
 453  
 454  
 455  
 456  
 457  
 458  
 459  
 460  
 461  
 462  
 463  
 464  
 465  
 466  
 467  
 468  
 469  
 470  
 471  
 472  
 473  
 474  
 475  
 476  
 477  
 478  
 479  
 480  
 481  
 482  
 483  
 484  
 485  
 486  
 487  
 488  
 489  
 490  
 491  
 492  
 493  
 494  
 495  
 496  
 497  
 498  
 499  
 500  
 501  
 502  
 503  
 504  
 505  
 506  
 507  
 508  
 509  
 510  
 511  
 512  
 513  
 514  
 515  
 516  
 517  
 518  
 519  
 520  
 521  
 522  
 523  
 524  
 525









Plotted By: Duff, Daniel    Date: December 20, 2023    07:51:03am    File Path: K:\AUS\_Civil\067783129 - Canon 140 - M1 Homes\PHASE 2-2\Cad\PlanSheets\C-Wastewater Plan & Profile 2.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




- WASTEWATER GENERAL NOTES**
1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
  2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
  3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
  4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
  5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.




KHA PROJECT 067783129		DATE DECEMBER 2023		SCALE: AS SHOWN		DESIGNED BY: DPD		DRAWN BY: AID		CHECKED BY: AEC	
KIMLEY-HORN		© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM		TEXAS REGISTERED ENGINEERING FIRM F-928		REVISIONS		DATE		BY	
WASTEWATER PLAN & PROFILE - WWL-F STA 10+50 - END											
EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS											
SHEET NUMBER 53 OF 112											





WWL-G





## UTILITY LEGEND

	PROPERTY LINE
	PROPOSED WASTE WATER LINE
	PROPOSED WATER LINE
	PROPOSED FORCE MAIN LINE
	PROPOSED WASTE WATER MANHOLE
	WASTE WATER FLOW DIRECTION
	PROPOSED FIRE HYDRANT
	EXISTING OVERHEAD POWER LINE
	EXISTING WATER LINE
	EXISTING WASTE WATER LINE
	EXISTING FORCE MAIN LINE
	EXISTING STORM SEWER LINE
	EXISTING POWER POLE
	EXISTING FIRE HYDRANT
	EXISTING WATER METER
	EXISTING WASTE WATER MANHOLE

## WASTEWATER GENERAL NOTES

1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.



PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL

## BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120 2350 ACRE TRACT FROM C.R. 175, QUINCY GATE, NEAR KEYPAD.

N: 10186642.4550  
E: 30959353.6490  
ELEVATION: 915.036' (NAVD '88)

BM-103: SIB ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO RONALD AND DOLORES GISH.

N: 10187095.0080  
E: 30979398.0100  
ELEVATION: 1002.490' (NAVD '88)

[illegible]

**Kimley»Horn**  
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
[WWW.KIMLEY-HORN.COM](http://WWW.KIMLEY-HORN.COM)  
TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT 067783129	DATE DECEMBER 2023	SCALE: AS SHOWN	DESIGNED BY: DPD	DRAWN BY: AJD	CHECKED BY: AEG
--------------------------	-----------------------	-----------------	------------------	---------------	-----------------

# WASTEWATER PLAN & PROFILE - WWL-G

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS



SHEET NUMBER  
OF 54 112








Plotted By:Durfy, Daniel Date:December 20, 2023 07:53:58Bom File Path:K:\AUS-Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Cod Plans\Sheets\C-Force Main Plan & Profile.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.





UTILITY LEGEND	
	PROPOSED WASTE WATER LINE
	PROPOSED WATER LINE
	PROPOSED FORCE MAIN LINE
	PROPOSED WASTE WATER MANHOLE
	WASTE WATER FLOW DIRECTION
	PROPOSED FIRE HYDRANT
	EXISTING OVERHEAD POWER LINE
	EXISTING WATER LINE
	EXISTING WASTE WATER LINE
	EXISTING FORCE MAIN LINE
	EXISTING STORM SEWER LINE
	EXISTING POWER POLE
	EXISTING FIRE HYDRANT
	EXISTING WATER METER
	EXISTING WASTE WATER MANHOLE

WASTEWATER GENERAL NOTES

1. WATER AND WASTEWATER SEPARATION (VERTICAL AND HORIZONTAL) SHALL BE MAINTAINED IN ACCORDANCE WITH TCEQ REQUIREMENTS.
2. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. ALL WASTEWATER LINES ARE 8" UNLESS OTHERWISE NOTED.
4. ALL STORM SEWER SHOWN IN PROFILES ARE PARALLEL FROM WASTEWATER UNLESS OTHERWISE NOTED (E.G. CROSSINGS)
5. MANHOLES OUTSIDE OF PAVEMENT TO BE 0.5' ABOVE PROPOSED GRADE.



FM-A



BENCHMARKS


ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: 3/4" OUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRE TRACT FROM C.R. 175. OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30959363.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8" ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)

KHA PROJECT 067783129		DATE DECEMBER 2023		SCALE: AS SHOWN		DESIGNED BY: DPD		DRAWN BY: AID		CHECKED BY: AEC	
KIMLEY-HORN		© 2023 KIMLEY-HORN AND ASSOCIATES, INC.		501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626		PHONE: 512-520-0768		FAX: 512-418-1791		WWW.KIMLEY-HORN.COM	
KIMLEY-HORN		TEXAS REGISTERED ENGINEERING FIRM F-928		REVISIONS		No.		DATE		BY	
EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS											
FORCE MAIN PLAN & PROFILE - FM-A STA 1+00 - 10+50											
SHEET NUMBER 56 OF 112											









- ## WASTEWATER GENERAL NOTES

- 
- BELL GASKET JOINTS CONFORMING TO ASTM D3212
- WATER LINE
- BELL GASKET JOINTS CONFORMING TO ASTM D3212
- WASTE WATER LINE
- WW LINE TO BE ENCASED IN CEMENT STABILIZED BACKFILL PER TCEQ REQUIREMENTS. CEMENT BACKFILL TO EXTEND 1' PAST ON EACH SIDE OF CENTERED WW PIPE (22' MIN TOTAL LENGTH OF CEMENT STABILIZED BACKFILL)
- 1-WW JOINT (20' MIN) PRESSURE RATED SDR -26 CONFORMING TO ASTM 3034 CENTERED AT WATER CROSSING
- 1'

PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL



ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.


101-101: "X" IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 100.2258 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.

N= 10186642.4550  
E= 30959353.6490  
ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 AC TRACT TO DONALD AND DOLORES GISH.

N= 10187908.0080  
E= 3097998.0100  
ELEVATION: 1002.490' (NAVD '88)

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
1501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
[WWW.KIMLEY-HORN.COM](http://WWW.KIMLEY-HORN.COM)  
TEXAS REGISTERED ENGINEERING FIRM F-928



EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
**58**

No.	REVISIONS	DATE	BY
-----	-----------	------	----







Plotted By:Kessler, Rachel Date:November 16, 2023 03:31:34pm File Path:k:\AUS-Civ\067783129 - Canton 140 - M1 Hornes\LIFT STATION\CAD\PLANS\SHEETS\G-Notes.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

PIPE AND FITTINGS

1. FORCE MAIN

1.1. 4" PVC DR11 FORCE MAIN SHALL BE USED.
1. LIFT STATION PIPING

1.1. DIP PIPE SHALL BE IN ACCORDANCE WITH AWWA C111 AND AWWA C150.

1.2. FITTINGS AND PIPE SHALL BE FLANGED

1.2.1. FITTINGS IN ACCORDANCE WITH AWWA C153 AND AWWA C110.

1.2.2. FLANGES: AWWA/ANSI C115/A21.15, ASME B16.1, CLASS 125

1.2.3. BOLTS AND NUTS SHALL BE 316 STAINLESS.

1.3. PIPE AND FITTINGS SHALL BE LINED WITH PROTECTO 401.

1.4. PROVIDE POLYETHYLENE ENCASEMENT IN ACCORDANCE WITH AWWA FOR BURIED DIP.
1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL OF THE NECESSARY WASTEWATER CONNECTIONS TO THE SITE. CONTRACTOR SHALL NOTIFY THE UTILITY AUTHORITIES INSPECTORS 72 HOURS PRIOR TO CONNECTING TO ANY EXISTING LINE. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS TO EXISTING UTILITIES DUE TO DAMAGE INCURRED DURING CONSTRUCTION.

2. CONTRACTOR SHALL CONSTRUCT LIFT STATION AND FORCE MAIN IN ACCORDANCE WITH THE CITY OF LEANDER UTILITY CRITERIA MANUAL, CITY OF AUSTIN UTILITY CRITERIA MANUAL, AND 2012 UNIFORM PLUMBING CODE.

3. A SIGN SHALL BE POSTED IN A VISIBLE LOCATION AT THE LIFT STATION TO INDICATE A PHONE NUMBER TO CALL IN CASE OF AN EMERGENCY. SIGN SHALL BE 24 INCHES BY 36 INCHES, CONSTRUCTED OF ½" THICK ALUMINUM. THE SIGN SHALL BE FASTENED TO THE FENCE WHERE DIRECTED BY OWNER USING A MINIMUM OF FOUR STAINLESS STEEL FASTENERS. THE SIGN SHALL INCLUDE THE NAME OF THE OWNER OF THE LIFT STATION AND EMERGENCY CONTACT INFORMATION.
1. CONTRACTOR SHALL USE DEZURIK PEC ECCENTRIC PLUG VALVES OR APPROVED EQUAL IN ACCORDANCE WITH AWWA C517.

2. CONTRACTOR SHALL USE VAL-MATIC SWING-FLEX CHECK VALVE OR APPROVED EQUAL IN ACCORDANCE WITH AWWA C508. CHECK VALVES SHOULD BE SUITABLE FOR DIRECT BURY.

3. A CHECK VALVE MUST BE A SWING TYPE VALVE WITH AN EXTERNAL LEVER OR EXTERNAL POSITION INDICATOR TO SHOW ITS OPEN AND CLOSED POSITIONS.

4. AN ISOLATION VALVE MUST INCLUDE AN EXTERNAL POSITION INDICATOR TO SHOW ITS OPEN AND CLOSED POSITIONS, UNLESS A FULL-CLOSING VALVE IS A RISING-STEM GATE VALVE.

5. CONTRACTOR SHALL USE ARI D-020 COMBINATION AIR VALVE OR APPROVED EQUAL.
- LIFT STATION GENERAL NOTES

1. CONFIGURATIONS AND DIMENSIONS SHOWN ARE BASED ON THE EQUIPMENT SPECIFIED. THE CONTRACTOR SHALL VERIFY THE LAYOUT AND ALL DIMENSIONS PRIOR TO CONSTRUCTION.

2. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE STRUCTURAL DESIGN FOR BRACING THE J-VENT SYSTEM.

3. A SCREEN SHALL BE INSTALLED ON THE VENT PIPE. THE SCREEN SHALL BE 304 STAINLESS STEEL-16 MESH.

4. ALL PENETRATIONS SHALL BE SEALED WATER AND GAS TIGHT PER APPROVED METHODS.

5. INSTALL ISOLATION KITS BETWEEN DISSIMILAR METAL PIPING.

6. ALL EXPOSED METAL WITHIN THE WET WELL SHALL BE GRADE 316 STAINLESS STEEL.

7. CONTRACTOR SHALL FOLLOW THE INSTALLATION INSTRUCTIONS PROVIDED BY THE SUPPLIER/MANUFACTURER.

8. UPON RECEIPT OF THE LIFT STATION SHIPMENT, INSPECT THE ENTIRE SHIPMENT FOR DAMAGE BEFORE THE LIFT STATION IS TAKEN OFF THE TRUCK. IF THERE IS DAMAGE, NOTE AS SPECIFICALLY AS POSSIBLE INCLUDING CLEAR PHOTOS OF DAMAGE ON THE BILL OF LADING AS TO ANY DAMAGE, THEN OFFLOAD. CONTACT THE SHIPPER AT ONCE AND HAVE THE BILL OF LADING WITH YOU.

9. PROPOSED CHECK VALVE, COUPLING, GATE VALVE AND AIR RELEASE VALVES (BALL VALVES MAY BE USED DEPENDING ON TYPE OF PROPOSED PUMPS).

10. PROPOSED PUMPS TO BE SELECTED BASED ON APPLICATION, FLOW, AND HEAD CONDITIONS OF FORCE MAIN.

11. CONCRETE SHALL BE 1500 psi COVERING THE ANTI-FLOATATION RING AS SHOWN.

12. SELECT BACKFILL MATERIAL FREE OF VOIDS, SHARP OBJECTS, OR OTHER DEBRIS IN ACCORDANCE WITH 510S-5-SM AND THE STRUCTURAL SHEETS PROVIDED.

SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES


1. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND PRODUCT DATA FOR LIFT STATION EQUIPMENT, PIPING AND APPURTENANCES. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS TO THE OWNER FOR REVIEW PRIOR TO INSTALLATION, ALLOWING SUFFICIENT TIME FOR THE OWNER'S REVIEW AND RESPONSE.
2. CONTRACTOR SHALL SUBMIT DIMENSIONAL LAYOUT DRAWINGS AND PRODUCT DATA, CERTIFIED CORRECT FOR CONSTRUCTION, FOR REVIEW BY THE OWNER.
3. THE CONTRACTOR WILL MAKE SPECIFIC MENTION OF THOSE ITEMS THAT VARY FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS IN THE LETTER OF TRANSMITTAL.
4. THE CONTRACTOR WILL ASSIGN A SEQUENTIAL NUMBER TO EACH SUBMITTAL (1, 2, 3, ETC.). RE-SUBMITTALS WILL BE IDENTIFIED WITH THEIR ORIGINAL NUMBER FOLLOWED BY A SEQUENTIAL LETTER (A, B, C, ETC. ). FOR EXAMPLE, SUBMITTAL 12-C IS THE THIRD RE-SUBMITTAL OF THE OF THE TWELFTH ITEM FOR THE PROJECT.
5. THE CONTRACTOR WILL NOT DELIVER TO THE SITE, STORE, OR INCORPORATE INTO THE WORK, ANY MATERIALS OR EQUIPMENT FOR WHICH APPROVED SUBMITTALS HAVE NOT BEEN OBTAINED.
6. OWNER'S REVIEW, APPROVAL, OR OTHER APPROPRIATE ACTION REGARDING CONTRACTOR'S SUBMISSIONS WILL BE ONLY TO CHECK CONFORMITY WITH THE DESIGN CONCEPT OF THE PROJECT AND FOR COMPLIANCE WITH THE INFORMATION CONTAINED IN THE CONTRACT DOCUMENTS AND SHALL NOT EXTEND TO MEANS, METHODS, TECHNIQUES, DEQUENCES OR PROCEDURES OF CONSTRUCTION (EXCEPT WHERE A SPECIFIC MEANS, METHOD, TECHNIQUE, SEQUENCE OR PROCEDURE OF CONSTRUCTION IS INDICATED IN OR REQUIRED BY THE CONTRACT DOCUMENTS) OR TO SAFETY PRECAUTIONS OR PROGRAMS INCIDENT THERETO. THE REVIEW AND APPROVAL OF A SEPARATE COMPONENT ITEM WILL NOT INDICATE APPROVAL OF THE ASSEMBLY INTO WHICH THE ITEM IS FUNCTIONALLY INTEGRATED. CONTRACTOR SHALL MAKE CORRECTIONS REQUIRED BY OWNER, AND SHALL RETURN THE REQUIRED NUMBER OF CORRECTED COPIES OF SHOP DRAWINGS TO THE OWNER. CONTRACTOR MAY BE REQUIRED TO RESUBMIT AS REQUIRED REVISED SHOP DRAWINGS OR SAMPLES FOR FURTHER REVIEW AND APPROVAL. CONTRACTOR SHALL DIRECT SPECIFIC ATTENTION IN WRITING TO ANY NEW REVISIONS NOT SPECIFIED BY CONTRACTOR ON PREVIEW CONTRACTOR SUBMISSIONS.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY  
LIFT STATION AND FORCE MAIN  
GENERAL CONSTRUCTION NOTES

THE FOLLOWING/LISTED "CONSTRUCTION NOTES" ARE INTENDED TO BE ADVISORY IN NATURE ONLY AND DO NOT CONSTITUTE AN APPROVAL OR CONDITIONAL APPROVAL BY THE EXECUTIVE DIRECTOR (ED), NOR DO THEY CONSTITUTE A COMPREHENSIVE LISTING OF RULES OR CONDITIONS TO BE FOLLOWED DURING CONSTRUCTION. FURTHER ACTIONS MAY BE REQUIRED TO ACHIEVE COMPLIANCE WITH TCEQ REGULATIONS FOUND IN TITLE 30, TEXAS ADMINISTRATIVE CODE (TAC), CHAPTERS 213 AND 217, AS WELL AS LOCAL ORDINANCES AND REGULATIONS PROVIDING FOR THE PROTECTION OF WATER QUALITY. ADDITIONALLY, NOTHING CONTAINED IN THE FOLLOWING/LISTED "CONSTRUCTION NOTES" RESTRICTS THE POWERS OF THE ED, THE COMMISSION OR ANY OTHER GOVERNMENTAL ENTITY TO PREVENT, CORRECT, OR CURTAIL ACTIVITIES THAT RESULT OR MAY RESULT IN POLLUTION OF THE EDWARDS AQUIFER OR HYDROLOGICALLY CONNECTED SURFACE WATERS. THE HOLDER OF ANY EDWARDS AQUIFER PROTECTION PLAN CONTAINING "CONSTRUCTION NOTES" IS STILL RESPONSIBLE FOR COMPLIANCE WITH TITLE 30, TAC, CHAPTERS 213 OR ANY OTHER APPLICABLE TCEQ REGULATION, AS WELL AS ALL CONDITIONS OF AN EDWARDS AQUIFER PROTECTION PLAN THROUGH ALL PHASES OF PLAN IMPLEMENTATION. FAILURE TO COMPLY WITH ANY CONDITION OF THE ED'S APPROVAL, WHETHER OR NOT IN CONTRADICTION OF ANY "CONSTRUCTION NOTES," IS A VIOLATION OF TCEQ REGULATIONS AND ANY VIOLATION IS SUBJECT TO ADMINISTRATIVE RULES, ORDERS, AND PENALTIES AS PROVIDED UNDER TITLE 30, TAC § 213.10 (RELATING TO ENFORCEMENT). SUCH VIOLATIONS MAY ALSO BE SUBJECT TO CIVIL PENALTIES AND INJUNCTION. THE FOLLOWING/LISTED "CONSTRUCTION NOTES" IN NO WAY REPRESENT AN APPROVED EXCEPTION BY THE ED TO ANY PART OF TITLE 30 TAC, CHAPTERS 213 AND 217, OR ANY OTHER TCEQ APPLICABLE REGULATION

1. THIS LIFT STATION AND/OR FORCE MAIN MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.5(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) EDWARDS AQUIFER RULES, AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.
2. ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED LIFT STATION/FORCE MAIN (LSFM) SYSTEM APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF A LSFM SYSTEM APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.
3. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:  
- THE NAME OF THE APPROVED PROJECT;  
- THE ACTIVITY START DATE; AND  
- THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
4. UPON COMPLETION OF ANY LIFT STATION EXCAVATION, A GEOLOGIST MUST CERTIFY THAT THE EXCAVATION HAS BEEN INSPECTED FOR THE PRESENCE OF SENSITIVE FEATURES. THE CERTIFICATION MUST BE SIGNED, SEALED, AND DATED BY THE GEOLOGIST PREPARING THE CERTIFICATION. CERTIFICATION THAT THE EXCAVATION HAS BEEN INSPECTED MUST BE SUBMITTED TO THE APPROPRIATE REGIONAL OFFICE.  
- IF SENSITIVE FEATURE(S) ARE IDENTIFIED, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY AND MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY FROM THE LIFT STATION. - CONSTRUCTION MAY CONTINUE IF THE GEOLOGIST CERTIFIES THAT NO SENSITIVE FEATURE OR FEATURES WERE PRESENT.
5. IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERY. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING WITHIN TWO WORKING DAYS. THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRUCTURAL INTEGRITY OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY TCEQ-0591 (REV. 2-26-2016) PAGE 2 OF 2 ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.
6. ALL FORCE MAIN LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC §217.68. TESTING METHOD WILL BE:  
- A PRESSURE TEST MUST USE 50 POUNDS PER SQUARE INCH ABOVE THE NORMAL OPERATING PRESSURE OF A FORCE MAIN.  
- A TEMPORARY VALVE FOR PRESSURE TESTING MAY BE INSTALLED NEAR THE DISCHARGE POINT OF A FORCE MAIN AND REMOVED AFTER A TEST IS SUCCESSFULLY COMPLETED.  
- A PUMP ISOLATION VALVE MAY BE USED AS AN OPPOSITE TERMINATION POINT.  
- A TEST MUST INVOLVE FILLING A FORCE MAIN WITH WATER.  
- A PIPE MUST HOLD THE DESIGNATED TEST PRESSURE FOR A MINIMUM OF 4.0 HOURS.  
- THE LEAKAGE RATE MUST NOT EXCEED 10.0 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER DAY.

Austin Regional Office 12100 Park 35 Circle, Building A Austin, Texas 78753-1808 Phone (512) 339-2929 Fax (512) 339-3795	San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329
--	---



EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
60

LIFT STATION  
NOTES

KHA PROJECT  
067783129  
DATE  
OCTOBER 2023  
SCALE: AS SHOWN  
DESIGNED BY: RAK  
DRAWN BY: NAN  
CHECKED BY: TRR

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM E-928

No.


REVISIONS

DATE

BY





Plotted By:Kessler, Rachel Date:November 16, 2023 03:32:21pm File Path:k:\AUS\_Civil\067783129 - Canyon 140 - MI Hornes\LIFT STATION\CAD\PLANS\SHEETS\C-1US Site Plan.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



NOTES

- ALL MECHANICAL JOINTS SHALL HAVE MEGA LUG THRUST RESTRAINTS.
- FOR ALL ELECTRICAL WORK REFER TO ELECTRICAL SHEETS.
- BURIED DUCTILE IRON PIPES, VALVES, AND FITTINGS SHALL BE ENCASED WITH POLYETHYLENE WRAP 8 MILS THICK.
- THE CONTRACTOR SHALL MAINTAIN ADEQUATE DRAINAGE AT ALL TIMES AND PROVIDE AND MAINTAIN EROSION PROTECTION IN AND ADJACENT TO THE CONSTRUCTION LIMITS.
- ALL STRUCTURES HAVE MIN. 6" OF CLEARANCE BETWEEN TOP OF SLAB AND PROPOSED NATURAL GROUND.
- CONTRACTOR SHALL GRADE THE SITE TO PROVIDE POSITIVE DRAINAGE AROUND ALL STRUCTURES AND SLABS.
- CONTRACTOR SHALL INCLUDE IDENTIFICATION SIGN WITH LIFT STATION NAME AND EMERGENCY CONTACT INFORMATION. THE CONTRACTOR SHALL COORDINATE WITH THE CITY OF LEANDER FOR INFORMATION AND SUBMIT SHOP DRAWINGS FOR THE SIGN DETAILS FOR APPROVAL.
- LIFT STATION DESIGN SHALL BE IN ACCORDANCE WITH THE ENCLOSED CITY OF LEANDER AND CITY OF AUSTIN LIFT STATION SPECIFICATIONS.
- ALL UNPAVED AREAS OF SITE WITHIN FENCED BOUNDARIES SHALL BE COVERED WITH WEED BARRIER AND A 6" LAYER OF TXDOT GRADE 1 CRUSHED STONE COARSE AGGREGATE.




LEGEND

- |  |                          |
|--|--------------------------|
|  | PROPOSED 4" FORCE MAIN   |
|  | PROPOSED WASTEWATER LINE |
|  | PROPOSED CONTOUR         |
|  | EXISTING CONTOUR         |
|  | PROPOSED CONCRETE SLAB   |

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM E-928



KHA PROJECT	067783129
DATE	OCTOBER 2023
SCALE	AS SHOWN
DESIGNED BY:	RAK
DRAWN BY:	NAN
CHECKED BY:	TRR

LIFT STATION SITE PLAN


**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
**61**










PUMP LEVEL SETTINGS	
PIPE INVERT	934.7'
HIGH WATER ALARM	933.70'
LAG PUMP ON	932.70'
LEAD PUMP ON	931.70'
TOP OF PUMP	928.87'
ALL PUMPS OFF	928.79'
LOW LEVEL ALARM	928.79'
BOTTOM OF PUMP	926.40'
ADJUSTED WET WELL FLOOR	926.00'

1. THE WORK PERFORMED UNDER THIS CONTRACT SHALL COMPLY WITH THE CITY OF AUSTIN SUSPENSIBLE LIFT STATION SPECIFICATIONS.
2. CONFIGURATIONS AND DIMENSIONS SHOWN ARE BASED ON THE EQUIPMENTS SPECIFIED. THE CONTRACTOR SHALL VERIFY THE LAYOUT AND ALL DIMENSIONS PRIOR TO FABRICATION.
3. ALL COUPLINGS SHALL BE EPOXY COATED STEEL AND SHALL BE DRESSER, SMITH-BLAIR, OR EQUAL. COUPLINGS SHALL BE RESTRAINED WITH A THRUST HARNESS DESIGNED IN ACCORDANCE WITH AWWA M-11.
4. CONTRACTOR SHALL COORDINATE VALVE VAULT ACCESS HATCH LOCATION WITH LADDER MANUFACTURER PRIOR TO FABRICATION.
5. CONTRACTOR SHALL VERIFY WETWELL ACCESS HATCH LOCATION AND DIMENSION WITH PUMP MANUFACTURER PRIOR TO FABRICATION.
6. PROVIDE 316 STAINLESS STEEL ANCHOR BOLTS FOR PUMP BASE MOUNTING TO SLAB.
7. INSTALL ISOLATION KITS BETWEEN DISSIMILAR METAL PIPING.
8. ALL PIPING WITHIN WET WELL AND VALVE VAULT SHALL BE SPECIAL THICKNESS CLASS 53 EPOXY LINED (PROTECTO 401) DUCTILE IRON PIPE. SEE CITY OF AUSTIN SPL WW-534.
9. ALL BURIED PIPE SHALL BE POLYWRAPPED DUCTILE IRON PRESSURE CLASS 350 PUSH JOINT PIPE WITH JOINT RESTRAINT GASKETS (SEE CITY OF AUSTIN SPL WW-27G).
10. ALL METALS WITHIN THE WET WELL, INCLUDING FLANGE BOLTS, SHALL BE STAINLESS STEEL, UNLESS OTHERWISE INDICATED.
11. CONCRETE FOR FOUNDATION SHALL BE CLASS S. CONCRETE SHALL HAVE A MIN COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS.
12. THE EDGE OF EXPOSED CONCRETE SLABS SHALL RECEIVE A 3/4" CHAMFER.
13. REINFORCED STEEL SHALL BE GRADE 60.
14. ALL VENTS SHALL HAVE SCREENS INSTALLED OVER OPENINGS AND SHALL BE 304 STAINLESS STEEL - 16 MESH. OPENINGS SHALL BE A MINIMUM OF 12" ABOVE THE SLAB.
15. THE HIGH LEVEL ALARM SHALL ACTIVATE A FLASHING RED LIGHT TO BE MOUNTED ON THE ROOF OF THE ELECTRICAL SHELTER. THE CONTRACTOR SHALL INSTALL METAL INFORMATION SIGN AT OR NEAR THE LIFT STATION ENTRY GATE, VISIBLE TO THE PUBLIC.
16. ALL PENETRATIONS SHALL BE SEALED WATER AND GAS TIGHT PER APPROVED METHODS.
17. ALL SUBMITTALS TO BE SUBMITTED TO THE CITY OF BUDA FOR APPROVAL.
18. BACK FILLING OF THE WET WELL SHALL COMPLY WITH CITY OF AUSTIN STANDARD SPECIFICATIONS, ITEM NO. 401.
19. SHOP DRAWING AND STRUCTURAL CALCULATIONS FOR THE CAST IN PLACE CONCRETE WET WELL SHALL BE SIGNED AND SEALED BY AN ENGINEER LICENSED IN THE STATE OF TEXAS AND SUBMITTED FOR REVIEW BY THE OWNER AND ENGINEER




Plotted By: kessler, Rachel Date: November 16, 2023 03:33:24pm File Path: K:\AUS-Civil\STATION\CAD\PLANS\DETAILS\DWG Detail.dwg  
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



- NOTES:
1. POLYMER CONCRETE MANHOLES SHALL BE MANUFACTURED BY U.S. COMPOSITE PIPE, INC., A DIVISION OF THOMPSON PIPE GROUP, OR PRE-APPROVED EQUAL.
  2. PIPES SHALL BE DIRECTLY CONNECTED TO ALL STRUCTURES USING RESILIENT FLEXIBLE PIPE TO MANHOLE CONNECTOR PER ASTM C923.
  3. ROUND MANHOLE COMPONENTS SHALL BE CONNECTED WITH AN ELASTOMERIC SEALING GASKET AS THE SOLE MEANS TO MAINTAIN JOINT WATER-TIGHTNESS AND BOTH THE GASKET MATERIAL AND THE MANHOLE JOINT SHALL MEET THE REQUIREMENTS OF ASTM C443. ROUND MANHOLES SHALL UTILIZE SPIGOT AND BELL TYPE JOINTS INCORPORATING EITHER A CONFINED O-RING OR SINGLE STEP PROFILE JOINT.

## POLYMER CONCRETE MANHOLE DETAIL


N.T.S.



## ADJUSTABLE PIPE SUPPORT DETAIL


N.T.S.

PIPE SIZE	WGT APPROX. LBS EACH						D	
	COMPLETE	SADDLE ONLY	A	A	A	MINIMUM	MAXIMUM	
2 1/2	9.0	4.8	2 1/2	3 1/2	1 1/2	8	13	
3	9.2	5.0	2 1/2	3 3/4	1 1/2	8 1/4	13 1/4	
3 1/2	9.4	5.2	2 1/2	4	1 1/2	8 1/2	13 1/2	
4	15.0	7.6	3	4 1/4	2 1/2	9 1/4	14	
5	16.7	8.3	3	4 7/8	2 1/2	10	14 3/4	
6	17.7	10.3	3	5 1/2	2 1/2	10 1/2	15 1/4	
8	20.2	12.8	3	6 7/8	2 1/2	11 3/4	16 1/2	
10	25.2	17.8	3	5 1/2	2 1/2	13 1/2	18 1/4	
12	29.0	21.6	3	9 15/16	2 1/2	15	19 3/4	
14	49.2	38.0	4	10 15/16	3	16 1/4	20 3/4	
16	53.2	42.0	4	12 3/8	3	17 3/4	22 1/4	
18	70.8	51.0	6	13 7/8	3 1/2	19 1/2	24	
20	104.8	85.0	6	15 3/8	3 1/2	21	25 1/2	
24	137.0	110.0	6	17 15/16	4	23 3/4	28 1/2	
30	170.0	150.0	6	21 5/16	4	27	31 1/2	
32	181.0	161.1	6	22 1/2	4	28 1/8	32 3/4	
36	249.0	229.0	6	24 1/4	4	30 1/4	34 3/4	




## COA WW-146-D WET WELL PENETRATION DETAIL

N.T.S.



## VAULT PENETRATION DETAIL


N.T.S.



- NOTES:
1. PRESSURE GAUGES SHALL HAVE 4-INCH DIAMETER FACES AND BE CALIBRATED FROM 0 TO 150 PSI.
  2. GAUGE SHALL BE FILLED WITH GLYCOL AND INSTALLED WITH A PRESSURE SNUBBER AND SHALL BE OF STAINLESS STEEL CONSTRUCTION.
  3. INSTALL GAUGE WITH A 0.25-INCH NPT CONNECTION AND INCLUDE A CORPORATION STOP AND AIR BLEED.
  4. VALVES TO BE RATED AT 200 PSI MIN..
  5. ALL WELDED COUPLINGS SHALL BE RATED FOR 3000 LBS.
  6. GAUGE SHALL BE TRECICE MANUFACTURED OR APPROVED EQUAL.

## PRESSURE GAUGE DETAIL

N.T.S.



## WATER SERVICE METER DETAIL

N.T.S.

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78628  
PHONE: 512-520-0768 FAX: 512-418-791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM E-928




KHA PROJECT	067783129	DATE	OCTOBER 2023	SCALE	AS SHOWN	DESIGNED BY	RAK	DRAWN BY	NAN	CHECKED BY	TRR
-------------	-----------	------	--------------	-------	----------	-------------	-----	----------	-----	------------	-----

LIFT STATION DETAILS  
(SHEET 1 OF 4)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
64






1 DE  
N.T.S.




† Specify ECT for plain trolley, ECGT for geared trolley, and ECMT for motorized trolley models.  
\* S = Small frame hoist, single or three phase. L = Large frame hoist, three phase only.  
P = Parallel mount, standard on small frame hoists. C = Cross mount, standard on large frame hoists.  
\*\* Weight for 10 ft. lift ECT units. Add 10 lb. for ECGT unit weights.  
\*\*\* 4 & 5 ton straight track only. Articulated model for 48" min. radius curved track available — consult factory.

**NOTE:** For complete dimensional data, refer to Coffing Dimensional Databook.



65


© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
[WWW.KIMLEY-HORN.COM](http://WWW.KIMLEY-HORN.COM)  
TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT 067783129	DATE OCTOBER 2023	SCALE: AS SHOWN	DESIGNED BY: RAK	DRAWN BY: NAN	CHECKED BY: TRR
--------------------------	----------------------	-----------------	------------------	---------------	-----------------




Plotted By:Kessler, Rachel Date:November 16, 2023 03:33:28pm File Path:K:\AUS\_Civil\STATION\CAD\PLANS\SEETS\D-15 Detail.dwg This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



1 ASPHALT PAVEMENT CONNECTION DETAIL

N.T.S.



2 LADDER DETAIL

N.T.S.

Motor type		682YSG	
Motor manufacturer	KSB SE & Co. KGaA	Rated voltage	460 V
Design acc. standard	-	Rated frequency	60 Hz
Degree of protection	IP68	Rated HP (D.O.L) or VFD	9.12 hp
Insulation class		Rated current	11.7 A
Coolant temperature	< / = 104 °F (40 °C)	Nominal speed	3,452 rpm
Starting mode	Direct starting	Starting to rated current	9.7 A
No. starts / h	30	Starting current	113.5 A
		Max. voltage	483 V
		Min. voltage	437 V
Discharge cover	Grey cast iron EN-GJL-250 (A 48 Class 35B)		
Explosion protection	Class I, Div. 1, Groups C&D T4		
Pump type	Amarex D-max 80-170/068F2YSG2		


PUMP MOTOR DATA

3 N.T.S.

Operating data			
Flow	200 US g.p.m.	Fluid	01 Water, clean water
Head	93.1 ft	Density of fluid	62.3 lb/ft³
Operating speed	3,473 rpm	Viscosity	1.08E-5 ft²/s
Shaft power	7.94 hp	Temperature	68 °F
Efficiency	59.2 %	Hydraulic acceptance acc.	
Required pump NPSH	121 ft		
Head H(Q=0)	121 ft	Flow	82.6 US g.p.m.
Application range	From 121 ft To 13 ft	Flow	409 US g.p.m.


PUMP OPERATING DATA

4 N.T.S.




5 ODOR CONTROL DETAIL

N.T.S.



6 AIR RELEASE VALVE DETAIL

N.T.S.




7 FLOW METER VAULT DETAIL

N.T.S.

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78628  
PHONE: 512-520-0768 FAX: 512-418-791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM E-928



KHA PROJECT	067783129	DATE	OCTOBER 2023	SCALE	AS SHOWN	DESIGNED BY	RAK	DRAWN BY	NAN	CHECKED BY	TTR
-------------	-----------	------	--------------	-------	----------	-------------	-----	----------	-----	------------	-----

LIFT STATION DETAILS  
(SHEET 3 OF 4)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
66




Project	Edgewood Lift Station - 11.2.23
Project ID	PSI - CADEN KOZIK
Created by	
Pos.no	1
Customer Pos. No.	



Page 5 / 11  
Created 2023-11-02  
Update 2023-11-02

### Performance curve

**Pump type** Amarex D-max 80-170/068F2YSG2




Impeller type	Single vane impeller ,Open	Curve number	K2573-62-08
Impeller size	5 11/16 inch	Density of fluid	62.322 lb/ft³
		Viscosity	1.082E-5 ft²/s
		Frequency	60 Hz
		Speed	3,472.9 1/min

KSB Aktiengesellschaft, Turmstrasse 92, 06110 Halle (Germany), Phone +49 (345) 48260, Fax +49 (345) 4826 4699, [www.ksb.com](http://www.ksb.com)

### 1 PUMP PERFORMANCE CURVE DETAIL

N.T.S.




## SYSTEM AND PUMP CURVE DETAIL

N.T.S.

**EDGEWOOD  
PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
67

LIFT STATION DETAILS  
(SHEET 4 OF 4)



**Kimley»»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
[WWW.KIMLEY-HORN.COM](http://WWW.KIMLEY-HORN.COM)

[illegible]



Plotted By: Cameron Cutbirth Date: November 07, 2023 03:32:55pm File Path: K:\Projects\2023\3950623--Kimley-Horn-Edgewood Lift Station\01 Design Phase\3950623-E10.dwg This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

ELECTRICAL SYMBOL LEGEND

NOT ALL SYMBOLS SHOWN MAY BE USED

PLAN LEGEND

SYMBOL	DESCRIPTION
	JUNCTION BOX
	DISCONNECT SWITCH
	MOTOR STARTER OR LIGHTING CONTACTOR, SURFACE MOUNTED
	COMBINATION MOTOR STARTER, AND DISCONNECT SWITCH, SURFACE MOUNTED
	MANHOLE, NUMBER OF MANHOLE SHOWN NEXT TO SYMBOL
	COMMUNICATIONS MANHOLE, NUMBER OF MANHOLE SHOWN NEXT TO SYMBOL
	TELECOMMUNICATIONS MANHOLE, NUMBER OF MANHOLE SHOWN NEXT TO SYMBOL
	KEYED NOTE, NUMBER IN POSITION "W" MATCHES NOTE NUMBER
	SWITCH, TOGGLE, WALL MOUNTED, (SINGLE POLE THROW) MOUNT 48" AFF, UON
	SWITCH, TOGGLE, WALL MOUNTED, THREE WAY, (SINGLE POLE DOUBLE THROW) MOUNT 48" AFF, UON
	EXPLOSION PROOF SWITCH, TOGGLE, WALL MOUNTED, (SINGLE POLE THROW) MOUNT 48" AFF, UON
	SWITCH, MOTOR RATED, WITH THERMAL OVERLOADS
	TERMINAL BOARD
	TELEPHONE OUTLET, PRIVATE, MOUNTED 12" AFF, UON
	WATHOUR METER
	POLE
	TRANSFORMER, PAD MOUNTED, KVA RATING MAY BE DISPLAYED NEXT TO SYMBOL
	TRANSFORMER, DRY TYPE, KVA RATING MAY BE DISPLAYED INSIDE OF SYMBOL
	ANTENNA
	CONDUIT AND/OR WIRING HOMERUN TO PANEL, TERMINAL BOARD, OR CONTROLLER, USED WITH THE FOUR PRECEDING SYMBOLS. DESTINATION EQUIPMENT IDENTIFIER SHOWN IN POSITION "W" CIRCUIT NUMBER SHOWN IN POSITIONS "X", "Y", OR "Z". THESE CIRCUITS MAY ONLY SHOW ONE CIRCUIT NUMBER
	WIRING CONTINUATION
	FLEXIBLE CONDUIT
	HOMERUN
	CONDUIT CAPPED FOR FUTURE USE
	CONDUIT GOING DOWN
	CONDUIT GOING UP
	CONDUIT RUN UNDERGROUND OR CONCEALED
	CONDUIT RUN EXPOSED
	120V RECEPTACLE FLUSH MOUNTED
	250V RECEPTACLE FLUSH MOUNTED
	WELDING OUTLET
	THERMOSTAT
	PANELBOARD SURFACE MOUNTED

GROUNDING LEGEND

SYMBOL	DESCRIPTION
	A OR B GROUNDING RECEPTACLE = A, GROUND TEST WELL = B
	CONDUCTOR BARE UON
	GROUNDING CONNECTION
	GROUND BUS BAR LENGTH AS SHOWN BY SYMBOL LENGTH UON
	COPPERCLAD GROUND ROD

SYMBOL	MODIFIERS
(E)	EXISTING
WP	WEATHERPROOF
EP	EXPLOSION PROOF
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
T	TELEPHONE
P	POWER
F	FIRE ALARM
VT	VAPORTIGHT
WT	WATERTIGHT
PT	PAINTTIGHT
P	PRIMARY
O	OVERHEAD
U	UNDERGROUND
S	SECONDARY
FT	FIXED TEMPERATURE
R	RECESSED
G	GROUNDING
UNG	UNGROUNDING

ONE LINE AND CONTROL SCHEMATIC LEGEND

SYMBOL	DESCRIPTION
	GROUNDING CONNECTION, WHEN USED WITH TRANSFORMER SYMBOL IT DENOTES A NEUTRAL GROUNDING CONNECTION
	GROUNDIED WYE WINDING CONNECTION
	DELTA WINDING CONNECTION
	RELAY OR CONTACTOR CONTACTS
	SEPARABLE CONNECTOR OR CONNECTION FOR DRAWOUT ASSEMBLIES
	CONDUCTOR CONNECTION
	CIRCUIT BREAKER, MOLDED CASE, TRIP CURRENT AND QUANTITY OF POLES (P) SHOWN NEXT TO SYMBOL
	SWITCH, DISCONNECT, NON-FUSED, LOAD BREAK, CONTINUOUS CURRENT RATING AND QUANTITY OF POLES SHOWN NEXT TO SYMBOL
	SWITCH, DISCONNECT, FUSED, LOAD BREAK, FUSED AMPERE RATING AND FUSE TYPE SHOWN NEXT TO SYMBOL
	FUSE, AMPERE RATING AND FUSE TYPE SHOWN NEXT TO SYMBOL
	MOTOR THERMAL OVERLOAD PROTECTOR
	MOTOR STARTER MAIN CONTACTOR
	CONTACTOR OR RELAY COIL, LETTER(S) INSIDE OF SYMBOL MATCH CONTACTS CONTROLLED
	PRESSURE TRANSMITTER
	EQUIPMENT ENCLOSURE
	VOLTMETER SWITCH
	AMMETER SWITCH
	AMMETER
	VOLTMETER
	CURRENT TRANSFORMER WITH RATIO SHOWN
	MOTOR, 10 HORSEPOWER SHOWN
	LIMIT SWITCH NORMALLY CLOSED
	LIMIT SWITCH NORMALLY OPEN
	MOTOR OPERATED VALVE GEARED LIMIT SWITCH
	PRESSURE SWITCH NORMALLY CLOSED OPENS ON INCREASING PRESSURE
	PRESSURE SWITCH NORMALLY OPEN CLOSSES ON INCREASING PRESSURE
	LEVEL SWITCH NORMALLY CLOSED OPENS ON INCREASING LEVEL
	LEVEL SWITCH NORMALLY OPEN CLOSSES ON INCREASING LEVEL
	FLOW SWITCH NORMALLY CLOSED OPENS WITH FLOW
	FLOW SWITCH NORMALLY OPEN CLOSSES ON LOSS OF FLOW
	SPACE HEATER
	PHASE FAILURE RELAY
	DRAW-OUT CIRCUIT BREAKER
	INSTANTANEOUS/TIME OVERCURRENT RELAY
	NEUTRAL TIME OVERCURRENT RELAY
	CABLE TERMINATOR
	UNDERVOLTAGE/PHASE-SEQUENCE RELAY
	LOCKOUT RELAY
	DESOLVED OXYGEN SENSOR
	FLOW SWITCH
	ANALYTIC INDICATOR
	LEVEL TRANSDUCER
	FLOW METER

ONE LINE AND CONTROL SCHEMATIC LEGEND (CONT'D)

SYMBOL	DESCRIPTION
	INSTRUMENT TRANSFORMER PT-POTENTIAL TRANSFORMER
	CONTROL POWER TRANSFORMER. VOLTAGE AS SHOWN
	LIGHTNING ARRESTER
	SWITCH
	NORMALLY OPEN CONTACT
	NORMALLY CLOSED CONTACT
	MOMENTARY PUSHBUTTON
	THREE POSITION MAINTAINED CONTACT SWITCH
	MOTOR OPERATED VALVE
	SOLENOID VALVE
	ELAPSED TIME METER
	TIME DELAY RELAY. TIMES OUT AFTER ENERGIZATION
	TIME DELAY RELAY. TIMES OUT AFTER DENERGIZATION
	PILOT LIGHT R=RED B=BLUE G=GREEN A=AMBER Y=YELLOW
	HIGH LEVEL FLOAT SWITCH
	LOW LEVEL CUTOFF FLOAT SWITCH
	MOTOR STARTER FVNR=FULL VOLTAGE NON-REVERSING VFD=VARIABLE FREQUENCY DRIVE WITH BYPASS SOFT START=ELECTRONIC SOFT START RVNR=REDUCED VOLTAGE NON-REVERSING FVR=FULL VOLTAGE REVERSING MCP=MOTOR CIRCUIT PROTECTOR SIZE=NEMA STARTER SIZE
	LEVEL SENSOR TERMINATION ENCLOSURE
	TEMPERATURE SWITCH
	MOISTURE PROBE
	SOLENOID VALVE
	LIMIT SWITCH
	AMMETER SWITCH
	VOLTMETER SWITCH
	PRESSURE SWITCH
	LIGHTING CONTACTOR

ELECTRICAL DRAWING INDEX

E1.0	ELECTRICAL NOTES, SYMBOLS AND ABBREVIATIONS
E1.1	ELECTRICAL SPECIFICATIONS
E1.2	GENERATOR SPECIFICATIONS
E1.3	GENERATOR / ATS SPECIFICATIONS
E1.4	SCADA SPECIFICATIONS
E2.0	ELECTRICAL SITE PLAN
E3.0	ELECTRICAL ONE-LINE DIAGRAM AND SCHEDULES
E4.0	ELECTRICAL DETAILS
E4.1	ELECTRICAL DETAILS
E4.2	ELECTRICAL DETAILS
E4.3	ELECTRICAL DETAILS
E4.4	ELECTRICAL DETAILS
E5.0	PUMP CONTROL PANEL DETAILS
E5.1	PUMP CONTROL DETAILS
E6.0	SCADA DETAILS

ABBREVIATIONS

A	AMPERES OR TRIP AMPERES
AC	ALTERNATING CURRENT
ACT	ABOVE COUNTER TOP
A/C	AIR CONDITIONING
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	ASYMMETRICAL AMPS INTERRUPTING CAPACITY
AWG	AMERICAN WIRE GAGE
BD	BOARD
BLDG	BUILDING
C	CONDUIT
CAB	CABINET
CAP	CAPACITOR
CB	CIRCUIT BREAKER
CKT	CIRCUIT
CL	CURRENT LIMITING
CONN	CONNECT OR CONNECTION
CONT'D	CONTINUED
CONTR	CONTRACTOR
CPT	CONTROL POWER TRANSFORMER
CT	CURRENT TRANSFORMER
CU	COPPER
DBL	DOUBLE
DIM	DIMENSION
DISC SW	DISCONNECT SWITCH
DC	DIRECT CURRENT
EA	EACH
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
ELEC	ELECTRICAL
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
ENCL	ENCLOSURE
EQUIP	EQUIPMENT
FLA	FULL LOAD AMPS
FLEX	FLEXIBLE CONDUIT
FIX	FIXTURE
GC	GENERAL CONTRACTOR
GALV	GALVANIZED
GEN	GENERATOR
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFI	GROUND FAULT INTERRUPTER
GND	GROUND
HOA	HAND-OFF-AUTO
HP	HORSEPOWER
HT	HEIGHT
HTR	HEATER
HZ	HERTZ
JB	JUNCTION BOX
KCMIL	THOUSAND CIRCULAR MILLS
KVA	KILOVOLT AMPERES
W	KILOWATT
KWH	KILOWATT HOURS
LA	LIGHTNING ARRESTOR
L-L	LINE TO LINE
L-N	LINE TO NEUTRAL
LTC	LIGHT OR LIGHTING
MC	MECHANICAL CONTRACTOR
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER

ABBREVIATIONS (CONT'D)

MCP	MOTOR CIRCUIT PROTECTOR
MIN	MINIMUM
MLO	MAIN LUGS ONLY
MSB	MAIN SWITCH BOARD
MTD	MOUNTED
MTG	MOUNTING
N.C.	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NEUT	NEUTRAL
NIC	NOT IN THIS CONTRACT
N.O.	NORMALLY OPEN
NTS	NOT TO SCALE
OC	ON CENTER
OH	OVERHEAD
OL	OVERLOAD
Ø	PHASE
P	POLE
PC	PHOTOELECTRIC
PEN	PENDANT
PNL	PANELBOARD
PRV	PRESSURE REDUCING VALVE
PVC	POLYVINYL CHLORIDE
R	RELOCATED
RECP	RECEPTACLE
REQ'D	REQUIRED
REQ'MTS	REQUIREMENTS
RM	ROOM
SCH	SCHEDULE
SE	SERVICE ENTRANCE
SM	SURFACE MOUNT
SN	SOLID NEUTRAL
SOV	SOLENOID OPERATED VALVE
SPACE	SPACES(S) ONLY (NO BREAKER OR DEVICE)
SPARE	SPARE BREAKER OR DEVICE
SPD	SURGE PROTECTIVE DEVICE
SPECS	CONTRACT SPECIFICATIONS
SS	STAINLESS STEEL HARDWARE
SWBD	SWITCHBOARD
SW	SWITCH
SWGR	SWITCH GEAR
TB	TELEPHONE BACKBOARD
TIB	TELEPHONE TERMINAL BOARD
TYP	TYPICAL
UE	UNDERGROUND ELECTRIC
UL	UNDERWRITERS LABORATORIES
UON	UNLESS OTHERWISE NOTED
UT	UNDERGROUND TELEPHONE
VA	VOLT AMPERES
W	WATTS
W/	WITH
WH	WATER HEATER
WP	WEATHER PROOF
XFMR	TRANSFORMER
XMTR	TRANSMITTER
1/C	SINGLE CONDUCTOR CABLE
3/C	THREE CONDUCTOR CABLE

GENERAL NOTES: (APPLICABLE TO ALL ELECTRICAL SHEETS)

- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE, ALL CITY, COUNTY, AND STATE REGULATIONS, NFPA, ANSI, UL, IEEE, AND THE LOCAL CODE AUTHORITY HAVING JURISDICTION. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMITS AND INSPECTIONS.
- ALL ELECTRICIANS SHALL BE LICENSED BY THE APPROPRIATE CITY, STATE, OR LOCAL CODE AUTHORITY HAVING JURISDICTION.
- THE ELECTRICAL CONTRACTOR SHALL FOLLOW ALL OSHA AND OWNER SAFETY RULES AS REQUIRED TO WORK ON THIS SITE.
- ALL INSTALLATIONS SHALL BE DONE IN A NEAT AND WORKMAN LIKE MANNER.
- ALL POWER OUTAGES SHALL BE PERFORMED DURING NON-BUSINESS HOURS. COORDINATE ALL POWER OUTAGES WITH THE OWNER. NOTIFY THE OWNER IN WRITING 10 DAYS PRIOR TO SCHEDULING ANY POWER OUTAGES.
- THE ELECTRICAL CONTRACTOR SHALL PROVIDE ALL TEMPORARY ELECTRICAL POWER AND LIGHTING REQUIRED FOR THIS PROJECT.
- THE DEMOLITION DRAWINGS (IF APPLICABLE) ARE DIAGRAMMATIC IN NATURE. THE ELECTRICAL CONTRACTOR SHALL BE THOROUGHLY FAMILIAR WITH THE PROJECT SCOPE OF WORK PRIOR TO SUBMITTING THEIR BID.
- THE ELECTRICAL CONTRACTOR SHALL VERIFY THE ELECTRICAL REQUIREMENTS OF ALL OWNER PROVIDED EQUIPMENT AND SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.
- ALL WORK SHOWN ON DRAWINGS IS NEW UNLESS OTHERWISE NOTED.
- ALL GROUNDING SHALL BE PER NEC AND LOCAL CODES.
- ALL ELECTRICAL CONSTRUCTION ON THE PROJECT SHALL CONFORM TO THE NEC AND ALL OTHER AUTHORITIES HAVING JURISDICTION. THE CONTRACTOR SHALL OBTAIN ALL PERMITS REQUIRED AND PAY ALL FEES.
- ALL WIRING SHALL BE FREE OF SHORTS AND GROUNDS. NO CIRCUIT WIRING SHALL BE LOADED BEYOND THE PERMITTED AMPACITIES ALLOWED BY THE NEC. ALL WIRE SIZES ARE FOR COPPER.
- CONTRACTOR SHALL FIELD VERIFY ALL CONDITIONS AND DIMENSIONS PRIOR TO SUBMITTING BID.
- ELECTRICAL CONTRACTOR SHALL PROVIDE ALL EQUIPMENT AND MATERIALS NECESSARY TO MAKE A COMPLETE AND WORKABLE JOB INCLUDING FINAL HOOK-UP OF ALL EQUIPMENT.
- FIRE STOP SHALL BE PROVIDED AT ALL LOCATIONS WHERE ELECTRICAL EQUIPMENT OR SYSTEMS PENETRATE FIRE RATED WALLS. SEE ARCHITECTURAL PLANS FOR RATED WALL LOCATIONS. CONTROL WIRING TO MECHANICAL EQUIPMENT IS NOT SHOWN ON THESE SHEETS.
- RISER AND ONE-LINE DIAGRAMS ARE MEANT TO SHOW ONLY VERTICAL AND ELECTRICAL RELATIONSHIPS AND THEREFORE MAY NOT INCLUDE ALL REQUIRED EQUIPMENT, DEVICES AND ACCESSORIES.
- EQUIPMENT INTERRUPTING CAPACITIES SPECIFIED IN THE CONTRACT DOCUMENTS ARE BASED UPON EQUIPMENT CHARACTERISTICS AND IMPEDANCES SHOWN ON THE DRAWINGS. IF ACTUAL INSTALLED EQUIPMENT DEVIATES FROM THESE CHARACTERISTICS OR HAS LOWER IMPEDANCES THE CONTRACTOR SHALL INCREASE THE INTERRUPTING CAPACITIES OF ALL ITEMS ON THE LOAD SIDE OF THE DEVIANT EQUIPMENT IN DIRECT PROPORTION TO THE CHANGED CHARACTERISTICS. INTERRUPTING CAPACITIES SHALL NOT BE REDUCED TO VALUES LESS THAN THOSE REQUIRED BY THE CONTRACT DOCUMENTS.
- EQUIPMENT SIZES ARE AS DESIGNED. CIRCUIT BREAKERS, CONDUIT, MOTOR STARTERS, DISCONNECT SWITCHES, PLUG-IN'S, ETC., SHALL BE ADJUSTED TO THE EQUIPMENT SUBMITTED AND APPROVED FOR INSTALLATION ON THIS PROJECT.
- REFER TO ARCHITECTURAL OR CIVIL DRAWINGS FOR SITE INFORMATION.
- LIGHT FIXTURE MOUNTING HEIGHTS ARE MEASURED BETWEEN THE FLOOR AND THE BOTTOM OF THE FIXTURE.



CONDUIT AND WIRING LEGEND	
_____	NEW
_____	EXISTING TO BE REMOVED
_____	EXISTING TO REMAIN
----- UE ----- UE	UNDERGROUND ELECTRICAL
----- UF ----- UF	UNDERGROUND FIBER OPTIC
----- UT ----- UT	UNDERGROUND TELEPHONE
----- UG ----- UG	UNDERGROUND GROUNDING
OE----- OE----- OE-----	OVERHEAD ELECTRICAL

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM

TEXAS REGISTERED ENGINEERING FIRM F-928

KHA PROJECT  
067783129

DATE  
OCTOBER 2023

SCALE: AS SHOWN

DESIGNED BY: CC

DRAWN BY: AH

CHECKED BY: SK

ELECTRICAL  
NOTES, SYMBOLS & ABBREVIATIONS

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
68




















THE LIFT STATION SHALL OPERATE PER THE SEQUENCE OF OPERATIONS AS NOTED ON THE CIVIL DRAWINGS AND SPECIFICATIONS. PLEASE NOTIFY THE ENGINEER IMMEDIATELY IF THERE ARE ANY DISCREPANCIES.



0 5' 10'

GRAPHIC SCALE (FEET)

- (1) INSTALL NEW 100A, 277/480V, 3 PHASE 4 WIRE ELECTRIC SERVICE. CONTRACTOR TO COORDINATE WITH GENERALES ELECTRIC COOPERATIVE, WWW.PEC.COOP (888) 554-4732. PROVIDE PULL STRING IN EACH CONDUIT. VERIFY EXACT LOCATION OF TRANSFORMER PRIOR TO INSTALLATION.
- (2) PROVIDE AND INSTALL #3/0 BARE COPPER GROUNDING RING. BOND EQUIPMENT RACKS, SCADA TOWER, AND GENERATOR SKID TO GROUNDING ELECTRODE SYSTEM VIA EXOTHERMIC WELD.
- (3) PROVIDE AND INSTALL PUMP CONTROL PANEL. REFER TO SHEET E5.0 & E5.1.
- (4) PROVIDE AND INSTALL GROUND RODS. REFER TO DETAIL 6/E4.0.
- (5) PROVIDE AND INSTALL EQUIPMENT RACK PER DETAILS 1/E4.1 & 2/E4.1.
- (6) PROVIDE AND INSTALL WET WELL JUNCTION BOX. REFER TO DETAIL 9/E4.0.
- (7) PROVIDE AND INSTALL POLE LIGHT. REFER TO DETAIL 3/E4.0.
- (8) PROVIDE AND INSTALL CONCRETE GENERATOR PAD FOR NEW STANDBY EMERGENCY GENERATOR. EXACT DIMENSIONS MAY VARY DEPENDING ON SELECTED MANUFACTURER.
- (9) REFER TO TRENCH SECTION DETAIL 1/E4.4 FOR CONSTRUCTION INFORMATION.
- (10) REFER TO ONCOR ELECTRIC CONDUIT ARRANGEMENT DETAILS ON SHEET E4.2.
- (11) REFER TO "CIRCUIT SCHEDULE" ON SHEET E3.0 FOR ADDITIONAL INFORMATION.
- (12) ELECTRICAL CONTRACTOR SHALL STUB OUT ELECTRICAL PRIMARY FEEDER 10' FROM SERVICE ENTRANCE TRANSFORMER. COORDINATE EXACT LOCATION AND CONNECTION WITH ELECTRICAL UTILITY AS REQUIRED.
- (13) REFER TO DUCTBANK SECTION DETAIL 2/E4.4 FOR CONSTRUCTION INFORMATION.
- (14) ELECTRICAL CONTRACTOR SHALL PROVIDE AND INSTALL 30A/2P/NF/N4XSS/600V DISCONNECT SWITCH TYPE SQUARE D OR EQUAL FOR ODOR CONTROL AND JIB CRANE AS REQUIRED. TYPICAL.
- (15) ELECTRICAL CONTRACTOR SHALL PROVIDE NEW ANTENNA TOWER, ROHN #25G AND CONCRETE BASE. USE 2" CONDUIT AND SWEEPING ELBOW TO RUN CABLE. SIZE TO BE BASED ON RADIO SYSTEM STUDY PROVIDED BY SCADA CONTRACTOR.
- (16) RTU, TOWER, ANTENNA AND COAX CABLE TO BE PROVIDED AND INSTALLED BY SCADA CONTRACTOR. ENCLOSURE, CONDUIT, AND WIRE PULLING BY ELECTRICAL CONTRACTOR. INSTALL CONDUITS AND WIRE AS REQUIRED PER CIRCUIT SCHEDULE.




**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
73

[illegible]

3950683



STEVE L. KANETZKY  
84696  
LICENSED  
PROFESSIONAL ENGINEER

10/18/11

KHA PROJECT 067783129	DATE OCTOBER 2023	SCALE: AS SHOWN	DESIGNED BY: CC	DRAWN BY: AH	CHECKED BY: SK
--------------------------	----------------------	-----------------	-----------------	--------------	----------------




Plotted By: Cameron Cutbirth Date: November 07, 2023 03:33:24pm File Path: K:\Projects\2023\3950623--Kimley-Horn--Edgewood Lift Station\01 Design Phase\ \_CAD\3950623--E30.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

CIRCUIT SCHEDULE					
TAG	CONDUIT	CONDUCTORS	FROM	TO	EQUIPMENT/FUNCTION
PF-100-01	2-4"C	PULL STRING	UTILITY	TRANSFORMER	POWER FEEDER
PF-100-02A	2"C	4#1	TRANSFORMER	SERVICE ENTRANCE DISCONNECT SWITCH	POWER FEEDER
PF-100-02B	2"C	PULL STRING	TRANSFORMER	SERVICE ENTRANCE DISCONNECT SWITCH	SPARE
PF-100-03	2"C	4#1, 1#6GND	SERVICE ENTRANCE DISCONNECT SWITCH	AUTOMATIC TRANSFER SWITCH	POWER FEEDER
PF-100-04	2"C	4#1, 1#6GND	AUTOMATIC TRANSFER SWITCH	PUMP CONTROL PANEL	POWER FEEDER
PF-101-01	1"C	2#12, 1#12GND	GENERATOR	PANEL LV	POWER FEEDER
PF-101-02	1"C	2#12, 1#12GND	GENERATOR	PANEL LV	POWER FEEDER
PF-102-01	2"C	4#1, 1#6GND	AUTOMATIC TRANSFER SWITCH	GENERATOR	POWER FEEDER
PF-102-02	2"C	PULL STRING	AUTOMATIC TRANSFER SWITCH	GENERATOR	SPARE
PF-103-01	1"C	5#6	SERVICE ENTRANCE DISCONNECT SWITCH	SURGE PROTECTION DEVICE	SURGE PROTECTION
PF-104-01	3/4"C	2#12, 1#12GND	POWER QUALITY METER	PANEL LV	POWER FEEDER
PF-200-01	1"C	3#10, 1#10GND	PUMP CONTROL PANEL	PUMP #1	POWER FEEDER
PF-200-02	1"C	3#10, 1#10GND	PUMP CONTROL PANEL	PUMP #2	POWER FEEDER
PF-200-03	2"C	PULL STRING	PUMP CONTROL PANEL	WET WELL J-BOX	SPARE
PF-300-01	1"C	2#8, 1#10GND	PUMP CONTROL PANEL	PANEL LV	POWER FEEDER
PF-300-02	3/4"C	4#10	PANEL LV	SURGE PROTECTION DEVICE	SURGE PROTECTION
PF-500-01	1"C	5#6	PUMP CONTROL PANEL	SURGE PROTECTION DEVICE	SURGE PROTECTION
PF-600-01	1"C	2#12, 1#12GND	PUMP CONTROL PANEL	SITE LIGHT	POWER FEEDER
PF-600-02	1"C	2#12, 1#12GND	PANEL LV	HOT BOX	POWER FEEDER
PF-600-03	1"C	2#10, 1#10GND	PANEL LV	JIB CRANE	POWER FEEDER
PF-600-04	1"C	2#10, 1#10GND	PANEL LV	ODOR CONTROL	POWER FEEDER
PF-600-05	3/4"C	2#12, 1#12GND	PANEL LV	RTU	POWER FEEDER
CC-101-01	1"C	8#14, 1#12 GND	GENERATOR	RTU	ALARMS/STATUS
CC-102-01	1"C	8#14	AUTOMATIC TRANSFER SWITCH	GENERATOR	CONTROLS CIRCUIT
CC-103-01	3/4"C	CT CONDUCTORS	AUTOMATIC TRANSFER SWITCH	POWER QUALITY METER	INSTRUMENTS
CC-103-02	1"C	1-CAT6	POWER QUALITY METER	SCADA RTU	COMMUNICATION
CC-200-01	1"C	8#14	PUMP CONTROL PANEL	PUMP OVER TEMP & SEAL FAIL	CONTROLS CIRCUIT
IC-200-01	1"C	STP CABLE AS REQUIRED	PUMP CONTROL PANEL	LEVEL TRANSDUCER	INSTRUMENTATION CIRCUIT
IC-200-02	1"C	10#14	PUMP CONTROL PANEL	WET WELL FLOATS	INSTRUMENTATION CIRCUIT
IC-200-03	2"C	COAX		SCADA ANTENNA	SCADA COMMUNICATION

LIGHTING FIXTURE SCHEDULE											
TYPE	MANUFACTURER	CATALOG NO.	LAMP			FIX. WATTS	VOLTS	MOUNTING	REMARKS		
			TYPE	LUMENS	COLOR TEMP						
A	LITHONIA	FEM L48 4000LM IMAFD MD MVOLT GZ10 40K 80CRI	LED	4,000	4000K	23.8	120	SURFACE	HIGH-EFFICIENCY LED. SUITABLE FOR WET, DAMP, AND/OR COLD LOCATIONS		
P	LITHONIA	CSX1 LED 60C 700 40K TFTM MVOLT RPA PER DDBXD	LED	16,710	4000K	134	120	POLE	LED FULL CUTOFF #RSA-16-4-C-DM19AS-FBC-VD-DDB (16" ROUND ALUMINUM POLE)		

PANEL LV													
AMPS: 60A PRIMARY MCB /70A SECONDARY MCB		PHASE: 1		MOUNTING: SURFACE									
VOLTAGE: 240/120V		WIRE: 3		MINIMUM AIC RATING: 10 KAIC									
LOCATION: LIFT STATION		BUSSING: COPPER											
FED FROM: 15 KVA XFMR		NEMA: 4X SS 316 STAINLESS STEEL											
CKT. NO.	SERVICE DESCRIPTION	WIRE	BKR	POLES	KVA	A	B	KVA	POLES	BKR	WIRE	SERVICE DESCRIPTION	CKT. NO.
1	RECEP TACLE	12	20	1	0.5	1.0		0.5	1	20	12	POLE LIGHT	2
3	LIGHTS	12	20	1	1.0		1.0	0.0	2	30	10	SPD	4
5	POWER QUALITY METER	12	20	1	0.5	0.5		0.0					6
7	RTU	12	20	1	0.5		1.5	1.0	1	20	10	GEN. BATT. CHARGER	8
9	HOT BOX	12	20	1	0.5	2.0		1.5	1	20	10	GEN. BLOCK HEATER	10
11	ODOR CONTROL	12	20	1	1.0		2.5	1.5	2	30	10	JIB CRANE	12
13	SPARE		20	1	0.0	1.5		1.5					14
15	SPARE		20	1	0.0		0.0	0.0	1	20		SPARE	16
17	SPARE		20	1	0.0	0.0		0.0	1	20		SPARE	18
19	SPARE		20	1	0.0		0.0	0.0	1	20		SPARE	20
21	SPARE		20	1	0.0	0.0		0.0	1	20		SPARE	22
23	SPARE		20	1	0.0		0.0	0.0	1	20		SPARE	24
PHASE LOAD IN KVA:						5.0	5.0						
PHASE LOAD IN AMPS:						42	42						
NOTE: EATON D MINI POWER-CENTER 15KVA/480-120-240V													

EDGEWOOD LOAD CALCULATION					
	UTILITY			GENERATOR	
	HP	AMPS	KVA	STARTING	STEP
MISC. LIGHTS, CONTROLS, MISC. 120V		31	15	N/A	1
MOTORS PUMP #1	9	11.7	9.7	FVNR	2
PUMP #2	9	11.7	9.7	FVNR	3
25% OF LARGEST MOTOR		3	2		
25% SPARE		14	9		
DESIGN KVA TOTAL			45		
DESIGN AMPS @ 277/480 VOLTS, 3 PHASE		71			
NOTE: THE ELECTRICAL SERVICE IS DESIGNED TO RUN TWO 9 HP PUMPS AND ALL MISC. LOADS.					
SHORT CIRCUIT CURRENT CALCULATION: ASSUMPTION: 1-75KVA PAD MOUNTED TRANSFORMER					
FULL LOAD AMPS: FLA=(1*75)/75KVA (75000)/(480*1.73) = 91A FLA					
INFINITE BUS SHORT CIRCUIT CURRENT CALCULATION:  ASSUMPTION: %Z=1.8 SCCR = (100 / %Z) * FLA (100/1.8) * 91 = 5,055 A					



1 LIFT STATION ONE-LINE DIAGRAM  
E3.0 SCALE: NTS

REFERENCE NOTES

- 1 PROVIDE AND INSTALL SPD, EATON SPD-200-480Y-3-P OR EQUAL IN A NEMA 4XSS STAINLESS STEEL ENCLOSURE. CONNECT TO LOAD SIDE.
- 2 PROVIDE AND INSTALL MAIN DISCONNECT SWITCH 100A/3P/100AF/N4XSS/600V/SN/SE SQUARE D OR EQUAL. USE BUSSMANN #FRS-R-100 OR EQUAL WITH FACTORY NEUTRAL KIT AND GROUND BAR.
- 3 PROVIDE AND INSTALL AUTOMATIC TRANSFER SWITCH, 100 AMP, 4 POLE, 600V, NEMA 4XSS ASCO OR EQUAL.
- 4 PROVIDE AND INSTALL STANDBY GENERATOR 40 KW, 277/480V, 3 PHASE, 4-WIRE.
- 5 PROVIDE AND INSTALL MINI POWER CENTER AS PANEL "LV", EATON OR EQUAL. REFER TO PANEL LV SCHEDULE THIS SHEET.
- 6 ALL ELECTRICAL EQUIPMENT ENCLOSURES SHALL BE NEMA 4XSS.
- 7 PROVIDE AND INSTALL SPD, EATON SPD-050-240S-3-P OR EQUAL IN A NEMA 4XSS ENCLOSURE. CONNECT TO LOAD SIDE.
- 8 PROVIDE AND INSTALL POWER QUALITY METER EATON 2280 OR EQUAL. REFER TO 2/E4.0 FOR ADDITIONAL INFORMATION.
- 9 PROVIDE AND INSTALL SPD, EATON SPD-100-480Y-3-P OR EQUAL IN A NEMA 4XSS ENCLOSURE. CONNECT TO LOAD SIDE.



S. Kanetzky  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

E3.0

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

3950623

STATE OF TEXAS  
STEVE L. KANETZKY  
84696  
LICENSED PROFESSIONAL ENGINEER  
7-11-18/13

KHA PROJECT 067783129

DATE OCTOBER 2023

SCALE: AS SHOWN

DESIGNED BY: CC

DRAWN BY: AH

CHECKED BY: SK


ELECTRICAL ONE-LINE AND SCHEDULES

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS


SHEET NUMBER  
74





Plotted By: Cameron Cutbirth Date: November 07, 2023 03:33:29pm File Path: K:\Projects\2023\3950623-Kimley-Horn-Edgewood Lift Station\01 Design Phase\CAD\3950623-E4.0.dwg  
This document, together with the concepts and designs presented herein, is an instrument of service. It is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



**9** **DETAIL - WET WELL JUNCTION BOX** ①  
E4.0 SCALE: NTS




**8** **DETAIL - GROUNDING SERVICE DISCONNECT**  
E4.0 SCALE: NTS




WHERE POSSIBLE RING TERMINALS SHALL BE USED. ONE OF THE ABOVE METHODS MUST BE USED ON ALL WIRE #8 AWG & SMALLER. THE SAME MUST ALSO BE USED ON LARGER WIRE UNLESS AN ALTERNATE METHOD IS SUBMITTED & APPROVED.

**7** **DETAIL - WIRE TERMINATION AND MARKING**  
E4.0 SCALE: NTS




\* INSTALL GROUND RODS AWAY FROM HEAVY TRAFFIC AREAS AND SIDEWALKS. COORDINATE EXACT LOCATION WITH CIVIL DRAWINGS.  
\*\* INSTALL 2'X2'X6\"/>


**6** **DETAIL - 3/4\"/>**




**5** **DETAIL - SURGE PROTECTION DEVICE (SPD)**  
E4.0 SCALE: NTS




**4** **DETAIL - BOLLARD** ②  
E4.0 SCALE: NTS



**3** **DETAIL - POLE MOUNTED LIGHTING FIXTURE**  
E4.0 SCALE: NTS



**2** **DETAIL - POWER QUALITY METER (PQM)**  
E4.0 SCALE: NTS



**1** **DETAIL - TYPICAL UNDERGROUND CONDUIT RUN**  
E4.0 SCALE: NTS



S. Kanetzky  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

## REFERENCE NOTES

- ① COORDINATE INSTALLATION OF WET WELL JUNCTION BOX WITH SITE CONDITIONS AND SHEET E2.0
- ② BOLLARD SHALL BE PAINTED YELLOW, TYPICAL.

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT	067783129
DATE	OCTOBER 2023
SCALE	AS SHOWN
DESIGNED BY:	CC
DRAWN BY:	AH
CHECKED BY:	SK

ELECTRICAL DETAILS

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
**75**

**E4.0**







TRENCH SPECIFICATIONS:			
Installation of conduit:			
1.	Minimum cover to be 30" from the top of primary conduit to sub-grade.		
2.	Bottom of trench shall be sanded to provide smooth, even support for conduits.		
3.	Sand to be placed directly around conduits for initial backfill.		
4.	There is to be a minimum of 12" separation between electrical conduits and all other utilities' conduits.		
5.	Warning tape to be a minimum of 12" above electrical conduits.		
6.	Concrete or flowable fill to be poured around all conduit crossings and 90-degree bends. On conduit bends of other angles, concrete or flowable fill may be required upon inspection.		
7.	Trench may be used jointly if adequate separation is provided. (See drawings 510-014, 510-022, 510-023, 510-024 and 510-025).		
8.	Conduit may be under pavement if a depth of 30" cover to sub-grade is maintained.		
9.	Trench may be on property if adequate depth is maintained. "Adequate depth" is defined as 30" below the lowest point between the edge of pavement and property line.		
Inspection schedule:			
1.	After primary conduit installation.		
2.	After initial backfill.		
3.	After secondary conduit installation.		
4.	After remainder of initial backfill and warning tape.		
5.	After secondary backfill (rock-free dirt).		
<b>Failure to receive inspection will require removal of the backfill to allow inspection.</b>			
<b>DEVELOPER/CONTRACTOR CONTRIBUTION:</b>			
1.	Payment to PEC for materials per the Line Extension Policy.		
2.	Trench.		
3.	Conduit:		
a.	3" conduit Schedule 40, conduit bends Schedule 80 with 3", 36" minimum radius and accessories.		
b.	4" conduit Schedule 40, conduit bends Schedule 80 with 4", 48" minimum radius and accessories.		
c.	Conduit for service will be sized as needed.		
d.	2" conduit for controls or temporary service only.		
e.	Conduit bends with a 24" radius may be used only for secondary.		
<b>NOTE: Contractor may be required to pull a mandrel, of diameter not less than 80% of the inside diameter of the conduit through all conduits, for inspection by a PEC representative.</b>			
4.	Conduit spacers.		
5.	Transformer pads.		
6.	Meter pedestal pads.		
7.	Underground secondary enclosures and extensions.		
8.	Ground rods and pads.		
9.	Polyester pulling tape (2,500-pound tensile strength) in all conduit. No knots to be tied in the mule tape. It must be a continuous run.		
10.	Sand for initial backfill.		
11.	Rock-free dirt over initial backfill.		
12.	1/2" to 3/4" gravel for the bottom of vaults and secondary enclosures.		
13.	Concrete or flowable fill where required. Flowable fill is NOT allowed as a substitute for concrete for PEC equipment pads. Flowable fill may be used as backfill in situations where trench setting may be an issue or anywhere that does not require structural strength. The 28-day compressive strength range when tested must be a minimum of 300-psi. Flowable fill is NOT a substitute for concrete except where explicitly listed in the Underground Installation Specifications.		
14.	Install meter socket when metering on building.		
15.	Furnish and install any gang-type meter sockets.		
16.	Primary enclosures and extensions (if applicable).		
17.	Meter sockets (PEC will provide pedestal-mounted sockets only).		
18.	Switchgear (if applicable).		
19.	Bollards, if deemed necessary by PEC to protect electrical equipment. Design must be approved by PEC prior to installation.		
<b>MEMBER'S RESPONSIBILITY:</b>			
Meter pedestals are approved by PEC. In situations where meter pedestals are used, the following conditions will apply:			
1.	Purchase and install circuit breaker in house. Circuit breakers are the bolt-in type. The box will accommodate 150 and 200 amp breakers. The breaker must have an interrupting capacity of 10,000 amps rated at 240 volts. GE Cat. No. TQD22 (amp needed) WL and Eaton Cutler-Hammer FDZ200 or equal (old Westinghouse # CAXZ200W).		
2.	Install insulated jumpers from bottom of meter socket to top of breakers.		
3.	Install galvanized rigid conduit, Schedule 40 PVC or an approved equal from pedestal pad to bottom of box.		
4.	Member will be responsible for the installation of underground cable from the meter pedestal to the house and the connections to the bottom of the circuit breakers. The underground cable drawn from the meter pedestal to the house shall be an approved type for underground installation (USE or UF type). Conductor size will be based on member load, location of meter and National Electrical Code size of conduit.		
<b>Refer to applicable drawings within these specifications.</b>			
<div style="display: flex; justify-content: space-between;"> <span>REV   B   DATE   07/09/2020   REVISION   ADD 2" CONDUIT AND FLOWABLE FILL NOTES</span> <span>BY   RWC   CHK   SSS   APR   MMG</span> </div>			

	<b>UNDERGROUND INSTALLATION SPECIFICATIONS</b>		<b>DEVELOPER/MEMBER/PEC SUPPLIED MATERIAL</b>	
			PAGE 1 OF 2	
	drawn:	approved:	date:	
	RWC	MMG	07/09/2020	500-100

<h3 style="margin: 0;">Typical for All Pads</h3>			
1.	Require 3" conduit (unless otherwise specified by PEC) with bell-end fittings to extend 1 1/2" to 2" above pad.		
2.	Pads must extend a minimum of 4" above final grade and 1 1/2" below final grade. All pads must be placed on a slope less than or equal to 3:1. If greater than 3:1, contractor must bring slope to required grade.		
3.	All disturbed soil underneath pad must be replaced by concrete.		
4.	All ground rods shall be 3/4" X 10' copper-clad with clamp and must extend 3" above top of pad.		
5.	Wood float finish leaving pad square and level with no dips or crown.		
6.	<b>Contact PEC before pouring concrete and comply with the following instructions:</b> <ul style="list-style-type: none"> <li>• Pre-pour inspection: Check framing and layout of pad and conduit components.</li> <li>• Final inspection: Overall review of pad and conduits. Ensure bell ends are on conduit.</li> </ul>		
<h3 style="margin: 0;">Typical for Single-Phase Transformer, Combination, Sectionalizer, and Secondary Pads</h3>			
7.	Concrete to have minimum strength of 3,000 PSI.		
8.	Steel reinforcing shall be 6" X 6" No. 10 wire mesh or 3/8" re-bar on 12" center to stop 1" from the sides.		
<h3 style="margin: 0;">Typical for Three-Phase Transformer Pads</h3>			
9.	Concrete testing, 4,000 PSI; 4%-6% entrained air, 3/4" maximum-size aggregate.		
10.	Steel reinforcement shall be 3/8" re-bar on 12" center to stop 1" from sides.		
11.	Minimum concrete cover over reinforcing steel 2" unless noted.		
<h3 style="margin: 0;">Typical Trench Details</h3>			
12.	Schedule 40 electrical-grade PVC conduit. Schedule 80 electrical-grade conduit can be used in place of sand in secondary-only trenches.		
13.	Initial backfill shall be manufactured or commercial sand. Minimum 3/8" pea gravel may be used for initial backfill in flood-prone areas.		
14.	With PEC approval, minimum cover requirements may be reduced by six inches with every two inches of 3,000 PSI concrete poured directly onto conduit. <b>*Contact PEC before pouring concrete.*</b>		
15.	If any type of vault or pedestal for the underground electric is planned, then all other utilities should be routed around these facilities.		
16.	For 2" and <b>smaller</b> waterlines, special permission must be granted by PEC. Water lines larger than 2" will not be allowed in PEC trench.		
17.	Refer to drawings 510-023 and 510-025 for PEC specifications and trench details on gas joint trench installations.		
<h3 style="margin: 0;">Conduit Legend</h3> <p style="margin: 0;">Typical in All Drawings</p>			
(P)	Primary Conduit	(S)	Secondary Conduit
(CW)	Communications or Water	(G)	Gas Line
(AS)	Alternate Secondary Conduit		
<h3 style="margin: 0;">Primary Phasing Legend</h3> <p style="margin: 0;">Phasing for three-phase primary applications: pad-mounted enclosures, combination pads, three-phase transformers, and three-phase risers.</p>			
(R)	Red = Phase A	(B)	Blue = Phase B
(Y)	Yellow = Phase C		
<div style="display: flex; justify-content: space-between; font-size: small;"> <span>REV   C   DATE   09/01/2023   REVISION   ADDED PRIMARY PHASING LEGEND</span> <span>BY   RWC   CHK   SSS   APR   MMG</span> </div>			


UNDERGROUND  
INSTALLATION  
SPECIFICATIONS

TYPICAL NOTES  
REFERENCE PAGE

drawn:	approved:	date:
RWC	MMG	09/01/2023

510-009

<b>MEMBER'S RESPONSIBILITY CONTINUED:</b>	
5.	Underground conductor from secondary enclosure/transformer to meter shall have 24" of cover. This depth may be reduced to 18" when a 2" supplemental protective covering of concrete or flowable fill is provided. If rigid conduit is used, the depth can be reduced by 6". Red electric warning tape is also required in the ditch.
6.	Apply and receive all applicable inspections.
7.	When all work is completed according to specifications, notify PEC you are ready for electric service. PEC will make the connect and set the meter on a routine connect order.
8.	For commercial and residential applications, the member shall supply the CT enclosure (if needed) and all secondary cable in accordance with the National Electrical Code.
<b>PEC CONTRIBUTION PAID FOR BY DEVELOPER/MEMBER AS INDICATED ON THE LINE EXTENSION POLICY:</b>	
1.	Primary conductors.
2.	Secondary conductors.
3.	Cable terminations.
4.	Transformers.
5.	Meter pedestals.
6.	Switchgear.
7.	Secondary GelPort connectors.
8.	Meter socket combo.
<b>PEC RESPONSIBILITY:</b>	
1.	Furnish and install meter pedestal.
2.	Furnish and install combination meter socket and breaker box.
3.	Install jumper wires from top of meter socket to pedestal connector and set meter on connect order after all work has been completed.
<b>Refer to applicable drawings within these specifications.</b>	
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="display: flex; align-items: center;"> <div style="border: 1px solid black; padding: 2px 5px;">REV/</div> <div style="border: 1px solid black; padding: 2px 5px;">B</div> <div style="border: 1px solid black; padding: 2px 5px;">DATE</div> <div style="border: 1px solid black; padding: 2px 5px;">07/09/2020</div> <div style="border: 1px solid black; padding: 2px 5px;">REVISION</div> <div style="border: 1px solid black; padding: 2px 5px;">ADD 2" CONDUIT AND FLOWABLE FILL NOTES</div> </div> <div style="display: flex; align-items: center;"> <div style="border: 1px solid black; padding: 2px 5px;">BY</div> <div style="border: 1px solid black; padding: 2px 5px;">RWC</div> <div style="border: 1px solid black; padding: 2px 5px;">CHK</div> <div style="border: 1px solid black; padding: 2px 5px;">SSS</div> <div style="border: 1px solid black; padding: 2px 5px;">APR</div> <div style="border: 1px solid black; padding: 2px 5px;">SSS</div> </div> </div>	



UNDERGROUND  
INSTALLATION  
SPECIFICATIONS

drawn:

RWC

approved:

MMG

date:


07/09/2020

500-100


Model Number # 1402-XR  
Stock # 80611161144


**NOTES:**

- 1) 3M Electronic Marking System Extended Range Ball Marker's are required at locations deemed necessary by PEC.
- 2) PEC inspector will deliver marker balls to developer's contractor for installation.
- 3) Ball markers must be tied to the conduit ends using the tie down tabs provided.
- 4) The XR Ball Marker cannot reliably re-radiate the locator's signal at a depth greater than 5 feet, this is the maximum allowable distance between ball marker and subgrade.
- 5) Hand fill at least 6 inches of soil over the marker to prevent movement or damage during backfill.

 <p>PEDERNALES ELECTRIC COOPERATIVE, INC.</p>		<p>3M Electronic Marking System Extended Range Ball Marker</p>	
drawn:	approved:	date:	drawing number:
DBS	MJB	July 18, 2016	580-010-0911

URD DEVELOPER'S SPECIFICATIONS




SHEET NUMBER <b>77</b>	<b>EDGEWOOD</b> <b>PHASE 2, SECTION 2</b> CITY OF LEANDER WILLIAMSON COUNTY, TEXAS	<b>ELECTRICAL DETAILS</b>	KHA PROJECT 067783129	 <p>3950623</p> <p>10/18/13</p>	<b>Kimley»Horn</b> © 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 <a href="http://WWW.KIMLEY-HORN.COM">WWW.KIMLEY-HORN.COM</a> TEXAS REGISTERED ENGINEERING FIRM F-928	No.	DATE	BY
			DATE OCTOBER 2023					
			SCALE: AS SHOWN					
			DESIGNED BY: CC					
			DRAWN BY: AH					
			CHECKED BY: SK					



**S. Kanetzky**  
**Engineering, LLC.**  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
[www.skaneng.com](http://www.skaneng.com)  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

## E4.2





1 SCADA CONTRACTOR SHALL DETERMINE THE FINAL HEIGHT AFTER CONDUCTING A LINE OF SITE STUDY.

[illegible]

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT 067783129	DATE OCTOBER 2023	SCALE: AS SHOWN	DESIGNED BY: CC	DRAWN BY: AH	CHECKED BY: SK
--------------------------	----------------------	-----------------	-----------------	--------------	----------------





**S. Kanetzky**  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

SHEET NUMBER





78

Plotted By: Cameron Cutbirth Date: November 07, 2023 03:33:52pm File Path: K:\Projects\2023\3950623-Kimley-Horn-Edgewood Lift Station\01 Design Phase\CAD\3950623-E4.4.dwg




This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



**2** **DETAIL - DUCTBANK SECTION CONSTRUCTION (TYPICAL)**  
E4.4 SCALE: NTS



**1** **DETAIL - TRENCH SECTION CONSTRUCTION (TYPICAL)**  
E4.4 SCALE: NTS



**SKE**

S. Kanetzky  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

**E4.4**

## REFERENCE NOTES

- ① REFER TO CIRCUIT SCHEDULE ON SHEET E3.0 FOR MORE INFORMATION.
- ② SEE DETAIL 2/E4.4 FOR DUCTBANK CONSTRUCTION DETAIL.
- ③ SEE DETAIL 1/E4.4 FOR TRENCH CONSTRUCTION DETAIL.

## GENERAL NOTE

1. IT IS THE ELECTRICAL CONTRACTORS RESPONSIBILITY TO PROVIDE AND INSTALL ALL RACEWAYS AND CONDUCTORS CUMULATIVELY BETWEEN THE DUCT BANK DETAILS, PANEL SCHEDULE, I/O SCHEDULE, AND CIRCUIT SCHEDULE. THE CIRCUIT SCHEDULE, I/O SCHEDULE AND PANEL SCHEDULES TAKE PRECEDENCE OVER THE DUCTBANK DETAILS.

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM

TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT	067783129
DATE	OCTOBER 2023
SCALE	AS SHOWN
DESIGNED BY:	CC
DRAWN BY:	AH
CHECKED BY:	SK

ELECTRICAL DETAILS


**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
**79**




Plotted By: Cameron Cutbirth Date: November 07, 2023 03:33:57pm File Path: K:\Projects\2023\3950623-Kimley-Horn-Edgewood Lift Station\01 Design Phase\CAD\3950623-E50.dwg

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



**2** PUMP CONTROL PANEL WIRING DIAGRAM **1 2 3**  
E5.0 SCALE: NTS



**1** PUMP CONTROL PANEL ENCLOSURE  
E5.0 SCALE: NTS

### REFERENCE NOTES

- PUMP CONTROL PANEL WIRING IS TYPICAL. FINAL HARDWARE CONFIGURATION WILL VARY ACCORDING TO PUMP CONTROL PANEL SPECIFICATIONS.
- DUPLEX PUMP CONTROL PANEL, 480V, 3 PHASE, UL805A LABELED. VERIFY EXACT PUMP SIZES AND SIZE CIRCUIT BREAKERS AND OVERLOADS ACCORDINGLY. THE PUMP CONTROL PANEL SHALL BE MANUFACTURED BY 5 STAR ELECTRIC, SAN ANTONIO, TEXAS 1(800) 229-8965, CONTROL PANELS USA, INC. (512) 863-3224) OR APPROVED EQUAL.
- PROVIDE AND INSTALL NEMA RATED CLASS 8536 STARTERS.



S. Kanetzky  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928




KHA PROJECT	067783129
DATE	OCTOBER 2023
SCALE	AS SHOWN
DESIGNED BY:	OC
DRAWN BY:	AH
CHECKED BY:	SK

PUMP CONTROL PANEL DETAILS

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
**80**

**E5.0**



## REFERENCE NOTES

2 PROVIDE STARTUP AND MINIMUM 4 HOURS TRAINING FOR OPERATOR PERSONNEL. SUBMIT STARTUP REPORT TO ENGINEER.

③ MOISTURE/OVER TEMPERATURE MONITOR RELAY SHALL BE INTEGRATED TO THE CONTROL LOGIC TO PROVIDE FAIL SAFE OPERATION. THUS, WHEN THE MOISTURE/OVER TEMPERATURE MONITOR RELAY IS REMOVED FROM THE CONTROL CIRCUIT OR FAILS, THE CORRESPONDING PUMP WILL BE LOCKED OUT.

4 ALL SEALED FLOAT SWITCHES SHALL BE CONNECTED TO THE CONTROL LOGIC VIA INTRINSICALLY SAFE RELAYS.

5 PROVIDE AND INSTALL RADAR SENSOR TYPE VEGAPULS 61 PS61.XXANPHKJXX.

6 PROVIDE AND INSTALL PRIMARY PUMP CONTROLLER TYPE SIEMENS HYDRORANGER 200.

### SEQUENCE OF OPERATION:

### LEVEL CONTROL OPERATION:

THE PUMP CONTROL PANEL SHALL UTILIZE ONE (1) LEVEL SENSOR TO CONTROL THE LEVEL IN THE WELL. ON SUMP LEVEL RISE TO 1ST PUMP TURN-ON LEVEL SETTING, THE CONTROLLER SHALL START THE 1ST PUMP. IF THE LEVEL CONTINUES TO RISE TO THE 2ND PUMP TURN-ON LEVEL SETTING, THE CONTROLLER SHALL START THE 2ND PUMP. SUMP LEVEL SHALL LOWER TO LOW LEVEL SETTING, THE CONTROLLER SHALL STOP THE 2ND PUMP. AN ALARM RELAY SHALL INDEX ON STOPPING OF PUMP. THAT 2ND PUMP WILL START ON NEXT OPERATION AND SO FORTHWARD. IF LEVEL CONTINUES TO RISE AND HIGH LEVEL SETTING IS REACHED, THE CONTROLLER SHALL TRIGGER THE HIGH LEVEL ALARM. ALARM SHALL BE MANUAL RESET. LEVELS SHALL BE SET AS INDICATED IN THE SPECIFICATIONS AND SHOWN ON THE CIVIL PLANS. AN AUTOMATIC BACKUP LEVEL FLOATS SYSTEM SHALL BE PROVIDED. IF ONE PUMP SHOULD FAIL FOR ANY REASON, THE OTHER PUMP SHALL TAKE OVER THE PUMPING. THE PUMPING CAPACITY OF THE PUMPS SHALL BE ADJUSTABLE FROM THE CONTROLLER SELECTABLE MENU/SCREEN, WITH THE PUMP OPERATING, THE SUMP FLUID LEVEL SHALL LOWER. WHEN THE LOW LEVEL TURN-OFF SETTING IS REACHED THE PUMP RUNNING WILL THEN CEASE TO OPERATE.

### AUTOMATIC BACKUP LEVEL FLOATS OPERATION:

WHEN THE RADAR SENSOR FAILS THE PUMP CONTROL PANEL SHALL AUTOMATICALLY OPERATE BY THE LEVEL FLOATS ACCORDING TO THE FOLLOWING ORDER.


ON SUMP LEVEL RISE, LOWER (OFF) FLOAT SWITCH SHALL FIRST BE ENERGIZED, WHEN THE LEVEL RISES FURTHER, THE 1ST PUMP (LEAD PUMP) LEVEL SWITCH SHALL NEXT ENERGIZE AND START 1ST PUMP. IF THE LEVEL CONTINUES TO RISE THE 2ND PUMP (LAG PUMP) LEVEL SWITCH SHALL NEXT ENERGIZE AND START THE 2ND PUMP WITH 1ST AND 2ND PUMPS OPERATING IN PARALLEL. WHEN THE LOWER (OFF) FLOAT SWITCH DEENERGIZES, BOTH PUMPS SHALL STOP. ALTERNATING RELAY SHALL INDEX ON STOPPING OF PUMP SO THAT 2ND PUMP WILL START ON NEXT OPERATION. IF LEVEL CONTINUES TO RISE, ALARM SWITCH SHALL ENERGIZE AND SIGNAL THE ALARM. IF ONE PUMP SHOULD FAIL FOR ANY REASON, THE SECOND PUMP WILL OPERATE AT THE OVERFLOW LEVEL. WHEN THE LEVEL RISES FURTHER, THE 3RD PUMP SHALL SIGNAL ALL LEVEL SWITCHES SHALL BE ADJUSTABLE FOR LEVEL TENDING FROM THE SURFACE. WITH THE PUMP OPERATING, THE SUMP FLUID LEVEL SHALL LOWER. WHEN THE LEVEL CAUSES THE LOWER (OFF) MERCURY FLOAT SWITCH TO TILT BACK TOWARD HANGING VERTICAL, ITS CONTACT SHALL OPEN CAUSING THE MOTOR CONTACTOR TO LOSE POWER TO THE PUMP MOTOR AND THE CIRCUIT TO THE PUMP MOTOR. THE PUMP OR PUMPS RUNNING WILL THEN CEASE TO OPERATE.

IF THE HIGH LEVEL FLOAT IS ACTIVATED ALL PUMPS SHALL BE CALLED TO RUN AT 100% FLOW CAPACITY.

PUMPS SHALL ALTERNATE TO MAINTAIN EQUAL RUN TIMES AND SHALL START WITH TIME DELAY TO ASSIST THE GENERATOR STARTING.




S. Kanetzky  
Engineering, LLC  
14425 Falcon Head Blvd  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623





Plotted By: Cameron Cutbirth Date: November 07, 2023 03:34:06pm File Path: K:\Projects\2023\3950623-Kimley-Horn-Edgewood Lift Station\01 Design Phase\CAD\3950623-E60.dwg

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




\* INDICATES FIELD WIRING  
REQUIRED BY CONTRACTOR

**2**  
E6.0


**RTU SCHEMATIC**  
SCALE: NTS

LIFT STATION I/O LIST				
ITEM	DESCRIPTION	TYP.	CONDUCTOR	REMARKS
1	UTILITY POWER STATUS	DI	2#14	
2	ATS IN EMERGENCY	DI	2#14	
3	GENERATOR FAIL	DI	2#14	
4	GENERATOR LOW FUEL	DI	2#14	
5	GENERATOR COMMON ALARM	DI	2#14	
6	PHASE MONITOR ALARM	DI	2#14	
7	WET WELL - HIGH LEVEL	DI	2#14	
8	WET WELL - LOW LEVEL	DI	2#14	
9	PUMP #1 RUN STATUS	DI	2#14	
10	PUMP #2 RUN STATUS	DI	2#14	
11	PUMP #1 HOA STATUS	DI	2#14	
12	PUMP #2 HOA STATUS	DI	2#14	
13	PUMP #1 OVER TEMP	DI	2#14	
14	PUMP #1 SEAL FAIL	DI	2#14	
15	PUMP #2 OVER TEMP	DI	2#14	
16	PUMP #2 SEAL FAIL	DI	2#14	
17	SPARE	DI		
18	SPARE	DI		
19	SPARE	DI		
20	SPARE	DI		
21	RADAR LEVEL SENSOR	AI	1#18TSP	
22	SPARE	AI		
23	SPARE	AI		
24	SPARE	AI		
25	SPARE	AI		
26	SPARE	AI		
27	POWER QUALITY METER	E	1-CAT6	



**1**  
E6.0

**SCADA RTU ENCLOSURE**  
SCALE: NTS



## REFERENCE NOTES

- RTU PANEL SCHEMATIC AND WIRING DIAGRAM IS TYPICAL IN NATURE. FINAL HARDWARE CONFIGURATION MAY VARY.
- PROVIDE FACTORY AUTHORIZED STARTUP AND MINIMUM 4 HOURS TRAINING FOR OPERATOR PERSONNEL.
- THE LIFT STATION SCADA SYSTEM SHALL OPERATE PER THE SEQUENCE OF OPERATIONS PROVIDED BY THE CIVIL ENGINEER.
- ALL CONDUITS AND WIRING PROVIDED, INSTALLED BY THE ELECTRICAL CONTRACTOR AND TERMINATED BY THE SCADA CONTRACTOR.
- ELECTRICAL CONTRACTOR MAY GROUP WIRES WITH SAME VOLTAGE FOR FIELD DEVICES IN CONDUIT AS HE DEEMS BEST APPROPRIATE.
- ANALOG AND LOW VOLTAGE SIGNALS SHALL NOT BE RUN IN SAME CONDUIT AS 120VAC AND 480VAC CIRCUITS.
- QUANTITY OF CONDUCTORS SHOWN ARE FOR REFERENCE ONLY. VERIFY EXACT WIRING REQUIREMENTS TO FIELD DEVICES PER INFORMATION PROVIDED BY THE EQUIPMENT VENDOR PRIOR TO INSTALLATION.
- USE SHIELDED TWISTED PAIR (STP) CABLE BELDEN #5341FE OR EQUAL.
- PROVIDE AND INSTALL SCHNEIDER ELECTRIC APC DIN RAIL - PANEL MOUNTED UPS WITH STANDARD BATTERY 500VA 120V TYPE SUA500PDR-S.
- PROVIDE AND INSTALL ALLEN BRADLEY MICROLOGIX 1400 PLC WITH I/O AS SHOWN ON SCHEDULE THIS SHEET.



S. Kanetzky  
Engineering, LLC.  
14425 Falcon Head Blvd.  
Building B, Suite 100  
Bee Cave, Texas 78738  
(512) 326-3380  
www.skaneng.com  
TBPE Firm No. F-2356  
SKE PROJECT # 3950623

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928



KHA PROJECT	067783129
DATE	OCTOBER 2023
SCALE	AS SHOWN
DESIGNED BY:	OC
DRAWN BY:	AH
CHECKED BY:	SK

ELECTRICAL SCADA

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
82

E6.0







Plotted By:Florides, George    Date:November 19, 2023 12:56:45pm    File Path:k:\WPB\_Civil\_Structures\Texas -- North Austin Office\Edgewood US\CAD\PlanSheets\SPECIAL INSPECTIONS.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

SPECIAL INSPECTIONS

- SI-1

THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE (RDP/RC) FOR THIS PROJECT IS THE ARCHITECT. SUBMIT ALL INSPECTION REPORTS DIRECTLY TO THE RDP/RC FOR REVIEW. ALSO, SUBMIT THE STRUCTURALLY RELATED INSPECTION REPORTS TO THE STRUCTURAL ENGINEER FOR SPECIAL REVIEW.
- SI-2

THE RDP/RC CONTRACTS WITH OR IS EMPLOYED BY THE OWNER. IN ORDER TO COMPLY WITH THE CODE REQUIREMENTS, THE RDP/RC AND THE SPECIAL INSPECTORS AND TESTING TECHNICIANS MAY NOT BE IN THE EMPLOY OF THE GENERAL CONTRACTOR (GC), SUB-CONTRACTORS OR MATERIAL SUPPLIERS. IN THE CASE OF AN OWNER / CONTRACTOR, THE BUILDING OFFICIAL SHALL SPECIFY WHO EMPLOYS THE RDP/RC, SPECIAL INSPECTORS AND TESTING TECHNICIANS.
- SI-3

THESE INSPECTIONS LISTED BELOW ARE IN ADDITION TO THE INSPECTIONS SPECIFIED IN SECTION 110 OF THE IBC. REFER TO THE BUILDING CODE, AND ANY AMENDMENTS TO THE BUILDING CODE FOR THIS JURISDICTION, TO DETERMINE ALL THE REQUIRED INSPECTIONS IN ADDITION TO THE SPECIAL INSPECTIONS LISTED BELOW.
- SI-4

INSPECTION OF FABRICATORS - FABRICATOR SHALL SUBMIT TO THE RDP/RC, WITH A COPY TO THE OWNER AND THE GC, A CERTIFICATE OF COMPLIANCE STATING THAT HE FABRICATED HIS WORK UNDER THE INSPECTIONS SERVICES OF A SPECIAL INSPECTOR OR UNDER THE INSPECTION SERVICES OF A NATIONALLY RECOGNIZED TRADE ORGANIZATION THAT REQUIRES QUALITY CONTROL INSPECTION. THE FOLLOWING SPECIAL INSPECTIONS IN TABLE FORM ARE REQUIRED ONLY IF MARKED BY A "X", "C" OR "P".  
X - DENOTES THAT THE INSPECTION IS REQUIRED, ONE TIME OCCURRENCE.  
C - DENOTES THAT THE INSPECTION IS REQUIRED AND SHALL BE CONTINUOUS.  
P - DENOTES THAT THE INSPECTION IS REQUIRED AND SHALL BE PERIODIC.  
R - DENOTES THAT INSPECTION/TESTING IS REQUIRED AND SHALL BE PERFORMED WITH APPLICABLE STANDARDS.  
" \_\_\_\_ " - OBSERVE OR PERFORM IN ACCORDANCE WITH APPLICABLE STANDARDS.  
N/A - DENOTES THAT THE SECTION IS NOT APPLICABLE.

VERIFICATION AND INSPECTION	REFERENCED STANDARD	CHECK IF REQ'D	CONT./ PERIODIC "C" OR "P"	RDP "A" OR "E"
CONSTRUCTION MATERIALS AND SYSTEMS THAT ARE ALTERNATIVES TO MATERIALS AND SYSTEMS PRESCIBED BY THE IBC	_____	X	P	E
UNUSUAL DESIGN APPLICATIONS OF MATERIALS DESCRIBED IN THIS CODE	_____	X	P	E
MATERIALS AND SYSTEMS REQUIRED TO BE INSTALLED IN ACCORDANCE WITH ADDITIONAL MANUFACTURER'S INSTRUCTIONS THAT PRESCRIBE REQUIREMENTS NOT CONTAINED IN THE IBC OR IN STANDARDS REFERENCED BY THE IBC	_____	X	P	E

SI-6

OPEN WEB STEEL JOISTS & JOIST GIRDERS (PER IBC 2018 TABLE 1705.2.3) DOES NOT APPLY TO THIS PROJECT.

SI-7

STEEL CONSTRUCTION - SECTION 1705.2 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-8

CONCRETE CONSTRUCTION (PER IBC TABLE 1705.3) SHALL APPLY AS FOLLOWS:

VERIFICATION AND INSPECTION	REFERENCED STANDARD	CHECK IF REQ'D	CONT./ PERIODIC "C" OR "P"	RDP "A" OR "E"
INSPECT REINFORCEMENT, INCLUDING PRESTRESSING TENDONS, AND VERIFY PLACEMENT	ACI 318 CH. 20, 25.2, 25.3, 26.6 & 26.8.3	X	P	E
REINFORCING BAR WELDING: A. VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706;	AWS D1.4; ACI 318: 26.6.4	N/A	P	E
B. INSPECT SINGLE-PASS FILLET WELDS, MAXIMUM 5/16" AND	AWS D1.4; ACI 318: 26.6.4	N/A	P	E
C. INSPECT ALL OTHER WELDS.	AWS D1.4; ACI 318: 26.6.4	N/A	C	E
INSPECT ANCHORS CAST IN CONCRETE	ACI 318: 17.8.2	X	P	E
INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS: A. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS	ACI 318: 17.8.2.4	X	C	E
B. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 11.A	ACI 318: 17.8.2	X	P	E
VERIFY USE OF REQUIRED DESIGN MIX	ACI 318: CH. 19, 26.4.3, 1904.2 IBC 1904.1, 1904.2	X	P	E
PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TEST, AND DETERMINE THE TEMPERATURE OF THE CONCRETE	ASTM C172; ASTM C31; ACI 318: 26.5, 26.12	X	C	E
INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES	ACI 318: 26.5	X	C	E
VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES	ACI 318: 26.5.3-26.5.5	X	P	E
INSPECT PRE-STRESSED CONCRETE FOR: A. APPLICATION OF PRE-STRESSING FORCES; AND	ACI 318: 26.10	N/A	C	
B. GROUTING OF BONDED PRE-STRESSING TENDONS	ACI 318: 26.10	X	C	E
INSPECT ERECTION OF PRECASE CONCRETE MEMBERS	ACI 318: CH. 26.9	X	P	E
VERIFY IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS	ACI 318: 26.11.2	N/A	P	
INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED	ACI 318: 26.11.1.2(b)	X	P	E
NOTE EXCEPTIONS 1, 2, 3, 4, AND 5 IN SECTION 1705.3 DISCUSSING FOOTINGS FOR BUILDINGS THREE STORIES OR LESS, NONSTRUCTURAL SLABS, FOUNDATIONS AND CERTAIN EXTERIOR CONCRETE FEATURES WHEN PLACED ON GRADE. CHECK HERE IF SPECIAL INSPECTION FOR CONCRETE NOT REQUIRED DUE TO EXCEPTIONS. CONCRETE NOTE : SPECIFY REQUIREMENTS FOR SPECIAL INSPECTION SHALL BE INCLUDED IN THE RESEARCH REPORT FOR THE ANCHOR ISSUED BY AN APPROVED SOURCE IN ACCORDANCE WITH 17.8.2 IN ACI 318, OR OTHER QUALIFICATION PROCEDURES. WHERE SPECIFIC REQUIREMENTS ARE NOT PROVIDED, SPECIAL INSPECTION REQUIREMENTS SHALL BE SPECIFIED BY THE REGISTERED DESIGN PROFESSIONAL AND SHALL BE APPROVED BY THE BUILDING OFFICIAL PRIOR TO THE COMMENCEMENT OF THE WORK.		NOT REQ'D	-	-

SI-9

MASONRY CONSTRUCTION - SECTION 1705.4 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-10

WOOD CONSTRUCTION - SECTION 1705.5 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).
- SI-11    SOILS (PER IBC TABLE 1705.6) SHALL APPLY AS FOLLOWS:
- | VERIFICATION AND INSPECTION  | REFERENCED STANDARD | CHECK IF REQ'D | CONT./ PERIODIC "C" OR "P" | RDP "A" OR "E" |
|--|---------------------|----------------|----------------------------|----------------|
| SOILS - SECTION 1705.6   |                     |                |                            |                |
| VERIFY MATERIALS BELOW SHALLOW FOUNDATION ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY  | -----               | X              | P                          |                |
| VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL   | -----               | X              | P                          |                |
| PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS   | -----               | X              | P                          |                |
| DURING FILL PLACEMENT, VERIFY USE OF PROPER MATERIALS AND PROCEDURES IN ACCORDANCE WITH THE PROVISIONS OF THE APPROVED GEOTECHNICAL REPORT. VERIFY DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL. | -----               | X              | C                          |                |
| PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY   | -----               | X              | P                          |                |
- SI-12

DRIVEN DEEP FOUNDATIONS - SECTION 1705.7 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-13

CAST IN PLACE DEEP FOUNDATIONS - SECTION 1705.8 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-14

HELICAL PILE FOUNDATIONS - SECTION 1705.9 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-15

STRUCTURAL INTEGRITY OF DEEP FOUNDATION ELEMENTS - SECTION 1705.10 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-16

FABRICATED ITEMS - SECTION 1705.11 SHALL OBTAIN APPROVAL BY DESIGN PROFESSIONAL AND BUILDING OFFICIAL WITH RESPECT TO INSPECTION REQUIREMENTS PRIOR TO FABRICATION FOR THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-17

SPECIAL INSPECTIONS FOR WIND RESISTANCE - SECTION 1705.12 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-18

SPECIAL INSPECTIONS FOR WIND RESISTANCE - SECTION 1705.13 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-19

SPECIAL INSPECTIONS FOR WIND RESISTANCE - SECTION 1705.14 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-20

SPECIAL INSPECTIONS FOR WIND RESISTANCE - SECTION 1705.15 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-21

MASTIC AND IN TUMESCENT FIRE-RESISTANT COATING - SECTION 1705.16 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-22

EXTERIOR INSULATION AND FINISH SYSTEMS (EIFS)- SECTION 1705.17 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-23

FIRE RESISTANCE JOINT PENETRATIONS AND JOINTS - SECTION 1705.18 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-24

TESTING FOR SMOKE CONTROL - SECTION 1705.19 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).

SI-25

SEALING OF MASS TIMBER - SECTION 1705.20 DOES NOT APPLY TO THIS PORTION OF THE PROJECT (SHEETS S-001 TO S-201).
- PERMIT SUBMITTAL
- EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
84

11/20/2023

KHA PROJECT  
067783129

DATE  
NOVEMBER 2023

SCALE: AS SHOWN

DESIGNED BY: GNH

DRAWN BY: ALB

CHECKED BY: JCL

SPECIAL INSPECTIONS

REVISIONS


NO.

DATE

BY

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

Plotted By:Florides, George Date:November 19, 2023 12:58:25pm File Path:K:\WPB\_Civil\_Structures\Texas -- North Austin Office\Edgewood US\CAD Plans\Sheets\STRUCTURAL SITE PLAN.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



2  
85  
STRUCTURAL SITE PLAN  
1" = 4'


PERMIT SUBMITTAL

SHEET NUMBER	85	EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS	STRUCTURAL SITE PLAN	KHA PROJECT 067783129	DATE NOVEMBER 2023	SCALE: AS SHOWN	DESIGNED BY: GNH	DRAWN BY: ALB	CHECKED BY: JCL	11/20/2023		© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928		REVISIONS		BY
														No.	DATE	





Plotted By:Florides, George Date:November 19, 2023 12:59:36pm File Path:K:\WPB\_Civil Structures\Texas -- North Austin Office\Edgewood LSCAD Plans\Sheets\S-201 LIFT STATION AND VAULT PLAN.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



1  
86 ENLARGED LIFT STATION AND VAULT PLAN  
1/2" = 1'

PERMIT SUBMITTAL

EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS	LIFT STATION AND VAULT PLAN		 11/20/2023	 © 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928	No.	REVISIONS	DATE	BY
	SHEET NUMBER	86						

Plotted By:Florides, George Date:November 19, 2023 01:01:02pm File Path:K:\WEB- Civil Structures\Texas -- North Austin Office\Edgewood US\CAD\PlanSheets\LIFT STATION AND VAULT\_SECTION.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

WET WELL NOTES:


- WET WELL STRUCTURE SHALL BE PRECAST CONSTRUCTION. THE FOLLOWING ARE THE REQUIREMENTS:
  - ALL PRECAST ELEMENTS SHALL BE SUBMITTED WITH FULL DESIGN CALCULATIONS AND REINFORCEMENT DETAILS PREPARED BY THE PRECAST MANUFACTURER. ALL PRECAST ELEMENTS SHALL BE DESIGNED BY A REGISTERED/LICENSED ENGINEER IN THE STATE OF TEXAS AND IN ACCORDANCE WITH THE REQUIREMENTS OF ASTM 478 - "STANDARD SPECIFICATION FOR CIRCULAR PRECAST REINFORCED CONCRETE MANHOLE SECTIONS." ALL JOINTS AND CONNECTIONS SHALL BE WATER TIGHT AND RECEIVE WATERSTOPS (CETCO RX101 OR APPROVED EQUAL) AS REQUIRED TO RETAIN WATER IN WET WELL WITHOUT LEAKING UNDER PRESSURE.
- WET WELL STRUCTURE SHALL BE ABLE TO WITHSTAND THE FOLLOWING LOAD CONDITIONS:
  - NO SOIL MATERIAL ON THE EXTERIOR OF THE WET WELL (FULLY EXCAVATED) WHILE BEING FULL OF LIQUID TO TOP ON THE INTERIOR OF THE WET WELL.
  - FULLY COMPACTED SOIL FULLY SATURATED TO THE SURFACE ON THE EXTERIOR OF THE WET WELL WHILE THE WET WELL INTERIOR IS EMPTY AND FREE OF LIQUID FOR FULL HEIGHT OF THE WET WELL. A PERIMETER RING AT BASE FOUNDATION WILL BE REQUIRED TO PREVENT SLIDING. AT TOP SLAB AN EXPANSION JOINT WILL BE REQUIRED TO SEPARATE TOP/LID FROM CAST-IN-PLACE SLAB.
  - BUOYANCY OF STRUCTURE EMPTY. WITH WATER ON EXTERIOR IN SOIL TO THE SURFACE OF GROUND.

TEMPORARY EARTHWORK SHORING WALLS:

- CONTRACTOR SHALL SUBMIT, IN THE FORM OF A SHOP DRAWING, THE DESIGN AND LAYOUT OF ANY TEMPORARY SHEET PILE WALLS, EARTHWORK SHORING OR EXCAVATION PLAN REQUIRED FOR CONSTRUCTION. SUBMITTED DOCUMENTS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF TEXAS RETAINED BY CONTRACTOR AND MEET ALL LOCAL, STATE AND FEDERAL CODES, INCLUDING OSHA.

DEWATERING:

- CONTRACTOR SHALL DEVELOP A DE-WATERING PLAN AND FULLY DESIGN AND PERMIT (WITH APPROPRIATE AGENCIES) AS REQUIRED FOR CONSTRUCTION AT A MINIMUM PLAN SHALL FOLLOW THE SEQUENCE DEFINED IN NOTES 2 AND 3 THIS SECTION.
- GROUNDWATER LEVELS BY WAY OF DE-WATERING SHALL BE MAINTAINED AT LEAST 2'-0" BELOW THE BASE OF EXCAVATION FOR FOUNDATION CONSTRUCTION OR PER GEOTECH REPORT (WHICH EVER IS DEEPER) FOR CONSTRUCTION OF ALL ELEMENTS.
- AT CONTRACTORS DISCRETION, CONTRACTOR MAY DE-WATER TO 2'-0" BELOW THE BASE OF EXCAVATION FOR FOUNDATION CONSTRUCTION AND SUSTAIN AT THIS LEVEL FOR THE FULL DURATION OF CONSTRUCTION UNTIL BACKFILL IS COMPLETE.



1 LIFT STATION AND VAULT SECTION  
3/8" = 1'-0"


NOTE:  
ELEVATIONS SHOWN ARE RELATIVE AND FOR REFERENCE ONLY. COORDINATE  
ACTUAL ELEVATIONS FOR TOP SLAB AT SURFACE WITH CIVIL DRAWINGS.

PERMIT SUBMITTAL

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

11/20/2023



KHA PROJECT 067783129  
DATE NOVEMBER 2023  
SCALE: AS SHOWN  
DESIGNED BY: GNH  
DRAWN BY: ALB  
CHECKED BY: JCL

LIFT STATION AND VAULT  
SECTION

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER

87

REVISIONS

No.

DATE

BY



Plotted By:Florides, George Date:November 19, 2023 01:01:56pm File Path:K:\WEB-Civil Structures\Texas - North Austin Office\Edgewood US CAD\PlanSheets\LIFT STATION AND VAULT BACKFILL AND LEAK TEST SECTION.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

BACKFILL NOTES:

ZONE 1

- IN THIS ZONE, BACKFILL AND COMPACT WITH SELECT FILL (CRUSHED LIMESTONE DERIVATIVE) WITHIN THE FIRST 5 FEET OF THE FARTHEST VERTICAL FACE OF THE STRUCTURE INCLUDING UNDER ALL MAT FOUNDATIONS.
- ALL SELECT FILL SHALL BE PLACED IN 6 INCH LIFTS (MAX.). FILL SHALL BE PLACED AROUND THE ENTIRE STRUCTURE IN UNIFORM LIFTS WITHOUT CREATING A VERTICAL DIFFERENTIAL OF THE SELECT FILL ALONG THE PERIMETER OF THE STRUCTURE AND FROM ONE SIDE OF STRUCTURE TO THE OTHER OF MORE THAN 2 FEET.
- OUTWARD OF 5 FEET (HORIZONTAL) OF THE EXTREME VERTICAL FACE OF THE OUTER WALL FOOTPRINT STRUCTURE, THE SELECT FILL MAY TRANSITION TO A SUITABLE AND APPROVED ONSITE BACKFILL MATERIAL (SEE ZONE 2 NOTES BELOW). ALL SUITABLE BACKFILL SHALL BE PLACED IN 6" LIFTS MAX BUT SHALL NOT ENCR OACH INTO THE 5 FOOT BOUNDARY FOR THE SELECT FILL. (ALL SELECT FILL BACKFILL SHALL BE COMPACTED AT A MIN. 95% ±2% STANDARD PROCTOR).
- DO NOT BACKFILL IN ZONE 1 WITH SELECT FILL UNTIL THE WALL STRUCTURE'S CONCRETE HAS REACHED DESIGN STRENGTH AND 10-DAYS. COORDINATE BACKFILL OPERATIONS WITH EXTERIOR COATING CURING. MINIMIZE LIFT HEIGHTS PER NOTE 2 ABOVE.

ZONE 2

- IN THIS ZONE, BACKFILL AND COMPACT WITH APPROVED ON-SITE SOIL.
- ALL APPROVED ON-SITE SOIL BACKFILL SHALL BE PLACED IN 6 INCH MAX LIFTS MAX AND SHALL BE PLACED IN UNIFORM LIFTS WITHOUT CREATING A VERTICAL DIFFERENTIAL IN BACKFILL ALONG THE PERIMETER OF THE STRUCTURE AND FROM ONE SIRE OF THE STRUCTURE TO THE OTHER OF MORE THAN 2 FEET. (ALL ON-SITE SOIL BACKFILL SHALL BE COMPACTED AT A MIN. 95% WITHIN -1 TO 3% OF OPTIMUM STANDARD PROCTOR).
- COMPACTION WITHIN 5 FEET OF THE STRUCTURAL WALLS SHALL BE ACCOMPLISHED USING HAND OR PLATE COMPACTION IN 6 INCH LIFTS.

LEAK TEST NOTES:

CONTRACTOR SHALL CONDUCT A LEAK TEST AS FOLLOWS DURING CONSTRUCTION OF THE WET WELL.

- L-1 WHILE STRUCTURE IS FULLY EXPOSED ON ALL VERTICAL SURFACES AND COMPLETELY INSTALLED BUT BEFORE COATINGS AND BACKFILLING HAS OCCURRED CONTRACTOR SHALL FILL WET WELL AND ALLOW TO SIT FOR TWELVE HOURS TO STABILIZED. ONCE STABILIZED START TEST AND CONDUCT FOR 12 HOURS. WATER LEVEL SHALL BE MARKED AT START OF TEST AND WITHOUT ADDING MORE WATER. AFTER TEST HAS STARTED THE WATER LEVEL SHALL BE RECORDED FOR TWELVE HOURS. EVERY TWO HOURS, CHECK EXTERIOR OF WET WELL AND ALL JOINTS FOR LEAKS. CONFIRM AMOUNT OF WATER LEVEL DROP, IF ANY. CHECK WATER LEVEL TO ENSURE IT HAS NOT LOWERED DURING THE TEST.
- L-2 ONCE STRUCTURE EXTERIOR HAS RECEIVED BACKFILL AND BEEN FULLY COMPACTED CONTRACTOR SHALL FILL WET WELL TO TOP OF WET WELL AND HOLD FOR TWO HOURS AFTER LEVEL HAS STABILIZED FOR 12 HOURS. WATER LEVEL SHALL BE MARKED AT START OF TEST AND WITHOUT ADDING MORE WATER AFTER TEST HAS STARTED THE WATER LEVEL SHALL BE RECORDED FOR TWELVE HOURS. EVERY TWO HOURS, CHECK EXTERIOR OF WET WELL AND ALL JOINTS FOR LEAKS. CONFIRM AMOUNT OF WATER LEVEL DROP, IF ANY. CHECK WATER LEVEL TO ENSURE IT HAS NOT LOWERED DURING THE TEST. SEE MECHANICAL SHEETS FOR WATER LEVEL PASS/FAIL CRITERIA.
- L-3 ONCE ALL BACKFILL HAS REACHED FINISHED GRADE AND BEEN FULLY COMPACTED CONTRACTOR SHALL FILL WET WELL TO TOP OF WET WELL CONDUCT THE OFFICIAL EXFILTRATION TEST AS SPECIFICALLY IDENTIFIED ON THE MECHANICAL PLANS.

1 BACKFILL AND LEAK TEST SECTION  
88 3/8" = 1'-0"

NOTE:  
ELEVATIONS SHOWN ARE RELATIVE AND FOR REFERENCE ONLY. COORDINATE ACTUAL ELEVATIONS FOR TOP SLAB AT SURFACE WITH CIVIL DRAWINGS.


PERMIT SUBMITTAL

KHA PROJECT 067783129		DATE NOVEMBER 2023		SCALE: AS SHOWN		DESIGNED BY: GNH		DRAWN BY: ALB		CHECKED BY: JCL	
<div>Kimley»Horn</div> <div>© 2023 KIMLEY-HORN AND ASSOCIATES, INC. 501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626 PHONE: 512-520-0768 FAX: 512-418-1791 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928</div> <div>11/20/2023</div> <div><div>STATE OF TEXAS</div><div>Professional Engineer</div><div>Don Casey Long</div><div>94119</div></div>											
LIFT STATION AND VAULT BACKFILL AND LEAK TEST SECTION											
EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS											
SHEET NUMBER 88											
REVISIONS										DATE	BY
										No.	




Plotted By:Florides, George Date:November 19, 2023 01:03:02pm File Path:K:\WPB\_Civil Structures\Texas -- North Austin Office\Edgewood LSCAD Plans\Sheets\LIFT STATION AND VAULT SECTIONS AND DETAILS.dwg


This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




1 LIFT STATION WALL / FOUNDATION CONNECTION  
89 N.T.S.



4 PIPE PENETRATION DETAIL  
89 N.T.S.




2 VAULT TOP OF WALL DETAIL  
89 N.T.S.




5 LINK-SEAL DETAIL  
89 N.T.S.

- LINK-SEAL NOTES:
1. INSIDE DIAMETER OF EACH WALL OPENING SHALL BE OF THE SIZE RECOMMENDED BY MANUFACTURER TO FIT THE PIPE OR CONDUIT AND THE LINK-SEAL WALL SEAL ASSEMBLY TO ASSURE WATER-TIGHT JOINT.
  2. PIPE TO WALL PENETRATION CLOSURES SHALL BE OF THE MODULAR MECHANICAL TYPE, CONSISTING OF INTERLOCKING SYNTHETIC RUBBER LINKS SHAPED TO FILL THE ANNULAR SPACE BETWEEN THE PIPE AND WALL OPENING. A PRESSURE PLATE SHALL BE PROVIDED UNDER EACH BOLT HEAD AND NUT, WITH THE SEAL CONSTRUCTED TO PROVIDE ELECTRICAL INSULATION BETWEEN PIPE AND WALL.
  3. WALL SEAL ASSEMBLY SHALL BE "LINK SEAL" AS MFG. BY THUNDERLINE CORP., WAYNE, MICHIGAN OR EQUAL.
  4. PROVIDE ESCUTCHEONS IN FINISHED SPACES.
  5. CONTRACTOR SHALL COORDINATE ALL MATERIAL TYPES, MATERIAL COMPATIBILITY, SIZES, GAPS, AND CONNECTIONS WITH LINK-SEAL MANUFACTURER TO ENSURE A WATER TIGHT CONNECTION.



3 VAULT WALL / FOUNDATION CONNECTION  
89 N.T.S.




6 TYPICAL WALL CORNER REINFORCEMENT DETAIL  
89 N.T.S.

PERMIT SUBMITTAL

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

11/20/2023



KHA PROJECT 067783129  
DATE NOVEMBER 2023  
SCALE AS SHOWN  
DESIGNED BY: GNH  
DRAWN BY: ALB  
CHECKED BY: JCL

LIFT STATION AND VAULT  
SECTIONS AND DETAILS

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER


89

BY DATE REVISIONS No.







Plotted By: Horiades, George    Date: November 19, 2023    01:05:10pm    File Path: K:\WPB\Civil Structures\Texas -- North Austin Office\Edgewood US CAD\PlanSheets\SLAB ON GRADE TYPICAL DETAILS.dwg    This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




1  
91  
TRANSFORMER THICKENED EDGE  
N.T.S.




4  
91  
ODOR CONTROL SLAB  
N.T.S.



2  
91  
GENERATOR SLAB  
N.T.S.




5  
91  
TYP. CONTROL JOINT (CJ) DETAIL AND ENLARGEMENT  
N.T.S.



A  
91  
CONTROL JOINT (CJ) ENLARGEMENT  
N.T.S.

- NOTES:
- WIDTH (W) OF SEALANT RESERVOIR IS 1/2" MIN. TO 5/8" MAX.
  - DEPTH OF INITIAL SAWCUT (SC) OR INSERT TYPE JOINT FORMER (CONTROL JOINT), 1/4 THICKNESS OF SLAB.
  - TOP OF SEALANT WILL BE 1/8" BELOW TOP OF SLAB.
  - JOINT SEALANT SHALL BE SIKAFLEX PRO-3 OR APPROVED EQUIVALENT. INSTALL PER MANUFACTURER'S REQUIREMENTS.



3  
91  
ELECTRICAL CONTROL PANEL THICKENED EDGE AT COLUMN  
N.T.S.


- BACKFILL AND COMPACTION NOTES:
- CONTRACTOR SHALL PREPARE SUBGRADE IN ACCORDANCE WITH THE REFERENCED GEOTECH REPORT, AT A MINIMUM, EXISTING GRADE SHALL BE CUT TO EXACT BOTTOM OF FOUNDATION TO A CONSISTENT ELEVATION AT BOTTOM OF FOUNDATION THROUGHOUT IF WEATHERED ROCK IS ENCOUNTERED.
  - IF WEATHERED ROCK IS NOT ENCOUNTERED AT BOTTOM OF FOOTING ELEVATION THEN CONTRACTOR SHALL EXCAVATE TO WEATHERED ROCK AND THEN BACKFILL FROM WEATHERED ROCK TO BOTTOM OF FOUNDATION WITH SELECT FILL TO ESTABLISH FOUNDATION SUBGRADE FOR CONSTRUCTION.

PERMIT SUBMITTAL

**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

11/20/2023



KHA PROJECT 067783129  
DATE NOVEMBER 2023  
SCALE AS SHOWN  
DESIGNED BY: GNH  
DRAWN BY: ALB  
CHECKED BY: JCL

SLAB ON GRADE TYPICAL  
DETAILS

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER

91

BY

REVISIONS


No.

DATE




Plotted By: Duff, Daniel Date: December 20, 2023 07:57:02am File Path: K:\AUS\_Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Cod Plans\Sheets\C-Water Quality Plan.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



TCEQ Water Quality Drainage Basins					
	Proposed Area (AC)	Proposed Impervious Cover (AC)	% Impervious Cover	REQUIRED TSS REMOVAL	PROPOSED TSS REMOVAL
WQP-C1	15.72	7.93	50%	6902	7825
WQP-C2	9.33	3.84	41%	3342	3925
WQP-B-C (2-2)	1.68	0.91	54%	792	960
VFS-7	0.55	0.24	44%	209	209
VFS-8	0.97	0.31	32%	270	270
VFS-9	0.29	0.09	31%	78	78
NOT TREATED (NT-1-3)	16.73	1.70	10%	1480	0
TOTAL ONSITE	45.27	15.02	33%	13073	13267



LEGEND

X-1

9.9 ac

AREA DESIGNATOR

AREA IN ACRES

—

---

---

→

▨


PROPERTY LINE

EXISTING STORM DRAIN LINE

PROPOSED DRAINAGE DIVIDE

PROPOSED FLOW DIRECTION

VEGETATIVE FILTER STRIP



- NOTES:
- ENGINEERED VEGETATIVE FILTER STRIPS TO COMPLY WITH TCEQ RG-348, SECTION 3.4.6.
  - VFS TO BE SEEDED PER LEANDER EROSION CONTROL NOTE 5 ON SHEET 2 FOR TEMPORARY EROSION AND SEDIMENTATION CONTROLS.

ENGINEERED VEGETATIVE FILTER STRIPS  
NTS

BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2358 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30859533.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3087998.0100  
ELEVATION: 1002.490' (NAVD '88)

Kimley»Horn

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023

STATE OF TEXAS

ALEXANDRO E. GRANADOS RICO

130084

PROFESSIONAL ENGINEER

*Alexandro E. Granados Rico*

KHA PROJECT

067783129

DATE

DECEMBER 2023

SCALE

AS SHOWN

DESIGNED BY

DPD

DRAWN BY

AMF

CHECKED BY

AEC

EDGEWOOD

PHASE 2, SECTION 2

CITY OF LEANDER

WILLIAMSON COUNTY, TEXAS

SHEET NUMBER

92

OF

112

REVISIONS

DATE

BY












Plotted By: Duffy, Daniel    Date: December 20, 2023    07:58:32am    File Path: K:\AUS-Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Grid Plan\Sheets\C-Pond Sections.dwg  
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



**LEGEND**


	PROPERTY LINE
	PROPOSED SPOT ELEVATION
	EXISTING SPOT ELEVATION
	STREET DRAINAGE FLOW DIRECTION
	PROPOSED CONTOUR
	EXISTING CONTOUR

BATCH DETENTION POND REVEGETATION PLAN

- IMMEDIATELY FOLLOWING COMPLETION OF CONSTRUCTION, EXCESS SPOIL AND DEBRIS SHALL BE REMOVED AND THE CONSTRUCTION AREA SHALL BE GRADED TO THE CONTOURS AS SHOWN ON THE PLANS. THE SURFACE OF THE GROUND SHOULD BE SMOOTH WITH NO LARGE ROCKS, STUMPS, OR OTHER DEBRIS. TOPSOIL OF SANDY LOAM, LOAM, CLAY LOAM OR EQUIVALENT AND FREE OF TREE ROOTS, ROCKS GREATER THAN 2 INCHES IN DIAMETER AND OTHER DEBRIS SHALL THEN BE UNIFORMLY SPREAD OVER ALL DISTURBED AREAS TO A MINIMUM DEPTH OF 6 INCHES. THE TOPSOIL SHOULD BE COMPACTED BY TRACKING A BULLDOZER WITH CLEATED TREADS VERTICALLY ON THE SLOPES TO CREATE HORIZONTAL EROSION CHECKS IN THE SURFACE.
  - RE-SEEDING SHALL IMMEDIATELY FOLLOW TOPSOILING WITH THE FOLLOWING MIXTURE OF GRASSES:  
BROADCAST SEEDING:  
A. FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH A COMBINATION OF 2 POUNDS PER 1000 SF OF UNHULLED TYPE 7 (SPECIAL PROVISION 164-WC 001) - STANDARD SHORT NATIVE GRASS SEED MIX AND 7 POUNDS PER 1000 SF OF WINTER RYE WITH A PURITY OF 95% WITH 90% GERMINATION.  
B. FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED TYPE 7 (SPECIAL PROVISION 164-WC 001) - STANDARD SHORT NATIVE GRASS SEED MIX AT A RATE OF 2 POUNDS PER 1000 SF WITH A PURITY OF 95% WITH 85% GERMINATION.  
C. FERTILIZER SHALL BE A PELLETTED OR GRANULAR SLOW RELEASE WITH AN ANALYSIS OF 15-15-15 TO BE APPLIED ONCE AT PLANTING AND ONCE DURING THE PERIOD OF ESTABLISHMENT AT A RATE OF 1 POUND PER 1000 SF.
  - THE SEEDED AREA SHALL BE IRRIGATED OR SPRINKLED IN A MANNER THAT WILL NOT ERODE THE TOPSOIL, AT 10-DAY INTERVALS DURING THE FIRST TWO MONTHS FOLLOWING PLANTING AT A RATE SUFFICIENT TO THOROUGHLY SOAK THE SOIL TO A DEPTH OF 6 INCHES. RAINFALL OCCURRENCES OF ONE-HALF INCH OR GREATER SHALL POSTPONE THE WATERING SCHEDULE 10 DAYS. RESTORATION SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1-1/2 INCHES HIGH WITH 95% COVERAGE AND NO BARE SPOT LARGER THAN 16 SQUARE FEET EXIST.
- NOTES**
  - BOTTOM OF SEDIMENTATION AND DETENTION BASINS SHALL BE GRASS LINED.
  - BARRIER FENCE SHALL BE INSTALLED ON ANY WALLS IN EXCESS OF 30" TALL.
  - ALL POND BOTTOMS, SIDE SLOPES, AND EARTHER EMBANKMENTS SHALL BE COMPACTED TO 95% MAXIMUM DENSITY PER GEOTECH REPORT.
  - EXPANSION JOINTS ON FREE STANDING WALLS SHALL HAVE WATER TIGHT SEALS AS NEEDED.
  - ALL EXPOSED CONCRETE THAT IS VISIBLE IS REQUIRED TO BE MADE OF STONE OR CLAD IN STONE INCLUDING BUT NOT LIMITED TO LEDGESTONE, FIELDSTONE, CAST STONE, OR OTHER DECORATIVE MATERIALS SUCH AS STAMPED AND TINTED CONCRETE THAT RESEMBLES STONE OR BRICK AS APPROVED BY THE DIRECTOR OF PLANNING. ALL OTHER EXPOSED CONCRETE IS REQUIRED TO BE MADE OF STONE OR CLAD IN STONE AS LISTED ABOVE OR TEXTURED AND TINTED IN EARTHERN COLORS. IN THE EVENT THAT THE DRAINAGE FACILITY IS BELOW GRADE, CONCRETE IS PERMITTED INSTEAD OF NATIVE STONE AND SCREENING REQUIREMENTS ARTICLE VI, SEC. 1 (D) OF THIS ORDINANCE SHALL APPLY.
  - CONTRACTOR SHALL SUBMIT STRUCTURAL DESIGN TO THE CITY FOR APPROVAL PRIOR TO CONSTRUCTION ON THIS STRUCTURE.

Detention Pond C-1:							Rating Table	
Stage (FT MSL)	Area (SF)	Area (AC)	Storage (CF)	Cumm. Storage (CF)	Cumm. Storage (AC-FT)	Flow (CFS)		
945.00	8296	0.190	-	-	-	0.00	WATER QUALITY ELEVATION	
946.00	16,403	0.377	12,350	12,350	0.28	0.00		
947.00	18,150	0.417	17,277	29,626	0.68	0.00		
948.00	19,965	0.458	19,058	48,684	1.12	1.00		
949.00	21,838	0.501	20,902	69,585	1.60	0.00		
950.00	23,768	0.546	22,803	92,388	2.12	0.00		
951.00	25,754	0.591	24,761	117,149	2.69	0.00		
952.00	27,797	0.638	26,776	143,925	3.30	0.00		
953.00	29,894	0.686	28,846	172,770	3.97	4.24		
954.00	32,049	0.736	30,972	203,742	4.68	22.04		
955.00	34,259	0.786	33,154	236,896	5.44	47.44		
956.00	36,500	0.838	35,380	272,275	6.25	78.55		

WSE	Pond C-1
2-YR WSE	951.49
10-YR WSE	952.83
25-YR WSE	953.63
100-YR WSE	954.89



**BENCHMARKS**

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAM DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.  
BM-101: 'X' CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.2368 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.  
N= 10186642.4550  
E= 30895933.6490  
ELEVATION: 915.036' (NAVD '88)  
BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.  
N= 10187908.0080  
E= 3087998.0100  
ELEVATION: 1002.490' (NAVD '88)


© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023


KHA PROJECT	067783129	POND C1	EDGEWOOD PHASE 2, SECTION 2 CITY OF LEANDER WILLIAMSON COUNTY, TEXAS
DATE	DECEMBER 2023		
SCALE	AS SHOWN		
DESIGNED BY	DPD		
DRAWN BY	AMF	SHEET NUMBER	95
CHECKED BY	AEC	OF	112
		REVISIONS	
		BY	DATE







This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adoption by Kinley-Horn and Associates, Inc. shall be without liability to Kinley-Horn and Associates, Inc.




WSE	Pond C-2
2-YR WSE	930.60
10-YR WSE	931.43
25-YR WSE	932.03
100-YR WSE	932.91







PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL



KHA PROJECT 067783129	DATE
DECEMBER 2023	
SCALE: AS SHOWN	
DESIGNED BY: DPD	
DRAWN BY: AMF	
CHECKED BY: AEG	

## POND CROSS SECTIONS

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER

OF 97

112

TEXAS REGISTERED ENGINEERING FIRM F-928

2

DATE \_\_\_\_\_


BY

Plotted By: Duffy, Daniel Date: December 20, 2023 07:59:58am File Path: K:\AUS\_Civil\067783129 - Connon 140 - MI Homes\PHASE 2-2\Coord\PlanSheets\C-Pond Sections.dwg




Plotted By: Duff, Daniel Date: December 20, 2023 08:00:11am File Path: K:\AUS\_Civil\067783129 - Cannon 140 - MI Homes\PHASE 2-2\Cad\PlanSheets\C-Pond Sections.dwg This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.


## SMARTBATCH C-1



## SMARTBATCH C-2



PROFILE SCALE  
1" = 40' HORIZONTAL  
1" = 4' VERTICAL




STORM OUTFALL DESIGN - POND C-1					
Edgewood Phase 2-2					
INPUT VALUES					
	Storm Line		Unit	Source	
	SD-A	SD-B			
Discharge (Q) =	49.80	47.92	cfs	StormCAD Model	
Velocity at Outfall (V <sub>1</sub> ) =	7.05	6.78	ft/s	StormCAD Model	
Outlet Pipe Diameter (D) =	3.0	3.0	ft	Required Size for Conveyance	
HEADWALL <sup>1</sup>					
Headwall Length (L) =	9.00	9.00	ft	COA Detail 5085-13, Based on Outlet Diameter	
Headwall Width (C) =	15	15	ft	COA Detail 5085-13, Based on Outlet Diameter	
Depth of Flow at End of Headwall (d) =	0.56	0.55	ft	Based on Manning's Equation, using Goal Seek in Excel to solve for depth	
Velocity at End of Headwall (V <sub>2</sub> ) =	5.95	5.84	ft/sec	$V = \frac{Q}{A}$ , where $A = Cd$	
RIPRAP					
Riprap Size (D <sub>50</sub> ) =	0.41	0.40	ft	D <sub>50</sub> = 0.0105V <sub>2</sub> <sup>2.06</sup> (ECM 1.4.6.D.5)	
	6.00	6.00	in	Rounded up to Nearest Diameter Size in City of Austin ECM, 591S.3 Rock Riprap Gradation Table	
Riprap Classification =	I	I	---	Based on City of Austin ECM, 591S.3 Rock Riprap Gradation Table	
Apron Width =	17.00	17.00	ft	Apron Width = C + 2	
Apron Length =	31.50	31.50	ft	Apron Length = 3D <sub>50</sub> + La (10*D) (5085-20)	
Apron Depth =	1.50	1.50	ft	Apron Depth = 3D <sub>50</sub> (5085-20)	

<sup>1</sup>For additional headwall geometry, refer to COA Standard Detail 5085-13

STORM OUTFALL DESIGN - POND C-2					
Edgewood 2-2					
INPUT VALUES					
	Storm Line	Unit	Source		
	SD-D				
Discharge (Q) =	50.62	cfs	StormCAD Model		
Velocity at Outfall (V <sub>j</sub> ) =	10.31	ft/s	StormCAD Model		
Outlet Pipe Diameter (D) =	2.5	ft	Required Size for Conveyance		
HEADWALL <sup>1</sup>					
Headwall Length (L) =	7.50	ft	COA Detail 5085-13, Based on Outlet Diameter		
Headwall Width (C) =	12.5	ft	COA Detail 5085-13, Based on Outlet Diameter		
Depth of Flow at End of Headwall (d) =	0.62	ft	Based on Manning's Equation, using Goal Seek in Excel to solve for depth		
Velocity at End of Headwall (V <sub>2</sub> ) =	6.50	ft/sec	$V = \frac{Q}{A}$ , where $A = Cd$		
RIPRAP					
Riprap Size (D <sub>50</sub> ) =	0.50	ft	$D_{50} = 0.0105V_2^{2.06}$ (ECM 1.4.6.D.5)		
	6.00	in	Rounded up to Nearest Diameter Size in City of Austin ECM, 591S.3 Rock Riprap Gradation Table		
Riprap Classification =	I	---	Based on City of Austin ECM, 591S.3 Rock Riprap Gradation Table		
Apron Width =	14.50	ft	Apron Width = C + 2		
Apron Length =	26.50	ft	Apron Length = 3D <sub>50</sub> + La (10*D) (5085-20)		
Apron Depth =	1.50	ft	Apron Depth = 3D <sub>50</sub> (5085-20)		

<sup>1</sup>For additional headwall geometry, refer to COA Standard Detail 5085-13

**Kimley»Horn**  
© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928






KHA PROJECT 067783129  
DATE 2023  
SCALE AS SHOWN  
DESIGNED BY: DPD  
DRAWN BY: AMF  
CHECKED BY: AEC

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 98 112



Plotted By: Duff, Daniel Date: December 20, 2023 08:00:16am File Path: K:\AUS\_Civil\067783129 - 2\ - MI Homes\PHASE 2 - 2\Cad\PlanSheets\C-Pond Sections.dwg  
This document, together with the concepts and designs presented herein, is an instrument of service. It is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



**Kimley»Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023

STATE OF TEXAS  
ALFONSO E. GRANADOS RICO  
130084  
PROFESSIONAL ENGINEER  
Alfonso E. Granados Rico

KHA PROJECT 067783129  
DATE 2023  
SCALE AS SHOWN  
DESIGNED BY: DPD  
DRAWN BY: AMF  
CHECKED BY: AEC














**WATER QUALITY DETAILS**

**EDGEWOOD**  
**PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS









SHEET NUMBER  
99  
OF 112

REVISIONS  
DATE  
BY













BENCHMARKS	
ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD 88) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.	
BM-101: 1/4" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 120.258 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.	
N= 10186642.4550	
E= 30959533.6490	
ELEVATION: 915.036' (NAVD 88)	
BM-103: 5/8" ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.	
N= 10187908.0080	
E= 3097998.0100	
ELEVATION: 1002.490' (NAVD 88)	





NO.	REVISIONS	DATE	BY

**Kimley-Horn**

© 2023 KIMLEY-HORN AND ASSOCIATES, INC.  
501 S. AUSTIN AVENUE, SUITE 1310, GEORGETOWN, TX 78626  
PHONE: 512-520-0768 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
TEXAS REGISTERED ENGINEERING FIRM F-928

12/06/2023

STATE OF TEXAS  
ALEXANDRO E. GRANADOS RICO  
130084  
PROFESSIONAL ENGINEER

Alpha E. Rios, Inc.












KHA PROJECT 067783129  
DATE 2023  
SCALE: AS SHOWN  
DESIGNED BY: DPD  
DRAWN BY: AD  
CHECKED BY: AEC

STORM DRAIN DETAILS  
(SHEET 2 OF 2)

EDGEWOOD  
PHASE 2, SECTION 2  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER  
OF 108 112





## BENCHMARKS

ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: "X" CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE TO SUBJECT 120.2358 ACRE TRACT FROM C.R. 175 DOWNSIDE GATE, NEAR KEYPAD.

N= 10186642.4550

E= 30959533.6490


ELEVATION: 915.036' (NAVD '88)

CM-103: 5/8 ROAD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.

N= 10187908.0080

E= 3097998.1002






ELEVATION: 1002.490' (NAVD '88)

[illegible]





**WATER & WASTEWATER  
NOTES & DETAILS  
(SHEET 1 OF 2)**

**EDGEWOOD  
PHASE 2, SECTION 2**  
CITY OF LEANDER  
WILLIAMSON COUNTY, TEXAS








1 UTILITY CROSSING DETAIL  
NOT TO SCALE




**NOTES:**

1. DURING SUBDIVISION CONSTRUCTION, UTILITY CONTRACTOR INSTALLS WASTEWATER CONNECTION TO MAIN 6" HORIZONTAL PIPE FOR DOUBLE SERVICES. 6" SERVICE SHALL BE INSTALLED TO THE STREET. UTILITY CONTRACTOR SHALL INSTALL 6" SERVICE TAPE TO END OF 6" STUB, WRAPE 3 TIMES AROUND LENGTH OF PVC BURIED TO END OF 6" STUB AND TIES TO TOP OF PVC EXTING A MINIMUM OF 2 FEET ABOVE GROUND.
2. ALL WASTEWATER PIPING SHALL HAVE ELASTOMERIC GASKET TYPE JOINTS AND SHALL BE 6" GRADE OR BETTER. ALL CONNECTIONS SHALL BE MADE TO THE DEPTH OF SERVICE STUB AT PROPERTY LINE WILL BE SHOWN ON PLANS BY THE CITY ENGINEER. IF WASTEWATER SERVICE LINE TO MAIN REQUIRES DEFLECTION, EXCEEDING WITH REFERENCE TO DETAIL 502-6 ON INSTALLATION, SHALL BE MADE IN ACCORDANCE WITH INFORMATION ON APPLICATION. ALL DEFLECTION SHALL BE INSPECTED BY CITY OF LEANDER CONSTRUCTION INSPECTION PERSONNEL.
3. CUSTOMER REMOVES PLUG FROM 6" SERVICE LINE STUB, INSTALLS 6" 2-WAY CLEANOUT TO STREET. CUSTOMER SHALL BE RESPONSIBLE FOR THE 6" 2-WAY THREADED PLUG, AND 6" SERVICE LINE TO STRUCTURE. IF WASTEWATER WILL NOT BE INSTALLED TO THE STREET, CUSTOMER SHALL BE RESPONSIBLE FOR THE 6" WASTEWATER MAIN. PUMP EQUIPMENT MUST BE PROVIDED BY THE CUSTOMER AS SHOWN ON PLANS.
4. CUSTOMER IS RESPONSIBLE FOR PUBLIC PIPING SYSTEM UNTIL WASTEWATER IS ANY MISSING OR DAMAGED PARTS SHALL BE REINSTALLED BY THE CUSTOMER. THE CITY OF LEANDER CONSTRUCTION INSPECTION SHALL SET OF ACCEPTANCE, THAT CONNECTIONS TO CITY SYSTEMS, ARE FREE FROM DEFECTS OR DAMAGE. THE CITY OF LEANDER CONSTRUCTION INSPECTION SHALL SET OF ASSURE, THAT ALL 2-WAY-CLEANOUTS REMAIN CLEAR OF SIDEWALKS AND OTHER OBSTRUCTIONS.
5. THE CITY OF LEANDER AUTHORITY IS LIMITED TO INSPECTION OF CONNECTIONS TO THE CITY'S WASTEWATER SYSTEM, FOR MAINTENANCE PURPOSES. THE CITY'S RESPONSIBILITY ENDS AT THE CUSTOMER'S WASTEWATER CONNECTION TO THE 2-WAY-CLEANOUT.
6. PIPING AND TUBING IN STREET RIGHT-OF-WAY AND IN EASEMENT AREA SHALL BE BEDDED IN GRANULAR MATERIALS AS REQUIRED BY CITY OF AUSTIN STANDARD SPECIFICATIONS. THE CITY OF LEANDER CONSTRUCTION INSPECTION SHALL SET OF ACCEPTANCE, THAT MATERIALS SHALL BE AS SPECIFIED IN 5102.2 (2)(A) AND (3)(B). BACKFILL ABOVE THE 6" SERVICE LINE SHALL BE GRANULAR MATERIAL. THE CITY OF LEANDER CONSTRUCTION LINES IN THESE AREAS SHALL HAVE A MINIMUM COVER BELOW FINAL STREET GRADE OF 12" ABOVE PIPE, 6" BELOW PIPE, 4" BELOW PIPE, AND 12" BEYOND JOINTS AT EACH END.
7. ALL SANITARY SEWER PIPE WITHIN 9' OF WATER MAINS SHALL BE BEDDED IN CENTENARY STABILIZED SAND PER TOWNSHIP 217 & 290 REQUIREMENTS, BEDDING SHALL BE A MINIMUM OF 12" ABOVE PIPE, 4" BELOW PIPE, AND 12" BEYOND JOINTS AT EACH END.
8. PIPE MATERIAL FOR WASTEWATER SERVICES SHALL BE 6" SDR-26 PVC D2241 60 PSI RATED.
9. NO METER BOX OR CLEAN OUT SHALL BE SET IN SIDEWALK OR DRIVEWAY AREA WITHOUT WRITTEN APPROVAL FROM THE CITY ENGINEERING DEPT.
10. NO JOINTS SHALL BE PERMITTED BETWEEN THE 6" 6" HORIZONTAL PIPE AND THE 6" 2-WAY CLEANOUT EXCEPT FOR THE 6" 45-DEGREE BEND REQUIRED FOR DOUBLE SERVICE.



NOTES:

1. ON 10" AND LARGER TWO PIECE COMBINATION AIR VALVES, THE OUTLET PIPING OF THE SMALL VALVE SHALL BE VENTED THROUGH THE VALVE INTO THE LARGER VENT PIPE.
2. AIR VENT PIPE 6" AND LARGER SHALL BE DI (CLASS 350 MIN.) PIPE. FLANGE FITTINGS AND EXTERIOR SURFACES OF ALL EXPOSED PIPE SHALL BE PERI SPR. SPL. WW-33. POTABLE WATER SHALL BE LIMITED TO ONLY BLUE. SURFACE PAINTATION SHALL BE PER PANT MANUFACTURER'S REQUIREMENTS.
3. ENTIRE AIR VENT ASSEMBLY SHALL BE LOCATED WITHIN EASEMENT OR R.O.W.
4. CONCRETE PIPE PENETRATIONS SHALL BE CORE BIT DRILLED. VOID SHALL BE SEALED W/INKSEAL LS 300 OR APPROVED EQUAL.
5. CROSS SECTIONAL AREA OF OPENING TO BE EQUAL TO OR GREATER THAN CROSS SECTIONAL AREA OF AIR VENT PIPE.
6. AIR/VACUUM VALVE SHALL BE INSTALLED IN A MANNER WHICH WILL ALLOW REMOVAL OF ASSEMBLY WITHOUT REMOVAL OF PRECAST CONCRETE LID.
7. IN UNDEVELOPED AREAS, THE AIR VENT PIPE SHALL BE 4" IN HEIGHT SUPPORTED BY A 4" DIA. DI PIPE WHICH HAS BEEN FILLED WITH CONCRETE (SUPPORT PIPE SHALL BE 6" LONG, BURRED TO THE CONCRETE OR CEMENT MORTAR FILLING). THE GATE AND EXTENDING 3' ABOVE FINAL GRADE. INSTALL ONE DELINEATOR STAKE WITHIN 3' OF THE VALVE ON THE VEHICULAR ACCESS SIDE. THE OTHER DELINEATOR SHALL BE 5' FROM THE VALVE. DELINEATORS SHALL BE BLUE FOR POTABLE WATER AND SHALL EXTEND AT LEAST 60° ABOVE GROUND. DELINEATORS SHALL HAVE 2" WHITE, WHITE IN COLOR, TYPE I REFLECTIVE TAPE MOUNTED DIAGONALLY AT 12° SPACING ON BOTH SIDES. FITTING DEVELOPED OUTLET SIDE OF AIR VENT PIPE SHALL BE LOCATED NOT TO CONFLICT WITH SIDEWALK, DRIVEWAY, OR OTHER PEDESTRIAN TRAFFIC.
8. GATE VALVE, PIPE, AND FITTINGS FROM MAIN TO ARV SHALL BE OF EQUAL DIAMETER AS THE AIR VALVE EXCEPT 3" ARV SHALL HAVE 4" FITTINGS AND 4"x3" REDUCER AT THE ARV, AND ALL PIPE 3" AND ON THE MAIN SHALL BE 4" DIAMETER. DELINEATORS SHALL BE BLUE FOR POTABLE WATER. THE "R" VALV'S SHALL BE 5" DIAMETER FOR 3" VALVE, 6" DIAMETER FOR 4", 6", AND 8" VALVES, AND 7" DIAMETER FOR 10" AND 12" VALVES.
9. FOR 24" AND LARGER MAINS, AN 18" OUTLET WITH BLIND FLANGE SHALL BE INSTALLED AT



## BENCHMARKS

ELEVATIONS HEREON ARE REFERENCED TO THE NORTH AMERICAN DATUM 1988 (NAVD) UTILIZING WESTERN DATA SYSTEMS CONTINUALLY OPERATING REFERENCE STATION (CORS) NETWORK.

BM-101: 'X' CUT IN CONCRETE ON NORTHWEST SIDE OF ENTRANCE OF SUBJECT 102.2358 ACRE TRACT FROM C.R. 175, OUTSIDE GATE, NEAR KEYPAD.

E= 10186642.4550

E= 30959353.6490

ELEVATION: 915.036' (NAVD '88)

BM-103: 5/8 ROD SET IN CONCRETE NEAR GRAVEL ROAD AND THE SOUTHWEST CORNER OF THE 0.20 ACRE TRACT TO DONALD AND DOLORES GISH.

E= 10187908.0080

E= 3097998.0100

ELEVATION: 1002.490' (NAVD '88)

