Chapel Hill Phase II

Organized Sewage Collection System Application



Prepared for: TCEQ Austin Regional Office

Prepared by: Paul Hames, P.E.



TBPE No. F-6324 TBPLS No. 10194230

Project #222012278 February 1, 2024

Sign-off Sheet

This document entitled Chapel Hill Phase II was prepared by Stantec Consulting Services Inc. ("Stantec") for the account of The Duke Companies (the "Client"). Any reliance on this document by any third-party is strictly prohibited. The material in it reflects Stantec's professional judgment considering the scope, schedule and other limitations stated in the document and in the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not consider any subsequent changes. In preparing the document, Stantec did not verify information supplied to it by others. Any use which a third-party makes of this document is the responsibility of such third-party. Such third-party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third-party because of decisions made or actions taken based on this document.

faul M. Homes (signature)

Uner

Prepared by

Paul Hames, P.E.

Reviewed by ____

(signature)

Zhongyue Mao, P.E.



CHAPEL HILL PHASE II

February 1, 2024

Organized Sewage Collection System Table of Contents

- i. Edwards Aquifer Application Cover Page (TCEQ-20705)
- I. General Information Form (TCEQ-0587)
 ATTACHMENT 1A Road Map
 ATTACHMENT 1B USGS / Edwards Recharge Quadrangle Map
 ATTACHMENT 1C Project Description
- II. Geologic Assessment Form (TCEQ-0585)
- III. Organized Sewage Collection System Plan (TCEQ-0582) ATTACHMENT 3A – SCS Engineering Design Report ATTACHMENT 3B – Not Applicable ATTACHMENT 3C – Not Applicable ATTACHMENT 3D – Not Applicable Site Plan Final Plan and Profile Sheets
- IV. Lift Station / Force Main System Application (TCEQ-0602) Not applicable
- V. Temporary Stormwater Section (TCEQ-0602) ATTACHMENT 5A – Spill Response Actions ATTACHMENT 5B – Potential Sources of Contamination ATTACHMENT 5C – Sequence of Major Activities ATTACHMENT 5D – Temporary Best Management Practices and Measures ATTACHMENT 5E – Not Applicable ATTACHMENT 5F – Structural Practices ATTACHMENT 5F – Structural Practices ATTACHMENT 5G – Drainage Area Maps ATTACHMENT 5H – Temporary Sediment Pond Plans and Calculations ATTACHMENT 5I – Inspection and Maintenance for BMPs ATTACHMENT 5J – Schedule of Interim and Permanent Soil Stabilization Practices
- VI. Agent Authorization Form (TCEQ-0599)
- VII. Application Fee Form (TCEQ-0574)
- VIII. Core Data Form (TCEQ-10400)



Texas Commission on Environmental Quality Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with <u>30 TAC 213</u>.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Chapel Hill Phase II						2. Regulated Entity No.: 111787560				
3. Customer Name:	/ Cha	pel Hill	II LLC		4. Customer No.:					
5. Project Type: (Please circle/check one)	New		Modification			Extension		Exception		
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS)	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures	
7. Land Use: (Please circle/check one)	Resider	ntial	Non-residential				8. Sit	e (acres):	14.881	
9. Application Fee:			10. Permanent B			BMP(s): Batch Deter		Batch Detention	1	
11. SCS (Linear Ft.):			12. AS	ST/US	ST (No	o. Tar	nks):			
13. County:	Williams	on	14. W	aters	hed:			Brushy Creek		

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region									
County:	Hays	Travis	Williamson						
Original (1 req.)			✓						
Region (1 req.)	_		<u>√</u>						
County(ies)									
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA						
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock						

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)			_		
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Paul M. Hames, PE Print Name of Customer/Authorized Agent

faul M. Homes

Signature of Customer/Authorized Agent

2/01/2024

Date

FOR TCEQ INTERNAL USE ONLY					
Date(s)Reviewed:	Date Admin	nistratively Complete:			
Received From:	Correct Nur	nber of Copies:			
Received By:	Distribution	n Date:			
EAPP File Number:	Complex:				
Admin. Review(s) (No.):	No. AR Rou	nds:			
Delinquent Fees (Y/N):	Review Tim	e Spent:			
Lat./Long. Verified:	SOS Custon	ner Verification:			
Agent Authorization Complete/Notarized (Y/N):	Fee	ayable to TCEQ (Y/N):			
Core Data Form Complete (Y/N):		Signed (Y/N):			
Core Data Form Incomplete Nos.:	L	ess than 90 days old (Y/N):			

Section I

General Information Form (TCEQ-0587)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Paul M. Hames, P.E.

Date: 2/01/2024

Signature of Customer/Agent:

faul M. Homes

Project Information

- 1. Regulated Entity Name: Chapel Hill Phase II
- 2. County: Williamson
- 3. Stream Basin: Brushy Creek
- 4. Groundwater Conservation District (If applicable): N/A
- 5. Edwards Aquifer Zone:

Х	Recharge Zone
Χ	Transition Zone

6. Plan Type:

WPAP	AST
× scs	UST
Modification	Exception Request

7. Customer (Applicant):

Contact Person: Erik Boraks Entity: AMFP V Chapel Hill II LLC	
Mailing Address: 13740 Midway Road, #804 City, State: Dallas, Texas Telephone: (972)385-1676	Zip: 75244 FAX:
Email Address: Erik.Boraks@dukecompanies.com	TAX
Agent/Representative (If any):	
Contact Person: Paul M. Hames, P.E.	
Entity: Stantec Consulting Services Mailing Address: 6080 Tennyson Pkwy., Suite 200	
City, State: Plano, Texas	Zip: 75024
Telephone: (214) 473-2483	FAX:

Email Address: Paul.hames@stantec.com

9. Project Location:

8.

X The project site is located inside the city limits of Georgetown, TX.

The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.

The project site is not located within any city's limits or ETJ.

10. X The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

South side of Southeast Inner Loop, east side of Interstate 35, north side of Westinghouse Road and west side of Celebration Blvd.

- 11. X Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
- 12. X Attachment B USGS / Edwards Recharge Zone Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
 - X Project site boundaries.
 - X USGS Quadrangle Name(s).
 - X Boundaries of the Recharge Zone (and Transition Zone, if applicable).
 - X Drainage path from the project site to the boundary of the Recharge Zone.
- 13. X The TCEQ must be able to inspect the project site or the application will be returned. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.
 - X Survey staking will be completed by this date: TBD

- 14. X Attachment C Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
 - X Area of the site
 - X Offsite areas
 - X Impervious cover
 - X Permanent BMP(s)
 - X Proposed site use
 - X Site history
 - X Previous development
 - X Area(s) to be demolished
- 15. Existing project site conditions are noted below:
 - Existing commercial site
 Existing industrial site
 Existing residential site
 Existing paved and/or unpaved roads
 Undeveloped (Cleared)
 Undeveloped (Undisturbed/Uncleared)
 Other:
- **Prohibited Activities**
- 16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
 - (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
 - (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
 - (4) The use of sewage holding tanks as parts of organized collection systems; and
 - (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
 - (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.
- 17. X I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
 - (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

- 18. The fee for the plan(s) is based on:
 - For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
 - X For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
 - For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
 - A request for an exception to any substantive portion of the regulations related to the protection of water quality.
 - A request for an extension to a previously approved plan.
- 19. X Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:


TCEQ cashier

X Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)

San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

- 20. X Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 21. X No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.


<u>Attachment A – Road Map</u>



V:\2220\active\222012278\civil.phase_01\drawing\exhibit\222012278_location_map.dwg modified by zomao on Oct 18, 21 9:37 AM

<u> Attachment B – USGS/Edwards Recharge Zone Map</u>

Chapel Hill Phase 2



- Edwards Aquifer Boundary central line
- TX Counties
 - 7.5 Minute Quad Grid
 - TCEQ_EDWARDS_OFFICIAL_MAPS

Attachment C – Project Description

The 17.425-acre site, platted as Lot 1 of Chapel Hill Subdivision Section Two, is located on the north side of Westinghouse Road, about a half mile east of the intersection of Interstate 35 and Westinghouse Road in Georgetown, Texas. Chapel Hill Apartments Phase II will consist of 10 apartment buildings and a club house with associated drives, sidewalks, parking, drainage, water quality and detention pond, and utilities. The offsite area to the south of the development will consist of an access driveway with deceleration lane and an additional water quality and detention pond. The existing condition of the site consists of natural grass land with a stock pond in the southwest corner of the property. Additionally, there is an abandoned residential home and barns enclosed with a fence that are all to be removed and surrounded by brush, weeds, and grass mixture with a tree population. The stock pond will be removed and stormwater detention will be provided by the proposed onsite detention pond. The site runoff drains to a box culvert under Westinghouse Road and eventually releases into Brushy Creek. The site generally slopes from northeast to southwest with slopes ranging from 5%-25%. The project is within the City Limits of Georgetown and is located over both the Edwards Aquifer Recharge and Transition Zones. Development of this project is designed in accordance with the City of Georgetown Unified Development Code (UDC) and the TCEQ RG-348 Technical Guidance Manual.

Temporary water quality controls will be provided during construction of the site improvements and will consist of silt fence, rock berms, inlet protection, a temporary sediment pond, concrete truck washout pits, stabilized construction entrances, and dust control.

Permanent water quality control will be provided for this site by an onsite water quality pond. This water quality/detention pond will be located on Lot 1, replacing the existing stock pond. The pond is designed to remove 85% of the increased TSS from the contributing drainage basins, as stipulated by the City of Georgetown UDC, which exceeds the required removal rate of 80% mandated by TCEQ. The water quality pond has been designed for the future impervious cover associated with Lot 1.

Wastewater from the Phase II site will drain to the Westinghouse South Regional Lift Station via an existing gravity sewage collection system where it will then be conveyed to the San Gabriel Wastewater Treatment Plant. The wastewater from the apartment site will be 100% domestic and includes approximately 1,923 LF of 8-inch pipe and 523 LF of 6-inch pipe to be installed from the Phase I manhole connection in the southeast corner of the property.

Water will be provided to the site by a connection to an existing water line contained within an easement on the northern boundary of the site.

The total limits of construction for this project including offsite development is approximately 17.7 acres.

Section II

Geologic Assessment Form (TCEQ-0585)



Narrative Description of Site Specific Geology for the Approximately 54-acre Chapel Hill Tract and Offsite Water and Wastewater Utility Lines, Williamson County, Texas

Prepared for:

Halff Associates, Inc

Prepared by:

Cambrian Environmental

April 22nd, 2020

NARRATIVE DESCRIPTION OF SITE SPECIFIC GEOLOGY FOR THE APPROXIMATELY 54-ACRE CHAPEL HILL TRACT AND OFFSITE WATER AND WASTERWATER UTILITY LINES, WILLIAMSON COUNTY, TEXAS

Prepared for

HALFF ASSOCIATES, INC. 9500 Amberglen Boulevard

Building F, Suite 125 Austin, Texas 78729

Prepared by

Craig Crawford, P.G.

CAMBRIAN ENVIRONMENTAL

4422 Pack Saddle Pass Suite 204 Austin, Texas 78745

Texas Geoscience Firm Registration # 50484



As a licensed professional geoscientist I attest that the contents of this report are complete and accurate to the best of my knowledge.

April 22nd, 2020

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Craig Crawford, PG

Telephone: 512.705.5541

AST UST

Date: 22 April 2020

Fax: _____

Representing: <u>Cambrian Environmental (Tx Geo Firm # 50484)</u> (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:

Regulated Entity Name: Chapel Hill (54-acre Tract and Offsite Wastewater Line)

Project Information

- 1. Date(s) Geologic Assessment was performed: 16 May & 21 August 2019, 10 March 2020
- 2. Type of Project:

\times	WPAP
$\overline{}$	202

\bigtriangleup	SCS	
1		

3. Location of Project:

Recharge Zone

Transition Zone

Contributing Zone within the Transition Zone



-	~ 5	2
1	OF	3

- 4. Attachment A Geologic Assessment Table. Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
- Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, InfiltrationCharacteristics and Thickness

Soil Name	Group*	Thickness(feet)
Austin- Whitewright	С	< 4
Ferris-Heiden	D	> 5
Heiden	D	> 5
Houston	D	> 5

* Soil Group Definitions (Abbreviated)

- A. Soils having a high infiltration rate when thoroughly wetted.
 - B. Soils having a moderate infiltration rate when thoroughly wetted.
 - C. Soils having a slow infiltration rate when thoroughly wetted.
 - D. Soils having a very slow infiltration rate when thoroughly wetted.
- 6. Attachment B Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
- 7. Attachment C Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
- 8. Attachment D Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale: 1" = <u>40</u>' Site Geologic Map Scale: 1" = <u>40</u>' Site Soils Map Scale (if more than 1 soil type): 1" = <u>1000</u>'

9. Method of collecting positional data:

Global Positioning System (GPS) technology.

Other method(s). Please describe method of data collection: _____

- 10. 🖂 The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
- 11. 🖂 Surface geologic units are shown and labeled on the Site Geologic Map.

TCEQ-0585 (Rev.02-11-15)

12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.

Geologic or manmade features were not discovered on the project site during the field investigation.

- 13. 🖂 The Recharge Zone boundary is shown and labeled, if appropriate.
- 14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.

There are $\underline{3}$ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)

The wells are not in use and have been properly abandoned.

 \boxtimes The wells are not in use and will be properly abandoned.

The wells are in use and comply with 16 TAC Chapter 76.

There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.



NARRATIVE DESCRIPTION OF SITE SPECIFIC GEOLOGY FOR THE APPROXIMATELY 54-ACRE CHAPEL HILL TRACT AND OFFSITE WATER AND WASTEWATER UTILITY LINES, WILLIAMSON COUNTY, TEXAS

PROJECT DESCRIPTION

This narrative Geologic Assessment accompanies the Texas Commission on Environmental Quality (TCEQ) Geologic Assessment form TCEQ-0585 completed for the approximately 54-acre Chapel Hill tract. The project site is located on the north side of Westinghouse Road, approximately 0.35 miles east of Interstate Highway (IH) 35. Additionally, this report covers an offsite wastewater line associated with this project. This utility line runs south-southeast from Westinghouse Road, and extends past North Mays Street towards an existing development along Centerbrook Place (see Project Location Map).

METHODOLOGY

Two Cambrian Environmental Registered Professional Geoscientists (License #s 10791 & 1350) and two karst technicians conducted a field survey for a Geologic Assessment on May 16th 2019, and a second site visit to complete the field survey for the wastewater line portion of the project occurred on August 21st 2019. A third site visit and survey were conducted on March 20th 2020 to survey the alignment of the offsite waterline. The pedestrian survey was completed by walking parallel transects spaced approximately 50 feet apart as directed by the TCEQ in the Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones (Rev. 10-01-04). Closer spacing was used where vegetation inhibited clear observation. All potential karst features, including depressions, holes, and animal burrows, were carefully examined for evidence of subsurface extent. A number of techniques were used for this effort, including probing with a digging implement to determine the thickness and consistency of fill material and feeling for the presence of air flow, which may indicate the presence of a sub-surface void space. Other techniques included making observations of any notable characteristics of the feature site such as the presence of various types of vegetation or a semi-circular burrow mound produced by the activities of small mammals. The locations of any discovered features were recorded with a handheld GPS unit and were also marked on-site with pink flagging tape. Cambrian also conducted due diligence activities as called for under the City of Georgetown Edwards Aquifer Recharge Zone Water Quality Ordinance ("the Ordinance").

RESULTS

<u>Soils</u>

Soils mapped within the project area include the Austin-Whitewright complex (AwC2), Ferris-Heiden complex (FhE), Heiden (HeD2, HsE), and Houston (HuB, HuC2) series soils (see Site Soils Map).¹ The Austin-Whitewright series soils are within the "C" classification of the hydrologic soil groups. Type "C" soils have a slow infiltration rate (high runoff potential) when thoroughly wet. The Ferris-Heiden, Heiden, and Houston series soils are within the "D" classification of the hydrologic soil groups. Type "D" soils have a very slow infiltration rate (very high runoff potential) when thoroughly wet.

¹ United States Department of Agriculture, Soil Conservation Service, Soil Survey of Williamson County, Texas, 1983.

Geology

The project site is located partially within the Edwards Aquifer Recharge Zone, and partially within the Edwards Aquifer Transition Zone. Generally, the Recharge Zone is the area where the stratigraphic units constituting the Edwards Aquifer are outcropping at the surface, and where permeable features create the potential for recharge of surface waters into the aquifer. The Transition Zone is where geologic formations outcrop in proximity to the Recharge Zone, and where geologic features may present possible avenues of recharge of surface waters to the aquifer. The Transition Zone includes portions of the Del Rio Clay, Buda Limestone, Eagle Ford Group, and Austin Chalk.

The bedrock lithologies underlying and outcropping in the 54-acre portion of the project area are Cretaceous in age and consist of the Eagle Ford Group, the Buda Limestone, and the Del Rio Clay, which are stratigraphically above the units that comprise the Edwards Aquifer (see Project Geologic Map, Sheet 1 of 3). The bedrock lithologies underlying the wastewater line portion of the project area consist of the Del Rio Clay and the Georgetown Limestone (see Project Geologic Map, Sheets 2 & 3). The geology of this area has been mapped most recently at a useful scale by Collins (2005), and we find his interpretation of the geology to be generally accurate.²

Recharge into the aquifer primarily occurs in areas where the Edwards Group and Georgetown Formation are exposed at the surface, and both of these units are absent in outcrop on the property. Most recharge is from direct infiltration via precipitation and streamflow loss. Recharge occurs predominantly along secondary porosity features such as faults, fractures, and karst features (caves, solution cavities, sinkholes, etc.). Karst features are commonly formed along joints, fractures, and bedding plane surfaces in the Edwards Group. No karst features on any type were discovered during the pedestrian survey, and very little outcropping bedrock was observed due to the generally thick soil cover. The alignment of one mapped fault crosses through the wastewater line portion of the project (see Project Geologic Map, Sheet 3 of 3), however no trace of this fault was observable in the field. This portion of the project area has a thick layer of clayey soil (Houston Black clay) over the bedrock, and the location of this fault was not able to be verified.

Three wells were discovered during the pedestrian survey. However, a review of the Texas Water Development Board's online Groundwater Data Viewer³ did not produce any results or data regarding any documented ground water wells located on this the property.

Site Hydrogeologic Assessment

In the absence of discrete recharge features, the likelihood of surface water infiltrating on this property and contributing to the main body of the aquifer is thought to be very low. This is further supported by the lack of the Edwards Limestone and Georgetown Limestone outcrop on the property. While the likelihood is low, should any karst features be discovered during the construction phase of the project, they should be reported to TCEQ and have appropriate mitigation measures emplaced.

² Collins, E.W., 2005, Geologic Map of the West Half of the Taylor 30x60 Quadrangle: Central Texas Urban Corridor, Encompassing Round Rock, Georgetown, Salado, Briggs, Liberty Hill, and Leander. Bureau of Economic Geology, The University of Texas at Austin. Austin, Texas 78713-8924.

³ https://www2.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer

City of Georgetown Ordinance

No springs were identified on the property during the pedestrian survey, and therefore no occupied site protection, or spring buffer protection measures will be required for this property. One mapped stream occurs in the wastewater line portion of the project area (see Project Geologic Map, sheets 2 & 3), however this channel appears to have been highly modified in the past by the installation two impoundment ponds are present near the headwaters of this draw. This mapped stream consists of a very shallow drainage that was dry and overgrown with vegetation during both site visits, and no flowing water was observed during either site visit in spite of recent rain events. It appears that this drainage may only flow if the two upstream impoundment ponds overflow. Any water that may potentially flow in this short section of this drainage draw, flows to the south into an existing series stormwater control structures and ponds associated with the existing subdivision to the south of this project. In accordance with the Ordinance, the construction of certain improvements may be subject to stated restrictions. This includes wastewater facilities, provided that the wastewater utility shall not be located below the normal highwater elevation within the channel of a stream, except at crossings of the stream.


All regulated activities within the recharge zone must follow water quality best management practices, and development of the property will need to comply with the water quality protection measures as outlined in Section 8 of the Ordinance.

Feature Descriptions

- **F-1** The feature consists of a water well. It is unknown if the well is still actively in use, or if it will be utilized during the proposed development of the tract. The depth of this well is unknown. If the well is not intended to be utilized, it should be properly abandoned by a licensed well driller prior to the construction phase of the project. (GPS: 30.58142, -97.68533)
- **F-2** The feature consists of a closed depression that measures approximately 10 feet in diameter by less than 1 foot deep. The feature is lined with limestone cobbles, bricks, and concrete; appears to be a relic of past land clearing, or other activities, associated with the existing homestead on the property. The feature does not appear to be karst in origin. (GPS: 30.58129, -97.68481)
- **F-3** The feature consists of limestone block cistern, and appears to have been used in the past for livestock or in association with the homestead. (GPS: 30.58184, -97.68411)
- **F-4** The feature consists of a water well. It is unknown if the well is still actively in use, or if it will be utilized during the proposed development of the tract. The depth of this well is unknown. If the well is not intended to be utilized, it should be properly abandoned by a licensed well driller prior to the construction phase of the project. (GPS: 30.58169, -97.68427)
- **F-5** The feature consists of a water well. It is unknown if the well is still actively in use, or if it will be utilized during the proposed development of the tract. The depth of this well is unknown. If the well is not intended to be utilized, it should be properly abandoned by a licensed well driller prior to the construction phase of the project. (GPS: 30.58105, -97.68548)

Fault One fault is mapped as crossing through the wastewater line portion of the project area. No traces of this fault were directly observable in the field, and therefore the location was not verifiable during the survey. This portion of the project area is underlain with thick clayey soils of the Houston Black series. Beneath the thick soil cover, the bedrock geology is mapped as the Del Rio Clay on east (downthrown) side of the fault, and the Georgetown Limestone on the west side of the fault, however no bedrock outcrop was observed in this portion of the project area. (inferred GPS: 30.57435, -97.68161)

Stratigraphic Column for the Approximately 54-acre Chapel Hill Tract



*Shaded areas represent lithologies underlying the project area

	C ASSESSME		T				TIID	E CL	ARACI	EDI			- Long and the	el Hill Tr	EVAL	ΠΔΤ	ION		PHY	SICAL SETTING			
	LOCATION		2A 2B 3			FEA	A		5		6	7	8A	8B	9	10		11		12			
1A FEATURE ID	1B *	1C*	2A FEATURE TYPE	POINTS			NSIONS (I	FEET)	TREND (DEGREES)	5A DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	OTAL SENSITI			ENT AREA RES)	TOPOGRAPHY			
						x	Y	z		10						<40	>40	<1.6	>1.6				
F-1	30.58142	-97.68533	MB	30				-					Х	5	35	Х		Х		Hillside			
F-2	30.58129	-97.68481	CD	5		10	10	1					С	10	15	Х		Х		Hillside			
F-3	30.58184	-97.68411	MB	30							-		Х	5	35	Х		Х		Hillside			
F-4	30.58169	-97.68427	MB	30									Х	5	35	Х		Х		Hillside			
F-5	30.58105	-97.68548	MB	30									Х	5	35	Х		Х		Hillside			
Fault	30.57435	-97.68161	F	20					N20E	10			F,V	5	35	Х		X		Hillside			
	· · · · · · · · · · · · · · · · · · ·		-													-		-	-				
	· · · · ·	-		1			_																
				<u> </u>																			
DATUM: WG	<u> </u>		1		1				I			L	L	I	L			L	L				
TYPE		TYPE		2	B POINTS						84	INFILLIN	NG										
	Cave				30		N None, exposed bedrock																
2	Solution cavity				20	C Coarse - cobbles, breakdown, sand, gravel																	
	Solution-enlarged fra	acture(s)			20	0 Loose or soft mud or soil, organics, leaves, sticks, dark c						ticks, dark co	olors										
	Fault	.,			20		F	Fines	s, compac	ted c	ay-rich	sediment	soil pro	ofile, gray or r	ed colo	s							
	Other natural bedroo	ck features			5		V	Vege	tation. Giv	ve de	tails in n	narrative o	lescripti	on			V Vegetation. Give details in narrative description						

 Other natural bedrock features
 3
 V
 Vegetation. Give details in narrative description

 Manmade feature in bedrock
 30
 FS
 Flowstone, cements, cave deposits

 Swallow hole
 30
 X
 Other materials

 Sinkhole
 20

 Non-karst closed depression
 5
 12 TOPOGRAPHY

 Zone, clustered or aligned features
 30
 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Date: 22 April 2020

Sheet 1 of 1



TCEQ-0585-Table (Rev. 10-01-04)

MB

SW

SH

CD

Z



Feature F-1, water well




Feature F-2, non-karst closed depression lined with limestone cobbles.




Feature F-3, cistern




Feature F-4, well and pressure tank



Feature F-5, well (located inside structure)









dwardsA


top :

Edwards Aquifer Recharge Zone


Kdr

-


















Section III

Organized Sewage Collection System Plan (TCEQ-0582)

Organized Sewage Collection System Application

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Chapel Hill Phase II

 Attachment A – SCS Engineering Design Report. This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

Customer Information

 The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Erik Boraks Entity: AMFP V Chapel Hill II LLC Mailing Address: 13740 Midway Road #804 City, State: Dallas, TX Zip: 75244 Telephone: (972) 385-1676 Fax: _____ Email Address: Erik.Boraks@dukecompanies.com The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: <u>Paul M. Hames, P.E.</u> Texas Licensed Professional Engineer's Number: <u>66791</u> Entity: <u>Stantec Consulting Services Inc.</u> Mailing Address: <u>6080 Tennyson Parkway, Suite 200</u> City, State:<u>Plano, TX</u> Zip: <u>75024</u> Telephone:(<u>214) 538-2483</u> Fax:____ Email Address:<u>Paul.Hames@stantec.com</u>

Project Information

4. Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):

Residential: Number of single-family lots:
Multi-family: Number of residential units: <u>276</u>
🔀 Commercial
Industrial
Off-site system (not associated with any development)
Other:

5. The character and volume of wastewater is shown below:

<u>100</u> % Domestic	<u>197,280</u> gallons/day
<u> %</u> Industrial	gallons/day
<u> %</u> Commingled	gallons/day
Total gallons/day: <u>197,280</u>	

- Existing and anticipated infiltration/inflow is <u>17,425</u> gallons/day. This will be addressed by: <u>The flow listed in Item 5 above includes Inflow & Infiltration</u>. The wastewater pipes have <u>been sized to accommodate this anticipated Inflow & Infiltration</u>.
- 7. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.

The WPAP application for this development was approved by letter dated _____. A copy of the approval letter is attached.

The WPAP application for this development was submitted to the TCEQ on $\frac{1}{12}/2024$, but has not been approved.

A WPAP application is required for an associated project, but it has not been submitted. There is no associated project requiring a WPAP application.

8. Pipe description:

Table 1 - Pipe Description

Pipe Diameter(Inches)	Linear Feet (1)	Pipe Material (2)	Specifications (3)
6"	523	SDR 26 PVC	ASTM 3034; ASTM 2241
8"	1923	SDR 26 PVC	ASTM 3034; ASTM 2241

Total Linear Feet: 2446

- (1) Linear feet Include stub-outs and double service connections. Do not include private service laterals.
- (2) Pipe Material If PVC, state SDR value.
- (3) Specifications ASTM / ANSI / AWWA specification and class numbers should be included.
- 9. The sewage collection system will convey the wastewater to the San Gabriel (name) Treatment Plant. The treatment facility is:



10. All components of this sewage collection system will comply with:

🔀 The City of Georgetown standard specifications. Other. Specifications are attached.

11. \square No force main(s) and/or lift station(s) are associated with this sewage collection system.

A force main(s) and/or lift station(s) is associated with this sewage collection system and the Lift Station/Force Main System Application form (TCEQ-0624) is included with this application.

Alignment

- 12. X There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.
- 13. 🛛 There are no deviations from straight alignment in this sewage collection system without manholes.
 - Attachment B Justification and Calculations for Deviation in Straight Alignment without Manholes. A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.

For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.

Manholes and Cleanouts

14. X Manholes or clean-outs exist at the end of each sewer line(s). These locations are listed below: (Please attach additional sheet if necessary)

Line	Shown on Sheet	Station	Manhole or Clean- out?
WW-A	31 Of 45	10+00.00	Manhole
WW-A	31 Of 45	10+74.73	Drop Manhole
WW-A	31 Of 45	12+78.72	Manhole
WW-A	31 Of 45	14+19.61	Manhole

Table 2 - Manholes and Cleanouts

Line	Shown on Sheet	Station	Manhole or Clean- out?
WW-A	31 Of 45	16+20.95	Manhole
WW-A-1	31 Of 45	10+02.14	Cleanout
WW-A-2	31 Of 45	10+00.00	Cleanout
WW-A-3	31 Of 45	10+00.00	Cleanout
WW-A-4	31 Of 45	10+00.00	Cleanout
WW-B	31 Of 45	10+72.37	Manhole

- 15. Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.
- 16. The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
≥54	2000

- Attachment C Justification for Variance from Maximum Manhole Spacing. The maximum spacing between manholes on this project (for each pipe diameter used) is greater than listed in the table above. A justification for any variance from the maximum spacing is attached, and must include a letter from the entity which will operate and maintain the system stating that it has the capability to maintain lines with manhole spacing greater than the allowed spacing.
- 17. All manholes will be monolithic, cast-in-place concrete.
 - The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

Site Plan Requirements

Items 18 - 25 must be included on the Site Plan.

18. \square The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1'' = 40'.

19. The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.

- 20. Lateral stub-outs:
 - \boxtimes The location of all lateral stub-outs are shown and labeled.

No lateral stub-outs will be installed during the construction of this sewer collection system.

- 21. Location of existing and proposed water lines:
 - \boxtimes The entire water distribution system for this project is shown and labeled.

If not shown on the Site Plan, a Utility Plan is provided showing the entire water and sewer systems.

- There will be no water lines associated with this project.
- 22. 100-year floodplain:
 - After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)

After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 3 - 100-Year Floodplain

Line	Sheet	Station
	of	to

23. 5-year floodplain:

After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concrete-lined channels constructed above sewer lines.)

After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concretelined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

Line	Sheet	Station
	of	to

- 24. \boxtimes Legal boundaries of the site are shown.
- 25. The *final plans and technical specifications* are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must be included on the Plan and Profile sheets.

- 26. All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.
 - There will be no water line crossings.
 - There will be no water lines within 9 feet of proposed sewer lines.

Table 5 - Water Line Crossings

Line	Station or Closest Point	Crossing or Parallel	Horizontal Separation Distance	Vertical Separation Distance
WW-A	12+31	Crossing	0	4.26'
WW-A	12+46	Crossing	0	3.21'
WW-A	13+26	Crossing	0	1.33'
WW-A	14+80	Crossing	0	2.35'
WW-B	14+33	Crossing	0	3.35'
WW-B	14+74	Crossing	0	1.48'
WW-C	10+16	Crossing	0	1.03'

27. Vented Manholes:

No part of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.

A portion of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.

A portion of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.

A portion of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.

Table 6 - Vented Manholes

Line		Manhole Station	Station	Sheet	

Line	Manhole	Station	Sheet

28. Drop manholes:

There are no drop manholes associated with this project.

Sewer lines which enter new or existing manholes or "manhole structures" higher than 24 inches above the manhole invert are listed in the table below and labeled on the appropriate profile sheets. These lines meet the requirements of 30 TAC §217.55(I)(2)(H).

Table 7 - Drop Manholes

Line	Manhole	Station	Sheet
WW-A	4' MH; 3.6' Drop	10+74.73	31 of 45
WW-D-1	4' MH; 4.2' Drop	10+06.57	31 of 45

29. Sewer line stub-outs (For proposed extensions):

The placement and markings of all sewer line stub-outs are shown and labeled.

No sewer line stub-outs are to be installed during the construction of this sewage collection system.

30. Lateral stub-outs (For proposed private service connections):

The placement and markings of all lateral stub-outs are shown and labeled.

No lateral stub-outs are to be installed during the construction of this sewage collection system.

31. Minimum flow velocity (From Appendix A)

Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.

32. Maximum flow velocity/slopes (From Appendix A)

Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.

Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second. Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

Table 8 - Flows Greater Than to Feet per Second						
Line	Profile Sheet	Station to Station	FPS	% Slope	Erosion/Shock Protection	

Table 8 - Flows Greater Than 10 Feet per Second

33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provisions noted below have been made to protect against pipe displacement by erosion and/or shock under 30 TAC §217.53(I)(2)(B).

Concrete encasement shown on appropriate Plan and Profile sheets for the locations listed in the table above.

 Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on appropriate Plan and Profile sheets for the locations listed in the table above.
 N/A

Administrative Information

- 34. The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
- 35. Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

Standard Details	Shown on Sheet
Lateral stub-out marking [Required]	35 of 45
Manhole, showing inverts comply with 30 TAC §217.55(I)(2) [Required]	35 of 45
Alternate method of joining lateral to existing SCS line for potential future connections [Required]	35 of 45
Typical trench cross-sections [Required]	34 of 45
Bolted manholes [Required]	35 of 45
Sewer Service lateral standard details [Required]	35 of 45
Clean-out at end of line [Required, if used]	35 of 45
Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps]	n.a. of n.a.

Table 9 - Standard Details

Standard Details	Shown on Sheet
Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed]	of
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used]	n.a. of n.a.
Drop manholes [Required, if a pipe entering a manhole is more than 24 inches above manhole invert]	35 of 45

36. All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.

- 37. All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
 - Survey staking was completed on this date: <u>TBD</u>
- 38. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 39. Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: Paul M. Hames, P.E.

Date: <u>2/01/2024</u>

Place engineer's seal here:

Paul M. Ha

2/01/2024



Signature of Licensed Professional Engineer:

fand M. Homes

Appendix A-Flow Velocity Table

Flow Velocity (Flowing Full) All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Pipe Diameter(Inches)	% Slope required for minimum flow velocity of 2.0 fps	% Slope which produces flow velocity of 10.0 fps
6	0.50	12.35
8	0.33	8.40
10	0.25	6.23
12	0.20	4.88
15	0.15	3.62
18	0.11	2.83
21	0.09	2.30
24	0.08	1.93
27	0.06	1.65
30	0.055	1.43
33	0.05	1.26
36	0.045	1.12
39	0.04	1.01
>39	*	*

Table 10 - Slope Velocity

*For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

Where:

v = velocity (ft/sec)
n = Manning's roughness coefficient
(0.013)
Rh = hydraulic radius (ft)
S = slope (ft/ft)

I			
Line	Sheet	Station	Manhole/Cleanout
WW-A	31 Of 45	10+00.00	Manhole
WW-A	31 Of 45	10+74.73	Drop Manhole
WW-A	31 Of 45	12+78.72	Manhole
WW-A	31 Of 45	14+19.61	Manhole
WW-A	31 Of 45	16+20.95	Manhole
WW-A-1	31 Of 45	10+02.14	Cleanout
WW-A-2	31 Of 45	10+00.00	Cleanout
WW-A-3	31 Of 45	10+00.00	Cleanout
WW-A-4	31 Of 45	10+00.00	Cleanout
WW-B	31 Of 45	10+72.37	Manhole
WW-B	31 Of 45	12+33.91	Manhole
WW-B	31 Of 45	14+67.93	Manhole
WW-B	31 Of 45	15+85.82	Manhole
WW-B	31 Of 45	16+57.06	Manhole
WW-B-1	31 Of 45	10+00.00	Manhole
WW-B-2	31 Of 45	10+00.00	Cleanout
WW-C	31 Of 45	11+72.13	Manhole
WW-C	31 Of 45	13+61.10	Manhole
WW-C	31 Of 45	15+23.29	Manhole
WW-C-1	31 Of 45	10+00.00	Cleanout
WW-C-2	31 Of 45	10+00.00	Cleanout
WW-C-3	31 Of 45	10+00.00	Cleanout
WW-D	31 Of 45	11+04.86	Manhole
WW-D-1	31 Of 45	10+06.57	Drop Manhole
WW-D-1	31 Of 45	10+16.91	Cleanout
WW-D-2	31 Of 45	10+00.00	Cleanout

Line	Sheet	Station	Crossing Utility	Vert Separation
WW-A	31 Of 45	12+31	6" Water	4.26
WW-A	31 Of 45	12+46	6" Water	3.21
WW-A	31 Of 45	13+26	6" Water	1.33
WW-A	31 Of 45	14+80	6" Water	2.35
WW Lat A-3	31 Of 45	10+64	8" Water	2.32
WW-B	31 Of 45	14+33	6" Water	3.35
WW-B	31 Of 45	14+74	8" Water	1.48
WW-C	31 Of 45	10+16	8" Water	1.03
WW Lat C-3	31 Of 45	10+32	8" Water	1.51
WW Lat D-2	31 Of 45	10+30	8" Water	1.08

ATTACHMENT 3A

SCS Final Engineering Design Report

TAC.30.1.217. A §217.10. §217.10 (f)-1

Location:

The following report was prepared to summarize the onsite wastewater design for the proposed Chapel Hill Phase II Development. Chapel Hill Phase II is a multi-family/commercial development in Georgetown, TX on a 17.425-acre site platted as Lot 1 of Chapel Hill Subdivision Section Two. The project will consist of 10 apartment buildings, totaling 276 units, and an amenity center.

The proposed site is located on the north side of Westinghouse Road at 403 Westinghouse Road, Georgetown, Texas 78626, immediately west of Chapel Hill Phase I. The Celebration Church is located just north of the site. The site has vehicular access to Westinghouse via an offsite drive through the Phase I development.

As required by the City of Georgetown, the developer previously constructed an offsite wastewater interceptor that connects Phase I and Phase II to an existing City of Georgetown lift station (the Westinghouse South Reginal Lift Station) located approximately 3,500 LF to the south of the Chapel Hill Phase I site. The downstream wastewater collection system has been sized and designed to accommodate the development's wastewater flow, as well as the wastewater flows from several of the downstream properties within the City of Georgetown's sewershed to this lift station. The design of the offsite and Phase I wastewater systems are included in an Organized Sewer Collection System application submitted to TCEQ by Halff in June 2020.

TAC.30.1.217.A §217.10 (f)-2

Existing Conditions:

The Chapel Hill Phase II site is located inside the City of Georgetown's city limits and has driveway access to Westinghouse Road to the south via an offsite drive through Phase I. The site is vacant and has been cleared of internal fences. A large stock pond is in the southwest corner of the site.

The site generally slopes from northeast to southwest with slopes ranging from 5%-15%. An onsite drainage channel slopes from the northeast corner of the site to the stock pond, with slopes ranging from 3%-8%.

There is an existing 8-inch wastewater main stubbed up from Phase I at the southeast corner of the site to which the proposed Phase II wastewater system will connect and be carried through Phase I to the Westinghouse South Regional Lift Station located approximately 0.75 miles to the south. This lift station ultimately connects to the San Gabriel Wastewater Treatment Plant (WWTP).

Proposed Conditions:

The 17.425-acre site is known as Lot 1 of Chapel Hill Subdivision Section Two. This project consists of the construction of 10 apartment buildings and amenity center on Lot 1, with associated drives, parking, sidewalks, drainage, and utilities. Onsite detention and water quality ponds will be constructed, plus an offsite detention and water quality pond will be constructed to the southwest of the site for commercial development in the future.

The proposed Phase II wastewater system is a combination of 8-inch diameter trunk lines with 6-inch diameter laterals that will collect gravity flow and connect to an existing 8-inch private wastewater gravity line stubbed up from the Phase I site to the south. This flow passes through the existing Phase I system which connects to the existing wastewater interceptor, owned, and maintained by the City of Georgetown, which conveys sewage approximately 4,700 LF to the south to the existing Westinghouse South Regional Lift Station. The interceptor was designed to collect developed flows from Lots 1, 2, 3, and 4, as well as the neighboring properties to the west of the site and several other properties within the sewershed (see OSCS application prepared by Halff, June 2020). The interceptor ranges in diameter from 8-inches to 12-inches until it connects to an existing 12-inch wastewater line which connects to the lift station.

Several water and wastewater crossings are proposed that do not meet the requirement of 9 feet horizontal and vertical separation. The 9-foot separation distance would require excessive depths of the wastewater line and, in some cases, would not be feasible to drain via gravity. As such, appropriate crossings have been designed meeting the requirements set forth within Chapter 217.53 and Chapter 290.44.

TAC.30.1.217.A §217.10 (f)-3_

Design Flow Determination:

The proposed Phase II development on Lot 1 includes a total of 276 units. For conservative design purposes, each apartment unit was assigned a Living Unit Equivalent (LUE) of 0.75 per unit. Each LUE was set to equal 2.5 persons, with each person using 100 gallons/day or 250 gallons/day/LUE (see equation 1). The Average Dry Weather Flow (ADWF) from the Phase II site was calculated to be 51,750 gpd. Using a Peaking Factor of 3.48 (see equation 2), the Peak Dry Weather Flow (PDWF) was calculated to be 179,974 gpd (see equation 3).


 $1 \text{ LUE} = 250 \frac{\text{gallons}}{\text{day}} = 100 \frac{\text{gal}}{\text{persons * day}} * 2.5 \text{ persons (Equation 1)}$

Peaking Factor (PF) = $2.8 * ADWF(MGD)^{-0.0732}$ (Equation 2) PDWF = ADWF * PF (Equation 3) The Peak Wet Weather Flow (PWWF)was determined using an Inflow & Infiltration factor of 1,000 gallons/acre/day. Based on the site acreage of 17.425, the PWWF calculates to be 137 gpm, including Inflow & Infiltration. A table of the calculations is below.

2/1/2024

CHAPEL HILL PHASE II - SCS WASTEWATER

1	2	3	4	5	6	7	8	9	10
UNITS	LUE Conversion	LUEs	Avg Dry Weather Flow (Gal per Day)	Avg Dry Weather Flow (MGal per Day)	Peaking Factor (PF)	Peak Dry Weather Flow (Gal per Day)	Estimated Area (Acres)	RD I & I (Gal per Day)	Peak Wet Weather Flow (Gal per Minute)
276	0.75 LUE/Unit	207	51,750	0.0518	3.48	179,974	17.425	17,425	137
			250 Gal/Day/LUE		2.8xADWF^-0.0732	ADWF x PF		(1000 gal/acre/day)	(7+9) / 1440
									Gal per Day 197,399



The design flow for properties to the south of Chapel Hill was provided by the City of Georgetown via a sewershed model performed by their consulting engineer utilizing the same

basis principals as presented above but with a slightly less peaking factor. The city does not typically model smaller diameter collection lines which are expected to have a higher peaking factor near the source of the flow. Their model attenuates the flow resulting in lower modeled numbers than the strict equations presented above. The city also utilizes an Inflow and Infiltration factor of 750 gallons per acre per day in lieu of 1,000 gallons. The city feels comfortable with 750 gallons because they are routinely looking at larger basins, which can balance out versus smaller pockets of acreage. As development matures, the city has much stricter requirements to maintain a tight system and keep inflow and infiltration low due to the TCEQ Edwards Aquifer Recharge Zone rules. The model results provided by the city is displayed below and calculates to a total of 2.0728 million gallons per day (MGD).

TAC.30.1.217.A §217.10 (f)-4

Minimum and Maximum Grades:

Using the City of Georgetown's Unified Development Code, the minimum pipe diameter of 8 inches was used for all mains within Lot 1. The 8-inch diameter pipe size is the minimum size specified throughout the entire project, excluding service laterals. TCEQ requires

a minimum slope of no less than 0.33% and a maximum allowable slope of 8.40% for 8-inch diameter pipes. All pipe segments designed within the construction documents fall within these acceptable ranges. The pipe material for all wastewater mains is designated as PVC (ASTM D2241 or D3034, SDR 26).

TAC.30.1.217.A §217.10 (f)-5

Analysis of the offsite pipe network is not applicable.

TAC.30.1.217.A §217.10 (f)-6

Existing System Impact:

Based on information and direction provided by the City of Georgetown, the existing 12-inch stub out to the lift station is sufficient in handling the incoming flows from this and other developments. The City of Georgetown instructed that the flows produced by the subject site and the surrounding properties within the sewershed will have no adverse impacts to the downstream system.

TAC.30.1.217.A §217.10 (f)-7

Inflow & Infiltration:

Using the inflow and infiltration expectation of 1,000 gallons/acre/day from the City of Georgetown's wastewater design criteria, the anticipated Inflow & Infiltration over the 17.425acre Phase II development is calculated to be 17,425 gallons/day considering the applicable drainage area to the site's wastewater lines. The remaining properties within the sewershed utilized a rate of 750 gallons/ac/day per the City of Georgetown's sewershed model. The added flows from inflow and infiltration for each line segment were taken into consideration with the calculation of the peak wet weather design flows. The hydraulic effect of the inflow and infiltration on the proposed onsite system is minor in relation to the wastewater line sizes required by the City of Georgetown. There will be no proposed inflow and infiltration flow rate monitoring systems installed, nor will there be any inflow and infiltration abatement measures taken.

TAC.30.1.217. A.§217.10 (f)-8

Trunk/Interceptor:

The proposed offsite and onsite wastewater pipes range from 8-inch to 12-inch PVC SDR 26 lines. Based on calculations for the proposed wastewater lines and information and direction from the City of Georgetown, the proposed wastewater collection system and the Westinghouse South Regional Lift Station will be able to handle the peak flow.

TAC.30.1.217. A.§217.10 (f)-9

Treatment Facility:

Based on the expected design flows and the direction provided by the City of Georgetown, the existing San Gabriel WWTP will have the capacity and capabilities of treating the proposed

wastewater flows produced by the proposed development.

TAC.30.1.217. A.§217.10 (f)-10

Structural Analysis:

Due to the Organized Sewage Collection System (SCS) meeting all the necessary requirements in TAC.30.1.217. C. §217.53. k.4, a structural analysis was deemed unnecessary.

TAC.30.1.217. A.§217.10 (f)-11

Future Expansion:

The sewage collection system within this project is designed for the proposed improvements associated with ultimate development of the property, as well as the ultimate development of the surrounding properties within the sewershed of the Westinghouse South Regional Lift Station. Future service lines will mainly be constructed within private developments accounted for within the City's model.

TAC.30.1.217. A.§217.10 (f)-12

Lift Station Calculations:

Not Applicable. The SCS does not include a lift station.

TAC.30.1.217. A.§217.10 (f)-13

Safety Considerations:

The project design incorporated numerous safety considerations. Security fences will be used throughout the project's boundary to prevent any passerby from accidentally entering an active construction zone. All trenches that require a depth of larger than 5 feet will follow the trenching and excavation safety guidelines set forth by OSHA. There will be no blasting on the entire construction site. The wastewater manholes are spaced less than the maximum allowed TCEQ spacing and allow appropriate ventilation throughout to prevent odor buildup. All buried pipe is set at a reasonable depth to prevent excessive excavation while serving the adjacent properties with appropriate depths. There are no tight workspaces throughout the entire jobsite. Traffic control will be implemented by the Contractor while work is conducted near Westinghouse Road and Mays Street

Section V

Temporary Stormwater Section (TECQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Paul M. Hames, P.E.

Date: 2/01/2024

Signature of Customer/Agent:

M. Homes

Regulated Entity Name: Chapel Hill Phase II

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: <u>Potential for</u> <u>diesel fuel, gasoline, lubricants, and paint.</u>

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

TCEQ-0602 (Rev. 02-11-15)

Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
 Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ

- prior to moving the tanks onto the project. Fuels and hazardous substances will not be stored on the site.
- 2. Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

- For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>Brushy Creek</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

		A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
		A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
		A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
		A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	\square	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
		Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
		There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.		Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10		Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
		 down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

- 11. Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
 - 🗌 N/A
- 12. Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. 🖂 Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. \square All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A – SPILL RESPONSE ACTIONS

Good Housekeeping and Material Management Practices shall include, but are not limited to the following:

- Neat and orderly storage of any chemicals, pesticides, fertilizers, fuels, etc., that are being stored on site. All storage tanks will be above ground, have a maximum storage capacity of 250 gallons and be stored on site for less than one (1) year. Aboveground storage tanks (ASTs) shall comply with Title 30 TAC, Chapter 334, Subchapter F and will be located within the respective phase's Stockpiling Area as illustrated on the Erosion and Sedimentation Control Plans included with this submittal.
- Regular garbage, rubbish, construction waste and sanitary waste disposal.
- Prompt cleanup of any spills that have occurred of liquid or dry materials.
- Cleanup of sediments that have been tracked by vehicles or have been transported by wind or storm water about the site or onto nearby roadways.

In addition to the Good Housekeeping and Material Management Practices, discussed in the previous sections of this plan, the following practices will be followed for spill prevention and clean up.

- Manufacturer's recommended methods of spill cleanup will be clearly posted, and site personnel will be made aware of the procedures and the location of the information and the cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the materials storage area onsite. Equipment and materials will include but are not limited to brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, plastic, and metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery.
- The spill area will be kept well ventilated, and personnel will wear appropriate clothing to prevent injury from contact with a hazardous substance.
- Spills of toxic or hazardous material will be reported to the appropriate State or Local government agency, regardless of the size.
- The spill prevention plan will be adjusted to include measures to prevent this type of spill from recurring and how to clean up the spill if there is another one. A description of the spill, what caused it, and the cleanup measures will also be included.
- The site superintendent responsible for the day-to-day site operations will be the spill prevention and cleanup coordinator. He will designate at least three (3) other site personnel who will receive spill prevention and cleanup training. These individuals will each become responsible for a particular phase of prevention and cleanup. The names of responsible spill personnel will be posted in the material storage area and in the office trailer onsite.

• Any hydrocarbon or hazardous material spill should be reported to the TCEQ at the following 24-hour toll free number 1-800-832-8224.

The Contractor shall notify the agency as soon as possible whenever necessary to provide information that would trigger a change in the response to the spill or discharge. If the discharge or spill creates an imminent health threat, the Contractor shall immediately notify and cooperate with local emergency authorities.

The Contractor will cooperate with the local emergency authority in providing support to implement appropriate notification and response actions. The local emergency authority, as necessary, will implement its emergency management plan, which may include notifying and evacuating affected personnel. In the absence of a local emergency authority, the Contractor shall take reasonable measure to notify potentially affected persons of the imminent health threat.

As soon as possible, but no later than two (2) weeks after discovery of the spill or discharge, the Contractor shall reasonably attempt to notify the Owner (if identifiable) or Occupant of the property upon which the discharge or spill occurred as well as the occupants of any property that the Contractor believes is adversely affected.

ATTACHMENT B -- POTENTIAL SOURCES OF CONTAMINATION

Asphalt products will be used on this project. After placement of asphalt, emulsion, or coatings, the applicant will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt curing time, the applicant should maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur.

Sediment and soil from disturbed areas are another potential source of contamination. During activities causing soil disturbance, temporary best management practices outlined in *Attachment D*, shall be followed to prevent discharge of sediment to North Fork San Gabriel River.

Other potential sources of contamination include hydraulic fluid and diesel fuel from mechanical equipment, as well as paints and chemicals used on site. Any spills shall be handled according to the Spill Response Actions in **Attachment A**.

ATTACHMENT C – SEQUENCE OF MAJOR ACTIVITIES

The project includes 17.425 acres of areas to be disturbed for the development. The location of the temporary erosion control measures are shown on the Erosion & Sedimentation Control sheets.

- 1) Install erosion controls as indicated on approved plan. (17.425 acres)
- 2) Prior to beginning construction, the owner or his authorized representative shall convene a Pre-Construction Conference between the TCEQ, City of Georgetown, consulting engineer, contractor, and any other affected parties. Notify the TCEQ at least 48 hours prior to the time of the conference and 48 hours prior to the beginning of construction. On-site Pre-Construction meeting should be held with Contractor, TCEQ, Engineer, and Owner.
- 3) Install tree protection and initiate tree mitigation measures. (1072 LF)
- 4) Contact the City of Georgetown Planning Department to schedule the on-site preconstruction coordination meeting.
- 5) Evaluate temporary erosion control installation. Review construction schedule with the water quality plan requirements and the erosion control plan.
- 6) Begin Site Cleaning. (17.425 acres)
- 7) Rough grade batch detention ponds and construct structural detention pond walls & outlet structures. (0.81 acres)
- 8) Rough grade site. Inspect and maintain all controls as per general notes. (17 acres)
- 9) Construct site utilities. (10075 LF)
- 10) Schedule and attend mid-construction on-site meeting to coordinate changes in construction schedule and evaluate effectiveness of erosion control plan (city inspector, project engineer, general contractor, environmental project manager). Identify anticipated completion date and coordinate final construction sequence and inspection schedule with environmental inspector.
- 11) Construct paving, parking, and buildings. (10.08 acres)
- 12) Final construction of batch detention ponds. (0.81 acre)
- 13) Complete construction and install landscaping.
- 14) Revegetate disturbed areas and clean out permanent controls and install filter media or complete a developer's contract for the revegetation along with the engineer's concurrence letter.
- 15) Project engineer inspects job and writes concurrence letter to the city. Final Inspection is scheduled upon receipt of letter.
- 16) Upon revegetation per City of Georgetown requirements, remove temporary erosion/sedimentation controls.

ATTACHMENT D -- TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

Temporary Best Management Practices (BMPs) and measures will be used during construction to prevent pollution of groundwater, surface water and naturally occurring environmental features. Silt fence, inlet protection, stabilized construction entrance and construction stockpiling areas will be installed prior to beginning construction and prior to commencement of any of the activities defined in the sequence of construction as **Attachment C**. Inspection and maintenance of the on-site controls shall be performed during the site clearing and rough grading process. The perimeter fence shall be regularly monitored to ensure that the buffers remain no-construction zones until the site work has been completed and authorization has been granted by the engineer. Please reference attached copy of the Erosion and Sedimentation Control Plans for specific controls and details.

BMPs and measures will prevent pollution of surface water or groundwater that originates on site or flows off-site, including pollution caused by contaminated stormwater run-off from the site, through the use of silt fences placed immediately downstream of disturbed areas. To minimize destruction to any portion of the Recharge Zone, on-site perimeter silt fence will also be implemented for pertinent areas throughout the entirety of construction. The Contractor is expected to inspect the controls weekly and after significant rainfalls to ensure proper function. When silt accumulates six (6) inches in depth the Contractor shall promptly remove the silt from the controls. As noted earlier, the proposed water quality pond will be used to treat storm water from the construction of the site. The water quality facility shall be properly inspected throughout construction and restored upon completion of the respective phase.

BMPs and measures will prevent pollutants from entering surface streams or the aquifer by intercepting stormwater potentially carrying sediment and other pollutants. BMPs and measures will implement one (1) stabilized construction entrance and a construction stockpiling/staging area to help minimize pollutant run-off and erosion generated during construction. Paved streets and driveways adjacent to these sites will be cleaned regularly to remove excess mud, dirt or rock tracked from the site. Sedimentation will be concentrated only in these areas for efficient maintenance. Water trucks will be on-site as necessary to aid in controlling dust. No setbacks were proposed for the site; however, BMPs will be implemented to limit/prevent contaminated inflow from entering surface streams or the aquifer. These practices are to include the following measures: the use of silt fence, triangular filter dikes and vegetative buffer zones. The fabricated silt fence barricade, triangular filter dikes and natural living filter vegetative buffer will provide help to reduce the likelihood of contaminated runoff from entering the aquifer. If any sensitive features are identified by TCEQ inspections, or during excavation or construction, measures appropriate to the sensitivity of the discovered feature will be enacted. No blasting is proposed.

Temporary Erosion and Sedimentation Notes:

- 1. The Contractor shall maintain, install erosion/sedimentation controls and tree/natural protective fencing prior to any site preparation work (clearing, grubbing or excavation).
- 2. The placement of erosion/sedimentation controls and tree/natural area protective fencing shall be in accordance with the City of Georgetown's current Code of Ordinances and the approved Erosion and Sedimentation Control Plan. No erosion controls shall be placed beyond the property lines of the site unless written permission has been obtained from adjacent property Owners.

- 3. A pre-construction conference shall be held on-site with the Contractor, design engineer/permit applicant and Environmental Inspector after installation of the erosion/sedimentation and tree/natural area protection measures and prior to beginning any site preparation work. The Contractor shall notify the Environmental Inspector at least three (3) days prior to the meeting date.
- 4. Any major variation in materials or locations of controls or fences from those shown on the approved plans will require a revision and must be approved by the reviewing engineer, environmental specialist, or city arborist as appropriate. Minor changes to be made as field revisions to the Erosion and Sedimentation Control Plan may be required by the Environmental Inspector during the course of construction to correct control inadequacies.
- 5. The Contractor is required to inspect the controls at weekly intervals and after significant rainfall events to ensure that they are functioning properly. The person(s) responsible for maintenance of controls shall immediately make any necessary repairs to damaged areas. Silt accumulation at controls must be removed when the depth reaches six (6) inches.
- 6. Prior to final acceptance by the City of Georgetown, haul roads and waterway crossing constructed for temporary Contractor access must be removed, accumulated sediment removed from the waterway and the area restored to the original grade and revegetated. All land clearing debris shall be disposed of in approved spoil disposal sites.
- 7. All work must stop if a void in the rock substrate is discovered, which is one (1) square foot in total area, blows air from within the substrate, and/or consistently received water during any rain event. At this time, it is the responsibility of the project manager to immediately contact an Environmental Inspector for further investigation.
- 8. Erosion control measures, site work and restoration work shall be in accordance with the City of Georgetown Erosion and Sedimentation Control Ordinance.
- 9. All slopes shall be sodded or seeded with approved grass, grass mixtures or ground cover suitable to the area and season in which they are applied.
- 10. Silt fences, rock berms, sedimentation basins and similarly recognized techniques and materials shall be employed during construction to prevent point source sedimentation loading of downstream facilities, such installation shall be regularly inspected by the City of Georgetown for effectiveness. Additional measures may be required if, in the opinion of the City Engineer, they are warranted.
- 11. All temporary erosion control measures shall not be removed until final inspection and approval of the project by the engineer. It shall be the responsibility of the Contractor to maintain all temporary erosion control structures and to remove each structure as approved by the engineer.
- 12. Any dirt, mud, rocks, debris, etc., that is spilled, tracked, or otherwise deposited on any existing paved street shall by cleaned up immediately.

ATTACHMENT E – REQUEST TO SEAL FEATURES

No environmental features are being temporarily sealed. Therefore, this section is not applicable.

ATTACHMENT F – STRUCTURAL PRACTICES

Silt fencing will be placed on the down gradient side of any exposed soils to limit the discharge of silt and pollutant form exposed areas of the site. Additionally, triangular filter dikes will be placed down gradient of areas that may require dewatering. Dewatering shall be directed toward the water quality pond and/or filter dikes to limit the discharge of silt and pollutants from exposed areas of the site. Also included are stabilized construction entrances to reduce the amount of mud tracked onto surrounding streets by construction vehicles. Inspection and maintenance of the onsite controls shall be performed during the site clearing and rough grading process.

Additionally, the use of the pond will also protect against contaminated runoff leaving the site. The Contractor will be responsible for proper inlet protection in addition to cleaning out all structures adversely affected by sediment after heavy rainfalls.

ATTACHMENT G – DRAINAGE AREA MAPS

The drainage area maps are provided in the Chapel Hill Phase 2 plan set.

ATTACHMENT H – TEMPORARY SEDIMENT POND PLANS AND CALCULATIONS

Temporary sediment pond plans and calculations were prepared in acceptance with TCEQ and TPDES requirements. Please see the TCEQ Water Quality Calculations Sheet in the plan set for reference.

ATTACHMENT I – INSPECTION AND MAINTENANCE FOR BEST MANAGEMENT PRACTICES

The following sections address inspection and maintenance taken from the TNRCC Manual, "Complying with Edward Aquifer Rules: Technical Guidance on Best Management Practices."

Silt Fence:

- 1. Inspection shall be made weekly and after each rainfall event, in accordance with Section 1.4.3 of RG-348.
- 2. Torn fabric shall be replaced or a second line of fencing parallel to the torn section shall be implemented as needed.
- 3. Accumulated silt shall be removed when it reaches a depth of six (6) inches. The silt shall be disposed of on an approved site and in such a manner that will not contribute to additional siltation.
- 4. Silt fence shall be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.

Inlet Protection:

- 1. Daily inspection shall be made by the Contractor and silt accumulation must be removed when depth reaches 50 mm (two (2) inches).
- 2. Contractor shall monitor the performance of inlet protection during each rainfall event and immediately remove the inlet protections if the stormwater begins to overtop the curb.
- 3. Inlet protections shall be removed as soon as the source of sediment is stabilized.

Stabilized Construction Entrance:

- The entrance shall be maintained in a condition that will prevent tracking or flowing of sediment onto public roadway. This may require periodic top dressing with additional stone as conditions demand. As well as repair and clean out of any measure device used to trap sediment. All sediments that are spilled, dropped, washed, or tracked onto public roadway must be removed immediately.
- 2. Entrance shall be properly graded to prevent run-off from leaving the construction site.

Concrete Washout Area:

- 1. Routine inspection in accordance with Section 1.4.18 of RG-348 of the area to ensure that sufficient quantity and volume remain to contain all liquid and concrete waste generated by washout operations.
- 2. Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

3. When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions, or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.

ATTACHMENT J – SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

Prior to commencing construction, all temporary erosion and sedimentation (E&S) control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. Controls specified in the SWPPP section of the approved Edwards Aquifer Contributing Zone Plan are required during construction. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. The controls must remain in place until disturbed areas are revegetated, and the areas have become permanently stabilized. *

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. *

Please see the Erosion & Sedimentation Control Plan Notes and Details Sheet of the attached construction plans for more details.

(*see General Notes for Edwards Aquifer Recharge Zone Plan)

Section VI

Agent Authorization Form (TCEQ-0599)

Agent Authorization Form For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999
1 Robert J. Sone III. Other (Autorized Acent
Title - Owner/Fresident/Other
of AMFP V Chapel Hill II LLC Corporation/Partnership/Entity Name
have authorized Paul M. Hames, P.E Print Name of Agent/Engineer
of Stantec Consulting Services Print Name of Firm

to represent and act on the behalf of the above-named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Dat

THE STATE OF Torran §

County of Darlar §

BEFORE ME, the undersigned authority, on this day personally appeared $\underline{h_{bu+1}}$, $\underline{s_{bu+1}}$, $\underline{s_{bu+1}}$, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this <u>12</u>th day of <u>Jon way</u>, 2004

DEN M. DAVID Notary Public, State of Texas Comro, Expires 07-15-2025 Hotary ID 129489196

NOTARY PUBLIC

Ben M, Dau J Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 7-15-24

Section VII

Application Fee Form (TCEQ-0574)

Application Fee Form

Texas Commission on Environme							
Name of Proposed Regulated Entity: <u>Chapel Hill Phase II</u>							
Regulated Entity Location: 403 We	estinghouse Road, Georg	getown, Texas 78626					
Name of Customer: AMFP V Chap	<u>el Hill II LLC</u>						
Contact Person: <u>Erik Boraks</u>	Phone	e: <u>(972) 385-1676</u>					
Customer Reference Number (if is	ssued):CN						
Regulated Entity Reference Numb	oer (if issued):RN <u>111787</u>	<u>'560</u>					
Austin Regional Office (3373)							
Hays	Travis	🖂 Wil	liamson				
San Antonio Regional Office (336	2)						
Bexar	Medina	Uva	lde				
 Comal	 Kinney						
Application fees must be paid by o	check, certified check, or	⁻ money order, payable	e to the Texas				
Commission on Environmental Q	uality. Your canceled ch	eck will serve as your	receipt. This				
form must be submitted with you	u r fee payment . This pa	yment is being submit	ted to:				
🔀 Austin Regional Office	an Antonio Regional Office						
Mailed to: TCEQ - Cashier	Ov	vernight Delivery to: TCEQ - Cashier					
Revenues Section	12	2100 Park 35 Circle					
Mail Code 214	Bu	uilding A, 3rd Floor					
P.O. Box 13088	Au	ıstin, TX 78753					
Austin, TX 78711-3088	(53	12)239-0357					
Site Location (Check All That App	ly):						
🔀 Recharge Zone	Contributing Zone	🔀 Transiti	ion Zone				
Type of Pla	an	Size	Fee Due				
Water Pollution Abatement Plan	, Contributing Zone						
Plan: One Single Family Resident	ial Dwelling	Acres	\$				
Water Pollution Abatement Plan	, Contributing Zone						
Plan: Multiple Single Family Resi	dential and Parks	Acres	\$				
Water Pollution Abatement Plan	, Contributing Zone						
Plan: Non-residential	Acres	\$					
Sewage Collection System		2446 L.F.	\$ 1223				
Lift Stations without sewer lines		Acres	\$				
Underground or Aboveground St	torage Tank Facility	Tanks	\$				
Piping System(s)(only)		Each	\$				
Exception		Each	\$				
Extension of Time		Fach	C				
		Each	\$				

Signature: Paul M. House

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	< 1	\$3,000
institutional, multi-family residential, schools, and	1 < 5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150

Section VIII

Core Data Form (TCEQ-10400)



TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

SECTION	I. Gel											
		sion (If other is c				, ,		,				
New Per	mit, Regis	stration or Authori	zation (Core	Data F	orm sho	ould be	subm	nitted v	vith the p	program applicatio	n.)	
		ata Form should b		vith the	e renew	al form)		Other			
2. Customer	2. Customer Reference Number (if issued) Follow this link to sea					arch	3. R	egulated	Entity Reference	e Number <i>(i</i>	f issued)	
CN	for CN or RN number							R	N 1117	87560		
SECTION	II: Cu	stomer Info	ormation									
4. General C	ustomer I	nformation	5. Effective	e Date	for Cu	stome	r Infor	matio	n Updat	es (mm/dd/yyyy)		
New Cust		me (Verifiable wit	_	•	e to Cue ary of St					Change in Fublic Accounts)	Regulated E	Entity Ownership
The Custo	mer Nar	ne submitted	here may	be up	odated	l auto	matio	cally	based	on what is cu	rrent and	active with the
Texas Sec	retary o	f State (SOS)	or Texas C	Comp	troller	of Pl	ublic	Acc	ounts (CPA).		
6. Customer	Legal Na	me (If an individual	l, print last nam	ne first:	eg: Doe,	John)			lf new Cu	stomer, enter previ	ous Custome	er below:
AMFP V	Chapel	Hill II LLC										
7. TX SOS/CI	PA Filing	Number	8. TX State	e Tax ID (11 digits)			9	9. Federa	al Tax ID (9 digits)	10. DUNS	S Number (if applicable)	
08040948	98		3207952	7084	1			1	88-277	9187		
11. Type of C	ustomer	: Corporati	on			Individ	ual		Pa	rtnership: 🔲 Gener	al 🗌 Limited	
Government:	🗌 City 🔲	County 🗌 Federal 🗌] State 🗌 Othe	r		Sole F	roprie	torshij	o 🛛	Other: LLC		
12. Number o 0-20	of Employ 21-100	/ees	251-500] 501 aı	nd hiah	er		13. Inder X Yes	endently Owned	l and Opera	ted?
	-									se check one of the	following	
Owner		Operat	tor			wner 8	Oper	ator				
	nal Licens	— •	nsible Party				•		pplicant	Other:		
	3610-2	2 N. Josey										
15. Mailing Address:	Suite 2	223										
	City	Carrollton		,	State	TX		ZIP	750	07	ZIP + 4	
16. Country I	Mailing In	formation (if outsi	de USA)				17. E	E-Mail	Addres	S (if applicable)		•
							Eril	k.Bo	raks@	dukecompani	es.com	
18. Telephon	e Numbe	r		19.	Extensi	on or (Code		_	20. Fax Numbe	r (if applicat	ole)
(972) 38	(972) 385-1676									()	-	

SECTION III: Regulated Entity Information

 21. General Regulated Entity Information (If 'New Regulated Entity" is selected below this form should be accompanied by a permit application)

 ☑ New Regulated Entity
 □ Update to Regulated Entity Name

 □ Update to Regulated Entity
 □ Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

Chapel Hill Phase 2

	403 Westinghouse Road											
23. Street Address of the Regulated Entity:	105 110											
<u>(No PO Boxes)</u>	City	Georgetow	vn State	T	X	ZIP	78626		ZIP + 4			
24. County	William	Williamson										
	E	nter Physical L	ocation Descript	ion if	no str	eet addres	s is provid	ed.				
25. Description to Physical Location:												
26. Nearest City							State		Nea	rest ZIP Code		
27. Latitude (N) In Decim	nal:				28. L	ongitude (W) In Deciı	nal:				
Degrees	Minutes		Seconds		Degree	es	Mir	utes		Seconds		
30	2	34	55.54			97		4	1	10.62		
29. Primary SIC Code (4					32. Se (5 or 6 di	condary NA	ICS Code					
6513	65.	31		53	1311			5311	10			
33. What is the Primary	Business of	f this entity?	(Do not repeat the SIC	or NA	ICS desc	cription.)		l				
Multifamily apartm	ent devel	opment										
				1	3740 N	/lidway Ro	ad					
34. Mailing			Suite 804									
Address:	City	Dallas	State		ТХ	ZIP 7		244	ZIP + 4			
35. E-Mail Address:				Erik.B	Boraks	@dukecon	npanies.co	m				
36. Telepho	one Number		37. Extensio	on or	Code	1	38.	Fax Num	ber <i>(if appli</i>	icable)		
(972) 3	85-1687							() -			
39. TCEQ Programs and ID form. See the Core Data Form i	Numbers C	Check all Program r additional guidar	s and write in the pence.	ermits/r	registrat	ion numbers	that will be	affected b	y the updates	submitted on this		
Dam Safety	Districts Edwards A			uifer Emissions Inventory Air			y Air	Industrial	Hazardous Waste			
Municipal Solid Waste	New So	ource Review Air	OSSF			Petroleum Storage Tank			PWS			
Sludge	Storm \	Water	Title V Air			Tires			Used Oil			
Voluntary Cleanup	□ Waste	Water	Wastewater /	Aaricul	ture	Water	Rights		Other:			


SECTION IV: Preparer Information

40. Name:	Paul M. Hames, P.E.		41. Title:	Principal		
42. Tele	phone Number 43. Ext./Code	44. Fax Number	45. E-Mail	Address		
(214)	473-2483	() -	Paul.Hames@stantec.com			

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Stantec Consulting Services	Job Title:	Principal		
Name (In Print):	Paul M. Hames, P.E.			Phone:	(214) 473- 2483
Signature:	fand M. Lames			Date:	2/01/2024



V:\2220\active\222012278\civil\phase_01\drawing\sheets\222012278crv01.dwg modified by jquinonez on May 21, 2023 - 11:49pm

purpose other than that authorized by Stantec is forbidden

CONSTRUCTION DOCUMENTS

FOR

CHAPEL HILL PHASE 2 403 WESTINGHOUSE ROAD GEORGETOWN, TEXAS 78626



Approved for construction by the City of Georgetown Planning & Zoning Commission on: June 6, 2023 This SDP will expire 24 months from the date of approval if the applicable conditions of UDC

Section 3.09.090 are not met.





403 WESTINGHOUSE ROAD ADDRESS : GEORGETOWN, TEXAS 78626

1ST SUBMITTAL DATE : 10/18/2021 2ND SUBMITTAL DATE : 12/06/2021 **3RD SUBMITTAL DATE :** 08/22/2022 4TH SUBMITTAL DATE : 10/03/2022

5TH SUBMITTAL DATE : 05/01/2023

SUBMITTED BY : BRAIN CARRINGTON, P.E. STANTEC

DATE 6080 TENNYSON PARKWAY, SUITE 200 PLANO, TEXAS 75024 (469)329-3613

I, ALYSSA N. CAMPBELL, P.E., CERTIFY THAT THESE ENGINEERING DOCUMENTS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THE INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO FORMAL CITY APPROVAL.

REVISION LOG:

NO.	DATE	COMMENTS

	SHEET NO. DESC	RIPTION SHEET INDEX
	CIV	IL ENGINEERING
	CIVIL SITE PLAN SE	Т
	Sheet List Table Sheet Number	Sheet Title
	01 02 03	COVER SHEET GENERAL NOTES SUBDIVISION PLAT
	04 05	EXISTING CONDITIONS & DEMOLITION PLAN ON—SITE EROSION & SEDIMENTATION CONTROL PLAN
	06 07 08	OFF-SITE EROSION & SEDIMENTATION CONTROL PLAN EROSION & SEDIMENTATION CONTROL DETAILS ON-SITE EXISTING DRAINAGE AREA MAP
	09 10	OFF-SITE EXISTING DRAINAGE AREA MAP ON-SITE PROPOSED DRAINAGE AREA MAP A
	11 12	ON-SITE PROPOSED DRAINAGE AREA MAP B OFF-SITE PROPOSED DRAINAGE AREA MAP
	13 14 15	ON-SITE GRADING PLAN OFF-SITE GRADING PLAN MASTER SITE PLAN
	16 17	SITE PLAN A SITE PLAN B
	18 19	SITE PLAN C SITE PLAN D
	20 21 22	DECELERATION LANE PLAN ON-SITE PAVING PLAN ON-SITE DRAINAGE PLAN
	23 24	OFF-SITE PAVING & DRAINAGE PLAN SITE & PAVING DETAILS
	25 26	TYPICAL ROAD SECTIONS NORTH WATER QUALITY & DETENTION POND
	27 28 29	SOUTH WATER QUALITY & DETENTION POND TCEQ WATER QUALITY CALCUATIONS STORM SEWER DETAILS 01
	30 31	PRIVATE WATER PLAN PRIVATE WASTEWATER PLAN
	32 33 34	WASTEWATER PROFILES 1 OF 2 WASTEWATER PROFILES 2 OF 2 WATER & WASTEWATER DETAILS 01
	35 36	WATER & WASTEWATER DETAILS 02 WATER & WASTEWATER DETAILS 03
	37 38	WATER & WASTEWATER DETAILS 04 ENTRY ROAD PLAN AND PROFILE
	Sheet Number C1.01 C2.01 C3.01 C4.01 C5.01 C6.01 C6.02	Sheet Title EXISTING CONDITIONS AND DEMOLITION PLAN GRADING PLAN PAVING PLAN DIMENSIONAL CONTROL PLAN STRIPING AND SIGNAGE PLAN UTILITY PLAN STORM SEWER PROFILES
IT OF GEOR	GETOWN	DATE
LLIAMSON C	OUNTY EMERGENCY SERVICE DIS	STRICT #3 DATE
		DATE
	THE LOCATION OF EXISTIN SHOWN IN AN APPROXIMA SHALL DETERMINE THE D UTILITIES BEFORE COMMED FULLY RESPONSIBLE FOR	IG UNDERGROUND UTILITIES ARE ITE WAY ONLY. THE CONTRACTOR (ACT LOCATION OF ALL EXISTING ICONG WORK. HE AGREES TO BE ANY AND ALL DAMAGES WHICH Y HIS FAILURE TO EXACTLY LOCATE ALL UNDERGROUND UTILITIES.
	AND PRESERVE ANY AND	
	AND PRESERVE ANY AND	SHEET

GENERAL	SITE	DEVELOPM	<u>ent f</u>	<u>PLAN</u>	NOTES:

- 1. IT IS THE RESPONSIBILITY OF THE PROPERTY OWNER, AND SUCCESSORS TO THE CURRENT PROPERTY OWNER, TO ENSURE THE SUBJECT PROPERTY AND ANY IMPROVEMENTS ARE MAINTAINED IN CONFORMANCE WITH THIS SITE DEVELOPMENT PLAN.
- 2. THIS DEVELOPMENT SHALL COMPLY WITH ALL STANDARDS OF THE UNIFIED DEVELOPMENT CODE (UDC), THE CITY OF GEORGETOWN CONSTRUCTION STANDARDS AND SPECIFICATIONS MANUAL, THE DEVELOPMENT MANUAL AND ALL OTHER APPLICABLE CITY STANDARDS.
- 3. THIS SITE DEVELOPMENT PLAN SHALL MEET THE UDC STORMWATER REQUIREMENTS.
- 4. ALL SIGNAGE REQUIRES A SEPARATE APPLICATION AND APPROVAL FROM THE INSPECTION SERVICES DEPARTMENT. NO SIGNAGE IS APPROVED WITH THE SITE DEVELOPMENT PLAN.
- 5. SIDEWALKS SHALL BE PROVIDED IN ACCORDANCE WITH THE UDC.
- 6. DRIVEWAYS WILL REQUIRE APPROVAL BY THE DEVELOPMENT ENGINEER OF THE CITY OF GEORGETOWN.
- 7. OUTDOOR LIGHTING SHALL COMPLY WITH SECTION 7.04 OF THE UDC.
- 8. SCREENING OF MECHANICAL EQUIPMENT, DUMPSTERS AND PARKING SHALL COMPLY WITH CHAPTER 8 OF THE UDC. THE SCREENING IS SHOWN ON THE LANDSCAPE AND ARCHITECTURAL PLANS, AS APPLICABLE.
- 9. THE COMPANION LANDSCAPE PLAN HAS BEEN DESIGNED AND PLANT MATERIALS SHALL BE INSTALLED TO MEET ALL REQUIREMENTS OF THE
- 10. ALL MAINTENANCE OF REQUIRED LANDSCAPE SHALL COMPLY WITH THE MAINTENANCE STANDARDS OF CHAPTER 8 OF THE UDC.
- 11. A SEPARATE IRRIGATION PLAN SHALL BE REQUIRED AT THE TIME OF BUILDING PERMIT APPLICATION.
- 12. FIRE FLOW REQUIREMENTS OF_PER MINUTE (INCLUDE AMOUNT) ARE BEING MET BY THIS PLAN.
- 13. ANY HERITAGE TREE NOTED ON THIS SITE DEVELOPMENT PLAN IS SUBJECT, IN PERPETUITY, TO THE MAINTENANCE, CARE, PRUNING AND REMOVAL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE.
- 14. THE CONSTRUCTION PORTION OF THESE PLANS WERE PREPARED, SEALED, SIGNED AND DATED BY A TEXAS LICENSED PROFESSIONAL ENGINEER. THEREFORE, BASED ON THE ENGINEER'S CONCURRENCE OF COMPLIANCE, THE CONSTRUCTION PLANS FOR CONSTRUCTION OF THE PROPOSED PROJECT ARE HEREBY APPROVED SUBJECT TO THE STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS MANUAL AND ALL OTHER APPLICABLE CITY, STATE AND FEDERAL REQUIREMENTS AND CODES.
- 15. THIS PROJECT IS SUBJECT TO ALL CITY STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS IN EFFECT AT THE TIME OF SUBMITTAL OF THE PROJECT TO THE CITY.
- 16. WHERE NO EXISTING OVERHEAD INFRASTRUCTURE EXISTS, UNDERGROUND ELECTRIC UTILITY LINES SHALL BE LOCATED ALONG THE STREET AND WITHIN THE SITE. WHERE EXISTING OVERHEAD INFRASTRUCTURE IS TO BE RELOCATED. I SHALL BE RE-INSTALLED UNDERGROUND AND THE EXISTING FACILITIES SHALL BE REMOVED AT THE DISCRETION OF THE DEVELOPMENT ENGINEER.
- 17. ALL ELECTRIC AND COMMUNICATION INFRASTRUCTURE SHALL COMPLY WITH UDC. SECTION 13.06.

CENERAL NOTES -

- SIDEWALKS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENT OF THE T.A.S. AS ADMINSTERED BY THE TDLR ("TDLR COMPLIANT
- SIDEWALKS SHALL BE INSTALLED IN ACCORANCE WITH THE REQUIREMENTS FOR THE REQUIREMENTS OF THE UDC, SECTION

GEOMETRIC AND DESIGN STANDARDS FOR SIDEWALKS

DESIGN AND CONSTRUCTION OF SIDEWALKS SHALL OCCUR IN COMPLIANCE WITH THE FOLLOWING STANDARDS:

- A. IN ORDER TO PROVIDE SADE AND ADEQUATE ACCESS ON CITY SIDEWALKS, ALL SIDEWALKS SHALL MEET MINIMUM CLEAR WIDTH REQUIREMENTS AROUND ALL OBSTRUCTIONS, NATURAL OF MANMADE, AS DESCRIBED HEREIN. CLEAR WIDTH SHALL MEAN THE DISTANCE AS MEASURED FROM THE OUTSIDE EDGE OF THE OBSTRUCTION TO THE OUTSIDE EDGE OF THE SIDEWALK OR FROM THE INSIDE EDGE OF THE OBSTRUCTION TO THE INSIDE EDGE OF THE SIDEWALK. IF THE CLEAR WIDTH IS TO BE OBTAINED BETWEEN THE INSIDE EDGE OF THE SIDEWALK AND OBSTRUCTION, GIVEN THAT THE SIDEWALK IS PLACED AGAINST THE BACK OF THE CURB, THE CLEAR WIDTH SHALL BE A MINIMUM OF FIVE FEET. IN ALL OTHER CASES, THE MINIMUM CLEAR WIDTH SHALL BE FOUR FEET.
- B. ALL SIDEWALKS SHALL MEET CITY STANDARDS AND SPECIFICATIONS. SIDEWALKS MAY BE PLACED SO THAT THEY VARY THE DISTANCE FROM BACK OF CURB, PROVIDED THAT THE MINIMUM WIDTH AND DISTANCE FROM BACK OF CURB IS NOT REDUCED.
- C. GIVEN THAT A COMBINATION OF VARIATION FROM THE TWO PLACEMENT METHODS IS NECESSARY OR DESIRED OR THAT AN OBSTRUCTION IS LOCATED WITHIN THE PAVED AREA, THE FOLLOWING CRITERIA SHALL BE SATISFIED.

1.ALL RADII IN THE TRANSITION SECTION SHALL BE A MINIMUM OF TEN

ATTENTON

ORIGINAL SHEET - ARCH I

A SEPARATE PERMIT IS REQUIRED FOR THE INSTALLATION OF PRIVATE DIRE SERVICE MAINS AND THEIR APPURTENANCES, AND UNDERGROUND FIRE LINE SUPPLY.

TRAFFIC CONTROL AND PAVEMENT MARKING NOTES:

ALL TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE STANDARDS OF THE TEXAS DEPARTMENT OF TRANSPORTATION AND THE TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

FIRE PROTECTION NOTES:

- APPROVAL OF THIS SITE PLAN DOES NOT IMPLY APPROVAL TO INSTALL UNDERGROUND FIRE LINES. PRIOR TO INSTALLATION OF UNDERGROUND FIRE LINES, A SEPARATE PERMIT SHALL BE SUBMITTED, UNDER GROUND FIRE LINE SUBJECT
- BACKFLOW PROTECTION WILL BE PROVIDED IN ACCORDANCE WITH THI CITY OF GEORGETOWN REQUIREMENTS WHEN REQUIRED. BACK FLOW PROTECTION WILL BE INSTALLED IN ACCORDANCE WITH THE DETAIL PROVIDED IN THE UTILITY DRAWINGS.
- ALL PRIVATE FIRE LINES AND WHAT THEY PROVIDE SERVICE TO WILL BE INSTALLED IN ACCORDANCE WITH NFPA 24 INSTALLATION OF PRIVATE SERVICE MAINS AND THEIR APPURTENANCES.
- ALL TEES, PLUGS, CAPS, BENDS, REDUCERS, VALVES SHALL BE RESTRAINED AGAINST MOVEMENT. THRUST BLOCKING AND JOINT RESTRAINED WILL BE INSTALLED IN ACCORDANCE WITH NFPA 24.
- ALL UNDERGROUND SHALL REMAIN UNCOVERED UNTIL A VISUAL INSPECTION IS CONDUCTED BY THE GEORGETOWN FIRE MARSHAL'S OFFICE (FMO). ALL JOINT RESTRAINTS AND THRUST BLOCKING SHALL BE UNCOVERED FOR VISUAL INSPECTION.
- 6. ALL UNDERGROUND SHALL BE FLUSHED PER THE REQUIREMENTS OF NFPA STANDARD 24 AND WITNESSED BY GEORGETOWN FMO.
- ALL UNDERGROUND SHALL PASS A HYDROSTATIC TEST WITNESSED BY GEORGETOWN FMO. ALL JOINTS SHALL BE UNCOVERED FOR HYDROSTATIC TESTING. ALL PIPING AND ATTACHMENTS SUBJECTED TO SYSTEM WORKING PRESSURE SHALL BE TESTED AT 200 PSI. OR 50 PSI. IN EXCESS OF THE SYSTEM WORKING PRESSURE, WHICHEVER IS GREATER., AND SHALL MAINTAIN THAT PRESSURE + OR 5 PSI FOR 2 HOURS.
- 8. FENCES, LANDSCAPING AND OTHER ITEMS WILL NOT BE INSTALLED WITHIN 3 FT, AND WHERE THEY WILL OBSTRUCT THE VISIBILITY OF ACCESS TO HYDRANTS, OR REMOTE FDCS.
- 9. LICENSE REQUIREMENTS OF EITHER RME-U OR G. WHEN CONNECTING BY UNDERGROUND TO THE WATER PURVEYOR'S MAIN FROM THE POINT OF CONNECTION OR VALVE WHERE THE PRIMARY PURPOSE OF WATER IS FRO FIRE PROTECTION SPRINKLER SYSTEM.

STREET AND DRAINAGE CONSTRUCTION NOTES

- 1. ROADWAY EXCAVATION, EMBANKMENT, AND SUBGRADE PREPARATION SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATIONS SD-2, ROADWAY EXCAVATION, AND SD-3 EMBANKMENT AND SUBGRADE.
- 2.CONTRACTOR TO FILL BEHIND CURBS AND WALKS AND SHAPE TO INSURE PROPER DRAINAGE.
- 3. CONSTRUCTION JOINTS TO EXISTING PAVEMENT SHALL BE MADE BY EITHER CUTTING BACK EXISTING TO PRODUCE A SLIGHTLY BEVELED EDGE FOR THE FULL THICKNESS OF THE WEARING COURSE OR A SUITABLE LAP JOINT SHALL BE MADE. SAW CUTTING REQUIRED.
- 4.NO TRAFFIC SHALL BE ALLOWED ON THE FINISHED WEARING SURFACE UNTIL AT LEAST 12 HOURS AFTER COMPLETION OF ROLLING.
- 5.HOT MIX CONCRETE TRANSPORT TRUCKS TO BE EQUIPPED WITH CANVAS COVERS TO BE UTILIZED DURING MATERIAL HAULING. MATERIAL DELIVERED TO SITE AT IMPROPER TEMPERATURE SHALL BE REJECTED. HOT MIX SHALL BE LAID AT A MINIMUM TEMPERATURE OF 225°F.
- 6.ANY SETTLEMENT UNDER PAVEMENT DUE TO INADEQUATE COMPACTION OF UTILITY LINE BACK FILL SHALL BE CAUSE FOR RECOMPACTION OF TRENCH AND REPLACEMENT OF PAVEMENT SECTION.
- 7.ALL STORM DRAIN PIPING SHALL MEET CITY OF GEORGETOWN SPECIFICATION C-8, REINFORCED CONCRETE PIPE AND SHALL BE CLASS III RCP UNLESS NOTED OTHERWISE IN THE PLANS.
- 8.ALL PROPOSED STORM SEWER MANHOLES SHALL MEET CITY OF GEORGETOWN
- 9.PIPE EXCAVATION, TRENCHING, EMBEDMENT, ENCASEMENT AND BACKFILLING SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN STANDARD SPECIFICATION G-4 AND G-5 UNLESS OTHERWISE SPECIFIED.
- 10. TRENCH EXCAVATION SAFETY SYSTEMS SHALL BE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION CIP-11.
- 11. CONTRACTOR SHALL REFERENCE THE GEOTECHNICAL REPORT NO. A211032-R1 "GEOTECHNICAL ENGINEERING REPORT CHAPEL HILL APARTMENTS WESTINGHOUSE ROAD GEORGETOWN, TEXAS" CONDUCTED BY TERRADYNE ENGINEERING, DATED JULY 7. 2021 FOR SOILS AND PAVEMENT INFORMATION. ANY DISCREPANCY BETWEEN THESE CONSTRUCTION PLANS AND THE GEOTECHNICAL REPORT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER OF RECORD PRIOR TO CONSTRUCTION. THE **PROPOSED PAVEMENT SECTION IS:**

PORTLAND CEMENT CONCRETE DESIGN						
	THICKNESS					
LIGHT DUTY						
6.0	7.0					
8.0	8.0					
	LIGHT DUTY 6.0					

12. ALL EMBANKMENT, SUBGRADE, TRENCH BACKFILL, BASE, ASPHALT, AND TESTING SHALL MEET THE CITY OF GEORGETOWN SPECIFICATIONS AND STANDARDS.

13. THESE PAVEMENT THICKNESS DESIGNS ARE INTENDED TO TRANSFER THE LOAD FROM THE ANTICIPATED TRAFFIC CONDITIONS.

EROSION AND SEDIMENTATION CONTROL NOTES

- 1. PRIOR TO ANY SITE PREPARATION WORK, THE CONTRACTOR SHALL INSTALL EROSION CONTROLS IN ACCORDANCE WITH THE EROSION & SEDIMENTATION CONTROL PLAN.
- 2.SEDIMENTATION AND TEMPORARY EROSION CONTROLS SHALL BE PROVIDED IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION G-6.
- 3. REVEGETATION SHALL BE PERFORMED IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION G-7 AND AS FURTHER SHOWN ON THIS SET OF PLANS.

- (INCHES) DUMPSTERS 7.0 8.0

- WATERLINE CONSTRUCTION NOTES
- 1. ALL WATER & WASTEWATER COLLECTION LINE CROSSINGS TO BE CONSTRUCTED IN ACCORDANCE WITH TCEQ REGULATION, CHAPTER 290 & 217.
- 2.ALL WATERLINE CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATIONS WI THRU W4. ALL WATERLINE TESTING SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION CIP-12, TESTING OF PIPELINES AND MANHOLES.
- 3.PIPE EXCAVATION, TRENCHING, EMBEDMENT, ENCASEMENT AND BACKFILLILING SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN STANDARD SPECIFICATIONS G-4 AND
- 4. TRENCH EXCAVATION SAFETY SYSTEMS SHALL BE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION CIP-11.
- 5. CONTRACTOR TO INFORM BOTH CITY AND PROPERTY OWNER A MIN OF 48 HOURS PRIOR TO INTERRUPTION OF WATER SERVICE. ANY INTERRUPTION SHALL NOT BE DURING PEAK USAGE TIME OR FOR MORE THAN 4 HOURS.
- 6.ALL PROPOSED PVC PIPE SHALL BE C900-DR18 AND MEET MANUFACTURER'S RECOMMENDATIONS FOR PIPE DEFLECTION. ALL PROPOSED FITTINGS, TEES, AND BENDS SHALL BE DOMESTICALLY MANUFACTURED DUCTILE IRON.
- 7.ALL GATE VALVES SHALL BE RESILIENT SEATED MEETING CITY OF GEORGETOWN SPECIFICATION W-3, VALVES, HYDRANTS, AND APPURTENANCES.
- 8. CONTRACTOR TO INSTALL TRACER WIRE PER STANDARD DETAILS FOR ALL PROPOSED WATER MAINS.
- 9. ALL PROPOSED WATER LINES SHALL BE THRUST BLOCKED PER STANDARD DETAILS AND SPECIFICATIONS.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE CAUSED BY THE CONTRACTOR OUTSIDE OF THE DESIGNATED WORK AREA WITH EQUAL OR BETTER QUALITY MATERIAL AT THE CONTRACTOR'S EXPENSE.
- 11. WET CONNECTIONS 4" DIAMETER AND LARGER SHALL INCLUDE AN APPROPRIATELY SIZED DUCTILE IRON SLEEVE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. DUCTILE IRON SLEEVE SHALL BE SUBSIDIARY TO WET CONNECTION.
- 12. CONTRACTOR TO MARK CURBS AS DETAILED FOR WATER SERVICES AND VALVES.

WASTEWATER COLLECTION LINE CONSTRUCTION NOTES

- 1. ALL CROSSING OF WASTEWATER COLLECTION LINES AND WATERLINES SHALL BE CONSTRUCTED IN ACCORDANCE WITH TCEQ REGULATIONS CHAPTER 290 AND 217.
- 2.ALL PROPOSED WASTEWATER LINES SHALL BE SDR 26 PIPE MATERIAL (UNLESS OTHERWISE NOTED), IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION WW-2.
- 3. PROPOSED WASTEWATER MANHOLES SHALL BE INSTALLED IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION WW-1.
- 4. CONNECTIONS TO THE EXISTING WASTEWATER SYSTEM SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION WW-3.
- 5. TESTING OF WASTEWATER LINES SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION CIP-12, TESTING OF PIPELINES AND MANHOLES.
- 6.CONTRACTOR TO PROVIDE DEFLECTION TEST IN ACCORDANCE WITH TCEQ CHAPTER 217.57 (B.) MANDREL TO BE PULLED IN BOTH DIRECTIONS.
- 7.CONTRACTOR TO PROVIDE LOW PRESSURE AIR TEST IN ACCORDANCE WITH TCEQ CHAPTER 271.57 (A), (1). 30 DAYS AFTER INSTALLATION. NO WATER TEST ALLOWED.
- 8. CONTRACTOR TO PROVIDE LEAKAGE TEST FOR MANHOLE IN ACCORDANCE WITH TCEQ CHAPTER 217.57 (A) OF THE STATE WASTEWATER CODE. NO WATER TEST ALLOWED.
- 9.PIPE EXCAVATION, TRENCHING, EMBEDMENT, ENCASEMENT AND BACKFILLING SHALL BE DONE IN ACCORDANCE WITH CITY OF GEORGETOWN STANDARD SPECIFICATIONS G-4 AND G-5.
- 10. TRENCH EXCAVATION SAFETY SYSTEMS SHALL BE IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATION CIP-11.
- 11. CONTRACTOR TO MARK CURBS AS DETAILED FOR WASTEWATER SERVICES.
- 12. NO WATER JETTING ALLOWED, MECHANICAL COMPACTION REQUIRED.

FIRE PROTECTION NOTES

- 1. APPROVAL OF THIS SITE PLAN DOES NOT IMPLY APPROVAL TO INSTALL UNDERGROUND FIRE LINES. PRIOR TO INSTALLATION OF UNDERGROUND FIRE LINES, A SEPARATE PERMIT SHALL BE SUBMITTED. UNDERGROUND FIRE LINE SUPPLY.
- 2.BACKFLOW PROTECTION WILL BE PROVIDED IN ACCORDANCE WITH THE CITY OF GEORGETOWN REQUIREMENTS WHEN REQUIRED. BACKFLOW PROTECTION WILL BE INSTALLED IN ACCORDANCE WITH THE DETAIL PROVIDED IN THE UTILITY DRAWINGS.
- 3.ALL PRIVATE FIRE LINES AND WHAT THEY PROVIDE SERVICE TO WILL BE INSTALLED IN ACCORDANCE WITH NFPA 24 INSTALLATION OF PRIVATE SERVICE MAINS AND THEIR APPURTENANCES.
- 4.ALL TEES, PLUGS, CAPS, BENDS, REDUCERS, VALVES SHALL BE RESTRAINED AGAINST MOVEMENT. THRUST BLOCKING AND JOINT RESTRAINED WILL BE INSTALLED IN ACCORDANCE WITH NFPA 24.
- 5.ALL UNDERGROUND SHALL REMAIN UNCOVERED UNTIL A VISUAL INSPECTION IS CONDUCTED BY THE GEORGETOWN FIRE MARSHAL'S OFFICE (FMO), ALL JOINT RESTRAINTS AND THRUST BLOCKING SHALL BE UNCOVERED FOR VISUAL INSPECTION.
- 6.ALL UNDERGROUND SHALL BE FLUSHED PER THE REQUIREMENTS OF NFPA STANDARD 24 AND WITNESSED BY GEORGETOWN FMO.
- 7.ALL UNDERGROUND SHALL PASS A HYDROSTATIC TEST WITNESSED BY GEORGETOWN FMO. ALL JOINTS SHALL BE UNCOVERED FOR HYDROSTATIC TESTING. ALL PIPING AND ATTACHMENTS SUBJECTED TO SYSTEM WORKING PRESSURE SHALL BE TESTED AT 200 PSI. OR 50 PSI MORE THAN THE SYSTEM WORKING PRESSURE, WHICHEVER IS GREATER, AND SHALL MAINTAIN THAT PRESSURE ± 5 PSI FOR 2 HOURS.
- 8.FENCES, LANDSCAPING, AND OTHER ITEMS WILL NOT BE INSTALLED WITHIN 3 FT. AND WHERE THEY WILL OBSTRUCT THE VISIBILITY OR ACCESS TO HYDRANTS, OR REMOTE FDC.
- 9.LICENSE REQUIREMENTS OF EITHER RME-U OR G. WHEN CONNECTING BY UNDERGROUND TO THE WATER PURVEYOR'S MAIN FROM THE POINT OF CONNECTION OR VALVE WHERE THE PRIMARY PURPOSE OF WATER IS FOR FIRE PROTECTION SPRINKLER SYSTEM.

DEVELOPER'S CONSTRUCTION NOTES;

- 1. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE CITY OF GEORGETOWN'S STANDARD SPECIFICATIONS AND DETAILS, UNLESS SPECIFICALLY DIRECTED OTHERWISE WITHIN THIS SET OF CONSTRUCTION DOCUMENTS. IN THE EVENT OF A DISCREPANCY, ENGINEER SHALL BE NOTIFIED VIA REQUEST FOR INFORMATION (RFI) TO PROVIDE CLARITY.
- 2.IN THE EVENT THAT DISCREPANCIES ARE FOUND IN THE FIELD CONTRADICTORY TO THESE CONSTRUCTION PLANS WITH REGARD TO EXISTING UTILITIES, EXISTING TOPOGRAPHY, EXISTING IMPROVEMENTS, TREES, OR ANY OTHER FEATURE AFFECTING CONSTRUCTION, THE ENGINEER OF RECORD SHALL BE NOTIFIED IMMEDIATELY AND DISCREPANCY SHALL BE DOCUMENTED VIA A REQUEST FOR INFORMATION (RFI).
- 3.ALL DISTURBED AREAS SHALL BE COMPLETELY REVEGETATED BY THE CONTRACTOR. IN DISTURBED AREAS NOT DESIGNATED ON LANDSCAPE PLANS AND WITHIN THE PRIVATE MULTI-FAMILY PROJECT SITE, CONTRACTOR SHALL REVEGETATE WITH A MINIMUM OF 6 INCHES OF QUALITY LOAMY MATERIAL OR CLEAN ONSITE TOPSOIL AND HYDROMULCH, BERMUDA SEED, OR SOD, DEPENDING UPON SLOPE CONDITIONS. CONTRACTOR IS RESPONSIBLE FOR TEMPORARY IRRIGATION AND ESTABLISHING 100% VEGETATIVE COVER OVER THE SITE PRIOR TO ENGINEER'S FINAL CONCURRENCE. CONTRACTOR MAY ELECT TO UTILIZE EROSION CONTROL MATTING ON SLOPES TO OBTAIN REVEGETATION. NO PORTIONS OF SLOPES OR DISTURBED AREAS SHALL REMAIN UNVEGETATED FOR MORE THAN 14 DAYS. SUBMIT EROSION CONTROL MATTING TO ENGINEER OF RECORD FOR REVIEW PRIOR TO CONSTRUCTION.
- 4.ALL EXISTING UTILITIES SHALL BE LOCATED BY CONTRACTOR PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES FOUND FROM THE PLAN SET Shall be sent to engineer of record prior to construction. Per GEOTECHNICAL ENGINEERING REPORT. ANY UTILITIES SLATED TO BE ABANDONE SHALL BE COMPLETELY REMOVED FROM ALL PROPOSED CONSTRUCTION AREAS. IF THIS IS NOT FEASIBLE, THEN THE ABANDONED UTILITY PIPING SHALL BE FILLED WITH FLOWABLE FILL (CITY OF AUSTIN SPECIFICATIONS ITEM NO. 402S OR TXDOT ITEM NO. 401) AND PLUGGED SUCH THAT IS DOES NOT BECOME A CONDUIT FOR WATER FLOW.
- 5.ALL REMNANTS OF EXISTING FOUNDATIONS SHALL BE COMPLETELY EXCAVATED AND REMOVED TO AT LEAST 2 FEET BELOW FINISHED GRADES. IF ANY UNUSUAL ITEMS ARE UNEARTHED DURING OR AFTER DEMOLITION, THE GEOTECHNICAL ENGINEER AND THE CIVIL ENGINEER OF RECORD SHALL BE CONTACTED IMMEDIATELY.
- 6.CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL. TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH CITY OF GEORGETOWN REQUIREMENTS. IN THE CASE OF NO GUIDANCE OR APPLICABLE TRAFFIC CONTROL DETAILS FROM THE CITY OF GEORGETOWN, TXDOT STANDARD TRAFFIC CONTROL METHODS AND DETAILS SHALL **3E UTILIZED**
- 7.ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION LAWS AND REGULATIONS.
- 8. ALL SUBMITTALS SHALL BE REVIEWED BY THE ENGINEER OF RECORD OR DESIGNATED REPRESENTATIVE PRIOR TO CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, WATER, STORM, AND SANITARY SEWER PIPES AND APPURTENANCES, EARTHWORK MATERIALS, TRENCH MATERIALS, PAVEMENTS, AND SIGNAGE. ALL PAVEMENT MIX DESIGNS SHALL BE SIGNED AND SEALED BY A LICENSED PROFESSIONAL ENGINEER IN THE STATE OF TEXAS. ALL SUBMITTALS NECESSARY FOR PUBLIC PROJECTS IN THE CITY OF GEORGETOWN SHALL BE APPLICABLE SUBMITTALS FOR THIS PROJECT.
- 9.ALL EARTHWORK OPERATIONS, MATERIALS, AND PAVING OPERATIONS OUTSIDE OF BUILDING ENVELOPES, INCLUDING BUT NOT LIMITED TO, DEMOLITION, CLEARING, GRUBBING, SCARIFYING, EXCAVATION, FILL, COMPACTION, SUBGRADE PREPARATION. BASE MATERIALS, AND CONCRETE PLACEMENT SHALL BE PERFORMED AND PROVIDED IN ACCORDANCE WITH THE TERRADYNE GEOTECHNICAL ENGINEERING REPORT NO. A211032-R1 FOR CHAPEL HILL APARTMENTS DATED JULY 7, 2021. WET POND QA/QC PLAN FOR CLAY LINER DATED APRIL 30, 2020, AND SUPPLEMENTAL LETTER NO. 2 DATED MAY 7, 2020. SPECIAL ATTENTION SHOULD BE GIVEN TO THE FILL COMPACTION REQUIREMENTS. FOR FILLS GREATER THAN 5 FEET IN DEPTH, THE COMPACTION SHALL BE INCREASED TO AT LEAST 100 PERCENT OF THE ASTM D698 MAXIMUM DRY UNIT WEIGHT. ALL EARTHWORK OPERATIONS WITHIN BUILDING ENVELOPE LIMITS SHALL BE CHECKED/VERIFIED WITH DEVELOPER/OWNER PRIOR TO CONSTRUCTION. THESE CIVIL ENGINEERING PLANS DO NOT ADDRESS EARTHWORK WITHIN THE BUILDING ENVELOPES. OTHER GEOTECHNICAL ENGINEERING REPORT(S) APPLY FOR BUILDING ENVELOPES.
- 10. PER THE RECOMMENDATIONS WITHIN THE TERRADYNE GEOTECHNICAL ENGINEERING REPORT NO. A211032-R1 FOR CHAPEL HILL APARTMENTS DATED JULY 7. 2021. AREAS IMMEDIATELY ADJACENT TO EACH BUILDING THAT ARE NOT PAVED SHALL HAVE 5 FEET BEYOND THE BUILDING LIMIT EXCAVATED OF THE SELECT FILL OVERBUILD AND REPLACED WITH MOISTURE CONDITIONED AND COMPACTED ON-SITE FAT CLAY SOILS FOR A MINIMUM DEPTH OF 2 FEET. REFERENCE THE "GRADING AND DRAINAGE" SECTION OF THE GEOTECHNICAL ENGINEERING REPORT FOR FURTHER INFORMATION AND SPECIFICATIONS. CONTRACTOR SHALL CONFIRM WITH DEVELOPER/OWNER PRIOR TO CONSTRUCTION AS OTHER GEOTECHNICAL ENGINEERING REPORTS MAY APPLY FOR BUILDING
- 11. PER THE RECOMMENDATIONS WITHIN THE TERRADYNE GEOTECHNICA ENGINEERING REPORT NO. A211032-R1 FOR CHAPEL HILL APARTMENTS DATED JULY 7, 2021, UTILITY LINES THAT PENETRATE INTO THE BUILDING ENVELOPE SHALL HAVE AN EFFECTIVE CLAY OR FLOWABLE FILL "TRENCH PLUG" THAT EXTENDS AT LEAST 2 FEET OUT FROM THE FACE OF THE BUILDING EXTERIOR THE CLAY FILL/FLOWABLE FILL SHALL BE PLACED TO COMPLETELY SURROUND THE UTILITY LINE AND IT SHALL FILL THE UTILITY TRENCH COMPLETELY IN WIDTH AND HEIGHT, WITH THE EXCEPTION OF THE TOPSOIL AT THE SURFACE. REFER TO "UTILITY TRENCH BACKFILL" SECTION OF THE GEOTECHNICAL ENGINEERING REPORT FOR FURTHER INFORMATION AND SPECIFICATIONS. CONTRACTOR SHALL SHALL CONFIRM/VERIFY WITH DEVELOPER/OWNER PRIOR TO CONSTRUCTION AS OTHER GEOTECHNICAL ENGINEERING REPORTS MAY APPLY FOR BUILDING ENVELOPES.
- 12. ALL EARTHWORK, MATERIALS, AND PAVEMENT TESTING SHALL BE PERFORMED BY A QUALIFIED PROFESSIONAL GEOTECHNICAL ENGINEER LICENSED IN THE STATE OF TEXAS. ALL TESTING METHODS AND FREQUENCY/SCHEDULE SHALL BE PERFORMED IN ACCORDANCE WITH THE TERRADYNE GEOTECHNICAL ENGINEERIN(REPORT NO. A211032-R1 FOR CHAPEL HILL APARTMENTS DATED JULY 7, 2021 AND SUBSEQUENT ADDENDUM LETTERS TO THIS REPORT, AND AS AGREED UPON BETWEEN DEVELOPER AND GEOTECHNICAL ENGINEER. TESTING SHALL BE PERFORMED IN ACCORDANCE WITH CITY OF GEORGETOWN SPECIFICATIONS AT A MINIMUM AND SHALL INCLUDE PROCTORS, MOISTURE AND DENSITY TESTING, GRADATIONS, CONCRETE CYLINDERS, SLUMP TESTS, AND OTHER TESTS RECOMMENDED BY GEOTECHNICAL ENGINEER. ALL TEST RESULTS AND REPORTS SHALL BE SUBMITTED TO THE ENGINEER OF RECORD.
- 13. ALL UTILITIES SHALL BE TESTED IN ACCORDANCE WITH CITY OF GEORGETOWN TESTING REQUIREMENTS WHETHER THEY ARE PRIVATE UTILITIES OR PUBLIC. ALL TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) RULES AND REGULATIONS APPLY TO THIS PROJECT. ALL TEST RESULTS AND REPORTS SHALL BE SUBMITTED TO THE ENGINEER OF RECORD.
- 14. THE CONTRACTOR SHALL HIRE AN INDEPENDENT THIRD PARTY TO CONDUCT NECESSARY INSPECTIONS FOR TEMPORARY BEST MANAGEMENT PRACTICES. CONTRACTOR IS RESPONSIBLE FOR PREPARING THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND SUBMITTING NOTICE OF INTENT AND NOTICE OF TERMINATION.
- 15. ALL STANDARD CITY OF GEORGETOWN NOTES AND DETAILS APPLY FOR THE WORK ASSOCIATED WITH THIS PLAN SET, UNLESS SPECIFICALLY WRITTEN OTHERWISE BY ENGINEER OF RECORD IN THIS PLAN SET OR DURING CONSTRUCTION PHASE.

5
GENERAL NOTES:
1. THESE CONSTRUCTION PLANS WERE PREPARED, SEALED AND DATED BY A TEXAS LICENSED PROFESSIONAL ENGINEER. THEREFORE BASED ON THE ENGINEER'S CONCURRENCE OF COMPLIANCE, THE CONSTRUCTION PLANS FOR CONSTRUCTION OF THE PROPOSED PROJECT ARE HEREBY APPROVED SUBJECT TO THE STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS MANUAL AND ALL OTHER APPLICABLE CITY, STATE AND FEDERAL REQUIREMENTS AND CODES.
2. THIS PROJECT IS SUBJECT TO ALL CITY STANDARD SPECIFICATIONS AND DETAILS IN EFFECT AT THE TIME OF SUBMITTAL OF THE PROJECT OF THE CITY.
3. THE SITE CONSTRUCTION PLANS SHALL MEET ALL REQUIREMENTS OF THE APPROVED SITE PLAN.
4. WASTEWATER MAINS AND SERVICE LINES SHALL BE SDR 26 PVC
5. WASTEWATER MAINS SHALL BE INSTALLED WITHOUT HORIZONTAL OR VERTICAL BENDS.
6. MAXIMUM DISTANCE BETWEEN WASTEWATER MANHOLES IN 500 FEET.
7. WASTEWATER MAINS SHALL BE LOW PRESSURE AIR TESTED AND MANDREL TESTED BY THE CONTRACTOR ACCORDING TO CITY OF GEORGETOWN AND TCEQ REQUIREMENTS.
8. WASTEWATER MANHOLES SHALL BE VACUUM TESTED AND COATED BY THE CONTRACTOR ACCORDING TO CITY OF GEORGETOWN AND TCEQ REQUIREMENTS.
9. WASTEWATER MAINS SHALL BE CAMERA TESTED BY THE CONTRACTOR AND SUBMITTED TO THE CITY ON DVD FORMAT PRIOR TO PAVING THE STREETS.
10. PRIVATE WATER SYSTEM FIRE LINES SHALL BE TESTED BY THE CONTRACTOR TO 200 PSI FOR 2 HOURS.
11. PRIVATE WATER SYSTEM FIRE LINES SHALL BE DUCTILE IRON PIPING FROM THE WATER MAIN TO THE BUILDING SPRINKLER SYSTEM, AND 200 PSI C900 PVC FOR ALL OTHERS.
12. PRIVATE WATER SYSTEM MAINS SHALL BE 150 PSI C900 PVC AND TESTED BY CONTRACTOR AT 150 PSI FOR 4 HOURS.
13. ALL BENDS AND CHANGES IN DIRECTION ON WATER MAINS SHALL BE RESTRAINED AND THRUST BLOCKED.
14. LONG FIRE HYDRANT LEADS SHALL BE RESTRAINED.
15. ALL WATER LINES ARE TO BACTERIA TESTED BY THE CONTRACTOR ACCORDING TO THE CITY STANDARDS AND SPECIFICATIONS.

16. WATER AND SEWER MAIN CROSSING SHALL MEET ALL REQUIREMENTS OF THE TCEQ AND THE CITY.

17. FLEXIBLE BASE MATERIAL FOR PUBLIC STREETS SHALL BE TXDOT TYPE A GRADE 1.

18. HOT MIX ASPHALTIC CONCRETE PAVEMENT SHALL BE TYPE D UNLESS OTHERWISE SPECIFIED AND SHALL BE A MINIMUM OF 2 INCHES THICK ON PUBLIC STREETS AND ROADWAYS.

20. A MAINTENANCE BOND IS REQUIRED TO BE SUBMITTED TO THE CITY PRIOR TO ACCEPTANCE OF PUBLIC IMPROVEMENTS. THIS BOND SHALL BE ESTABLISHED FOR 1 YEAR IN THE AMOUNT OF 25% OF THE COST OF THE PUBLIC IMPROVEMENTS AND SHALL FOLLOW THE CITY FORMAT.

21. RECORD DRAWINGS OF THE PUBLIC IMPROVEMENTS SHALL BE SUBMITTED TO THE CITY BY THE DESIGN ENGINEER PRIOR TO ACCEPTANCE OF THE PROJECT. THESE DRAWINGS SHALL BE MYLAR OR ON TIFF OR PDF (300P DPI), IF A DISK IS SUBMITTED, A BOND SET SHALL E INCLUDED WITH THE

19. ALL SIDEWALK RAMPS ARE TO BE INSTALLED WITH THE PUBLIC INFRASTRUCTURE.

 \mathbf{n} U

Φ


Permit/Seal X BRIAN E. CARRINGTO 123263

4/28/2023


Client/Project DUKE, INC.	CHAPEL HILL PHASE 2	403 WESTINGHOUSE ROAD, GEORGETOWN, TEXAS 78626
Project No File Name: 22201	.: 222012278 2278GNS01	
Scale:		
Dwn. Ds	sgn. Chkd. Y	5.21.2023 YYY.MM.DD
Title	ogn. Criku. T	
	al notes	
Revision:0		02 of 38
Drawing N	0.	
02		




THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.




CHARGE, ' (CPS)		ATIONS 25 YR WEIGHTED 'C' VALUE	PEAK DISCHARGE 'Q' (CPS)	INTENSITY, ' 'i' (IN/HR)	100 YR WEIGHTED 'C' VALUE	PEAK DISCHARGE 'Q' (CPS)	COMMENTS			100 LF SH SLOPE
<u>(01 0)</u> 31.05 4.05	5.89 8.25	0.44	40.21 5.14	7.27	0.51	57.54 7.26	POINT OF INTEREST 1 DRA ADJACENT PROPERT POINT OF INTEREST 2 DRA CHAPEL HILL PHASE 1 PRO	Y INS TO		
		EX	. DA	× 1						
`` ``		[15	.50							
 \										
L] _ 7										
_	$\langle \langle \rangle \rangle$									
									FINAL PLAT OF	OT 1, BLOCK A CHAPEL HILL SECTION ONE
									FINAL PLAT OF	T 1, BLOCK CHAPEL HILL SECTION ONE NT NO. 2020 CHAPEL HI NDS. 2020
									FINAL PLAT OF DOCUME	T 1, BLOCK A CHAPEL HILL SECTION ONE NT NO. 2020 CHAPEL HILL MDS. 202001 (2012) & 2000 (2012) & 2000 (2012) & 2000
									FINAL PLAT OF DOCUME AMFP DOC 2020	T 1, BLOCK CHAPEL HIL SECTION ONE NT NO. 2020
									FINAL PLAT OF DOCUME AMFP DOC 2020	OT 1, BLOCK CHAPEL HILI SECTION ONE NT NO. 2020 CHAPEL HIL NDS. 2020 D12 & CHAPEL HIL NDS. 202001
									FINAL PLAT OF DOCUME AMFP DOC 2020	DT 1, BLOCK CHAPEL HIL SECTION ONE NT NO. 2020 CHAPEL HI NDS. 20200 CP12 8 CP12






ORIGINAL SHEET - ARCH D





THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. 2021-65-SDP



DRAINAGE BASIN AREA RATIONAL METHOD CALCULATIONS

References: City of Georgetown Drainage Criteria Manual Formulas: Rational Method Intensity (in/hr) i = a / ((T_c+b)^c) Q = CiA 2-year 10-year 25-year 100-year 111.07 129.03 Q = design flow (cfs) a= 106.29 96.84 C = weighted 'C' coefficient b= 16.81 15.88 17.23 17.83 c= 0.9076 0.7952 0.7815 0.7625 i = Intensity (in/hr) 10-YEAR 2-YEAR 25-YEAR 100-YEAR

 Sub-Basin ID
 Area (ac)
 Tc (min)
 Intensity
 Weighted 'C'
 Sub-Basin Q2 (cfs)
 Intensity
 Weighted
 Sub-Basin C' Value
 Intensity
 Weighted
 Sub-Basin
 Intensity
 In Weighted Sub-Basin PROPOSED CONDITIONS DRAINAGE SUB-BASINS DA-1 0.21 5.0 6.48 0.97 1.32 8.64 0.97 1.76 9.84 0.97 2.00 11.88 0.97 DA-2 0.22 5.0 6.48 0.97 1.85 9.84 0.97 2.10 11.88 2.5 1.39 8.64 0.97 0.97 DA-3 0.29 5.0 6.48 0.97 0.97 2.45 9.84 0.97 2.79 11.88 0.97 3.3 1.84 8.64 0.97 1.76 9.84 0.97 2.00 11.88 0.97 2.4 DA-4 0.21 5.0 6.48 0.97 1.32 8.64 DA-5 0.21 5.0 6.48 0.97 1.32 8.64 0.97 1.76 9.84 0.97 2.00 11.88 0.97 2.4 DA-6 0.29 5.0 6.48 0.97 1.84 8.64 0.97 2.45 9.84 0.97 2.79 11.88 0.97 3 DA-7 0.29 5.0 6.48 0.97 1.84 8.64 0.97 2.45 9.84 0.97 2.79 11.88 0.97 3.
 DA-8
 0.21
 5.0
 6.48
 0.97
 1.32
 8.64
 0.97
 1.76
 9.84
 0.97
 2.10
 11.88
 0.97
 2.4

 DA-9
 0.22
 5.0
 6.48
 0.97
 1.39
 8.64
 0.97
 1.85
 9.84
 0.97
 2.10
 11.88
 0.97
 2.4
 ____ 0.21 5.0 6.48 0.97 1.32 8.64 0.97 1.76 9.84 0.97 2.00 11.88 DA-10 0.97 2.4 0.14 5.0 6.48 0.97 0.85 0.97 1.13 9.84 0.97 DA-11 8.64 1.29 11.88 1.5 0.97 DA-12 0.46 5.0 6.48 0.36 1.06 8.64 0.42 1.65 9.84 0.46 2.05 11.88 0.52 2.8 DA-13 0.87 5.0 6.48 0.71 3.98 8.64 0.73 5.49 9.84 0.75 6.39 11.88 0.77 8.0 DA-14 0.37 5.0 6.48 0.36 0.86 0.41 1.33 0.45 8.64 1.66 11.88 0.52 2. 9.84 DA-15 0.52 5.0 6.48 0.38 1.28 8.64 0.44 1.96 9.84 0.48 2.42 11.88 0.54 3.1 DA-16 3.15 5.0 6.48 0.34 6.98 8.64 0.40 10.94 9.84 0.44 13.69 11.88 0.51 19.
 DA-16
 3.15
 5.0
 6.48
 0.34
 6.36
 6.04
 6.40
 10.94
 5.04
 6.44
 10.05
 11.00
 0.01
 10.14

 DA-17
 0.30
 5.0
 6.48
 0.39
 0.76
 8.64
 0.44
 1.16
 9.84
 0.48
 1.44
 11.88
 0.54
 1.97


 DA-18
 0.63
 5.0
 6.48
 0.67
 2.75
 8.64
 0.70
 3.82
 9.84
 0.72
 4.47
 11.88
 0.75
 5.64

 DA-19
 0.80
 5.0
 6.48
 0.82
 4.26
 8.64
 0.84
 5.77
 9.84
 0.84
 6.64
 11.88
 0.86
 8.16

 DA-20
 0.09
 9.5
 5.47
 0.39
 0.20
 7.41
 0.45
 0.31
 8.53
 0.48
 0.39
 10.37
 0.55
 0.57
 DA-21 0.34 5.0 6.48 0.91 2.00 8.64 0.92 2.67 9.84 0.92 3.05 11.88 0.92 3.7 DA-22 0.31 5.0 6.48 0.87 1.72 8.64 0.88 2.32 9.84 0.88 2.65 11.88 0.89 3.2 DA-23 0.53 7.6 5.84 0.34 1.05 7.86 0.40 1.66 9.01 0.44 2.09 10.93 0.51 2.9 DA-24 0.42 5.5 6.35 0.34 0.92 8.48 0.40 1.44 9.67 0.44 1.81 11.69 0.51 2.5 DA-25 0.72 5.0 6.48 0.87 4.05 8.64 0.88 5.46 9.84 0.88 6.26 11.88 0.89 7.6 A g
 0.12
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 0.10
 <th0.10</th>
 0.10
 0.10
 <th0 DA-26 DA-27 DA-28 DA-29 0.16 5.0 6.48 0.88 0.93 8.64 0.88 1.25 9.84 0.89 1.44 11.88 0.90 1. DA-30 0.44 6.7 6.05 0.34 0.90 8.12 0.40 1.42 9.28 0.44 1.78 11.24 0.51 2. 0.41 5.0 6.48 0.86 2.29 8.64 DA-31 0.87 3.09 9.84 0.87 3.54 11.88 0.89 4.3 DA-32 0.22 5.0 6.48 0.86 1.20 8.64 0.87 1.62 9.84 0.87 1.86 11.88 0.88 2.2 0.61 5.0 6.48 0.83 3.29 8.64 0.84 4.45 9.84 0.85 5.11 11.88 0.87 6.2 DA-33 0.27 5.0 6.48 0.88 1.52 8.64 0.88 2.05 9.84 0.89 2.35 11.88 0.90 2.8 DA-34 0.37 14.6 4.66 0.35 0.61 6.40 0.41 0.98 7.44 0.45 1.24 9.09 DA-35 0.52 1.7 DA-36 0.12 5.0 6.48 0.92 0.70 8.64 0.92 0.94 9.84 0.92 1.07 11.88 0.93 1.3 DA-37 0.22 5.0 6.48 0.60 0.87 8.64 0.64 1.23 9.84 0.66 1.45 11.88 0.70 1.8 0.74 5.0 6.48 0.60 2.89 8.64 0.64 4.07 9.84 0.66 4.80 11.88 0.70 6.1 DA-38
 DA-39
 0.19
 7.1
 5.95
 0.34
 0.39
 8.00
 0.40
 0.61
 9.16
 0.44
 0.77
 11.09
 0.51
 1.08
 Drains into grate inlet

 DA-40
 0.35
 6.8
 6.03
 0.34
 0.71
 8.09
 0.40
 1.12
 9.26
 0.44
 1.41
 11.21
 0.51
 1.97
 Drains into grate inlet

ORIGINAL SHEET - ARCH D




COMMENTS

ewer
ewer
ond
ve
t
t
t
t
t
:
:
t
:
t
t
t i
t

3	4	5	
3	DA 24 0.42 AC	DA 23 0.53 AC DA 10 0.21 AC	AnotherAnoth
DA 27 0.11 AC DA 28 0.50 AC DA 29 0.16 AC DA 7 0.29 AC DA 31 0.41 AC DA 40 0.35 AC	0.21 AC	DA 22 0.32 AC DA 20 0.08 AC DA 21 0.34 AC MATCHLINE SEE SHEET 11	By Appd Image: Sime set of the
INLET # DRAINAGE INLET Q-25 Q-BY Q-TOT SLOPE	(ff/ft) FLOW (ft.) (ft.) SLOPE (Se) SIZE (II) 0.02 0.016 0.3310 16.549 0.268 8.388 OK	Image: Section of the s	Permit/Seal BRIAN E. CARRINGTON 123263 CENSSIONAL 4/28/2023
INLET # DRAINAGE INLET Q-100 Q-BY Q-TOT SLOPE	CROSS SLOPE (ft/ft)nOF GUTTER FLOW (ft.)PONDED WIDTH (ft.)EFFECTIVE SLOPE(Se)REQUIRED SIZE (ft)PASS?0.020.0160.35917.9680.2669.245OK	Q-bypassBY-PASS TO DA-CURB DEPRES SION (ft.)DEPRES SION (ft.)AwPwKwAoPoKoEo0.000.479171.50.8759171.58406151.355842.71197416.4680715.294720.770524	Client/Project DUKE, INC. CHAPEL HILL PHASE 2 403 WESTINGHOUSE ROAD, GEORGETOWN, TEXAS 78626

JA 31 DA 33 DA 31 DA 14 AC	A TCHLNE SEE SHEET 11 A SOUND SEE SHEET 11	Image: Section
SISPER ON-GRADE CURB INLET CAPACITY CALCULATIONS INLET # DRAINAGE AREA INLET SIZE (ft) Q-25 Q-BY Q-TOT LONG. SLOPE (ft/ft) CROSS SLOPE (ft/ft) n DEPTH OF GUTTER FLOW (ft) C1 DA-13 10 7.67 7.67 0.007 0.02 0.016 0.3310 IOD-YEA FON-GRADE CURB INLET CAPACITY CALCULATIONS INLET # DRAINAGE AREA INLET Q-100 Q-BY Q-TOT LONG. SLOPE SLOPE CROSS SLOPE SLOPE DEPTH OF GUTTER FLOW	PONDED WIDTH (ft.)EFFECTIVE SLOPE (Se)REQUIRED SIZE (ft)PASS?Q-bypassBY-PASS TO DA-CURB SION (ft.)DEPRES SION (ft.)AwPwKwAoPoKoEo16.5490.2688.388OK0.000.479171.50.8333341.58406148.859182.26461915.0486513.976430.777571PONDED WIDTH (ft.)EFFECTIVE SLOPE (Se)REQUIRED SIZE (ft)PASS?Q-bypassBY-PASS TO DA-CURB SION (ft.)DEPRES SION (ft.)AwPwKwAoPoKoEo	4/28/2023
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$	17.9680.2669.245OK0.000.479171.50.8759171.58406151.355842.71197416.4680715.294720.770524On-Grade Curb EquationLT = Kt*Q*0.42*St*0.3*[1/(n*Se)]*0.6LT = curb opening required to intercept 100% of the gutter flow (ft) Kt=0.6Q = gutter flow (cls) S1 = longitudinal slope (ft/t) Se = equireant cross slope for depressed guttersGrate Inlet Equation Submerged grate inlets use the orfice equation: Submerged grate inlets use the orfice equation: S= longitudinal slope (ft/t) S = longitudinal slope (ft/t) 	Revision:0 Sheet: 10 of 38 Drawing No.

	Grate Inlet Flow Calculation Table (50% Clogging Factor)									
Inlet No.	Drainage Area	Inlet Size	Q 25 Yr (CFS)	Q 100 Yr (CFS)	h (FT)	Open Area (SF)	Q Capacity (CFS)	Capacity with 50% Clogging (CFS)	Q25 Pass?	
OS G2	OS DA-2	2'x2'	0.77	0.96	2.00	1.60	10.91	5.45	YES	
OS G3	OS DA-3	2'x2'	1.81	2.25	2.00	1.60	10.91	5.45	YES	
G1	DA-19	2.5'x2.5'	8.40	10.29	2.00	2.50	17.04	8.52	YES	
G2	DA-20	2'x2'	1.44	1.80	2.00	1.60	10.91	5.45	YES	
G3	DA-21	2'x2'	3.05	3.70	2.00	1.60	10.91	5.45	YES	
G4	DA-22	2'x2'	2.82	3.44	2.00	1.60	10.91	5.45	YES	
G5	DA-23	2'x2'	2.79	3.78	2.00	1.60	10.91	5.45	YES	
G6	DA-25	3'x3'	10.60	12.36	2.00	3.60	24.54	12.27	YES	
G7	DA-26	2'x2'	2.36	3.01	2.00	1.60	10.91	5.45	YES	
G8	DA-27	2'x2'	1.23	1.57	2.00	1.60	10.91	5.45	YES	
G9	DA-28	2'x2'	4.88	5.95	2.00	1.60	10.91	5.45	YES	
G10	DA-29	2'x2'	1.78	2.17	2.00	1.60	10.91	5.45	YES	
G11	DA-31	2'x2'	4.92	6.00	2.00	1.60	10.91	5.45	YES	
G12	DA-32	2'x2'	2.26	2.75	2.00	1.60	10.91	5.45	YES	
G13	DA-33	3'x3'	9.60	11.17	2.00	3.60	24.54	12.27	YES	
G14	DA-34	2'x2'	2.92	3.55	2.00	1.60	10.91	5.45	YES	
G15	DA-35	2'x2'	3.30	4.24	2.00	1.60	10.91	5.45	YES	
G16	DA-36	2'x2'	1.30	1.58	2.00	1.60	10.91	5.45	YES	
G17	DA-37	2'x2'	1.78	2.26	2.00	1.60	10.91	5.45	YES	
G18	DA-38	2.5'x2.5'	5.48	6.97	2.00	2.50	17.04	8.52	YES	




ORIGINAL SHEET - ARCH D


Grate Inlet Flow Calculation Table (50% Clogging Factor)	4 5 DRAINAGE BASIN AREA 5	,
Drainage Inlet Q 25 Yr Q 100 Yr Area Size (CFS) (CFS) (CFS) h (FT) Area (SF) (CFS) (RATIONAL METHOD CALCULATIONS References: City of Georgetown Drainage Criteria Manual	
P OS DA-2 2'x2' 0.77 0.96 2.00 1.60 10.91 5.45 YES B OS DA-3 2'x2' 1.81 2.25 2.00 1.60 10.91 5.45 YES	Formulas:Rational MethodIntensity (in/hr)i = a / ((T_c+b)^c)	
DA-19 2.5'x2.5' 8.40 10.29 2.00 2.50 17.04 8.52 YES DA-20 2'x2' 1.44 1.80 2.00 1.60 10.91 5.45 YES DA-21 2'x2' 3.05 3.70 2.00 1.60 10.91 5.45 YES	Q = CiA 2-year 10-year 25-year 100-year Q = design flow (cfs) a= 106.29 96.84 111.07 129.03 C = weighted 'C' coefficient b= 16.81 15.88 17.23 17.83	
DA-22 2'x2' 2.82 3.44 2.00 1.60 10.91 5.45 YES DA-23 2'x2' 2.79 3.78 2.00 1.60 10.91 5.45 YES DA-25 3'x3' 10.60 12.36 2.00 3.60 24.54 12.27 YES	i = Intensity (in/hr) c= 0.9076 0.7952 0.7815 0.7625 2-YEAR 10-YEAR 25-YEAR 100-YEAR Sub-Basin Intensity Weighted 'C' Sub-Basin Intensity Weighted Sub-Basin	b-Basin COMMENTS
DA-26 2'x2' 2.36 3.01 2.00 1.60 10.91 5.45 YES DA-27 2'x2' 1.23 1.57 2.00 1.60 10.91 5.45 YES DA-28 2'x2' 4.88 5.95 2.00 1.60 10.91 5.45 YES	$\frac{ \text{ID} ^{\text{Area}(ac)} }{ \text{ID} ^{\text{Area}(ac)} } (\text{min}) (\text{in/hr}) Value Q_2 (cfs) \frac{ \text{Intensity} }{ C' Value Q_{10} (cfs) } \frac{ \text{Intensity} }{ C' Value Q_{25} (cfs) } \frac{ \text{Intensity} }{ C' Value Q_1 (cfs) } \frac{ \text{Intensity} }{ C' Value Q_{25} (cfs) } \frac{ \text{Intensity} }{ C' Value Q_2 (cfs) } \text{Intens$	
DA-29 2'x2' 1.78 2.17 2.00 1.60 10.01 5.45 YES DA-31 2'x2' 4.92 6.00 2.00 1.60 10.91 5.45 YES DA-32 2'x2' 2.26 2.75 2.00 1.60 10.91 5.45 YES	DA-2 0.22 5.0 6.48 0.97 1.39 8.64 0.97 1.85 9.84 0.97 2.10 11.88 0.97 DA-3 0.29 5.0 6.48 0.97 1.84 8.64 0.97 2.45 9.84 0.97 2.79 11.88 0.97	2.42Roof drains into storm sewer2.54Roof drains into storm sewer3.37Roof drains into storm sewer2.42Roof drains into storm sewer
DA-33 3'x3' 9.60 11.17 2.00 3.60 24.54 12.27 YES DA-34 2'x2' 2.92 3.55 2.00 1.60 10.91 5.45 YES	DA-5 0.21 5.0 6.48 0.97 1.32 8.64 0.97 1.76 9.84 0.97 2.00 11.88 0.97 DA-6 0.29 5.0 6.48 0.97 1.84 8.64 0.97 2.45 9.84 0.97 2.79 11.88 0.97	2.42Roof drains into storm sewer3.37Roof drains into storm sewer
DA-35 2'x2' 3.30 4.24 2.00 1.60 10.91 5.45 YES DA-36 2'x2' 1.30 1.58 2.00 1.60 10.91 5.45 YES DA-37 2'x2' 1.78 2.26 2.00 1.60 10.91 5.45 YES DA-37 2'x2' 1.78 2.26 2.00 1.60 10.91 5.45 YES	DA-8 0.21 5.0 6.48 0.97 1.32 8.64 0.97 1.76 9.84 0.97 2.00 11.88 0.97 DA-9 0.22 5.0 6.48 0.97 1.39 8.64 0.97 1.85 9.84 0.97 2.10 11.88 0.97	3.37Roof drains into storm sewer2.42Roof drains into storm sewer2.54Roof drains into storm sewer
DA-38 2.5'x2.5' 5.48 6.97 2.00 2.50 17.04 8.52 YES	DA-11 0.14 5.0 6.48 0.97 0.85 8.64 0.97 1.13 9.84 0.97 1.29 11.88 0.97 DA-12 0.46 5.0 6.48 0.36 1.06 8.64 0.42 1.65 9.84 0.46 2.05 11.88 0.97	2.42Roof drains into storm sewer1.56Roof drains into storm sewer2.84Roof drains into storm sewer
	DA-14 0.37 5.0 6.48 0.36 0.86 8.64 0.41 1.33 9.84 0.45 1.66 11.88 0.52 5.0 DA-15 0.52 5.0 6.48 0.38 1.28 8.64 0.44 1.96 9.84 0.48 2.42 11.88 0.54	8.01Drains into curb inlet2.30Drains offsite3.33Drains offsite
S DEPRES SION AW PW KW AO PO KO EO SION (ft.) (ft.)	DA-17 0.30 5.0 6.48 0.39 0.76 8.64 0.44 1.16 9.84 0.48 1.44 11.88 0.54 DA-18 0.63 5.0 6.48 0.67 2.75 8.64 0.70 3.82 9.84 0.72 4.47 11.88 0.75	19.14Drains offsite1.97Drains into proposed pond5.64Drains onto access drive
0.47917 1.5 0.833334 1.584061 48.85918 2.264619 15.04865 13.97643 0.777571	DA-20 0.09 9.5 5.47 0.39 0.20 7.41 0.45 0.31 8.53 0.48 0.39 10.37 0.55 DA-21 0.34 5.0 6.48 0.91 2.00 8.64 0.92 2.67 9.84 0.92 3.05 11.88 0.92	8.16Drains into grate inlet0.53Drains into grate inlet3.70Drains into grate inlet
S CURB SION DEPRES	DA-23 0.53 7.6 5.84 0.34 1.05 7.86 0.40 1.66 9.01 0.44 2.09 10.93 0.51 DA-24 0.42 5.5 6.35 0.34 0.92 8.48 0.40 1.44 9.67 0.44 1.81 11.69 0.51	3.24Drains into grate inlet2.94Drains into grate inlet2.52Drains into DA-25
- BEPRES WIDTH AW PW KW AO PO KO EO SION (ft.) (ft.)	DA-26 0.24 12.1 5.02 0.36 0.43 6.85 0.42 0.68 7.92 0.46 0.86 9.66 0.53	7.64Drains into grate inlet1.21Drains into grate inlet0.67Drains into grate inlet
0.47917 1.5 0.875917 1.584061 51.35584 2.711974 16.46807 15.29472 0.770524	DA-29 0.16 5.0 6.48 0.88 0.93 8.64 0.88 1.25 9.84 0.89 1.44 11.88 0.90	5.25Drains into grate inlet1.75Drains into grate inlet2.50Drains into DA-33
	DA-32 0.22 5.0 6.48 0.86 1.20 8.64 0.87 1.62 9.84 0.87 1.86 11.88 0.88	4.33Drains into grate inlet2.27Drains into grate inlet6.27Drains into grate inlet
Chapel Hill Phase 2 Onsite Proposed Conditions 2-YR 10 Yr 25-YR 100-YR	DA-35 0.37 14.6 4.66 0.35 0.61 6.40 0.41 0.98 7.44 0.45 1.24 9.09 0.52	2.86Drains into grate inlet1.75Drains into grate inlet1.30Drains into grate inlet
(CFS)(CFS)(CFS)Point of Interest 121.7143.7450.6659.71	DA-38 0.74 5.0 6.48 0.60 2.89 8.64 0.64 4.07 9.84 0.66 4.80 11.88 0.70	1.86Drains into grate inlet6.14Drains into grate inlet1.08Drains into grate inlet
	DA-40 0.35 6.8 6.03 0.34 0.71 8.09 0.40 1.12 9.26 0.44 1.41 11.21 0.51	1.97 Drains into grate inlet
	A 40 .35 AC	MAICHLINE See sheet 10
		\sim
DA 39		
	DA 15 0.52 AC	0 40' 80'
	DA 19 0.80 AC EXISTING	LEGEND PROPOSED DESCRIPTION
	DOCUMENT NO. 2020145589	-/
	AMER V CHAPEL HILL LLC DOC. NDS. 2020010911, 2020110912, & 2020011100	EX. DA 11.03 AC
DA 38 0.74 AC		
0.14 AC		

3

MATCHLINE SEE SHEET 12



now what's **below. Call** before you dig.





Û


Z

Ŋ









LEGEND EXISTING PROPOSED DESCRIPTION ____ PROPERTY LINE/(R.O.W.) LINE RECORD INFORMATION LIGHT POLE POWER POLE РРØ GROUND LIGHT DOWN GUY JUNCTION BOX T TRANSFORMER (SIZE VARIES) SW ELECTRICAL SWITCHBOX FIRE HYDRANT \bullet WATER VALVE WATER METER WATER METER VAULT WM BACKFLOW PREVENTER TELEPHONE RISER CABLE TV RISER ELECTRIC BOX ELECTRIC METER GAS METER GAS VALVE TRAFFIC CONTROL BO TRAFFIC SIGNAL POST TCB**∭** TSP ● GRATE INLET CURB INLET (SIZE VARIES) GT GREASE TRAP (SIZE VARIES) CHAINLINK FENCE WOOD FENCE OVERHEAD ELECTRIC EMH 💽 ELECTRIC MANHOLE (SIZE VARIES) WASTEWATER MANHOLE (SIZE VARIES) STORMSEWER MANHOLE (SIZE VARIES) тмн(●) TELEPHONE MANHOLE (SIZE VARIES) WATER MANHOLE CO WASTEWATER CLEANOUT DUMPSTER CURB & GUTTER ADA ACCESS ROUTE CONCRETE SIDEWALKS WHEELSTOP BOLLARD PARKING COUNT (REGULAR SPACES) PARKING COUNT (HANDICAP SPACES) HC PARKING COUNT COMPACT SPACES) C PARKING COUNT COMPACT SPACES) TREE TO REMAIN HANDICAP SPACE 6 111111 BIKE RACK - - BICYCLE ACCESS ROUTE ZONING LIMITS LINE PEDESTRIAN ACCESS ROUTE ----- SETBACK LINE CARPORT SPACES GARAGE SPACES

FIRE APPARATUS ACCESS ROAD GATES:

- GATES SECURING FIRE APPARATUS ACCESS ROADS SHALL COMPLY WITH ALL OF THE FOLLOWING THE MINIMUM UNOBSTRUCTED GATE WIDTH SHALL BE 20 FEET (6096MM). EXCEPTION: ONE- AND TWO-FAMILY DWELLINGS AS APPROVED BY THE FIRE CODE OFFICIAL.
 GATES SHALL BE OF THE SWINGING OR SLIDING TYPE.
 CONSTRUCTION OF GATES SHALL BE OF MATERIALS THAT ALLOW MANUAL OPERATION BY
- GATE COMPONENTS SHALL ALWAYS BE MAINTAINED IN AN OPERATIVE CONDITION AND REPLACED OR REPAIRED WHEN DEFECTIVE.
- 5. ELECTRICALLY OPERATED GATES: A. SHALL BE EQUIPPED WITH A MEANS OF OPENING THE GATE BY FIRE DEPARTMENT PERSONNEL FOR EMERGENCY ACCESS. EMERGENCY ACCESS DEVICES SHALL BE APPROVED BY THE FIRE CODE OFFICIAL.
- SHALL BE IN THE FULLY OPENED POSITION FOR NO MORE THAN 30 SECONDS. SHALL HAVE A MANUAL OVERRIDE SYSTEM. MANUAL OVERRIDE OPERATIONS SHALL BE LOCATED ON THE ENTRANCE SIDE OF THE GATE, OR WHEN POWER IS RESTORED FOR NORMAL OPERATIONS. . SHALL HAVE INSTALLED APPROVED PREEMPTIVE CONTROL OPENING EQUIPMENT.
- E. EXCEPTIONS I. DRIVEWAYS SERVING ONE- AND TWO- FAMILY DWELLINGS AS APPROVED BY THE THE FIRE CODE OFFICIAL. II. GATES SERVING AS AN EMERGENCY ACCESS WITH 24-HOUR STAFFED GATEHOUSES
- A. MANUAL OFERATING GATES.
 A. MAY BE LOCKED WHEN APPROVED BY THE FIRE CODE OFFICIAL.
 B. IF EQUIPPED WITH A LOCK, KEYS SHALL BE PROVIDED FOR INSTALLATION INTO AN APPROVED FIRE DEPARTMENT KEY BOX. KEYS SHALL BE MAINTAINED CURRENT.
 7. LOCKING DEVICE SPECIFICATIONS SHALL BE SUBMITTED FOR APPROVAL BY THE FIRE CODE
- 8. ELECTRIC GATE OPERATORS, WHERE PROVIDED, SHALL BE LISTED IN ACCORDANCE WITH UL 9. GATES INTENDED FOR AUTOMATIC OPERATION SHALL BE DESIGNED, CONSTRUCTED AND INSTALLED TO COMPLY WITH THE REQUIREMENTS OF ASTM F2200. 10. A CONSTRUCTION PERMIT IN ACCORDANCE WITH SUBSECTION 503.6 IS REQUIRED TO INSTALL
- OR MODIFY A GATE ACROSS FIRE APPARATUS ROADWAYS. 11. MAINTENANCE OF GATES SECURING FIRE APPARATUS ACCESS. GATES SHALL BE MAINTAINED IN AN OPERATIVE CONDITION AND REPAIRED OR REPLACED WHEN DEFECTIVE. WHEN REQUIRED BY THE FIRE CODE OFFICIAL, DEFECTIVE GATES SHALL BE SECURED IN THE OPEN POSITION

PARKING TABLE								
		TOTAL	MINIMUM					
PROPOSED) USE	UNITS	PARKING RATIO	REQUIRED				
			PARKINGRATIO	PARKING				
	1 BR	156	1 SPACE/UNIT*	156				
MUTIFAMILY	2 BR	108	2 SPACES/UNIT*	216				
	3 BR	12	2 SPACES/UNIT*	24				
	VISITOR		5% OF TOTAL	20				
-	TOTAL REQU	JIRED PAF	KING SPACES: 416					
TOTAL PROVIDED PARKING SPACES: 426								
RE	QUIRED AC	CESSIBLE	PARKING SPACES: 12					

PROVIDED CARPORT PARKING SPACES: 312 PROVIDED STANDARD PARKING SPACES: 56 * MINIMUM PARKING RATIO REQUIRED PER PUD ORD 2020-49 ** 12 STANDARD ACCESSIBLE SPACES PLUS 2 ACCESSIBLE GARAGE SPACES

> THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND DESERVE ANY AND ALL UNDERCOUND UTILITIES AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.


2021-65-SDP

Project No.: 222012278 ile Name: 222012278SPN01 cale: 1.12.2024 Dwn. Dsgn. Chkd. YYYY.MM.DD **Title** MASTER SITE PLAN


N

Ш

AS RC





Permit/Seal \mathbf{X} BRIAN E. CARRINGTON 123263 4/28/2023



Φ

G





LEGEND		
XISTING	PROPOSED	DESCRIPTION
XXX A A A A A A A A A A A A A A A A A A	₽₽ <i>Ø</i>	PROPERTY LINE/ (R.O.W.) LINE RECORD INFORMATION LIGHT POLE GROUND LIGHT POWER POLE DOWN GUY
0	T	WATER LINE MARKER TRANSFORMER (SIZE VARIES)
\oplus \circ	_ ◆ × ⊙ ⊑	FIRE HYDRANT FIRE DEPARTMENT CONNECTION WATER VALVE WATER METER
	WM	WATER METER VAULT BACKFLOW PREVENTER
		GRATE INLET CURB INLET (SIZE VARIES) WIRE FENCE
	w	WATER LINE
WW G	WW G	WASTEWATER LINE GAS LINE
UE	UE	ELECTRIC LINE
wwmh o		WASTEWATER MANHOLE (SIZE VARIES)
SSMH O	$\bullet \bullet$	STORMSEWER MANHOLE (SIZE VARIES)
<i>co</i> ° WTRMH ●	CO•	WASTEWATER CLEANOUT WATER MANHOLE
678	678-	CURB & GUTTER CONCRETE SIDEWALKS WALL CONTOUR TREE TO REMAIN
		ROW EASEMENT

WASTEWATER SERVICE CONSTRUCTION NOTES:

INSTALL 6" PVC SDR-26 WASTEWATER SERVICE.

[2] INSTALL 8" PVC SDR-26 WASTEWATER SERVICE.


CONNECT SERVICE TO BUILDING. SEE PLUMBING PLAN FOR EXACT BUILDING POINT OF CONNECTION AND 2-WAY

WASTEWATER CROSSING OVER WATER PIPE:


1. INSTALL A MINIMUM OF 18 LF (CENTERED ON THE CROSSING WATER PIPE) OF 12-INCH DIAMETER CASING PIPE WITH SPACERS AND SEALED ON EACH END

 $\sim\!\!\sim\!\!\sim\!\!\sim\!\!\sim\!\!\sim\!\!\sim$

- ALTERNATE: INSTALL A MINIMUM OF 18 LF OF 8-INCH DIAMETER PIPE WITH MIN. 150 PSI PRESSURE RATING (CENTERED ON THE CROSSING WATER PIPE) INSTEAD OF THE EQUIVALENT LENGTH OF SDR 26 PIPE.
 ALTERNATE: INSTALL A MINIMUM OF 18 LF OF 8-INCH DIAMETER PIPE WITH MIN. 150 PSI PRESSURE RATING
- (CENTERED ON THE CROSSING WATER PIPE) INSTEAD OF THE EQUIVALENT LENGTH OF SDR 26 PIPE.
- WASTEWATER PIPE CROSSING UNDER WATER PIPE: 1. FOR PIPES CLEARING BY AT LEAST 2' VERTICALLY. INSTALL
- 8" SDR 26 WASTEWATER PIPE IN MINIMUM OF 18 LF OF CEMENT-STABILIZED SAND EMBEDMENT TO BE CENTERED ON THE CROSSING WATER PIPE. 2. EMBEDMENT TO CONTAIN A MIN. OF 160 LBS OF PORTLAND
- CEMENT PER CY. 3. EMBEDMENT ENVELOPE SHALL START AT BOTTOM OF PIPE AND EXTEND TO 12" ABOVE THE PIPE AND 6" TO EACH SIDE OF WASTEWATER PIPE.









THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. 2021-65-SDP


900 896 PROP. GRADE EX. GRADE 6" WATER 6" WATER 892 -6" WATER ±201 LF 8" PVC SDR-26 • 0.50% ±204 LF 8" PVC SDR-26 **9** 0.50% 888 . 8" PVC ₩₩¬ 884 $\sim\sim\sim$ †6**" water{─** INSTALL MIN. 18 LF OF CEMENT-STABILIZED SAND EMBEDMENT CENTERED ON WATER PIPE (SEE NOTES 12 K 65 880 886. 886. <u>887.</u> 887. THIS SHEET) 0+00.00 W WWMH IN (NW)= 0UT (SE)= EV.=894.8 4+19.61 W WMH IN (NW)= IN (SW)= OUT (SE)= EV.=892.1 74.73 00.00 DR0F <u>2+78.72</u> <u>WMH</u> IN (NW) OUT (E) EV.=894 876 !ੇ≦ ਦੇ ਦੇ ' ੵੑਫ਼ੵਜ਼ੵਜ਼ 8 8 8 4 IIA 893.4 886.96 893.2 887.08 893.8 **387.33** 894.0 **887.45** 893.7 **86.73** 893.5 87.20 894.1 3**87.68** 893.0 396.9 9+50 10+00 11+00 12+00 13+00 14+00 15+00 WW A STA. 10+00.00 - 16+18.51 912 908 904 ±172 LF 8" PVC SDR-26 • 0.50% SDR-26 0 0.50% 900 896 - INSTALL MIN. 18 LF OF 12" - DIA CASING PIPE -CENTERED ON WATER PIPE 8" WATER-W-C 899.60 899.29 = 899.29 892 (SEE NOTES THIS SHEET) 72.13 (NW)= (SW)= (SW)= (SW)= 35 A. 10+00.0(A. 12+33.7 DIA WWMH FL IN (N)= FL IN (NW) FL OUT (S) 888 ±₿zz82 906.8 899.01 899.01 906.8 899.14 906.5 899.70 906.5 906.6 899.70 906.6 906.6 906.6 906.2 906.6 906.2 906.6 906.2 906.4 906.2 906.4 906.2 906.4 906.2 906.1 906.2 906.1 906.2 900.2 906.2 9 906.4 **898.64** 906.6 **898.76** 9+50 10+00 11+00 12+00 13+00


WW C STA. 10+00.00 - 15+23.29

ORIGINAL SHEET - ARCH D











904





ORIGINAL SHEET - ARCH D

..... 2021-65-SDP