# TCEQ ORGANIZED SEWAGE COLLECTION SYSTEM PLAN

HTG Red Oaks 11723 N FM 620 Rd. Austin, TX 78735

February 2024

Prepared For: HTG Anderson, LLC 3225 Aviation Avenue,

Coconut Grove, FL 33133

Prepared By:
Kimley-Horn and Associates, Inc.
10814 Jollyville Road
Building IV, Suite 200
Austin, TX 78759
TEXAS REGISTRATION #928



# **Table of Contents**

<b>Section 1</b> Edwards Aquifer Application Cover Page (TCEQ-20705)	1
Edwards Aquirer Application Cover Page (TCEQ-20703)	4
Section 2	
General Info Form (TCEQ-0587)	9
Attachment A	
Attachment B	16
Attachment C	18
Section 3	
Geologic Assessment Form (TCEQ-0585)	19
Attachment A	23
Attachment B	25
Attachment C	27
Attachment D	29
Section 4	
Application Form, Organized Sewage Collection System Application (TCEQ-0582)	32
Attachment A	
Attachment B	46
Attachment C	47
Attachment D	48
Section 5	
Temporary Stormwater Section (TCEQ-0602)	74
Attachment A	80
Attachment B	82
Attachment C	83
Attachment D	84
Attachment E	85
Attachment F	86
Attachment G	
Attachment H	89
Attachment I	90
Attachment J	93
Section 6	
Agent Authorization Form (TCEQ-0599)	95

Section 7	
Application Fee Form (TCEQ-0574)	99
Section 8	
Core Data Form (TCEQ-10400)	102

# **SECTION 1**

Edwards Aquifer Application Cover Page (TCEQ-20705)

### **Texas Commission on Environmental Quality**

## **Edwards Aquifer Application Cover Page**

#### **Our Review of Your Application**

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

#### **Administrative Review**

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
  - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <a href="http://www.tceq.texas.gov/field/eapp">http://www.tceq.texas.gov/field/eapp</a>.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
  - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

#### **Technical Review**

- When an application is deemed administratively complete, the technical review period begins. The regional
  office will distribute copies of the application to the identified affected city, county, and groundwater
  conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
  to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

#### **Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity N	ame:	НТ	G Red	d Oak	S	2. Re	egulate	ed Entity No.:	
3. Customer Name: HTG Anderson, LLC			4. Customer No.:						
5. Project Type: (Please circle/check one)	New		Modification Extens		sion	Exception			
6. Plan Type: (Please circle/check one)	WPAP C	CZP (	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residenti	ial	Non-residential		8. Site		e (acres):	3.57	
9. Application Fee:	\$650	)	10. Permanent BN			BMP(s	s):	Partial sedime	ntation/biofiltration pond
11. SCS (Linear Ft.):	475	·	12. AST/UST (No. Ta			o. Tar	ıks):		
13. County:	Williams	son	14. Watershed:					Lake Creek	

## **Application Distribution**

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field\_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)			X		
Region (1 req.)			X		
County(ies)			X		
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	X Austin Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock		

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)			_		
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.		
Kyle Moore, P.E.		
Print Name of Customer/Authorized Agent		
H M	02/02/2024	
Signature of Customer/Authorized Agent	Date	

**FOR TCEQ INTERNAL USE ONLY**			
Date(s)Reviewed:	Date Ad	ministratively Complete:	
Received From:	Correct	Number of Copies:	
Received By:	Distribu	ntion Date:	
EAPP File Number:	Complex	x:	
Admin. Review(s) (No.):	No. AR	Rounds:	
Delinquent Fees (Y/N):	Review '	Time Spent:	
Lat./Long. Verified:	SOS Cus	stomer Verification:	
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):	
Core Data Form Complete (Y/N):	Check:	Signed (Y/N):	
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):	

# **SECTION 2**

General Info Form (TCEQ-0587)

## **General Information Form**

#### **Texas Commission on Environmental Quality**

Print Name of Customer/Agent: Kyle Moore, P.E.

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Da	Date: <u>02/02</u> /2024	
Sig	Signature of Customer/Agent:	
1	L M	
Pi	Project Information	
1.	1. Regulated Entity Name: HTG Red Oaks	
2.	2. County: Williamson	
3.	3. Stream Basin: Colorado River	
4.	4. Groundwater Conservation District (If applicable):	
5.	5. Edwards Aquifer Zone:	
	X Recharge Zone Transition Zone	
6.	6. Plan Type:	
	WPAP AST   X SCS UST   X Modification Exception Request	

7.	Customer (Applicant):	
	Contact Person: Matthew Rieger Entity: HTG Anderson, LLC Mailing Address: 3225 Aviation Ave. City, State: Coconut Grove, FL Telephone: (786) 347-4554 Email Address: mattr@htgf.com	Zip: FAX:
8.	Agent/Representative (If any):	
	Contact Person: Kyle Moore, P.E. Entity: Kimley-Horn and Associates, Inc. Mailing Address: 10814 Jollyville Rd., Bldg 4, St. City, State: Austin, TX Telephone: (512) 418-1771 Email Address: kyle.moore@kimley-horn.com	te 200 Zip: FAX:
9.	Project Location:	
	<ul> <li>X The project site is located inside the city limits</li> <li>The project site is located outside the city limit jurisdiction) of</li> <li>The project site is not located within any city's</li> </ul>	s but inside the ETJ (extra-territorial
10.	<ul> <li>The location of the project site is described bel detail and clarity so that the TCEQ's Regional st boundaries for a field investigation.</li> <li>11723 N FM 620, Austin, TX 78750</li> </ul>	
11	X Attachment A – Road Map. A road map showi	ng directions to and the location of the
11.	project site is attached. The project location and the map.	_
12.	X Attachment B - USGS / Edwards Recharge Zon USGS Quadrangle Map (Scale: 1" = 2000') of th The map(s) clearly show:	
	<ul> <li>X Project site boundaries.</li> <li>X USGS Quadrangle Name(s).</li> <li>X Boundaries of the Recharge Zone (and Trank)</li> <li>X Drainage path from the project site to the k</li> </ul>	
13.	X The TCEQ must be able to inspect the project sufficient survey staking is provided on the protect the boundaries and alignment of the regulated features noted in the Geologic Assessment.	ject to allow TCEQ regional staff to locate
	Survey staking will be completed by this date: _	

narra	chment C – Project Description. Attached at the end of this form is a detailed ative description of the proposed project. The project description is consistent ughout the application and contains, at a minimum, the following details:
	rea of the site  Offsite areas  Impervious cover  Impervious BMP(s)  Imposed site use  Ite history  Ite revious development  Ite a(s) to be demolished
15. Existing ր	project site conditions are noted below:
E:   E:   U   X  U	xisting commercial site xisting industrial site xisting residential site xisting paved and/or unpaved roads Indeveloped (Cleared) Indeveloped (Undisturbed/Uncleared) Other:
Prohibit	ted Activities
	aware that the following activities are prohibited on the Recharge Zone and are not osed for this project:
	Vaste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Inderground Injection Control);
(2) N	lew feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
(3) La	and disposal of Class I wastes, as defined in 30 TAC §335.1;
(4) T	he use of sewage holding tanks as parts of organized collection systems; and
st	lew municipal solid waste landfill facilities required to meet and comply with Type I tandards which are defined in §330.41(b), (c), and (d) of this title (relating to Types f Municipal Solid Waste Facilities).
, ,	lew municipal and industrial wastewater discharges into or adjacent to water in the tate that would create additional pollutant loading.
<u> </u>	aware that the following activities are prohibited on the Transition Zone and are proposed for this project:

(1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground

(2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and


Injection Control);

(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.


## Administrative Information

18. Th	e fee for the plan(s) is based on:
X	For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.  For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.  For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.  A request for an exception to any substantive portion of the regulations related to the protection of water quality.  A request for an extension to a previously approved plan.
19. X	Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:
	<ul> <li>TCEQ cashier</li> <li>Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)</li> <li>San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)</li> </ul>
20. X	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
21. X	No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

# Attachment A Road Map



# Attachment B USGS Quadrangle Map



# Attachment C Project Narrative

The proposed project is located at 11723 N FM 620, Austin, TX 78735 in the Full-Purpose Jurisdiction of the City of Austin in Williamson County, Texas. The existing platted property is approximately ±3.57 acres and is an undeveloped parcel (COA #: C8J-03-0095.0A). The site is currently undeveloped.

The proposed improvements include an affordable housing 70-unit multifamily complex with associated utility, water quality, drainage, grading, and site improvements. There will be no proposed offsite improvements as part of this project. This project is located within the Lake Creek watershed, a suburban watershed. No demolition will be required. Existing impervious cover area is 3.90% and development will increase cover to 54.59%.

No portion of this site is in the Federal Emergency Management Agency's 100-year flood plain according to Flood Insurance Rate Map #48491C0605F, dated December 20, 2019. The site is located within the Edwards Aquifer Recharge Zone according to City of Austin GIS and no critical water quality zone buffers encroach the site. Proposed best management practices (BMPs) include a partial sedimentation/biofiltration pond with stacked detention (pond). The pond will be sized to capture site runoff to control flow below existing conditions and is designed in accordance with City of Austin Watershed Protection Ordinance Regulations Summary Table, effective October 28, 2013, City of Austin Environmental Criteria Manual Appendix R-6, and TCEQ Technical Guidance Manual RG-348.

Access will be provided from N FM 620. Detention is required and a partial sedimentation/filtration pond is proposed on-site accordance with the City of Austin requirements. Existing storm infrastructure includes a private storm line along the western property line that gradually increases in size from 24" to 36". Flow travels from the southwest to the northeast and continues to a public storm line in El Salido Pkwy.

# **SECTION 3**

Geological Assessment Form (TCEQ-0585)

## **Geologic Assessment**

**Texas Commission on Environmental Quality** 

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Pri	nt Name of Geologist: <u>Dave Hill</u>	Telephone: <u>512 837 8005</u>
Da	te: <u>11 01 23</u>	Fax:
	presenting: <u>ECS Southwest, LLP Geology Firm 50</u> gistration number)	0674 (Name of Company and TBPG or TBPE
Sig	nature of Geologist:	STATE OF TETA
	David Itill	DAVID W. HILL  GEOLOGY 1480
Re	gulated Entity Name: HTG Red Oaks	SOUND GEOGRAPHICS
PI	roject Information	
1.	Date(s) Geologic Assessment was performed:	<u>10 27 23</u>
2.	Type of Project:	
	WPAP     SCS     SCS	☐ AST ☐ UST
3.	Location of Project:	
	Recharge Zone Transition Zone Contributing Zone within the Transition Zo	ne

4. X Attachmen	t A - Geol	ogic Assessment	Table	e. Complete	ed Geolo	gic Assess	ment Table			
(Form TCE	Q-0585-Ta	ble) is attached.								
Hydrologic 55, Append	Soil Grou lix A, Soil	ject site is summa ps* (Urban Hydro Conservation Serv w each soil type or	logy vice, :	for Small W 1986).  If th	atershed ere is mo	ds, Technio ore than o	cal Release No. ne soil type on			
Table 1 - Soil Ur		Soil Na	ame	Group*	Thickness(feet)					
Characteristics and Thickness										
Soil Name	Group*	Thickness(feet)		* Soil	Group De	efinitions (	(Abbreviated)			
GsB 1-3% Slope				A.			h infiltration			
Georgetown Stony Clay Loam	D	5	rate when thoroughly B. Soils having a modero infiltration rate when				oderate			
EeB 0-3% Slope Eckrant Stony Clay	D	6.7		wetted.  C. Soils having a slow infiltration rate when thoroughly wetted						
CfB 1-3% Slope			D. Soils having a very slow							
Crawford Clay	D	2.5		infiltration rate when thorou wetted.						
<ol> <li>Attachment B – Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.</li> <li>Attachment C – Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the</li> </ol>										
potential fo	potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.									
	8. X Attachment D – Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'									
	Applicant's Site Plan Scale: 1" =' Site Geologic Map Scale: 1" =' Site Soils Map Scale (if more than 1 soil type): 1" ='									
9. Method of coll	ecting po	sitional data:								
	☐ Global Positioning System (GPS) technology.  ☐ Other method(s). Please describe method of data collection: Google Earth									
							2 nf 3			

10. 🔀	The project site and boundaries are clearly shown and labeled on the Site Geologic Map
11. 🔀	Surface geologic units are shown and labeled on the Site Geologic Map.
12. 🗌	Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
	Geologic or manmade features were not discovered on the project site during the field investigation.
13. 🔀	The Recharge Zone boundary is shown and labeled, if appropriate.
	known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If olicable, the information must agree with Item No. 20 of the WPAP Application Section.
	There are (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)  The wells are not in use and have been properly abandoned.  The wells are not in use and will be properly abandoned.  The wells are in use and comply with 16 TAC Chapter 76.  There are no wells or test holes of any kind known to exist on the project site.
Adm	ninistrative Information
15. 🛚	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and

county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional

office.

# Attachment A Geological Assessment Table

GEOLOGI	GEOLOGIC ASSESSMENT TABLE						PR	OJE	CT NA	MI	E:	Red O	ak l	ECS Proje	ct 51-3	774				
	LOCATION					FEA	TUR	E CI	HARAC	ΓER	ISTIC	3			EVAL	.UA1	ΓΙΟN	PHY	SICAI	SETTING
1A	1B *	1C*	2A	2B	3		4		5	5A	6	7	8A	8B	9		10		11	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIME	NSIONS	(FEET)	TREND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	SENS	SITIVITY		ENT AREA RES)	TOPOGRAPHY
						Х	Υ	Z		10						<40	>40	<1.6	>1.6	
No features																				
																			-	0.00
																			68	1
																		1	MARKE.	in Holle
																			1811	GEOLOGY IS
																		1	May .	CENSSO S
																			7	Habers .

*	$\nabla$	ΤI	IN/	ŀ

DATOM:		
2A TYPE	TYPE	2B POINTS
С	Cave	30
sc	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
0	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
SW	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

	8A INFILLING
N	None, exposed bedrock
С	Coarse - cobbles, breakdown, sand, gravel
0	Loose or soft mud or soil, organics, leaves, sticks, dark colors
F	Fines, compacted clay-rich sediment, soil profile, gray or red colors
V	Vegetation. Give details in narrative description
FS	Flowstone, cements, cave deposits
Х	Other materials

	12 TOPOGRAPHY
Gently sloping	north

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field.


My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Date 10/27/2023

Sheet \_\_1\_\_ of \_\_1\_\_

TCEQ-0585-Table (Rev. 10-01-04)

# Attachment B Stratigraphic Column



# Attachment C Site Geology

#### NARRATIVE DESCRIPTION OF SITE-SPECIFIC GEOLOGY

Ranging from north to south, two primary physiographic provinces are present in Travis or Williamson County: the Great Southern Plains and the Gulf Coastal Plain. The Gulf Coastal Plain is comprised mainly of Blackland Prairie. The Great Southern Plain locally merges with the Edwards Plateau which is comprised chiefly of limestone plains.

Groundwater recharge and flow are controlled by faulted Edwards Aquifer and adjacent strata. Water enters the aquifer by means of solution features controlled by faults, fractures and solution conduits. Solution features are created by the dissolution of limestone primarily from rainwater and groundwater. Deformation of the Balcones fault system controls both the large and small-scale flow barriers and flow pathways present in the Edwards Aquifer.

Geological information pertaining to the area was obtained from the Geologic Atlas of Texas, Austin Sheet, published by University of Texas at Austin, Bureau of Economic Geology (BEG), 1997. The subject property is situated on Edwards Limestone, undivided (Ked) (Figure 6).

The Bureau of Economic Geology defines the Edwards Limestone (Ked) on the Austin Sheet of the Geologic Atlas (Geologic Atlas of Texas San Antonio Sheet, UT Austin, Texas BEG, 1974, reprinted 1995) as follows: limestone, dolomite, and chert; limestone aphanitic to fine grained, massive to thin bedded, hard, brittle, in part rudistid biostromes, much miliolid biosparite; dolomite fine to very fine grained, porous, medium gray to grayish brown; nodules and plates common, varies in amount from bed to bed, some intervals free of chert, mostly white to light gray; in zone of weathering considerably recrystallized, "honeycombed" and cavernous forming an aquifer; forms flat areas and plateaus bordered by scarps; thickness 60 - 350 feet, thins northward.

ECS did not observe potable water wells on the subject property. Evidence of septic systems was not observed during the site reconnaissance.

Potential natural recharge features such as caves, sinkholes, closed depressions, solution cavities, fractured rock outcrops, faults or lineaments were not observed on the subject property.

# Attachment D Site Geologic Map





ECS Southwest, LLP 14050 Summit Drive, Suite 104 Austin, Texas 78728 Phone: (512) 837-8005

www.ecslimited.com

ECS Project No. 51:3774

## El Salido Parkway Austin, Williamson County, Texas


Project Acreage: 3.573

**NRCS Soils Map** 

USGS Quadrangle: Jollyville, TX Watershed: San Gabriel

World Imagery: Williamson County TX, Maxar, Microsoft
Hybrid Reference Layer: Esri Community Maps Contributors, Austin Community College, City of
Austin, County of Williamson, Texas Parks & Wildlife, © OpenStreetMap, Microsoft, CONANP, Esri,
HERE, Garmin, SafeGraph, GeoTechnologies, Inc, METI/NASA, USGS, EPA, NPS, US Census

Bureau, USDA
USGS Topographic Map Jollyville, TX Quadrangle 2019
Soils Data: USDA NRCS Web Soil Survey
Wetlands Data: National Wetlands Inventory Floodplain Data: FEMA National Flood Hazard Layer LIDAR Data: USGS 3D Elevation Program





14050 Summit Drive, Suite 104 Austin, Texas 78728 Phone: (512) 837-8005 www.ecslimited.com

ECS Project No. 51:3774

**Austin, Williamson County, Texas** 

Project Acreage: 3.573

USGS Quadrangle: Jollyville, TX Watershed: San Gabriel

Hybrid Reference Layer: Austin Community College, City of Austin, County of Williamson, Texas Parks & Wildlife, CONANP, Esri, HERE, Garmin, SafeGraph, GeoTechnologies, Inc, METI/NASA, USGS, EPA, NPS, USDA

World Imagery: Williamson County TX, Earthstar Geographics USGS Topographic Map Jollyville, TX Quadrangle 2019 Soils Data: USDA NRCS Web Soil Survey Wetlands Data: National Wetlands Inventory Floodplain Data: FEMA National Flood Hazard Layer LIDAR Data: USGS 3D Elevation Program

# **SECTION 4**

Organized Sewage Collection System
Application
(TCEQ-0600)

## Organized Sewage Collection System Application

#### **Texas Commission on Environmental Quality**

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: HTG Red Oaks

1. Attachment A – SCS Engineering Design Report. This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

### **Customer Information**

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Mauricio Teran Entity: HTG Anderson, LLC

Mailing Address: 3225 Aviation Ave.

 City, State:
 Coconut Grove, FL
 Zip: 33133

 Telephone:
 (786)
 347-4554
 Fax: \_\_\_\_\_\_

Email Address: mauriciot@htgf.com

The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: Justin Kramer, P.E.

Texas Licensed Professional Engineer's Number: 122309

Entity: Kimley-Horn and Associates, Inc.

Mailing Address: 10614 Jollyville Rd., Bldg. 4, Ste. 200

City, State: Austin, TX

Telephone: (512) 418-1771

Zip: 78759

Email Address: justin.kramer@kimley-horn.com

## **Project Information**

4.	Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):
	Residential: Number of single-family lots:  Multi-family: Number of residential units:  Commercial Industrial  Off-site system (not associated with any development)  Other:
5.	The character and volume of wastewater is shown below:
	100 % Domestic581,918 gallons/day% Industrialgallons/day% Commingledgallons/dayTotal gallons/day: 581,918
6.	Existing and anticipated infiltration/inflow is $\underline{750}$ gallons/day. This will be addressed by:
7.	A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.
	<ul> <li>The WPAP application for this development was approved by letter dated A copy of the approval letter is attached.</li> <li>The WPAP application for this development was submitted to the TCEQ on 8/30/2023, but has not been approved.</li> <li>A WPAP application is required for an associated project, but it has not been submitted.</li> <li>There is no associated project requiring a WPAP application.</li> </ul>

### 8. Pipe description:

**Table 1 - Pipe Description** 

Pipe Diameter(Inches)	Linear Feet (1)	Pipe Material (2)	Specifications (3)
12"	195"	SDR-26 PVC	ASTM D3034
12"	280"	SDR-26 PVC	ASTM D3034

Total Linear Feet: 475"

- (1) Linear feet Include stub-outs and double service connections. Do not include private service laterals.
- (2) Pipe Material If PVC, state SDR value.
- (3) Specifications ASTM / ANSI / AWWA specification and class numbers should be included.

Anderson Mill

Plant. The treatmen	,	e wastewater to the MU	JD WWTP Treatment				
∑ Existing     Proposed							
10. All components of t	his sewage collection sys	stem will comply with:					
	The City of <u>Austin</u> standard specifications.  Other. Specifications are attached.						
11. X No force main(s)	and/or lift station(s) are	e associated with this sev	wage collection system.				
	A force main(s) and/or lift station(s) is associated with this sewage collection system and the <b>Lift Station/Force Main System Application</b> form (TCEQ-0624) is included with this						
Alignment							
	12. X There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.						
	13. X There are no deviations from straight alignment in this sewage collection system without manholes.						
Attachment B - Justification and Calculations for Deviation in Straight Alignment without Manholes. A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.  For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.							
Manholes and	Cleanouts						
	ttach additional sheet if	of each sewer line(s). The necessary)	ese locations are listed				
Table 2 - Mailioles a	ind Cleanouts		Manhole or Clean-				
Line	Shown on Sheet	Station	out?				
Offsite WWL-A	21 Of 25	1+00.00, 2+96.79	Manholes (both ends)				
Offsite WWL-B	22 Of 25	1+00.00, 3+78.91	Manholes (both ends)				
	Of						
	Of						
	Of						
	Of						

Of

Line	Shown on Sheet	Station	Manhole or Clean- out?
	Of		
	Of		
	Of		

- 15. Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.
- 16. The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
>54	2000

Attachment C – Justification for Variance from Maximum Manhole Spacing. The
maximum spacing between manholes on this project (for each pipe diameter used) is
greater than listed in the table above. A justification for any variance from the
maximum spacing is attached, and must include a letter from the entity which will
operate and maintain the system stating that it has the capability to maintain lines with
manhole spacing greater than the allowed spacing.

- 17. X All manholes will be monolithic, cast-in-place concrete.
  - The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

## Site Plan Requirements

#### Items 18 - 25 must be included on the Site Plan.

- 18.  $\boxed{X}$  The Site Plan must have a minimum scale of 1" = 400'.
  - Site Plan Scale: 1" = 40 '.
- 19. The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.
- 20. Lateral stub-outs:

	The location of all lateral stub-outs are shown and labeled.
X	No lateral stub-outs will be installed during the construction of this sewer collection
	system.

21. Location of existing and proposed water lines:								
If not shown on the Site sewer systems.	ition system for this project is sho Plan, a Utility Plan is provided sh nes associated with this project.							
22. 100-year floodplain:								
floodplain, either natura lined channels construct After construction is con have water-tight manho and labeled on the Site F constructed above sewe	,	ot include streets or concrete- the 100-year floodplain will the table below and are shown						
Table 3 - 100-Year Floodpla	in Sheet	Station						
Line								
	of to							
of to								
	of	to						
	of	to						
22 E year floodalain:								

# 23. 5-year floodplain:

X After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concretelined channels constructed above sewer lines.) After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table

below and are shown and labeled on the Site Plan. (Do not include streets or concretelined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

Line	Sheet	Station
	of	to

- 24. |X| Legal boundaries of the site are shown.
- 25. X The *final plans and technical specifications* are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must	t be included on the	Plan and Profile sh	eets.	
sewer lines rated pipe variance fro	or proposed water I are listed in the tab to be installed show om the required pre om 30 TAC Chapter	ole below. These ling on the plan and p ssure rated piping a	es must have the ty rofile sheets. Any i	pe of pressure request for a
	pe no water line cros pe no water lines wit	=	sed sewer lines.	
Table 5 - Water	Line Crossings			_
Line	Station or Closest Point	Crossing or Parallel	Horizontal Separation Distance	Vertical Separation Distance
27. Vented Manho	les.			
No part of required by A portion of the table by A portion of venting shall alternative A portion of A portion of the table by A portion of table by A por	this sewer line is with a 30 TAC Chapter 21 of this sewer line is well at less than 1500 felow and labeled on of this sewer line is well be provided at less means is described of this sewer line is well at less than 1500 feet less than 1500 feet less than 1500 feet less were line is well at less than 1500 feet less than 1500 feet less were line is well as	7. vithin the 100-year foot intervals. These the appropriate provithin the 100-year for the following partithin the 100-year for the following partition the following parti	floodplain and vent water-tight manh ofile sheets. floodplain and an a ervals. A description ge. floodplain; howeve	red manholes will oles are listed in lternative means of on of the r, there is no
Line	Manho	ole S	tation	Sheet
			-	

Line	Manhole	Station	Sheet						
28. Drop manholes:									
Sewer lines which Sewer lines which Sewer lines which seems above		manholes or "manhole st listed in the table below	and labeled on the						
Line	Manhole	Station	Sheet						
29. Sewer line stub-out	s (For proposed extensio	ns):							
	and markings of all sewer ub-outs are to be installe m.								
30. Lateral stub-outs (Fo	30. Lateral stub-outs (For proposed private service connections):								
<ul> <li>☐ The placement and markings of all lateral stub-outs are shown and labeled.</li> <li>☐ No lateral stub-outs are to be installed during the construction of this sewage collection system.</li> </ul>									
31. Minimum flow velo	city (From Appendix A)								
Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.									
32. Maximum flow velo	city/slopes (From Appen	dix A)							
<ul> <li>32. Maximum flow velocity/slopes (From Appendix A)</li> <li>Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.</li> <li>Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.         Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.     </li> </ul>									

Table 8 - Flows Greater Than 10 Feet per Second

Line	Profile Sheet	Station to Station	FPS	% Slope	Erosion/Shock Protection

33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provision below have been made to protect against pipe displacement by erosion and/or shall shall be	
<ul> <li>Concrete encasement shown on appropriate Plan and Profile sheets for the lo listed in the table above.</li> <li>Steel-reinforced, anchored concrete baffles/retards placed every 50 feet show appropriate Plan and Profile sheets for the locations listed in the table above.</li> <li>N/A</li> </ul>	

# Administrative Information

- 34. The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
- 35. Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

**Table 9 - Standard Details** 

Standard Details	Shown on Sheet
Lateral stub-out marking [Required]	N/A
Manhole, showing inverts comply with 30 TAC §217.55(I)(2) [Required]	N/A
Alternate method of joining lateral to existing SCS line for potential future connections [Required]	N/A
Typical trench cross-sections [Required]	25 of 25
Bolted manholes [Required]	N/A
Sewer Service lateral standard details [Required]	N/A
Clean-out at end of line [Required, if used]	N/A
Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps]	N/A
Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed]	N/A
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used]	19, 21, of 25

Standard Details	Shown on Sheet
Drop manholes [Required, if a pipe entering a manhole is more than 24	of
inches above manhole invert]	

- 36. All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
- 37. All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
  - Survey staking was completed on this date:
- 38. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 39. Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

# Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: <u>Justin Kramer</u>, P.E.

Date: 02/02/2024

Place engineer's seal here:



Signature of Licensed Professional Engineer:

# Appendix A-Flow Velocity Table

**Flow Velocity (Flowing Full)** All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Table 10 - Slope Velocity

Pipe Diameter(Inches)	% Slope required for minimum flow velocity of 2.0 fps	% Slope which produces flow velocity of 10.0 fps		
6	0.50	12.35		
8	0.33	8.40		
10	0.25	6.23		
12	0.20	4.88		
15	0.15	3.62		
18	0.11	2.83		
21	0.09	2.30		
24	0.08	1.93		
27	0.06	1.65		
30	0.055	1.43		
33	0.05	1.26		
36	0.045	1.12		
39	0.04	1.01		
>39	*	*		

<sup>\*</sup>For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

v = velocity (ft/sec)
n = Manning's roughness coefficient
(0.013)
Rh = hydraulic radius (ft)
S = slope (ft/ft)

# Attachment A SCS Engineering Design Report

This Engineering Design Report has been prepared to comply with the Texas Commission on Environmental Quality Design Criteria for Domestic Wastewater Systems, 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable. Please note that throughout this application, the more stringent of AWU or TCEQ regulations shall apply.

### **Project description**

### Introduction

Red Oaks is an undeveloped ±3.57-acre lot located at 11723 N FM 620 and within the Full Purpose city limits of the City of Austin, Texas. The project includes the development of a 70-unit multifamily complex. The project will also include a parking lot, proposed utility connections, drainage, water quality and detention pond, other site improvements, and offsite wastewater improvements.

The site is not located in the Federal Emergency Management Agency's 100-year floodplain according to FIRM 48491C0605F. The site is located within the North Edwards Aquifer Recharge Zone according to TCEQ Edwards Aquifer Map.

On-site infrastructure is comprised of private domestic/fire water, gas, electric, wastewater, and storm sewer lines. The offsite wastewater service outlined in this report will consist of two lines that will convey wastewater from existing manhole that is not part of a previous approved SCS as the lines were installed prior to the SCS rule (installed in 1980-81). The project consists of the replacement of two segments of 8" PVC pipe with 12" PVC with no proposed laterals or stubs. The manholes located at both ends of both pipes are existing. All proposed wastewater lines will be installed within the Edwards Aquifer Recharge Zone (EARZ).

### **Pipe Design**

### Flow Design Basis

Service for the build-out of the project site will be served by these wastewater extensions These segments of wastewater pipes serve neighboring properties to the project site. The City of Austin Criteria Manuals were used to determine the parameters for the design of the wastewater line extensions.

# **Gravity Pipe and Joint Materials**

The proposed pipe to be used for the 12-inch wastewater lines will be ASTM D3034 SDR-26 PVC pipe. The joints for this pipe shall meet the requirements of ASTM D3212. The pipe joints shall have an integral bell and rubber gasket seal with the locked-in type gasket.

### Separation Distances for Water and Wastewater

A nine-foot minimum horizontal separation is maintained between all proposed wastewater infrastructure and existing and proposed public water supply lines. There is one (1) perpendicular water line crossing on 'Offsite WWL-A' at the intersection of El Salido Pkwy. and Tanglebriar Trl. This portion of water line is asbestos concrete and will be replaced with a different pipe material and encased in steel.

## **Building Laterals and Taps**

There are no laterals and taps proposed with the offsite wastewater lines.

## **Boring and Tunneling of Crossings**

No boring or tunneling of crossings are proposed for this project.

### **Corrosion Potential**

PVC pipe will be utilized for or all proposed wastewater lines. No deterioration of the proposed pipe or its associated components is anticipated in this application.

### **Odor Control**

All flows contributing to the proposed wastewater lines are domestic sewage. There are no significant generators of sulfide or other odorous compounds (such as lift stations) immediately upstream of the proposed wastewater lines. Therefore, no odor control measures are proposed for this project.

### **Active Geologic Faults**

Per the Geologic Assessment, no active geologic faults were located within the area of the project.

### **Capacity Analysis**

The capacity of each proposed wastewater segment is calculated below based on Manning's Equation. The calculation for each segment is based on the minimum proposed slope.

$$Q = \frac{1.49}{n} * A * R^{0.67} * S^{0.5}$$

Where:

Qfull = flow rate of fluid in pipe at full flow ( $ft^3/s$ ) (cfs)

Q90%= flow rate of fluid in pipe at 90% full flow (ft<sup>3</sup>/s) (cfs)

A = area of pipe (ft^2) = 
$$\frac{\pi * d^2}{4}$$

d = internal pipe diameter (ft) = Do - 2t

Do = outside diameter (in)

t = pipe wall thickness (in)

n = Manning's Roughness coefficient = 0.013

Rfull = hydraulic radius of pipe (full flow) = A/P = D/4 (ft)

R90%= hydraulic radius of pipe (90% full flow) = 0.9\*A/P = 0.9\*D/4 (ft)

P = wetted perimeter of pipe =  $\pi$  \*D (ft)

S = slope of energy line

Pipe	Length	Slope	Dian	neter	Pipe	Manning's	Р	Α	R <sub>full</sub>	R <sub>90%</sub>	Q <sub>full</sub>	Q <sub>90%</sub>	$V_{\text{full}}$	V <sub>90%</sub>
ripe	(ft)	(ft/ft)	(in)	(ft)	Material	waiiiiig s	(ft)	(sf)	(ft)	(ft)	(cfs)	(cfs)	(fps)	(fps)
Offsite WWL-A	195.00	0.016	12	1.00	PVC	0.012	3.14	0.79	0.25	0.23	4.83	4.34	6.15	5.53
Offsite WWL-B	280.00	0.012	12	1.00	PVC	0.012	3.14	0.79	0.25	0.23	4.13	3.72	5.26	4.73

The proposed wastewater line installed at the slope specified provides capacity in excess of the calculated peak wet weather design flows at full and 90% flow conditions.

# Attachment B Justification and Calculations for Deviation in Straight Alignment without Manholes

(Not applicable)

# Attachment C Justification for Variance from Maximum Manhole Spacing


(Not applicable)

# Attachment D Construction Plans

# CIVIL SITE DEVELOPMENT PLANS FOR

# RED OAKS

# 11723 N FM 620 RD AUSTIN, TEXAS 78750 WILLIAMSON COUNTY



06/30/2023

DATE

DATE

DATE

# **SHEET INDEX**

SHEET NO.	DESCRIPTION
01	COVER SHEET
02	PLAT
03	GENERAL NOTES
04	KIMLEY-HORN GENERAL NOTES
05	AW GENERAL NOTES
06	EXISTING CONDITIONS & DEMOLITION PLAN
07	EROSION CONTROL PLAN
08	SITE PLAN
09	GRADING PLAN (SHEET 1 OF 2)
10	GRADING PLAN (SHEET 2 OF 2)
11	EXISTING DRAINAGE AREA MAP
12	PROPOSED DRAINAGE AREA MAP
13	INLET DRAINAGE AREA MAP
14	WATER QUALITY & DETENTION POND PLAN
15	TCEQ NOTES & CALCULATIONS
16	STORM PLAN
17	OVERALL WATER PLAN
18	PUBLIC WATER PLAN & PROFILE
19	WASTEWATER PLAN & PROFILE
20	OVERALL OFFSITE WASTEWATER PLAN
21	OFFSITE WASTEWATER LINE 'A' PLAN & PROFILE
22	OFFSITE WASTEWATER LINE 'B' PLAN & PROFILE
23	EROSION CONTROL DETAILS
24	STORM & WATER QUALITY DETAILS
25	UTILITY DETAILS

TRATEGY WITH THE FULL UNDERSTANDING THAT, AT A MINIMUM OF 6 WEEKS PRIOR TO THE VERSION OF THE CITY'S FEE ORDINANCE, SHALL BE PAID EACH TIME A PLAN OR PLAN REVISION IS SUBMITTED TO RIGHT OF WAY MANAGEMENT DIVISION FOR REVIEW. THE FOLLOWING MUST BE TAKEN INTO CONSIDERATION WHEN DEVELOPING FUTURE TRAFFIC **CONTROL STRATEGIES:** 

PEDESTRIAN AND BICYCLE TRAFFIC ACCESS MUST BE MAINTAINED AT ALL TIMES, UNLESS OTHER WISE AUTHORIZED BY RIGHT OF WAY MANAGEMENT.

NO LONG-TERM LANE CLOSURES WILL BE AUTHORIZED, UNLESS RIGHT OF WAY MANAGEMENT DETERMINES THAT ADEQUATE ACCOMMODATIONS HAVE BEEN MADE TO MINIMIZE TRAFFIC

PROJECT SHOULD BE PHASED SO THAT UTILITY INSTALLATION MINIMALLY IMPACTS EXISTING OR TEMPORARY PEDESTRIAN FACILITIES.

AUSTIN FIRE DEPARTMENT						
DESIGN STANDARDS		ONAL FIRE CODE WITH LOCAL AMENDMENTS				
FIRE FLOW DEMAND @ 20 PSI	5,000	GPM				
INTENDED USE	AFFORDAB	LE MULTIFAMILY				
CONSTRUCTION CLASSIFICATION	TYPE V-A					
BUILDING FIRE AREA	84,477	SF				
AUTOMATIC FIRE SPRINKLER SYSTEM	NFPA-13R (APARTMENTS) & NFPA 13 (CLUBHOUSE/AMENITIE					
REDUCED FIRE FLOW DEMAND @ 20 PSI	1,500 GPM MINIMU					
FIRE HYDRANT FLOW TEST DATE	5/26/2023					
FIRE HYDRANT FLOW TEST LOCATIONS	11700 BLK N I	-M 620 RD (#56990)				
HIGH-RISE		NO				
ALTERNATIVE METHOD OF COMPLIANCE	N/A					
WILDLAND URBAN INTERFACE CODE	INTERFACE CODE (IV LOCAL AMENDMEN' CONSTRUCTED TO T IGNITION-RESISTAN	ONAL WILDLAND-URBAN VUIC) WITH CITY OF AUSTIN TS. ALL BUILDINGS SHALL BE HE WUI PROXIMITY CLASS C TT REQUIREMENTS OF THE				

# Know what's below. Call before you dig. WARNING: CONTRACTOR IS TO 4 VERIFY PRESENCE AND EXACT / LOCATION OF ALL UTILITIES IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'

SITE PLAN APPROVAL SHEET 01 OF 39 FILE NUMBER SP-2023-0252C.SH APPLICATION DATE 06/30/2023 APPROVED BY COMMISSION ON CHAPTER **25-5** OF THE CITY OF AUSTIN CODE. EXPIRATION DATE (25-5-81,LDC) \_\_\_\_\_CASE MANAGER CHRIS SAPUPPO PROJECT EXPIRATION DATE (ORD.#970905-A)

Director, Development Services Department RELEASED FOR GENERAL COMPLIANCE: ZONING GR-CO Correction 1 Correction 2

Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plat which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

BENCHMARKS

# CHANGE AUSTIN | SHEETS | IMP. COVER | IMP. COVER DESCRIPTION **IMAGED** APPROVAL IN PLAN (SQ. FT.)/% (SQ. FT.)

REVISIONS/CORRECTIONS

# **GENERAL PLAN NOTES**

- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE REGISTERED PROFESSIONAL ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS THE CITY OF AUSTIN MUST RELY UPON THE ADEQUACY OF THE WORK OF THE
- WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY AUSTIN WATER UTILITY,
- THERE ARE NATURAL SLOPES ON THIS SITE IN EXCESS OF 15%.

- INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED
- (SWPPP) IS REQUIRED TO BE ON SITE AT ALL TIMES.
- SITE IS SUBJECT TO THE WATERSHED PROTECTION REGULATIONS.
- THIS SITE IS LOCATED IN THE EDWARDS AQUIFER RECHARGE ZONE
- MAY BE REQUIRED PRIOR TO THE START OF CONSTRUCTION. THE APPLICANT IS
- 1.12.0 AND COA ITEM NO. 658S OF THE SSM) PROVISION THAT ALL TRENCHING GREATER THAN 5 FEET DEEP MUST BE INSPECTED BY A GEOLOGIST (TEXAS P.G.) OR GEOLOGIST
- 13. IF AT ANY TIME DURING CONSTRUCTION OF THIS PROJECT AN UNDERGROUND STORAGE TANK (UST) IS FOUND. CONSTRUCTION IN THAT AREA MUST STOP UNTIL A CITY OF AUSTIN UST CONSTRUCTION PERMIT IS APPLIED FOR AND APPROVED. ANY UST REMOVAL WORK MUST BE CONDUCTED BY A UST CONTRACTOR THAT IS REGISTERED WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ). CONTACT ELIZABETH SIMMONS AT ELIZABETH.SIMMONS@AUSTINTEXAS.GOV IF YOU HAVE ANY
- 14. A FEE-IN-LIEU OF PARKLAND DEDICATION AND PARK DEVELOPMENT HAS BEEN PAID FOR 0 MARKET-RATE DWELLING UNITS. AN EXEMPTION TO THE PARKLAND DEDICATION ORDINANCE HAS BEEN GRANTED FOR 70 SMART CERTIFIED AFFORDABLE DWELLING UNITS. THE PARKLAND DEDICATION ORDINANCE IS SUBJECT TO ENFORCEMENT IF THIS DEVELOPMENT NO LONGER COMPLIES WITH AFFORDABLE HOUSING REQUIREMENTS SET FORTH IN THE APPROVAL FROM THE HOUSING AND PLANNING DEPARTMENT.
- 15. A CONDITIONAL LETTER OF APPROVAL IS REQUIRED BY AUSTIN ENERGY GREEN BUILDING PROGRAM PRIOR TO BUILDING PERMIT.
- 16. ALL PONDS WILL BE PRIVATELY MAINTAINED.

FUGLEBERG-KOCH ARCHITECTURE TED HUNTON, AIA 2555 TEMPLE TRAIL WINTER PARK, FL 32789

PH: (407) 629-0595

PH: (210) 331-7886

LANDSCAPE ARCHITECT KIMLEY-HORN LEO O'BRIAN, PLA ASLA 10101 REUNION PLACE, SUITE 400 SAN ANTONIO, TX 78216

DA MAWYER LAND SURVEYING FIRM #10191500 5151 W. SH 46 NEW BRAUNFELS, TX 78132 PH: (830) 730-4449

TBPELS # F-6324; #10194230 221 WEST SIXTH STREET, SUITE 600 **AUSTIN, TX 78701** 

# LISTS OF CONTACTS:

**WATER & SANITARY SEWER AUSTIN WATER** 625 E 10TH STREET **AUSTIN, TX 78701** 

TEXAS GAS SERVICE LINDA BARGAR 5613 AVENUE F **AUSTIN, TX 78751** PH: (512) 465-1134

OWNER/DEVELOPER NAME AND ADDRESS HTG ANDERSON, LLC

S8431 - 620 HILL COUNTRY CENTER

LOT 6, ACRES 3.573 [TU PCTS]

WILLIAMSON COUNTY, TEXAS.

FILL BETWEEN 4 AND 8 FEET.

(LTS 5 & 6 BLK A AMENDED), BLOCK A,

SEE AGREEMENT FILED IN DOCUMENT

AN ADMINISTRATIVE ENVIRONMENTAL

FOR INTEGRATED PEST MANAGEMENT PLAN,

ADMINISTRATIVE ENVIRONMENTAL VARIANCE

VARIANCE HAS BEEN GRANTED TO ALLOW

, OFFICIAL PUBLIC RECORDS,

MAURICIO TERAN 3225 AVIATION AVENUE COCONUT GROVE, FL 33133

C14-2021-0090

960229-B

PEDERNALES ELECTRIC COOP JIM ROWIN 2412 KRAMER LANE, BUILDING C AUSTIN, TEXAS 78758

CHARTER/SPECTRUM

LBARGAR@TXGAS.COM

CITY OF AUSTIN PLANNING & DEVELOPMENT REVIEW DEPARTMENT 505 BARTON SPRINGS ROAD AUSTIN, TX 78704 PH: (512) 974-2680

**AUSTIN FIRE DEPARTMENT** ONE TEXAS CENTER SUITE 200 505 BARTON SPRINGS ROAD AUSTIN, TX 78704 PH: (512) 974-0192

PH: (512) 972-1000 (OPTION 3)

PH: 512) 505-7665

STEVEN SCHUH 12012 N MOPAC EXPRESSWAY AUSTIN, TX 78759 PH: (512) 485-6360 STEVEN.SCHUH@CHARTER.COM



I CERTIFY THAT THESE ENGINEERING DOCUMENTS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THE INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO FORMAL CITY APPROVAL.

AUSTIN WATER UTILITY


CITY OF AUSTIN FIRE DEPARTMENT

DEVELOPMENT SERVICES DEPARTMENT

SP-2023-0252C.SH

SHEET NUMBER

OVER



SHEET NUMBER
02
OF 25

- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE ADEQUACY OF THE WORK OF THE CONTRACTOR SHALL CALL TEXAS 811 (811 OR 1-800-344-8377) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W. PAY CONSTRUCTION INSPECTION FEES. AND TO SCHEDULE THE REQUIRED SITE & SUBDIVISION THE R.O.W. OR PUBLIC EASEMENTS. PLEASE VISIT REQUIREMENTS, INFORMATION CONCERNING FEES, AND CONTACT INFORMATION. THE GOVERNMENT PRINTING OFFICE: INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN, TEXAS.) ALL SITE WORK SHALL COMPLY WITH ENVIRONMENTAL REQUIREMENTS. CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS: [] RELEASE OF THE CERTIFICATE OF OCCUPANCY BY THE DEVELOPMENT SERVICES DEPARTMENTS (INSIDE THE CITY LIMITS) [] INSTALLATION OF AN ELECTRIC OR WATER METER (IN THE FIRE-MILE ETJ) OWNER/DEVELOPER INFORMATION OWNER/DEVELOPER DEVELOPER: HTG ANDERSON LLC
- CONTRACTOR SHALL NOTIFY THE CITY OF AUSTIN SITE & SUBDIVISION TO SUBMIT REQUIRED DOCUMENTATION, PRE-CONSTRUCTION MEETING. THIS MEETING MUST BE HELD PRIOR TO ANY CONSTRUCTION ACTIVITIES WITHIN HTTP://AUSTINTEXAS.GOV/PAGE/COMMERCIAL-SITE-AND-SUBDIVISION-INSPECTIONS FOR A LIST OF SUBMITTAL
- FOR SLOPES OR TRENCHES GREATER THAN FIVE (5) FEET IN DEPTH. A NOTE MUST BE ADDED STATING: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION." (OSHA STANDARDS MAY BE PURCHASED FROM
- UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS AND PRIOR TO THE FOLLOWING: THE ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DRAINAGE, FILTRATION, AND DETENTION FACILITIES WERE
- - COMPANY: HOUSING TRUST GROUP LLC CONTACT: MAURICIO TERAN
- EMAIL: MAURICIOT@HTGF.COM PHONE: (786) 347-4554
  - COMPANY: KIMLEY-HORN & ASSOCIATES, INC. CONTACT: JUSTIN J. KRAMER. P.E. EMAIL: JUSTIN.KRAMER@KIMLEY-HORN.COM
- PHONE: (512) 418-1771 PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE:
  - DEVELOPER: HTG ANDERSON LLC COMPANY: HOUSING TRUST GROUP LLC CONTACT: MAURICIO TERAN

PHONE: (786) 347-4554

- EMAIL: MAURICIOT@HTGF.COM PHONE: (786) 347-4554 PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA CONTROL MAINTENANCE:
  - DEVELOPER: HTG ANDERSON LLC COMPANY: HOUSING TRUST GROUP LLC
  - CONTACT: MAURICIO TERAN EMAIL: MAURICIOT@HTGF.COM
- ALL CONSTRUCTION SHALL COMPLY WITH THE "CITY OF AUSTIN STANDARD SPECIFICATIONS," AS AMENDED BY SPECIAL PROVISION, CURRENT AT THE TIME OF BIDDING.
- CONTRACTOR TO TAKE ALL DUE PRECAUTIONS TO PROTECT EXISTING FACILITIES FROM DAMAGE. ANY DAMAGE TO EXISTING FACILITIES INCURRED AS A RESULT OF THESE CONSTRUCTION OPERATIONS TO BE REPAIRED IMMEDIATELY BY THE CONTRACTOR, AT NO ADDITIONAL COST TO OWNER.
- CONTRACTOR TO GIVE NOTICE TO ALL AUTHORIZED INSPECTORS, SUPERINTENDENTS, OR PERSONS IN CHARGE OF PRIVATE AND PUBLIC UTILITIES AFFECTED BY HIS OPERATIONS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR TO MAKE CERTAIN THAT ALL CONSTRUCTION PERMITS THAT CAN ONLY BE ISSUED TO THE CONTRACTOR HAVE BEEN OBTAINED BY THE CONTRACTOR AT ITS EXPENSE PRIOR TO COMMENCEMENT OF
- CONTRACTOR TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REQUIREMENTS REGARDING EXCESS AND WASTE MATERIAL, INCLUDING METHODS OF HANDLING AND DISPOSAL
- CONTRACTOR TO COORDINATE INTERRUPTIONS OF ALL UTILITIES AND SERVICES. ALL WORK TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPLICABLE UTILITY COMPANY OR AGENCY INVOLVED.
- LOCATION OF EXISTING UTILITIES SHOWN ON PLANS WAS COMPILED FROM RECORD INFORMATION. NO WARRANTY IS IMPLIED AS TO THE ACTUAL LOCATION OF EXISTING UTILITIES.
- WHEN UNLOCATED OR INCORRECTLY LOCATED UNDERGROUND PIPING. OR A BREAK LOCATED IN THE LINE. OR OTHER UTILITIES AND SERVICES ARE ENCOUNTERED DURING SITE WORK OPERATIONS, NOTIFY THE APPLICABLE UTILITY COMPANY IMMEDIATELY TO OBTAIN PROCEDURE DIRECTIONS. COOPERATE WITH THE APPLICABLE UTILITY COMPANY IN MAINTAINING ACTIVE SERVICES IN OPERATION.
- CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS, AND PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO OWNER.
- CONTRACTOR TO CONTROL DUST CAUSED BY THE WORK AND COMPLY WITH POLLUTION CONTROL REGULATIONS OF GOVERNING AUTHORITIES. (NO SEPARATE PAY.)
- THROUGHOUT THE CONSTRUCTION, AND AT THE COMPLETION OF CONSTRUCTION, THE CONTRACTOR TO
- THESE PLANS. PREPARED BY KIMLEY-HORN & ASSOCIATES. DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONSTRUCTION CONTRACTOR OR ITS EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE SEAL OF KIMLEY-HORN & ASSOCIATES MAY NOW OR HEREAFTER BE INCORPORATED INTO THESE PLANS. THE CONSTRUCTION CONTRACTOR TO PREPARE OR OBTAIN THE APPROPRIATE SAFETY SYSTEMS, INCLUDING THE PLANS AND SPECIFICATIONS REQUIRED BY HOUSE BILLS 662 AND 665 ENACTED BY THE TEXAS LEGISLATURE IN THE 70TH LEGISLATURE -
- TRAFFIC CONTROLS TO BE CONTRACTOR'S RESPONSIBILITY AND INSTALLED IN ACCORDANCE WITH THE "CITY OF AUSTIN MANUAL OF UNIFORM CONSTRUCTION BARRICADING STANDARDS." OCTOBER 1986, ADDITIONALLY, THE CONTRACTOR IS TO SCHEDULE THE WORK AND TRAFFIC CONTROLS TO ACHIEVE THE FOLLOWING TRAFFIC
- MINIMUM OF ONE ACCESS POINT TO PARKING LOTS TO REMAIN OPEN AT ALL TIMES.
- 0. CONTRACTOR TO EXERCISE CAUTION DURING CONSTRUCTION NEAR AND AROUND GAS LINES. NOTIFY GAS COMPANY 24 HOURS PRIOR TO CONSTRUCTION.
- NO BLASTING WITHIN 15 FEET OF EXISTING UTILITIES OR STRUCTURES. IF BLASTING IS TO BE USED BY THE CONTRACTOR, A BLASTING PERMIT MUST BE SECURED PRIOR TO COMMENCEMENT OF WORK, BLASTING TO BE IN ACCORDANCE WITH "CITY OF AUSTIN STANDARD SPECIFICATIONS" AND CRITERIA OF THE NATIONAL FIRE PROTECTION ASSOCIATION.
- 22. BURNING IS NOT ALLOWED ON THIS PROJECT.
- CONTRACTOR TO INSTALL 1/2-INCH-DIAMETER BY 12-INCH-LONG REBAR VERTICALLY, WITH TWO (2) FEET OF SURVEYOR'S RIBBON ATTACHED, AT END OF ALL PIPE STUBS. TOP OF BAR TO BE NOT LESS THAN 12 INCHES BELOW THE FINISHED GRADE A. BLUE RIBBON- WATER LINE D. ORANGE RIBBON- TELECOM DUCT BANK B. GREEN RIBBON- WASTEWATER LINE E. RED RIBBON- ELECTRICAL DUCT BANK
- MAKE CONNECTION BETWEEN NEW AND EXISTING ASPHALT STREETS BY REMOVING EXISTING STREET FROM END BACK, UNTIL FULL DEPTH BASE AND HMAC ARE ENCOUNTERED AND HMAC APPEARS TO BE IN SOUND CONDITION. PROVIDE EXPANSION JOINT AND DOWELS WHERE CONNECTING EXISTING CURB TO NEW.
- A CURB LAYDOWN IS REQUIRED AT ALL POINTS WHERE THE PROPOSED SIDEWALK INTERSECTS THE CURB. UNLESS OCCURRING AT AN EXPANSION JOINT, MAKE CONNECTION BETWEEN NEW AND EXISTING SIDEWALK BY EXPOSING AND CLEANING A ONE-FOOT LENGTH OF WELDED WIRE REINFORCEMENT AND LAPPING NEW
- REINFORCEMENT ONTO THIS LENGTH. CONCRETE FOR SITE WORK, OTHER THAN CONCRETE PAVEMENT AND STRUCTURES. TO BE CLASS "A" (5 SACK, 3000 PSI @ 28-DAYS) AND ALL REINFORCING STEEL TO BE ASTM A615 60. UNLESS OTHERWISE NOTED. REFER TO GEOTECHNICAL REPORT AND ARCHITECTURAL DRAWINGS FOR PAVEMENT STRUCTURAL SPECIFICATIONS.
- TREE SURVEY, CONTOURS, AND BENCHMARK INFORMATION SUPPLIED BY OTHERS. ACTUAL LOCATION OF TREES AND ELEVATION OF NATURAL GROUND ON THE PROJECT SITE MAY VARY FROM WHAT IS DEPICTED ON THE PLAN SHEETS. KIMLEY-HORN & ASSOCIATES IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION REGARDING SURVEYS OR BENCHMARK LOCATIONS. BENCHMARKS ARE AS FOLLOWS:
- 29. DEMOLITION PERMITS (IF NEEDED) ARE TO BE OBTAINED BY THE CONTRACTOR AT THEIR EXPENSE. CONTRACTOR SHALL REFER TO THE GEOTECHNICAL INVESTIGATION REPORT FOR THIS SITE FOR SUBSURFACE INFORMATION REGARDING THIS PROJECT. AT ITS EXPENSE THE CONTRACTOR IS
- CONTRACTOR TO FIELD VERIFY LOCATION AND FLOWLINES OF EXISTING UTILITIES PRIOR TO INSTALLATION OF PROPOSED UTILITY, CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.
- PUMPING OF STORMWATER FROM EXCAVATIONS IS PROHIBITED UNLESS THE STORMWATER IS DISCHARGED TO ENCOURAGE SHEET/OVERLAND FLOW. ADDITIONAL EROSION AND SEDIMENTATION CONTROLS MAY BE REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.
- 33. UNLESS OTHERWISE NOTED, STORM SEWERS TO BE: 6"-15" SDR 35 PVC, 18" AND GREATER RCP ASTM-C76 CLASS III.
- ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS ONE SQUARE FOOT IN TOTAL AREA. BLOWS AIR FROM WITHIN THE SUBSTRATE, AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION.

- ALL TREES AND NATURAL AREAS SHOWN ON PLANS TO BE PRESERVED SHALL BE PROTECTED DURING
- CONSTRUCTION WITH TEMPORARY FENCING.
- PROTECTIVE FENCES TO BE ERECTED ACCORDING TO CITY OF AUSTIN "STANDARDS FOR TREE PROTECTION."
- PROTECTIVE FENCES TO BE INSTALLED PRIOR TO THE START OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING, OR GRADING), AND TO BE MAINTAINED THROUGHOUT ALL PHASES OF THE CONSTRUCTION PROJECT.
- EROSION AND SEDIMENTATION CONTROL BARRIERS TO BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILDUP WITHIN TREE DRIPLINES.
- PROTECTIVE FENCES TO SURROUND THE TREE OR GROUP OF TREES. AND TO BE LOCATED AT THE OUTERMOST LIMIT OF BRANCHES (DRIPLINE) OR, FOR DESIGNATED PROTECTED NATURAL AREAS, PROTECTIVE FENCES TO FOLLOW THE LIMIT OF CONSTRUCTION LINE. CONTRACTOR IS TO AVOID THE FOLLOWING
- A. SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF **EQUIPMENT OR MATERIALS:** B. ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN SIX (6) INCHES CUT OR FILL), OR
- TRENCHING NOT REVIEWED AND AUTHORIZED BY THE CITY ARBORIST WOUNDS TO EXPOSED ROOTS. TRUNK, OR LIMBS BY MECHANICAL EQUIPMENT:
- D. OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CONCRETE TRUCK CLEANING, EXCEPTIONS TO INSTALLING FENCES AT TREE DRIPLINES MAY BE PERMITTED IN THE FOLLOWING CASES:
- A. WHERE THERE IS TO BE AN APPROVED GRADE CHANGE, IMPERMEABLE PAVING SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE APPROXIMATELY TWO TO FOUR (2-4) FEET BEHIND B. WHERE PERMEABLE PAVING IS TO BE INSTALLED WITHIN A TREE'S DRIPLINE, ERECT THE FENCE AT THE
- OUTER LIMITS OF THE PERMEABLE PAVING AREA (PRIOR TO SITE GRADING SO THAT THIS AREA IS GRADED SEPARATELY PRIOR TO PAVING INSTALLATION TO MINIMIZE ROOT DAMAGE); WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE TO ALLOW SIX TO TEN (6-10) FEET OF WORK SPACE BETWEEN THE FENCE AND THE BUILDING;
- D. WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE OR OTHER SPECIAL REQUIREMENTS, CONTACT THE CITY ARBORIST AT 974-1876 TO DISCUSS ALTERNATIVES.
- NOTE: FOR THE PROTECTION OF NATURAL AREAS, NO EXCEPTIONS TO INSTALLING FENCES AT THE LIMIT OF CONSTRUCTION LINE WILL BE PERMITTED WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE BEING CLOSER FIVE (5) FEET TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF EIGHT (8) FEET (OR TO THE LIMITS OF
- LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING PROVIDED. TREES APPROVED FOR REMOVAL TO BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE
- PRESERVED. ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY TO BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT AREAS WITH GOOD QUALITY TOPSOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN TWO DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE
- AND MINIMIZES WATER LOSS DUE TO EVAPORATION. 10. ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION TO BE PLACED AS FAR FROM

EXISTING TREE TRUNKS AS POSSIBLE

BEFORE DAMAGE OCCURS (RIPPING OF BRANCHES, ETC.).

- NO LANDSCAPE TOPSOIL DRESSING GREATER THAN FOUR (4) INCHES SHALL BE PERMITTED WITHIN THE
- DRIPLINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC, AND EQUIPMENT TO TAKE PLACE
- ALL FINISHED PRUNING TO BE DONE ACCORDING TO RECOGNIZED, APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE "NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES", AVAILABLE ON REQUEST FROM THE CITY ARBORIST).
- 14. DEVIATIONS FROM THE ABOVE NOTES ARE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NONCOMPLIANCE, OR IF A TREE SUSTAINS DAMAGE AS A RESULT.
- FIRE DEPARTMENT NOTES THE WILLIAMSON COUNTY EMERGENCY SERVICES DISTRICT 2 REQUIRES ASPHALT OR CONCRETE PAVEMENT PRIOR TO CONSTRUCTION AS AN "ALL-WEATHER DRIVING SURFACE."
- HYDRANTS MUST BE INSTALLED WITH THE CENTER OF THE FOUR-INCH OPENING AT LEAST 18 INCHES ABOVE FINISHED GRADE. THE FOUR-INCH OPENING MUST FACE THE DRIVEWAY OR STREET WITH THREE- TO SIX-FOOT SETBACKS FROM THE CURBLINE(S). NO OBSTRUCTION IS ALLOWED WITHIN THREE FEET OF ANY HYDRANT AND THE FOUR-INCH OPENING MUST BE TOTALLY UNOBSTRUCTED FROM THE STREET.
- TIMING OF INSTALLATION: WHEN FIRE PROTECTION FACILITIES ARE INSTALLED BY THE DEVELOPER, SUCH FACILITIES SHALL INCLUDE ALL SURFACE ACCESS ROADS WHICH SHALL BE INSTALLED AND SERVICEABLE PRIOR TO AND DURING THE TIME OF CONSTRUCTION. WHERE ALTERNATIVE METHODS OF PROTECTION, AS APPROVED BY THE FIRE CHIEF, ARE PROVIDED, THE ABOVE MAY BE MODIFIED OR WAIVED
- ALL PERVIOUS/DECORATIVE PAVING SHALL BE ENGINEERED AND INSTALLED FOR 80,000 LB. LIVE-VEHICLE LOADS. ANY PERVIOUS/DECORATIVE PAVING WITHIN 100 FEET OF ANY BUILDING MUST BE APPROVED BY THE FIRE
- COMMERCIAL DUMPSTERS AND CONTAINERS WITH AN INDIVIDUAL CAPACITY OF 1.5 CUBIC YARDS OR GREATER SHALL NOT BE STORED OR PLACED WITHIN TEN FEET OF OPENINGS, COMBUSTIBLE WALLS, OR COMBUSTIBLE
- FIRE LANES DESIGNATED ON SITE PLAN SHALL BE REGISTERED WITH WILLIAMSON COUNTY EMERGENCY SERVICES DISTRICT 2 FIRE MARSHAL'S OFFICE AND INSPECTED FOR FINAL APPROVAL.
- VERTICAL CLEARANCE REQUIRED FOR FIRE APPARATUS IS 14 FEET FOR FULL WIDTH OF ACCESS DRIVE.
- ALL CURBS LOCATED WITHIN FIRE LANES SHALL BE MARKED WITH RED PAINT OR WHITE PAINT WITH RED STENCILING READING WITH WHITE STENCILING "FIRE LANE/ TOW-AWAY ZONE" IN LETTERING AT LEAST 3 INCHES IN HEIGHT IDENTIFIED AT BOTH ENDS AND AT INTERVALS OF 35 FEET OR LESS. IN ADDITION, SUCH STENCILING SHALL BE ZONE AND AT INTERVALS SIGNS SHALL BE POSTED AT BOTH ENDS OF A FIRE ALTERNATIVE MARKINGS OF THE FIRE LANES MAY BE OF 50 FEET OR LESS. APPROVED BY THE FIRE CHIEF PROVIDED THE FIRE LANES ARE CLEARLY AT INTERVALS NOT TO EXCEED 35 FEET.
- AMERICANS WITH DISABILITIES ACT THE CITY OF AUSTIN HAS REVIEWED THIS PLAN FOR COMPLIANCE WITH CITY DEVELOPMENT REGULATIONS ONLY. THE
- APPLICANT, PROPERTY OWNER, AND OCCUPANT OF THE PREMISES ARE RESPONSIBLE FOR DETERMINING WHETHER THE PLAN COMPLIES WITH ALL OTHER LAWS, REGULATIONS, AND RESTRICTIONS WHICH MAY BE APPLICABLE TO THE PROPERTY AND ITS USE.
- SPECIAL CONSTRUCTION TECHNIQUES PRIOR TO EXCAVATION WITHIN TREE DRIPLINES OR THE REMOVAL OF TREES ADJACENT TO OTHER TREES THAT ARE TO REMAIN, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT TO MINIMIZE ROOT DAMAGE.
- IN CRITICAL ROOT ZONE AREAS THAT CANNOT BE PROTECTED DURING CONSTRUCTION WITH FENCING AND WHERE HEAVY VEHICULAR TRAFFIC IS ANTICIPATED. COVER THOSE AREAS WITH A MINIMUM OF 12 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION. IN AREAS WITH HIGH SOIL PLASTICITY GEOTEXTILE FABRIC.PER STANDARD SPECIFICATION 620S. SHOULD BE PLACED UNDER THE MULCH TO PREVENT EXCESSIVE MIXING OF THE SOIL AND MULCH. ADDITIONALLY. MATERIAL SUCH AS PLYWOOD AND METAL SHEETS, COULD BE REQUIRED BY THE CITY ARBORIST TO MINIMIZE ROOT IMPACTS FROM HEAVY EQUIPMENT. ONCE THE PROJECT IS COMPLETED, ALL MATERIALS SHOULD BE REMOVED, AND THE MULCH SHOULD BE REDUCED TO A DEPTH OF 3
- PERFORM ALL GRADING WITHIN CRITICAL ROOT ZONE AREAS BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE
- WATER ALL TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. SPRAY TREE CROWNS WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
- WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, USE A PLASTIC VAPOR BARRIER BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO THE SOIL.

# APPENDIX P-1 - EROSION CONTROL NOTES

- THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS. TREE/NATURAL AREA PROTECTIVE FENCING, AND CONDUCT "PRE-CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE) PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR EXCAVATION).
- THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENVIRONMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. THE COA ESC PLAN SHALL BE CONSULTED AND USED AS THE BASIS FOR A TPDES REQUIRED SWPPP. IF A SWPPP IS REQUIRED. IT SHALL BE AVAILABLE FOR REVIEW BY THE CITY OF AUSTIN ENVIRONMENTAL INSPECTOR AT ALL TIMES DURING CONSTRUCTION, INCLUDING AT THE PRE-CONSTRUCTION MEETING. THE CHECKLIST BELOW CONTAINS THE BASIC ELEMENTS THAT SHALL BE REVIEWED FOR PERMIT APPROVAL BY COA EV PLAN REVIEWERS AS WELL AS COA EV INSPECTORS.
- THE PLACEMENT OF TREE/NATURAL AREA PROTECTIVE FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL AREA PLAN.
- 4. A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD ON-SITE WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT AND ENVIRONMENTAL INSPECTOR AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS. TREE/NATURAL AREA PROTECTION MEASURES AND "PRE-CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE) PRIOR TO BEGINNING ANY SITE PREPARATION WORK, THE OWNER OR OWNER'S REPRESENTATIVE SHALL NOTIFY THE DEVELOPMENT SERVICES DEPARTMENT, 512-974-2278 OR BY EMAIL AT ENVIRONMENTAL.INSPECTIONS@AUSTINTEXAS.GOV AT I FAST THREE DAYS PRIOR TO THE MEETING DATE. COA APPROVED ESC PLAN AND TPDES SWPPP (IF REQUIRED) SHOULD BE REVIEWED BY COA EV INSPECTOR AT THIS TIME.
- ANY MAJOR VARIATION IN MATERIALS OR LOCATIONS OF CONTROLS OR FENCES FROM THOSE SHOWN ON THE APPROVED PLANS WILL REQUIRE A REVISION AND MUST BE APPROVED BY THE REVIEWING ENGINEER. ENVIRONMENTAL SPECIALIST OR CITY ARBORIST AS APPROPRIATE. MAJOR REVISIONS MUST BE APPROVED BY AUTHORIZED COA STAFF. MINOR CHANGES TO BE MADE AS FIELD REVISIONS TO THE EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE ENVIRONMENTAL INSPECTOR DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES.
- THE CONTRACTOR IS REQUIRED TO PROVIDE A CERTIFIED INSPECTOR THAT IS EITHER A LICENSED ENGINEER (OR PERSON DIRECTLY SUPERVISED BY THE LICENSED ENGINEER) OR CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC OR CPESC - IT), CERTIFIED EROSION, SEDIMENT AND STORMWATER -INSPECTOR (CESSWI OR CESSWI - IT) OR CERTIFIED INSPECTOR OF SEDIMENTATION AND EROSION CONTROLS (CISEC OR CISEC - IT) CERTIFICATION TO INSPECT THE CONTROLS AND FENCES AT WEEKLY OR BI-WEEKLY INTERVALS AND AFTER ONE-HALF (1/2) INCH OR GREATER RAINFALL EVENTS TO INSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES OR ONE-THIRD (1/3) OF THE
- PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED, ACCUMULATED SEDIMENT REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES.
- ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS; ONE SQUARE FOOT IN TOTAL AREA: BLOWS AIR FROM WITHIN THE SUBSTRATE AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION. IN ADDITION, IF THE PROJECT SITE IS LOCATED WITHIN THE EDWARDS AQUIFER, THE PROJECT MANAGER MUST NOTIFY THE TRAVIS COUNTY BAI CONES CANYONI ANDS CONSERVATION PRESERVE (BCCP) BY FMAIL AT BCCP@TRAVISCOUNTYTX.GOV. CONSTRUCTION ACTIVITIES WITHIN 50 FEET OF THE VOID MUST STOP.
- TEMPORARY AND PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED ALL DISTURBED AREAS TO BE REVEGETATED ARE REQUIRED TO PLACE A MINIMUM OF SIX (6) INCHES OF TOPSOIL [SEE STANDARD SPECIFICATION ITEM NO. 601S.3(A)]. DO NOT ADD TOPSOIL WITHIN THE CRITICAL ROOT ZONE OF EXISTING TREES.
  - TOPSOIL SALVAGED FROM THE EXISTING SITE IS ENCOURAGED FOR USE, BUT IT SHOULD MEET THE STANDARDS SET FORTH IN 601S. • AN OWNER/ENGINEER MAY PROPOSE USE OF ONSITE SALVAGED TOPSOIL WHICH DOES NOT MEET
  - THE CRITERIA OF STANDARD SPECIFICATION 601S BY PROVIDING A SOIL ANALYSIS AND A WRITTEN STATEMENT FROM A QUALIFIED PROFESSIONAL IN SOILS LANDSCAPE ARCHITECTURE OR AGRONOMY INDICATING THE ONSITE TOPSOIL WILL PROVIDE AN EQUIVALENT GROWTH MEDIA AND SPECIFYING WHAT, IF ANY, SOIL AMENDMENTS ARE REQUIRED.
  - SOIL AMENDMENTS SHALL BE WORKED INTO THE EXISTING ONSITE TOPSOIL WITH A DISC OR TILLER TO CREATE A WELL-BLENDED MATERIAL.
- DEVELOPER INFORMATION A. OWNER/DEVELOPER:
  - DEVELOPER: HTG ANDERSON LLC

INSTALLED HEIGHT OF THE CONTROL WHICHEVER IS LESS.

- COMPANY: HOUSING TRUST GROUP LLC CONTACT: MAURICIO TERAN
- EMAIL: MAURICIOT@HTGF.COM PHONE: (786) 347-4554
- A. OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: COMPANY: KIMLEY-HORN & ASSOCIATES, INC.
  - CONTACT: JUSTIN J. KRAMER, P.E. EMAIL: JUSTIN.KRAMER@KIMLEY-HORN.COM
- PHONE: (512) 418-1771 B. PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE.
  - DEVELOPER: HTG ANDERSON LLC COMPANY: HOUSING TRUST GROUP LLC
  - **CONTACT: MAURICIO TERAN** EMAIL: MAURICIOT@HTGF.COM
- PHONE: (786) 347-4554 C. PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA CONTROL MAINTENANCE:
  - DEVELOPER: HTG ANDERSON LLC COMPANY: HOUSING TRUST GROUP LLC
  - CONTACT: MAURICIO TERAN
- EMAIL: MAURICIOT@HTGF.COM PHONE: (786) 347-4554
- 11 THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT NOTIFYING THE DEVELOPMENT SERVICES DEPARTMENT AT 512-974-2278 AT LEAST 48 HOURS PRIOR WITH THE LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL
- FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH OR INCLUDE A COOL SEASON COVER CROP: (WESTERN WHEATGRASS ( PASCOPYRUM SMITHII ) AT 5.6 POUNDS PER ACRE, OATS ( AVENA SATIVA ) AT 4.0 POUNDS PER ACRE, CEREAL RYE GRAIN (SECALE CEREALE) AT 45 POUNDS PER ACRE. CONTRACTOR MUST ENSURE THAT ANY SEED APPLICATION REQUIRING A COOL SEASON COVER CROP DOES NOT UTILIZE ANNUAL RYEGRASS ( LOLIUM MULTIFLORUM ) OR PERENNIAL RYEGRASS ( LOLIUM PERENNE ). COOL SEASON COVER CROPS ARE NOT PERMANENT EROSION CONTROL
- FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 45 POUNDS PER ACRE OR A NATIVE PLANT SEED MIX CONFORMING TO ITEM 604S OR 609S. A. FERTILIZER SHALL BE APPLIED ONLY IF WARRANTED BY A SOIL TEST AND SHALL CONFORM TO ITEM NO.
- 606S, FERTILIZER, FERTILIZATION SHOULD NOT OCCUR WHEN RAINFALL IS EXPECTED OR DURING SLOW PLANT GROWTH OR DORMANCY. CHEMICAL FERTILIZER MAY NOT BE APPLIED IN THE CRITICAL WATER B. HYDROMULCH SHALL COMPLY WITH TABLE 1, BELOW.
- C. TEMPORARY EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 11/2 INCHES HIGH WITH A MINIMUM OF 95% TOTAL COVERAGE SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR TEMPORARY STABILIZATION ARE UNIFORMLY VEGETATED, AND PROVIDED THERE ARE NO BARE SPOTS LARGER THAN 10 SQUARE FEET.
- D. WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, AND STANDARD SPECIFICATION 604S OR 609S.

TABLE 1: HYDROMULCHING FOR TEMPORARY VEGETATIVE STABILIZATION				
MATERIAL	DESCRIPTION	LONGEVITY	TYPICAL APPLICATIONS	APPLICATION RATES
100% OR ANY BLEND OF WOOD, CELLULOSE, STRAW, AND/OR COTTON PLANT MATERIAL (EXCEPT NO MULCH SHALL EXCEED 30% PAPER)	70% OR GREATER WOOD/STRAW 30% OR LESS PAPER OR NATURAL FIBERS	0-3 MONTHS	MODERATE SLOPES; FROM FLAT TO 3:1	1500 TO 2000 LBS PER ACRE

# PERMANENT VEGETATIVE STABILIZATION

- FROM SEPTEMBER 15 TO MARCH 1, SEEDING IS CONSIDERED TO BE TEMPORARY STABILIZATION ONLY. IF COOL SEASON COVER CROPS EXIST WHERE PERMANENT VEGETATIVE STABILIZATION IS DESIRED, THE GRASSES SHALL BE MOWED TO A HEIGHT OF LESS THAN ONE-HALF (½) INCH AND THE AREA SHALL BE RE-SEEDED IN ACCORDANCE WITH TABLE 2 BELOW. ALTERNATIVELY, THE COOL SEASON COVER CROP CAN BE MIXED WITH BERMUDA GRASS OR NATIVE SEED AND INSTALLED TOGETHER, UNDERSTANDING THAT
- GERMINATION OF WARM-SEASON SEED TYPICALLY REQUIRES SOIL TEMPERATURES OF 60 TO 70 DEGREES. FROM MARCH 2 TO SEPTEMBER 14. SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 45 POUNDS PER ACRE WITH A PURITY OF 95% AND A MINIMUM PURE LIVE SEED (PLS) OF 0.83. BERMUDA GRASS IS A WARM SEASON GRASS AND IS CONSIDERED PERMANENT EROSION CONTROL. PERMANENT VEGETATIVE STABILIZATION CAN ALSO BE ACCOMPLISHED WITH A NATIVE PLANT SEED MIX CONFORMING TO ITEM 604S OR
  - A. FERTILIZER USE SHALL FOLLOW THE RECOMMENDATION OF A SOIL TEST. SEE ITEM 606S, FERTILIZER. APPLICATIONS OF FERTILIZER (AND PESTICIDE) ON CITY-OWNED AND MANAGED PROPERTY REQUIRES THE YEARLY SUBMITTAL OF A PESTICIDE AND FERTILIZER APPLICATION RECORD, ALONG WITH A CURRENT COPY OF THE APPLICATOR'S LICENSE. FOR CURRENT COPY OF THE RECORD TEMPLATE CONTACT THE CITY OF AUSTIN'S IPM COORDINATOR.
  - B. HYDROMULCH SHALL COMPLY WITH TABLE 2, BELOW. C. WATER THE SEEDED AREAS IMMEDIATELY AFTER INSTALLATION TO ACHIEVE GERMINATION AND A HEALTHY STAND OF PLANTS THAT CAN ULTIMATELY SURVIVE WITHOUT SUPPLEMENTAL WATER. APPLY THE WATER UNIFORMLY TO THE PLANTED AREAS WITHOUT CAUSING DISPLACEMENT OR EROSION OF THE MATERIALS OR SOIL MAINTAIN THE SEEDBED IN A MOIST CONDITION FAVORABLE FOR PLANT GROWTH. ALL WATERING SHALL COMPLY WITH CITY CODE CHAPTER 6-4 (WATER CONSERVATION), AT RATES AND EREQUENCIES DETERMINED BY A LICENSED IRRIGATOR OR OTHER QUALIFIED PROFESSIONAL, AND AS ALLOWED BY THE AUSTIN WATER UTILITY AND CURRENT WATER RESTRICTIONS AND WATER CONSERVATION INITIATIVES.
  - D. PERMANENT EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 11/2 INCHES HIGH WITH A MINIMUM OF 95 PERCENT FOR THE NON-NATIVE MIX. AND 95 PERCENT COVERAGE FOR THE NATIVE MIX SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR STABILITY MUST BE
  - UNIFORMLY VEGETATED, AND PROVIDED THERE ARE NO BARE SPOTS LARGER THAN 10 SQUARE FEET. E. WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, ITEMS 604S AND 609S.

TABLE 2: HYDROMULCHING FOR PERMANENT VEGETATIVE STABILIZATION					
MATERIAL	DESCRIPTION	LONGEVITY	TYPICAL APPLICATIONS	APPLICATION RATES	
BONDED FIBER MATRIX (BFM)	80% ORGANIC DEFIBRATED FIBERS 10% TACKIFIER				
10% TACKIFIER		6 MONTHS	ON SLOPES UP TO 2:1 AND EROSIVE SOIL CONDITIONS	2500 TO 4000 LBS PER ACRE (SEE MANUFACTURERS RECOMMENDATIONS)	
FIBER REINFORCED MATRIX (FRM)	65% ORGANIC DEFIBRATED FIBERS 25% REINFORCING FIBERS OR LESS 10% TACKIFIER	UP TO 12 MONTHS	ON SLOPES UP TO 1:1 AND EROSIVE SOIL CONDITIONS	3000 TO 4500 LBS PER ACRE (SEE MANUFACTURERS RECOMMENDATIONS)	

- I. ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRE A SITE PLAN AMENDMENT AND APPROVAL FROM THE CITY OF AUSTIN DEVELOPMENT SERVICES DEPARTMENT
- 2. APPROVAL OF THIS SITE PLAN DOES NOT INCLUDE BUILDING CODE AND FIRE CODE APPROVAL NOR BUILDING
- 3. ALL SIGNS MUST COMPLY WITH THE REQUIREMENTS OF THE SIGN AND LAND DEVELOPMENT CODE.
- 4. THE OWNER IS RESPONSIBLE FOR ALL COST OF RELOCATION, OR DAMAGE TO, UTILITIES.
- 5. ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE.
- 6. A DEVELOPMENT PERMIT MUST BE ISSUED PRIOR TO AN APPLICATION FOR BUILDING PERMIT FOR NON-CONSOLIDATED OR PLANNING COMMISSION APPROVED SITE PLANS.
- 7. WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY AUSTIN WATER.
- 8. ALL EXISTING STRUCTURES SHOWN TO BE REMOVED WILL REQUIRE A DEMOLITION PERMIT FROM THE CITY OF AUSTIN DEVELOPMENT SERVICES DEPARTMENT.
- 9. FOR DRIVEWAY CONSTRUCTION: THE OWNER IS RESPONSIBLE FOR ALL COSTS FOR RELOCATION OF, OR DAMAGE TO UTILITIES.
- 10. FOR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, A ROW EXCAVATION PERMIT IS REQUIRED.

AS A COMPONENT OF AN EFFECTIVE REMEDIAL TREE CARE PROGRAM PER ENVIRONMENTAL CRITERIA MANUAL SECTION 3.5.4, PRESERVED TREES WITHIN THE LIMITS OF CONSTRUCTION MAY REQUIRE SOIL AERATION AND SUPPLEMENTAL NUTRIENTS. SOIL AND/OR FOLIAR ANALYSIS SHOULD BE USED TO DETERMINE THE NEED FOR SUPPLEMENTAL NUTRIENTS. THE CITY ARBORIST MAY REQUIRE THESE ANALYSES AS PART OF A COMPREHENSIVE TREE CARE PLAN. SOIL PH SHALL BE CONSIDERED WHEN DETERMINING THE FERTILIZATION COMPOSITION AS SOIL PH INFLUENCES THE TREE'S ABILITY TO UPTAKE NUTRIENTS FROM THE SOIL. IF ANALYSES INDICATE THE NEED FOR SUPPLEMENTAL NUTRIENTS. THEN HUMATE/NUTRIENT SOLUTIONS WITH MYCORRHIZAE COMPONENTS ARE HIGHLY RECOMMENDED. IN ADDITION, SOIL ANALYSIS MAY BE NEEDED TO DETERMINE IF ORGANIC MATERIAL OR BENEFICIAL MICROORGANISMS ARE NEEDED TO IMPROVE SOIL HEALTH. MATERIALS AND METHODS ARE TO BE APPROVED BY THE CITY ARBORIST (512-974-1876) PRIOR TO APPLICATION. THE OWNER OR GENERAL CONTRACTOR SHALL SELECT A FERTILIZATION CONTRACTOR AND ENSURE COORDINATION WITH THE CITY ARBORIS'

PRE-CONSTRUCTION TREATMENT SHOULD BE APPLIED IN THE APPROPRIATE SEASON, IDEALLY THE SEASON PRECEDING THE PROPOSED CONSTRUCTION, MINIMALLY, AREAS TO BE TREATED INCLUDE THE ENTIRE CRITICAL ROOT ZONE OF TREES AS DEPICTED ON THE CITY APPROVED PLANS. TREATMENT SHOULD INCLUDE, BUT NOT LIMITED TO, FERTILIZATION, SOIL TREATMENT, MULCHING, AND PROPER PRUNING. POST-CONSTRUCTION TREATMENT SHOULD OCCUR DURING FINAL REVEGETATION OR AS DETERMINED BY A QUALIFIED ARBORIST AFTER CONSTRUCTION, CONSTRUCTION ACTIVITIES OFTEN RESULT IN A REDUCTION IN SOIL

MACRO AND MICRO PORES AND AN INCREASE IN SOIL BULK DENSITY. TO AMELIORATE THE DEGRADED SOIL CONDITIONS. AERATION VIA WATER AND/OR AIR INJECTED INTO THE SOIL IS NEEDED OR BY OTHER METHODS AS APPROVED BY THE CITY ARBORIST. THE PROPOSED NUTRIENT MIX SPECIFICATIONS AND SOIL AND/OR FOLIAR ANALYSIS RESULTS NEED TO BE PROVIDED TO AND APPROVED BY THE CITY ARBORIST PRIOR TO APPLICATION (FAX # 512-974-3010). CONSTRUCTION WHICH WILL BE COMPLETED IN LESS THAN 90 DAYS MAY USE MATERIALS AT 1/2 RECOMMENDED RATES. ALTERNATIVE ORGANIC FERTILIZER MATERIALS ARE ACCEPTABLE WHEN APPROVED BY THE CITY ARBORIST. WITHIN 7 DAYS AFTER FERTILIZATION IS PERFORMED, THE CONTRACTOR SHALL PROVIDE DOCUMENTATION OF THE WORK PERFORMED TO THE CITY ARBORIST. CITY OF AUSTIN DEVELOPMENT SERVICES DEPARTMENT. P.O. BOX 1088, AUSTIN, TX 78767. THIS NOTE SHOULD BE REFERENCED AS ITEM #1 IN THE SEQUENCE OF CONSTRUCTION

# APPENDIX P-4 - SEQUENCE OF CONSTRUCTION:

- TEMPORARY EROSION AND SEDIMENTATION CONTROLS ARE TO BE INSTALLED AS INDICATED ON THE APPROVED SITE PLAN OR SUBDIVISION CONSTRUCTION PLAN AND IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) THAT IS REQUIRED TO BE POSTED ON THE SITE. INSTALL TREE PROTECTION, INITIATE TREE MITIGATION MEASURES AND CONDUCT "PRE - CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE).
- THE ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR MUST CONTACT THE DEVELOPMENT SERVICES DEPARTMENT, ENVIRONMENTAL INSPECTION, AT 512-974-2278, 72 HOURS PRIOR TO THE SCHEDULED DATE OF THE REQUIRED ON-SITE PRECONSTRUCTION MEETING.
- 3. THE ENVIRONMENTAL PROJECT MANAGER, AND/OR SITE SUPERVISOR, AND/OR DESIGNATED RESPONSIBLE PARTY, AND THE GENERAL CONTRACTOR WILL FOLLOW THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE REVISED, IF NEEDED, TO COMPLY WITH CITY INSPECTORS' DIRECTIVES, AND REVISED CONSTRUCTION SCHEDULE RELATIVE TO THE WATER QUALITY PLAN REQUIREMENTS AND THE EROSION PLAN.
- 4. ROUGH GRADE THE POND(S) TO 100% PROPOSED CAPACITY. EITHER THE PERMANENT OUTLET STRUCTURE OR A TEMPORARY OUTLET MUST BE CONSTRUCTED PRIOR TO DEVELOPMENT OF EMBANKMENT OR EXCAVATION THAT LEADS TO PONDING CONDITIONS. THE OUTLET SYSTEM MUST CONSIST OF A SUMP PIT OUTLET AND AN EMERGENCY SPILLWAY MEETING THE REQUIREMENTS OF THE DRAINAGE CRITERIA MANUAL AND/OR THE ENVIRONMENTAL CRITERIA MANUAL, AS REQUIRED. THE OUTLET SYSTEM SHALL BE PROTECTED FROM EROSION AND SHALL BE MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION UNTIL INSTALLATION OF THE PERMANENT WATER QUALITY POND(S).
- 5. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE.
- 6. BEGIN SITE CLEARING/CONSTRUCTION (OR DEMOLITION) ACTIVITIES.
- 7. IN THE BARTON SPRINGS ZONE, THE ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR WILL SCHEDULE A MID-CONSTRUCTION CONFERENCE TO COORDINATE CHANGES IN THE CONSTRUCTION SCHEDULE AND EVALUATE EFFECTIVENESS OF THE EROSION CONTROL PLAN AFTER POSSIBLE CONSTRUCTION ALTERATIONS TO THE SITE, PARTICIPANTS SHALL INCLUDE THE CITY INSPECTOR, PROJECT ENGINEER, GENERAL CONTRACTOR AND ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR, THE ANTICIPATED COMPLETION DATE AND FINAL CONSTRUCTION SEQUENCE AND INSPECTION SCHEDULE WILL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR.
- 8. PERMANENT WATER QUALITY PONDS OR CONTROLS WILL BE CLEANED OUT AND FILTER MEDIA WILL BE INSTALLED PRIOR TO/CONCURRENTLY WITH REVEGETATION OF SITE. STORM DRAINS WILL BE OPERATIONAL
- 9. COMPLETE CONSTRUCTION AND START REVEGETATION OF THE SITE AND INSTALLATION OF LANDSCAPING.
- 10. UPON COMPLETION OF THE SITE CONSTRUCTION AND REVEGETATION OF A PROJECT SITE. THE DESIGN ENGINEER SHALL SUBMIT AN ENGINEER'S LETTER OF CONCURRENCE BEARING THE ENGINEER'S SEAL SIGNATURE. AND DATE TO THE DEVELOPMENT SERVICES DEPARTMENT INDICATING THAT CONSTRUCTION INCLUDING REVEGETATION, IS COMPLETE AND IN SUBSTANTIAL COMPLIANCE WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY
- 11. UPON COMPLETION OF LANDSCAPE INSTALLATION OF A PROJECT SITE, THE LANDSCAPE ARCHITECT SHALL SUBMIT A LETTER OF CONCURRENCE TO THE DEVELOPMENT SERVICES DEPARTMENT INDICATING THAT THE REQUIRED LANDSCAPING IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY
- 12. AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY INSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR, REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND COMPLETE ANY NECESSARY FINAL REVEGETATION RESULTING FROM REMOVAL OF THE CONTROLS. CONDUCT ANY MAINTENANCE AND REHABILITATION OF THE WATER QUALITY PONDS OR CONTROLS.

SHEET NUMBER

ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THESE PLANS, CITY (OR TOWN) STANDARD DETAILS AND SPECIFICATIONS. THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA. AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION AND DETAIL SHALL BE FOLLOWED.

THE CONTRACTOR SHALL COMPLY WITH CITY (OR TOWN) "GENERAL NOTES" FOR CONSTRUCTION IF EXISTING AND REQUIRED BY THE CITY. FOR INSTANCES WHERE THEY CONFLICT WITH THESE KH GENERAL NOTES, THEN THE MORE RESTRICTIVE SHALL APPLY. THE CONTRACTOR SHALL FURNISH ALL MATERIAL AND LABOR TO CONSTRUCT THE FACILITY AS SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS IN ACCORDANCE WITH THE APPROPRIATE AUTHORITIES' SPECIFICATIONS AND REQUIREMENTS. arphi . THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING TO DETERMINE EXISTING CONDITIONS. . THE EXISTING CONDITIONS SHOWN ON THESE PLANS WERE PROVIDED BY THE TOPOGRAPHIC SURVEY PREPARED BY THE PROJECT

SURVEYOR, AND ARE BASED ON THE BENCHMARKS SHOWN. THE CONTRACTOR SHALL REFERENCE THE SAME BENCHMARKS. THE CONTRACTOR SHALL REVIEW AND VERIFY THE EXISTING TOPOGRAPHIC SURVEY SHOWN ON THE PLANS REPRESENTS EXISTING FIELD CONDITIONS PRIOR TO CONSTRUCTION, AND SHALL REPORT ANY DISCREPANCIES FOUND TO THE OWNER AND ENGINEER IMMEDIATELY

IF THE CONTRACTOR DOES NOT ACCEPT THE EXISTING TOPOGRAPHIC SURVEY AS SHOWN ON THE PLANS, WITHOUT EXCEPTION, THEN THE CONTRACTOR SHALL SUPPLY AT THEIR OWN EXPENSE, A TOPOGRAPHIC SURVEY BY A REGISTERED PROFESSIONAL LAND SURVEYOR TO THE OWNER AND ENGINEER FOR REVIEW. CONTRACTOR SHALL PROVIDE ALL CONSTRUCTION SURVEYING AND STAKING

. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL CONTROL, INCLUDING BENCHMARKS PRIOR TO COMMENCING CONSTRUCTION OR STAKING OF IMPROVEMENTS. PROPERTY LINES AND CORNERS SHALL BE HELD AS THE HORIZONTAL CONTROL. 0. THE CONTRACTOR SHALL REVIEW AND VERIFY ALL DIMENSIONS, ELEVATIONS, AND FIELD CONDITIONS THAT MAY AFFECT CONSTRUCTION. ANY DISCREPANCIES ON THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE ARCHITECT. ENGINEER. AND IF APPLICABLE THE CITY AND OWNER, NO CONSIDERATION WILL BE GIVEN TO CHANGE ORDERS FOR WHICH THE CITY, ENGINEER, AND OWNER WERE NOT CONTACTED PRIOR TO CONSTRUCTION OF THE AFFECTED ITEM. CONTRACTOR SHALL THOROUGHLY CHECK COORDINATION OF CIVIL, LANDSCAPE, MEP, ARCHITECTURAL, AND OTHER PLANS PRIOR TO COMMENCING CONSTRUCTION. OWNER/ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY PRIOR TO COMMENCING WITH CONSTRUCTION

2.IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES WHICH MAY HAVE BURIED OR AERIAL UTILITIES WITHIN OR NEAR THE CONSTRUCTION AREA BEFORE COMMENCING WORK TO HAVE THEM LOCATE THEIR EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AN ADEQUATE MINIMUM NOTICE TO ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION.

3. CONTRACTOR SHALL CALL TEXAS 811 AN ADEQUATE AMOUNT OF TIME PRIOR TO COMMENCING CONSTRUCTION OR ANY EXCAVATION. 14. CONTRACTOR SHALL USE EXTREME CAUTION AS THE SITE CONTAINS VARIOUS KNOWN AND UNKNOWN PUBLIC AND PRIVATE UTILITIES. 5. THE LOCATIONS, ELEVATIONS, DEPTH, AND DIMENSIONS OF EXISTING UTILITIES SHOWN ON THE PLANS WERE OBTAINED FROM AVAILABLE UTILITY COMPANY MAPS AND PLANS, AND ARE CONSIDERED APPROXIMATE AND INCOMPLETE. IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO VERIFY THE PRESENCE, LOCATION, ELEVATION, DEPTH, AND DIMENSION OF EXISTING UTILITIES SUFFICIENTLY IN ADVANCE OF CONSTRUCTION SO THAT ADJUSTMENTS CAN BE MADE TO PROVIDE ADEQUATE CLEARANCES. THE ENGINEER SHALL BE NOTIFIED WHEN A PROPOSED IMPROVEMENT CONFLICTS WITH AN EXISTING UTILITY.

3. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY ADJUSTMENTS AND RELOCATIONS OF EXISTING UTILITIES THAT CONFLICT WITH THE PROPOSED IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO, ADJUSTING EXISTING MANHOLES TO MATCH PROPOSED GRADE, RELOCATING EXISTING POLES AND GUY WIRES THAT ARE LOCATED IN PROPOSED DRIVEWAYS, ADJUSTING THE HORIZONTAL OR VERTICAL ALIGNMENT OF EXISTING UNDERGROUND UTILITIES TO ACCOMMODATE PROPOSED GRADE OR CROSSING WITH A PROPOSED UTILITY, AND ANY OTHERS THAT MAY BE ENCOUNTERED THAT ARE UNKNOWN AT THIS TIME AND NOT SHOWN ON

7. CONTRACTOR SHALL ARRANGE FOR OR PROVIDE, AT ITS EXPENSE, ALL GAS, TELECOMMUNICATIONS, CABLE, OVERHEAD AND UNDERGROUND POWER LINE, AND UTILITY POLE ADJUSTMENTS NEEDED.

8. CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION OF FRANCHISE UTILITIES THAT ARE NECESSARY FOR ON-SITE AND OFF-SITE CONSTRUCTION, AND SERVICE TO THE PROPOSED DEVELOPMENT. 9. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ALL DAMAGES DUE TO THE CONTRACTORS' FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES. THE OWNER OR ENGINEER WILL ASSUME NO LIABILITY FOR ANY DAMAGES SUSTAINED OR COST INCURRED OR RELOCATE A UTILITY. THE UTILITY COMPANY OR DEPARTMENT AFFECTED SHALL BE CONTACTED BY THE CONTRACTOR AND THEIR PERMISSION OBTAINED REGARDING THE METHOD TO USE FOR SUCH WORK.

D.BRACING OF UTILITY POLES MAY BE REQUIRED BY THE UTILITY COMPANIES WHEN TRENCHING OR EXCAVATING IN CLOSE PROXIMITY TO THE POLES. THE COST OF BRACING POLES WILL BE BORNE BY THE CONTRACTOR, WITH NO SEPARATE PAY ITEM FOR THIS WORK. THE COST IS INCIDENTAL TO THE PAY ITEM. 1.CONTRACTOR SHALL USE ALL NECESSARY SAFETY PRECAUTIONS TO AVOID CONTACT WITH OVERHEAD AND UNDERGROUND POWER LINES. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE, FEDERAL AND UTILITY OWNER REGULATIONS PERTAINING TO WORK SETBACKS FROM POWER LINES.

22.THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL REQUIRED CONSTRUCTION PERMITS, APPROVALS, AND BONDS PRIOR TO 3.THE CONTRACTOR SHALL HAVE AVAILABLE AT THE JOB SITE AT ALL TIMES A COPY OF THE CONTRACT DOCUMENTS INCLUDING PLANS, GEOTECHNICAL REPORT AND ADDENDA, PROJECT AND CITY SPECIFICATIONS, AND SPECIAL CONDITIONS, COPIES OF ANY REQUIRED CONSTRUCTION PERMITS, EROSION CONTROL PLANS, SWPPP AND INSPECTION REPORTS.

SUFFICIENTLY IN ADVANCE OF CONSTRUCTION OF THAT ITEM, SO THAT NO LESS THAN 10 BUSINESS DAYS FOR REVIEW AND RESPONSE IS AVAII ABI F 25.ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES, JURISDICTIONAL AGENCIES, AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO USE OF THE FACILITY AND THE FINAL CONNECTION OF SERVICES.

4.ALL SHOP DRAWINGS AND OTHER DOCUMENTS THAT REQUIRE ENGINEER REVIEW SHALL BE SUBMITTED BY THE CONTRACTOR

6.CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 27.CONTRACTOR'S BID PRICE SHALL INCLUDE ALL INSPECTION FEES. 28.ALL SYMBOLS SHOWN ON THESE PLANS (E.G. FIRE HYDRANT, METERS, VALVES, INLETS, ETC....) ARE FOR PRESENTATION PURPOSES ONLY AND ARE NOT TO SCALE. CONTRACTOR SHALL COORDINATE FINAL SIZES AND LOCATIONS WITH APPROPRIATE CITY INSPECTOR.

29.THE SCOPE OF WORK FOR THE CIVIL IMPROVEMENTS SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. REFERENCE THE BUILDING PLANS (E.G. ARCHITECTURAL, STRUCTURAL, MEP) FOR AREAS WITHIN 5-FEET OF THE BUILDING AND WITHIN THE BUILDING FOOTPRINT 30.REFER TO ARCHITECTURAL AND STRUCTURAL PLANS FOR ALL FINAL BUILDING DIMENSIONS.

31.THE PROPOSED BUILDING FOOTPRINT(S) SHOWN IN THESE PLANS WAS PROVIDED TO KIMLEY-HORN AND ASSOCIATES, INC. (KH) BY THE PROJECT ARCHITECT AT THE TIME THESE PLANS WERE PREPARED. IT MAY NOT BE THE FINAL CORRECT VERSION BECAUSE THE BUILDING DESIGN WAS ONGOING. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFIRMING THE FINAL CORRECT VERSION OF THE BUILDING FOOTPRINT WITH THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO LAYOUT. DIMENSIONS AND/OR COORDINATES SHOWN ON THESE PLANS WERE BASED ON THE ABOVE STATED ARCHITECTURAL FOOTPRINT, AND ARE THEREFORE A PRELIMINARY LOCATION OF THE BUILDING. THE CONTRACTOR IS SOLELY RESPONSIBLE TO VERIEY WHAT PART OF THE BUILDING THE ARCHITECT'S FOOTPRINT REPRESENTS (E.G. SLAB, OUTSIDE WALL, MASONRY LEDGE, ETC.....) AND TO CONFIRM ITS FINAL POSITION ON THE SITE BASED ON THE FINAL ARCHITECTURAL FOOTPRINT, CIVIL DIMENSION CONTROL PLAN, SURVEY BOUNDARY AND/OR PLAT. ANY

DIFFERENCES FOUND SHALL BE REPORTED TO KH IMMEDIATELY. 32.ALL CONSTRUCTION SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING

33.CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS TESTING AND CERTIFICATION. UNLESS SPECIFIED OTHERWISE BY OWNER. ALL MATERIALS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND COMPLY WITH CITY STANDARD SPECIFICATIONS AND GEOTECHNICAL REPORT. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING MATERIALS. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR MATERIALS TESTING. 34.ALL COPIES OF MATERIALS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING

35.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE MATERIALS, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 36.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING. THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO

FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING. 37.ALL CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA. NO ENCROACHMENTS OUTSIDE OF THE WORK AREA WILL BE ALLOWED. ANY DAMAGE RESULTING THEREFROM SHALL BE CONTRACTOR'S SOLE RESPONSIBILITY TO REPAIR. 38. THE CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES, UTILITIES, MANHOLES, POLES, GUY WIRES, VALVE COVERS, VAULT LIDS, FIRE HYDRANTS, COMMUNICATION BOXES/PEDESTALS, AND OTHER FACILITIES TO REMAIN AND SHALL REPAIR ANY DAMAGES AT

39.THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE ANY PHYSICAL DAMAGE TO PRIVATE PROPERTY OR PUBLIC IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO: FENCES, WALLS, SIGNS, PAVEMENT, CURBS, UTILITIES, SIDEWALKS, GRASS, TREES. LANDSCAPING, AND IRRIGATION SYSTEMS, ETC.... TO ORIGINAL CONDITION OR BETTER AT NO COST TO THE OWNER. 40.ALL AREAS IN EXISTING RIGHT-OF-WAY DISTURBED BY SITE CONSTRUCTION SHALL BE REPAIRED TO ORIGINAL CONDITION OR BETTER

INCLUDING AS NECESSARY GRADING, LANDSCAPING, CULVERTS, AND PAVEMENT. 41.THE CONTRACTOR SHALL SALVAGE ALL EXISTING POWER POLES, SIGNS, WATER VALVES, FIRE HYDRANTS, METERS, ETC... THAT ARE TO BE RELOCATED DURING CONSTRUCTION. 42.CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING

DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. 43.THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 44.THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

45.SITE SAFETY IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR. 46.THESE PLANS DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONTRACTOR OR ITS EMPLOYEES, AGENTS OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE ENGINEER'S SEAL HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF ALL REQUIRED SAFETY

47.SIGNS RELATED TO SITE OPERATION OR SAFETY ARE NOT INCLUDED IN THESE PLANS. 48.CONTRACTOR OFFICE AND STAGING AREA SHALL BE AGREED ON BY THE OWNER AND CONTRACTOR PRIOR TO BEGINNING OF CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING REQUIREMENTS FOR THE CONSTRUCTION OFFICE, TRAILER, STORAGE, AND STAGING OPERATIONS AND LOCATIONS.

49.LIGHT POLES, SIGNS, AND OTHER OBSTRUCTIONS SHALL NOT BE PLACED IN ACCESSIBLE ROUTES. 50.ALL SIGNS, PAVEMENT MARKINGS, AND OTHER TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES".

51.TOP RIM ELEVATIONS OF ALL EXISTING AND PROPOSED MANHOLES SHALL BE COORDINATED WITH TOP OF PAVEMENT OR FINISHED GRADE AND SHALL BE ADJUSTED TO BE FLUSH WITH THE ACTUAL FINISHED GRADE AT THE TIME OF PAVING. 52.CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED VALVES, FIRE HYDRANTS, AND OTHER UTILITY APPURTENANCES TO MATCH ACTUAL FINISHED GRADES AT THE TIME OF PAVING. 53. THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND PHASING, AND SHALL CONTACT THE APPROPRIATE CITY

OFFICIALS, INCLUDING BUILDING OFFICIAL, ENGINEERING INSPECTOR, AND FIRE MARSHALL TO LEARN OF ANY REQUIREMENTS. 54.CONTRACTOR IS RESPONSIBLE FOR PREPARATION, SUBMITTAL, AND APPROVAL BY THE CITY OF A TRAFFIC CONTROL PLAN PRIOR TO THE START OF CONSTRUCTION, AND THEN THE IMPLEMENTATION OF THE PLAN.

55.CONTRACTOR SHALL KEEP A NEAT AND ACCURATE RECORD OF CONSTRUCTION, INCLUDING ANY DEVIATIONS OR VARIANCES FROM 56.THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.

THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS, LAWS, AND ORDINANCES THAT APPLY TO THE CONSTRUCTION SITE LAND DISTURBANCE. 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE "TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS

POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000 EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBANCE.

4. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THE i. CONTRACTOR IS SOLELY RESPONSIBLE FOR INSTALLATION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL EROSION

CONTROL DEVICES, BEST MANAGEMENT PRACTICES (BMPS), AND FOR UPDATING THE EROSION CONTROL PLAN DURING CONSTRUCTION AS FIELD CONDITIONS CHANGE CONTRACTOR SHALL DOCUMENT THE DATES OF INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL FOR EACH BMP EMPLOYED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE. AS STORM SEWER INLETS ARE INSTALLED ON-SITE, TEMPORARY EROSION CONTROL DEVICES SHALL BE INSTALLED AT EACH INLET PER

THE EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE AREA IT PROTECTS HAS BEEN PERMANENTLY STABILIZED. CONTRACTOR SHALL PROVIDE ADEQUATE EROSION CONTROL DEVICES NEEDED DUE TO PROJECT PHASING. 10. CONTRACTOR SHALL OBSERVE THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES AND MAKE FIELD ADJUSTMENTS AND

MODIFICATIONS AS NEEDED TO PREVENT SEDIMENT FROM LEAVING THE SITE. IF THE EROSION CONTROL DEVICES DO NOT

EFFECTIVELY CONTROL EROSION AND PREVENT SEDIMENTATION FROM WASHING OFF THE SITE, THEN THE CONTRACTOR SHALL

ENCIRCLING THE AREA WITH AN APPROPRIATE BARRIER.

I1.OFF-SITE SOIL BORROW, SPOIL, AND STORAGE AREAS (IF APPLICABLE) ARE CONSIDERED AS PART OF THE PROJECT SITE AND MUST ALSO COMPLY WITH THE EROSION CONTROL REQUIREMENTS FOR THIS PROJECT. THIS INCLUDES THE INSTALLATION OF BMP'S TO CONTROL EROSION AND SEDIMENTATION AND THE ESTABLISHMENT OF PERMANENT GROUND COVER ON DISTURBED AREAS PRIOR TO FINAL APPROVAL OF THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP AND EROSION CONTROL PLAN TO INCLUDE BMPS FOR ANY OFF-SITE THAT ARE NOT ANTICIPATED OR SHOWN ON THE EROSION CONTROL PLAN. 12. ALL STAGING. STOCKPILES. SPOIL. AND STORAGE SHALL BE LOCATED SUCH THAT THEY WILL NOT ADVERSELY AFFECT STORM WATER QUALITY. PROTECTIVE MEASURES SHALL BE PROVIDED IF NEEDED TO ACCOMPLISH THIS REQUIREMENT, SUCH AS COVERING OR

13. CONTRACTORS SHALL INSPECT ALL EROSION CONTROL DEVICES, BMPS, DISTURBED AREAS, AND VEHICLE ENTRY AND EXIT AREAS WEEKLY AND WITHIN 24 HOURS OF ALL RAINFALL EVENTS OF 0.5 INCHES OR GREATER, AND KEEP A RECORD OF THIS INSPECTION IN THE SWPPP BOOKLET IF APPLICABLE, TO VERIFY THAT THE DEVICES AND EROSION CONTROL PLAN ARE FUNCTIONING PROPERLY. 14. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT ALL PRIMARY POINTS OF ACCESS IN ACCORDANCE WITH CITY SPECIFICATIONS. CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION TRAFFIC USES THE STABILIZED ENTRANCE AT ALL TIMES FOR ALL INGRESS/EGRESS

15. SITE ENTRY AND EXITS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING AND FLOWING OF SEDIMENT AND DIRT ONTO OFF-SITE ROADWAYS. ALL SEDIMENT AND DIRT FROM THE SITE THAT IS DEPOSITED ONTO AN OFF-SITE ROADWAY SHALL BE

16. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL SILT AND DEBRIS FROM THE AFFECTED OFF-SITE ROADWAYS THAT ARE A RESULT OF THE CONSTRUCTION, AS REQUESTED BY OWNER AND CITY. AT A MINIMUM, THIS SHOULD OCCUR ONCE PER DAY FOR THE OFF-SITE ROADWAYS

17. WHEN WASHING OF VEHICLES IS REQUIRED TO REMOVE SEDIMENT PRIOR TO EXITING THE SITE, IT SHALL BE DONE IN AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP BMP 18 CONTRACTOR SHALL INSTALL A TEMPORARY SEDIMENT BASIN FOR ANY ON-SITE DRAINAGE AREAS THAT ARE GREATER THAN 10 ACRES. PER TCEQ AND CITY STANDARDS. IF NO ENGINEERING DESIGN HAS BEEN PROVIDED FOR A SEDIMENTATION BASIN ON THESE PLANS. THEN THE CONTRACTOR SHALL ARRANGE FOR AN APPROPRIATE DESIGN TO BE PROVIDED 19. ALL FINES IMPOSED FOR SEDIMENT OR DIRT DISCHARGED FROM THE SITE SHALL BE PAID BY THE RESPONSIBLE CONTRACTOR

20.WHEN SEDIMENT OR DIRT HAS CLOGGED THE CONSTRUCTION ENTRANCE VOID SPACES BETWEEN STONES OR DIRT IS BEING TRACKED ONTO A ROADWAY. THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASH-DOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL SEDIMENTATION. PERIODIC RE-GRADING OR NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFECTIVENESS OF THE CONSTRUCTION ENTRANCE. 21.TEMPORARY SEEDING OR OTHER APPROVED STABILIZATION SHALL BE INITIATED WITHIN 14 DAYS OF THE LAST DISTURBANCE OF ANY AREA, UNLESS ADDITIONAL CONSTRUCTION IN THE AREA IS EXPECTED WITHIN 21 DAYS OF THE LAST DISTURBANCE.

22. CONTRACTOR SHALL FOLLOW GOOD HOUSEKEEPING PRACTICES DURING CONSTRUCTION, ALWAYS CLEANING UP DIRT, LOOSE MATERIAL AND TRASH AS CONSTRUCTION PROGRESSES 23.UPON COMPLETION OF FINE GRADING, ALL SURFACES OF DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED. STABILIZATION IS ACHIEVED WHEN THE AREA IS EITHER COVERED BY PERMANENT IMPERVIOUS STRUCTURES, SUCH AS BUILDINGS, SIDEWALK,

PAVEMENT, OR A UNIFORM PERENNIAL VEGETATIVE COVER. 24.AT THE CONCLUSION OF THE PROJECT, ALL INLETS, DRAIN PIPE, CHANNELS, DRAINAGEWAYS AND BORROW DITCHES AFFECTED BY THE CONSTRUCTION SHALL BE DREDGED, AND THE SEDIMENT GENERATED BY THE PROJECT SHALL BE REMOVED AND DISPOSED IN ACCORDANCE WITH APPLICABLE REGULATIONS.

CONTRACTOR SHALL COMPLY WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION REQUIREMENTS. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLITITANT DISCHARGE FLIMINATION SYSTEM TXR 150000

3. THE CONTRACTOR SHALL ENSURE THAT ALL PRIMARY OPERATORS SUBMIT A NOI TO TCEQ AT LEAST SEVEN DAYS PRIOR TO COMMENCING CONSTRUCTION (IF APPLICABLE), OR IF UTILIZING ELECTRONIC SUBMITTAL, PRIOR TO COMMENCING CONSTRUCTION. ALL PRIMARY OPERATORS SHALL PROVIDE A COPY OF THE SIGNED NOI TO THE OPERATOR OF ANY MS4 (TYPICALLY THE CITY) RECEIVING DISCHARGE FROM THE SITE

4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE, INCLUDING POSTING SITE NOTICE, INSPECTIONS, DOCUMENTATION, AND SUBMISSION OF ANY INFORMATION REQUIRED BY THE TCEQ AND EPA (E.G. NOI). BECAUSE OF THE OPERATIONS IN THE VICINITY OF EXISTING UTILITIES OR STRUCTURES. IF IT IS NECESSARY TO SHORE, BRACE, SWING 5. ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICES RELATED TO THE SWPPP SHALL SIGN THE REQUIRED CONTRACTOR CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS SPECIFIED IN THE SWPPP

> A COPY OF THE SWPPP, INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATIONS, AND ANY REVISIONS, SHALL BE SUBMITTED TO THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION. A NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO TCEQ BY ANY PRIMARY OPERATOR WITHIN 30 DAYS AFTER ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND A UNIFORM VEGETATIVE COVER HAS BEEN ESTABLISHED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY STRUCTURES. A TRANSFER OF OPERATIONAL CONTROL HAS OCCURRED. OR THE OPERATOR HAS OBTAINED ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT. A COPY OF THE NOT SHALL BE PROVIDED TO THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.

I. KH IS NOT RESPONSIBLE FOR THE MEANS AND METHODS EMPLOYED BY THE CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS PRELIMINARY DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACT THAT ARE TO BE DEMOLISHED

2. KH DOES NOT WARRANT OR REPRESENT THAT THE PLAN, WHICH WAS PREPARED BASED ON SURVEY AND UTILITY INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY, OR THAT THE UTILITIES SHOWN CAN BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING ITS OWN SITE RECONNAISSANCE TO SCOPE ITS WORK AND TO CONFIRM WITH THE OWNERS OF IMPROVEMENTS AND UTILITIES THE ABILITY AND PROCESS FOR THE REMOVAL OF THEIR FACILITIES

. THIS PLAN IS INTENDED TO GIVE A GENERAL GUIDE TO THE CONTRACTOR, NOTHING MORE. THE GOAL OF THE DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT. REMOVAL OR PRESERVATION OF IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL ARE THE RESPONSIBILITY OF THE CONTRACTOR. 4. CONTRACTOR IS STRONGLY CAUTIONED TO REVIEW THE FOLLOWING REPORTS DESCRIBING SITE CONDITIONS PRIOR TO BIDDING AND

IMPLEMENTING THE DEMOLITION PLAN: a. ENVIRONMENTAL SITE ASSESSMENT PROVIDED BY THE OWNER, b. ASBESTOS BUILDING INSPECTION REPORT(S) PROVIDED BY THE OWNER, GEOTECHNICAL REPORT PROVIDED BY THE OWNER

d. OTHER REPORTS THAT ARE APPLICABLE AND AVAILABLE CONTRACTOR SHALL CONTACT THE OWNER TO VERIFY WHETHER ADDITIONAL REPORTS OR AMENDMENTS TO THE ABOVE CITED REPORTS HAVE BEEN PREPARED AND TO OBTAIN/REVIEW/AND COMPLY WITH THE RECOMMENDATION OF SUCH STUDIES PRIOR TO

STARTING ANY WORK ON THE SITE. CONTRACTOR SHALL COMPLY WITH ALL LOCAL STATE AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO REVIEW THE SITE, DETERMINE THE APPLICABLE REGULATIONS, RECEIVE THE REQUIRED PERMITS AND AUTHORIZATIONS, AND COMPLY. 7. KH DOES NOT REPRESENT THAT THE REPORTS AND SURVEYS REFERENCED ABOVE ARE ACCURATE, COMPLETE, OR COMPREHENSIVE

SHOWING ALL ITEMS THAT WILL NEED TO BE DEMOLISHED AND REMOVED 8. SURFACE PAVEMENT INDICATED MAY OVERLAY OTHER HIDDEN STRUCTURES, SUCH AS ADDITIONAL LAYERS OF PAVEMENT, FOUNDATIONS OR WALLS, THAT ARE ALSO TO BE REMOVED.

1. THE CONTRACTOR AND GRADING SUBCONTRACTOR SHALL VERIFY THE SUITABILITY OF EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE START OF CONSTRUCTION. THE CIVIL ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES. 2. CONTRACTOR SHALL OBTAIN ANY REQUIRED GRADING PERMITS FROM THE CITY.

UNLESS OTHERWISE NOTED, PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN IN PAVED AREA REFLECT TOP OF PAVEMENT SURFACE. IN LOCATIONS ALONG A CURB LINE, ADD 6-INCHES (OR THE HEIGHT OF THE CURB) TO THE PAVING GRADE FOR TOP OF CURB 10. WHERE COVER EXCEEDS 20-FEET OR IS LESS THAN 2-FEET, CLASS IV RCP SHALL BE USED. FI FVATION 4. PROPOSED SPOT ELEVATIONS AND CONTOURS OUTSIDE THE PAVEMENT ARE TO TOP OF FINISHED GRADE

5. PROPOSED CONTOURS ARE APPROXIMATE. PROPOSED SPOT ELEVATIONS AND DESIGNATED GRADIENT ARE TO BE USED IN CASE OF DISCREPANCY 6. ALL FINISHED GRADES SHALL TRANSITION UNIFORMLY BETWEEN THE FINISHED ELEVATIONS SHOWN. CONTOURS AND SPOT GRADES SHOWN ARE ELEVATIONS OF TOP OF THE FINISHED SURFACE. WHEN PERFORMING THE GRADING OPERATIONS, THE CONTRACTOR SHALL PROVIDE AN APPROPRIATE ELEVATION HOLD-DOWN ALLOWANCE FOR THE THICKNESS OF PAVEMENT, SIDEWALK, TOPSOIL, MULCH, STONE, LANDSCAPING, RIP-RAP AND ALL OTHER SURFACE MATERIALS THAT WILL

CONTRIBUTE TO THE TOP OF FINISHED GRADE. FOR EXAMPLE, THE LIMITS OF EARTHWORK IN PAVED AREAS IS THE BOTTOM OF THE PAVEMENT SECTION. 8. NO REPRESENTATIONS OF EARTHWORK QUANTITIES OR SITE BALANCE ARE MADE BY THESE PLANS. THE CONTRACTOR SHALL PROVIDE THEIR OWN EARTHWORK CALCULATION TO DETERMINE THEIR CONTRACT QUANTITIES AND COST. ANY SIGNIFICANT VARIANCE FROM A BALANCED SITE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CIVIL ENGINEER.

9. ALL GRADING AND EARTHWORK SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING SUBSEQUENT ADDENDA 10. ALL EXCAVATION IS UNCLASSIFIED AND SHALL INCLUDE ALL MATERIALS ENCOUNTERED. UNUSABLE EXCAVATED MATERIAL AND ALL WASTE RESULTING FROM SITE CLEARING AND GRUBBING SHALL BE REMOVED FROM THE SITE AND APPROPRIATELY DISPOSED BY THE

I.EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START OF GRADING. REFERENCE EROSION CONTROL PLAN, DETAILS, GENERAL NOTES, AND SWPPP FOR ADDITIONAL INFORMATION AND REQUIREMENTS

12.BEFORE ANY EARTHWORK IS PERFORMED, THE CONTRACTOR SHALL STAKE OUT AND MARK THE LIMITS OF THE PROJECT'S PROPERTY LINE AND SITE IMPROVEMENTS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY ENGINEERING AND SURVEYING FOR LINE AND GRADE CONTROL POINTS RELATED TO EARTHWORK

13. CONTRACTOR TO DISPOSE OF ALL EXCESS EXCAVATION MATERIALS IN A MANNER THAT ADHERES TO LOCAL, STATE AND FEDERAL LAWS AND REGULATIONS. THE CONTRACTOR SHALL KEEP A RECORD OF WHERE EXCESS EXCAVATION WAS DISPOSED, ALONG WITH THE RECEIVING LANDOWNER'S APPROVAL TO DO SO. 14. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF TOPSOIL AT THE COMPLETION OF FINE GRADING. CONTRACTOR

SHALL REFER TO LANDSCAPE ARCHITECTURE PLANS FOR SPECIFICATIONS AND REQUIREMENTS FOR TOPSOIL. 15. CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. 16.NO EARTHWORK FILL SHALL BE PLACED IN ANY EXISTING DRAINAGE WAY, SWALE, CHANNEL, DITCH, CREEK, OR FLOODPLAIN FOR ANY REASON OR ANY LENGTH OF TIME, UNLESS THESE PLANS SPECIFICALLY INDICATE THIS IS REQUIRED. 17. TEMPORARY CULVERTS MAY BE REQUIRED IN SOME LOCATIONS TO CONVEY RUN-OFF.

19. THE CONTRACTOR SHALL CLEAR AND GRUB THE SITE AND PLACE, COMPACT, AND CONDITION FILL PER THE PROJECT GEOTECHNICAL

18. REFER TO DIMENSION CONTROL PLAN, AND PLAT FOR HORIZONTAL DIMENSIONS.

ENGINEER'S SPECIFICATIONS. THE FILL MATERIAL TO BE USED SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO 20.CONTRACTOR IS RESPONSIBLE FOR ALL SOILS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL SOILS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND SHALL COMPLY WITH CITY STANDARD SPECIFICATIONS AND THE GEOTECHNICAL REPORT. SOILS TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING SOILS. THE OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR SOILS TESTING. 21.ALL COPIES OF SOILS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING

22.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE SOILS, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 23.THE SCOPE OF WORK FOR CIVIL IMPROVEMENT SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT AND STRUCTURAL PLANS AND SPECIFICATIONS FILL, CONDITIONING, AND PREPARATION

24.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING. IF NONE IS CURRENTLY EXISTING. 25.CONTRACTOR SHALL ENSURE THAT SUFFICIENT POSITIVE SLOPE AWAY FROM THE BUILDING PAD IS ACHIEVED FOR ENTIRE PERIMETER OF THE PROPOSED BUILDING(S) DURING GRADING OPERATIONS AND IN THE FINAL CONDITION. IF THE CONTRACTOR OBSERVES THAT THIS WILL NOT BE ACHIEVED, THE CONTRACTOR SHALL CONTACT THE ENGINEER TO REVIEW THE LOCATION.

26.THE CONTRACTOR SHALL TAKE ALL AVAILABLE PRECAUTIONS TO CONTROL DUST. CONTRACTOR SHALL CONTROL DUST BY

SPRINKLING WATER, OR BY OTHER MEANS APPROVED BY THE CITY, AT NO ADDITIONAL COST TO THE OWNER. 27 CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES FOR ANY REQUIRED UTILITY ADJUSTMENTS AND/OR RELOCATIONS NEEDED FOR GRADING OPERATIONS AND TO ACCOMMODATE PROPOSED GRADE, INCLUDING THE UNKNOWN UTILITIES NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL REFER TO THE GENERAL NOTES "OVERALL" SECTION THESE PLANS FOR ADDITIONAL INFORMATION.

28.EXISTING TREE LOCATIONS SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL REPORT ANY DISCREPANCIES FOUND IN THE FIELD THAT AFFECT THE GRADING PLAN TO THE CIVIL ENGINEER. 29.CONTRACTOR SHALL FIELD VERIFY ALL PROTECTED TREE LOCATIONS. INDIVIDUAL PROTECTED TREE CRITICAL ROOT ZONES. AND PROPOSED SITE GRADING, AND NOTIFY THE CIVIL ENGINEER AND LANDSCAPE ARCHITECT OF ANY CONFLICTS WITH THE TREE PRESERVATION PLAN BY THE LANDSCAPE ARCHITECT PRIOR TO COMMENCING THE WORK. 18. THE ENDS OF ALL EXISTING WATER MAINS THAT ARE CUT, BUT NOT REMOVED, SHALL BE PLUGGED AND ABANDONED IN PLACE. THIS 30. TREE PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE CITY STANDARD TREE PROTECTION DETAILS AND THE

APPROVED TREE PRESERVATION PLANS BY THE LANDSCAPE ARCHITECT. 31.CONTRACTOR SHALL REFER TO THE LANDSCAPING AND TREE PRESERVATIONS PLANS FOR ALL INFORMATION AND DETAILS

REGARDING EXISTING TREES TO BE REMOVED AND PRESERVED 32.NO TREE SHALL BE REMOVED UNLESS A TREE REMOVAL PERMIT HAS BEEN ISSUED BY THE CITY, OR CITY HAS OTHERWISE CONFIRMED IN WRITING THAT ONE IS NOT NEEDED FOR THE TREE(S)

33.NO TREE SHALL BE REMOVED OR DAMAGED WITHOUT PRIOR AUTHORIZATION OF THE OWNER OR OWNER'S REPRESENTATIVE. EXISTING TREES SHALL BE PRESERVED WHENEVER POSSIBLE AND GRADING IMPACT TO THEM HELD TO A MINIMUM. 34. AFTER PLACEMENT OF SUBGRADE AND PRIOR TO PLACEMENT OF PAVEMENT, CONTRACTOR SHALL TEST AND OBSERVE PAVEMENT AREAS FOR EVIDENCE OF PONDING AND INADEQUATE SLOPE FOR DRAINAGE. ALL AREAS SHALL ADEQUATELY DRAIN TOWARDS THE INTENDED STRUCTURE TO CONVEY STORMWATER RUNOFF. CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND ENGINEER IF ANY AREAS OF POOR DRAINAGE ARE DISCOVERED

35. CONTRACTOR FIELD ADJUSTMENT OF PROPOSED SPOT GRADES IS ALLOWED, IF THE APPROVAL OF THE CIVIL ENGINEER IS OBTAINED.

RETAINING WALLS SHOWN ARE FOR SITE GRADING PURPOSES ONLY, AND INCLUDE ONLY LOCATION AND SURFACE SPOT ELEVATIONS AT THE TOP AND BOTTOM OF THE WALL 2. RETAINING WALL TYPE OR SYSTEM SHALL BE SELECTED BY THE OWNER. E. RETAINING WALL DESIGN SHALL BE PROVIDED BY OTHERS AND SHALL FIT IN THE WALL ZONE OR LOCATION SHOWN ON THESE PLANS.

STRUCTURAL DESIGN AND PERMITTING OF RETAINING WALLS, RAILINGS, AND OTHER WALL SAFETY DEVICES SHALL BE PERFORMED BY A LICENSED ENGINEER AND ARE NOT PART OF THIS PLAN SET 4. RETAINING WALL DESIGN SHALL MEET THE INTENT OF THE GRADING PLAN AND SHALL ACCOUNT FOR ANY INFLUENCE ON ADJACENT BUILDING FOUNDATIONS, UTILITIES, PROPERTY LINES AND OTHER CONSTRUCTABILITY NOTES. 5. RETAINING WALL ENGINEER SHALL CONSULT THESE PLANS AND THE GEOTECHNICAL REPORT FOR POTENTIAL CONFLICTS.

ALL PAVING MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THESE PLANS. THE CITY STANDARD DETAILS AND SPECIFICATIONS. THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA. AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION/DETAIL SHALL BE FOLLOWED.

. ALL PRIVATE ON-SITE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION). INCLUDING ALL ADDENDA. 3. ALL FIRELANE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARDS AND DETAILS. IF THESE ARE DIFFERENT THAN THOSE IN THE GEOTECHNICAL REPORT, THEN THE MORE RESTRICTIVE SHALL BE FOLLOWED. 4. ALL PUBLIC PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS. 5. CONTRACTOR IS RESPONSIBLE FOR ALL PAVING AND PAVING SUBGRADE TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE

ABBREVIATIONS AND DEFINITIONS: BY OWNER. ALL PAVING AND PAVING SUBGRADE TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING PAVING AND SUBGRADE. OWNER SHALL

APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR PAVING AND PAVING SUBGRADE TESTING. : IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE PAVING AND PAVING SUBGRADE THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS 7. DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING. THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING. 8. CURB RAMPS ALONG PUBLIC STREETS AND IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED BASED ON THE CITY STANDARD

CONSTRUCTION DETAIL AND SPECIFICATIONS. 9. PRIVATE CURB RAMPS ON THE SITE (I.E. OUTSIDE PUBLIC STREET RIGHT-OF-WAY) SHALL CONFORM TO ADA AND TAS STANDARDS AND SHALL HAVE A DETECTABLE WARNING SURFACE THAT IS FULL WIDTH AND FULL DEPTH OF THE CURB RAMP. NOT INCLUDING FLARES. 10. ALL ACCESSIBLE RAMPS, CURB RAMPS, STRIPING, AND PAVEMENT MARKINGS SHALL CONFORM TO ADA AND TAS STANDARDS, LATEST

11. ANY COMPONENTS OF THE PROJECT SUBJECT TO RESIDENTIAL USE SHALL ALSO CONFORM TO THE FAIR HOUSING ACT, AND COMPLY WITH THE FAIR HOUSING ACT DESIGN MANUAL BY THE US DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT. 12. CONTRACTOR SHALL CONSTRUCT PROPOSED PAVEMENT TO MATCH EXISTING PAVEMENT WITH A SMOOTH, FLUSH, CONNECTION. 13. CONTRACTOR SHALL FURNISH AND INSTALL ALL PAVEMENT MARKINGS FOR FIRE LANES, PARKING STALLS, HANDICAPPED PARKING SYMBOLS, AND MISCELLANEOUS STRIPING WITHIN PARKING LOT AND AROUND BUILDING AS SHOWN ON THE PLANS. ALL PAINT AND PAVEMENT MARKINGS SHALL ADHERE TO CITY AND OWNER STANDARDS.

14. REFER TO GEOTECHNICAL REPORT FOR PAVING JOINT LAYOUT PLAN REQUIREMENTS FOR PRIVATE PAVEMENT. 15.REFER TO CITY STANDARD DETAILS AND SPECIFICATIONS FOR JOINT LAYOUT PLAN REQUIREMENTS FOR PUBLIC PAVEMENT. 16. ALL REINFORCING STEEL SHALL CONFORM TO THE GEOTECHNICAL REPORT, CITY STANDARDS, AND ASTM A-615, GRADE 60, AND SHALL BE SUPPORTED BY BAR CHAIRS. CONTRACTOR SHALL USE THE MORE STRINGENT OF THE CITY AND GEOTECHNICAL STANDARDS. 17 ALL JOINTS SHALL EXTEND THROUGH THE CURB.

18. THE MINIMUM LENGTH OF OFFSET JOINTS AT RADIUS POINTS SHALL BE 2 FEET. 19. CONTRACTOR SHALL SUBMIT A JOINTING PLAN TO THE ENGINEER AND OWNER PRIOR TO BEGINNING ANY OF THE PAVING WORK. 20.ALL SAWCUTS SHALL BE FULL DEPTH FOR PAVEMENT REMOVAL AND CONNECTION TO EXISTING PAVEMENT. 21.FIRE LANES SHALL BE MARKED AND LABELED AS A FIRELANE PER CITY STANDARDS

22.UNLESS THE PLANS SPECIFICALLY DICTATE TO THE CONTRARY, ON-SITE AND OTHER DIRECTIONAL SIGNS SHALL BE ORIENTED SO THEY ARE READILY VISIBLE TO THE ONCOMING TRAFFIC FOR WHICH THEY ARE INTENDED. 23. CONTRACTOR IS RESPONSIBLE FOR INSTALLING NECESSARY CONDUIT FOR LIGHTING, IRRIGATION, ETC. PRIOR TO PLACEMENT OF PAVEMENT. ALL CONSTRUCTION DOCUMENTS (CIVIL, MEP, LANDSCAPE, IRRIGATION, AND ARCHITECT) SHALL BE CONSULTED. 24.BEFORE PLACING PAVEMENT, CONTRACTOR SHALL VERIFY THAT SUITABLE ACCESSIBLE PEDESTRIAN ROUTES (PER ADA, TAS, AND FHA) EXIST TO AND FROM EVERY DOOR AND ALONG SIDEWALKS. ACCESSIBLE PARKING SPACES. ACCESS AISLES. AND ACCESSIBLE ROUTES. IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL. IN NO CASE SHALL SIDEWALK

SPACES AND ACCESS AISLES SHALL NOT EXCEED 2.0 PERCENT SLOPE IN ANY DIRECTION. 25.CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA/TAS SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA AND TAS SLOPE COMPLIANCE ISSUES.

. ALL STORM SEWER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS.

2. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING STORM SEWER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY STORM SEWER, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.

4. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF CURB INLETS AND GRATE INLETS AND ALL UTILITIES CROSSING THE STORM SEWER. 5. FLOW LINE, TOP-OF-CURB, RIM, THROAT, AND GRATE ELEVATIONS OF PROPOSED INLETS SHALL BE VERIFIED WITH THE GRADING PLAN AND FIELD CONDITIONS PRIOR TO THEIR INSTALLATION.

6. ALL PUBLIC STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS 7. ALL PRIVATE STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. ALL PVC TO RCP CONNECTIONS AND ALL STORM PIPE CONNECTIONS ENTERING STRUCTURES OR OTHER STORM PIPES SHALL HAVE A CONCRETE COLLAR AND BE GROUTED TO ASSURE THE CONNECTION IS WATERTIGHT. 9. ALL PUBLIC STORM SEWER LINES SHALL BE MINIMUM CLASS III RCP. PRIVATE STORM SEWER LINES 18-INCHES AND GREATER SHALL BE

CLASS III RCP OR OTHER APPROVED MATERIAL. 11.IF CONTRACTOR PROPOSES TO USE HDPE OR PVC IN LIEU OF RCP FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPF AND PVC SHALL BE WATERTIGHT

12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL STORM SEWER LINES. 13. EMBEDMENT FOR ALL STORM SEWER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS. 14. ALL WYE CONNECTIONS AND PIPE BENDS ARE TO BE PREFABRICATED AND INSTALLED PER MANUFACTURERS SPECIFICATIONS. 15.USE 4 FOOT JOINTS WITH BEVELED ENDS IF RADIUS OF STORM SEWER IS LESS THAN 100 FEET.

16. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN. PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY.

17. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

ANY PONDS THAT ARE INTENDED TO HOLD WATER INDEFINITELY SHALL BE CONSTRUCTED WATERTIGHT 2. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR POND LINER SPECIFICATIONS.

3. A GEOTECHNICAL ENGINEER SHALL REVIEW AND APPROVE ALL POND LINER MATERIAL, PLACEMENT PROCEDURES, AND PROVIDE TESTING TO ENSURE THE POND LINER MATERIAL PLACED IS WATERTIGHT 4. STORM SEWER PIPES AND HEADWALLS THAT CONNECT TO A POND INTENDED TO HOLD WATER INDEFINITELY SHALL BE INSTALLED WITH WATERTIGHT JOINTS TO AT LEAST 1-FOOT ABOVE THE NORMAL POOL WATER SURFACE ELEVATION. 5. ANY GRAVEL OR OTHER PERVIOUS EMBEDMENT AROUND PIPES OR OUTFALL STRUCTURES NEAR THE POND SHALL BE ELIMINATED FOR AT LEAST 20-FEET FROM THE POND SO NO ROUTE FOR WATER TO LEAK THROUGH THE EMBEDMENT MATERIAL IS PROVIDED. BACKFILL

IN THESE AREAS SHALL BE OF IMPERVIOUS MATERIAL. 6. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE WATER LEVEL FOLLOWING COMPLETION AND FILLING OF THE POND SHALL BE MONITORED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO OBSERVE WATER INFLOW, OUTFLOW, AND CALCULATE EVAPORATION TO VERIFY THAT THE POND IS WATERTIGHT.

. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE POND WATER LEVEL SHALL ALSO BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION SO THAT IT REMAINS FULL TO ITS DESIGN WATER LEVEL, AND IS NOT LOWERED, AS THIS MAY DRY-OUT THE POND LINER AND RISK ITS WATERTIGHT PROPERTIES.

ALL WATER AND WASTEWATER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND

11. CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL WATER AND WASTEWATER LINES.

2. CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER AND WASTEWATER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY WATER OR WASTEWATER CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED. 3. CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITY SERVICES ENTERING THE BUILDING. 4. THE CONTRACTOR SHALL FIELD VERIFY THE ELEVATION OF ALL UTILITY CROSSINGS PRIOR TO THE INSTALLATION OF ANY PIPE 5. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE WATER AND WASTEWATER IMPROVEMENTS. 6. ALL PUBLIC WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS

STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS 7. ALL PRIVATE WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. FIRE SPRINKLER LINES SHALL BE DESIGNED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR, AND COMPLY TO THE APPLICABLE CODES AND INSPECTIONS REQUIRED. THESE PLANS WERE PREPARED WITHOUT THE BENEFIT OF THE FIRE SPRINKLER

DESIGN. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES. 9. EMBEDMENT FOR ALL WATER AND WASTEWATER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS 10. CONTRACTOR SHALL TAKE REQUIRED SANITARY PRECAUTIONS, FOLLOWING ANY CITY, TCEQ, AND AWWA STANDARDS, TO KEEP WATER PIPE AND FITTINGS CLEAN AND CAPPED AT TIMES WHEN INSTALLATION IS NOT IN PROGRESS.

12. ALL WATER AND WASTEWATER SERVICES SHALL TERMINATE 5-FEET OUTSIDE THE BUILDING, UNLESS NOTED OTHERWISE. 13. CONTRACTOR SHALL COMPLY WITH CITY REQUIREMENTS FOR WATER AND WASTEWATER SERVICE DISRUPTIONS AND THE AMOUNT OF PRIOR NOTICE THAT IS REQUIRED, AND SHALL COORDINATE DIRECTLY WITH THE APPROPRIATE CITY DEPARTMENT. 14. CONTRACTOR SHALL SEQUENCE WATER AND WASTEWATER CONSTRUCTION TO AVOID INTERRUPTION OF SERVICE TO SURROUNDING 15. CONTRACTOR SHALL MAINTAIN WATER SERVICE AND WASTEWATER SERVICE TO ALL CUSTOMERS THROUGHOUT CONSTRUCTION (IF

16.THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL WATER AND WASTEWATER LINES CROSSING THE PROJECT. THE CONTRACTOR SHALL REPAIR ALL DAMAGED LINES IMMEDIATELY. ALL REPAIRS OF EXISTING WATER MAINS, WATER SERVICES, SEWER MAINS, AND SANITARY SEWER SERVICES ARE SUBSIDIARY TO THE WORK, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 17. VALVE ADJUSTMENTS SHALL BE CONSTRUCTED SUCH THAT THE COVERS ARE AT FINISHED SURFACE GRADE OF THE PROPOSED

WORK SHALL BE CONSIDERED AS A SUBSIDIARY COST TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

NECESSARY, BY USE OF TEMPORARY METHODS APPROVED BY THE CITY AND OWNER). THIS WORK SHALL BE CONSIDERED

19. ALL FIRE HYDRANTS, VALVES, TEES, BENDS, WYES, REDUCERS, FITTINGS, AND ENDS SHALL BE MECHANICALLY RESTRAINED AND/OR THRUST BLOCKED TO CITY STANDARDS. 20.CONTRACTOR SHALL INSTALL A FULL SEGMENT OF WATER OR WASTEWATER PIPE CENTERED AT ALL UTILITY CROSSINGS SO THAT THE JOINTS ARE GREATER THAN 9-FEET FROM THE CROSSING. 21.ALL CROSSINGS AND LOCATIONS WHERE WASTEWATER IS LESS THAN 9-FEET FROM WATER, WASTEWATER CONSTRUCTION AND

MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 217.53. 22.ALL CROSSING AND LOCATIONS WHERE WATER IS LESS THAN 9-FEET FROM WASTEWATER, WATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 290.44

23.ALL WATER AND WASTEWATER SHALL BE TESTED IN ACCORDANCE WITH THE CITY, AWWA, AND TCEQ STANDARDS AND SPECIFICATIONS. AT A MINIMUM, THIS SHALL CONSIST OF THE FOLLOWING:

a. ALL WATERLINES SHALL BE HYDROSTATICALLY TESTED AND CHLORINATED BEFORE BEING PLACED INTO SERVICE. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. b. WASTEWATER LINES AND MANHOLES SHALL BE PRESSURE TESTED. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. AFTER COMPLETION OF THESE TESTS, A TELEVISION INSPECTION SHALL BE PERFORMED AND PROVIDED TO THE CITY AND OWNER ON A DVD. 24.CONTRACTOR SHALL INSTALL DETECTABLE WIRING OR MARKING TAPE A MINIMUM OF 12" ABOVE WATER AND WASTEWATER LINES.

SHALL COMPLY WITH CITY STANDARDS, AND SHALL BE INCLUDED IN THE COST OF THE WATER AND WASTEWATER PIPE. 25.DUCTILE IRON PIPE SHALL BE PROTECTED FROM CORROSION BY A LOW-DENSITY POLYETHYLENE LINER WRAP THAT IS AT LEAST A SINGLE LAYER OF 8-MIL. ALL DUCTHE IRON JOINTS SHALL BE BONDED. 26. WATERLINES SHALL BE INSTALLED AT NO LESS THAN THE MINIMUM COVER REQUIRED BY THE CITY. 27.CONTRACTOR SHALL PROVIDE CLEAN-OUTS FOR PRIVATE SANITARY SEWER LINES AT ALL CHANGES IN DIRECTION AND 100-FOOT INTERVALS, OR AS REQUIRED BY THE APPLICABLE PLUMBING CODE. CLEAN-OUTS REQUIRED IN PAVEMENT OR SIDEWALKS SHALL

MARKER DECALS SHALL BE LABELED "CAUTION - WATER LINE", OR "CAUTION - SEWER LINE". DETECTABLE WIRING AND MARKING TAPE

28.CONTRACTOR SHALL PROVIDE BACKWATER VALVES FOR PLUMBING FIXTURES AS REQUIRED BY THE APPLICABLE PLUMBING CODE (E.G. FLOOR ELEVATION OF FIXTURE UNIT IS BELOW THE ELEVATION OF THE MANHOLE COVER OF THE NEXT UPSTREAM MANHOLE IN THE PUBLIC SEWER). CONTRACTOR SHALL REVIEW BOTH MEP AND CIVIL PLANS TO CONFIRM WHERE THESE ARE REQUIRED. 29. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY

AMERICANS WITH DISABILITIES ACT AMERICAN WATER WORKS ASSOCIATION BACK TO BACK B-B **BEGIN CURVE** BACK OF CURB BEGIN CURB RETURN BEST MANAGEMENT PRACTICE BACK OF CURB BEGIN VERTICAL CURVE ELEVATION BEGIN VERTICAL CURVE STATION BOTTOM OF WALL CUBIC FEET PER SECOND CITY, TOWN, OR OTHER APPLICABLE LOCAL GOVERNMENT JURISDICTION CENTERLINE CENTERLINE CONCRETE CUBIC YARD DEMOLITION DECOMPOSED GRANITE EACH END CURVE END CURB RETURN **EXISTING GROUND ELEVATION** ELECTRICAL / ELECTRICITY ELEVATION UNITES STATES ENVIRONMENTAL PROTECTION AGENCY EASEMENT **EVCE** END VERTICAL CURVE ELEVATION EVCS END VERTICAL CURVE STATION **EXISTING** CROSS SLOPE EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPE EXCEED 5.0 PERCENT. ACCESSIBLE PARKING FACE TO FACE FINISHED GROUND FIRE HYDRANT FLOW LINE FACE OF CURB FFFT

HAVE CAST IRON COVERS FLUSH WITH FINISHED GRADE.

30.THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

HYDRAULIC GRADE LINE KIMLEY-HORN AND ASSOCIATES, INC KIMLEY-HORN AND ASSOCIATES, INC. LATERAL LINEAR FEET **MAXIMUM** 

MATCH EXISTING ELEVATION

NUMBER NOTICE OF INTENT, REF. TCEQ GENERAL PERMIT NOTICE OF TERMINATION, REF. TCEQ GENERAL PERMIT NOT TO SCALE ON CENTER

OFFSET OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION POINT OF CURVATURE PORTLAND CEMENT CONCRETE / POINT OF COMPOUND CURVATURE

PROPOSED GRADE LINE POINT OF INFLECTION PROPOSED POINT OF REVERSE CURVATURE POUNDS PER SQUARE INCH POINT OF TANGENCY

POLYVINYL CHLORIDE POINT OF VERTICAL INFLECTION PAVEMENT REINFORCED CONCRETE PIPE RIGHT OF WAY

RIGHT SQUARE FEET SANITARY SEWER SANITARY SEWER MANHOLE STANDARD

SQUARE YARD ARCHITECTURAL BARRIERS TEXAS ACCESSIBILITY STANDARDS TOP OF CURB TEXAS COMMISSION OF ENVIRONMENTAL QUALITY

**TEMPORARY** TEXAS DEPARTMENT OF TRANSPORTATION TXDOT TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES TOP OF WALL

TYPICAL VERTICAL CURVE WATER WASTEWATER

THESE PLAN AND GENERAL NOTES REFER TO GEOTECH REPORT: ECS SOUTHWEST, LLP ECS PROJECT #17:6232

MAY 12, 2023 INCLUDING ALL REVISIONS AND ADDENDA TO THIS REPORT THAT MAY HAVE BEEN RELEASED AFTER THE NOTED DATE

SHEET NUMBER

© COPYRIGHT 2017 KIMLEY-HORN AND ASSOCIATES, INC., ALL RIGHTS RESERVED

SUBSIDIARY TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

# **GENERAL NOTES**

ALL RESPONSIBILITY FOR THE ADEQUECY OF THESE PLANS REMAINS WITH THE ENGINEER. APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN DOES NOT REMOVE THESE RESPONSIBILITIES "REVIEWED BY AUSTIN WATER" APPLIES ONLY TO AW PUBLIC FACILITIES. ALL OTHER WATER AND WASTEWATER FACILITIES INSIDE PRIVATE PROPERTY ARE UNDER THE JURISDICATION OF BUILDING INSPECTIONS.

Use of Electronic Files General Disclaimer: Use of the attached files in any manner indicates your acceptance of terms and conditions as set forth below. If you do not agree to all of the terms and conditions, please contact Austin Water Pipeline Engineering, project coordinator prior to use of the referenced information. Please be advised that the attached files are in a format that can be altered by the user. Due to this fact, any reuse of the data will be at the user's sole risk without liability or legal exposure to The City of Austin and user shall indemnify and hold harmless The City of Austin from all claims, damages, losses and expenses including attorney's fees arising out of or resulting from using the digital file. In addition, it is the responsibility of the user to compare all data with the PDF version of this drawing. In the event there is a conflict between the PDF version drawing and the electronic file, the PDF version drawing shall prevail.

# **FIRE FLOW TEST DATA**




**AUSTIN FIRE DEPARTMENT** FIRE PREVENTION DIVISION 6310 Wilhelmina Delco Dr., Austin, Texas 78752 afd.hydrants@austintexas.gov



EST DATE	05/26/2023	3		FIRE BOX	3802	COMPANY	PREVENTION
TIME	1030 HRS			MAP GRID ID	E38	AFD STAFF	DECUIR, SCOTT
				RESIDUAI	L HYDRAN	[ <b>T</b>	
]	RESIDUAL I	HYDRANT#	57291	L		MAIN SIZE (in.)	12
BLI	K #	DIRECTION			STREET NAM	E	ТҮРЕ
117	700	N			FM 620		RD
STA	ATIC PRESS	URE (PSI)	82		RESID	OUAL PRESSURE (PSI)	80
					1		
				FLOW I	HYDRANT		
	FLOW I	HYDRANT#	56990	)		MAIN SIZE (in.)	12
BLI	K #	DIRECTION			STREET NAM	E	ТҮРЕ
117	700	N			FM 620		RD
S	TATIC PRES	SSURE (PSI)	84		RESI	DUAL PRESSURE (PSI)	74
					•		
omments						discharge coefficient traight 2½" butt = 0.9 w/ 45° elbow = 0.75	0.9
					FLOW	V RATE (GPM) =	1443

# FIRE FLOW MAP



Automated Metering Infrastructure: Effective March 2022, new water meters installed shall be in conformance with AW's automated metering infrastructure technology, and with the applicable standard product list. Applicants filing a site plan or subdivision plan will be required to coordinate with the Austin Water Plan Reviewer for details on approval and installation.

Prior to the handling and disposal of Asbestos Pipe, the Contractor's work plans will be reviewed and coordinated through Austin Water's Asbestos Program Manager who can be reached at 512-972-0915. It is the Contractor's responsibility to utilize a trained, certified and licensed Asbestos Abatement Contractor in accordance with the Federal, State and Local regulations.

Modifications to Austin Water signed and stamped sheets are not permitted. All design modifications will need to be submitted via the ABC portal for a Plan Correction or Revision. All unethical engineering practices, including modifying City Stamped plan sheets, shall be reported to the Texas Board of Professional Engineers and Land Surveyors (PELS).

Reference: Texas Engineering Practice Act and Rules, Subchapter C: Professional

# **Acknowledgement**

**Onsite Water Reuse & AW Reclaimed** Information

YES NO 🗙

**Automated Metering Information** 

Is this project within the current service area of AW's Data Collection Units (DCUs)?

NO X

Does this project require a dedicated easement for

YES

YES

IF YES, PLEASE PROVIDE UCC#\_\_\_

# **Additional Review**

Does this development have a total gross floor building area of 250,000 square feet or more?

Distance to nearest existing AW reclaimed main?

250' or less 251' to 500' Greater than 500'

DCU infrastructure?

AULCC Requirement

Does this project lie within the current service area of AW's Data Collection Units (DCUs)?

NO 🔀


# **SERVICE EXTENSION REQUESTS**

WATER SER NO. 5803

NOTE: SER-5803 IS CURRENTLY IN REVIEW AND WILL BE PROVIDED ONCE APPROVED.

> **PLACE WATER SER** (WITH MAP EXHIBIT)

# **WASTEWATER SER NO. 5531**



# PROJECT INFORMATION<sup>1</sup>

GRID NUMBER:	E38
MAPSCO NUMBER:	433K
AW INTERSECTION NUMBER:	16,120
BUILDING SIZE IN SQUARE FEET:	79,854
BUILDING TYPE PER IFC:	V-A
BUILDING HEIGHT:	3 STORIES
AVAILABLE FIRE FLOW CALCS AT 20 PSI:	9,223 GPM
REQUIRED BUILDING FIRE FLOW PER IFC TABLE B105.1(2):	5,000 GPM
REDUCED FIRE FLOW PER 75% FIRE SPRINKLER REDUCTION PER IFC TABLE B105.2:	1,500 GPM
MINIMUM FIRE FLOW (SEE NOTE #2 BELOW):	1,500 GPM
DOMESTIC WATER DEMAND IN GPM:	250 GPM
WATER SUPPLY FIXTURE UNITS (WSFUXFLUSH TANKS)OR FLUSHOMETERS (CIRCLE APPLICABLE ITEM):	1,334
AUSTIN WATER PRESSURE ZONE:	NORTHWEST B
STATIC WATER PRESSURE IN PSI:	82
STATIC PRESSURE AT THE HIGHEST LOT SERVED IN PSI:	82
STATIC PRESSURE AT THE LOWEST LOT SERVED IN PSI:	82
MAXIMUM IRRIGATION DEMAND:	142
FIRE LINE VELOCITY: 8"	9.57 FPS / 1500 GPM
DOMESTIC LINE VELOCITY: 8"	9.57 FPS / 1500 GPM
LIVING UNIT EQUIVALENTS (LUEs)	49

- 2. MIN FIRE FLOW: DESIGN ENGINEER MUST INDICATE VALUES WHICH COMPLY WITH IFC TABLES B105.1(2) OR B105.2 (REQUIRED OR REDUCED FIRE FLOWS). MIN FIRE FLOW VALUE SHALL BE NO LESS THAN 1000 GPM FOR NFPA 13
- 3. IF DEMAND, OTHER THAN MINIMUM FIRE FLOW, IS UTILIZED IN FIRE LINE VELOCITY DETERMINATION, ENGINEERING JUSTIFICATION SHALL BE SHOWN ON THIS SHEET WITH APPLICABLE DATA CALCULATIONS.

SYSTEMS OR 1500 GPM FOR NFPA 13R SYSTEMS (FOOTNOTES a and b FOR TABLE B105.2).

# **INSPECTION NOTES**

Please contact Development Services Department, Site and Subdivision Inspection at sitesubintake@austintexas.gov for arrangements for payment of Inspection fees and job assignment for Inspection of the public utilities to this site. Inspection fees must be paid before any Pre-construction meeting can be held.

STANDARD CONSTRUCTION NOTES October 1, 2021

- 1. THE CITY STANDARD CONSTRUCTION SPECIFICATIONS CURRENT AT THE TIME OF BIDDING SHALL COVER MATERIALS AND METHODS USED TO DO THIS WORK.
- CONTRACTOR MUST OBTAIN A R.O.W. PERMIT FROM AUSTIN TRANSPORTATION DEPT, RIGHT OF WAY MANAGEMENT DIVISION BEFORE BEGINNING CONSTRUCTION WITHIN THE RIGHT-OF-WAY OF A PUBLIC STREET OR ALLEY. ACTIVITY WITHIN RIGHT-OF-WAY SHALL COMPLY WITH APPROVED TCP.
- 3. AT LEAST 48 HOURS PRIOR TO BEGINNING ANY UTILITY CONSTRUCTION ACTIVITY IN PUBLIC R.O.W. OR PUBLIC EASEMENT, THE CONTRACTOR SHALL NOTIFY THE APPLICABLE CITY OF AUSTIN INSPECTION GROUP (AUSTIN TRANSPORTATION, DEVELOPMENT SERVICES, OR PUBLIC WORKS). SEE CURRENT NOTIFICATION REQUIREMENTS AT WWW.AUSTINTEXAS.GOV.
- THE CONTRACTOR SHALL CONTACT THE AUSTIN AREA "ONE CALL" SYSTEM AT 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS PRIOR TO ANY EXCAVATION IN ADVANCE OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES TO BE EXTENDED, TIED TO, OR ALTERED, OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS. THE CITY OF AUSTIN WATER AND WASTEWATER MAINTENANCE RESPONSIBILITY ENDS AT R.O.W./EASEMENT LINES.
- NO OTHER UTILITY SERVICE/APPURTENANCES SHALL BE PLACED NEAR THE PROPERTY LINE, OR OTHER ASSIGNED LOCATION DESIGNATED FOR WATER AND WASTEWATER UTILITY SERVICE THAT WOULD INTERFERE WITH THE WATER AND WASTEWATER SERVICES.
- MINIMUM TRENCH SAFETY MEASURES SHALL BE PROVIDED, AS REQUIRED BY OSHA, CITY SPECIFICATION 509S, AND CITY/COUNTY CONSTRUCTION INSPECTORS.
- ALL MATERIALS TESTS ORDERED BY THE OWNER FOR QUALITY ASSURANCE PURPOSES, SHALL BE CONDUCTED BY AN INDEPENDENT LABORATORY AND FUNDED BY THE OWNER IN ACCORDANCE WITH CITY STANDARD SPECIFICATION ITEM 1804S.04. PRESSURE TAPS SHALL BE ALLOWED ON A CASE BY CASE BASIS, AS DETERMINED BY THE DIRECTOR'S DESIGNEE. NORMALLY PRESSURE TAPS 4 INCHES AND LARGER SHALL BE ALLOWED IN
- THE FOLLOWING CASES: A) A TEST SHUT OUT INDICATES AN ADEQUATE SHUT OUT TO PERFORM THE WORK IS NOT FEASIBLE B) MORE THAN 30 CUSTOMERS OR A SINGLE CRITICAL CUSTOMER (AS DEFINED BY AUSTIN WATER) WOULD BE IMPACTED BY THE SHUT OUT OR C) THE EXISTING WATER LINE WARRANTS IT.
- WATER LINE TESTING AND STERILIZATION SHALL BE PERFORMED IN ACCORDANCE WITH CITY STANDARD SPECIFICATION ITEMS 510.3 (27)-(29). FORCE MAIN PRESSURE TESTING SHALL BE CONDUCTED AND FALL UNDER THE SPECIFICATIONS AS WATER LINES (PRESSURE PIPE) OR AT THE PRESSURES SHOWN ON THE APPROVED PLANS.
- 10. ALL MATERIAL USED ON THIS PROJECT MUST BE LISTED ON THE STANDARD PRODUCTS LISTING. ANY MATERIAL NOT LISTED HAS TO GO THROUGH THE REVIEW OF THE STANDARDS COMMITTEE FOR REVIEW AND APPROVAL PRIOR TO START OF PROJECT. TESTING AND EVALUATION OF PRODUCTS ARE REQUIRED BEFORE APPROVAL WILL BE GIVEN ANY CONSIDERATION 11. WHEN WATER SERVICES ARE DAMAGED AND THE SERVICE MATERIAL IS POLYETHYLENE (PE), THE LINE SHALL BE REPAIRED ONLY BY HEAT FUSION WELD, AT BRASS FITTINGS, OR THE FULL
- LENGTH SHALL BE REPLACED PER CURRENT STANDARD DETAIL(S). WHEN POLYBUTYLENE (PB) TUBING IS DAMAGED OR TAMPERED WITH IN ANY WAY, THE FULL LENGTH OF SERVICE LINE SHALL BE REPLACED. (NOTE: FULL LENGTH IS FROM THE CORPORATION STOP TO THE METER.) REPAIR COUPLINGS ARE NOT ALLOWED FOR ANY WATER OR WASTEWATER SERVICE LINE REPAIR, RECONNECT, OR REPLACEMENT.
- 12. WHEN AN EXISTING WATERLINE SHUT OUT IS NECESSARY AND POSSIBLE, THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTOR WHO WILL THEN NOTIFY AUSTIN WATER DISPATCH AND THE AFFECTED CUSTOMERS A MINIMUM OF FORTY-FIGHT (48) HOURS IN ADVANCE.
- 13. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTOR SO THAT HE CAN NOTIFY THE AUSTIN WATER AT 972-0000 AT A MINIMUM OF 72 HOURS PRIOR TO RELOCATING ANY DOMESTIC OR FIRE DEMAND WATER METERS. THE CONTRACTOR SHALL CAREFULLY REMOVE ALL METERS AND METERS BOXES THAT ARE INDICATED TO BE RELOCATED OR SALVAGED. THE CONTRACTOR SHALL INSTALL THE REMOVED METER OR CITY PROVIDED METER AT THE NEW LOCATION INDICATED ON THE CONSTRUCTION PLANS.

DRAWINGS SHALL INCLUDE THE FLOWLINE ELEVATIONS OF ALL CONNECTING PIPES; ELEVATIONS OF TRANSITIONS FROM LARGE DIAMETER SECTIONS TO 48" DIAMETER SECTIONS; TOP OF

- 14. THE CONTRACTOR SHALL VERIFY ALL VERTICAL AND HORIZONTAL LOCATIONS OF EXISTING UTILITIES, BELOW GROUND AND OVERHEAD, PRIOR TO STARTING ONSITE UTILITY WORK. 15. ALL WATER, WASTEWATER, AND RECLAIMED MAINS SHALL BE INSTALLED IN ACCORDANCE WITH THE SEPARATION DISTANCES INDICATED ON THE PLANS, PER UTILITY CRITERIA MANUAL
- **AND TCEQ CHAPTERS 210, 217, AND 290.** 16. PROJECT-SPECIFIC SHOP DRAWINGS SHALL BE SUBMITTED FOR AUSTIN WATER APPROVAL FOR PRE-CAST CIRCULAR VERTICAL MANHOLE SECTIONS LARGER THAN 48" DIAMETER. THE SHOP
- MANHOLE AND SURROUNDING GROUND ELEVATIONS; AND DETAILS OF SPECIAL CONSTRUCTION CONSIDERATIONS SPECIFIED IN THE CONTRACT DOCUMENTS. 17. WHEN CONCRETE MANHOLES LARGER THAN 48 INCH DIAMETER ARE USED, DRAWINGS THAT ARE SEALED BY A PROFESSIONAL ENGINEER SHALL BE SUBMITTED FOR BASE SLABS, FLAT TOP LIDS (IF USED), AND FLAT TYPE CONCRETE PIECES USED TO TRANSITION FROM LARGER TO SMALLER DIAMETER MANHOLE SECTIONS.
- 18. ALL FIRE HYDRANTS AND VALVES THAT ARE TO BE ABANDONED SHALL BE REMOVED, SALVAGED AND RETURNED TO AUSTIN WATER. NOTICE SHOULD BE GIVEN 48 HOURS PRIOR TO RETURN TO: PIPELINE OPERATIONS DISTRIBUTION SYSTEM MAINTENANCE, VALVES AND HYDRANT SERVICES, SUPERVISING AW PIPELINE TECHNICIAN AT 512-972-1133 19. ALL EXISTING WATER METERS IDENTIFIED TO BE RELOCATED OR ABANDONED AT THE DEVELOPMENT, SHALL BE REMOVED FROM THE METER BOX PRIOR TO CONSTRUCTION AND GIVEN
- IMMEDIATELY TO THE CITY OF AUSTIN INSPECTOR. 20. THE ENGINEER SHALL CALL OUT THE SIZE, TYPE AND USE (DOMESTIC OR IRRIGATION) OF ALL EXISTING WATER METERS TO BE RELOCATED OR REPURPOSED. WATER METER NUMBERS WILL NOT BE REQUIRED TO BE PLACED ON THE PLAN SHEET. A SEPARATE AUSTIN WATER TAPS OFFICE FORM WILL BE USED TO PROVIDE RELEVANT INFORMATION FOR THE EXISTING INFORMATION ON EXISTING METERS TO RECEIVE APPROPRIATE CREDITS. THIS FORM SHALL BE DIRECTLY SUBMITTED TO AUSTIN WATER TAPS OFFICE FOR REVIEW AND PROCESSING.
- 21. NO CONNECTION MAY BE MADE BETWEEN THE PRIVATE PLUMBING AND AUSTIN WATER INFRASTRUCTURE UNTIL A CITY APPROVED WATER METER HAS BEEN INSTALLED. 22. METER BOXES AND CLEAN OUTS SHALL NOT BE LOCATED WITHIN PAVED AREAS SUCH AS DRIVEWAYS AND SIDEWALKS.

**Meter Notice:** 

Meter 1.5 inches and larger must be purchased and ordered 90 days in advance of installation.

Meter(s) Requirement for Project: Address: 11723 N FM 620, AUSTIN, TX 78750

Type: COMPOUND

**Proposed Use: DOMESTIC POTABLE** 


GPM: 350 Service Units: 17.5

Address: 11723 N FM 620, AUSTIN, TX 78750


**Proposed Use: IRRIGATION POTABLE** Type: TURBINE, CLASS II

Size: 2" **GPM: 190** 


Service Units: 16.0



SHEET NUMBER



SP-2023-0252C.SH







LEGEND				
			PROPERTY LINE	
	LOC ——LOC ——		LIMITS OF CONSTRUCTION	
	XXX		EXISTING MAJOR CONTOUR	
	XXX		EXISTING MINOR CONTOUR	
	XXX		PROPOSED MAJOR CONTOUR	
	XXX		PROPOSED MINOR CONTOUR	
	CWQZ-		CRITICAL WATER QUALITY ZONE	
	\$F	SF	SILT FENCE	
		MS	MULCH SOCK	
		CE	CONSTRUCTION ENTRANCE	
		SA	STAGING AREA	
		CW	CONCRETE WASHOUT	
		(IP)	INLET PROTECTION	
	TP — TP —	TP	TREE PROTECTION	
		DS	DEWATERING SKIMMER	
	XXXXX		EXISTING TREE TO REMAIN	

# NOTES

- CONTRACTOR IS SOLELY RESPONSIBLE FOR IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
- 2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
- THE ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD AND/OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE TO KEEP PROJECT IN COMPLIANCE WITH THE CITY OF CEDAR PARK RULES AND REGULATIONS
- 4. CONTRACTOR SHALL UTILIZE DUST CONTROL MEASURES DURING SITE CONSTRUCTION SUCH AS IRRIGATION TRUCKS AND MULCHING AS PER ECM 1.4.5(D) OR AS DIRECTED BY THE ENVIRONMENTAL INSPECTOR.

5. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE

- INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
- 6. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE: SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
- ADDITIONAL EROSION AND SEDIMENTATION CONTROLS MAY BE REQUIRED BY THE CITY DURING CONSTRUCTION.
- 8. REFERENCE EROSION CONTROL NOTES ON SHEET 04 AND DETAILS ON SHEET 26.
- 9. IF DISTURBED AREA IS NOT TO BE WORKED ON FOR MORE THAN 14 DAYS, DISTURBED AREA NEEDS TO BE STABILIZED BY REVEGETATION, MULCH, TARP, OR REVEGETATION MATTING [ECM 1.4.4.B.3, SECTION 5, I.]. THE CONTRACTOR WILL CLEAN UP SPOILS THAT MIGRATE ONTO THE ROADS A MINIMUM OF ONCE DAILY [ECM 1.4.4.D.4].
- 10. ALL DISTURBED AREAS TO BE RE-VEGETATED PER CITY OF AUSTIN STANDARDS.
- 11. SEE LANDSCAPE ARCHITECT PLANS FOR TREE PRESERVATION PLAN AND TREE LIST.
- 12. PER LDC 25-8-323(C), FOR AREAS ON THE SITE THAT ARE TO REMAIN PERVIOUS AFTER DEVELOPMENT, ANY SOILS THAT ARE COMPACTED DURING SITE GRADING AND CONSTRUCTION MUST BE DE-COMPACTED IN COMPLIANCE WITH THE ECM AND IN COMPLIANCE WITH SSM 661S.
- FINISHED ELEVATION FOR PARKING LOT ISLANDS, MEDIANS, PENINSULAS, AND SIMILAR LANDSCAPE AREAS MUST BE AT LEAST SIX (6) INCHES BELOW THE FINISHED PARKING LOT ELEVATION TO ALLOW FOR PLACEMENT OF SIX (6) INCHES OF TOPSOIL [ECM 1.4.7].
   CONTRACTOR IS RESPONSIBLE FOR REMOVING ANY SEDIMENT TRANSPORTED FROM





**BENCHMARKS** 

IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740' SHE

SP-2023-0252C.SH

. 200, 791

10814 JOLLYVILLE ROAD, CAMPUS IV, SU AUSTIN TX 78759
PHONE: 512-418-1771 FAX: 512-418
WWW.KIMLEY-HORN.COM
© 2023 KIMLEY-HORN AND ASSOCIATE

JUSTIN J. KRAMER

122309

1/CENSE

2/2/2024

DATE
06/30/2023
SCALE: AS SHOWN
DESIGNED BY: JK/KM
DRAWN BY: SA/AM

ON CONTROL PLAN

EROS


SITE PLAN
11723 N FM 620
CITY OF AUSTIN
TRAVIS COUNTY, TEXAS


SITE 11723 CITY C


SHEET NUMBER


07

OF 25











SP-2023-0252C.SH





\*Runoff Coefficient ( C ) per City of Austin Drainage Criteria Manual; Runoff Coefficient C=Cperv\*(Aperv/Atotal)+Cimperv\*(Aimperv/Atotal): Rainfall Intensity I=a/(Tc+b)^c

\*\*Peak Flow Q = CIA

\*\*\*The minimum Tc is 6 minutes per the TR-55.







# LEGEND AREA DESIGNATOR 9.9 ac AREA IN ACRES Q100 FLOW IN CFS INLET NUMBER PROPERTY LINE CRITICAL WATER QUALITY ZONE EXISTING STORM DRAIN LINE PROPOSED DRAINAGE DIVIDE PROPOSED STORM DRAIN LINE PROPOSED STORM DRAIN INLET PROPOSED STORM DRAIN MANHOLE PROPOSED STORM DRAIN HEADWALL PROPOSED FLOW DIRECTION EXISTING MAJOR CONTOUR EXISTING MINOR CONTOUR PROPOSED MAJOR CONTOUR PROPOSED MINOR CONTOUR AUSTIN CITY LIMITS LANDSCAPE INLET CAPTURE

# NOTES

. RATIONAL METHOD DRAINAGE CALCULATIONS RELY ON CITY OF AUSTIN ATLAS-14

2. THE FLOW OFF THE SITE HAS NOT BEEN INCREASED FROM THE EXISTING CONDITION. 3. PROPOSED DEVELOPMENT DOES NOT ADVERSELY AFFECT ANY DOWNSTREAM






INLET DRAINAGE AREA MAP

SHEET NUMBER

BENCHMARKS IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'

VERIFY PRESENCE AND EXACT
LOCATION OF ALL UTILITIES

SP-2023-0252C.SH



Texas Commission on Environmental Quality TSS Removal Calculations 04-20-2009 Project Name: HTG Red Oaks Date Prepared: 11/8/2023 Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348. Characters shown in red are data entry fields. Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet. Calculations from RG-348 Pages 3-27 to 3-30 1. The Required Load Reduction for the total project: Page 3-29 Equation 3.3: L<sub>M</sub> = 27.2(A<sub>N</sub> x P) L<sub>M TOTAL PROJECT</sub> = Required TSS removal resulting from the proposed development = 80% of increased load A<sub>N</sub> = Net increase in impervious area for the project P = Average annual precipitation, inches Site Data: Determine Required Load Removal Based on the Entire Project Total project area included in plan \* = 3.57 acres

Predevelopment impervious area within the limits of the plan \* = 0.14 acres

Total post-development impervious cover fraction \* = 0.54

Total post-development impervious cover fraction \* = 0.54

Total post-development impervious cover fraction \* = 0.54

Total post-development impervious cover fraction \* = 0.54 L<sub>M TOTAL PROJECT</sub> = 1567 lbs. \* The values entered in these fields should be for the total project area. Number of drainage basins / outfalls areas leaving the plan area = 2. Drainage Basin Parameters (This information should be provided for each basin): Drainage Basin/Outfall Area No. = 1 Total drainage basin/outfall area = 3.40 acres Predevelopment impervious area within drainage basin/outfall area = 0.00 acres
Post-development impervious area within drainage basin/outfall area = 1.81 acres Post-development impervious fraction within drainage basin/outfall area = 0.53  $L_{M THIS BASIN} = 1575$  lbs. 3. Indicate the proposed BMP Code for this basin. Proposed BMP = Sand Filter Removal efficiency = 89 percent Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Grassy Swale Retention / Irrigation Stormceptor Vegetated Filter Strips Wet Basin Wet Vault 4. Calculate Maximum TSS Load Removed (L<sub>R</sub>) for this Drainage Basin by the selected BMP Type. RG-348 Page 3-33 Equation 3.7:  $L_R$  = (BMP efficiency) x P x (A<sub>1</sub> x 34.6 + A<sub>P</sub> x 0.54) A<sub>C</sub> = Total On-Site drainage area in the BMP catchment area A<sub>I</sub> = Impervious area proposed in the BMP catchment area A<sub>P</sub> = Pervious area remaining in the BMP catchment area L<sub>R</sub> = TSS Load removed from this catchment area by the proposed BMP A<sub>C</sub> = 3.40 acres A<sub>I</sub> = **1.81** acres A<sub>P</sub> = **1.59** acres L<sub>R</sub> = **1808** lbs 5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area Desired L<sub>M THIS BASIN</sub> = 1575 lbs. F = **0.87** 6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area. Calculations from RG-348 Pages 3-34 to 3-36 Rainfall Depth = 1.44 inches Post Development Runoff Coefficient = 0.38 On-site Water Quality Volume = 6682 cubic feet Calculations from RG-348 Pages 3-36 to 3-37 Off-site area draining to BMP = 0.00 acres Off-site Impervious cover draining to BMP = 0.00 acres Impervious fraction of off-site area = 0
Off-site Runoff Coefficient = 0.00 Off-site Water Quality Volume = 0 cubic feet Storage for Sediment = 1336 Total Capture Volume (required water quality volume(s) x 1.20) = 8019 cubic feet The following sections are used to calculate the required water quality volume(s) for the selected BMP. The values for BMP Types not selected in cell C45 will show NA. 7. Retention/Irrigation System Designed as Required in RG-348 Pages 3-42 to 3-46 Required Water Quality Volume for retention basin = NA cubic feet Irrigation Area Calculations: Soil infiltration/permeability rate = in/hr Enter determined permeability rate or assumed value of 0.1


Irrigation area = in/hr Enter determined permeability rate or assumed value of 0.1


NA square feet
NA acres Designed as Required in RG-348 8. Extended Detention Basin System Pages 3-46 to 3-51 Required Water Quality Volume for extended detention basin = NA cubic feet Pages 3-58 to 3-63 9. Filter area for Sand Filters Designed as Required in RG-348 9A. Full Sedimentation and Filtration System Water Quality Volume for sedimentation basin = 8019 cubic feet Maximum sedimentation basin area = 3341 square feet For minimum water depth of 2 feet
Minimum sedimentation basin area = 835 square feet For maximum water depth of 8 feet 9B. Partial Sedimentation and Filtration System Water Quality Volume for combined basins = 8019 cubic feet Minimum filter basin area = 668 square feet Maximum sedimentation basin area = 2673 square feet For minimum water depth of 2 feet Square feet For maximum water depth of 8 feet For maximum water depth of 8 feet

2/2/2024


TCEQ NOTES & CALCULATIONS

SHEET NUMBER






SP-2023-0252C.SH









LEGEND				
	PROPERTY LINE			
XXX	EXISTING MAJOR CONTOUR			
XXX	EXISTING MINOR CONTOUR			
XXX	PROPOSED MAJOR CONTOUR			
XXX	PROPOSED MINOR CONTOUR			
———— w ————	PROPOSED WATER LINE			
<b>+</b>	PROPOSED FIRE HYDRANT			
ww	PROPOSED WASTEWATER LINE			
(1)	PROPOSED WASTEWATER MANHOLE			
0	PROPOSED WASTEWATER CLEANOUT			
	PROPOSED STORM DRAIN LINE			
	PROPOSED STORM DRAIN INLET			
	EXISTING WATER LINE			
	EXISTING WASTEWATER LINE			
========	EXISTING STORM DRAIN LINE			
	EXISTING FIRE HYDRANT			
(W)	EXISTING WASTEWATER MANHOLE			

# NOTES

- 1. CONTRACTOR TO FIELD VERIFY LOCATION AND ELEVATION OF ALL EXISTING UTILITIES. 2. CONTRACTOR TO COORDINATE WITH MEP PLANS FOR ALL UTILITY STUB OUTS.
- 3. CONTRACTOR TO REFERENCE IRRIGATION PLANS BY LANDSCAPE ARCHITECT.
- 4. WATER SERVICE AND FIRE SERVICE LINES SHALL TERMINATE 5' FROM BUILDING. REFER
- TO MEP PLANS FOR CONTINUATION. 5. ALL MANHOLES LOCATED IN PAVEMENT ARE TO BE RAISED TO FINISHED GRADE.
- 6. ALL WATER AND WASTEWATER LINE CROSSINGS TO BE INSTALLED PER TCEQ REQUIREMENTS.
- 7. CONTRACTOR TO INSTALL FIRE SERVICE LINES IN ACCORDANCE WITH NFPA REQUIREMENTS.
- 8. ALL PVC LINES TO BE SDR-26







PUBLIC WATER PLAN & PROFILE


SHEET NUMBER 18


BENCHMARKS IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'

Know what's below.

Call before you dig.

WARNING: CONTRACTOR IS TO
VERIFY PRESENCE AND EXACT
LOCATION OF ALL UTILITIES
PRIOR TO CONSTRUCTION.







2+00

0+00

1+00








# NOTES

- 1. ALL DIMENSIONS ARE TO CENTERLINE OF PIPE UNLESS NOTED OTHERWISE.
- 2. CONTRACTOR TO FIELD VERIFY LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTACT ENGINEER IF FIELD CONDITIONS VARY.
- 3. SEE ARCHITECTURAL AND MEP PLANS FOR EXACT UTILITY TIE-IN AT BUILDING.
- 4. WASTEWATER SERVICE WILL BE PROVIDED BY THE CITY OF AUSTIN.
- 5. CONTRACTOR SHALL PROVIDE 48 HOUR NOTICE TO THE UTILITY PRIOR TO TESTING THE NEW WASTEWATER CONSTRUCTION AT (866) 654-7992.
- 6. PROPOSED WASTEWATER MANHOLES OUTSIDE OF PAVED AREAS REQUIRE BOLTED MANHOLE
- 7. MANDREL TO BE USED ON PVC PIPE SHOWING COMPLIANCE WITH 30 TAC §217.57(B) AND (C).



JUSTIN J. KRAMER


WASTEWATER PLAN & PROFILE


SHEET NUMBER


Know what's **below**. **Call** before you dig. WARNING: CONTRACTOR IS TO
VERIFY PRESENCE AND EXACT
LOCATION OF ALL UTILITIES
PRIOR TO CONSTRUCTION.


BENCHMARKS

IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'









# NOTES

- 1. ALL DIMENSIONS ARE TO CENTERLINE OF PIPE UNLESS NOTED OTHERWISE.
- 2. CONTRACTOR TO FIELD VERIFY LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTACT ENGINEER IF FIELD CONDITIONS VARY.
- WASTEWATER CONSTRUCTION AT (866) 654-7992.
- ADVANCE. ALL LANE CLOSURES SHALL TAKE PLACE BETWEEN THE HOURS OF 9:00 AM AND 3:00 PM.

- 3. CONTRACTOR SHALL PROVIDE 48 HOUR NOTICE TO THE UTILITY PRIOR TO TESTING THE NEW
- 4. ALL LANE CLOSURES SHALL BE COORDINATED WITH THE SITE INSPECTOR MINIMUM 48 HOURS IN

# 5. MANDREL TO BE USED ON PVC PIPE SHOWING COMPLIANCE WITH 30 TAC §217.57(B) AND (C).

# Know what's below. Call before you dig. WARNING: CONTRACTOR IS TO VERIFY PRESENCE AND EXACT LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.

IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'

SHEET NUMBER 21

JUSTIN J. KRAMER

 $\preceq$ 

SP-2023-0252C.SH

1025 1025 1020 1020 1015 1015 EXISTING GRADE\_ AT & PIPE 1010 1010 EXISTING 8" PVC (TO BE REMOVED) 1005 1005 197 LF OF 12" PVC @ 1.57% 1000 995 995

2+00

3+00

1+00

12" PVC EL SALIDO PARKWAY

OFFSITE WWL-A

STA: 2+96.79 OFFSITE WWL-A

990

4+00

EXISTING 6' MANHOLE (REF. SP-2020-0427C)

€ 8" IN (NW) 1005.20

€ 12" IN (W) 1005.30

€ 12" OUT (SE) 1005.00

₹ 6" IN (N) 1005.20

RIM: 1012.93

STA: 1+00 OFFSITE WWL-A

EXISTING MH #285142

€ 12" IN (NW) 1001.92

€ 12" OUT (NW) 1001.92

990


0+00


RIM: 1009.38


EBRIAR

OFFSITE WASTEWATER LINE 'A PLAN & PROFILE

BENCHMARKS









LEGEND				
	PROPERTY LINE			
XXX	EXISTING MAJOR CONTOUR			
	EXISTING MINOR CONTOUR			
XXX	PROPOSED MAJOR CONTOUR			
XXX	PROPOSED MINOR CONTOUR			
CWQZ-	CRITICAL WATER QUALITY ZONE			
	AUSTIN CITY LIMITS			
	PROPOSED WATER LINE			
- <del> -</del>	PROPOSED FIRE HYDRANT			
ww	PROPOSED WASTEWATER LINE			
(w)	PROPOSED WASTEWATER MANHOLE			
0	PROPOSED WASTEWATER CLEANOUT			
	PROPOSED STORM DRAIN LINE			
	PROPOSED STORM DRAIN INLET			
	EXISTING WATER LINE			
WW	EXISTING WASTEWATER LINE			
=======	EXISTING STORM DRAIN LINE			
	EXISTING FIRE HYDRANT			
(ii)	EXISTING WASTEWATER MANHOLE			

# NOTES


- 1. ALL DIMENSIONS ARE TO CENTERLINE OF PIPE UNLESS NOTED OTHERWISE.
- 2. CONTRACTOR TO FIELD VERIFY LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTACT ENGINEER IF FIELD CONDITIONS VARY.
- 3. CONTRACTOR SHALL PROVIDE 48 HOUR NOTICE TO THE UTILITY PRIOR TO TESTING THE NEW WASTEWATER CONSTRUCTION AT (866) 654-7992.
- ADVANCE. ALL LANE CLOSURES SHALL TAKE PLACE BETWEEN THE HOURS OF 9:00 AM AND 3:00 PM. 5. MANDREL TO BE USED ON PVC PIPE SHOWING COMPLIANCE WITH 30 TAC §217.57(B) AND (C).



4. ALL LANE CLOSURES SHALL BE COORDINATED WITH THE SITE INSPECTOR MINIMUM 48 HOURS IN


ā OFFSITE WASTEWATER LINE 'I PLAN & PROFILE


SHEET NUMBER 22





BENCHMARKS


IRFC ALUMCAP RPLS-5086 ELEVATION=102418' NORTHING=10138988.8950' EASTING=3087269.3740'







































JUSTIN J. KRAMER


2/2/2024


SP-2023-0252C.SH


SHEET NUMBER



























ALL CONCRETE SHALL BE CLASS "A"












JUSTIN J. KRAMER


122309


STORM & WATER QUALIT DETAILS


2/2/2024


SHEET NUMBER






































JUSTIN J. KRAMER

/2/2024

## **SECTION 5**

Temporary Storm Water Section (TCEQ-0602)

## **Temporary Stormwater Section**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

#### **Signature**

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

exe	ecutive director approval. The application was prepared by:
Prir	nt Name of Customer/Agent: Kyle Moore, P.E.
Dat	te: <u>02/02</u> /2024
Sign	nature of Customer/Agent:
7	L M
Reg	gulated Entity Name: HTG Red Oaks
Pr	roject Information
Po	otential Sources of Contamination
	amples: Fuel storage and use, chemical storage and use, use of asphaltic products, astruction vehicles tracking onto public roads, and existing solid waste.
1.	Fuels for construction equipment and hazardous substances which will be used during construction:
	☐ The following fuels and/or hazardous substances will be stored on the site:
	These fuels and/or hazardous substances will be stored in:
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
   Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- X Fuels and hazardous substances will not be stored on the site.
- 2. Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

#### Sequence of Construction

- 5. Attachment C Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: N/A

#### Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

		<ul> <li>A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.</li> <li>A description of how BMPs and measures will prevent pollution of surface water or</li> </ul>
		groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
		X A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
		A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	X	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
		Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
		There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	X	<b>Attachment F - Structural Practices</b> . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	X	<b>Attachment G - Drainage Area Map</b> . A drainage area map supporting the following requirements is attached:
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
		There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
- 11. Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.

X N/A

- 12. Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. X If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. X Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

#### Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. X Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. X Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

#### Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. X If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

# Attachment A Spill Response Actions

If there is an accidental spill on site, the contractor shall respond with appropriate action. The contractor will be required to contact the owner and in turn the owner will contact the TCEQ in the event of a spill on site. In addition to the following guidance, reference the latest version of TCEQ's Technical Guidance Manual (TGM) RG-348 Section 1.4.16.

#### Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

#### **Minor Spills**

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
- Contain the spread of the spill.
- Recover spilled materials.
- Clean the contaminated area and properly dispose of contaminated materials.

#### Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

#### Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at (512)339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.

Other agencies which may need to be consulted include, but not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

# Attachment B Potential Sources of Contamination

Examples of items and activities to be expected with the proposed development include saw cutting the existing asphalt, dripping petroleum-based fuels and fluids used in vehicles during driving, dirt from moving vehicles, and landscape debris such as grass and leaves. During construction, water quality could be affected by the runoff carrying sediments from the open construction area. Filter dike will be installed along the downstream portion of the installation. After construction, the site will be backfilled and repaved, and runoff will continue to follow the existing drainage patterns. No other industrial activity other than construction will occur.

# Attachment C Sequence of Major Activities

Major activities involved in the installation of the proposed improvements include first saw-cutting the pavement and excavating the fill above the existing pipe, followed by temporarily rerouting wastewater service and replacement of the existing pipe, and finished with the backfill and repaving of the installation area. Each activity in the construction sequence will disturb 0.071 acres for offsite segment A and 0.099 acres for offsite segment B. Triangular filter dike will be implemented for the duration of the installation process where necessary.

# Attachment D Temporary Best Management Practices and Measures

There is approximately 0.61 acres of storm water that originates up gradient from Offsite WWL-A and 2.01 acres from Offsite WWL-B that will flow across the sites or be routed around the sites. Triangular filter dike will be placed at the upstream side of each installation location that will prevent sediment from entering the utility trench and downstream to prevent sediment from the trench from continuing downstream. There are no surface streams or sensitive features in the area.


# Attachment E Request to Temporarily Seal a Feature

(Not applicable)

# Attachment F Structural Practices

No structural practices will be used to divert flows away from the exposed areas outside of typical erosion controls. Neither installation location is located within a floodplain.

# <u>Attachment G</u> Drainage Area Map



SP-2023-0252C.SH

# Attachment H Temporary Sediment Pond(s) Plans and Calculations

(Not applicable)

# Attachment I Inspection and Maintenance for BMPs

#### Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

#### Inspection Schedule

Option 1: Once every seven calendar days. If this alternative schedule is developed,

The primary operator is required to choose one of the two inspections listed below.

then the inspection must occur regardless of whether or not there has been a rainfall event since the previous inspection.

**Option 2:** Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).

If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded.

Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized;
- areas used for storage of materials that are exposed to precipitation;
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system);
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly); and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking).

#### **Reductions in Inspection Frequency**

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

#### **Inspection Report Forms**

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

#### **Corrective Action**

#### Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

#### **Corrective Action Forms**

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.

## Attachment J

# Schedule of Interim and Permanent Soil Stabilization Practices

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a) The dates when major grading activities occur;
- b) The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c) The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more that fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.

Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

#### Maintenance

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)
- Sediment must be removed from sediment traps and sedimentation ponds no later than the
  time that design capacity has been reduced by 50%. For perimeter controls such as silt
  fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the
  above-ground height.
- Silt fence will be inspected for depth of sediment, tears, to see of the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Straw bale dike will be inspected and repaired as necessary.
- Diversion dike will be inspected and any breaches promptly repaired.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes
  off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own
  or operate the off-site conveyance, then the permittee must to work with the owner or
  operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of storm water controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.

# **SECTION 6**

Agent Authorization Form (TCEQ-0599)

#### **Agent Authorization Form**

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

1	Matthew Rieger	
	Print Name	
	Manager	
	Title - Owner/President/Other	
of	HTG Anderson, LLC	
	Corporation/Partnership/Entity Name	
have authorized	Kyle Moore	
	Print Name of Agent/Engineer	
of	Kimley-Horn	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

#### I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

#### SIGNATURE PAGE:

Applicant's Signature

By: Matthew Rieger, Manager

7/14/2023 Date

THE STATE OF Florida §

County of \_\_\_Miami-Dade &

BEFORE ME, the undersigned authority, on this day personally appeared Nathres Recer known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 14 day of

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 1

Notary Public State of Florida Glenda Brown My Commission HH 274894 Exp. 6/12/2026

#### May 13, 2023

Myrna Rios, City Clerk City of Austin 301 W. Second St., Suite 2030 Austin, TX 78701

RE: Authorization Letter from Owner to Developer in order to apply for and obtain the necessary municipal approvals for the development of the property located at 11617 El Salido Pkwy, Austin Texas 78750, identified by Tax Parcel #R413803 (the "Property").

Dear City Clerk:

Magna Properties, LTD (the "Owner") hereby authorizes HTG Anderson, LLC (the "Developer"), its representatives, affiliates and/or consultants to act as agents on behalf of the Owner in connection with applying for and obtaining the necessary applications, agreements, approvals and other documents related to the development of a 70-unit multifamily affordable housing project called Red Oaks on the Property.

These may include, but not be limited to, applications for and related to site plan approvals, building permits, and other applications similar in nature, and executing various applications and agreements with public or provide utility providers, municipalities or other government authorities, related to obtaining a final building permit and/or permit ready letter for the development of the Property.

Sincerely,

MAGNA PROPERTIES, LTD

Printed Name: ELTAS SARKE

My Commission Expires:

My Commission Expires 3/24/2027 Notary ID 134269959

Typed, printed or stamped name of Notary Public

# **SECTION 7**

Application Fee Form (TCEQ-0574)

## **Application Fee Form**

Texas Commission on Environmental Quality  Name of Proposed Regulated Entity: Red Oaks (HTG Anderson, LLC)  Parallel 15 10 10 10 10 10 10 10 10 10 10 10 10 10								
Regulated Entity Location: <u>11723 N FM 620 Rd., Austin, TX 78750</u> Name of Customer: <u>HTG Anderson, LLC</u>								
Contact Person: Mauricio Teran Phone: 786-347-4554								
Customer Reference Number (if issued):CN								
Regulated Entity Reference Number (if issued):RN								
Austin Regional Office (3373)								
☐ Hays ☐ Travis	Xw	illiamson						
San Antonio Regional Office (3362)	_							
☐ Bexar ☐ Medina ☐ Kinney	U\	<i>r</i> alde						
Application fees must be paid by check, certified check	. or money order, payab	le to the <b>Texas</b>						
Commission on Environmental Quality. Your canceled								
form must be submitted with your fee payment. This	•	•						
X Austin Regional Office	San Antonio Regional O	Office						
Mailed to: TCEQ - Cashier	Overnight Delivery to: 1	CEQ - Cashier						
Revenues Section	12100 Park 35 Circle							
Mail Code 214	Building A, 3rd Floor							
P.O. Box 13088	Austin, TX 78753							
Austin, TX 78711-3088	(512)239-0357							
Site Location (Check All That Apply):								
X Recharge Zone Contributing Zon	e Transi	tion Zone						
Type of Plan	Size	Fee Due						
Water Pollution Abatement Plan, Contributing Zone								
Plan: One Single Family Residential Dwelling	Acres	\$						
Water Pollution Abatement Plan, Contributing Zone								
Plan: Multiple Single Family Residential and Parks	Acres	\$						
Water Pollution Abatement Plan, Contributing Zone	A	<u> </u>						
Plan: Non-residential	Acres 475 L.F.	\$ \$ 650						
Sewage Collection System  Lift Stations without sewer lines		Т						
Underground or Aboveground Storage Tank Facility	Acres Tanks	\$						
Piping System(s)(only)	Each	\$						
Exception	Each	\$						
Extension of Time	Each	\$						
Extension of Time	Lacii	7						
Signature: Matthew Rieger, Manager	te: <u>7/14/</u> 2023							

### **Application Fee Schedule**

**Texas Commission on Environmental Quality** 

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	<1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

	Cost per Linear	Minimum Fee-
Project	Foot	Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

## Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee				
Exception Request	\$500				

Extension of Time Requests

Project Project	Fee
Extension of Time Request	\$150

# **SECTION 8**

Core Data Form (TCEQ-10400)



## **TCEQ Core Data Form**

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

#### **SECTION I: General Information**

**1. Reason for Submission** (*If other is checked please describe in space provided.*)

New Pern	nit, Registra	ation or A	Authorization	(Core Data F	orm should b	be submitt	ted witi	the prog	ıram ap	plication.)			
Renewal	(Core Data	Form sho	ould be submit	tted with the	renewal fori	m)		Other					
2. Customer Reference Number (if issued)  Follow this link to search for CN or RN numbers in							ssued)						
CN	Control Donishu.**												
SECTIO	N II:	Cus	tomer	Infor	<u>matio</u>	<u>n</u>							
4. General Cu	ustomer Ir	nformat	tion	5. Effecti	ve Date for	Custome	er Info	rmation	Updat	es (mm/dd	/уууу)		
New Custon	mer		Πυ	pdate to Cus	stomer Inforr	mation		Char	nge in R	egulated Er	tity Own	ership	
Change in L		(Verifiab		-			nptrolle		•	•	,		
The Custome	r Name sı	ıbmitte	d here may l	be updated	l automatic	cally base	ed on 1	what is c	urrent	and active	with th	ne Texas Sec	retary of State
(SOS) or Text	as Comptr	oller of	Public Accou	ınts (CPA).									
6. Customer	Legal Nan	ne (If an	individual, pri	nt last name	first: eg: Doe	e, John)			<u>If new</u>	Customer,	enter pre	evious Custom	er below:
HTG Anderson	LLC												
7. TX SOS/CP	A Filing N	umber		8. TX Stat	te Tax ID (1:	1 digits)			9. Federal Tax ID 10. DU				Number (if
											applicable)	applicable)	
0804305476				32081837422				(9 digits)					
									87-43	884755			
11. Type of C	ustomer:			tion				Individ	lual		Partne	rship: 🗌 Gen	eral 🗌 Limited
Government: [	City 🔲	County	Federal 🗌	Local 🗌 St	ate 🗌 Other	r		Sole P	roprieto	rship	Otl	ner:	
12. Number	of Employ	ees							13. lı	ndepende	ntly Ow	ned and Ope	erated?
□ 0-20 □ :	21-100	101-2	50 🗌 251-	500 🗌 50	01 and highe	r			⊠ Ye	es	☐ No		
14. Custome	r Role (Pro	posed or	r Actual) – <i>as i</i>	t relates to t	he Regulatea	d Entity list	ted on	this form.	Please (	check one o	f the follo	owing	
⊠Owner ☐Occupation	al Licensee		erator esponsible Pa		Owner & Ope					Other			
15. Mailing	3225 Avi	ation Ave	enue										
Address:						4741							
16. Country I	Mailing In	formati	<b>on</b> (if outside	USA)		1	17.	E-Mail A	ddress	(if applicab	le)		
							mauı	riciot@htg	gf.com				
18. Telephon	e Numbe	r			19. Exten	sion or C	ode			20. Fax N	lumber	(if applicable)	

TCEQ-10400 (11/22) Page 1 of 3

( 786 ) 347-4554		( ) -	
------------------	--	-------	--

### **SECTION III: Regulated Entity Information**

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)									
New Regulated Entity  Update to Regulated Entity Name  Update to Regulated Entity Information									
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).									
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)									
HTG Red Oaks									
23. Street Address of the Regulated Entity:	11723 N FM 620 Rd.								
(No PO Boxes)	City	Austin	State	TX	ZIP	7875	0	ZIP + 4	1348
24. County	Williamson								
If no Street Address is provided, fields 25-28 are required.									
25. Description to									
Physical Location:									
26. Nearest City	City State Nearest ZIP Code								
Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).									
27. Latitude (N) In Decima	al:	30.456613		28. L	ongitude (\	W) In De	ecimal:	-97.82261	1
Degrees	Minutes		Seconds	Degre	Degrees		Minutes		Seconds
29. Primary SIC Code (4 digits)	30. Secondary SIC ( (4 digits)		Code	31. Primary NAICS (5 or 6 digits)		ode	32. Secondary NAICS Code (5 or 6 digits)		S Code
6500									
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)									
Land development									
Land development									
	3225 Aviat	ion Avenue							
34. Mailing	3225 Aviat	ion Avenue							
	3225 Aviat	ion Avenue  Coconut Grove	e State	FL	ZIP	3313	3	ZIP + 4	4741
34. Mailing	City	1		FL	ZIP	3313	3	ZIP + 4	4741
34. Mailing Address:	City	Coconut Grove					3 nber (if applical		4741
34. Mailing Address: 35. E-Mail Address:	City	Coconut Grove							4741

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	Districts	Edwards Aquifer	Emissions Inventory Air	☐ Industrial Hazardous Waste			
Municipal Solid Waste	New Source Review Air	OSSF	Petroleum Storage Tank	□ PWS			
Sludge	Storm Water	☐ Title V Air	Tires	Used Oil			
☐ Voluntary Cleanup	☐ Wastewater	☐ Wastewater Agriculture	☐ Water Rights	Other:			
SECTION IV: Preparer Information							
4 70							

40. Name:	Kyle Moore, P.E.			41. Title:	Civil Engineer
42. Telephone Number		43. Ext./Code	44. Fax Number	45. E-Mail Address	
(512)489-6376	i	N/A	( ) -	kyle.moore@	Dkimley-horn.com

#### **SECTION V: Authorized Signature**

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Kimley-Horn and Associates Inc Job Title: Civil Engine			eer		
Name (In Print):	Kyle Moore, P.E.				(512)489- <b>6376</b>	
Signature:				Date:	7/18/2023	

TCEQ-10400 (11/22) Page 3 of 3