## **Texas Commission on Environmental Quality**

# **Edwards Aquifer Application Cover Page**

### **Our Review of Your Application**

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

#### **Administrative Review**

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
  - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <a href="http://www.tceq.texas.gov/field/eapp">http://www.tceq.texas.gov/field/eapp</a>.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
  - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### **Technical Review**

- When an application is deemed administratively complete, the technical review period begins. The regional
  office will distribute copies of the application to the identified affected city, county, and groundwater
  conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
  to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### **Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Liberty Hill MF Development			2. Regulated Entity No.:					
3. Customer Name: OP III ATX LIBERTY HILL 183 LP			4. Customer No.:					
5. Project Type: (Please circle/check one)	New	Modif	ication	1	Exter	nsion	Exception	
6. Plan Type: (Please circle/check one)	WPAP CZP	scs	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential	Non-r	Non-residential 8. Site			8. Sit	te (acres):	12.638
9. Application Fee:	\$6,500	10. P	10. Permanent BMP(s):			s):	Batch Detention	on Pond
11. SCS (Linear Ft.):		12. AST/UST (No. Tanks):			ıks):			
13. County:	Williamson	n 14. Watershed:			_	South Fork Sa	n Gabriel River	

# **Application Distribution**

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field\_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region				
County:	Hays	Travis	Williamson	
Original (1 req.)			_	
Region (1 req.)	_	_		
County(ies)				
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA	
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrellLeander X_Liberty HillPflugervilleRound Rock	

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)			_		
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the a application is hereby submitted to TCEQ for admin	application is complete and accurate. This istrative review and technical review.
Bilal Alizai, P.E.	
Print Name of Customer/Authorized Agent	
Frill Alizi	05-07-2024
Signature of Customer/Authorized Agent	Date

**FOR TCEQ INTERNAL USE ONLY**				
Date(s)Reviewed:	Date Ad	ministratively Complete:		
Received From:	Correct	Correct Number of Copies:		
Received By:	Distribu	ntion Date:		
EAPP File Number:	Complex	x:		
Admin. Review(s) (No.):	No. AR	No. AR Rounds:		
Delinquent Fees (Y/N):	Review '	Time Spent:		
Lat./Long. Verified:	SOS Cus	stomer Verification:		
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):		
Core Data Form Complete (Y/N):	Check:	Signed (Y/N):		
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):		

# **Contributing Zone Plan Application**

### **Texas Commission on Environmental Quality**

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

# Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Bilal Alizai, P.E.

Date: 05-07-2024

Signature of Customer/Agent: Thill Him

Regulated Entity Name: Liberty Hill MF Development

# **Project Information**

1. County: Williamson

2. Stream Basin: Brazos River Basin

3. Groundwater Conservation District (if applicable): N/A

4. Customer (Applicant):

Contact Person: Collin Aufhammer
Entity: OP III ATX LIBERTY HILL 183 LP
Mailing Address: 500 W 5TH St, Ste 700

Email Address: caufhammer@endeavor-re.com

5.	Agent/Representative (If any):
	Contact Person: Bilal Alizai  Entity: GarzaEMC  Mailing Address: 9106 Wheat Cross Dr  City, State: Houston, TX Zip: 77095  Telephone: 713-491-6039 Fax:  Email Address: balizai@garzaemc.com
6.	Project Location:
	<ul> <li>The project site is located inside the city limits of <u>Liberty Hill</u></li> <li>The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of</li> <li>The project site is not located within any city's limits or ETJ.</li> </ul>
7.	The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.  250 Gracie Ln, Liberty Hill, TX 78642  S13297 - GUNNER NE MULTI-FAMILY SUB, BLOCK A, Lot 1B, ACRES 12.638
8.	X Attachment A - Road Map. A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
9.	X Attachment B - USGS Quadrangle Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:
	<ul><li>X Project site boundaries.</li><li>X USGS Quadrangle Name(s).</li></ul>
10.	Attachment C - Project Narrative. A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:
	<ul> <li>Area of the site</li> <li>Offsite areas</li> <li>Impervious cover</li> <li>Permanent BMP(s)</li> <li>Proposed site use</li> <li>Site history</li> <li>Previous development</li> <li>Area(s) to be demolished</li> </ul>
11.	Existing project site conditions are noted below:
	Existing commercial site Existing industrial site Existing residential site

Undeveloped (Cl	nd/or unpaved roads leared) ndisturbed/Not cleared)			
12. The type of project i	s:			
	Residential: # of Lots:  X Residential: # of Living Unit Equivalents: _224  Commercial Industrial			
13. Total project area (s	ize of site): <u>12.638</u> Acres			
Total disturbed area	: <u>12.638</u> Acres			
14. Estimated projected	population: 456			
15. The amount and typ below:	e of impervious cover ex	pected after construction	on is complete is shown	
Table 4 Income decide	Cover			
Table 1 - Impervious	Covei			
Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres	
Impervious Cover of		<b>Sq. Ft./Acre</b> ÷ 43,560 =	<b>Acres</b> 2.336	
Impervious Cover of Proposed Project	Sq. Ft.	*		
Impervious Cover of Proposed Project Structures/Rooftops	<b>Sq. Ft.</b> 101,770	÷ 43,560 =	2.336	
Impervious Cover of Proposed Project Structures/Rooftops Parking	<b>Sq. Ft.</b> 101,770 77,598	÷ 43,560 = ÷ 43,560 =	2.336 1.781	
Impervious Cover of Proposed Project  Structures/Rooftops Parking Other paved surfaces Total Impervious Cover  Total Impervious Cover  16. X Attachment D - factors that coul location and desconstruction.	<b>Sq. Ft.</b> 101,770 77,598 121,756	÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  2.638 X 100 = 54.7 % In  e Water Quality. A deta hality is attached. If app hassociated with industr	2.336 1.781 2.795 6.913  hpervious Cover iled description of all licable, this includes the ial activity other than	
Impervious Cover of Proposed Project  Structures/Rooftops Parking Other paved surfaces Total Impervious Cover  Total Impervious Cover  16. X Attachment D - factors that coul location and desconstruction.	Sq. Ft.  101,770  77,598  121,756  301,124  Factors Affecting Surface d affect surface water queription of any discharge rials as defined by 30 TAC	÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  ÷ 43,560 =  2.638 X 100 = 54.7 % In  e Water Quality. A deta hality is attached. If app hassociated with industr	2.336 1.781 2.795 6.913  hpervious Cover iled description of all licable, this includes the ial activity other than	

□ N/A

18. Type of project:
<ul> <li>TXDOT road project.</li> <li>County road or roads built to county specifications.</li> <li>City thoroughfare or roads to be dedicated to a municipality.</li> <li>Street or road providing access to private driveways.</li> </ul>
19. Type of pavement or road surface to be used:
Concrete Asphaltic concrete pavement Other:
20. Right of Way (R.O.W.):
Length of R.O.W.: feet. Width of R.O.W.: feet. $L \times W = $ $Ft^2 \div 43,560 Ft^2/Acre = acres.$
21. Pavement Area:
Length of pavement area: feet.  Width of pavement area: feet.  L x W = Ft <sup>2</sup> ÷ 43,560 Ft <sup>2</sup> /Acre = acres.  Pavement area acres ÷ R.O.W. area acres x 100 = % impervious cover.
22. A rest stop will be included in this project.
A rest stop will not be included in this project.
23. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.
Stormwater to be generated by the Proposed Project
24. X Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.
Wastewater to be generated by the Proposed Project
25. X Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.  N/A

26. Wastewater will be	disposed of by:		
On-Site Sewage	Facility (OSSF/Septic Tar	nk):	
will be used licensing authe land is sthe requirer relating to C Each lot in the size. The sy	to treat and dispose of thority's (authorized age uitable for the use of priments for on-site sewage Pacilities. his project/development stem will be designed by	m Authorized Agent. And the wastewater from this nt) written approval is at vate sewage facilities and facilities as specified under its at least one (1) acre (4) a licensed professional of the linstaller in compliance was the waste of the line waste of the li	site. The appropriate tached. It states that d will meet or exceed der 30 TAC Chapter 285
	on system will convey th	: Liberty Hill Wastewater Tr e wastewater to the	
X Existing. Proposed.			
☐ N/A			
Permanent Ab Gallons	oveground Sto	rage Tanks( <b>AST</b>	s) ≥ 500
Complete questions 27 greater than or equal t		des the installation of AS	T(s) with volume(s)
XN/A			
27. Tanks and substance	e stored:		
Table 2 - Tanks and	Substance Storage		
AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1			
2			
3			
4			
5			
	•	<b>Tot</b> nent structure that is size ity of the system. For fac	•

5 of 11

•	stem, the containm umulative storage c		ed to capture one and	d one-half (1 1/2)	
for providir		nment are proposed	ent Methods. Alternd. Specifications sho		
29. Inside dimensi	ons and capacity of	containment structu	ure(s):		
Table 3 - Second	dary Containment	t .			
Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons	
			То	tal: Gallons	
Some of the structure.  The piping The piping of the piping of the piping of the contain substance (state of the contain substance).	e piping to dispense will be aboveground will be underground nment area must be s) being stored. The	ers or equipment wild d constructed of and e proposed containn	ings. A scaled drawi	containment vious to the e constructed of:	
32. Attachment H - AST Containment Structure Drawings. A scaled drawing of the containment structure is attached that shows the following:					
<ul> <li>Interior dimensions (length, width, depth and wall and floor thickness).</li> <li>Internal drainage to a point convenient for the collection of any spillage.</li> <li>Tanks clearly labeled</li> <li>Piping clearly labeled</li> <li>Dispenser clearly labeled</li> </ul>					
33. Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.					
<u></u>		pillage will be remo	ved from the contain	nment structure	

through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.
Site Plan Requirements
tems 34 - 46 must be included on the Site Plan.
34. $\boxed{X}$ The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = 40 '.
35. 100-year floodplain boundaries:
<ul> <li>Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.</li> <li>No part of the project site is located within the 100-year floodplain.</li> <li>The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA_FIRM 48491C0275E eff. 9/25/2008</li> </ul>
36. X The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. $\boxed{X}$ A drainage plan showing all paths of drainage from the site to surface streams.
38. $\overline{X}$ The drainage patterns and approximate slopes anticipated after major grading activities.
39. X Areas of soil disturbance and areas which will not be disturbed.
40. X Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
11. X Locations where soil stabilization practices are expected to occur.
42. Surface waters (including wetlands).
X N/A
13. Locations where stormwater discharges to surface water.
X There will be no discharges to surface water.
14. Temporary aboveground storage tank facilities.
X Temporary aboveground storage tank facilities will not be located on this site.

45. Permanent aboveground storage tank facilities.	
X Permanent aboveground storage tank facilities will not be lo	cated on this site.
46. 🗶 Legal boundaries of the site are shown.	
Permanent Best Management Practices (E	BMPs)
Practices and measures that will be used during and after construc	ction is completed.
47. X Permanent BMPs and measures must be implemented to co pollution from regulated activities after the completion of co	_
□ N/A	
48. X These practices and measures have been designed, and will and maintained to insure that 80% of the incremental increasional loading of total suspended solids (TSS) from the site caused removed. These quantities have been calculated in accorda prepared or accepted by the executive director.	ase in the annual mass by the regulated activity is
<ul> <li>The TCEQ Technical Guidance Manual (TGM) was used to and measures for this site.</li> <li>A technical guidance other than the TCEQ TGM was used and measures for this site. The complete citation for the was used is:</li> </ul>	I to design permanent BMPs
□ N/A	
49. X Owners must insure that permanent BMPs and measures are as designed. A Texas Licensed Professional Engineer must constructed as designed must be submitted to the appropriate regional office within N/A	ertify in writing that the d. The certification letter
<b>—</b> ·	
50. Where a site is used for low density single-family residential develess impervious cover, other permanent BMPs are not required, permanent BMPs must be recorded in the county deed records, percent impervious cover increases above 20% or land use chan whole site as described in the property boundaries required by Application Processing and Approval), may no longer apply and notify the appropriate regional office of these changes.	This exemption from with a notice that if the ges, the exemption for the 30 TAC §213.4(g) (relating to
<ul> <li>The site will be used for low density single-family residen 20% or less impervious cover.</li> <li>The site will be used for low density single-family residen more than 20% impervious cover.</li> </ul>	·
The site will not be used for low density single-family resi	dential development.

far im red ind the an	e executive director may waive the requirement for other permanent BMPs for multimily residential developments, schools, or small business sites where 20% or less pervious cover is used at the site. This exemption from permanent BMPs must be corded in the county deed records, with a notice that if the percent impervious cover creases above 20% or land use changes, the exemption for the whole site as described in a property boundaries required by 30 TAC §213.4(g) (relating to Application Processing d Approval), may no longer apply and the property owner must notify the appropriate gional office of these changes.
	<ul> <li>Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.</li> <li>X The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.</li> <li>The site will not be used for multi-family residential developments, schools, or small</li> </ul>
52 <b>Y</b>	business sites.  Attachment J - BMPs for Upgradient Stormwater.
J2. <u>                                    </u>	A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.  X No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.  Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
53. X	Attachment K - BMPs for On-site Stormwater.
	<ul> <li>A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.</li> <li>Permanent BMPs or measures are not required to prevent pollution of surface wate or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.</li> </ul>
54.	Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.
X	] N/A
55. X	Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

		attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.
		N/A
56.	X	<b>Attachment N - Inspection, Maintenance, Repair and Retrofit Plan</b> . A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
		<ul> <li>Prepared and certified by the engineer designing the permanent BMPs and measures</li> <li>Signed by the owner or responsible party</li> <li>Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.</li> <li>Contains a discussion of record keeping procedures</li> </ul>
		N/A
57.		<b>Attachment O - Pilot-Scale Field Testing Plan</b> . Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
	X	N/A
58.	X	Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
		N/A
	-	oonsibility for Maintenance of Permanent BMPs and sures after Construction is Complete.
59.	X	The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or

60. X A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a

multiple single-family residential development, a multi-family residential development,

ownership is transferred.

or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### Administrative Information

- 61. X Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. X Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
  - X The Temporary Stormwater Section (TCEQ-0602) is included with the application.

# **Temporary Stormwater Section**

### **Texas Commission on Environmental Quality**

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

# Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Regulated Entity Name: Liberty Hill MF Development	
Signature of Customer/Agent: Thill Alixi	
Cignature of Customer/Agents 3 1/ A 4/ 5	
Date: <u>05-07</u> -2024	
Print Name of Customer/Agent: Bilal Alizai, P.E.	

# **Project Information**

## **Potential Sources of Contamination**

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used durin construction:				
	The following fuels and/or hazardous substances will be stored on the site:			
	These fuels and/or hazardous substances will be stored in:			
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.			

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
   Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2. X Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. X Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. X Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

# Sequence of Construction

- 5. Attachment C Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - X For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - X For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. X Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: South Fork San Gabriel River

# Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. X Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

		X A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
		<ul> <li>A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.</li> </ul>
		A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
		X A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	X	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
		Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
		X There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	X	<b>Attachment F - Structural Practices</b> . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	X	<b>Attachment G - Drainage Area Map</b> . A drainage area map supporting the following requirements is attached:
		<ul><li>For areas that will have more than 10 acres within a common drainage area</li><li>disturbed at one time, a sediment basin will be provided.</li></ul>
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
		There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
   Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary
- Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
  - X N/A
- 12. X Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. X If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. X Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. X Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

### Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. X Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. X Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. X Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### Administrative Information

- 20. X All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. X If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. X Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



# **Liberty Hill MF Development**

250 Gracie Ln Liberty Hill, TX, Williamson County

# **Contributing Zone Plan**

Prepared by:

### GARZA EMC, LLC.

7708 Rialto Blvd., Suite 125 Austin, Texas 78735 TBPE Registration No. F-14629



# **ATTACHMENTS FOR CONTRIBUTING ZONE APPLICATION**

**ATTACHMENT A: ROAD & SITE LOCATION MAP** 







**ATTACHMENT B: USGS QUADRANGLE MAP** 










PV

PU

Grid Zone Designation



This map was produced to conform with the National Geospatial Program US Topo Product Standard.





2022

### ATTACHMENT C: PROJECT NARRATIVE

The proposed site is 12.638 acres, located at 250 Gracie Ln, Liberty Hill, Williamson County, Texas. The entire limits of the site are within the Edwards Aquifer Contributing Zone. The existing site has no impervious cover while 55% impervious cover is proposed. The proposed development consists of five garden style multifamily apartment buildings with an amenity center. Each building will be four floors. In total, there will be 320 units.

The existing site consists of undeveloped property. Proposed construction consists of earthwork, storm water management controls (a batch detention pond), and related construction. The site erosion control measures will be in effect accordingly and are described in more detail elsewhere in the construction plans.

The majority of the site will be disturbed for the construction of the buildings, parking lot, and associated stormwater facilities.

The project will not involve rerouting, filling, or crossing a waterway of any kind. Onsite stormwater will be conveyed through a stormsewer system to the batch detention pond. Storm water will be discharged into the water quality basin of the pond where it will sit for 12 hours until the controller valve releases it to the outfall junction box which then conveys it to the neighboring drainage channel. An overflow weir at the water quality elevation will allow water to spill into the detention basin during large storm events once the full water quality volume of the water quality basin has been fulfilled. The detention volume will be discharged through an outlet structure designed to keep developed releases equal to existing flow. Pond effluent will be released toward the southeast corner of the site into the neighboring drainage channel. The detention pond has been sized to provide 1.60 feet of freeboard during the 100-year storm event.

The subject property is located at the top of the watershed, with Gracie Ln along the entire upstream segment of the site. The natural drainage pattern is from the West (Gracie Ln) to the East. The property to the north is an undeveloped lot whose drainage will be routed around the subject parcel through the use of a temporary swale until the lot is developed. The lot to the south is an undeveloped lot planned to be a multi-family development in the future. Gracie Ln borders the site on the west. The eastern boundary of the property is an open drainage channel routing drainage south toward the South Fork San Gabriel River.

### ATTACHMENT D: FACTORS AFFECTING SURFACE WATER QUALITY

Potential sources of sediment to stormwater runoff include:



• Clearing, grading, and excavating activities, primarily un-stabilized areas; paving operations, demolition and debris disposal; dewatering operations, drilling, material delivery, storage and use and landscaping operations.

Potential pollutants other than sediment include the following materials and substances that could be expected to be present on-site:

- Heavy Metals from material delivery, storage and use, and hazardous substance/waste spills
- Trash, Debris and Solids from clearing and grading, paving, concrete wash waste, construction painting and cleaning, demolition, drilling and blasting, material delivery storage and use, landscaping, and general construction
- Petroleum Based Products vehicle and equipment use on site.
- Pesticides/Herbicides from material delivery, storage and use, hazardous waste spills, vehicle use, storage, service and maintenance
- Fertilizers/Nutrients from painting, cleaning products, dewatering, material delivery and storage, spills during landscaping operation

Potential sources of post construction stormwater runoff include:

- Sediment coarse and fine from vehicle and equipment use on site.
- Heavy Metals dissolved and particulate from vehicle washing activities
- Petroleum Based Products from hazardous material spills, vehicle and equipment use on site.

## ATTACHMENT E: VOLUME AND CHARACTER OF STORMWATER

The existing site consists of undeveloped land. Proposed construction consists of earthwork, storm water management controls, and related construction to build the permanent BMP (batch detention pond). The site erosion control measures will be in effect accordingly and are described in more detail elsewhere in the construction plans.

The surface soils, according to the USDA/Natural Resources Conservation Service's Soil Survey for Williamson County, in the local area are mapped as belonging mainly of Denton silty clay and Doss silty clay; both within soil hydrologic group 'D'. These are consistent with a visual inspection of the site.

The proposed impervious cover will be treated by an engineered batch detention pond designed to fulfill the water quality requirements of the Edward Aquifer Protection plan. The TCEQ Technical Guidance Manual RG-348 and "TSS Removal Calculations 04-20-2009" worksheet was utilized to design the water quality feature. These practices and measures have been designed, and will be



constructed, operated, and maintained to ensure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. The pond has been designed to treat 55% impervious cover in order to accommodate for the full buildout. Following is a summary of the TCEQ worksheet calculations for this site:

BATCH DETENTION POND WORKSHEET:



#### TSS Removal Calculations 04-20-2009

**Project Name: Liberty Hill MF Development** 

Date Prepared: 04.26.2024

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348. Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

#### 1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3:  $L_{M} = 27.2(A_{N} \times P)$ 

where:

L<sub>M TOTAL PROJECT</sub> = Required TSS removal resulting from the proposed development = 80% of increased load

A<sub>N</sub> = Net increase in impervious area for the project P = Average annual precipitation, inches

3

Site Data: Determine Required Load Removal Based on the Entire Project

	williamson	County =
acres	12.64	Total project area included in plan *=
acres	0.00	Predevelopment impervious area within the limits of the plan * =
acres	6.91	Total post-development impervious area within the limits of the plan* =
1	0.55	Total post-development impervious cover fraction * =
inches	32	P =

L<sub>M TOTAL PROJECT</sub> = 6014 lbs.

Number of drainage basins / outfalls areas leaving the plan area =

### 2. Drainage Basin Parameters (This information should be provided for each basin):

Orainage	Basin/Outfall	Aroa	Nο	=
Jrainage	Dasiii/Outiaii	Area	NO.	_

Total drainage basin/outfall area = 12.64 acres Predevelopment impervious area within drainage basin/outfall area = 0.00 acres Post-development impervious area within drainage basin/outfall area = 0.55 acres 0.55 0.55 0.55 0.55 0.55 0.55 0.55

#### 3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Extended Detention/Batch Detention

Removal efficiency = **91** percent

Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault

#### 4. Calculate Maximum TSS Load Removed (L<sub>R</sub>) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7:  $L_R = (BMP \text{ efficiency}) \times P \times (A_1 \times 34.6 + A_2 \times 0.54)$ 

where:

 $A_C$  = Total On-Site drainage area in the BMP catchment area  $A_I$  = Impervious area proposed in the BMP catchment area

A<sub>P</sub> = Pervious area remaining in the BMP catchment area

 $L_{\text{R}}\,\text{=}\,\text{TSS}$  Load removed from this catchment area by the proposed BMP

 $A_{C} =$  12.64 acres  $A_{I} =$  6.91 acres  $A_{P} =$  5.73 acres  $L_{R} =$  7052 lbs

<sup>\*</sup> The values entered in these fields should be for the total project area.

#### 5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L<sub>M THIS BASIN</sub> = 6014 lbs.

F = **0.85** 

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 1.32 inches
Post Development Runoff Coefficient = 0.38
On-site Water Quality Volume = 23298 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = 0.00 acres
Off-site Impervious cover draining to BMP = 0.00 acres
Impervious fraction of off-site area = 0
Off-site Runoff Coefficient = 0.00

Off-site Water Quality Volume = 0 cubic feet

Storage for Sediment = 4660

Total Capture Volume (required water quality volume(s) x 1.20) = 27958 cubic feet

### SEE INCLUDED PLANS FOR MORE DETAILS OF THE BMP.

### ATTACHMENT J: BMP FOR UPGRADIENT STORMWATER

No upgradient stormwater is routed through the proposed development. There is an existing open channel along the east boundary of the property that routes all upgradient stormwater south, never mixing with onsite stormwater.

### ATTACHMENT K: BMPS FOR ON-SITE STORMWATER

### 1. Stabilization Practices

- A. Installation of temporary onsite controls; silt fence and stabilized construction entrance.
- B. Excavation and construction of the batch detention pond to collect and treat on-site storm water runoff before conveyed back to natural drainage patterns.
- C. Permanent seeding and planting of all unpaved areas using a manual broadcasting or hydro mulching grass seeding technique. Permanent vegetation controls erosion by physically protecting a bare soil surface from raindrop impact, flowing water and wind. Vegetation binds soil particles together with a dense root system and reduces the velocity of runoff.
- D. Mulching exposed areas. Surface mulch is the most effective, practical means of controlling erosion on disturbed areas before establishing vegetation. Mulch protects the soil surface, reduces runoff velocity, increases infiltration, slows soil moisture loss, helps prevent soil crusting and sealing, moderates soil temperatures, and improves the microclimate for seed germination.
- E. Sodding/Landscape Planting Trees, Shrubs, vines, and ground covers can provide superior, low-maintenance, long-term erosion protection. Woody plants and ground covers are particularly adapted for use on steep or rocky slopes where maintenance is difficult, in shaded areas, for wildlife habitat improvements, as windbreaks or screens.

### 2. Structural Practices

- A. A storm sewer system and minor site grading will be used to direct the flow of stormwater to the designed on-site water quality BMP.
- B. A batch detention pond will be utilized as the primary water quality control for the project.



### ATTACHMENT M: CONSTRUCTION PLANS

The batch detention BMP has been designed in accordance with RG—348. Construction plans and design calculations for the proposed permanent BMP and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer and are attached with this report. All construction plans and design information have been signed, sealed, and dated by the Texas Licensed Professional Engineer. See plans by GarzaEMC for technical calculations and construction details.

# ATTACHMENT N: INSPECTION, MAINTENANCE, REPAIR, AND RETROFIT PLANS

The following inspection and maintenance practices will be used to maintain permanent erosion and sediment controls.

### **BATCH DETENTION BASIN**

- 1. Inspections. Inspections should take place a minimum of twice a year. One inspection should take place during wet weather to determine if the pond is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. The remaining inspections should occur between storm events so that manual operation of the valve and controller can be verified. The level sensor in the basin should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet(s) as described in the previous section. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately. The owner will provide routine inspection and maintenance for this pond, generally following these practices:
  - A. Mowing. The basin, basin side-slopes, and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas.
  - B. Litter and Debris Removal. Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for possible clogging or obstructions and any debris removed.
  - C. Complete inspection log and note any actions taken.



### 2. Maintenance:

- A. Erosion control. The basin side slopes and embankment all may periodically suffer from slumping and erosion. To correct these problems, corrective action, such as regrading and revegetation, may be necessary. Correction of erosion control should take place whenever required based on the periodic inspections.
- B. Nuisance Control. Standing water or soggy conditions may occur in the basin. Some standing water may occur after a storm event since the valve may close with 2 to 3 inches of water in the basin. Some flow into the basin may also occur between storms due to spring flow and residential water use that enters the storm sewer system. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.)
- C. Structural Repairs and Replacement. With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, etc.) should be identified and repaired immediately. An example of this type of repair can include patching of cracked concrete, sealing of voids, removal of vegetation from cracks and joints. The various inlet/outlet structures in a basin will eventually deteriorate and must be replaced.
- D. Sediment Removal. A properly designed batch detention basin will accumulate quantities of sediment over time. The accumulated sediment can detract from the appearance of the facility and reduce the pollutant removal performance of the facility. The sediment also tends to accumulate near the outlet structure and can interfere with the level sensor operation. Sediment shall be removed from the basin at least every 5 years, when sediment depth exceeds 6 inches or when the basin does not drain within 48 hours. Care should be taken not to compromise the basin lining during maintenance.
- E. Logic Controller. The Logic Controller should be inspected as part of the twice yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris. The solar panel should be inspected and any dust or debris on the panel should be carefully removed. The controller and all other circuitry and wiring should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. At the end of the inspection, the controller should be reset.



### MODIFICATIONS/REPAIRS & RETROFIT PLAN

The required inspections should also identify if any revisions to the permanent BMP are warranted due to unexpected conditions. This is meant to be a dynamic working guide that is to be kept current and amended whenever necessary:

- (a) There is a change in design, construction, operation, or maintenance at the site that has or could have significant effect on the discharge of pollutants to the Waters of the United States that has not been previously addressed.
- (b) Inspections or investigations by site staff, or by local, state, or federal officials, determine that the discharges from the permanent BMP are ineffective in eliminating or significantly minimizing pollutants in storm water discharges from the construction site.
- (c) Based on the results of an inspection, it must be modified as necessary to include additional or modified BMPs designed to correct problems identified.



OWNER ACKNOWLEDGEMENT OF INSPECTION, MAINTENANCE, REPAIR AND RETROFIT PLAN

RESPONSIBLE PARTY FOR OP III ATX LIBERTY HILL 183, LP

SIGNATURE:

PRINT NAME: Luke Phillippi

TITLE: Executive Vice President

# ATTACHMENT P: MEASURES FOR MINIMIZING SURFACE STREAM CONTAMINATION

The project will not involve rerouting, filling, or crossing a waterway of any kind. This drain to a batch detention pond through an underground storm system; refer to the construction plan sheets for more detail.

The proposed site plan and improvements will have minimal impact on the existing site condition and surrounding property. The design, analysis, and their applicability as presented herein is based on and by the most current weather data available for this area. This development, with recommended improvements if constructed per the site development plans prepared by GarzaEMC, is deemed not to increase existing endangerment to life or property in the surrounding area and no adverse impacts to existing drainage patterns.



#### **ATTACHMENTS FOR TEMPORARY STORMWATER SECTION (TCEQ-0602)**

#### ATTACHMENT A: SPILL RESPONSE ACTIONS

- 1. Report to TCEQ within 24 hours any noncompliance with this CZP that will endanger public health or the environment. Follow up with a written report within 5 days of the noncompliance event. The following events require 24 hour reporting: a) any unanticipated bypass which exceeds any effluent limitation in the permit, b) any upset which exceeds any effluent limitation in the permit, and c) a violation of a maximum daily discharge limitation for any of the pollutants listed by the TPDES General Permit TXR150000 are to be reported within 24 hours. The written submission must contain a description of the non-compliance and its cause; the period of non-compliance, including exact dates and times, and if the non-compliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the non-compliance.
- 2. Spills or Releases of Hazardous Substances or Oil in excess of reportable quantities (as established under 40 CFR Part 110, 40 CFR Part 117 or 40 CFR Part 302) must be reported immediately, and in no case any longer than 24 hours subsequent from the occurrence of the spill or release. Contact Info Track at 1-888-429-6281 (1-888-HAZMAT 1) to determine whether the spill is reportable. Reports shall be made to the US EPA National Response Center (1-800-424-8802). The permitee must also report any spills or releases to the Environmental Emergency Response at TCEQ.

#### 3. INSTRUCTIONS FOR CLEAN-UP/SPILL REMEDIATION:

- Avoid direct contact with the spilled material.
- Avoid inhalation of any gases, fumes, vapors, or smoke. All personnel should stay upwind (some gases inhibit the sense of smell or may be dangerous at undetectable concentrations).
- Move and keep people away from the incident scene. Contact the nearest law-enforcement authority for assistance, if necessary.
- Find and, if possible, safely remove all ignition sources.
- Assess the situation with regard to injuries.
- Contact the appropriate authorities and responsible parties and allow them to handle the response.

The following steps will help reduce the stormwater impacts of leaks and spills:



#### Education

- 1. Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
- 2. Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- 3. Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- 4. Establish a continuing education program to indoctrinate new employees.
- 5. Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

#### **General Measures**

- 1. To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- 2. Store hazardous materials and wastes in covered containers and protect from vandalism.
- 3. Place a stockpile of spill cleanup materials where it will be readily accessible.
- 4. Train employees in spill prevention and cleanup.
- 5. Designate responsible individuals to oversee and enforce control measures.
- 6. Spills should be covered and protected from stormwater runon during rainfall to the extent that it doesn't compromise clean-up activities.
- 7. Do not bury or wash spills with water.
- 8. Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.



- 9. Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- 10. Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- 11. Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- 12. Keep waste storage areas clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

#### Cleanup

- 1. Clean up leaks and spills immediately.
- 2. Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- 3. Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

#### Minor Spills

- 1. Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- 2. Use absorbent materials on small spills rather than hosing down or burying the spill.
- 3. Absorbent materials should be promptly removed and disposed of properly.
- 4. Follow the practice below for a minor spill:
  - a. Contain the spread of the spill.
  - b. Recover spilled materials.
  - c. Clean the contaminated area and properly dispose of contaminated materials.



#### Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- 1. Contain spread of the spill.
- 2. Notify the project foreman immediately.
- 3. If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- 4. If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- 5. If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

#### Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- 1. Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224.It is
- 2. the contractor's responsibility to have all emergency phone numbers at the construction site.
- 3. For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- 4. Notification should first be made by telephone and followed up with a written report.
- 5. The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- 6. Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc. More



information on spill rules and appropriate responses is on the TCEQ website at: Spills, Discharges, and Releases - Texas Commission on Environmental Quality - www.tceq.texas.gov

#### Vehicle and Equipment Maintenance

- 1. If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- 2. Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- 3. Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- 4. Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- 5. Place drip pans or absorbent materials under paving equipment when not in use.
- 6. Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
- 7. Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- 8. Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- 9. Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Vehicle and Equipment Fueling

1. If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.



- 2. Discourage "topping off" of fuel tanks.
- 3. Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.

#### ATTACHMENT B: POTENTIAL SOURCES OF CONTAMINATION

Potential pollutants other than sediment include the following materials and substances that could be expected to be present on-site during construction:

- Heavy Metals from concrete additives, concrete washout, material delivery, storage and use, and hazardous substance/waste spills
- pH (Acids and Bases) from concrete washout, painting and cleaning, drilling, material delivery, storage and use, hazardous waste spills, and sanitary/septic waste.
- Paints and Solvents from concrete washout and waste, painting, concrete polishing, cleaning products, material delivery and use, hazardous waste spills, and sanitary/septic waste
- Trash, Debris and Solids from clearing and grading, paving, concrete wash waste, construction painting and cleaning, demolition, drilling and blasting, material delivery storage and use, landscaping, and general construction
- Petroleum Based Products from material delivery storage and use, hazardous waste spills, vehicle and equipment use on site, and vehicle and equipment fueling and maintenance and storage
- Pesticides/Herbicides from material delivery, storage and use, hazardous waste spills, vehicle use, storage, service and maintenance
- Fertilizers/Nutrients from painting, cleaning products, dewatering, material
- Delivery and storage, spills during landscaping operation, sanitary/septic waste.

Potential sources of post construction stormwater runoff include:

- Sediment coarse and fine from vehicle and equipment use on site.
- Heavy Metals dissolved and particulate from vehicle washing activities
- Petroleum Based Products from hazardous material spills, vehicle and equipment use on site.

#### ATTACHMENT C: SEQUENCE OF MAJOR ACTIVITIES

- 1. Pre-construction meeting shall be held by the project manager and the operator's engineer prior to land disturbing activities.
- 2. Install perimeter sediment fences in the locations shown.  $\sim$  3.0 acres of disturbance.
- 3. Commence construction of the temporary sedimentation basin (site of the batch detention pond) and associated facilities. ~ 1 acre of disturbance.



- 4. Commence with site grading~ 11 acres
- 5. Disturbed areas of the site where construction activity has ceased for more than 14 days shall be temporarily seeded and watered.
- 6. Finish grading once pond is complete and site is stabilized. ~ 11 acres of disturbance.
- 7. Remove sediment fencing only after all pond work is complete and exposed surfaces are stabilized; 75% cover on all pervious surfaces. ~ 0.50 acres of disturbance.
- 8. Maintain erosion and sediment control devices along perimeter of site as needed for ongoing mulching and soil mixing operations.

# ATTACHMENT D: TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

- Temporary seeding and planting of all unpaved areas. Temporary seeding is used to protect earthen sediment control practices and to stabilize denuded areas that will not be brought to final grade for several weeks or months. Temporary seeding can provide a nurse crop for permanent vegetation, provide residue for soil protection and seedbed preparation, and help prevent dust production during construction.
- Mulching exposed areas. Surface mulch is the most effective, practical
  means of controlling erosion on disturbed areas before establishing
  vegetation. Mulch protects the soil surface, reduces runoff velocity,
  increases infiltration, slows soil moisture loss, helps prevent soil crusting and
  sealing, moderates soil temperatures, and improves the microclimate for
  seed aermination.
- Soil Roughening by normal tilling, disking, harrowing, or use of a cultipackerseeder. Roughening a sloping bare soil surface with horizontal depressions helps control erosion by aiding the establishment of vegetable cover with seed, reducing runoff velocity, and increasing infiltration. The depressions also trap sediment on the face of the slope.
- Dust Control (frequent watering to minimize wind erosion during construction). To minimize dust on construction sites, it is important to schedule construction activities so the least amount of soil is disturbed at any one time.

#### ATTACHMENT F: STRUCTURAL PRACTICES

• The area disturbed with a common drainage area is approximately 12 acres. A rough cut of the proposed pond will be used as a temporary sediment basin in addition to erosion and sediment controls other than sediment basins or sediment traps.



- Perimeter protection using reinforced silt fencing. A silt fence is a
  permeable barrier erected on small disturbed areas to capture sediment
  form sheet flow. It is made of a filter fabric buried at the bottom, the fabric
  restricts flow rate, forming a sedimentation pool at the approach to the inlet
  or downstream conveyance.
- Stabilized construction entrance/exit points. During wet weather, unstabilized staging/laydown areas become muddy and are virtually unusable. These areas generate sediment and cause work disruption. Proper grading and stabilization of construction routes often saves money for the Contractor by improving the overall efficiency of the construction operation while reducing potential erosion problems.
- Concrete washout area is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting onsite washout in a designated area as shown on the plans per the included detail.

#### ATTACHMENT G: DRAINAGE AREA MAP

See Sheet 05 EXISTING DRAINAGE AREA MAP in the GarzaEMC plan set attached at the end of this application package.

# ATTACHMENT H: TEMPORARY SEDIMENT POND PLANS AND CALCULATIONS

Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information have been signed, sealed, and dated by the Texas Licensed Professional Engineer. See plans by GarzaEMC for temporary sediment controls and details.

#### ATTACHMENT I: INSPECTION AND MAINTENANCE FOR BMPS

The following inspection and maintenance practices will be used to maintain erosion and sediment controls and stabilization measures:

- Inspection of all erosion controls and other SWPPP requirements shall be performed during permit coverage using a copy of the form provided in the Construction Forms Package (included with this SWPPP), and inspections shall be performed:
  - a. at least weekly for a minimum of four inspections per month; and within 24 hr of any rainfall event, and
  - b. as often as is necessary to ensure that appropriate erosion and sediment controls have been properly constructed and maintained and determine if additional or alternative control measures are required.



- 2. All measures will be maintained in good working order; if repairs or other measures are found to be necessary, they will be completed within 24 hours of report.
- 3. Built up sediment will be removed from silt fence before it has reached 6 inches in height.
- 4. Silt fences will be inspected for depth of sediment, tears, etc., to see if the fabric is securely attached to the fence posts, and to see that the fence posts are securely in the ground.
- 5. Temporary and permanent seeding and all other stabilization measures will be inspected for bare spots, washouts, and healthy growth.
- 6. An Inspection Report will be completed after each inspection.
- 7. The Contractor's Superintendent will be responsible for selecting and training the individuals who will be responsible for these inspections, maintenance and repair activities, and filling out the Inspection Report and Certification Forms.
- 8. Disturbed areas and materials storage areas will be inspected for evidence of or potential for pollutants entering storm water systems.

# ATTACHMENT J: SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES


- DAY 1 Install perimeter silt fences in the locations shown on this sheet.
- DAY 2 Begin clearing and grubbing operations; clearing and grubbing shall be done only in areas where earthwork will be performed and only in areas where building is planned to commence within 14 days after clearing and grubbing.
- DAY 2 Install remaining erosion control measures and structures.
- DAY 5 Install permanent stormwater controls.
- DAY 70 Disturbed areas of the site where construction activity has ceased for more than 14 days shall be temporarily seeded and watered.
- DAY 71 Carry out final grading, seeding and planting; fine grade and install permanent seeding and plantings.
- DAY 75 Submit notice of termination for permit termination.
- DAY 76 Maintain erosion and sediment control devices along perimeter of site as needed for ongoing mulching and soil mixing operation



7708 Rialto Blvd. | Suite 125 Austin, TX. 78735

p: (512) 298-3284 | e: info@garzaemc.com





OWNER OP III ATX LIBERTY HILL 183, LP 500 WEST 5TH STREET, SUITE 700

AUSTIN, TX 78701 (512) 761-1848

DEVELOPER: ENDEAVOR REAL ESTATE GROUP 500 WEST 5TH STREET, SUITE 700

> AUSTIN, TX 78735 (512) 682-5500

ARCHITECT: STEINBERG DICKEY COLLABORATIVE, LLP

8100 WASHINGTON AVENUE, SUITE 250 HOUSTON, TX 77007

ENGINEER: GARZAEMC, LLC.

9106 WHEAT CROSS DR

(713) 552-1777

HOUSTON, TEXAS 77095 (713) 491-6039

SURVEYOR 4WARD LAND SURVEYING

4120 FREIDRICH LANE, SUITE 200 AUSTIN, TX 78744 (512) 537-2384

# FLOODPLAIN INFORMATION:

THE FEDERAL EMERGENCY MANAGEMENT AGENCY FIRM COMMUNITY PANEL NUMBER 48453C0585H WITH AN EFFECTIVE DATE OF SEPTEMBER 26, 2009 INDICATES THAT THE ABOVE DESCRIBED PROPERTY LIES WITHIN AREAS DESIGNATED AS ZONE "X". ZONE "X" IS DEFINED AS AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN PER THE FLOOD INSURANCE RATE MAPS. THIS MAP DOES NOT NECESSARILY SHOW ALL AREAS SUBJECT TO FLOODING IN THE COMMUNITY OR ALL PLANIMETRIC FEATURES OUTSIDE SPECIAL FLOOD HAZARD AREAS. THIS DOES NOT GUARANTEE THAT THE SURVEYED PROPERTY WILL OR WILL NOT FLOOD. APPROXIMATE LOCATIONS OF FLOOD ZONES HAVE BEEN SHOWN HEREON BASED ON THE CURRENT FLOOD INSURANCE RATE MAPS.

LEGAL DESCRIPTION:

GUNNER NE MULTI-FAMILY SUBDIVISION LOT 1B BLOCK A 12.638 ACRES

BENCHMARK NOTE:

TBM #1 - SQUARE CUT FOUND IN CONCRETE IN THE EAST MARGIN OF HIGHWAY US-183 AND NORTH MARGIN OF COUNTY ROAD 259. ELEVATION = 960.40'

TBM #2 - SQUARE CUT FOUND IN CONCRETE IN THE NORTH MARGIN OF COUNTY ROAD 259, EAST OF HIGHWAY US-183. **ELEVATION = 965.62'** 

SUBDIVISION No: S13297

ZONING ORDINANCE No.: 15-O-55



9106 Wheat Cross Drive Houston, Texas 77095 Tel. (713) 491-6039 Fax (512) 298-2592 TBPE # F-14629 Garza EMC, LLC © Copyright 2024

LAND USE SUMMARY

ZONING: PUD 1 PER ORDINANCE 15-0-55 PROPOSED USE: MULTI-FAMILY ACREAGE: 550,492 SF/ 12.638 AC TOTAL IMPERVIOUS COVER: 301,124 SF/ 6.91 AC BUILDING IMPERVIOUS COVER: 101,770 SF/ 2.34 AC MULTI-FAMILY UNITS: 320

TOTAL PUD AREA: 82.28 AC PERCENTAGE OF PUD AREA: 16.6% FUTURE LAND USE: NEW URBAN VILLAGE

# SITE DEVELOPMENT PERMIT PLANS

FOR

# LIBERTY HILL MF DEVELOPMENT 2024-4-SDP

FILE NO.: 2024-4-SDP

ADDRESS: 250 GRACIE LANE

LIBERTY HILL, TX 78642

SUBMITTAL DATE: FEBRUARY 7, 2024

Frile Alizi SUBMITTED BY:

05-07-2024 BILAL ALIZAI, P.E.

BILAL A. ALIZAI

DATE

GarzaEMC, LLC. 9106 WHEAT CROSS DRIVE HOUSTON, TEXAS 77095 (713) 491-6039

# PLAN SUBMITTALS:

NO.	DATE	COMMENTS

I, BILAL ALIZAI, P.E., CERTIFY THAT THESE ENGINEERING DOCUMENTS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THE INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO FORMAL

# SHEET INDEX

SHEET NO.	DESCRIPTION
01	COVER
02	GENERAL NOTES
03	PLAT — SHEET 1
04	PLAT — SHEET 2
05	EXISTING DRAINAGE AREA MAP
06	PROPOSED DRAINAGE AREA MAP
07	EXISTING CONDITIONS & DEMOLITION
08	EROSION CONTROL PLAN
09	EROSION CONTROL DETAILS
10	MASTER SITE PLAN
11	SITE PLAN A
12	SITE PLAN B
13	SITE PLAN C
14	SITE PLAN D
15	PAVING PLAN
16	SITE DETAILS
17	MASTER GRADING PLAN
18	GRADING PLAN A
19	GRADING PLAN B
20	GRADING PLAN C
21	GRADING PLAN D
22	STORM SEWER PLAN
23	STORM SEWER DETAILS
24	POND PLAN
25	POND DETAILS
26	WATER PLAN
27	WATER PLAN — ENLARGED VIEWS
28	UTILITY PLAN-SIMPLIFIED
29	PUBLIC WATER LINE A PNP
30	WATER DETAILS
31	WASTEWATER PLAN
32	WASTEWATER DETAILS
33	UTILITY CALCULATIONS

NO.	DESCRIPTION	REVISE (R) ADD (A) VOID (V) SHEET NO.'S	TOTAL # SHEETS IN PLAN SET	NET CHANGE IMP. COVER (sq. ft.)	TOTAL SITE IMP. COVER (sq. ft.) [%]	CITY OF GEORGETOWN APPROVAL/DATE	DATE IMAGED

APPROVED FOR ACCEPTANCE:

LIZ BRANIGAN, MAYOR DATE PAUL BRANDENBURG, CITY MANAGER DATE

TEXAS DEPARTMENT OF TRANSPORTATION DATE WILLIAMSON COUNTY ESD NO. 4 DATE

GEORGETOWN WATER UTILITY DEPARTMENT DATE

ELAINE SIMPSON, CITY SECRETARY DATE

CURTIS STEGER, P.E., CITY ENGINEER BASED ON THE DESIGN ENGINEER'S CERTIFICATION OF COMPLIANCE WITH ALL APPLICABLE CITY, STATE AND FEDERAL REGULATIONS,

THE PLANS AND SPECIFICATIONS CONTAINED HEREIN HAVE BEEN REVIEWED AND ARE FOUND TO BE IN COMPLIANCE WITH THE REQUIREMENTS OF THE CITY OF LIBERTY HILL.

SHEET

DATE

#### GENERAL NOTES:

- 1. IT IS THE RESPONSIBILITY OF THE PROPERTY OWNER, AND SUCCESSORS TO THE CURRENT PROPERTY OWNER, TO ENSURE THE SUBJECT PROPERTY AND ANY IMPROVEMENTS ARE MAINTAINED IN CONFORMANCE WITH THIS SITE DEVELOPMENT PLAN.
- THIS DEVELOPMENT SHALL COMPLY WITH ALL STANDARDS OF THE UNIFIED DEVELOPMENT CODE (UDC), THE CITY OF ROUND ROCK DESIGN AND CONSTRUCTION STANDARDS AND SPECIFICATIONS MANUAL, THE DEVELOPMENT MANUAL AND ALL OTHER APPLICABLE CITY STANDARDS.
- THIS SITE DEVELOPMENT PLAN SHALL MEET THE UDC STORMWATER REQUIREMENTS.
- ALL SIGNAGE REQUIRES A SEPARATE APPLICATION AND APPROVAL FROM THE INSPECTION SERVICES DEPARTMENT. NO SIGNAGE IS APPROVED WITH THE SITE DEVELOPMENT PLAN.
- SIDEWALKS SHALL BE PROVIDED IN ACCORDANCE WITH THE UDC.
- DRIVEWAYS WILL REQUIRE APPROVAL BY THE DEVELOPMENT ENGINEER OF
- 7. OUTDOOR LIGHTING SHALL COMPLY WITH SECTION 7.04 OF THE UDC.
- 8. SCREENING OF MECHANICAL EQUIPMENT, DUMPSTERS AND PARKING SHALL COMPLY WITH CHAPTER 6 OF THE UDC. THE SCREENING IS SHOWN ON THE LANDSCAPE AND ARCHITECTURAL PLANS, AS APPLICABLE.
- 9. THE COMPANION LANDSCAPE PLAN HAS BEEN DESIGNED AND PLANT MATERIALS SHALL BE INSTALLED TO MEET ALL REQUIREMENTS OF THE UDC.
- 10. ALL MAINTENANCE OF REQUIRED LANDSCAPE SHALL COMPLY WITH THE
- 11. A SEPARATE IRRIGATION PLAN SHALL BE REQUIRED AT THE TIME OF BUILDING PERMIT APPLICATION.
- 12. FIRE FLOW REQUIREMENTS OF 1500 GALLONS PER MINUTE (INCLUDE AMOUNT) ARE BEING MET BY THIS PLAN.

MAINTENANCE STANDARDS OF CHAPTER 6 OF THE UDC.

- 13. ANY HERITAGE TREE NOTED ON THIS SITE DEVELOPMENT PLAN IS SUBJECT, IN PERPETUITY, TO THE MAINTENANCE, CARE, PRUNING AND REMOVAL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE.
- 14. THE CONSTRUCTION PORTION OF THESE PLANS WERE PREPARED, SEALED, SIGNED AND DATED BY A TEXAS LICENSED PROFESSIONAL ENGINEER. THEREFORE, BASED ON THE ENGINEER'S CONCURRENCE OF COMPLIANCE, THE CONSTRUCTION PLANS FOR CONSTRUCTION OF THE PROPOSED PROJECT ARE HEREBY APPROVED SUBJECT TO THE STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS MANUAL AND ALL OTHER APPLICABLE CITY, STATE AND FEDERAL REQUIREMENTS AND CODES.
- 15. THIS PROJECT IS SUBJECT TO ALL CITY STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS IN EFFECT AT THE TIME OF SUBMITTAL OF THE PROJECT TO THE CITY.
- 16. WHERE NO EXISTING OVERHEAD INFRASTRUCTURE EXISTS, UNDERGROUND ELECTRIC UTILITY LINES SHALL BE LOCATED ALONG THE STREET AND WITHIN THE SITE. WHERE EXISTING OVERHEAD INFRASTRUCTURE IS TO BE RELOCATED, IT SHALL BE RE-INSTALLED UNDERGROUND AND THE EXISTING FACILITIES SHALL BE REMOVED AT THE DISCRETION OF THE DEVELOPMENT ENGINEER.
- 17. ALL ELECTRIC AND COMMUNICATION INFRASTRUCTURE SHALL COMPLY WITH UDC SECTION 5.04.A.6.
- 18. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF ROUND ROCK STANDARD SPECIFICATIONS MANUAL.
- 19. ANY EXISTING UTILITIES, PAVEMENT, CURBS, SIDEWALKS, STRUCTURES, TREES, ETC., NOT PLANNED FOR DESTRUCTION OR REMOVAL THAT ARE DAMAGED OR REMOVED SHALL BE REPAIRED OR REPLACED AT OWNER'S EXPENSE.
- 20. THE CONTRACTOR SHALL VERIFY ALL DEPTHS AND LOCATIONS OF EXISTING UTILITIES PRIOR TO ANY CONSTRUCTION, ANY DISCREPANCIES WITH THE CONSTRUCTION PLANS FOUND IN THE FIELD SHALL BE BROUGHT IMMEDIATELY TO THE ATTENTION OF THE ENGINEER WHO SHALL BE RESPONSIBLE FOR REVISING THE PLANS ARE APPROPRIATE.
- 21. MANHOLE FRAMES, COVERS, VALVES, CLEANOUTS, ETC. SHALL BE RAISED TO FINISHED GRADE PRIOR TO FINAL PAVING CONSTRUCTION.
- 22. THE CONTRACTOR SHALL GIVE THE CITY OF LIBERTY HILL 48 HOURS NOTICE BEFORE BEGINNING EACH PHASE OF CONSTRUCTION. TELEPHONE (512) 548-5519 (PLANNING AND DEVELOPMENT DEPARTMENT).
- 23. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE REVEGETATED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. REVEGETATION OF ALL DISTURBED OR EXPOSED AREAS SHALL CONSIST OF SODDING OR SEEDING, AT THE CONTRACTOR'S OPTION. HOWEVER, THE TYPE OF REVEGETATION MUST EQUAL OR EXCEED THE TYPE OF VEGETATION PRESENT BEFORE CONSTRUCTION.
- 24. PRIOR TO ANY CONSTRUCTION, THE ENGINEER SHALL CONVENE A PRECONSTRUCTION CONFERENCE BETWEEN THE CITY OF LIBERTY HILL, HIMSELF, THE CONTRACTOR, OTHER UTILITY COMPANIES, ANY AFFECTED PARTIES AND ANY OTHER ENTITY THE CITY OF LIBERTY HILL OR ENGINEER MAY REQUIRE.
- 25. THE CONTRACTOR AND THE ENGINEER SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE ENGINEER SHALL FURNISH THE CITY OF ROUND ROCK ACCURATE "AS-BUILT" DRAWINGS FOLLOWING COMPLETION OF ALL CONSTRUCTION. THESE "ASBUILT" DRAWINGS SHALL MEET WITH THE SATISFACTION OF THE PLANNING AND DEVELOPMENT DEPARTMENT PRIOR TO FINAL ACCEPTANCE.
- 26. THE CITY OF LIBERTY HILL COUNCIL SHALL NOT BE PETITIONED FOR ACCEPTANCE UNTIL ALL NECESSARY EASEMENT DOCUMENTS HAVE BEEN SIGNED AND RECORDED.
- 27. WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS, THE CONTRACTOR SHALL CONFINE HIS WORK TO WITHIN THE PERMANENT AND ANY TEMPORARY EASEMENTS. PRIOR TO FINAL ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. CLEAN-UP SHALL BE TO THE SATISFACTION OF THE CITY ENGINEER.
- 28. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL APPLY FOR AND SECURE ALL PROPER PERMITS FROM THE APPROPRIATE AUTHORITIES.
- 29. AVAILABLE BENCHMARKS (CITY OF LIBERTY HILL DATUM) THAT MAY BE UTILIZED FOR THE CONSTRUCTION OF THIS PROJECT ARE DESCRIBED AS FOLLOWS.

#### TRENCH SAFETY NOTES:

- 1. IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U. S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, ALL TRENCHES OVER 5 FEET IN DEPTH IN EITHER HARD AND COMPACT OR SOFT AND UNSTABLE SOIL SHALL BE SLOPED, SHORED, SHEETED, BRACED OR OTHERWISE SUPPORTED. FURTHERMORE, ALL TRENCHES LESS THAN 5 FEET IN DEPTH SHALL ALSO BE EFFECTIVELY PROTECTED WHEN HAZARDOUS GROUND MOVEMENT MAY BE EXPECTED. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT (WILL BE PROVIDED BY THE CONTRACTOR; ARE ON SHEET <u>30</u>, ETC.).
- 2. IN ACCORDANCE WITH THE U. S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, WHEN PERSONS ARE IN TRENCHES 4-FEET DEEP OR MORE, ADEQUATE MEANS OF EXIT, SUCH AS A LADDER OR STEPS, MUST BE PROVIDED AND LOCATED SO AS TO REQUIRE NO MORE THAN 25 FEET OF LATERAL TRAVEL.
- 3. IF TRENCH SAFETY SYSTEM DETAILS WERE NOT PROVIDED IN THE PLANS BECAUSE TRENCHES WERE ANTICIPATED TO BE LESS THAN 5 FEET IN DEPTH AND DURING CONSTRUCTION IT IS FOUND THAT TRENCHES ARE IN FACT 5 FEET OR MORE IN DEPTH OR TRENCHES LESS THAN 5 FEET IN DEPTH ARE IN AN AREA WHERE HAZARDOUS GROUND MOVEMENT IS EXPECTED, ALL CONSTRUCTION SHALL CEASE, THE TRENCHED AREA SHALL BE BARRICADED AND THE ENGINEER NOTIFIED IMMEDIATELY. CONSTRUCTION SHALL NOT RESUME UNTIL APPROPRIATE TRENCH SAFETY SYSTEM DETAILS, AS DESIGNED BY A PROFESSIONAL ENGINEER, ARE RETAINED AND COPIES SUBMITTED TO THE CITY OF LIBERTY HILL.

#### STREET AND DRAINAGE NOTES

- 1. ALL TESTING SHALL BE DONE BY AN INDEPENDENT LABORATORY AT THE OWNER'S EXPENSE. ANY RETESTING SHALL BE PAID FOR BY THE CONTRACTOR. A CITY OF LIBERTY HILL INSPECTOR SHALL BE PRESENT DURING ALL TESTS. TESTING SHALL BE COORDINATED WITH THE CITY OF LIBERTY HILL INSPECTOR AND HE SHALL BE GIVEN A MINIMUM OF 24 HOURS NOTICE PRIOR TO ANY TESTING. TELEPHONE 512-548-5510 KATHERYN MITCHELL (INSPECTIONS).
- 2. BACKFILL BEHIND THE CURB SHALL BE COMPACTED TO OBTAIN A MINIMUM OF 95% MAXIMUM DENSITY TO WITHIN 3" OF TOP OF CURB. MATERIAL USED SHALL BE PRIMARILY GRANULAR WITH NO ROCKS LARGER THAN 6" IN THE GREATEST DIMENSION. THE REMAINING 3" SHALL BE CLEAN TOPSOIL FREE FROM ALL CLODS AND SUITABLE FOR SUSTAINING PLANT LIFE.
- DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT INCLUDING GAS, ELECTRIC, TELEPHONE, CABLE TV, WATER SERVICES, ETC., SHALL BE A MINIMUM OF 30" BELOW SUBGRADE.
- 4. STREET RIGHTS-OF-WAY SHALL BE GRADED AT A SLOPE OF 1/4" PER FOOT TOWARD THE CURB UNLESS OTHERWISE INDICATED. HOWEVER, IN NO CASE SHALL THE WIDTH OF RIGHT-OF-WAY AT 1/4" PER FOOT SLOPE BE LESS THAN 10 FEET UNLESS A SPECIFIC REQUEST FOR AN ALTERNATE GRADING SCHEME IS MADE TO AND ACCEPTED BY THE CITY OF ROUND ROCK ENGINEERING AND DEVELOPMENT SERVICES DEPARTMENT.
- 5. BARRICADES BUILT TO CITY OF ROUND ROCK STANDARDS SHALL BE CONSTRUCTED ON ALL DEAD-END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB AND PUBLIC SAFETY.
- 6. ALL R.C.P. SHALL BE MINIMUM CLASS III.
- 7. THE SUBGRADE MATERIAL FOR THE STREETS SHOWN HEREIN WAS TESTED

AND THE PAVING SECTIONS DESIGNED IN ACCORDANCE WITH THE CURRENT CITY OF ROUND ROCK DESIGN CRITERIA. THE PAVING SECTIONS ARE TO BE CONSTRUCTED AS FOLLOWS:

FLEX. BASE HMAC LIME STAB. THICKNESS THICKNESS

THE GEOTECHNICAL ENGINEER SHALL INSPECT THE SUBGRADE FOR COMPLIANCE WITH THE DESIGN ASSUMPTIONS MADE DURING PREPARATION OF THE SOILS REPORT. ANY ADJUSTMENTS THAT ARE REQUIRED SHALL BE MADE THROUGH REVISION OF THE CONSTRUCTION PLANS.

- 8. WHERE PI'S ARE OVER 20, SUBGRADES MUST BE STABILIZED UTILIZING A METHOD ACCEPTABLE TO THE CITY OF ROUND ROCK ENGINEER. THE GEOTECHNICAL ENGINEER SHALL RECOMMEND AN APPROPRIATE SUBGRADE STABILIZATION IF SULFATES ARE DETERMINED TO BE PRESENT.
- 9. THE MAINTENANCE OF THE DRAINAGE AND DETENTION FACILITIES IS THE RESPONSIBILITY OF THE PROPERTY OWNER. THE HOMEOWNER'S ASSOCIATION (HOA)/ PROPERTY OWNER'S ASSOCIATION (POA)/ ETC. WILL BE RESPONSIBLE FOR THE MAINTENANCE OF THESE FACILITIES.

# WATER AND WASTEWATER NOTES:

- 1. PIPE MATERIAL FOR WATER MAINS SHALL BE PVC (AWWA C-900, MIN. CLASS 200), OR DUCTILE IRON (AWWA C-100, MIN. CLASS 200). WATER SERVICES (2" OR LESS) SHALL BE POLYETHYLENE TUBING (BLACK, 200 PSI, DR 9).
- 2. PIPE MATERIAL FOR PRESSURE WASTEWATER MAINS SHALL BE PVC (AWWA C-900, MIN. CLASS 150), OR DUCTILE IRON (AWWA C-100, MIN. CLASS 200). PIPE MATERIAL FOR GRAVITY WASTEWATER MAINS SHALL BE PVC (ASTM D2241 OR D3034, MAX. DR-26), DUCTILE IRON (AWWA C-100, MIN. CLASS 200).
- 3. UNLESS OTHERWISE ACCEPTED BY THE CITY OF ROUND ROCK ENGINEER, DEPTH OF COVER FOR ALL LINES OUT OF THE PAVEMENT SHALL BE 42" MIN., AND DEPTH OF COVER FOR ALL LINES UNDER PAVEMENT SHALL BE A MIN. OF 30" BELOW SUBGRADE.
- 4. ALL FIRE HYDRANT LEADS SHALL BE DUCTILE IRON PIPE (AWWA C-100, MIN. CLASS 200).
- 5. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH MINIMUM 8-MIL POLYETHYLENE AND SEALED WITH DUCT TAPE OR EQUAL ACCEPTED BY THE CITY OF ROUND ROCK ENGINEER.
- 6. THE CONTRACTOR SHALL CONTACT THE CITY OF LIBERTY HILL INSPECTOR AT 512-548-5510 KATHERYN MITCHELL TO COORDINATE UTILITY TIE-INS AND NOTIFY HIM AT LEAST 48 HOURS PRIOR TO CONNECTING TO EXISTING LINES.
- 7. ALL MANHOLES SHALL BE CONCRETE WITH CAST IRON RING AND COVER. ALL MANHOLES LOCATED OUTSIDE OF THE PAVEMENT SHALL HAVE BOLTED COVERS. TAPPING OF FIBERGLASS MANHOLES SHALL NOT BE ALLOWED.
- 8. THE CONTRACTOR MUST OBTAIN A BULK WATER PERMIT OR PURCHASE AND INSTALL A WATER METER FOR ALL WATER USED DURING CONSTRUCTION. A COPY OF THIS PERMIT MUST BE CARRIED AT ALL TIMES BY ALL WHO USE WATER.
- 9. LINE FLUSHING OR ANY ACTIVITY USING A LARGE QUANTITY OF WATER MUST BE SCHEDULED WITH THE WATER & WASTEWATER SUPERINTENDENT, TELEPHONE 218-5555.

- 10. THE CONTRACTOR, AT HIS EXPENSE, SHALL PERFORM STERILIZATION OF ALL (INCLUDING TEST GAUGES), SUPPLIES (INCLUDING CONCENTRATED COLLECTED BY THE CITY OF ROUND ROCK TO VERIFY EACH TREATED LINE HAS ATTAINED AN INITIAL CHLORINE CONCENTRATION OF 50 PPM. WHERE MEANS OF FLUSHING IS NECESSARY, THE CONTRACTOR, AT HIS EXPENSE, SHALL PROVIDE FLUSHING DEVICES AND REMOVE SAID DEVICES PRIOR TO
- 11. SAMPLING TAPS SHALL BE BROUGHT UP TO 3 FEET ABOVE GRADE AND SHALL BE EASILY ACCESSIBLE FOR CITY OF ROUND ROCK PERSONNEL. AT THE CONTRACTOR'S REQUEST, AND IN HIS PRESENCE, SAMPLES FOR BACTERIOLOGICAL TESTING WILL BE COLLECTED BY THE CITY OF ROUND ROCK NOT LESS THAN 24 HOURS AFTER THE TREATED LINE HAS BEEN FLUSHED OF THE CONCENTRATED CHLORINE SOLUTION AND CHARGED WITH WATER APPROVED BY THE CITY. THE CONTRACTOR SHALL SUPPLY A CHECK OR MONEY ORDER, PAYABLE TO THE CITY OF ROUND ROCK, TO COVER THE FEE CHARGED FOR TESTING EACH WATER SAMPLE. CITY OF LIBERTY HILL FEE AMOUNTS MAY BE OBTAINED BY CALLING THE PLANNING AND DEVELOPMENT DEPARTMENT (512) 548-5519.
- 12. THE CONTRACTOR, AT HIS EXPENSE, SHALL PERFORM QUALITY TESTING FOR ALL WASTEWATER PIPE INSTALLED AND PRESSURE PIPE HYDROSTATIC TESTING OF ALL WATER LINES CONSTRUCTED AND SHALL PROVIDE ALL EQUIPMENT (INCLUDING PUMPS AND GAUGES), SUPPLIES AND LABOR NECESSARY TO PERFORM THE TESTS. QUALITY AND PRESSURE TESTING SHALL BE MONITORED BY CITY OF LIBERTY HILL PERSONNEL.
- 13. THE CONTRACTOR SHALL COORDINATE TESTING WITH THE CITY OF LIBERTY HILL INSPECTOR AND PROVIDE NO LESS THAN 24 HOURS NOTICE PRIOR TO PERFORMING STERILIZATION, QUALITY TESTING OR PRESSURE TESTING.
- 14. THE CONTRACTOR SHALL NOT OPEN OR CLOSE ANY VALVES UNLESS AUTHORIZED BY THE CITY OF LIBERTY HILL.
- 15. ALL VALVE BOXES AND COVERS SHALL BE CAST IRON.
- 16. ALL WATER SERVICE, WASTEWATER SERVICE AND VALVE LOCATIONS SHALL BE APPROPRIATELY MARKED AS FOLLOWS:

WATER SERVICE "W" ON TOP OF CURB WASTEWATER SERVICE "S" ON TOP OF CURB "V" ON FACE OF CURB VALVE

TOOLS FOR MARKING THE CURB SHALL BE PROVIDED BY THE CONTRACTOR. OTHER APPROPRIATE MEANS OF MARKING SERVICE AND VALVE LOCATIONS SHALL BE PROVIDED IN AREAS WITHOUT CURBS. SUCH MEANS OF MARKING SHALL BE AS SPECIFIED BY THE ENGINEER AND ACCEPTED BY THE CITY OF LIBERTY HILL.

- 17. CONTACT CITY OF LIBERTY HILL PLANNING AND DEVELOPMENT DEPARTMENT (512) 548-5519 FOR ASSISTANCE IN OBTAINING EXISTING WATER AND WASTEWATER LOCATIONS.
- 18. THE CITY OF LIBERTY HILL FIRE DEPARTMENT SHALL BE NOTIFIED 48 HOURS PRIOR TO TESTING OF ANY BUILDING SPRINKLER PIPING IN ORDER THAT THE FIRE DEPARTMENT MAY MONITOR SUCH TESTING.
- 19. SAND, AS DESCRIBED IN SPECIFICATION ITEM 510 PIPE, SHALL NOT BE USED AS BEDDING FOR WATER AND WASTEWATER LINES. ACCEPTABLE BEDDING MATERIALS ARE PIPE BEDDING STONE, PEA GRAVEL AND IN LIEU OF SAND, A NATURALLY OCCURRING OR MANUFACTURED STONE MATERIAL CONFORMING TO ASTM C33 FOR STONE QUALITY AND MEETING THE FOLLOWING GRADATION SPECIFICATION:

SIEVE SIZE	PERCENT RETAINED BY WEIG
1/2"	0
3/8"	0-2
#4	40-85
#10	95-100

- 20. THE CONTRACTOR IS HEREBY NOTIFIED THAT CONNECTING TO, SHUTTING DOWN, OR TERMINATING EXISTING UTILITY LINES MAY HAVE TO OCCUR AT OFF-PEAK HOURS. SUCH HOURS ARE USUALLY OUTSIDE NORMAL WORKING HOURS AND POSSIBLY BETWEEN 12 A.M. AND 6 A.M.
- 21. ALL WASTEWATER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) REGULATIONS, 30 TAC CHAPTER 213 AND 317, AS APPLICABLE. WHENEVER TCEQ AND CITY OF ROUND ROCK SPECIFICATIONS CONFLICT, THE MORE STRINGENT SHALL

# TRAFFIC MARKING NOTES:

- 1. ANY METHODS, STREET MARKINGS AND SIGNAGE NECESSARY FOR WARNING MOTORISTS, WARNING PEDESTRIANS OR DIVERTING TRAFFIC DURING CONSTRUCTION SHALL CONFORM TO THE TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION.
- 2. ALL PAVEMENT MARKINGS, MARKERS, PAINT, TRAFFIC BUTTONS, TRAFFIC CONTROLS AND SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES AND, THE TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITIONS.

# **EROSION AND SEDIMENTATION CONTROL NOTES:**


- 1. EROSION CONTROL MEASURES, SITE WORK AND RESTORATION WORK SHALL COMPLY WITH CHAPTER 5 OF THE UDC.
- 2. ALL SLOPES SHALL BE SODDED OR SEEDED WITH APPROVED GRASS, GRASS MIXTURES OR GROUND COVER SUITABLE TO THE AREA AND SEASON IN WHICH THEY ARE APPLIED.
- 3. SILT FENCES, ROCK BERMS, SEDIMENTATION BASINS AND SIMILARLY RECOGNIZED TECHNIQUES AND MATERIALS SHALL BE EMPLOYED DURING CONSTRUCTION TO PREVENT POINT SOURCE SEDIMENTATION LOADING OF DOWNSTREAM FACILITIES. SUCH INSTALLATION SHALL BE REGULARLY INSPECTED BY THE CITY OF LIBERTY HILL FOR EFFECTIVENESS. ADDITIONAL MEASURES MAY BE REQUIRED IF, IN THE OPINION OF THE CITY ENGINEER, THEY ARE WARRANTED.
- 4. ALL TEMPORARY EROSION CONTROL MEASURES SHALL NOT BE REMOVED UNTIL FINAL INSPECTION AND APPROVAL OF THE PROJECT BY THE ENGINEER. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN ALL TEMPORARY EROSION CONTROL STRUCTURES AND TO REMOVE EACH STRUCTURE AS APPROVED BY THE ENGINEER.
- 5. ALL MUD, DIRT, ROCKS, DEBRIS, ETC., SPILLED, TRACKED OR OTHERWISE DEPOSITED ON EXISTING PAVED STREETS, DRIVES AND AREAS USED BY THE PUBLIC SHALL BE CLEANED UP IMMEDIATELY.

POTABLE WATER LINES CONSTRUCTED AND SHALL PROVIDE ALL EQUIPMENT CHLORINE DISINFECTING MATERIAL), AND NECESSARY LABOR REQUIRED FOR THE STERILIZATION PROCEDURE. THE STERILIZATION PROCEDURE SHALL BE MONITORED BY CITY OF ROUND ROCK PERSONNEL. WATER SAMPLES WILL BE FINAL ACCEPTANCE BY THE CITY OF ROUND ROCK.



ELOPMENT HILL, TX 7 (L) Ш 0 Z U U  $\sim$ 

SHEET



# **GUNNER NE MULTI-FAMILY** SUBDIVISION

12.934 ACRES OUT OF THE JOHN B. ROBINSON SURVEY, ABSTRACT NO. 521, IN WILLIAMSON COUNTY, TEXAS

OWNER: 212 GUNNER, LTD **ACREAGE: 12.934** PATENT SURVEY: JOHN B. ROBINSON, ABS. 521

SURVEYOR: ABRAM DASHNER, RPLS **ENGINEER: ANTHONY GOODE** NUMBER OF BLOCKS: SUBMITTAL DATE: 3/7/2022 ACREAGE BY LOT TYPE: MULTI-FAMILY DEVELOPMENT: 12.638

NUMBER OF LOTS BY TYPE: MULTI-FAMILY DEVELOPMENT - 1

R.O.W. RESERVE: 0.296

R.O.W. RESERVE — 1

SUBDIVISIO

**MULTI-FAMIL** UNNER

O REVISED: 6/16/23 DRAWN BY: TRS SURVEY DATE: 3/13/23

1"=100' SCALE: SHEET

ISSUE DATE: 2/10/23

STATE OF TEXAS COUNTY OF WILLIAMSON

THAT, 212 GUNNER, LTD., AS THE OWNER OF THE CERTAIN 12.934 ACRE TRACT SHOWN HEREON, BEING A PORTION OF THAT CERTAIN 73.5850 ACRE TRACT OF LAND RECORDED IN DOCUMENT NO. 2020007536, OF THE OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS DO HEREBY CERTIFY THAT THERE ARE NO LIEN HOLDERS AND DEDICATE TO THE PUBLIC FOREVER USE OF THE STREETS, ALLEYS, EASEMENTS AND ALL OTHER LANDS INTENDED FOR PUBLIC DEDICATION AS SHOWN HEREON TO BE KNOWN AS

GUNNER NE MULTI-FAMILY SUBDIVISION

10800 PECAN PARK BLVD., SUITE 125 AUSTIN, TEXAS 78750

THE STATE OF TEXAS COUNTY OF WILLIAMSON §

THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON THE  $20\pm0$ 

NOTARY PUBLIC, STATE OF TEXAS



# ENGINEER'S CERTIFICATION:

THE STATE OF TEXAS COUNTY OF WILLIAMSON

THAT I, ANTHONY GOODE, DO HEREBY CERTIFY THAT THE INFORMATION CONTAINED ON THIS PLAT COMPLIES WITH CHAPTER 5, SUBDIVISIONS, PUBLIC IMPROVEMENTS CITY OF LIBERTY HILL UNIFIED DEVELOPMENT CODE, AND THE DESIGN AND CONSTRUCTION STANDARDS ADOPTED BY THE CITY OF LIBERTY HILL, TEXAS.

ANTHONY GOODE, P.E. NO. 97263 GOODE FAITH ENGINEERING, LLC TBPE FIRM NO. F-22664 1620 LA JAITA DR. SUITE 300, CEDAR PARK, TEXAS, 78613 (972) 822-1682



# CITY CERTIFICATION

I, JERRY L. MILLARD, JR. INTERIM DIRECTOR OF PLANNING, DESIGNEE, OF THE CITY OF LIBERTY HILL, TEXAS, UNDER THE AUTHORITY GRANTED ME IN SECTION 3.09.02 OF THE UNIFIED DEVELOPMENT CODE, AND IN ACCORDANCE WITH CHAPTER 212 OF THE TEXAS LOCAL GOV'T CODE. DO HEREBY CERTIFY THIS PLAT AS APPROVED FOR FILING OF RECORD WITH THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS.

6-72-23

# **GENERAL NOTES:**

1. THIS SUBDIVISION IS WHOLLY CONTAINED WITHIN THE CURRENT CORPORATE LIMITS OF THE CITY OF LIBERTY HILL, TEXAS. (INSIDE CITY ONLY)

2. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO PERMITTED WATER DISTRIBUTION AND WASTEWATER COLLECTION FACILITIES.

3. A BUILDING PERMIT IS REQUIRED FROM THE CITY OF LIBERTY HILL PRIOR TO CONSTRUCTION OF ANY BUILDING OR SITE IMPROVEMENTS ON ANY LOT IN THIS SUBDIVISION.

4. NO BUILDINGS, FENCES, LANDSCAPING OR OTHER STRUCTURES ARE PERMITTED WITHIN DRAINAGE EASEMENTS SHOWN EXCEPT AS APPROVED BY THE CITY OF LIBERTY HILL PUBLIC WORKS DEPARTMENT.

5. PROPERTY OWNER SHALL PROVIDE FOR ACCESS TO DRAINAGE EASEMENTS AS MAY BE NECESSARY AND SHALL NOT PROHIBIT ACCESS BY THE CITY OF LIBERTY HILL.

6. ALL EASEMENTS ON PRIVATE PROPERTY THAT ARE GRANTED HEREIN, IF ANY, SHALL BE MAINTAINED BY THE PROPERTY OWNER OR HIS OR HER ASSIGNS, EXCEPT THAT ANY UTILITY LINES OR FACILITIES INSTALLED IN ANY PUBLIC UTILITY EASEMENT SHALL BE MAINTAINED BY THE PUBLIC UTILITY THAT INSTALLED SUCH UTILITY LINES OF FACILITIES...

7. IN ADDITION TO THE EASEMENT SHOWN HEREON, A TEN (10') FOOT WIDE PUBLIC UTILITY EASEMENT IS DEDICATED ALONG AND ADJACENT TO ALL RIGHT-OF-WAY AND A TWO AND A HALF (2.5') FOOT WIDE PUBLIC UTILITY EASEMENT IS DEDICATED ALONG ALL SIDE LOT LINES.

8. NO PORTION OF THIS TRACT IS WITHIN A FLOOD HAZARD AREA AS SHOWN ON THE FLOOD INSURANCE RATE MAP PANEL #48491C0275E FOR WILLIAMSON CO., EFFECTIVE SEPTEMBER 26,

9. BUILDING SETBACKS NOT SHOWN HEREON SHALL COMPLY WITH THE MOST CURRENT ZONING ORDINANCE OF THE CITY OF LIBERTY HILL.

10. SIDEWALKS SHALL BE INSTALLED ON THE SUBDIVISION SIDE OF GRACIE LANE AND S.H. 29 (INCLUDING SIDEWALKS ALONG STREET FRONTAGES OF LOTS PROPOSED FOR SCHOOLS, CHURCHES, PARK LOTS, DETENTION LOTS, DRAINAGE LOTS, LANDSCAPE LOTS, OR SIMILAR LOTS), SIDEWALKS ON ARTERIAL STREETS TO WHICH ACCESS IS PROHIBITED, SIDEWALKS ON DOUBLE FRONTAGE LOTS ON THE SIDE TO WHICH ACCESS IS PROHIBITED, AND ALL SIDEWALKS ON SAFE SCHOOL ROUTES SHALL BE INSTALLED WHEN THE ADJOINING STREET IS

11. ALL UTILITY LINES MUST BE LOCATED UNDERGROUND.

12. ALL DRIVE LANES, FIRE LANES, AND DRIVEWAYS WITHIN THIS SUBDIVISION SHALL PROVIDE FOR RECIPROCAL ACCESS FOR INGRESS AND EGRESS TO ALL OTHER LOTS WITHIN THE

# **SURVEYOR'S CERTIFICATION:**

THE STATE OF TEXAS COUNTY OF TRAVIS

THAT I, ABRAM C. DASHNER, DO HEREBY CERTIFY THAT I PREPARED THIS PLAT FROM AN ACTUAL AND ACCURATE ON-THE-GROUND SURVEY OF THE LAND AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPERLY PLACED UNDER MY PERSONAL SUPERVISION, IN ACCORDANCE WITH CHAPTER 5, SUBDIVISIONS, PUBLIC IMPROVEMENTS, CITY OF LIBERTY HILL UNIFIED DEVELOPMENT CODE, THAT ALL EASEMENTS OF RECORD (AS FOUND ON THE MOST RECENT TITLE POLICY ISSUED FOR THE SUBJECT PROPERTY) ARE PLOTTED OR NOTED HEREON, IN CONFORMANCE WITH THE LIBERTY HILL SUBDIVISION ORDINANCE.

RPLS NO. 5901 6448 E HWY 290, STE. B-105 AUSTIN, TX 78723



#### LEGAL DESCRIPTION:

12.934 ACRES OUT OF THE JOHN B. ROBINSON SURVEY, ABSTRACT NO. 521, IN WILLIAMSON COUNTY, TEXAS, BEING A PORTION OF THAT CERTAIN 73.5850 ACRE TRACT CONVEYED TO 212 GUNNER LTD, BY DEED OF RECORD IN DOCUMENT NO. 2020007536, OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS; SAID 12.934 ACRE TRACT BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING, AT A 1/2-INCH IRON ROD FOUND IN THE WEST LINE OF THAT CERTAIN 14.200 ACRE TRACT CONVEYED TO PEDERNALES ELECTRIC COOPERATIVE, INC., BY DEED OF RECORD IN DOCUMENT NO. 2020062257, OF SAID OFFICIAL PUBLIC RECORDS, BEING AN ANGLE POINT IN THE SOUTH RIGHT-OF-WAY LINE OF SH 29 (R.O.W. VARIES), ALSO BEING THE NORTHEAST CORNER OF SAID 73.5850 ACRE TRACT. FOR THE NORTHEASTERLY CORNER HEREOF:

THENCE, S20'30'56'E, LEAVING SAID SOUTH RIGHT-OF-WAY LINE OF SH 29, ALONG THE WEST LINE OF SAID 14.200 ACRE TRACT, BEING THE EAST LINE OF SAID 73.5850 ACRE TRACT, A DISTANCE OF 395.74 FEET TO A 1/2-INCH IRON ROD WITH "MANHARD CONSULTING" CAP SET, FOR THE SOUTHEASTERLY CORNER HEREOF;

THENCE, LEAVING THE WEST LINE OF SAID 14.200 ACRE TRACT, OVER AND ACROSS SAID 73.5850 ACRE TRACT, THE FOLLOWING TWO (2) COURSES AND DISTANCES:

- S68°45°42"W, A DISTANCE OF 1128.04 FEET TO A 1/2-INCH IRON ROD WITH "MANHARD CONSULTING" CAP SET, FOR THE SOUTHWESTERLY CORNER HEREOF;
- 2. N20'09'39"W, A DISTANCE OF 530.86 FEET TO A CALCULATED POINT IN THE NORTH LINE OF SAID 73.5850 ACRE TRACT, BEING THE SOUTH LINE OF THAT CERTAIN 33.9575 ACRE TRACT CONVEYED TO HENRIETTA 212 LLC, BY DEED OF RECORD IN DOCUMENT NO. 2019003562, OF SAID OFFICIAL PUBLIC RECORDS, FOR THE

THENCE, ALONG THE SOUTH LINE OF SAID 33.9575 ACRE TRACT, BEING THE NORTH LINE OF SAID 73.5850 ACRE TRACT, THE FOLLOWING TWO (2) COURSES AND DISTANCES:

- N68'57'29'E, A DISTANCE OF 52.46 FEET TO A 1/2-INCH IRON ROD FOUND AT THE POINT OF CURVATURE OF A CURVE TO THE LEFT:
- 2. ALONG SAID CURVE, HAVING A RADIUS OF 435.00 FEET, A CENTRAL ANGLE OF 39°34'04", AN ARC LENGTH OF 300.41 FEET, AND A CHORD WHICH BEARS N49°09'56'E, A DISTANCE OF 294.47 FEET TO A CALCULATED POINT AT THE END OF SAID CURVE:

THENCE, LEAVING THE SOUTH LINE OF SAID 33.9575 ACRE TRACT, OVER AND ACROSS SAID 73.5850 ACRE TRACT, THE FOLLOWING TWO (2) COURSES AND DISTANCES:

- 1. S71"36'22"E, A DISTANCE OF 468.92 FEET TO A 1/2-INCH IRON ROD WITH "MANHARD CONSULTING" CAP SET,
- N17"46"28"E, A DISTANCE OF 325.87 FEET TO A 1/2-INCH IRON ROD WITH "MANHARD CONSULTING" CAP SET IN THE NORTH LINE OF SAID 73.5850 ACRE TRACT, BEING SAID SOUTH RIGHT-OF-WAY LINE OF SH 29, FOR AN

THENCE, S71°38'05'E, ALONG SAID SOUTH RIGHT-OF-WAY LINE, BEING THE NORTH LINE OF SAID 73.5850 ACRE TRACT, A DISTANCE OF 294.49 FEET TO THE POINT OF BEGINNING, AND CONTAINING 12.934 ACRES (563,392 SQUARE FEET) OF LAND, MORE OR LESS.

# WILLIAMSON COUNTY CLERK RECORDATION CERTIFICATION:

THE STATE OF TEXAS § COUNTY OF WILLIAMSON §

THAT I. NANCY RISTER. CLERK OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT IN WRITING, WITH ITS CERTIFICATION OF AUTHENTICATION, WAS FILED FOR RECORD IN MY OFFICE ON


A.D., 202**2**, AT <u>10:30</u> O'CLOCK <u>A</u>M. AND DULY RECORDED ON THE 24 DAY OF \_\_\_\_\_\_\_


AT 10:40 O'CLOCK A.M. IN THE PLAT RECORDS OF SAID COUNTY, IN DOCUMENT


NO. 202301010 ... WITNESS MY HAND AND SEAL OF THE COUNTY COURT OF SAID COUNTY, AT OFFICE IN GEORGETOWN, TEXAS, THE DATE LAST ABOVE WRITTEN.


NANCY RISTER, CLERK, COUNTY COURT WILLIAMSON COUNTY, TEXAS











S

Ш


GROUP

OR

**ENDEAV** 

2

MF DEVELOPMENT LIBERTY HILL, TX 7864




92792


S


 $\overline{\Omega}$ 


OR


N N

















OF

33

92792

MF DEVELOPMENT LIBERTY HILL, TX 7864

LIBERTY HILL GRACIE LANE


2


GROUP


**ESTATE** 


2


ENDEAVOR




















GROUI

OR


END









JUNCTION BOX A NTS





CONTROL MANHOLE MAY BE 36" HDPE OR OTHER EQUIVALENT, AS LONG AS THEIR IS MAINTENANCE ACCESS

-SECURED MANHOLE



OF

33


LIBERTY HILL MF DEVELOPMENT 250 GRACIE LANE LIBERTY HILL, TX 78642

ENDEAVOR REAL ESTATE GROUP

STOR	M SYS	TEM D	ESIGN								
	ject Name:										
Proje	ct Number:	2024-4-	SDP								
Entry Number	Outfall Elevation inv.(in)	Line Number	Line Size diameter (inches)	Line Length (C-C ft.)	Line Slope (ft/ft)	Manhole inv.(out)	Number inv.(in)	Full Flow Line Capacity n=.011 (cfs)	Full Flow Velocity (fps)	Design Flow (25 YR) (cfs)	Percent of Line Capacity (%)
A1	975.00	1	36	12.00	0.005	975.06	975.06	55.7	7.9	45.7	82.0%
A2	975.06	2	30	194	0.005	976.03	976.03	34.3	7.0	32.4	94.5%
A3	976.03	3	2-24	170	0.005	976.88	976.88	27.0	6.0	22.4	1 05 70/
AS	976.03	4	2-24	170	0.005	970.88	970.86	37.8	6.0	32.4	85.7%
A4	976.88	5	2-24	79	0.005	977.28	977.28	37.8	6.0	22	58.2%
A5	977.28	3	18	271	0.01	979.99	979.99	12.4	7.0	7.5	60.5%
A6	979.99	6	12	121	0.02	982.40	982.4	6.0	7.6	2.1	35.3%
A7	982.40	7	8	25	0.01	982.66		1.4	4.1	0.9	62.9%
A2-1	975.06	8	18	96	0.01	976.02	976.02	12.4	7.0	3.9	31.5%
A2-2	976.02	9	12	143	0.005	976.74		3.0	3.8	2.3	77.2%
		10									
A3-1	977.28	11	24 ]	136	0.005	977.95	977.95	18.9	6.0	14.5	76.7%
A3-2	977.95		18	187	0.01	979.83		12.4	7.0	11.8	95.2%
A4-1	979.99	12	12	46	0.005	980.22		3.0	3.8	1	33.3%
B1	975	13	36	26	0.005	975.13	975.13	55.7	7.9	35.1	63.0%
B2	975.13	14	30	124	0.01	976.36	976.36	48.5	9.7	32.1	66.2%
B3	976.36	15	30	151	0.01	977.88	977.88	48.5	9.7	30.2	62.3%
		16									
B4	977.88	17	24 ]	119	0.005	978.47	978.47	18.9	6.0	16.9	89.4%
B5	978.47	18	18	99	0.005	978.97	978.97	8.8	5.0	8.3	94.3%
В6	978.97		18	99	0.005	979.46	979.46	8.8	5.0	7	79.5%
В7	979.46	19	18	141	0.005	980.17		8.8	5.0	4.1	46.6%
B1-1	979.87	20	12	11	0.01	979.07		4.2	5.4	1.3	31.0%
B2-1	976.36	21	12	47	0.01	976.84		4.2	5.4	1.9	45.2%
B3-1	978.47	22	12	11	0.01	978.58		4.2	5.4	8.6	204.8%
		23									
B4-1	979.46	24	12	11	0.01	979.57		4.2	5.4	2.9	69.0%
C1	977.88	25	24	327	0.01	981.15	981.15	26.7	8.5	13.3	49.8%
C2	981.15		18	93	0.02	983.01	983.01	17.6	9.9	6.6	37.5%
C3	983.01	26	18	100	0.02	985.02		17.6	9.9	0.5	2.8%
C2-1	983.01	27	18	20	0.01	983.21		12.1	7.0	6.1	50.4%

Pro	ject Name:	Liberty	Hill MF												
	ct Number:	_													
Entry	Outfall	Line	Line Size	Line	Line			Full Flow Line Capacity		Design	Percent of Line	area of	Wetted	Hydraulic	
Number	Elevation inv.(in)	Number	diameter (inches)	Length (C-C ft.)	Slope (ft/ft)	Manhole inv.(out)	inv.(in)	n=.013 (gpm)	Velocity (fps)	Flow (gpm)	Capacity (%)	line (sf)	Perimeter (ft)	Radius (A/wp)	Qc (c
	1114.(111)		_ (11101103)	(0 0 11.)	(let let	iiiv.(out)	1114. (111)	(90111)	(100)	(9711)	(70)	(31)	(11.)	(7 tr trp)	
A1	964.82	1	10	140.00	0.0189	967.46	967.56	1355	5.5	738	54.4%	0.55	2.62	0.21	3.
	904.02	2	7	140.00	0.0109	907.40	907.30	1	5.5	730	34.470	0.55	2.02	0.21	J.
A2	967.56	2	10	221	0.0174	971.40	971.5	1301	5.3	738	56.7%	0.55	2.62	0.21	2.
		3	 1					1	'		_				
А3	971.5	<u> </u>	8	311	0.0069	973.64	973.74	452	2.9	330	73.1%	0.35	2.09	0.17	1.
		4	1					- 1							
A4	973.74	7	8	56	0.0083	974.20	974.3	495	3.2	330	66.6%	0.35	2.09	0.17	1.
		5	1					- 1			_				
A5	974.3		8	175	0.006	975.34	975.34	421	2.7	330	78.3%	0.35	2.09	0.17	0
		6	1					1							
A6	975.34	<u> </u>	8	177	0.006	976.40	978.4	421	2.7	220	52.2%	0.35	2.09	0.17	0
		7	1					1							
<b>A</b> 7	978.4	1	6	78	0.0624	983.29	983.29	631	7.2	110	17.4%	0.20	1.57	0.13	1.
		8	1					1							
A8	983.29		6	7	0.026	983.47	983.47	407	4.6	110	27.0%	0.20	1.57	0.13	0.
		9	1					1							
A9	983.47		6	39	0.026	984.50		407	4.6	110	27.0%	0.20	1.57	0.13	0
		10	1					1							
B1	971.5		6	90	0.0499	976.00		564	6.4	195	34.6%	0.20	1.57	0.13	1
		11	1					1							
C1	971.5		6	231	0.0227	976.75	976.85	380	4.3	213	56.0%	0.20	1.57	0.13	0
		12	1					1							
C2	976.85		6	158	0.0265	981.05	981.05	411	4.7	18	4.4%	0.20	1.57	0.13	0.
		13	]					]							
C3	981.05		6	16	0.0265	981.46	981.46	411	4.7	18	4.4%	0.20	1.57	0.13	0.
		14	]					]							
C4	981.46		6	28	0.0265	982.20		411	4.7	18	4.4%	0.20	1.57	0.13	0.
		15	1					]							
D1	976.85		6	30	0.0613	978.70		625	7.1	195	31.2%	0.20	1.57	0.13	1.
		16	1					]							
E1	975.34		6	43	0.0613	978.00		625	7.1	110	17.6%	0.20	1.57	0.13	1.
		17	]					]							
F1	976.4		6	107	0.0524	982.00		578	6.6	110	19.0%	0.20	1.57	0.13	1.

**Garza**7708 Rialto Blvd., Suite 125
Austin, Texas 78735
Tel. (512) 298-3284 Fax (512) 298-25
TBPE # F-14629



TILITY CALCULATION

LIBERTY HILL MF DEVELOPMENT
250 GRACIE LANE LIBERTY HILL, TX 78642
ENDEAVOR REAL ESTATE GROUP

DESIGNED BY
THE CALCE B. AL
PROJECT NO.

33

#### Agent Authorization Form

For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Ĭ	Jason Thumlert	1
***************************************	Print Name	
	Executive Vice President	,
	Title - Owner/President/Other	
of	OP III ATX Liberty Hill 183, LP Corporation/Partnership/Entity Name	
have authorized Bilal Aliza	Print Name of Agent/Engineer	-
of Garza EMC	Print Name of Firm	_

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

#### I also understand that:

- The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- Application fees are due and payable at the time the application is submitted. The
  application fee must be sent to the TCEQ cashier or to the appropriate regional office.
  The application will not be considered until the correct fee is received by the
  commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

#### SIGNATURE PAGE:

Applicant's Signature

4/25/2024 Date

THE STATE OF \_Texas \_ §

County of \_\_\_\_ Travis \_\_\_ §

BEFORE ME, the undersigned authority, on this day personally appeared <u>Jason Thumlert</u> known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 25th day of April , 2024.

JESSIE RUSK Notary ID #132903161 My Commission Expires February 1, 2025 NOTARY PUBLIC

Jessie Wisk

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: February 1, 2025

# **Application Fee Form**

#### **Texas Commission on Environmental Quality** Name of Proposed Regulated Entity: Liberty Hill MF Development Regulated Entity Location: 250 Gracie Ln, Liberty Hill, TX Name of Customer: OP III ATX LIBERTY HILL 183 LP Contact Person: Collin Aufhammer Phone: <u>512-76</u>1-1814 Customer Reference Number (if issued):CN Regulated Entity Reference Number (if issued):RN \_\_\_\_\_\_ **Austin Regional Office (3373)** Havs Travis X Williamson San Antonio Regional Office (3362) Medina Uvalde Bexar Comal Kinney Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: X Austin Regional Office San Antonio Regional Office Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier **Revenues Section** 12100 Park 35 Circle Mail Code 214 Building A, 3rd Floor P.O. Box 13088 Austin, TX 78753 Austin, TX 78711-3088 (512)239-0357 Site Location (Check All That Apply): X Contributing Zone **Transition Zone** Recharge Zone Type of Plan Size Fee Due Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling Acres Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks Acres Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential 12.638 Acres | \$ 6,500 L.F. \$ Sewage Collection System Lift Stations without sewer lines Acres \$ Underground or Aboveground Storage Tank Facility Tanks | \$ Each \$ Piping System(s)(only) Each | \$ Exception Each | \$ Extension of Time

Date: <u>05-07-2024</u>

Signature: Triul Alizi

## **Application Fee Schedule**

**Texas Commission on Environmental Quality** 

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

#### Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
	710703	
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

# Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

**Exception Requests** 

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



# **TCEQ Core Data Form**

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

#### **SECTION I: General Information**

**1. Reason for Submission** (*If other is checked please describe in space provided.*)

New Pern	nit, Registra	ation or Authorization	(Core Data Fo	orm should be s	submitte	d with	the prog	ram application.)			
Renewal (Core Data Form should be submitted with the renewal form)					ther						
2. Customer I	Customer Reference Number (if issued)  Follow this link to search for CN or RN numbers in				3. Re	gulated Entity Re	ference	Number (if i	ssued)		
CN	Central Registry**  RN										
ECTIO	N II:	Customer	Infor	<u>mation</u>	<u>l</u>						
4. General Customer Information 5. Effective Date for Customer Information Updates (mm/dd/yyyy)					04/25/2024						
New Custor	mer		pdate to Cus	tomer Informat	tion		Chai	nge in Regulated En	tity Own	ership	
 Change in Le	egal Name	(Verifiable with the Te	-			otroller	of Publ	c Accounts)	•	•	
The Custome	r Name su	ubmitted here may l	be updated	automaticali	ly based	d on w	hat is c	urrent and active	with th	he Texas Sec	retary of State
		oller of Public Accoเ	-								, ,
6. Customer I	Legal Nan	ne (If an individual, pri	nt last name <sub>.</sub>	first: eg: Doe, J	lohn)			If new Customer,	enter pr	evious Custom	er below:
OP III ATX LIBEI	RTY HILL 18	33, LP									
7. TX SOS/CP	A Filing N	umber	8. TX State	<b>e Tax ID</b> (11 d	ligits)			9. Federal Tax ID 10. DUNS Number (if			
305137918								(9 digits)			
505157916							(5 digits)				
								92-2298493			
L1. Type of C	ustomer:	☐ Corporat	ion				Individ	lual	Partne	ership: 🔲 Gen	eral 🛛 Limited
		County  Federal	Local 🗌 Sta	ite 🗌 Other			Sole P	roprietorship	Ot	her:	
12. Number o								13. Independer	ntly Ow	ned and Ope	erated?
☑ 0-20     2	21-100	] 101-250   251-	500 🗌 50	1 and higher				☐ Yes	⊠ No		
14. Customer	<b>Role</b> (Pro	posed or Actual) – as i	t relates to th	ne Regulated Er	ntity liste	d on th	nis form.	Please check one o	f the follo	owing	
⊠Owner		Operator		Owner & Opera	ntor						
Occupation	al Licensee			VCP/BSA App				☐ Other:			
15 Mailine	500 W 5 <sup>t</sup>	h ST									
15. Mailing SUITE 700											
Address:	City	AUSTIN		State	TX		ZIP	78701		ZIP + 4	
L6. Country N	Mailing In	formation (if outside	USA)			17. E-	-Mail A	l ddress (if applicabl	e)	l	
						CAUF	HAMME	R@ENDEAVOR-RE.C	OM		
L8. Telephon	o Numbo	•		19. Extensio	on or Co	do		20 Eav N	umber	(if applicable)	

TCEQ-10400 (11/22) Page 1 of 3

( 512 ) 761-1848		( ) -
------------------	--	-------

## **SECTION III: Regulated Entity Information**

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)														
☑ New Regulated Entity ☐ Update to Regulated Entity Name ☐ Update to Regulated Entity Information														
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).														
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)														
LIBERTY HILL MF DEVELOPMENT														
23. Street Address of the Regulated Entity:	250 GRACIE	250 GRACIE LN												
(No PO Boxes)		Т		T	T	ı		T	1					
(NOTO BOXES)	City	LIBERTY HILL	State	TX	ZIP	78642	2	ZIP + 4						
24. County	WILLIAMSO	N												
		If no Stre	et Address is provi	ded, fields 2	5-28 are re	equired.								
25. Description to														
Physical Location:														
26. Nearest City						State		Nea	rest ZIP Code					
Latitude/Longitude are re used to supply coordinate	-	-			ata Stand	ards. (G	eocoding of ti	he Physical	Address may be					
27. Latitude (N) In Decim	al:			28. L	ongitude (\	W) In De	cimal:							
Degrees	Minutes		Seconds	Degre	es		Minutes		Seconds					
29. Primary SIC Code	30.	Secondary SIC	Code	31. Primar	y NAICS Co	ode	32. Seco	ondary NAIC	CS Code					
(4 digits)	(4 d	igits)		(5 or 6 digit	:s)		(5 or 6 dig	gits)						
6513				531110										
33. What is the Primary E	Business of t	his entity? (D	o not repeat the SIC o	r NAICS descr	iption.)									
MULTI-FAMILY APARTMENT	MULTI-FAMILY APARTMENT RESIDENTIAL													
	THE STOP ET THE							250 GRACIE LN						
34. Mailing		E LN												
34. Mailing		E LN												
34. Mailing Address:		LIBERTY HILL	State	тх	ZIP	78642	2	ZIP + 4						
-	250 GRACI	LIBERTY HILL	State DEAVOR-RE.COM	тх	ZIP	78642	2	ZIP + 4						
Address:	250 GRACI	LIBERTY HILL					2 aber (if applical							
Address:  35. E-Mail Address:	250 GRACI	LIBERTY HILL	DEAVOR-RE.COM											

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety	Districts	☑ Edwards Aquifer	Emissions Inventory Air	☐ Industrial Hazardous Waste
Municipal Solid Waste	New Source Review Air	OSSF	Petroleum Storage Tank	□ PWS
Sludge	Storm Water	☐ Title V Air	Tires	Used Oil
☐ Voluntary Cleanup	Wastewater	Wastewater Agriculture	☐ Water Rights	Other:
SECTION TV: Dr	enarer Info	ormation		

40. Name:	PRESLEY GOOD	)		41. Title:	PROJECT ENGINEER	
42. Telephone	Number	43. Ext./Code	44. Fax Number	45. E-Mail Address		
(713)491-6039			( ) -	PGOOD@GA	RZAEMC.COM	

#### **SECTION V: Authorized Signature**

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	GARZA EMC	MANAGER			
Name (In Print):	BILAL ALIZAI	Phone:	( 713 ) 491- <b>6039</b>		
Signature:	Fill Alizi			Date:	05-07-2024

TCEQ-10400 (11/22) Page 3 of 3