

# **CONTRIBUTING ZONE PLAN MODIFICATION**

## **WORLDSPRINGS AUSTIN Cedar Park, Williamson County, TEXAS**

*Prepared For:*

### **Worldsprings Austin**

3110 Woodcreek Drive  
Downers Grove, IL 60515

*Prepared By:*

### **KIMLEY-HORN AND ASSOCIATES, INC.**

6800 Burleson Rd, Bldg 312, Suite 150  
Austin, TX 78744  
(512) 616-9942

Firm No. 928  
KHA Project No. 0694274007

**JUNE 2024**

# TABLE OF CONTENTS

<b>EDWARDS AQUIFER APPLICATION COVER PAGE.....</b>	<b>SECTION 1</b>
EDWARDS AQUIFER APPLICATION COVER PAGE.....	TCEQ-20705
<b>Modification of a Previously Approved Contributing Zone Plan.....</b>	<b>SECTION 2</b>
Original Approval Letter and Approved Modification Letters.....	Attachment A
Narrative of Proposed Modification.....	Attachment B
Current Site Plan of the Approved Project.....	Attachment C
<b>Contributing Zone Plan Application.....</b>	<b>SECTION 3</b>
CONTRIBUTING ZONE PLAN APPLICATION.....	TCEQ-10257
Road Map.....	Attachment A
USGS Quadrangle Map.....	Attachment B
Project Narrative.....	Attachment C
Factors Affecting Surface Water Quality.....	Attachment D
Volume and Character of Stormwater.....	Attachment E
Suitability Letter from Authorized Agent.....	Attachment F
Alternative Secondary Containment Methods.....	Attachment G (N/A)
AST Containment Structure Drawings.....	Attachment H (N/A)
20% or Less Impervious Cover Waiver.....	Attachment I (N/A)
BMPs for Upgradient Stormwater.....	Attachment J
BMPs for On-site Stormwater.....	Attachment K
BMPs for Surface Streams.....	Attachment L
Construction Plans.....	Attachment M
Inspection, Maintenance, Repair and Retrofit Plan.....	Attachment N
Pilot-Scale Field Testing Plan.....	Attachment O (N/A)
Measures for Minimizing Surface Stream Contamination.....	Attachment P
<b>TEMPORARY STORMWATER SECTION.....</b>	<b>SECTION 4</b>
TEMPORARY STORMWATER SECTION.....	TCEQ0602
Spill Response Actions.....	Attachment A
Potential Source of Contamination.....	Attachment B
Sequence of Major Activities.....	Attachment C
Temporary Best Management Practices and Measures.....	Attachment D
Request to Temporarily Seal a Feature.....	Attachment E
Structural Practices.....	Attachment F
Drainage Area Map.....	Attachment G
Temporary Sediment Pond(s) Plans and Calculations.....	Attachment H
Inspection and Maintenance for BMPs.....	Attachment I
Schedule of Interim and permanent Soil Stabilization.....	Attachment J





**ADDITIONAL FORMS....SECTION 5**

AGENT AUTHORIZATION FORM.....	TCEQ-0599
APPLICATION FEE FORM.....	TCEQ-0574
CORE DATA FORM.....	TCEQ-10400

***SECTION 1:  
EDWARDS AQUIFER APPLICATION  
COVER PAGE***

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> New Hope - West Phase					<b>2. Regulated Entity No.:</b> 111875886				
<b>3. Customer Name:</b> New Hope Land, LP					<b>4. Customer No.:</b> 606043032				
<b>5. Project Type:</b> (Please circle/check one)	New	Modification			Extension	Exception			
<b>6. Plan Type:</b> (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	Residential	Non-residential				<b>8. Site (acres):</b>		8.00	
<b>9. Application Fee:</b>	\$5,000	<b>10. Permanent BMP(s):</b>				N/A - existing regional water quality/detention pond			
<b>11. SCS (Linear Ft.):</b>	N/A	<b>12. AST/UST (No. Tanks):</b>				N/A			
<b>13. County:</b>	Williamson	<b>14. Watershed:</b>				Cottonwood Creek			

# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	<u>X</u>
Region (1 req.)	—	—	<u>X</u>
County(ies)	—	—	<u>X</u>
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Barton Springs/ Edwards Aquifer <u>—</u> Hays Trinity <u>—</u> Plum Creek	<u>—</u> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<u>—</u> Austin <u>—</u> Buda <u>—</u> Dripping Springs <u>—</u> Kyle <u>—</u> Mountain City <u>—</u> San Marcos <u>—</u> Wimberley <u>—</u> Woodcreek	<u>—</u> Austin <u>—</u> Bee Cave <u>—</u> Pflugerville <u>—</u> Rollingwood <u>—</u> Round Rock <u>—</u> Sunset Valley <u>—</u> West Lake Hills	<u>—</u> Austin <u>X</u> Cedar Park <u>—</u> Florence <u>—</u> Georgetown <u>—</u> Jerrell <u>—</u> Leander <u>—</u> Liberty Hill <u>—</u> Pflugerville <u>—</u> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Trinity-Glen Rose	<u>—</u> Edwards Aquifer Authority	<u>—</u> Kinney	<u>—</u> EAA <u>—</u> Medina	<u>—</u> EAA <u>—</u> Uvalde
City(ies) Jurisdiction	<u>—</u> Castle Hills <u>—</u> Fair Oaks Ranch <u>—</u> Helotes <u>—</u> Hill Country Village <u>—</u> Hollywood Park <u>—</u> San Antonio (SAWS) <u>—</u> Shavano Park	<u>—</u> Bulverde <u>—</u> Fair Oaks Ranch <u>—</u> Garden Ridge <u>—</u> New Braunfels <u>—</u> Schertz	NA	<u>—</u> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Ryan McKay

Print Name of Customer/Authorized Agent



06/21/2024

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

***SECTION 2:  
MODIFICATION OF A PREVIOUSLY APPROVED  
CONTRIBUTING ZONE PLAN***

# Modification of a Previously Approved Contributing Zone Plan

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Modification of a Previously Approved Contributing Zone Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Ryan McKay

Date: 06/21/2024

Signature of Customer/Agent:



## Project Information

1. Current Regulated Entity Name: New Hope Land, LP  
Original Regulated Entity Name: New Hope Land, LP  
Assigned Regulated Entity Number(s) (RN): 111875886  
Edwards Aquifer Protection Program ID Number(s): 11003853  
☐ The applicant has not changed and the Customer Number (CN) is: \_\_\_\_\_  
☒ The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
2. ☒ **Attachment A: Original Approval Letter and Approved Modification Letters.** A copy of the original approval letter and copies of any modification approval letters are attached.
3. A modification of a previously approved plan is requested for (check all that apply):



- ☐ Any physical or operational modification of any best management practices or structure(s), including but not limited to temporary or permanent ponds, dams, berms, silt fences, and diversionary structures;
- ☐ Any change in the nature or character of the regulated activity from that which was originally approved;
- ☐ A change that would significantly impact the ability to prevent pollution of the Edwards Aquifer and hydrologically connected surface water; or
- ☐ Any development of land previously identified in a contributing zone plan as undeveloped.

4. ☒ **Summary of Proposed Modifications** (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

<b><i>CZP Modification</i></b>	<b><i>Approved Project</i></b>	<b><i>Proposed Modification</i></b>
<b><i>Summary</i></b>		
Acres	<u>32.01</u>	<u>N/A</u>
Type of Development	<u>Commercial</u>	<u>N/A</u>
Number of Residential Lots	<u>N/A</u>	<u>N/A</u>
Impervious Cover (acres)	<u>1.79</u>	<u>8.35</u>
Impervious Cover (%)	<u>5.59</u>	<u>26.1%</u>
Permanent BMPs	<u>Batch Detention Pond</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>
<b><i>AST Modification</i></b>		
<b><i>Summary</i></b>		
Number of ASTs	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>
<b><i>UST Modification</i></b>		
<b><i>Summary</i></b>		
Number of USTs	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>

5. ☒ **Attachment B: Narrative of Proposed Modification.** A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved,

including previous modifications, and how this proposed modification will change the approved plan.

6. ☒ **Attachment C: Current Site Plan of the Approved Project.** A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.
- ☐ The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.
- ☐ The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.
- ☐ The approved construction has commenced and has been completed. Attachment C illustrates that the site was **not** constructed as approved.
- ☒ The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was constructed as approved.
- ☐ The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was **not** constructed as approved.
7. ☐ Acreage has not been added to or removed from the approved plan.
- ☒ Acreage has been added to or removed from the approved plan and is discussed in *Attachment B: Narrative of Proposed Modification*.
8. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

**ATTACHMENT A: Original Approval Letter and Approved Modification Letters**

Jon Niermann, *Chairman*  
Bobby Janecka, *Commissioner*  
Catarina R. Gonzales, *Commissioner*  
Kelly Keel, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

March 15, 2024

Mr. Chris Whitworth  
New Hope Land, LP  
5515 Balcones Drive  
Austin, Texas 78731

Re: Approval of a Contributing Zone Plan (CZP)  
New Hope West Phase; NE of US 183A and East New Hope Drive, Williamson County  
Edwards Aquifer Protection Program ID: 11003853, Regulated Entity No. RN111875886

Dear Mr. Whitworth:

The Texas Commission on Environmental Quality (TCEQ) has completed its review on the application for the above-referenced project submitted to the Edwards Aquifer Protection Program (EAPP) by Malone Wheeler, Inc. on behalf of the applicant, New Hope Land, LP on January 9, 2024.

As presented to the TCEQ, the application was prepared in general compliance with the requirements of 30 Texas Administrative Codes (TAC) Chapter §213. The permanent best management practices (BMPs) and measures represented in the application were prepared by a Texas licensed professional engineer (PE). All construction plans and design information were sealed, signed, and dated by a Texas licensed PE. Therefore, the application for the construction of the proposed project and methods to protect the Edwards Aquifer are **approved**, subject to applicable state rules and the conditions in this letter.

**This approval expires two years from the date of this letter**, unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been officially requested. This approval or extension will expire, and no extension will be granted if more than 50 percent of the project has not been completed within ten years from the date of this letter.

The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer protection plan. A motion for reconsideration must be filed in accordance with 30 TAC §50.139.

### PROJECT DESCRIPTION

The commercial development is the opening phase of a multi-lot 32.0-acre site which proposes grading, a private drive aisle, storm sewer and utilities, and constructing a sitewide drainage and water quality basin. The project is located entirely within the Edwards Aquifer Contributing Zone. Individual future tracts are to modify this CZP as they propose development. A roundabout on CR 180 adjacent to the project will be constructed by City of Cedar Park and is not part of the project.

In addition to the described activities, temporary erosion and sedimentation controls will be installed prior to commencing site disturbance and maintained during construction. No wastewater will be generated by this project.

#### PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, a batch detention basin (BD), designed using the TCEQ technical guidance, *RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices*, will be constructed to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 17,932 pounds of TSS generated from a future maximum 20.6 acres of impervious cover. Water runoffs also stack atop the water quality volume. The approved permanent BMPs and measures meet the required 80 percent removal of the increased load in TSS caused by the project. Approximately 4.5 acres do not drain to the BD.

**The permanent BMPs shall be implemented prior to occupancy or use of the proposed finished project lanes.** Inspection, maintenance, repair, and retrofit of the permanent BMPs shall be in accordance with the approved application.

#### STANDARD CONDITIONS

1. The plan holder (applicant) must comply with all provisions of 30 TAC Chapter §213 and all technical specifications in the approved plan. The plan holder should also acquire and comply with additional and separate approvals, permits, registrations or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, Dam Safety, Underground Injection Control) as required based on the specifics of the plan.
2. In addition to the rules of the Commission, the plan holder must also comply with state and local ordinances and regulations providing for the protection of water quality as applicable.

#### Prior to Commencement of Construction:

3. The plan holder of any approved contributing zone plan must notify the EAPP and obtain approval from the executive director prior to initiating any modification to the activities described in the referenced application following the date of the approval.
4. The plan holder must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the EAPP no later than 48 hours prior to commencement of the regulated activity. Notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person.
5. Temporary erosion and sedimentation (E&S) controls as described in the referenced application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

#### During Construction:

6. The application must indicate the placement of permanent aboveground storage tanks facilities for static hydrocarbons and hazardous substances with cumulative storage capacity of 500 gallons or more. Subsequent permanent storage tanks on this project site require a modification to be submitted and approved prior to installation.

7. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
8. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge must be filtered through appropriately selected BMPs.
9. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
10. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

11. Owners of permanent BMPs and temporary measures must ensure that the BMPs and measures are constructed, and function as designed. A Texas licensed PE **must certify** in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the EAPP within 30 days of site completion.
12. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or the ownership of the property is transferred to the entity. A copy of the transfer of responsibility must be filed with the executive director through the EAPP within 30 days of the transfer. TCEQ form, Change in Responsibility for Maintenance on Permanent BMPs and Measures (TCEQ-10263), may be used.

The holder of the approved contributing zone plan is responsible for compliance with Chapter §213 subchapter B and any condition of the approved plan through all phases of plan implementation. Failure to comply with any condition within this approval letter is a violation of Chapter §213 subchapter B and is subject to administrative rule or orders and penalties as provided under §213.25 of this title (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. Upon legal transfer of this property, the new owner is required to comply with all terms of the approved contributing zone plan.

This action is taken as delegated by the executive director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Mr. Kevin Lee Smith, P.E. of the Edwards Aquifer Protection Program of the Austin Regional Office at 512-339-2929.

Sincerely,



Lillian Butler, Section Manager  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality

LIB/klb

cc: Mr. Dan Brown, P.E., Malone Wheeler

## **ATTACHMENT B: Narrative of Proposed Modification**

The Worldsprings Austin project proposes modifications to the approved  $\pm 32.01$ -acre New Hope – West Phase CZP located at 30.539164, -97.810744, North of Cr. 180 and West of Scottsdale Drive in Cedar Park, Williamson County, Texas. The current commercial development proposes a private drive aisle, private storm sewer, and a proposed permanent BMP which is a batch detention pond.


The  $\pm 8.00$ -acre Worldsprings Austin tract proposes modifications to the total impervious cover of the original approved CZP for New Hope – West Phase. A commercial development consisting of several buildings, utility, storm, and parking improvements is to be constructed on this  $\pm 8.00$ -acre tract within the New Hope – West Phase commercial development. The original impervious cover approved with the current CZP is 1.79 acres. The proposed modification includes an additional  $\pm 6.56$ -acres which results in a total of 8.35 acres of impervious cover.



**ATTACHMENT C: Current Site Plan of the Approved Project**



F:\THOMPSON - CEDAR PARK\PROJECTS\22-065-NEWHOPE - WEST DRAWINGS\PHASE PRIVATE IMPROVEMENTS\SITE PLAN.DWG, 11/27/2023, JACKIE KEVIAN



SCALE: 1" = 100'

**LEGEND**

	PROP. ROW
	EXIST. CURB
	EXIST. DRIVE
	EXIST. PUBLIC UTILITY EASEMENT
	PROPERTY BOUNDARY
	EXIST. SIGN
	EXIST. UTILITY POLE
	EXIST. UTILITY POLE
	EXIST. UTILITY POLE
	EXIST. OVERHEAD ELEC.
	EXIST. FENCE
	EXIST. FENCE
	EXIST. LOT LINE
	EXIST. STORM SEWER
	EXIST. CURB INLET
	PROP. BACK OF CURB
	PROP. CENTER LINE
	PROP. PUBLIC UTILITY EASEMENT
	PHASE 1 CONSTRUCTION
	PHASE 2 PAVING AND EARTHWORK

BY		REVISION		DATE		NO.	
NEW HOPE WEST PHASE PRIVATE INFRASTRUCTURE PLANS CEDAR PARK, TEXAS				OVERALL SITE PLAN			
<b>MALONE ★ WHEELER</b> SINCE 1995 CIVIL ENGINEERING ★ DEVELOPMENT CONSULTING ★ PROJECT MANAGEMENT 5113 Southwest Plaza, Suite 260 Austin, Texas 78735 Phone: (512) 899-0601 Fax: (512) 899-0655 Firm Registration No. F-786							
DESIGN BY : JSK/MV				APPROVED BY : DB			
CHECKED BY : AV				DATE : 10/19/2023			
SHEET 12				OF 32			

***SECTION 3:  
CONTRIBUTING ZONE PLAN***

# Contributing Zone Plan Application

## Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Ryan McKay

Date: 06/19/2024

Signature of Customer/Agent:



Regulated Entity Name: New Hope - West Phase

## Project Information

1. County: Williamson
2. Stream Basin: Cottonwood Creek
3. Groundwater Conservation District (if applicable): N/A
4. Customer (Applicant):

Contact Person: Christopher Whitworth

Entity: New Hope Land, Ltd

Mailing Address: 5515 Balcones Drive

City, State: Austin, Texas

Telephone: 512-633-0628

Email Address: chris@cordovarev.com

Zip: 78731

Fax: \_\_\_\_\_

5. Agent/Representative (If any):

Contact Person: Ryan McKay

Entity: Kimley-Horn

Mailing Address: 6800 Burleson Rd, Building 312, Suite 150

City, State: Austin, Texas

Zip: 78744

Telephone: 512-518-4875

Fax: \_\_\_\_\_

Email Address: ryan.mckay@kimley-horn.com

6. Project Location:

- ☒ The project site is located inside the city limits of Cedar Park
- ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.
- ☐ The project site is not located within any city's limits or ETJ.

7. ☒ The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

NEC CO-180 & New Hope Drive

8. ☒ **Attachment A - Road Map.** A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.

9. ☒ **Attachment B - USGS Quadrangle Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000") is attached. The map(s) clearly show:

- ☐ Project site boundaries.
- ☐ USGS Quadrangle Name(s).

10. ☒ **Attachment C - Project Narrative.** A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:

- ☒ Area of the site
- ☒ Offsite areas
- ☒ Impervious cover
- ☒ Permanent BMP(s)
- ☒ Proposed site use
- ☒ Site history
- ☒ Previous development
- ☒ Area(s) to be demolished

11. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site

- ☐ Existing paved and/or unpaved roads  
☐ Undeveloped (Cleared)  
☒ Undeveloped (Undisturbed/Not cleared)  
☐ Other: \_\_\_\_\_

12. The type of project is:

- ☐ Residential: # of Lots: \_\_\_\_\_  
☐ Residential: # of Living Unit Equivalents: \_\_\_\_\_  
☒ Commercial  
☐ Industrial  
☐ Other: \_\_\_\_\_

13. Total project area (size of site): 8.00 Acres

Total disturbed area: 8.00 Acres

14. Estimated projected population: N/A

15. The amount and type of impervious cover expected after construction is complete is shown below:

**Table 1 - Impervious Cover**

<i><b>Impervious Cover of Proposed Project</b></i>	<i><b>Sq. Ft.</b></i>	<i><b>Sq. Ft./Acre</b></i>	<i><b>Acres</b></i>
Structures/Rooftops	32,462	÷ 43,560 =	0.75
Parking	159,610	÷ 43,560 =	3.66
Other paved surfaces	93,654	÷ 43,560 =	2.15
Total Impervious Cover	285,754	÷ 43,560 =	6.56

**Total Impervious Cover** 6.56 ÷ **Total Acreage** 8.00 X 100 = 82.0 % Impervious Cover

16. ☒ **Attachment D - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. ☒ Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

### ***For Road Projects Only***

***Complete questions 18 - 23 if this application is exclusively for a road project.***

☒ N/A

18. Type of project:

- ☐ TXDOT road project.
- ☐ County road or roads built to county specifications.
- ☐ City thoroughfare or roads to be dedicated to a municipality.
- ☐ Street or road providing access to private driveways.

19. Type of pavement or road surface to be used:

- ☐ Concrete
- ☐ Asphaltic concrete pavement
- ☐ Other: \_\_\_\_\_

20. Right of Way (R.O.W.):

Length of R.O.W.: \_\_\_\_\_ feet.

Width of R.O.W.: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

21. Pavement Area:

Length of pavement area: \_\_\_\_\_ feet.

Width of pavement area: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

Pavement area \_\_\_\_\_ acres  $\div$  R.O.W. area \_\_\_\_\_ acres  $\times 100 = \text{_____ \%}$  impervious cover.

22. ☐ A rest stop will be included in this project.

☐ A rest stop will not be included in this project.

23. ☐ Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

***Stormwater to be generated by the Proposed Project***

24. ☒ **Attachment E - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

***Wastewater to be generated by the Proposed Project***

25. ☐ Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

☒ N/A



26. Wastewater will be disposed of by:

☐ On-Site Sewage Facility (OSSF/Septic Tank):

☐ **Attachment F - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

☐ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

☐ Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the Brushy Creek Regional Wastewater Treatment Plant. The treatment facility is:

☒ Existing.

☐ Proposed.

☐ N/A

### ***Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons***

***Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.***

☒ N/A

27. Tanks and substance stored:

**Table 2 - Tanks and Substance Storage**

<b><i>AST Number</i></b>	<b><i>Size (Gallons)</i></b>	<b><i>Substance to be Stored</i></b>	<b><i>Tank Material</i></b>
1			
2			
3			
4			
5			

**Total x 1.5 = \_\_\_\_\_ Gallons**

28. ☐ The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than

5 of 11

one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

- ☐ **Attachment G - Alternative Secondary Containment Methods.** Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

**Table 3 - Secondary Containment**

<i>Length (L)(Ft.)</i>	<i>Width(W)(Ft.)</i>	<i>Height (H)(Ft.)</i>	<i>L x W x H = (Ft3)</i>	<i>Gallons</i>

**Total: \_\_\_\_\_ Gallons**

30. Piping:

- ☐ All piping, hoses, and dispensers will be located inside the containment structure.
- ☐ Some of the piping to dispensers or equipment will extend outside the containment structure.
- ☐ The piping will be aboveground
- ☐ The piping will be underground

31. ☐ The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of: \_\_\_\_\_.

32. ☐ **Attachment H - AST Containment Structure Drawings.** A scaled drawing of the containment structure is attached that shows the following:

- ☐ Interior dimensions (length, width, depth and wall and floor thickness).
- ☐ Internal drainage to a point convenient for the collection of any spillage.
- ☐ Tanks clearly labeled
- ☐ Piping clearly labeled
- ☐ Dispenser clearly labeled

33. ☐ Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

- ☐ In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.



- ☐ In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

## ***Site Plan Requirements***

***Items 34 - 46 must be included on the Site Plan.***

34. ☒ The Site Plan must have a minimum scale of 1" = 400'.  
Site Plan Scale: 1" = 50 '.
35. 100-year floodplain boundaries:
- ☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☒ No part of the project site is located within the 100-year floodplain.  
The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): 48491C0470F, dated December 20
36. ☒ The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
- ☐ The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. ☐ A drainage plan showing all paths of drainage from the site to surface streams.
38. ☒ The drainage patterns and approximate slopes anticipated after major grading activities.
39. ☒ Areas of soil disturbance and areas which will not be disturbed.
40. ☒ Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. ☒ Locations where soil stabilization practices are expected to occur.
42. ☐ Surface waters (including wetlands).  
☒ N/A
43. ☒ Locations where stormwater discharges to surface water.  
☐ There will be no discharges to surface water.
44. ☐ Temporary aboveground storage tank facilities.  
☒ Temporary aboveground storage tank facilities will not be located on this site.

45. ☐ Permanent aboveground storage tank facilities.  
☒ Permanent aboveground storage tank facilities will not be located on this site.
46. ☒ Legal boundaries of the site are shown.

### ***Permanent Best Management Practices (BMPs)***

#### ***Practices and measures that will be used during and after construction is completed.***

47. ☐ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.  
☒ N/A
48. ☐ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
- ☐ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.
- ☐ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: \_\_\_\_\_.
- ☒ N/A
49. ☐ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
- ☒ N/A
50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
- ☐ The site will be used for low density single-family residential development and has 20% or less impervious cover.
- ☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.
- ☒ The site will not be used for low density single-family residential development.

51. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

- ☐ **Attachment I - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.

52. ☒ **Attachment J - BMPs for Upgradient Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☒ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

53. ☒ **Attachment K - BMPs for On-site Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.

54. ☐ **Attachment L - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.

☒ N/A

55. ☒ **Attachment M - Construction Plans.** Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

☐ N/A

56. ☐ **Attachment N - Inspection, Maintenance, Repair and Retrofit Plan.** A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:

- ☐ Prepared and certified by the engineer designing the permanent BMPs and measures
- ☐ Signed by the owner or responsible party
- ☐ Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.
- ☐ Contains a discussion of record keeping procedures

☒ N/A

57. ☐ **Attachment O - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.

☒ N/A

58. ☐ **Attachment P - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.

☒ N/A

***Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.***

59. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60. ☒ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development,


or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### ***Administrative Information***

- 61. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. ☒ Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. ☐ The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
- ☒ The Temporary Stormwater Section (TCEQ-0602) is included with the application.



## ATTACHMENT A: Road Map



PROJECT  
LOCATION

183A TOLL ROAD

CO-C-180

E NEW HOPE DR

COTTONWOOD CREEK TRAIL

LAKEMOOD TRAIL



ROAD MAP  
Cedar Park, Texas  
June 20, 2024





## ATTACHMENT B: USGS Quadrangle Map






Produced by the United States Geological Survey

North American Datum of 1983 (NAD83)  
World Geodetic System of 1984 (WGS84). Projection and  
1 000-meter grid/Universal Transverse Mercator, Zone 14R.  
This map is not a legal document. Boundaries may be  
generalized for this map scale. Private lands within government  
reservations may not be shown. Obtain permission before  
entering private lands.

Imagery.....NAIP, September 2016 - November 2016  
Roads.....U.S. Census Bureau, 2015 - 2019  
Names.....GNIS, 1979 - 2022  
Hydrography.....National Hydrography Dataset, 2002 - 2020  
Contours.....National Elevation Dataset, 2019  
Boundaries.....Multiple sources; see metadata file  
Wetlands.....FWS National Wetlands Inventory Not Available



CONTOUR INTERVAL 10 FEET  
NORTH AMERICAN DATUM OF 1983  
This map was produced to conform with the  
National Geospatial Program US Topo Product Standard.



1	2	3
4	5	6
7	8	9

ADJOINING QUADRANGLES

1 Liberty Hill  
2 Leander NE  
3 Georgetown  
4 Nameless  
5 Round Rock  
6 Mansfield Dam  
7 Jollyville  
8 Pflugerville West

ROAD CLASSIFICATION	
Expressway	Local Connector
Secondary Hwy	Local Road
Ramp	4WD
Interstate Route	US Route
	State Route

LEANDER, TX  
2022





## **ATTACHMENT C: PROPOSED NARRATIVE**

The Wordsprings Austin project proposed improvements on a ±8.00-acre tract of the New Hope – West Phase commercial development located at NEC CO-180 & New Hope Drive, Cedar Park, Texas. This tract is currently undeveloped. The development proposed with this site plan application is for the construction of a commercial building, pool amenity features, and associated parking and utility improvements.

No portion of the site is located within the Federal Emergency Management Agency's 100-year floodplain according to Flood Insurance Rate Map number 48491C0470F, dated December 20, 2019, for Williamson County, Texas and incorporated areas. The site is located within the Edwards Aquifer Contributing Zone according to the Texas Commission on Environmental Quality (TCEQ). There are no critical water quality zones or water quality transition zones on-site. There are no critical environmental features located on-site according to an ERI performed for the property.

The site is in the Cottonwood Creek watershed. There is an existing Water Quality Best Management Practice (BMP) for the original CZP of New Hope – West Phase. The batch detention pond proposed with the New Hope – West Phase CZP will be used by this project to address the water quality requirements for the ultimate area disturbed by this commercial development.

The proposed impervious cover for this project is ±6.56-acres and no areas are to be demolished considering that the site is undeveloped.

## **ATTACHMENT D: Factors Affecting Surface Water Quality**

No Industrial associated activity discharges are expected for this proposed commercial development site. Surface water quality can be affected by disturbance during construction and by development after construction. Soil disturbance from clearing and grubbing and cut / fill operations can lead to discharge of sediment unless adequate temporary erosion control measures are in place. For this project, the use of silt fence and construction entrances will prevent sediment from leaving the site. Siltation collected by the control measures will be cleaned from fences, berms, etc. on a routine schedule.

During construction, surface water quality may also be affected by a spill of hydrocarbons or other hazardous substances used in construction. The most likely instances of a spill of hydrocarbons or hazardous substances are:

- a) Refueling construction equipment.
- b) Oil and grease from the asphalt pavement and vehicle traffic.
- c) Performing operator-level maintenance, including adding petroleum, oils, or lubricants.
- d) Normal silt build-up
- e) Unscheduled or emergency repairs, such as hydraulic fluid leaks.
- f) Trash which becomes loose from subdivision residents.
- g) Fertilizers used in the landscaping around the apartment buildings.

Every effort will be taken to be cautious and prevent spills. In the event of a fuel or hazardous substance spill as defined by the Reportable Quantities Table 1 (page 3) of the TCEQ's Small-Business Handbook for Spill Response (RG-285, June 1997), the contractor is required to clean up the spill and notify the TCEQ as required in RG-285. During business hours report spills to the TCEQ's Austin Regional Office at (512) 339-2929, after business hours call 1-800-832-8224, the Environmental Response Hotline or (512) 463-7727, the TCEQ Spill Reporting Hotline, which is also answered 24 hours a day. After construction is complete, impervious cover for the tract of land is the major reason for degradation of water quality. Impervious cover includes the building foundations, street pavement and concrete sidewalks. Oil and fuel discharge from vehicles is anticipated. The permanent BMP proposed with the New Hope – West Phase commercial development will help mitigate these occurrences.

## ATTACHMENT E: Volume and Character of Stormwater

### EXISTING HYDROLOGIC CONDITIONS ANALYSIS

The drainage analysis of the existing site conditions was performed with Rational Method using Atlas 14 rainfall data. The site has one existing on-site drainage area which outfalls at one point of analysis (POA-1). Runoff from the existing drainage area EDA-01 flows from the north west corner of the property to the south east (POA-1).

The approach taken for the existing conditions of this site is to maintain the design peak flows to assure the downstream storm infrastructure can adequately convey the runoff and that the major point of confluence is not adversely affected. Table 4.1 below summarizes the existing drainage areas and the runoff produced for each storm event.

**Table 4.1 Existing Drainage Areas Summary**

EXISTING CONDITIONS							PEAK FLOWS AT POA			
DRAINAGE AREA	AREA (AC.)	IMPERVIOUS COVER	BASE CN	IMPERVIOUS CN	WEIGHTED CN	TC (MIN)	Q2 (CFS)	Q10 (CFS)	Q25 (CFS)	Q100 (CFS)
EDA-1	8.00	0.0%	80	98	80.00	17.76	16.9	32.0	42.6	60.8

### PROPOSED HYDROLOGIC CONDITIONS ANALYSIS

The drainage analysis of the existing site conditions was performed with the Rational Method using Atlas 14 rainfall data. The proposed drainage areas consider the additional impervious cover added in the proposed development. The proposed drainage areas generally follow the same drainage paths as existing conditions. The existing and proposed drainage areas were analyzed at their respective points of analysis. In all analyzed storm events, 2-year, 10-year, 25-year and 100-year, no point of analysis increased in peak run-off in the developed condition.

The time of concentrations were calculated for sheet flow, shallow concentrated flow, and channel flow. Rainfall data taken from the Atlas 14 Rainfall depth revisions and IDF Curves Memorandum were used to define the 2, 10, 25, and 100-year rainfall events.

Proposed drainage areas correspond to their respective existing drainage areas by number. For example, PDA-01 is outfalling to the same point-of-analysis (POA-1) as EDA-01.

**Table 4.2 Proposed Drainage Areas Summary**

PROPOSED CONDITIONS							PEAK FLOWS AT POA			
DRAINAGE AREA	AREA (AC.)	IMPERVIOUS COVER	BASE CN	IMPERVIOUS CN	WEIGHTED CN	TC (MIN)	Q2 (CFS)	Q10 (CFS)	Q25 (CFS)	Q100 (CFS)
PDA-1	8.00	69.9%	80	98	92.58	7.52	31.2	49.5	62.5	84.8

NOTE: INCREASE IN FLOW IS ACCOUNTED FOR IN THE REGIONAL DETENTION POND DESIGNED AND PERMITTED WITH THE NEW HPE WEST PHASE PRIVATE INFRASTRUCTURE PLANS.

## ATTACHMENT F: Suitability Letter From Authorized Agent

An authorizes suitability letter from Williamson County is not applicable to this project because no OSSFs are proposed.



## ATTACHMENT G: Alternative Secondary Containment Methods

This attachment is not applicable. No alternative secondary containment methods will be utilized.



## ATTACHMENT H: AST Containment Structure Drawings

This attachment is not applicable. No ASTs will be utilized.



## ATTACHMENT I: 20% or Less Impervious Cover Waiver

This attachment is not applicable.



## ATTACHMENT J: BMPs for Upgradient Stormwater

There is no stormwater up-gradient of the project site that will travel through the site. An existing regional batch detention pond is being constructed with the New Hope - West Phase Private Infrastructure SDP and will be utilized for capturing and treating the stormwater from this site. Please refer to the existing/proposed drainage area maps provided at the end of this report under the appropriate tab for your reference.

## ATTACHMENT K: BMPs for On-site Stormwater

No permanent BMPs are proposed for this project. A regional batch detention pond to be constructed with the New Hope - West Phase Private Infrastructure SDP will be utilized to prevent surface water or groundwater that originates from on-site flows, including pollution caused by contaminated stormwater runoff.



## ATTACHMENT L: BMPs for Surface Streams

There are no existing surface streams or sensitive features on site.













CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED VALVES, FIRE HYDRANTS, AND OTHER UTILITY APPURTENANCES TO MATCH ACTUAL FINISHED GRADES AT THE TIME OF PAVING.

53. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND PHASING, AND SHALL CONTACT THE APPROPRIATE CITY OFFICIALS, INCLUDING BUILDING OFFICIALS, ENGINEERING INSPECTOR, AND FIRE MARSHAL TO LEARN OF ANY REQUIREMENTS.

54. CONTRACTOR IS RESPONSIBLE FOR PREPARATION, SUBMITTAL, AND APPROVAL BY THE CITY OF A TRAFFIC CONTROL PLAN PRIOR TO THE START OF CONSTRUCTION, AND THEN THE IMPLEMENTATION OF THE PLAN.

55. CONTRACTOR SHALL KEEP A NEAT AND ACCURATE RECORD OF CONSTRUCTION, INCLUDING ANY DEVIATIONS OR VARIANCES FROM THE PLANS.

56. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.

**EROSION CONTROL:**

1. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS, LAWS, AND ORDINANCES THAT APPLY TO THE CONSTRUCTION SITE LAND DISTURBANCE.

2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM (TXR 150000).

3. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBANCE.

4. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THE PROJECT.

5. CONTRACTOR IS SOLELY RESPONSIBLE FOR INSTALLATION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL EROSION CONTROL DEVICES, BEST MANAGEMENT PRACTICES (BMPs), AND FOR UPDATING THE EROSION CONTROL PLAN DURING CONSTRUCTION AS FIELD CONDITIONS CHANGE.

6. CONTRACTOR SHALL PROVIDE TEMPORARY SEDIMENTATION, MAINTENANCE OR MODIFICATION, AND REMOVAL FOR EACH BMP EMPLOYED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE.

7. AS STORM SEWER INLETS ARE INSTALLED ON-SITE, TEMPORARY EROSION CONTROL DEVICES SHALL BE INSTALLED AT EACH INLET PER APPROVED DETAILS.

8. THE EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE AREA IT PROTECTS HAS BEEN PERMANENTLY STABILIZED.

9. CONTRACTOR SHALL PROVIDE ADEQUATE EROSION CONTROL DEVICES NEEDED DUE TO PROJECT PHASING.

10. CONTRACTOR SHALL OBSERVE THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES AND MAKE FIELD ADJUSTMENTS AND MODIFICATIONS AS NEEDED TO PREVENT SEDIMENT FROM LEAVING THE SITE. IF THE EROSION CONTROL DEVICES DO NOT PREVENT SEDIMENT FROM LEAVING THE SITE, THE CONTRACTOR SHALL IMMEDIATELY REMOVE THE DEVICES FROM WASHING OFF THE SITE, THEN THE CONTRACTOR SHALL NOTIFY THE ENGINEER.

11. OFF-SITE SOIL BORROW, SPOIL, AND STORAGE AREAS (IF APPLICABLE) ARE CONSIDERED AS PART OF THE PROJECT SITE AND MUST ALSO COMPLY WITH THE EROSION CONTROL REQUIREMENTS FOR THIS PROJECT. THIS INCLUDES THE STABILIZATION OF BORROW, SPOIL, AND STORAGE AREAS WITH PERMANENT VEGETATION OR PERMANENT GROUND COVER ON DISTURBED AREAS PRIOR TO FINAL APPROVAL OF THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP AND EROSION CONTROL PLAN TO INCLUDE BMPs FOR ANY OFF-SITE THAT ARE NOT ANTICIPATED OR SHOWN ON THE EROSION CONTROL PLAN.

12. STORMWATER STOCKPILES, SPOIL, AND STORAGE SHALL BE LOCATED SUCH THAT THEY WILL NOT ADVERSELY AFFECT STORM WATER QUALITY. PROTECTIVE MEASURES SHALL BE PROVIDED IF NEEDED TO ACCOMPLISH THIS REQUIREMENT, SUCH AS COVERING OR ENCIRCLING THE AREA WITH AN APPROPRIATE BARRIER.

13. CONTRACTORS SHALL INSPECT ALL EROSION CONTROL DEVICES, BMPs, DISTURBED AREAS, AND VEHICLE ENTRY AND EXIT AREAS WEEKLY AND WITHIN 24 HOURS OF ALL RAINFALL EVENTS OF 0.5 INCHES OR GREATER, AND KEEP A RECORD OF THIS INSPECTION IN THE SWPPP. A BOOKLET IF APPLICABLE, TO VERIFY THAT THE DEVICES AND EROSION CONTROL PLAN ARE FUNCTIONING PROPERLY.

14. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT ALL PRIMARY POINTS OF ACCESS IN ACCORDANCE WITH CITY SPECIFICATIONS. CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION TRAFFIC USES THE STABILIZED ENTRANCE.

15. SITE ENTRY AND EXITS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING AND FLOWING OF SEDIMENT AND DIRT ONTO OFF-SITE ROADWAYS. ALL SEDIMENT AND DIRT FROM THE SITE THAT IS DEPOSITED ONTO AN OFF-SITE ROADWAY SHALL BE REMOVED IMMEDIATELY.

16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SILT AND DEBRIS FROM THE OFFSETTED OFF-SITE ROADWAYS THAT ARE A RESULT OF THE CONSTRUCTION AS REQUESTED BY OWNER AND CITY. AT A MINIMUM, THIS SHOULD OCCUR ONCE PER DAY FOR THE OFF-SITE ROADWAYS.

17. WHEN WASHING OF VEHICLES IS REQUIRED TO REMOVE SEDIMENT PRIOR TO EXITING THE SITE, IT SHALL BE DONE IN AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP BMP.

18. CONTRACTOR SHALL ENSURE THAT THE CONSTRUCTION OF ANY ON-SITE DRAINAGE AREAS THAT ARE GREATER THAN 10 ACRES, PER TCEQ AND CITY STANDARDS. IF NO ENGINEERING DESIGN HAS BEEN PROVIDED FOR A SEDIMENTATION BASIN ON THESE PLANS, THEN THE CONTRACTOR SHALL ARRANGE FOR AN APPROPRIATE DESIGN TO BE PROVIDED.

19. ALL FINES IMPOSED FOR SEDIMENT OR DIRT DISCHARGED FROM THE SITE SHALL BE PAID BY THE RESPONSIBLE CONTRACTOR.

20. WHEN SEDIMENT OR DIRT HAS CLOGGED THE CONSTRUCTION ENTRANCE VOID SPACES BETWEEN STONES OR DIRT IS BEING TRACKED ONTO A ROADWAY, THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASH-DOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL SEDIMENT. PERIODIC RE-GRADING OR NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFECTIVENESS OF THE CONSTRUCTION ENTRANCE.

21. TEMPORARY SEEDING OR OTHER SEDIMENTATION PRACTICE SHALL BE INITIATED WITHIN 14 DAYS OF THE LAST DISTURBANCE IN AN AREA, UNLESS ADDITIONAL CONSTRUCTION IN THE AREA IS EXPECTED WITHIN 21 DAYS OF THE LAST DISTURBANCE.

22. CONTRACTOR SHALL FOLLOW GOOD HOUSEKEEPING PRACTICES DURING CONSTRUCTION, ALWAYS CLEANING UP DIRT, LOOSE MATERIAL, AND TRASH AS CONSTRUCTION PROGRESSES.

23. UPON COMPLETION OF FINE GRADING, ALL SURFACES OF DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED. STABILIZATION IS ACHIEVED WHEN THE AREA IS EITHER COVERED BY PERMANENT IMPROVED STRUCTURES, SUCH AS DRIVEWAYS, SIDEWALKS, OR PAVEMENT, OR BY PERMANENT VEGETATION. ANY REVISIONS TO THE STABILIZATION SHALL BE SUBMITTED TO THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION.

24. AT THE CONCLUSION OF THE PROJECT, ALL INLETS, DRAIN PIPE, CHANNELS, DRAINAGEWAYS AND BORROW DITCHES AFFECTED BY THE CONSTRUCTION SHALL BE DREGGED, AND THE SEDIMENT GENERATED BY THE PROJECT SHALL BE REMOVED AND DISPOSED IN ACCORDANCE WITH APPLICABLE REGULATIONS.

**STORM WATER DISCHARGE AUTHORIZATION:**

1. CONTRACTOR SHALL COMPLY WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION REQUIREMENTS.

2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM (TXR 150000).

3. CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE CITY AND ANY PRIMARY OPERATORS SUBMIT A NOI TO CATCH SEVEN DAYS PRIOR TO COMMENCING CONSTRUCTION (IF APPLICABLE), OR IF UTILIZING ELECTRONIC SUBMITTAL, PRIOR TO COMMENCING CONSTRUCTION. ALL PRIMARY OPERATORS SHALL PROVIDE A COPY OF THE SIGNED NOI TO THE OPERATOR OF ANY MSA (TYPICALLY THE CITY) RECEIVING DISCHARGE FROM THE SITE.

4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE, INCLUDING POSTING SITE NOTICE, INSPECTIONS, DOCUMENTATION, AND SUBMISSION OF ANY INFORMATION REQUIRED BY THE TCEQ AND EPA (E.G. NOI).

5. ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICES RELATED TO THE SWPPP SHALL SIGN THE REQUIRED CONTRACTOR CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS SPECIFIED IN THE SWPPP.

6. A COPY OF THE CONTRACTOR SWPPP, INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATIONS, AND ANY REVISIONS, SHALL BE SUBMITTED TO THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION.

7. A NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO TCEQ BY ANY PRIMARY OPERATOR WITHIN 30 DAYS AFTER THE SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND A UNIFORM VEGETATIVE COVER HAS BEEN ESTABLISHED ON AN ON-SITE DRAINAGE AREA. IF THE COVER IS NOT COVERED BY STRUCTURES, A TRANSFER OF DISCHARGE AUTHORITY HAS OCCURRED, OR THE OPERATOR HAS OBTAINED ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT, A COPY OF THE NOI SHALL BE PROVIDED TO THE OPERATOR OF ANY MSA RECEIVING DISCHARGE FROM THE SITE.

**DEMOLITION:**

1. KH IS NOT RESPONSIBLE FOR THE MEANS AND METHODS EMPLOYED BY THE CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS PRELIMINARY DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACT THAT ARE TO BE DEMOLISHED AND REMOVED FROM THE SITE.

2. KH DOES NOT WARRANT OR REPRESENT THAT THE PLAN, WHICH WAS PREPARED BASED ON SURVEY AND UTILITY INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY, OR THAT THE UTILITIES SHOWN CAN BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR IMPROVING ITS OWN SITE RECONNAISSANCE TO SCOPE ITS WORK AND TO CONFIRM WITH THE OWNERS OF IMPROVEMENTS AND UTILITIES THE ABILITY AND PROCESS FOR THE REMOVAL OF THEIR FACILITIES.

3. THE CONTRACTOR INTENDS TO CONDUCT THE DEMOLITION OF THE PROJECT IN ACCORDANCE WITH THE PLAN. IF THE DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT, REMOVAL OR PRESERVATION OF IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL ARE THE RESPONSIBILITY OF THE CONTRACTOR.

4. CONTRACTOR IS STRONGLY CAUTIONED TO REVIEW THE FOLLOWING REPORTS DESCRIBING SITE CONDITIONS PRIOR TO BIDDING AND IMPLEMENTING THE DEMOLITION PLAN:

a. ENVIRONMENTAL SITE ASSESSMENT PROVIDED BY THE OWNER.

b. ASBESTOS BUILDING INSPECTION REPORT(S) PROVIDED BY THE OWNER.

c. GEOTECHNICAL REPORT PROVIDED BY THE OWNER.

d. OTHER REPORTS THAT ARE APPLICABLE AND AVAILABLE.

5. CONTRACTOR SHALL CONTACT THE OWNER TO VERIFY WHETHER ADDITIONAL REPORTS OR AMENDMENTS TO THE ABOVE CITED REPORTS HAVE BEEN PREPARED AND TO OBTAIN/REVIEW/AND COMPLY WITH THE RECOMMENDATION OF SUCH STUDIES PRIOR TO STARTING ANY WORK ON THE SITE.

6. CONTRACTOR SHALL COMPLY WITH ALL CITY, STATE, AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO REVIEW THE SITE, DETERMINE THE APPLICABLE REGULATIONS, RECEIVE THE REQUIRED PERMITS AND AUTHORIZATIONS, AND COMPLY.

7. THE OWNER REPRESENTS THAT THE REPORTS AND SURVEYS REFERENCED ABOVE ARE ACCURATE, COMPLETE, OR COMPREHENSIVE SHOWING ALL ITEMS THAT WILL NEED TO BE DEMOLISHED AND REMOVED.

8. SURFACE PAVEMENT INDICATED MAY OVERLAY OTHER HIDDEN STRUCTURES, SUCH AS ADDITIONAL LAYERS OF PAVEMENT, FOUNDATIONS OR WALLS, THAT ARE ALSO TO BE REMOVED.

**GRADING:**

1. THE CONTRACTOR AND GRADING SUBCONTRACTOR SHALL VERIFY THE SUITABILITY OF EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE START OF CONSTRUCTION. THE CIVIL ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES.

2. CONTRACTOR SHALL OBTAIN ANY REQUIRED GRADING PERMITS FROM THE CITY.

3. UNLESS OTHERWISE NOTED, PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN IN PAVED AREA REFLECT TOP OF PAVEMENT SURFACE. IN LOCATIONS ALONG A CURB LINE, ADD 6-INCHES (OR THE HEIGHT OF THE CURB) TO THE PAVING GRADE FOR TOP OF CURB ELEVATION.

4. CONTRACTOR SHALL COMPLY WITH ALL CITY, STATE, AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO REVIEW THE SITE, DETERMINE THE APPLICABLE REGULATIONS, RECEIVE THE REQUIRED PERMITS AND AUTHORIZATIONS, AND COMPLY.

5. PROPOSED CONTOURS OR ELEVATIONS, PROPOSED SPOT ELEVATIONS AND DESIGNATED GRADIENT ARE TO BE USED IN CASE OF DISCREPANCY.

6. ALL FINISHED GRADES SHALL TRANSITION UNIFORMLY FROM THE FINISHED ELEVATIONS SHOWN.

7. CONTOURS AND SPOT GRADES SHOWN ARE ELEVATIONS OF TOP OF THE FINISHED SURFACE. WHEN PERFORMING THE GRADING, CONTRACTOR SHALLS, IT SHALL PROVIDE AN APPROPRIATE ELEVATION HOLD-DOWN ALLOWANCE FOR THE THICKNESS OF PAVEMENT, SIDEWALK, TOPSOIL, MULCH, STONE, LANDSCAPING, RIP-RAP AND ALL OTHER SURFACE MATERIALS THAT WILL CONTRIBUTE TO THE TOP OF FINISHED GRADE. FOR EXAMPLE, THE LIMITS OF EARTHWORK IN PAVED AREAS IS THE BOTTOM OF THE PAVEMENT SECTION.

8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN AND SITE BALANCE ARE MADE BY THESE PLANS. THE CONTRACTOR SHALL PROVIDE THEIR OWN EARTHWORK CALCULATION TO DETERMINE THEIR CONTRACT QUANTITIES AND COST. ANY SIGNIFICANT VARIANCE FROM A BALANCED SITE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CIVIL

THE CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER SEWER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY STORM SEWER, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.

4. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF CURB INLETS AND GRATE INLETS AND ALL UTILITIES CROSSING THE STORM SEWER.

5. FLOW LINE, TOP-OF-CURB, RIM, THROAT, AND GRATE ELEVATIONS OF PROPOSED INLETS SHALL BE VERIFIED WITH THE GRADING PLAN AND FIELD CONDITIONS PRIOR TO THEIR INSTALLATION.

6. THE CONTRACTOR SHALL PROPOSE TO USE HDPE OR PVC IN LIEU OF RCP FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPE AND PVC SHALL BE WATERTIGHT.

7. ALL PRIVATE STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.

8. THE CONTRACTOR SHALL VERIFY ALL EXISTING PUBLIC OR PRIVATE STRUCTURES ENTERING STRUCTURES OR OTHER STORM PIPES SHALL HAVE A CONCRETE COLLAR AND BE GROUTED TO ASSURE THE CONNECTION IS WATERTIGHT.

9. ALL PUBLIC STORM SEWER LINE SIZE SHALL BE MINIMUM CLASS III RCP. PRIVATE STORM SEWER LINES 18-INCHES AND GREATER SHALL BE CLASS III RCP OR OTHER APPROVED MATERIAL.

10. WHERE COVER EXCEEDS 20-FEET OR IS LESS THAN 2-FEET, CLASS III RCP SHALL BE USED.

11. IF CONTRACTOR FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPE AND PVC SHALL BE WATERTIGHT.

12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL STORM SEWER LINES.

13. EMBEDMENT FOR ALL STORM SEWER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS.

14. ALL WYE CONNECTIONS AND PIPE BENDS ARE TO BE PREFABRICATED AND INSTALLED PER MANUFACTURERS SPECIFICATIONS.

15. USE 4 FOOT JOINTS WITH BEVELED ENDS IF RADIUS OF STORM SEWER IS LESS THAN 100 FEET.

16. FOR ANY PONDS INTENDED FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION, CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY.

17. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

**POND NOTES:**

1. ANY PONDS THAT ARE INTENDED TO HOLD WATER INDEFINITELY SHALL BE CONSTRUCTED WATERTIGHT.

2. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY, THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR POND LINER SPECIFICATIONS.

3. A GEOTECHNICAL ENGINEER SHALL REVIEW AND APPROVE ALL POND LINER MATERIAL, PLACEMENT PROCEDURES, AND PROVIDE TESTING TO ENSURE THE POND LINER MATERIAL PLACED IS WATERTIGHT.

4. THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION OF PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.

5. ANY GRAVEL OR OTHER PERVIOUS EMBEDMENT ABOVE PIPES OR OUTFALL STRUCTURES NEAR THE POND SHALL BE ELIMINATED FOR AT LEAST 20-FOOT FROM THE POND SO NO ROUTE FOR WATER TO LEAK THROUGH THE EMBEDMENT MATERIAL IS PROVIDED. BACKFILL IN THESE AREAS SHALL BE COMPACTED TO THE WATER LEVEL FOLLOWING COMPLETION AND FILLING OF THE POND. SHALL BE MONITORED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO OBSERVE WATER INFLOW, OUTFLOW, AND CALCULATE EVAPORATION TO VERIFY THAT THE POND IS WATERTIGHT.

6. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY, THE POND WATER LEVEL SHALL ALSO BE MAINTAINED BY THE CONTRACTOR TO REMAIN FULL TO ITS DESIGN WATER LEVEL, AND IS NOT LOWERED, AS THIS MAY DRY-OUT THE POND LINER AND RISK ITS WATERTIGHT PROPERTIES.

**WATER AND WASTEWATER:**

1. ALL PRIVATE WATER AND WASTEWATER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS.

2. CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER AND WASTEWATER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY WATER OR WASTEWATER CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.

3. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITY SERVICES ENTERING THE BUILDING.

4. THE CONTRACTOR SHALL FIELD VERIFY THE ELEVATION OF ALL UTILITY CROSSINGS PRIOR TO THE INSTALLATION OF ANY PIPE.

5. THE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE WATER AND WASTEWATER IMPROVEMENTS.

6. ALL PUBLIC WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.

7. ALL PRIVATE WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.

8. FIRE SPRINKLER LINES SHALL BE DESIGNED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR, AND COMPLY TO THE APPLICABLE CODES AND INSPECTIONS REQUIRED. THESE PLANS WERE PREPARED WITHOUT THE BENEFIT OF THE FIRE SPRINKLER DESIGN. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES.

9. EMBEDMENT FOR ALL WATER AND WASTEWATER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS.

10. CONTRACTOR SHALL TAKE REQUIRED SANITARY PRECAUTIONS, FOLLOWING ANY CITY, TCEQ, AND AWWA STANDARDS, TO KEEP WATER PIPE AND FITTINGS CLEAN AND CAPPED AT TIMES WHEN INSTALLATION IS NOT IN PROGRESS.

11. CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL WATER AND WASTEWATER LINES.

12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING TO THE CITY TO REMAIN FULL TO ITS DESIGN WATER LEVEL, UNLESS NOTED OTHERWISE.

13. CONTRACTOR SHALL COMPLY WITH CITY REQUIREMENTS FOR WATER AND WASTEWATER SERVICE DISRUPTIONS AND THE AMOUNT OF PRIORITY NOTICE THAT IS REQUIRED, AND SHALL COORDINATE DIRECTLY WITH THE APPROPRIATE CITY DEPARTMENT.

14. THE CONTRACTOR SHALL SEQUENCE WATER AND WASTEWATER CONSTRUCTION TO AVOID INTERRUPTION OF SERVICE TO SURROUNDING PROPERTIES.

15. CONTRACTOR SHALL MAINTAIN WATER SERVICE AND WASTEWATER SERVICE TO ALL CUSTOMERS THROUGHOUT CONSTRUCTION (IF NECESSARY, BY USE OF TEMPORARY METHODS APPROVED BY THE CITY AND OWNER). THIS WORK SHALL BE CONSIDERED SUBSIDIARY TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

16. THE CONTRACTOR SHALL REPAIR ALL DAMAGED LINES IMMEDIATELY. ALL REPAIRS OF EXISTING WATER MAINS, WATER SERVICES, SEWER MAINS, AND SANITARY SEWER SERVICES ARE SUBSIDIARY TO THE WORK, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

17. VALVE ADJUSTMENTS SHALL BE CONSTRUCTED SUCH THAT THE COVERS ARE AT FINISHED SURFACE GRADE OF THE PROPOSED PAVEMENT.

18. THE ENDS OF ALL EXISTING WATER MAINS THAT ARE CUT, BUT NOT REMOVED, SHALL BE PLUGGED AND ABANDONED IN PLACE. THIS WORK SHALL BE CONSIDERED AS A SUBSIDIARY COST TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

19. ALL FIRE HYDRANTS, VALVES, TEES, BENDS, WYES, REDUCERS, FITTINGS, AND ENDS SHALL BE MECHANICALLY RESTRAINED AND/OR THRUST BLOCKED TO CITY STANDARDS.

20. CONTRACTOR SHALL INSTALL A FULL SEGMENT OF WATER OR WASTEWATER PIPE CENTERED AT ALL UTILITY CROSSINGS SUCH THAT THE JOINTS ARE GREATER THAN 9-FEET FROM THE CROSSING.

21. ALL CROSSINGS AND LOCATIONS WHERE WASTEWATER IS LESS THAN 9-FEET FROM WATER, WASTEWATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 217.53.

22. ALL CROSSING AND LOCATIONS WHERE WATER IS LESS THAN 9-FEET FROM WASTEWATER, WATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 290.44.

23. WATER AND WASTEWATER SHALL BE TESTED IN ACCORDANCE WITH THE CITY, AWWA, AND TCEQ STANDARDS AND SPECIFICATIONS. AT A MINIMUM, THIS SHALL CONSIST OF THE FOLLOWING:

a. ALL WATERLINES SHALL BE HYDROSTATICALLY TESTED AND CHLORINATED BEFORE BEING PLACED INTO SERVICE. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS.

b. WASTEWATER LINES AND MANHOLES SHALL BE PRESSURE TESTED. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. AFTER COMPLETION OF THESE TESTS, A TELEVISION INSPECTION SHALL BE PERFORMED AND PROVIDED TO THE CITY AND OWNER ON A DVD.

24. CONTRACTOR SHALL INSTALL DETECTABLE WIRING OR MARKING TAPE A MINIMUM OF 12" ABOVE WATER AND WASTEWATER LINES. MARKING DECALS SHALL BE LABELED "WATER" - "WATER LINE," OR "CAUTION" - "SEWER LINE." DETECTABLE WIRING AND MARKING TAPE SHALL COMPLY WITH CITY STANDARDS, AND SHALL BE INCLUDED IN THE COST OF THE WATER AND WASTEWATER PIPE.

25. DUCTILE IRON PIPE SHALL BE PROTECTED FROM CORROSION BY A LOW-DENSITY POLYETHYLENE LINER WRAP THAT IS AT LEAST A SINGLE LAYER OR BUILT UP DUCTILE IRON JOINTS SHALL BE BONDED.

26. WATERLINES SHALL BE INSTALLED AT NO LESS THAN THE MINIMUM COVER REQUIRED BY THE CITY.

27. CONTRACTOR SHALL PROVIDE CLEAN-OUTS FOR PRIVATE SANITARY SEWER LINES AT ALL CHANGES IN DIRECTION AND 100-FOOT INTERVALS, OR AS REQUIRED BY THE APPLICABLE PLUMBING CODE. CLEAN-OUTS REQUIRED IN PAVEMENT OR ON GRADE SHALL BE INSTALLED AT THE CITY STANDARD DETAILS.

28. CONTRACTOR SHALL PROVIDE BACKWATER VALVES FOR PLUMBING FIXTURES AS REQUIRED BY THE APPLICABLE PLUMBING CODE (E.G. FLOOR ELEVATION OF FIXTURE UNIT IS BELOW THE ELEVATION OF THE MANHOLE COVER OF THE NEXT UPSTREAM MANHOLE IN THE PUBLIC SEWER). CONTRACTOR SHALL REVIEW BOTH MEP AND CIVIL PLANS TO CONFIRM WHEN THESE ARE REQUIRED.

29. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY.

30. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

THESE PLAN AND GENERAL NOTES REFER TO:

**GEOTECHNICAL ENGINEERING REPORT**

**(FIRM) ECS SOUTHWEST, LLP**

17-0421

DATE: 05/24/2024

INCLUDING ALL REVISIONS AND ADDENDA TO THIS REPORT THAT MAY HAVE BEEN RELEASED AFTER

**BENCHMARKS**

CP22: 3" BRASS DISC IN CONCRETE  
N 10165081.83; E 3092268.19


CP41: 3" BRASS DISC IN CONCRETE  
N 10166207.91; E 3092268.19

CP22: 3" BRASS DISC IN CONCRETE  
N 10165081.83; E 3092268.19

CP41: 3" BRASS DISC IN CONCRETE  
N10166207.91; E 3092268.19

A circular professional engineer seal for the State of Texas. The seal features a five-pointed star in the center. The text "STATE OF TEXAS" is written along the top inner edge, and "PROFESSIONAL ENGINEER" is written along the bottom inner edge. The name "RYAN MCKAY" and the license number "146418" are printed in the center. The seal is surrounded by a decorative wreath-like border. There are handwritten signatures and scribbles over the seal.





## DEMOLITION NOTES

1. CONTRACTOR SHALL SECURE ALL PERMITS REQUIRED FOR DEMOLITION AND SHALL NOTIFY ALL RESPECTIVE GOVERNMENTAL AND UTILITY AGENCIES AFFECTED BY DEMOLITION PRIOR TO STARTING DEMOLITION.
2. ALL CONSTRUCTION OPERATIONS SHALL BE ACQUIRED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL HEALTH AND SAFETY ADMINISTRATION, AND IF APPLICABLE, STATE AND LOCAL REGULATIONS. MATERIALS MAY BE PURCHASED FROM THE U.S. GOVERNMENT PRINTING OFFICE, INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 903 SAN JACINTO, RM 319, AUSTIN, TX 78701, TEL (512) 916-5783.
3. PRIOR TO DEMOLITION, PROPER PHASING OF EROSION CONTROL DEVICES AND TREE PROTECTION ARE TO BE INSTALLED.
4. SHOULD REMOVAL AND/OR RELOCATION ACTIVITIES DAMAGE FENCING, LIGHTING, STORM INLET STRUCTURES OR ANY OTHER APPURTENANCE, THEN THE CONTRACTOR SHALL PROVIDE NEW MATERIALS/STRUCTURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
5. ALL NEW MATERIALS AND CONSTRUCTION DEBRIS SHALL BE REMOVED FROM THE SITE IN ACCORDANCE WITH ALL APPLICABLE RULES AND REGULATIONS.
6. ALL BARRICADES AND WARNING SIGNS SHALL CONFORM TO THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND ARE GENERALLY LOCATED TO AFFORD MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND EQUIPMENT AND TO ASSURE AN EXPEDITIOUS TRAFFIC FLOW AT ALL TIMES DURING THE PROGRESS OF WORK, THE CONTRACTOR SHALL PROVIDE ACCESS FOR LOCAL TRAFFIC.
7. CONTRACTOR MAY LIMIT SAW CUT & PAVEMENT REMOVAL TO ONLY THOSE AREAS WHERE IT IS REQUIRED AS SHOWN ON THE CONSTRUCTION PLANS, BUT IF ANY DAMAGE IS INCURRED ON ANY OF THE SURROUNDINGS PAVEMENT, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS REMOVAL, REPLACEMENT, AND/OR REPAIR.
8. ALL PAVING AND CURB TO BE REMOVED ARE TO BE REMOVED USING FULL-DEPTH SAWCUT 2" OFF EXISTING EDGE OF PAVEMENT.
9. ANY ADDITIONAL CONCRETE PAVING, FOOTINGS OR STRUCTURES NOT IDENTIFIED ON THIS PLAN SHALL BE LOCATED BY CONTRACTOR AND SUBMITTED TO ENGINEER FOR APPROVAL.
10. CONTRACTOR SHALL EXERCISE EXTREME CAUTION AS SITE MAY CONTAIN PRIVATE AND/OR PUBLIC UTILITIES. CONTRACTOR SHALL CALL 811 AT LEAST 72 HOURS PRIOR TO COMMENCING DEMOLITION OR CONSTRUCTION ACTIVITIES. CONTRACTOR SHALL CONTACT ANY OTHER UTILITY COMPANIES WHO DO NOT SUBSCRIBE TO THE DIG TEST PROGRAM FOR LINE MARKINGS. THE CONTRACTOR BEARS SOLE RESPONSIBILITY FOR VERIFYING LOCATIONS OF EXISTING UTILITIES, SHOWN OR NOT SHOWN, AND FOR REPAIRING ANY DAMAGE DONE TO THESE FACILITIES.
11. ELECTRICAL, TELEPHONE, CABLE, WATER, FIBER OPTIC CABLE, AND GAS LINES REQUIRED TO BE REMOVED OR RELOCATED SHALL BE COORDINATED WITH THE AFFECTED UTILITY COMPANY. ADEQUATE TIME SHALL BE PROVIDED FOR RELOCATION AND CLOSE COORDINATION WITH THE UTILITY COMPANY IS NECESSARY TO PROVIDE A SMOOTH TRANSITION IN UTILITY SERVICE. CONTRACTOR SHALL PAY CLOSE ATTENTION TO EXISTING UTILITIES WITHIN ROAD RIGHT OF WAY DURING CONSTRUCTION.
12. THE CONTRACTOR SHALL COORDINATE WATER MAIN WORK WITH THE FIRE DEPT. AND THE CITY UTILITY DEPT. TO PLAN PROPOSED IMPROVEMENTS AND TO ENSURE ADEQUATE FIRE PROTECTION IS CONTINUALLY AVAILABLE TO THE EXISTING BUILDING. CONTRACTOR WILL BE RESPONSIBLE FOR ARRANGING/PROVIDING ANY REQUIRED WATER MAIN SHUT OFFS WITH THE CITY DURING CONSTRUCTION. ANY COSTS ASSOCIATED WITH WATER MAIN SHUT OFFS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND NO EXTRA COMPENSATION WILL BE PROVIDED.
13. ANY OTHER PAVING, FOUNDATION, CONDUIT, PIPES, AND DEBRIS SHOWN OR NOT SHOWN ON THIS PLAN SHALL BE REMOVED AFTER NOTIFICATION IS MADE TO THE OWNER AND AFTER THE CONTRACTOR CONFIRMS THE ITEM IS NO LONGER IN SERVICE.
14. KIMLEY-HORN AND ASSOCIATES, INC. IS NOT RESPONSIBLE FOR THE MEANS AND METHODS EMPLOYED BY THE CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACTS THAT ARE TO BE DEMOLISHED AND REMOVED FROM THE SITE. THE DESIGN AND CONSTRUCTION OF THE DEMOLITION PROJECT WAS PREPARED BASED ON SURVEY AND UTILITY INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, AND THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING HIS OWN SITE RECONNAISSANCE TO SCOPE HIS WORK AND TO CONFIRM WITH THE OWNERS OF EXISTING IMPROVEMENTS AND UTILITIES THE ABILITY AND PROCESS FOR THE REMOVAL OF PROPOSED DEMOLITION. THE GOAL OF DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF FUTURE DEVELOPMENT, REMOVAL, RELOCATION, OR PRESERVATION OF EXISTING IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FOLLOWING:
15. INSTALL TREE PROTECTION TO THE GREATEST EXTENTS POSSIBLE PRIOR TO DEMOLITION ACTIVITIES. DEMOLITION WITHIN THE HALF CRITICAL ROOT ZONE SHALL BE PERFORMED BY HAND. TREE PROTECTION SHALL BE EXPANDED TO MATCH EROSION CONTROL PLAN AS SOON AS DEMOLITION ACTIVITIES HAVE BEEN COMPLETED.


## LEGEND

	PROPERTY LINE
	ADJACENT PROPERTY LINE
	EASEMENT LINE
	WATER LINE
	WASTEWATER LINE
	STORM SEWER LINE
	GAS
	FENCE
	OVERHEAR ELECTRIC
	BENCHMARK
	FIRE HYDRANT
	WATER METER
	WATER MANHOLE
	WATER VAULT
	IRRIGATION VALVE
	WASTEWATER CLEANOUT
	WASTEWATER MANHOLE
	STORM SEWER GRATE INLET
	STORM SEWER MANHOLE
	GAS METER
	GAS SIGN
	GAS VALVE
	TELEPHONE BOX
	TELEPHONE MANHOLE
	ELECTRIC BOX
	ELECTRIC METER
	ELECTRIC MANHOLE
	UTILITY POLE
	GUY ANCHOR
	TRAFFIC SIGNAL
	SIGN
	DEMOLITION AREA: ITEMS TO BE REMOVED AS NOTED
	LIMITS OF CONSTRUCTION AREA
	EXISTING TREES TO REMAIN
	EXISTING TREES TO BE REMOVED

## BENCHMARKS


CP22: 3" BRASS DISC IN CONCRETE  
N 10165081.83; E 3092268.19

CP41: 3" BRASS DISC IN CONCRETE  
N10166207.91; E 3092268.19

[illegible]

# Kimley»»Horn

800 BURLESON ROAD, BUILDING 312, SUITE 150  
AUSTIN, TX 78744  
PHONE: 512-616-9942 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.  
TRPE Firm No. 928



06/21/2024

KHA PROJECT	DATE
064508610	JUNE 2024
SCALE: AS SHOWN	DESIGNED BY: JUE
	DRAWN BY: JAA
	CHECKED BY: RJM

## EXISTING CONDITIONS AND DEMO PLAN

**WORLDSPRINGS**  
**AUSTIN**  
CITY OF CEDAR PARK  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER




5 OF 31

~~XXXXXXXXXXXX~~



Plotted By: McKay, Ryan Date: June 20, 2024 03:10:37pm File Path: K:\EAU\_Civil\064508610-ARCO New Hope Hot Springs\CAD\PlanSheets\C - Erosion Control Plan.dwg

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and/or improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND

	SF	SILT FENCE
	TFD	TRIANGULAR FILTER DIKE
	TP	TREE PROTECTION
	IP	PROPOSED INLET PROTECTION
	CE	CONSTRUCTION ENTRANCE
	RB	ROCK BERM
	450	EXISTING CONTOURS
	450	PROPOSED CONTOURS
	LOC	LIMITS OF CONSTRUCTION AREA
		TREE TO REMAIN

NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. THE ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD AND/OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE TO KEEP PROJECT IN COMPLIANCE WITH THE CITY OF CEDAR PARK RULES AND REGULATIONS.
4. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
5. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE: SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
6. ADDITIONAL EROSION AND SEDIMENTATION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT THE TIME OF CONSTRUCTION.
7. REFERENCE EROSION CONTROL NOTES AND DETAILS ON SHEET 25.
8. ALL DISTURBED AREAS TO BE RE-VEGETATED TO MEET THE REQUIREMENTS OF THE CITY OF CEDAR PARK'S ORDINANCES.
9. SEE LANDSCAPE ARCHITECT PLANS FOR TREE PRESERVATION PLAN AND TREE LIST.
10. CONSTRUCTION SCREENING SHOULD BE PROVIDED ALONG THE PROPERTY LINE ADJACENT TO RESIDENTIAL LOTS.
11. DURING CONSTRUCTION OF ANY STRUCTURE, THE CITY SERVICE ADDRESS MUST BE POSTED ON A SIGN IN SUCH A POSITION AS TO BE PLAINLY VISIBLE AND LEGIBLE FROM THE STREET INDICATED IN THE CITY'S SERVICE ADDRESS.
12. CONCRETE WASHOUT SHOULD BE LOCATED A MINIMUM OF 50' AWAY FROM ANY ENVIRONMENTAL SENSITIVE FEATURES OR STORM INLETS.
13. STABILIZED CONSTRUCTION ENTRANCE TO BEGIN TEMPORARY SIDEWALK.
14. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY INSPECTOR AT TIME OF CONSTRUCTION.

BENCHMARKS

CP22: 3" BRASS DISC IN CONCRETE  
N 10165081.83; E 3092268.19  
CP41: 3" BRASS DISC IN CONCRETE  
N 10166207.91; E 3092268.19

No.	REVISIONS	DATE	BY

**Kimley»Horn**

6800 BURLERSON ROAD, BUILDING 312, SUITE 150  
AUSTIN, TX 78744  
PHONE: 512-816-9842 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.  
TBPE Firm No. 928



06/21/2024

KHA PROJECT	DATE	SCALE:	DESIGNED BY:	DRAWN BY:	CHECKED BY:
064508610	JUNE 2024	AS SHOWN	JUE	JAA	RJM

EROSION CONTROL  
PLAN

**WORLDSPRINGS  
AUSTIN**  
CITY OF CEDAR PARK  
WILLIAMSON COUNTY, TEXAS

SHEET NUMBER


6 OF 31

XXXXXXXXXX














Plotted By: McKay, Ryan Date: June 20, 2024 03:11:09pm File Path: K:\EAU\_Civil\064508610-ARCO New Hope Hot Springs\CAD\PlanSheets\C - Paving Plan.dwg

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND	
	PROPERTY LINE
	PROPOSED FIRE LANE
	SIDEWALK PAVEMENT
	HEAVY DUTY CONCRETE PAVEMENT
	LIGHT DUTY CONCRETE PAVEMENT
	PUBLIC PAVEMENT
	FIRE RATED PAVERS
	REF. LANDSCAPE PLANS

THESE PLAN AND GENERAL NOTES REFER TO:  
GEOTECHNICAL ENGINEERING REPORT  
(FIRM) ECS SOUTHWEST, LLP  
17-6421  
(DATE) 05/24/2024  
INCLUDING ALL REVISIONS AND ADDENDA TO THIS REPORT THAT MAY HAVE BEEN RELEASED AFTER THE NOTED DATE.



REVISIONS		DATE	BY
No.			

# Kimley»Horn

6800 BURLERSON ROAD, BUILDING 312, SUITE 150  
AUSTIN, TX 78744  
PHONE: 512-816-9942 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.  
TBP Firm No. 928



KHA PROJECT 064508610	DATE JUNE 2024	SCALE: AS SHOWN	DESIGNED BY: JUE	DRAWN BY: JAA	CHECKED BY: RJM
--------------------------	-------------------	-----------------	------------------	---------------	-----------------

## PAVING PLAN



**WORLDSPRINGS**  
**AUSTIN**  
CITY OF CEDAR PARK  
WILLIAMSON COUNTY, TEXAS

XXXXXXXXXX




















## LEGEND

	<p>AREA DESIGNATOR</p> <p>AREA IN ACRES</p> <p>Q100 FLOW IN CFS</p>
	<p>PROPERTY LINE</p>
	<p>EXISTING STORM DRAIN LINE</p>
	<p>EXISTING DRAINAGE DIVIDE</p>
	<p>EXISTING STORM DRAIN INLET</p>
	<p>EXISTING STORM DRAIN MANHOLE</p>
	<p>EXISTING STORM DRAIN HEADWALL</p>
	<p>EXISTING FLOW DIRECTION</p>
	<p>EXISTING CONTOUR</p>

[illegible]

**Kimley»»Horn**  
6800 BURLISON ROAD, BUILDING 312, SUITE 150  
AUSTIN, TX 78744  
PHONE: 512-516-9942 FAX: 512-418-1791  
WWW.KIMLEY-HORN.COM  
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.  
TBP Firm No. 928




06/21/2024	
KHA PROJECT 064508610	
DATE JUNE 2024	
SCALE: AS SHOWN	
DESIGNED BY: JUE	
DRAWN BY: JAA	
CHECKED BY: RUM	

# EXISTING DRAINAGE AREA MAP

WORLDSPRINGS  
AUSTIN  
CITY OF CEDAR PARK  
WILLIAMSON COUNTY, TEXAS

XXXXXXXXXXXX



[illegible]












































F:\THOMPSON - CEDAR PARK\PROJECTS\22-065-NEW HOPE WEST DRAWING\PRIVATE IMPROVEMENTS\PROP DAM.DWG, 12/19/2023, CHUCK BARRETT



0 100'  
SCALE: 1" = 100'

**LEGEND**

- PROPERTY BOUNDARY
- EXIST. STORM SEWER
- EXIST. CURB INLET
- EXIST. DRAINAGE AREA
- Tc EXIST. TIME OF CONCENTRATION
- EXIST. FLOW DIRECTION
- E-1 1.00 ACRES EXIST. DRAINAGE AREA ID DRAINAGE AREA ACREAGE

NOTE:  
1. IMPROVEMENTS INCLUDED IN THE APPROVED PLANS FOR SI-21-006 (SCOTTSDALE DRIVE) ARE SHOWN AS EXISTING ON THIS DRAINAGE AREA MAP.

NEW HOPE WEST PHASE  
PRIVATE INFRASTRUCTURE PLANS  
CEDAR PARK, TEXAS

EXISTING DRAINAGE AREAS

**MALONE ★ WHEELER**  
INC. 1995

CIVIL ENGINEERING ★ DEVELOPMENT CONSULTING ★ PROJECT MANAGEMENT  
5113 Southwest Pkwy, Suite 240  
Austin, Texas 78735  
Phone: (512) 899-0601 Fax: (512) 899-0655  
Firm Registration No. E-786



DESIGN BY: JSK/MV  
CHECKED BY: AV  
APPROVED BY: DB  
DATE: 10/19/2023

SHEET 09  
OF 33



FOR REFERENCE ONLY  
2023-32-SD







F:\THOMPSON - CEDAR PARK\PROJECTS\2023-06\NEW HOPE - WEST DRAWINGS\PRIVATE IMPROVEMENTS\2025 PROPOSED POND DETAILS & CALCULATIONS.DWG, 12/19/2023, ANTHONY VINCENT



NOTE:  
• LOCATION OF CONDUIT FROM SOLAR PANEL & LOGIC CONTROLLER TO VALVE & FLOAT NOT SHOWN. CONTRACTOR TO PROVIDE CONDUIT AS REQUIRED.

PROP. POND 4 TOTAL VOLUME				
CONTOUR	AREA	AVERAGE AREA	INCREMENTAL STORAGE (CF)	CUMULATIVE STORAGE (CF)
917.5	0	0	0	0
918	1,579	789.50	394.75	394.75
919	13,207	7,393.00	7,393.00	7,787.75
920	34,125	23,666.00	23,666.00	31,453.75
921	45,629	39,877.00	39,877.00	71,330.75
922	49,641	47,635.00	47,635.00	118,965.75
923	52,731	51,186.00	51,186.00	170,151.75
924	55,885	54,308.00	54,308.00	224,459.75
925	59,099	57,492.00	57,492.00	281,951.75
926	62,373	60,736.00	60,736.00	342,687.75
927	65,708	64,040.50	64,040.50	406,728.25
928	69,103	67,405.50	67,405.50	474,133.75
929	72,559	70,831.00	70,831.00	544,964.75
930	76,075	74,317.00	74,317.00	619,281.75

PROP. POND 4 WQ				
CONTOUR	AREA	AVERAGE AREA	INCREMENTAL STORAGE (CF)	CUMULATIVE STORAGE (CF)
917.5	10	0	0	0
918	1,579	794.50	397.25	397.25
919	13,207	7,393.00	7,393.00	7,790.25
920	34,125	23,666.00	23,666.00	31,456.25
921	45,629	39,877.00	39,877.00	71,333.25
921.5	47,635	46,632.00	23,316.00	94,649.25
922	49,641	48,638.00	24,319.00	118,968.25


PROP. POND 4 DETENTION				
CONTOUR	AREA	AVERAGE AREA	INCREMENTAL STORAGE (CF)	CUMULATIVE STORAGE (CF)
921.5	47,635	0	0	0
922	49,641	48,638.00	24,319.00	24,319.00
923	52,731	51,186.00	51,186.00	75,505.00
924	55,885	54,308.00	54,308.00	129,813.00
925	59,099	57,492.00	57,492.00	187,305.00
926	62,373	60,736.00	60,736.00	248,041.00
927	65,708	64,040.50	64,040.50	312,081.50
928	69,103	67,405.50	67,405.50	379,487.00
929	72,559	70,831.00	70,831.00	450,318.00
930	76,075	74,317.00	74,317.00	524,635.00

NEW HOPE WEST PHASE  
PRIVATE INFRASTRUCTURE PLANS  
CEDAR PARK, TEXAS

PROPOSED POND PLAN

**MALONE ★ WHEELER**  
SINCE 1975  
INC.

CIVIL ENGINEERING ★ DEVELOPMENT CONSULTING ★ PROJECT MANAGEMENT  
5113 Southwest Parkway, Suite 240  
Austin, Texas 78735  
Phone: (512) 899-0601 Fax: (512) 899-0655  
Firm Registration No. E-786



DESIGN BY : JSK  
CHECKED BY : MV  
APPROVED BY : DB  
DATE : 06/24/22

SHEET 24  
OF 33

2023-32-SD

FOR REFERENCE ONLY  
2023-32-SD



OPERATIONS & TEST CYCLE CONTROL FOR BATCH DETENTION POND VALVE CONTROLLER

SYSTEM OVERVIEW

-THIS SYSTEM SHALL UTILIZE A SINGLE FLOAT SWITCH TO ACTIVATE TIMERS THAT CONTROL A SINGLE VALVE OPEN AND CLOSE COMMANDS.

MODES OF OPERATION

-THE SYSTEM SHALL HAVE THREE BASIC MODES OF OPERATION; OFF, MANUAL, AND AUTOMATIC.  
-WHEN THE ON/OFF SWITCH IS IN THE 'OFF' POSITION, POWER SHALL NOT BE PROVIDED TO THE VALVE ACTUATOR OR VALVE PROGRAMMABLE LOGIC CONTROLLER (PLC).  
-WHEN THE ON/OFF SWITCH IS IN THE 'ON' POSITION, THE SYSTEM SHALL OPERATE BASED ON THE OPEN/AUTO/CLOSE SWITCH POSITION. THE SOLAR CIRCUIT IS FULLY OPERATIONAL, TO CHARGE THE BATTERY, WHITE THE SWITCH IS IN THE 'ON' OR 'OFF' POSITION.

MANUAL CONTROL

-THE OPEN/AUTO/CLOSE SWITCH SHALL HAVE TWO MANUAL POSITIONS, OPEN AND CLOSE.  
-THERE SHOULD BE A FIVE SECOND DELAY BEFORE THEY SYSTEM SHALL RECOGNIZE THE AUTO POSITION, SO THE VALVE CAN BE SWITCHED FROM OPEN TO CLOSE WITHOUT AUTOMATIC OPERATION.  
-WHEN THE OPEN/AUTO/CLOSE SWITCH IS IN THE OPEN POSITION, THE VALVE SHALL OPEN AND STAY OPEN WHEN THE OPEN/AUTO/CLOSE SWITCH IS IN THE CLOSE POSITION, THE VALVE SHALL CLOSE AND STAY CLOSED.

AUTOMATIC CONTROL

-VALVE SHALL HAVE A DEFAULT CLOSED POSITION. AN INSTALLED FLOAT SWITCH SHALL INDICATE THE PRESENCE OF WATER FOLLOWING A RAIN EVENT.  
-UPON ACTIVATION OF THE FLOAT SWITCH, A 12 HOUR DETENTION TIMER SHALL BE STARTED. THE VALVE SHALL REMAIN CLOSED.  
-AFTER THE 12 HOUR TIMER EXPIRES, THE VALVE SHALL OPEN. VALVE SHALL

REMAIN OPEN WHILE WATER IS DRAINING AND REMAIN OPEN AS LONG AS THE FLOAT SWITCH CONTACT REMAINS CLOSED.  
-WHEN THE WATER LEVEL FALLS BELOW THE FLOAT SWITCH ELEVATION, AND THE FLOAT SWITCH CONTACT OPENS, A 2 HOUR TIMER SHALL BE STARTED. AFTER THE 2 HOUR TIMER EXPIRES, THE VALVE SHALL CLOSE.  
-WHEN THE VALVE CLOSES, THE SYSTEM BEGINS A STANDBY PERIOD, WITH THE VALVE CLOSED, UNTIL THE WATER LEVEL RISES ABOVE THE FLOAT SWITCH ELEVATION.

ADDITIONAL FEATURES

THE FOLLOWING FEATURES SHALL BE PART OF THE NORMAL CONTROL SEQUENCE OF OPERATION.

VALVE EXERCISE

-A TIMER IN THE VALVE CONTROLLER, SET AT ONE WEEK, SHALL START WHEN THE FLOAT SWITCH CONTACT HAS REMAINED OPEN FOR THE SEVEN DAYS. THE VALVE CONTROLLER SHALL OPEN THE VALVE FOR 120 MINUTES. AFTER 120 MINUTES THE VALVE CONTROLLER SHALL CLOSE. THE VALVE.

VALVE ACTUATION TIME

-A TIMER IN THE VALVE CONTROLLER SHALL MONITOR THE VALVE OPEN OR CLOSE COMMAND TIME. THIS TIMER SHALL BE SYNCHRONIZED WITH THE VALVE OPENING AND CLOSING SEQUENCE, TO SAVE BATTERY POWER.

CHANGING TIMER SET POINTS

-FOUR TIMERS SHALL BE PROVIDED AND MODIFIED AS NEEDED FOR FINE TUNED CONTROL. THESE TIMERS, IN ORDER OF DISPLAY ON THE PLC SCREEN, SHALL BE:  
-DELAY ON TIME (DEFAULT 12 HOURS) : TIME DELAY BETWEEN THE FLOAT INDICATING WATER IS PRESENT AND THE VALVE AUTOMATICALLY OPENING.  
-DELAY OFF TIME (DEFAULT 2 HOURS) : TIME DELAY BETWEEN THE FLOAT INDICATING WAS HAS EMPTIED AND THE VALVE AUTOMATICALLY CLOSING.  
-EXERCISE TIME (DEFAULT 120 MINUTES) : LENGTH OF TIME THE VALVE SHALL STAY OPEN WHILE IN EXERCISE MODE.  
-ACTUATION TIME (DEFAULT 60 SECONDS) : LENGTH OF TIME THE OPEN OR CLOSE COMMANDS SHALL BE GIVEN TO THE VALVE ACTUATOR.

NOTES:

1. WATER QUALITY POND IS A BATCH DETENTION POND PER TCEQ DESIGN CRITERIA.
2. OUTLET STRUCTURE FOR WATER QUALITY POND IS A PERFORATED PIPE (PER DETAIL) WITH A DOWNSTREAM ACTUATOR VALVE.
3. ACTUATOR VALVE IS TO BE CONTROLLED SUCH THAT A 12 HOUR MINIMUM DETENTION TIME IS ACHIEVED AND SHALL REMAIN OPEN FOR TWO HOURS AFTER THE LEVEL SENSOR INDICATES THE BASIN IS EMPTY TO ALLOW ANY REMAINING SHALLOW WATER TO BE DISCHARGED.
4. ORIFICE/PIPE HAS BEEN SIZED TO ALLOW COMPLETE DRAWDOWN OF WATER QUALITY VOLUME WITHIN 48 HOURS AFTER THE 12 HOUR DETENTION TIME.
5. SEE POND PLAN SHEET FOR MORE DETAILS.
6. ELECTRIC CONTROL PANEL SHALL BE CAPABLE OF:  
1. 12 HOUR DELAY PRIOR TO OPENING ACTUATED VALVE  
2. PROVIDE MANUAL OVERRIDE TO ACTUATOR

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: NEW HOPE-WEST PHASE

Date Prepared: 10/30/2023

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348. Characters shown in red are data entry fields. Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project: Calculations from RG-348 Pages 3-27 to 3-30

Page 3-29 Equation 3.3:  $L_M = 27.2(A_N \times P)$

where:  $L_M$  TOTAL PROJECT = Required TSS removal resulting from the proposed development = 80% of increased load  
 $A_N$  = Net increase in impervious area for the project  
 $P$  = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County =	Williamson	
Total project area included in plan *	27.47	acres
Predevelopment impervious area within the limits of the plan *	0.00	acres
Total post-development impervious area within the limits of the plan *	20.60	acres
Total post-development impervious cover fraction *	0.75	
P =	32	inches

$L_M$  TOTAL PROJECT = 17932 lbs.

\* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = 1

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =	P:4	
Total drainage basin/outfall area =	27.47	acres
Predevelopment impervious area within drainage basin/outfall area =	0.00	acres
Post-development impervious area within drainage basin/outfall area =	20.60	acres
Post-development impervious fraction within drainage basin/outfall area =	0.75	
$L_M$ THIS BASIN =	17932	lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = BATCH DET  
Removal efficiency = 91 percent

Aqualogic Cartridge Filter  
Bioretention  
Contech StormFilter  
Constructed Wetland  
Extended Detention  
Grassy Swale  
Retention / Irrigation  
Sand Filter  
Stormceptor  
Vegetated Filter Strips  
Vortechs  
Wet Basin  
Wet Vault

4. Calculate Maximum TSS Load Removed ( $L_R$ ) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7:  $L_R = (BMP \text{ efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where:

$A_C$  = Total On-Site drainage area in the BMP catchment area  
 $A_i$  = Impervious area proposed in the BMP catchment area  
 $A_p$  = Pervious area remaining in the BMP catchment area  
 $L_R$  = TSS Load removed from this catchment area by the proposed BMP

$A_C$  = 27.47 acres  
 $A_i$  = 20.60 acres  
 $A_p$  = 6.87 acres  
 $L_R$  = 20866 lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired  $L_M$  THIS BASIN = 17932 lbs.  
F = 0.86

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area. Calculations from RG-348 Pages 3-34 to 3-36





Rainfall Depth = 1.38 inches  
Post Development Runoff Coefficient = 0.56  
On-site Water Quality Volume = 77061 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37


Off-site area draining to BMP = 0.00 acres  
Off-site impervious cover draining to BMP = 0.00 acres  
Impervious fraction of off-site area = 0  
Off-site Runoff Coefficient = 0.00  
Off-site Water Quality Volume = 0 cubic feet

Storage for Sediment = 15412  
Total Capture Volume (required water quality volume(s) x 1.20) = 92473 cubic feet

FOR REFERENCE ONLY  
2023-32-SD



COMPONENT	DESCRIPTION
Power	System to be solar powered. See plans for location of solar panels. Actuator and Controller are 24V. Backup battery to be provided.
Logic Controller	Allen Bradley 810 Programmable Logic Controller. (Or approved equal). See attached notes for operations and test cycle control.
Parts Enclosure	Saginaw SCE-24EL246SSLP NEMA 4X, 304 stainless steel lockable enclosure. (Or approved equal)
Circuit	See below block diagram for controller circuit.
Nature of Event Sensing	ECO-FLOAT Model G Mercury Free Float Sensor. (Or approved equal). Float to be located within a concrete box with manhole cover for access. Stormwater will flow through trash rack and perforated pipe to remove vegetation and debris prior to reaching the float.
Actuator	EIM HQ series Electric Quarter turn actuator Model HQ-015 with no local controls for 24V power supply with integral condensation heater and manual handwheel override with padlock capability. (Or approved equal).
Valve Type	Henry Pratt Ballcentric Plug Valve with over torque sensors. Able to withstand 100 PSI minimum. (Or approved equal).




CONTOUR	AREA	AVERAGE AREA	INCREMENTAL STORAGE (CF)	CUMULATIVE STORAGE (CF)
917.5	10	0	0	0
918	1,579	794.50	397.25	397.25
919	13,207	7,393.00	7,393.00	7,790.25
920	34,125	23,666.00	23,666.00	31,456.25
921	45,629	39,877.00	39,877.00	71,333.25
921.5	47,635	46,632.00	23,316.00	94,649.25
922	49,641	48,638.00	24,319.00	118,968.25

F:\THOMPSON - CEDAR PARK\PROJECTS\2023-06\NEW HOPE - WEST DRAWINGS\PRIVATE PHASE IMPROVEMENTS\PROPOSED POND DETAILS & CALCULATIONS.DWG, 12/19/2023, CHUCK BARRETT

NEW HOPE WEST PHASE  
PRIVATE INFRASTRUCTURE PLANS  
CEDAR PARK, TEXAS  
PROPOSED POND DETAILS & CALCULATIONS

MALONE ★ WHEELER  
INC. SINCE 1995

CIVIL ENGINEERING ★ DEVELOPMENT CONSULTING ★ PROJECT MANAGEMENT  
5113 Southwest Plaza, Suite 260  
Austin, Texas 78735  
Phone: (512) 899-0601 Fax: (512) 899-0655  
Firm Registration No. E-786



DESIGN BY: JSK  
CHECKED BY: MV  
APPROVED BY: DB  
DATE: 06/24/22

SHEET 26  
OF 33

2023-32-SD





## ATTACHMENT N: Inspection, Maintenance, Repair and Retrofit Plan

There is no permanent BMP proposed with this project.





## ATTACHMENT O: Pilot-Scale Field Testing Plan

A plan for pilot-scale field testing is not required for this project.





## ATTACHMENT P: Measures for Minimizing Surface Stream Contamination

Surface streams do not exist on site. All disturbed areas will be re-vegetated as soon as practical.



***SECTION 4:  
TEMPORARY STORWATER  
SECTION***



# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Ryan McKay

Date: 06/21/2024

Signature of Customer/Agent:



Regulated Entity Name: New Hope Land, LP

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

- ☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.



- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☐ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: N/A

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:



- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.



- ☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- ☒ N/A
12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

### ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.



- 18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

- 20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



## ATTACHMENT A: Spill Response Actions

If there is an accidental spill on site, the contractor shall respond with appropriate action. The contractor will be required to contact the owner and in turn the owner will contact the TCEQ in the event of a spill on site. In addition to the following guidance, reference the latest version of TCEQ's Technical Guidance Manual (TGM) RG-348 Section 1.4.16.

### Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

### Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
  - Contain the spread of the spill.
  - Recover spilled materials.
  - Clean the contaminated area and properly dispose of contaminated materials.

### Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, cleanup using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.



## Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at (512)339-2929 (Austin) or (254)751-0335 (Waco) between 8 AM and 5PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
  - For spills of federal reportable quantities, in conformance with requirements in 40 CFR parts 110,119 and 302, the contractor should notify the National Response Center at (800) 424-8802.
  - Notification should first be made by telephone and followed up with a written report.
  - The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
  - Other agencies which may need to be consulted include, but not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.



## ATTACHMENT B: Potential Source of Contamination

**Potential Source:** Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping.

**Preventative Measures:** Vehicle maintenance will be performed within the construction staging area or a local maintenance shop.

**Potential Source:** Miscellaneous trash and litter from construction workers and material wrappings.

**Preventative Measures:** Trash containers will be placed throughout the site to encourage proper disposal of trash.

**Potential Source:** Silt leaving the site.

**Preventative Measures:** Contractor will install all temporary best management practices prior to start of construction including the stabilized construction entrance to prevent tracking onto adjoining streets.

**Potential Source:** Construction Debris

**Preventative Measures:** Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

**Potential Source:** Soil and Mud from Construction Vehicle tires as they leave the site.

**Preventative Measures:** A stabilized construction exit shall be utilized as vehicles leave the site. Any soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

**Potential Source:** Sediment from soil, sand and gravel and excavated materials stock piled on site.

**Preventative Measures:** Silt fence shall be installed on the down gradient side of the stock piled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

**Potential Source:** Portable toilet spill.

**Preventative Measures:** Toilets on the site will be emptied on a regular basis by the contracted toilet company.



## ATTACHMENT C: Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage to be disturbed is listed in parentheses next to each activity.

Intended Schedule or Sequence of Major Activities:

1. Construct Access (0.03 Acres)
2. Installation of Temporary BMPs (8.41 Acres)
3. Initiate Grubbing and Topsoil Stripping of Site (8.41 Acres)
4. Rough Subgrade Preparation (earthwork, grading, street and drainage excavation and embankment) (8.41 Acres)
5. Wet and Dry Utility Construction (1.57 Acres)
6. Final Subgrade Preparation (5.40 Acres)
7. Instillation of Base Materials (5.40 Acres)
8. Paving Activities (5.40 Acres)
9. Site cleanup and Removal of Temporary BMPs (8.41 Acres) Maximum total construction time is not expected to exceed 12 months.



## ATTACHMENT D: Temporary Best Management Practices And Measures

As shown in the erosion and sediment control plan, to protect surface streams during construction activities, silt fence and triangular filter dike will be placed on the downslope along the property line where construction activities end. In addition, a construction entrance will be utilized to filter stormwater through the rock material and inlet protection will be placed at installed inlets.





## ATTACHMENT E: Request to Temporarily Seal a Feature

This attachment is not applicable. No features will be sealed on this site.



## ATTACHMENT F - Structural Practices

The plan for temporary structural controls on this site includes placing silt fence and triangular filter dike at the down slope of the site that will collect sediment prior to exiting the site. For continued effective use, the silt fence and triangular filter dike will need to be cleaned out when appropriate.





## ATTACHMENT G: Drainage Area Map

Refer to Existing and Proposed Drainage Area Maps in Construction Plans.

## ATTACHMENT H: Temporary Sediment Pond(s) Plans and Calculations

This attachment is not applicable. There will be no temporary sediment pond or basin provided on site.



## ATTACHMENT I: Inspection and Maintenance for BMPs

### A. Inspection Schedule

1. All disturbed areas, as well as all erosion and sediment control devices, will be inspected according to one of the following schedules:
  - a) at least every seven (7) calendar days and within 24 hours after a rainfall of 0.25" or greater, or
  - b) every seven (7) days on the same day of the week each week, regardless of whether or not there has been a rainfall event since the previous inspection.
2. Inspections will occur on the schedule provided in this plan and any changes made to the schedule must adhere to the following:
  - a) the schedule can change a maximum of one time each month,
  - b) the schedule change must be implemented at the beginning of a calendar month, and
  - c) the reason for the schedule change must be documented in this plan (an inspection schedule form is located below).

### B. Inspection Reports

1. Completed inspection reports (see below) will include the following information:
  - a) scope of the inspection,
  - b) date of the inspection,
  - c) name(s) of personnel making the inspection,
  - d) reference to qualifications of inspection personnel,
  - e) observed major construction activities, and
  - f) actions taken as a result of the inspection.
2. All disturbed areas (on and off-site), areas for material storage locations where vehicles enter or exit the site, and all of the erosion and sediment controls that were identified as part this plan must be inspected. The inspection report must state whether the site was in compliance or identify any incidents of non-compliance. The report will be signed by the qualified inspector in accordance with the TPDES general permit and filed in this plan. A sample Inspection Report is included below along with an Inspector Qualification Form. All reports and inspections required by the general construction permit will be completed by a duly authorized representative.
3. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in this plan, and wherever possible, those changes implemented before the next storm event or as soon as practicable. A list of maintenance guidelines are included below.

4. Inspection reports will be kept in the Operator's file, along with this plan, for at least three years from the date that the NOT is submitted to the TCEQ for the construction site.

### **C. Final Stabilization**

Final stabilization of the construction site has been achieved when all soil disturbing activities at the site have been completed, and a uniform (e.g., evenly distributed, without large bare areas) perennial vegetative cover with a density of 70 percent of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures. If a vegetative cover cannot be established, equivalent permanent stabilization measures (such as riprap, gabions, or geotextiles) can be employed. When these conditions have been met, BMPs can be removed from the construction area.



**Inspector Qualifications\***

Inspector Name: \_\_\_\_\_

Qualifications (Check as appropriate and provide description):

- ☐ Training Course \_\_\_\_\_
- ☐ Supervised Experience \_\_\_\_\_
- ☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_

Qualifications (Check as appropriate and provide description):

- ☐ Training Course \_\_\_\_\_
- ☐ Supervised Experience \_\_\_\_\_
- ☐ Other \_\_\_\_\_

Inspector Name: \_\_\_\_\_

Qualifications (Check as appropriate and provide description):

- ☐ Training Course \_\_\_\_\_
- ☐ Supervised Experience \_\_\_\_\_
- ☐ Other \_\_\_\_\_

*\*Personnel conducting inspections must be knowledgeable of the general permit, familiar with the construction site, and knowledgeable of the SWP3 for the site.*

## INSPECTION SCHEDULE

Inspections must be conducted:

- **Option 1** – at least once every 7 calendar days and within 24 hours of the end of a storm event of 0.25 inch or greater
- **Option 2** – at least once every 7 calendar days, regardless of whether or not there has been a rainfall event since the previous inspection.

Any changes to the schedule are conducted in accordance with the following:

- the schedule is changed a maximum of one time each month,
- the schedule change must be implemented at the beginning of a calendar month, and
- the reason for the schedule change must be documented below.

Date	Schedule Option	Reason for Schedule Change





ACTIONS TO BE TAKEN	RESPONSIBLE PERSON(S)	DUE DATE	DATE COMPLETED	INITIALS

NOTE: These reports will be kept on file as part of the Storm Water Pollution Prevention Plan for at least three years. A copy of the SWP3 will be kept at the site at all times during construction.

**CERTIFICATION STATEMENT:** *"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."*

Name:

Address:

Telephone:

Site Location:

Inspector Signature:

Date:



## MAINTENANCE GUIDELINES

1. Below are some maintenance practices to be used to maintain erosion and sediment controls:
  - All control measures will be inspected according to the schedule identified in Appendix E.
  - All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
  - BMP Maintenance (as applicable)
    - Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.
    - Silt fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
    - Drainage swale will be inspected and repaired as necessary.
    - Inlet control will be inspected and repaired as necessary.
    - Check dam will be inspected and repaired as necessary.
    - Straw bale dike will be inspected and repaired as necessary.
    - Diversion dike will be inspected and any breaches promptly repaired.
    - Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
    - If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must work with the owner or operator of the property to remove the sediment.
    - Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.
2. To maintain the above practices, the following will be performed:
  - Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of storm water controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.
  - Any necessary revisions to the SWP3 as a result of the inspection must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the SWP3 and wherever possible those changes implemented before the next storm event.
  - Personnel selected for inspection and maintenance responsibilities must be knowledgeable of the general permit, familiar with the construction site, and knowledgeable of the SWP3 for the site.

## ATTACHMENT J: Schedule of Interim and Permanent Soil Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

1. Seeding: Disturbed areas subject to erosion shall be stabilized by seeding and watering to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
2. Sodding and Wood Mulch: As per the project landscaping plan, Sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a. The dates when major grading activities occur;
- b. The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c. The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

1. Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.
2. Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.
3. In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

### Maintenance

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)
- Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as



silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.

- Silt fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must work with the owner or operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

- Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of stormwater controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.

***SECTION 5:  
ADDITIONAL FORMS***



# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Worldsprings Austin

Regulated Entity Location: 5515 Balcones Drive, Austin, Texas 78731

Name of Customer: ARCO/MURRAY National Entertainment

Contact Person: Rachel Husting

Phone: 331-801-1116

Customer Reference Number (if issued):CN \_\_\_\_\_

Regulated Entity Reference Number (if issued):RN \_\_\_\_\_

### Austin Regional Office (3373)

☐ Hays

☒ Travis

☒ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☐ Recharge Zone

☒ Contributing Zone

☐ Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	8.00 Acres	\$ 5,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: 

Date: 06/20/2024

# Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

## ***Water Pollution Abatement Plans and Modifications***

### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

### ***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150





# TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other
<b>2. Customer Reference Number</b> (if issued)	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a>	<b>3. Regulated Entity Reference Number</b> (if issued)
CN 606043032		RN

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)		3/11/2024	
<input type="checkbox"/> New Customer <input checked="" type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership					
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>					
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)				<i>If new Customer, enter previous Customer below:</i>	
New Hope Land, LP					
<b>7. TX SOS/CPA Filing Number</b>		<b>8. TX State Tax ID</b> (11 digits)		<b>9. Federal Tax ID</b>	<b>10. DUNS Number</b> (if applicable)
0804343556		32082174148		(9 digits) 87-3960448	
<b>11. Type of Customer:</b>		<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input checked="" type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		<input type="checkbox"/> Other:	
<b>12. Number of Employees</b>				<b>13. Independently Owned and Operated?</b>	
<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input checked="" type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator <input type="checkbox"/> Other:					
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant					
<b>15. Mailing Address:</b>					
5515 Balcones Dr					
City		Austin		State	TX
ZIP		78731		ZIP + 4	
<b>16. Country Mailing Information</b> (if outside USA)				<b>17. E-Mail Address</b> (if applicable)	
				chris@cordovarev.com	
<b>18. Telephone Number</b>		<b>19. Extension or Code</b>		<b>20. Fax Number</b> (if applicable)	

**SECTION III: Regulated Entity Information****21. General Regulated Entity Information** (If "New Regulated Entity" is selected, a new permit application is also required.)
☒ New Regulated Entity    ☐ Update to Regulated Entity Name    ☐ Update to Regulated Entity Information

*The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).*

**22. Regulated Entity Name** (Enter name of the site where the regulated action is taking place.)

Worldsprings Austin

**23. Street Address of the Regulated Entity:**

(No PO Boxes)

City

State

ZIP

ZIP + 4

**24. County**

If no Street Address is provided, fields 25-28 are required.

**25. Description to****Physical Location:**

NEC CO-180 &amp; E New Hope Dr

**26. Nearest City****State****Nearest ZIP Code**

Cedar Park

TX

78613

*Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).*

**27. Latitude (N) In Decimal:****28. Longitude (W) In Decimal:**

Degrees

Minutes

Seconds

Degrees

Minutes

Seconds

30

32

17.4

-97

48

48.7

**29. Primary SIC Code****30. Secondary SIC Code****31. Primary NAICS Code****32. Secondary NAICS Code**

(4 digits)

(4 digits)

(5 or 6 digits)

(5 or 6 digits)

4214

4225

493110

492110

**33. What is the Primary Business of this entity?** (Do not repeat the SIC or NAICS description.)

Commercial Land Development

**34. Mailing****Address:**

City

State

ZIP

ZIP + 4

**35. E-Mail Address:****36. Telephone Number****37. Extension or Code****38. Fax Number** (if applicable)

( ) -

( ) -

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.




<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

## **SECTION IV: Preparer Information**

<b>40. Name:</b>	Ryan McKay	<b>41. Title:</b>	Civil Engineer
<b>42. Telephone Number</b>	<b>43. Ext./Code</b>	<b>44. Fax Number</b>	<b>45. E-Mail Address</b>
(512) 518-4875		( ) -	ryan.mckay@kimley-horn.com

## **SECTION V: Authorized Signature**

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

<b>Company:</b>	New Hope Land, LP	<b>Job Title:</b>	Owner
<b>Name (In Print):</b>	Christopher Whitworth	<b>Phone:</b>	(512) 956-5600
<b>Signature:</b>		<b>Date:</b>	7/08/27

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I Christopher Whitworth,  
Print Name  
Manager of New Hope Land BP, LLC general partner  
Title - Owner/President/Other  
of New Hope Land LP,  
Corporation/Partnership/Entity Name  
have authorized Ryan McKay  
Print Name of Agent/Engineer  
of Kimley-Horn and Associates Inc  
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.



SIGNATURE PAGE:

  
Applicant's Signature

6/18/24  
Date

THE STATE OF TEXAS §

County of TRAVIS §

BEFORE ME, the undersigned authority, on this day personally appeared CHRISTOPHER WHITWORTH known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 18TH day of JUNE, 2024.

  
NOTARY PUBLIC

MICHAEL PREZZATO  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 08-24-2025

