FOR ARKA MONTESSORI ACADEMY

PREPARED FOR ARKA LEANDER INVESTMENTS, LLC.

Site Development Permit No. 24-XXXX

Job No. 23-00436

JULY 2024



FOR ARKA MONTESSORI ACADEMY

PREPARED FOR ARKA LEANDER INVESTMENTS, LLC.



Prepared By:

ESP Associates, INC.
TBPE Registration #159 / TBPLS Registration #10004100
12940 Country Parkway
San Antonio, Texas 78216-2004
(210) 349-3271

Site Development Permit No. 24-XXXX

Job No. 23-00436

JULY 2024



Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- When an application is deemed administratively complete, the technical review period begins. The regional
 office will distribute copies of the application to the identified affected city, county, and groundwater
 conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
 to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Arka Leander Investments, LLC				2. Regulated Entity No.:				
3. Customer Name: Arka Leander Investments, LLC		4. Cı	4. Customer No.:					
5. Project Type: (Please circle/check one)	New	Modification Extension		Exception				
6. Plan Type: (Please circle/check one)	WPAP CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential	Non-r	Non-residential 8. Site		te (acres): 1.698			
9. Application Fee:	\$4,000	10. P	10. Permanent BMP(s):		Water Quality Inlets & Underground Storage			
11. SCS (Linear Ft.):		12. A	12. AST/UST (No. Tanks):			ıks):	N/A	
13. County:	Williamson	14. Watershed:		Brushy Creek				

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)	_	_	_X_		
Region (1 req.)		_	_X_		
County(ies)	_	_	_X_		
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrell X_LeanderLiberty HillPflugervilleRound Rock		

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	_		_	_	_
Region (1 req.)	_				_
County(ies)	_		_		_
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the appl application is hereby submitted to TCEQ for administra	
Ravindra Maddi, Arka Leander Investments LL	С
Print Name of Customer/Authorized Agent	
Ravindra Madd	7/26/2024
Signature of Customer/Authorized Agent	Date

FOR TCEQ INTERNAL USE ONLY	7 -			
Date(s)Reviewed:	Date Ad	Date Administratively Complete:		
Received From:	Correct	Number of Copies:		
Received By:	Distribu	ition Date:		
EAPP File Number:	Complex	x:		
Admin. Review(s) (No.):	No. AR	Rounds:		
Delinquent Fees (Y/N):	Review '	Time Spent:		
Lat./Long. Verified:	SOS Cus	stomer Verification:		
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):		
Core Data Form Complete (Y/N):	Check:	Signed (Y/N):		
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):		

Contributing Zone Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Ravindra Maddi

Date: 7/19/2024

Signature of Customer/Agent:

Regulated Entity Name: Arka Leander Investments, LLC

Project Information

1. County: Williamson County

2. Stream Basin: Brushy Creek

3. Groundwater Conservation District (if applicable): N/A

4. Customer (Applicant):

Contact Person: <u>Ravindra Maddi</u>
Entity: <u>Arka Leander Investments, LLC</u>
Mailing Address: <u>2309 Palmetto Way</u>

City, State: Southlake, Texas Zip: 76902
Telephone: ____ Fax: ____

Email Address: ravidra.maddi@gmail.com

5.	Agen	nt/Representative (If any):	
	Entit Maili City, Telep	ract Person: Ariella Meadows y: ESP Associates, INC ing Address: 12940 County Parkway State: San Antonio, Texas phone: 210-349-3271 il Address: ameadows@espassiociates.com	Zip: <u>78216</u> Fax: <u>210-349-2561</u>
6.	Proje	ect Location:	
	<u></u> ⊤	The project site is located inside the city limits the project site is located outside the city limit urisdiction) of The project site is not located within any city's	s but inside the ETJ (extra-territorial
7.	p	The location of the project site is described belorovided so that the TCEQ's Regional staff can boundaries for a field investigation.	-
	<u>T</u>	the left onto I-35 S, merge onto I-35 S for 2 Take the ramp to US 183 N/Lampasas. Mer and continue onto Route 183A, stay on Rou San Gabriel Pkwy. Turn left onto San Gabrie 1.5 miles. The destination will be on right.	.9 miles. Take the exit toward US-183 N, ge onto US-183 N, take US-183 N for 11.6 ute 183A for 9.5 miles and take exit from
8.		Attachment A - Road Map. A road map showing oroject site is attached. The map clearly shows	_
9.		Attachment B - USGS Quadrangle Map. A cop Quadrangle Map (Scale: 1" = 2000') is attached	
		✓ Project site boundaries. ✓ USGS Quadrangle Name(s).	
10	p	Attachment C - Project Narrative. A detailed roroject is attached. The project description is contains, at a minimum, the following details:	
		Area of the site Offsite areas Impervious cover Permanent BMP(s) Proposed site use Site history Previous development Area(s) to be demolished	

11. Existing project site conditions are noted below:
Existing commercial site Existing industrial site Existing residential site Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Not cleared) Other:
12. The type of project is:
Residential: # of Lots: Residential: # of Living Unit Equivalents: Commercial Industrial Other:
13. Total project area (size of site): <u>1.698</u> Acres
Total disturbed area: <u>1.821</u> Acres
14. Estimated projected population: <u>0</u>
15. The amount and type of impervious cover expected after construction is complete is shown below:
Table 1 - Impervious Cover

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	13907.34	÷ 43,560 =	0.319
Parking	23125.72	÷ 43,560 =	0.531
Other paved surfaces	10283.55	÷ 43,560 =	0.236
Total Impervious Cover	47,316.61	÷ 43,560 =	1.086

Total Impervious Cover $\underline{1.086}$ ÷ Total Acreage $\underline{1.698}$ X 100 = $\underline{0.64}$ % Impervious Cover

16. X Attachment I	D - Factors Affecting Surface Water Quality.	A detailed description of all
factors that c	ould affect surface water quality is attached.	If applicable, this includes the
location and	description of any discharge associated with i	industrial activity other than
construction.		

17. \boxtimes Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

For Road Projects Only

Complete questions 18 - 23 if this application is exclusively for a road project. \bowtie N/A 18. Type of project: TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways. 19. Type of pavement or road surface to be used: Concrete Asphaltic concrete pavement Other: 20. Right of Way (R.O.W.): Length of R.O.W.: feet. Width of R.O.W.: feet. L x W = $Ft^2 \div 43,560 Ft^2/Acre = acres.$ 21. Pavement Area: Length of pavement area: _____ feet. Width of pavement area: _____ feet. Pavement area _____ acres ÷ R.O.W. area _____ acres x 100 = _____% impervious cover. 22. A rest stop will be included in this project. A rest stop will not be included in this project. 23. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ. Stormwater to be generated by the Proposed Project 24. Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project 25. Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied. \times N/A 26. Wastewater will be disposed of by: On-Site Sewage Facility (OSSF/Septic Tank): Attachment F - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities. Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285. Sewage Collection System (Sewer Lines): The sewage collection system will convey the wastewater to the Leander (name) Treatment Plant. The treatment facility is: X Existing. Proposed. N/A Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s)

27. Tanks and substance stored:

 \times N/A

greater than or equal to 500 gallons.

Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1			
2			
3			

AST NUTTIBET	Size (Guii	Olisj	3	torea		i alik iviateriai
4						_
5						
	1	<u> </u>		Tot	al x 1	L.5 = Gallon
one-half (1 one tank sy times the cu	be placed within a 1/2) times the stora stem, the containmoundative storage can	ge capacit ent structu apacity of	y of the sure is size all systen	system. For faced to capture of the	cilitie ne an	s with more than nd one-half (1 1/2)
for providin	t G - Alternative Sec g secondary contain for the Edwards Aqu	nment are	propose			
.9. Inside dimensio	ons and capacity of o	containme	nt struct	ure(s):		
Гable 3 - Second	ary Containment					
Length (L)(Ft.)	Width(W)(Ft.)	Height	(H)(Ft.)	L x W x H = (F	₹t3)	Gallons
					T	otal: Gallon
30. Piping:						
All piping, h Some of the structure. The piping v	oses, and dispenser piping to dispenser will be aboveground will be underground	rs or equip				
	ment area must be) being stored. The					
	t H - AST Containme It structure is attach			_	draw	ing of the
☐ Internal ☐ Tanks cle	dimensions (length, drainage to a point early labeled early labeled					

Substance to be

Dispenser clearly labeled
33. Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.
 In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly. In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.
Site Plan Requirements
Items 34 - 46 must be included on the Site Plan.
34. \square The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = <u>20</u> '.
35. 100-year floodplain boundaries:
 Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled. No part of the project site is located within the 100-year floodplain. The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA FIRM Maps 48491C0435F & 48491C0455F effective 12/20/2019.
36. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. A drainage plan showing all paths of drainage from the site to surface streams.
38. The drainage patterns and approximate slopes anticipated after major grading activities.
39. Areas of soil disturbance and areas which will not be disturbed.
40. \(\sum \) Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. \sum Locations where soil stabilization practices are expected to occur.
42. Surface waters (including wetlands).
⊠ N/A


43.	Locations where stormwater discharges to surface water.	
	There will be no discharges to surface water.	
44.	Temporary aboveground storage tank facilities.	
	Temporary aboveground storage tank facilities will not be located on this site.	
45.	Permanent aboveground storage tank facilities.	
	Permanent aboveground storage tank facilities will not be located on this site.	
46.	Legal boundaries of the site are shown.	
Pe	rmanent Best Management Practices (BMPs)	
Pra	ctices and measures that will be used during and after construction is completed.	
47.	Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.	
	□ N/A	
48.	These practices and measures have been designed, and will be constructed, operat and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activit removed. These quantities have been calculated in accordance with technical guid prepared or accepted by the executive director.	ty is
	 ☐ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BN and measures for this site. ☐ A technical guidance other than the TCEQ TGM was used to design permanent and measures for this site. The complete citation for the technical guidance the was used is: N/A 	BMPs
49.	as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification lett must be submitted to the appropriate regional office within 30 days of site comple	e :er
	N/A	
50.	Where a site is used for low density single-family residential development and has 20 9 less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for whole site as described in the property boundaries required by 30 TAC §213.4(g) (relate Application Processing and Approval), may no longer apply and the property owner must be appropriate regional office of these changes.	e the ing to


	 The site will be used for low density single-family residential development and has 20% or less impervious cover. The site will be used for low density single-family residential development but has more than 20% impervious cover. ∑The site will not be used for low density single-family residential development.
51.	The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	 Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. ☑ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. ☑ The site will not be used for multi-family residential developments, schools, or small business sites.
52.	Attachment J - BMPs for Upgradient Stormwater.
	 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
53.	Attachment K - BMPs for On-site Stormwater.
	 A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface wate or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
54.	Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.

	\boxtimes	N/A
55.		Attachment M - Construction Plans . Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.
		N/A
56.		Attachment N - Inspection, Maintenance, Repair and Retrofit Plan . A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
		Prepared and certified by the engineer designing the permanent BMPs and measures
		 Signed by the owner or responsible party Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit. Contains a discussion of record keeping procedures
		N/A
57.		Attachment O - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached. N/A
-0	_	
58.		Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
		N/A
	-	oonsibility for Maintenance of Permanent BMPs and sures after Construction is Complete.
59.		The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the

ownership of the property is transferred to the entity. Such entity shall then be

	responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60. 🗌	A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
Adm	ninistrative Information
61. 🔀	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
62. 🔀	Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
63. 🔀	The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
	The Temporary Stormwater Section (TCEQ-0602) is included with the application.





ATTACHMENT C

PROJECT DESCRIPTION

The Arka Montessori Academy site is a proposed daycare facility located along San Gabriel Parkway in Leander, Texas. Zoned LC (Local Commercial), this commercial development spans a 1.698-acre tract, which will be transformed into an 11,988-square-foot daycare center. The site, which is not within the floodplain, features minimal trees, moderate grass, and slopes ranging from 1% to 10%. It drains from the northeast into an existing drainage channel along the eastern and southern borders, ultimately flowing into Brushy Creek.

The project is bordered by an access road for Glenn High School to the west, a single-family subdivision to the north, undeveloped land to the east, and San Gabriel Parkway to the south. ESP Associates, Inc. provided civil design services for this development, which includes an 11,988-square-foot building, parking areas, playground structures, an underground detention pond with water quality treatment, and a concrete drainage channel along the eastern and southern property lines.

The final construction documents comprise an existing conditions plan, erosion control plans for various construction phases, offsite and onsite drainage area maps for existing and proposed conditions, grading plan, storm drainage plan, underground detention plan, channel plan, site plan, address plan, utility plan, and fire protection plan.

Of the 1.698 acres, 1.086 acres will be impervious cover. To manage the changes in water flow due to construction, both temporary and permanent best management practices (BMPs) will be implemented to ensure no adverse impacts on neighbors or water quality. Temporary BMPs during construction include a construction entrance/exit, silt fencing along the southern and eastern property lines and the proposed concrete drainage channel, inlet protection at all storm drain inlets, and a concrete washout pit. Permanent BMPs post-construction include Jellyfish® inlets and underground storage provided by ConTech Engineering Solutions to treat storm runoff and discharge at pre-development flows into the new concrete drainage channel. Storm drainage inlets and networks will convey the water to the Jellyfish® treatment inlets, which will then discharge the water into the underground storage facility before releasing it into the proposed concrete drainage channel.



ATTACHMENT D

FACTORS AFFECTING SURFACE WATER QUALITY

Akra Montessori Academy will not have any factors that negatively impact surface water quality once construction is complete. However, during the construction phase, there is a possibility of oil, grease, and silt accumulation on the project site due to the equipment used for building the pavement, parking lot, sidewalks, drainage channel, and the structure itself. Potential contaminants include fluid leaks from construction vehicles, hydrocarbons from asphalt paving, and washout from concrete trucks. Additionally, improperly disposed construction trash and debris could pose a contamination risk. Grading of rock and soil on the site will generate silt.

To address water quality concerns during construction, both temporary and permanent best management practices (BMPs) will be implemented to prevent adverse impacts on neighbors and water quality. Temporary BMPs include:

- Construction entrance/exit
- Silt fencing along the southern and eastern property lines and the proposed concrete drainage channel
- Inlet protection at all storm drain inlets
- Concrete washout pit

Permanent BMPs post-construction include:

- Jellyfish® inlets and underground storage provided by ConTech Engineering Solutions to treat storm runoff
- Discharge of treated water at pre-development into the new concrete drainage channel

Storm drainage inlets and networks will convey water to the Jelly Fish treatment inlets. This water will then be stored in the underground facility before being released into the proposed concrete drainage channel.



ATTACHMENT E

VOLUME AND CHARACTER OF STORMWATER

The project site currently has one drainage area, labeled DA-1-EX Onsite, which covers the entire site. This area drains into a channel located at the southern property line and ultimately flows into Brushy Creek. DA-1-EX Onsite encompasses 1.89 acres of undeveloped natural land with grass coverage and gentle slopes ranging from 1% to 5%. Using the Rational Method and the guidelines from table 2-3 in the Austin Drainage Criteria Manual, the existing peak flow rates were calculated. The peak flows for DA-1-EX Onsite are 2.06 cfs, 3.65 cfs, 5.14 cfs, and 8.32 cfs for the 2-year, 10-year, 25-year, and 100-year storm events, respectively.

Under the proposed conditions, the site remains as one drainage area, now designated as Proposed Drainage Area 1 (DA-1). DA-1 Onsite will cover 1.89 acres and will drain into a storm drainage system equipped with a Jellyfish filter inlet to treat stormwater before it infiltrates into an underground detention system. Using the Rational Method, the calculated peak flow rates for DA-1 are 5.98 cfs, 10.15 cfs, 13.44 cfs, and 20.08 cfs for the 2-year, 10-year, 25-year, and 100-year storm events, respectively. The treated flows from DA-1 will eventually be discharged into the improved drainage channel along the southern border of the property.



ATTACHMENT F

SUITABILITY LETTER FROM AUTHORITY AGENT

No on-site sewage facility will be used for wastewater treatment and disposal. This proposed development will be connected to the existing city-operated sanitary sewer network.



ATTACHMENT G

ALTERNATIVE SECONDARY CONTAINMENT METHODS

No above ground storage will be used during construction or post development of this site. No alternative secondary containment methods needed.



ATTACHMENT H

AST CONTAINMENT STRUCTURE DRAWINGS

No above ground storage will be used during construction or post development of this site. No above ground storage tank structure drawings needed.



ATTACHMENT I

20% OR LESS IMPERVIOUS COVER WAIVER

The site will be used for a school but will have more than 20% impervious cover.



ATTACHMENT J

BMPs FOR UPGRADIENT STORMWATER

The proposed site is bordered on its east and southern sides by a private road for Glenn High School and San Gabriel Parkway. To the north and west, it is bordered by residential lots and undeveloped land. None of these adjacent properties drain onto the proposed site.



ATTACHMENT K

BMPS FOR ON-SITE STORMWATER

Akra Montessori Academy will have permanent best management practices (BMPs) will be implemented to prevent adverse impacts on neighbors and water quality. Temporary BMPs include:

• Jellyfish® inlets and underground storage provided by ConTech Engineering Solutions to treat storm runoff

Storm drainage inlets and networks will convey water to the Jellyfish® treatment inlets. This water will then be stored in the underground facility before being released into the proposed concrete drainage channel. The Jellyfish® system designed by ConTech Engineering Solutions is an TCEQ certified BMP used to treat stormwater. Stormwater from the proposed site will flow into the Jellyfish® inlets by surface drain or by pipe networks.



ATTACHMENT M

CONSTRUCTION PLANS



ARKA MONTESSORI SCHOOL

SITE DEVELOPMENT PLANS
PROJECT NUMBER: SD-24-0219
1201 W SAN GABRIEL PKWY

OWNER

ARKA CHILDCARE MANAGEMENT SERVICES, LLC 1019 THORNCLIFF TRL.

1019 THORNCLIFF 1 IRVING, TX 75063

CONTACT: RAVI MADDI
EMAIL: RAVINDRA.MADDI@GMAIL.COM

ENGINEER:

ENGINEER.

ESP ASSOCIATES, INC.

ADDRESS: 12940 COUNTRY PKWY
SAN ANTONIO, TX 78216
PHONE: (210) 349-3271
CONTACT: ARIELLA MEADOWS
EMAIL: AMEADOWS@VICKREYLLC.COM

SURVEYOR:

SHERWOOD SURVEYING & S.U.E.

ADDRESS: 6477

SPRING BRANCH, TX 78070
PHONE: (830) 228-5788
CONTACT: RICHARD A. GOODWIN

SUBMITTAL DATE

SITE INFORMATION:

ZONING:

NING: LC-2-B LOCAL COMMERCIAL LOT 2 HOPE ALLIANCE MINOR PUD


ACREAGE: 1.70 ACRES
LOC ACREAGE: 1.77 ACRES


TOTAL IMPERVIOUS COVER: 47,316.61 SF
BUILDING IMPERVIOUS COVER: 11,987.77 SF

LEGAL DESCRIPTION: 1.699 ACRES HOPE ALLIANCE CRISIS CENTER SUBDIVISION LOT 1

FUTURE LAND USE: MULTI-USE CORRIDOR
EXISTING EASEMENTS: DRAINAGE EASEMENT, DOC. 2011046338 OPRWCT

LOCATION MAP







REVISION#	DESCRIPTION	APPROVAL

ROBIN M. GRIFFIN, AICP, EXECUTIVE DIRECTOR OF DEVELOPMENT SERVICES	DATE
EMILY TRUMAN, P.E., CFM, CITY ENGINEER	DATE
MARK TUMMONS, CPRP, DIRECTOR OF PARKS AND RECREATION	DATE

SHEET LIST TABLE		
Sheet Number	Sheet Title	
1	COVER SHEET	
2	GENERAL NOTES	
3	FINAL PLAT	
4	FINAL PLAT	
5	FINAL PLAT	
6	EXISTING CONDITIONS PLAN	
7	EROSION & SEDIMENTATION CONTROL PLAN PHASE 1	
8	EROSION & SEDIMENTATION CONTROL PLAN PHASE 2	
9	OFFSITE EXISTING DRAINAGE AREA MAP	
10	OFFSITE PROPOSED DRAINAGE AREA MAP	
11	ONSITE EXISTING DRAINAGE AREA MAP	
12	ONSITE PROPOSED DRAINAGE AREA MAP	
13	CHANNEL DRAINAGE AREA MAP	
14	GRADING PLAN	
15	STORM DRAIN PLAN	
16	UNDERGROUND DETENTION PLAN	
17	CHANNEL PLAN AND PROFILE	
18	SITE PLAN	
19	ADDRESS PLAN	
20	UTILITY PLAN	
21	FIRE PROTECTION PLAN	
22	EROSION & SEDIMENTATION CONTROL DETAILS	
23	STORM DRAIN DETAILS	
24	STORM DRAIN DETAILS	
25	SITE DETAILS	
26	SITE DETAILS	
27	SITE DETAILS	
28	SITE DETAILS	
29	UTILITY DETAILS	
30	UTILITY DETAILS 2	
31	UTILITY DETAILS 3	
L1	OVERALL PLANTING PLAN	
L2	PLANTING PLAN	
L3	PLANTING PLAN	
L4	PLANTING DETAILS & CODE	
L5	GENERAL NOTES	

NOTE:
THE ENGINEER-OF-RECORD IS SOLELY RESPONSIBLE FOR THE
COMPLETENESS, ACCURACY, REGULATORY COMPLIANCE, AND ADEQUACY OF
THESE PLANS AND/OR SPECIFICATIONS WHETHER THE PLANS AND/OR
SPECIFICATIONS WERE REVIEWED BY THE CITY ENGINEER(S).





CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

ESP Associary 12940 Country San Antonio, T (210) 349-3



Ñ.	DATE		ВҮ	
_ , , , , , , ,	ġ.	DATE	DATE REVISION	DATE

PROJECT INFORMATION

PROJECT NUMBER:

ORIGINAL DATE:

ADA NOTES:

- 1. THE MINIMUM CLEAR WIDTH OF AN ACCESSIBLE ROUTE IS 36 IN. IF THE ACCESSIBLE ROUTE IS LESS THAN 60 IN. WIDE AND LONGER THAN 200 FT., PASSING SPACES AT LEAST 60 IN. MUST BE LOCATED EVERY 200 FT.
- 2. SLOPES ON ACCESSIBLE ROUTES MAY NOT EXCEED 1:20 (5.0%) UNLESS DESIGNED AS A RAMP.
- 3. ACCESSIBLE PARKING SPACES MUST BE LOCATED ON A SURFACE WITH A SLOPE NOT EXCEEDING 1:50 (2.0%) IN ALL DIRECTIONS.
- 4. ACCESSIBLE ROUTES MUST HAVE A CROSS SLOPE NO GREATER THAN 1:50 (2.0%).

SITE NOTES:

- 1. ALL DIMENSIONS TO CURBS ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED.
- 2. ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRES SITE PLAN AMENDMENT AND APPROVAL OF THE PLANNING AND DEVELOPMENT REVIEW DEPARTMENT.
- 3. THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRICAL SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS, CITY OF AUSTIN RILES AND REGULATIONS AND TEXAS STATE LAWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES
- 4. CONTRACTOR TO ADJUST CASTINGS, MANHOLE LIDS AND OTHER APPLICABLE APPURTENANCES ON EXISTING UTILITIES WITHIN THE PROPOSED DRIVEWAY AND SIDEWALK RECONSTRUCTION LIMITS.
- 5. SCREENING FOR SOLID WASTE COLLECTION AND LOADING AREAS SHALL BE THE SAME AS, OR EQUAL QUALITY TO, PRINCIPLE BUILDING MATERIALS.
- 6. EACH PARKING SPACE MUST HAVE A VERTICAL CLEARANCE AS SPECIFIED IN THE BUILDING CODE(MINIMUM OF 7.0 FEET).
- 7. A MINIMUM OF VERTICAL CLEARANCE OF 114" MUST BE PROVIDED AT ACCESSIBLE PASSENGER LOADING ZONES ALONG VEHICLE ROUTES TO SUCH AREAS FROM SITE ENTRANCES. A MINIMUM VERTICAL CLEARANCE OF 98" MUST BE PROVIDED FOR VAN-ACCESSIBLE PARKING SPACES AND ALONG VEHICULAR ROUTE THERETO.
- 8. EXISTING STRUCTURES SHOWN TO BE REMOVED WILL REQUIRE A DEMOLITION PLAN FROM THE CITY OF AUSTIN PLANNING AND DEVELOPMENT REVIEW DEPARTMENT.
- 9. ALL SITE DRIVEWAYS SHALL MAINTAIN A VERTICAL CLEARANCE OF 14'-0" FOR FIRE DEPARTMENT ACCESS. TRESS SHALL BE PRUNED APPROPRIATELY PER STANDARDS SET BY THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL.
- 10. APPROVAL OF THIS SITE PLAN DOES NOT INCLUDE BUILDING AND FIRE CODE APPROVAL NOR BUILDING PERMIT APPROVAL.
- 11. ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE.

CONSTRUCTION SEQUENCING NOTES:

- 1. CALL CITY OF LEANDER CONSTRUCTION INSPECTION, (512) 528-2766 AT LEAST 48 HOURS PRIOR TO BEGINNING ANY WORK. CALL THE ONE CALL CENTER AT (800) 545-6005 AND THE TEXAS UNDERGROUND FACILITY NOTIFICATION CORPORATION FOR UTILITY LOCATIONS AND OBTAIN PERMIT FOR ANY WORK WITHIN THE RIGHT-OF-WAY.
- 2. INSTALL TEMPORARY EROSION CONTROLS AND TREE PROTECTION FENCING PRIOR TO ANY CLEARING AND GRUBBING. NOTIFY THE CITY OF LEANDER WHEN INSTALLED, AND SCHEDULE A PRE-CONSTRUCTION MEETING.
- BEGIN CLEARING AND GRUBBING.
- 4. ROUGH GRADE ALL STORM WATER BASINS AND STREETS, PONDS, INCLUDING INTERIM DRAINAGE CONVEYANCES TO THE PONDS, PRIOR TO ROUGH GRADING OF DRIVEWAY AND PARKING LOT. NO DEVELOPMENT OF EMBANKMENT WILL BE PERMITTED AT THIS TIME.
- 5. INSTALL ALL UTILITIES TO BE LOCATED UNDER THE PROPOSED PAVEMENT.
- REGIN INSTALLATION OF STORM SEWER LINES. LIPON, COMPLETION, REVEGETATE AS MITCH. DISTURBED AREA AS POSSIBLE, PARTICULARLY CHANNELS AND LARGE OPEN AREAS. REVIEW ADJUST TEMPORARY EROSION CONTROL LOCATIONS AS NECESSARY.
- 7. REGRADE DRIVEWAY AND PARKING LOT TO SUBGRADE.
- 8. ENSURE THAT ALL UNDERGROUND UTILITY CROSSINGS ARE COMPLETED ON ALL DRIVEWAY AND PARKING LOT AREAS.
- 9. INSTALL INLET PROTECTION SEDIMENT CONTROLS WHEN STORM SEWER INLETS AND PIPING
- 10. INSTALL GABION BASKETS BEFORE STORM SEWER OUTFALL DISCHARGE IS PUT ON-LINE.
- 11. COMPLETE CONSTRUCTION, AND FINAL STABILIZATION OF EXTENDED DETENTION PONDS.
- 12. INSTALL CURB AND GUTTER.
- 13. LAY CONCRETE
- 14. INSTALL ALL STRIPING, AND PAVEMENT MARKERS.
- 15. COMPLETE ALL UNDERGROUND INSTALLATIONS WITHIN THE RIGHT-OF-WAY.
- 16. COMPLETE FINAL GRADING AND RESTORATION OF EXTENDED DETENTION PONDS.
- 17. COMPLETE PERMANENT EROSION CONTROL AND RESTORATION OF SITE VEGETATION.
- 18. REMOVE AND DISPOSE OF TEMPORARY EROSION CONTROLS AND ACCUMULATED SEDIMENT AFTER APPROVAL OF CITY OF LEANDER INSPECTOR.
- 19. COMPLETE ANY NECESSARY FINAL DRESS-UP OF AREAS DISTURBED BY ITEM 18.

GENERAL NOTES FOR SUBDIVISIONS AND SITE DEVELOPMENT PLANS

REVISED March 27, 2023

CITY CONTACTS: 512-528-2721 ENGINEERING MAIN LINE: PLANNING DEPARTMENT: 512-528-2750 PUBLIC WORKS MAIN LINE: 512-259-2640 STORMWATER INSPECTIONS: 512-285-0055 **UTILITIES MAIN LINE:** 512-259-1142 UTILITIES ON-CALL: 512-690-4760

GENERAL:

- 1. CONTRACTORS SHALL HAVE AN APPROVED SET OF PLANS WITH APPROVED REVISIONS ON SITE AT ALL TIMES. FAILURE TO HAVE APPROVED PLANS ON SITE MAY RESULT IN ISSUANCE OF WORK STOPPAGE.
- 2. CONTACT 811 SYSTEM FOR EXISTING WATER AND WASTEWATER LOCATIONS 48 HOURS PRIOR TO CONSTRUCTION.
- a. **REFRESH ALL LOCATES** *BEFORE* **14 DAYS** LOCATE REFRESH REQUESTS <u>MUST INCLUDE</u> A COPY OF YOUR 811 TICKET. TEXAS PIPELINE DAMAGE PREVENTION LAWS REQUIRE THAT A LOCATE REFRESH REQUEST BE SUBMITTED BEFORE 14 DAYS, OR IF LOCATION
- b. **REPORT PIPELINE DAMAGE IMMEDIATELY** IF YOU WITNESS OR EXPERIENCE PIPELINE EXCAVATION DAMAGE, PLEASE CONTACT THE CITY OF LEANDER BY PHONE AT 512-259-
- 3. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR 48 HOURS BEFORE:
- a. BEGINNING EACH PHASE OF CONSTRUCTION. CONTACT ASSIGNED CITY INSPECTOR. ANY TESTING. CONTRACTOR SHALL PROVIDE QUALITY TESTING FOR ALL INFRASTRUCTURES TO BE ACCEPTED AND MAINTAINED BY THE CITY OF LEANDER AFTER
- c. PROOF ROLLING SUB-GRADE AND EVERY LIFT OF ROADWAY EMBANKMENT, IN-PLACE DENSITY TESTING OF EVERY BASE COURSE, AND ASPHALT CORES. ALL OF THIS TESTING
- MUST BE WITNESSED BY A CITY OF LEANDER REPRESENTATIVE. d. CONNECTING TO THE EXISTING WATER LINES. e. THE INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE EASEMENT OR
- STREET ROW. THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S ROW MUST BE APPROVED PRIOR TO THE START OF BACKFILL OPERATIONS. 4. ALL RESPONSIBILITILY FOR THE ACCURACY OF THESE PLANS REMAINS WITH THE ENGINEER
- THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD. 5. EXCESS SOIL SHALL BE REMOVED AT THE CONTRACTOR'S EXPENSE. NOTIFY THE CITY OF

LEANDER IF THE DISPOSAL SITE IS INSIDE THE CITY'S JURISDICTIONAL BOUNDARIES.

OF RECORD WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY MUST RELY ON

- BURNING IS PROHIBITED.
- 7. NO WORK IS TO BE PERFORMED BETWEEN THE HOURS OF 9:00 P.M. AND 7:00 A.M. OR WEEKENDS. THE CITY INSPECTOR RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO UNCOVER ALL WORK PERFORMED WITHOUT INSPECTION.
- 8. CONTACT THE CITY INSPECTOR 4 DAYS PRIOR TO WORK FOR APPROVAL TO SCHEDULE ANY INSPECTIONS ON WEEKENDS OR CITY HOLIDAYS.
- NO BLASTING IS ALLOWED
- 10. ANY CHANGES OR REVISIONS TO THESE PLANS MUST FIRST BE SUBMITTED TO THE CITY BY THE DESIGN ENGINEER FOR REVIEW AND WRITTEN APPROVAL PRIOR TO CONSTRUCTION OF THE REVISION. ALL CHANGES AND REVISIONS SHALL USE REVISION CLOUDS TO HIGHLIGHT ALL REVISIONS AND CHANGES WITH EACH SUBMITTAL. REVISION TRIANGLE MARKERS AND NUMBERS SHALL BE USED TO MARK REVISIONS. ALL CLOUDS AND TRIANGLE MARKERS FROM PREVIOUS REVISIONS MUST BE REMOVED. REVISION INFORMATION SHALL BE UPDATED ON COVER SHEET AND AFFECTED PLAN SHEET TITLE BLOCK.
- 11. THE CONTRACTOR AND ENGINEER SHALL KEEP ACCURATE RECORDS OF ALL CONSTRUCTION THAT DEVIATES FROM THE PLANS. THE ENGINEER SHALL FURNISH THE CITY OF LEANDER ACCURATE "RECORD DRAWINGS" FOLLOWING THE COMPLETION OF ALL CONSTRUCTION. THESE "RECORD DRAWINGS" SHALL MEET THE SATISFACTION OF THE ENGINEERING DEPARTMENTS PRIOR TO FINAL ACCEPTANCE
- 12. THE CONTRACTOR WILL REIMBURSE THE CITY FOR ALL REPAIR AND/OR COST INCURRED AS A RESULT OF ANY DAMAGE TO ANY PUBLIC INFRASTRUCTURE WITHIN CITY EASEMENT OR PUBLIC RIGHT-OF-WAY, REGARDLESS OF THESE PLANS
- 13. WHEN CONSTRUCTION IS BEING CARRIED OUT WITHIN EASEMENTS, THE CONTRACTOR SHALL CONFINE HIS WORK TO WITHIN THE PERMANENT AND TEMPORARY EASEMENTS. PRIOR TO ACCEPTANCE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TRASH AND DEBRIS WITHIN THE PERMANENT EASEMENTS. CLEANUP SHALL BE TO THE SATISFACTION OF THE ENGINEER OF RECORD AND CITY.
- 14. CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS AND PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO THE PROPERTY OWNER.
- 15. ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA). OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE; INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 1033 LA POSADA DR. SUITE 375, AUSTIN, TEXAS 78752-3832.
- 16. ALL MANHOLE FRAMES/COVERS AND WATER VALVE/METER BOXES MUST BE ADJUSTED TO FINISHED GRADE AT THE OWNER'S EXPENSE BY THE CONTRACTOR FOR CITY CONSTRUCTION INSPECTOR INSPECTION. ALL UTILITY ADJUSTMENTS SHALL BE COMPLETED PRIOR TO FINAL PAVING. CONTRACTOR SHALL BACKFILL AROUND MANHOLES AND VALVE BOXES WITH
- 17. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT WHERE NOT SPECIFICALLY COVERED IN THE PROJECT SPECIFICATIONS SHALL CONFORM TO
- ALL CITY OF LEANDER DETAILS AND CITY OF AUSTIN STANDARD SPECIFICATIONS. 18. PROJECT SPECIFICATIONS TAKE PRECEDENCE OVER PLANS AND SPECIAL CONDITIONS GOVERN OVER TECHNICAL SPECIFICATIONS.
- 19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT.
- 20. THE CONTRACTOR MUST OBTAIN A CONSTRUCTION WATER METER FOR ALL WATER USED DURING CONSTRUCTION. A COPY OF THIS PERMIT MUST BE CARRIED AT ALL TIMES BY ALL
- 21. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ROADS AND DRIVES ADJACENT TO AND NEAR THE SITE FREE FROM SOIL, SEDIMENT AND DEBRIS. CONTRACTOR WILL NOT REMOVE SOIL, SEDIMENT OR DEBRIS FROM ANY AREA OR VEHICLE BY MEANS OF WATER. ONLY SHOVELING AND SWEEPING WILL BE ALLOWED. THE CONTRACTOR WILL BE RESPONSIBLE FOR DUST CONTROL FROM THE SITE. THE CONTRACTOR SHALL KEEP THE SITE AREA CLEAN AND MAINTAINED AT ALL TIMES, TO THE SATISFACTION OF THE CITY. THE SUBDIVISION (OR SITE) WILL NOT BE ACCEPTED (OR CERTIFICATE OF OCCUPANCY ISSUED)
- UNTIL THE SITE HAS BEEN CLEANED TO THE SATISIFACTION OF THE CITY. 22. TREES IN EXISTING ROW SHOULD BE PROTECTED OR NOTED IN THE PLANS TO BE REMOVED.

CONSTRUCTION SEQUENCE NOTES

NOTE: BELOW IS GENERAL SEQUENCE OF CONSTRUCTION. THE ENGINEER OF RECORD SHALL UPDATE BELOW WITH NOTES SPECIFIC TO THE PROJECT.

- 1. REACH OUT TO THE CITY FOR PRE-CONSTRUCTION MEETING AND CONSTRUCTION PERMIT.
- 2. SET-UP E/S CONTROLS AND TREE PROTECTION AND REACH OUT TO CITY FOR INSPECTION. 3. SET UP TEMPORARY TRAFFIC CONTROLS.
- 4. CONSTRUCT THE DRAINAGE PONDS AND STORM WATER FEATURES.
- 5. START UTILITY, ROAD, GRADING, FRANCHISE UTILITY AND ALL NECESSARY INFRASTRUCTURE
- CONSTRUCTION. [NOTE: PLEASE UPDATE AS PER THE PROJECT] 6. REQUEST FINAL WALKTHROUGH AND CONDUCT WALKTHROUGH WITH ENGINEER OF RECORD
- AND CITY DEPARTMENT.
- 7. ENGINEER OF RECORD IS RESPONSIBLE TO PREPARE AND SUBMIT CLOSEOUT DOCUMENTS FOR PROJECT CLOSEOUT.

EROSION CONTROL NOTES

1. THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY. THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES AND SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES.

2. THE TEMPORARY SPOILS DISPOSAL SITE IS TO BE SHOWN IN THE EROSION CONTROL MAP.

- 6. STABILIZED CONSTRUCTION ENTRANCE IS REQUIRED AT ALL POINTS WHERE CONSTRUCTION
- 5. SEEDING FOR REESTABLISHING VEGETATION SHALL COMPLY WITH THE AUSTIN GROW GREEN GUIDE OR WILLIAMSON COUNTY'S PROTOCOL FOR SUSTAINABLE ROADSIDES (SPEC 164--WC001 SEEDING FOR EROSION CONTROL). RESEEDING VARIETIES OF BERMUDA SHALL NOT BE USED.

SPECIFICALLY SHOWN ON THE PLANS. THE DEPTH OF SPOIL SHALL NOT EXCEED 10 FEET IN ANY

MINIMUM OF 6 INCHES OF TOPSOIL AND COMPOST BLEND. TOPSOIL ON SINGLE FAMILY LOTS

MAY BE INSTALLED WITH HOME CONSTRUCTION. THE TOPSOIL AND COMPOST BLEND SHALL

4. ALL AREAS DISTURBED OR EXPOSED DURING CONSTRUCTION SHALL BE RESTORED WITH A

- TRAFFIC IS EXITING THE PROJECT ONTO EXISTING PAVEMENT. LINEAR CONSTRUCTION PROJECTS MAY REQUIRE SPECIAL CONSIDERATION. ROADWAYS SHALL REMAIN CLEAR OF SILT AND MUD. 7. TEMPORARY STOP SIGNS SHOULD BE INSTALLED AT ALL CONSTRUCTION ENTRANCES WHERE A
- 8. IN THE EVENT OF INCLEMENT WEATHER THAT MAY RESULT IN A FLOODING SITUATION, THE CONTRACTOR SHALL REMOVE INLET PROTECTION MEASURES UNTIL SUCH TIME AS THE

3. ANY ON-SITE SPOILS DISPOSAL SHALL BE REMOVED PRIOR TO ACCEPTANCE UNLESS

WATER AND WASTEWATER NOTES

STOP CONDITION DOES NOT ALREADY EXIST.

CONSIST OF 75% TOPSOIL AND 25% COMPOST.

WATER AND WASTEWATER GENERAL NOTES

- 1. ALL NEWLY INSTALLED PIPES AND RELATED PRODUCTS MUST CONFORM TO AMERICAN NATIONAL STANDARDS INSTITUTE/NATIONAL SANITATION FOUNDATION (ANSI/NSF) STANDARD 61 AND MUST BE CERTIFIED BY AND ORGANIZATION ACCREDITED BY ANSI.
- 2. ALL WATER SERVICE, WASTEWATER SERVICE AND VALVE LOCATIONS SHALL BE APPROPRIATELY STAMPED AS FOLLOWS:

WATER SERVICE "W" ON TOP OF CURB WASTEWATER SERVICE "S" ON TOP OF CURB "V" ON TOP OF CURB

- 3. OPEN UTILITIES SHALL NOT BE PERMITTED ACROSS THE EXISTING PAVED SURFACES. WATER AND WASTEWATER LINES ACROSS THE EXISTING PAVED SURFACES SHALL BE BORED AND INSTALLED IN STEEL ENCASEMENT PIPES. BELL RESTRAINTS SHALL BE PROVIDED AT JOINTS.
- 4. INTERIOR SURFACES OF ALL DUCTILE IRON POTABLE OR RECLAIMED WATER PIPE SHALL BE CEMENT-MORTAR LINED AND SEAL COATED AS REQUIRED BY AWWA C104.
- 5. SAND, AS DESCRIBED IN AUSTIN SPECIFICATION ITEM 510 PIPE, SHALL NOT BE USED AS BEDDING FOR WATER AND WASTEWATER LINES. ACCEPTABLE BEDDING MATERIALS ARE PIPE BEDDING STONE, PEA GRAVEL AND IN LIEU OF SAND, A NATURALLY OCCURRING OR MANUFACTURED STONE MATERIAL CONFORMING TO ASTM C33 FOR STONE QUALITY AND

TING THE FOLLOWING GRADATION SPECIFICATION:			
SIEVE SIZE	PERCENT RETAINED BY WEIGHT		
1/2"	0		
3/8"	0-2		
#4	40-85		
#10	95-100		

6. DENSITY TESTING FOR TRENCH BACKFILL SHALL BE DONE IN MAXIMUM 12" LIFTS.

- 1. SAMPLING TAPS SHALL BE BROUGHT UP TO 3 FEET ABOVE GRADE AND SHALL BE EASILY ACCESSIBLE FOR CITY PERSONNEL. AT THE CONTRACTORS' REQUEST, AND IN HIS PRESENCE, SAMPLES FOR BACTERIOLOGICAL TESTING WILL BE COLLECTED BY THE CITY OF LEANDER NOT LESS THAN 24 HOURS AFTER THE TREATED LINE HAS BEEN FLUSHED OF THE CONCENTRATED CHLORINE SOLUTION AND CHARGED WITH WATER APPROVED BY THE CITY.
- 2. CITY PERSONNEL WILL OPERATE OR AUTHORIZE THE CONTRACTOR TO OPERATE ALL WATER VALVES THAT WILL PASS THROUGH THE CITY'S POTABLE WATER. THE CONTRACTOR MAY BE FINED \$500 OR MORE, INCLUDING ADDITIONAL THEFT OF WATER FINES, IF A WATER VALVE IS OPERATED IN AN UNAUTHORIZED MANNER, REGARDLESS OF WHO OPERATED THE VALVE.
- 3. THE CONTRACTOR IS HEREBY NOTIFIED THAT CONNECTING TO, SHUTTING DOWN, OR TERMINATING EXISTING UTILITY LINES MAY HAVE TO OCCUR AT OFF-PEAK HOURS. SUCH HOURS ARE USUALLY OUTSIDE NORMAL WORKING HOURS AND POSSIBLY BETWEEN 12 AM AND 6 AM AFTER COORDINATING WITH CITY CONSTRUCTION INSPECTORS AND INFORMING
- 4. PRESSURE TAPS OR HOT TAPS SHALL BE IN ACCORDANCE WITH CITY OF LEANDER STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL PERFORM ALL EXCAVATION AND SHALL FURNISH, INSTALL AND AIR TEST THE SLEEVE AND VALVE. A CITY OF LEANDER INSPECTOR MUST BE PRESENT WHEN THE CONTRACTOR MAKES A TAP, AND/OR ASSOCIATED TESTS. A MINIMUM O TWO (2) WORKING DAYS NOTICE IS REQUIRED. "SIZE ON SIZE" TAPS SHALL NOT BE PERMITTED UNLESS MADE BY THE USE OF AN APPROVED FULL-CIRCLE GASKETED TAPPING SLEEVE. CONCRETE THRUST BLOCKS SHALL BE PLACED BEHIND AND UNDER ALL TAP SLEEVES A MINIMUM OF 24 HOURS PRIOR TO THE BRANCH BEING PLACED INTO SERVICE. THRUST BLOCKS SHALL BE INSPECTED PRIOR TO BACKFILL.
- 5. FIRE HYDRANTS ON MAINS UNDER CONSTRUCTION SHALL BE SECURELY WRAPPED WITH A BLACK POLY WRAP BAG AND TAPED INTO PLACE. THE POLY WRAP SHALL BE REMOVED WHEN THE MAINS ARE ACCEPTED AND PLACED INTO SERVICE.
- 6. THRUST BLOCKS OR RESTRAINTS SHALL BE IN ACCORDANCE WITH THE CITY OF LEANDER STANDARD SPECIFICATIONS AND REQUIRED AT ALL FITTINGS PER DETAIL OR MANUFACTURER'S RECOMMENDATION. ALL FITTINGS SHALL HAVE BOTH THRUST BLOCKS AND RESTRAINTS.
- 7. ALL DEAD END WATER MAINS SHALL HAVE "FIRE HYDRANT ASSEMBLY" OR "BLOW-OFF VALVE AND THRUST BLOCK" OR "BLOW-OFF VALVE AND THRUST RESTRAINTS". THRUST RESTRAINTS SHALL BE INSTALLED ON THE MINIMUM LAST THREE PIPE LENGTHS (STANDARD 20' LAYING LENGTH). ADDITIONALL THRUST RESTRAINTS MAY BE REQUIRED BASED UPON THE MANUFACTURERS RECOMMENDATION AND/OR ENGINEER'S DESIGN.
- 8. PIPE MATERIAL FOR PUBLIC WATER MAINS SHALL BE PVC (AWWA C900-DR14 MIN. 305 PSI PRESSURE RATING). WATER SERVICES (2" OR LESS) SHALL BE POLYETHYLENE TUBING (BLACK, 200PSI, AND SDR-(9)). COPPER PIPES AND FITTINGS ARE NOT ALLOWED IN THE PUBLIC RIGHT OF WAY. ALL PLASTIC PIPES FOR USE IN PUBLIC WATER SYSTEMS MUST BEAR THE NATIONAL SANITATION FOUNDATION SEAL OF APPROVAL (NSF-PW).
- 9. ALL FIRE HYDRANT LEADS SHALL BE DUCTILE IRON PIPE (AWWA C115/C151 PRESSURE CLASS
- 10. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH MINIMUM 8-MIL POLYETHYLENE. 11. LINE FLUSHING OR ANY ACTIVITY USING A LARGE QUANTITY OF WATER MUST BE COORDINATED WITH THE PUBLIC WORKS DEPARTMENT.
- a. SINGLE, 1" METER AND BELOW DFW37F-12-1CA, OR EQUAL b. DUAL, 1" METERS AND BELOW DFW39F-12-1CA, OR EQUAL
- DFW65C-14-1CA, OR EQUAL c. 1.5" SINGLE METER DFW1730F-12-1CA, OR EQUAL
- d. 2" SINGLE METER 13. ALL WATER VALVE COVERS ARE TO BE PAINTED BLUE.

WASTEWATER

12. ALL WATER METER BOXES SHALL BE:

- 1. CURVILINEAR WASTEWATER DESIGN LAYOUT IS NOT PERMITTED. 2. MANDREL TESTING SHALL BE CONDUCTED AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT
- 3. MANHOLES SHALL BE COATED PER CITY OF AUSTIN SPL WW-511 (RAVEN 405 OR SPRAYWALL). PENETRATIONS TO EXISTING WASTEWATER MANHOLES REQUIRE THE CONTRACTOR TO RECOAT THE ENTIRE MANHOLE IN ACCORDANCE WITH CITY OF AUSTIN STANDARD SPECIFICATIONS
- 4. RECLAIMED AND RECYCLED WATER LINE SHALL BE CONSTRUCTED OF "PURPLE PIPE." ALL
- RECLAIMED AND RECYCLED WATER VALVE COVERS SHALL BE SQUARE AND PAINTED PURPLE. 5. FORCE MAIN PIPES NEED TO HAVE SWEEPING WYES FOR JOINTS.

STREET AND DRAINAGE NOTES

- 1. THE CITY OF LEANDER HAS NOT REVIEWED THESE PLANS FOR COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT (ADA). IT IS THE RESPONSIBILITY OF THE OWNER TO PROVIDE COMPLIANCE WITH ALL LEGISTATION RELATED TO ACCESSIBLITY WITHIN THE LIMITS OF CONSTRUCTION SHOWN IN THESE PLANS. ALL SIDEWALKS SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT AND TEXAS ACCESSIBILITY STANDARS (TAS).
- 2. BACKFILL BEHIND THE CURB SHALL BE COMPACTED TO OBTAIN A MINIMUM OF 95% MAXIMUM DENSITY TO WITHIN 6" OF TOP OF CURB. MATERIAL USED SHALL BE PRIMARILY GRANULAR WITH NO ROCKS LARGER THAN 6" IN THE GREATEST DIMENSION. THE REMAINING 6" SHALL BE CLEAN TOPSOIL FREE FROM ALL CLODS AND SUITABLE FOR SUSTAINING PLANT LIFE.
- 3. A MINIMUM OF 6" OF TOPSOIL SHALL BE PLACED BETWEEN THE CURB AND RIGHT-OF-WAY AND IN ALL DRAINAGE CHANNELS EXCEPT CHANNELS CUT IN STABLE ROCK.

4. DEPTH OF COVER FOR ALL CROSSINGS UNDER PAVEMENT, INCLUDING GAS, ELECTRIC

- TELEPHONE, CABLE TV, ETC., SHALL BE A MINIMUM OF 36" BELOW SUBGRADE. 5. STREET RIGHT-OF-WAY SHALL BE GRADED AT A SLOPE OF 1/2" PER FOOT TOWARD THE CURB UNLESS OTHERWISE INDICATED.
- 6. ALL DRAINAGE PIPE IN PUBLIC RIGHT OF WAY OR EASEMENTS SHALL BE REINFORCED CONCRETE PIPE MINIMUM CLASS III OF TONGUE AND GROOVE OR O-RING JOINT DESIGN. CORRUGATED
- METAL PIPE IS NOT ALLOWED IN PUBLIC RIGHT OR WAY OR EASEMENTS. 7. THE CONTRACTOR MUST PROVIDE A PNEUMATIC TRUCK PER TXDOT SPEC FOR PROOF ROLLING. 8. ALL STRIPING, WITH THE EXCEPTION OF STOP BARS, CROSS WALKS, WORDS AND ARROWS, IS TO BE TYPE II (WATER BASED). STOP BARS, CROSS WALKS, WORDS AND ARROWS REQUIRE TYPE I
- 9. MANHOLE FRAMES, COVERS, VALVES, CLEAN-OUTS, ETC. SHALL BE RAISED TO GRADE PRIOR TO FINAL PAVEMENT CONSTRUCTION
- 10. A STOP BAR SHALL BE PLACED AT ALL STOP SIGN LOCATIONS.
- 11. THE GEOTECHNICAL ENGINEER SHALL INSPECT THE SUBGRADE FOR COMPLIANCE WITH THE DESIGN ASSUMPTIONS MADE DURING PREPARATION OF THE SOILS REPORT. ANY ADJUSTMENTS THAT ARE REQUIRED SHALL BE MADE THROUGH REVISIONS OF THE APPROVED CONSTRUCTION PLANS.
- 12. GEOTECHNICAL INVESTIGATION INFORMATION AND PAVEMENT RECOMMENDATIONS WERE PROVIDED BY GEOSCIENCE ENGINEERS, LLC. DATED APRIL 2024, PROJECT NUMBER: 24-DG2697. PAVEMENT RECOMMENDATIONS ARE AS FOLLOWS:

	Minimum Thickness (inches)
Parking	
Portland Cement Concrete	5
Lime Stabilized Soils	6
Compacted subgrade	6
**Fire Lane/Driveways	
Portland Cement Concrete	6
Lime Stabilized Soils	6
Compacted Subgrade Soils	6
Dumpster/Approach	
Portland Cement Concrete	7
Lime Stabilized Soils	6
Compacted Subgrade Soils	6

**capable of carrying the fire apparatus load of 85000 lbs

b) FOR FULL REPORT REFERENCE GEOTECHNICAL INVESTIGATION REPORT #24-DG2697 PROVIDED BY GEOSCIENCE ENGINEERS, LLC. DATED APRIL 2024

- 13. A TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, CITY OF AUSTIN TRANSPORATION CRITERIA MANUAL, CITY OF LEANDER STANDARD DETAILS AND TEXAS DEPARTMENT OF TRANSPORTATION CRITERIA, SHALL BE SUBMITTED TO THE CITY OF LEANDER FOR REVIEW AND APPROVAL PRIOR TO ANY PARTIAL OR COMPLETE ROADWAY CLOSURES. TRAFFIC CONTROL PLANS MUST BE SITE SPECIFIC AND SIGNED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
- 14. ALL LANE CLOSURES SHALL OCCUR ONLY BETWEEN THE HOURS OF 9 AM AND 4 PM UNLESS OTHERWISE NOTED ON THE PLANS. ANY NIGHT TIME LANE CLOSURES REQUIRE APPROVAL OF THE CITY ENGINEER AND SHALL OCCUR BETWEEN THE HOURS OF 8 PM AND 6 AM. LANE CLOSURES OBSERVED BY THE CITY DURING PEAK HOURS OF 6 AM TO 9 AM OR 4 PM TO 8 PM WILL BE SUBJECT TO A FINE AND/OR SUBSEQUENT ISSUANCE OF WORK STOPPAGE.
- 15. TEMPORARY ROCK CRUSHING IS NOT ALLOWED. ALL SOURCES OF FLEXIBLE BASE MATERIAL ARE REQUIRED TO BE APPROVED BY THE CITY. PRIOR TO BASE PLACEMENT ALL CURRENT TRIAXIAL TEST REPORTS FOR PROPOSED STOCK PILES ARE TO BE SUBMITTED TO THE CITY CONSTRUCTION INSPECTOR FOR REVIEW AND APPROVAL.
- 16. AT ROAD INTERSECTIONS THAT HAVE A VALLEY GUTTER, THE CROWN TO THE INTERSECTING ROAD WILL BE CULMINATED AT A DISTANCE OF 40 FEET FROM THE INTERSECTING CURB LINE UNLESS OTHERWISE NOTED. 17. NO PONDING OF WATER SHALL BE ALLOWED TO COLLECT ON OR NEAR THE INTERSECTION OF

PRIVATE DRIVEWAYS AND PUBLIC STREETS. RECONSTRUCTION OF THE DRIVEWAY APPROACH

- SHALL BE AT THE CONTRACTOR'S EXPENSE. 18. ALL DRIVEWAY APPROACHES SHALL HAVE A UNIFORM TWO PERCENT SLOPE WITHIN THE
- PUBLIC RIGHT OF WAY UNLESS APPROVED IN WRITING BY THE ENGINEERING DEPARTMENT. 19. IMPROVEMENTS THAT INCLUDE RECONSTRUCTION OF AN EXISTING TYPE II DRIVEWAY SHALL BE DONE IN A MANNER WHICH RETAINS OPERATIONS OF NOT LESS THAN HALF OF THE DRVIEWAY TO REMAIN OPEN AT ALL TIMES. FULL CLOSURE OF SUCH DRIVEWAY CAN BE CONSIDERED WITH WRITTEN AUTHORIZATION OBTAINED BY THE CONTRACTOR FROM ALL PROPERTY OWNERS AND
- ACCESS EASEMENT RIGHT HOLDERS ALLOWING THE FULL CLOSURE OF THE DRIVEWAY. 20. CONTRACTOR MUST CLEAR FIVE (5) FEET BEYOND ALL PUBLIC RIGHT OF WAY TO PREVENT FUTURE VEGETATIVE GROWTH INTO THE SIDEWALK AREAS.
- 21. SLOPE OF NATURAL GROUND ADJACENT TO THE PUBLIC RIGHT OF WAY SHALL NOT EXCEED 3:1 SLOPE. IF A 3:1 SLOPE IS NOT POSSIBLE, SLOPE PROTECTION OR RETAINING WALL MUST BE
- 22. THERE SHALL BE NO WATER, WASTEWATER OR DRAINAGE APPURTENANCES, INCLUDING BUT NOT LIMITED TO VALVES, FITTINGS, METERS, CLEAN-OUTS, MANHOLES, OR VAULTS IN ANY DRIVEWAY, SIDEWALK, TRAFFIC OR PEDESTRIAN AREA. 23. PUBLIC SIDEWALKS SHALL NOT USE CURB INLETS AS PARTIAL WALKING SURFACE. SIDEWALKS

SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO FINAL ACCEPTANCE.

- SHALL NOT USE TRAFFIC CONTROL BOXES, METERS, CHECK VALVE VAULTS, COMMUNICATION VAULTS, OR OTHER BURIED OR PARTIALLY BURIED INFRASTRUCTURE AS A VEHICULAR OR PEDESTRIAN SURFACE.
- 24. ALL WET UTILITIES SHALL BE INSTALLED AND ALL DENSITIES MUST HAVE PASSED INSPECTION(S) PRIOR TO THE INSTALLATION OF DRY UTILITIES. 25. DRY UTILITIES SHALL BE INSTALLED AFTER SUBGRADE IS CUT AND BEFORE THE FIRST COURSE OF
- BASE. NO TRENCHING COMPACTED BASE. IF NECESSARY DRY UTILITIES INSTALLED AFTER FIRST COURSE BASE SHALL BE BORED ACROSS THE FULL WIDTH OF THE PUBLIC RIGHT-OF-WAY. 26. A MINIMUM OF SEVEN (7) DAYS OF CURE TIME IS REQUIRED FOR HMAC PRIOR TO THE

INTRODUCTION OF VEHICULAR TRAFFIC TO ALL STREETS.

AND HEALTH ADMINISTRATION REGULATIONS.

TRENCH SAFETY NOTES 1. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT ARE DESCRIBED IN ITEM 509S "TRENCH SAFETY SYSTEMS" OF THE CITY OF AUSTIN STANDARD SPECIFICATIONS AND SHALL BE IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U.S. OCCUPATION SAFETY

GRADING NOTES

- 1. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT TO ALLOW ANY PONDING OF
- 2. THE CONTRACTOR SHALL CONSTRUCT EARTHEN EMBANKMENTS WITH SLOPES NO STEEPER THAN 3:1 AND COMPACT SOIL TO 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH THE CITY
- OF AUSTIN STANDARD SPECIFICATIONS. 3. AREAS OF SOIL DISTURBANCE ARE LIMITED TO GRADING AND IMPROVEMENTS SHOWN. ALL


OTHER AREAS WILL NOT BE DISTURBED.

BENCHMARK NOTES 1. CP#1 IRON ROD W/CAP N:10189137.91 E:3069858.19 2. CP#2 IRON ROD W/CAP

N:10188863.72

E:3068745.23

Z:1018.92



CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES



PROJECT INFORMATION PROJECT MANAGER: DESIGNED BY: DRAWN BY: PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024

DOC# 2024004549 HOPE ALLIANCE CRISIS CENTER SUBDIVISION OWNER/DEVELOPER:
WILLIAMSON COUNTY CRISIS CENTER 1/2" IRON ROD FOUND (UNLESS NOTED) A.K.A - HOPE ALLIANCE ROW RIGHT OF WAY SHORT FORM FINAL PLAT 1011 GATTIS SCHOOL RD # 110 ROUND ROCK, TX 78664 ENGINEER: EDDIE BOGARD, PE VICKREY & ASSOCIATES, LLC - FIRM #159 3600 W. PARMER LN, STE 175 AUSTIN, TX 78727 512.904.2523 **NUMBER OF LOTS: 3 ACREAGE: 11.527** PROPOSED USE: COMMERCIAL RESERVATIONS: NONE STREETS: ZERO SURVEYOR: RICHARD A. GOODWIN, RPLS 6477 FM 311 SPRING BRANCH, TX 78070 830.228.4163 AGENT/APPLICANT: **HEATHER L. STEED** 6477 FM 311 SPRING BRANCH, TX 78070 830.228.4163 SITE LOCATION **LOCATION MAP SCALE: 1"=2000"** SHEET INDEX: SHEET 1 = COVER PAGE SHEET 2 = EXHIBIT SHEET 3 = EASEMENT/NOTES & SIGNATURES SURVEYING & S.U.E.


UTILITIES | RESIDENTIAL | COMMERCIAL | INDUSTRIAL


6477 FM 311, P.O. BOX 992 TBPLS FIRM#10044200

SPRING BRANCH, TEXAS 78070

PHONE (830) 228-5788 FAX (830) 885-2170 OWNER/DEVELOPER: WILLIAMSON COUNTY CRISIS CENTER SHEET 1 OF 3 A.K.A - HOPE ALLIANCE 1011 GATTIS SCHOOL RD # 110 **COVER PAGE** ROUND ROCK, TX 78664 FILING DATE: NOVEMBER 8, 2022


JOB #21HAI001





PROJECT INFORMATION
PROJECT MANAGER: JT
DESIGNED BY: AM
DRAWN BY: CR/RM
PROJECT NUMBER: 23-00436
ORIGINAL DATE: 07/19/2024
SHEET OF
NCIES.

3 1



CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

PROJECT INFORMATION

PROJECT MANAGER: JT

DESIGNED BY: AM

DRAWN BY: CR/RM

PROJECT NUMBER: 23-00436

ORIGINAL DATE: 07/19/2024

SHEET OF

4

31

SHERWOOD UTILITIES | RESIDENTIAL | COMMERCIAL | INDUSTRIAL 6477 FM 311, P.O. BOX 992 TBPLS FIRM#10044200 SPRING BRANCH, TEXAS 78070 PHONE (830) 228-5788 FAX (830) 885-2170

GENERAL PLAT NOTES:

1. THIS SUBDIVISION IS WHOLLY CONTAINED WITHIN THE CURRENT CORPORATE LIMITS OF THE CITY OF LEANDER, TEXAS.

- 2. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO THE CITY OF LEANDER WATER DISTRIBUTION AND WASTEWATER COLLECTION FACILITIES.
- 3. A BUILDING PERMIT IS REQUIRED FROM THE CITY OF LEANDER PRIOR TO CONSTRUCTION OF ANY BUILDING OR SITE IMPROVEMENTS ON ANY LOT IN THIS SUBDIVISION.
- NO BUILDINGS, FENCES, LANDSCAPING OR OTHER STRUCTURES ARE PERMITTED WITHIN DRAINAGE EASEMENTS SHOWN EXCEPT AS APPROVED BY THE CITY OF LEANDER PUBLIC
- 5. PROPERTY OWNER SHALL PROVIDE FOR ACCESS TO DRAINAGE EASEMENTS AS MAY BE NECESSARY AND SHALL NOT PROHIBIT ACCESS BY THE CITY OF LEANDER.
- ALL EASEMENTS ON PRIVATE PROPERTY SHALL BE MAINTAINED BY THE PROPERTY OWNER
- IN ADDITION TO THE EASEMENTS SHOWN HEREON, A TEN (10') FOOT WIDE PUBLIC UTILITY EASEMENT, A PEDESTRIAN ACCESS EASEMENT AND A LANDSCAPE EASEMENT ARE DEDICATED ALONG AND ADJACENT TO ALL RIGHT-OF-WAY, AND A TWO AND A HALF (2.5") FOOT WIDE PUBLIC UTILITY EASEMENT IS DEDICATED ALONG ALL SIDE LOT LINES.
- 8. NO PORTION OF THIS TRACT IS WITHIN A FLOOD HAZARD AREA AS SHOWN ON THE FLOOD INSURANCE RATE MAP PANEL #48491 C0435F FOR WILLIAMSON COUNTY, EFFECTIVE
- BUILDING SETBACKS NOT SHOWN HEREON SHALL COMPLY WITH THE MOST CURRENT ZONING ORDINANCE OF THE CITY OF LEANDER. ADDITIONAL RESIDENTIAL GARAGE SETBACKS MAY BE REQUIRED AS LISTED IN THE CURRENT ZONING ORDINANCE.
- 10. SIDEWALKS SHALL BE INSTALLED ON THE SUBDIVISION SIDE OF SAN GABRIEL PARKWAY, AND WILL TIE INTO THE EXISTING SIDEWALK ON HALSEY DR. THOSE SIDEWALKS NOT ABUTTING A RESIDENTIAL, COMMERCIAL OR INDUSTRIAL LOT (INCLUDING SIDEWALKS ALONG STREET FRONTAGES OF ITS PROPOSED FOR SCHOOLS, CHURCHES, PARK LOTS, DETENTION LOTS, DRAINAGE LOTS, LANDSCAPE LOTS, OR SIMILAR LOTS), SIDEWALKS ON ARTERIAL STREETS TO WHICH ACCESS IS PROHIBITED, SIDEWALKS ON DOUBLE FRONTAGE LOTS ON THE SIDE TO WHICH ACCESS IS PROHIBITED, AND ALL SIDEWALKS ON SAFE SCHOOL ROUTES SHALL BE INSTALLED WHEN THE ADJOINING STREET IS CONSTRUCTED.
- 11. ALL UTILITY LINES MUST BE LOCATED UNDERGROUND.
- 12. APPROVAL OF THIS FINAL PLAT DOES NOT CONSTITUTE THE APPROVAL OF VARIANCES OR WAIVERS TO ORDINANCE REQUIREMENTS.
- 13. ALL DRIVE LANES, FIRE LANES, AND DRIVEWAYS WITHIN THIS SUBDIVISION SHALL PROVIDE FOR RECIPROCAL ACCESS FOR INGRESS AND EGRESS TO ALL OTHER LOTS WITHIN THE SUBDIVISION AND TO ADJACENT PROPERTIES.
- 14. AT THE TIME OF SITE DEVELOPMENT PERMIT, THE APPLICANT WILL PROVIDE A PAYMENT TO THE CITY IN LIEU OF A TRAFFIC IMPACT ANALYSIS (TIA), UNLESS A TIA FOR THE ENTIRE DEVELOPMENT INDICATES THAT AVERAGE DAILY TRIPS ARE ESTIMATED BELOW 2,000.

THE STATE OF TEXAS COUNTY OF COMAL

THAT I, RICHARD A. GOODWIN, AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS TO PRACTICE THE PROFESSION OF LAND SURVEYING AND HEREBY STATE THAT I PREPARED THIS PLAT FROM AN ACTUAL AND ACCURATE ON-THE-GROUND SURVEY OF THE LAND AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPERLY PLACED UNDER MY PERSONAL SUPERVISION, IN ACCORDANCE WITH ALL CITY OF LEANDER ORDINANCE AND CODES AND THAT ALL EXISTING EASEMENTS OF RECORD AS FOUND ON THE TITLE POLICY ISSUED BY TITLE RESOURCES GUARANTY COMPANY ISSUED SEPTEMBER 14, 2021, AND NOTHING FURTHER STATEMENT ISSUED THROUGH OCTOBER 4, 2022, HAVE BEEN SHOWN OR NOTED


RICHARD A. GOODWIN, RPLS




THE STATE OF TEXAS COUNTY OF TRAVIS


THAT I, EDDIE BOGARD, PE AM AUTHORIZED UNDER THE LAWS OF THE STATE OF TEXAS TO PRACTICE THE PROFESSION OF ENGINEERING, AND DO HEREBY STATE THAT THIS PLAT CONFORMS WITH THE APPLICABLE ORDINANCES, OF THE CITY OF LEANDER, TEXAS.

JOB #21HAI001





HOPE ALLIANCE CRISIS CENTER SUBDIVISION SHORT FORM FINAL PLAT



[
LINE	BEARING	DISTANCE
L20	S 83°16'02" W	113.97'
L21	N 18°49'46" W	208.05'
L22	N 68°41'22" E	54.88'
L23	N 21°19'18" W	12.40'
L24	N 70°15'34" E	18.97'
L25	S 21°19'18" E	31.47'
L26	S 21°19'12" E	155.19'
L27	S 66°18'38" E	2.83'
L28	N 68°41'22" E	10.10'
L29	N 22°44'36" W	4.00'
L30	N 68°41'22" E	1.00'
L31	S 21°18'38" E	78.38'
L32	S 28°26'20" W	5.98'
L33	N 04°39'08" E	24.81'
L34	S 81°57'16" W	52.02'
L35	S 69°45'31" W	4.24'
L36	S 68°39'31" W	88.27'
L37	S 68°41'24" W	23.50'
L38	N 21°18'36" W	218.13'
L39	N 19°29'48" W	21.58'
L40	S 70°15'34" W	48.70'
L41	N 21°18'36" W	26.01'
L42	N 70°15'34" E	75.68'
L43	S 19°17'46" E	46.87'
L44	S 21°18'36" E	218.13'
Little Control Control		

L40	N 00 41 24 E	∠ 3.3U
L46	N 68°42'25" E	88.28'
L47	N 68°44'58" E	4.26'
L48	N 81°57'16" E	51.91'
L49	S 04°39'08" W	25.27'
L50	N 68°40'59" E	250.30'
L51	S 51°21'40" E	42.44'
L52	S 18°29'59" E	37.71'
L53	N 05°15'54" E	23.81'
L54	N 88°55'35" E	75.13'
L55	N 03°30'25" E	12.12'
L56	S 86°08'56" E	54.58'
L57	S 03°54'54" W	42.15'
L58	S 08°11'37" W	45.56'
L59	S 10°39'11" W	1.89'
L60	S 13°06'45" W	46.72'
L61	S 35°40'38" W	10.67'
L62	S 58°13'09" W	49.70'
L63	N 80°14'54" W	127.31'
L64	N 08°37'08" W	25.39'
L65	N 68°41'24" E	1.78'
L66	N 38°57'29" E	0.51'
L67	N 18°29'59" W	36.29'
L68	N 51°21'40" W	19.78'
L69	S 68°41'24" W	190.87'

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C14	25.00'	44.81'	39.05'	N 46°41'51" W	102°41'58"
C15	55.00'	49.16'	47.54'	N 72°01'00" W	51°12'59"
C16	25.00'	28.29'	26.81'	N 78°49'44" W	64°50'29"
C17	51.00'	80.11'	72.12'	N 66°18'36" W	90°00'00"
C18	19.00'	29.33'	26.50'	N 24°27'59" E	88°26'46"
C19	25.00'	39.27'	35.36'	S 66°18'36" E	90°00'00"
C20	51.00'	57.72'	54.69'	S 78°49'45" E	64°50'29"
C21	29.00'	25.84'	25.00'	S 71°56'14" E	51°03'28"
C22	51.00'	91.41'	79.66'	S 46°41'50" E	102°41'58"
C23	1863.00'	26.00'	26.00'	N 84°19'11" W	0°47'59"
C24	51.00'	53.95'	51.47'	S 81°00'24" E	60°36'24"
C25	27.00'	39.42'	36.01'	N 47°05'44" E	83°39'40"
C26	27.00'	42.57'	38.30'	N 48°40'45" E	90°20'38"
C27	27.00'	42.42'	38.19'	S 41°08'37" E	90°00'39"
C28	27.00'	10.63'	10.56'	S 24°23'42" W	22°33'53"
C29	27.00'	10.62'	10.55'	S 46°56'54" W	22°32'31"
C30	27.00'	19.55'	19.12'	S 78°57'30" W	41°28'42"
C31	27.00'	24.04'	23,26'	N 54°44'08" W	51°01'33"
C32	55.05'	31.83'	31.39'	N 11°46'22" W	33°07'39"
C33	27.00'	36.43'	33.73'	N 30°02'08" E	77°18'31"

DOC # 2024 004599

THE STATE OF TEXAS § COUNTY OF WILLIAMSON

THAT WILLIAMSON COUNTY CRISIS CENTER, a Renee A. Petscheas the OWNER OF THAT CERTAIN 11.527 ACRE TRACT OF LAND RECORDED IN DOCUMENT #2021153652, OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS, DOES HEREBY CERTIFY THAT THERE ARE NO LIEN HOLDERS AND DEDICATES TO THE PUBLIC FOREVER USE OF ALL ADDITIONAL ROW, STREETS, ALLEYS, EASEMENTS, PARKS, AND ALL OTHER LANDS INTENDED FOR PUBLIC DEDICATION OR WHEN THE SUBDIVIDER HAS MADE PROVISION FOR PERPETUAL MAINTENANCE THEREOF, TO THE INHABITANTS OF THE SUBDIVISION AS SHOWN HEREON TO BE KNOWN AS HOPE ALLIANCE SUBDIVISION. CAS'S CENTER SUBDIVISION.

WILLIAMSON COUNTY CRISIS CENTER A.K.A. Hope Alliance


AUTHORIZED SIGNATURE PETSCHE THE STATE OF TEXAS, & COUNTY OF WILLIAMSON

BEFORE ME, THE UNDERSIGNED AUTHORITY, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE ON THIS THE STA DAY OF DECEMBER, 2023 personally appeared, LEGGES BOAT PRESIDENT OF WILLIAMSON COUNTY CRISIS CENTER, a , ON BEHALF OF SAID COMPANY, A DULY AUTHORIZED AGENT WITH AUTHORITY TO SIGN SAID DOCUMENT, PERSONALLY KNOWN TO ME (AND PROVED TO ME ON THE BASIS OF SATISFACTORY EVIDENCE) TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATION THEREIN EXPRESSED.

PRINTED NAME: YCKID. Jone MY COMMISSION EXPIRES: 6-15-27

VICKI D. JONES Expires June 15, 2027

My Notary ID # 134407989



NUMBER OF LOTS: 3 ACREAGE: 11.527 PROPOSED USE: COMMERCIAL RESERVATIONS: NONE STREETS: ZERO

FILING DATE: NOVEMBER 8, 2022

APPROVED THIS THE 28 DAY OF December 2023 A.D. AT A PUBLIC MEETING OF THE PLANNING AND ZONING COMMISSION OF THE CITY OF LEANDER, TEXAS, AND AUTHORIZED TO BE FILED FOR RECORD BY THE COUNTY CLERK OF WILLIAMSON COUNTY.

Tama Partito PLANNING AND ZONING COMMUSION CITY OF LEANDER, TEXAS Laura Lantrop, Chair

ELLEN COUFAL, SECRETARY PLANNING AND ZONING COMMISSION CITY OF LEANDER, TEXAS

STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS: COUNTY OF WILLIAMSON §


I, NANCY RISTER, CLERK OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT IN WRITING, WITH ITS CERTIFICATE OF AUTHENTICATION WAS FILED FOR RECORD IN MY OFFICE ON THE DAY OF AND DULY RECORDED THIS THE DAY OF AND DULY RECORDED THIS THE DAY OF AND DULY RECORDS OF SAID COUNTY IN INSTRUMENT NO. 201601500.


TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT MY OFFICE IN GEORGETOWN, TEXAS, THE DATE LAST SHOWN ABOVE WRITTEN.

NANCY RISTER, CLERK COUNTY COURT OF WILLIAMSON COUNTY, TEXAS BY: Dlave au



SHEET 3 OF 3 **EASEMENT/NOTES & SIGNATURES**





<u>CAUTION:</u>
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.


DESIGNED BY: DRAWN BY: PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024

PROJECT MANAGER:


PROJECT INFORMATION

0

O




PROJECT INFORMATION					
JECT MANAGER:	JT				
IGNED BY:	AM				
WN BY:	CR/RM				
JECT NUMBER:	23-00436				
GINAL DATE:	07/19/2024				
SHEET	OF				





ARIELLA D. MEADOW


EDIMENTATION LAN PHASE 1


PROJECT INFORMATION PROJECT MANAGER: PROJECT NUMBER:














	EXISTING	PROPOSED	POST-DETENTION
	(CFS)	(CFS)	(CFS)
2-YR	2.03	3.58	1.99
10-YR	3.71	6.33	3.48
25-YR	5.22	8.47	4.82
100-YR	8.42	15.11	6.45



Time of Concentration Worksheet


	Are	eas	DA-1 OVERALL
			PROP
Overland	Length	ft	100
	n		0.130
$t_o = \frac{0.42(nL)^{0.8}}{(P)^{0.5}(s)^{o.4}}$	slope	ft/ft	0.038
$t_o = \frac{1}{(P)^{0.5}(s)^{o.4}}$	То	min	6.13
P=3.92 in		hr	0.10
Shallow Concentrated (Unpaved)	Length	ft	323
	Slope	ft/ft	0.010
L	К		16.13
$t_{sc} = \frac{L}{60 * K * s^{0.5}}$	Tsc	min	3.37
		hr	0.06
Shallow Concentrated (Paved)	Length	ft	325
	Slope	ft/ft	0.011
, L	К		20.33
$t_{sc} = \frac{L}{60 * K * s^{0.5}}$	Tsc	min	2.58
		hr	0.04
Channel	Length	ft	694
	Velocity	ft/sec	6.00
$t_c = \Sigma \frac{L}{(60V)}$	Тс	min	1.93
$\frac{\iota_c - 2\overline{(60V)}}{}$		hr	0.03
Total Time of Concentration		min	14.0
$t_c = t_o + t_{sc} + t_c$		hr	0.23

- - -				
-				
-	REVISION			
-	DATE			
J	NO.			


PROPOSED DRAINAGE AREA MAP


5					
PROJECT INFORMATION					
OJECT MANA	JT				
SIGNED BY:		AM			
AWN BY:	CR/RM				
OJECT NUME	23-00436				
RIGINAL DATE	07/19/2024				

CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES
VERTICALLY AND HORIZONTALLY PRIOR TO
CONSTRUCTION. CONTRACTOR TO NOTIFY THE
ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.




PROJECT INFORMATION						
PROJECT MANAGE	ER:	JT				
ESIGNED BY:	AM					
RAWN BY:	CR/RM					
ROJECT NUMBER	23-00436					
RIGINAL DATE:	07/19/2024					
SHEET		OF				
		04				






LEGEND



TIME OF CONCENTRATION (TOC) END OF TOC PATH



CHANNEL 1 DRAINAGE AREA 10.04 AC



CHANNEL 2 DRAINAGE AREA 11.94 AC

Time of Concentration Worksheet


Exhibit G					
	Are	eas	Chanel		
Overland	Length	ft	100		
	n		0.130		
$t_o = \frac{0.42(nL)^{0.8}}{(P)^{0.5}(s)^{0.4}}$	slope	ft/ft	0.038		
$t_o = \frac{1}{(P)^{0.5}(s)^{o.4}}$	То	min	6.13		
P=3.92 in		hr	0.10		
Shallow Concentrated (Unpaved)	Length	ft	323		
	Slope	ft/ft	0.010		
L	К		16.13		
$t_{sc} = \frac{L}{60 * K * s^{0.5}}$	Tsc	min	3.37		
		hr	0.06		
Shallow Concentrated (Paved)	Length	ft	325		
	Slope	ft/ft	0.011		
, L	К		20.33		
$t_{sc} = \frac{L}{60 * K * s^{0.5}}$	Tsc	min	2.58		
		hr	0.04		
Channel	Length	ft	394		
	Velocity	ft/sec	6.00		
$t_c = \Sigma \frac{L}{(60V)}$	Tc	min	1.10		
$\iota_c = \iota_c (60V)$		hr	0.02		
Total Time of Concentration		min	13.2		
$t_c = t_o + t_{sc} + t_c$		hr	0.22		


$)^{o.4}$	То	min	6.13				
		hr	0.10				
(Unpaved)	Length	ft	323				
	Slope	ft/ft	0.010				
	К		16.13				
S ^{0.5}	Tsc	min	3.37				
		hr	0.06				
d (Paved)	Length	ft	325				
	Slope	ft/ft	0.011				
	К		20.33				
$S^{0.5}$	Tsc	min	2.58				
		hr	0.04				
	Length	ft	394				
	Velocity	ft/sec	6.00				
	Tc	min	1.10				
<u>/)</u> n		hr	0.02				
1		min	13.2				
+ t _c		hr	0.22		_		
				'	REVISION		
					REVI		
					DATE		
					DA		

DRAINAGE

PROJECT INFORMATION						
PROJECT MANAGER:	JT					
DESIGNED BY:	AM					
DRAWN BY:	CR/RM					
PROJECT NUMBER:	23-00436					
ORIGINAL DATE:	07/19/2024					


CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES
VERTICALLY AND HORIZONTALLY PRIOR TO
CONSTRUCTION. CONTRACTOR TO NOTIFY THE
ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.





REVISION			
DATE			
Š.			


PROJECT INFORMATION					
PROJECT MANAGE	ER:	JT			
ESIGNED BY:	AM				
RAWN BY:		CR/RM			
ROJECT NUMBER	R :	23-00436			
RIGINAL DATE:		07/19/2024			
SHEET		OF			
15	24				




UNDERGROUND DETENTION CALCULATION DATA


Label	Scenario	Return Event (years)	Hydrograph Volume (ft³)	Time to Peak (min)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ft³)
PO-1 (IN)	Post- Development 2	2	4,586.000	6.000	3.35	(N/A)	(N/A)
PO-1 (OUT)	Post- Development 2	2	4,586.000	27.000	1.43	1,015.81	2,908.000
PO-1 (IN)	Post- Development 10	10	9,179.000	6.000	7.28	(N/A)	(N/A)
PO-1 (OUT)	Post- Development 10	10	9,179.000	24.000	5.01	1,017.17	4,588.000
PO-1 (IN)	Post- Development 25	25	11,256.000	6.000	8.93	(N/A)	(N/A)
PO-1 (OUT)	Post- Development 25	25	11,256.000	24.000	6.25	1,017.38	5,635.000
PO-1 (IN)	Post- Development 100	100	14,839.000	6.000	11.78	(N/A)	(N/A)
PO-1 (OUT)	Post- Development 100	100	14,839.000	24.000	8.15	1,017.79	7,528.000

UNDERGROUND DETENTION OUTLET STRUCTURE



UNDERGROUND DETENTION





CONNECT TO UNDERGROUND DETENTION =

A-1.1 12" ADS CATCH BASIN INV. OUT=1016.87 RIM=1021.14

CONNECT TO UNDERGROUND DETENTION

SEE RISER DETAIL THIS SHEET-


INV: 1015.59

A-2.1 12" ADS CATCH BASIN

60' LF OF 6" HDPE @ 0.50%

A-2.3 JELLYFISH 1. INV. OUT = 1016 70

A-2.2 12_ ADS CATCH BASIN INV. OUT=1017.44 INV. IN=1017.54 (A-2.1 12" ADS Catch Basin) RIM=1020.87



A-1.2 3X3 JUNCTION BOX INV. DUT=1016.42 INV. IN=1016.52 (A-1.1 12" ADS Catch Basin) RIM=1020.83

INV. OUT=10 5.72 INV. IN=1015.42 (A RIM=1019.06

CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

PROJECT INFORMATION


7


DETENTION


UNDERGROUND


SCHOOL


MONTESSORI














"DEEPROOT" ROOT BARRIERS, OR APPROVED EQUAL, A MINIMUM OF TWENTY-FOUR INCHES (24") IN HEIGHT AND EIGHT FEET IN LENGTH (8') SHALL BE PROVIDED PARALLEL TO CURBLINE ON BOTH SIDES OF STREET TREES. ROOT BARRIERS SHALL BE PLACED WITH TOP OF ROOT BARRIER TWO INCHES (2") BELOW FINISHED GRADE AND

- RIBS FACING TOWARDS THE TREE. TREES SHALL BE PLACED A MINIMUM OF TEN FEET (10') FROM ALL EXISTING AND PROPOSED WASTEWATER LINES,
- WATER SERVICES, STORM SEWER LINES, AND CURB INLETS. I. A WATER RETENTION BASIN THREE INCHES (3") IN HEIGHT AND FOUR FEET (4') IN DIAMETER FORMED WITH TOPSOIL SHALL BE PROVIDED AROUND ALL TREES. INTERIOR OF BASIN SHALL BE FILLED WITH THREE INCH (3")
- LAYER OF SHREDDED BARK MULCH HELD THREE INCHES (3") BACK FROM THE TRUNK. ALL TREES SHALL BE STAKED WITH 7' LENGTH STEEL "T" POSTS, PAINTED DARK GREEN. LOCATE POSTS 6" +/-FROM ROOTBALL. DO NOT DISTURB ROOTBALL. POSTS SHALL BE DRIVEN 2' INTO GROUND WITH 5' EXPOSED ABOVE GROUND. POSTS SHALL BE CONSISTENT HEIGHT AND ALIGNED PARALLEL TO ADJACENT CURBS. USE 12-GAUGE STRANDED CABLE WITH HOSE TO PROTECT TRUNK. ENSURE THERE IS NO SLACK IN WIRES.


S. IF SOLID ROCK IS ENCOUNTERED AT DEPTHS LESS THAN TWENTY—SIX INCHES (26") FROM FINISHED GRADE,

INSTALL ROOT BARRIER TO TOP OF ROCK LAYER AND TRIM EXCESS LENGTH. *THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. DRAWING NOT TO SCALE.





City Of Leander, Texas STREET TREE INSTALLATION



FLOW TRENCH (BACKFILLED)

1. STEEL OR WOOD POSTS WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 300 mm (12 INCHES). IF WOOD POSTS CANNOT ACHIEVE 300 mm (12 inches) DEPTH, USE STEEL POSTS.

2 THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. 3. THE TRENCH MUST BE A MINIMUM OF 150 mm (6 inches) DEEP AND 150 mm (6 inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED


4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL OR WOOD FENCE POST. 5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR


REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED. 6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR


IMPEDE STORM FLOW OR DRAINAGE. 7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 Inches). THE SILT


SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MA	ANNER THAT WILL NOT CONTRIBUTE
TO ADDITIONAL SILTATION.	
	Pi Pi
rī	


	- ⁶		
CITY OF AUSTIN WATERSHED PROTECTION DEPARTMENT	SILT FENCE		
My 5. My 9/1/2011 ADDPTED	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	8TANDARD NO. 642S-1	
















CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

PROJECT INFORMATION PROJECT MANAGER: DESIGNED BY: DRAWN BY: PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024


F.


ORI


ONT


EDIME


DET













LEANDER, TX

SITE DESIGNATION: JELLYFISH 1






<u>CAUTION:</u>
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.


PROJECT INFORMATION PROJECT MANAGER: DESIGNED BY: DRAWN BY: PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024


H


0


ONT












PRE-CONSTRUCTION MEETING WITH YOUR LOCAL SALES ENGINEER TO DETERMINE IF ADDITIONAL MEASURES, NOT COVERED IN THIS GUIDE, ARE APPROPRIATE FOR YOUR SITE.

FOUNDATION

CONSTRUCT A FOUNDATION THAT CAN SUPPORT THE DESIGN LOADING APPLIED BY THE PIPE AND ADJACENT BACKFILL WEIGHT AS WELL AS MAINTAIN ITS INTEGRITY DURING CONSTRUCTION.

IF SOFT OR UNSUITABLE SOILS ARE ENCOUNTERED, REMOVE THE POOR SOILS DOWN TO A SUITABLE DEPTH AND THEN BUILD UP TO THE APPROPRIATE ELEVATION WITH A COMPETENT BACKFILL MATERIAL. THE STRUCTURAL FILL MATERIAL GRADATION SHOULD NOT ALLOW THE MIGRATION OF FINES, WHICH CAN CAUSE SETTLEMENT OF THE DETENTION SYSTEM OR PAVEMENT ABOVE. IF THE STRUCTURAL FILL MATERIAL IS NOT COMPATIBLE WITH THE UNDERLYING SOILS AN ENGINEERING FABRIC SHOULD BE USED AS A SEPARATOR. IN SOME CASES, USING A STIFF REINFORCING GEOGRID



REDUCES OVER EXCAVATION AND REPLACEMENT FILL QUANTITIES.

GRADE THE FOUNDATION SUBGRADE TO A UNIFORM OR SLIGHTLY SLOPING GRADE. IF THE SUBGRADE IS CLAY OR RELATIVELY NON-POROUS AND THE CONSTRUCTION SEQUENCE WILL LAST FOR AN EXTENDED PERIOD OF TIME IT IS BEST TO SLOPE THE GRADE TO ONE END OF THE SYSTEM. THIS WILL ALLOW EXCESS WATER TO DRAIN QUICKLY, PREVENTING SATURATION OF THE SUBGRADE.


GEOMEMBRANE BARRIER

A SITE'S RESISTIVITY MAY CHANGE OVER TIME WHEN VARIOUS TYPES OF SALTING AGENTS ARE USED, SUCH AS ROAD SALTS FOR DEICING AGENTS, IF SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE, A GEOMEMBRANE THE ENTIRE WIDTH OF THE SYSTEM IS REACHED, ADVANCE THE EQUIPMENT BARRIER IS RECOMMENDED WITH THE SYSTEM. THE GEOMEMBRANE LINER IS TO THE END OF THE RECENTLY PLACED FILL, AND BEGIN THE SEQUENCE INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM THE USE OF SUCH AGENTS INCLUDING PREMATURE CORROSION AND REDUCED ACTUAL SERVICE LIFE. THE PROJECT'S ENGINEER OF RECORD IS TO EVALUATE WHETHER SALTING

AGENTS WILL BE USED ON OR NEAR THE PROJECT SITE, AND USE HIS/HER BEST JUDGEMENT TO DETERMINE IF ANY ADDITIONAL PROTECTIVE MEASURES ARE REQUIRED. BELOW IS A TYPICAL DETAIL SHOWING THE PLACEMENT OF A GEOMEMBRANE BARRIER FOR PROJECTS WHERE SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE.


DETERMINE THE LIMITS OF EXCAVATION BEYOND THE SPRING LINE OF THE PIPE DISTORTION OR DISPLACEMENT, WHICH ALSO AFFECTS THE CLSM OUTER MOST PIPES. LIFT THICKNESS. YOUR LOCAL CONTECH SALES ENGINEER CAN HELP

PROPER BACKFILL PLACEMENT AND COMPACTION TAKE CARE OF THIS CONCERN.



BACKFILL PLACEMENT

MATERIAL SHALL BE WORKED INTO THE PIPE HAUNCHES BY MEANS OF SHOVEL-SLICING, RODDING, AIR TAMPER, VIBRATORY ROD, OR OTHER EFFECTIVE



IF AASHTO T99 PROCEDURES ARE DETERMINED INFEASIBLE BY THE GEOTECHNICAL ENGINEER OF RECORD, COMPACTION IS CONSIDERED ADEQUATE WHEN NO FURTHER YIELDING OF THE MATERIAL IS OBSERVED UNDER THE COMPACTOR, OR UNDER FOOT, AND THE GEOTECHNICAL ENGINEER OF RECORD (OR REPRESENTATIVE THEREOF) IS SATISFIED WITH THE LEVEL OF COMPACTION.

FOR LARGE SYSTEMS, CONVEYOR SYSTEMS, BACKHOES WITH LONG REACHES OR DRAGLINES WITH STONE BUCKETS MAY BE USED TO PLACE BACKFILL. ONCE MINIMUM COVER FOR CONSTRUCTION LOADING ACROSS AGAIN UNTIL THE SYSTEM IS COMPLETELY BACKFILLED. THIS TYPE OF CONSTRUCTION SEQUENCE PROVIDES ROOM FOR STOCKPILED BACKFILL IRECTLY BEHIND THE BACKHOE, AS WELL AS THE MOVEMENT OF CONSTRUCTION TRAFFIC. MATERIAL STOCKPILES ON TOP OF THE

AND MUST PROVIDE BALANCED LOADING ACROSS ALL BARRELS. TO DETERMINE THE PROPER COVER OVER THE PIPES TO ALLOW THE MOVEMENT OF CONSTRUCTION EQUIPMENT SEE TABLE 1, OR CONTACT YOUR

www.ContechES.com

025 Centre Pointe Dr., Suite 400, West Chester, OH 450

BACKFILLED DETENTION SYSTEM SHOULD BE LIMITED TO 8- TO 10-FEET HIGH

(OR OTHER REMOVABLE WEIGHTS)


CONSTRUCTION LOADING

DETERMINE THE PROPER LIFT THICKNESS

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.

ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION; POTENTIALLY CAUSING FLOATATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.



INSPECTION IS THE KEY TO EFFECTIVE MAINTENANCE OF CMP DETENTION SYSTEMS AND IS EASILY PERFORMED, CONTECH RECOMMENDS ONGOING ANNUAL INSPECTIONS. SITES WITH HIGH TRASH LOAD OR SMALL OUTLET CONTROL ORIFICES MAY NEED MORE FREQUENT INSPECTIONS. THE RATE AT WHICH THE SYSTEM COLLECTS POLLUTANTS WILL DEPEND MORE ON SITE SPECIFIC ACTIVITIES RATHER THAN THE SIZE OR CONFIGURATION OF THE

INSPECTIONS SHOULD BE PERFORMED MORE OFTEN IN EQUIPMENT WASHDOWN AREAS, IN CLIMATES WHERE SANDING AND/OR SALTING OPERATIONS TAKE PLACE, AND IN OTHER VARIOUS INSTANCES IN WHICH ONE WOULD EXPECT HIGHER ACCUMULATIONS OF SEDIMENT OR ABRASIVE/ CORROSIVE CONDITIONS A RECORD OF EACH INSPECTION IS TO BE MAINTAINED FOR THE LIFE OF THE SYSTEM

MAINTENANCE

CMP DETENTION SYSTEMS SHOULD BE CLEANED WHEN AN INSPECTION REVEALS ACCUMULATED SEDIMENT OR TRASH IS CLOGGING THE DISCHARGE


ACCUMULATED SEDIMENT AND TRASH CAN TYPICALLY BE EVACUATED THROUGH THE MANHOLE OVER THE OUTLET ORIFICE. IF MAINTENANCE IS NOT LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE PERFORMED AS RECOMMENDED, SEDIMENT AND TRASH MAY ACCUMULATE IN FRONT OF THE OUTLET ORIFICE, MANHOLE COVERS SHOULD BE SECURELY SEATED FOLLOWING CLEANING ACTIVITIES. CONTECH SUGGESTS THAT ALL SYSTEMS BE DESIGNED WITH AN ACCESS/INSPECTION MANHOLE SITUATED AT OR NEAR THE INLET AND THE OUTLET ORIFICE. SHOULD IT BE NECESSARY TO GET INSIDE THE SYSTEM TO PERFORM MAINTENANCE ACTIVITIES, ALL APPROPRIATE PRECAUTIONS REGARDING CONFINED SPACE ENTRY AND OSHA REGULATIONS SHOULD BE FOLLOWED.

> ANNUAL INSPECTIONS ARE BEST PRACTICE FOR ALL UNDERGROUND SYSTEMS. DURING THIS INSPECTION, IF EVIDENCE OF SALTING/DE-ICING AGENTS IS OBSERVED WITHIN THE SYSTEM, IT IS BEST PRACTICE FOR THE SYSTEM TO BE RINSED. INCLUDING ABOVE THE SPRING LINE SOON AFTER THE SPRING THAW

AS PART OF THE MAINTENANCE PROGRAM FOR THE SYSTEM. MAINTAINING AN UNDERGROUND DETENTION OR INFILTRATION SYSTEM IS

EASIEST WHEN THERE IS NO FLOW ENTERING THE SYSTEM. FOR THIS REASON, IT IS A GOOD IDEA TO SCHEDULE THE CLEANOUT DURING DRY

THE FOREGOING INSPECTION AND MAINTENANCE FEFORTS HELP ENSURE UNDERGROUND PIPE SYSTEMS USED FOR STORMWATER STORAGE CONTINUE TO FUNCTION AS INTENDED BY IDENTIFYING RECOMMENDED REGULAR INSPECTION AND MAINTENANCE PRACTICES. INSPECTION AND MAINTENANCE RELATED TO THE STRUCTURAL INTEGRITY OF THE PIPE OR THE SOUNDNESS OF PIPE JOINT CONNECTIONS IS BEYOND THE SCOPE OF THIS GUIDE.



DYO50807 San Gabriel Day Care





CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES

35338 50807 5/15/2024

DRAWN:

PROJECT INFORMATION PROJECT MANAGER: **DESIGNED BY:** DRAWN BY: CR/RM PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024

0

0

 Employed


S


0


S


NO


0



























IRE DEPARTMENT CONNECTION SIGN




- 3. SIGNS SHALL BE PERMANENTLY AFFIXED TO A STATIONARY POST AND THE BOTTOM OF THE SIGN ASSEMBLY SHALL BE
- SIX FEET, SIX INCHES (6'-6") ABOVE FINISHED GRADE.
- 4. SIGNS SHALL BE SPACED NOT MORE THAN 35' APART.
- 5. SIGNS MAY BE INSTALLED ON PERMANENT BUILDINGS OR WALLS AS APPROVED BY THE FIRE CODE OFFICIAL. 6. IF THE SIGN IS AT THE END OF A FIRE ZONE, THE SIGN SHALL HAVE A SINGLE-HEADED ARROW POINTING IN THE DIRECTION OF THE ZONE. IF THE SIGN IS AT AN INTERMEDIATE POINT IN THE ZONE, THE SIGN SHALL HAVE A DOUBLE-HEADED ARROW POINTING IN BOTH DIRECTIONS.
- 7. FIRE LANE SIGNS SHALL BE POSTED ON BOTH SIDES OF FIRE APPARATUS ACCESS ROADS THAT ARE TWENTY FEET (20') TO TWENTY-SIX FEET (26') WIDE.
- 8-FIRE LANE SIGNS SHALL BE POSTED ON ONE SIDE OF FIRE APPARATUS ACCESS ROADS MORE THAN TWENTY-SIX FEET
- (26') WIDE AND LESS THAN THIRTY-TWO FEET (32') WIDE.

THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. DRAWING NOT TO SCALE.





City Of Leander, Texas DETAIL #501-1 FIRE LANE SIGN ASSEMBLY







CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES


PROJECT NUMBER:


PROJECT INFORMATION

PROJECT MANAGER:











OF THIS STANDARD.

2 OF 2




NTS


ASPHALT TO CONCRETE PAVEMENT JOINT





9 1/2"


IFITA D. MFADO\













CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

ESP Associate

ESP Associate

ESP Associate

12940 Country

1410322

San Antonio, TX

(210) 349-32


www.espassociate


SITE DETAILS


KA MONTESSORI SCHOOL


PROJECT INFORMATION						
PROJECT MANAGE	JT					
DESIGNED BY:	AM					
DRAWN BY:	CR/RM					
PROJECT NUMBER	23-00436					
ORIGINAL DATE:	07/19/2024					
SHEET		OF				


31




















BOLLARD NOT TO SCALE









SCHOOL

MONTESSORI


PROJECT INFORMATION


DETAILS








STANDARD FIRE HYDRANT ASSEMBLY

















CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES
VERTICALLY AND HORIZONTALLY PRIOR TO
CONSTRUCTION. CONTRACTOR TO NOTIFY THE
ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

PROJECT INFORMATION

PROJECT MANAGER: JT

DESIGNED BY: AM

DRAWN BY: CR/RM

PROJECT NUMBER: 23-00436

ORIGINAL DATE: 07/19/2024

SHEET OF


0


CHO


ORI


MONT

DETAIL











ADOPTED


OF THIS STANDARD. MODIFICATIONS TO

THIS STANDARD ARE PROHIBITED.

2 OF 2










CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.


PROJECT INFORMATION PROJECT MANAGER: DESIGNED BY: DRAWN BY: PROJECT NUMBER: 23-00436 ORIGINAL DATE: 07/19/2024


 Employed

S

O











CAUTION:
CONTRACTOR TO VERIFY ALL EXISTING UTILITIES
VERTICALLY AND HORIZONTALLY PRIOR TO
CONSTRUCTION. CONTRACTOR TO NOTIFY THE
ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.

31

ORIGINAL DATE:

31

23-00436

07/19/2024

PROJECT INFORMATION

PROJECT MANAGER:

PROJECT NUMBER:

DESIGNED BY:
DRAWN BY:

7


SCHO


ORI


MONTESS

DETAIL

UTILITY










0741 0175 4854									
OTAL SITE AREA	73,947								
OTAL STREETYARD AREA	15,254	SF							
OMMERCIAL	73,947	Χ	15%	=	11,092				
OVERALL LANDSCAPE AREA REQUIRED					11,092	SF			
	15,254	Χ	15%	=	2288				
STREETYARD LANDSCAPE REQUIRED					2,288	SF			
	11,092	+	600	=	18	Χ	2	=	37
OTAL TREES REQUIRED	······································								37
	11,092	+	600	=	18	Χ	4	=	74
OTAL SHRUBS REQUIRED	······································								74
TREETYARD LANDSCAPE AREA	3,084	SF	84.4%						
(50% MIN. REQUIRED)									
THER LANDSCAPE AREA	571	SF	15.6%	_					
TOTAL LANDSCAPE AREA PROVIDED	3,655	SF	100%	_					
	CODE	QTY	%	(50% MAX.	EA.)				
	СМ	4	8.3%						
	DS	3	6.3%						
	LI	5	10.4%						
OTAL SMALL/ORNAMENTAL TREES		12	25.0%	_					
	PM	7	14.6%						
	QM	7	14.6%						
	QV	7	14.6%						
	TD	7	14.6%						
	UC	8	16.7%						
OTAL SIGNIFICANT/SHADE TREES (75% MIN. REQUIRED)		36	75.0%						
OTAL TREES PROVIDED		48	100%						
ARKING LOT SCREENING									
IO PACE MORE THAN 50' AWAY FROM TE	EE. PROVIDED	AS REQUI	RED.						
ANDSCAPE SCREENING									
ROVIDED AS REQUIRED.									

CITY OF LEANDER NOTES

- 1. THE DEVELOPER AND SUBSEQUENT OWNERS OF THE LANDSCAPED PROPERTY, OR THE MANAGER OR AGENT OF THE OWNER, SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL LANDSCAPE AREAS. SAID AREAS SHALL BE MAINTAINED SO AS TO PRESENT A HEALTHY, NEAT AND ORDERLY APPEARANCE AT ALL TIMES AND SHALL BE KEPT FREE OF REFUSE AND DEBRIS. ALL PLANTED AREAS SHALL BE PROVIDED WITH AN AUTOMATIC IRRIGATION SYSTEM AND WATERED AS NECESSARY TO ENSURE CONTINUOUS HEALTHY GROWTH AND DEVELOPMENT. MAINTENANCE SHALL INCLUDE THE REPLACEMENT OF ALL DEAD PLANT MATERIAL IF THAT MATERIAL WAS USED TO MEET THE REQUIREMENTS OF THE LANDSCAPE ORDINANCE.
- 2. TREE CALIPER IS THE TRUNK DIAMETER OF A TREE AT TWELVE (12") INCHES ABOVE NATURAL GRADE PER THE COMPOSITE ZONING ORDINANCE.
- 3. ALL NEW LANDSCAPES (NON-RESIDENTIAL AND RESIDENTIAL) ARE REQUIRED TO HAVE A MINIMUM OF SIX INCHES (6") OF SOIL DEPTH IN AREAS PLANTED WITH TURFGRASS. THIS SIX-INCH (6") MINIMUM SOIL DEPTH WILL CONSIST OF 75 PERCENT SOIL BLENDED WITH 25 PERCENT COMPOST. THE SOIL/COMPOST BLEND SHALL BE INCORPORATED INTO THE TOP TWO INCHES OF THE NATIVE SOIL. THE SIX-INCH (6") DEPTH REQUIREMENT DOES NOT APPLY TO THE AREA BETWEEN THE DRIP LINE AND TRUNK OF EXISTING TREES, SHRUB BEDS OR WILDSCAPE AREAS. AREAS WITH EXISTING NATIVE VEGETATION THAT REMAIN UNDISTURBED SHALL BE EXEMPT FROM THE SOIL DEPTH PROVISION; PROVIDED THAT NATIVE SOIL AND VEGETATION IN SUCH AREA IS FENCED DURING CONSTRUCTION AND PROTECTED FROM DISTURBANCE AND COMPACTION DURING THE CONSTRUCTION PROCESS.
- 4. ALL DISTURBED AREAS AND ROW WILL BE RE-VEGETATED BY THE DEVELOPER.
- 5. ALL INVASIVE SPECIES SHALL BE REMOVED FROM THE PROPERTY.
- 6. A MINIMUM PERVIOUS AREA 3 FEET IN RADIUS AND NOT LESS THAN 50% OF THE CALCULATED DRIP LINE AREA IS PROVIDED AROUND THE TRUNKS OF ALL EXISTING AND PROPOSED TREES.
- 7. NO MORE THAN 50% OF THE SAME SPECIES MAY BE PLANTED TO MEET THE TREE PLANTING REQUIREMENTS.
- 8. NO LANDSCAPING OVER 3 FEET HIGH IS LOCATED WITHIN 40 FEET OF THE INTERSECTION OF ANY STREET. (MEASURED FROM THE EDGE OF PAVEMENT AS IF THE CURBS OR PAVEMENT EDGES ARE NOT ROUNDED OFF AND INTERSECT AT A RIGHT ANGLE).
- 9. IN THE EVENT OF A CONFLICT WITH TREE REMOVAL/PRESERVATION CALL OUTS ON PLAN SHEET(S) VERSUS TREE REMOVAL/PRESERVATION MATRIX, THE TREE REMOVAL/PRESERVATION MATRIX SHALL APPLY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY WITH CITY STAFF SHOULD ANY INCONSISTENCY EXIST WITHIN AN APPROVED PLAN SET. NO IN-FIELD CHANGES ARE MADE TO APPROVED PLANS, NO EXCEPTIONS.







LANDSCAPE PLANTING

- 1.1 Section Includes
- A. Contractor will provide all labor, materials, supplies, equipment. tools, transportation, and services; perform all operations to complete installation of landscape planting, complete in place, as shown and specified on drawings; and guarantee all work.
 - 1. Work will include, but is not limited to Procurement of all applicable licenses, permits, and
 - Location of utility locations prior to construction.
 - Site inspection.
 - Soil preparation and fine grading. Planting of trees, shrubs, and other plants.
 - Installation of sod.
 - Installation of seed.
 - Anchoring or staking of trees.
 - Mulching all trees and plant beds. Installing landscape gravel.
 - Fertilization and pest and disease control for plants.
 - Site cleanup.
 - Maintenance of planting as specified in these specifications or in Contract documents.

Guarantee of all planting.

- A. The requirements of the "General and Supplementary Conditions of the Contract" and Division 1 specification sections will apply to all work of this Section with the same force and effect as though repeated in full herein.
- General Scope of Work and Requirements
- Site Gradina (see Civil specifications)
- Section 32 01 90.33: Tree Protection Section 32 80 00: Irrigation System Section 32 92 13: Hydromulching
- Section 32 93 19: Seeding Section 32 93 23: Sodding

1.3 References

- A. American Society for Testing and Materials (ASTM)
- D5268-13: Topsoil Used for Landscaping Purposes American National Standards Institute (ANSI) 1. ANSI Z60.1—2014: American Standard for Nursery Stock
- C. Hortus Third: Concise Dictionary of Plants Cultivated in United
- States and Canada D. Tree Case Industry Association (TCIA) 1. ANSI A300P1-2017: Tree Care Operations - Trees, Shrubs and Other Woody Plant Maintenance Standard Practices
- Turfgrass Producers International (TPI)
- 2006 Guideline Specifications to Turfgrass Sodding F. U.S. Department of Agriculture Rules and Regulations under the
- Federal Seed Act G. Texas Seed Law regulations and requirements

1.4 Submittals A. General Requirements:

- 1. The Contractor will furnish the articles, equipment, materials, or processes specified by name in the drawings and specifications. No substitution will be allowed without
- prior approval by the Landscape Architect. Submit a complete material list prior to performing any work. Material list will include the manufacturer and description of all materials to be used and samples as outlined below.
- 3. Contractor will be prepared to show receipt, bill of sale, or other documentation as proof of source for all materials submitted, including but not limited to plant materials, soils, soil amendments, and mulch
- Submit qualifications per 1.8 Quality Assurance and Requirements.
- Submit a schedule of work to be performed.
- B. Plant Selection: 1. Submit plant schedule on Contractor letterhead naming quantities and supplier of each plant species for Landscape Architect's approval.
- Submit source and guarantee of sod quality. Submit certification of seed and mulching agent.
- If material is to be approved on—site, tag and maintain plant material as representative samples. Samples may be used to complete installation, provided they remain tagged until final acceptance of entire installation.
- C. Miscellaneous Materials: 1. Submit for approval one (1) gallon quantities and product information of topsoil, prepared soil, soil amendment, mulch
- 2. Submit topsoil analysis with recommendations for amendments required to support plant growth. See
- paragraph 2.4 Source Quality Control and Tests, D. 3. Submit product information on packaged materials, tree stakes/root anchoring system, tree boots, fabric, fertilizer, herbicide and insecticide. Product information must be approved by the Landscape Architect before use on the
- 4. All samples will be delivered in a box. Clearly mark samples with job name and Contractor name. Product information may be submitted in electronic format
- or printed and collated into a binder. Clearly mark binder with job name and Contractor name. D. Record Drawings:
- 1. The Contractor will provide and keep up—to—date an "as-built" set of drawings, which will be corrected daily and show every change from the original drawings and specifications and the exact "as-built" locations and sizes of plant material installed. This set of drawings will be kept
- on the site and will be used only as a working set. Before the date of the final inspection, the Contractor will transfer all information from the "as-built" prints to a final set of drawings. All work will be in pen to allow
- proper printing of original 3. On or before the date of the final inspection, the
- Contractor will deliver the completed drawings, in hard copy or electronic format as required by contract documents, to the Owner and Landscape Architect. Delivery of the record drawings will not relieve the Contractor of the responsibility of furnishing required information that may be omitted from the prints.
- Maintenance Schedule: Submit a maintenance schedule identifying landscape maintenance procedures to be performed during construction and throughout the maintenance period. See section 1.12 Maintenance. The schedule will be typewritten and specify procedures to be accomplished month by month.

A. Submit proof to Landscape Architect if plant material is not available 30 days prior to plant installation. Substitution will be approved by Owner or Landscape Architect by Architect's Supplemental Instructions.

- 1.6 Product Delivery, Storage and Handling
 - A. Deliver plant material to site in containers. Protect plant material from sun-scald and wind burn during transport to site. Prune only limbs that have broken in transport. Keep plants watered as
 - Deliver grass seed mixture in sealed containers. Seed in damaged packaging is not acceptable. Deliver seed mixture in containers showing percentage of seed mix, year of production, net weight, date of packaging, and location of packaging C. Deliver sod to site on pallets or in "big roll" form. Protect
- exposed roots from dehydration. Do not stack for more than 24 hours between time of cutting and time of delivery. Do not deliver more sod than can be laid within 24 hours.
- Deliver packaged materials in containers showing weight, analysis and name of manufacturer. Protect materials from deterioration during delivery and while stored at site.
- 1.7 Quality Assurance and Requirements A. Permits and Fees: The Contractor will obtain and pay for all permits and inspections as required. Contractor will also be
 - responsible for all fees and costs involved for work. 1. Contractor will comply with County inspector directions with agreement from Landscape Architect without additional cost to Owner.
 - Ordinances and Regulations: All local, municipal and state laws, rules and regulations governing or relating to any portion of this work are hereby incorporated into and made a part of these specifications, and their provisions will be carried out by the Contractor. Anything contained in these specifications will not be construed to conflict with any of the above rules and regulations or requirements of the same. However, when these specifications and drawings call for or describe materials, workmanship, or construction of a better quality, higher standard, or larger size than is required by the above rules and regulations, the provisions of these specifications and drawings will take precedence.
 - Personnel: Landscape Contractor personnel will be supervised by a certified landscape professional (TCLA or TCLP—Texas Nursery & Landscape Association). Employ only experienced installation personnel who are familiar with the required work. Provide adequate supervision by a qualified foreman
- Plant Material: Plant materials will be subject to inspection and approval of Landscape Architect at place of growth or upon delivery for conformity to specifications. Such approval will not impair the right of inspection and rejection during progress of the work. Inspection and tagging of plant material by the Landscape Architect is for design intent only and does not constitute the Landscape Architects' approval of the plant materials regarding their health and vigor as specified in Part 2, Section 2.1 Plant Material. The health and vigor of the plant material is the sole responsibility of the Contractor.
 - 1. General: Comply with applicable federal, state, county, and local regulations governing landscape materials and work. 2. Any plant material in shock, decline or not meeting specified planting size, height and caliper will be rejected by the Landscape Architect at any time during the project.

1.8 Project Conditions

A. Site Utilities: Contractor will be responsible for determining locations of all underground utilities prior to commencement of work.

Perform all work in a manner which will avoid damage to

- utilities, including damage from heavy equipment or trucks. Hand excavate as required to minimize possibility of damage to underground utilities. 4. Coordinate work with the Irrigation Contractor to prevent
- damage to underground wire or pipe located in landscape Contractor will be responsible for repairing any damage to
- underground utilities caused by landscape work. Condition of Surfaces: All shrub and groundcover planting areas
- will be left at finished grade. Water will be provided on site by the Owner. Landscape Contractor will provide hoses and other watering equipment and labor necessary for work.. The round—a—bouts do not have water and will require regular visits with a water truck to insure one year of

A. The Contractor will begin exterior landscape work upon acceptance of the Contract by the Owner. Landscape Contractor will submit a schedule for the work to be performed to the Landscape Architect for approval.

1.10 Protections

A. All items required to complete this contract remain the property and responsibility of the Contractor until final acceptance. Contractor will take adequate precautions to protect all work and materials from damage. Contractor will cooperate fully with other trades to ensure a satisfactory completion.

- A. Maintain plant material for three (3) months after final acceptance by Owner.
- Maintain plant materials upon delivery to job site. Maintain plant materials immediately after placement and until plants are well established and exhibit a vigorous growing
- Maintenance to include:
- Cultivation and weeding plant beds and tree pits. Applying herbicides, insecticides, and fungicides as necessary for weed control of all areas and plant materials
- in accordance with manufacturer's instructions. Remedy damage resulting from use of herbicides. 3. Irrigating sufficiently to saturate root system of all plant
- materials and to sustain life and promote growth. Pruning and treatment of pruned areas or other wounds. Applying appropriate chemicals as required to control any disease that may occur during the maintenance period.

Notify Owner and Landscape Architect of any sign of

- serious disease. 6. Maintaining tree anchor systems. Tighten straps as
- Maintaining guys and tree stakes. Adjust to keep guy wires firm. Repair or replace accessories when required.
- Replacing mulch. Watering, mowing, edging, weeding and fertilizing lawn

- A. Contractor will warranty trees for one year after final acceptance. 1. Replace trees which have partially died thereby damaging shape, size or symmetry with same kind and sizes as originally planted at no additional cost to Owner.
- 2. Trees may be replaced at the start of next year's planting or digging season at the direction of Owner or Landscape Architect. In such cases, remove dead trees immediately.
- Provide one—year guarantee on replacement trees. Replace dead plant materials and plant materials not in vigorous, thriving condition as soon as weather permits and on notification

- by Owner or Landscape Architect.
- C. Protect irrigation system and any other piping, conduit, or other work during replacement. Repair any damage immediately. Warranty excludes replacement of plants because of injury by storm, drought, hail, freeze, insects or diseases, and other acts of God occurring after final acceptance.

PART 2: PRODUCTS

- 2.1 General A. All materials and equipment furnished will be free of noxious weeds including.
 - B. Plants will be in accordance with the latest edition of "American Standard for Nursery Stock" sponsored by AmericanHort. C. All plants will have a normal habit of growth and will be sound, healthy, vigorous and free from insect infestations, plant diseases, sunscalds, fresh abrasions of the bark, excessive abrasions, shock or other objectionable disfigurements. If sample plants inspected are found to be defective, the Landscape Architect reserves the right to reject the entire lot or lots of plants represented by the defective samples. Any plants rendered unsuitable for planting

because of this inspection will be rejected and will be the

- responsibility of the Contractor and removed from site. The size of the plants will correspond with that normally expected for species and variety of commercially available nursery stock or as specified on drawings. The minimum acceptable size of all plants measured before pruning with the branches in normal position will conform with the measurements specified on the drawings. Plants larger in size than specified may be used with
- no change in contract price. E. If larger plants than indicated on drawings are approved, the rootball for each plan will be increased proportionally.
- F. Under no conditions will there be any substitutions for plants or sizes listed in the drawings, except with the express consent of the Landscape Architect. G. Plant material will be true to botanical and common name and
- H. Plants will be hardy under climatic conditions similar to those in locality of project.
- Seed will be prepared for sale during the year of installation. All materials used will be new and without flaws or defects of any type and will be the best of their class and kind.

K. Any materials that have become wet, moldy, or otherwise

damages in transit or in storage will not be used.

- 2.2 Shade and Ornamental Trees
- A. Healthy, vigorous, full-branched, well-shaped, trunk diameter and height requirements as specified. Trees will be in containers unless otherwise noted on plans.
- B. B&B trees will not be accepted for containerized materials without approval from Landscape Architect.
- C. Specified B&B trees will have rootballs that correspond with that normally expected for species and variety of commercially available nursery stock. Rooballs will be firm, neat, slightly
- tapered, and heeled for a period of one (1) year. D. Trees with loose or broken rootballs at time of planting will be
- Trees in grow bags or grow liners will be rejected. Trees will be individually approved by the Landscape Architect. Rootballs will conform to ANSI Z60.1-2014 American Standard for
- Nursery Stock.
- 2.3 Shrubs, Groundcovers, and Perennials A. Shrubs, groundcovers, and perennials will be nursery grown,
- healthy, vigorous, bushy, well branched, of normal habit of growth for species, free from disease, insect eggs and larvae. B. Specified sizes will be before pruning, and plants will be measured
- with their branches in normal position. Rootballs will conform to ANSI Z60.1-2014 American Standard for Nursery Stock.
- 2.4 Turf Materials: A. Sod: Sod will be classified as certified stock or originate as
 - 1. TPI, Certified Turfgrass Sod; Approved Turfgrass Sod; Nursery Turf grass Sod; Field Turfgrass Sod; or cultivated grass sod; with strong fibrous root system, free of stones, burned or bare spots; containing no more than 5 weeds per 1,000 sq ft. Minimum age of 18 months, with root development that will support its own weight without tearing, when suspended vertically by holding the upper two
 - Deliver to site on pallets. Do not stack for more than 24 hours between time of cutting and time of delivery. Species will be Common Bermuda (Cynodon dactylon).
 - Seed will only be that which is specified by Landscape Architect in drawings. All seed shall be mixed by a wholesale see supplier in order to obtain the specified mixture and application rate required by Landscape
 - Architect. No species substitutions will be permitted without prior approval of the Landscape Architect. All seed will conform to all current State and Federal
 - reaulations. All seed and seed mixed will be furnished din bags or container clearly labeled to show the name and address of the supplier, the common, scientific, and variety name(s) of the seed(s), the lot number, point of origin, new weight, percent of weed content, and the guaranteed percentage
 - of purity and germination. 4. All seed will be guaranteed for purity and germination, free of noxious weed seed, and supplied on a Pure Live Seed (PLS) basis. Seed species:
 - a. Seed mix will be hulled Common Bermuda (Cynodon dactylon), minimum two (2#) PLS per one thousand 1,000 sq.ft.) square feet. Seed mix will be Buffalograss (Buchloe dactyloides),
 - minimum two (2#) PLS per one thousand (1,000 sq. ft.) square feet. c. Shade areas: Shade—Friendly Grass Mix, by Native American Seed, 1-800-728-4043, minimum one and one—half (1.5#) PLS per one thousand (1,000 sq.
 - ft.) square feet. Sunny areas: Caliche Mix, by Native American Seed, -800-728-4043, minimum four and one-half (4.5#) PLS per one thousand (1,000 sq.ft.) square

2.5 Soil Preparation Materials

1. Native topsoil: Soil in-place on site will be harvested and stockpiled for reuse. Native topsoil will be free from contaminants and debris, and reasonably free from rocks,

Soil and Compost in San Antonio, TX, or approved

roots and limbs. 2. When native soil cannot be used, or is not plentiful, soil may be imported as follows: a. Bed areas: 4—Way Mix, manufactured by New Earth

or approved equal. C. Fertilizer: otherwise approved), organic base, uniform in composition,

b. Lawn areas: Enriched Topsoil, manufactured by New

3. Soils containing high clay content, rock or debris greater

Native topsoil will be amended with: Landscapers Compost,

than one-half (1/2) inch diameter, or weeds will be

manufactured by New Earth Soil and Compost in San Antonio, TX,

Earth Soil and Compost in San Antonio, TX, or

rejected and the Contractor will be responsible for removing

1. Turf Fertilizer: Complete fertilizer with 12:4:8 ratio (unless dry and free flowing. Deliver fertilizer to site in original, unopened containers, each bearing manufacturer's guaranteed statement of analysis.

it from site.

- Tree and Shrub Fertilizer: Agriform 20-10-5 planting tablets, 21 grams.
- 1. Pre-emergent herbicide: Will be of a composition to kill undesirable weed species. Submit information Post-emergent herbicide: Will be of composition to selectively kill undesirable weed species. Submit information
- Pesticides: Fungicides: Submit information as required. Insecticides: Submit information as required. Other chemicals: Submit information as required.

2.6 Miscellaneous Materials

- Mulch: Mulch will be Double Shredded Native Hardwood Mulch by New Earth Soil and Compost in San Antonio, TX, or approved
- B. Seed mulching material: Wood cellulose fiber, free from germination or grown inhibiting factor. Shall become evenly dispersed and suspended when agitated with water. Will form a groundcover which readily absorbs water and allows infiltration to underlying soil. Weight specifications from suppliers will refer to air dry weight of the fiber with a standard equivalent to eighteen (18%) percent moisture. Mulch material will be marked by the
- manufacturer to show the dry weight content. C. Steel edger: 4"x1/4" steel landscape edging with stakes, black in
- D. Tree root anchor: ArborGuy tree guying system by GreenBlue Urban, 1-866-282-2743, or approved equal.
- E. Tree staking Stakes: Metal T-posts, 6' ht., green in color. Tie: A.M. Leonard rubber extra heavy duty adj-a-tye chaiin lock 1" thick tree ties or approved equal.
- Tree boot: ArborGard+, Model AG9-4 or approved equal. Tree watering bag: TreeGator Bag, 15 gallon, or approved equal. H. Gravel: Gravel will be 1" diameter scale Texas Blend gravel and will be clean, washed, hard, sound, durable, uniform in quality, and free of foreign matter. Available from Keller Material, Inc.,
- San Antonio, Texas, (210) 648-4221, or approved equal. Filter fabric: Dewitt's Pro-5 Weed Barrier, 5 oz. woven, needle

Water: Water will be available on site. 2.7 Source Quality Control and Tests

punched polypropylene fabric or approved equal.

- A. Section 01 40 00 Quality Requirements: If existing, excavated. on-site soil is to be reused, provide a chemical analysis of existing topsoil.
- Soil analysis will ascertain the percentage of nitrogen, phosphorus, potash, soluble salt, organic matter and pH value. Contractor will indicate, by test results, information regarding necessary soil amendments to support plant growth.
- Testing is not required for imported soil if recent tests are available. Submit these test results to the Landscape Architect

D. Soils analysis must be dated within 45 days of installation of

PART 3: EXECUTION

- A. It will be the responsibility of the Contractor to locate and protect all utilities and existing feature (including vegetation) on the work site. Any damage caused by the Contractor or Subcontractor will be immediately repaired or correct by the
- Contractor at no expense to the Owner. B. In order to protect the site from excessive erosion, planting will be completed as soon as practical after the completion of final grading. Contractor will coordinate the actual start of planting
- operations with Landscape Architect. C. Planting will be performed during those periods when weather and soil conditions are suitable and in accordance with locally

of lawn. Contractor will maintain seeded areas until established

accepted practices. Plants will be grown in containers as indicated on the plans. Plants will remain in those containers until transplanting. E. Contractor is responsible for establishing a healthy and full stand

and approved by Landscape Architect. Provide temporary irrigation as required for grown of a full stand of lawn.

- Inspection Observe site prior to construction and accept site when satisfied with conditions. Landscape Contractor will be responsible for
- shaping all planting areas as indicated on plans or as directed by Landscape Architect. B. Inspect trees, shrubs and liner stock plant material for injury,
- insect infestation and trees and shrubs for improper pruning. C. All planting beds will be free of any deleterious materials, including but not limited to concrete debris, trash, buried organic material, and base material from drive and building construction. D. Do not begin planting until deficiencies are corrected or plants

replaced. Do not start work until grading is complete and

approved by Engineer or Architect.

- A. Preparing subgrade: 1. Prepare subgrade to eliminate uneven areas. Maintain profiles and contours. Make changes in grade gradual.
 - Blend slopes into level areas. Remove foreign material, rocks, base material, weeds and undesirable plants and their roots. Remove contaminated
- Till subgrade to a minimum depth of six (6") inches areas where plants are to be placed. Till subgrade to a depth twelve (12") inches areas where
- soil has been compacted by construction activities. Placing topsoil: 1. Place topsoil during dry weather and on dry unfrozen
- Spread topsoil to a minimum depth of four (4") inches over bed areas. Rake smooth. Spread topsoil to a minimum depth of two (2") inches over sod and seed areas. Rake smooth.

Remove organic matter and foreign non-organic material

- from topsoil while spreading. Break up soil clods as possible, remove those that cannot be broken. Grade topsoil to eliminate rough, low or soft areas, and to
- ensure positive drainage. Install topsoil in pits and beds intended for plant root balls, to a minimum thickness of 6 inches.
- C. Final grades: 1. Minor modifications to grade may be required to establish
- the final grade. 2. Finish grading will insure proper drainage of the site as determined by the Landscape Architect. Surface drainage
- will be away from all building pads. 3. Grade all areas so that the final grades are one (1") below adjacent paved areas, sidewalks, valve boxes, edging, concrete headers, clean-outs, drains, manholes, etc., in lawn areas and in bed areas.
- 4. Eliminate all erosion scars prior to mulching and commencing maintenance period. Dispose of any unacceptable soil or debris offsite. Excess soil
- may be spread on site. 3.4 Pre-plant weed Control:
- A. Eliminate all existing Bermuda grass in lawn areas by spraying with a non-selective systemic contact herbicide. Follow
- manufacturer's directions for applications. Clear and remove existing weeds by grubbing weeds over the
- entire area to be planted. Prior to planting install pre-emergent per manufacturer's recommendations
- 3.5 Tree planting: Protect all areas from excessive compaction when trucking plants
- or other material to the planting site. Till area two to three (2-3) times the size of the rootball of
- tree to be planted to a depth of twelve (12") inches. Excavated pits will: Have vertical sides with roughened surfaces Be twice the diameter of the rootball
- Be the same depth of the rootball, such that the top of the rootball is level with finish grade Do not bury root flares.
- Face trees with fullest growth to most visible direction. Trees will be backfilled with:
- 1. Two (3) parts native topsoil One (1) part compost
- 3. One (1 lb.) pound of fertilizer per one (1 c.y.) cubic yard
- Agriform tablets (see manufacturer's specifications for number of tablets per tree)
- 4-way landscape mix 2. One (1 lb.) pound of fertilizer per one (1 c.y.) cubic yard
- 3. Agriform tablets (see manufacturer's specifications for number of tablets per tree) Trees which settle deeper than the surrounding grade will be raised to the correct level. Do not bury root flares. Additional
- backfill will be added as necessary. If B&B is specified, remove any polyethylene rope from rootballs and trunks. Bend 1/3 of wire down away from trunk and rootball. Tamp soil as backfilling occurs to minimize settling of soil.
- After backfilling, construct an earthen basin around each plant. Each basin will be four (4") inches deep. Basins may be constructed of existing soil, amended backfill materials, or mulch. Install a two (2") inch thick, four (4') foot diameter of mulch at each tree. Mulch will be set back six (6") from root flare.

injured twigs and branches. N. Install tree watering bag. See section 3.7 Miscellaneous Materials.

3.6 Bed planting: A. Add soil amendments to existing soil/topsoil as needed for bed preparation. The final soil mix will be: 1. Two (2") inches of compost and one (1 lb.) pound of

Pruning will be limited to the minimum necessary to remove

- fertilizer per one (1 c.y.) cubic yard of mix. Install Agriform tablets per manufacturer's recommendations. 2. 4—way landscape mix and one (1 lb.) pound of fertilizer
- per one (1 c.y.) cubic yard of mix. Install Agriform tablets per manufacturer's recommendations. Shrubs, perennials and groundcovers will be planted in straight rows and evenly spaced, unless otherwise noted, and at intervals as called out on the drawings. Triangular spacing will be used
- unless otherwise noted on the drawings. C. Install a two (2") inch layer of mulch in plant areas, unless otherwise noted on drawings. Water plants by hose after planting until the entire area is
- soaked to the full depth of each hole. Exercise care at all times to protect the plants after planting. Any damage to plants by trampling or other operations will be

3.7 Installing lawn: A. Fertilizing 1. Apply fertilizer at the rate specified by manufacturer, based on recommendation from soil analysis.

Apply fertilizer after smooth raking of topsoil, and no more

- than 48 hours before laying sod. Thoroughly mix into upper two (2") of topsoil. 4. Lightly water soil to aid the dissipation of fertilizer.
- Hydromulching: Apply seeded slurry with a hydraulic seeder at a rate of two (2 lbs.) per 1,000 sq. ft. evenly in two intersecting directions with following mixture:
 - a. Mixture 1 (Standard Mix): b. 45 lbs./1,000 sq. ft. mulching agent c. 20 lbs./1,000 sq. ft. water soluble fertilizer

d. Mixture 2 (for Slopes over 6:1 [17%] and Problem

e. 50 lbs./1,000 sq. ft. mulching agent 20 lbs./1,000 sq. ft. water soluble fertilizer 1.5 lbs./1,000 sq. ft. glue agent 2. Do not hydroseed area in excess of that which can be

mulched on same day.

thickness of one-eighth (1/8") inch. Stay clear of shrubs and trees. 4. Apply water with a fine spray immediately after each area has been seeded. Saturate top four (4") inches of soil.

Immediately following hydromulching, apply mulch to a

- Water lightly and frequently to prevent top of soil from Once seeds have begun to sprout, reduce watering
- 6. Control weed growth. Apply herbicides in accordance with manufacturer's instructions. Remedy damage resulting from improper use of herbicides.

- Immediately reseed areas which show bare spots. Winter rye grass installation will be considered a temporary grass for applications after September 31 and before March 15. Should rye grass be installed, the contractor will return to site after March 15 to apply seed as specified.
- C. Laying Sod Moisten prepared surface immediately prior to laying sod. Lay sod immediately after delivery to site; within 24 hours
- after harvesting to prevent deterioration. 3. Lay sod tight with no open joints visible, and no overlapping; stagger end joints twelve (12") inches
- minimum. Do not stretch or overlap sod pieces. a. Fill gaps between sod squares with top dressing 4. Lay smooth. Align with adjoining grass areas. New finish
- grade and existing grade will be flush. 5. Place top elevation of sod mat one (1") inch below adjoining edging, paving, or curbs.
- a. Slopes 3:1 and greater will received solid sod per specifications.
- Lay sod perpendicular to slope and swales and secure ever row with wooden pegs at maximum two (2') feet on center. Drive pegs flush with soil portion
- inches per foot, or where indicated, place reinforcing mat over topsoil. Securely anchor in place with wood pegs sunk firmly into the ground.

c. Prior to placing sod on slopes exceeding eight (8")

- Water sodded areas immediately after installation. Saturate sod to 4 inches of soil. After sod and soil have dried, roll sodded areas to ensure good bond between sod and soil and to remove minor depressions and irregularities. Roll sodded areas with roller not exceeding 100-150 lbs. per linear foot of roller.
- Should construction last longer than twenty (20) days beyond specified finish date with any area of lawn in disrepair or in an unacceptable state to Landscape Architect or owner, Landscape Contractor will install solid sod in sod or seed areas to complete project with no additional cost to Owner.

Leave four (4') foot diameter ring around each tree, whether newly planted or existing, free of turf material. See section 3.5 Tree Planting.

Shadow Rock: Size 1"-2". Install filter fabric.

- 3.8 Miscellaneous Materials A. Steel edging: install per manufacturer's recommendation where
- indicated on drawings. Decomposed Granite Gravel: Install filter fabric. Install steel edger where gravel abuts lawn or bed areas. 3" gravel depth. Lay gravel in 2" lifts. Roll of tamp in place. Texas Blend River Rock: Size 2"-6". Install filter fabric.
- Tree staking: Install three (3) stakes per tree. Install tie straps forty-fifty (40-50%) percent the height of the tree. Tighten straps to hold trees firmly.

Tree root anchors: Install per manufacturer's recommendation.

- G. Tree guards: Install tree guards per manufacturer's recommendation. Join two or more guards as necessary for larger H. Pruning: At no time will new trees or plant materials be pruned, trimmed or topped prior to delivery. Any alteration of their shape
- will be conducted only with the approval of the Landscape Tree watering bags: Watering bags will be used when indicated on drawings, or when trees are planted prior to irrigation is

complete. Install watering bags per manufacturer's

recommendation.

- 3.9 Areas Disturbed by Construction A. Recondition areas disturbed by construction operations including, but not limited to, graded areas, laydown areas, construction trailers and movement of vehicles.
- B. Till all compacted areas to twelve (12") inches depth. Rake smooth and free of any rock or other deleterious materials. Apply sod or seed as specified on the drawings. Install temporary irrigation as required to establish these areas. C. Slopes 3:1 and greater will receive solid sod per specifications.
- 3.10 Maintenance of Site (While Under Construction or Until Final Acceptance) A. Maintain all plant materials and trees by watering, cultivating, weeding, spraying chemicals, cleaning and replacing as necessary to keep landscape in a vigorous, healthy condition.

This will apply to areas on site whether or not identified on the

or new irrigation system is operational. Notify the Owner and Landscape Architect for any deficiencies in the irrigation system. Failure to do so does not relieve the Contractor from replacing

B. Contractor is responsible for maintenance whether or not existing

- plant materials that have died. Water plant materials necessary to keep top two (2") inches of soil moist, or as necessary to encourage growth. Remove weeds and foreign grass from bed and lawn areas weekly. Herbicides may be used when required. Rake bed areas as
- Mow and edge newly planted lawns as necessary to maintain two (2") height. F. It is the responsibility of the Contractor to ensure plant material

construction. This includes, but is not limited to, picking up and

is in vigorous, healthy condition. Apply fertilizers, herbicides,

pesticides, and fungicides as necessary per manufacturer

required. Work will not be accepted with a presence of weeds in

requirements and state and local codes as necessary to encourage growth and to control pest, insect, or fungal problems.

A. Contractor will maintain a clean and neat site throughout

disposing trash daily. Do not allow trash or other debris to be scattered by wind or rain. After all planting operations have been completed, remove all trash, excess soil, empty plant containers and other debris from the property. All scars, ruts or other marks in the ground caused by this work will be repaired and the ground left in a neat and

C. The Contractor will leave the site area broom—clean and wash

down all paved areas within the contract area, leaving the

orderly condition throughout the site.

Pre-job conference

premises in a clean condition. All walks will be left in clean and safe condition.

A. The Contractor will be responsible for notifying the Landscape

Architect in advance for the following site visits:

- Plant material review Plant layout review Soil preparation and planting operations
- Final walk-through B. No site visits will commence without all items noted in previous Observation Reports either completed or remedied.

END OF SECTION

RIELLA D. MEADOW 141035

NOTE Ś S MONTES

PROJECT INFORMATION ROJECT MANAGER: ESIGNED BY: RAWN RY: 23-00436 ORIGINAL DATE: 07/31/2024

0 C S ORI

ENER/ (7) RKA

PROJECT NUMBER:

ATTACHMENT N

INSPECTION, MAINTENANCE, REPAIR AND RETROFIT PLAN

Jellyfish® Filter

Inspection and Maintenance Overview

The primary purpose of the Jellyfish® Filter is to capture and remove pollutants from stormwater runoff. As with any filtration system, these pollutants must be removed to maintain the filter's maximum treatment performance. Regular inspection and maintenance are required to ensure proper functioning of the system. Maintenance frequencies and requirements are site specific and vary depending on pollutant loading. Additional maintenance activities may be required in the event of non-storm event runoff, such as base-flow or seasonal flow, an upstream chemical spill or due to excessive sediment loading from site erosion or extreme runoff events. It is a good practice to inspect the system after major storm events.

Inspection activities are typically conducted from surface observations and include:

- Observe if standing water is present
- Observe if there is any physical damage to the deck or cartridge lids
- Observe the amount of debris in the Maintenance Access Wall (MAW) or inlet bay for vault systems

Maintenance activities include:

- Removal of oil, floatable trash and debris
- Removal of collected sediments y Rinsing and re-installing the filter cartridges
- Replace filter cartridge tentacles, as needed

Inspection Timing

Inspection of the Jellyfish® Filter is key in determining the maintenance requirements for, and to develop a history of, the site's pollutant loading characteristics. In general, inspections should be performed at the times indicated below; or per the approved project stormwater quality documents (if applicable), whichever is more frequent.

1. A minimum of quarterly inspections during the first year of operation to assess the sediment and floatable pollutant accumulation, and to ensure proper functioning of the system.



- 2. Inspection frequency in subsequent years is based on the inspection and maintenance plan developed in the first year of operation. Minimum frequency should be once per year.
- 3. Inspection is recommended after each major storm event.
- 4. Inspection is required immediately after an upstream oil, fuel or other chemical spill.

Inspection Procedure

The following procedure is recommended when performing inspections:

- 1. Provide traffic control measures as necessary.
- 2. Inspect the MAW or inlet bay for floatable pollutants such as trash, debris, and oil sheen.
- 3. Measure oil and sediment depth in several locations, by lowering a sediment probe until contact is made with the floor of the structure. Record sediment depth, and presences of any oil layers.
- 4. Inspect cartridge lids. Missing or damaged cartridge lids to be replaced.
- 5. Inspect the MAW (where appropriate), cartridge deck and receptacles, and backwash pool weir, for damaged or broken components.

Dry Weather Inspections

- Inspect the cartridge deck for standing water, and/or sediment on the deck.
- No standing water under normal operating conditions.
- Standing water inside the backwash pool, but not outside the backwash pool indicates, that the filter cartridges need to be rinsed.

Wet Weather Inspections

- Observe the rate and movement of water in the unit. Note the depth of water above deck elevation within the MAW or inlet bay.
- Less than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges (i.e. cartridges located outside the backwash pool).
- Greater than 6 inches, flow should be exiting the cartridge lids of each of the draindown cartridges and each of the hi-flo cartridges (i.e. cartridges located inside the backwash pool), and water should be overflowing the backwash pool weir.
- 18 inches or greater and relatively little flow is exiting the cartridge lids and outlet pipe, this condition indicates that the filter cartridges need to be rinsed.



Maintenance Requirements

Required maintenance for the Jellyfish® Filter is based upon results of the most recent inspection, historical maintenance records, or the site specific water quality management plan; whichever is more frequent. In general, maintenance requires some combination of the following:

- 1. Sediment removal for depths reaching 12 inches or greater, or within 3 years of the most recent sediment cleaning, whichever occurs sooner.
- 2. Floatable trash, debris, and oil removal.
- 3. Deck cleaned and free from sediment.
- 4. Filter cartridges rinsed and re-installed as required by the most recent inspection results, or within 12 months of the most recent filter rinsing, whichever occurs sooner.
- 5. Replace tentacles if rinsing does not restore adequate hydraulic capacity, remove accumulated sediment, or if damaged or missing. It is recommended that tentacles should remain in service no longer than 5 years before replacement.
- 6. Damaged or missing cartridge deck components must be repaired or replaced as indicated by results of the most recent inspection.
- 7. The unit must be cleaned out and filter cartridges inspected immediately after an upstream oil, fuel, or chemical spill. Filter cartridge tentacles should be replaced if damaged or compromised by the spill.

Maintenance Procedure

The following procedures are recommended when maintaining the Jellyfish® Filter:

- 1. Provide traffic control measures as necessary.
- 2. Open all covers and hatches. Use ventilation equipment as required, according to confined space entry procedures. Caution: Dropping objects onto the cartridge deck may cause damage.
- 3. Perform Inspection Procedure prior to maintenance activity.
- 4. To access the cartridge deck for filter cartridge service, descend into the structure and step directly onto the deck. Caution: Do not step onto the maintenance access wall (MAW) or backwash pool weir, as damage may result. Note that the cartridge deck may be slippery.
- 5. Maximum weight of maintenance crew and equipment on the cartridge deck not to exceed 450 lbs.



Filter Cartridge Removal

- 1. Remove a cartridge lid.
- 2. Remove cartridges from the deck using the lifting loops in the cartridge head plate. Rope or a lifting device (available from Contech) should be used. Caution: Should a snag occur, do not force the cartridge upward as damage to the tentacles may result. Wet cartridges typically weigh between 100 and 125 lbs.
- 3. Replace and secure the cartridge lid on the exposed empty receptacle as a safety precaution. Contech does not recommend exposing more than one empty cartridge receptacle at a time.

Filter Cartridge Rinsing

- 1. Remove all 11 tentacles from the cartridge head plate. Take care not to lose or damage the O-ring seal as well as the plastic threaded nut and connector.
- 2. Position tentacles in a container (or over the MAW), with the threaded connector (open end) facing down, so rinse water is flushed through the membrane and captured in the container.
- 3. Using the Jellyfish® rinse tool (available from Contech) or a low-pressure garden hose sprayer, direct water spray onto the tentacle membrane, sweeping from top to bottom along the length of the tentacle. Rinse until all sediment is removed from the membrane. Caution: Do not use a high pressure sprayer or focused stream of water on the membrane. Excessive water pressure may damage the membrane.
- 4. Collected rinse water is typically removed by vacuum hose.
- 5. Reassemble cartridges as detailed later in this document. Reuse O-rings and nuts, ensuring proper placement on each tentacle.

Sediment and Floatbles Extraction

- 1. Perform vacuum cleaning of the Jellyfish® Filter only after filter cartridges have been removed from the system. Access the lower chamber for vacuum cleaning only through the maintenance access wall (MAW) opening. Be careful not to damage the flexible plastic separator skirt that is attached to the underside of the deck on manhole systems. Do not lower the vacuum wand through a cartridge receptacle, as damage to the receptacle will result.
- 2. Vacuum floatable trash, debris, and oil, from the MAW opening or inlet bay. Alternatively, floatable solids may be removed by a net or skimmer.



- Pressure wash cartridge deck and receptacles to remove all sediment and debris.
 Sediment should be rinsed into the sump area. Take care not to flush rinse water into the outlet pipe.
- 4. Remove water from the sump area. Vacuum or pump equipment should only be introduced through the MAW or inlet bay.
- 5. Remove the sediment from the bottom of the unit through the MAW or inlet bay opening.
- 6. For larger diameter Jellyfish® Filter manholes (≥8-ft) and some vaults complete sediment removal may be facilitated by removing a cartridge lid from an empty receptacle and inserting a jetting wand (not a vacuum wand) through the receptacle. Use the sprayer to rinse loosened sediment toward the vacuum hose in the MAW opening, being careful not to damage the receptacle.

Filter Cartridge Reinstallation and Replacement

- 1. Cartridges should be installed after the deck has been cleaned. It is important that the receptacle surfaces be free from grit and debris.
- 2. Remove cartridge lid from deck and carefully lower the filter cartridge into the receptacle until head plate gasket is seated squarely in receptacle. Caution: Do not force the cartridge downward; damage may occur.
- 3. Replace the cartridge lid and check to see that both male threads are properly seated before rotating approximately 1/3 of a full rotation until firmly seated. Use of an approved rim gasket lubricant may facilitate installation. See next page for additional details.
- 4. If rinsing is ineffective in removing sediment from the tentacles, or if tentacles are damaged, provisions must be made to replace the spent or damaged tentacles with new tentacles. Contact Contech to order replacement tentacles.

Chemical Spills

Caution: If a chemical spill has been captured, do not attempt maintenance. Immediately contact the local hazard response agency and contact Contech.



Material Disposal

The accumulated sediment found in stormwater treatment and conveyance systems must be handled and disposed of in accordance with regulatory protocols. It is possible for sediments to contain measurable concentrations of heavy metals and organic chemicals (such as pesticides and petroleum products). Areas with the greatest potential for high pollutant loading include industrial areas and heavily traveled roads. Sediments and water must be disposed of in accordance with all applicable waste disposal regulations. When scheduling maintenance, consideration must be made for the disposal of solid and liquid wastes. This typically requires coordination with a local landfill for solid waste disposal. For liquid waste disposal a number of options are available including a municipal vacuum truck decant facility, local waste water treatment plant or on-site treatment and discharge.



Jellyfish Filter Inspection and Maintenance Log

Owner:			Jellyfi	Jellyfish Model No.:				
Location:							_	
Land Use:	Commercial: Industrial:			Service Stat				
	Road/Highway:	Road/Highway: Airport:		Residential:		Parking Lot:		
					Ι			
Date/Time:								
Inspector:								
Maintenance	Contractor:							
Visible Oil Pre	esent: (Y/N)							
Oil Quantity R	Removed							
Floatable Deb	oris Present: (Y/N)							
Floatable Deb	oris removed: (Y/N)							
Water Depth	in Backwash Pool							
Cartridges ext	ternally rinsed/re-commission	ed: (Y/N)						
New tentacles	s put on Cartridges: (Y/N)							
Sediment Dep	oth Measured: (Y/N)							
Sediment Dep	oth (inches or mm):							
Sediment Ren	noved: (Y/N)							
Cartridge Lids	s intact: (Y/N)							
Observed Dan	mage:							
Comments:								

Contech CMP Detention Inspection and Maintenance Guide

Underground stormwater detention and infiltration systems must be inspected and maintained at regular intervals for purposes of performance and longevity.

Inspection

Inspection is the key to effective maintenance of CMP detention systems and is easily performed. Contech recommends ongoing, annual inspections. Sites with high trash load or small outlet control orifices may need more frequent inspections. The rate at which the systems collect pollutants will depend more on-site specific activities rather than the size or configuration of the system.

Inspections should be performed more often in equipment washdown areas, in climates where sanding and/or salting operations take place, and in other various instances in which one would expect higher accumulations of sediment or abrasive/corrosive conditions. A record of each inspection is to be maintained for the life of the system.

Maintenance

CMP detention systems should be cleaned when an inspection reveals accumulated sediment or trash is clogging the discharge orifice. Accumulated sediment and trash can typically be evacuated through the manhole over the outlet orifice. If maintenance is no performed as recommended, sediment and trash may accumulate in front of the outlet orifice. Manhole covers should be securely seated following cleaning activities. Contech suggests that all systems be designed with an access/inspection manhole situated at or near the inlet and the outlet orifice. Should it be necessary to get inside the system to perform maintenance activities, all appropriate precautions regarding confined space entry and OSHA regulations should be followed.

Annual inspections are best practice for all underground systems. During this inspection if evidence of salting/de-icing agents is observed within the system, it is best practice for the system to be rinsed, including above the spring line soon after the spring thaw as part of the maintenance program for the system.

Maintaining an underground detention or infiltration system is easiest when there is no flow entering the system. For this reason, it is a good idea to schedule the cleanout during dray weather.



The foregoing inspection and maintenance efforts help ensure underground pipe systems used for stormwater storage continue to function as intended by identifying recommended regular inspection and maintenance practices. Inspection and maintenance related to the structural integrity of the pipe or the soundness of pipe joint connections is beyond the scope of this guide.

Ravindra Maddi	
Arka Leander Investments LLC	7/26/2024
OWNER	DATE
OWNER'S AGENT	 DATE



ATTACHMENT O

PILOT-SCALE FIELD TESTING PLAN

The proposed site will be using TCEQ approved water quality product, specifically the Jelly Fish Inlet designed by Contech Engineering Solutions.



ATTACHMENT P

MEASURES FOR MINIMIZING SURFACE STREAM CONTAMINATION

Erosion control measures and construction sequencing have been implemented to minimize surface stream contamination. These measures include a silt fence along the proposed site's border and the existing drainage channel on its eastern and southern boundaries, inlet protection, construction entrances and exits, a concrete washout pit, and an equipment staging area.



Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Ager	nt: <u>Ravindra Maddi</u>	
Date: <u>7/26/</u> 2024	0	
Signature of Customer/Agent	Kaundra	Madd
Regulated Entity Name: Arka	 Leander Investments, LL	.C

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1.	Fuels for construction equipment and hazardous substances which will be used during construction:
	The following fuels and/or hazardous substances will be stored on the site:
	These fuels and/or hazardous substances will be stored in:
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
	$igthered{igwedge}$ Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
S	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6.	Name the receiving water(s) at or near the site which will be disturbed or which will


Temporary Best Management Practices (TBMPs)

receive discharges from disturbed areas of the project: Brushy Creek

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
	A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
	There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not
	attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
	There are no areas greater than 10 acres within a common drainage area that will be
	disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.



Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

Attachment A

1.4.16 Spill Prevention and Control

The objective of this section is to describe measures to prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees.

The following steps will help reduce the stormwater impacts of leaks and spills:

Education

- (1) Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
- (2) Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- (3) Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- (4) Establish a continuing education program to indoctrinate new employees.
- (5) Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

- (1) To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- (2) Store hazardous materials and wastes in covered containers and protect from vandalism.
- (3) Place a stockpile of spill cleanup materials where it will be readily accessible.
- (4) Train employees in spill prevention and cleanup.
- (5) Designate responsible individuals to oversee and enforce control measures.
- (6) Spills should be covered and protected from stormwater runon during rainfall to the extent that it doesn't compromise clean up activities.
- (7) Do not bury or wash spills with water.

- (8) Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- (9) Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- (10) Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- (11) Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- (12) Keep waste storage areas clean, well organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

Cleanup

- (1) Clean up leaks and spills immediately.
- (2) Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- (3) Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- (1) Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- (2) Use absorbent materials on small spills rather than hosing down or burying the spill.
- (3) Absorbent materials should be promptly removed and disposed of properly.
- (4) Follow the practice below for a minor spill:
- (5) Contain the spread of the spill.
- (6) Recover spilled materials.
- (7) Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- (1) Contain spread of the spill.
- (2) Notify the project foreman immediately.
- (3) If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- (4) If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- (5) If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- (1) Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- (2) For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- (3) Notification should first be made by telephone and followed up with a written report.
- (4) The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

More information on spill rules and appropriate responses is available on the TCEQ website at: http://www.tnrcc.state.tx.us/enforcement/emergency response.html

Vehicle and Equipment Maintenance

- (1) If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- (2) Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- (3) Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- (4) Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- (5) Place drip pans or absorbent materials under paving equipment when not in use.
- (6) Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
- (7) Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- (8) Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
- (9) Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

Vehicle and Equipment Fueling

- (1) If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- (2) Discourage "topping off" of fuel tanks.
- (3) Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.

ATTACHMENT B

POTENTIAL SOURCES OF CONTAMINATION

During construction of this site, it is possible that there will be oil/grease and silt accumulation on the project site due to the equipment used to construct the roadways, utilities and residential lots. This may include fluid leaks from construction vehicles, hydrocarbons associated with asphalt paving, and washout from concrete trucks. Construction trash and/or debris not properly disposed of in appropriate containers are a potential source of contamination. The grading of rock and/or soil on the project site will create silt on the project site. The use of silt fences and construction exits will control the amount of silt and/or rock leaving the site.

Other potential sources of contamination include portable toilet spills or sewer contamination at the proposed sewer tie-ins. A soil berm would be constructed around the spill site and the affected area marked for further investigation and remediation.



ATTACHMENT C

SEQUENCE OF MAJOR ACTIVITIES

The sequence of major activities for construction with the approximate total disturbed area is as follows:

- Installation of Temporary Best Management Practices on the Project Site (1.82 Acres)
- Grading and Basin Construction (1.82 Acres)
- Building Construction (0.28 Acres)
- Establish Vegetation and Cleanup (0.74 Acres)
- Remove Temporary BMPs (1.82 Acres)



ATTACHMENT D

TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

The temporary Best Management Practices (BMP's) shall be installed as the first construction activity of the unit and will remain in place until all construction activities are complete and 70% of the vegetative cover has been established for that unit. The unit will have a designated construction exit, a silt fence along the down gradient side of the unit, inlet protection at storm drain inlets, and tree protection for the undisturbed trees where applicable. The existing native grasses will be left undisturbed in areas not under construction. Silt fence will be placed down gradient of all disturbed areas. The temporary BMP's shall be installed according to details on the Storm Water Pollution Prevention Plan detail sheet. The silt fences will be anchored six (6) inches into the soil and shall be monitored weekly for any failures of the silt fence or problems associated with silt build up.

- a. There is no surface water, groundwater or storm water that originates upgradient from the site and flows across the site, silt fencing will be placed along the south and east portion of the site.
- b. To prevent pollution of surface water or groundwater that originates onsite or flows offsite, including pollution caused by contaminated storm water runoff from the site, silt fencing will be placed along the down gradient sides of the site. A construction exit and concrete washout pit will also be installed at the entrance to the unit and a storage and refueling area will be designated on the site for each unit.
- c. To prevent pollutants from entering surface streams, sensitive features, or the aquifer, the silt fence and rock berms mentioned in item (b) above will be installed. If sensitive features are identified during trenching activities, all regulated activities near the sensitive feature must be suspended immediately. The owner must contact the TCEQ San Antonio Regional Office in writing within two working days of the discovery. The applicant must submit a plan for ensuring the structural integrity of the sewer line or for modifying the proposed collection system alignment around the feature. The regulated activities near the sensitive feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the sensitive feature and the Edwards Aquifer from any potentially adverse impacts to water quality while maintaining the structural integrity of the line.
- d. To maintain flow to naturally occurring sensitive features identified in the geologic assessment, inspections, or during construction, silt fencing or sand bag berms will be installed. If a feature must be sealed, processes must comply with Section 5.2 of the TGM RG-348 and Section 2.2 of the RG-348A.




ATTACHMENT F

STRUCTURAL PRACTICES

Silt fences will be used on site to trap sediments and pollutants from leaving the areas of construction. A construction exit will be located at the entrance to the site to prevent mud and sediment from collecting on public roads. Inlet protection will be added to each constructed grate and curb inlet to filter out pollutants from entering the water quality pond and/or watershed. A concrete washout pit will be established to reduce contamination of pollutants from concrete waste and prevent pollutant discharge to storm water runoff.





ATTACHMENT I

STORM WATER POLLUTION PREVENTION PLAN

INSPECTION AND MAINTENANCE REPORT	
CHANGES REQUIRED TO THE POLLUTION PREVENTION PLAN:	
REASONS FOR CHANGES:	
INSPECTOR'S SIGNATURE: DATE:	



ATTACHMENT J

SCHEDULED INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporary or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

Stabilization practices used on this site may include, but are not limited to, establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, seeding, vegetative buffer strips, protection of trees, protection of mature vegetation and other appropriate measures.

Infrastructure construction activities on this site include roadway excavation, utility installation, drainage construction, preliminary site grading, site cleanup, and permanent stabilization, final site grading.



Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

	Ravindra Maddi	
	Print Name	
	Owner	
	Title - Owner/President/Other	
of	Arka Leander Investment, LLC Corporation/Partnership/Entity Name	
have authorized	Ariella Meadows Print Name of Agent/Engineer	
of	ESP Associates, INC Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Raundya M Applicant's Signature	add 7/29/ Date	2024
THE STATE OF TUXES		
County of Tarrant §		
to me to be the person whose nan me that (s)he executed same for th	ne is subscribed to the forego ne purpose and consideration t	ippeared \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
GIVEN under my hand and seal of	office on this $\frac{29}{2}$ day of $\frac{30}{2}$	W 2034
	Chrish Prost NOTARY PUBLIC	
	Christon Prestor Typed or Printed Name of N	lotary
	MY COMMISSION EXPIRES	s: 11/29/24

Christin Preston My Commission Expires 11/29/2024 ID No 12203867

Application Fee Form

Texas Commission on Environmental Quality			
Name of Proposed Regulated Enti	ty: <u>Akra Leander Invest</u>	ments, LLC	
Regulated Entity Location: 2309 P	almetto Way, Southlak	e, Texas	
Name of Customer: Akra Leander	Investments, LLC		
Contact Person: Ravindra Maddi	Phor	ne:	
Customer Reference Number (if is	sued):CN		
Regulated Entity Reference Numb	er (if issued):RN		
Austin Regional Office (3373)			
Hays	Travis	\boxtimes w	illiamson
San Antonio Regional Office (336	2)		
Bexar	Medina	Пи	<i>r</i> alde
Comal	Kinney		raide
<u> </u>	<u> </u>		la ra da 🛖 a a a
Application fees must be paid by o	·		
Commission on Environmental Quantity form must be submitted with you	=		· ·
_		_	
Austin Regional Office	<u></u> S	an Antonio Regional C	Office
Mailed to: TCEQ - Cashier	∐ C	overnight Delivery to: 1	ГСЕQ - Cashier
Revenues Section	ction 12100 Park 35 Circle		
Mail Code 214	Building A, 3rd Floor		
P.O. Box 13088	Austin, TX 78753		
Austin, TX 78711-3088 (512)239-0357			
Site Location (Check All That Apply):			
☐ Recharge Zone ☐ Contributing Zone ☐ Transition Zone			tion Zone
Type of Plan	n	Size	Fee Due
Water Pollution Abatement Plan,	Contributing Zone		
Plan: One Single Family Residential Dwelling		Acres	\$
Water Pollution Abatement Plan, Contributing Zone			
Plan: Multiple Single Family Residential and Parks		Acres	\$
Water Pollution Abatement Plan, Contributing Zone			
Plan: Non-residential		1.698 Acres	\$ 4,000
Sewage Collection System		L.F.	\$
Lift Stations without sewer lines		Acres	\$
Underground or Aboveground Storage Tank Facility		Tanks	\$
Piping System(s)(only) Each \$			
Exception		Each	\$

Signature: Laundra Madd Date: 7/26/2024

Each \$

Extension of Time

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee				
Exception Request		\$500			

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)

New Pern	nit, Registra	tion or Authorization	(Core Data Form	should be s	submitte	ed with	the prog	ram application.)					
Renewal	(Core Data F	Form should be subm	itted with the ren	ewal form)			Other						
					ink to se I numbe legistry*	ers in					issued)		
4. General Cu		Customer formation				r Infor	mation	Updates (mm/dd/	· /yyyy)				
New Custor	mor	П	Update to Customer Information Change in Regulated E							archin			
=		ک ب Verifiable with the Te				ptroller			tity Own	ersnip			
(SOS) or Texa	s Comptro	bmitted here may ller of Public Acco e (If an individual, pr	unts (CPA).			d on w	nat is c	If new Customer,					
Arka Leander II	nvestments,	LLC											
7. TX SOS/CP	A Filing Nu	ımber	8. TX State Ta	State Tax ID (11 digits)			9. Federal Tax ID 10. DUN			Number (if			
0805169403			32091043359	32091043359				(9 digits)		applicable)			
11. Type of C	ustomer:	☐ Corpora	ation			[Individ	dual	Partne	Partnership: X General Limited			
Government: City County Federal Local State Other							Sole Proprietorship Other:						
12. Number	of Employe	ees				ı		13. Independe	ntly Ow	ned and Op	erated?		
□ 0-20 □ 2	21-100] 101-250	-500 🔲 501 a	nd higher				⊠ Yes	☐ No				
14. Custome	r Role (Prop	oosed or Actual) – as	it relates to the R	egulated Er	ntity liste	ed on tl	his form.	Please check one o	f the follo	owing			
⊠Owner ☐Occupation	al Licensee	Operator Responsible Pa		ier & Opera CP/BSA App				☐ Other:					
15. Mailing	2309 Paln	netto Way											
Address:	City	South Lake		State	ate TX		ZIP	76092		ZIP + 4	1457		
	J.,										1.0.		
16. Country N	Mailing Inf	ormation (if outside	e USA)			17. E	-Mail A	ddress (if applicabl	le)				
					ravindra.maddi@gmail.com								

TCEQ-10400 (11/22) Page 1 of 3

19. Extension or Code	20. Fax Number (if applicable)
	() -
	13. Extension of Code

New Regulated Entity	□ Undato to	Regulated Entity	v Namo	Update to	o Pogula	od Entit	v Inform	ntion			
M New Regulated Entity		Regulated Elltit	y ivaille		o neguia	eu Entit	y iiiioiiii	ation			
The Regulated Entity Nar as Inc, LP, or LLC).	ne submitte	d may be updo	ated, in o	rder to mee	et TCEQ	Core Do	ata Stan	dards (re	emoval of o	rganization	al endings such
22. Regulated Entity Nam	ne (Enter nam	e of the site whe	ere the reg	ulated action	is taking	place.)					
Akra Leander Investments, L	LC										
23. Street Address of the Regulated Entity:	2309 Palmetto Way										
(No PO Boxes)	City	Leander	Si	tate	TX	ZI	P	76092	2	ZIP + 4	1457
24. County	North Tarrant County										
If no Street Address is provided, fields 25-28 are required.											
25. Description to Physical Location:	Lot located east of the private access road of Glenn High School and San Gabrial Parkway										
26. Nearest City State Nearest ZIP Code											
Leander								TX		7864	
Latitude/Longitude are re used to supply coordinate	-	-	-				Standa	rds. (Ged	coding of th	he Physical	Address may be
27. Latitude (N) In Decim	al:	30.596143			28	3. Longi	tude (V	/) In Deci	imal:	97.87832	4
Degrees	Minutes		Seconds	i	D	Degrees M			Minutes		Seconds
30		35		46.1148			97		52		41.9664
29. Primary SIC Code (4 digits)		Secondary SIC igits)	C Code		31. Pri (5 or 6		AICS Co	de	32. Seco (5 or 6 dig	ondary NAIO	CS Code
8351	655	2			624410						
33. What is the Primary E	Business of t	his entity? ([Do not repe	eat the SIC or	NAICS d	escriptio	n.)		1		
Child Daycare Facility											
34. Mailing	2309 Palm	etto Way									
Address:				_	1			<u> </u>		I	
	City	South Lake		State	TX		ZIP	76092		ZIP + 4	1457
35. E-Mail Address:	ravi	ndra.maddi@gn	mail.com								
36. Telephone Number			37. Ex	tension or 0	Code		38. Fa	ax Numb	er (if applical	ble)	

TCEQ-10400 (11/22) Page 2 of 3

(972)971-8857

() -

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance. ☐ Dam Safety Districts Edwards Aquifer ☐ Emissions Inventory Air ☐ Industrial Hazardous Waste CZP ☐ New Source Municipal Solid Waste OSSF ☐ Petroleum Storage Tank ☐ PWS Review Air Sludge X Storm Water ☐ Title V Air Tires Used Oil ☐ Voluntary Cleanup ■ Wastewater ■ Wastewater Agriculture ■ Water Rights Other: **SECTION IV: Preparer Information** 40. Name: Ariella Meadows PE 41. Title: Project Manager 42. Telephone Number 43. Ext./Code 44. Fax Number 45. E-Mail Address (210)349-3271 ameadows@espassociates.com **SECTION V: Authorized Signature** 46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39. Company: Job Title: Arka Leander Investments, LLC Owner Name (In Print): Ravindra Maddi (972)971-8857 Phone: Signature: Date: 7/26/2024

TCEQ-10400 (11/22) Page 3 of 3