

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> Violet Crown Trailhead-Mile Zero				<b>2. Regulated Entity No.:</b>			
<b>3. Customer Name:</b> Hill Country Conservancy				<b>4. Customer No.:</b> CN603578816			
<b>5. Project Type:</b> (Please circle/check one)	New	Modification		Extension	<u>Exception</u>		
<b>6. Plan Type:</b> (Please circle/check one)	<u>WPAP</u> CZP	SCS	UST	AST	<u>EXP</u> EXT	Technical Clarification	Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	Residential	<u>Non-residential</u>			<b>8. Site (acres):</b>		2.6 Acres
<b>9. Application Fee:</b>	\$500	<b>10. Permanent BMP(s):</b>			Rain Garden for roadway treatment		
<b>11. SCS (Linear Ft.):</b>	N/A	<b>12. AST/UST (No. Tanks):</b>			N/A		
<b>13. County:</b>	Travis	<b>14. Watershed:</b>			Barton Creek		



# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input checked="" type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input checked="" type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Jessica Powers

Print Name of Customer/Authorized Agent

Jessica Powers

Digitally signed by Jessica Powers  
DN: cn=J. Powers, email=jpowers@tceq.com, cn=Jessica Powers  
Date: 2024.07.11 11:13:43-0500

7/11/2024

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# General Information Form

## Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

**To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.**

**Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.**

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Jessica Powers

Date: 7/11/2024

Signature of Customer/Agent:

Jessica Powers

Digitally signed by Jessica Powers  
DN: C=US,  
E=jpowers@dunaway.com,  
CN=Jessica Powers  
Date: 2024.07.11 11:15:53-05'00'

## Project Information

1. Regulated Entity Name: Violet Crown Trailhead-Mile Zero
2. County: Travis
3. Stream Basin: Barton Creek
4. Groundwater Conservation District (If applicable): Barton Creek
5. Edwards Aquifer Zone:  
☒ Recharge Zone  
☐ Transition Zone
6. Plan Type:  
☒ WPAP  
☐ SCS  
☐ Modification  
☐ AST  
☐ UST  
☒ Exception Request

7. Customer (Applicant):

Contact Person: Hill Country Conservancy  
Entity: Trail Conservator/applicant  
Mailing Address: 1601 S MoPac Expy Suite 150C  
City, State: Austin, TX Zip: 78746  
Telephone: 512-328-2481 FAX: \_\_\_\_\_  
Email Address: \_\_\_\_\_

8. Agent/Representative (If any):

Contact Person: Jessica Powers  
Entity: Agent  
Mailing Address: 5707 Southwest Pkwy. Bldg. 2 Ste. 250  
City, State: Austin, TX Zip: 78735  
Telephone: 512-399-5378 FAX: \_\_\_\_\_  
Email Address: jpowers@dunaway.com

9. Project Location:

- ☒ The project site is located inside the city limits of Austin  
☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.  
☐ The project site is not located within any city's limits or ETJ.

10. ☒ The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

William Barton Drive, Austin, Texas 78746 (At the southwest intersection of William Barton Drive and Columbus Drive)

11. ☒ **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12. ☒ **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- ☐ Project site boundaries.
  - ☐ USGS Quadrangle Name(s).
  - ☐ Boundaries of the Recharge Zone (and Transition Zone, if applicable).
  - ☐ Drainage path from the project site to the boundary of the Recharge Zone.

13. ☒ **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment. Acknowledged. GA is exempt. Refer to TCEQ Form 0585 for details.
- ☐ Survey staking will be completed by this date: \_\_\_\_\_

14. ☒ **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- ☒ Area of the site
- ☐ Offsite areas
- ☐ Impervious cover
- ☐ Permanent BMP(s)
- ☐ Proposed site use
- ☐ Site history
- ☐ Previous development
- ☐ Area(s) to be demolished

15. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site
- ☒ Existing paved and/or unpaved roads
- ☐ Undeveloped (Cleared)
- ☒ Undeveloped (Undisturbed/Uncleared)
- ☐ Other: \_\_\_\_\_

William Barton Drive within the Limits of Construction. The remainder is open space with low covering vegetation and trees. Refer to Attachment C at end of this form.

### ***Prohibited Activities***

16. ☒ I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. ☒ I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

## ***Administrative Information***

18. The fee for the plan(s) is based on:

- ☐ For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
- ☐ For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
- ☐ For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
- ☒ A request for an exception to any substantive portion of the regulations related to the protection of water quality GA is exempt. Refer to TCEQ Form 0585 for details.
- ☐ A request for an extension to a previously approved plan.

19. ☒ Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:

- ☐ TCEQ cashier
- ☒ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
- ☐ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

20. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21. ☒ No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.


Acknowledged.



## **ATTACHMENT A – ROAD MAP**

WILLIAM BARTON DR.  
AUSTIN TX 78746


LOCATION MAP



COA GRID: G22, MAPSCO PG: 584X


**ATTACHMENT B – USGS / EDWARDS  
RECHARGE ZONE MAP**

# Violet Crown Trail - TCEQ EA Map



7/2/2024, 11:00:16 AM

- Segments (Streams)
- Edwards Aquifer Boundary central line
- Edwards Aquifer Label
- Edwards Aquifer Boundary
- Groundwater Conservation Districts
- Barton Springs/Edwards Aquifer CD
- TX Counties
- 7.5 Minute Quad Grid
- TCEQ\_EDWARDS\_OFFICIAL\_MAPS



TCEQ, Austin Community College, City of Austin, Texas Parks & Wildlife, Esri, HERE, Garmin, INCREMENT P, Intermap, USGS, METI/NASA, EPA,

Web AppBuilder for ArcGIS

TCEQ | Austin Community College, City of Austin, Texas Parks & Wildlife, Esri, HERE, Garmin, INCREMENT P, Intermap, USGS, METI/NASA, EPA, USDA |

## **ATTACHMENT C – PROJECT DESCRIPTION**

The Site is approximately 2.57 acres. The Site is partially undeveloped and consists of an internal road, trees, and low covering vegetation. The Site is open space parkland.

The existing conditions of the surrounding adjacent offsite drainage areas are composed of Columbus Drive to the North, William Barton Drive to the East, and low covering vegetation, trees to the West and South. There is only 2.35 acres (drainage basin OS) of offsite stormwater that originates upgradient from the site. OS is partially developed with Columbus Drive, trees, and low covering vegetation. This stormwater sheet flows onto the Site. The Site is located in drainage basin V. Drainage area maps have been provided in this submittal package section identified as Permanent Stormwater Section-TCEQ-0600, attachment F.

The Site currently has an existing 480 linear feet gravel multi-use trail that is approximately 8 feet wide. Approximately 190 linear feet of William Barton Drive. The full width of the roadway in this section has a pavement width of 40 feet, of which 20 feet runs through the Site's LOC.

The total existing impervious cover of the 2.57 acre tract is 0.11 acres or 4 %.

Proposed improvements will include constructing approximately 620 linear feet of a 12-foot wide decomposed granite multi-use trail, approximately 200 linear feet of 5-foot wide decomposed granite multi-use trail, 2 outdoor facilities, 25 linear feet of 5-foot concrete multi-use trail, and reconstruction of 24 linear feet of 5-feet of concrete maintenance path. Both the decomposed granite and concrete multi-use trails will be constructed to Americans with Disabilities compliance. The existing multi-use trail will be demolished, and the width of William Barton Drive will be reduced from 40 feet down to 24 feet, inside the LOC. The reduction in width will be on the west side of the road.

The total proposed impervious cover is 0.02 acres or 1 %. This is a net decrease of 0.09 acres.

Permanent BMPs are as follows WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the Critical Water Quality Zone (CWQZ) and 100-Year floodplain, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs.

Stormwater detention is not required as the proposed improvements/ Site will be reducing the existing impervious cover from 4% down to 1%. Detention is also not required due to its proximity to Barton Creek and Lady Bird Lake watersheds.

Refer to the Drainage Area Maps, Water Quality plan sheets from the Site Plan Set. Refer to Attachment F- Construction Plans in TCEQ Form 600. The pond will return discharges to sheet flow, which will continue to sheet flow to Barton Creek. No construction activities will be in the creek area.



N/A Please refer to email from James Slone  
with TCEQ Edwards Aquifer Protection  
Program- dated June 10, 2024 attached at the  
end of this document.

# Geologic Assessment

## Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: \_\_\_\_\_

Telephone: \_\_\_\_\_

Date: \_\_\_\_\_

Fax: \_\_\_\_\_

Representing: \_\_\_\_\_ (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:

\_\_\_\_\_

Regulated Entity Name: \_\_\_\_\_

## Project Information

1. Date(s) Geologic Assessment was performed: \_\_\_\_\_

2. Type of Project:

☐ WPAP  
☐ SCS

☐ AST  
☐ UST

3. Location of Project:

☐ Recharge Zone  
☐ Transition Zone  
☐ Contributing Zone within the Transition Zone

4. ☐ **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. ☐ Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups\* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

**Table 1 - Soil Units, Infiltration Characteristics and Thickness**

Soil Name	Group*	Thickness(feet)

*\* Soil Group Definitions (Abbreviated)*

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6. ☐ **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7. ☐ **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
8. ☐ **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'
- Applicant's Site Plan Scale: 1" = \_\_\_\_\_'
- Site Geologic Map Scale: 1" = \_\_\_\_\_'
- Site Soils Map Scale (if more than 1 soil type): 1" = \_\_\_\_\_'
9. Method of collecting positional data:
- ☐ Global Positioning System (GPS) technology.
- ☐ Other method(s). Please describe method of data collection: \_\_\_\_\_
10. ☐ The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11. ☐ Surface geologic units are shown and labeled on the Site Geologic Map.

12. ☐ Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
- ☐ Geologic or manmade features were not discovered on the project site during the field investigation.
13. ☐ The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
- ☐ There are \_\_\_\_\_ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
- ☐ The wells are not in use and have been properly abandoned.
- ☐ The wells are not in use and will be properly abandoned.
- ☐ The wells are in use and comply with 16 TAC Chapter 76.
- ☐ There are no wells or test holes of any kind known to exist on the project site.

### ***Administrative Information***

15. ☐ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

**GEOLOGIC ASSESSMENT**  
**NOT APPLICABLE - PLEASE REFER TO EMAIL FROM**  
**JAMES SLONE, GEOSCIENTIST WITH TCEQ**  
**EDWARDS AQUIFER PROTECTION PROGRAM, DATED**  
**JUNE 10, 2024 ATTACHED BELOW.**

## Michael Mullone

---

**From:** James Slone <james.slone@tceq.texas.gov>  
**Sent:** Monday, June 10, 2024 9:17 AM  
**To:** Michael Mullone  
**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Michael,

I can give you the Exception the Geologic Assessment. Please note, if we find any features when we perform our site assessment, you may be required to conduct a Geologic Assessment. Retain this email for you records and provide it during plan submittal.

Have a good week,

Bo

James "Bo" Slone, P.G.  
Geoscientist  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality  
(512) 239-6994

---

**From:** Michael Mullone <MMullone@dunaway.com>  
**Sent:** Sunday, June 9, 2024 6:44 PM  
**To:** James Slone <james.slone@tceq.texas.gov>  
**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Bo,

Thanks for the below. In looking at the website for exception, are all of the below required? Especially on the Geological Assessment?

Thanks,



## Forms - Recharge and Transition Zone

The following forms are required when requesting an exception in the Recharge or Transition Zone.







### Application Cover Page

- Form TCEQ-20705 (  PDF,  Word)

### General Information

- Form TCEQ-0587 (  PDF,  Word)



### Geologic Assessment

- Form TCEQ-0585 (  PDF,  Word)
- Instructions to Geologists TCEQ-0585 (  PDF,  Word)
- Geologic Assessment Table TCEQ-0585 (  PDF,  Excel)



### Recharge and Transition Zone Exception Request

- Form TCEQ-0628 (  PDF,  Word)
- Application Checklist TCEQ-0628-Checklist (  PDF,  Word)

### Temporary Stormwater Section (if applicable)

- Form TCEQ-0602 (  PDF,  Word)

### Permanent Stormwater Section (if applicable)

- Form TCEQ-0600 (  PDF,  Word)

### Agent Authorization

- Form TCEQ-0599 (  PDF,  Word), if application submitted by agent

### Application Fee

- Form TCEQ-0574 (  PDF,  Word)
- Check payable to the "Texas Commission on Environmental Quality"

### Core Data Form

- Form TCEQ-10400 (  Word)
- Instructions TCEQ-10400-Instructions (  PDF)

## Michael Mullone

Discipline Lead II | Associate

Dunaway

T 512.306.8252 D 512-399-5373

---

**From:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>

**Sent:** Friday, June 7, 2024 3:02 PM

**To:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>

**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry



Michael,

You can submit this as an WPAP Exception which will require a smaller fee (\$500). Please retain this email for you records and provide it with your application to show you can submit as a WPAP Exception.

Have a great weekend,

Bo

James "Bo" Slone, P.G.

Geoscientist

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

(512) 239-6994

---

**From:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>

**Sent:** Friday, June 7, 2024 1:15 PM


**To:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>

**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Bo,

Thank you so much for getting back to me. Here is the requested information.

The Site is about 2.5 acers. It currently has an existing 480 linear feet gravel multi-use trail that is approximately 8 feet wide. It is bordered on the east by 190 linear feet by 40 feet wide pavement of Columbus Drive. Proposed improvements will include constructing approximately 620 linear feet of a 12-foot wide decomposed granite multi-use trail, 200 linear feet of 5-foot wide decomposed granite (DG) multi-use trail, 2 outdoor facilities, 25 linear feet of 5-foot concrete multi-use trail, and reconstruction of 24 linear feet of 5-feet of concrete maintenance path. The existing multi-use trail will be demolished, and the width of the Columbus Drive will be reduced from 40 feet down to 24 feet, inside the LOC. We are actually removing more impervious cover than what we are placing inside the LOC.



The COA still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone

(CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs.

I have attached some sheets for visual help.

**Michael Mullone, PE, CFM, CESSWI, CPESC**

Senior Project Engineer | Associate

Dunaway

**T** 512.306.8252 **D** 512-399-5373

---

**From:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>  
**Sent:** Friday, June 7, 2024 8:08 AM  
**To:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>  
**Subject:** [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Michael,

A WPAP is required in this part of Austin. If it was on the other side of the river, it would not be required. Depending on the size of the project, we might allow a WPAP Exception Plan submittal, rather than a standard WPAP, but an approval would still be required. Can you give me some details on the project of a draft site plan?  
Bo

James "Bo" Slone, P.G.  
Geoscientist  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality  
(512) 239-6994

---


**From:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>  
**Sent:** Thursday, June 6, 2024 2:10 PM  
**To:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>  
**Subject:** Violet Crown Trailhead WPAP Requirement Inquiry


Good afternoon Bo,

I work with Caleb Milligan at Dunaway and he mentioned you were a good resource to inquire about this. I have a Park and Trail project located in Zilker Park in Austin Texas. It is in the City of Austin City Limits, Barton Creek watershed, and in the Edwards aquifer recharge zone. I was curious if we have to submit a

WPAP for a project? The owner we told they may need one but I didn't think that TCEQ requires a WPAP if it is located within this part of Austin. See below. Can you let me know if we need to submit anything please?

Thanks,





**Michael Mullone, PE, CFM, CESSWI, CPESC**  
Senior Project Engineer | Associate



**T** 512.306.8252 **D** 512-399-5373  
[dunaway.com](http://dunaway.com)

# Recharge and Transition Zone Exception Request Form

Texas Commission on Environmental Quality

30 TAC §213.9 Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Recharge and Transition Zone Exception Request Form** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Jessica Powers

Date: 7/11/2024

Signature of Customer/Agent:

Jessica Powers   
Digitally signed by Jessica Powers  
DN: C=US, E=jpowers@dunaway.com,  
OU=Jessica Powers  
Date: 2024.07.11 11:17:57-05'00'

Regulated Entity Name: \_\_\_\_\_

## Exception Request

- ☒ **Attachment A - Nature of Exception.** A narrative description of the nature of each exception requested is attached. All provisions of 30 TAC §213 Subchapter A for which an exception is being requested have been identified in the description.
- ☒ **Attachment B - Documentation of Equivalent Water Quality Protection.** Documentation demonstrating equivalent water quality protection for the Edwards Aquifer is attached.


## Administrative Information

- ☐ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- ☒ The applicant understands that no exception will be granted for a prohibited activity in Chapter 213. **Acknowledged.**
- ☒ The applicant understands that prior approval under this section must be obtained from the executive director for the exception to be authorized. **Acknowledged.**

## ATTACHMENT A – NATURE OF EXCEPTION


Not Applicable - please refer to email from James Slone, Geoscientist with TCEQ Edwards aquifer protection program, dated June 10, 2024 attached below.

The Site is about 2.5 acers. It currently has an existing 480 linear feet gravel multi-use trail that is approximately 8 feet wide. It is bordered on the east by 190 linear feet by 40 feet wide pavement of William Barton Drive. Proposed improvements will include constructing approximately 620 linear feet of a 12-foot wide decomposed granite multi-use trail, 200 linear feet of 5-foot wide decomposed granite (DG) multi-use trail, 2 outdoor facilities, 25 linear feet of 5-foot concrete multi-use trail, and reconstruction of 24 linear feet of 5-feet of concrete maintenance path. The existing multi-use trail will be demolished, and the width of the William Barton Drive will be reduced from 40 feet down to 24 feet, inside the Limits of Construction (LOC). We are actually removing more impervious cover than what we are placing inside the LOC.



Impervious Cover Calculations	
Description	ft <sup>2</sup>
Existing Pavement and Concrete Sidewalk to be removed	-4852
Proposed Outdoor Facilities - Decked*	707
Proposed Concrete Sidewalk	284
Net Impervious Cover	-3861
* Area shown is 50% of Outdoor Facilities Impervious Cover since they are decked.	

**LEGEND**



VISION DESCRIPTION

The existing impervious cover for the 2.57 acre LOC/Site is 0.11 acres or 4%. Proposed impervious cover is 0.02 acres or 1%. The proposed improvements are allowed in the Critical Water Quality Zone (CWQZ) per the Environmental Criteria Manual (ECM), Section 1.5.3 Development Allowed in the CWQZ.

The City of Austin (COA) still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone (CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.



WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs.

## Michael Mullone

---

**From:** James Slone <james.slone@tceq.texas.gov>  
**Sent:** Monday, June 10, 2024 9:17 AM  
**To:** Michael Mullone  
**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Michael,

I can give you the Exception the Geologic Assessment. Please note, if we find any features when we perform our site assessment, you may be required to conduct a Geologic Assessment. Retain this email for you records and provide it during plan submittal.

Have a good week,

Bo

James "Bo" Slone, P.G.  
Geoscientist  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality  
(512) 239-6994

---

**From:** Michael Mullone <MMullone@dunaway.com>  
**Sent:** Sunday, June 9, 2024 6:44 PM  
**To:** James Slone <james.slone@tceq.texas.gov>  
**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Bo,

Thanks for the below. In looking at the website for exception, are all of the below required? Especially on the Geological Assessment?

Thanks,



## Forms - Recharge and Transition Zone

The following forms are required when requesting an exception in the Recharge or Transition Zone.







### Application Cover Page

- Form TCEQ-20705 (  PDF,  Word)

### General Information

- Form TCEQ-0587 (  PDF,  Word)



### Geologic Assessment

- Form TCEQ-0585 (  PDF,  Word)
- Instructions to Geologists TCEQ-0585 (  PDF,  Word)
- Geologic Assessment Table TCEQ-0585 (  PDF,  Excel)



### Recharge and Transition Zone Exception Request

- Form TCEQ-0628 (  PDF,  Word)
- Application Checklist TCEQ-0628-Checklist (  PDF,  Word)

### Temporary Stormwater Section (if applicable)

- Form TCEQ-0602 (  PDF,  Word)

### Permanent Stormwater Section (if applicable)

- Form TCEQ-0600 (  PDF,  Word)

### Agent Authorization

- Form TCEQ-0599 (  PDF,  Word), if application submitted by agent

### Application Fee

- Form TCEQ-0574 (  PDF,  Word)
- Check payable to the "Texas Commission on Environmental Quality"

### Core Data Form

- Form TCEQ-10400 (  Word)
- Instructions TCEQ-10400-Instructions (  PDF)

**Michael Mullone**

Discipline Lead II | Associate

Dunaway

T 512.306.8252 D 512-399-5373

---

**From:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>

**Sent:** Friday, June 7, 2024 3:02 PM

**To:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>

**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Michael,

You can submit this as an WPAP Exception which will require a smaller fee (\$500). Please retain this email for your records and provide it with your application to show you can submit as a WPAP Exception.

Have a great weekend,

Bo

James "Bo" Slone, P.G.

Geoscientist

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

(512) 239-6994

---

**From:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>

**Sent:** Friday, June 7, 2024 1:15 PM


**To:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>

**Subject:** RE: [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Bo,

Thank you so much for getting back to me. Here is the requested information.

The Site is about 2.5 acers. It currently has an existing 480 linear feet gravel multi-use trail that is approximately 8 feet wide. It is bordered on the east by 190 linear feet by 40 feet wide pavement of Columbus Drive. Proposed improvements will include constructing approximately 620 linear feet of a 12-foot wide decomposed granite multi-use trail, 200 linear feet of 5-foot wide decomposed granite (DG) multi-use trail, 2 outdoor facilities, 25 linear feet of 5-foot concrete multi-use trail, and reconstruction of 24 linear feet of 5-feet of concrete maintenance path. The existing multi-use trail will be demolished, and the width of the Columbus Drive will be reduced from 40 feet down to 24 feet, inside the LOC. We are actually removing more impervious cover than what we are placing inside the LOC.



The COA still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone

(CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs.

I have attached some sheets for visual help.

**Michael Mullone, PE, CFM, CESSWI, CPESC**

Senior Project Engineer | Associate

Dunaway

**T** 512.306.8252 **D** 512-399-5373

---

**From:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>  
**Sent:** Friday, June 7, 2024 8:08 AM  
**To:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>  
**Subject:** [EXTERNAL]RE: Violet Crown Trailhead WPAP Requirement Inquiry

Michael,

A WPAP is required in this part of Austin. If it was on the other side of the river, it would not be required. Depending on the size of the project, we might allow a WPAP Exception Plan submittal, rather than a standard WPAP, but an approval would still be required. Can you give me some details on the project of a draft site plan?  
Bo

James "Bo" Slone, P.G.  
Geoscientist  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality  
(512) 239-6994

---


**From:** Michael Mullone <[MMullone@dunaway.com](mailto:MMullone@dunaway.com)>  
**Sent:** Thursday, June 6, 2024 2:10 PM  
**To:** James Slone <[james.slone@tceq.texas.gov](mailto:james.slone@tceq.texas.gov)>  
**Subject:** Violet Crown Trailhead WPAP Requirement Inquiry

Good afternoon Bo,


I work with Caleb Milligan at Dunaway and he mentioned you were a good resource to inquire about this. I have a Park and Trail project located in Zilker Park in Austin Texas. It is in the City of Austin City Limits, Barton Creek watershed, and in the Edwards aquifer recharge zone. I was curious if we have to submit a

WPAP for a project? The owner we told they may need one but I didn't think that TCEQ requires a WPAP if it is located within this part of Austin. See below. Can you let me know if we need to submit anything please?

Thanks,







**Michael Mullone, PE, CFM, CESSWI, CPESC**  
Senior Project Engineer | Associate



**T** 512.306.8252 **D** 512-399-5373  
[dunaway.com](http://dunaway.com)

## **ATTACHMENT B – DOCUMENTATION OF EQUIVALENT WATER QUALITY PROTECTION**

The City of Austin (COA) still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone (CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs.

Refer to Attachment F- Construction Plans in TCEQ Form 0600 and Attachment C – Project Description in Form TCEQ 0587.



# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Jessica Powers

Date: 7/11/2024

Signature of Customer/Agent:

Jessica Powers

Digitally signed by Jessica Powers  
DN: C=US, E=jpowers@dunaway.com,  
CN=Jessica Powers  
Date: 2024.07.11 11:19:34-05'00'

Regulated Entity Name: \_\_\_\_\_

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

N/A- no  
Fuels will  
be stored  
on-site

These fuels and/or hazardous substances will be stored in:

☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

N/A- no  
storage  
tanks on  
site

- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.

☒ Fuels and hazardous substances will not be stored on the site.

2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.

N/A- no  
storage  
tanks on  
site

3. ☐ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.

4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

☐ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.

6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Barton Creek

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☐ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☐ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☐ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.

☒ N/A

12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

## ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

- 20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## **ATTACHMENT A – SPILL RESPONSE ACTIONS**

All major equipment/vehicle fueling and maintenance will be performed off-site.

.All sediment spilled, dropped, washed or tracked onto public rights of way must be removed immediately by contractor.


All hazardous waste materials such as oil filters, petroleum products, paint, and equipment maintenance fluids will be stored in structurally sound and sealed shipping containers in a hazardous-materials storage area located within the limits of construction and segregated from other non-waste materials. Secondary containment will be provided for all materials in the hazardous materials storage area and will consist of commercially available spill pallets. Additionally, all hazardous materials will be disposed of in accordance with federal, state, and municipal regulations. Hazardous waste materials will not be disposed of into the onsite dumpsters. All personnel will be instructed, during training sessions, regarding proper procedures for hazardous waste disposal. Notices that state these procedures will be posted in the office trailer and the individual who manages day-to-day site operations will be responsible for seeing that these procedures are followed.

An erosion and sedimentation control (ESC) plan and a Stormwater Pollution Prevention Plan (SWPPP) will be used to minimize the impact of grading and construction activities.



# Stormwater Best Management Practice

## Spill Prevention and Control Measures



**Minimum Measure:** Construction Site Stormwater Runoff Control  
**Subcategory:** Good Housekeeping/Materials Management

### Description

Liquid and solid products may enter the environment when they leak or spill from containers during use or transfer. These materials may then directly enter nearby storm drains or receiving waters, or stormwater may carry them there (WES, 2008). Federal requirements for the construction and development industry require that any stormwater discharge permit for construction sites include requirements to “minimize the discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures” (40 CFR §450.21(d)(3)). Most state Construction General Permits (CGPs) and EPA’s CGP require that stormwater pollution prevention plans (SWPPPs) identify measures to prevent, contain, clean up and dispose of material leaks or spills. Managers of small municipal separate storm sewer systems (MS4) should develop, implement and enforce a program to reduce stormwater pollutants from any construction activity within the MS4 that results in a land disturbance of greater than or equal to one acre, as well as any construction activity that is part of a larger common plan of development or sale that would disturb one acre or more. Managers should share these procedures with construction personnel as part of the program and examine those procedures when doing inspections/reviews.

### Applicability

Spill prevention and control measures apply to construction sites that store or use materials such as pesticides, paints, cleaners, petroleum products, fertilizers, concrete wash, metals, solvents, soil stabilizers and binders, and contaminated groundwater. Construction staff should develop spill prevention and control measures for material storage areas, refueling stations (both mobile and stationary), material transfer locations, storm drain inlet and outlet locations, and waterways (WES, 2008). The spill prevention, control and countermeasure (SPCC) rule (40 CFR §112) covers every site with a total aboveground oil storage capacity greater than 1,320 gallons or a buried oil storage capacity greater than 42,000 gallons of petroleum



[Skill kit at a construction site.](#)

products. The SPCC rule requires every such site to prepare and implement an SPCC plan, which may differ from SWPPP requirements for spill prevention and control measures (U.S. EPA, 2007).

### Siting and Design Considerations

As the name implies, spill prevention and control measures consist of pollution prevention measures and measures to control and minimize impact if a spill does occur. Prevention measures should be routinely implemented by construction staff while spill control measures are generally included within a spill plan such as an SPCC plan. All construction staff should be familiar with both prevention and control measures.

When developing spill prevention and control measures, construction staff should identify areas where spills are likely to occur, such as loading and unloading areas, storage and processing areas, places where dust or particulate matter is generated or handled, areas where

equipment maintenance and fueling occur, chemical storage areas, and areas designated for waste disposal. Construction staff should also evaluate the spill potential for stationary facilities—including manufacturing areas, warehouses, service stations, parking lots and access roads—during the project planning phase and re-evaluate that potential during each phase of construction. Designing projects to minimize or use the right amount of herbicides, fertilizers and petroleum-based fuels can also be an important way to reduce stormwater pollutants (PWD, 2018). If construction staff need any of these materials on-site, they should use them as quickly as possible upon delivery to minimize the risk of a spill.

The most successful spill prevention and control measures include both structural and operational controls. Routine prevention measures include (SPU, 2017a, 2017b; U.S. EPA, 2019):

- Recycling, reclaiming or reusing materials, thereby reducing the amount of process materials that are brought on-site.
- Installing leak detection devices, overflow controls and diversion berms.
- Installing inlet protection on storm drains.
- Performing preventative maintenance on storm tanks, valves, pumps, pipes and other equipment.
- Using material transfer procedures or filling procedures for tanks and other equipment that minimize spills.
- Substituting less toxic or non-toxic materials for toxic materials.
- Storing materials in covered areas and within adequate secondary containment structures.
- Leaving hazardous materials in original, labeled containers and keeping Safety Data Sheets on-site.
- Storing materials off the bare ground and away from vehicular traffic and drainage pathways.
- Maintaining a clearly labeled and prominently displayed spill kit that includes, at a minimum, absorbent pads, sorbent booms or socks, absorbent granular material, protective clothing (such as latex gloves and safety glasses), thick plastic garbage bags, and drain covers.
- Following good housekeeping practices at project sites, such as appropriately disposing of unwanted

or unused waste material and immediately cleaning up spills or debris.

In the event of a spill, it is critical that a plan and appropriate equipment be in place and responsible parties be identified to carry out control measures immediately. A spill plan, such as an SPCC plan, should include components such as (SPU, 2017a, 2017b; U.S. EPA, 2019):

- Identification of individuals responsible for implementing control measures as well as personnel to contact in case of a spill.
- Identification of spill response procedures for small, medium and worst-case discharges, as appropriate.
- Definition of safety measures for each kind of waste.
- Instructions for how to notify appropriate authorities, such as police and fire departments, hospitals, or municipal sewage treatment facilities, for assistance.
- Description of procedures approved by state and local governments for containing, diverting, isolating and cleaning up spills.
- Description of spill response equipment to use, including safety and cleanup equipment, location of spill kits, and proper disposal methods for used materials.

For any spill, construction staff should avoid the use of water for cleaning to prevent contaminated stormwater from reaching storm drains; dry spills can be swept up while wet spills can be contained and absorbed using the equipment included in standard spill kits.

## Limitations

Training is necessary to ensure that all workers are aware of and knowledgeable about spill prevention and control measures. All staff on-site should receive training on spill prevention and control measures, including regular refresher training. Construction staff should make equipment and materials for cleanup readily accessible and mark them clearly so workers can follow procedures quickly and effectively.

## Maintenance Considerations

Construction staff should update the spill prevention and control measures regularly to accommodate any changes to the site, procedures or responsible staff (this



may include a site diagram showing the locations of spill kits, drainage pathways and evacuation routes). They should regularly inspect areas where spills may occur to ensure that procedures are posted and cleanup equipment is readily available. They should also replace spill kit materials as soon as workers use them and ensure spill kits always remain easily accessible.

## Effectiveness

Spill prevention and control measures can be highly effective at reducing the risk of surface and groundwater contamination; however, to ensure workers follow the procedures, construction staff should provide worker

training, appropriate materials and equipment for cleanup, and adequate staff time. If a spill occurs, prompt action is the most effective measure to limit environmental harm and cleanup costs.

## Cost Considerations

Spill prevention and control measures can be inexpensive to implement; however, construction staff need adequate time and resources to properly handle and dispose of spills. Good housekeeping is the cheapest and most cost-effective way to control a spill. Once a spill has occurred, the cost of cleanup can be significant.

### Additional Information

Additional information on related practices and the Phase II MS4 program can be found at EPA's National Menu of Best Management Practices (BMPs) for Stormwater website

## References

Philadelphia Water Department (PWD). (2018). *Stormwater retrofit guidance manual*. Philadelphia, PA: City of Philadelphia.

Seattle Public Utilities (SPU). (2017a). *City of Seattle stormwater manual* (Vol. 2).

Seattle Public Utilities (SPU). (2017b). *City of Seattle stormwater manual* (Vol. 4).

U.S. Environmental Protection Agency (U.S. EPA). (2007). *Developing your stormwater pollution prevention plan: A guide for construction sites* (EPA-833-R-06-004).

U.S. Environmental Protection Agency (U.S. EPA). (2019). *Oil spills prevention and preparedness regulations*.

Water Environment Services (WES). (2008). *Erosion prevention and sediment control: Planning and design manual*.


### Disclaimer

*This fact sheet is intended to be used for informational purposes only. These examples and references are not intended to be comprehensive and do not preclude the use of other technically sound practices. State or local requirements may apply.*



# Stormwater Best Management Practice

## Spill Response and Prevention



**Minimum Measure:** Pollution Prevention/Good Housekeeping for Municipal Operations  
**Subcategory:** Municipal Facilities

### Description

Accidental spills of hazardous materials, petroleum products or common chemicals/ can endanger public health or the environment if they reach waterways. Spill response and prevention practices can help to prevent spills from happening and can minimize impacts when a spill does occur. A key practice is creating and implementing a spill response and prevention plan, which should clearly state how to prevent spills, stop the source of a spill, how to contain and clean up a spill, how to dispose of contaminated materials, and how to train personnel to prevent and control future spills.

### Applicability

See the [Hazardous Materials Storage](#) fact sheet and [Materials Management](#) fact sheet for more information on storing and managing hazardous materials.

Spill response and prevention practices apply to any facility that uses or stores hazardous materials. Hazardous materials include petroleum products, pesticides, paints, cleaners, fertilizers and solvents. Applicable

facilities may include manufacturing areas, warehouses, service stations, roadways and parking lots. These facilities may be on public or private property, so municipal spill response and prevention practices pertain to both municipal activities on public properties and spill response procedures for private properties.

### Implementation

A municipality may implement spill response and prevention practices individually, within a stormwater management plan, or within a spill prevention and control plan. Being proactive to implement practices to prevent spills in the first place is pivotal. Instituting effective and coordinated response measures is key to responding quickly to prevent or limit any impacts that could occur from a spill.

### Prevention Practices

Municipalities should define material handling procedures and storage requirements and take actions to reduce the potential for spills. They can achieve this by:



Spills should be responded to swiftly and according to established response plans.

Photo Credit: Mark Herlihy/U.S. Air Force

- Recycling, reclaiming or reusing process materials, thereby reducing the amount of process materials they bring into facilities.
- Installing leak detection devices, overflow controls and diversion berms.
- Disconnecting drains from processing areas that lead to the storm sewer.
- Performing preventative maintenance on storm tanks, valves, pumps, pipes and other equipment.
- Using material transfer or filling procedures that minimize spills from tanks and other equipment.
- Replacing toxic materials with less or non-toxic products.

### Spill Response Plan

When a spill happens, it is critical to have a detailed plan in place. The plan should be clear and concise and should outline step-by-step instructions for spill containment, material cleanup and disposal, documentation, reporting, and follow-up procedures. The spill response plan can be in the form of a procedural handbook or a sign and should include the following components (EPA, 2007):

- Identification of potential spill or source areas such as loading and unloading, storage, and processing areas and areas designated for waste disposal.

- Identification of individuals responsible for implementing the plan.
- Description of safety measures to take with each kind of waste.
- Procedures for notifying appropriate authorities, such as police and fire departments, hospitals, or publicly owned treatment works.
- Procedures for containing, diverting, isolating and cleaning up the spill.
- Description of spill response equipment that staff should use, including safety and cleanup equipment.
- Storage of spill response supplies in easily accessible locations and in staff vehicles.
- Identification of a contractor for larger spill response.
- For spills on private property, procedures to collect cleanup and abatement costs from the responsible party.
- Procedures to document spills and spill response.

To make a spill response plan effective, municipalities need to make sure their staff understand it. They should also routinely train staff on best practices. In addition, municipalities should develop inspection checklists and response forms as part of the recordkeeping process.

A well-conceived plan reduces the likelihood of accidental spills and helps speed effective response if spills do occur.

### Public Education

In addition to the procedures described above, public education is essential for reducing spills outside municipal facilities. By informing the public of actions they can take to reduce spill potential, a municipality can reduce or prevent spills. Some municipalities have set up phone numbers that citizens can use to report spills. This helps ensure that municipalities can clean up spills safely, properly and promptly.

### Limitations

Municipalities need to plan their spill response and prevention programs well, define them clearly and execute them properly. One limitation of spill response and prevention is that municipalities are often largely reactive, focusing on response rather than prevention. Proper spill prevention requires that municipal staff participate in training and maintenance programs, and that plans have a strong public education component. Proper spill response also requires a proactive approach and enough funding to implement practices before a spill occurs. This includes staff training and having proper equipment and materials on hand, readily accessible and clearly marked so workers can respond according to plan.

### Maintenance Considerations

To prevent spills, staff should properly maintain potential sources of spills and leaks, keeping them in good operating condition. They should also regularly inspect areas where spills might occur to ensure that spill response procedures are in view and adequate stocks of cleanup equipment are readily accessible. If facility management changes any procedures or sites, it should update the spill prevention and response plan to reflect these changes.

### Cost Considerations

Costs of spill response and prevention include the cost of training municipal employees, purchasing spill kits or other on-site spill response equipment, and developing a public education program. This program will need a varying investment of staff hours and materials, depending on its extent. Spill response and prevention practices can be expensive—though arguably less so than cleaning up toxic spills that have already contaminated downstream waters and ecosystems.

### Additional Information

Additional information on related practices and the Phase II MS4 program can be found at EPA's National Menu of Best Management Practices (BMPs) for Stormwater website

### References

U.S. Environmental Protection Agency (EPA). (2007). *MS4 program evaluation guidance*.

### Disclaimer

*This fact sheet is intended to be used for informational purposes only. These examples and references are not intended to be comprehensive and do not preclude the use of other technically sound practices. State or local requirements may apply.*

## **ATTACHMENT B – POTENTIAL SOURCES OF CONTAMINATION**

Potential sources of sediment to stormwater runoff will include earthwork for drainage conveyance and erosion control, sidewalks, and access driveway improvements.

Potential pollutants and sources, other than sediment, to stormwater runoff will include concrete, grout mix, batteries, cleaning solvents, paint, asphalt mix, motor oil, gasoline, and diesel fuel.

## **ATTACHMENT C – SEQUENCE OF MAJOR ACTIVITIES**

1. Call 811 for existing utilities prior to any work on the Site.
2. Temporary erosion and sedimentation controls are to be installed, as indicated on the approved Site Plan and in accordance with a signed and sealed SWPPP, prior to any clearing and grubbing. Install tree protection. Post SWPPP on the Site.
3. Environmental project manager or site supervisor must contact the Environmental Inspection at the City of Austin, at 512-974-2278, 72 hours prior to the scheduled date of the required on-site preconstruction meeting.
4. Evaluate erosion control installation and review construction schedule with erosion control plan. Inspect and maintain controls weekly and prior to rainfall events, and after rainfall events. If a disturbed area is not to be worked on for more than 14 days, disturbed area needs to be stabilized by re-vegetation or mulching.
5. Begin site clearing/construction (or demolition) activities.
6. Rough grade site.
7. Rough grade rain garden area with temporary outlet. The rain garden will act as temporary sedimentation basins during construction.
8. Begin construction.
9. Place compacted base material in parking/driving areas.
10. Install curbing and place asphalt.
11. Install sidewalk and plaza area.
12. Construct rain garden with irrigation field.
13. Complete, construction, and begin re-vegetation and installing landscaping.
14. Project engineer and landscape architect inspect job and writes concurrence letters and submit letters to the City. Final inspection is scheduled upon receipt of the concurrence letters from each the engineer and the architect.
15. After final inspection has been approve by City inspector, temporary erosion controls and tree protection is removed. Perform final revegetation resulting from removal of erosion controls as necessary.

## **ATTACHMENT D – TEMPORARY BEST MANAGEMENT AND PRACTICES**

Silt fence and mulch sock will be located just down slope of all disturbed areas. Trees located inside the limits of construction will be protected by tree fencing.

See Erosion and Sedimentation Control (ESC) Plan from the Site Plan for locations of Best Management Practices and Details. Refer to Attachment F-Construction Plans in TCEQ Form 600.

A signed and sealed Stormwater Pollution Prevention Plan (SWPPP) will be required prior beginning any construction activities. The SWPPP in addition to the ESCs will be used to minimize the impact of grading and construction activities.

**ATTACHMENT E – REQUEST TO  
TEMPORARILY SEAL A FEATURE  
(IF REQUESTED)**

Not Applicable – No Features to Seal.

## **ATTACHMENT F – STRUCTURAL PRACTICES**

All discharge from rain garden and Site will be in the form of sheet flow. Rock riprap and/or energy dissipators have been provided at rain garden outfall.

The existing impervious cover for the 2.57 acre LOC/Site is 0.11 acres or 4%. Proposed impervious cover is 0.02 acres or 1%. The proposed improvements are allowed in the Critical Water Quality Zone (CWQZ) per the Environmental Criteria Manual (ECM), Section 1.5.3 Development Allowed in the CWQZ.


The City of Austin (COA) still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone (CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs. These ponds will be rough graded as described in Attachment C above, to act as temporary sedimentation basins during construction. The ponds will be fully constructed as Permanent BMPs. Refer to the Drainage Area Maps, Water Quality plan sheets from the Site Plan Set. Refer to Attachment F- Construction Plans in TCEQ Form 600.




## **ATTACHMENT G – DRAINAGE AREA MAP**





EXISTING DRAINAGE MAP



PROPOSED DRAINAGE MAP

Time of Concentration Calculations								
Basin ID	Area	Z <sub>1</sub>	Z <sub>3</sub>	Z <sub>2</sub>	Z <sub>1</sub>	L <sup>sheet</sup>	L <sup>shallow</sup>	L <sup>channel</sup>
-	ac	ft	ft	ft	ft	ft	ft	ft
OS1	2.35	512	498	471	0	100	107	0
V	2.57	470	459	454	0	100	99	0
Sheet Flow Calculations								
P <sub>2</sub>	3.44	t <sup>sheet</sup>	(0.007*((n*L) <sup>.8</sup> )/(((P <sub>2</sub> ) <sup>.5</sup> )*(s <sup>.4</sup> ))*60					
Basin ID	Z <sub>1</sub>	Z <sub>3</sub>	L <sup>sheet</sup>	s <sup>sheet</sup>	n <sup>sheet</sup>	t <sup>sheet</sup>		
-	ft	ft	ft	-	-	min		
OS1	512	498	100	0.140	0.15	4.3		
V	470	459	100	0.110	0.15	4.8		
Shallow Flow Calculations								
t <sup>shallow</sup>			t <sup>unpaved</sup> = L/(60(16.1345)(s)0.5)			t <sup>paved</sup> = L/(60(20.3282)(s)0.5)		
Basin ID	Z <sub>3</sub>	Z <sub>2</sub>	L <sup>shallow</sup>		s <sup>shallow</sup>	t <sup>shallow</sup>		
-	ft	ft	ft		-	min		
OS1	498	471	107		0.252	0.2		
V	459	454	99		0.051	0.5		
*All basins -unpaved								
Channel Flow Calculations								
t <sup>channel</sup>	L/(60*v)		v <sup>channel</sup>	(1.49*(r <sup>.667</sup> )*(s <sup>.5</sup> ))/n				
Basin ID	Z <sub>2</sub>	Z <sub>1</sub>	L <sup>channel</sup>	s <sup>channel</sup>	r	n <sup>channel</sup>	v <sup>channel</sup>	t <sup>channel</sup>
-	ft	ft	ft	-	ft	-	ft/s	min
OS1	471	0	0	N/A	0.500	0.012	N/A	0
V	454	0	0	N/A	0.750	0.012	N/A	0
Time of Concentration Summary								
Basin ID	Area	t <sup>Total</sup>			t <sup>lag</sup>			
-	ac	min			min			
OS1	2.35	5			3			
V	2.57	5			3			
*OS1 had an assumed Time of Concentration of 5 minutes.								

Existing Hydrologic Summary									
Basin ID	Area	Impervious	CN <sub>weighted</sub>	ToC	Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>	
-	ac.	%	-	min.	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	
OS1	2.4	13	82.3	5	9	17	22	31	
V	2.6	4	62.6	5	4	11	16	26	
Proposed Hydrologic Summary									
Basin ID	Area	Impervious	CN <sub>weighted</sub>	ToC	Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>	
-	ac.	%	-	min.	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	
OS1	2.35	13	82.3	5	9	17	22	31	
V	2.57	1	61.3	5	3	10	16	25	
Point of Analysis - To Barton Creek					Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>	
Existing					13.0	27.8	38.5	56.8	
Proposed					12.6	27.2	37.9	56.1	
Proposed - Existing					-0.4	-0.6	-0.6	-0.7	

- LEGEND
- X = XX ac. DRAINAGE AREA ID
- DRAINAGE AREA
- CONTOUR - EXISTING
- CONTOUR - PROPOSED
- FLOW - EXISTING
- FLOW - PROPOSED

SITE PLAN APPROVAL

FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_ SHEET 226 OF 239

APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION 112 OF

CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.

EXPIRATION DATE (25-5-81, LDC) \_\_\_\_\_ CASE MANAGER: \_\_\_\_\_

PROJECT EXPIRATION DATE (OED #97905-A) \_\_\_\_\_ N/A DWFPZ \_\_\_\_\_ DDZ \_\_\_\_\_

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_

Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_

Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

R5

NEW SHEET

REVISION DESCRIPTION

DATE

BY

REV. NO.

APPROVED

DATE 12/16/2021

MICHAEL C. MULLONE

127850

LICENSED PROFESSIONAL ENGINEER

Mike Mullone

12/16/2021

SCALE 1" = 50'

0 25 50

VIOLET CROWN TRAILHEAD

WILLIAM BARTON DR.

AUSTIN TX 78746

EXISTING & PROPOSED DRAINAGE MAPS

DUNAWAY UDOG

TX Registered Engineering Firm #F-11114

TBPLS Firm No. 10065900

5707 Southwest Parkway

Building 2, Suite 250

Austin, TX 78735

Phone: 512-306-8252

C4.00

JOB NO. B005344.001

SPC-2012-0104D(R5)

SHEET NUMBER 226 OF 239



## **ATTACHMENT H – TEMPORARY SEDIMENT PONDS PLANS AND CALCULATIONS**

Not Applicable – Refer to Attachments C and F about permanent pond structures.

# ATTACHMENT I – INSPECTION AND MAINTENANCE FOR BMPS

- Silt Fence - Inspect prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season. Repair or replace split, torn, slumping, or weathered fabric. Silt fences that are damaged and become unsuitable for the intended purpose should be removed from the site of work, disposed of, and replaced with new silt fence barriers. Sediment that accumulates in the silt fence must be periodically removed in order to maintain silt fence effectiveness. Sediment should be removed when the sediment accumulation reaches approximately one-half of the fence height (one foot) on the silt fence. Sediment removed during maintenance may be incorporated into earthwork on the site or disposed at an appropriate location. Upon removal of silt fence, accumulated sediment must also be removed and disposed of properly. Silt fences should be left in place until the upstream area is permanently stabilized. Holes, depressions, or other ground disturbance caused by the removal of the silt fences should be backfilled and repaired.
- Mulch Sock - Inspect mulch socks after installation for gaps under the mulch socks and for gaps between the joints of adjacent ends of mulch socks. Inspect every 7-days and within 24-hours of a rainfall event of 0.5-inches or greater event and replace or repair if necessary. Sediment retained by the sock shall be removed when it has reached 1/3 of the exposed height of the sock. Alternatively, the sediment and sock can be stabilized with vegetation at the end of construction.
- Triangular Sediment Filter Dike - Inspect prior to forecast rain, daily during extended rain events, after rain events, weekly during the rainy season, and at two-week intervals during the non-rainy season. Repair or replace split, torn, or weathered fabric. Triangular sediment filter dike that are damaged and become unsuitable for the intended purpose should be removed from the site of work, disposed of, and replaced. Sediment that accumulates in the triangular sediment filter dike must be periodically removed in order to maintain effectiveness.
- Stabilized Construction Entrance - The entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public rights of way. This may require periodic top dressing with additional stone as conditions

demand and repair and/or clean out of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public rights of way must be removed immediately by contractor. When necessary, wheels must be cleaned to remove sediment prior to entrance onto public right of way. When washing is required, it shall be done on an area stabilized with crushed stone which drains into an approved sediment trap or sediment basin. All sediment shall be prevented from entering any storm drain, ditch or watercourse using approved methods.

- Concrete Washout Area : shall be maintained in a condition which will prevent direct discharges to surface waters, groundwater, or to areas that have minimal slope that allow infiltration and filtering of wash out water to prevent direct discharges to surface waters. Wash out of concrete trucks during rainfall events shall be minimized. Concrete washout area shall be emptied when full and prior to rain events.

# ATTACHMENT J – SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

## **Temporary Soil Stabilization**

- Soil Retention Blanket/Sodding - will be used to stabilize exposed soils where construction activities have permanently ceased or be temporarily halted for 14 days or longer. Construction debris, trash and temporary BMPs (including silt fences, tree protection, and inlet protection) will also be removed and any areas disturbed during removal will be seeded immediately.
- Mulching - will be used to stabilize soils where construction activities have temporarily halted for 14 days or longer.
- Tree Protection - will be installed prior to initiation of construction activities. Fencing will be inspected Before and after daily construction activities.

**Permanent Soil Stabilization** – Refer to Landscape Plan Sheets of Site Plan.  
Refer to Attachment F- Construction Plans in TCEQ Form 600.

# Permanent Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(li), (E), and (5), Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Jessica Powers

Date: 7/11/2024

Signature of Customer/Agent

Jessica Powers

Digitally signed by Jessica Powers  
DN: C=US, E=jpowers@dunaway.com,  
CN=Jessica Powers  
Date: 2024.07.11 11:21:37-05'00'

Regulated Entity Name: \_\_\_\_\_

## Permanent Best Management Practices (BMPs)

***Permanent best management practices and measures that will be used during and after construction is completed.***

- ☒ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.  
☐ N/A
- ☒ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.  
☐ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

- ☒ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: City of Austin Drainage Criteria Manual - Save Our Springs Design Section and Regulations
- ☐ N/A
3. ☒ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
- ☐ N/A
4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
- ☐ The site will be used for low density single-family residential development and has 20% or less impervious cover.
- ☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.
- ☒ The site will not be used for low density single-family residential development.
5. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
- ☐ **Attachment A - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.
6. ☒ **Attachment B - BMPs for Upgradient Stormwater.**



- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☐ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7. ☒ **Attachment C - BMPs for On-site Stormwater.**
- ☒ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8. ☐ **Attachment D - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
- ☒ N/A
9. ☒ The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
- ☒ The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.
- ☐ **Attachment E - Request to Seal Features.** A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10. ☒ **Attachment F - Construction Plans.** All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
- ☒ Design calculations (TSS removal calculations)
- ☐ TCEQ construction notes
- ☐ All geologic features
- ☒ All proposed structural BMP(s) plans and specifications
- ☐ N/A

11. ☒ **Attachment G - Inspection, Maintenance, Repair and Retrofit Plan.** A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
- ☒ Prepared and certified by the engineer designing the permanent BMPs and measures
  - ☐ Signed by the owner or responsible party
  - ☒ Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
  - ☒ A discussion of record keeping procedures
- ☐ N/A
12. ☐ **Attachment H - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- ☒ N/A
13. ☒ **Attachment I - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
- ☐ N/A

### ***Responsibility for Maintenance of Permanent BMP(s)***

***Responsibility for maintenance of best management practices and measures after construction is complete.***

14. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- ☐ N/A
15. ☐ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
- ☒ N/A

**ATTACHMENT A – 20% OR LESS  
IMPERVIOUS COVER  
(IF REQUESTED FOR MULTI-FAMILY, SCHOOL, OR  
SMALL BUSINESS SITE)**



July 1, 2024

**20% or Less Impervious Cover Waiver** : Violet Crown Trailhead

To whom it may concern:

The existing impervious cover for the 2.57 acre LOC/Site is 0.11 acres or 4%. Proposed impervious cover is 0.02 acres or 1%. The proposed improvements are allowed in the Critical Water Quality Zone (CWQZ) per the Environmental Criteria Manual (ECM), Section 1.5.3 Development Allowed in the CWQZ.

The City of Austin (COA) still requires WQ treatment for the new impervious cover even though we are reducing the amount in our Site. The site is in the Barton Springs 100-year floodplain and Critical Water Quality Zone (CWQZ). The COA does not allow WQ controls in the floodplain or CWQZ. The COA instead had us treat an equivalent amount of impervious cover from an existing roadway that matched our proposed impervious cover square footage.

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs. The ponds will be fully constructed as Permanent BMPs. Refer to the Drainage Area Maps, Water Quality plan sheets from the Site Plan Set. Refer to Attachment F- Construction Plans in TCEQ Form 600.

Respectfully submitted,

**DUNAWAY ASSOCIATES, L.P.,**  
**a Texas limited partnership**

A handwritten signature in black ink that reads "Mike Mullone".

---

Mike Mullone, PE, CFM, CESSWI, CPESC

## **ATTACHMENT B – BMPS FOR UPGRADIENT STOMRWATER**

Not Applicable – Upgradient is being treated already by the Off Site itself as it is required by City of Austin.

## **ATTACHMENT C – BMPS FOR ON-SITE STOMRWATER**

WQ will be in the form of a dual storm water control measure (SCM) of a biofiltration pond and irrigation field. The SCMs will be located outside of the CWQZ, approximately 250 feet northeast of the intersection of Columbus Drive and William Barton Drive. A portion of William Barton Drive, located outside of the CWQZ will be treated by the SCMs. These ponds will be rough graded as described in Attachment C above, to act as temporary sedimentation basins during construction. The ponds will be fully constructed as Permanent BMPs. Refer to the Drainage Area Maps, Water Quality plan sheets from the Site Plan Set. Refer to Attachment F- Construction Plans in TCEQ Form 600. The pond will return discharges to sheet flow, which will continue to sheet flow to Barton Creek. No construction activities will be in the creek area.

## **ATTACHMENT D – BMPS FOR SURFACE STREAMS**

- Not Applicable – Refer to Attachment C above.

**ATTACHMENT E – REQUEST TO SEAL  
FEATURES  
(IF SEALING A FEATURE)**

Not Applicable – No Features to Seal.



## **ATTACHMENT F – CONSTRUCTION PLANS**

JURISDICTION

THE SITE IS LOCATED WITHIN THE FULL PURPOSE JURISDICTION OF THE CITY OF AUSTIN.

ZONING

THE SITE IS ZONED "P"

LEGAL DESCRIPTION

-

WATERSHED

1. THIS PROJECT IS LOCATED IN THE BARTON CREEK WATERSHED, A BARTON SPRINGS WATERSHED.
2. THIS SITE IS LOCATED OVER THE EDWARDS AQUIFER RECHARGE ZONE.

FEMA FLOODPLAIN NO.

1. A PORTION OF THIS PROJECT IS LOCATED WITHIN THE 100-YR FLOODPLAIN AS SHOWN ON FEMA PANEL NO. 48453C0445J, EFFECTIVE ON JANUARY 6, 2016

NOTES

APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN INDICATES COMPLIANCE WITH APPLICABLE CITY REGULATIONS ONLY. APPROVAL BY OTHER GOVERNMENTAL ENTITIES MAY BE REQUIRED PRIOR TO THE START OF CONSTRUCTION. THE APPLICANT IS RESPONSIBLE FOR DETERMINING WHAT ADDITIONAL APPROVALS MAY BE NECESSARY.

RETAINING WALLS OVER FOUR FEET IN HEIGHT, MEASURED FROM THE BOTTOM OF THE FOOTING TO THE TOP OF WALL, SHALL BE ENGINEERED AND WILL REQUIRE A SEPARATE PERMIT (UNIFORM BUILDING CODE 106.2.5)

EXISTING CONDITIONS

THE LOCATION OF EXISTING UTILITIES AND STORM SEWER SHOWN ON THE PLAN WERE TAKEN FROM CITY OF AUSTIN RECORDS WHICH MAY NOT HAVE BEEN COMPLETE AND/OR ACCURATE. THEREFORE, THE PRESENCE, LOCATION, AND ELEVATION OF EXISTING UTILITIES AND STORM SEWER IN THE FIELD SHALL BE VERIFIED BY THE CONTRACTOR BEFORE COMMENCING WORK. IT SHALL BE THE DUTY OF THE CONTRACTOR TO ASCERTAIN WHETHER ANY ADDITIONAL FACILITIES OTHER THAN THOSE SHOWN ON THE PLANS MAY BE PRESENT. FAILURE OF AN EXISTING UTILITY OR STORM SEWER TO APPEAR ON THE PLANS OR RECORDS SHALL NOT RELIEVE THE CONTRACTOR OF THEIR RESPONSIBILITY TO PROTECT AND REPAIR, IF THEY DAMAGE, SUCH UTILITIES AND STORM SEWER.

TRAFFIC CONTROL PLAN NOTE

THIS NOTE IS BEING PLACED ON THE PLAN SET IN THE ABSENCE OF A TEMPORARY TRAFFIC CONTROL STRATEGY WITH THE FULL UNDERSTANDING THAT, AT A MINIMUM OF 6 WEEKS PRIOR TO THE START OF CONSTRUCTION, A TEMPORARY TRAFFIC CONTROL PLAN MUST BE REVIEWED AND APPROVED BY RIGHT OF WAY MANAGEMENT DIVISION. STANDARD DETAILS ARE NOT A TRAFFIC CONTROL PLAN. THE OWNER/REPRESENTATIVE FURTHER RECOGNIZES THAT A REVIEW FEE, AS PRESCRIBED BY THE MOST CURRENT VERSION OF THE CITY'S FEE ORDINANCE, SHALL BE PAID EACH TIME A PLAN OR PLAN REVISION IS SUBMITTED TO RIGHT OF WAY MANAGEMENT DIVISION FOR REVIEW.

THE FOLLOWING MUST BE TAKEN INTO CONSIDERATION WHEN DEVELOPING FUTURE TRAFFIC CONTROL STRATEGIES:

- \* PEDESTRIAN AND BICYCLE TRAFFIC ACCESS MUST BE MAINTAINED AT ALL TIMES, UNLESS OTHERWISE AUTHORIZED BY RIGHT OF WAY MANAGEMENT
- \* NO LONG-TERM LANE CLOSURES WILL BE AUTHORIZED, UNLESS RIGHT OF WAY MANAGEMENT DETERMINES THAT ADEQUATE ACCOMMODATIONS HAVE BEEN MADE TO MINIMIZE TRAFFIC IMPACT.
- \* PROJECT SHOULD BE PHASED SO THAT UTILITY INSTALLATION MINIMALLY IMPACTS EXISTING OR TEMPORARY PEDESTRIAN FACILITIES.

SUB-CHAPTER E

THIS SITE PLAN IS SUBJECT TO SUBCHAPTER E OF THE LAND DEVELOPMENT CODE (COMMERCIAL DESIGN STANDARDS).

AMERICANS WITH DISABILITIES ACT

THE CITY OF AUSTIN HAS REVIEWED THIS PLAN FOR COMPLIANCE WITH CITY DEVELOPMENT REGULATIONS ONLY. THE APPLICANT, PROPERTY OWNER, AND OCCUPANT OF THE PREMISES ARE RESPONSIBLE FOR DETERMINING WHETHER THE PLAN COMPLIES WITH ALL OTHER LAWS, REGULATIONS, AND RESTRICTIONS WHICH MAY BE APPLICABLE TO THE PROPERTY AND ITS USE.

NO UTILITY CHANGES

NO CHANGES TO EXISTING OR PROPOSED, PUBLIC OR PRIVATE WATER OR WASTEWATER UTILITY INFRASTRUCTURE WILL BE MADE WITH THESE IMPROVEMENTS

ELECTRICAL NOTES

- 1.) AUSTIN ENERGY HAS THE RIGHT TO PRUNE AND/OR REMOVE TREES, SHRUBBERY AND OTHER OBSTRUCTIONS TO THE EXTENT NECESSARY TO KEEP THE EASEMENTS CLEAR. AUSTIN ENERGY WILL PERFORM ALL TREE WORK IN COMPLIANCE WITH CHAPTER 25-8, SUBCHAPTER B OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- 2.) THE OWNER/DEVELOPER OF THIS SUBDIVISION/LOT SHALL PROVIDE AUSTIN ENERGY WITH ANY EASEMENT AND/OR ACCESS REQUIRED, IN ADDITION TO THOSE INDICATED, FOR THE INSTALLATION AND ONGOING MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8 OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- 3.) THE OWNER SHALL BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY EROSION CONTROL, REVEGETATION AND TREE PROTECTION. IN ADDITION, THE OWNER SHALL BE RESPONSIBLE FOR ANY INITIAL TREE PRUNING AND TREE REMOVAL THAT IS WITHIN TEN FEET OF THE CENTER LINE OF THE PROPOSED OVERHEAD ELECTRICAL FACILITIES DESIGNED TO PROVIDE ELECTRIC SERVICE TO THIS PROJECT. THE OWNER SHALL INCLUDE AUSTIN ENERGY'S WORK WITHIN THE LIMITS OF CONSTRUCTION FOR THIS PROJECT.
- 4.) THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRIC SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS, CITY OF AUSTIN RULES AND REGULATIONS AND TEXAS STATE LAWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES AND EQUIPMENT. AUSTIN ENERGY WILL NOT RENDER ELECTRIC SERVICE UNLESS REQUIRED CLEARANCES ARE MAINTAINED. ALL COSTS INCURRED BECAUSE OF FAILURE TO COMPLY WITH THE REQUIRED CLEARANCES WILL BE CHARGED TO THE OWNER.
- 5.) ANY RELOCATION OF ELECTRIC FACILITIES SHALL BE AT LANDOWNER'S/DEVELOPER'S EXPENSE.


DRAINAGE NOTES

RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.

VIOLET CROWN TRAILHEAD

WILLIAM BARTON DR.  
AUSTIN TX 78746

LOCATION MAP



COA GRID: G22, MAPSCO PG: 584X

ENVIRONMENTAL NOTES

1. THIS PROJECT IS SUBJECT TO THE VOID AND WATER FLOW MITIGATION RULE ( COA ECM 1.12.0 AND COA ITEM No. 658S OF THE SSM) PROVISION THAT ALL TRENCHING GREATER THAN 5 FEET DEEP MUST BE INSPECTED BY A GEOLOGIST (TEXAS P.G.) OR A GEOLOGIST'S REPRESENTATIVE.

SHEET INDEX

SHEET #	DESIGNATION	TITLE
218	C0.00	COVER SHEET
219	C0.01	GENERAL NOTES
220	C0.10	EXISTING CONDITIONS & DEMOLITION PLAN
221	C1.00	SITE PLAN
222	C1.10	PHASING PLAN
223	C2.00	GRADING PLAN
224	C3.00	EROSION, SEDIMENTATION CONTROL, & TREE PROTECTION PLAN
225	C3.20	EROSION, SEDIMENTATION CONTROL, & TREE PROTECTION DETAILS
226	C4.00	EXISTING & PROPOSED DRAINAGE AREA MAPS
227	C4.10	PROPOSED DRAINAGE AREA MAP RAIN GARDEN
228	C6.00	RAIN GARDEN
229	C6.10	RAIN GARDEN DETAILS
230	C7.00	DETAILS
231	L-1	LANDSCAPE PLAN
232	L-2	TREE MITIGATION & LANDSCAPE CALCULATIONS
233	L-3	LANDSCAPE DETAILS
234	L-4	WATER QUALITY POND CALCULATIONS
235	L-5	APPENDIX X PLANTING
236	S-1	SHADE STRUCTURE FOUNDATION AND ROOF FRAMING PLANS
237	S-2	SHADE STRUCTURE SECTIONS AND DETAILS
238	S-3	ENTRY GATEWAY SECTIONS AND DETAILS
239	S-4	OVERLOOK SECTION AND DETAILS

APPROVALS:

REVIEWED BY:

NA	
CITY OF AUSTIN INDUSTRIAL WASTE DEPT.	DATE
<i>Jana Hagenson</i>	12/28/2021
CITY OF AUSTIN WATER UTILITY	DATE
<i>M. Lewis</i>	Jan. 04, 2022
CITY OF AUSTIN FIRE DEPARTMENT	DATE

APPLICABLE WATERSHED ORDINANCE: \_\_\_\_\_  
OPERATING PERMIT WHERE APPLICABLE UNDER 25-8-233

WATERSHED PROTECTION DEPARTEMENT	DATE
----------------------------------	------


APPROVAL FOR SITE DEVELOPMENT PERMIT:

REVIEWED BY:

<i>Renee Johns</i>	01/07/22
DEVELOPMENT SERVICES DEPARTMENT	DATE

SPC-2012-0104D(R5)	P
SITE DEVELOPMENT PERMIT NO.	SITE ZONING

SUBMITTAL DATE



NEW SHEET

SITE PLAN APPROVAL

FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
APPROVED BY COMMISSION ON: 01/07/22 UNDER SECTION 112. OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.  
EXPIRATION DATE (25-5-81, LDC) \_\_\_\_\_ CASE MANAGER: \_\_\_\_\_  
PROJECT EXPIRATION DATE (OED #970905-A) 01/07/25 DWFPZ \_\_\_\_\_ DDZ \_\_\_\_\_

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_  
Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_  
Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_  
Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_  
Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

SHEET 218 OF 239

12/8/2021

CITY OF AUSTIN  
APPROVED  
DATE: 12/10/2021  
FOUNDED 1837

REVISION DESCRIPTION

DATE

BY

REV. NO.

CITY OF TEXAS  
MICHAEL C. MULLONE  
127850  
LICENSED PROFESSIONAL ENGINEER  
Mike Mullone  
12/16/2021

VIOLET CROWN TRAILHEAD  
WILLIAM BARTON DR.  
AUSTIN TX 78746  
COVER SHEET

DUNAWAY UDOG  
TX Registered Engineering Firm #F-11114  
TBDLS Firm No. 10065900  
5707 Southwest Parkway  
Building 2, Suite 250  
Austin, TX 78735  
Phone: 512-306-8252

C0.00

JOB NO. B005344.001

SPC-2012-0104D(R5)

SHEET NUMBER 218 OF 239

G:\Production\4000\0065300\5344\_001\Civil\CAD\Plans\Site Plan\Sheets\VC1-S-COVER.dgn12/8/2021



APPENDIX P-1 - EROSION CONTROL NOTES

1. The contractor shall install erosion/sedimentation controls, tree/natural area protective fencing, and conduct "Pre-Construction" tree fertilization (if applicable) prior to any site preparation work (clearing, grubbing or excavation) that can ultimately result in soil compaction or erosion.
2. The placement of erosion/sedimentation controls shall be in accordance with the Environmental Criteria Manual and the approved Erosion and Sedimentation Control Plan. The COA ESC Plan shall be consulted and used as the basis for a TPDES required SWPPP. If a SWPPP is required, it shall be available for review by the City of Austin Environmental Inspector at all times during construction, including at the Pre-Construction meeting. The checklist below contains the basic elements that shall be reviewed for permit approval by COA EV Inspectors. Reviewers as well as COA EV Inspectors.
- Plan sheets submitted to the City of Austin MUST show the following:
- ✓ Direction of flow during grading operations.
  - ✓ Location, description, and calculations for off-site flow diversion structures.
  - ✓ Areas that will not be disturbed; natural features to be preserved.
  - ✓ Delineation of contributing drainage area to each proposed BMP (e.g., silt fence, sediment basin, etc.).
  - ✓ Location and type of E&S BMPs for each phase of disturbance.
  - ✓ Calculations for BMPs as required.
  - ✓ Location and description of temporary stabilization measures.
  - ✓ Location of on-site spoils, description of handling and disposal of borrow materials, and description of on-site permanent spoils disposal areas, including size, depth of fill and revegetation procedures.
  - ✓ Describe sequence of construction as it pertains to ESC including the following elements:
    - 1. Installation sequence of controls (e.g., perimeter controls, then sediment basins, then temporary stabilization, then permanent, etc.)
    - 2. Project phasing if required (LOC greater than 25 acres)
    - 3. Sequence of grading operations and notation of temporary stabilization measures to be used
    - 4. Schedule for converting temporary basins to permanent WQ controls
  - 5. Schedule for removal of temporary control
  - 6. Anticipated maintenance schedule for temporary controls
- Categorize each BMP under one of the following areas of BMP activity as described below:
- 3.1 Minimize disturbed area and protect natural features and soil
  - 3.2 Control Stormwater flowing onto and through the project
  - 3.3 Stabilize Soils
  - 3.4 Protect Slopes
  - 3.5 Protect Storm Drain Inlets
  - 3.6 Establish Perimeter Controls and Sediment Barriers
  - 3.7 Retain Sediment On-Site and Control Dewatering Practices
  - 3.8 Establish Stabilized Construction Exits
  - 3.9 Any Additional BMPs
- Note the location of each BMP on your site map(s).
- For any structural BMPs, you should provide design specifications and details and refer to them.
- For more information, see City of Austin Environmental Criteria Manual 1.4.
3. The Placement of tree/natural area protective fencing shall be in accordance with the City of Austin standard Notes for Tree and Natural Area Protection and the approved Grading/Tree and Natural Area Plan.
4. A pre-construction conference shall be held on-site with the contractor, design Engineer/permit applicant and Environmental Inspector after installation of the erosion/sedimentation controls, tree/natural area protection measures and "Pre-Construction" tree fertilization (if applicable) prior to beginning any site preparation work. The preparation work or owner's representative shall notify the Development Services Department, 512-974-2278 or by email at [environmental.inspections@austintexas.gov](mailto:environmental.inspections@austintexas.gov), at least three days prior to the meeting date. COA approved ESC Plan and TPDES SWPPP (if required) should be reviewed by COA EV Inspector at this time.
5. Any major variation in materials or locations of controls or fences from those shown on the approved plans will require a revision and must be approved by the reviewing Engineer, Environmental Specialist or City Arborist as appropriate. Major revisions must be approved by authorized COA staff. Minor changes to be made as field revisions to the Erosion and Sedimentation Control Plan may be required by the Environmental Inspector during the course of construction to correct control inadequacies.
6. The contractor is required to provide a certified inspector that is either a licensed engineer (or person directly supervised by the licensed engineer) or Certified Professional in Erosion and Sediment Control (CPESC or CPESC - IT), Certified Erosion, Sediment and Stormwater Inspector (CESSWI or CESSWI - IT) or Certified Inspector of Sedimentation and Erosion Controls (CISEC or CISEC - IT) certification to inspect the controls and fences at weekly or bi-weekly intervals and after one-half (1/2) inch or greater rainfall events to insure that they are functioning properly. The person(s) responsible for maintenance of controls and fences shall immediately make any necessary repairs to damaged areas. Silt accumulation at controls must be removed when the depth reaches six (6) inches or one-third (1/3) of the installed height of the control whichever is less.
7. Prior to final acceptance by the City, haul roads and waterway crossings constructed for temporary contractor access must be removed, accumulated sediment removed from the waterway and the area resloped to the original grade and revegetated. All land clearing debris shall be disposed of in approved spoil disposal sites.
8. All work must stop if a void in the root substrate is discovered which is; one square foot in total area; blows air from within the substrate and/or consistently receives water during any rain event. At this time it is the responsibility of the Project Manager to immediately contact a City of Austin Environmental Inspector for further investigation.
9. Temporary and Permanent Erosion Control: All disturbed areas shall be restored as noted below:
- All disturbed areas to be revegetated are required to place a minimum of six (6) inches of topsoil [see Standard Specification Item No. 601S.3(A)]. Do not add topsoil within the critical root zone of existing trees.
  - Topsoil salvaged from the existing site is encouraged for use, but it should meet the standards set forth in 601S.
  - An owner/engineer may propose use of onsite salvaged topsoil which does not meet the criteria of Standard Specification 601S by providing a soil analysis and a written statement from a qualified professional in soils, landscape architecture, or agronomy indicating the onsite topsoil will provide an equivalent growth media and specifying what, if any, soil amendments are required.
  - Soil amendments shall be worked into the existing onsite topsoil with a disc or tiller to create a well-blended material.
- The vegetative stabilization of areas disturbed by construction shall be as follows:
- TEMPORARY VEGETATIVE STABILIZATION:**
- From September 15 to March 1, seedling shall be with or include a cool season cover crop: (Western Wheatgrass (*Pascopyrum smithii*) at 5.6 pounds per acre, Oats (*Avena sativa*) at 4.0 pounds per acre, Sorrel Five Grain (*Sorrel cereale*) at 45 pounds per acre. Contractor must ensure that any seed application requiring a cool season cover crop does not utilize annual ryegrass (*Lolium multiflorum*) or perennial ryegrass (*Lolium perenne* ). Cool season cover crops are not permanent erosion control.
  - From March 2 to September 14, seedling shall be with hulled Bermuda at a rate of 45 pounds per acre or a native plant seed mix conforming to Item 604S or 609S.
    - Fertilizer shall be applied only if warranted by a soil test and shall conform to Item No. 606S. Fertilizer. Fertilization should not occur when rainfall is expected or during slow plant growth or dormancy. Chemical fertilizer may not be applied in the Critical Water Quality Zone.
  - Hydromulch shall comply with Table 1, below.
  - Temporary erosion control shall be acceptable when the grass has grown at least 1 1/2 inches high with a minimum of 95% total coverage so that all areas of a site that rely on vegetation for temporary stabilization are uniformly vegetated, and provided there are no bare spots larger than 10 square feet.
  - When required, native plant seeding shall comply with requirements of the City of Austin Environmental Criteria Manual, and Standard Specification 604S or 609S.
- Table 1: Hydromulching for Temporary Vegetative Stabilization**
- | MATERIAL                      | DESCRIPTION  | LONGEVITY                                      | TYPICAL APPLICATIONS   | APPLICATION RATES  |
|-------------------------------|--|--|--|--|
| BONDED FIBER MATRIX (BFM)     | 80% ORGANIC DEBRATED FIBERS  | ON SLOPES UP TO 2:1 AND ERODIVE SOL CONDITIONS | 2,500 TO 4,000 LBS PER ACRE (SEE MANUFACTURER'S RECOMMENDATIONS) |  |
| 10% TACKIFIER                 | 6 MONTHS   |  |  |  |
| FIBER REINFORCED MATRIX (FRM) | 65% ORGANIC DEBRATED FIBERS<br>25% REINFORCING FIBERS OR LESS<br>10% TACKIFIER | UP TO 12 MONTHS                                | ON SLOPES UP TO 1:1 AND ERODIVE SOL CONDITIONS                   | 3,000 TO 4,500 LBS PER ACRE (SEE MANUFACTURER'S RECOMMENDATIONS) |
10. Developer Information:  
Owner: AUSTIN PARKS AND RECREATION DEPARTMENT  
Phone #: 512.974.6270  
Address: 200 S LAMAR BLVD., AUSTIN, TX 78704  
Owner's representative responsible for plan alterations: DUNAWAY UDOG  
Phone #: 512.306.8252  
Person or firm responsible for erosion/sedimentation control maintenance: \_\_\_\_\_  
Phone #: \_\_\_\_\_  
Person or firm responsible for tree/natural area protection Maintenance: \_\_\_\_\_  
Phone #: \_\_\_\_\_
11. The contractor shall not dispose of surplus excavated material from the site without notifying the Development Services Department at 512-974-2278 at least 48 hours prior with the location and a copy of the permit issued to receive the material.
- Source: Rule No. R161-15.13, 1-4-2016; Rule No. R161-17.03, 3-2-2017.

APPENDIX P-2: - CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION

- All trees and natural areas shown on plan to be preserved shall be protected during construction with temporary fencing.
- Protective fences shall be erected according to City of Austin Standards for Tree Protection.
- Protective fences shall be installed prior to the start of any site preparation work (clearing, grubbing or grading), and shall be maintained throughout all phases of the construction project.
- Erosion and sedimentation control barriers shall be installed or maintained in a manner which does not result in soil build-up within tree drip lines.
- Protective fences shall surround the trees or group of trees, and will be located at the outermost limit of branches (drip line), for natural areas, protective fences shall follow the Limit of Construction line, in order to prevent the following:
  - Soil compaction in the root zone area resulting from vehicular traffic or storage of equipment or materials;
  - Root zone disturbances due to grade changes (greater than 6 inches cut or fill), or trenching not reviewed and authorized by the City Arborist;
  - Wounds to exposed roots, trunk or limbs by mechanical equipment;
  - Other activities detrimental to trees such as chemical storage, cement truck cleaning, and fires.
- Exceptions to installing fences at tree drip lines may be permitted in the following cases:
  - Where there is to be an approved grade change, impermeable paving surface, tree well, or other such site development, erect the fence approximately 2 to 4 feet beyond the area disturbed;
  - Where permeable paving is to be installed within a tree's drip line, erect the fence at the outer limits of the permeable paving area (prior to site grading so that this area is graded separately prior to paving installation to minimize root damage);
  - Where trees are close to proposed buildings, erect the fence to allow 6 to 10 feet of work space between the fence and the building;
  - Where there are severe space constraints due to tract size, or other special requirements, contact the City Arborist at 974-1876 to discuss alternatives.
- Special Note: For the protection of natural areas, no exceptions to installing fences at the Limit of Construction line will be permitted.
- Where any of the above exceptions result in a fence being closer than 4 feet to a tree trunk, protect the trunk with strapped-on planking to a height of 8 ft (or to the limits of lower branching) in addition to the reduced fencing provided.
- Trees approved for removal shall be removed in a manner which does not impact trees to be preserved.
- Any roots exposed by construction activity shall be pruned flush with the soil. Backfill root areas with good quality top soil as soon as possible. If exposed root areas are not backfilled within 2 days, cover them with organic material in a manner which reduces soil temperature and minimizes water loss due to evaporation.
- Any trenching required for the installation of landscape irrigation shall be placed as far from existing tree trunks as possible.
- No landscape topsoil dressing greater than 4 inches shall be permitted within the drip line of trees. No soil is to be placed on or in the root flare of any tree.
- Purning to provide clearance for structures, vehicular traffic and equipment shall take place before damage occurs (ripping of branches, etc.).
- All finished pruning shall be done according to recognized, approved standards of the industry (Reference the National Arborist Association Pruning Standards for Shade Trees available on request from the City Arborist).
- Deviations from the above notes may be considered ordinance violations if there is substantial non-compliance of if a tree sustains damage as a result.

DUST CONTROL

Dust shall be controlled on the project site by one of the following methods:

Mulches - Section 1.4.4. Chemical mulch binders may be used instead of asphalt to bind mulch materials. Binders such as Curasol or Terra Tack should be used according to manufacturer's recommendations.

Vegetative Cover - See Section 1.4.4.

Spray-on Adhesives - On mineral soils (not effective on muck soils). Keep traffic off these areas.

TABLE 1-4S  
SPRAY-ON ADHESIVES

Water Dilution	Type of Nozzle	Apply- Gallons/Acre
Anionic asphalt emulsion	7:1 Coarse Spray	1,200
Latex emulsion	12/12:1 Fine Spray	235
Resin-in-water emulsion	4:1 Fine Spray	300

Source: City of Austin

Tillage - To roughen surface and bring clods to the surface. This is an emergency measure which should be used before soil blowing starts. Begin plowing on windward side of site. Chisel-type plows spaced about 12 inches apart, spring-toothed harrows and similar plows are examples of equipment which may produce the desired effect.

Irrigation - This is generally done as an emergency treatment. Site is sprinkled with water until the surface is moist. Repeat as needed.

Barriers - Solid board fences, snow fences, burlap fences, crate walls, bales of hay and similar materials can be used to control air currents and soil blowing. Barriers placed at right angles to prevailing currents at intervals of about 15 times their height are effective in controlling soil blowing.

APPENDIX P-4 - STANDARD SEQUENCE OF CONSTRUCTION

- Temporary erosion and sedimentation controls are to be installed as indicated on the approved site plan in accordance with the Erosion Sedimentation Control Plan (ESC) that is required to be posted on the site. Install tree protection, initiate tree mitigation measures and conduct "Pre-Construction" tree fertilization (if applicable).
  - The Environmental Project Manager or Site Supervisor must contact the Development Services Department, Environmental Inspection, at 512-974-2278, 72 hours prior to the scheduled date of the required on-site preconstruction meeting.
  - The Environmental Project Manager, and/or Site Supervisor, and/or Designated Responsible Party, and the General Contractor will follow the Erosion Sedimentation Control Plan (ESC) posted on the site. Temporary erosion and sedimentation controls will be revised, if needed, to comply with City Inspectors' directives, and revised construction schedule relative to the water quality plan requirements and the erosion plan.
  - Rough grade the pond(s) at 100% proposed capacity. Either the permanent outlet structure or a temporary outlet must be constructed prior to development of embankment or excavation that leads to ponding conditions. The outlet system must consist of a sump pit outlet and an emergency spillway meeting the requirements of the Drainage Criteria Manual and/or the Environmental Criteria Manual, as required. The outlet system shall be protected from erosion and shall be maintained throughout the course of construction.
  - Temporary erosion and sedimentation controls will be inspected and maintained in accordance with the Erosion Sedimentation Control Plan (ESC) and Storm Water Pollution Prevention Plan (SWPPP) posted on the site.
  - Begin site clearing/construction (or demolition) activities.
  - In the Barton Springs Zone, the Environmental Project Manager or Site Supervisor will schedule a mid-construction conference to coordinate changes in the construction schedule and evaluate effectiveness of the erosion control plan after possible construction alterations to the site. Participants shall include the City Inspector, Project Engineer, General Contractor, and Environmental Project Manager or Site Supervisor. The anticipated completion date and final construction sequence and inspection schedule will be coordinated with the appropriate City Inspector.
  - Permanent water quality ponds or controls will be cleaned out and filter media will be installed prior to/concurrently with revegetation of site.
  - Complete construction and start revegetation of the site and installation of landscaping.
  - Upon completion of the site construction and revegetation of a project site, the design engineer shall submit to the City Engineer's letter of concurrence bearing the engineer's seal, signature, and date to the Development Services Department indicating that construction, including revegetation, is complete and in substantial compliance with the approved plans. After receiving this letter, a final inspection will be scheduled by the appropriate City inspector.
  - Upon completion of landscape installation of a project site, the Landscape Architect shall submit a letter of concurrence to the Development Services Department indicating that the required landscaping is complete and in substantial conformity with the approved plans. After receiving this letter, a final inspection will be scheduled by the appropriate City inspector.
  - After a final inspection has been conducted by the City inspector and with approval from the City inspector, remove the temporary erosion and sedimentation controls and complete any necessary final revegetation resulting from removal of the controls.
- Source: Rule No. R161-17.03, 3-2-2017.

APPENDIX P-6 - REMEDIAL TREE CARE NOTES AERATION AND SUPPLEMENTAL NUTRIENT REQUIREMENTS FOR TREES WITHIN CONSTRUCTION AREAS

As a component of an effective remedial tree care program per Environmental Criteria Manual section 3.5.4, preserved trees within the limits of construction may require soil aeration and supplemental nutrients. Soil and/or foliar analysis should be used to determine the need for supplemental nutrients. The City Arborist may require these analyses as part of a comprehensive tree care plan. Soil pH shall be considered when determining the fertilization composition as soil pH influences the tree's ability to uptake nutrients from the soil. If analyses indicate the need for supplemental nutrients, then humate/nutrient solutions with mycorrhizae components are highly recommended. In addition, soil analysis may be needed to determine if organic material or beneficial microorganisms are needed to improve soil health. Materials and methods are to be approved by the City Arborist (512-974-1876) prior to application. The owner or general contractor shall select a fertilization contractor and ensure coordination with the City Arborist.

Pre-construction treatment should be applied in the appropriate season. Ideally the season preceding the proposed construction. Minimally, areas to be treated include the entire critical root zone of trees as depicted on the City approved plans. Treatment should include, but not limited to, fertilization, soil treatment, mulching, and proper pruning.

Post-construction treatment should occur during final revegetation or as determined by a qualified arborist after construction. Construction activities often result in a reduction in soil macro and micro pores and an increase in soil bulk density. To ameliorate the degraded soil conditions, aeration via water and/or air injected into the soil is needed or by other methods as approved by the City Arborist. The proposed nutrient mix specifications and soil and/or foliar analysis results need to be provided to and approved by the City Arborist prior to application (Fax # 512-974-3010). Construction which will be completed in less than 90 days may use materials at 1/2 recommended rates. Alternative organic fertilizer materials are acceptable when approved by the City Arborist. Within 7 days after fertilization is performed, the contractor shall provide documentation of the work performed to the City Arborist, Planning and Development Review Department, P.O. Box 1008, Austin, TX 78767. This note should be referenced as Item #1 in the Sequence of Construction.

ADDITIONAL SITE MANAGEMENT PRACTICES

- In addition to the temporary erosion controls shown hereon, the contractor shall install and maintain throughout the construction period and until final stabilization of disturbed areas other temporary controls interior to the site to prevent soil loss. Such additional controls shall include protection of drainage inlets, silt fences to prevent soil migration onto completed roadways and rock berms in locations with concentrated runoff.
- If disturbed area is not to be worked on for more than 14days, the contractor shall stabilize disturbed areas revegetation, mulch, tarp or revegetation matting. [ECM 1.4.4.B.3, Section 5, I]
- Environmental Inspector has the authority to add and/or modify erosion/sedimentation controls on site to keep project in-compliance with the city of austin rules and regulations. [LDC 25-8-183]
- Contractor shall utilize dust control measures during site construction such as irrigation trucks and mulching as per ECM 1.4.5 (A), or as directed by the Environmental Inspector.
- The contractor shall clean up spoils that migrate onto the roads a minimum of once daily. [ECM 1.4.4.d.4]

SPECIAL CONSTRUCTION TECHNIQUES ECM 3.5.4 (D)

In conjunction with remedial care, mitigation for trees removed may include special construction techniques not normally required in standard specifications. Some of these techniques include the following:

- Prior to excavation within tree driplines or the removal of trees adjacent to other trees that are to remain, make a clean cut between the disturbed and undisturbed root zones with a rock saw or similar equipment to minimize root damage.
- In critical root zone areas that cannot be protected during construction with fencing and where heavy vehicular traffic is anticipated, cover those areas with a minimum of 12 inches of organic mulch to minimize soil compaction. In areas with high soil plasticity Geotextile fabric, per standard specification 620S, should be placed under the mulch to prevent excessive mixing of the soil and mulch. Additionally, material such as plywood and metal sheets, could be required by the City Arborist to minimize root impacts from heavy equipment. Once the project is completed, all materials should be removed, and the mulch should be reduced to a depth of 3 inches.
- Perform all grading within critical root zone areas by hand or with small equipment to minimize root damage.
- Water all trees most heavily impacted by construction activities deeply once a week during periods of hot, dry weather. Spray tree crowns with water periodically to reduce dust accumulation on the leaves.
- When installing concrete adjacent to the root zone of a tree, use a plastic vapor barrier behind the concrete to prohibit leaching of lime into the soil.

ADDITIONAL NOTES

If disturbed area is not to be worked on for more than 14 days, disturbed area needs to be stabilized by revegetation, mulch, tarp or revegetation matting. [ECM 1.4.4.B.3, Section 5, I]

Environmental Inspector shall have the authority to add and/or modify erosion/sedimentation controls on site to keep project in-compliance with the City of Austin Rules and Regulations. [LDC 25-8-183]

Contractor shall utilize dust control measures during site construction such as irrigation trucks and mulching as per ECM 1.4.5.(A), or as directed by the Environmental Inspector.

The contractor will clean up spoils that migrate onto the roads a minimum of once daily.

The contractor is responsible for removing any sediment transported from the LOC to the existing detention / water quality pond(s).

Only rubber tired equipment is allowed within the CWQZ and Floodplain. No track equipment is allowed."

All equipment and spoils are to be removed from the creek, the CWQZ, and 100 year floodplain nightly. [ECM 1.4.4.D.4]

GENERAL CONSTRUCTION NOTES

- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.
- CONTRACTOR SHALL CALL THE ONE CALL CENTER (472-2822) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W.
- CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTION DIVISION OF THE CITY'S ONE STOP SHOP (OSS) AT 974-6300 OR 974-1034 AT LEAST 24 HOURS PRIOR TO THE INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE EASEMENT OR STREET R.O.W. THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S R.O.W. MUST BE APPROVED PRIOR TO THE START OF BACKFILL OPERATIONS.
- FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH, A NOTE MUST BE ADDED STATING: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION." (OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE. INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN TEXAS.)
- ALL SITE WORK MUST ALSO COMPLY WITH ENVIRONMENTAL REQUIREMENTS.
- UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS AND PRIOR TO THE FOLLOWING, THE ENGINEERS SHALL CERTIFY IN WRITING THAT THE PROPOSED DRAINAGE, FILTRATION AND DETENTION FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS:-  
-RELEASE OF THE CERTIFICATE OF OCCUPANCY BY THE DEVELOPMENT SERVICES DEPARTMENT (INSIDE THE CITY LIMITS);  
-OR INSTALLATION OF AN ELECTRIC OR WATER METER (IN THE FIVE-MILE ETJ)
- DEVELOPER INFORMATION  
-OWNER: AUSTIN PARKS AND RECREATION DEPARTMENT  
ADDRESS: 200 S LAMAR BLVD. AUSTIN, TX 78704  
PHONE: (512) 974-6700  
-OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: DUNAWAY/UDG (512) 306-8252  
-PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE: \_\_\_\_\_  
PHONE: \_\_\_\_\_  
-PERSON OR FIRM RESPONSIBLE FOR TREENATURAL AREA PROTECTION MAINTENANCE: \_\_\_\_\_  
PHONE: \_\_\_\_\_
- AUSTIN ENERGY HAS THE RIGHT TO PRUNE AND/OR REMOVE TREES SHRUBBERY AND OTHER OBSTRUCTIONS TO THE EXTENT NECESSARY TO KEEP THE EASEMENTS CLEAR OF OBSTRUCTIONS. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING, AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8, SUBCHAPTER B OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER/DEVELOPER OF THIS LOT SHALL PROVIDE AUSTIN ENERGY WITH ANY EASEMENT AND/OR ACCESS REQUIRED, IN ADDITION TO THOSE INDICATED, FOR THE INSTALLATION AND ONGOING MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES TO SERVICE THIS PROPERTY. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING, AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8 OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER SHALL BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY EROSION CONTROL, RE-VEGETATION, AND TREE PROTECTION. IN ADDITION, THE OWNER SHALL BE RESPONSIBLE FOR ANY INITIAL TREE PRUNING AND TREE REMOVAL THAT IS WITHIN TEN FEET OF THE CENTERLINE OF THE PROPOSED OVERHEAD ELECTRICAL FACILITIES DESIGNED TO PROVIDE ELECTRIC SERVICE TO THIS PROJECT. THE OWNER SHALL INCLUDE AUSTIN ENERGY'S WORK WITHIN THE LIMITS OF CONSTRUCTION FOR THIS PROJECT.
- THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRIC SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS, CITY OF AUSTIN RULES AND REGULATIONS AND TEXAS STATE LAWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES AND EQUIPMENT. AUSTIN ENERGY WILL NOT RENDER ELECTRIC SERVICE UNLESS REQUIRED CLEARANCES ARE MAINTAINED. ALL COSTS INCURRED BECAUSE OF FAILURE TO COMPLY WITH THE REQUIRED CLEARANCES WILL BE CHARGED TO THE OWNER.
- THE CONTRACTOR IS RESPONSIBLE FOR TEMPORARY RIGHT-OF-WAY PERMIT FOR CONSTRUCTION OF SIDEWALKS AND DRIVEWAY(S).
- OWNER IS RESPONSIBLE FOR ALL COSTS OF RELOCATION OF, OR DAMAGE TO, UTILITIES. ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE. WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY THE CITY OF AUSTIN. ALL EXISTING STRUCTURES SHOWN TO BE REMOVED WILL REQUIRE A DEMOLITION PERMIT FROM THE CITY OF AUSTIN WATERSHED PROTECTION AND DEVELOPMENT REVIEW DEPARTMENT.
- FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH, ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- RETAINING WALLS OVER FOUR FEET IN HEIGHT, MEASURED FROM THE BOTTOM OF THE FOOTING TO THE TOP OF THE WALL, SHALL BE ENGINEERED AND WILL REQUIRE A SEPARATE PERMIT.
- ALL CONSTRUCTION WITHIN CITY OF AUSTIN RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD SPECIFICATIONS.
- THE CONTRACTOR, AT HIS EXPENSE, WILL REPAIR ANY EXISTING PAVEMENT, CURBS, AND/OR SIDEWALKS DAMAGED OR REMOVED.
- THE LOCATION OF ANY WATER AND/OR WASTEWATER LINES SHOWN ON THE PLANS MUST BE VERIFIED BY THE WATER AND WASTEWATER DEPARTMENT.
- ALL STORM SEWER PIPES SHALL BE CLASS III RCP UNLESS NOTED OTHERWISE.
- TRENCHES WITHIN THE RIGHT-OF-WAY SHALL BE BACKFILLED OR SUFFICIENTLY PROTECTED BY TRAFFIC BEARING PLATES AFTER THE CONCLUSION OF EACH DAYS WORK.
- TRENCHES TO 15-12-131 OF THE CITY CODE, THE CONTRACTOR MAY NOT BLOCK, DIRECT, IMPEDE, OR REROUTE PEDESTRIAN AND VEHICULAR TRAFFIC, NOR PLACE A BARRICADE OR OTHER TRAFFIC CONTROL DEVICE IN A RIGHT-OF-WAY, WITHOUT FIRST OBTAINING A TEMPORARY USE OF RIGHT-OF-WAY PERMIT FROM THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION.
- FOR DRIVEWAY CONSTRUCTION: THE OWNER IS RESPONSIBLE FOR ALL COSTS FOR RELOCATION OF, OR DAMAGE TO UTILITIES.
- SPOILS IN THE RIGHT-OF-WAY MUST BE REMOVED ON A DAILY BASIS. NO SPOILS MAY BE STORED IN THE RIGHT-OF-WAY OVER NIGHT.

ACCESSIBILITY SITE NOTES

SITE GRADING SHALL COMPLY WITH THE TEXAS ACCESSIBILITY STANDARDS EXISTING AT THE TIME OF PLAN APPROVAL. GRADING SHOWN ON THE PLANS IS INTENDED TO COMPLY WITH SUCH STANDARDS AND SHOULD THE CONTRACTOR DETERMINE THAT COMPLIANCE WITH THE STANDARDS IS NOT CONSISTENT WITH THE SITE PLAN OR ELEVATIONS, HE/SHE SHALL NOTIFY THE ENGINEER IMMEDIATELY FOR A REMEDY.

ACCESSIBLE ROUTES (SIDEWALKS, PATHS, ETC)

- THE MAXIMUM SLOPE OF A RAMP IN NEW CONSTRUCTION IS 1:12. THE MAXIMUM RISE FOR ANY RAMP RUN IS 30 IN. THE MAXIMUM HORIZONTAL PROJECTION IS 30 FEET FOR A RAMP WITH A SLOPE BETWEEN 1:12 AND 1:15, AND 40 FEET FOR A RAMP WITH A SLOPE BETWEEN 1:16 AND 1:20.
- CROSS SLOPE SHALL NOT EXCEED 1:50 (2%).
- GROUND SURFACES SHALL BE RELATIVELY FIRM, STABLE AND SMOOTH. GRANITE PATHS WHERE SHOWN ON THE PLANS SHALL BE SUFFICIENTLY COMPACTED.
- CHANGES IN LEVEL SHALL NOT EXCEED 1/2" . 12" \* CHANGE IN LEVEL MUST HAVE A BEVELED EDGE OF 1:2. 1/4" \* CHANGE IN LEVEL OR LESS DOES NOT HAVE TO PROVIDE A BEVELED EDGE.
- MANEUVERING CLEARANCE (60") AT ACCESSIBLE ENTRANCES SHALL NOT EXCEED 1:50 (2% SLOPE).
- A 60" X 60" PASSING SPACE SHALL BE PROVIDED EVERY 200' ALONG AN ACCESSIBLE ROUTE.

PARKING

- SLOPE IN ACCESSIBLE PARKING AREAS (PARKING SPACE AND ACCESS AISLE) SHALL NOT EXCEED 1:50 (2%) SLOPE IN ALL DIRECTIONS.
- EACH ACCESSIBLE PARKING SPACE SHALL PROVIDE AN ADJACENT ACCESS AISLE (5' FOR STANDARDS ACCESSIBLE SPACES AND 8' FOR VAN ACCESSIBLE SPACES).
- EVERY ACCESSIBLE PARKING SPACE MUST BE IDENTIFIED BY A SIGN, CENTERED AT THE HEAD OF THE PARKING SPACE. THE SIGN MUST INCLUDE THE INTERNATIONAL SYMBOL OF ACCESSIBILITY AND STATE "RESERVED", OR OTHER EQUIVALENT LANGUAGE. CHARACTERS AND SYMBOLS ON SUCH SIGNS MUST BE LOCATED 60" MINIMUM ABOVE THE GROUND SO THAT THEY CANNOT BE OBSCURED BY A VEHICLE PARKED IN THE SPACE.
- WHERE THE ACCESSIBLE ROUTE PASSES IN FRONT OF VEHICLES, WHEEL STOPS SHALL BE PROVIDED TO PREVENT VEHICLES FROM PULLING UP AND BLOCKING THE ACCESSIBLE ROUTE. ENOUGH SPACE SHALL BE ALLOWED TO MAINTAIN A MINIMUM OF 36" WIDE ACCESSIBLE ROUTE.
- CURB RAMPS  
1. SLOPE SHALL NOT EXCEED 1:12 (8.3%). FLARED SIDES SHALL NOT EXCEED 1:10. CROSS SLOPE SHALL TO EXCEED 1:50 (2%).
- FULL WIDTH AND DEPTH OF CURB RAMP SURFACES SHALL PROVIDE A CONTRASTING LIGHT REFLECTIVE VALUE (COLOR) AND TEXTURE. TEXTURE MAY CONSIST OF TRUNCATED DOMES OR 3/4" WIDE GROOVES, 1/4" DEEP AND 2" APART. COLOR SHALL CONTRAST AT LEAST 70% FROM ADJACENT SURFACES.
- MINIMUM RAMP WIDTH SHALL BE 36".
- WHERE AN ACCESSIBLE ROUTE CROSSES A CURB RAMP, IT SHALL CIRCUMVENT THE CURB RAMP SO AS TO NOT REQUIRE THE USER TO CROSS OVER THE CURB RAMP.
- CURB RAMPS ARE NOT PERMITTED TO PROJECT INTO THE ACCESSIBLE PARKING ACCESS AISLES.
- TRANSITIONS FROM GUTTER OR STREET TO CURB RAMPS SHALL BE FLUSH.
- OTHER RAMPS  
1. MAXIMUM SLOPE SHALL BE 1:12 (8.3%).
- RAMPS OVER 6' IN LENGTH REQUIRE HANDRAILS ON BOTH SIDES.
- HANDRAIL HEIGHT SHALL BE 34" - 36" ABOVE RAMP SURFACE.
- HANDRAIL DIAMETER - 1.25" TO 1.5".
- EDGE PROTECTION IS REQUIRED WHERE DROP OFFS OCCUR.
- MINIMUM HANDRAIL EXTENSIONS ARE REQUIRED AT LANDINGS, EXCEPT WHERE HANDRAILS ARE CONTINUOUS. HANDRAIL EXTENSIONS SHALL EXTEND IN THE SAME DIRECTION AS THE RAMP.
- MAXIMUM RUN BETWEEN LANDINGS SHALL BE 30'.
- 60" LEVEL (2% MAX. SLOPE) LANDINGS REQUIRED AT TOP AND BOTTOM OF EACH RUN. A 60" X 60" LANDING REQUIRED WHERE A RAMP CHANGES DIRECTION.


TRAFFIC CONTROL NOTES

PURSUANT TO 15-12-131 OF THE CITY CODE, THE CONTRACTOR MAY NOT BLOCK, DIRECT, IMPEDE, OR REROUTE PEDESTRIAN AND VEHICULAR TRAFFIC, NOR PLACE A BARRICADE OR OTHER TRAFFIC CONTROL DEVICE IN A RIGHT-OF-WAY, WITHOUT FIRST OBTAINING A TEMPORARY USE OF RIGHT-OF-WAY PERMIT FROM THE TEMPORARY TRAFFIC CONTROL SECTION OF THE DEPARTMENT OF TRANSPORTATION PLANNING AND SUSTAINABILITY.

CONTRACTOR SHALL NOTIFY THE TEMPORARY TRAFFIC CONTROL SECTION OF THE DEPARTMENT OF TRANSPORTATION PLANNING AND SUSTAINABILITY (974-2217) AT LEAST 24 HOURS PRIOR TO THE INSTALLATION OF ANY BARRICADE OR OTHER TRAFFIC CONTROL DEVICE IN A RIGHT-OF-WAY.

SEQUENCE OF CONSTRUCTION

- COORDINATE WITH OWNER AND "DIG TESS" TO IDENTIFY EXISTING UTILITIES.
- INSTALL TEMPORARY EROSION CONTROL DEVICES.
- ARRANGE A PRE-CONSTRUCTION CONFERENCE WITH A CITY OF AUSTIN GENERAL PERMIT INSPECTOR.
- PERFORM PAVEMENT CONSTRUCTION OF ROADWAY WIDTH REDUCTION, INSTALLATION OF PAVILION AND TREE OUTLOOK DECK, AND FINAL GRADING OF SITE.
- REVEGETATE ALL DISTURBED AREAS.
- REMOVE TEMPORARY EROSION CONTROL DEVICES.
- DRESS UP AND RESTORE ANY AREAS DISTURBED BY ITEM 6 ABOVE.



NEW SHEET



REVISION DESCRIPTION

DATE

BY

REV. NO.

VIOLET CROWN TRAILHEAD  
WILLIAM BARTON DR.  
AUSTIN TX 78746

GENERAL NOTES

TX Registered Engineering Firm #F-11114  
TPLS Firm No. 10065900  
5707 Southwest Parkway  
Building 2, Suite 250  
Austin, TX 78735  
Phone: 512-306-8252

JOE NO. B005344.001

C0.01

SPEC-2012-0104D(R5)

SHEET NUMBER

219 OF 239

Site Plan Approval

FILE NUMBER: \_\_\_\_\_

APPROVED BY COMMISSION ON: \_\_\_\_\_

CHAPTER 25-5 OF THE CITY OF AUSTIN CODE

EXPIRATION DATE (25-481, LDC) \_\_\_\_\_

PROJECT EXPIRATION DATE (OED #97905-A) \_\_\_\_\_

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_

Revised: \_\_\_\_\_


Revised: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

SHEET

219 OF 239





**LEGEND**

- LIMIT OF CONSTRUCTION
- \*\*\*\*\* CURB & GUTTER DEMO & REMOVAL
- GRAVEL TRAIL REMOVAL
- ASPHALT PAVEMENT DEMO AND REMOVAL
- CURRENT CONSTRUCTION UNDER SPC-2012-0104-DIR3
- TREE TO REMAIN- 8" OR >
- TREE TO BE REMAIN- < 8"
- TREE TO BE REMOVED
- HERITAGE TREE

**NOTES**

1. CALL AUSTIN ONE CALL CENTER AT 1-800-545-6005 FOR ALL EXISTING UTILITY LOCATIONS PRIOR TO BEGINNING ANY WORK.
2. THE CONTRACTOR SHALL FIELD VERIFY WATER, WASTEWATER, ELECTRIC, AND OTHER UTILITY LOCATIONS PRIOR TO CONSTRUCTION.
3. ANY PUBLIC UTILITY FOUND TO BE IN CONFLICT WITH PROPOSED IMPROVEMENTS SHALL BE SUBMITTED TO THE PROPER REVIEW AUTHORITY FOR REVIEW AND APPROVAL PRIOR TO ANY UTILITIES BEING RELOCATED.
4. FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH, ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
5. THE CONTRACTOR, AT HIS EXPENSE, WILL REPAIR ANY EXISTING PAVEMENT, CURBS, FENCES AND SIDEWALKS DAMAGED OR REMOVED.
6. THE CONTRACTOR SHALL FIELD VERIFY PIPE FLOWLINE ELEVATIONS PRIOR TO CONSTRUCTION.
7. A PRECONSTRUCTION MEETING WITH THE ENVIRONMENTAL INSPECTOR IS REQUIRED PRIOR TO ANY SITE DISTURBANCE.
8. DEMOLITION WITHIN THE CRZ OF PROTECTED/HERITAGE TREES TO BE DONE WITH HAND TOOLS OR SMALL EQUIPMENT.

TREE LIST				
DATE OF TREE SURVEY: 08/29/2020				
TO BE REMOVED	TREE #	(HERITAGE) (PROTECTED)	SIZE	SPECIES
	3050	P	20.0'	PECAN
	3051	P	26.0'	WHITE MULLBERRY
	3052	P	12.0'	PECAN
	3053	P	10.5'	AMERICAN ELM
	3054	P	17.5'	AMERICAN ELM
	3055	P	12.0'	AMERICAN ELM
	3056	P	11.0'	AMERICAN ELM
	3057	P	16.5'	CHINESE PISTACHE
	3058	H	39.0'	PECAN
	3059	P	26.0'	MESQUITE
	3060	P	10.0'	LIVE OAK
X	3061	P	8.5'	LIVE OAK
	3062	P	8.0'	LIVE OAK
X	3068	P	30.0'	MESQUITE
	3069	P	21.3'	MESQUITE
	3070	P	9.8'	PECAN
	3071	P	9.8'	PECAN
	3072	P	9.3'	MESQUITE
	3073	P	14.3'	HACKBERRY
	3074	P	8.5'	HACKBERRY
	3075	P	13.0'	MESQUITE
	3076	P	12.2'	LIVE OAK
	3077	P	17.0'	CEDAR ELM
	3078	P	14.3'	CEDAR ELM
	3079	P	4.5'	PECAN
	3080	P	4.5'	HACKBERRY
	3081	P	8.5'	HACKBERRY
	3082	P	7.0'	PECAN
	3083	P	6.5'	GREEN ASH
	3084	P	6.5'	CHINA BERRY
	3085	P	4.5'	AMERICAN ELM
	3086	P	5.0'	CHINESE PISTACHE
X	3087	P	8.0'	ASH JUMPER
	3088	P	4.0'	MESQUITE
	3089	P	4.0'	CEDAR ELM
	3090	P	5.5'	HACKBERRY
	3091	P	4.0'	HACKBERRY
	3092	P	6.7'	HACKBERRY
	3093	P	12.5'	MESQUITE
	30932	P	22.8'	CREPE MYRTLE
	30933	P	8.8'	CREPE MYRTLE
	30934	P	9.0'	CREPE MYRTLE
	30935	P	15.3'	CREPE MYRTLE
	30936	P	12.5'	CREPE MYRTLE
	30937	P	13.5'	CREPE MYRTLE
	30938	P	17.0'	CREPE MYRTLE
X	30939	P	7.8'	CREPE MYRTLE
X	30940	P	14.8'	CREPE MYRTLE
	30941	P	6.0'	LIVE OAK
	30942	P	6.0'	LIVE OAK
	30943	P	5.0'	CEDAR ELM
	30944	P	5.0'	LIVE OAK
	30945	P	2.5'	LIVE OAK
	30946	P	4.0'	LIVE OAK
	30947	P	4.0'	LIVE OAK
	30948	P	8.0'	LIVE OAK
	30949	P	7.0'	LIVE OAK
	30950	P	2.5'	MESQUITE
X	30951	P	5.75'	CHINKAPIN OAK
	30952	P	6.5'	CHINKAPIN OAK
X	30953	P	6.0'	CHINKAPIN OAK
	30954	P	13.5'	CHINKAPIN OAK
	30955	P	5.0'	CHINKAPIN OAK
	30956	P	4.5'	LIVE OAK
	30957	P	7.0'	LIVE OAK
	30958	P	4.5'	HACKBERRY
	30959	P	3.0'	CEDAR ELM
	30960	P	5.3'	MOUNTAIN LAUREL
	30971	P	8.0'	MOUNTAIN LAUREL
	30972	P	5.5'	MOUNTAIN LAUREL
	30973	P	6.5'	MOUNTAIN LAUREL
	30974	P	5.0'	MOUNTAIN LAUREL
	30975	P	3.5'	MOUNTAIN LAUREL
	30976	P	3.5'	HACKBERRY
	30977	P	4.8'	HACKBERRY
	30980	H	34.5'	LIVE OAK
	30991	H	26.0'	LIVE OAK
	30992	P	21.2'	LIVE OAK
	30993	P	18.1'	LIVE OAK
	30994	P	22.4'	LIVE OAK
X	30995	P	6.5'	YALPON HOLLY
	30996	P	13.8'	PECAN

REVISION DESCRIPTION

REV. NO.	DATE	BY	DESCRIPTION

DATE: 12/16/2021

SCALE 1" = 30'

VIOLET CROWN TRAILHEAD  
WILLIAM BARTON DR.  
AUSTIN TX 78746

**EXISTING CONDITIONS & DEMOLITION PLAN**

**DUNAWAY UDOG**

TX Registered Engineering Firm #F-11114  
TPELS Firm No. 10065900  
5707 Southwest Parkway  
Building 2, Suite 250  
Austin, TX 78735  
Phone: 512-366-8252

**C0.10**

JOB NO. B005344.001

SPC-2012-0104D(R5)

SHEET NUMBER 220 OF 239

**REVIEWED**  
December 28, 2021  
*Jaron Hogenson*  
Austin Water



**NEW SHEET**

SITE PLAN APPROVAL SHEET 220 OF 239

FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_

APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION 112 OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.

EXPIRATION DATE (25-5-81, LDC) CASE MANAGER: \_\_\_\_\_

PROJECT EXPIRATION DATE (OED #970905-A) N/A DWFP DOZ

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_


Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_

Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_

Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.





Impervious Cover Calculations	
Description	ft <sup>2</sup>
Existing Pavement and Concrete Sidewalk to be removed	-4852
Proposed Outdoor Facilities - Decked*	707
Proposed Concrete Sidewalk	284
Net Impervious Cover	-3861

\* Area shown is 50% of Outdoor Facilities Impervious Cover since they are decked.



LEGEND

- SITE PLAN BOUNDARY
- ACCESSIBLE ROUTE
- FIRE LANE
- LIMIT OF CONSTRUCTION
- CRUSHED GRANITE TRAIL
- CONCRETE SIDEWALK
- ACCESSIBLE PARKING W/ SIGN
- PARKING WHEEL STOP
- CURB RAMP
- FINISH FLOOR ELEVATION
- CURRENT CONSTRUCTION UNDER SPC-2012-0104-DIR3
- PLANTING AREA
- SEE SHEET L1
- FLAGSTONE WALKWAY
- SEE SHEET L1
- TREE >8"
- TREE <8"

NOTES

1. ALL EXTERIOR LIGHTING WILL BE FULL CUT-OFF AND FULLY SHIELDED IN COMPLIANCE WITH SUBCHAPTER E 2.5 AND WILL BE REVIEWED DURING BUILDING PLAN REVIEW. ANY CHANGE OR SUBSTITUTION OF LAMPLIGHT FIXTURES SHALL BE SUBMITTED TO THE DIRECTOR FOR APPROVAL IN ACCORDANCE WITH SECTION 2.5.2.1. INCLUDE FIGURE 34 SHOWING EXAMPLES OF FULLY-SHIELDED FIXTURES:





Figure 34: Examples of fully-shielded light fixtures.

REVISION	DESCRIPTION	DATE	BY	REV. NO.

STATE OF TEXAS  
MICHAEL C. MULLONE  
127850  
LICENSED PROFESSIONAL ENGINEER  
Mike Mullone  
12/16/2021



VIOLET CROWN TRAILHEAD  
WILLIAM BARTON DR.  
AUSTIN TX 78746  
**SITE PLAN**


**DUNAWAY UDOG**  
TX Registered Engineering Firm #F-1114  
TBPUS Firm No. 10065900  
5707 Southwest Parkway  
Building 2, Suite 250  
Austin, TX 78735  
Phone: 512-306-8252

**C1.00**

JOB NO. B005344.001

SPC-2012-0104D(R5)

SHEET NUMBER 221 OF 239



**INSET**  
SCALE: 1" = 30'

**R5**

**NEW SHEET**

**REVIEWED**  
December 28, 2021  
Jaron Hoggerson  
Austin Water


**AUSTIN FIRE DEPARTMENT**  
OUR MISSION GOES BEYOND OUR NAME  
ENGINEERING SERVICES REVIEW  
M. Lewis  
REVIEWER: M. Lewis DATE: 01/04/2022

SITE PLAN APPROVAL	SHEET 221 OF 239
FILE NUMBER: _____	APPLICATION DATE: _____
APPROVED BY COMMISSION ON: _____	UNDER SECTION 112 OF _____
CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.	
EXPIRATION DATE (25-5-81, LDC) _____	CASE MANAGER: _____
PROJECT EXPIRATION DATE (OED #970905-A) _____	N/A DWFP _____ DDZ _____

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_  
Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_  
Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_  
Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.






## NOTES

PHASE I IS ALL SITE WORK EXCLUDING THE PROPOSED OUTDOOR FACILITIES AND WQ POND. THIS WORK IS RESTRICTED TO CONSTRUCTION OF WILLIAM BARTON DRIVE, GRADING, TRAIL, FENCE AND GATE, AND THEIR ASSOCIATED LANDSCAPE. THIS WORK WILL BE SEPARATE FROM THE PROPOSED OUTDOOR FACILITIES AND WQ POND.

PHASE II WILL BE THE PROPOSED OUTDOOR FACILITIES AND WQ POND. THIS WORK WILL INCLUDE WQ POND LANDSCAPING.

[illegible]






SITE PLAN APPROVAL		SHEET		223	OF	239
FILE NUMBER: _____		APPLICATION DATE: _____				
APPROVED BY COMMISSION ON: _____		UNDER SECTION		112	OF	_____
CHAPTER <u>25-5</u> OF THE CITY OF AUSTIN CODE.						
EXPIRATION DATE (25-581.DLC) _____		CASE MANAGER: _____				
PROJECT EXPIRATION DATE (OED #070905-A) _____		N/A		DW/PZ		_____
				D/DZ		_____
Director, Development Services Department						
RELEASED FOR GENERAL COMPLIANCE: _____		ZONING: _____				
Rev 1: _____		Correction 1: _____				
Rev 2: _____		Correction 2: _____				
Rev 3: _____		Correction 3: _____				
<i>Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.</i>						

[illegible]

NEW SHEET

2/16/2021 G:\Production4000\005300\5344\001\Civil\CAD\ (Plans) Site Plan\Sheets\VCT-S-GRD.dgn




















Figure 6.64a Schematic of a skimmer, from Pennsylvania Erosion and Sediment Pollution Control Manual March, 2000.





EXISTING DRAINAGE MAP



PROPOSED DRAINAGE MAP

Time of Concentration Calculations								
Basin ID	Area	Z <sub>1</sub>	Z <sub>3</sub>	Z <sub>2</sub>	Z <sub>1</sub>	L <sup>sheet</sup>	L <sup>shallow</sup>	L <sup>channel</sup>
-	ac	ft	ft	ft	ft	ft	ft	ft
OS1	2.35	512	498	471	0	100	107	0
V	2.57	470	459	454	0	100	99	0
Sheet Flow Calculations								
P <sub>2</sub>	3.44	t <sup>sheet</sup>	(0.007*((n*L) <sup>.8</sup> )/(((P <sub>2</sub> ) <sup>.5</sup> )*(s <sup>.4</sup> ))*60					
Basin ID	Z <sub>1</sub>	Z <sub>3</sub>	L <sup>sheet</sup>	s <sup>sheet</sup>	n <sup>sheet</sup>	t <sup>sheet</sup>		
-	ft	ft	ft	-	-	min		
OS1	512	498	100	0.140	0.15	4.3		
V	470	459	100	0.110	0.15	4.8		
Shallow Flow Calculations								
t <sup>shallow</sup>			t <sup>unpaved</sup> = L/(60(16.1345)(s)0.5)			t <sup>paved</sup> = L/(60(20.3282)(s)0.5)		
Basin ID	Z <sub>3</sub>	Z <sub>2</sub>	L <sup>shallow</sup>		s <sup>shallow</sup>	t <sup>shallow</sup>		
-	ft	ft	ft		-	min		
OS1	498	471	107		0.252	0.2		
V	459	454	99		0.051	0.5		
*All basins -unpaved								
Channel Flow Calculations								
t <sup>channel</sup>	L/(60*v)		v <sup>channel</sup>	(1.49*(r <sup>.667</sup> )*(s <sup>.5</sup> ))/n				
Basin ID	Z <sub>2</sub>	Z <sub>1</sub>	L <sup>channel</sup>	s <sup>channel</sup>	r	n <sup>channel</sup>	v <sup>channel</sup>	t <sup>channel</sup>
-	ft	ft	ft	-	ft	-	ft/s	min
OS1	471	0	0	N/A	0.500	0.012	N/A	0
V	454	0	0	N/A	0.750	0.012	N/A	0
Time of Concentration Summary								
Basin ID	Area	t <sup>Total</sup>			t <sup>lag</sup>			
-	ac	min			min			
OS1	2.35	5			3			
V	2.57	5			3			
*OS1 had an assumed Time of Concentration of 5 minutes.								

Existing Hydrologic Summary								
Basin ID	Area	Impervious	CN <sub>weighted</sub>	ToC	Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>
-	ac.	%	-	min.	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s
OS1	2.4	13	82.3	5	9	17	22	31
V	2.6	4	62.6	5	4	11	16	26
Proposed Hydrologic Summary								
Basin ID	Area	Impervious	CN <sub>weighted</sub>	ToC	Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>
-	ac.	%	-	min.	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s	ft <sup>3</sup> /s
OS1	2.35	13	82.3	5	9	17	22	31
V	2.57	1	61.3	5	3	10	16	25
Point of Analysis - To Barton Creek					Q <sup>2</sup>	Q <sup>10</sup>	Q <sup>25</sup>	Q <sup>100</sup>
Existing					13.0	27.8	38.5	56.8
Proposed					12.6	27.2	37.9	56.1
Proposed - Existing					-0.4	-0.6	-0.6	-0.7

- LEGEND
- X = XX ac. DRAINAGE AREA ID
- DRAINAGE AREA
- CONTOUR - EXISTING
- CONTOUR - PROPOSED
- FLOW - EXISTING
- FLOW - PROPOSED

SITE PLAN APPROVAL

FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_ SHEET 226 OF 239

APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION 112 OF

CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.

EXPIRATION DATE (25-5-81, LDC) \_\_\_\_\_ CASE MANAGER: \_\_\_\_\_

PROJECT EXPIRATION DATE (OED #97905-A) \_\_\_\_\_ N/A DWFPZ \_\_\_\_\_ DDZ \_\_\_\_\_

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_

Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_

Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

R5

NEW SHEET

REVISION DESCRIPTION

DATE

BY

REV. NO.

APPROVED

DATE 12/16/2021

12/16/2021

SCALE 1" = 50'

0 25 50

VIOLET CROWN TRAILHEAD

WILLIAM BARTON DR.

AUSTIN TX 78746

EXISTING & PROPOSED DRAINAGE MAPS

DUNAWAY UDOG

TX Registered Engineering Firm #F-11114

TBPLS Firm No. 10065900

5707 Southwest Parkway

Building 2, Suite 250

Austin, TX 78735

Phone: 512-306-8252

C4.00

JOB NO. B005344.001


SPC-2012-0104D(R5)

SHEET NUMBER 226 OF 239










**A RAIN GARDEN PLAN**  
SCALE: 1" = 10'



**B RAIN GARDEN SECTION**  
SCALE: H1" = 10' V1" = 5'



**C RAIN GARDEN OVERFLOW OUTLET**  
SCALE:

**LEGEND**

FL	FLOW LINE
WEIR	TOP OF WEIR
XXX.X	ELEVATION
TC	TOP OF GABION
XXX	CONTOUR
@	CLEANOUT, TYP.
---	COLLECTOR LINE
SIS	STORM DRAIN

**NOTES**

1. SEE POND DETAILS SHEET C5.10
2. WATER QUALITY POND WILL BE PRIVATELY MAINTAINED.
3. BIOFILTRATION MEDIUM SHALL COMPLY WITH ECM 1.3.7.C.4(A).
4. THE CONTRACTOR SHALL PROVIDE TO DUNAWAY AN AS-BUILT DRAWING SIGNED BY A REGISTERED PUBLIC LAND SURVEYOR OF THE WATER QUALITY POND PRIOR TO ENGINEER'S CONCURRENCE TO THE CITY OF AUSTIN. THE SURVEY SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL POND DIMENSIONS, TOP OF POND ELEVATIONS, ALL PIPE SIZES AND ELEVATIONS, WEIR DIMENSIONS AND ELEVATIONS, AND ANY OTHER MEASUREMENT NECESSARY TO CONFIRM THAT POND APPURTENANCES WERE BUILT PER APPROVED PLANS.
5. POND PLANTING PLAN ON SHEETS -----

COA APPENDIX R-11 RAIN GARDEN CALCULATIONS FOR DEVELOPMENT PERMITS					
Violet Crown Trailhead - R2					
<b>DRAINAGE AREA DATA: R2</b>					
Drainage Area to Control (DA - Maximum 2.0 ac.)	0.02	ac.			
Drainage Area Percent Impervious Cover	100	%			
Capture Depth (CD)	1.30	in.			
Required Capture Depth per SLAT for Barton Springs Zone	2.54	in.			
<b>WATER QUALITY CONTROL CALCULATIONS:</b>					
Water Quality Volume (WQV)	184	ft <sup>3</sup>	265	ft <sup>3</sup>	
100 Year Peak Flow Rate to Control (Q100)		ft <sup>3</sup> /s			
Filtration Pond Area (A <sub>f</sub> )	214	ft <sup>2</sup>	308	ft <sup>2</sup>	
Depth of Ponding (D)	Max. 1.0	ft.	0.50	ft.	
Depth of Filtration Media (L)	Min. 1.5	ft.	1.5	ft.	
Effective Porosity Water Quality Volume (WQV <sub>eff</sub> = 0.24*A <sub>f</sub> *L)			111	ft <sup>3</sup>	
Ponded Water Quality Volume (WQV <sub>ponded</sub> = WQV - WQV <sub>eff</sub> )			154	ft <sup>3</sup>	
Water Quality Elevation (WQE)	Provided WQV		265	ft <sup>3</sup>	
Elevation of Splitter/Overflow Weir (minimum WQE)			496.75	ft.	
			496.75	ft.	
Length of Splitter Weir				ft.	
Required Head to Pass Q100			0.08	ft.	
Pond Freeboard Provided to Pass Q100	Min. 0.25	ft.	0.42	ft.	
<b>FILTRATION RAIN GARDENS</b>					
Rain Garden Pond Drawdown Time (at 0.25 in./hr.)	Min. 48	hr.	48	hr.	
Underdrain Orifice Size (Diameter)			0.19	in.	
Underdrain Orifice (Area)			0.03	in <sup>2</sup>	

**SLAT** STORMWATER LOAD ANALYSIS TOOL 2.0

Quick Guide

1. Enable Macros in the worksheet.
2. Click "Restore Defaults" button to the right.
3. Fill all yellow cells with project specifics, moving from top to bottom.
4. Click "View Full Results" button.
5. Project Passes if Green "COMPLIANT" button appears.

Find the Full User Manual at [austintexas.gov/departments/stormwater-management](http://austintexas.gov/departments/stormwater-management)  
Questions? Email [SLAT@austintexas.gov](mailto:SLAT@austintexas.gov)

Click Here To Restore Defaults For a New Analysis

Click Here To View Results

KEY

Required User Input

Internal Calculation

Error

Calculator Output

Does Not Apply

Step 1: Input site characteristics in yellow highlighted cells

Violet Crown Trailhead

Mike Mullone

6/3/2021

SLAT 2.0 - 3/2018

Is your site within the Barton Springs Zone (BSZ)?  
How many drainage areas,  $n_{max}$ , does your site have?

Yes

1

1

Drainage area to the control,  $A_c$  (acres)  
Base impervious cover of the drainage area,  $IC_b$  (%)  
Developed impervious cover of the drainage area,  $IC_d$  (%)

0.02

0.0

100.0

Step 2: Input SCM characteristics in yellow highlighted cells

SCM 1 (First in Series)

SCM Type

Is SCM 1 off-line?

What is the Water Quality Volume, WQV (inches) aka Capture Depth?

Minimum water quality volume allowed (in)

SCM 1 Actual Volume (ft<sup>3</sup>)

Do you know the drawdown time or the flow rate?

Drawdown Time

Drawdown Time, DDT (hrs) [tot. time to empty full SCM]

Flow Rate (gpm) [use only for "alternative" controls]

Treatment Rate, Q (in/hr)

Do you already know the runoff capture efficiency?

User Entered Runoff Capture Efficiency, RCE (%)

Runoff Capture Efficiency, RCE (%)

Conveyance

How is effluent from SCM 1 discharged?

Delay after end of rainfall before discharging SCM 1 (hrs)

SCM 2 (Second in Series)

SCM Type

Do you know the infiltrated or reused water quantity?

User-entered inflit. water quality volume, WQV<sub>in</sub> (in)

-OR- Percent of yearly runoff infiltrated, RCE<sub>in</sub> (%)

Soil infiltration rate (in/hr)

Ratio of drawdown time / irrigation time, for any zone

Approximate Minimum Field Area (Ac)

Step 3: Input Effluent Data for Alternative SCMs

**SLAT** STORMWATER LOAD ANALYSIS TOOL 2.0 1/2

**SLAT** STORMWATER LOAD ANALYSIS TOOL 2.0 2/2

Site Name: Violet Crown Trailhead By: Mike Mullone Date: 4/2/20

Site Name: Violet Crown Trailhead By: Mike Mullone Date: 4/2/20

RESULTS: COMPLIANCE TABLE

RESULTS: PLOTS

POLLUTANT	Drainage Area A	Drainage Area B	Drainage Area C	Drainage Area D	TOTAL LOAD	EXISTING LOAD	LOAD FACTOR	COMPLIES ?
COD	lbs/yr	1.00E+01	0.00E+00	0.00E+00	1.03E-01	2.30E-01	0.45	YES
E. coli	10% MPN/l	1.53E+02	0.00E+00	0.00E+00	1.53E+02	2.34E+02	0.69	YES
Pb	lbs/yr	2.17E-05	0.00E+00	0.00E+00	2.17E-05	2.53E-05	0.86	YES
TN	lbs/yr	5.58E-03	0.00E+00	0.00E+00	5.58E-03	7.03E-03	0.79	YES
TP	lbs/yr	6.94E-04	0.00E+00	0.00E+00	6.94E-04	7.32E-04	0.95	YES
TSS	lbs/yr	7.80E-02	0.00E+00	0.00E+00	7.80E-02	9.80E-01	0.08	YES
Zn	lbs/yr	1.38E-04	0.00E+00	0.00E+00	1.38E-04	1.39E-04	0.99	YES

ERROR CHECK PASSED

COMPLIANT

Change Inputs

Print Results

Jump to Loads Removed Table

SUMMARY OF INPUTS

Site Location	Within Barton Springs Zone - Compare to Existing Loads	Drainage Area A	Drainage Area B	Drainage Area C	Drainage Area D	TOTALS
Drainage Area, An (Ac)	0.02	N/A	N/A	N/A	N/A	0.02
Developed IC, IC <sub>d</sub> (%)	100.0	N/A	N/A	N/A	N/A	100%
SCM 1	Biofiltration	N/A	N/A	N/A	N/A	-
Water Qual. Vol, WQV (in)	2.54	N/A	N/A	N/A	N/A	-
Actual Volume (ft <sup>3</sup> )	184	N/A	N/A	N/A	N/A	184
Drawdown Time, DDT (hrs)	48	N/A	N/A	N/A	N/A	-
Flowrate (gpm)	0.48	N/A	N/A	N/A	N/A	-
SCM 2	Infiltration Field	N/A	N/A	N/A	N/A	-
Infiltration Rate (in/hr)	0.10	N/A	N/A	N/A	N/A	-
Appx. Min. Infil. Field Area (Ac)	0.02	N/A	N/A	N/A	N/A	0.02
Average Irrigation Rate (gpm)	0.5	N/A	N/A	N/A	N/A	-
Error with Input Values?	NO	NO	NO	NO	NO	-

Load Equivalency Factor

POLLUTANT	Existing	Proposed
E. coli	2.54E+02	1.53E+02
Pb	2.17E-05	2.17E-05
TN	5.58E-03	5.58E-03
TP	6.94E-04	6.94E-04
TSS	7.80E-02	7.80E-02
Zn	1.38E-04	1.38E-04

ORIFICE CALCULATION FOR WQ POND DRAWDOWN TIME					
POND: Rain Garden					
WQV = water quality volume (ft <sup>3</sup> )	g = gravitational constant = (32.2 ft/s <sup>2</sup> )				
t = drawdown time (s)	pi = 3.1416				
Q = flow rate (ft <sup>3</sup> /s)	h = WQV / elevation	Y = minimum elevation in the sedimentation pond (ft)			
d = diameter of orifice (ft)	A = area of orifice (ft <sup>2</sup> )				
Or <sub>ave</sub> = orifice centerline elev.	C = orifice coefficient				
WQV (ft <sup>3</sup> )	265	t (hr)	48	g (ft/s <sup>2</sup> )	32.2
WQV <sub>in</sub> (ft <sup>3</sup> )	496.75	t (s)	172800	Or <sub>ave</sub> (ft)	494.10
Y <sub>min</sub> (ft)	496.25	C	0.6		
h (ft)	2.65				
Q = WQV/t = flow rate out of sedimentation pond					
Q (ft <sup>3</sup> /s)	0.0015				
Q = CA (2gh) <sup>0.5</sup> or A = Q / C * ((2gh) <sup>-0.5</sup> )					
A (ft <sup>2</sup> )	0.0002				
A (m <sup>2</sup> )	0.03				
A = pi*d <sup>2</sup> /4 or d = (4A/pi) <sup>0.5</sup>					
d (ft)	0.0158				
d (in)	0.19				

Basin ID	Area	Impervious	WQCD	WQV	H = Depth	Minimum A <sub>f</sub>
-	ac.	%	in.	ft <sup>3</sup>	ft	ft <sup>2</sup>
V	0.02	100	1.30	94	1.25	17
R2	0.02	100	1.30	94	1.25	17

IN BASIN V, THERE IS A TOTAL OF 981 sq. ft. OR .02 ACRES OF IMPERVIOUS COVER THAT WOULD BE TREATED BY A WQ FEATURE. WQ FEATURES ARE NOT ALLOWED IN THE CWOZ OF THE BARTON SPRINGS ZONE. THEREFORE A PORTION OF WILLIAM BARTON DRIVE IS BEING TREATED. THIS IS REPRESENTED BY BASIN R. REFER TO EXISTING AND PROPOSED DRAINAGE AREA SHEET AND SITE PLAN SHEET.

SITE PLAN APPROVAL

FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_ SHEET 228 OF 239

APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION 112 OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.

EXPIRATION DATE (25-5-81, LDC) \_\_\_\_\_ CASE MANAGER: \_\_\_\_\_

PROJECT EXPIRATION DATE (OED #979905-A) \_\_\_\_\_ N/A \_\_\_\_\_ DWFP \_\_\_\_\_ DDZ \_\_\_\_\_

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1: \_\_\_\_\_ Correction 1: \_\_\_\_\_

Rev. 2: \_\_\_\_\_ Correction 2: \_\_\_\_\_

Rev. 3: \_\_\_\_\_ Correction 3: \_\_\_\_\_

Final plan must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

CITY OF AUSTIN  
APPROVED  
Date: 4/13/2021  
PROJECT: 100

STATE OF TEXAS  
MICHAEL C. MULLONE  
127850  
LICENSED PROFESSIONAL ENGINEER  
Mike Mullone  
12/16/2021

VIOLET CROWN TRAILHEAD  
WILLIAM BARTON DR.  
AUSTIN TX 78746

RAIN GARDEN

**DUNAWAY UDOG**  
TX Registered Engineering Firm #F-1114  
TPELS Firm No. 10065900  
5707 Southwest Parkway  
Building 2, Suite 250  
Austin, TX 78735  
Phone: 512-306-8252

**C6.00**

JOB NO. B005344.001

SPEC-2012-0104D(R5)

SHEET NUMBER 228 OF 239







**R5**  
**NEW SHEET**

C:\Production\4000\0065300\5344\001\CVin\CAD\Plans\ Site Plan\Sheets\VCT-S-RG.dgn 12/6/2021










GENERAL NOTES:

1. THIS STANDARD IS APPLICABLE FOR RAMP CONSTRUCTION ON CITY PROPERTY AND EIGHTH AVENUE AREAS ONLY.
2. PAVERS ARE REQUIRED FOR ALL CURB RAMP INSTALLATIONS.
3. PAVERS WILL HAVE DETECTABLE WARNING THAT CONSISTS OF RAISED TRUNCATED DOMES WITH A DIAMETER OF 0.9" (23 mm), A NOMINAL HEIGHT OF 0.2" (5 mm) AND A CENTER-TO-CENTER SPACING OF 2.0" (51 mm). DETECTABLE WARNING SHALL BE LAYED VISUALLY WITH ADJOINING SURFACES, EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT AND SHALL BE LAYED TO MATCH THE ADJOINING SURFACES. CONTROL JOINTS SHALL BE LAYED IN ACCORDANCE WITH SECTION 2.29.2. MATERIAL USED FOR DETECTABLE WARNING SHALL BE INTEGRAL PORTLAND CEMENT CONCRETE. DETECTABLE WARNING PATTERN SHALL BE BASKET WEAVE, UNLESS DIRECTED OTHERWISE BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.
4. THE WIDTH OF THE WALKWAY SHALL BE 48" (1219 mm) MINIMUM. THE WALKWAY SHALL REFER TO THE TRANSPORTATION CRITERIA MANUAL FOR SIDEWALK WIDTHS, CURB RADIUS AND CURB BAYS.
5. THE DETECTABLE CONSTRUCTION JOINT BETWEEN THE PAVERS AND THE ADJOINING SURFACE SHALL BE LIMITED TO 1/4" (6 mm) JOINT SIZE. GAPS LARGER THAN 1/4" (6 mm) SHALL BE REPAIRED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE. ALL JOINTS BETWEEN BRICKS OR ADJOINING SURFACES SHALL BE REPAIRED BY THE ENGINEER OR DESIGNATED REPRESENTATIVE BY THE ENGINEER OR DESIGNATED REPRESENTATIVE.
6. THE CONCRETE JOINTS TO STD. SPECIFICATION AND SHOW SECTION 11.01.01.01 MORTAR AND GROUT. ALL OTHER CONCRETE SHALL CONFORM TO STD. SPECIFICATION ITEM 403S, CONCRETE FOR STRUCTURES, UNLESS OTHERWISE NOTED.
7. CURB RAMPERS WITH RETRAINED WHEELS SHALL BE USED WHERE PEDESTRIANS WOULD NOT NORMALLY WALK DIAGONALLY ACROSS THE RAMP.



## ACCESSIBILITY SITE NOTES

SITE GRADING SHALL COMPLY WITH THE TEXAS ACCESSIBILITY STANDARDS EXISTING AT THE TIME OF PLAN APPROVAL. GRADING SHOWN ON THE PLANS IS INTENDED TO COMPLY WITH SUCH STANDARDS AND SHOULD THE CONTRACTOR DETERMINE THAT COMPLIANCE WITH THE STANDARDS IS NOT CONSISTENT WITH THE SITE PLAN OR ELEVATIONS, HE SHALL NOTIFY THE ENGINEER IMMEDIATELY FOR A REMEDY.

- ACCESSIBLE ROUTES (SIDEWALKS, PATHS, ETC)**
1. RUNNING SLOPES SHALL NOT EXCEED 1:20 (5%) OTHER THAN FOR RAMPS, SEE RAMP REQUIREMENTS BELOW.
  2. CROSS SLOPE SHALL NOT EXCEED 1:50 (2%).
  3. DELETED
  4. CHANGES IN LEVEL SHALL NOT EXCEED 1/2" . 1/2" CHANGE IN LEVEL MUST HAVE A BEVELED EDGE OR 1/2" 1/4" CHANGE IN LEVEL OR LESS DOES NOT HAVE TO PROVIDE A BEVELED EDGE.
  5. MANUEVERING CLEARANCE (60") AT ACCESSIBLE ENTRANCES SHALL NOT EXCEED 1:50 (2% SLOPE).
  6. A 6'0" X 6'0" PASSING SPACE SHALL BE PROVIDED EVERY 200' ALONG AN ACCESSIBLE ROUTE.

## CURB RAMPS





1. SLOPE SHALL NOT EXCEED 1:12 (8.3%). FLARED SIDES SHALL NOT EXCEED 1:10. CROSS SLOPE SHALL TO EXCEED 1:50 (2%).
2. FULL WIDTH AND DEPTH OF CURB RAMP SURFACES SHALL PROVIDE A CONTRASTING LIGHT REFLECTIVE VALUE (COLOR) AND TEXTURE. TEXTURE MAY CONSIST OF TRUNCATED DOMES OR 3/4" WIDE GROOVES, 1/4" DEEP AND 2" APART. COLOR SHALL CONTRAST AT LEAST 70% FROM ADJACENT SURFACES.
3. MINIMUM RAMP WIDTH SHALL BE 36".
4. WHERE AN ACCESSIBLE ROUTE CROSSES A CURB RAMP, IT SHALL CIRCUMVENT THE CURB RAMP SO AS TO NOT REQUIRE THE USER TO CROSS OVER THE CURB RAMP.
5. CURB RAMP ARE NOT PERMITTED TO PROJECT INTO THE ACCESSIBLE PARKING ACCESS AISLES.
6. TRANSITIONS FROM GUTTER OR STREET TO CURB RAMP SHALL BE FLUSH.

OTHER RAMPS

1. MAXIMUM SLOPE SHALL BE 1:12 (8.3%).
2. RAMPS OVER 6' IN LENGTH REQUIRE HANDRAILS ON BOTH SIDES.
3. HANDRAIL HEIGHT SHALL BE 34" - 36" ABOVE RAMP SURFACE.
4. HANDRAIL DIAMETER - 1.25" TO 1.5".
5. EDGE PROTECTION IS REQUIRED WHERE DROP OFFS OCCUR.
6. 12" MINIMUM HANDRAIL EXTENSIONS ARE REQUIRED AT LANDINGS, EXCEPT WHERE HANDRAILS ARE CONTINUOUS. HANDRAIL EXTENSIONS SHALL EXTEND IN THE SAME DIRECTION AS THE RAMP.
7. MAXIMUM RUN BETWEEN LANDINGS SHALL BE 30'.
8. 60° LEVEL (2% MAX. SLOPE) LANDINGS ARE REQUIRED AT TOP AND BOTTOM OF EACH RUN. A 60° X 60° LANDING REQUIRED WHERE A RAMP CHANGES DIRECTION.

PAVERS

1. JOINTS BETWEEN PAVERS 1/2" MAXIMUM
2. VERTICAL DIFFERENCES BETWEEN PAVERS 1/4" MAXIMUM
3. RUNNING SLOPE (IN DIRECTION OF TRAVEL) 1:20 (5%) MAXIMUM
4. CROSS SLOPE (PERPENDICULAR TO THE DIRECTION OF TRAVEL) 1/4" PER FOOT (2%) MAXIMUM



**A CURB & GUTTER AT SAWCUT**  
NOT TO SCALE

[illegible]

G:\Production4000\005300\5344\001\Civil\CAD\VC1-S-DIL.dgn

170719172



PROPOSED SHADE TREE LEGEND			
SYMBOL	TOTAL TREES		SPECIES
		MITIGATION (R)	
	3	3	CHINQUAPIN OAK <i>Quercus muehlenbergii</i> 4" CALIPER
	5	5	LIVE OAK <i>Quercus virginiana</i> 4" CALIPER
	7	6	CEDAR ELM <i>Ulmus crassifolia</i> 4" CALIPER
	15	14	SUBTOTAL (SHADE TREES)

PROPOSED ORNAMENTAL TREE LEGEND			
SYMBOL	TOTAL TREES		SPECIES
		MITIGATION (R)	
	5	3	TEXAS REDBUD (2" CAL) <i>Cercis canadensis</i> var. <i>texensis</i>
	3	2	TEXAS PERSIMMON (2" CAL) <i>Diospyros texana</i>
	3	0	THORNLESS PALO VERDE (2" CAL) <i>Parkinsonia 'Desert Museum'</i>
	2	1	TEXAS MOUNTAIN LAUREL (2" CAL) <i>Sophora secundiflora</i>
	2	1	MEXICAN BUCKEYE (2" CAL) <i>Ungnadia speciosa</i>
	15	7	SUBTOTAL (ORN. TREES)

GRAND TOTAL (ALL TREES): 15 + 15 = 30 TOTAL TREES  
REFERENCE L-2 FOR LANDSCAPE CALCULATIONS AND  
BREAKDOWN OF QUANTITY OF INCHES PROVIDED  
TOWARDS MITIGATION.



THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

NOTE:  
IF ESTABLISHING VEGETATION DURING ANY STAGE OF A DROUGHT, SECTION 6-4-30 MAY REQUIRE A VARIANCE. CONTACT AUSTIN WATER CONSERVATION STAFF AT WATERUSECOMPAR@AUSTINTEXAS.GOV OR CALL (512) 974-2199.

NOTE:  
ALL PROPOSED TREES TO BE LOCATED A MINIMUM OF 10'-0" OFFSET AWAY FROM EXISTING WASTEWATER LINES.

SITE PLAN APPROVAL Sheet \_\_\_\_\_ of \_\_\_\_\_  
FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION \_\_\_\_\_ OF  
CHAPTER \_\_\_\_\_ OF THE CITY OF AUSTIN CODE.  
EXPIRATION DATE (25-5-81,110C) \_\_\_\_\_ CASE MANAGER \_\_\_\_\_  
PROJECT EXPIRATION DATE (ORD.#970905-4) \_\_\_\_\_ DWG# \_\_\_\_\_ DD# \_\_\_\_\_

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_  
Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_  
Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_

FINAL PLAN MUST BE RECORDED BY THE PROJECT EXPIRATION DATE. IF APPLICABLE, SUBSEQUENT SITE PLANS WHICH DO NOT COMPLY WITH THE CODE CURRENT AT THE TIME OF FILING, AND ALL REQUIRED BUILDING PERMITS AND/OR A NOTICE OF CONSTRUCTION (IF A BUILDING PERMIT IS NOT REQUIRED), MUST ALSO BE APPROVED PRIOR TO THE PROJECT EXPIRATION DATE.



1705 guadalupe street  
suite 500  
austin, tx 78701  
[512] 327-1011  
tbgpartners.com



project  
violet crown trail


zilkner trailhead

Austin, Texas

project number A16512

issue date 12/02/21


designed: JL, AS  
drawn: CC  
reviewed: JL



sheet title  
landscape plan

sheet  
L-1  
SHEET 231 OF 239


SPC-2012-0104D(R5)



# 1 OVERALL LANDSCAPE PLAN

- TREE CARE PLAN FOR HERITAGE PECAN TREE 3058:
1. DEEP ROOT WATERING TO OCCUR DURING CONSTRUCTION. (RATE OF 1/2 GAL. EVERY 2-3' WITHIN PRESERVED PERMEABLE CRZ.)
  2. AIR SPADING TO A DEPTH OF 4'-6" IN PRESERVED, PERMEABLE CRZ AREA, WITH 1" ORGANIC COMPOST INCORPORATED INTO TOPSOIL PROFILE. WORK SHALL OCCUR DURING TREE DORMANCY; IF NOT, WORK SHALL INCLUDE WATERING 2-3x DURING THE 7-10 DAY PERIOD FOLLOWING THE WORK IF NO RAIN.
  3. INSTALL SHREDDED, DECOMPOSED HARDWOOD MULCH TO DEPTH OF 3" WITHIN AVAILABLE CRZ AREA.
  4. DEEP ROOT FERTILIZATION NEAR END OF CONSTRUCTION.

LANDSCAPE LEGEND			
	6" STABILIZED DECOMPOSED GRANITE PATH (REF. 8/L-3)		EXISTING TREE TO REMAIN
	3" STABILIZED DECOMPOSED GRANITE PATH (REF. 9/L-3)		EXISTING TREE TO BE REMOVED
	FLAGSTONE WALKWAY (REF. 6/L-3)	SY	TREE COUNTING TOWARD STREET/YARD REQUIREMENT
	CONCRETE WALK	PA	SHRUB BED/PLANTING AREA
	SHRUB BED PLANTING AREA		
	NATIVE GRASS AND WILDFLOWER SEED MIX PER CITY OF AUSTIN 60% SPECIFICATION		
	EXISTING NATIVE AREA TO REMAIN UNDISTURBED		
	APPENDIX X CWQZ PLANTING (REF. L-5)		





Z:\TBG\ Violet Crown Trail (416512)\X02 Permit Sheets\416512-L-1-permit.dwg

CITY OF AUSTIN LANDSCAPE NOTES:

1. ALL PROPOSED LANDSCAPE AREAS WITHIN PROPERTY LINE TO RECEIVE 100% HEAD TO HEAD IRRIGATION COVERAGE.
2. ALL LANDSCAPE AREAS ADJACENT TO VEHICULAR USE SHALL BE PROTECTED BY MIN. 6" HL. WHEEL CURBS, WHEELSTOPS OR OTHER APPROVED BARRIERS PER ECM 2.4.7.
3. THE OWNER SHALL CONTINUOUSLY MAINTAIN THE REQUIRED LANDSCAPING IN ACCORDANCE WITH THE LDC SECTION 25-2-984
4. AN UNDERGROUND AUTOMATIC IRRIGATION SYSTEM WILL BE USED TO IRRIGATE ALL NEW LANDSCAPE MATERIAL WITH TURF. ZONES SEPARATED FROM PLANTING ZONES. AUTOMATIC IRRIGATION SYSTEMS SHALL COMPLY WITH THE WATER CONSERVATION IRRIGATION SYSTEM REQUIREMENTS, AS REQUIRED IN THE ENVIRONMENTAL CRITERIA MANUAL.
5. THE IRRIGATION SYSTEM SHALL BE IN PLACE AND FUNCTIONAL AT THE TIME OF THE LANDSCAPE INSPECTION.
6. REFERENCE TREE STAKING DETAIL FOR ALL NEW TREES.
7. A MINIMUM OF 6" OF PERMEABLE SOIL IS REQUIRED FOR TURF AND LANDSCAPE AREAS.
8. IRRIGATION LINES SHOULD BE TRENCHED SO THAT THERE IS NO DISTURBANCE TO THE CRITICAL ROOT ZONE OF EXIST. TREES.
9. PROOF OF PAYMENT OF THE LANDSCAPE INSPECTION FEE IN THE AMOUNT REQUIRED BY C.O.A. WILL BE REQUIRED PRIOR TO FINAL APPROVAL OF THIS SITE PLAN BY ECSD.

CITY OF AUSTIN LANDSCAPE/IRRIGATION NOTES - APPENDIX 0

AUTOMATIC IRRIGATION SYSTEMS SHALL COMPLY WITH TCEQ CHAPTER 344, AS WELL AS THE FOLLOWING REQUIREMENTS:

1. A NEW COMMERCIAL AND MULTI-FAMILY IRRIGATION SYSTEM MUST BE DESIGNED AND INSTALLED SO THAT:
- (A) THE SYSTEM MUST PROVIDE A MOISTURE LEVEL ADEQUATE TO SUSTAIN GROWTH OF THE PLANT MATERIALS;
- (B) THE SYSTEM DOES NOT INCLUDE SPRAY IRRIGATION ON AREAS LESS THAN TEN (10) FEET WIDE (SUCH AS MEDIANS, BUFFER STRIPS, AND PARKING LOT ISLANDS);
- (C) CIRCUIT REMOTE CONTROL VALVES HAVE ADJUSTABLE FLOW CONTROLS;
- (D) SERVICEABLE IN-HEAD CHECK VALVES AREA ADJACENT TO PAVED AREAS WHERE ELEVATION DIFFERENCES MAY CAUSE LOW HEAD DRAINAGE;
- (E) A MASTER VALVE INSTALLED ON THE DISCHARGE SIDE OF THE BACKFLOW PREVENTER;
- (F) ABOVE-GROUND IRRIGATION EMISSION DEVICES ARE SET BACK AT LEAST SIX (6) INCHES FROM IMPERVIOUS SURFACES
- (G) AN AUTOMATIC RAIN SHUT-OFF DEVICE SHUTS OFF THE IRRIGATION SYSTEM AUTOMATICALLY AFTER NOT MORE THAN A ONE-HALF INCH (1/2") RAINFALL;
- (H) NEWLY PLANTED TREES SHALL HAVE PERMANENT IRRIGATION CONSISTING OF DRIP BUBBLERS.

2. THE IRRIGATION INSTALLER SHALL DEVELOP AND PROVIDE AN AS-BUILT DESIGN PLAN TO THE CITY AT THE TIME THE FINAL IRRIGATION INSPECTION IS PERFORMED;
- (A) UNLESS FISCAL SECURITY IS PROVIDED TO THE CITY FOR THE INSTALLATION OF THE SYSTEM, IT MUST BE OPERATIONAL AT THE TIME OF THE FINAL LANDSCAPE INSPECTION.

3. THE IRRIGATION INSTALLER SHALL ALSO PROVIDE EXHIBITS TO BE PERMANENTLY INSTALLED INSIDE OR ATTACHED TO THE IRRIGATION CONTROLLER, INCLUDING:
- (A) A LAMINATED COPY OF THE WATER BUDGET CONTAINING ZONE NUMBERS, PRECIPITATION RATE, GALLONS PER MINUTE AND THE LOCATION OF THE ISOLATION VALVE, AND AN AS BUILT PLAN.

4. THE IRRIGATION INSTALLER SHALL PROVIDE A REPORT TO THE CITY ON A FORM PROVIDED BY AUSTIN WATER CERTIFYING COMPLIANCE WITH SUBSECTION 1 WHEN THE FINAL PLUMBING INSPECTION IS PERFORMED BY THE CITY.


TREE SYMBOL LEGEND:	
	EXISTING TREE TO REMAIN
	HALF CRITICAL ROOT ZONE (CRZ) FOR EXISTING TREE OVER 19' TO REMAIN
	EXISTING TREE TO BE REMOVED
	REPLACEMENT/MITIGATION TREE

Violet Crown Trail


Austin, Travis County, Texas  
Job Number: A16512

														TREE LIST / MITIGATION CALCULATIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
HERITAGE MULTI-TREE TAD			SPECIES	CAL 1	CAL 2	CAL 3	CAL 4	CAL 5	CAL 6	CAL 7	CAL 8	CAL 9	CAL 10	Trees Removed										Trees Preserved																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
														Heritage Trees					ECM 3.5.1 (A)(2) - Tree Type Categories					Heritage Trees					ECM 3.5.1 (A)(2) - Tree Type Categories																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
														HERITAGE 30"+	HERITAGE 24"+	APODX-F 19' & UP	APODX-F 8'-18.9'	NON- APODX-F 19' & UP	NON APODX-F 8'-18.9'	APODX-F <8'	NON APODX- F <8'	INVASIVE	HERITAGE 30"+	HERITAGE 24"+	APODX-F 19' & UP	APODX-F 8'-18.9'	NON- APODX-F 19' & UP	NON APODX-F 8'-18.9'	APODX-F <8'	NON APODX-F <8'	INVASIVE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
P			3050 Pecan	20																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											







9 DECOMPOSED GRANITE TRAIL AT HERITAGE TREE  
PLAN SCALE: 1"=1'-0"




8 DECOMPOSED GRANITE TRAIL  
PLAN SCALE: 1"=1'-0"




7 FLAGSTONE WALKWAY  
SECTION SCALE: 1"=1'-0"




6 FLAGSTONE WALKWAY  
PLAN SCALE: 1"=1'-0"




5 SHRUB BED PLANTING  
SECTION SCALE: 1/2"=1'-0"




2 TREE PLANTNG - MULTI-TRUNK  
SECTION SCALE: 1/2"=1'-0"



4 CURVED BED LAYOUT  
PLAN SCALE: 1/2"=1'-0"



3 PLANT SPACING DIAGRAM  
PLAN SCALE: 1/2"=1'-0"



1 TREE PLANTNG - STANDARD TRUNK  
SECTION SCALE: 1/2"=1'-0"



THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

SITE PLAN APPROVAL Sheet \_\_\_\_\_ of \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
FILE NUMBER: \_\_\_\_\_ UNDER SECTION \_\_\_\_\_ OF CHAPTER \_\_\_\_\_ OF THE CITY OF AUSTIN CODE.  
EXPIRATION DATE (25-5-81.LDC) \_\_\_\_\_ CASE MANAGER \_\_\_\_\_  
PROJECT EXPIRATION DATE (ORD.#970905-4) \_\_\_\_\_ DWG# \_\_\_\_\_ DD# \_\_\_\_\_

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_  
Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_  
Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_  
Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_


FINAL PLAN MUST BE RECORDED BY THE PROJECT EXPIRATION DATE, IF APPLICABLE. SUBSEQUENT SITE PLANS WHICH DO NOT COMPLY WITH THE CODE CURRENTLY IN THE YEAR OF FILING, AND ALL REQUIRED BUILDING PERMITS AND/OR A NOTICE OF CONSTRUCTION (IF A BUILDING PERMIT IS NOT REQUIRED), MUST ALSO BE APPROVED PRIOR TO THE PROJECT EXPIRATION DATE.

LANDSCAPE CERTIFICATION BLOCK  
I CERTIFY THAT ALL INFORMATION IS TRUE AND ACCURATE AND THAT THE REQUIREMENTS OF SECTION 25-2, ARTICLE 9 OF THE LDC HAVE BEEN MET.

ELLIOTT DOERLE 10/15/2021  
DATE



landscape architects, planners & designers  
1705 guadalupe street  
suite 500  
austin, tx 78701  
[512] 327-1011  
tbgpartners.com



project  
violet crown  
trail

zilkner trailhead

Austin, Texas

project number A16512

issue date 10/15/21

designed: J.L. AS  
drawn: CC  
reviewed: J.L.

sheet title  
landscape  
details

sheet  
L-3  
SHEET 233 OF 239

SPC-2012-0104D(R5)



Z:\TBDG\Violet Crown Trail (416512)\02 Permits\Sheets\A16512-L-1-permit.dwg

COA APPENDIX R-11 RAIN GARDEN CALCULATIONS FOR DEVELOPMENT PERMITS				
Violet Crown Trailhead - R2				
DRAINAGE AREA DATA: R2				
Drainage Area to Control (DA - Maximum 2.0 ac.)	0.02	ac.		
Drainage Area Percent Impervious Cover	100	%		
Capture Depth (CD)	1.30	in.		
Required Capture Depth per SLAT for Barton Springs Zone	2.54	in.		
WATER QUALITY CONTROL CALCULATIONS:				
	Required		Provided	
Water Quality Volume (WQV)	184	ft <sup>3</sup>	265	ft <sup>3</sup>
100 Year Peak Flow Rate to Control (Q100)		ft <sup>3</sup> /s		
Filtration Pond Area (A <sub>f</sub> )	214	ft <sup>2</sup>	308	ft <sup>2</sup>
Depth of Ponding (D)	Max 1.0	ft.	0.50	ft.
Depth of Filtration Media (L)	Min 1.5	ft.	1.5	ft.
Effective Porosity Water Quality Volume (WQV <sub>eff</sub> = 0.24*A <sub>f</sub> *L)			111	ft <sup>3</sup>
Ponded Water Quality Volume (WQV <sub>ponded</sub> = WQV - WQV <sub>eff</sub> )			154	ft <sup>3</sup>
	Provided WQV		265	ft <sup>3</sup>
Water Quality Elevation (WQE)			496.75	ft.
Elevation of Splitter/Overflow Weir (minimum WQE)			496.75	ft.
Length of Splitter Weir				ft.
Required Head to Pass Q100			0.08	ft.
Pond Freeboard Provided to Pass Q100	Min 0.25	ft.	0.42	ft.
FILTRATION RAIN GARDENS				
Rain Garden Pond Drawdown Time (at 0.25 in./hr.)	Min 48	hr.	48	hr.
Underdrain Orifice Size (Diameter)			0.19	in.
Underdrain Orifice (Area)			0.03	in <sup>2</sup>

RAINGARDEN LANDSCAPE CALCULATIONS	
PLANTS REQUIRED PER ECM SECTION 1.6.7.H.8 - RAINGARDENS *	
TOTAL SF OF RAINGARDEN BOTTOM	693
TOTAL (10% OF POND BOTTOM)	69
RAINGARDEN BASIN:	
50% OF TOTAL PLANTS TO BE FROM TABLE 1.6.7.C.2	35
50% OF TOTAL MAY BE OTHER SUITABLE SPECIES AS SELECTED BY THE DESIGNER (PER ECM 1.6.7.C.5-F)	34
*Note: Per ECM Section 1.6.7.H.8, Vegetation quantity, size, spacing and selection shall meet the requirements for filtration basins as provided in ECM 1.6.7.C, Biofiltration, with the exception that rain gardens do not require a minimum of five different species (i.e., one species is acceptable), although higher diversity is recommended	

RAINGARDEN PLANT LIST		
RAINGARDEN SPECIES FROM TABLE 1.6.7.C.2		
Plant Quantities in this table are based on the one gallon size requirement for COA. If other container sizes are planted, quantities will be adjusted based on the Plant Size Equivalents on Table 1.6.7.C.1 to maintain the required quantity of plants.		
BOTANICAL NAME	COMMON NAME	QUANTITY
<i>Muhlenbergia capillaris</i>	Gulf coast muhly	15
<i>Muhlenbergia lindheimeri</i>	Big muhly	10
<i>Panicum virgatum</i>	Switchgrass	5
<i>Penstemon tenuis</i>	Brazos Penstemon	5
<i>Physostegia</i> spp.	Obedient Plant	5
Total Per ECM Table 1.6.7.C.2		40

RAINGARDEN SPECIES NOT LISTED TABLE 1.6.7.C.2		
Plant Quantities in this table are based on the one gallon size requirement for COA. If other container sizes are planted, quantities will be adjusted based on the Plant Size Equivalents on Table 1.6.7.C.1 to maintain the required quantity of plants.		
BOTANICAL NAME	COMMON NAME	QUANTITY
<i>Carex cherokeensis</i>	Cherokee Sedge	15
<i>Chasmanthium latifolium</i>	Inland sea oats	10
<i>Echinacea purpurea</i>	Purple Coneflower	5
<i>Phylla nodiflora</i>	Frogfruit	5
<i>Rudbeckia hirta</i>	Black-eyed Susan	5
Total Per ECM Section 1.6.7.C.5-F		40
TOTAL QUANTITY OF PLANTS PROVIDED		80



THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.



SITE PLAN APPROVAL Sheet \_\_\_\_ of \_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
FILE NUMBER: \_\_\_\_\_ APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION \_\_\_\_\_ OF CHAPTER \_\_\_\_\_ OF THE CITY OF AUSTIN CODE.  
EXPIRATION DATE (25-6-81,110C) \_\_\_\_\_ CASE MANAGER \_\_\_\_\_  
PROJECT EXPIRATION DATE (ORD.4970905-4) \_\_\_\_\_ DWG# \_\_\_\_\_ DD# \_\_\_\_\_

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_

Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_  
Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_  
Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_

FINAL PLAN MUST BE RECORDED BY THE PROJECT EXPIRATION DATE. IF APPLICABLE, SUBSEQUENT SITE PLANS WHICH DO NOT COMPLY WITH THE COA COVENANT AT THE TIME OF FILING, AND ALL REQUIRED BUILDING PERMITS AND/OR A NOTICE OF CONSTRUCTION (IF A BUILDING PERMIT IS NOT REQUIRED), MUST ALSO BE APPROVED PRIOR TO THE PROJECT EXPIRATION DATE.

BIOFILTRATION POND NOTES:	
1. BIOFILTRATION MEDIA BED WITH GRAVEL LAYER. THE BIOFILTRATION MEDIA BED FOR BIOFILTRATION BASINS MUST BE BUILT TO THE "SAND BED WITH GRAVEL LAYER" CONFIGURATION. THE BIOFILTRATION MEDIA LAYER IS TO BE A MINIMUM OF EIGHTEEN (18) INCHES MEETING THE COA SPECIFICATIONS. THE BIOFILTRATION MEDIA SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES. NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE BIOFILTRATION AREA THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS.	4. <u>MAINTENANCE</u> ONCE VEGETATION IS ESTABLISHED, BIOFILTRATION SYSTEMS SHOULD REQUIRE LESS MAINTENANCE THAN SAND FILTRATION SYSTEMS BECAUSE THE VEGETATION PROTECTS THE FILTRATION MEDIA FROM SURFACE CRUSTING AND SEDIMENT CLOGGING. PLANT ROOTS ALSO PROVIDE A PATHWAY FOR WATER TO PERMEATE DOWN INTO THE MEDIA, THUS FURTHER ENHANCING THE HYDRAULIC PERFORMANCE OF THE SYSTEM. UNLESS DAMAGED BY UNUSUAL SEDIMENT LOADS, HIGH FLOWS, OR VANDALISM, THE BIOFILTRATION MEDIA SHOULD BE LEFT UNDISTURBED AND ALLOWED TO AGE NATURALLY.
2. BIOFILTRATION MEDIA BED DEPTHS ARE FINAL. CONSOLIDATION EFFECTS MUST BE TAKEN INTO ACCOUNT. UNDER THE BIOFILTRATION MEDIA SHALL BE A LAYER OF ONE-HALF (0.5) TO ONE AND ONE-HALF (1.5) INCH DIAMETER WASHED, ROUNDED, RIVER GRAVEL WHICH PROVIDES A MINIMUM OF THREE (3) INCHES OF COVER OVER THE TOP OF THE 6" SCHEDULE 40, PVC UNDERDRAIN LATERAL PIPES. THE SOIL MEDIA AND GRAVEL MUST BE SEPARATED BY A LAYER OF GEOTEXTILE FABRIC MEETING THE SPECIFICATIONS LISTED IN SECTION 1.6.2(C). TO AVOID COMPACTION OF THE BIOFILTRATION MEDIA AND PROMOTE FILTRATION DO NOT ALLOW HEAVY EQUIPMENT IN BIOFILTRATION AREA AFTER THE BIOFILTRATION MEDIA HAS BEEN PLACED.	-- <u>WATER PLANTS</u> AS NECESSARY DURING THE FIRST GROWING SEASON AND DURING DRY PERIODS. IRRIGATION WILL BE NECESSARY TO ESTABLISH THE VEGETATIVE COMMUNITY DURING THE FIRST 3-6 MONTHS AFTER PLANTING HAS BEEN COMPLETED AND BY HAND IMMEDIATELY AFTER COMPLETION OF THE PROJECT. -- <u>BIMONTHLY</u> INSPECTION OF VEGETATION DURING FIRST GROWING SEASON UNTIL 95% VEGETATIVE COVER IS ESTABLISHED. -- <u>MONTHLY</u> CHECK FOR ACCUMULATED SEDIMENTS, REMOVE AS NEEDED. -- <u>QUARTERLY</u> REMOVAL OF DEBRIS, SEDIMENT ACCUMULATION, AND SOIL MEDIA SHOULD BE REPLACED IN VOID AREAS CAUSED BY SETTLEMENT, AND REPAIR ERODED AREAS. REMOVE ANY VOID AREAS BY HAND WHENEVER NEEDED. -- <u>SIX MONTHS</u> REMOVE AND REPLACE DEAD AND DISEASED VEGETATION. REMOVAL AND REPLACEMENT OF ALL DEAD AND DISEASED VEGETATION CONSIDERED BEYOND TREATMENT (SEE PLANTING SPECIFICATIONS). TREAT ALL DISEASED TREES AND SHRUBS MECHANICALLY OR BY HAND DEPENDS ON INSECT OR DISEASE INFESTATION. -- <u>LATE WINTER HARVESTING</u> INVOLVING TRIMMING OF BUNCHGRASSES (TRIM TO MINIMUM 18" OR HIGHER, SEE SPECIFIC TRIMMING RECOMMENDATIONS), AND MOWING OF TURF GRASSES (MINIMUM 5" HIGH). FOR OTHER TYPES VEGETATION SEE RECOMMENDATIONS IN THE PLANTING SPECIFICATIONS. -- <u>SPRING</u> REMOVE PREVIOUS MULCH LAYER BEFORE APPLYING NEW LAYER (OPTIONAL) BY HAND ONCE EVERY TWO TO THREE YEARS IN THE SPRING. -- ANY TIME 48 HOUR DRAWDOWN TIME IS EXCEEDED OR SIGNIFICANT DECREASE IN DRAWDOWN TIME IS OBSERVED EVALUATE BED SOIL, UNDERDRAIN SYSTEM AND APPROPRIATE MEASURES SHOULD BE TAKEN. BIOFILTRATION POND VEGETATION SHALL BE MANAGED SO THAT A DENSE, HEALTHY VEGETATIVE COVER IS PRESERVED. ONCE ESTABLISHED, NATIVE GRASSES SHALL BE MAINTAINED WITHOUT FERTILIZERS AND LIMITED USE OF ORGANIC HERBICIDES. A RECORDED RESTRICTIVE COVENANT AND COVER SHEET NOTES WILL ESTABLISH THE REQUIREMENTS FOR THE IMPLEMENTATION AND ONGOING MAINTENANCE OF AN APPROVED INTEGRATED PEST MANAGEMENT PLAN (IPM).
3. <u>IRRIGATION</u> IRRIGATION WILL BE NECESSARY TO ESTABLISH THE VEGETATIVE COMMUNITY DURING THE FIRST 3-6 MONTHS AFTER PLANTING. THEREAFTER IRRIGATION NEEDS SHOULD BE MINIMAL AND A PERMANENT IRRIGATION SYSTEM MAY NOT BE NECESSARY. IF A PERMANENT IRRIGATION SYSTEM IS PROPOSED, THE DESIGN MUST ADDRESS BOTH STORMWATER MANAGEMENT AND PLANT HEALTH NEEDS. IN PARTICULAR, OVERWATERING IS UNACCEPTABLE AS IT WILL NEGATIVELY IMPACT THE HYDRAULIC PERFORMANCE AND POLLUTANT REMOVAL CAPABILITIES OF THE BIOFILTRATION SYSTEM. THE FOLLOWING MINIMUM CRITERIA WILL APPLY FOR PERMANENT IRRIGATION SYSTEMS:  -- SOIL WATER MOISTURE SENSORS MUST BE INSTALLED AT APPROPRIATE DEPTHS AND LOCATIONS IN THE BIOFILTRATION BASIN. -- NO IRRIGATION DURING PERIODS WHEN RAINFALL IS OCCURRING. -- NO IRRIGATION IS TO COMMENCE UNTIL THE SOIL MOISTURE CONTENT OF THE FILTRATION MEDIA IS 25% OF THE AVAILABLE WATER CAPACITY (AWC) -- FOR PLANTS NATIVE OR ADAPTED TO ARID AND SEMI-ARID CONDITIONS, NO IRRIGATION SHOULD COMMENCE UNTIL THE SOIL MOISTURE CONTENT IS WILTING POINT (WP), OR 0% AWC. -- IRRIGATION WILL CEASE ONCE THE SOIL MOISTURE CONTENT IS 75% AWC; 50% FOR PLANTS NATIVE OR ADAPTED TO ARID AND SEMI-ARID CONDITIONS.	



project  
violet crown trail

zilker trailhead

Austin, Texas

project number A16512

issue date 12/02/21

designed: JL, AS  
drawn: CC  
reviewed: JL

sheet title  
water quality pond calculations

sheet  
L-4  
SHEET 234 OF 239

SPC-2012-0104D(R5)





THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.


SITE PLAN APPROVAL Sheet \_\_\_\_\_ of \_\_\_\_\_  
FILE NUMBER: \_\_\_\_\_ APPLICATION DATE: \_\_\_\_\_  
APPROVED BY COMMISSION ON: \_\_\_\_\_ UNDER SECTION \_\_\_\_\_ OF CHAPTER \_\_\_\_\_ OF THE CITY OF AUSTIN CODE.  
EXPIRATION DATE (25-5-81.LDC) \_\_\_\_\_ CASE MANAGER \_\_\_\_\_  
PROJECT EXPIRATION DATE (ORD.#970905-4) \_\_\_\_\_ DWG# \_\_\_\_\_ DD# \_\_\_\_\_

Director, Development Services Department  
RELEASED FOR GENERAL COMPLIANCE: \_\_\_\_\_ ZONING: \_\_\_\_\_  
Rev. 1 \_\_\_\_\_ Correction 1 \_\_\_\_\_  
Rev. 2 \_\_\_\_\_ Correction 2 \_\_\_\_\_  
Rev. 3 \_\_\_\_\_ Correction 3 \_\_\_\_\_

**FINAL PLAN MUST BE RECORDED BY THE PROJECT EXPIRATION DATE. IF APPLICABLE. SUBSEQUENT SITE PLANS WHICH DO NOT COMPLY WITH THE CODE CURRENT AT THE TIME OF FILING, AND ALL REQUIRED BUILDING PERMITS AND/OR A NOTICE OF CONSTRUCTION (IF A BUILDING PERMIT IS NOT REQUIRED), MUST ALSO BE APPROVED PRIOR TO THE PROJECT EXPIRATION DATE.**



1705 guadalupe street  
suite 500  
austin, tx 78701  
[512] 327-1011  
tbgpartners.com



APPENDIX X - ZONE 2 CWQZ PLANTING LEGEND

PROPOSED SHADE TREE LEGEND			
SYMBOL	TOTAL	SPECIES	SIZE
	4	CEDAR ELM <i>Ulmus crassifolia</i>	2.5" caliper 8' height single trunk
	2	TEXAS RED OAK <i>Quercus texana</i>	1.5" caliper 6' height single trunk
	1	PECAN <i>Carya illinoensis</i>	1.5" caliper 6' height single trunk
PROPOSED ORNAMENTAL TREE LEGEND			
SYMBOL	TOTAL	SPECIES	SIZE
	2	TEXAS REDBUD <i>Cercis canadensis</i> var. <i>texensis</i>	6' height multi trunk

PROPOSED SHRUB AND GROUNDCOVER LEGEND			
SYMBOL	TOTAL	SPECIES	SIZE
	20	WHITE MISTFLOWER <i>Ageratina havanensis</i>	3 gallon 12" min. height
	15	AMERICAN BEAUTYBERRY <i>Callicarpa americana</i>	5 gallon 18" min. height
	35	KIDNEYWOOD <i>Eysenhardtia texana</i>	3 gallon 12" min. height
	25	FRAGRANT SUMAC <i>Rhus aromatica</i>	5 gallon 18" min. height
	20	EVERGREEN SUMAC <i>Rhus virens</i>	5 gallon 18" min. height
	75	INLAND SEA OATS <i>Chasmanthium latifolium</i>	4" pot plant @ 24" o.c.
	65	TURK'S CAP <i>Malvaviscus arboreus</i> var. <i>drummondii</i>	1 gallon plant @ 24" o.c.


NOTES:

THE PLANTING DESIGN IN THIS AREA HAS BEEN DEVELOPED TO ENHANCE THE FUNCTIONALITY IN THE CRITICAL WATER QUALITY ZONE FOR THIS PROJECT, BASED ON THE RECOMMENDATIONS OUTLINED IN APPENDIX X OF THE ENVIRONMENTAL CRITERIA MANUAL. PLANT MATERIAL HAS BEEN SELECTED AND ARRANGED TO IMPROVE THE CWQZ BASED ON THE FOLLOWING PARAMETERS:

- GAP FREQUENCY
- LARGE WOODY DEBRIS
- SOIL COMPACTION
- STRUCTURAL DIVERSITY
- TREE DEMOGRAPHY
- WETLAND TREE STATUS
- RIPARIAN ZONE WIDTH

ALL PROPOSED TREES IN THIS ZONE TO BE LOCATED A MINIMUM OF 10'-0" OFFSET AWAY FROM EXISTING WASTEWATER LINES. TREES IN THIS ZONE ARE COUNTED TO MEET APPENDIX X REQUIREMENTS ONLY AND ARE NOT FOR TREE REMOVAL MITIGATION. REFER TO L-1 FOR MITIGATION TREES.

ALL EXPOSED GROUND PLANE IN THIS AREA TO BE TOP DRESSED WITH 3" MINIMUM NATIVE ORGANIC SHREDDED HARDWOOD MULCH. PLANT MATERIAL IN THIS AREA TO RECEIVE TEMPORARY IRRIGATION FOR ESTABLISHMENT ONLY.



1 APPENDIX X PLANTING  
PLAN

project  
violet crown  
trail

zilker trailhead

Austin, Texas

project number A16512

issue date 10/15/21

designed: JL, AS  
drawn: CC  
reviewed: JL

sheet title  
appendix X  
planting

sheet  
L-5  
SHEET 235 OF 239

SPC-2012-0104D(R5)







**FOR PERMITTING ONLY**  
THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF  
PERMITTING ONLY, UNDER THE AUTHORITY OF:  
NAME: LARRY S. T. WU  
P.E. No: 89530  
DATE: 12/16/2021


AND IS NOT INTENDED TO BE USED FOR  
CONSTRUCTION PURPOSES.

Copyright 2021  
SHEET NO.  
237 OF 239

LANDSCAPE STRUCTURES

---


VIOLET CROWN TRAIL  
AUSTIN, TEXAS



**Pickett, Kelm & Associates, Inc.**  
Consulting Structural Engineers

Texas Registration No. F-1491  
4100 Duval Road, Bldg. 4, Suite 103  
Austin, Texas 78759 • Phone 512-345-5538


PROJECT NO.	011-4977
DESIGNED BY:	DMC/LGC
DRAWN BY:	DMC/LGC
CHECKED BY:	LSW
APPROVED BY:	LSW
DATE:	12/16/2021




NO.	REVISION	BY	DATE
-----	----------	----	------

NO.	REVISION	BY	DATE
-----	----------	----	------


NO.	REVISION	BY	DATE
-----	----------	----	------



2 SECTION  
1" = 1'-0"



PROJECT NO.	011-4977
DESIGNED BY:	DMC/LGC
DRAWN BY:	DMC/LGC
CHECKED BY:	LSW
APPROVED BY:	LSW
DATE:	12/16/2021



LANDSCAPE STRUCTURES

---

VIOLET CROWN TRAIL  
AUSTIN, TEXAS

## ENTRY GATEWAY SECTIONS & DETAILS

Copyright 2021  
SHEET NO.  
238 OF 239

SPC-2012-0104D(R5)

**FOR PERMITTING ONLY**

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF  
PERMITTING ONLY, UNDER THE AUTHORITY OF:

NAME: LARRY S. T. WU  
P.E. No: 89530  
DATE: 12/16/2021

AND IS NOT INTENDED TO BE USED FOR  
CONSTRUCTION PURPOSES.





**ATTACHMENT G – INSPECTION,  
MAINTENANCE, REPAIR AND RETROFIT  
PLAN**



# WATER QUALITY AND DETENTION POND MAINTENANCE AND INSPECTION PLAN



07/02/20274

*Mike Mullone*

## Objective:

The OWNER and contractor shall provide for adequate long term maintenance and continuation of the stormwater control measures described in the Stormwater Pollution Prevention Plan (SWPPP) to ensure that the facilities are and remain in proper working condition in accordance with approved design standards, rules and regulations and applicable laws. The OWNER and/or contractor shall perform preventative maintenance activities at intervals described in the inspection schedule along with necessary landscaping (grass cutting, etc.) and trash removal as part of regular maintenance.

The required maintenance interval for stormwater Best Management Practices (BMPs) are often dependent upon the degree of pollutant loading from a particular drainage basin. BMP maintenance can best be broken into three categories: inspection, routine maintenance, and major maintenance. Though each BMP type has its own unique characteristics, inspections will generally consist of an assessment to assure its functionality and the general condition. Routine maintenance will generally consist of trash and vegetation removal, unclogging of drains, routine pump assessments (if applicable), minor sediment removal and exchange of filter media where applicable. Major maintenance will be completed as required from inspections and generally consists of significant reconstruction due to failures in the BMP. Examples of major maintenance include dredging, excavation, removal of existing media, replacing fabric, replacing the under-drain, and reestablishment of vegetation.

The following schedule is offered as a guideline for performing inspection and routine maintenance for a range of BMP categories.

Inspection Frequency:	SA = semi-annual	S = after storms > 0.5 inches
	A = annually	B = bi-monthly
BMP	Inspection Frequency	Routine Maintenance Frequency
Sedimentation Pond	SA,S,B	SA = 2x/year
Filtration Pond	SA,S,B	SA = 2x/year
Detention Pond	A,S,B	A = 1 x/year

### Bi-Monthly

Remove woody vegetative growth from pond area including embankments. Minimize heavy equipment, including mowers, in the vegetated areas to reduce compaction. Mow monthly between the months of April and October or anytime vegetation exceeds 12-inches in height. Inspect and remove invasive plants. Remove obstructions in orifices and/or outlets.

### Semi-Annually

Repair animal burrows and/or other leaks in the pond structures/embankments. Remove debris from overflow spillway. Remove trash, floating debris, and/or accumulated sediment. Test all components of pump station (if applicable).

### Annually – As Necessary

Repair erosion to outfall or spillway. Repair and/or replace damaged structures, such as, risers, pipes, and headwalls. Dredge pond on a 3-5 year cycle or as necessary to retain design capacity.

## **General Maintenance Procedures**

Periodic silt removal shall occur when standing water conditions occur or the pond's storage volume is reduced by more than 10%. Silt shall be removed and the pond returned to original lines and grades shown on the approved engineering plans. In addition, corrective measures are required any time a basin does not drain completely within 48 hours of cessation of inflow. NO STANDING WATER IS ALLOWED in the detention or water quality ponds.

Accumulated litter, sediment, and debris shall be removed as necessary to maintain proper operation of the basin. Disposal shall be in accordance with federal, state and local regulations.

Erosion gullies should be filled and the area reseeded to establish native vegetation coverage.

Overgrown woody vegetation at the outfall of a storm sewer prevents water from discharging from the outfall into the basin. Woody vegetation, such as trees and shrubs, should be cleared from the basin. Excessive vegetation, litter, and sediment accumulations should be removed from basin inlets and outfalls to allow water to enter and exit the basin without obstruction

## **Storm Drain and Inlet Infrastructure to Ponds**

The following are a list of simple steps to keep the storm drains clean that in turn will minimize the general ponds' maintenance needs.

- Keep a tight lid on trash cans and recycling bins, especially during windy days.
- Pick up trash in the property.
- Rake leaves into piles and dispose of properly, per the County and/or City. Do not rake or blow them into the storm drain inlets, drives isles, or parking areas. Direct them onto your property.
- Trim tree limbs as required and remove dead vegetation that is prone to breaking down and becoming windblown.
- Limit use of sand and salt on your driveway and walkways. Sweep up residual sand once the snow and ice has melted and before the next rainstorm, so the sediment doesn't end up in the ponds.
- Pick-up after your dog. Stormwater will pick up the waste and wash it into the storm drain and then to the ponds. Pet waste contains harmful bacteria that impact waterways and water quality.
- Limit fertilizer, pesticide, and herbicide application.
- It is illegal to allow pollutants to flow into a storm drain. If you see someone dumping or not containing pollutants report it.

## **Pumps**

A Site Manager must monitor status of control panel alarms semi-annually. A Pump maintenance (if applicable) contractor must make an inspection annually.

## **Inspection Reports**

All inspections must be recorded and must contain the following information:

- An assessment of the condition and functionality of the stormwater or water quality control.
- Maintenance and repair actions performed on the control facility during the past year.
- The professional opinion of the inspector regarding the current functionality of the control and its ability to operate per the original design specifications.
- Recommendations regarding the need for maintenance or modifications that will allow for the control to be operated per the original design specifications. Inspection and maintenance records must be retained and provided to the city for review upon request.

A log shall be kept of maintenance actions, and inspections. The log should document the condition of the pond system's primary components, mowing, and silt, litter and debris removal dates.

Inspection Report			
Inspection	Date	Repairs	Notes of Future Recommendations
Mowing			
Remove Trash and debris			
Remove grass clippings			
Minor Inspections			
Condition of Pond			
Amount of silt in pond			
Amount of ponded water			
Location of Erosion			
Percent of vegetation			
Major Inspections			
Condition of Stormwater Quality Structure			
Type of Stormwater Quality Structure			
Structure type and Condition			
Condition of Rip-Rap			
Condition of filtration system			
Berm or Embankment Settlement			
Location of erosion			
Evidence of Animals			

\* Make copies as necessary

**Sketch Page, If Necessary**

\* Make copies of this page as necessary

**Photographs:**

Please attach photographs taken of each assessment inspection in this section of the report. Include a description of each photograph. Attach additional pages as needed.

**Inspection results:**

☐

**Pass**

Inspection determined that the facility is operating as it was originally designed and no apparent problems exist.

☐

**Pass with conditions**

The facility is operating as it was originally designed, however, some maintenance items should be addressed as a good housekeeping measure to prevent future deficiencies. These maintenance items are addressed in the above assessments and/or in the additional comments listed below.

☐

**Fail**

Inspection of the facility determined that deficiencies were discovered and the facility is not operating as it was originally designed. Maintenance and/or recommended repairs are addressed in the individual assessments and/or in the additional comments section of this report.



## **ATTACHMENT H – PILOT-SCALE FIELD TESTING PLAN**

N/A – No pilot-scale field testing plan. A water quality pond has been provided in accordance with TCEQ technical guidance manual.

# **ATTACHMENT I – MEASURES FOR MINIMIZING SURFACE STREAM CONTAMINATION**

N/A –.. Refer to the Temporary and Permanent BMP sections of this From TCEQ 600 for controlling potential contamination upstream of the San Marcos River.

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999


I Kathy Miller,  
\_\_\_\_\_  
Print Name  
CEO  
\_\_\_\_\_  
Title - Owner/President/Other  
of Hill Country Conservancy,  
\_\_\_\_\_  
Corporation/Partnership/Entity Name  
have authorized Jessica Powers and Michael Mullone  
\_\_\_\_\_  
Print Name of Agent/Engineer  
of Dunaway Associates LLC  
\_\_\_\_\_  
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

  
Applicant's Signature

6.20.2024  
Date

THE STATE OF Texas §

County of Travis §

BEFORE ME, the undersigned authority, on this day personally appeared Katherine Miller known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 20<sup>th</sup> day of June, 2024



Shelly R. Rutledge  
NOTARY PUBLIC

Shelly R. Rutledge  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: Sept. 6, 2024

# Owner Authorization Form

Texas Commission on Environmental Quality  
for Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999


## Land Owner Authorization

I, D'Anne Williams of \_\_\_\_\_  
Land Owner Signatory Name

City of Austin, Parks & Recreation Department

Land Owner Name (Legal Entity or Individual)

am the owner of the property located at  
ABS 45 Barton W Acre 5.22



Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize Kathy Miller

Applicant Name (Legal Entity or Individual)

to conduct trail conservancy and management

Description of the proposed regulated activities

at 190 linear feet south of the intersection of William Barton Drive and Columbus Drive

Precise location of the authorized regulated activities

## Land Owner Acknowledgement

I understand that City of Austin, Parks & Recreation Department

Land Owner Name (Legal Entity or Individual)

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

## Land Owner Signature

D'Anne Williams Digitally signed by D'Anne Williams  
Date: 2024 09 03 12:58:32 -05'00'

9-3-2024

Land Owner Signature

Date

THE STATE OF § Texas

County of § Travis

BEFORE ME, the undersigned authority, on this day personally appeared D'Anne Williams  
known to me to be the person whose name is subscribed to the foregoing instrument, and  
acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 3<sup>rd</sup> day of September



J. Canales  
Jennifer Canales NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 5/31/26

Attached: (Mark all that apply)

- ☐ Lease Agreement
- ☐ Signed Contract
- ☐ Deed Recorded Easement
- ☐ Other legally binding document

## ***Applicant Acknowledgement***

I, Kathy Miller of The Hill Country Conservancy  
Applicant Signatory Name Applicant Name (Legal Entity or Individual)  
acknowledge that City of Austin, Parks & Recreation Department  
Land Owner Name (Legal Entity or Individual)  
has provided The Hill Country Conservancy  
Applicant Name (Legal Entity or Individual)

with the right to possess and control the property referenced in the Edwards Aquifer protection plan.

I understand that The Hill Country Conservancy  
Applicant Name (Legal Entity or Individual)

is contractually responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation. I further understand that failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

### ***Applicant Signature***

[Signature]  
Applicant Signature

9.4.2024  
Date

THE STATE OF § Texas

County of § Travis

BEFORE ME, the undersigned authority, on this day personally appeared Katherine Miller  
known to me to be the person whose name is subscribed to the foregoing instrument, and  
acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 4<sup>th</sup> day of September, 2024



Shelly R. Rutledge  
NOTARY PUBLIC

Shelly R. Rutledge  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: Sept. 6, 2024

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Violet Crown Trailhead-Mile Zero

Regulated Entity Location: @ SW Intersection of Columbus Dr. & William Barton Dr.

Name of Customer: Hill Country Conservancy

Contact Person: Michael Mullone

Phone: 512-399-5373

Customer Reference Number (if issued): CN CN603578816

Regulated Entity Reference Number (if issued): RN \_\_\_\_\_

### Austin Regional Office (3373)

☐ Hays

☒ Travis

☐ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☒ Recharge Zone

☐ Contributing Zone

☐ Transition Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$ 500
Extension of Time	Each	\$

Signature: Jessica Powers

Digitally signed by Jessica Powers  
DN: C=US, E=jpowers@dunaway.com,  
CN=Jessica Powers  
Date: 2024.07.11 11:23:21-05'00'

Date: 7/11/2024



# Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

## ***Water Pollution Abatement Plans and Modifications***

### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

### ***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150



# TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
<b>2. Customer Reference Number</b> (if issued)	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a>	<b>3. Regulated Entity Reference Number</b> (if issued)
CN 603578816		

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)			
<input type="checkbox"/> New Customer <input checked="" type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership					
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>					
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)				<i>If new Customer, enter previous Customer below:</i>	
Hill Country Conservancy					
<b>7. TX SOS/CPA Filing Number</b>		<b>8. TX State Tax ID</b> (11 digits)		<b>9. Federal Tax ID</b>	<b>10. DUNS Number</b> (if applicable)
156928601		17429481454		74-2948145	
<b>11. Type of Customer:</b>		<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		<input checked="" type="checkbox"/> Other: Nonprofit corporation	
<b>12. Number of Employees</b>				<b>13. Independently Owned and Operated?</b>	
<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator <input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant <input checked="" type="checkbox"/> Other: Trail Conservancy and Operator					
<b>15. Mailing Address:</b>		PO Box 163125			
City		Austin	State	TX	ZIP
				78716	ZIP + 4
<b>16. Country Mailing Information</b> (if outside USA)				<b>17. E-Mail Address</b> (if applicable)	
				ryan@hillcountryconservancy.org	

<b>18. Telephone Number</b>	<b>19. Extension or Code</b>	<b>20. Fax Number (if applicable)</b>
( 512)923-2925		(   )   -

## SECTION III: Regulated Entity Information

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity' is selected, a new permit application is also required.)								
<input type="checkbox"/> New Regulated Entity <input checked="" type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information								
<i>The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).</i>								
<b>22. Regulated Entity Name</b> (Enter name of the site where the regulated action is taking place.)								
Hill Country Conservancy								
<b>23. Street Address of the Regulated Entity:</b>  (No PO Boxes)								
	City		State		ZIP		ZIP + 4	
<b>24. County</b>								

If no Street Address is provided, fields 25-28 are required.

<b>25. Description to Physical Location:</b>	@SW Intersection at Columbus and William Barton Drive							
<b>26. Nearest City</b>	Austin	<b>State</b>				<b>Nearest ZIP Code</b>		
		Texas				78705		
<i>Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).</i>								
<b>27. Latitude (N) In Decimal:</b>					<b>28. Longitude (W) In Decimal:</b>			
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds			
30	15	51.336N	97	46	23.628W			
<b>29. Primary SIC Code</b> (4 digits)	<b>30. Secondary SIC Code</b> (4 digits)		<b>31. Primary NAICS Code</b> (5 or 6 digits)		<b>32. Secondary NAICS Code</b> (5 or 6 digits)			
7990			237990					
<b>33. What is the Primary Business of this entity?</b> (Do not repeat the SIC or NAICS description.)								
Public Park - Open Space								
<b>34. Mailing Address:</b>	PO Box 163125							
	City	Austin	State	TX	ZIP	78716	ZIP + 4	
<b>35. E-Mail Address:</b>	ryan@hillcountryconservancy.org							
<b>36. Telephone Number</b>	<b>37. Extension or Code</b>		<b>38. Fax Number (if applicable)</b>					
( 512 ) 923-2925			(   )   -					

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

## **SECTION IV: Preparer Information**

<b>40. Name:</b>	Mike Mullone	<b>41. Title:</b>	engineer
<b>42. Telephone Number</b>	<b>43. Ext./Code</b>	<b>44. Fax Number</b>	<b>45. E-Mail Address</b>
512-399-5373	( ) -		mmullone@dunaway.com

## **SECTION V: Authorized Signature**

**46.** By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

<b>Company:</b>	Dunaway Associates LLC	<b>Job Title:</b>	Senior Project Engineer, Associate
<b>Name (In Print):</b>	Mike Mullone	<b>Phone:</b>	( 512 ) 399- 5373
<b>Signature:</b>		<b>Date:</b>	7/11/2024