Modification of Contributing Zone Plan

For

AAA Storage at FM 1826

12100 Ranch to Market Rd 1826 Austin, TX 78737



Prepared By Hill Country Civil, LLC 1042 Northpark Ridge New Braunfels, TX 78130 Ross Corder, PE





Application Cover Page

Texas Commission on Environmental Quality Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with <u>30 TAC 213</u>.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Appaloosa Run Storage Facility				2. Regulated Entity No.:RN111012910				
3. Customer Name: A-A-A Storage FM 1826			4. Customer No.:CN6505766427					
5. Project Type: (Please circle/check one)	New	Modif	ication)	Exter	nsion	Exception	
6. Plan Type: (Please circle/check one)	WPAP CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential	Non-r	residen	tial		8. Sit	e (acres):	17.88 acres
9. Application Fee:	\$6,500	10. P	10. Permanent BMP(s):			s):	(2) Batch Deter	ntion Ponds
11. SCS (Linear Ft.):		12. AST/UST (No. Tanks):			nks):	N/A		
13. County:	Travis	14. W	aters	hed:			Bear Creek	

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)		Х			
Region (1 req.)		Х	_		
County(ies)		X	_		
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock		

San Antonio Region							
County:	Bexar	Comal	Kinney	Medina	Uvalde		
Original (1 req.)		_					
Region (1 req.)							
County(ies)			_				
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde		
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA		

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Ross Corder, PE

Print Name of Customer/Authorized Agent

Roos Cont

10-04-2024

Signature of Customer/Authorized Agent

Date

FOR TCEQ INTERNAL USE ONL	_Y			
Date(s)Reviewed:		Date Administratively Complete:		
Received From:		Correct N	Number of Copies:	
Received By:		Distribution Date:		
EAPP File Number:		Complex:		
Admin. Review(s) (No.):		No. AR Rounds:		
Delinquent Fees (Y/N):		Review Time Spent:		
Lat./Long. Verified:		SOS Customer Verification:		
Agent Authorization Complete/Notarized (Y/N):		Fee	Payable to TCEQ (Y/I	N):
Core Data Form Complete (Y/N):		Check: Si	Signed (Y/N):	
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):	



Modification of a Previously Approved Contributing Zone Plan

Modification of a Previously Approved Contributing Zone Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Modification of a Previously Approved Contributing Zone Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Ross Corder, PE

Date: <u>10-04-2024</u>

Signature of Customer/Agent:

Koos Cont

Project Information

 Current Regulated Entity Name: <u>A-A-A Storage FM 1826</u> Original Regulated Entity Name: <u>A-A-A Storage FM 1826</u> Assigned Regulated Entity Number(s) (RN): <u>RN111012910</u> Edwards Aquifer Protection Program ID Number(s): <u>11001983</u>

The applicant has not changed and the Customer Number (CN) is: <u>CN605766427</u>

- The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
- 2. Attachment A: Original Approval Letter and Approved Modification Letters. A copy of the original approval letter and copies of any modification approval letters are attached.
- 3. A modification of a previously approved plan is requested for (check all that apply):

Any physical or operational modification of any best management practices or structure(s), including but not limited to temporary or permanent ponds, dams, berms, silt fences, and diversionary structures;
 Any change in the nature or character of the regulated activity from that which was originally approved;
 A change that would significantly impact the ability to prevent pollution of the

- A change that would significantly impact the ability to prevent pollution of the
 Edwards Aquifer and hydrologically connected surface water; or
- Any development of land previously identified in a contributing zone plan as undeveloped.
- 4. Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

CZP Modification	Approved Project	Proposed Modification
Summary		
Acres	<u>17.89</u>	<u>17.89</u>
Type of Development	<u>Commercial</u>	<u>Commercial</u>
Number of Residential	<u>N/A</u>	<u>N/A</u>
Lots		
Impervious Cover (acres)	<u>4.35</u>	<u>10.40</u>
Impervious Cover (%)	<u>34%</u>	<u>58%</u>
Permanent BMPs	Retention/Irrigation	2-Batch Ponds
Other		
AST Modification	Approved Project	Proposed Modification
Summary		
Number of ASTs	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>
UST Modification	Approved Project	Proposed Modification
Summary		
Number of USTs	<u>N/A</u>	<u>N/A</u>
Other	<u>N/A</u>	<u>N/A</u>

5. Attachment B: Narrative of Proposed Modification. A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved,

including previous modifications, and how this proposed modification will change the approved plan.

- 6. Attachment C: Current Site Plan of the Approved Project. A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.
 The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was **not** constructed as approved.
 - The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was constructed as approved.
 - The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was **not** constructed as approved.
- 7. Acreage has not been added to or removed from the approved plan.
 Acreage has been added to or removed from the approved plan and is discussed in *Attachment B: Narrative of Proposed Modification*.
- 8. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.



Attachment A: Original Approval Letter and Approved Modification Letters

Jon Niermann, *Chairman* Emily Lindley, *Commissioner* Bobby Janecka, *Commissioner* Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

May 14, 2020

Mr. John Munich A-A-A Storage FM 1826, LLC 4203 Spinnaker CV Austin, TX 78731

Re: Edwards Aquifer, Travis County

NAME OF PROJECT: Appaloosa Run Storage Facility; Located North of Appaloosa Run and FM 1826, Austin, TX

TYPE OF PLAN: Request for Approval of a Contributing Zone Plan (CZP) 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program ID No. 11001983; Regulated Entity No. RN111012910

Dear Mr. Munich:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the request for approval of a CZP Application for the above-referenced project submitted to the Austin Regional Office by Doucet and Associates, Inc. on behalf A-A-A Storage FM 1826, LLC on March 18, 2020. Final review of the CZP application was completed after additional material was received on May 13, 2020. As presented to the TCEO, the Temporary and Permanent Best Management Practices (BMPs) and construction plans were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer Protection Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been requested.

PROJECT DESCRIPTION

The proposed commercial development will have a site area of approximately 17.88 acres. It will include the construction of 11 buildings, surface parking, access drives, and utilities. The impervious cover will be 4.36 acres (24.38 %). According to a letter dated February 25, 2020, signed by Michael Chapa, P.E., D.R. with Travis County, the site in the development is acceptable for the use of on-site sewage facilities.

TCEQ Region 11 • P.O. Box 13087 • Austin, Texas 78711-3087 • 512-339-2929 • Fax 512-339-3795

Mr. John Munich Page 2 May 14, 2020

PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, a retention irrigation system, designed using the City of Austin Environmental Criteria Manual, will be used to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 3,795 pounds of TSS generated from the 4.36 acres of impervious cover. The approved measures meet the required 80 percent removal of the increased load in TSS caused by the project.

STANDARD CONDITIONS

- 1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
- 2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
- 3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

Prior to Commencement of Construction:

- 4. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved CZP and this notice of approval shall be maintained at the project location until all regulated activities are completed.
- 5. Any modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.
- 6. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the Austin Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person. The executive director will use the notification to determine if the approved plan is eligible for an extension.
- 7. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved CZP, must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established and the construction area is stabilized. If a water quality pond is proposed, it shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

- 8. During the course of regulated activities related to this project, the applicant or agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
- 9. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment.
- 10. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
- 11. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge will be filtered through appropriately selected best management practices. These may include vegetated filter strips, sediment traps, rock berms, silt fence rings, etc.
- 12. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 13. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

- 14. Owners of permanent BMPs and measures must ensure that the BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the Austin Regional Office within 30 days of site completion.
- 15. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through the Austin Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
- 16. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved CZP. If the new owner intends to commence any new regulated activity on the site, a new CZP that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.

Mr. John Munich Page 4 May 14, 2020

- 17. A CZP approval or extension will expire and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new plan must be submitted to the Austin Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
- 18. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Ms. Jade Mendiola, of the Edwards Aquifer Protection Program of the Austin Regional Office at (512) 339-2929.

Sincerely,

Robert Sadlier, Section Manager Edwards Aquifer Protection Program Texas Commission on Environmental Quality

RCS/jkm

Enclosure: Change in Responsibility for Maintenance of Permanent BMPs, Form TCEQ-10263 Deed Recordation Affidavit, Form TCEQ-0625A

Deed Recordation Affidavit

Edwards Aquifer Protection Plan

THE STATE OF TEXAS

County of _____ §

ß

BEFORE ME, the undersigned authority, on this day personally appeared ______ who, being duly sworn by me, deposes and says:

- (1) That my name is ______and that I own the real property described below.
- (2) That said real property is subject to an EDWARDS AQUIFER PROTECTION PLAN which was required under the 30 Texas Administrative Code (TAC) Chapter 213.
- (3) That the EDWARDS AQUIFER PROTECTION PLAN for said real property was approved by the Texas Commission on Environmental Quality (TCEQ) on ______.

A copy of the letter of approval from the TCEQ is attached to this affidavit as Exhibit A and is incorporated herein by reference.

(4) The said real property is located in _____ County, Texas, and the legal description of the property is as follows:

LANDOWNER-AFFIANT

SWORN AND SUBSCRIBED TO before me, on this _ day of _____, ____.

NOTARY PUBLIC

THE STATE OF _____ §

County of _____ §

BEFORE ME, the undersigned authority, on this day personally appeared ______ known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this __ day of _____, ____,

NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: _____

Change in Responsibility for Maintenance on Permanent Best Management Practices and Measures

The applicant is no longer responsible for maintaining the permanent best management practice (BMP) and other measures. The project information and the new entity responsible for maintenance is listed below.

Customer:		 		
Regulated Entity Name:		 		
Site Address:		 		
City, Texas, Zip:		 		
County:		 		
Approval Letter Date:		 	· · · · · · · · · · · · · · · · · · ·	
BMPs for the project:		 		
New Responsible Party	:	 		
Name of contact:		 		
Mailing Address:		 		
City, State:		 	Zip:	
Telephone:		 FAX:		

Signature of New Responsible Party

Date

I acknowledge and understand that I am assuming full responsibility for maintaining all permanent best management practices and measures approved by the TCEQ for the site, until another entity assumes such obligations in writing or ownership is transferred.

If you have questions on how to fill out this form or about the Edwards Aquifer protection program, please contact us at 210/490-3096 for projects located in the San Antonio Region or 512/339-2929 for projects located in the Austin Region.

Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at 512/239-3282.

Attachment B: Narrative of Proposed Modification

A-A-A FM 1826 Phase 1 and 2 was approved with 4.85 acres of proposed impervious cover on a total site area of 17.89 acres. The Phase 1 and 2 impervious cover is treated by an existing irrigation/retention pond. The site is fully constructed and operational at this time.

A new expansion of the development is planned, with proposed Phase 3 and 4. This new expansion will include the construction of additional buildings, parking and drives needed to serve the development. The new development will create a new site total impervious cover of 10.40 acres out of the 17.89 acre tract, or 58%.

The increase in TSS generated by the proposed expansion will require modification to the existing irrigation/retention pond along with the construction of a new pond. The existing irrigation/retention pond will be modified to a Batch Detention Pond (Pond 1) located generally in the same location, although expanded in footprint and volume. Additionally, there was an existing onsite channel that routed upgradient runoff around the Phase 1 and 2 Development. Given the location of development, this channel is also now routed to Batch Pond 1. The outfall location remains the same, as it outfalls to the east into the TxDOT ROW.

Pond 2 will also be a Batch Detention Pond and will treat runoff that drains to the southwest for primarily the southern portion of the development. This pond will outfall towards the southwest property corner. Both ponds are sized using TCEQ RG-348 Criteria, and incorporate some level of overtreatment, as some drainage areas could not be captured. Reference the attached RG-348 Calculations for both Pond 1 and Pond 2.





Attachment C: Current Site Plan



COVI L / BA	ER ARTON SPRII	NGS ZONE
/QTZ)	0.19	ACRES
WQTZ AREA	0.00 4.36	_ACRES _ACRES
DRY	0.002	_Acres
-	<u>0%</u> 25%	-

vious	VIOUS COVER					
OUS	DRIVEWAYS/ ROADWAYS					
iory	ACRES	% OF CATEGORY				
	1.69	10%				
	0.00	0%				
	0.00	0%				
	0.00	0%				

	25 0 12.5 25 50 (IN FEET) GRAPHIC SCALE 1"=50'
L	EGEND
	PROPOSED BUILDING
	PROPERTY LINE
(12)	PROPOSED PARKING SPACES SYSL/4"
←	TRAFFIC DIRECTION
	PROPOSED CONCRETE PAVEMENT. SEE DETAIL SHEET.
	PROPOSED CONCRETE SIDEWALK. SEE DETAIL SHEET.
	PROPOSED ENGINEERED PAVERS. SEE DETAIL SHEET.
$\begin{array}{c} \downarrow & \downarrow & \downarrow & \downarrow \\ \downarrow & \downarrow & \bigcup \\ \downarrow & \downarrow & \downarrow \\ \downarrow & \downarrow & \downarrow \\ \end{array} \downarrow \qquad \downarrow$	PRIVATE COMMON OPEN SPACE AREA

SITE DATA TABLE				
	ACRES	SF		
TOTAL SITE AREA	17.88	778853		
EXISTING IMP. COVER	0.20	8885		
PROPOSED IMP. COVER	4.35	189486		
ALLOWABLE IMP. COVER	4.36	189922		
LOC	13.37	582397		
TOTAL BUILDINGS	13			
TOTAL PARKING	99			
ACCESSIBLE SPACES	5			
STANDARD	94			



- L. COMPLIANCE WITH THE COMMERCIAL AND MULTI-FAMILY RECYCLING ORDINANCE IS MANDATORY FOR MULTI-FAMILY COMPLEXES AND BUSINESSES AND OFFICE BUILDINGS. SPACE SHOULD BE PROVIDED ON-SITE FOR STORAGE OR RECYCLING CONTAINERS.
- 2. ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRE SITE PLAN AMENDMENT AND APPROVAL OF THE DEVELOPMENT SERVICES DEPARTMENT.
- 3. APPROVAL OF THIS SITE PLAN DOES NOT INCLUDE BUILDING AND FIRE CODE APPROVAL NOR BUILDING PERMIT APPROVAL.
- 4. ALL SIGNS MUST COMPLY WITH REQUIREMENTS OF THE LAND DEVELOPMENT CODE (CHAPTER 25-10).
- 5. ADDITIONAL ELECTRICAL EASEMENTS MAY BE REQUIRED AT A LATER DATE. 6. ALL EXISTING STRUCTURES SHOWN TO BE REMOVED WILL REQUIRE A DEMOLITION PERMIT FROM THE CITY OF AUSTIN DEVELOPMENT SERVICES DEPARTMENT.
- 7. A DEVELOPMENT PERMIT MUST BE ISSUED PRIOR TO AN APPLICATION FOR BUILDING PERMIT FOR NON-CONSOLIDATED OR PLANNING COMMISSION APPROVED SITE PLANS.
- 3. FOR DRIVEWAY CONSTRUCTION: THE OWNER IS RESPONSIBLE FOR ALL COSTS FOR RELOCATION OF, OR DAMAGE TO UTILITIES.
- 9. FOR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, A ROW EXCAVATION PERMIT IS REQUIRED.
- 10. APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN INDICATES COMPLIANCE WITH APPLICABLE CITY REGULATIONS ONLY. COMPLIANCE WITH ACCESSIBILITY STANDARDS SUCH AS THE 2010 STANDARDS FOR ACCESSIBLE DESIGN OR THE 2012 TEXAS ACCESSIBILITY STANDARDS WAS NOT VERIFIED. THE APPLICANT IS RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE ACCESSIBILITY STANDARDS.

BUILDING DATA					
BUILDING #	AREA (S.F.)	CONSTRCUTION TYPE	STORIES	HEIGHT	
1	3,900	TYPE 2	1	12'-0"	
2	7,800	TYPE 2	1	12'-0"	
3	22,604	TYPE 2	2	24'-0"	
4	18,772	TYPE 2	2	24'-0"	
5	18,772	TYPE 2	2	24'-0"	
6	3,950	TYPE 2	1	12'-0"	
7	4,650	TYPE 2	1	12'-0"	
8	14,000	TYPE 2	1	12'-0"	
9	13,800	TYPE 2	1	12'-0"	
10	15,050	TYPE 2	1	12'-0"	
11	12,000	TYPE 2	1	12'-0"	
12	1,444	TYPE 2	1	12'-0"	



SP-2019-0082D



Contributing Zone Plan Application

Contributing Zone Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: <u>AAA_Storage FM 1826</u>

Date: <u>10-0</u>4-2024

Signature of Customer/Agent:

Roos Cont

Regulated Entity Name: <u>A-A-A</u> Storage FM 1826

Project Information

- 1. County: Travis
- 2. Stream Basin: Bear Creek
- 3. Groundwater Conservation District (if applicable):
- 4. Customer (Applicant):

Contact Person: <u>John</u> Muhich Entity: <u>A-A-A</u> Storage FM 1826 Mailing Address: <u>4203</u> Spinnaker CV City, State: <u>Austin</u>, TX Telephone:(<u>512)</u> 657-6789 Email Address: <u>johns</u>muhich@gmail.com

Zip: <u>78731</u> Fax: _____

TCEQ-10257 (Rev. 02-11-15)

5. Agent/Representative (If any):

Contact Person: <u>Ross</u> Corder, PE Entity: <u>Hill C</u>ountry Civil Mailing Address: <u>1042</u> Northpark Ridge City, State: <u>New B</u>raunfels, TX Telephone: <u>(210)</u> 378-4953 Email Address: <u>ross@</u>hillcountrycivil.com

Zip: <u>78130</u> Fax: _____

6. Project Location:

The project site is located inside the city limits of _____.

X The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of <u>Austin</u>

The project site is not located within any city's limits or ETJ.

7. X The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

The AAA FM 1826 project is located southwest intersection of FM 1826 and Dalea Drive.

- 8. X Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
- 9. X Attachment B USGS Quadrangle Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:

X Project site boundaries.

X USGS Quadrangle Name(s).

10. X Attachment C - Project Narrative. A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:



- X Offsite areas
- X Impervious cover
- X Permanent BMP(s)
- X Proposed site use
- X Site history
- X Previous development
- X Area(s) to be demolished
- 11. Existing project site conditions are noted below:
 - X Existing commercial site
 - Existing industrial site
 - Existing residential site

X Existing paved and/or unpaved roads

Undeveloped (Cleared)

Undeveloped (Undisturbed/Not cleared)

- Other: _____
- 12. The type of project is:

Residential: # of Lots: _____
 Residential: # of Living Unit Equivalents: _____
 X Commercial
 Industrial
 Other: _____

13. Total project area (size of site): <u>17.88</u> Acres

Total disturbed area: _____ Acres

- 14. Estimated projected population:
- 15. The amount and type of impervious cover expected after construction is complete is shown below:

Table	1	-	Impervious Cover	
-------	---	---	-------------------------	--

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	221,827	÷ 43,560 =	5.1
Parking	231,091	÷ 43,560 =	5.3
Other paved surfaces	0	÷ 43,560 =	0
Total Impervious Cover	452,918	÷ 43,560 =	10.4

Total Impervious Cover $\frac{10.4}{10.4}$ ÷ Total Acreage $\frac{17.88}{100}$ X 100 = $\frac{58}{100}$ % Impervious Cover

16. X Attachment D - Factors Affecting Surface Water Quality. A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. X Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

For Road Projects Only

Complete questions 18 - 23 if this application is exclusively for a road project.

X N/A

18.	Туре	of	project:
-----	------	----	----------

TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways. 19. Type of pavement or road surface to be used: Concrete Asphaltic concrete pavement Other: 20. Right of Way (R.O.W.): Length of R.O.W.: _____ feet. Width of R.O.W.: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$ 21. Pavement Area: Length of pavement area: _____ feet. Width of pavement area: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$ Pavement area acres ÷ R.O.W. area acres x 100 = % impervious cover.

22. A rest stop will be included in this project.

A rest stop will not be included in this project.

23. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

24. Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

25. Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

X N/A

- 26. Wastewater will be disposed of by:
 - X On-Site Sewage Facility (OSSF/Septic Tank):
 - X Attachment F Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.
 - X Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the _____ (name) Treatment Plant. The treatment facility is:

	Existing.
	Proposed.
X N//	4

Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons

Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.

XN/A

27. Tanks and substance stored:

Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1			
2			
3			
4			
5			
	*	То	tal x 1 E = Gallons

Total x 1.5 = ____ Gallons

28. The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than

one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

Attachment G - Alternative Secondary Containment Methods. Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

Table	3 -	Secondary	Containment
-------	-----	-----------	-------------

Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons

Total: _____ Gallons

30. Piping:

] All piping, hoses, and dispensers will be located inside the containment structure.

Some of the piping to dispensers or equipment will extend outside the containment structure.

The piping will be aboveground

The piping will be underground

- 31. The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of:
- 32. Attachment H AST Containment Structure Drawings. A scaled drawing of the containment structure is attached that shows the following:
 - Interior dimensions (length, width, depth and wall and floor thickness).
 - Internal drainage to a point convenient for the collection of any spillage.

Tanks clearly labeled

Piping clearly labeled

Dispenser clearly labeled

33. Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.

In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

Site Plan Requirements

Items 34 - 46 must be included on the Site Plan.

34. X The Site Plan must have a minimum scale of 1'' = 400'.

Site Plan Scale: 1" = <u>40</u>'.

35. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

X No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): _____.

36. X The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

- 37. X A drainage plan showing all paths of drainage from the site to surface streams.
- 38. X The drainage patterns and approximate slopes anticipated after major grading activities.
- 39. X Areas of soil disturbance and areas which will not be disturbed.
- 40. X Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 41. X Locations where soil stabilization practices are expected to occur.
- 42. Surface waters (including wetlands).

X N/A

43. Locations where stormwater discharges to surface water.

X There will be no discharges to surface water.

44. Temporary aboveground storage tank facilities.

X Temporary aboveground storage tank facilities will not be located on this site.

45. Permanent aboveground storage tank facilities.

X Permanent aboveground storage tank facilities will not be located on this site.

46. X Legal boundaries of the site are shown.

Permanent Best Management Practices (BMPs)

Practices and measures that will be used during and after construction is completed.

47. X Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.



- 48. X These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 - X The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____.

🗌 N/A

49. X Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

🗌 N/A

50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

The site will be used for low density single-family residential development but has more than 20% impervious cover.

X The site will not be used for low density single-family residential development.

The executive director may waive the requirement for other permanent BMPs for multi-
family residential developments, schools, or small business sites where 20% or less
impervious cover is used at the site. This exemption from permanent BMPs must be
recorded in the county deed records, with a notice that if the percent impervious cover
increases above 20% or land use changes, the exemption for the whole site as described in
the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing
and Approval), may no longer apply and the property owner must notify the appropriate
regional office of these changes.

Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for
multi-family residential developments, schools, or small business sites and has 20%
or less impervious cover. A request to waive the requirements for other permanent
BMPs and measures is attached.

The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.

X The site will not be used for multi-family residential developments, schools, or small business sites.

52. X Attachment J - BMPs for Upgradient Stormwater.

A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.

No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.

Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

53. X Attachment K - BMPs for On-site Stormwater.

A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
 Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff.

54. X Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.

□ N/A

55. X Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

N/A

56. X	Attachment N - Inspection, Maintenance, Repair and Retrofit Plan. A site and BMP
	specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the
	permanent BMPs and measures is attached. The plan fulfills all of the following:
	$\overline{ X }$ Prepared and certified by the engineer designing the permanent BMPs and

- measures
- X Signed by the owner or responsible party
- X Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.
- X Contains a discussion of record keeping procedures
- □ N/A
- 57. Attachment O Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.

X N/A

58. X Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.

□ N/A

Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.

- 59. X The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- 60. X A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development,

or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

Administrative Information

- 61. X Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. X Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
 - X The Temporary Stormwater Section (TCEQ-0602) is included with the application.



Attachment A-Road Map

Google Maps TCEQ Bldg E, 12118 N Interstate Hwy 35, Austin, TX Drive 31.8 miles, 32 min 78753 to AAA Storage Austin Texas, 12100 Ranch to Market Rd 1826, Austin, TX 78737



Map data ©2024 Google

2 mi L

A	This route has tolls.
	A

Get on I-35 S

↑	1.	2 min (Head northeast toward S I-35 Frontage Rd Restricted usage road	0.8 mi)
۲	2.	Turn right onto S I-35 Frontage Rd	187 ft
*	3.	Use the left lane to take the ramp onto I-35 S	0.6 mi
			0.1 mi

Continue on I-35 S. Take US-183 S to 183 Toll

*	4.	6 min (6.3 mi) Merge onto I-35 S
ŕ	5.	2.9 mi Use the 2nd from the right lane to take the exit toward US-183 S
*	6.	0.1 mi Use the left lane to take the ramp to U.S. 183 S

		7,	nin (7 5
n	8. <u> </u>	Keep left to continue on 183 Toll Toll road	inin (7.5
,	9. 🔺 T	Use the left 2 lanes to turn slightly left on Texas State Hwy 71 W/Ben white Blvd rai Toll road	to the
			- 1.0
op S	S to	TX-45 W. Exit from TX-1 Loop S	
op S	S to	TX-45 W. Exit from TX-1 Loop S	
op S	S to ⁻ 10. 11.	TX-45 W. Exit from TX-1 Loop S 14 m Merge onto State Hwy 71/E Ben White E Continue onto State Hwy 71 W/US-290 1	in (14.6 Blvd 4.: W/W B
op S	S to 10. 11.	TX-45 W. Exit from TX-1 Loop S 14 m Merge onto State Hwy 71/E Ben White E Continue onto State Hwy 71 W/US-290 V White Blvd	in (14.6 Blvd — 4.: W/W B — 2.:
op s ג ר	S to ⁻ 10. 11. 12.	TX-45 W. Exit from TX-1 Loop S 14 m Merge onto State Hwy 71/E Ben White E Continue onto State Hwy 71 W/US-290 W White Blvd Use the 2nd from the right lane to stay of W	in (14.6 Blvd — 4.: W/W B — 2.: on US-2
op	10. 11. 11. 12.	TX-45 W. Exit from TX-1 Loop S 14 m Merge onto State Hwy 71/E Ben White E Continue onto State Hwy 71 W/US-290 W White Blvd Use the 2nd from the right lane to stay of W Take the exit onto TX-1 Loop S	in (14.6 Blvd — 4.: W/W B — 2.: on US-2 — 1.: — 1.:

↑	15.	Continue onto TX-45 W	
۲	16.	Use any lane to turn left onto Ranch to Mark 1826	2.3 mi et Rd
ر ا	17.	Turn right	0.4 mi
			98 II



Attachment B-USGS Quadrangle Map

AAA FM 1826 USGS Map



7.5 Minute Quad Grid Signal Hill Quad

TCEQ_EDWARDS_OFFICIAL_MAPS

8/30/2024, 9:14:13 AM

Edwards Aquifer Label

Edwards Aquifer Boundary

Edwards Aquifer Boundary central line

0.5 mi

0.8 km

0.25

0.4

0.13

0.2

Copyright:© 2013 National Geographic Society, i-cubed, TCEQ

n


Attachment C-Narrative

Attachment C: Project Narrative

A-A-A FM 1826 Appaloosa Storage is a storage and mixed-use facility located at 12100 RM 1826 in Travis County, TX. The 17.89-acre property is located fully within Travis County and recently has been removed from the City of Austin ETJ. Furthermore, the project is located entirely inside of the Edwards Aquifer Contributing Zone. The tract is not located within a 100-Year Floodplain per FEMA Panel No. 48453C0560J. The site generally drains from the northwest to southeast, towards the RM 1826 ROW. However, a portion of the tract drains towards the southwest. In accordance with 30 TAC Chapter 213, this CZP application is being submitted for the proposed development to occur onsite.

The site is currently fully operational and built per the previously approved CZP for Phase 1 and 2. However, a new expansion is planned and documented in this CZP Modification, which includes Phases 3 and 4. This new expansion includes a new total impervious cover of 10.40 acres, which generates 8,817 lbs of TSS per RG-348 methodology.

The existing irrigation/retention pond will be eliminated and expanded into a new proposed Batch Detention Pond in order to treat the increased TSS for this contributing area. In addition, this Batch Pond, noted as Pond 1 in the Plans and Calculations, is also sized to treat a portion of the site that is uncaptured (overtreatment). The drainage area for Pond 1 generates 6441 lbs of TSS, but the pond is sized to treat 7,000 lbs of TSS, for an "F" factor of 0.93.

Pond 2 is also a proposed Batch Pond, noted as Pond 2 on the Construction Drawings and Calculations. Pond 2 has a drainage area that contributes 1645 lbs of TSS, but the basin is designed to treat 1,817 of TSS for uncaptured (overtreatment) areas.

There is some offsite drainage that runs through the site. A portion of upgradient flows is routed through Pond 1, while other areas are routed around the site via drainage channels.

Wastewater flows generated by the project will be treated by a new septic system sized to treat the new development. Potable water will be provided by a Public Waster System unique to the development. This PWS is currently being modified and updated based on the proposed improvements with TCEQ.





Attachment D- Factors Affecting Surface Water Quality

Attachment D: Factors Affecting Surface Water Quality

The list below are potential sources of pollution that may be reasonably expected to impact the quality of stormwater runoff from the site during construction.

- Hydrocarbons from asphalt paving construction
- Oil, fuel, grease and hydraulic fluid from construction equipment and automobiles
- Soil erosion due to site clearing, grading and demolition activities
- Trash, litter and construction debris from workers and construction activities
- Concrete truck washout
- Concrete/masonry
- Fertilizers
- Cleaning solvents

The list below are potential sources of pollution that may be reasonably expected to impact the quality of stormwater runoff from the site after construction or after development.

- Trash and litter typical of daily use from customers and tenants
- Oil, fuel, grease and hydraulic fluid from vehicles parked/traveling onsite
- Dirt and dust from landscape areas and vehicles
- Fertilizers
- Cleaning solvents





Attachment E- Volume and Character of Stormwater

Attachment E: Volume and Character of Stormwater

A-A-A FM 1826 site will generate stormwater typical of a commercial/storage development, as outlined in the Travis County Drainage Criteria Manual. Runoff will increase because of the development for all storm events. The proposed 100-year peak stormwater discharge will be mitigated and control by use of two proposed batch detention pond. The volumes for the pond are sized for the 100-year storm and the outlet control structure is also sized to regulate 100-year storm flows.





Attachment F- Suitability Letter from Authorized Agent



TRANSPORTATION AND NATURAL RESOURCES

ONSITE WASTEWATER PROGRAM

411 West 13th Street Executive Office Building PO Box 1748 Austin, Texas 78767 (512) 854-9383 FAX (512) 854-4626

February 25, 2020

Mr. Wenzel,

Re: OSSF Suitability Letter 11.75 Acres of Lot 39, Appaloosa Run

Dear Mr. Wenzel:

This subdivision/lot referenced above is suitable for the use of on-site sewage facilities (OSSF's) in accordance with 30 TAC Chapter 285 and Travis County Code Chapter 48.

Please do not hesitate to call me at (512) 854-7576 if you should have any questions.

Sincerely,

Michael Chapa, P.E., D.R. #OS34900 On-Site Wastewater Program Development Services Division



Attachment J- BMPs for Upgradient Stormwater

Attachment J: BMPs for Upgradient Stormwater

Upgradient flows generated from the western boundary line are intercepted by a proposed onsite channel and routed to the proposed Batch Detention Pond 1. These flows are included in the pond volume analysis and the overflow weir is sized to bypass large storm events generated from this area.

Upgradient flows generated from the northern boundary are intercepted by a proposed onsite channel and routed around the development and directed to the TxDOT ROW. No proposed BMPs are required for this portion of the upgradient flows.





Attachment K- BMPs for On-Site Stormwater

Attachment K: BMPs for On-Site Stormwater

Proposed on-site BMPs include two (2) Batch Detention Ponds designed in accordance with TCEQ's Technical Guidance Manual (TGM) RG-348. The Batch Detention Ponds will be designed as an online facility. For online facilities the principal and emergency spillways must be sized to provide 1.0 foot of freeboard during the 25-year event and to safely pass the flow from the 100-year storm. The water quality volume required in Pond 1 is 52,909 cuft and Pond 2 is 8,781 cuft. Both the 25-year and 100-year storm events are contained within the ponds. The Batch Detention Ponds are sized to treat a total of 8817 lbs of TSS generated by the site.





Attachment L- BMPs for Surface Streams

Attachment L: BMPs for Surface Steams

Upon approval of this plan, the Batch Detention Ponds, traditionally designed, will be constructed before the proposed A-A-A FM 1826 Phase 3 and 4 development starts. Therefore, any storm water run-off leaving the site will be treated per TCEQ RG-348, and no surface steam contamination is anticipated.





Attachment M-Construction Plans

CONTACT INFORMATION

OWNER / DEVELOPER:

A-A-A STORAGE FM 1826 4203 SPINNAKER CV AUSTIN, TX 78731 CONTACT: JOHN MUHICH PHONE: (512) 657-6789

ENGINEER

HILL COUNTRY CIVIL, LLC 1042 NORTHPARK RIDGE NEW BRAUNFELS, TX 78070 CONTACT: ROSS CORDER, PE PHONE: (210) 378-4953 EMAIL: ROSS@HILLCOUNTRYCIVIL.COM

SURVEYOR: CHAPARRAL PROFESSIONAL LAND SURVEYING, INC. 3500 McCALL LANE AUSTIN, TX 78744 CONTACT: ERIC J. DANNHEIM PHONE: (512) 443-1724

SITE INFORMATION

LEGAL DESCRIPTION LOT 39, APPALOOSA RUN, A SUBDIVISION IN TRAVIS COUNTY, TEXAS, ACCORDING TO THE MAP OR PLAT

RECORDED IN VOLUME 67, PAGE 79 OF THE PLAT RECORDS OF TRAVIS COUNTY, TEXAS.

PROJECT ADDRESS 12100 FM 1826 AUSTIN, TX 78737

WATERSHED BEAR CREEK WATERSHED, CONTRIBUTING TO THE BARTON SPRINGS ZONE WATERSHED

CITY GRID WZ15

MAPSCO GRID 670C

REVIEWED BY

TRAVIS COUNTY TRANSPORTATION AND NATURAL RESOURCES DATE

TNR DEVELOPMENT PERMIT NUMBER

NO.

REVISION DESCRIPTION REVIEWED BY DATE

FLOOD PLAIN NOTE

THE TRACT SHOWN HEREON LIES WITHIN ZONE "X" (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN), AS IDENTIFIED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, NATIONAL FLOOD INSURANCE PROGRAM, AS SHOWN ON MAP NO. 48453C0560H, DATED SEPTEMBER 26, 2008, FOR TRAVIS COUNTY, TEXAS AND INCORPORATED AREAS. IF THIS SITE IS NOT WITHIN AN IDENTIFIED SPECIAL FLOOD HAZARD AREA, THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY AND/OR THE STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. THIS FLOOD STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

TRAVIS COUNTY NOTE

THE ENGINEER WHO PREPARED THESE PLANS IS RESPONSIBLE FOR THEIR ADEQUACY. IN REVIEWING THE PLANS, TRAVIS COUNTY MUST RELY UPON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.

GOVERNMENT / UTILITY CONTACT INFORMATION

DIG TESS/ONE CALL	
AT&T	
PEDERNALES ELECTRIC COOP	
TEXAS GAS SERVICE	
TIME WARNER CABLE	
TXDOT	
WEST TRAVIS COUNTY PUA	

811 (512) 870-2736 (888) 554-4732 (512) 465-1134 (830) 646-6938 (512) 832-7000 (512) 263-0100

CONTRACTOR, SUB-CONTRACTOR AND/OR

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH **EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS** AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

HCC JOB NUMBER: 041-01

CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

CIVIL CONSTRUCTION DRAWINGS FOR **APPALOOSA RUN STORAGE** FACILITY PH. 3&4 TRAVIS COUNTY, TX



LOCATION MAP N.T.S

CIVIL SHEET INDEX			
Sheet Title	Sheet Number		
COVER SHEET	1		
GENERAL CONSTRUCTION NOTES	2		
EXISTING CONDITIONS AND DEMOLITION PLAN	3		
EROSION CONTROL PLAN	4		
EROSION CONTROL DETAILS	5		
OVERALL SITE PLAN	6		
FIRE PROTECTION PLAN	7		
DIMENSION CONTROL PLAN (1 OF 5)	8		
DIMENSION CONTROL PLAN (2 OF 5)	9		
DIMENSION CONTROL PLAN (3 OF 5)	10		
DIMENSION CONTROL PLAN (4 OF 5)	11		
DIMENSION CONTROL PLAN (5 OF 5)	12		
OVERALL GRADING PLAN	13		
GRADING PLAN (1 OF 5)	14		
GRADING PLAN (2 OF 5)	15		
GRADING PLAN (3 OF 5)	16		
GRADING PLAN (4 OF 5)	17		
GRADING PLAN (5 OF 5)	18		
DET PONDS - POND 1	19		
DET PONDS - POND 2	20		
DETENTION POND DETAILS	21		
MAINTENANCE PLAN	22		
CHANNEL SECTIONS - CHANNEL 1A	23		
EXISTING DRAINAGE AREA MAP	24		
PROPOSED DRAINAGE AREA MAP	25		
SLOPE MAP	26		
OVERALL UTILITY CONNECTION PLAN	27		
UTILITY CONNECTION PLAN (1 OF 4)	28		
UTILITY CONNECTION PLAN (2 OF 4)	29		
UTILITY CONNECTION PLAN (3 OF 4)	30		
UTILITY CONNECTION PLAN (4 OF 4)	31		
UTILITY DETAILS (1 OF 2)	32		
UTILITY DETAILS (2 OF 2)	33		
SITE DETAILS (1 OF 2)	34		
SITE DETAILS (2 OF 2)	35		



HCC GENERAL CONSTRUCTION NOTES:

- CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE AND FEDERAL BUILDING CODES APPLICABLE TO THIS PROJECT. FURTHERMORE, THE CONTRACTOR WILL BE RESPONSIBLE FOR SECURING REQUIRED PERMITS AND SHALL NOTIFY ALL GOVERNMENT AGENCIES. TCEQ. AND/OR UTILITY AGENCIES AFFECTED BY THE PROPOSED CONSTRUCTION IMPROVEMENTS.
- 2. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SAFETY SYSTEMS, PLANS AND DESIGNS APPLICABLE TO THE PROJECT. HILL COUNTRY CIVIL DOES NOT EXTEND TO OR INCLUDE DESIGNS OR PLANS PERTAINING TO THE SAFETY OF THE CONTRACTOR, SUBCONTRACTORS, EMPLOYEES OR PROJECT SITE. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE ALL SAFETY REGULATIONS. CODES AND ORDINANCES ARE BEING MET DURING THE DURATION OF THE PROJECT.
- CONTRACTOR SHALL FOLLOW ALL SAFETY REQUIREMENTS AND REGULATIONS OUTLINED BY THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION.
- CONTRACTOR SHALL KEEP A COPY OF THE APPROVED PLANS AT THE JOBSITE THROUGHOUT THE DURATION AND COMPLETION OF THE PROJECT.
- PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL COORDINATE WITH LOCAL TV, ELECTRIC, GAS, 5 WATER, SEWER AND PHONE PROVIDERS AS REQUIRED TO PROVIDE SERVICE TO THE PROJECT SITE. IN ADDITION, CONTRACTOR SHALL COORDINATE ANY INTERRUPTIONS OF UTILITY SERVICE TO THE APPLICABLE SERVICE PROVIDER.
- CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN OPERATING NEAR OR AROUND EXISTING GAS LINES. CONTRACTOR SHALL NOTIFY GAS COMPANY 72 HOURS PRIOR TO CONSTRUCTION WHEN OPERATING NEAR GAS LINE FACILITIES.
- CONTRACTOR SHALL PROTECT ALL EXISTING FACILITIES INCLUDING BUT NOT LIMITED TO UTILITIES. 7. PAVEMENT, STREETS, CURB AND GUTTER, TREES, LANDSCAPING, IRRIGATION SYSTEMS, ETC., IMPACTED BY THE PROJECT CONSTRUCTION LIMITS. CONTRACTOR RESTORE ANY DISTURBED AREAS IMPACTED BY CONSTRUCTION TO ITS ORIGINAL OR BETTER CONDITION, INCLUDING ANY AREAS DAMAGED REQUIRING REPAIR (NO SEPARATE PAY ITEM).
- 8. CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT. FURTHERMORE, CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER. TELEPHONE, SEWER, FIBER OPTIC, ELECTRIC, DUCT BANKS, IRRIGATION LINES AND GAS LINES.
- LOCATION AND DEPICTION OF UTILITIES SHOWN ARE FOR REFERENCE ONLY AND PER NOTE 8 ABOVE. SHOULD BE CONFIRMED BEFORE STARTING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND ANY REPAIR COSTS SHALL BE BORNE BY THE CONTRACTOR
- CONTRACTOR SHALL PROTECT EXISTING TREES, BOTH DEPICTED ON THE CONSTRUCTION DRAWINGS AND 10. THOSE TREES WHICH ARE NOT AS WELL. ANY TREES THAT EXIST ON SITE NOT SHOWN TO BE REMOVED, BUT APPEAR TO BE DISTURBED, OR REQUIRED TO BE REMOVED IN ORDER TO MEET THE PROPOSED SITE PLAN, SHALL BE COORDINATED WITH THE LANDSCAPE ARCHITECT, CIVIL ENGINEER OR OWNER PRIOR TO REMOVAL.
- DURING CONSTRUCTION, CONTRACTOR SHALL MAINTAIN UNRESTRICTED DRAINAGE. NO PONDING OF 11 STORM DRAINAGE SHALL BE PERMITTED IN AREAS OF PREPARED SUBGRADE OR EXCAVATION, EMBANKMENT. IF PONDING SHOULD OCCUR, CONTRACTOR SHALL IMMEDIATELY PUMP OUT OR GRAVITY DRAIN PONDING WATER OUT OF IMPACTED AREAS. IF ANY DAMAGE OCCURRED TO SUBGRADE, BUILDING PAD OR EXCAVATION AREAS, THE SOILS MUST BE DRIED OUT, REMOVED, REPLACED AND RE-COMPACTED.
- 12. DISTURBED AREAS (CONSTRUCTION AREAS) SHALL BE STRIPPED OF VEGETATION, LOOSE TOPSOIL, ORGANICS, BRUSH AND DEBRIS. AFTERWARDS, THE EXPOSED SUBGRADE SHALL SHALL BE PROOF ROLLED WITH A MINIMUM 25 TON PNEUMATIC ROLLER. ANY WEAK AREAS DETECTED SHALL BE REMOVED AND REPLACED WITH SUITABLE SOILS OF SIMILAR TYPE (CLASSIFICATION, MOISTURE CONTENT AND DENSITY).
- 13. IF REQUIRED TO MODIFY EXISTING GRADE, FILL MATERIALS SHOULD BE PLACED ON PREPARED SURFACES IN LIFTS NOT EXCEED 8 INCHES (LOOSE MEASURE), WITH COMPACTED THICKNESS NOT TO EXCEED 6 INCHES OR AS INDICATED IN SITE GEOTECHNICAL REPORT. FILL SHALL BE COMPACTED TO OPTIMUM MOISTURE CONTENT OR UP TO +3 PERCENTAGE POINTS OF OPTIMUM MOISTURE CONTENT TO A MINIMUM OF 95% MAXIMUM DENSITY AS DETERMINED BY TXDOT, TEX-114-E OR AS DESCRIBED IN THE SITE GEOTECHNICAL REPORT.
- ALL FILL MATERIALS SHALL BE CLEAR OF DEBRIS, ORGANICS AND VEGETATION. IF IMPORTED FILL IS USED, IT 14. SHALL BE A RELATIVELY HOMOGENEOUS PARTICLE SIZE DISTRIBUTION, WITH MAX SIZE OF 3 INCHES, PLASTICITY INDEX BETWEEN 7 AND 20 AND A LIQUID LIMIT LESS THAN 40; OR AS INDICATED ON THE GEOTECHNICAL REPORT.
- 15 ANY EXCESS EXCAVATION MATERIALS NOT USED, SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFFSITE IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL LAWS.
- 16. CONTRACTOR IS RESPONSIBLE FOR FILING WITH THE TCEQ FOR THE TEMPORARY STORM WATER POLLUTION PREVENTION PLAN NOTICE TO PROCEED AND NOTICE OF TERMINATION AT THE START AND END OF CONSTRUCTION.
- 17. AFTER COMPLETION OF CONSTRUCTION, THE SITE SHALL BE THOROUGHLY CLEANED OF CONSTRUCTION DEBRIS, SEDIMENT, MATERIAL, ETC. PRIOR TO TURNING OVER TO OWNER.
- 18. CONTRACTOR SHALL INCLUDE IN THEIR BASE BID ANY TRAFFIC AND/OR PEDESTRIAN CONTROL DEVICES, PLANS OR LAYOUT NECESSARY FOR CONSTRUCTION; INCLUDING SEQUENCING OF CONSTRUCTION, DELIVERIES OF CONSTRUCTION MATERIAL AND EQUIPMENT, AND DEMOLITION ACTIVITIES, SO THAT THE ADJACENT ROADWAYS AND NEIGHBORING PROPERTIES HAVE SUITABLE VEHICULAR AND PEDESTRIAN ACCESS.
- 19. NOTES, CALLOUTS OR ITEMS NOTED AS "BY-OTHERS" SHALL BE CONSIDERED OUTSIDE THE SCOPE OF SERVICES PERFORMED BY HILL COUNTRY CIVIL. THESE ITEMS ARE CALLED OUT FOR REFERENCE ONLY, AND THE CONTRACTOR SHALL CONFIRM WITH OWNER, OTHER CONSULTANT OR MANUFACTURE FOR PLANS, OR DESIGNS DETAILING THOSE SPECIFIC ITEMS.
- 20. CONTRACTOR IS RESPONSIBLE FOR ALL VERTICAL AND HORIZONTAL CONTROL THROUGHOUT CONSTRUCTION.

AUSTIN ENERGY CONSTRUCTION NOTES:

- AUSTIN ENERGY HAS THE RIGHT TO PRUNE AND/OR REMOVE TREES, SHRUBBERY AND OTHER OBSTRUCTIONS TO THE EXTENT NECESSARY TO KEEP THE EASEMENTS CLEAR. AUSTIN ENERGY WILL PERFORM ALL TREE WORK IN COMPLIANCE WITH CHAPTER25-8, SUBCHAPTER B OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER/DEVELOPER OF THIS SUBDIVISION/LOT SHALL PROVIDE AUSTIN ENERGY WITH ANY EASEMENT AND/ORACCESS REQUIRED, IN ADDITION TO THOSE INDICATED, FOR THE INSTALLATION AND ONGOING MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8 OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER SHALL BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY EROSION CONTROL, REVEGETATION AND TREE PROTECTION. IN ADDITION, THE OWNER SHALL BE RESPONSIBLE FOR ANY INITIAL TREE PRUNING AND TREE REMOVAL THAT IS WITHIN TEN FEET OF THE CENTER LINE OF THE PROPOSED OVERHEAD ELECTRICAL FACILITIES DESIGNED TO PROVIDE ELECTRIC SERVICE TO THIS PROJECT. THE OWNER SHALL INCLUDE AUSTIN ENERGY'S WORK WITHIN THE LIMITS OF CONSTRUCTION FOR THIS PROJECT.
- THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRIC SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS, CITY OF AUSTIN RULES AND REGULATIONS AND TEXAS STATE LAWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES AND EQUIPMENT. AUSTIN ENERGY WILL NOT RENDER ELECTRIC SERVICE UNLESS REQUIRED CLEARANCES ARE MAINTAINED. ALL COSTS INCURRED BECAUSE OF FAILURE TO COMPLY WITH THE REQUIRED CLEARANCES WILL BE CHARGED TO THE OWNER

TRAVIS COUNTY STANDARD CONSTRUCTION NOTES:

- TRAVIS COUNTY.
- PERMITS AT THE JOB SITE.
- 3. TRAFFIC CONTROL PLAN FROM TRAVIS COUNTY.
- THE CONSTRUCTION PROCESS.

5.

- 512-854-9383.
- SEQUENCING NOTES IN THESE APPROVED PLANS.
- DECOMPOSABLE WASTES, ETC.) IS PROHIBITED IN PERMANENT FILL SITES.
- 10. FILL
- DESIGN ENGINEER.
- 12. SHALL TAKE PRECEDENCE.
- 13. POSSIBLE.
- TRAVIS COUNTY.

14

17.

18.

19.

- 15. EXCAVATION ACTIVITIES.
- 16.
- COUNTY RIGHT-OF-WAY.
- IN THE SWP3 AND ESC PLAN SHEET NOTES.
- 20. NOTES.
- 22. SUBMITTED BEFORE THE CONTRACTOR OR PRIMARY OPERATOR REQUESTS A FINAL INSPECTION BY TRAVIS COUNTY.
- 23. REVISIONS ARE APPROVED.
- 24. ARE COMPLETE

EACH DRIVEWAY MUST BE CONSTRUCTED IN ACCORDANCE WITH TRAVIS COUNTY CODE SECTION 482.302(G), AND EACH DRAINAGE STRUCTURE OR SYSTEM MUST BE CONSTRUCTED IN ACCORDANCE WITH THE CITY OF AUSTIN DRAINAGE CRITERIA MANUAL. UNLESS OTHER DESIGN CRITERIA ARE APPROVED BY

BEFORE BEGINNING ANY CONSTRUCTION, THE OWNER MUST OBTAIN A TRAVIS COUNTY DEVELOPMENT PERMIT AND POST THE DEVELOPMENT PERMIT, THE TCEQ SITE NOTICE, AND ANY OTHER REQUIRED

CONSTRUCTION MAY NOT TAKE PLACE WITHIN TRAVIS COUNTY RIGHT-OF-WAY UNTIL AFTER THE OWNER HAS SUBMITTED A TRAFFIC CONTROL PLAN TO TRAVIS COUNTY AND OBTAINED WRITTEN APPROVAL OF THE

THE CONTRACTOR AND PRIMARY OPERATOR SHALL FOLLOW THE SEQUENCE OF CONSTRUCTION AND THE SWP3 IN THESE APPROVED PLANS. THE CONTRACTOR AND PRIMARY OPERATOR SHALL REQUEST TRAVIS COUNTY INSPECTION AT SPECIFIC MILESTONES IN THE SEQUENCE OF THE CONSTRUCTION OF THE SITE DEVELOPMENT CORRESPONDING TO THE PRIORITY INSPECTIONS SPECIFIED IN CONSTRUCTION SEQUENCING NOTES IN THESE APPROVED PLANS. DEVELOPMENT OUTSIDE THE LIMITS OF CONSTRUCTION SPECIFIED IN THE APPROVED PERMIT AND CONSTRUCTION PLANS IS PROHIBITED.

BEFORE BEGINNING ANY CONSTRUCTION, ALL STORM WATER POLLUTION PREVENTION PLAN (SWP3) REQUIREMENTS SHALL BE MET, AND THE FIRST PHASE OF THE TEMPORARY EROSION CONTROL (ESC) PLAN INSTALLED WITH A SWP3 INSPECTION REPORT UPLOADED TO MYPERMITNOW.ORG. ALL SWP3 AND ESC PLAN MEASURES AND PRIMARY OPERATOR SWP3 INSPECTIONS MUST BE PERFORMED BY THE PRIMARY OPERATOR IN ACCORDANCE WITH THE APPROVED PLANS AND SWP3 AND ESC PLAN NOTES THROUGHOUT

BEFORE STARTING CONSTRUCTION. THE OWNER OR CONTRACTOR OR THEIR DESIGNATED REPRESENTATIVES SHALL SUBMIT A REQUEST VIA THE MYPERMITNOW.ORG CUSTOMER PORTAL FOR TRAVIS COUNTY TO REQUEST AND SCHEDULE A MANDATORY PRECONSTRUCTION CONFERENCE AND ESC INSPECTION. IF FURTHER ASSISTANCE IS NEEDED, THE TNR PLANNING AND ENGINEERING DIVISION STAFF OR TNR STORM WATER MANAGEMENT PROGRAM STAFF CAN BE CONTACTED BY TELEPHONE AT

THE CONTRACTOR SHALL KEEP TRAVIS COUNTY TNR ASSIGNED INSPECTION STAFF CURRENT ON THE STATUS OF SITE DEVELOPMENT AND UTILITY CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY TRAVIS COUNTY AND REQUEST PRIORITY INSPECTIONS THROUGH THE MYPERMITNOW.ORG CUSTOMER PORTAL FOR TRAVIS COUNTY IN ACCORDANCE WITH THE SPECIFIC MILESTONES IN THE CONSTRUCTION

CONTOUR DATA SOURCE: FIELD SURVEY, TEXAS STATE PLANES, SOUTH CENTRAL ZONE, NAD 83

FILL MATERIAL MUST BE MANAGED AND DISPOSED OF IN ACCORDANCE WITH ALL REQUIREMENTS SPECIFIED IN THE APPROVED PLANS, SWP3, AND THE TRAVIS COUNTY CODE. THE CONTRACTOR SHALL STOCKPILE FILL AND CONSTRUCTION MATERIALS ONLY IN THE AREAS DESIGNATED ON THE APPROVED PLANS AND NOT WITHIN THE 0.2 PERCENT ANNUAL CHANCE FLOODPLAIN OR THE 1 PERCENT ANNUAL CHANCE FLOODPLAIN, WATERWAY SETBACK, CRITICAL ENVIRONMENTAL FEATURE SETBACK, OR OUTSIDE THE LIMITS OF CONSTRUCTION. DISPOSAL OF SOLID WASTE MATERIALS, AS DEFINED BY STATE LAW (E.G., LITTER, TIRES,

BEFORE DISPOSING ANY EXCESS FILL MATERIAL OFF-SITE, THE CONTRACTOR OR PRIMARY OPERATOR MUST PROVIDE THE COUNTY INSPECTOR DOCUMENTATION THAT DEMONSTRATES THAT ALL REQUIRED PERMITS FOR THE PROPOSED DISPOSAL SITE LOCATION, INCLUDING TRAVIS COUNTY, TCEQ NOTICE, AND OTHER APPLICABLE DEVELOPMENT PERMITS, HAVE BEEN OBTAINED. THE OWNER OR PRIMARY OPERATOR MUST REVISE THE SWP3 AND ESC PLAN IF HANDLING OR PLACEMENT OF EXCESS FILL ON THE CONSTRUCTION SITE IS REVISED FROM THE EXISTING SWP3. IF THE FILL DISPOSAL LOCATION IS OUTSIDE TRAVIS COUNTY OR DOES NOT REQUIRE A DEVELOPMENT PERMIT, THE CONTRACTOR OR PRIMARY OPERATOR MUST PROVIDE THE COUNTY INSPECTOR THE SITE ADDRESS, CONTACT INFORMATION FOR THE PROPERTY OWNER OF THE

THE DESIGN ENGINEER IS RESPONSIBLE FOR THE ADEQUACY OF THE CONSTRUCTION PLANS. IN REVIEWING THE CONSTRUCTION PLANS, TRAVIS COUNTY WILL RELY UPON THE ADEQUACY OF THE WORK OF THE

IN THE EVENT OF ANY CONFLICTS BETWEEN THE CONTENT IN THE SWP3 SITE NOTEBOOK AND THE CONTENT IN THE CONSTRUCTION PLANS APPROVED BY TRAVIS COUNTY, THE CONSTRUCTION PLANS

A MINIMUM OF TWO SURVEY BENCHMARKS SHALL BE SET, INCLUDING DESCRIPTION, LOCATION, AND ELEVATION; THE BENCHMARKS SHOULD BE TIED TO A TRAVIS COUNTY CONTROL BENCHMARK WHEN

ANY EXISTING PAVEMENT, CURBS, SIDEWALKS, OR DRAINAGE STRUCTURES WITHIN COUNTY RIGHT-OF-WAY WHICH ARE DAMAGED, REMOVED, OR SILTED, WILL BE REPAIRED BY THE CONTRACTOR AT OWNER OR CONTRACTOR'S EXPENSE BEFORE APPROVAL AND ACCEPTANCE OF THE CONSTRUCTION BY

CALL THE TEXAS EXCAVATION SAFETY SYSTEM AT 8-1-1 AT LEAST 2 BUSINESS DAYS BEFORE BEGINNING

ALL STORM SEWER PIPES SHALL BE CLASS III RCP, UNLESS OTHERWISE NOTED.

CONTRACTOR IS REQUIRED TO OBTAIN A UTILITY INSTALLATION PERMIT IN ACCORDANCE WITH TRAVIS COUNTY CODE SECTION 482.901(A) (3) BEFORE ANY CONSTRUCTION OF UTILITIES WITHIN ANY TRAVIS

THIS PROJECT IS LOCATED ON FLOOD INSURANCE RATE MAP 48453C0560H.

TEMPORARY STABILIZATION MUST BE PERFORMED IN ALL DISTURBED AREAS THAT HAVE CEASED CONSTRUCTION ACTIVITIES FOR 14 DAYS OR LONGER, IN ACCORDANCE WITH THE STANDARDS DESCRIBED

PERMANENT SITE STABILIZATION/RE-VEGETATION MUST BE PERFORMED IMMEDIATELY IN ALL SITE AREAS WHICH ARE AT FINAL PLAN GRADE AND IN ALL SITE AREAS SPECIFIED IN THE APPROVED PLANS FOR PHASED RE-VEGETATION, IN ACCORDANCE WITH THE STANDARDS DESCRIBED IN THE SWP3 AND ESC PLAN SHEET

ALL TREES WITHIN THE RIGHT-OF-WAY AND DRAINAGE EASEMENTS SHALL BE SAVED OR REMOVED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION PLANS. TRAVIS COUNTY TREE PRESERVATION STANDARDS IN TRAVIS COUNTY CODE SECTION 482.973, INCLUDING INSTALLATION AND MAINTENANCE OF ALL SPECIFIED TREE PROTECTION MEASURES, MUST BE FOLLOWED DURING CONSTRUCTION.

AN ENGINEER'S CONCURRENCE LETTER IN ACCORDANCE WITH TRAVIS COUNTY CODE SECTION 482.953 MUST BE SUBMITTED VIA THE MYPERMITNOW.ORG CUSTOMER PORTAL FOR TRAVIS COUNTY WHEN CONSTRUCTION IS SUBSTANTIALLY COMPLETE. THE ENGINEER'S CONCURRENCE LETTER MUST BE

SITE IMPROVEMENTS MUST BE CONSTRUCTED IN CONFORMANCE WITH THE ENGINEER'S CONSTRUCTION PLANS APPROVED BY TRAVIS COUNTY. NON-CONFORMANCE WITH THE APPROVED PLANS WILL DELAY FINAL INSPECTION APPROVAL BY THE COUNTY UNTIL PLAN CONFORMANCE IS ACHIEVED OR ANY REQUIRED PLAN

FINAL SITE STABILIZATION. ALL AREAS DISTURBED BY THE CONSTRUCTION MUST BE PERMANENTLY REVEGETATED AND ALL TEMPORARY SEDIMENT CONTROLS AND ACCUMULATED SEDIMENTATION MUST BE REMOVED BEFORE THE COUNTY WILL ISSUE A CERTIFICATE OF COMPLIANCE FOR FINAL SITE STABILIZATION AS PART OF FINAL INSPECTION AND PROJECT COMPLETION. A DEVELOPERS CONTRACT, AS DESCRIBED IN THE SWP3 AND ESC NOTES SHEET MAY BE EXECUTED WITH TRAVIS COUNTY FOR CONDITIONAL ACCEPTANCE OF A PROJECT FOR WHICH HAS ESC FISCAL SECURITY POSTED AND FOR WHICH ALL ITEMS

482.951 SWP3 AND ESC INSPECTIONS

GENERAL. THE REQUIREMENTS OF THIS SECTION ARE IN ADDITION TO THE APPLICABLE TECHNICAL CRITERIA IN SECTION 482.933 2. 1. AND THE REQUIREMENTS IN 482.601. THE REQUIREMENTS OF THIS SECTION APPLY TO A CONSTRUCTION SITE THAT REQUIRES A SWP3. FOR A NON-RESIDENTIAL PROJECT LESS THAN ONE ACRE SUBJECT TO AN ESC PLAN, THE INSPECTION SHOULD BE CONDUCTED BY AN INSPECTOR QUALIFIED IN CONSTRUCTION STORM WATER MANAGEMENT REQUIREMENTS AND IS SUBJECT TO THE REQUIREMENTS OF THIS SECTION, EXCEPT THAT WHENEVER A REFERENCE IS MADE TO A SWP3, SWP3 INSPECTION, AND SWP3 REPORT, IT SHALL BE CONSTRUED AS AN ESC PLAN, ESC PLAN INSPECTION, OR ESC PLAN REPORT, RESPECTIVELY. OWNER AND OPERATOR SWP3 INSPECTION RESPONSIBILITIES. AN OWNER OR OPERATOR SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS IN THE IMPLEMENTATION AND INSPECTION OF CONSTRUCTION PROJECTS AND ASSOCIATED RECORDKEEPING SUBJECT TO A SWP3 AND TRAVIS COUNTY DEVELOPMENT PERMIT: 2.1. THE OWNER OR OPERATOR SHALL POST AT THE CONSTRUCTION SITE A COPY OF THE TCEQ CONSTRUCTION SITE NOTICE ("CSN"). NO LATER THAN TWO DAYS BEFORE THE START OF CONSTRUCTION, THE OWNER OR OPERATOR MUST PROVIDE THE COUNTY EXECUTIVE A COPY OF THE TCEQ CSN. NO LATER THAN SEVEN DAYS BEFORE THE START OF CONSTRUCTION, 6 THE OWNER OR OPERATOR MUST PROVIDE TO THE COUNTY EXECUTIVE A COPY OF THE TCEQ NOTICE OF INTENT, IF ANY. 2.2. THE OWNER OR OPERATOR SHALL DESIGNATE AN ON-SITE PROJECT MANAGER AND PERSONNEL WITH THE NECESSARY EXPERIENCE, QUALIFICATIONS, AND TRAINING WHO WILL BE RESPONSIBLE FOR PERFORMING AND MONITORING THE SWP3, ESC PLAN BMPS, AND CONSTRUCTION ACTIVITIES TO ENSURE SPECIFIED PRACTICES AND STRUCTURAL CONTROLS ARE CONTINUOUSLY IMPLEMENTED AND MAINTAINED IN EFFECTIVE OPERATING CONDITION THROUGHOUT CONSTRUCTION. THE OWNER OR PRIMARY OPERATOR MUST PERFORM ANY ONGOING INSPECTIONS, MONITORING, AND ACTIONS NECESSARY TO MAINTAIN COMPLIANCE, INCLUDING PREPARING A SIGNED SWP3 INSPECTION REPORT ON THE SCHEDULE DESCRIBED IN PARAGRAPH (4) OF THIS SUBSECTION. ANY NECESSARY CORRECTIVE ACTION IDENTIFIED SHALL BE RECORDED ON THE SWP3 INSPECTION REPORT. THE OWNER OR PRIMARY OPERATOR SHALL ENSURE ANY CORRECTIVE ACTION IS PROMPTLY PERFORMED IN ACCORDANCE WITH THE SWP3 AND REQUIREMENTS OF THIS CHAPTER. 2.3. THE OWNER OR PRIMARY OPERATOR SHALL DESIGNATE A QUALIFIED INSPECTOR FAMILIAR WITH THE SWP3 AND POSSESSING THE REQUIRED CERTIFICATION AS SPECIFIED IN SECTION 482.934(C) TO CONDUCT WEEKLY SWP3 INSPECTIONS OF THE SITE AND PREPARE A SIGNED SWP3 INSPECTION REPORT EACH WEEK. THE DESIGNATED PROJECT MANAGER AND THE QUALIFIED SWP3 INSPECTOR ARE TO COORDINATE WITH THE INSPECTOR ON A REGULAR BASIS DURING CONSTRUCTION TO HELP ENSURE THE SWP3 CONTROLS AND MEASURES ARE PROPERLY IMPLEMENTED. 2.4. SWP3 INSPECTION SCHEDULE. SWP3 INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS ON A SPECIFICALLY DEFINED DAY UNTIL THE ENTIRE SITE IS TEMPORARILY OR FINALLY STABILIZED, AND MUST BEGIN: 2.4.1. FROM THE TIME OF THE INITIAL INSTALLATION OF THE FIRST PHASE OF ESC CONTROLS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE WITH RESPECT TO PROJECTS FOR WHICH A PRE-CONSTRUCTION CONFERENCE IS REQUIRED: AND 2.4.2. FROM THE START OF CONSTRUCTION SITE SOIL DISTURBING ACTIVITY WITH RESPECT TO PROJECTS FOR WHICH A PRE-CONSTRUCTION CONFERENCE IS NOT REQUIRED. POST-RAINFALL INSPECTIONS. THE OWNER, PRIMARY OPERATOR, OR OTHER DESIGNEE SHALL CONDUCT A 2.5. POST-RAINFALL INSPECTION WITHIN 48 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER. 2.5.1. THE INSPECTION MUST INCLUDE ALL AREAS OF THE CONSTRUCTION SITE IDENTIFIED IN THE SWP3, EXCEPT AS PROVIDED BY PARAGRAPH (8); 2.5.2. THE OWNER, OPERATOR, OR DESIGNEE MUST COMMENCE CORRECTIVE ACTION, AS FEASIBLE AND AS SITE CONDITIONS ALLOW; AND 2.5.3. THE OWNER, OPERATOR, OR DESIGNEE MUST PROVIDE THE FINDINGS OF THE POST-RAINFALL INSPECTION TO THEIR SWP3 INSPECTOR NO LATER THAN THE NEXT SCHEDULED SWP3 INSPECTION. 2.6. WHEN THE ENTIRE SITE HAS BEEN FINALLY OR TEMPORARILY STABILIZED, SWP3 INSPECTIONS MUST BE CONDUCTED AT LEAST ONCE EVERY MONTH UNTIL FULL SITE COMPLETION AND FINAL INSPECTION RELEASE THROUGH ISSUANCE OF A CERTIFICATE OF COMPLIANCE. THIS ALSO APPLIES TO DISCRETE AREAS OR PHASES OF A LARGER ACTIVE SITE WHICH ARE FINALLY OR TEMPORARILY STABILIZED. UNFINISHED SITES FINALLY OR TEMPORARILY STABILIZED BUT INACTIVE FOR THREE MONTHS OR LONGER MUST BE INSPECTED ONCE EVERY TWO MONTHS AS A MINIMUM. 2.7. LONG, NARROW, LINEAR CONSTRUCTION ACTIVITIES WHERE ACCESS IS LIMITED MAY BE INSPECTED ON AN ALTERNATIVE SCHEDULE, WITH REPRESENTATIVE INSPECTIONS IN ACCORDANCE WITH THE TCEQ GENERAL PERMIT, IF THE OWNER OR PRIMARY OPERATOR SUBMITS SUPPORTING DOCUMENTATION TO THE COUNTY AND THE COUNTY APPROVES THE ALTERNATIVE SCHEDULE. 2.8. IN THE EVENT OF FLOODING OR OTHER UNCONTROLLABLE SITUATIONS WHICH PROHIBIT ACCESS TO THE INSPECTION SITES, THE INSPECTION MUST BE CONDUCTED AS SOON AS ACCESS IS PRACTICAL. THE SWP3 INSPECTION MUST INCLUDE INSPECTION OF THE SITE FOR COMPLIANCE WITH ALL APPLICABLE SWP3 2.9. REQUIREMENTS. SWP3 INSPECTIONS MUST COVER ALL AREAS OF THE CONSTRUCTION SITE TO DETERMINE WHETHER SWP3 AND ESC PLAN BMPS ARE FULLY IMPLEMENTED AND OPERATING AS REQUIRED. AND TO DETERMINE IF THERE IS EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND DISCHARGING OFF-SITE. THE FORMAT FOR SWP3 INSPECTIONS AND THE CONTENTS OF THE SWP3 INSPECTION REPORT MUST CONFORM TO THE ITEMS LISTED IN EXHIBIT 482.951 – SWP3 INSPECTION AREAS AND REPORT CONTENTS. 2.10. THE SWP3 MUST BE REVISED AS NECESSARY BASED ON ANY INSPECTION RESULT BY THE PRIMARY OPERATOR OR INSPECTOR FOR TRAVIS COUNTY, IN A MANNER THAT WILL ELIMINATE OR MINIMIZE, TO THE MAXIMUM EXTENT PRACTICABLE, THE DISCHARGE OR POTENTIAL DISCHARGE OF POLLUTANTS IN RUNOFF. THE OWNER OR PRIMARY OPERATOR MUST REVISE THE SWP3 AS NECESSARY IN ACCORDANCE WITH SECTION 482.935(I). 2.11. FINAL INSPECTION AND CERTIFICATE OF COMPLIANCE. THE OWNER OR OPERATOR SHALL SCHEDULE A FINAL INSPECTION WITH THE INSPECTOR WHEN ALL CONSTRUCTION PLAN REQUIREMENTS ARE COMPLETED. THE FINAL INSPECTION MUST BE PRECEDED BY SUBMITTAL OF THE PROFESSIONAL ENGINEER'S CONCURRENCE LETTER, AS REQUIRED BY SECTION 482.953. 2.11.1. COMPLETION OF THE SWP3 ELEMENTS OF THE CONSTRUCTION PLANS INCLUDES: 2.11.1.1. FINAL SITE STABILIZATION; 2.11.1.2. REMOVAL AND PROPER DISPOSAL OF ALL TEMPORARY SEDIMENT CONTROLS AND ACCUMULATED SEDIMENT CAPTURED OR DEPOSITED BY ALL ESCS; 2.11.1.3. PROPER CONSTRUCTION AND FUNCTIONALITY OF EACH PERMANENT WATER QUALITY CONTROL AND DRAINAGE STRUCTURE; 2.11.1.4. REMOVAL OF SEDIMENT, DEBRIS, OR OTHER MATERIALS FROM THE CONSTRUCTION AND LAND DISTURBANCE WHICH IS DEPOSITED IN EACH PERMANENT WATER QUALITY CONTROL AND DRAINAGE STRUCTURE; AND 2.11.1.5. STABILIZATION OF ALL SUBDIVISION DISTURBED LOTS, IF A SUBDIVISION DEVELOPMENT. A SUBDIVISION LOT WHICH HAS OBTAINED ALTERNATE OPERATIONAL CONTROL AND SWP3 COVERAGE MAY BE EXCLUDED FROM THIS REQUIREMENT. 2.11.2. IF THE FINDINGS OF THE INSPECTION DEMONSTRATE TO TRAVIS COUNTY THAT THE SWP3 AND CONSTRUCTION PLAN REQUIREMENTS HAVE BEEN FULLY COMPLETED, A CERTIFICATE OF COMPLIANCE WILL BE ISSUED FOR THE PROJECT AND ANY FISCAL SECURITY FOR EROSION AND SEDIMENTATION CONTROLS, PERMANENT STORM WATER MANAGEMENT FACILITIES, AND ON-SITE AND OFF-SITE CLEANUP SHALL BE RELEASED. THE PRIMARY OPERATOR MUST NOT SUBMIT A NOTICE OF TERMINATION UNTIL THE REQUIREMENTS OF SECTION 482.931(G)(4) HAVE BEEN ACHIEVED. 2.11.3. IF RE-VEGETATION COVERAGE IS NOT FULLY COMPLETED, A DEVELOPERS CONTRACT AS DESCRIBED IN SECTION 482.936 (D) (4) MAY BE ISSUED AT THE DISCRETION OF TRAVIS COUNTY FOR ELIGIBLE PROJECTS WITH FISCAL SECURITY POSTED FOR EROSION AND SEDIMENTATION CONTROLS, AS A CONDITIONAL ACCEPTANCE UNTIL THE 8. REQUIRED VEGETATIVE COVERAGE IS ATTAINED, EXCESS SEDIMENTATION IS REMOVED, AND REMAINING TEMPORARY SEDIMENT CONTROLS ARE REMOVED. 2.11.4. A CERTIFICATE OF COMPLIANCE IS NOT REQUIRED FOR CONSTRUCTION ON A SINGLE FAMILY RESIDENTIAL LOT, UNLESS SO SPECIFIED IN THE TRAVIS COUNTY DEVELOPMENT PERMIT, BASED UPON THE POTENTIAL IMPACT ON WATER QUALITY OF THE ACTIVITIES APPROVED FOR CONSTRUCTION, OR WHEN A PERMANENT WQC IS REQUIRED 12. FOR THE RESIDENTIAL LOT DEVELOPMENT. REGARDLESS, RESIDENTIAL LOT CONSTRUCTION MUST COMPLY WITH ALL APPLICABLE SWP3 AND ESC PLAN MEASURES AND REQUIREMENTS OF THIS CHAPTER PRIOR TO SUBMISSION OF THE NOTICE OF TERMINATION, INCLUDING CONSTRUCTION SEQUENCE, FINAL COMPLETION SCHEDULE, AND FINAL SITE STABILIZATION. 2.12. SWP3 REPORTS. EITHER AT THE TIME OF EACH SWP3 INSPECTION REQUIRED BY THIS SECTION, OR NO LATER THAN THE DATE OF THE INSPECTION, THE OWNER'S DESIGNATED, QUALIFIED INSPECTOR (AS SPECIFIED IN SECTION 482.934(C)(3)) SHALL PREPARE AND SIGN A SWP3 INSPECTION REPORT, CONTAINING NOTATIONS OF THE INSPECTION FINDINGS FOR THE REQUIRED SITE AREAS AND CONTROL MEASURES, AS DESCRIBED IN SUBSECTION (C), CERTIFYING WHETHER THE SITE IS IN COMPLIANCE WITH THE APPROVED SWP3 AND ESC PLAN, AND DESCRIBING ANY CORRECTIVE ACTIONS NECESSARY.

2.13.

SHALL BE MAINTAINED BY THE PRIMARY OPERATOR OR THE QUALIFIED INSPECTOR (AS SPECIFIED IN SECTION 482.934(C)(3)) AT THE CONSTRUCTION SITE, AND IT SHALL BE READILY AVAILABLE UPON REQUEST. ALL SWP3 RECORDS MUST BE KEPT BY THE OWNER OR PRIMARY OPERATOR FOR A MINIMUM OF THREE YEARS AFTER SITE COMPLETION.





4CC/OneDrive - Hill Country Civil/Projects/041 AAA Storage/01 FM 1826 Storage Phase 3/1 - CAD/2 - Sheets/041-01 EXIST









- 1. The aggregate should consist of four (4) inch to eight (8) inch washed stone over a stable undation as specified in the plan.
- The aggregate should be placed with a minimum thickness of eight (8) inches. The geotextile fabric should be designed specifically for use as a soil filtration media with an
- approximate weight of 6 oz./sq.yd., a Mullen burst rating of 140 #/sq.in., and an equivalent opening size greater that a U.S. Sieve No. 50.
- 4. If a washing facility is required, a level area with a minimum of four (4) inch diameter washed stone or commercial rack should be included in the plans. Wastewater should be diverted to a sediment trap or basin.

INSTALLATION:

- 1. Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation area. Grade a crown in the center of the foundation for
- positive drainage. 2. The minimum width of the facility should be either twelve (12) feet or the full width of Exit roadway, whichever is greater.
- 3. The Construction Entrance should be at least fifty (50) feet long. 4. If the slope toward the road exceeds two (2) percent, construct a ridge six (6) inches to eight (8) inches high with three to one (3H:1V) side slopes across the foundation
- approximately fifteen (15) feet from the Entrance to divert runoff away from the public road. 5. Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated.
- 6. Place stone to dimensions and grade shown on plans. Leave the surface smooth and sloped r drainage. Divert all surface runoff and drainage from the stone pad to a sediment trap or basin.
- 8. Install a pipe under pad as needed to maintain proper public road drainage.
- INSPECTION AND MAINTENANCE GUIDELINES:
- 1. The Entrance should be maintained in a condition which will prevent the tracking and flowing of sediment into public right-of-way. This may require a periodic top dressing of additiona stone as conditions demand and repairing and/or cleaning out any measures used to trap
- 2. All sediment spilled, dropped, washed or tracked onto the public right-of-way should be removed immediately by the Contractor.
- 3. When necessary vehicular wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
- 4. When washing is required it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin. 5. All sediment should be prevented from entering any storm drain, ditch, or water course by using approved methods.

TEMPORARY CONSTRUCTION ENTRANCE/EXIT

GENERAL S.W.P.P.P. NOTES:

- 1. The location of Erosion and Sedimentation Control facilities are approximate. Contractor may modify, relocate, or add facilities with prior authorization from the Engineer.
- 2. Where a note or detail differs from the official Texas Commission On Environmental Quality (TCEQ) latest edition regulations, the TCEQ note or detail shall apply.



- Pollution Prevention Plan (SWPPP) and all other related documents so that they are available on-site for the Inspector.
- 2. The canister shall be located on solid level ground adjacent to the construction entrance and on the opposite side of the Concrete

Washout Area.

S.W.P.P.P. DOCUMENT CONTAINER



NOTES:

- 1. Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough or liquid and solid waste.
- 2. Wash out wastes into the temporary pit where the concrete can set be broken up, and then disposed properly. 3. Below grade concrete washout facilities are typical. These consist of a lined excavation sufficiently large to hold expected volume of washout material. Above grade facilities are used if excavation is not
- practical. Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this section, with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material. 4. When temporary concrete washout facilities are no longer required for
- the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired

CONCRETE WASHOUT AREA





MATERIALS:

- 1. Silt fence material should be polypropylene, polyethylene or polyamide woven or non-woven fabric. The fabric width should be thirty—six (36) inches with a minimum unit weight of 4.5 oz./sq.yd., a mullen burst strength exceeding 190 #/sq.in., ultraviolet stability exceeding 70%, and
- minimum apparent opening size of U.S. Sieve No. 30. 2. Fence posts should be made of hot rolled steel, at least four (4) feet long with Tee or Y-bar cross section, surface painted or galvanized, minimum nominal weight 1.25 #/ft, and Brindell hardness exceeding 140.
- 3. Woven wire backing to support the fabric should be galvanized twelve (12) gauge minimum two by four (2x4) inch welded wire.

INSTALLATION:

- 1. Steel posts which support the silt fence should be installed on a slight angle toward the anticipated runoff source. Posts must be embedded a minimum of one (1) foot deep and spaced not more than eight (8) feet on center. Where water concentrates the maximum spacing should be six (6)
- 2. Lay out fencing down-slope of disturbed area following the contour as closely as possible. The fence should be sited so that the maximum drainage area is one-quarter (1/4)
- acre per one-hundred (100) feet of fence. 3. The toe of the silt fence should be trenched in with a spade or mechanical trencher so that the down-slope face of the trench is flat and perpendicular to the line of flow. Where fence cannot be trenched in (e.g. pavement or rock outcrop) weight fabric flap with three (3) inches of pea gravel on uphill side to prevent flow from seeping under the

SILT FENCE

Polyamide woven or non-woven fabric

– Polypropylene, Polyethylene,

- Steel "T" or "Y" shape

Fence Post (1.25#/Ft)

at 5' on center

- Ground at grade

[▲]*12" min. (driven)

- Bottom of fence

(6" below grade)

6" min. (drilled & driven)

-Non-woven Geotextile Fabric

- 4. The trench must be a minimum of six (6) inches deep and six (6) inches wide to allow for the silt fence fabric to be laid in the around and backfilled with compacted material.
- Silt fence should be securely fastened to each steel support post or to woven wire which is in turn attached to the
- steel fence post. There should be a securely fastened three (3) foot overlap where ends of the fabric meet.
- Silt fence should be removed when the site is completely stabilized so as not to block or impede storm flow or drainaae.

INSPECTION AND MAINTENANCE GUIDELINES:

- Inspect all fencing weekly and after any rainfall event. Remove sediment when buildup reaches 6 inches. Replace any torn fabric or install a second line of fencing parallel to the torn section.
- During the course of construction activities, Contractor shall replace or repair any crushed, collapsed sections. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access
- When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be re-vegetated. The fence itself should be disposed of in an approved landfill.

Clean, open graded rock. See notes below.

MATERIALS:

- 1. The berm structure should be secured with a woven wire sheathing having a maximum opening of one (1) inch and a minimum wire diameter of 20 gauge galvanized and should be secured with shoat rings.
- 2. Clean, open graded three (3) inch to five (5) inch diameter rock should be used, except in areas where high velocities or large volumes of flow are expected five (5) inch to eight (8) inch diameter rocks may be used.

INSTALLATION:

- 1. Lay out the woven wire sheathing perpendicular to the flow line. The sheathing should be
- twenty (20) gauge woven wire mesh with one (1) inch openings. 2. Berm should have a top width of two (2) feet minimum with side slopes being two to one (2H:1V) ratio slope or flatter.
- 3. Place the rock along the sheathing as shown above to a height not less than eighteen (18)
- 4. Wrap the wire sheathing around the rock and secure with tie wire so that the ends of the sheathing overlap at least two (2) inches. The berm should retain its shape when walked
- Berm should be built along the contour at zero percent grade or as near as possible. . The ends of the berm should be tied into existing up-slope grade and the berm should be buried in a trench approximately three (3) to four (4) inches deep to prevent failure of the

INSPECTION AND MAINTENANCE GUIDELINES:

accumulated silt is removed.

- 1. Inspection should be made weekly and after each rainfall by the responsible party. For installations in stream beds additional daily inspections should be made. 2. Remove sediment and other debris when buildup reaches six (6) inches and dispose of the
- accumulated silt in a approved manner that will not cause any additional siltation. Repair any loose wire sheathing.
- The berm should be reshaped as needed during inspection. 5. The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc. 6. The rock berm should be left in place until all upstream areas are stabilized and

ROCK BERM

Woven Wire Sheathina

Natura Ground

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY CONTRIBUTING ZONE PLAN **GENERAL CONSTRUCTION NOTES**

EDWARDS AQUIFER PROTECTION PROGRAM CONSTRUCTION NOTES - LEGAL DISCLAIMER

THE FOLLOWING/LISTED "CONSTRUCTION NOTES" ARE INTENDED TO BE ADVISORY IN NATURE ONLY AND DO NOT CONSTITUTE AN APPROVAL OR CONDITIONAL APPROVAL BY THE EXECUTIVE DIRECTOR (ED), NOR DO THEY CONSTITUTE A COMPREHENSIVE LISTING OF RULES OR CONDITIONS TO BE FOLLOWED DURING CONSTRUCTION, FURTHER ACTIONS MAY BE REQUIRED TO ACHIEVE COMPLIANCE WITH TCEO REGULATIONS FOUND IN TITLE 30. TEXAS ADMINISTRATIVE CODE (TAC). CHAPTERS 213 AND 217, AS WELL AS LOCAL ORDINANCES AND REGULATIONS PROVIDING FOR THE PROTECTION OF WATER QUALITY. ADDITIONALLY, NOTHING CONTAINED IN THE FOLLOWING/LISTED "CONSTRUCTION NOTES" RESTRICTS THE POWERS OF THE ED, THE COMMISSION OR ANY OTHER GOVERNMENTAL ENTITY TO PREVENT, CORRECT, OR CURTAIL ACTIVITIES THAT RESULT OR MAY RESULT IN POLLUTION OF THE EDWARDS AQUIFER OR HYDROLOGICALLY CONNECTED SURFACE WATERS. THE HOLDER OF ANY EDWARDS AQUIFER PROTECTION PLAN CONTAINING "CONSTRUCTION NOTES" IS STILL RESPONSIBLE FOR COMPLIANCE WITH TITLE 30, TAC, CHAPTERS 213 OR ANY OTHER APPLICABLE TCEQ REGULATION, AS WELL AS ALL CONDITIONS OF AN EDWARDS AQUIFER PROTECTION PLAN THROUGH ALL PHASES OF PLAN IMPLEMENTATION. FAILURE TO COMPLY WITH ANY CONDITION OF THE ED'S APPROVAL, WHETHER OR NOT IN CONTRADICTION OF ANY "CONSTRUCTION NOTES," IS A VIOLATION OF TCEQ REGULATIONS AND ANY VIOLATION IS SUBJECT TO ADMINISTRATIVE RULES, ORDERS, AND PENALTIES AS PROVIDED UNDER TITLE 30 TAC § 213 10 (RELATING TO ENFORCEMENT). SUCH VIOLATIONS MAY ALSO BE SUBJECT TO CIVIL PENALTIES AND INJUNCTION. THE FOLLOWING/LISTED "CONSTRUCTION NOTES" IN NO WAY REPRESENT AN APPROVED EXCEPTION BY THE ED TO ANY PART OF TITLE 30 TAC, CHAPTERS 213 AND 217, OR ANY OTHER TCEQ APP.

1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY GROUND DISTURBANCE OR CONSTRUCTION ACTIVITIES. THIS NOTICE MUST INCLUDE:

THE NAME OF THE APPROVED PROJECT; -- THE ACTIVITY START DATE; AND

- THE CONTACT INFORMATION OF THE PRIME CONTRACTOR. 2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT SHOULD BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED CONTRIBUTING ZONE PLAN (CZP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTOR(S)

SHOULD KEEP COPIES OF THE APPROVED PLAN AND APPROVAL LETTER ON-SITE. 3. NO HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE. 4. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND

SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.

5. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.

6. SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY. 7. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE. 8. ALL EXCAVATED MATERIAL THAT WILL BE STORED ON-SITE MUST HAVE PROPER E&S CONTROLS.

9. IF PORTIONS OF THE SITE WILL HAVE A CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL TCEQ-0592A (REV. JULY 15, 2015) PAGE 2 OF 2

STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE. 10. THE FOLLOWING RECORDS SHOULD BE MAINTAINED AND MADE AVAILABLE TO THE

TCEQ UPON REQUEST: THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR; THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A

PORTION OF THE SITE: AND

THE DATES WHEN STABILIZATION MEASURES ARE INITIATED. THE HOLDER OF ANY APPROVED CZP MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING: A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY BEST MANAGEMENT

PRACTICES (BMPS) OR STRUCTURE(S), INCLUDING BUT NOT LIMITED TO TEMPORARY OR PERMANENT PONDS, DAMS, BERMS, SILT FENCES, AND DIVERSIONARY STRUCTURES; B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM

THAT WHICH WAS ORIGINALLY APPROVED; C. ANY CHANGE THAT WOULD SIGNIFICANTLY IMPACT THE ABILITY TO PREVENT POLLUTION OF THE EDWARDS AQUIFER; OR D. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE APPROVED

CONTRIBUTING ZONE PLAN.

Austin Regional Office 12100 Park 35 Circle, Building A Austin, Texas 78753-1808 Phone (512) 339-2929 Fax (512) 339-3795

San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329







Civil ountry LOT 37–A APPALOOSA RUN LEGEND SECTION ONE-A (86/188B) PROPERTY BOUNDARY _____ _ _ _ LOT LINE Ŭ SETBACK LINE Ξ — — — — — LANDSCAPE BUFFER LINE 150 LF MAN PULL EASEMENT LINE _ _ _ _ _ _ _ SITE BENCHMARK PROPERTY CORNER — GAS — GAS — GAS LINE OVERHEAD ELECTRIC LINE FENCE LINE EXISTING TREE • SIGN $\Box O$ POWER POLE WATER LINE _____ w _____ REDUCER ISOLATION/GATE VALVE Ø T FIRE HYDRANT SERVICE SADDLE FIRE TRUCK HOSE PULL **ROSS T. CORDER** FIRE HOSE MAN PULL 125401 150 LF MAN PULL FIRE LANE CENSE FIRE PROTECTION PLAN NOTES 1. THIS PLAN COMPLIES WITH THE TRAVIS COUNTY FIRE PROTECTION ORDINANCES. HOSE PULL BY TRUCK SHALL NOT EXCEED 350 LF AND 150 LF MAN PULL WHEN EXIST 75,000 GAL FIRE WATER BUILDINGS ARE NOT PROTECTED BY A FIRE SPRINKLER SYSTEM, AND WHEN PROTECTED BY A FIRE PROTECTION SYSTEM 200 LF. STORAGE TANK 2. FIRE LANE STRIPING SHALL BE RED PAINT STRIPING WITH 4" TYPE D BLOCK WHITE REFERENCE APPROVED APALOOSA LETTERING SPACED EVERY 40'. WHITE LETTERING SHALL STATE: "FIRE LANE - NO STORAGE PHASE 1 PLANS FOR SIZING PARKING - TOW AWAY ZONE". AND CALCUALTIONS FIRE TANK NOTE ALL BUILDINGS MUST MAINTAIN A MAXIMUM VOLUME NO GREATER THAN 331,100 CUBIC FEET IN ORDER TO UTILIZE THE EXISTING WATER STORAGE TANK VOLUME OF 75,000 GALLONS. TRAVIS COUNTY WATER TANK SIZING I IS BASED OFF THE EQUATION BELOW PER NFPA 1142: WSmin = (VStot / OHC) x CC PROPOSED PHASE 3 AND PHASE 4 BUILDINGS MUST UTILIZE FIRE PPALOOSA RUN STORAGE FACILITY PH. 3 & 4 12100 RM 1826 AUSTIN, TEXAS 78737 SEPARATION WALLS, OR OTHER MEASURES TO KEEP EACH BUILDING VOLUME UNDER THE REQUIRED AMOUNT. **BUILDING NOTES:** I ALL PROPOSED BUILDINGS MUST BE FINISHED OUT SO THAT A FIRE SPRINKLER SYSTEM IS NOT REQUIRED, WITH FIRE WALLS CONSTRUCTED PER INTERNATIONAL FIRE CODE AND THE TRAVIS COUNTY \triangleleft FIRE MARSHAL. PROPOSED 4" DOMESTIC ✓ PROPERTY LINE RYSWYK ESTATES (84/62A) Ш Ω CAUTION! SHEET NO. CONTRACTOR SHALL EXERCISE CAUTION DURING

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT. CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

OF 35

-













7. ALL RAMPS, ACCESSIBLE PATHS, AND ACCESSIBLE PARKING SPOTS SHALL BE IN COMPLIANCE WITH THE LATEST TEXAS ACCESSIBILITY STANDRS (TAS). 8. WHEELSTOPS SHALL BE PRE-CAST CONCRETE AND AND 6' IN LENGTH, OR AS SPECIFICALLY CALLED OUT ON PLANS. FURTHERMORE, WHEELSTOPS SHALL BE DOWELED IN PLACE A MINIMUM OF 12" INTO PAVEMENT AND BASE SECTION.

CONSULTANT FOR LAYOUT OF PARKING LOT LIGHTS.

CONCRETE PAVEMENT, WITH #4 BARS, 18" O.C.E.W.

LANE - NO PARKING - TOW AWAY ZONE".

11. DUMPSTER'S SHALL BE SCREENED FROM PUBLIC RIGHT-OF-WAY AND

12. PROPOSED PAVEMENT SECTIONS SHALL BE PER THE SITE GEOTECH REPORT.

13. FIRE LANE STRIPING SHALL BE RED PAINT STRIPING WITH 4" TYPE D BLOCK

TO ACCESS DUMPSTER'S SHALL BE A MINIMUM OF 12' WIDE.

6. CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

10. ALL DUMPSTER PADS AND APRONS SHALL BE CONSTRUCTED OF 6" REINFORCED

ADJACENT PROPERTIES. SCREENING SHALL BE A MINIMUM OF 7' TALL. GATES

WHITE LETTERING SPACED EVERY 40'. WHITE LETTERING SHALL STATE: "FIRE

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION

CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD

ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING

TRENCH EXCAVATION SAFETY PROTECTION

EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE

INSTALLATION SITES WITHIN THE PROJECT AREA IN

EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE

SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH

ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

TRENCH SAFETY PROTECTION THAT COMPLY WITH AS

ORDER TO IMPLEMENT CONTRACTORS TRENCH

A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR

SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND

CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED

NEAR POWER LINES.

ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

- REQUIRED TO PROVIDE SERVICE TO THE PROJECT SITE.
- 5. PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL COORDINATE WITH LOCAL TV, ELECTRIC, GAS, WATER, SEWER AND PHONE PROVIDERS AS
- 4. ALL DIMENSIONS SHOWN ARE TO FACE OF CURB OR EDGE OF PAVEMENT UNLESS STATED OTHERWISE.
- 3. PROPERTY LIES IN UNSHADED ZONE "X" AS DELINEATED ON THE FLOOD INSURANCE RATE MAP FOR TRAVIS COUNTY, TEXAS AND INCORPORATED AREAS, MAP NO.48453C0560J.
- 2. CONTRACTOR SHALL KEEP A COPY OF APPROVED CONSTRUCTION DRAWINGS ONSITE AT ALL TIMES.
- 1. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL BUILDING, SAFETY, AND INSPECTION REGULATIONS.

SITE PLAN NOTES







OF 35

11





BENCHMARK TABLE				
	Х	Y	ELEVATION	DESCRIPTION
3M # 1	3055879.5	10040179.6	992.13 '	COTTON SPINDLE SET
3M # 2	3056283.4	10039908.8	987.47'	SQUARE IN THE SOUTH SIDE OF A CULVERT





C/OneDrive - Hill Country Civil/Projects/041 AAA Storage/01 FM 1826 Storage Phase 3/1 - CAD/2 - Sheets/041-01 GRI



OF 35

AROUND THE EXPOSED TRENCH EXCAVATION.



OneDrive - Hill Country Civil/Proiects/041 AAA Storage/01 FM 1826 Storage Phase 3/1 - CAD/2 - Sheets/041-01 GF



PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

SHEET NO.

16



Copyright Hill Country Civil, LLC October 4, 2024

	0 10	20 40 SCALE: 1"=20'	
	← GAS — GAS — GAS —	LEGEND PROPERTY BOUNDARY PROPERTY BOUNDARY LOT LINE EASEMENT LINE SITE BENCHMARK PROPERTY CORNER GAS LINE OVERHEAD ELECTRIC LINE FENCE LINE EXISTING TREE SIGN POWER POLE EXISTING FLOW ARROW EXISTING MINOR CONTOUR EXISTING MAJOR CONTOUR	
		PROPOSED MINOR CONTOUR PROPOSED MAJOR CONTOUR PROPOSED FLOW ARROW	
	600.00	PROPOSED SPOT ELEVATION	
	,	PROPOSED DRAINAGE SWALE/CONCENTRATED FLOW PATH IN PAVED AREAS	
GRADING NOTES			
1.	CONTRACTOR SHALL COM SAFETY, AND INSPECTION F	PLY WITH ALL APPLICABLE LOCAL BUILDING, REGULATIONS.	
2. CONTRACTOR SHALL PROTECT EXISTING FACILITIES TO REMAIN INCLUDING BUT NOT LIMITED TO STRUCTURES, PAVEMENT, TREES, FENCES LANDSCAPING, UTILITIES, ETC. ALL EXISTING FACILITIES SHALL BE IN ORIGINAL OR BETTER CONDITION AT THE COMPLETION OF THE PROJECT.			
3.	DURING CONSTRUCTION, C UNRESTRICTED DRAINAGE. BE PERMITTED IN AREAS OF EMBANKMENT. IF PONDING IMMEDIATELY PUMP OUT O	CONTRACTOR SHALL MAINTAIN . NO PONDING OF STORM DRAINAGE SHALL F PREPARED SUBGRADE OR EXCAVATION, SHOULD OCCUR, CONTRACTOR SHALL R GRAVITY DRAIN PONDING WATER OUT OF	

- IMPACTED AREAS. IF ANY DAMAGE OCCURRED TO SUBGRADE, BUILDING PAD OR EXCAVATION AREAS, THE SOILS MUST BE DRIED OUT, REMOVED, REPLACED AND RE-COMPACTED. 4. DISTURBED AREAS (CONSTRUCTION AREAS) SHALL BE STRIPPED OF VEGETATION, LOOSE TOPSOIL, ORGANICS, BRUSH AND DEBRIS. AFTERWARDS, THE EXPOSED SUBGRADE SHALL SHALL BE PROOF ROLLED WITH A MINIMUM 25 TON PNEUMATIC ROLLER. ANY WEAK
- AREAS DETECTED SHALL BE REMOVED AND REPLACED WITH SUITABLE SOILS OF SIMILAR TYPE (CLASSIFICATION, MOISTURE CONTENT AND DENSITY). 5. IF REQUIRED TO MODIFY EXISTING GRADE, FILL MATERIALS SHOULD BE PLACED ON PREPARED SURFACES IN LIFTS NOT EXCEED 8 INCHES
- (LOOSE MEASURE), WITH COMPACTED THICKNESS NOT TO EXCEED 6 INCHES OR AS INDICATED IN SITE GEOTECHNICAL REPORT. FILL SHALL BE COMPACTED TO OPTIMUM MOISTURE CONTENT OR UP TO +3 PERCENTAGE POINTS OF OPTIMUM MOISTURE CONTENT TO A MINIMUM OF 95% MAXIMUM DENSITY AS DETERMINED BY TXDOT, TEX-114-E OR AS DESCRIBED IN THE SITE GEOTECHNICAL REPORT.
- 6. ALL FILL MATERIALS SHALL BE CLEAR OF DEBRIS, ORGANICS AND VEGETATION. IF IMPORTED FILL IS USED, IT SHALL BE A RELATIVEL HOMOGENEOUS PARTICLE SIZE DISTRIBUTION, WITH MAX SIZE OF 3 INCHES, PLASTICITY INDEX BETWEEN 7 AND 20 AND A LIQUID LIMIT LESS THAN 40; OR AS INDICATED ON THE GEOTECHNICAL REPORT.
- 7. ANY EXCESS EXCAVATION MATERIALS NOT USED, SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFFSITE IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL LAWS.
- 8. CONTRACTOR IS RESPONSIBLE FOR FILING WITH THE TCEQ FOR THE TEMPORARY STORM WATER POLLUTION PREVENTION PLAN NOTICE TO PROCEED AND NOTICE OF TERMINATION AT THE START AND END OF CONSTRUCTION.
- 9. CONTRACTOR SHALL KEEP A COPY OF APPROVED CONSTRUCTION DRAWINGS ONSITE AT ALL TIMES.
- 10. ALL SPOT ELEVATIONS ARE TO EDGE OF PAVEMENT/GUTTER LINE OF CURB, FINISHED GRADE, FINISHED GRADE ADJACENT TO WALLS UNLESS OTHERWISE SPECIFIED AS BELOW
- HP HIGH POINT LOW POINT LP

ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

- ME MATCH EXISTING
- TOP OF CURB AT BACK TC TS TOP OF STRUCTURE
- ΤW TOP OF WALL
- FINISHED GRADE AT BOTTOM OF WALL BW FFE FINISHED FLOOR ELEVATION
- FINISHED GRADE FG
- 11. STORM SEWER PIPE SHALL BE ADS HP STORM (HPPP) PIPE, OR AS CALLED OUT ON PLANS.
- 12. ALL ADA PARKING STALLS, WALKING AISLES AND PATHWAYS SHALL NOT EXCEED 2% SLOPE IN ANY DIRECTION. RAMPS SHALL NOT EXCEED 8.033% SLOPE.
- 13. RETAINING WALLS SHOWN FOR FINISHED GRADE ELEVATION REFERENCE ONLY. WALL DESIGN TO BE COMPLETED BY OTHERS.

CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.







NOTES:

Copyright Hill Country Civil, LLC October 4, 2024

- 1. CONCRETE SHALL HAVE A MINIMUM THICKNESS OF 6" UNLESS NOTED OTHERWISE NOTED ON THE PLANS AND HAVE A MINIMUM OF 3,000 PSI COMPRESSIVE STRENGTH
- CONCRETE FOR WEIR SHALL BE REINFORCED WITH #3 BARS @ 12" CENTERS
- THICKENED TOE DOWN SHALL BE INSTALLED ON THE UP AND DOWNSTREAM ENDS OF THE WEIR STRUCTURE. TOE DOWN SHALL HAVE A MINIMUM THICKNESS OF 12" AND DEPTH OF 18"

1"=40' HORIZONTAL 1"=4' VERTICAL



- 1. POND WALLS SHALL BE OF WATER TIGHT DESIGN IN ORDER TO MAINTAIN PROPER FUNCTION OF THE POND.
- 2. THE CONSTRUCTION HEIGHT OF AN EARTHEN EMBANKMENT SHALL BE EQUAL TO THE DESIGN HEIGHT PLUS THE AMOUNT NECESSARY TO ENSURE THAT THE DESIGN HEIGHT WILL BE MAINTAINED ONCE ALL SETTLEMENT HAS TAKEN PLACE. ALL
- ALL ROCK RIP RAP SHALL BE A MINIMUM 6" AND HAVE A MINIMUM APRON LENGTH 3 OF 6' UNLESS SIZE IS SPECIFIED ON THE PLANS. EMBEDMENT DEPTH OF RIP RAP SHALL BE 1.5 TIMES THE DIAMETER OF THE ROCK.
- 4. ALL DISTURBED AREAS SHALL BE RESTORED AND PERMANENTLY REVEGETATED
- 164 SEEDING FOR EROSION CONTROL. PLANTING MUST FOLLOW EITHER SAN ANTONIO OR AUSTIN TXDOT REQUIREMENTS FOR SEED WEIGHT PER ACRE.
- 6. THE PLANTED AREAS SHALL BE IRRIGATED OR SPRINKLED IN A MANNER THAT WILL NOT ERODE THE TOPSOIL, BUT WILL SUFFICIENTLY SOAK THE SOIL TO A DEPTH OF SIX INCHES. THE IRRIGATION SHALL OCCUR AT TEN-DAY INTERVALS DURING THE FIRST TWO MONTHS, RAINFALL OCCURRENCES OF $\frac{1}{2}$ INCH OF MORE SHALL POSTPONE THE WATERING SCHEDULE FOR ONE WEEK.
- REFER TO DETENTION POND DETAILS SHEETS FOR ADDITIONAL DETAILS ON POND 7. DESIGN.
- 8. CONTRACTOR TO FIELD VERIFY EXISTING OUTFALLS INTO POND 1 FOR INVERT ELEVATION AND FUNCTION. ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE PLANS SHOULD BE CONVEYED TO THE ENGINEER.
- CONTRACTOR TO ADJUST EXISTING STORM DRAINS FLOWING INTO THE PONDS AS 9 NECESSARY TO MAINTAIN POSITIVE DRAINAGE INTO THE POND. ALL INFLOW PIPES TO THE POND ARE TO BE ARMORED WITH END TREATMENTS OR HEADWALLS FOR PERMANENT STABILIZATION.

CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

SHEET NO. 19

RUN Y PH.

ALOOSA | FACILITY

4

 $\overline{\Box}$

Δ

ENTION

ш

 \square

POND 1 CROSS-SECTION B-B



Copyright Hill Country Civil, LLC October 4, 2024



POND 2 CROSS-SECTION A-A

1"=40' HORIZONTAL 1"=4' VERTICAL



WEIR CROSS-SECTION B-B NTS

			Total
Stage	Elevation	Incremental	Storage
(ft)	(ft)	Storage (cuft)	(cuft)
0.00	979.50	0.00	0.00
0.50	980.00	646.00	646.00
1.50	981.00	7,054.00	7,700.00
2.50	982.00	10,946.00	18,646.00
3.50	983.00	11,217.00	29,863.00
4.50	984.00	11,486.00	41,349.00
5.50	985.00	11,753.00	53,102.00

WATER QUALITY NOTES

REQUIRED WATER QUALITY VOLUME IN POND 2 IS: 8,781 CF PROVIDED WATER QUALITY VOLUME IN POND 2 IS: 24,254.5 CF AT ELEVATION 982.5

Storm Event	Stage (ft)	Storage (cuft)	Discharge (cfs)
2-yr	982.80	26,136.00	4.100
10-yr	983.30	34,847.90	17.700
25-yr	983.50	37,025.90	24.300
100-yr	983.70	39,203.90	33.300

POND 2 STAGE, STORAGE, DISCHARGE NTS



CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.




PEST MANAGEMENT:

AN INTEGRATED PEST MANAGEMENT PLAN SHOULD BE DEVELOPED FOR VEGETATED AREAS. THIS PLAN SHOULD SPECIFY HOW PROBLEM INSECTS AND WEEDS WILL BE CONTROLLED WITH MINIMAL OR NO USE OF INSECTICIDES AND HERBICIDES. IT SHOULD ALSO ADDRESS THE MAINTAINING OF PROPER DRAINAGE FOR THE SITE THROUGH THE BATCH DETENTION PONDS.

SEASONAL MOWING AND LAWN CARE:

THE BASIN, BASIN SIDE-SLOPES AND EMBANKMENT OF THE BASIN MUST BE MOWED TO PREVENT WOODY GROWTH AND CONTROL WEEDS. A MULCHING MOWER SHOULD BE USED, OR THE GRASS CLIPPINGS SHOULD BE CAUGHT AND REMOVED. MOWING SHOULD TAKE PLACE AT LEAST TWICE A YEAR. OR MORE FREQUENTLY IF VEGETATION EXCEEDS 18 INCHES IN HEIGHT. MORE FREQUENT MOWING TO MAINTAIN AESTHETIC APPEAL MAY BE NECESSARY IN LANDSCAPED AREAS.

INSPECTION AND MAINTENANCE/REPAIR:

INSPECTIONS SHOULD TAKE PLACE A MINIMUM OF TWICE A YEAR. ONCE INSPECTION SHOULD TAKE PLACE DURING WET WEATHER TO DETERMINE IF THE BASIN IS MEETING THE TARGET DETENTION TIME OF 12 HOURS AND A DRAWDOWN TIME OF NO MORE THAN 48 HOURS. THE REMAINING INSPECTIONS SHOULD OCCUR BETWEEN STORM EVENT SO THAT MANUAL OPERATION OF THE VALVE AND CONTROLLER CAN BE VERIFIED. THE LEVEL SENSOR IN THE BASIN SHOULD BE INSPECTED AND ANY DEBRIS OR SEDIMENT IN THE AREA SHOULD BE REMOVED. THE OUTLET STRUCTURE AND THE TRASH SCREEN SHOULD BE INSPECTED FOR SIGNS OF CLOGGING. DEBRIS AND SEDIMENT SHOULD BE REMOVED FROM THE ORIFICE AND OUTLET AS DESCRIBED IN PREVIOUS SECTIONS. DEBRIS OBSTRUCTING THE VALVE SHOULD BE REMOVED. DURING EACH INSPECTION, EROSION AREAS INSIDE AND DOWNSTREAM OF THIS BMP SHOULD BE IDENTIFIED AND REPAIRED/REVEGETATED IMMEDIATELY. IN ADDITION, ELECTRICAL CONTROL SYSTEM SHOULD BE INCLUDED IN THE INSPECTION SCHEDULE. IF THE VALVE IS DAMAGED OR NOT FUNCTIONING TO ACHIEVE THE REQUIRED DRAWDOWN TIME, THEN THE VALVE SHOULD BE REPAIRED OR REPLACED.

DEBRIS AND LITTER REMOVAL:

LITTER AND DEBRIS REMOVAL SHOULD TAKE PLACE AT LEAST TWICE A YEAR, AS PART OF THE PERIODIC MOWING OPERATIONS AND INSPECTIONS. DEBRIS AND LITTER SHOULD BE REMOVED FROM THE SURFACE OF THE BASIN. PARTICULAR ATTENTION SHOULD BE PAID TO FLOATABLE DEBRIS AROUND THE OUTLET STRUCTURE. THE OUTLET SHOULD BE CHECKED FOR THE POSSIBLE CLOGGING OR OBSTRUCTIONS AND ANY DEBRIS REMOVED.

SEDIMENT REMOVAL:

SEDIMENT ACCUMULATING NEAR CULVERTS AND IN CHANNELS NEEDS TO BE REMOVED WHEN THEY BUILD UP TO 3 INCHES AT ANY SPOT. EXCESS SEDIMENT SHOULD BE REMOVED BY HAND OR WITH FLAT-BOTTOMED SHOVELS. IF AREAS ARE ERODED, THEY SHOULD BE FILLED, COMPACTED TO FINAL GRADE. SEDIMENT REMOVAL SHOULD BE PERFORMED PERIODICALLY, AS DETERMINED THROUGH INSPECTION.

PUBLIC EDUCATION:

THE DELEGATION OF MAINTENANCE RESPONSIBILITIES IS FOR THE LANDOWNER. HOWEVER, LOCALITIES SHOULD PROVIDE AN ACTIVE EDUCATIONAL PROGRAM TO ENCOURAGE THE RECOMMENDED PRACTICES. LANDSCAPERS FOR THE SITE WILL ALSO NEED TO BE EDUCATED ON THE SUITABLE PRACTICES FOR LAWN UP KEEP THROUGHOUT THE YEAR WITH LIMITED AMOUNT OF THE PESTICIDES OR FERTILIZER.

LEGEND PROPERTY BOUNDARY _____ _ _ _ _ _ _ _ _ LOT LINE — — — — — — SETBACK LINE _____ LANDSCAPE BUFFER LINE ---- --- EASEMENT LINE SITE BENCHMARK PROPERTY CORNER GAS GAS GAS GAS GAS GAS LINE ------ 0E ------- 0E ------OVERHEAD ELECTRIC LINE

EXISTING TREE _0_ SIGN $- \bigcirc -$ POWER POLE FIRE LANE \searrow EXISTING FLOW ARROW EXISTING MINOR CONTOUR _____101 _____ -101 PROPOSED MINOR CONTOUR 100 PROPOSED MAJOR CONTOUR \rightarrow PROPOSED FLOW ARROW - 600.00 PROPOSED SPOT ELEVATION

FENCE LINE

_____x _____x

PROPOSED DRAINAGE SWALE/CONCENTRATED FLOW PATH IN PAVED AREAS

TRENCH EXCAVATION SAFETY PROTECTION

CAUTION!

CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES.

DIG TESS:

CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.

CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.



OF 35



SHALLOW CONC FLOW 761' @ 3.3% UNPAVED	
SHALLOW CONC. FLOW 761' @ 3.9% UNDALED	
SHALLOW CONC FLOW 100 'e 188 1004.3	
SHALLOW CONC FLOW 761'@ 3.9% - UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED UNPAVED	
SHALLOW CONC. FLOW 101 '9' 1004.3 UNPAVED	Å
SHALLOW CONC. FLOW 761'@ 3.9% UNPAVED UNPAVED	$\langle \rangle$
SHEET FLOW 100 '@ 1.8% 1006.1 1004.3 1004.3 1004.3	
SHEET FLOW 100'@ 1.8% 1006.1 FLOW 100'@ 1.8% 1004.3 1004.3 1004.3 1004.3 1004.3	
SHALLOW CONC. FLOW 761'@ 3.9% - UNPAVED	Z
SHEET FLOW 100' @ 1.8% 1004.3 1000 1000 1000 1000 1000 1000 1000 10	
SHALLOW CONC. FLOW 761' @ 3.9% UNPAVED	1
SHALLOW CONC. FLOW 761' @ 3.9% - UNPAVED UNPAVED	
	LOT 14 APPALOOSA RU (67/79)
	<u>-,</u>
	ent
APPLICIS RUN (67/79)	
EDA 3 (EDA 3	
3.95 AC 3.95 AC 3.95 AC	~~~
$\begin{bmatrix} -1 \\ -1 \\ -1 \\ -1 \\ -1 \\ -1 \\ -1 \\ -1 $	2
	Junin na
AP2: 983.8	
	7
CHANNEL FLOW 235' > (987.1 %) (987.1	}
	}
	ξ
Proposed Time of Concentration (min): 21.4 Lag Time (min): 12.9	
Minimum Initial T _c (min): 5 Elevation (ft) Wetted XS Incremental Cumulative Segment Condition (ft) Start End n (ft/s) (ft) Travel (min) Travel (min). Travel (min).*	
1 Sheet 100.0 1086.0 1081.7 0.240 N/A N/A 0.0430 9.2370 9.2370 2 Shall. Conc. 2376.0 1081.7 985.5 N/A N/A 0.0405 12.1976 21.4346 3 Channel or Sewer 0.0 0.0 0.0000 0.0000 21.4346	
Drainage Area Name: EDA 2 Proposed Time of Concentration (min): 21.8 Lag Time (min): 13.1 *Minimum Initial T _o (min): 5 Elevation (ft) Wetted	
Segment Condition Length (ft) Start End n (ft/s) Perimeter (ft) Area (sq. ft.) Slope (ft/ft) Time of Travel (min) Time of Travel (min)* 1 Sheet 100.0 1081.0 1074.0 0.240 N/A N/A 0.0700 7.6011 7.6011 2 Shall. Conc. 2367.0 1074.0 987.1 N/A N/A 0.0367 12.7609 20.3620 Final Area 10.000 10.	
3 Channel or Sewer 235.0 987.1 983.8 0.040 20.00 10.00 0.0140 1.4085 21.7705 Drainage Area Name: EDA 3 Proposed Time of Concentration (min): 17.1 Lag Time (min): 10.3	\sim
Elevation (ft) Mannings Velocity Perimeter Area Slope Time of Segment Condition (ft) Start End n (ft/s) (ft) (ft/s) (ft/s) Travel (min)	~
1 Sheet 100.0 1006.1 1004.3 0.240 N/A N/A 0.0180 13.0861 13.0861 2 Shall. Conc. 761.0 1004.3 975.0 N/A N/A 0.0385 4.0062 17.0923 3 Channel or Sewer 0.0 975.0 0.0 0.0000 17.0923	
COMPOSITE CURVE NUMBER RUNOFF SUMMARY TABLE Drainage Area Name: EDA 1	
DESCRIPTIONAREACNResidential District, Average lot size 2-ac, 12% IC49.582Open space, Good condition11.4780Best below (cfs)10 yr25 yrDescription (cfs)100 yr	
Paved parking lots, root, driveway, etc. 0 98 Total 60.97 82 EDA 1 AP 1 142.7 266.2 BDA 1 AP 1 142.7 266.2 EDA 2 AP 2 23.6 44.3 EDA 2 AP 2 23.6 44.3	\
DESCRIPTIONAREACNResidential District, Average lot size 2-ac, 12% IC5.782Open space, Good condition4.3380	
Paved parking lots, roof, driveway, etc. 0.1 98 Total 10.13 81	
DESCRIPTION AREA CN Residential District, Average lot size 2-ac, 12% IC 0.96 82 Open space, Good condition 2.82 80 Description 0.17 02	

Copyright Hill Country Civil, LLC October 4, 2024

Total 3.95 81



Civil - ZHill Country (Engineers • Consultant 1042 Northpark Ridge, Phone: 817-659-9 www.hillco SCALE: 1"=100' LEGEND PROPERTY BOUNDARY _____ LOT LINE セ _____ SETBACK LINE LANDSCAPE BUFFER LINE EASEMENT LINE $\mathbf{\mathbf{+}}$ SITE BENCHMARK PROPERTY CORNER GAS GASLINE OVERHEAD ELECTRIC LINE FENCE LINE \bigcirc EXISTING TREE . Incal _0_ SIGN ____ POWER POLE X FIRE LANE ROSS T. CORDER 125401 TIME OF CONCENTRATION CENSE DRAINAGE AREA BOUNDARY / DA # ` DRAINAGE AREA LABEL ACRES
 No
 APPALOOSA RUN STORAGE FACILITY PH. 3 & 4 12100 RM 1826 AUSTIN, TEXAS 78737 ш C 4 CAUTION! STING DRAINA AREA MAP CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES. EXIS⁻ TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE SHEET NO. TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH 24 SAFETY PLAN IN ACCORDANCE WITH OSHA REGULATIONS GOVERNING THE PRESENCE AND

OF 35

ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

	La S S		
		mas 2	
Land of			
All cr ~		$\sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i$	
			S Company and S
		5HEET FLOW	
		1004.3	
	SHALLOW CONC. FLOW		
	334'@ 2.6% UNPAVED	CHANNEL FLOW	s LOT 14 APPALOOS RUN
	рит. то со		.5 .5
984.7	CONC. FLOW 362' @ 3.0% PAVED	SHA SHA IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII	ALLOW NC. FLOW '@ 1.4% >
		PDA 1A PDA 1A	ED TRE-100.00 X - 200-00 X - 100-00 X -
PDA 3	ROUTING ODA2 307'		
3.96 AC	999 CHA 190'	© 2.5%	
		994	
PDA 2 PDA 2 PD		991.0	
	SHEET FLOW 100' @ 1.8% 990.0		PDA1
986 986 989 989 989	988.2,		
986.9 CHANNEL FLOW 204' @ 1.5% FLOW	90 LLOW CONC.		
	AVED		
TIME OF CONCENTRATIO	ON 985.5 AP 1		
Drainage Area Name: ODA 1 Proposed Time of Concentration (min): 22.6 Lag Elevation (ft)	Time (min): 13.5 <i>*Minimum Initial T_c (min):</i> Wetted XS Incremental	5 Cumulative	
Segment Condition Length (ft) Start End Ma 1 Sheet 100.0 1086.0 1081.7 0 2 Shall. Conc. 1688.0 1081.7 1001.0	Innings Velocity Perimeter (ft/s) Area (ft) Slope (gq, ft.) Time of (ft/ft) Travel (min) 2.240 N/A N/A 0.0430 9.2370 N/A N/A 0.0478 7.9747	Time of Travel (min)* 9.2370 17.2117	
3 Channel or Sewer 960.0 1001.0 985.5 0 Drainage Area Name: ODA 1A Proposed Time of Concentration (min): 16.0 Lag	20.040 20.00 10.00 0.0161 5.3660	22.5777 CHANNEL / FLOW 960' @ 1.6%	
Segment Condition (ft) Start End	*Minimum Initial T _c (min): Metted XS Incremental Innings Velocity Perimeter Area Slope Time of n (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min)	5 Cumulative Time of Travel (min)*	
1 Sheet 100.0 1087.0 1083.0 0 2 Shall. Conc. 1492.0 1083.0 999.0 3 Channel or Sewer 999.0 999.0	N/A N/A 0.0400 9.5081 N/A N/A 0.0563 6.4954 0.0000 0.0000 0.0000	9.5081 16.0035 16.0035 Drainage Area Name:	
Drainage Area Name: ODA 2 Proposed Time of Concentration (min): 16.8 Lag Elevation (ft) Elevation (ft)	Time (min): 10.1 <i>*Minimum Initial T_c (min):</i> Wetted XS Incremental	DESCRIPTION Residential District, Average lot size 2-ac, 12% IC 5 Open space, Good condition Paved parking lots, roof, driveway, etc.	AREA CN 44.5 82 2.62 80 0.21 98
Segment Condition Length (ft) Start End Ma 1 Sheet 100.0 1081.0 1074.0 0 2 Shall. Conc. 1598.0 1074.0 998.5	Innings Velocity Perimeter Area Slope Time of n (ft/s) (ft) (gq. ft.) (ft/ft) Travel (min) 1 0.240 N/A N/A 0.0700 7.6011 1 1 N/A N/A 0.0472 7.5943 1	Time of Travel (min)* 7.6011 15.1954 Drainage Area Name: DESCRIPTION Description	ODA 1A
3 Channel or Sewer 289.0 998.5 993.8 0 Drainage Area Name: PDA 1 Proposed Time of Concentration (min): 8.7 Lag	1.040 20.00 10.00 0.0163 1.6096 Time (min): 5.2 *Minimum Lag Time (min): *Minimum Initial T(min):	16.8050 Open space, Good condition Paved parking lots, roof, driveway, etc.	0.23 80 0 98 Fotal 7.29 82
Segment Condition (ft) Length Ma Segment Condition (ft) Start End	Innings Velocity Perimeter Area Slope Time of (ft/s) (ft/s) (sq. ft.) (ft/ft) Travel (min)	Cumulative Time of Travel (min)* 1 7341 Open space. Good condition	ODA 2 AREA CN 10.81 82 0.41 80
1 100.0 1004.9 1003.8 0 2 Shall. Conc. 573.0 1003.8 995.4 3 Shall. Conc. 279.0 992.4 990.0	N/A N/A 0.0110 1.7341 N/A N/A 0.0147 3.8801 0.0086 3.1074	1.7.341 Paved parking lots, roof, driveway, etc. 8.7215 Drainage Area Name:	0 98 Total 11.22 82 PDA 1
Proposed Time of Concentration (min): 14.5 Lag	Time (min): 8.7 *Minimum Initial T _c (min): Wetted XS Incremental Incremental	DESCRIPTION 5 Residential District, Average lot size 2-ac, 12% IC 5 Open space, Good condition Cumulative Paved parking lots, roof, driveway, etc.	AREA CN 0 82 3.45 80 7.4 98
Segment Condition (ft) Start End 1 Sheet 100.0 990.0 988.2 0 2 Shall. Conc. 36.0 988.2 986.9 3 Channel or Sewer 204.0 096.0 092.0 0	n (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min) 0.240 N/A N/A 0.0180 13.0861 N/A N/A 0.0361 0.1957 0.040 20.00 10.00 0.0152 1.1754	Drainage Area Name: 13.2818 14.4571	Ottal 10.85 92 MUNUFF PDA 2 Rainfall Runoff - S Rainfall Runoff - S
Drainage Area Name: PDA 3 Proposed Time of Concentration (min): 15.6	<u></u>	Kesigential District, Average lot size 2-ac, 12% IC Open space, Good condition	0 82 <u>E</u> 0.71 80 <u>E</u> 0.94 98 <u>E</u> 2 yr
	Time (min): 9.4 *Minimum Initial T_(min):	Paved parking lots, roof, driveway, etc.	iotal 1.65 90
Segment Condition (ft) Elevation (ft) 1 Sheet 100.0 1000.4 400.40 0	Best Stress Stress innings Velocity Vetted XS Incremental innings Velocity Perimeter Area Slope Time of innings (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min)	5 Cumulative Time of Travel (min)* Residential District, Average lot size 2-ac, 12% IC Open space Good condition	otal 1.65 90 E PDA 3 ODA 1 110.0 AREA CN ODA 2 29.7 0.91 82 PDA 1 W/ POND 24.6 0.99 %0 CONSTRUCT 10.0

Copyright Hill Country Civil, LLC October 4, 2024



 259.1
 344.6
 484.8

 9.8
 12.3
 16.5

 17.7
 24.3
 33.3



ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.



CC)OneDrive - Hill Country Civil/Projects/041 AAA Storage/01 FM 1826 Storage Phase 3/1 - CAD/2 - Sheets/041-01 UTIL.dw

ClOneDrive - Hill Country Civil/Projects/041 AAA Storage\01 EM 1826 Storage Phase 3\1 - CAD\2 - Sheets\041-01 UTI

AUSTIN WATER		WASTEWATER CLEANOUT F	RAME AND LID
<u>0</u>	08/16/2019 ADOPTED	THE ENGINEER/ARCHITECT ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD. MODIFICATIONS TO THIS STANDARD ARE PROHIBITED.	STANDARD NO. 520-AW-03 1 OF 1

Copyright Hill Country Civil, LLC October 4, 2024

TRIAN RAMP. RADIUS AND	
W THE FIRE SHOE TYPES)	
ESTRAINT OF RESTRAINT	
D AND FILLED AND AROUND E STD. SPEC. RAIN GRAVEL	
RAP AT BOOT	
CATION ITEM ON THE SIDE	

– #5 BARS @

MID-DEPTH

- PROPOSED

HMAC DEPTH

---Ø8½"---

→Ø7½"→

╼│**|**╼──*१*%" ── ►| |╼

- 1/3"

STANDARD NO.

511-AW-01

3 OF 4

COLLAR *

* 12" COLLAR: 39 LBS

- CONCRETE PAD

PLAN VIEW

3" CLEAR ----

| - Ø 6" →

⊢Ø6" ·

Revisions							
Date							
Ž							
RUN STORAGE 7 PH. 3 & 4	RM 1826	EXAS 78737			DRAWN BY.: RTC		
APPALOOSA FACILITY	12100	AUSTIN, T			HCC JOB No.: 041-01		
		UTILITY DETAILS (2 OF 2)					
SHE	SHEET NO.						
		33					
		(DF 3	5			

6" BOLLARD DETAIL N.T.S.

	Engineers • Consultants	Texas FirmLicense No. F-22872 1042 Northpark Ridge, New Braunfels, TX 78130 Phone: 817-659-9078 or 210-578-4953 www.hillcountrycivil.com				
Rose Rose Rose Rose Rose Rose Rose Rose	SS T. CO 12540	RDER 1 2 2 2 2 2				
App.						
No. Date Revisions						
APPALOOSA RUN STORAGE FACILITY PH. 3 & 4	12100 RM 1826 AUSTIN, TEXAS 78737	HCC.JOB No : 041-01 DRAWN BY : RTC				
SITE DETAILS (2 OF 2)						
SHE	ET N 35	10. 5 DF 35				

TCEQ Calculation Pond 1

Texas Commission on Environmental Quality				
TSS Removal Calculations 04-20-2009				Project Name: AAA FM 1826 Date Prepared: 4/26/2024
Additional information is provided for cells with a red tria Text shown in blue indicate location of instructions in the Tech Characters shown in red are data entry fields. Characters shown in black (Bold) are calculated fields. C	ngle i Inrical Thange	n the up Guidance es to the	per right co e Manual - F se fields wi	arner. Place the cursor over the cell. RG-348. Il remove the equations used in the spreadsheet.
1. The Required Load Reduction for the total project:	С	alculations	from RG-348	Pages 3-27 to 3-30
Page 3-29 Equation 3.3:	L _M = 2	7.2(A _N x P)		
where: L _{M TOTAL PROJ}	_{ECT} = R A _N = N P = A	equired TS let increase verage ani	S removal res in impervious nual precipitatio	ulting from the proposed development = 80% of increased load area for the project on, inches
Site Data: Determine Required Load Removal Based on the Entire P	roject			
Cou Total project area included in pla Predevelopment impervious area within the limits of the pla Total post-development impervious area within the limits of the pl Total post-development impervious cover fraction	nty = n * = an* = lar* = P =	Travis 17.88 0.27 10.40 0.58 32	acres acres acres inches	Russentinlande
	ECT =	8817	lbs.	ATE OF TEXAS
* The values entered in these fields should be for the total project are	ea.			
Number of drainage basins / outfalls areas leaving the plan a	irea =	2		ROSS T. CORDER
2. Drainage Basin Parameters (This information should be provided for	or eacl	n basin)		
Drainage Basin/Outfall Area N	No. =	1		LISSIONAL HOLD
Total drainage basin/outfall a	rea=	10.85	acres	CISTERNAL -
Predevelopment impervious area within drainage basin/outfall a	are; =	0.00	acres	
Post-development impervious area within drainage basin/outfall a	are; =	7.40	acres	
Post-development impervious fraction within drainage basin/outfall a	are; =	0.68		
L _{M THIS BA}	ASIN =	6441	lbs.	
3. Indicate the proposed BMP Code for this basin.				
Proposed BI	MP = B	atch Dete	ntion	
Removal efficier	ncy =	91	percent	Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault Batch Detention

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A x 34.6 + A_P x 0.54)

where:

- A_{C} = Total On-Site drainage area in the BMP catchment area
- A_I = Impervious area proposed in the BMP catchment area

 $A_{\rm P}$ = Pervious area remaining in the BMP catchment area

 L_R = TSS Load removed from this catchment area by the proposed BMP

Batch Detention

A _C =	10.85	acres
A _i =	7.40	acres
A _P =	3.45	acres
L _R =	7510	lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall	area				
Desired L _{M THIS BASIN} =	7000	lbs.			
F =	0.93				
6. Calculate Capture Volume required by the BMP Type for this drainage b	oasin / outfa	ll area	Calculations from RG	-348	Pages 3-34 to 3-36
Rainfall Depth = Post Development Runoff Coefficient =	2.20 0.49	inches			
Un-site Water Quality Volume -	42302	Cubic leet			
	Calculations	s from RG-348	Pages 3-36 to 3-37		
Off-site area draining to BMP =	11.20	acres			
Off-site Impervious cover draining to BMP =	0.00	acres			
Impervious fraction of off-site area =	0.00				
Off-site Vater Quality Volume =	1789	cubic feet			
Storage for Sediment =	8818				
Total Capture Volume (required water quality volume(s) x 1.20) =	52909	cubic feet		1.21	Acre-ft
The following sections are used to calculate the required water quality vol	lume(s) for t	the selected BI	MP.		
7. Retention/Irrigation System	Designed as	s Required in R	G-348	Pages 3-42 to	o 3-46
Required Water Quality Volume for retention basin =	= NA	cubic feet			
Irrigation Area Calculations:					
Soil infiltration/permeability rate = Irrigation area =	<mark>0.1</mark> NA NA	in/hr square feet acres	Enter determined pe	ermeability ra	te or assumed value of 0.1
8. Extended Detention Basin System	Designed as	s Required in R	G-348	Pages 3-46 to	o 3-51
Required Water Quality Volume for extended detention basin	= NA	cubic feet			
9. Filter area for Sand Filters	Designed as	s Required in R	G-348	Pages 3-58 to	o 3-63
9A. Full Sedimentation and Filtration System					
Water Quality Volume for sedimentation basin =	= NA	cubic feet			
Minimum filter basin area =	NA	square feet			
Maximum sedimentation basin area = Minimum sedimentation basin area =	NA NA	square feet square feet	For minimum water For maximum water	depth of 2 fe depth of 8 fe	et
9B. Partial Sedimentation and Filtration System					
Water Quality Volume for combined basins =	NA NA	cubic feet			
Minimum filter basin area =	NA	square feet			
Maximum sedimentation basin area = Minimum sedimentation basin area =	NA NA	square feet square feet	For minimum water For maximum water	depth of 2 fe depth of 8 fe	et et
10. Bioretention System	Designed as	s Required in R	G-348	Pages 3-63 to	o 3-65
Required Water Quality Volume for Bioretention Basin =	= NA	cubic feet			
11. Wet Basins	Designed as	s Required in R	G-348	Pages 3-66 to	o 3-71
Required capacity of Permanent Pool = Required capacity at WQV Elevation =	NA NA	cubic feet cubic feet	Permanent Pool Cap Total Capacity shou plus a second WQV	pacity is 1.20 Ild be the Per	times the WQV manent Pool Capacity

12. Constructed Wetlands	Designed as I	Required in RG-348	Pages 3-71 to 3-73
Required Water Quality Volume for Constructed Wetlands	= NA	cubic feet	
13. AquaLogic [™] Cartridge System	Designed as I	Required in RG-348	Pages 3-74 to 3-78
** 2005 Technical Guidance Manual (RG-348) does not exempt the require	ed 20% increas	e with maintenance contract with	h AquaLogic [™] .
Required Sedimentation chamber capacity Filter canisters (FCs) to treat WQV Filter basin area (RIA _F)	= NA = NA = NA	cubic feet cartridges square feet	
14. Stormwater Management StormFilter® by CONTECH			
Required Water Quality Volume for Contech StormFilter System	= NA	cubic feet	
THE SIZING REQUIREMENTS FOR THE FOLLOWING BMPs / LOAD REM	OVALS ARE B	ASED UPON FLOW RATES - NOT	CALCULATED WATER QUALITY VOLUME
15. Grassy Swales	Designed as I	Required in RG-348	Pages 3-51 to 3-54
Design parameters for the swale:			
$\label{eq:product} \begin{array}{l} \mbox{Drainage Area to be Treated by the Swale = A Impervious Cover in Drainage Area Rainfall intensity = i Swale Slope (2): Swale Slope (2): Design Water Depth = y: Weighted Runoff Coefficient = C \\ \mbox{A}_{CS} = cross-sectional area of flow in Swale P_W = Wetted Perimeter = R_H = hydraulic radius of flow cross-section = A_{CS}/P_W = R_H = hydraulic radius of flow cross-section = A_{CS}/P_W = n = Manning's roughness coefficient = T \\ \mbox{ISA. Using the Method Described in the RG-348} \\ \mbox{Manning's Equation: } Q = \underline{1.49} A_{CS} R_{H}^{2/3} S^{0.7} R_{H}^{1/3} S^{0.$	= 0.0 = 0.0 = 1. = 0.0 = #DIV/0! = #DIV/0! = #DIV/0! = 0.:	0 acres 0 acres 1 in/hr 0 ft/ft 0 ft sf feet feet 2	
$b = \frac{0.134 \text{ x Q}}{\text{y}^{1.67} \text{ S}^{0.5}} - \text{zy}^{-5}$	= #DIV/0!	feet	
Q = CiA :	= #DIV/0!	cfs	
To calculate the flow velocity in the swale:			
V (Velocity of Flow in the swale) = Q/A_{CS}	= #DIV/0!	ft/sec	
To calculate the resulting swale length:			
L = Minimum Swale Length = V (ft/sec) * 300 (sec)	= #DIV/0!	feet	
If any of the resulting values do not meet the design requirement	ent set forth in F	RG-348, the design parameters mu	st be modified and the solver rerun.

15B. Alternative Method using Excel Solver

Design Q = CiA =	#DIV/0!	cfs		
Manning's Equation Q = Swale Width=	0.00 6.00) cfs) ft	Error 1 =	#DIV/0!
Flow Velocity Minimum Length =	#DIV/0! #DIV/0!	ft/s ft		
Design Width = Design Discharge = Design Depth = Flow Velocity = Minimum Length =	0 0.00 0.33 #DIV/0! #DIV/0!) ft) cfs 3 ft cfs ft	Error 2 =	#DIV/0!

If any of the resulting values do not meet the design requirement set forth in RG-348, the design parameters may be modified and the solver rerun. If any of the resulting values still do not meet the design requirement set forth in RG-348, widening the swale bottom value may not be possible.

16. Vegetated Filter Strips

Designed as Required in RG-348

Pages 3-55 to 3-57

There are no calculations required for determining the load or size of vegetative filter strips. The 80% removal is provided when the contributing drainage area does not exceed 72 feet (direction of flow) and the sheet flow leaving the impervious cover is directed across 15 feet of engineered filter strips with maximum slope of 20% or across 50 feet of natural vegetation with a maximum slope of 10%. There can be a break in grade as long as no slope exceeds 20%

If vegetative filter strips are proposed for an interim permanent BMP, they may be sized as described on Page 3-56 of RG-348

17. Wet Vaults	Designed as	Required in R	G-348 Pages 3-30 to 3-32 & 3-79
Required Load Removal Based upon Equation 3.3	= NA	lbs	
First calculate the load removal at 1.1 in/hour			
RG-348 Page 3-30 Equation 3.4: Q = C	iA		
C = runoff coefficient for the drainage area i = design rainfall intensity A = drainage area in acres	= 0. = 1 =	51 .1 in/hour 1 acres	C = Runoff Coefficient = 0.546 (IC) ² + 0.328 (IC) + 0.03
Q = flow rate in cubic feet per second	= 0.	56 cubic feet/se	ec
RG-348 Page 3-31 Equation 3.5: $V_{OR} = Q/$	A		
Q = Runoff rate calculated above A = Water surface area in the wet vault	= 0. =	56 cubic feet/se 0 square feet	20
V _{OR} = Overflow Rate	= #DIV/0!	feet/sec	
Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31)	=	0 percent	
Load removed by Wet Vault	= #VALUE!	lbs	
If a bypass occurs at a rainfall intensity of less than 1.1 in/hours Calculate the efficiency reduction for the actual rainfall intensity rate			
Actual Rainfall Intensity at which Wet Vault bypass Occurs	; =	0 in/hour	
Fraction of rainfall treated from Figure 3-2 RG-348 Page 3-32 Efficiency Reduction for Actual Rainfall Intensity	= v = 0.	0 percent 00 percent	
Resultant TSS Load removed by Wet Vault	= #VALUE!	lbs	
18. Permeable Concrete	Designed as	Required in R	G-348 Pages 3-79 to 3-83

PERMEABLE CONCRETE MAY ONLY BE USED ON THE CONTRIBUTING ZONE

19. BMPs Installed in a Series		Designed as	Required in R	G-348 Pages 3-32	
	Michael E. Ba	rrett, Ph.D P.E. recommended that the coeff	icient for E ₂ b	e changed fr	om 0.5 to 0.65 on May 3, 2006
	E _{TOT} = [1	- ((1 - E ₁) X (1 - 0.65E ₂) x (1 - 0.25E ₃))] X 100 =	0.0	0 percent	NET EFFICIENCY OF THE BMPs IN THE SERIES
	EFFICIENCY OF FIRST BMP IN THE SERIES = E_1 =		0.0	0 percent	
	EFFICIENCY	OF THE SECOND BMP IN THE SERIES = E_2 =	0.0	0 percent	
	EFFICIENC	CY OF THE THIRD BMP IN THE SERIES = $E_3 =$	0.0	0 percent	
	THEREFORE, (A _I AND A _P VA	THE NET LOAD REMOVAL WOULD BE: LUES ARE FROM SECTION 3 ABOVE)			
		L _R = E _{TOT} X P X (A _I X 34.6 X A _P X0.54) =	0.0	0 lbs	
20. Stormcep	tor				
		Required TSS Removal in BMP Drainage Area=	NA	lbs	
		Impervious Cover Overtreatment=	0.0000	ac	
		TSS Removal for Uncaptured Area =	0.00	lbs	
	BMP Sizing				
	Actual Mo	= Effective Area = Calculated Model Size(s) del Size (if multiple voluce provided in Calculate	NA #N/A	EA	
	Model	Size or if you are choosing a larger model size) =	0	Model Size	
		Surface Area =	#N/A	ft ²	
		Overflow Rate =	#VALUE!	Vor	
		Rounded Overflow Rate =	#VALUE!	Vor	
		BMP Efficiency % =	#VALUE!	%	
		L _R Value =	#VALUE!	lbs	
		TSS Load Credit =	#VALUE!	lbs	
	Is Sufficient T	reatment Available? (TSS Credit <u>></u> TSS Uncapt.)	#VALUE!		
		TSS Treatment by BMP (LM + TSS Uncapt.) =	#VALUE!		
21. Vortech					
		Required TSS Removal in BMP Drainage Area=	NA	lbs	
		Impervious Cover Overtreatment=	0.0000	ac	
	DUD 0	TSS Removal for Uncaptured Area =	0.00	lbs	
	BMP Sizing	Effective Area =	NA #N/A	EA	
	٨	tual Model Size (if choosing larger model size) -	Vx1000	Pick Model	Size
			7 10	1 10K 1000Cl	
		Surface Area =	7.10	π	
			#VALUE!	v _{or} V	
			#VALUE!	• or 0/2	
		L - Value =		/u lbe	
		L _R value –	#VALUE!	IDP	
		TSS Load Credit =	#VALUE!	lbs	
	Is Sufficient T	reatment Available? (TSS Credit <u>></u> TSS Uncapt.)	#VALUE!		
		TSS Treatment by BMP (LM + TSS Uncapt.) =	#VALUE!		

TCEQ Calculation Pond 2

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: AAA FM 1826 Date Prepared: 4/26/2024

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348. Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the sp

1. The Required Load Reduction for the total project: Calculations from RG-348 Pages 3-27 to 3-30 Page 3-29 Equation 3.3: L_M = 27.2(A_N x P) $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of where: A_N = Net increase in impervious area for the project P = Average annual precipitation, inches Site Data: Determine Required Load Removal Based on the Entire Project Travis County = Total project area included in plan * = 17.88 acres Predevelopment impervious area within the limits of the plan* = 0.27 acres Total post-development impervious area within the limits of the plan* = 10.40 acres Total post-development impervious cover fraction * = 0.58 P = 32 inches L_{M TOTAL PROJECT} = 8817 lbs. * The values entered in these fields should be for the total project area. Number of drainage basins / outfalls areas leaving the plan area = 2 CORDER 2. Drainage Basin Parameters (This information should be provided for each basin): Drainage Basin/Outfall Area No. = 2 Total drainage basin/outfall area = 3.96 acres Predevelopment impervious area within drainage basin/outfall area = 0.17 acres Post-development impervious area within drainage basin/outfall area = 2.06 acres Post-development impervious fraction within drainage basin/outfall area = 0.52

L_{M THIS BASIN} =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP =	Batch Deten	tion
Removal efficiency =	91	percent

1645

lbs.

Aqualogic Cartridge Filt Bioretention Contech StormFilter Constructed Wetland Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault Batch Detention

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L	. _R = (BMP efficien	ncy) x P x (A _l x	34.6 + A _P x 0.54)
where: A	ч _с = Т	Fotal On-Site	e drainage area	in the BMP catchment area
P A		mpervious a	rea proposed il	n the BMP catchment area
A	чр = н – т		a remaining in t	the BMP catchment area
	. _R – I	ISS Load rei	moved from thi	s catchment area by the proposed BMP
A	. _с =	3.96	acres	
Α	۹ _I =	2.06	acres	
A	۱ _P =	1.90	acres	
L	. _R =	2105	lbs	
5. Calculate Fraction of Annual Runoff to Treat the drainage basin / out	fall a	irea_		
Desired L _{M THIS BASI}	_{IN} =	1817	lbs.	
	F =	0.86		
6 Calculate Canture Volume required by the BMD Type for this drainage	o hai	sin / outfall	2102	Calculations from PC 348 Pages 3 (
o. Calculate Capture volume required by the BMP Type for this dramage	<u>e na</u> :		area.	Calculations from ICO-340 Pages 3-C
Rainfall Dept	th =	1.38	inches	
Post Development Runoff Coefficient	t =	0.37		
On-site Water Quality Volume	e =	7317	cubic feet	
	C	Calculations	from RG-348	Pages 3-36 to 3-37
Off-site area draining to BM	P =	0.00	acres	
Off-site Impervious cover draining to BMI	P =	0.00	acres	
Impervious fraction of off-site area	:a =	0		
Off-site Runoff Coefficien	1t =	0.00		
Off-site Water Quality Volume	e =	0	cubic feet	
Storage for Sedimen	nt =	1463		
Total Capture Volume (required water quality volume(s) x 1.20)) =	8781	cubic feet	0.20 Acre-ft
The following sections are used to calculate the required water quality	volu	me(s) for th	e selected BM	Ρ.
The values for BMP Types not selected in cell C45 will show NA.			Doguirod in D(Dages 2,42 to 2,46
7. Retention/irrigation System	L	Jesigned as	Required in RU	5-348 Pages 3-42 to 3-46
Required Water Quality Volume for retention basi	in =	NA	cubic feet	
Irrigation Area Calculations:				
Soil infiltration/permeability rate Irrigation area	e = a =	0 NA NA	in/hr square feet acres	Enter determined permeability rate or assu
8. Extended Detention Basin System	C	Designed as	Required in R	G-348 Pages 3-46 to 3-51
Required Water Quality Volume for extended detention basi	in =	NA	cubic feet	
9. Filter area for Sand Filters	C	Designed as	Required in R	G-348 Pages 3-58 to 3-63
9A. Full Sedimentation and Filtration System				
Water Quality Volume for sedimentation basi	in =	NA	cubic feet	
Minimum filter basin are	ea =	NA	square feet	
Maximum sedimentation basin are Minimum sedimentation basin are	ea = ea =	NA NA	square feet square feet	For minimum water depth of 2 feet For maximum water depth of 8 feet

9B. Partial Sedimentation and Filtration System

Water Quality Volume for combined basins =	NA	cubic feet		
Minimum filter basin area =	NA	square feet		
Maximum sedimentation basin area = Minimum sedimentation basin area =	NA NA	square feet square feet	For minimum water For maximum water	depth of 2 feet depth of 8 feet
10. Bioretention System	Designed as	Required in R	G-348	Pages 3-63 to 3-65
Required Water Quality Volume for Bioretention Basin =	NA	cubic feet		
11. Wet Basins	Designed as	Required in R	G-348	Pages 3-66 to 3-71
Required capacity of Permanent Pool = Required capacity at WQV Elevation =	NA NA	cubic feet cubic feet	Permanent Pool Cap Total Capacity shoul plus a second WQV.	acity is 1.20 times the Id be the Permanent Pc
12. Constructed Wetlands	Designed as	Required in R	G-348	Pages 3-71 to 3-73
Required Water Quality Volume for Constructed Wetlands =	NA	cubic feet		
<u>13. AquaLogic[™] Cartridge System</u>	Designed as	Required in R0	G-348	Pages 3-74 to 3-78
** 2005 Technical Guidance Manual (RG-348) does not exempt the required	d 20% increas	e with mainte	enance contract with	AquaLogic [™] .
Required Sedimentation chamber capacity = Filter canisters (FCs) to treat WQV = Filter basin area (RIA _F) =	NA NA NA	cubic feet cartridges square feet		
14. Stormwater Management StormFilter® by CONTECH				
Required Water Quality Volume for Contech StormFilter System =	NA	cubic feet		
THE SIZING REQUIREMENTS FOR THE FOLLOWING BMPs / LOAD REMO	VALS ARE BA	SED UPON F	LOW RATES - NOT C	ALCULATED WATER (
15. Grassy Swales	Designed as	Required in R	G-348	Pages 3-51 to 3-54
Design parameters for the swale:				
Drainage Area to be Treated by the Swale = A = Impervious Cover in Drainage Area = Rainfall intensity = i = Swale Slope = Side Slope (z) = Design Water Depth = y = Weighted Runoff Coefficient = C =	0.0 0.0 1. 0.0 #DIV/0!	0 acres 0 acres 1 in/hr 0 ft/ft 0 0 ft		
A_{CS} = cross-sectional area of flow in Swale =	#DIV//01			
P _w = Wetted Perimeter =	#DIV/0! #DIV/0!	st feet		

 $\begin{array}{ll} R_{\text{H}} = \text{hydraulic radius of flow cross-section} = A_{\text{CS}}/P_{\text{W}} = & \#\text{DIV}/0! & \text{feet} \\ & n = \text{Manning's roughness coefficient} = & 0.2 \end{array}$

15A. Using the Method Described in the RG-348

Manning's Equation:	Q = <u>1.49</u> A _{CS} R _H ^{2/3} S ^{0.5} n		
	$b = 0.134 \times Q - zy = y^{1.67} S^{0.5}$	#DIV/0!	feet
	Q = CiA =	#DIV/0!	cfs
To calculate the flow velocity in the swale:			
V (Velocity of Flo	w in the swale) = Q/A_{CS} =	#DIV/0!	ft/sec
To calculate the resulting swale length:			
L = Minimum Swale Lengtl	n = V (ft/sec) * 300 (sec) =	#DIV/0!	feet

If any of the resulting values do not meet the design requirement set forth in RG-348, the design parameters must be modified and the solv

15B. Alternative Method using Excel Solver

Design Q = CiA =	#DIV/0!	cfs		
Manning's Equation Q = Swale Width=	0.00 6.00) cfs) ft	Error 1 =	#DIV/0!
Flow Velocity Minimum Length =	#DIV/0! #DIV/0!	ft/s ft		
Design Width = Design Discharge = Design Depth = Flow Velocity = Minimum Length =	0.00 0.33 #DIV/0! #DIV/0!	ft cfs ft cfs ft	Error 2 =	#DIV/0!

If any of the resulting values do not meet the design requirement set forth in RG-348, the design parameters may be modified and the solver reru If any of the resulting values still do not meet the design requirement set forth in RG-348, widening the swale bottom value may not be possible.

6. Vegetated Filter Strips	Designed as Required in RG-348	Pages 3-55 to 3-57
----------------------------	--------------------------------	--------------------

There are no calculations required for determining the load or size of vegetative filter strips. The 80% removal is provided when the contributing drainage area does not exceed 72 feet (direction of flow) and the sheet flow leaving the impervious cover is directed across 15 feet of engineered filter strips with maximum slope of 20% or across 50 feet of natural vegetation with a maximum slope of 10%. There can be a break in grade as long as no slope exceeds 20%.

If vegetative filter strips are proposed for an interim permanent BMP, they may be sized as described on Page 3-56 of RG-348.

Required Load Removal Based upon Equation 3.3 = NA Ibs First calculate the load removal at 1.1 in/hour RG-348 Page 3-30 Equation 3.4: Q = CiA C = runoff coefficient for the drainage area = i = design rainfall intensity = A = drainage area in acres = 0.35 C = Runoff Coefficient = 0.546 (IC) ² + 0.328 Q = flow rate in cubic feet per second = 0.00 cubic feet/sec 0 acres Q = Runoff rate calculated above = A = Water surface area in the wet vault = 0.00 cubic feet/sec V _{OR} = Overflow Rate = #DIV/0! feet/sec Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent Load removed by Wet Vault = #VALUE! Ibs	17. Wet Vaults	Designed as I	Required in R	G-348 Pages 3-30 to 3-32 & 3-
First calculate the load removal at 1.1 in/hour RG-348 Page 3-30 Equation 3.4: Q = CiA C = runoff coefficient for the drainage area = i = design rainfall intensity = A = drainage area in acres = Q = flow rate in cubic feet per second = RG-348 Page 3-31 Equation 3.5: V _{OR} = Q/A Q = Runoff rate calculated above = A = Water surface area in the wet vault = V _{OR} = Overflow Rate = #DIV/0! feet/sec V _{OR} = Overflow Rate = #DIV/0! feet/sec Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = Load removed by Wet Vault = #VALUE! lbs	Required Load Removal Based upon Equation 3.3 =	NA	lbs	
RG-348 Page 3-30 Equation 3.4: Q = CiA C = runoff coefficient for the drainage area = i = design rainfall intensity = A = drainage area in acres = 0.35 C = Runoff Coefficient = 0.546 (IC) ² + 0.328 Q = flow rate in cubic feet per second = Q = flow rate in cubic feet per second = 0.00 cubic feet/sec 0.00 cubic feet/sec RG-348 Page 3-31 Equation 3.5: V _{OR} = Q/A 0.00 cubic feet/sec Q = Runoff rate calculated above = A = Water surface area in the wet vault = V _{OR} = Overflow Rate = #DIV/0! feet/sec 0.00 cubic feet/sec Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent 0 percent Load removed by Wet Vault = #VALUE! Ibs	First calculate the load removal at 1.1 in/hour			
$C = runoff coefficient for the drainage area = i = design rainfall intensity = A = drainage area in acres = 0.35$ $C = Runoff Coefficient = 0.546 (IC)^2 + 0.328$ $1.1 in/hour$ $0 acres$ $Q = flow rate in cubic feet per second = 0.00 cubic feet/sec$ $RG-348 Page 3-31 Equation 3.5: V_{OR} = Q/A$ $Q = Runoff rate calculated above = 0.00 cubic feet/sec$ $A = Water surface area in the wet vault = 0 square feet$ $V_{OR} = Overflow Rate = \#DIV/0! feet/sec$ Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent $Load removed by Wet Vault = \#VALUE! lbs$	RG-348 Page 3-30 Equation 3.4: Q = CiA	L.		
Q = flow rate in cubic feet per second = $0.00 \text{ cubic feet/sec}$ RG-348 Page 3-31 Equation 3.5: $V_{OR} = Q/A$ Q = Runoff rate calculated above = $0.00 \text{ cubic feet/sec}$ A = Water surface area in the wet vault =0 square feet $V_{OR} = Overflow Rate =$ #DIV/0!feet/secPercent TSS Removal from Figure 3-1 (RG-348 Page 3-31) =0 percentLoad removed by Wet Vault =#VALUE!Ibs	C = runoff coefficient for the drainage area = i = design rainfall intensity = A = drainage area in acres =	0.3 1.	5 1 in/hour) acres	C = Runoff Coefficient = 0.546 (IC) ² + 0.328
RG-348 Page 3-31 Equation 3.5: $V_{OR} = Q/A$ Q = Runoff rate calculated above = A = Water surface area in the wet vault =0.00 cubic feet/sec 0 square feet $V_{OR} = Overflow Rate =$ #DIV/0! #DIV/0!feet/secPercent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = Load removed by Wet Vault =0 percent	Q = flow rate in cubic feet per second =	.0.0) cubic feet/se	ec
Q = Runoff rate calculated above = 0.00 cubic feet/sec A = Water surface area in the wet vault = 0 square feet V _{OR} = Overflow Rate = #DIV/0! feet/sec Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent Load removed by Wet Vault = #VALUE!	RG-348 Page 3-31 Equation 3.5: V _{OR} = Q/A			
V _{OR} = Overflow Rate = #DIV/0! feet/sec Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent Load removed by Wet Vault = #VALUE! lbs	Q = Runoff rate calculated above = A = Water surface area in the wet vault =	. 0.0) cubic feet/se) square feet	ec
Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) = 0 percent Load removed by Wet Vault = #VALUE! Ibs	V _{OR} = Overflow Rate =	#DIV/0!	feet/sec	
Load removed by Wet Vault = #VALUE! Ibs	Percent TSS Removal from Figure 3-1 (RG-348 Page 3-31) =) percent	
	Load removed by Wet Vault =	#VALUE!	lbs	
if a bypass occurs at a rainfail intensity of less than 1.1 in/nours Calculate the efficiency reduction for the actual rainfall intensity rate	If a bypass occurs at a rainfall intensity of less than 1.1 in/hours Calculate the efficiency reduction for the actual rainfall intensity rate			
Actual Rainfall Intensity at which Wet Vault bypass Occurs = 0 in/hour	Actual Rainfall Intensity at which Wet Vault bypass Occurs =	:) in/hour	
Fraction of rainfall treated from Figure 3-2 RG-348 Page 3-32 =0percentEfficiency Reduction for Actual Rainfall Intensity =0.00 percent	Fraction of rainfall treated from Figure 3-2 RG-348 Page 3-32 = Efficiency Reduction for Actual Rainfall Intensity =	= 0.0) percent) percent	
Resultant TSS Load removed by Wet Vault = #VALUE! Ibs	Resultant TSS Load removed by Wet Vault =	#VALUE!	lbs	
18. Permeable Concrete Designed as Required in RG-348 Pages 3-79 to 3-83	18. Permeable Concrete	Designed as I	Required in R	G-348 Pages 3-79 to 3-83
PERMEABLE CONCRETE MAY ONLY BE USED ON THE CONTRIBUTING ZONE	PERMEABLE CONCRETE MAY ONLY BE USED ON THE CONTRIBUTING 2	ZONE		
19. BMPs Installed in a Series Designed as Required in RG-348 Pages 3-32	<u>19. BMPs Installed in a Series</u>	Designed as I	Required in R	G-348 Pages 3-32
Michael E. Barrett, Ph.D P.E. recommended that the coefficient for E ₂ be changed from 0.5 to 0.65 on May 3, 2006	Michael E. Barrett, Ph.D., P.E. recommended that the coeff	icient for E ₂ b	e changed fro	om 0.5 to 0.65 on May 3, 2006
$E_{TOT} = [1 - ((1 - E_1) X (1 - 0.65E_2) x (1 - 0.25E_3))] X 100 = 0.00 \text{ percent}$ NET EFFICIENCY OF THE BMPs IN THE SE	E _{TOT} = [1 - ((1 - E ₁) X (1 - 0.65E ₂) x (1 - 0.25E ₃))] X 100 =	0.0) percent	NET EFFICIENCY OF THE BMPs IN THE SE
EFFICIENCY OF FIRST BMP IN THE SERIES = $E_1 = 0.00$ percent	EFFICIENCY OF FIRST BMP IN THE SERIES = E_1 =	0.0) percent	
EFFICIENCY OF THE SECOND BMP IN THE SERIES = $E_2 = 0.00$ percent	EFFICIENCY OF THE SECOND BMP IN THE SERIES = E_2 =	0.0) percent	
EFFICIENCY OF THE THIRD BMP IN THE SERIES = $E_3 = 0.00$ percent	EFFICIENCY OF THE THIRD BMP IN THE SERIES = E_3 =	0.0) percent	
THEREFORE, THE NET LOAD REMOVAL WOULD BE: $(A_1 \text{ AND } A_P \text{ VALUES ARE FROM SECTION 3 ABOVE})$	THEREFORE, THE NET LOAD REMOVAL WOULD BE: (A _I AND A _P VALUES ARE FROM SECTION 3 ABOVE)			

 $L_R = E_{TOT} X P X (A_1 X 34.6 X A_P X 0.54) = 0.00$ lbs

20. Stormceptor

		Required TSS Removal in BMP Drainage Area=	NA	lbs
		Impervious Cover Overtreatment=	0.0000	ac
		TSS Removal for Uncaptured Area =	0.00	lbs
	BMP Sizing			
		Effective Area =	NA	EA
		Calculated Model Size(s) =	#N/A	
	Actual Mo	odel Size (if multiple values provided in Calculated		
	Mode	Size or if you are choosing a larger model size) =	0	Model Size
		Surface Area =	#N/A	ft ²
		Overflow Rate =	#VALUE!	Vor
		Rounded Overflow Rate =	#\/ALLIE!	Var
		BMP Efficiency % =	#\/ALUE!	%
		L _o Value =	#\/ALLIE!	lhe
		$\underline{-}_{R}$ tand	<i>"viiccc</i> .	105
		TSS Load Credit =	#VALUE!	lbs
	Is Sufficient	Freatment Available? (TSS Credit <u>></u> TSS Uncapt.)	#VALUE!	
		TSS Treatment by BMP (LM + TSS Uncapt.) =	#VALUE!	
21 Vortoch				
ZI. VOILECH		Required TSS Removal in BMP Drainage Area=	NA	lbs
		Impervious Cover Overtreatment=	0.0000	ac
		TSS Removal for Uncaptured Area =	0.00	lbs
	BMP Sizing			
		Effective Area =	NA	EA
		Calculated Model Size(s) =	#N/A	
	A	ctual Model Size (if choosing larger model size) =	Vx1000	Pick Model Size

Surface Area =

Rounded Overflow Rate = #VALUE!

TSS Load Credit =

Is Sufficient Treatment Available? (TSS Credit
> TSS Uncapt.)

TSS Treatment by BMP (LM + TSS Uncapt.) =

BMP Efficiency % = #VALUE!

L_R Value =

7.10

#VALUE!

#VALUE!

#VALUE!

#VALUE!

Overflow Rate = #VALUE! V_{or}

 ft^2

 $V_{\rm or}$

%

lbs

lbs

Attachment N- Inspection, Maintenance, Repair and Retrofit Plan

Attachment N: Inspection, Maintenance, Repair, Retrofit Plan

Batch Detention Pond:

Pest Management:

An Integrated Pest Management Plan should be developed for vegetated areas. This plan should specify how problem insects and weeds will be controlled with minimal or no use of insecticides and herbicides. It should also address the maintaining of proper drainage for the site through the batch detention ponds.

Seasonal Mowing and Lawn Care:

The basin, basin side-slopes and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas.

Inspection and Maintenance/Repair:

Inspections should take place a minimum of twice a year. Once inspection should take place during wet weather to determine if the basin is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. The remaining inspections should occur between storm event so that manual operation of the valve and controller can be verified. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. The outlet structure and the trash screen should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet as described in previous sections. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately. In addition, electrical control system should be included in the inspection schedule. If the valve is damaged or not functioning to achieve the required drawdown time, then the valve should be repaired.

Debris and Litter Removal:

Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for the possible clogging or obstructions and any debris removed.

Sediment Removal:

Sediment accumulating near culverts and in channels needs to be removed when they build up to 3 inches at any spot. Excess sediment should be removed by hand or with flat-bottomed shovels. If areas are eroded, they should be filled, compacted to final grade. Sediment removal should be performed periodically, as determined through inspection.

Public Education:

The delegation of maintenance responsibilities is for the landowner. However, localities should provide an active educational program to encourage the recommended practices. Landscapers for the site will also need to be educated on the suitable practices for lawn up keep throughout the year with limited amount of the pesticides or fertilizer.

Detention Pond/BMP Records

Ī	Type of Inspection: Comments:	Date:			
	Signature:	(Inspector)			
1	Maintenance Work Performed: Comments:	Date:			
	Signature:	(Maintenance Personnel)			
(Other Comments:	Date:			
	Signature:	(Title:)			

Responsibility of Maintenance

Shawn Beichler Print Name

> Director of Land Development & Construction Title – Owner/President/Other

A-A-A Storage FM 1826 Corporation/Partnership/Entity Name

Agree to assume the responsibility of maintaining the permanent BMPs constructed as part of the Pecan Park Bulverde development in accordance with the rules and regulations of the Texas Commission on Environmental Quality (TCEQ).

I also understand that:

- 1. I am responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- 2. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools and other sites where regulated activities occur.

have Boichlon

Applicant's Signature

Contact Person: Shawn Beichler Entity: A-A-A Storage FM 1826 Mailing Address: 4203 Spinnaker Cove City, State, Zip: Austin, TX 78731 Telephone: (704) 754-3200

Date

Attachment P- Measures for Minimizing Surface Stream Contamination

Attachment P: Measures for Minimizing Surface Stream Contamination

Upon approval of this plan, the Batch Detention Ponds, traditionally designed, will be constructed before the proposed A-A-A FM 1826 Phase 3 and 4 development starts. Therefore, any storm water run off leaving the site will be treated per TCEQ RG-348, and no surface steam contamination is anticipated.

Temporary Stormwater

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Ross Corder, PE

Date: <u>10-04-2024</u>

Signature of Customer/Agent:

Roos Cont

Regulated Entity Name: A-A-A Storage FM 1826

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.
Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2. Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

- For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>Bear Creek</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. X Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

		 A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or
8.		The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
		 Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.		Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	\square	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
		 For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided. For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used. For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be used in combination with other erosion and sediment controls within each disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

- 11. Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
 - 🛛 N/A
- 12. Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. 🖂 Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. \square All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



Attachment A- Spill Response Actions

Attachment A: Spill Response Actions

Contractors working onsite with materials which could potentially cause pollution shall implement the following measures to prevent stormwater pollution.

Education of Employees or Subcontractors Who Handle Materials Which Can Cause Pollution

- Employees should know what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when a spill must be reported to the TCEQ. Information is available in 30 TAC 327.4 and 40 CFR 302.4.
- Educate employees and subcontractors on the potential dangers to humans and the environment from spills and leaks, and provide training in spill prevention and cleanup. Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- Establish a continuing education program to indoctrinate new employees, who will use or handle potential pollutants.
- Provide for a superintendent or representative to oversee and enforce proper spill prevention and control measures.

General Measures

- To the extent that work can be accomplished safely, spills of oil, petroleum products, and substances listed under 40 CFR part 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and waste in covered containers and protect from vandalism.
- Place spill cleanup materials where it will be readily accessible.
- Spills should be covered and protected from stormwater runoff during rainfall to the extent that it doesn't compromise clean-up activities.
- Do not bury spills onsite.
- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMP"s.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- Contain contaminated water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.



• Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function

<u>Cleanup</u>

- Clean up leaks and spills immediately, or as soon as it is safely practical.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent materials for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly.

Minor Spills

- Minor spills such as small quantities of oil, gasoline, paint, etc, should be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
 - Contain the spread of the spill.
 - Recover spilled materials.
 - Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills may also be controlled by the first responder along with the aid of other personnel such as labors and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately, or as soon as safely practical

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other materials to prevent contaminating runoff.



Significant/Hazardous Spills

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- For spills of federal reportable quantities, in conformance with the requirements in 40CFR parts 110, 119 and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report. The services of a spill contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staff have arrived at the job site.
- Other agencies which may need to be contacted include, but are not limited to, City, Police Department, County Sheriff Office, Fire Departments, etc.

Vehicle and Equipment Maintenance

- If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runoff of stormwater and the runoff of spills.
- Regularly inspect onsite vehicles and equipment for leaks and repair immediately. Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles onsite.
- Always use secondary containment, such as drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- Place drip pans or absorbent materials under paving equipment when not in use.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Remove the absorbent materials promptly and dispose of properly.
- Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil recycled. As the oil supplier or recycler about recycling oil filters.
- Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat as if it cracked. Put into the containment area until you are sure it is not leaking.
- If fueling must occur on site, used designated areas, located away from drainage courses, to prevent the runoff of stormwater and the runoff of spills.
- Discourage "topping off" on fuel tanks.
- Always use secondary containment, such as drain pan, when fueling to catch spill/leaks.





Attachment B- Potential Sources of Contamination

Attachment B: Potential Sources of Contamination

Asphalt products used on this project

- Preventative measures
 - After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of forecasted rain.

Oil, grease fuel and hydrocarbon fluid contamination from construction equipment and vehicle drippings.

- Preventative measures
 - Vehicle maintenance, when possible, will be performed within the construction staging area.
 - Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.

Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.

- Preventative measures
 - Contractor to incorporate regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.
 - Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.
 - Hazardous material and waste shall be stored in covered containers and protected from vandalism.
 - A stockpile of spill cleanup materials shall be stored on site where it will be readily available.



Miscellaneous trash and litter from construction workers and material wrappings.

- Preventative measures
 - Trash containers will be placed throughout the site to encourage proper trash disposal.

Construction Debris

- Preventative measures
 - Construction debris will be monitored daily by the site contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case-by-case basis.

Spills/ Overflow of waste from portable toilets

- Preventative measures
 - Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
 - Portable toilets will be placed on a level ground surface.
 - Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.





Attachment C- Sequence of Major Construction Activities

Attachment C: Sequence of Major Construction Activities

The sequence of major construction activities that will disturb earth/soil of the proposed site will be completed in two stages. Initially, the site will cleared, and grubbed of existing vegetation to prepare for the proposed site plan. This stage will include installation of temporary erosion controls. Temporary controls include temporary construction entrance, silt fence, and concrete washout pit. The second stage will include the construction of buildings, parking, drives, utilities, Batch Detention Ponds, landscaping, and site cleanup. Once the site is fully stabilized with vegetation back in place, the temporary erosion controls may be removed. Both stages will disturb approximately 13.0 acres of land.





Attachment D- Temporary Best Management Practices and Measures

Attachment D: Temporary Best Management Practices and Measures

7a A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

Upgradient flows are intercepted by two channels. One channel routes upgradient storm water flows to Pond 1 and will be treated by the proposed Batch Detention Basin. The northern channel diverts upgradient flows around the northern edge of the site, and discharges into the TxDOT ROW. The proposed onsite batch detention ponds is sized to treat all onsite flows and contributing up gradient flows and impervious cover.

7b A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off-site, including pollution caused by contaminated stormwater runoff from the site.

Site preparations will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include:

- Erection of silt fence along downgradient boundary of construction activities for temporary erosion and sedimentation controls.
- Installation of stabilized construction entrance/exits to reduce the dispersion of sediment from the site.
- Installation of concrete truck washout.
- Installation of construction staging areas.

7c A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

Temporary measures are intended to provide a method of controlling and slowing the flow of runoff from the construction site. By utilizing silt fence staged down gradient and along flow paths, will allow sediment and suspended solids to settle out of stormwater flows and be captured onsite. By containing the sediment and suspended solids within the site, they will not enter the aquifer, surface streams and/or sensitive features that may exist downstream of the site.



7d A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. The BMPs are providing settlement of suspended solids and containment onsite, but stormwater flows will continue on their natural drainage path. Features discovered during construction will be reported and assessed in accordance with applicable regulations.





Attachment F- Structural Practices

Attachment F: Structural Practices

The structural practices listed below are shown on the Erosion Control Plans and are listed on Attachment D of the Temporary Controls Section of the CZP.

- A stabilized construction entrance with washout pit will be constructed at all locations where vehicular traffic enters and leaves the site. This will reduce sediments which leave the site and are tracked or fall onto adjacent roadways. Currently there are two proposed stabilized construction entrance locations.
- A concrete truck washout will be located next to the south stabilized construction entrance to prevent pollutants to stormwater from concrete waste.
- Silt fencing will be installed adjacent to any drainage way which receives sheet flow from upgradient-disturbed areas and along the side slope perimeter of disturbed areas.
- Sandbags filled with washed pea gravel will be used at storm drainage inlets prior to stabilization of the drainage areas.





Attachment G-Drainage Area Map

		2/ ~			
	Sha	Son S			
			\sim		
	\sim		~~~~{<		
Leff for the second sec	2 ~				
All and a f	$\int \int $	ξ	\sim) } } } ^ک ^م ر
			\sum		
			< st	\sim	
		$\left\{ \right\} > \left\{ \right\}$		-	The second second
		S A FLOW	SHEET /100'@		" A the second second
			1.8% 004.3		and the second s
	SHALLOW C FLOW 761' @	ONC. 3.9%		U Laurente Laurente	
				survey and the second	LOT 14 APPALOOSA RU
		APPAROS RUN (67/79)		APP2/505A RUN (67/79)	(67/79)
			and have have been been been been been been been be		Liz
		Contraction of the second seco			jers j
				x,, x,	7002 7003
EDA 3				966	
		STR. C	in the second se	- Martine	y y y
			$\frac{1}{2}$	2 S SI	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
	IS AC				
983.8 984. (1789/00)				erennen and a factor of the second se	
987. CHANNEL				~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
FLOW 235' → @ 1.4%				è c	
		15 E E E E E			
				$\sum_{i=1}^{n}$	
	2 mm	AP1: 985.5			<pre></pre>
Proposed Time of Concentration (min): 21.4 Lag Time (min): 1 Elevation (ft) Length Length Length	2.9 *Minimum Initial T _c (min): etted XS Incremental meter Area Slope Time of	5 Cumulative			
Segment Condition (ft) Start End n (ft/s) fd/s 1 Sheet 100.0 1086.0 1081.7 0.240 N 2 Shall. Conc. 2376.0 1081.7 985.5 N 3 Channel or Sewer 0.0 0.0 0.0 0.0	ft) (sq. ft.) (ft/ft) Travel (min) I/A N/A 0.0430 9.2370 I/A N/A 0.0405 12.1976 0.0000 0.0000 0.0000	Travel (min)* 9.2370 21.4346 21.4346	Phy 182	6 Contraction	
Drainage Area Name: EDA 2 Proposed Time of Concentration (min): 21.8 Lag Time (min): 1	3.1 *Minimum Initial T _c (min):	5			
LengthElevation (ft)ManningsWeSegmentCondition(ft)StartEndn(ft/s)1Sheet100.01081.01074.00.240N	Atteal XS Incremental meter Area Slope Time of (ft) (sq. ft.) (ft/ft) Travel (min) I/A N/A 0.0700 7.6011	Cumulative Time of Travel (min)* 7.6011		, , , , , , , , , , , , , , , , , , ,	
2 Shall. Conc. 2367.0 1074.0 987.1 N 3 Channel or Sewer 235.0 987.1 983.8 0.040 20 Drainage Area Name: EDA 3	I/A N/A 0.0367 12.7609 0.00 10.00 0.0140 1.4085	20.3620 21.7705			
Proposed Time of Concentration (min): 17.1 Lag Time (min): 1 Elevation (ft) Mannings Velocity Peri (ft) Start End Day (ft)	*Minimum Initial T _c (min): etted XS Incremental meter Area Slope Time of (t) (cg. ft.) (ft/ft) Time(min)	5 Cumulative Time of Travel (min)*			
Segment Condition (II) Start End II (IUs) II 1 Sheet 100.0 1006.1 1004.3 0.240 N 2 Shall. Conc. 761.0 1004.3 975.0 N 3 Channel or Sewer 0.0 975.0 0.0 N	It/A N/A 0.0180 13.0861 I/A N/A 0.0385 4.0062 I/A N/A 0.0000 0.0000	13.0861 17.0923 17.0923	,		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
COMPOSITE CURVE NUMBER		SUMMARY T	ABLE	` <	
DESCRIPTIONAREACNResidential District, Average lot size 2-ac, 12% IC49.582Open space, Good condition11.4780		Flow (cfs) 10 yr 25 yr 100 yr			
Paved parking lots, roof, driveway, etc. 0 98 Total 60.97 82 Drainage Area Name: EDA 2	EDA 1 AP 1 142.7 EDA 2 AP 2 23.6	266.2 350.3 486.6 44.3 58.4 81.2 10.1 35.4 81.2			
DESCRIPTIONAREACNResidential District, Average lot size 2-ac, 12% IC5.782Open space, Good condition4.3380Description bits5.11	EDA 3 AP 3 10.2 	עד איז			
Paved parking lots, roof, driveway, etc. 0.1 98 Total 10.13 81 Drainage Area Name: EDA 3					
DESCRIPTIONAREACNResidential District, Average lot size 2-ac, 12% IC0.9682Open space, Good condition2.8280Paved parking lots, roof, driveway, etc.0.1798	_				

Copyright Hill Country Civil, LLC October 4, 2024

Total 3.95 81



Civil - ZHill Country (Engineers • Consultant 1042 Northpark Ridge, New Braun Phone: 817-659-9078 or 210-www.hillcountrycivil.c SCALE: 1"=100' LEGEND PROPERTY BOUNDARY ____ _ _ _ LOT LINE P _____ SETBACK LINE LANDSCAPE BUFFER LINE EASEMENT LINE $\mathbf{\mathbf{+}}$ SITE BENCHMARK PROPERTY CORNER GAS GASLINE OVERHEAD ELECTRIC LINE FENCE LINE \bigcirc EXISTING TREE . Incal _0_ SIGN ____ POWER POLE X FIRE LANE ROSS T. CORDER 125401 TIME OF CONCENTRATION CENSE DRAINAGE AREA BOUNDARY / DA # ` DRAINAGE AREA LABEL ACRES
 No
 APPALOOSA RUN STORAGE FACILITY PH. 3 & 4 12100 RM 1826 AUSTIN, TEXAS 78737 ш C 4 CAUTION! STING DRAINA AREA MAP CONTRACTOR SHALL EXERCISE CAUTION DURING DEMOLITION, EXCAVATION, CLEARING AND CONSTRUCTION ACTIVITIES NEAR OVERHEAD ELECTRIC LINES. CONTRACTOR SHALL COMPLY WITH ALL SAFETY REGULATIONS WHEN OPERATING NEAR POWER LINES. EXIS⁻ TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR, SUB-CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE, OR STRUCTURAL/GEOTECHNICAL/SAFETY EQUIPMENT CONSULTANT, SHALL REVIEW THESE PLANS AND GEOTECHNICAL REPORT, THE INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION PLAN, SYSTEMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE SHEET NO. TRENCH SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM OSHA STANDARDS, SPECIFICALLY, CONTRACTOR AND/OR RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH 24 SAFETY PLAN IN ACCORDANCE WITH OSHA

OF 35

REGULATIONS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND/OR AROUND THE EXPOSED TRENCH EXCAVATION.

	La S S		
		mas 2	
Land of			
All cr ~		$\sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i=1}^{n} \sum_{j=1}^{n} \sum_{i$	
			S Company and S
		5HEET FLOW	
		1004.3	
	SHALLOW CONC. FLOW		
	334'@ 2.6% UNPAVED	CHANNEL FLOW	s LOT 14 APPALOOS RUN
	рит. то со		.5 .5
984.7	CONC. FLOW 362' @ 3.0% PAVED	SHA SHA IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII	ALLOW NC. FLOW '@ 1.4% >
		PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A PDA 1A	ED TRE-100.00 X - 200-00 X - 100-00 X -
PDA 3	ROUTING ODA2 307'		
3.96 AC	999 CHA 190'	© 2.5%	
		994	
PDA 2 PDA 2 PD		991.0	
	SHEET FLOW 100' @ 1.8% 990.0		PDA1
986 986 989 989 989	988.2,		
986.9 CHANNEL FLOW 204' @ 1.5% FLOW	90 LLOW CONC.		
	AVED		
TIME OF CONCENTRATIO	ON 985.5 AP 1		
Drainage Area Name: ODA 1 Proposed Time of Concentration (min): 22.6 Lag Elevation (ft)	Time (min): 13.5 <i>*Minimum Initial T_c (min):</i> Wetted XS Incremental	5 Cumulative	
Segment Condition Length (ft) Start End Ma 1 Sheet 100.0 1086.0 1081.7 0 2 Shall. Conc. 1688.0 1081.7 1001.0	Innings Velocity Perimeter (ft/s) Area (ft) Slope (gq, ft.) Time of (ft/ft) Travel (min) 2.240 N/A N/A 0.0430 9.2370 N/A N/A 0.0478 7.9747	Time of Travel (min)* 9.2370 17.2117	
3 Channel or Sewer 960.0 1001.0 985.5 0 Drainage Area Name: ODA 1A Proposed Time of Concentration (min): 16.0 Lag	20.040 20.00 10.00 0.0161 5.3660	22.5777 CHANNEL / FLOW 960' @ 1.6%	
Segment Condition (ft) Start End	*Minimum Initial T _c (min): Metted XS Incremental Innings Velocity Perimeter Area Slope Time of n (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min)	5 Cumulative Time of Travel (min)*	
1 Sheet 100.0 1087.0 1083.0 0 2 Shall. Conc. 1492.0 1083.0 999.0 3 Channel or Sewer 999.0 999.0	N/A N/A 0.0400 9.5081 N/A N/A 0.0563 6.4954 0.0000 0.0000 0.0000	9.5081 16.0035 16.0035 Drainage Area Name:	
Drainage Area Name: ODA 2 Proposed Time of Concentration (min): 16.8 Lag Elevation (ft) Elevation (ft)	Time (min): 10.1 <i>*Minimum Initial T_c (min):</i> Wetted XS Incremental	DESCRIPTION Residential District, Average lot size 2-ac, 12% IC 5 Open space, Good condition Paved parking lots, roof, driveway, etc.	AREA CN 44.5 82 2.62 80 0.21 98
Segment Condition Length (ft) Start End Ma 1 Sheet 100.0 1081.0 1074.0 0 2 Shall. Conc. 1598.0 1074.0 998.5	Innings Velocity Perimeter Area Slope Time of n (ft/s) (ft) (gq. ft.) (ft/ft) Travel (min) 1 0.240 N/A N/A 0.0700 7.6011 1 0.240 N/A N/A 0.0472 7.5943 1	Time of Travel (min)* 7.6011 15.1954 Drainage Area Name: DESCRIPTION Description	ODA 1A
3 Channel or Sewer 289.0 998.5 993.8 0 Drainage Area Name: PDA 1 Proposed Time of Concentration (min): 8.7 Lag	1.040 20.00 10.00 0.0163 1.6096 Time (min): 5.2 *Minimum Lag Time (min): *Minimum Initial T(min):	16.8050 Open space, Good condition Paved parking lots, roof, driveway, etc.	0.23 80 0 98 Fotal 7.29 82
Segment Condition (ft) Length Ma Segment Condition (ft) Start End	Innings Velocity Perimeter Area Slope Time of (ft/s) (ft/s) (sq. ft.) (ft/ft) Travel (min)	Cumulative Time of Travel (min)* 1 7341 Open space. Good condition	ODA 2 AREA CN 10.81 82 0.41 80
1 100.0 1004.9 1003.8 0 2 Shall. Conc. 573.0 1003.8 995.4 3 Shall. Conc. 279.0 992.4 990.0	N/A N/A 0.0110 1.7341 N/A N/A 0.0147 3.8801 0.0086 3.1074	5.6142 Paved parking lots, roof, driveway, etc. 8.7215 Drainage Area Name:	0 98 Total 11.22 82 PDA 1
Proposed Time of Concentration (min): 14.5 Lag	Time (min): 8.7 *Minimum Initial T _c (min): Wetted XS Incremental Incremental	DESCRIPTION 5 Residential District, Average lot size 2-ac, 12% IC 5 Open space, Good condition Cumulative Paved parking lots, roof, driveway, etc.	AREA CN 0 82 3.45 80 7.4 98
Segment Condition (ft) Start End 1 Sheet 100.0 990.0 988.2 0 2 Shall. Conc. 36.0 988.2 986.9 3 Channel or Sewer 204.0 096.0 092.0 0	n (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min) 0.240 N/A N/A 0.0180 13.0861 N/A N/A 0.0361 0.1957 0.040 20.00 10.00 0.0152 1.1754	Drainage Area Name: 13.2818 14.4571	Ottal 10.85 92 MUNUFF PDA 2 Rainfall Runoff - S Rainfall Runoff - S
Drainage Area Name: PDA 3 Proposed Time of Concentration (min): 15.6	<u></u>	Kesigential District, Average lot size 2-ac, 12% IC Open space, Good condition	0 82 <u>E</u> 0.71 80 <u>E</u> 0.94 98 <u>E</u> 2 yr
	Time (min): 9.4 *Minimum Initial T_(min):	Paved parking lots, roof, driveway, etc.	iotal 1.65 90
Segment Condition (ft) Elevation (ft) 1 Sheet 100.0 1000.4 400.40 0	Best Stress Stress innings Velocity Vetted XS Incremental innings Velocity Perimeter Area Slope Time of innings (ft/s) (ft) (sq. ft.) (ft/ft) Travel (min)	5 Cumulative Time of Travel (min)* Residential District, Average lot size 2-ac, 12% IC Open space Good condition	otal 1.65 90 E PDA 3 ODA 1 110.0 AREA CN ODA 2 29.7 0.91 82 PDA 1 W/ POND 24.6 0.99 %0 COULT 10.0

Copyright Hill Country Civil, LLC October 4, 2024



 259.1
 344.6
 484.8

 9.8
 12.3
 16.5

 17.7
 24.3
 33.3



ACTIVITY (ON OR OFFSITE) FOR THE PROJECT.



Attachment I- Inspection and Maintenance for BMPs

Attachment I: Inspection and Maintenance for BMPs

The following list of items outlines and dictates Inspection and Maintenance for BMPs practices. Inspection and maintenance guidelines come from TCEQ RG-348.

In addition to these measures the contractor will be subject to the provisions of the TCEQ General Permit Number TXR 150000 relating to discharges from construction activities.

Temporary Construction Entrance/Exit

- 1. The entrance should be maintained in a condition which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repairs and/or cleanout of any measures used to trap sediment.
- 2. All sediment spilled, dropped, washed, or tracked onto public rights-of-way should be removed immediately by contractor.
- 3. When necessary, wheels should be cleaned to remove sediment prior to entrance on to public right-of-way.
- 4. When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin
- 5. All sediment should be prevented from entering any storm drain, ditch, or water course by using approved methods.

Silt Fence

- 1. Inspect all fencing weekly, and after any rainfall.
- 2. Remove sediment when buildup reaches 6 inches.
- 3. Replace any torn fabric or install a second line of fencing parallel to the torn section.
- 4. Replace or repair any sections crushed or collapsed during construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot to where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
- 5. When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

Inlet Protection Barrier

- 1. Inspections should be made weekly and after each rainfall. Repair or replacement should be made promptly as needed by the contractor.
- 2. Remove sediment when buildup reaches a depth of 3 inches. Removed sediment should be deposited in a suitable area and in such a manner that it will not erode.
- 3. Check placement of devices to prevent gaps between device and curb.
- 4. Inspect filter fabric and patch or replace if torn or missing.
- 5. Structures should be removed, and the area stabilized only after the remaining drainage area has been properly stabilized.





Attachment J- Schedule of Interim and Permanent Soil Stabilization Practices

Attachment J: Schedule of Interim and Permanent Soil Stabilization Practices

Onsite construction activities shall be conducted in accordance with the Erosion Control Plan for the project which includes the provisions of the TPDES General Permit TXR150000.

Interim on-site stabilization measures will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest duration and maximizing the use of natural vegetation. All disturbed soil will be stabilized as per project specifications in accordance with of TCEQ Technical Guidance Manual RG-348 (2005).

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site has temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of the site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is preclude by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

Interim Stabilization Measures will include one or more of the following methods.

- 1. Temporary Vegetation
- 2. Installation of blankets or matting material
- 3. Hydraulic Mulch
- 4. Sod

The interim and permanent stabilization will be installed in accordance with the standard specifications for the county or city having jurisdiction over the project, whichever is more stringent. If the governing entity does not have specifications for these items, the work shall be completed in compliance with the procedures and specifications outlined in the current Technical Guidance Manual published by the TCEQ.

Permanent Stabilization measures will include one or more of the following methods.

- 1. Permanent Vegetation including landscape planting with trees, shrubs, or ground cover.
- 2. Installation of blankets or matting material
- 3. Hydromulch
- 4. Grass Sodding
- 5. Rock or concrete riprap

A copy of the Erosion Control Plan is attached.





Agent Authorization

Agent Authorization Form For Required Signature Edwards Aguifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Shawn Beichler

Print Name

Director of Land Development & Construction

Title - Owner/President/Other A-A-A STORAGE FM1826 LLC

of

Corporation/Partnership/Entity Name

have authorized

Ross Corder, PE Print Name of Agent/Engineer

of Hill Country Civil Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- Application fees are due and payable at the time the application is submitted. The 3. application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

icant's Signature

5.2.24

Date

THE STATE OF NC §

County of Iredul §

BEFORE ME, the undersigned authority, on this day personally appeared <u>Shown Beichlucknown</u> to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this $\underline{\mathcal{A}}$ day of Typed or Printed Name of Notary

MY COMMISSION EXPIRES: My Commission Expires





Application Fee Form

Application Fee Form

Texas Commission on Environmental Quality								
Name of Proposed Regulated Entity: A-A-A Storage FM	<u>1826</u>							
Regulated Entity Location: 12100 Ranch to MarketRd 1	<u>326 Austin, TX 78737</u>							
Name of Customer: <u>A-A-A STORAGE FM1826 LLC</u>								
Contact Person: Shawn Beichler Pho	one: <u>(704754-3200</u>							
Customer Reference Number (if issued):CN								
Regulated Entity Reference Number (if issued):RN	_							
Austin Regional Office (3373)								
🗌 Hays 🛛 🖾 Travis	🗌 Wil	liamson						
San Antonio Regional Office (3362)								
🗌 Bexar 👘 Medina	Uva	alde						
Comal Kinney								
Application fees must be paid by check, certified check	or money order, payable	e to the Texas						
Commission on Environmental Quality . Your canceled	check will serve as your	receipt. This						
form must be submitted with your fee payment. This	, payment is being submit	ted to:						
Austin Regional Office								
Mailed to: TCEQ - Cashier	Overnight Delivery to: T	vernight Delivery to: TCEQ - Cashier						
Revenues Section	12100 Park 35 Circle	2100 Park 35 Circle						
Mail Code 214	uilding A, 3rd Floor							
P.O. Box 13088	Austin, TX 78753	ustin, TX 78753						
Austin, TX 78711-3088	(512)239-0357							
Site Location (Check All That Apply):								
Recharge Zone Contributing Zon	e 🗌 Transit	ion Zone						
Type of Plan	Size	Fee Due						
Water Pollution Abatement Plan, Contributing Zone								
Plan: One Single Family Residential Dwelling	Acres	\$						
Water Pollution Abatement Plan, Contributing Zone								
Plan: Multiple Single Family Residential and Parks	Acres	\$						
Water Pollution Abatement Plan, Contributing Zone								
Plan: Non-residential	11.747 Acres	\$ 6 <i>,</i> 500						
Sewage Collection System	L.F.	\$						
Lift Stations without sewer lines	Acres	\$						
Underground or Aboveground Storage Tank Facility	Tanks	\$						
Piping System(s)(only)	Each	\$						
Exception	Each	\$						
Extension of Time	Each	\$						

Signature: Shawn Beichler

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	< 1	\$3,000
institutional, multi-family residential, schools, and	1 < 5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



TCEQ Core Data Form



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)								
New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)								
Renewal (Core Data Form should be submitted with the renewal form) Other								
2. Customer Reference Number (if issued)	Follow this link to search	3. Regulated Entity Reference Number (if issued)						
CN 605766427	Central Registry**	RN 111012910						

SECTION II: Customer Information

4. General Customer Information 5. Effective Date for Custom					ustome	er Information Updates (mm/dd/yyyy) 5/3/2024			5/3/2024		
New Custor	Image:										
The Custome	r Name sı	ıbmitted here ı	nay be updated au	tomaticall	ly base	don	what is c	urrent and active	with th	e Texas Seci	retary of State
(SOS) or Texa	s Comptro	oller of Public A	Accounts (CPA).								
6. Customer	Legal Nam	ne (If an individu	al, print last name first	: eg: Doe, J	ohn)			<u>If new Customer, o</u>	enter pre	vious Custom	er below:
A-A-A STORAGI	E FM1826 L	LC									
7. TX SOS/CP	A Filing N	umber	8. TX State Ta	ax ID (11 d	igits)			9. Federal Tax I	D	10. DUNS	Number (if
0803127642			32068499139					(9 digits)		applicable)	
							83-4562896				
11. Type of Customer: Corporation Individual Partnership: S General Limited							eral 🗌 Limited				
Government:	City 🗌 🤇	County 🗌 Feder	al 🗌 Local 🔲 State [Other			Sole Pr	roprietorship	🗌 Otł	ner:	
12. Number of	12. Number of Employees 13. Independently Owned and Operated?										
⊠ 0-20 □ 2	21-100	101-250	251-500 🗌 501 a	nd higher				🛛 Yes	🗌 No		
14. Customer	Role (Pro	posed or Actual)	– as it relates to the R	egulated Er	ntity liste	ed on t	this form. I	Please check one of	the follo	wing	
Owner	Owner Operator Owner & Operator Occupational Licensee Responsible Party VCP/BSA Applicant										
4203 Spinnaker Cove											
Addross											
Address.	City	Austin		State	ТХ		ZIP	78731		ZIP + 4	
16. Country N	Mailing In	formation (if ou	tside USA)			17.	E-Mail Ac	ddress (if applicabl	e)		·
						Shawn.beichler@aaastorage.com					

18. Telephone Number	19. Extension or Code	20. Fax Number (if applicable)
(704) 754-3200		() -

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)								
New Regulated Entity	New Regulated Entity 🔲 Update to Regulated Entity Name 🛛 Update to Regulated Entity Information							
The Pequilated Entity Nar	no cubmittor	I may be undeted i	n order to may		o Data Sta	ndards (romova	d of organization	al andinas such
The Regulated Entity Nat	ne submittet	i may be apaalea, i	n order to mee		e Dulu Slu	indurus (removu	n oj organization	ui enuings such
as Inc, LP, or LLC).								
22. Regulated Entity Nam	ne (Enter name	of the site where the	reaulated action	is takina pla	ce.)			
- 3	- ,	·, · · · · · · · · · · · · · · · · · ·	- j	51	,			
A-A-A STORAGE FM1826 LLC								
23 Street Address of	2 Street Address of 12100 FM 1826							
25. Sileet Address Di								
the Regulated Entity:	<i>f</i> :							
<u>(No PO Boxes)</u>	City	Austin	Stata	ту	710	70727	710 1 4	
	City	Austin	Sidle	1.	216	10151	218 + 4	
							I	
24. County	Travis							
-								

If no Street Address is provided, fields 25-28 are required.

25. Description to	Storage Faci	lity							
26 Noarost City						State		Noa	roct 7ID Codo
20. Nearest City						State		ivea	rest ZIP Code
Austin		ТХ		78737					
Latitude/Longitude are r used to supply coordinat	equired and es where no	may be added/u ne have been pro	pdated to meet T vided or to gain d	CEQ Core D accuracy).	ata Stando	ards. (Geoc	oding of th	e Physical	Address may be
27. Latitude (N) In Decim	al:			28. Lo	28. Longitude (W) In Decimal:				
Degrees	Minutes	Se	econds	Degree	es	M	nutes		Seconds
29. Primary SIC Code	30.	Secondary SIC Co	de	31. Primar	y NAICS Co	ode	32. Seco	ndary NAI	CS Code
(4 digits)	(4 di	(4 digits) (5 or 6 digits)				(5 or 6 digits)			
4226				236220					
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)									
Storage Facility									
	4203 Spinnaker CV								
34. Mailing									
Address:									
	City	Austin	State	тх	ZIP	78731		ZIP + 4	
35. E-Mail Address:	shav	wn.beichler@aaasto	orage.com	•		_			
36. Telephone Number		:	37. Extension or (Code	38. F	ax Numbe	r (if applicab	ole)	
(704) 754-3200				() -				

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

🔄 Dam Safety	Districts	🔀 Edwards Aquifer	Emissions Inventory Air	Industrial Hazardous Waste
	New Source			
Municipal Solid Waste	Review Air		Petroleum Storage Tank	L] PWS
	Neview All			
Gludge				
Voluntary Cleanup	Wastewater	Wastewater Agriculture	Water Rights	Other:

SECTION IV: Preparer Information

40. Name:	Kortnie Thoma	S		41. Title:	Project Coordinator
42. Telephone Number 43. Ext./Code 44. Fax Number		44. Fax Number	45. E-Mail Address		
(210) 378-4953			() -	kortnie@hillo	countrycivil.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	AAA Storage Co. Job Title:			Director of Land Development & Construction			
Name (In Print):	Shawn Beichler	Phone:	(704) 754- 3200				
Signature:	Shawn Beichler			Date:	5/1/2024		