

Owner Authorization Form

Edwards Aquifer Protection Program

C

Instructions

Complete the following form by adding the requested information in the fields below. The form must be notarized for it to be considered complete. Attach it to other programmatic submittals required by 30 Texas Administrative Code (30 TAC), Chapter 213, and provide it to TCEQ's Edwards Aquifer Protection Program (EAPP) as part of your application.

If you have questions on how to fill out this form or about EAPP, please contact us by phone at 512-339-2929 or by e-mail at eapp@tceq.texas.gov.

Landowner Authorization

I, Michael Valenzuela of Marielle Land Group LLC

am the Manager of the owner of the property located at:

Marielle Subdivision Lot 1A, Block A

and am duly authorized in accordance with 30 TAC 213.4(c)(2) and 213.4(d)(1), or 30 TAC 213.23(c)(2) and 213.23(d), relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize Zach Summers, Vice President of Land Acquisition of Mill Creek Residential Trust

To conduct development of multi-family units and associated site, utility, and pond improvements.

At 13220 Morris Road, Austin, Texas 78729

Landowner Acknowledgement

I understand that Marielle Land Group LLC

Is ultimately responsible for the compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation and subject to administrative rule or orders and penalties as provided under 30 TAC 213.10, relating to enforcement. Such violations may also be subject to civil penalties.

| Landowner Signature |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Michael Valenzuela, Manager, Marielle Land Group LLC 2-26-25 |
| Date |
| THE STATE § OF State Texas County § of County Travis |
| BEFORE ME, the undersigned authority, on this day personally appeared Michael Valenzvela |
| known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed. GIVEN under my hand and seal of office on this Day day of Month |
| #/26330111 (ID) |
| NOTARY PUBLIC CECILIA GUNN |
| Cecilia Sunt (Notary Signature) MY COMMISSION EXPIRES: Date 3/5/2028 Notary ID #126330111 My Commission Expires March 5, 2028 |
| System states of system states |
| Optional Attachments |
| Select All that apply: |
| ☐ Lease Agreement |
| □ Signed Contract |
| □ Deed Restricted Easement |
| ☐ Other legally binding documents |

WATER POLLUTION ABATEMENT PLAN & ORGANIZED SEWAGE COLLECTION SYSTEM PLAN

MORRIS ROAD RESIDENTIAL AUSTIN, WILLIAMSON COUNTY, TEXAS

Prepared For:

MCRT SFR INVESTMENT, LLC

5910 N. Central Expressway, Suite 1100 Dallas, TX 75206

Prepared By:

KIMLEY-HORN AND ASSOCIATES, INC.

10814 Jollyville Road Avallon IV Suite 200 Austin, Texas 78759 (512) 418-1771

Firm No. 928 KHA Project No. 064487031

December 10, 2024

Table of Contents

| EDWARDS AQUIFER APPLICATION COVER PAGE | |
|-----------------------------------------------------------------------------|--------------|
| GENERAL INFORMATION | Section 2 |
| General Information Form | TCEQ-0587 |
| Road Map | Attachment A |
| USGS / Edwards Recharge Zone Map | Attachment B |
| Project Description | Attachment C |
| GEOLOĞIC ASSESSMENT | Section 3 |
| Geologic Assessment Form | |
| Geologic Assessment Table | |
| Soil Profile and Narrative of Soil Units | Attachment B |
| Stratigraphic Column | |
| Narrative of Site Specific Geology | Attachment D |
| WATER POLLUTION ABATEMENT PLAN | Section 4 |
| Water Pollution Abatement Plan Application Form | |
| Factors Affecting Water Quality | |
| Volume and Character of Storm Water | Attachment C |
| Suitability Letter from Authorized Agent | |
| TEMPORARY STORMWATER | |
| Temporary Stormwater Form | |
| Spill Response Actions | |
| Potential Sources of Contamination | |
| Sequence of Major Activities. | |
| Temporary Best Management Practices and Measures | |
| Request to Temporarily Seal a Feature | |
| Structural Practices | |
| Drainage Area Map | |
| Temporary Sediment Pond(s) Plans and Calculations | |
| Inspection and Maintenance for BMPs | |
| Schedule of Interim and Permanent Soil Stabilization Practices | Attachment I |
| PERMANENT STORMWATER | |
| Permanent Stormwater Form | |
| | |
| 20% or Less Impervious Cover Waiver | |
| BMPs for Upgradient Stormwater | |
| BMPs for On-site Stormwater | |
| BMPs for Surface Streams | |
| Request to Seal Features | |
| Construction Plans | |
| Inspection, Maintenance, Repair and Retrofit Plan | |
| Pilot-Scale Field Testing Plan | |
| Measures for Minimizing Surface Stream Contamination | Attachment I |
| ORGANIZED SEWAGE COLLECTION SYSTEM PLAN | |
| Organized Sewage Collection System Plan Application Form | |
| Engineering Design Report | Attachment A |
| Justification and Calculations for Deviation in Straight Alignment Manholes | |
| Justification of Variance for Manhole Spacing | |
| Exception of Slopes for Flows Greater Than 10.0 FPS | |
| ADDITIONAL FORMS | |
| Agent Authorization Form | |
| Application Fee Form | TCEQ-0574 |
| Check Payable to the "Texas Commission on Environmental Quality" | |
| Core Data Form | |
| EXHIBITS | |
| Civil Design Plan Set | Exhibit 1 |



SECTION 1: EDWARDS AQUIFER APPLICATION COVER PAGE

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.

- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or if not withdrawn the application will be denied and the application fee will be forfeited.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available to you:

- You can withdraw your application, and your fees will be refunded or credited for a resubmittal.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the effected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

| 1. Regulated Entity Name: MCRT SFR TEXAS CONSTRUCTI LLC | | | | | | | 2. Re | gulated Enti | ty No.: |
|---------------------------------------------------------|--------------------|------|-------------------|-------|------------------------------|---------|------------------|----------------------------------|-------------------------------|
| 3. Customer Name: Zach Summers | | | | | 4. Customer No.: CN605974344 | | | | |
| 5. Project Type: (Please circle/check one) | ⊠ New Modification | | Extension | | Exception | | | | |
| 6. Plan Type: (Please circle/check one) | ⊠ WPAP | CZP | ⊠scs | UST | AST | EXP | EXT | Technical Clarification | Optional Enhanced Measures |
| 7. Land Use: (Please circle/check one) | □Residen | tial | Non-residential | | | | 8. Site (acres): | | 7.913 |
| 9. Application Fee: | \$5,650 | | 10. Permanent BMI | | | P(s): | | Partial Sedimentation/Filtration | |
| 11. SCS (Linear Ft.): | 137 | | 12. AST/ | No. T | anks) | s): N/A | | | |
| 13. County: | Williamson | n | 14. Wate | l: | | | Lake Creek | | |

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

| Austin Region | | | | | | | |
|-----------------------------------------|--------------------------------------------------------------------------------|-----------------------------------------------------------------------------|----------------------------------------------------------------------------------------------|--|--|--|--|
| County: | Hays | Travis | Williamson | | | | |
| Original (1 req.) | _ | _ | <u>X</u> | | | | |
| Region (1 req.) | _ | _ | _X_ | | | | |
| County(ies) | _ | | _ <u>X</u> _ | | | | |
| Groundwater Conservation District(s) | Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek | Barton Springs/ Edwards Aquifer | NA | | | | |
| City(ies) Jurisdiction | AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek | AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills | X Austin Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock | | | | |

| San Antonio Region | | | | | | |
|--------------------------------------------|----------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|--------|------------------------------|---------------|--|
| County: | Bexar | Comal | Kinney | Medina | Uvalde | |
| Original (1 req.) | _ | | | | | |
| Region (1 req.) | _ | _ | _ | | | |
| County(ies) | _ | | | | | |
| Groundwater Conservation District(s) | Edwards Aquifer Authority Trinity-Glen Rose | Edwards Aquifer Authority | Kinney | EAA Medina | EAA Uvalde | |
| City(ies) Jurisdiction | Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park | Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz | NA | San Antonio ETJ (SAWS) | NA | |

| I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review. | | | | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|--|--|--|--|
| Jose M. Farias, P.E. | 7- | | | | |
| Print Name of Customer/Authorized Agent | | | | | |
| | 2-20-25 | | | | |
| Signature of Customer/Authorized Agent | Date | | | | |
| | | | | | |

| **FOR TCEQ INTERNAL USE ONLY** | | | | |
|--------------------------------------------------|---------------------------------|--|--|--|
| Date(s)Reviewed: | Date Administratively Complete: | | | |
| Received From: | Correct Number of Copies: | | | |
| Received By: | Distribution Date: | | | |
| EAPP File Number: | Complex: | | | |
| Admin. Review(s) (No.): | No. AR Rounds: | | | |
| Delinquent Fees (Y/N): | Review Time Spent: | | | |
| Lat./Long. Verified: | SOS Customer Verification: | | | |
| Agent Authorization Complete/Notarized (Y/N): | Payable to TCEQ (Y/N): | | | |
| Core Data Form Complete (Y/N): | Check: Signed (Y/N): | | | |
| Core Data Form Incomplete Nos.: | Less than 90 days old (Y/N): | | | |



SECTION 2: GENERAL INFORMATION

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

was prepared by:
Print Name of Customer/Agent: <u>Jose M. Farias, P.E.</u>

Date: 12/10/2025

Signature of Customer/Agent:

ga 7-

| Pı | roject Information | |
|----|-------------------------------------------------------------|-------------------|
| 1. | Regulated Entity Name: MCRT SFR TEXAS CONSTRU | JCTION LLC |
| 2. | County: Williamson | |
| 3. | Stream Basin: <u>Lake Creek</u> | |
| 4. | Groundwater Conservation District (If applicable): <u>I</u> | N/A |
| 5. | Edwards Aquifer Zone: | |
| | Recharge Zone Transition Zone | |
| 6. | Plan Type: | |
| | ⋈PAP | AST |
| | ⊠ scs | UST |
| | Modification | Exception Request |

| 7. | Customer (Applicant): | |
|-----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| | Contact Person: Zach Summers Entity: MCRT SFR Investment, LLC Mailing Address: 5910 N. Central Expressway, Suite City, State: Dallas, TX Telephone: 210.885.4676 Email Address: zsummers@mcrtrust.com | <u>e 1100</u> Zip: <u>75206</u> Fax: <u>N/A</u> |
| 3. | Agent/Representative (If any): | |
| | Contact Person: <u>Jose M. Farias</u> , <u>P.E.</u> Entity: <u>Kimley-Horn & Associates</u> Mailing Address: <u>10814 Jollyville Road</u> , <u>Avallon IV</u> , City, State: <u>Austin, Texas</u> Telephone: <u>737-249-0434</u> Email Address: <u>joe.farias@kimley-horn.com</u> | <u>Suite 200</u> Zip: <u>78759</u> Fax: <u>N/A</u> |
| Э. | Project Location: | |
| | ☐ The project site is located inside the city limits of the project site is located outside the city limits jurisdiction) of the city of ☐ The project site is not located within any city's | s but inside the ETJ (extra-territorial |
| 10. | The location of the project site is described believed and clarity so that the TCEQ's Regional st boundaries for a field investigation. | |
| | 13220 Morris Road, Austin, Texas north of And | derson Mill Road |
| | Legal Descriptions: | |
| | MARIELLE SUB (BLLK A LTS 1A & 2A), BLOCK A | , Lot 1A, ACRES 7.913 |
| 11. | Attachment A – Road Map. A road map showi project site is attached. The project location and the map. | |
| 12. | Attachment B - USGS / Edwards Recharge Zon USGS Quadrangle Map (Scale: 1" = 2000') of the The map(s) clearly show: | |
| | ☑ Project site boundaries. ☑ USGS Quadrangle Name(s). ☑ Boundaries of the Recharge Zone (and Tran ☑ Drainage path from the project site to the boundaries. | |
| 13. | The TCEQ must be able to inspect the project so Sufficient survey staking is provided on the pro | |

| | the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment. |
|---------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| \boxtimes s | Survey staking will be completed by this date: 01/9/2025 |
| r | Attachment C – Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details: |
| | Area of the site Offsite areas Impervious cover Permanent BMP(s) Proposed site use Site history Previous development Area(s) to be demolished |
| 15. Exist | ting project site conditions are noted below: |
| | Existing commercial site Existing industrial site Existing residential site Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Uncleared) Other: |
| Prohi | ibited Activities |
| | am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project: |
| (| Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control); |
| (| 2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3; |
| (| 3) Land disposal of Class I wastes, as defined in 30 TAC §335.1; |
| (| 4) The use of sewage holding tanks as parts of organized collection systems; and |
| (| 5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities). |
| (| 6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading. |
| | am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project: |


- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

| 18. Th | e fee for the plan(s) is based on: |
|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur. For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines. For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems. A request for an exception to any substantive portion of the regulations related to the protection of water quality. A request for an extension to a previously approved plan. |
| 19. | Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's: |
| | ☐ TCEQ cashier ☐ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties) ☐ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties) |
| 20. | Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regiona office. |
| 21. 🔀 | No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director. |

Attachment A Road Map





DIRECTIONS FROM TCEQ HEADQUARTERS TO PROJECT SITE


- GET ON I-35 N FROM S I-35 FRONTAGE ROAD AND N INTERSTATE 35 FRONTAGE ROAD
- 2. FOLLOW I-35 N TO N INTERSTATE 35
- FRONTAGE ROAD IN GEORGETOWN
- TAKE EXIST 253 FROM I-35 N
 DRIVE TO CHISHOLM TRAIL ROAD

Morris Road Residential Road Map

Austin, Texas December 2024



Attachment B USGS/Edwards Recharge Zone Map



Morris Road Residential USGS Quadrangle Map

Austin, Texas December 2024



Project Description

Introduction

The subject property containing the Project is located west of IH-35, bordered by Anderson Mill Road to the south and Morris Road to the east in Austin, Texas. This Project will include an overall ± 7.91 -acre tract with a new multifamily development.

This project is located within the Lake Creek Watershed. The proposed site is not located in the Federal Emergency Management Agency's 100-year floodplain according to the FEMA FIRM map 48491C0610F.

The entire ± 7.91 -acre tract is located within the Edwards Aquifer Recharge Zone. There are no known environmental or geological features located on-site.

Legal Description

The legal description of the subject tract is as follows: MARIELLE SUB (BLLK A LTS 1A & 2A), BLOCK A, Lot 1A, ACRES 7.913

Land Use

The existing Marielle Land Group tract is mostly undeveloped land with two single story buildings that are set to be removed.

Existing Drainage Conditions

The existing site has two drainage areas. The runoff from the existing site is currently not treated. The existing drainage generally flows east to west across the site. The total existing impervious cover is 1.47 acres.

Proposed Development

The proposed Marielle Land Group Property development includes 143 residential units. The total building coverage of the residential units is 109,300 square feet. The water quality BMP's account for 60% impervious cover for pond A and 57% impervious cover for pond B.

Proposed Drainage Conditions

Runoff from this development will be collected by inlet structures placed along the driving aisles and routed through proposed storm pipes to two on-site water quality ponds. Water will eventually discharge from the pond to the existing drainage system. Detention will be designed such that peak flows for the 2-,10-,25-,50- and 100-year storm events do not increase from existing to proposed conditions.

Detention and Water Quality

The entire Project is located within the Edwards Aquifer Recharge Zone. Subsequently, water quality requirements set forth by the Texas Commission on Environmental Quality (TCEQ) will need to be met. Best managements practices (BMPs) used include a partial sedimentation and filtration basin.

Erosion and Sedimentation Controls

Temporary erosion and sedimentation controls during construction are proposed on the Erosion Control Plan and include silt fences, inlet protection, and a stabilized construction entrance designed to City of Austin criteria. The land disturbed during construction will drain into the proposed on-site storm sewer system where it will be conveyed to the proposed water quality ponds located on-site.



SECTION 3: GEOLOGIC ASSESSMENT

Geologic Assessment TCEQ-0585

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

| | nt Name of Geologist: <u>Chad M. Copeland,</u> | Telephone: <u>512-335-1785x124</u> |
|-----------------|--------------------------------------------------------------------------------|---------------------------------------------|
| <u>PG</u> Da | te: 08/02/2022 | Fax: <u>512-335-0527</u> |
| | presenting: Ranger Environmental Services, LLC PG or TBPE registration number) | (TBPG Firm #50140) (Name of Company and |
| | nature of Geologist: My Marielle gulated Entity Name: Marielle | CHAD M. COPELAND SOIL SCIENCE OF 102 (2022) |
| | roject Information | SOIL SCIENCE 08/02/2022 |
| 1. | Date(s) Geologic Assessment was performed: 7 | <u>/20/2022</u> |
| 2. | Type of Project: | |
| 3. | WPAP SCS Location of Project: | ☐ AST ☐ UST |
| | Recharge Zone Transition Zone Contributing Zone within the Transition Zone | e |

| 4. | | | ologic Assessmen Table) is attached. | | Complete | d Geol | ogic Asses | sment Table |
|------|---------------------------------|-----------------------------------------|-----------------------------------------------------------------------------------------------|-----------|-----------------------------------|----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
| 5. | Hydrolog 55, Appe | ic Soil Gro ndix A, So | roject site is summ ups* (Urban Hydr il Conservation Se ow each soil type | ology for | or Small W 986). If the | atersh ere is r | eds, Techr nore than | nical Release No. one soil type on |
| | ble 1 - Soil l aracteristics | • | | | Soil Na | ime | Group* | Thickness(feet) |
| s 6. | members top of the | s, and thic | greater than 6.67' ratigraphic Colum knesses is attache phic column. Oth | d. The c | A. B. C. D. atigraphic outcroppin | Soils I rate v Soils I infiltr wette Soils I rate v Soils I infiltr wette column | having a having a mation rate having a si when thoro having a viation rate having a figure sention rate having a viation rate having a viation rate having a showing a figure sention rate having a showing a showing a figure sention rate having a showing a figure sention rate having a figure sention rate h | when thoroughly Iow infiltration oughly wetted. ery slow when thoroughly formations, , should be at the |
| 7. | Attachmo including potential | ent C – Sit any featu for fluid r | e Geology. A narrance identified in the flower to the flower state of the flower is attached. | ne Geolo | ogic Assess | sment ' | Table, a di | scussion of the |
| 8. | the appli | cant's Site | e Geologic Map(s Plan. The minimu | - | _ | - | must be t | the same scale as |
| | Site Geol | ogic Map | n Scale: 1" = <u>60</u> ' Scale: 1" = <u>60</u> ' e (if more than 1 s | oil type |): 1" = <u>~49</u> | <u>0</u> ' | | |
| 9. | Method of co | ollecting p | ositional data: | | | | | |
| | | _ | System (GPS) tech lease describe me | | data colle | ection: | | |

| 10. $igotimes$ The project site and boundaries are clearly shown and labeled on the Site Geologic N | √lap. |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
| 11. $igwidz$ Surface geologic units are shown and labeled on the Site Geologic Map. | |
| 12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table. | oed |
| \boxtimes Geologic or manmade features were not discovered on the project site during the figure investigation. | eld |
| 13. $igotimes$ The Recharge Zone boundary is shown and labeled, if appropriate. | |
| 14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section | on. |
| There are (#) wells present on the project site and the locations are shown an labeled. (Check all of the following that apply.) The wells are not in use and have been properly abandoned. The wells are not in use and will be properly abandoned. The wells are in use and comply with 16 TAC Chapter 76. There are no wells or test holes of any kind known to exist on the project site. | ıd |
| Administrative Information | |
| 15. $igotimes$ Submit one (1) original and one (1) copy of the application, plus additional copies as | |

needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A

Geological Assessment Table TCEQ-0585 Table

| GEOL | OGIC | ASSES | SMEN. | T TAE | BLE | | PR | OJE | CT NA | ME | <u>:</u> | Mariell | e | | | | | | | |
|------------|----------|-----------|-----------------|--------|-----------|-------------------|-----|------|--------|--------------------|--------------------|---------|----------------------------------|-------|------|----------|-----------------|------|----------------|-----------|
| L | OCATIO | ON | | | | FE/ | TUR | E CI | 1ARAC1 | ΈR | ISTICS | 3 | | | EVAL | LUAT | TION | PHY | SICAL | . SETTING |
| 1A | 1B * | 1C* | 2A | 2B | 3 | 4 | | | 5 | 5A | 6 | 7 | 7 8A 8B | | 9 | 10 | | 11 | | 12 |
| FEATURE ID | LATITUDE | LONGITUDE | FEATURE TYPE | POINTS | FORMATION | DIMENSIONS (FEET) | | | | DENSITY (NO/FT) | APERTURE (FEET) | INFILL | RELATIVE INFILTRATION RATE | TOTAL | SENS | SITIVITY | CATCHMI (ACI | | TOPOGRAPHY | |
| | | | | | | Х | Υ | Z | | 10 | | | | | | <40 | <u>>40</u> | <1.6 | <u>>1.6</u> | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| No geo | ogic fea | tures obs | erved | ļ | | | | | | | | ! | | ļ | | ! | | | l | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | - | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | <u> </u> | <u> </u> | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |

* DATUM WGS84

| 2A TYPE | TYPE | 2B POINTS |
|---------|-------------------------------------|-----------|
| С | Cave | 30 |
| sc | Solution cavity | 20 |
| SF | Solution-enlarged fracture(s) | 20 |
| F | Fault | 20 |
| 0 | Other natural bedrock features | 5 |
| MB | Manmade feature in bedrock | 30 |
| SW | Swallow hole | 30 |
| SH | Sinkhole | 20 |
| CD | Non-karst closed depression | 5 |
| Z | Zone, clustered or aligned features | 30 |

| | 8A INFILLING |
|----|-----------------------------------------------------------------------|
| N | None, exposed bedrock |
| С | Coarse - cobbles, breakdown, sand, gravel |
| 0 | Loose or soft mud or soil, organics, leaves, sticks, dark colors |
| F | Fines, compacted clay-rich sediment, soil profile, gray or red colors |
| V | Vegetation. Give details in narrative description |
| FS | Flowstone, cements, cave deposits |
| Χ | Other materials |
| | |
| | 12 TOPOGRAPHY |

12 TOPOGRAPHY
Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field.

signature of tifies that I am qualified as a geologist as defin

Sheet ____1 of ___1

TCEQ-0585-Table (Rev. 10-01-04)

CHAD M. COPELAND SOIL SCIENCE 12668


OB/02/2022

ATTACHMENT B

Stratigraphic Column

Stratigraphic column of Cretaceous rocks of the northern segment of the Edwards aquifer, Austin region.







RANGER ENVIRONMENTAL SERVICES, INC.

Marielle

8600 Black Oak Street, Austin, Texas

RANGER REFERENCE 6568

*FIGURE ADAPTED AND EDITED BY RANGER ENVIRONMETAL SERVICES

*ORIGINAL SOURCE: Senger, R., Collins E., Kreitler C. (1990). Hydrology of the Northern Segment of the Edwards Aquifer, Austin Region. The University of Texas at Austin, Texas 78713. Bureau of Economic Geology.

ATTACHMENT C

Site Geology



GEOLOGIC ASSESSMENT
Marielle
8600 Black Oak Street
Austin, Texas
Williamson County
August 2022

INTRODUCTION

Ranger Environmental Services, Inc. (Ranger) was contracted to conduct a Geologic Assessment of the referenced property. This location lies within the designated Edwards Aquifer Recharge Zone. This subject site was noted to be mostly undeveloped with a driveway, shop and garage. Since the subject site is located over the Edwards Aquifer Recharge Zone, site development should adhere to the Texas Commission on Environmental Quality (TCEQ) Edwards Aquifer Protection Program Rules in accordance with Title 30 of the Texas Administrative Code, Section 213 (30 TAC§ 213).

PROJECT DESCRIPTION

The subject site consists of one approximate 2.999-acre lot, more or less, located at 8600 Black Oak Street, Austin, in Williamson County, Texas at approximately N 30.458034 and approximately W 97.769158.

The subject site is located within a mixed use area of residential and commercial properties.

METHODOLOGY

P.O. BOX 201179

This assessment follows general guidelines contained in Texas Commission on Environmental Quality (TCEQ) guidance "Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones" (TCEQ Guidance 0585). The site is located on an area of the recharge zone that may contain karst features within the outcropping limestone. Karst features may be expressed as surface features but more commonly tend to persist with depth.

A field geologic assessment was conducted by Chad M. Copeland, P.G. on July 20, 2022. The site is mostly undeveloped with a driveway, shop and garage.

The walking geologic survey was conducted on 50-foot center transects, where possible. No intrusive testing was conducted. If present, features identified in the field were photographed and recorded with a hand held global positioning system (GPS). Features include, but were not limited to, caves, solution cavities, solution-enlarged fractures, faults, manmade features in bedrock, swallow holes, sinkholes, non-karst closed depressions, and zone clustered or aligned features.

STATE OF TEXAS PROFESSIONAL GEOSCIENTIST FIRM NO. 50140 • STATE OF TEXAS PROFESSIONAL ENGINEERING FIRM NO. F-6160

The geologic assessment table, stratigraphic column, geologic, soils and topographic maps are included herein.

RESEARCH INFORMATION

Prior to conducting the geologic survey, Ranger conducted a review of existing geologic data and maps to prepare for the field survey. Reviewed references included, but are not limited to:

- Barnes, V.E. 1974. *Geologic Atlas of Texas, Austin Sheet*. The University of Texas at Austin, Bureau of Economic Geology.
- Senger, R.K., E.W. Collins and C.W. Kreitler. 1990. <u>Hydrogeology of the Northern</u> Segment of the Edwards Aquifer, Austin Region, Report of Investigations 192. The University of Texas at Austin, Bureau of Economic Geology.
- Texas Commission on Environmental Quality. 1999. <u>Complying with the Edwards Aquifer Rules: Administrative Guidance.</u>
- Texas Commission on Environmental Quality. Revised 2004. <u>Instructions to Geologist for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones.</u>
- Sellards, E.H., W.S. Adkins and F.B. Plummer. 1932. <u>The University of Texas Bulletin No. 3232</u>. The Geology of Texas. Volume 1, Stratigraphy.
- U.S. Department of Agriculture National Resources Conversation Services (www.nrcs.usda.gov).
- Texas Commission on Environmental Quality (www.tceq.state.tx.us).
- FEMA Flood Plain Maps.
- Center for Geospatial Technology, Texas Tech University, obtained from the Texas Geologic Atlas of Texas.
- USGS Topographic Maps Terrain Navigator Pro 2015.
- ESRI

SITE GEOLOGY

The subject site is underlain by Cretaceous sedimentary strata. In general, the Cretaceous strata dip regionally one degree towards the east-southeast. The area lies within the Balcones Fault Zone, a geologic province characterized in this region by north-northeast trending en echelon normal faults with the downthrown side most commonly to the east of the fault planes.

The Balcones Fault Zone trend closely follows the structural trend of the late Paleozoic Ouachita fold and thrust belt. Faulting may have been initiated in the Late Cretaceous with the majority of movement taking place during the late Oligocene and early Miocene. Minor isostatic adjustments resulting from sediment loading in the Gulf of Mexico continue to the present.

Referencing the Geologic Atlas of Texas, Austin Sheet, and The University of Texas Bulletin No. 3232, The Geology of Texas, Volume 1 the local stratigraphic units that outcrop at the site is the Edwards Limestone (Ked).

The Lower Cretaceous Edwards Limestone is a member of the Fredericksburg Group and is massive to thinly bedded limestones and dolostones. The Edwards Limestone is generally light gray, crystalline to coarse-grained, cavernous and includes calcareous shell detritus. Chert and rudistids are present within the Edwards Limestone and can serve as markers to differentiate the Edwards Limestone from the underlying Comanche Peak Formation and the unconformable and overlying Georgetown Formation.

In the Austin area, the Edwards Limestone has a maximum thickness of approximately 300 feet and thins to the north. Recharge to groundwater within the Edwards Limestone is primarily through precipitation. The regional groundwater system is characterized by varied porosity and permeability as associated with the vast solution cavities and fracture zones within the Edwards Limestone. Large amounts of groundwater can move from the recharge area through the local system in a short period of time.

No vugs, faults, or fractures were observed during the site geologic inspection. No outcropping was observed.

SITE SPECIFIC GEOLOGIC FEATURES

No geologic features, as defined in Texas Commission on Environmental Quality (TCEQ) guidance "Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones" (TCEQ Guidance 0585), were observed at the site.

SOIL DESCRIPTION

According to the U.S. Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS) *Web Soil Survey*, the soils located at the site are noted as Eckrant extremely stony clay (0-3% slopes) (EeB).

Please see attached USDA NRCS Custom Soil Resource Report.

TOPOGRAPHY AND DRAINAGE

The site is relatively flat with drainage flowing towards the east and south.

CONCLUSIONS AND RECOMMENDATIONS

Ranger Environmental Services, Inc. conducted a Geologic Assessment of the site in accordance with 30 TAC§ 213. Ranger concludes that no sensitive features as defined by the TCEQ (30 TAC§ 213) were observed at the site.

This assessment does not address the possible presence of subsurface conditions that may be exposed during future construction and/or development. Should solution features or conditions be exposed during site construction activities that indicate a potential for hydraulic interconnectedness between the surface and the Edwards Aquifer, operations in the vicinity of the feature should be halted and the Texas Commission on Environmental Quality (TCEQ) Edwards

Aquifer Protection Program should be contacted immediately in accordance with 30 TAC §213.5(f)(2).

LIMITATIONS

It should be noted that only areas readily accessible were inspected. There may be geologic features present that were not identified as part of this study. This non-intrusive visual field assessment cannot wholly eliminate the possibility of sensitive features at the site.

SOIL SCIENCE


Prepared by:


Chad M. Copeland, P.G.

CMGRIC

ATTACHMENT D

Site Geologic Map(s)





AIR RELEASE VALVE

BASKET BALL GOAL

© CABLE TV HANDHOLE

CABLE TV MARKER FLAG

COMMUNICATIONS MANHOLE

COMMUNICATIONS VAULT

ECTRIC METER

ECTRIC VAULT

FIBER OPTIC HANDHOLE

GAS BOX

GAS METER

GREASE TRAP

IRRIGATION VALVE

MARQUEE/BILLBOARI

CONCRETE MONUMENT FOUNI

EASEMENT LINE

SANITARY SEWER LINE

STORM DRAINAGE LINE

UNDERGROUND GAS LINE

OVERHEAD UTILITY LINE

UNDERGROUND CABLE LINE

UNDERGROUND ELECTRIC LINE

Copyright © 2021

Kimley-Horn and Associates, Inc

All rights reserved

BUILDING LINE

SIDEWALK

SURVEY LINE

CONCRETE PAVEMENT

ASPHALT PAVEMENT

-OHE

— CBL ·

-UGE

X X X FENCE

——— — FEMA FLOOD LINE

CAR AXLE FOUN

IRON PIPE FOUND

IRON ROD FOUND

PK NAIL FOUND

RSS RAILROAD SPIKE SET

P.O.B. POINT OF BEGINNING

WILLIAMSON COUNTY, TEXAS

OPRWC
OFFICIAL PUBLIC RECORDS OF

WILLIAMSON COUNTY, TEXAS

- RPRWC WALLIAMSON COUNTY, TEXAS

- RPRWC WALLIAMSON COUNTY, TEXAS

RAILROAD SPIKE FOU

"X" CUT IN CONCRETE FOUN
"X" CUT IN CONCRETE SET

140.50') PARENTHESIS INDICATES RECORD MEASUREMEN
DEED AND RECORDS OF

WILLIAMSON COUNTY, TEXAS

PK NAIL SET

COTTON SPINDLE FOUND

IRON ROD WITH CAP FOUN

1/2" IRON ROD W/ "KHA" CAP SET

MONITORING WEL

PARKING METER

PIPELINE HANDHOI

PIPELINE METER

PIPELINE MARKER FLAG

PIPELINE VALVE

RAILROAD HANDHOL

SANITARY SEWER CLEAN OU

RAILROAD SIGN

RAILROAD VAULT

PIPELINE MANHOLE

PIPELINE MARKER SIGN

PHONE BOOTH

P PIPELINE BOX

GAS HANDHOLE

AS MARKER FL

FIBER OPTIC MARKER SIGN

ECTRIC MANHOLE

LECTRIC MARKER FLA

CTRIC MARKER SIGN

COMMUNICATIONS MARKER FI

BEING A 4.913 ACRE (214,025 SQUARE FEET) TRACT OF LAND, CALLED TRACT 1, SITUATED IN THE M. M. HORNSBY SURVEY, ABSTRACT NO. 280, CITY OF AUSTIN, WILLIAMSON COUNTY, TÉXAS, AND BEING A PORTION OF LOT 1, BLOCK A OF THE VINEYARD CHRISTIAN FELLOWSHIP SUBDIVISION, AS SHOWN ON PLAT RECORDED IN DOCUMENT NO. 2008070951 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS; AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT A 1/2" IRON ROD FOUND IN THE EAST BOUNDARY LINE OF LOT 44 OF THE NORTHWEST WOODS SUBDIVISION, AS SHOWN ON PLAT RECORDED IN DOCUMENT NO. 1975000313 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS; AT THE SOUTHWEST CORNER OF A CALLED 11.47 ACRE TRACT OF AND DESCRIBED TO THE OPTIMIST CLUB OF TOWN AND COUNTY ROUND ROCK AS EVIDENCED IN DOCUMENT NO. 9554400 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS; FOR THE NORTHWEST CORNER OF SAID LOT 1 AND THE NORTHWEST CORNER OF THIS TRACT:

THENCE NORTH 68°54'43" EAST, 570.64 FEET ALONG THE COMMON BOUNDARY LINE OF SAID 11.47 ACRE TRACT AND SAID LOT 1, TO A POINT IN THE WESTERLY RIGHT-OF-WAY LINE OF MORRIS ROAD (VARIABLE WIDTH ROW). FOR THE NORTHEAST CORNER OF SAID LOT 1 AND THE NORTHEAST CORNER OF THIS TRACT: WHENCE A 1/2" IRON ROD WITH SURVEYOR'S CAP STAMPED "C-A INC RPLS 298-" FOUND FOR REFERENCE BEARS NORTH 68°54'43" EAST, 16.13 FEET;

THENCE. SOUTH $20^{\circ}07'27''$ EAST. ALONG THE WESTERLY RIGHT-OF-WAY LINE OF SAID MORRIS ROAD AND THE EAST BOUNDARY LINE OF SAID LOT 1. AT 0.86 FEET PASSING A 3/8" IRON ROD FOUND FOR A LINE MARKER. IN ALL A DISTANCE OF 547.83 FEET TO A 1/2" IRON ROD WITH PLASTIC SURVEYOR'S CAP STAMPED "KHA" SET FOR THE SOUTHEAST CORNER OF THIS TRACT: WHENCE A 1/2" IRON ROD FOUND FOR REFERENCE BEARS SOUTH 20°07'27" EAST. 302.72 FEET

THENCE SOUTH 68°52'43" WEST 301.06 FEET DEPARTING THE WESTERLY RIGHT-OF-WAY LINE OF SAID MORRIS ROAD, ACROSS SAID LOT 1. TO A 1/2" IRON ROD WITH PLASTIC SURVEYOR'S CAP STAMPED "KHA" SET IN THE EAST BOUNDARY LINE OF A LOT 2, BLOCK A OF SAID VINEYARD CHRISTIAN FELLOWSHIP SUBDIVISION AND A WEST BOUNDARY LINE OF SAID LOT 1, FOR THE SOUTHERLY SOUTHWEST CORNER OF THIS TRACT; WHENCE A 1/2" IRON ROD FOUND AT THE SOUTHEAST CORNER OF SAID LOT 2 BEARS SOUTH 20°14'32" EAST, 122.84 FEET

THENCE NORTH 20°14'32" WEST. 358.55 FEET ALONG THE COMMON BOUNDARY LINE OF SAID LOT 1 AND SAID LOT 2 TO A 1/2" IRON ROD WITH PLASTIC SURVEYOR'S CAP STAMPED "KHA" SET AT THE NORTHEAST CORNER OF SAID LOT 2, FOR AND INTERIOR CORNER OF SAID LOT 1 AND AN INTERIOR CORNER OF THIS TRACT; THENCE SOUTH 72°12'02" WEST, 268.70 FEET CONTINUING ALONG THE COMMON BOUNDARY LINE OF SAID LOT 1 AND SAID LOT 2 TO A 1/2" IRON ROD WITH PLASTIC SURVEYOR'S CAP STAMPED "KHA" SET IN A CUL-DE-SAC RIGHT-OF-WAY LINE OF BLACK OAK STREET (60' ROW WIDTH) AS SHOWN ON SAID NORTHWEST WOODS SUBDIVISION AND AT THE NORTHWEST CORNER OF SAID LOT 2, FOR THE NORTHERLY SOUTHWEST CORNER OF SAID LOT 1 AND THE NORTHERLY SOUTHWEST CORNER OF THIS TRACT

THENCE NORTH 20°13'52" WEST. ALONG THE COMMON BOUNDARY LINE OF SAID LOT 1 AND SAID NORTHWEST WOODS SUBDIVISION, AT 10.13 FEET PASSING A 1/2" RON ROD FOUND AT THE SOUTHEAST CORNER OF LOT 41 OF SAID NORTHWEST WOODS SUBDIVISION FOR A LINE MARKER, IN ALL A DISTANCE OF 174.02 FEET TO THE POINT OF BEGINNING AND CONTAINING 4.913 ACRES OF LAND, MORE OR LESS, IN WILLIAMSON COUNTY, TEXAS. THE BASIS OF BEARING FOR THIS DESCRIPTION IS THE TEXAS STATE PLANE COORDINATE SYSTEM GRID, CENTRAL ZONE (FIPS 4203) (NAD'83). ALL DISTANCES ARE ON THE SURFACE AND SHOWN IN U.S. SURVEY FEET. THIS DOCUMENT WAS PREPARED IN THE OFFICE OF KIMLEY-HORN AND ASSOCIATES, INC. IN AUSTIN, TEXAS.

BEING LOT 2, BLOCK A, VINEYARD CHRISTIAN FELLOWSHIP SUBDIVISION, AS PER MAP OR PLAT THEREOF RECORDED UNDER DOCUMENT NUMBER 2008070951, OFFICIAL PUBLIC RECORDS, WILLIAMSON COUNTY, TEXAS.

NOTES ADDRESSING SCHEDULE B EXCEPTIONS:

PURSUANT TO COMMITMENT FOR TITLE INSURANCE LISTED IN GENERAL NOTE 1.)

- THE FOLLOWING RESTRICTIVE COVENANTS OF RECORD ITEMIZED BELOW: CABINET FF, SLIDE 62, PAGE OF THE PLAT RECORDS OF WILLIAMSON COUNTY, TEXAS.
- THE FOLLOWING MATTERS AND ALL TERMS OF THE DOC.S CREATING OR OFFERING EVIDENCE OF THE MATTERS (WE MUST INSERT MATTERS OR DELETE THIS EXCEPTION.):
- a. RIGHTS OF PARTIES IN POSSESSION. (NOT A SURVEY MATTER)
- b. THE FOLLOWING EXCEPTION WILL APPEAR IN ANY POLICY ISSUED (OTHER THAT THE T-1R RESIDENTIAL OWNER POLICY OF TITLE INSURANCE AND THE T-2R SHORT-FORM RESIDENTIAL MORTGAGEE POLICY) IF THE COMPANY IS
- THAT WOULD BE DISCLOSED BY AN ACCURATE AND COMPLETE LAND SURVEY OF THE LAND.


ANY ENCROACHMENT, ENCUMBRANCE, VIOLATION, VARIATION, OR ADVERSE CIRCUMSTANCE AFFECTING THE TITLE

- NOTE: UPON RECEIPT OF A SURVEY ACCEPTABLE TO THE TITLE COMPANY, THIS EXCEPTION WILL BE DELETED. THE COMPANY RESERVES THE RIGHT TO EXCEPT ADDITIONAL ITEMS AND/OR MAKE ADDITIONAL REQUIREMENTS AFTER REVIEWING SAID SURVEY. (NOT A SURVEY MATTER)
- c. ELECTRIC AND TELECOMMUNICATIONS EASEMENT(S) 10 FEET IN WIDTH ALONG THE SOUTH, EAST AND WEST PROPERTY LINE(S), AS SHOWN BY THE RECORDED PLAT OF SAID SUBDIVISION. (SUBJECT TO, AS SHOWN)
- d. ELECTRIC DISTRIBUTION UTILITY EASEMENT GRANTED TO CITY OF AUSTIN, AS SET FORTH AND DESCRIBED BY INSTRUMENT FILED FOR RECORD UNDER WILLIAMSON COUNTY CLERK'S FILE NO.(S) 2009041127. (DOES NOT AFFECT)
- e. ANY PORTION OF THE SUBJECT PROPERTY LYING WITHIN THE BOUNDARIES OF A PUBLIC OR PRIVATE ROADWAY, WHETHER DEDICATED OR NOT. (DOES NOT AFFECT)
- ALL LEASES, GRANTS, EXCEPTIONS OR RESERVATIONS OF COAL, LIGNITE, OIL, GAS AND OTHER MINERALS, TOGETHER WITH ALL RIGHTS, PRIVILEGES, AND IMMUNITIES RELATING THERETO. APPEARING IN THE PUBLIC RECORDS WHETHER LISTED IN SCHEDULE B OR NOT. THERE MAY BE LEASES, GRANTS, EXCEPTIONS OR RESERVATIONS OF MINERAL INTEREST THAT ARE NOT LISTED. (NOT A SURVEY MATTER
- g. IF ANY PORTION OF THE PROPOSED LOAN AND/OR THE OWNER'S TITLE POLICY COVERAGE AMOUNT INCLUDES FUNDS FOR IMMEDIATELY CONTEMPLATED IMPROVEMENTS, THE FOLLOWING EXCEPTIONS WILL APPEAR IN SCHEDULE B OF ANY POLICY ISSUED AS INDICATED
- OWNER'S AND LOAN POLICY(IES): ANY AND ALL LIENS ARISING BY REASON OF UNPAID BILLS OR CLAIMS FOR WORK PERFORMED OR MATERIALS FURNISHED IN CONNECTION WITH IMPROVEMENTS PLACED, OR TO BE PLACED, UPON THE SUBJECT LAND, HOWEVER, THE COMPANY DOES INSURE THE INSURED AGAINST LOSS, IF ANY, SUSTAINED BY THE INSURED UNDER THIS POLICY IF SUCH LIENS HAVE BEEN FILED WITH THE COUNTY CLERK OF (COUNTY) COUNTY. TEXAS, PRIOR TO THE DATE HEREOF.
- OWNER'S POLICY(IES) ONLY: LIABILITY HEREUNDER AT THE DATE HEREOF IS LIMITED TO \$0.00. LIABILITY SHALL INCREASE AS CONTEMPLATED IMPROVEMENTS ARE MADE. SO THAT ANY LOSS PAYABLE HEREUNDER SHALL BE LIMITED TO SAID SUM PLUS THE AMOUNT ACTUALLY EXPENDED BY THE INSURED IN IMPROVEMENTS AT THE TIME THE LOSS OCCURS. ANY EXPENDITURES MADE FOR IMPROVEMENTS, SUBSEQUENT TO THE DATE OF THIS POLICY, WILL BE DEEMED MADE AS OF THE DATE OF THIS POLICY. IN NO EVENT SHALL THE LIABILITY OF THE COMPANY HEREUNDER EXCEED THE FACE AMOUNT OF THIS POLICY. (NOT A SURVEY MATTER)
- I. VARIANCE OF FENCE AND PROPERTY LINE(S) ALONG THE MOST SOUTHERLY WEST PROPERTY LINE(S), AS EVIDENCED BY SURVEY DATED JULY 21, 2020, PREPARED BY ZACHARY KEITH PETRUS, REGISTERED PROFESSIONAL LAND SURVEYOR NO. 6769, JOB NO. 069273503. (OWNER'S POLICY ONLY)

NOTES ADDRESSING SCHEDULE B EXCEPTIONS:

PURSUANT TO COMMITMENT FOR TITLE INSURANCE LISTED IN GENERAL NOTE 1.)

- THE FOLLOWING RESTRICTIVE COVENANTS OF RECORD ITEMIZED BELOW:
- CABINET FF, SLIDE 62, PAGE OF THE PLAT RECORDS OF WILLIAMSON COUNTY, TEXAS. (SUBJECT TO, AS SHOWN ON SURVEY)
- THE FOLLOWING MATTERS AND ALL TERMS OF THE DOCUMENTS CREATING OR OFFERING EVIDENCE OF THE MATTERS (WE MUST INSERT MATTERS OR DELETE THIS EXCEPTION.):
- a. RIGHTS OF PARTIES IN POSSESSION. (NOT A SURVEY MATTER)
- b. ALL VISIBLE AND APPARENT EASEMENTS OR USES AND ALL UNDERGROUND EASEMENTS OR USES, THE EXISTENCE OF WHICH MAY ARISE BY UNRECORDED GRANT OR BY USE. (SUBJECT TO)
- RIGHTS, IF ANY, OF THIRD PARTIES WITH RESPECT TO ANY PORTION OF THE SUBJECT PROPERTY LYING WITHIN THE BOUNDARIES OF A PUBLIC OR PRIVATE ROAD. (SUBJECT TO)
- d. ANY AND ALL MATTERS THAT WOULD BE SHOWN ON A CURRENT, CORRECT SURVEY OF THE PROPERTY.
- e. ALL LEASES, GRANTS, EXCEPTIONS, OR RESERVATIONS OF COAL, LIGNITE, OIL, GAS AND OTHER MINERALS, TOGETHER WITH ALL RIGHTS, PRIVILEGES AND IMMUNITIES RELATING THERETO, APPEARING IN THE PUBLIC RECORDS WHETHER LISTED IN SCHEDULE B OR NOT. THERE MAY BE LEASES, GRANTS, EXCEPTIONS, OR RESERVATIONS OF MINERAL INTEREST THAT ARE NOT LISTED. (NOT A SURVEY MATTER)
- DEFECTS, LIENS, ENCUMBRANCES, ADVERSE CLAIMS OR OTHER MATTERS, IF ANY, CREATED, FIRST APPEARING IN THE PUBLIC RECORDS OR ATTACHING SUBSEQUENT TO THE EFFECTIVE DATE HEREOF BUT PRIOR TO THE DATE THE PROPOSED INSURED ACQUIRES FOR VALUE OF RECORD THE ESTATE OR INTEREST OR MORTGAGE THEREON COVERED BY THIS COMMITMENT
- RESTRICTIONS, TERMS, PROVISIONS, CONDITIONS, EASEMENTS AND OTHER MATTERS SHOWN IN PLAT OF VINEYARD CHRISTIAN FELLOWSHIP AS RECORDED IN CABINET FF. SLIDES 62 AND 63. PLAT RECORDS OF WILLIAMSON COUNTY, TEXAS. (SUBJECT TO, AS SHOWN)



Map adapted by Ranger Env. Svcs.

GENERAL NOTES:

- 1. TITLE COMMITMENTS:
- TRACT 1: THIS SURVEY WAS PERFORMED UTILIZING THAT CERTAIN TITLE REPORT PREPARED BY WESTCOR LAND TITLE INSURANCE COMPANY, G.F. NO. 9991-20-6631 (ISSUE DATE: MAY 03, 2021, EFFECTIVE DATE: APRIL 27, 2021) AND REFLECTS ONLY THOSE EASEMENTS AND ENCUMBRANCES OF RECORD MENTIONED THEREIN. KIMLEY-HORN DID NOT ABSTRACT THE PUBLIC RECORDS. THE SURVEYED TRACT MAY BE SUBJECT TO ADDITIONAL GOVERNMENT REGULATIONS AND RESTRICTIONS PRIOR TO FURTHER SITE DEVELOPMENT.
- TRACT 2: THIS SURVEY WAS PERFORMED UTILIZING THAT CERTAIN TITLE REPORT PREPARED BY AGENTS NATIONAL TITLE INSURANCE COMPANY, G.F. NO. GF21144684 (ISSUE DATE: APRIL 30, 2021, EFFECTIVE DATE: APRIL 19, 2021) AND REFLECTS ONLY THOSE EASEMENTS AND ENCUMBRANCES OF RECORD MENTIONED THEREIN. KIMLEY-HORN DID NOT ABSTRACT THE PUBLIC RECORDS. THE SURVEYED TRACT MAY BE SUBJECT TO ADDITIONAL GOVERNMENT REGULATIONS AND RESTRICTIONS PRIOR TO FURTHER SITE DEVELOPMENT
- 2. ACCORDING TO COMMUNITY PANEL NO. 48491C0610F, EFFECTIVE DATE: DECEMBER 20, 2019, OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP (FIRM), THE SUBJECT TRACTS ARE LOCATED WITHIN ZONE "X" (UN-SHADED) WHICH IS DEFINED BY FEMA AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN." COMMONLY KNOWN AS THE 500-YEAR FLOODPLAIN. ZONE "X" (UN-SHADED) IS OUTSIDE OF ANY FEMA ESTABLISHED FLOOD HAZARD ZONE. ALL ZONE DELINEATIONS SHOWN HEREON ARE APPROXIMATE. THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY AND/OR THE STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN AND WILL OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOOD STATEMENT SHALL NOT CREATE ANY LIABILITY ON THE PART OF KIMLEY-HORN OR THE UNDERSIGNED.
- 3. THE BEARINGS, DISTANCES, AREAS AND COORDINATES SHOWN HEREON ARE TEXAS STATE COORDINATE SYSTEM GRID, CENTRAL ZONE (FIPS 4203) (NAD'83), AS DETERMINED BY THE GLOBAL POSITIONING SYSTEM (GPS). ALL DISTANCES SHOWN HEREON ARE ON THE GRID. THE UNIT OF LINEAR MEASUREMENT IS U.S. SURVEY FEET.
- 4. PER ALTA/NSPS SURVEY STANDARDS ITEM 5, SECTION C. PARAGRAPH III: THE TERM "ENCROACHMENT" IMPLIES A LEGAL OPINION. "EVIDENCE OF POTENTIALLY ENCROACHING STRUCTURAL APPURTENANCES AND PROJECTIONS OBSERVED IN THE PROCESS OF CONDUCTION FIELDWORK" RELATIVE TO TITLE LINES, SETBACKS, ADJOINING PROPERTIES, AND RIGHTS-OF-WAYS, WILL BE SHOWN, BUT THE SURVEY WILL MAKE NO JUDGMENT OF "ENCROACHMENT" OR
- 5. A PRIVATE ZONING REPORT WAS NOT PROVIDED BY THE OWNER OR THE INSURER PER ALTA/NSPS OPTIONAL TABLE A ITEMS 6(A)(B). THIS SURVEY DOES NOT REFLECT ZONING STATUS OR RESTRICTIONS.
- 6. ANY UNDERGROUND UTILITIES SHOWN HEREON ARE FROM TEXAS 811 MARKINGS LOCATED BY SURVEY CREWS, OR RECORD DRAWINGS OBTAINED FROM UTILITY COMPANIES REPRESENTATIVES, KIMLEY-HORN CANNOT GUARANTEE THE LOCATIONS OF SAID UTILITIES. EXCEPT THOSE THAT ARE OBSERVED AND READILY VISIBLE ON THE SURFACE AT THE TIME OF THIS SURVEY. KIMLEY-HORN HAS MADE NO ATTEMPT TO OBTAIN OR SHOW DATA CONCERNING THE SIZE, DEPTH, CONDITION, OR CAPACITY OF ANY BURIED UTILITIES OR UNDERGROUND FACILITIES. FOR INFORMATION REGARDING SAID UTILITIES OR FACILITIES. PLEASE CONTACT THE APPROPRIATE AGENCIES. TEXAS 811 MARKINGS SHOWING THE LOCATION OF BURIED UTILITIES WERE OBSERVED AND LOCATED BY SURVEY CREWS WHILE PERFORMING THE FIELD SURVEY. KIMLEY-HORN CANNOT GUARANTEE THE ACCURACY AND THOROUGHNESS OF UTILITY COMPANY REPRESENTATIVES MARKING EFFORT. KIMLEY-HORN ASSUMES NO LIABILITY FOR POORLY OR IMPROPERLY MARKED UTILITY LOCATIONS. NO PRIVATE INTERIOR SERVICE LINES WERE MARKED AND NOT ARE SHOWN.
- THE SURVEY CREW OBSERVED NO EVIDENCE OF RECENT EARTH MOVING WORK ON THE SURVEYED PROPERTY.
- THE SURVEYOR IS UNAWARE OF ANY PROPOSED CHANGES TO STREET RIGHT-OF-WAYS AND THERE WAS NO VISIBLE EVIDENCE OF CHANGES TO STREET RIGHT-OF-WAYS AT THE TIME OF SURVEY.
- 9. THE SURVEY CREW OBSERVED NO EVIDENCE OF READILY VISIBLE MARKERS DELINEATING THE WETLANDS ON THE
- 10. THE SURVEY CREW OBSERVED NO EVIDENCE OF SITE USE AS A SOLID WASTE DUMP, SUMP OR SANITARY LANDFILL
- 12. KIMLEY-HORN DID NOT REVIEW LEASE INTEREST WHILE PERFORMING SURVEY.
- 13. THE SURVEYED PROPERTY IS LOCATED WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
- 14. THE SURVEYED TRACTS HAVE ACCESS TO THE PUBLIC STREET RIGHT-OF-WAYS AS FOLLOWS:
- TRACT 1: MORRIS ROAD TRACT 2: BLACK OAK STREET

SURVEYORS CERTIFICATION:

TO: MAG CONSTRUCTION MANAGEMENT LLC AND/OR ASSIGNS; VINEYARD CHRISTIAN FELLOWSHIP OF AUSTIN, TEXAS, INC.;

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT IS BASED WERE MADE IN ACCORDANCE WITH THE 2016 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS, JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 8, 9, 13, AND 16 OF TABLE A THEREOF.

FIELD WORK COMPLETED: JUNE 30, 2021 ALTA SURVEY COMPLETED: JULY 23, 2021

ZACHARY KEITH PETRUS REGISTERED PROFESSIONAL LAND SURVEYOR NO 6769 10814 JOLLYVILLE ROAD CAMPUS IV, SUITE 200 AUSTIN, TEXAS 78759 PH. (512) 572-6674

THIS DOC. SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED OR VIEWED OR RELIED **UPON AS A FINAL** S<u>U</u>RVEY D<u>O</u>C.


Ked - Edwards Formation




ALTA/NSPS LAND TITLE SURVEY OF TRACT 1 - 4.913 ACRES TRACT 2 - 2.999 ACRES


BEING A PORTION OF LOT 1, BLOCK A & ALL OF LOT 2, BLOCK A OF THE VINEYARD CHRISTIAN FELLOWSHIP SUBDIVISION AS SHOWN ON DOC. NO. 2008070951, OPRWC M. M. HORNSBY SURVEY, ABSTRACT NO. 280 CITY OF AUSTIN, WILLIAMSON COUNTY, TEXAS

WWW.KIMLEY-HORN.COM SUITE 200, AUSTIN, TEXAS 78759 FIRM # 10194624 <u>Date</u> <u>Scale</u> REVISION DESCRIPTION 1" = 60' NLS ZKP 7/23/2021 069273503




Edwards Aquifer Viewer Custom Print





Web AppBuilder for ArcGIS





Natural Resources Conservation Service A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Williamson County, Texas

Marielle



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

| Preface | 2 |
|------------------------------------------------------|----|
| How Soil Surveys Are Made | |
| Soil Map | |
| Soil Map | |
| Legend | 10 |
| Map Unit Legend | 11 |
| Map Unit Descriptions | 11 |
| Williamson County, Texas | 13 |
| EeB—Eckrant stony clay, 0 to 3 percent slopes, stony | 13 |
| References | 15 |

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Map Unit Polygons

Soil Map Unit Lines

Soil Map Unit Points

Special Point Features

(o)

Blowout

Borrow Pit

Clay Spot

Closed Depression

Gravel Pit

Gravelly Spot

Landfill Lava Flow

Marsh or swamp

Mine or Quarry

Miscellaneous Water Perennial Water

Rock Outcrop

Saline Spot

Sandy Spot

Slide or Slip

Severely Eroded Spot

Sinkhole

Sodic Spot

Spoil Area

å

Stony Spot

Very Stony Spot

Ŷ

Wet Spot Other

Δ

Special Line Features

Water Features

Streams and Canals

Transportation

Rails

Interstate Highways

US Routes

Major Roads

00

Local Roads

Background

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20.000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Williamson County, Texas Survey Area Data: Version 22, Sep 10, 2021

Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Nov 15, 2020—Dec 1. 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
|-----------------------------|--------------------------------------------------|--------------|----------------|
| EeB | Eckrant stony clay, 0 to 3 percent slopes, stony | 3.2 | 100.0% |
| Totals for Area of Interest | | 3.2 | 100.0% |

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Custom Soil Resource Report

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Williamson County, Texas

EeB—Eckrant stony clay, 0 to 3 percent slopes, stony

Map Unit Setting

National map unit symbol: djpv Elevation: 650 to 1,320 feet

Mean annual precipitation: 30 to 35 inches Mean annual air temperature: 65 to 69 degrees F

Frost-free period: 210 to 250 days

Farmland classification: Not prime farmland

Map Unit Composition

Eckrant, stony, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Eckrant, Stony

Setting

Landform: Ridges

Landform position (two-dimensional): Summit, shoulder Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Residuum weathered from limestone

Typical profile

A1 - 0 to 4 inches: stony clay

A2 - 4 to 11 inches: extremely stony clay

R - 11 to 80 inches: bedrock

Properties and qualities

Slope: 0 to 3 percent

Surface area covered with cobbles, stones or boulders: 0.0 percent

Depth to restrictive feature: 4 to 20 inches to lithic bedrock

Drainage class: Well drained Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum content: 10 percent

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Sodium adsorption ratio, maximum: 1.0

Available water supply, 0 to 60 inches: Very low (about 0.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: D

Ecological site: R081CY360TX - Low Stony Hill 29-35 PZ

Hydric soil rating: No

Custom Soil Resource Report

Minor Components

Georgetown

Percent of map unit: 8 percent

Landform: Ridges

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R081CY361TX - Redland 29-35 PZ

Hydric soil rating: No

Doss

Percent of map unit: 7 percent

Landform: Ridges

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex

Ecological site: R081CY355TX - Adobe 29-35 PZ

Hydric soil rating: No

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Geologic Assessment TCEQ-0585

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Mr. Chad M. Telephone: 512-335-1785 Copeland, P.G., PWS Fax: 512-335-0527 Date: 9/25/2020 Representing: Ranger Environmental Services, Inc. (State of Texas Geoscience Firm No. 50140) (Name of Company and TBPG or TBPE registration number) Signature of Geologist: 09/25/2020 **Regulated Entity Name:** Morris Road Condos SOIL SCIENCE **Project Information** 1. Date(s) Geologic Assessment was performed: <u>09/2</u>5/2020 2. Type of Project: $oxed{oxtime}$ WPAP 3. Location of Project: Recharge Zone **Transition Zone** Contributing Zone within the Transition Zone

| 4. | | | ologic Assessmen Table) is attached. | | Complete | d Geol | ogic Asses | sment Table |
|----|-----------------------------------------------------------------------|----------------------------|---------------------------------------------------------------------------------|------------|----------------------------|----------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|-------------------------------------------------------|
| 5. | Hydrolog 55, Apper | ic Soil Gro ndix A, Soi | oject site is summups* (Urban Hydr Il Conservation Se Dow each soil type | ology for | or Small W 986). If the | atershoere is n | eds, Techr nore than | nical Release No. one soil type on |
| | ble 1 - Soil l aracteristics | = | | | Soil Na | ime | Group* | Thickness(feet) |
| | Soil Name ckrant stony clay, 0 to 3 percent slopes, stony | Group* | Thickness(feet) 0.33-1.67 | | А. В. С. | Soils I rate v Soils I infiltr wette Soils I rate v Soils I | naving a having a having a mation rate d. naving a slaving a slaving a vertion rate aving a vertion rate | when thoroughly low infiltration oughly wetted. |
| 6. | members, | and thickr stratigrap | ratigraphic Colum nesses is attached hic column. Othe umn. | . The ou | utcropping | unit, i | f present, | should be at the |
| 7. | including a potential f | nny feature or fluid me | e Geology. A narra es identified in the ovement to the Ed is attached. | e Geolo | gic Assessr | ment T | able, a dis | cussion of the |
| 8. | | | e Geologic Map(s Plan. The minimu | - | _ | • | must be t | the same scale as |
| | Site Geolo | gic Map So | Scale: 1" = <u>60</u> ' cale: 1" = <u>60</u> ' (if more than 1 so | oil type): | 1:1,750 8 | <u> </u> | <u>30</u> | |
| 9. | Method of co | ollecting p | ositional data: | | | | | |
| | | _ | System (GPS) tech lease describe me | • | data colle | ection: | | |

| 10. 🔀 | The project site and boundaries are clearly shown and labeled on the Site Geologic Map |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 11. 🔀 | Surface geologic units are shown and labeled on the Site Geologic Map. |
| 12. | Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table. |
| | Geologic or manmade features were not discovered on the project site during the field investigation. |
| 13. 🔀 | The Recharge Zone boundary is shown and labeled, if appropriate. |
| | known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If plicable, the information must agree with Item No. 20 of the WPAP Application Section. |
| | There are (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.) The wells are not in use and have been properly abandoned. The wells are not in use and will be properly abandoned. The wells are in use and comply with 16 TAC Chapter 76. There are no wells or test holes of any kind known to exist on the project site. |
| Adn | ninistrative Information |
| 15. 🔀 | Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and |

county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional

office.

ATTACHMENT A

Geological Assessment Table TCEQ-0585 Table

No Features observed

| GEOLOGIC ASSESSMENT TABLE | | | | | | | PR | OJE | CT NA | ME | : | Morris | Road | Condos | | | | | | | | | | | | | | | | | | |
|---------------------------|----------|-----------|-----------------|--------|-----------|-------------------|-----|-------------------|---------------|-------------------|--------|-------------------|------|-------------------|------|-------------------|---------------|-------------------|----------------|-------------------|--|-----|--------------------|--------------------|--------|----------------------------------|-------|------|---------|--|------------------|------------|
| L | OCATIO | ON | | | | FEA | TUR | E CI | HARACT | ER | ISTICS | 3 | | | EVAL | _UAT | ION | PHY | SICAL | SETTING | | | | | | | | | | | | |
| 1A | 1B * | 1C* | 2A | 2B | 3 | | 4 | | 5 | 5A | 6 | 7 | 8A | 8B | 9 | 1 | 10 | 1 | 1 | 12 | | | | | | | | | | | | |
| FEATURE ID | LATITUDE | LONGITUDE | FEATURE TYPE | POINTS | FORMATION | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DIMENSIONS (FEET) | | DOM | DENSITY (NO/FT) | APERTURE (FEET) | INFILL | RELATIVE INFILTRATION RATE | TOTAL | SENS | ITIVITY | | ENT AREA RES) | TOPOGRAPHY |
| | | | | | | Х | Υ | Z | | 10 | | | | | | <40 | <u>>40</u> | <1.6 | <u>>1.6</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

* DATUM WGS84

| 2A TYPE | TYPE | 2B POINTS |
|---------|-------------------------------------|-----------|
| С | Cave | 30 |
| sc | Solution cavity | 20 |
| SF | Solution-enlarged fracture(s) | 20 |
| F | Fault | 20 |
| 0 | Other natural bedrock features | 5 |
| MB | Manmade feature in bedrock | 30 |
| SW | Swallow hole | 30 |
| SH | Sinkhole | 20 |
| CD | Non-karst closed depression | 5 |
| Z | Zone, clustered or aligned features | 30 |

| | 8A INFILLING |
|----|-----------------------------------------------------------------------|
| N | None, exposed bedrock |
| С | Coarse - cobbles, breakdown, sand, gravel |
| 0 | Loose or soft mud or soil, organics, leaves, sticks, dark colors |
| F | Fines, compacted clay-rich sediment, soil profile, gray or red colors |
| V | Vegetation. Give details in narrative description |
| FS | Flowstone, cements, cave deposits |
| Χ | Other materials |
| | |
| | 12 TOPOGRAPHY |

ression 5 12 TOPOGRAPHY
gned features 30 Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The

information presented here complies with that document and is a true representation of the conditions observed in the field.

My signature certifies that am qualified as a geologist as defined by 30 TAC Chapter 213.

Date 09/25/2020

Sheet _1__ of _1__

TCEQ-0585-Table (Rev. 10-01-04)




ATTACHMENT B

Stratigraphic Column

Stratigraphic column of Cretaceous rocks of the northern segment of the Edwards aquifer, Austin region.







RANGER ENVIRONMENTAL SERVICES, INC.

Morris Road Condos

RANGER REFERENCE 6055

*FIGURE ADAPTED AND EDITED BY RANGER ENVIRONMETAL SERVICES, INC.

*ORIGINAL SOURCE: Senger, R., Collins E., Kreitler C. (1990). Hydrology of the Northern Segment of the Edwards Aquifer, Austin Region. The University of Texas at Austin, Texas 78713. Bureau of Economic Geology.

ATTACHMENT C

Site Geology



GEOLOGIC ASSESSMENT
Morris Road Condos
13208 Morris Road
Austin, Texas
Williamson County
September 2020

INTRODUCTION

Ranger Environmental Services, Inc. (Ranger) was contracted to conduct a Geologic Assessment of the referenced property. This location lies within the designated Edwards Aquifer Recharge Zone. The site was noted to be undeveloped. Since the subject site is located over the Edwards Aquifer Recharge Zone, site development should adhere to the Texas Commission on Environmental Quality (TCEQ) Edwards Aquifer Protection Program Rules in accordance with Title 30 of the Texas Administrative Code, Section 213 (30 TAC§ 213).

PROJECT DESCRIPTION

The subject site consists of one approximate 4.91-acre tract, more or less, that was part of an approximate 8.47 lot located at 13208 Morris Road, Austin, in Williamson County, Texas at approximately N 30° 27' 30.8" and approximately W 097° 46' 0.36".

The subject site was noted to be undeveloped. It was reported to Ranger that the construction residential condos were planned for the site. The site is situated in a residential/commercial area.

METHODOLOGY

P.O. BOX 201179

This assessment follows general guidelines contained in Texas Commission on Environmental Quality (TCEQ) guidance "Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones" (TCEQ Guidance 0585). The site is located on an area of the recharge zone that may contain karst features within the outcropping limestone. Karst features may be expressed as surface features but more commonly tend to persist with depth.

A field geologic assessment was conducted by Mr. Chad M. Copeland, P.G., PWS on September 25, 2020. The site was noted to be undeveloped

The walking geologic survey was conducted on 50-foot center transects, where possible. No intrusive testing was conducted. If present, features identified in the field were photographed and recorded with a hand held global positioning system (GPS). Features include, but were not limited to, caves, solution cavities, solution-enlarged fractures, faults, manmade features in bedrock, swallow holes, sinkholes, non-karst closed depressions, and zone clustered or aligned features.

STATE OF TEXAS PROFESSIONAL GEOSCIENTIST FIRM NO. 50140 • STATE OF TEXAS PROFESSIONAL ENGINEERING FIRM NO. F-6160

AUSTIN, TX 78720 OFFICE: 512/335-1785 FAX: 512/335-0527

The geologic assessment table, stratigraphic column, geologic, soils and topographic maps are included herein.

RESEARCH INFORMATION

Prior to conducting the geologic survey, Ranger conducted a review of existing geologic data and maps to prepare for the field survey. Reviewed references included, but are not limited to:

- Barnes, V.E. 1974. *Geologic Atlas of Texas, Austin Sheet*. The University of Texas at Austin, Bureau of Economic Geology.
- Senger, R.K., E.W. Collins and C.W. Kreitler. 1990. <u>Hydrogeology of the Northern Segment of the Edwards Aquifer, Austin Region, Report of Investigations 192</u>. The University of Texas at Austin, Bureau of Economic Geology.
- Texas Commission on Environmental Quality. 1999. <u>Complying with the Edwards Aquifer Rules: Administrative Guidance.</u>
- Texas Commission on Environmental Quality. Revised 2004. <u>Instructions to Geologist for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones.</u>
- Sellards, E.H., W.S. Adkins and F.B. Plummer. 1932. <u>The University of Texas Bulletin No. 3232</u>. <u>The Geology of Texas</u>. Volume 1, Stratigraphy.
- U.S. Department of Agriculture National Resources Conversation Services (www.nrcs.usda.gov).
- Texas Commission on Environmental Quality (www.tceq.state.tx.us).
- FEMA Flood Plain Maps.
- Center for Geospatial Technology, Texas Tech University, obtained from the Texas Geologic Atlas of Texas.
- USGS Topographic Maps Terrain Navigator Pro 2015.
- ESRI

SITE GEOLOGY

According to the *Geologic Atlas of Texas*, *Austin Sheet* (1974), the site is underlain by Edwards Limestone (Ked), a formation belonging to the Fredericksburg Group. The Edwards Limestone is characterized by limestone, dolomite, and chert. The limestone is aphanitic to fine grained, massive to thin bedded, hard, brittle, in part rudistid biostromes, much miliolid biospharite. The dolomite is fine to very fine grained, porous, medium gray to grayish brown. The chert varies in amount bed to bed with some intervals free of chert. It is mostly white to light gray. In zones of weathering, the Edwards Limestone is considerably recrystallized, "honeycombed," and cavernous forming an aquifer. The Edwards Limestone thickness is 60-350 feet and thins northward.

During the field inspection, the site was noted to be a mix of woodland and grassland supporting vegetation. There were no defined drainage features. No outcropping was observed. Numerous manmade piles of rock and soil were noted on the property. No vugs, faults, or fractures were observed during the site geologic inspection.

SITE SPECIFIC GEOLOGIC FEATURES

No geologic features, as defined in Texas Commission on Environmental Quality (TCEQ) guidance "Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones" (TCEQ Guidance 0585), were observed at the site.

SOIL DESCRIPTION

According to the U.S. Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS) *Web Soil Survey*, the soil located at the site are classified as Eckrant stony clay, 0 to 3 percent slopes, stony (EeB). These soils typically have a stony clay A horizon with a shallow R horizon of approximately 0.33 feet to 1.67 feet. Additionally, these soils are well drained with very slow infiltration.

Please see attached USDA NRCS Custom Soil Resource Report.

TOPOGRAPHY AND DRAINAGE

The site was observed to be relatively flat. The elevation ranged from approximately 874 feet above mean sea level to approximately 881. There were numerous manmade rock/soil piles noted. The general direction of drainage is northeast/east.

CONCLUSIONS AND RECOMMENDATIONS

Ranger Environmental Services, Inc. conducted a Geologic Assessment of the site in accordance with 30 TAC§ 213. Ranger concludes that no sensitive features as defined by the TCEQ (30 TAC§ 213) were observed at the site.

This assessment does not address the possible presence of subsurface conditions that may be exposed during future construction and/or development. Should solution features or conditions be exposed during site construction activities that indicate a potential for hydraulic interconnectedness between the surface and the Edwards Aquifer, operations in the vicinity of the feature should be halted and the Texas Commission on Environmental Quality (TCEQ) Edwards Aquifer Protection Program should be contacted immediately in accordance with 30 TAC §213.5(f)(2).

LIMITATIONS

It should be noted that only areas readily accessible were inspected. There may be geologic features present that were not identified as part of this study. This non-intrusive visual field assessment cannot wholly eliminate the possibility of sensitive features at the site.


Prepared by:

Chad M. Cooeland, P.G., PWS

CHAD M. COPELAND 509/25/2020

SOIL SCIENCE 12668 ATTACHMENT D

Site Geologic Map(s)




Map adapted by Ranger Environmental Services, Inc.

Copyright © 2020

(imley-Horn and Associates, In-

All rights reserved



SANITARY SEWER MARKER FLA

ANITARY SEWER MARKER SIGN SANITARY SEWER METER STORM SEWER METER ORM SEWER VAULT ELEPHONE BOX TELEPHONE HANDHOL ELEPHONE MARKER FLA TELEPHONE MARKER SIGN ELECTRIC MARKER FLA AFFIC MANHOLE UNIDENTIFIED HANDHOL UNIDENTIFIED MANHOLE UNIDENTIFIED MARKER FLAG WATER MANHOLE WATER MARKER FLAC BRASS TXDOT DISK FOUND MARQUEE/BILLBOARD CONCRETE MONUMENT FOUND PHONE BOOTH IRON PIPE FOUND PIPELINE BOX IRF IRON ROD FOUND IRFC IRON ROD WITH CAP FOUND DPRTC DEED AND PLAT RECURDS OF TRAVIS COUNTY, TEXAS

OPRTC OFFICIAL PUBLIC RECORDS OF TRAVIS COUNTY, TEXAS

PRTC PLAT RECORDS OF SANITARY SEWER CLEAN OU SANITARY SEWER HANDHOLE SANITARY SEWER HANDHOLE
SANITARY SEWER LIFT STATION
PRTC PLAT RECORDS OF TRAVIS COUNTY, TEXAS

09/25/2020

SOIL SCIENCE

GENERAL NOTES

- THIS SURVEY WAS PERFORMED UTILIZING THAT CERTAIN TITLE REPORT PREPARED BY WESTCOR LAND TITLE INSURANCE COMPANY, G.F. NO. 9991-20-6631 (ISSUE DATE: MARCH 27 2020, EFFECTIVE DATE: MARCH 16, 2020) AND REFLECTS ONLY THOSE EASEMENTS AND ENCUMBRANCES OF RECORD MENTIONED THEREIN. KIMLEY-HORN DID NOT ABSTRACT THE PUBLIC RECORDS. THE SURVEYED TRACT MAY BE SUBJECT TO ADDITIONAL GOVERNMENT REGULATIONS AND RESTRICTIONS PRIOR TO FURTHER SITE DEVELOPMENT.
- 2. THIS IS A TOPOGRAPHIC MAP PREPARED FOR SITE IMPROVEMENT AND DESIGN PURPOSES ONLY. THIS NOT A LAND TITLE SURVEY.
- ACCORDING TO COMMUNITY PANEL NO. 48491C0610F, DATED 12/20/2019 OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP (FIRM), THE SUBJECT TRACT IS LOCATED WITHIN ZONE "X" (UN-SHADED) WHICH IS DEFINED BY FEMA AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN," COMMONLY KNOWN AS THE 500-YEAR FLOODPLAIN. ZONE "X" (UN-SHADED) IS OUTSIDE OF ANY FEMA ESTABLISHED FLOOD HAZARD ZONE. ALL ZONE DELINEATIONS SHOWN HEREON ARE APPROXIMATE. THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY AND/OR THE STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. ON RARE OCCASIONS, GREATER FLOODS CAN AND WILL OCCUR AND FLOOD HEIGHTS MAY BE INCREASED BY MAN-MADE OR NATURAL CAUSES. THIS FLOOD STATEMENT SHALL NOT CREATE ANY LIABILITY ON THE PART OF KIMLEY-HORN OR THE UNDERSIGNED.
- 4. THE BEARINGS, DISTANCES, AREAS AND COORDINATES SHOWN HEREON ARE TEXAS STATE COORDINATE SYSTEM GRID, CENTRAL ZONE (FIPS 4203) (NAD'83), AS DETERMINED BY THE GLOBAL POSITIONING SYSTEM (GPS). ALL DISTANCES SHOWN HEREON ARE ON THE GRID. THE UNIT OF LINEAR MEASUREMENT IS U.S. SURVEY FEET.
- 4. THIS DRAWING SHOWS EXISTING SPOT ELEVATIONS AND CONTOUR LINES BASED UPON A FIELD SURVEY CONDUCTED BY SURVEY PERSONNEL. THE CONTOUR INTERVAL IS 1 FOOT, ALL ELEVATIONS SHOWN HEREON ARE TIED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD '88) BASED ON GPS OBSERVATIONS.
- 5. KIMLEY-HORN HAS MADE NO ATTEMPT TO OBTAIN OR SHOW DATA CONCERNING THE EXISTENCE, SIZE, DEPTH, CONDITION, CAPACITY, OR LOCATION OF ANY UTILITY OR UNDERGROUND FACILITY. FOR INFORMATION REGARDING SAID UTILITIES OR FACILITIES, PLEASE CONTACT THE APPROPRIATE AGENCIES. NO TEXAS 811 MARKINGS SHOWING THE LOCATION OF BURIED UTILITIES WERE OBSERVED AND LOCATED BY SURVEY CREWS WHILE PERFORMING THE FIELD SURVEY. KIMLEY-HORN CANNOT GUARANTEE THE ACCURACY AND THOROUGHNESS OF UTILITY COMPANY REPRESENTATIVES MARKING EFFORT. KIMLEY-HORN ASSUMES NO LIABILITY FOR POORLY OR IMPROPERLY MARKED UTILITY LOCATIONS. NO PRIVATE INTERIOR SERVICE LINES WERE MARKED AND NOT ARE SHOWN.
- 6. THE TREE SPECIES REFERENCE ON THIS EXHIBIT REFLECT FIELD INDICATIONS MADE BY SURVEY CREW PERSONNEL. AN ARBORIST OR OTHER EXPERT CONSULTANT SHOULD MAKE THE FINAL DETERMINATION OF TREE TYPES AND CONDITIONS.


TOPOGRAPHIC AND TREE SURVEY OF TRACT 1 - 4.913 ACRES


BEING A PORTION OF LOT 1, BLOCK A, M.M. HORNSBY SURVEY, ABSTRACT NO. 280 13208 MORRIS ROAD, CITY OF AUSTIN, WILLIAMSON COUNTY, TEXAS




<u>Date</u> 7/6/2020 069273503

ZKP









Natural Resources Conservation Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Williamson County, Texas

13208 Morris Road, Austin, Texas



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2 053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

| Preface | 2 |
|------------------------------------------------------|----|
| How Soil Surveys Are Made | |
| Soil Map | |
| Soil Map | |
| Legend | 10 |
| Map Unit Legend | 11 |
| Map Unit Descriptions | |
| Williamson County, Texas | 13 |
| CfB—Crawford clay, 1 to 3 percent slopes | 13 |
| EeB—Eckrant stony clay, 0 to 3 percent slopes, stony | 14 |
| References | 17 |

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



MAP LEGEND

Special Line Features Streams and Canals Interstate Highways Very Stony Spot Major Roads Local Roads Stony Spot US Routes Spoil Area Wet Spot Other Rails Nater Features ransportation W 8 ◁ ŧ Soil Map Unit Polygons Area of Interest (AOI) Soil Map Unit Points Soil Map Unit Lines Closed Depression Special Point Features **Gravelly Spot** Borrow Pit **Gravel Pit** Clay Spot Area of Interest (AOI) Blowout Landfill 9 Soils

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL: Coordinate System: Web Mercator (EPSG:3857) Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

Aerial Photography

Marsh or swamp

Lava Flow

Mine or Quarry

Miscellaneous Water

Perennial Water

Rock Outcrop

Saline Spot Sandy Spot

3ackground

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Williamson County, Texas Survey Area Data: Version 21, Jun 11, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Severely Eroded Spot

Slide or Slip

Sinkhole

Sodic Spot

Date(s) aerial images were photographed: May 27, 2018—Nov 16, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
|-----------------------------|--------------------------------------------------|--------------|----------------|
| CfB | Crawford clay, 1 to 3 percent slopes | 1.2 | 8.6% |
| EeB | Eckrant stony clay, 0 to 3 percent slopes, stony | 12.5 | 91.4% |
| Totals for Area of Interest | | 13.6 | 100.0% |

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however,

onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An association is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Williamson County, Texas

CfB—Crawford clay, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2rspf Elevation: 400 to 1,100 feet

Mean annual precipitation: 26 to 34 inches Mean annual air temperature: 64 to 68 degrees F

Frost-free period: 230 to 250 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Crawford and similar soils: 85 percent *Minor components:* 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Crawford

Setting

Landform: Plains

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear Across-slope shape: Linear

Parent material: Residuum weathered from limestone

Typical profile

A - 0 to 6 inches: clay Bss - 6 to 27 inches: clay R - 27 to 30 inches: bedrock

Properties and qualities

Slope: 1 to 3 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Drainage class: Well drained Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately

low (0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum content: 2 percent

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: D

Ecological site: R081CY358TX - Deep Redland 29-35 PZ

Hydric soil rating: No

Minor Components

Georgetown

Percent of map unit: 4 percent

Landform: Plains

Landform position (two-dimensional): Summit, footslope Landform position (three-dimensional): Interfluve, base slope

Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R081CY361TX - Redland 29-35 PZ

Hydric soil rating: No

Denton

Percent of map unit: 4 percent

Landform: Ridges

Landform position (two-dimensional): Summit, shoulder Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Convex

Ecological site: R081CY357TX - Clay Loam 29-35 PZ

Hydric soil rating: No

Fairlie

Percent of map unit: 4 percent

Landform: Ridges

Landform position (two-dimensional): Toeslope, footslope Landform position (three-dimensional): Base slope

Down-slope shape: Linear Across-slope shape: Convex

Ecological site: R086AY011TX - Southern Blackland

Hydric soil rating: No

Purves

Percent of map unit: 2 percent

Landform: Ridges

Landform position (two-dimensional): Summit, shoulder Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex

Ecological site: R081CY574TX - Shallow 29-35 PZ

Hydric soil rating: No

Unnamed

Percent of map unit: 1 percent

Hydric soil rating: No

EeB—Eckrant stony clay, 0 to 3 percent slopes, stony

Map Unit Setting

National map unit symbol: djpv

Elevation: 650 to 1,320 feet

Mean annual precipitation: 30 to 35 inches Mean annual air temperature: 65 to 69 degrees F

Frost-free period: 210 to 250 days

Farmland classification: Not prime farmland

Map Unit Composition

Eckrant, stony, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Eckrant, Stony

Setting

Landform: Ridges

Landform position (two-dimensional): Shoulder, summit Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Residuum weathered from limestone

Typical profile

A1 - 0 to 4 inches: stony clay

A2 - 4 to 11 inches: extremely stony clay

R - 11 to 80 inches: bedrock

Properties and qualities

Slope: 0 to 3 percent

Surface area covered with cobbles, stones or boulders: 0.0 percent

Depth to restrictive feature: 4 to 20 inches to lithic bedrock

Drainage class: Well drained Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Calcium carbonate, maximum content: 10 percent

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Sodium adsorption ratio, maximum: 1.0

Available water capacity: Very low (about 0.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: D

Ecological site: R081CY360TX - Low Stony Hill 29-35 PZ

Hydric soil rating: No

Minor Components

Georgetown

Percent of map unit: 8 percent

Landform: Ridges

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: R081CY361TX - Redland 29-35 PZ

Hydric soil rating: No

Doss

Percent of map unit: 7 percent

Landform: Ridges

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex

Ecological site: R081CY355TX - Adobe 29-35 PZ

Hydric soil rating: No

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

SECTION 4: WATER POLLUTION ABATEMENT PLAN

Water Pollution Abatement Plan Application Form

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Jose M. Farias, P.E.

Date: 12/10/2025

Signature of Customer/Agent:

Regulated Entity Name: MCRT SFR TEXAS CONSTRUCTION LLC

Regulated Entity Information

| 1. | The type of project is: |
|----|---------------------------------------------------------------------------------------------------------------|
| | Residential: Number of Lots: Residential: Number of Living Unit Equivalents: 143 Commercial Industrial Other: |
| 2 | Total site acreage (size of property): 7 913 acres |

- 2. Total site acreage (size of property): 7.913 acres
- 3. Estimated projected population: 286
- 4. The amount and type of impervious cover expected after construction are shown below:

Table 1 - Impervious Cover Table

| Impervious Cover of Proposed Project | Sq. Ft. | Sq. Ft./Acre | Acres |
|--------------------------------------|------------|--------------|-------|
| Structures/Rooftops | 109,285.00 | ÷ 43,560 = | 2.50 |
| Parking | 2,268 | ÷ 43,560 = | 0.05 |
| Other Paved Surfaces | 87,616 | ÷ 43,560 = | 2.01 |
| Total Impervious Cover | 199,169.00 | ÷ 43,560 = | 4.57 |

Total Impervious Cover <u>4.57</u> ÷ Total Acreage <u>7.913</u> X 100 = <u>57.8%</u> Impervious Cover

| 5. | Attachment A - Factors Affecting Surface Water Quality. A detailed description of al |
|----|-----------------------------------------------------------------------------------------|
| | factors that could affect surface water and groundwater quality that addresses ultimate |
| | land use is attached. |

6. Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

| 7. | Type of project: <u>N/A</u> |
|-----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | ☐ TXDOT road project. ☐ County road or roads built to county specifications. ☐ City thoroughfare or roads to be dedicated to a municipality. ☐ Street or road providing access to private driveways. |
| 8. | Type of pavement or road surface to be used: <u>N/A</u> |
| | Concrete Asphaltic concrete pavement Other: |
| 9. | Length of Right of Way (R.O.W.): feet. <u>N/A</u> |
| | Width of R.O.W.: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$ |
| 10. | Length of pavement area: feet. <u>N/A</u> |
| | Width of pavement area: feet. L x W = $Ft^2 \div 43,560 \ Ft^2/Acre = acres.$ Pavement area acres \div R.O.W. area acres x $100 = \%$ impervious cover. |
| 11. | A rest stop will be included in this project. N/A |
| | A rest stop will not be included in this project. |

| 12. | Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ. <u>N/A</u> |
|-----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| St | formwater to be generated by the Proposed Project |
| 13. | Attachment B - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions. |
| W | astewater to be generated by the Proposed Project |
| 14. | The character and volume of wastewater is shown below: |
| | 100 % Domestic110,857Gallons/day% IndustrialGallons/day% CommingledGallons/dayTOTAL 110,857Gallons/day |
| 15. | Wastewater will be disposed of by: |
| | □ On-Site Sewage Facility (OSSF/Septic Tank): □ Attachment C - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities. □ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285. |
| | Sewage Collection System (Sewer Lines): ☐ Private service laterals from the wastewater generating facilities will be connected to an existing SCS. ☐ Private service laterals from the wastewater generating facilities will be connected to a proposed SCS. ☐ The SCS was previously submitted on ☐ The SCS was submitted with this application. ☐ The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval. |

| ∑ The sewage collection system will convey the wastewater to the Austin West WWTP _The treatment facility is: ∑ Existing. ☐ Proposed. |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 16. All private service laterals will be inspected as required in 30 TAC §213.5. |
| Site Plan Requirements |
| Items 17 – 28 must be included on the Site Plan. |
| 17. \square The Site Plan must have a minimum scale of 1" = 400'. |
| Site Plan Scale: 1" = <u>30', 40'</u> |
| 18. 100-year floodplain boundaries: |
| Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled. No part of the project site is located within the 100-year floodplain. The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): Federal Emergency Management Agency Flood Insurance Rate Map (FEMA) and 48491C0610F dated December 20th 2019. |
| 19. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan. |
| The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan. |
| 20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.): |
| ☐ There are 0 (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply) ☐ The wells are not in use and have been properly abandoned. ☐ The wells are not in use and will be properly abandoned. ☐ The wells are in use and comply with 16 TAC §76. ☐ There are no wells or test holes of any kind known to exist on the project site. |
| 21. Geologic or manmade features which are on the site: |
| All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled. No sensitive geologic or manmade features were identified in the Geologic Assessment. |
| Attachment D - Exception to the Required Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached. |
| 22. The drainage patterns and approximate slopes anticipated after major grading activities. |

| 23. | . $igotimes$ Areas of soil disturbance and areas which will not be disturbed. |
|-----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 24. | . \boxtimes Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices. |
| 25. | . $igotimes$ Locations where soil stabilization practices are expected to occur. |
| 26. | . 🔲 Surface waters (including wetlands). |
| | ⊠ N/A |
| 27. | . Locations where stormwater discharges to surface water or sensitive features are to occur. |
| | There will be no discharges to surface water or sensitive features. |
| 28. | . 🔀 Legal boundaries of the site are shown. |
| A | dministrative Information |
| 29. | . Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office. |

30. Any modification of this WPAP will require Executive Director approval, prior to

construction, and may require submission of a revised application, with appropriate fee.



Attachment A Factors Affecting Water Quality

Materials that are anticipated to be used on site that could be a potential source of contamination include the following:

During Construction:

- 1. Petroleum drippings from vehicle movement
- 2. Integrated Pest Management
- 3. Asphalt and /or Concrete Products
- 4. Soil/Stockpile
- 5. Concrete and Masonry Materials
- 6. Wood, plastic, and metal Materials
- 7. Tar and hydrocarbons from paving operations
- 8. Oil, grease, fuel, and hydraulic fluid from construction equipment and vehicle drippings
- 9. Fertilizers, herbicides, and pesticides
- 10. Cleaning solutions and detergents
- 11. Miscellaneous construction trash and debris
- 12. Soil erosion and sedimentation due to construction activity

Ultimate Use:

- 1. Pollutants generated from vehicles utilizing the site
- 2. Fertilizers, herbicides, and pesticides used to maintain landscaping
- 3. Miscellaneous trash and debris generated from the public

This is not intended to be an all-inclusive list. All practical management practices will be used to reduce the risk of spills and other exposure of any contaminant to surface or groundwater.

Attachment B Volume and Character of Storm Water

Existing Drainage Conditions

The existing site topographic information used for this drainage study is provided by an on-site topographic survey of the ±7.91-acre tract and Aerial Lidar contours of the off-site contributing drainage areas. From the topography, one (1) drainage basin/point of analysis was identified and analyzed. E-A drains from west to and drains into Morris Road. E-B drains from west to south and drains into Morris Road.

| | | | | EXISTING C | ONDITIONS | (HEC-HMS) | | | | |
|------------------|-----------------|------------------|-----------------|----------------------------|-----------|--------------------|-------------|--------------|--------------|---------------|
| Draiange Area | AREA (acres) | AREA (sq.mi.) | Curve Number | Impervious Cover (%) | TC (min.) | LAG TIME (min.) | Q2 (cfs) | Q10 (cfs) | Q25 (cfs) | Q100 (cfs) |
| E-A | 6.27 | 0.010 | 84 | 14.39 | 37.4 | 22.4 | 12.6 | 21.9 | 28.3 | 38.9 |
| E-B | 4.04 | 0.006 | 84 | 14.21 | 26.4 | 15.8 | 9.7 | 16.9 | 21.8 | 29.9 |
| POA "A" | | | | | | | 12.6 | 21.9 | 28.3 | 38.9 |
| POA "B" | | | | | | | 9.7 | 16.9 | 21.8 | 29.9 |

Proposed Drainage Conditions

Two drainage areas are proposed, "P-A" and "P-B". Basin "E-A" and "E-B" will be routed through water quality ponds proposed within the Project to reduce peak flows to existing conditions.

| | | | | PROPOSED (| CONDITIONS | S (HEC-HMS) | | | | |
|------------------|-----------------|------------------|-----------------|----------------------------|------------|--------------------|-------------|--------------|--------------|---------------|
| Draiange Area | AREA (acres) | AREA (sq.mi.) | Curve Number | Impervious Cover (%) | Tc (min.) | LAG TIME (min.) | Q2 (cfs) | Q10 (cfs) | Q25 (cfs) | Q100 (cfs) |
| P-A | 29.48 | 0.046 | 80 | 85 | 5.0 | 3.0 | 18.3 | 29.7 | 37.3 | 50.1 |
| P-B | 19.86 | 0.031 | 80 | 85 | 5.0 | 3.0 | 11.9 | 19.0 | 23.7 | 31.6 |
| POA "A" | | | | | | | 11.5 | 18.9 | 24.1 | 33.8 |
| POA "B" | | | | | | | 8.4 | 13.4 | 17.2 | 23.7 |

Storm Water Detention and Water Quality

The detention pond requirements used for the purpose of this report are assumed to be based on the requirements outlined by the City of Austin Drainage Specifications. Therefore, this report focuses on the reduction of flows to pre-developed conditions for the 2, 10, 25, & 100-year frequencies. To reduce the flow to pre-developed conditions, a partial sedimentation/filtration pond will be constructed as a part of this development to reduce flows to existing conditions. Water Quality Best Management Practices (BMP) for the Project will address the water quality requirements for the area disturbed. Drainage area "DA-1" will utilize a partial sedimentation and filtration basin to meet all water quality requirements per TCEQ requirements.



Pond "A"

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: Pond "A" Date Prepared: 9/26/2024

2/5/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadshee

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: Lu = 27.2(A_N x P)

where:

 $L_{M.TOTAL.PHOJECT}$ = Required TSS removal resulting from the proposed development = 80% of increased k

A_N = Net increase in impervious area for the project

P = Average annual precipitation, inches

lbs.

1996

Site Data: Determine Required Load Removal Based on the Entire Project

County = Williamson

Total project area included in plan * = 4.35 acres

Predevelopment impervious area within the limits of the plan * = 0.34 acres

Total post-development impervious cover fraction * = 0.60

P = 32 inches

L_{M TOTAL PROJECT} =

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin);

Drainage Basin/Outfall Area No. = Pond A

Total drainage basin/outfall area = 4.35 acres
Predevelopment impervious area within drainage basin/outfall area = 0.34 acres
Post-development impervious area within drainage basin/outfall area = 2.63 acres
Post-development impervious fraction within drainage basin/outfall area = 0.60

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Sand Filter

Removal efficiency = 89 percent

Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault

4. Calculate Maximum TSS Load Removed (L.) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A_t x 34.6 + A_o x 0.54)

where:

A_C = Total On-Site drainage area in the BMP catchment area

A_I = Impervious area proposed in the BMP catchment area

A_P = Pervious area remaining in the BMP catchment area

L_R = TSS Load removed from this catchment area by the proposed BMP

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L_{M THIS BASIN} = 1996 lbs.

F = 0.76

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 0.94 inches

Post Development Runoff Coefficient = 0.42

On-site Water Quality Volume = 6315 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = 1.26 acres
Off-site Impervious cover draining to BMP = 0.57 acres

Impervious fraction of off-site area = 0.45
Off-site Runoff Coefficient = 0.33

Off-site Water Quality Volume = 1427 cubic feet

Storage for Sediment = 1548

Total Capture Volume (required water quality volume(s) x 1.20) = 9291 cubic feet

The following sections are used to calculate the required water quality volume(s) for the selected BMP.

The values for BMP Types not selected in cell C45 will show NA.

7. Retention/Irrigation System Designed as Required in RG-348 Pages 3-42 to 3-46

Required Water Quality Volume for retention basin = NA cubic feet

Irrigation Area Calculations:

Soil infiltration/permeability rate = 0.1 in/hr Enter determined permeability rate or assumed value

Irrigation area = NA square feet NA acres

8. Extended Detention Basin System Designed as Required in RG-348 Pages 3-46 to 3-51

Required Water Quality Volume for extended detention basin = NA cubic feet

9. Filter area for Sand Filters Designed as Required in RG-348 Pages 3-58 to 3-63

9A, Full Sedimentation and Filtration System

Water Quality Volume for sedimentation basin = 9291 cubic feet

Minimum filter basin area = 351 square feet

Maximum sedimentation basin area = 3158 square feet For minimum water depth of 2 feet
Minimum sedimentation basin area = 789 square feet For maximum water depth of 8 feet

9B. Partial Sedimentation and Filtration System

Water Quality Volume for combined basins = 9291 cubic feet

Minimum filter basin area = 632 square feet

Maximum sedimentation basin area = 2526 square feet For minimum water depth of 2 feet
Minimum sedimentation basin area = 158 square feet For maximum water depth of 8 feet

10. Bioretention System Designed as Required in RG-348 Pages 3-63 to 3-65

Required Water Quality Volume for Bioretention Basin = NA cubic feet

11. Wet Basins Designed as Required in RG-348 Pages 3-66 to 3-71

Required capacity of Permanent Pool *
Required capacity at WQV Elevation = NA cubic feet cubic feet

plus a second WQV.

JOSE M. FARIAS 111389 /CENSE

2/5/2025

Pond "B"

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: Pond "B" Date Prepared: 9/26/2024

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the s

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: L_M = 27.2(A_N x P)

where:

 $L_{M\,TOTAL\,PROJECT}$ = Required TSS removal resulting from the proposed development = 80% of A_{N} = Net increase in impervious area for the project

P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

| Williamson | County = |
|------------|-------------------------------------------------------------------------|
| 3,57 acres | Total project area included in plan * = |
| 0.05 acres | Predevelopment impervious area within the limits of the plan* = |
| 2.02 acres | Total post-development impervious area within the limits of the plan' = |
| 0.57 | Total post-development impervious cover fraction * = |
| 32 inches | P = |
| | |

L_{M TOTAL PROJECT} = 1712 lbs.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

| | Drainage Basin/Outfall Area No. = | Pond B | |
|-----------------------------------|-----------------------------------------|--------|-------|
| | Total drainage basin/outfall area = | 3.57 | acres |
| Predevelopment impervious as | rea within drainage basin/outfall area= | 0.05 | acres |
| Post-development impervious as | rea within drainage basin/outfall area= | 2.02 | acres |
| Post-development impervious fract | ion within drainage basin/outfall area= | 0.57 | |
| | L _{M THIS BASIN} = | 1715 | lbs. |

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Sand Filter
Removal efficiency = 89 percent

Aqualogic Cartridge Filt Bioretention Contech StommFilter Constructed Wetland Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin

4. Calculate Maximum TSS Load Removed (Lo) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A x 34.6 + A_P x 0.54)

where:

 A_0 = Total On-Site drainage area in the BMP catchment area A_1 = Impervious area proposed in the BMP catchment area A_P = Pervious area remaining in the BMP catchment area

L_R = TSS Load removed from this catchment area by the proposed BMP

^{*} The values entered in these fields should be for the total project area.

 $A_C = 3.57$ acres $A_I = 2.02$ acres $A_P = 1.55$ acres $L_R = 2014$ lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L_{M THIS BASIN} = 1715 lbs.

F = 0.85

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 34

Rainfall Depth = 1.32 inches
Post Development Runoff Coefficient = 0.40
On-site Water Quality Volume = 6788 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = 1.15 acres
Off-site Impervious cover draining to BMP = 0.52 acres
Impervious fraction of off-site area = 0.45

Off-site Runoff Coefficient = 0.33
Off-site Water Quality Volume = 1834 cubic feet

Storage for Sediment = 1724

Total Capture Volume (required water quality volume(s) x 1.20) = 10347 cubic feet illowing sections are used to calculate the required water quality volume(s) for the selected BMP.

The values for BMP Types not selected in cell C45 will show NA.

7. Retention/Irrigation System Designed as Required in RG-348 Pages 3-42 to 3-46

Required Water Quality Volume for retention basin = NA cubic feet

Irrigation Area Calculations:

Soil infiltration/permeability rate = 0.1 in/hr Enter determined permeability rate or assu

Irrigation area = NA square feet NA acres

8. Extended Detention Basin System

Designed as Required in RG-348 Pages 3-46 to 3-51

Required Water Quality Volume for extended detention basin = NA cubic feet

9. Filter area for Sand Filters Designed as Required in RG-348 Pages 3-58 to 3-63

9A, Full Sedimentation and Filtration System

Water Quality Volume for sedimentation basin = 10347 cubic feet

Minimum filter basin area = 377 square feet

Maximum sedimentation basin area = 3394 square feet For minimum water depth of 2 feet
Minimum sedimentation basin area = 849 square feet For maximum water depth of 8 feet

9B. Partial Sedimentation and Filtration System

Water Quality Volume for combined basins = 10347 cubic feet

Minimum filter basin area = 679 square feet

Maximum sedimentation basin area = 2715 square feet For minimum water depth of 2 feet
Minimum sedimentation basin area = 170 square feet For maximum water depth of 8 feet

Attachment C Suitability Letter From Authorized Agent

Attachment C is not applicable for this project. An on-site sewage facility will not be implemented for this development. A sewage collection system is proposed and an SCS Application is submitted with this application.

Attachment D Exception to the Required Geologic Assessment

Attachment D is not applicable for this project. A geological assessment exemption will not be requested. Raba Kistner has prepared a Geologic Assessment for this site, see Geologic Assessment Form and Attachments.



SECTION 5: TEMPORARY STORMWATER SECTION

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Jose M. Farias P.E.

Date: 12/10/2025

Signature of Customer/Agent:

Regulated Entity Name: MCRT SFR TEXAS CONSTRUCTION LLC

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

| 1. | Fuels for construction equipment and hazardous substances which will be used during construction: |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------|
| | The following fuels and/or hazardous substances will be stored on the site: |
| | These fuels and/or hazardous substances will be stored in: |
| | Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year. |
| | Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. |

| | Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project. |
|---------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Fuels and hazardous substances will not be stored on the site. |
| | Attachment A - Spill Response Actions . A site-specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached. |
| | Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature. |
| | Attachment B - Potential Sources of Contamination . A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached. |
| Sequ | ence of Construction |
| | Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached. |
| | For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented. |
| | Name the receiving water(s) at or near the site which will be disturbed, or which will receive discharges from disturbed areas of the project: Onion Branch |
| Tem | porary Best Management Practices (TBMPs) |
| stabiliza constru basins. | control examples: tree protection, interceptor swales, level spreaders, outlet ation, blankets or matting, mulch, and sod. Sediment control examples: stabilized ection exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment Please refer to the Technical Guidance Manual for guidelines and specifications. All ral BMPs must be shown on the site plan. |
| | Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached: |
| | A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site. |

| | A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction. |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| to | he temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided. |
| | Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. There will be no temporary sealing of naturally-occurring sensitive features on the site. |
| u d | ttachment F - Structural Practices . A description of the structural practices that will be sed to divert flows away from exposed soils, to store flows, or to otherwise limit runoff ischarge of pollutants from exposed areas of the site is attached. Placement of tructural practices in floodplains has been avoided. |
| | ttachment G - Drainage Area Map . A drainage area map supporting the following equirements is attached: |
| | For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided. For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used. |
| | For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed |
| | drainage area. There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used. |

| 11. 🔀 | Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached. |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | N/A |
| 12. 🔀 | Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP. |
| 13. | All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. |
| 14. 🔀 | If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). |
| 15. 🔀 | Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume. |
| 16. 🔀 | Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily). |
| Soil | Stabilization Practices |
| mulchi | les: establishment of temporary vegetation, establishment of permanent vegetation, ing, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or vation of mature vegetation. |
| 17. 🔀 | Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices . A schedule of the interim and permanent soil stabilization practices for the site is attached. |
| 18. 🔀 | Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated. |
| 19. 🛚 | Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased. |

Administrative Information

| 20. $igwidge$ All structural controls will be inspected and maintained accordin | g to the submitted and |
|---------------------------------------------------------------------------------|------------------------|
| approved operation and maintenance plan for the project. | |

- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

Attachment A

Spill Response Actions

If there is an accidental spill on site, the contractor shall respond with appropriate action. The contractor will be required to contact the owner and in turn the owner will contact the TCEQ in the event of a spill on site. In addition to the following guidance, reference the latest version of TCEQ's Technical Guidance Manual (TGM) RG-348 Section 1.4.16.

Cleanup and Good House Keeping

- Clean up leaks and spills immediately.
- Neat and orderly storage of any chemicals, pesticides, fertilizers, fuels, etc. that are being stored
 on site.
- Regular garbage, rubbish, construction waste and sanitary waste disposal.
- Cleanup of sediments that have been tracked by vehicles or have been transported by wind or storm water about the site or onto nearby roads.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
 - Contain the spread of the spill.
 - Recover spilled materials.
 - Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Manufacturer's recommended methods of spill cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and the cleanup supplies. Spills should be cleaned up immediately:

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.

• If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at (512)339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc. The local emergency authority, as necessary, will implement its emergency management plans, which may include notifying and evacuating affected personnel. In the absence of a local emergency authority, the contractor shall take reasonable measure to notify potentially affected persons of the imminent health threat.

Attachment B

Potential Sources of Contamination

Potential Source: Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle dripping. Any spills shall be handled according to the Spill Response Actions in *Attachment A*.

Preventative Measures: Vehicle maintenance will be performed within the construction staging area or a local maintenance shop.

Potential Source: Asphalt wash -off after unexpected rain.

Preventative Measures: After placement of asphalt, emulsion, or coatings, the applicant will be responsible for immediate cleanup should an unexpected rain occur. During the entirety of the asphalt curing time, the applicant should maintain standby personnel and equipment to contain any asphalt wash-off.

Potential Source: Miscellaneous trash and litter from construction workers and material wrappings.

Preventative Measures: Trash containers will be placed throughout the site to encourage proper disposal of trash.

Potential Source: Silt leaving the site.

Preventative Measures: Contractor will install all temporary best management practices, described in *Attachment D*, prior to start of construction including the stabilized construction entrance to prevent tracking onto adjoining streets and to prevent the discharge of sediment to the San Gabriel River.

Potential Source: Construction Debris.

Preventative Measures: Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

Potential Source: Soil and Mud from Construction Vehicle tires as they leave the site.

Preventative Measures: A stabilized construction exit shall be utilized as vehicles leave the site. Any soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

Potential Source: Sediment from soil, sand, gravel and excavated materials stock piled on site.

Preventative Measures: Silt fence shall be installed on the down gradient side of the stock piled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

Potential Source: Portable toilet spill.

Preventative Measures: Toilets on the site will be emptied on a regular basis by the contracted toilet company.

Attachment C

Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage to be disturbed is listed in parentheses next to each activity. The location of the temporary erosion control measures is shown on the Erosion & Sedimentation Control Sheets.

Intended Schedule or Sequence of Major Activities:

Site Construction:

- 1. Construct Access (0.65 acres)
- 2. Installation of Temporary BMPs (76 EA inlet protection)
- 3. Initiate Grubbing and Topsoil Stripping of Site (7.91 acres onsite)
- 4. Rough Subgrade Preparation (earthwork, grading, street and drainage excavation and embankment) (7.91 acres onsite)
- 5. Wet and Dry Utility Construction (6.6 acres)
- 6. Final Subgrade Preparation (7.91 acres)
- 7. Installation of Base Materials (7.91 acres)
- 8. Concrete (foundations, curbs, flatwork) (2.55 acres)
- 9. Building Construction (7.91 acres)
- 10. Paving Activities (1.39 acres)
- 11. Topsoil, Irrigation and Landscaping (7.91 acres)
- 12. Site cleanup and Removal of Temporary BMPs (76 EA inlet protection)

Complete any necessary final dress up of areas. Conduct a final inspection and complete all punch list items.

Attachment D

Temporary Best Management Practices and Measures

- **A.** There is no storm water that originates up gradient from the site that will flow across the site.
- **B.** Temporary BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed on site to reduce vehicle "tracking" onto adjoining streets. A concrete washout pit will be used to collect all excess concrete during construction. Inlet protection will be placed over all existing and proposed inlets to stop the discharge of sediments into the sewer system. Please reference the attached copy of the Erosion and Sedimentation Control Plans for specific locations and details of all controls.

BMPs for this project will protect surface water or groundwater from turbid water, phosphorus, sediment, oil, and other contaminants, which may mobilize in storm water flows by slowing the flow of runoff to allow sediment and suspended solids to settle out of the runoff.

Practices may also be implemented on site for interim and permanent stabilization. Stabilization practices may include but are not limited to: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of existing trees and vegetation, and other similar measures.

The contractor is expected to inspect the controls weekly and after significant rainfalls to ensure proper function.

- **C.** There are no sensitive features or surface streams within the boundaries of the project. The temporary onsite BMPs will be used to treat stormwater runoff before it leaves the project and prevent pollutants from entering into surface streams or any sensitive features down-gradient of the site.
- **D.** There were no sensitive features on the 7.91 acre site identified during the geologic assessment. However, the BMPs for this project are designed to allow water to pass through after sedimentation has occurred. Existing flow patterns will be maintained to any naturally occurring sensitive features that are discovered during construction.

Attachment E Request to Temporarily Seal a Feature

Naturally-occurring features will not be sealed on the site; therefore this section is not applicable.

Attachment F

Structural Practices

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the downgradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets. A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck washout pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all structural temporary BMP's are shown on the erosion control plan sheet and details and specifications are provided on the erosion control details sheet which can be found at the end of this report under Section 9.

Description of Temporary BMPs

Temporary Construction Entrance/Exit

The purpose of a temporary gravel construction entrance is to provide a stable entrance/exit condition from the construction site and keep mud and sediment off public roads. A stabilized construction entrance is a stabilized pad of crushed stone located at any point traffic will be entering or leaving the construction site from a public right-of-way, street, alley, sidewalk or parking area. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking or flowing of sediment onto public rights-of-way. This practice should be used at all points of construction ingress and egress.

Excessive amounts of mud can also present a safety hazard to roadway users. To minimize the amount of sediment loss to nearby roads, access to the construction site should be limited to as few points as possible and vegetation around the perimeter should be protected where access is not necessary. A rock stabilized construction entrance should be used at all designated access points.

Silt Fence

The purpose of a silt fence is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Silt fence is used during the period of construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This fence should remain in place until the disturbed area is permanently stabilized. Silt fence should not be used where there is a concentration of water in a channel or drainage way. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

Silt fencing within the site may be temporarily moved during the day to allow construction activity provided it is replaced and properly anchored to the ground at the end of the day. Silt fences on the perimeter of the site or around drainage ways should not be moved at any time.

Rock Berm

The purpose of a rock berm is to serve as a check dam in areas of concentrated flow, to intercept sediment-laden runoff, detain the sediment and release the water in sheet flow. The rock berm should be used when the contributing drainage area is less than 5 acres. Rock berms are used in areas where the volume of runoff is too great for a silt fence to contain. They are less effective for sediment removal than silt fences, particularly for fine particles, but are able to withstand higher flows than a silt fence. As such, rock berms are often used in areas of channel flows (ditches, gullies, etc.). Rock berms are most effective at reducing bed load in channels and should not be substituted for other erosion and sediment control measures further up the watershed.

Triangular Filter Dike

The purpose of a triangular sediment filter dike is to intercept and detain water-borne sediment from unprotected areas of limited extent. The triangular sediment filter dike is used where there is no concentration of water in a channel or other drainage way above the barrier and the contributing drainage area is less than one acre. If the uphill slope above the dike exceeds 10%, the length of the slope above the dike should be less than 50 feet. If concentrated flow occurs after installation, corrective action should be taken such as placing rock berm in the areas of concentrated flow. This measure is effective on paved areas where installation of silt fence is not possible or where vehicle access must be maintained. The advantage of these controls is the ease with which they can be moved to allow vehicle traffic and then reinstalled to maintain sediment.

Inlet Protection

In developments for which drainage is to be conveyed by underground storm sewers (i.e., streets with curbs and gutters), all inlets that may receive storm runoff from disturbed areas should be protected. Temporary inlet protection is a series of different measures that provide protection against silt transport or accumulation in storm sewer systems. This clogging can greatly reduce or completely stop the flow in the pipes. The different measures are used for different site conditions and inlet types

Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- · Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.
- For onsite washout:
- Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
- Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.

Below grade concrete washout facilities are typical. These consist of a lined excavation sufficiently large to hold expected volume of washout material. Above grade facilities are used if excavation is not practical. Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this section, with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.

Attachment G Drainage Area Map

An existing and proposed drainage area map is provided at the end of this report in Section 9 to support the aforementioned requirement.

Attachment H

Temporary Sediment Pond(s) Plans and Calculations

The proposed development will not disturb areas over 10 acres. Therefore, a temporary sediment pond is not proposed.

Attachment I

Inspection and Maintenance for BMPs

Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

Inspection Guidelines for BMPs

The following sections address inspection and maintenance taken from the TNRCC Manual, "Complying with Edwards Aquifer Rules: Technical Guidance on Best Management Practices."

Silt Fence:

- 1. Inspection shall be made weekly and after each rainfall event, in accordance with Section 1.4.3 of RG-348.
- 2. Torn fabric shall be replaced or a second line of fencing parallel to the torn section shall be implemented as needed.
- 3. Accumulated silt shall be removed when it reaches a depth of six (6) inches. The silt shall be disposed of on an approved site and in such a manner that will not contribute to additional siltation.
- 4. Silt fence shall be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.

Inlet Protection:

- 1. Daily inspection shall be made by the contractor and silt accumulation must be removed when depth reaches 50 millimeters (two (2) inches).
- 2. Contractor shall monitor the performance of inlet protection during each rainfall event and immediately remove the inlet protections if the stormwater begins to overtop the curb.
- 3. Inlet protections shall be removed as soon as the source of sediment is stabilized.

Stabilized Construction Fence:

- The entrance shall be maintained in a condition that will prevent tracking or flowing of sediment onto public roadway. This may require periodic top dressing with additional stone as conditions demand. As well as repair and clean out of any measure device used to trap sediment. All sediments that are spilled, dropped, washed or tracked onto a public roadway must be removed immediately.
- 2. Entrance shall be properly graded to prevent run-off from leaving the construction site.

Sediment Basins:

- Inspection should be made weekly and after each rainfall in accordance to Section 1.4.13 of RG-348.
- 2. To prevent clogging of the outlet structure of proposed water quality facilities implemented as temporary sediment basins, trash and other debris shall be removed promptly after each rainfall event.
- 3. Silt accumulation should be removed as well as basin re-graded to original dimensions once the capability of the facility has been reduced to 75% of original storage capacity.
- 4. Removed sediment should be redistributed in the respective phases' stockpiling area.

Rock Berm:

- 1. Inspection should be made weekly and after each rainfall in accordance to Section 1.4.5 of RG-348. If placed in streambeds, inspection should occur daily.
- 2. Accumulated silt shall be removed when it reached a depth of six (6) inches. The silt shall be disposed of on an approved site and in such a manner that will not contribute to additional siltation.
- 3. Loose wire sheathing shall be repaired immediately when necessary and the berm shall be reshaped as needed during inspection.

- 4. Berm shall be replaced if the structure ceases to function as initially intended due to factors such as silt accumulation, washout, construction traffic damage, etc.
- 5. When all upstream areas are stabilized and the accumulated silt has been removed, the rock berm should be removed and disposed of.

Concrete Washout:

- 1. The purpose of a concrete washout is to provide a process for cleaning off all equipment involved in the production and placement of concrete before exiting the construction limits of the subject site. These pieces of equipment typically include large concrete mixing trucks and smaller hand tools such as wheelbarrows. Upon performing a washout, the effluent water produced can be toxic and harmful to the natural environment, including, but not limited to, seepage into subsurface groundwater. The concrete washout provides a designated location for wash and proper disposal of aforementioned effluent.
- 2. Remove concrete waste in the washout area as needed to maintain BMP function (typically when two-thirds capacity). Collect concrete waste and deliver off-site to a designated disposal location.
- 3. Upon completion of concrete work and needed for washout activities, accumulated waste must be removed from the site as noted above in item #2. Wash water may be allowed to evaporate for solid disposal.

Inspection Schedule

The primary operator is required to complete inspections as specified above, and choose one of the two inspections listed below for all temporary stormwater controls not specifically listed.

| Option 1: Once every seven calendar days. If this alternative schedule is developed, then the |
|------------------------------------------------------------------------------------------------------|
| inspection must occur regardless of whether or not there has been a rainfall event |
| since the previous inspection. |
| Option 2: Once every 14 calendar days and within 24 hours of the end of a storm event of two |
| inches or greater. |

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).

If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded.

Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized;
- areas used for storage of materials that are exposed to precipitation;
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system);
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly); and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking).

Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

Inspection Report Forms

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections). Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of non-compliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

Corrective Action

Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

Corrective Action Forms

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.

Attachment J

Schedule of Interim and Permanent Soil Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, Sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a) The dates when major grading activities occur;
- b) The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c) The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more that fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.

Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

Maintenance

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)
- Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.

- Silt fence will be inspected for depth of sediment, tears, to see of the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Straw bale dike will be inspected and repaired as necessary.
- Diversion dike will be inspected, and any breaches promptly repaired.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes offsite impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must work with the owner or operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

• Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of storm water controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.



Inspector Qualifications Log*

| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience □ Other |
|--------------------------------------------------------------------------------------------------------------------------------------|
| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience □ Other |
| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience □ Other |
| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience □ Other |
| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience □ Other |
| Inspector Name: Qualifications (Check as appropriate and provide description): □ Training Course □ Supervised Experience |

^{*} The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.



Amendment Log

| No. | Description of the Amendment | Date of Amendment | Amendment Prepared by [Name(s) and Title] |
|-----|------------------------------|----------------------|----------------------------------------------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |



Construction Activity Sequence Log

| Name of Operator | Projected dates Month/year | Activity Disturbing Soil clearing, excavation, etc. | Location on-site where activity will be conducted | Acreage being disturbed |
|------------------|-------------------------------|-----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | l de la companya de l | |

^{*}Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.



Stormwater Control Installation and Removal Log

| Stormwater Control | Location On-Site | Installation Date | Removal Date |
|--------------------|-------------------------|----------------------|-----------------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | • | | |
| | • | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |



Stabilization Activities Log

| Date Activity Initiated | Description of Activity | Description of Stabilization Measure and Location | Date Activity Ceased (Indicate Temporary or Permanent) | Date When Stabilization Measures Initiated |
|----------------------------|-------------------------|------------------------------------------------------|--------------------------------------------------------------|-----------------------------------------------------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Stabilization and erosion control practices may include, but are not limited to: establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.



Inspection Frequency Log

| Date | Frequency Schedule and Reason for Change |
|------|------------------------------------------|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |



Rain Gauge Log

| Date | Location of Rain Gauge | Gauge Reading |
|------|------------------------|---------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



| General Information | | | | | | | | |
|------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|----------------------------|----------------------|--|--|--|
| Name of Project | | Tracking No. Inspection Date | | | | | | |
| Inspector Name, T Contact Information | | | | | | | | |
| Present Phase of Co | onstruction | | | | | | | |
| Inspection Location inspections are require location where this instead being conducted) | ed, specify | | | | | | | |
| - Once per n | nency: Vuency: ency: vency: Vuency: vency: vency | Weekly Every 14 days and within 24 ho Every 7 days and within 24 hours of a 0.25" r ilized areas) in 24 hours of a 0.25" rain (for arid, semi-arid, or a en conditions where earth-disturbing activities are | ain drought-stricken areas du | ring seasonally dry period | s or during drought) | | | |
| If yes, how did y ☐ Rain gauge on | Was this inspection triggered by a 0.25" storm event? ☐ Yes ☐ No If yes, how did you determined whether a 0.25" storm event has occurred? ☐ Rain gauge on site ☐ Weather station representative of site. Specify weather station source: Total rainfall amount that triggered the inspection (in inches): | | | | | | | |
| If "yes", con | ine that any mplete the fo | portion of your site was unsafe for insp | | No | | | | |
| - Location(s) where conditions were found: | | | | | | | | |



| Condition and Effectiveness of Erosion and Sediment (E&S) Controls | | | | | |
|--------------------------------------------------------------------|-----------------------------------------------|-----------------------------------|------------------------------------------------------------------------------|-------|--|
| Type/Location of E&S Control | Repairs or Other Maintenance Needed? | Corrective Action Required? | Date on Which Maintenance or Corrective Action First Identified? | Notes | |
| 1. | □Yes □No | □Yes □No | | | |
| 2. | □Yes □No | □Yes □No | | | |
| 3. | □Yes □No | □Yes □No | | | |
| 4. | □Yes □No | □Yes □No | | | |
| 5. | □Yes □No | □Yes □No | | | |
| 6. | □Yes □No | □Yes □No | | | |
| 7. | □Yes □No | □Yes □No | | | |
| 8. | □Yes □No | □Yes □No | | | |
| 9. | □Yes □No | □Yes □No | | | |
| 10. | □Yes □No | □Yes □No | | | |



| Condition and Effectiveness of Pollution Prevention (P2) Practices | | | | | |
|--------------------------------------------------------------------|-----------------------------------------------|-----------------------------------|------------------------|-------|--|
| Type/Location of P2 Practices | Repairs or Other Maintenance Needed? | Corrective Action Required? | Identification Date | Notes | |
| 1. | □Yes □No | □Yes □No | | | |
| 2. | □Yes □No | □Yes □No | | | |
| 3. | □Yes □No | □Yes □No | | | |
| 4. | □Yes □No | □Yes □No | | | |
| 5. | □Yes □No | □Yes □No | | | |
| 6. | □Yes □No | □Yes □No | | | |
| 7. | □Yes □No | □Yes □No | | | |
| 8. | □Yes □No | □Yes □No | | | |
| 9. | □Yes □No | □Yes □No | | | |
| 10. | □Yes □No | □Yes □No | | | |



| Stabilization of Exposed Soil | | | | |
|----------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|--|
| Stabilization Area | Stabilization Method | Have You Initiated Stabilization? | Notes | |
| 1. | | ☐ YES ☐ NO If yes, provide date: | | |
| 2. | | ☐ YES ☐ NO If yes, provide date: | | |
| 3. | | ☐ YES ☐ NO If yes, provide date: | | |
| 4. | | ☐ YES ☐ NO If yes, provide date: | | |
| 5. | | ☐ YES ☐ NO If yes, provide date: | | |
| | Description of l | Discharges | | |
| Was a stormwater discharge or oth If "yes", provide the following in | er discharge occurring from any par nformation for each point of dischar | rt of your site at the time of the inspec ege: | ction? | |
| Discharge Location | Observations | | | |
| 1. | Describe the discharge: | | | |
| | At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? Yes No If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue: | | | |
| 2. | Describe the discharge: | | | |
| | At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? | | | |
| 3. | Describe the discharge: | | | |
| | signs of erosion and/or sediment accum | and banks of surface waters in the immedia ulation that can be attributed to your discha- location(s) where these conditions were for e action is needed to resolve the issue: | arge? 🗌 Yes 🔲 No | |



| Contractor or Subcontractor Certification and Signature | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------|
| "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in a to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possiknowing violations." | person or persons who manage the knowledge and belief, true, |
| Signature of Contractor or Subcontractor: | Date: |
| Printed Name and Affiliation: | |
| | |
| Certification and Signature by Permittee | |
| "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations." | |
| Signature of Permittee or "Duly Authorized Representative": | Date: |
| Printed Name and Affiliation: | |



| Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action) | | | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------|------------------------------------------------|--------------|------------------------------|
| Name of Project Tracking No. | | lo. | | Today's Date | |
| Date Problem First Discovered | | | Time Problem Firs | t Discovered | |
| Name and Contact Inform | nation of Individual Completing this | | | | |
| What site conditions triggered the requirement to conduct corrective action: A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3 The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards A prohibited discharge has occurred or is occurring | | | | | |
| Provide a description of t | he problem: | | | | |
| | corrective action (Enter date that is eithork within the first 7 days, enter the da | | | | the problem, or (2) if it is |
| | If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe: | | | | |
| | Section (Complete this section <u>no later than 7 c</u> | | ctive Action Progr or discovering the condi | | |
| Section B.1 – Why the | Problem Occurred | | | | |
| Cause(s) of Problem (Add an additional sheet if necessary) | | How This Was Determined and the Date You Determined the Cause | | | |
| 1. | | 1. | | | |
| 2. | | 2. | | | |
| 3. | | 3. | | | |
| Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem | | | | | |
| List of Stormwater Contr Problem (Add an addition | ol Modification(s) Needed to Correct nal sheet if necessary) | Completion Date | SWPPP Update Necessary? | Notes | |
| 1. | | | □Yes □No Date: | | |
| 2. | | | ☐Yes ☐No Date: | | - |
| 3. | | | ☐Yes ☐No Date: | | |



| Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action) | | | | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|---------------------------------------------------------------|---------------|------------------------------|
| Name of Project Tracking No. | | | Today's Date | | |
| Date Problem First Disco | overed | | Time Problem Firs | st Discovered | |
| Name and Contact Infor | mation of Individual Completing this | | | | |
| ☐ A required stormwat☐ The stormwater cont | What site conditions triggered the requirement to conduct corrective action: A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3 The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards A prohibited discharge has occurred or is occurring | | | | |
| Provide a description of | the problem: | | | | |
| | corrective action (Enter date that is eit ork within the first 7 days, enter the da | | | | the problem, or (2) if it is |
| If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe: | | | | | |
| | Section (Complete this section no later than 7 c | | ctive Action Progr r discovering the cond | | |
| Section B.1 – Why the | e Problem Occurred | | | | |
| Cause(s) of Problem (Add an additional sheet if necessary) | | | How This Was Determined and the Date You Determined the Cause | | |
| 1. | | 1. | | | |
| 2. | | 2. | | | |
| 3. | | 3. | | | |
| Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem | | | | | |
| List of Stormwater Contr Problem (Add an addition | rol Modification(s) Needed to Correct onal sheet if necessary) | Completion Date | SWPPP Update Necessary? | Notes | |
| 1. | | | □Yes □No Date: | | |
| 2. | | | □Yes □No Date: | | |
| 3. | | | ☐Yes ☐No Date: | | |



| Contractor or Subcontractor Certification and Signature | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------|
| "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision is to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of maccurate, and complete. I am aware that there are significant penalties for submitting false information, including the poknowing violations." | ne person or persons who manage the ny knowledge and belief, true, |
| Signature of Contractor or Subcontractor: | Date: |
| Printed Name and Affiliation: | |
| | |
| Certification and Signature by Permittee | |
| "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations." | |
| Signature of Permittee or "Duly Authorized Representative": | Date: |
| Printed Name and Affiliation: | |



SECTION 6: PERMANENT STORMWATER

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(Ii), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

| Print Name of Customer/Agent: <u>Jose Farias, P.E.</u> |
|--------------------------------------------------------|
| Date: 12/10/2025 |
| Signature of Customer/Agent |
| - 3- 7- <u></u> |
| Regulated Entity Name: MCRT SFR TEXAS CONSTRUCTION LLC |

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

| 1. | Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction. |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | □ N/A |
| 2. | These practices and measures have been designed, and will be constructed, operated, and maintained to ensure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director. |
| | The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site. |

| | A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: |
|----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | □ N/A |
| 3. | Owners must ensure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion. |
| | □ N/A |
| 4. | Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes. |
| | □ The site will be used for low density single-family residential development and has 20% or less impervious cover. □ The site will be used for low density single-family residential development but has more than 20% impervious cover. □ The site will not be used for low density single-family residential development. |
| 5. | The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes. |
| | □ Attachment A - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. □ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. □ The site will not be used for multi-family residential developments, schools, or small |
| 6 | business sites. Attachment B - BMPs for Upgradient Stormwater. |
| | TAN ENGINEERE DE DIVITA IOTAUE (OUICITAU UNIVOLE). |

| | | ☑ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. ☑ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. ☑ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and |
|-----|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 7. | \boxtimes | flows across the site, and an explanation is attached. Attachment C - BMPs for On-site Stormwater. |
| ,. | | A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached. |
| 8. | | Attachment D - BMPs for Surface Streams . A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed. |
| | | N/A |
| 9. | | The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction. |
| | | The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed. Attachment E - Request to Seal Features. A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached. |
| 10. | | Attachment F - Construction Plans. All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include: |
| | | ✓ Design calculations (TSS removal calculations) ✓ TCEQ construction notes ✓ All geologic features ✓ All proposed structural BMP(s) plans and specifications |
| | | N/A |

| 11. | Attachment G - Inspection, Maintenance, Repair and Retrofit Plan . A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following: |
|-------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | □ Prepared and certified by the engineer designing the permanent BMPs and measures |
| | Signed by the owner or responsible party Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit |
| | A discussion of record keeping procedures |
| _ | N/A |
| 12 | Attachment H - Pilot-Scale Field Testing Plan . Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached. |
| | N/A |
| 13. | Attachment I -Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation. |
| \boxtimes | N/A |
| Resp | oonsibility for Maintenance of Permanent BMP(s) |
| = | nsibility for maintenance of best management practices and measures after action is complete. |
| | The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. |
| | N/A |
| _ | A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur. |
| | N/A |



Attachment A

20% or Less Impervious Cover Waiver

The site will be used for multifamily purposes but has more than 20% impervious cover. Therefore, a waiver will not be submitted for this project, and this section is not applicable.



Attachment B

BMPs for UP-GRADIENT STORMWATER

Up-gradient storm water does not apply to this development exist based on current topography maps and field observations.



Attachment C

BMPs for On-Site Stormwater

Revegetation of the site will be utilized as a permanent best management practice on this site. Revegetation is to include:

- A minimum of four (4) inches of top soil placed in all drainage channels (except rock) and between the curb and right-of-way line.
- Seeding must be provided for all permanent erosion control measures, to include broadcast seeding and hydraulic seeding.
- Planted areas shall be irrigated or sprinkled in a manner that will not erode the topsoil, but will sufficiently soak the soil to a depth of 6 inches.
- Restoration shall be acceptable when the grass has grown at least one and a half (1 $\frac{1}{2}$) inches high with 95% coverage, provided no bare spots larger than 16 square feet exist.
- Native grass seeding shall comply with the requirements of the Williamson County.

A water quality pond will be utilized as a permanent best management practice on this site. The proposed, permanent water quality pond is a wet pond with a TSS reduction efficiency of 91%. The proposed wet basin was designed to treat the additional impervious cover from the development. The total project area draining to the proposed smart batch detention pond is 73.57 acres. 31.74 acres of the total area is designated as post-development impervious cover.

Construction plans, calculations and specifications are provided in Section 9 which is located at the end of this report. The TSS Spreadsheet Calculations are included on page 49 of the Chisholm Trail Developers Venture Property Civil Construction Plans.



Attachment D BMPs for Surface Streams

There are no existing surface streams or sensitive features on the subject site. Therefore, this section is not applicable.



Attachment E

Request to Seal a Feature

The permanent sealing of or diversion of flow from a naturally-occurring "sensitive" or "possibly sensitive" feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed for any naturally-occurring "sensitive" or "possibly sensitive" features on this site; and therefore, this section is not applicable.



Attachment F

Construction Plans

Calculations for the load removal requirements for the project and the load removal provided by the permanent BMP's are provided in the Subdivision Construction Plans in Section 9 which have been signed and sealed by a professional engineer licensed in the state of Texas. The load removal requirements are derived from the equations from the technical guidance manual based upon project area and increase in impervious cover. All stormwater runoff from impervious areas will be treated by the proposed permanent BMP's to provide the overall required removal of at least 80% of the increase in Total Suspended Solids. Provided within the calculations is a summary of the amount of pollutant load required to be removed from the drainage areas and the amount of removal provided by the permanent BMP's.

Construction plans, details, specifications, calculations and construction notes for the development are provided in Section 9 which is attached at the end of this report.



Attachment G

Inspection, Maintenance, Repair and Retrofit Plan

The inspection and maintenance plan outlines the procedures necessary to maintain the performance of the Permanent Best Management Practices for this project. It should be noted that the plan provides guidelines that may have to be adjusted dependent on site specific and weather related conditions.

It is the responsibility of the owner to provide the inspections and maintenance as outlined in the plan for the duration of the project. The owner will maintain this responsibility until it is assumed or transferred to another entity in writing. If the property is leased or sold, the responsibility for the maintenance will be required to be transferred through the lease agreement, binding covenants, closing documents, or other binding legal instrument.

Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

Maintenance records shall be kept on the installation, maintenance, or removal of items necessary for the proper operation of the facilities. All inspections shall be documented.

An amended copy of this document will be provided to the Texas Commission on Environmental Quality within thirty (30) days of any changes in the following information.

MCRT SFR Investment, LLC

| Mailing Address: | _5910 N. Central Expressway, Suite 110 | 00 |
|----------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|-------------------|
| City, State: | Dallas, TX | Zip: <u>75206</u> |
| Telephone: | 210-885-4676 | Fax: |
| Plan for the proposed Permaintain responsibility f | ermanent Best Management Praetices for the implementation and execution of the day another party in writing through a | |
| This Maintenance Plan i | s based on TCEQ Maintenance Guidelin | nes. |
| By:Jose Faria | Date Date | 12/10/2025 |

Responsible Party:



Water Quality Ponds

Routine Maintenance

<u>Mowing:</u> The side-slopes, embankment, and emergency spillway of the basin should be mowed at least twice a year to prevent woody growth and to control weeds.

<u>Inspections.</u> Water Quality Ponds should be inspected at least twice a year (once during or immediately following wet weather) to evaluate facility operation. When possible, inspections should be conducted during wet weather to determine if the basin is functioning properly. There are many functions and characteristics of these BMPs that should be inspected. The embankment should be checked for subsidence, erosion, leakage, cracking, and tree growth. The condition of the emergency spillway should be checked. The inlet, barrel, and outlet should be inspected for clogging. Stability of the side slopes should be checked. Modifications to the basin structure and contributing watershed should be evaluated. During semi-annual inspections, replace any dead or displaced vegetation. Replanting of various species of wetland vegetation may be required at first, until a viable mix of species is established. Cracks, voids and undermining should be patched/filled to prevent additional structural damage. Trees and root systems should be removed to prevent growth in cracks and joints that can cause structural damage. The inspections should be carried out with As-built pond plans in hand.

<u>Debris and Litter Removal:</u> As part of periodic mowing operations and inspections, debris and litter should be removed from the surface of the basin. Attention should be paid to floatable debris, and the outlet should be checked for possible clogging.

<u>Sediment Removal:</u> Inspection of the forebay should be completed every three months for the first two years after construction completion, and during the three-month inspection cycle, if more than 15% of the forebay volume is lost, the sediment build-up should be removed. After the two-year period, the sediment forebay should be inspected every three years, and the sediment should be cleaned out if more than one-third of the forebay volume is lost. Every six years, the sediment build-up in the mail pool should be inspected and sediment should be removed if twenty percent of the main pool volume is lost.

<u>Erosion Control:</u> The basin side slopes, emergency spillway, and embankment all may periodically suffer from slumping and erosion. Corrective measures such as re-grading and re-vegetation may be necessary.

<u>Nuisance Control:</u> Most public agencies surveyed indicate that control of insects, weeds, odors, and algae may be needed in some ponds. Nuisance control is probably the most frequent maintenance item demanded by local residents. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.). Biological control of algae and mosquitoes using fish such as fathead minnows is preferable to chemical applications.

Non-Routine Maintenance

<u>Structural Repairs and Replacement:</u> The structural integrity of the embankment, outlet structure and retaining walls should be inspected during the required routine inspections. Leakage or seepage of water through the embankment must be avoided and any structural damage should be repaired immediately.

<u>Harvesting:</u> If vegetation is present on the fringes or in the pond, it can be periodically harvested and the clippings removed to provide export of nutrients and to prevent the basin from filling with decaying organic matter.



An amended copy of this document will be provided to the Texas Commission on Environmental Quality within thirty (30) days of any changes in the following information.

| Responsible Party: | MCRT SFR Investment, LLC | | |
|--------------------|----------------------------------------|------|-------|
| Mailing Address: | 5910 N. Central Expressway, Suite 1100 | | |
| City, State: | Dallas, Texas | Zip: | 75206 |
| Telephone: | 210-885-4676 | Fax: | |

I, the owner, have read and understand the requirements of the attached Inspection and Maintenance Plan for the proposed Permanent Best Management Practices for my project. I acknowledge that I will maintain responsibility for the implementation and execution of the plan until the responsibility is transferred to or assumed by another party in writing through a binding legal instrument.

Date 12/18/2024

Signature of Responsible Party _



Attachment H

Pilot-Scale Field Testing Plan

The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site; therefore pilot-scale field testing is not required for this project.

Attachment I

Measures for Minimizing Surface Stream Contamination

All flows generated onsite due to this development are conveyed through a combination of sheet flow and storm sewer systems. Ultimately the flows are conveyed to Lake Creek Branch.

The TSS removal calculations for the proposed pond are attached.

Surface streams do not exist on site. Therefore, a description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream because of the construction and development is not provided at the end of this form. All disturbed areas will be revegetated as soon as practical.



SECTION 7: ORGANIZED SEWAGE COLLECTION SYSTEM PLAN

Organized Sewage Collection System Application

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: MCRT SFR TEXAS CONSTRUCTION LLC

1. Attachment A – SCS Engineering Design Report. This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

Customer Information

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: <u>Zach Summers</u> Entity: MCRT SFR Investment, LLC

Mailing Address: 5910 N. Central Expressway, Suite 1100

 City, State: Dallas, TX
 Zip: 75206

 Telephone: 210-885-4676
 Fax: N/A

Email Address: _zsummers@mcrtrust.com

The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: Jose M. Farias, P.E.

Texas Licensed Professional Engineer's Number: 111389

Entity: Kimley-Horn

Mailing Address: 10814 Jollyville Road Avallon IV Suite 200
City, State: Austin, Texas
Telephone: 737-249-0434
Fax: N/A

Email Address: joe.farias@kimley-horn.com

Project Information

| 4. | • • • • • • • • • • • • • • • • • • • • | levelopment to be serve ance for institutional and | | oulation to be served, |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------|-------------------------------------------|
| | Multi-family: Commercial Industrial | Number of lots: Number of residential u m (not associated with a | | |
| 5. | The character and vo | olume of wastewater is s | shown below: | |
| | % Domestic % Industrial % Commingled | d | - | ns/day ns/day |
| 6. | Existing and anticipation Existing and anticipation Exist N/A | ted infiltration/inflow is | 0 gallons/day. This w | vill be addressed by: |
| | commercial, industrice The WPAP apcopy of the wPAP application of the apcopy of the a | patement Plan (WPAP) is al, or residential project plication for this develo pproval letter is attache plication for this develo ut has not been approve ication is required for an | located on the Recharg pment was approved by d. pment was submitted to ed. h associated project, but | e Zone. Pletter dated . A O the TCEQ on |
| 8. | Pipe description: | | | |
| Ta | ble 1 - Pipe Description Pipe Diameter (Inches) | on Linear Feet (1) | Pipe Material (2) | Specifications (3) |
| | 8 | 137 | PVC SDR-26 | ASTM D-3034 |
| 9. | service laterals. (2) Pipe Material - (3) Specifications - included. | | specification and class no | Do not include private |

| 10. All components of th | is sewage collection syst | em will comply with: | |
|-------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------|---------------------------------------|
| | ustin standard specificati fications are attached. | ons. | |
| 11. 🔀 No force main(s) | and/or lift station(s) are | associated with this sev | vage collection system |
| | (s) and/or lift station(s) is tation/Force Main Syste lication. | | • |
| Alignment | | | |
| | iations from uniform gra ith open cut construction | | tion system without |
| 13. X There are no dev without manhole | iations from straight alig es. | nment in this sewage co | llection system |
| manufacture For curved se construction Manholes and (14. Manholes or clean | ction system without ma r allowing pipe curvature ewer lines, all curved sew plans for the wastewater Cleanouts an-outs exist at the end o ttach additional sheet if r | e is attached. For line notes (TCEQ-059) The collection system. If each sewer line(s). The | 6) are included on the |
| Table 2 - Manholes a | nd Cleanouts | | |
| Line | Shown on Sheet | Station | Manhole or Clean- out? |
| WWL-A | 29 | 2+58.04 | Manhole |
| 15. Manholes are ins line. | stalled at all Points of Cur | vature and Points of Ter | mination of a sewer |
| 16. 🔀 The maximum sp greater than: | acing between manholes | s on this project for each | n pipe diameter is no |
| | neter (inches) | Max. Maı | nhole Spacing (feet) |
| | 5 - 15 | | 500 |
| | 6 - 30 | | 800 |
| | 6 - 48 ≥54 | | 1000 2000 |
| Attachment C – . maximum spacin | Justification for Variance of between manholes on ed in the table above. A j | this project (for each pi | ole Spacing. The oe diameter used) is |

| | Line | Sheet | Station |
|---------|------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| Table | 3 - 100-Year Floodpla | in | |
| 22. 100 | floodplain, either nat concrete-lined chann After construction is will have water-tight | complete, no part of this project curally occurring or manmade. (I nels constructed above of sewer complete, all sections located w manholes. These locations are in the Site Plan. (Do not include d above sewer lines.) | Do not include streets or lines.) ithin the 100-year floodplain listed in the table below and are |
| 22.404 | If not shown on the S sewer systems. There will be no water | ribution system for this project i lite Plan, a Utility Plan is provide er lines associated with this proje | d showing the entire water and |
| 21. Loc | cation of existing and prop | posed water lines: | |
| 20. Lat | | eral stub-outs are shown and lal will be installed during the const | |
| 19. | manholes with station no overlain by topographic | de the sewage collection system umbers, and sewer pipe stub out contour lines, using a contour in ea within both the five-year flood ge way. | ts (if any). Site plan must be terval of not greater than ten |
| 18. 🔀 | The Site Plan must have a Site Plan Scale: 1" = 30', | a minimum scale of 1" = 400'. 4 <u>0'</u> | |
| _ | | be included on the S | Site Plan. |
| Site | Plan Requireme | ents | |
| 17. 🔀 | ☐ The use of pre-cast m | nolithic, cast-in-place concrete. nanholes is requested for this pronstruction drawings, showing th | - |
| | operate and maintain the manhole spacing greater | nched and must include a letter for e system stating that it has the contract than the allowed spacing. | |

| Line | Sheet | Station |
|------|-------|---------|
| n/a | n/a | n/a |
| n/a | n/a | n/a |

| Line | Sheet | Station |
|------|-------|---------|
| n/a | n/a | n/a |
| n/a | n/a | n/a |

23. 5-year floodplain:

| After construction is complete, no part of this project will be in or cross a 5-year |
|--------------------------------------------------------------------------------------|
| floodplain, either naturally occurring or man-made. (Do not include streets or |
| concrete-lined channels constructed above sewer lines.) |

After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

| Line | Sheet | Station |
|------|-------|---------|
| n/a | n/a | n/a |

- 24. \int Legal boundaries of the site are shown.
- 25. The *final plans and technical specifications* are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must be included on the Plan and Profile sheets.

| 26. 🛚 | All existing or proposed water line crossings and any parallel water lines within 9 feet of |
|-------|---------------------------------------------------------------------------------------------|
| | sewer lines are listed in the table below. These lines must have the type of pressure |
| | rated pipe to be installed shown on the plan and profile sheets. Any request for a |
| | variance from the required pressure rated piping at crossings must include a variance |
| | approval from 30 TAC Chapter 290. |

There will be no water line crossings.

There will be no water lines within 9 feet of proposed sewer lines.

Table 5 - Water Line Crossings

| Line | Station or Closest Point | Crossing or Parallel | Horizontal Separation Distance | Vertical Separation Distance |
|-------|-----------------------------|-------------------------|--------------------------------------|------------------------------------|
| WWL-A | 1+00 | Parallel | 4' | n/a |
| WWL-A | 2+20.96 | Crossing | n/a | 1.9' |

27. Vented Manholes:

| not required A portion of the will be provided listed in the the the means of venture the alternative of the portion of the control of the c | by 30 TAC Chapter 217. This sewer line is within the led at less than 1,500-for able below and labeled within the sewer line is within the means is described on this sewer line is within the than 1500 feet located | the 100-year floodplain and the 100-year floodplain a cot intervals. These water on the appropriate profict he 100-year floodplain at the following page. The 100-year floodplain; the the following page within. No vented mare the following page. | and vented manholes er-tight manholes are le sheets. and an alternative ervals. A description of however, there is no |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------|
| Line | Manhole | Station | Sheet |
| n/a | n/a | n/a | n/a |
| Sewer lines w than 24 inche | es above the manhole in te profile sheets. These (H). | ng manholes or "manho vert are listed in the tab e lines meet the requirer | le below and labeled or |
| Line | Manhole | Station | Sheet |
| n/a | n/a | n/a | n/a |
| | nt and markings of all se stub-outs are to be inst | ns): wer line stub-outs are shealled during the constru | |
| = : | nt and markings of all lat b-outs are to be installe | r extension of public line eral stub-outs are show d during the constructio | n and labeled. |
| 31. Minimum flow veloc | ity (From Appendix A) | | |
| | es are flowing full; all slo 2.0 feet per second for t | opes are designed to pro his system/line. | duce flows equal to or |
| 32. Maximum flow veloc | city/slopes (From Appen | dix A) | |
| | es are flowing full, all slo r equal to 10 feet per se | opes are designed to pro | |

Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second. Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

Table 8 - Flows Greater Than 10 Feet per Second

| Line | Profile Sheet | Station to Station | n FPS % Slope | | Erosion/Shock Protection | |
|------|---------------|--------------------|---------------|-----|-----------------------------|--|
| n/a | n/a | n/a | n/a | n/a | n/a | |
| n/a | n/a | n/a | n/a | n/a | n/a | |
| n/a | n/a | n/a | n/a | n/a | n/a | |

| 33. | Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provisions noted |
|-----|---------------------------------------------------------------------------------------------|
| | below have been made to protect against pipe displacement by erosion and/or shock under |
| | 30 TAC §217.53(I)(2)(B). |
| | Concrete encasement shown on appropriate Plan and Profile sheets for the locations |
| | listed in the table above. |

| Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on |
|-----------------------------------------------------------------------------------|
| appropriate Plan and Profile sheets for the locations listed in the table above. |

 \bowtie N/A

Administrative Information

- 34. The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
- 35. Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

Table 9 - Standard Details

| Standard Details | Shown on Sheet |
|-------------------------------------------------------------------------------------------------------------------------|----------------|
| Lateral stub-out marking [Required] | n/a |
| Manhole, showing inverts comply with 30 TAC §217.55(l)(2) [Required] | 34 |
| Alternate method of joining lateral to existing SCS line for potential future connections [Required] | n/a |
| Typical trench cross-sections [Required] | 34 |
| Bolted manholes [Required] | 34 |
| Sewer Service lateral standard details [Required] | n/a |
| Clean-out at end of line [Required, if used] | 34 |
| Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps] | n/a |

| Standard Details | Shown on Sheet |
|-------------------------------------------------------------------------------------------------------------------------|----------------|
| Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed] | 34 |
| Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used] | n/a |
| Drop manholes [Required, if a pipe entering a manhole is more than 24 inches above manhole invert] | n/a |

- 36. All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
- 37. All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
 - Survey staking will be completed on this date: **01/10/2025**
- 38. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 39. Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: Jose M. Farias, P.E.

Date: <u>12/9/2024</u>

Place engineer's seal here:

JOSE M. FARIAS

111389

7/CENSE

Signature of Licensed Professional Engineer:

Appendix A-Flow Velocity Table

Flow Velocity (Flowing Full) All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Table 10 - Slope Velocity

| Pipe Diameter(Inches) | % Slope required for minimum flow velocity of 2.0 fps | % Slope which produces flow velocity of 10.0 fps | | | |
|-----------------------|-------------------------------------------------------|--------------------------------------------------|--|--|--|
| 6 | 0.50 | 12.35 | | | |
| 8 | 0.33 | 8.40 | | | |
| 10 | 0.25 | 6.23 | | | |
| 12 | 0.20 | 4.88 | | | |
| 15 | 0.15 | 3.62 | | | |
| 18 | 0.11 | 2.83 | | | |
| 21 | 0.09 | 2.30 | | | |
| 24 | 0.08 | 1.93 | | | |
| 27 | 0.06 | 1.65 | | | |
| 30 | 0.055 | 1.43 | | | |
| 33 | 0.05 | 1.26 | | | |
| 36 | 0.045 | 1.12 | | | |
| 39 | 0.04 | 1.01 | | | |
| >39 | * | * | | | |

^{*}For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula



Attachment A

Engineer's Design Report

This Engineering Design Report has been prepared to comply with the Texas Commission on Environmental Quality Design Criteria for Domestic Wastewater Systems, 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable. Please note that throughout this application, the more stringent of AWU or TCEQ regulations shall apply.

Project Description

Introduction

The subject property containing the Project is located west of IH-35, bordered by Anderson Mill Road to the south and Morris Road to the east in Austin, Texas. The Project will include an overall ± 7.91 -acre tract with a new multifamily development.

This project is located within Lake Creek. The proposed site is not located in the Federal Emergency Management Agency's 100-year floodplain according to the FEMA FIRM map 48491C0610F dated December 20th 2019.

The entire ± 7.91 -acre tract is located within the Edwards Aquifer Recharge Zone. There are no known critical water quality zones or critical environmental features located on-site.

Pipe Design

Flow Design Basis

The build-out of the multifamily site will be served by this wastewater system. The City of Austin Criteria Manuals were used to determine the parameters for the design of the wastewater line extension.

Gravity Pipe and Joint Materials

The proposed pipe to be used for the 8-inch wastewater line will be ASTM D3034 SDR-26 PVC pipe (cell class 12454). The joints for this pipe shall meet the requirements of ASTM D3212. The pipe joints shall have an integral bell and rubber gasket seal with the locked-in type gasket.

Separation Distances for Water and Wastewater

At all waterline crossings a two-foot vertical separation is maintained. A nine-foot minimum horizontal separation is maintained between all proposed wastewater infrastructure and existing and proposed public water supply lines.

Building Laterals and Taps

A single service lateral is provided for the multifamily development.

Boring and Tunneling of Crossings

No boring or tunneling of crossings are proposed for this project.

Corrosion Potential

PVC pipe will be utilized for or all proposed wastewater lines. No deterioration of the proposed pipe or its associated components is anticipated in this application.



Odor Control

No odor control is proposed with this project.

Active Geologic Faults

Per the Geologic Assessment, no active geologic faults were located within the area of the project.

Capacity Analysis

The capacity of each proposed wastewater segment is calculated below based on Manning's Equation. The calculation for each segment is based on the minimum proposed slope.

$$Q = \frac{1.49}{n} * A * R^{0.67} * S^{0.5}$$

Where:

Qfull = flow rate of fluid in pipe at full flow (ft³/s) (cfs)

Q90%= flow rate of fluid in pipe at 90% full flow (ft³/s) (cfs)

A = area of pipe (ft^2) =
$$\frac{\pi * d^2}{4}$$

d = internal pipe diameter (ft) = Do - 2t

Do = outside diameter (in) t = pipe wall thickness (in)

n = Manning's Roughness coefficient = 0.013

Rfull = hydraulic radius of pipe (full flow) = A/P = D/4 (ft)

R90%= hydraulic radius of pipe (90% full flow) = 0.9*A/P = 0.9*D/4 (ft)

P = wetted perimeter of pipe = \mathcal{T} *D (ft)

S = slope of energy line

| | LENGTH | AVERAGE SLOPE | PIPE DI | AMETER | | PW | Α | Rfull | R90% | Qfull | Q90% | Vfull | V90% |
|-------------------|--------|---------------|---------|--------|-----------|------|------|-------|------|-------|------|-------|------|
| PIPE-ID | FT | FT/FT | IN | FT | MANNING'S | FT | SF | FT | FT | CFS | CFS | FPS | FPS |
| EX MH TO WWL-A MH | 137 | 0.005 | 8 | 0.67 | 0.013 | 2.09 | 0.35 | 0.17 | 0.15 | 0.85 | 0.77 | 2.44 | 2.20 |

The proposed wastewater line installed at the slope specified provides capacity in excess of the calculated peak wet weather design flows at full flow and 90% full flow conditions.

Structural Analysis

Flexible pipe is proposed on this project. Structural calculations are provided for the flexible pipe to be installed. The proposed collection system piping is designed to have a minimum structural life of 50 years. As previously mentioned, all proposed PVC pipe shall be cell class 12454 with a tensile strength of 7,000 psi.

Live Load Calculations - no significant live loads are anticipated on any segment of this project.

Buckling Pressure - the following equations utilized for the calculation of buckling pressure are taken from the Handbook of PVC Pipe: Design and Construction (Uni-Bell PVC Pipe Association, 2001).

Kimley » Horn

Pcr =
$$\frac{2*E}{(1-v^2)*(DR-1)^3}$$
 (Equation 7.14)

Pb =
$$1.15 * \sqrt{Pcr * E'}$$
 (Equation 7.18)

$$H = (Pb*144)/w$$
 (Equation 6.7)

Where:

Pcr = critical buckling pressure (psi)

E = modulus of elasticity (psi) = 400,000 psi for PVC

v = Poisson's Ratio = 0.38 for PVC

DR = dimension ratio

Pb = buckling pressure in soil (psi)

E' = modulus of soil reaction (psi) = 2,000 psi for crushed rock compacted to greater than 95% relative

density

H = maximum allowable cover height of soil (ft)

 $w = weight of soil (lbs/ft^3) = 120 lbs/ft^3$

8" ASTM D3034 SDR-26

$$Pcr = \frac{2*400,000}{(1-0.38^2)*(26-1)^3}$$

Pcr = 59.84 psi

Pb =
$$1.15 * \sqrt{59.84 * 2,000}$$

Pb = 397.84 psi

H = (397.84*144) / 120

H = 477.41 ft height of soil to cause pipe buckling

Prism Load Calculations - the following equations utilized for the calculation of prism loads are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

 $P = H^*w$ (Equation 6.7)

Where:

P = prism load pressure due to soil weight (lbs/ft²)

H = depth of pipe (ft)

 $w = soil density (lbs/ft^3) = 120 lbs/ft^3$

8" ASTM D3034 SDR-26

H = 15' (Max Depth for System)

P = 15 * 120



$P = 1.800 \text{ lbs/ft}^2 \text{ or } 12.50 \text{ psi}$

Long Term Deflection Calculations - the following equations utilized for the calculation of long term deflection are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$\Delta Y/D = \frac{DL*K*P+K*W_{\perp}}{[2E/(3(DR-1)^{3})]+0.061*E'}*100$$
 (Equation 7.10)

Where:

 $\Delta Y/D$ = long term deflection (%)

DL = Deflection Lag Factor = 1.0 for prism load calculation

K = bedding constant = 0.096 for 90°

P = prism load pressure due to soil weight (lbs/ft²)

 $W_1 =$ live load (psi) = 0 psi

E = modulus of elasticity (psi) = 400,000 psi for PVC

DR = dimension ratio

E' = modulus of soil reaction (psi) = 2,000 psi for crushed rock bedding compacted to greater than 95% relative density

Note: Leonhardt's Zeta factor is assumed to equal 1, and thus is not required in the calculation. This is a conservative assumption that results in a more conservatively calculated value for long term deflection.

8" ASTM D3034 SDR-26

$$\Delta Y/D = \frac{1.0*0.096*12.50 + 0.096*0}{[2(400,000)/(3(26-1)^3)] + 0.061*2,000} *100$$

 $\Delta Y/D = 0.86\%$

Wall Crushing Calculations - the following equations utilized for the calculation of wall crushing are taken from the Handbook of PVC Pipe: Design and Construction (Uni-Bell PVC Pipe Association, 2001).

$$Py = \frac{\Theta c * 2 * A}{D}$$
 (Equation 7.20)

$$H = Py / w$$
 (Equation 6.7)

Where:

Py = pressure due to soil weight (psi)

 Θc = compressive stress (psi) = 4,000 psi for PVC pipe

A= surface area of the pipe wall (in²/in)



D = mean pipe diameter (in) = Do - t

t = pipe wall thickness (in)

H = maximum allowable height of cover (ft)

 $w = soil density (lbs/ft^3) = 120 lbs/ft^3$

8" ASTM D3034 SDR-26

 $D = 6.275 - 0.241 = 6.034 \text{ in}, A = 2.89 \text{ in}^2/\text{ft} (0.241 \text{ in} * 12 \text{ in}/\text{ft})$

$$Py = \frac{4,000*2*(2.89/12)}{6.034}$$

Py = 319.30 psi

H = (319.30*144) / 120

H = 383.16 ft height of soil to cause wall crushing

8" ASTM D3034 SDR-26

Do = 8.40 - 0.323 = 8.077 in, A = 3.88 in²/ft (0.323 in * 12 in/ft)

$$Py = \frac{4,000 * 2 * (3.88/12)}{8.077}$$

Py = 320.25 psi

H = (320.25*144) / 120

H = 384.30 ft height of soil to cause wall crushing

Strain Calculations - the following equations utilized for the calculation of strain are taken from the Handbook of PVC Pipe: Design and Construction (Uni-Bell PVC Pipe Association, 2001).

$$\epsilon h = \frac{P*D}{2*t*E}$$
(Equation 7.22)

$$\varepsilon f = \frac{t}{D} * \frac{[3 * \Delta Y/D]}{[1 - 2 * \Delta Y/D]}$$
 (Equation 7.24)

$$\varepsilon = \varepsilon h + \varepsilon f$$
 (Equation 7.25)

Where:

εh = maximum strain in the pipe wall due to hoop stress (in/in)

P = prism load pressure due to soil weight (psi)

D = mean pipe diameter (in) = Do - t

t = pipe wall thickness (in)

E = modulus of elasticity (psi) = 400,000 psi for PVC

εf = maximum strain in the pipe due to ring deflection or flexure (in/in)

 $\Delta Y/D$ = long term deflection

 ε = maximum combined strain in pipe wall (in/in)



8" ASTM D3034 SDR-26

$$\epsilon h = \frac{12.50 *6.034}{2 *0.241 *400,000}$$

 $\epsilon h = 0.00039 \text{ in/in}$

$$\varepsilon f = \frac{0241}{6.034} * \frac{[3*0.0086]}{[1-2*0.0086]}$$

 $\varepsilon f = 0.00105 \text{ in/in}$

 $\varepsilon = 0.00039 + 0.00105$

 $\epsilon = 0.00144 \text{ in/in}$

8" ASTM D3034 SDR-26

$$\epsilon h = \frac{10.00*8.077}{2*0.323*400,000}$$

 $\epsilon h = 0.00031 in/in$

$$\varepsilon f = \frac{0.323}{8.077} * \frac{[3 * 0.0069]}{[1 - 2 * 0.0069]}$$

 $\varepsilon f = 0.00084 \text{ in/in}$

 $\varepsilon = 0.00031 + 0.00084$

 $\epsilon = 0.00115 in/in$

Per the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001), deflection test samples have experienced a pipe wall strain of up to 0.025 in/in and have not "showed any failures or cracks". The calculated strains for this project are significantly below this level, so no failure due to strain is anticipated.

Pipe Stiffness Calculation - the following equations utilized for the calculation of pipe stiffness are taken from the *Handbook of PVC Pipe: Design and Construction* (Uni-Bell PVC Pipe Association, 2001).

$$Ps = 4.47 * \frac{E}{(DR-1)^3}$$
 (Equation 7.3)

Where:

Ps = pipe stiffness (psi)

DR = Dimensional Ration = Do / t

Do = Outside diameter (in)

t = pipe wall thickness (in)

E = modulus of elasticity (psi) = 400,000 psi for PVC

6" & 8" ASTM D3034 SDR-26



$$DR = 26$$

$$Ps = 4.47 * \frac{400,000}{(26-1)^3}$$

Ps = 115 psi

| Total Site Area = | | | | | | | | | | |
|-------------------|---------------------|---------------------------------|---------------------|------------------|-----|--------------------------------------|------|--------------------------------------|------------------------------|--------------------------------|
| | | | | | | | | | | |
| Development Tract | <u>Proposed Use</u> | Proposed Bldg, SF/# Units | LUE Conversion** | Proposed LUEs | | WW Avg. Dry Weather Flow (gpm) | | WW Peak Dry Weather Flow (gpm) | Infiltration Area (acres) | WW Peak Wet Weather Flow (gpm) |
| Marielle Condos | Condo [units] | 143 | 0.7 LUE/unit | 101 | 101 | 17.2 | 4.00 | 68.7 | 7.91 | 72.9 |
| | | | | | | | | | | |

* Required Fire Flow based on the 2021 International Fire Code requirements and determined using the following assumptions:

A) Actual building types may change based on final construction drawings

B) 2 Hour Fire Walls shall be provided between each of the units

**LUE Conversions based on the following assumptions:

A) Condo consists of 6+ Units/AC to 24+ Units/AC

This project generates approximately 72.9 GPM of Peak Wet Weather Flow. Per coordination with the City of Austin Public Works department, there will be no adverse impacts or capacity issues within the existing downstream collection system and off-site wastewater treatment system.

Criteria for Laying Pipe

Pipe Embedment

Bedding and initial backfill material selection and installation will be carried out in accordance with applicable governing procedures contained within the *City of Austin Criteria Manual, TCEQ Chapter 217.54(a)*, and in accordance with the City of Austin Details on sheets 34 and 35. Brush, debris, and junk shall not be utilized as a backfilling material.

Compaction

Trench compaction will be carried out in accordance with the *City of Austin Code of Ordinances* and *TCEQ Chapter 217.54(b)*. Proper placement of the backfill and compaction per City of Austin requirements will not negatively impact the structural integrity of the pipe.

Envelope Size

Envelope size will be in accordance with *City of Austin Code of Ordinances* and *TCEQ Chapter 217.54(c)*. Per the City of Austin Detail 1100S-2 on sheet 34, a minimum of 6-inch and maximum of 24-inch space shall be allowed between the outside diameter of the pipe and the trench wall and floor. The embedment and initial backfill must be installed to a minimum depth of 12 inches above the crown of the pipe.

Trench Width

Trench width will be in accordance with the *City of Austin Code of Ordinances* and *TCEQ Chapter 217.54(d)*. Per the City of Austin Detail 1100S-2 on sheet 34, a minimum of 6-inch and maximum of 24-inch space shall be allowed between the outside diameter of the pipe and the trench wall and floor. These



limits shall be maintained to protect the structural integrity of the pipe and will be sufficient for the placement of materials and use of compaction equipment in the pipe zone.

Manholes and Related Structures

Manhole and Appurtenance Placement

Manholes are located at all points of change in alignment or grade and at the intersection of all pipes for this project.

Manhole Stub Outs

No manhole stub outs are proposed in this project.

Cleanouts

Cleanouts are proposed along the wastewater line and all dead ends.

Manhole Material

Monolithic or precast manholes are acceptable for the contractor to utilize and are included in the City of Austin Detail 506S-10.

Manhole Spacing

Manhole spacing meets the requirements of Table C.2 in TCEQ Chapter 217.55.

Manholes within Waterways

No manholes will be located within flow paths of waterways or in areas where water ponding is probable.

Manhole Covers, Inlets, and Bases

Per the *City of Austin Code of Ordinances*, the manhole covers shall have a 32-inch diameter clear opening. Manhole covers shall be constructed of cast iron and have no openings for water to infiltrate. No proposed manholes are located within the 100-year flood plain. All manholes shall be watertight, with watertight rings and covers, as shown per the City of Austin detail 506S-10. As shown in the project details, the bottom of the manhole shall have a U-shaped channel to provide smooth continuation between the inlet and outlet pipes. For the proposed pipe, the manhole channel depth shall be equal to at least half the largest pipe diameter. Manholes with different pipe sizes shall have the tops of the pipes at the same elevation and flow channels in the invert sloped evenly from pipe to pipe. A bench will be provided above each manhole channel to slope at a minimum of 0.5 inches per foot.

Manhole Steps

No steps shall be allowed in any proposed manholes.

Manhole Connections

Manhole-pipe connections shall be watertight per City of Austin Code of Ordinances. See City of Austin detail 506S-10.



Manhole Venting

The proposed manholes are spaced at less than 500-foot intervals and none are located within the 100-year flood plain. Therefore, no vented manholes are proposed in this project.

Trenchless Pipe Installation

There will be no trenchless pipe installation.

Testing Requirements for Gravity Pipes

Infiltration/Exfiltration and Low Pressure Air Test

All testing will be in compliance with Texas Administrative Code title 30 Part 1 Chapter 217 Subchapter C 217.57 and 217.58. Infiltration and exfiltration or low-pressure air testing in accordance with ASTM C828, C924 or F1417 are required for all proposed gravity wastewater pipe as specified in the project notes. The requirements specified are in accordance with *TCEQ Chapter 217.57*.

Deflection Testing

For the proposed 8-inch wastewater line, deflection shall be measured with a rigid mandrel. The requirements specified are in accordance with *TCEQ Chapter 217.57*.

Owner Inspection

The Owner shall have an inspector onsite during construction of the project. A professional engineer registered in the state of Texas (Jose Farias, P.E.) shall be present to witness the testing of the wastewater lines.

Testing Requirements for Manholes

Manhole testing in accordance with TCEQ Chapter 217.58 is specified in the project notes. Manholes will be tested after assembly and backfilling for leakage by either a hydrostatic test and/or a vacuum test. For the vacuum test, all lift holes and exterior joints shall be plugged with an approved non-shrink grout and no grout shall be placed in horizontal joints before testing. All pipes entering the manhole shall be plugged, taking care to securely brace the plugs from being drawn into the manhole. Stub outs, manhole boots and pipe plugs shall be secured to prevent movement while the vacuum is drawn. A minimum 60inch/lb torque wrench shall be used to tighten the external clamps that secure the test cover to the top of the manhole. The test head shall be placed at the inside of the top of the cone section and the seal inflated in accordance with the manufacturer's recommendation. A vacuum of 10 inches of mercury shall be drawn and the vacuum pump shut off. With the valves closed, the time shall be measured for the vacuum to drop to 9 inches of mercury. The manhole shall pass if the time is greater than 2 minutes. If the manhole fails the initial test, necessary repairs shall be made with a non-shrink grout while the vacuum is still being drawn. If the manhole fails a second time, repairs should again be made, and the manhole shall be tested by means of a hydrostatic test. If any manhole fails the hydrostatic test, after failing the vacuum test twice, the contractor should consider replacing that manhole. If the contractor chooses to attempt to repair that manhole, the manhole must be retested by means of the hydrostatic test until it passes.

Inspection will be provided during critical phases of construction by a qualified inspector under the direction of a P.E. (Jose Farias, P.E.). Critical phases of construction are deemed at a minimum to include testing of pipe and manholes for leakage and testing of flexible pipe for installed deflection.



TCEQ approval letters for plans and specifications review contain the requirement that once the project is completed, a P.E. registered in the state of Texas (Jose Farias, P.E.) much certify that the construction was performed substantially in accordance with the approved plans and specifications.

Notification and Inspection

TCEQ Chapter 213 requires that the applicant must provide written notification to the Austin regional office at least 48 hours prior to commencing construction on the regulated activity. If any sensitive feature is discovered during construction, then the work shall be suspended immediately, and the Austin regional office shall be notified to then determine the appropriate course of action. All other notification and inspection requirements identified in TCEQ Chapter 213.5(c) shall be met. Justification and Calculations for Deviation in Straight Alignment without Manholes.



Attachment B Justification and Calculations for Deviation in Straight Alignment Manholes

Attachment C Justification for Variance from Manhole Spacing



Attachment D Explanation of Slopes for Flows Greater Than 10.0 FPS





SECTION 8: ADDITIONAL FORMS

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

| hay | Tunucok | 190 |
|-----------------|-------------------------------------|-----|
| | Print Name | |
| V | Title - Owner/President/Other | |
| | Title - Owner/President/Other | |
| of <u>M:U</u> | Corporation/Partnership/Entity Name | |
| | Corporation/Partnership/Entity Name | |
| have authorized | Jose Farias, P.E. | |
| | Print Name of Agent/Engineer | |
| of | Kimley-Horn and Associates, LLC | |
| | Print Name of Firm | |

to represent and act on the behalf of the above-named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

| SIGNATURE PAGE: | |
|-----------------------------------------|---------------------------------------------|
| | |
| te de | 2/2/ |
| Applicant's Signature | |
| , pp. sam de sam | |
| | |
| THE STATE OF Tens | _§ |
| County of 1 - wig § | |
| | 7 5 |
| known to me to be the person wh | uthority, on this day personally appeared |
| | 2015 |
| GIVEN under my hand and seal | of office on this 20th day of February 2025 |
| | |
| | NOTARY PUBLIC |
| TATE SULLIVAN My Notary ID # 130370506 | The Julium |
| Expires September 16, 2027 | Typed or Printed Name of Notary |
| | MY COMMISSION EXPIRES: 9 /16 /2027 |
| | |

Application Fee Form

Texas Commission on Environmental Quality Name of Proposed Regulated Entity: MCRT SFR Texas Construction LLC Regulated Entity Location: 5910 N. Central Expressway, Suite 1100 Name of Customer: Zach Summers Contact Person: Jose Farias Phone: 737-249-0434 Customer Reference Number (if issued): CN ____605974344_____ Regulated Entity Reference Number (if issued): RN Austin Regional Office (3373) Hays Travis San Antonio Regional Office (3362) Medina Uvalde Bexar Kinney Comal Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: Austin Regional Office San Antonio Regional Office Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier 12100 Park 35 Circle **Revenues Section** Building A, 3rd Floor Mail Code 214 P.O. Box 13088 Austin, TX 78753 (512)239-0357 Austin, TX 78711-3088 Site Location (Check All That Apply): Recharge Zone Contributing Zone Transition Zone Type of Plan Size Fee Due Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling Acres \$ Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks Acres \$ Water Pollution Abatement Plan, Contributing Zone 7.91 Acres \$5,000 Plan: Non-residential Sewage Collection System 137 L.F. \$ 650 \$ Lift Stations without sewer lines Acres Underground or Aboveground Storage Tank Facility Tanks \$ Piping System(s)(only) Each Each \$ Exception

Signature:

Extension of Time

Date: 2/5/2025

Each

\$

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

| Project | Project Area in Acres | Fee |
|---------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------|------------------------------------------------------------------------|
| One Single Family Residential Dwelling | < 5 | \$650 |
| Multiple Single Family Residential and Parks | < 5 5 < 10 10 < 40 40 < 100 100 < 500 ≥ 500 | \$1,500 \$3,000 \$4,000 \$6,500 \$8,000 \$10,000 |
| Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur) | <1 1<5 5<10 10<40 40<100 ≥100 | \$3,000 \$4,000 \$5,000 \$6,500 \$8,000 \$10,000 |

Organized Sewage Collection Systems and Modifications

| Project | Cost per Linear Foot | Minimum Fee- Maximum Fee |
|---------------------------|-------------------------|-----------------------------|
| Sewage Collection Systems | \$0.50 | \$650 - \$6,500 |

Underground and Aboveground Storage Tank System Facility Plans and Modifications

| Project | Cost per Tank or Piping System | Minimum Fee- Maximum Fee |
|---------------------------------------------------|-----------------------------------|-----------------------------|
| Underground and Aboveground Storage Tank Facility | \$650 | \$650 - \$6,500 |

Exception Requests

| Project | Fee |
|-------------------|-------|
| Exception Request | \$500 |

Extension of Time Requests

| Project | Fee |
|---------------------------|-------|
| Extension of Time Request | \$150 |



Check Payable to the "Texas Commission on Environmental Quality"



Core Data Form



TCEQ Core Data Form

TCEQ Use Only

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

| 1 Reason fo | r Suhmis | sion (If other is cl | hacked nlease | describ | o in snace | nrovid | od) | | | | |
|------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------|------------------------------|--------------------|------------|-------------------------------|----------|-------------|--------------------|------------|--------------------|--------------------------|
| | | stration or Authoriz | • | | • | • | , | h the program a | pplicatio | n.) | |
| ☐ Renewal (Core Data Form should be submitted with the renewal form) ☐ Other | | | | | | | | | | | |
| 2. Customer | Referenc | e Number (if iss | ued) | Follow th | his link to se | arch | 3. Reg | ulated Entity R | eference | e Number <i>(i</i> | f issued) |
| CN 6059 | | | | for CN o | or RN number tral Registry | ers in | RN | - | | | , |
| SECTION II: Customer Information | | | | | | | | | | | |
| | neral Customer Information 5. Effective Date for Customer Information Updates (mm/dd/yyyy) | | | | | | | | | | |
| ☐ New Cust☐ Change in | | me (Verifiable with | • | | o Customer of State or | | | | • | • | Entity Ownership |
| The Custo | mer Nan | ne submitted | here may be | upda | ated auto | matic | cally b | ased on wha | t is cu | rrent and | active with the |
| | | f State (SOS) | • | - | | | - | | | | |
| 6. Customer | Legal Naı | ne (If an individual, | , print last name | first: eg: | Doe, John) | | <u>If r</u> | new Customer, ei | nter previ | ous Custome | er below: |
| Zach Sum | | | | | | | | | | | |
| 7. TX SOS/CI | PA Filing | Number | 8. TX State T | ax ID (1 | 11 digits) | | 9. | Federal Tax ID | (9 digits) | 10. DUNS | S Number (if applicable) |
| 11. Type of C | ustomer: | | on | | ☐ Individ | dual | | Partnership: | ☐ Gener | al Limited | |
| Government: | City (| County Federal | State Other | | ☐ Sole F | Proprie | torship | Other: | | | |
| 12. Number o | of Employ 21-100 | rees 101-250 | <u>251-500</u> | ☐ 5(| 01 and high | · | | . Independently | y Owned | and Opera | ted? |
| | _ | oposed or Actual) – | | | | | n this for | | | following | |
| Owner Occupation | nal Licens | ⊠ Operati ee ☐ Respo | or nsible Party | | Owner & | • | | olicant 🔲 O | ther: | | |
| | 5910 N | N. Central Ex | pressway, S | Suite 1 | 1100 | | | | | | |
| 15. Mailing Address: | | | | | | | | | | | |
| 714410001 | City | Dallas | | Sta | ite TX | - | ZIP | 75206 | | ZIP + 4 | |
| 16. Country I | Mailing In | formation (if outside | de USA) | | | 17. E | E-Mail A | ddress (if applica | able) | | |
| | | | | | | | | | | | |
| 18. Telephon | e Numbe | ſ | , | 19. Ext | ension or | Code | | 20. Fax | Numbe | r (if applicat | ole) |
| () | - | | | | | | | (|) | - | |
| SECTION | III: R | egulated En | tity Infori | matio | <u>on</u> | | | | | | |
| 21. General F | Regulated | Entity Informati | on (If 'New Reg | gulated | Entity" is s | elected | d below | this form should | be acco | mpanied by | a permit application) |
| ☐ New Regu | ulated Enti | ty 🛛 Update | to Regulated E | ntity Na | ame 🖂 | Updat | e to Reg | julated Entity Inf | ormation | 1 | |
| _ | | • | • | • | | ordei | r to me | et TCEQ Ag | ency D | ata Stand | lards (removal |
| | | ndings such a | | · | • | io tale! | na nlass | | | | |
| | | ame (Enter name of | oi the site where | ıne regu | Jiated action | is takir | ig place., | | | | |
| MCRT SF | K Inves | tment, LLC | | | | | | | | | |

TCEQ-10400 (02/21) Page 1 of 2

| 23. Street Address | s of | 5910 N. Central Expressway, Suite 1100 | | | | | | | | | | | | |
|--------------------------------------------------------------------------|------------|----------------------------------------|-------------|-----------------------------------------------|------------------------------------|---------|---------------------------|---------------------------|-----------------|-------------|------------------------------|---------------------|-------|-------------------|
| the Regulated Ent | | | | | | | T | • | | | | | | T |
| (No PO Boxes) | (| City | Dalla | ıs | State | | TX | ZIP | | 75206 | | ZIP + | 4 | |
| 24. County |] | Dallas | | | | | | | | | | | | |
| | | E | nter Phy | sical Lo | cation Desc | riptic | on if no str | eet ado | dress i | s prov | ided. | | | |
| 25. Description to Physical Location | | 3220 Morris Road | | | | | | | | | | | | |
| 26. Nearest City | , | | | | | | | | 5 | State | | | Nea | rest ZIP Code |
| Austin | | | | | | | | | Т | X | | , | 787 | 29 |
| 27. Latitude (N) In | Decima | l: | 30.45 | 76530 | | | 28. L | ongitu | de (W) | | | -97.76 | 688 | |
| Degrees | N | Minutes | | Se | econds | | Degree | es | | | Minutes | | | Seconds |
| | | | | | | | | | | | | | | |
| 29. Primary SIC Co | ode (4 dig | gits) 30. | Seconda | ary SIC (| Code (4 digits) | | 31. Primai (5 or 6 digits | • | CS Cod | de | 32. S 6 (5 or 6 | econdary digits) | NAI | CS Code |
| 6531 | | | | | | | • | 53131 | 1 | | | | | |
| 33. What is the Pri | imary Bı | usiness of | f this ent | ity? (E | o not repeat the | e SIC d | or NAICS desc | cription.) | Real | Estate | Investmer | nt and Dev | elop | ment Company |
| | | | | | | | | | | | | | | |
| O.4. Mailian | | | | | 59 | 10 N | . Central E | xpress | sway, S | Suite 1 | 100 | | | |
| 34. Mailing Address: | | | | | | | | | | | | | | |
| Address. | | City | Mar | nchaca | State | | TX | ZI | Р | 7 | 8652 | ZIP + | 4 | |
| 35. E-Mail Ad | dress: | | • | | | | | • | • | | | • | | |
| 36. To | elephon | e Number | • | | 37. Exte | nsio | n or Code | | | 38 | 3. Fax Nu | mber (if a | ppli | cable) |
| () - | | | | | | | () - | | | | | | | |
| 89. TCEQ Programs a porm. See the Core Data | | | | | | e peri | mits/registrat | tion nun | nbers th | at will b | e affected | by the upd | ates | submitted on this |
| ☐ Dam Safety | | District | | ar garaario | | | | ☐ Emissions Inventory Air | | | ☐ Industrial Hazardous Waste | | | |
| | | | | | | | | | | | | | | |
| ☐ Municipal Solid Wa | aste | ☐ New Source Review Air | | | OSSF | | ☐ Petroleum S | | um Storage Tank | | ☐ PWS | | | |
| | | _ | | | | | | | | | | | | |
| Sludge | | Storm \ | Water | | ☐ Title V Air ☐ | | | ∐ Ti | Tires | | | Used Oil | | |
| ☐ Voluntary Cleanup | | ☐ Waste | \Mater | | ☐ Wastewater Agriculture ☐ Water I | | | | lator Did | ater Rights | | | ır. | |
| U Voluntary Cleanup | <u>'</u> | waste | vvalei | | wastewa | ilei A | gricuiture | ☐ Water Rights | | | | Other: | | |
| SECTION IV: | Pren | arer In | ıforms | ation | | | | | | | | | | |
| 40. Joe Fari | | | | | | | 41. Title: | P | rojec | t Mai | nager | | | |
| 42. Telephone Num | ber 43 | . Ext./Cod | le | 44. Fax | Number | | 45. E-M | ail Add | Iress | | | | | |
| (737)249-0434 | | | | () | - | | joe.far | ias@ | kiml | ey-ho | orn.com | l | | |
| SECTION V: | Auth | orized | Signa | <u>. </u> | | | | | | | | | | |
| 16. By my signature lignature authority to dentified in field 39. | below, I | certify, to | the best of | of my kn | | | | | | | | | | |
| Company: | Kimley-l | ey-Horn Job Title: Project Manger | | | | | | | | | | | | |
| | Joe Fari | | | | | 1 | | | - | | one: | (737)2 | 49- 4 | 134 |
| Signotura | | | | | | 1 | ~ | | | | | | | |
| Signature: | | | | | Ta - | T | | | | Da | te: | | | |

TCEQ-10400 (02/21) Page 2 of 2



SECTION 9: EXHIBITS



Civil Design Plan Set

DALLAS, TEXAS 75206

ZONING: 4.913 ACRES MF-2 3.00 ACRES MF-2 CO

WATERSHED: LAKE CREEK

AMAVI NORTHWEST AUSTIN


FOR

CIVIL SITE DEVELOPMENT PLANS

- 16. THE PROPOSED PONDS WILL BE PRIVATELY MAINTAINED.
- TYPE III DRIVEWAYS MUST BE RECONSTRUCTED AS CONCRETE APPROACHES BY THE OWNER WITHIN 60 DAYS AFTER CONSTRUCTION OF THE ABUTTING STREET TO PERMANENT GRADE WITH CURBS AND GUTTER.

| AUSTIN FIRE DEPARTMENT | | | | | | |
|---------------------------------------------------------------------------------------|------------------------------------------------------------------------|--|--|--|--|--|
| FIRE DESIGN CODES | 2021 INTERNATIONAL FIRE COD WITH CITY OF AUSTIN LOCAL AMENDMENTS | | | | | |
| REQUIRED FIRE FLOW DEMAND @ 20 PSI (GPM) | 1,500 GPM | | | | | |
| INTENDED USE | MULTI-FAMILY RESIDENTIAL | | | | | |
| CONSTRUCTION CLASSIFICATION (ALL BUILDINGS) | V-B | | | | | |
| LARGEST BUILDING FIRE AREA (SF) | 3,600 | | | | | |
| AUTOMATIC FIRE SPRINKLER SYSTEM TYPE | TYPE 13D | | | | | |
| REDUCED FIRE FLOW DEMAND @ 20 PSI FOR HAVING A SPRINKLER SYSTEM (GPM) (IF APPLICABLE) | 1,500 GPM | | | | | |
| AFD FIRE HYDRANT FLOW TEST DATE | 6/7/2020 | | | | | |
| AFD FIRE HYDRANT FLOW TEST LOCATION | 13200 Morris Road Hydrant #233665 | | | | | |
| BUILDING HEIGHT AND NO. OF STORIES | 37' BLDG HEIGHT, 3 STORIES | | | | | |
| ALTERNATIVE METHOD OF COMPLIANCE | N/A | | | | | |

13220 MORRIS ROAD AUSTIN, TX 78729 SP-2024-0063C



VICINITY MAP SCALE: 1" = 1.000'

COA GRID: H38 MAPSCO: 434L

APRIL 15, 2024

REVISIONS/CORRECTIONS CHANGE AUSTIN VOID (V) DESCRIPTION IMP. COVER SHEETS IMP. COVER ADD (A) APPROVAL **IMAGED** (SQ. FT.)/% IN PLAN SHEET NO.'S (SQ. FT.) DATE SET

Fax No. (512) 418-1791

DESIGNERS:

DANZE & DAVIS ARCHITECTS, INC. 4701 SPICEWOOD SPRINGS ROAD, SUITE 200, AUSTIN, TEXAS 78759 PH. (512) 343-0714 CONTACT: HARRISON DAVIS

CERTIFICATE OF REGISTRATION #928

LANDSCAPE ARCHITECT: KIMLEY-HORN 10814 JOLLYVILLE ROAD, AVALLON IV, SUITE 200 AUSTIN, TEXAS 78759 PH. (512) 418-1771 CONTACT: EDGAR ORTEGA

KIMLEY-HORN 10814 JOLLYVILLE ROAD, AVALLON IV, SUITE 200 AUSTIN, TEXAS 78759 PH. (512) 418-1771 CONTACT: JOE FARIAS, P.E.

LISTS OF CONTACTS:

WATER & SANITARY SEWER AUSTIN WATER UTILITY 625 E. 10TH STREET, SUITE 715 AUSTIN, TX 78701 PH. (512) 972-0207

AUSTIN FIRE DEPARTMENT RALPH CASTILLO ONE TEXAS CENTER SUITE 200 505 BARTON SPRINGS ROAD AUSTIN, TX 78704 PH. (512) 974-0192

ATMOS GAS ENERGY CORPORATION MICHAEL ANDREWS 3110 N. IH 35 ROUND ROCK, TX 78681 PH. (512) 310-3855

AUSTIN ENERGY JIM ROWIN 2412 KRAMER LANE, BUILDING C AUSTIN, TEXAS 78758

PLANNING & DEVELOPMENT REVIEW DEPARTMENT 505 BARTON SPRINGS ROAD AUSTIN, TX 78704 PH. (512) 974-2680

PH. (512) 505-7665

AUSTIN WATER UTILITY DATE CITY OF AUSTIN FIRE DEPARTMENT DATE FOR DIRECTOR, PLANNING AND DEVELOPMENT REVIEW DEPARTMENT DATE

I CERTIFY THAT THESE ENGINEERING DOCUMENTS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THE INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO FORMAL CITY APPROVAL.

| SHEET NO. | DESCRIPTION |
|-----------|-----------------------------------------|
| 1 | COVER SHEET |
| 2 | KIMLEY-HORN GENERAL NOTES |
| 3 | CITY OF AUSTIN GENERAL NOTES |
| 4 | AWU GENERAL NOTES |
| 5 | FINAL PLAT |
| 6 | EXISTING CONDITIONS AND DEMOLITION PLAN |
| 7 | EROSION CONTROL PLAN |
| 8 | TREE LIST |
| 9 | SITE PLAN |
| 10 | FIRE PROTECTION PLAN |
| 11 | DIMENSION CONTROL PLAN |
| 12 | PAVING PLAN |
| 13 | GRADING PLAN (SHEET 1 OF 2) |
| 14 | GRADING PLAN (SHEET 2 OF 2) |
| 15 | EXISTING DRAINAGE AREA MAP |
| 16 | PROPOSED DRAINAGE AREA MAP |
| | INLET DRAINAGE AREA MAP |
| 17 | |
| 18 | INLET DRAINAGE CALCULATIONS |
| 19 | STORM PLAN (SHEET 2 OF 2) |
| 20 | STORM PLAN (SHEET 2 OF 2) |
| 21 | PUBLIC STORM LINE A PLAN & PROFILE |
| 22 | PUBLIC STORM LINE B PLAN & PROFILE |
| 23 | POND A PLAN |
| 24 | POND B PLAN |
| 25 | WATER QUALITY CALCULATIONS |
| 26 | POND DETAILS |
| 27 | PUBLIC WATERLINE A - PLAN & PROFILE |
| 28 | PRIVATE WATER PLAN (SHEET 1 OF 2) |
| 29 | PRIVATE WATER PLAN (SHEET 2 OF 2) |
| 30 | PUBLIC WASTEWATER A - PLAN AND PROFILE |
| 31 | PRIVATE WASTEWATER PLAN (SHEET 1 OF 2) |
| 32 | PRIVATE WASTEWATER PLAN (SHEET 2 OF 2) |
| 33 | SITE DETAILS |
| 34 | STORM DRAIN DETAILS |
| 35 | UTILITY DETAILS (SHEET 1 OF 2) |
| 36 | UTILITY DETAILS (SHEET 2 OF 2) |
| 37 | EROSION CONTROL DETAILS |
| 38 | A4.0 - BUILDING ELEVATIONS |
| 39 | TREE PRESERVATION PLAN |
| 40 | TREE MITICATION CUMMARY |
| 41 | OVERALL LANDSCAPE PLAN |
| 42 | LANDSCAPE PLAN (1 OF 1) |
| 43 | LANDSCAPE PLAN (2 OF 4) |
| 44 | LANDSCAPE PLAN (3 OF 4) |
| 45 | LANDSSAPE PLAN (4 OF 4) |
| 40 | LANDOCAPE NOTES AND DETAILS |
| 47 | LANDOCAPE SPECIFICATIONS |
| 47 | |

THIS NOTE IS BEING PLACED ON THE PLAN SET IN PLACE OF A TEMPORARY TRAFFIC CONTROL STRATEGY WITH THE FULL UNDERSTANDING THAT, AT A MINIMUM OF 6 WEEKS PRIOR TO THE START OF CONSTRUCTION, A TEMPORARY TRAFFIC CONTROL PLAN MUST BE REVIEWED AND APPROVED BY THE RIGHT OF WAY MANAGEMENT DIVISION. THE OWNER/REPRESENTATIVE FURTHER RECOGNIZES THAT A REVIEW FEE, AS PRESCRIBED BY THE MOST CURRENT VERSION OF THE CITY'S FEE ORDINANCE, SHALL BE PAID EACH TIME A PLAN OR PLAN REVISION IS SUBMITTED TO RIGHT OF WAY MANAGEMENT DIVISION FOR REVIEW. THE FOLLOWING MUST BE TAKEN INTO CONSIDERATION WHEN DEVELOPING FUTURE TRAFFIC CONTROL STRATEGIES:

PEDESTRIAN AND BICYCLE TRAFFIC ACCESS MUST BE MAINTAINE AT ALL TIMES, UNLESS OTHER WISE AUTHORIZED BY RIGHT OF WAY MANAGEMENT.

NO LONG-TERM LANE CLOSURES WILL BE AUTHORIZED, UNLESS RIGHT OF WAY MANAGEMENT DETERMINES THAT ADEQUATE ACCOMMODATIONS HAVE BEEN MADE TO MINIMIZE TRAFFIC IMPACT.

PROJECT SHOULD BE PHASED SO THAT UTILITY INSTALLATION MINIMALLY IMPACTS EXISTING OR TEMPORARY PEDESTRIAN FACILITIES.

ELEV.=874.612' SITE PLAN APPROVAL SHEET 1 OF 48 FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024 APPROVED BY COMMISSION ON UNDER SECTION 112 OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE. CASE MANAGER **CLARISSA E. DAVIS** EXPIRATION DATE (25-5-81,LDC) PROJECT EXPIRATION DATE (ORD.#970905-A) DWPZ DDZ Director, Development Services Departmen RELEASED FOR GENERAL COMPLIANCE: ZONING MF-2, MF-2 CO Correction 1 Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plan. which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date

DENICHMADIC

| | BENCHWARKS |
|----|----------------------------------------------------------------------------------------------------------------------------|
| ΞD | DATUM IS NAVD '88, USING GEOID xxx, BASED ON GPS OBSERVATIONS. |
| S | BM #100 MAG SET JUST WEST OF END OF SIDEWALK OF EASTERN SIDE OF MORRIS STREET JUST SOUTH OF TALY CHAISE INTERSECTION |
| | • ELEV.=875.069' |
| | BM #101 MAG SET JUST WEST OF SIDEWALK ON WESTERN SIDE OF MORRIS RD JUST SOUTH OF YELLOW OAK INTERSECTION |

Know what's below. WARNING: CONTRACTOR IS TO VERIFY PRESENCE AND EXACT LOCATION OF ALL UTILITIES

SHEET NUMBER

SP-2024-0063C

OVER

OF 48

SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION AND DETAIL SHALL BE FOLLOWED. 2. THE CONTRACTOR SHALL COMPLY WITH CITY (OR TOWN) "GENERAL NOTES" FOR CONSTRUCTION. IF EXISTING AND REQUIRED BY THE CITY. FOR INSTANCES WHERE THEY CONFLICT WITH THESE KH GENERAL NOTES, THEN THE MORE RESTRICTIVE SHALL APPLY. 3. THE CONTRACTOR SHALL FURNISH ALL MATERIAL AND LABOR TO CONSTRUCT THE FACILITY AS SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS IN ACCORDANCE WITH THE APPROPRIATE AUTHORITIES' SPECIFICATIONS AND REQUIREMENTS.

4. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING TO DETERMINE EXISTING CONDITIONS. 5. THE EXISTING CONDITIONS SHOWN ON THESE PLANS WERE PROVIDED BY THE TOPOGRAPHIC SURVEY PREPARED BY THE PROJECT SURVEYOR, AND ARE BASED ON THE BENCHMARKS SHOWN. THE CONTRACTOR SHALL REFERENCE THE SAME BENCHMARKS. 6. THE CONTRACTOR SHALL REVIEW AND VERIFY THE EXISTING TOPOGRAPHIC SURVEY SHOWN ON THE PLANS REPRESENTS EXISTING FIELD CONDITIONS PRIOR TO CONSTRUCTION, AND SHALL REPORT ANY DISCREPANCIES FOUND TO THE OWNER AND ENGINEER

7. IF THE CONTRACTOR DOES NOT ACCEPT THE EXISTING TOPOGRAPHIC SURVEY AS SHOWN ON THE PLANS, WITHOUT EXCEPTION, THEN THE CONTRACTOR SHALL SUPPLY AT THEIR OWN EXPENSE, A TOPOGRAPHIC SURVEY BY A REGISTERED PROFESSIONAL LAND SURVEYOR TO THE OWNER AND ENGINEER FOR REVIEW 8. CONTRACTOR SHALL PROVIDE ALL CONSTRUCTION SURVEYING AND STAKING.

9. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL CONTROL, INCLUDING BENCHMARKS PRIOR TO COMMENCING CONSTRUCTION OR STAKING OF IMPROVEMENTS. PROPERTY LINES AND CORNERS SHALL BE HELD AS THE HORIZONTAL CONTROL. 10 THE CONTRACTOR SHALL REVIEW AND VERIEY ALL DIMENSIONS, ELEVATIONS, AND FIELD CONDITIONS THAT MAY AFFECT CONSTRUCTION. ANY DISCREPANCIES ON THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE ARCHITECT. ENGINEER. AND IF APPLICABLE THE CITY AND OWNER. NO CONSIDERATION WILL BE GIVEN TO CHANGE ORDERS FOR WHICH THE CITY. ENGINEER. AND OWNER WERE NOT CONTACTED PRIOR TO CONSTRUCTION OF THE AFFECTED ITEM. 11. CONTRACTOR SHALL THOROUGHLY CHECK COORDINATION OF CIVIL, LANDSCAPE, MEP, ARCHITECTURAL, AND OTHER PLANS PRIOR TO

CONSTRUCTION. 12.IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES WHICH MAY HAVE BURIED OR AERIAL UTILITIES WITHIN OR NEAR THE CONSTRUCTION AREA BEFORE COMMENCING WORK TO HAVE THEM LOCATE THEIR EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AN ADEQUATE MINIMUM NOTICE TO ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION

COMMENCING CONSTRUCTION. OWNER/ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY PRIOR TO COMMENCING WITH

13. CONTRACTOR SHALL CALL TEXAS 811 AN ADEQUATE AMOUNT OF TIME PRIOR TO COMMENCING CONSTRUCTION OR ANY EXCAVATION. 14. CONTRACTOR SHALL USE EXTREME CAUTION AS THE SITE CONTAINS VARIOUS KNOWN AND UNKNOWN PUBLIC AND PRIVATE UTILITIES. 15. THE LOCATIONS. ELEVATIONS. DEPTH. AND DIMENSIONS OF EXISTING UTILITIES SHOWN ON THE PLANS WERE OBTAINED FROM AVAILABLE UTILITY COMPANY MAPS AND PLANS, AND ARE CONSIDERED APPROXIMATE AND INCOMPLETE. IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO VERIFY THE PRESENCE, LOCATION, ELEVATION, DEPTH, AND DIMENSION OF EXISTING UTILITIES SUFFICIENTLY IN ADVANCE OF CONSTRUCTION SO THAT ADJUSTMENTS CAN BE MADE TO PROVIDE ADEQUATE CLEARANCES. THE

ENGINEER SHALL BE NOTIFIED WHEN A PROPOSED IMPROVEMENT CONFLICTS WITH AN EXISTING UTILITY

16. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY ADJUSTMENTS AND RELOCATIONS OF EXISTING UTILITIES THAT CONFLICT WITH THE PROPOSED IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO, ADJUSTING EXISTING MANHOLES TO MATCH PROPOSED GRADE. RELOCATING EXISTING POLES AND GUY WIRES THAT ARE LOCATED IN PROPOSED DRIVEWAYS. ADJUSTING THE HORIZONTAL OR VERTICAL ALIGNMENT OF EXISTING UNDERGROUND UTILITIES TO ACCOMMODATE PROPOSED GRADE OR CROSSING WITH A PROPOSED UTILITY, AND ANY OTHERS THAT MAY BE ENCOUNTERED THAT ARE UNKNOWN AT THIS TIME AND NOT SHOWN ON THESE PLANS 17. CONTRACTOR SHALL ARRANGE FOR OR PROVIDE, AT ITS EXPENSE, ALL GAS, TELECOMMUNICATIONS, CABLE, OVERHEAD AND

UNDERGROUND POWER LINE. AND UTILITY POLE ADJUSTMENTS NEEDED. 18. CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION OF FRANCHISE UTILITIES THAT ARE NECESSARY FOR ON-SITE AND OFF-SITE CONSTRUCTION AND SERVICE TO THE PROPOSED DEVELOPMENT

19. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ALL DAMAGES DUE TO THE CONTRACTORS' FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES. THE OWNER OR ENGINEER WILL ASSUME NO LIABILITY FOR ANY DAMAGES SUSTAINED OR COST INCURRED BECAUSE OF THE OPERATIONS IN THE VICINITY OF EXISTING UTILITIES OR STRUCTURES. IF IT IS NECESSARY TO SHORE, BRACE, SWING OR RELOCATE A UTILITY, THE UTILITY COMPANY OR DEPARTMENT AFFECTED SHALL BE CONTACTED BY THE CONTRACTOR AND THEIR PERMISSION OBTAINED REGARDING THE METHOD TO USE FOR SUCH WORK.

20.BRACING OF UTILITY POLES MAY BE REQUIRED BY THE UTILITY COMPANIES WHEN TRENCHING OR EXCAVATING IN CLOSE PROXIMITY TO THE POLES. THE COST OF BRACING POLES WILL BE BORNE BY THE CONTRACTOR, WITH NO SEPARATE PAY ITEM FOR THIS WORK. 21.CONTRACTOR SHALL USE ALL NECESSARY SAFETY PRECAUTIONS TO AVOID CONTACT WITH OVERHEAD AND UNDERGROUND POWER

LINES. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE, FEDERAL AND UTILITY OWNER REGULATIONS PERTAINING

TO WORK SETBACKS FROM POWER LINES 22.THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL REQUIRED CONSTRUCTION PERMITS, APPROVALS, AND BONDS PRIOR TO 23. THE CONTRACTOR SHALL HAVE AVAILABLE AT THE JOB SITE AT ALL TIMES A COPY OF THE CONTRACT DOCUMENTS INCLUDING PLANS,

GEOTECHNICAL REPORT AND ADDENDA, PROJECT AND CITY SPECIFICATIONS, AND SPECIAL CONDITIONS, COPIES OF ANY REQUIRED CONSTRUCTION PERMITS. EROSION CONTROL PLANS. SWPPP AND INSPECTION REPORTS. 24.ALL SHOP DRAWINGS AND OTHER DOCUMENTS THAT REQUIRE ENGINEER REVIEW SHALL BE SUBMITTED BY THE CONTRACTOR

SUFFICIENTLY IN ADVANCE OF CONSTRUCTION OF THAT ITEM. SO THAT NO LESS THAN 10 BUSINESS DAYS FOR REVIEW AND RESPONSE

25.ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES, JURISDICTIONAL AGENCIES, AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO USE OF THE FACILITY AND THE FINAL CONNECTION OF SERVICES. 26.CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS.

28.ALL SYMBOLS SHOWN ON THESE PLANS (E.G. FIRE HYDRANT, METERS, VALVES, INLETS, ETC....) ARE FOR PRESENTATION PURPOSES ONLY AND ARE NOT TO SCALE. CONTRACTOR SHALL COORDINATE FINAL SIZES AND LOCATIONS WITH APPROPRIATE CITY INSPECTOR. 29 THE SCOPE OF WORK FOR THE CIVIL IMPROVEMENTS SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. REFERENCE THE BUILDING PLANS (E.G. ARCHITECTURAL, STRUCTURAL, MEP) FOR AREAS WITHIN 5-FEET OF THE BUILDING AND WITHIN THE

27.CONTRACTOR'S BID PRICE SHALL INCLUDE ALL INSPECTION FEES

BUILDING FOOTPRINT. 30.REFER TO ARCHITECTURAL AND STRUCTURAL PLANS FOR ALL FINAL BUILDING DIMENSIONS. 31.THE PROPOSED BUILDING FOOTPRINT(S) SHOWN IN THESE PLANS WAS PROVIDED TO KIMLEY-HORN AND ASSOCIATES, INC. (KH) BY THE PROJECT ARCHITECT AT THE TIME THESE PLANS WERE PREPARED. IT MAY NOT BE THE FINAL CORRECT VERSION BECAUSE THE BUILDING DESIGN WAS ONGOING. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFIRMING THE FINAL CORRECT VERSION OF THE BUILDING FOOTPRINT WITH THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO LAYOUT. DIMENSIONS AND/OR COORDINATES SHOWN ON THESE PLANS WERE BASED ON THE ABOVE STATED ARCHITECTURAL FOOTPRINT. AND ARE THEREFORE A PRELIMINARY LOCATION OF THE BUILDING. THE CONTRACTOR IS SOLELY RESPONSIBLE TO VERIFY WHAT PART OF THE BUILDING THE ARCHITECT'S FOOTPRINT REPRESENTS (E.G. SLAB, OUTSIDE WALL, MASONRY LEDGE, ETC.....) AND TO CONFIRM ITS FINAL POSITION ON THE SITE

BASED ON THE FINAL ARCHITECTURAL FOOTPRINT, CIVIL DIMENSION CONTROL PLAN, SURVEY BOUNDARY AND/OR PLAT. ANY DIFFERENCES FOUND SHALL BE REPORTED TO KH IMMEDIATELY. 32.ALL CONSTRUCTION SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING

SUBSEQUENT ADDENDA 33.CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL MATERIALS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND COMPLY WITH CITY STANDARD SPECIFICATIONS AND GEOTECHNICAL REPORT. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING MATERIALS. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR MATERIALS TESTING.

34.ALL COPIES OF MATERIALS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING 35.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE MATERIALS, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS 36.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO

GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING. 37.ALL CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA. NO ENCROACHMENTS OUTSIDE OF THE WORK AREA WILL BE

ALLOWED. ANY DAMAGE RESULTING THEREFROM SHALL BE CONTRACTOR'S SOLE RESPONSIBILITY TO REPAIR. 38. THE CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES. UTILITIES. MANHOLES. POLES. GUY WIRES. VALVE COVERS. VAULT LIDS, FIRE HYDRANTS, COMMUNICATION BOXES/PEDESTALS, AND OTHER FACILITIES TO REMAIN AND SHALL REPAIR ANY DAMAGES AT NO COST TO THE OWNER.

39. THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE ANY PHYSICAL DAMAGE TO PRIVATE PROPERTY OR PUBLIC IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO: FENCES, WALLS, SIGNS, PAVEMENT, CURBS, UTILITIES, SIDEWALKS, GRASS, TREES, LANDSCAPING, AND IRRIGATION SYSTEMS, ETC TO ORIGINAL CONDITION OR BETTER AT NO COST TO THE OWNER. 40.ALL AREAS IN EXISTING RIGHT-OF-WAY DISTURBED BY SITE CONSTRUCTION SHALL BE REPAIRED TO ORIGINAL CONDITION OR BETTER, INCLUDING AS NECESSARY GRADING, LANDSCAPING, CULVERTS, AND PAVEMENT.

41.THE CONTRACTOR SHALL SALVAGE ALL EXISTING POWER POLES, SIGNS, WATER VALVES, FIRE HYDRANTS, METERS, ETC... THAT ARE TO BE RELOCATED DURING CONSTRUCTION. 42.CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. 43.THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL

ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 44.THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER. 45.SITE SAFETY IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR

46.THESE PLANS DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONTRACTOR OR ITS EMPLOYEES, AGENTS OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE ENGINEER'S SEAL HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF ALL REQUIRED SAFETY PROCEDURES AND PROGRAMS

47.SIGNS RELATED TO SITE OPERATION OR SAFETY ARE NOT INCLUDED IN THESE PLANS. 48.CONTRACTOR OFFICE AND STAGING AREA SHALL BE AGREED ON BY THE OWNER AND CONTRACTOR PRIOR TO BEGINNING OF CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING REQUIREMENTS FOR THE CONSTRUCTION OFFICE, TRAILER, STORAGE, AND STAGING OPERATIONS AND LOCATIONS.

49.LIGHT POLES, SIGNS, AND OTHER OBSTRUCTIONS SHALL NOT BE PLACED IN ACCESSIBLE ROUTES. 50.ALL SIGNS, PAVEMENT MARKINGS, AND OTHER TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM

51.TOP RIM ELEVATIONS OF ALL EXISTING AND PROPOSED MANHOLES SHALL BE COORDINATED WITH TOP OF PAVEMENT OR FINISHED GRADE AND SHALL BE ADJUSTED TO BE FLUSH WITH THE ACTUAL FINISHED GRADE AT THE TIME OF PAVING. 52.CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED VALVES, FIRE HYDRANTS, AND OTHER UTILITY APPURTENANCES TO MATCH ACTUAL FINISHED GRADES AT THE TIME OF PAVING.

53.THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND PHASING, AND SHALL CONTACT THE APPROPRIATE CITY OFFICIALS, INCLUDING BUILDING OFFICIAL, ENGINEERING INSPECTOR, AND FIRE MARSHALL TO LEARN OF ANY REQUIREMENTS. 54.CONTRACTOR IS RESPONSIBLE FOR PREPARATION, SUBMITTAL, AND APPROVAL BY THE CITY OF A TRAFFIC CONTROL PLAN PRIOR TO THE START OF CONSTRUCTION. AND THEN THE IMPLEMENTATION OF THE PLAN.

55.CONTRACTOR SHALL KEEP A NEAT AND ACCURATE RECORD OF CONSTRUCTION, INCLUDING ANY DEVIATIONS OR VARIANCES FROM CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS.

56.THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.

THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS,

LAWS, AND ORDINANCES THAT APPLY TO THE CONSTRUCTION SITE LAND DISTURBANCE. 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE "TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS

POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000" 3. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START

4. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THE 5. CONTRACTOR IS SOLELY RESPONSIBLE FOR INSTALLATION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL EROSION

CONTROL DEVICES, BEST MANAGEMENT PRACTICES (BMPS), AND FOR UPDATING THE EROSION CONTROL PLAN DURING CONSTRUCTION AS FIELD CONDITIONS CHANGE. 6. CONTRACTOR SHALL DOCUMENT THE DATES OF INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL FOR EACH BMP EMPLOYED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE. 7. AS STORM SEWER INLETS ARE INSTALLED ON-SITE, TEMPORARY EROSION CONTROL DEVICES SHALL BE INSTALLED AT EACH INLET PER

APPROVED DETAILS.

8. THE EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE AREA IT PROTECTS HAS BEEN PERMANENTLY STABILIZED. 9. CONTRACTOR SHALL PROVIDE ADEQUATE EROSION CONTROL DEVICES NEEDED DUE TO PROJECT PHASING. 10. CONTRACTOR SHALL OBSERVE THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES AND MAKE FIELD ADJUSTMENTS AND MODIFICATIONS AS NEEDED TO PREVENT SEDIMENT FROM LEAVING THE SITE. IF THE FROSION CONTROL DEVICES DO NOT

EFFECTIVELY CONTROL EROSION AND PREVENT SEDIMENTATION FROM WASHING OFF THE SITE, THEN THE CONTRACTOR SHALL

11. OFF-SITE SOIL BORROW. SPOIL, AND STORAGE AREAS (IF APPLICABLE) ARE CONSIDERED AS PART OF THE PROJECT SITE AND MUST ALSO COMPLY WITH THE EROSION CONTROL REQUIREMENTS FOR THIS PROJECT. THIS INCLUDES THE INSTALLATION OF BMP'S TO CONTROL EROSION AND SEDIMENTATION AND THE ESTABLISHMENT OF PERMANENT GROUND COVER ON DISTURBED AREAS PRIOR TO FINAL APPROVAL OF THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP AND EROSION CONTROL PLAN TO INCLUDE BMPS FOR ANY OFF-SITE THAT ARE NOT ANTICIPATED OR SHOWN ON THE EROSION CONTROL PLAN.

12. ALL STAGING, STOCKPILES, SPOIL, AND STORAGE SHALL BE LOCATED SUCH THAT THEY WILL NOT ADVERSELY AFFECT STORM WATER QUALITY. PROTECTIVE MEASURES SHALL BE PROVIDED IF NEEDED TO ACCOMPLISH THIS REQUIREMENT, SUCH AS COVERING OR ENCIRCLING THE AREA WITH AN APPROPRIATE BARRIER.

13. CONTRACTORS SHALL INSPECT ALL EROSION CONTROL DEVICES, BMPS, DISTURBED AREAS, AND VEHICLE ENTRY AND EXIT AREAS WEEKLY AND WITHIN 24 HOURS OF ALL RAINFALL EVENTS OF 0.5 INCHES OR GREATER, AND KEEP A RECORD OF THIS INSPECTION IN THE SWPPP BOOKLET IF APPLICABLE. TO VERIFY THAT THE DEVICES AND EROSION CONTROL PLAN ARE FUNCTIONING PROPERLY 14. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT ALL PRIMARY POINTS OF ACCESS IN ACCORDANCE WITH CITY SPECIFICATIONS. CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION TRAFFIC USES THE STABILIZED ENTRANCE AT

ALL TIMES FOR ALL INGRESS/EGRESS. 15. SITE ENTRY AND EXITS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING AND FLOWING OF SEDIMENT AND REMOVED IMMEDIATELY

16. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL SILT AND DEBRIS FROM THE AFFECTED OFF-SITE ROADWAYS THAT ARE A RESULT OF THE CONSTRUCTION, AS REQUESTED BY OWNER AND CITY. AT A MINIMUM, THIS SHOULD OCCUR ONCE PER DAY FOR THE OFF-SITE ROADWAYS. 17. WHEN WASHING OF VEHICLES IS REQUIRED TO REMOVE SEDIMENT PRIOR TO EXITING THE SITE, IT SHALL BE DONE IN AN AREA

STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP BMP 18 CONTRACTOR SHALL INSTALL A TEMPORARY SEDIMENT BASIN FOR ANY ON-SITE DRAINAGE AREAS THAT ARE GREATER THAN 10 ACRES, PER TCEQ AND CITY STANDARDS. IF NO ENGINEERING DESIGN HAS BEEN PROVIDED FOR A SEDIMENTATION BASIN ON THESE PLANS. THEN THE CONTRACTOR SHALL ARRANGE FOR AN APPROPRIATE DESIGN TO BE PROVIDED 19. ALL FINES IMPOSED FOR SEDIMENT OR DIRT DISCHARGED FROM THE SITE SHALL BE PAID BY THE RESPONSIBLE CONTRACTOR.

20. WHEN SEDIMENT OR DIRT HAS CLOGGED THE CONSTRUCTION ENTRANCE VOID SPACES BETWEEN STONES OR DIRT IS BEING TRACKED ONTO A ROADWAY. THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASH-DOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL SEDIMENTATION. PERIODIC RE-GRADING OR NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFECTIVENESS OF THE CONSTRUCTION ENTRANCE. 21.TEMPORARY SEEDING OR OTHER APPROVED STABILIZATION SHALL BE INITIATED WITHIN 14 DAYS OF THE LAST DISTURBANCE OF ANY AREA, UNLESS ADDITIONAL CONSTRUCTION IN THE AREA IS EXPECTED WITHIN 21 DAYS OF THE LAST DISTURBANCE. 22.CONTRACTOR SHALL FOLLOW GOOD HOUSEKEEPING PRACTICES DURING CONSTRUCTION, ALWAYS CLEANING UP DIRT, LOOSE MATERIAL, AND TRASH AS CONSTRUCTION PROGRESSES.

23.UPON COMPLETION OF FINE GRADING, ALL SURFACES OF DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED. STABILIZATION IS ACHIEVED WHEN THE AREA IS EITHER COVERED BY PERMANENT IMPERVIOUS STRUCTURES, SUCH AS BUILDINGS, SIDEWALK, PAVEMENT. OR A UNIFORM PERENNIAL VEGETATIVE COVER. 24.AT THE CONCLUSION OF THE PROJECT, ALL INLETS, DRAIN PIPE, CHANNELS, DRAINAGEWAYS AND BORROW DITCHES AFFECTED BY THE CONSTRUCTION SHALL BE DREDGED. AND THE SEDIMENT GENERATED BY THE PROJECT SHALL BE REMOVED AND DISPOSED IN

STORM WATER DISCHARGE AUTHORIZATION

ACCORDANCE WITH APPLICABLE REGULATIONS.

CONTRACTOR SHALL COMPLY WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION REQUIREMENTS 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000 3. THE CONTRACTOR SHALL ENSURE THAT ALL PRIMARY OPERATORS SUBMIT A NOI TO TCEQ AT LEAST SEVEN DAYS PRIOR TO

COMMENCING CONSTRUCTION (IF APPLICABLE), OR IF UTILIZING ELECTRONIC SUBMITTAL, PRIOR TO COMMENCING CONSTRUCTION. ALL PRIMARY OPERATORS SHALL PROVIDE A COPY OF THE SIGNED NOI TO THE OPERATOR OF ANY MS4 (TYPICALLY THE CITY) RECEIVING DISCHARGE FROM THE SITE. 4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF

APPLICABLE, INCLUDING POSTING SITE NOTICE, INSPECTIONS, DOCUMENTATION, AND SUBMISSION OF ANY INFORMATION REQUIRED BY THE TOPO AND PPA (F.G. NOI) ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICES RELATED TO THE SWPPP SHALL SIGN THE REQUIRED CONTRACTOR CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS SPECIFIED IN THE SWPPP.

THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION. 7. A NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO TCEQ BY ANY PRIMARY OPERATOR WITHIN 30 DAYS AFTER ALL SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND A UNIFORM VEGETATIVE COVER HAS BEEN ESTABLISHED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY STRUCTURES, A TRANSFER OF OPERATIONAL CONTROL HAS OCCURRED, OR THE OPERATOR HAS OBTAINED ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT. A COPY OF THE NOT SHALL BE PROVIDED TO

6. A COPY OF THE SWPPP, INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATIONS, AND ANY REVISIONS, SHALL BE SUBMITTED TO

. KH IS NOT RESPONSIBLE FOR THE MEANS AND METHODS EMPLOYED BY THE CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS PRELIMINARY DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACT THAT ARE TO BE DEMOLISHED AND REMOVED FROM THE SITE 2. KH DOES NOT WARRANT OR REPRESENT THAT THE PLAN. WHICH WAS PREPARED BASED ON SURVEY AND UTILITY INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY, OR THAT THE UTILITIES SHOWN CAN BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING ITS OWN SITE RECONNAISSANCE TO SCOPE ITS WORK AND TO CONFIRM WITH THE OWNERS OF IMPROVEMENTS AND UTILITIES THE ABILITY AND

PROCESS FOR THE REMOVAL OF THEIR FACILITIES. 3. THIS PLAN IS INTENDED TO GIVE A GENERAL GUIDE TO THE CONTRACTOR, NOTHING MORE. THE GOAL OF THE DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT. REMOVAL OR PRESERVATION OF IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL ARE THE RESPONSIBILITY OF THE CONTRACTOR. 4. CONTRACTOR IS STRONGLY CAUTIONED TO REVIEW THE FOLLOWING REPORTS DESCRIBING SITE CONDITIONS PRIOR TO BIDDING AND

IMPLEMENTING THE DEMOLITION PLANa ENVIRONMENTAL SITE ASSESSMENT PROVIDED BY THE OWNER b. ASBESTOS BUILDING INSPECTION REPORT(S) PROVIDED BY THE OWNER.

c. GEOTECHNICAL REPORT PROVIDED BY THE OWNER. d. OTHER REPORTS THAT ARE APPLICABLE AND AVAILABLE.

THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.

5. CONTRACTOR SHALL CONTACT THE OWNER TO VERIFY WHETHER ADDITIONAL REPORTS OR AMENDMENTS TO THE ABOVE CITED REPORTS HAVE BEEN PREPARED AND TO OBTAIN/REVIEW/AND COMPLY WITH THE RECOMMENDATION OF SUCH STUDIES PRIOR TO STARTING ANY WORK ON THE SITE. 6. CONTRACTOR SHALL COMPLY WITH ALL LOCAL STATE AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO REVIEW

THE SITE, DETERMINE THE APPLICABLE REGULATIONS, RECEIVE THE REQUIRED PERMITS AND AUTHORIZATIONS. AND COMPLY. . KH DOES NOT REPRESENT THAT THE REPORTS AND SURVEYS REFERENCED ABOVE ARE ACCURATE, COMPLETE, OR COMPREHENSIVE SHOWING ALL ITEMS THAT WILL NEED TO BE DEMOLISHED AND REMOVED.

8. SURFACE PAVEMENT INDICATED MAY OVERLAY OTHER HIDDEN STRUCTURES, SUCH AS ADDITIONAL LAYERS OF PAVEMENT FOUNDATIONS OR WALLS, THAT ARE ALSO TO BE REMOVED.

 THE CONTRACTOR AND GRADING SUBCONTRACTOR SHALL VERIFY THE SUITABILITY OF EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE START OF CONSTRUCTION. THE CIVIL ENGINEER SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES. CONTRACTOR SHALL OBTAIN ANY REQUIRED GRADING PERMITS FROM THE CITY

3. UNLESS OTHERWISE NOTED, PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN IN PAVED AREA REFLECT TOP OF PAVEMENT SURFACE. IN LOCATIONS ALONG A CURB LINE, ADD 6-INCHES (OR THE HEIGHT OF THE CURB) TO THE PAVING GRADE FOR TOP OF CURB 4. PROPOSED SPOT ELEVATIONS AND CONTOURS OUTSIDE THE PAVEMENT ARE TO TOP OF FINISHED GRADE.

5. PROPOSED CONTOURS ARE APPROXIMATE. PROPOSED SPOT ELEVATIONS AND DESIGNATED GRADIENT ARE TO BE USED IN CASE OF DISCREPANCY. ALL FINISHED GRADES SHALL TRANSITION UNIFORMLY BETWEEN THE FINISHED ELEVATIONS SHOWN . CONTOURS AND SPOT GRADES SHOWN ARE ELEVATIONS OF TOP OF THE FINISHED SURFACE. WHEN PERFORMING THE GRADING OPERATIONS, THE CONTRACTOR SHALL PROVIDE AN APPROPRIATE ELEVATION HOLD-DOWN ALLOWANCE FOR THE THICKNESS OF

PAVEMENT, SIDEWALK, TOPSOIL, MULCH, STONE, LANDSCAPING, RIP-RAP AND ALL OTHER SURFACE MATERIALS THAT WILL CONTRIBUTE TO THE TOP OF FINISHED GRADE. FOR EXAMPLE, THE LIMITS OF EARTHWORK IN PAVED AREAS IS THE BOTTOM OF THE 3. NO REPRESENTATIONS OF EARTHWORK QUANTITIES OR SITE BALANCE ARE MADE BY THESE PLANS. THE CONTRACTOR SHAL PROVIDE THEIR OWN EARTHWORK CALCULATION TO DETERMINE THEIR CONTRACT QUANTITIES AND COST. ANY SIGNIFICANT VARIANCE FROM A BALANCED SITE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CIVIL ENGINEER.

9. ALL GRADING AND EARTHWORK SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING 10. ALL EXCAVATION IS UNCLASSIFIED AND SHALL INCLUDE ALL MATERIALS ENCOUNTERED. UNUSABLE EXCAVATED MATERIAL AND ALL WASTE RESULTING FROM SITE CLEARING AND GRUBBING SHALL BE REMOVED FROM THE SITE AND APPROPRIATELY DISPOSED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE 11. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START

OF GRADING. REFERENCE EROSION CONTROL PLAN, DETAILS, GENERAL NOTES, AND SWPPP FOR ADDITIONAL INFORMATION AND

12.BEFORE ANY EARTHWORK IS PERFORMED, THE CONTRACTOR SHALL STAKE OUT AND MARK THE LIMITS OF THE PROJECT'S PROPERTY LINE AND SITE IMPROVEMENTS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY ENGINEERING AND SURVEYING FOR LINE AND GRADE CONTROL POINTS RELATED TO EARTHWORK. 13. CONTRACTOR TO DISPOSE OF ALL EXCESS EXCAVATION MATERIALS IN A MANNER THAT ADHERES TO LOCAL, STATE AND FEDERAL LAWS AND REGULATIONS. THE CONTRACTOR SHALL KEEP A RECORD OF WHERE EXCESS EXCAVATION WAS DISPOSED, ALONG WITH

THE RECEIVING LANDOWNER'S APPROVAL TO DO SO. 14. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF TOPSOIL AT THE COMPLETION OF FINE GRADING. CONTRACTOR SHALL REFER TO LANDSCAPE ARCHITECTURE PLANS FOR SPECIFICATIONS AND REQUIREMENTS FOR TOPSOIL 15. CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES.

16.NO EARTHWORK FILL SHALL BE PLACED IN ANY EXISTING DRAINAGE WAY, SWALE, CHANNEL, DITCH, CREEK, OR FLOODPLAIN FOR ANY REASON OR ANY LENGTH OF TIME, UNLESS THESE PLANS SPECIFICALLY INDICATE THIS IS REQUIRED. 17. TEMPORARY CULVERTS MAY BE REQUIRED IN SOME LOCATIONS TO CONVEY RUN-OFF 18. REFER TO DIMENSION CONTROL PLAN, AND PLAT FOR HORIZONTAL DIMENSIONS.

19. THE CONTRACTOR SHALL CLEAR AND GRUB THE SITE AND PLACE, COMPACT, AND CONDITION FILL PER THE PROJECT GEOTECHNICAL ENGINEER'S SPECIFICATIONS. THE FILL MATERIAL TO BE USED SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO 20. CONTRACTOR IS RESPONSIBLE FOR ALL SOILS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL SOILS

TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND SHALL COMPLY WITH CITY STANDARD SPECIFICATIONS AND THE GEOTECHNICAL REPORT. SOILS TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING SOILS. THE OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR SOILS TESTING. 21.ALL COPIES OF SOILS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING 22.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE SOILS, THAT THE WORK

SHALL REFER TO THE GEOTECHNICAL REPORT AND STRUCTURAL PLANS AND SPECIFICATIONS FILL, CONDITIONING, AND PREPARATION IN THE BUILDING PAD. 24.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING. IF NONE IS CURRENTLY EXISTING.

23. THE SCOPE OF WORK FOR CIVIL IMPROVEMENT SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. CONTRACTOR

25.CONTRACTOR SHALL ENSURE THAT SUFFICIENT POSITIVE SLOPE AWAY FROM THE BUILDING PAD IS ACHIEVED FOR ENTIRE PERIMETER OF THE PROPOSED BUILDING(S) DURING GRADING OPERATIONS AND IN THE FINAL CONDITION. IF THE CONTRACTOR OBSERVES THAT THIS WILL NOT BE ACHIEVED, THE CONTRACTOR SHALL CONTACT THE ENGINEER TO REVIEW THE LOCATION 26.THE CONTRACTOR SHALL TAKE ALL AVAILABLE PRECAUTIONS TO CONTROL DUST. CONTRACTOR SHALL CONTROL DUST BY SPRINKLING WATER OR BY OTHER MEANS APPROVED BY THE CITY AT NO ADDITIONAL COST TO THE OWNER

NEEDED FOR GRADING OPERATIONS AND TO ACCOMMODATE PROPOSED GRADE, INCLUDING THE UNKNOWN UTILITIES NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL REFER TO THE GENERAL NOTES "OVERALL" SECTION THESE PLANS FOR ADDITIONAL INFORMATION 28.EXISTING TREE LOCATIONS SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL REPORT ANY DISCREPANCIES FOUND IN THE FIELD THAT AFFECT THE GRADING PLAN TO THE CIVIL ENGINEER. 29. CONTRACTOR SHALL FIELD VERIFY ALL PROTECTED TREE LOCATIONS, INDIVIDUAL PROTECTED TREE CRITICAL ROOT ZONES, AND PROPOSED SITE GRADING, AND NOTIFY THE CIVIL ENGINEER AND LANDSCAPE ARCHITECT OF ANY CONFLICTS WITH THE TREE

PRESERVATION PLAN BY THE LANDSCAPE ARCHITECT PRIOR TO COMMENCING THE WORK. 30 TREE PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE CITY STANDARD TREE PROTECTION DETAILS AND THE WORK SHALL BE CONSIDERED AS A SUBSIDIARY COST TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

APPROVED TREE PRESERVATION PLANS BY THE LANDSCAPE ARCHITECT 31. CONTRACTOR SHALL REFER TO THE LANDSCAPING AND TREE PRESERVATIONS PLANS FOR ALL INFORMATION AND DETAILS

REGARDING EXISTING TREES TO BE REMOVED AND PRESERVED. 32.NO TREE SHALL BE REMOVED UNLESS A TREE REMOVAL PERMIT HAS BEEN ISSUED BY THE CITY, OR CITY HAS OTHERWISE CONFIRMED

IN WRITING THAT ONE IS NOT NEEDED FOR THE TREE(S) 33.NO TREE SHALL BE REMOVED OR DAMAGED WITHOUT PRIOR AUTHORIZATION OF THE OWNER OR OWNER'S REPRESENTATIVE

EXISTING TREES SHALL BE PRESERVED WHENEVER POSSIBLE AND GRADING IMPACT TO THEM HELD TO A MINIMUM 34.AFTER PLACEMENT OF SUBGRADE AND PRIOR TO PLACEMENT OF PAVEMENT, CONTRACTOR SHALL TEST AND OBSERVE PAVEMENT AREAS FOR EVIDENCE OF PONDING AND INADEQUATE SLOPE FOR DRAINAGE. ALL AREAS SHALL ADEQUATELY DRAIN TOWARDS THE INTENDED STRUCTURE TO CONVEY STORMWATER RUNOFF, CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND ENGINEER IF ANY AREAS OF POOR DRAINAGE ARE DISCOVERED.

35. CONTRACTOR FIELD ADJUSTMENT OF PROPOSED SPOT GRADES IS ALLOWED, IF THE APPROVAL OF THE CIVIL ENGINEER IS OBTAINED. . RETAINING WALLS SHOWN ARE FOR SITE GRADING PURPOSES ONLY, AND INCLUDE ONLY LOCATION AND SURFACE SPOT ELEVATIONS

AT THE TOP AND BOTTOM OF THE WALL. 2. RETAINING WALL TYPE OR SYSTEM SHALL BE SELECTED BY THE OWNER DIRT ONTO OFF-SITE ROADWAYS. ALL SEDIMENT AND DIRT FROM THE SITE THAT IS DEPOSITED ONTO AN OFF-SITE ROADWAY SHALL BE 3. RETAINING WALL DESIGN SHALL BE PROVIDED BY OTHERS AND SHALL FIT IN THE WALL ZONE OR LOCATION SHOWN ON THESE PLANS. STRUCTURAL DESIGN AND PERMITTING OF RETAINING WALLS, RAILINGS, AND OTHER WALL SAFETY DEVICES SHALL BE PERFORMED BY A LICENSED ENGINEER AND ARE NOT PART OF THIS PLAN SET 4. RETAINING WALL DESIGN SHALL MEET THE INTENT OF THE GRADING PLAN AND SHALL ACCOUNT FOR ANY INFLUENCE ON ADJACENT BUILDING FOUNDATIONS, UTILITIES, PROPERTY LINES AND OTHER CONSTRUCTABILITY NOTES 5. RETAINING WALL ENGINEER SHALL CONSULT THESE PLANS AND THE GEOTECHNICAL REPORT FOR POTENTIAL CONFLICTS.

> 1. ALL PAVING MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THESE PLANS. THE CITY STANDARD DETAILS AND SPECIFICATIONS, THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA, AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION/DETAIL SHALL BE FOLLOWED. ALL PRIVATE ON-SITE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING ALL ADDENDA.

3. ALL FIRELANE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARDS AND DETAILS. IF THESE ARE DIFFERENT THAN THOSE IN THE GEOTECHNICAL REPORT. THEN THE MORE RESTRICTIVE SHALL BE FOLLOWED 4. ALL PUBLIC PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS. 5. CONTRACTOR IS RESPONSIBLE FOR ALL PAVING AND PAVING SUBGRADE TESTING AND CERTIFICATION. UNLESS SPECIFIED OTHERWISE BY OWNER. ALL PAVING AND PAVING SUBGRADE TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR.

TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING PAVING AND SUBGRADE. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR PAVING AND PAVING SUBGRADE TESTING 6. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE PAVING AND PAVING SUBGRADE, THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 7. DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO ELATWORK ADJACENT TO THE PROPOSED. BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING.

8. CURB RAMPS ALONG PUBLIC STREETS AND IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED BASED ON THE CITY STANDARD CONSTRUCTION DETAIL AND SPECIFICATIONS 9. PRIVATE CURB RAMPS ON THE SITE (I.E. OUTSIDE PUBLIC STREET RIGHT-OF-WAY) SHALL CONFORM TO ADA AND TAS STANDARDS AND SHALL HAVE A DETECTABLE WARNING SURFACE THAT IS FULL WIDTH AND FULL DEPTH OF THE CURB RAMP, NOT INCLUDING FLARES. 10. ALL ACCESSIBLE RAMPS, CURB RAMPS, STRIPING, AND PAVEMENT MARKINGS SHALL CONFORM TO ADA AND TAS STANDARDS, LATEST

11. ANY COMPONENTS OF THE PROJECT SUBJECT TO RESIDENTIAL USE SHALL ALSO CONFORM TO THE FAIR HOUSING ACT, AND COMPLY WITH THE FAIR HOUSING ACT DESIGN MANUAL BY THE US DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT. 12. CONTRACTOR SHALL CONSTRUCT PROPOSED PAVEMENT TO MATCH EXISTING PAVEMENT WITH A SMOOTH, FLUSH, CONNECTION, 13. CONTRACTOR SHALL FURNISH AND INSTALL ALL PAVEMENT MARKINGS FOR FIRE LANES, PARKING STALLS, HANDICAPPED PARKING SYMBOLS, AND MISCELLANEOUS STRIPING WITHIN PARKING LOT AND AROUND BUILDING AS SHOWN ON THE PLANS. ALL PAINT AND

PAVEMENT MARKINGS SHALL ADHERE TO CITY AND OWNER STANDARDS. 14. REFER TO GEOTECHNICAL REPORT FOR PAVING JOINT LAYOUT PLAN REQUIREMENTS FOR PRIVATE PAVEMENT. 15. REFER TO CITY STANDARD DETAILS AND SPECIFICATIONS FOR JOINT LAYOUT PLAN REQUIREMENTS FOR PUBLIC PAVEMENT 16. ALL REINFORCING STEEL SHALL CONFORM TO THE GEOTECHNICAL REPORT, CITY STANDARDS, AND ASTM A-615, GRADE 60, AND SHALL BE SUPPORTED BY BAR CHAIRS. CONTRACTOR SHALL USE THE MORE STRINGENT OF THE CITY AND GEOTECHNICAL STANDARDS.

18. THE MINIMUM LENGTH OF OFFSET JOINTS AT RADIUS POINTS SHALL BE 2 FEET. 19. CONTRACTOR SHALL SUBMIT A JOINTING PLAN TO THE ENGINEER AND OWNER PRIOR TO BEGINNING ANY OF THE PAVING WORK. 20.ALL SAWCUTS SHALL BE FULL DEPTH FOR PAVEMENT REMOVAL AND CONNECTION TO EXISTING PAVEMENT. 21.FIRE LANES SHALL BE MARKED AND LABELED AS A FIRELANE PER CITY STANDARDS

22.UNLESS THE PLANS SPECIFICALLY DICTATE TO THE CONTRARY, ON-SITE AND OTHER DIRECTIONAL SIGNS SHALL BE ORIENTED SO THEY ARE READILY VISIBLE TO THE ONCOMING TRAFFIC FOR WHICH THEY ARE INTENDED. 23. CONTRACTOR IS RESPONSIBLE FOR INSTALLING NECESSARY CONDUIT FOR LIGHTING, IRRIGATION, ETC. PRIOR TO PLACEMENT OF PAVEMENT. ALL CONSTRUCTION DOCUMENTS (CIVIL, MEP, LANDSCAPE, IRRIGATION, AND ARCHITECT) SHALL BE CONSULTED. 24.BEFORE PLACING PAVEMENT. CONTRACTOR SHALL VERIFY THAT SUITABLE ACCESSIBLE PEDESTRIAN ROUTES (PER ADA. TAS. AND FHA) EXIST TO AND FROM EVERY DOOR AND ALONG SIDEWALKS, ACCESSIBLE PARKING SPACES, ACCESS AISLES, AND ACCESSIBLE ROUTES, IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL, IN NO CASE SHALL SIDEWALK

CROSS SLOPE EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPE EXCEED 5.0 PERCENT. ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL NOT EXCEED 2.0 PERCENT SLOPE IN ANY DIRECTION. 25. CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA/TAS SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA AND TAS SLOPE COMPLIANCE ISSUES.

17. ALL JOINTS SHALL EXTEND THROUGH THE CURB.

1. ALL STORM SEWER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND **SPECIFICATIONS** 2. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE STORM SEWER

3. THE CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING STORM SEWER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY STORM SEWER, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED. 4. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF CURB INLETS AND GRATE INLETS AND ALL UTILITIES CROSSING THE STORM SEWER

5. FLOW LINE, TOP-OF-CURB, RIM, THROAT, AND GRATE ELEVATIONS OF PROPOSED INLETS SHALL BE VERIFIED WITH THE GRADING PLAN NO AND FIELD CONDITIONS PRIOR TO THEIR INSTALLATION. 6. ALL PUBLIC STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS

7. ALL PRIVATE STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. ALL PVC TO RCP CONNECTIONS AND ALL STORM PIPE CONNECTIONS ENTERING STRUCTURES OR OTHER STORM PIPES SHALL HAVE A CONCRETE COLLAR AND BE GROUTED TO ASSURE THE CONNECTION IS WATERTIGHT. 9. ALL PUBLIC STORM SEWER LINES SHALL BE MINIMUM CLASS III RCP. PRIVATE STORM SEWER LINES 18-INCHES AND GREATER SHALL BE

CLASS III RCP OR OTHER APPROVED MATERIAL 10. WHERE COVER EXCEEDS 20-FEET OR IS LESS THAN 2-FEET, CLASS IV RCP SHALL BE USED. 11.IF CONTRACTOR PROPOSES TO USE HDPE OR PVC IN LIEU OF RCP FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPE AND PVC SHALL BE WATERTIGHT.

12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL STORM SEWER LINES. 13.EMBEDMENT FOR ALL STORM SEWER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS. 14.ALL WYE CONNECTIONS AND PIPE BENDS ARE TO BE PREFABRICATED AND INSTALLED PER MANUFACTURERS SPECIFICATIONS. 15.USE 4 FOOT JOINTS WITH BEVELED ENDS IF RADIUS OF STORM SEWER IS LESS THAN 100 FEET. 16 THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN. PREPARED BY A PROFESSIONAL

ENGINEER IN THE STATE OF TEXAS. TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 17. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.

ANY PONDS THAT ARE INTENDED TO HOLD WATER INDEFINITELY SHALL BE CONSTRUCTED WATERTIGHT 2. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR POND LINER SPECIFICATIONS

3. A GEOTECHNICAL ENGINEER SHALL REVIEW AND APPROVE ALL POND LINER MATERIAL, PLACEMENT PROCEDURES, AND PROVIDE TESTING TO ENSURE THE POND LINER MATERIAL PLACED IS WATERTIGHT. 4. STORM SEWER PIPES AND HEADWALLS THAT CONNECT TO A POND INTENDED TO HOLD WATER INDEFINITELY SHALL BE INSTALLED WITH WATERTIGHT JOINTS TO AT LEAST 1-FOOT ABOVE THE NORMAL POOL WATER SURFACE ELEVATION.

AS THIS MAY DRY-OUT THE POND LINER AND RISK ITS WATERTIGHT PROPERTIES.

SUBSIDIARY TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED

5. ANY GRAVEL OR OTHER PERVIOUS EMBEDMENT AROUND PIPES OR OUTFALL STRUCTURES NEAR THE POND SHALL BE ELIMINATED FOR TCEQ AT LEAST 20-FEET FROM THE POND SO NO ROUTE FOR WATER TO LEAK THROUGH THE EMBEDMENT MATERIAL IS PROVIDED. BACKFILL IN THESE AREAS SHALL BE OF IMPERVIOUS MATERIAL. 6. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE WATER LEVEL FOLLOWING COMPLETION AND FILLING OF THE POND

SHALL BE MONITORED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO OBSERVE WATER INFLOW, OUTFLOW, AND CALCULATE EVAPORATION TO VERIFY THAT THE POND IS WATERTIGHT. 7. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE POND WATER LEVEL SHALL ALSO BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION SO THAT IT REMAINS FULL TO ITS DESIGN WATER LEVEL, AND IS NOT LOWERED,

. ALL WATER AND WASTEWATER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS 2. CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER AND WASTEWATER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY WATER OR WASTEWATER CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED.

3. CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITY SERVICES ENTERING THE BUILDING. 4. THE CONTRACTOR SHALL FIELD VERIFY THE ELEVATION OF ALL UTILITY CROSSINGS PRIOR TO THE INSTALLATION OF ANY PIPE 5. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE WATER AND WASTEWATER IMPROVEMENTS

6. ALL PUBLIC WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 7. ALL PRIVATE WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. FIRE SPRINKLER LINES SHALL BE DESIGNED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR, AND COMPLY TO THE

DESIGN. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES. 9. EMBEDMENT FOR ALL WATER AND WASTEWATER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS. 10. CONTRACTOR SHALL TAKE REQUIRED SANITARY PRECAUTIONS, FOLLOWING ANY CITY, TCEQ, AND AWWA STANDARDS, TO KEEP WATER PIPE AND FITTINGS CLEAN AND CAPPED AT TIMES WHEN INSTALLATION IS NOT IN PROGRESS 11. CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL WATER AND WASTEWATER LINES 12. ALL WATER AND WASTEWATER SERVICES SHALL TERMINATE 5-FEET OUTSIDE THE BUILDING, UNLESS NOTED OTHERWISE

APPLICABLE CODES AND INSPECTIONS REQUIRED. THESE PLANS WERE PREPARED WITHOUT THE BENEFIT OF THE FIRE SPRINKLER

13. CONTRACTOR SHALL COMPLY WITH CITY REQUIREMENTS FOR WATER AND WASTEWATER SERVICE DISRUPTIONS AND THE AMOUNT OF PRIOR NOTICE THAT IS REQUIRED, AND SHALL COORDINATE DIRECTLY WITH THE APPROPRIATE CITY DEPARTMENT. 14. CONTRACTOR SHALL SEQUENCE WATER AND WASTEWATER CONSTRUCTION TO AVOID INTERRUPTION OF SERVICE TO SURROUNDING 27.CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES FOR ANY REQUIRED UTILITY ADJUSTMENTS AND/OR RELOCATIONS 15. CONTRACTOR SHALL MAINTAIN WATER SERVICE AND WASTEWATER SERVICE TO ALL CUSTOMERS THROUGHOUT CONSTRUCTION (IF NECESSARY, BY USE OF TEMPORARY METHODS APPROVED BY THE CITY AND OWNER). THIS WORK SHALL BE CONSIDERED

> SHALL REPAIR ALL DAMAGED LINES IMMEDIATELY. ALL REPAIRS OF EXISTING WATER MAINS, WATER SERVICES, SEWER MAINS, AND SANITARY SEWER SERVICES ARE SUBSIDIARY TO THE WORK, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 17. VALVE ADJUSTMENTS SHALL BE CONSTRUCTED SUCH THAT THE COVERS ARE AT FINISHED SURFACE GRADE OF THE PROPOSEI 18. THE ENDS OF ALL EXISTING WATER MAINS THAT ARE CUT. BUT NOT REMOVED. SHALL BE PLUGGED AND ABANDONED IN PLACE. THIS

16. THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL WATER AND WASTEWATER LINES CROSSING THE PROJECT. THE CONTRACTOR

© COPYRIGHT 2017 KIMLEY-HORN AND ASSOCIATES, INC., ALL RIGHTS RESERVED

19. ALL FIRE HYDRANTS, VALVES, TEES, BENDS, WYES, REDUCERS, FITTINGS, AND ENDS SHALL BE MECHANICALLY RESTRAINED AND/OR THRUST BLOCKED TO CITY STANDARDS. 20.CONTRACTOR SHALL INSTALL A FULL SEGMENT OF WATER OR WASTEWATER PIPE CENTERED AT ALL UTILITY CROSSINGS SO THAT THE JOINTS ARE GREATER THAN 9-FEET FROM THE CROSSING

21.ALL CROSSINGS AND LOCATIONS WHERE WASTEWATER IS LESS THAN 9-FEET FROM WATER, WASTEWATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 217.53.

22.ALL CROSSING AND LOCATIONS WHERE WATER IS LESS THAN 9-FEET FROM WASTEWATER. WATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 290.44.

23.ALL WATER AND WASTEWATER SHALL BE TESTED IN ACCORDANCE WITH THE CITY, AWWA, AND TCEQ STANDARDS AND SPECIFICATIONS. AT A MINIMUM, THIS SHALL CONSIST OF THE FOLLOWING

SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. b. WASTEWATER LINES AND MANHOLES SHALL BE PRESSURE TESTED. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. AFTER COMPLETION OF THESE TESTS, A TELEVISION INSPECTION SHALL BE PERFORMED AND PROVIDED TO THE CITY AND OWNER ON A DVD. 24. CONTRACTOR SHALL INSTALL DETECTABLE WIRING OR MARKING TAPE A MINIMUM OF 12" ABOVE WATER AND WASTEWATER LINES.

MARKER DECALS SHALL BE LABELED "CAUTION - WATER LINE" OR "CAUTION - SEWER LINE" DETECTABLE WIRING AND MARKING TAPE SHALL COMPLY WITH CITY STANDARDS, AND SHALL BE INCLUDED IN THE COST OF THE WATER AND WASTEWATER PIPE. 25.DUCTILE IRON PIPE SHALL BE PROTECTED FROM CORROSION BY A LOW-DENSITY POLYETHYLENE LINER WRAP THAT IS AT LEAST A

a. ALL WATERLINES SHALL BE HYDROSTATICALLY TESTED AND CHLORINATED BEFORE BEING PLACED INTO SERVICE. CONTRACTOR

26.WATERLINES SHALL BE INSTALLED AT NO LESS THAN THE MINIMUM COVER REQUIRED BY THE CITY. 27. CONTRACTOR SHALL PROVIDE CLEAN-OUTS FOR PRIVATE SANITARY SEWER LINES AT ALL CHANGES IN DIRECTION AND 100-FOOT INTERVALS, OR AS REQUIRED BY THE APPLICABLE PLUMBING CODE. CLEAN-OUTS REQUIRED IN PAVEMENT OR SIDEWALKS SHALL HAVE CAST IRON COVERS FLUSH WITH FINISHED GRADE. 28.CONTRACTOR SHALL PROVIDE BACKWATER VALVES FOR PLUMBING FIXTURES AS REQUIRED BY THE APPLICABLE PLUMBING CODE (E.G

FLOOR ELEVATION OF FIXTURE UNIT IS BELOW THE ELEVATION OF THE MANHOLE COVER OF THE NEXT UPSTREAM MANHOLE IN THE PUBLIC SEWER). CONTRACTOR SHALL REVIEW BOTH MEP AND CIVIL PLANS TO CONFIRM WHERE THESE ARE REQUIRED. 29. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN. PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCI SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO

OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 30. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER. **ABBREVIATIONS AND DEFINITIONS:** ADA AMERICANS WITH DISABILITIES ACT AMERICAN WATER WORKS ASSOCIATION B-B BACK TO BACK **BEGIN CURVE** BACK OF CURB BCR BEGIN CURB RETURN BEST MANAGEMENT PRACTICE BOC BACK OF CURB BEGIN VERTICAL CURVE ELEVATION **BVCS** BEGIN VERTICAL CURVE STATION BOTTOM OF WALL BW CUBIC FEET PER SECOND CITY CITY, TOWN, OR OTHER APPLICABLE LOCAL GOVERNMENT JURISDICTION CENTERLINE CENTERLINE CONCRETE CUBIC YARD CY **DEMO** DEMOLITION DG DECOMPOSED GRANITE DETAIL FACH END CURVE **FCR** END CURB RETURN EXISTING GROUND FI EVATION ELECTRICAL / ELECTRICITY ELEV FI EVATION UNITES STATES ENVIRONMENTAL PROTECTION AGENCY FASEMENT END VERTICAL CURVE ELEVATION **EVCE** END VERTICAL CURVE STATION **EVCS EXISTING** FACE TO FACE FINISHED GROUND FIRE HYDRANT FLOW LINE FOC FACE OF CURB FEET HYDRAULIC GRADE LINE HGL KIMLEY-HORN AND ASSOCIATES, INC KIMLEY-HORN AND ASSOCIATES, INC. LATERAL LINEAR FEET MAXIMUM MATCH EXISTING ELEVATION MANHOLE

SINGLE LAYER OF 8-MIL. ALL DUCTILE IRON JOINTS SHALL BE BONDED.

THESE PLAN AND GENERAL NOTES REFER TO: GEOTECHNICAL ENGINEERING REPORT AAA21-116-00 , AAA21-115-00 INCLUDING ALL REVISIONS AND ADDENDA TO THIS REPORT THAT MAY HAVE BEEN RELEASED AFTER THE NOTED DATE.

TEXAS COMMISSION OF ENVIRONMENTAL QUALITY TXDOT TEXAS DEPARTMENT OF TRANSPORTATION TXMUTCD TEXAS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES TOP OF WALL

ARCHITECTURAL BARRIERS TEXAS ACCESSIBILITY STANDARDS

NOTICE OF INTENT, REF. TCEQ GENERAL PERMIT

NOT TO SCALE

POINT OF CURVATURE

POINT OF INFLECTION

POINT OF TANGENCY

POLYVINYL CHLORIDE

PROPOSED GRADE LINE

POINT OF REVERSE CURVATURE

POINT OF VERTICAL INFLECTION

REINFORCED CONCRETE PIPE

SANITARY SEWER MANHOLE

POUNDS PER SQUARE INCH

ON CENTER

PROPOSED

PAVEMENT

STATION

STANDARD

RIGHT OF WAY

SQUARE FEET

SQUARE YARD

SANITARY SEWER

OFFSET

PROP

PVMT

ROW

NOTICE OF TERMINATION, REF. TCEQ GENERAL PERMIT

OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION

PORTLAND CEMENT CONCRETE / POINT OF COMPOUND CURVATURE

TW **TYPICAL** VERTICAL CURVE WTR WATER WW WASTEWATER

> SITE PLAN APPROVAL SHEET 2 OF 48 FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024 APPROVED BY COMMISSION ON UNDER SECTION 112 OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE. ___CASE MANAGER CLARISSA E. DAVIS EXPIRATION DATE (25-5-81,LDC)___ PROJECT EXPIRATION DATE (ORD.#970905-A) DWPZ DDZ Know what's below. Director, Development Services Departmen RELEASED FOR GENERAL COMPLIANCE: ZONING MF-2, MF-2 CO Correction 1 Correction 2 Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans PRIOR TO CONSTRUCTION. which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.



20

JOSE M. FARIAS

GENERAL NOTES

- 1. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.
- 2. THE CONTRACTOR IS TO CONTACT ONE OF THE FOLLOWING: NATIONAL "CALL BEFORE YOU DIG" TEXAS EXCAVATION SAFETY SYSTEM (TESS) 1-800-344-8377 TEXAS ONE CALL SYSTEM (TOCS) 1-800-245-4545 I ONE STAR NOTIFICATION CENTER 1-800-669-8344 FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W.
- 3. CONTRACTOR SHALL NOTIFY THE DEPARTMENT OF PUBLIC WORKS AND TRANSPORTATION (DPWT) AT (512) 974-7161 AT LEAST 24 HOURS PRIOR TO INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE EASEMENT OR STREET R.O.W. THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S R.O.W. MUST BE APPROVED PRIOR TO THE START OF BACKFILL OPERATIONS.
- 4. FOR SLOPES OR TRENCHES GREATER THAN FIVE (5) FEET IN DEPTH, ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION. (OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE; INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN, TEXAS.)
- 5. ALL SITE WORK SHALL COMPLY WITH ENVIRONMENTAL REQUIREMENTS SET FORTH IN THE CITY OF AUSTIN LAND DEVELOPMENT CODE AND ENVIRONMENTAL CRITERIA MANUAL.
- 6. UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS AND PRIOR TO RELEASE OF THE CERTIFICATE OF OCCUPANCY OR FINAL INSPECTION RELEASE BY THE CITY, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DRAINAGE AND DETENTION FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED
- 7. DEVELOPER INFORMATION DEVELOPER: MARIELLE DEVELOPMENT GROUP, LLC ADDRESS: 104 TEXAS ASH COVE

MANCHACA, TX 78652

- A. OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: KIMLEY-HORN AND ASSOCIATES, INC. 10814 JOLLYVILLE RD, AVALLON IV, SUITE 200 AUSTIN. TX 78759 PHONE NO: 512-684-3232 CONTACT: KELLY BEST, P.E.
- B. PERSON OR FIRM RESPONSIBLE FOR EROSION / SEDIMENTATION CONTROL
- MAINTENANCE: DEVELOPER: MARIELLE DEVELOPMENT GROUP, LLC ADDRESS: 104 TEXAS ASH COVE MANCHACA, TX 78652
- PHONE NO: (XXX) XXX-XXXX CONTACT: MICHAEL VALENZUELA D. PERSON OR FIRM RESPONSIBLE FOR TREE / NATURAL AREA CONTROL
- DEVELOPER: MARIELLE DEVELOPMENT GROUP, LLC ADDRESS: 104 TEXAS ASH COVE MANCHACA, TX 78652 PHONE NO: (XXX) XXX-XXXX CONTACT: MICHAEL VALENZUELA
- 8. ALL CONSTRUCTION SHALL COMPLY WITH THE "CITY OF AUSTIN STANDARD SPECIFICATIONS," AS AMENDED BY SPECIAL PROVISION, CURRENT AT THE TIME OF
- 9. CONTRACTOR TO TAKE ALL DUE PRECAUTIONS TO PROTECT EXISTING FACILITIES FROM DAMAGE. ANY DAMAGE TO EXISTING FACILITIES INCURRED AS A RESULT OF THESE CONSTRUCTION OPERATIONS TO BE REPAIRED IMMEDIATELY BY THE CONTRACTOR, AT NO ADDITIONAL COST TO OWNER.
- 10. CONTRACTOR TO GIVE NOTICE TO ALL AUTHORIZED INSPECTORS. SUPERINTENDENTS OR PERSONS IN CHARGE OF PRIVATE AND PUBLIC UTILITIES AFFECTED BY HIS OPERATIONS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR TO MAKE CERTAIN THAT ALL CONSTRUCTION PERMITS THAT CAN ONLY BE ISSUED TO THE CONTRACTOR HAVE BEEN OBTAINED BY THE CONTRACTOR AT ITS EXPENSE PRIOR TO COMMENCEMENT OF WORK.
- 11. CONTRACTOR TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REQUIREMENTS REGARDING EXCESS AND WASTE MATERIAL, INCLUDING METHODS OF HANDLING AND DISPOSAL
- 12. CONTRACTOR TO COORDINATE INTERRUPTIONS OF ALL UTILITIES AND SERVICES. ALL WORK TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPLICABLE UTILITY COMPANY OR AGENCY INVOLVED.
- 13. LOCATION OF EXISTING UTILITIES SHOWN ON PLANS WAS COMPILED FROM RECORD INFORMATION. NO WARRANTY IS IMPLIED AS TO THE ACTUAL LOCATION OF EXISTING
- 14. WHEN UNLOCATED OR INCORRECTLY LOCATED UNDERGROUND PIPING, OR A BREAK LOCATED IN THE LINE, OR OTHER UTILITIES AND SERVICES ARE ENCOUNTERED DURING SITE WORK OPERATIONS, NOTIFY THE APPLICABLE UTILITY COMPANY IMMEDIATELY TO OBTAIN PROCEDURE DIRECTIONS. COOPERATE WITH THE APPLICABLE UTILITY COMPANY IN MAINTAINING ACTIVE SERVICES IN OPERATION.
- 15. CONTRACTOR TO LOCATE, PROTECT, AND MAINTAIN BENCHMARKS, MONUMENTS, CONTROL POINTS, AND PROJECT ENGINEERING REFERENCE POINTS. RE-ESTABLISH DISTURBED OR DESTROYED ITEMS BY REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AT NO ADDITIONAL COST TO OWNER.
- 16. CONTRACTOR TO CONTROL DUST CAUSED BY THE WORK AND COMPLY WITH POLLUTION
- CONTROL REGULATIONS OF GOVERNING AUTHORITIES. (NO SEPARATE PAY.) 17. THROUGHOUT THE CONSTRUCTION, AND AT THE COMPLETION OF CONSTRUCTION, THE

CONTRACTOR TO ENSURE THAT DRAINAGE OF STORM WATER RUNOFF IS NOT BLOCKED.

- 18. THESE PLANS, PREPARED BY KIMLEY-HORN AND ASSOCIATES. INC., DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONSTRUCTION CONTRACTOR OR ITS EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE SEAL OF KIMLEY-HORN AND ASSOCIATES, INC. REGISTERED PROFESSIONAL ENGINEER(S) HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEMS THAT MAY NOW OR HEREAFTER BE INCORPORATED INTO THESE PLANS. THE CONSTRUCTION CONTRACTOR TO PREPARE OR OBTAIN THE APPROPRIATE SAFETY SYSTEMS, INCLUDING THE PLANS AND SPECIFICATIONS REQUIRED BY HOUSE BILLS 662 AND 665 ENACTED BY THE TEXAS LEGISLATURE IN THE 70TH LEGISLATURE - REGULAR
- 19. TRAFFIC CONTROLS TO BE CONTRACTOR'S RESPONSIBILITY AND INSTALLED IN ACCORDANCE WITH THE "CITY OF AUSTIN MANUAL OF UNIFORM CONSTRUCTION BARRICADING STANDARDS." OCTOBER 1986. ADDITIONALLY, THE CONTRACTOR IS TO SCHEDULE THE WORK AND TRAFFIC CONTROLS TO ACHIEVE THE FOLLOWING TRAFFIC **GUIDELINES:**
- MINIMUM OF ONE ACCESS POINT TO PARKING LOTS TO REMAIN OPEN AT ALL TIMES. 20.CONTRACTOR TO EXERCISE CAUTION DURING CONSTRUCTION NEAR AND AROUND GAS

LINES. NOTIFY GAS COMPANY 24 HOURS PRIOR TO CONSTRUCTION.

- 21.NO BLASTING WITHIN 15 FEET OF EXISTING UTILITIES OR STRUCTURES. IF BLASTING IS TO BE USED BY THE CONTRACTOR, A BLASTING PERMIT MUST BE SECURED PRIOR TO COMMENCEMENT OF WORK. BLASTING TO BE IN ACCORDANCE WITH "CITY OF AUSTIN STANDARD SPECIFICATIONS" AND CRITERIA OF THE NATIONAL FIRE PROTECTION ASSOCIATION.
- 22.BURNING IS NOT ALLOWED ON THIS PROJECT.
- 23.CONTRACTOR TO INSTALL 1/2-INCH-DIAMETER BY 12-INCH-LONG REBAR VERTICALLY, WITH TWO (2) FEET OF SURVEYOR'S RIBBON ATTACHED, AT END OF ALL PIPE STUBS. TOP OF BAR TO BE NOT LESS THAN 12 INCHES BELOW THE FINISHED GRADE. A. BLUE RIBBON- WATER LINE D. ORANGE RIBBON- TELECOM DUCT
- B. GREEN RIBBON- WASTEWATER LINE E. RED RIBBON- ELECTRICAL DUCT BANK C. YELLOW RIBBON- GAS LINE
- 24.MAKE CONNECTION BETWEEN NEW AND EXISTING ASPHALT STREETS BY REMOVING EXISTING STREET FROM END BACK. UNTIL FULL DEPTH BASE AND HMAC ARE ENCOUNTERED AND HMAC APPEARS TO BE IN SOUND CONDITION. PROVIDE EXPANSION
- JOINT AND DOWELS WHERE CONNECTING EXISTING CURB TO NEW. 25.A CURB LAY DOWN IS REQUIRED AT ALL POINTS WHERE THE PROPOSED SIDEWALK INTERSECTS THE CURB.
- 26.UNLESS OCCURRING AT AN EXPANSION JOINT, MAKE CONNECTION BETWEEN NEW AND EXISTING SIDEWALK BY EXPOSING AND CLEANING A ONE-FOOT LENGTH OF WELDED WIRE REINFORCEMENT AND LAPPING NEW REINFORCEMENT ONTO THIS LENGTH.
- 27.CONCRETE FOR SITE WORK, OTHER THAN CONCRETE PAVEMENT AND STRUCTURES, TO BE CLASS "A" (5 SACK, 3,500 PSI @ 28-DAYS) AND ALL REINFORCING STEEL TO BE ASTM A615 60, UNLESS OTHERWISE NOTED. REFER TO GEOTECHNICAL REPORT AND ARCHITECTURAL DRAWINGS FOR PAVEMENT STRUCTURAL SPECIFICATIONS.

GENERAL NOTES (CONTINUED)

- 28. TREE SURVEY, CONTOURS, AND BENCHMARK INFORMATION SUPPLIED BY OTHERS. ACTUAL LOCATION OF TREES AND ELEVATION OF NATURAL GROUND ON THE PROJECT SITE MAY VARY FROM WHAT IS DEPICTED ON THE PLAN SHEETS. KIMLEY-HORN AND ASSOCIATES, INC. IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION REGARDING SURVEYS OR BENCHMARK LOCATIONS. BENCHMARKS ARE AS FOLLOWS:
- TBM #1 SQUARE CUT ON TOP OF CONCRETE CURB AT THE MIDDLE OF THE NOSE ON THE EAST END OF THE MEDIAN OF THE INTERSECTION OF I-35 FRONTAGE ROAD AND AVENIDA MERCADO STREET, ±12' SOUTHEAST FROM A LIGHT POLE, AND ±33' NORTHEAST FROM A YIELD SIGN. **ELEVATION = 745.46'**
- TBM #2 SQUARE CUT ON TOP OF CONCRETE CURB AT THE MIDDLE OF THE NOSE ON THE NORTH END OF THE MEDIAN ON ESTANCIA PARKWAY +13 FEET NORTHWEST FROM A STORM MANHOLE IN ESTANCIA PARKWAY. AND ±64' NORTHEAST FROM A LIGHT POLE IN THE MEDIAN ELEVATION = 727.40'
- 29. DEMOLITION PERMITS (IF NEEDED) ARE TO BE OBTAINED BY THE CONTRACTOR AT THEIR EXPENSE.
- 30. CONTRACTOR SHALL REFER TO THE GEOTECHNICAL INVESTIGATION REPORT FOR THIS SITE FOR SUBSURFACE INFORMATION REGARDING THIS PROJECT. AT ITS EXPENSE THE CONTRACTOR IS ENCOURAGED TO MAKE ADDITIONAL SUBSURFACE
- 31. CONTRACTOR TO FIELD VERIFY LOCATION AND FLOWLINES OF EXISTING UTILITIES PRIOR TO INSTALLATION OF PROPOSED UTILITY. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES.
- 32. PUMPING OF STORMWATER FROM EXCAVATIONS IS PROHIBITED UNLESS THE STORMWATER IS DISCHARGED TO ENCOURAGE SHEET/OVERLAND FLOW. ADDITIONAL EROSION AND SEDIMENTATION CONTROLS MAY BE REQUIRED, AT NO ADDITIONAL COST TO THE OWNER.
- 33. UNLESS OTHERWISE NOTED, STORM SEWERS TO BE: 6"-15" SDR 35 PVC. 18" AND GREATER RCP ASTM-C76 CLASS III.
- 34. ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS ONE SQUARE FOOT IN TOTAL AREA, BLOWS AIR FROM WITHIN THE SUBSTRATE. AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION.
- 35. CONTRACTOR SHALL CALL THE ONE CALL CENTER (472-2822) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W.
- 36. CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTION DIVISION OF THE CITY'S ONE STOP SHOP (OSS) AT 974-6360 OR 974-7034 AT LEAST 24 HOURS PRIOR O THE INSTALLATION OF ANY DRAINAGE FACILITY WITHIN A DRAINAGE EASEMENT OR STREET R.O.W.THE METHOD OF PLACEMENT AND COMPACTION OF BACKFILL IN THE CITY'S R.O.W. MUST BE APPROVED PRIOR TO THE START OF BACKFILL
- 37. FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH. A NOTE MUST BE ADDED STATING: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION." (OSHA STANDARDS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE; INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN
- 38. ALL SITE WORK MUST ALSO COMPLY WITH ENVIRONMENTAL REQUIREMENTS.
- 39. UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS AND PRIOR TO THE FOLLOWING, THE ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DRAINAGE, FILTRATION AND DETENTION FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.: RELEASE OF THE CERTIFICATE OF OCCUPANCY BY THE DEVELOPMENT SERVICES DEPARTMENT (INSIDE THE CITY LIMITS); OR INSTALLATION OF AN ELECTRIC OR WATER METER (IN THE FIVE-MILE

AMERICANS WITH DISABILITIES ACT

THE CITY OF AUSTIN HAS REVIEWED THIS PLAN FOR COMPLIANCE WITH CITY DEVELOPMENT REGULATIONS ONLY. THE APPLICANT, PROPERTY OWNER, AND OCCUPANT OF THE PREMISES ARE RESPONSIBLE FOR DETERMINING WHETHER THE PLAN COMPLIES WITH ALL OTHER LAWS, REGULATIONS, AND RESTRICTIONS WHICH MAY BE APPLICABLE TO THE PROPERTY AND ITS USE.

- ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRE A SITE PLAN AMENDMENT AND APPROVAL FROM THE DEVELOPMENT SERVICES DEPARTMENT.
- THE OWNER IS RESPONSIBLE FOR ALL COST OF RELOCATION, OR DAMAGE TO,
- 3. ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE.

FIRE DEPARTMENT NOTES

- . THE AUSTIN FIRE DEPARTMENT REQUIRES FINAL ASPHALT OR CONCRETE PAVEMENT ON REQUIRED ACCESS ROADS PRIOR TO THE START OF COMBUSTIBLE CONSTRUCTION. ANY OTHER METHOD OF PROVIDING "ALL-WEATHER DRIVING CAPABILITIES" SHALL BE REQUIRED TO BE DOCUMENTED AND APPROVED AS AN ALTERNATE METHOD OF CONSTRUCTION IN ACCORDANCE WITH THE APPLICABLE RULES FOR TEMPORARY ROADS OUTLINED IN THE CITY OF AUSTIN FIRE PROTECTION CRITERIA MANUAL.
- 2. FIRE HYDRANTS SHALL BE INSTALLED WITH THE CENTER OF THE FOUR (4) INCH OPENING (STEAMER) LOCATED AT LEAST 18 INCHES ABOVE FINISHED GRADE. THE STEAMER OPENING OF FIRE HYDRANTS SHALL FACE THE APPROVED FIRE ACCESS DRIVEWAY OR PUBLIC STREET AND SET BACK FROM THE CURB LINE(S) AN APPROVED DISTANCE, TYPICALLY THREE (3) TO SIX (6) FEET, THE AREA WITHIN THREE (3) FEET IN ALL DIRECTIONS FROM ANY FIRE HYDRANT SHALL BE FREE OF OBSTRUCTIONS, AND THE AREA BETWEEN THE STEAMER OPENING AND THE STREET OR DRIVEWAY GIVING EMERGENCY VEHICLE ACCESS SHALL BE FREE OF OBSTRUCTIONS.
- 3. TIMING OF INSTALLATIONS: WHEN FIRE PROTECTION FACILITIES ARE INSTALLED BY THE CONTRACTOR, SUCH FACILITIES SHALL INCLUDE SURFACE ACCESS ROADS. EMERGENCY ACCESS ROADS OR DRIVES SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DURING THE TIME OF CONSTRUCTION. WHEN THE FIRE DEPARTMENT APPROVES AN ALTERNATE METHOD OF PROTECTION. THIS REQUIREMENT MAY BE MODIFIED AS DOCUMENTED IN THE APPROVAL OF THE ALTERNATE METHOD.
- 4. ALL EMERGENCY ACCESS ROADWAYS AND FIRE LANES, INCLUDING PERVIOUS/DECORATIVE PAVING, SHALL BE ENGINEERED AND INSTALLED AS REQUIRED TO SUPPORT THE AXLE LOADS OF EMERGENCY VEHICLES. A LOAD CAPACITY SUFFICIENT TO MEET THE REQUIREMENTS FOR HS-20 LOADING (16 KIPS/WHEEL) AND A TOTAL VEHICLE LIVE LOAD OF 80,000 POUNDS IS CONSIDERED COMPLIANT WITH THIS REQUIREMENT. ANY PERVIOUS/DECORATIVE PAVING WITHIN 100 FEET OF ANY BUILDING MUST BE APPROVED BY THE FIRE DEPARTMENT.
- 5. FIRE LANES DESIGNATED ON SITE PLANS SHALL BE REGISTERED WITH THE CITY OF AUSTIN FIRE DEPARTMENT AND INSPECTED FOR FINAL APPROVAL.
- 6. THE MINIMUM VERTICAL CLEARANCE REQUIRED FOR EMERGENCY VEHICLE ACCESS ROADS OR DRIVES IS 14 FEET FOR THE FULL WIDTH OF THE ROADWAY OR DRIVEWAY.
- 7. COMMERCIAL DUMPSTERS AND CONTAINERS WITH AN INDIVIDUAL CAPACITY OF 1.5 CUBIC YARDS OR GREATER SHALL NOT BE STORED OR PLACED WITHIN TEN FEET OF OPENINGS, COMBUSTIBLE WALLS, OR COMBUSTIBLE EAVE LINES.

ENVIRONMENTAL NOTES:

SPECIAL CONSTRUCTION TECHNIQUES ECM 3.5.4(D). PRIOR TO EXCAVATION WITHIN TREE DRIPLINES OR THE REMOVAL OF TREES ADJACENT TO OTHER TREES THAT ARE TO REMAIN, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT TO MINIMIZE ROOT DAMAGE. IN CRITICAL ROOT ZONE AREAS THAT CANNOT BE PROTECTED DURING CONSTRUCTION WITH FENCING AND WHERE HEAVY VEHICULAR TRAFFIC IS ANTICIPATED, COVER THOSE AREAS WITH A MINIMUM OF 12 INCHES OF ORGANIC MULCH TO MINIMIZE SOIL COMPACTION. IN AREAS WITH HIGH SOIL PLASTICITY GEOTEXTILE FABRIC. PER STANDARD SPECIFICATION 620S. SHOULD BE PLACED UNDER THE MULCH TO PREVENT EXCESSIVE MIXING OF THE SOIL AND MULCH ADDITIONALLY MATERIAL SUCH AS PLYWOOD AND METAL SHEETS, COULD BE REQUIRED BY THE CITY ARBORIST TO MINIMIZE ROOT IMPACTS FROM HEAVY EQUIPMENT. ONCE THE PROJECT IS COMPLETED, ALL MATERIALS SHOULD BE REMOVED, AND THE MULCH SHOULD BE REDUCED TO A DEPTH OF 3 INCHES. PERFORM ALL GRADING WITHIN CRITICAL ROOT ZONE AREAS BY HAND OR WITH SMALL EQUIPMENT TO MINIMIZE ROOT DAMAGE. WATER ALL TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. SPRAY TREE CROWNS WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES. WHEN INSTALLING CONCRETE ADJACENT TO THE ROOT ZONE OF A TREE, USE A PLASTIC VAPOR BARRIER BEHIND THE CONCRETE TO PROHIBIT LEACHING OF LIME INTO

- ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRE A SITE PLAN AMENDMENT AND APPROVAL FROM THE DEVELOPMENT SERVICES DEPARTMENT.
- APPROVAL OF THIS SITE PLAN DOES NOT INCLUDE BUILDING CODE AND FIRE CODE APPROVAL NOR BUILDING PERMIT APPROVAL. A CITY DEMOLITION OR RELOCATION PERMIT CAN ONLY BE ISSUED ONCE THE HISTORIC REVIEW PROCESS IS COMPLETED.
- ALL SIGNS MUST COMPLY WITH THE REQUIREMENTS OF THE SIGN AND LAND DEVELOPMENT CODE.
- THE OWNER IS RESPONSIBLE FOR ALL COST OF RELOCATION, OR DAMAGE TO,
- ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE.

FOR RELOCATION OF, OR DAMAGE TO UTILITIES.

- A DEVELOPMENT PERMIT MUST BE ISSUED PRIOR TO AN APPLICATION FOR BUILDING PERMIT FOR NON-CONSOLIDATED OR PLANNING COMMISSION APPROVED SITE PLANS.
- 7. WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY THE CITY OF AUSTIN.
- 8. ALL EXISTING STRUCTURES SHOWN TO BE REMOVED WILL REQUIRE A DEMOLITION PERMIT FROM THE CITY OF AUSTIN DEVELOPMENT SERVICES DEPARTMENT. FOR DRIVEWAY CONSTRUCTION: THE CONTRACTOR IS RESPONSIBLE FOR ALL COSTS
- 10. FOR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, A ROW EXCAVATION PERMIT IS

TREE PROTECTION NOTES

- 1. ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE PROTECTED DURING CONSTRUCTION WITH TEMPORARY FENCING.
- 2. PROTECTIVE FENCES SHALL BE ERECTED ACCORDING TO CITY OF AUSTIN STANDARDS FOR
- 3. PROTECTIVE FENCES SHALL BE INSTALLED PRIOR TO THE START OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR GRADING), AND SHALL BE MAINTAINED THROUGHOUT ALL PHASES OF THE CONSTRUCTION PROJECT.
- 4. EROSION AND SEDIMENTATION CONTROL BARRIERS SHALL BE INSTALLED OR MAINTAINED IN A MANNER WHICH DOES NOT RESULT IN SOIL BUILD-UP WITHIN TREE DRIP LINES. . PROTECTIVE FENCES SHALL SURROUND THE TREES OR GROUP OF TREES, AND WILL BE LOCATED AT THE OUTERMOST LIMIT OF BRANCHES (DRIP LINE). FOR NATURAL AREAS.
- PREVENT THE FOLLOWING: A. SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC OR STORAGE OF EQUIPMENT OR MATERIALS;

PROTECTIVE FENCES SHALL FOLLOW THE LIMIT OF CONSTRUCTION LINE, IN ORDER TO

- B. ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN 6 INCHES CUT OR FILL), OR TRENCHING NOT REVIEWED AND AUTHORIZED BY THE CITY ARBORIST;
- C. WOUNDS TO EXPOSED ROOTS, TRUNK OR LIMBS BY MECHANICAL EQUIPMENT; D. OTHER ACTIVITIES DETRIMENTAL TO TREES SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING, AND FIRES.
- 6. EXCEPTIONS TO INSTALLING FENCES AT TREE DRIP LINES MAY BE PERMITTED IN THE
- A. WHERE THERE IS TO BE AN APPROVED GRADE CHANGE, IMPERMEABLE PAVING SURFACE, TREE WELL, OR OTHER SUCH SITE DEVELOPMENT, ERECT THE FENCE APPROXIMATELY 2 TO 4 FEET BEYOND THE AREA DISTURBED; B. WHERE PERMEABLE PAVING IS TO BE INSTALLED WITHIN A TREE'S DRIP LINE, ERECT THE
- SO THAT THIS AREA IS GRADED SEPARATELY PRIOR TO PAVING INSTALLATION TO MINIMIZED ROOT DAMAGE); C. WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE TO ALLOW 6 TO

FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA (PRIOR TO SITE GRADING

- 10 FEET OF WORK SPACE BETWEEN THE FENCE AND THE BUILDING; D. WHERE THERE ARE SEVERE SPACE CONSTRAINTS DUE TO TRACT SIZE, OR OTHER SPECIAL REQUIREMENTS, CONTACT THE CITY ARBORIST AT 512-974-1876 TO DISCUSS
- SPECIAL NOTE: FOR THE PROTECTION OF NATURAL AREAS, NO EXCEPTIONS TO INSTALLING 6 FENCES AT THE LIMIT OF CONSTRUCTION LINE WILL BE PERMITTED. 7. WHERE ANY OF THE ABOVE EXCEPTIONS RESULT IN A FENCE BEING CLOSER THAN 4 FEET
- TO A TREE TRUNK, PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF 8 FT (OR TO THE LIMITS OF LOWER BRANCHING) IN ADDITION TO THE REDUCED FENCING
- 8. TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER WHICH DOES NOT IMPACT TREES TO BE PRESERVED.
- 9 ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL. BACKFILL ROOT AREAS WITH GOOD QUALITY TOP SOIL AS SOON AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN 2 DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
- 10. ANY TRENCHING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE
- 11.NO LANDSCAPE TOPSOIL DRESSING GREATER THAN 4 INCHES SHALL BE PERMITTED WITHIN THE DRIP LINE OF TREES. NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE. 12. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND
- EQUIPMENT SHALL TAKE PLACE BEFORE DAMAGE OCCURS (RIPPING OF BRANCHES, ETC.). 13. ALL FINISHED PRUNING SHALL BE DONE ACCORDING TO RECOGNIZED, APPROVED STANDARDS OF THE INDUSTRY (REFERENCE THE NATIONAL ARBORIST ASSOCIATION PRUNING STANDARDS FOR SHADE TREES AVAILABLE ON REQUEST FROM THE CITY
- 14. DEVIATIONS FROM THE ABOVE NOTES MAY BE CONSIDERED ORDINANCE VIOLATIONS IF THERE IS SUBSTANTIAL NON-COMPLIANCE OR IF A TREE SUSTAINS DAMAGE AS A RESULT.

- 1. AUSTIN ENERGY HAS THE RIGHT TO PRUNE AND/OR REMOVE TREES, SHRUBBERY AND OTHER OBSTRUCTIONS TO THE EXTENT NECESSARY TO KEEP THE EASEMENTS CLEAR. AUSTIN ENERGY WILL PERFORM ALL TREE WORK IN COMPLIANCE WITH CHAPTER 25-8. SUBCHAPTER B OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- 2. THE OWNER/DEVELOPER OF THIS SUBDIVISION/LOT SHALL PROVIDE AUSTIN ENERGY WITH ANY EASEMENT AND/OR ACCESS REQUIRED, IN ADDITION TO THOSE INDICATED, FOR THE INSTALLATION AND ONGOING MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8 OF THE CITY OF AUSTIN LAND DEVELOPMENT
- 3. THE OWNER SHALL BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY EROSION CONTROL, REVEGETATION AND TREE PROTECTION. IN ADDITION, THE OWNER SHALL BE RESPONSIBLE FOR ANY INITIAL TREE PRUNING AND TREE REMOVAL THAT IS WITHIN TEN FEET OF THE CENTER LINE OF THE PROPOSED OVERHEAD ELECTRICAL FACILITIES DESIGNED TO PROVIDE ELECTRIC SERVICE TO THIS PROJECT. THE OWNER SHALL INCLUDE AUSTIN ENERGY'S WORK WITHIN THE LIMITS OF CONSTRUCTION FOR THIS PROJECT
- 4. THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRIC SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATION, CITY OF AUSTIN RULES AND REGULATIONS
 FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AND TEXAS STATE I AWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES AND EQUIPMENT. AUSTIN ENERGY WILL NOT RENDER ELECTRIC SERVICE UNLESS REQUIRED CLEARANCES ARE MAINTAINED. ALL COSTS
- CHARGED TO THE OWNER. 5. ANY RELOCATION OF ELECTRIC FACILITIES SHALL BE AT LANDOWNER'S/DEVELOPER'S EXPENSE.

- APPENDIX P-1: EROSION CONTROL NOTES THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS
- AND TREE/NATURAL AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR EXCAVATION) THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENVIRONMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN THE COA ESC.
 - PLAN SHALL BE CONSULTED AND USED AS THE BASIS FOR A TPDES REQUIRED SWPPP, IF A SWPPP IS REQUIRED, IT SHALL BE AVAILABLE FOR REVIEW BY THE CITY OF AUSTIN ENVIRONMENTAL INSPECTOR AT ALL TIMES DURING CONSTRUCTION. INCLUDING AT THE PRE-CONSTRUCTION MEETING. THE CHECKLIST BELOW CONTAINS THE BASIC ELEMENTS THAT SHALL BE REVIEWED FOR PERMIT APPROVAL BY COA EV PLAN REVIEWERS AS WELL AS COA EV INSPECTORS.
 - PLAN SHEETS SUBMITTED TO THE CITY OF AUSTIN MUST SHOW THE FOLLOWING:
 - •• DIRECTION OF FLOW DURING GRADING OPERATIONS. •• LOCATION, DESCRIPTION, AND CALCULATIONS FOR OFF-SITE FLOW DIVERSION STRUCTURES.
 - •• AREAS THAT WILL NOT BE DISTURBED; NATURAL FEATURES TO BE PRESERVED •• DELINEATION OF CONTRIBUTING DRAINAGE AREA TO EACH PROPOSED BMP (E.G., SILT FENCE, SEDIMENT BASIN, ETC.) •• LOCATION AND TYPE OF E&S BMPS FOR EACH PHASE OF DISTURBANCE. •• CALCULATIONS FOR BMPS AS REQUIRED.
 - •• LOCATION AND DESCRIPTION OF TEMPORARY STABILIZATION MEASURES. •• LOCATION OF ON-SITE SPOILS, DESCRIPTION OF HANDLING AND DISPOSAL OF BORROW MATERIALS, AND DESCRIPTION OF ON-SITE PERMANENT SPOILS DISPOSAL AREAS, INCLUDING SIZE, DEPTH OF FILL
 - AND REVEGETATION PROCEDURES. •• DESCRIBE SEQUENCE OF CONSTRUCTION AS IT PERTAINS TO ESC INCLUDING THE FOLLOWING ELEMENTS: ••• INSTALLATION SEQUENCE OF CONTROLS (E.G. PERIMETER
 - CONTROLS, THEN SEDIMENT BASINS, THEN TEMPORARY STABILIZATION, THEN PERMANENT, ETC) ••• PROJECT PHASING IF REQUIRED (LOC GREATER THAN 25 ACRES) ••• SEQUENCE OF GRADING OPERATIONS AND NOTATION OF
 - TEMPORARY STABILIZATION MEASURES TO BE USED ••• SCHEDULE FOR CONVERTING TEMPORARY BASINS TO PERMANENT WQ CONTROLS ••• SCHEDULE FOR REMOVAL OF TEMPORARY CONTROLS
 - ••• ANTICIPATED MAINTENANCE SCHEDULE FOR TEMPORARY CONTROLS • CATEGORIZE EACH BMP UNDER ONE OF THE FOLLOWING AREAS OF BMP ACTIVITY AS DESCRIBED BELOW: •• MINIMIZE DISTURBED AREA AND PROTECT NATURAL FEATURES AND SOIL
 - •• CONTROL STORMWATER FLOWING ONTO AND THROUGH THE PROJECT • STABILIZE SOILS • PROTECT SLOPES
 - •• PROTECT STORM DRAIN INLETS •• ESTABLISH PERIMETER CONTROLS AND SEDIMENT BARRIERS
 - •• RETAIN SEDIMENT ON-SITE AND CONTROL DEWATERING PRACTICES •• ESTABLISH STABILIZED CONSTRUCTION EXITS ANY ADDITIONAL BMPS • NOTE THE LOCATION OF EACH BMP ON YOUR SITE MAP(S).
 - FOR ANY STRUCTURAL BMPS, YOU SHOULD PROVIDE DESIGN SPECIFICATIONS AND DETAILS AND REFER TO THEM. • FOR MORE INFORMATION, SEE CITY OF AUSTIN ENVIRONMENTAL CRITERIA
 - THE PLACEMENT OF TREE/NATURAL AREA PROTECTIVE FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL ARFA PLAN
 - A PRE-CONSTRUCTION CONFERENCE SHALL BE HELD ON-SITE WITH THE CONTRACTOR. DESIGN ENGINEER/PERMIT APPLICANT AND ENVIRONMENTAL INSPECTOR AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTION MEASURES AND PRIOR TO BEGINNING ANY SITE PREPARATION WORK. THE OWNER OR OWNER'S REPRESENTATIVE SHALL NOTIFY THE DEVELOPMENT SERVICES DEPARTMENT, 974-2278, AT LEAST THREE DAYS PRIOR TO THE MEETING DATE. COA APPROVED ESC PLAN AND TPDES SWPPP (IF REQUIRED) SHOULD BE REVIEWED BY COA EV INSPECTOR AT THIS TIME
 - ANY MAJOR VARIATION IN MATERIALS OR LOCATIONS OF CONTROLS OR FENCES FROM THOSE SHOWN ON THE APPROVED PLANS WILL REQUIRE A REVISION AND MUST BE APPROVED BY THE REVIEWING ENGINEER ENVIRONMENTAL SPECIALIST OR CITY ABORIST AS APPROPRIATE. MAJOR REVISIONS MUST BE APPROVED BY THE DEVELOPMENT SERVICES DEPARTMENT, MINOR CHANGES TO BE MADE AS FIELD REVISIONS TO THI EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THI ENVIRONMENTAL INSPECTOR DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES THE CONTRACTOR IS REQUIRED TO PROVIDE A CERTIFIED INSPECTOR WITH
 - EITHER A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC). CERTIFIED EROSION. SEDIMENT AND STORMWATER-INSPECTOR (CESSWI) OR CERTIFIED INSPECTOR OF SEDIMENTATION AND EROSION CONTROLS (CISEC) CERTIFICATION TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO INSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH
 - PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED. ACCUMULATED SEDIMENT REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES 8. ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS; ONE SQUARE FOOT IN TOTAL AREA; BLOWS AIR FROM WITHIN THE

REACHES SIX (6) INCHES.

SHALL BE AS FOLLOWS:

- SUBSTRATE AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER O IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION. TEMPORARY AND PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED BELOW. • ALL DISTURBED AREAS TO BE REVEGETATED ARE REQUIRED TO PLACE A
- ITEM NO. 601S.3(A)]. DO NOT ADD TOPSOIL WITHIN THE CRITICAL ROOT ZONE OF EXISTING TREES. •• TOPSOIL SALVAGED FROM THE EXISTING SITE IS ENCOURAGED FOR USE, BUT IT SHOULD MEET THE STANDARDS SET FORTH IN 601S. • AN OWNER/ENGINEER MAY PROPOSE USE OF ONSITE SALVAGED TOPSOIL WHICH DOES NOT MEET THE CRITERIA OF STANDARD SPECIFICATION 601S BY PROVIDING A SOIL ANALYSIS AND A WRITTEN STATEMENT FROM A
- QUALIFIED PROFESSIONAL IN SOILS, LANDSCAPE ARCHITECTURE, OR AGRONOMY INDICATING THE ONSITE TOPSOIL WILL PROVIDE AN EQUIVALENT GROWTH MEDIA AND SPECIFYING WHAT, IF ANY, SOIL AMENDMENTS ARE REQUIRED. •• SOIL AMENDMENTS SHALL BE WORKED INTO THE EXISTING ONSITE TOPSOIL WITH A DISC OR TILLER TO CREATE A WELL-BLENDED MATERIAL
- TOPSOIL SALVAGED FROM THE EXISTING SITE MAY OFTEN BE USED, BUT IT SHOULD MEET THE SAME STANDARDS AS SET FORTH IN THESE STANDARDS. • THE VEGETATIVE STABILIZATION OF AREAS DISTURBED BY CONSTRUCTION
- FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH OR INCLUDE A COOL SEASON COVER CROP: (WESTERN WHEATGRASS (PASCOPYRUM SMITHII) AT 5.6 POUNDS PER ACRE, OATS (AVENA SATIVA) AT 4.0 POUNDS PER ACRE, CEREAL RYE GRAIN (SECALE CEREALE) AT 45 POUNDS PER ACRE. CONTRACTOR MUST ENSURE THAT ANY SEED APPLICATION REQUIRING A COOL

MULTIFLORUM) OR PERENNIAL RYEGRASS (LOLIUM PERENNE). COOL SEASON

AT A RATE OF 45 POUNDS PER ACRE OR A NATIVE PLANT SEED MIX CONFORMING TO ITEMS 604S OR 609S

SEASON COVER CROP DOES NOT UTILIZE ANNUAL RYEGRASS (LOLIUM

COVER CROPS ARE NOT PERMANENT EROSION CONTROL.

- A. FERTILIZER SHALL BE APPLIED ONLY IF WARRANTED BY A SAOIL TEST INCURRED BECAUSE OF FAILURE TO COMPLY WITH THE REQUIRED CLEARANCES WILL BE AND CONFORM TO ITEM NO. 606S, FERTILIZER. FERTILIZATION SHOULD NOT OCCUR WHEN RAINFALL IS EXPECTED OR DURING SLOW PLANT GROWTH OR DORMANCY. CHEMICAL FERTILIZER MAY NOT BE APPLIED IN THE CRITICAL WATER ZONE.
 - B. HYDROMULCH SHALL COMPLY WITH TABLE1, BELOW. C. TEMPORARY EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 11/2 INCHES HIGH WITH A MINIMUM OF 95% TOTAL COVERAGE SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR TEMPORARY STABILIZATION ARE UNIFORMLY VEGETATED, AND PROVIDED THERE ARE NO BARE SPOTS LARGER THAN 10 SQUARE FEET EXIST
 - D. WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, AND STANDARD SPECIFICATIONS 604S OR 609S.

| MATERIAL | DESCRIPTION | LONGEVITY | TYPICAL APPLICATIONS | APPLICATION RATES |
|------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|------------|-----------------------------------------|------------------------------|
| 100%, OR ANY BLEND OF WOOD, GELLULOSE, STRAW, AND/OR COTTON PLANT MATERIAL (EXCEPT NO MULCH SHALL EXCEED 30% PAPER) | 70% OR GREATER WOOD/STRAW 30% OR LESS PAPER OR NATURAL FIBERS | 0-3 MONTHS | MODERATE SLOPES; FROM FLAT TO 3:1 | 1500 TO 2000 LBS PER ACRE |

PERMANENT VEGETATIVE STABILIZATION: . FROM SEPTEMBER 15 TO MARCH 1, SEEDING IS CONSIDERED TO BE TEMPORARY STABILIZATION ONLY. IF COOL SEASON COVER CROPS EXIST WHERE PERMANENT VEGETATIVE STABILIZATION IS DESIRED. THE GRASSES SHALL BE MOWED TO A HEIGHT OF LESS THAN ONE-HALF (%) INCH AND THE AREA SHALL BE RE-SEEDED IN ACCORDANCE WITH TABLE 2 BELOW ALTERNATIVELY, THE COOL SEASON COVER CROP CAN BE MIXED WITH BERMUDA GRASS OR NATIVE SEED AND INSTALLED TOGETHER UNDERSTANDING THAT GERMINATION OF WARM-SEASON SEED TYPICALLY REQUIRES SOIL TEMPERATURES OF 60 TO 70 DEGREES. P. FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED

BERMUDA AT A RATE OF 45 POUNDS PER ACRE WITH A PURITY OF 95% AND A MINIMUM PURE LIVE SEED (PLS) OF 0.83. BERMUDA GRASS IS A WARM SEASON GRASS AND IS CONSIDERED PERMANENT EROSION CONTROL PERMANENT VEGETATIVE STABILIZATION CAN ALSO BE ACCOMPLISHED WITH A NATIVE PLANT SEED MIX CONFORMING TO ITEMS 604S OR 609S. A. FERTILIZER USE SHALL FOLLOW THE RECOMMENDATION OF A SOIL TEST. SEE ITEM 606S, FERTILIZER. APPLICATIONS OF FERTILIZER (AND PESTICIDE) ON CITY-OWNED AND MANAGED PROPERTY REQUIRES THE YEARLY SUBMITTAL OF A PESTICIDE AND FERTILIZER APPLICATION RECORD, ALONG WITH A CURRENT COPY OF THE APPLICATOR'S LICENSE FOR CURRENT COPY OF THE RECORD TEMPLATE CONTACT THE CITY OF AUSTIN'S IPM COORDINATOR.

- INITIATIVES.
- NO BARE SPOTS LARGER THAN 16 SQUARE FEET.
- E. WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA

| MANUAL, ITE | M2 6042 AND | 0095. | | |
|-------------------------------------|-------------------------------------------------------------------------------|-------------------------------------------------------|----------------------------------------------------------------------|----------------------------------------------------------------------|
| | TABLE 2: HYDRON | JULCHING FOR PERM | IANENT VEGETATIVE STABILIZ | ATION |
| MATERIAL | DESCRIPTION | LONGEVITY | TYPICAL APPLICATIONS | APPLICATION RATES |
| BONDED FIBER MATRIX (BFM) | 80% ORGANIC DEFIBRATED FIBERS | | | |
| 10% TACKIFIER | 6 MONTHS | ON SLOPES UP TO 2:1 AND EROSIVE SOIL CONDITIONS | 2,500 TO 4,000 LBS PER ACRE (SEE MANUFACTURES RECOMMENDATIONS) | |
| FIBER REINFORCED MATRIX (FRM) | 65% ORGANIC DEFIBRATED FIBERS 25% FIBERS OR LESS 10% TACKIFIER | UP TO 12 MONTHS | ON SLOPES UP TO 1:1 AND EROSIVE SOIL CONDITIONS | 3,000 TO 4,500 LBS PER ACRE (SEE MANUFACTURES RECOMMENDATIONS) |

- CONTACT: MICHAEL VALENZUELA F. OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: KIMLEY-HORN AND ASSOCIATES, INC.
- PHONE NO: 512-684-3232 CONTACT: KELLY BEST, P.E. G. PERSON OR FIRM RESPONSIBLE FOR EROSION / SEDIMENTATION CONTROL MAINTENANCE: DEVELOPER: MARIELLE DEVELOPMENT GROUP, LLC ADDRESS: 104 TEXAS ASH COVE MANCHACA, TX 78652 CONTACT: MICHAEL VALENZUELA
- H. PERSON OR FIRM RESPONSIBLE FOR TREE / NATURAL AREA CONTROL MAINTENANCE
- 11. THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT NOTIFYING THE DEVELOPMENT SERVICES DEPARTMENT AT 974-2278 AT LEAST 48 HOURS PRIOR WITH THE LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL

3.6.2 Standard Plan Note

The following plan note summarizes the contents of the Environmental Criteria Manual as it relates to tree protection on sites with active permits:

All trees and natural areas shown on plan to be preserved shall be protected per ECM 3.6.1 ree protection shall be installed prior to the start of any site work, including demolition or site preparation

Fencing for tree protection shall be chain-link mesh with a minimum height of 5 feet and shall be installed und or beyond the Critical Root Zone except as allowed in ECM 3.6.1.B.4. Unfenced sections of the Critical Root Zone shall be covered with mulch at a minimum depth of 8 inches and a maximum depth of 12 inches per ECM 3.6.1.C

Where fencing is located 5 feet or less from the trunk of a preserved tree, trunk wrapping shall be installed per ECM 3.6.1.D

Erosion and sedimentation controls shall be installed and maintained so as not to cause impacts that exceed reservation criteria listed in ECM 3.5.3.D. DURING CONSTRUCTION ees approved for removal shall be removed in a manner that does not exceed preservation criteria for the

ncing may not be temporarily moved or removed during development without prior authorization. The

Landscape installation within the CRZ of preserved trees, including irrigation, soil and plantings, shall not exceed

fenced Critical Root Zone shall not be used for tool or material storage of any kind and shall be kept free of er. Refer to ECM 3.6.1.B.3. Pruning shall be in compliance with the current ANSI A300 standard for tree care MINIMUM OF SIX (6) INCHES OF TOPSOIL [SEE STANDARD SPECIFICATION AFTER CONSTRUCTION Tree protection shall be removed at the end of the project after all construction and final grading is complete,

> ocumentation of tree work performed must be provided to inspector per ECM Appendix P-6. THIS LIST IS NOT EXHAUSTIVE.

REFER TO APPROPRIATE ECM SECTIONS FOR FULL REQUIREMENTS.

t before final inspection. Refer to ECM 3.6.1.A.

reservation criteria listed in ECM 3.5.2.

Source: Rules No. R161-21.22, 9-15-2021

Refer to ECM 3.6.1.A.

- B. HYDROMULCH SHALL COMPLY WITH TABLE 2, BELOW. C. WATER THE SEEDED AREAS IMMEDIATELY AFTER INSTALLATION TO ACHIEVE GERMINATION AND A HEALTHY STAND OF PLANTS THAT CAN ULTIMATELY SURVIVE WITHOUT SUPPLEMENTAL WATER. APPLY THE WATER UNIFORMLY TO THE PLANTED AREAS WITHOUT CAUSING DISPLACEMENT OR EROSION OF THE MATERIALS OR SOIL. MAINTAIN THE SEEDBED IN A MOIST CONDITION FAVORABLE FOR PLANT GROWTH. ALL WATERING SHALL COMPLY WITH CITY CODE CHAPTER 6-4 (WATER CONSERVATION), AT RATES AND FREQUENCIES DETERMINED BY A LICENSED IRRIGATOR OR OTHER QUALIFIED PROFESSIONAL, AND AS ALLOWED BY THE AUSTIN WATER UTILITY AND CURRENT WATER RESTRICTIONS AND WATER CONSERVATION
- D. PERMANENT EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 11/2 INCHES HIGH WITH A MINIMUM OF 95 PERCENT FOR THE NON-NATIVE MIX, AND 95 PERCENT COVERAGE FOR THE NATIVE MIX SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR STABILITY MUST BE UNIFORMLY VEGETATED, AND PROVIDED THERE ARE

| ANUAL, ITE | MS 604S AND | 609S. | | | | | | | | |
|---------------------------------------------------------------|-------------------------------------------------------------------------------|-------------------------------------------------------|----------------------------------------------------------------------|----------------------------------------------------------------------|--|--|--|--|--|--|
| TABLE 2: HYDROMULCHING FOR PERMANENT VEGETATIVE STABILIZATION | | | | | | | | | | |
| MATERIAL | DESCRIPTION | LONGEVITY | TYPICAL APPLICATIONS | APPLICATION RATES | | | | | | |
| NDED FIBER ATRIX (BFM) | 80% ORGANIC DEFIBRATED FIBERS | | | | | | | | | |
| % TACKIFIER | 6 MONTHS | ON SLOPES UP TO 2:1 AND EROSIVE SOIL CONDITIONS | 2,500 TO 4,000 LBS PER ACRE (SEE MANUFACTURES RECOMMENDATIONS) | | | | | | | |
| BER EINFORCED ATRIX (FRM) | 65% ORGANIC DEFIBRATED FIBERS 25% FIBERS OR LESS 10% TACKIFIER | UP TO 12 MONTHS | ON SLOPES UP TO 1:1 AND EROSIVE SOIL CONDITIONS | 3,000 TO 4,500 LBS PER ACRE (SEE MANUFACTURES RECOMMENDATIONS) | | | | | | |

- CONSTRUCTION SEQUENCE AND INSPECTION SCHEDULE WILL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR. 8. PERMANENT WATER QUALITY PONDS OR CONTROLS WILL BE CLEANED OUT
- AND FILTER MEDIA WILL BE INSTALLED PRIOR TO/CONCURRENTLY WITH REVEGETATION OF SITE. 9. COMPLETE CONSTRUCTION AND START REVEGETATION OF THE SITE AND INSTALLATION OF LANDSCAPING. 10. UPON COMPLETION OF THE SITE CONSTRUCTION AND REVEGETATION OF A
 - AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY INSPECTOR. 11. UPON COMPLETION OF LANDSCAPE INSTALLATION OF A PROJECT SITE, THE LANDSCAPE ARCHITECT SHALL SUBMIT A LETTER OF CONCURRENCE TO THI DEVELOPMENT SERVICES DEPARTMENT INDICATING THAT THE REQUIRE

APPENDIX P-4: - STANDARD SEQUENCE OF CONSTRUCTION

DETAILS APPROPRIATE FOR THE PARTICULAR DEVELOPMENT.

THE REQUIRED ON-SITE PRECONSTRUCTION MEETING.

PLAN REQUIREMENTS AND THE EROSION PLAN.

PRIOR TO ANY CLEARING.*

(SWPPP) POSTED ON THE SITE.

THE FOLLOWING SEQUENCE OF CONSTRUCTION SHALL BE USED FOR ALL

DEVELOPMENT. THE APPLICANT IS ENCOURAGED TO PROVIDE ANY ADDITIONAL

1. TEMPORARY EROSION AND SEDIMENTATION CONTROLS ARE TO BE

INSTALLED AS INDICATED ON THE APPROVED SITE PLAN OR SUBDIVISION

CONSTRUCTION PLAN AND IN ACCORDANCE WITH THE EROSION

PREVENTION PLAN (SWPPP) THAT IS REQUIRED TO BE POSTED ON THE SITE

CONDUCT "PRE - CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE).

3. THE ENVIRONMENTAL PROJECT MANAGER, AND/OR SITE SUPERVISOR

AND/OR DESIGNATED RESPONSIBLE PARTY. AND THE GENERAL

CONTRACTOR WILL FOLLOW THE EROSION SEDIMENTATION CONTROL PLAN

(ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED

ON THE SITE. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL

BE REVISED IF NEEDED TO COMPLY WITH CITY INSPECTORS' DIRECTIVES

4. ROUGH GRADE THE POND(S) AT 100% PROPOSED CAPACITY. EITHER THE

AND REVISED CONSTRUCTION SCHEDULE RELATIVE TO THE WATER QUALITY

PERMANENT OUTLET STRUCTURE OR A TEMPORARY OUTLET MUST BE

CONSTRUCTED PRIOR TO DEVELOPMENT OF EMBANKMENT OR EXCAVATION

THAT LEADS TO PONDING CONDITIONS. THE OUTLET SYSTEM MUST CONSIST

OF A SUMP PIT OUTLET AND AN EMERGENCY SPILLWAY MEETING THE

REQUIREMENTS OF THE DRAINAGE CRITERIA MANUAL AND/OR THI

ENVIRONMENTAL CRITERIA MANUAL, AS REQUIRED. THE OUTLET SYSTEM

HALL BE PROTECTED FROM EROSION AND SHALL BE MAINTAINEI

THROUGHOUT THE COURSE OF CONSTRUCTION UNTIL INSTALLATION OF

THE PERMANENT WATER QUALITY POND(S). *NOTE: DUE TO THE AMOUNT OF

5. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE INSPECTED

7. IN THE BARTON SPRINGS ZONE, THE ENVIRONMENTAL PROJECT MANAGER

6. BEGIN SITE CLEARING/CONSTRUCTION (OR DEMOLITION) ACTIVITIES.

TREES ON THIS SITE, IT WILL NOT BE FEASIBLE TO ROUGH GRADE IN PONDS

AND MAINTAINED IN ACCORDANCE WITH THE EROSION SEDIMENTATION

CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN

OR SITE SUPERVISOR WILL SCHEDULE A MID-CONSTRUCTION CONFERENCE

TO COORDINATE CHANGES IN THE CONSTRUCTION SCHEDULE AND

EVALUATE EFFECTIVENESS OF THE EROSION CONTROL PLAN AFTER

POSSIBLE CONSTRUCTION ALTERATIONS TO THE SITE. PARTICIPANTS SHALL

INCLUDE THE CITY INSPECTOR, PROJECT ENGINEER, GENERAL

CONTRACTOR AND ENVIRONMENTAL PROJECT MANAGER OR SITE

SUPERVISOR. THE ANTICIPATED COMPLETION DATE AND FINAL

PROJECT SITE. THE DESIGN ENGINEER SHALL SUBMIT AN ENGINEER'S

INDICATING THAT CONSTRUCTION INCLUDING REVEGETATION IS COMPLETE

LETTER OF CONCURRENCE TO THE DEVELOPMENT SERVICES DEPARTMENT

2. THE ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR MUST

SEDIMENTATION CONTROL PLAN (ESC) AND STORMWATER POLLUTION

INSTALL TREE PROTECTION. INITIATE TREE MITIGATION MEASURES AND

CONTACT THE DEVELOPMENT SERVICES DEPARTMENT, ENVIRONMENTAL

INSPECTION, AT 512-974-2278, 72 HOURS PRIOR TO THE SCHEDULED DATE OF

LANDSCAPING IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY INSPECTOR 12. AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY INSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR. REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND COMPLETI

WATER QUALITY PONDS OR CONTROLS.

HAVING JURISDICTION AND ALL OTHER APPLICABLE LAWS.

ANY NECESSARY FINAL REVEGETATION RESULTING FROM REMOVAL OF THE

CONTROLS. CONDUCT ANY MAINTENANCE AND REHABILITATION OF TH

NOTE: THE SEQUENCE OF CONSTRUCTION SHOWN ABOVE IS A GENERAL OVERVIEW AND IS INTENDED TO CONVEY THE GENERAL CONCEPTS OF THE EROSION CONTROL DESIGN AND SHOULD NOT BE RELIED UPON FOR CONSTRUCTION PURPOSES. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETAILED PHASING AND CONSTRUCTION SEQUENCING NECESSARY TO CONSTRUCT THE PROPOSED IMPROVEMENTS INCLUDED IN THESE PLANS. THE CONTRACTOR SHALL NOTIFY ENGINEER IN WRITING IMMEDIATELY, PRIOR TO AND/OR DURING CONSTRUCTION IF ANY ADDITIONAL INFORMATION ON THE CONSTRUCTION SEQUENCE IS NECESSARY. CONTRACTOR IS SOLELY RESPONSIBLE FOR COMPLYING WITH THE REQUIREMENTS OF THE AUTHORITY

APPENDIX P-6 - REMEDIAL TREE CARE NOTES AERATION AND SUPPLEMENTAL NUTRIE REQUIREMENTS FOR TREES WITHIN CONSTRUCTION AREAS AS A COMPONENT OF AN EFFECTIVE REMEDIAL TREE CARE PROGRAM PER ENVIRONMENTAL CRITERIA MANUAL SECTION 3.5.4, PRESERVED TREES WITHIN THE LIMITS OF CONSTRUCTION MAY REQUIRE SOIL AERATION AND SUPPLEMENTAL NUTRIENTS. SOIL AND/OR FOLIAR ANALYSIS SHOULD BE USED TO DETERMINE THE NEED FOR SUPPLEMENTAL NUTRIENTS. THE CITY ARBORIST MAY REQUIRE THESE ANALYSES AS PART OF A COMPREHENSIVE TREE CARE PLAN. SOIL PH SHALL BE CONSIDERED WHEN DETERMINING THE FERTILIZATION COMPOSITION AS SOIL PH INFLUENCES THE TREE'S ABILITY TO UPTAKE NUTRIENTS FROM THE SOIL. IF ANALYSES INDICATE THE NEED FOR SUPPLEMENTAL NUTRIENTS, THEN HUMATE/NUTRIENT SOLUTIONS WITH MYCORRHIZAE COMPONENTS ARE HIGHLY RECOMMENDED. IN ADDITION, SOIL ANALYSIS MAY BE NEEDED TO DETERMINE IF ORGANIC MATERIAL OR BENEFICIAL MICROORGANISMS ARE NEEDED TO IMPROVE SOIL HEALTH MATERIALS AND METHODS ARE TO BE APPROVED BY THE CITY ARBORIST

WITH THE CITY ARBORIST. PRE-CONSTRUCTION TREATMENT SHOULD BE APPLIED IN THE APPROPRIATE SEASON, IDEALLY THE SEASON PRECEDING THE PROPOSED CONSTRUCTION. MINIMALLY, AREAS TO BE TREATED INCLUDE THE ENTIRE CRITICAL ROOT ZONE OF TREES AS DEPICTED ON THE CITY APPROVED PLANS. TREATMENT SHOULD INCLUDE, BUT NOT LIMITED TO, FERTILIZATION, SOIL TREATMENT, MULCHING, AND PROPER PRUNING.

(512-974-1876) PRIOR TO APPLICATION. THE OWNER OR GENERAL CONTRACTOR

SHALL SELECT A FERTILIZATION CONTRACTOR AND IENSURE COORDINATION

POST-CONSTRUCTION TREATMENT SHOULD OCCUR DURING FINAL REVEGETATION OR AS DETERMINED BY A QUALIFIED ARBORIST AFTER CONSTRUCTION. CONSTRUCTION ACTIVITIES OFTEN RESULT IN A REDUCTION IN SOIL MACRO AND MICRO PORES AND AN INCREASE IN SOIL BULK DENSITY. TO AMELIORATE THE DEGRADED SOIL CONDITIONS, AERATION VIA WATER AND/OR AIR INJECTED INTO THE SOIL IS NEEDED OR BY OTHER METHODS AS APPROVED BY THE CITY ARBORIST. THE PROPOSED NUTRIENT MIX SPECIFICATIONS AND SOIL AND/OR FOLIAR ANALYSIS RESULTS NEED TO BE PROVIDED TO AND APPROVED BY THE CITY ARBORIST PRIOR TO APPLICATION (FAX # 512-974-3010). CONSTRUCTION WHICH WILL BE COMPLETED IN LESS THAN 90 DAYS MAY USE MATERIALS AT 1/2 RECOMMENDED RATES. ALTERNATIVE ORGANIC FERTILIZER MATERIALS ARE ACCEPTABLE WHEN APPROVED BY THE CITY ARBORIST. WITHIN 7 DAYS AFTER FERTILIZATION IS PERFORMED, THE CONTRACTOR SHALL PROVIDE DOCUMENTATION OF THE WORK PERFORMED TO THE CITY ARBORIST, PLANNING AND DEVELOPMENT REVIEW . P.O. BOX 1088, AUSTIN, TX 78767. THIS NOTE SHOULD BE REFERENCED AS ITEM #1 IN THE SEQUENCE OF

SITE PLAN APPROVAL SHEET 3 OF 48 FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024 APPROVED BY COMMISSION ON UNDER SECTION 112 OF CHAPTER **25-5** OF THE CITY OF AUSTIN CODE. EXPIRATION DATE (25-5-81,LDC) _____CASE MANAGER CLARISSA E. DAVIS PROJECT EXPIRATION DATE (ORD.#970905-A) DWPZ DDZ Director, Development Services Department RELEASED FOR GENERAL COMPLIANCE: ZONING MF-2, MF-2 CO Correction 1 Correction 2 WARNING: CONTRACTOR IS TO VERIFY PRESENCE AND EXACT -LOCATION OF ALL UTILITIES Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans PRIOR TO CONSTRUCTION. which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.

JOSE M. FARIAS 111389 2/24/2024

0 2

Please call Development Services Department Site and Subdivision Inspection at 512.974.6360 for arrangements for payment of Inspection fees and job assignment for Inspection of the public

ALL RESPONSIBILITY FOR THE ADEQUECY OF THESE PLANS REMAINS WITH THE ENGINEER. APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN DOES NOT REMOVE THESE RESPONSIBILITIES. REVIEWED BY AUSTIN WATER APPLIES ONLY TO FACILITIES WITHIN PUBLIC STREETS OR PUBLIC UTILITY EASEMENTS. ALL OTHER WATER AND WASTEWATER FACILITIES INSIDE PRIVATE PROPERTY ARE UNDER THE JURISDICATION OF BUILDING

Use of Electronic Files General Disclaimer: Use of the attached files in any manner indicates your acceptance of terms and conditions as set forth below. If you do not agree to all of the terms and conditions, please contact Austin Water pipeline engineering, project coordinator prior to use of the referenced information. Please be advised that the attached files are in a format that can be altered by the user. Due to this fact, any reuse of the data will be at the user's sole risk without liability or legal exposure to The City of Austin and user shall indemnify and hold harmless The City of Austin from all claims, damages losses and expenses including attorney's fees arising out of or resulting from using the digital file. In addition, it is the responsibility of the user to compare all data with the PDF version of this drawing. In the event there is a conflict between the PDF version drawing and the electronic file, the PDF version drawing shall prevail.

utilities to this site. Inspection fees must be paid before any Pre-construction meeting can be held.

FIRE DEPARTMENT DATA

and included in the hydraulic calculations.




GENERAL NOTES

AUSTIN FIRE DEPARTMENT FIRE PREVENTION DIVISION 505 Barton Springs Rd, Ste 200, Austin, Texas 78704




| | | | Hydrant Flo | w Test R | eport | |
|------------|---------|---------------|--------------------|--------------------------------------|--------------------|----------------|
| TEST DATE | 06/27/ | /2020 | FIRE BOX | 3810 | COMPANY | PREVENTION |
| TIME | 1030 | HRS | MAP GRID ID | Н38 | AFD STAFF | CHAFINO, XOCHI |
| | | | RESIDUA | L HYDRAN | Г | |
| | RESIDU | JAL HYDRANT # | 233665 | | MAIN SIZE (in.) | 8 |
| BL | K # | DIRECTION | Γ | STREET NAME | 3 | TYPE |
| 132 | | | | MORRIS | - | RD |
| ST | ATIC PF | RESSURE (PSI) | 100 | RESID | UAL PRESSURE (PSI) | 83 |
| | | | FLOW | HYDRANT | | |
| | | | FLOW | HYDRANT | | |
| | FLO | OW HYDRANT # | 55570 | HYDRANT | MAIN SIZE (in.) | 8 |
| BL | | OW HYDRANT # | | HYDRANT STREET NAME | | 8 TYPE |
| BLI 132 | K # | | | | | |
| 132 | K# | DIRECTION | | STREET NAME MORRIS | | TYPE RD |
| 132 S | K# | DIRECTION | 55570 | STREET NAME MORRIS | 3 | TYPE RD |
| 132 | K# | DIRECTION | 55570 | STREET NAME MORRIS RESII dc = 6 st | 3 | TYPE RD |

HFTR #14250440





SERVICE EXTENSION REQUESTS WATER SER NO. 5746



STAFF PROPOSED APPROXIMATELY 620 FEET OF 8-INCH WATER MAIN Subject Tract 600 100-Year COA Floodplain Critical Water Quality Zone W. S.E.R. Name: Marielle Condos W. S.E.R. Number: 5746 This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relationstance for the property boundaries. This product has been produced by the City of Austin represents only the City of Austin represents only the approximate relationstance for the property boundaries. This product has been produced by the City of Austin represents only the City of Austin represents only the approximate relationstance for the property boundaries. This product has been produced by the City of Austin represents only the approximate relationstance for the property boundaries. This product has been produced by the City of Austin represents only the approximate relationstance for the property boundaries.

WASTEWATER SERVICE NO.4121





PROJECT INFORMATION

| GRID NUMBER: | H38 |
|---------------------------------------------------|--------------|
| MAPSCO NUMBER: | 434L |
| AW INTERSECTION NUMBER: | 11132 |
| BUILDING SIZE IN SQUARE FEET: | 5,406 |
| BUILDING TYPE PER IFC: | V-B |
| BUILDING HEIGHT: | 37'-0" |
| AVAILABLE FIRE FLOW CALCS AT 20 PSI: | 3420 |
| REQUIRED BUILDING FIRE FLOW PER IFC: | 1500 |
| REDUCED FIRE FLOW PER % FIRE SPRINKLER REDUCTION: | 750 |
| *MINIMUM FIRE FLOW: | 1500 |
| DOMESTIC WATER DEMAND: | 520 |
| WATER SUPPLY FIXTURE UNITS (WSFU): | 3,622 |
| DOMESTIC DEMAND CALCULATED PER THE WSFU: | 520 |
| AUSTIN WATER PRESSURE ZONE: | Northwest B |
| STATIC WATER PRESSURE: | 101.73 |
| HIGHEST LOT SERVED: | 880 |
| LOWEST LOT SERVED: | 874 |
| IRRIGATION DEMAND: | 130 |
| 8" FIRE LINE VELOCITY: | 9.57 ft/sec |
| 6" DOMESTIC LINE VELOCITY: | 13.27 ft/sec |

DOMESTIC WATER METER. ON MINIMUM FIRE FLOW, DESIGN ENGINEER MUST INCLUDE 1500 GALLONS PER MINUTE OR REDUCED FIRE FLOW

AMOUNT, WHICHEVER IS GREATER) STANDARD CONSTRUCTION NOTES

THE CITY STANDARD CONSTRUCTION SPECIFICATIONS CURRENT AT THE TIME OF BIDDING SHALL COVER MATERIALS AND METHODS USED TO DO THIS WORK. CONTRACTOR MUST OBTAIN A STREET CUT PERMIT FROM AUSTIN TRANSPORTATION DEPARTMENT, RIGHT OF WAY MANAGEMENT DIVISION BEFORE BEGINNING ONSTRUCTION WITHIN THE RIGHT-OF-WAY OF A PUBLIC STREET OR ALLEY.

AT LEAST 48 HOURS BEFORE BEGINNING ANY WATER AND WASTEWATER CONSTRUCTION IN PUBLIC R.O.W. OR PUBLIC EASEMENT, THE CONTRACTOR SHALL NOTIFY AUSTIN TRANSPORTATION INSPECTION OR DEVELOPMENT SERVICES DEPARTMENT (DSD) INSPECTIONS AT THE NUMBER INDICATED ON THE PLANS BY THE AW PLAN

Meter Notice:

Type: Compound

Service Units: 30

Size: 4"

Size: 2"

Address:

Proposed Use:

Service Units: 8.0

Meter(s) Requirement for Project:

Proposed Use: Potable Domestic

Meter(s) Requirement for Project:

Proposed Use: Irrigation (Potable Source)

Reclaimed Meter(s) Requirement for Project:

GPM: 160

Address: 13208 Morris Road

Type: Positive Displacement

GPM: 520

Address: 13208 Morris Road

THE CONTRACTOR SHALL CONTACT THE AUSTIN AREA "ONE CALL" SYSTEM AT 1-800-344-8377 FOR EXISTING UTILITY LOCATIONS PRIOR TO ANY EXCAVATION IN ADVANCE OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES TO BE EXTENDED, TIED TO, OR ALTERED, OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS. THE CITY OF AUSTIN WATER AND WASTEWATER MAINTENANCE RESPONSIBILITY ENDS AT

NO OTHER UTILITY SERVICE/APPURTENANCES SHALL BE PLACED NEAR THE PROPERTY LINE, OR OTHER ASSIGNED LOCATION DESIGNATED FOR WATER AND VASTEWATER UTILITY SERVICE THAT WOULD INTERFERE WITH THE WATER AND WASTEWATER SERVICES.

THE CITY SPECIFICATION ITEM 509S WILL BE REQUIRED AS A MINIMUM TRENCH SAFETY MEASURE.

ALL MATERIALS TESTS ORDERED BY THE OWNER FOR QUALITY ASSURANCE PURPOSES, SHALL BE CONDUCTED BY AN INDEPENDENT LABORATORY AND FUNDED BY THE NER IN ACCORDANCE WITH CITY STANDARD SPECIFICATION ITEM 1804S.04.

PRESSURE TAPS SHALL BE ALLOWED ON A CASE BY CASE BASIS, AS DETERMINED BY THE DIRECTOR'S DESIGNEE. NORMALLY PRESSURE TAPS WILL BE ALLOWED ONLY IN THE FOLLOWING CASES: A) A TEST SHUT OUT INDICATES AN ADEQUATE SHUT OUT TO PERFORM THE WORK IS NOT FEASIBLE B) MORE THAN 30 CUSTOMERS OR A SINGLE CRITICAL CUSTOMER (AS DEFINED BY AUSTIN WATER) WOULD BE IMPACTED BY THE SHUT OUT OR C) THE EXISTING WATER LINE WARRANTS IT.

HYDRANTS AND ASSOCIATED VALVES. TEN (10) YEARS AND OLDER WILL BE REQUIRED TO BE REPLACED WITH A NEW FIRE HYDRANT AND APPERTENUNANCES.

WATER LINE TESTING AND STERILIZATION SHALL BE PERFORMED IN ACCORDANCE WITH CITY STANDARD SPECIFICATION ITEMS 510.3 (27)-(29). FORCE MAIN PRESSURE TESTING SHALL BE CONDUCTED AND FALL UNDER THE SPECIFICATIONS AS WATER LINES (PRESSURE PIPE) OR AT THE PRESSURES SHOWN ON THE APPROVED

12. ALL MATERIAL USED ON THIS PROJECT MUST BE LISTED ON THE STANDARD PRODUCTS LISTING. ANY MATERIAL NOT LISTED HAS TO GO THROUGH THE REVIEW OF THE STANDARDS COMMITTEE FOR REVIEW AND APPROVAL PRIOR TO START OF PROJECT. TESTING AND EVALUATION OF PRODUCTS ARE REQUIRED BEFORE APPROVAL

13. WHEN WATER SERVICES ARE DAMAGED AND THE SERVICE MATERIAL IS PE, THE LINE SHALL BE REPAIRED ONLY BY HEAT FUSION WELD OR REPLACED THE FULL LENGTH WITH TYPE K COPPER MATERIAL. ANY TIME PB IS DAMAGED OR TAMPERED WITH IN ANY WAY. THE SERVICE LINE SHALL BE REPLACED FULL LENGTH WITH TYPE K COPPER MATERIAL. NOTE: FULL LENGTH IS FROM CORPORATION STOP TO METER.

WHEN AN EXISTING WATERLINE SHUT OUT IS NECESSARY AND POSSIBLE, THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTOR WHO WILL THEN NOTIFY

THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION INSPECTOR SO THAT HE CAN NOTIFY THE AUSTIN WATER AT 972-0000 AT A MINIMUM OF 72 HOURS PRIOR TO RELOCATING ANY DOMESTIC OR FIRE DEMAND WATER METERS. THE CONTRACTOR SHALL CAREFULLY REMOVE ALL METERS AND METERS BOXES THAT ARE INDICATED TO BE RELOCATED OR SALVAGED. THE CONTRACTOR SHALL INSTALL THE REMOVED METER OR CITY PROVIDED METER AT THE NEW LOCATION INDICATED ON THE

16. WATER AND WASTE WATER SERVICES WILL NEED TO BE REPLACED UP TO THE MAIN. REPAIR COUPLINGS ARE NOT ALLOWED ON NEW INSTALLTIONS.

17. ALL MANHOLES IN UNPAVED AREAS PROVIDING DIRECT ACCESS TO A WASTEWATER LINE SHALL BE WATERTIGHT AND BEAR THE WORDING AND INSIGNIA FOR THE

18. THE CONTRACTOR SHALL VERIFY ALL VERTICAL AND HORIZONTAL LOCATIONS OF EXISTING UTILITIES, BELOW GROUND AND OVERHEAD, PRIOR TO STARTING ONSITE

19. ALL WATER AND WASTEWATER MAINS SHALL BE INSTALLED IN ACCORDANCE WITH THE SEPARATION DISTANCES INDICATED IN CHAPTER 290 - DRINKING WATER STANDARDS, CHAPTER 217 - DESIGN CRITERIA FOR SEWERAGE SYSTEMS AMD CHAPTER 210 - DESIGN CRIERIA FOR RECLAIMED SYSTEMS OF TCEO RULES. 20. CONTRACTOR'S PERSONNEL THAT PERFORM BUTT FUSION AND ELECTROFUSION ON OR TO HDPE PIPE AND FITTINGS MUST HAVE CURRENT QUALIFICATION TRAINING

CERTIFICATE ISSUED BY MCELROY OR COMPARABLE TRAINING PROGRAM. 21. SHOP DRAWINGS SIGNED AND SEALED BY A PROFESSIONAL STRUCTURAL ENGINEER, REGISTERED IN THE STATE OF TEXAS, SHALL BE SUBMITTED FOR AUSTIN WATER APPROVAL FOR LARGE DIAMETER PRE-CAST MANHOLES, JUNCTION BOXES, WET WELLS, AND SIMILAR STRUCTURES. THE SHOP DRAWINGS SHALL INCLUDE FLOWLINE ELEVATIONS OF ALL INCOMING AND OUTGOING PIPES, ELEVATION OF TRANSITION FROM LARGE DIAMETER SECTIONS TO 48" ID SECTION, TOP OF MANHOLE ELEVATION.

22. VALVE STEM EXTENSIONS SHALL CONSIST OF A SINGLE PIECE OF IRON ROD OF THE REQUIRED LENGTH WITH A SOCKET ON ONE END AND NUT ON THE OTHER.

SURROUNDING GROUND ELEVATION. AS WELL AS SPECIAL CONSTRUCTION CONSIDERATIONS THAT ARE SPECIFIED IN THE CONTRACT DRAWINGS.

23. ALL POTABLE WATER SYSTEM COMPONENTS INSTALLED AFTER JANUARY 4, 2014, SHALL BE ESSENTIALLY "LEAD FREE" ACCORDING TO THE US SAFE DRINKING WATER ACT. EXAMPLES ARE VALVES (CORPORATION STOP, CURB STOP, AND PRESSURE REDUCING), NIPPLES, BUSHINGS, PIPE, FITTINGS, BACKFLOW PREVENTERS AND FIRE HYDRANTS. TAPPING SADDLES AND 2 INCH AND LARGER GATE VALVES ARE THE ONLY COMPONENTS EXEMPT FROM THIS REQUIREMENT. COMPONENTS THAT ARE NOT CLEARLY IDENTIFIED BY THE MANUFACTURER AS MEETING THIS REQUIREMENT EITHER BY MARKINGS ON THE COMPONENT OR ON THE PACKAGING SHALL NOT BE

24. ALL FIRE HYDRANTS AND VALVES THAT ARE TO BE ABANDONED SHALL BE REMOVED, SALVAGED AND RETURNED TO AUSTIN WATER. NOTICE SHOULD BE GIVEN 48 HOURS PRIOR TO RETURN TO: PIPELINE OPERATIONS DISTRIBUTION SYSTEM MAINTENANCE, VALVES AND HYDRANT SERVICES, SUPERVISING AW PIPELINE TECHNICIAN AT

25. ALL EXISTING WATER METERS IDENTIFIED TO BE RELOCATED OR ABANDONED AT THE DEVELOPMENT, SHALL BE REMOVED FROM THE METER BOX PRIOR TO CONSTRUCTION AND GIVEN IMMEDIATELY TO THE DSD INSPECTOR.


THE ENGINEER SHALL CALL OUT THE SIZE, TYPE AND USE (DOMESTIC OR IRRIGATION) OF ALL EXISTING WATER METERS TO BE RELOCATED OR REPURPOSED. WATER METER NUMBERS WILL NOT BE REQUIRED TO BE PLACED ON THE PLAN SHEET. A SEPARATE AUSTIN WATER TAPS OFFICE FORM WILL BE USED TO PROVIDE RELEVANT INFORMATION FOR THE EXISTING INFORMATION ON EXISTING METERS TO RECEIVE APPROPRIATE CREDITS. THIS FORM SHALL BE DIRECTLY SUBMITTED TO AUSTIN WATER


27. NO CONNECTION MAY BE MADE BETWEEN THE PRIVATE PLUMBING AND AUSTIN WATER INFRASTRUCTURE UNTIL A CITY APPROVED WATER METER HAS BEEN

28. ALL GRAVITY LINES SHALL BE INSTALLED DOWNSTREAM TO UPSTREAM.

29. METER BOXES AND CLEAN OUTS SHALL NOT BE LOCATED WITHIN PAVED AREAS SUCH AS DRIVEWAYS AND SIDEWALKS.


0. PROTECTED STREET STATUS IS SUBJECT TO CHANGE OVER TIME. IT IS THE OWNER'S RESPONSIBILITY TO CONFIRM THE STREET STATUS PRIOR TO CONSTRUCTION AS PROTECTED STREET STATUS WILL DIRECTLY IMPACT THE CONSTRUCTION COSTS. IF PROTECTED STREETS ARE PROPOSED TO BE DISTURBED, APPROVAL FROM THE STREET AND BRIDGE DIVISION OF THE TRANSPORTATION DEPARTMENT IS REQUIRED.








Meter 1.5 inches and larger must be purchased and ordered 90 days in advance of installation.



Ш 0 Ш Z Ш Ŋ

SHEET NUMBER



SITE PLAN APPROVAL SHEET 5_ OF 48

FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024

APPROVED BY COMMISSION ON UNDER SECTION 112_ OF

CHAPTER 25-5_ OF THE CITY OF AUSTIN CODE.

EXPIRATION DATE (25-5-81,LDC) CASE MANAGER CLARISSA E. DAVIS

PROJECT EXPIRATION DATE (ORD.#970905-A) DWPZ DDZ

Director, Development Services Department

RELEASED FOR GENERAL COMPLIANCE: ZONING MF-2, MF-2 CO

Rev. 1 Correction 1

Rev. 2 Correction 2

Rev. 3 Correction 3

Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.


AMAVI NORTHWEST AUSTIN 13220 MORRIS ROAD


JOSE M. FARIAS

FINAL

SHEET NUMBER

5 OF 48





| | 7 | TREE TABLE | | | | | TREE TABLE | | | | 7 | REE TABLE | | | | | TREE TABLE | | | | | TREE TABLE | | |
|---------|----------------|-------------|-------------|----------|---------|----------------|-------------|------------|--------|---------|----------------|-------------|--------------|--------|---------|--------------------------------|-------------|------------|--------|---------|----------------|-------------|------------|--------|
| TAG NO. | DESCRIPTION | MULTI-TRUNK | STEM SIZE | S REMOVE | TAG NO. | DESCRIPTION | MULTI-TRUNK | STEM SIZES | REMOVE | TAG NO. | DESCRIPTION | MULTI-TRUNK | STEM SIZES | REMOVE | TAG NO. | DESCRIPTION | MULTI-TRUNK | STEM SIZES | REMOVE | TAG NO. | DESCRIPTION | MULTI-TRUNK | STEM SIZES | REMOVE |
| 30001 | 16.5" LIVE OAK | MULTI-TRUNK | 12, 9 | R | 30074 | 14" LIVE OAK | NON-MT | | | 30142 | 13" LIVE OAK | NON-MT | | R | 61337 | 15" LIVE OAK | NON-MT | | R | 61402 | 16" LIVE OAK | MULTI-TRUNK | 11, 10 | R |
| 30002 | 14.5" LIVE OAK | MULTI-TRUNK | 11, 7 | R | 30075 | 17" LIVE OAK | MULTI-TRUNK | 13, 8 | | 30143 | 10" LIVE OAK | NON-MT | | R | 61338 | 10" HACKBERRY | NON-MT | | R | 61403 | 10" LIVE OAK | NON-MT | | R |
| 30003 | 11" LIVE OAK | NON-MT | | R | 30076 | 9" LIVE OAK | NON-MT | | | 30144 | 10" LIVE OAK | NON-MT | | R | 61339 | 8" LIVE OAK | NON-MT | | R | 61404 | 9" LIVE OAK | NON-MT | | R |
| 30004 | 10" LIVE OAK | NON-MT | | R | 30077 | 9" LIVE OAK | NON-MT | | | 30145 | 14.5" LIVE OAK | MULTI-TRUNK | 12, 5 | R | 61340 | 14" LIVE OAK | NON-MT | | R | 61405 | 9" LIVE OAK | NON-MT | | R |
| 30005 | 10" LIVE OAK | NON-MT | | R | 30078 | 13" LIVE OAK | NON-MT | | | 30146 | 21" LIVE OAK | MULTI-TRUNK | 12.5, 11, 6 | R | 61341 | 13" LIVE OAK | NON-MT | | R | 61406 | 8" LIVE OAK | NON-MT | | R |
| 30006 | 24.5" LIVE OAK | MULTI-TRUNK | 11, 12, 13 | R | 30079 | 9" LIVE OAK | NON-MT | | | 30147 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R | 61342 | 11" LIVE OAK | MULTI-TRUNK | 8, 6 | R | 61407 | 13.5" LIVE OAK | MULTI-TRUNK | 9, 9 | R |
| 30007 | 8" LIVE OAK | NON-MT | | R | 30080 | 9" LIVE OAK | MULTI-TRUNK | 6, 6 | | 30148 | 9" HACKBERRY | NON-MT | | R | 61343 | 14" LIVE OAK | NON-MT | | R | 61408 | 9" LIVE OAK | NON-MT | | R |
| 30008 | 10" LIVE OAK | NON-MT | | R | 30081 | 9" LIVE OAK | MULTI-TRUNK | 6, 6 | R | 30149 | 12" CHINABERRY | MULTI-TRUNK | 7, 5, 5 | R | 61344 | 10" LIVE OAK | NON-MT | | R | 61409 | 17" LIVE OAK | MULTI-TRUNK | 12, 10 | R |
| 30009 | 8" LIVE OAK | NON-MT | | R | 30082 | 8" LIVE OAK | NON-MT | | R | 30150 | 13" LIVE OAK | NON-MT | | R | 61345 | 13" LIVE OAK | NON-MT | | R | 61410 | 11" LIVE OAK | NON-MT | | R |
| 30010 | 12" LIVE OAK | NON-MT | | R | 30083 | 8" LIVE OAK | NON-MT | | R | 30151 | 20" LIVE OAK | MULTI-TRUNK | 14, 11.5 | R | 61346 | 10" LIVE OAK | NON-MT | | R | 61411 | 11" LIVE OAK | NON-MT | | R |
| 30011 | 12" LIVE OAK | MULTI-TRUNK | 8, 8 | R | 30084 | 8" LIVE OAK | NON-MT | | R | 30152 | 13" LIVE OAK | NON-MT | | R | 61347 | 14.5" ASH | MULTI-TRUNK | 10, 9 | R | 61412 | 11" LIVE OAK | NON-MT | | R |
| 30014 | 12" LIVE OAK | NON-MT | | R | 30085 | 9" LIVE OAK | NON-MT | | R | 30153 | 11" LIVE OAK | NON-MT | | R | 61348 | 13" LIVE OAK | NON-MT | | R | 61413 | 8" LIVE OAK | NON-MT | | R |
| 30015 | 9" LIVE OAK | NON-MT | | R | 30086 | 11" LIVE OAK | NON-MT | | R | 30154 | 12" LIVE OAK | NON-MT | | R | 61349 | 14" LIVE OAK | NON-MT | | | 61415 | 8" LIVE OAK | NON-MT | | R |
| 30016 | 10" LIVE OAK | NON-MT | | R | 30087 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R | 30155 | 12" LIVE OAK | NON-MT | | R | 61350 | 9" LIVE OAK | NON-MT | | | 61416 | 9" LIVE OAK | NON-MT | | R |
| 30017 | 12" LIVE OAK | NON-MT | | R | 30088 | 12.5" LIVE OAK | MULTI-TRUNK | 9, 7 | R | 30156 | 13" LIVE OAK | NON-MT | | R | 61351 | 11" LIVE OAK | NON-MT | | R | 61417 | 10.5" LIVE OAK | MULTI-TRUNK | 7, 7 | R |
| 30018 | 11" LIVE OAK | NON-MT | | R | 30089 | 10" LIVE OAK | NON-MT | | R | 30157 | 9" CEDAR ELM | NON-MT | | | 61352 | 13" LIVE OAK | NON-MT | | R | 61418 | 9" LIVE OAK | NON-MT | | R |
| 30019 | 12" LIVE OAK | NON-MT | | R | 30090 | 10" LIVE OAK | MULTI-TRUNK | 8, 4 | R | 30158 | 12" LIVE OAK | NON-MT | | | 61353 | 12" LIVE OAK | NON-MT | | R | 61419 | 17.5" LIVE OAK | MULTI-TRUNK | 13, 9 | R |
| 30020 | 10" LIVE OAK | NON-MT | | R | 30091 | 8" LIVE OAK | NON-MT | | R | 30159 | 12" LIVE OAK | NON-MT | | | 61354 | 15" LIVE OAK | NON-MT | | R | 61420 | 12" LIVE OAK | NON-MT | | R |
| 30021 | 10" LIVE OAK | NON-MT | | R | 30092 | 11" LIVE OAK | MULTI-TRUNK | 8, 6 | R | 30160 | 32" LIVE OAK | MULTI-TRUNK | 23, 18 | | 61355 | 13" LIVE OAK | NON-MT | | R | 61421 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R |
| 30022 | 1" LIVE OAK | NON-MT | | | 30093 | 8" LIVE OAK | NON-MT | | R | 30161 | 16" LIVE OAK | NON-MT | | | 61356 | 13" LIVE OAK | NON-MT | | R | 61423 | 10" LIVE OAK | NON-MT | | R |
| 30023 | 8" LIVE OAK | NON-MT | | R | 30094 | 8" LIVE OAK | NON-MT | | R | 30162 | 14" LIVE OAK | NON-MT | | | 61357 | 16" LIVE OAK | NON-MT | | R | 61424 | 9" LIVE OAK | NON-MT | | R |
| 30025 | 18" LIVE OAK | MULTI-TRUNK | 12, 12 | R | 30095 | 9" LIVE OAK | NON-MT | | R | 30163 | 9" LIVE OAK | NON-MT | | | 61358 | 12" LIVE OAK | NON-MT | | R | 61425 | 10" LIVE OAK | NON-MT | | R |
| 30027 | 10" LIVE OAK | NON-MT | | | 30096 | 8" LIVE OAK | NON-MT | | R | 30164 | 27.5" LIVE OAK | MULTI-TRUNK | 15, 12.5, 12 | | 61359 | 10" LIVE OAK | NON-MT | | R | 61426 | 9" LIVE OAK | NON-MT | | R |
| 30028 | 10" LIVE OAK | NON-MT | | | 30097 | 11.5" LIVE OAK | MULTI-TRUNK | 9, 5 | R | 30165 | 9" LIVE OAK | NON-MT | | | 61360 | 11" LIVE OAK | NON-MT | | R | 61427 | 12" LIVE OAK | NON-MT | | R |
| 30029 | 13" LIVE OAK | NON-MT | | | 30098 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R | 30166 | 14.5" LIVE OAK | MULTI-TRUNK | 10, 9 | R | 61361 | 19" LIVE OAK | NON-MT | | | 61428 | 10" LIVE OAK | NON-MT | | R |
| 30034 | 8" LIVE OAK | NON-MT | | | 30099 | 9" LIVE OAK | NON-MT | | R | 30167 | 13.5" LIVE OAK | MULTI-TRUNK | 9, 9 | R | 61362 | 10" LIVE OAK | NON-MT | | R | 61429 | 11" LIVE OAK | NON-MT | | R |
| 30035 | 9" LIVE OAK | NON-MT | | R | 30100 | 11" LIVE OAK | NON-MT | | R | 30169 | 14.5" LIVE OAK | MULTI-TRUNK | 10, 9 | R | 61363 | 14" LIVE OAK | NON-MT | | | 61430 | 13" LIVE OAK | NON-MT | | |
| 30036 | 10" LIVE OAK | NON-MT | | R | 30101 | 9" LIVE OAK | NON-MT | | R | 30170 | 8.5" LIVE OAK | MULTI-TRUNK | 6, 5 | R | 61364 | 9" LIVE OAK | NON-MT | | R | 61431 | 12" LIVE OAK | NON-MT | | |
| 30037 | 13" LIVE OAK | NON-MT | | R | 30102 | 9" LIVE OAK | NON-MT | | R | 30171 | 8" LIVE OAK | NON-MT | | R | 61365 | 11" LIVE OAK | NON-MT | | R | 61433 | 8" LIVE OAK | NON-MT | | R |
| 30038 | 13.5" LIVE OAK | MULTI-TRUNK | 9, 9 | R | 30103 | 9" LIVE OAK | NON-MT | | R | 30172 | 8" LIVE OAK | NON-MT | | R | 61366 | 9" LIVE OAK | NON-MT | | R | 61435 | 19" LIVE OAK | NON-MT | | |
| 30039 | 10" LIVE OAK | NON-MT | | R | 30104 | 8" LIVE OAK | NON-MT | | R | 30173 | 8" LIVE OAK | NON-MT | | R | 61367 | 14" LIVE OAK | NON-MT | | R | 61436 | 16" LIVE OAK | NON-MT | | |
| 30040 | 8" LIVE OAK | NON-MT | | R | 30105 | 8" LIVE OAK | NON-MT | | R | 30175 | 10" LIVE OAK | NON-MT | | R | 61368 | 8" LIVE OAK | NON-MT | | R | 61437 | 20" LIVE OAK | NON-MT | | |
| 30041 | 10" LIVE OAK | NON-MT | | R | 30106 | 8" LIVE OAK | NON-MT | | R | 30176 | 10.6" LIVE OAK | MULTI-TRUNK | 8, 8 | R | 61369 | 8" LIVE OAK | NON-MT | | R | 61438 | 8" LIVE OAK | NON-MT | | |
| 30042 | 8" LIVE OAK | MULTI-TRUNK | 6, 4 | R | 30107 | 13" LIVE OAK | NON-MT | | R | 30177 | 15.5" LIVE OAK | MULTI-TRUNK | 8, 8, 7 | R | 61370 | 16" LIVE OAK | MULTI-TRUNK | 12, 8 | R | 61439 | 21" LIVE OAK | NON-MT | | |
| 30043 | 8" LIVE OAK | NON-MT | | R | 30108 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R | 30178 | 11" LIVE OAK | NON-MT | | R | 61371 | 12" LIVE OAK | NON-MT | | R | 61440 | 9" CEDAR ELM | MULTI-TRUNK | 6, 6 | R |
| 30044 | 11" LIVE OAK | MULTI-TRUNK | 8, 6 | R | 30109 | 10" LIVE OAK | NON-MT | | R | 30179 | 8" LIVE OAK | NON-MT | | R | 61372 | 16.5" LIVE OAK | | 11, 11 | R | 61441 | 8" LIVE OAK | NON-MT | | R |
| 30045 | 14" LIVE OAK | MULTI-TRUNK | 8, 6, 6 | R | 30110 | 9" LIVE OAK | NON-MT | | R | 30180 | 17" LIVE OAK | MULTI-TRUNK | 12, 10 | R | 61373 | 13" LIVE OAK | MULTI-TRUNK | 9, 8 | R | 61450 | 15.5" LIVE OAK | MULTI-TRUNK | 11, 9 | R |
| 30046 | 8" LIVE OAK | NON-MT | | R | 30111 | 9" LIVE OAK | NON-MT | | R | 30181 | 12" LIVE OAK | NON-MT | | R | 61374 | 13" LIVE OAK | NON-MT | | R | 61452 | 10" LIVE OAK | NON-MT | | R |
| 30047 | 8" LIVE OAK | NON-MT | | R | 30112 | 9" LIVE OAK | NON-MT | | R | 30182 | 8" LIVE OAK | NON-MT | | R | 61375 | 8" LIVE OAK | NON-MT | | R | 61453 | 8" LIVE OAK | NON-MT | | R |
| 30048 | 9" LIVE OAK | MULTI-TRUNK | 6, 6 | R | 30113 | 16" LIVE OAK | MULTI-TRUNK | 11, 10 | R | 30183 | 14.5" LIVE OAK | MULTI-TRUNK | 8, 7, 6 | R | 61376 | 10" LIVE OAK | MULTI-TRUNK | 7, 6 | R | 61454 | 10" LIVE OAK | NON-MT | | R |
| 30049 | 11" LIVE OAK | MULTI-TRUNK | 6, 5, 5 | R | 30114 | 15.5" LIVE OAK | MULTI-TRUNK | 11, 9 | R | 30184 | 9" LIVE OAK | NON-MT | | R | 61377 | 17" LIVE OAK | NON-MT | | R | 61455 | 10" LIVE OAK | NON-MT | | R |
| 30050 | 22" LIVE OAK | MULTI-TRUNK | 12, 11, 9 | | 30115 | 10" CEDAR ELM | NON-MT | | R | 30185 | 9" LIVE OAK | NON-MT | | R | 61378 | 13" LIVE OAK | NON-MT | | R | 61456 | 13" LIVE OAK | NON-MT | | R |
| 30051 | 9" LIVE OAK | NON-MT | | | 30116 | 10" LIVE OAK | NON-MT | | R | 30186 | 8" LIVE OAK | NON-MT | | R | 61379 | 8" LIVE OAK | NON-MT | | R | 61457 | 10" LIVE OAK | NON-MT | | R |
| 30052 | 27" LIVE OAK | MULTI-TRUNK | 11, 10.5, 8 | | 30117 | 17.5" LIVE OAK | MULTI-TRUNK | 10, 9, 6 | R | 30187 | 8" LIVE OAK | NON-MT | | R | 61380 | 11" LIVE OAK | NON-MT | | R | 61458 | 11" LIVE OAK | NON-MT | | R |
| 30053 | 15" LIVE OAK | NON-MT | | | 30118 | 14" LIVE OAK | NON-MT | | R | 61025 | 12" LIVE OAK | NON-MT | | R | 61381 | 8" LIVE OAK | NON-MT | | R | 61506 | 19" LIVE OAK | NON-MT | | R |
| 30054 | 10" LIVE OAK | NON-MT | | | 30119 | 14" LIVE OAK | MULTI-TRUNK | 11, 6 | | 61026 | 11" LIVE OAK | NON-MT | | R | 61382 | 14" LIVE OAK | NON-MT | | R | 61507 | 8" LIVE OAK | NON-MT | | |
| 30055 | 15" LIVE OAK | MULTI-TRUNK | 10, 10 | | 30120 | 30" LIVE OAK | MULTI-TRUNK | 20, 10, 10 | | 61027 | 13" LIVE OAK | NON-MT | | | 61383 | 9" LIVE OAK | NON-MT | | R | | | | | |
| 30056 | 11" LIVE OAK | NON-MT | | | 30122 | 8" LIVE OAK | NON-MT | | | 61300 | 11" LIVE OAK | NON-MT | | R | 61384 | 15" LIVE OAK | NON-MT | | R | | | | | |
| 30057 | 9" LIVE OAK | NON-MT | | R | 30123 | 16" LIVE OAK | MULTI-TRUNK | 11, 10 | R | 61301 | 11" LIVE OAK | NON-MT | | R | 61385 | 11" LIVE OAK | NON-MT | | R | | | | | |
| 30058 | 10" LIVE OAK | MULTI-TRUNK | 7, 6 | R | 30125 | 13" LIVE OAK | MULTI-TRUNK | 8, 4, 6 | R | 61302 | 10" LIVE OAK | NON-MT | | R | 61386 | 10" LIVE OAK | NON-MT | | Γ. | | | | | |
| 30059 | 15" LIVE OAK | MULTI-TRUNK | 10, 10 | R | 30126 | 9" LIVE OAK | NON-MT | | R | 61303 | 12" LIVE OAK | NON-MT | | R | 61388 | 15" LIVE OAK | NON-MT | | R | | | | | |
| 30060 | 12" LIVE OAK | MULTI-TRUNK | 8, 8 | R | 30127 | 8" LIVE OAK | NON-MT | | R | 61304 | 10" MISC. TREE | NON-MT | | R | 61388 | 21.5" LIVE OAK | MULTI-TRUNK | 15, 13 | R | | | | | |
| 30061 | 19.5" LIVE OAK | MULTI-TRUNK | 14, 11 | R | 30128 | 12" LIVE OAK | MULTI-TRUNK | 8, 8 | R | 61305 | 10" MISC. TREE | NON-MT | | R | 61399 | | NON-MT | 10, 10 | R | | | | | |
| 30062 | 11.5" LIVE OAK | MULTI-TRUNK | 9, 5 | R | 30129 | 10" LIVE OAK | NON-MT | | R | 61325 | 20" LIVE OAK | MULTI-TRUNK | 16, 12 | R | 61390 | 16" LIVE OAK | NON-MT | | R | | | | | |
| 30063 | 13.5" LIVE OAK | MULTI-TRUNK | 9, 9 | R | 30130 | 10" LIVE OAK | NON-MT | | R | 61326 | 17" LIVE OAK | NON-MT | | R | 61391 | | NON-MT | | R | | | | | |
| 30064 | 13.5" LIVE OAK | MULTI-TRUNK | 9, 9 | R | 30131 | 13" LIVE OAK | NON-MT | | R | 61327 | 15" CEDAR ELM | NON-MT | | R | 61392 | 12" LIVE OAK 18.5" LIVE OAK | NON-MT | | R | | | | | |
| 30065 | | | 8, 7, 7 | | 30133 | 13" CEDAR ELM | NON-MT | | R | 61328 | 16.5" LIVE OAK | MULTI-TRUNK | 11, 11 | | 61393 | 18.5" LIVE OAK | NON-MT | | R | | | | | |
| 30066 | 10" LIVE OAK | NON-MT | | R | 30134 | 10" LIVE OAK | NON-MT | | R | 61329 | 13" LIVE OAK | NON-MT | | R | 61394 | 12" LIVE OAK 13" CEDAR ELM | NON-MT | | R | | | | | |
| 30067 | 9" LIVE OAK | NON-MT | | R | 30135 | 8" LIVE OAK | NON-MT | | R | 61330 | 10" LIVE OAK | NON-MT | | R | 61395 | 9" LIVE OAK | NON-MT | | R | | | | | |
| 30068 | 8" LIVE OAK | NON-MT | | R | 30136 | 9" LIVE OAK | NON-MT | | R | 61331 | 10" LIVE OAK | NON-MT | | R | 61396 | | NON-MT | | R | | | | | |
| 30069 | | NON-MT | | | 30137 | 9" LIVE OAK | NON-MT | | R | 61332 | 10" LIVE OAK | NON-MT | | R | 0139/ | 9" LIVE OAK | INOIN-IVI I | | Γ | | | | | |

61333 11" LIVE OAK NON-MT

61334 11" LIVE OAK NON-MT

61335 10" LIVE OAK NON-MT

61336 9" LIVE OAK NON-MT

61398 12" LIVE OAK NON-MT

61400 15" LIVE OAK NON-MT

61401 14" LIVE OAK NON-MT

61399 | 18.5" LIVE OAK | MULTI-TRUNK | 13, 11 | R

30139 8" LIVE OAK NON-MT

30140 10" LIVE OAK NON-MT

30141 11" LIVE OAK NON-MT

30138 | 11.5" LIVE OAK | MULTI-TRUNK | 8, 7 | R

30069 9" LIVE OAK NON-MT

30070 8" LIVE OAK NON-MT

30071 9" LIVE OAK NON-MT

30072 9" LIVE OAK NON-MT

30073 11" LIVE OAK NON-MT

TREE LEGEND

- H HERITAGE TREE R TREE TO BE REMOVED
- TREE SURVEY DATE: 7/9/2021



TREE

BENCHMARKS

DATUM IS NAVD '88, USING GEOID xxx, BASED ON GPS OBSERVATIONS.

BM #100 MAG SET JUST WEST OF END OF SIDEWALK ON EASTERN SIDE OF MORRIS STREET JUST SOUTH OF TALYNE CHAISE INTERSECTION

ELEV.=875.069'

BM #101 MAG SET JUST WEST OF SIDEWALK ON WESTERN SIDE OF MORRIS RD JUST SOUTH OF YELLOW OAK INTERSECTION


SITE PLAN APPROVAL SHEET 8 OF 48 FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024 UNDER SECTION 112 OF APPROVED BY COMMISSION ON_ CHAPTER 25-5 OF THE CITY OF AUSTIN CODE. EXPIRATION DATE (25-5-81,LDC) _____CASE MANAGER CLARISSA E. DAVIS PROJECT EXPIRATION DATE (ORD.#970905-A)_____DWPZ____DDZ__ Director, Development Services Department RELEASED FOR GENERAL COMPLIANCE: ZONING MF-2, MF-2 CO Rev. 1 Correction 1 _Correction 2_ _Correction 3_ Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.





SHEET NUMBER 8 OF 48


20


32




















| Intensity-Du | | juency Curv NE 2) | e Coefficient |
|--------------|-------|----------------------|---------------|
| Frequency | a | b | С |
| 2 | 46.99 | 9.575 | 0.7517 |
| 10 | 60.75 | 8.361 | 0.7185 |
| 25 | 64.56 | 7.382 | 0.6814 |
| 100 | 76.9 | 6.726 | 0.6554 |

| | | Р | roposed "C" Va | alue Calculations | | , | |
|--------------|----------------|-----------|----------------|-------------------|------------|-----------------|------------------|
| D.A. | Drainage | Drainage | Pervious Area | Impervious Area | I.C. | Comp. | Comp. |
| Number | Area (SF) | Area (Ac) | (SF) | (SF) | (%) | C ₂₅ | C ₁₀₀ |
| A-1 | 6,534 | 0.15 | 4706 | 1828 | 28% | 0.53 | 0.60 |
| A-2 | 8,276 | 0.19 | 6653 | 1623 | 20% | 0.49 | 0.56 |
| A-3 | 8,712 | 0.20 | 6610 | 2102 | 24% | 0.51 | 0.58 |
| A-4 | 10,019 | 0.23 | 895 | 9124 | 91% | 0.84 | 0.92 |
| A-5 | 6,098 | 0.14 | 497 | 5601 | 92% | 0.84 | 0.93 |
| A-6 | 17,424 | 0.40 | 8902 | 8522 | 49% | 0.63 | 0.71 |
| A-7 | 5,227 | 0.12 | 670 | 4557 | 87% | 0.82 | 0.90 |
| A-8 | 1,742 | 0.04 | 465 | 1277 | 73% | 0.75 | 0.83 |
| A-9 | 4,792 | 0.11 | 2794 | 1997 | 42% | 0.59 | 0.67 |
| A-10 | 1,307 | 0.03 | 426 | 880 | 67% | 0.72 | 0.80 |
| A-11 | 6,970 | 0.16 | 3372 | 3597 | 52% | 0.64 | 0.72 |
| A-12 | 19,602 | 0.45 | 9432 | 10170 | 52% | 0.64 | 0.72 |
| A-13 | 2,178 | 0.05 | 1079 | 1099 | 50% | 0.64 | 0.72 |
| A-14 | 4,356 | 0.10 | 298 | 4058 | 93% | 0.85 | 0.94 |
| A-15 | 3,485 | 0.08 | 274 | 3211 | 92% | 0.84 | 0.93 |
| A-16 | 3,049 | 0.07 | 1673 | 1376 | 45% | 0.61 | 0.69 |
| A-17 | 3,049 | 0.07 | 195 | 2854 | 94% | 0.85 | 0.94 |
| A-18 | 3,920 | 0.09 | 257 | 3663 | 93% | 0.85 | 0.94 |
| A-19 | 5,663 | 0.13 | 2975 | 2688 | 47% | 0.62 | 0.70 |
| A-20 | 24,829 | 0.57 | 3050 | 21780 | 88% | 0.82 | 0.91 |
| A-21 | 9,148 | 0.21 | 692 | 8456 | 92% | 0.84 | 0.93 |
| A-22 | 7,405 | 0.17 | 5275 | 2131 | 29% | 0.53 | 0.61 |
| A-23 | 5,227 | 0.12 | 2875 | 2352 | 45% | 0.61 | 0.69 |
| A-24 | 47,480 | 1.09 | 26114 | 21366 | 45% | 0.61 | 0.69 |
| B-1 | 2,614 | 0.06 | 1875 | 739 | 28% | 0.53 | 0.60 |
| B-2 | 10,019 | 0.23 | 4419 | 5600 | 56% | 0.66 | 0.75 |
| B-3 | 15,682 | 0.36 | 2067 | 13614 | 87% | 0.82 | 0.90 |
| B-4 | 10,890 | 0.25 | 6410 | 4480 | 41% | 0.59 | 0.67 |
| B-5 | 10,890 | 0.25 | 1302 | 9588 5545 | 88% 42% | 0.82 | 0.91 |
| B-6 B-7 | 13,068 | 0.30 | 7523 517 | 8630 | 94% | 0.60 0.85 | 0.68 |
| B-8 | 9,148 5,663 | 0.21 | 3380 | 2283 | 40% | 0.65 | 0.94 |
| B-9 | 3,920 | 0.13 | 3920 | 0 | 0% | 0.39 | 0.46 |
| B-10 | 11,761 | 0.09 | 7110 | 4652 | 40% | 0.58 | 0.40 |
| B-10 B-11 | 6,534 | 0.27 | 4333 | 2201 | 34% | 0.56 | 0.63 |
| B-11 | 3,049 | 0.07 | 3049 | 0 | 0% | 0.39 | 0.46 |
| B-13 | 5,663 | 0.13 | 4804 | 859 | 15% | 0.46 | 0.54 |
| B-14 | 8,276 | 0.19 | 405 | 7871 | 95% | 0.86 | 0.95 |
| B-15 | 12,197 | 0.28 | 1314 | 10882 | 89% | 0.83 | 0.92 |
| B-16 | 7,841 | 0.18 | 5405 | 2435 | 31% | 0.54 | 0.62 |
| B-17 | 8,712 | 0.20 | 4615 | 4097 | 47% | 0.62 | 0.70 |
| B-18 | 5,663 | 0.13 | 1707 | 3955 | 70% | 0.73 | 0.82 |
| B-19 | 44,431 | 1.02 | 24437 | 19994 | 45% | 0.61 | 0.69 |
| D-01 | 4,356 | 0.10 | 4356 | 0 | 0% | 0.39 | 0.46 |
| D-02 | 436 | 0.01 | 0 | 436 | 100% | 0.88 | 0.97 |
| D-03 | 5,227 | 0.12 | 4879 | 348 | 7% | 0.42 | 0.49 |
| | 1 -, | J. 12 | 1 .5,5 | J 10 | . , , | J | J |

| DΛ | Drainage | | | | Calculat | _ | ; | $\overline{}$ | _ |
|--------|-----------|------------|-----------------|------------------|-----------------------|-----------------|------------------|-----------------|------------------|
| D.A. | | TOTAL I.C. | | | TOTAL | i ₂₅ | i ₁₀₀ | Q ₂₅ | Q ₁₀₀ |
| Number | Area (Ac) | (%) | C ₂₅ | C ₁₀₀ | T _c (Min.) | • | ` ' | (cfs) | (cfs) |
| A-1 | 0.15 | 28% | 0.53 | 0.60 | 5.0 | 11.62 | 15.32 | 0.92 | 1.38 |
| A-2 | 0.19 | 20% | 0.49 | 0.56 | 5.0 | 11.62 | 15.32 | 1.07 | 1.63 |
| A-3 | 0.20 | 24% | 0.51 | 0.58 | 5.0 | 11.62 | 15.32 | 1.18 | 1.79 |
| A-4 | 0.23 | 91% | 0.84 | 0.92 | 5.0 | 11.62 | 15.32 | 2.24 | 3.26 |
| A-5 | 0.14 | 92% | 0.84 | 0.93 | 5.0 | 11.62 | 15.32 | 1.37 | 1.99 |
| A-6 | 0.40 | 49% | 0.63 | 0.71 | 5.0 | 11.62 | 15.32 | 2.93 | 4.35 |
| A-7 | 0.12 | 87% | 0.82 | 0.90 | 5.0 | 11.62 | 15.32 | 1.14 | 1.66 |
| A-8 | 0.04 | 73% | 0.75 | 0.83 | 5.0 | 11.62 | 15.32 | 0.35 | 0.51 |
| A-9 | 0.11 | 42% | 0.59 | 0.67 | 5.0 | 11.62 | 15.32 | 0.76 | 1.13 |
| A-10 | 0.03 | 67% | 0.72 | 0.80 | 5.0 | 11.62 | 15.32 | 0.25 | 0.37 |
| A-11 | 0.16 | 52% | 0.64 | 0.72 | 5.0 | 11.62 | 15.32 | 1.20 | 1.77 |
| A-12 | 0.45 | 52% | 0.64 | 0.72 | 5.0 | 11.62 | 15.32 | 3.37 | 4.99 |
| A-13 | 0.05 | 50% | 0.64 | 0.72 | 5.0 | 11.62 | 15.32 | 0.37 | 0.55 |
| A-14 | 0.10 | 93% | 0.85 | 0.94 | 5.0 | 11.62 | 15.32 | 0.98 | 1.43 |
| A-15 | 0.08 | 92% | 0.84 | 0.93 | 5.0 | 11.62 | 15.32 | 0.78 | 1.14 |
| A-16 | 0.07 | 45% | 0.61 | 0.69 | 5.0 | 11.62 | 15.32 | 0.50 | 0.74 |
| A-17 | 0.07 | 94% | 0.85 | 0.94 | 5.0 | 11.62 | 15.32 | 0.69 | 1.01 |
| A-18 | 0.09 | 93% | 0.85 | 0.94 | 5.0 | 11.62 | 15.32 | 0.89 | 1.29 |
| A-19 | 0.13 | 47% | 0.62 | 0.70 | 5.0 | 11.62 | 15.32 | 0.94 | 1.40 |
| A-20 | 0.57 | 88% | 0.82 | 0.91 | 5.0 | 11.62 | 15.32 | 5.43 | 7.92 |
| A-21 | 0.21 | 92% | 0.84 | 0.93 | 5.0 | 11.62 | 15.32 | 2.06 | 3.00 |
| A-22 | 0.17 | 29% | 0.53 | 0.61 | 5.0 | 11.62 | 15.32 | 1.05 | 1.58 |
| A-23 | 0.12 | 45% | 0.61 | 0.69 | 5.0 | 11.62 | 15.32 | 0.85 | 1.27 |
| A-24 | 1.09 | 45% | 0.61 | 0.69 | 13.7 | 8.10 | 10.66 | 5.39 | 8.01 |
| B-1 | 0.06 | 28% | 0.53 | 0.60 | 5.0 | 11.62 | 15.32 | 0.37 | 0.56 |
| B-2 | 0.23 | 56% | 0.66 | 0.75 | 5.0 | 11.62 | 15.32 | 1.77 | 2.62 |
| B-3 | 0.36 | 87% | 0.82 | 0.90 | 5.0 | 11.62 | 15.32 | 3.41 | 4.98 |
| B-4 | 0.25 | 41% | 0.59 | 0.67 | 5.0 | 11.62 | 15.32 | 1.72 | 2.57 |
| B-5 | 0.25 | 88% | 0.82 | 0.91 | 5.0 | 11.62 | 15.32 | 2.39 | 3.48 |
| B-6 | 0.30 | 42% | 0.60 | 0.68 | 5.0 | 11.62 | 15.32 | 2.08 | 3.11 |
| B-7 | 0.21 | 94% | 0.85 | 0.94 | 5.0 | | 15.32 | 2.08 | 3.03 |
| B-8 | 0.13 | 40% | 0.59 | 0.67 | 5.0 | 11.62 | 15.32 | 0.89 | 1.33 |
| B-9 | 0.09 | 0% | 0.39 | 0.46 | 5.0 | 11.62 | 15.32 | 0.41 | 0.63 |
| B-10 | 0.27 | 40% | 0.58 | 0.66 | 5.0 | 11.62 | 15.32 | 1.83 | 2.74 |
| B-11 | 0.15 | 34% | 0.56 | 0.63 | 5.0 | 11.62 | 15.32 | 0.97 | 1.45 |
| B-12 | 0.07 | 0% | 0.39 | 0.46 | 5.0 | 11.62 | 15.32 | 0.32 | 0.49 |
| B-13 | 0.13 | 15% | 0.46 | 0.54 | 5.0 | 11.62 | 15.32 | 0.70 | 1.07 |
| B-14 | 0.19 | 95% | 0.86 | 0.95 | 5.0 | 11.62 | 15.32 | 1.89 | 2.75 |
| B-15 | 0.28 | 89% | 0.83 | 0.92 | 5.0 | 11.62 | 15.32 | 2.69 | 3.92 |
| B-16 | 0.18 | 31% | 0.54 | 0.62 | 5.0 | 11.62 | 15.32 | 1.13 | 1.71 |
| B-17 | 0.20 | 47% | 0.62 | 0.70 | 5.0 | 11.62 | 15.32 | 1.44 | 2.14 |
| B-18 | 0.13 | 70% | 0.73 | 0.82 | 5.0 | 11.62 | 15.32 | 1.11 | 1.63 |
| B-19 | 1.02 | 45% | 0.61 | 0.69 | 13.8 | 8.05 | 10.60 | 5.01 | 7.45 |
| D-01 | 0.10 | 0% | 0.39 | 0.46 | 5.0 | 11.62 | 15.32 | 0.45 | 0.70 |
| D-02 | 0.01 | 100% | 0.88 | 0.97 | 5.0 | 11.62 | 15.32 | 0.10 | 0.15 |
| D-03 | 0.12 | 7% | 0.42 | 0.49 | 5.0 | 11.62 | 15.32 | 0.59 | 0.91 |


| Note. All inlet drainage calculations have been determined using the Rational Method per the |
|----------------------------------------------------------------------------------------------|
| City of Austin Engineering Design Manual. |

| | | | Inlet Calculation Table | | | | | | |
|--------------|-----------------------------|------------------------------------------------------------------------------------------|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------|-----------|--------------|------------------------------------------|--|--|
| Equations: C | Curb Inlet Orifice (Submerg | ed) Q=0.67*h*L*(2gd)^.5 (CC ed) Q=3*L*d^1.5 (COA Eq. 4 ged) Q=0.67*A*(2gd)^.5 (COA | -3) | Clogging Factor = 0% (Area inlets in Sump) Clogging Factor = 10% (Curb inlets in Sump) Clogging Factor = 50% (Grate inlets in Sump) | | | | | |
| Inlet# or | Q25 - Required Q to Pass | Q100 - Required Q to Pass | INLET | Available Weir | Open Area | Provided 'h' | Provided Capacity (w/ Clogging Factor | | |
| Area # | (cfs) | (cfs) |] | Length (ft) | (sf) | (ft.) | (cfs) | | |
| A-1 | 0.92 cfs | 1.38 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| A-2 | 1.07 cfs | 1.63 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| A-3 & A-24 | 6.57 cfs | 9.80 cfs | 4' - 4' Sided Area Inlet | 16.0 | N/A | 0.42' | 35.8 cfs | | |
| A-4 | 2.24 cfs | 3.26 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-5 | 1.37 cfs | 1.99 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-6 | 2.93 cfs | 4.35 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.17' | 5.18 cfs | | |
| A-7 | 1.14 cfs | 1.66 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-8 | 0.35 cfs | 0.51 cfs | 24"x12" - Trench Grate | N/A | 0.89 | 0.17' | 0.98 cfs | | |
| A-9 | 0.76 cfs | 1.13 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.50' | 8.98 cfs | | |
| A-10 | 0.25 cfs | 0.37 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.50' | 8.98 cfs | | |
| A-11 | 1.20 cfs | 1.77 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| A-12 | 3.37 cfs | 4.99 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| A-13 | 0.37 cfs | 0.55 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| A-14 | 0.98 cfs | 1.43 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-15 | 0.78 cfs | 1.14 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-16 | 0.50 cfs | 0.74 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| A-17 | 0.69 cfs | 1.01 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.08' | 1.71 cfs | | |
| A-18 | 0.89 cfs | 1.29 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| A-19 | 0.94 cfs | 1.40 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.50' | 8.98 cfs | | |
| A-20 | 5.43 cfs | 7.92 cfs | 5' x 5' - Grate Inlet | N/A | 19.49 | 0.08' | 15.13 cfs | | |
| A-21 | 2.06 cfs | 3.00 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.08' | 3.63 cfs | | |
| A-22 & A-23 | 1.90 cfs | 2.85 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| B-1 | 0.37 cfs | 0.56 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| B-2 | 1.77 cfs | 2.62 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| B-3 | 3.41 cfs | 4.98 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.17' | 5.18 cfs | | |
| B-4 | 1.72 cfs | 2.57 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| B-5 | 2.39 cfs | 3.48 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| B-6 | 2.08 cfs | 3.11 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| B-7 | 2.08 cfs | 3.03 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| B-8 & B-9 | 1.30 cfs | 1.96 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| B-10 | 1.83 cfs | 2.74 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| B-11 & B-19 | | 8.91 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.50' | 8.98 cfs | | |
| B-13 & B-12 | | 1.56 cfs | 3' x 3' - Grate Inlet | N/A | 4.67 | 0.50' | 8.88 cfs | | |
| B-14 | 1.89 cfs | 2.75 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.08' | 3.66 cfs | | |
| B-15 | 2.69 cfs | 3.92 cfs | 10' - Curb Inlet | 10.0 | N/A | 0.50' | 9.55 cfs | | |
| B-16 | 1.13 cfs | 1.71 cfs | 4' x 4' - Grate Inlet | N/A | 4.72 | 0.50' | 8.98 cfs | | |
| B-17 | 1.44 cfs | 2.14 cfs | 2' x 2' - Grate Inlet | N/A | 2.21 | 0.50' | 4.20 cfs | | |
| B-18 | 1 11 cfs | 1 63 cfs | 24"v12" - Trench Grate | | 0.89 | 0.50' | 1 69 cfs | | |

OBSERVATIONS.

BM #100 MAG SET JUST WEST OF END OF SIDEWALK ON EASTERN SIDE OF MORRIS STREET JUST SOUTH OF TALYNE CHAISE INTERSECTION

Know what's below.
Call before you dig.



BENCHMARKS

DATUM IS NAVD '88, USING GEOID xxx, BASED ON GPS OBSERVATIONS.

BM #101 MAG SET JUST WEST OF SIDEWALK ON WESTERN SIDE OF MORRIS RD JUST SOUTH OF YELLOW OAK INTERSECTION

SITE PLAN APPROVAL SHEET 18 OF 48

CHAPTER 25-5 OF THE CITY OF AUSTIN CODE.

APPROVED BY COMMISSION ON_

Director, Development Services Department RELEASED FOR GENERAL COMPLIANCE:__

Rev. 1_

FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024

EXPIRATION DATE (25-5-81,LDC) ____CASE MANAGER CLARISSA E. DAVIS PROJECT EXPIRATION DATE (ORD.#970905-A)_____DWPZ____DDZ__

Correction 1


Correction 2 _Correction 3_ Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans


which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.


UNDER SECTION 112 OF


ZONING MF-2, MF-2 CO


SHEET NUMBER 18 OF 48
















| | PON | ID "A" Partial 9 | Appendi Sedimentation/Filtration Po | ond Calculations for Develo | nment Permits |
|--------------------------|----------------|---------------------|----------------------------------------|------------------------------|------------------|
| Drainage Aı | | A Farual | Seamentation/Filtration Po | Jila Galculations for Develo | pinelit reilills |
| Drainage Ar | | ol (DA) | | 6.27 AC. | |
| _ | | Impervious Cover | | 51% | |
| Capture Dep | | | | 0.81 IN. | |
| | - () | | | | |
| Water Quali | ty Control | Calculations: | | Required | Provided |
| The Water | Quality Co | ntrol is to be Par | tial Sedimentation/Filtration | | |
| | | ate to Control (Q | • | 37.30 CFS | |
| 100 Year P | eak Flow F | Rate to Control (0 | 2100) | 50.10 CFS | |
| | - | (WQV=CD*DA* | • | 18436 CF | 19580 CF |
| | | pth Above Sand | Bed (H) | 1 | 8.00 FT |
| Sedimentat | | | 000/ 514/01/0 | | 1197 SF |
| | | Volume (minimun | • | 3687 CF | 9396 CF |
| | • | WQV/(4+1.33*H) - |) | 1259 SF | 1273 SF |
| Filtration Po | ond Volum | е | | | 10184_CF |
| Water Qua | lity Elevation | on | | | 876.70 FT MSL |
| | | verflow Weir | | Minimum WQ Elevation | 876.70 FT MSL |
| Height of G | abian Wal | l | | WQ Elevation - 0.5' | 876.20 FT |
| Length of S | Splitter Wei | r | | | 38 FT |
| Required H | | | | Max. 1.0 FT | 0.58 FT |
| Pond Freek | oard Prov | ided to Pass Q10 | 00 | Min. 0.25 FT | 0.25 FT |
| | | | | | |
| 48 Hour Dr | awdown Ti | ime Orifice Open | ing Diameter (inches) | | 1.24 IN |
| Sedimentat | ion Pond: | | | | |
| Stage A | Area | - | age Cumm. | | |
| (FT MSL) (| | (CF) (CF |) | | |
| 868.70 | 0 | 0 | 0 | | |
| 869.00 | 1,197 | 180 | 180 | | |
| 870.00 | 1,197 | 1197 | 1377 | 1 | |
| 871.00 | 1,197 | 1197 | 2574 | 1 | |
| 872.00 | 1,197 | 1197 | 3771 > 20% WQV | 1 | |
| 873.00 | 1,197 | 1197 | 4968 | 1 | |
| 874.00 | 1,197 | 1197 | 6165 | 1 | |
| 875.00 | 1,197 | 1197 | 7362 | 1 | |
| 876.00 | 1,197 | 1197 | 8559 | 1 | |
| 876.70 | 1,197 | 838 | 9396 | | |
| Filtration Po Stage A | ona: Area | Storage Stor | age Cumm. | | |
| (FT MSL) (| | (CF) (CF | | 1 | |
| 868.70 | 1,273 | 0 | 0 | 1 | |
| 869.00 | 1,273 | 382 | 382 | 1 | |
| 870.00 | 1,273 | 1273 | 1655 | 1 | |
| 871.00 | 1,273 | 1273 | 2928 | 1 | |
| 872.00 | 1,273 | 1273 | 4201 | 1 | |
| 873.00 | 1,273 | 1273 | 5474 | 1 | |
| 874.00 | 1,273 | 1273 | 6747 | 1 | |
| 875.00 | 1,273 | 1273 | 8020 | 1 | |
| 876.00 | 1,273 | 1273 | 9293 | 1 | |
| 876 70 | 1 273 | 891 | 10184 WQV | I | |

| | | UDU B | 10:: | Append | | -4: f- - | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|-----------|--------------------------|-------------------------|
| | | "B" Partia | aı Sedimen | tation/Filtration Po | nd Calcul | ations for Develor | oment Permits |
| | Area Data: | | | | | 474.00 | |
| - | Area to Contr | | _ | | | 4.71 AC. | |
| - | Area Percent | Impervious (| Cover | | | 63% | |
| Capture De | epth (CD) | | | | | 0.93 IN. | |
| Water Qu | ıality Contro | l Calculatio | ons: | | Requ | ired | Provided |
| The Wate | er Quality C | ontrol is to | be Partial Se | edimentation/Filtration | , [| | |
| | | | | | | | |
| 25 Year F | Peak Flow F | Rate to Cor | trol (Q25) | | | 23.70 CFS | |
| 100 Year | Peak Flow | Rate to Co | ntrol (Q100) | | | 31.60 CFS | |
| Water Qı | ualitv Volum | e (WQV=0 | D*DA*3630 |)) | | 15900 CF | 16191 CF |
| | - | | Sand Bed (| • | | | 7.50 FT |
| | tation Pond | • | ` | , | | | 1197 SF |
| | | | ninimum 20% | 6 of WQV) | | 3180 CF | 6643 CF |
| | Pond Area | • | | • • • • • • • | | 1138 SF | 1273 CF |
| | Pond Volum | | 1.55 1197 | | - | 1100 | 9548 CF |
| i iii aliOII | i ona voidii | 10 | | | | | OF |
| Water Qı | uality Elevat | ion | | | | | 876.10 FT MSL |
| | of Splitter/C | | eir eir | | Minin | num WQ Elevation | 876.10 FT MSL |
| | Gabian Wa | | O.I. | | I | Elevation - 0.5' | 875.60 FT |
| | | | | | | | |
| Length of | | | | | | | |
| Longin Of | f Splitter We | eir | | | | | 38 FT |
| | f Splitter We I Head to Pa | | | | M | ax. 1.0 FT | <u>38</u> FT 0.43 FT |
| Required | f Splitter We I Head to Pa eeboard Pro | ss Q100 | ıss Q100 | | | ax. 1.0 FT n. 0.25 FT | |
| Required | l Head to Pa | ss Q100 | ss Q100 | | | | 0.43 FT |
| Required Pond Fre | I Head to Pa eeboard Pro | iss Q100 vided to Pa | | viameter (inches) | | | 0.43 FT |
| Required Pond Fre | I Head to Pa eeboard Pro | iss Q100 vided to Pa | | viameter (inches) | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour [| I Head to Pa eeboard Pro | iss Q100 vided to Pa Fime Orific | | liameter (inches) | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour [Sediment | I Head to Pa eeboard Pro Drawdown 1 | iss Q100 vided to Pa Fime Orific Storage | e Opening D Storage Cu | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour [Sediment | Head to Pa eeboard Pro Drawdown T tation Pond: Area | iss Q100 vided to Pa Fime Orific | e Opening D | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) 868.60 | Head to Pa eeboard Pro Drawdown T tation Pond: Area | ss Q100 vided to Pa Fime Orifice Storage (CF) 0 | Storage Cu (CF) | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) | Head to Pageboard Production Drawdown Tation Pond: Area) (SF) | ss Q100 vided to Pa Fime Orifice Storage (CF) | Storage Cu | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) 868.60 | I Head to Pa eeboard Prod Drawdown T tation Pond: Area () (SF) | ss Q100 vided to Pa Fime Orifice Storage (CF) 0 | Storage Cu (CF) | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Stage (FT MSL) 868.60 869.00 | I Head to Pa eeboard Pro Drawdown 1 tation Pond: Area) (SF) 0 1,197 | ss Q100 vided to Pa Fime Orific Storage (CF) 0 239 | Storage Cu (CF) 0 239 | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 872.00 | I Head to Pa beboard Prodeboard P | ss Q100 vided to Pa Fime Orific Storage (CF) 0 239 1197 | Storage Cu (CF) 0 239 1436 | | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 | I Head to Pageboard Production Ponds tation Ponds Area 0 (SF) 0 1,197 1,197 1,197 | ss Q100 vided to Par Firme Orification Storage (CF) 0 239 1197 1197 | Storage Cu (CF) 0 239 1436 2633 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour I Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 872.00 | I Head to Pageboard Production Ponds Area () (SF) 0 1,197 1,197 1,197 1,197 | ss Q100 vided to Par Firme Orification (CF) 0 239 1197 1197 1197 | Storage Cu (CF) 0 239 1436 2633 3830 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 872.00 873.00 | I Head to Pa eeboard Prode Drawdown Tattion Ponds Area () (SF) 0 1,197 1,197 1,197 1,197 1,197 | ss Q100 vided to Par Firme Orification (CF) 0 239 1197 1197 1197 1197 | Storage Cu (CF) 0 239 1436 2633 3830 5027 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 873.00 874.00 | I Head to Page board Prove Drawdown To tation Ponds Area () (SF) () 1,197 1,197 1,197 1,197 1,197 1,197 1,197 | Storage (CF) 0 239 1197 1197 1197 1197 | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 872.00 873.00 874.00 875.00 | I Head to Page board Production P | ss Q100 vided to Par Vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 873.00 875.00 876.00 876.10 | I Head to Page board Provide Marketion Pond: Area () (SF) 0 1,197 1,197 1,197 1,197 1,197 1,197 1,197 1,197 1,197 1,197 1,197 1,197 | ss Q100 vided to Pa vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 | umm. | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 873.00 875.00 876.00 876.00 876.00 876.10 Filtration Stage | I Head to Page board Provide B | ss Q100 vided to Pa vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 873.00 875.00 876.00 876.00 876.00 876.10 Filtration Stage | I Head to Page board Provide B | ss Q100 vided to Pa vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 873.00 875.00 876.00 876.00 876.00 876.10 Filtration Stage | I Head to Page board Provide B | ss Q100 vided to Pa vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 | I Head to Page board Provide B | ss Q100 vided to Pa vided to P | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 870.00 871.00 872.00 875.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876. | I Head to Page board Provide B | ss Q100 vided to Pa Fime Orifica Storage (CF) 0 239 1197 1197 1197 1197 1197 1197 120 Storage (CF) 0 | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 870.00 871.00 873.00 875.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 | I Head to Page board Provide B | ss Q100 vided to Pa Fime Orifica Storage (CF) 0 239 1197 1197 1197 1197 1197 1197 120 Storage (CF) 0 509 | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 870.00 871.00 873.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 | I Head to Page board Provide B | ss Q100 vided to Particle Storage (CF) | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 1782 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 548 Hour E 549 (FT MSL) 868.60 869.00 871.00 872.00 875.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 870.00 870.00 871.00 872.00 | Head to Page board Prove between Transport Interest Inter | ss Q100 vided to Particle Storage (CF) | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 1782 3055 4328 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 875.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 870.00 870.00 871.00 873.00 873.00 | Head to Page board Provide Boa | ss Q100 vided to Particle Storage (CF) | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 1782 3055 4328 5601 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 870.00 871.00 875.00 876.01 Filtration (FT MSL) 868.60 869.00 870.00 871.00 873.00 871.00 873.00 873.00 874.00 | Head to Page board Provide Boa | ss Q100 vided to Particle Storage (CF) | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 1782 3055 4328 5601 6874 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |
| Required Pond Fre 48 Hour E 5 Sediment Stage (FT MSL) 868.60 869.00 871.00 872.00 875.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 876.00 870.00 870.00 871.00 873.00 873.00 | Head to Page board Provide Boa | ss Q100 vided to Particle Storage (CF) | Storage Cu (CF) 0 239 1436 2633 3830 5027 6224 7421 8618 8738 Storage Cu (CF) 0 509 1782 3055 4328 5601 | umm. > 20% WQV | | | 0.43 FT 0.25 FT |










 \sim

SHEET NUMBER


 \mathcal{C}







GABION WALL NOTES



MAINTENANCE NOTES

THE FOLLOWING MAINTENANCE ACTIVITIES SHALL BE PERFORMED ON ALL SCMS, IN ADDITION TO THE REQUIREMENTS LISTED FOR THE INDIVIDUAL SCM TYPES, TO ENSURE PROPER FUNCTION:

- A. ACCUMULATED PAPER, TRASH AND DEBRIS SHALL BE REMOVED EVERY SIX (6) MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- B. STRUCTURAL INTEGRITY SHALL BE MAINTAINED AT ALL TIMES. BASINS AND ALL APPURTENANCES SHALL BE INSPECTED ANNUALLY, OR MORE FREQUENTLY IF SPECIFIED, AND REPAIRS
- SHALL BE MADE IF NECESSARY. WHEN MAINTENANCE OR REPAIRS ARE PERFORMED, THE SCM SHALL BE RESTORED TO THE ORIGINAL LINES AND GRADES. C. CORRECTIVE MAINTENANCE SHALL OCCUR:
 - I. ANY TIME DRAWDOWN OF THE WATER QUALITY VOLUME DOES NOT OCCUR WITHIN NINETY-SIX (96) HOURS (I.E., NO STANDING WATER IS ALLOWED), UNLESS A GREATER MAXIMUM DRAWDOWN TIME IS SPECIFIED IN THE PLANS.
- II. FOR DETENTION PONDS ONLY, ANY TIME DRAWDOWN DOES NOT OCCUR WITHIN TWENTY-FOUR (24) HOURS. D. THE INLET AND OUTLET OF SCMS SHALL BE MAINTAINED UNIMPEDED IN ORDER TO CONVEY FLOW AT ALL TIMES. OBSERVED BLOCKAGES TO THE INLET AND OUTLET, DUE TO
- VEGETATION, SEDIMENT, DEBRIS, OR ANY OTHER CAUSE, SHALL BE REMOVED. E. NO UNVEGETATED AREA SHALL EXCEED TEN (10) SQUARE FEET. THIS PERFORMANCE REQUIREMENT APPLIES TO THE ENTIRE POND INCLUDING THE POND BOTTOM, SIDE SLOPES, AND
- AREAS ADJACENT TO THE POND, AND IS INTENDED TO LIMIT EROSION. INTEGRATED PEST MANAGEMENT SHALL BE PERFORMED AND SHALL ADHERE TO SECTION 1.6.2.F, INTEGRATED PEST MANAGEMENT GUIDELINES.
- G. THE MINIMUM VEGETATION HEIGHT SHALL BE FOUR (4) INCHES IN THE SCM AND ALL APPURTENANCES, INCLUDING THE TOE OF THE BERM OR WALL OUTSIDE THE SCM, WHERE
- APPLICABLE. H. SEDIMENT BUILD-UP SHALL BE REMOVED:
- WHEN THE ACCUMULATION EXCEEDS SIX (6) INCHES IN SPLITTER BOXES, WET WELLS AND BASINS. WHEN SEDIMENT TRAPS ARE FULL.
- III. WHEN SEDIMENT, OF ANY AMOUNT, CAUSES STANDING WATER CONDITIONS OR REDUCES BASIN STORAGE BY MORE THAN 10%.
- I. WHEN SEDIMENT IS REMOVED, THE FOLLOWING REQUIREMENTS APPLY: IRRIGATION SHALL BE PROVIDED, AS NEEDED, UNTIL VEGETATION IS ESTABLISHED (WELL ROOTED). SEE SECTION 1.6.3.D, IRRIGATION GUIDELINES.
- THE DESIGN DEPTH OF THE FILTRATION MEDIA SHALL BE VERIFIED. SEE SECTION 1.6.3.B.5. III. TILLING OF THE FILTRATION MEDIUM IS NOT ALLOWED.
- J. FOR SUBSURFACE PONDS MAINTENANCE PLAN REQUIREMENTS, REFER TO ECM SECTION 1.6.2(E).2.SEDIMENTATION AND FILTRATION SCMS (SECTION 1.6.5).


SEDIMENTATION AND FILTRATION SCMS (SECTION 1.6.5):


- A. VEGETATION WITHIN THE SCM SHALL NOT EXCEED EIGHTEEN (18) INCHES IN HEIGHT AT ANY TIME, EXCEPT AS CALLED FOR IN THE DESIGN.
- B. VEGETATION THAT IS MOWED OR CUT SHALL BE REMOVED FROM THE SCM.

A. VEGETATION WITHIN THE BASIN SHALL NOT EXCEED EIGHTEEN (18) INCHES IN HEIGHT AT ANY TIME.










OND


20 \sim


SHEET NUMBER


 \mathcal{C}

26 OF 48










895

3+50


3+00




895


0+00


1+00






PUBLIC PRIVATE







KHA PROJECT
064487031
DATE
APRIL 2024
SCALE: AS SHOWN
DESIGNED BY: AH

PUBLIC ASTEWATER A -NN AND PROFILE

BENCHMARKS

PROFILE SCALE

1" = 40' HORIZONTAL 1" = 4' VERTICAL

DATUM IS NAVD '88, USING GEOID xxx, BASED ON GPS OBSERVATIONS.

BM #100 MAG SET JUST WEST OF END OF SIDEWALK ON EASTERN SIDE OF MORRIS STREET JUST SOUTH OF TALYN CHAISE INTERSECTION

ELEV.=875.069'

BM #101 MAG SET JUST WEST OF SIDEWALK ON WESTERN SIDE OF MORRIS RD JUST SOUTH OF YELLOW OAK INTERSECTION

FV =874 612'


| SITE PLAN APPRO | OVAL SHEET 3 | 30_OF_48_ | | |
|------------------------------|--------------------------------------------|----------------------------|------------------------|---------------|
| FILE NUMBER S | P-2024-0063C APP | LICATION I | DATE 04/15/2024 | |
| APPROVED BY CO | OMMISSION ON | | UNDER SECTION | 112 OF |
| CHAPTER 25-5 | OF THE CITY OF A | AUSTIN CO | DE. | |
| EXPIRATION DAT | ΓΕ (25-5-81,LDC) | CASE | MANAGER CLAF | RISSA E. DAV |
| PROJECT EXPIRA | TION DATE (ORD.#97 | 70905-A) | DWPZ | DDZ |
| | | | | |
| , 1 | ent Services Departmen GENERAL COMPLIAN | | ZONING M I | F-2, MF-2 CO |
| RELEASED FOR G | ent Services Departmen GENERAL COMPLIAN | CE: | | |
| RELEASED FOR G | GENERAL COMPLIAN | CE: | | |
| RELEASED FOR G Rev. 1 Rev. 2 | GENERAL COMPLIAN | OCE:orrection 1orrection 2 | | |





30 OF 48


20


2+00


















ADOPTED OF THIS STANDARD.








HANDICAPPED PARKING DETAIL TYP.





- 1. EXPANSION JOINTS 1/2-INCH WIDE SHALL BE LOCATED IN CURBS AND GUTTERS AT EACH SIDE OF STRUCTURES, AT THE ENDS OF ALL CURB RETURNS, AND ABUTTING HARDENED IN-PLACE CURB AND GUTTER, EXCEPT THAT EXPANSION JOINTS SHALL NOT BE INSTALLED WITHIN 20 FEET OF AN ISLAND NOSE. EXPANSION JOINTS SHALL BE 1/2-INCH THICK, SHAPED TO THE CROSS SECTION OF THE CURB AND GUTTER, AND CONSTRUCTED AT RIGHT ANGLES TO THE CURB AND GUTTER. JOINT FILLER MATERIAL SHALL CONFORM TO SSPWC SECTION 202.10. WEAKENED PLAN JOINTS SHALL BE EVERY 10 FEET AND LOCATED ON THE BACK, TOP AND FACE OF THE CURB AND THE TOP OF THE GUTTER PAN.
- 2. CURB AND GUTTER SECTIONS HALL BE PLACED SEPARATELY FROM SIDEWALK
- 3. WHEN SIDEWALK IS NOT REQUIRED, BACKFILL BEHIND THE CURB TO THE TOP FOR A HORIZONTAL DISTANCE OF 12" FROM BACK FACE OF CURB, WITH A MATCH TO EXISTING GRADE OF NOT EXCEEDING A 3:1 SLOPE.

ROLLED CURB & GUTTER





33 OF 48

SHEET NUMBER

20

 \sim


 \mathcal{C}

JOSE M. FARIAS

111389

SITE

2/24/2024



BENCHMARKS

AVD '88 USING GEOID XXX BASED ON

DATUM IS NAVD '88, USING GEOID xxx, BASED ON GPS OBSERVATIONS.

BM #100 MAG SET JUST WEST OF END OF SIDEWALK ON EASTERN SIDE OF MORRIS STREET JUST SOUTH OF TALYNE CHAISE INTERSECTION

• ELEV.=875.069'

BM #101 MAG SET JUST WEST OF SIDEWALK ON WESTERN SIDE OF MORRIS RD JUST SOUTH OF YELLOW OAK INTERSECTION

:V.=874.612'

SITE PLAN APPROVAL SHEET 34 OF 48 FILE NUMBER SP-2024-0063C APPLICATION DATE 04/15/2024 APPROVED BY COMMISSION ON_ UNDER SECTION 112 OF CHAPTER 25-5 OF THE CITY OF AUSTIN CODE. EXPIRATION DATE (25-5-81,LDC) ____CASE MANAGER CLARISSA E. DAVIS PROJECT EXPIRATION DATE (ORD.#970905-A)____DWPZ___DDZ__ Director, Development Services Department RELEASED FOR GENERAL COMPLIANCE:__ ZONINGMF-2, MF-2 CO Rev. 1 _Correction 1_ _Correction 2_ _Correction 3_ Final plat must be recorded by the Project Expiration Date, if applicable. Subsequent Site Plans which do not comply with the Code current at the time of filing, and all required Building Permits and/or a notice of construction (if a building permit is not required), must also be approved prior to the Project Expiration Date.



ALK ON HOF YELLOW
HOF YELLOW
HOW.
E you dig.

34 OF 48


20


132

JOSE M. FARIAS


DETAIL


STORM DRAIN







| DIIME | ENSIONS IN INCHES | 3" TURBINE | 3" COMPOUND | 4" TURBINE | 4" COMPOUND | 6" TURBINE | 6" COMPOUND |
|-----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|------------------|------------|----------------------|---------------------|-------------|
| No. | METER LINE | 4" BYPASS | 4" BYPASS | 4" BYPASS | 4" BYPASS | 6" BYPASS | 6" BYPASS |
| 1 | CLEARANCE FROM VALVE WALL TO TEE | 8" | 8" | 12" | 12" | 6" | 6" |
| 2 | FLANGED TEE | 13" | 13" | 13" | 13" | 16" | 16" |
| 3 | COA GATE VALVE SQUARE NUT | 9" | 9" | 9" | 9" | 10 1/2" | 10 1/2" |
| 4 | 3" X 4" FLANGED REDUCER (3" METER ONLY) | 7" | 7" | | _ | , many | _ |
| 5 | METER | 17" | 19" | 20" | 23" | 24" | 27" |
| 6 | 3" X 4" FLANGED REDUCER (3" METER ONLY) | 7" | 7" | | | | _ |
| 7+8 | ⑦FLANGED X PLAIN END DI PIPE + ⑧ RESTRAINED FLANGE COUPLING ADAPTER (RFCA) OR ⑦ FLANGE X DI PIPE + ⑧ DISMANTLING JOINT (DJ) | 17" | 15" | 20" | 17" | 19" | 16" |
| 9 | COA GATE VALVE SQUARE NUT | 9" | 9" | 9" | 9" | 10 1/2" | 10 1/2" |
| 10 | FLANGED TEE | 13" | 13" | 13" | 13" | 16" | 16" |
| 11 | CLEARANCE FROM INSIDE WALL TO TEE | 8" | 8" | 12" | 12" | 6" | 6" |
| | TOTAL (INCHES) | 108.0" | 108.0" | 108.0" | 108.0" | 108.0" | 108.0" |
| | BYPASS LINE | | | | | | |
| 1 | CLEARANCE FROM INSIDE WALL TO TEE | | 8" | 12" | 12" | 6" | 6" |
| | 1/2 TEE | 6 1/2" | 6 1/2" | 6 1/2" | 6 1/2" | 8" | 8" |
| 12 | FLANGED 90° ELBOW | | 6 1/2" | 6 1/2" | 6 1/2" | 8" | 8" |
| 13 | BYPASS GATE VALVE WITH HAND WHEEL | 9" | 9" | 9" | 9" | 10 1/2" | 10 1/2" |
| 4+15 | (4) FLANGED X PLAIN END DI PIPE + (5) RESTRAINED FLANGE COUPLING ADAPTOR (RFCA) OR (4) FLANGE 15 X FLANGE DI PIPE + (15) DISMANTLING JOINT (DJ) | | 57" | 49" | 49" | 53 1/2" | 53 1/2" |
| 16 | FLANGED 90° ELBOW | 6 1/2" | 6 1/2" | 6 1/2" | 6 1/2" | 8" | 8" |
| | 1/2 TEE | 6 1/2" | 6 1/2" | 6 1/2" | 6 1/2" | 8" | 8" |
| 11 | CLEARANCE FROM VALVE WALL TO TEE | 8" | 8" | 12" | 12" | 6" | 6" |
| | TOTAL (INCHES) | 108.0" | 108.0" | 108.0" | 108.0" | 108.0" | 108.0" |
| 17 | CLEARANCE FROM INSIDE WALL TO CENTER OF BYPASS LINE | 23" | 23" | 23" | 23" | 20" | 20" |
| TRA SIDI TO S ALL FAC | ES: TER VAULT MUST BE PLACED AT THE PROPERT EDICATED WATER METER EASEMENT. METER IFFIC INCLUDING ROADWAYS, DRIVEWAYS AND EWALKS UNLESS SPECIFICALLY APPROVED BY SERVICE VEHICLES AND SHALL NOT BE ENCLO PIPE AND FITTINGS FROM MAIN TO CUSTOMER TOORY NOTCHES WHERE PIPING GOES THROUGH-SHRINK GROUT PER SPL NO. WW-704A. | PARKIN AUSTIN | G LOTS. WATER | METER: | S MAY NO S MUST P | OT BE PL SE ACCE | ACED IN |
| | | | | | | | |












JOSE M. FARIAS 12/24/2024

ETAILS OF 2) DE UTILITY (SHEET

20 132

SHEET NUMBER 36 OF 48



CATCH

GRADE CONTROL

LAYDOWN CURB

CURB AND GUTTER SECTION

TYPICAL MULCH SOCK INSTALLATION

MULCH SOCK

 Place additional mulch material to fill seam between the sock

25 mm —

and the ground

Mulch material

Plate

Bottom Surface

PVC Pipe

Figure 6.64a Schematic of a skimmer, from Pennsylvania Erosion and Sediment Pollution Control Manual,

FRONT VIEW

PVC Tee


March, 2000.

"Holes in

Underside

END VIEW

Flexible



SHEET NUMBER 37 OF 48

20

 \sim

3

THWE

JOSE M. FARIAS

2/24/2024