

<b>ADDRESS</b> 1978 S. AUSTIN AVENUE GEORGETOWN, TX 78626	<b>PHONE</b> 512.930.9412	
	<b>FAX</b> 512.930.9416	
<b>WEB</b> STEGERBIZZELL.COM		
SERVICES > > ENGINEERS > > PLANNERS > > SURVEYORS		
TEXAS REGISTERED ENGINEERING FIRM F-181		

## Contributing Zone Plan

For

## Highland Village Phase II Commercial – Block B

In the

City of Georgetown

Williamson County, Texas

Submitted:

2/27/2025

Job Number: 22901

# **Contributing Zone Plan**

For

## **Highland Village Phase II Commercial – Block B**

In

City of Georgetown  
Williamson County, Texas

Job Number: 22901

Prepared by:



A handwritten signature in blue ink that reads "Chad W. Jones".



Texas Registered Engineering Firm-181  
1978 S. Austin Ave  
Georgetown, TX 78626



## Contributing Zone Plan Checklist

- **Edwards Aquifer Application Cover Page (TCEQ-20705)**
- **Contributing Zone Plan Application (TCEQ-10257)**
  - Attachment A - Road Map
  - Attachment B - USGS Quadrangle Map
  - Attachment C - Project Narrative
  - Attachment D - Factors Affecting Surface Water Quality
  - Attachment E - Volume and Character of Stormwater
  - Attachment F - Suitability Letter from Authorized Agent (if OSSF is proposed)
  - Attachment G - Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)
  - Attachment H - AST Containment Structure Drawings (if AST is proposed)
  - Attachment I - 20% or Less Impervious Cover Declaration (if project is multi-family residential, a school, or a small business and 20% or less impervious cover is proposed for the site)
  - Attachment J - BMPs for Upgradient Stormwater
  - Attachment K - BMPs for On-site Stormwater
  - Attachment L - BMPs for Surface Streams
  - Attachment M - Construction Plans
  - Attachment N - Inspection, Maintenance, Repair and Retrofit Plan
  - Attachment O - Pilot-Scale Field Testing Plan, if BMPs not based on Complying with the Edwards Aquifer Rules: Technical Guidance for BMPs
  - Attachment P - Measures for Minimizing Surface Stream Contamination
- **Storm Water Pollution Prevention Plan (SWPPP)**
  - OR-
- **Temporary Stormwater Section (TCEQ-0602)**
  - Attachment A - Spill Response Actions
  - Attachment B - Potential Sources of Contamination
  - Attachment C - Sequence of Major Activities
  - Attachment D - Temporary Best Management Practices and Measures
  - Attachment E - Request to Temporarily Seal a Feature, if sealing a feature
  - Attachment F - Structural Practices
  - Attachment G - Drainage Area Map
  - Attachment H - Temporary Sediment Pond(s) Plans and Calculations
  - Attachment I - Inspection and Maintenance for BMPs
  - Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices
- **Copy of Notice of Intent (NOI)**
- **Agent Authorization Form (TCEQ-0599), if application submitted by agent**
- **Application Fee Form (TCEQ-0574)**
- **Check Payable to the “Texas Commission on Environmental Quality”**
- **Core Data Form (TCEQ-10400)**

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> Highland Village Phase II Block B					<b>2. Regulated Entity No.:</b>				
<b>3. Customer Name:</b> Highland Village Georgetown, LP					<b>4. Customer No.:</b>				
<b>5. Project Type:</b> (Please circle/check one)	New		Modification		Extension		Exception		
<b>6. Plan Type:</b> (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	Residential		Non-residential			<b>8. Site (acres):</b>		8.52	
<b>9. Application Fee:</b>	\$5000		<b>10. Permanent BMP(s):</b>			Batch detention pond			
<b>11. SCS (Linear Ft.):</b>	NA		<b>12. AST/UST (No. Tanks):</b>			NA			
<b>13. County:</b>	Williamson		<b>14. Watershed:</b>			Berry Creek			

# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	<u>X</u>
Region (1 req.)	—	—	<u>X</u>
County(ies)	—	—	<u>X</u>
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Barton Springs/ Edwards Aquifer <u>—</u> Hays Trinity <u>—</u> Plum Creek	<u>—</u> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<u>—</u> Austin <u>—</u> Buda <u>—</u> Dripping Springs <u>—</u> Kyle <u>—</u> Mountain City <u>—</u> San Marcos <u>—</u> Wimberley <u>—</u> Woodcreek	<u>—</u> Austin <u>—</u> Bee Cave <u>—</u> Pflugerville <u>—</u> Rollingwood <u>—</u> Round Rock <u>—</u> Sunset Valley <u>—</u> West Lake Hills	<u>—</u> Austin <u>—</u> Cedar Park <u>—</u> Florence <u>X</u> Georgetown <u>—</u> Jerrell <u>—</u> Leander <u>—</u> Liberty Hill <u>—</u> Pflugerville <u>—</u> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Trinity-Glen Rose	<u>—</u> Edwards Aquifer Authority	<u>—</u> Kinney	<u>—</u> EAA <u>—</u> Medina	<u>—</u> EAA <u>—</u> Uvalde
City(ies) Jurisdiction	<u>—</u> Castle Hills <u>—</u> Fair Oaks Ranch <u>—</u> Helotes <u>—</u> Hill Country Village <u>—</u> Hollywood Park <u>—</u> San Antonio (SAWS) <u>—</u> Shavano Park	<u>—</u> Bulverde <u>—</u> Fair Oaks Ranch <u>—</u> Garden Ridge <u>—</u> New Braunfels <u>—</u> Schertz	NA	<u>—</u> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Chad W. Jones, P.E.

Print Name of Customer/Authorized Agent



2/10/2025

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# Contributing Zone Plan Application

## Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Highland Village Georgetown, LP/StegerBizzell, Chad Jones, P.E.

Date: 2/10/2025

Signature of Customer/Agent:



Regulated Entity Name: Highland Village Phase II Block B

## Project Information

1. County: Williamson
2. Stream Basin: Berry Creek
3. Groundwater Conservation District (if applicable): N/A
4. Customer (Applicant):

Contact Person: Joe Birdwell

Entity: Highland Village Georgetown, LP

Mailing Address: 2005 Birdcreek Drive #211

City, State: Temple, TX

Telephone: 512-917-7648

Email Address: jbirdwell@amsw.net

Zip: 76502

Fax: N/A

5. Agent/Representative (If any):

Contact Person: Chad W. Jones, P.E.

Entity: Steger Bizzell

Mailing Address: 1978 S Austin Ave

City, State: Georgetown, TX

Zip: 78626

Telephone: 512-930-9412

Fax: N/A

Email Address: chad.jones@stegerbizzell.com

6. Project Location:

- ☒ The project site is located inside the city limits of Georgetown.
- ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.
- ☐ The project site is not located within any city's limits or ETJ.

7. ☒ The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

From Austin: Traveling north on I-35, take Exit 266 toward TX-195 N. turn left onto TX-195 W, and continue for 5.5 miles. Turn left onto Rattlesnake Road, and then turn left onto Ronald Reagan Boulevard. Continue for 3.5 miles until you reach the intersection of Ronald Reagan Boulevard and CR 245. The site is at the southwest corner of the intersection.

8. ☒ **Attachment A - Road Map.** A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
9. ☒ **Attachment B - USGS Quadrangle Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:
- ☒ Project site boundaries.
  - ☒ USGS Quadrangle Name(s).
10. ☒ **Attachment C - Project Narrative.** A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:
- ☒ Area of the site
  - ☒ Offsite areas
  - ☒ Impervious cover
  - ☒ Permanent BMP(s)
  - ☒ Proposed site use
  - ☒ Site history
  - ☒ Previous development
  - ☒ Area(s) to be demolished

11. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site
- ☐ Existing paved and/or unpaved roads
- ☐ Undeveloped (Cleared)
- ☒ Undeveloped (Undisturbed/Not cleared)
- ☐ Other: \_\_\_\_\_

12. The type of project is:

- ☐ Residential: # of Lots: \_\_\_\_\_
- ☐ Residential: # of Living Unit Equivalents: \_\_\_\_\_
- ☒ Commercial
- ☐ Industrial
- ☐ Other: \_\_\_\_\_

13. Total project area (size of site): 8.52 Acres

Total disturbed area: 3.02 Acres

14. Estimated projected population: n/a

15. The amount and type of impervious cover expected after construction is complete is shown below:

**Table 1 - Impervious Cover**

<i><b>Impervious Cover of Proposed Project</b></i>	<i><b>Sq. Ft.</b></i>	<i><b>Sq. Ft./Acre</b></i>	<i><b>Acres</b></i>
Structures/Rooftops		÷ 43,560 =	
Parking		÷ 43,560 =	
Other paved surfaces		÷ 43,560 =	
Total Impervious Cover		÷ 43,560 =	

**Total Impervious Cover 0 ÷ Total Acreage 8.52 X 100 = 0% Impervious Cover**

16. ☒ **Attachment D - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.
17. ☒ Only inert materials as defined by 30 TAC 330.2 will be used as fill material.



## ***For Road Projects Only***

***Complete questions 18 - 23 if this application is exclusively for a road project.***

☒ N/A

18. Type of project:

- ☐ TXDOT road project.
- ☐ County road or roads built to county specifications.
- ☐ City thoroughfare or roads to be dedicated to a municipality.
- ☐ Street or road providing access to private driveways.

19. Type of pavement or road surface to be used:

- ☐ Concrete
- ☐ Asphaltic concrete pavement
- ☐ Other: \_\_\_\_\_

20. Right of Way (R.O.W.):

Length of R.O.W.: \_\_\_\_\_ feet.

Width of R.O.W.: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

21. Pavement Area:

Length of pavement area: \_\_\_\_\_ feet.

Width of pavement area: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

Pavement area \_\_\_\_\_ acres  $\div$  R.O.W. area \_\_\_\_\_ acres  $\times 100 = \text{_____ \%}$  impervious cover.

22. ☐ A rest stop will be included in this project.

☐ A rest stop will not be included in this project.

23. ☐ Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

## ***Stormwater to be generated by the Proposed Project***

24. ☒ **Attachment E - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

## ***Wastewater to be generated by the Proposed Project***

25. ☐ Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

☒ N/A

26. Wastewater will be disposed of by:

☐ On-Site Sewage Facility (OSSF/Septic Tank):

☐ **Attachment F - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

☐ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

☐ Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the \_\_\_\_\_ (name) Treatment Plant. The treatment facility is:

☐ Existing.

☐ Proposed.

☒ N/A

## ***Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons***

***Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.***

☒ N/A

27. Tanks and substance stored:

**Table 2 - Tanks and Substance Storage**

<b><i>AST Number</i></b>	<b><i>Size (Gallons)</i></b>	<b><i>Substance to be Stored</i></b>	<b><i>Tank Material</i></b>
1			
2			
3			

<i><b>AST Number</b></i>	<i><b>Size (Gallons)</b></i>	<i><b>Substance to be Stored</b></i>	<i><b>Tank Material</b></i>
4			
5			

**Total x 1.5 = \_\_\_\_\_ Gallons**

28. ☐ The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

☐ **Attachment G - Alternative Secondary Containment Methods.** Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

**Table 3 - Secondary Containment**

<i><b>Length (L)(Ft.)</b></i>	<i><b>Width(W)(Ft.)</b></i>	<i><b>Height (H)(Ft.)</b></i>	<i><b>L x W x H = (Ft3)</b></i>	<i><b>Gallons</b></i>

**Total: \_\_\_\_\_ Gallons**

30. Piping:

- ☐ All piping, hoses, and dispensers will be located inside the containment structure.  
☐ Some of the piping to dispensers or equipment will extend outside the containment structure.  
☐ The piping will be aboveground  
☐ The piping will be underground

31. ☐ The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of: \_\_\_\_\_.

32. ☐ **Attachment H - AST Containment Structure Drawings.** A scaled drawing of the containment structure is attached that shows the following:

- ☐ Interior dimensions (length, width, depth and wall and floor thickness).  
☐ Internal drainage to a point convenient for the collection of any spillage.  
☐ Tanks clearly labeled  
☐ Piping clearly labeled

- ☐ Dispenser clearly labeled
33. ☐ Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.
- ☐ In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.
- ☐ In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

## **Site Plan Requirements**

**Items 34 - 46 must be included on the Site Plan.**

34. ☒ The Site Plan must have a minimum scale of 1" = 400'.
- Site Plan Scale: 1" = \_\_\_\_\_'.
35. 100-year floodplain boundaries:
- ☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☒ No part of the project site is located within the 100-year floodplain.
- The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA National Flood Hazard Map, panel 48491C0275E, effective date 9/26/2008.
36. ☒ The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
- ☒ The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. ☒ A drainage plan showing all paths of drainage from the site to surface streams.
38. ☒ The drainage patterns and approximate slopes anticipated after major grading activities.
39. ☒ Areas of soil disturbance and areas which will not be disturbed.
40. ☒ Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. ☒ Locations where soil stabilization practices are expected to occur.
42. ☐ Surface waters (including wetlands).

☒ N/A

43. ☐ Locations where stormwater discharges to surface water.

☒ There will be no discharges to surface water.

44. ☐ Temporary aboveground storage tank facilities.

☒ Temporary aboveground storage tank facilities will not be located on this site.

45. ☐ Permanent aboveground storage tank facilities.

☒ Permanent aboveground storage tank facilities will not be located on this site.

46. ☒ Legal boundaries of the site are shown.

### ***Permanent Best Management Practices (BMPs)***

***Practices and measures that will be used during and after construction is completed.***

47. ☒ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.

☐ N/A

48. ☒ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.

☒ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

☐ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: \_\_\_\_\_.

☐ N/A

49. ☒ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

☐ N/A

50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to

Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

- ☐ The site will be used for low density single-family residential development and has 20% or less impervious cover.
- ☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.
- ☒ The site will not be used for low density single-family residential development.

51. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

- ☐ **Attachment I - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.

52. ☒ **Attachment J - BMPs for Upgradient Stormwater.**

- ☒ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☐ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

53. ☒ **Attachment K - BMPs for On-site Stormwater.**

- ☒ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.

54. ☐ **Attachment L - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.
- ☒ N/A
55. ☒ **Attachment M - Construction Plans.** Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.
- ☐ N/A
56. ☒ **Attachment N - Inspection, Maintenance, Repair and Retrofit Plan.** A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
- ☒ Prepared and certified by the engineer designing the permanent BMPs and measures
  - ☒ Signed by the owner or responsible party
  - ☒ Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.
  - ☒ Contains a discussion of record keeping procedures
- ☐ N/A
57. ☐ **Attachment O - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- ☒ N/A
58. ☐ **Attachment P - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
- ☒ N/A

***Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.***

59. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an

owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.

60. ☐ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### ***Administrative Information***

61. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
62. ☒ Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
63. ☐ The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
- ☒ The Temporary Stormwater Section (TCEQ-0602) is included with the application.





ROAD MAP  
ATTACHMENT A  
SCALE: 1" = 2000'




ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181 TSP'S FIRM No. 1005700
SERVICES	>>ENGINEERS >>PLANNERS >>SURVEYORS	


JOB NO. 22901

1/9/2025












UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

GEORGETOWN QUADRANGLE  
TEXAS-WILLIAMSON CO.  
7.5 MINUTE SERIES (TOPOGRAPHIC)



Produced by the United States Geological Survey  
Control by USGS and NOS/NOAA  
Compiled from aerial photographs taken 1974. Field checked 1975  
Map edited 1982  
North American Datum of 1927 (NAD 27). Projection and  
10000-foot ticks. Texas Coordinate System, central zone  
(Lambert Conformal Conic)  
Blue 1000-meter Universal Transverse Mercator ticks, zone 14  
North American Datum of 1983 (NAD 83) is shown by dashed  
corner ticks. The values of the shift between NAD 27 and NAD 83  
for 7.5-minute intersections are obtainable from National Geodetic  
Survey NADCON software.  
Red tint indicates areas in which only landmark buildings are shown  
Fine red dashed lines indicate selected fence lines  
Areas covered by dashed light-blue pattern are subject to  
controlled inundation

UTM GRID AND 1982 MAGNETIC NORTH  
DECLINATION AT CENTER OF SHEET

SCALE 1:24 000  
CONTOUR INTERVAL 10 FEET  
NATIONAL GEODETIC VERTICAL DATUM OF 1929

TEXAS  
QUADRANGLE LOCATION  
3097-313

ROAD CLASSIFICATION  
Primary highway, hard surface  
Secondary highway, hard surface  
Unimproved road  
Interstate Route  
U. S. Route  
State Route


GEORGETOWN, TX  
30097-F6-TF-024  
1982  
JOB No. 22901

180607 510041  
ISBN 0-607-51004-6



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

WEIR QUADRANGLE  
TEXAS-WILLIAMSON CO.  
7.5 MINUTE SERIES (TOPOGRAPHIC)  
NE4 ROUND ROCK 10' QUADRANGLE




Mapped, edited, and published by the Geological Survey  
Control by USGS and NOS/NOAA  
Topography by photogrammetric methods from aerial photographs  
taken 1974. Field checked 1975. Map edited 1982  
Projection and 10,000-foot grid ticks: Texas  
coordinate system, central zone (Lambert conformal conic)  
1000-meter Universal Transverse Mercator grid, zone 14  
1927 North American datum  
To place on the predicted North American Datum 1983  
move the projection lines 17 meters south and  
28 meters east as shown by dashed corner ticks  
Fine red dashed lines indicate selected fence lines

UTM GRID AND 1982 MAGNETIC NORTH  
DECLINATION AT CENTER OF SHEET

SCALE 1:24 000  
CONTOUR INTERVAL 10 FEET  
DOTTED LINES REPRESENT 5-FOOT CONTOURS  
NATIONAL GEODETIC VERTICAL DATUM OF 1929

HIGHLAND VILLAGE PHASE TWO BLOCK B  
WILLIAMSON COUNTY, TEXAS



QUADRANGLE LOCATION

3097-314

ROAD CLASSIFICATION  
Primary highway, hard surface  
Secondary highway, hard surface  
Light duty road, hard or improved surface  
Unimproved road  
Interstate Route  
U. S. Route  
State Route

WEIR, TEX.  
NE4 ROUND ROCK 10' QUADRANGLE  
N3037.5-W97307.5  
1982  
JOB No. 22901



### **Attachment C – Project Narrative**

This project consists of the partial development of a commercial tract known as Highland Village Phase II Commercial – Block B. The site is an 8.52-acre tract in the Lewis P. Dyches Survey, Abstract No. 171. The site is in Georgetown, Texas and bound on the west by a section of Veneta Ln. and a row of residential lots, on the south by a residential neighborhood, on the east by CR 245, and on the north by Ronald Reagan Blvd. The site limits of construction is 3.02 acres. The site is undeveloped former agricultural land and no demolition activities will be required as a part of the project.

The project scope addressed in this CZP application includes grading and drainage improvements within a drainage lot that will serve future commercial development on the site. The actual full commercial development will be addressed in the future phases with separate CZP applications; the current scope includes only the water quality and batch detention pond that will serve the future development. Temporary and permanent BMPs are shown in this application.

Removal of suspended solids and pollutants will be performed by a water quality and batch detention Pond to achieve an eighty-five percent removal. The site generally drains from northwest to southeast and into Berry Creek.

The site area is 8.52 acres. The total drainage area contributing to the on-site pond is 9.95 acres, which includes a small portion of the developed residential neighborhood surrounding the site from the west. A total of 5.96 acres of impervious cover will be treated with the detention pond.

There are no sensitive features located within the overall 8.52 acre project boundary.

### **Attachment D – Factors Affecting Surface Water Quality**

The following factors are anticipated to adversely affect surface water and groundwater quality:

- Disturbance of vegetated areas.
- Leaking oil from parked vehicles.
- Malfunctioning wastewater collection system and spill on site.
- Loss of vegetative ground cover due to inadequate watering or mismanagement.
- Over fertilizing vegetative areas.
- The use of roads by automotive traffic and subsequent oil/grease pollutants from normal use.
- The accidental or improper discharge of the following:
  - a) Concrete
  - b) Cleaning solvents
  - c) Detergents
  - d) Petroleum based products
  - e) Paints
  - f) Paint solvents
  - g) Acids
  - h) Concrete additives

### **Attachment E – Volume and Character of Storm Water**

In the existing condition the site is underdeveloped and considered pasture in fair condition. There is no existing impervious cover on-site.

The proposed storm water capture will be typical of what is normally observed for a local commercial development. Runoff from the development will flow directly into a proposed batch development pond and may be routed to pond inlets from storm drains on site. Pervious cover in the development state will be a combination of mowed pastureland and irrigated lawns in good condition. Impervious cover will consist of buildings, roadway, parking areas, and pavement. The existing and proposed drainage plans, contained within the construction plans for the project, contain detailed data regarding storm water runoff expected in the existing and proposed conditions.

The developed peak flows leaving Highland Village Phase II for the 2, 10, 25, and 100-year storms will be less than or equal to those of the pre-developed existing conditions as shown in the attached Existing and Proposed Drainage Plans within the construction plans for the project.



**Attachment F – Suitability Letter from Authorized Agent (if OSSF is proposed)**

Not applicable.

**Attachment G - Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)**

There are no ASTs proposed for the site.

**Attachment H - AST Containment Structure Drawings (if AST is proposed)**

There are no ASTs proposed for the site.

**Attachment I - 20% or Less Impervious Cover Declaration (if project is multi-family residential, a school, or a small business and 20% or less impervious cover is proposed for the site)**

Not applicable.

**Attachment J - BMPs for Upgradient Stormwater**

Not applicable.

## **Attachment K - BMPs for On-site Stormwater**

Batch detention, as described in the Addendum to TCEQ's "Complying with the Edwards Rules: Technical Guidance Manual on Best Management Practices" Section 3.2.17 (RG-348), will be used as the BMP for this development. A batch detention basin has a TSS removal efficiency of 91% according to the above referenced manual. For 85% TSS removal, 5191 pounds of solids must be removed from the site to treat the project site. The total capture volume is the required water quality volume increased by 20%. The total capture volume required for 85% TSS removal is 28,424 cubic feet. A total capture volume of 31,039 cubic feet is provided by the proposed batch detention basin. The capture volume collected by the batch detention basin will be held for the required 48-hour detention time, and a programmed controller will send a signal to an actuator to open the output valve and release the treated runoff.

After the required capture volume is collected, a weir within the batch detention basin will divert additional runoff to a concrete spillway, sending the water to the existing runoff infrastructure.

Batch Detention Pond: The pond is sized for the total buildout of Highland Village Phase II. There are approximately 8.52 acres draining to the pond, of which, 5.96 are impervious cover.

Calculations to determine the pollutant load and sizing for each BMP are attached directly behind this sheet.

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: **Highland Village II Commercial Lot 1, Block B**  
Date Prepared: **2/10/2025**

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

**1. The Required Load Reduction for the total project:**

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3:  $L_M = 27.2(A_N \times P)$

where:

$L_{M \text{ TOTAL PROJECT}}$  = Required TSS removal resulting from the proposed development = 85% of increased load

$A_N$  = Net increase in impervious area for the project

P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Williamson**

Total project area included in plan = **8.52** acres

Predevelopment impervious area within the limits of the plan = **0.00** acres

Total post-development impervious area within the limits of the plan = **5.96** acres

Total post-development impervious cover fraction = **0.70**

P = **32** inches

$L_{M \text{ TOTAL PROJECT}}$  = **5191** lbs.

\* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

**2. Drainage Basin Parameters (This information should be provided for each basin):**

Drainage Basin/Outfall Area No. = **1**

Total drainage basin/outfall area = **8.52** acres

Predevelopment impervious area within drainage basin/outfall area = **0.00** acres

Post-development impervious area within drainage basin/outfall area = **5.96** acres

Post-development impervious fraction within drainage basin/outfall area = **0.70**

$L_{M \text{ THIS BASIN}}$  = **5191** lbs.

**3. Indicate the proposed BMP Code for this basin.**

Proposed BMP = **Batch Detention Basin**

Removal efficiency = **91** percent

Aqualogic Cartridge Filter  
Bioretention  
Batch Detention Basin  
BaySeparator  
Contech StormFilter  
Constructed Wetland  
Extended Detention  
Grassy Swale  
Retention / Irrigation  
Sand Filter  
Stormceptor  
Vegetated Filter Strips  
Vortechs  
Wet Basin  
Wet Vault

**4. Calculate Maximum TSS Load Removed ( $L_R$ ) for this Drainage Basin by the selected BMP Type.**

RG-348 Page 3-33 Equation 3.7:  $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where:

$A_C$  = Total On-Site drainage area in the BMP catchment area

$A_i$  = Impervious area proposed in the BMP catchment area

$A_p$  = Pervious area remaining in the BMP catchment area

$L_R$  = TSS Load removed from this catchment area by the proposed BMP

$A_C$  = **8.52** acres

$A_i$  = **5.96** acres

$A_p$  = **2.56** acres

$L_R$  = **6049** lbs

**5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area**

Desired  $L_{M \text{ THIS BASIN}}$  = **5191** lbs.

F = **0.86**

**6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.**

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = **1.38** inches  
Post Development Runoff Coefficient = **0.51**  
On-site Water Quality Volume = **21582** cubic feet

Calculations from RG-348

Pages 3-36 to 3-37

Off-site area draining to BMP = **1.02** acres  
Off-site Impervious cover draining to BMP = **0.60** acres  
Impervious fraction of off-site area = **0.59**  
Off-site Runoff Coefficient = **0.41**  
Off-site Water Quality Volume = **2105** cubic feet

Storage for Sediment = **4737**

Total Capture Volume (required water quality volume(s) x 1.20) = **28424** cubic feet

PROPOSED POND B VOLUME SUMMARY						
ELEVATION (Ft.)	AREA (Sq. Ft.)	AVERAGE AREA (Sq. Ft.)	INC. ELEV. (Ft.)	INC. VOLUME (Cu.-Ft.)	TOTAL VOL. (Cu. Ft.)	TOTAL VOL. (Ac.- Ft.)
910	25				0	0.0000
		2060	1	2060		
911	4095				2060	0.0473
		10094	1	10094		
912	16093				12154	0.2790
		18884.5	1	18884.5		
913	21676				31039	0.7125
		24687	1	24687		
914	27698				55726	1.2793
		30814	1	30814		
915	33930				86540	1.9867
		35579.5	1	35579.5		
916	37229				122119	2.8035
		38064.5	0.5	19032.25		
916.5	38900				141151	3.2404



**Attachment L - BMPs for Surface Streams**

Not applicable.

**Attachment M - Construction Plans**

Please refer to the Highland Village Phase Two Block B construction plans included with this CZP submittal.



These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.

PROJECT NAME: HIGHLAND VILLAGE PHASE II - COMMERCIAL - LOT 1, BLOCK B

SITE ADDRESS: 901 CR 245, GEORGETOWN, TX 78633

SUBDIVISION NAME: HIGHLAND VILLAGE, PHASE 2, COMMERCIAL

LEGAL DESCRIPTION: S13344 - HIGHLAND VILLAGE COMMERCIAL PH 2, BLOCK B, Lot 1, ACRES 8.52

DOCUMENT NUMBER: 2023076261

RECORDING DATE: SEPTEMBER 12, 2023

ZONING DISTRICT: PLANNED UNIT DEVELOPMENT - PUD ORDINANCE NO. 2018-18

OWNER: HIGHLAND VILLAGE GEORGETOWN, GP LLC  
2005 BIRDCREEK DRIVE, SUITE 211  
TEMPLE, TX 76502  
VERNON W. BARGE, III  
254-771-1157  
jbirdwell@amsw.net

APPLICANT/AGENT: CHAD W. JONES, P.E.  
STEGER & BIZZELL ENGINEERING, INC.  
TEXAS REGISTERED ENGINEERING FIRM F-181  
1978 SOUTH AUSTIN AVE.  
GEORGETOWN, TX 78626  
(512) 930-9412  
chad.jones@stegerbizzell.com  
https://stegerbizzell.com

ENGINEER/SURVEYOR: STEGER & BIZZELL ENGINEERING, INC.  
TBPELS FIRM NO. 10003700  
1978 S. AUSTIN AVE.  
GEORGETOWN, TX 78626  
(512) 930-9412  
https://stegerbizzell.com

ORIGINAL DATE: OCTOBER 6, 2023

LATEST REVISION DATE: FEBRUARY 10, 2025

LIMITS OF CONSTRUCTION: 3.02 ACRES

DRAINAGE FACILITY: STORMWATER WILL BE DIRECTED THROUGH AN ON-SITE WATER QUALITY FACILITY

UTILITIES: WATER - CITY OF GEORGETOWN, 512-930-3555, https://gus.georgetown.org  
300-1 INDUSTRIAL AVE., GEORGETOWN, TEXAS 78626  
WASTEWATER - CITY OF GEORGETOWN, 512-930-3555, https://gus.georgetown.org  
300-1 INDUSTRIAL AVE., GEORGETOWN, TEXAS 78626  
ELECTRIC - PEDERNALES ELECTRIC COOPERATIVE, 877-372-0391, https://www.pec.coop  
P.O. BOX 1, JOHNSON CITY, TEXAS 78636

ASSUMED TOTAL FUTURE IMPERVIOUS COVER: 5.96 ACRES/259,618 SQ.FT. (BASED ON 70% MAXIMUM ALLOWABLE IMPERVIOUS COVER)

TOTAL PROPOSED IMPERVIOUS COVER: 0.0056 ACRES/242 SQ.FT.

PROPOSED USE: GENERAL COMMERCIAL

- General Notes:
- It is the responsibility of the property owner, and successors to the current property owner, to ensure the subject property and any improvements are maintained in conformance with this Site Development Plan.
  - This development shall comply with all standards of the Unified Development Code (UDC), the City of Georgetown Construction Standards and Specifications Manual, the Development Manual and all other applicable City standards.
  - This Site Development Plan shall meet the UDC Stormwater requirements.
  - All signage requires a separate application and approval from the Inspection Services Department. No signage is approved with the Site Development Plan.
  - Sidewalks shall be provided in accordance with the UDC. [See included Summary Letter and additional note below.]
  - Driveways will require approval by the Development Engineer of the City of Georgetown.
  - Outdoor lighting shall comply with Section 7.04 of the UDC.
  - Screening of mechanical equipment, dumpsters and parking shall comply with Chapter 8 of the UDC. The screening is shown on the Landscape and Architectural Plans, as applicable.
  - The companion Landscape Plan has been designed and plant materials shall be installed to meet all requirements of the UDC.
  - All maintenance of required landscape shall comply with the maintenance standards of Chapter 8 of the UDC.
  - A separate Irrigation Plan shall be required at the time of building permit application.
  - Fire flow requirements of 0 gal per minute are being met by this plan. [See included Summary Letter and additional note below.]
  - Any Heritage Tree noted on this Site Development Plan is subject, in perpetuity, to the maintenance, care, pruning and removal requirements of the Unified Development Code.
  - The construction portion of these plans were prepared, sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the construction plans for construction of the proposed project are hereby approved subject to the Standard Construction Specifications and Details Manual and all other applicable City, State and Federal Requirements and Codes.
  - This project is subject to all City Standard Construction Specifications and Details in effect at the time of submittal of the project to the City.
  - Where no existing overhead infrastructure exists, underground electric utility lines shall be located along the street and within the site. Where existing overhead infrastructure is to be relocated, it shall be re-installed underground and the existing facilities shall be removed at the discretion of the Development Engineer.
  - All electric and communication infrastructure shall comply with UDC Section 13.06.

NOTE: THESE PLANS PRESENT THE DESIGN OF A WATER QUALITY AND BATCH DETENTION POND THAT WILL ACCOMMODATE THE REQUIRED RUNOFF THAT THIS SITE WILL PRODUCE AFTER IT HAS BEEN FULLY DEVELOPED. THESE PLANS DO NOT INCLUDE ANY OTHER DEVELOPMENT FEATURE ON THE SITE, AND ALL STRUCTURES, PAVEMENTS, SIDEWALKS, AND UTILITIES NOT ASSOCIATED WITH THE POND WILL NEED TO BE ADDRESSED IN A FUTURE SITE DEVELOPMENT PLAN. IN ORDER FOR THE POND TO FUNCTION AS DESIGNED, THE FINAL SITE DEVELOPMENT DESIGN WILL NEED TO INCLUDE SITE GRADING WHICH WILL DIRECT ALL SITE RUNOFF THROUGH THE WATER QUALITY AND BATCH DETENTION POND.

# SITE DEVELOPMENT PLANS FOR HIGHLAND VILLAGE PHASE II - COMMERCIAL LOT 1, BLOCK B CITY OF GEORGETOWN WILLIAMSON COUNTY, TEXAS



Location Map  
1" = 1000'

Submitted By:

CHAD W. JONES, P.E.

Date



NOTE:  
CONTRACTOR IS TO FURNISH A SET OF CONSTRUCTION PLANS BACK TO THE ENGINEER AT THE END OF THE PROJECT WITH ALL DEVIATIONS NOTED IN RED INK ON THE PLAN SHEETS. CONTRACTOR SHALL NOT RECEIVE FINAL PAYMENT UNTIL COMPLETE "AS-BUILT" SET IS RETURNED TO ENGINEER.

Sheet List Table	
Sheet Number	Sheet Title
01	COVER SHEET
02	GENERAL NOTES
03	FINAL PLAT (1 OF 4)
04	FINAL PLAT (2 OF 4)
05	FINAL PLAT (3 OF 4)
06	FINAL PLAT (4 OF 4)
07	EXISTING TOPOGRAPHIC SURVEY AND DRAINAGE MAP
08	PROPOSED DRAINAGE AREA MAP
09	TCEQ WATER QUALITY CALCULATIONS
10	DIMENSION SITE AND GRADING PLAN
11	DETENTION & WQ POND SECTIONS & DETAILS
12	UTILITY PLAN
13	EROSION CONTROL PLAN
14	DETAILS
LP-N1	PLANTING NOTES
LP-1	PLANTING PLAN

HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B TREE LIST				
REMOVAL	TREE#	SIZE (IN)	TYPE	NOTES
	1538	13	LIVE OAK	
	1539	16	LIVE OAK	MULTI
	1540	15	LIVE OAK	MULTI
	1541	14	LIVE OAK	MULTI
	1542	17	LIVE OAK	MULTI
	1543	12	LIVE OAK	MULTI
	1544	13	LIVE OAK	MULTI
X	1545	13	LIVE OAK	MULTI
X	1546	16	LIVE OAK	MULTI
	1547	12	LIVE OAK	
	1548	12	LIVE OAK	
	1549	12	LIVE OAK	
	1550	15	LIVE OAK	MULTI
	1551	14	ELM	
	1552	13	LIVE OAK	
	1553	12	LIVE OAK	MULTI
	1554	13	LIVE OAK	MULTI
	1555	15	LIVE OAK	MULTI
	1556	15	LIVE OAK	MULTI
	1557	13	LIVE OAK	MULTI
	1558	15	LIVE OAK	MULTI
	1559	17	LIVE OAK	MULTI
	1560	14	ELM	MULTI
	1561	13	ELM	MULTI
	1562	13	ELM	MULTI
	1563	16	LIVE OAK	
	1564	21	LIVE OAK	
	1565	14	LIVE OAK	
	1566	15	LIVE OAK	
	1567	12	LIVE OAK	MULTI
	1568	17	ELM	MULTI
	1569	13	LIVE OAK	MULTI
	1570	14	LIVE OAK	MULTI
	1571	13	LIVE OAK	MULTI
	1572	13	ELM	
	1573	17	LIVE OAK	MULTI
	1574	12	LIVE OAK	
	1575	12	LIVE OAK	
	1576	17	LIVE OAK	MULTI
	1577	18	LIVE OAK	MULTI
	1578	15	LIVE OAK	MULTI
	1579	12	LIVE OAK	
	1580	12	LIVE OAK	

NOTES:

- All bearings and coordinates are referenced to the Texas Coordinate System, Central Zone. NAD 83 horizontal control datum and NAVD 88 vertical control datum. Coordinates are based on a three temporary control points (see E&S Control Plan, Sheet 13, for locations):  
Point 1: N=10240741.0000, E=3100639.9410, EL=928.03'  
Point 2: N=10239214.0100, E=3098312.5270, EL=913.42'  
Point 3: N=10239699.3200, E=3097217.5790, EL=928.33'
- Distances shown in these plans are surface and may be converted to grid by multiplying by the combined scale factor of 0.9998500225.

<div>WARNING! There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.</div>	NO.	REVISION	BY	DATE	CWJ DESIGNED BY: 2/27/25 DATE
					CWJ, NIE DRAWN BY: 2/27/25 DATE
					CWJ CHECKED BY: DATE
					CWJ APPROVED BY: DATE

STEGER & BIZZELL	
ADDRESS 1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO 512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181
SERVICES TBPELS FIRM No. 10003700	WEB STEGERBIZZELL.COM
->>ENGINEERS >>PLANNERS >>SURVEYORS	

COVER SHEET  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901

SHEET  
01  
of 14



These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.

GENERAL CONSTRUCTION NOTES

- All construction shall be in accordance with the latest City of Georgetown Technical Specifications and Details.
- Prior to beginning construction, the Owner or his authorized representative shall convene a Pre-Construction Conference between the City of Georgetown, Engineer, Contractor, County Engineer (if applicable), Texas Commission on Environmental Quality Field Office, and any other affected parties. Notify all such parties at least 48 hours prior to the time of the conference and 48 hours prior to beginning construction. Written construction notification must be given to the appropriate TCEQ regional office no later than 48 hours prior to commencement of the regulated activity. Information must include the date on which the regulated activity will commence, the name of the approved plan for the regulated activity, the name of the prime contractor and the name and telephone number of the contact person.
- The Contractor shall give the City a minimum of 48 hours notice before beginning each phase of construction, call 512-930-3555.
- No blasting will be permitted on this project.
- Any existing utilities, pavement, curbs, and/or sidewalks damaged or removed will be repaired by the Contractor at his expense before acceptance of the project.
- The location of any existing water and/or wastewater lines shown on the plans must be verified by the Georgetown Utility Systems Department.
- Manhole frames, covers, water valve covers, etc., shall be raised to finished pavement grade at the Contractor's expense by a qualified contractor with City inspection. All utility adjustments shall be completed prior to final paving construction.
- The Contractor is responsible for any damages to any public improvements.
- Replace all destructured CMP culverts with CMP of equal size.

SEQUENCE OF CONSTRUCTION

Note: Other contractors could be working on this site. Coordinate all activities with the activities of others.

- Call all affected parties at least 48 hours prior to beginning any construction to schedule a pre-construction conference and secure all required permits.
- Install temporary erosion controls prior to any clearing and grubbing. Notify the City of Georgetown when installed.
- Clear and grub site.
- Install all utility mains & services.
- Ensure that all underground utility installations are complete.
- Complete final site grading and revegetation.
- Remove and dispose of temporary erosion controls.
- Complete any necessary final dress-up.

PERMANENT EROSION CONTROL NOTES

- All disturbed areas shall be restored as noted below:
  - A minimum of six inches of imported sandy loam topsoil or approved equal shall be placed in all drainage channels (except rock) and on all cleared areas.
  - The seeding for permanent erosion control shall be applied over areas disturbed by construction as follows, unless specified elsewhere:
    - From September 15 to March 1, seeding shall be with a combination of 1 pound per 1,000 square feet of unhulled Bermuda and 7 pounds per 1,000 square feet of Winter Rye with a purity of 95% with 90% germination.
    - From March 2 to September 14, seeding shall be with hulled Bermuda at a rate of 3 pounds per 1,000 square feet with a purity of 95% with 85% germination.
  - Fertilizer shall be slow release granular or pelleted type and shall have an analysis of 15-15-15 and shall be applied at the rate of 23 pounds per acre once at the time of planting and again once during the time of establishment.
  - The planted area shall be irrigated or sprinkled in a manner that will not erode the top soil, but will sufficiently soak the soil to a depth of six inches. The irrigation shall occur at ten-day intervals during the first two months. Rainfall occurrences of 1/2 inch or more shall postpone the watering schedule for one week.
- Mulch type used shall be Mulch, applied at a rate of 1,500 pounds per acre.

TEMPORARY EROSION CONTROL NOTES

- The Contractor shall install erosion/sedimentation controls and tree protective fencing prior to any site preparation work (clearing, grubbing or excavation).
- The placement of erosion/sedimentation controls shall be in accordance with the PLANS.
- Any significant variation in materials or locations of controls or fences from those shown on the approved plans must be approved by the City Engineer.
- The Contractor is required to inspect all controls and fences at weekly intervals and after significant rainfall events to insure that they are functioning properly. The person(s) responsible for maintenance of controls and fences shall immediately make any necessary repairs to damaged areas. Silt accumulation at controls must be removed when the depth reaches six (6) inches.
- Prior to final acceptance, haul roads and waterway crossings constructed for temporary Contractor access must be removed, accumulated sediment removed from the waterway, and the area restored to the original grade and revegetated. All land clearing debris shall be disposed of in approved spoil disposal sites.
- Field revisions to the EROSION & SEDIMENTATION CONTROL PLANS may be required by the Engineer or field inspector with the Texas Commission on Environmental Quality (TCEQ) during the course of construction to correct control inadequacies. Major revisions must be approved by the TCEQ.

CITY OF GEORGETOWN GENERAL NOTES

- These construction plans were prepared, sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the construction plans for construction of the proposed project are hereby approved subject to the standard Construction Specifications and Details Manual and all other applicable City, State and Federal Requirements and Codes.
- This project is subject to all City Standard Specifications and Details in effect at the time of submittal of the project to the City.
- The site construction plans shall meet all requirements of the approved site plan.
- Wastewater mains and service lines shall be SDR 26 PVC.
- Wastewater mains shall be installed without horizontal or vertical bends.
- Maximum distance between wastewater manholes is 500 feet.
- Wastewater mains shall be low pressure air tested and mandrel tested by the contractor according to the City of Georgetown and TCEQ requirements.
- Wastewater manholes shall be vacuum tested and coated by the contractor according to City of Georgetown and TCEQ requirements.
- Wastewater mains shall be camera tested by the contractor and submitted to the City on DVD format prior to paving the streets.
- Private water system fire lines shall be tested by the contractor to 200 psi for 2 hours.
- Private water system fire lines shall be ductile iron piping from the water main to the building sprinkler system, and 200 psi C900 PVC for all others.
- Public water system mains shall be 150 psi C900 PVC and tested by the contractor at 200 psi for 15 minutes and 150 psi for 2 hours.
- All bends and changes in direction on water mains shall be restrained and thrust blocked.
- Long fire hydrant leads shall be restrained.
- All water lines are to be bacteria tested by the contractor according to the City standards and specifications.
- Water and Sewer main crossings shall meet all requirements of the TCEQ and the City.
- Flexible base material for public streets shall be TXDOT Type A Grade 1.
- Hot mix asphaltic concrete pavement shall be Type D unless otherwise specified and shall be a minimum of 2 inches thick on public streets and roadways.
- All sidewalk ramps are to be installed with the public infrastructure.
- A maintenance bond is required to be submitted to the City prior to acceptance of the public improvements. This bond shall be established for 2 years in the amount of 10% of the cost of the public improvements and shall follow the City format.
- Record drawings of public improvements shall be submitted to the City by the design engineer prior to acceptance of the project. These drawings shall be a pdf emailed to the City Development engineer.

CITY OF GEORGETOWN HERITAGE TREE PROTECTION DURING CONSTRUCTION

- Prior to the commencement of any development, a tree protection fence constructed of approved materials shall encompass the Critical Root Zone (CRZ) of any Heritage Tree. Said tree protection fence must be maintained throughout the construction process, and must also comply with Chapter 11 of this Code.
- During construction, no materials including but not limited to excess soil, vehicles, equipment, liquids, trash, or construction debris may be placed inside of the tree protection fence, nor shall the tree protection fence be altered in any way so as to increase the encroachment of the construction.
- Excavation, grading, soil deposit, impervious covering, drainage and leveling within the CRZ of Heritage Trees is prohibited unless approved by the Urban Forester. Any impervious cover proposed within the CRZ of a Heritage Tree will be reviewed on a case by case basis by the Urban Forester upon field inspections and or plan reviews. In any case, generally no more than 50% of the CRZ of any Heritage Tree can be covered with impervious cover. Any protective fencing being used around Heritage Trees may only be reduced while impervious cover activity is being done. The remainder of the protective fencing must stay intact for the duration of the project.
- Disposal or depositing of oil, gasoline, chemicals, paints, solvents or other materials is prohibited within the CRZ of Heritage Trees.
- The attachment of wires, signs and ropes to any Heritage Tree is prohibited.
- The location of utility service and irrigation lines inside the CRZ of Heritage Trees is only allowed when approved by the Urban Forester. If boring is used to provide underground utility access, the minimum length of the bore shall be the width of the tree's mature canopy. The minimum depth of the bore shall be specified by the Urban Forester, but in no event be less than 24" below the natural grade existing prior to any development activity within the CRZ..
- Soil disturbance or other injurious and detrimental activity within the CRZ of Heritage Trees is prohibited.
- At applicant's expense, an ISA Certified Arborist or their employee(s) shall be present whenever activities occur which will pose a potential threat to the health of the Heritage Tree such as pruning, or whenever any work needs to be done within the CRZ of such tree.
- Should the area within the CRZ become compacted during excavation or grading, the affected area shall be aerated. The Urban Forester shall be notified whenever any Damage or injury occurs to a Heritage Tree during construction so that proper treatment may be administered.
- The Urban Forester shall be notified whenever any Damage or injury occurs to a Heritage Tree during construction so that proper treatment may be administered.
- Contact the City of Georgetown's Urban Forester (512-930-6113) when tree protection is installed and prior to any fencing being removed.

ACCESSIBILITY NOTES

- Project shall be constructed in full compliance with the Texas Accessibility Standards (TAS) 2012.
- Slopes in the direction of pedestrian travel shall not exceed 5% (1:20) or have a cross slope greater than 2% (1:48). This shall include routes that cross-vehicular ways including but not limited pedestrian/ vehicular ways such as street intersections.
  - Exception: Per TAS 405.8 and 68.102 (1) grades at the new sidewalks parallel to the streets shall be equal to, or less than, the street grade. Should the new sidewalks exceed the street grade, and the new sidewalk grades exceed 5% in the direction of travel, ramps complying with TAS 405 are required at these conditions.
- Curb Ramps:
  - Curb ramps shall not exceed 8.3% (1:12) in the direction of pedestrian travel.
  - Curb ramps flares (wings) shall not exceed 1:10.
  - Minimum width of a curb ramp is 36".
  - Top of the curb ramp must be 2% in all directions for an area 36" wide and 48" deep.
  - When truncated domes are used, the truncated dome system shall extend the full width of the curb ramp and for a minimum depth of 24" at the bottom of the curb ramp.
  - Returned curb ramps shall only be used where the adjacent surface on one or both sides of the curb ramp do not allow pedestrian travel such as but not limited to stop lights, stop signs and permanently mounted waste receptacles.
- There shall be no changes in level greater than ¼" on any accessible route or ½" with a 1:2 bevel.
- Decomposed granite surfaces, or similar Engineer-approved surfaces shall be compacted tight and maintained by the Owner at all times.
- Provide directional signage using the international symbol of accessibility when not all routes are accessible. Signage shall be placed at the beginning of the route to avoid a patron from proceeding on a non-accessible route.
- Verify that no plantings or other site elements on circulation paths would be protruding objects based on TAS 307 ( protrudes more 4" and is higher than 27" from the surface and less than 80" from the surface).

Contractor shall notify the Engineer before proceeding with any Work, which is in conflict with the Texas Accessibility Standards. Contractor is financially responsible for proceeding with any Work without written direction on any clarification from the Engineer.

**WARNING!**

There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ	DESIGNED BY:	2/27/25
CWJ, NIE	DATE	2/27/25
CWJ	DRAWN BY:	DATE
CWJ	CHECKED BY:	DATE
CWJ	DATE	DATE
CWJ	APPROVED BY:	DATE



ADDRESS		1978 S. AUSTIN AVENUE		GEORGETOWN, TX 78626	
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181	WEB STEGERBIZZELL.COM		
SERVICES	>>ENGINEERS		>>PLANNERS		>>SURVEYORS



GENERAL NOTES  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901  
  
**SHEET**  
**02**  
of 14









**WARNING!**

There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE
			CWJ DESIGNED BY:
			2/27/25 DATE
			CWJ, NIE DRAWN BY:
			2/27/25 DATE
			CWJ CHECKED BY:
			DATE
			CWJ APPROVED BY:
			DATE



STEGER  BIZZELL

ADDRESS		1978 S. AUSTIN AVENUE		GEORGETOWN, TX 78626	
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181 TBPELS FIRM No.10003700			WEB STEGERBIZZELL.COM
SERVICES		>>ENGINEERS	>>PLANNERS	>>SURVEYORS	

FINAL PLAT (2 OF 4)  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS







WARNING!

There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ	DESIGNED BY:	2/27/25
CWJ	DRAWN BY:	2/27/25
CWJ	CHECKED BY:	DATE
CWJ	APPROVED BY:	DATE



STEGERBIZZELL

ADDRESS1978 S. AUSTIN AVENUEGEORGETOWN, TX 78626METRO512.930.9412TEXAS REGISTERED ENGINEERING FIRM F-181TBPELS FIRM No. 10003700WEBSTEGERBIZZELL.COMSERVICES>>ENGINEERS>>PLANNERS>>SURVEYORS

FINAL PLAT (4 OF 4)  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901

SHEET  
06  
of 14

STATE OF TEXAS  
COUNTY OF WILLIAMSON  
HIGHLAND VILLAGE GEORGETOWN GP, LLC, ACTING BY AND THROUGH ITS VICE PRESIDENT, JOE A. BROWELL, SOLE MEMBER, HAS CAUSED JOE A. BROWELL TO EXECUTE AND SIGN THIS INSTRUMENT, KNOWING THE CONTENTS AND EFFECTS THEREOF, AND A CALL TO JOE A. BROWELL, LOCATED IN THE LEWIS DITCH SURVEY, ABSTRACT NO. 171, IN THE CITY OF GEORGETOWN AND WILLIAMSON COUNTY, TEXAS SHOWN HEREON AND DESCRIBED IN A DEED RECORDED IN DOCUMENT NO. 2023076261, DATED 09/15/2023, AND THE INSTRUMENT BEING A TRUE AND CORRECT COPY OF THE INSTRUMENT AS RECORDED IN THE PUBLIC RECORDS OF THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS, DO HEREBY CERTIFY THAT THIS SUBDIVISION IS IN ACCORDANCE WITH THE EDDWARDS ACQUIFER RECHARGE AND CONTRIBUTING ZONE, AND IS ENCOMPASSED BY A ZONE A FLOOD AREA, AS SHOWN ON THE FLOOD MAP OF WILLIAMSON COUNTY, TEXAS, DATED SEPTEMBER 25, 2008, AND THAT EACH LOT CONFORMS TO THE CITY OF GEORGETOWN REGULATIONS, THE FULLY DEVELOPED, CONCENTRATED STORMWATER RUNOFF RESULTING FROM THE ONE (1) ACRE OF DEVELOPED LAND SHOWN HEREON IS CONTAINED WITHIN THE DRAINAGE EASEMENTS SHOWN AND/OR PUBLIC RIGHTS-OF-WAY DEDICATED BY THIS PLAT.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT GEORGETOWN, WILLIAMSON COUNTY, TEXAS, THIS 5<sup>th</sup> DAY OF September, 2023.

JOE A. BROWELL, VICE PRESIDENT  
2005 WIMCOOKE DRIVE  
SUITE 211  
TEMPLE, TEXAS 76702

STATE OF TEXAS  
COUNTY OF WILLIAMSON  
§ KNOW ALL MEN BY THESE PRESENTS  
BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE, ON THIS 5<sup>th</sup> DAY OF September, 2023, A.D., DID PERSONALLY APPEAR JOE A. BROWELL, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 5<sup>th</sup> DAY OF September, 2023.



NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS  
MY COMMISSION EXPIRES ON: 11/22/2025

STATE OF TEXAS  
COUNTY OF WILLIAMSON  
§ KNOW ALL MEN BY THESE PRESENTS

L. BRYAN E. MOORE, REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS SUBDIVISION IS IN ACCORDANCE WITH THE EDDWARDS ACQUIFER RECHARGE AND CONTRIBUTING ZONE, AND IS ENCOMPASSED BY A ZONE A FLOOD AREA, AS SHOWN ON THE FLOOD MAP OF WILLIAMSON COUNTY, TEXAS, DATED SEPTEMBER 25, 2008, AND THAT EACH LOT CONFORMS TO THE CITY OF GEORGETOWN REGULATIONS, THE FULLY DEVELOPED, CONCENTRATED STORMWATER RUNOFF RESULTING FROM THE ONE (1) ACRE OF DEVELOPED LAND SHOWN HEREON IS CONTAINED WITHIN THE DRAINAGE EASEMENTS SHOWN AND/OR PUBLIC RIGHTS-OF-WAY DEDICATED BY THIS PLAT.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT GEORGETOWN, WILLIAMSON COUNTY, TEXAS, THIS 5<sup>th</sup> DAY OF September, 2023.




BRYAN E. MOORE  
REGISTERED PROFESSIONAL ENGINEER  
STATE OF TEXAS NO. 98920

STATE OF TEXAS  
COUNTY OF WILLIAMSON  
§ KNOW ALL MEN BY THESE PRESENTS

L. PATRICK STEVENS, REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECTLY MADE FROM AN ACTUAL SURVEY MADE ON THE GROUND OF THE PROPERTY LEGALLY DESCRIBED HEREON, AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPERLY PLACED UNDER MY SUPERVISION IN ACCORDANCE WITH THE SUBDIVISION REGULATIONS OF THE CITY OF GEORGETOWN, TEXAS, AND THAT THE PLAT IS A TRUE AND CORRECT COPY OF THE INSTRUMENT AS RECORDED IN THE PUBLIC RECORDS OF THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT GEORGETOWN, WILLIAMSON COUNTY, TEXAS, THIS 5<sup>th</sup> DAY OF September, 2023.



PATRICK STEVENS  
REGISTERED PROFESSIONAL LAND SURVEYOR  
STATE OF TEXAS NO. 98920  
TEMPLE, TEXAS 76702

BASED UPON THE ABOVE REPRESENTATIONS OF THE ENGINEER OR SURVEYOR WHOSE SEAL IS AFFIXED HERETO, AND AFTER A REVIEW OF THE INSTRUMENT AND THE RECORDS OF THE PUBLIC RECORDS OF THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS, I, THE UNDERSIGNED, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE, DO HEREBY CERTIFY THAT THIS INSTRUMENT IS MADE SOLELY UPON SUCH REPRESENTATIONS AND SHOULD NOT BE RELIED UPON FOR VERIFICATIONS OF THE FACTS ALLEGED, THE REPRESENTATION, FACTUAL OR OTHERWISE, CONTAINED IN THIS PLAT AND THE DOCUMENTS ASSOCIATED WITH IT.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT GEORGETOWN, WILLIAMSON COUNTY, TEXAS, THIS 5<sup>th</sup> DAY OF September, 2023.

I, SOPA NELSON, PLANNING DIRECTOR OF THE CITY OF GEORGETOWN, TEXAS, DO HEREBY CERTIFY THIS PLAT IS APPROVED FOR FILING OF RECORD WITH THE COUNTY CLERK OF WILLIAMSON COUNTY, TEXAS.

SOPA NELSON, PLANNING DIRECTOR  
DATE: 9/6/23

PLANNING AND ZONING COMMISSION  
THIS SUBDIVISION TO BE KNOWN AS HIGHLAND VILLAGE, PHASE 2, COMMERCIAL, AND HAS BEEN ACCEPTED AND APPROVED FOR THE CITY OF GEORGETOWN, TEXAS, AND WILLIAMSON COUNTY, TEXAS, ACCORDING TO THE MINUTES OF THE MEETING OF THE PLANNING AND ZONING COMMISSION.

ON THE 13<sup>th</sup> DAY OF August, 2023, A.D.

P. D. NELSON, CHAIRMAN  
DATE: 9/6/23

A. DICKER, SECRETARY  
DATE: 9/6/23

STATE OF TEXAS  
COUNTY OF WILLIAMSON  
§ KNOW ALL MEN BY THESE PRESENTS

L. NANCY RISTER, CLERK OF THE COUNTY COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING INSTRUMENT IN WRITING, WITH ITS CERTIFICATE OF AUTHENTICATION WAS FILED FOR RECORD IN MY OFFICE ON THE 12<sup>th</sup> DAY OF September, 2023, A.D., AT 10:00 O'CLOCK A.M., AND DULY RECORDED THIS THE 12<sup>th</sup> DAY OF September, 2023, A.D., AT 10:00 O'CLOCK A.M., IN THE OFFICIAL PUBLIC RECORDS OF SAID COUNTY IN DOCUMENT NO. 2023076261.

TO CERTIFY WHICH, WITNESS MY HAND AND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT MY OFFICE IN GEORGETOWN, TEXAS, THE DATE LAST SHOWN ABOVE WRITTEN.



NANCY RISTER, CLERK  
COUNTY COURT OF WILLIAMSON COUNTY, TEXAS  
BY: Diane Lane, Deputy

FINAL PLAT  
HIGHLAND VILLAGE, PHASE 2,  
COMMERCIAL  
A 31.80 Acre Subdivision situated in the  
Lewis P. Dyches Survey Abstract No. 171, City of Georgetown,  
Williamson County, Texas



STEGERBIZZELL

ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181
SERVICES	>>ENGINEERS	>>PLANNERS

SUBMITTAL DATE: 09/19/2023	JOB No. 22901	DATE: 5-Sep-23	SHEET 7 of 7
DRAWN BY: ROW	REVIEWED BY: J.S	>>SURVEYORS	APPROVED BY:



These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.



LEGEND	
	EXISTING CONTOURS (MAJOR)
	EXISTING CONTOURS (MINOR)
	DRAINAGE AREA BOUNDARY

TIME OF CONCENTRATION CALCULATIONS																			
Drainage Area	Length (ft)	Surface Condition	Sheet Flow					Shallow Concentrated 1					Channel						
			"n"	U/S Elev	D/S Elev	Slope (%)	T <sub>c</sub>	Length (ft)	Surface Condition	U/S Elev	D/S Elev	Slope (%)	T <sub>c</sub>	Length (ft)	A (ft <sup>2</sup> )	P (ft)	R (ft)	U/S Elev	D/S Elev
EX-B1	300	RANGE	0.15	929.00	922.00	2.33%	19.36	355	UNPAVED	922.00	917.00	1.41%	3.09	-	-	-	-	-	-
EX-B2	300	RANGE	0.15	929.00	923.30	1.90%	21.02	643	UNPAVED	923.30	905.80	2.72%	4.03	195	16.81	15.93	1.06	905.80	905.00

BASIN	TOTAL AREA			PASTURE & RANGE	PAVEMENT	1/8-ACRE RESIDENTIAL	COMPOSITE
No.	S.F.	ACRES	SQ. MI.	CN 80 (HSG D)	CN 98 (HSG D)	CN 92 (HSG D)	CN (HSG D)
EX-B1	104,114	2.390	0.0037346	2.390	0.00	0.00	80
EX-B2	329,487	7.564	0.0118187	6.544	0.00	1.02	82

FLOW DATA (CFS)				
EXISTING CONDITIONS				
BASIN	Q2	Q10	Q25	Q100
EX-B1	3.8	7.8	10.2	13.9
EX-B2	12.8	25.1	32.6	43.8
Analysis Point	Q2	Q10	Q25	Q100
AP-1	16.6	32.9	42.8	57.6

HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B TREE LIST				
REMOVAL	TREE#	SIZE (IN)	TYPE	NOTES
	1538	13	LIVE OAK	
	1539	16	LIVE OAK	MULTI
	1540	15	LIVE OAK	MULTI
	1541	14	LIVE OAK	MULTI
	1542	17	LIVE OAK	MULTI
	1543	12	LIVE OAK	MULTI
	1544	13	LIVE OAK	MULTI
X	1545	13	LIVE OAK	MULTI
X	1546	16	LIVE OAK	MULTI
	1547	12	LIVE OAK	
	1548	12	LIVE OAK	
	1549	12	LIVE OAK	
	1550	15	LIVE OAK	MULTI
	1551	14	ELM	
	1552	13	LIVE OAK	
	1553	12	LIVE OAK	MULTI
	1554	13	LIVE OAK	MULTI
	1555	15	LIVE OAK	MULTI
	1556	15	LIVE OAK	MULTI
	1557	13	LIVE OAK	MULTI
	1558	15	LIVE OAK	MULTI
	1559	17	LIVE OAK	MULTI
	1560	14	ELM	MULTI
	1561	13	ELM	MULTI
	1562	13	ELM	MULTI
	1563	16	LIVE OAK	
	1564	21	LIVE OAK	
	1565	14	LIVE OAK	
	1566	15	LIVE OAK	
	1567	12	LIVE OAK	MULTI
	1568	17	ELM	MULTI
	1569	13	LIVE OAK	MULTI
	1570	14	LIVE OAK	MULTI
	1571	13	LIVE OAK	MULTI
	1572	13	ELM	
	1573	17	LIVE OAK	MULTI
	1574	12	LIVE OAK	
	1575	12	LIVE OAK	
	1576	17	LIVE OAK	MULTI
	1577	18	LIVE OAK	MULTI
	1578	15	LIVE OAK	MULTI
	1579	12	LIVE OAK	
	1580	12	LIVE OAK	

Landscape sheet LP-1 contains tree mitigation calculations

**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ  
DESIGNED BY: 2/27/25  
DATE

CWJ, NIE  
DRAWN BY: 2/27/25  
DATE

CWJ  
CHECKED BY: DATE

CWJ  
APPROVED BY: DATE



ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181
SERVICES	TBPELS FIRM No. 10003700	WEB STEGERBIZZELL.COM

>>ENGINEERS >>PLANNERS >>SURVEYORS

EXISTING TOPOGRAPHIC SURVEY AND DRAINAGE MAP

FOR

HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B


CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901

**SHEET**  
**07**  
of 14




These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.



TIME OF CONCENTRATION CALCULATIONS																									
	Sheet Flow							Shallow Concentrated 1							Channel							Total			
Drainage Area	Length (ft)	Surface Condition	"n"	U/S Elev	D/S Elev	Slope (%)	T <sub>c</sub>	Length (ft)	Surface Condition	U/S Elev	D/S Elev	Slope (%)	T <sub>c</sub>	Length (ft)	A (ft2)	P (ft)	R (ft)	U/S Elev	D/S Elev	S (ft/ft)	n	Velocity (fps)	T <sub>c</sub>	T <sub>c</sub> Total (min)	Tag
PR-B	30	GRASS	0.24	929.00	928.00	3.33%	3.88	200	PAVED	928.00	924.00	2.00%	1.16	485	9.62	11.00	0.87	918.00	913.00	0.01	0.013	10.64	0.76	6.0	3.6

BASIN No.	TOTAL AREA S.F.	TOTAL AREA ACRES	TOTAL AREA SQ. MI.	PASTURE & RANGE CN 80 (HSG D)	COMMERCIAL 70% IC CN 92 (HSG D)	1/8-ACRE RESIDENTIAL CN 92 (HSG D)	PAVEMENT CN 98 (HSG D)	COMPOSITE CN (HSG D)
PR-B	433,601	9.954	0.0155533	0.00	8.93	1.02	0.00	92

- LEGEND
- 750 EXISTING CONTOURS (MAJOR)
  - EXISTING CONTOURS (MINOR)
  - 750 PROPOSED CONTOURS (MAJOR)
  - PROPOSED CONTOURS (MINOR)



FLOW DATA (CFS)				
EXISTING CONDITIONS				
BASIN	Q2	Q10	Q25	Q100
EX-B1	3.8	7.8	10.2	13.9
EX-B2	12.8	25.1	32.6	43.8
Analysis Point	Q2	Q10	Q25	Q100
AP-1	16.6	32.9	42.8	57.6

FLOW DATA (CFS)				
PROPOSED CONDITIONS - WITH DETENTION				
BASIN	Q2	Q10	Q25	Q100
PR-B	10.0	24.7	33.6	47.4
Analysis Point	Q2	Q10	Q25	Q100
AP-1	10.0	24.7	33.6	47.4

FLOW DATA (CFS)				
CHANGE IN FLOW FROM EXISTING CONDITIONS				
Analysis Point	Q2	Q10	Q25	Q100
AP-1	-6.6	-8.2	-9.2	-10.2

NOTE: THESE PLANS PRESENT THE DESIGN OF A WATER QUALITY AND BATCH DETENTION POND THAT WILL ACCOMMODATE THE REQUIRED RUNOFF THAT THIS SITE WILL PRODUCE AFTER IT HAS BEEN FULLY DEVELOPED. THESE PLANS DO NOT INCLUDE ANY OTHER DEVELOPMENT FEATURE ON THE SITE, AND ALL STRUCTURES, PAVEMENTS, SIDEWALKS, AND UTILITIES NOT ASSOCIATED WITH THE POND WILL NEED TO BE ADDRESSED IN A FUTURE SITE DEVELOPMENT PLAN. IN ORDER FOR THE POND TO FUNCTION AS DESIGNED, THE FINAL SITE DEVELOPMENT DESIGN WILL NEED TO INCLUDE SITE GRADING WHICH WILL DIRECT ALL SITE RUNOFF THROUGH THE WATER QUALITY AND BATCH DETENTION POND.

**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ  
DESIGNED BY: 2/27/25  
DATE  
CWJ, NIE  
DRAWN BY: 2/27/25  
DATE  
CWJ  
CHECKED BY: DATE  
CWJ  
APPROVED BY: DATE



ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181
SERVICES	TBPELS FIRM No. 10003700	WEB STEGERBIZZELL.COM
>>ENGINEERS >>PLANNERS >>SURVEYORS		

PROPOSED DRAINAGE AREA MAP  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901  
  
**SHEET**  
**08**  
of 14



Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: Highland Village II Commercial Lot 1, Block B

Date Prepared: 2/27/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3:  $L_M = 27.2(A_N \times P)$

where:

$L_M$  TOTAL PROJECT = Required TSS removal resulting from the proposed development = 85% of increased load

$A_N$  = Net increase in impervious area for the project

P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = Williamson

Total project area included in plan = 8.52 acres

Predevelopment impervious area within the limits of the plan = 0.00 acres

Total post-development impervious area within the limits of the plan = 5.96 acres

Total post-development impervious cover fraction = 0.70

P = 32 inches

$L_M$  TOTAL PROJECT = 5191 lbs.

The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = 1

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = 1

Total drainage basin/outfall area = 8.52 acres

Predevelopment impervious area within drainage basin/outfall area = 0.00 acres

Post-development impervious area within drainage basin/outfall area = 5.96 acres

Post-development impervious fraction within drainage basin/outfall area = 0.70

$L_M$  THIS BASIN = 5191 lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Batch Detention Basin

Removal efficiency = 91 percent

Aqualogic Cartridge Filter

Bioretention

Batch Detention Basin

BaySeparator

Contech StormFilter

Constructed Wetland

Extended Detention

Grassy Swale

Retention / Irrigation

Sand Filter

Stormceptor

Vegetated Filter Strips

Vortechs

Wet Basin

Wet Vault

4. Calculate Maximum TSS Load Removed ( $L_R$ ) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7:  $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where:

$A_C$  = Total On-Site drainage area in the BMP catchment area

$A_i$  = Impervious area proposed in the BMP catchment area

$A_p$  = Pervious area remaining in the BMP catchment area

$L_R$  = TSS Load removed from this catchment area by the proposed BMP

$A_C$  = 8.52 acres

$A_i$  = 5.96 acres

$A_p$  = 2.56 acres

$L_R$  = 6049 lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired  $L_M$  THIS BASIN = 5191 lbs.

F = 0.86

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 1.38 inches

Post Development Runoff Coefficient = 0.51

On-site Water Quality Volume = 21582 cubic feet

Calculations from RG-348

Pages 3-36 to 3-37

Off-site area draining to BMP = 1.02 acres

Off-site Impervious cover draining to BMP = 0.60 acres

Impervious fraction of off-site area = 0.59

Off-site Runoff Coefficient = 0.41

Off-site Water Quality Volume = 2105 cubic feet

Storage for Sediment = 4737

Total Capture Volume (required water quality volume(s) x 1.20) = 28424 cubic feet

<div style="border: 2px solid black; padding: 5px;"> <p><b>WARNING!</b></p> <p>There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.</p> </div>	NO.	REVISION	BY	DATE	CWJ DESIGNED BY:	2/27/25 DATE		 <b>STEGERBIZZELL</b>					<b>TCEQ WATER QUALITY CALCULATIONS</b> FOR <b>HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS</b>	Project No: 22901
					CWJ NIE	2/27/25 DATE				<b>SHEET</b>  <b>09</b>  <i>of 14</i>				
					CWJ DRAWN BY:									
					CWJ CHECKED BY:									
					CWJ APPROVED BY:									
				ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626								
				METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM P-181 TPELS FIRM No. 10003700	WEB	STEBERBIZZELL.COM						
				SERVICES	>>>ENGINEERS	>>>PLANNERS	>>>SURVEYORS							



These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.

LEGEND

- PROPERTY BOUNDARY
- EASEMENT BOUNDARY
- EXISTING CONTOURS (MAJOR)
- EXISTING CONTOURS (MINOR)
- PROPOSED CONTOURS (MAJOR)
- PROPOSED CONTOURS (MINOR)
- STRUCTURAL CONCRETE
- RIPRAP

NOTE: THESE PLANS PRESENT THE DESIGN OF A WATER QUALITY AND BATCH DETENTION POND THAT WILL ACCOMMODATE THE REQUIRED RUNOFF THAT THIS SITE WILL PRODUCE AFTER IT HAS BEEN FULLY DEVELOPED. THESE PLANS DO NOT INCLUDE ANY OTHER DEVELOPMENT FEATURE ON THE SITE, AND ALL STRUCTURES, PAVEMENTS, SIDEWALKS, AND UTILITIES NOT ASSOCIATED WITH THE POND WILL NEED TO BE ADDRESSED IN A FUTURE SITE DEVELOPMENT PLAN. IN ORDER FOR THE POND TO FUNCTION AS DESIGNED, THE FINAL SITE DEVELOPMENT DESIGN WILL NEED TO INCLUDE SITE GRADING WHICH WILL DIRECT ALL SITE RUNOFF THROUGH THE WATER QUALITY AND BATCH DETENTION POND.

PEAK FLOWS (CFS)		
STORM	POND OUTFLOW	POND OUTFLOW VELOCITY (FT/S)
2-YEAR	10.0	2.5
10-YEAR	24.7	3.2
25-YEAR	33.6	3.6
100-YEAR	47.4	4.1


BLOCK B POND OUTLET SPILLWAYS	
STAGE-DISCHARGE	
DISCHARGE EQUATION: $Q = C_w L H^{1.5}$	
WEIR 1 CREST TYPE	BROAD
WEIR 1 COEFFICIENT ( $C_w$ ) =	2.89
WEIR 1 LENGTH (FT) =	2.5
WEIR 1 ELEVATION (FT) =	913.00
WEIR 2 CREST TYPE	SHARP
WEIR 2 COEFFICIENT ( $C_w$ ) =	3
WEIR 2 LENGTH (FT) =	2
WEIR 2 ELEVATION (FT) =	914.25

STAGE (FT)	WEIR 1 DISCHARGE (CFS)	WEIR 2 DISCHARGE (CFS)	TOTAL DISCHARGE (CFS)	STORAGE (ACRE-FT)
910.0	0	0	0	0
911.0	0	0	0	0.0473
912.0	0	0	0	0.2790
913.0	0	0	0	0.7125
914.0	7.23	0.00	7.23	1.2793
915.0	20.44	3.90	24.33	1.9867
916.0	37.54	13.89	51.43	2.8035
916.5	47.31	20.25	67.56	3.2404



BLOCK B INLET PIPE A						
Number	Length	Line/Chord Direction	Start Northing	Start Easting	End Northing	End Easting
L1	47.161	S26° 21' 06.22"E	10241509.2368	3101241.5898	10241466.9765	3101262.5236

BLOCK B INLET PIPE B						
Number	Length	Line/Chord Direction	Start Northing	Start Easting	End Northing	End Easting
L2	213.593	S25° 24' 28.24"E	10241602.9219	3100982.1483	10241409.9882	3101073.7923


BLOCK B POND OUTLET PIPE						
Number	Length	Line/Chord Direction	Start Northing	Start Easting	End Northing	End Easting
L3	90.764	S52° 26' 40.80"E	10241416.3233	3101227.8712	10241361.0001	3101299.8258




GRADING AND BATCH DETENTION POND PLAN



POND OUTLET PROFILE  
1"=10' VERTICAL  
1"=10' HORIZONTAL



INLET PIPE A PROFILE  
1"=10' VERTICAL  
1"=10' HORIZONTAL



INLET PIPE B PROFILE  
1"=10' VERTICAL  
1"=10' HORIZONTAL

**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ  
DESIGNED BY: 2/27/25  
DATE  
CWJ, NIE  
DRAWN BY: 2/27/25  
DATE  
CWJ  
CHECKED BY: DATE  
CWJ  
APPROVED BY: DATE



ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181 TBPELS FIRM No.10003700
SERVICES	>>ENGINEERS	>>PLANNERS >>SURVEYORS





DIMENSION SITE AND GRADING PLAN  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLAMSON COUNTY, TEXAS

Project No:  
22901

**SHEET**  
**10**  
of 14




These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.



#### BATCH POND CONTROLLER NOTES:

- SUBMITTALS - THE CONTRACTOR SHALL PROVIDE THE ENGINEER WITH BATCH POND CONTROLLER SUBMITTALS FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION. SUBMITTALS SHALL INCLUDE: POWER SOURCE, BATTERY BACKUP, LOGIC CONTROLLER, LOCKABLE PARTS ENCLOSURE, FLOAT, VALVE, ACTUATOR, RELAY, ALARM SYSTEM, SIGNAGE, ETC. TOTAL WATTAGE OF POWER CONSUMPTION AND W-HOURS OF ACTUATOR, CONTROLLER AND RELAY SHALL BE PROVIDED. A COPY OF THE APPROVED SUBMITTALS SHALL BE PROVIDED TO TCEQ WITH THE ENGINEERS CERTIFICATION OF PROJECT COMPLETION FOR INCLUSION IN THE TCEQ PROJECT FILE.
- CONTROLLER - THE CONTROLLER CONSISTS OF A LEVEL SENSOR IN THE DETENTION BASIN, A VALVE (WITH A DEFAULT CLOSED POSITION), AN ACTUATOR, AND THE ASSOCIATED CONTROL. THE CONTROLLER DETECTS WATER FILLING THE BASIN FROM THE LEVEL SENSOR AND INITIATES A 12-HOUR DETENTION TIME. AT THE END OF THE REQUIRED DETENTION TIME, THE CONTROLLER OPENS THE VALVE AND DRAINS INTO THE SECOND BASIN. SUBSEQUENT RAINFALL EVENTS THAT OCCUR PRIOR TO THE BASIN DRAINING SHOULD CAUSE THE VALVE TO REMAIN OPEN AND ALLOW THE ADDITIONAL STORMWATER RUNOFF TO PASS THROUGH THE BASIN. ONCE THE BASIN IS DRAINED THE CONTROLLER CLOSES THE VALVE. THE DRAWDOWN TIME OF THE BASIN SHOULD NOT EXCEED 48 HOURS FOR A SINGLE STORM EVENT AFTER THE 12 HOUR REQUIRED DETENTION TIME. ALL CABLES SHOULD BE PROTECTED BY CONDUIT AND BURIED TO PREVENT DAMAGE DURING MAINTENANCE ACTIVITIES. INFORMATION ON THE DESIGN AND CONFIGURATION OF AN EXISTING SYSTEM, INCLUDING THE SYSTEM SCHEMATIC, CAN BE VIEWED AT THE AUSTIN OR SAN ANTONIO REGIONAL OFFICES.
- LOGIC CONTROLLER - THE CONTROLLER SHOULD BE PROGRAMMED TO BEGIN DRAINING STORMWATER RUNOFF FROM THE BASIN 12 HOURS AFTER THE FIRST STORMWATER RUNOFF IS SENSED. THE SYSTEM SHOULD BE PROGRAMMED TO HAVE THE VALVE REMAIN OPEN FOR TWO HOURS AFTER THE LEVEL SENSOR INDICATES THE BASIN IS EMPTY TO ALLOW ANY REMAINING SHALLOW WATER TO BE DISCHARGED. THE SYSTEM SHOULD PROVIDE THE FOLLOWING: A TEST SEQUENCE; BE ABLE TO DEAL WITH LOW BATTERY/POWER OUTAGES, AN ON/OFF/RESET SWITCH, MANUAL OPEN/CLOSE SWITCHES (MAINTENANCE/SPILL), CLEARLY VISIBLE EXTERNAL INDICATOR TO INDICATE A CYCLE IS IN PROGRESS WITHOUT OPENING THE BOX, AND ABILITY TO EXERCISE THE VALVE TO PREVENT SEIZING.
- POWER - THE POND CONTROL SYSTEM CONTROLLER AND ACTUATOR SHALL BE 120 VOLT POWDERED OR 120 VOLT SOLAR POWERED WITH BACKUP BATTERY POWER TO RESPOND TO A LOSS OF POWER IN THE MIDDLE OF A CYCLE.
- PARTS ENCLOSURE & ALARM SYSTEM - THE PARTS ENCLOSURE SHALL BE LOCKABLE. AN ALARM SYSTEM CLEARLY VISIBLE TO INDICATE SYSTEM MALFUNCTION, WITH PHONE NUMBERS OF THE OWNER AND TCEQ REGION 11 OFFICE SHALL BE PROVIDED.
- TEMPERATURE/WEATHER - THE SYSTEM SHALL BE CAPABLE OF OPERATION FROM 0 TO 130 DEGREES FAHRENHEIT AND FROM 10 TO 90% HUMIDITY.
- RELIABILITY - THE SYSTEM SHALL HAVE A MINIMUM RELIABILITY OF 40,000 HOURS (4.6 YEARS).



**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ  
DESIGNED BY: 2/27/25  
DATE  
CWJ, NIE  
DRAWN BY: 2/27/25  
DATE  
CWJ  
CHECKED BY: DATE  
CWJ  
APPROVED BY: DATE







ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181
SERVICES	144785	TBPELS FIRM No. 10003700
	>>ENGINEERS	>>PLANNERS
	>>ENGINEERS	>>SURVEYORS

DETENTION & WQ POND SECTIONS & DETAILS  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901  
**SHEET**  
**11**  
of 14




These drawings are the sole property of STEGER & BIZZELL ENGINEERING, INC. The use of these drawings is hereby restricted to the original site for which they were prepared. Reproduction or reuse of these drawings in whole or in part without written permission of STEGER & BIZZELL ENGINEERING, INC. is strictly prohibited.



#### CITY OF GEORGETOWN GENERAL NOTES

1. These construction plans were prepared, sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore based on the engineer's concurrence of compliance, the construction plans for construction of the proposed project are hereby approved subject to the standard Construction Specifications and Details Manual and all other applicable City, State and Federal Requirements and Codes.
2. This project is subject to all City Standard Specifications and Details in effect at the time of submittal of the project to the City.
3. The site construction plans shall meet all requirements of the approved site plan.
4. Wastewater mains and service lines shall be SDR 26 PVC.
5. Wastewater mains shall be installed without horizontal or vertical bends.
6. Maximum distance between wastewater manholes is 500 feet.
7. Wastewater mains shall be low pressure air tested and mandrel tested by the contractor according to the City of Georgetown and TCEQ requirements.
8. Wastewater manholes shall be vacuum tested and coated by the contractor according to City of Georgetown and TCEQ requirements.
9. Wastewater mains shall be camera tested by the contractor and submitted to the City on DVD format prior to paving the streets.
10. Private water system fire lines shall be tested by the contractor to 200 psi for 2 hours.
11. Private water system fire lines shall be ductile iron piping from the water main to the building sprinkler system, and 200 psi C900 PVC for all others.
12. Public water system mains shall be 150 psi C900 PVC and tested by the contractor at 150 psi for 2 hours.
13. All bends and changes in direction on water mains shall be restrained and thrust blocked.
14. Long fire hydrant leads shall be restrained.
15. All water lines are to be bacteria tested by the contractor according to the City standards and specifications.
16. Water and Sewer main crossings shall meet all requirements of the TCEQ and the City.
17. Flexible base material for public streets shall be TXDOT Type A Grade 1.
18. Hot mix asphaltic concrete pavement shall be Type D unless otherwise specified and shall be a minimum of 2 inches thick on public streets and roadways.
19. All sidewalk ramps are to be installed with the public infrastructure.
20. A maintenance bond is required to be submitted to the City prior to acceptance of the public improvements. This bond shall be established for 2 years in the amount of 10% of the cost of the public improvements and shall follow the City format.
21. Record drawings of the public improvements shall be submitted to the City by the design engineer prior to acceptance of the project. These drawings shall be PDF (300 dpi).



**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ	DESIGNED BY:	2/27/25	DATE
CWJ	NIE	2/27/25	DATE
CWJ	DRAWN BY:		
CWJ	CHECKED BY:		
CWJ	APPROVED BY:		




ADDRESS	1978 S. AUSTIN AVENUE	GEORGETOWN, TX 78626
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181 TBPELS FIRM No.10003700
SERVICES	>>ENGINEERS	>>PLANNERS >>SURVEYORS

UTILITY PLAN  
FOR  
HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS


Project No:  
22901  
**SHEET**  
12  
of 14





## LEGEND


- SF — SILT FENCE  
 - - - - - LIMITS OF CONSTRUCTION  
 — 750 — EXISTING CONTOURS (MAJOR)  
 - - - - - EXISTING CONTOURS (MINOR)  
 — 750 — PROPOSED CONTOURS (MAJOR)  
 - - - - - PROPOSED CONTOURS (MINOR)




NOTES:

1. WHERE ANY EXCEPTIONS RESULT IN A FENCE BEING CLOSER THAN FOUR FEET (4'-0") TO A TREE TRUNK; PROTECT THE TRUNK WITH STRAPPED-ON PLANKING TO A HEIGHT OF EIGHT FEET (8'-0"), OR TO THE LIMITS OF LOWER BRANCHING IN ADDITION TO THE REDUCED FENCE PROVIDED.
2. ANY ROOTS EXPOSED BY CONSTRUCTION ACTIVITY SHALL BE PRUNED FLUSH WITH THE SOIL BACKFILL. THE EXPOSED ROOTS SHALL BE COVERED WITH MULCH AS POSSIBLE. IF EXPOSED ROOT AREAS ARE NOT BACKFILLED WITHIN TWO (2) DAYS, COVER THEM WITH ORGANIC MATERIAL IN A MANNER WHICH REDUCES SOIL TEMPERATURE, AND MINIMIZES WATER LOSS DUE TO EVAPORATION.
3. PRIOR EXCAVATION OR GRADE CUTTING WITHIN TREE DRILLPIE, MAKE A CLEAN CUT BETWEEN THE DISTURBED AND UNDISTURBED ROOT ZONES WITH A ROCK SAW OR SIMILAR EQUIPMENT, TO MINIMIZE DAMAGE TO REMAINING ROOTS.
4. TREES MOST HEAVILY IMPACTED BY CONSTRUCTION ACTIVITIES SHOULD BE WATERED DEEPLY ONCE A WEEK DURING PERIODS OF HOT, DRY WEATHER. TREE CROWNS SHOULD BE SPRAYED WITH WATER PERIODICALLY TO REDUCE DUST ACCUMULATION ON THE LEAVES.
5. ANY TRENCING REQUIRED FOR THE INSTALLATION OF LANDSCAPE IRRIGATION SHALL BE PLACED AS FAR FROM EXISTING TREE TRUNKS AS POSSIBLE.
6. NO LANDSCAPE TOPSOIL PRESSING GREATER THAN FOUR INCHES (4") SHALL BE PERMITTED WITHIN THE DRILLPIE OF A TREE, NO SOIL IS PERMITTED ON THE ROOT FLARE OF ANY TREE.
7. PRUNING TO PROVIDE CLEARANCE FOR STRUCTURES, VEHICULAR TRAFFIC AND EQUIPMENT SHALL TAKE PLACE BEFORE CONSTRUCTION BEGINS.

*The Architect/Engineer assumes responsibility for appropriate use of this standard.*

		CITY OF GEORGETOWN CONSTRUCTION STANDARDS AND DETAILS TREE PROTECTION - WOOD SLATS		REVISION NOTES ADOPTED 6/21/2006	
100% <b>GEORGETOWN</b> TEXAS Georgetown Utility Systems 600 West 10th Street, Suite 100 Georgetown, TX 78626				DRAWING NAME EC10	
		SCALE NTS		DATE 1/2003	
		DRAWN BY MRS		CHECKED BY TRB	




NOTES:

3. TREE PROTECTION FENCES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR GRADING).
- FENCES SHALL COMPLETELY SURROUND THE TREE, OR CLUSTERS OF TREES, WILL BE LOCATED AT THE EXTENDED LIMIT OF THE TREE CANOPY (DROPLINE), AND WILL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROJECT IN ORDER TO PREVENT THE FOLLOWING:
- A. SOIL COMPACTION IN THE ROOT ZONE AREA RESULTING FROM VEHICULAR TRAFFIC, OR STORAGE OF CONSTRUCTION MATERIALS.
  - B. ROOT ZONE DISTURBANCES DUE TO GRADE CHANGES (GREATER THAN SIX INCHES (6") CUT OR FILL, OR TREENCHING NOT REVEALED BY THE EXISTING SURFACE).
  - C. WOUNDS TO EXPOSED ROOTS, TRUNKS OR LIMBS BY MECHANICAL EQUIPMENT.
  - D. OTHER ACTIVITIES DETRIMENTAL TO TREES, SUCH AS CHEMICAL STORAGE, CEMENT TRUCK CLEANING AREA, ETC.
3. EXCEPTIONS TO INSTALLING FENCES ON TREE DROPLINES MAY BE PERMITTED IN THE FOLLOWING CASES:
- A. WHERE PERMEABLE PAVING IS TO BE INSTALLED, ERECT THE FENCE AT THE OUTER LIMITS OF THE PERMEABLE PAVING AREA.
  - B. WHERE TREES ARE CLOSE TO PROPOSED BUILDINGS, ERECT THE FENCE NO CLOSER THAN SIX FEET (6'-0") TO BUILDING.

*The Architect/Engineer assumes responsibility for appropriate use of this standard.*

 <p><b>GEORGETOWN TEXAS</b> Georgetown Valley Systems New Community Development</p>		<p>CITY OF GEORGETOWN CONSTRUCTION STANDARDS AND DETAILS</p> <p><b>TREE PROTECTION - CHAIN LINK FENCE</b></p>		<p>REVISION DATE: <b>ADOPTED 6/21/2006</b></p> <p>DRAWING NAME: <b>EC09</b></p>	
DATE:	JUNE	YEAR:	(2003)	DATE:	
DRAWN BY:	NTS	APPROVED BY:		DATE:	
MRS		TRG			





## INSTALLATION

- LAYOUT THE SILT FENCE FOLLOWING AS CLOSELY AS POSSIBLE TO THE CONTOUR.  
CLEAR THE GROUND OF DEBRIS, ROCKS, PLANTS (INCLUDING GRASSES TALLER THAN 2")  
AND FOLIAGE. SMOOTH FLOW APPROACH SIDES. EXCAVATE 6" DEEP 1" WIDE TRENCH ON  
UPSTREAM SIDE OF FACE PER FENCE.  
USE HEAVY DUTY "POST" AT LEAST 12" INCHES INTO THE GROUND AND AT A SIGHT ANGLE TOWARDS THE FLOW.  
TIE TO CONTOUR. DRILL 1/2" DIA. HOLES 12" DEEP. WIRE MESH TO T-POST WITH 1 1/2 GAUGE GALVANIZED T-POST CLOSER  
TO TOP OF THE WIRE TO BE 24" ABOVE GROUND LEVEL. THE WELDED WIRE MESH TO BE OVERLAPPED 6" AND  
THE ENDS OF THE WIRE TO BE 6" ABOVE GROUND.  
THE SILT FENCE TO BE INSTALLED WITH A SHORT A MINIMUM OF 6" WIDE PLACED ON THE UPHILL SIDE OF THE FENCE  
LINE EXCAVATED TRENCH. THE FABRIC TO OVERLAP THE TOP OF THE WIRE BY 6".  
INSTALL THE SILT FENCE BY BACKFILLING WITH SOIL TO THE T-POST WITH AT LEAST 12" OF SOIL. PLACES  
GEOTECHNICAL SPECIFICATIONS TO BE A MINIMUM OF 18" WIDE ATTACHED AT LEAST 6" LARGER. SPECIES IN CONCENTRATED  
FLOW AREAS WILL NOT BE ACCEPTED.  
SILT FENCE SHALL BE REMOVED WHEN THE SILT IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPIDE STORM  
WATER DRAINAGE.



800.508.5088  
**GEORGETOWN**  
**TEXAS**  
 Georgetown Utility Systems

 CITY OF GEORGETOWN TEXAS Georgetown Utility Company		REVISION NO: <b>ADOPTED 6/21/2006</b>	
		DRAWING NAME: <b>EC02</b>	
CITY OF GEORGETOWN CONSTRUCTION STANDARDS AND DETAILS  SILT FENCE DETAIL		SCALE: NTS	DATE: 1/2003
		DRAWN BY: MADE	APPROVED BY: TJMS



INSTALLATION:


- CLEAR THE AREA OF DEBRIS, ROCKS OR PLANTS THAT WILL INTERFERE WITH INSTALLATION.
- GRADE THE AREA FOR THE ENTRANCE TO FLOW BACK ON TO THE CONSTRUCTION SITE. RUNOFF FROM THE STABILIZED CONSTRUCTION
- PLACE GEOTEXTILE FABRIC AS APPROVED BY THE CITY.
- PLACE ROCK AS APPROVED BY THE CITY.

INSPECTIONS AND MAINTENANCE GUIDELINES:


- THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
- ALL SEDIMENT SPILLED, DROPPED, OR TRACKED ON TO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.
- WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY.
- WHEN REQUIRED, WHEELS SHOULD BE CLEANED BY A STATION STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.
- ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS

*The Architect/Engineer assumes responsibility for appropriate use of this standard.*

 <p> <b>GEORGETOWN</b>          TEXAS  <small>Georgetown EXIST STUDY</small> </p>	<p>             CITY OF GEORGETOWN              CONSTRUCTION STANDARDS AND DETAILS  <b>STABILIZED CONSTRUCTION ENTRANCE</b> </p>	(ADOPTED) DATE: <b>ADOPTED 6/21/2006</b>	
		(DRAWING NAME): <b>EC06</b>	
		SCALE: <b>NTS</b> DRAWN BY: <b>MPS</b>	DATE: <b>1/2003</b> APPROVED BY: <b>TRB</b>



## Temporary Concrete Washout Area Detail



**WARNING!**  
There are existing water pipelines, underground telephone cables and other above and below ground utilities in the vicinity of this project. The Contractor shall contact all appropriate companies prior to any construction in the area and determine if any conflicts exist. If so, the Contractor shall immediately contact the Engineer who shall revise the design as necessary.

NO.	REVISION	BY	DATE

CWJ	2/27/25
DESIGNED BY:	DATE
CWJ, NIE	2/27/25
DRAWN BY:	DATE
CWJ	
CHECKED BY:	DATE
CWJ	
APPROVED BY:	DATE



STEGER BIZZELL

ADDRESS		1978 S. AUSTIN AVENUE		GEORGETOWN, TX 78626	
METRO	512.930.9412	TEXAS REGISTERED ENGINEERING FIRM F-181 TBPELS FIRM No.10003700			WEB STEGERBIZZELL.COM
SERVICES		>>ENGINEERS		>>PLANNERS	
		>>>SURVEYORS			

## EROSION CONTROL PLAN

FOR

HIGHLAND VILLAGE PHASE II - COMMERCIAL - BLOCK B  
CITY OF GEORGETOWN, WILLIAMSON COUNTY, TEXAS

Project No:  
22901

***SHEET***

13

of 14







## **Attachment N – Inspection, Maintenance, Repair, and Retrofit Plan**

The following can be found in the TCEQ's "Complying with the Edwards Rules: Technical Guidance Manual on Best Management Practices."

### **Maintenance Guidelines for Batch Detention Basins**

Batch detention basins may have somewhat higher maintenance requirements than an extended detention basin since they are active stormwater controls. The maintenance activities are identical to those of extended detention basins with the addition of maintenance and inspections of the automatic controller and the valve at the outlet.

- *Inspections.* Inspections should take place a minimum of twice a year. One inspection should take place during wet weather to determine if the basin is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. The remaining inspections should occur between storm events so that manual operation of the valve and controller can be verified. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. The outlet structure and the trash screen should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet(s) as described in previous sections. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately.
- *Mowing.* The basin, basin side-slopes, and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas.
- *Litter and Debris Removal.* Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for possible clogging or obstructions and any debris removed.
- *Erosion control.* The basin side slopes and embankment all may periodically suffer from slumping and erosion. To correct these problems, corrective action, such as regarding and revegetation, may be necessary. Correction of erosion control should take place whenever required based on the periodic inspections.
- *Nuisance Control.* Standing water or soggy conditions may occur in the basin. Some standing water may occur after a storm event since the valve may close with 2 to 3 inches of water in the basin. Some flow into the basin may also occur between storms due to spring flow and residential water use that enters the storm sewer system. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.).

- **Structural Repairs and Replacement.** With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, retaining walls, etc.) should be identified and repaired immediately. An example of this type of repair can include patching of cracked concrete, sealing of voids, removal of vegetation from cracks and joints. The various inlet/outlet structures in a basin will eventually deteriorate and must be replaced.
- **Sediment Removal.** A properly designed batch detention basin will accumulate quantities of sediment over time. The accumulated sediment can detract from the appearance of the facility and reduce the pollutant removal performance of the facility. The sediment also tends to accumulate near the outlet structure and can interfere with the level sensor operation. Sediment shall be removed from the basin at least every 5 years, when sediment depth exceeds 6 inches, when the sediment interferes with the level sensor or when the basin does not drain within 48 hours. Care should be taken not to compromise the basin lining during maintenance.
- **Logic Controller.** The Logic Controller should be inspected as part of the twice yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris. The solar panel should be inspected and any dust or debris on the panel should be carefully removed. The controller and all other circuitry and wiring should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. At the end of the inspection, the controller should be reset.

**NOTE:** This Inspection, Maintenance, Repair and Retrofit Plan for the **Highland Village Phase I – Commercial Batch Detention Pond** was created and designed by the engineer of this BMP. Maintenance is the responsibility of the Owner and should be followed in accordance with this plan in order to keep the BMPs operating correctly.



Highland Village Georgetown LP



Date



Chad W. Jones, P.E.

Steger Bizzell

F-181



Date

SAMPLE)\*\*

PERMANENT BMP LOG

\*\*SAMPLE)\*\*

INSPECTOR: \_\_\_\_\_ DATE: \_\_\_\_\_

Inspectors Company: \_\_\_\_\_

Company Address: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Company Phone: \_\_\_\_\_ Fax: \_\_\_\_\_

Date of Last Inspection: \_\_\_\_\_ Recent Heavy Rainfall: YES NO  
(CIRCLE ONE)

Status of BMP(s): \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Corrective Action Required (if any): \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Date Corrected (if applicable): \_\_\_\_\_

\*If actions are required they must be completed within 7 working days of this INSPECTION.

\_\_\_\_\_

Inspectors Signature

\_\_\_\_\_

Date:

**Attachment O - Pilot-Scale Field Testing Plan, if BMPs not based on Complying with the Edwards  
Aquifer Rules: Technical Guidance for BMPs**

Not applicable.

### **Attachment P - Measures for Minimizing Surface Stream Contamination**

The proposed site will be used for commercial development with a maximum 70-percent impervious cover and a permanent BMP is included. There are no surface streams located within the project limits or directly downstream.

# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Highland Village Georgetown LP / Steger Bizzell, Chad Jones, P.E.

Date: 2/10/2025

Signature of Customer/Agent:



**Regulated Entity Name:** Highland Village Phase II Block B

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Berry Creek

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.



- ☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- ☒ N/A
12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

## ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

- 20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## **Attachment A – Spill Response Actions**

Because fuels and hazardous substances will be provided by an off-site facility, no on-site containment procedures are provided for in this CZP.

The objective of this section is to describe measures to prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees. The following steps will help reduce the stormwater impacts of leaks and spills:

### ***Education***

1. Be aware that different materials pollute in different amounts. Make sure that each employee knows what a “significant spill” is for each material they use, and what is the appropriate response for “significant” and “insignificant” spills. Employees should also be aware of when spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
2. Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
3. Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
4. Establish a continuing education program to indoctrinate new employees.
5. Have contractor’s superintendent or representative oversee and enforce proper spill prevention and control measures.

### ***General Measures***

1. To the extent that the work can be accomplished safely, spills of oil, petroleum products, and substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
2. Store hazardous materials and wastes in covered containers and protect from vandalism.
3. Place a stockpile of spill cleanup materials where it will be readily accessible.
4. Train employees in spill prevention and cleanup.
5. Designate responsible individuals to oversee and enforce control measures.
6. Spills should be covered and protected from stormwater run-on during rainfall to the extent that it doesn’t compromise clean-up activities.
7. Do not bury or wash spills with water.
8. Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
9. Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
10. Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
11. Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.

12. Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

### ***Cleanup***

1. Clean up leaks and spills immediately.
2. Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
3. Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

### ***Minor Spills***

1. Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
2. Use absorbent materials on small spills rather than hosing down or burying the spill.
3. Absorbent materials should be promptly removed and disposed of properly.
4. Follow the practice below for a minor spill:
5. Contain the spread of the spill.
6. Recover spilled materials.
7. Clean the contaminated area and properly dispose of contaminated materials.

### ***Semi-Significant Spills***

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

1. Contain spread of the spill.
2. Notify the project foreman immediately.
3. If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
4. If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
5. If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

### ***Significant/Hazardous Spills***

For significant or hazardous spills that are in reportable quantities:

1. Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.

2. For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110, 119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
3. Notification should first be made by telephone and followed up with a written report.
4. The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
5. Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

More information on spill rules and appropriate responses is available on the TCEQ website at: <http://www.tceq.texas.gov/response/>

### ***Vehicle and Equipment Maintenance***

1. If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the run-on of stormwater and the runoff of spills.
2. Regularly inspect onsite vehicles and equipment for leaks and repair immediately.
3. Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
4. Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
5. Place drip pans or absorbent materials under paving equipment when not in use.
6. Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
7. Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
8. Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
9. Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

### ***Vehicle and Equipment Fueling***

1. If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the run-on of stormwater and the runoff of spills.
2. Discourage "topping off" of fuel tanks.
3. Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.

If a spill should occur, the person responsible for the spill should contact the TCEQ at (512) 339-2929 or call 911. Soil contaminated by spills that occur on-site will be removed and disposed at an approved disposal site.

## **Attachment B – Potential Sources of Contamination**

- Hydraulic fluid and diesel fuel
- Portable toilet systems (sanitary waste)
- Trash from construction activities
- Paints, paint solvents, glues, concrete and other building materials
- Plant fertilizers and pesticides
- Inadequate maintenance of temporary water pollution abatement measures
- Stockpiles or spoils of materials

### **Attachment C – Sequence of Major Activities**

The following sequence of activities is suggested. The sequence of construction will take place in one phase. The actual sequence may vary slightly depending on the contractor or weather conditions.

1. Construction activities will commence with the installation of the required silt fence and erosion and sedimentation control measures (Estimated Area = 3.0 Acres).
2. Excavation will take place where the detention pond will be situated. Spoils of this material may be placed at a location on the project site as directed by the owner or hauled off-site. These spoils and any other loose granular material will be enclosed by a silt fence. **Silt fence will be utilized as the control measure** (Estimated Area = 3.0 Acres).
3. Grading on the site will consist of the placement and compaction of base or select fill material and excavation and fill for the proposed detention pond. **Silt fence and a concrete washout will be utilized as the control measures** (Estimated Area = 3.0 Acres).
4. The installation of the utilities will disturb a portion of the site. Proposed utility improvements include the construction of water extensions and connections for the pond irrigation.
5. Subsequent to the construction of the civil infrastructure disturbed areas will be hydro mulched or seeded. **Silt fence and inlet protection will be utilized as the control measures** (Estimated Area = 3.0 Acres).
6. Once vegetation is established on the site, Temporary BMPs will be removed as allowed by the engineer.

All surface runoff originating up-gradient or on site will be contained within the proposed silt fence and rock berm. The silt fence and rock berm will trap most pollutants and prevent them from entering off-site surface streams, sensitive features, or the aquifer.

## **Attachment D – Temporary Best Management Practices and Measures**

All on-site runoff will be contained within the proposed silt fence and inlet protection. In addition, a concrete washout area will be located on the site. Off-site runoff will be captured and reduced with the proposed silt fence. The stabilized construction entrance will reduce the amount of sediment leaving the site. These temporary BMPs will trap most pollutants and prevent them from entering off-site surface streams, sensitive features, or the aquifer.



**Attachment E – Request to Temporarily Seal a Feature**

There will be no temporary sealing of naturally occurring sensitive features on the site.

### **Attachment F – Structural Practices**

Construction will be conducted in a manner which will minimize areas of unstabilized disturbance. Silt fences, and a construction entrance will be used to limit the runoff discharge of sediments from exposed areas on the site during construction. Drainage off the site is typically in a sheet flow or shallow concentrated flow condition due to the relatively flat topography. The Water Quality Pond will be excavated to provide a temporary sediment trap.

## **Attachment H – Temporary Sediment Pond(s) Plan and Calculations**

The permanent water quality pond will serve as the temporary sediment pond during construction.

## **Attachment I – Inspection and Maintenance for BMPs**

### *Silt Fence*

1. Inspect all fences weekly and after any rainfall.
2. Remove sediment when buildup reaches 6 inches, or install a second line of fencing parallel to the old fence.
3. Replace any torn fabric or install a second line of fencing parallel to the torn section.
4. Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
5. When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

### *Concrete Washout*

1. Inspection should be made weekly and after each rainfall by the responsible party.
2. Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.
3. The berm/temporary pit should be reshaped as needed during inspection.
4. The berm/temporary pit should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.
5. The washout should be left in place until construction has been completed.
6. When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the Concrete Washout should be revegetated.
7. The concrete from the washout should be removed from the site in an appropriate manner.

### *Temporary Construction Entrance/Exit*

1. The entrance should be maintained in a condition which will prevent tracking or flowing of sediment onto the public right-of-way. This may require periodic top dressing with additional stone as conditions demand, and repair or cleanout of any measures used to trap sediment.
2. All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor.
3. When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
4. When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
5. All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

The following sample forms should be utilized to document the inspection and maintenance of the proposed temporary BMPs as described above. This form shall be kept on site with the CZP until the project is completed.

## Temporary BMP Logs – Silt Fence

[illegible]

## Temporary BMP Logs – Concrete Washout

[illegible]

## Temporary BMP Logs – Temporary Construction Entrance

[illegible]

## **Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices**

Vehicular traffic should be limited to areas of the project site where construction will take place. The contractor should endeavor to preserve existing vegetation as much as practicable to reduce erosion and lower the cost associated with stabilization. **Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.**

All disturbed areas shall be stabilized as described below.

Except as provided for below, stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased.

- A. Where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity temporarily or permanently ceases is precluded by snow cover or frozen ground conditions, stabilization measures shall be initiated as soon as practicable.
- B. Where construction activity on a portion of the site has temporarily ceased, and earth-disturbing activities will be resumed with 21 days, temporary stabilization measures do not have to be initiated on that portion of the site.
- C. In areas experiencing drought, where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

Stabilization measures as described as follows:

All disturbed grass areas should be planted in drought resistant species normally grown as permanent lawns, such as Zoysia, Bermuda and Buffalo. Grass areas may be sodded, plugged, sprigged, or seeded except that solid sod shall be used in swales or other areas subject to erosion. All planted areas shall be provided with a readily available water supply and watered as necessary to ensure continuous healthy growth and development. Maintenance shall include the replacement of all dead plant material if that material was used to meet the requirements of this section.



**Insert Copy of Notice of Intent (NOI) prior to Start of Construction**

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Highland Village Phase II Block B

Regulated Entity Location: Georgetown, TX

Name of Customer: Highland Village Georgetown, LP

Contact Person: Mr. Joe Birdwell

Phone: 512-917-7648

Customer Reference Number (if issued):CN \_\_\_\_\_

Regulated Entity Reference Number (if issued):RN \_\_\_\_\_

### Austin Regional Office (3373)

☐ Hays

☐ Travis

☒ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☐ Recharge Zone

☒ Contributing Zone

☐ Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	8.52 Acres	\$ 5,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature:  \_\_\_\_\_

Date: February 10, 2025

## Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

### ***Water Pollution Abatement Plans and Modifications***

#### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

#### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

#### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

#### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I Vernon W. Barge III,  
Print Name  
Managing General Partner,  
Title - Owner/President/Other  
of Highland Village Georgetown, L.P.,  
Corporation/Partnership/Entity Name  
have authorized Mr. Chad W. Jones, P.E.,  
Print Name of Agent/Engineer  
of Steger Bizzell,  
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

*V.W. Barge III*

Applicant's Signature

2/24/25


Date

THE STATE OF TEXAS §

COUNTY OF BELL §

BEFORE ME, the undersigned authority, on this day personally appeared V.W. Barge III known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 26th day of February, 2025.



*Petra Klarus*

NOTARY PUBLIC

PETRA KLARIUS

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 01-30-2029



TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided)			
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application)			
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other	
<b>2. Attachments</b> Describe Any Attachments: (ex. Title V Application, Waste Transporter Application, etc.)			
<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
<b>3. Customer Reference Number (if issued)</b>		<b>4. Regulated Entity Reference Number (if issued)</b>	
CN		RN	

## SECTION II: Customer Information

<b>5. Effective Date for Customer Information Updates (mm/dd/yyyy)</b>							
<b>6. Customer Role</b> (Proposed or Actual) – as it relates to the <u>Regulated Entity</u> listed on this form. Please check only <u>one</u> of the following:							
<input checked="" type="checkbox"/> Owner		<input type="checkbox"/> Operator		<input type="checkbox"/> Owner & Operator			
<input type="checkbox"/> Occupational Licensee		<input type="checkbox"/> Responsible Party		<input type="checkbox"/> Voluntary Cleanup Applicant		<input type="checkbox"/> Other: _____	
<b>7. General Customer Information</b>							
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information		<input type="checkbox"/> Change in Regulated Entity Ownership			
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State)				<input checked="" type="checkbox"/> No Change**			
<b>**If "No Change" and Section I is complete, skip to Section III – Regulated Entity Information.</b>							
<b>8. Type of Customer:</b>		<input checked="" type="checkbox"/> Corporation		<input type="checkbox"/> Individual		<input type="checkbox"/> Sole Proprietorship- D.B.A	
<input type="checkbox"/> City Government		<input type="checkbox"/> County Government		<input type="checkbox"/> Federal Government		<input type="checkbox"/> State Government	
<input type="checkbox"/> Other Government		<input type="checkbox"/> General Partnership		<input type="checkbox"/> Limited Partnership		<input type="checkbox"/> Other: _____	
<b>9. Customer Legal Name</b> (If an individual, print last name first: ex: Doe, John) <span style="float: right;">If new Customer, enter previous Customer below</span> <span style="float: right;">End Date:</span>							
Highland Village Georgetown, LP							
<b>10. Mailing Address:</b>		2005 Birdcreek Drive, Suite 211					
City		Temple		State		TX	
ZIP		76502		ZIP + 4			
<b>11. Country Mailing Information</b> (if outside USA)				<b>12. E-Mail Address</b> (if applicable)			
n/a				n/a			
<b>13. Telephone Number</b>		<b>14. Extension or Code</b>		<b>15. Fax Number</b> (if applicable)			
( ) -				( ) -			
<b>16. Federal Tax ID</b> (9 digits)		<b>17. TX State Franchise Tax ID</b> (11 digits)		<b>18. DUNS Number</b> (if applicable)		<b>19. TX SOS Filing Number</b> (if applicable)	
<b>20. Number of Employees</b>						<b>21. Independently Owned and Operated?</b>	
<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher						<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	

## SECTION III: Regulated Entity Information

<b>22. General Regulated Entity Information</b> (If "New Regulated Entity" is selected below this form should be accompanied by a permit application)			
<input checked="" type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information <input type="checkbox"/> No Change** (See below)			
<b>**If "NO CHANGE" is checked and Section I is complete, skip to Section IV, Preparer Information.</b>			
<b>23. Regulated Entity Name</b> (name of the site where the regulated action is taking place)			
Highland Village Georgetown LP			

<b>24. Street Address of the Regulated Entity:</b> (No P.O. Boxes)	2005 Birdcreek Drive, Suite 211						
	<b>City</b>	Temple	<b>State</b>	TX	<b>ZIP</b>	76502	<b>ZIP + 4</b>
<b>25. Mailing Address:</b>	2005 Birdcreek Drive, Suite 211						
	<b>City</b>	Temple	<b>State</b>	TX	<b>ZIP</b>	76502	<b>ZIP + 4</b>
<b>26. E-Mail Address:</b>							
<b>27. Telephone Number</b>	<b>28. Extension or Code</b>		<b>29. Fax Number (if applicable)</b>				
( ) -			( ) -				
<b>30. Primary SIC Code (4 digits)</b>	<b>31. Secondary SIC Code (4 digits)</b>	<b>32. Primary NAICS Code (5 or 6 digits)</b>		<b>33. Secondary NAICS Code (5 or 6 digits)</b>			
<b>34. What is the Primary Business of this entity?</b> (Please do not repeat the SIC or NAICS description.)							

Questions 34 – 37 address geographic location. Please refer to the instructions for applicability.

<b>35. Description to Physical Location:</b>	If driving North on I-35, Take exit 262 toward Williams Drive. Turn left onto Williams Dr and continue for 7.2 miles. Turn right onto CR 245 and continue for a mile. The destination will be on the SW corner of the intersection of CR 245 and Ronald Reagan Blvd.				
<b>36. Nearest City</b>	<b>County</b>	<b>State</b>	<b>Nearest ZIP Code</b>		
Georgetown	Williamson	TX	78633		
<b>37. Latitude (N) In Decimal:</b>	30.734661		<b>38. Longitude (W) In Decimal:</b>	-97.773847	
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
30	44	04.8	97	46	25.9

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form or the updates may not be made. If your Program is not listed, check other and write it in. See the Core Data Form instructions for additional guidance.

<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Industrial Hazardous Waste	<input type="checkbox"/> Municipal Solid Waste
		CZP		
<input type="checkbox"/> New Source Review – Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS	<input type="checkbox"/> Sludge
<input type="checkbox"/> Stormwater	<input type="checkbox"/> Title V – Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil	<input type="checkbox"/> Utilities
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:


#### SECTION IV: Preparer Information

<b>40. Name:</b>	Steger Bizzell - Chad W. Jones, P.E.		<b>41. Title:</b>	Project Engineer
<b>42. Telephone Number</b>	<b>43. Ext./Code</b>	<b>44. Fax Number</b>	<b>45. E-Mail Address</b>	
( 512 ) 930-9412	n/a	( n/a ) -	chad.jones@stegerbizzell.com	

#### SECTION V: Authorized Signature

**46.** By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 9 and/or as required for the updates to the ID numbers identified in field 39.

(See the Core Data Form instructions for more information on who should sign this form.)

<b>Company:</b>	Steger Bizzell	<b>Job Title:</b>	Project Engineer
<b>Name (In Print):</b>	Mr. Chad W. Jones, P.E.	<b>Phone:</b>	( 512 ) 930-9412
<b>Signature:</b>		<b>Date:</b>	2/10/25