May 22, 2025

City of Cedar Park 450 Cypress Creek Rd Cedar Park, TX 78613

RE: Cypress Creek Retail 703 Cypress Creek Rd Cedar Park, TX 78613

To whom it may concern:

Please accept this *Comment Response Letter* in reply to the Texas Commission on Environmental Quality's review, dated May 20, 2025, regarding the above referenced project's Contributing Zone Plan review. Original comments have been included below for reference. All Kimley-Horn responses are listed in **maroon**.

Sarah Patterson – <u>EAAdmin@tceq.texas.gov</u> - 512-239-7009

Contributing Zone Plan Application (TCEQ-10257)

TCEQ1. Please include the entire form. **Response: The entire form has been included in the submittal.**

TCEQ2. The following attachments are missing and must be included:

- Attachment A Road Map
- Attachment B USGS Quadrangle Map
- Attachment C Project Narrative
- Attachment D Factors Affecting Surface Water Quality
- Attachment E Volume and Character of Stormwater
- Attachment F Suitability Letter from Authorized Agent (if OSSF is proposed)
- Attachment G Alternative Secondary Containment Methods (if AST with an alternative method of secondary containment is proposed)
- Attachment H AST Containment Structure Drawings (if AST is proposed)
- Attachment I 20% or Less Impervious Cover Declaration (if project is multi-family residential, a school, or a small business and 20% or less impervious cover is proposed for the site)
- Attachment J BMPs for Upgradient Stormwater
- Attachment K BMPs for On-site Stormwater
- Attachment L BMPs for Surface Streams
- Attachment O Pilot-Scale Field Testing Plan, if BMPs not based on Complying with the Edwards Aquifer Rules: Technical Guidance for BMPs
- Attachment P Measures for Minimizing Surface Stream Contamination

Response: All the attachments have been included in the resubmittal.

Agent Authorization Form (TCEQ-0599)

TCEQ3. Missing and must be included. **Response: Agent Authorization Form is included in the resubmittal.**

Application Fee Form (TCEQ-0574)

TCEQ4. Missing and must be included. **Response: Application Fee Form is included in the resubmittal.**

KHA Project No. 069241731Page 2Core Data Form (TCEQ-10400)TCEQ5 Please include entire form.Response: Core Data Form is included in the resubmittal.

Should you have any questions or additional comments, please feel free to contact me using the information in my signature below.

Sincerely, KIMLEY-HORN AND ASSOCIATES, INC.

Homas

Thomas J. Lombardi Jr., P.E. (512) 774-6190

CONTRIBUTING ZONE PLAN

CYPRESS CREEK RETAIL Cedar Park, Williamson County, TEXAS

Prepared For:

Cypress Creek Fortune, LLC

3620 Aquamarine Dr Round Rock, TX 78681 (832-875-9525)

Prepared By:

KIMLEY-HORN AND ASSOCIATES, INC.

501 S Austin Avenue, Suite 1310 Georgetown, TX 78626 (512) 520-0768



Firm No. 928 KHA Project No. 065011800

May 2025

TABLE OF CONTENTS

Edwards Aquifer Application Cover Page	SECTION 1
Edwards Aquifer Application Cover Page	TCEQ-20705

Contributing Zone Plan Application	Section 2
CONTRIBUTING ZONE PLAN APPLICATION Road Map	
USGS Quadrangle Map	
Project Narrative	
Factors Affecting Surface Water Quality	
Volume and Character of Stormwater	
Suitability Letter from Authorized Agent	
Alternative Secondary Containment Methods	
•	· · · ·
AST Containment Structure Drawings	1 /
20% or Less Impervious Cover Waiver	
BMPs for Upgradient Stormwater	
BMPs for On-site Stormwater	
BMPs for Surface Streams	
Construction Plans	
Inspection, Maintenance, Repair and Retrofit Plan	
Pilot-Scale Field Testing Plan	
Measures for Minimizing Surface Stream Contamination	Attachment P
TEMPORARY STORMWATER SECTION.	Section 3
TEMPORARY STORMWATER SECTION	
Spill Response Actions	
Potential Sources of Contamination	Attachment B
Sequence of Major Activities	Attachment C
Temporary Best Management Practices and Measures	Attachment D
Request to Temporarily Seal a Feature, if sealing a feature	Attachment E
Structural Practices	
Drainage Area Map	
Temporary Sediment Pond(s) Plan and Calculation	
Inspection and Maintenance for BMPs	
Schedule of Interim and Permanent Soil Stabilization Practices	
Schedule of Interim and Permanent Soli Stabilization Practices	Allachment J (N/A)
ADDITIONAL FORMS	
COPY OF NOTICE OF INTENT	
AGENT AUTHORIZATION FORM	
APPLICATION FEE FORM	TCEQ-0574

CHECK PAYABLE to the "Texas Commission on Environmental Quality"

Texas Commission on Environmental Quality Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with <u>30 TAC 213</u>.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Cypress Creek Retail				il	2. Regulated Entity No.: N/A				
3. Customer Name: C	3. Customer Name: Cypress Creek Fortune LLC			C	4. Customer No.: N/A				
5. Project Type: (Please circle/check one)	<u>New</u>		Modi	Modification Extension			ision	Exception	
6. Plan Type: (Please circle/check one)	WPAP	<u>CZP</u>	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Reside	ntial	<u>Non</u> -	Non-residential 8. Sit		8. Sit	e (acres):	5.753 AC	
9. Application Fee:	\$5000		10. P	10. Permanent BMP(s):			5):	Water Quality	/Detention Pond
11. SCS (Linear Ft.):			12. AST/UST (No. Tanks):						
13. County:	Willian	ison	14. V	Vaters	hed:	14. Watershed:			-Brushy Creek

Application Distribution

Г

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region						
County:	Hays	Travis	Williamson			
Original (1 req.)		_	_X_			
Region (1 req.)		_	_X_			
County(ies)			_X_			
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA			
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin _X_Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock			

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)					
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

Austin Region

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

 Thomas Lombardi Jr., PE

 Print Name of Customer/Authorized Agent

 Annual formland for

 Signature of Customer/Authorized Agent

 Date

FOR TCEQ INTERNAL USE ONLY				
Date(s)Reviewed:	Date Administratively Complete:			
Received From:	Correct Number of Copies:			
Received By:	Distribution Date:			
EAPP File Number:	Complex:			
Admin. Review(s) (No.):	No. AR Rounds:			
Delinquent Fees (Y/N):	Review Time Spent:			
Lat./Long. Verified:	SOS Customer Verification:			
Agent Authorization Complete/Notarized (Y/N):	Payable to TCEQ (Y/N):			
Core Data Form Complete (Y/N):	Check: Signed (Y/N):			
Core Data Form Incomplete Nos.:	Less than 90 days old (Y/N):			

Contributing Zone Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Thomas Lombardi Jr

Date: <u>3/4/25</u>

Signature of Customer/Agent:

max forward of

Regulated Entity Name: Cypress Creek Retail

Project Information

- 1. County: Williamson
- 2. Stream Basin: Cluck Creek
- 3. Groundwater Conservation District (if applicable): _____
- 4. Customer (Applicant):

Contact Person: <u>Praveen Katapally</u> Entity: <u>Cypress Creek Fortune LLC</u> Mailing Address: <u>3620 Aquamarine Drive</u> City, State: <u>Round Rock, TX</u> Telephone: <u>832-875-9525</u> Email Address: <u>praveenkvl147@gmail.com</u>

Zip: <u>78681</u> Fax: _____

TCEQ-10257 (Rev. 02-11-15)

5. Agent/Representative (If any):

Contact Person: Thomas Lombardi Jr.Entity: Kimley-HornMailing Address: 501 S Austin Avenue, Suite 1310City, State: Georgetown, TXZip: 78626Telephone: 512-518-6534Fax: _____Email Address: thomas.lombardi@kimley-horn.com

6. Project Location:

 \boxtimes The project site is located inside the city limits of <u>Cedar Park</u>.

- The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.
- The project site is not located within any city's limits or ETJ.
- 7. The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

703/705 Cypress Creek Road,	Cedar Park, 7	FX 78613	(NE corner	of intersection	of Cypress
Creek Rd and Cluck Creek	Trl)				

- 8. Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
- 9. Attachment B USGS Quadrangle Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) clearly show:

Project site boundaries. USGS Quadrangle Name(s).

- 10. Attachment C Project Narrative. A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:
 - Area of the site Offsite areas
 - \square Impervious cover
 - \boxtimes Permanent BMP(s)
 - Proposed site use
 - Site history
 - Previous development
 - Area(s) to be demolished
- 11. Existing project site conditions are noted below:

Existing commercial site Existing industrial site

Existing residential site

Existing paved and/or unpaved roads

- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Not cleared)
- Other: _____
- 12. The type of project is:

	Residential: # of Lots:
	Residential: # of Living Unit Equivalents:
\boxtimes	Commercial
	Industrial
	Other:

13. Total project area (size of site): <u>5.82</u> Acres

Total disturbed area: <u>5.82</u> Acres

- 14. Estimated projected population: _____
- 15. The amount and type of impervious cover expected after construction is complete is shown below:

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	44,945	÷ 43,560 =	1.032
Parking	120,541.269	÷ 43,560 =	2.767
Other paved surfaces	11,685.777	÷ 43,560 =	0.268
Total Impervious Cover	177,172.046	÷ 43,560 =	4.07

Table 1 - Impervious Cover

Total Impervious Cover <u>4.07</u> ÷ Total Acreage <u>5.82</u> X 100 = <u>70</u>% Impervious Cover

16. Attachment D - Factors Affecting Surface Water Quality. A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

For Road Projects Only

Complete questions 18 - 23 if this application is exclusively for a road project.

🛛 N/A

TCEQ-10257 (Rev. 02-11-15)

18.	Туре	of	project:
-----	------	----	----------

TXDOT road project. County road or roads built to county specifications. City thoroughfare or roads to be dedicated to a municipality. Street or road providing access to private driveways. 19. Type of pavement or road surface to be used: Concrete Asphaltic concrete pavement Other: 20. Right of Way (R.O.W.): Length of R.O.W.: _____ feet. Width of R.O.W.: feet. L x W =_____Ft² ÷ 43,560 Ft²/Acre = _____ acres. 21. Pavement Area: Length of pavement area: feet. Width of pavement area: feet. $L \times W = Ft^2 \div 43,560 Ft^2/Acre = acres.$ Pavement area acres ÷ R.O.W. area acres x 100 = % impervious cover.

22. A rest stop will be included in this project.

A rest stop will not be included in this project.

23. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

24. Attachment E - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

25. Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.

🗌 N/A

26. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

Attachment F - Suitability Letter from Authorized Agent. An on-site sewage facility
will be used to treat and dispose of the wastewater from this site. The appropriate
licensing authority's (authorized agent) written approval is attached. It states that
the land is suitable for the use of private sewage facilities and will meet or exceed
the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285
relating to On-site Sewage Facilities.
Each lot in this project/development is at least one (1) acre (43,560 square feet) in
size. The system will be designed by a licensed professional engineer or registered
sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter
285.
Sewage Collection System (Sewer Lines):
The sewage collection system will convey the wastewater to the <u>Cedar Park Wastewater</u>
(name) Treatment Plant. The treatment facility is:
Existing.
Proposed.
∟ N/A
ormanant Above around Storage Tanks (ASTa) > 500

Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons

Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.

□N/A

27. Tanks and substance stored:

Table 2 - Tanks and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1			
2			
3			
4			
5			
	-	То	tal x 1.5 = Gallons

28. The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than

one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

Attachment G - Alternative Secondary Containment Methods. Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

Table 3 - Secondary Containment

Length (L)(Ft.)	Width(W)(Ft.)	Height (H)(Ft.)	L x W x H = (Ft3)	Gallons

Total: _____ Gallons

30. Piping:

All piping, hoses, and dispensers will be located inside the containment structure.
 Some of the piping to dispensers or equipment will extend outside the containment structure.

The piping will be aboveground

] The piping will be underground

- 31. The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of:
- 32. Attachment H AST Containment Structure Drawings. A scaled drawing of the containment structure is attached that shows the following:
 - Interior dimensions (length, width, depth and wall and floor thickness).
 - Internal drainage to a point convenient for the collection of any spillage.

Tanks clearly labeled

Piping clearly labeled

Dispenser clearly labeled

33. Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.

In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

Site Plan Requirements

Items 34 - 46 must be included on the Site Plan.

34. \square The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1'' = 40'.

35. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): <u>FEMA Flood Map FIRM Panel No. 48491C0605F (Revised Dec 20, 2019)</u>.

36. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.

- 37. \square A drainage plan showing all paths of drainage from the site to surface streams.
- 38. 🖂 The drainage patterns and approximate slopes anticipated after major grading activities.
- 39. \square Areas of soil disturbance and areas which will not be disturbed.
- 40. 🛛 Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 41. 🛛 Locations where soil stabilization practices are expected to occur.
- 42. Surface waters (including wetlands).

🛛 N/A

43. Locations where stormwater discharges to surface water.

There will be no discharges to surface water.

44. Temporary aboveground storage tank facilities.

Temporary aboveground storage tank facilities will not be located on this site.

45. Permanent aboveground storage tank facilities.

Permanent aboveground storage tank facilities will not be located on this site.

46. \square Legal boundaries of the site are shown.

Permanent Best Management Practices (BMPs)

Practices and measures that will be used during and after construction is completed.

47. Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.

🗌 N/A

- 48. These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 - The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.
 - A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____.

🗌 N/A

49. Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

🗌 N/A

50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

- The site will be used for low density single-family residential development but has more than 20% impervious cover.
- The site will not be used for low density single-family residential development.

51.	The executive director may waive the requirement for other permanent BMPs for multi-
	family residential developments, schools, or small business sites where 20% or less
	impervious cover is used at the site. This exemption from permanent BMPs must be
	recorded in the county deed records, with a notice that if the percent impervious cover
	increases above 20% or land use changes, the exemption for the whole site as described in
	the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing
	and Approval), may no longer apply and the property owner must notify the appropriate
	regional office of these changes.

 Attachment I - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. The site will not be used for multi-family residential developments, schools, or small business sites.
52. 🔀 Attachment J - BMPs for Upgradient Stormwater.
 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
53. 🔀 Attachment K - BMPs for On-site Stormwater.
 A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
54. Attachment L - BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.
⊠ N/A
55. Attachment M - Construction Plans. Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

🗌 N/A

56. Attachment N - Inspection, Maintenance, Repair and Retrofit Plan. A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:
Prepared and certified by the engineer designing the permanent BMPs and measures
 Signed by the owner or responsible party Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit. Contains a discussion of record keeping procedures
□ N/A
57. Attachment O - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
⊠ N/A
58. Attachment P - Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.
⊠ N/A
Responsibility for Maintenance of Permanent BMPs and

Measures after Construction is Complete.

- 59. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- 60. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development,

or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.


Administrative Information

- 61. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
 - The Temporary Stormwater Section (TCEQ-0602) is included with the application.

CYPRESS CREEK Retail CONTRIBUTING ZONE PLAN

ATTACHMENT A ROAD MAP

CONTRIBUTING ZONE PLAN ATTACHMENT A



KIEAU_C

SHARE .



THE PROJECT IS LOCATED WEST OF US HWY 183A AND NORTHEAST OF THE INTERSECTION OF CYPRESS CREEK ROAD AND CLUCK CREEK TRAIL, SOUTHEAST OF THE INTERSECTION BETWEEN CLUCK CREEK TRAIL AND RUSSET VALLEY DRIVE

703/705 CYPRESS CREEK RD, CEDAR PARK, TX 78613



ATTACHMENT B USGS QUADRANGLE MAP



The National Map OnDemand Topo

97.7633







Local Local State Route oute

7.5-MINUTE TOPO, TX 2024

PROJECT NARRATIVE

The Cypress Creek Retail project is located at the northeast corner of the intersection of Cypress Creek Road and Cluck Creek Trail in Cedar Park, Williamson County, Texas. The proposed project will add a stacked water quality and detention pond to account for the impervious cover associated with the development of the property (City of Cedar Park, 2024-24-SD). The site improvements also include development of five retail buildings and adding a detention pond on site to convey the Atlas-14 flows.

No portion of the site is located within the Federal Emergency Management Agency's 100-year floodplain according to Flood Insurance Rate Map number 48491C0605F, dated December 20, 2019, Williamson County, Texas. The site is located within the Edwards Aquifer Contributing Zone or Transition Zones according to the Texas Commission on Environmental Quality (TCEQ). The site is in the Turkey Creek-Brushy Creek watershed.

Per the Site Plan, the proposed water quality and detention basin will be designed with a project area of 5.82 acres, with 5.13 acres draining to the detention basin.

Per the Site Plan, 4.07 Acres of impervious cover were proposed and constructed under its site plan and CZP application

The wet basin proposed for this project will provide water quality and detention for the site plan with the City of Cedar Park; Cypress Creek Retail. Cypress Creek Commercial is proposed commercial office and business condos, associated parking, and utilities. The partial sedimentation pond has been designed in accordance with TCEQ water quality requirements for the 5.13 acres project area. The drainage basins include: a 5.13-acre drainage basin with 4.07 acres of impervious cover.

FACTORS AFFECTING SURFACE WATER QUALITY

Surface water quality can be affected by disturbance during construction and by development after construction. Soil disturbance from clearing and grubbing, and cut and fill operations can lead to discharge of sediment unless adequate temporary erosion control measures are in place. For this project, the use of silt fences and rock berms will prevent sediment from leaving the site. Siltation collected by the control measures will be cleaned from fences, berms, etc. on a routine schedule.

During construction, surface water quality may also be affected by a spill of hydrocarbons or other hazardous substances used in construction. The most likely instances of a spill of hydrocarbons and hazardous substance area:

- 1. Refueling construction equipment.
- 2. Performing operator-level maintenance, including adding petroleum, oils, or lubricants.
- 3. Unscheduled or emergency repairs, such as hydraulic fluid leaks.

Every effort will be taken to be cautious and prevent spills. In the event of a fuel or hazardous substance spill, the contractor is required to clean up the spill and notify the TCEQ. During business hours report spills to TCEQ's Austin Regional Office at (512) 339-2929, after business hours call 1-800-832-8224.

After construction is complete, impervious cover for the tract of land is the major reason for degradation of water quality. Impervious cover includes parking, driveways, future buildings and associate site improvements. Oil and fuel discharges from vehicles is anticipated. A partial sedimentation filtration pond is proposed to mitigate these features.

VOLUME AND CHARACTER OF STORMWATER

The subject site slopes generally toward the northside of the property, and the elevation ranges from 931 to 914 feet. Drainage from the property drains into an existing channel adjacent to the site to the North.

In the proposed condition a partial sedimentation basin with stacked detention will be constructed. Both the existing and proposed drainage area maps are provided within the construction plans included with this report.

The first flush of runoff will contain small amounts of oil, gas, and suspended solids, which will be captured and treated by the pond. The proposed basin will be deigned to provide water quality and detention.

The existing and proposed flows were analyzed using Atlas-14 rainfall data and compared the existing conditions. Flows were calculated using the SCS method and HEC-HMS modeling program. Below are the tables for the existing and proposed flows:

	EXISTING DRAINAGE AREA CALCULATIONS							
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₁₀₀ (CFS)
EX-1	5.82	5.9%	80	12.23	14.9	28.3	37.8	54.3
OS-1	0.46	80%	94	10.79	1.9	3.0	3.7	5.0

PROPOSED DRAINAGE AREA CALCULATIONS								
DRAINAGE AREA	AREA (ac.)	IMPERVIOUS COVER (%)	CN (COMPOSITE)	TC (MIN)	Q ₂ (CFS)	Q ₁₀ (CFS)	Q ₂₅ (CFS)	Q ₁₀₀ (CFS)
PR-1	5.13	78%	94	5	25.5	39.8	49.7	66.9
PR-2	0.69	10%	82	9.84	2.1	3.8	5.0	7.1
OS-1	0.46	80%	95	5	2.3	3.6	4.5	6.0

The proposed pond design uses the project site area of 5.13 acres. Based on the proposed improvements the site will require TSS load removal of 3,482 pounds.

The drainage basin that is conveyed to the proposed pond has a drainage are of 5.13 acres and 4 acres of impervious cover.

There is approximately 0.69 acres of the onsite drainage area that does not drain to the pond. This area includes approximately 0.07 acres of impervious cover from an existing parking lot.

The proposed water quality pond provides 23,737 cubic feet. The remaining volume of the pond is used for detention.

BMPs FOR UPGRADIENT STORMWATER

Stormwater originating up-gradient of the project site will travel through the site via sheet flow and proposed storm sewer to be conveyed to the proposed sedimentation filtration pond to the northwest of the site development. Please refer to the proposed drainage area map that is provided at the end of this report under the appropriate tab.

BMPs FOR ON-SITE STORMWATER

A wet basin will be utilized as the permanent best management practice on this site. All stormwater runoff from impervious areas will be collected by an underground storm sewer system or sheet flow and conveyed to the sedimentation filtration pond to the required overall removal of a minimum of 89% of the increase in Total Suspended Solids.

Construction plans, calculations, and specifications are provided at the end of this report under the appropriate tab.

BMPs FOR UPGRADIENT STORMWATER

There are no existing surface streams or sensitive features on site. All permanent BMPs have been designed to remove 80% of the increase in Total Suspended Solids as per current TCEQ requirements.

CONSTRUCTION PLANS

Calculations for the load removal requirements for the project and the load removal provided by the permanent BMP's are provided at the end of this report. The calculations have been signed and sealed by a professional engineer licensed in the state of Texas. The load removal requirements are derived from the equations from the technical guidance manual based upon project area and increase in impervious cover. All stormwater runoff from impervious areas will be treated by the proposed permanent BMP's to provide the overall required removal of 80% of the increase in Total Suspended Solids. Provided within the calculations is a summary of the amount of pollutant load required to be removed from the drainage areas and the amount of removal provided by the permanent BMP's.

Construction plans, details, specifications, calculations, and construction notes are provided in at the end of this report under the appropriate tab.

INSPECTION, MAINTENANCE, REPAIR AND RETROFIT PLAN

Inspection, Maintenance, Repair and Retrofit Plan

The inspection and maintenance plan outlines the procedures necessary to maintain the performance of the Permanent Best Management Practices for this project. It should be noted that the plan provides guidelines that may have to be adjusted dependent on site specific and weather related conditions.

It is the responsibility of the owner to provide the inspections and maintenance as outlined in the plan for the duration of the project. The owner will maintain this responsibility until it is assumed or transferred to another entity in writing. If the property is leased or sold, the responsibility for the maintenance will be required to be transferred through the lease agreement, binding covenants, closing documents, or other binding legal instrument.

Disposal of accumulated silt shall be accomplished following Texas Commission on Environmental Quality guidelines and specifications.

Maintenance records shall be kept on the installation, maintenance, or removal of items necessary for the proper operation of the facilities. All inspections shall be documented.

An amended copy of this document will be provided to the Texas Commission on Environmental Quality within thirty (30) days of any changes in the following information.

Responsible Party: Cypress Creek Fortune LLC

Mailing Address: <u>3620 Aquamarine Dr</u> City, State: Round Rock, Texas	Zip:78681			
Telephone: (832-875-9525)	Fax: N/A			

I, the owner, have read and understand the requirements of the attached Inspection and Maintenance Plan for the proposed Permanent Best Management Practices for my project. I acknowledge that I will maintain responsibility for the implementation and execution of the plan until the responsibility is transferred to or assumed by another party in writing through a binding legal instrument.

Signature of Responsible Part

Gaven

____ Date__3 24 2024

Suma Somland of

By:

Date 3/4/2025

CONTRIBUTING ZONE PLAN ATTACHMENT N

PAGE 1 OF 1

MEASURE FOR MINIMIZING SURFACE STREAM CONTAMINATION

Surface streams do not exist on site. All disturbed areas will be re-vegetated as soon as practical.

Spill Response Actions

If there is an accidental spill on site, the contractor shall respond with appropriate action. The contractor will be required to contact the owner and in turn the owner will contact the TCEQ in the event of a spill on site. In addition to the following guidance, reference the latest version of TCEQ's Technical Guidance Manual (TGM) RG-348 Section 1.4.16.

Cleanup

- Clean up leaks and spills immediately.
- Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
- Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- Use absorbent materials on small spills rather than hosing down or burying the spill.
- Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
 - Contain the spread of the spill.
 - Recover spilled materials.
 - Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

- Contain spread of the spill.
- Notify the project foreman immediately.
- If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at (512)339-2929
 - (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
 - For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

Potential Sources of Contamination

Potential Source: Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle dripping.

Preventative Measures: Vehicle maintenance will be performed within the construction staging area or a local maintenance shop.

Potential Source: Miscellaneous trash and litter from construction workers and material wrappings.

Preventative Measures: Trash containers will be placed throughout the site to encourage proper disposal of trash.

Potential Source: Silt leaving the site.

Preventative Measures: Contractor will install all temporary best management practices prior to start of construction including the stabilized construction entrance to prevent tracking onto adjoining streets.

Potential Source: Construction Debris.

Preventative Measures: Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case-by-case basis.

Potential Source: Soil and Mud from Construction Vehicle tires as they leave the site. **Preventative Measures:** A stabilized construction exit shall be utilized as vehicles leave the site. Any soil, mud, etc. carried from the project onto public roads shall be cleaned up within 24 hours.

Potential Source: Sediment from soil, sand, gravel and excavated materials stock piled on site. **Preventative Measures:** Silt fence shall be installed on the down gradient side of the stock piled materials. Reinforced rock berms shall be installed at all downstream discharge locations.

Potential Source: Portable toilet spill.

Preventative Measures: Toilets on the site will be emptied on a regular basis by the contracted toilet company.

Sequence of Major Activities

The installation of erosion and sedimentation controls shall occur prior to any excavation of materials or major disturbances on the site. The sequence of major construction activities will be as follows. Approximate acreage to be disturbed is listed in parentheses next to each activity.

Intended Schedule or Sequence of Major Activities:

- 1. Construct Access (<u>0.03</u> Acres)
- 2. Installation of Temporary BMPs (5.82 Acres)
- 3. Initiate Grubbing and Topsoil Stripping of Site (5.82 Acres)
- 4. Rough Subgrade Preparation (earthwork, grading, street and drainage excavation and embankment) (<u>5.82 Acres</u>)
- 5. Wet and Dry Utility Construction (<u>0.70</u> Acres)
- 6. Final Subgrade Preparation (2.849 Acres)
- 7. Installation of Base Materials (2.849 Acres)
- 8. Paving Activities (<u>2.849</u> Acres)
- 9. Site cleanup and Removal of Temporary BMPs (<u>5.82</u> Acres) Maximum total construction time is not expected to exceed 12 months.

Temporary Best Management Practices and Measures

- A. The stormwater originating upgradient from the site will surface flow to the existing storm sewer system and be conveyed to the rough cut wet pond area
- B. Temporary BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed on site to reduce vehicle "tracking" onto adjoining streets. A concrete washout pit will be used to collect all excess concrete during construction.

BMPs for this project will protect surface water or groundwater from turbid water, phosphorus, sediment, oil, and other contaminants, which may mobilize in stormwater flows by slowing the flow of runoff to allow sediment and suspended solids to settle out of the runoff.

Practices may also be implemented on site for interim and permanent stabilization. Stabilization practices may include but are not limited to: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of existing trees and vegetation, and other similar measures.

- C. There are no sensitive features or surface streams within the boundaries of the project. The temporary onsite BMPs will be used to treat stormwater runoff before it leaves the project and prevent pollutants from entering into surface streams or any sensitive features down gradient of the site.
- D. There were no sensitive features identified during the geologic assessment. However, the BMPs for this project are designed to allow water to pass through after sedimentation has occurred. Existing flow patterns will be maintained to any naturally-occurring sensitive features that are discovered during construction

Request to Temporarily Seal a Feature

There are no known naturally occurring sensitive features on the site, therefore a request for temporarily a feature is not included.

Structural Practices

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the downgradient sides of the property to prevent silt from escaping the construction area. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets.

A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck washout pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all the structural temporary BMP's are shown on the Overall Erosion Control Plan (sheet 8) and details and specifications are provided on the Erosion Control Details (sheet 32) which can be found at the end of this report in the construction plans.

Description of Temporary BMPs

Temporary Construction Entrance/Exit

The purpose of a temporary gravel construction entrance is to provide a stable entrance/exit condition from the construction site and keep mud and sediment off public roads. A stabilized construction entrance is a stabilized pad of crushed stone located at any point traffic will be entering or leaving the construction site from a public right-of-way, street, alley, sidewalk or parking area. This practice should be used at all points of construction ingress and egress.

Excessive amounts of mud can also present a safety hazard to roadway users. To minimize the amount of sediment loss to nearby roads, access to the construction site should be limited to as few points as possible and vegetation around the perimeter should be protected were access is not necessary. A rock stabilized construction entrance should be used at all designated access points.

Silt Fence

The purpose of a silt fence is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Silt fence is used during the period of construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This fence should remain in place until the disturbed area is permanently stabilized. Silt fence should not be used where there is a concentration of water in a channel or drainage way. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

Silt fencing within the site may be temporarily moved during the day to allow construction activity provided it is replaced and properly anchored to the ground at the end of the day. Silt fences on the perimeter of the site or around drainage ways should not be moved at any time.

Inlet Protection

Temporary inlet protection is a series of different measures that provide protection against silt transport or accumulation in storm sewer systems. This clogging can greatly reduce or completely stop the flow in the pipes. The different measures are used for different site conditions and inlet types.

Care should be taken when choosing a specific type of inlet protection. Field experience has shown that inlet protection that causes excessive ponding in an area of high construction activity may become so inconvenient that it is removed or bypassed, thus transmitting sediment-laden flows unchecked. In such situations, a structure with an adequate overflow mechanism should be utilized.

It should also be noted that inlet protection devices are designed to be installed on construction sites and not on streets and roads open to the public. When used on public streets these devices will cause ponding of runoff, which can cause minor flooding and can present a traffic hazard. An example of appropriate siting would be a new subdivision where the storm drain system is installed before the area is stabilized and the streets open to the general public. When construction occurs adjacent to active streets, the sediment should be controlled on site and not on public thoroughfares.

Concrete Washout Area

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.

Refer to Existing and Proposed Drainage Area Maps in Construction Plans

Temporary Sediment Pond's Plans and Calculations

The proposed pond will be rough cut to serve as a temporary sediment pond.

Inspection and Maintenance for BMPs

Inspections

Personnel Responsible for Inspections

The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification. Documentation of the inspector's qualifications is to be included in the attached Inspector Qualifications Log.

Inspection Schedule

The primary operator is required to choose one of the two inspections listed below.

- **Option 1:** Once every seven calendar days. If this alternative schedule is developed, then the inspection must occur regardless of whether or not there has been a rainfall event since the previous inspection.
- **Option 2:** Once every 14 calendar days and within 24 hours of the end of a storm event of two inches or greater.

The inspections may occur on either schedule provided that documentation reflects the current schedule and that any changes to the schedule are conducted in accordance with the following provisions: the schedule may be changed a maximum of one time each month, the schedule change must be implemented at the beginning of a calendar month, and the reason for the schedule change must be documented (e.g., end of "dry" season and beginning of "wet" season).

If option 2 is the chosen frequency of inspections a rain gauge must be properly maintained on site or the storm event information from a weather station that is representative of the site location. For any day of rainfall during normal business hours that measures 0.25 inches or greater, proper documentation of the total rainfall measured for that day must be recorded. Personnel provided by the permittee must inspect:

- disturbed areas of the construction site that have not been finally stabilized; areas used for storage of materials that are exposed to precipitation;
- structural controls (for evidence of, or the potential for, pollutants entering the drainage system);
- sediment and erosion control measures identified in the SWP3 (to ensure they are operating correctly); and
- locations where vehicles enter or exit the site (for evidence of off-site sediment tracking).

Reductions in Inspection Frequency

Where sites have been finally or temporarily stabilized or where runoff is unlikely due to winter conditions (e.g. site is covered with snow, ice, or frozen ground exists), inspections must be conducted at least once every month. In arid, semi-arid, or drought-stricken areas, inspections must be conducted at least once every month and within 24 hours after the end of a storm event of 0.5 inches or greater. A record of the total rainfall measured, as well as the approximate beginning and ending dates of winter or drought conditions resulting in monthly frequency of

CYPRESS CREEK Retail Contributing Zone Plan

inspections in the attached Rain Gauge Log.

In the event of flooding or other uncontrollable situations which prohibit access to the inspection sites, inspections must be conducted as soon as access is practicable.

Inspection Report Forms

Use the Inspection Report Forms given as a checklist to ensure that all required areas of the construction site are addressed. There is space to document the inspector's name as well as when the inspections regularly take place. The tables will document that the required area was inspected. (If there were any areas of concern, briefly describe them in this space with a more detailed description in the narrative section. Use the last table to document any discharges found during the inspections).

Describe how effective the installed BMPs are performing. Describe any BMP failures that were noted during the investigation and describe any maintenance required due to the failure. If new BMPs are needed as the construction site changes, the inspector can use the space at the bottom of the section to list BMPs to be implemented before the next inspection.

Describe the inspector's qualifications, how the inspection was conducted, and describe any areas of noncompliance in detail. If an inspection report does not identify any incidents of non-compliance, then it must contain a certifying signature stating that the facility or site is in compliance. The report must be signed by a person and in a manner required by 30 TAC 305.128. There is space at the end of the form to allow for this certifying signature.

Whenever an inspection shows that BMP modifications are needed to better control pollutants in runoff, the changes must be completed within seven calendar days following the inspection. If existing BMPs are modified or if additional BMPs are needed, you must describe your implementation schedule, and wherever possible, make the required BMP changes before the next storm event.

The Inspection Report Form functions as the required report and must be signed in accordance with TCEQ rules at 30 TAC 305.128.

Corrective Action

Personnel Responsible for Corrective Actions

Both Primary and Secondary Operators are responsible for maintaining all necessary Corrective Actions. If an individual is specifically identified as the responsible party for modifying the contact information for that individual should be documented in the attached Inspector Qualifications Log.

Corrective Action Forms

The Temporary BMPs must be modified based on the results of inspections, as necessary, to better control pollutants in runoff. Revisions must be completed within seven (7) calendar days following the inspection. If existing BMPs are modified or if additional BMPs are necessary, an implementation schedule must be described in the attached forms and wherever possible those changes implemented before the next storm event. If implementation before the next anticipated storm event is impracticable, these changes must be implemented as soon as practicable. Actions taken as a result of inspections must be properly documented by completing the corrective action forms given.

Schedule of Interim and Permanent Soil Stabilization

Construction practices shall disturb the minimal amount of existing ground cover as required for land clearing, grading, and construction activity for the shortest amount of time possible to minimize the potential of erosion and sedimentation from the site. Existing vegetation shall be maintained and left in place until it is necessary to disturb for construction activity. For this project the following stabilization practices will be implemented:

- 1. Hydraulic Mulch and Seeding: Disturbed areas subject to erosion shall be stabilized with hydraulic mulch and/or seeded and watered to provide interim stabilization. For areas that are not to be sodded as per the project landscaping plan, a minimum of 85% vegetative cover will be established to provide permanent stabilization.
- 2. Sodding and Wood Mulch: As per the project landscaping plan, Sodding and wood mulch will be applied to landscaped areas to provide permanent stabilization prior to project completion.

Records of the following shall be maintained:

- a. The dates when major grading activities occur;
- b. The dates when construction activities temporarily or permanently cease on a portion of the site; and
- c. The dates when stabilization measures are initiated.

Stabilization measures must be initiated as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, and except as provided in the following, must be initiated no more that fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased:

Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceased is precluded by snow cover or frozen ground conditions, stabilization measures must be initiated as soon as practical.

Where construction activity on a portion of the site is temporarily ceased and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of the site.

In arid areas (areas with an average rainfall of 0-10 inches), semiarid areas (areas with an average annual rainfall of 10 to 20 inches), and areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practical.

Maintenance

Below are some maintenance practices to be used to maintain erosion and sediment controls:

- All measures will be maintained in good working order. The operator should correct any damage or deficiencies as soon as practicable after the inspection, but in no case later than seven (7) calendar days after the inspection.
- BMP Maintenance (as applicable)

CYPRESS CREEK Retail CONTRIBUTING ZONE PLAN

- Sediment must be removed from sediment traps and sedimentation ponds no later than the time that design capacity has been reduced by 50%. For perimeter controls such as silt fences, berms, etc., the trapped sediment must be removed before it reaches 50% of the above-ground height.
- Silt fence will be inspected for depth of sediment, tears, to see of the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Drainage swale will be inspected and repaired as necessary.
- Inlet control will be inspected and repaired as necessary.
- Check dam will be inspected and repaired as necessary.
- Straw bale dike will be inspected and repaired as necessary.
- Diversion dike will be inspected and any breaches promptly repaired.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- If sediment escapes the site, accumulations must be removed at a frequency that minimizes off-site impacts, and prior to the next rain event, if feasible. If the permittee does not own or operate the off-site conveyance, then the permittee must to work with the owner or operator of the property to remove the sediment.
- Locations where vehicles enter or exit the site must be inspected for evidence of off-site sediment tracking.

To maintain the above practices, the following will be performed:

Maintenance and repairs will be conducted before the next anticipated storm event or as necessary to maintain the continued effectiveness of stormwater controls. Following an inspection, deficiencies should be corrected no later than seven (7) calendar days after the inspection.

Inspector Qualifications Log*

Inspector Name:
Qualifications (Check as appropriate and provide description): Training Course
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
□ Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
Training Course
 Supervised Experience Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
 Training Course Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description):
 Training Course Supervised Experience
□ Other
Inspector Name:
Qualifications (Check as appropriate and provide description): □ Training Course
Supervised Experience
□ Other

* The agent that performs the inspections should be knowledgeable of this general permit, familiar with the construction site, and knowledgeable of the SWPPP for the site. The contractor is to provide an inspector with a CPESC, CESSWI, or CISEC certification.

Amendm	ent	Log
--------	-----	-----

No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]

Construction Activity Sequence Log

Name of Operator	Projected dates Month/year	Activity Disturbing Soil clearing, excavation, etc.	Location on-site where activity will be conducted	Acreage being disturbed

*Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area. The Contractor is required to complete and update the schedule and adjust as necessary.

Stormwater Control Installation and Removal Log

Stormwater Control	Location On-Site	Installation Date	Removal Date

Stabilization Activities Log

Date Activity Initiated	Description of Activity	Description of Stabilization Measure and Location	Date Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures Initiated

Stabilization and erosion control practices may include, but are not limited to: establishing temporary or permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, and protecting existing trees and vegetation. List practices used where they are located, when they will be implemented, and whether they are temporary (interim) or permanent.

Inspection	Frequency Log	J
-		

Date	Frequency Schedule and Reason for Change
Dute	Trequency beneaute una neuson for enange

Rain Gauge Log

Date	Location of Rain Gauge	Gauge Reading
Dute	Location of hum outgo	ouuge neuunig
L		1

General Information							
Name of Project		Tracking No. Inspection Date					
Inspector Name, T Contact Informatio							
Present Phase of Co	onstruction						
Inspection Location inspections are require location where this ins being conducted)	ed, specify						
Reduced Freque - Once per n - Once per n	lency : V uency : C ency: nonth (for stabi nonth and with	-	0.25" rain id, or drought-stricken areas during seasona	ally dry periods or during drought)			
If yes, how did y	Was this inspection triggered by a 0.25" storm event? Yes No If yes, how did you determined whether a 0.25" storm event has occurred? Rain gauge on site Weather station representative of site. Specify weather station source: Total rainfall amount that triggered the inspection (in inches):						
If "yes", con - Describe	ine that any mplete the for the conditions	portion of your site was unsafe fo ollowing: that prevented you from conducting the in	-				
- Location(s) where condi	tions were found:					

	Condition and Effectiveness of Erosion and Sediment (E&S) Controls				
Type/Location of E&S Control	Repairs or Other Maintenance Needed?	Corrective Action Required?	Date on Which Maintenance or Corrective Action First Identified?	Notes	
1.	□Yes □No	□Yes □No			
2.	□Yes □No	□Yes □No			
3.	□Yes □No	□Yes □No			
4.	□Yes □No	□Yes □No			
5.	□Yes □No	□Yes □No			
6.	□Yes □No	□Yes □No			
7.	□Yes □No	□Yes □No			
8.	□Yes □No	□Yes □No			
9.	□Yes □No	□Yes □No			
10.	□Yes □No	□Yes □No			

	Condition and Effectiveness of Pollution Prevention (P2) Practices					
Type/Location of P2 Practices	Repairs or Other Maintenance Needed?	Corrective Action Required?	Identification Date	Notes		
1.	□Yes □No	□Yes □No				
2.	□Yes □No	□Yes □No				
3.	□Yes □No	□Yes □No				
4.	□Yes □No	□Yes □No				
5.	□Yes □No	□Yes □No				
6.	□Yes □No	□Yes □No				
7.	□Yes □No	□Yes □No				
8.	□Yes □No	□Yes □No				
9.	□Yes □No	□Yes □No				
10.	□Yes □No	□Yes □No				

Stabilization of Exposed Soil			
Stabilization Area	Stabilization Method Have You Initiated Stabilization? Notes		
1.		YES NO If yes, provide date:	
2.	YES NO If yes, provide date:		
3.		YES NO If yes, provide date:	
4.		YES NO If yes, provide date:	
5.		YES NO If yes, provide date:	
	Description of 1	Discharges	
	ner discharge occurring from any pain Information for each point of dischar	rt of your site at the time of the inspec rge:	ction? 🗌 Yes 🗌 No
Discharge Location			
1.	Describe the discharge:		
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		
2.	Describe the discharge:		
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		
3.	Describe the discharge:		
	At points of discharge and the channels and banks of surface waters in the immediate vicinity, are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:		

Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Contractor or Subcontractor:

Printed Name and Affiliation:

Certification and Signature by Permittee

Date:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Permittee or "Duly Authorized Representative":	Date:
Printed Name and Affiliation:	

Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)						
Name of Project	Tracking N	Jo.		Today's Date		
Date Problem First Discovered		Time Problem Firs	t Discovered			
Name and Contact Information of Individual Completing this Form						
A required stormwate	What site conditions triggered the requirement to conduct corrective action: A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3 The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards A prohibited discharge has occurred or is occurring 					
Provide a description of the	Provide a description of the problem:					
Deadline for completing c infeasible to complete wo	Deadline for completing corrective action (Enter date that is either: (1) no more than 7 calendar days after the date you discovered the problem, or (2) if it is infeasible to complete work within the first 7 days, enter the date that is as soon as practicable following the 7th day):					
	If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe:					
	Section (Complete this section <u>no later than 7 c</u>	o n B – Corre o alendar days afte	ctive Action Progr r discovering the condi	ress tion that triggered corrective action)		
Section B.1 – Why the	Problem Occurred					
Cause(s) of Problem (Add	Cause(s) of Problem (Add an additional sheet if necessary) How This Was Determined and the Date You Determined the Cause					
1.		1.				
2.		2.				
3.			3.			
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem						
List of Stormwater Contro Problem (Add an addition	ol Modification(s) Needed to Correct nal sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes		
1.			□Yes □No Date:			
2.			□Yes □No Date:			
3.			□Yes □No Date:			

Section A – Initial Report (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)						
Name of Project Tracking	No.		Today's Date			
Date Problem First Discovered		Time Problem Firs	t Discovered			
Name and Contact Information of Individual Completing this Form						
What site conditions triggered the requirement to conduct corrective action: A required stormwater control was never installed, was installed incorrectly, or not in accordance with the requirements in Part 2 and/or 3 The stormwater controls that have been installed and maintained are not effective enough for the discharge to meet applicable water quality standards A prohibited discharge has occurred or is occurring 						
Provide a description of the problem:	Provide a description of the problem:					
	Deadline for completing corrective action (Enter date that is either: (1) no more than 7 calendar days after the date you discovered the problem, or (2) if it is infeasible to complete work within the first 7 days, enter the date that is as soon as practicable following the 7th day):					
If your estimated date of completion falls after the 7-day deadline, explain (1) why you believe it is infeasible to complete work within 7 days, and (2) why the date you have established for making the new or modified stormwater control operational is the soonest practicable timeframe:						
	Section B – Corrective Action Progress (Complete this section <u>no later than 7 calendar days</u> after discovering the condition that triggered corrective action)					
Section B.1 – Why the Problem Occurred						
Cause(s) of Problem (Add an additional sheet if necessary)		How This Was Determined and the Date You Determined the Cause				
1.		1.				
2.		2.				
3.		3.				
Section B.2 – Stormwater Control Modifications to be Implemented to Correct the Problem						
List of Stormwater Control Modification(s) Needed to Correct Problem (Add an additional sheet if necessary)	Completion Date	SWPPP Update Necessary?	Notes			
1.		□Yes □No Date:				
2.		□Yes □No Date:				
3.		□Yes □No Date:				

Contractor or Subcontractor Certification and Signature

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Contractor or Subcontractor:

Printed Name and Affiliation:

Certification and Signature by Permittee

Date:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Permittee or "Duly Authorized Representative":	Date:
Printed Name and Affiliation:	

SECTION 3:

Temporary Stormwater Section

TEMPORARY STORMWATER SECTION

Cypress Creek Retail

Cedar Park, Texas

MAY 2025

Project Owner:

Cypress Creek Fortune, LLC 3620 Aquamarine Dr Round Rock, TX (832) 875-8525

Prepared By:

Kimley-Horn 501 S Austin Avenue, Suite 1301 Georgetown, Texas 78626 (512) 520-0768

Firm No. 928 KHA No. 067786605

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Thomas Lombardi Jr.

Date: 3/4/2025

Signature of Customer/Agent:

max formland fl

Regulated Entity Name: Cypress Creek Retail

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site:

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
 Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.

- Fuels and hazardous substances will not be stored on the site.
- 2. Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.

6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>Cluck Creek</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	 A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	 Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
	 For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided. For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used. For areas that will have more than 10 acres within a common drainage area
	 disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
N/A
12. Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
Soil Stabilization Practices
Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. \square All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

SPILL RESPONSE ACTIONS

(NOT APPLICABLE)

POTENTIAL SOURCES OF CONTAMINATION

(NOT APPLICABLE)

SEQUENCE OF MAJOR ACTIVITIES

- 1. Assign an environmental project manager who will be onsite greater than 90% of the time during construction activity and be responsible for the items listed under section 1.2.3.3 of the environmental criteria manual. **(0 acres of disturbed area)**
- 2. Install erosion controls and tree protection per approved plans. **(5.81 acres of disturbed area)**
- 3. The environmental project manager must contact the watershed protection department to schedule and hold pre-construction conference on site. **(5.81 acres of disturbed area)**
- 4. Rough cut all required or necessary ponds. Either the permanent outlet structure or a temporary outlet must be constructed prior to development of any embankment or excavation that leads to ponding conditions. The outlet system must consist of a low-level outlet and an emergency overflow meeting the requirements of the drainage criteria manual (section 8.3) and/or the environmental criteria manual (section 1.4.2.k) as required. The outlet system shall be protected from erosion and shall be maintained throughout the course of construction until final restoration is achieved. Temporary erosion and sedimentation controls will be inspected and maintained in accordance with the storm water pollution prevention plan (SWPPP) posted on the site. (5.81 acres of disturbed area)
- 5. Temporary control to be inspected and maintained weekly and prior to anticipated rainfall events and after rainfall events, as needed. **(5.81 acres of disturbance)**
- 6. Storm drains will be installed along with the other wet utilities after all rough grading operations are complete. Storm drains will be operational prior to any paving being constructed on site. **(5.81 acres of disturbance)**
- 7. Environmental project manager will schedule a mid-construction conference to coordinate changes in the construction schedule and evaluate effective ness of the erosion control plan after possible construction alterations to the site. Participants shall include the city inspector, project engineer, general contractor, and environmental project manager. The anticipated completion date and final construction sequence and inspection schedule will be coordinated with the appropriate city inspector. A mid construction conference is required for each phase, if phasing is proposed, with the watershed protection department staff, which will be coordinated based upon completion of buildings, drainage facilities, water quality controls and temporary erosion controls by phase. (5.81 acres of disturbance)
- 8. Complete and clean out permanent erosion control, filter media will be installed prior to /concurrently with rev-vegetation of site. Re-vegetate disturbed areas including removal of temporary erosion /sedimentation controls and tree protection. Restore any areas disturbed during removal of erosion/sedimentation controls. **(5.81 acres of disturbance)**

Construction Activity Schedule

Activities	Start Date	Finish Date
1. Assign Environmental Project Manager		
2. Install Erosion Controls and Tree Protection		
3. Environmental Project Manager to Contact the Watershed Protection Department		
4. Rough Cut All Required or Necessary Ponds		
5. Temporary Control to be Inspected and Maintained Weekly		
6. Storm Drain and Wet Utility Installation		
7. Environmental Project Manager to Schedule Mid- Construction Conference		
8. Complete and Clean Out Permanent Erosion Control		

*Construction activity sequences for linear projects may be conducted on a rolling basis. As a result, construction activities may be at different stages at different locations in the project area.

The Contractor is required to complete and update the schedule and adjust as necessary.

TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

All runoff directed to the stream will be treated per TCEQ requirements and no increase in peak flows are anticipated. The project site is upstream of Cluck Creek. All drainage from the project site will be conveyed into Cluck Creek via private storm infrastructure in compliance with TCEQ and City of Cedar Park regulations. These procedures will limit erosion and contamination of the surface stream. All disturbed areas will be re-vegetated as soon as practical. Temporary erosion controls will be utilized during construction to reduce the potential for construction related run-off to enter the creek.

Best Management Practice (BMP)	In Use	Maintained Post Construction?
Tree Protection		
Triangular Sediment Filter Dike		
Rock Berm		
Dry Stack Rock Wall		
Storm Inlet Sediment Trap		
Tree Wells		
Silt Fence		
Dust Control		
Silt Fence and J-Hooks		
Stabilized Construction Entrance		
Grate Inlet Protection		
Curb Inlet Protection		
Concrete Truck Washout Pit		
Mulch Sock		
Temporary Dewatering Skimmer		


REQUEST TO TEMPORARILY SEAL A FRACTURE

STRUCTURAL PRACTICES


A permanent water quality and detention pond will be utilized as a best management practice on-site to intercept disturbed soils from leaving the site via stormwater runoff. All stormwater runoff from impervious areas will be collected by an underground storm sewer system and routed through the structures to provide the required overall removal of 80% of the increase in Total Suspended Solids.

Best Management Practice (BMP)	In Use	Maintained Post Construction?
Water Quality/Detention Pond		

DRAINAGE AREA MAP



	EXISTING DRAINAGE AREA CALCULATIONS											
RD. N	DRAINAGE AREA	AREA (ac.)	AREA (SQ M)	IMPERVIOUS COVER (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	LAG (MIN)	Q ₂ (CFS)
	EX-1	5.82	0.00909	0.07	1.2%	98	99%	80	80.2	12.23	7.34	14.9
	OS-1	0.46	0.00072	0.37	80.0%	98	20%	80	94.4	5.11	3.07	1.9




<u>NOTES</u>:


- 1. EXISTING CONDITIONS ASSUMED TO BE PREDEVELOPED CONDITIONS OF DRAINAGE AREAS EX-1 AND OS-1. USING ATLAS 14 RAINFALL DATA FOR
- CEDAR PARK.
 THE FLOW OFF THE SITE HAS NOT BEEN INCREASED FROM THE EXISTING CONDITION.


ENTRATION						
LOW CONCENTRATED FLOW			CH	IANNEL FLC	W	
S (FT/FT)	L (FT)	T2 (MIN)	V (FT/S)	L (FT)	T4 (MIN)	TOTAL TC (MIN)
0.029	527.0	3.22	5.00	0.00	0.00	12.23
0.029	570.0	3.47	5.00	0.00	0.00	5.11

Unpaved $T_t = \frac{L}{(60(16.1345)(s^{0.5}))}$ Paved $T_t = \frac{L}{(60(20.3282)(s^{0.5}))}$



S)	0 (CES)	0 (058)	Q ₁₀₀ (CFS)
3)	Q ₁₀ (CF3)	Q ₂₅ (CF3)	Q ₁₀₀ (CF3)
	28.3	37.8	54.3
	3.0	3.7	5.0





								.
		[LEO	GEND]	B
	X-1 AREA DESIGNATOR 9.9 ac AREA IN ACRES 5.5 cfs Q100 FLOW IN CFS							DATE
				F	PROPERTY LIN PROPOSED STO EXISTING STOF PROPOSED DR PROPOSED STO PROPOSED STO	e DRM DRAIN LIN M DRAIN LINE AINAGE DIVIDE DRM DRAIN INI DRM DRAIN MA	E LET NHOLE	REVISIONS
		-	555 —	F	PROPOSED STO PROPOSED FLO PROPOSED CO	OW DIRECTION		ġ Ż
		_	— — — 555 —	E	EXISTING CONT	TOUR		ODD SUITE 100 -1791 S, INC.
	<u>NC</u> 1.	<u>DTES:</u> THE FLOW (CONDITION.	،	40' PHIC SCALE 4 HAS NOT BEE		FROM THE EX	XISTING	HWEST PARKWAY, BUILDING 3, S AUSTIN, TX 78735 512–646–2237 FAX: 512–418 WWW.KIMLEY-HORN.COM KIMLEY-HORN AND ASSOCIATE TBPE Firm No. 928
ION								301 SOUTH PHONE: © 2025
FT)	L (FT) 368.0		I) V (FT/S)	L (FT)	T4 (MIN)	TOTAL TO 5.00 9.84)	
ed T	$T_t = L_{j}$	0.00	282)(<i>s</i> ^{0.5})))		5.00		KHA PROJECT 065011800 DATE MAY 2025 MAY 2025 Scale: AS SHOWN Designed BY: IC DRAWN BY: IC DRAWN BY: TLJ
(COM	CN POSITE) 94.0	TC (MIN) 5.00	LAG (MIN) 3.00	Q ₂ (CFS) 25.5	Q ₁₀ (CFS) 39.8	Q ₂₅ (CFS) 49.7	Q ₁₀₀ (CFS) 66.9	PROPOSED DRAINAGE AREA MAP
	31.8 94.5	9.84 5.00	5.91 3.00	2.1 2.3	3.8 3.6	5.0 4.5	7.1 6.0	

PRESS CREI COMMERCIAL CITY OF CEDAR PARK LIAMSON COUNTY, TEXA \succ \mathbf{O} SHEET NUMBER 210F 44 2024-42-SD

 $O \odot =$

 \geq

TEMPORARY SEDIMENT POND(S) PLANS AND CALCULATIONS

INSPECTION AND MAINTENANCE FOR BMPS

SCHEDULE FOR INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

Kimley **»Horn**

SECTION 4: Additional Forms

Agent Authorization Form

Additional Forms (TCEQ-0599)

Agent Authorization Form

For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

I	Praveen Katapally	
	Print Name	
	Owner	,
	Title - Owner/President/Other	
of	Cypress Creek Fortune LLC	
	Corporation/Partnership/Entity Name	
have authorized	Thomas Lombardi Jr	
	Print Name of Agent/Engineer	
of	Kimley-Horn and Associates	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

TCEQ-0599 (Rev.04/01/2010)

SIGNATURE PAGE:

Applicant's Signature

2024 Date

THE STATE OF LEXAS § County of Williamson §

BEFORE ME, the undersigned authority, on this day personally appeared <u>Proven</u> Katapally known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 7 day of sept. ,2024

NOTARY PUBLIC

HETAL PATEL My Notary ID # 124406090 Expires November 27, 2026

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 11,27,2026

Application Fee Form

Application Fee Form

Texas Commission on Environment	tal Quality			
Name of Proposed Regulated Entity	r: <u>Cypress Creek Retai</u>	<u>l</u>		
Regulated Entity Location:				
Name of Customer: Cypress Creek I	Fortune LLC			
Contact Person: <u>Madhuri Movva</u>	Phor	ie: <u>832-875-9525</u>		
Customer Reference Number (if iss				
Regulated Entity Reference Numbe	r (if issued):RN			
Austin Regional Office (3373)				
Hays	Travis	×	illiamson	
San Antonio Regional Office (3362))			
Bexar	Medina		valde	
Comal	 Kinney			
Application fees must be paid by ch	Application fees must be paid by check, certified check, or money order, payable to the Texas			
Commission on Environmental Qua				
form must be submitted with your	fee payment. This p	ayment is being submi	itted to:	
🔀 Austin Regional Office	S	an Antonio Regional C	office	
Mailed to: TCEQ - Cashier	C	Vernight Delivery to: 1	rceQ - Cashier	
Revenues Section	1	12100 Park 35 Circle		
Mail Code 214	В	uilding A, 3rd Floor		
P.O. Box 13088	Д	ustin, TX 78753		
Austin, TX 78711-3088	()	512)239-0357		
Site Location (Check All That Apply):			
Recharge Zone	🛛 Contributing Zone	Transi	tion Zone	
Type of Plan		Size	Fee Due	
Water Pollution Abatement Plan, C	ontributing Zone			
Plan: One Single Family Residential	Dwelling	Acres	\$	
Water Pollution Abatement Plan, C	ontributing Zone			
Plan: Multiple Single Family Resider	ntial and Parks	Acres	\$	
Water Pollution Abatement Plan, C	ontributing Zone			
Plan: Non-residential	5.753 Acres	\$ 5000		
Sewage Collection System		L.F.	\$	
Lift Stations without sewer lines		Acres	\$	
Underground or Aboveground Stora	age Tank Facility	Tanks	\$	
Piping System(s)(only)		Each	\$	
Exception		Each	\$	
Extension of Time		Each	\$	
\bigcirc 1				

Signature:

Date: <u>2/7/25</u>

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150

Check Payable to the "Texas Commission on Environmental Quality"



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)					
New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)					
Renewal (Core Data Form should be submitted with the	e renewal form)	Other			
2. Customer Reference Number (if issued) Follow this link to search for CN or RN numbers in		3. Regulated Entity Reference Number (if issued)			
CN	RN				

SECTION II: Customer Information

4. General Cu	istomer li	nformat	ion	5. Effective	Date for C	ustome	er Inf	ormation	Updat	es (mm/dd/	′уууу)		02/06/2025
New Custor		(Verifiahl		pdate to Custo			nntrol		•	egulated Ent	tity Own	ership	
		-		-									
				-	utomatical	lly base	ed on	what is c	urrent	and active	with th	ne Texas Seci	retary of State
(SOS) or Texa	is comptr	oller of l	Ρυδιίς Αςζοι	ints (CPA).									
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John) If new Customer, enter previous Customer below:						er below:							
Cypre	Cypress Creek Fortune LLC												
7. TX SOS/CP	A Filing N	lumber		8. TX State	Tax ID (11 c	ligits)			9. Fe	deral Tax I	D	10. DUNS N	Number (if
08054	70625								(9 dig	its)		applicable)	
00034	12030												
											1		
11. Type of C	ustomer:		Corporat	tion				Indivic	lual		Partne	ership: 🗌 Gen	eral 🔀 Limited
Government:	City	County 🗌	Federal	Local 🗌 State	e 🗌 Other			Sole P	roprieto	orship	🗌 Otl	her:	
12. Number o	of Employ	rees							13. l	ndependen	ntly Ow	ned and Ope	erated?
⊠ 0-20 □ 2	21-100 [101-25	50 🗌 251-	500 🗌 501	and higher				X Ye	es (🗌 No		
14. Customer	r Role (Pro	posed or	Actual) – as i	t relates to the	Regulated E	ntity list	ted on	n this form.	Please	check one of	the follo	owing	
Owner		Оре	erator	Ov	vner & Opera	ator				Other:			
Occupation	al Licensee	🗌 Re	esponsible Pa	rty 🗌	VCP/BSA Apj	plicant							
15. Mailing	Cypre	ess Cr	eek For	tune LLC									
	3620 Aqı	uamarine	Dr										
Address:	ess: City Round Rock State TX				ZIP	78681		ZIP + 4					
16. Country M	16. Country Mailing Information (if outside USA)					17. E-Mail Address (if applicable)							
19 Tolophon	o Numbo	r		.	L9. Extensio	on or C	Code 20 Few Number (Cov Partic)						
18. Telephone Number				LJ. EXLENSIO		20. Pa			20. Fax N	. Fax Number (if applicable)			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on	this
form. See the Core Data Form instructions for additional guidance.	
TCEQ-10400 (11/22) Page	je 2

)

-

(

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.) 🛛 New Regulated Entity 🔄 Update to Regulated Entity Name 🔄 Update to Regulated Entity Information The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC). 22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.) **Cypress Creek Retail** 25. Description to **Physical Location:** 26. Nearest City Nearest ZIP Code State Cedar Park ΤХ 78613 Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy). 27. Latitude (N) In Decimal: 28. Longitude (W) In Decimal: 30.495067 97.826494 Degrees Minutes Seconds Minutes Seconds Degrees 97 30 49 29 42.24 35.38 29. Primary SIC Code 30. Secondary SIC Code 32. Secondary NAICS Code **31. Primary NAICS Code** (5 or 6 digits) (4 digits) (4 digits) (5 or 6 digits) 45811 3599 3585 45511 33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.) General retail sales 703 Cypress Creek Road 34. Mailing Address: City Cedar Park State ZIP + 4TΧ ZIP 78613 35. E-Mail Address: 36. Telephone Number 37. Extension or Code 38. Fax Number (if applicable)

)

-

(

()	-

(

23. Street Address of the Regulated Entity:	3620 Aquam	arine Dr						
<u>(No PO Boxes)</u>	City	Round Rock	State	ТХ	ZIP	78681	ZIP + 4	
24. County	Williamson							
If no Street Address is provided, fields 25-28 are required.								

Dam Safety	Districts	Edwards Aquifer	Emissions Inventory Air	Industrial Hazardous Waste
Municipal Solid Waste	New Source Review Air	OSSF	Petroleum Storage Tank	D PWS
Sludge	Storm Water	Title V Air	Tires	Used Oil
Voluntary Cleanup	U Wastewater	Wastewater Agriculture	Water Rights	Other:

SECTION IV: Preparer Information

40. Name:	Thomas Lombardi Jr., PE			41. Title:	Project Manager	
42. Telephone	one Number 43. Ext./Code 44. Fax Number		44. Fax Number	45. E-Mail Address		
(512)518 6	(512)518 6534 () -		Thomas	s.Lombardi@Kimley-Horn.com		

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Kimley-Horn	Proje	ect Manager			
Name (In Print):	Thomas Lombardi Jr.		Phone:	(512)518 6534		
Signature:	Summa formband i the		Date:	2/6/25		

PROJECT SUMMARY THE CYPRESS CREEK COMMERCIAL PROJECT PROPOSED A COMMERCIAL DEVELOPMENT WITH ASSOCIATED INFRASTRUCTURE ON A 5.82-ACRE SITE

THE PROPOSED 5 BUILDINGS WILL CONSIST OF 44,945 GSF OF GROUND FLOOR COMMERCIAL USE. THIS PROJECT WILL ALSO INCLUDE THE CONSTRUCTION OF UTILITIES, DRIVEWAYS, AND PARKING NECESSARY TO SERVE THE DEVELOPMENT.

GENERAL PLAN NOTES

- ALL RESPONSIBILITY FOR THE ACCURACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS THE CITY OF CEDAR PARK MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.
- NO PORTION OF THIS SITE IS LOCATED WITHIN THE 100-YEAR FLOODPLAIN. FIRM PANEL NO. 48491C0605F, WILLIAMSON COUNTY, TEXAS AND INCORPORATED AREAS, MAP REVISED DECEMBER 20, 2019.
- WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY CITY OF CEDAR PARK, CONDITIONED UPON ALL FEES AND CHARGES ARE PAID.
- 4. THERE ARE NO NATURAL SLOPES ON THIS SITE IN EXCESS OF 15%.
- THERE ARE NO KNOWN CRITICAL ENVIRONMENTAL FEATURES ON THIS SITE
- NO STRUCTURES CAN BE BUILT WITHIN WATER & WASTEWATER EASEMENTS.
- RELEASE OF THIS APPLICATION DOES NOT CONSTITUTE A VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL WHETHER OR NOT THE APPLICATION IS REVIEWED FOR CODE COMPLIANCE BY CITY ENGINEERS.
- AS PART OF THIS SITE PLAN, THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO BE ON SITE AT ALL TIMES.
- THIS SITE IS NOT LOCATED IN THE EDWARDS AQUIFER CONTRIBUTING ZONE AS DEFINED BY THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ).
- APPROVAL OF THESE PLANS BY THE CITY OF CEDAR PARK INDICATES COMPLIANCE WITH APPLICABLE CITY REGULATIONS ONLY. APPROVAL BY OTHER GOVERNMENTAL ENTITIES MAY BE REQUIRED PRIOR TO THE STAR OF CONSTRUCTION. THE APPLICANT IS RESPONSIBLE FOR DETERMINING WHAT ADDITIONAL APPROVALS MAY BE NECESSARY
- 11. THIS PROJECT IS SUBJECT TO THE 2021 INTERNATIONAL FIRE CODE WITH AMENDMENTS APPROVED BY THE CITY OF CEDAR PARK

CIVIL SITE DEVELOPMENT PLANS FOR **CYPRESS CREEK COMMERCIAL** 703/705 CYPRESS CREEK ROAD OWNER/DEVELOPER NAME AND ADDRESS CYPRESS CREEK FORTUNE LLC CEDAR PARK, TX 78613 3620 AQUAMARINE DR, ROUND ROCK, TX 78681 CONTACT: MADHURI MOVVA PH: (832) 875-9525 ACREAGE 5.822 ACRES

2.953 ACRES

TOTAL IMPERVIOUS COVER

LAND USE SUMMARY COMMERCIAL - 44,945 SF

WATERSHED: **CLUCK CREEK WATERSHED**

SUBMITTAL DATE FEBRUARY 3, 2025

TABS REGISTRATION NO.: 2025008197

TCEQ APPROVAL

CONTRIBUTING ZONE PLAN: TCEQ LETTER DATED XXXXXX EDWARDS AQUIFER PROTECTION PROGRAM ID NO. XXXX REGULATED ENTITY NO. RNXXXXX ZONING: GENERAL BUSINESS (GB)

		REVI	SIONS/CC	RRECTIONS	5		
NO.	DESCRIPTION	REVISE (R) VOID (V) ADD (A) SHEET NO.'S	TOTAL NO. SHEETS IN PLAN SET	NET CHANGE IMP. COVER (SQ. FT.)	TOTAL SITE IMP. COVER (SQ. FT.)/%	CITY OF CEDAR PARK APPROVAL DATE	DATE IMAGED

LEGAL DESCRIPTION

EMERSON COMM # 2 RESUB, LOT 102, ACRES 3.85

S3325 - BUTTERCUP CREEK IND PARK RESUB LOT 2, LOT 1, ACRES 1.972

DESIGNERS

ARCHITECT MAT DESIGN STUDIO 14618 MANSFIELD DAM CT AUSTIN, TX 78734 PH. (469) 951-0614

LANDSCAPE ARCHITECT GREEN EYE STUDIO STACIE E. HOLT AUSTIN, TX PH. (512) 484-1105

SURVEYOR DELTA LAND SURVEYING LARRY W. BUSBY 14900 AVERY RANCH BLVD, STE C200 #241 AUSTIN, TX 78717 PH. (512) 781-9800

LISTS OF CONTACTS:

WATER & SANITARY SEWER CITY OF CEDAR PARK 450 CYPRESS CREEK RD CEDAR PARK, TX 78613 PH. (512) 401-5300

STORM SEWER CITY OF CEDAR PARK PUBLIC WORKS DEPARTMENT 2401 BRUSHY CREEK LP CEDAR PARK, TX 78613 PH. (512) 401-5550


CEDAR PARK FIRE DEPARTMENT 450 CYPRESS CREEK RD CEDAR PARK, TX 78613 PH. (512) 401-5220

TEXAS GAS SERVICE LINDA BARGAR 5613 AVENUE F **AUSTIN, TX 78751** PH. (512) 465-1134 LBARGAR@TXGAS.COM

ELECTRIC PEDERNALES ELECTRIC **1949 W WHITESTONE BLVD** CEDAR PARK, TX 78613 PH. (512)331-8883

PREPARED B 5301 SOUTHWEST PARKWAY, BUILDING 2, SUITE 100 Tel. No. (512) 626-2237

AUSTIN TEXAS 78735 CERTIFICATE OF REGISTRATION #928 SP-42-SD



VICINITY MAP SCALE: 1" = 500'

MAPSCO: 1489 TABS: 2025008197

MAY 2025

THIS NOTE IS BEING PLACED ON THE PLAN SET IN PLACE OF A TEMPORARY TRAFFIC CONTROL STRATEGY WITH THE FULL UNDERSTANDING THAT, AT A MINIMUM OF 6 WEEKS PRIOR TO THE START OF CONSTRUCTION, A TEMPORARY TRAFFIC CONTROL PLAN MUST BE REVIEWED AND APPROVED BY THE RIGHT OF WAY MANAGEMENT DIVISION. THE OWNER/REPRESENTATIVE FURTHER RECOGNIZES THAT A REVIEW FEE, AS PRESCRIBED BY THE MOST CURRENT VERSION OF THE CITY'S FEE ORDINANCE, SHALL BE PAID EACH TIME A PLAN OR PLAN REVISION IS SUBMITTED TO RIGHT OF WAY MANAGEMENT DIVISION FOR REVIEW. THE FOLLOWING MUST BE TAKEN INTO CONSIDERATION WHEN DEVELOPING FUTURE TRAFFIC CONTROL STRATEGIES:

PEDESTRIAN AND BICYCLE TRAFFIC ACCESS MUST BE MAINTAINED AT ALL TIMES, UNLESS OTHER WISE AUTHORIZED BY RIGHT OF WAY MANAGEMENT.

NO LONG-TERM LANE CLOSURES WILL BE AUTHORIZED, UNLESS RIGHT OF WAY MANAGEMENT DETERMINES THAT ADEQUATE ACCOMMODATIONS HAVE BEEN MADE TO MINIMIZE TRAFFIC IMPACT.

PROJECT SHOULD BE PHASED SO THAT UTILITY INSTALLATION MINIMALLY IMPACTS EXISTING OR TEMPORARY PEDESTRIAN FACILITIES.






SHEET INDEX

Sheet Number	Sheet Title
1	COVER SHEET
2	FINAL PLAT
3	CITY OF CEDAR PARK GENERAL NOTES
4	KIMLEY-HORN GENERAL NOTES
5	SURVEY SHEET
6	EXISTING CONDITIONS AND DEMO PLAN
7	TREE LIST
8	EROSION CONTROL PLAN
9	OVERALL SITE PLAN
10	SITE PLAN (SHEET 1 OF 2)
11	SITE PLAN (SHEET 2 OF 2)
12	FIRE PROTECTION PLAN
13	FIRE PROFILE VIEW
14	FIRE PROTECTION NOTES
15	PAVING PLAN
16	PHOTOMETRIC PLAN
17	OVERALL GRADING PLAN
18	GRADING PLAN (SHEET 1 OF 2)
19	GRADING PLAN (SHEET 2 OF 2)
20	EXISTING DRAINAGE AREA MAP
21	PROPOSED DRAINAGE AREA MAP
22	OVERALL STORM PLAN
23	STORM PLAN (SHEET 1 OF 2)
24	STORM PLAN (SHEET 2 OF 2)
25	POND PLAN
26	POND PROFILE
27	POND DETAILS
28	WASTEWATER PLAN
29	OVERALL WATER PLAN
30	WATER PLAN (1 OF 2)
31	WATER PLAN (2 OF 2)
31	EROSION CONTROL DETAILS
33	SITE DETAILS
34	STORM DRAIN DETAILS
35	UTILITY DETAILS (SHEET 1 OF 2)
36	UTILITY DETAILS (SHEET 2 OF 2)
37	LANDSCAPE PLAN - 1
38	LANDSCAPE PLAN - 2
39	
40	
41	BUILDING 2 ELEVATION BUILDING 3 ELEVATION
42	BUILDING 4 ELEVATION
43	BUILDING 5 ELEVATION



BENCHMARKS MAG NAIL WITH WASHER MARKED "JPH

- BENCHMARK" AT BACK OF SIDEWALK +/-65' EAST OF MOST SOUTHERLY SOUTHEAST CORNER OF LOT 1 IN RESUBMISSION OF BUTTERCUP CREEK INDUSTRIAL PARK, LOT 2 ELEVATION = 926.27' 3" BRASS DISK IN CONCRETE. STANDING
- ON WEST ROW OF CLUCK CREEK TRL. NORTH OF CYPRESS CREEK ROD. LOOKING NORTH TO RAMBLING TRAIL ELEVATION = 928.55



REPLAT OF LOT 102 RESUBDIVISION OF EMERSON COMMERCIAL NO. 2 AND LOT 1 RESUBDIVISION OF BUTTERCUP **CREEK INDUSTRIAL PARK, LOT 2** SHORT FORM FINAL PLAT

VICINITY MAP

SCALE: 1" = 2000'

LEGAL DESCRIPTION BEING ALL OF LOT 102, RESUBDIVISION OF EMERSON COMMERCIAL NO. 2, A LEGAL SUBDIVISION ACCORDING TO THE PLAT OF RECORD UNDER CAB. I, SL. 221, AND ALL OF LOT 1, RESUBDIVISION OF BUTTERCUP CREEK INDUSTRIAL PARK, LOT 2, A LEGAL SUBDIVISION ACCORDING TO THE PLAT OF RECORD UNDER CAB. I, SL. 118, SITUATED IN THE R. DUTY SURVEY, ABSTRACT 183, WILLIAMSON COUNTY, TEXAS.

OWNER INFORMATION: CYPRESS CREEK FORTUNE LLC

KIMLEY-HORN AND ASSOCIATES, INC.

SURVEYOR INFORMATION: KIMLEY-HORN AND ASSOCIATES, INC.

705 CYPRESS CREEK ROAD

CEDAR PARK, TX 78613

ENGINEER INFORMATION:

6800 BURLESON ROAD

AUSTIN, TX 78744

(512) 616-9942

BUILDING 312, SUITE 150

10814 JOLLYVILLE ROAD

CAMPUS IV, SUITE 200

FILING DATE: 05/08/2025

AUSTIN, TX 78759

(512) 418-1771

STANDARD NOTES:

- CONSTRUCTION PLANS AND SPECIFICATIONS FOR ALL SUBDIVISION IMPROVEMENTS SHALL BE REVIEWED AND APPROVED BY THE CITY OF CEDAR PARK PRIOR TO ANY CONSTRUCTION WITHIN THE SUBDIVISION.
- 2. ALL SUBDIVISION CONSTRUCTION SHALL CONFORM TO THE CITY OF CEDAR PARK CODE OF ORDINANCES, CONSTRUCTION STANDARDS, AND GENERALLY ACCEPTED ENGINEERING PRACTICES.
- ON-SITE STORM WATER DETENTION FACILITIES WILL BE PROVIDED TO REDUCE POST-DEVELOPMENT PEAK RATES OF DISCHARGE OF THE 2, 10, 25 AND 100-YR. STORM EVENTS.
- 4. THE OWNER OF THIS SUBDIVISION, AND HIS OR HER SUCCESSORS AND ASSIGNS, ASSUMES RESPONSIBILITY FOR PLANS FOR CONSTRUCTION OF SUBDIVISION IMPROVEMENTS WHICH COMPLY WITH APPLICABLE CODES AND REQUIREMENTS OF THE CEDAR OF CEDAR PARK. THE OWNER UNDERSTANDS AND ACKNOWLEDGES THAT PLAT VACATION OR REPLATITING MAY BE REQUIRED. AT THE OWNER'S SOLE EXPENSE, IF PLANS TO CONSTRUCT THIS SUBDIVISION DO NOT COMPLY WITH SUCH CODES AND REQUIREMENTS.
- 5. NO LOT IN THIS SUBDIVISION SHALL BE OCCUPIED UNTIL CONNECTED TO THE CITY OF CEDAR PARK WATER DISTRIBUTION AND WASTEWATER COLLECTION FACILITIES. 3. THIS SUBDIVISION PLAT WAS APPROVED AND RECORDED BEFORE THE CONSTRUCTION AND ACCEPTANCE OF STREETS AND/OR OTHER SUBDIVISION IMPROVEMENTS. THE OWNER OF THIS SUBDIVISION AND HIS OR HER SUCCESSORS AND ASSIGNS, ARE RESPONSIBLE FOR THE CONSTRUCTION OF ALL STREETS, WATER SYSTEMS, WASTEWATER SYSTEMS, AND OTHER FACILITIES NECESSARY TO SERVE THE LOTS WITHIN THE SUBDIVISION.
- SITE DEVELOPMENT CONSTRUCTION PLANS SHALL BE REVIEWED AND APPROVED BY THE CITY OF CEDAR PARK PRIOR TO ANY CONSTRUCTION.
- WASTEWATER AND WATER SYSTEMS SHALL CONFORM TO TCEQ (TEXAS COMMISSION ON ENVIRONMENTAL QUALITY) AND STATE BOARD OF INSURANCE REQUIREMENTS. THE OWNER UNDERSTANDS AND ACKNOWLEDGES THE PLAT VACATION OR RE-PLATING MAY BE REQUIRED, AT THE OWNER'S SOLE EXPENSE, IF PLANS TO DEVELOP THIS SUBDIVISION DO NOT COMPLY WITH SUCH CODES AND REQUIREMENTS.
- D. NO BUILDINGS, FENCES, LANDSCAPING OR OTHER STRUCTURES ARE PERMITTED WITHIN DRAINAGE EASEMENTS SHOWN, EXCEPT AS APPROVED BY THE CITY OF CEDAR PARK PUBLIC WORKS DEPARTMENT.
- 10. PROPERTY OWNER SHALL PROVIDE FOR ACCESS TO DRAINAGE EASEMENTS AS MAY BE NECESSARY AND SHALL NOT PROHIBIT ACCESS BY CITY OF CEDAR PARK.
- 11. ALL EASEMENTS ON PRIVATE PROPERTY SHALL BE MAINTAINED BY THE PROPERTY OWNER OR HIS OR HER
- 12. FISCAL SURETY FOR SUBDIVISION CONSTRUCTION, IN A FORM ACCEPTABLE TO THE CITY OF CEDAR PARK, SHALL BE PROVIDED PRIOR TO PLAT APPROVAL BY THE PLANNING AND ZONING COMMISSION.
- 13. IN ADDITION TO THE EASEMENT SHOWN HEREON, A TEN (10) FOOT WIDE PUBLIC UTILITY EASEMENT (P.U.E.) IS HEREBY DEDICATED ADJACENT TO STREET ROW ON ALL LOTS. A FIVE (5) FOOT WIDE P.U.E. IS HEREBY DEDICATED ALONG EACH SIDE LOT LINE. A SEVEN AND ONE HALF (7 1/2) FOOT WIDE P.U.E. IS HEREBY DEDICATED ADJACENT TO ALL REAR LOT LINES.
- 14. COMMUNITY IMPACT FEES FOR INDIVIDUAL LOTS TO BE PAID PRIOR TO ISSUANCE OF ANY BUILDING PERMITS. 15. DEVELOPER SHALL BE RESPONSIBLE FOR ALL RELOCATION AND MODIFICATIONS TO EXISTING UTILITIES.
- NO PORTION OF THIS TRACT IS WITHIN A FLOOD HAZARD AREA AS SHOWN ON THE FLOOD INSURANCE RATE MAP PANEL # 48491C0605F FOR WILLIAMSON CO., EFFECTIVE DECEMBER 20, 2019.
- 17. TEMPORARY AND PERMANENT EASEMENTS TO BE PROVIDED AS REQUIRED FOR OFF-SITE WATER, WASTEWATER AND DRAINAGE IMPROVEMENTS.
- 18. ALL PROPOSED ACCESS POINTS AND/OR ACCESS EASEMENTS INTERSECTING WITH PUBLIC ROADWAY ROW SHALL BE IN COMPLIANCE WITH CITY ACCESS STANDARDS AS DESCRIBED IN CHAPTER 14 OF CITY CODE-.
- THIS SITE IS LOCATED WITHIN THE EDWARDS AQUIFER CONTRIBUTING ZONE. DEVELOPMENT OF THIS SITE WILL COMPLY WITH ALL APPLICABLE TCEQ EDWARDS AQUIFER RULES.
- 20. THIS SUBDIVISION IS SUBJECT TO THE LAKE TRAVIS NON-POINT SOURCE POLLUTION CONTROL ORDINANCE OF THE CEDAR PARK CITY CODE. A NON-POINT SOURCE POLLUTION DEVELOPMENT PERMIT IS REQUIRED PRIOR TO ANY CONSTRUCTION WITHIN THE SUBDIVISION.
- 21. PRIOR TO SUBDIVISION/SITE PLAN APPROVAL, THE ENGINEER SHALL SUBMIT TO THE CITY OF CEDAR PARK (COCP) DOCUMENTATION OF SUBDIVISION/SITE REGISTRATION WITH THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS (TULP) AND PROVIDE DOCUMENTATION OF REVIEW AND COMPLIANCE OF THE SUBDIVISION CONSTRUCTION PLANS WITH TEXAS ARCHITECTURAL BARRIERS ACT (TABA).
- 22. ALL PROPOSED FENCES AND WALLS ADJACENT TO INTERSECTING PUBLIC ROADWAY RIGHT-OF-WAY OR ADJACENT TO PRIVATE ACCESS POINTS SHALL BE IN COMPLIANCE WITH CITY CODE SECTION 14.05.007 SIGHT DISTANCE REQUIREMENTS: INSTALLING A FENCE OR WALL WHICH DOES NOT COMPLY WITH THE CITY'S SIGHT DISTANCE REQUIREMENTS OR FROLING REGULATIONS IS A VIOLATION OF THE CITY'S ORDINANCE AND MAY BE PUNISHABLE PURSUANT TO SECTION 1.01.009.
- 23. NO BUILDINGS, FENCES, RETAINING WALLS, SIGNS, PONDS, TREES, PARKING LOTS, OR OTHER STRUCTURES ARE PERMITTED WITHIN ANY OF THE PUBLIC WATER OR WASTEWATER EASEMENTS SHOWN ON THIS PLAT EXCEPT AS APPROVED BY THE CITY OF CEDAR PARK PUBLIC WORKS DEPARTMENT.
- 24. THIS SUBDIVISION WILL BE IN FULL COMPLIANCE WITH THE LANDSCAPE AND TREE ORDINANCE OF THE CITY OF CEDAR PARK, TEXAS.
- 25. A DETAILED REVIEW OF THE DRAINAGE ANALYSIS WILL BE PERFORMED AT SITE PLAN SUBMISSION.

SURVEYOR'S NOTES:

- 1. ACCORDING TO COMMUNITY PANEL NO. 4812820805F, MAP NO. 48491C0805F, EFFECTIVE DATE: DECEMBER 20, 2019, OF THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP (FIRM), THE SUBJECT TRACT IS LOCATED WITHIN ZONE X' (UN-SHADED) WHICH IS DEFINED BY FEMA AS 'AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN,' COMMONLY KNOWN AS THE 500-YEAR FLOODPLAIN, ZONE 'X' (UN-SHADED) IS OUTSIDE OF ANY FEMA ESTABLISHED FLOOD HAZARD ZONE, ALZ ZONE DELINEATIONS SHOWN HEREON ARE APPROXIMATE. THIS FLOOD STATEMENT DOC DHAZARD ZONE, ALZ ZONE DELINEATIONS SHOWN HEREON ARE APPROXIMATE. THIS FLOOD STATEMENT DOCD DAMAGE. ON RARE OCCASIONS, GREATER FLOODDS CAN AND WILL OCCUR AND FLOOD HLOOD HACREASED YMAN-MADE OR NATURAL CAUSES. THIS FLOOD STATEMENT BOATE DATA THE PROCESSIONS, GREATER FLOODD STATEMENT SHALL OCCUR AND FLOOD HLOOD HAZARD ZONE. THATEMENT DOLES AND INFRASOR ANA ARTURAL CAUSES. THIS FLOOD STATEMENT DOLE DATAS AND AND ART ANTURAL CAUSES. THIS FLOOD STATEMENT SHALL NOT CREATE ANY LIABILITY ON THE PART OF KIMLEY-HORN OR THE UNDERSIGNED.
- . BASIS OF BEARINGS IS THE TEXAS COORDINATE SYSTEM OF 1983, CENTRAL ZONE (4203). ALL COORDINATES AND DISTANCES SHOWN HEREON ARE SURFACE VALUES. THE SURFACE ADJUSTMENT FACTOR IS 1.00012. THE UNIT OF LINEAR MEASUREMENT IS U.S. SURVEY FEET.

STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS: COUNTY OF WILLIAMSON

CYPRESS CREEK FORTUNE LLC, SOLE OWNER OF LOT 102, RESUBDIVISION OF EMERSON COMMERCIAL NO. 2 AND LOT I, CYPRESS CREEK FORTURE LLC, SOLE OWNER OF LOT 102, RESUBJIVISION OF EMERSION COMMERCIAL NO. 2 AND LOT 1, RESUBJIVISION OF BUTTERCUP CREEK INDUSTRIAL PARK, LOT 2 SHOWN HEREON AND DESCRIBED IN A DEED RECORDED IN DOCUMENT NO. 2024027910 OF THE OFFICIAL RECORDS OF WILLIAMSON COUNTY, TEXAS, DO HEREBY STATE THAT THERE ARE NO LIEN HOLDERS OF THE CERTAIN TRACT OF LAND; DO HEREBY CERTIFY THERE ARE NO EASEMENT HOLDERS EXCEPT AS SHOWN HEREON; DO HEREBY RESUBJIVIDE SAID TRACT AS SHOWN HEREON; DO HEREBY COVENANT TO ALL RESTRICTIONS LISTED HEREIN, WHICH SHALL RUN WITH THE LAND; AND DO HEREBY DEDICATE TO THE CITY OF CEDAR PARK THE STREETS, ALLEYS, RIGHTS-OF-WAY, EASEMENTS AND PUBLIC PLACES SHOWN HEREON FOR SUCH PUBLIC PURPOSES AS THE CITY OF CEDAR PARK MAY DEEM APPROPRIATE. I HEREBY BIND INV HERE CICCESSORE AND ASSICIES TO MORPHATI AND EOREDER DECIDER DICUD ENCIDER, ALL ADD SHOUL & DIVICIL BAD. Y HEIRS, SUCCESSORS, AND ASSIGNS TO WARRANT AND FOREVER DEFEND SUC TO THE CITY OF CEDAR PARK AGAINST EVERY PERSON WHOMSOEVER CLAIMING OR TO CLAIM THE SAME OR ANY PART THEREOF. THIS SUBDIVISION IS TO BE KNOWN AS REPLAT OF LOT 102 RESUBDIVISION OF EMERSON COMMERCIAL NO. 2 AND LOT 1 RESUBDIVISION OF BUTTERCUP CREEK INDUSTRIAL PARK, LOT 2.

TO CERTIFY WHICH, WITNESS BY MY HAND THIS _____ DAY OF _____, 20__.

CYPRESS CREEK FORTUNE LLC, OWNER PRAVEEN KATAPULLY, SIGNING AUTHORITY

STATE OF TEXAS KNOW ALL MEN BY THESE PRESENTS: COUNTY OF WILLIAMSON §

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC IN AND FOR SAID COUNTY AND STATE, ON THIS DAY PERSONALLY APPEARED PRAVEEN KATAPULLY, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS _____ DAY OF _____, 20__.

NOTARY PUBLIC-STATE OF TEXAS MY COMMISSION EXPIRES ON: ____

STATE OF TEXAS COUNTY OF WILLIAMSON

ENGINEER'S CERTIFICATION: I, THOMAS J. LOMBARDI JR., REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS SUBDIVISION IS IN THE EDWARDS AQUIFER RECHARGE ZONE AND IS NOT ENCROACHED BY A ZONE A FLOOD AREA, AS DENOTED HEREIN, AND AS DEFINED BY FEDERAL EMERGENCY MANAGEMENT ADMINISTRATION FLOOD HAZARD BOUNDARY MAP, COMMUNTY PANEL NUMBER 48:1225065F, EFFECTIVE DATE DECEMBER 20, 2019, AND THAT EACH LOT CONFORMS TO THE CITY OF CEDAR PARK REGULATIONS.

THE FULLY DEVELOPED, CONCENTRATED STORMWATER RUNOFF RESULTING FROM THE ONE HUNDRED (100) YEAR REQUENCY STORM IS CONTAINED WITHIN THE DRAINAGE EASEMENTS SHOWN AND/OR PUBLIC RIGHTS-OF-WAY DEDICATED BY THIS PLAT. TO CERTIFY WHICH, WITNESS MY HAND AND SEAL, THIS ____ DAY OF _____, 20__.

THOMAS J. LOMBARDI JR., P.E. REGISTERED PROFESSIONAL ENGINEER NO. 131071 KIMLEY-HORN AND ASSOCIATES, INC.


6800 BURLESON ROAD BUILDING 312, SUITE 150 AUSTIN, TEXAS 78744 PH. (512) 518-6534 THOMAS.LOMBARDI@KIMLEY-HORN.COM

STATE OF TEXAS SCOUNTY OF WILLIAMSON

SURVEYOR'S CERTIFICATION:

I, MICHAEL A. MONTGOMERY II, REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS PLAT IS TRUE AND CORRECTLY MADE FROM AN ACTUAL SURVEY MADE ON THE GROUND OF THE PROPERTY LEGALLY DESCRIBED HEREON, THAT ALL EXISTING FASEMENTS ON OR ADJACENT TO THE PROPOSED SUBDIVISION ARE SHOWN AS NOTED IN THE MOST RECENT TITLE SURVEY OR DISCOVERED WITH A TITLE SEARCH PREPARED IN CONJUNCTION WITH THE MOST RECENT PURCHASE OF THE PROPERTY, AND THAT THERE ARE NO APPARENT DISCREPANCIES, CONFLICTS, OVERLAPPING OF IMPROVEMENTS, VISIBLE UTILITY LINES OR ROADS IN PLACE, EXCEPT AS SHOWN ON THE ACCOMPANYING PLAT, AND THAT THE CORNER MONUMENTS SHOWN THEREON WERE PROPERTY, PLACED UNDER MY SUPERVISION IN ACCORDANCE WITH THE SUBDIVISION REGULATIONS OF THE CITY OF CEDAR PARK, TEXAS. TO CERTIFY WHICH, WITNESS MY HAND AND SEAL, THIS _____ DAY OF _____, 20__.

MICHAEL A. MONTGOMERY II, R.P.L.S. REGISTERED PROFESSIONAL LAND SURVEYOR NO. 6890



RALPH E. STRADER, II, CHAIR PLANNING AND ZONING COMMISSION CITY OF CEDAR PARK, TEXAS	ATTEST: KIMBERLY BRADFORD-BROWN, SECRETARY PLANNING AND ZONING COMMISSION CITY OF CEDAR PARK, TEXAS
	OR RECORD BY THE DIRECTOR, DEVELOPMENT SERVICES DEPARTMENT, N THIS THE DAY OF, 20 A.D.
AMY LINK, DIRECTOR DEVELOPMENT SERVICES DEPARTMENT	-
STATE OF TEXAS \$ S KNOW ALL KNOW ALL S S S S S S S S S S S S S S S S S S	MEN BY THESE PRESENTS:
INSTRUMENT IN WRITING, WITH ITS CERTIFIC. DAY OF, 20 AD, 40, 40, 41, 40, 41, 40, 41, 40, 41, 41, 41, 41, 41, 41, 41, 41, 41, 41	COURT OF SAID COUNTY, DO HEREBY CERTIFY THAT THE FOREGOING ATION OF AUTHENTICATION WAS FILED FOR RECORD IN MY OFFICE ON THE AT OCLOCK,M, AND DULY RECORDED ON THIS THE DAY OF OCLOCK,M, IN THE PLAT RECORDS OF SAID COUNTY IN INSTRUMENT
NO TO CERTIFY WHICH, WITNESS MY HAND A GEORGETOWN, TEXAS, THE DATE LAST SHOV	ND SEAL AT THE COUNTY COURT OF SAID COUNTY, AT MY OFFICE IN VN ABOVE WRITTEN.
NANCY RISTER, CLERK COUNTY COURT OF W	
	LOT 102 RESUBDIVISION
	SON COMMERCIAL NO. 2 T 1 RESUBDIVISION OF
BUTTERC	CUP CREEK INDUSTRIAL
	PARK, LOT 2
BEIN R. D	PARK, LOT 2 NG 5.821 ACRES OUT OF THE UTY SURVEY, ABSTRACT 183
BEIN R. D	PARK, LOT 2 NG 5.821 ACRES OUT OF THE UTY SURVEY, ABSTRACT 183 LLIAMSON COUNTY, TEXAS
BEIN R. D WI	PARK, LOT 2 NG 5.821 ACRES OUT OF THE UTY SURVEY, ABSTRACT 183 LLIAMSON COUNTY, TEXAS
BEIN R. D	PARK, LOT 2 NG 5.821 ACRES OUT OF THE UTY SURVEY, ABSTRACT 183 LLIAMSON COUNTY, TEXAS DICOMPUSIV XAS 78759 TEPELS FIRM # 10194624

Inc.		CITY OF CEDAR PARK STANDARD CONSTRUCTION AND SITE PLAN NOTES REVISED 04/02/2024
Associates,	GE	ENERAL NOTES:
ssoci	1.	GENERAL CONTRACTOR SHALL CALL FOR ALL UTILITY LOCATES PRIOR TO
		ANY CONSTRUCTION. CONTRACTOR SHALL DELINEATE AREAS OF EXCAVATION USING WHITE PAINT (WHITE LINING) IN ACCORDANCE WITH 16
n and		TAC 18.3. WATER & WASTEWATER OWNED BY THE CITY OF CEDAR PARK CAN BE LOCATED BY CALLING TEXAS 811 AT 1- 800-344-8377. ALLOW THREE
Kimley–Horn		BUSINESS DAYS FOR UTILITY LOCATES BY THE CITY OF CEDAR PARK.
nley-	2.	ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST CITY OF AUSTIN STANDARD SPECIFICATIONS. CITY OF AUSTIN STANDARDS SHALL BE
to Kir	3	USED UNLESS OTHERWISE NOTED. DESIGN PROCEDURES SHALL BE IN GENERAL COMPLIANCE WITH THE CITY
		OF AUSTIN DRAINAGE CRITERIA MANUAL. BENCHMARKS SHOULD BE TIED TO THE CITY OF CEDAR PARK BENCHMARKS
liabil	4.	AND BE CORRECTLY "GEO- REFERENCED" TO STATE PLANE COORDINATES.
without liability		A LIST OF THE CITY'S BENCHMARKS CAN BE FOUND AT: HTTP://WWW.CEDARPARKTEXAS.GOV/INDEX.ASPX?PAGE=793.
with	5.	PRIOR TO ISSUANCE OF A CERTIFICATE OF OCCUPANCY FOR A SITE DEVELOPMENT PERMIT, THE RIGHT OF WAY BETWEEN THE PROPERTY LINE
- be		AND EDGE OF PAVEMENT / BACK OF CURB SHALL BE REVEGETATED ACCORDING TO COA SPECIFICATION 602S AND 606S. PRIOR TO CITY
shall		ACCEPTANCE OF SUBDIVISION IMPROVEMENTS ALL GRADED AND DISTURBED AREAS SHALL BE RE-VEGETATED IN ACCORDANCE WITH THE
Inc.		CITY OF AUSTIN SPECIFICATION ITEM #604 NATIVE SEEDING UNLESS NON-
Associates,	6.	NATIVE IS SPECIFICALLY APPROVED. THE CONTRACTOR SHALL PROVIDE THE CITY OF CEDAR PARK COPIES OF
socio		ALL TEST RESULTS PRIOR TO ACCEPTANCE OF SUBDIVISION IMPROVEMENTS.
	7.	CITY, OWNER, ENGINEER, CONTRACTOR, REPRESENTATIVES OF ALL UTILITY COMPANIES, AND A REPRESENTATIVE FROM THE TESTING LAB SHALL
n and		ATTEND PRE-CONSTRUCTION CONFERENCE PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR SHALL SCHEDULE THE MEETING WITH
Kimley-Horn		THE CITY OF CEDAR PARK ENGINEERING DEPARTMENT A MINIMUM OF 48
nley-		HOURS PRIOR TO THIS PRE-CONSTRUCTION MEETING (512-401-5000). FINAL CONSTRUCTION PLANS SHALL BE DELIVERED TO ENGINEERING A MINIMUM
by Kir		OF SEVEN BUSINESS DAYS PRIOR TO REQUESTING A PRE-CONSTRUCTION MEETING.
	8.	EXCESS SOIL SHALL BE REMOVED AT THE CONTRACTOR'S EXPENSE. NOTIFY THE CITY OF CEDAR PARK IF THE DISPOSAL SITE IS INSIDE THE
adaptation	٩	CITY'S JURISDICTIONAL BOUNDARIES. BURNING IS PROHIBITED.
		ANY CHANGES OR REVISIONS TO THESE PLANS MUST FIRST BE SUBMITTED
and		TO THE CITY BY THE DESIGN ENGINEER FOR REVIEW AND WRITTEN APPROVAL PRIOR TO CONSTRUCTION OF THE REVISION. ALL CHANGES AND
ıtion		REVISIONS MADE TO THE DESIGN OF UTILITIES OR IMPACTS UTILITIES SHALL USE REVISION CLOUDS TO HIGHLIGHT ALL REVISIONS OR CHANGES
authorization		WITH EACH SUBMITTAL. REVISION TRIANGLES SHALL BE USED TO MARK REVISIONS. ALL CLOUDS AND TRIANGLE MARKERS FROM PREVIOUS
		REVISIONS MAY BE REMOVED. REVISION INFORMATION SHALL BE UPDATED IN THE APPROPRIATE AREAS OF THE TITLE BLOCK.
	11	MINIMUM SETBACK REQUIREMENTS FOR EXISTING AND NEWLY PLANTED TREES FROM THE EDGE OF PAVEMENT TO CONFORM TO THE
t wri		REQUIREMENTS AS SHOWN IN TABLE 6-1 OF THE CITY OF AUSTIN'S
without written	12	TRANSPORTATION CRITERIA MANUAL. . THE CONTRACTOR WILL REIMBURSE THE CITY FOR ALL COST INCURRED AS
		A RESULT OF ANY DAMAGE TO ANY CITY UTILITY OR ANY INFRASTRUCTURE WITHIN THE RIGHT-OF-WAY BY THE CONTRACTOR, REGARDLESS OF THESE
document	13	PLANS. AN ENGINEER'S CONCURRENCE LETTER AND ELECTRONIC 22"X34" RECORD
		DRAWINGS SHALL BE SUBMITTED TO THE ENGINEERING DEPARTMENT PRIOR TO THE ISSUANCE OF CERTIFICATE OF OCCUPANCY OR SUBDIVISION
this		ACCEPTANCE. THE ENGINEER AND CONTRACTOR SHALL VERIFY THAT ALL
u ou		FINAL REVISIONS AND CHANGES HAVE BEEN MADE TO RECORD DRAWINGS PRIOR TO CITY SUBMITTAL. RECORD CONSTRUCTION DRAWINGS,
reliance		INCLUDING ROADWAY AND ALL UTILITIES, SHALL BE PROVIDED TO THE CITY IN AUTOCAD ". DWG" FILES AND ".PDF" FORMAT ON A CD OR DVD. LINE
		WEIGHTS, LINE TYPES AND TEXT SIZE SHALL BE SUCH THAT IF HALF-SIZE PRINTS (11"X 17") WERE PRODUCED, THE PLANS WOULD STILL BE LEGIBLE.
improper		ALL REQUIRED DIGITAL FILES SHALL CONTAIN A MINIMUM OF TWO (2) CONTROL POINTS REFERENCED TO THE STATE PLANE GRID COORDINATE
		SYSTEM - TEXAS CENTRAL ZONE (4203), IN US FEET AND SHALL INCLUDE
and		ROTATION INFORMATION AND SCALE FACTOR REQUIRED TO REDUCE SURFACE COORDINATES TO GRID COORDINATES IN US FEET.
se of	14	. THE CITY OF CEDAR PARK HAS NOT REVIEWED THESE PLANS FOR COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT. IT IS THE
Reuse		RESPONSIBILITY OF THE OWNER TO PROVIDE COMPLIANCE WITH ALL LEGISLATION RELATED TO ACCESSIBILITY WITHIN THE LIMITS OF
red.	15	CONSTRUCTION SHOWN IN THESE PLANS. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH
prepared.	15	THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE
d spw		CITY OF CEDAR PARK MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.
÷		.NO BLASTING IS ALLOWED ON THIS PROJECT. . A TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH THE TEXAS MANUAL ON
which		UNIFORM TRAFFIC CONTROL DEVICES, SHALL BE SUBMITTED TO THE CITY FOR REVIEW AND APPROVAL PRIOR TO ANY PARTIAL OR COMPLETE
for v		ROADWAY CLOSURES. TRAFFIC CONTROL PLANS SHALL BE SITE SPECIFIC AND SEAL BY A REGISTERED PROFESSIONAL ENGINEER.
lient	18	THE CONTRACTOR SHALL KEEP THE SITE CLEAN AND MAINTAINED AT ALL TIMES, TO THE SATISFACTION OF THE CITY. THE SUBDIVISION WILL NOT BE
0 P		ACCEPTED (OR CERTIFICATE OF OCCUPANCY ISSUED) UNTIL THE SITE HAS BEEN CLEANED TO THE SATISFACTION OF THE CITY.
se an	19	SIGNS ARE NOT PERMITTED IN PUBLIC UTILITY EASEMENTS, SET BACKS OR
purpose	20	DRAINAGE EASEMENTS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO INSPECT
		TEMPORARY EROSION CONTROLS ON A DAILY BASIS. ADJUST THE CONTROLS AND/OR REMOVE ANY SEDIMENT BUILDUP AS NECESSARY. A
specific		STOP WORK ORDER AND/OR FINE MAY BE IMPOSED IF THE EROSION CONTROLS ARE NOT MAINTAINED.
the s	21	A FINAL CERTIFICATE OF OCCUPANCY WILL NOT BE ISSUED ON COMMERCIAL SITES UNTIL ALL DISTURBED AREAS HAVE BEEN
for		RE-VEGETATED. SUBSTANTIAL GRASS COVER, AS DETERMINED BY
only		ENGINEERING DEPARTMENT, MUST BE ACHIEVED PRIOR TO THE ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY. ALL EROSION CONTROLS MUST
		REMAIN IN PLACE AND MAINTAINED UNTIL ALL DISTURBED AREAS HAVE BEEN RE-VEGETATED TO THE ACCEPTANCE OF THE CITY OF CEDAR PARK
intended		ENGINEERING DEPARTMENT. PRIOR TO ISSUANCE OF A CERTIFICATE OF OCCUPANCY FOR A SITE DEVELOPMENT PERMIT, THE RIGHT OF WAY
. <u>o</u>		BETWEEN THE PROPERTY LINE AND EDGE OF PAVEMENT / BACK OF CURB SHALL BE REVEGETATED ACCORDING TO COA SPECIFICATION 602S AND
service,	22	.CONTRACTOR WILL BE RESPONSIBLE FOR KEEPING ROADS AND DRIVES
of se		ADJACENT TO AND NEAR THE SITE FREE FROM SOIL, SEDIMENT AND
		DEBRIS. CONTRACTOR WILL NOT REMOVE SOIL, SEDIMENT OR DEBRIS FROM ANY AREA OR VEHICLE BY MEANS OF WATER, ONLY SHOVELING AND
instrument		SWEEPING WILL BE ALLOWED. CONTRACTOR WILL BE RESPONSIBLE FOR DUST CONTROL FROM THE SITE. FAILURE TO COMPLY WITH THIS
	23	REQUIREMENT MAY RESULT IN A STOP WORK ORDER OR A FINE. ALL WET UTILITIES SHALL BE INSTALLED AND ALL DENSITIES MUST HAVE.
s an	24	PASSED INSPECTION(S) PRIOR TO THE INSTALLATION OF DRY UTILITIES. A MINIMUM OF SEVEN DAYS OF CURE TIME IS REQUIRED FOR HMAC PRIOR
in, as		TO THE INTRODUCTION OF VEHICULAR TRAFFIC TO ANY STREETS. .PRIOR TO PLAN APPROVAL, THE ENGINEER SHALL SUBMIT TO THE
herein,	20	ENGINEERING DEPARTMENT DOCUMENTATION OF SUBDIVISION/SITE
		REGISTRATION WITH THE TEXAS DEPARTMENT OF LICENSING AND REGULATIONS (TDLR) AND PROVIDE DOCUMENTATION OF REVIEW AND
presented		COMPLIANCE OF THE SUBDIVISION/SITE CONSTRUCTION PLANS WITH TEXAS ARCHITECTURAL BARRIERS ACT (TABA).
	26	PRIOR TO SUBDIVISION/SITE ACCÈPTAŃCE, THE ENGINEER/DEVELOPER-OWNER SHALL SUBMIT TO THE ENGINEERING
designs		DEPARTMENT DOCUMENTATION THAT THE SUBDIVISION/SITE WAS INSPECTED BY TDLR OR A REGISTERED ACCESSIBILITY SPECIALIST (RAS)
and d		AND THE SUBDIVISION/SITE IS IN COMPLIANCE WITH THE REQUIREMENTS OF
pts	27	THE TABA. ALL CONSTRUCTION AND CONSTRUCTION RELATED ACTIVITIES SHALL BE
JCe		PERFORMED MONDAY THRU FRIDAY FROM 7:00 A.M. TO 6:00 P.M. HOWEVER, CONSTRUCTION ACTIVITIES WITHIN ONE HUNDRED FEET (100') OF A
he col		DWELLING OR DWELLING UNIT SHALL BE PERFORMED BETWEEN THE HOURS OF 8:00
ith th		a.m. AND 6:00 P.M. OTHERWISE ALL CONSTRUCTION AND CONSTRUCTION RELATED ACTIVITIES SHALL CONFORM TO CITY OF
together with	. .	CEDAR PARK CODE OF ORDINANCES, SPECIFICALLY ARTICLE 8.08.
geth	28	APPROVAL FOR CONSTRUCTION ACTIVITIES PERFORMED ON OWNER'S HOLIDAYS, AND/OR SATURDAYS, OUTSIDE OF MONDAY THROUGH FRIDAY 8
		AM TO 5 PM, OR IN EXCESS OF 8 HOURS PER DAY SHALL BE OBTAINED IN WRITING 48 HOURS IN ADVANCE, AND INSPECTION FEES AT 1.5 TIMES THE
nent,		HOURLY INSPECTION RATE SHALL BE BILLED DIRECTLY TO THE

CONTRACTOR. THERE SHALL BE NO CONSTRUCTION OR CONSTRUCTION RELATED ACTIVITIES PERFORMED ON SUNDAY. THE CITY RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO UNCOVER ALL WORK

PERFORMED WITHOUT CITY INSPECTION

- 29.ALL POLES TO BE APPROVED BY CITY AND PEC, NO CONDUIT SHALL BE INSTALLED DOWN LOT LINES / BETWEEN HOMES. ALL CONDUIT SHALL BE LOCATED IN THE PUBLIC ROW OR IN AN EASEMENT ADJACENT TO AND PARALLEL TO THE PUBLIC ROW.
- 30.DRY UTILITIES SHALL BE INSTALLED AFTER SUBGRADE IS CUT AND BEFORE FIRST COURSE BASE. NO TRENCHING OF COMPACTED BASE. IF NECESSARY DRY UTILITIES INSTALLED AFTER FIRST COURSE BASE SHALL BE BORED ACROSS THE FULL WIDTH OF THE ROW.
- 31.NO PONDING OF WATER SHALL BE ALLOWED TO COLLECT ON OR NEAR THE INTERSECTION OF PRIVATE DRIVEWAY(S) AND A PUBLIC STREET. RECONSTRUCTION OF THE DRIVEWAY APPROACH SHALL BE AT THE CONTRACTOR'S EXPENSE
- 32. ALL DRIVEWAY APPROACHES SHALL HAVE A UNIFORM TWO PERCENT SLOPE WITHIN THE ROW UNLESS APPROVED IN WRITING BY THE ENGINEERING DEPARTMENT
- 33.CONTRACTORS ON SITE SHALL HAVE AN APPROVED SET OF PLANS AT ALL TIMES. FAILURE TO HAVE AN APPROVED SET MAY RESULT IN A STOP WORK
- 34.CONTRACTOR TO CLEAR FIVE FEET BEYOND ALL RIGHT OF WAY TO PREVENT FUTURE VEGETATIVE GROWTH INTO THE SIDEWALK AREAS.
- 35. THERE SHALL BE NO WATER OR WASTEWATER APPURTENANCES, INCLUDING BUT NOT LIMITED TO. VALVES. FITTINGS. METERS. CLEAN-OUTS. MANHOLES, OR VAULTS IN ANY DRIVEWAY, SIDEWALK, TRAFFIC OR PEDESTRIAN AREA.
- 36.SIDEWALKS SHALL NOT USE CURB INLETS AS A PARTIAL WALKING SURFACE. SIDEWALKS SHALL NOT USE TRAFFIC CONTROL BOXES, METER OR CHECK VALVE VAULTS, COMMUNICATION VAULTS, OR OTHER BURIED OR PARTIALLY BURIED INFRASTRUCTURE AS A VEHICULAR OR PEDESTRIAN SURFACE.

STREET NOTES:

- 1. NO TRENCHING OF COMPACTED BASE WILL BE ALLOWED, A PENALTY AND/OR FINE MAY BE IMPOSED TO THE GENERAL CONTRACTOR IF TRENCHING OF COMPACTED BASE OCCURS WITHOUT CITY APPROVAL REGARDLESS OF WHO PERFORMED THE TRENCHING.
- 2. ALL SIDEWALKS SHALL COMPLY WITH THE AMERICANS WITH DISABILITIES ACT. THE CITY OF CEDAR PARK HAS NOT REVIEWED THESE PLANS FOR COMPLIANCE WITH THE AMERICANS WITH DISABILITIES ACT, OR ANY OTHER ACCESSIBILITY LEGISLATION, AND DOES NOT WARRANTY OR APPROVE THESE PLANS FOR ANY ACCESSIBILITY STANDARDS.
- 3. STREET BARRICADES SHALL BE INSTALLED ON ALL DEAD END STREETS AND AS NECESSARY DURING CONSTRUCTION TO MAINTAIN JOB SAFETY. 4. ANY DAMAGE CAUSED TO EXISTING PAVEMENT, CURBS, SIDEWALKS,
- RAMPS, ETC., SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE CITY PRIOR TO ACCEPTANCE OF THE SUBDIVISION.
- 5. AT INTERSECTIONS, WHICH HAVE VALLEY DRAINAGE, THE CROWN TO THE INTERSECTING STREET WILL BE CULMINATED AT A DISTANCE OF 40 FT. FROM THE INTERSECTING CURB LINE UNLESS OTHERWISE NOTED.
- 6. THE SUBGRADE MATERIAL WAS TESTED BY TERRADYNE, 1608 ROYSTON LANE, BUILDING 2 (PH. 512-252-1218) ON NOVEMBER 1, 2024. THE PAVEMENT SECTIONS WERE DESIGNED ACCORDINGLY. THE PAVEMENT SECTORS ARE TO BE CONSTRUCTED AS FOLLOWS:

Flexible Pavement Section		Thickness in Inches			
Flexible 1 avenient Section	Alt 1	Alt 2	Alt 3		
Hot Mix Asphaltic Concrete	2.0	2.0	2.0		
Aggregate Base	8.0	8.0	12.0		
Lime Stabilized Subgrade		6.0			
Tensar HX5.5 Geogrid*	Yes				
Compacted Subgrade	-		8.0		
Rigid Pavement Section	Thickness in Inches				

Rigid Pavement Section	Thickness in Inches
Portland Cement Concrete	6.0
Lime Stabilized Subgrade	8.0

DRIVES AND FIRE LANE DESIGN ESALS: 150,000

Flexible Pavement Section	Thickness in Inches				
Flexible Favement Section	Alt 1	Alt 2	Alt 3		
Hot Mix Asphaltic Concrete	3.0	3.0	3.0		
Aggregate Base	10.0	10.0	16.0		
Lime Stabilized Subgrade		8.0			
Tensar HX5.5 Geogrid*	Yes				
Compacted Subgrade			8.0		
Rigid Pavement Section		Thickness in Inches	i		
Portland Cement Concrete		7.0			
		8.0			

- 7. DENSITY TESTING OF COMPACTED SUBGRADE MATERIAL, FIRST COURSE AND SECOND COURSE COMPACTED BASE, SHALL BE MADE AT 500 FOOT INTERVALS
- 8. ALL DENSITY TESTING IS THE RESPONSIBILITY OF THE OWNER OR CONTRACTOR AND SHALL BE WITNESSED BY THE CITY OF CEDAR PARK'S PROJECT REPRESENTATIVE. THE CONTRACTOR IS TO NOTIFY THE CITY 48 HOURS PRIOR TO SCHEDULED DENSITY TESTING.
- 9. TRAFFIC CONTROL SIGNS AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND INSTALLED AS DIRECTED BY THE CITY OF CEDAR PARK PRIOR TO CITY ACCEPTANCE OF THE SUBDIVISION.
- 10. SLOPE OF NATURAL GROUND ADJACENT TO THE RIGHT-OF-WAY SHALL NOT EXCEED 3:1. IF A 3:1 SLOPE IS NOT POSSIBLE, A RETAINING WALL OR SOME OTHER FORM OF SLOPE PROTECTION APPROVED BY THE CITY SHALL BE PLACED IN A LOCATION ACCEPTABLE TO THE CITY
- 11. THE CITY, ENGINEER, CONTRACTOR, AND A REPRESENTATIVE FROM THE ASPHALT TESTING LAB SHALL ATTEND A PRE-PAVING CONFERENCE PRIOR TO THE START OF HMAC PAVING. THE CONTRACTOR SHALL GIVE THE CITY A MINIMUM OF 48 HOURS NOTICE PRIOR TO THIS MEETING (512-401-5000).
- 12. THE CONTRACTOR OR OWNER IS RESPONSIBLE FOR CONDUCTING TESTS ON ASPHALT PAVEMENT IN ACCORDANCE WITH THE REQUIREMENTS SET FORTH IN THE CITY OF AUSTIN STANDARD SPECIFICATION NO. 340. ANY RE-TESTING OF THE ASPHALT PAVEMENT SHALL BE CONDUCTED
- UNDER THE SUPERVISION OF THE ENGINEER AND THE CITY OF CEDAR PARK. RE-TESTING OF THE ASPHALT PAVEMENT SHALL BE LIMITED TO ONE RETEST PER PROJECT.
- 13. ALL PAVEMENT MARKINGS AND SIGNAGE SHALL COMPLY WITH MUTCD STANDARDS. STREET NAME LETTER SIZING SHALL BE IN ACCORDANCE WITH MUTCDTABLE2D-2.PAVEMENT MARKINGS SHALL BE THERMOPLASTIC UNLESS OTHERWISE NOTED. 14. ALL STREET NAME SIGNS SHALL BE HIGH INTENSITY RETRO GRADE.
- 15.NO FENCING OR WALL IS ALLOWED TO BE CONSTRUCTED SO THAT IT OBSTRUCTS THE SIGHT LINES OF DRIVERS FROM AN INTERSECTING PUBLIC ROADWAY OR FROM AN INTERSECTING PRIVATE DRIVEWAY, SIGHT LINES ARE TO BE MAINTAINED AS DESCRIBED IN CITY CODE SECTION 14.05.007. INSTALLING A FENCE OR WALL WHICH DOES NOT COMPLY WITH THE CITY'S SIGHT DISTANCE REQUIREMENTS OR FENCING REGULATIONS IS A VIOLATION OF THE CITY'S ORDINANCE AND MAY BE PUNISHABLE PURSUANT TO SECTION 1.01.009 OF CITY CODE.
- 16. TEMPORARY ROCK CRUSHING OPERATIONS ARE NOT ALLOWED. ALL SOURCES FOR FLEXIBLE BASE MATERIAL ARE REQUIRED TO BE APPROVED BY THE CITY. PRIOR TO BASE PLACEMENT ALL CURRENT TRIAXIAL TEST

IMPROVEMENTS. AND 4 PM. ANY NIGHT TIME LANE STOPPAGE.

CLOSURE OF THE DRIVEWAY.

WASTEWATER NOTES:

- SPECIFICATIONS MANUAL

- BIDDING THE PROJECT. POLYETHYLENE WRAP.

- (INCHES) OR LESS.

- UTILITIES.
- STANDARD SPECIFICATIONS.
- ASTM A615 60.
- ACCEPTABLE.
- NOTE 20.
- FITTINGS.

WATER NOTES:

- SPECIFICATIONS MANUAL.

- ELEVATION OF THE BURY LINE.

- 7. APPROVED 5 1/4" FIRE HYDRANTS:

REPORTS FOR THE PROPOSED STOCKPILES ARE TO BE SUBMITTED TO THE CITY'S PROJECT REPRESENTATIVE FOR REVIEW AND APPROVAL 17. UTILITY SERVICE BOXES OR OTHER UTILITY FACILITIES SHALL NOT BE INSTALLED WITHIN AREAS DETERMINED TO BE REQUIRED SIGHT LINES OF TWO INTERSECTING PUBLIC STREETS OR WITHIN SIGHT LINES OF A PRIVATE DRIVEWAY, SIGHT LINES ARE TO BE MAINTAINED COMPLIANT WITH TABLE 1-1 OF THE AUSTIN TRANSPORTATION CRITERIA MANUAL. UTILITIES DETERMINED BY THE DIRECTOR OF ENGINEERING TO BE PLACED WITHIN

REQUIRED SIGHT LINES MAY BE REQUIRED TO BE RELOCATED AT THE EXPENSE OF THE CONTRACTOR PRIOR TO THE CITY ISSUING A CERTIFICATE OF OCCUPANCY OR PRIOR TO THE CITY'S ACCEPTANCE OF THE PROJECT

18. ALL LANE CLOSURES SHALL OCCUR ONLY BETWEEN THE HOURS OF 9 AM

CLOSURES REQUIRE APPROVAL BY THE DIRECTOR OF ENGINEERING AND SHALL OCCUR BETWEEN THE HOURS OF 8 PM AND 6 AM. LANE CLOSURES OBSERVED BY CITY DURING THE PEAK HOURS OF 6 AM TO 9 AM, OR 4 PM TO 8 PM WILL BE SUBJECT TO FINE PER CHAPTER 1 OF CITY ORDINANCE, AND/OR SUBSEQUENT ISSUANCE OF WORK

19. IMPROVEMENTS THAT INCLUDE RECONSTRUCTION OF AN EXISTING TYPE II DRIVEWAY SHALL BE DONE IN A MANNER WHICH RETAINS OPERATIONS OF NOT LESS THAN HALF OF THE DRIVEWAY AT ALL TIMES. FULL CLOSURE OF SUCH DRIVEWAY CAN BE CONSIDERED WITH WRITTEN AUTHORIZATION RETAINED BY THE CONTRACTOR FROM THE PROPERTY OWNER(S) OR ACCESS EASEMENT RIGHT HOLDER(S) OF THE DRIVEWAY ALLOWING FULI

20. TREES MUST NOT OVERHANG WITHIN 10' VERTICALLY OF A SIDEWALK, OR 18' VERTICALLY OF A ROADWAY OR DRIVEWAY.

1. REFER TO THE CITY OF CEDAR PARK PUBLIC WORKS UTILITY POLICY AND

2. MANHOLE FRAMES AND COVERS AND WATER VALVE BOXES SHALL BE RAISED TO FINISHED PAVEMENT GRADE AT THE OWNER'S EXPENSE BY THE CONTRACTOR WITH THE CITY APPROVAL. ALL UTILITY ADJUSTMENTS SHALL BE COMPLETED PRIOR TO FINAL PAVING CONSTRUCTION. 3. THE LOCATION OF ANY EXISTING UTILITY LINES SHOWN ON THESE PLANS

MAY NOT BE ACCURATE. ANY DAMAGE TO EXISTING UTILITY LINES, BOTH KNOWN AND UNKNOWN, SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR. THE CONTRACTOR SHALL LOCATE ALL UTILITIES PRIOR TO

4. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH AT LEAST 8 MIL.

5. ALL WATER MAINS, WASTEWATER MAINS AND SERVICE LINES SHALL MEET CITY OF AUSTIN MINIMUM COVER SPECIFICATIONS. ALL STREETS ARE TO BE CUT TO SUBGRADE PRIOR TO INSTALLATION OF WATER MAINS OR CUTS WILL BE ISSUED BY THE ENGINEER

6. WHERE 48-INCHES OF COVER BELOW SUBGRADE CANNOT BE ACHIEVED FOR WASTEWATER SERVICE LINES ALTERNATE MATERIALS MAY BE USED. A MINIMUM OF 36-INCHES OF COVER BELOW SUBGRADE SHALL BE ACHIEVED. ANY WASTEWATER SERVICE LINE WITH COVER BETWEEN 36-INCH AND 48-INCHES SHALL BE SDR-26 PVC PRESSURE PIPE.

7. GASKETED PVC SEWER MAIN FITTINGS SHALL BE USED TO CONNECT SDR-35 PVC TO SDR-26 PVC PRESSURE PIPE OR C-900. 8. PIPE MATERIALS TO BE USED FOR CONSTRUCTION OF UTILITY LINES:

WASTEWATER- SDR 26-PVC FORCE MAIN- N/A

(NOTE: IF USING PVC, SDR-26 IS REQUIRED, SDR-35 WW IS NOT ALLOWED. FORCEMAINS SHALL BE EPOXY LINED DUCTILE IRON) 9. ALL SANITARY SEWERS, EXCLUDING SERVICE LINES, SHALL BE MANDREL TESTED PER TCEQ (TEXAS COMMISSION ON ENVIRONMENTAL QUALITY) CRITERIA. A MANDREL TEST WILL NOT BE PERFORMED UNTIL BACKFILL HAS BEEN IN PLACE FOR A MINIMUM OF 30 DAYS.

10. ALL WASTEWATER LINES 10" AND LARGER SHALL BE VIDEO INSPECTED IN ACCORDANCE WITH CITY OF CEDAR PARK PUBLIC WORKS DEPARTMENT UTILITY POLICY AND STANDARD SPECIFICATIONS MANUAL APPENDIX E: REQUIREMENTS FOR VIDEO INSPECTION OF WASTEWATER LINES AT THE CONTRACTOR'S EXPENSE. NO SEPARATE PAY UNLESS NOTED ON THE BID

11. ALL SANITARY SEWERS, INCLUDING SERVICE LINES, SHALL BE AIR TESTED PER CITY OF AUSTIN STANDARD SPECIFICATIONS. 12. DENSITY TESTING OF COMPACTED BACKFILL SHALL BE MADE AT A RATE OF

ONE TEST PER TWO FOOT LIFTS PER 500 FEET OF INSTALLED PIPE. 13.CITY SHALL BE GIVEN 48 HOURS NOTICE PRIOR TO ALL TESTING OF WATER AND WASTEWATER LINES. CITY INSPECTION IS REQUIRED FOR ALL TESTING OF WATER AND WASTEWATER LINES.

14. WHERE A WATER OR WASTEWATER LINE CROSSES ABOVE (OR BELOW) A STORM SEWER STRUCTURE AND THE BOTTOM (OR TOP) OF THE PIPE IS WITHIN 18 INCHES OF THE TOP (OR BOTTOM) OF THE UTILITY STRUCTURE THE PIPE SHALL BE ENCASED WITH CONCRETE FOR A DISTANCE OF AT LEAST 1 FT. ON EITHER SIDE OF THE DITCH LINE OF THE UTILITY

STRUCTURE OR THE STORM SEWER. CONCRETE ENCASEMENT WILL NOT BE REQUIRED FOR DUCTILE IRON (THICKNESS CLASS 50). AWWA C-900 (SDR- 18) 150 PSI RATED PVC IN SIZES TO 12 INCHES OR AWWA C-905 (SDR-25) 165 PSI RATED PVC IN SIZES LARGER THAN 12 INCHES. CONCRETE ENCASEMENT SHALL CONFORM TO C.O.A. STANDARD DETAIL 505-1.

15. THE ALLOWABLE (MAXIMUM) ADJUSTMENT FOR A MANHOLE SHALL BE 12" 16. WHERE A SEWER LINE CROSSES A WATER LINE, THE SEWER LINE SHALL BE

ONE 20 FT. JOINT OF 150 PSI RATED PVC CENTERED ON CROSSING. 17. ALL MANHOLE AND INLET COVERS SHALL READ "CITY OF CEDAR PARK". 18. CONTRACTOR TO NOTIFY, AND OBTAIN APPROVAL FROM. THE CITY OF CEDAR PARK 48 HOURS PRIOR TO CONNECTING TO EXISTING CITY

19. ALL PIPE BEDDING MATERIAL SHALL CONFORM TO CITY OF AUSTIN

20.UNLESS OTHERWISE SPECIFIED BY THE ENGINEER ALL CONCRETE IS TO BE CLASS "A" (5 SACK, 3000 PSI ~ 28-DAYS), AND ALL REINFORCING STEEL TO BE

21.ALL WASTEWATER MANHOLES TO BE COATED WITH ORGANIC MATERIALS AND PROCEDURES LISTED IN CITY OF AUSTIN QUALIFIED PRODUCTS LIST NO. WW-511 (WW-511A AND WW-511B ARE NOT ALLOWED UNLESS MANHOLE IS BEING STRUCTURALLY REHABILITATED WITH APPROVAL BY PUBLIC WORKS). ALL MANHOLES WILL BE PRE-COATED OR COATED AFTER TESTING. 22.POLYBRID COATINGS ON WASTEWATER MANHOLES WILL NOT BE ALLOWED. ANY OTHER PRODUCT APPEARING ON THE COA SPL WW-511 IS

23.ALL PENETRATIONS OF EXISTING WASTEWATER MANHOLES ARE REQUIRED TO BE RE-COATED IN ACCORDANCE WITH THE SPECIFICATIONS LISTED IN

24.ALL MANHOLES WILL BE VACUUM TESTED ONLY. 25. TRACER TAPE AND MARKING TAPE SHALL BE INSTALLED ON ALL WATER

AND WASTEWATER MAINS IN ACCORDANCE WITH CITY OF AUSTIN STANDARDS, REGARDLESS OF THE TYPE OF PIPE. 26.ALL PRESSURE PIPE SHALL HAVE MECHANICAL RESTRAINT AND CONCRETE

THRUST BLOCKING AT ALL VALVES, BENDS, TEES, PLUGS, AND OTHER

1. REFER TO THE CITY OF CEDAR PARK PUBLIC WORKS UTILITY POLICY AND 2. THE TOP OF VALVE STEMS SHALL BE AT LEAST 18", AND NO MORE THAN 36",

BELOW FINISHED GRADE. VALVE STEM RISERS SHALL BE WELDED ON EACH END TO THE CITY'S SATISFACTION. 3. FIRE HYDRANT LEADS TO BE DUCTILE IRON, CLASS 350, AND INSTALLED PER

CITY OF AUSTIN STANDARD SPECIFICATIONS AND DETAIL. 4. PRIOR TO INSTALLATION OF FIRE HYDRANTS, THE ENGINEER WILL PROVIDE THE CONTRACTOR ONE (1) CUT FROM A HUB PIN, ESTABLISHING THE

5. THE ENGINEER SHALL PROVIDE CUTS FOR ALL WATER LINES AT ALL STORM SEWER CROSSINGS TO THE CITY OF CEDAR PARK. 6. PIPE MATERIALS TO BE USED FOR CONSTRUCTION OF UTILITY LINES: WATER - DUCTILE IRON OR C900 DR 14 PVC

COPPER PIPE AND FITTINGS ARE NOT PERMITTED WITHIN THE RIGHT-OF-WAY MINIMUM DR-14 12" DIA AND SMALLER. MINIMUM CLASS 250 DI LARGER THAN 12" DIA.

§ AMERICAN FLOW CONTROL. B84B

§ MUELLER COMPANY, SUPER CENTURION 250 § CLOW MEDALLION HYDRANT

- REQUIREMENTS FOR PRIVATE FIRE HYDRANTS (BEHIND DOUBLE CHECK BACKFLOW PREVENTION ASSEMBLY): MUST BE IN
- ACCORDANCE WITH CITY OF AUSTIN SPECIFICATIONS. § ALL FIRE HYDRANTS MUST MEET CITY OF CEDAR PARK THREAD SPECIFICATIONS (NATIONAL THREAD)
- **§ BLUE REFLECTOR MARKERS SHALL BE LOCATED ON THE**
- CENTERLINE OF THE PAVEMENT ACROSS FROM ALL FIRE HYDRANTS. PAVEMENT MARKERS AT INTERSECTIONS SHALL BE FOUR-SIDED. § ALL PRIVATE HYDRANTS TO BE PAINTED RED.

8. SHOULD A TAPPING SADDLE BE APPROVED BY PUBLIC WORKS, THE SADDLE SHALL BE SMITH-BLAIR 662 STAINLESS STEEL TAPPING SLEEVES WITH ALL STAINLESS HARDWARE, OR APPROVED EQUAL. REQUESTS FOR ALTERNATE PROVIDERS SHALL BE MADE TO THE CITY OF CEDAR PARK PUBLIC WORKS. NO TAP EXCEEDING 2" IN DIAMETER WILL BE

APPROVED. 9. ALL WATER LINES, INCLUDING SERVICE LINES, SHALL BE PRESSURE AND LEAK TESTED PER CITY OF AUSTIN STANDARD SPECIFICATIONS AND WITNESSED BY THE CITY OF CEDAR PARK REPRESENTATIVE. ALL TESTING IS TO BE THE RESPONSIBILITY OF THE CONTRACTOR, AND THE

CONTRACTOR MAY BE REQUIRED TO RE-TEST LINES IF THE TESTING IS NOT WITNESSED BY THE CITY. CONTRACTOR MUST NOTIFY THE CITY OF CEDAR PARK 48 HOURS PRIOR TO ANY TESTING. INITIAL WATER LINE DISINFECTION MUST MEET A CHLORINE RESIDUAL OF 50PPM. AND A CHLORINE RESIDUAL OF 25 PPM AFTER A 24 HOUR DETENTION PERIOD. SECTIONS THAT ARE 20 - 30 FEET CAN USE GRANULAR OR TABLET DISINFECTION, BUT ANYTHING BEYOND THAT MUST BE LIQUID DISINFECTION TO EVENLY CLEAN THE PIPE.

10. ALL WATER LINES SHALL BE STERILIZED AND BACTERIOLOGICALLY TESTED IN ACCORDANCE WITH CITY OF AUSTIN STANDARDS. THE CONTRACTOR IS RESPONSIBLE FOR STERILIZATION AND THE CITY OF CEDAR PARK IS RESPONSIBLE FOR SUBMITTING BACTERIOLOGICAL SAMPLES TO THE STATE. PUBLIC WORKS WILL REQUIRE A CONTRACTOR SPECIALIZED IN

DISINFECTION FOR LARGE DIAMETER LINES OR CRITICAL INFRASTRUCTURE, SUBSIDIARY TO PIPE INSTALLATION 11. DENSITY TESTING OF COMPACTED BACKFILL SHALL BE MADE AT A RATE OF

ONE TEST PER TWO FOOT LIFTS PER 500 FEET OF INSTALLED PIPE. 12. CONTRACTOR TO OBTAIN A WATER METER FROM THE CITY OF CEDAR PARK FOR ANY WATER THAT MAY BE REQUIRED DURING CONSTRUCTION. (512 - 401 - 5000)

13. ALL WATER METER BOXES SHALL BE FORD GULF METER BOX WITH LOCKING

- SINGLE G-148-233 • DUAL DG-148-243
- 1" METER YL111 444
- 1 1/2" 2" METER 1730-R (LID) & 1730-12 (BOX)/ACCEPTABLE BOXES FOR THIS SIZE OF METER
- 14. MANHOLE FRAMES AND COVERS AND WATER VALVE BOXES SHALL BE RAISED TO FINISHED PAVEMENT GRADE, WHEN IN PUBLIC STREETS, AT THE OWNER'S EXPENSE BY THE CONTRACTOR WITH CITY INSPECTION. ALL UTILITY ADJUSTMENTS SHALL BE COMPLETED PRIOR TO FINAL PAVING CONSTRUCTION
- 15. THE LOCATION OF ANY EXISTING UTILITY LINES SHOWN ON THESE PLANS IS THE BEST AVAILABLE AND MAY NOT BE ACCURATE. ANY DAMAGE TO EXISTING UTILITY LINES, BOTH KNOWN AND UNKNOWN, SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
- 16. ALL IRON PIPE AND FITTINGS SHALL BE WRAPPED WITH AT LEAST 8 MIL. POLYETHYLENE WRAP. 17. ALL WATER MAINS, WASTEWATER MAINS AND SERVICE LINES SHALL MEET

CITY OF AUSTIN SPECIFICATIONS FOR MINIMUM COVER REQUIREMENTS. ALL STREETS ARE TO BE CUT TO SUBGRADE PRIOR TO INSTALLATION OF WATER MAINS OR CUTS WILL BE ISSUED BY THE ENGINEER.

18. CITY TO BE GIVEN 48 HOURS NOTICE PRIOR TO ALL TESTING OF WATER AND WASTEWATER LINES. CITY INSPECTION IS REQUIRED FOR ALL TESTING OF WATER AND WASTEWATER LINES.

19. WHERE A WATER OR WASTEWATER LINE CROSSES ABOVE (OR BELOW) A STORM SEWER STRUCTURE AND THE BOTTOM (OR TOP) OF THE PIPE IS WITHIN 18 INCHES OF THE TOP (OR BOTTOM) OF THE UTILITY STRUCTURE THE PIPE SHALL BE ENCASED WITH CONCRETE FOR A DISTANCE OF AT LEAST 1 FT. ON EITHER SIDE OF THE DITCH LINE OF THE UTILITY

STRUCTURE OR THE STORM SEWER. CONCRETE ENCASEMENT WILL NOT BE REQUIRED FOR DUCTILE IRON (THICKNESS CLASS 50), AWWA C-900 (SDR- 18) 150 PSI RATED PVC IN SIZES TO 12 INCHES OR AWWA C-905 (SDR-25) 165 PSI RATED PVC IN SIZES LARGER THAN 12 INCHES. CONCRETE ENCASEMENT SHALL CONFORM TO C.O.A. STANDARD DETAIL 505-1.

20.CONTRACTOR TO NOTIFY THE CITY OF CEDAR PARK 48 HOURS PRIOR TO CONNECTING TO EXISTING UTILITIES. 21.ALL PIPE BEDDING MATERIAL SHALL CONFORM TO CITY OF AUSTIN

STANDARD SPECIFICATIONS. 22. TRACER TAPE SHALL BE INSTALLED ON ALL WATER AND WASTEWATER

MAINS REGARDLESS OF THE TYPE OF PIPE OR DEPTH OF PIPE INSTALLED. 23.UNLESS OTHERWISE SPECIFIED BY THE ENGINEER ALL CONCRETE IS TO BE CLASS "A" (5 SACK, 3000 PSI ~ 28-DAYS), AND ALL REINFORCING STEEL TO BE ASTM A615 60.

24. THE CITY CONSIDERS PROTECTION OF ITS WATER SYSTEM PARAMOUNT TO CONSTRUCTION ACTIVITIES, CITY PERSONNEL WILL OPERATE, OR

AUTHORIZE THE CONTRACTOR TO OPERATE, ALL WATER VALVES THAT WILL PASS THROUGH THE CITY'S POTABLE WATER. THE CONTRACTOR MAY NOT OPERATE ANY WATER VALVE, EXISTING OR PROPOSED, THAT WILL ALLOW WATER FROM THE CITY'S WATER SYSTEM TO FLOW TO A PROPOSED OR EXISTING WATER SYSTEM WITHOUT THE EXPRESS CONSENT OF THE CITY. NOTIFY THE CITY TWO BUSINESS DAYS IN ADVANCE OF ANY REQUEST TO OPERATE A WATER VALVE. THE GENERAL CONTRACTOR MAY BE FINED

\$500 OR MORE, INCLUDING ADDITIONAL THEFT OF WATER FINES, IF A WATER VALVE IS OPERATED IN AN UNAUTHORIZED MANNER, REGARDLESS OF WHO OPERATED THE VALVE. 25.ALL WATER VALVES OVER 24" IN SIZE SHALL HAVE A BY-PASS LINE AND

VALVE INSTALLED. BY-PASS VALVES AND LINES ARE SUBSIDIARY TO THE COST OF THE VALVE UNLESS SPECIFICALLY IDENTIFIED ON THE BID FORM. 26.ALL WATER VALVES, INCLUDING THOSE OVER 12" IN SIZE, SHALL BE GATE VALVES.

- 27.A DOUBLE CHECK BACKFLOW DEVICE IN A VAULT SHALL BE INSTALLED AT THE PROPERTY LINE ON ALL PRIVATE FIRE LINES. A DETECTOR WATER METER WILL BE INSTALLED ON THIS BACKFLOW DEVICE, AND IT MUST BE A SENSUS SRII 3/4" METER WITH AMI RADIO READ CAPABILITY. THE CITY WILL PROVIDE THIS METER. PLEASE REFERENCE THE CITY OF CEDAR PARK
- DOUBLE CHECK BACKFLOW PREVENTION ASSEMBLY DETAIL. 28.ALL POTABLE WATER SYSTEM COMPONENTS INSTALLED AFTER JANUARY 4, 2014, SHALL BE "LEAD FREE" ACCORDING TO THE UNITED STATES SAFE DRINKING WATER ACT. THE ONLY COMPONENTS EXEMPT FROM THIS REQUIREMENT ARE FIRE HYDRANTS. COMPONENTS THAT ARE NOT CLEARLY IDENTIFIED BY THE MANUFACTURER AS MEETING THIS REQUIREMENT BY MARKING, OR ON THE PRODUCT PACKAGING, OR BY PRE-APPROVED SUBMITTAL, WILL BE REJECTED FOR USE. A NSF CERTIFICATION WILL BE ADEQUATE IF THE CERTIFICATION HAS NOT EXPIRED AS OF JANUARY 4, 2014 AND REMAINS UNEXPIRED AT THE TIME OF CONSTRUCTION.
- 29. ALL PRESSURE PIPE SHALL HAVE MECHANICAL RESTRAINT AND CONCRETE THRUST BLOCKING AT ALL VALVES, BENDS, TEES, PLUGS, AND OTHER FITTINGS.

STORM SEWER NOTES:

- 1. MANHOLE FRAMES AND COVERS AND WATER VALVE BOXES SHALL BE RAISED TO FINISHED PAVEMENT GRADE AT THE OWNER'S EXPENSE BY THE CONTRACTOR WITH CITY INSPECTION. ALL UTILITY ADJUSTMENTS SHALL BE COMPLETED PRIOR TO FINAL PAVING CONSTRUCTION. CONTRACTOR SHALL BACKFILL AROUND MANHOLES AND JUNCTION BOXES WITH CLASS A CONCRETE.
- 2. ALL MANHOLE LIDS SHALL BE 32" OR LARGER, UNLESS EXPRESSLY
- APPROVED IN WRITING BY THE ENGINEERING DEPARTMENT. 3. THE LOCATION OF ANY EXISTING UTILITY LINES SHOWN ON THESE PLANS IS THE BEST AVAILABLE AND MAY NOT BE ACCURATE. ANY DAMAGE TO EXISTING UTILITY LINES, BOTH KNOWN AND UNKNOWN, SHALL BE REPAIRED AT THE EXPENSE OF THE CONTRACTOR.
- 4. PIPE MATERIALS TO BE USED FOR CONSTRUCTION OF UTILITY LINES:


UNLESS OTHERWISE SPECIFIED BY THE ENGINEER, ALL STORM SEWER RCP SHALL BE CLASS III. CORRUGATED METAL PIPE IS NOT PERMITTED. 5. ALL MANHOLE AND INLET COVERS SHALL READ "CITY OF CEDAR PARK".

- 6. CONTRACTOR TO NOTIFY THE CITY OF CEDAR PARK 48 HOURS PRIOR TO CONNECTING TO EXISTING
- UTILITIES. 7. ALL PIPE BEDDING MATERIAL SHALL CONFORM TO CITY OF AUSTIN
- STANDARD SPECIFICATIONS 8. UNLESS OTHERWISE SPECIFIED BY THE ENGINEER ALL CONCRETE IS TO BE CLASS "A" (5 SACK, 3000 PSI ~ 28-DAYS), AND ALL REINFORCING STEEL TO BE
- ASTM A615 60. 9. CONTRACTOR TO INSTALL AND MAINTAIN GEO-TEXTILE FABRIC BARRIER (INLET PROTECTION) AROUND STORM SEWER LEADS AND INLETS TO PREVENT SILT AND OTHER MATERIAL FROM ENTERING THE STORM SEWER
- COLLECTION SYSTEM 10. INSTALL CONCRETE SAFETY END TREATMENTS TO ALL CULVERTS AND ENDS OF DRAINAGE PIPE.
- 11. ALL CURB INLETS SHALL HAVE AN ALMETEK 4" DISC "NO DUMPING DRAINS TO WATERWAY" MARKER

SEQUENCE OF CONSTRUCTION NOTES:

THE FOLLOWING SEQUENCE OF CONSTRUCTION SHALL BE USED FOR ALL DEVELOPMENT. THE APPLICANT IS ENCOURAGED TO PROVIDE ANY ADDITIONAL DETAILS APPROPRIATE FOR THE PARTICULAR DEVELOPMENT.

- 1. TEMPORARY EROSION AND SEDIMENTATION CONTROLS ARE TO BE INSTALLED AS INDICATED ON THE APPROVED SITE PLAN OR SUBDIVISION CONSTRUCTION PLAN AND IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) THAT IS REQUIRED TO BE POSTED ON THE SITE.
- INSTALL TREE PROTECTION AND INITIATE TREE MITIGATION MEASURES. 2. THE GENERAL CONTRACTOR MUST CONTACT THE CITY INSPECTOR AT 512-401-5000, 72 HOURS PRIOR TO THE SCHEDULED DATE OF THE REQUIRED ON-SITE PRECONSTRUCTION MEETING.
- 3. THE GENERAL CONTRACTOR WILL FOLLOW THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE, TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE REVISED, IF NEEDED, TO COMPLY WITH CITY INSPECTORS' DIRECTIVES, AND REVISED CONSTRUCTION SCHEDULE RELATIVE TO THE WATER QUALITY PLAN REQUIREMENTS AND THE EROSION
- 4. ROUGH GRADE THE POND(S) AT 100% PROPOSED CAPACITY, EITHER THE PERMANENT OUTLET STRUCTURE OR A TEMPORARY OUTLET MUST BE CONSTRUCTED PRIOR TO DEVELOPMENT OF EMBANKMENT OR EXCAVATION THAT LEADS TO PONDING CONDITIONS. THE OUTLET SYSTEM MUST CONSIST OF A SUMP PIT OUTLET AND AN EMERGENCY SPILLWAY MEETING THE REQUIREMENTS OF THE CITY OF AUSTIN DRAINAGE CRITERIA MANUAL. AS REQUIRED. THE OUTLET SYSTEM SHALL BE PROTECTED FROM EROSION AND SHALL BE MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION UNTIL INSTALLATION OF THE PERMANENT WATER QUALITY POND(S).
- 5. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE.
- 6. BEGIN SITE CLEARING/CONSTRUCTION (OR DEMOLITION) ACTIVITIES. 7. UNDERGROUND UTILITIES WILL BE INSTALLED, INCLUDING FIRE HYDRANTS.
- 8. FIRE DEPARTMENT ACCESS WILL BE INSTALLED WHERE REQUIRED BY APPROVED SITE PLAN. 9. VERTICAL CONSTRUCTION MAY OCCUR AFTER THE PRE-VERTICAL
- INSPECTION HAS BEEN CLEARED BY THE FIRE MARSHAL 10.PERMANENT WATER QUALITY PONDS OR CONTROLS WILL BE CLEANED OUT AND FILTER MEDIA WILL BE INSTALLED PRIOR TO/CONCURRENTLY WITH
- REVEGETATION OF SITE. 11. COMPLETE CONSTRUCTION AND START REVEGETATION OF THE SITE AND INSTALLATION OF LANDSCAPING.
- 12. UPON COMPLETION OF THE SITE CONSTRUCTION AND REVEGETATION OF A PROJECT SITE, THE DESIGN ENGINEER SHALL SUBMIT AN ENGINEER'S LETTER OF CONCURRENCE BEARING THE ENGINEER'S SEAL, SIGNATURE, AND DATE TO THE CITY INDICATING THAT CONSTRUCTION. INCLUDING REVEGETATION, IS COMPLETE AND IN SUBSTANTIAL COMPLIANCE WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE CITY INSPECTOR
- 13. UPON COMPLETION OF LANDSCAPE INSTALLATION OF A PROJECT SITE, THE LANDSCAPE ARCHITECT SHALL SUBMIT A LETTER OF CONCURRENCE TO THE CITY INDICATING THAT THE REQUIRED LANDSCAPING IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE CITY INSPECTOR.
- 14. AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY NSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR, REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND COMPLETE ANY NECESSARY FINAL REVEGETATION RESULTING FROM REMOVAL OF THE CONTROLS. CONDUCT ANY MAINTENANCE AND REHABILITATION OF THE WATER QUALITY PONDS OR CONTROLS.



KH GENERAL NOTES

ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THESE PLANS, CITY (OR TOWN) STANDARD DETAILS AND SPECIFICATIONS, THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA, AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS, THE MORE RESTRICTIVE SPECIFICATION AND DETAIL SHALL BE FOLLOWED THE CONTRACTOR SHALL COMPLY WITH CITY (OR TOWN) "GENERAL NOTES" FOR CONSTRUCTION, IF EXISTING AND REQUIRED BY THE CITY. FOR INSTANCES WHERE THEY CONFLICT WITH THESE KH GENERAL NOTES, THEN THE MORE RESTRICTIVE SHALL APPLY 3. THE CONTRACTOR SHALL FURNISH ALL MATERIAL AND LABOR TO CONSTRUCT THE FACILITY AS SHOWN AND DESCRIBED IN THE CONSTRUCTION DOCUMENTS IN ACCORDANCE WITH THE APPROPRIATE AUTHORITIES' SPECIFICATIONS AND REQUIREMENTS THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING TO DETERMINE EXISTING CONDITIONS. 5. THE EXISTING CONDITIONS SHOWN ON THESE PLANS WERE PROVIDED BY THE TOPOGRAPHIC SURVEY PREPARED BY THE PROJECT SURVEYOR, AND ARE BASED ON THE BENCHMARKS SHOWN. THE CONTRACTOR SHALL REFERENCE THE SAME BENCHMARKS 6. THE CONTRACTOR SHALL REVIEW AND VERIFY THE EXISTING TOPOGRAPHIC SURVEY SHOWN ON THE PLANS REPRESENTS EXISTING FIELD CONDITIONS PRIOR TO CONSTRUCTION, AND SHALL REPORT ANY DISCREPANCIES FOUND TO THE OWNER AND ENGINEER IMMEDIATELY 7. IF THE CONTRACTOR DOES NOT ACCEPT THE EXISTING TOPOGRAPHIC SURVEY AS SHOWN ON THE PLANS, WITHOUT EXCEPTION, THEN THE CONTRACTOR SHALL SUPPLY AT THEIR OWN EXPENSE, A TOPOGRAPHIC SURVEY BY A REGISTERED PROFESSIONAL LAND SURVEYOR TO THE OWNER AND ENGINEER FOR REVIEW. CONTRACTOR SHALL PROVIDE ALL CONSTRUCTION SURVEYING AND STAKING. 9. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL CONTROL, INCLUDING BENCHMARKS PRIOR TO COMMENCING CONSTRUCTION OR STAKING OF IMPROVEMENTS. PROPERTY LINES AND CORNERS SHALL BE HELD AS THE HORIZONTAL CONTROL 10. THE CONTRACTOR SHALL REVIEW AND VERIFY ALL DIMENSIONS, ELEVATIONS, AND FIELD CONDITIONS THAT MAY AFFECT CONSTRUCTION. ANY DISCREPANCIES ON THE DRAWINGS SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER BEFORE COMMENCING WORK. NO FIELD CHANGES OR DEVIATIONS FROM DESIGN ARE TO BE MADE WITHOUT PRIOR APPROVAL OF THE ARCHITECT. ENGINEER, AND IF APPLICABLE THE CITY AND OWNER, NO CONSIDERATION WILL BE GIVEN TO CHANGE ORDERS FOR WHICH THE CITY, ENGINEER, AND OWNER WERE NOT CONTACTED PRIOR TO CONSTRUCTION OF THE AFFECTED ITEM. 1. CONTRACTOR SHALL THOROUGHLY CHECK COORDINATION OF CIVIL, LANDSCAPE, MEP, ARCHITECTURAL, AND OTHER PLANS PRIOR TO COMMENCING CONSTRUCTION. OWNER/ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCY PRIOR TO COMMENCING WITH CONSTRUCTION 2.IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES WHICH MAY HAVE BURIED OR AERIAL UTILITIES WITHIN OR NEAR THE CONSTRUCTION AREA BEFORE COMMENCING WORK TO HAVE THEM LOCATE THEIR EXISTING UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE AN ADEQUATE MINIMUM NOTICE TO ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION 13. CONTRACTOR SHALL CALL TEXAS 811 AN ADEQUATE AMOUNT OF TIME PRIOR TO COMMENCING CONSTRUCTION OR ANY EXCAVATION 14. CONTRACTOR SHALL USE EXTREME CAUTION AS THE SITE CONTAINS VARIOUS KNOWN AND UNKNOWN PUBLIC AND PRIVATE UTILITIES. 15. THE LOCATIONS. ELEVATIONS. DEPTH. AND DIMENSIONS OF EXISTING UTILITIES SHOWN ON THE PLANS WERE OBTAINED FROM AVAILABLE UTILITY COMPANY MAPS AND PLANS, AND ARE CONSIDERED APPROXIMATE AND INCOMPLETE. IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO VERIFY THE PRESENCE. LOCATION. ELEVATION. DEPTH. AND DIMENSION OF EXISTING UTILITIES SUFFICIENTLY IN ADVANCE OF CONSTRUCTION SO THAT ADJUSTMENTS CAN BE MADE TO PROVIDE ADEQUATE CLEARANCES. THE ENGINEER SHALL BE NOTIFIED WHEN A PROPOSED IMPROVEMENT CONFLICTS WITH AN EXISTING UTILITY 6. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY ADJUSTMENTS AND RELOCATIONS OF EXISTING UTILITIES THAT CONFLICT WITH THE PROPOSED IMPROVEMENTS. INCLUDING BUT NOT LIMITED TO. ADJUSTING EXISTING MANHOLES TO MATCH PROPOSED GRADE, RELOCATING EXISTING POLES AND GUY WIRES THAT ARE LOCATED IN PROPOSED DRIVEWAYS, ADJUSTING THE HORIZONTAL OR VERTICAL ALIGNMENT OF EXISTING UNDERGROUND UTILITIES TO ACCOMMODATE PROPOSED GRADE OR CROSSING WITH A PROPOSED UTILITY, AND ANY OTHERS THAT MAY BE ENCOUNTERED THAT ARE UNKNOWN AT THIS TIME AND NOT SHOWN ON THESE PLANS. 7. CONTRACTOR SHALL ARRANGE FOR OR PROVIDE, AT ITS EXPENSE, ALL GAS, TELECOMMUNICATIONS, CABLE, OVERHEAD AND UNDERGROUND POWER LINE. AND UTILITY POLE ADJUSTMENTS NEEDED. 18. CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION OF FRANCHISE UTILITIES THAT ARE NECESSARY FOR ON-SITE AND OFF-SITE CONSTRUCTION, AND SERVICE TO THE PROPOSED DEVELOPMENT. 19. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ALL DAMAGES DUE TO THE CONTRACTORS' FAILURE TO EXACTLY LOCATE AND PRESERVE ALL UTILITIES. THE OWNER OR ENGINEER WILL ASSUME NO LIABILITY FOR ANY DAMAGES SUSTAINED OR COST INCURRED BECAUSE OF THE OPERATIONS IN THE VICINITY OF EXISTING UTILITIES OR STRUCTURES. IF IT IS NECESSARY TO SHORE, BRACE, SWING OR RELOCATE A UTILITY, THE UTILITY COMPANY OR DEPARTMENT AFFECTED SHALL BE CONTACTED BY THE CONTRACTOR AND THEIR PERMISSION OBTAINED REGARDING THE METHOD TO USE FOR SUCH WORK. 20. BRACING OF UTILITY POLES MAY BE REQUIRED BY THE UTILITY COMPANIES WHEN TRENCHING OR EXCAVATING IN CLOSE PROXIMITY TO THE POLES. THE COST OF BRACING POLES WILL BE BORNE BY THE CONTRACTOR, WITH NO SEPARATE PAY ITEM FOR THIS WORK. THE COST IS INCIDENTAL TO THE PAY ITEM 1.CONTRACTOR SHALL USE ALL NECESSARY SAFETY PRECAUTIONS TO AVOID CONTACT WITH OVERHEAD AND UNDERGROUND POWER LINES. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE, FEDERAL AND UTILITY OWNER REGULATIONS PERTAINING TO WORK SETBACKS FROM POWER LINES. 22. THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL REQUIRED CONSTRUCTION PERMITS, APPROVALS, AND BONDS PRIOR TO CONSTRUCTION. 23. THE CONTRACTOR SHALL HAVE AVAILABLE AT THE JOB SITE AT ALL TIMES A COPY OF THE CONTRACT DOCUMENTS INCLUDING PLANS. GEOTECHNICAL REPORT AND ADDENDA, PROJECT AND CITY SPECIFICATIONS, AND SPECIAL CONDITIONS, COPIES OF ANY REQUIRED CONSTRUCTION PERMITS FROSION CONTROL PLANS SWPPP AND INSPECTION REPORTS 24.ALL SHOP DRAWINGS AND OTHER DOCUMENTS THAT REQUIRE ENGINEER REVIEW SHALL BE SUBMITTED BY THE CONTRACTOR SUFFICIENTLY IN ADVANCE OF CONSTRUCTION OF THAT ITEM, SO THAT NO LESS THAN 10 BUSINESS DAYS FOR REVIEW AND RESPONSE IS AVAILABLE. 25 ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES. JURISDICTIONAL AGENCIES. AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO USE OF THE FACILITY AND THE FINAL CONNECTION OF SERVICES. 26.CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 27.CONTRACTOR'S BID PRICE SHALL INCLUDE ALL INSPECTION FEES. 28.ALL SYMBOLS SHOWN ON THESE PLANS (E.G. FIRE HYDRANT, METERS, VALVES, INLETS, ETC....) ARE FOR PRESENTATION PURPOSES ONLY AND ARE NOT TO SCALE. CONTRACTOR SHALL COORDINATE FINAL SIZES AND LOCATIONS WITH APPROPRIATE CITY INSPECTOR 29. THE SCOPE OF WORK FOR THE CIVIL IMPROVEMENTS SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. REFERENCE THE BUILDING PLANS (E.G. ARCHITECTURAL, STRUCTURAL, MEP) FOR AREAS WITHIN 5-FEET OF THE BUILDING AND WITHIN THE BUILDING FOOTPRINT 0.REFER TO ARCHITECTURAL AND STRUCTURAL PLANS FOR ALL FINAL BUILDING DIMENSIONS 31. THE PROPOSED BUILDING FOOTPRINT(S) SHOWN IN THESE PLANS WAS PROVIDED TO KIMLEY-HORN AND ASSOCIATES, INC. (KH) BY THE PROJECT ARCHITECT AT THE TIME THESE PLANS WERE PREPARED. IT MAY NOT BE THE FINAL CORRECT VERSION BECAUSE THE BUILDING DESIGN WAS ONGOING. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONFIRMING THE FINAL CORRECT VERSION OF THE BUILDING FOOTPRINT WITH THE ARCHITECT AND STRUCTURAL ENGINEER PRIOR TO LAYOUT. DIMENSIONS AND/OR COORDINATES SHOWN ON THESE PLANS WERE BASED ON THE ABOVE STATED ARCHITECTURAL FOOTPRINT AND ARE THEREFORE A PREI IMINARY LOCATION OF THE BUILDING. THE CONTRACTOR IS SOLELY RESPONSIBLE TO VERIFY WHAT PART OF THE BUILDING THE ARCHITECT'S FOOTPRINT REPRESENTS (E.G. SLAB, OUTSIDE WALL, MASONRY LEDGE, ETC) AND TO CONFIRM ITS FINAL POSITION ON THE SITE BASED ON THE FINAL ARCHITECTURAL FOOTPRINT, CIVIL DIMENSION CONTROL PLAN, SURVEY BOUNDARY AND/OR PLAT. ANY DIFFERENCES FOUND SHALL BE REPORTED TO KH IMMEDIATELY. 32.ALL CONSTRUCTION SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING SUBSEQUENT ADDENDA 3. CONTRACTOR IS RESPONSIBLE FOR ALL MATERIALS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL MATERIALS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND COMPLY WITH CITY STANDARD SPECIFICATIONS AND GEOTECHNICAL REPORT. TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING MATERIALS. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR MATERIALS TESTING 34.ALL COPIES OF MATERIALS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING AGENCY. 35.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW. BY THE STANDARD TESTING PROCEDURES OF THE MATERIALS. THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 36.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING. IF NONE IS CURRENTLY EXISTING. 37.ALL CONTRACTORS MUST CONFINE THEIR ACTIVITIES TO THE WORK AREA. NO ENCROACHMENTS OUTSIDE OF THE WORK AREA WILL BE ALLOWED. ANY DAMAGE RESULTING THEREFROM SHALL BE CONTRACTOR'S SOLE RESPONSIBILITY TO REPAIR. 38. THE CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES, UTILITIES, MANHOLES, POLES, GUY WIRES, VALVE COVERS, VAULT LIDS, FIRE HYDRANTS, COMMUNICATION BOXES/PEDESTALS, AND OTHER FACILITIES TO REMAIN AND SHALL REPAIR ANY DAMAGES AT NO COST TO THE OWNER. 39. THE CONTRACTOR SHALL IMMEDIATELY REPAIR OR REPLACE ANY PHYSICAL DAMAGE TO PRIVATE PROPERTY OR PUBLIC IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO: FENCES, WALLS, SIGNS, PAVEMENT, CURBS, UTILITIES, SIDEWALKS, GRASS, TREES, LANDSCAPING, AND IRRIGATION SYSTEMS, ETC.... TO ORIGINAL CONDITION OR BETTER AT NO COST TO THE OWNER. 40.ALL AREAS IN EXISTING RIGHT-OF-WAY DISTURBED BY SITE CONSTRUCTION SHALL BE REPAIRED TO ORIGINAL CONDITION OR BETTER, INCLUDING AS NECESSARY GRADING, LANDSCAPING, CULVERTS, AND PAVEMENT 41.THE CONTRACTOR SHALL SALVAGE ALL EXISTING POWER POLES, SIGNS, WATER VALVES, FIRE HYDRANTS, METERS, ETC.. THAT ARE TO BE RELOCATED DURING CONSTRUCTION. 42.CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. 43. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN. PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 44. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER. 45.SITE SAFETY IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR 46. THESE PLANS DO NOT EXTEND TO OR INCLUDE DESIGNS OR SYSTEMS PERTAINING TO THE SAFETY OF THE CONTRACTOR OR ITS EMPLOYEES, AGENTS OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE ENGINEER'S SEAL HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF ALL REQUIRED SAFETY PROCEDURES AND PROGRAMS. 47. SIGNS RELATED TO SITE OPERATION OR SAFETY ARE NOT INCLUDED IN THESE PLANS. 48.CONTRACTOR OFFICE AND STAGING AREA SHALL BE AGREED ON BY THE OWNER AND CONTRACTOR PRIOR TO BEGINNING OF CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR ALL PERMITTING REQUIREMENTS FOR THE CONSTRUCTION OFFICE, TRAILER, STORAGE, AND STAGING OPERATIONS AND LOCATIONS. 49.LIGHT POLES, SIGNS, AND OTHER OBSTRUCTIONS SHALL NOT BE PLACED IN ACCESSIBLE ROUTES. 50.ALL SIGNS, PAVEMENT MARKINGS, AND OTHER TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES". 51. TOP RIM ELEVATIONS OF ALL EXISTING AND PROPOSED MANHOLES SHALL BE COORDINATED WITH TOP OF PAVEMENT OR FINISHED GRADE AND SHALL BE ADJUSTED TO BE FLUSH WITH THE ACTUAL FINISHED GRADE AT THE TIME OF PAVING. 52.CONTRACTOR SHALL ADJUST ALL EXISTING AND PROPOSED VALVES, FIRE HYDRANTS, AND OTHER UTILITY APPURTENANCES TO MATCH ACTUAL FINISHED GRADES AT THE TIME OF PAVING. 53. THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND PHASING, AND SHALL CONTACT THE APPROPRIATE CITY OFFICIALS, INCLUDING BUILDING OFFICIAL, ENGINEERING INSPECTOR, AND FIRE MARSHALL TO LEARN OF ANY REQUIREMENTS.

55. CONTRACTOR SHALL KEEP A NEAT AND ACCURATE RECORD OF CONSTRUCTION, INCLUDING ANY DEVIATIONS OR VARIANCES FROM THE PLANS. 56. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AS-BUILT PLANS TO THE ENGINEER AND CITY IDENTIFYING ALL DEVIATIONS AND VARIATIONS FROM THESE PLANS MADE DURING CONSTRUCTION.

EROSION CONTRO

- THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL EROSION CONTROL AND WATER QUALITY REQUIREMENTS, LAWS, AND ORDINANCES THAT APPLY TO THE CONSTRUCTION SITE LAND DISTURBANCE
- 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE "TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000'
- THE START OF LAND DISTURBANCE. FOR THE PROJECT.
- 5. CONTRACTOR IS SOLELY RESPONSIBLE FOR INSTALLATION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL
- DURING CONSTRUCTION AS FIELD CONDITIONS CHANGE BMP EMPLOYED IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IF APPLICABLE.
- INLET PER APPROVED DETAILS
- 8. THE EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE AREA IT PROTECTS HAS BEEN PERMANENTLY STABILIZED.
- 9. CONTRACTOR SHALL PROVIDE ADEQUATE EROSION CONTROL DEVICES NEEDED DUE TO PROJECT PHASING NOT EFFECTIVELY CONTROL EROSION AND PREVENT SEDIMENTATION FROM WASHING OFF THE SITE, THEN THE
- CONTRACTOR SHALL NOTIFY THE ENGINEER BMP'S TO CONTROL FROSION AND SEDIMENTATION AND THE ESTABLISHMENT OF PERMANENT GROUND COVER ON AND EROSION CONTROL PLAN TO INCLUDE BMPS FOR ANY OFF-SITE THAT ARE NOT ANTICIPATED OR SHOWN ON THE EROSION CONTROL PLAN.
- COVERING OR ENCIRCLING THE AREA WITH AN APPROPRIATE BARRIER 13. CONTRACTORS SHALL INSPECT ALL EROSION CONTROL DEVICES, BMPS, DISTURBED AREAS, AND VEHICLE ENTRY AND EXIT
- FUNCTIONING PROPERLY 14. CONTRACTOR SHALL CONSTRUCT A STABILIZED CONSTRUCTION ENTRANCE AT ALL PRIMARY POINTS OF ACCESS IN
- STABILIZED ENTRANCE AT ALL TIMES FOR ALL INGRESS/EGRESS. 15. SITE ENTRY AND EXITS SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT THE TRACKING AND FLOWING OF
- OFF-SITE ROADWAY SHALL BE REMOVED IMMEDIATELY
- DAY FOR THE OFF-SITE ROADWAYS.
- AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP BMP. ON THESE PLANS, THEN THE CONTRACTOR SHALL ARRANGE FOR AN APPROPRIATE DESIGN TO BE PROVIDED
- 19 ALL FINES IMPOSED FOR SEDIMENT OR DIRT DISCHARGED FROM THE SITE SHALL BE PAID BY THE RESPONSIBLE CONTRACTOR
- CONTROL SEDIMENTATION. PERIODIC RE-GRADING OR NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFECTIVENESS OF THE CONSTRUCTION ENTRANCE
- 22.CONTRACTOR SHALL FOLLOW GOOD HOUSEKEEPING PRACTICES DURING CONSTRUCTION, ALWAYS CLEANING UP DIRT, I OOSE MATERIAL AND TRASH AS CONSTRUCTION PROGRESSES 23.UPON COMPLETION OF FINE GRADING, ALL SURFACES OF DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED.
- BUILDINGS, SIDEWALK, PAVEMENT, OR A UNIFORM PERENNIAL VEGETATIVE COVER. 24 AT THE CONCLUSION OF THE PROJECT, ALL INLETS, DRAIN PIPE, CHANNELS, DRAINAGEWAYS AND BORROW DITCHES
- REMOVED AND DISPOSED IN ACCORDANCE WITH APPLICABLE REGULATIONS.

STORM WATER DISCHARGE AUTHORIZATION

- 2. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE TCEQ GENERAL PERMIT TO DISCHARGE UNDER THE TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM TXR 150000.
- COMMENCING CONSTRUCTION (IF APPLICABLE), OR IF UTILIZING ELECTRONIC SUBMITTAL, PRIOR TO COMMENCING
- (TYPICALLY THE CITY) RECEIVING DISCHARGE FROM THE SITE. 4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN
- INFORMATION REQUIRED BY THE TCEQ AND EPA (E.G. NOI). 5. ALL CONTRACTORS AND SUBCONTRACTORS PROVIDING SERVICES RELATED TO THE SWPPP SHALL SIGN THE REQUIRED
- SUBMITTED TO THE CITY BY THE CONTRACTOR AND SHALL BE RETAINED ON-SITE DURING CONSTRUCTION.
- SOIL DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED AND A UNIFORM VEGETATIVE COVER HAS BEEN THE NOT SHALL BE PROVIDED TO THE OPERATOR OF ANY MS4 RECEIVING DISCHARGE FROM THE SITE.

PLAN. THIS PRELIMINARY DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS ON THE SUBJECT TRACT THAT ARE TO

- BE DEMOLISHED AND REMOVED FROM THE SITE 2. KH DOES NOT WARRANT OR REPRESENT THAT THE PLAN, WHICH WAS PREPARED BASED ON SURVEY AND UTILITY AND UTILITIES THE ABILITY AND PROCESS FOR THE REMOVAL OF THEIR FACILITIES.
- 3. THIS PLAN IS INTENDED TO GIVE A GENERAL GUIDE TO THE CONTRACTOR, NOTHING MORE. THE GOAL OF THE DEMOLITION IS TO LEAVE THE SITE IN A STATE SUITABLE FOR THE CONSTRUCTION OF THE PROPOSED DEVELOPMENT. REMOVAL OR PRESERVATION OF IMPROVEMENTS. UTILITIES. ETC. TO ACCOMPLISH THIS GOAL ARE THE RESPONSIBILITY OF THE CONTRACTOR
- BIDDING AND IMPLEMENTING THE DEMOLITION PLAN:
- a ENVIRONMENTAL SITE ASSESSMENT PROVIDED BY THE OWNER
- b. ASBESTOS BUILDING INSPECTION REPORT(S) PROVIDED BY THE OWNER. c. GEOTECHNICAL REPORT PROVIDED BY THE OWNER.
- d. OTHER REPORTS THAT ARE APPLICABLE AND AVAILABLE.
- CITED REPORTS HAVE BEEN PREPARED AND TO OBTAIN/REVIEW/AND COMPLY WITH THE RECOMMENDATION OF SUCH STUDIES PRIOR TO STARTING ANY WORK ON THE SITE
- 6. CONTRACTOR SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS REGARDING THE DEMOLITION OF OBJECTS ON THE SITE AND THE DISPOSAL OF THE DEMOLISHED MATERIALS OFF-SITE. IT IS THE CONTRACTOR'S SOLE AUTHORIZATIONS, AND COMPLY.
- 7. KH DOES NOT REPRESENT THAT THE REPORTS AND SURVEYS REFERENCED ABOVE ARE ACCURATE, COMPLETE, OR
- COMPREHENSIVE SHOWING ALL ITEMS THAT WILL NEED TO BE DEMOLISHED AND REMOVED. FOUNDATIONS OR WALLS, THAT ARE ALSO TO BE REMOVED.

- NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES.
- 2. CONTRACTOR SHALL OBTAIN ANY REQUIRED GRADING PERMITS FROM THE CITY. 3. UNLESS OTHERWISE NOTED, PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN IN PAVED AREA REFLECT TOP OF GRADE FOR TOP OF CURB ELEVATION.
- 4. PROPOSED SPOT ELEVATIONS AND CONTOURS OUTSIDE THE PAVEMENT ARE TO TOP OF FINISHED GRADE. CASE OF DISCREPANCY
- 6. ALL FINISHED GRADES SHALL TRANSITION UNIFORMLY BETWEEN THE FINISHED ELEVATIONS SHOWN. 7. CONTOURS AND SPOT GRADES SHOWN ARE ELEVATIONS OF TOP OF THE FINISHED SURFACE. WHEN PERFORMING THE THICKNESS OF PAVEMENT, SIDEWALK, TOPSOIL, MULCH, STONE, LANDSCAPING, RIP-RAP AND ALL OTHER SURFACE
- AREAS IS THE BOTTOM OF THE PAVEMENT SECTION SIGNIFICANT VARIANCE FROM A BALANCED SITE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CIVIL FNGINFFR
- INCLUDING SUBSEQUENT ADDENDA
- DISPOSED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE.
- INFORMATION AND REQUIREMENTS. PROPERTY LINE AND SITE IMPROVEMENTS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY ENGINEERING AND

- 54.CONTRACTOR IS RESPONSIBLE FOR PREPARATION, SUBMITTAL, AND APPROVAL BY THE CITY OF A TRAFFIC CONTROL PLAN PRIOR TO THE START OF CONSTRUCTION, AND THEN THE IMPLEMENTATION OF THE PLAN.

3. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO

4. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS

EROSION CONTROL DEVICES, BEST MANAGEMENT PRACTICES (BMPS), AND FOR UPDATING THE EROSION CONTROL PLAN 6. CONTRACTOR SHALL DOCUMENT THE DATES OF INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL FOR EACH

7. AS STORM SEWER INLETS ARE INSTALLED ON-SITE, TEMPORARY EROSION CONTROL DEVICES SHALL BE INSTALLED AT EACH

10. CONTRACTOR SHALL OBSERVE THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES AND MAKE FIELD ADJUSTMENTS AND MODIFICATIONS AS NEEDED TO PREVENT SEDIMENT FROM LEAVING THE SITE. IF THE EROSION CONTROL DEVICES DO

11. OFF-SITE SOIL BORROW, SPOIL, AND STORAGE AREAS (IF APPLICABLE) ARE CONSIDERED AS PART OF THE PROJECT SITE AND MUST ALSO COMPLY WITH THE EROSION CONTROL REQUIREMENTS FOR THIS PROJECT. THIS INCLUDES THE INSTALLATION OF DISTURBED AREAS PRIOR TO FINAL APPROVAL OF THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP

12. ALL STAGING, STOCKPILES, SPOIL, AND STORAGE SHALL BE LOCATED SUCH THAT THEY WILL NOT ADVERSELY AFFECT STORM WATER QUALITY. PROTECTIVE MEASURES SHALL BE PROVIDED IF NEEDED TO ACCOMPLISH THIS REQUIREMENT. SUCH AS

AREAS WEEKLY AND WITHIN 24 HOURS OF ALL RAINFALL EVENTS OF 0.5 INCHES OR GREATER, AND KEEP A RECORD OF THIS INSPECTION IN THE SWPPP BOOKLET IF APPLICABLE, TO VERIFY THAT THE DEVICES AND EROSION CONTROL PLAN ARE

ACCORDANCE WITH CITY SPECIFICATIONS. CONTRACTOR SHALL ENSURE THAT ALL CONSTRUCTION TRAFFIC USES THE

SEDIMENT AND DIRT ONTO OFF-SITE ROADWAYS ALL SEDIMENT AND DIRT FROM THE SITE THAT IS DEPOSITED ONTO AN

16. THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL SILT AND DEBRIS FROM THE AFFECTED OFF-SITE ROADWAYS THAT ARE A RESULT OF THE CONSTRUCTION, AS REQUESTED BY OWNER AND CITY. AT A MINIMUM, THIS SHOULD OCCUR ONCE PER

17. WHEN WASHING OF VEHICLES IS REQUIRED TO REMOVE SEDIMENT PRIOR TO EXITING THE SITE, IT SHALL BE DONE IN AN 18. CONTRACTOR SHALL INSTALL A TEMPORARY SEDIMENT BASIN FOR ANY ON-SITE DRAINAGE AREAS THAT ARE GREATER THAN 10 ACRES, PER TCEQ AND CITY STANDARDS. IF NO ENGINEERING DESIGN HAS BEEN PROVIDED FOR A SEDIMENTATION BASIN

20. WHEN SEDIMENT OR DIRT HAS CLOGGED THE CONSTRUCTION ENTRANCE VOID SPACES BETWEEN STONES OR DIRT IS BEING TRACKED ONTO A ROADWAY, THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASH-DOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO

21. TEMPORARY SEEDING OR OTHER APPROVED STABILIZATION SHALL BE INITIATED WITHIN 14 DAYS OF THE LAST DISTURBANCE OF ANY AREA, UNLESS ADDITIONAL CONSTRUCTION IN THE AREA IS EXPECTED WITHIN 21 DAYS OF THE LAST DISTURBANCE.

STABILIZATION IS ACHIEVED WHEN THE AREA IS EITHER COVERED BY PERMANENT IMPERVIOUS STRUCTURES, SUCH AS

AFFECTED BY THE CONSTRUCTION SHALL BE DREDGED. AND THE SEDIMENT GENERATED BY THE PROJECT SHALL BE

CONTRACTOR SHALL COMPLY WITH ALL TCEQ AND EPA STORM WATER POLLUTION PREVENTION REQUIREMENTS.

3. THE CONTRACTOR SHALL ENSURE THAT ALL PRIMARY OPERATORS SUBMIT A NOI TO TCEQ AT LEAST SEVEN DAYS PRIOR TO CONSTRUCTION ALL PRIMARY OPERATORS SHALL PROVIDE A COPY OF THE SIGNED NOLTO THE OPERATOR OF ANY MS4

(SWPPP) IF APPLICABLE, INCLUDING POSTING SITE NOTICE, INSPECTIONS, DOCUMENTATION, AND SUBMISSION OF ANY

CONTRACTOR CERTIFICATION STATEMENT ACKNOWLEDGING THEIR RESPONSIBILITIES AS SPECIFIED IN THE SWPPP 6. A COPY OF THE SWPPP, INCLUDING NOI, SITE NOTICE, CONTRACTOR CERTIFICATIONS, AND ANY REVISIONS, SHALL BE 7. A NOTICE OF TERMINATION (NOT) SHALL BE SUBMITTED TO TCEQ BY ANY PRIMARY OPERATOR WITHIN 30 DAYS AFTER ALL

ESTABLISHED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY STRUCTURES, A TRANSFER OF OPERATIONAL CONTROL HAS OCCURRED. OR THE OPERATOR HAS OBTAINED ALTERNATIVE AUTHORIZATION UNDER A DIFFERENT PERMIT. A COPY OF

INFORMATION PROVIDED BY OTHERS, SHOWS ALL IMPROVEMENTS AND UTILITIES, THAT THE IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY. OR THAT THE UTILITIES SHOWN CAN BE REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING ITS OWN SITE RECONNAISSANCE TO SCOPE ITS WORK AND TO CONFIRM WITH THE OWNERS OF IMPROVEMENTS

4. CONTRACTOR IS STRONGLY CAUTIONED TO REVIEW THE FOLLOWING REPORTS DESCRIBING SITE CONDITIONS PRIOR TO

5. CONTRACTOR SHALL CONTACT THE OWNER TO VERIFY WHETHER ADDITIONAL REPORTS OR AMENDMENTS TO THE ABOVE

RESPONSIBILITY TO REVIEW THE SITE, DETERMINE THE APPLICABLE REGULATIONS, RECEIVE THE REQUIRED PERMITS AND

8. SURFACE PAVEMENT INDICATED MAY OVERLAY OTHER HIDDEN STRUCTURES, SUCH AS ADDITIONAL LAYERS OF PAVEMENT,

THE CONTRACTOR AND GRADING SUBCONTRACTOR SHALL VERIFY THE SUITABILITY OF EXISTING AND PROPOSED SITE CONDITIONS INCLUDING GRADES AND DIMENSIONS BEFORE START OF CONSTRUCTION. THE CIVIL ENGINEER SHALL BE

PAVEMENT SURFACE. IN LOCATIONS ALONG A CURB LINE, ADD 6-INCHES (OR THE HEIGHT OF THE CURB) TO THE PAVING

5. PROPOSED CONTOURS ARE APPROXIMATE. PROPOSED SPOT ELEVATIONS AND DESIGNATED GRADIENT ARE TO BE USED IN

GRADING OPERATIONS, THE CONTRACTOR SHALL PROVIDE AN APPROPRIATE ELEVATION HOLD-DOWN ALLOWANCE FOR THE

MATERIALS THAT WILL CONTRIBUTE TO THE TOP OF FINISHED GRADE. FOR EXAMPLE, THE LIMITS OF EARTHWORK IN PAVED 8. NO REPRESENTATIONS OF EARTHWORK QUANTITIES OR SITE BALANCE ARE MADE BY THESE PLANS. THE CONTRACTOR SHALL PROVIDE THEIR OWN EARTHWORK CALCULATION TO DETERMINE THEIR CONTRACT QUANTITIES AND COST. ANY

9. ALL GRADING AND EARTHWORK SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION),

10. ALL EXCAVATION IS UNCLASSIFIED AND SHALL INCLUDE ALL MATERIALS ENCOUNTERED. UNUSABLE EXCAVATED MATERIAL AND ALL WASTE RESULTING FROM SITE CLEARING AND GRUBBING SHALL BE REMOVED FROM THE SITE AND APPROPRIATELY

11. EROSION CONTROL DEVICES SHOWN ON THE EROSION CONTROL PLAN FOR THE PROJECT SHALL BE INSTALLED PRIOR TO THE START OF GRADING. REFERENCE EROSION CONTROL PLAN, DETAILS, GENERAL NOTES, AND SWPPP FOR ADDITIONAL

12. BEFORE ANY EARTHWORK IS PERFORMED, THE CONTRACTOR SHALL STAKE OUT AND MARK THE LIMITS OF THE PROJECT'S

- SURVEYING FOR LINE AND GRADE CONTROL POINTS RELATED TO FARTHWORK 13 CONTRACTOR TO DISPOSE OF ALL EXCESS EXCAVATION MATERIALS IN A MANNER THAT ADHERES TO LOCAL. STATE AND FEDERAL LAWS AND REGULATIONS. THE CONTRACTOR SHALL KEEP A RECORD OF WHERE EXCESS EXCAVATION WAS
- DISPOSED, ALONG WITH THE RECEIVING LANDOWNER'S APPROVAL TO DO SO. 14. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF TOPSOIL AT THE COMPLETION OF FINE GRADING. CONTRACTOR SHALL REFER TO LANDSCAPE ARCHITECTURE PLANS FOR SPECIFICATIONS AND REQUIREMENTS FOR TOPSOIL
- 15. CONTRACTOR SHALL MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION, INCLUDING MAINTAINING EXISTING DITCHES OR CULVERTS FREE OF OBSTRUCTIONS AT ALL TIMES. 16.NO EARTHWORK FILL SHALL BE PLACED IN ANY EXISTING DRAINAGE WAY, SWALE, CHANNEL, DITCH, CREEK, OR FLOODPLAIN FOR ANY REASON OR ANY LENGTH OF TIME, UNLESS THESE PLANS SPECIFICALLY INDICATE THIS IS REQUIRED.
- 17. TEMPORARY CULVERTS MAY BE REQUIRED IN SOME LOCATIONS TO CONVEY RUN-OFF 18. REFER TO DIMENSION CONTROL PLAN, AND PLAT FOR HORIZONTAL DIMENSIONS
- 19. THE CONTRACTOR SHALL CLEAR AND GRUB THE SITE AND PLACE, COMPACT, AND CONDITION FILL PER THE PROJECT GEOTECHNICAL ENGINEER'S SPECIFICATIONS. THE FILL MATERIAL TO BE USED SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT
- 20. CONTRACTOR IS RESPONSIBLE FOR ALL SOILS TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL SOILS TESTING SHALL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR AND SHALL COMPLY WITH CITY STANDARD SPECIFICATIONS AND THE GEOTECHNICAL REPORT. SOILS TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING SOILS. THE OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR SOILS TESTING.
- 21.ALL COPIES OF SOILS TEST RESULTS SHALL BE SENT TO THE OWNER, ENGINEER AND ARCHITECT DIRECTLY FROM THE TESTING AGENCY. 22.IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE SOILS, THAT
- THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS. 23 THE SCOPE OF WORK FOR CIVIL IMPROVEMENT SHOWN ON THESE PLANS TERMINATES 5-FEET FROM THE BUILDING. CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT AND STRUCTURAL PLANS AND SPECIFICATIONS FILL, CONDITIONING, AND PREPARATION IN THE BUILDING PAD.
- 24.DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING, THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING. IF NONE IS CURRENTLY EXISTING.
- 25.CONTRACTOR SHALL ENSURE THAT SUFFICIENT POSITIVE SLOPE AWAY FROM THE BUILDING PAD IS ACHIEVED FOR ENTIRE PERIMETER OF THE PROPOSED BUILDING(S) DURING GRADING OPERATIONS AND IN THE FINAL CONDITION. IF THE CONTRACTOR OBSERVES THAT THIS WILL NOT BE ACHIEVED, THE CONTRACTOR SHALL CONTACT THE ENGINEER TO REVIEW THE LOCATION. 26. THE CONTRACTOR SHALL TAKE ALL AVAILABLE PRECAUTIONS TO CONTROL DUST. CONTRACTOR SHALL CONTROL DUST BY
- SPRINKLING WATER, OR BY OTHER MEANS APPROVED BY THE CITY, AT NO ADDITIONAL COST TO THE OWNER. 27.CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES FOR ANY REQUIRED UTILITY ADJUSTMENTS AND/OR RELOCATIONS NEEDED FOR GRADING OPERATIONS AND TO ACCOMMODATE PROPOSED GRADE, INCLUDING THE UNKNOWN UTILITIES NOT SHOWN ON THESE PLANS. CONTRACTOR SHALL REFER TO THE GENERAL NOTES "OVERALL" SECTION THESE
- PLANS FOR ADDITIONAL INFORMATION 28.EXISTING TREE LOCATIONS SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL REPORT ANY DISCREPANCIES FOUND IN THE FIELD THAT AFFECT THE GRADING PLAN TO THE CIVIL ENGINEER. 29. CONTRACTOR SHALL FIELD VERIFY ALL PROTECTED TREE LOCATIONS, INDIVIDUAL PROTECTED TREE CRITICAL ROOT ZONES.
- AND PROPOSED SITE GRADING. AND NOTIFY THE CIVIL ENGINEER AND LANDSCAPE ARCHITECT OF ANY CONFLICTS WITH THE TREE PRESERVATION PLAN BY THE LANDSCAPE ARCHITECT PRIOR TO COMMENCING THE WORK 30. TREE PROTECTION MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH THE CITY STANDARD TREE PROTECTION DETAILS
- AND THE APPROVED TREE PRESERVATION PLANS BY THE LANDSCAPE ARCHITECT. 31.CONTRACTOR SHALL REFER TO THE LANDSCAPING AND TREE PRESERVATIONS PLANS FOR ALL INFORMATION AND DETAILS REGARDING EXISTING TREES TO BE REMOVED AND PRESERVED 32.NO TREE SHALL BE REMOVED UNLESS A TREE REMOVAL PERMIT HAS BEEN ISSUED BY THE CITY, OR CITY HAS OTHERWISE
- CONFIRMED IN WRITING THAT ONE IS NOT NEEDED FOR THE TREE(S). 33.NO TREE SHALL BE REMOVED OR DAMAGED WITHOUT PRIOR AUTHORIZATION OF THE OWNER OR OWNER'S REPRESENTATIVE. EXISTING TREES SHALL BE PRESERVED WHENEVER POSSIBLE AND GRADING IMPACT TO THEM HELD TO A MINIMUM.
- 34 AFTER PLACEMENT OF SUBGRADE AND PRIOR TO PLACEMENT OF PAVEMENT, CONTRACTOR SHALL TEST AND OBSERVE PAVEMENT AREAS FOR EVIDENCE OF PONDING AND INADEQUATE SLOPE FOR DRAINAGE. ALL AREAS SHALL ADEQUATELY DRAIN TOWARDS THE INTENDED STRUCTURE TO CONVEY STORMWATER RUNOFF. CONTRACTOR SHALL IMMEDIATELY NOTIFY OWNER AND ENGINEER IF ANY AREAS OF POOR DRAINAGE ARE DISCOVERED
- 35. CONTRACTOR FIELD ADJUSTMENT OF PROPOSED SPOT GRADES IS ALLOWED, IF THE APPROVAL OF THE CIVIL ENGINEER IS OBTAINED.

TAINING WALLS RETAINING WALLS SHOWN ARE FOR SITE GRADING PURPOSES ONLY, AND INCLUDE ONLY LOCATION AND SURFACE SPOT ELEVATIONS AT THE TOP AND BOTTOM OF THE WALL.

- . RETAINING WALL TYPE OR SYSTEM SHALL BE SELECTED BY THE OWNER. 3. RETAINING WALL DESIGN SHALL BE PROVIDED BY OTHERS AND SHALL FIT IN THE WALL ZONE OR LOCATION SHOWN ON THESE PLANS. STRUCTURAL DESIGN AND PERMITTING OF RETAINING WALLS, RAILINGS, AND OTHER WALL SAFETY DEVICES SHALL
- BE PERFORMED BY A LICENSED ENGINEER AND ARE NOT PART OF THIS PLAN SET.
- 4. RETAINING WALL DESIGN SHALL MEET THE INTENT OF THE GRADING PLAN AND SHALL ACCOUNT FOR ANY INFLUENCE ON ADJACENT BUILDING FOUNDATIONS, UTILITIES, PROPERTY LINES AND OTHER CONSTRUCTABILITY NOTES.

5. RETAINING WALL ENGINEER SHALL CONSULT THESE PLANS AND THE GEOTECHNICAL REPORT FOR POTENTIAL CONFLICTS. 1. ALL PAVING MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THESE PLANS, THE CITY STANDARD DETAILS

- AND SPECIFICATIONS, THE FINAL GEOTECHNICAL REPORT AND ALL ISSUED ADDENDA, AND COMMONLY ACCEPTED CONSTRUCTION STANDARDS. THE CITY SPECIFICATIONS SHALL GOVERN WHERE OTHER SPECIFICATIONS DO NOT EXIST. IN CASE OF CONFLICTING SPECIFICATIONS OR DETAILS. THE MORE RESTRICTIVE SPECIFICATION/DETAIL SHALL BE FOLLOWED. 2. ALL PRIVATE ON-SITE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH THE PROJECT'S FINAL GEOTECHNICAL REPORT (OR LATEST EDITION), INCLUDING ALL ADDENDA.
- 3. ALL FIRELANE PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARDS AND DETAILS. IF THESE ARE DIFFERENT THAN THOSE IN THE GEOTECHNICAL REPORT. THEN THE MORE RESTRICTIVE SHALL BE FOLLOWED 4. ALL PUBLIC PAVING AND PAVING SUBGRADE SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND
- SPECIFICATIONS. 5. CONTRACTOR IS RESPONSIBLE FOR ALL PAVING AND PAVING SUBGRADE TESTING AND CERTIFICATION, UNLESS SPECIFIED OTHERWISE BY OWNER. ALL PAVING AND PAVING SUBGRADE TESTING SHALL BE COORDINATED WITH THE APPROPRIATE
- CITY INSPECTOR TESTING SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY FOR TESTING PAVING AND SUBGRADE. OWNER SHALL APPROVE THE AGENCY NOMINATED BY THE CONTRACTOR FOR PAVING AND PAVING SUBGRADE TESTING 6. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SHOW, BY THE STANDARD TESTING PROCEDURES OF THE PAVING AND
- PAVING SUBGRADE THAT THE WORK CONSTRUCTED MEETS THE PROJECT REQUIREMENTS AND CITY SPECIFICATIONS 7. DUE TO THE POTENTIAL FOR DIFFERENTIAL SOIL MOVEMENT ADJACENT TO THE BUILDING. THE CONTRACTOR SHALL ADHERE TO GEOTECHNICAL REPORT'S RECOMMENDATION FOR SUBGRADE PREPARATION SPECIFIC TO FLATWORK ADJACENT TO THE PROPOSED BUILDING. THE OWNER AND CONTRACTOR ARE ADVISED TO OBTAIN A GEOTECHNICAL ENGINEER
- RECOMMENDATION SPECIFIC TO FLATWORK ADJACENT TO THE BUILDING, IF NONE IS CURRENTLY EXISTING. 8. CURB RAMPS ALONG PUBLIC STREETS AND IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED BASED ON THE CITY STANDARD CONSTRUCTION DETAIL AND SPECIFICATIONS
- 9 PRIVATE CURB RAMPS ON THE SITE (LE. OUTSIDE PUBLIC STREET RIGHT-OF-WAY) SHALL CONFORM TO ADA AND TAS STANDARDS AND SHALL HAVE A DETECTABLE WARNING SURFACE THAT IS FULL WIDTH AND FULL DEPTH OF THE CURB RAMP, NOT INCLUDING FLARES.
- 10. ALL ACCESSIBLE RAMPS, CURB RAMPS, STRIPING, AND PAVEMENT MARKINGS SHALL CONFORM TO ADA AND TAS STANDARDS, I ATEST EDITION 11. ANY COMPONENTS OF THE PROJECT SUBJECT TO RESIDENTIAL USE SHALL ALSO CONFORM TO THE FAIR HOUSING ACT, AND
- COMPLY WITH THE FAIR HOUSING ACT DESIGN MANUAL BY THE US DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT. 12. CONTRACTOR SHALL CONSTRUCT PROPOSED PAVEMENT TO MATCH EXISTING PAVEMENT WITH A SMOOTH, FLUSH, CONNECTION.
- 13. CONTRACTOR SHALL FURNISH AND INSTALL ALL PAVEMENT MARKINGS FOR FIRE LANES, PARKING STALLS, HANDICAPPED PARKING SYMBOLS, AND MISCELLANEOUS STRIPING WITHIN PARKING LOT AND AROUND BUILDING AS SHOWN ON THE PLANS. ALL PAINT AND PAVEMENT MARKINGS SHALL ADHERE TO CITY AND OWNER STANDARDS. 14. REFER TO GEOTECHNICAL REPORT FOR PAVING JOINT LAYOUT PLAN REQUIREMENTS FOR PRIVATE PAVEMENT
- 15. REFER TO CITY STANDARD DETAILS AND SPECIFICATIONS FOR JOINT LAYOUT PLAN REQUIREMENTS FOR PUBLIC PAVEMENT. 16. ALL REINFORCING STEEL SHALL CONFORM TO THE GEOTECHNICAL REPORT, CITY STANDARDS, AND ASTM A-615, GRADE 60, AND SHALL BE SUPPORTED BY BAR CHAIRS. CONTRACTOR SHALL USE THE MORE STRINGENT OF THE CITY AND GEOTECHNICAL STANDARDS.
- 17. ALL JOINTS SHALL EXTEND THROUGH THE CURB.
- 18. THE MINIMUM LENGTH OF OFFSET JOINTS AT RADIUS POINTS SHALL BE 2 FEET. 19. CONTRACTOR SHALL SUBMIT A JOINTING PLAN TO THE ENGINEER AND OWNER PRIOR TO BEGINNING ANY OF THE PAVING WORK
- 20.ALL SAWCUTS SHALL BE FULL DEPTH FOR PAVEMENT REMOVAL AND CONNECTION TO EXISTING PAVEMENT. 21.FIRE LANES SHALL BE MARKED AND LABELED AS A FIRELANE PER CITY STANDARDS.
- 22.UNLESS THE PLANS SPECIFICALLY DICTATE TO THE CONTRARY, ON-SITE AND OTHER DIRECTIONAL SIGNS SHALL BE ORIENTED SO THEY ARE READILY VISIBLE TO THE ONCOMING TRAFFIC FOR WHICH THEY ARE INTENDED. 23.CONTRACTOR IS RESPONSIBLE FOR INSTALLING NECESSARY CONDUIT FOR LIGHTING, IRRIGATION, ETC. PRIOR TO
- PLACEMENT OF PAVEMENT. ALL CONSTRUCTION DOCUMENTS (CIVIL, MEP, LANDSCAPE, IRRIGATION, AND ARCHITECT) SHALL BE CONSULTED. 24.BEFORE PLACING PAVEMENT, CONTRACTOR SHALL VERIFY THAT SUITABLE ACCESSIBLE PEDESTRIAN ROUTES (PER ADA. TAS.
- AND FHA) EXIST TO AND FROM EVERY DOOR AND ALONG SIDEWALKS, ACCESSIBLE PARKING SPACES, ACCESS AISLES, AND ACCESSIBLE ROUTES. IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL. IN NO CASE SHALL SIDEWALK CROSS SLOPE EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPE EXCEED 5.0 PERCENT. ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL NOT EXCEED 2.0 PERCENT SLOPE IN ANY DIRECTION
- 25. CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ADA/TAS SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA AND TAS SLOPE COMPLIANCE ISSUES.

STORM DRAINAGE


- ALL STORM SEWER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS. 2. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE
- INSTALLATION OF THE STORM SEWER. 3. THE CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING
- STORM SEWER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY STORM SEWER, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED
- 4. THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF CURB INLETS AND GRATE INLETS AND ALL UTILITIES CROSSING THE STORM SEWER. 5. FLOW LINE. TOP-OF-CURB, RIM, THROAT, AND GRATE ELEVATIONS OF PROPOSED INLETS SHALL BE VERIFIED WITH THE
- GRADING PLAN AND FIELD CONDITIONS PRIOR TO THEIR INSTALLATION. 6. ALL PUBLIC STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS
- STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 7. ALL PRIVATE STORM SEWER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE
- PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. 8. ALL PVC TO RCP CONNECTIONS AND ALL STORM PIPE CONNECTIONS ENTERING STRUCTURES OR OTHER STORM PIPES SHALL HAVE A CONCRETE COLLAR AND BE GROUTED TO ASSURE THE CONNECTION IS WATERTIGHT
- 9. ALL PUBLIC STORM SEWER LINES SHALL BE MINIMUM CLASS III RCP. PRIVATE STORM SEWER LINES 18-INCHES AND GREATER SHALL BE CLASS III RCP OR OTHER APPROVED MATERIAL. 10. WHERE COVER EXCEEDS 20-FEET OR IS LESS THAN 2-FEET, CLASS IV RCP SHALL BE USED.

11.IF CONTRACTOR PROPOSES TO USE HDPE OR PVC IN LIEU OF RCP FOR PRIVATE STORM SEWER, CONTRACTOR SHALL SUBMIT


TECHNICAL DATA TO THE OWNER, ENGINEER AND CITY ENGINEER/INSPECTOR FOR APPROVAL PRIOR TO ORDERING THE MATERIAL. ANY PROPOSED HDPE AND PVC SHALL BE WATERTIGHT. 12. THE CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL STORM SEWER LINES. 13. EMBEDMENT FOR ALL STORM SEWER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS.	B
 14. ALL WYE CONNECTIONS AND PIPE BENDS ARE TO BE PREFABRICATED AND INSTALLED PER MANUFACTURERS SPECIFICATIONS. 15. USE 4 FOOT JOINTS WITH BEVELED ENDS IF RADIUS OF STORM SEWER IS LESS THAN 100 FEET. 16. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE 	DATE
FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN APPROVAL OF THE CITY. 17. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.	ល
 POND NOTES: ANY PONDS THAT ARE INTENDED TO HOLD WATER INDEFINITELY SHALL BE CONSTRUCTED WATERTIGHT. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR POND LINER SPECIFICATIONS. A GEOTECHNICAL ENGINEER SHALL REVIEW AND APPROVE ALL POND LINER MATERIAL, PLACEMENT PROCEDURES, AND 	KEVISION
 PROVIDE TESTING TO ENSURE THE POND LINER MATERIAL PLACED IS WATERTIGHT. 4. STORM SEWER PIPES AND HEADWALLS THAT CONNECT TO A POND INTENDED TO HOLD WATER INDEFINITELY SHALL BE INSTALLED WITH WATERTIGHT JOINTS TO AT LEAST 1-FOOT ABOVE THE NORMAL POOL WATER SURFACE ELEVATION. 5. ANY GRAVEL OR OTHER PERVIOUS EMBEDMENT AROUND PIPES OR OUTFALL STRUCTURES NEAR THE POND SHALL BE ELIMINATED FOR AT LEAST 20-FEET FROM THE POND SO NO ROUTE FOR WATER TO LEAK THROUGH THE EMBEDMENT 	
 MATERIAL IS PROVIDED. BACKFILL IN THESE AREAS SHALL BE OF IMPERVIOUS MATERIAL. 6. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE WATER LEVEL FOLLOWING COMPLETION AND FILLING OF THE POND SHALL BE MONITORED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO OBSERVE WATER INFLOW, OUTFLOW, AND CALCULATE EVAPORATION TO VERIFY THAT THE POND IS WATERTIGHT. 7. FOR ANY PONDS INTENDED TO HOLD WATER INDEFINITELY: THE POND WATER LEVEL SHALL ALSO BE MAINTAINED BY THE CONTRACTOR FOR AT LEAST 60 DAYS TO USE SHALL ALSO BE MAINTAINED BY THE CONTRACTOR FOR AND FILL TO USE DESIGN WATER INFORMATION OF CONSTRUCTION SO THAT IT DEMANDS FILL TO USE DESIGN WATER INFORMATION OF CONSTRUCTION SO THAT IT DEMANDS FILL TO USE DESIGN WATER INFORMATION OF CONSTRUCTION SO THAT IT DEMANDS FILL TO USE DESIGN WATER INFORMATION OF CONSTRUCTION SO THAT IT DEMANDS FILL TO USE DESIGN WATER INFORMATION OF CONSTRUCTION FOR AND FILL TO USE DESIGN WATER INFORMATION FILLS IN THE POND IS NOT. 	o Z
CONTRACTOR FOR THE DURATION OF CONSTRUCTION SO THAT IT REMAINS FULL TO ITS DESIGN WATER LEVEL, AND IS NOT LOWERED, AS THIS MAY DRY-OUT THE POND LINER AND RISK ITS WATERTIGHT PROPERTIES. WATER AND WASTEWATER:	
 ALL WATER AND WASTEWATER MATERIALS AND CONSTRUCTION SHALL COMPLY WITH CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL FIELD VERIFY THE SIZE, CONDITION, HORIZONTAL, AND VERTICAL LOCATIONS OF ALL EXISTING WATER AND WASTEWATER FACILITIES THAT ARE TO BE CONNECTED TO, PRIOR TO START OF CONSTRUCTION OF ANY WATER OR WASTEWATER CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER OF ANY CONFLICTS DISCOVERED. CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS SHOWN, INCLUDING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITY SERVICES ENTERING THE BUILDING. TURE CONTRACTOR SHALL VERIFY INFORMATION OF ANY WATER OF ANY CONSTRUCTION OF ALL UTILITY SERVICES ENTERING THE BUILDING. 	DING 3, SUITE 1 512-418-1791 5200 S5 5200 S5 520 S5 512-418-1791 S5 528 S5 512-418-1791 S5 52 S5 52 S5 S5 S5 S5 S5 S5 S5 S5 S5 S5 S5 S5 S5
 THE CONTRACTOR SHALL FIELD VERIFY THE ELEVATION OF ALL UTILITY CROSSINGS PRIOR TO THE INSTALLATION OF ANY PIPE. THE SITE UTILITY CONTRACTOR SHALL PROVIDE ALL MATERIALS AND APPURTENANCES NECESSARY FOR COMPLETE INSTALLATION OF THE WATER AND WASTEWATER IMPROVEMENTS. 	K 78735 FAX: 5 FAX: 5 FAX: 5 FAX: 5 No. 928
 ALL PUBLIC WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO CITY PUBLIC WORKS STANDARD DETAILS AND SPECIFICATIONS. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. ALL PRIVATE WATER AND WASTEWATER CONSTRUCTION, PIPE, STRUCTURES, AND FITTINGS SHALL ADHERE TO THE APPLICABLE PLUMBING CODE. CONTRACTOR SHALL ARRANGE FOR REQUIRED CITY INSPECTIONS. FIRE SPRINKLER LINES SHALL BE DESIGNED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR, AND COMPLY TO THE APPLICABLE CODES AND INSPECTIONS REQUIRED. THESE PLANS WERE PREPARED WITHOUT THE BENEFIT OF THE FIRE 	ST PARKWAY AUSTIN, TX AUSTIN, TX AUSTIN, TX AUSTIN, TX AUSTIN, TX AUSTIN, TX MWW.KIMLEY- MLEY-HORN, TBPE Firm
 SPRINKLER DESIGN. CONTRACTOR SHALL NOTIFY THE ENGINEER IF ANY DISCREPANCIES. 9. EMBEDMENT FOR ALL WATER AND WASTEWATER LINES, PUBLIC OR PRIVATE, SHALL BE PER CITY STANDARD DETAILS. 10. CONTRACTOR SHALL TAKE REQUIRED SANITARY PRECAUTIONS, FOLLOWING ANY CITY, TCEQ, AND AWWA STANDARDS, TO KEEP WATER PIPE AND FITTINGS CLEAN AND CAPPED AT TIMES WHEN INSTALLATION IS NOT IN PROGRESS. 11. CONTRACTOR SHALL PROVIDE CONSTRUCTION SURVEYING FOR ALL WATER AND WASTEWATER LINES. 12. ALL WATER AND WASTEWATER SERVICES SHALL TERMINATE 5-FEET OUTSIDE THE BUILDING, UNLESS NOTED OTHERWISE. 13. CONTRACTOR SHALL COMPLY WITH CITY REQUIREMENTS FOR WATER AND WASTEWATER SERVICE DISRUPTIONS AND THE AMOUNT OF PRIOR NOTICE THAT IS REQUIRED, AND SHALL COORDINATE DIRECTLY WITH THE APPROPRIATE CITY 	301 SOUTHWE PHONE: 51; © 2025 KIN
DEPARTMENT. 14. CONTRACTOR SHALL SEQUENCE WATER AND WASTEWATER CONSTRUCTION TO AVOID INTERRUPTION OF SERVICE TO SURROUNDING PROPERTIES. 15. CONTRACTOR SHALL MAINTAIN WATER SERVICE AND WASTEWATER SERVICE TO ALL CUSTOMERS THROUGHOUT	
CONSTRUCTION (IF NECESSARY, BY USE OF TEMPORARY METHODS APPROVED BY THE CITY AND OWNER). THIS WORK SHALL BE CONSIDERED SUBSIDIARY TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 16. THE CONTRACTOR IS RESPONSIBLE TO PROTECT ALL WATER AND WASTEWATER LINES CROSSING THE PROJECT. THE CONTRACTOR SHALL REPAIR ALL DAMAGED LINES IMMEDIATELY. ALL REPAIRS OF EXISTING WATER MAINS, WATER SERVICES, SEWER MAINS, AND SANITARY SEWER SERVICES ARE SUBSIDIARY TO THE WORK, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.	5, ATE OF TEHAS
 17. VALVE ADJUSTMENTS SHALL BE CONSTRUCTED SUCH THAT THE COVERS ARE AT FINISHED SURFACE GRADE OF THE PROPOSED PAVEMENT. 18. THE ENDS OF ALL EXISTING WATER MAINS THAT ARE CUT, BUT NOT REMOVED, SHALL BE PLUGGED AND ABANDONED IN PLACE. THIS WORK SHALL BE CONSIDERED AS A SUBSIDIARY COST TO THE PROJECT AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED. 19. ALL FIRE HYDRANTS, VALVES, TEES, BENDS, WYES, REDUCERS, FITTINGS, AND ENDS SHALL BE MECHANICALLY RESTRAINED 	THOMAS J. LOMBARDI JR. 131071
AND/OR THRUST BLOCKED TO CITY STANDARDS. 20.CONTRACTOR SHALL INSTALL A FULL SEGMENT OF WATER OR WASTEWATER PIPE CENTERED AT ALL UTILITY CROSSINGS SO THAT THE JOINTS ARE GREATER THAN 9-FEET FROM THE CROSSING. 21.ALL CROSSINGS AND LOCATIONS WHERE WASTEWATER IS LESS THAN 9-FEET FROM WATER, WASTEWATER CONSTRUCTION	Homas formand the
AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 217.53. 22.ALL CROSSING AND LOCATIONS WHERE WATER IS LESS THAN 9-FEET FROM WASTEWATER, WATER CONSTRUCTION AND MATERIALS SHALL COMPLY WITH TCEQ CHAPTER 290.44. 23.ALL WATER AND WASTEWATER SHALL BE TESTED IN ACCORDANCE WITH THE CITY, AWWA, AND TCEQ STANDARDS AND SPECIFICATIONS. AT A MINIMUM. THIS SHALL CONSIST OF THE FOLLOWING:	ROJECT 111800 ATE 2025 SHOWN SY: IC : IC SY: TLJ
 a. ALL WATERLINES SHALL BE HYDROSTATICALLY TESTED AND CHLORINATED BEFORE BEING PLACED INTO SERVICE. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. b. WASTEWATER LINES AND MANHOLES SHALL BE PRESSURE TESTED. CONTRACTOR SHALL COORDINATE WITH THE CITY FOR 	KHA PRO 0650118 DATE MAY 20 SCALE: AS SCALE: AS DESIGNED BY: DRAWN BY: CHECKED BY:
 THEIR REQUIRED PROCEDURES AND SHALL ALSO COMPLY WITH TCEQ REGULATIONS. AFTER COMPLETION OF THESE TESTS, A TELEVISION INSPECTION SHALL BE PERFORMED AND PROVIDED TO THE CITY AND OWNER ON A DVD. 24.CONTRACTOR SHALL INSTALL DETECTABLE WIRING OR MARKING TAPE A MINIMUM OF 12" ABOVE WATER AND WASTEWATER LINES. MARKER DECALS SHALL BE LABELED "CAUTION - WATER LINE", OR "CAUTION - SEWER LINE". DETECTABLE WIRING AND MARKING TAPE SHALL COMPLY WITH CITY STANDARDS, AND SHALL BE INCLUDED IN THE COST OF THE WATER AND WASTEWATER PIPE. 	
 25.DUCTILE IRON PIPE SHALL BE PROTECTED FROM CORROSION BY A LOW-DENSITY POLYETHYLENE LINER WRAP THAT IS AT LEAST A SINGLE LAYER OF 8-MIL. ALL DUCTILE IRON JOINTS SHALL BE BONDED. 26.WATERLINES SHALL BE INSTALLED AT NO LESS THAN THE MINIMUM COVER REQUIRED BY THE CITY. 27.CONTRACTOR SHALL PROVIDE CLEAN-OUTS FOR PRIVATE SANITARY SEWER LINES AT ALL CHANGES IN DIRECTION AND 100-FOOT INTERVALS, OR AS REQUIRED BY THE APPLICABLE PLUMBING CODE. CLEAN-OUTS REQUIRED IN PAVEMENT OR 	L S L S
SIDEWALKS SHALL HAVE CAST IRON COVERS FLUSH WITH FINISHED GRADE. 28.CONTRACTOR SHALL PROVIDE BACKWATER VALVES FOR PLUMBING FIXTURES AS REQUIRED BY THE APPLICABLE PLUMBING CODE (E.G. FLOOR ELEVATION OF FIXTURE UNIT IS BELOW THE ELEVATION OF THE MANHOLE COVER OF THE NEXT UPSTREAM MANHOLE IN THE PUBLIC SEWER). CONTRACTOR SHALL REVIEW BOTH MEP AND CIVIL PLANS TO CONFIRM WHERE THESE ARE	NOT NOT
REQUIRED. 29. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND SUBMITTING A TRENCH SAFETY PLAN, PREPARED BY A PROFESSIONAL ENGINEER IN THE STATE OF TEXAS, TO THE CITY PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TRENCH SAFETY REQUIREMENTS IN ACCORDANCE WITH CITY, STATE, AND FEDERAL REQUIREMENTS, INCLUDING OSHA FOR ALL TRENCHES. NO OPEN TRENCHES SHALL BE ALLOWED OVERNIGHT WITHOUT PRIOR WRITTEN	AL F
APPROVAL OF THE CITY. 30. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM WATER.	MLE
THESE PLAN AND GENERAL NOTES REFER TO: <u>GEOTECHNICAL ENGINEERING REPORT</u> (FIRM)	RIM GENE
(DATE) INCLUDING ALL REVISIONS AND ADDENDA TO THIS REPORT THAT MAY HAVE BEEN RELEASED AFTER THE NOTED DATE.	
	PARK PARK TE) TE)
	S CRI IERCIAI EDAR PARK COUNTY, TE
	U N N N N N N N N N N N N N N N N N N N
	R S C ζ
	SHEET NUMBER 4 OF 44
© COPYRIGHT 2022 KIMLEY-HORN AND ASSOCIATES, INC., ALL RIGHTS RESERVED	2024-42-SD







	DATE BY
Three proved of last 100, frame, 10	L 100 No. REVISIONS
bit bit<	Kimpey » Hond S301 SOUTHWEST PARKWAY, BUILDING 3, SUITE 100 AUSTIN, TX 78735 PHONE: 512–646–2237 FAX: 512–418–1791 WWW.KIMLEY-HORN.COM © 2025 KIMLEY-HORN.COM TBPE Firm No. 928
<text><text><text><text></text></text></text></text>	KHA PROJECT NAF OL DATE DATE DATE DATE DATE DATE MAY 2025 MAY 2025
	SURVEY SHEET
ALE SHOWN WHEN EETS PLOTTED AT JAGES SCALED TO AT 40%.	CYPRESS CREEK COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS
	SHEET NUMBER 5 OF 44 2024-42-SD




DEMOLITION NOTES

- CONTRACTOR SHALL SECURE ALL PERMITS REQUIRED FOR 1 DEMOLITION AND SHALL NOTIFY ALL RESPECTIVE GOVERNMENTAL AND UTILITY AGENCIES AFFECTED BY DEMOLITION PRIOR TO STARTING DEMOLITION. 2. ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REGULATIONS OF THE U.S. OCCUPATIONAL HEALTH AND SAFETY ADMINISTRATION. COPIES OF OSHA STANDARDS MAY BE PURCHASED FROM THE U.S. GOVERNMENT PRINTING OFFICE. INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 903 SAN JACINTO, RM 319, AUSTIN, TX. 78701, TEL (512) 916-5783.
- 3. PRIOR TO DEMOLITION, PROPER PHASING OF EROSION CONTROL DEVICES AND TREE PROTECTION ARE TO BE INSTALLED.
- 4. SHOULD REMOVAL AND/OR RELOCATION ACTIVITIES DAMAGE FENCING. LIGHTING. STORM INLET STRUCTURES OR ANY OTHER APPURTENANCE, THEN THE CONTRACTOR SHALL PROVIDE NEW MATERIALS/STRUCTURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. ALL DEMOLITION AND CONSTRUCTION DEBRIS SHALL BE
- REMOVED FROM THE SITE IN ACCORDANCE WITH ALL APPLICABLE RULES AND REGULATIONS. ALL BARRICADES AND WARNING SIGNS SHALL CONFORM TO
- THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND ARE GENERALLY LOCATED TO AFFORD MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND EQUIPMENT AND TO ASSURE AN EXPEDITIOUS TRAFFIC FLOW AT ALL TIMES. DURING THE PROGRESS OF WORK, THE CONTRACTOR SHALL PROVIDE ACCESS FOR LOCAL TRAFFIC. CONTRACTOR MAY LIMIT SAW CUT & PAVEMENT REMOVAL TO ONLY THOSE AREAS WHERE IT IS REQUIRED AS SHOWN ON THE CONSTRUCTION PLANS. BUT IF ANY DAMAGE IS INCURRED ON ANY OF THE SURROUNDINGS PAVEMENT, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS REMOVAL,
- REPLACEMENT, AND/OR REPAIR. ALL PAVING AND CURB TO BE REMOVED ARE TO BE REMOVED USING FULL-DEPTH SAWCUT 2' OFF EXISTING EDGE OF PAVEMENT. 9. ANY ADDITIONAL CONCRETE PAVING, FOOTINGS OR
- STRUCTURES NOT IDENTIFIED ON THIS PLAN SHALL BE LOCATED BY CONTRACTOR AND SUBMITTED TO ENGINEER FOR APPROVAL
- 10. CONTRACTOR SHALL EXERCISE EXTREME CAUTION AS SITE MAY CONTAIN PRIVATE AND/OR PUBLIC UTILITIES. CONTRACTOR SHALL CALL 811 AT LEAST 72 HOURS PRIOR TO COMMENCING DEMOLITION OR CONSTRUCTION ACTIVITIES. CONTRACTOR SHALL CONTACT ANY OTHER UTILITY COMPANIES WHO DO NOT SUBSCRIBE TO THE DIG TESS PROGRAM FOR LINE MARKINGS. THE CONTRACTOR BEARS SOLE RESPONSIBILITY FOR VERIFYING LOCATIONS OF EXISTING UTILITIES, SHOWN OR NOT SHOWN, AND FOR REPAIRING ANY DAMAGE DONE TO THESE FACILITIES. 11. ELECTRICAL, TELEPHONE, CABLE, WATER, FIBER OPTIC CABLE, AND GAS LINES REQUIRED TO BE REMOVED OR RELOCATED SHALL BE COORDINATED WITH THE AFFECTED UTILITY COMPANY. ADEQUATE TIME SHALL BE PROVIDED FOR
- 12. RELOCATION AND CLOSE COORDINATION WITH THE UTILITY COMPANY IS NECESSARY TO PROVIDE A SMOOTH TRANSITION IN UTILITY SERVICE. CONTRACTOR SHALL PAY CLOSE







ARE THE RESPONSIBILITY OF THE CONTRACTOR.. INSTALL TREE PROTECTION TO THE GREATEST EXTENTS 16 POSSIBLE PRIOR TO DEMOLITION ACTIVITIES. DEMOLITION WITHIN THE HALF CRITICAL ROOT ZONE SHALL BE PERFORMED BY HAND. TREE PROTECTION SHALL BE EXPANDED TO MATCH EROSION CONTROL PLAN AS SOON AS DEMOLITION ACTIVITIES HAVE BEEN COMPLETED. REFER TO THE TREE REMOVAL AND TREE PRESERVATION 17

KIMLEY-HORN AND ASSOCIATES. INC. IS NOT RESPONSIBLE

FOR THE MEANS AND METHODS EMPLOYED BY THE

CONTRACTOR TO IMPLEMENT THIS DEMOLITION PLAN. THIS

DEMOLITION PLAN SIMPLY INDICATES THE KNOWN OBJECTS

ON THE SUBJECT TRACTS THAT ARE TO BE DEMOLISHED AND

REMOVED FROM THE SITE. KIMLEY-HORN AND ASSOCIATES,

INC. DOES NOT WARRANT OR REPRESENT THAT THE PLAN,

WHICH WAS PREPARED BASED ON SURVEY AND UTILITY

INFORMATION PROVIDED BY OTHERS, SHOWS ALL

IMPROVEMENTS AND UTILITIES, AND THAT THE

IMPROVEMENTS AND UTILITIES ARE SHOWN ACCURATELY. THE

CONTRACTOR IS RESPONSIBLE FOR PERFORMING HIS OWN

SITE RECONNAISSANCE TO SCOPE HIS WORK AND TO

CONFIRM WITH THE OWNERS OF EXISTING IMPROVEMENTS

OF PROPOSED DEMOLITION. THE GOAL OF DEMOLITION IS TO

LEAVE THE SITE IN A STATE SUITABLE FOR THE

RELOCATION, OR PRESERVATION OF EXISTING

IMPROVEMENTS, UTILITIES, ETC. TO ACCOMPLISH THIS GOAL

CONSTRUCTION OF FUTURE DEVELOPMENT, REMOVAL,

AND UTILITIES THE ABILITY AND PROCESS FOR THE REMOVAL

PLAN FOR COMPLETE TREE LIST. CONTRACTOR TO PROVIDE AN ADA COMPLIANT TEMPORARY SIDEWALK PATH USING COMPACTED BASE OR 1" OF COLD MIX ASPHALT PRIOR TO THE DEMOLITION OF THE EXISTING WEST PARK STREET SIDEWALK

NOTES:

IN SERVICE.

- PROPERTY LINES SHOWN PER PROPOSED PLAT, WHICH IS 1 CONCURRENTLY UNDER REVIEW WITH THE CITY OF CEDAR PARK
- ALL ABOVE GROUND IMPROVEMENTS SHOW PER SURVEY PROVIDED BY 4WARD LAND SURVEYING, DATED 02/04/2024. REF. SHEET 5
- ALL UNDERGROUND UTILITIES SHOULD BE LOCATED PRIOR TO CONSTRUCTION.

()



ITIONS

AN

EMO PI

EXISTING AND DI

Ш

2024-42-SD


	TREE DA			TREE DA	
NO.	SPECIES	DIAMETER (INCHES)	NO.	SPECIES	DIAMETER (INCHES)
1	Live Oak	18	1	Live Oak	18
3	Oak Oak	<u>12</u> 8	951	<u>Live Oak</u>	11
6 9	Live Oak	15	952 953	<u> </u>	13
9 11		10	953	<u> </u>	25
11		8	955	<u> </u>	13
12	<u> </u>	8	956	<u> </u>	13
13	Oak	24	957		8
17	Oak	8	958	— Live Oak —	11
18	Oak	9	959	<u> </u>	9
19		10	960		12
20	<u> </u>	12	961	<u> </u>	18
21	Live Oak	10	962	<u> </u>	18
22	Live Oak	13	963	<u> </u>	17
24 25	Live Oak	13	964	Live Oak	23
25	<u> </u>	12 10	965 966	Live Oak Live Oak	29 24
20	<u> </u>	10	960	Live Oak	13
28	Oak	11	968	Live Oak	12
29	Live Oak	15	969		10
30	<u>Live Oak</u>	13	970	Live Oak	14
31	Oak	8	971	Live Oak	12
32	Pecan	10	972	Live Oak	14
33	Pecan	10	973	Live Oak	12
34	Live Oak	11	974	Live Oak	21
557	<u> </u>	7	975	Live Oak	22
558	Live Oak	6	976	Live Oak	12
559	Oak Oak	6	977	<u> </u>	8
560 561	<u> </u>	5	978 979	<u> </u>	<u>15</u> 11
562	<u>Live Oak</u>	6	979	<u> </u>	11
563	Oak	6	981	<u>Live Oak</u>	16
564	<u> </u>	5	982	Live Oak	16
565	——Live Oak——	6	983	— Live Oak —	11
566	——Live Oak——	7	984	<u> </u>	13
567	Oak	7	985	<u> </u>	10
568	Oak	7	986	<u> </u>	12
569	Oak	7	987	<u>Live Oak</u>	12
570 571	<u> </u>	7 6	988 989	— Live Oak — Data Market	14
572	<u> </u>	6	989	Live Oak	9
573	<u> </u>	6	991	Live Oak	10
574		10	992	Live Oak	13
575	- American Elm	6	993	Oak	16
576	- American Elm	6	994	— Live Oak	13
577		7	995	Live Oak	13
578	<u>—American Elm</u>	6	996	<u> </u>	9
579	<u>American Elm</u>	7	997	Live Oak	12
580	<u>American Elm</u>	6	998		11
581 582	Cedar Elm Oak	6 7	999 1000	<u> </u>	20 14
<u>582</u> 583	Oak	6	1000	recail	14
584	<u> </u>	6	1		
585	<u>Live Oak</u>	7	1		
586	<u> </u>	7	1		
587		7	1		
588		12]		
934	Oak	16	1		
936	Sycamore	14	4		
939	Oak Oak	12	4		
940	Oak Oak	13	4		
941 943	<u> </u>	12	4		
943	Live Oak Live Oak	14	-		
944 945	Live Oak	9	4		
946	Live Oak	8	1		
	Live Oak	8	1		
947					
947 948	Live Oak	9			
	Live Oak Live Oak Live Oak	9 8 9	-		






what's below. all before you dig.	
ARNING: CONTRACTOR IS TO CRIFY PRESENCE AND EXACT CATION OF ALL UTILITIES RIOR TO CONSTRUCTION.	

					DATE BY
					REVISIONS
					No.
		5301 SOUTHWEST PARKWAY, BUILDING 3, SUITE 100	AUSTIN, TX 78735 PHONE: 512-646-2237 FAX: 512-418-1791		TBPE Firm No. 928
KHA PROJECT 065011800	DATE MAY 2025	SCALE: AS SHOWN	DESIGNED BY: IC	DRAWN BY: IC	СНЕСКЕД ВҮ: ТLJ
		TREE LIST			
CYPRESS CREEK COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS					
7		DF			
202	24-4	42	-5	SD)





SITE DATA TABLE			
ZONING	GENERAL BUSINES		
ADDRESS	703/705 CYPRESS CREEK CED/ 78613		
LEGAL DESCRIPTION	EMERSON COMM #2 RESUB ACRES 3.85 S3325-BUTTERCUP CREEK I RESUB LOT 2, LOT 1 ACRE		
FIRE DESIGN CODES	2021 INTERNATIONAL FIRE C CHAPTER 5 AND APPENDIX D, 7 CEDAR PARK CODE OF ORD SECTION 5.01.001		
CONSTRUCTION CLASSIFICATION	TYPE II		
BUILDING FIRE AREA (SF)	44,945 SF		
FIRE FLOW DEMAND @ 20 PSI (GPM)	3000 GPM		
REDUCED (75%) FIRE FLOW DEMAND @ 20 PSI FOR HAVING A SPRINKLER SYSTEM (GPM)	750 GPM		
MINIMUM FIRE FLOW DEMAND	750 GPM		
FIRE HYDRANT FLOW TEST DATE	9/4/2024		
HIGH-RISE	NO		





REQUIRED			
TOTAL BUILDING SQUARE FOOTAGE 44,945 SF			
TOTAL REQUIRED PARKING RETAIL - 1 SPOT FOR 250 SF	180 SPACES		
PRO	OPOSED		
STANDARD PARKING	217 SPACES		
COMPACT PARKING	5 SPACES		
ADA PROVIDED	7 SPACES		
TOTAL PARKING	229 SPACES		
ВІКЕ	20 SPACES		


BUILDING-2 ONE-STORY SHELL GSF = 9,000 SF BUILDING HEIGHT = 35' FFE = 922 N12°38'32"W 86.73' BUILDING-3 ONE-STORY SHELL GSF = 8,875 SF WASTEWATER LOT 2, RESUBDIVISION BUILDING HEIGHT = 35' OF BUTTERCUP CREEK FFE = 922.5' INDUSTRIAL PARK, LOT 2 <u>,</u> Gr CAB. I, SL. 118 – 119, P. R. W. C. T. PROPOSED -JUNCTION BOX _ PROPOSED h wastewater -- PROPOSED CLEANOUT PROPOSED DUMPSTER ENCLOSURE WASTEWATER MANHOLE FRR S65°31'14"E 41.81 ¥////////// #207 PROPOSED · N24°58'37"E FIRE HYDRANT 30.30' - 10' PUBLIC UTILITY EASEMENT CAB. I, SL. 118 P.R.W.C.T. - PROPOSED STORM INLET BUILDING-4 ONE-STORY SHELL GSF = 8,875 SF BUILDING HEIGHT = 35' FFE = 925.5' ן יק ^ו - PROPOSED STORM INLET ~ Gr EXISTING FIRE HYDRANT TO BE RELOCATED S57°47'16"E 30.12' Þ٩ - 10' PUBLIC UTILITY & ELECTRIC -- 25' BUILDING LINE SETBACK EASEMENT - 5' R.O.W. DEDICATION _ CAB. I, SL. 118 P.R.W.C.T. CAB. I, SL. 118 P.R.W.C.T. CYPRESS CREEK ROAD (CO. RD. NO. 182) - CONNECT TO PUBLIC SIDEWALK FOR INTERNAL CIRCULATION ROUTE


- 10' PUBLIC UTILITY EASEMENT


CAB. I, SL. 118-119, P.R.W.C.T.































or	care	raciiitie	es where	e animai







NOTES:

EQUIVALENT SINGLE AXEL LOADS (ESALS).













Know what's below. Call before you dig. WARNING: CONTRACTOR IS TO VERIFY PRESENCE AND EXACT LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.




			DATE BY
	0 G	40' 80' RAPHIC SCALE 40'	REVISIONS
		PROPERTY LINE PROPOSED FINISHED FLOOR ELEVATION PROPOSED TOP GRADE / TOP OF PAVEMENT ELEVATION MATCH EXISTING ELEVATION	ODD SUITE 100 B-1791 ES, INC. No.
	• TG XXX.XX • TW XXX.XX • BW XXX.XX • EW XXX.XX • EW XXX.XX	PROPOSED TOP OF GRATE PROPOSED GRADE AT TOP OF WALL PROPOSED GRADE AT BOTTOM OF WALL PROPOSED GRADE AT END OF WALL PROPOSED RETAINING WALL PROPOSED CONTOUR EXISTING CONTOUR	CALLEY-HORN AND AND AND AND AND AND AND AND AND AN
NOTES:	\bigcirc	EXISTING TREE TO REMAIN ADA ROUTE	5301 SOUTHWES PHONE: 512- WM
2. A 3. A 4. C A M A 5. M	LL BOTTOM OF WALL ELEVAT ONTRACTOR TO VERIFY A.D., CCESSIBLE ROUTES, INCLUD PPLICABLE A.D.A. STANDARD ORE THAN 2.0% CROSS SLOF CCESSIBLE PARKING AREAS. AINTAIN EXISTING GRADE IN RAINAGE TO AREA INLETS.	S ARE TO TOP OF GRADE AT WALL. TIONS ARE TO BOTTOM OF GRADES IN ALL SIDEWALK A. COMPLIANCE FOR GRADES IN ALL SIDEWALK VING DRIVEWAY CROSSINGS, SHALL CONFORM TO SS: NOT EXCEED 5.0% ALONG TRAVEL PATH WITH PE AND NOT EXCEED 2.0% IN ANY DIRECTION IN TREE WELLS. CONTRACTOR TO ENSURE POSITIV E DESIGNED AND PERMITTED BY OTHERS.	
			OVERALL GRADING PLAN
Inow what's b Call befor WARNING: CONT VERIFY PRESEN LOCATION OF PRIOR TO CONS	TRACTOR IS TO CE AND EXACT ALL UTILITIES		CYPRESS CREEK COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS
			SHEET NUMBER 17 OF 44
			2024-42-SD







	EXISTING DRAINAGE AREA CALCULATIONS											
RD. N	DRAINAGE AREA	AREA (ac.)	AREA (SQ M)	IMPERVIOUS COVER (ac.)	IMPERVIOUS COVER (%)	CN-VALUE (IMPERVIOUS)	PERVIOUS COVER (%)	CN-VALUE (PERVIOUS)	CN (COMPOSITE)	TC (MIN)	LAG (MIN)	Q ₂ (CFS)
	EX-1	5.82	0.00909	0.07	1.2%	98	99%	80	80.2	12.23	7.34	14.9
	OS-1	0.46	0.00072	0.37	80.0%	98	20%	80	94.4	5.11	3.07	1.9




<u>NOTES</u>:


- 1. EXISTING CONDITIONS ASSUMED TO BE PREDEVELOPED CONDITIONS OF DRAINAGE AREAS EX-1 AND OS-1. USING ATLAS 14 RAINFALL DATA FOR
- CEDAR PARK.
 THE FLOW OFF THE SITE HAS NOT BEEN INCREASED FROM THE EXISTING CONDITION.


INTRATION								
OW CONCENTR	RATED FLOW	CH						
S (FT/FT)	L (FT)	T2 (MIN)	V (FT/S)	L (FT)	T4 (MIN)	TOTAL TC (MIN)		
0.029	527.0	3.22	5.00	0.00	0.00	12.23		
0.029	570.0	3.47	5.00	0.00	0.00	5.11		

Unpaved $T_t = \frac{L}{(60(16.1345)(s^{0.5}))}$ Paved $T_t = \frac{L}{(60(20.3282)(s^{0.5}))}$



S)	0 (CES)	0 (058)	Q ₁₀₀ (CFS)
3)	Q ₁₀ (CF3)	Q ₂₅ (CF3)	Q ₁₀₀ (CF3)
	28.3	37.8	54.3
	3.0	3.7	5.0






								.
		[LEO	GEND]	B
			X-1 9.9 ac 5.5 cfs [A-1]		AREA DESIGNA AREA IN ACRES Q100 FLOW IN (NLET NUMBER	S CFS		DATE
				F	PROPERTY LIN PROPOSED STO EXISTING STOF PROPOSED DR PROPOSED STO PROPOSED STO	e DRM DRAIN LIN M DRAIN LINE AINAGE DIVIDE DRM DRAIN INI DRM DRAIN MA	E LET NHOLE	REVISIONS
		-	555 —	F	PROPOSED STO PROPOSED FLO PROPOSED CO	OW DIRECTION		ġ Ż
		_	— — — 555 —	E	EXISTING CONT	TOUR		ODD SUITE 100 -1791 S, INC.
	<u>NC</u> 1.	<u>DTES:</u> THE FLOW (CONDITION.	،	40' PHIC SCALE 4 HAS NOT BEE		FROM THE EX	XISTING	HWEST PARKWAY, BUILDING 3, S AUSTIN, TX 78735 512–646–2237 FAX: 512–418 WWW.KIMLEY–HORN.COM KIMLEY–HORN AND ASSOCIATE TBPE Firm No. 928
ION								301 SOUTH PHONE: © 2025
FT)	L (FT) 368.0		I) V (FT/S)	L (FT)	T4 (MIN)	TOTAL TO 5.00 9.84)	
ed T	$T_t = L_{j}$	0.00	282)(<i>s</i> ^{0.5})))		5.00		KHA PROJECT 065011800 DATE MAY 2025 MAY 2025 Scale: AS SHOWN Designed BY: IC DRAWN BY: IC DRAWN BY: TLJ
(COM	CN POSITE) 94.0	TC (MIN) 5.00	LAG (MIN) 3.00	Q ₂ (CFS) 25.5	Q ₁₀ (CFS) 39.8	Q ₂₅ (CFS) 49.7	Q ₁₀₀ (CFS) 66.9	PROPOSED DRAINAGE AREA MAP
	31.8 94.5	9.84 5.00	5.91 3.00	2.1 2.3	3.8 3.6	5.0 4.5	7.1 6.0	

PRESS CREI COMMERCIAL CITY OF CEDAR PARK LIAMSON COUNTY, TEXA \succ \mathbf{O} SHEET NUMBER 210F 44 2024-42-SD

 $O \odot =$


 \geq



		NOP			DATE BY
		0 40 GRAPHIC	0' 80' SCALE 40'		REVISIONS
		w PRC y EXIS y EXIS	END PERTY LINE POSED WASTEWATER POSED WASTEWATER POSED WASTEWATER POSED FIRE HYDRAN POSED STORM DRAIN POSED STORM DRAIN POSED STORM DRAIN POSED STORM DRAIN STING OVERHEAD POW STING WASTEWATER L STING WASTEWATER L STING FIRE HYDRANT STING WASTEWATER N STING WASTEWATER N	R MANHOLE T I LINE I INLET TION VER LINE LINE	Image: State of the state
CROSSING TYPE OF HIGHER NUMBER PIPE	UTILITY CROS	SING TABLE TYPE OF LOWER PIPE	CROWN ELEVATION	VERTICAL SEPARATION (FT)	KHA PROJECT 065011800 DATE MAY 2025 Scale: AS SHOWN DESIGNED BY: IC DRAWN BY: IC CHECKED BY: TLJ
1WASTEWATER2WASTEWATER3WASTEWATER4WASTEWATER5WASTEWATER6STORM7WASTEWATER8WASTEWATER9WASTEWATER10WASTEWATER	917.93 917.93 917.78 917.37 917.37 917.37 919.06 918.46 918.46 918.46 917.77 917.77	WATER WATER STORM WATER WATER WATER WATER WATER WATER WATER	915.52 915.69 916.80 915.69 915.86 917.71 915.69 915.52 915.52 915.69	2.41 2.24 0.97 1.69 1.51 1.35 2.77 2.94 2.25 2.08	OVERALL STORM PLAN
Know what's be Call befor WARNING: CONTR VERIFY PRESENCI- LOCATION OF A	e you dig.				CYPRESS CREEK COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS
					SHEET NUMBER 22 OF 44 2024-42-SD










LEGEND

PROPERTY LINE
WASTEWATER LINE
WATER LINE
WASTEWATER MANHOLE
FIRE HYDRANT
STORM DRAIN LINE
STORM DRAIN INLET
EXISTING OVERHEAD POWER LINE
EXISTING WATER LINE
EXISTING WASTEWATER LINE
EXISTING STORM SEWER LINE
EXISTING POWER POLE
EXISTING FIRE HYDRANT
EXISTING WATER VALVE
EXISTING WASTEWATER MANHOLE




$\frac{1}{6}$	No. REVISIONS DATE BY
	Kimbey Horn And Solates, INC. S301 SOUTHWEST PARKWAY, BUILDING 3, SUITE 100 AUSTIN, TX 78735 PHONE: 512–646–2237 FAX: 512–418–1791 WWW.KIMLEY-HORN.COM © 2025 KIMLEY-HORN.COM CO25 KIMLEY-HORN.AND ASSOCIATES, INC. TBPE Firm No. 928
	KHA PROJECT KHA PROJECT 065011800 DATE DATE MAY 2025 MAY 2025 MAY 2025 Mar Endon Designed BY: IC DRAWN BY: IC DRAWN BY: IC DRAWN BY: IC
	STORM PLAN (SHEET 1 OF 2)
WARNING: CONTRACTOR IS TO WARNING: CONTRACTOR IS TO VERIFY PRESENCE AND EXACT DOUGTION OF ALL UTILITIES	CYPRESS CREEK COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS
PRIOR TO CONSTRUCTION.	23 OF 44 2024-42-SD





2024-42-SD




	TOTAL PROVIDED POND VOLUME									
	STAGE STORAGE CALCULATION									
ELEVATION	AREA (SF)	AREA (AC)	DEPTH (FT)	INCR. VOLUME (CF)	INCR. VOLUME (AC-FT)	CUMULATIVE VOLUME (CF)	CUMULATIVE VOLUME (AC-FT)			
912	7,690	0.177	0.00	0	0.000	0	0.00			
913	9,457	0.217	1.00	8574	0.197	8,574	0.20			
914	10,417	0.239	1.00	9937	0.228	18,511	0.42			
914.5	10,488	0.241	0.50	5226	0.120	23,737	0.54			
915	10,558	0.242	0.50	5262	0.121	28,999	0.67			
916	10,696	0.246	1.00	10627	0.244	39,626	0.91			
917	10,831	0.249	1.00	10763	0.247	50,389	1.16			
918	10,962	0.252	1.00	10896	0.250	61,286	1.41			


PROPOSED	PON


POND AND	OUTLET CO	NTROL CAL	CULATIO
RETURN PERIOD (YR)	OUTFLOW (CFS)	VOLUME (AC-FT)	MAX W (FT)
2	14.4	0.69	916.2
10	25.4	0.86	916.9
25	34.8	0.95	917.2
100	52.0	1.06	917.8

	SEDIMENTATION VOLUME									
	STAGE STORAGE CALCULATION									
ELEVATION	AREA (SF)	AREA (AC)	INCR. DEPTH (FT)	INCR. VOLUME (CF)	INCR. VOLUME (AC-FT)	CUMULATIVE VOLUME (CF)	CUMULATIVE VOLUME (AC-FT			
912	0	0.000	0.00	0	0.000	0	0.00			
913	1,767	0.041	1.00	884	0.020	884	0.02			
914	2,727	0.063	1.00	2247	0.052	3,131	0.07			
914.5	2,798	0.064	0.50	1381	0.032	4,512	0.10			

			FILTRATI	ON VOLUME			
		c,	STAGE STORA	GE CALCULA	TION		
ELEVATION	AREA (SF)	AREA (AC)	INCR. DEPTH (FT)	INCR. VOLUME (CF)	INCR. VOLUME (AC-FT)	CUMULATIVE VOLUME (CF)	CUMULATIVE VOLUME (AC-FT)
912	7,690	0.177	0.00	0	0.000	0	0.00
913	7,690	0.177	1.00	7690	0.177	7,690	0.18
914	7,690	0.177	1.00	7690	0.177	15,380	0.35
914.5	7,690	0.177	0.50	3845	0.088	19,225	0.44







TCEQ CALCULATIONS

TSS Removal Calculations 04-20-2009					Cypress Creek
1. The Required Load Reduction for the total project:		Calculation	s from RG-348	Date Prepared:	8/29/2024 Pages 3-27 to 3-30
Page 3-29 Equation 3	3.3: L _M =	27.2(A _N x F))		
where: L _{M TOTAL P}	A _N =	Net increas		area for the project	d development = 80% of increas
Site Data: Determine Required Load Removal Based on the Ent		-		,	
Total project area included in		Williams 5.82	on ` acres		
Predevelopment impervious area within the limits of the Total post-development impervious area within the limits of the	-		acres acres		
Total post-development impervious cover fra	action * =	0.70			
	P =	32	inches		
L _{M TOTAL P} * The values entered in these fields should be for the total proj			■lbs.		
Number of drainage basins / outfalls areas leaving the pla	an area =	1	•		
2. Drainage Basin Parameters (This information should be prov	vided for	each basir	<u>ı):</u>		
Drainage Basin/Outfall Are	rea No. =	1	•		
Total drainage basin/outfa			acres		
Predevelopment impervious area within drainage basin/outfa Post-development impervious area within drainage basin/outfa			acres acres		
Post-development impervious fraction within drainage basin/outfa	f <mark>all area =</mark> HIS BASIN =		∎lbs.		
3. Indicate the proposed BMP Code for this basin.	IIS BASIN	0040	100.		
where:	A _C =	Total On-Sit	te drainage area	in the BMP catchmen	t area
where:	A ₁ =	Impervious a	area proposed in	the BMP catchment	area
where:	A _I = A _P =	Impervious are	area proposed in ea remaining in tl		area ea
where:	A ₁ = A _P = L _R =	Impervious are	area proposed in ea remaining in tl	the BMP catchment and BMP catchment and the	area ea
where:	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$	Impervious are Pervious are TSS Load re 5.13 4.00	area proposed in ea remaining in tl emoved from this	the BMP catchment and BMP catchment and the	area ea
where:	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13	area proposed in ea remaining in th emoved from this acres acres acres	the BMP catchment and BMP catchment and the	area ea
where:	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$	Impervious are Pervious are TSS Load re 5.13 4.00	area proposed in ea remaining in th emoved from this acres acres	the BMP catchment and BMP catchment and the	area ea
where: 5. Calculate Fraction of Annual Runoff to Treat the drainage ba	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$	Impervious and Pervious and TSS Load n 5.13 4.00 1.13 3959	area proposed in ea remaining in th emoved from this acres acres acres	the BMP catchment and BMP catchment and the	area ea
	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $asin / out$	Impervious and Pervious and TSS Load n 5.13 4.00 1.13 3959	area proposed in ea remaining in the emoved from this acres acres acres Ths	the BMP catchment and BMP catchment and the	area ea
5. Calculate Fraction of Annual Runoff to Treat the drainage ba	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $asin / out$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 fall area	area proposed in ea remaining in th emoved from this acres acres acres lbs	the BMP catchment and BMP catchment and the	area ea
5. Calculate Fraction of Annual Runoff to Treat the drainage ba	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $I_{R} =$ $I_{R} =$ $I_{R} =$ $F =$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88	area proposed in ea remaining in the moved from this acres acres acres Ibs	the BMP catchment and BMP catchment and the	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THI} 6. Calculate Capture Volume required by the BMP Type for this Rainfall	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $IS BASIN =$ $F =$ $S drainag$ $I Depth =$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88 <u>e basin / or</u> 1.50	area proposed in ea remaining in the moved from this acres acres acres Ibs	the BMP catchment and catchment are BMP catchment are catchment area by th	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THI} 6. Calculate Capture Volume required by the BMP Type for this	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $IS BASIN =$ $F =$ $S drainag$ $I Depth =$ $fficient =$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88 <u>e basin / o</u>	area proposed in ea remaining in the moved from this acres acres lbs lbs.	the BMP catchment and catchment are BMP catchment are catchment area by th	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THI} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $IS BASIN =$ $F =$ $G drainag$ $I Depth =$ $fficient =$ $J Depth =$	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88 <u>e basin / or</u> 1.50 0.60 16668	area proposed in ea remaining in the moved from this acres acres lbs lbs. utfall area. inches cubic feet	the BMP catchment and catchment are BMP catchment are catchment area by th	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THI} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site area draining to	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $I_{R} =$ $F $	Impervious and Pervious and TSS Load m 5.13 4.00 1.13 3959 fall area 3482 0.88 te basin / ou 1.50 0.60 16668 Calculations 0.46	area proposed in ea remaining in the moved from this acres acres acres lbs lbs. utfall area. inches cubic feet s from RG-348 acres	the BMP catchment and catchment area by the Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $I_{R} =$ $F $	Impervious are Pervious are TSS Load n 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88 <u>e basin / o</u> 1.50 0.60 16668 Calculations	area proposed in ea remaining in the moved from this acres acres lbs lbs. utfall area. inches cubic feet	the BMP catchment and catchment area by the Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site area draining to Off-site Impervious cover draining to	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{L} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $F =$	Impervious are Pervious are TSS Load m 5.13 4.00 1.13 3959 <u>fall area</u> 3482 0.88 <u>e basin / or</u> 1.50 0.60 16668 Calculations 0.46 0.37	area proposed in ea remaining in the moved from this acres acres acres lbs lbs. utfall area. inches cubic feet s from RG-348 acres	the BMP catchment and catchment area by the Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site area draining to Off-site Impervious cover draining to Impervious fraction of off-sit Off-site Runoff Coeff	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{L} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $A_{P} =$ $C_{R} =$ $A_{P} =$ $C_{R} =$ $A_{P} =$ A_{P	Impervious and Pervious and TSS Load m 5.13 4.00 1.13 3959 fall area 3482 0.88 te basin / or 1.50 0.60 16668 Calculations 0.46 0.37 0.80 0.63	area proposed in ea remaining in the moved from this acres acres lbs lbs. utfall area. inches cubic feet s from RG-348 acres acres	the BMP catchment an catchment area by th Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site Impervious cover draining to Off-site Impervious fraction of off-sit Off-site Runoff Coef Off-site Water Quality V Storage for Sec Total Capture Volume (required water quality volume(s) x 9B. Partial Sedimentation and Filtration System	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{L} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $A_{P} =$ $L_{R} =$ $F =$ $S drainag$ $I Depth =$	Impervious and Pervious and TSS Load m 5.13 4.00 1.13 3959 fall area 3482 0.88 te basin / or 1.50 0.60 16668 Calculations 0.46 0.37 0.80 0.63 1578 3649 21895	area proposed in ea remaining in the moved from this acres acres lbs lbs. lbs. utfall area. inches cubic feet s from RG-348 acres acres cubic feet	the BMP catchment an catchment area by th Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site Impervious cover draining to Off-site Impervious cover draining to Off-site Impervious cover draining to Off-site Runoff Coeff Off-site Runoff	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ A_{P	Impervious and Pervious and TSS Load m 5.13 4.00 1.13 3959 fall area 3482 0.88 re basin / or 1.50 0.60 16668 Calculations 0.46 0.37 0.80 0.63 1578 3649 21895 cubic feet	area proposed in ea remaining in the moved from this acres acres lbs lbs. lbs. utfall area. inches cubic feet s from RG-348 acres acres cubic feet	the BMP catchment an catchment area by th Calculations from RG-	area ea he proposed BMP
5. Calculate Fraction of Annual Runoff to Treat the drainage ba Desired L _{M THE} 6. Calculate Capture Volume required by the BMP Type for this Rainfall Post Development Runoff Coeff On-site Water Quality V Off-site area draining to Off-site Imperious cover draining to Off-site Imperious cover draining to Off-site Runoff Coeff Off-site Runoff Off-site Runoff O	$A_{I} =$ $A_{P} =$ $L_{R} =$ $A_{C} =$ $A_{I} =$ $A_{P} =$ $L_{R} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $A_{P} =$ $L_{R} =$ $F =$ $S drainag$ $I Depth =$ $I De$	Impervious and Pervious and TSS Load m 5.13 4.00 1.13 3959 fall area 3482 0.88 ie basin / or 1.50 0.60 16668 Calculations 0.46 0.37 0.80 0.63 1578 3649 21895 cubic feet square feet	area proposed in ea remaining in the moved from this acres acres acres lbs lbs. lbs. utfall area. inches cubic feet s from RG-348 acres acres acres cubic feet cubic feet	the BMP catchment an catchment area by th Calculations from RG-	area ea he proposed BMP 348 Pages 3-34 to 3-3

POND MAINTENANCE NOTES:

DUE TO THE NATURE OF WET PONDS BEING FULL OF WATER WHEN IN OPERATION, THE NEED FOR MAINTENANCE IS NOT EASILY VISIBLE. HOWEVER, WHEN THE PONDS ARE BUILT IN STABLE UPLAND AREAS, THE NEED FOR MAINTENANCE OF THESE PONDS SHOULD BE INFREQUENT. ACCUMULATION OF SEDIMENT IN THE BASIN IS THE PRIMARY REASON THE POND WILL REQUIRE INTENSIVE MAINTENANCE. BECAUSE OF THIS, VERY CAREFUL ATTENTION SHOULD BE PAID TO ADEQUATE, WELL-MAINTAINED EROSION AND SEDIMENTATION CONTROLS IN THE CONTRIBUTING DRAINAGE AREA DURING CONSTRUCTION. THIS, IN COMBINATION WITH THE SEDIMENT FOREBAY, SHOULD PREVENT THE REQUIREMENT OF MAINTENANCE OF THE MAIN POOL SOON AFTER THE POND IS PUT ONLINE. THE FOLLOWING ARE GUIDELINES FOR POND MAINTENANCE:

DURING SITE CONSTRUCTION - THE SEDIMENT LOAD TO THE SEDIMENT FOREBAY SHALL BE CLOSELY MONITORED AFTER EVERY STORM EVENT. IF HEAVY SEDIMENT LOADS ARE DETECTED DURING AN INSPECTION, THE SOURCE SHOULD BE CORRECTED. SEDIMENT SHALL BE REMOVED FROM THE SEDIMENT FOREBAY WHEN ONE-THIRD OF THE FOREBAY VOLUME IS LOST.

UPON COMPLETION OF SITE REVEGETATION - ANY SEDIMENT BUILD-UP (GREATER THAN 5% VOLUME LOSS) SHALL BE REMOVED FROM THE FOREBAY UPON COMPLETION OF SITE REVEGETATION. THE SEDIMENT BUILD-UP IN THE MAIN POOL SHALL BE CHECKED AND IF MORE THE TEN-PERCENT OF THE VOLUME IS LOST, IT SHOULD BE CLEANED AT THAT TIME.


EVERY THREE MONTHS FOR THE FIRST TWO YEARS - DURING THE THREE MONTH INITIAL INSPECTION CYCLE, IF MORE THAN FIFTEEN PERCENT OF THE VOLUME OF THE FOREBAY IS LOST, IT SHALL BE CLEANED AT THAT TIME.


EVERY THREE MONTHS - TURF AREAS AROUND THE POND SHOULD BE MOWED. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY THREE MONTHS OR AS NECESSARY. CATTAILS, COTTONWOODS, AND WILLOWS CAN QUICKLY COLONIZE SHALLOW WATER AND THE EDGE OF THE POND. THESE SPECIES OR ANY AREAS OF PLANT OVERGROWTH MAY BE THINNED AT THIS TIME OR AS NEEDED.


ANNUALLY - THE BASIN SHOULD BE INSPECTED ANNUALLY FOR SIDE SLOPE EROSION AND DETERIORATION OR DAMAGE TO THE STRUCTURAL ELEMENTS. ANY DAMAGE SHALL BE REPAIRED. LARGE AREAS, WHICH HAVE DEAD OR MISSING VEGETATION, SHALL BE REPLANTED.


EVERY THREE YEARS - THE SEDIMENT BUILD-UP IN THE SEDIMENT FOREBAY SHALL BE CHECKED. THE SEDIMENT FOREBAY SHALL BE CLEANED IF MORE THAN ONE-THIRD OF THE FOREBAY VOLUME IS LOST.


EVERY SIX YEARS - THE SEDIMENT BUILD-UP IN THE MAIN POOL SHALL BE CHECKED. SEDIMENT SHALL BE REMOVED FROM THE MAIN POOL WHEN TWENTY PERCENT OF THE MAIN POOL VOLUME IS LOST.

























LEGEND

	PROPERTY LINE
ww	WASTEWATER LINE
w	WATER LINE
w	WASTEWATER MANHOLE
0	WASTEWATER CLEANOUT
	WASTEWATER FLOW DIRECTION
₽	FIRE HYDRANT
	TAPPING SLEEVE & VALVE
	STORM DRAIN LINE
	STORM DRAIN INLET
OHP	EXISTING OVERHEAD POWER LINE
W	EXISTING WATER LINE
WW	EXISTING WASTEWATER LINE
=======	EXISTING STORM SEWER LINE
\Diamond	EXISTING POWER POLE
	EXISTING FIRE HYDRANT
\otimes	EXISTING WATER METER
\bigcirc	EXISTING WASTEWATER MANHOLE

WATER NOTES

NON-CITY INFRASTRUCTURE INCLUDING GAS, ELECTRIC, CABLE AND
ELECOMMUNICATIONS SHALL TRAVERSE UNDERNEATH CITY INFRASTRUCTURE. THIS
CLUDES, BUT IS NOT LIMITED TO WATER LINES, WASTEWATER LINES AND STORM
EWER, WITH A MINIMUM OUTSIDE-TO-OUTSIDE CLEARANCE OF 18"
PIPE FITTINGS SHALL BE JOINT-RESTRAINED. ALL SEGMENTS OF PIPE LOCATED IN
NCASEMENT SHALL BE FULLY RESTRAINED.
. FITTINGS SHALL HAVE THRUST BLOCKING PER CORR WT-25.
. VALVES SHOWN ARE MUELLER BRAND.
. FIRE SERVICE LEADS SHALL BE DUCTILE IRON.
. PVC WATER MAINS SHALL BE CONSTRUCTED OF C-900 DR-14.
E DRY UTILITY ALIGNMENTS ARE PRELIMINARY. TO HAVE PRELIMINARY STATUS
EMOVED FROM PDS PERMIT, THE PERMIT MUST BE REVISED ONCE DRY ALIGNMENTS
RE APPROVED BY THE FRANCHISE UTILITY. THEN, INSTALLATION OF DRY UTILITIES MAY
DMMENCE.
E CALCULATIONS FOR THIS DEVELOPMENT WERE CALCULATED UTILIZING LUE
ONVERSIONS PROVIDED BY CITY OF AUSTIN UTILITY DEVELOPMENT SERVICES DIVISIOI
660 SF OF RETAIL/LUE). THIS PROJECT PROPOSES 28 LUES.
NTRACTOR IS REQUIRED TO USE A CERTIFIED ASBESTOS CEMENT REMOVAL

CONTRACTOR AND CONDUCT AIR MONITORING BY A STATE CERTIFIED INSPECTOR. THESE ENVIRONMENTAL MITIGATION STEPS WILL BE TAKEN TO ENSURE THE SAFETY OF WORKERS AND CUSTOMERS DURING THE REMOVAL.

0.REMOVE ASBESTOS CEMENT PIPE SECTION TO NEAREST JOINT/BELL IN BOTH DIRECTIONS. LOCATE AND REMOVE BELLS AT BOTH OF YOUR CONNECTION POINTS TO THE EXISTING ASBESTOS CEMENT WATER LINE, AND SAW CUT 1' BACK ON BELL END SIDE OF THE ASBESTOS CEMENT PIPE. CONNECT THE AC PIPE TO PVC WITH 8" MACRO HP TWO BOLT EXTEND RANGE COUPLING.


WASTEWATER/WATER CROSSING NOTE

1. ALL WASTEWATER PIPE CROSSING WATER LINES SHALL BE ENCASED IN HDPE DR-17 (DIPS) IN ACCORDANCE WITH TAC 290.44[e][4][B][ii][II].


	UTILITY CROS	SING TABLE		
TYPE OF HIGHER PIPE	INVERT ELEVATION	TYPE OF LOWER PIPE	CROWN ELEVATION	VERTICAL SEPARATION (FT)
WASTEWATER	917.93	WATER	915.52	2.41
WASTEWATER	917.93	WATER	915.69	2.24
WASTEWATER	917.78	STORM	916.80	0.97
WASTEWATER	917.37	WATER	915.69	1.69
WASTEWATER	917.37	WATER	915.86	1.51
STORM	919.06	WASTEWATER	917.71	1.35
WASTEWATER	918.46	WATER	915.69	2.77
WASTEWATER	918.46	WATER	915.52	2.94
WASTEWATER	917.77	WATER	915.52	2.25
WASTEWATER	917.77	WATER	915.69	2.08




Know what's **below. Call** before you dig.





					DATE BY
					REVISIONS
					No.
		5301 SOUTHWEST PARKWAY, BUILDING 3, SUITE 100	AUSTIN, TX 78735 PHONE: 512–646–2237 FAX: 512–418–1791	C 2025 VIMIEY-HORN.COM	TBPE Firm No. 928
	DMAS J. 13 22 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	OF 72 LOME	Stas BARDI	/19/	25
KHA PROJECT 065011800	DATE MAY 2025	SCALE: AS SHOWN	DESIGNED BY: IC	DRAWN BY: IC	CHECKED BY: TLJ
		OVERALL WATER PLAN			
		COMMERCIAL	CITY OF CEDAR PARK	WILLIAMSON COUNTY, TEXAS	
29 202	· ·	DF	4	4	



		DATE BY
		S S S S S S S S S S S S S S S S S S S
	LEGEND	REVISIONS
		RE \
	W WASTEWATER LINE W WATER LINE	
	W WASTEWATER MANHOLE	
	O WASTEWATER CLEANOUT	o Ż
	WASTEWATER FLOW DIRECTION	
	FIRE HYDRANT	
	TAPPING SLEEVE & VALVE	
	STORM DRAIN LINE	Horn DING 3, SUITE 100 5 512-418-1791 COM SSOCIATES, INC.
	STORM DRAIN INLET EXISTING OVERHEAD POWER LINE	<u>ш</u> о п
	W — EXISTING WATER LINE	BUILDING 3, 8735 AX: 512-41 DRN.COM D ASSOCIAT
,	WW — EXISTING WASTEWATER LINE	
====		X 787 X 787 Y FAX: -HORN No. 5
	EXISTING POWER POLE	Trm , Tx 177
	EXISTING FIRE HYDRANT	D ARK J SARK A 46-2 KIMU PE F
	EXISTING WATER METER	ALEY MLEY TBI
	EXISTING WASTEWATER MANHOLE	H H ME
	WATER NOTES	
	 ALL NON-CITY INFRASTRUCTURE INCLUDING GAS, ELECTRIC, CABLE AND TELECOMMUNCATIONS SHALL TRAVERSE UNDERNEATH CITY INFRASTRUTURE. THIS INCLUDES, BUT IS NOT LIMITED TO WATER LINES, WASTEWATER. LINES AND STORM SEWER, WITH A MINIMUM OUTSIDE-TO-OUTSIDE CLEARANCE OF 18' ALL PITTINGS SHALL BE JOINT-RESTRAINED. ALL SEGMENTS OF PIPE LOCATED IN ENCASEMENT SHALL BE JOINT-RESTRAINED. ALL SEGMENTS OF PIPE LOCATED IN ENCASEMENT SHALL BE CONSTRUCTED OF C.900 DR-14. ALL PYC WATER MAINS SHALL BE CONSTRUCTED OF C.900 DR-14. THE DRY UTILTY ALISON BUT ALL BE CONSTRUCTED OF C.900 DR-14. THE DRY UTILTY ALISON BET ARE PREMIMINARY. TO HAVE PRELIMINARY STATUS REMOVED FROM PDS PERMIT, THE PERMIT MUST BE REVISED ONCE DRY ALIGNMENTS ARE APPROVED BY THE FRANCHSE UTILITY. THEN, INSTALLTION OF DRY UTILITES MAY COMMENCE. UE CALCULATIONS FOR THIS DEVELOPMENT WERE CALCULATED UTILIZING LUE CONTRACTOR AND CONDUCT AIR MONITORING BY A STATE CERTIFIED INSPECTOR. THESE ENVIRONMENTAL MITIGATION STEPS WILL BE TAKEN TO ENSURE THE SAFETY OF WORKERS AND CUSTORERS DURING THE REMOVAL. ONTRACTOR AND CONDUCT AIR MONITORING BY A STATE CERTIFIED INSPECTOR. THESE ENVIRONMENTAL MITIGATION STEPS WILL BE TAKEN TO ENSURE THE SAFETY OF WORKERS AND CUSTORERS DURING THE REMOVAL. ONTRACTOR AND CONDUCT AIR MONITORING BY A STATE CERTIFIED INSPECTOR. THESE ENVIRONMENTAL MITIGATION STEPS WILL BE TAKEN TO ENSURE THE SAFETY OF WORKERS AND CUSTORERS DURING THE REMOVAL. ONTRACTOR AND CONDUCT AIR MONITORING BY A STATE CERTIFIED INSPECTOR. THESE ENVIRONMENTAL MITIGATION STEPS WILL BE TAKEN TO ENSURE THE SAFETY OF WORKERS AND CUSTOR CERTIFIES CONNECT THE ACONNECTION POINTS TO THE EXISTING ASBESTOS CEMENT WATER LINE, AND SAW CUT 'I BACK ON BELL END SIDE OF THE ASBESTOS CEMENT WATER LINE, AND SAW CUT 'I BACK ON BELL END SIDE OF THE ASBESTOS CEMENT WHE CONNECT THE ACONNECTION POLICE TO POURS THE SECONNECTION FOR ALL UTILITIES PRICE TO CONSTRUCTION. 	A COLECT WATER PLAN (1 OF 2) ISON MAY 2025 MAY 2026 MAY 2027 MAY 2026 MAY 2026
7		CYPRESS CREE COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS WILLIAMSON COUNTY, TEXAS
		30 OF 44
		2024-42-SD







 \odot


OUNTY,

C NO

IAMS

Ž











			TABLE O FOR 18 REINFORCIN	"OUTLE	ITITIES ET PIPE L QUANTITIES	
	BARS	SIZE	SPACING	NUMBER	LENGTH	WEIGHT
	A	4	230mm (9")*	15	2 m (7'-0'')	73
	В	4	250 mm (10")	4	3.25 m (10'-8'')	29
	С	4	460 mm (18")	7	760 mm (2'-6'')	12
	D	6	150 mm (6'')	5	3.25 m (10'-8'')	80
	E	4	300 mm (12")	6	760 mm (2'-6'')	10
	F	4	<u>250 mm (10'')</u>	3	4 m (13'-0'')	35
	G	4	300 mm (12")	11	1.25 m (4'-3'')	31
	H	6		1	4.25 m (14'-0'')	20
	J	4	300 mm (12")	7	3.25 m (10'-8'')	50
	K	4	230 mm (9")*	30	800 mm (2'-7 1/2'')	52
	L	4	300 mm (12")*	6	1.3 m (4'-4'')	17
	М	4	_	4	500 mm (1'-8'') AVG	4
	N	MOE COLOR: SURFACE	DEL SD-SP, SQU/ Blue. use alme Mount W/ Adh	ARE HOLE Tek spec	RAINS TO WATERWAY" M OPTION, SYMBOL: FISH S FOR THEFT RESISTAN R DRY CONCRETE INSTA	H, T RIVET ALLATION.
		l steel,				413
		CONCRE				4.06
	* EXCE	PT AS SH	OWN ON PLAN			
180 m (7'		560 mr (22")	V V V V V V V V V V V V V V V V V V V	2 1 () 200 mm 200 mm		") MIN.
	BA	RG	Br	AR K	bar a	
		CEDAR		TYPI	CAL DETAILS FOR C	
1.0	Je II	Maill	12/03/09	THE ARCHITI RESPONSIBIL OF THIS STA	ECT/ENGINEER ASSUMES ITY FOR APPROPRIATE USE INDARD.	standard no. 3 of 4




R PARK Blic works	TYPICAL DETAILS FOR C	CURB INLET
	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE	STANDARD NO. 1 OF 4
ADOPTED	OF THIS STANDARD.	






		DATE
		REVISIONS
		Kim ey and a southwest parkway, Building 3, suite 100 austin, tx 78735 phone: 512-646-2237 fax: 512-418-1791 www.kimley-horn.com cold kimley-horn.com tbpe firm No. 928
		KHA PROJECT 065011800 065011800 065011800 DATE MAY 2025 MAY
5.5" BRANCH 5.5" BRANCH 8.0" BRANCH ILIENT WEDGE (length 8") ILIENT WEDGE (length 9") ILIENT WEDGE (length 10.5") .) .) .) .) .2 (COMPOUND) (length 17") C2 (COMPOUND) (length 17") C2 (COMPOUND) (length 20") C2 (COMPOUND) (length 24") COUPLING ADAPTER COUPLING ADAPTER COUPLING ADAPTER D) ED) ILIENT WEDGE (length 8") LLIENT WEDGE (length 8")		UTILITY DETAILS (SHEET 1 OF 2)
LIENT WEDGE (length 10.5") 5.5" BRANCH 0" BRANCH 0" BRANCH CUT IF NEEDED) (CUT IF NEEDED) COUPLING ADAPTER (912) COUPLING ADAPTER (912) ILIENT WEDGE (length 8") ILIENT WEDGE (length 9")		COMMERCIAL COMMERCIAL CITY OF CEDAR PARK WILLIAMSON COUNTY, TEXAS
		SHEET NUMBER
	1	2024-42-SD







						DATE BY
						REVISIONS
						No.
	Vindan Mundani V	NIIIley »> TOLII	5301 SOUTHWEST PARKWAY, BUILDING 3, SUITE 100	AUSTIN, TX 78735 PHONF: 512-646-2237 FAX: 512-418-1791		TBPE Firm No. 928
		5, ATE MAS J. 13 2, (10) 5, (10) 13 13 13 13 13 13 13 13 13 13 13 13 13	DF TE LOME 1071 ENSE	BARD	/19/	25
	KHA PROJECT 065011800	DATE MAY 2025	SCALE: AS SHOWN	DESIGNED BY: IC	DRAWN BY: IC	снескер ву: ТLJ
		UTILITY DETAILS				
			COMMERCIAL	CITY OF CEDAR PARK	WILLIAMSON COUNTY, TEXAS	
	3	^{SHEET} 6 С 24-4)F		4	
4	202		t∠'	-C) L	,



F	NO	TREE DAT	
$\left \right $	NO. 1	SPECIES Live Oak	DIAMETER (INCHES) 18
F	3 6	Oak Oak	12
E	9	Live Oak	15
F	11 12	Oak Oak	10 8
	13	Oak	8
F	14 17	Oak Oak	24
ŀ	17	Oak	9
: [19	Live Oak	10
$\left \right $	20 21	Live Oak Live Oak	12
Ē	21	Live Oak	13
-	24 25	Live Oak	13
$\left \right $	25 26	Live Oak Live Oak	12
	27	Oak	13
╞	28 29	Oak Live Oak	11 15
ŀ	30	Live Oak	13
	31	Oak	8
╞	32 33	Pecan Pecan	10
Ē	34	Live Oak	11
	557	Live Oak	7
╞	558 559	Live Oak Oak	6
	560	Oak	5
F	561	Live Oak	7
ŀ	562 563	Live Oak Oak	6
Ę	564	Oak	5
	565 566	Live Oak Live Oak	<u>6</u> 7
ŀ	567	Oak	7
F	568	Oak	7
ŀ	569 570	Oak Oak	7 7
	571	Oak	6
F	572 573	Oak Cedar Elm	6
	573	Cedar Elm Oak	<u>6</u> 10
	575	American Elm	6
$\left \right $	576 577	American Elm Oak	<u>6</u> 7
ŀ	578	American Elm	6
	579	American Elm	7
-	580 581	American Elm Cedar Elm	6
t	582	Oak	7
	583	Oak Live Oak	6
	584 585	Live Oak Live Oak	6 7
	586	Cedar Elm	7
╞	587 588	Cedar Elm Oak	7 12
ŀ	934	Oak	16
F	936	Sycamore	14
╞	939 940	Oak Oak	12
	941	Oak	12
F	943 944	Live Oak	14 12
ŀ	944 945	Live Oak Live Oak	9
Ľ	946	Live Oak	8
┝	947 948	Live Oak Live Oak	8
F	949	Live Oak	8
F	950	Live Oak	9
$\left \right $	951 952	Live Oak Live Oak	11 13
	953	Live Oak	12
╞	954 955	Live Oak	25
ŀ	955	Oak Live Oak	13 14
	957	Live Oak	8
	958 959	Live Oak Live Oak	<u> </u>
E	959	Live Oak	12
	961	Live Oak	18
╞	962 963	Live Oak Live Oak	<u>18</u> 17
F	964	Live Oak	23
F	965	Live Oak	29
┢	966 967	Live Oak Live Oak	24
Ľ	968	Live Oak	12
-	969 970	Cedar Elm Live Oak	10
F	970 971	Live Oak	14 12
F	972	Live Oak	14
┝	973 974	Live Oak Live Oak	<u>12</u> 21
t	975	Live Oak	22
F	976	Live Oak Coder Film	12
╞	977 978	Cedar Elm Live Oak	8
	979	Cedar Elm	11
	980	Live Oak	15
╞	981 982	Live Oak Live Oak	<u>16</u> 16
	983	Live Oak	11
F	984	Live Oak	13
╞	985 986	Live Oak Live Oak	10
	987	Live Oak	12
F	988	Live Oak	14
┢	989 990	Live Oak Live Oak	<u>12</u> 9
Ľ	991	Live Oak	10
F	992	Live Oak	13
┢	993 994	Oak Live Oak	16
Ľ	995	Live Oak	13
F	996 997	Live Oak Live Oak	<u>9</u> 12
ŀ	997 998	Live Oak Oak	12
Ľ	999	Live Oak	20
Г	1000	Pecan	14

н





a) Regular maintenance of all required landscaped areas and plant materials in a vigorous and healthy condition, free from diseases, pests, weeds, and litter. This maintenance shall include weeding, watering, fertilization, pruning, mowing, edging, mulching, or other needed maintenance, in accordance with generally accepted horticultural practice.

- b) The repair or replacement of required landscape sructures
- (walls, fences, etc.) to a sctructurally sound condition. c) The regular maintenance, repair, or replacement, where
- necessary, of any required screening or buffering.


IRRIGATION NOTES


Automatic irrigation systems shall comply with the following guidelines.

- Adjustable flow controls shall be required on circuit remote control valves and
- pressure regulation component(s) shall be required where static pressure exceeds manufacturer's recommended operating range.
- 2. Valve and circuits shall be separated based on water use, so that turf areas are watered separately from shrub and ground cover areas. Irrigation heads in the turf areas will be valved separately from shrub and/or ground cover areas.
- Sprinkler heads shall have matched precipitation rates within each control valve circuit.
- Serviceable check values shall be required adjacent to paved areas where elevation differences may cause low head drainage.
 Sprinkler head spacing shall be designed for head-to-head coverage or heads shall be spaced as per manufacturer's recommendations and adjusted for prevailing winds. The system shall be designed so that irrigation is not applied to vehicular traffic lanes, other pavement
- or structures. All automatic irrigation systems shall be equipped with a controller capable of dual or multiple programming. Controllers shall have multiple cycle start capacity and a flexible calendar program, including the capability of being set to water every five days. All automatic irrigation systems shall be equipped with a rain sensor shut-off device.
 Irrigation construction plans shall include a water budget. A laminated copy of the water budget shall be permanently installed inside the irrigation controller door. Water budget shall include:
- A. Chart containing zone number, precipitation rate and gpm.
- B. Location of emergency irrigation system shut-off valve.

LANDSCAPE CERTIFICATION I, Stacie Holt, do hereby certify that the plans

for this development project satisfy the requirements of the Cedar Park Landscape and Tree Ordinance.





0.0 **BUILDING-1 ONE-STORY SHELL** 0.0 0.0 0.0 0.0 GSF = 8,875 SF BUILDING HEIGHT = 35' 0.1 0.2 1.3 4.1 2.5 6.7 0.7 5.8 3.1 0.5 6.3 1.6 0.3 0.4 0.2 0.3 0.3 0.1 0.4 0.2 0.1 0.2 0.1 0.2 0.9 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 FFE = 921' 0.1 0.2 1.5 990 RR 0.0 0.000 0.0 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 BUILDING-**ONE-STORY SHEL** GSF = 9,000 SF BUILDING HEIGHT = 35 0.0 0.0 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0 4 0.5 0.6 0.7 0.7 0.7 0.7 0.7 0.6 0.6 0.5 0.5 FFE = 922 0.0 0.0 0.0 0.0 0.0 0.0 0.1 0.1 0.2 0.3 0.4 0.7 0.9 1.1 1.3 1.3 1.4 1.4 1.3 1.2 1.1 0.9 2.2 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.5 0.8 1.4 1.9 2.2 2.4 2.6 2.5 2.3 2.1 1.8 1.2 0.8 9.1⁶3.2 9.4⁶6.1 3.5 1.5 1.1 2.3 4.5 3.8 4.3 3.6 1.5 1.1 2.3 4.212.6 1.2 8.3⁶4.3 0.1 0.1 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.5 0.8 1.4 2.3 2.7 3.1 3.4 3.3 2.9 2.5 2.0 1.1 0.7 0.5 0.5 0.8 1.2 1 1 0.7 0.5 0.9 1.3 1.4 1.4 1.2 0.7 0.5 0.9 1.2 1.0 7.8 1.4 6.5 1.9 0.1 0.7 0.2 0.0 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0 4 0.6 0.8 1.3 2.2 2.8 3.6 4.2 4.0 3 2 2 5 1.8 1.0 0.6 0.5 0.4 0.4 0.4 0.4 0.2 0.3 0.2 0.3 0.4 0.5 0.5 0.4 0.3 0.3 0.3 0.5 3.6 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.4 0.5 0.6 0.8 1.0 1.3 1.6 1.5 1. 1.4 1.4 1.3 1.0 0.6 0.4 0.3 0.2 0.2 0.2 0.2 0.2 0.2 0.2 0.3 0.3 0.3 0.3 0.3 0.3 0.4 0.8 4. 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.5 0.7 0.9 1.2 1.5 2.1 2.9 3.4 3.6 3.6 3.4 3.2 2.8 2.0 1.1 0.7 0.4 0.3 0.3 0.2 0.3 0.3 0.3 0.4 0.5 0.5 0.5 0.5 0.5 0.5 0.7 1.5 5.2 0.0 0.0 0.1 0.1 0.2 0.2 0.4 0.6 1.1 2.0 2.7 3.4 4.2 5.2 5.4 5.5 5.4 4.7 3.7 3.0 2.3 1.3 0.8 0.5 0.4 0.4 0.3 0.4 0.5 0.9 1.3 1.6 1.7 1.9 2.0 1.9 1.8 1.8 2.0 2.7 0.0 0.0 0.1 0.1 0.2 0.3 0.4 0.6 1.0 1.9 2.8 3.6 4.8 5.6 5.4 5.0 4.6 3.8 2.9 2.4 1.9 1.4 0.8 0.6 0.4 0.4 0.4 0.4 0.6 0.9 1.7 2.3 2.6 2.8 3.0 2.9 2.8 2.5 2 7 4 7 0.0 0.0 0.1 0.1 0.1 0.2 0.4 0.6 1.0 1.7 2.5 3.4 4.2 4.8 4.5 3.9 3.3 2.6 2.0 1.6 1.3 1.0 0.8 0.5 0.4 0.4 0.4 0.4 0.5 0.8 1.5 2.3 2.8 3.5 4.0 3.6 3.0 2.5 X.8/X. 00 0.0 0.0 0.1 0.1 0.2 0.3 0.4 0.7 1.2 2.0 2.8 3.0 31 3.1 3.0 2.2 1.5 1.1 0.9 0.7 0.6 0.5 0.5 0.4 0.4 0.5 0.5 0.8 1.4 2.1 2.7 3.4 5.9 3.6 3.0 2.4 1.7 1.2 0.0 0.0 0.0 0.1 0.1 0.2 0.3 0.4 0.7 1.2 2.1 3.0 2.8 28 2.9 3.1 2.1 1.4 0.9 0.7 0.5 0.5 0.5 0.4 0.4 0.4 0.4 0.4 0.4 0.5 1.0 1.6 2.4 2.6 2 8 2.8 2.0 1.5 4.4 0 0 0 0 0 0.0 0.0 0.1 0.1 0.2 0.3 0.5 0.9 1.5 2.3 2.9 3.7 4.2 3.7 3,0 2.3 1.6 1.0 0.7 0.5 0.5 0.6 0.6 0.6 0.6 0.6 0.4 0.6 1.1 1.9 2.8 2.6 28 2.9 3.3 2.5 2.2 2.7 0,0 0.0 0.0 0.1 0.1 0.2 0.2 0.3 0.5 0.9 1 7 2.4 2.8 3.5 3.9 3.5 2.9 2.4 1.7 0.9 0.6 0.5 0.5 0.6 0.8 0.8 0.8 0.9 0.8 0.6 0.8 1.4 2.1 2.8 3.6 4.5 4.3 3.5 3.2 3.3 5.7 0 0 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.5 0.9 1.8 2.2 2.6 2.8 3.0 2.8 2.6 2.3 1.8 1.1 0.7 0.5 0.5 0.7 1.1 1.4 1.4 1.3 1.2 0.6 0.8 1.6 2.3 2.8 3.4 4.5 4.4 4.0 3.8 3.7 6.5 0.0 0.0 0.1 0.1 0.1 0.2 0.3 0.5 0.9 1.2 1.5 1.6 1.7 1.8 1.8 1.8 1.7 1.5 1.2 0.8 0.6 0.6 0.8 1.3 2.0 2.3 2.1 2.1 0.7 0.9 1.6 2.2 2.5 2.7 4.4 4.6 4.7 4.4 3.5 5.3 0.0 0.0 0.0 0.0 0.1 0.1 0.2 0.3 0.4 0.5 0.7 0.8 0.9 0.9 1.0 1.1 1.5 1.9 1.9 1.6 1.2 0.8 0.7 1.0 1.5 2.4 2.8 2.9 2.8 0.7 0.8 1.2 1.4 1.6 1.7 1.2 4.3 4.2 3.9 2.9 2.1 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.2 0.2 0.3 0.3 0.4 0.4 0.5 0.6 1.0 2.3 5.2 4.5 3.9 2.2 1.2 0.9 1.1 1.7 2.7 3.3 3.6 2.9 0.5 0.5 0.6 0.8 0.8 0.9 3.6 4.214.0 3.6 2.5 4.7 0.0 0.0 0.0 0.0 0.1 0.1 0.1 0.1 0.1 0.2 0.2 0.3 0.4 0.4 0.4 1.1 4.11779.019.013.416.517.7 1.2 1.8 3.0 3.7 4.4 28 0.4 0.3 0.3 0.4 0.4 0.5 3.1 4.6 4.2 3.4 2.3 1.4 8.4 1.6 6.5 1.9 0.2 0.1 0.1 0.0 0.0 B 7.9 1.3 2.0 3.1 3.9 4.6 2.8 0.3 0.1 0.2 0.2 0.2 0.3 3.6 4.7 4.3 3.5 2.3 1.4 0.8 0.5 0.3 0.2 0.2 0.1 0.1 0.0 0.0 6.4 1.6 2.3 3.3 3.8 4 1 2.9 0.2 0.1 0.1 0.1 0.1 0.2 3.2 4.2 3.9 3.6 2.5 1.5 0.8 0.5 0.3 0.4 0.4 0.1 0.1 0.0 0.0 3.4 2.8 3.2 4.3 4.5 4.1 2.9 0.3 0.0 0.0 0.0 0.1 0.1 3.2 4.0 4.4 4.3 2.9 8.5 B RETENTION STRUCTURE 7.6 3.8 3.5 4.2 4.1 3.7 2.4 0.2 0.0 0.0 0.0 0.0 0.1 3.1 3.8 4.0 4.0 2.9 2.0 0.0 0.1 0.1 0.1 6.5 4.0 3.5 3.8 4.3 3.6 2.1 0.1 0.0 0.0 0.0 0.0 0.1 3.0 4.0 4.1 3.7 3.1 9.3 0.0 0.0 0.1 0.1 <u>* . . .</u> BUILDING-5 **ONE-STORY SHEL** 7.8 4.1 3.4 3.6 4.5 3.5 + 0.1 0.0 0.0 0.0 0.0 0.1 4.2 4.4 3.6 3.7 7.8 -CHAIN LINK FENCE 0.0 0.0 0.0 0 1 GSF = 8,994 SF & ELECTRIC -TRASH ENCLOSURE BUILDING HEIGHT = 35 7.0 3.9 3.2 3.3 4.0 3.2 1.8 0.1 0.0 0.0 0.0 0.0 0.1 2.7 3.7 3.9 3.4 3.5 6 2 🖡 0.0 0.0 v.c.h FFE = 925.5' 6.8 3.7 2.9 3.1 3.1 2.8 1.6 0.1 0SO 0.0 0.0 0.0 0.1 2.6 3.0 3.1 3.1 2.8 3.2 0.0 0.0 PROPANE 10' PUBLIC UTILITY EASEMENT -TANK -0.0_0.0 CAB. I, SL. 221 P.R.W.C.T. RAIL FENCE ON LOT 101 0.0 0.0 2.5 1.9 1.8 1.9 1.6 1.5 0.7 0.0 0.0 0.0 0.0 0.0 0.0 1.1 1.6 1.8 2.0 1.5 1.1 0.0 0.0 0.1 0001010.2 3.5 0.7 0.6 0.6 0.5 0.5 0.2 0.0 0.0 0.0 0.0 0.0 0.0 0.3 0.5 0.6 0.7 0.9 8 0 0.0 0.1 0.4 0.0 0.1 0.3 0.9 2.2 3.1 3.1 2.5 1.1 0.5 0.3 0.2 0.2 0.2 0.2 0.1 0.1 0.0 0.0 0.0 0.0 0.0 0.0 0.1 0.2 0.2 0.5 1.5 6.9 RETAININ WALL ----10' PUBLIC UTILITY & EASEMENT CAB. 1, SL. 221 P.R.W.C.T.


SHEET NOTES

0' PUBLIC UTILITY EASEMENT CAB. I, SL. 118-119, P.R.W.C.T.

GENERAL: REFER ALSO TO GENERAL ELECTRICAL NOTES ON SHEET E1.0.

- LIGHT SOURCES TO BE COMPLETELY CONCEALED WITHIN OPAQUE HOUSING AND SHALL NOT BE VISIBLE FROM ADJACENT STREETS OR PROPERTIES.
- ALL EXTERIOR LIGHT FIXTURES SHALL BE FULL CUT-OFF TYPE FIXTURES.
- LIGHT IS CONTAINED ON SITE AND DOES NOT CROSS ANY PROPERTY LINE OF THE SITE. (REFERENCE SECTION 14.08.006 AND SITE DEVELOPMENT PERMIT APPLICATION CHECKLIST)

Disclaimer: The lighting for this site is designed to meet the City of Cedar Park's requirement of 0.0 lighting at the property line. This requirement does not allow for the



MODEL	INPUT WATTS	VOLTS	NOTE 1	
30K-D010X-TF2-CP104-PA15-MWI-I	39 IB-WLKA	120V 1P 2W	COORDINATE EXACT MOUNTING HEIGTH WITH ARCHITECT PRIOR TO INSTALLING	4_
30K-XW-D010X-CL-WM-MB	20	120V 1P 2W	COORDINATE EXACT MOUNTING HEIGTH WITH ARCHITECT PRIOR TO INSTALLING. COORDINATE FINISH WITH ARCHTIECT PRIOR TO ORDERING/PURCHASING.	Issue Log Original Date: 03/28/2025
-30K-80CRI-VW-MVOLT-SRM-FINISH	27	120V 1P 2W	COORDINATE MOUNTING HEIGHT WITH ARCHITECT PRIOR TO INSTALLING	
	5.8	120V 1P 2W	MOUNT AT 8'-0"	
	11	120V 1P 2W	COORDINATE EXACT MOUNTING HEIGHT WITH ARCHITECT	DRAWN BY: CHECKED BY: AYS AYS
G M MDD MVOLT 35K 80CRI WH	42	120V 1P 2W		COPYRIGHT
G iok-blc-208-spa-nltair2-pirhn-d -5c-dm19as finish	163 BLXD	208V 2P 2W	COORDINATE FINISH WITH ARCHITECT	
g iok—T5w—208—SPA—Nltair2—Pirhn—D -5C—DM28AS Finish	326 BLXD	208V 2P 2W	COORDINATE FINISH WITH ARCHITECT	K DING ROAD 7861
C				CYPRESS CREEK RETAIL CENTER, BUILDIN 703 CYPRESS CREEK RO/ CEDAR PARK, TEXAS 78
)				
				Sheet Number:

Engineering, LLC

1 W. Main Street, Suite 310 • Round Rock • TX

w w w. A Y S e n g . c o m • 512-961-6835 TBPE Firm F-10298

ARON DENNING

39 OF 44

Project Number:

24 - 023

