EDWARDS AQUIFER WATER POLLUTION ABATEMENT PLAN EXCEPTION

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS

MAY 2025

Prepared For:



Williamson County 3151 SE Inner Loop Georgetown, Texas 78626 Prepared By:



STV, Inc. 13809 Research Blvd Suite 300 Austin, Texas 78750



TCEQ – Austin Regional Office 2800 S. IH 35, Suite 100 Austin, TX 78704-5700

RE: Pond Springs Road – Water Pollution Abatement Plan Exception Request

To Whom It May Concern:

Please find all necessary attachments required for the Edwards Aquifer Recharge Zone Exception Request (Form TCEQ-0628). With the included forms and attachments, we demonstrate equivalent water quality protection for the Edwards Aquifer. This package also demonstrates no permanent mitigation is necessary.

If you have any questions or need additional information, please do not hesitate to contact our office at (512) 349-0700.

Sincerely,

Anthony Serda, P.E.

Table of Contents

- 1. Edwards Aguifer Application Cover Page (TCEQ-20705)
- 2. General Information Form (TCEQ-0587)

```
Attachment A – Road Map
```

Attachment B – USGS / Edwards Recharge Zone Map

Attachment C - Project Description

- 3. Geologic Assessment Exception
- 4. Recharge and Transition Zone Exception Request Form (TCEQ-0628)

```
Attachment A – Nature of Exception
```

Attachment B – Documentation of Equivalent Water Quality Protection

5. Temporary Stormwater Section (TCEQ-0602)

Attachment A - Spill Response Actions

Attachment B - Potential Sources of Contamination

Attachment C - Sequence of Major Activities

Attachment D - Temporary Best Management Practices and Measures

Attachment E - Request to Temporarily Seal a Feature (if sealing a feature)

Attachment F - Structural Practices

Attachment G - Drainage Area Map

Attachment H - Temporary Sediment Pond(s) Plans and Calculations

Attachment I - Inspection and Maintenance for BMPs

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

- 6. Permanent Stormwater Section Exception
- 7. Agent Authorization Form (TCEQ-0599), if application submitted by agent
- 8. Application Fee Form (TCEQ-0574)
- 9. Core Data Form (TCEQ-10400)

SECTION 1 Application Cover Page TCEQ-20705

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- 1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- When an application is deemed administratively complete, the technical review period begins. The regional
 office will distribute copies of the application to the identified affected city, county, and groundwater
 conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
 to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Pond Springs Road Drainage Improvements				2. Regulated Entity No.:				
3. Customer Name: Williamson County			4. Customer No.: CN600897888					
5. Project Type: (Please circle/check one)	New	Modif	Modification Extension		nsion (Exception		
6. Plan Type: (Please circle/check one)	WPAP CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential	Non-r	Non-residential 8.		8. Sit	e (acres):	2.28	
9. Application Fee:	\$500	10. P	10. Permanent BMP(s)		s):	N/A		
11. SCS (Linear Ft.):	N/A	12. AST/UST (No. Tank			ıks):	N/A		
13. County:	Williamson	14. Watershed:				San Gabriel River Basin		

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)	_	_	<u>X</u>		
Region (1 req.)	_	_	<u>X</u>		
County(ies)	_	_	<u>X</u>		
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	X_AustinCedar ParkFlorenceGeorgetownJerrellLeanderLiberty HillPflugervilleRound Rock		

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	_		_	_	_
Region (1 req.)	_				_
County(ies)	_		_		_
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that to		
application is hereby submitted to TCEQ for administrative review and technical review.		
Anthony Serda		
Print Name of Customer/Authorized Agent		
1 dty	5/29/2025	
Signature of Customer/Authorized Agent	Date	

FOR TCEQ INTERNAL USE ONL	Y			
Date(s)Reviewed:		Date Administratively Complete:		
Received From:	Correct Number of Copies:		•	
Received By:	Dis	ribution Date	e:	
EAPP File Number:	Cor	Complex:		
Admin. Review(s) (No.):	No	No. AR Rounds:		
Delinquent Fees (Y/N):	Rev	Review Time Spent:		
Lat./Long. Verified:	SO	SOS Customer Verification:		
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):):
Core Data Form Complete (Y/N):		Check: Signed (Y/N): Less than 90 days old (Y/N):		
Core Data Form Incomplete Nos.:				Y/N):

SECTION 2

General Information *TCEQ-0587*

General Information Form

Texas Commission on Environmental Quality

Print Name of Customer/Agent: Anthony Serda

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

Date: 5/29/2025

Signature of Customer/Agent:

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Д	the state of the s
Pi	roject Information
1.	Regulated Entity Name: Pond Springs Road Drainage Improvements
2.	County: Williamson
3.	Stream Basin: San Gabriel River Basin
4.	Groundwater Conservation District (If applicable):
5.	Edwards Aquifer Zone:
	Recharge Zone Transition Zone
6.	Plan Type:
	WPAP AST SCS UST Modification Exception Request

/.	Customer (Applicant):	
	Contact Person: Adam D. Boatright Entity: Williamson County Mailing Address: 701 Main St City, State: Georgetown Telephone: 512-943-3374 Email Address: adam.boatright@wilco.org	Zip: <u>78626</u> FAX:
8.	Agent/Representative (If any):	
	Contact Person: Anthony Serda Entity: STV, Inc Mailing Address: 13809 Research Blvd, Suite 300 City, State: Austin, Texas Telephone: 512-340-9800 Email Address: anthony.serda@stvinc.com	Zip: <u>78750</u> FAX:
9.	Project Location:	
	 ☐ The project site is located inside the city limits ☐ The project site is located outside the city limit jurisdiction) of ☐ The project site is not located within any city's 	s but inside the ETJ (extra-territorial
10.	The location of the project site is described bel detail and clarity so that the TCEQ's Regional suboundaries for a field investigation.	
	Pond Springs Rd from Roxie Dr to 300' S of Tur	tle Rock Rd
11.	Attachment A – Road Map. A road map show project site is attached. The project location are the map.	_
12.	Attachment B - USGS / Edwards Recharge Zon USGS Quadrangle Map (Scale: 1" = 2000') of th The map(s) clearly show:	
	 ☑ Project site boundaries. ☑ USGS Quadrangle Name(s). ☑ Boundaries of the Recharge Zone (and Trange) ☑ Drainage path from the project site to the Interpretation 	
13.	The TCEQ must be able to inspect the project Sufficient survey staking is provided on the pro the boundaries and alignment of the regulated features noted in the Geologic Assessment.	ject to allow TCEQ regional staff to locate
	Survey staking will be completed by this date:	

14. Attachment C – Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
 Area of the site ○ Offsite areas ○ Impervious cover ○ Permanent BMP(s) ○ Proposed site use ○ Site history ○ Previous development ○ Area(s) to be demolished
15. Existing project site conditions are noted below:
 □ Existing commercial site □ Existing industrial site □ Existing residential site ○ Existing paved and/or unpaved roads □ Undeveloped (Cleared) □ Undeveloped (Undisturbed/Uncleared) □ Other:
Prohibited Activities
16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
 Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
(2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
(3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
(4) The use of sewage holding tanks as parts of organized collection systems; and
(5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
(6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.
17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
(1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);

(2) Land disposal of Class I wastes, as defined in 30 TAC $\S335.1$; and


(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

18.	8. The fee for the plan(s) is based on:	
	 □ For a Water Pollution Abatement Plan or Modwhere regulated activities will occur. □ For an Organized Sewage Collection System Plan ot Goodage of all collection system lines. □ For a UST Facility Plan or Modification or an Anumber of tanks or piping systems. □ A request for an exception to any substantive protection of water quality. □ A request for an extension to a previously approach of the protection of the protection of the protection of the protection to a previously approach of the protection of the protection of the protection to a previously approach of the protection of the protection of the protection to a previously approach of the protection of	lan or Modification, the total linear ST Facility Plan or Modification, the total portion of the regulations related to the
19.	9. Application fees are due and payable at the tifee is not submitted, the TCEQ is not required correct fee is submitted. Both the fee and the sent to the Commission's:	to consider the application until the
	☐ TCEQ cashier☐ Austin Regional Office (for projects in Hay☐ San Antonio Regional Office (for projects Uvalde Counties)	
20.	O. Submit one (1) original and one (1) copy of the needed for each affected incorporated city, go county in which the project will be located. To copies to these jurisdictions. The copies mus office.	roundwater conservation district, and he TCEQ will distribute the additional
21.	 No person shall commence any regulated act Plan(s) for the activity has been filed with and 	




Attachment A – Road Map





Attachment B – USGS / Edwards Recharge Zone Map





Attachment C – Project Description

Williamson County has retained CP&Y, Inc. (CP&Y) to provide plans, specifications and estimates for the construction of drainage improvements designed to improve drainage conditions along Pond Springs Road. The project includes the construction of a storm drain trunk line along a portion of Roxie Drive and Pond Springs Road. The goal of the project will be to reduce the frequency and severity of ponding along the west side of Pond Springs Road, from just south of Roxie Road to about 300 feet south of Turtle Rock Road, that has been reported in the past by adjacent business owners.

The project includes the construction of a storm drain trunk line along a portion of Roxie Drive and Pond Springs Road. Proposed improvements will also include the addition of three curb and gutter inlets along the portion of Roxie Drive near the Pond Springs intersection. The goal of the project will be to reduce the frequency and severity of ponding along the west side of Pond Springs Road and Roxie Drive, from just south of Roxie Road to about 300 feet south of Turtle Rock Road, that has been reported in the past by adjacent business owners.

The total project area is approximately 2.28 acres. The current uses of adjacent areas along Pond Springs Road and Roxie Drive include mostly commercial, industrial, and office uses as well as a few single family and multi-family areas. The project is located within the City of Austin; therefore, the project has been designed per City of Austin design requirements. No additional impervious cover or permanent BMP's are being added as a result of this project.

The project overall does not propose changes to impervious cover. But there are some minor adjustments which overall decrease the impervious cover and are summarized in the table below. Of the 3 inlets, 1 of them adds impervious cover. However, throttling of the existing driveway decreases impervious cover and more than offsets for the increase in impervious cover from the inlets. All construction work is within previously disturbed land with existing water lines, culverts, and roadway improvements. No work will be performed in undisturbed areas.

Source of IC change	Change in IC
1 out of 3 inlets not in existing pavement	+39 sqft
Removal of pavement due to driveway reconstruction	-337 sqft
Total Change	-298 sqft

SECTION 3 Geologic Assessment Exception



Waiver for Geologic Assessment

No Geologic Assessment is included with this exception request package. James Slone, Geoscientist at TCEQ, confirmed that it is not required due to the prior development of the area. The project proposes adding storm sewer to existing roadway, and all work is within previously disturbed land with existing water lines, culverts, and roadway improvements. No work is in undisturbed areas. The correspondence between Bradley McConnon (STV) and James Slone (TCEQ) is attached below.

From: James Slone <james.slone@tceq.texas.gov>

Sent: Wednesday, June 5, 2024 7:46 AM

To: Bradley McConnon

Cc: Serda, Anthony; Wienke, Stephanie

Subject: RE: Wavier for Geologic Assessment- WPAP Exception

This e-mail is from outside STV

Bradley,

You can submit the plan without the Geologic Assessment due to the prior development of the area. Please retain this email for your records and attached it to the application when you submit it. Bo

James "Bo" Slone, P.G. Geoscientist Edwards Aquifer Protection Program Texas Commission on Environmental Quality (512) 239-6994

From: Bradley McConnon < Bradley. McConnon@stvinc.com>

Sent: Tuesday, June 4, 2024 3:15 PM

To: James Slone < <u>james.slone@tceq.texas.gov</u>>

Cc: Serda, Anthony <Anthony.Serda@stvinc.com>; Wienke, Stephanie <Stephanie.Wienke@stvinc.com>

Subject: RE: Wavier for Geologic Assessment- WPAP Exception

Good afternoon James,

Thanks for taking a quick look at this! Attached is a location map and a .kmz of the project. If you would like a bit more information, I can send you the drainage plan & profile sheets.

There are existing concrete lined ditches currently handling the flow, but they are insufficient and cause localized flooding. This project is adding a new trunkline and should help alleviate some of the flooding.

Bradley McConnon, P.E.

Design Engineer, Transportation Texas/Mountain Region (o) 512.340.9800 | (c) 281.795.1751 bradley.mcconnon@stvinc.com | stvinc.com



From: James Slone <james.slone@tceq.texas.gov>

Sent: Monday, June 3, 2024 9:35 AM

To: Bradley McConnon < <u>Bradley.McConnon@stvinc.com</u>>

Cc: Serda, Anthony < Anthony. Serda@stvinc.com>; Wienke, Stephanie < Stephanie. Wienke@stvinc.com>

Subject: RE: Wavier for Geologic Assessment- WPAP Exception

This e-mail is from outside STV

Bradley,

Sorry I have not responded. I was out last week and it must have fallen off of my radar previously. Can you give me a location with maybe a draft drawing of the project? Thanks,

Во

From: Bradley McConnon < Bradley. McConnon@stvinc.com>

Sent: Tuesday, May 28, 2024 8:46 AM

To: James Slone <james.slone@tceq.texas.gov>

Cc: Serda, Anthony < Anthony.Serda@stvinc.com; Wienke, Stephanie < Stephanie.Wienke@stvinc.com

Subject: RE: Wavier for Geologic Assessment- WPAP Exception

Good morning Mr. Slone,

I am following up on my request from two weeks ago about a geologic assessment waiver for a project. This might help- on this project, we are only adding some storm sewer to an existing roadway- all work is within previously disturbed land with existing water lines, culverts and roadway improvements. No work is in undisturbed areas.

Thank you!

Bradley McConnon, P.E.

Design Engineer, Transportation Texas/Mountain Region (o) 512.340.9800 | (c) 281.795.1751 bradley.mcconnon@stvinc.com | stvinc.com



From: Bradley McConnon

Sent: Tuesday, May 14, 2024 3:33 PM **To:** <u>James.Slone@tceq.texas.gov</u>

Cc: Serda, Anthony < Anthony. Serda@stvinc.com>; Wienke, Stephanie < Stephanie. Wienke@stvinc.com>

Subject: Wavier for Geologic Assessment- WPAP Exception

Good afternoon Mr. Slone,

My name is Bradley McConnon and I am an engineer with STV, Inc. I received your information from the EAPP staff on call just now. It's nice to make your acquaintance!

I am the lead for a drainage improvements project for Williamson County and we are preparing to submit a WPAP Exception for the project (there is no change in impervious cover). The WPAP exception criteria on the TCEQ website indicates that a geologic assessment is required (although not required for a CZP exception), but I'm not sure it would have any bearing on our project. The staff member indicated that you would be able to waive the requirement if you thought a geologic assessment had no bearing on the project.

To that end, I would like to know what you might need to make a determination on whether a geologic assessment is prudent for the project? Thank you!

Bradley McConnon, P.E.

Design Engineer, Transportation Texas/Mountain Region (o) 512.340.9800 | (c) 281.795.1751 bradley.mcconnon@stvinc.com | stvinc.com



Please consider the environment before printing this e-mail.

The information contained in this electronic message is intended only for the use of the individual or entity to which it is addressed and may contain information that is privileged, confidential and exempt from disclosure under applicable law. If the reader of this message is not the intended recipient, you are informed that any dissemination, copying or disclosure of the material contained herein, in whole or in part, is strictly prohibited. If you have received this transmission in error, please notify STV and purge this message.

SECTION 4

Recharge and Transition Zone Exception Request TCEQ-0628

Recharge and Transition Zone Exception Request Form

Texas Commission on Environmental Quality

30 TAC §213.9 Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This Recharge and Transition Zone Exception Request Form is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Anthony Serda

Date: 5/29/2025

Signature of Customer/Agent:

Regulated Entity Name: ____

Exception Request

- 1. Attachment A Nature of Exception. A narrative description of the nature of each exception requested is attached. All provisions of 30 TAC §213 Subchapter A for which an exception is being requested have been identified in the description.
- 2. Attachment B Documentation of Equivalent Water Quality Protection. Documentation demonstrating equivalent water quality protection for the Edwards Aquifer is attached.

Administrative Information

- 3. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional
- 4. The applicant understands that no exception will be granted for a prohibited activity in Chapter 213.
- 5. The applicant understands that prior approval under this section must be obtained from the executive director for the exception to be authorized.



Attachment A – Nature of Exception

This project is located within the Edwards Aquifer Recharge Zone in Williamson County. We request an exception from submitting a water pollution abatement plan because the site has been developed before, and the project has an overall decrease in impervious cover from existing to proposed conditions. None of the prohibited activities listed in 30 TAC Rule 213.8 of Subchapter A are proposed for this project.



Attachment B – Documentation of Equivalent Water Quality Protection

Water quality will be protected in the design and construction of this project. Regarding impervious cover (IC), three (3) curb and gutter inlets will be added along Roxie Drive. Two (2) of the inlets will be configured on existing pavement, and one (1) inlet will add roughly 39 sqft of IC. This addition of IC is offset by roughly 337 sqft of driveway pavement removal, resulting in an insignificant net decrease of 298 sqft of IC. All other work will be completed on existing previously developed roadway. Because the project does not increase IC beyond 8,000 sqft, no water quality was required for the City of Austin.

All required water quality protection measures will be observed during construction. For more detail please see the Environmental Sheets, Storm Water Pollution Prevention Plan, and Erosion and Sedimentation Control Plan sheets provided in **Attachment D – Temporary Best Management Practices and Measures** of Section 3 – Temporary Stormwater.

Section (

SECTION 5

Temporary Stormwater Section *TCEQ-0602*

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Aquiter. This Temporary Stormwater Section is hereby submitted for TCEQ review at
executive director approval. The application was prepared by:
Print Name of Customer/Agent: Anthony Serda
Date: <u>5/29/2</u> 025
Signature of Customer/Agent:

Regulated Entity Name: Pond Springs Road Drainage Improvements

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1.	Fuels for construction equipment and hazardous substances which will be used during construction:
	The following fuels and/or hazardous substances will be stored on the site:
	These fuels and/or hazardous substances will be stored in:
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project. 	
	Evels and hazardous substances will not be stored on the site.	
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.	
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.	
1.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.	
Sequence of Construction		
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.	
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented. 	
ô.	Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: San Gabriel River Basin	
_	D / // / / / / / / / / / / / / / / / /	

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. 🔀	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	 ☐ Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature. ☐ There will be no temporary sealing of naturally-occurring sensitive features on the
	site.
9.	Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. 🗌	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
\boxtimes	N/A
12. 🔀	Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. 🔀	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. 🔀	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. 🔀	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. 🔀	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



Attachment A – Spill Response Actions

Should an accidental release occur, it will be immediately contained by earthen dikes, berms or other appropriate measures. Free liquids will be stabilized promptly using bulking agents, absorbent pads, booms, soil or other appropriate material. Once no free liquids are present in the containment area, the released material will be picked up mechanically or by personnel wearing proper protective equipment and stored in 55-gallon steel drums or on plastic sheeting. Released material will be covered to prevent contact with stormwater. Stormwater runoff will be diverted around the stored material if necessary. Traffic will be routed around and away from any spill are to avoid spreading the spilled material to other areas. Only qualified licensed personnel will be involved with the actual handling and removal of the spilled material. The Contractor is required to remediate any spills, and to immediately report spills (including sanitary sewer discharge) of reportable quantities to the National Response Center at (800) 424-8802, and one of the following: State Emergency Response Center (800) 832-8224 (if after hours), or to the TCEQ Regional Office (512) 339-2929 (if during business hours).

Spills shall be reported within 24 hours unless other regulations require more expedient notification.

More information on spill rules and appropriate responses is available on the TCEQ website at: http://www.tceq.state.tx.us/response/spills/spills.html



Attachment B – Potential Sources of Contamination

Potential sources of contamination include:

- Soil disturbed and mobilized during excavation and grading operations
- Hydrocarbons and fuels required to service and operate the construction equipment
 - o Gasoline
 - o Diesel
 - o Oil
 - o Antifreeze
- Materials and liquids used to conduct paving operations
 - o Asphalt
 - o Emulsions
 - o Aggregate
 - o Cement
- Various paints, solvents, adhesives, glue
- Concrete washout areas
- Fertilizers
- Dewatering activities near water bodies and/or near groundwater



Attachment C – Sequence of Major Activities

The General Contractor will ultimately be responsible for the sequence of construction for each project; however, it is anticipated that the general sequence of activities will be as follows:

- 1. Install temporary stormwater BMPs (Sediment Control Fence, Erosion Control Logs, Rock Filter Dam) per erosion and sedimentation control plan.
- 2. Base bid work- Construct roadway (i.e. construct detours, drainage construction, paving), storm sewer, and utilities, making minor adjustments to silt fencing and erosion control logs as needed; apply temporary seeding as needed.
- 3. Striping/pavement marking applications.
- 4. Site cleanup.
- 5. Place permanent seeding/sodding in areas where grading is completed.
- 6. Removal of remaining temporary erosion control devices.

Appropriately sized erosion control measures will be utilized until vegetation is reestablished. See the Erosion plan sections of the attached construction plans for specific erosion control measures.



Attachment D – Temporary Best Management Practices and Measures

At the beginning of the construction phase, rock filter dams, sediment control fence, and inlet protection will be installed at surface water discharge points to reduce the potential for erosion. All temporary BMPs will remain until the end of construction.

Offsite water flows onto the project and through these temporary BMPs, preventing pollution of surface water, groundwater or stormwater.

On-site water flows into and through the same temporary BMPs, preventing pollution of surface water, groundwater or stormwater.

By slowing down the offsite and on-site water, pollutants will have time to settle to the bottom of the temporary BMPs, resulting in proper contaminant removal before discharged water enters surface streams, sensitive features or the Edwards aquifer.

Existing drainage paths will not be affected by the temporary BMPs.

See the attached Stormwater Pollution Prevention Plan (SW3P) for more information regarding general site data, best management practices, and other requirements and practices that pertain to the temporary best management practices described above. The locations of temporary BMPs are shown on the attached Erosion Control Plan sheets. Standard details show information relevant to BMP installation and maintenance.

INDEX OF SHEETS

SHEET NO. DESCRIPTION TITLE SHEET INDEX OF SHEETS

WILLIAMSON COUNTY

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS

CORRECTIONS RECORD

NO	DESCRIPTION	ву	REVISE (R) ADD (D) VOID (V) SHEET NO.'s	TOTAL # SHEETS IN PLAN SET	NET CHANGE IMPV. COVER (sq.ft.)	TOTAL SITE IMPV. COVER (sq.ft.) %	CITY OF AUSTIN APPROVAL / DATE

WAIVER REQUESTS

THE 100 YEAR FLOODPLAIN IS CONTAINED WITHIN DRAINAGE EASEMENT SHOWN A PORTION OF THIS TRACT IS WITHIN THE BOUNDARIES OF THE 100 YEAR

FLOODPLAIN OF ANY WATERWAY THAT IS WITHIN THE LIMITS OF STUDY OF THE FEDERAL FLOOD INSURANCE ADMINISTRATION (FIRM), PER FEMA MAP

NUMBER 4849100610F DATED DECEMBER 20, 2019.
REQUIRED SIGNS SHALL BE PLACED IN ACCORDANCE WITH STANDARD SHEETS
BC(1)-21 THRU BC(12)-21 AND THE "TEXAS MANUAL ON UNIFORM TRAFFIC
CONTROL DEVICES.

REASON FOR WAIVER REQUEST

PRECINCT NUMBER 1

Williamson County Project No. 25IFB

NET LENGTH OF ROADWAY = 1237.65 FT (0.234 MILES) NET LENGTH OF PROJECT = 1237.65 FT (0.234 MILES)

SUBMISSION DATE: AUGUST 22,2024

FROM 13266 1/2 POND SPRINGS RD TO 13174 1/2 POND SPRINGS RD

LIMITS: POND SPRINGS RD FROM ROXIE DR TO LAKE CREEK TRIBUTARY 3 FOR THE CONSTRUCTION OF DRAINAGE IMPROVEMENTS CONSISTING OF STRUCTURES AND STREET REPAIRS



APPROVED BY: WILLIAMSON COUNTY

HONORABLE STEVEN SNELL. WILLIAMSON COUNTY JUDGE

APPROVED BY:

WILLIAMSON COUNTY

DATE COMMISSIONER TERRY COOK WILLIAMSON COUNTY COMMISSIONER PRECINCT 1

DATE

DATE

DATE

DATE

DATE

DATE

DATE

APPROVED BY: HNTB CORPORATION

CHRISTEN ESCHBERGER, PE ROAD BOND MANAGEMENT TEAM

AUSTIN TRANSPORTATION DEPARTMENT

AUSTIN FIRE DEPARTMENT

@ 2025 Williamson County, Texas All rights reserved.

STA. 53+35.30

BEGIN PROJECT

€ PONDSPRINGS

AUSTIN WATER


END PROJECT ♠ PONDSPRINGS STA. 64+75.13

CONTROL DEVICES.
THIS PROJECT IS LOCATED WITHIN THE LAKE CREEK WATERSHED CLASSIFIED AS SUBURBAN.
THIS PROJECT IS SUBJECT TO THE VOID AND WATER FLOW MITIGATION RULE
(COA ECM 1.12.0 AND COA ITEM NO. 658S OF THE SSM) PROVISION THAT
ALL TRENCHING/DISTURBANCE GREATER THAN 5 FEET DEEP MUST BE INSPECTED

ALL TRENCHING/DISTURBANCE GREATER THAN 5 FEET DEEP MUST BE INSPECTED BY A GEOLOGIST (TEXAS P.G.) OR A GEOLOGIST'S REPRESENTATIVE. THIS SITE IS LOCATED OVER THE EDWARDS AQUIFER RECHARGE ZONE.

IF AT ANY TIME DURING CONSTRUCTION OF THIS PROJECT AN UNDERGROUND STORAGE TANK (UST) IS FOUND, CONSTRUCTION IN THAT AREA MUST STOP UNTIL A CITY OF AUSTIN UST CONSTRUCTION PERMIT IS APPLIED FOR AND APPROVED. ANY UST REMOVAL WORK MUST BE CONDUCTED BY A UST CONTRACTOR THAT IS REGISTERED WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TOEQ). CONTACT ELIZABETH SIMMONS AT ELIZABETH. SIMMONS@AUSTINTEXAS.GOV IF YOU HAVE ANY QUESTIONS. (COA TITLE 6)

APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN INDICATES COMPLIANCE WITH APPLICABLE CITY BEGUN ATTORS ONLY APPROVAL BY OTHER COVERNMENTAL ENTITIE APPROVAL OF THESE PLANS BY THE CITY OF AUSTIN INDICATES COMPETANCE WITH
APPLICABLE CITY REGULATIONS ONLY. APPROVAL BY OTHER GOVERNMENTAL ENTITIES
MAY BE REQUIRED PRIOR TO THE START OF CONSTRUCTION. THE APPLICANT IS RESPONSIBLE FOR DETERMINING WHAT ADDITIONAL APPROVALS MAY BE NECESSARY.



COA AND TXDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES ADOPTED ON SEPTEMBER 1, 2024 AND ALL APPLICABLE SPECIAL PROVISIONS AND SPECIAL SPECIFICATIONS AS INDICATED IN THE BID DOCUMENTS SHALL GOVERN ON THIS PROJECT.

GRID NUMBERS: C18, C19, D18, E17, E18 MAPSCO NUMBERS: 612W-X, 642B-D, 642H, 643E, 643J

MAJOR COLLECTOR STREET ADT (CURRENT) ROADWAY 8.194 (2020) DHV (CURRENT) 615 (2020) DIRECTIONAL DISTRIBUTION (D)

APPLICATION IS REVIEWED FOR CODE

COMPLIANCE BY CITY ENGINEERS.

62%

"RELEASE OF THIS APPLICATION DOES NOT CONSTITU VERIFICATION OF ALL DATA, INFORMATION AND CALCULATIONS SUPPLIED BY THE APPLICANT. THE EN OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY AND ADEQUACY OF HIS/HER SUBMITTAL, WHETHER OR NOT THE

40 MPH

861 (2040)

ADT (DESIGN YEAR)

DHV (DESIGN YEAR)

11,472 (2040)

WATER PRESSURE ZONE: TYP. LOCATION MIN. MAX. 36" WATER MAIN 24" WATER MAIN

EXCEPTIONS: ___ EQUATIONS: NONE NONE RAILROAD CROSSINGS:___ LAKE CREEK WATERSHED: __ AREA OF DISTURBANCE: 0.32

PREPARED BY: ANTHONY

4/24/2025 DATE

WOODS POND

SURVEYOR:

ENGINEER:

STV, INC.

AUSTIN, TX 78750

FAX: (512) 349-

PHONE: (512) 349-0700

13809 RESEARCH BOULEVARD, SUITE 300 AUSTIN, TX 78750 TBPE REGISTRATION NO. F - 1741

13809 RESEARCH BOULEVARD, SUITE 300

TBPE REGISTRATION NO. F - 1741

APPROVED BY:

DEVELOPMENT SERVICES DEPARTMENT

SITE PLAN / DEVELOPMENT PERMIT NUMBER

SITE PLAN APPROVAL SHEET_1_0F_124 FILE NUMBER: SP-2024-0324D APPLICATION DATE: AUGUST 22,2024 APPROVED BY COMMISSION ON: UNDER SECTION 112_OF CHAPTER 25-5 OF THE CITY OF EXPIRATION DATE (LDC 15-5-81)_ PROJECT EXPIRATION DATE (ORD. #970905-A) __ ___ CASE MANAGER: ALYSE RAMIREZ

DEVELOPMENT SERVICES DEPARTMENT RELEASED FOR GENERAL COMPLIANCE REVISION 1 REVISION 2

CORRECTION 2 Final Plat must be recorded by the project expiration date, if applicable. Subsequent site plans which do not comply with the Code current at the time of filling, and all required building permits and /or a notice of construction (if a building permit is not required) must also be approved prior to the project expiration date.

PERCENT TRUCKS (1 3.2%	-)
OT CONSTITUTE A N AND ANT. THE ENGINEER R THE ACY OF HE	ANTHONY J. SERDA 106300 CENSO

CHASE BANK BUILDING/TOWER OF THE HILLS 13809 RESEARCH BOULEVARD, SUITE 300 AUSTIN, TX 78750

CRITERIA MANUAL CODE REFERENCE

SP-2024-0324D

```
SHEET NO.
                    DESCRIPTION
                    VOLUME_I
                    GENERAL
                    TITLE SHEET
                    INDEX OF SHEETS
                    GENERAL NOTES
                    TREE LIST
                    AUSTIN ENERGY GENERAL NOTES
                    PROJECT LAYOUT
                    TYPICAL SECTIONS
8 - 10
11 - 12
                    HORIZONTAL ALIGNMENT DATA
                    SUMMARY OF DRAINAGE QUANTITIES
13
                    SUMMARY OF ROADWAY & MISC QUANTITIES
                    ROADWAY
15 - 18
                    ROADWAY PLAN
                    ROADWAY DETAILS
19 - 20
                * COA ROADWAY STANDARD DETAILS
                    DRAINAGE
                   DRAINAGE AREA MAP EXTERIOR (EXISTING)
DRAINAGE AREA MAP EXTERIOR (PROPOSED)
DRAINAGE AREA MAP FUTURE INLETS EXISTING CONDITIONS
21
22
23
                   DRAINAGE AREA MAP PROPOSED INLETS PROPOSED CONDITIONS DRAINAGE AREA CALCULATIONS EXISTING & PROPOSED
24
25
26
                    HYDRAULIC DATA SHEET
27 -
                    DRAINAGE PLAN AND PROFILE
31
                    DRAINAGE PROFILES
32
                    CULVERT L-PS06 EXIST PARALLEL WINGWALL CONNECTION DETAIL
33
                    JUNCTION BOX DETAILS 16ft x8ft
                    DRAINAGE DETAILS
34
35
36
                * SCP-MD
                   SCP-5
                   PJB
37
                   PBGC
                * PDD
40 - 41
                   PSL
42 - 43
                   SETB-CD
44 - 48
                   COA DRAINAGE STANDARD DETAILS
                    TRAFFIC ITEMS
                    SIGNING & PAVEMENT MARKING LAYOUT
49 - 52
                    TRAFFIC DETAILS
                   PM(1)-22 THRU PM(3)-22
53 - 55
                   D&OM(1)-20 THRU D&OM(4)-20 TRAFFIC DETAILS
56 - 59
60
                    ENVIRONMENTAL SHEETS
61
                    STORM WATER POLLUTION PREVENTION PLAN
62
63
                    WATER POLLUTION ABATEMENT PLAN GENERAL NOTES
                    ENVIRONMENTAL CRITERIA MANUAL APPENDIX Q2 TABLE
64
65
                    SLOPE MAP
                    EROSION HAZARD ZONE ANALYSIS
66
                    EROSION AND SEDIMENTATION CONTROL PLAN
67 - 69
                    ENVIRONMENTAL DETAILS
                   EC(1)-16
EC(2)-16
70
71
72 - 74
                   EC(9)-16
75 - 77
                   ENVIRONMENTAL STANDARD DETAILS
                    CROSS SECTIONS
78 - 92
                    CROSS SECTIONS (FOR CONTRACTORS INFORMATION ONLY)
                    UTILITY PLAN
                    TITLE SHEET
93
                    AUSTIN WATER UTILITIY GENERAL NOTES
94
                    WATERLINE SUMMARY OF QUANTITIES
95
                    WATERLINE PLANS
96 - 100
```

UTILITY DETAILS


101 - 103

THIS NOTE IS BEING PLACED ON THE PLAN SET IN THE ABSENCE OF A TEMPORARY TRAFFIC CONTROL PLAN (TCP) WITH THE FULL UNDERSTANDING THAT AN ENGINEERED TCP SHALL BE REVIEWED AND APPROVED BY THE RIGHT OF WAY MANAGEMENT DIVISION. FURTHERMORE, A TCP SHALL BE SUBMITTED TO THE TCP PORTAL FOR REVIEW A MINIMUM OF 6 WEEKS PRIOR TO THE START OF CONSTRUCTION. THE APPLICANT/PROJECT REPRESENTATIVE FURTHER RECOGNIZES THAT A TCP REVIEW FEE IS REQUIRED FOR THE INITIAL REVIEW AND ALL RE—REVIEWS, AS PRESCRIBED BY THE MOST CURRENT VERSION OF THE CITY?S FEE ORDINANCE.



CITY APPROVAL

THE STANDARD DRAWINGS SHOWN IN THE INDEX OF SHEETS AND IDENTIFIED HEREIN BY THE SYMBOL * HAVE BEEN SELECTED BY ME OR UNDER MY DIRECT SUPERVISION AS BEING APPLICABLE TO THIS PROJECT.



CUEET 4 OF

 Drawn:
 MRR
 Designed:
 MRR
 STATE
 COUNTY
 SHEET NO.

 Checked:
 AJS
 Checked:
 AJS
 TEXAS
 WILLIAMSON
 2
 OF 103

2. THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE ENVIRONMENTAL CRITERIA MANUAL AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. THE COA ESC PLAN SHALL BE CONSULTED AND USED AS THE BASIS FOR A TPDES REQUIRED SWPPP. IF A SWPPP IS REQUIRED, IT SHALL BE AVAILABLE FOR REVIEW BY THE CITY OF AUSTIN ENVIRONMENTAL INSPECTOR AT ALL TIMES DURING CONSTRUCTION, INCLUDING AT THE PRE-CONSTRUCTION MEETING. THE CHECKLIST BELOW CONTAINS THE BASIC ELEMENTS THAT SHALL BE REVIEWED FOR PERMIT APPROVAL BY COA EV PLAN REVIEWERS AS WELL AS COA EV INSPECTORS.

PLAN SHEETS SUBMITTED TO THE CITY OF AUSTIN MUST SHOW THE FOLLOWING:

> DIRECTION OF FLOW DURING GRADING OPERATIONS.

> LOCATION, DESCRIPTION, AND CALCULATIONS FOR OFF-SITE FLOW DIVERSION STRUCTURES.

> AREAS THAT WILL NOT BE DISTURBED; NATURAL FEATURES TO BE PRESERVED. > DELINEATION OF CONTRIBUTING DRAINAGE AREA TO EACH PROPOSED BMP (E.G., SILT FENCE, SEDIMENT BASIN, ETC.).

> LOCATION AND TYPE OF E&S BMPS FOR EACH PHASE OF DISTURBANCE.

> CALCULATIONS FOR BMPS AS REQUIRED.

> LOCATION AND DESCRIPTION OF TEMPORARY STABILIZATION MEASURES.

> LOCATION OF ON-SITE SPOILS, DESCRIPTION OF HANDLING AND DISPOSAL OF BORROW MATERIALS, AND DESCRIPTION OF ON-SITE PERMANENT SPOILS DISPOSAL AREAS, INCLUDING SIZE, DEPTH OF FILL AND REVEGETATION PROCEDURES.

> DESCRIBE SEQUENCE OF CONSTRUCTION AS IT PERTAINS TO ESC INCLUDING THE FOLLOWING ELEMENTS:

INSTALLATION SEQUENCE OF CONTROLS (E.G. PERIMETER CONTROLS, THEN SEDIMENT BASINS, THEN TEMPORARY STABILIZATION, THEN PERMANENT, ETC.)

2. PROJECT PHASING IF REQUIRED (LOC GREATER THAN 25 ACRES)

3. SEQUENCE OF GRADING OPERATIONS AND NOTATION OF TEMPORARY STABILIZATION MEASURES TO BE USED

4. SCHEDULE FOR CONVERTING TEMPORARY BASINS TO PERMANENT WQ CONTROLS

5. SCHEDULE FOR REMOVAL OF TEMPORARY CONTROLS

6. ANTICIPATED MAINTENANCE SCHEDULE FOR TEMPORARY CONTROLS $\boldsymbol{\mathsf{-}}$ Categorize each BMP under one of the following areas of BMF activity as described below:

3.1 MINIMIZE DISTURBED AREA AND PROTECT NATURAL FEATURES AND SOIL

3.2 CONTROL STORMWATER FLOWING ONTO AND THROUGH THE PROJECT

3.3 STABILIZE SOILS

3.4 PROTECT SLOPES

3.5 PROTECT STORM DRAIN INLETS

3.6 ESTABLISH PERIMETER CONTROLS AND SEDIMENT BARRIERS

3.7 RETAIN SEDIMENT ON-SITE AND CONTROL DEWATERING PRACTICES

3.8 ESTABLISH STABILIZED CONSTRUCTION EXITS

3.9 ANY ADDITIONAL BMPS

ANSIB. ANSIB

- NOTE THE LOCATION OF EACH BMP ON YOUR SITE MAP(S).

- for any structural BMPs, you should provide design specifications and details and refer to them.

- FOR MORE INFORMATION, SEE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL 1.4.

3. THE PLACEMENT OF TREE/NATURAL AREA PROTECTIVE FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AUSTIN STANDARD NOTES FOR TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL AREA PROTECTION AND THE APPROVED GRADING/TREE AND NATURAL

AREA PLAN.

4. A PRE—CONSTRUCTION CONFERENCE SHALL BE HELD ON—SITE WITH THE CONTRACTOR, DESIGN ENGINEER/PERMIT APPLICANT AND ENVIRONMENTAL INSPECTOR AFTER INSTALLATION OF THE EROSION/SEDIMENTATION CONTROLS, TREE/NATURAL AREA PROTECTION MEASURES AND "PRE—CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE) PRIOR TO BEGINNING ANY SITE PREPARATION WORK. THE OWNER OR OWNER'S REPRESENTATIVE SHALL NOTIFY THE DEVELOPMENT SERVICES DEPARTMENT, 512—974—2278 OR BY EMAIL AT ENVIRONMENTAL INSPECTIONS@AUSTINTEXAS.GOV, AT LEAST THREE DAYS PRIOR TO THE MEETING DATE. COA APPROVED ESC PLAN AND TPDES SWPPP (IF REQUIRED) SHOULD BE REVIEWED BY COA EV INSPECTOR AT THIS TIME.

ANY MAJOR VARIATION IN MATERIALS OR LOCATIONS OF CONTROLS OR FENCES FROM THOSE SHOWN ON THE APPROVED PLANS WILL REQUIRE A REVISION AND MUST BE APPROVED BY THE REVIEWING ENGINEER, ENVIRONMENTAL SPECIALIST OR CITY ARBORIST AS APPROPRIATE. MAJOR REVISIONS MUST BE APPROVED BY AUTHORIZED COA STAFF, MINOR CHANGES TO BE MADE AS FIELD REVISIONS TO THE EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE ENVIRONMENTAL INSPECTOR DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES.

CORRECT CONTROL INADEQUACIES.

6. THE CONTRACTOR IS REQUIRED TO PROVIDE A CERTIFIED INSPECTOR THAT IS EITHER A LICENSED ENGINEER (OR PERSON DIRECTLY SUPERVISED BY THE LICENSED ENGINEER) OR CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC OR CPESC — IT), CERTIFIED EROSION, SEDIMENT AND STORMWATER — INSPECTOR (CESSWI OR CESSWI — IT) OR CERTIFIED INSPECTOR OF SEDIMENTATION AND EROSION CONTROLS (CISEC OR CISEC — IT) CERTIFICATION TO INSPECT THE CONTROLS AND FENCES AT WEEKLY OR BI—WEEKLY INTERVALS AND AFTER ONE—HALF (½) INCH OR GREATER RAINFALL EVENTS TO INSURE THAT THEY ARE FUNCTIONING PROPERTY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION TO CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES OR ONE—THIRD (?) OF THE INSTALLED HEIGHT OF THE CONTROL WHICHEVER IS LESS.

7. PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED, ACCUMULATED SEDIMENT REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES.

8. ALL WORK MUST STOP IF A VOID IN THE ROCK SUBSTRATE IS DISCOVERED WHICH IS; ONE SQUARE FOOT IN TOTAL AREA; BLOWS AIR FROM WITHIN THE SUBSTRATE AND/OR CONSISTENTLY RECEIVES WATER DURING ANY RAIN EVENT. AT THIS TIME IT IS THE RESPONSIBILITY OF THE PROJECT MANAGER TO IMMEDIATELY CONTACT A CITY OF AUSTIN ENVIRONMENTAL INSPECTOR FOR FURTHER INVESTIGATION. IN ADDITION, IF THE PROJECT SITE IS LOCATED WITHIN THE EDWARDS AQUIFER, THE PROJECT MANAGER MUST NOTIFY THE TRAVIS COUNTY BALCONES CANYONLANDS CONSERVATION PRESERVE (BCCP) BY EMAIL AT BCCP®TRAVISCOUNTYTX.GOV. CONSTRUCTION ACTIVITIES WITHIN 50 FEET OF THE VOID MUST STOP.

9. TEMPORARY AND PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED BELOW:

ALL DISTURBED AREAS TO BE REVEGETATED ARE REQUIRED TO PLACE A MINIMUM OF SIX (6) INCHES OF TOPSOIL ISEE STANDARD SPECIFICATION ITEM NO. 601S.3(A)]. DO NOT ADD TOPSOIL WITHIN THE CRITICAL ROOT ZONE OF EXISTING TREES.

TOPSOIL SALVAGED FROM THE EXISTING SITE IS ENCOURAGED FOR USE, BUT IT SHOULD MEET THE STANDARDS SET FORTH IN 601S.

AN OWNER/ENGINEER MAY PROPOSE USE OF ONSITE SALVAGED TOPSOIL WHICH DOES NOT MEET THE CRITERIA OF STANDARD SPECIFICATION 601S BY PROVIDING A SOIL ANALYSIS AND A WRITTEN STATEMENT FROM A QUALIFIED PROFESSIONAL IN SOILS, LANDSCAPE ARCHITECTURE, OR AGRONOMY INDICATING THE ONSITE TOPSOIL WILL PROVIDE AN EQUIVALENT GROWTH MEDIA AND SPECIFYING WHAT, IF ANY, SOIL AMENDMENTS ARE REQUIRED.

SOIL AMENDMENTS SHALL BE WORKED INTO THE EXISTING ONSITE TOPSOIL WITH A DISC OR TILLER TO CREATE A WELL-BLENDED MATERIAL.

THE VEGETATIVE STABILIZATION OF AREAS DISTURBED BY CONSTRUCTION SHALL BE AS FOLLOWS:

TEMPORARY VEGETATIVE STABILIZATION:

1. FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH OR INCLUDE A COOL SEASON COVER CROP: (WESTERN WHEATGRASS (PASCOPYRUM SMITHII) AT 5.6 POUNDS PER ACRE, OATS (AVENA SATIVA) AT 4.0 POUNDS PER ACRE, CEREAL RYE GRAIN (SECALE CEREALE) AT 45 POUNDS PER ACRE, CONTRACTOR MUST ENSURE THAT ANY SEED APPLICATION REQUIRING A COOL SEASON COVER CROP DOES NOT UTILIZE ANNUAL RYEGRASS (LOLIUM MULTIFLORUM) OR PERENNIAL RYEGRASS (LOLIUM PERENNIAL RYEGRASS (LOLIUM PERENNIAL RYEGRASS (LOLIUM PERENNIAL RYEGRASS (LOLIUM PERENNE).

FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 45 POUNDS PER ACRE OR A NATIVE PLANT SEED MIX CONFORMING TO ITEM 604S OR 609S.

A. FERTILIZER SHALL BE APPLIED ONLY IF WARRANTED BY A SOIL TEST AND SHALL CONFORM TO ITEM NO. 606S, FERTILIZER: FERTILIZATION SHOULD NOT OCCUR WHEN RAINFALL IS EXPECTED OR DURING SLOW PLANT GROWTH OR DORMANCY. CHEMICAL FERTILIZER MAY NOT BE APPLIED IN THE CRITICAL WATER QUALITY ZONE.

B. HYDROMULCH SHALL COMPLY WITH TABLE 1, BELOW.

C. TEMPORARY EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1½ INCHES HIGH WITH A MINIMUM OF 95% TOTAL COVERAGE SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR TEMPORARY STRABILIZATION ARE UNIFORMLY VEGETATED, AND PROVIDED THERE ARE NO BARE SPOTS LARGER THAN 10 SQUARE FEET.

D. WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, AND STANDARD SPECIFICATION 604S OR 609S.

TABLE 1: HYDROMULCHING FOR TEMPORARY VEGETATIVE STABILIZATION

MATERIAL	DESCRIPTION	LONGEVITY	TYPICAL APPLICATIONS	APPLICATION RATES
100% OR ANY BLEND OF WOOD, CELLULOSE, STRAW, AND/OR COTTON PLANT MATERIAL (EXCEPT NO MULCH SHALL EXCEED 30% PAPER)	70% OR GREATER WOOD/STRAW 30% OR LESS PAPER OR NATURAL FIBERS	0-3 MONTHS	MODERATE SLOPES; FROM FLAT TO 3:1	1,500 TO 2,000 LBS PER ACRE

PERMANENT VEGETATIVE STABILIZATION:

1. FROM SEPTEMBER 15 TO MARCH 1, SEEDING IS CONSIDERED TO BE TEMPORARY STABILIZATION ONLY. IF COOL SEASON COVER CROPS EXIST WHERE PERMANENT VEGETATIVE STABILIZATION IS DESIRED, THE GRASSES SHALL BE MOWED TO A HEIGHT OF LESS THAN ONE—HALF (½) INCH AND THE AREA SHALL BE RE—SEEDED IN ACCORDANCE WITH TABLE 2 BELOW, ALTERNATIVELY, THE COOL SEASON COVER CROP CAN BE MIXED WITH BERMUDAGRASS OR NATIVE SEED AND INSTALLED TOGETHER, UNDERSTANDING THAT GERMINATION OF WARM—SEASON SEED TYPICALLY REQUIRES SOIL TEMPERATURES OF 60 TO 70 DEGREES.

FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 45 POUNDS PER ACRE WITH A PURITY OF 95% AND A MINIMUM PURE LIVE SEED (PLS) OF 0.83. BERMUDA GRASS IS A WARM SEASON GRASS AND IS CONSIDERED PERMANENT EROSION CONTROL PERMANENT VEGETATIVE STABILIZATION CAN ALSO BE ACCOMPLISHED WITH A NATIVE PLANT SEED MIX CONFORMING TO ITEM 604S OR 609S.

FERTILIZER USE SHALL FOLLOW THE RECOMMENDATION OF A SOIL TEST. SEE ITEM 606S, FERTILIZER. APPLICATIONS OF FERTILIZER (AND PESTICIDE) ON CITY-OWNED AND MANAGED PROPERTY REQUIRES THE YEARLY SUBMITTAL OF A PESTICIDE AND FERTILIZER APPLICATION RECORD, ALONG WITH A CURRENT COPY OF THE APPLICATION'S LICENSE. FOR CURRENT COPY OF THE APPLICATOR'S LICENSE. FOR CURRENT COPY OF THE RECORD TEMPLATE CONTACT THE CITY OF AUSTIN'S IPM COORDINATOR.

B. HYDROMULCH SHALL COMPLY WITH TABLE 2, BELOW.

B. HYDROMULCH SHALL COMPLY WITH TABLE 2, BELOW.

C. WATER THE SEEDED AREAS IMMEDIATELY AFTER INSTALLATION TO ACHIEVE GERMINATION AND A HEALTHY STAND OF PLANTS THAT CAN ULTIMATELY SURVIVE WITHOUT SUPPLEMENTAL WATER. APPLY THE WATER UNIFORMLY TO THE PLANTED AREAS WITHOUT CAUSING DISPLACEMENT OR EROSION OF THE MATERIALS OR SOIL MAINTAIN THE SEEDBED IN A MOIST CONDITION FAVORABLE FOR PLANT GROWTH. ALL WATERING SHALL COMPLY WITH CITY CODE CHAPTER 6-4 (WATER CONSERVATION), AT RATES AND FREQUENCIES DETERMINED BY A LICENSED IRRIGATOR OR OTHER QUALIFIED PROFESSIONAL, AND AS ALLOWED BY THE AUSTIN WATER UTILITY AND CURRENT WATER RESTRICTIONS AND WATER CONSERVATION INITIATIVES.

PERMANENT EROSION CONTROL SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1½ INCHES HIGH WITH A MINIMUM OF 95 PERCENT FOR THE NON-MATIVE MIX, AND 95 PERCENT COVERAGE FOR THE NATIVE MIX SO THAT ALL AREAS OF A SITE THAT RELY ON VEGETATION FOR STABILITY MUST BE UNIFORMLY VEGETATED, AND PROVIDED THERE ARE NO BARE SPOTS LARGER THAN 10 SQUARE FEET.

WHEN REQUIRED, NATIVE PLANT SEEDING SHALL COMPLY WITH REQUIREMENTS OF THE CITY OF AUSTIN ENVIRONMENTAL CRITERIA MANUAL, ITEMS 604S AND 609S.

TABLE 2: HYDROMULCHING FOR PERMANENT VEGETATIVE STABILIZATION

MATERIAL	DESCRIPTION	LONGEVITY	TYPICAL APPLICATIONS	APPLICATION RATES
BONDED FIBER MATRIX (BFM)	80% ORGANIC DEFIBRATED FIBERS			
10% TACKIFIER	6 MONTHS	ON SLOPES UP TO 2:1 AND EROSIVE SOIL CONDITIONS	2,500 TO 4,000 LBS PER ACRE (SEE MANUFACTURERS RECOMMENDATIONS)	
FIBER REINFORCED MATRIX (FRM)	65% ORGANIC DEFIBRATED FIBERS 25% REINFORCING FIBERS OR LESS 10% TACKIFIER	UP TO 12 MONTHS	ON SLOPES UP TO 1:1 AND EROSIVE SOIL CONDITIONS	3,000 TO 4,500 LBS PER ACRE (SEE MANUFACTURERS RECOMMENDATIONS)

10. DEVELOPER INFORMATION:

OWNER: WILLIAMSON COUNTY

ADDRESS: 3151 SE INNER LOOP RD, SUITE B, GEORGETOWN, TX 78626 OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS: STV inc.

PHONE #: (512) 349-0700 PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE: WILLIAMSON COUNTY ENGINEER

PHONE #: (512) 943-3330

PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE: WILLIAMSON COUNTY ENGINEER

PHONE #: (512) 943-3330

11. THE CONTRACTOR SHALL NOT DISPOSE OF SURPLUS EXCAVATED MATERIAL FROM THE SITE WITHOUT

NOTIFYING THE DEVELOPMENT SERVICES DEPARTMENT AT 512-974-2278 AT LEAST 48 HOURS PRIOR

WITH THE LOCATION AND A COPY OF THE PERMIT ISSUED TO RECEIVE THE MATERIAL

BRABIAY MCCONNON

WASTAMA

CENSES

SEAL EFFECTIVE UPON CITY APPROVAL

CP&Y



an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741

BY

DATE

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD **GENERAL NOTES**

WILLIAMSON COUNTY ROAD BOND PROGRAM STATE MEB Designed:

TEXAS

SHEET 1 OF 2

THE FOLLOWING SEQUENCE OF CONSTRUCTION SHALL BE USED FOR ALL DEVELOPMENT. THE APPLICANT IS ENCOURAGED TO PROVIDE ANY ADDITIONAL DETAILS APPROPRIATE FOR THE PARTICULAR DEVELOPMENT.

- TEMPORARY EROSION AND SEDIMENTATION CONTROLS ARE TO BE INSTALLED AS INDICATED ON THE APPROVED SITE PLAN OR SUBDIVISION CONSTRUCTION PLAN AND IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) THAT IS REQUIRED TO BE POSTED ON THE SITE. INSTALL TREE PROTECTION, INITIATE TREE MITIGATION MEASURES AND CONDUCT "PRE CONSTRUCTION" TREE FERTILIZATION (IF APPLICABLE).
- THE ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR MUST CONTACT THE DEVELOPMENT SERVICES DEPARTMENT, ENVIRONMENTAL INSPECTION, AT 512–974–2278, 72 HOURS PRIOR TO THE SCHEDULED DATE OF THE REQUIRED ON-SITE PRECONSTRUCTION MEETING.
- THE ENVIRONMENTAL PROJECT MANAGER, AND/OR SITE SUPERVISOR, AND/OR DESIGNATED RESPONSIBLE PARTY, AND THE GENERAL CONTRACTOR WILL FOLLOW THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE. TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE REVISED, IF NEEDED, TO COMPLY WITH CITY INSPECTORS' DIRECTIVES, AND REVISED CONSTRUCTION SCHEDULE RELATIVE TO THE WATER QUALITY PLAN REQUIREMENTS AND THE EROSION PLAN.
- REQUIREMENTS AND THE EROSION PLAN.

 ROUGH GRADE THE POND(S) AT 100% PROPOSED CAPACITY. EITHER THE PERMANENT OUTLET STRUCTURE OR A TEMPORARY OUTLET MUST BE CONSTRUCTED PRIOR TO DEVELOPMENT OF EMBANKMENT OR EXCAVATION THAT LEADS TO PONDING CONDITIONS. THE OUTLET SYSTEM MUST CONSIST OF A SUMP PIT OUTLET AND AN EMERGENCY SPILLWAY MEETING THE REQUIREMENTS OF THE DRAINAGE CRITERIA MANUAL AND/OR THE ENVIRONMENTAL CRITERIA MANUAL, AS REQUIRED. THE OUTLET SYSTEM SHALL BE PROTECTED FROM EROSION AND SHALL BE MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION UNTIL INSTALLATION OF THE PERMANENT WATER QUALITY POND(S).
- TEMPORARY EROSION AND SEDIMENTATION CONTROLS WILL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH THE EROSION SEDIMENTATION CONTROL PLAN (ESC) AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) POSTED ON THE SITE.
- 6. BEGIN SITE CLEARING/CONSTRUCTION (OR DEMOLITION) ACTIVITIES, WORK ADJACENT TO THE CWQZ IS ANTICIPATED TO TAKE PLACE IN THE FIRST PHASE OF CONSTRUCTION.
- IN THE BARTON SPRINGS ZONE, THE ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR WILL SCHEDULE A MID—CONSTRUCTION CONFERENCE TO COORDINATE CHANGES IN THE CONSTRUCTION SCHEDULE AND EVALUATE EFFECTIVENESS OF THE EROSION CONTROL PLAN AFTER POSSIBLE CONSTRUCTION ALTERATIONS TO THE SITE. PARTICIPANTS SHALL INCLUDE THE CITY INSPECTOR, PROJECT ENGINEER, GENERAL CONTRACTOR AND ENVIRONMENTAL PROJECT MANAGER OR SITE SUPERVISOR. THE ANTICIPATED COMPLETION DATE AND FINAL CONSTRUCTION SEQUENCE AND INSPECTION SCHEDULE WILL BE COORDINATED WITH THE APPROPRIATE CITY INSPECTOR.
- PERMANENT WATER QUALITY PONDS OR CONTROLS WILL BE CLEANED OUT AND FILTER MEDIA WILL BE INSTALLED PRIOR TO/CONCURRENTLY WITH REVEGETATION OF SITE.
- 9. COMPLETE CONSTRUCTION AND START REVEGETATION OF THE SITE AND INSTALLATION OF LANDSCAPING.
- 10. UPON COMPLETION OF THE SITE CONSTRUCTION AND REVEGETATION OF A PROJECT SITE, THE DESIGN ENGINEER SHALL SUBMIT AN ENGINEER'S LETTER OF CONCURRENCE BEARING THE ENGINEER'S SEAL, SIGNATURE, AND DATE TO THE DEVELOPMENT SERVICES DEPARTMENT INDICATING THAT CONSTRUCTION, INCLUDING REVEGETATION, IS COMPLETE AND IN SUBSTANTIAL COMPLANCE WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY INSPECTOR.
- 11. UPON COMPLETION OF LANDSCAPE INSTALLATION OF A PROJECT SITE, THE LANDSCAPE ARCHITECT SHALL SUBMIT A LETTER OF CONCURRENCE TO THE DEVELOPMENT SERVICES DEPARTMENT INDICATING THAT THE REQUIRED LANDSCAPING IS COMPLETE AND IN SUBSTANTIAL CONFORMITY WITH THE APPROVED PLANS. AFTER RECEIVING THIS LETTER, A FINAL INSPECTION WILL BE SCHEDULED BY THE APPROPRIATE CITY INSPECTOR.
- AFTER A FINAL INSPECTION HAS BEEN CONDUCTED BY THE CITY INSPECTOR AND WITH APPROVAL FROM THE CITY INSPECTOR, REMOVE THE TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND COMPLETE ANY NECESSARY FINAL REVEGETATION RESULTING FROM REMOVAL OF THE CONTROLS. CONDUCT ANY MAINTENANCE AND REHABILITATION OF THE WATER QUALITY PONDS OR CONTROLS.

EROSION AND SEDIMENTATION CONTROL REQUIREMENTS

IF DISTURBED AREA IS NOT TO BE WORKED FOR MORE THAN 14 DAYS, DISTURBED AREA NEEDS TO BE STABILIZED BY REVEGETATION, MULCH, TARP, OR REVEGETATION MATTING. [ECM 1.4.4.B.3, SECTION 5.1]

ENVIRONMENTAL INSPECTOR HAS THE AUTHORITY TO ADD AND/OR MODIFY EROSION/SEDIMENTATION CONTROLS ON SITE TO KEEP PROJECT IN COMPLIANCE WITH THE CITY OF AUSTIN RULES AND REGULATIONS [LDC 25-8-182]

CONTRACTOR SHALL UTILIZE DUST CONTROL MEASURES DURING SITE CONSTRUCTION SUCH AS IRRIGATION TRUCKS AND MULCHING AS PER ECM 1.4.5(A), OR AS DIRECTED BY THE ENVIRONMENTAL INSPECTOR.

THE CONTRACTOR WILL CLEAN UP SPOILS THAT MIGRATE ONTO THE ROADS A MINIMUM OF ONCE DAILY. [ECM 1.4.4.D.4]

PER LDC 25-8-323(C), FOR AREAS ON THE SITE THAT ARE TO REMAIN PERVIOUS AFTER DEVELOPMENT, ANY SOILS THAT ARE COMPACTED DURING SITE GRADING AND CONSTRUCTION OPERATIONS MUST BE DECOMPACTED IN COMPLIANCE WITH THE ECM AND IN COMPLIANCE WITH SSM 661S.

NO MORE THAN 2000 FEET OF CONSTRUCTION ZONE SHALL BE OPEN AT ANY TIME WITH CLEAN UP AND RESTORATION WORK OCCURRING BEFORE PROCEEDING TO THE NEXT SECTION. THE CONTRACTOR IS REQUIRED TO RESTORE ALL DISTURBED AREAS AS THE WORK PROGRESSES.

ALL SPOILS ARE TO BE PLACED BACK IN TRENCH EVERY NIGHT; OR IF SPOILS PILES ARE TO REMAIN OVERNIGHT, SPOILS MUST BE PLACED ON THE UPHILL SIDE OF TRENCH WITHIN THE LOC.

PERPENDICULAR EROSION CONTROLS MUST BE INSTALLED EVERY 30 FEET AS THE TRENCH IS BACKFILLED. [ECM 1.4.4.6]

CONTRACTOR SHALL PROVIDE AND MAINTAIN A DEWATERING SYSTEM TO ENSURE IT MEETS COMPLANCE WITH TITLE 6, ARTICLE V OF THE AUSTIN CITY CODE. THE DEWATERING PLAN MUST BE APPROVED BY THE ENVIRONMENTAL INSPECTOR DURING THE PRE-CONSTRUCTION CONFERENCE. IF THE PERFORMANCE OF THE DEWATERING SYSTEM IS NOT IN COMPLIANCE, THE CONTRACTOR MUST IMMEDIATELY MAKE THE NECESSARY MODIFICATIONS, FOLLOWING THE ENVIRONMENTAL INSPECTOR'S DIRECTION, TO ENSURE ADEQUATE SYSTEM PERFORMANCE.

ONLY RUBBER-TIRED EQUIPMENT IS ALLOWED WITHIN THE CWQZ AND FLOODPLAIN. NO TRACK EQUIPMENT IS ALLOWED.

ALL EQUIPMENT AND SPOILS ARE TO BE REMOVED FROM THE CREEK, THE CWQZ, AND 100-YEAR FLOODPLAIN NIGHTLY.

ECM 3.6.2 STANDARD PLAN NOTE

THE FOLLOWING PLAN NOTE SUMMARIZES THE CONTENTS OF THE ENVIRONMENTAL CRITERIA MANUAL AS IT RELATES TO TREE PROTECTION ON SITES WITH ACTIVE PERMITS:

- BEFORE CONSTRUCTION

 ALL TREES AND NATURAL AREAS SHOWN ON PLAN TO BE PRESERVED SHALL BE PROTECTED PER ECM 3.6.1.

 TREE PROTECTION SHALL BE INSTALLED PRIOR TO THE START OF ANY SITE WORK, INCLUDING DEMOLITION OR SITE PREPARATION. REFER TO ECM 3.6.1.A.

 FENCING FOR TREE PROTECTION SHALL BE CHAIN-LINK MESH WITH A MINIMUM HEIGHT OF 5 FEET AND SHALL BE INSTALLED AROUND OR BEYOND THE CRITICAL ROOT ZONE EXCEPT AS ALLOWED IN ECM 3.6.1.B.4.

 UNFENCED SECTIONS OF THE CRITICAL ROOT ZONE SHALL BE COVERED WITH MULCH AT A MINIMUM DEPTH OF 8 INCHES AND A MAXIMUM DEPTH OF 12 INCHES PER ECM 3.6.1.C.

- AT A MINIMUM DEPTH OF 8 INCHES AND A MAXIMUM DEPTH OF 12 INCHES PER ELM 3.6.1.C.

 WHERE FENCING IS LOCATED 5 FEET OR LESS FROM THE TRUNK OF A PRESERVED TREE, TRUNK WRAPPING SHALL BE INSTALLED PER ECM 3.6.1.D.

 EROSION AND SEDIMENTATION CONTROLS SHALL BE INSTALLED AND MAINTAINED SO AS NOT TO CAUSE IMPACTS THAT EXCEED PRESERVATION CRITERIA LISTED IN ECM 3.5.3.D.

- DURING CONSTRUCTION

 TREES APPROVED FOR REMOVAL SHALL BE REMOVED IN A MANNER THAT DOES NOT EXCEED PRESERVATION CRITERIA FOR THE TREES TO REMAIN. REFER TO ECM 3.5.2 A.

 FENCING MAY NOT BE TEMPORARILY MOVED OR REMOVED DURING DEVELOPMENT WITHOUT PRIOR AUTHORIZATION. THE FENCED CRITICAL ROOT ZONE SHALL NOT BE USED FOR TOOL OR MATERIAL STORAGE OF ANY KIND AND SHALL BE KEPT FREE OF LITTER. REFER TO ECM 3.6.1.B.3.

 PRUNING SHALL BE IN COMPLIANCE WITH THE CURRENT ANSI A300 STANDARD FOR TREE CARE.

- AFTER CONSTRUCTION

 TREE PROTECTION SHALL BE REMOVED AT THE END OF THE PROJECT AFTER ALL CONSTRUCTION AND FINAL GRADING IS COMPLETE, BUT BEFORE FINAL INSPECTION. REFER TO ECM 3.6.1.A.

 LANDSCAPE INSTALLATION WITHIN THE CRZ OF PRESERVED TREES, INCLUDING IRRIGATION, SOIL AND PLANTINGS, SHALL NOT EXCEED PRESERVATION CRITERIA LISTED IN ECM 3.5.2.

 DOCUMENTATION OF TREE WORK PERFORMED MUST BE PROVIDED TO INSPECTOR PER ECM APPENDIX P-6.

THIS LIST IS NOT EXHAUSTIVE.
REFER TO APPROPRIATE ECM SECTIONS FOR FULL REQUIREMENTS.

DEWATERING NOTES

CONSTRUCT OR PLACE STRUCTURES IN THE PRESENCE OF WATER ONLY IF APPROVED. PLACE PRECAST MEMBERS, PIPE, AND CONCRETE ONLY ON A DRY, FIRM SURFACE. REMOVE WATER BY BAILING, PUMPING, WELL-POINT INSTALLATION, DEEP WELLS, UNDERDRAINS, OR OTHER APPROVED METHOD.

REMOVE STANDING WATER IN A MANNER THAT DOES NOT ALLOW WATER MOVEMENT THROUGH OR ALONGSIDE CONCRETE BEING PLACED IF STRUCTURES ARE APPROVED FOR PLACEMENT IN THE PRESENCE OF WATER. PUMP OR BAIL ONLY FROM A SUITABLE SUMP SEPARATED FROM THE CONCRETE WORK WHILE PLACING STRUCTURAL CONCRETE OR FOR A PERIOD OF AT LEAST 36 HR. THEREAFTER. PUMP OR BAIL DURING PLACEMENT OF SEAL CONCRETE ONLY TO THE EXTENT NECESSARY TO MAINTAIN A STATIC HEAD OF WATER WITHIN THE COFFERDAM. PUMP OR BAIL TO DE-WATER INSIDE A SEALED COFFERDAM ONLY AFTER THE SEAL HAS AGED AT LEAST 36 HR.

PLACE A STABILIZING MATERIAL IN THE BOTTOM OF THE EXCAVATION IF THE BOTTOM OF AN EXCAVATION CANNOT BE DEWATERED TO THE POINT THE SUBGRADE IS FREE OF MUL OR IT IS DIFFICULT TO KEEP REINFORCING STELL CLEAN. USE FLEXIBLE BASE, CEMENT-STABILIZED BASE OR BACKFILL, LEAN CONCRETE, OR OTHER APPROVED STABILIZING MATERIAL. PROVIDE CONCRETE WITH AT LEAST 275 LB. OF CEMENT PER CUBIC YARD, IF LEAN CONCRETE IS USED, AND PLACE TO A MINIMUM DEPTH OF 3 IN. STABILIZING MATERIAL PLACED FOR THE CONVENIENCE OF THE CONTRACTOR WILL BE AT THE CONTRACTOR?S EXPENSE.



BY DATE





POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD GENERAL NOTES

WILLIAMSON COUNTY ROAD BOND PROGRAM

SHEET 2 OF 2

MEB Designed: STATE

ANSIB. ANSIB


	TREE LIST						
		, ,					
TAG NO.	G NO. DESCRIPTION						
# 10	20" WILLOW	P					
# 11	10" BOXELDER						
# 12	18" CHINABERRY						
# 13	12" COTTONWOOD						
# 14	22" PECAN	Р					
# 15	8" HACKBERRY						
# 16	13" MT MULBERRY (7", 6", 6")						
# 17	21" MT LIVE OAK (15", 12")	Р					
# 18	8" CEDAR						
# 19	9" HACKBERRY						

NOTES:

TREE SURVEY COMPELETED IN APRIL 2024.

TREE PROTECTION IS SUBSIDIARY TO PERTINENT ITEMS PER CITY OF AUSTIN SPEC 610S.

P — PROTECTED TREE H — HERITAGE TREE R — SCHEDULED FOR REMOVAL



WILLIAMSON COUNTY ROAD BOND PROGRAM

STATE

BAM Designed:

SHEET 1 OF

SP-2024-0324D

- AUSTIN ENERGY HAS THE RIGHT TO PRUNE AND/OR REMOVE TREES, SHRUBBERY AND OTHER OBSTRUCTIONS TO THE EXTENT NECESSARY TO KEEP THE EASEMENTS CLEAR, AUSTIN ENERGY WILL PERFORM ALL TREE WORK IN THE COMPLIANCE WITH CHAPTER 25-8, SUBCHAPTER B OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER/DEVELOPER OF THIS SUDIVISION/LOT SHALL PROVIDE AUSTIN ENERGY WITH ANY EASEMENT AND/OR ACCESS REQUIRED, IN ADDITION TO THOSE INDICATED, FOR THE INSTALLATION AND ONGOING MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES. THESE EASEMENTS AND/OR ACCESS ARE REQUIRED TO PROVIDE ELECTRIC SERVICE TO THE BUILDING AND WILL NOT BE LOCATED SO AS TO CAUSE THE SITE TO BE OUT OF COMPLIANCE WITH CHAPTER 25-8 OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE.
- THE OWNER SHALL BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY EROSION CONTROL, REVEGETATION AND TREE PROTECTION. IN ADDITION, THE OWNER SHALL BE RESPONSIBLE FOR ANY INITIAL TREE PRUNING AND TREE REMOVAL THAT IS WITHIN TEM FEET OF THE CENTER LINE OF THE PROPOSED OVERHEAD ELECTRICAL FACILITIES DESIGNED TO PROVIDE ELECTRIC SERVICE TO THIS PROJECT. THE OWNER SHALL INCLUDE AUSTIN ENERGY'S WORK WITHIN THE LIMITS OF CONSTRUCTION FOR THIS PROJECT.
- THE OWNER OF THIS PROJECT IS RESPONSIBLE FOR MAINTAINING CLEARANCES REQUIRED BY THE NATIONAL ELECTRIC SAFETY CODE, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSH'A) REGULATIONS, CITY OF AUSTIN RULES AND REGULATIONS AND TEXAS STATE LAWS PERTAINING TO CLEARANCES WHEN WORKING IN CLOSE PROXIMITY TO OVERHEAD POWER LINES AND EQUIPMENT. AUSTIN ENERGY WILL NOT RENDER ELECTRIC SERVICE UNLESS REQUIRED CLEARANCES ARE MAINTAINED. ALL COSTS INCURRED BECAUSE OF FAILURE TO COMPLY WITH THE REQUIRED CLEARANCES WILL BE CHARAGED TO THE OWNER.

STANDARD SITE PLAN NOTES

ORDINANCE REQUIREMENTS

- ALL IMPROVEMENTS SHALL BE MADE IN ACCORDANCE WITH THE RELEASED SITE PLAN. ANY ADDITIONAL IMPROVEMENTS WILL REQUIRE A SITE PLAN AMENDMENT AND APPROVAL FROM THE DEVELOPMENT SERVICES DEPARTMENT.

 APPROVAL OF THIS SITE PLAN DOES NOT INCLUDE BUILDING CODE APPROVAL; FIRE CODE APPROVAL; OR BUILDING, DEMOLITION, OR REPORT OF A SITE PLAN DOES NOT INCLUDE STATEMENT OF REFLOCATION PERMIT CAN ONLY BE ISSUED ONCE THE HISTORIC REVIEW PROCESS SO COMMETTED PROVALS A CITY DEMOLITION OR RELOCATION PERMIT CAN ONLY BE ISSUED ONCE THE HISTORIC REVIEW ALL SIGNS MUST COMPLY WITH THE REQUIREMENTS OF THE CITY OF AUSTIN LAND DEVELOPMENT CODE. THE OWNER IS RESPONSIBLE FOR ALL COSTS OF RELOCATION OF, OR DAMAGE TO, UTILITIES. ADDITIONAL ELECTRIC EASEMENTS MAY BE REQUIRED AT A LATER DATE.

 A SITE DEVELOPMENT PERMIT MUST BE ISSUED PRIOR TO AN APPLICATION FOR BUILDING PERMIT FOR NON-CONSOLIDATED OR LAND USE COMMISSION APPROVED SITE PLANS.

- WATER AND WASTEWATER SERVICE WILL BE PROVIDED BY THE CITY OF AUSTIN --- OR IDENTIFY THE SERVICE PROVIDER IF OTHER THAN THE
- FOR CONSTRUCTION WITHIN THE RIGHT-OF-WAY, A R.O.W. EXCAVATION PERMIT IS REQUIRED.

FIRE DEPARTMENT

- THE AUSTIN FIRE DEPARTMENT REQUIRES ASPHALT OR CONCRETE PAVEMENT PRIOR TO CONSTRUCTION AS AN "ALL WEATHER DRIVING SURFACE."
- SUBFACE."

 HYDRANTS MUST BE INSTALLED WITH THE CENTER OF THE FOUR-INCH OPENING AT LEAST 18 INCHES ABOVE FINISHED GRADE. THE FOUR-INCH OPENING MUST FACE THE DRIVEWAY OR STREET WITH THREE-TO SIX-FOOT SETBACKS FROM THE CURBLINE(S). NO OBSTRUCTION IS ALLOWED WITHIN THREE FEET OF ANY HYDRANT AND THE FOUR-INCH OPENING MUST BE TOTALLY HORDSTRUCTED FROM THE STREET. TIMING OF INSTALLATION; WHEN FIRE PROTECTION FACILITIES ARE INSTALLED BY THE DEVELOPER, SUCH FACILITIES SHALL INCLUDE ALL SURFACE ACCESS ROADS WHICH SHALL BE INSTALLED AND MADE SERVICEABLE PRIOR TO AND DUTHET THE TIME OF CONSTRUCTION. WHEN ALTERNATIVE METHODS OF PROTECTION, AS APPROVED BY THE FIRE CHIEF, ARE PROVIDED, THE ABOVE MAY BE MODIFIED OR WAIVED.
- WAIVEL).
 ALL PREVIOUS/DECORATIVE PAVINGWITHIN 100 FEET OF ANY BUILDING MUST BE APPROVED BY THE FIRE DEPARTMENT.
 COMMERCIAL DUMPSTERS AND CONTAINERS WITH AN INDIVIDUAL CAPACITY OF 1.5 CUBIC YARDS OR GREATER SHALL NOT BE STORED
 OR PLACED WITHIN TEN FEET OF OPENINGS, COMBUSTBLE WALLS, OR COMBUSTBLE EAVE LINES.
 FIRE LANES DESIGNATED ON SITE PLAN SHALL BE REGISTERED WITH CITY OF AUSTIN FIRE MARSHAL'S OFFICE AND INSPECTED FOR

- VERTICAL CLEARANCE REQUIRED FOR FIRE APPARATUS IS 14 FEET FOR FULL WIDTH OF ACCESS DRIVE.

GENERAL CONSTRUCTION NOTES

- 1. ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER WHO PREPARED THEM. IN REVIEWING THESE PLANS, THE CITY OF AUSTIN MUST RELY ON THE ADEQUACY OF THE WORK OF THE DESIGN ENGINEER.

 2. CONTRACTOR SHALL CALL TEXAS 811 (811 OR 1-800-344-8377) FOR UTILITY LOCATIONS PRIOR TO ANY WORK IN CITY EASEMENTS OR STREET R.O.W.

 3. CONTRACTOR SHALL NOTIFY THE CITY OF AUSTIN SITE & SUBDIMISION TO SUBMIT REQUIRED DOCUMENTATION, PAY CONSTRUCTION INSPECTION FEES, AND TO SCHEDULE THE REQUIRED SITE AND SUBDIMISION PRE-CONSTRUCTION MEETING. THIS MEETING MUST BE HELD PRIOR TO ANY CONSTRUCTION ACTIVITIES WITHIN THE R.O.W. OR PUBLIC EASEMENTS, PLEASE VISIT, INFORMATION CONCERNING FEES, AND CONTACT INFORMATION.

 4. FOR SLOPES OR TRENCHES GREATER THAN FIVE FEET IN DEPTH, A NOTE MUST BE ADDED STATING: "ALL CONSTRUCTION OPERATIONS SHALL BE ACCOMPLISHED IN ACCORDANCE WITH APPLICABLE REQULATIONS OF THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION." (OSH) ASTANDADS MAY BE PURCHASED FROM THE GOVERNMENT PRINTING OFFICE; INFORMATION AND RELATED REFERENCE MATERIALS MAY BE PURCHASED FROM OSHA, 611 EAST 6TH STREET, AUSTIN TEXAS.)

 5. ALL SITE WORK MUST ALSO COMPLY WITH ENVIRONMENTAL RECOVERMENTS.

- ☐ RELEASE OF THE CERTIFICATE OF OCCUPANCY BY THE DEVELOPMENT SERVICES DEPARTMENT (INSIDE THE CITY LIMITS); OR ☐ INSTALLATION OF AN ELECTRIC OR WATER METER (IN THE FIVE-MILE ETJ)

DEVELOPER INFORMATION

DWNER	PHONE #	
OWNER ADDRESS		
OWNER'S REPRESENTATIVE RESPONSIBLE FOR PLAN ALTERATIONS	PHONE #	
PERSON OR FIRM RESPONSIBLE FOR EROSION/SEDIMENTATION CONTROL MAINTENANCE	PHONE #	
PERSON OR FIRM RESPONSIBLE FOR TREE/NATURAL AREA PROTECTION MAINTENANCE	PHONE #	

AMERICANS WITH DISABILITIES ACT

THE CITY OF AUSTIN HAS REVIEWED THIS PLAN FOR COMPLIANCE WITH CITY DEVELOPMENT REGULATIONS ONLY. THE APPLICANT, PROPTERY OWNER, AND OCCUPANT OF THE PREMISES ARE RESPONSIBLE FOR DETERMINING WHETHER THE PLAN COMPLIES WITH ALL OTHER LAWS, REGULATIONS, AND RESTRICTIONS WHICH MAY SE APPLICABLE TO THE PROPERTY AND ITS USE.

NOTE: DO

DO NOT REMOVE THE TITLE BLOCK
RGY GENERAL INFORMATION AND
NOTES FOR COMMERCIAL SITES AN
SUBDIVISION PLANS

Ω

October 2021
VERSION 2.0
STANDARD NO.
1 OF 1

CITY OF AUSTIN AUSTIN ENERGY

IN ENER JCTION I AUSTII ONSTRU

RADINY MOCONNON SEAL EFFECTIVE UPON CITY APPROVAL







POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

AUSTIN ENERGY GENERAL NOTES STANDARD SITE PLAN NOTES

WILLIAMSON COUNTY ROAD BOND PROGRAM MSB Designed: MSB STATE AJS Checked: AJS TEXAS WILLIAMSON


SHEET 1 OF 1





EXISTING TYPICAL SECTION


ROXIE DR, POND SPRINGS TO STA 14+50.00




EXISTING TYPICAL SECTION

N.T.S.


ROXIE DR, STA 14+50.00 TO STA END






EXISTING TYPICAL SECTION

POND SPRINGS, BEGIN TO END





Radius =
External =
Long Chord =
Mid. Ord. =
P.C. Station
P.T. Station
C.C.
Back =

C.C.
Back = S 21° 18′ 48.19" E
Ahead = S 48° 50′ 46.56" W
Chord Bear = S 13° 45′ 59.18" W

Course from PT ROXIE4 to PC ROXIE5 S 48° 50′ 46.56" W Dist 336.1478

10,133,959.3562 E

3,100,395.9175

27+73.66 N 26° 03′ 39.71" (RT) 45° 50′ 11.84" 28.9287 56.8564 125.0000 3.3038 56.3675 3.2187 27+44.73 N 28+01.59 N 10, 133, 978. 3936 10, 133, 951. 8237 10, 134, 072. 5119 3,100,417.6992 3,100,367.9867 3,100,335.4390

Curve ROXIE5
P.I. Station
Delta = 26° 03′ 39.71"
Degree = 45° 50′ 11.84"
Tangent = 28.9287
Length = 56.8564
Radius = 125.0000
External = 3.3038
Long Chord = 56.3675
Mid. Ord. = 3.2187
P.C. Station 27*44.73
P.T. Station 28*01.59
C.C.
Back = \$ 48° 50′ 46.56" W
Ahead = \$ 74° 54′ 26.27" W
Chord Bear = \$ 61° 52′ 36.41" W Course from PT ROXIE5 to PC ROXIE6 S 74° 54′ 26.27" W Dist 153.2471

		Curve	e Data		
		*	*		
Curve ROXIE6 P.I. Station Delta = Degree =	29+80.31 23° 02′ 18.81" 45° 50′ 11.84"	N (LT)	10, 133, 905. 2877	E	3,100,195.4292
Tangent = Length = Radius = External =	25. 4753 50. 2623 125. 0000 2. 5696				
Long Chord = Mid. Ord. = P.C. Station P.T. Station	49. 9244 2. 5178 29+54. 83 30+05. 10	N N	10, 133, 911. 9210 10, 133, 889. 5576	E	3,100,220.0258 3,100,175.3903
C.C. Back = S Ahead = S Chord Bear = S	74° 54′ 26.27" W 51° 52′ 07.47" W 63° 23′ 16.87" W	N	10, 133, 791. 2328	E	3, 100, 252, 5734

Course from PT ROXIE6 to A2 S 51° 52′ 07.47" W Dist 65.2813

Point A2 N 10,133,849.2487 E 3,100,124.0402 Sta 30+70.38

.....

Ending chain ROXIE description

Curve Data

Point A1	N 10,135,37	8.5086	Ε	3,101,	050.48	62 Sta	10+00.00
Course from	A1 to PC ROXIE1 S 39°	14′ 34.	50"	W Dist	56.67	05	
		Curve					
Curve ROXIE1 P.I. Statio Delta Degree Tangent Length		* N (RT)		-* 135,285	. 3707	E	3,100,974.4085
Radius External Long Chord Mid. Ord. P.C. Statio P.T. Statio C.C. Back Ahead Chord Bear		N N N	10,	135,334 135,251 135,587	.0253	E E	3,101,014.6359 3,100,920.8920 3,100,704.8475
	PT ROXIE1 to PC ROXIE2	S 57°	18′	31.64"	W Dis	+ 123.7	924
004 00 11 0111	TO NOMIZE TO TO NOMIZE				0.0		JE 1
O BOYTE		Curve *					
Curve ROXIE2 P.I. Statio Delta Degree Tangent	on 14+03.68 = 27° 17′ 15.73" = 14° 19′ 26.20" = 97.0943	N (LT)	10,	135,131	.7219	E	3,100,734.9952
Length Radius External Long Chord Mid. Ord. P.C. Static P.T. Static C.C. Back Ahead Chord Bear		N N N	10,	135,184 135,047 134,847	.6537	E E E	3,100,816.7091 3,100,686.4171 3,101,032.7536
Course from	PT ROXIE2 to PC ROXIE3	5 S 30°	01′	15.91"	W Dis	+ 27.43	32
004 00 11 0111	TO NOMIZE TO TO NOMIZE				0.0		.
Curve ROXIES P.I. Static Delta Degree Tangent		Curve * N (LT)			. 4756	E	3,100,606.5722
Length Radius External Long Chord Mid. Ord. P.C. Static	= 246.3878 = 275.0000 = 30.1064 = 238.2291 = 27.1357	N		135,023		Ē	3,100,672.6917
P.T. Static C.C. Back	on 17+70.91 = S 30° 01′ 15.91" W	N N		134,786 134,886		E E	3, 100, 654. 6064 3, 100, 910. 7981
Ahead Chord Bear	= S 21° 18′ 48.19" E = S 4° 21′ 13.86" W						
	PT ROXIE3 to PC ROXIE4	I S 21°	18′	48.19"	E Dis	+ 270.3	162
		Curve					
Curve ROXIE	4	*					
P.I. Static Delta Degree Tangent Length	on 22+51.91 = 70° 09′ 34.74″ = 19° 05′ 54.94″ = 210.6858 = 367.3551	N (RT)	10,	134,338	. 2548	E	3,100,829.4356
Radius External Long Chord Mid. Ord. P.C. Statio P.T. Statio C.C.		N N	10,	134,534 134,199	. 6063	E	3, 100, 752. 8579 3, 100, 670. 8005
C.C. Back	= S 21° 18′ 48.19" E	N	10,	134, 425	. 4903	E	3, 100, 473. 3760

Chain ROXIE contains:
A1 CUR ROXIE1 CUR ROXIE2 CUR ROXIE3 CUR ROXIE4 CUR ROXIE5 CUR ROXIE6 A2

Beginning chain ROXIE description


BRADILEY MOCONNON SEAL EFFECTIVE UPON CITY APPROVAL


BY DATE


an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741


POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD HORIZONTAL ALIGNMENT DATA


	WILLIAMSON	COUN	TY ROAD	BOND	PROGRA	AM
)rawn:	Designed:		STATE	co	UNTY	SHEET































- NOTES:


 1. CONTROLLED LOW STRENGTH MATERIAL (CLSM) SHALL BE USED IN LIEU OF FLEXBASE TO 3 1/2" OF BOTTOM OF HOT MIX LAYERS. SEE NOTE 6 ON STANDARD 1100S−2.

 2. ALL EXCAVATION, REMOVAL, AND MATERIAL BACKFILL SHALL BE SUBSIDIARY TO THE CUT & RESTORE PAY ITEM AND PIPE/BOX ITEMS. NO EXTRA PAYMENT SHALL BE MADE. CLSM IS QUANTIFIED AND PAID FOR SEPARATELY (10" THICKNESS ASSUMED).






SP-2024-0324D



_ANSIB.tbl


END SHEET FLOW





(PROPOSED) WILLIAMSON COUNTY ROAD BOND PROGRAM



cpybw_ANSIB.tbl cpypdf_ANSIB.plt








LEGEND


FLOW DIRECTION



CRITICAL WATER QUALITY ZONE CREEK CENTERLINE

WETLAND

CEF SETBACK




CITY APPROVAL

an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

DRAINAGE AREA MAP EXTERIOR (EXISTING)

WILLIAMSON COUNTY ROAD BOND PROGRAM



cpybw_ANSIB.tbl

D3-ON

D4-ON

PAVEMENT GRASS PAVEMENT

127

43

1.1

1.4

PAVED

PAVED


20.32

20.32 0.30

0.99

0

0



HORIZ.

SEE EXTERIOR DRAINAGE AREA MAP FOR AREAS

2. NOTE: SEE HYDROLOGIC INFO ON SHEET NAMED

"DRAINAGE AREA CALCULATIONS EXISTING & PROPOSED" **LEGEND**

TRAFFIC DIRECTION

FLOW DIRECTION

STORM SEWER

DRAINAGE AREA BOUNDARY DRAINAGE AREA ID

EXISTING & PROPOSED FEMA/CITY 100 YR FLOODPLAIN

€ DITCH

NOTES:

SHEET 1 OF 1

5.15

5.00

5.15

2.80


g ∑
8:54:51
/2025
4

	EXISTING DRAINAGE AREA CALCULATIONS - RUNOFF SUMMARY											
DRAINAGE AREA ID	AREA A (AC)	COMPUTATION METHOD	CURVE NUMBER	Tc (MIN)	2-YR Q (CFS)	10-YR Q (CFS)	25-YR Q (CFS)	100-YR Q (CFS)				
A-ON	0.78	HYDROGRAPH	96.30	5.90	4.20	6.50	8.00	10.50				
A-OFF	21.22	HYDROGRAPH	93.82	31.49	58.30	91.20	113.20	149.60				
B00	256.93	HYDROGRAPH	93.10	44.88	572.10	904.90	1128.90	1501.20				
COO	4.36	HYDROGRAPH	89.54	13.53	15.90	26.30	33.10	44.40				
C01	2.31	HYDROGRAPH	85.58	8.67	8.70	15.30	19.60	26.80				
D2-ON	0.45	HYDROGRAPH	95.93	3.39	2.50	3.90	4.70	6.20				
D2-OFF	0.14	HYDROGRAPH	95.21	0.58	0.80	1.20	1.50	2.00				
D3-ON	0.12	HYDROGRAPH	94.33	2.95	0.60	1.00	1.20	1.60				
D4-ON	0.09	HYDROGRAPH	97. 20	1.53	0.50	0.80	1.00	1.30				

	PROPOSED DRAINAGE AREA CALCULATIONS - RUNOFF SUMMARY										
DRAINAGE AREA ID	AREA A (AC)	COMPUTATION METHOD	CURVE NUMBER	Tc (MIN)	2-YR Q (CFS)	10-YR Q (CFS)	25-YR Q (CFS)	100-YR Q (CFS)			
A-ON	0.78	HYDROGRAPH	96.30	5.90	4.20	6.50	8.00	10.50			
A-OFF	21.22	HYDROGRAPH	93.82	31.49	58.30	91.20	113.20	149.60			
B00	256.93	HYDROGRAPH	93.10	44.88	572.10	904.90	1128.90	1501.20			
C00	4.36	HYDROGRAPH	89.54	13.53	15.90	26.30	33.10	44.40			
CO1	2.31	HYDROGRAPH	85.58	8.67	8.70	15.30	19.60	26.80			
D2-ON	0.45	HYDROGRAPH	95.93	3.39	2.50	3.90	4.70	6.20			
D2-OFF	0.14	HYDROGRAPH	95.21	0.58	0.80	1.20	1.50	2.00			
D3-ON	0.12	HYDROGRAPH	94.33	2.95	0.60	1.00	1.20	1.60			
D4-ON	0.09	HYDROGRAPH	97.20	1.53	0.50	0.80	1.00	1.30			

	NCRS ANAL	YSIS RESULT	S - PEAK FLO	OW (CFS)	
POA	SCENARIO	2-yr	10-yr	25-yr	100-yr
	EXISTING	636.50	1006.70	1255.70	1669.20
OUTFALL	PROPOSED	636.50	1006.70	1255.70	1669.20
	NET CHANGE	0.00	0.00	0.00	0.00
	EXISTING	58.30	91.20	113.20	149.60
A-OFF	PROPOSED	58.30	91.20	113.20	149.60
	NET CHANGE	0.00	0.00	0.00	0.00
	EXISTING	59.30	92.60	115.00	152.00
A-ON	PROPOSED	59.30	92.60	115.00	152.00
	NET CHANGE	0.00	0.00	0.00	0.00
	EXISTING	0.80	1.20	1.50	2.00
D2-OFF	PROPOSED	0.80	1.20	1.50	2.00
	NET CHANGE	0.00	0.00	0.00	0.00
	EXISTING	3.30	5.10	6.20	8.20
D2	PROPOSED	3.30	5.10	6.20	8.20
	NET CHANGE	0.00	0.00	0.00	0.00
	EXISTING	3.90	6.10	7.50	9.80
D3	PROPOSED	0.60	1.00	1.20	1.60
	NET CHANGE	-3.30	-5.10	-6.30	-8.20
	EXISTING	4.40	6.90	8.40	11.10
D4	PROPOSED	0.50	0.80	1.00	1.30
	NET CHANGE	-3.90	-6.10	-7.40	-9.80

NOTE: ANALYSIS COMPLETED IN HEC-HMS v4.12



DRAINAGE AREA CALCULATIONS EXISTING & PROPOSED

WILLIAMSON COUNTY ROAD BOND PROGRAM

ID	NODE	NODE	SHAPE	NO.	PIPE	HYD. LEN.	_	SLOPE	DIAMETER	RISE	SPAN	FL US	FL DS	TOTAL TC	Q	CAP.	DEPTH	VELOCITY	HGL US	HGL DS	JCT.
טו	UPSTREAM	DOWNSTREAM	SHAPE	INO.	CLASS	(FT)] "	(%)	(IN)	(FT)	(FT)	(FT)	(FT)	(MIN)	(CFS)	(CFS)	(FT)	(FT/S)	(FT)	(FT)	LOSS (FT)
L-D03	D02	MH03-R	Circle	1	V	6.50	0.013	2.34	18.00	N/A	N/A	931.75	931.60	3.39	5.42	16.06	1.91	3.07	933.53	933.51	0.02
L-D04	D03	MH02-R	Circle	1	V	9.00	0.013	2.14	18.00	N/A	N/A	931.20	931.01	5.15	1.37	15.37	1.99	0.77	933.00	933.00	0.00
L-D05	D04	MH04-R	Circle	1	V	11.51	0.013	0.43	18.00	N/A	N/A	930.75	930.70	2.80	0.94	6.92	1.88	0.53	932.58	932.58	0.00
L-R03	MH03-R	MH02-R	Circle	1	V	156.84	0.013	0.38	18.00	N/A	N/A	931.60	931.01	3.43	5.42	6.45	1.91	3.07	933.33	932.91	0.42
L-R04	MH02-R	MH04-R	Circle	1	V	61.19	0.013	0.50	18.00	N/A	N/A	931.01	930.70	5.34	6.68	7.44	1.75	3.78	932.70	932.45	0.25
L-R05	MH04-R	MH01	Circle	1	V	70.31	0.013	0.14	18.00	N/A	N/A	930.70	930.60	5.61	7.49	3.96	1.06	4.24	932.21	931.66	0.34
L-PS01	JCT01	MH01	Box	1	N/A	57.79	0.013	1.38	N/A	3.00	5.00	925.50	924.70	33.35	88.45	193.22	4.16	5.90	929.03	928.86	0.17
L-PS02	MH01	MH02	Box	1	N/A	258.32	0.013	1.21	N/A	3.00	5.00	924.70	921.58	33.52	91.65	180.49	2.77	12.09	926.89	924.35	3.05
L-PS03	MH02	MH03	Box	1	N/A	270.00	0.013	0.49	N/A	3.00	5.00	920.23	918.90	33.87	91.10	115.19	3.67	6.07	923.40	922.57	0.83
L-PS04	MH03	MH04	Box	1	N/A	290.89	0.013	0.31	N/A	4.00	5.00	917.90	916.99	34.61	90.00	137.17	5.16	4.50	922.54	922.15	0.39
L-PS05	MH04	MH05	Box	1	N/A	287.46	0.013	0.50	N/A	4.00	5.00	916.99	915.55	35.69	88.45	173.57	6.05	4.42	921.97	921.60	0.37
L-PS06	MH05	HW-PS06	Box	1	N/A	29.84	0.013	0.50	N/A	4.00	5.00	915.55	915.40	36.77	86.95	173.89	2.01	8.70	917.66	917.41	0.14
L-PS07	A01	JCT01	Box	2	N/A	24.50	0.013	3.06	N/A	2.00	5.00	932.50	931.75	33.32	88.49	319.60	0.86	13.12	933.85	932.61	0.26
LIGHT OTODA	L OFWED DEOL	ONED HOUSE DAT		ETHOROLO	0) (

NOTE: STORM SEWER DESIGNED USING RATIONAL METHODOLOGY

NOTE: TAILWATER ELEVATION FOR SYSTEM SET AT DOWNSTREAM CHANNEL 25-YR WSEL = 916.50'.

NOTE: ACTUAL TIME OF CONCENTRATION USED FOR LINK CALCULATIONS.

LINK CONFIGURATION AND CALCULATIONS - (100-YR DESIGN STORM)

ID.	NODE	NODE	SHAPE	NO.	PIPE	HYD. LEN.		SLOPE	DIAMETER	RISE	SPAN	FL US	FL DS	TOTAL TC	Q	CAP.	DEPTH	VELOCITY	HGL US	HGL DS	JCT.
טו	UPSTREAM	DOWNSTREAM	SHAFE	NO.	CLASS	(FT)	"	(%)	(IN)	(FT)	(FT)	(FT)	(FT)	(MIN)	(CFS)	(CFS)	(FT)	(FT/S)	(FT)	(FT)	LOSS (FT)
L-D03	D02	MH03-R	Circle	1	V	6.50	0.013	2.34	18.00	N/A	N/A	931.75	931.60	3.39	6.99	16.06	3.70	3.96	935.33	935.30	0.03
L-D04	D03	MH02-R	Circle	1	V	9.00	0.013	2.14	18.00	N/A	N/A	931.20	931.01	5.15	2.81	15.37	3.42	1.59	934.44	934.43	0.01
L-D05	D04	MH04-R	Circle	1	V	11.51	0.013	0.43	18.00	N/A	N/A	930.75	930.70	2.80	1.35	6.92	2.84	0.76	933.54	933.54	0.00
L-R03	MH03-R	MH02-R	Circle	1	V	156.84	0.013	0.38	18.00	N/A	N/A	931.60	931.01	3.42	6.99	6.45	3.30	3.96	935.00	934.31	0.70
L-R04	MH02-R	MH04-R	Circle	1	V	61.19	0.013	0.50	18.00	N/A	N/A	931.01	930.70	5.24	9.70	7.44	2.57	5.49	933.79	933.27	0.52
L-R05	MH04-R	MH01	Circle	1	V	70.31	0.013	0.14	18.00	N/A	N/A	930.70	930.60	5.43	10.93	3.96	1.27	6.18	932.75	931.87	0.75
L-PS01	JCT01	MH01	Box	1	N/A	57.79	0.013	1.38	N/A	3.00	5.00	925.50	924.70	32.77	130.92	193.22	5.12	8.73	930.19	929.82	0.37
L-PS02	MH01	MH02	Box	1	N/A	258.32	0.013	1.21	N/A	3.00	5.00	924.70	921.58	32.88	135.76	180.49	4.67	9.05	928.02	926.25	1.77
L-PS03	MH02	MH03	Box	1	N/A	270.00	0.013	0.49	N/A	3.00	5.00	920.23	918.90	33.35	134.70	115.19	4.80	8.98	925.51	923.70	1.82
L-PS04	MH03	MH04	Box	1	N/A	290.89	0.013	0.31	N/A	4.00	5.00	917.90	916.99	33.86	133.62	137.17	5.76	6.68	923.62	922.75	0.86
L-PS05	MH04	MH05	Box	1	N/A	287.46	0.013	0.50	N/A	4.00	5.00	916.99	915.55	34.58	132.09	173.57	5.97	6.60	922.35	921.52	0.83
L-PS06	MH05	HW-PS06	Box	1	N/A	29.84	0.013	0.50	N/A	4.00	5.00	915.55	915.40	35.31	130.60	173.89	5.25	6.53	920.73	920.65	0.08
L-PS07	A01	JCT01	Box	2	N/A	24.50	0.013	3.06	N/A	2.00	5.00	932.50	931.75	32.74	130.98	319.60	1.16	14.97	934.25	932.91	0.24

NOTE: STORM SEWER DESIGNED USING RATIONAL METHODOLOGY

NOTE: TAILWATER ELEVATION FOR SYSTEM SET AT DOWNSTREAM CHANNEL 100-YR WSEL = 921.68'.

NOTE: ACTUAL TIME OF CONCENTRATION USED FOR LINK CALCULATIONS.

1. ALLOWABLE HEADWATER BASED ON GUTTER FLOW LINE ELEVATION.

INLETS - OUTFALL A (25-YR DESIGN STORM)


	INLET CONFIGURATION					INLET FLOW CALCULATION TABLE — DCM 4.4.3																
INLET ID	ד	YPE	OPENING (FT)	WIDTH (FT)	CONTRIBUTING DRAINAGE AREAS	DRAINAGE AREA DISCHARGE (CFS)	Qpass UPSTREAM (CFS)	Qa (CFS)	LONG SLOPE (%)	CROSS SLOPE (%)	GUTTER DEPRESSION (FT)	Yo (GUTTER DEPTH) (FT)	PONDED WIDTH (FT)*	REDUCTION FACTOR	Qa/La	La	L (FT)	L/La	GUTTER DEPRESSION / GUTTER DEPTH (FT/FT)	Q/Qa	Q (CFS)	Opass (CFS)
D02	Curb	On Grade	10.00	3.50	D2-ON D2-OFF	4.35 1.35	0.00	5.70	0.6	2.95	0.25	0.33	9.89	N/A	10.257	0.556	10.00	17.980	0.755	0.950	5.42	0.28
D03	Curb	On Grade	10.00	3.50	D3-ON	1.09	0.28	1.37	1.2	2.06	0.25	0.19	6.62	N/A	3.050	0.450	10.00	22.246	1.322	0.998	1.37	0.00
D04	Curb	In Sag	10.00	3.50	D4-ON	0.94	0.00	0.94	0.0	2.18	0.25	0.66	5.05	N/A	N/A	N/A	10.00	N/A	0.377	1.000	0.94	0.00


*NOTE: FOR A CLEAR WIDTH OF 12', THE MAX PONDED WITDH ALLOWED IS 12'.


RUNOFF - STORM DRAIN OUTFALL A


		Flow Calculations — Storm Drain Drainage Areas												
	ID	Outflow	Computation	Tc	C Value	Α	AE	EP = 4%	AEP = 1%					
		Element	Method	10	C value	_ ^	I	Q	1	Q				
	A1-OFF	A01	Rational Method	31.49	0.84	21.22	5.43	87.77	7.17	128.59				
	A1-ON	A01	Rational Method	5.90	0.91	0.78	11.25	7.37	14.70	10.58				
	D2-OFF	D02	Rational Method	1.39	0.88	0.14	11.79	1.35	15.42	1.96				
	D2-ON	D02	Rational Method	3.39	0.91	0.45	11.79	4.35	15.42	6.31				
	D3-ON	D03	Rational Method	5.15	0.84	0.12	11.70	1.09	15.30	1.55				
	D4-ON	D04	Rational Method	2.80	0.94	0.09	11.79	0.94	15.42	1.35				


NOTE: A MINUMUM OF A 5-MIN TIME OF CONCENTRATION WAS USED.

















0.11 IN²/FT

0.31 IN²/FT

0.31 IN²/FT


0.31 IN²/FT

0.31 IN²/FT

0.31 IN²/FT

0.31 IN²/FT

PLAN VIEW



FABRICATION NOTES:

- 1. PROVIDE CLASS "H" CONCRETE IN ACCORDANCE WITH TXDOT ITEM 421 AND HAVING A MINIMUM COMPRESSIVE STRENGTH OF 5,000 psi.
- PROVIDE CLASS A CONCRETE IN ACCORDANCE WITH TABOT TEM 4217


 PROVIDE 60 GRADE REINFORCING STEEL OR EQUIVALENT AREA OF WWR.
- 3. COVER DIMENSIONS ARE CLEAR DIMENSIONS.
- 4. JOINT IN WALLS SHALL BE A 6" MIN FROM TOP OR BOTOM OF BOX CULVERTS CONNECTING TO JUNCTION BOX.
- 5. MANUFACTURE BASE AND RISERS TO NEAREST 3" INCREMENT.
- 6. PROVIDE LIFTING DEVICES IN CONFORMANCE WITH MANUFACTURER'S RECOMMENDATIONS.


INSTALLATION NOTES:

- INVERTS (BENCHING) TO BE PROVIDED BY CONTRACTOR. CONCRETE OR MORTAR USED FOR INVERT IS SUBSIDIARY TO JUNCTION BOX.
- 2. SEAL TONGUE AND GROOVE JOINTS WITH PREFORMED BULK MASTIC IN CONFORMANCE WITH MANUFACTURER'S RECOMMENDATIONS. TONGUE AND GROOVE JOINTS MAY BE GROUTED NO MORE THAN 1" BETWEEN EACH SECTION, OR ½ THE JOINT DEPTH.
- 3. DO NOT GROUT RUBBER GASKET JOINTS WITHOUT MANUFACTURER'S RECOMMENDATION.
- 4. AT BOX CULVERT CONNECTIONS, CAST HOLE 2" MIN, 4" MAX LARGER THAN OUTSIDE DIMENSIONS OF BOX CULVERT.
- 5. FOR MANHOLE, PROVIDE 11/2" CLEAR TO REINFORCEMENT INTERSECTING OR ADJACENT TO HOLE IN LID.

GENERAL NOTES:

- 1. PRECAST JUNCTION BOX CONSISTS OF BASE SLAB, BASE UNIT, RISERS (AS REQUIRED) AND BELOW GRADE SLAB.
- . DESIGNED ACCORDING TO ASTM C913.
- 3. PAYMENT FOR JUNCTION BOX IS PER TXDOT ITEM 465 "JUNCTION BOXES, MANHOLES, AND INLETS" BY TYPE AND SIZE.
- 4. SEE CITY OF AUSTIN STORM DRAIN MANHOLE DETAIL STANDARDS 503S-2S AND 503S-3S FOR MANHOLE COVER DETAILS.








NO. REVISION BY DATE OF THE PROPERTY OF THE PR


POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

> JUNCTION BOX DETAILS 16 FT X 8 FT

 WILLIAMSON COUNTY ROAD BOND PROGRAM

 Drown:
 CBR Designed:
 FKM STATE COUNTY NO.
 CHOCKED:
 CHOCKED:
 TSAS WILLIAMSON — OF —






WILLIAMSON COUNTY ROAD BOND PROGRAM

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

SHEET 1 OF 1

| TEXAS | WILLIAMSON | 34 OF TO

TEXAS REGISTERED



BOX DATA

REINFORCING (sq. in. / ft.) (2)

SECTION DIMENSIONS






POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

	WILLIAMSON	COUNTY	ROAD	BOND	PROGRA	AM
wn:	Designed:		STATE	co	YTNU	SHE

TEXAS

_AS2 _AS7





BY DATE






POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSOI	N COUNT	' ROAD	BOND	PROGRAM	

STATE SHEET 1 OF 1








an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM STATE

SHEET 1 OF 1



1" Min, 3" Max. 1


CONSTRUCTION NOTES:
Do not grout rubber gasket joints without Manufacturer's recommendations.
Do not use bricks, masonry blocks, native stone, or similar materials in conjunction with grouted connections when filling void spaces around pipes or box culverts.

MATERIAL NOTES:

Provide grouted connections in accordance with DMS-4675 "Cementitious Grouts and Mortars for Miscellaneous Application".

Application*.

GENERAL NOTES:
See applicable standards for notes and details not shown:
Precast Base (PB)
Precast Junction Box (PJB)
Precast Sunction Box (PJB)
Precast Safety End Treatments P/D Square (PSET-SC)
Precast Safety End Treatments P/D Square (PSET-SC)
Precast Safety End Treatments P/D Square (PSET-SC)
Provide Concrete Box Culverts in accordance with Item 462
Concrete Box Culverts and Drains.
Provide Reinforced Concrete Pipe (RCP) in accordance with
Item 464 *Reinforced Concrete Pipe*.
Provide Thermoplastic Pipe (TP) in accordance with Special
Specification Thermoplastic Pipe (TP) in accordance with Special
Specification Thermoplastic Pipe.
Payment for grouted connections is considered subsidiary
to other bid Items.







POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

RADILIY MOCONNON

WILLIAMSON COUNTY ROAD BOND PROGRAM

concrete pipe (RCP) —

	5x6	0.29	0.29	9	0.34	0.45	6	48"	0.36	0.45	9	0.47	0.45	9	0.38	0.54	8	48"	0.74	0.57	9	5.5	60/72	60/72
	5x6	0.29	0.29	9	0.34	0.45	6	3x5	0.45	0.45	9	0.47	0.45	9	0.38	0.54	8	3x5	0.61	0.61	9	5.5	60/72	60/72
	6x6	0.29	0.29	9	0.45	0.45	6	3x3	0.41	0.41	9	0.52	0.52	9	0.54	0.54	8	3x3	0.74	0.74	9	6.5	72	72
	6x6	0.27	0.27	9	0.45	0.45	6	4x4	0.45	0.45	9	0.52	0.52	9	0.54	0.54	8	4x4	0.87	0.87	9	6.5	72	72
	6x6 6x6	0.29	0.29	9	0.45	0.45	6	48" 3x5	0.45	0.45	9	0.52 0.52	0.52 0.52	9	0.54	0.54	8	48" 3x5	0.87	0.87	9	6.5 6.5	72 72	72 72
	8x8	0.29	0.29	9	0.43	0.43	8	3x3	0.43	0.43	12	0.52	0.52	9	0.70	0.34	10	3x3	0.87	0.87	12	8.5	96	72
	8x8	0.52	0.52	9	0.51	0.51	8	4x4	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	4x4	1.01	1.01	12	8.5	96	72
	8x8	0.52	0.52	9	0.51	0.51	8	48"	0.70	0.70	12	0.87	0.87	9	0.70	0.70	10	48"	1.01	1.01	12	8.5	96	72
	8x8	0.52	0.52	9	0.51	0.51	8	3x5	0.70	0.85	12	0.87	0.87	9	0.70	0.70	10	3x5	1.01	1.01	12	8.5	96	72
	FABRICATION NOTES: 1. Maximum spacing of reinforcement is 8". Bridge Bridge														Bridge									
														* exas Departm	ent of Trans	portation	Bridge Division Standard							
GENERAL NOTES: 1. Precast Junction Box consists of base slab, base unit, risers (as required), and below grade slab. See sheet PJB for details. 2. Precast Base consists of base slab, base unit, risers (as required), reducing slab (as required), and reduced risers (as required). See sheet PB for details. 3. Min Height shown is for stock base units. Use stock base units whenever practical. Smaller height base units can be used in special installation circumstances, when noted elsewhere in the plans. Absolute minimum height of base units is 2"-6",													DESIGN DATA FOR PRECAST BASE AND JUNCTION BOX											
																				FILE: CD-PDD	0-20.dgn February 2020 REVISIONS		DD CK: TXDOT DW: T JOB	KDOT CK: TXDOT HIGHWAY

Base Slab

Along

0.29

0.47

0.26

0.62

0.52

0.87

0.29

0.47

0.26

0.26

0.26

0.26

0.62

0.62

0.62

0.62

0.45

0.45

BS

6

Bshort

0.24

0.38

0.23

0.39

0.59

0.38

0.54

0.59

0.24

0.38

0.23

0.39

0.39

0.39

0.39

0.59

0.59

0.59

0.59

0.38

0.38

Blong

0.24

0.38

0.59

0.59

0.59

0.54

0.54

0.59

0.24

0.38

0.59

0.59

0.59

0.59

0.59

0.59

0.59

0.59

0.59

0.54

0.54

10

RWSxRWL or ID

N/A

N/A

N/A

N/A

N/A

N/A

N/A

N/A

3x3

4x4

3x5

3x3

4x4

48"

3x5

3x3

4x4

N/A

Dshort

0.37

0.41

0.48

0.42

0.43

0.56

0.45

N/A

N/A

0.46

0.39

0.47

0.48

0.53

0.64

0.64

0.53

0.61

0.74

Dlong

0.37

0.41

0.42

0.43

0.56

0.45

N/A

N/A

0.37

0.48

0.53

0.64

0.64

0.53

0.50

0.57

0.39

TS

N/A

BH MIN

3.5

4.5

4.5

5.5

6.5

8.5

4.5

45

4.5

4.5

5.5

5.5

5.5

5.5

5.5

5.5

HOLE DIA

48

36/60

48/60

60/72

72

96

48

48/60

48/60

48/60

48/60

60

60

60

60/72

60/72

60

KO DIA

36

48

36/60

48/60

60

60/72 72

72

36

48

36/60

48/60

48/60

48/60

48/60

60

60

60

60

60/72

60/72

MAX DEPTH = 15 ft. to top of BASE SLAB

W

6

6

6

Blong

0.19

0.24

0.34

0.34

0.45

0.51

0.19

0.24

0.34

0.34

0.34

0.34

0.34

0.34

0.34

0.34

0.45

0.45

RWSxRWL or ID

N/A

N/A

N/A

N/A

N/A

N/A

N/A

N/A

N/A

3x3

4x4

3x5

3x3

4x4

48"

3x5

3x3

4x4

N/A

Dshort

0.37

0.41

0.48

0.42

0.43

0.48

0.56

0.45

N/A

N/A

0.30

0.30

0.30

0.39

0.33

0.34

0.36

0.36

0.34

0.34

0.36

Dlong

0.37

0.41

0.48

0.42

0.43

0.56

0.45

N/A

N/A

0.34

0.30

0.30

0.39

0.40

0.34

0.36

0.36

0.40

0.34

0.45

TS

N/A

Ashort

0.29

0.47

0.53

0.62

0.52

0.87

0.47

0.53

0.53

0.53

0.53

0.62

0.62

0.62

0.62

0.47

0.47

0.29

Base Slab

Along

0.23

0.29

0.18

0.18

0.36

0.27

0.27

0.46

0.23

0.29

0.18

0.18

0.18

0.18

0.18

0.36

0.36

0.38

0.36

0.31

0.27

BS

Bshort

0.19

0.24

0.19

0.22

0.34

0.34

0.45

0.51

0.19

0.24

0.19

0.22

0.22

0.22

0.22

0.34

0.34

0.34

0.34

0.34

0.34

XxY

8x8

4×4

4x5

5x5

5x5

DISCLAIMER The use of t TxDOT assur

Ashort

0.23

0.29

0.36

0.27

0.27

0.46

0.23

0.29

0.36

0.36

0.36

0.36

0.36

0.36

0.38

0.36

0.31

0.27

0.29

0.36

BRADILEY MOCONNON SEAL EFFECTIVE UPON CITY APPROVAL

an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM

STATE

SHEET 1 OF 1

cpyp cpyp

SHEET 1 OF 2

 WILLIAMSON COUNTY ROAD BOND PROGRAM

 Drown:
 Designed:
 STATE
 COUNTY
 SHEET NO.

 Checked:
 Checked:
 TEXAS
 WILLIAMSON
 40
 OF 103

SEAL EFFECTIVE UPON CITY APPROVAL

NO. REVISION BY DATE

TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

ROADWAY STANDARD DETAILS

No warranty of any kind is made by TxDOT formats or for incorrect results or damage:

ing Practice Act." standard to other


by the

DISCLAIMER: The use of this s TXDOT assumes r

Style	Size (X x Y)	w 2	A x B (nominal)	Short Span Reinf Steel Area	Long Span Reinf Steel Area
SL	3'x3'	6"	n/a	0.37 in²/ft	0.37 in²/ft
RH,RC,RG,SH,S1,FG	3'x3'	6"	3'x3' or 32" Dia	0.37 in²/ft	0.37 in²/ft
SFG	3'x3'	6"	3'x3'	0.32 in²/ft	0.32 in²/ft
SL	4'x4'	6"	n/a	0.34 in ² /ft	0.34 in ² /ft
RH,RC,RG,SH,S1,FG	4'x4'	6"	3'x3' or 32" Dia	0.41 in²/ft	0.41 in²/ft
SH.S1.FG	4' x 4'	6"	4' x 4'	0.41 in ² /ft	0.41 in ² /ft
SFG	4'x4'	6"	4' x 4'	0.32 in ² /ft	0.32 in ² /ft
SL	3'x5'	6"	n/a	0.39 in ² /ft	0.39 in ² /ft
RH.RC.RG.SH.S1.FG	3'x5'	6"	3'x3' or 32" Dia	0.48 in ² /ft	0.48 in ² /ft
SH,S1,FG	3'x5'	6"	3'x5'	0.48 in ² /ft	0.48 in ² /ft
SFG	3'x5'	6"	3'x5'	0.32 in ² /ft	0.32 in ² /ft
SL	4' x 5'	6"	n/a	0.42 in ² /ft	0.42 in ² /ft
RH,RC,RG,SH,S1,FG	4' x 5'	6"	3'x3' or 32" Dia	0.42 in ² /ft	0.42 in ² /ft
SH,S1,FG	4' x 5'	6"	4'x4'	0.63 in²/ft	0.63 in ² /ft
SH,S1,FG	4' x 5'	6"	3' x 5'	0.66 in²/ft	0.66 in²/ft
SL	5'x5'	6"	n/a	0.36 in²/ft	0.36 in²/ft
RH,RC,RG,SH,S1,FG	5' x 5'	6"	3'x3' or 32" Dia	0.43 in ² /ft	0.43 in ² /ft
SH,S1,FG	5' x 5'	6"	4' x 4'	0.63 in²/ft	0.63 in²/ft
SH,S1,FG	5' x 5'	6"	3' x 5'	0.63 in²/ft	0.63 in²/ft
SL	5'x6'	6"/8"	n/a	0.48 in²/ft	0.48 in²/ft
RH,RC,RG,SH,S1,FG	5' x 6'	6"/8"	3'x3' or 32" Dia	0.48 in ² /ft	0.48 in²/ft
SH,S1,FG	5'x6'	6"/8"	4' x 4'	0.60 in²/ft	0.60 in²/ft
SH,S1,FG	5' x 6'	6"/8"	3' x 5'	0.60 in²/ft	0.60 in²/ft
SL	6' x 6'	6"/8"	n/a	0.43 in ² /ft	0.43 in²/ft
RH,RC,RG,SH,S1,FG	6'x6'	6"/8"	3'x3' or 32" Dia	0.56 in²/ft	0.56 in²/ft
SH,S1,FG	6'x6'	6"/8"	4' x 4'	0.56 in²/ft	0.56 in²/ft
SH,S1,FG	6'x6'	6"/8"	3'x5'	0.59 in²/ft	0.59 in²/ft
SL	8' x 3'	8"/10"	n/a	0.45 in²/ft	0.45 in²/ft
RH,RC,RG,SH,S1,FG	8' x 8'	8"/10"	3'x3' or 32" Dia	0.45 in²/ft	0.45 in²/ft
SH,S1,FG	8' x 3'	8"/10"	4' x 4'	0.45 in²/ft	0.45 in²/ft
SH,S1,FG	8' x 8'	8"/10"	3' x 5'	0.45 in ² /ft	0.45 in ² /ft

2) See sheet PDD for corresponding wall thickness (W) of base unit or riser.

Construct cast-in-place reinforced concrete apron, when shown elsewhere in plans. Use Class "A" concrete. Apron is subsidiary to PSL. Apron is 1'-6" Min width around precast zone drain.



DETAIL "A"

(Reinforcing not shown for clarity) When an apron is to be cast around PSL, use detail above to create an apron ledge on all 4 sides.

FABRICATION NOTES:

- FABRICATION NOTES:

 1. Locate penetration (Style 'RH'), ring and cover (Style 'RC'), ring and grate (Style 'RG'), and frame and grate (Style 'FG') in a corner. Only one penetration is allowed per slab lid.

 Provide Class "H" concrete in accordance with Item 421 and having a minimum compressive strength of 5,000 psi.

 Provide Grade 60 reinforcing steel or equivalent area of WWR.

 Provide clear cover of ¾ to reinforcing from lower outside shoulder of slab for structural reinforcement, and 2" from top of slab for shrinkage and temperature reinforcement. Place short span reinforcing closest to surface.

 Slabs with a thickness of 8" or greater require shrinkage and temperature reinforcing. Provide steel area = 0.11 in*Ift each way.

 No substitution is allowed for diagonal #4 bars around openings.

 Design tongue and groove joints for full closure on both shoulders. Minimum spigot depth is ¾.

 Provide lifting devices in conformance with Manufacturer's recommendations.

- 8. Provide lifting devices in conformance with Manufacturer's recommendations.

 INSTALLATION NOTES:

 1. Precast slab lids are intended for direct traffic and may be placed in roadway.

 2. Seal tongue and groove joints with preformed or bulk mastic in conformance with Manufacturer's recommendations. Tongue and groove joints may be grouted no more than 1" between each section, or ½ the joint depth, whichever is greater.

 3. Do not grout rubber gasket joints without Manufacturer's recommendation.

 4. Initial installation of grade adjustment rings for Styles 'RH' and 'SH' is limited to 1'-0" Max as shown.

 5. Grade adjustment rings for Styles 'RH' and 'SH' may be increased to 2'-0" Max when future construction affects final grade of structure. Make adjustments greater than 2'-0" with additional risers. Adjustments can be made up to Max depth shown on sheet PDD. Structure must be evaluated if Max depth will be exceeded. exceeded.
 6. Orient long dimension of grate slots perpendicular to traffic, unless noted otherwise on plans


GENERAL NOTES:

- GENERAL NOTES:

 1. Designed according to ASTM C913.

 2. Payment for lid is per Item 465, "Junction Boxes, Manholes, and Inlets" by type, style, size, and opening size (when applicable).

Cover dimensions are clear dimensions, unless noted otherwise.






BY DATE





POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM STATE TEXAS WILLIAMSON 41 OF 103











POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM

DATE









WILCO



POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM

699 mm (27½") DIA. 660 mm -(26") DIA.

597 mm (23½") DIA.

559 mm (22") DIA.

457 mm— (18") DIA. 419 mm— (16½") DIA. 356 mm— (14") DIA. 317.5 mm— (12½") DIA.

254 mm-(10") DIA. 216 mm-(8½") DIA. 178 mm-(7") DIA.

559 mm (22")

248 mm (9¾")

756 mm (29¾")

762 mm (30")

806 mm (31¾")

CITY OF AUSTIN


LID SECTION VIEW

506S-5

THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.

- FINISH GRADE

WILLIAMSON COUNTY ROAD BOND PROGRAM MRR Designed: MRR STATE AJS Checked: AJS TEXAS WILLIAMSON 44 OF 10



12.5 mm (1/2") BORDER (TYP.)

38 mm (11/2") LETTERS

(RELIEVE SPOKE ENDS 3 mm (1/4") BEYOND LID FOR SEAT MACHINING PURPOSES)

LID SECTION VIEW

STORM DRAIN MANHOLE
RING AND 813 mm (32") COVER

LID PLAN VIEW
MACHINED SURFACE (LID SEAT)

- PICK BAR 3

19 mm (¾")-LETTERS (TYP.)

STANDARD NO.

STANDARD NO.

STANDARD NO.


STANDARD NO.

STANDARD NO.

5035-45

9 mm (¾") - LID WEIGHT③ LETTERS - DATE


3



4-GUSSETS AT 90°

19 mm (¾" LETTERS

- MFG. LOGO - DATE - COUNTRY O ORIGIN



MANHOLE RING

819 mm (321/4")

762 mm (30")


857 mm (33¾")

1,022 mm (40¹/₄")

RING SECTION


MACHINED SURFACE


STORM DRAIN MANHOLE RING AND 813 mm (32") COVEF




WATER AND WASTEWATER UTILITY


RECORD COPY SIGNED BY KATHI F. PAYNE









WILLIAMSON COUNTY ROAD BOND PROGRAM MRR Designed: MRR STATE AJS Checked: AJS TEXAS WILLIAMSON 45 OF 10







TOP MAT

1/2LENGTH OF INLET

150 mm-

(6")

(SYMMETRICAL ABOUT C.L.) 460

PERM. CONSTRUCTION JOINT


225 mm (9") A₇ B₇

/2LENGTH OF INLET LENGTH OF INLET 3 m (10'-0") STANDARD

BOTTOM MAT

- PERMISSIBLE CONSTRUCTION JOINT

(SYMMETRICAL ABOUT C.L.)




CONE FLAT TOP


VARIES

21/2

CITY OF AUSTIN

610 mm (2') MIN.





DETAIL # 1

SIDE ELEVATION SECTION

PLAN VIEW

END ELEVATION SECTION


-GRATE AND FRAME--2 BARS E-

GROUT BOTTOM TO ALLOW-FLOW TO OUTLET PIPE

3'-0"

QTY SIZE SPACING LENGTH WEIGHT





12.5 mm ($\frac{1}{2}$ ") - MFR. LOGO - COUNTRY OF ORIGIN

32 mm (11/4") LETTERS

LID PLAN VIEW
MACHINED SURFACE TILD SEATS

DA'TE CASTING

(RELIEVE SPOKE ENDS 3 mm (1/8") BEYOND LID FOR SEAT MACHINING PURPOSES)

STORM DRAIN MANHOLE
RING AND 813 mm (32") COVER

LID SECTION VIEW

PICK BAR (2)

19 mm (¾")· LETTERS (TYP.)

DEPARTMENT OF WATERSHOP PROTECTION AND DEVELOPMENT HATTER THE ARCHITECT/ENGINEER ASSUMES STANDARD NO.

12.5 mm (1/2") BORDER (TYP.)

19 mm (¾") - LID WEIGHT③ LETTERS - DATE

38 mm (1½") - AUSTIN LETTERS - TEXAS

699 mm (27¹/₂") DIA.

660 mm – (26") DIA. 597 mm (23½") DIA.

559 mm (22") DIA.

457 mm (18") DIA. 419 mm -(16¹/₂'') DIA.

356 mm — (14") DIA. 317.5 mm -(12½") DIA. 254 mm – (10") DIA. 216 mm –

> 813 mm (32") 559 mm (22")


248 mm (9¾'')


756 mm (29¾")

LID SECTION VIEW

CITY OF AUSTIN

762 mm (30") 806 mm (31¾4")





MANHOLE RING

819 mm (321/4")

MACHINED SURFACE

762 mm (30")

857 mm (33¾")


1,022 mm (40¹/₄")


RING SECTION

4-GUSSETS AT 90° (TYP.)

19 mm (¾' LETTERS


- MFG. LOGO - DATE - COUNTRY O






























SHEET 5 OF 5

WILLIAMSON COUNTY ROAD BOND PROGRAM SMW Designed:



1.8m(6'-0")FOR 5' INLET OR 3.4m(11'-0")FOR 10' INLET

1.5m(5'-0")FOR 5' INLET OR 3m(10'-0")FOR 10' INLET

1.5m(5'-0") FOR 5' INLET OR 3m(10'-0") FOR 10' INLET

_13 MM (#4) BARS @ 225 mm (9") O.C.

CURB INLET 1.5m(5')AND3m(10')PRECAST

FOR 1.5m(5') AND 3m(10')NLET (N.T.S.)


A BARS 13 MM (#4) BARS @ 250 mm (10") O.C. B BARS 13 MM (#4) BARS @-225 mm (9") 0.C. 1.1 m (3'-8") LONG


19 MM (#6) BARS © 225 mm (9") O.C. 1.7m(5'-8") LONG FOR 5' INLET 3.2m (10'-8") LONG FOR 10' INLET


150 mm (6") 64 mm (2½")


900 mm (3'-0")


150 mm— (6")














ğβ

inconi

Eng of

₽ p

DISCLAIMER: The use of T TXDOT assumm

4/2⁴

CTODAWATED DOLLUTION D	DEVENTION OF EAST WATER	AOT CEOTION 400		CHI TUDAL DECOUDOES
	PREVENTION-CLEAN WATER		111.	CULTURAL RESOURCES
required for projects with	r Discharge Permit or Constr 1 or more acres disturbed so for erosion and sedimentati	oil. Projects with any		Refer to TxDOT Standard Specifications in the event historical issues or archeological artifacts are found during construction. Upon discovery of archeological artifacts (bones, burnt rock, flint, pottery, etc.) cease
	ay receive discharges from act			work in the immediate area and contact the Engineer immediately. No Action Required Required Action
1. City of Austin				Action No.
2.				ACTION NO.
No Action Required	Required Action			1. If unanticipated archaeological deposits are encountered during
Action No.	_			construction, work in the immediate area will cease, and City of Austin archaeological staff will be contacted to initiate
	tion by controlling erosion	and sedimentation in		post-review discovery procedures.
accordance with TPDES Pe		and dearmentation in		2.
Comply with the SW3P and required by the Engineer	revise when necessary to co.	ontrol pollution or	•.,	VEGET LITTON DESCRIPTION
3. Post Construction Site N	otice (CSN) with SW3P inform	nation on or near	10.	VEGETATION RESOURCES
the site, accessible to	the public and TCEQ, EPA or	other inspectors.		Preserve native vegetation to the extent practical. Contractor must adhere to Construction Specification Requirements Specs 162,
	specific locations (PSL's) submit NOI to TCEQ and the			164, 192, 193, 506, 730, 751, 752 in order to comply with requirements for invasive species, beneficial landscaping, and tree/brush removal commitments.
. WORK IN OR NEAR STREA ACT SECTIONS 401 AND	AMS, WATERBODIES AND WE	ETLANDS CLEAN WATER		☐ No Action Required
	filling, dredging, excavati	ng or other work in any		Action No.
	eks, streams, wetlands or we			1. If unanticipated archaeological deposits are encountered during
The Contractor must adhere the following permit(s):	e to all of the terms and co	nditions associated with		construction, work in the immediate area will cease, and City of Austin archaeological staff will be contacted to initiate post-review discovery procedures.
No Permit Required				2.
Nationwide Permit 14 - wetlands affected)	PCN not Required (less than	1/10th acre waters or		3.
☐ Nationwide Permit 14 -	PCN Required (1/10 to <1/2 o	acre, 1/3 in tidal waters)		4.
☐ Individual 404 Permit R	equired		٧.	FEDERAL LISTED, PROPOSED THREATENED, ENDANGERED SPECIES,
Other Nationwide Permit	Required: NWP#			CRITICAL HABITAT, STATE LISTED SPECIES, CANDIDATE SPECIES AND MIGRATORY BIRDS.
	ers of the US permit applies Practices planned to control			■ No Action Required
1. TRIBUTARY 3 TO LAKE CR	EEK			Action No.
2.				1.
3.				2.
4.				3.
	ary high water marks of any ers of the US requiring the Bridge Layouts.			4.
Best Management Practic	ces:			any of the listed species are observed, cease work in the immediate area, not disturb species or habitat and contact the Engineer immediately. The
Erosion	Sedimentation	Post-Construction TSS	wo	ork may not remove active nests from bridges and other structures during esting season of the birds associated with the nests. If caves or sinkholes
▼ Temporary Vegetation	X Silt Fence	Vegetative Filter Strips	ar	e discovered, cease work in the immediate area, and contact the
Blankets/Matting	X Rock Berm	Retention/Irrigation Systems	En	ngineer immediately.
Mulch	☐ Triangular Filter Dike	Extended Detention Basin		
Sodding	Sand Bag Berm	Constructed Wetlands		LIST OF ABBREVIATIONS
☐ Interceptor Swale	Straw Bale Dike	Wet Basin	BMP:	Best Management Practice SPCC: Spill Prevention Control and Countermeasure
Diversion Dike	Brush Berms	Erosion Control Compost	CGP:	Construction Ceneral Permit SW3P: Storm Water Pollution Prevention Plan Texas Department of State Health Services PCN: Pre-Construction Notification
Erosion Control Compost	Erosion Control Compost	Mulch Filter Berm and Socks	FHWA:	Federal Highway Administration PSL: Project Specific Location Memorandum of Agreement TCEQ: Texas Commission on Environmental Quality
Mulch Filter Berm and Socks	Mulch Filter Berm and Socks	Compost Filter Berm and Socks	MQU:	Memorandum of Understanding TPDES: Texas Pollutant Discharge Elimination System
☐ Compost Filter Berm and Socks	Compost Filter Berm and Socks	_	MBTA:	Municipal Separate Stormwater Sewer System TPMD: Texas Parks and Wildlife Department Migratory Bird Treaty Act TXDOT: Texas Department of Transportation
	Stone Outlet Sediment Traps Sediment Basins	Sand Filter Systems Grassy Swales	NWP:	Notice of Termination TRE: Threatened and Endangered Species Notice of Termination USACE: U.S. Army Corps of Engineers Notice of Intent USPMS: U.S. Fish and Wildlife Service

VI. HAZARDOUS MATERIALS OR CONTAMINATION ISSUES

Comply with the Hazard Communication Act (the Act) for personnel who will be working with hazardous materials by conducting safety meetings prior to beginning construction and making workers aware of potential hazards in the workplace. Ensure that all workers are provided with personal protective equipment appropriate for any hazardous materials used. Obtain and keep on-site Material Safety Data Sheets (MSDS) for all hazardous products used on the project, which may include, but are not limited to the following categories: Paints, acids, solvents, asphalt products, chemical additives, fuels and concrete curing compounds or additives. Provide protected storage, off bare ground and covered, for products which may be hazardous. Maintain product labelling as required by the Act. Maintain an adequate supply of on-site spill response materials, as indicated in the MSDS In the event of a spill, take actions to mitigate the spill as indicated in the MSDS, in accordance with safe work practices, and contact the District Spill Coordinator immediately. The Contractor shall be responsible for the proper containment and cleanup of all product spills.

- Contact the Engineer if any of the following are detected:

 * Dead or distressed vegetation (not identified as normal)

 * Trash piles, drums, canister, barrels, etc.

 * Undesirable smells or odors

- * Evidence of leaching or seepage of substances

Does the project involve any bridge class structure rehabilitation or replacements (bridge class structures not including box culverts)?

☐ Yes 🔀 No

If "No", then no further action is required. If "Yes", then TxDOT is responsible for completing asbestos assessment/inspection.

Are the results of the asbestos inspection positive (is asbestos present)?

Yes

If "Yes", then TxDOT must retain a DSHS licensed asbestos consultant to assist with the notification, develop abatement/mitigation procedures, and perform management activities as necessary. The notification form to DSHS must be postmarked at least 15 working days prior to scheduled demolition.

If "No", then TxDOT is still required to notify DSHS 15 working days prior to any scheduled demolition.

In either case, the Contractor is responsible for providing the date(s) for abatemen activities and/or demolition with careful coordination between the Engineer and asbestos consultant in order to minimize construction delays and subsequent claims.

Any other evidence indicating possible hazardous materials or contamination discovered

ite.	Hazardous Materials or	Conta	mination	Issues	Specif
No	Action Required		Required	Action	1
Action	No.				
١.					

VII. OTHER ENVIRONMENTAL ISSUES

(includes regional issues such as Edwards Aquifer District, etc.)

No Action Required

X Required Action

1. Project is within the Edwards Aquifer Recharge Zone. No additional impervious cover is being added as a result of this project. Ensure TCEQ construction regulations are being followed.

2.

Texas Depai	rtment of 1	Transport	tation	Standard
ENVIRO	NMEN'	TAL	PER	MITS,
ISSUES	AND	СОМ	міт	MENTS

EPIC

ILE: epic.dgn	DN: Txl	TOC	ck: RG	DW:	VP	ck: AR
C TxDOT: February 2015	CONT	SECT	JOB		н	GHWAY
REVISIONS 2-12-2011 (DS)						
5-07-14 ADDED NOTE SECTION IV.	DIST		COUNTY			SHEET NO.
1-23-2015 SECTION I (CHANGED ITEM 1122 O ITEM 506, ADDED GRASSY SWALES.	AUS	US WILLIAMSON 61			31	





POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ENVIRONMENTAL PERMITS, ISSUES AND COMMITMENTS (EPIC)

WILLIAMSON COUNTY ROAD BOND PROGRAM MRR Designed: MRR STATE Checked: AJS Checked: AJS TEXAS WILLIAMSON 61 OF 10

Design Division

2. PROJECT SITE MAPS:

- * Project Location Map: The Title Sheet
- * Drainage Patterns: Drainage Area Maps (Sheets 21-23)
- * Slopes Anticipated After Major Gradings or Areas of Soil Disturbance: Typical Sections (Sheets 8-IO)
- * Location of Erosion and Sediment Controls: SW3P Site Maps (Sheets 66-68)
- * Surface Waters and Discharge Locations: Drainage Plans (Sheets 26-29)
- * Project Specific Location(s) (PSL): To be determined by the project Construction Personnel. Location(s) shown on SW3P Site Map (If PSL location(s) is within one mile of project) and information located in project SW3P Binder (Reference Item #10 below).

3. PROJECT DESCRIPTION:

CONSTRUCTION OF STORM DRAIN IMPROVEMENTS CONSISTING OF STREET REPAIRS AND STRUCTURES.

4. MAJOR SOIL DISTURBING ACTIVITIES:

Install controls down-slope of work area and initiate inspection and maintenance activities.

Beain phased construction with interim stabilization practices. Adjust erosion and sedimentation controls during construction to meet requirements and changing conditions and as directed/ approved by the Engineer.

Major soil disturbing activities may include but are not limited to: right-of-way preparation, cut and/or fill to improve roadway profile, final grading and placement of topsoil and the following (if marked) installing culverts.

5. EXISTING CONDITION OF SOIL & VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER:

Crawford Clay (53%), Eckrant cobbly clay (22%), Fairlie clay (26%), 10% vegetative cover

6. TOTAL PROJECT AREA: 0.38 Acres

7. TOTAL AREA TO BE DISTURBED: 0.32 Acres (84 %)

8. WEIGHTED RUNOFF COEFFICIENT

BEFORE CONSTRUCTION: AFTER CONSTRUCTION:

9. NAME OF RECEIVING WATERS:

All runoff associated with this project drains into Lake Creek Tributary 3 which drains into Lake Creek Seament No. 1244B, Brushy Creek Seament No. 1244, San Gabriel River Segment No. 1214, Little River Segment No. 1213, the Brazos River Segment No. 1242, the Brazos River segment No. 1202, and ultimately, into the Gulf of Mexico.

10. PROJECT SW3P Binder:

A. For projects disturbing one to five acres, The Contractor will maintain a SW3P Binder at the project field office (If there is not a project field office, should be kept on the Job Site at all times) which contains the following: Index Sheet, TCEQ Signature Authority, TCEQ Small Construction Site Notice, Contractor Certification of Compliance, SW3P Inspector Qualification Statements, Inspection and Maintenance Reports (Form 2118), SW3P Sheet, Site Location Maps, Stored Material Lists specifying associated control measures and the Appendix which contains the TPDES Construction General Permit, MS4 Operator Notification(s) and the Construction PSL Permits per all applicable requirements.

B. For projects disturbing 5 acres or more, the Contractor will follow the actions listed in (IO.A.) above with the addition of the following: Notice Of Intent (N.O.I.) and Fee Payment Form, TCEQ Large Construction Site Notice (to be used instead of Small Site Notice), and TPDES Permit Coverage Notice.

C. For projects disturbing less than one acre, actions described in (IO.A.) and (IO.B.) above are not required. Acreage is calculated by adding Total Area To Be Disturbed Acres on project (See *7 above) and the PSL(s) acreage located within one mile of project.

B. EROSION AND SEDIMENT CONTROLS

1. <u>SOIL STABILIZATION PRACTICES</u>: (Select_T = Temporary or P = Permanent, as

MULCHING (Hay or Straw)

BUFFER ZONES

____ PLANTING

SEEDING

SODDING

PRESERVATION OF NATURAL RESOURCES

FLEXIBLE CHANNEL LINER

RIGID CHANNEL LINER

SOIL RETENTION BLANKET

COMPOST MANUFACTURED TOPSOIL

VERTICAL TRACKING

OTHER: Disturbed areas on which Construction activity has ceased, either temporarily or permanently, shall be stabilized within 14 days unless activities are scheduled to resume and do so within 21 days.

2. STRUCTURAL PRACTICES:

- = Temporary or P = Permanent) _______ SILT FENCES

 - EROSION CONTROL COMPOST BERMS (Low Velocity)
 - _____ EROSION CONTROL (
 - DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
 - DIVERSION, INTERCEPTOR, OR PERIMETER SWALES DIVERSION DIKE AND SWALE COMBINATIONS

 - ____ PIPE SLOPE DRAINS
 - PAVED FLUMES
 - ROCK BEDDING AT CONSTRUCTION EXIT
 - TIMBER MATTING AT CONSTRUCTION EXIT
 - CHANNEL LINERS
 - SEDIMENT TRAPS
 - SEDIMENT BASINS
 - STORM INLET SEDIMENT TRAP
 - STONE OUTLET STRUCTURES
 - CURBS AND GUTTERS
 - P STORM SEWERS
 - ____ VELOCITY CONTROL DEVICES
 - ____ OTHER:

NOTE: TOP OF BMP'S SHOULD NOT BE HIGHER THAN ROADWAY ELEVATION AS NOT TO FLOOD ROADWAY UNLESS PRIOR APPROVAL FROM ENGINEER IS OBTAINED.

3. STORM WATER MANAGEMENT:

- A. Storm water drainage will be provided by ditches, inlets, and storm water systems which carry drainage within the R.O.W. to the lows within the roadway and project site which drains to natural facilities.
- B. Non paved areas and ditches shall be stabilized with a permanent veaetative cover.

4. STORM WATER MANAGEMENT ACTIVITIES: (Sequence of Construction)

- I, INSTALL SILT FENCES AND ROCK BERMS, PREPARE R.O.W. BEGIN EXCAVATION AND EMBANKMENT.
- 2. INSTALL ALL CROSS CULVERTS AND STORM DRAIN FACILITIES.
- 3. WHEN ALL CONSTRUCTION ACTIVITY IS COMPLETE AND THE SITE IS STABLE AND APPROVED BY THE CONSTRUCTION ENGINEER, REMOVE ALL TEMPORARY CONTROLS AND SOD ANY AREAS DISTURBED BY THEIR REMOVAL.

5. NON-STORM WATER DISCHARGES:

Filter non-storm water discharges, or hold in retention basins, before being allowed to mix with storm water. These discharges consist of, but not limited to, non-polluted ground water, spring water, foundation or footing drain water, water used for dust control or pavement washing and vehicle washwater containing no deteraents.

C. OTHER REQUIREMENTS & PRACTICES

1. MAINTENANCE:

Maintain all erosion and sediment controls in good working order. Perform any necessary cleaning/repairs/replacements at the earliest possible date prior to next rain event, but no later than 7 calendar days. Ensure the surrounding ground has dried sufficiently to prevent damage from equipment. "Too Wet" is the only reason for not adhering to time frames described. When construction activities permanently or temporarily cease and are not expected to resume for I4 or more days on a disturbed portion of the site, stabilization measures must be initiated immediately,

A Construction Observer will perform a regularly scheduled SW3P inspection every 7 calendar days, An Inspection and Maintenance Report, signed by the Construction Observer and the Contractor, will be filed for each inspection. Revise/clean/repair/replace each BMP control device in accordance with the current Field Inspection and Maintenance Report (Form 2118) and Item I (Maintenance) above.

3. WASTE MATERIALS:

On a daily basis, or as may be directed, collect all waste materials, trash and debris from the construction site and deposit into a metal dumpster having a secure cover and which meets all state and local city solid waste management requirements. Empty the dumpster as required by regulation, or as may be directed, at a local approved landfill site. Do not bury construction waste on the construction project site.

4. HAZARDOUS WASTE & SPILL REPORTING:

As a minimum, any products in the following categories are considered to be hazardous: Paints, Acids, Solvents, Fuels, Asphalt Products, Chemical Additives for Soil Stabilization, and Concrete Curing Compounds or Additives. When storing hazardous material on the project site, or at a Project Specific Location, take all practicable precaution to prevent and/or contain any spillage of these materials. In the event of a spill, contact the spill coordinator immediately.

5. SANITARY WASTE:

Use a licensed sanitary waste management contractor to collect all sanitary waste from portable units as may be required by local regulation, or as directed.

6. CONSTRUCTION VEHICLE TRACKING:

On a regular basis, or as may be directed, dampen haul roads for dust control and stabilize construction entrances/exits. Provide for a motorized broom or vacuum type sweeper to be available on a daily basis, or as may be directed, to remove sediment from paved roadways abutting or traversing the project site.

7. MANAGEMENT PRACTICES:

- A. Construct disposal areas, stockpiles, haul roads and PSL's in a manner that will minimize and control the amount of sediment that may enter receiving waters. Do not locate disposal areas in any wetland, waterbody or streambed.
- B. Locate construction staging areas, vehicle maintenance and PSL's areas in a manner to minimize the runoff of pollutants.
- C. When working in or near a wetland, install and maintain operating soil erosion and sediment controls at all times during construction and isolate the work from the wetland.
- D. Clear all waterways as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.
- E. Procedures and/or practices should be taken to control dust.
- F. Sediment to be removed from roadways daily or when work begins after weather events if construction activities have ceased due to weather event.
- G. The Contractor will be required to contain wash water from concrete trucks in a manner that will prevent same from entering any waterway.
- H. The Contractor is responsible for insuring that all Subcontractors are aware and comply with all components of the Temporary Erosion Control Plans.



BY DATE an STV Company TEXAS REGISTERED

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD STORM WATER POLLUTION PREVENTION PLAN (SW3P)

WILLIAMSON COUNTY ROAD BOND PROGRAM

SHEET 1 OF 1

MRR Designed: MRR STATE Checked: AJS Checked: AJS TEXAS WILLIAMSON 62 OF 10

Texas Commission on Environmental Quality Water Pollution Abatement Plan General Construction Notes

Edwards Aquifer Protection Program Construction Notes - Legal Disclaimer

The following/listed "construction notes" are intended to be advisory in nature only and do not constitute an approval or conditional approval by the Executive Director (ED), nor do they constitute a comprehensive listing of rules or conditions to be followed during construction. Further actions may be required to achieve compliance with TCEQ regulations found in Title 30, Texas Administrative Code (TAC), Chapters 213 and 217, as well as local ordinances and regulations providing for the protection of water quality. Additionally, nothing contained in the following/listed "construction notes" restricts the powers of the ED, the commission or any other governmental entity to prevent, correct, or curtail activities that result or may result in pollution of the Edwards Aquifer or hydrologically connected surface waters. The holder of any Edwards Aquifer Protection Plan containing "construction notes" is still responsible for compliance with Title 30, TAC, Chapters 213 or any other applicable TCEQ regulation, as well as all conditions of an Edwards Aguifer Protection Plan through all phases of plan implementation, Failure to comply with any condition of the ED's approval, whether or not in contradiction of any "construction notes," is a violation of TCEQ regulations and any violation is subject to administrative rules, orders, and penalties as provided under Title 30, TAC § 213.10 (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. The following/listed "construction notes" in no way represent an approved exception by the ED to any part of Title 30 TAC, Chapters 213 and 217, or any other TCEQ applicable regulation

- A written notice of construction must be submitted to the TCEQ regional office at least 48 hours prior to the start of any regulated activities. This notice must include:
 - the name of the approved project;
 - the activity start date: and
 - the contact information of the prime contractor.
- All contractors conducting regulated activities associated with this project must be provided with complete copies of the approved Water Pollution Abatement Plan (WPAP) and the TCEQ letter indicating the specific conditions of its approval. During the course of these regulated activities, the contractors are required to keep on-site copies of the approved plan and approval letter.
- If any sensitive feature(s) (caves, solution cavity, sink hole, etc.) is discovered during construction, all regulated activities near the sensitive feature must be suspended immediately. The appropriate TCEQ regional office must be immediately notified of any sensitive features encountered during construction. Construction activities may not be resumed until the TCEQ has reviewed and approved the appropriate protective measures in order to protect any sensitive feature and the Edwards Aquifer from potentially adverse impacts to water quality.
- No temporary or permanent hazardous substance storage tank shall be installed within 150 feet of a water supply source, distribution system, well, or sensitive feature.
- Prior to beginning any construction activity, all temporary erosion and sedimentation (E&S) control measures must be properly installed and maintained in accordance with the approved plans and manufacturers specifications. If inspections indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations. These controls must remain in place until the disturbed areas have been permanently stabilized.
- Any sediment that escapes the construction site must be collected and properly disposed of before the next rain event to ensure it is not washed into surface streams, sensitive features,
- Sediment must be removed from the sediment traps or sedimentation basins not later than

TCEQ-0592 (Rev. July 15, 2015) Page 1 of 2 when it occupies 50% of the basin's design capacity.

- Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from being discharged offsite.
- All spoils (excavated material) generated from the project site must be stored on-site with proper E&S controls. For storage or disposal of spoils at another site on the Edwards Aquifer Recharge Zone, the owner of the site must receive approval of a water pollution abatement plan for the placement of fill material or mass grading prior to the placement of spoils at the other site.
- If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity will resume prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day. stabilization measures shall be initiated as soon as possible.
- 11. The following records shall be maintained and made available to the TCEQ upon request:
 - the dates when major grading activities occur;
 - the dates when construction activities temporarily or permanently cease on a portion of the site; and
 - the dates when stabilization measures are initiated.
- 12. The holder of any approved Edward Aquifer protection plan must notify the appropriate regional office in writing and obtain approval from the executive director prior to initiating any of the following:
 - any physical or operational modification of any water pollution abatement structure(s), including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
 - any change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aguifer;
 - any development of land previously identified as undeveloped in the original water pollution abatement plan.

Austin Regional Office 12100 Park 35 Circle, Building A Austin, Texas 78753-1808 Phone (512) 339-2929 Fax (512) 339-3795

San Antonio Regional Office 14250 Judson Road San Antonio, Texas 78233-4480 Phone (210) 490-3096 Fax (210) 545-4329

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

TCEQ-0592 (Rev. July 15, 2015) Page 2 of 2







POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD EROSION AND SEDIMENT CONTROL GENERAL CONSTRUCTION NOTES

	WILLIAMSON		COUN	TY ROAD	BOND	PROGRA	AM
Drawn:	AUR	Designed:	AUR	STATE	cou	NTY	SHEET NO.

SHEET 1 OF 1 Checked: AJS Checked: AJS TEXAS WILLIAMSON 63 OF 103

WATER QUALITY TRANSITION ZONE(WQTZ) WQTZ OUTSIDE OF 100-YEAR FLOODPLAIN (NON-FP WQTZ) = 0 ACRES ALLOWABLE IMPERVIOUS COVER IMPERVIOUS COVER ALLOWS AT **ACRES** IMPERVIOUS COVER ALLOWS AT 90 % X(NET SITE AREA) = 3.538 ACRES TOTAL ALLOWED IMPERVIOUS COVER = 3.538 ACRES PROPOSED IMPERVIOUS COVER IMPERVIOUS COVER IN NON-FP WQTZ EXISTING PROPOSED TO REMAIN = 0 ACRES 5b PROPOSED NEW = 0 ACRES SUBTOTAL = 0 ACRES 5c IMPERVIOUS COVER IN UPLANDS ZONE EXISTING PROPOSED TO REMAIN = 2.250 ACRES 6b PROPOSED NEW = 0 ACRES SUBTOTAL = 2.250 ACRES 6с

8		US COVER BREAKDOWN REAGE WITH SLOPES 15			= <u> </u>
	PROPOSED IMPERVIOU	JS COVER ON SLOPES	IMPE	ERVIOUS COVER	
			BUILDING &	OTHER IMPERVIOUS COVER	DRIVES/ ROADWAYS
	SLOPE CATEGORIES	ACRES	ACRES	% OF CATEGORY	ACRES
9	0-15%	2.25	0	0.00%	2.25
10	15-25%		0	0.00%	0
11	25-35%		0	0.00%	0
12	>35%	O	0	0.00%	0
1.3	GROSS SITE AREA	3 9309			

TOTAL PROPOSED IMPERVIOUS COVER = 2.250 ACRES







POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD COA ENVIRONMENTAL CRITERIA MANUAL APPENDIX Q-1 & Q-2 TABLES


	WILL	IAMSON	COUN	TY ROAD	BOND	PROGRA	AM
Drawn:	MSB	Designed:	MSB	STATE	co	UNTY	SHEET NO.


SHEET 1 OF 1 Checked: AJS Checked: AJS TEXAS WILLIAMSON 64 OF 10































WILCO





POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

EROSION AND SEDIMENTATION CONTROL PLAN STA 62+00.00 TO END

SP-2024-0324D







GENERAL NOTES



IO. REVISION BY DATE

WILCO



POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

 WILLIAMSON COUNTY ROAD BOND PROGRAM

 Designed:
 STATE
 COUNTY
 SHEET NO.

 Charled:
 TEXAS
 WILLIAMSON
 70.0F 1.03

Flow Galvanized Woven Wire Mesh (for Types 2 & 3) Excavation (If shown on construction drawings) Width for paymen -Earth embankment SEE NOTE 6 A "V" Shape may be used for higher velocity flows. (See "V" Shape Plan View below) FILTER DAM AT CHANNEL SECTIONS

FILTER DAM AT SEDIMENT TRAP

Width for Payment

Length

PROF [LE

SECTION C-C

Rock Filter Dams should be constructed downstream from disturbed areas to intercept sediment from overland runoff and/or concentrated flow. The dams should be sized to filter a maximum flow through rate of 60 CPM/FT² of cross sectional area. A 2 year storm frequency may be used

Type 1 (18" high with no wire mesh) (3" to 6" aggregate): Type 1 may be used at the toe of slopes, around inlets, in small ditches, and at dike or swale outlets. This type of dam is recommended to control erosion from a drainage area of 5 acres or less. Type 1 may not be used in concentrated high velocity flows (approximently 8 Ft/Sec or more) in which aggregate wash out may occur. Sandbags may be used at the embedded foundation (4" deep min.) for better filtering efficiency of low flows if called for on the plans or directed by the Engineer.

 $\underline{\text{Type 2}}$ (18" high with wire mesh) (3" to 6" aggregate): $\underline{\text{Type 2}}$ may be used in ditches and at dike or swale outlets.

Type 5: Provide rock filter dams as shown on plans.

Type 3 (36" high with wire mesh) (4" to 8" aggregate): Type 3 may be used in stream flow and should be secured to the stream bed.

_Level Crested Weir

______ OR ________

Galvanized woven

Open graded rock

ROCK FILTER DAM USAGE GUIDELINES

Types 1 & 2 = 18"

Type 3 • 36*

- If shown on the plans or directed by the Engineer, filter dams should be placed near the toe of slopes where erosion is anticipated, upstream and/or downstream at drainage structures, and in roadway ditches and channels to collect sediment.
- Materials (aggregate, wire mesh, sandbags, etc.) shall be as indicated by the specification for "Rock Filter Dams for Erosion and Sedimentation Control".
- 3. The rock filter dom dimensions shall be as indicated on the SW3P plans.
- 4. Side slopes should be 2:1 or flatter. Dams within the safety zone shall
- 5. Maintain a minimum of 1' between top of rock filter dam weir and top of embankment for filter dams at sediment traps.
- 6. Filter dams should be embedded a minimum of 4" into existing ground.
- The sediment trap for ponding of sediment laden runoff shall be of the dimensions shown on the plans.
- 8. Rock filter dom types 2 & 3 shall be secured with 20 gauge galvanized woven wire mesh with 1" diameter hexagonal openings. The aggregate shall be placed on the mesh to the height & slopes specified. The mesh shall be folded at the upstream side over the aggregate and tightly secured to itself on the downstream side using wire ties or hog rings. For in stream use, the mesh should be secured or staked to the stream bed prior to aggregate placement.
- 9. Sack Gabions should be staked down with $\frac{1}{4}$ " dia. rebar stakes, and have a double-twisted hexagonal weave with a nominal mesh opening of 2 ½" x 3 ½"
- 10. Flow outlet should be onto a stabilized area (vegetation, rock, etc.).

PLAN SHEET LEGEND

Type I Rock Filter Dam -RFD1-

Type 4 Rock Filter Dom -RFD4-

SEDIMENT AND WATER ROCK FILTER DAMS


LO	٠.	•				
FILE: ec216	DN: TxE	ЮT	ck: KM	DW:	۷P	DN/CK: LS
C TxDOT: JULY 2016	CONT	SECT	JOB			HIGHWAY
REVISIONS						
	DIST		COUNTY			SHEET NO.

Type 3 Rock Filter Dom -RFD3-

TEMPORARY EROSION. POLLUTION CONTROL MEASURES

FC(2)-16

LO	٠.	•				
FILE: ec216	DN: TxE	ЮT	ck: KM	DW:	۷P	DN/CK: LS
C TxDOT: JULY 2016	CONT	SECT	JOB			HIGHWAY
REVISIONS						
	DIST		COUNTY			SHEET NO.






POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM

STATE



DATE



 $-\!($ cl-gi $)\!-\!$ EROSION CONTROL LOG AT CURB & GRATE INLET

TEMP. EROSION CONTROL LOG

FLOW

ENGINEER.

ADDITIONAL UPSTREAM

BACK OF CURB

STAKES FOR HEAVY

RUNOFF EVENTS

- DISTURBED AREA

- TEMP. EROSION CONTROL LOG

- COMPOST CRADLE UNDER FROSTON

CONTROL LOG

- STAKE

(TYP.)

ADDITIONAL UPSTREAM STAKES FOR HEAVY -RUNOFF EVENTS

SECURE END OF LOG TO STAKE AS

STAKE.

GENERAL NOTES:

- 1. EROSION CONTROL LOGS SHALL BE INSTALLED IN ACCORDANCE WITH MANFACTURER'S RECOMMENDATIONS, OR AS DIRECTED BY THE ENGINEER.
- LENGTHS OF EROSION CONTROL LOGS SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND AS REQUIRED FOR THE PURPOSE INTENDED.
- 3. UNLESS OTHERWISE DIRECTED, USE BIODEGRADABLE OR PHOTODEGRADABLE CONTAINMENT MESH ONLY WHERE LOG WILL REMAIN IN PLACE AS PART OF A VEGETATIVE SYSTEM. FOR TEMPORARY INSTALLATIONS, USE RECYCLABLE CONTAINMENT MESH.
- FILL LOGS WITH SUFFICIENT FILTER MATERIAL TO ACHIEVE THE MINIMUM COMPACTED DIAMETER SPECIFIED IN THE PLANS WITHOUT EXCESSIVE DEFORMATION.
- STAKES SHALL BE 2" X 2" WOOD OR #3 REBAR, 2'-4' LONG, EMBEDDED SUCH THAT 2" PROTRUDES ABOVE LOG, OR AS DIRECTED BY
- THE ENGINEER.

 6. DO NOT PLACE STAKES THROUGH CONTAINMENT
- 7. COMPOST CRADLE MATERIAL IS INCIDENTAL & WILL NOT BE PAID FOR SEPARATELY.
- 8. SANDBAGS USED AS ANCHORS SHALL BE PLACED ON TOP OF LOGS & SHALL BE OF SUFFICIENT SIZE TO HOLD LOGS IN PLACE.
 TURN THE ENDS OF EACH ROW OF LOGS UPSLOPE
- TO PREVENT RUNOFF FROM FLOWING AROUND THE
- 10. FOR HEAVY RUNOFF EVENTS, ADDITIONAL UPSTREAM STAKES MAY BE NECESSARY TO KEEP LOG FROM FOLDING IN ON ITSELF.

SECTION C-C EROSION CONTROL LOG AT EDGE OF RIGHT-OF-WAY

STAKE ON DOWNHILL SIDE OF LOG AT 8' (ON CENTER) MAX. AS NEEDED TO SECURE LOG,

TEMPORARY

-DISTURBED AREA

LIP OF GUTTER

LOG

BACK OF CURB

OR AS DIRECTED BY THE

ENGINEER.

PLAN VIEW

TEMP. EROSION CONTROL LOG

COMPOST CRADIF

UNDER EROSION CONTROL LOG

SEDIMENT BASIN & TRAP USAGE GUIDELINES

<u>Log Traps</u>: The drainage area for a sediment trap should not exceed 5 acres. The trap capacity should be 1800 CF/Acre (0.5" ove the drainage area).

Control logs should be placed in the following locations:

1. Within drainage ditches spaced as needed or min, 500' on center

2. Immediately preceding ditch inlets or drain inlets

Cleaning and removal of accumulated sediment deposits is incidental and

3. Just before the drainage enters a water course
4. Just before the drainage leaves the right of way
5. Just before the drainage leaves the construction

depth of 1/2 the log diameter.


will not be paid for separately.

limits where drainage flows away from the project.

The logs should be cleaned when the sediment has accumulated to a

FLOW







SHEET 1 OF 3

DN:TXDOT CK: KM DW:LS/PT CK:LS







an STV Company TEXAS REGISTERED

RADINY MOCONNON

SEAL EFFECTIVE UPON


CITY APPROVAL

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD ROADWAY STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM


SHEET 1 OF 3






RADILIY MOCONNON

SEAL EFFECTIVE UPON CITY APPROVAL



WILLIAMSON COUNTY ROAD BOND PROGRAM



an STV Company

TEXAS REGISTERED ENGINEERING FIRM F-1741 POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

ROADWAY STANDARD DETAILS

2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.

3. THE TRENCH MUST BE A MINIMUM OF 150 mm (6 Inches) DEEP AND 150 mm (6 Inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.


4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE , WHICH IS IN TURN ATTACHED TO THE STEEL OR WOOD FENCE POST.


5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.


6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 Inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

CITY OF AUSTIN WATERSHED PROTEOTION DEPARTMENT	SILT FENCE					
Muy 5. My 9/1/2011	THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD.	standard no. 642S-1				










an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

EROSION AND SEDIMENTATION CONTROL STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM MRR Designed: MRR STATE

SHEET 1 OF 3







an STV Company TEXAS REGISTERED ENGINEERING FIRM F-1741


POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD

CONCRETE WASHOUT STANDARD DETAILS

WILLIAMSON COUNTY ROAD BOND PROGRAM

SHEET 3 OF 3

WILLIAMSON COUNTY ROAD BOND PROGRAM



FENCE LOCATION PRIOR TO CLEARING, GRADING AND PAVING

TREES IN PAVING AREA -- MINIMUM NESESSARY WORK AREA (WOOD CHIP MULCH 100 TO 150 mm (4" TO 6" DEPTH)

BLDG.

TREES NEAR CONSTRUCTION ACTIVITY

GROUP OF TREES

TREE PROTECTION FENCE LOCATIONS

THE ARCHITECT/ENGINEER ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE
OF THIS STANDARD.

FENCE LOCATION DURING PERMEABLE PAVING INSTALLATION

-C.R.Z.

STANDARD NO.

6 10S-1

TEMPORARY ACCESS ROAD, EXISTING ROADWAY

WOOD CHIP MULCH AREA OR EASEMENT 100 mm-150 mm AS APPROVED (4"-6") DEPTH

LINEAR CONSTRUCTION THROUGH TREES

NATURAL AREAS


CRITICAL ROOT ZONE (C.R.Z.)
RADIUS = 12 mm PER mm
(1 FT. PER INCH)
OF TRUNK DIAMETER


INDIVIDUAL TREE


CITY OF AUSTIN

LIMIT OF CONSTRUCTION LINE

AS SHOWN ON PLAN







an STV Company

TEXAS REGISTERED ENGINEERING FIRM F-1741

POND SPRINGS ROAD DRAINAGE IMPROVEMENTS 13062 1/2 POND SPRINGS RD TREE PROTECTION FENCE STANDARD DETAILS

SP-2024-0324D


POND SPRINGS ROAD - ROXIE DRIVE CROSS SECTIONS (FOR CONTRACTORS INFORMATION ONLY)


MM Designed: MM STATE Checked: BJ Checked: QJ TEXAS WILLIAMSON


10 5 0

SCALE HORIZ. & VERT. FEET

NOTES: THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION. 2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.







TEXAS REGISTERED ENGINEERING FIRM F-1741

Williamson


NOTES:


THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED
SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE
INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR
TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SCALE HORIZ. & VERT. FEET

10 5 0





TEXAS REGISTERED ENGINEERING FIRM F-1741

Williamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

Drawn:
SHEET 2 OF 15 Checked:

 POND
 SPRINGS ROAD DRAINAGE IMPROVEMENTS 132062
 TOTAL POND SPRINGS RD

 Drown:
 MM
 Designed:
 MM
 STATE
 COUNTY

 Checked:
 BJ
 Checked:
 QJ
 TEXAS
 WILLIAMSON


THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.


TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SCALE HORIZ. & VERT. FEET

10 5 0





TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIIamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

Drawn: N


80


NOTES:

. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

10 5 0 10 20 SCALE HORIZ. & VERT. FEET





TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

Drawn: M
SHEET 4 OF 15 Checked: E

 POND
 SPRINGS 132062
 ROAD DRAINAGE IMPROVEMENTS RD

 Drawn:
 MM
 Designed:
 MM
 STATE
 COUNTY
 SHEET NO.

 Checked:
 BJ
 Checked:
 QJ
 TEXAS
 WILLIAMSON
 81


NOTES:


1. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SCALE HORIZ. & VERT. FEET

10 5 0





TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

Drawn:
SHEET 5 OF 15 Checked:

82


10 5 0

SCALE HORIZ. & VERT. FEET

NOTES: THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.


> POND SPRINGS ROAD - ROXIE DRIVE CROSS SECTIONS (FOR CONTRACTORS INFORMATION ONLY)


MM Designed: MM STATE Checked: BJ Checked: QJ TEXAS WILLIAMSON 83



TEXAS REGISTERED ENGINEERING FIRM F-1741

NOTES: THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION. 2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.






NOTES:


 THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SCALE HORIZ. & VERT. FEET

10 5 0





TEXAS REGISTERED ENGINEERING FIRM F-1741

W Illiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

Drawn:
SHEET 8 OF 15 Checked:

 NOTES:

1. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

920 7 - - 90

-80

-70

-60


-50


-40

-30

-20

10 5 0 10 20 SCALE HORIZ. & VERT. FEET





-10 0 10

20

30

50

60

70

CPAY

TEXAS REGISTERED ENGINEERING FIRM F-1741

W illiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)

| Drawn: M | SHEET 9 OF 15 | Checked: |


十 920


100


 NOTES:

1. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.







CP ₄	
EXAS REGISTERED ENGINEERING FIRM F-1741	



POND SPRINGS ROAD - ROXIE DRIVE	
CROSS SECTIONS	
(FOR CONTRACTORS INFORMATION	ONLY)


. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.


TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.

SCALE HORIZ. & VERT. FEET

10 5 0





TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)


SHEET 11 OF 15 Checked:


. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.







TEXAS REGISTERED ENGINEERING FIRM F-1741

W illiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)


Drawn:


SHEET 12 OF 15 Checked:

. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.







TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIiamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS


(FOR CONTRACTORS INFORMATION ONLY)


Drawn:
SHEET 13 OF 15 Checked:

. THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.







TEXAS REGISTERED ENGINEERING FIRM F-1741

Williamson

POND SPRINGS ROAD - ROXIE DRIVE

CROSS SECTIONS

(FOR CONTRACTORS INFORMATION ONLY)


Drawn:
SHEET 14 OF 15 Checked:

| Table | Tabl

THE UTILITY INFORMATION SHOWN IS PROVIDED BY OTHERS AND IS REPRESENTATIVE. THIS INFORMATION WAS OBTAINED SOLELY FOR THE USE OF THE ENGINEERING DESIGN OF THE PROJECT. THE ACCURACY AND SUFFICIENCY OF THE INFORMATION SHOWN IS NOT GUARANTEED. THE CONTRACTOR SHALL FIELD VERIFY UTILITY LIMITS AND LOCATIONS PRIOR TO CONSTRUCTION.

2. VERTICAL LOCATION OF UTILITIES IS APPROXIMATE AND SHOULD BE FIELD VERIFIED PRIOR TO CONSTRUCTION.





TEXAS REGISTERED ENGINEERING FIRM F-1741

W IIIiamson

POND SPRINGS ROAD - ROXIE DRIVE CROSS SECTIONS (FOR CONTRACTORS INFORMATION ONLY)

MM Designed: MM STATE Checked: BJ Checked: QJ TEXAS WILLIAMSON

SUMMARY OF SHEET INDEX:

COVER

GENERAL NOTES 94

95 SUMMARY OF WATER LINE QUANTITIES

OVERALL LAYOUT

97 AW GRID MAP

98 WATERLINE "A" RELOCATION 99 WATER SERVICE RELOCATION WATERLINE CALCULATIONS 100 101 STANDARD WATER DETAILS

102-103 ASBESTOS CEMENT PIPE CONNECTION DETAILS

(C)ORRECT, (A)DD, (V)OID SHEET NUMBERS

DATE



WILLIAMSON COUNTY POND SPRINGS ROAD DRAINAGE IMPROVEMENTS WATER LINE RELOCATIONS 100% DESIGN

TOTAL LENGTH OF PROJECT: 180 LF PROJECT LIMITS: POND SPRINGS DRIVE FROM SCHICK ROAD TO ROXIE DRIVE

CONSTRUCTION OF 8" MAIN, AND 2" SERVICE WATER LINE INSTALLED VIA OPEN TRENCH, REQUIRED APPURTENANCES, AND CONNECTIONS TO THE EXISTING 8" WATER LINE.



VICINITY MAP (NOT TO SCALE)



OWNER: **AUSTIN WATER** 625 E. 10TH ST AUSTIN, TEXAS 78701

CONTACT: WALE ODUFUYE, P.E. 512-974-7119

DESIGNER: COBB FENDLEY 9600 N. MOPAC EXPRESSWAY, SUITE 800 AUSTIN, TEXAS 78759

CONTACT: HEATHER BYRNE, P.E. 512-646-4351

SUBMITTED FOR APPROVAL:



NOTE: SEAL EFFECTIVE UPON PERMIT APPROVAL

03/05/2025

HEATHER BYRNE, P.E.

DATE

APPROVALS:

CHRIS POUSSON AUSTIN WATER



512.834.9798 | FAX 512.834.9553 WWW.COBBFENDLEY.COM

REVISION DESCRIPTION

Use of Electronic Files General Disclaimer: Use of the attached files in any manner indicates your acceptance of terms and conditions as set forth below. If you do not agree to all of the terms and conditions, please contact Austin Water Pipeline Engineering, project coordinator prior to use of the referenced information. Please be advised that the attached files are in a format that can be altered by the user. Due to this fact, any reuse of the data will be at the user's sole risk without liability or legal exposure to the City of Austin and user shall indemnify and hold harmless The City of Austin from all claims, damages, losses and expenses including attorney's fees arising out of or resulting from using the digital file. In addition, it is the responsibility of the user to compare all data with the PDF version of this drawing. In the event there is a conflict between the PDF version drawing and the electronic file, the PDF version drawing shall prevail.

Automated Metering Infrastructure: Effective March 2022, new water meters installed shall be in conformance with AW's automated metering infrastructure technology, and with the applicable standard product list. Applicants filing a site plan or subdivision plan will be required to coordinate with the Austin Water Plan Reviewer for details on approval and installation.

Prior to the handling and disposal of Asbestos Pipe, the Contractor's work plans will be reviewed and coordinated through Austin Water's Asbestos Program Manager who can be reached at \$25.275.2951. It is the Contractor's responsibility to utilize a trained, certified and licensed Asbestos Abatement Contractor in accordance with the Federal, State and Local regulations.

Modifications to Austin Water signed and stamped sheets are not permitted. All design modifications will need to be submitted via the ABC portal for a Plan Correction or Revision. All unethical engineering practices, including modifying CI Stamped plan sheets, shall be reported to the Texas Board of Professional Engineers and Land Surveyors (PEL).

Texas Engineering Practice Act and Rules, Subchapter C: Professional

AW INFRASTRUCTURE INFORMATION				
PROPOSED PRODUCT TYPE (TO BE INSTALLED)	LENGTH OF PIPE (L.F.)	SIZE OF PIPE (INCH)	NO. OF SERVICES	
WATER MAIN	96	8	NA	
WASTEWATER MAIN	NA	NA	NA	
RECLAIMED WATER MAIN	NA	NA	NA	
WATER SERVICE	NA	NA	1	
WASTEWATER SERVICE	NA	NA	NA	
RECLAIMED WATER SERVICE	NA	NA	NA	

UC CASE #: 2024-107311 SP ROW ID:

PROJECT INFORMATION¹

GRID NUMBER:	G37
MAPSCO NUMBER:	434T
AW INTERSECTION NUMBER:	15895
UILDING SIZE IN SQUARE FEET:	NA
UILDING TYPE PER IFC:	NA
UILDING HEIGHT:	NA
VAILABLE FIRE FLOW CALCS AT 20 PSI:	NA
EQUIRED BUILDING FIRE FLOW PER IFC TABLE B105.1(2):	NA
EDUCED FIRE FLOW PER% FIRE SPRINKLER EDUCTION PER IFC TABLE B105.2:	NA
NINIMUM FIRE FLOW (SEE NOTE #2 BELOW):	NA
OMESTIC WATER DEMAND IN GPM:	NA
VATER SUPPLY FIXTURE UNITS (WSFU) FLUSH TANKS OR LUSHOMETERS (CIRCLE APPLICABLE ITEM):	NA
USTIN WATER PRESSURE ZONE:	NWB1
TATIC WATER PRESSURE IN PSI:	NA
TATIC PRESSURE AT THE HIGHEST LOT SERVED IN PSI:	NA
TATIC PRESSURE AT THE LOWEST LOT SERVED IN PSI:	NA
AXIMUM IRRIGATION DEMAND:	NA
RE LINE VELOCITY:SIZE OF FIRE LINE	NA
OMESTIC LINE VELOCITY:SIZE OF DOMESTIC LINE	NA
VING UNIT EQUIVALENTS (LUEs)	NA

1. WITH THE EXCEPTION OF PROVIDING THE REQUIRED INFORMATION, DO NOT REVISE THESE TABLES IN ANYWAY.

2. MIN FIRE FLOW: DESIGN ENGINEER MUST INDICATE VALUES WHICH COMPLY WITH IT CTABLES BIDS.1(2) OR BIDS.2 (REQUIRED OR REDUCES OR REFLOWS), MIN FIRE FLOW VALUE SHALL BE NO LESS THAN 1,000 GPM FOR NFPA 13 SYSTEMS OR 1300 GPM FOR NFPA 1300 GPM FOR NFPA 1300

Meter Notice:

Meter 1.5 inches and larger must be purchased and ordered 90 days in advance of installation.

Meter(s) Requirement for Project:

Address:

Proposed Use: Type:

GPM Range:

Service Units:

Meter(s) Requirement for Project:

Address:

Proposed Use: Type:

GPM Range: Size:

Service Units:

Reclaimed Meter(s) Requirement for Project:

Address: Proposed Use:

Size:

GPM Range:

INSPECTION NOTES

Please contact Development Services Department, Site and Subdivision Inspection at sitesubintake@austintexa arrangements for payment of Inspection fees and job assignment for Inspection of the public utilities to this site. Inspe-must be paid before any Pre-construction meeting can be held.

STANDARD CONSTRUCTION NOTES

October 1, 2021

1. THE CITY STANDARD CONSTRUCTION SPECIFICATIONS CURRENT AT THE TIME OF BIDDING SHALL COVER MATERIALS AND METHODS USED TO DO THIS WORK.
2. CONTRACTOR MISTOR STORMAN A ROW PERMIT FROM AUSTIN TRANSPORTATION DEPT, RIGHT OF WAY MANAGEMENT DWISION BEFORE BEGINNING CONSTRUCTION WITHIN THE RIGHT-OF-WAY SHALL COMPLY WITH PAPPOVED TOF.
3. AT LEAST 48 HOURS PRIOR TO BEGINNING DAY UTILITY CONSTRUCTION ACTIVITY IN PUBLIC ROW OR PUBLIC EASEMENT, THE CONTRACTOR SHALL NOTIFY THE APPLICABLE CITY OF A USIN'S INSPECTION GROUP (LIGHTS THAN TRANSPORTATION, DEVELOPMENT SERVICES, ON PUBLIC VENEXIS, SEE CURRENT NOTIFICATION REQUIREMENTS AT WAY AUSTINITEAS. SOV.
4. THE CONTRACTOR SHALL CONTACT THE AUSTIN AREA "ONE CALL" SYSTEM AT -809-344-357 FOR EXISTING UTILITY LOCATIONS PRIOR TO MAY EXCAVATION IN ADMANGE. OF CONSTRUCTION. THE CONTRACTOR SHALL VERRY THE LOCATIONS OF ALL UTILITIES TO BE EXTENDED. TIED TO, OR ALTERD, ON SUBJECT TO ADMANGE. THE CONSTRUCTION OF PERMIT DISD AT I COMPLEX SERVICES.

AND ADMANGEMENT OF THE CONSTRUCTION OPERATIONS. THE CITY OF AUSTIN WATER AND WASTENANCE RESPONSIBILITY BIDS AT I COMPLEX SEMENT.

ANATOMIC ON CHIEF CONSTRUCTION OPERATIONS. THE COUNTING OF ALL DISTRICTS TO BE EXTENDED. HELD JULY OF ALTERED. ON SUBJECT TO WAS A COUNTING.

5. NO OTHER UTILITY SERVICE INFORMATION OPERATIONS. THE PROPERTY LIKE, OR OTHER ASSIGNED LOCATION DESIGNATED FOR WATER AND WASTEWATER SAFELY SERVICE SERVICE.

6. MINIMUM TRENCH SAFETY MEASURES SHALL BE PLACED HEAR THE PROPERTY LIKE, OR OTHER ASSIGNED LOCATION DESIGNATED FOR WATER AND WASTEWATER SERVICES.

7. ALL MATERIALS TESTS GONDERO BY THE OWNER FOR QUALITY ASSURANCE PURPOSES, SHALL BE CONDUCTED BY AN INDEPENDENT LABORATORY AND FUNDED BY ALL MATERIALS TESTS OMER OF THE ASSURANCE SHALL BE PLACED BY OSTABLE THE OFFICE OF THE OWNER OWNER OF THE OWNER OF THE OWNER OWNER OF THE OWNER OWNER OF THE OWNER OWNER

TRUCTION PLANS.
THE CONTRACTOR SHALL VERIFY ALL VERTICAL AND HORIZONTAL LOCATIONS OF EXISTING UTILITIES, BELOW GROUND AND OVERHEAD, PRIOR TO STARTING ONSITE

14. THE CONTRACTOR SHALL VERIFY ALL VERTICAL AND HORIZONTAL LOCATIONS OF EXISTING UTILITIES, BELOW GROUND AND OVERHEAD, PRIOR TO STARTING ONSITE UTILITY WORK.

15. ALL WATER, WASTEWATER, AND RECLAIMED MAINS SHALL BE INSTALLED IN ACCORDANCE WITH THE SEPARATION DISTANCES INDICATED ON THE PLANS, PER UTILITY CRITICAL AND TECH CHAPTERS 210, 217, AND 280.

16. PROJECT-SPECIFIC SHOP DRAWINGS SHALL BE SUBMITTED FOR AW APPROVAL FOR PRE-CAST CIRCULAR VERTICAL MAINHOLE SECTIONS LARGER THAN 48" DIAMETER. THE SHOP DRAWINGS SHALL INCIDENT THE FLOW THAT ALL CONNECTION PRES, ELEVATION OF OF TRANSITIONS AND ACRE DIAMETER SECTIONS; TOP OF MAINIOLE AND SURROUNDING GROUND ELEVATIONS; AND DETAILS OF SPECIAL CONSTRUCTION CONSIDERATIONS SPECIFIED IN THE CONTRACT DOCUMENTS.

DIAMETER SECTIONS; TOP OF MANHOLE AND SURROUNDING ROUND ELEVATIONS; AND DETAILS OF SPECIAL CONSTRUCTION CONSIDERATIONS SPECIFIED IN THE CONTRACT DOCUMENTS.

CONTRACT DOCUMENTS.

MICHAEL AGRESS THAT HE HAD THE PROPERTY OF T

INSTALLED. 22. METER BOXES AND CLEAN OUTS SHALL NOT BE LOCATED WITHIN PAVED AREAS SUCH AS DRIVEWAYS AND SIDEWALKS.

AUSTIN WATER REVIEW BLOCK

AW EXPIRATION STAMP THREE YEARS FROM THE DATE OF SIGN-OFF

0 **E**

A N AND SITES INFORMATION COMMERCIAL S PLANS ENERAL I R GE OTES UBDI AUSTIN WATER CONSTRUCTION NO SU

Ü

CITY OF AUSTIN AUSTIN WATER October 2021

0

12. Z

VERSION 2 TANDARD I 1 OF 1

S

₩ S

CobbFendley

NOTES

GENERAL

S RD DRAINAGE IN AUSTIN, TEXAS

POND

BLOCK



SHEET

	509-A	510-AW-2"-W	510-AWRJ-8"-W	510-AWRJ-12"-W	510-JW-12"X8"	510-KW	511-A-8"	510-BW-2"x2" Dia.	SP510-JW-AC-8"x8"	SP510-JW-CI-12"x12"	SP1900-W8Dia
LOCATION	Safety Protection	∪la.Copper Type	all depths, Complete in Place,	Pipe, 12" Dia. DI CL- 350 (Restrained), all depths, Complete in Place, Including Excavation and Backfill	Wet	Ductile Iron Fittings (C-110 Weight Schedule)	Valves, Gate 8" Dia.	Water Service Reconnection, including 2" Corporation Stop, Tap to Main, as well as removal of the existing components	8" Dia. x 8" Dia.	CI Pipe Connections, 12" Dia. x 12" Dia.	Removing Pipe, 8" Diameter, AC Pipe - For Removal at Storm Crossings, Required Restrained Joints, to Existing Couplings, and Other Areas Specified on Plans; Pipe Removal shall include the cost of trench and pavement repairs, Complete and in place; Removal of valves considered subsidiary to cost of pipe removal
	LF	LF	LF	LF	EA	TON	EA	EA	EA	EA	LF
97	183		96	20	1	0.12	1		1	1	92
98	53	53						1			
Total	236	53	96	20	1	0.12	1	1	1	1	92







SUMMARY OF WATER LINE QUANTITIES POND SPRINGS RD DRAINAGE IMPROVEMENTS AUSTIN, TEXAS

PROJ. NO. 1903-099-2 DESIGN: H. BYRNE DRAWN: H. BYRNE CHECK: C. WEEKS APPR: H. BYRNE DATE: 4/23/2025



THESE DESIGN DOCUMENTS ARE NOT TO USED FOR CONSTRUCTION PRIOR TO REGULATORY SIGNATURE AND PERMI







CobbFendley

AW GRID MAP







PRIOR TO HANDLING AND DISPOSAL OF ASBESTOS PIPE, THE CONTRACTOR'S WORK PLANS WILL BE REVIEWED AND COORDINATED THROUGH OMAR ALMOUSLLI, THE AUSTIN WATER ASBESTOS PROGRAM MANAGER WHO CAN BE REACHED AT (512) 974-7137. IT IS THE CONTRACTOR'S RESPONSIBILITY TO UTILIZE A TRAINED, CERTIFIED AND LICENSED ASBESTOS ABATEMENT CONTRACTOR IN ACCORDANCE WITH THE FEDERAL, STATE AND LOCAL REGULATIONS.



EX. WATER T.B.R. PR. WATER VALVE (XX) EX. WATER VALVE PR. FIRE HYDRAN EX. FIRE HYDRANT PR. AIR RELEASE W EX. WATER METER VALVE

EX. FENCE

EX. OVERHEAD UTILITIES

EX. OVERHEAD TELECOM

FX. U.G. TELECOM

EX. U.G. ELECTRIC

GENERAL NOTES:

1. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES THAT MIGHT BE OCCASIONED BY THE FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES WHEN THE CONTRACTOR IS USING TRENCHLESS INSTALLATION METHODS, THE CONTRACTOR SHALL LOCATE ALL UTILITIES FOR THE ENTIRE LENGTH OF THE INSTALLATION PRIOR TO ANY ACTIVITIES. ANY DISCREPANCIES FROM WHAT IS SHOWN SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ENGINEER.

- CONTRACTOR TO GIVE CITY OF AUSTIN A MINIMUM OF TWO WEEKS NOTICE FOR ALL WATERLINE SHUTDOWNS. SHUTDOWNS MUST OCCUR ONLY DURING THE MONTHS OF DECEMBER, JANUARY, AND FEBRUARY.
- EXISTING 8" & 12" WATER MAINS ARE TO BE PROTECTED AND REMAIN IN SERVICE UNTIL THE NEW MAINS ARE CONSTRUCTED, TESTED, APPROVED AND SERVICE LINES RECONNECTED AND THE NEW MAIN IS PLACED IN SERVICE.
- 4. EXISTING WATER SERVICE LINES AND METERS ARE TO BE PROTECTED AND REMAIN I SERVICE UNTIL NEW SERVICE LINES ARE CONSTRUCTED, TESTED, APPROVED AND RECONNECTED AND IN SERVICE.
- 5. EXISTING WATER MAINS THAT ARE TO BE ABANDONED IN PLACE AND ARE UNDER THE PROPOSED ROADWAY ARE TO BE CUT, CAPPED, AND FILLED WITH FLOWABLE FILL SUBSIDIARY TO COST OF PIPE, NO SEPARATE PAY. EXISTING WATER LINES THAT ARE TO BE ABANDONED IN PLACE AND ARE NOT UNDER THE PROPOSED ROADWAY WILL
- 6. CONNECTION LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL LOCATE THE EXISTING COUPLINGS ON THE AC PIPE, MAKE CONNECTIONS, AND REMOVE THE AMOUNT OF AC PIPE AS SHOWN PER DETAIL ON SHEETS 102 - 103.
- 7. EXISTING ASBESTOS CEMENT WATER MAIN(S) IS TO BE PROTECTED AND REMAIN IN SERVICE UNTIL THE NEW DUCTILE IRON MAIN(S) IS CONSTRUCTED, TESTED, APPROVE AND THE SERVICE LINES RECONNECTED AND THE NEW MAIN IS PLACED IN SERVICE.
- 8. AN APPROVED CITY OF AUSTIN ASBESTOS CONSULTING FIRM WILL NEED TO BE RETAINE TO OVERSEE THE WORK ACTIVITIES AND DOCUMENT AIR QUALITY. THE CONTRACTOR IS RESPONSIBLE TO RETAIN A LICENSED CONTRACTOR FAMILIAR WITH CITY OF AUSTIN PROCEDURES FOR ANY ACTIVITY DISTURBING THE EXISTING AC PIPE.
- THE DEPARTMENT OF STATE HEALTH SERVICES MUST BE CONTACTED 10 DAYS PRIOR T THE START OF ANY ABATEMENT WORK.
- 10. EXISTING ASBESTOS CEMENT PIPE TO BE REMOVED FROM JOINT TO JOINT. PIPE REMOVA SHALL INCLUDE THE COST OF TRENCH AND PAVEMENT REPAIRS, AS WELL AS ALL OTHE INCIDENTALS NECESSARY TO COMPLETE THE PIPE REMOVAL
- WATERLINES TO BE INSTALLED PRIOR TO ROADWAY CONSTRUCTION. MINIMUM DEPTH OF COVE SHOWN IS TO FINISHED GRADE. CONTRACTOR SHALL INSTALL VALVES AND HYDRANTS AS SHOWN. ADJUSTMENTS TO FINISHED GRADE MAY BE NECESSARY DURING ROADWAY CONSTRUCTION.
- 12. CONTRACTOR TO VERIFY SIZES OF WATER LINES, SERVICE LINES, AND METERS PRIOR TO INSTALLATION AND NOTIFY ENGINEER OF ANY DISCREPANCIES.

GRADE FLOW LI

PROFILE SCALE 1"=40' HORIZ. 1"=4' VERT

endley obbF


END 0 8ш STA. 10+1 PROFILE ST ∞ INE "A" PLAN

WATE

U



SHEET



LEGEND

EX. RIGHT-OF-WAY

CobbFendley

 $\overline{\alpha}$

SERVICE

WATER

PR. RIGHT-OF-WAY ---- TEMP. CONST. ESMT. EX. EDGE OF PAVEMENT PR. EDGE OF PAVEMENT ULTIMATE PAVEMENT -- W-----FX. WATER PR. WATER EX. WASTEWATER EX. STORM DRAIN PR. STORM DRAIN EX. GAS LINE EX. OVERHEAD ELECTRIC EX. OVERHEAD CABLE EX. OVERHEAD UTILITIES EX. OVERHEAD TELECOM EX. U.G. TELECOM EX. U.G. ELECTRIC EX. FENCE EX. WATER T.B.R.

PR. WATER VALVE (XX) EX. WATER VALVE EX. FIRE HYDRANT PR. FIRE HYDRAN PR. AIR RELEASE W EX. WATER METER VALVE

GENERAL NOTES:

1. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY OF ALL EXISING UILINES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES THAT MIGHT BE COCASIONED BY THE FAILURE TO EXACITY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. WHEN THE CONTRACTOR IS USING TRENCHLESS INSTALLATION METHODS, THE CONTRACTOR SHALL LOCATE ALL UTILITIES FOR THE ENTIRE LENGTH OF THE INSTALLATION PRIOR TO ANY ACTIVITIES, ANY DISCREPANCIES FROM WHAT IS SHOWN SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE ENGINEER.

- CONTRACTOR TO GIVE CITY OF AUSTIN A MINIMUM OF TWO WEEKS NOTICE FOR ALL WATERLINE SHUTDOWNS. SHUTDOWNS MUST OCCUR ONLY DURING THE MONTHS OF DECEMBER, JANUARY, AND FEBRUARY.
- EXISTING 8" & 12" WATER MAINS ARE TO BE PROTECTED AND REMAIN IN SERVICE UNTIL THE NEW MAINS ARE CONSTRUCTED, TESTED, APPROVED AND SERVICE LINES RECONNECTED AND THE NEW MAIN IS PLACED IN SERVICE.
- 4. EXISTING WATER SERVICE LINES AND METERS ARE TO BE PROTECTED AND REMAIN I SERVICE UNTIL NEW SERVICE LINES ARE CONSTRUCTED, TESTED, APPROVED AND RECONNECTED AND IN SERVICE.
- 5. EXISTING WATER MAINS THAT ARE TO BE ABANDONED IN PLACE AND ARE UNDER THI PROPOSED ROADWAY ARE TO BE CUT, CAPPED, AND FILED WITH FLOWABLE FILL.
 SUBSIDIARY TO COST OF PIPE, NO SEPARATE PAY, EXISTING WATER LINES THAT ARE
 TO BE ABANDONED IN PLACE AND ARE NOT UNDER THE PROPOSED ROADWAY WILL
 BE CAPPED.
- 6. CONNECTION LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL LOCATE THE EXISTING COUPLINGS ON THE AC PIPE, MAKE CONNECTIONS, AND REMOVE THE AMOUNT OF AC PIPE AS SHOWN PER DETAIL ON SHEETS 102 - 103.
- 7. EXISTING ASBESTOS CEMENT WATER MAIN(S) IS TO BE PROTECTED AND REMAIN IN SERVICE UNTIL THE NEW DUCTILE IRON MAIN(S) IS CONSTRUCTED, TESTED, APPROVE AND THE SERVICE LINES RECONNECTED AND THE NEW MAIN IS PLACED IN SERVICE.
- 8. AN APPROVED CITY OF AUSTIN ASBESTOS CONSULTING FIRM WILL NEED TO BE RETAINE TO OVERSEE THE WORK ACTIVITIES AND DOCUMENT AIR QUALITY. THE CONTRACTOR IS REPORTED TO RETAIN A LICENSED CONTRACTOR FAMILIAR WITH CITY OF AUSTIN PROCEDURES FOR ANY ACTIVITY DISTURBING THE EXISTING AC PIPE.
- THE DEPARTMENT OF STATE HEALTH SERVICES MUST BE CONTACTED 10 DAYS PRIOR T THE START OF ANY ABATEMENT WORK.
- 10. EXISTING ASBESTOS CEMENT PIPE TO BE REMOVED FROM JOINT TO JOINT. PIPE REMOVA SHALL INCLUDE THE COST OF TRENCH AND PAVEMENT REPAIRS, AS WELL AS ALL OTHE INCIDENTALS NECESSARY TO COMPLETE THE PIPE REMOVAL
- WATERLINES TO BE INSTALLED PRIOR TO ROADWAY CONSTRUCTION. MINIMUM DEPTH OF COVE SHOWN IS TO FINISHED GRADE. CONTRACTOR SHALL INSTALL VALVES AND HYDRANTS AS SHOWN. ADJUSTMENTS TO FINISHED GRADE MAY BE NECESSARY DURING ROADWAY CONSTRUCTION.
- CONTRACTOR TO VERIFY SIZES OF WATER LINES, SERVICE LINES, AND METERS PRIOR TO INSTALLATION AND NOTIFY ENGINEER OF ANY DISCREPANCIES.



PROFILE SCALE

1"=40' HORIZ. 1"=4' VERT.

GRADE FLOW LI

SHEET 99

contractor shall restrain the next joint beyond the required restraint at no additional 2. The first length listed is for the large diameter side of reducer, and second length

is for the small side of reducer.

Settings: Pipe Material DI (Polywrapped) **Laying Condition** Type 5 COH-GRAN Soil Designation Depth of Cover (FT) Design Pressure (psi) 200 Safety Factor 1.5



WATERLINE CALCULATIONS





AND 18" FROM FINISHED GRADE.

RECLAIMED WATER. ALL RECLAIMED PVC PIPE SHALL BE MANUFACTURED PURPLE PIPE. HDDE PIPE

SHALL BE MANUFACTURED WITH PURPLE STRIPES. ALL OTHER PIPE AND APPURTENANCES SHALL BE

MANUFACTURED PURPLE IF AVAILABLE. ALL PIPE AND FITTINGS THAT ARE NOT AVAILABLE FROM THE

MANUFACTURED IN PURPLE SHALL BE PRAINTED UPPLE FER SHE, WAYSO, ALL BURDED IAND GIPPE

AND FITTINGS SHALL ALSO BE WRAPPED IN PURPLE POLYETHYLENE PER SPL WW-27D. ALL COVERS

SHALL HAVE TRECLAIMED WATER CAST INTO THEM.


LISTIN WATER


TYPICAL GATE VALVE 4" - 16"


AUSTIN WATER AUSTIN WAITER


RECORD COPY SIGNED
BY KATHIL FLOWERS
05/18/2016
ADOPTED

THE ENGINEER/ANGURIECT ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE
0F THIS STANDARD DIRECTATIONS TO
11-AW-01
1 0F 4











Z CORPORATION STOP, SPI, WW-88
Z PLOPE WATER SERVICE TUBING, SPI, WW-85
Z* BALL VALVE, SPI, WW-88
SINGLE SERVICE: Z* MPR X 1" COPPER FLARE FITTING, SPI, WW-88
OR DOUBLE SERVICE: Z* MPR X 1" COPPER FLARE WYE, SPI, WW-88
1" SWIVEL NUT X 1" COMPRESSION 90" SEMD, SPI, WW-88
1" HOPE WATER SERVICE TUBING, SPI, WW-85
1" ANGLE METER STOP, SPI, WW-95
ANGLE METER BOX AND LID, SWI WH-145X
POR DUAL, 1" METERS. USE TWO SINGLE METER BOXES

MATERIALS TO BE INSTALLED BY PLUMBER:

J. BRASS METER BUSHING: SUZE AS NEEDED TO CONNECT ANGLE METER STOP TO METER

K. WATER METER PURCH-AGES PROM AUSTIN WATER

L. BRASS WATER METER GOUPLING MALE IPT X SWIVEL COUPLING NUT:

\$\frac{\partial}{2}\text{AND} \text{ WATER METERS 6}\frac{\partial}{2}\text{ COUPLING NUT:}

\$\frac{\partial}{2}\text{AND} \text{ WATER METERS 6}\frac{\partial}{2}\text{ COUPLING NUT:}

M. PROPERTY OWNERS OUT OFF VALVE. SPL WAY-20

M. PROPERTY OWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY OWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY OWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY OWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY OWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VALVE BOX AND 20

M. PROPERTY DOWNERS OUT OFF VAL

NOTES:

SERVICE CLAMP SHALL BE WRAPPED COMPLETELY WITH 8 MIL. POLYETHYLENE FILM, SPL WW-27D.
BRANCH CONNECTIONS AND ALL ANGLE METER STOPS MUST BE INSTALLED PRIOR TO ANY METER
TOP OF METER BOXES SHOULD BE A BBOVE GROUND.
PIPING AND TUBING IN STREET RIGHT-OF-WAY SHALL BE BEDDED IN GRANULAR MATERIALS AS
REQUIRED BY SECTION 5103 (4) OF THE CITY OF AUSTIN STANDARD SPECIFICATIONS; BACKFILL
ABOVE GRANULAR BEDDING AS REQUIRED BY SECTION 5103 (25).
METER BOX MAST BE BEHAND CARN BOXT TO PROPERTY LINE OR EASEMENT AND OUT OF VEHICULAR

TRAFFICAREA AND SIDEWILK.

TRAFFICAREA AND SIDEWILK.

BALL VAIVE "O' SHALL NOT BE LOCATED UNDER SIDEWALK, CURB, OR PAVEMENT, AND NOT BE LOCATED UNDER SIDEWALK, CURB, OR PAVEMENT, AND NOT BE LOCATED UNDER SIDEWALK, CURB, OR PAVEMENT, AND NOT BE METER SIZES TO BE SHOWN ON PLANS.

LOCATED MORE THAN 5'S BELOW FIRM, GRADE.

METER SIZES TO BE SHOWN ON PLANS.

METER BOX CUT OUTS SHALL NOT EXCENDED THE STHE PIPE DIAMETER.

METER BOX CUT OUTS SHALL NOT EXCENDED.

METER BOX CUT OUTS SHALL NOT EXCENDED.

TO SHALL VALVE "TWO-CAPE THAN STATE, SP. WH-597, MINIMOM 1' ABOVE TUBING FROM SERVICE CLAMP "A".

TO SHALL VALVE "TWO-CAPE THAN STATE, SP. WH-597, MINIMOM 1' ABOVE TUBING FROM SERVICE CLAMP "A".


TO SHALL SE PLACED IN A STRAIGHT ALIGNMENT AND ALLOWED TO RELAX AND "SINAKE".


LOOSELY IN THE TRENCH. TUBING SENION CUTS BAND GUTTER SHALL SE INSTALLED WITH A MINIMOM 2' DEPTH OF COVER.

"I "TUBING, WHEN BENT, SHALL HAVE A RADIUS NO SMALLER THAN 3'.2" TUBING, WHEN BENT, SHALL HAVE A RADIUS NO SMALLER THAN 5'. SIRASS FITTINGS SHALL NOT SE CONNECTED TO A BENT SECTION OF TUBINAN SHALL SHALL INSERT STIFFENERS FOR HOPE TUBING SHALL SHALL

COMPRESSION IN LINEAR, INSERT STITUTED STATES ALL RECLAIMED TUBING SHALL BE MANUFACTURED COMPRESSION FITTING USED. YES AND WETERS, ALL RECLAIMED TUBING SHALL BE MANUFACTURED DURINE FOR AULA PROVINCIANNOES SHALL BE MANUFACTURED PURPLE F AVAILABLE ALL HITTINGS THAT ARE NOT AVAILABLE FROM THE MANUFACTURED IN PURPLE SHALL BE FAINTED PURPLE FROM THE FAINTED FOR THE AND HAVE "RECLAIMED WATER" CAST INTO THEM, SYL WA-19A. ALL METER BOX LIDS SHALL BE PURPLE AND HAVE "RECLAIMED WATER" CAST INTO THEM, SYL WA-19A.

CITY OF AUSTIN		WATER SERVICE & METER II	NSTALLATION -
AUSTIN WATER		1" & SMALLER MET	ERS
RECORD COPY SIGNED JEFF A. KYLE	08/16/2019 ADOPTED	THE ENGINEER/ARCHITECT ASSUMES RESPONSIBILITY FOR APPROPRIATE USE OF THIS STANDARD MODIFICATIONS TO THIS STANDARD ARE PROHIBITED.	STANDARD NO. 520-AW-011 2 OF 2









IMPROVEMENTS

RD DRAINAGE IN AUSTIN, TEXAS


CobbFendley




SIGN: H. BYRNE AWN: H. BYRNE IECK: C. WEEKS PR: H. BYRNE



SHEET




PROPOSED 8"x8" OFFSET CONNECTION




ASBESTOS CEMENT PROPOSED OFFSET CONNECTION DETAILS PROP. 8" D.I. PIPE CONNECTION TO EXIST. 8" A.C. PIPE





PROPOSED 12"x8" BRANCH OFFSET CONNECTION



*PAYMENT ITEM SP510-JW-AC TO INCLUDE ALL WORK FROM TYING INTO EXISTING COUPLINGS, BRANCH CONNECTION, AND MATERIALS AND LABOR TO MAKE CONNECTION TO EXISTING A.C. AND C.I. SYSTEM.

CAST IRON TO ASBESTOS CEMENT BRANCH CONNECTION DETAILS - 12"x8" OFFSET BRANCH CONNECTION

NTS



ESE DESIGN DOCUMENTS ARE NOT TO BE USED FOR CONSTRUCTION PRIOR TO REGULATORY SIGNATURE AND PERMIT.

SHEET 103



Attachment E – Request to Temporarily Seal a Feature

Not applicable.



Attachment F – Structural Practices

Sediment derived from excavation and grading will be controlled through the use of rock filter dams, erosion control logs, sediment control fence, and inlet protection.



Attachment G – Drainage Area Map

See the attached Drainage Area Map sheets included with **Attachment D – Temporary Best Management Practices and Measures** of this section.



Attachment H – Temporary Sediment Pond(s) Plans and Calculations

Not applicable.



Attachment I – Inspection and Maintenance for BMP's

The key to maintaining the performance of and efficiency of the temporary BMPs is inspection and repair when needed. The project will use an established schedule of inspection to identify the weak or failing sections of the sediment controls and institute repairs immediately to ensure the continued performance of the installed BMPs. BMPs will be inspected at least once every fourteen (14) calendar days and within twenty four (24) hours of the end of a storm of 0.5 inches or greater. An inspection and maintenance report shall be prepared and maintained onsite by qualified personnel. Damaged BMPs will either be repaired or replaced as needed. If storms damage the BMPs, efforts will be made immediately to restore them to original performance levels. Should damage exceed the capacity to repair during storm events, alternate methods such as temporary fiber rolls or rock dams will be available. Other inspection and maintenance data can be found in the Stormwater Pollution Prevention Plan (SW3P) provided in **Attachment D – Temporary Best Management Practices and Measures** of this section.



Attachment J – Schedule of Interim and Permanent Soil Stabilization Practices

When soil disturbance activities cease at a location, immediate soil stabilization actions will be implemented. Disturbed areas on which construction activities have ceased, temporarily or permanently, shall be stabilized within 14 calendar days unless they are scheduled to and do resume within 21 calendar days. The entire limits of construction will be reseeded once construction is complete.

Prior to Disturbance – Install all temporary erosion and sedimentation control features as described in the plans. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

During Construction – All temporary erosion and sedimentation control devices shall be maintained and inspected. Inspect all temporary erosion and sedimentation control devices in accordance with applicable laws and Attachment I. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.

Post Construction – Stabilize all areas disturbed during construction on the project site and adjacent areas. Permanent seeding shall be applied immediately after final design grades are achieved but no later than 14 days after construction activities have permanently ceased. After the entire site is stabilized, any sediment that has accumulated will be removed and hauled off-site for disposal. Construction debris, trash and temporary BMPs including silt fences, material storage areas, sanitary toilets, etc.) will also be removed and any areas disturbed during removal will be seeded immediately.

SECTION 6

Permanent Stormwater Section Exception



Permanent Stormwater

No permanent BMP's are being changed or added as a result of this project. The Permanent Stormwater Section (TCEQ-0600) is not necessary.

SECTION 7

Agent Authorization *TCEQ-0599*

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

The Honorable Bill Gravell Jr.
Print Name
Title - Owner/President/Other
of Williamson County
Corporation/Partnership/Entity Name
have authorized Anthony Serda, P.E.
Print Name of Agent/Engineer
of STV Infrastructure, Inc.
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:


Valerie Covey	May 8, 2024
Applicant's Signature	Date

THE STATE OF <u>Texas</u> §

County of Williamson §

BEFORE ME, the undersigned authority, on this day personally appeared Valerie Covey known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 8th day of May



NOTARY PUBLIC

Andrea Schiele

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 02-23-2025

SECTION 8

Application Fee *TCEQ-0574*

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Ent	tity: Pond Springs Road Drai	nage Improvements
Regulated Entity Location: Pond	Springs Rd from Roxie Dr to	300' S of Turtle Rock Road
Name of Customer: <u>Williamson C</u>	<u>County</u>	
Contact Person: <u>Adam D. Boatri</u> g	<u>tht</u> Phone: <u>5</u>	<u>12-943-3374</u>
Customer Reference Number (if	· -	
Regulated Entity Reference Num	ber (if issued):RN	
Austin Regional Office (3373)		
☐ Hays	Travis	Williamson
San Antonio Regional Office (33	62)	_
Bexar	Medina	Uvalde
Comal	Kinney	
Application fees must be paid by	check, certified check, or m	oney order, payable to the Texas
Commission on Environmental C	Quality. Your canceled chec	k will serve as your receipt. This
form must be submitted with yo	our fee payment. This paym	ent is being submitted to:
X Austin Regional Office	San A	antonio Regional Office
Mailed to: TCEQ - Cashier	Overi	night Delivery to: TCEQ - Cashier
Revenues Section	1210	0 Park 35 Circle
Mail Code 214	Build	ing A, 3rd Floor
P.O. Box 13088	Austi	n, TX 78753
Austin, TX 78711-3088	(512)	239-0357
Site Location (Check All That Ap	ply):	
Recharge Zone	Contributing Zone	Transition Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$ 500
Extension of Time	Each	\$

Date: <u>5/29/</u>2025

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee		
Extension of Time Request	\$150		

SECTION 9

Core Data Form *TCEQ-10400*

If new Customer, enter previous Customer below:

Other:

13. Independently Owned and Operated?

☐ No

Other:

10. DUNS Number (if

Partnership: General Limited

applicable)

ZIP + 4

9. Federal Tax ID

(9 digits)

☐ Individual

☐ Sole Proprietorship

78626

17. E-Mail Address (if applicable)



Williamson County

7. TX SOS/CPA Filing Number

11. Type of Customer:

12. Number of Employees

Occupational Licensee

Owner

15. Mailing

Address:

TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)

☐ Corporation

Government:
City County Federal Local State Other

☐ 0-20 ☐ 21-100 ☐ 101-250 ☐ 251-500 ☐ 501 and higher

Responsible Party

□ Operator

Georgetown

710 Main Street

16. Country Mailing Information (if outside USA)

City

SECTION I: General Inf	<u>ormation</u>				
1. Reason for Submission (If other is checked p	olease describe in space provided.)				
New Permit, Registration or Authorization (Core Data Form should be submitted with	the program application.)			
Renewal (Core Data Form should be submitt	ed with the renewal form)	☑ Other			
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in	3. Regulated Entity Reference Number (if issued)			
CN 600897888 Central Registry** RN					
SECTION II: Customer	<u>Information</u>				
4. General Customer Information	5. Effective Date for Customer Infor	mation Updates (mm/dd/yyyy)			
☐ New Customer ☐ Up	date to Customer Information	Change in Regulated Entity Ownership			
Change in Legal Name (Verifiable with the Texa	as Secretary of State or Texas Comptroller	of Public Accounts)			
The Customer Name submitted here may be	e updated automatically based on w	hat is current and active with the Texas Secretary of State			
(SOS) or Texas Comptroller of Public Accoun	nts (CPA).				

8. TX State Tax ID (11 digits)

14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following

Owner & Operator

State

18. Telephone Number 19. Extension or Code 20. Fax Number (if applicable)

TCEQ-10400 (11/22) Page 1 of 3

(512) 930-3330	(512) 930-3335
------------------	------------------

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)										
New Regulated Entity Update to Regulated Entity Name Update to Regulated Entity Information										
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).										
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)										
Pond Springs Road Drainage Improvements										
23. Street Address of the Regulated Entity:										
(No PO Boxes)	City		State		ZIF	•			ZIP + 4	
24. County	Williamson	1	1			l		l		1
	l	If no Stre	et Address is pro	ovided, fi	ields 25-28	are req	uired.			
25. Description to Physical Location:	Pond Springs Road from Roxie Drive to Lake Creek Tributary 3									
26. Nearest City	26. Nearest City State Nearest ZIP Code									rest ZIP Code
Austin TX 78729										
Latitude/Longitude are ru used to supply coordinate	-	-	-			Standar	ds. (Ged	ocoding of th	e Physical	Address may be
_	es where no	-	-						e Physical 97.78014	
used to supply coordinate	es where no	ne have been p	-		асу).) In Dec			
27. Latitude (N) In Decim Degrees 30	es where no al:	ne have been p	provided or to go		28. Longit Degrees) In Dec	imal: Vinutes	97.78014	6 Seconds 48.5
27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code	Minutes 30.	30.446520 26 Secondary SIC	Seconds 47.5	ain accure	28. Longit Degrees Primary NA	tude (W)) In Dec	imal: Winutes 46 32. Secon	97.78014	6 Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits)	Minutes 30.	30.446520 26 Secondary SIC	Seconds 47.5	31. F	Degrees Primary NA 6 digits)	tude (W)) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	6 Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611	### Add to the control of the contro	30.446520 26 Secondary SIC ligits)	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits)	97 AICS Cod) In Dec	imal: Winutes 46 32. Secon	97.78014	6 Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E	Minutes 30. (4 d 353	30.446520 26 Secondary SIC ligits)	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits)	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	6 Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611	Minutes 30. (4 d 353	30.446520 26 Secondary SIC ligits)	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits)	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	6 Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E	Minutes 30. (4 d 353	30.446520 26 Secondary SIC ligits) 1 this entity? (E	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits)	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E Road and Bridge Construction	Minutes 30. (4 d 353 Business of t	30.446520 26 Secondary SIC ligits) 1 this entity? (E	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits)	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E Road and Bridge Constructio 34. Mailing	Minutes 30. (4 d 353 Business of t	30.446520 26 Secondary SIC ligits) 1 this entity? (E	Seconds 47.5 Code	31. F (5 or	Degrees Primary NA 6 digits) S description	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014	Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E Road and Bridge Constructio 34. Mailing	Minutes 30. (4 d 353 Business of t	30.446520 26 Secondary SIC ligits) 1 Chis entity? (D	Seconds 47.5 Code	31. F (5 or 2373	Degrees Primary NA 6 digits) S description	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014 ndary NAIG	Seconds 48.5
used to supply coordinate 27. Latitude (N) In Decim Degrees 30 29. Primary SIC Code (4 digits) 1611 33. What is the Primary E Road and Bridge Constructio 34. Mailing Address:	Minutes 30. (4 d 353 Business of t	30.446520 26 Secondary SIC ligits) 1 Chis entity? (D	Seconds 47.5 Code	31. F (5 or 2373	Degrees Primary NA 6 digits) S description	97 AICS Cod) In Dec	imal: Vinutes 46 32. Secon (5 or 6 dig	97.78014 ndary NAI its)	Seconds 48.5

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety		Districts	Edwards Aquifer		Emissions Inventory Air	☐ Industrial Hazardous Waste	
☐ Municipal S	olid Waste	New Source Review Air	OSSF		Petroleum Storage Tank	PWS	
Sludge		Storm Water	☐ Title V Air		Tires	Used Oil	
☐ Voluntary C	leanup	☐ Wastewater	☐ Wastewater Agricul	ture	Water Rights	Other:	
SECTION IV: Preparer Information							
40. Name: Bradley McConnon, P. E.			41. Title:	Lead Engineer			

40. Name:	Bradley McConnon, P. E.		41. Title:	Lead Engineer	
42. Telephone	Number	43. Ext./Code	44. Fax Number	45. E-Mail <i>i</i>	Address
(512)340-9800	١		() -	bradley.mcco	onnon@stvinc.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	STV, Inc.	Job Title:	Principal		
Name (In Print):	Anthony Serda, P. E.				(512)241- 2228
Signature:	Anthy Sal			Date:	5/29/2025

TCEQ-10400 (11/22) Page 3 of 3