CLARA VISTA LIFT STATION & FORCE MAIN ABOVEGROUND STORAGE TANK APPLICATION

PREPARED BY:
PAPE-DAWSON CONSULTING ENGINEERS, LLC.
TBPE FIRM REGISTRATION #470
10801 N MoPac Expy., Bldg. 3, Suite 200
AUSTIN, TEXAS 78759



PAPE-DAWSON

PAPE-DAWSON.COM

CLARA VISTA LIFT STATION & FORCE MAIN

ABOVEGROUND STORAGE TANK APPLICATION

PREPARED BY:

PAPE-DAWSON CONSULTING ENGINEERS, LLC. TBPE FIRM REGISTRATION #470 10801 N MoPac Expy., Bldg. 3, Suite 200 AUSTIN, TEXAS 78759

August 2025

PAPE-DAWSON

August 20, 2025

Ms. Lori Wilson Texas Commission on Environmental Quality Region 11 12100 Park 35 Circle, Bldg. A Austin, Texas 78753

Re:

Clara Vista Lift Station & Force Main Aboveground Storage Tank Application

Dear Ms. Wilson:

Please find attached one (1) electronic copy of the Clara Vista Lift Station & Force Main Aboveground Storage Tank Application. This Aboveground Storage Tank Application has been prepared in accordance with the Texas Administrative Code (30 TAC 213), and current policies for development over the Edwards Aquifer Contributing Zone within the Transition Zone.

This Aboveground Storage Tank Application applies to one (1) aboveground storage tank included in the project. Please review the plan information for the items it is intended to address. If acceptable, please provide a written approval of the plan in order that construction may begin at the earliest opportunity.

If you have any questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,

Pape-Dawson Consulting Engineers, LLC

Aimee Chavez, P.E.

anne

Associate Vice President

H:\Projects\514\56\10\302 Construction Documents\Documents\Reports\AST\CZP Cover Letter.docx

EDWARDS AQUIFER APPLICATION COVER PAGE (TCEQ-20705)

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- When an application is deemed administratively complete, the technical review period begins. The regional
 office will distribute copies of the application to the identified affected city, county, and groundwater
 conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
 to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Clara Vista Lift Station & Force Main				2. Regulated Entity No.: 112094636				
3. Customer Name: Toll Southwest LLC.			4. Customer No.: CN605682475					
5. Project Type: (Please circle/check one)	New Modification		ication	Extension Exception		Exception		
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST AST	EXP	EXT	Technical Clarification	
7. Land Use: (Please circle/check one)	Residen	ıtial	Non-residential)	8. Sit	e (acres):	1.79 acres
9. Application Fee:	\$650.00	0	10. Permanent I		BMP(s	BMP(s): N/A		
11. SCS (Linear Ft.):	N/A		12. A	ST/UST (N	o. Tar	o. Tanks): N/A		
13. County:	Hays 14. Watershed:					Blanco River		

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)	✓	_	_		
Region (1 req.)	✓	_	_		
County(ies)	✓	_	_		
Groundwater Conservation District(s)	Edwards Aquifer Authority ✓ Barton Springs/ Edwards AquiferHays TrinityPlum Creek	Barton Springs/ Edwards Aquifer	_		
City(ies) Jurisdiction	AustinBudaDripping Springs ✓KyleMountain City _San MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJarrellLeanderLiberty HillPflugerville Round Rock		

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	_	_	_	_	_
Region (1 req.)	_	_		_	_
County(ies)	_	_	_		_
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.		
-		
Aimee Chavez, P.E.		
Print Name of Customer/Authorized Agent		
ainei a	8/29/25	
Signature of Customer/Authorized Agent	Date	

**FOR TCEQ INTERNAL USE ONLY	**			
Date(s)Reviewed:		Date Administratively Complete:		
Received From:		Correct Number of Copies:		
Received By:		Distribution Date:		
EAPP File Number:		Complex:		
Admin. Review(s) (No.):		No. AR Rounds:		
Delinquent Fees (Y/N):		Review Time Spent:		
Lat./Long. Verified:		SOS Customer Verification:		
Agent Authorization Complete/Notarized (Y/N):	Fee	Payable to TCEQ (Y/N):		
Core Data Form Complete (Y/N):	Check:	Signed (Y/N):		
Core Data Form Incomplete Nos.:		Less than 90 days old (Y/N):		

GENERAL INFORMATION FORM (TCEQ-0587)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Pri	nt Name of Customer/Agent: <u>Aimee Chavez</u>
Da	te: <u>8/2%</u> 25
Sig	nature of Customer/Agent:
	roject Information
1.	Regulated Entity Name: Clara Vista Lift Station & Force Main
2.	County: <u>Hays</u>
3.	Stream Basin: Blanco River
4.	Groundwater Conservation District (If applicable): <u>barton Springs/Edwards Aquifer</u>
5.	Edwards Aquifer Zone:
	☐ Recharge Zone ☐ Transition Zone
6.	Plan Type:
	WPAP

7.	Customer (Applicant):
	Contact Person: Kyle Ninness Entity: Toll Southwest, LLC. Mailing Address: 1320 Arrow Point Dr., Suite 401 City, State: Cedar Park, Texas Telephone: 303-263-7132 Email Address: kninness@tollbrothers.com
8.	Agent/Representative (If any):
	Contact Person: Aimee Chavez Entity: Pape-Dawson Consulting Engineers, LLC Mailing Address: 10801 N Mopac Expy., Bldg. 3, Ste. 200 City, State: Austin, Texas Telephone: 512-454-8711 Email Address: AChavez@pape-dawson.com
9.	Project Location:
	The project site is located inside the city limits of Kyle , Texas. The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of The project site is not located within any city's limits or ETJ.
10.	The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.
	From TCEQ's Regional Office, travel south along the IH-35 frontage road for approximately 0.7 miles. Merge onto IH-35 S and continue for approximately 26.8 miles. Take exit 215 toward FM 1626 & Kyle Parkway. In approximately 0.3 miles turn right onto Kohlers Crossing. Continue approximately 2.6 miles and then turn left onto Jack C Hays Trail. In 1.1 miles continue onto N Old Stagecoach Rd. Then in 0.5 miles turn right onto 6 Creeks Blvd and continue for approximately 1 mile before reaching the site.
11.	Attachment A – Road Map. A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12.	Attachment B - USGS / Edwards Recharge Zone Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
	 ☑ Project site boundaries. ☑ USGS Quadrangle Name(s). ☑ Boundaries of the Recharge Zone (and Transition Zone, if applicable). ☑ Drainage path from the project site to the boundary of the Recharge Zone.

	The TCEQ must be able to inspect the project site or the application will be returned. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.
	Survey staking will be completed by this date:
	Attachment C – Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
	 ✓ Area of the site ✓ Offsite areas ✓ Impervious cover ✓ Permanent BMP(s) ✓ Proposed site use ✓ Site history ✓ Previous development ✓ Area(s) to be demolished
15. Exis	ting project site conditions are noted below:
	 □ Existing commercial site □ Existing industrial site □ Existing residential site ⋈ Existing paved and/or unpaved roads ⋈ Undeveloped (Cleared) ⋈ Undeveloped (Undisturbed/Uncleared) □ Other:
Proh	ibited Activities
	I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
	(1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
	(2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
	(3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
	(4) The use of sewage holding tanks as parts of organized collection systems; and
	(5) New municipal solid waste landfill facilities required to meet and comply with Type I

standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types

(6) New municipal and industrial wastewater discharges into or adjacent to water in the


of Municipal Solid Waste Facilities).

state that would create additional pollutant loading.

- 17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
 - (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
 - (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information	
18. The fee for the plan(s) is based on:	
 □ For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur. □ For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines. □ For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the to number of tanks or piping systems. □ A request for an exception to any substantive portion of the regulations related to the protection of water quality. □ A request for an extension to a previously approved plan. 	otal
19. Application fees are due and payable at the time the application is filed. If the correfee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have bee sent to the Commission's:	
 TCEQ cashier Austin Regional Office (for projects in Hays, Travis, and Williamson Counties) San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties) 	
20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regions.	
21. No person shall commence any regulated activity until the Edwards Aquifer Protect Plan(s) for the activity has been filed with and approved by the Executive Director.	ion

ATTACHMENT A



JOB NO. 51456-10 DATE AUGUST 2025 DESIGNER _ CHECKED AC DRAWN CK 1 of 1


SHEET

CLARA VISTA LIFT STATION & FORCE MAIN KYLE, TEXAS ATTACHMENT A - ROAD MAP



AUSTIN I SAN ANTONIO I HOUSTON I FORT WORTH I DALLAS 10801 N MOPAC EXPY, BLDG 3, STE 200 I AUSTIN, TX 78759 I 512.454.8711 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028801

ATTACHMENT B



PAPE-DAWSON
ENGINEERS
11 SAN ANTONIO 1 HOUSTON 1 FORT WORTH 1 DALLAS
MODES EXY, BLOG 3. STE 2001 AISTIN, 17 37599 5124548711

CLARA VISTA LIFT STATION & FORCE MAIN KYLE, TEXAS

- USGS QUAD MAP

ATTACHMENT B

JOB NO. <u>51456-10</u>

DATE <u>AUGUST 2025</u>

DESIGNER _____

CHECKED ____ AC

SHEET 1 of 1

ATTACHMENT C

Brooke Paup, *Chairwoman*Bobby Janecka, *Commissioner*Catarina R. Gonzales, *Commissioner*Kelly Keel, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

January 10, 2025

Mr. Mike Boswell Toll Southwest LLC 1320 Arrow Point Dr., Suite 401 Cedar Park, Texas 78613

Re: Approval of a Contributing Zone Plan (CZP)

Clara Vista Lift Station & Force Main; Located west of Falling River Road and Seaside

Sparrow Way; Kyle, Hays County, Texas

Edwards Aquifer Protection Program ID: 11004250, Regulated Entity No. RN112094636

Dear Mr. Boswell:

The Texas Commission on Environmental Quality (TCEQ) has completed its review on the application for the above-referenced project submitted to the Edwards Aquifer Protection Program (EAPP) by Pape-Dawson Consulting Engineers, LLC on behalf of the applicant, Toll Southwest LLC on December 3, 2025. Final review of the application was completed after additional material was received on January 8, 2025.

As presented to the TCEQ, the application was prepared in general compliance with the requirements of 30 Texas Administrative Codes (TAC) Chapter §213. The permanent best management practices (BMPs) and measures represented in the application were prepared by a Texas licensed professional engineer (PE). All construction plans and design information were sealed, signed, and dated by a Texas licensed PE. Therefore, the application for the construction of the proposed project and methods to protect the Edwards Aquifer are **approved**, subject to applicable state rules and the conditions in this letter.

This approval expires two years from the date of this letter, unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been officially requested. This approval or extension will expire, and no extension will be granted if more than 50 percent of the project has not been completed within ten years from the date of this letter.

The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this contributing zone plan or modification to a plan. A motion for reconsideration must be filed in accordance with 30 TAC §50.139.

PROJECT DESCRIPTION

The proposed commercial project will have an area of approximately 1.79-acres. The project will include construction of gravity sewer main and force main, manhole installation, excavation for and construction of a lift station and installation of five engineered vegetative filter strips. The impervious cover will be 0.60-acres (33.52-percent). No wastewater will be generated at the Lift Station site. Project wastewater pumped by the lift station will be disposed of by conveyance to the existing Kyle Wastewater Treatment Plant.

PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, five engineered vegetative filter strips, designed using the TCEQ technical guidance, *RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices,* will be constructed to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 526-pounds of TSS generated from the 0.60-acres of impervious cover. The approved permanent BMPs and measures meet the required 80 percent removal of the increased load in TSS caused by the project.

The permanent BMPS shall be operational prior to occupancy or use of the proposed project. Inspection, maintenance, repair, and retrofit of the permanent BMPs shall be in accordance with the approved application.

STANDARD CONDITIONS

- 1. The plan holder (applicant) must comply with all provisions of 30 TAC Chapter §213 and all technical specifications in the approved plan. The plan holder should also acquire and comply with additional and separate approvals, permits, registrations or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, Dam Safety, Underground Injection Control) as required based on the specifics of the plan.
- 2. In addition to the rules of the Commission, the plan holder must also comply with state and local ordinances and regulations providing for the protection of water quality as applicable.

Prior to Commencement of Construction:

- 3. The plan holder of any approved contributing zone plan must notify the EAPP and obtain approval from the executive director prior to initiating any modification to the activities described in the referenced application following the date of the approval.
- 4. The plan holder must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the EAPP no later than 48 hours prior to commencement of the regulated activity. Notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person.
- 5. Temporary erosion and sedimentation (E&S) controls as described in the referenced application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

- 6. The application must indicate the placement of permanent aboveground storage tanks facilities for static hydrocarbons and hazardous substances with cumulative storage capacity of 500 gallons or more. Subsequent permanent storage tanks on this project site require a modification to be submitted and approved prior to installation.
- 7. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
- 8. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge must be filtered through appropriately selected BMPs.

- 9. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 10. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

- 11. Owners of permanent BMPs and temporary measures must ensure that the BMPs and measures are constructed and function as designed. A Texas licensed PE **must certify** in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the EAPP within 30 days of site completion.
- 12. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or the ownership of the property is transferred to the entity. A copy of the transfer of responsibility must be filed with the executive director through the EAPP within 30 days of the transfer. TCEQ form, Change in Responsibility for Maintenance on Permanent BMPs and Measures (TCEQ-10263), may be used.

The holder of the approved contributing zone plan is responsible for compliance with Chapter §213 subchapter B and any condition of the approved plan through all phases of plan implementation. Failure to comply with any condition within this approval letter is a violation of Chapter §213 subchapter B and is subject to administrative rule or orders and penalties as provided under §213.25 of this title (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. Upon legal transfer of this property, the new owner is required to comply with all terms of the approved contributing zone plan.

This action is taken as delegated by the executive director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Don Vandertulip, PE, BCEE of the Edwards Aquifer Protection Program at 210-403-4057 or the regional office at 512-339-2929.

Sincerely,

Monica Reyes

Monica Reyes, Section Manager Edwards Aquifer Protection Program Texas Commission on Environmental Quality

MR/dv

GEOLOGIC ASSESSMENT FORM (TCEQ-0585)

Geologic Assessment

Texas Commission on Environmental Quality

Print Name of Geologist: Henry F Stultz III P.G.

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Telephone: 210-375-9000

Time traine of Geologist.	relephone	210 373 3000
Date: May 7, 2024	Fax:	210-375-9090
Representing: Pape-Dawson Engineers, Inc., TBPG reg	istration num	ber 50351
Signature of Geologist:		-20201111111111111111111111111111111111
13		HENRY STULTZ III GEOLOGY 12121
Regulated Entity Name: Clara Vista – Force Main		CENSE O
Project Information		* 18 STELLE STATE OF THE STATE
1. Date(s) Geologic Assessment was performed: April	3, 2024	
2. Type of Project:		
WPAPSCSLocation of Project:	AST UST	
Recharge ZoneTransition ZoneContributing Zone within the Transition Zone		

- 4. Attachment A Geologic Assessment Table. Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
- 5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

0		
Soil Name	Group*	Thickness(feet)
Austin-Castephen complex, 1 to 3 % slopes (AuB)	С	2-3
Lewisville silty clay, 1 to 3 % slopes (LeB)	С	3-6
Real gravelly loam, 1 to 8 % slopes (RaD)	D	1-3

- * Soil Group Definitions (Abbreviated)
 - A. Soils having a high infiltration rate when thoroughly wetted.
 - B. Soils having a moderate infiltration rate when thoroughly wetted.
 - C. Soils having a slow infiltration rate when thoroughly wetted.
 - D. Soils having a very slow infiltration rate when thoroughly wetted.
- 6. Attachment B Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
- 7. Attachment C Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
- 8. Attachment D Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale: 1" = 200' Site Geologic Map Scale: 1" = 200'

Site Soils Map Scale (if more than 1 soil type): 1" = 1500'

9. Method of collecting positional data:

Global Positioning System (GPS) technology.

Other method(s). Please describe method of data collection:_____

10. $\boxed{\hspace{-0.05cm}}$ The project site and boundaries are clearly shown and labeled on the Site Geologic Map.

11. Surface geologic units are shown and labeled on the Site Geologic Map.

investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
Geologic or manmade features were not discovered on the project site during the field investigation.
igwedge The Recharge Zone boundary is shown and labeled, if appropriate.
All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
 □ There are(#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.) □ The wells are not in use and have been properly abandoned. □ The wells are not in use and will be properly abandoned. □ The wells are in use and comply with 16 TAC Chapter 76. ☑ There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A Geologic Assessment Table

GEOLOGIC ASSESSMENT TABLE						PROJECT NAME: Clara Vista – Force Main														
LOCATION						FE	FEATURE CHARACTERISTICS						EVALUATION		PHYSICAL SETTING					
1A	1B * 1C* 2A 2B 3			4 5 5A 6			7 8A	8B	9	10		11		12						
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIME	NSIONS (FEET)	TREND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	SENS	SITIVITY		IENT AREA CRES)	TOPOGRAPHY
	19.00			31 233	and the law	Х	Y	Z		10	7 - 4 3 -				(Clare)	<40	≥40	<1.6	≥1.6	
S-1	29.99103	-97.89238	MB	30	Kau								F,C	5	35	35		Х		Hillside
								-												

^{**} DATUM: NAD 83



2A TYPE	TYPE	2B POINTS
С	Cave	30
SC SF	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
0	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
sw	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

	8A INFILLING
N	None, exposed bedrock
С	Coarse - cobbles, breakdown, sand, gravel
0	Loose or soft mud or soil, organics, leaves, sticks, dark colors
F	Fines, compacted clay-rich sediment, soil profile, gray or red colors
V	Vegetation. Give details in narrative description
FS	Flowstone, cements, cave deposits
Х	Other materials

				12 TOPOGE	RAPHY		
Cliff,	Hilltop,	Hillside,	Drainage,	Floodplain,	Streambe	ed	

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Date May 7,2024

ATTACHMENT B Stratigraphic Column

Clara Vista – Force Main Geologic Assessment (TCEQ-0585)

<u>Attachment B – Stratigraphic Column</u>

Period	Epoch	Group	Formation	Maximum Thickness	Lithology	Hydrologic Unit
	Gulfian	Austin	Austin Chalk (Kau)	325-420	Austin Chalk, chalk and marl; chalk mostly microgranular calcite with minor Foraminifera tests and Inoceramus prisms, average about 85 percent calcium carbonate, ledge forming grayish white to white; alternates with marl, bentonitic seams locally recessive, medium gray; pyrete nodules common, weather to limonite.	Confining
		Washita	Eagle Ford Group and Buda Limestone	25-65	Eagle Ford Group, shale and limestone. Upper part-shale, compact, silty, contains fossil fish teeth and bones, 10 feet or more thick; middle part-silty limestone grading to calcareous siltstone, flaggy, medium gray, weathers pale yellowish brown, 5 feet thrick. Lower part-shale, calcareous, dark gray, 7-50 feet thick.	Confining
			(undivided) (Keb)	45	Buda Limestone , fine grained bioclastic, commonly glauconitic, pyritiferous, hard, massice, poorly bedded to nodular, thinner bedded and argillacrous near upper contact, light gray to pasle orange; weathers dark gray to brown; burrows filled with chalky marl, abundant pelecypods.	Confining
			Del Rio Clay and Georgetown Formation	40–60	Del Rio Clay , mostly clay, calcareous and gypsiferous, becoming less calcareous and more gypsiferous upward, pyrity common, blocky, medium gray, weather light gray to yellowish gray; some thin lenticular beds of hightly calcareous siltstone; some thin limestone beds composed of pelecypods.	Confining
snoa			(undivided) (Kdg)	10-45	Georgetown Formation , mostly limestone, fine grained, argillaceous, nodular, moderalty indurated, light gray; some limestone, hard brittle, thick bedded, white; some shale, calcareous, soft, light gray to yellowish gray.	
Cretaceous	Comanchean	Fredricksburg		60-350	Edwards Limestone, limestone, dolomite, and chert; limestone aphanitic to fine grained, massive to thin bedded, hard, brittle, in part rudistid biostromes, much miliolid biosparite; dolomite fine to very fine grained, porous, medium gray to grayish brown; chert, nodules and plates common, varies in amount from bed o bed, some intervals free of chert, mostly white to light gray; in zone of weathering considerably recrystallized, "honeycombed," and cavernous forming an aquifer; forms flat areas and plateaus bordered by scarps; thickness 60-350 feet, thins northward.	Edwards Aquifer
			Fredricksburg Group (undivided) (Kfr)	80	Comanche Peak Limestone, fine to very fine grained, fairly hard, nodular, light gray, weathers white, extensively burrowed, burrow fillings slightly coarser and darker, typically outcrops in scarp face beneath Edwards Limestone; feathers out southward near Williamson-Travis County line.	
		Fre	, ,	50	Keys Valley Marl , soft, white; marine megafossils include Exogyra texana, Gryphaea mucronate, and other pelecypods, ammonites, gastropods, and echinoids; feathers out southward near Williamson-Travis County line.	Confining
				40	Cedar Park Limestone, Kcp, lithologically and faunally similar to Comanche Peak Limestone; south of Williamson-Travis County line upper part interfingers with Edwards Limestone and lower part is mapped with Bee Cave Marl.	Aquifer
				25-40	Bee Cave Marl , Kbc lithologically and faunally similar to Keys Valley Marl, except Exogyra texana are more abundant and ammonites are scarce.	Confining



ATTACHMENT C Site Geology

CLARA VISTA – FORCE MAIN Geologic Assessment

<u>Attachment C – Site Geology</u>

SUMMARY

The Clara Vista – Force Main project site is primarily located along Cypress Road, west of Old Stagecoach Road in the City of Kyle, Hays County, Texas. The remaining portions of the project site are located south of the Clara Vista subdivision.

Based on the results of the field survey conducted in accordance with *Instructions for Geologists for Geologic Assessments in the Edwards Aquifer Recharge/Transition Zones (TCEQ-0585 Instructions),* no naturally occurring sensitive features were identified on site. No springs were identified on site. Three tributaries of the Lower Blanco River were identified on site. The overall potential for fluid migration to the Edwards Aquifer for the site is low.

SITE GEOLOGY

As observed through field evidence, the geologic formations which outcrop at the surface within the project limits are the Austin Chalk (Kau), the Eagle Ford Group and Buda Limestone (undivided) (Keb), and the Del Rio Clay and Georgetown Formation (undivided) (Kdg). These formations are described in further detail below.

- The Kau is comprised of limestone, argillaceous chalky limestone and calcareous shale, and is locally bentonitic. Karst development within the Kau is commonly related to geologic structure within the formation.
- The Keb is comprised of undivided units of the Eagle Ford Group and the Buda Limestone. Portions of the formation exhibiting geologic settings of the Eagle Ford Group are characterized by brown, flaggy shale and argillaceous limestone. Karst development in the Eagle Ford Group is uncommon and generally minor. Portions of the formation exhibiting geologic settings of the Buda Limestone are characterized by buff, light gray, dense mudstone. Karst development in the Buda Limestone is generally minor.



CLARA VISTA – FORCE MAIN Geologic Assessment

• The Kdg is comprised of undivided units of the Del Rio Clay and Georgetown Formations. Portions of the formation exhibiting geologic settings of the Del Rio Clay characterized by blue-green to yellow-brown waxy clay. Karst development within the Del Rio Clay does not occur. Portions of the formation exhibiting geologic settings of the Georgetown Formation are characterized by reddish-brown to light tan marly limestone. Karst development within the Georgetown Formation generally does not occur.

The predominant trend of faults in the vicinity of the site is approximately N40°E, based on faults identified during the previous mapping of the area.

FEATURE DESCRIPTIONS:

A description of the features observed onsite is provided below:

Feature S-1

Feature S-1 is an existing sewer line that is located beneath pavement. The probability of rapid infiltration is low.

REFERENCES

Barnes, V.E., Humble Oil and Refining Co., Shell Oil Co., Mobile Oil Co., Proctor, C.V., Brown, T.E., Waechter, N.B., Aronow, Saul, Tobin, Edward, Eargle, D.H., Baker, E.T., Peckham, R.C., Bluntzer, R.L., Hinds, G.W., LeBlanc, R.J., and Solliday, J., 1974, Geologic atlas of Texas, Seguin sheet, University of Texas at Austin, Bureau of Economic Geology, Geologic Atlas of Texas 30, 1:250,000.

Nationwide Environmental Title Research, LLC. Historical Aerials, HistoricAerials.com. https://www.historicaerials.com/viewer, May 10, 2021.


Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Web Soil Survey. http://websoilsurvey.sc.egov.usda.gov/, May 10, 2021.

Texas Water Development Board, Wells in TWDB Groundwater Database Viewer, https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer, May 10, 2021.


U.S. Geological Survey, National Water Information System: Mapper, https://maps.waterdata.usgs.gov/mapper/index.html, May 10, 2021. May 7, 2024.





ATTACHMENT D Site Geologic Map(s)




Date: Apr 25, 2024 2:19 PM User. HStuff









NOTE: THE GEOSCIENTIST SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR PURPOSES OF GEOLOGIC INFORMATION. ALL OTHER INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SIGNED AND SEALED CIVIL ENGINEERING DRAWINGS.

MAIN ARA VISTA - FORCE HAYS COUNTY, TEXAS

JOB NO. 51432-32 DATE APRIL 2024 DESIGNER HS CHECKED HDJ DRAWN HS

ATTACHMENT D

ABOVEGROUND STORAGE TANK FACILITY PLAN (TCEQ-0575)

Aboveground Storage Tank Facility Plan Application

Texas Commission on Environmental Quality

For Permanent Storage on The Edwards Aquifer Recharge and Transition Zones And Relating to 30 TAC §213.5(e), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Aboveground Storage Tank Facility Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Aimee Chavez

Date: 8/29/25

Signature of Customer/Agent:

Regulated Entity Name: Clara Vista Lift Station & Force Main

Aboveground Storage Tank (AST) Facility Information

1. Tanks and substance stored:

Table 1 - Tank and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1	777	Diesel Fuel	Steel
2			
3			
4			

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
5			

Total x 1.5 = <u>1166</u> **Gallons**

2.	The AST will be placed within a containment structure that is sized to capture or one-half (1 1/2) times the storage capacity of the system. For facilities with moone tank system, the containment structure is sized to capture one and one-hal times the cumulative storage capacity of all systems.	re than
	Attachment A - Alternative Methods of Secondary Containment. Alternative n for providing secondary containment are proposed. Specifications that show ec protection for the Edwards Aquifer are attached.	

3. Inside dimensions and capacity of containment structure(s):

Table 2 - Secondary Containment

Length (L) (Ft.)	Width (W) (Ft.)	Height (H) (Ft.)	L x W x H = (Ft3)	Gallons
10.03	3.11	3.73	116.30	870

Total: 870 Gallons

4.	 ✓ All piping, hoses, and dispensers will be located inside the containment structure. ✓ Some of the piping to dispensers or equipment will extend outside the containment structure. ✓ The piping will be aboveground ✓ The piping will be underground
5.	\boxtimes The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of <u>Steel</u> .
6.	Attachment B - Scaled Drawing(s) of Containment Structure. A scaled drawing of the containment structure that shows the following is attached:
	 ✓ Interior dimensions (length, width, depth and wall and floor thickness). ✓ Internal drainage to a point convenient for the collection of any spillage. ✓ Tanks clearly labeled. ✓ Piping clearly labeled. ✓ Dispenser clearly labeled.

Site Plan Requirements

Items 7 - 18 must be included on the Site Plan.

7.	\square The Site Plan must have a minimum scale of 1" = 400'.
	Site Plan Scale: $1'' = 40'$.
3.	100-year floodplain boundaries:
	 Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled. No part of the project site is located within the 100-year floodplain.
	The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): NFHL DFIRM for Hays County, Texas panel #48209C0385G (1/17/2025) & #48209C0270G (1/17/2025).
Э.	The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Show lots, recreation centers, buildings, roads, etc.
	The layout of the development is shown with existing contours. Finished topographic contours will not differ from the existing topographic configuration and are not shown.
10.	. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):
	There are (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply): The wells are not in use and have been properly abandoned. The wells are not in use and will be properly abandoned. The wells are in use and comply with 16 TAC § 76.
	There are no wells or test holes of any kind known to exist on the project site.
11.	. Geologic or manmade features which are on the site:
	All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.
	No sensitive geologic or manmade features were identified in the Geologic Assessment.
	Attachment C - Exception to the Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached.
12.	. $igotimes$ The drainage patterns and approximate slopes anticipated after major grading activities
13.	. Areas of soil disturbance and areas which will not be disturbed.
14.	. \boxtimes Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.

15.	$\overline{igwedge}$ Locations where soil stabilization practices are expected to occur.
16.	Surface waters (including wetlands). N/A
17.	Locations where stormwater discharges to surface water or sensitive features. There will be no discharges to surface water or sensitive features.
18.	Legal boundaries of the site are shown.
Ве	st Management Practices
19.	Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.
	 In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly. In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.
20.	All stormwater accumulating inside the containment structure will be disposed of through an authorized waste disposal contractor.
	☐ Containment area will be covered by a roof.☐ Containment area will not be covered by a roof.
	A description of the alternate method of stormwater disposal is submitted for the executive director's review and approval and is attached.
21.	Attachment D - Spill and Overfill Control. A site-specific description of the methods to be used at the facility for spill and overfill control is attached.
22.	Attachment E - Response Actions to Spills. A site-specific description of the planned response actions to spills that will take place at the facility is attached.
A	ministrative Information
23.	A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.
	 The WPAP application for this project was approved by letter dated A copy of the approval letter is attached at the end of this application. The WPAP application for this project was submitted to the TCEQ on, but ha not been approved. A WPAP application is required for an associated project, but it has not been submitted.

	 There will be no building or structure associated with this project. In the event a building or structure is needed in the future, the required WPAP will be submitted to the TCEQ. ☑ The proposed AST is located on the Transition Zone and a WPAP is not required. Information requested in 30 TAC 213.5 subsection (b) (4)(B) and (C) and (5) is provided with this application. (Forms TCEQ-0600 Permanent Stormwater Section and TCEQ-0602 Temporary Stormwater Section or Stormwater Pollution Prevention Plan/SW3P).
24. 🔀	This facility is subject to the requirements for the reporting and cleanup of surface spills and overfills pursuant to 30 TAC 334 Subchapter D relating to Release Reporting and Corrective Action.
25. 🔀	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
26. 🔀	Any modification of this AST Facility Plan application will require executive director approval, prior to construction, and may require submission of a revised application, with appropriate fees

ATTACHMENT A

<u>Attachment A – Alternative Methods of Secondary Containment</u>

This Clara Vista Lift Station and Force Main Aboveground Storage Tank (AST) Facility Plan proposes one (1) base-mounted, double-wall, steel construction tanks for storage of 777 gallons of diesel fuel to service lift station machinery in the event of an emergency.

Fuel Tank Description

This 777-gallon tank is located on a 1.79-acre site within an overall fenced and gated 0.086-acre lift station. The tank will be located on a 112 square foot concrete pad above 3727 square feet of concrete pavement. The tank will be surrounded by removable bollards.

The tank is constructed of materials that are compatible with the liquids stored (diesel) within and have the appropriate safety equipment, such as primary and emergency venting, overfill protection, and fuel level sensors with low-level and high-level alarms.

The primary tank is wholly contained within the secondary tank, and the interstitial space between the tanks is hollow. If failure occurs in the primary tank, all fuel will be trapped within the 870-gallon secondary tank. Additionally, the tank will be regularly maintained by qualified personnel.

ATTACHMENT B



Austin • Brownsville • Corpus Christi • Dallas • Edinburg • Ft Worth • Laredo • Longview • Pflugerville • San Antonio • Victoria • Waco

Enclosure





Picture shown may not reflect actual configuration

Weather Protective and Sound Attenuated Enclosures

D40 to D60 D80 to D100 D125 to D200

Features

Highly Corrosion Resistant construction

- Stainless steel flush fitting latches and hinges tested and proven to withstand extreme conditions of corrosion
- · Zinc plated or stainless steel fastener

Excellent Access

- Single side access for service and controls
- All non-service sides have removable doors and/or panels
- Radiator fill access
- Lube oil and coolant drains piped to the exterior of the enclosure base
- Large cable entry area for installation ease
- Double doors on both sides
- Vertically hinged doors with solid bar door stays to hold doors in place when open

Security and Safety

- Lockable access doors which give full access to control panel and breaker
- Cooling fan and battery charging alternator fully guarded
- · Fuel fill, oil fill, and battery can only be reached via lockable access
- Stub-up area is rodent proof

Transportability

- These enclosures are of extremely rugged construction to withstand outdoor exposure and rough handling common on many construction sites. The sound deadening material is of a selfextinguishing design
- This range of enclosures are designed on modular principles with many interchangeable components permitting on site repair

Options

- Weather Protective constructed with 16 gauge steel; industrial silencer mounted within the main enclosure body
- Sound Attenuated Level 1 constructed with 16 gauge steel; weather protective with critical silencer - silencer mounted in separate upward discharging radiator hood
- Sound Attenuated Level 2 constructed with 16 gauge steel; weather protective with critical silencer and 100% lined with sound deadening material – silencer mounted in separate upward discharging radiator hood
- Sound Attenuated Aluminum constructed with 14 gauge Aluminum 5052 grade. Weather protective with critical silencer and 100% lined with sound deadening material – silencer mounted in separate upward discharging radiator hood
- Caterpillar white paint
- UL Listed sub base tanks
- Externally mounted emergency stop button
- Seismic certification per applicable building codes: IBC 2000, IBC 2003, IBC 2006, IBC 2009, IBC 2012, CBC 2007, CBC 2010
- IBC certification for 180 mph wind loading

^{*}Not available with Aluminium enclosures




Enclosure Sound Pressure Levels (SPL) at 100%

SA Level 2	Enclosure	Cooling Air	Flow Rate	SPL @7m (23ft)
Model	Standby eKW	m³/s	cfm	dBA
D80-8	80	3.2	6696	75
D100-8	100	3.2	6696	76
D125-8	125	4.2	8899	74
D150-10	150	4.2	8899	74
D175-4	175	5.2	11018	74
D200-2	200	5.1	10806	75



Enclosure Dimensions and Weights






Image represents SA Level 1, SA Level 2 and SA Aluminum enclosures mounted on optional UL listed sub base tank

BA - J - I	Ctoudhu al/M	WP Inc	dustrial	SA Lo	evel 1	SA L	evel 2	SA Alu	ıminum
Model	Standby eKW	kg	lb	kg	lb	kg	lb	kg	lb
D40-2	40								
D50-2	50	121	267	137	302	NA	NA	NA	NA
D60-2	60								
D80-8	80	202	Ε00	212	coo	221	700	1.40	212
D100-8	100	263	580	313	690	321	708	142	312
D125-8	125								
D150-10	150	240	760	202	007	400	000	176	207
D175-4	175	348	768	393	867	406	896	176	387
D200-2	200								

Enclosure weights (includes muffler)

PLEASE REFER TO DRAWING FOR ENCLOSURE DIMENSION



Austin • Brownsville • Corpus Christi • Dallas • Edinburg • Ft Worth • Laredo • Longview • Pflugerville • San Antonio • Victoria • Waco

Fuel System

Attachments





Image shown may not reflect actual configuration

C4.4 and C7.1 Sub-base Fuel Tanks

Diesel Generator Set 80 – 200 kW 60 Hz

Features

- UL Listed for United States (UL 142) and Canada (CAN/ULC S601)
- Facilitate compliance with NFPA 30 code, NFPA 37 and 110 standards and CSA C282 code and B139-09 standard
- Welded, heavy steel gauge construction with a containment basin sized as a minimum 110% of the tank
- Gloss black polyester triglycidyl isocyanurate (TGIC) powder coating
- Dedicated external customer interface area with access to the 4" (101.6 mm) fuel fill, visual level gauge, normal and emergency vents
- Rear electrical stub-up area with removable access panel
- Removable engine supply and return dip tubes
- Two additional 1" (25.4 mm) ports for customer use
- Tanks are rated to safely support the weight of the generator
- 8 gal (30.3 L) drip pan for oil and coolant (for generator sets up to 60 ekW only)
- Standard NPT tank fittings
- UL listed emergency vents sized as per UL standards 3" (76.2 mm), 4" (101.6 mm), and 5" (127 mm) NPT
- Normal atmospheric vent 1-1/4" (31.75 mm)
- Top-mounted fuel level sensor with control panel alarms
- Top-mounted leak detection switch
- Lockable fuel fill cap, 4" (101.6 mm) NPT

Description


- Dual wall, secondary containment
- Pressure tested to UL requirements
- Fuel tank mounts directly below generator skid base
- Modular tank design is compatible with all factory units open and enclosed

Attachments



C4.4, and C7.1 Sub-base Fuel Tank Dimensions and Capacities

Engine	Tank	Generator	Est. Run	Filla Capa		Usa Capa	ible acity	Vent	Lenç	gth 'L'	Widtl	า 'W'	Heig	ht 'H'	We (D	ight ry)
Model	Feature Code	Set Rating ekW	Time hrs	L	gal	L	gal	in	mm	in	mm	in	mm	in	kg	lb
C4.4	FSBTC24	80 100	30 25	793	209	733	194	3	2447	125.7			485	19.1	526	1160
C4.4	FSBTD48	80 100	58 49	1492	394	1432	378	4	3447	135.7			835	32.9	739	1629
C7.1	FSBTI24	125 150 175 200	40 35 29 27	1520	402	1495	395	4	4035	158.9	1000	39.4	647	25.5	720	1587
67.1		125 150	78 68													
	FSBTJ48	175	57	2940	777	2918	771	5	5035	198.2			933	36.7	1145	2524
		200	52													



Note: For reference only – do not use for installation design. Please contact your local dealer for exact dimensions.

Tanks are UL Listed and constructed in accordance with UL Standard for Safety UL 142, Steel Aboveground Tanks for Flammable and Combustible Liquids and Canada CAN/ULC S601, Standard for Shop Fabricated Steel Aboveground Horizontal Tanks for Flammable and Combustible Liquids.

Fuel tanks facilitate compliance with the following United States NFPA Code and Standards:

- NFPA 30: Flammable and Combustible Liquids Code
- NFPA 37: Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines
- NFPA 110: Standard for Emergency and Standby Power Systems

Fuel tanks facilitate compliance with the following Canadian Standard and Code:

- CSA C282 Emergency Electrical Pow er Supply for Buildings
- CSA B139-09 Installation Code for Oil-Burning Equipment





FUEL LEVEL ALARMS - FSS

CRITICAL LOW FUEL LEVEL SHUTDOWN AND LOW FUEL LEVEL ALARM

These options provide an alarm on low fuel level and a shutdown on critical low fuel level. This warning is reported by an indicator light on the control panel with an audible alarm also available as an option. This warning can additionally be relayed to a remote annunciator.

Note: Standard Fuel Fill, UL Rated Emergency-vent, Standard vent, Fuel Sender & Leak Detection Probe are included as standard on generator sets fitted with UL Listed fuel tanks.

CRITICAL HIGH FUEL LEVEL ALARM

This option provides an alarm on critical high fuel level. This warning is reported by an indicator light on the control panel with an audible alarm also available as an option. This warning can additionally be relayed to a remote annunciator.

Information contained in this publication may be considered confidential. Discretion is recommended when distributing.

Materials and specifications are subject to change without notice.

CAT, CATERPILLAR, LET'S DO THE WORK, their respective logos, "Caterpillar Corporate Yellow," the "Power Edge" and Cat "Modern Hex" trade dress as well as corporate and product identity used herein, are trademarks of Caterpillar and may not be used without permission.





Inches of Fuel Massured College Inches of Fuel Massured College									
Inches of Fuel on Dipstick	Measured Gallons	Inches of Fuel on Dipstick	Measured Gallo						
0.5	11.3	24.0	541.9						
1.0	22.6	24.5	553.1						
1.5	33.9	25.0	564.4						
2.0	45.2	25.5	575.7						
2.5	56.4	26.0	587.0						
3.0	67.7	26.5	598.3						
3.5	79.0	27.0	609.6						
4.0	90.3	27.5	620.9						
4.5	101.6	28.0	632.2						
5.0	112.9	28.5	643.5						
5.5	124.2	29.0	654.7						
6.0	135.5	29.5	666.0						
6.5	146.8	30.0	677.3						
7.0	158.0	30.5	688.6						
7.5	169.3	31.0	699.9						
8.0	180.6	31.5	711.2						
8.5	191.9	32.0	722.5						
9.0	203.2	32.5	733.8						
9.5	214.5	33.0	745.0						
10.0	225.8	33.5	756.3						
10.5	237.1		767.6						
		34.0							
11.0	248.3	34.5	778.9						
11.5	259.6	35.0	790.2						
12.0	270.9	35.5	801.5						
12.5	282.2								
13.0	293.5								
13.5	304.8								
14.0	316.1								
14.5	327.4								
15.0	338.7								
15.5	349.9								
16.0	361.2								
16.5	372.5								
17.0	383.8								
17.5	395.1								
18.0	406.4								
18.5	417.7								
19.0	429.0								
19.5	440.3								
20.0	451.5								
20.5	462.8								
21.0	474.1								
21.5	485.4		1						
22.0	496.7								
22.5	508.0								
23.0	519.3								
23.5	530.6								
24.0	541.9		+						



Austin • Brownsville • Corpus Christi • Dallas • Edinburg • Ft Worth • Laredo • Longview • Pflugerville • San Antonio • Victoria • Waco

MECHANICAL DRAWINGS





ATTACHMENT D

Attachment D - Spill and Overfill Control

The Clara Vista Lift Station and Force Main Aboveground Storage Tank (AST) Facility Plan proposes one (1) fuel tanks for storage of diesel fuel to service lift station machinery in the event of an emergency. This 777-gallon tank is located within an overall fenced and gated 0.086-acre lift station. The tank will be located on a 112 square foot concrete pad above 3727 square feet of concrete pavement. The tank will be surrounded by removable bollards.

Fuel Tank Description

The proposed aboveground storage tank will be used to store diesel to fuel lift station machinery for the Clara Vista Lift Station in the event of an emergency. The double-walled steel tanks are both constructed to the UL-142 standard. The tank is constructed of materials that are compatible with the liquids stored (diesel) within and have the appropriate safety equipment, such as primary and emergency venting and overfill protection.

The primary tank is wholly contained within the 870-gallon secondary tank, and the interstitial space between the tanks is hollow. If failure occurs in the primary tank, all fuel will be trapped within the secondary tank. Additionally, the tank will be regularly maintained by qualified personnel.

Holt-CAT C7.1 Sub-base fuel tank includes the following features:

- a. Double-wall, steel construction tanks
- b. Top-mounted fuel level sensor with control panel alarms
- c. Top-mounted leak detection switch
- d. Manual shut-off
- e. Emergency vents on primary and secondary tanks in accordance with NFPA 30

AST Filling

Spill prevention for the AST filling will be achieved at the fuel filling with a lockable cap. This system includes all valves and fittings necessary for hose connection from the pumper truck. Human presence and observation of the filling process is another means to prevent spills and overfills. There shall be an experienced, trained person at the fill point at all times that a fill operation is taking place. The refueling tanker trucks are equipped with fuel spill containment kits for minor spills.

ATTACHMENT E

Attachment E - Response Actions to Spills

General Measures:

- To the extent that the work product can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110, 117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Develop an inventory of potentially polluting materials, including their estimated quantities and size
 and number of storage containers. Use inventory to determine the size and type of spill kits that
 should be present at the site.
- Store hazardous materials and wastes in covered containers and prevent form vandalism.
- Provide spill-cleanup kits at locations where spills are most likely to occur, such as fueling and maintenance areas. Kits are available from several manufacturers or may be prepared by the facility owner. Each spill kit should have sufficient adsorbent capacity to handle a spill of the largest movable container at that location.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from stormwater run-on during rainfall to the extent that it does not compromise clean-up activities.
- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup and spill reporting
 instructions for hazardous materials stored or used on the site in an open, conspicuous, and accessible
 location.

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.

- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the
 analysis results are known the contaminated soils and cleanup materials will be removed from the
 site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:


The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. https://www.tceq.texas.gov/response/spills/spill-rq.html
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

• Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

SITE PLAN




25.86

Total

3.10

2.50

0.59



LEGEND ----

> OFFSITE 3A 3.92 AC WATERSHED ACREAGE

FLOW DIRECTION

PROPOSED WATERSHED

CALCULATED EXISTING 100-YR FLOODPLAIN CALCULATED PROPOSED 100-YR FLOODPLAIN

WATERWAY BUFFER ZONE

NOTES

526

526

NO ADDITIONAL IMPERVIOUS COVER IS PROPOSED TO BE ADDED IN DRAINAGE AREA UNCAPTURED 4.

CLARA

DRAINAGE


QUALITY

WATER

CITY JOB No. CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 12 OF 54

Treatment Summary Table
Current Application - Hawkes Landing North Phase 1 Required TSS Designed TS Total Net Total Existing Total Proposed Watershed Area BMP Impervious Cover Watershed Impervious Cover Removal Impervious Cover (lbs./yr.) (lbs./yr.) (acres) (acres) (acres) 0.26 ENGINEEREDVFS1 0.09 0.08 VFS 1 ENGINEERED VFS2 0.10 0.03 0.00 0.03 VFS 2 0.06 0.02 0.02 ENGINEEREDVFS3 14 14 0.00 VFS 3 1.27 0.33 0.33 292 310 0.00 ENGINEEREDVFS4 VFS 4 104 104 0.18 0.00 0.12 0.12 ENGINEERED VFS5 VFS 5
UNCAPTURED1 0.09 0.02 OVERTREATMENT BY ENGINEERED VFS4 0.00 0.02 0.36 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) UNCAPTURED2 0.00 0.00 UNCAPTURED3 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.00 UNCAPTURED4 11.25 2.50 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 2.50 OFFSITE1 0.45 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.64 OFFSITE2 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) OFFSITE3 0.16 0.00 0.00 0.00 OFFSITE4 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 5.60 0.00 0.00 0.00 OFFSITE5 5.43 0.00 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED)

S DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



TEMPORARY STORMWATER SECTION (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Aimee Chavez, P.E.

Date: 8/29/25

Signature of Customer/Agent:

Umei (

Regulated Entity Name: Clara Vista Lift Station & Force Main

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

some serior remained to all and planting remained and a single serior rema			
1.	Fuels for construction equipment and hazardous substances which will be used during construction:		
	The following fuels and/or hazardous substances will be stored on the site: <u>Diesel Fuel Gasoline</u> , etc.		
	These fuels and/or hazardous substances will be stored in:		
	Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.		

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
	Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
Se	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6.	Name the receiving water(s) at or near the site which will be disturbed or which will

Temporary Best Management Practices (TBMPs)

receive discharges from disturbed areas of the project: Blanco River

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

		A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
		A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
		A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
		A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.		The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
		Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
		There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.		Attachment F - Structural Practices . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	\boxtimes	Attachment G - Drainage Area Map . A drainage area map supporting the following requirements is attached:
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
		For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
		For areas that will have more than 10 acres within a common drainage area
		disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
		There are no areas greater than 10 acres within a common drainage area that will be
		disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. 🗌	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
	N/A
12. 🔀	Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. 🔀	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. 🔀	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. 🔀	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. 🔀	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A

Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

- Visit TCEQ's Reportable Quantities site: https://www.tceq.texas.gov/response/spills/spill rq.html
- The contractor will be required to report significant or hazardous spills in reportable quantities as soon as possible and within 24 hours to:
 - the National Response Center at (800) 424-8802
 - the TCEQ Regional Office (512) 339-2929 (if during business hours: 8 AM to 5 PM) or
 - the State Emergency Response Center (800) 832-8224 (if after hours)

• Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

ATTACHMENT B

POTENTIAL SOURCES OF CONTAMINATION

Potential Source • Asphalt products used on this project.

Preventative Measure

After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain.

Potential Source

Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping.

Preventative Measure

- Vehicle maintenance when possible will be performed within the construction staging area.
- Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.

Potential Source

Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.

Preventative Measure

- Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.
- Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.

- Hazardous materials and wastes shall be stored in covered containers and protected from vandalism.
- A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.

Potential Source

 Miscellaneous trash and litter from construction workers and material wrappings.

Preventive Measure

 Trash containers will be placed throughout the site to encourage proper trash disposal.

Potential Source

Construction debris.

Preventive Measure

Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

Potential Source

Spills/Overflow of waste from portable toilets

Preventative Measure

- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

ATTACHMENT C

SEQUENCE OF MAJOR ACTIVITIES

The sequence of major activities which disturb soil during construction on this site are listed below.

- 1) Set erosion controls approximately 1,912 LF of silt fence
- 2) Clear and grub approximately 2.72 acres
- 3) Rough grade roadway approximately 0.82 acres
- 4) Rough grade lift station approximately 0.23 acres
- 5) Trench utilities approximately 1,461 LF
- 6) Install water, wastewater, and storm approximately 1,461 LF
- 7) Install sub base/base for road/parking areas approximately 0.59 acres
- 8) Pave roadway/parking areas approximately 0.46 acres
- 9) Site cleanup approximately 2.72 acres
- 10) Remove erosion controls approximately 1,912 LF of silt fence

ATTACHMENT D

TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

Please see the Erosion Control sheets included in the Construction Plans Section for TBMP layout and the responses below for more details.

Due to existing topography, upgradient stormwater from adjacent property north of the site enters the property and flows from north to south through the lift station project limits. As this upgradient area is currently undeveloped and undisturbed, sedimentation from off-site areas is not anticipated. All TBMPs utilized are adequate for the drainage areas served.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activities on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter the aquifer, surface streams and/or sensitive features that may exist downstream of the site.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter the aquifer, surface streams and/or sensitive features that may exist downstream of the site.

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site. Features discovered during construction will be reported and assessed in accordance with applicable regulations.

ATTACHMENT F

STRUCTURAL PRACTICES


The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms
 for secondary protection, as located on the Erosion Control sheets and illustrated on the
 Construction Details Erosion Controls sheet.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on the Erosion Control sheets and illustrated on the Construction Details Erosion Controls sheet.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

- Installation of concrete truck washout pit(s), as required and located on the Erosion Control sheets and illustrated on the Construction Details Erosion Controls sheet.
- Installation of rock berm, as required and located on the Erosion Control sheets and illustrated on the Construction Details Erosion Controls sheet.

ATTACHMENT G




25.86

Total

3.10

2.50

0.59



LEGEND ----

> OFFSITE 3A 3.92 AC WATERSHED ACREAGE

FLOW DIRECTION

PROPOSED WATERSHED

CALCULATED EXISTING 100-YR FLOODPLAIN CALCULATED PROPOSED 100-YR FLOODPLAIN

WATERWAY BUFFER ZONE

NOTES

526

526

NO ADDITIONAL IMPERVIOUS COVER IS PROPOSED TO BE ADDED IN DRAINAGE AREA UNCAPTURED 4.

CLARA

DRAINAGE

QUALITY

WATER

CITY JOB No. CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 12 OF 54

Treatment Summary Table
Current Application - Hawkes Landing North Phase 1 Required TSS Designed TS Total Net Total Existing Total Proposed Watershed Area BMP Impervious Cover Watershed Impervious Cover Removal Impervious Cover (lbs./yr.) (lbs./yr.) (acres) (acres) (acres) 0.26 ENGINEEREDVFS1 0.09 0.08 VFS 1 ENGINEERED VFS2 0.10 0.03 0.00 0.03 VFS 2 0.06 0.02 0.02 ENGINEEREDVFS3 14 14 0.00 VFS 3 1.27 0.33 0.33 292 310 0.00 ENGINEEREDVFS4 VFS 4 104 104 0.18 0.00 0.12 0.12 ENGINEERED VFS5 VFS 5
UNCAPTURED1 0.09 0.02 OVERTREATMENT BY ENGINEERED VFS4 0.00 0.02 0.36 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) UNCAPTURED2 0.00 0.00 UNCAPTURED3 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.00 UNCAPTURED4 11.25 2.50 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 2.50 OFFSITE1 0.45 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.64 OFFSITE2 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) OFFSITE3 0.16 0.00 0.00 0.00 OFFSITE4 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 5.60 0.00 0.00 0.00 OFFSITE5 5.43 0.00 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED)

S DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

ATTACHMENT I

INSPECTIONS & MAINTENANCE

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection will be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Contributing Zone Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable. Temporary sediment basins and permanent basins will be inspected until final stabilization of 70% within the basin watershed is achieved.

BMP inspection and maintenance requirements from sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual are detailed below.

Temporary Construction Entrance/Exit

 The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment.

- All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor.
- When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
- When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
- All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

Silt Fence

- Inspect all fencing weekly, and after any rainfall.
- Remove sediment when buildup reaches 6 inches.
- Replace any torn fabric or install a second line of fencing parallel to the torn section.
- Replace or repair any sections crushed or collapsed in the course of construction
 activity. If a section of fence is obstructing vehicular access, consider relocating it to
 a spot where it will provide equal protection, but will not obstruct vehicles. A
 triangular filter dike may be preferable to a silt fence at common vehicle access
 points.
- When construction is complete, the sediment should be disposed of in a manner that
 will not cause additional siltation and the prior location of the silt fence should be
 revegetated. The fence itself should be disposed of in an approved landfill.

Rock Berms

- Inspection should be made weekly and after each rainfall by the responsible party.
 For installations in streambeds, additional daily inspections should be made.
- Remove sediment and other debris when buildup reaches 6 inches and dispose of the accumulated silt in an approved manner that will not cause any additional siltation.
- Repair any loose wire sheathing.
- The berm should be reshaped as needed during inspection.

- The berm should be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.
- The rock berm should be left in place until all upstream areas are stabilized and accumulated silt removed.

Pollution Corrective A		Corrective Act	tion Required	
Prevention	ed in	Description		Date
Measure	Inspected in Compliance	(use additional sheet if neces	ssary)	Completed
Best Management Practices				
Natural vegetation buffer strips				
Temporary vegetation				
Permanent vegetation				
Sediment control basin				
Silt fences				
Rock berms				
Gravel filter bags				
Drain inlet protection				
Other structural controls				
Vehicle exits (off-site tracking)				
Material storage areas (leakage)				
Equipment areas (leaks, spills)				
Concrete washout pit (leaks, failure)				
General site cleanliness				
Trash receptacles				
Evidence of Erosion				
Site preparation				
Roadway or parking lot construction				
Utility construction				
Drainage construction				
Building construction				
Major Observations				
Sediment discharges from site				
BMPs requiring maintenance				
BMPs requiring modification				
Additional BMPs required				
A brief statement describing the certify under penalty of law that this document and all attassure that qualified personnel properly gather and evaluate those persons directly responsible for gathering the informationam aware there are significant penalties for submitting false in further certify I am an authorized signatory in accordance with the control of the certify I am an authorized signatory in accordance with the certify I am an authorized signatory in accordance with the certify I am an authorized signatory in accordance with the certify I am an authorized signatory in accordance with the certification of the certification	chments he inform n, the info nformatio	were prepared under my direction or supervis ation submitted. Based on my inquiry of the p ormation submitted is, to the best of my knowle on, including the possibility of fine and imprison	ion in accordance verson or persons whedge and belief, true	with a system designed to no manage the system, o e, accurate, and complete
nspector's Name	Inspe	ctor's Signature	Date	

PROJECT MILESTONE DATES

Date when major site grading activities begin:

Construction Activity		Date
Installation of BMPs		
	-	
	_	
	_	
	- -	
	 	
Dates when construction activities temporarily or perm	anentiy (
Construction Activity	_	Date
	_	
	_	
	_	
	<u> </u>	
	_	
Dates when stabilization measures are initiated:		
Stabilization Activity		Date
	- -	
	_	
	_	
Removal of BMPs	_	

ATTACHMENT J

SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized via permanent revegetation. Details, such as installation, irrigation, and maintenance are provided below.

Installation:

- Final grading must be completed prior to seeding, minimizing all steep slopes. In addition, all necessary erosion structures such as dikes, swales, diversions, should also be installed.
- Seedbed should be well pulverized, loose, and uniform.
- Fertilizer should be applied at the rate of 40 pounds of nitrogen and 40 pounds of phosphorus
 per acre, which is equivalent to about 1.0 pounds of nitrogen and phosphorus per 1000 square
 feet. Compost can be used instead of fertilizer and applied at the same time as the seed.

Irrigation:

• Temporary irrigation should be provided according to the schedule described below, or to replace moisture loss to evapotranspiration (ET), whichever is greater. Significant rainfall (onsite rainfall of ½" or greater) may allow watering to be postponed until the next scheduled irrigation.

Time Period	Irrigation Amount and Frequency
Within 2 hours of installation	Irrigate entire root depth, or to germinate seed
During the next 10 business days	Irrigate entire root depth every Monday, Wednesday, and Friday
During the next 30 business days or until Substantial Completion	Irrigate entire root depth a minimum of once per week, or as necessary to ensure vigorous growth
During the next 4 months or until Final Acceptance of the Project	Irrigate entire root depth once every two weeks, or as necessary to ensure vigorous growth

Inspection and Maintenance Guidelines:

 Permanent vegetation should be inspected weekly and after each rain event to locate and repair any erosion.

- Erosion from storms or other damage should be repaired as soon as practical by regrading the area and applying new seed.
- If the vegetated cover is less than 80%, the area should be reseeded.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.

PERMANENT STORMWATER

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(Ii), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: <u>Aimee Chavez, P.E.</u>

Date: <u>August 22, 2025</u>

Signature of Customer/Agent

Regulated Entity Name: Clara Vista Lift Station & Force Main

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

1.	Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.
	□ N/A
2.	These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
	The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

	A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is:
	□ N/A
3.	Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
	□ N/A
4.	Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	 The site will be used for low density single-family residential development and has 20% or less impervious cover. The site will be used for low density single-family residential development but has more than 20% impervious cover.
	$oxed{\boxtimes}$ The site will not be used for low density single-family residential development.
5.	The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
	 Attachment A - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached. □ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover. □ The site will not be used for multi-family residential developments, schools, or small business sites.
6.	Attachment B - BMPs for Upgradient Stormwater.

		 A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached. No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached. Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7.	\boxtimes	Attachment C - BMPs for On-site Stormwater.
		 A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached. Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8.		Attachment D - BMPs for Surface Streams . A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
		N/A
9.		The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
		 The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed. Attachment E - Request to Seal Features. A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10.		Attachment F - Construction Plans . All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
		 ☑ Design calculations (TSS removal calculations) ☑ TCEQ construction notes ☑ All geologic features ☑ All proposed structural BMP(s) plans and specifications
		N/A

inspe	chment G - Inspection, Maintenance, Repair and Retrofit Plan . A plan for the ection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and sures is attached. The plan includes all of the following:
m Si P	repared and certified by the engineer designing the permanent BMPs and neasures igned by the owner or responsible party rocedures for documenting inspections, maintenance, repairs, and, if necessary etrofit discussion of record keeping procedures
☐ N/A	
recog	chment H - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not gnized by the Executive Director require prior approval from the TCEQ. A plan for scale field testing is attached.
⊠ N/A	
of the and c and c creat by th	chment I -Measures for Minimizing Surface Stream Contamination. A description e measures that will be used to avoid or minimize surface stream contamination changes in the way in which water enters a stream as a result of the construction development is attached. The measures address increased stream flashing, the cion of stronger flows and in-stream velocities, and other in-stream effects caused be regulated activity, which increase erosion that results in water quality addation.
☐ N/A	
Respons	sibility for Maintenance of Permanent BMP(s)
=	ty for maintenance of best management practices and measures after is complete.
until entit owne owne respo	applicant is responsible for maintaining the permanent BMPs after construction such time as the maintenance obligation is either assumed in writing by another y having ownership or control of the property (such as without limitation, an er's association, a new property owner or lessee, a district, or municipality) or the ership of the property is transferred to the entity. Such entity shall then be onsible for maintenance until another entity assumes such obligations in writing or ership is transferred.
☐ N/A	
appro multi or a r	py of the transfer of responsibility must be filed with the executive director at the opriate regional office within 30 days of the transfer if the site is for use as a iple single-family residential development, a multi-family residential development, non-residential development such as commercial, industrial, institutional, schools, other sites where regulated activities occur.
N/A	

ATTACHMENT B

Attachment B - BMPs for Upgradient Stormwater

Fifteen-foot (15') wide Engineered Vegetative Strips (VFS) are proposed as the Permanent Best Management Practices (PBMPs) for all upgradient stormwater. All PBMPs have been designed in accordance with the TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) to remove 85% of the increase in Total Suspended Solids (TSS) from the site.

ATTACHMENT C

<u>Attachment C – BMPs for On-Site Stormwater</u>

Fifteen-foot (15') wide Engineered Vegetative Strips (VFS) are proposed as the Permanent Best Management Practices (PBMPs) for this site. All PBMPs have been designed in accordance with the TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) to remove 85% of the increase in Total Suspended Solids (TSS) from the site.

ATTACHMENT D

<u>Attachment D – BMPs for Surface Streams</u>

Fifteen-foot (15') wide Engineered Vegetative Strips (VFS) are proposed as the Permanent Best Management Practices (PBMPs) for this site. All PBMPs have been designed in accordance with the TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) to remove 85% of the increase in Total Suspended Solids (TSS) from the site.

ATTACHMENT F

Will Atkinson, Planning Director Jacon Lutz

Hays County Commisioners Court Hays County, Texas

FAX (512) 459-8867

ENGINEER/SURVEYOR: PAPE-DAWSON CONSULTING ENGINEERS, LLC. 10801 N MOPAC EXPY., BLDG. 3, SUITE 200 AUSTIN, TEXAS 78759

OWNER/DEVELOPER: TOLL BROTHERS 1320 ARROW POINT DR., SUITE 401 CEDAR PARK, TX 78613 (412) 780-2312

DATE

PROJECT NO. CP-23-0150 ZONING: R-1-1 SINGLE FAMILY RESIDENTIAL

DEVELOPMENT AGREEMENT: BLANCO RIVER RANCH (PHASE TWO RESIDENTIAL-SAVANNAH DISTRICT) DEVELOPMENT AGREEMENT FILED: RECORED 4/19/2022

THE ENGINEER OF RECORD IS SOLELY RESPONSIBLE FOR THE COMPLETENESS, ACCURACY, REGULATORY COMPLIANCE, AND ADEQUACY OF THESE PLANS AND / OR SPECIFICATIONS WHETHER OR NOT THE PLANS AND/OR SPECIFICATIONS WERE REVIEWED BY THE CITY ENGINEER(S).

THE TRACT SHOWN HEREON LIES WITHIN ZONE "AE" AND ZONE "A" AS IDENTIFIED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY, FEDERAL INSURANCE ADMINISTRATION, AS SHOWN ON MAP NO. 48209C0270F, DATED SEPTEMBER 02, 2005 FOR HAYS COUNTY, TEXAS AND INCORPORATED


THIS FLOOD PLAIN NOTE DOES NOT IMPLY THAT THE PROPERTY AND/OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. THIS FLOOD STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.

<u>WATERSHED:</u>
THIS SUBDIVISION IS LOCATED WITHIN THE BLANCO RIVER WATERSHED.

ENVIRONMENTAL:
THIS SUBDIVISION PROJECT IS LOCATED IN THE EDWARDS AQUIFER CONTRIBUTING ZONE WITHIN THE TRANSITION ZONE.

CLARA VISTA LIFT STATION & FORCE MAIN

PUBLIC IMPROVEMENTS CONSTRUCTION PLANS PROJECT NO. CP-22-0144 CITY OF KYLE ETJ HAYS COUNTY, TEXAS



Sheet Number Sheet Title COVER 2 GENERAL NOTES 3 TCEQ NOTES 4 EROSION AND SEDIMENTATION CONTROL PLAN 1 OF 7 5 EROSION AND SEDIMENTATION CONTROL PLAN 2 OF 7 EROSION AND SEDIMENTATION CONTROL PLAN 3 OF 7 EROSION AND SEDIMENTATION CONTROL PLAN 4 OF 7 EROSION AND SEDIMENTATION CONTROL PLAN 5 OF 7 9 EROSION AND SEDIMENTATION CONTROL PLAN 6 OF 7 EROSION AND SEDIMENTATION CONTROL PLAN 7 OF 7 11 TREE PRESERVATION PLAN TREE LIST WATER QUALITY DRAINAGE MAP 12 13 SEWERSHED PLAN 14 OVERALL LAYOUT 15 WASTEWATER PROFILES WW-1A 1 OF 2 16 WASTEWATER PROFILES WW-1A 2 OF 2 FORCE MAIN PROFILES FM-1A 1 OF 11 17 18 FORCE MAIN PROFILES FM-1A 2 OF 11 19 FORCE MAIN PROFILES FM-1A 3 OF 11 20 FORCE MAIN PROFILES FM-1A 4 OF 11 21 FORCE MAIN PROFILES FM-1A 5 OF 11 22 FORCE MAIN PROFILES FM-1A 6 OF 11 23 FORCE MAIN PROFILES FM-1A 7 OF 11 24 FORCE MAIN PROFILES FM-1A 8 OF 11 25 FORCE MAIN PROFILES FM-1A 9 OF 11 26 FORCE MAIN PROFILES FM-1A 10 OF 11 27 FORCE MAIN PROFILES FM-1A 11 OF 11 & WW-1B 28 TRAFFIC CONTROL PLAN 29 EROSION & SEDIMENTATION CONTROL DETAILS 30 WASTEWATER DETAILS 31 LIFT STATION SITE PLAN LIFT STATION GRADING, PAVING & DRAINAGE 32 33 LIFT STATION CIVIL DETAILS 34 LIFT STATION MECHANICAL PLAN & SECTION LIFT STATION MECHANICAL DETAILS STRUCTUAL ELEVATION AND DETAILS 37 STRUCTURAL NOTES AND DISCHARGE PIPING DETAILS 38 STRUCTURAL VALVE VAULT PLAN AND DETAILS 39 MISCELLANEOUS STRUCTURAL DETAILS 40 ELECTRICAL LEGENDS SCHEDULES AND NOTES 41 ELECTRICAL SITE LAYOUT 42 ELECTRICAL ONE-LINE DIAGRAM 43 LIFT STATION ELECTRICAL DETAILS 1 OF 6 44 LIFT STATION ELECTRICAL DETAILS 2 OF 6 45 LIFT STATION ELECTRICAL DETAILS 3 OF 6 46 LIFT STATION ELECTRICAL DETAILS 4 OF 6 LIFT STATION ELECTRICAL DETAILS 5 OF 6 48 LIFT STATION ELECTRICAL DETAILS 6 OF 6 ODOR CONTROL ELECTRICAL NOTES SYMBOLS AND ABBREVIATIONS 49 50 ODOR CONTROL ELECTRICAL SPECIFICATIONS 51 ODOR CONTROL ELECTRICAL SITE PLAN 52 ODOR CONTROL ELECTRICAL SCHEDULES 53 ODOR CONTROL ELECTRICAL DETAILS 1 OF 2 54 ODOR CONTROL ELECTRICAL DETAILS 2 OF 2

Sheet List Table

SUBMITTED BY:

I, MICHAEL S. FISHER, P.E. # 87704, DO HEREBY CERTIFY THAT THE ENGINEERING WORK BEING SUBMITTED HEREIN COMPLIES WITH ALL THE PROVISION OF THE TEXAS ENGINEERING PRACTICE ACT, INCLUDING 131.152 (e). I HEREBY ACKNOWLEDGE THAT ANY MISREPRESENTATION REGARDING THIS CERTIFICATION CONSTITUTES A VIOLATION OF THE ACT, AND MAY RESULT IN CRIMINAL, CIVIL AND/OR ADMINISTRATIVE PENALTIES AGAINST ME, AS AUTHORIZED BY THE ACT.



PAPE-DAWSON CONSULTING ENGINEERS, LLC MICHAEL S. FISHER, P.E. #87704

4/11/25

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S SIGNATURE AND SEAL.



AUSTIN I SAN ANTONIO I HOUSTON I FORT WORTH I DALLAS 10801 N MOPAC EXPY, BLDG 3, STE 200 I AUSTIN, TX 78759 I 512.454.8711 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028801

SHEET 1 OF 54

ALL CONSTRUCTION IS TO BE IN ACCORDANCE WITH THE FOLLOWING REGULATIONS AND SPECIFICATIONS THE FIRST LISTED WILL HAVE PRIORITY OVER THOSE LISTED BELOW:

PERMITS ISSUED FOR PROJECT BY ANY REGULATORY AGENCIES. TEXAS COMMISSION ON ENVIRONMENTAL QUALITY REGULATIONS. CITY OF KYLE CONSTRUCTION STANDARDS. PLANS FOR THIS PROJECT.

2. PRIOR TO THE BEGINNING OF CONSTRUCTION, THE DEVELOPER SHALL ARRANGE A PRE-CONSTRUCTION CONFERENCE. PRE-CONSTURCTION SHALL BE SCHEDULED WITH THE PW OFFICE, 512-262-3024 AND HELD AT THE PW FACILITY LOCATED AT 520 E RR150, KYLE, TEXAS. EPRESENTATIVES FROM THE FOLLOWING ORGANIZATIONS SHALL BE INVITED:

CITY OF KYLE STAFF INCLUDING THE DIRECTOR OF PUBLIC WORKS, CITY ENGINEER AND THE PUBLIC WORKS INSPECTOR.

CONTRACTOR

DESIGN ENGINEER. ELECTRIC, GAS, PHONE AND CABLE UTILITY REPRESENTATIVES, IF APPROPRIATE.

3. PRIOR TO THE BEGINNING OF CONSTRUCTION, ALL PLAN REVIEW AND CONSTRUCTION INSPECTION FEES SHALL BE PAID TO THE CITY OF KYLE AND THE FOLLOWING PERMITS SHALL BE IN PLACE, IF NECESSARY:

TEXAS DEPARTMENT OF TRANSPORTATION, ENTRY ONTO A HIGHWAY CORPS OF ENGINEERS, SECTION 404, FOR CONSTRUCTION IN

FLOOD PLAIN. COMPLIANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) TEXAS POLLUTANT DISCHARGE ELIMINATION SYSTEM (TPDES) CONSTRUCTION GENERAL PERMIT (TXR150000).

TEXAS DEPARTMENT OF LICENSING AND REGULATION FOR ACCESSIBILITY. TCEQ FOR SIGNIFICANT WATER AND WASTEWATER FACILITIES, INCLUDING LIFT STATIONS.

4. BENCHMARKS FOR THIS PROJECT ARE DESCRIBED AS FOLLOWS:

5. ANY EXISTING PAVEMENT, CURBS, AND/OR SIDEWALKS DAMAGED OR REMOVED SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE BEFORE ACCEPTANCE OF THE SUBDIVISION.

6. THE CONTRACTOR SHALL GIVE THE CITY OF KYLE (PHONE NO. 512-262-3024), 48 HOURS NOTICE PRIOR TO CONNECTING TO ANY EXISTING CITY UTILITY LINE.

SIDEWALKS FRONTING PUBLIC RIGHT-OF-WAY LAND OR INCLUDING ALL SIDEWALK RAMPS REQUIRED BY CITY ORDINANCE SHOWN ON THESE PLANS SHALL BE CONSTRUCTED WITH THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR WARNING AND SAFETY SIGNS, BARRICADES AND TRAFFIC CONTROL DURING CONSTRUCTION. ALL ROAD SIGNAGE SHALL CONFORM TO THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

9. CONTRACTOR SHALL MAKE ARRANGEMENTS WITH THE CITY OF KYLE FOR THE USE OF ALL WATER FOR CONSTRUCTION.

10. ALL FILL OR CUT ON LOTS WHICH IS GREATER THAN TWELVE (12) INCHES SHALL BE SHOWN ON THE PLANS AND SHALL CONFORM TO THE FOLLOWING:

FILL MATERIAL SHALL NOT CONTAIN ANY ROCKS HAVING A MAXIMUM DIMENSION GREATER THAN SIX (6) INCHES.

FILL MATERIAL SHALL HAVE AT LEAST FIFTY PERCENT (50%) PASSING THE NO. 4 SIEVE.

FILL MATERIAL SHALL BE REASONABLY FREE OF ROOTS, TRASH, CONCRETE RUBBLE AND OTHER ORGANIC MATERIAL.

COMPACTION SHALL BE TO NINETY-FIVE PERCENT (95%) OF MAXIMUM LABORATORY DENSITY DETERMINED IN ACCORDANCE WITH THE ASTM D 698. THE MATERIAL SHALL BE WITHIN THREE (3) PERCENTAGE POINTS OF OPTIMUM MOISTURE CONTENT DURING COMPACTION.

PLACEMENT SHALL BE IN LIFTS NOT EXCEEDING EIGHT (8) INCHES AFTER COMPACTION. EACH COMPACTED LIFT SHOULD BE INSPECTED AND/OR TESTED FOR DENSITY COMPLIANCE BY A GEOTECHNICAL ENGINEER PRIOR TO PLACING THE NEXT LIFT. THE FILL AREA SHOULD EXTEND AT LEAST 24 INCHES (36 INCHES ON FILLS OVER SIX (6) FEET IN HEIGHT) BEYOND THE BACK OF CURB OR FOUNDATION LINE BEFORE SLOPING DOWNWARD ON NOT MORE THÁN THREE (3) TÓ ONE (1) SLOPE TO NATURAL SOIL. BACKSLOPES SHALL BE WELL COMPACTED. MAXIMUM FILL HEIGHTS SHOULD NOT EXCEED TEN (10) FEET WITHOUT ENGINEERING CONSULTATION.

11. CONTRACTOR SHALL GIVE CITY INSPECTOR 36 HOURS NOTICE OF THE NEED FOR MATERIALS TESTING. ALL TESTING WILL BE ARRANGED AND PAID FOR BY THE CONTRACTOR. THE CITY SHALL RECEIVE A COPY OF TEST RESULTS.

12. CONTRACTOR OR THE DESIGN ENGINEER SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING AND CUT SHEETS FOR PIPE LINES LAID ON GRADE AND ROAD CONSTRUCTION. CUT SHEETS SHALL BE DELIVERED TO THE CITY INSPECTOR 36 HOURS PRIOR TO CONSTRUCTION.

13. IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, ALL TRENCHES OVER 5 FEET IN DEPTH IN EITHER HARD AND STABLE OR SOFT AND UNSTABLE SOIL SHALL BE SLOPED, SHORED, SHEETED, BRACED OR OTHERWISE SUPPORTED. FURTHERMORE. ALL TRENCHES LESS THAN 5 FEET IN DEPTH SHALL ALSO BE EFFECTIVELY PROTECTED WHEN HAZARDOUS GROUND MOVEMENT MAY BE EXPECTED. TRENCH SAFETY SYSTEMS TO BE UTILIZED FOR THIS PROJECT SHALL BE PROVIDED BY THE CONTRACTOR.

15. NO TREES OVER 6 INCHES IN DIAMETER SHALL BE REMOVED UNLESS DESIGNATED TO BE REMOVED ON THE APPROVED PLANS. ALL TREE LIMBS REMOVED OR TRIMMED SHALL BE VERTICALLY CUT AND DRESSED.

16. ALL CONSTRUCTION ACTIVITIES SHALL BE CONFINED TO PROPERTY OWNED BY THE DEVELOPER OR PUBLIC RIGHT-OF-WAY AND EASEMENT UNLESS WRITTEN PERMISSION IS OBTAINED BY THE CONTRACTOR FROM THE PROPERTY OWNER AFFECTED.

17. THE CITY OF KYLE DOES NOT ALLOW ANY BLASTING WITHIN THE CITY LIMITS.

TYPICAL SEQUENCE OF CONSTRUCTION

HOLD PRE-CONSTRUCTION CONFERENCE.

2. NO CLEARING OR ROUGH GRADING MAY BE DONE UNTIL THE APPROVED EROSION AND SEDIMENTATION CONTROLS ARE IN PLACE.

3. INSTALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS AND STABILIZATION CONSTRUCTION ENTRANCE, IF REQUIRED, IN THE APPROVED PLANS.

ROUGH GRADE STREETS.

5. INSTALL ALL UTILITIES IN RIGHTS-OF-WAY.

6. RE-GRADE AND COMPACT SUBGRADE. MEET WITH CITY INSPECTOR AND/DESIGN ENGINEER TO DETERMINE AREAS OF DIFFERING STREET SECTION THICKNESS OR SUBGRADE PREPARATION IF CALLED FOR IN THE GEOTECHNICAL REPORT.

7. INSURE ALL UNDERGROUND UTILITY CROSSINGS ARE IN PLACE INCLUDING SLEEVES FOR DRY UTILITIES AND INSTALL

FIRST COURSE OF BASE.

8. INSTALL CURBS, RIP-RAP AND MISCELLANEOUS CONCRETE.

TYPICAL SEQUENCE OF CONSTRUCTION CONTINUED

OCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

INSTALL SECOND COURSE OF BASE.

LAY ASPHALT.

11. FINAL GRADE ANY DITCHES AND PARKWAYS.

12. REVEGETATE ALL DISTURBED AREAS. DISPOSE OF SPOIL IN AN APPROVED MANNER.

SCHEDULE A FINAL INSPECTION WITH CITY.

14. AFTER ACCEPTANCE OF CONSTRUCTION, TEMPORARY EROSION CONTROLS MAY BE REMOVED.

MINIMUM CRITERIA FOR ACCEPTANCE

ALL CONSTRUCTION IS COMPLETE INCLUDING DRY UTILITIES AND RESTORATION TO THE CRITERIA.

2. ALL CITY OF KYLE FEES PAID AND MAINTENANCE BOND POSTED.

3. ALL RECORDS OF CONSTRUCTION TESTING AND RECORD DRAWINGS SHOWING ANY CHANGES DURING CONSTRUCTION PROVIDED TO THE CITY OF KYLE.

4. ALL STREET LIGHTING, SIGNS AND PAVEMENT MARKINGS SHALL BE IN PLACE.

WATER AND WASTEWATER NOTES

1. PIPE MATERIAL FOR WATER MAINS SHALL BE PVC (AWWA C-900, DR-14) OR DUCTILE IRON (AWWA C-151, CLASS 350).

2. PIPE MATERIAL FOR GRAVITY SEWER SHALL BE SDR-26 PVC IF LOCATED GREATER THAN 9 FEET FROM A WATERLINE, OTHERWISE SHALL BE PRESSURE RATED PIPE.

3. BEDDING FOR FLEXIBLE GRAVITY PIPE (I.E. SDR-26 PVC) SHALL CONFORM TO ASTM 2321 CLASS 1 MATERIAL, I.E., 3/4" - 1" CLEAN ANGULAR CRUSHED ROCK.

4. CITY INSPECTOR SHALL OBSERVE ALL TAPS TO CITY UTILITY LINES AND PRIOR TO ANY UTILITY RELOCATION.

5. CONTRACTOR SHALL DISINFECT AND PRESSURE TEST ALL WATER LINES AND PERFORM LEAK AND DEFLECTION TESTS ON GRAVITY WASTEWATER LINES AT HIS EXPENSE.

6. THE CITY INSPECTOR SHALL BE NOTIFIED 36 HOURS PRIOR TO ALL UTILITY LINE TESTING. CONTRACTOR, WITH CITY STAFF PRESENT, IS RESPONSIBLE FOR SAMPLING. CITY STAFF WILL TRANSPORT BACTERIOLOGICAL TEST SAMPLES TO THE STATE DEPARTMENT OF HEALTH. ALL TEST RESULTS, WHETHER PASSING OR FAILING, SHALL BE PROVIDED TO THE CONTRACTOR. MANDREL DEFLECTION TESTING SHALL NOT BE CONDUCTED UNTIL THE PIPES HAVE BEEN BACKFILLED FOR 30 DAYS.

7. FIRE HYDRANTS SHALL BE MUELLER SUPER CENTURION OR APPROVED EQUAL,

8. THE CONTRACTOR SHALL SUBMIT TO THE DESIGN ENGINEER, DESCRIPTIVE INFORMATION FOR MATERIALS TO BE USED ON THE PROJECT FOR REVIEW. A COPY OF THE ACCEPTED MATERIAL SHALL ALSO BE PROVIDED TO THE CITY OF KYLE TEN DAYS PRIOR TO THE INSTALLATION OF UTILITIES.

PRESSURE TAPS SHALL BE IN ACCORDANCE WITH THE CITY OF KYLE. THE CONTRACTOR SHALL DO ALL EXCAVATION ETC., AND SHALL FURNISH, INSTALL AND AIR TEST THE SLEEVE AND VALVE. A CITY OF KYLE INSPECTOR MUST BE PRESENT WHEN TAP IS MADE. 7/32 SIZE ON SIZE 9/32 TAPS WILL NOT BE PERMITTED WITHOUT PRIOR APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. CONCRETE BLOCKING SHALL BE PLACED BEHIND AND UNDER ALL TAP SLEEVES

10. ONE CALL NOTE - CONTRACTOR MUST CALL CITY OF KYLE (512-262-3024) FOR LOCATION OF CITY UTILITIES.

11. 200 PSI, BLACK, POLYETHYLENE TUBING SHALL BE USED ON WATER SERVICES.

TWENTY-FOUR (24) HOURS PRIOR TO MAKING THE WET TAP.

12. ALL MANHOLES SHALL BE INTERNALLY COATED TO CITY OF AUSTIN SPECIFICATIONS, INCLUDING THE TIE-IN MANHOLE, UNLESS WAIVED BY THE DIRECTOR OF PUBLIC WORKS.

13. ALL PUBLIC MANHOLE COVERS WITHIN THE CITY LIMITS OF KYLE SHALL HAVE THE CITY OF KYLE LOGO.

14. ALL GATE VALVE OPERATING NUT OR VALVE EXTENTION NEEDS TO BE 24 9/32 TO FINAL GRADE.

FIRE PREVENTION NOTES

1. THE CONTRACTOR SHALL PROVIDE COMPACTED FLEXIBLE BASE PAVEMENT PRIOR TO CONSTRUCTION OF COMBUSTIBLE MATERIALS AS AN 7/32 ALL WEATHER DRIVING SURFACE. 9/32

HYDRANTS MUST BE INSTALLED WITH THE CENTER OF THE 4 59/64 INCH OPENING AT LEAST EIGHTEEN (18) INCHES ABOVE FINISHED GRADE. THE 4 59/64 INCH OPENING MUST FACE THE DRIVEWAY OR STREET WITH 3' - 6" SETBACK FROM CURBLINE(S). NO OBSERVATION IS ALLOWED WITHIN THREE (3) FEET OF ANY HYDRANT AND THE 4 69/64 INCH OPENING MUST BE TOTALLY UNOBSTRUCTED FROM THE STREET (USE NST THREADS).

DESIGNATE NO PARKING - FIRE LANE WITH CURB PAINTED RED AND WHITE STENCIL IN 7/32 FIRE ZONE / TOW AWAY ZONE 9/32 IN LETTERING 3 INCHES IN HEIGHT IN PROXIMITY TO COMMERCIAL, INDUSTRIAL AND PUBLIC STRUCTURES.

EROISON AND SEDIMENTATION CONTROL

1. AFTER THE PRECONSTRUCTION MEETING IS HELD, THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND FENCING FOR AREAS OUTSIDE OF THE CONSTRUCTION AREA PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING OR EXCAVATION).

2. THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AND FENCES AT WEEKLY INTERVALS, AND AFTER SIGNIFICANT RAINFALL EVENTS TO ENSURE THAT THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS AND FENCES SHALL IMMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILT ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6) INCHES.

PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED, ACCUMULATED SEDIMENT REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BE DISPOSED OF IN APPROVED SPOIL DISPOSAL SITES.

FIELD REVISIONS TO THE EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE CITY INSPECTOR DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL INADEQUACIES.

5. PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED BELOW:

A.A MINIMUM OF FOUR (4) INCHES OF TOPSOIL SHALL BE PLACED IN ALL DRAINAGE CHANNELS (EXCEPT ROCK), AND BETWEEN THE CURB AND RIGHT-OF-WAY.

B. TRASH, WOOD, BRUSH, STUMPS, ROCKS OVER 1 59/64 INCHES IN SIZE AND OTHER OBJECTIONABLE MATERIAL ENCOUNTERED SHALL BE REMOVED AND DISPOSED OF AS DIRECTED BY THE ENGINEER OR INSPECTOR PRIOR TO BEGINNING OF WORK REQUIRED BY THIS ITEM. GRASS AND OTHER HERBACEOUS PLANT MATERIALS MAY REMAIN. LARGE CLUMPS SHALL BE BROKEN UP.

C. THE SEEDING FOR PERMANENT EROSION CONTROL SHALL BE APPLIED OVER AREAS DISTURBED BY CONSTRUCTION AS FOLLOWS:

BROADCAST SEEDING

(I) FROM OCTOBER TO FEBRUARY, SEEDING SHALL BE WITH ONE (1) POUND PER 1,000 SQUARE FEET OF UNHULLED BERMUDA OR THREE (3) POUNDS PER 1,000 SQUARE FEET OF WINTER RYE.

(II) FROM MARCH TO SEPTEMBER, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF ONE (1) POUND

PER 1,000 SQUARE FEET.

FERTILIZER, IF USED, SHALL BE SLOW RELEASE GRANULAR OR PALETTE TYPE, AND SHALL HAVE AN ANALYSIS OF 15-15, AND SHALL BE APPLIED AT THE RATE OF ONE (1) POUND PER 1,000 SQUARE FEET, ONCE AT THE TIME OF PLANTING, AND AGAIN ONCE DURING THE TIME OF ESTABLISHMENT.

MULCH TYPE USED SHALL BE STRAW OR HAY APPLIED AT A RATE OF 45 POUNDS PER 1,000 SQUARE FEET.

HYDRAULIC SEEDING

(I) FROM OCTOBER TO FEBRUARY, SEEDING SHALL BE WITH ONE (1) POUND PER 1,000 SQUARE FEET OF UNHULLED BERMUDA, OR THREE (3) POUNDS PER 1,000 SQUARE FEET OF WINTER RYE.

(II) FROM MARCH TO SEPTEMBER, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF ONE (1) POUND PER 1,000

FERTILIZER, IF USED, SHALL BE A WATER SOLUBLE FERTILIZER WITH AN ANALYSIS OF 15-15-15 AT A RATE OF 1.5 POUNDS PER 1,000 SQUARE FEET.

MULCH TYPE SHALL BE HAY, STRAW OR MULCH APPLIED AT A RATE OF 45 POUNDS PER 1,000 SQUARE FEET, WITH A SOIL TACKIFIER AT A RATE OF 1.4 POUNDS PER 1,000 SQUARE FEET.

D. THE PLANTED AREA SHALL BE IRRIGATED OR SPRINKLED IN A MANNER THAT WILL NOT ERODE THE TOPSOIL, BUT WILL SUFFICIENTLY SOAK TO A DEPTH OF SIX (6) INCHES. THE IRRIGATION SHALL OCCUR AT 10-DAY INTERVALS DURING THE FIRST TWO (2) MONTHS. RAINFALL OCCURRENCES OF 59/64 INCH OR MORE SHALL POSTPONE THE WATERING SCHEDULE FOR TEN (10) DAYS.

E. RESTORATION SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1 INCH HIGH WITH 85% COVERAGE, PROVIDED NO BARE SPOTS LARGER THAN 20 SQUARE FEET EXIST.

F. A SOIL RETENTION BLANKET SHALL BE PLACED ON ALL SLOPES EQUAL TO OR GREATER THAN 3:1. ALL SOIL RETENTION BLANKETS MUST BE LISTED ON THE TXDOT APPROVED PRODUCTS LIST OR APPROVED BY THE CITY.

DEVELOPER INFORMATION:

OWNER: TOLL BROTHERS

ADDRESS: 1320 ARROW POINT DRIVE, SUITE 401, CEDAR PARK, TX. 78613

PHONE: (412) 780-2312

REPRESENTATIVE: ADRIENNE DONATUCCI

DESIGN ENGINEER: REPRESENTATIVE RESPONSIBLE FOR PLAN CHANGES.

NAME: MICHAEL FISHER, P.E.

ADDRESS: 10801 N. MOPAC EXPY., BUILDING. 3, SUITE 200, AUSTIN, TX 78759

PHONE: (512) 454-8711

DIRECTOR OF WATER UTILITIES: MIKE MURPHY (512) 262-3024

CITY ENGINEER: LEON BARBA, P.E. (512) 262-3958

CITY OF KYLE WATER RESTRICTIONS

1. CITY OF KYLE WATERING RESTRICTIONS MUST BE ADHERED TO. THIS MAY INCLUDE RESTRICTION ON CONSTRUCTION WATER FROM CITY OF KYLE POTABLE WATER SYSTEM.

X MICHAEL S. FISHE

87704

NIS. ARA

CITY JOB No. CP-22-0144

JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 2 OF 54

 ARA

0

 \circ

*

MICHAEL S. FISHE

87704

WAR 4/11/25

JALLAS 454.8711

0

DESIGNER AD/BA/JS CHECKED AC DRAWN AL SHEET 3 OF 54

CP-22-0144

IIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL

TCEQ-0596 (Rev. July 15, 2015)

All excavated material that will be stored on-site must have proper E&S controls.

9. If portions of the site will have a cease in construction activity lasting longer than 14 days, soil

collection system alignment around the feature. The regulated activities near the sensitive feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the sensitive feature and the Edwards Aquifer from any potentially

TCEQ-0591 (Rev. 2-26-2016)

(1) For a collection pipe with inside diameter less than 27 inches, deflection (i) A rigid mandrel must have an outside diameter (OD) not less than 95% of the base inside diameter (ID) or average ID of a

> American Water Works Association, UNI-BELL, or American (ii) If a mandrel sizing diameter is not specified in the appropriate standard, the mandrel must have an OD equal to 95% of the ID of a pipe. In this case, the ID of the pipe, for the purpose of determining the OD of the mandrel, must equal be the average outside diameter minus two minimum wall thicknesses for OD controlled pipe and the average inside diameter for ID

A rigid mandrel must be constructed of a metal or a rigid plastic material that can withstand 200 psi without being deformed. A mandrel must have nine or more odd number of runners or

A test may not use television inspection as a substitute for a (iii) If requested, the executive director may approve the use of a deflectometer or a mandrel with removable legs or runners on a

(2) For a gravity collection system pipe with an inside diameter 27 inches and greater, other test methods may be used to determine vertical deflection. (3) A deflection test method must be accurate to within plus or minus 0.2%

(4) An owner shall not conduct a deflection test until at least 30 days after the final

(5) Gravity collection system pipe deflection must not exceed five percent (5%). (6) If a pipe section fails a deflection test, an owner shall correct the problem and conduct a second test after the final backfill has been in place at least 30 days.

An owner shall test each manhole (after assembly and backfilling) for leakage, separate and independent of the collection system pipes, by hydrostatic exfiltration testing, vacuum testing, or other method approved by the executive director.

Page 5 of 6

A temporary valve for pressure testing may be installed near the discharge point of a

The leakage rate must not exceed 10.0 gallons per inch diameter per mile of pipe per

THESE LIFT STATION AND FORCE MAINS CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL

TCEQ-0591 (Rev. 2-26-2016)


TCEQ-0592A (Rev. July 15, 2015)


Page 2 of 2


Page 1 of 2


CITY JOB No. CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024


Page 2 of 2


















CP-22-0144


TREE NUMBER 2672	TREE TYPE CHINABERRY	CALIPER INCH 13.5	CIRCUMFERENCE INCH 42.4	EXEMPT	PROTECTED TREE	SPECIMEN TREE	REMOVED INCHES	PRESERVED INCHES 42.4	REASON FOR REMOVAL
2673	LIVE OAK	22	69.1		Х			69.1	
2674	LIVE OAK	26.5	83.3	-		X		83.3 86.4	
2675 2676	LIVE OAK	27.5	86.4 31.4		X	X		31.4	
2677	LIVE OAK	17.5	55.0		X			55.0	
2678	LIVE OAK	17	53.4		X			53.4	
2679 2680	HACKBERRY	8.5 8.5	26.7	X	-	+		26.7 26.7	
2681	LIVE OAK	30	94.2	^	<u> </u>	X		94.2	
2682	LIVE OAK	11	34.6		X			34.6	
2683	LIVE OAK	8.5	26.7					26.7	
2684 2685	HACKBERRY	13.5 8.5	42.4 26.7	X	-	 		42.4 26.7	
2686	HACKBERRY	11	34.6	X				34.6	
2687	CHINABERRY	9.5	29.8	Х				29.8	
2688	HACKBERRY	10	31.4	X			31.4	00.1	FM ALIGNMENT CONFLICT
2689 2690	LIVE OAK HACKBERRY	25.5 8.5	80.1 26.7	X	-	X	 	80.1 26.7	
2691	LIVE OAK	10	31.4		X			31.4	
2692	LIVE OAK	8.5	26.7					26.7	
2693	LIVE OAK	9	28.3		X		28.3		FM ALIGNMENT CONFLICT
2694 2695	HACKBERRY HACKBERRY	15 9	47.1 28.3	X	-		47.1 28.3		FM ALIGNMENT CONFLICT
2696	PECAN	11	34.6	^	Х		34.6		FM ALIGNMENT CONFLICT
2697	HACKBERRY	9.5	29.8	Х			29.8		FM ALIGNMENT CONFLICT
2698	HACKBERRY	20	62.8	X			62.8		FM ALIGNMENT CONFLICT
2699	HACKBERRY	10	31.4	X		-	31.4		FM ALIGNMENT CONFLICT
2700 2701	CEDAR ELM HACKBERRY	8	25.1 50.3	X		-	25.1	50.3	FM ALIGNMENT CONFLICT
2702	HACKBERRY	10.5	33.0	X				33.0	
2703	HACKBERRY	10	31.4	Х				31.4	
2704	HACKBERRY	9	28.3	X				28.3	
2705 2706	CEDAR ELM CEDAR ELM	12 12	37.7 37.7		X			37.7 37.7	
2707	CEDAR ELM	15.5	48.7	 	X	 		48.7	
2708	LIVE OAK	12	37.7		X			37.7	
2709	CEDAR ELM	21.5	67.5		X			67.5	
2710 2711	DEAD HACKBERRY	9.5 12.5	29.8 39.3	X	-		39.3	29.8	FM ALIGNMENT CONFLICT
2712	LIVE OAK	8.5	26.7	^		 	39.3	26.7	FIN ALIGNMENT CONFLICT
2713	LIVE OAK	17.5	55.0		Х			55.0	
2714	CEDAR ELM	17	53.4		Х			53.4	
2715	HACKBERRY	10 9.5	31.4	X	- V	-	31.4	20.9	FM ALIGNMENT CONFLICT
2716 2717	LIVE OAK	9.5	29.8 29.8		X	 		29.8 29.8	
2718	CEDAR ELM	17	53.4		Х			53.4	
2719	LIVE OAK	8	25.1					25.1	
2720 2721	LIVE OAK	9	44.0		X	1		44.0 28.3	
2722	LIVE OAK HACKBERRY	17.5	28.3 55.0	X	X	-		55.0	
2723	HACKBERRY	9.5	29.8	Х			29.8		FM ALIGNMENT CONFLICT
2724	HACKBERRY	18.5	58.1	X			58.1		FM ALIGNMENT CONFLICT
2725	DEAD	11	34.6	X			20.0	34.6	FM ALIGNMENT CONFLICT
2726 2727	HACKBERRY HACKBERRY	9.5	29.8	X	 		29.8		FM ALIGNMENT CONFLICT
2728	CEDAR ELM	9.5	29.8		Х		29.8		FM ALIGNMENT CONFLICT
2729	HACKBERRY	12.5	39.3	X			39.3		FM ALIGNMENT CONFLICT
2730	HACKBERRY	9.5	29.8	X			29.8	27.7	FM ALIGNMENT CONFLICT
2731	CEDAR ELM	12	37.7 31.4	X	X	 		37.7 31.4	
2733	LIVE OAK	38	119.4			X		119.4	
2734	LIVE OAK	26.5	83.3			Х		83.3	
2735	LIVE OAK	23	72.3		X		26.7	72.3	
2736 2737	HACKBERRY LIVE OAK	8.5 19	26.7 59.7	X	X	-	26.7 59.7		FM ALIGNMENT CONFLICT
2738	LIVE OAK	16.5	51.8		X		51.8		FM ALIGNMENT CONFLICT
2739	LIVE OAK	15.5	48.7		X		48.7		FM ALIGNMENT CONFLICT
2740	LIVE OAK	22	69.1		X		69.1		FM ALIGNMENT CONFLICT
2741 2742	CEDAR ELM	10.5	33.0 25.1		X	_	33.0 25.1		FM ALIGNMENT CONFLICT
2743	LIVE OAK	9.5	29.8		Х		29.8		FM ALIGNMENT CONFLICT
2744	LIVE OAK	10	31.4		X		31.4		FM ALIGNMENT CONFLIC
2745	LIVE OAK	13.5	42.4		X		42.4		FM ALIGNMENT CONFLICT FM ALIGNMENT CONFLICT
2746 2747	CEDAR ELM	25 10	78.5 31.4		X	X	78.5 31.4		FM ALIGNMENT CONFLIC
2748	CEDAR ELM	11	34.6		X		34.6		FM ALIGNMENT CONFLIC
2749	CEDAR ELM	17	53.4		Х			53.4	
2750	HACKBERRY	13.5 9.5	42.4	X		_		42.4 29.8	
2751 2752	HACKBERRY LIVE OAK	28.5	29.8 89.5	X	 	X		89.5	
2753	CEDAR ELM	12.5	39.3		Х			39.3	
2754	CEDAR ELM	9.5	29.8		Х			29.8	
2755	CEDAR ELM	10	31.4		X			31.4	
2756 2757	CEDAR ELM CEDAR	10.5 17	33.0 53.4	X	X			33.0 53.4	
2758	POST OAK	19	59.7		Х			59.7	
2759	CEDAR	10	31.4	Х				31.4	
2760	POST OAK	15.5	48.7		X	_		48.7	
2761 2762	CEDAR CEDAR	4.5 10	14.1 31.4	X			1	14.1 31.4	
2763	CEDAR	19	59.7	X				59.7	
2764	CEDAR	20	62.8	Х				62.8	
2765	CEDAR	18.5	58.1	X			-	58.1	
2766 2767	POST OAK	10 21.5	31.4 67.5		X	-		31.4 67.5	
2768	CEDAR	8	25.1	X	1			25.1	
2/00	and the second s								

TREE	TREE TYPE	CALIPER	CIRCUMFERENCE	EXEMPT	PROTECTED	3	2.50 m 100 m 100 m 100 m 100 m	PRESERVED	REASON FOR
NUMBER	055.15	INCH	INCH		TREE	TREE	INCHES	INCHES	REMOVAL
2770	CEDAR	19.5	61.3	X	-			61.3	
2771	COTTONWOOD	16	50.3		X			50.3	
2772	COTTONWOOD	21	66.0		X			66.0	
2773	POST OAK	15	47.1		X			47.1	
2774	POST OAK	11	34.6		X			34.6	
2775	POST OAK	11	34.6		X			34.6	
2776	POST OAK	12.5	39.3		X			39.3	
2777	CEDAR	8.5	26.7	X				26.7	
2778	CEDAR	11	34.6	X				34.6	
2779	LIVE OAK	8	25.1					25.1	
2780	LIVE OAK	11.5	36.1		X			36.1	
2781	LIVE OAK	13	40.8		X			40.8	
2782	LIVE OAK	11.5	36.1		X			36.1	
2783	LIVE OAK	11	34.6	,	X			34.6	
2784	LIVE OAK	13	40.8		X			40.8	
2785	LIVE OAK	10.5	33.0		X			33.0	
2786	CEDAR	9	28.3	X				28.3	
2787	LIVE OAK	8.5	26.7					26.7	
2788	COTTONWOOD	8	25.1					25.1	
2789	CEDAR	8.5	26.7	X				26.7	
2790	CEDAR	10.5	33.0	X				33.0	
2791	POST OAK	9	28.3		X			28.3	
2792	CEDAR	21	66.0	X				66.0	
2793	POST OAK	21.5	67.5		Х			67.5	
2794	CEDAR	12.5	39.3	Х				39.3	
2795	CEDAR	21.5	67.5	Х				67.5	
2796	POST OAK	12	37.7		Х			37.7	
2797	COTTONWOOD	24	75.4			Х		75.4	
2798	BLACKJACK	9	28.3		Х			28.3	
2799	BLACKJACK	14.5	45.6		X			45.6	
2800	CEDAR	8	25.1	Χ				25.1	
2801	POST OAK	19	59.7		X			59.7	
2802	POST OAK	11.5	36.1		X			36.1	
2803	POST OAK	11	34.6		X			34.6	
2804	LIVE OAK	19	59.7		X			59.7	
2805	LIVE OAK	15.5	48.7		X			48.7	
2806	LIVE OAK	11	34.6		X			34.6	
2807	LIVE OAK	13.5	42.4		X			42.4	**************************************
2808	CEDAR	21.5	67.5	Х				67.5	
2809	CEDAR	37	116.2	X		X		116.2	
2810	CEDAR	13.5	42.4	X				42.4	
2811	CEDAR	16	50.3	X				50.3	
2812	CEDAR	11.5	36.1	X				36.1	
2813	DEAD	13.5	42.4	X				42.4	
2814	CEDAR	23	72.3	X				72.3	
2815	MESQUITE	8	25.1	X	1			25.1	
2816	CEDAR	22	69.1	X	1			69.1	
2817	CEDAR	10.5	33.0	X	 			33.0	
2818	CEDAR	19	59.7	X	 			59.7	
2819	POST OAK	9	28.3	^	X			28.3	
2820	CEDAR	18	56.5	X	^			56.5	
2821	BLACKJACK	9.5	29.8	^					
2821	BLACKJACK	9.5	29.8		X			29.8	
			26.7		\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \			29.8	
2823	CEDAR	8.5 9		X	-			26.7	
2824			greater than 28" bu					28.3	

		PERCENTAGE OF TOTAL
TOTAL SPECIMEN TREE	78.5	9.94%
CIRCUMFERENCE INCHES REMOVED		
TOTAL SPECIMEN TREE CIRCUMFERENCE INCHES PRESERVED	711.6	90.06%
TOTAL SPECIMEN TREE CIRCUMFERENCE INCHES	790.1	100.00%
TOTAL NUMBER OF SPECIMEN TREES REMOVED	1.0	11.11%
TOTAL NUMBER OF SPECIMEN TREES PRESERVED	8.0	88.89%
TOTAL NUMBER OF SPECIMEN TREES	9.0	100.00%
TOTAL PROTECTED TREE CIRCUMFERENCE INCHES REMOVED	524.6	17.94%
TOTAL PROTECTED TREE CIRCUMFERENCE INCHES PRESERVED	2,400.2	82.06%
TOTAL PROTECTED TREE CIRCUMFERENCE INCHES	2,924.8	100.00%
TOTAL NUMBER OF PROTECTED TREES REMOVED	13.0	18.84%
TOTAL NUMBER OF PROTECTED TREES PRESERVED	56.0	81.16%
TOTAL NUMBER OF PROTECTED TREES	69.0	100.00%


	Surveyed P		Rer	Removed Mitigation				Credits					
	# of Trees	Total Inches	# of Trees	Total Inches	Percentage of Trees	Replacement Ratio	Required Replacement	Trees Preserved	Inches Preserved	Credit Ratio	Credit Inches	Credit 12" Trees	
SPECIMEN TREES	9	790.1	1	78.5	11%	1":1"	78.5	8	711.6	1":1"	711.6	N/A	
PROTECTED TREES	69	2,924.8	13	524.6	19%	2.5 Trees : 1 Tree*	0.0	56	2400.2	2 Trees : 1 Tree	N/A	84	
<28" Trees	9	232.5	2	50.3	22%	None	0.0	7	182.2	1.5 Trees : 1 Tree	N/A	14	





TREE PRESERVATION PLAN TREE LIST CLARA VISTA

CITY JOB No. CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 11 OF 54




25.86

Total

3.10

2.50

0.59



LEGEND ----

> OFFSITE 3A 3.92 AC WATERSHED ACREAGE

FLOW DIRECTION

PROPOSED WATERSHED

CALCULATED EXISTING 100-YR FLOODPLAIN CALCULATED PROPOSED 100-YR FLOODPLAIN

WATERWAY BUFFER ZONE

NOTES

526

526

NO ADDITIONAL IMPERVIOUS COVER IS PROPOSED TO BE ADDED IN DRAINAGE AREA UNCAPTURED 4.

CLARA

DRAINAGE


QUALITY

WATER


CITY JOB No. CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 12 OF 54

Treatment Summary Table
Current Application - Hawkes Landing North Phase 1 Required TSS Designed TS Total Net Total Existing Total Proposed Watershed Area BMP Impervious Cover Watershed Impervious Cover Removal Impervious Cover (lbs./yr.) (lbs./yr.) (acres) (acres) (acres) 0.26 ENGINEEREDVFS1 0.09 0.08 VFS 1 ENGINEERED VFS2 0.10 0.03 0.00 0.03 VFS 2 0.06 0.02 0.02 ENGINEEREDVFS3 14 14 0.00 VFS 3 1.27 0.33 0.33 292 310 0.00 ENGINEEREDVFS4 VFS 4 104 104 0.18 0.00 0.12 0.12 ENGINEERED VFS5 VFS 5
UNCAPTURED1 0.09 0.02 OVERTREATMENT BY ENGINEERED VFS4 0.00 0.02 0.36 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) UNCAPTURED2 0.00 0.00 UNCAPTURED3 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.00 UNCAPTURED4 11.25 2.50 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 2.50 OFFSITE1 0.45 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 0.00 0.00 0.00 0.64 OFFSITE 2 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) OFFSITE3 0.16 0.00 0.00 0.00 OFFSITE4 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED) 5.60 0.00 0.00 0.00 OFFSITE5 5.43 0.00 0.00 0.00 NO BMP REQUIRED (NO ADDITIONAL IMPERVIOUS COVER PROPOSED)

S DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



CITY OF AUSTIN



TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 300 mm (12 NCHES). IF WOOD POSTS CANNOT ACHIEVE 300 mm (12 Inches) DEPTH, USE STEEL POSTS.

2. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, 80 THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.

3. THE TRENCH MUST BE A MINIMUM OF 150 mm (8 Inches) DEEP AND 150 mm (8 Inches) WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED


4. SILT FENCE FABRIC SHOULD BE SECURELY FASTENED TO EACH STEEL OR WOOD SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL OR WOOD FENCE POST.


5. INSPECTION SHALL BE MADE WEEKLY OR AFTER EACH RAINFALL EVENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTY AS NEEDED.


6. SILT FENCE SHALL BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.


7. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF 150 mm (6 inches). THE SILT SHALL BE DISPOSED OF ON AN APPROVED SITE AND IN SUCH A MANNER THAT WILL NOT CONTRIBUTE TO ADDITIONAL SILTATION.

CITY OF AUSTIN SILT FENCE 642S-1










IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEA


STABILIZED CONSTRUCTION ENTRANCE


641S-1


THE ARCHITECT/ENGINEER ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE


THIS STANDARD.















AR.

CITY JOB No. CP-22-0144 51456-10 DATE SEPTEMBER 2024 DESIGNER AD/BA/JS CHECKED AC DRAWN AD SHEET 29 OF 54











ALL WEATHER PAVEMENT



THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL



MASONRY SCREEN WALL DETAILS

CONCRETE SURFACE -

6" CRUSHED LIMESTONE BASE-

CONCRETE SURFACE DETAIL

SCALE: N.T.S.

3" (MIN.)(TYP) -

-UNDISTURBED SUBGRADE

#4 BARS 0 18" ON CENTER EACH WAY

NOTES: 0 MATERIAL 1.1 ALL REINFORCING BARS SHALL CONFORM TO ASTM A615; FY = 40 KSI STRUCTURAL APPLICATIONS. 1.5 THREADED RODS SHALL BE ½" DIA; FY = 36 KSI 2.1 VERTICAL CONSTRUCITON JOINTS SHALL BE SPACED AT 45' O.C. MIN. 2.2 DESIGN WIND LOADS INCLUDE 90 MPH, EXPOSURE C SIDES OF THE WALL. SPECIFICATIONS SHALL BE THE RESPONSIBILITY OF THE OWNER OR OWNER'S REPRESENTATIVE. SECTION WITH FULL DEPTH MORTAR JOINTS

2'-0" (TYP.)-----

- 1.2 ALL CONCRETE SHALL BE 3000 PSI COMPRESSIVE STRENGTH AT 28 DAYS
- 1.3 SANDSTONE UNITS SHALL BE HARD, DURABLE STONE UNITS SUITABLE FOR
- 1.4 ALL MASONRY MORTAR SHALL BE TYPE 'S'; 750 PSI AT 28 DAYS
- 1.6 ALL THREADED RODS SHALL BE TENSIONED TO 60 FT. LB\$. OF TORQUE
- 2.3 FOUNDATION SOIL IS ASSUMED TO BE STIFF CLAY AS DESCRIBED IN THE PROJECT SOIL REPORT PREPARED BY INTEC AND DATED OCTOBER 2,
- 2.4 SCREEN WALL SHOWN IS NOT DESIGNED TO ACCOMMODATE RETAING OF SOIL ON EITHER SIDE. FINSHED GRADE SHALL BE THE SAME ON BOTH
- 2.5 TESTING METHODS, FREQUENCY AND VERIFICATION OF MATERIAL
- 2.6 WALL CAP UNITS SHALL BE PERMANENTLY SECURED TO THE WALL
- 2.7 A COMPLETE SET OF CONSTRUCTION DRAWINGS, CONTRACT SPECIFICATIONS AND MANUFACTURER'S INSTALLATION INSTRUCTIONS SHALL BE ONSITE AT ALL TIMES DURING THE CONSTRUCTION OF THE
- 2.8 THE ENGINEERING, DESIGN, ANALYSIS DETAILING, AND MITIGATION OF BOTH SURFACE DRAINAGE AND SEEPAGE OF GROUND WATER SHALL BE THE RESPONSIBILITY OF THE OWNER OR OWNER'S REPRESENTATIVE.
- 2.9 STRUCTURAL DESIGN HEREIN REPRESENTS A FINISHED STRUCTURE. THE CONTRACTOR SHALL PROVIDE ALL INTERIM BRACING, SHORING, INTERIM DRAINAGE PROVISIONS AND EROSION PROTECTION REQUIRED UNTIL FINAL CAPPING, PAVING, CURBING AND COMPLETION OF FINAL STORM DRAIN SYSTEM IS COMPLETE.



09-23-2024

*

HARRY B. WALKER

82788

ARA

JOB NO. 51456-10 MAY 2024 DESIGNER HBW CHECKED HBW DRAWN LDH

 MAXIMUM WIDTH BETWEEN LONGITUDINAL JOINTS SHALL NOT EXCEED 15'-0".
 ALL JOINTS TO BE SEALED TO BE THOROUGHLY CLEANED BY HYDROBLASTING AND/OR SAND BLASTING METHODS, THE JOINTS ARE TO BE FREE FROM ALL DUST COATINGS, ANY CONTAMINATES, AND FREE FROM ALL MOISTURE THAT MIGHT INTERFERE WITH THE PROPER AND SATISFACTORY BONDING OF THE JOINT SEALANT MATERIAL. THE JOINT WILL BE BLOWN OUT WITH DRY COMPRESSED AIR IMMEDIATELY PRIOR TO APPLYING SEALANT. CONSTRUCTION EQUIPMENT AND OTHER VEHICLES AND PEDESTRIANS WHICH MAY CAUSE DAMAGE TO THE JOINTS SHALL NOT BE ALLOWED ON THE PAVEMENT & SIDEWALKS BEFORE THE JOINT SEALANT BECOMES TACK FREE. 4. USE 3/4" x 4" EXPANSION JOINT MATERIAL AROUND POLES OR OTHER OBSTRUCTIONS. 5. SAW CUT JOINTS WITHIN 24 HOURS.

CP-22-0144

	ONE-LINE DIAG	RAM LEGEN	ND
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
°) 100AF 2P 50AT	MOLDED CASE CIRCUIT BREAKER	B-7-5	OILER HEATER WITH THERMOSTAT
十	STARTER (SIZE NOTED)	MTS)	MOTOR WINDING THERMOSTAT
HP	THREE-PHASE MOTOR (HORSEPOWER NOTED)	[=]	POWER FACTOR CORRECTION CAPACITOR
\$	ELECTRICAL GROUND	М	POWER QUALITY MONITOR
PFR	PHASE FAILURE RELAY	N/G	NEUTRAL/GROUND BOND
PS	PRESSURE SWITCH	ETM	ELAPSED TIME METER
(OS)	OILER SOLENOID	Ø	INDICATING LIGHT (COLOR AS SHOWN: G=GREEN, R=RED, A=AMBER, B=BLUE, W=WHITE
	TEMPERATURE INDICATING TRANSMITTER		HAND-OFF-AUTO SWITCH
L	LOCAL LOCK STOP	LAI	
T	TEMPERATURE SWITCH		OFF-AUTO SWITCH
V S	VIBRATION SWITCH		
	FLOW METER	TD	TIME DELAY RELAY
SPD	SURGE PROTECTIVE DEVICE		
5	MOTOR SPACE HEATER	A	SWING-OUT PANEL
A	SPECIAL DEVICE (SEE SCHEDULE THIS SHEET)		
SSOL	SOLID STATE OVERLOAD		

CONTR	OL DIAGRAM LEGEND
SYMBOL	DESCRIPTION
°)100AF 2P 50AT	MOLDED CASE CIRCUIT BREAKER
مأه	SELECTOR SWITCH
مله	PUSH BUTTON
CR/TD	CONTROL/ TIME-DELAY RELAY - PLUG
CR CR	RELAY CONTACT (NORMALLY OPEN - NORMALLY CLOSED)
o To	TIME-DELAY RELAY CONTACT
M	MOTOR STARTER COIL
OL X	MOTOR OVERLOAD
ETM	ELAPSED TIME METER
-©	INDICATING LIGHT - LED TYPE - PUSH-TO-TEST (COLOR AS SHOWN: G=GREEN, R=RED, A=AMBER, B=BLUE, W=WHITE
٥٠٠٠٠٥	MOTOR SPACE HEATER
IS	TEMPERATURE SWITCH
e FS	FLOAT SWITCH
A	SPECIAL DEVICE (SEE SCHEDULE THIS SHEET)
A	ITEM LOCATED ON CONTROL PANEL SWING-OUT PANEL

M - MOTOR

ABBREVIATIONS

#PDT - # POLE, DOUBLE THROW; WHERE # IS # OF POLES (S=SINGLE, D=DOUBLE) A - AMPS OR AMPERES ASP - AUTOSENSORY PANEL BC - BARE COPPER C - CONDUIT CC - COPPER CLAD CGB - CABLE GLAND BUSHING

CLR - CLEARANCE CR - CONTROL RELAY DTL - DETAIL ETM - ELAPSED TIME METER

EW - EACH WAY FG - FINISHED GRADE FIN - FINISHED (AS IN FINISHED GRADE)

G; GND - GROUND GSE - GROUNDING ELECTRODE SYSTEM HDG - HOT DIPPED GALVANIZED HTR - HEATER

MIN - MINIMUM MLO - MAIN LUGS ONLY MSH - MOTOR SPACE HEATER NEMA - NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION

N; NEU - NEUTRAL NG - NEUTRAL/GROUND BOND NTS - NOT TO SCALE

OC - OFF CENTER OL - OVERLOAD P - POLES

PFCC - POWER FACTOR CORRECTION CAPACITOR PROP - PROPOSED

PVC - POLYVINYL CHLORIDE RGS - RIGID GALVANIZED STEEL SCH - SCHEDULE SHT - SHEET

SPD - SURGE PROTECTIVE DEVICE S.S.; STN STL - STAINLESS STEEL TD - TIME DELAY RELAY

TYP - TYPICAL V — VOLT/VOLTAGE W/ - WITH

WIU - WHILE IN USE WP - WEATHERPROOF OR WEATHER PROTECTED

GFCI - GROUND FAULT CIRCUIT INTERRUPTER

GENERAL NOTES:


- 1. ALL CONSTRUCTION SHALL COMPLY WITH LOCAL AND NATIONAL CODES AND REQUIREMENTS.
- 2. CONDUITS SHALL NOT BE ROUTED ACROSS WALKWAYS, PATHS OF ACCESS, TRAVEL, OR EGRESS. ROUTE BENEATH GRATINGS, IN CONCRETE STRUCTURES, OR AROUND EQUIPMENT. DO NOT ROUTE IN CONFLICT WITH OTHER PIPING, CONDUITS, EQUIPMENT, OR STRUCTURES.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS ASSOCIATED WITH THE WORK. THE COSTS OR THE PERMITS, IF ANY, SHALL BE BORNE BY THE CONTRACTOR.
- 4. ALL POWER AND INSTRUMENTATION CONDUCTORS SHALL BE INSTALLED IN SEPARATE CONDUITS.
- 5. ALL EXTERIOR ABOVE GRADE CONDUIT SHALL BE PVC-COATED RIGID GALVANIZED STEEL CONDUIT. ALL MOUNTING HARDWARE SHALL BE STAINLESS STEEL.


* GREGORY S. BAIRD 100260 CENSED CHES 9/30/24


BAIRD GILROY & DIXON


PLAT NO. ____CP-22-0144 JOB NO. 51456-10 DATE SEPTEMBER 2024 DESIGNER CHECKED GSB DRAWN LAF


					PK	UP	PA	NEL	LV					
AMP	S: 40A PRIMARY MCB/80A SECONDARY MCB					-	HASE:	1				MOUNTING: SURFACE		
VOLTAG	E: 240/120A	WIRE: 3									MINIMUM AIC RATING: 10KAIC			
OCATIO	N: LIFT STATION											BUSSING: COPPER		
ED FROM	M: 15KVA XFMR				-							NEMA: 4XSS 316 STAINLE	SS STEEL	
CKT	SERVICE DESCRIPTION	WIRE	BRKR	POLES	KVA	Α	В	KVA	POLES	BRKR	WIRE	SERVICE DESCRIPTION	CK	
1	LIGHTS	12	20	1	0.5	0.7		0.2	1	20	12	POLE LIGHT	2	
3	BLOCK HEATER	12	20	1	1.5		2.0	0.5	1	20	12	RTU	4	
5	RECEPTACLE	12	20	1	0.5	1.0		0.5	1	20	12	AUTODIALER	6	
7	BATTERY CHARGER	12	20	1	1.0		0.0	0.5	2	30	10	SPD	8	
9	JIB CRANE	10	30	2	1.0	1.0		0.0				SPD	10	
11	JIB CRANE				1.0		1.0	0.0	1	20	12	POWER QUALITY METER	12	
13	TEMP PUMP	12	20	1	1.0	1.5		0.5	2	20	12	ODOR CONTROL	14	
15	SPARE		20	1	0.0	-CERT	2.0	0.5				ODOR CONTROL	16	
17	SPARE		20	1	0.0	0.0	311	0.5	1	20		SPARE	18	
19	SPARE		20	1	0.0		3.0	0.0	1	20		SPARE	20	
21	SPARE		20	1	0.0	0.0		0.0	1	20		SPARE	22	
23	SPARE		20	1	0.0		4.0	0.0	1	20		SPARE	24	
			PH	ASE LOAI	D IN KVA:	4.2	12.0							
			PHA	SE LOAD	IN AMPS:	35	100							














LIFT STATION SCADA RTU ENCLOSURE NOT TO SCALE

FRONT VIEW (DOOR REMOVED)

NOT TO SCALE

FRONT VIEW (EXTERIOR)

NOT TO SCALE

	LIFT STA	OITA	N I/O LIST	
ITEM	DESCRIPTION	TYP.	CABLE/CONDUIT	REMARKS
1	P1 RUN STATUS	DI	1/2" C, W/2-#16	PHYSICAL I/
2	P2 RUN STATUS	DI	1/2" C, W/2-#16	PHYSICAL I/
3	P1 H-O-A STATUS	DI	1/2" C, W/2-#16	PHYSICAL I/
4	P2 H-O-A STATUS	DI	1/2" C, W/2-#16	PHYSICAL I/
5	HIGH WET WELL LEVEL	DI	1/2" C, W/2-#16	PHYSICAL I/
6	LOW WET WELL LEVEL	DI	1/2" C, W/2-#16	PHYSICAL I/
7	MAIN POWER FAULT	DI	1/2" C, W/2-#16	PHYSICAL I/
8	CONTROL POWER FAULT	DI	1/2" C, W/2-#16	PHYSICAL I/
9	GEN RUN	DI	1/2" C, W/2-#16	PHYSICAL I/
10	GENERATOR FAULT	DI	1/2" C, W/2-#16	PHYSICAL I/
11	PUMP ROTATION BINARY	DI	1/2" C, W/2-#16	PHYSICAL I/
12	PUMP ROTATION BINARY	DI	1/2" C, W/2-#16	PHYSICAL I/
13	AC POWER	DI	1/2" C, W/2-#16	RADIO I/O
14	PUMP 1 CALL	DO	1/2" C, W/2-#16	PHYSICAL I/
15	PUMP 2 CALL	DO	1/2" C, W/2-#16	PHYSICAL I/
16	PLC FAULT	DO	1/2" C, W/2-#16	PHYSICAL I/
17	P1 STARTER FAULT	DO	1/2" C, W/2-#16	PHYSICAL I/
18	P2 STARTER FAULT	DO	1/2" C, W/2-#16	PHYSICAL I/
19	PUMP 1 OVERRIDE	DO	1/2" C, W/2-#16	PHYSICAL I/
20	PUMP 2 OVERRIDE	DO	1/2" C, W/2-#16	PHYSICAL I/
21	PUMP 1 OFF	DO	1/2" C, W/2-#16	PHYSICAL I/
22	PUMP 2 OFF	DO	1/2" C, W/2-#16	PHYSICAL I/
23	ANY PUMP OUT	DO	1/2" C, W/2-#16	PHYSICAL I/
24	ANY ALARM	DO	1/2" C, W/2-#16	PHYSICAL I/
25	BATTERY TEST	DO	1/2" C, W/2-#16	RADIO I/O
26	PUMP 1 VFD SPEED	AO	1/2" C, W/2-#18 STP	PHYSICAL I/
27	PUMP 2 VFD SPEED	AO	1/2" C, W/2-#18 STP	PHYSICAL I/
28	WET WELL LEVEL	Al	1/2" C, W/2-#18 STP	PHYSICAL I/
29	P1 CURRENT	Al	1/2" C, W/2-#18 STP	PHYSICAL I/
30	P1 CURRENT	Al	1/2" C, W/2-#18 STP	PHYSICAL I/
31	FLOW METER STATUS	Al	1/2" C, W/2-#18 STP	PHYSICAL I/
32	RADIO KEY CURRENT	Al	1/2" C, W/2-#18 STP	RADIO I/O
33	RADIO SIGNAL STRENGTH	Al	1/2" C, W/2-#18 STP	RADIO I/O

NOTES:


- RTU PANEL SCHEMATIC AND WIRING DIAGRAM IS TYPICAL IN NATURE. FINAL HARDWARE CONFIGURATION MAY VARY.
- 2. PROVIDE FACTORY AUTHORIZED STARTUP AND MINIMUM 4 HOURS TRAINING FOR OPERATOR PERSONNEL.
- 3. THE LIFT STATION SCADA SYSTEM SHALL OPERATE PER THE SEQUENCE OF OPERATIONS.
- 4. ALL CONDUITS AND WIRING PROVIDED, INSTALLED BY THE ELECTRICAL CONTRACTOR AND TERMINATED BY THE SCADA CONTRACTOR.
- 5. ELECTRICAL CONTRACTOR MAY GROUP WIRES WITH SAME VOLTAGE FOR FIELD DEVICES IN CONDUIT AS HE DEEMS BEST APPROPRIATE.
- 6. ANALOG AND LOW VOLTAGE SIGNALS SHALL NOT BE RUN IN SAME CONDUIT AS 120VAC AND 480VAC CIRCUITS.
- QUANTITY OF CONDUCTORS SHOWN ARE FOR REFERENCE ONLY. VERIFY EXACT WIRING REQUIREMENTS TO FIELD DEVICES ER INFORMATION PROVIDED BY THE EQUIPMENT VENDOR PRIOR TO INSTALLATION.
- 8. USE SHIELDED TWISTED PAIR (STP) CABLE BELDEN #5341FE OR EQUAL.
- 9. WET WELL LEVEL TRANSDUCER SCALING SHALL BE COORDINATED WITH CIVIL ENGINEER.

BAIRD Ste. 125 #326

GILROY
(281) 529-5005

WWW.bgdeng.com
TBFE No. F-16575
Job No. 128-0051

DATE



N, TX 77042 I 713.428.2400

10350 RICHMOND AVE, STE 200 I HOUSTON, TX 77042 I 7

CLARA VISTA
LIFT STATION & FORCE MAIN
LIFT STATION ELECTRICAL


PLAT NO. ____CP-22-0144

JOB NO. ____51456-10

DATE ____SEPTEMBER 2024

DESIGNER _____LAF

CHECKED _GSB _DRAWN _LAF



Project Name: Clara Vista Lift Station & Force Main

Date Prepared: 1/8/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

lhs

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where:

L_{M.TOTAL PROJECT} = Required TSS removal resulting from the proposed development = 80% of increased load A_N = Net increase in impervious area for the project P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

Couny Total project area included in Jan ' Predevelopment impervious area within the limits of the plan ' Total post-development impervious area within the limits of the plan' Total post-development Impervious cover fraction ' inches

526

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = Total drainage basin/outfall area = acres Predevelopment impervious area within drainage basin/outfall area =
Post-development impervious area within drainage basin/outfall area =
Post-development impervious fraction within drainage basin/outfall area = 0.01 acres

LM THIS BASN =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Strips **Batch Detention** Removal efficiency =

lbs.

71

Aqualogic Cartridge Filter Bloretention Contech StormFilter Constructed Wetland Extended Detention Grassy Swale
Retention / Irrigation
Sand Filter Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault

4. Calculate Maximum TSS Load Removed (LR) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A₁ x 34.6 + A_P x 0.54)

A_C = Total On-Site drainage area in the BMP catchment area A_I = Impervious area proposed in the BMP catchment area A_P = Pervious area remaining in the BMP catchment area L_R = TSS Load removed from this catchment area by the proposed BMP

A_i = 0.09 acres Ap = 0.18 acres

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired LMTHIS BASIN = 71 lbs.

0.83

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 1.20 inches Post Development Runoff Coefficient = On-site Water Quality Volume = 0.27 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =
Off-site Impervious cover draining to BMP =
Impervious fraction of off-site area = 0.00 Off-site Runoff Coefficient = 0.02 Off-site Water Quality Volume = 39 cubic feet

> Storage for Sediment = 70

Total Capture Volume (required water quality volume(s) x 1.20) = 417
The following sections are used to calculate the required water quality volume(s) for the The values for BMP Types not selected in cell C45 will show NA. cubic feet selected BMP

Project Name: Clara Vista Lift Station & Force Main

Date Prepared: 1/8/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: L_M = 27.2(A_N x P)

where:

L_{M.TOTAL PROJECT} = Required TSS removal resulting from the proposed development = 80% of increased load A_N = Net increase in impervious area for the project P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County –
Total project area included in plan * =
Predevelopment impervious area within the limits of the plan * =
Total post-development impervious area within the limits of the plan * =
Total post-development impervious cover fraction * = inches

> 526 lhs

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = Total drainage basin/outfall area = acres acres

Predevelopment impervious area within drainage basin/outfall area =
Post-development impervious area within drainage basin/outfall area =
Post-development impervious fraction within drainage basin/outfall area = lbs. LM THIS BASIN =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Strips moval efficiency = 85 percent **Batch Detention** Removal efficiency =

Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A_I x 34.6 + A_P x 0.54)

A_C = Total On-Site drainage area in the BMP catchment area A_I = Impervious area proposed in the BMP catchment area A_P = Pervious area remaining in the BMP catchment area L_R = TSS Load removed from this catchment area by the proposed BMP

A₁= 0.03 acres 0.07 acres 30 Ibs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired LM THIS BASIN = 27 lbs.

0.91

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 1.80 inches Post Development Runoff Coefficient =
On-site Water Quality Volume = cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =
Off-site Impervious cover draining to BMP =
Impervious fraction of off-site area =
Off-site Runoff Coefficient = 0.02 Off-site Water Quality Volume = cubic feet 59

Storage for Sediment =

cubic feet

Total Capture Volume (required water quality volume(s) x 1.20) = 268
The following sections are used to calculate the required water quality volume(s) for the The values for BMP Types not selected in cell C45 will show NA.

Project Name: Clara Vista Lift Station & Force Main

Date Prepared: 1/8/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where

 $L_{M.TOTAL.PROJECT}$ = Required TSS removal resulting from the proposed development = 80% of increased load A_V = Net increase in impervious area for the project P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County
Total project area included in plan
Predevelopment impervious area within the limits of the plan
Total post-development impervious area within the limits of the plan
Total post-development impervious cover fraction inches

> L_{M TOTAL PROJECT} = 526 lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =

Total drainage basin/outfall area = acres Predevelopment impervious area within drainage basin/outfall area =
Post-development impervious area within drainage basin/outfall area =
Post-development impervious area within drainage basin/outfall area = acres LM THIS BASIN =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Strips emoval efficiency = 85 percent **Batch Detention** Removal efficiency =

Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A₁ x 34.6 + A_P x 0.54)

A_C = Total On-Site drainage area in the BMP catchment area A = Impervious area proposed in the BMP catchment area Ap = Pervious area remaining in the BMP catchment area L_R = TSS Load removed from this catchment area by the proposed BMP

A_i= 0.02 acres acres 15 Ibs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired LMTHIS BASIN = 14 lbs.

0.91

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = inches Post Development Runoff Coefficient =
On-site Water Quality Volume = 91 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =
Off-site Impervious cover draining to BMP =
Impervious fraction of off-site area =
Off-site Runoff Coefficient = Off-site Water Quality Volume = cubic feet 59

Storage for Sediment =

cubic feet

Total Capture Volume (required water quality volume(s) x 1.20) = 179
The following sections are used to calculate the required water quality volume(s) for the The values for BMP Types not selected in cell C45 will show NA.

Project Name: Clara Vista Lift Station & Force Main

Date Prepared: 1/8/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: L_M = 27.2(A_N x P)

where:

LM TOTAL PROJECT = Required TSS removal resulting from the proposed development = 80% of increased load A_N = Net increase in impervious area for the project P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

Total project area included in plan acres Predevelopment impervious area within the limits of the plan * =
Total post-development impervious area within the limits of the plan * =
Total post-development impervious cover fraction * = acres acres

> LM TOTAL PROJECT = 526 lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =

Total drainage basin/outfall area = acres Predevelopment impervious area within drainage basin/outfall area = acres Post-development impervious area within drainage basin/outfall area = Post-development impervious fraction within drainage basin/outfall area = 0.33 acres LM THIS BASIN =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Stri Removal efficiency = 85 perce **Batch Detention** percent

Aqualogic Cartridge Filter Bioretention
Contech StormFilter
Constructed Wetland
Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips Vortechs Wet Basin

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A₁ x 34.6 + A_P x 0.54)

where

A_C = Total On-Site drainage area in the BMP catchment area A_i = Impervious area proposed in the BMP catchment area A_P = Pervious area remaining in the BMP catchment area L_R = TSS Load removed from this catchment area by the proposed BMP

1.27 acres A_i = 0.33 acres

0.95 acres Lp = 330 lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L_{M THIS BASIN} = 310 lbs.

0.94

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = inches Post Development Runoff Coefficient = 0.23 On-site Water Quality Volume = 2600 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =
Off-site Impervious cover draining to BMP =
Impervious fraction of off-site area =
Off-site Runoff Coefficient =
Off-site Water Quality Volume = acres 0.00 cubic feet 78

Storage for Sediment =

3214 cubic feet

Total Capture Volume (required water quality volume(s) x 1.20) = The following sections are used to calculate the required water quality volum The values for BMP Types not selected in cell C45 will show NA.

Project Name: Clara Vista Lift Station & Force Main

Date Prepared: 1/8/2025

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

Calculations from RG-348

1. The Required Load Reduction for the total project:

Page 3-29 Equation 3.3: L_M = 27.2(A_N x P)

Pages 3-27 to 3-30

where:

 $L_{M.TOTAL\ PROJECT}$ = Required TSS removal resulting from the proposed development = 80% of increased load A_N = Net increase in impervious area for the project

Batch Detention

P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

Total project area included in plan Predevelopment impervious area within the limits of the plan * =
Total post-development impervious area within the limits of the plan * =
Total post-development impervious cover fraction * = acres acres inches

> L_{M TOTAL PROJECT} = 526 lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area =

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =

Total drainage basin/outfall area = acres Predevelopment impervious area within drainage basin/outfall area = Post-development impervious area within drainage basin/outfall area = Post-development impervious fraction within drainage basin/outfall area = 0.00 acres 0.12 acres LM THIS BASIN =

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Strips Removal efficiency = 85 percent

Aqualogic Cartridge Filter Bioretention Contech StormFilter Constructed Wetland Extended Detention Extended Detention Grassy Swale Retention / Irrigation Sand Filter Stormceptor Vegetated Filter Strips

Vortechs Wet Rasin

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: L_R = (BMP efficiency) x P x (A_I x 34.6 + A_P x 0.54)

where:

A_C = Total On-Site drainage area in the BMP catchment area A = Impervious area proposed in the BMP catchment area A_P = Pervious area remaining in the BMP catchment area

L_R = TSS Load removed from this catchment area by the proposed BMP

acres A = 0.12 acres 0.07 acres 114 lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired LMTHIS BASN = 104 lbs.

0.92

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = 2.00 inches Post Development Runoff Coefficient = On-site Water Quality Volume = cubic feet 593

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =
Off-site Impervious cover draining to BMP =
Impervious fraction of off-site area =
Off-site Runoff Coefficient = 0.02 Off-site Water Quality Volume = cubic feet 65

> Storage for Sediment = 132

790 cubic feet

Total Capture Volume (required water quality volume(s) x 1.20) =
The following sections are used to calculate the required water quality volun
The values for BMP Types not selected in cell C45 will show NA.

ATTACHMENT G

CLARA VISTA LIFT STATION & FORCE MAIN Aboveground Storage Tank Application

MAINTENANCE PROCEDURES FOR PERMANENT BMPs

Note: Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 3.5.

A written record will be kept of inspection results and maintenance performed.

3.5.8 Vegetative Filter Strips

Once a vegetated area is well established, little additional maintenance is generally necessary. The key to establishing a viable vegetated feature is the care and maintenance it receives in the first few months after it is planted. Once established, all vegetated BMPs require some basic maintenance to insure the health of the plants including:

- Pest Management. An Integrated Pest Management (IPM) Plan should be developed for vegetated areas. This plan should specify how problem insects and weeds will be controlled with minimal or no use of insecticides and herbicides.
- Seasonal Mowing and Lawn Care. If the filter strip is made up of turf grass, it should be mowed as needed to limit vegetation height to 18 inches, using a mulching mower (or removal of clippings). If native grasses are used, the filter may require less frequent mowing, but a minimum of twice annually. Grass clippings and brush debris should not be deposited on vegetated filter strip areas. Regular mowing should also include weed control practices, however herbicide use should be kept to a minimum (Urbonas et al., 1992). Healthy grass can be maintained without using fertilizers because runoff usually contains sufficient nutrients. Irrigation of the site can help assure a dense and healthy vegetative cover.
- Inspection. Inspect filter strips at least twice annually for erosion or damage to vegetation; however, additional inspection after periods of heavy runoff is most desirable. The strip should be checked for uniformity of grass cover, debris and litter, and areas of sediment accumulation. More frequent inspections of the grass cover during the first few years after establishment will help to determine if any problems are developing, and to plan for long-term restorative maintenance needs. Bare spots and areas of erosion identified during semi-annual inspections must be replanted and restored to meet specifications. Construction of a level spreader device may be necessary to reestablish shallow overland flow.
- Debris and Litter Removal. Trash tends to accumulate in vegetated areas, particularly along highways. Any filter strip structures (i.e. level spreaders) should be kept free of obstructions to reduce floatables being flushed downstream, and for aesthetic reasons.

CLARA VISTA LIFT STATION & FORCE MAIN Aboveground Storage Tank Application

The need for this practice is determined through periodic inspection, but should be performed no less than 4 times per year.

- Sediment Removal. Sediment removal is not normally required in filter strips, since the vegetation normally grows through it and binds it to the soil. However, sediment may accumulate along the upstream boundary of the strip preventing uniform overland flow. Excess sediment should be removed by hand or with flat-bottomed shovels. Inspections should be performed at least twice a year and after each rainfall event, with at least one biannual inspection to occur during or immediately after a rainfall event.
- Grass Reseeding and Mulching. A healthy dense grass should be maintained on the filter strip. If areas are eroded, they should be filled, compacted, and reseeded so that the final grade is level. Grass damaged during the sediment removal process should be promptly replaced using the same seed mix used during filter strip establishment. If possible, flow should be diverted from the damaged areas until the grass is firmly established. Bare spots and areas of erosion identified during semi-annual inspections must be replanted and restored to meet specifications. Corrective maintenance, such as weeding or replanting should be done more frequently in the first two to three years after installation to ensure stabilization. Dense vegetation may require irrigation immediately after planting, and during particularly dry periods, particularly as the vegetation is initially established. Inspections should be performed twice a year and after each rainfall event, with at least one biannual inspection to occur during or immediately after a rainfall event.

CLARA VISTA LIFT STATION & FORCE MAIN Aboveground Storage Tank Application

Other recommended maintenance guidelines include:

- Inspections. BPM facilities should be inspected at least twice a year (once during or immediately following wet weather) to evaluate facility operation. During each inspection, erosion areas inside and downstream of the BPM must be identified and repaired or revegetated immediately.
- Sediment Removal. Remove sediment from the facility when sediment depth reaches 3 inches or when the sediment interferes with the health of vegetation or ability of the facility to meet required drawdown times. Sediment removal should be performed at least every 2 years.
- *Drain Time*. When the drain time exceeds 72 hours as observed in the observation well, the filter media should be removed and replaced with more permeable material.
- Vegetation. All dead and diseased vegetation considered beyond treatment shall be removed and replaced during semi-annual inspections. Diseased trees and shrubs should be treated during inspections. Remulch any bare areas by hand whenever needed. Replace mulch annually in the spring, or more frequently if needed, in landscaped areas of the basin where grass or groundcover is not planted. Grass areas in and around bioretention facilities must be mowed at least twice annually to limit vegetation height to 18 inches. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas.
- *Debris and Litter Removal*. Debris and litter will accumulate in the facility and should be removed during regular mowing operations and inspections.
- *Filter Undrain*. Clean underdrain piping network to remove any sediment buildup every 5 years, or as needed to maintain design drawdown time.

Signature

Kyle Ninness, Director of Land Development

Toll Southwest, LLC.

Date

8/20/25

ATTACHMENT I

CLARA VISTA LIFT STATION & FORCE MAIN Aboveground Storage Tank Application

<u>Attachment I – Measures for Minimizing Surface Stream Contamination</u>

Any points where discharge from the site is concentrated and erosive velocities exist will include appropriately sized energy dissipators to reduce velocities to non-erosive levels.

OWNER AUTHORIZATION FORM

Owner Authorization Form

Texas Commission on Environmental Quality for Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Land Owner Authorization

l, Gregg 1. Reyes	of	Bianco River Ranch Properties, LP
Land Owner Signatory Name	_	Land Owner Name (Legal Entity or Individual)
am the owner of the property locate WATERRIDGE 150 DISTRICT SE		7
Legal description	of the property re	eferenced in the application
§213.23(d) relating to the right to su signatory.	bmit an application	2) and §213.4(d)(1) or §213.23(c)(2) and on, signatory authority, and proof of authorized
I do hereby authorize Toll Southw	est, LLC	
Ap	plicant Name (Leg	gal Entity or Individual)
to conduct the submittal of an ap	oplication for TO	CEQ on its behalf
		ed regulated activities
at Cypress Road, Kyle, TX 78640		5
Precise loca	ation of the autho	rized regulated activities
Land Owner Acknowle		
I understand that Blanco River R	anch Properties	s, LP
		gal Entity or Individual)
protection plan and any special concimplementation even if the responsi property referenced in the application	litions of the appr bility for compliar on has been contr	oved or conditionally approved Edwards Aquifer oved plan through all phases of plan nce and the right to possess and control the actually assumed by another legal entity. I y condition of the executive director's approval

a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating

to Enforcement). Such violation may also be subject to civil penalties and injunction.

Land Owner Signature	
Land Owner Signature	11/8/2024 Date
THE STATE OF § TEXAS	Date
County of § HARRIS	
BEFORE ME, the undersigned authority, on this of known to me to be the person whose name is su acknowledged to me that (s)he executed same of GIVEN under my hand and seal of office on this survive in the search of the search o	ubscribed to the foregoing instrument, and for the purpose and consideration therein expressed.
Attached: (Mark all that apply)	
Lease Agreement	
Signed Contract	
Deed Recorded Easement	
Other legally binding document	

Applicant Acknowledgement

1, Durvis M. "Mike" Bravel of	Toll Southwest, LLC	
Applicant Signatory Name	Applicant Name (Legal Entity or Individual)	
acknowledge that Blanco River Ranch Properties	s, LP	
Land Owner Name (Legal Entity or Individual)		
has provided Toll Southwest, LLC		
Applicant Name (Legal E	ntity or Individual)	
with the right to possess and control the property refe		
I understand that Blanco River Ranch Properties	s, LP	
Applicant Name (Lega	l Entity or Individual)	
is contractually responsible for compliance with the apparent of the Aquifer protection plan and any special conditions of the implementation. I further understand that failure to condition is a violation is subject to administration under §213.10 (relating to Enforcement). Such violation injunction.	he approved plan through all phases of plan omply with any condition of the executive rative rule or orders and penalties as provided	
Applicant Signature		
Applicant Signature THE STATE OF § Texas County of § Texas	ululz4 Date	
BEFORE ME, the undersigned authority, on this day pe known to me to be the person whose name is subscrib acknowledged to me that (s)he executed same for the	ed to the foregoing instrument, and	
GIVEN under my hand and seal of office on this 11th	NOTARY PUBLIC NOTARY PUBLIC La Youda Heah Typed or Printed Name of Notary MY COMMISSION EXPIRES: 12-23-2024	
	LAVONDA HIGH Notary Public, State of Texas Comm. Expires 12-28-2024 Notary ID 12924615-4	

AGENT AUTHORIZATION FORM (TCEQ-0599)

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

Ι	David M. "Mike" Boswell	
	Print Name	
	Vice President, Land Development	
	Title - Owner/President/Other	
of	Toll Southwest LLC	
	Corporation/Partnership/Entity Name	
have authorized	Aimee Chavez, P.E.	
	Print Name of Agent/Engineer	
of	Pape-Dawson Consulting Engineers, LLC.	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Applicant's Signature

Date

THE STATE OF <u>TEXAS</u>

County of <u>TARRANT</u> §

BEFORE ME, the undersigned authority, on this day personally appeared Mike Boswell known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 9th day of Scotember

LAVONDA HIGH
Notary Public, State of Texas
Comm. Expires 12-28-2024
Notary ID 12924615-4

NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 12 28 2024

APPLICATION FEE FORM (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: <u>Clara Vista Lift Station & Force Main</u>

Regulated Entity Location: <u>Approximately 0.7 miles southweest of the intersection of Six Creeks</u>

Blvd. and Falling River Rd.		
Name of Customer: <u>Toll Southwe</u> s	st LLC.	
Contact Person: Kyle Ninness	Phon	e: <u>303-263-7132</u>
Customer Reference Number (if is	ssued):CN <u>605682475</u>	
Regulated Entity Reference Numb	oer (if issued):RN <u>11209</u>	4636
Austin Regional Office (3373)		
	Travis	Williamson
San Antonio Regional Office (336	2)	_
Bexar	☐ Medina	Uvalde
Comal	Kinney	
Application fees must be paid by	check, certified check, c	or money order, payable to the Texas
Commission on Environmental Q	uality. Your canceled c	heck will serve as your receipt. This
form must be submitted with yo	u r fee payment . This pa	ayment is being submitted to:
X Austin Regional Office	Sa	an Antonio Regional Office
Mailed to: TCEQ - Cashier	o	vernight Delivery to: TCEQ - Cashier
Revenues Section	1	2100 Park 35 Circle
Mail Code 214	В	uilding A, 3rd Floor
P.O. Box 13088	A	ustin, TX 78753
Austin, TX 78711-3088	(5	512)239-0357
Site Location (Check All That App	oly):	
Recharge Zone	Contributing Zone	Transition Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	1 Tanks	\$ 650
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: _____

Date: August 20, 2025

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee

Project	Fee
Extension of Time Request	\$150

CORE DATA FORM (TCEQ-10400)



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)

nenewarte	ore Data Form should be subn	nitted with the renew	val form)			ther						
2. Customer Re	eference Number (if issued)	for	for CN or RN numbers in			3. Regulated Entity Reference Number (if issued) RN 112094636						
ECTION	II: Custome	r Informa	<u>tion</u>									
4. General Cus	tomer Information	5. Effective Date	te for Custon	ner Info	rmation	Updates (mm/dd,	/уууу)					
New Custom	er 🔲	Update to Customer		Change in Regulated Entity Ownership								
Change in Leg	gal Name (Verifiable with the T	exas Secretary of Sta	ite or Texas Co	mptrolle	r of Public	Accounts)						
	Name submitted here may Comptroller of Public Acco		matically ba	sed on 1	what is c	urrent and active	with th	e Texas Secr	etary of State			
6. Customer Le	egal Name (If an individual, p	rint last name first: e	g: Doe, John)			If new Customer,	enter pre	evious Custom	er below:			
Toll Southwest LI	LC.											
7. TX SOS/CPA	Filing Number		9. Federal Tax ID			10. DUNS Number (if						
0801775669		32050842304	1			(9 digits)		applicable)				
						472582910						
11. Type of Cu	stomer:	ration			☐ Individ	dual	Partne	rship: 🗌 Gen	eral Limited			
Government: 🗌	City County Federal	Local State	Other		☐ Sole P	roprietorship	Otl	ner:				
12. Number of	Employees			_		13. Independe	ntly Ow	ned and Ope	erated?			
O-20 21	1-100 🗌 101-250 🔲 25	1-500 🛮 501 and	higher			☐ Yes	⊠ No					
14. Customer I	Role (Proposed or Actual) – as	s it relates to the Reg	ulated Entity l	isted on	this form.	Please check one o	f the follo	wing				
☐Owner ☐Occupational	Operator Licensee Responsible P		& Operator /BSA Applicant	t		☐ Other	:					
15 Mailing		11										
Ī	1320 Arrow Point Dr., Suite 40)1										
Address:	1320 Arrow Point Dr., Suite 40 City Cedar Park		State TX		ZIP	78613		ZIP + 4				

TCEQ-10400 (11/22) Page 1 of 3

18. Telephone Number				19. Extension of	r Code	е			20. Fa	ax Numbe	r (if app	olicable)	
(412) 780-2312							() -						
SECTION III:	Regu	ıla	ted Enti	ity Infor	mat	ion							
21. General Regulated En	itity Info	rmat	ion (If 'New Regi	ulated Entity" is sel	ected, a	new pe	rmit	applica	ation is a	lso require	d.)		
☐ New Regulated Entity	Updat	e to F	Regulated Entity N	Name 🛚 Update	to Reg	gulated E	ntity	Inform	nation				
The Regulated Entity Nar as Inc, LP, or LLC).	me subm	itted	l may be updat	ed, in order to m	eet TC	EQ Core	. Da	ta Sta	ndards	(removal	of orgo	anization	al endings such
22. Regulated Entity Nam	ne (Enter	name	of the site where	the regulated acti	on is ta	king plac	e.)						
Clara Vista Lift Station & Ford	ce Main												
23. Street Address of the Regulated Entity:													
(No PO Boxes)	City			State		ZIP)			7	ZIP + 4	
24. County	Hays												
	<u> </u>		If no Stree	t Address is prov	ided, 1	fields 25	5-28	are re	equired.				
25. Description to													
Physical Location:	Approxi	mate	ly 0.7 miles south	nweest of the inters	ection	of Six Cre	eeks I	Blvd. a	nd Fallin	g River Rd.			
26. Nearest City									State			Near	rest ZIP Code
Kyle									TX			7864	0
Latitude/Longitude are rused to supply coordinate	•		•	•			ata S	Stando	ards. (G	eocoding	of the	Physical i	Address may be
27. Latitude (N) In Decim	al:		29.999333			28. Lo	ngit	ude (\	N) In De	ecimal:		-97.91698	3
Degrees	Minutes	S	:	Seconds		Degree	es			Minutes			Seconds
29		5	9	57.6			(97			55		1.1
29. Primary SIC Code (4 digits)		30. 9	Secondary SIC C	Code		Primary or 6 digits		ICS Co	ode		Secono	dary NAIC	S Code
4952					237	110							
33. What is the Primary I	Business	of th	nis entity? (Do	not repeat the SIC	or NAI	CS descri _l	otion	.)					
Lift station													
1320 Arrow Point Dr., Suite 401 34. Mailing													
Address:													
Address.	City	y	Cedar Park	State	тх		;	ZIP	7861	3		ZIP + 4	
35. E-Mail Address:													I
36. Telephone Number				37. Extension o	r Code			38. F	ax Nun	nber (if ap	plicable)	
(412) 780-2312								() -				

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety ☐ Municipal Solid Waste ☐ Sludge ☐ Voluntary Cleanup	Districts New Source Review Air Storm Water	☐ OSSF☐ Title V Air		Emissions Inventory Air Petroleum Storage Tank Tires	☐ Industrial Hazardous Waste			
☐ Sludge	Review Air		i					
		☐ Title V Air		Tires	Licad Oil			
☐ Voluntary Cleanup	☐ Wastewater				☐ Used Oil			
		☐ Wastewater Ag	riculture	Water Rights	Other:			
	Preparer Inf ause, E.I.T. 43. Ext./Code	44. Fax Number	41. Title: 45. E-Mai	Engineer in Training I				
(512)454-8711		() -	ckrause@p	pape-dawson.com				
6. By my signature below, I		wledge, that the inforr		this form is true and complete updates to the ID numbers ide	e, and that I have signature authority entified in field 39.			
Company: Pap	e-Dawson Consulting Engine	ers, LLC.	Job Title:	Associate Vice President				
Name (In Print): Aim	ee Chavez, P.E.			Phone:	(512) 454- 8711			
Signature:	aimer Og			Date:	8/29/28			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this

TCEQ-10400 (11/22) Page 3 of 3