

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
(TCEQ)

WATER POLLUTION ABATEMENT PLAN
(WPAP)
&
ORGANIZED SEWAGE COLLECTION SYSTEM
(SCS)

Moore Estates Subd Improvements
8.4-acre property

Located at: 803 Westlake Drive, West Lake Hills, Texas 78746

Prepared for:

Tirres Group, LLC
3507 Native Dancer Cove
Austin, Texas 78746-1434

Prepared by:

Mr. Robert Thompson, P.E.
Thompson Land Engineering, LLC
904 N Cuernavaca DR
Austin, Texas 78733

August 2025



Thompson Land
Engineering, LLC
(F-10220)

08/27/25

Water Pollution Abatement Plan (WPAP) & Organized Sewage Collection System (SCS) Checklist

✓ **Edwards Aquifer Application Cover Page (TCEQ-20705)**

✓ **General Information Form (TCEQ-0587)**

- Attachment A - Road Map
- Attachment B - USGS / Edwards Recharge Zone Map
- Attachment C - Project Description

Geologic Assessment Form (TCEQ-0585) - Not applicable for this Residential Project

- Attachment A - Geologic Assessment Table (TCEQ-0585-Table)
- Attachment B - Stratigraphic Column
- Attachment C - Site Geology
- Attachment D - Site Geologic Map(s)

✓ **Water Pollution Abatement Plan Application Form (TCEQ-0584)**

- Attachment A - Factors Affecting Water Quality
- Attachment B - Volume and Character of Stormwater
- Attachment C - Suitability Letter from Authorized Agent (if OSSF is proposed)
- Attachment D - Exception to the Required Geologic Assessment (if requesting an exception)
 - Site Plan

✓ **Organized Sewage Collection System Plan (TCEQ-0582)**

- Attachment A - SCS Engineering Design Report
- Attachment B - Justification and Calculations for Deviation in Straight Alignment Without Manholes
- Attachment C - Justification for Variance from Manhole Spacing
- Attachment D - Calculations for Slopes for Flows Greater Than 10.0 Feet Per Second
 - Site Plan
 - Final Plan and Profile Sheets

✓ **Lift Station / Force Main System Application (TCEQ-0624)**

- Attachment A - Engineering Design Report
 - Site Plan
 - Final Plan and Profile Sheets

✓ **Temporary Stormwater Section (TCEQ-0602)**

- Attachment A - Spill Response Actions
- Attachment B - Potential Sources of Contamination
- Attachment C - Sequence of Major Activities
- Attachment D - Temporary Best Management Practices and Measures
- Attachment E - Request to Temporarily Seal a Feature (if requested)
- Attachment F - Structural Practices

- Attachment G - Drainage Area Map
- Attachment H - Temporary Sediment Pond(s) Plans and Calculations
- Attachment I - Inspection and Maintenance for BMPs
- Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

✓ **Permanent Stormwater Section (TCEQ-0600)**

- Attachment A - 20% or Less Impervious Cover Waiver (if requested for multi-family, school, or small business site)
- Attachment B - BMPs for Upgradient Stormwater
- Attachment C - BMPs for On-site Stormwater
- Attachment D - BMPs for Surface Streams
- Attachment E - Request to Seal Features (if sealing a feature)
- Attachment F - Construction Plans
- Attachment G - Inspection, Maintenance, Repair and Retrofit Plan
- Attachment H - Pilot-Scale Field Testing Plan (if proposed)
- Attachment I - Measures for Minimizing Surface Stream Contamination

✓ **Agent Authorization Form (TCEQ-0599), if application submitted by agent**

✓ **Application Fee Form (TCEQ-0574)**

✓ **Check Payable to the "Texas Commission on Environmental Quality"**

✓ **Core Data Form (TCEQ-10400)**

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Moore Estates Subd Improvements					2. Regulated Entity No.:				
3. Customer Name: Tirres Group, LLC					4. Customer No.:				
5. Project Type: (Please circle/check one)	<input checked="" type="radio"/> New	<input type="radio"/> Modification			<input type="radio"/> Extension		<input type="radio"/> Exception		
6. Plan Type: (Please circle/check one)	<input checked="" type="radio"/> WPAP	<input type="radio"/> CZP	<input checked="" type="radio"/> SCS	<input type="radio"/> UST	<input type="radio"/> AST	<input type="radio"/> EXP	<input type="radio"/> EXT	<input type="radio"/> Technical Clarification	<input type="radio"/> Optional Enhanced Measures
7. Land Use: (Please circle/check one)	<input checked="" type="radio"/> Residential		<input type="radio"/> Non-residential			8. Site (acres):		8.4	
9. Application Fee:	\$3,650		10. Permanent BMP(s):			Vegetated Filter Strips			
11. SCS (Linear Ft.):	1,022		12. AST/UST (No. Tanks):			Not applicable; none proposed			
13. County:	Travis		14. Watershed:			Little Bee Creek			

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	<u>✓</u>	—
Region (1 req.)	—	<u>✓</u>	—
County(ies)	—	<u>✓</u>	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Barton Springs/ Edwards Aquifer <u>—</u> Hays Trinity <u>—</u> Plum Creek	<u>✓</u> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<u>—</u> Austin <u>—</u> Buda <u>—</u> Dripping Springs <u>—</u> Kyle <u>—</u> Mountain City <u>—</u> San Marcos <u>—</u> Wimberley <u>—</u> Woodcreek	<u>—</u> Austin <u>—</u> Bee Cave <u>—</u> Pflugerville <u>—</u> Rollingwood <u>—</u> Round Rock <u>—</u> Sunset Valley <u>✓</u> West Lake Hills	<u>—</u> Austin <u>—</u> Cedar Park <u>—</u> Florence <u>—</u> Georgetown <u>—</u> Jerrell <u>—</u> Leander <u>—</u> Liberty Hill <u>—</u> Pflugerville <u>—</u> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<u>—</u> Edwards Aquifer Authority <u>—</u> Trinity-Glen Rose	<u>—</u> Edwards Aquifer Authority	<u>—</u> Kinney	<u>—</u> EAA <u>—</u> Medina	<u>—</u> EAA <u>—</u> Uvalde
City(ies) Jurisdiction	<u>—</u> Castle Hills <u>—</u> Fair Oaks Ranch <u>—</u> Helotes <u>—</u> Hill Country Village <u>—</u> Hollywood Park <u>—</u> San Antonio (SAWS) <u>—</u> Shavano Park	<u>—</u> Bulverde <u>—</u> Fair Oaks Ranch <u>—</u> Garden Ridge <u>—</u> New Braunfels <u>—</u> Schertz	NA	<u>—</u> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Robert C. Thompson

Print Name of Customer/Authorized Agent

Robert C. Thompson

08/07/25

Signature of Customer/Authorized Agent

Date

****FOR TCEQ INTERNAL USE ONLY****

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Robert C. Thompson

Date: July 24, 2025

Signature of Customer/Agent:



08/07/25

Project Information

1. Regulated Entity Name: Moore Estates Subd Improvments
2. County: Travis
3. Stream Basin: Little Bee Creek
4. Groundwater Conservation District (If applicable): Barton Springs/Edwards Aquifer
5. Edwards Aquifer Zone:
☒ Recharge Zone
☐ Transition Zone
6. Plan Type:

<input checked="" type="checkbox"/> WPAP	<input type="checkbox"/> AST
<input checked="" type="checkbox"/> SCS	<input type="checkbox"/> UST
<input type="checkbox"/> Modification	<input type="checkbox"/> Exception Request

7. Customer (Applicant):

Contact Person: Michael Tirres

Entity: Tirres Group, LLC

Mailing Address: 3507 Native Dancer Cove

City, State: Austin, Texas

Zip: 78746-1434

Telephone: 512-422-2880

FAX: N/A

Email Address: michael@tirreshomes.com

8. Agent/Representative (If any):

Contact Person: Robert C. Thompson

Entity: Thompson Land Engineering, LLC

Mailing Address: 904 N Cuernavaca Drive

City, State: Austin, Texas

Zip: 78733

Telephone: (512) 328-0002

FAX: none

Email Address: ric@tleng.net

9. Project Location:

- ☒ The project site is located inside the city limits of West Lake Hills.
- ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.
- ☐ The project site is not located within any city's limits or ETJ.

10. ☒ The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

The site is located on the southeast side of Westlake Drive, south of Yaupon Valley Road and directly east of the intersection of Buckeye Trail and Westlake Drive.

11. ☒ **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12. ☒ **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- ☒ Project site boundaries.
 - ☒ USGS Quadrangle Name(s).
 - ☒ Boundaries of the Recharge Zone (and Transition Zone, if applicable).
 - ☒ Drainage path from the project site to the boundary of the Recharge Zone.

13. ☒ **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

☒ Survey staking will be completed by this date: (it already has established lots)

14. ☒ **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- ☒ Area of the site
- ☒ Offsite areas
- ☒ Impervious cover
- ☒ Permanent BMP(s)
- ☒ Proposed site use
- ☒ Site history
- ☒ Previous development
- ☒ Area(s) to be demolished

15. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☒ Existing residential site
- ☐ Existing paved and/or unpaved roads
- ☐ Undeveloped (Cleared)
- ☒ Undeveloped (Undisturbed/Uncleared)
- ☐ Other: _____

Prohibited Activities

16. ☒ I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. ☒ I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);

- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

18. The fee for the plan(s) is based on:

- ☒ For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
- ☒ For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
- ☐ For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
- ☐ A request for an exception to any substantive portion of the regulations related to the protection of water quality.
- ☐ A request for an extension to a previously approved plan.

19. ☒ Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:

- ☐ TCEQ cashier
- ☒ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
- ☐ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

20. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21. ☒ No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

ATTACHMENT C – PROJECT DESCRIPTION

This Water Pollution Abatement Plan (WPAP) and Organized Sewage Collection System (SCS) application is submitted for the proposed residential subdivision construction plan on Lots 1 through 6 in the Moore Estates Subdivision in Travis County, Texas. The total property area is approximately 8.4-acres and Lot 1 is located at 803 Westlake Drive, West Lake Hills, TX 78746.

Total Project area in plan = 8.423-acres

Limits of construction (LOC) area = 1.125-acres

On-site area (within the LOC) = 0.842-acres (with 0.286-acres added Impervious Cover)

Offsite area (within the LOC) = 0.283- acres (with 0.011-acres added IC)

Total Added IC (within plan) = 0.297-acres

Offsite area (outside LOC, but contributing runoff area to water quality control) = 0.439-acres

Impervious Cover (existing roadway IC within Offsite area and outside the LOC) = 0.141-acres

Permanent BMPs = Vegetative Filter Strips

Proposed site use = Single Family Residential

Site History = Lot 1 has had a SF residence since 1959; Lots 2-6 have always been vacant

Previous Development = none (except for the SF development on Lot 1)

Areas to be demolished = two (2) existing driveways and pavement on Lots 1 and 2


The storm water runoff from the proposed impervious covered areas will be treated by vegetative filter strips (VFS). No detention is expected to be required (or proposed) with this project. This project is proposing for the construction of a shared driveway for Lots 1 through 6 with two (2) driveway approaches along with the extension of a wastewater force main and a water main (as well as the associated service connections for each lot). The proposed work will mostly take place onsite, except for the driveway connections in the Westlake Drive right-of-way and the utility extensions and connections. There are no proposed aboveground or below ground storage tanks planned with this project.

For the total suspended solids (TSS) removal calculations, all proposed impervious cover will be treated by VFS that are planned to be fifteen (15) wide and downgradient of the pavement. The VFS has been designed according to the current TCEQ Technical Guidance Manual; see the attached construction plan sheets for further clarifications.

The SCS will consist of **1,022-linear feet of 2” PVC SDR 21 force main wastewater line** that starts where two (2) proposed service lines combine (where the service line from Lot 2 connects with the service line from Lot 1). There are no cleanouts on the “combined flow line” but each lot connection will have cleanouts.

There are no additional water quality controls that are proposed with this application. No other construction is being planned with this application. There are some existing driveways to be removed for this work before the new pavement is added.

Attachment A – Road Map




MAP GRID: F24 MAPSCO PG: 853D

LOCATION MAP

SCALE: NTS


Edwards Aquifer Viewer Custom Print



7/24/2025, 1:41:39 PM

1:24,075

- | | |
|------------------------------------|---------------------------------------|
| TCEQ_EDWARDS_OFFICIAL_MAPS | City/Place |
| 7.5 Minute Quad Grid | Edwards Aquifer Boundary central line |
| TX Counties | Edwards Aquifer Boundary |
| Groundwater Conservation Districts | |
| Barton Springs/Edwards Aquifer CD | Edwards Aquifer Label |
| Southwestern Travis County GCD | World_Hillshade |



Esri, NASA, NGA, USGS, FEMA, Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, (c) OpenStreetMap contributors, and the GIS User Community, TCEQ

Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Robert C. Thompson

Date: July 24, 2025

Signature of Customer/Agent:



08/07/25

Regulated Entity Name: Moore Estates Subd Improvements

Regulated Entity Information

1. The type of project is:

- ☒ Residential: Number of Lots: 6
- ☐ Residential: Number of Living Unit Equivalents: _____
- ☐ Commercial
- ☐ Industrial
- ☐ Other: _____

2. Total site acreage (size of property): 8.4-acres

3. Estimated projected population: 21

4. The amount and type of impervious cover expected after construction are shown below:

Table 1 - Impervious Cover Table

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	0	÷ 43,560 =	0
Parking	0	÷ 43,560 =	0
Other paved surfaces	12,937	÷ 43,560 =	0.297
Total Impervious Cover	12,937	÷ 43,560 =	0.297

Total Impervious Cover 0.297 ÷ Total Acreage 8.423 X 100 = 3.5% Impervious Cover

5. ☒ **Attachment A - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
6. ☒ Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

7. Type of project:

- ☐ TXDOT road project.
- ☐ County road or roads built to county specifications.
- ☐ City thoroughfare or roads to be dedicated to a municipality.
- ☐ Street or road providing access to private driveways.

8. Type of pavement or road surface to be used:

- ☐ Concrete
- ☐ Asphaltic concrete pavement
- ☐ Other: _____

9. Length of Right of Way (R.O.W.): _____ feet.

Width of R.O.W.: _____ feet.

L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.

10. Length of pavement area: _____ feet.

Width of pavement area: _____ feet.

L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.

Pavement area _____ acres ÷ R.O.W. area _____ acres x 100 = _____% impervious cover.

11. ☐ A rest stop will be included in this project.

☐ A rest stop will not be included in this project.

12. ☐ Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

13. ☒ **Attachment B - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

14. The character and volume of wastewater is shown below:

<u>100%</u> Domestic	<u>1,470</u> Gallons/day
<u>0%</u> Industrial	<u>0</u> Gallons/day
<u>0%</u> Commingled	<u>0</u> Gallons/day
TOTAL gallons/day <u>1,470 (or 12,735-gpd using peaking factor and wet weather flows)</u>	

15. Wastewater will be disposed of by:

☐ On-Site Sewage Facility (OSSF/Septic Tank):

☐ **Attachment C - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

☐ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

☒ Sewage Collection System (Sewer Lines):

☐ Private service laterals from the wastewater generating facilities will be connected to an existing SCS.

☒ Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.

☐ The SCS was previously submitted on_____.

☒ The SCS was submitted with this application.

☐ The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

☒ The sewage collection system will convey the wastewater to the South Austin Regional (SAR) Wastewater (name) Treatment Plant. The treatment facility is:

☒ Existing.

☐ Proposed.

16. ☒ All private service laterals will be inspected as required in 30 TAC §213.5.

Site Plan Requirements

Items 17 – 28 must be included on the Site Plan.

17. ☒ The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 60'.

18. 100-year floodplain boundaries:

☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

☒ No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA FIRM Map Number 48453C0445K, effective date: Jan. 22, 2020

19. ☒ The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.

☐ The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.

20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

☐ There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)

☐ The wells are not in use and have been properly abandoned.

☐ The wells are not in use and will be properly abandoned.

☐ The wells are in use and comply with 16 TAC §76.

☒ There are no wells or test holes of any kind known to exist on the project site.

21. Geologic or manmade features which are on the site:

☐ All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.

☐ No sensitive geologic or manmade features were identified in the Geologic Assessment.

☒ **Attachment D - Exception to the Required Geologic Assessment.** A request and justification for an exception to a portion of the Geologic Assessment is attached.

- 22. ☒ The drainage patterns and approximate slopes anticipated after major grading activities.
- 23. ☒ Areas of soil disturbance and areas which will not be disturbed.
- 24. ☒ Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 25. ☒ Locations where soil stabilization practices are expected to occur.
- 26. ☐ Surface waters (including wetlands).
☒ N/A
- 27. ☐ Locations where stormwater discharges to surface water or sensitive features are to occur.
☒ There will be no discharges to surface water or sensitive features.
- 28. ☒ Legal boundaries of the site are shown.

Administrative Information

- 29. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 30. ☒ Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

ATTACHMENT A – FACTORS AFFECTING WATER QUALITY

The following are believed to be the potential sources of sediment to stormwater runoff:

- 1) Disturbed earth from rough grading,
- 2) road base for pavement, and
- 3) disturbed earth from the construction of the water quality control

The following are believed to be potential pollutants and sources, other than sediment, to stormwater runoff:

- 1) Construction debris (e.g., wood form boards, nails, tie wire for rebar, survey laths, survey tape, etc.),
- 2) Items that can float, such as cups and paper,
- 3) Possibly oils from leaking machinery,
- 4) Possibly fuel should any refueling activity occur,
- 5) Possibly concrete materials from truck washout activities (if not bound in the solidifying mass), and
- 6) Possibly paint from striping activities (if not adhered to something large).

ATTACHMENT B – VOLUME AND CHARACTER OF STORM WATER

The proposed work with this application is not expected to produce a significant amount of volume from the stormwater, due to the relatively small site and disturbance area and the impervious cover will not increase. Additionally, the quality of the stormwater is expected to improve in the existing conditions, since the impervious cover being added will now be treated by a water quality control.

Pre-construction runoff coefficient = 80.00

Post-construction runoff coefficient = 86.09

ATTACHMENT C – SUITABILITY LETTER FROM AUTHORIZED AGENT

This is not applicable for this project

ATTACHMENT D – EXCEPTION TO THE REQUIRED GEOLOGIC ASSESSMENT

See correspondence on the next page; this project is Exempt from a GA because it is for a single-family residential subdivision with only six (6) residential lots (not a part of a larger development) that will be constructed on less than ten (10) acres.

RE: Moore Estates Subdivision Improvements WPAP/SCS - Administrative NOD

1 message

James Slone <james.slone@tceq.texas.gov>
To: Mark Roeder <mark@tleng.net>
Cc: Robert Thompson <ric@tleng.net>

Mon, Aug 25, 2025 at 2:35 PM

Well, I forgot that provision! You are off the hook. NO Geologic Assessment is required for the project.

Bo

James "Bo" Slone, P.G.

Team Leader

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

(512) 239-6994

From: Mark Roeder <mark@tleng.net>
Sent: Monday, August 25, 2025 2:22 PM
To: James Slone <james.slone@tceq.texas.gov>
Cc: Robert Thompson <ric@tleng.net>
Subject: Re: Moore Estates Subdivision Improvements WPAP/SCS - Administrative NOD

Ah, okay, we did already contact a GA for a proposal for this property, so hopefully we'll have a quick turnaround.

Just to confirm, though, per the TAC, it looks like it states that ALL Single-family Subdivisions (less than 10-acres) automatically qualify for the exemption, but that is not the case, apparently?

(3) Geologic assessment. For all regulated activities, the applicant must submit a geologic assessment report prepared by a geologist describing the site-specific geology. The report must identify all potential pathways for contaminant movement to the Edwards Aquifer. **Single-family residential subdivisions constructed on less than ten acres are exempt from this requirement.** The geologic assessment report must be signed, sealed, and dated by the geologist preparing the report.

On Mon, Aug 25, 2025 at 2:13 PM James Slone <james.slone@tceq.texas.gov> wrote:

Sorry, this one will need a Geologic Assessment. There are a lot of features relatively close by. It should be an easy one for the PG,

Bo

James "Bo" Slone, P.G.

Team Leader

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

(512) 239-6994

From: Mark Roeder <mark@tleng.net>

Sent: Monday, August 25, 2025 2:08 PM

To: James Slone <james.slone@tceq.texas.gov>

Cc: Robert Thompson <ric@tleng.net>

Subject: Re: Moore Estates Subdivision Improvements WPAP/SCS - Administrative NOD

Yes, I should have included the [attached] project description. This will be six (6) single-family residential projects, but we are only preparing a "shared use driveway" and the W/WW utility connections at this time.

This is a separate subdivision (and not part of a larger master-planned community).

Mark

On Mon, Aug 25, 2025 at 2:00 PM James Slone <james.slone@tceq.texas.gov> wrote:

Mark,

It looks like this is a single -family residential project. (please let me know if not) For single-family residential projects not associated with a larger master-planned community/subdivision, a geologic exception is not required, Please let me know if you have any questions.

Bo

James "Bo" Slone, P.G.

Team Leader

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

(512) 239-6994

From: Mark Roeder <mark@tleng.net>
Sent: Monday, August 25, 2025 1:13 PM
To: James Slone <james.slone@tceq.texas.gov>
Cc: Robert Thompson <ric@tleng.net>
Subject: Re: Moore Estates Subdivision Improvements WPAP/SCS - Administrative NOD

Greetings Bo,

See attached [location maps and Geotechnical Report] and let us know if this project [at 803 Westlake Drive] qualifies for the Exception to the Geologic Assessment. Let us know if you have any questions or concerns.

Thanks,

Mark Roeder, EIT

Thompson Land Engineering, LLC

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: **Moore Estates Subd Improvements**

Date Prepared: **8/25/2025**

Updated:

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where:

$L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load

A_N = Net increase in impervious area for the project

P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County =	Travis	
Total project area included in plan =	8.423	acres
Predevelopment impervious area within the limits of the plan =	0.000	acres
Total post-development impervious area within the limits of the plan =	0.297	acres
Total post-development impervious cover fraction =	0.035	
P =	32	inches

$L_{M \text{ TOTAL PROJECT}}$ = **259** lbs.

Number of drainage basins / outfalls areas leaving the plan area = **2**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =	1	2
Total drainage basin/outfall area =	0.933 acres	7.490
Predevelopment impervious area within drainage basin/outfall area =	0.000 acres	0.000
Post-development impervious area within drainage basin/outfall area =	0.297 acres	0.000
Post-development impervious fraction within drainage basin/outfall area =	0.32	0.00
$L_{M \text{ THIS BASIN}}$ =	259 lbs.	0

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
Removal efficiency = **85** percent

Vegetated Filter Strips

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_I \times 34.6 + A_P \times 0.54)$

where:

A_C = Total On-Site drainage area in the BMP catchment area

A_I = Impervious area proposed in the BMP catchment area

A_P = Pervious area remaining in the BMP catchment area

L_R = TSS Load removed from this catchment area by the proposed BMP

A_C =	0.933	acres
A_I =	0.297	acres
A_P =	0.636	acres
L_R =	289	lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **289** lbs.

F = **1.00**

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth =	4.00	inches
Post Development Runoff Coefficient =	0.27	
On-site Water Quality Volume =	3623	cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP =	0.439	acres
Off-site Impervious cover draining to BMP =	0.141	acres
Impervious fraction of off-site area =	0.32	
Off-site Runoff Coefficient =	0.27	
Off-site Water Quality Volume =	1714	cubic feet

Storage for Sediment =	1067	
Total Capture Volume (required water quality volume(s) x 1.20) =	6403	cubic feet

THE SIZING REQUIREMENTS FOR THE FOLLOWING BMPs / LOAD REMOVALS ARE BASED UPON FLOW RATES - NOT CALCULATED WATER QUALITY VOLUMES

16. Vegetated Filter Strips

Designed as Required in RG-348

Pages 3-55 to 3-57

There are no calculations required for determining the load or size of vegetative filter strips.

The 80% removal is provided when the contributing drainage area does not exceed 72 feet (direction of flow) and the sheet flow leaving the impervious cover is directed across 15 feet of engineered filter strips with maximum slope of 20% or across 50 feet of natural vegetation with a maximum slope of 10%. There can be a break in grade as long as no slope exceeds 20%.

If vegetative filter strips are proposed for an interim permanent BMP, they may be sized as described on Page 3-56 of RG-348.

Organized Sewage Collection System Application

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Moore Estates Subd Improvements

1. ☒ **Attachment A – SCS Engineering Design Report.** This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

Customer Information

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Michael Tirres

Entity: Tirres Group, LLC

Mailing Address: 3507 Native Dancer Cove

City, State: Austin, Texas

Zip: 78746-1434

Telephone: 512-422-2880

Fax: N/A

Email Address: michael@tirreshomes.com

The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: Robert C. Thompson

Texas Licensed Professional Engineer's Number: 69524

Entity: Thompson Land Engineering, LLC

Mailing Address: 904 N Cuernavaca

City, State: Austin, Texas

Zip: 78733

Telephone: (512) 328-0002

Fax: none

Email Address: ric@tleng.net

Project Information

4. Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):

- ☒ Residential: Number of single-family lots: 6
☐ Multi-family: Number of residential units: _____
☐ Commercial
☐ Industrial
☐ Off-site system (not associated with any development)
☐ Other: _____

5. The character and volume of wastewater is shown below:

100% Domestic 1,470 gallons/day
 _____% Industrial _____ gallons/day
 _____% Commingled _____ gallons/day
 Total gallons/day: 1,470 (or 12,735-gpd using peaking factor and wet weather flows)

6. Existing and anticipated infiltration/inflow is 6,300 gallons/day. This will be addressed by: using water-tight pipes and joints (include rubber gaskets and PVC compression joints), and size-on-size resilient connectors; testing the installed pipe per TCEQ requirements.
7. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.
- ☐ The WPAP application for this development was approved by letter dated _____. A copy of the approval letter is attached.
☒ The WPAP application for this development was submitted to the TCEQ on the same date as this application, but has not been approved.
☐ A WPAP application is required for an associated project, but it has not been submitted.
☐ There is no associated project requiring a WPAP application.

8. Pipe description:

Table 1 - Pipe Description

<i>Pipe Diameter(Inches)</i>	<i>Linear Feet (1)</i>	<i>Pipe Material (2)</i>	<i>Specifications (3)</i>
2	1,022	PVC SDR 21	ASTM D 2241

Total Linear Feet: 1,022

(1) Linear feet - Include stub-outs and double service connections. Do not include private service laterals.

(2) Pipe Material - If PVC, state SDR value.

(3) Specifications - ASTM / ANSI / AWWA specification and class numbers should be included.

9. The sewage collection system will convey the wastewater to the South Austin Regional (SAR) Wastewater (name) Treatment Plant. The treatment facility is:

- ☒ Existing
☐ Proposed

10. All components of this sewage collection system will comply with:

- ☒ The City of Austin standard specifications.
☐ Other. Specifications are attached.

11. ☐ No force main(s) and/or lift station(s) are associated with this sewage collection system.
☒ A force main(s) and/or lift station(s) is associated with this sewage collection system and the **Lift Station/Force Main System Application** form (TCEQ-0624) is included with this application.

Alignment

12. ☐ There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.
13. ☐ There are no deviations from straight alignment in this sewage collection system without manholes.
☒ **Attachment B - Justification and Calculations for Deviation in Straight Alignment without Manholes.** A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.
☐ For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.

Manholes and Cleanouts

- N/A 14. ☐ Manholes or clean-outs exist at the end of each sewer line(s). These locations are listed below: (Please attach additional sheet if necessary)

Table 2 - Manholes and Cleanouts

<i>Line</i>	<i>Shown on Sheet</i>	<i>Station</i>	<i>Manhole or Clean-out?</i>
Not Applicable (N/A)	Of		
	Of		
	Of		
	Of		
	Of		
	Of		

<i>Line</i>	<i>Shown on Sheet</i>	<i>Station</i>	<i>Manhole or Clean-out?</i>
N/A	Of		
	Of		
	Of		
	Of		

☐ N/A 15. ☐ Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.

☐ N/A 16. ☐ The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
≥54	2000

☐ **Attachment C – Justification for Variance from Maximum Manhole Spacing.** The maximum spacing between manholes on this project (for each pipe diameter used) is greater than listed in the table above. A justification for any variance from the maximum spacing is attached, and must include a letter from the entity which will operate and maintain the system stating that it has the capability to maintain lines with manhole spacing greater than the allowed spacing.

☐ N/A 17. ☐ All manholes will be monolithic, cast-in-place concrete.

☐ The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

Site Plan Requirements

Items 18 - 25 must be included on the Site Plan.

18. ☒ The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 20' & 40'.

19. ☒ The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.

20. Lateral stub-outs:

☒ The location of all lateral stub-outs are shown and labeled.

- ☐ No lateral stub-outs will be installed during the construction of this sewer collection system.

21. Location of existing and proposed water lines:

- ☒ The entire water distribution system for this project is shown and labeled.
☐ If not shown on the Site Plan, a Utility Plan is provided showing the entire water and sewer systems.
☐ There will be no water lines associated with this project.

22. 100-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)
☐ After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 3 - 100-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
	of	to
	of	to
	of	to
	of	to

23. 5-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concrete-lined channels constructed above sewer lines.)
☐ After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
	of	to
	of	to
	of	to
	of	to

24. ☒ Legal boundaries of the site are shown.

25. ☒ The **final plans and technical specifications** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must be included on the Plan and Profile sheets.

26. ☐ All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.

☒ There will be no water line crossings.

☐ There will be no water lines within 9 feet of proposed sewer lines.

Table 5 - Water Line Crossings

<i>Line</i>	<i>Station or Closest Point</i>	<i>Crossing or Parallel</i>	<i>Horizontal Separation Distance</i>	<i>Vertical Separation Distance</i>
-------------	-------------------------------------	---------------------------------	---	---

Note: in the future, private domestic services could cross the force main, but both will use pressure rated pipe.

27. Vented Manholes:

☒ **No part** of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.

☐ **A portion** of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.

☐ **A portion** of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.

☐ **A portion** of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.

Table 6 - Vented Manholes

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>

28. Drop manholes:

- ☒ There are no drop manholes associated with this project.
- ☐ Sewer lines which enter new or existing manholes or "manhole structures" higher than 24 inches above the manhole invert are listed in the table below and labeled on the appropriate profile sheets. These lines meet the requirements of 30 TAC §217.55(l)(2)(H).

Table 7 - Drop Manholes

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>

29. Sewer line stub-outs (For proposed extensions):

- ☐ The placement and markings of all sewer line stub-outs are shown and labeled.
- ☒ No sewer line stub-outs are to be installed during the construction of this sewage collection system.

30. Lateral stub-outs (For proposed private service connections):

- ☐ The placement and markings of all lateral stub-outs are shown and labeled.
- ☒ No lateral stub-outs are to be installed during the construction of this sewage collection system.

31. Minimum flow velocity (From Appendix A)

- ☒ Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.

32. Maximum flow velocity/slopes (From Appendix A)

- ☒ Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.
- ☐ **Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.** Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

Table 8 - Flows Greater Than 10 Feet per Second

<i>Line</i>	<i>Profile Sheet</i>	<i>Station to Station</i>	<i>FPS</i>	<i>% Slope</i>	<i>Erosion/Shock Protection</i>

33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provisions noted below have been made to protect against pipe displacement by erosion and/or shock under 30 TAC §217.53(l)(2)(B).

- ☐ Concrete encasement shown on appropriate Plan and Profile sheets for the locations listed in the table above.
- ☐ Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on appropriate Plan and Profile sheets for the locations listed in the table above.
- ☒ N/A

Administrative Information

34. ☒ The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
35. ☒ Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

Table 9 - Standard Details

<i>Standard Details</i>	<i>Shown on Sheet</i>
Lateral stub-out marking [Required]	7 & 11 of 15
Manhole, showing inverts comply with 30 TAC §217.55(l)(2) [Required]	n/a of n/a
Alternate method of joining lateral to existing SCS line for potential future connections [Required]	n/a of n/a
Typical trench cross-sections [Required]	13 of 15
Bolted manholes [Required]	n/a of n/a
Sewer Service lateral standard details [Required]	13 of 15
Clean-out at end of line [Required, if used]	n/a of n/a
Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps]	n/a of n/a
Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed]	n/a of n/a
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used]	n/a of n/a

Standard Details	Shown on Sheet
Drop manholes [Required, if a pipe entering a manhole is more than 24 inches above manhole invert]	n/a of n/a

36. ☒ All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
37. ☒ All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
- ☒ Survey staking was completed on this date: (it is already an established lot)
38. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
39. ☒ Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: Robert C. Thompson

Date: July 17, 2025

Place engineer's seal here:

Thompson Land
Engineering, LLC
(F-10220)



Signature of Licensed Professional Engineer:

Robert C. Thompson

08/07/25

Appendix A-Flow Velocity Table

Flow Velocity (Flowing Full) All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Table 10 - Slope Velocity

<i>Pipe Diameter(Inches)</i>	<i>% Slope required for minimum flow velocity of 2.0 fps</i>	<i>% Slope which produces flow velocity of 10.0 fps</i>
6	0.50	12.35
8	0.33	8.40
10	0.25	6.23
12	0.20	4.88
15	0.15	3.62
18	0.11	2.83
21	0.09	2.30
24	0.08	1.93
27	0.06	1.65
30	0.055	1.43
33	0.05	1.26
36	0.045	1.12
39	0.04	1.01
>39	*	*

**For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.*

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

Where:

v = velocity (ft/sec)
 n = Manning's roughness coefficient (0.013)
 R_h = hydraulic radius (ft)
 S = slope (ft/ft)



THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering

SCS ENGINEERING DESIGN REPORT

for:

Moore Estates Subd Improvements

To be located at:

803 Westlake Drive
West Lake Hills, Texas 78746


Prepared By:

Thompson Land Engineering, LLC

Robert C. Thompson, P.E.
904 N. Cuernavaca
Austin, Texas 78733
512-328-0002
512-328-1112 (fax)

Preparation Date

July 18, 2025



Thompson Land
Engineering, LLC
(F-10220)

August 4, 2025

SCS Engineering Design Report

Introduction (and background information)

The application submitted is to permit the Subdivision Construction Plan for an 8.4-acre residential subdivision with six (6) lots. The project will consist of a shared driveway and the extension of the water and wastewater lines within the right-of-way of Westlake Drive, which is within the Edwards Aquifer Recharge Zone. Only the force mains are to be installed with this SCS; any future developments in these single-family lots will include the lift stations (and modified SCS and/or WPAP application, as appropriate) when each lot is developed in future.

The property is within the City limits of West Lake Hills and has mostly been vacant except for a single-family residence that was shown to be built in 1959. The property is legally divided and consists of Lots 1-6 in the Moore Estates Subdivision that was recorded in Document # 202300003 in the Travis County public records.

Floodplain

The nearest drainage feature is a tributary to Little Bee Creek, which is located on the back side of the property; however, there is no portion of this project that will be located within a floodplain, as shown on FEMA FIRM map # 48453C0445K (effective date January 22, 2020).

Edwards Aquifer

This site is located within Edward's Aquifer Recharge Zone. A water quality control (vegetative filter strip) is proposed to treat this proposed shared driveway, which is designed in accordance with the TCEQ Technical Guidance Manual. A Water Pollution Abatement Plan (WPAP) application is being submitted concurrently with this Organized Sewage Collection System (SCS) application. Prior to any construction, the WPAP and SCS will be approved by the TCEQ, (in addition to the Construction Plan set being approved by the City of Westlake, as well as the Westlake Fire Department and the Water District WCID-10).

Soils

Based on the USDA Natural Resources Conservation Services, the soils are primarily Urban land and Brackett soils (UuE) at the front of the lots and Eckrant soils and Urban land (TeE) in the back of the property. These soil types are both classified into the "D" Hydrologic group.

Wastewater Utilities

The existing wastewater lines at the site are listed below, along with the general proposed flows from this project.

Existing WW Force Main	Location:	Size (in):	Material:
	Within the Right-of-Way of Westlake Drive	2"	PVC SDR 21
Proposed Average Dry Weather Flows =	1,470-GPD	=	1.0-gpm (pumped at 20-gpm)
Proposed Peak Dry Weather Flows =	6,435-GPD	=	4.5-gpm (pumped at 20-gpm)
Proposed Peak Wet Weather Flows =	12,735-GPD	=	8.8-gpm (pumped at 20-gpm)

Piping Materials

This project is proposed to install PVC SDR 21 (ASTM D 2241) force main wastewater lines, which can withstand the pressure generated by instantaneous pump stoppage, due to power failure under maximum pumping conditions. See attached Buckling, Wall Crushing and Deflection analyses that are included with this report.

The underground force main pipe joint will include either push-on rubber gaskets or mechanical joints with a pressure rating equal to or greater than that of the force main pipe material. Exposed force main pipe joints will be flanged or flexible and will be adequately secured (to prevent movement due to wastewater surges).

A detectable underground warning tape will be laid in the same trench as a force main pipe. This warning tape will be located above and parallel to the force main and will include the label "PRESSURIZED WASTEWATER" continuously repeated in at least 1.5-inch-tall letters.

Manholes

There are no proposed manholes for this project; lines will be pressurized in the force main. There are no existing wastewater manhole covers that lie within a 100-year floodplain for this project.

Testing, Inspection and Certification

The final plans and specifications will include the pressure testing procedures. A pressure test (using 50 pounds per square inch above the normal operating pressure of a force main) will be included. A valve for pressure testing will be installed (near the discharge point of a force main), which would remain after a test is successfully completed. A pump isolation valve may potentially be used as an opposite termination point. A test will involve filling a force main with water. This proposed pipe is expected to hold the designated test pressure for a minimum of 4.0 hours. The leakage rate should not exceed 10.0 gallons per inch of diameter per mile of pipe per day. The following equation, from Figure: 30 TAC §217.68(g), is used to calculate the acceptable leakage rate in gallons per hour per 1,000 feet of pipe:

$$L = \frac{SD\sqrt{P}}{155,400}$$

Equation C.5.

Where:

L = Acceptable leakage rate (gallons/hour/1,000 feet of pipe, based on a leakage rate of 10.0 gallons per inch of diameter per mile of pipe per day)

S = Length of pipe (feet)

D = Nominal diameter of pipe (inches)

P = Average test pressure (pounds/square inch)

Occupational Safety, Public Health, and Environmental Protection

The project plans and specifications must ensure that the pipe installation will adhere to the minimum separation distances allowed by Section 217.53(d) of the TCEQ's rules. Additionally, the project plans include the exact reproduction of the separation distance wording detailed in Section 217.53, which ensures that the separation distance between any unknown water lines that are discovered during the installation phase of the project.

There are no manholes anticipated with this project.

Personal gas detectors are required for wear by all personnel whose jobs require entering enclosed spaces (such as manholes and lift stations that can have accumulations of hydrogen sulfide or other harmful gases). Even though these items are not expected for this project, the contractor would be responsible for ensuring the detectors when required.

For environmental protection and controlling erosion, silt fencing will be installed along the downstream perimeter of the limits of construction and any spoils storage areas, due to runoff during construction. A stabilized construction entrance will be installed at the construction entrance to further control sediments being released downstream.

Moore Estates Subd Improvements
WASTEWATER SERVICE CALCULATIONS
FOR TCEQ SCS

7/17/2025

Tract Information

8.4 Total Tract Area
8.4 Drainage Area Acres

LUE Table

Shopping Center	Restaurant; Cafeteria	Office	Office Warehouse	Single Family	Condo	Apart.	
0	0	0	0	6	0	0	Square Feet or Number
1660	200	3000	4000	1	0.7	0.5	LUEs/sf
							LUEs/each
0	0	0	0	6	0	0	Total LUEs per category
							Total LUEs in this project = 6.0

Wastewater Service Calculations

Use Criteria

245 gpd/LUE per UCM 2.9.4 (A)(1) or 70 gal/cap x 3.5 people/LUE)
750 gal/ac/day (Inflow/Infiltration) per UCM 2.9.4(A)(3)

Average Demand

1.0 gpm, Average Dry Weather Flow (ADWF) = gpd/LUE * LUEs

Peak Demands

4.4 Peaking Factor, Pf = $[18 + (0.0206 \times \text{ADWF})^{1/2}] / [4 + (0.0206 \times \text{ADWF})^{1/2}]$ per UCM 2.9.4(A)(4)

4.5 gpm, Peak Dry Weather Flow (PDWF) = ADWF * Pf

8.8 gpm, Peak Wet Weather Flow = PDWF + I/I per UCM 2.9.4(A)(5)

Required Line Sizes (per UCM 2.9.4(B)(3))

1.3 Size of Main Required at Half Full for PDWF at 2 fps

0.6 Size of Main Required at Half Full for PDWF at 10 fps

Buckling Analysis: 30 TAC 217.10 (c)

- 1 Calculate allowable and predicted buckling pressure. Predicted and allowable buckling pressures must be calculated for each size of pipe and type of flexible pipe material. For the purposes of this application form, the buckling analysis must be performed using the method outlined below. The method of calculating allowable buckling pressure provided below is only valid for lines which are installed at depths of 2 ft < H < 80 feet.

- a) Calculate allowable buckling pressure as follows:

$$q_a = 0.4 * \sqrt[3]{32 * R_w * B' * E_b * (E * I / D^3)}$$

$$R_w = 1 - 0.33 * (h_w / h)$$

$$B' = \frac{I}{I + 4 * e^{-0.065H}}$$

$$I = (t^3 / 12) * (\text{inches}^4 / \text{Linch})$$

1,022-feet gravity wastewater line with a size material = 2" PVC SDR 21

q_a	=	allowable buckling pressure, pounds per square inch (psi)	
			2" = 71 psi
h	=	height of soil surface above top of pipe in inches (in)	
			2" = 73.54 inches
h_w	=	height of water surface above top of pipe in inches (in) (groundwater elevation)	
			2" = 0 inches
R_w	=	Water buoyancy factor. If $h_w = 0$, $R_w = 1$. If $0 < h_w < h$ (groundwater elevation is between the top of the pipe and the ground surface), calculate R_w with Equation 2	
			2" = 1
H	=	Depth of burial in feet (ft) from ground surface to crown of pipe.	
			2" = 6.13 feet
B'	=	Empirical coefficient of elastic support	
			2" = 0.27
E_b	=	modulus of soil reaction for the bedding material (psi)	
			2" = 750 psi
E	=	modulus of elasticity of the pipe material (psi)	
			2" = 400,000 psi
I	=	moment of inertia of the pipe wall cross section per linear inch of pipe, $\text{inch}^4 / \text{lineal inch} = \text{inch}^3$. For solid wall pipe, I can be calculated with equation 4. If the pipe used is not solid wall pipe (for example a pipe with a ribbed cross section), the proper moment of inertia formula must be obtained from the manufacturer.	
			I = 0.0001 cubic inches

t = pipe structural wall thickness (in)
2" = 0.113 inches

D = mean pipe diameter (in)
2" = 2.149 inches

b) Calculate pressure applied to pipe under installed conditions:

$$W_c = \gamma_s * H * (D + t) / 144 \quad q_p = \gamma_w * h_w + R_w * (W_c / D) + L_l$$

W_c = vertical soil load on the pipe per unit length in pounds per linear inch (lb/in)
2" = 11.6 lb/in

Y_w = 0.0361 pounds per cubic inch (pci), specific weight of water

Y_s = specific weight of soil in pounds per cubic foot (pcf) = 120 lbs/cf

q_p = pressure applied to pipe under installed conditions (psi)
2" = 15.4 psi

L_l = Live load as previously determined = 10 for all pipes

2 Report q_a and q_p for each pipe diameter proposed and for each type of pipe material proposed:

2 inches
PVC SDR 21
71 psi
15.4 psi

3 If q_a > q_p, specified pipe is acceptable for the proposed installation. If q_a < q_p, the wall thickness of the pipe must be increased and/or a pipe with a larger modulus of elasticity (E) must be used. Make the appropriate modifications and repeat the buckling analysis, showing that for the upgraded pipe, q_a > q_p. Do all of the proposed pipes for this project meet these requirements?

YES

4 Calculate the maximum depth that the pipe can be buried before **WALL CRUSHING** will occur

$$H = (24 * P_c * A) / (\gamma_s * D_o)$$

D_o = outside pipe diameter (in)
2" = 2.375 in

P_c = compressive stress or hydrostatic design basis (HDB); For typical PVC pipes, assume 4,000-psi

A = surface area of the pipe wall (in²/ft)
2" = 0.8 in²/ft

Y_s = specific weight of soil in pounds per cubic foot (pcf) = 120 lbs/cf

24 = conversions and coefficients

H = Depth of burial in feet (ft) from ground surface to crown of pipe
2" = 270 ft

Deflection Analysis: 30 TAC 217.10 (c)

- 5a** Indicate E_b (modulus of soil reaction for the bedding material) in psi. If E_b is greater than 750 psi, justification must be provided:

750 psi

- 5b** Indicate E'_n (modulus of soil reaction for the in-situ soil) in psi:

1,250 psi

- 6** Based on the above, calculate the ratio of bedding modulus to soil modulus:

$$E_b/E'_n = \quad \quad \quad \underline{0.6}$$

If this ratio is greater than 1.25, a zeta factor must be calculated by completing **7** and **8**, where zeta is a factor which corrects for the effect of in-situ soil on pipe stability. If the ratio of bedding modulus to soil modulus is **less than or equal to 1.25, assume zeta = 1.0** and skip to **8**.

- 7** Where native soil is significantly weaker than bedding material, or where predicted deflection approaches 5%, the effect of native soil must be quantified using Leonhardt's Zeta factor. Zeta must be determined for each diameter of pipe and corresponding trench width. Zeta may be estimated graphically or calculated directly. If zeta is estimated graphically, identify the source for tables, figures, etc...(including page numbers and table numbers or figure numbers for each source) which were used to estimate zeta. To calculate zeta directly use the formulas in **7(b)**, below. The calculations which are done to determine the zeta factors for the different pipe diameters must be included with this submittal.

- (a) Sources: Not applicable

- (b) Calculations:

$$zeta = \frac{1.44}{f + (1.44 - f) * (E_b / E'_n)}$$

$$f = \frac{b/d_a - 1}{1.154 + 0.444 * (b/d_a - 1)}$$

f = pipe/trench width coefficient

b = trench width

d_a = pipe diameter

E_b = modulus of soil reaction for the bedding material (psi)

E'_n = modulus of soil reaction for the in-situ soil (psi)

- 8** For each size of pipe, report zeta factor determined in **6** or **7**:

Pipe Diameter: 2 inches

Trench Width (minumum): 26 inches

Zeta: 1.0

9

Determine pipe stiffness (P_s) in psi. P_s can be determined either by parallel plate test at 5% deflection, based on manufacturer's data or national reference standards; or, calculated using either equation 10 or equation 11. As an example, the minimum pipe stiffness at 5% deflection for PVC pipe less than 15 inches in diameter meeting ASTM D 3034, is 46 psi for SDR-35 and 115 psi for SDR 26. If equation 11 is used, the ring stiffness constant (RSC) is provided by the pipe manufacturer. Show calculations, or provide proper references, for each size of pipe and for each flexible pipe material.

$$P_s = \frac{EI}{0.149 * r^3}$$

or

$$P_s = 0.80 * RSC * (8.337/D)$$

E = modulus of elasticity of the pipe material (psi) =

4.E+05 psi

I = moment of inertia of the pipe wall cross section per linear inch of pipe, $\text{inch}^4/\text{lineal inch} = \text{inch}^3$. For solid wall pipe, I can be calculated with equation 4. If the pipe used is not solid wall pipe (for example a pipe with a ribbed cross section), the proper moment of inertia formula must be obtained from the manufacturer.

$$\begin{aligned} \text{Shell Thickness, } t &= 0.113 \text{ in} \\ I = t^3/12 &= 0.0001 \text{ in}^3 \end{aligned}$$

D = mean pipe diameter (in)

2.149 inches

r = mean radius (in)

1.0745 inches

10 Report P_s for each pipe size and each type of flexible pipe material as determined in 9.

Pipe Diameter: 2 inches
 Pipe Material: PVC SDR 21
 P_s : 260 psi

11

Because the terms in the denominator of the modified Iowa formula (Equation 13) are added, it is theoretically possible to have zero pipe stiffness ($P_s=0$) and still predict flexible pipe deflections less than 5%. In order to ensure that the stiffness being provided to the installation has a reasonable contribution from pipe stiffness, and does not rely solely on the stiffness provided by the soil stiffness factor (SSF), the ratio of P_s/SSF must be calculated. If $P_s/\text{SSF} < 0.15$, 9 and 10 must be repeated such that a higher stiffness pipe is chosen for each portion of the project where $P_s/\text{SSF} < 0.15$. The P_s/SSF ratio(s) must then be recalculated for the new higher stiffness pipe. This process must be repeated until $P_s/\text{SSF} \geq 0.15$ exists for all proposed pipe sizes and for all types of flexible pipe materials.

P_s = Pipe stiffness (psi) [from 10]:

2" = 260 psi

E_b = modulus of soil reaction for the bedding material (psi) [from 5a] =

2" = 750 psi

zeta = 1.0, or a value calculated with the method in 7 =

2" = 1.0

SSF = soil stiffness factor ($0.061 * \text{zeta} * E_b$):

2" = 45.75

- 12 Indicate the final values calculated for P_s/SSF for each diameter of pipe and for each pipe material:

Pipe Diameter: 2 inches
 Pipe Material: PVC SDR 21
 P_s/SSF : 5.7

- 13 Do all proposed pipe sizes and flexible pipe materials have a pipe stiffness to soil stiffness factor ratio of greater than or equal to 0.15?

YES

- 14 Calculate and report predicted deflection. Predicted deflection must be calculated for each size of pipe and type of flexible pipe material. For the purposes of this application form, predicted deflection must be calculated using the method outlined below. Show calculations and report calculated maximum deflection for each size of pipe and type of flexible pipe material. Maximum allowable deflection in installed lines is 5%, as determined by the deflection analysis and verified by a mandrel test. Some conservatism should be employed in determining allowable predicted deflections. This conservatism is necessary to allow for variability in the quality of installation.

$$L_p = \frac{\gamma_s * H}{144}$$

D = Undeflected mean pipe diameter (in) 2.149 inches

K = Bedding angle constant. (Assumed to be 0.110 unless otherwise justified.) 0.110

γ_s = Unit weight of soil (pcf). γ_s less than 120 pcf must be justified. 120 pcf

H = Depth of burial (ft) from ground surface to crown of pipe. 6.1285 ft

L_p = Prism load (psi). If prism load is calculated using Marston's load formula, or other formulas less conservative than the one provided above, the load should be multiplied by a deflection lag factor $D_L = 1.5$ to account for long-term deflection of the pipe as the bedding consolidates.

2" = 5.1 psi

% $\Delta Y/D$ = Predicted % vertical deflection under load.
 Change in vertical pipe diameter under load
 = $(K*(L_p-L_i)*100)/(0.149Ps+(0.061*Zeta*E_b)) = 0.66 \%$

(P_s from 12; zeta from 10; and E_b from 5a)

- If the predicted % $\Delta Y/D$ for any proposed pipe size or material is over 5%, the proposed flexible pipe design cannot be approved by the TCEQ. Appropriate design modifications must be made and the analysis must be repeated until a deflection of less than or equal to 5% is predicted.

- If a zeta value of 1.0 was assumed as a result of 6, and the predicted deflection for any size or type of pipe is determined to be between 4% and 5%, the deflection analysis must be repeated. Repeat the deflection analysis by performing all the same calculations. The difference will be that instead of using an assumed zeta factor of 1.0, the zeta factor must be calculated as outlined in 7. If the predicted deflection is determined to be above 5% after the deflection analysis is repeated, this flexible pipe design cannot be approved by the TCEQ. Appropriate design modifications must be made and the analysis must be repeated until a deflection of less than or equal to 5% is predicted.

- If the predicted deflection, for a particular pipe, using the deflection analysis method detailed above, is less than or equal to 4%, and a zeta factor of 1.0 was assumed as a result of 6, that particular pipe is assumed to comply with the TCEQ's requirements for deflection analysis and can therefore be approved.

- If the predicted deflection, for a particular pipe, using the deflection analysis method detailed above, is between 4% and 5%, and the zeta factor which was used in the analysis was determined using the method in 7, that particular pipe is assumed to comply with the TCEQ's requirements for deflection analysis and can therefore be approved.

$$\Delta Y/D(\%) = 0.66 \%$$

- 15 Report the final pipe diameters, types of pipe material proposed for each diameter, type of pipe material, pipe stiffness for each pipe material (P_s), zeta factors assumed or calculated for each pipe diameter, modulus of the pipe bedding material (E_b) as well as the % deflection predicted for each pipe size and type of pipe material.

Type of Pipe Material

P_s (psi)	[from #10 above]	<u>PVC SDR 21</u> <u>260</u>	psi
Zeta Factor Assumed or Calculated	[from # 8 above]	<u>1.0</u>	
E_b (psi)	[from # 5a above]	<u>750</u>	psi
% Deflection	[from #14 above]	<u>0.66</u>	%

- 16 Do all pipes proposed for this project have a maximum predicted deflection of 5.0%?

YES

Lift Station/Force Main System Application

Texas Commission on Environmental Quality

for Regulated Activities On the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c)(3)(B)and(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Moore Estates Subd Improvements

Customer Information

(If different than customer information provided on core data form)

1. The person(s) responsible for providing the engineering certification to the TCEQ pursuant to 30 TAC §213.5(f)(2)(C) during construction and 30 TAC §213.5 (c)(3)(D) upon completion of construction is:

Contact Person: Michael Tirres

Entity: Tirres Group, LLC

Mailing Address: 3507 Native Dancer Cove

City, State: Austin, Texas

Zip: 78746-1434

Telephone: 512-422-2880

Fax: N/A

Email Address: michael@tirreshomes.com

2. The engineer responsible for the design of this lift station and force main:

Contact Person: Robert Thompson

Entity: Thompson Land Engineering, LLC

Mailing Address: 904 N Cuernavaca Drive

City, State: Austin, Texas

Zip: 78733

Telephone: 512-328-0002

Fax: 512-328-1112

Email Address: ric@tleng.net

Texas Licensed Professional Engineer's Serial Number: F-10220

Project Information

3. This project is for the construction or replacement of:

☐ Lift Station only.

Note: Force main only for this Subdivision.
A Lift station will be provided (with either a new or a modified WPAP), when a home is proposed for construction.

- ☒ Lift Station and Force Main system.
☐ Lift Station, Force Main, and Gravity system.

4. The sewage collection system will convey the wastewater to the South Austin Regional (SAR) (name) Treatment Plant. The treatment facility is:

- ☒ Existing
☐ Proposed

5. All components of this lift station/force main system will comply with:

- ☒ The City of West Lake Hills standard specifications.
☐ Other. Specifications are attached.

Site Plan Requirements

Items 6-14 must be included on the Site Plan.

6. ☒ The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = 40'.
7. ☒ Lift station/force main system layout meets all requirements of 30 TAC Chapter 217.

8. Geologic or Manmade Features:

- ☐ No geologic or manmade features were identified in the Geologic Assessment.
☐ All geologic or manmade features identified in the Geologic Assessment (caves, solution openings, sinkholes, fractures, joints, porous zones, etc.) which exist at the site of the proposed lift station and along the path(s) or within **50 feet of each side** of a proposed force main line are shown on the Site Plan and are listed in the table below. Designs used to protect the integrity of the sewer line crossing each feature are described and labeled on the attached page. A detailed design drawing for each feature is shown on Plan Sheet _____ of _____.
☒ No Geologic Assessment is required for this project.

Table 1 - Geologic or Manmade Features

<i>Line</i>	<i>Station to Station</i>	<i>Type of Feature</i>
	to	
	to	
	to	
	to	
	to	
	to	
	to	
	to	

9. ☒ Existing topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
10. ☒ Finished topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
- ☒ Finished topographic contours will not differ from the existing topographic configuration and are not shown.

11. 100-year floodplain boundaries

- ☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☒ No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA FIRM Map Number 48453C0445K, effective date: Jan. 22, 2020

12. 5-year floodplain:

- ☒ After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above sewer lines.)
- ☐ After construction is complete, all sections of the force main located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 2 - 5-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station to Station</i>
	of	to
	of	to
	of	to
	of	to

13. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

If applicable, this must agree with Item No. 15 on the Geologic Assessment Form.

- ☐ There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)
- ☐ The wells are not in use and have been properly plugged.
- ☐ The wells are not in use and will be properly plugged.
- ☐ The wells are in use and comply with 16 TAC Chapter 76.

☒ There are no wells or test holes of any kind known to exist on the project site.

14. ☒ Legal boundaries of the site are shown.

Plan and Profile Sheets

The construction drawings and technical specifications will not be considered for review unless they are the **final plans and technical specifications** which will be used by the contractor for bidding and construction.

Items 15 – 18 must be included on the Plan and Profile sheets.

15. ☐ The equipment installation construction plans must have a minimum scale of 1" = 10'.
Plan sheet scale: 1" = 20 '.
16. ☒ Locations, descriptions and elevations of all required equipment and piping for the lift station and force main are shown and labeled.
17. ☐ Air Release/Vacuum Valves will be provided at all peaks in elevation of the proposed force main. These locations are listed in the table below and labeled on the appropriate plan and profile sheets.

Table 3 - Air Release/Vacuum Valves

<i>Line</i>	<i>Station</i>	<i>Sheet</i>
		of
		of
		of
		of
		of
		of

18. ☒ The **final plans and technical specifications** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
19. ☒ **Attachment A - Engineering Design Report.** An engineering design report with the following required items is attached:
- ☒ The report is dated, signed, and sealed by a Texas Licensed Professional Engineer.
 - ☒ Calculations for sizing system.
 - ☐ Pump head calculations, including, but not limited to, system head and pump capacity curves, head loss calculations, and minimum and maximum static head C values for normal and peak operational conditions.
 - ☐ 100-year and 25-year flood considerations.
 - ☐ Total lift station pumping capacity with the largest pump out of service.
 - ☐ Type of pumps, including standby units.
 - ☐ Type of pump controllers, including standby air supply for bubbler controllers, as applicable.

- ☐ Pump cycle time.
- ☐ Type of wet well ventilation; include number of air changes for mechanical ventilation.
- ☒ Minimum and maximum flow velocities for the force main.
- ☐ Lift station security.
- ☐ Lift station emergency provisions and reliability.

Administrative Information

20. ☐ Upon completion of the wet well excavation, a geologist must certify that the excavation was inspected for the presence of sensitive features and submit the signed, sealed, and dated certification to the appropriate regional office.
21. ☒ The TCEQ Lift Stations and Force Mains General Construction Notes (TCEQ-0591) are included on the General Notes Sheet of the Final Construction Plans for this lift station and/or force main system.
22. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
23. ☒ Any modification of this lift station/force main system application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Lift Station/Force Main System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c)(3)(C) and 30 TAC Chapter 217, and prepared by:

Print Name of Licensed Professional Engineer: Robert Thompson

Place engineer's seal here:

Date: July 18, 2025

Signature of Licensed Professional Engineer:

Robert C. Thompson 08/07/25



Thompson Land
Engineering, LLC
(F-10220)

Robert C. Thompson



THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering

FORCE MAIN ENGINEERING DESIGN REPORT

for:

Moore Estates Subd Improvements

To be located at:

803 Westlake Drive
West Lake Hills, Texas 78746


Prepared By:

Thompson Land Engineering, LLC

Robert C. Thompson, P.E.
904 N. Cuernavaca
Austin, Texas 78733
512-328-0002
512-328-1112 (fax)

Preparation Date

July 18, 2025



Thompson Land
Engineering, LLC
(F-10220)

August 5, 2025

Force Main Engineering Design Report

Calculations (for sizing the force main)

The force main was sized using the City of Austin's Utility Criteria Manual (section 2.9.4) with the minimum size being two (2) inches. Additionally, the size was set to match the existing line to which this connects.

Minimum and Maximum flow velocities (for the force main)

The force main is intended to operate with a minimum pump rate of 20-gpm that would yield a velocity of 2.0-fps. The likelihood of multiple homes pumping at the same time is remote but should half the homes (3 total) all pump at the same time, that total rate would be 60-gpm, yielding a velocity of 6.1-fps.

Therefore, reaching the flushing velocity of 5-fps is expected to be difficult, but the situation exists in the line to which this force main will connect (and is also the result of Austin's policy not allowing smaller force mains). Should a velocity of 6.1-fps be experienced, the pipe is understood to be able to withstand the surge pressures as shown in the calculations.

Detention Time

The force main detention time calculations are included in this report, which are performed using a range of flow rates (that represent the flow expected to be delivered to a force main by an upstream pump station during any 24-hour period).

Water Hammer

The water hammer surge pressure was computed to be 31-psi and the pipe is rated for a maximum pressure of 200-psi, therefore, we are computing a factor of safety of over 6. See the following pages for the force main calculations.

Connection to Gravity Main

This project is not proposing for any force main terminations at a collection system manhole or at a manhole or preliminary treatment unit at a wastewater treatment facility, rather, this force main will terminate at an existing force main (and will be an extension of that force main). The existing collection system that would be receiving wastewater from this force main is understood (from the City of West Lake Hill's preliminary approval) to be designed to accept the maximum pump discharge from the force main without surcharging.

Pipe Separation

A separation distance between a force main and any water supply pipe meets the minimum separation requirements established in TAC §217.53(d), relating to Pipe Design.

Odor Control

The force main being proposed is closed and pressure rated with check valves at the ends; therefore, no odor is known to escape this system. When grinder pumps are added (that will be permitted with either a modified or a new SCS application), further control will be addressed at that time.

Air Release Valves in Force Mains

At the single high point along the vertical force main alignment, a combination of air release and air vacuum valves is included. The air release valve will have an isolation valve (between the air release valve and the force main). Additionally, the air release valve will be inside of a vault (that is at least 48 inches in diameter and has a vented access opening of at least 30 inches in diameter). The air release valve will be made of corrosion-resistant material.

Valves

This force main will have valves that are spaced at no more than 2,000-foot intervals (to facilitate initial testing and subsequent maintenance and repairs).

Fatigue Life

The calculations that show the strength of the force main pipe at the end of the 50-year design life are included in this report.

Alignment Changes

No pipe bending is proposed; only 1-degree joint deflections (or the use of manufactured bends) are proposed to adjust the vertical and horizontal alignment.

Maintenance, Inspection, and Rehabilitation of the Collection System

The owner of a collection system is to develop a maintenance and inspection program for its collection system with the assistance of an engineer and licensed operators. The owner is responsible for ensuring that the maintenance and inspection program includes all the information pertaining to inspection, maintenance, and rehabilitation of the collection system necessary to ensure efficient, safe, and environmentally compliant operation. The owner is also responsible for ensuring that all records pertaining to maintenance, inspection, and rehabilitation activities are maintained by the licensed collection system operators.

The inspection program, at a minimum, will include:

- (1) a schedule for inspections, cleaning, and maintenance;
- (2) methods for inspecting, cleaning, and maintaining each unit within the collection system;
- (3) methods for estimating the current condition and life expectancy of each unit; and
- (4) a requirement to estimate the structural integrity of each collection system unit.

The plans and specifications for a rehabilitation project must include, at a minimum:

- (1) a surface preparation plan that includes:
 - (A) a cleaning plan to remove all contaminants;
 - (B) references for the cleaning method;
 - (C) dewatering or bypassing provisions; and
 - (D) field preparation and application logs;
- (2) a plan for managing volatile chemicals and dust in confined spaces;
- (3) a requirement to follow the manufacturer's installation procedures and specifications;
- (4) a requirement to re-inspect the rehabilitation project, including the underlayment and coating, between six months and 11 months after installation; and
- (5) a requirement to re-inspect the rehabilitation project, including the underlayment and coating, 18 months after installation.

The owner must maintain records of all activities related to collection system inspection, maintenance, cleaning, and rehabilitation. The records must be made available to the executive director upon request according to the requirements of §217.18 of this title (relating to provisions that apply to all sections in this chapter).

Force Main Calculations
(Based on UCM 2.9.4)

GIVENS:

- General Data

1 ac, Drainage Area (DA) to Lift Station (for infiltration) *(Assumed; cut off by road & groundwater going under)*
 SF Use (SF, MF, Off/Ware, Retail)
 if Off/Ware or Retail
 N/A Floor Area (sf)
 if SF or MF
 1 Units *(Checking least flow version (one house))*

- Elevation Data

703.00 Pump Discharge Flowline *(approximate for house on Lot 1)*
 693.08 Forcemain Discharge Flowline (Ed) *(see plans)*
 709.76 High Point (on public) *(see plans)*
 691.59 Low Point (on public) *(see plans)*

- Pipe Data

Type "A": PVC, ASTM D2241, SDR-PR, SDR 21(200)
 2 in, Size "A" (Force Main diameter)
 400,000 psi, E (Young's Modulus)
 0.09 in, "A" Pipe Wall Thickness (t)
 1,022 ft, Length "A" *(382 public and 640 private)*

- Pump Data

20 gpm, Pump Rate *(Pump Rate to get 2 fps)*
 0.045 cfs, Pump Rate
 65 gal, Pump on Volume (Von)
 49 gal, Pump off Volume (Voff)

COMPUTATIONS

1) Peaking Factors

$$PF(\max) = [18 + (\text{pop}/1,000)^{0.5}] / [4 + (\text{pop}/1,000)^{0.5}]$$

and

$$PF(\min) = 0.2 * (\text{pop}/1,000)^{0.198}$$

where:

$$\text{pop} = 3.50$$

therefore:

$$PF(\max) = 4.45$$

$$PF(\min) = 0.07$$

2) Flow Rates

a) Avg Dry Weather Flow (Qd)

where:

$$SF = \text{Use}$$

$$1 = \text{Units or Floor Area (as applicable)}$$

therefore:

$$Qd = 350 \text{ gpd}$$

b) Equivalent Population (pop)

$$\text{pop} = Q_d / (100 \text{ gal/cap/day})$$

therefore:

$$\text{pop} = 3.5$$

c) Infiltration (Q_i)

$$Q_i = 1,500 \text{ gpd/ac} * DA$$

where:

$$DA = 1 \text{ ac}$$

therefore:

$$Q_i = 1,500 \text{ gpd}$$

d) Max Wet Weather Flow ($Q_w(\text{max})$)

$$Q_w(\text{max}) = \text{pop} * 100 \text{ ppcd} * PF(\text{max}) + Q_i$$

where:

$$\text{pop} = 3.50$$

$$PF(\text{max}) = 4.45$$

$$Q_i = 1,500 \text{ gpd}$$

therefore:

$$\begin{array}{ll} Q_w(\text{max}) & 3,057 \text{ gpd} \\ \text{or} & 2.1 \text{ gpm} \end{array}$$

e) Max Dry Weather Flow ($Q_d(\text{max})$)

$$Q_d(\text{max}) = \text{pop} * 100 \text{ ppcd} * PF(\text{max})$$

where:

$$\text{pop} = 3.50$$

$$PF(\text{max}) = 4.45$$

therefore:

$$Q_d(\text{max}) = 1,557 \text{ gpd}$$

f) Min Dry Weather Flow ($Q_d(\text{min})$)

$$Q_d(\text{min}) = \text{pop} * 100 \text{ ppcd} * PF(\text{min})$$

where:

$$\text{pop} = 3.50$$

$$PF(\text{min}) = 0.07$$

therefore:

$$Q_d(\text{min}) = 23 \text{ gpd}$$

3) Force Main Velocities

$$V = P / (3.1415 * d^2 / 4)$$

where:

$$P = 0.045 \text{ cfs}$$

$$d = 2 \text{ in (Line A)}$$

therefore:

$V = 2.0 \text{ fps (Line A)}$

4) Water Hammer

a) pressure wave velocity (a)

$$a = 12 / [(1.9379 * (1/300,000 + d/(E * t)))]$$

where:

$$d = 2 \text{ in (Line A)}$$

$$E = 400,000 \text{ psi}$$

$$t = 0.09 \text{ in (Line A)}$$

therefore:

$$1123 \text{ fps (Line A)}$$

b) Surge Pressure (Ps)

$$Ps = a * V / 74.382$$

therefore:

$$30.8 \text{ psi (Line A)}$$

5) Total Head

a) Elevation Head (He)

$$He = Ed - Es$$

where:

$$Ed = 693.08 \text{ (Forcemain Discharge Elevation)}$$

$$Ed = 709.76 \text{ Highest FM elevation}$$

$$Es = 703.00 \text{ Lowest Pump Discharge Elev (Estimated)}$$

therefore:

$$He = 6.76 \text{ ft}$$

b) Friction Loss (f)

$$f = (V^{1.85} * L) / [(1.318 * 150)^{1.85} * (d/4/12)^{1.17}]$$

where:

$$V = 2.0 \text{ fps (Line A)}$$

$$L = 1022 \text{ ft (Line A)}$$

$$d = 2 \text{ in (Line A)}$$

therefore:

$$f = 8.92 \text{ ft (Line A)}$$

c) Total Head (H)

Note: ignoring minor losses in fittings, entrance, exit

$$H = He + F(a)$$

therefore:

$$15.68 \text{ ft}$$

or:

$$6.80 \text{ psi}$$

d) Velocity Head (Hv)

$$Hv = V^2 / (2 * 32.2)$$

$$Hv = 0.06 \text{ ft (Line A)}$$

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Robert C. Thompson

Date: July 10, 2025

Signature of Customer/Agent:



Regulated Entity Name: Moore Estates Subd Improvements

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

- ☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Little Bee Creek

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
 - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
 - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
 - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- ☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- ☒ N/A
12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A – SPILL RESPONSE ACTIONS

The spill response actions will be in accordance with the current TCEQ RG348:

1.4.16 Spill Prevention and Control

The objective of this section is to describe measures to prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees.

The following steps will help reduce the stormwater impacts of leaks and spills:

Education

(1) Be aware that different materials pollute in different amounts. Make sure that each employee knows what a “significant spill” is for each material they use, and what is the appropriate response for “significant” and “insignificant” spills. Employees should also be aware of when the spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.

(2) Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.

(3) Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).

(4) Establish a continuing education program to indoctrinate new employees.

(5) Have contractor’s superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

(1) To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.

(2) Store hazardous materials and waste in covered containers and protect from vandalism.

- (3) Place a stockpile of spill cleanup materials where it will be readily accessible.
- (4) Train employees in spill prevention and cleanup.
- (5) Designate responsible individuals to oversee and enforce control measures.
- (6) Spills should be covered and protected from stormwater runoff during rainfall to the extent that it does not compromise cleanup activities.
- (7) Do not bury or wash spills with water.
- (8) Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- (9) Do not allow water used for cleaning and decontamination to enter storm drains or water courses. Collect and dispose of contaminated water in accordance with applicable regulations.
- (10) Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- (11) Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- (12) Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

Cleanup

- (1) Clean up leaks and spills immediately.
- (2) Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spilled material is hazardous, then

the used cleanup materials are also hazardous and must be disposed of as hazardous waste.

(3) Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of it properly. See the waste management BMPs in this Section for specific information.

Minor Spills

(1) Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.

(2) Use absorbent materials on small spills rather than hosing down or burying the spill.

(3) Absorbent materials should be promptly removed and disposed of properly.

(4) Follow the practice below for a minor spill:

(5) Contain the spread of the spill.

(6) Recover spilled materials.

(7) Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities.

Spills should be cleaned up immediately:

(1) Contain spread of the spill.

(2) Notify the project foreman immediately.

(3) If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.

- (4) If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- (5) If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

(1) Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.

(2) For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.

(3) Notification should first be made by telephone and followed up with a written report.

(4) The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staff have arrived at the job site.

(5) Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc. More information on spill rules and appropriate responses is available on the TCEQ website at:

http://www.tnrcc.state.tx.us/enforcement/emergency_response.html

ATTACHMENT B – POTENTIAL SOURCES OF CONTAMINATION

The only “pollutants” expected from the work during construction are sediment. Mostly inert materials (i.e. pipe, wood, drywall, concrete, etc.) will be stored or installed on the site. No off-site fill material is expected to be brought onto the site (other than crushed limestone base, asphalt and concrete). No significant chemicals are planned to be stored or distributed on the site. A portable toilet might be on the site during construction, but no spill is expected from maintaining this toilet. Re-fueling of vehicles is the only other perceived threat, but short of an accidental spill, no threat should be posed. The other possible “pollutants” expected after the construction is complete are pesticides, fertilizers, automotive fluids, and air conditioning condensate.

ATTACHMENT C – SEQUENCE OF MAJOR ACTIVITIES

- | | | |
|---|---|---|
| - | Install erosion controls:
Control measure: Silt Fence | less than 0.05-acres
approximately 1-week |
| - | Clear, grub, and rough grade site
(for the paving):
Control measure: Silt Fence | approximately 0.8-acres
approximately 2-weeks |
| - | Install water & WW utilities:
Control measure: Silt Fence & Tri. Filter Dykes | less than 1.0-acres
approximately 6-weeks |
| - | Construct Driveway:
Control measure: Silt Fence & Tri. Filter Dykes | less than 0.8-acres
approximately 3-weeks |
| - | Install water quality facilities (VFS):
Control measure: Silt Fence | approximately 0.25-acres
approximately 1-weeks |

ATTACHMENT D – TEMPORARY BEST MANAGEMENT PRACTICES (TBMPs)

Silt fence (SF) and triangular filter dikes (TFDs) will be strategically placed to capture the offsite and onsite flows and to prevent any sediment and possible pollutants from leaving the site. No runoff should be able to leave the site

without first being filtered by these temporary controls. Additionally, a stabilized construction entrance (SCE) will be used to prevent the dirt on the wheels of vehicles that leave the site. Inside the property, a concrete washout control is proposed (with SF surrounding it), as shown on the plans, which will be adjacent to the proposed construction staging area.

Any pollutants are expected to be either soil or attached to soil (unless it is trash which will float) and with the silt fence described, that soil (or any floating trash) is expected to be caught and held until removal. Notes are included on the plans (on **sheet 3**), in relation to the Storm Water Pollution Prevention Plan (SW3P) that specify the minimum maintenance required for silt fence, including cleaning of soil and debris. Run-off will still be released after either filtering through the silt fence or infiltrating through the soil.

ATTACHMENT E – REQUEST TO TEMPORARILY SEAL A FEATURE

This is not applicable for this project.

ATTACHMENT F – STRUCTURAL PRACTICES

The SF and TFDs will be located throughout the site to limit runoff discharge of pollutants from exposed areas of the site. (See the discussion under Temporary BMPs and Measures above.)

ATTACHMENT G – DRAINAGE AREA MAP

See sheet 12 (of 16 from the Construction Plan set = *Attachment F* of the *Permanent Stormwater Section*) for the drainage areas and flow patterns.

ATTACHMENT H – TEMPORARY SEDIMENT POND(S) PLAN & CALCS

This is not applicable for this project.

ATTACHMENT I – INSPECTION AND MAINTENANCE FOR BMPs

See the Storm Water Pollution Prevention (SW3P) notes on **sheet 3** and the details (for the stabilized construction entrance, silt fence, etc.) on **sheet 5** in the construction plan set for the inspection plan of each of these temporary BMPs

and measures. Additionally, see the following pages for the attached copies of the maintenance schedule (to be kept onsite during construction), as well as the information taken directly from the TCEQ's Technical Guidance, in addition to the approved construction plan sheets for the storm water pollution prevention plan (SWPPP) notes on the General Notes sheet and the Erosion and Sedimentation Controls (ESC) details (stabilized construction entrance, silt fence and concrete washout area) for the inspection plan of each of these temporary BMPs and measures.

ATTACHMENT J – SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

If portions of the site will have a temporary or permanent cease in construction activity lasting longer than 14 days, soil stabilization in those areas shall be initiated as soon as possible prior to the 14th day of inactivity. If activity resumes prior to the 21st day, stabilization measures are not required. If drought conditions or inclement weather prevent action by the 14th day, stabilization measures shall be initiated as soon as possible.

The work at this site is relatively small, will happen quickly, and will occur in one phase. The time from the beginning of grading to stabilization is not expected to be more than 9-months; therefore, there is no particular schedule, other than to complete construction as quickly as possible and then to re-vegetate the site as quickly as possible, in accordance with the re-vegetation notes on the construction plans, which are copied below (and on the following page):

PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS NOTED BELOW:

- A. UNLESS DIRECTED OTHERWISE BY THE OWNER, A MINIMUM OF FOUR INCHES OF TOPSOIL SHALL BE PLACED IN ALL DRAINAGE CHANNELS (EXCEPT ROCK) AND 1-INCH OF TOPSOIL IN OTHER AREAS.
- B. THE SEEDING FOR PERMANENT EROSION CONTROL SHALL BE APPLIED OVER AREAS DISTURBED BY CONSTRUCTION AS FOLLOWS:

BROADCAST SEEDING:

1. FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH A COMBINATION OF 2 POUNDS PER 1000-SF OF UNHULLED BERMUDA AND 7 POUNDS PER 1000 SF OF WINTER RYE WITH A PURITY OF 95% WITH 90% GERMINATION.
2. FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 2 POUNDS PER 1000 SF WITH A PURITY OF 95% WITH 85% GERMINATION.
3. OTHER REQUIREMENTS:
 - A. FERTILIZER SHALL BE A PELLETTED OR GRANULAR SLOW RELEASE WITH AN ANALYSIS OF 15-15-15 TO BE APPLIED ONCE AT PLANTING AND ONCE DURING THE PERIOD OF ESTABLISHMENT AT A RATE OF 1 POUND PER 1000-SF.
 - B. MULCH TYPE USED SHALL BE HAY, STRAW OR MULCH APPLIED AT A RATE OF 45 POUNDS PER 1000-SF.

HYDRAULIC SEEDING:

1. FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH A COMBINATION OF 1 POUND PER 1000-SF OF UNHULLED BERMUDA AND 7 POUNDS PER 1000-SF OF WINTER RYE WITH A PURITY OF 95% WITH 90% GERMINATION.
2. FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED BERMUDA AT A RATE OF 1 POUND PER 1000 SF WITH A PURITY OF 95% WITH 85% GERMINATION.
3. OTHER REQUIREMENTS:
 - A. FERTILIZER SHALL BE A WATER-SOLUBLE FERTILIZER WITH AN ANALYSIS OF 15-15-15 AT A RATE OF 1.5 POUNDS PER 1000 SF.
 - B. MULCH TYPE USED SHALL BE HAY, STRAW OR MULCH APPLIED AT A RATE OF 45 POUNDS PER 1000 SF, WITH SOIL TACKIFIER AT A RATE OF 1.4 POUNDS PER 1000 SF.
 - C. THE PLANTED AREA SHALL BE IRRIGATED OR SPRINKLED IN A MANNER THAT WILL NOT ERODE THE TOPSOIL, BUT WILL SUFFICIENTLY SOAK THE SOIL TO A DEPTH OF SIX INCHES. THE IRRIGATION SHALL OCCUR AT TEN-DAY INTERVALS DURING THE FIRST TWO MONTHS. RAINFALL OCCURRENCES OF « INCH OR MORE SHALL POSTPONE THE WATERING SCHEDULE FOR ONE WEEK.
 - D. RESTORATION SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1« INCHES HIGH WITH 95% COVERAGE, PROVIDED NO BARE SPOTS LARGER THAN 16 SQUARE FEET EXIST.

Inspection & Maintenance (Attachment I continuation)

Project Name: Moore Estates Subd Improvements

SWPPP Contact: _____

BEST MANAGEMENT PRACTICE INSPECTION AND MAINTENANCE REPORT FORM

SILT FENCE

Name of Inspector: _____

Inspection Date: _____

Days Since Last Rainfall: _____

Amount of Last Rainfall: _____ inches

Where is the Silt Fence Located?	Is the Bottom of the Fabric Still Buried?	Is the Fabric Torn or Sagging?	Are the Posts Tipping Over?	How Deep is the Sediment?

MAINTENANCE REQUIRED FOR SILT FENCE: _____

TO BE PERFORMED BY: _____

ON OR BEFORE: _____

Project Name: Moore Estates Subd Improvements

SWPPP Contact: _____

**BEST MANAGEMENT PRACTICE
INSPECTION AND MAINTENANCE REPORT FORM**

STABILIZED CONSTRUCTION ENTRANCE

Name of Inspector: _____

Inspection Date: _____

Days Since Last Rainfall: _____

Amount of Last Rainfall: _____ inches

Location	Is Sediment Being Tracked onto Road?	Is the Entry Surface Clean or Sediment Filled?	Does All Traffic Use the Entrance?

MAINTENANCE REQUIRED FOR STABILIZED CONSTRUCTION ENTRANCES: _____

TO BE PERFORMED BY: _____

ON OR BEFORE: _____

Project Name: Moore Estates Subd Improvements

SWPPP Contact: _____

**BEST MANAGEMENT PRACTICE
INSPECTION AND MAINTENANCE REPORT FORM**
(Completed weekly or as soon as possible after a significant storm event)

Name of Inspector: _____

Inspection Date: _____

Days Since Last Rainfall: _____

Amount of Last Rainfall: _____

STABILIZATION MEASURES					
Area or Drainage Areas*	Date Since Last Disturbance	Date of Next Disturbance	Stabilized (Yes or No)	Control Measures Implemented	Current Conditions of Control Measures

* See site map for drainage areas. Site may include borrow sources, haul roads, contractor's yard, stockpiles, etc.

** Areas that will be exposed more than 21 days must be stabilized within 14 days

STABILIZATION REQUIRED: _____

TO BE PERFORMED BY: _____ **ON OR BEFORE:** _____

Control Measure Codes		Condition Codes
1. Temporary Seeding	14. Rock Bed at Construction Exit	U – Upgrade Needed
2. Permanent Plant, Sod, or Seed	15. Timber Mat at Construction Entrance	R – Replacement Needed
3. Mulch	16. Channel Liner	M – Maintenance Needed
4. Soil Retention Blanket	17. Sediment Trap	C – Cleaning Needed
5. Buffer Zone	18. Sediment Basin	I – Increase Measures
6. Preserve Natural Resources	19. Storm Inlet Sediment Trap	S – Stable (no action required)
7. Silt Fence	20. Stone Outlet Structure	
8. Hay Bales	21. Curb and Gutter	
9. Rock Berm	22. Storm Sewers	
10. Diversion Dike	23. Velocity Control Devices	
11. Diversion Swale	24. Excess Dirt Removed From Road	
12. Pipe Slope Drain	25. Haul Roads Dampened for Dust	
13. Paved Flume	26. Cleanup of Possible Contaminants	

Project Name: Moore Estates Subd Improvements

SWPPP Contact: _____

**BEST MANAGEMENT PRACTICE
INSPECTION AND MAINTENANCE REPORT FORM**

CONSTRUCTION ACTIVITIES LOG

Name of Inspector	Date	Major Grading Activities	Temporary Suspension of Construction Activities	Permanent Suspension of Construction Activities	Initiation of Stabilization Measures	Comments

Date	Additional Changes

Corrective Action Log

Project Name: Moore Estates Subd Improvements

SWPPP Contact: _____

Inspection Date	Inspector Name(s)	Description of BMP Deficiency	Corrective Action Needed (including planned date/responsible person)	Date Action Taken/Responsible person

1.4.2 Temporary Construction Entrance/Exit

The purpose of a temporary gravel construction entrance is to provide a stable entrance/exit condition from the construction site and keep mud and sediment off public roads. A stabilized construction entrance is a stabilized pad of crushed stone located at any point traffic will be entering or leaving the construction site from a public right-of-way, street, alley, sidewalk or parking area. The purpose of a stabilized construction entrance is to reduce or eliminate the tracking or flowing of sediment onto public rights-of-way. This practice should be used at all points of construction ingress and egress. Schematic diagrams of a construction entrance/exit are shown in Figure 1-24 and Figure 1-25.

Excessive amounts of mud can also present a safety hazard to roadway users. To minimize the amount of sediment loss to nearby roads, access to the construction site should be limited to as few points as possible and vegetation around the perimeter should be protected where access is not necessary. A rock stabilized construction entrance should be used at all designated access points.




Figure 1-24 Schematic of Temporary Construction Entrance/Exit (after NC, 1993)




Figure 1-25 Cross-section of a Construction Entrance/Exit (NC, 1993)

Materials:

- (1) The aggregate should consist of 4 to 8 inch washed stone over a stable foundation as specified in the plan.
- (2) The aggregate should be placed with a minimum thickness of 8 inches.
- (3) The geotextile fabric should be designed specifically for use as a soil filtration media with an approximate weight of 6 oz/yd², a mullen burst rating of 140 lb/in², and an equivalent opening size greater than a number 50 sieve.
- (4) If a washing facility is required, a level area with a minimum of 4 inch diameter washed stone or commercial rack should be included in the plans. Divert wastewater to a sediment trap or basin.

Installation: (North Carolina, 1993)

- (1) Avoid curves on public roads and steep slopes. Remove vegetation and other objectionable material from the foundation area. Grade crown foundation for positive drainage.
- (2) The minimum width of the entrance/exit should be 12 feet or the full width of exit roadway, whichever is greater.
- (3) The construction entrance should be at least 50 feet long.
- (4) If the slope toward the road exceeds 2%, construct a ridge, 6 to 8 inches high with 3:1 (H:V) side slopes, across the foundation approximately 15 feet from the entrance to divert runoff away from the public road.
- (5) Place geotextile fabric and grade foundation to improve stability, especially where wet conditions are anticipated.
- (6) Place stone to dimensions and grade shown on plans. Leave surface smooth and slope for drainage.
- (7) Divert all surface runoff and drainage from the stone pad to a sediment trap or basin.
- (8) Install pipe under pad as needed to maintain proper public road drainage.

Common trouble points

- (1) Inadequate runoff control – sediment washes onto public road.
- (2) Stone too small or geotextile fabric absent, results in muddy condition as stone is pressed into soil.
- (3) Pad too short for heavy construction traffic – extend pad beyond the minimum 50 foot length as necessary.
- (4) Pad not flared sufficiently at road surface, results in mud being tracked on to road and possible damage to road edge.
- (5) Unstable foundation – use geotextile fabric under pad and/or improve foundation drainage.

Inspection and Maintenance Guidelines:

- (1) The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public rights-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or cleanout of any measures used to trap sediment.
- (2) All sediment spilled, dropped, washed or tracked onto public rights-of-way should be removed immediately by contractor.
- (3) When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-way.
- (4) When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
- (5) All sediment should be prevented from entering any storm drain, ditch or water course by using approved methods.

1.4.3 Silt Fence

A silt fence is a barrier consisting of geotextile fabric supported by metal posts to prevent soil and sediment loss from a site. When properly used, silt fences can be highly effective at controlling sediment from disturbed areas. They cause runoff to pond, allowing heavier solids to settle out. If not properly installed, silt fences are not likely to be effective. A schematic illustration of a silt fence is shown in Figure 1-26.




Figure 1-26 Schematic of a Silt Fence Installation (NCTCOG, 1993b)

The purpose of a silt fence is to intercept and detain water-borne sediment from unprotected areas of a limited extent. Silt fence is used during the period of construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This fence should remain in place until the disturbed area is permanently stabilized. Silt fence should not be used where there is a concentration of water in a channel or drainage way. If concentrated flow occurs after installation, corrective action must be taken such as placing a rock berm in the areas of concentrated flow.

Silt fencing within the site may be temporarily moved during the day to allow construction activity provided it is replaced and properly anchored to the ground at the end of the day. Silt fences on the perimeter of the site or around drainage ways should not be moved at any time.

Materials:

- (1) Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in², ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- (2) Fence posts should be made of hot rolled steel, at least 4 feet long with Tee or Y-bar cross section, surface painted or galvanized, minimum nominal weight 1.25 lb/ft², and Brindell hardness exceeding 140.
- (3) Woven wire backing to support the fabric should be galvanized 2" x 4" welded wire, 12 gauge minimum.

Installation:

- (1) Steel posts, which support the silt fence, should be installed on a slight angle toward the anticipated runoff source. Post must be embedded a minimum of 1-foot deep and spaced not more than 8 feet on center. Where water concentrates, the maximum spacing should be 6 feet.
- (2) Lay out fencing down-slope of disturbed area, following the contour as closely as possible. The fence should be sited so that the maximum drainage area is ¼ acre/100 feet of fence.
- (3) The toe of the silt fence should be trenched in with a spade or mechanical trencher, so that the down-slope face of the trench is flat and perpendicular to the line of flow. Where fence cannot be trenched in (e.g., pavement or rock outcrop), weight fabric flap with 3 inches of pea gravel on uphill side to prevent flow from seeping under fence.
- (4) The trench must be a minimum of 6 inches deep and 6 inches wide to allow for the silt fence fabric to be laid in the ground and backfilled with compacted material.
- (5) Silt fence should be securely fastened to each steel support post or to woven wire, which is in turn attached to the steel fence post. There should be a 3-foot overlap, securely fastened where ends of fabric meet.

- (6) Silt fence should be removed when the site is completely stabilized so as not to block or impede storm flow or drainage.

Common Trouble Points:

- (1) Fence not installed along the contour causing water to concentrate and flow over the fence.
- (2) Fabric not seated securely to ground (runoff passing under fence)
- (3) Fence not installed perpendicular to flow line (runoff escaping around sides)
- (4) Fence treating too large an area, or excessive channel flow (runoff overtops or collapses fence)

Inspection and Maintenance Guidelines:

- (1) Inspect all fencing weekly, and after any rainfall.
- (2) Remove sediment when buildup reaches 6 inches.
- (3) Replace any torn fabric or install a second line of fencing parallel to the torn section.
- (4) Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
- (5) When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

1.4.4 Triangular Sediment Filter Dikes

The purpose of a triangular sediment filter dike (Figure 1-27) is to intercept and detain water-borne sediment from unprotected areas of limited extent. The triangular sediment filter dike is used where there is no concentration of water in a channel or other drainage way above the barrier and the contributing drainage area is less than one acre. If the uphill slope above the dike exceeds 10%, the length of the slope above the dike should be less than 50 feet. If concentrated flow occurs after installation, corrective action should be taken such as placing rock berm in the areas of concentrated flow.

This measure is effective on paved areas where installation of silt fence is not possible or where vehicle access must be maintained. The advantage of these controls is the ease with which they can be moved to allow vehicle traffic, then reinstalled to maintain sediment control.


Materials:

- (1) Silt fence material should be polypropylene, polyethylene or polyamide woven or nonwoven fabric. The fabric width should be 36 inches, with a minimum unit weight of 4.5 oz/yd, mullen burst strength exceeding 190 lb/in², ultraviolet stability exceeding 70%, and minimum apparent opening size of U.S. Sieve No. 30.
- (2) The dike structure should be 6 gauge 6" x 6" wire mesh folded into triangular form being eighteen (18) inches on each side.

Installation:

- (1) As shown in the diagram (Figure 1-27), the frame should be constructed of 6" x 6", 6 gauge welded wire mesh, 18 inches per side, and wrapped with geotextile fabric the same composition as that used for silt fences.
- (2) Filter fabric should lap over ends six (6) inches to cover dike to dike junction; each junction should be secured by shoat rings.
- (3) Position dike parallel to the contours, with the end of each section closely abutting the adjacent sections.
- (4) There are several options for fastening the filter dike to the ground as shown in Figure 1-27. The fabric skirt may be toed-in with 6 inches of compacted material, or 12 inches of the fabric skirt should extend uphill and be secured with a minimum of 3 inches of open graded rock, or with staples or nails. If these two options are not feasible the dike structure may be trenched in 4 inches.


- (5) Triangular sediment filter dikes should be installed across exposed slopes during construction with ends of the dike tied into existing grades to prevent failure and should intercept no more than one acre of runoff.
- (6) When moved to allow vehicular access, the dikes should be reinstalled as soon as possible, but always at the end of the workday.



CROSS SECTION OF INSTALLATION OPTIONS

N.T.S.

1. TOE-IN 6" MIN
2. WEIGHTED W/ 3" - 5" OPEN GRADED ROCK
3. TRENCHED IN 4"



ISOMETRIC PLAN VIEW

N.T.S.

Figure 1-27 Schematic of a Triangular Filter Dike (NCTCOG, 1993)

Common Trouble Points:

- (1) Fabric skirt missing, too short, or not securely anchored (flows passing under dike).
- (2) Gap between adjacent dikes (runoff passing between dikes).
- (3) Dike not placed parallel to contour (runoff flowing around dike).

Inspection and Maintenance Guidelines:

- (1) Inspection should be made weekly or after each rainfall event and repair or replacement should be made promptly as needed by the contractor.
- (2) Inspect and realign dikes as needed to prevent gaps between sections.
- (3) Accumulated silt should be removed after each rainfall, and disposed of in a manner which will not cause additional siltation.
- (4) After the site is completely stabilized, the dikes and any remaining silt should be removed. Silt should be disposed of in a manner that will not contribute to additional siltation.

1.4.18 Concrete Washout Areas

The purpose of concrete washout areas is to prevent or reduce the discharge of pollutants to stormwater from concrete waste by conducting washout offsite, performing onsite washout in a designated area, and training employees and subcontractors.

The following steps will help reduce stormwater pollution from concrete wastes:

- Incorporate requirements for concrete waste management into material supplier and subcontractor agreements.
- Avoid mixing excess amounts of fresh concrete.
- Perform washout of concrete trucks in designated areas only.
- Do not wash out concrete trucks into storm drains, open ditches, streets, or streams.
- Do not allow excess concrete to be dumped onsite, except in designated areas.

For onsite washout:

- Locate washout area at least 50 feet from sensitive features, storm drains, open ditches, or water bodies. Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste.
- Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly.

Below grade concrete washout facilities are typical. These consist of a lined excavation sufficiently large to hold expected volume of washout material. Above grade facilities are used if excavation is not practical. Temporary concrete washout facility (type above grade) should be constructed as shown on the details at the end of this section, with sufficient quantity and volume to contain all liquid and concrete waste generated by washout operations. Plastic lining material should be a minimum of 10 mil in polyethylene sheeting and should be free of holes, tears, or other defects that compromise the impermeability of the material.

When temporary concrete washout facilities are no longer required for the work, the hardened concrete should be removed and disposed of. Materials used to construct temporary concrete washout facilities should be removed from the site of the work and disposed of. Holes, depressions or other ground disturbance caused by the removal of the temporary concrete washout facilities should be backfilled and repaired.




Figure 1-43 Schematics of Concrete Washout Areas

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(li), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Robert C. Thompson

Date: July 10, 2025

Signature of Customer/Agent



08/07/25

Regulated Entity Name: Moore Estates Subd Improvements

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

1. ☒ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.
☐ N/A
2. ☒ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
☒ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

- ☐ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____
- ☐ N/A
3. ☒ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.
- ☐ N/A
4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
- ☒ The site will be used for low density single-family residential development and has 20% or less impervious cover.
- ☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.
- ☐ The site will not be used for low density single-family residential development.
5. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
- ☐ **Attachment A - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.
6. ☒ **Attachment B - BMPs for Upgradient Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☒ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7. ☒ **Attachment C - BMPs for On-site Stormwater.**
- ☒ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☐ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8. ☒ **Attachment D - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
- ☐ N/A
9. ☒ The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
- ☒ The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.
- ☐ **Attachment E - Request to Seal Features.** A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10. ☒ **Attachment F - Construction Plans.** All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
- ☒ Design calculations (TSS removal calculations)
- ☒ TCEQ construction notes
- ☒ All geologic features
- ☒ All proposed structural BMP(s) plans and specifications
- ☐ N/A

11. ☒ **Attachment G - Inspection, Maintenance, Repair and Retrofit Plan.** A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
- ☒ Prepared and certified by the engineer designing the permanent BMPs and measures
 - ☒ Signed by the owner or responsible party
 - ☒ Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
 - ☒ A discussion of record keeping procedures
- ☐ N/A
12. ☐ **Attachment H - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- ☒ N/A
13. ☒ **Attachment I - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
- ☐ N/A

Responsibility for Maintenance of Permanent BMP(s)

Responsibility for maintenance of best management practices and measures after construction is complete.

14. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- ☐ N/A
15. ☒ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
- ☐ N/A

ATTACHMENT A – 20% OR LESS IMPERVIOUS COVER

This is not applicable: this project will be low density single-family residential

ATTACHMENT B – BMPs FOR UPGRADIENT STORMWATER

This is not applicable: separate permanent BMPs (or measures) are not required for the upgradient surface water, groundwater or stormwater, since that area has existing pavement (from Westlake Drive) that will mostly flow across a vegetated area before it flows across the proposed pavement from this project. Additionally, any upgradient surface water (groundwater or stormwater) would also be treated by the proposed BMP (vegetative filter strips) that is proposed for this project; see attachment C below.

ATTACHMENT C – BMPs FOR ON-SITE STORMWATER

Vegetative filter strips (VFS) are proposed to prevent the pollution of surface water or groundwater that originates onsite. The VFS alongside the pavement will be engineered to have less than 20% ground slopes for at least fifteen (15) feet (in the direction of flow). The TCEQ TSS calculations are provided on the sheet 12 of the construction plan set (Joint Use Driveway Plan). From the VFS, water will continue to sheet flow towards the back of the lots and, ultimately, into a tributary of Little Bee Creek.

ATTACHMENT D – BMPs FOR SURFACE STREAMS

The BMP (a VFS, in this case) that is planned above for onsite storm water is the same one that will protect any downstream surface streams. All run-off that contacts the proposed impervious area will flow across the VFS. If there is any pollutant released on this property, it is most likely to be expected on top of the impervious area (or would end up on the impervious cover) and, therefore, will be treated by the VFS (before flowing downstream).

ATTACHMENT E – REQUEST TO SEAL A FEATURE

This is not applicable for this project

ATTACHMENT F – CONSTRUCTION PLANS

See attached construction plan set (that is a total of 16 sheets).

ATTACHMENT G – INSPECTION, MAINTENANCE, REPAIR AND RETROFIT PLAN

See next page

ATTACHMENT H – PILOT-SCALE FIELD TESTING PLAN

This is not applicable for this project

ATTACHMENT I – MEASURES FOR MINIMIZING SURFACE STREAM CONTAMINATION

As a result of this construction and development, the storm water flows from this site are planned to be conveyed via sheet flow across a VFS and will continue sheet flow across the site; therefore, there would not be any known increases to stream flashing, the creation of stronger flows or in-stream velocities. Furthermore, no stream contamination or changes to the way water enters a stream is expected or known to be likely from the proposed regulated activities.

ATTACHMENT G

Inspection, Maintenance, Repair and Retrofit (IMRR) Plan

Purpose

This plan is for the "water quality" controls on this site and intended to help the site owner (and whoever is delegated) to maintain the water quality controls.

Construction Plans

This plan is for work constructed under the **Major Residential Permit** (_____) from the City of West Lake Hills. The information and details from those plans are included in this IMRR plan, however, anyone accepting responsibility for maintaining this system should obtain a copy of those plans and become familiar with the construction specifications on those plans.

Description of Controls

The water quality controls are **vegetative filter strips** (VFS), which are engineered grass areas that drain water using gravity. The purpose of these controls is to capture the initial run-off contacting the pavement and treat pollutants washed off from the impervious surfaces before releasing back into the natural ground. Vegetative filter strips are to receive sheet flow from contributing areas (unconcentrated).

General Description of Maintenance Required

The primary components of the water quality control are:

- the vegetated areas (grass).

The anticipated maintenance other than periodic cleaning of accumulated silt and debris in the grass areas will be mowing of the grass. The vegetative filter strips (grass field) should be maintained to allow vegetation to grow and should be kept level so that water distributes evenly.

Specific Maintenance Guidelines

The recommended maintenance guidelines are as follows. Records should be kept of the following and any other maintenance work and inspections, and those records should be kept on site for review by the TCEQ should they request to see them.

Inspections. The water quality control system should be inspected and tested at least six times a year to evaluate facility operation. One of these inspections should be during or immediately following wet weather. Any poor vegetation should be repaired immediately. Items which should be inspected include:

- distressed or dying grass,
- accumulation of silt and/or debris that might block flow,
- areas of water accumulation, and
- eroded areas or areas of uneven flow across the grass

Regular Maintenance.

- **Sediment Removal.** At a minimum, the sediment needs to be removed when buildup fills to 2 inches, or when it accumulates to such a point that it blocks the flow of water.
- **Debris and Litter Removal.** The areas should also be checked for accumulation of debris and trash. The debris and trash shall be removed. This should occur no less than 4 times a year. In addition, debris and litter should be removed after each significant rainfall event.
- **Mowing and Field Leveling.** Regular mowing should occur as often as necessary. If areas have become eroded in the grassy areas, they should be replenished and leveled. Fertilizers should be used at a minimum.


Additional Maintenance:

Once a vegetated area is well established, little additional maintenance is generally necessary. The key to establishing a viable vegetated feature is the care and maintenance it receives in the first few months after it is planted. Once established, some basic maintenance is required to ensure the health of the treatment, including:

- **Grassy Areas.** Vegetation must be maintained in the designated grassy areas to prevent erosion and provide additional water quality treatment.
- **Mowing.** The vegetative filter strips must be mowed regularly to discourage weed growth and control weeds. Grass areas in and around basins must be mowed at least twice annually to limit vegetation height to 18 inches. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and removed.
- **Debris and Litter Removal.** Debris and litter will accumulate and should be removed during regular mowing operations and inspections. Particular attention should be paid to floating debris that can eventually clog the system outfall.
- **Erosion Control.** The side slopes and embankment may periodically suffer from slumping and erosion, although this should not occur often if the soils are properly compacted during construction. Regrading and revegetation may be required to correct the problems.
- **Nuisance Control.** Standing water or soggy conditions in the basins can create nuisance conditions for nearby residents. Odors, mosquitoes, weeds, and litter are all occasionally perceived to be problems. Most of these problems are generally a sign that regular inspections and maintenance are not being performed (e.g., mowing and debris removal).

Replacement Parts

- **Grass.** Standard sods may be obtained at a hardware store (such as Home Depot or Lowes).

Responsible Party: Michael Tirres The Tirres Group, LLC (DBA Tirres Homes)
Name

Signature July 30, 2025
Date

Mailing Address: 3507 Native Dancer Cove
City, State: Austin, Texas 78746-1434
Telephone: (512) 422-2880

Agent Authorization Form
For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I Michael Tirres,
Print Name
Owner,
Title - Owner/President/Other
of The Tirres Group, LLC (DBA Tirres Homes),
Corporation/Partnership/Entity Name
have authorized Robert (Ric) Thompson, P.E.
Print Name of Agent/Engineer
of Thompson Land Engineering, LLC
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:


Applicant's Signature


8/4/2025
Date

THE STATE OF Texas §

County of Travis §

BEFORE ME, the undersigned authority, on this day personally appeared Michael Times known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 4 day of August 2025




NOTARY PUBLIC
Cody Lane Griffin
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 07-17-2028

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Moore Estates Subd Improvements

Regulated Entity Location: 803 Westlake Drive, West Lake, Texas 78746

Name of Customer: Tirres Group, LLC

Contact Person: Michael Tirres

Phone: (512) 422-2880

Customer Reference Number (if issued):CN _____

Regulated Entity Reference Number (if issued):RN _____

Austin Regional Office (3373)

☐ Hays

☒ Travis

☐ Williamson

San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☐ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☒ Austin Regional Office

☐ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

Site Location (Check All That Apply):

☒ Recharge Zone

☐ Contributing Zone

☐ Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	8.4 Acres	\$ 3,000
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	1,022 L.F.	\$ 650
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Robert C Thompson

Date: July 24, 2025

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

<i>Project</i>	<i>Project Area in Acres</i>	<i>Fee</i>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

<i>Project</i>	<i>Cost per Linear Foot</i>	<i>Minimum Fee- Maximum Fee</i>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

<i>Project</i>	<i>Cost per Tank or Piping System</i>	<i>Minimum Fee- Maximum Fee</i>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

<i>Project</i>	<i>Fee</i>
Exception Request	\$500

Extension of Time Requests

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN		RN

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)			
<input checked="" type="checkbox"/> New Customer <input type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership					
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>					
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)				<i>If new Customer, enter previous Customer below:</i>	
Tirres Group, LLC					
7. TX SOS/CPA Filing Number 802510806		8. TX State Tax ID (11 digits) 32061182229		9. Federal Tax ID (9 digits) 81-3463637	10. DUNS Number (if applicable)
11. Type of Customer:		<input checked="" type="checkbox"/> Corporation		<input type="checkbox"/> Individual	
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited	
12. Number of Employees				13. Independently Owned and Operated?	
<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input checked="" type="checkbox"/> Owner & Operator <input type="checkbox"/> Other:					
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant					
15. Mailing Address:		3507 Native Dancer Cove			
City	Austin	State	TX	ZIP	78746
ZIP + 4					
16. Country Mailing Information (if outside USA)				17. E-Mail Address (if applicable)	

18. Telephone Number	19. Extension or Code	20. Fax Number (if applicable)
() -		() -

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If "New Regulated Entity" is selected, a new permit application is also required.)								
<input checked="" type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information								
<i>The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).</i>								
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)								
Moore Estates Subd Improvements								
23. Street Address of the Regulated Entity: (No PO Boxes)	803 Westlake Drive							
	City	West Lake Hills	State	TX	ZIP	78746	ZIP + 4	1434
24. County								

If no Street Address is provided, fields 25-28 are required.

25. Description to Physical Location:										
26. Nearest City						State			Nearest ZIP Code	
<i>Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).</i>										
27. Latitude (N) In Decimal:						28. Longitude (W) In Decimal:				
Degrees	Minutes		Seconds		Degrees	Minutes		Seconds		
29. Primary SIC Code		30. Secondary SIC Code		31. Primary NAICS Code		32. Secondary NAICS Code				
(4 digits)		(4 digits)		(5 or 6 digits)		(5 or 6 digits)				
1771		1521		238110		236115				
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)										
Single-family residential subdivision										
34. Mailing Address:										
	City		State		ZIP		ZIP + 4			
35. E-Mail Address:										
36. Telephone Number			37. Extension or Code			38. Fax Number (if applicable)				
() -						() -				

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name:	Mark Roeder	41. Title:	Graduate Civil Engineer
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(512) 328-0002		(N/A) -	mark@tleng.net

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	The Tirres Group, LLC (DBA Tirres Homes)	Job Title:	Owner
Name (In Print):	Michael Tirres	Phone:	() 512-422-2880
Signature:		Date:	July 30, 2025

SITE DEVELOPMENT PERMIT PLAN

FOR

MOORE ESTATES SUBD IMPROVEMENTS

SHEET INDEX

- 1 COVER SHEET
- 2 PLAT
- 3 GENERAL NOTES
- 4 UTILITY DATA COLLECTION & PERMITS
- 5 EROSION & SEDIMENTATION CONTROL PLAN
- 6 ESC DETAILS & TREE LIST
- 7 OVERALL WATER & WASTEWATER PLAN
- 8 WATER PLAN & PROFILE (1 OF 2)
- 9 WATER PLAN & PROFILE (2 OF 2)
- 10 FORCEMAIN PLAN & PROFILE SHEET
- 11 ON-SITE PRIVATE WASTEWATER PLAN
- 12 JOINT USE DRIVEWAY PLAN
- 13 WATER & WASTEWATER DETAILS (1 OF 2)
- 14 WATER & WASTEWATER DETAILS (2 OF 2)
- 15 WATER & WASTEWATER CALCULATIONS
- 16 DEMOLITION DRIVEWAY

SUBMITTAL DATE: JULY 2025 EXPIRATION DATE:

WATERSHED:
THIS PROJECT IS LOCATED IN THE LITTLE BEE CREEK WATERSHED.

EDWARDS AQUIFER
THIS PROJECT LIES OVER THE EDWARDS AQUIFER RECHARGE ZONE.

FLOOD PLAIN NOTE:
A PORTION OF THIS PROJECT IS WITHIN THE 100 YEAR FLOOD PLAIN AND IS LOCATED IN ZONE X ACCORDING TO INFORMATION FROM FEDERAL FLOOD INSURANCE RATE MAP (FIRM) PANEL NO. 48453C0445K, EFFECTIVE DATE JANUARY 22, 2020 FOR TRAVIS COUNTY, TEXAS.

SITE DATA:
LOC ACREAGE: 0.88
TAX ID: 978038 - 978043
MAP GRID: F24
DEED: 2025038625
ZONING: R1


EXISTING LAND USE: SINGLE FAMILY RESIDENTIAL
PROPOSED LAND USE: SINGLE FAMILY RESIDENTIAL

LEGAL DESCRIPTION: LOTS 1-6, BLOCK A, MOORE ESTATES SUBDIVISION

RELATED CASES: NONE

ENGINEER: THOMPSON LAND ENGINEERING, LLC
904 N. CUERNAVACA
AUSTIN, TEXAS 78733
(512) 328-0002

OWNER: TIRRES GROUP LLC
3507 NATIVE DANCER CV
AUSTIN, TX 78746-1434



LOCATION MAP

SCALE: NTS

WARNING!!!!!!
REVIEW THE SEQUENCE OF CONSTRUCTION ON THE GENERAL NOTES SHEET PRIOR TO BEGINNING CONSTRUCTION. MANY NOTIFICATION OBLIGATIONS (AND OTHER OBLIGATIONS) INCLUDED IN THAT SEQUENCE.

TRAVIS COUNTY EMERGENCY SERVICES DISTRICT No. 9
(TC ESD-9) NOTES:
SEE SHEET 7 FOR THESE NOTES.

TRAVIS COUNTY WATER CONTROL AND IMPROVEMENT DISTRICT NO. 10 CONSTRUCTION NOTES:
SEE SHEET 7 FOR THESE NOTES.

THE APPLICANT/OWNER MUST COORDINATE WITH UTILITY COMPANIES PRIOR TO CONSTRUCTION.

FOR CITY
REVIEWED BY:

CITY ADMINISTRATOR
CITY OF WEST LAKE HILLS

DATE

DEVELOPMENT PERMIT NUMBER

FOR WATER
REVIEWED BY:

TRAVIS COUNTY WATER CONTROL AND IMPROVEMENT DISTRICT 10
(WCID 10)

DATE

FOR FIRE DEPARTMENT
REVIEWED BY:

TRAVIS COUNTY EMERGENCY SERVICES DISTRICT NO. 9

DATE

SUBMITTAL DATE: SUBMITTAL DATE:

TCEQ WATER: N/A TDLR: N/A


TCEQ WASTEWATER: N/A COUNTY: NA

TCEQ EDWARDS AQUIFER: N/A FIRE MARSHALL: JULY 2025

TPDES REPORT: NA WATER & WASTEWATER: N/A

REVISION/CORRECTION TABLE

NO.	DESCRIPTION	REVISE (R) ADD (A) VOID (V) SHEET NO's	TOTAL # SHEETS IN PLAN SET	NET CHANGE IMP. COVER (SQ. FT.)	TOTAL SITE IMP. COVER (SQ. FT.) (%)	CITY OF AUSTIN APPROVAL/DATE	TRAVIS COUNTY APPROVAL/DATE	APPROVED BY	DATE IMAGED
△									



8/20/25

THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512) 328-0002
www.tleng.net email: ric@tleng.net



DATE					

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746

COVER SHEET


PROJECT	SHEET NAME
DATE ISSUED August, 2025	
DRAWN BY RCT	DRAFTED BY BH
JOB NUMBER 1959	
SHEET 1 OF 16	

#156.00



01-09-2023

202300003

FINAL PLAT MOORE ESTATES SUBDIVISION TRAVIS COUNTY, TEXAS



VICINITY MAP
N.T.S.



- LEGEND
- 1/2" REBAR FOUND (OR AS NOTED)
 - 1/2" REBAR WITH "ALL POINTS" CAP FOUND
 - 1/2" IRON PIPE FOUND
 - 1/2" REBAR WITH "CHAMPARRAL" CAP SET
 - CONTROL POINT/BENCHMARK LOCATION
 - B.S.L. BUILDING SETBACK LINE
 - P.U.E. PRIVATE UTILITY EASEMENT
 - J.U.A.E. JOINT USE ACCESS EASEMENT
 - D.E. DRAINAGE EASEMENT
 - C.E. CONSERVATION EASEMENT
 - R.O.W. RIGHT-OF-WAY
 - () RECORD INFORMATION
 - 100-YEAR FLOODPLAIN
 - CREEK CENTERLINE

THIS IS A SURFACE DRAWING.
BEARING DATA: THE TEXAS COORDINATE SYSTEM OF 1983 (NAD83), CENTRAL ZONE, BASED ON GPS SOLUTIONS FROM THE NATIONAL GEODETIC SURVEY (NGS) ON-LINE POSITIONING USER SERVICE (OPUS) FOR CHAMPARRAL CONTROL POINT "2".
600 MAIL SET
SURFACE COORDINATES:
N 10078312.88
E 3095758.07
TEXAS STATE PLANE COORDINATES:
N 10078310.03
E 3095448.53
ELEVATION = 612.32'
VERTICAL DATUM: NAVD 88 (GEOID 12B)
COMBINED SCALE FACTOR = 0.999990010
(FOR SURFACE TO GRID CONVERSION)
INVERSE SCALE FACTOR = 1.000010
(FOR GRID TO SURFACE CONVERSION)
SLOPED ABOUT 0.0
THETA ANGLE: 0.0000"

BENCHMARK INFORMATION:
BM: 600 Mail set on the east side of Westlake Dr. at the end of Buckeye Trail 1/2" x 5" from edge of asphalt. OPUS POINT CHAMPARRAL CONTROL POINT #2 (SEE NOTE ABOVE)
ELEVATION = 612.32'
VERTICAL DATUM: NAVD 88 (GEOID 12B)

LOT SUMMARY TABLE		
LOT	ACRES	(MIN)
LOT 1: 1.78 ACRES	643	
LOT 2: 1.53 ACRES	647	
LOT 3: 1.28 ACRES	650	
LOT 4: 1.14 ACRES	655	
LOT 5: 1.02 ACRES	670	
LOT 6: 1.72 ACRES	679	
TOTAL: 8.42 ACRES		

DATE OF PREPARATION: February 22, 2021

Chaparral
Professional Land Surveying, Inc.
Surveying and Mapping
3500 McCall Lane
Austin, Texas 78744
S12-44-3-1724-1
Firm No. 10124500

PROJECT NO.: 1573-001
DRAWING NO.: 1573-001-PL#6LT
PLOT DATE: 08/30/2022
PLOT SCALE: 1"=100'
DRAWN BY: RGH/PAQ
SHEET 01 OF 05

WARNING:
DRAWING HAS BEEN
REDUCED TO FIT WITHIN THE
BORDER. USE BAR SCALE
FOR MEASUREMENT

FINAL PLAT MOORE ESTATES SUBDIVISION TRAVIS COUNTY, TEXAS

STATE OF TEXAS §
COUNTY OF TRAVIS §

WHEREAS, Robin Mallory Moore, Doyle Randall Moore and Sherry Moore Waldrop, beneficiaries under Doyle R. Moore Family Trust, by virtue of a Warranty Deed recorded in Document No. Volume 13112, Page 269, Deed Records of Travis County, Texas, are the owners of that certain 8.423 acre tract of land (called 7.875 acres) in the Wilkersons Spark Survey No. 1 in Travis County, Texas; and

NOW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS: That, the undersigned Trust Beneficiaries, owners of the land shown on this plat and described herein and named herein as the Moore Estates Subdivision of the City of West Lake Hills, Travis County, Texas, hereby subdivide said property and do hereby dedicate to the use of the Public, the common ways, the utility easements, and access easements for utility and emergency vehicle access as shown thereon for the purposes and consideration expressed.

WITNESS MY HAND this 12th day of December, 2022.
Robin Mallory Moore
Doyle Randall Moore
Sherry Moore Waldrop

STATE OF TEXAS §
COUNTY OF TRAVIS §

BEFORE ME, the undersigned authority, on this day personally appeared Robin Mallory Moore, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein expressed.

STATE OF TEXAS §
COUNTY OF TRAVIS §

BEFORE ME, the undersigned authority, on this day personally appeared Doyle Randall Moore, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein expressed.

STATE OF TEXAS §
COUNTY OF TRAVIS §

BEFORE ME, the undersigned authority, on this day personally appeared Sherry Moore Waldrop, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein expressed.

STATE OF TEXAS §
COUNTY OF TRAVIS §

The tract of land described on this plat is within the boundaries of Travis County Water Control and Improvement District (WCID) No. 10 and has water service available.

DATE: 12-14-22

Paul C. Barber, Jr.
President of the Board WCID No. 10

I, the undersigned, City Administrator of the City of West Lake Hills, Texas, hereby certify that this subdivision plat conforms to all the plat requirements of the City of West Lake Hills Code of Ordinances, for which my approval is required.

DATE: 12/10/2022

Michael B...
City Administrator, City of West Lake Hills, Texas

DATE: 12/15/2022

City of West Lake Hills, Texas

This plat has been submitted to and considered by the Zoning and Planning Commission (ZAPCO) of the City of West Lake Hills, Texas.

DATE: 12/09/2022
Michael B...
ZAPCO Chairperson, City of West Lake Hills, Texas

Approved and authorized for record by the City Council of the City of West Lake Hills, Texas.

DATE: 9th day of December, 2022.
Michael B...
Mayor, City of West Lake Hills, Texas

ATTEST:
Jerry Blanchard
City Secretary

STATE OF TEXAS
COUNTY OF TRAVIS

I, Robert C. Thompson, P.E., am authorized under the State of Texas to practice engineering and hereby certify that a portion of this property is within a special flood hazard area as shown on the Federal Emergency Management Agency Map Community Panel No. 48453 C0445K, dated January 22, 2020.

DATE: 12/02/2022
Robert C. Thompson
Robert C. Thompson, P.E. 69524
Thompson Land Engineering, LLC
504 N. Duembeck Austin, Texas 78733

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Paul J. Flugel, R.P.L.S. 5086
Chaparral Professional Land Surveying, Inc.
Firm No. 10124500
3500 McCall Lane
Austin, Texas 78744
(512) 443-1724

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Judy YHU
Judy YHU
Notary Public, State of Texas
Notary ID #1077368-3
My Commission Expires 02-19-2025

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Judy YHU
Judy YHU
Notary Public, State of Texas
Notary ID #1077368-3
My Commission Expires 02-19-2025

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Judy YHU
Judy YHU
Notary Public, State of Texas
Notary ID #1077368-3
My Commission Expires 02-19-2025

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Judy YHU
Judy YHU
Notary Public, State of Texas
Notary ID #1077368-3
My Commission Expires 02-19-2025

STATE OF TEXAS
COUNTY OF TRAVIS

I, the undersigned, a Registered Professional Land Surveyor in the State of Texas, hereby certify that this plat is true and correct and was prepared from the actual survey of the property made under my supervision on the ground.

DATE: 12-02-2022
Judy YHU
Judy YHU
Notary Public, State of Texas
Notary ID #1077368-3
My Commission Expires 02-19-2025

ALL RESIDENTIAL STRUCTURES OVER 3,600 SQUARE FEET SHALL COMPLY WITH THE REQUIREMENTS OF TABLE 805.1 FROM THE INTERNATIONAL FIRE CODE. RESIDENTIAL STRUCTURES WITH AN APPROVED NATIONAL FIRE PROTECTION ASSOCIATION 120 RESIDENTIAL FIRE SPRINKLER SYSTEM SHALL RECEIVE A 50% REDUCTION IN REQUIRED FIRE FLOW. THE RESULTING FIRE FLOW SHALL NOT BE LESS THAN 1,000 GALLONS PER MINUTE. IF ADDITIONAL FIRE FLOW REDUCTIONS ARE NEEDED, THEY MUST BE OBTAINED THROUGH CONSULTATION WITH THE EMERGENCY SERVICE DISTRICT NO. 9, TRAVIS COUNTY WATER CONTROL AND IMPROVEMENT DISTRICT NO. 10, AND THE CITY OF WEST LAKE HILLS, TEXAS.

NO PARKING ON THE J.U.A.E. DRIVEWAY OR SHOULDER IS ALLOWED SO THAT IT MAY REMAIN OPEN FOR EMERGENCY VEHICLES TO FACILITATE THIS REQUIREMENT THE ENTIRE J.U.A.E. DRIVEWAY SHALL BE PAINTED WITH RED FIRE LANE/TOW AWAY ZONE STRIPING AND SHALL HAVE NO PARKING SIGNAGE.

DEVELOPMENT OF THIS PROPERTY IS SUBJECT TO AND SHALL BE PERFORMED IN ACCORDANCE WITH THE TERMS AND CONDITIONS SET OUT IN THE SETTLEMENT AGREEMENT AND RELEASE BY AND BETWEEN SHERRY WALDROP MOORE, DOYLE RANDALL MOORE, AND ROBIN MALLORY MOORE AS CO-TRUSTEES OF THE MOORE FAMILY TRUST. PLANNERS & CITY OF WEST LAKE HILLS, DEFENDANT IN THAT CERTAIN CAUSE NO. 9-1-08-01-028372 IN THE 9TH JUDICIAL DISTRICT COURT OF TRAVIS COUNTY, TEXAS, INCLUDING THOSE SPECIAL TERMS, CONDITIONS, AND COVENANTS RELATING TO TREE SURVEY, CLEARING, AND MITIGATION REQUIREMENTS, JOINT USE DRIVEWAY REQUIREMENT, AND MAXIMUM HEIGHT OF BUILDINGS REQUIREMENT AS PROVIDED THEREIN.

SITE CLEARANCE: SITE DISTURBANCE, AND IMPROVED COVER, EVERY LOT OR UNIT IN THIS SUBDIVISION IS SUBJECT TO THE CITY OF WEST LAKE HILLS SITE CLEARANCE PROCEDURES. NO SITE CLEARANCE, EXCAVATION, GRADING OR LANDFILL SHALL COMMENCE UNLESS A PERMIT SHALL HAVE FIRST BEEN ISSUED FOR SAID WORK IN ACCORDANCE WITH THE PROVISION OF APPLICABLE ORDINANCES. IMPROVED COVER SHALL NOT EXCEED MAXIMUM PERCENTAGE PERMITTED UNDER CITY CODE. IN THE EVENT OF CONFLICT BETWEEN THE CODE AND THESE PLAT NOTES, THE PLAT NOTES SHALL CONTROL.

LOTS IN THIS SUBDIVISION ARE LOCATED OVER THE EDWARDS AQUIFER RECHARGE ZONE AND SUBJECT TO THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY EDWARDS AQUIFER RULES COORDINATED IN 30 TAC CHAPTER 213. AS AMENDED, NO BUILDING PERMIT WILL BE ISSUED BY THE CITY OF WEST LAKE HILLS UNTIL THE PERMITTING REQUIREMENTS OF THE EDWARDS RULES TAC CHAPTER 213 ARE FULLY COMPLIED WITH. THE APPLICANT FOR A BUILDING PERMIT IS RESPONSIBLE TO FURNISH THE CITY WRITTEN COMPLIANCE WITH THE PERMITTING REQUIREMENTS OF THE EDWARDS AQUIFER RULES FROM THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY UNLESS THEY MEET THE <20% IC EXEMPTION WHERE THE TCD ISSUES NO REVIEW.

STATE OF TEXAS
COUNTY OF TRAVIS

I, Rebecca Surran, Clerk of the County Court of Travis County, Texas, do hereby certify that on the 12th day of December, 2022, A.D., the County Clerk of Travis County, Texas, passed an Order authorizing the filing for record of this plat, and that said Order has been entered into the Minutes of said Court, at said Court, at said Court.

WITNESS MY HAND AND SEAL OF THE COUNTY COURT OF SAID COUNTY, this 12th day of December, 2022.

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

THE STATE OF TEXAS

THE COUNTY OF TRAVIS

I, Rebecca Surran, Clerk of the County Court of Travis County, Texas, do hereby certify that on the 12th day of December, 2022, A.D., the County Clerk of Travis County, Texas, passed an Order authorizing the filing for record of this plat, and that said Order has been entered into the Minutes of said Court, at said Court, at said Court.

WITNESS MY HAND AND SEAL OF THE COUNTY COURT OF SAID COUNTY, this 12th day of December, 2022, A.D.

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS

Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

STATE OF TEXAS

COUNTY OF TRAVIS


Filed for record this 9th day of January, 2023, A.D., at 3:11 P.M.

BY: *Rebecca Surran*
Deputy

Clerk of the County Court, Travis County, Texas

BY: *Rebecca Surran*
Deputy

WATER




TELEPHONE

COWEN, CHRIS
to me
Hello Valerie,
Nothing has changed. We do not provide redlined drawings.
Best Regards,
Chris Cowen
Manager-OSP Planning & Engineering Design
AT&T Texas
512-750-7140 (mobile)
cc2753@att.com


PROVIDER: AT & T
CONTACT: CHRIS COWEN
DATE(S) OF CONTACT: 4-15-2020

ELECTRIC




PROVIDER: AUSTIN ENERGY
CONTACT: AE GIS SERVICES
DATE(S) OF CONTACT: 7-8-2025


WASTEWATER



GAS




CABLE



MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
UTILITY DATA COLLECTION & PERMITS

DATE ISSUED	August, 2025
DRAWN BY	RCT
CHECKED BY	BH
JOB NUMBER	1959
SHEET	4 OF 16

THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512-328-0002)
www.tleng.net
email: ric@tleng.net




1 ESC & SEDIMENTATION CONTROL PLAN
SCALE: 1:20

SCALE: 1" = 20'


!!! NOTICE !!!
IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY RESUMES PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.

LEGEND	
	TREE TO REMAIN
	TREE TO BE REMOVED
	PROTECTED TREE
	HERITAGE TREE
	TREE PROTECTION
	EXISTING WATER METER
	EXISTING FIRE HYDRANT
	EXISTING GATE VALVE
	EXISTING POWER POLE
	HATCHED ITEMS TO BE DEMOLISHED AND REMOVED
	STABILIZED CONSTRUCTION ENTRANCE
	CONSTRUCTION STAGING AND TEMP. SPOILS AREA
	LIMITS OF CONSTRUCTION
	EROSION CONTROL SILT FENCE
	EROSION CONTROL MULCH SOCK
	TRIANGULAR FILTER DIKE
	ROCK BERM
	STORM INLET PROTECTION
	EXISTING MINOR CONTOURS
	EXISTING MAJOR CONTOURS
	PROPOSED CONTOURS
	EXISTING OVERHEAD ELECTRIC
	EXISTING UNDERGROUND TELEPHONE
	EXISTING UNDERGROUND GAS
	EXISTING WATER LINE
	EXISTING WASTEWATER LINE



2 ESC & SEDIMENTATION CONTROL PLAN
SCALE: 1:20

SCALE: 1" = 20'



BENCH MARK: 600 SET IN THE EAST SIDE OF WESTLAKE DR AT THE END OF BUCKEYE TRAIL 4'-5' FROM EDGE OF ASPHALT. ELEV. = 612.32' VERTICAL DATUM: NAVD 88 (GEOID 128)

!!!WARNING!!! BENCH MARK BEING PROVIDED IS FROM THE SURVEYOR AND COULD HAVE BEEN ADJUSTED, CHANGED, RESET, OR DESTROYED BETWEEN THE TIME OF THE SURVEY AND THE TIME OF CONSTRUCTION. CONTRACTOR SHOULD GET THE BENCH MARK ELEVATION VERIFIED AND SHOULD CHECK INTO AT LEAST TWO POINTS ON THE PROVIDED TOPOGRAPHY TO MAKE SURE THAT THE BENCH MARK ELEVATION SEEMS REASONABLE BEFORE USING.

!!!WARNING!!! TOPOGRAPHY AND MOST OR ALL OF THE EXISTING FEATURES ARE BASED ON THE SURVEY BY CHAPARRAL PROFESSIONAL LAND SURVEYING, INC. DATED 12-4-2019 AND WERE ASSUMED TO BE ACCURATE FOR THIS DESIGN.

!!!WARNING!!! UNDERGROUND UTILITIES SHOWN ON THESE PLANS IS A BEST ESTIMATE BASED ON RECORDS THAT COULD BE OBTAINED AND PHYSICAL FEATURES VISIBLE AT THE GROUND LEVEL. THE ENGINEER MAKES NO ASSERTIONS BEYOND THAT THEY ARE A BEST ESTIMATE AND AN ATTEMPT TO HELP IDENTIFY POSSIBLE UTILITIES IN THE AREA. THE CONTRACTOR MUST CALL ONE CALL IN ACCORDANCE WITH THE NOTES TO BETTER LOCATE ANY UNDERGROUND UTILITIES.

3 EXISTING DRIVEWAY DEMOLITION
SCALE: 1"=30



THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512)328-0002
email: rct@tleng.net
www.tleng.net

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746

EROSION & SEDIMENTATION CONTROL PLAN

PROJECT	DATE ISSUED
PROJECT	August, 2025
DRAWN BY	DRAFTED BY
RCT	BH
JOB NUMBER	1959
SHEET	5 OF 16










Table 1.4.5.G.1: Maximum spacing between silt fences on slopes




Slope	Spacing Interval (ft)	Max. Drainage Area (sf)
100:1 to 50:1 (1-2%)	500	25,000
50:1 to 30:1 (2-3.3%)	250	15,000
30:1 to 25:1 (3.3-4%)	150	12,000
25:1 to 20:1 (4-5%)	120	10,000
20:1 to 10:1 (5-10%)	100	5,000
10:1 to 5:1 (10-20%)	50	2,500
5:1 to 2:1 (20-50%)	10	1,000

TABLE 1. Silt Fence Fabric Requirements

Physical Properties	Method	Requirements
Fabric Weight in ounces per square yard (grams/square meter)	TEX-616-J ¹	5.0 minimum (150 minimum)
Equivalent Sieve Opening Size: US Standard (SI Standard sieve size)	CW-02215 ²	40 to 100 (425 to 150 µm)
Mullen Burst Strength: lbs. per sq. inch (psi) (megaPascal (mPa))	ASTM D-3786 ³	280 minimum (1.9 minimum)
Ultraviolet Resistance: % Strength Retention	ASTM D-1682 ⁴	70 minimum

¹ TexDot Test Method Tex-616-J, "Testing of Construction Fabrics".
² US Army Corps of Engineers Civil Works Construction Guide Specification CW-02215.
³ "Plastic Filter Fabric".
⁴ ASTM D-3786, "Test Method for Hydraulic Bursting Strength of Knitting Goods and Nonwoven Fabrics: Diaphragm Bursting Strength Tester Method".
⁵ ASTM D-1682, "Test Methods for Breaking Load and Elongation of Textile Fabrics".

CITY OF AUSTIN
WATERSHED PROTECTION DEPARTMENT
RECORD COPY SIGNED BY J. PATRICK MURPHY 11/15/99
STANDARD NO. 642S-1



TREE LIST

TREE NO	<8"	8-10"	10-24"	24"+	DESCRIPTION
**	11144	16			16" CDR
**	11145	6			6" LO
**	11146		22		15.8, 6" LO
M	11147	10.5			8.3, 2" UKT
** M	11148	7			7" LO
**	11149				9.6, 6" LO
**	11160	17			17" CE
**	11161	11			11" LO
**	11162	13			13" LO
**	11163	9			9" SO
**	11164				8" CE
**	11165	7			7" LO
**	11166	9			9" LO
**	11167	11			11" LO
**	11168	9			9" LO
M	11169	10			10" LO
**	11174	12			8, 6" LO
** M	11175		25		21, 8" SO
**	11176	10			10" CDR
**	11177	11			11" CDR
** M	11178		19		11, 8, 8" CDR
**	11191	17			17" CDR
**	11192	12			12" CDR
**	11193	14			7, 7, 7" UKT
**	11194	11			11" CDR
** M	11195	9			7, 4" CDR
** M	11196	14			10, 8" CDR
**	11197	10			10" LO
** M	11198	18			12, 12" CDR
**	11199	12			12" LO
M	11200	11			8, 6" CDR
** M	11201		21.5		12, 10, 9" CDR
**	11202				10" LO
**	11203	7			7" LO
M	11204	10			10" LO
M	11222		23		12, 8, 8, 8" CDR
**	11223	9			9" CDR
M	11224	12			12" CDR
M	11225	12			8, 6" CDR
**	11226	12			12" CB
**	11227	9			9" CDR
**	11228	12			12" UKT
**	11229	15			15" CDR
** M	11230	11.5			7, 3, 3, 3" UKT
** M	11231	14			10, 8" CDR
M	11232	9			6, 3, 3" UKT
**	11233	9			9" LO
** M	11234	17.5			12, 11" LO
**	11235	8			8" CDR
**	11236	9			9" LO
**	11237	8			8" CDR
**	11238	12			12" CDR
**	11239	8			8" LO
**	11240	7			7" CDR
**	11263	12			12" CDR
**	11264	7			7" CDR
**	11265	15			15" CB
** M	11266	9			7, 6" UKT
**	11267	9			9" CDR
** M	11268	16			12, 8" CB
**	11269	10			10" CDR
**	11270	14.5			11, 7" CDR
**	11261	7			7" CB
**	11262	9			9" CB
**	11263	9			9" CDR
** M	11264	9.5			7, 5" CDR
**	11265	9			9" UKT
**	11266	9			9" CDR
**	11267	7			7" CDR
**	11268	7			9" CDR
**	11269	7			7" UKT
**	11270	7			7" LO
**	11271	7			7" CDR
**	11272	13			13" CDR
**	11273	6			6" LO
**	11278	15			15" LO
**	11280	13			13" LO
** M	11307	16.5			9, 7, 4, 4" CDR
**	11308	11			11" CDR
**	11309	14			14" CDR
**	11310	9			9" CDR
**	11311	9			9" CDR
**	11312	9			9" CDR
**	11313	10			10" CDR
**	11314	6			6" CDR
**	11315	10			10" CDR
**	11316	17			17" CDR
**	11317	8			8" LO
M	11318				6, 3, 2" LO
**	11319	7			7" CDR
**	11320	10			10" CDR
M	11321	8			7, 2" HB
** M	11322	7			6, 2" CE
**	11323	6			6" LO
** M	11324	7.5			6, 3" LO
**	11325	7			7" HB
**	11326	13			13" CDR
**	11327	13			13" CDR
**	11328	11			11" CDR
**	11329	7			7" CDR
** M	11330		19.5		11, 8, 9" CDR
**	11331	7			7" CDR
M	11332	6			6" LO
** M	11333	8.5			7, 3" LO
** M	11334				6, 5, 3" UKT
M	11335	6			6" CDR
M	11336	6			6" CDR
**	11337	9			7, 4" CDR
**	11338	13			13" CDR
**	11339	6			6" LO
**	11340	6			6" LO
**	11341	8.5			7, 3" CDR
**	11343	7			7" CDR
**	11344	7			7" CDR
**	11345				8" CDR
** M	11346	11.5			8, 4, 3" CDR
**	11347	8			8" CDR
**	11348	8			8" CDR
**	11349	16			16" CDR
**	11350	7			7" CDR
**	11351				8" CDR
** M	11352	7	24		12, 6, 4, 4, 4" CDR
**	11353				7" CDR
**	11354	7			12, 3, 3" LO
** M	11355	13			10, 6" CDR
**	11356	6			6" CDR
**	11357	6			6" CDR
**	11359	8			8" CDR

TREE NOTES:

- TREE NUMBERS IN **BOLD** WITH ** ARE TO BE REMOVED
- TREE NUMBER IN *ITALICS* WITH THE PREFIX "H" ARE HERITAGE TREES AND **CANNOT** BE REMOVED.
- TREE NUMBERS WITH PREFIX "M" INDICATE MULTI-TRUNK TREES.
- TREE SURVEY PREPARED 2019 BY CHAPPARRAL PROFESSIONAL LAND SURVEYING, INC.

TOTAL	200.5	1028	129	25	
-------	-------	------	-----	----	--

8/20/25

THE FOLLOWING LISTED "CONSTRUCTION NOTES" ARE INTENDED TO BE ADVISORY IN NATURE ONLY AND DO NOT CONSTITUTE AN APPROVAL OR CONDITIONAL APPROVAL BY THE EXECUTIVE DIRECTOR. NOR DO THEY CONSTITUTE A COMPREHENSIVE LISTING OF ALL RULES OR CONDITIONS TO BE FOLLOWED DURING CONSTRUCTION. FURTHER ACTIONS MAY BE REQUIRED TO ACHIEVE COMPLIANCE WITH TCEQ REGULATIONS FOUND IN TITLE 30, TEXAS ADMINISTRATIVE CODE, CHAPTERS 213 AND 217, AS WELL AS LOCAL ORDINANCES AND REGULATIONS PROVIDING FOR THE PROTECTION OF WATER QUALITY. ADDITIONALLY, NOTHING CONTAINED IN THE FOLLOWING LISTED "CONSTRUCTION NOTES" RESTRICTS THE POWERS OF THE EXECUTIVE DIRECTOR. THE COMMISSION OR ANY OTHER GOVERNMENTAL ENTITY TO PREVENT, CORRECT, OR CURTAIL ACTIVITIES THAT RESULT OR MAY RESULT IN POLLUTION OF THE EDWARDS AQUIFER OR HYDROLOGICALLY CONNECTED SURFACE WATERS. THE HOLDER OF ANY EDWARDS AQUIFER PROTECTION PLAN CONTAINING "CONSTRUCTION NOTES" IS STILL RESPONSIBLE FOR COMPLIANCE WITH TITLE 30, TEXAS ADMINISTRATIVE CODE, CHAPTERS 213 OR ANY OTHER APPLICABLE TCEQ REGULATION, AS WELL AS ALL CONDITIONS OF AN EDWARDS AQUIFER PROTECTION PLAN THROUGH ALL PHASES OF PLAN IMPLEMENTATION. FAILURE TO COMPLY WITH ANY CONDITION OF THE EXECUTIVE DIRECTOR'S APPROVAL, WHETHER OR NOT IN CONTRADICTION OF ANY "CONSTRUCTION NOTES", IS A VIOLATION OF TCEQ REGULATIONS AND ANY VIOLATION IS SUBJECT TO ADMINISTRATIVE RULES, ORDERS, AND PENALTIES AS PROVIDED UNDER TITLE 30, TEXAS ADMINISTRATIVE CODE § 213.10 (RELATING TO ENFORCEMENT). SUCH VIOLATIONS MAY ALSO BE SUBJECT TO CIVIL PENALTIES AND INJUNCTION. THE FOLLOWING LISTED "CONSTRUCTION NOTES" IN NO WAY PRESENT AN APPROVED EXERCISE OF THE EXECUTIVE DIRECTOR TO ANY PART OF TITLE 30, TEXAS ADMINISTRATIVE CODE, CHAPTERS 213 AND 217, OR ANY OTHER TCEQ APPLICABLE REGULATION.

1. THIS ORGANIZED SEWAGE COLLECTION SYSTEM (SCS) MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.53(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S (TCEQ) EDWARDS AQUIFER RULES AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.

2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROPOSED REGULATED PROJECT MUST BE PROVIDED WITH COPIES OF THE SCS PLAN AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF THE PROJECT'S APPROVAL DURING THE COURSE OF THESE REGULATED ACTIVITIES. THE CONTRACTORS MUST BE REQUIRED TO KEEP ON-SITE COPIES OF THE PLAN AND THE APPROVAL LETTER.

3. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
- THE NAME OF THE APPROVED PROJECT;
- THE ACTIVITY START DATE; AND
- THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.

4. ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED SCS APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF AN SCS APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.

5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.

6. IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERED. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING AND THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRUCTURAL INTEGRITY OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.

7. SEWER LINES LOCATED WITHIN OR CROSSING THE 5-YEAR FLOODPLAIN OF A DRAINAGE WAY WILL BE PROTECTED FROM VIBRATION AND STREAM VELOCITIES WHICH COULD CAUSE EROSION AND SCOURING OF BACKFILL. THE TRENCH MUST BE CAPPED WITH CONCRETE TO PREVENT SCOURING OF BACKFILL, OR THE SEWER LINES MUST BE ENCASED IN CONCRETE. ALL CONCRETE SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES.

8. BLASTING PROCEDURES FOR PROTECTION OF EXISTING SEWER LINES AND OTHER UTILITIES WILL BE IN ACCORDANCE WITH THE NATIONAL FIRE PROTECTION ASSOCIATION CRITERIA. SAND IS NOT ALLOWED AS BEDDING OR BACKFILL IN TRENCHES THAT HAVE BEEN BLASTED. IF ANY EXISTING SEWER LINES ARE DAMAGED, THE LINES MUST BE REPAIRED AND RETESTED.

9. ALL MANHOLES CONSTRUCTED OR REHABILITATED ON THIS PROJECT MUST HAVE WATERIGHT SIZE ON SIZE RESILIENT CONNECTORS ALLOWING FOR DIFFERENTIAL SETTLEMENT. IF MANHOLES ARE CONSTRUCTED WITHIN THE 100-YEAR FLOODPLAIN, THE COVER MUST HAVE A GASKET AND BE BOLTED TO THE RING. WHERE GASKETED MANHOLE COVERS ARE REQUIRED FOR MORE THAN THREE MANHOLES IN SEQUENCE, OR FOR MORE THAN 1500 FEET, ALTERNATE MEANS OF VENTING WILL BE PROVIDED. BRICKS ARE NOT AN ACCEPTABLE CONSTRUCTION MATERIAL FOR ANY PORTION OF THE MANHOLE.

THE DIAMETER OF THE MANHOLES MUST BE A MINIMUM OF FOUR FEET AND THE MANHOLE FOR ENTRY MUST HAVE A MINIMUM CLEAR OPENING DIAMETER OF 30 INCHES. THESE DIMENSIONS AND OTHER DETAILS SHOWING COMPLIANCE WITH THE COMMISSION'S RULES CONCERNING MANHOLES AND SEWER LINE/MANHOLE INVERTS DESCRIBED IN 30 TAC §217.55 ARE INCLUDED ON PLAN SHEET (NOT APPLICABLE) OF 16.

IT IS SUGGESTED THAT ENTRANCE INTO MANHOLES IN EXCESS OF FOUR FEET DEEP BE ACCOMPLISHED BY MEANS OF A PORTABLE LADDER. THE INCLUSION OF STEPS IN A MANHOLE IS PROHIBITED.

10. WHERE WATER LINES AND NEW SEWER LINE ARE INSTALLED WITH A SEPARATION DISTANCE CLOSER THAN NINE FEET (I.E. WATER LINES CROSSING WASTEWATER LINES, WATER LINES PARALLELING WASTEWATER LINES, OR WATER LINES NEXT TO MANHOLES) THE INSTALLATION MUST MEET THE REQUIREMENTS OF 30 TAC §217.53(D) (PIPE DESIGN) AND 30 TAC §290.44(E) (WATER DISTRIBUTION).

11. WHERE SEWERS LINES DEViate FROM STRAIGHT ALIGNMENT AND UNIFORM GRADE ALL CURVATURE OF SEWER PIPE MUST BE ACHIEVED BY THE FOLLOWING PROCEDURE WHICH IS RECOMMENDED BY THE PIPE MANUFACTURER:

IF PIPE FLEXURE IS PROPOSED, THE FOLLOWING METHOD OF PREVENTING DEFLECTION OF THE JOINT MUST BE USED:

SPECIFIC CARE MUST BE TAKEN TO ENSURE THAT THE JOINT IS PLACED IN THE CENTER OF THE TRENCH AND PROPERLY BEDDED IN ACCORDANCE WITH 30 TAC §217.54.

12. NEW SEWAGE COLLECTION SYSTEM LINES MUST BE CONSTRUCTED WITH STUB OUTS FOR THE CONNECTION OF ANTICIPATED EXTENSIONS. THE LOCATION OF SUCH STUB OUTS MUST BE MARKED ON THE GROUND SUCH THAT THEIR LOCATION CAN BE EASILY DETERMINED AT THE TIME OF CONNECTION OF THE EXTENSIONS. SUCH STUB OUTS MUST BE MANUFACTURED WYES OR TEES THAT ARE COMPATIBLE IN SIZE AND MATERIAL WITH BOTH THE SEWER LINE AND THE EXTENSION. AT THE TIME OF ORIGINAL CONSTRUCTION, NEW STUB-OUTS MUST BE CONSTRUCTED SUFFICIENTLY TO EXTEND BEYOND THE END OF THE STREET PAVEMENT. ALL STUB-OUTS MUST BE SEALED WITH A MANUFACTURED CAP TO PREVENT LEAKAGE. EXTENSIONS THAT WERE NOT ANTICIPATED AT THE TIME OF ORIGINAL CONSTRUCTION OR THAT ARE TO BE CONNECTED TO AN EXISTING SEWER LINE NOT FURNISHED WITH STUB OUTS MUST BE CONNECTED USING A MANUFACTURED SADDLE AND IN ACCORDANCE WITH ACCEPTED PLUMBING TECHNIQUES.

IF NO STUB-OUT IS PRESENT AN ALTERNATE METHOD OF JOINING LATERALS IS SHOWN IN THE DETAIL ON PLAN SHEET (NOT APPLICABLE) OF 16. (FOR POTENTIAL FUTURE LATERALS).

THE PRIVATE SERVICE LATERAL STUB-OUTS MUST BE INSTALLED AS SHOWN ON THE PLAN AND PROFILE SHEETS ON PLAN SHEET (NOT APPLICABLE) OF 16 AND MARKED AFTER BACKFILLING AS SHOWN IN THE DETAIL ON PLAN SHEET (NOT APPLICABLE) OF 16.

13. TRENCHING, BEDDING AND BACKFILL MUST CONFORM WITH 30 TAC §217.54. THE BEDDING AND BACKFILL FOR FLEXIBLE PIPE MUST COMPLY WITH THE STANDARDS OF ASTM D-2221, CLASSES A, B, II OR III. RIGID PIPE BEDDING MUST COMPLY WITH THE REQUIREMENTS OF ASTM C 12 (ANSI A 106.2) CLASSES A, B OR C.

14. SEWER LINES MUST BE TESTED FROM MANHOLE TO MANHOLE. WHEN A NEW SEWER LINE IS CONNECTED TO AN EXISTING STUB OR CLEAN-OUT, IT MUST BE TESTED FROM EXISTING MANHOLE TO NEW MANHOLE. IF A STUB OR CLEAN-OUT IS USED AT THE END OF THE PROPOSED SEWER SERVICE, PRIVATE SERVICE ATTACHMENTS MAY BE CONNECTED BETWEEN THE LAST MANHOLE AND THE CLEAN-OUT UNLESS IT CAN BE CERTIFIED AS CONFORMING WITH THE PROVISIONS OF 30 TAC §213.53(C)(E).

15. ALL SEWER LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC §217.57. THE ENGINEER MUST RETAIN COPIES OF ALL TEST RESULTS WHICH MUST BE MADE AVAILABLE TO THE EXECUTIVE DIRECTOR UPON REQUEST. THE ENGINEER MUST CERTIFY IN WRITING THAT ALL WASTEWATER LINES HAVE PASSED ALL REQUIRED TESTING TO THE APPROPRIATE REGIONAL OFFICE WITHIN 30 DAYS OF TEST COMPLETION AND PRIOR TO USE OF THE NEW COLLECTION SYSTEM. TESTING METHOD WILL BE:

(a) FOR A COLLECTION SYSTEM PIPE THAT WILL TRANSPORT WASTEWATER BY GRAVITY FLOW, THE DESIGN TEST SPECIFY AN INFLATION AND EXFILTRATION TEST OR A LOW-PRESSURE AIR TEST. A TEST MUST CONFORM TO THE FOLLOWING

REQUIREMENTS:

(1) LOW PRESSURE AIR TEST.

(A) A LOW PRESSURE AIR TEST MUST FOLLOW THE PROCEDURES DESCRIBED IN AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) C-828, ASTM C-924, OR ASTM F-1417 OR OTHER PROCEDURE APPROVED BY THE EXECUTIVE DIRECTOR, EXCEPT AS TO TESTING TIMES AS REQUIRED IN TABLE C.3 IN SUBPARAGRAPH (C) OF THIS PARAGRAPH OR EQUATION C.3 IN SUBPARAGRAPH (B)(II) OF THIS PARAGRAPH.

(B) FOR SECTIONS OF COLLECTION SYSTEM PIPE LESS THAN 36 INCH AVERAGE INSIDE DIAMETER, THE FOLLOWING PROCEDURE MUST APPLY, UNLESS A PIPE IS TO BE TESTED AS REQUIRED BY PARAGRAPH (2) OF THIS SUBSECTION:

(i) A PIPE MUST BE PRESSURIZED TO 3.5 POUNDS PER SQUARE INCH (PSI) GREATER THAN THE PRESSURE EXERTED BY GROUNDWATER ABOVE THE PIPE.

(ii) ONCE THE PRESSURE IS STABILIZED, THE MINIMUM TIME ALLOWABLE FOR THE PRESSURE TO DROP FROM 3.5 PSI GAUGE TO 2.5 PSI GAUGE IS COMPUTED FROM THE FOLLOWING EQUATION:

$$T = \frac{0.085 \times D \times K}{Q}$$

WHERE:

T = TIME FOR PRESSURE TO DROP 1.0 POUND PER SQUARE INCH GAUGE IN SECONDS

K = 0.000419 X D X L, BUT NOT LESS THAN 1.0

D = AVERAGE INSIDE PIPE DIAMETER IN INCHES

L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET

Q = RATE OF LOSS, 0.0015 CUBIC FEET PER MINUTE PER SQUARE FOOT

INTERNAL SURFACE

(C) SINCE A K VALUE OF LESS THAN 1.0 MAY NOT BE USED, THE MINIMUM TESTING TIME FOR EACH PIPE DIAMETER IS SHOWN IN THE FOLLOWING TABLE C.3.

Pipe Diameter (inches)	Minimum Time (seconds)	Maximum Length for Minimum Time (feet)	Time for Longer Length (seconds/foot)
6	340	398	0.855
8	454	298	1.520
10	567	239	2.374
12	683	199	3.419
15	850	159	5.342
18	1020	133	7.693
21	1190	114	10.471
24	1360	100	13.676
27	1530	88	17.309
30	1700	80	21.369
36	1970	72	27.356

(D) AN OWNER MAY STOP A TEST IF NO PRESSURE LOSS HAS OCCURRED DURING THE FIRST 25% OF THE CALCULATED TESTING TIME.

(E) IF ANY PRESSURE LOSS OR LEAKAGE HAS OCCURRED DURING THE FIRST 25% OF A TESTING PERIOD, THEN THE TEST MUST CONTINUE FOR THE ENTIRE TEST DURATION AS OUTLINED ABOVE OR UNTIL FAILURE.

(F) WASTEWATER COLLECTION SYSTEM PIPES WITH A 27 INCH OR LARGER AVERAGE INSIDE DIAMETER MAY BE AIR TESTED AT EACH JOINT INSTEAD OF FOLLOWING THE PROCEDURE OUTLINED IN THIS SECTION.

(G) A TESTING PROCEDURE FOR PIPE WITH AN INSIDE DIAMETER GREATER THAN AN SCS APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.

(2) INFILTRATION/EXFILTRATION TEST

(A) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE.

(B) AN OWNER SHALL USE AN INFILTRATION TEST IN LIEU OF AN EXFILTRATION TEST WHEN PIPES ARE INSTALLED BELOW THE GROUNDWATER LEVEL.

(C) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF TWO FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE, OR AT LEAST TWO FEET ABOVE EXISTING GROUNDWATER LEVEL, WHICHEVER IS GREATER.

(D) FOR CONSTRUCTION WITHIN A 25-YEAR FLOOD PLAIN, THE INFILTRATION OR EXFILTRATION MUST NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT THE SAME MINIMUM TEST HEAD AS IN SUBPARAGRAPH (C) OF THIS PARAGRAPH.

(E) IF THE QUANTITY OF INFILTRATION OR EXFILTRATION EXCEEDS THE MAXIMUM QUANTITY SPECIFIED, AN OWNER SHALL UNDERTAKE REMEDIAL ACTION IN ORDER TO REDUCE THE INFILTRATION OR EXFILTRATION TO AN AMOUNT WITHIN THE LIMITS SPECIFIED. AN OWNER SHALL RETEST A PIPE FOLLOWING A REMEDIATION ACTION.

(F) A GRAVITY COLLECTION PIPE IS COMPOSED OF FLEXIBLE PIPE. DEFLECTION TESTING IS ALSO REQUIRED. THE FOLLOWING PROCEDURES MUST BE FOLLOWED:

(1) FOR A COLLECTION PIPE WITH INSIDE DIAMETER LESS THAN 27 INCHES, DEFLECTION MEASUREMENT REQUIRES A RIGID MANDREL.

(A) MANDREL SIZING

(i) A RIGID MANDREL MUST HAVE AN OUTSIDE DIAMETER (OD) NOT LESS THAN 95% OF THE BASE INSIDE DIAMETER (ID) OR AVERAGE ID OF A PIPE, AS SPECIFIED ON THE PIPE, OR APPROPRIATE STANDARD BY THE ASTM, AMERICAN WATER WORKS ASSOCIATION, UNI-BELL, OR AMERICAN NATIONAL STANDARDS INSTITUTE, OR ANY RELATED APPENDIX.

(ii) IF A MANDREL SIZING DIAMETER IS NOT SPECIFIED IN THE APPROPRIATE STANDARD, THE MANDREL MUST HAVE AN OD EQUAL TO 96% OF THE ID OF A PIPE, IN THIS CASE, THE ID OF THE PIPE, FOR THE PURPOSE OF DETERMINING

THE OD OF THE MANDREL, MUST EQUAL BE THE AVERAGE OUTSIDE DIAMETER MINUS TWO MINIMUM WALL THICKNESSES FOR OD CONTROLLED PIPE AND THE AVERAGE INSIDE DIAMETER FOR ID CONTROLLED PIPE.

(iii) ALL DIMENSIONS MUST MEET THE APPROPRIATE STANDARD.

(B) MANDREL DESIGN

(i) A RIGID MANDREL MUST BE CONSTRUCTED OF A METAL OR A RIGID PLASTIC MATERIAL THAT CAN WITHSTAND 200 PSI WITHOUT BEING DEFORMED.

(ii) A MANDREL MUST HAVE NINE OR MORE OOD NUMBER OF RUNNERS OR LEGS.

(iii) A BARREL SECTION LENGTH MUST EQUAL AT LEAST 75% OF THE INSIDE DIAMETER OF A PIPE.

(iv) EACH SIZE MANDREL MUST USE A SEPARATE PROVING RING.

(v) METHOD OPTIONS

(i) AN ADJUSTABLE OR FLEXIBLE MANDREL IS PROHIBITED.

(ii) A TEST MAY NOT USE TELEVISION INSPECTION AS A SUBSTITUTE FOR A DEFLECTION TEST.

(iii) IF REQUESTED, THE EXECUTIVE DIRECTOR MAY APPROVE THE USE OF A DEFLECTOMETER OR A MANDREL WITH REMOVABLE LEGS OR RUNNERS ON A CASE-BY-CASE BASIS.

(2) FOR A GRAVITY COLLECTION SYSTEM PIPE WITH AN INSIDE DIAMETER 27 INCHES AND GREATER, OTHER TEST METHODS MAY BE USED TO DETERMINE VERTICAL DEFLECTION.

(3) A DEFLECTION TEST METHOD MUST BE ACCURATE TO WITHIN PLUS OR MINUS 0.2% DEFLECTION.

(4) AN OWNER SHALL NOT CONDUCT A DEFLECTION TEST UNTIL AT LEAST 30 DAYS AFTER THE FINAL BACKFILL.

(5) GRAVITY COLLECTION SYSTEM PIPE DEFLECTION MUST NOT EXCEED FIVE PERCENT (5%).

(6) IF A PIPE SECTION FAILS A DEFLECTION TEST, AN OWNER SHALL CORRECT THE PROBLEM AND CONDUCT A SECOND TEST AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS.

16. ALL MANHOLES MUST BE TESTED TO MEET OR EXCEED THE REQUIREMENTS OF 30 TAC §217.58.

(a) ALL MANHOLES MUST PASS A LEAKAGE TEST.

(b) AN OWNER SHALL TEST EACH MANHOLE (AFTER ASSEMBLY AND BACKFILLING) FOR LEAKAGE.

(c) SEPARATE AND INDEPENDENT OF THE COLLECTION SYSTEM PIPES, BY HYDROSTATIC EXFILTRATION TESTING, VACUUM TESTING, OR OTHER METHOD APPROVED BY THE EXECUTIVE DIRECTOR.

(1) HYDROSTATIC TESTING

(A) THE MAXIMUM LEAKAGE FOR HYDROSTATIC TESTING OR ANY ALTERNATIVE TEST METHODS IS 0.025 GALLONS PER FOOT DIAMETER PER FOOT OF MANHOLE DEPTH PER HOUR.

(B) TO PERFORM A HYDROSTATIC EXFILTRATION TEST, AN OWNER SHALL SEAL ALL WASTEWATER PIPES COMING INTO A MANHOLE WITH AN INTERNAL PIPE PLUG, FILL THE MANHOLE WITH WATER, AND MAINTAIN THE TEST FOR AT LEAST ONE HOUR.

(C) A TEST FOR CONCRETE MANHOLES MAY USE A 24-HOUR WETTING PERIOD BEFORE TESTING TO ALLOW SATURATION OF THE CONCRETE.

(2) VACUUM TESTING

(A) TO PERFORM A VACUUM TEST, AN OWNER SHALL PLUG ALL LIFT HOLES AND EXTERIOR JOINTS WITH A NON-SHRINK GROUT AND PLUG ALL PIPES ENTERING THE MANHOLE.

(B) NO GROUT MUST BE PLACED IN HORIZONTAL JOINTS BEFORE TESTING.

(C) STUB-OUTS, MANHOLE BOOTS, AND PIPE PLUGS MUST BE SECURED TO PREVENT MOVEMENT WHILE A VACUUM IS DRAWN.

(D) AN OWNER SHALL USE A MINIMUM 60 INCH LB TORQUE WRENCH TO TIGHTEN THE EXTERNAL CLAMPS THAT SECURE A TEST COVER TO THE TOP OF A MANHOLE.

(E) A TEST HEAD MUST BE PLACED AT THE INSIDE OF THE TOP OF A CONE SECTION, AND THE SEAL INFLATED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

(F) THERE MUST BE A VACUUM OF 10 INCHES OF MERCURY INSIDE A MANHOLE TO PERFORM A VALID TEST.

(G) A TEST DOES NOT BEGIN UNTIL AFTER THE VACUUM PUMP IS OFF.

(H) A MANHOLE PASSES THE TEST IF AFTER 2.0 MINUTES AND WITH ALL VALVE CLOSED, THE VACUUM IS AT LEAST 9.0 INCHES OF MERCURY.

17. ALL PRIVATE SERVICE LATERALS MUST BE INSPECTED AND CERTIFIED IN ACCORDANCE WITH 30 TAC §213.53(C)(3)(i). AFTER INSTALLATION OF AND, PRIOR TO COVERING AND CONNECTING A PRIVATE SERVICE LATERAL TO AN EXISTING ORGANIZED SEWAGE COLLECTION SYSTEM, A TEXAS LICENSED PROFESSIONAL ENGINEER, TEXAS REGISTERED SANITARIAN, OR APPROPRIATE CITY INSPECTOR MUST VISUALLY INSPECT THE PRIVATE SERVICE LATERAL AND THE CONNECTION TO THE SEWAGE COLLECTION SYSTEM, AND CERTIFY THAT IT IS CONSTRUCTED IN CONFORMITY WITH THE APPLICABLE PROVISIONS OF THIS SECTION. THE OWNER OF THE COLLECTION SYSTEM MUST MAINTAIN SUCH CERTIFICATIONS FOR FIVE YEARS AND FORWARD COPIES TO THE APPROPRIATE REGIONAL OFFICE UPON REQUEST. CONNECTIONS MAY ONLY BE MADE TO AN APPROVED SEWAGE COLLECTION SYSTEM.

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

AUSTIN REGIONAL OFFICE 12100 PARK 35 CIRCLE, BUILDING A AUSTIN, TEXAS 78733-4480 PHONE (512) 339-2929 FAX (512) 339-3795	SAN ANTONIO REGIONAL OFFICE 14250 JUDSON ROAD SAN ANTONIO, TEXAS 78233-4480 PHONE (210) 490-3096 FAX (210) 545-4329
--	---

ADDITIONAL TCEQ SCS NOTES

PIPING MATERIALS

THIS PROJECT IS PROPOSED TO INSTALL PVC SDR 21 (ASTM D 2241) FORCE MAIN WASTEWATER LINES, WHICH CAN WITHSTAND THE PRESSURE GENERATED BY INSTANTANEOUS PUMP STOPPAGE, DUE TO POWER FAILURE UNDER MAXIMUM PUMPING CONDITIONS.

THE UNDERGROUND FORCE MAIN PIPE JOINT WILL INCLUDE EITHER PUSH-ON RUBBER GASKETS OR MECHANICAL JOINTS WITH A PRESSURE RATING EQUAL TO OR GREATER THAN THAT OF THE FORCE MAIN PIPE MATERIAL.

EXPOSED FORCE MAIN PIPE JOINTS WILL BE FLANGED OR FLEXIBLE AND WILL BE ADEQUATELY SECURED (TO PREVENT MOVEMENT DUE TO WASTEWATER SURGES).

A DETECTABLE UNDERGROUND WARNING TAPE WILL BE LAID IN THE SAME TRENCH AS A FORCE MAIN PIPE. THIS WARNING TAPE WILL BE LOCATED ABOVE AND PARALLEL TO THE FORCE MAIN AND WILL INCLUDE THE LABEL "PRESSURIZED WASTEWATER" CONTINUOUSLY REPEATED IN AT LEAST 15-INCH-TALL LETTERS.

MANHOLES

THERE ARE NO PROPOSED MANHOLES FOR THIS PROJECT. LINES WILL BE PRESSURIZED IN THE FORCE MAIN. THERE ARE NO EXISTING WASTEWATER MANHOLE COVERS THAT LIE WITHIN A 100-YEAR FLOODPLAIN FOR THIS PROJECT.

TESTING, INSPECTION AND CERTIFICATION

THE FINAL PLANS AND SPECIFICATIONS WILL INCLUDE THE PRESSURE TESTING PROCEDURES.

A PRESSURE TEST (USING 50 POUNDS PER SQUARE INCH ABOVE THE NORMAL OPERATING PRESSURE OF A FORCE MAIN) WILL BE INCLUDED.

A VALVE FOR PRESSURE TESTING WILL BE INSTALLED (NEAR THE DISCHARGE POINT OF A FORCE MAIN), WHICH WOULD REMAIN AFTER A TEST IS SUCCESSFULLY COMPLETED.

A PUMP ISOLATION VALVE MAY POTENTIALLY BE USED AS AN OPPOSITE TERMINATION POINT.

A TEST WILL INVOLVE FILLING A FORCE MAIN WITH WATER. THIS PROPOSED PIPE IS EXPECTED TO HOLD THE DESIGNATED TEST PRESSURE FOR A MINIMUM OF 4.0 HOURS. THE LEAKAGE RATE SHOULD NOT EXCEED 10.0 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER DAY.

OCCUPATIONAL, SAFETY, PUBLIC HEALTH AND ENVIRONMENTAL PROTECTION

THE PROJECT PLANS AND SPECIFICATIONS MUST ENSURE THAT THE PIPE INSTALLATION WILL ADHERE TO THE MINIMUM SEPARATION DISTANCES ALLOWED BY SECTION 217.53(D) OF THE TCEQ'S RULES.

ADDITIONALLY, THE PROJECT PLANS INCLUDE THE EXACT REPRODUCTION OF THE SEPARATION DISTANCE WORDING DETAIL IN SECTION 217.53, WHICH ENSURES THAT THE SEPARATION DISTANCE BETWEEN ANY UNKNOWN WATER LINES THAT ARE DISCOVERED DURING THE INSTALLATION PHASE OF THE PROJECT.

TRAVIS COUNTY WCID #9 (WESTLAKE FIRE DEPARTMENT) NOTES

1. CONTRACTOR SHALL NOTIFY MS. CARLA ORTS, WC&ID NO. 10 DISTRICT MANAGER, AT (512) 327-2230 AT LEAST 48-HOURS PRIOR TO BEGINNING ANY CONSTRUCTION INCLUDING MOBILIZATION.

2. CONTRACTOR SHALL COORDINATE WITH WC&ID NO. 10 AND CROSSROADS UTILITY SERVICES, DISTRICT OPERATOR TO LOCATE EXISTING WATER LINES AT LEAST 48-HOURS PRIOR TO BEGINNING ANY CONSTRUCTION.

3. CONTRACTOR SHALL NOTIFY MS. CARLA ORTS, WC&ID NO. 10 DISTRICT MANAGER, AT (512) 327-2230 AT LEAST 48-HOURS PRIOR TO CLOSING OR OPENING WATER SERVICES VALVES, AND/OR DISRUPTION OF WATER SERVICES TO ANY CUSTOMER.

4. CONTRACTOR SHALL NOT BE PERMITTED TO OPERATE ANY DISTRICT WATER VALVES. CONTRACTOR SHALL COORDINATE WITH CROSSROADS UTILITY SERVICES, DISTRICT OPERATOR, DISTRICT OPERATOR, TO OPERATE DISTRICT VALVES.

5. CONTRACTOR SHALL SUPPLY CROSSROADS UTILITY SERVICES, DISTRICT OPERATOR, WITH ALL WATER LINE TESTING AND STERILIZATION REPORTS.

6. CONTRACTOR SHALL NOTIFY CROSSROADS UTILITY SERVICES, DISTRICT OPERATOR, 48-HOURS PRIOR TO ANY WET CONNECTIONS OR PRESSURE TAPS TO BE PRESENT AT ANY AND ALL CONNECTIONS AND TAPS.

7. ALL WATERLINES 12" AND SMALLER SHALL BE DUCTILE IRON PIPE (CL-350) OR (PVC C-900, DR-14).

8. ALL 16" WATERLINES SHALL BE DUCTILE IRON (CL-250) OR PVC (C-905, DR-14).

!!! WARNING !!!

UNDERGROUND UTILITIES SHOWN ON THESE PLANS IS A BEST ESTIMATE BASED ON RECORDS THAT COULD BE OBTAINED AND PHYSICAL FEATURES VISIBLE AT THE GROUND LEVEL. THE ENGINEER MAKES NO ASSERTIONS BEYOND THAT THEY ARE A BEST ESTIMATE AND AN ATTEMPT TO HELP IDENTIFY POSSIBLE UTILITIES IN THE AREA. THE CONTRACTOR MUST CALL ONE CALL IN ACCORDANCE WITH THE NOTES TO BETTER LOCATE ANY UNDERGROUND UTILITIES.

TRAVIS COUNTY ESD #9 (WESTLAKE FIRE DEPARTMENT) NOTES

1. ALL FIRE LANE MARKING SHALL BE RED IN COLOR WITH WHITE LETTERS THAT STATE "FIRE LANE TOW AWAY ZONE" EVERY 35 FEET. IT IS RECOMMENDED TO HAVE AN INSPECTOR FROM OUR OFFICE VISIT THE SITE WITH THE INSTALLER PRIOR TO MARKING THE ACCESS ROADS TO CONFIRM ALL REQUIRED APPLICATION LOCATIONS AND WORDING.

2. ASPHALTIC HOT MIX CONCRETE ACCESS ROADWAYS SHALL BE ENGINEERED NOT TO EXCEED 13 PERCENT IN GRADE. CONCRETE ROADWAYS SHALL BE DESIGNED NOT TO EXCEED 15 PERCENT IN GRADE. CONCRETE ROADWAYS SHALL BE DESIGNED NOT TO EXCEED 15 PERCENT IN GRADE. MAXIMUM IMMEDIATE GRADE CHANGE OR GRADE CHANGE WITHIN 20 FEET SHALL NOT EXCEED 10 PERCENT.

3. FIRE FLOW TEST SHALL BE CONDUCTED BY OUR OFFICE UTILIZING THE NEW HYDRANTS ONCE THEY ARE INSTALLED TO DETERMINE THAT THE PROJECTED FIRE FLOWS ARE AVAILABLE. THIS TEST WILL BE PERFORMED UPON COMPLETION OF THE NEW INSTALLATION.

4. ALL UNDERGROUND FIRE MAINS SUPPLYING FUTURE SPRINKLER SYSTEMS SHALL BE INSTALLED AND TESTED IN ACCORDANCE WITH NFPA 13 AND NFPA 24, BY A LICENSED FIRE PROTECTION CONTRACTOR, AS REQUIRED BY THE TEXAS DEPARTMENT OF INSURANCE / STATE FIRE MARSHAL'S OFFICE FIRE SPRINKLER RULES. THE INSTALLATION MUST BE DOCUMENTED BY SUBMITTING SHOP DRAWINGS OR AS-BUILT PLANS ALONG WITH AN UNDERGROUND TEST CERTIFICATE TO THE TRAVIS COUNTY EMERGENCY SERVICES DISTRICT NO. 9 WITH THE INFORMATION REQUIRED BY THE 2013 EDITION OF NFPA 13 AND SECTION 34.7.17 OF THE FIRE SPRINKLER RULES. PROJECTS WILL NOT BE GIVEN FINAL APPROVAL PRIOR TO THE RECEIPT OF THIS DOCUMENTATION.

5. A VISUAL INSPECTION WILL BE REQUIRED BEFORE THE FIRE MAINS ARE COVERED TO VERIFY PIPE TYPE, SIZE, WRAPPED JOINTS, AND PROPER INSTALLATION OF THRUST BLOCKING OR PIPE RESTRAINTS PER PLANS. IF THE PIPE IS COVERED UP PRIOR TO THE INSPECTION, THE INSPECTION WILL BE TERMINATED. THE PIPE WILL BE REQUIRED TO BE UNCOVERED, AND A RE-INSPECTION FEE WILL BE ASSESSED.

6. THE FIRE MAIN WILL BE REQUIRED TO HAVE A HYDROSTATIC TEST WITNESSED (200 PSI FOR 2 HOURS). THE MAIN SHALL BE ABLE TO BE ISOLATED OFF THE EXISTING MAIN AND AT THE POINT IT TERMINATES TO THE BUILDING. THE MAIN MUST HOLD PRESSURE WITHOUT LOSS. A PRETEST SHOULD BE PERFORMED PRIOR TO SCHEDULING THE HYDRO INSPECTION WITH OUR OFFICE. IF PRESSURE LOSS IS IDENTIFIED, THE INSPECTION WILL BE TERMINATED, AND A RE-INSPECTION FEE WILL BE ASSESSED.

7. THE MAIN SHALL BE FLUSHED IN COMPLIANCE WITH NFPA 13. THE FLUSHING IS REQUIRED TO BE WITNESSED BY AN ASSIGNED INSPECTOR FROM OUR OFFICE. THE FLUSHING OPERATION SHALL BE CONTINUED FOR A SUFFICIENT TIME TO ENSURE THOROUGH CLEANING. THE MINIMUM RATE OF FLOW SHALL BE NOT LESS THAN ONE OF THE FOLLOWING:



- THE HYDRAULICALLY CALCULATED WATER DEMAND RATE OF THE SYSTEM INCLUDING ANY HOSE REQUIREMENTS
- THAT FLOW NECESSARY TO PROVIDE A VELOCITY OF 10 FT / SEC. (4 INCH LINES – 380 GPM)
- THE MAXIMUM FLOW RATE AVAILABLE TO THE SYSTEM UNDER FIRE CONDITIONS.

8. THE NEW PROPOSED FIRE HYDRANT SHALL BE PAINTED IN ACCORDANCE WITH OUR COLOR-CODING SYSTEM. THE BODY OF THE HYDRANTS ARE REQUIRED TO BE PAINTED SILVER SINCE THEY ARE CONSIDERED PUBLIC HYDRANTS. THE TOP OF THE HYDRANT SHALL BE PAINTED BASED ON THE FIRE FLOW COLOR CODING SYSTEM ONCE CONFIRMED. IN GENERAL, IF THE AVAILABLE HYDRANT FIRE FLOW IS OVER 1,500 GPM THE TOP OF THE HYDRANTS SHALL BE PAINTED BLUE. UPON FLOW TESTING THE NEW HYDRANT, IF THE FLOW IS LESS THAN 1,500-GPM, WE CAN ASSIST WITH THE CORRECT COLOR CODING. A BLUE STREET REFLECTOR SHALL ALSO BE INSTALLED NEAR THE HYDRANT IN THE CENTER OF THE ACCESS DRIVE PRIOR TO THE FIRE FINAL INSPECTION.

9. ADDRESSING AND BUILDING IDENTIFICATION SHALL BE PROVIDED IN FULL COMPLIANCE WITH THE INTERNATIONAL FIRE CODE (IFC).

LEGEND

- EXISTING MINOR CONTOURS
- EXISTING MAJOR CONTOURS
- PROPOSED CONTOURS
- EXISTING OVERHEAD ELECTRIC
- EXISTING UNDERGROUND TELEPHONE
<



LEGEND


- EXISTING MINOR CONTOURS
- EXISTING MAJOR CONTOURS
- PROPOSED CONTOURS MINOR
- PROPOSED CONTOURS MAJOR
- EXISTING OVERHEAD ELECTRIC
- EXISTING UNDERGROUND TELEPHONE
- EXISTING UNDERGROUND GAS
- EXISTING WATER LINE
- EXISTING WASTEWATER LINE
- PROP. PRIVATE WATER LINE
- PROP. PRIVATE WASTEWATER LINE
- PROP. STORM SEWER LINE
- EXISTING POWER POLE
- EXISTING WATER METER
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- PROP. WATER METER
- PROP. GATE VALVE
- EXISTING GATE VALVE
- PROP. GATE VALVE
- ROW CURVE NUMBER
- WATER LINE CURVE NUMBER





LEGEND

- NATURAL GROUND RT.
 - NATURAL GROUND &
 - NATURAL GROUND LT.
 - PROP. T/C
 - LT. & RT.
- PROFILE SCALE:
HORIZ. 1" = 20'
VERT. 1" = 2'

WATER LINE 'A'




WATER LINE 'B'





THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512-328-0002)
www.tleng.net email: rlc@tleng.net

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
WATER PLAN & PROFILE (1 OF 2)


PROJECT	DATE ISSUED
PROJECT	August, 2025
DRAWN BY	DRAFTED BY
RCT	BH
JOB NUMBER	SHEET
1959	8 OF 16



WATERLINE "C"



WATERLINE "D"




SCALE: 1" = 20'

- LEGEND**
- EXISTING MINOR CONTOURS
 - EXISTING MAJOR CONTOURS
 - PROPOSED CONTOURS MINOR
 - PROPOSED CONTOURS MAJOR
 - EXISTING OVERHEAD ELECTRIC
 - EXISTING UNDERGROUND TELEPHONE
 - EXISTING UNDERGROUND GAS
 - EXISTING WATER LINE
 - EXISTING WASTEWATER LINE
 - PROP. PRIVATE WATER LINE
 - PROP. PRIVATE WASTEWATER LINE
 - PROP. STORM SEWER LINE
 - EXISTING POWER POLE
 - EXISTING WATER METER
 - EXISTING FIRE HYDRANT
 - PROPOSED FIRE HYDRANT
 - PROP. WATER METER
 - EXISTING GATE VALVE
 - PROP. GATE VALVE
 - ROW CURVE NUMBER
 - WATER LINE CURVE NUMBER




- LEGEND**
- NATURAL GROUND RT.
 - NATURAL GROUND &
 - NATURAL GROUND LT.
 - PROP. T/C
 - LT. & RT.
- PROFILE SCALE:
HORIZ. 1" = 20'
VERT. 1" = 2'





THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512-328-0002)
email: ric@tleng.net
www.tleng.net

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
WATER PLAN & PROFILE (2 OF 2)

PROJECT: 8/20/25
DATE ISSUED: August, 2025
DESIGNED BY: RCT
CHECKED BY: BH
JOB NUMBER: 1959
SHEET: 9 OF 16



FORCEMAIN PROFILE



LEGEND	
	EXISTING MINOR CONTOURS
	EXISTING MAJOR CONTOURS
	PROPOSED CONTOURS MINOR
	PROPOSED CONTOURS MAJOR
	EXISTING OVERHEAD ELECTRIC
	EXISTING UNDERGROUND TELEPHONE
	EXISTING UNDERGROUND GAS
	EXISTING WATER LINE
	EXISTING WASTEWATER LINE
	PROP. PRIVATE WATER LINE
	PROP. PRIVATE WASTEWATER LINE
	PROP. STORM SEWER LINE
	EXISTING POWER POLE
	EXISTING WATER METER
	EXISTING FIRE HYDRANT
	PROPOSED FIRE HYDRANT
	PROP. WATER METER
	EXISTING GATE VALVE
	PROP. GATE VALVE
	ROW CURVE NUMBER
	WATER LINE CURVE NUMBER




LEGEND	
	NATURAL GROUND RT.
	NATURAL GROUND LT.
	NATURAL GROUND LT.
	PROP. T/C LT. & RT.
PROFILE SCALE:	
HORIZ. 1" = 20'	
VERT. 1" = 2'	

Professional Engineer Seal for Robert C. Thompson, State of Texas, License No. 69524. The seal includes the text "Thompson Land Engineering, LLC (F-10220)".

THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512)328-0002
www.tleng.net email: ric@tleng.net

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
PROJECT
DATE ISSUED
August, 2025
DESIGNED BY
RCT
DRAFTED BY
BH
JOB NUMBER
1959
SHEET
10 OF 16



1 ON-SITE WASTEWATER PLAN

SCALE: 1:20

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
LIFT STATION AND FORCE MAIN
GENERAL CONSTRUCTION NOTES
TCEQ-0591 (REV. 2-26-2016)

EDWARDS AQUIFER PROTECTION PROGRAM CONSTRUCTION NOTES - LEGAL DISCLAIMER


THE FOLLOWING LISTED "CONSTRUCTION NOTES" ARE INTENDED TO BE ADVISORY IN NATURE ONLY AND DO NOT CONSTITUTE AN APPROVAL OR CONDITIONAL APPROVAL BY THE EXECUTIVE DIRECTOR (ED), NOR DO THEY CONSTITUTE A COMPREHENSIVE LISTING OF RULES OR CONDITIONS TO BE FOLLOWED DURING CONSTRUCTION. FURTHER ACTIONS MAY BE REQUIRED TO ACHIEVE COMPLIANCE WITH TCEQ REGULATIONS FOUND IN TITLE 30, TEXAS ADMINISTRATIVE CODE (TAC), CHAPTERS 213 AND 217, AS WELL AS LOCAL ORDINANCES AND REGULATIONS PROVIDING FOR THE PROTECTION OF WATER QUALITY. ADDITIONALLY, NOTHING CONTAINED IN THE FOLLOWING LISTED "CONSTRUCTION NOTES" RESTRICTS THE POWERS OF THE ED, THE COMMISSION OR ANY OTHER GOVERNMENTAL ENTITY TO PREVENT, CORRECT, OR CURTAIL ACTIVITIES THAT RESULT OR MAY RESULT IN POLLUTION OF THE EDWARDS AQUIFER OR HYDROLOGICALLY CONNECTED SURFACE WATERS. THE HOLDER OF ANY EDWARDS AQUIFER PROTECTION PLAN CONTAINING "CONSTRUCTION NOTES" IS STILL RESPONSIBLE FOR COMPLIANCE WITH TITLE 30, TAC, CHAPTERS 213 OR ANY OTHER APPLICABLE TCEQ REGULATION, AS WELL AS ALL CONDITIONS OF AN EDWARDS AQUIFER PROTECTION PLAN THROUGH ALL PHASES OF PLAN IMPLEMENTATION. FAILURE TO COMPLY WITH ANY CONDITION OF THE ED'S APPROVAL, WHETHER OR NOT IN CONTRADICTION OF ANY "CONSTRUCTION NOTES" IS A VIOLATION OF TCEQ REGULATIONS AND ANY VIOLATION IS SUBJECT TO ADMINISTRATIVE RULES, ORDERS, AND PENALTIES AS PROVIDED UNDER TITLE 30, TAC § 213.10 (RELATING TO ENFORCEMENT). SUCH VIOLATIONS MAY ALSO BE SUBJECT TO CIVIL PENALTIES AND INJUNCTION. THE FOLLOWING LISTED "CONSTRUCTION NOTES" IN NO WAY REPRESENT AN APPROVED EXCEPTION BY THE ED TO ANY PART OF TITLE 30 TAC, CHAPTERS 213 AND 217, OR ANY OTHER TCEQ APPLICABLE REGULATION.

- THIS LIFT STATION AND/OR FORCE MAIN MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.5(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) EDWARDS AQUIFER RULES, AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.
- ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED LIFT STATION/FORCE MAIN (LSFM) SYSTEM APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF A LSFM SYSTEM APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.
- A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
 - THE NAME OF THE APPROVED PROJECT;
 - THE ACTIVITY START DATE; AND
 - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- UPON COMPLETION OF ANY LIFT STATION EXCAVATION, A GEOLOGIST MUST CERTIFY THAT THE EXCAVATION HAS BEEN INSPECTED FOR THE PRESENCE OF SENSITIVE FEATURES. THE CERTIFICATION MUST BE SIGNED, SEALED, AND DATED BY THE GEOLOGIST PREPARING THE CERTIFICATION. CERTIFICATION THAT THE EXCAVATION HAS BEEN INSPECTED MUST BE SUBMITTED TO THE APPROPRIATE REGIONAL OFFICE.
 - IF SENSITIVE FEATURE(S) ARE IDENTIFIED, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY AND MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY FROM THE LIFT STATION.
 - CONSTRUCTION MAY CONTINUE IF THE GEOLOGIST CERTIFIES THAT NO SENSITIVE FEATURE OR FEATURES WERE PRESENT.
- IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERY. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING WITHIN TWO WORKING DAYS. THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRUCTURAL INTEGRITY OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.
- ALL FORCE MAIN LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC §217.66. TESTING METHOD WILL BE:
 - A PRESSURE TEST MUST USE 50 POUNDS PER SQUARE INCH ABOVE THE NORMAL OPERATING PRESSURE OF A FORCE MAIN.
 - A TEMPORARY VALVE FOR PRESSURE TESTING MAY BE INSTALLED NEAR THE DISCHARGE POINT OF A FORCE MAIN AND REMOVED AFTER A TEST IS SUCCESSFULLY COMPLETED.
 - A PUMP ISOLATION VALVE MAY BE USED AS AN OPPOSITE TERMINATION POINT.
 - A TEST MUST INVOLVE FILLING A FORCE MAIN WITH WATER.
 - A PIPE MUST HOLD THE DESIGNATED TEST PRESSURE FOR A MINIMUM OF 4.0 HOURS.
 - THE LEAKAGE RATE MUST NOT EXCEED 10.0 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER DAY.

AUSTIN REGIONAL OFFICE
12100 PARK 35 CIRCLE, BUILDING A
AUSTIN, TEXAS 78753-1808
PHONE (512) 339-2929
FAX (512) 339-3795



SAN ANTONIO REGIONAL OFFICE
14250 JUDSON ROAD
SAN ANTONIO, TEXAS 78233-4480
PHONE (210) 490-3096
FAX (210) 545-4329

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.



2 ON-SITE WASTEWATER PLAN

SCALE: 1:20




THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512) 328-0002
www.tleng.net
email: ric@tleng.net
Texas Reg. No. 131020 © Copyright 2012

DATE
REVISION

MOORE ESTATES SUBD IMPROVEMENTS
8103 WEST LAKE DR WESTLAKE HILLS, TX 78746
ON-SITE PRIVATE WASTEWATER PLAN

PROJECT
DATE ISSUED
August, 2025
DESIGNED BY
RCT
DRAFTED BY
BH
JOB NUMBER
1959
SHEET
11 OF 16



- A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
 - THE NAME OF THE APPROVED PROJECT;
 - THE ACTIVITY START DATE; AND
 - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.
- IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SINK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES MAY NOT BE RESUMED UNTIL THE TCQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.
- NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
- PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN COMPLIANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
- ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
- SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
- LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
- ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARDS AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE OTHER SITE.
- IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
- THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCQ UPON REQUEST:
 - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
 - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
 - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
- THE HOLDER OF ANY APPROVED EDWARD AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
 - ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
 - ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
 - ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

AUSTIN REGIONAL OFFICE
12100 PARK 35 CIRCLE, BUILDING A
AUSTIN, TEXAS 78753-1808
PHONE: (512) 339-2929
FAX: (512) 339-3795

SAN ANTONIO REGIONAL OFFICE
14250 JUDSON ROAD
SAN ANTONIO, TEXAS 78233-4480
PHONE: (210) 490-3096
FAX: (210) 542-3328

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: Moore Estates Subd Improvements
Data Prepared: 8/25/2025
Updated:

1. The Required Load Reduction for the total project:

Page 3-29 Equation 3.3: $L_{\text{req}} = 27.2(A_{\text{p}} \times P)$ Calculations from RG-348 Pages 3-27 to 3-30

where:

L_{req} = Required TSS removal resulting from the proposed development = 80% of increased load
 A_{p} = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County	Travis
Total project area included in plan	1.623 acres
Predevelopment impervious area within the limits of the plan	0.000 acres
Total post-development impervious area within the limits of the plan	0.000 acres
Total post-development impervious cover fraction	0.000
P	3.2
L_{req} total project	289 lbs.

Number of drainage basins / outfalls areas leaving the plan area = 2

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No.	1	2
Total drainage basin/outfall area	0.833 acres	7.490 acres
Predevelopment impervious area within drainage basin/outfall area	0.000 acres	0.000 acres
Post-development impervious area within drainage basin/outfall area	0.297 acres	0.000 acres
Post-development impervious fraction within drainage basin/outfall area	0.36	0.00
L_{req} this basin	289 lbs.	0

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Vegetated Filter Strips
Removal efficiency = 85 percent

4. Calculate Maximum TSS Load Removed (L_{r}) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-30 Equation 3.7: $L_{\text{r}} = (\text{BMP efficiency}) \times P \times (A_{\text{p}} \times 34.6 + A_{\text{p}} \times 0.54)$

where:

A_{p} = Total On-Site drainage area in the BMP catchment area
 A_{p} = Impervious area proposed in the BMP catchment area
 A_{p} = Pervious area remaining in the BMP catchment area
 L_{r} = TSS Load removed from this catchment area by the proposed BMP

	1	2
A_{p}	0.833 acres	
A_{p}	0.297 acres	
A_{p}	0.536 acres	
L_{r}	289 lbs.	

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L_{r} per basin	289 lbs.
F	1.00

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Calculations from RG-348 Pages 3-36 to 3-37

	1	2
Post Development Runoff Coefficient	0.40	
On-site Water Quality Volume	3.27	
Off-site area draining to BMP	0.439 acres	
Off-site impervious cover draining to BMP	0.141 acres	
Impervious fraction of off-site area	0.32	
Off-site Runoff Coefficient	0.27	
Off-site Water Quality Volume	174.4	
Storage for Sediment	1967	
Total Capture Volume (required water quality volume) x 1.20	6403	


15. Vegetated Filter Strips

Designed as Required in RG-348 Pages 3-35 to 3-37

FOR THE WPAP, THIS PROJECT IS ONLY INSTALLING THE SHARED DRIVEWAY AND ASSOCIATED VFS FOR THE OVERALL SUBDIVISION. ANY FUTURE DEVELOPMENT ON THE LOTS WILL BE REQUIRED TO FILE A MODIFIED WPAP PERMIT(S) (AS WELL AS THE SC'S) FOR EACH HOME, AS (AND/OR IF) THEY BECOME AVAILABLE IN THE FUTURE (LOTS 1 THROUGH 6).

ENGINEERED VEGETATIVE FILTER STRIP (VFS) TCQ NOTES:

- THE FILTER STRIP SHOULD EXTEND ALONG THE ENTIRE LENGTH OF THE CONTRIBUTING AREA AND THE SLOPE SHOULD NOT EXCEED 20%. THE MINIMUM DIMENSION OF THE FILTER STRIP (IN THE DIRECTION OF FLOW) SHOULD BE NO LESS THAN 15 FEET, THE MAXIMUM WIDTH (IN THE DIRECTION OF FLOW) OF THE CONTRIBUTING IMPERVIOUS AREA SHOULD NOT EXCEED 72 FEET. FOR ROADWAYS WITH A VEGETATED STRIP ALONG BOTH SIDES THE TOTAL WIDTH OF THE ROADWAY SHOULD NOT EXCEED 144 FEET (I.E. 72 FEET DRAINING TO EACH SIDE).
- THE MINIMUM VEGETATED COVER FOR ENGINEERED STRIPS IS 90%.
- THE AREA CONTRIBUTING RUNOFF TO A FILTER STRIP SHOULD BE RELATIVELY FLAT SO THAT THE RUNOFF IS DISTRIBUTED EVENLY TO THE VEGETATED AREA WITHOUT THE USE OF A LEVEL SPREADER.
- THE AREA TO BE USED FOR THE STRIP SHOULD BE FREE OF GULLIES OR RILLS THAT CAN CONCENTRATE OVERLAND FLOW (SCHUELER, 1987).
- THE TOP EDGE OF THE FILTER STRIP ALONG THE PAVEMENT WILL BE DESIGNED TO AVOID THE SITUATION WHERE RUNOFF WOULD TRAVEL ALONG THE TOP OF THE FILTER STRIP, RATHER THAN THROUGH IT.
- TOP EDGE OF THE FILTER STRIP SHOULD BE LEVEL. OTHERWISE RUNOFF WILL TEND TO FORM A CHANNEL IN THE LOW SPOT. A LEVEL SPREADER SHOULD NOT BE USED TO DISTRIBUTE RUNOFF TO AN ENGINEERED FILTER STRIP.
- FILTER STRIPS SHOULD BE LANDSCAPED AFTER OTHER PORTIONS OF THE PROJECT ARE COMPLETED.



LEGEND

- 88. TREE TO REMAIN
- 94. STORM WATER FLOW DIRECTIONAL ARROWS
- HERITAGE TREE
- EXISTING MINOR CONTOURS
- EXISTING MAJOR CONTOURS
- PROPOSED CONTOURS MINOR
- PROPOSED CONTOURS MAJOR
- EXISTING OVERHEAD ELECTRIC
- UT EXISTING UNDERGROUND TELEPHONE
- G EXISTING UNDERGROUND GAS
- W EXISTING WATER LINE
- W EXISTING WASTEWATER LINE
- PP EXISTING POWER POLE
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- EXISTING WATER METER
- PROP. WATER METER
- EXISTING GATE VALVE
- GV PROP. GATE VALVE

!!! WARNING !!!:
UNDERGROUND UTILITIES SHOWN ON THESE PLANS IS A BEST ESTIMATE BASED ON RECORDS THAT COULD BE OBTAINED AND PHYSICAL FEATURES VISIBLE AT THE GROUND LEVEL. THE ENGINEER MAKES NO ASSERTIONS BEYOND THAT THEY ARE A BEST ESTIMATE AND AN ATTEMPT TO HELP IDENTIFY POSSIBLE UTILITIES IN THE AREA. THE CONTRACTOR MUST CALL ONE CALL IN ACCORDANCE WITH THE NOTES TO BETTER LOCATE ANY UNDERGROUND UTILITIES.

8/26/25

Thompson Land Engineering, LLC (F-10220)











ROBERT C. THOMPSON
69524
REGISTERED PROFESSIONAL ENGINEER






DATE ISSUED: August, 2025

DESIGNED BY: RCT
DRAWN BY: BH

JOB NUMBER: 1959


SHEET: 12 OF 16






CONCRETE
PAVEMENT CONTROL JOINT

SCALE: 1" = 0.5' FOR 6" THICKNESS SHOWN




DOWEL- CONCRETE PAVEMENT
EXPANSION JOINT DETAIL

SCALE: N.T.S.




PAVEMENT SECTIONS

SCALE: 1" = 1'




TYPICAL STREET SECTION - CURB & GUTTER

SCALE: 1"=4'





TYP. SECTION THRU
EXIST. AND NEW ASPHALT PAVEMENT

SCALE: 1" = 1'



AIR RELEASE AND AIR/VACUUM VALVE



THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512-328-0002)
www.tleng.net
email: rlc@tleng.net

DATE	
REVISION	

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
WATER & WASTEWATER DETAILS (2 OF 2)

PROJECT	DATE ISSUED
DESIGNED BY	August, 2023
DRAWN BY	BY
JOB NUMBER	1959
SHEET	14 OF 16

Force Main Calculations
(Based on UCM 2.6.2(b))

GIVENS:

- General Data
1 ac, Drainage Area (DA) to Lift Station (for infiltration) (Assumed; cut off by road & groundwater going under)
SF Use (SF, MF, O/Ware, Retail)
if O/Ware or Retail
N/A Floor Area (sf)
if SF or MF
1 Units (Checking least flow version (one house))

- Elevation Data
703.00 Pump Discharge Flowline (approximate for house on Lot 1)
693.08 Forcemain Discharge Flowline (Ed) (see plans)
709.76 High Point (on public) (see plans)
691.58 Low Point (on public) (see plans)

- Pipe Data
Type "A": PVC, ASTM D2241, SDR-PR, SDR 21(200)
2 in, Size "A" (Force Main diameter)
400,000 psi, E (Young's Modulus)
0.09 in, "A" Pipe Wall Thickness (t) (392 public and 640 private)
1,022 ft, Length "A"

- Pump Data
20 gpm, Pump Rate (Pump Rate to get 2 fps)
0.045 cfs, Pump Rate
65 gal, Pump on Volume (Von)
49 gal, Pump off Volume (Voff)

COMPUTATIONS

1) Peaking Factors

$$PF(max) = [18 + (pop/1,000)^{0.5}] / [4 + (pop/1,000)^{0.5}]$$
$$PF(min) = 0.2 * (pop/1,000)^{0.198}$$

where:
pop = 3.50

therefore:
PF(max) = 4.45
PF(min) = 0.07

2) Flow Rates

a) Avg Dry Weather Flow (Qd) per 2.6.2 B

where:
SF = Use
1 = Units or Floor Area (as applicable)

therefore:
Qd = 350 gpd

b) Equivalent Population (pop)

$$pop = Qd / (100 \text{ gal/cap/day})$$

therefore:
pop = 3.5

c) Infiltration (Qi)

$$Qi = 1,500 \text{ gpd/ac} * DA$$

where:
DA = 1 ac

therefore:
Qi = 1,500 gpd

d) Max Wet Weather Flow (Qw(max))

$$Qw(max) = pop * 100 \text{ ppcd} * PF(max) + Qi$$

where:
pop = 3.50
PF(max) = 4.45
Qi = 1,500 gpd

therefore:
Qw(max) = 3,057 gpd
or
2.1 gpm

e) Max Dry Weather Flow (Qd(max))

$$Qd(max) = pop * 100 \text{ ppcd} * PF(max)$$

where:
pop = 3.50
PF(max) = 4.45

therefore:
Qd(max) = 1,557 gpd

f) Min Dry Weather Flow (Qd(min))

$$Qd(min) = pop * 100 \text{ ppcd} * PF(min)$$

where:
pop = 3.50
PF(min) = 0.07


therefore:
Qd(min) = 23 gpd

3) Force Main Velocities

$$V = P / (3.1415 * d^2 / 4)$$

where:
P = 0.045 cfs
d = 2 in (Line A)

therefore:
V = 2.0 fps (Line A)



1 EMERGENCY FIRE PROTECTION PLAN

SCALE: 1:40

4) Water Hammer

a) pressure wave velocity (a)

$$a = 12 / [(1/1,9379 * (1/300,000 + d/(E * t)))]$$

where:
d = 2 in (Line A)
E = 400,000 psi
t = 0.09 in (Line A)

therefore:
a = 1123 fps (Line A)

b) Surge Pressure (Ps)

$$Ps = a * V / 74.382$$

therefore:

30.8 psi (Line A)

5) Total Head

a) Elevation Head (He)

$$He = Ed - Es$$

where:
Ed = 693.08 (Forcemain Discharge Elevation)
Ed = 709.76 Highest FM elevation
Es = 703.00 Lowest Pump Discharge Elev (Estimated)

therefore:
He = 6.76 ft

b) Friction Loss (f)

$$f = (V^{1.85} * L) / [(1.318 * 150)^{1.85} * (d/412)^{1.17}]$$

where:
V = 2.0 fps (Line A)
L = 1022 ft (Line A)
d = 2 in (Line A)

therefore:
f = 8.92 ft (Line A)

c) Total Head (H)

Note: ignoring minor losses in fittings, entrance, exit




$$H = He + F(a)$$

therefore:
15.68 ft
or:
6.80 psi


d) Velocity Head (Hv)

$$Hv = V^2 / (2 * 32.2)$$

Hv = 0.06 ft (Line A)



SCALE: 1" = 40'



LEGEND


HOSE PULL FIRE HYDRANT
HOSE PULL DISTANCE

THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 140062, Austin, Texas 78716 (512) 328-0002
email: ric@tleng.net
www.tleng.net


DATE	
REVISION	

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
PROJECT
WATER & WASTEWATER CALCULATIONS
SHEET NAME

DATE ISSUED	August, 2025
DESIGNED BY	RC
DRAFTED BY	BH
JOB NUMBER	1959
SHEET	15 OF 16




8/20/25



1 EXISTING DRIVEWAY DEMOLITION
SCALE: 1"=30'

LEGEND	
	TREE TO REMAIN
	TREE TO BE REMOVED
	PROTECTED TREE
	HERITAGE TREE
	TREE PROTECTION
	EXISTING WATER METER
	EXISTING FIRE HYDRANT
	EXISTING GATE VALVE
	EXISTING POWER POLE
	HATCHED ITEMS TO BE DEMOLISHED AND REMOVED
	STABILIZED CONSTRUCTION ENTRANCE
	CONSTRUCTION STAGING AND TEMP. SPOILS AREA
	LIMITS OF CONSTRUCTION
	EROSION CONTROL SILT FENCE
	EROSION CONTROL MULCH SOCK
	TRIANGULAR FILTER DIKE
	ROCK BERM
	STORM INLET PROTECTION
	EXISTING MINOR CONTOURS
	EXISTING MAJOR CONTOURS
	PROPOSED CONTOURS
	EXISTING OVERHEAD ELECTRIC
	EXISTING UNDERGROUND TELEPHONE
	EXISTING UNDERGROUND GAS
	EXISTING WATER LINE
	EXISTING WASTEWATER LINE

!!! NOTICE !!!
IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY RESUMES PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.



THOMPSON LAND ENGINEERING, LLC
Land Planning, Site Design, Subdivision Engineering
P.O. Box 160062, Austin, Texas 78716 (512) 328-0002
www.tleng.net email: ric@tleng.net
Texas Reg. No. F12020 © Copyright 2012

MOORE ESTATES SUBD IMPROVEMENTS
803 WEST LAKE DR WEST LAKE HILLS, TX 78746
DEMOLITION DRIVEWAY

PROJECT	DATE ISSUED
803 WEST LAKE DR WEST LAKE HILLS, TX 78746	August, 2025
DESIGNED BY	DRAFTED BY
RCT	BH
JOB NUMBER	SHEET NAME
1959	DEMOLITION DRIVEWAY
SHEET	
16 OF 16	