

# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

**The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).**

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited.**
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

**Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name: Keith Wing Two-Story Office</b>					<b>2. Regulated Entity No.: TBD</b>				
<b>3. Customer Name: 4 Wing Holding, LLC</b>					<b>4. Customer No.: TBD</b>				
<b>5. Project Type:</b> (Please circle/check one)		<input checked="" type="radio"/> New	Modification			Extension		Exception	
<b>6. Plan Type:</b> (Please circle/check one)		<input checked="" type="radio"/> WPAP	<input type="radio"/> CZP	<input type="radio"/> SCS	<input type="radio"/> UST	<input type="radio"/> AST	<input type="radio"/> EXP	<input type="radio"/> EXT	Technical Clarification Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)		<input type="radio"/> Residential	<input checked="" type="radio"/> Non-residential			<b>8. Site (acres):</b>		2.54	
<b>9. Application Fee:</b>		\$4,000		<b>10. Permanent BMP(s):</b>			Batch Detention Basin		
<b>11. SCS (Linear Ft.):</b>					<b>12. AST/UST (No. Tanks):</b>		N/A		
<b>13. County:</b>		Comal		<b>14. Watershed:</b>			Dry Comal Creek		



# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

<b>Austin Region</b>			
<b>County:</b>	<b>Hays</b>	<b>Travis</b>	<b>Williamson</b>
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

<b>San Antonio Region</b>					
<b>County:</b>	<b>Bexar</b>	<b>Comal</b>	<b>Kinney</b>	<b>Medina</b>	<b>Uvalde</b>
Original (1 req.)	—	<input checked="" type="checkbox"/>	—	—	—
Region (1 req.)	—	<input checked="" type="checkbox"/>	—	—	—
County(ies)	—	<input checked="" type="checkbox"/>	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input checked="" type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input checked="" type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Joseph T. Sandoval, P.E.

Print Name of Customer/Authorized Agent

*Joseph Sandoval, P.E.*      *Feb. 10, 2023*

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# General Information Form

## Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Joseph T. Sandoval, P.E.

Date: Feb. 10, 2023

Signature of Customer/Agent:

Joseph Sandoval, P.E.



## Project Information

1. Regulated Entity Name: Keith Wing Two-Story Office
2. County: Comal
3. Stream Basin: N/A
4. Groundwater Conservation District (If applicable): Edwards Aquifer Authority
5. Edwards Aquifer Zone:
  - Recharge Zone
  - Transition Zone
6. Plan Type:
  - WPAP
  - SCS
  - Modification
  - AST
  - UST
  - Exception Request

7. Customer (Applicant):

Contact Person: Keith Wing

Entity: 4 Wing Holding, LLC

Mailing Address: 2027 State Highway 46 West, Suite 106

City, State: New Braunfels, TX

Zip: 78132

Telephone: 830.266.9464

FAX: N/A

Email Address: \_\_\_\_\_

8. Agent/Representative (If any):

Contact Person: Joseph T. Sandoval, P.E.

Entity: HMT Engineering & Surveying

Mailing Address: 290 S. Castell

City, State: New Braunfels, TX

Zip: 78130

Telephone: 830-625-8555

FAX: N/A

Email Address: josephs@hmtnb.com

9. Project Location:

- The project site is located inside the city limits of New Braunfels.
- The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_\_.
- The project site is not located within any city's limits or ETJ.

10.  The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

Beginning at TCEQ San Antonio regional office, head south on Judson Road towards Willa Camino, turn left onto I-35 Frontage Road, take the ramp on the left on I-35 North. Take exit 184 toward TX-337 Loop/Farm to Market Rd 482/Ruckle Rd, merge onto I-35 Frontage Road, and turn left onto TX-337 Loop N/S Ruckle Rd. Turn right onto Ridge Hill Dr

11.  **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12.  **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- Project site boundaries.
  - USGS Quadrangle Name(s).
  - Boundaries of the Recharge Zone (and Transition Zone, if applicable).
  - Drainage path from the project site to the boundary of the Recharge Zone.
13.  **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate

the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

Survey staking will be completed by this date: \_\_\_\_\_

14.  **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- Area of the site
- Offsite areas
- Impervious cover
- Permanent BMP(s)
- Proposed site use
- Site history
- Previous development
- Area(s) to be demolished

15. Existing project site conditions are noted below:

- Existing commercial site
- Existing industrial site
- Existing residential site
- Existing paved and/or unpaved roads
- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Uncleared)
- Other: \_\_\_\_\_

### ***Prohibited Activities***

16.  I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17.  I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:



- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

### ***Administrative Information***

18. The fee for the plan(s) is based on:

- For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
- For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
- For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
- A request for an exception to any substantive portion of the regulations related to the protection of water quality.
- A request for an extension to a previously approved plan.

19.  Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:

- TCEQ cashier
- Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
- San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)


20.  Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21.  No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.



Texas Commission-Environmental, 14250 Judson Drive 18.5 miles, 23 min  
 Rd, San Antonio, TX 78233 to 671 Ridge Hill Dr, New Braunfels, TX 78130

Taylor Office Complex - General Information Form (TCEQ-0587) Attachment A




Map data ©2022 Google 2 mi



**Texas Commission-Environmental**  
 14250 Judson Rd, San Antonio, TX 78233

**Get on I-35 N from Lookout Rd and N Loop 1604 E**







- \_\_\_\_\_ 7 min (3.5 mi)
- ↑ 1. Head southeast toward Judson Rd  
\_\_\_\_\_ 115 ft
- ↘ 2. Turn right toward Judson Rd  
\_\_\_\_\_ 85 ft
- ↙ 3. Turn left onto Judson Rd  
\_\_\_\_\_ 482 ft
- ↙ 4. Turn left to stay on Judson Rd  
\_\_\_\_\_ 0.1 mi
- ↙ 5. Turn left onto Lookout Rd  
\_\_\_\_\_ 1.6 mi
- ↘ 6. Turn right onto N Loop 1604 E  
\_\_\_\_\_ 499 ft
- ↑ 7. Continue straight to stay on N Loop 1604 E  
\_\_\_\_\_ 0.4 mi
- ↗ 8. Use the left lane to take the Texas 1604 Loop S ramp  
\_\_\_\_\_ 0.3 mi

-  9. Keep right at the fork, follow signs for I-35 N/Austin and merge onto I-35 N  
0.8 mi

**Follow I-35 N to N Interstate 35 Frontage Rd in New Braunfels. Take exit 184 from I-35 N**

- 11 min (12.5 mi)
-  10. Merge onto I-35 N  
12.3 mi
-  11. Take exit 184 toward TX-337 Loop/Farm to Market Rd 482/Rueckle Rd  
0.1 mi

**Take Loop 337 to Ridge Hill Dr**

- 4 min (2.6 mi)
-  12. Merge onto N Interstate 35 Frontage Rd  
0.2 mi
-  13. Use the left 2 lanes to turn left onto S Rueckle Rd  
305 ft
-  14. Continue onto Loop 337  
2.1 mi
-  15. Continue straight to stay on Loop 337  
0.2 mi
-  16. Slight right onto Ridge Hill Dr  
 Destination will be on the right  
194 ft

671 Ridge Hill Dr  
New Braunfels, TX 78130


These directions are for planning purposes only. You may find that construction projects, traffic, weather, or other events may cause conditions to differ from the map results, and you should plan your route accordingly. You must obey all signs or notices regarding your route.




+ 671 Ridge Hill Dr, New Braunfels X Q

- Show search results for 671 Ridge Hil...

**NEW BRAUNFELS WEST QUADRANGLE**  
TEXAS  
7.5 MINUTE SERIES (TOPOGRAPHIC)



**Edwards Aquifer  
Recharge Zone**



0 300 600ft

-98.164 29.704 Degrees

## GENERAL INFORMATION

### ATTACHMENT C

#### Project Description

The proposed Keith Wing Two-Story Office is located at 671 Ridge Hill Dr, New Braunfels, Texas. The development is located in Comal County within the City of New Braunfels. The development of the office complex will occur within the Mission Forest Subdivision Unit 3 plat on Lot 11. The total site area is 2.54 acres and is currently undeveloped. The proposed improvements include parking, driveways and office building. Also, the proposed improvements include the construction of 62 L.F. of 6" gravity wastewater line. The proposed condition impervious cover is 1.16 acres. The entire property is located within the Recharge Zone of the Edwards Aquifer. The total impervious cover percentage at the completion of the project is 46%.

A batch detention/water quality basin will be constructed in the office complex improvements as shown in Attachment F, of the Keith Wing Two-Story Office Permanent Storm Water Section. The batch detention basin is sized to provide the required volume and treatment for complete development of the site improvements.

The construction plans and required applications are hereby submitted for review.



# Geologic Assessment

## Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Matt Anding

Telephone: 832-641-8143

Date: 08/18/2022


Fax: \_\_\_\_\_

Representing: Anding Environmental Consulting, LLC (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



Regulated Entity Name: Keith Wing



## Project Information

1. Date(s) Geologic Assessment was performed: July 15, 2022

2. Type of Project:

WPAP  
 SCS

AST  
 UST

3. Location of Project:

Recharge Zone  
 Transition Zone  
 Contributing Zone within the Transition Zone

4.  **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5.  Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups\* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

**Table 1 - Soil Units, Infiltration Characteristics and Thickness**

Soil Name	Group*	Thickness(feet)
RUD	D	2'
ERG	C	1.5'

\* Soil Group Definitions (Abbreviated)

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6.  **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7.  **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
8.  **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'  
 Applicant's Site Plan Scale: 1" = 40'  
 Site Geologic Map Scale: 1" = 40'  
 Site Soils Map Scale (if more than 1 soil type): 1" = 40'
9. Method of collecting positional data:
  - Global Positioning System (GPS) technology.
  - Other method(s). Please describe method of data collection: \_\_\_\_\_
10.  The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11.  Surface geologic units are shown and labeled on the Site Geologic Map.

12.  Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
- Geologic or manmade features were not discovered on the project site during the field investigation.
13.  The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
- There are \_\_\_\_\_ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
- The wells are not in use and have been properly abandoned.
- The wells are not in use and will be properly abandoned.
- The wells are in use and comply with 16 TAC Chapter 76.
- There are no wells or test holes of any kind known to exist on the project site.

### ***Administrative Information***

15.  Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

---

**GEOLOGIC ASSESSMENT**

**ATTACHMENT A - GEOLOGIC ASSESSMENT TABLE**





---

**GEOLOGIC ASSESSMENT  
ATTACHMENT B - STRATIGRAPHIC COLUMN**

SITE STRATIGRAPHY  
(Person Formation Outcrop)

STRATIGRAPHIC COLUMN

Hydrogeologic subdivision		Group, formation, or member	Hydro-logic function	Thickness (feet)	Lithology	Field identification	Cavern development	Porosity/permeability type		
Upper Cretaceous	Upper confining unit	Taylor Group	CU	600	Clay; chalky limestone	Gray-brown clay; marly limestone	None	Low porosity/low permeability		
		Austin Group	CU; rarely AQ	130 – 150	White to light-tan to gray limestone	White, chalky limestone; <i>Pycnodonte aucella</i> <i>Inoceramus subquadratus</i>	None	Low porosity; rare water production from fractures/low permeability		
		Eagle Ford Group	CU	30 – 50	Brown, flaggy sandy shale and argillaceous limestone	Thin flagstones; petroliferous	None	Primary porosity lost/low permeability		
		Buda Limestone	CU	40 – 50	Buff, light-gray, dense mudstone	Porcelaneous limestone	Minor surface karst	Low porosity/low permeability		
		Del Rio Clay	CU	50 – 60	Blue-green to yellow-brown clay	Fossiliferous; <i>Ilymatogyra arietina</i>	None	None/primary upper confining unit		
I		Georgetown Formation	CU	40 – 60	Gray to light-tan, marly limestone	Marker fossil: <i>Waconella wacoensis</i>	None	Low porosity/low permeability		
Lower Cretaceous	Edwards aquifer	Edwards Group	Person Formation	Cyclic and marine members, undivided (4)	AQ	0 – 70	Mudstone to packstone; <i>miliolid</i> grainstone; chert	Boxwork vugs; light tan, massive; some <i>Toucasia</i> , <i>Caprinid</i> , and <i>Chondrodonta</i>	Many caves; might be associated with earlier karst development	Laterally extensive; both fabric and not fabric/water-yielding; one of the most porous and permeable; essentially absent in Travis County
				Leached and collapsed members, undivided (4)	AQ	30 – 80	Crystalline limestone; mudstone to wackestone to <i>miliolid</i> grainstone; chert; collapsed breccia	Light-gray, bioturbated iron-stained beds separated by massive limestone beds; <i>Toucasia</i> , <i>Chondrodonta</i>	Extensive lateral development; large rooms	Majority not fabric/one of the most porous and permeable
				Regional dense member (3)	CU	20 – 30	Light-tan, dense, argillaceous mudstone	Wispy iron-oxide stains; <i>Pleuromya knowltoni</i> , <i>Ceratostreon texanum</i>	None; only vertical fracture enlargement	Not fabric/low permeability; vertical barrier
		Kainer Formation	Grainstone member (2)	AQ	45 – 60	Light-gray, <i>miliolid</i> grainstone; mudstone to wackestone; chert	White crossbedded grainstone; <i>Toucasia</i> , <i>Turritella</i> , and <i>Chondrodonta</i>	Few caves	Not fabric/re-crystallization reduces permeability	
			Kirschberg evaporite member (1)	AQ	65 – 75	Light-gray, crystalline limestone; chalky mudstone; chert	Boxwork voids, with neospar and travertine frame; <i>Cladophyllia</i> and <i>Turritella</i>	Probably extensive cave development	Majority fabric/one of the most porous and permeable	
			Dolomitic member (1)	AQ	110 – 150	Mudstone to grainstone; crystalline limestone; chert	Massively bedded, light gray, <i>Toucasia</i> abundant; <i>Dictyoconus walnutensis</i> , <i>Caprinid</i>	Caves related to structure or bedding planes	Mostly not fabric; some bedding-plane fabric/water-yielding; locally permeable	
			Basal nodular member	Karst AQ; not karst CU	45 – 60	Shaly, fossiliferous, nodular limestone; mudstone; <i>miliolid</i> grainstone	Massive, nodular and mottled; <i>Ceratostreon texanum</i> , <i>Dictyoconus walnutensis</i> , and <i>Texigryphaea</i>	Few caves	Fabric/low permeability	
			Lower confining unit	Upper member of the Glen Rose Limestone	CU; evaporite beds AQ	350 – 500	Yellowish-tan, thinly bedded limestone and marl	Stair-step topography; alternating limestone and marl	Some surface cave development	Some water production at evaporite beds/relatively impermeable


---

**GEOLOGIC ASSESSMENT**  
**ATTACHMENT C - SITE GEOLOGY**





**GEOLOGIC ASSESSMENT**  
**671 Ridge Hill Drive**  
**New Braunfels, Comal County, Texas**



**Prepared for:**  
**Keith Wing Custom Builders**  
**Prepared by:**  
**Anding Environmental Consulting, LLC**  
**August 2022**



# Geologic Assessment

---

671 Ridge Hill Drive  
New Braunfels, Comal County, Texas

**Prepared for:**

Keith Wing Custom Builders  
2027 State Highway 46 West, Suite 106  
New Braunfels, TX 78130

Prepared by:



Anding Environmental Consulting, LLC.  
925 Lauren Street  
New Braunfels, TX 78130

August 2022



This page intentionally left blank.

## Table of Contents

1.0	INTRODUCTION AND PURPOSE.....	1
1.1	INTRODUCTION .....	1
1.2	PROJECT DESCRIPTION.....	1
2.0	METHODOLOGY .....	2
2.1	RESEARCH INFORMATION.....	2
2.2	FIELD SURVEY .....	2
2.3	DATA GAPS .....	2
2.4	LIMITATIONS OF ASSESSMENT .....	2
3.0	NARRATIVE DESCRIPTION OF SITE GEOLOGY .....	3
3.1	SITE CHARACTERIZATION.....	3
3.2	SITE GEOLOGY .....	3
3.3	SITE SOILS .....	4
3.4	SITE ASSESSMENT.....	5
4.0	SUMMARY .....	7
5.0	REFERENCES .....	8

## List of Tables

Table 3-1            Site Soils

## Attachments

Attachment A        Geologic Assessment Table  
Attachment B        Stratigraphic Column  
Attachment C        Site Geology and Geologic Assessment  
Attachment D        Site Geologic Maps  
Attachment E        Photo Log

## **Acronyms**

BMP	Best Management Practices
EAPP	Edwards Aquifer Protection Plan
FEMA	Federal Emergency Management Administration
GPS	Global Positioning System
TCEQ	Texas Commission on Environmental Quality
USDA	United States Department of Agriculture
USGS	United States Geological Survey

## 1.0 INTRODUCTION AND PURPOSE

---

### 1.1 Introduction

This Geologic Assessment was prepared in general accordance with to 30 TAC §213.5(b)(3), effective September 01, 2003, Texas Commission on Environmental Quality (TCEQ) requirements for regulated developments within the Edwards Aquifer Recharge Zone, and the “Instructions to Geologists”, TCEQ-0585-Instructions (Rev. 10-1-04). Per TCEQ guidance, a proposed project on the Site for future development of additional school facilities requires a Geologic Assessment to identify all potential pathways for contaminant movement to the Edwards Aquifer and provide sufficient geologic information so that the appropriate Best Management Practices (BMPs) can be proposed in the Edwards Aquifer Protection Plan (EAPP). This Geologic Assessment has been prepared by a Texas Board of Professional Geoscientists licensed geologist, Mr. Matt Anding, P.G.

### 1.2 Project Description

The Site is located at 671 Ridge Hill Drive, New Braunfels, TX 78130, near the intersection of Ridge Hill Drive and Loop 337. The center of the Site is located at 29°42'19.18"N Latitude and 98° 9'42.34"W Longitude (WGS 84), and the Site is ~2.45 acres in size. The Site is currently undeveloped. The property location is depicted on **Figure D-1**. A project is in place to develop the Site with a commercial business.

## **2.0 METHODOLOGY**

---

### **2.1 Research Information**

The Geologic Assessment was performed by Matt Anding, P.G., with Anding Environmental Consulting, LLC (Anding Environmental) on July 15, 2022. Anding Environmental first conducted a desktop analysis of the geology of the area surrounding the Site. The research included, but was not limited to, the Geologic Atlas of Texas, Federal Emergency Management Agency (FEMA) maps, Edwards Aquifer Recharge Zone Maps, USGS 7.5 Minute Quadrangle Maps, Bureau of Economic Geology online digital data, historic aerials and topographic maps, and the United States Department of Agriculture (USDA) Soil Survey of Comal County, Texas.

### **2.2 Field Survey**

After reviewing the available information, a field investigation was performed to identify any geologic or man-made potential recharge features. A transect spacing of approximately 25-50 feet, or less depending on Site vegetation, was used to inspect the Site. A 2020 aerial photograph, in conjunction with a hand held sub-meter Trimble GeoXH Global Positioning System (GPS), was used to navigate on the property and search for potential recharge features, as recommended in the “Instructions to Geologists”, TCEQ-0585-Instructions (Rev. 10-1-04). The Geologic Assessment Form, Stratigraphic Column, and the Geologic Assessment Table have been filled with the appropriate information for this Site and are included in this report. Special attention was given to the mapped faults, bedrock outcroppings, and other structural features mapped in the area.

### **2.3 Data Gaps**

No data gaps were incurred during the desktop analysis or field reconnaissance.

### **2.4 Limitations of Assessment**

No Geologic Assessment can wholly eliminate uncertainty regarding potential pathways for contaminant movement to the Edwards Aquifer in connection with a property. Performance of a Geologic Assessment in accordance with TCEQ-0585 instructions is intended to reduce, but cannot eliminate, uncertainty regarding the potential for surficial points of infiltration in connection with a property, and the TCEQ recognizes reasonable limits of time and cost.

Anding Environmental assumes no responsibility for the discovery of any surficial or subsurface points of infiltration, caves, solution cavities or enlarged fractures/faults, sinkholes, or any other karst features not observed during this Geologic Assessment. Anding Environmental does not have any responsibility with regard to the Client's compliance with or fulfillment of its obligation under any law, ordinance, or regulation prevailing at any of the observed locations.



## 3.0 NARRATIVE DESCRIPTION OF SITE GEOLOGY

---

### 3.1 Site Characterization

The Site is located on the edge of a broad sloping topographic high area that is currently undeveloped. The northern and central portions of the Site is largely open grass vegetation with oak trees, and the western, eastern, and southern portions of the Site are heavily vegetated with oak and ashe juniper trees and scrub brush.

The Site is bordered by Ridge Hill Drive to the north where site access is located with a curb-cut. The site is bordered by residential homes to the east and south, and the Loop 337 easement to the west.

Site topography consists of a broad bench reaching from the northern portion of the Site south through the center of the Site, with erosional drainage features on the east and west sides of the bench. Site topography tends to slope to the south along the bench, or to the erosional features to the west and east. The highest elevation is approximately 852 ft amsl at the northern Site corner. The lowest elevation is approximately 798 ft amsl at the southwestern Site boundary. Surface water tends to largely sheetflow from the northern portion of the Site towards the channeled erosional drainage features to the east and west, exiting the Site southwestern boundary through a culvert.

The Site vegetation for the upland portion of the Site consists of typical oak savannah vegetation, such as grasses, oak trees, and ashe juniper. Where the upland portion of the Site starts to slope down into the drainages, vegetation consists of mix scrub brush and cactus. The steep sloped drainages and bottoms are densely vegetated with oak, ash juniper, mountain laurel, and persimmon trees, along with grasses, cacti, and vines.

### 3.2 Site Geology

Per the TCEQ Edwards Aquifer Program GIS dataset, the entire Site is located within the Edwards Aquifer Recharge Zone. A map of the Site and Edwards Aquifer Zones is presented as **Figure D-4**.

The following resources were most utilized in mapping the Site geology:

- Digital Geologic Map Database for the State of Texas (USGS)
- 1982 Geologic Atlas of Texas, San Antonio Sheet (Bureau of Economic Geology)
- 1992 Geologic Map of Texas (Bureau of Economic Geology)
- 2007 Geology of the New Braunfels Area (Bureau of Economic Geology, Texas Water Development Board, and USGS)
- Geologic Framework and Hydrogeologic Characteristics of the Edwards Aquifer Outcrop, Comal County, Texas (USGS)
- Geologic Map of the Edwards Aquifer Recharge Zone, South-Central Texas (USGS)

High resolution geologic mapping in the Site area was best found in the 1982 Geologic Atlas of Texas, San Antonio Sheet (BEG) and the 2007 Geology of the New Braunfels Area (BEG, TWDB, USGS). The 1982 San Antonio Sheet maps the Site as largely Edwards Limestone Undivided

(Ked). The 2007 Geology of the New Braunfels Area figure maps the entire Site as the Person Member (Kp) of the Edwards Group.

**Person Member of Edwards Group** (Lower Cretaceous) - The entirety of the Site consists of the Person Cyclic and Marine Member of the Edwards Group. This is characterized as a chert-bearing mudstone to packstone and miliolid grainstone. This unit weathers to massive, light-tan outcrops with scattered toucasia present. This member is one of the most productive hydrologically because of the large number of subsurface caverns associated with incipient karstification. It can be very permeable with laterally extensive, fabric and nonfabric-selective porosity (Small and Hanson, 1995; Stein and Ozuna, 1995). Thickness 10–180 ft.

Edwards limestone outcroppings were observed throughout the Site. Typical outcroppings on the upland portions of the Site include minor bedding outcrops where soil has eroded and exposed bedding. Bedrock stair-step bluffs outcrop along the steep slopes of the drainages at approximately 816' AMSL. The bluff outcroppings range from 3' vertical solid bedrock to minor 12" bedrock ledges. The outcroppings are present throughout the drainages and are present due to stream-cut erosion and not any particular faulting trends.

The Site is located in the Balcones Fault Zone approximately 0.5 miles north of the main Balcones fault. Based on literature research and field reconnaissance, the Site has no known or inferred faults on the Site or immediate surrounding area. Anding Environmental observed no fault structures on the Site during the field reconnaissance. No evidence of fault structures were observed on historic aerial imagery.

A geologic map of the Site is presented as **Figure D-5**. Attachment E, Photo Log, displays photographs of typical outcroppings of the mapped geologic unit on Site.

### 3.3 Site Soils

The northern portion of the Site is covered with Rumble-Comfort (RUD) soils, and the southern portion of the Site is covered with Eckrant-Rock (ErG) soils. **Table 3-1** displays soils mapped on the Site and **Figure D-6** illustrates the soils in relation to the Site.

**Table 3-1 – Site Soils**

<b>RUD - Rumble-Comfort, rubbly association, 1% to 8% slopes</b>
<b>ErG - Eckrant-Rock outcrop association, 8% to 30% slopes</b>

**Rumble-Comfort, Rubbly Association (RUD)** – The northern portion of the Site is mapped as Rumble-Comfort, Rubbly Association (RUD) soils. RUD soils are on broad ridgetops and side slopes with gently sloping topography and more sloping areas near rock outcrops and drainage-ways. Rumble-Comfort, Rubbly Association soils (RUD) may have the surface covered with as much as 20 percent by volume of rounded chert, limestone fragments, gravels, and/or cobble. The surface soil layer is a dark reddish brown, very cherty loam, or gravelly clay loams to extremely cobbly clay loams that is about 10 inches thick. The subsoil (10-28 inches deep) is a dark reddish

brown very cherty clay to extremely cherty clay that may have up to 75 percent by volume of limestone fragments present in the lower part of the subsoil. The underlying material is coarsely fractured indurated limestone that has dark reddish brown soil in the crevices. The underlying material is 28-36 inches in depth. Bedrock can be below 28-29 inches. Rumble-Comfort, Rubbly Association soils are typically well drained with very high runoff class and moderately low to moderately high capacity to transmit water (USDA/NRCS, 2022).

**Eckrant-Rock outcrop association (ErG)** – The southern portion of the Site is mapped as Eckrant-Rock outcrop association soils. Eckrant-Rock soils tend to be shallow upland soils located on slopes. Topsoils are typically very dark gray or shades of dark brown and even black. ErG soils are very stony clays with many stone fragments ranging from 4” to 20” and can make up about 35% to 75% by volume of the soil horizon. These soils may be 10” thick and typically deposited on fractured limestone. The shallow soils are very well drained with limited soil moisture due to the lack of soil depth, abundance of limestone rocks, and slope location. (USDA/NRCS, 2022).

### 3.4 Site Assessment

Minor bedrock outcroppings were observed on the upland portion of the Site, bluff outcroppings are present along the top of the incised drainages, and slab bedrock is present in some portions of the drainage channels. No vuggy, highly-fractured, or other significant features with potential for rapid recharge were observed. No faulting was observed on the Site and the nearest mapped faults are located 0.9 miles to the northwest, or 0.5 miles to the south at the main Balcones Fault.

Anding Environmental observed three (3) potential recharge features during the Site reconnaissance. All 3 solution cavities observed on the Site are approximately located along the same elevation at the bottom of the outcropping bluffs on the drainage slopes. Details regarding these features can be found in the Attachment A Geologic Assessment Table, Photo Log, and Figure D-7 Geologic Findings.

**SC-1 Sensitive**     **Solution Cavity:** SC-1 consists of a horizontal solution cavity located at the bottom of the streamcut bluff on the northern slopes of the Site’s southern drainage. The solution cavity is located below a 3” collapsed bed of chert within fractured stair-step bedrock. The cavity is approximately 3.5’ wide, 1’ tall, and extends over 3’ horizontally back into the bedding plane before petering out. The cavity is currently being used as an animal burrow, as recently disturbed soil was observed to have been dug out of the cavity. Well developed, thin fine dark brown ErG soils were observed to fill the cavity, which has a solid bedrock bottom with no observed significant fracturing or additional cavities. The cavity does not appear to act as a significant rapid flowpath for surface water to the aquifer due to its’ positioning on the stair step ledges on top of the drainage. Surface water would appear to flow over the ledge and continue down the slope into the drainage. No soil, vegetation, or erosional evidence indicating flow into the cavity was observed. However, due to the width of the feature and that the entire cavity is not observable, it is Anding Environmental’s professional judgement that the solution cavity may have an intermediate probability of rapid infiltration, and should be considered a potentially sensitive feature.

**SC-2**      **Solution Cavity:** SC-2 consists of a vertical solution cavity located on a stair-step  
**Sensitive** ledge on the northern slopes of the Site's southern drainage, just outside of the southwestern Site boundary. The solution cavity is located within horizontal bedrock. The cavity is approximately 1.6' long, 0.6' wide, and extends over 2.5' vertically into bedrock. Due to how narrow the cavity is, Anding Environmental was only able to dig and reach to 2.5' in depth, however, it appears that the cavity extends further down into bedrock. Well developed, thin fine light brown ErG soils were observed to surround the cavity, and infill includes breakdown and some soil. The cavity does not appear to act as a significant rapid flowpath for surface water to the aquifer due to its' positioning on the stair step ledges on top of the drainage. Surface water appears to sheetflow down the slope into the drainage. No erosional channel or other indicators of significant water flow into the cavity were observed, although small amounts of localized surface water would flow into the cavity. It is Anding Environmental's professional judgement that the solution cavity may have an intermediate probability of rapid infiltration due to its relative location on the slope, and should be considered a potentially sensitive feature.

**SC-3**      **Solution Cavity:** SC-3 consists of a horizontal solution cavity located on the eastern  
**Not** slopes of the Site's western drainage, just outside of the southwestern Site boundary.  
**Sensitive** The solution cavity is located within broken rock and soil on the slope. The cavity is approximately 0.8' tall, 0.6' wide, and 1.5' deep vertically. The cavity and surrounding area was investigated for potential for surface water infiltration to the subsurface. It appears the cavity is located between breakdown rock and soil, not within bedrock, and was likely formed as an animal burrow, as it is currently being used as burrow. Digging by hand, the bottom of the cavity appeared to be limestone without additional fracturing or cavities. The slope which the boulders are located, displayed no evidence of surface water drainage or infiltration. Furthermore, the way the cavity is situated within the boulders and under an overhanging limestone block, surface water would appear to drain around the cavity. Due to a very low potential for surface water infiltration to the subsurface, and the animal burrow nature of the dug-out cavity, this finding is not being considered a potential sensitive feature.

No other geologic features, sensitive features, or potential recharge features were observed on the Site.

## 4.0 SUMMARY

---

Anding Environmental has conducted a Geologic Assessment for the referenced Site in accordance with 30 TAC §213.5(b)(3), TCEQ requirements for regulated developments within the Edwards Aquifer Recharge Zone, and the “Instructions to Geologists”, TCEQ-0585-Instructions (Rev. 10-1-04). Two (2) geologic or potentially sensitive features were observed on the Site.

The upland portion of the Site contains mostly clay loam soils with high runoff and slower infiltration rates, and the drainage slopes have high runoff potential. The drainage bottoms did not appear to have features which would provide opportunity for rapid infiltration into the subsurface. The two (2) potentially sensitive karst features observed on the Site did not appear to have large catchment areas due to their relative locations on the slopes of the drainages. Therefore, it is Anding Environmental’s professional judgement that the Site has low potential for rapid surface water movement to the Edwards Aquifer via direct infiltration.

Please note that other karst features may exist on Site, either buried or obscured from view, which may have potential for openings to the subsurface. If any additional potentially karst features are discovered during future Site activities, please do not hesitate to contact Anding Environmental for support.



## 5.0 REFERENCES

---

Bureau of Economic Geology, 1992, Geologic Map of Texas: University of Texas at Austin, Virgil E. Barnes, project supervisor, Hartmann, B.M. and Scranton, D.F., cartography, scale 1: 500,000

Collins, E.W., 2000, Geologic map of the New Braunfels, Texas, 30 x 60 minute quadrangle—Geologic framework of an urban-growth corridor along the Edwards aquifer, south-central Texas: University of Texas, Bureau of Economic Geology Miscellaneous Map 39, 28 p., 1 sheet, scale 1: 100,000.

Comal County Appraisal District. Property Search. <http://www.comalad.org/>

Federal Emergency Management Agency. Floodplain Maps. <https://msc.fema.gov/portal>

Hanson, J.A., and Small, T.A., 1995, Geologic framework and hydrogeologic characteristics of the Edwards aquifer outcrop, Hays County, Texas: U.S. Geological Survey Water-Resources Investigations Report 95-4265, 10 p., 1 sheet, scale 1: 75,000.

Stein, W.G., and Ozuna, G.B., 1995, Geologic framework and hydrogeologic characteristics of the Edwards aquifer recharge zone, Bexar County, Texas: U.S. Geological Survey Water-Resources Investigations Report 95-4030, 8 p., 1 sheet, scale 1:75,000.

Stoeser, D.B., Shock, Nancy, Green, G.N., Dumonceaux, G. M., and Heran, W.D., in press, A Digital Geologic Map Database for the State of Texas: U.S. Geological Survey Data Series.

Texas Commission on Environmental Quality. Regulatory Databases. <http://www.tceq.state.tx.us/>

United States Department of Agriculture (USDA), 2021. NRCS Web Soil Survey. *Custom Soil Report for Comal County, Texas*. Accessed July 2022.

U.S. Geological Survey. Topographic Maps. <https://ngmdb.usgs.gov/maps/topoview/viewer>

U.S. Geological Survey. Texas Geology. <http://mrdata.usgs.gov/sgmc/tx.html>

---

**GEOLOGIC ASSESSMENT**  
**ATTACHMENT D - SITE GEOLOGIC MAPS**



**Legend**




**671 Ridge Hill Drive  
New Braunfels, Comal County, Texas**

**Site Location Map**

Geologic Assessment  
671 Ridge Hill Drive, New Braunfels, TX



925 Lauren St.  
New Braunfels, TX 78130



TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/5/2022	ANDING	001	<b>D-1</b>





**Site**

**Legend**

 Site


**671 Ridge Hill Drive  
New Braunfels, Comal County, Texas**

**Site Aerial**


Geologic Assessment  
671 Ridge Hill Drive, New Braunfels, TX



925 Lauren St.  
New Braunfels, TX 78130



TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/5/2022	ANDING	002	<b>D-2</b>









**Recharge Zone**

**Site**

**Transition Zone**

**Legend**

-  Site
-  Edwards Aquifer Contributing Zone
-  Edwards Aquifer Contributing Zone within the Transition Zone
-  Edwards Aquifer Recharge Zone
-  Edwards Aquifer Transition Zone



**671 Ridge Hill Drive  
New Braunfels, Comal County, Texas**

**Edwards Aquifer Zone Map**

Geologic Assessment  
671 Ridge Hill Drive, New Braunfels, TX



925 Lauren St.  
New Braunfels, TX 78130


TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/5/2022	ANDING	004	<b>D-4</b>





**Legend**

- Site
- ErG - Eckrant-Rock outcrop association, 8% to 30% slopes
- RUD - Rumple-Comfort, rubbly association, 1% to 8% slopes



**671 Ridge Hill Drive  
New Braunfels, Comal County, Texas**

**Site Soils**

Geologic Assessment  
671 Ridge Hill Drive, New Braunfels, TX




925 Lauren St.  
New Braunfels, TX 78130

TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/5/2022	ANDING	006	<b>D-6</b>



**Legend**

- Elevation Contours 2' Intervals
- Site



**671 Ridge Hill Drive  
New Braunfels, Comal County, Texas**

**Site Topography**


Geologic Assessment  
671 Ridge Hill Drive, New Braunfels, TX



925 Lauren St.  
New Braunfels, TX 78130

TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/5/2022	ANDING	003	<b>D-3</b>





**RUD**

**Site**

**Kp**

**ErG**

**SC3**

**SC2**

**SC1**

**Legend**

◆ Geologic Assessment Findings

■ Kp (Kep) - Person

■ NRCS Soils

■ Site

ErG - Eckrant-Rock outcrop association, 8% to 30% slopes  
 RUD - Rumble-Comfort, rubbly association, 1% to 8% slopes



**Site Findings and Geology Map**

Geologic Assessment  
 671 Ridge Hill Drive, New Braunfels, TX

**ANDING** 925 Lauren St.  
 New Braunfels, TX 78130

TC NO.	DATE	DRAWN BY	MAP NO.	FIGURE
22-010	7/21/2022	ANDING	007	<b>D-7</b>

---

**GEOLOGIC ASSESSMENT  
ATTACHMENT E - PHOTO LOG**



**Attachment E - Photo Log**  
**Site Investigation Photos**



**Site**



**Site Entrance and Northwestern Site Boundary**



**Southeastern Site Boundary**



**Site Southern Corner**





**Drainage Along Southeastern Site Boundary**



**Northeastern Site Boundary**



**Uplands Portion of Site**



**Uplands Portion of Site**





**Emergence of Western Site Drainage**



**Western Site Drainage**



**Western Site Drainage**



**Culvert Draining Site Where Western and Eastern Site Drainages Converge**





**Eastern Site Drainage**



**Additional Parking Area  
North of Gymnasium**



**Typical Edwards Limestone Outcropping on  
Uplands Portion of Site**



**Typical Edwards Rock and Eckrant-Rock Soils  
in Upland Portion of Site**





**Typical Edwards Limestone and Rumple-Comfort Soils on Sloped Portions of Site**



**Typical Slopes Down to Drainages**



**Typical Stair-Step Bluff Ledges on Drainage Slopes**



**Solution Cavity SC-1**





**Solution Cavity SC-2**



**Solution Cavity SC-3**

# Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Joseph T. Sandoval, P.E.

Date: Feb. 10, 2023

Signature of Customer/Agent:

Joseph Sandoval, P.E.

Regulated Entity Name: Keith Wing Two-Story Office



## Regulated Entity Information

1. The type of project is:

- Residential: Number of Lots: \_\_\_\_\_
- Residential: Number of Living Unit Equivalents: \_\_\_\_\_
- Commercial
- Industrial
- Other: \_\_\_\_\_

2. Total site acreage (size of property): 2.54

3. Estimated projected population: \_\_\_\_\_

4. The amount and type of impervious cover expected after construction are shown below:

**Table 1 - Impervious Cover Table**

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	14,135	÷ 43,560 =	0.32
Parking	34,153	÷ 43,560 =	0.79
Other paved surfaces	2,242	÷ 43,560 =	0.05
Total Impervious Cover	50,530	÷ 43,560 =	1.16

**Total Impervious Cover 1.16 ÷ Total Acreage 2.54 X 100 = 46% Impervious Cover**

5.  **Attachment A - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
6.  Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

***For Road Projects Only***

**Complete questions 7 - 12 if this application is exclusively for a road project.**

7. Type of project:

- TXDOT road project.
- County road or roads built to county specifications.
- City thoroughfare or roads to be dedicated to a municipality.
- Street or road providing access to private driveways.

8. Type of pavement or road surface to be used:

- Concrete
- Asphaltic concrete pavement
- Other: \_\_\_\_\_

9. Length of Right of Way (R.O.W.): \_\_\_\_\_ feet.

Width of R.O.W.: \_\_\_\_\_ feet.

L x W = \_\_\_\_\_ Ft<sup>2</sup> ÷ 43,560 Ft<sup>2</sup>/Acre = \_\_\_\_\_ acres.

10. Length of pavement area: \_\_\_\_\_ feet.

Width of pavement area: \_\_\_\_\_ feet.

L x W = \_\_\_\_\_ Ft<sup>2</sup> ÷ 43,560 Ft<sup>2</sup>/Acre = \_\_\_\_\_ acres.

Pavement area \_\_\_\_\_ acres ÷ R.O.W. area \_\_\_\_\_ acres x 100 = \_\_\_\_\_% impervious cover.

11.  A rest stop will be included in this project.
- A rest stop will not be included in this project.

12.  Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

### ***Stormwater to be generated by the Proposed Project***

13.  **Attachment B - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

### ***Wastewater to be generated by the Proposed Project***

14. The character and volume of wastewater is shown below:

<u>100</u> % Domestic	<u>1,329</u> Gallons/day
<u>N/A</u> % Industrial	<u>N/A</u> Gallons/day
<u>N/A</u> % Commingled	<u>N/A</u> Gallons/day
TOTAL gallons/day <u>1,900</u>	

15. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

**Attachment C - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

Sewage Collection System (Sewer Lines):

Private service laterals from the wastewater generating facilities will be connected to an existing SCS.

Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.

The SCS was previously submitted on\_\_\_\_\_.

The SCS was submitted with this application.

The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

The sewage collection system will convey the wastewater to the Gruene Wastewater Reclamation Facility (name) Treatment Plant. The treatment facility is:

Existing.

Proposed.

16.  All private service laterals will be inspected as required in 30 TAC §213.5.

## **Site Plan Requirements**

**Items 17 – 28 must be included on the Site Plan.**

17.  The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 100'.

18. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FIRM 48091C0435F (effective September 2, 2009)

19.  The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.

20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

There are 0 (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)

The wells are not in use and have been properly abandoned.

The wells are not in use and will be properly abandoned.

The wells are in use and comply with 16 TAC §76.

There are no wells or test holes of any kind known to exist on the project site.

21. Geologic or manmade features which are on the site:

All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.

No sensitive geologic or manmade features were identified in the Geologic Assessment.

**Attachment D - Exception to the Required Geologic Assessment.** A request and justification for an exception to a portion of the Geologic Assessment is attached.



- 22.  The drainage patterns and approximate slopes anticipated after major grading activities.
- 23.  Areas of soil disturbance and areas which will not be disturbed.
- 24.  Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 25.  Locations where soil stabilization practices are expected to occur.
- 26.  Surface waters (including wetlands).  
 N/A
- 27.  Locations where stormwater discharges to surface water or sensitive features are to occur.  
 There will be no discharges to surface water or sensitive features.
- 28.  Legal boundaries of the site are shown.

### ***Administrative Information***

- 29.  Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 30.  Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

## WATER POLLUTION ABATEMENT PLAN

### ATTACHMENT A

#### Factors Affecting Water Quality

The Keith Wing Two-Story Office includes the construction of 62 L.F. of 6" gravity wastewater line, 14,135 SF of buildings with rooftops, 34,153 SF of driveway with parking, and 2,242 SF of retaining wall and storm structures. The impervious area allocated for the projected development is 50,530 SF, which includes structures, rooftops, and driveways. The gravity wastewater line will be installed to connect to an existing SCS. Factors affecting water quality are runoff sediment transport from trench work and construction being performed. However, temporary BMP measures are being taken to ensure water quality is not impaired by construction. No groundwater impacts are anticipated with this project.

# WATER POLLUTION ABATEMENT PLAN

## ATTACHMENT B

### Volume and Character of Stormwater

The Keith Wing Two-Story Office covers 2.54 acres. The Existing Drainage Area Map and Proposed Drainage Area Map can be found on Sheets C2.00 and C2.01 of the Keith Wing Two-Story Office Civil Construction Document Set.

In existing conditions, 0.86 acres flow southwest from the high point of the site located at the northern corner of the site boundary into the adjacent Loop 337 R.O.W. at a peak flow rate of 8.77 CFS for the 100-yr storm event. The remaining 1.68-acre portion flows from the northeast side of the site southward before it flows into an existing dry creek at a peak flow rate of 17.1 CFS for the 100-yr storm event.

In proposed conditions, the portion of runoff flowing southwest towards the Loop 337 R.O.W. has a 100-yr peak flow rate of 3.85 CFS which is below the existing conditions peak flow. The portion of runoff flowing into the existing dry creek was divided among three areas to offset the increase in peak flow rate created by added impervious cover. The portion of runoff from the building, driveway, and parking will be detained through a batch detention basin to hold the 100-yr peak flow rate of 13.3 CFS. The 100-yr peak flow rate was reduced from 17.1 CFS to 16.8 CFS.

There exists 1.16 acres of impervious cover on the 2.54 acres. The proposed development will increase the impervious cover to 46% at full development. The plans include permanent BMP's to treat the increase of TSS due to this development. The required 80% TSS removal amount as a result of the development is 996 LBS, which is achieved with this design. Please see Sheet C7.02 and C7.03 of civil construction documents for the overall water quality layout.

The existing and proposed runoff from the site was determined using the Soil Conservation Service Method. Runoff coefficients were derived from Table 4-1 from the City of New Braunfels Drainage and Erosion Control design Manual Revised January 2018. Tables showing the drainage areas and resulting flows are shown on Sheets C2.00 and C2.01 of The Civil Construction Document Set.

# Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Joseph T. Sandoval, P.E.

Date: Feb. 10, 2023

Signature of Customer/Agent:

Joseph Sandoval, P.E.

Regulated Entity Name: Keith Wing Two-Story Office



## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2.  **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3.  Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4.  **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5.  **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6.  Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Dry Comal Creek

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7.  **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.  The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
  - There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.  **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.  **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11.  **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- N/A
12.  **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13.  All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14.  If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15.  Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16.  Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

### ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17.  **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.



18.  Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19.  Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

20.  All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21.  If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22.  Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## TEMPORARY STORMWATER SECTION

### ATTACHMENT A

#### Spill Response Actions

Contractor to notify all appropriate authorities if more than 25 gallons of hydrocarbons are spilled. The construction plans include the required notes regarding appropriate spill response actions as directed by TCEQ. There will be no temporary storage vessels of fuel or hydrocarbons to be stored on site.

If spills of any hydrocarbons occur, construction must contain spills by immediate action. Earthen materials must be kept readily available to provide a Dike. Sand should be used to help soak fuels. Proper disposal of any materials will be required.

Contractor must promote job site awareness to all employees involved. All employees must be made aware of provisions in this report.

#### **Spill Prevention and Control**

The objective of this section is to describe measures to prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees.

The following steps will help reduce the stormwater impacts of leaks and spills:

#### ***Education***

1. Be aware that different materials pollute in different amounts. Make sure that each employee knows what a “significant spill” is for each material they use, and what is the appropriate response for “significant” and “insignificant” spills. Employees should also be aware of when a spill must be reported to the TCEQ. Information available in 30 TAC 327.4 and 40 CFR 302.4.
2. Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
3. Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
4. Establish a continuing education program to indoctrinate new employees.
5. Have contractor’s superintendent or representative oversee and enforce proper spill prevention and control measures

#### ***General Measures***

1. To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110, 117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
2. Store hazardous materials and wastes in covered containers and protect from vandalism.

3. Place a stockpile of spill cleanup materials where it will be readily accessible.
4. Train employees in spill prevention and cleanup.
5. Designate responsible individuals to oversee and enforce control measures.
6. Spills should be covered and protected from stormwater runoff during rainfall to the extent that it doesn't compromise cleanup activities.
7. Do not bury or wash spills with water.
8. Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
9. Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
10. Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
11. Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
12. Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

### ***Clean up***

1. Clean up leaks and spills immediately.
2. Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and absorbent material for larger spills. If the spill material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.
3. Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

### ***Minor Spills***

1. Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
2. Use absorbent materials on small spills rather than hosing down or burying the spill.
3. Absorbent materials should be promptly removed and disposed of properly.

4. Follow the practice below for a minor spill:
  - a. Contain the spread of the spill.
  - b. Recover spilled materials
  - c. Clean the contaminated area and properly dispose of contaminated materials.

### ***Semi-Significant Spills***

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. this response may require the cessation of all other activities.

Spills should be cleaned up immediately:

1. Contain spread of the spill.
2. Notify the project foreman immediately.
3. If the spill occurs, on paved or impermeable surfaces, clean up using “dry” methods (absorbent materials, cat litter, and/or rags). Contain the spill by encircling with the absorbent materials and do not let the spill spread widely.
4. If the spill occurs in dirt areas immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
5. If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

### ***Significant/Hazardous Spills***

for significant or hazardous spills that are in reportable quantities:

1. Notify the TCEQ by telephone as soon as possible and within 24 hours at (512) 339-2929 (Austin) or (210) 490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at (800) 832-8224. It is the contractor’s responsibility to have all emergency phone numbers at the construction site.
2. For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110, 119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
3. Notification should first be made by telephone and followed up with a written report.
4. The services of a spills contactor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.

5. Other agencies which may need to be consulted include, but are not limited to, the City of Police Department, County Sheriff Office, Fire Departments, etc.

#### Vehicle and Equipment Maintenance

1. If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runoff of spills.
2. Regularly inspect onsite vehicles and equipment for leaks and repair immediately.
3. Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
4. Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
5. Place drip pans or absorbent materials under paving equipment when not in use.
6. Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
7. Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
8. Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling oil filters.
9. Store cracked batteries in non-leaking secondary container. Do this with all cracked batteries even if you think the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

#### Vehicle and Equipment Fueling

1. If fueling must occur onsite, use designated areas, located away from drainage courses, to prevent runoff of stormwater and the runoff of spills.
2. Discourage "topping off" fuel tanks.
3. Always use secondary containment, such as a drain pan, when fueling to catch spill/leaks.



## TEMPORARY STORMWATER SECTION

### ATTACHMENT B

#### Potential Sources of Contamination

This project includes the construction of 62 linear feet of 6" gravity wastewater line. One possible source of contamination includes fuel spills by the contractor while refueling equipment. Other small quantities of solvent for construction may be present. Contractor shall keep all fuel transfers and any other contaminants used secure. Silt fences, rock berms, and filter curb inlet protection will aid in the removal of transported sediment from the runoff.

Please see Attachment A for response actions.

## TEMPORARY STORMWATER SECTION

### ATTACHMENT C

#### Sequence of Major Activities

Construction sequencing – the construction will be performed in one phase.

1. Call New Braunfels Utilities and TCEQ 48-hours prior to beginning any work. Call the Dig Tess for utilities locations.
2. Install temporary erosion controls prior to any clearing and grubbing.
3. Begin site clearing. (2.54 acres disturbed)
4. Inspect erosion controls at weekly intervals, before and after significant rainfall events to insure they are functioning properly.
5. Road cuts to subgrade elevation. (2.54 acres already disturbed)
6. Install onsite sewer laterals. (2.54 acres already disturbed)
7. Install private water service lines. (2.54 acres already disturbed)
8. Construct drainage improvements. (2.54 acres already disturbed)
9. Complete fill and compaction on site to match subgrade elevations. (2.54 acres already disturbed)
10. Construct curb inlet protection at the time of curb and inlet installation. (2.54 acres already disturbed)
11. Complete all construction per approved plans and stabilize all disturbed areas.
12. Install streetscape and/or landscaping improvements.
13. Contact project engineer to inspect site. Final city inspection to be scheduled.
14. Complete any necessary final dress up areas disturbed.
15. Removed and dispose of temporary erosion controls after site revegetation has occurred.

## TEMPORARY STORMWATER SECTION

### ATTACHMENT D

#### Temporary Best Management Practices and Measures

Temporary erosion controls are proposed for this project to include silt fence, filter dike, concrete wash out area, temporary spoils area, and a stabilized construction entrances and exits.

Approximately 1211 linear feet of silt fence will be used. This silt fence will be placed down gradient of all proposed construction. Please see sheet C4.00 of the Keith Wing Two-Story Office Construction Plans. There is no known surface streams of ground water that originates on this site.

From the TCEQ RG 348 dated July 2005, silt fences provide temporary protection. In addition, the contractor has been directed to minimize disturbance to reasonable working space.

There are three potential sensitive recharge features in the onsite portion that were identified in the Geologic Assessment by Matthew Anding dated August 18<sup>th</sup>, 2022.

## TEMPORARY STORMWATER SECTION

### ATTACHMENT F

#### Structural Practices

During construction, silt fences will be used until construction is complete and vegetation and paving has been established. Rough cutting of the proposed parking lot will divert flows from entering the trench area. Additionally, the contractor will pile the spoils from trench excavation on the uphill side of the trench, with a minimum of one foot between the trench and the pile, in order to prevent storm water from entering the trench.

In addition, the contractor will be directed to minimize site disturbance and avoid having equipment in areas that are not necessary for the construction. Natural vegetation shall be left undisturbed and will help remove sediment if any bypass at silt fences or other structural measures occurs.





# ATTACHMENT G - Existing Drainage Area Map

Table 1 - Existing Conditions Hydrology Calculations - City of New Braunfels									
Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
EX 1	Site Area to EX 1	EX 1	1.68	10.1	84.0	4.01	8.07	11.2	17.1
EX 2	Site Area to EX 2	EX 2	0.86	10.0	84.0	2.05	4.13	5.73	8.77


Table 2 - Off-site Conditions Hydrology Calculations - City of New Braunfels									
Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
OS 1	Ridge Hill Dr. ROW	OS 1	0.07	10.0	84.0	0.17	0.34	0.47	0.71



- LEGEND**
- 700 --- EXISTING CONTOURS
  - 700 --- PROPOSED CONTOURS
  - B.L. --- BUILDING SETBACK LINE
  - U.E. --- UTILITY EASEMENT
  - D.E. --- DRAINAGE EASEMENT
  - SC --- SOLUTION CAVITY
  - DA --- DRAINAGE AREA
  - TC --- TC --- TIME OF CONCENTRATION
  - A-1 --- POINT OF CONCENTRATION
  - --- DRAINAGE FLOW DIRECTION
  - DA --- DRAINAGE AREA LABEL

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600

**HMT**  
 ENGINEERING & SURVEYING



11/9/2022

**EXISTING DRAINAGE MAP**

KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: **NOVEMBER 2022**

DRAWN BY: **WRC**

DESIGNED BY: **JTS**

REVIEWED BY: **JTS**

HMT PROJECT NO.:  
**429.002**

**SHEET**

**C2.00**

Drawing Name: N:\Projects\429 - Keith Wing Custom Builders\002 - Taylor Office Complex\429\002\_DRNG.dwg User: wllc Nov 09, 2022 - 3:12pm



# ATTACHMENT G - Proposed Drainage Area Map

**Table 3 - Ultimate Proposed Conditions Hydrology Calculations - City of New Braunfels**

Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
P 1	Contributing to Basin 1	P 1.1	1.24	10.0	93.0	3.83	6.77	9.00	13.3
P 1	Basin Area	P 1.2	0.27	10.0	93.0	0.83	1.48	1.96	2.89
P 1	Area outside Basin 1 to P 1	P 1.3	0.66	10.0	93.0	2.04	3.61	4.79	7.06
P 2	Area to P 2	P 2	0.36	10.0	93.0	1.11	1.97	2.61	3.85

**Table 4 - Existing to Proposed Comparison**

Point of Concentration	Drainage Area	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
EX 1	1.68	4.01	8.07	11.2	17.1
P 1	1.51	2.04	4.16	10.4	16.8
Proposed is Less Than or Equal to Existing		YES	YES	YES	YES
EX 2	0.86	2.05	4.13	5.73	8.77
P 2	0.36	1.11	1.97	2.61	3.85
Proposed is Less Than or Equal to Existing		YES	YES	YES	YES




1  
0 20 40 80  
HORIZONTAL SCALE: 1:40

**LEGEND**

- 700 --- EXISTING CONTOURS
- 700 --- PROPOSED CONTOURS
- B.L. BUILDING SETBACK LINE
- U.E. UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- SC SOLUTION CAVITY
- DA --- DRAINAGE AREA
- TC --- TC --- TIME OF CONCENTRATION
- A-1 ○ POINT OF CONCENTRATION
- ← DRAINAGE FLOW DIRECTION
- DA ○ DRAINAGE AREA LABEL

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



11/9/2022

**PROPOSED DRAINAGE MAP**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: NOVEMBER 2022  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS  
HMT PROJECT NO.: 429.002

**SHEET C2.01**

Drawing Name: N:\Projects\429 - Keith Wing Custom Builders\002 - Taylor Office Complex\429.002\_DRNG.dwg User: wllc Nov 09, 2022 - 3:12pm



## TEMPORARY STORMWATER SECTION

### ATTACHMENT I

#### Inspection and Maintenance of BMPs

The contractor will be directed to inspect and maintain all temporary BMPs. The design engineer will also make regular visits to the project during construction to provide visual inspections as well. Any deficiency noted must be corrected immediately by the contractor.

#### Maintenance:

1. Inspect all silt fence, rock berms, concrete wash out areas, filter dams, and stabilized concrete entrances and exits weekly and after any rainfall event. Inspect the filter curb inlet protection daily.
2. Remove sediment when buildup reaches 6 inches of depth on silt fence or rock berms or install a second line of silt fence parallel to the original installation. Remove sediment when buildup reaches 2 inches depth in filter curb inlet protection.
3. Replace any torn fabric in the silt fence, filter dams, or filter curb inlet protection.
4. Replace or repair any section that is crushed or collapsed in the course of construction.
5. See stormwater pollution plan detail as shown in the construction plans for proper size and installation.
6. Contractor to maintain a daily log and note any deficiencies to temporary BMPs and corrective action taken. Rainfall events shall also be noted.

## TEMPORARY STORMWATER SECTION

### ATTACHMENT J

#### Schedule of Interim and Permanent Soil Stabilization Practices

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity temporary or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on the portion of site.

If after 21 days, and construction activity will not resume, hydromulch shall be applied to all disturbed areas except in drainage channels or where slopes exceed 3:1. In areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

All erosion control measures must remain in place until such stabilization has successfully occurred.

Owner shall consult with design engineer to determine all necessary measures to stabilize the site if construction does not resume.

TCEQ RG 348 dated July 2005 shall be used as a guide in determining these areas that may require stabilization.

# Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(ii), (E), and (5), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Joseph T. Sandoval, P.E.

Date: Feb. 10, 2023

Signature of Customer/Agent

Joseph Sandoval, P.E.



Regulated Entity Name: Keith Wing Two-Story Office

## Permanent Best Management Practices (BMPs)

*Permanent best management practices and measures that will be used during and after construction is completed.*

- Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.  
 N/A
- These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.  
 The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.



A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: \_\_\_\_\_

N/A

3.  Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

N/A

4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

The site will be used for low density single-family residential development but has more than 20% impervious cover.

The site will not be used for low density single-family residential development.

5. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

**Attachment A - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.

The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.

The site will not be used for multi-family residential developments, schools, or small business sites.

6.  **Attachment B - BMPs for Upgradient Stormwater.**

- A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
  - No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
  - Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7.  **Attachment C - BMPs for On-site Stormwater.**
- A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
  - Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8.  **Attachment D - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
- N/A
9.  The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
- The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.
  - Attachment E - Request to Seal Features.** A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10.  **Attachment F - Construction Plans.** All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
- Design calculations (TSS removal calculations)
  - TCEQ construction notes
  - All geologic features
  - All proposed structural BMP(s) plans and specifications
- N/A

11.  **Attachment G - Inspection, Maintenance, Repair and Retrofit Plan.** A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
- Prepared and certified by the engineer designing the permanent BMPs and measures
  - Signed by the owner or responsible party
  - Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
  - A discussion of record keeping procedures
- N/A
12.  **Attachment H - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- N/A
13.  **Attachment I -Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
- N/A

### ***Responsibility for Maintenance of Permanent BMP(s)***

***Responsibility for maintenance of best management practices and measures after construction is complete.***

14.  The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- N/A
15.  A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
- N/A

PERMANENT STORMWATER SECTION  
ATTACHMENT B  
BMPs for Upgradient Stormwater

There are no permanent BMPs for upgradient stormwater for the Keith Wing Two-Story Office because the site does not accept upgradient stormwater.



PERMANENT STORMWATER SECTION  
ATTACHMENT C  
BMPs for On-Site Stormwater

One (1) batch detention/water quality basin is proposed as the Permanent Best Management Practices (PBMPs) for the proposed impervious cover associated with the proposed portable classroom building. All PBMPs have been designed in accordance with the TCEQ's Technical Guidance Manual (TGM) RG-348 (Revised July 2005) to remove 80% of the increase in TSS from the site.

PERMANENT STORMWATER SECTION  
ATTACHMENT D  
BMPs for Surface Streams

There are no surface streams on or immediately adjacent to the site. Therefore, no additional BMPs are required.

PERMANENT STORMWATER SECTION  
ATTACHMENT F  
Construction Plans

There is one type of proposed Permanent BMPs for the on-site stormwater for the Keith Wing Two-Story Office. The permanent BMP consists of a batch detention/water quality basin. The design plans and details can be found in the Keith Wing Two-Story Office Construction Plans.


# KEITH WING TWO-STORY OFFICE

## 671 RIDGE HILL DR.

### NEW BRAUNFELS, TEXAS

## CIVIL SITE CONSTRUCTION PLANS

KEITH WING  
2027 STATE HIGHWAY 46 WEST, SUITE 106  
NEW BRAUNFELS, TEXAS 78132



PROJECT LOCATION MAP SCALE: N.T.S.

#### PROJECT BENCHMARK PROJECT DESCRIPTION

SITE TBM #1  
SET #50  
N: 13805125.86  
E: 2234438.62  
ELEV: 844.63'

THIS PROJECT CONSISTS OF THE CONSTRUCTION OF A TWO STORY OFFICE BUILDING WITH A BUILDING COVERAGE OF 10,126 SF AND A GROSS FLOOR AREA OF 19,063 SF. ADDITIONALLY, THIS INCLUDES ASSOCIATED PARKING, A DETENTION/WATER QUALITY POND, AND UTILITIES ON A 2.54 ACRE SITE WITH A TOTAL IMPERVIOUS COVER OF 46%.

SITE TBM #2  
SET #51  
N: 13805267.30  
E: 2234537.62  
ELEV: 825.17'

**FIRE FLOW REQUIREMENTS**  
CONSTRUCTION TYPE PER IBC 2018: TYPE II-B  
BUILDING AREA: 19,063 SF  
REQUIRED FIRE FLOW PER IFC 2018: 3000 GPM  
DEDUCTION FOR NFPA 13 SPRINKLER SYSTEM: 0.75 x 3000 = 2250 GPM  
REQUIRED FIRE FLOW AFTER DEDUCTION: 750 GPM  
MIN. REQUIRED FIRE FLOW AT ANY SITE: 1,000 GPM

WSFU

OFFICE = 112

#### LEGAL DESCRIPTION

LOT 11, BLOCK 1 OF THE MISSION FOREST SUBDIVISION UNIT THREE RECORDED IN VOLUME 13, PAGE 178, DOCUMENT 20006001773 OF THE MAP AND PLAT RECORDS OF COMAL COUNTY, TEXAS.

PLEASE NOTE: NBU REQUIRES GPS POINTS FOR CERTAIN ELECTRIC, WATER AND WASTEWATER ATTRIBUTES, SOME OF WHICH MUST BE TAKEN PRIOR TO BACKFILL DURING CONSTRUCTION.

GPS POINTS SHALL BE REQUIRED FROM THE DEVELOPER'S CONTRACTOR OR ENGINEER. A MINIMUM OF THREE COORDINATE POINTS FOR GEOREFERENCING SHALL BE REQUIRED. THE WATER AND WASTEWATER GPS POINTS SHALL BE TO SURVEY GRADE. THE ELECTRIC GPS POINTS SHALL BE TO MAP GRADE. REFERENCE NBU'S WATER CONNECTION POLICY FOR ADDITIONAL CAD DELIVERABLE REQUIREMENTS.

**WATER**  
VERTICAL BENDS AND EDGE OF STEEL CASING (IF APPLICABLE) PRIOR TO BACKFILL  
HORIZONTAL BENDS PRIOR TO BACKFILL  
TEES PRIOR TO BACKFILL  
FITTINGS (REDUCERS AND COUPLINGS) PRIOR TO BACKFILL  
FIRE HYDRANTS (TOP OF FLANGE)  
VALVES  
METERS (TOP CENTER OF BOX)  
BLOW OFF ASSEMBLY  
CORNER SLAB OF WATER TANK & GATE VALVE ON WATER TANK

**WASTEWATER**  
MANHOLES  
CLEANOUTS  
CORNER SLAB OF LIFT STATION

**ELECTRIC**  
POLES  
TRANSFORMERS, BOTH ABOVE AND UNDERGROUND (FRONT LOCK)  
PULL BOXES  
STREET LIGHTS

COORDINATE GPS REQUIREMENTS WITH NBU INSPECTOR

#### GENERAL NOTES:

- IF CONSTRUCTION HAS NOT COMMENCED WITHIN ONE-YEAR OF CITY APPROVAL FOR CONSTRUCTION INSPECTION, THAT APPROVAL IS NO LONGER VALID.
- THE MOST CURRENT EDITIONS OF THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS AND THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES SHALL BE FOLLOWED FOR ALL CONSTRUCTION EXCEPT AS AMENDED BY THE CITY OF NEW BRAUNFELS STANDARD DETAILS.
- ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL CONTACT THE CITY OF NEW BRAUNFELS TO SET A PRE-CONSTRUCTION MEETING. A 48-HOUR ADVANCED NOTIFICATION IS REQUIRED FOR ALL INSPECTION AND MEETING REQUESTS.
  - ALL INSPECTIONS ARE TO BE CALLED IN AT 830-221-4068 OR,
  - FAXED IN AT 830-608-2117 OR
  - E-MAILED AT INSPECTIONS@NBUTEXAS.ORG.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL TEMPORARY AND PERMANENT TRAFFIC CONTROL DEVICES ARE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE PLANS AND LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. IF THE NEED ARISES, ADDITIONAL TEMPORARY TRAFFIC CONTROL DEVICES MAY BE ORDERED BY THE ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.
- DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE OFFSITE IMPACT OF CONSTRUCTION MUST BE COMPLETED AND IN PLACE PRIOR TO ADDING IMPERVIOUS COVER TO THE SITE.
- THIS DEVELOPMENT IS A TYPE 3 DEVELOPMENT.
- NO PORTION OF THE SUBDIVISION IS LOCATED WITHIN ANY SPECIAL FLOOD HAZARD AREA (100 YR. FLOOD), AS DEFINED BY THE COMAL COUNTY, TEXAS, FIRM PANEL NUMBER 48091C0435F EFFECTIVE DATE SEPTEMBER, 02, 2009, AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.
- THIS PROJECT IS LOCATED WITHIN THE EDWARDS AQUIFER RECHARGE ZONE.
- GAS UTILITIES ARE NOT INCLUDED IN THE CIVIL CONSTRUCTION PLANS. FINAL GAS UTILITY DESIGN SHALL BE APPROVED BY THE CITY FOR ANY WORK WITHIN PUBLIC RIGHT-OF-WAY, IF APPLICABLE.
- THE ENGINEER OF RECORD ACKNOWLEDGES THAT ALL PROPOSED WATER AND WASTEWATER IMPROVEMENTS MUST COMPLY WITH TCEQ, CITY OF NEW BRAUNFELS, NBU WATER CONNECTION POLICY, SOUND ENGINEERING JUDGEMENT AND ANY OTHER GOVERNING ENTITY ORDINANCES OR CODES.


#### GEOLOGIC ASSESSMENT

A GEOLOGIC ASSESSMENT WAS PERFORMED BY ANDING ENVIRONMENTAL CONSULTING, LLC ON 8/18/2022. SEE GA FOR MORE INFORMATION ON SOLUTION CAVITIES SHOWN IN THIS PLAN SET.

#### REQUIRED PERMITS NUMBER

- | REQUIRED PERMITS           | NUMBER |
|----------------------------|--------|
| 1. CITY OF NEW BRAUNFELS   | #      |
| 2. NEW BRAUNFELS UTILITIES | #      |
| 3. TCEQ WPAP               | #      |
| 4. TXDOT UIR               | #      |

# JANUARY 2023



ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD.

Joseph T. Sandoval, P.E.  
Joseph T Sandoval P.E.  
License No. 110257

## PREPARED BY:



290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
HMTNB.COM  
P(830)625-8555\*F(830)625-8556  
TBPE FIRM F-10961  
TBPLS FIRM 1053600

#### NOTE TO CONTRACTOR:

BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.

THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT EACH OF THE INDIVIDUAL UTILITIES FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.

ANY QUANTITIES PROVIDED BY HMT OR OWNER ON THE PLANS, OPINION OF PROBABLE COST, BID SUMMARIES, ETC. ARE FOR CURSORY USE ONLY. CONTRACTOR IS RESPONSIBLE FOR BIDDING SIGNED AND SEALED CONSTRUCTION PLANS. IF A DISCREPANCY EXISTS, CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY.

CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE LOCATION AND ELEVATION OF ALL DOWNSTREAM CONNECTION POINTS PRIOR TO CONSTRUCTION. IF A DISCREPANCY EXISTS, CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY.

CONTRACTOR SHALL INSTALL ALL GRAVITY SEWER, GRAVITY STORM SEWER, CURBS AND PAVEMENT FROM THE MOST DOWNSTREAM POINT OF CONNECTION. IF IMPROVEMENTS ARE CONSTRUCTED FROM UPSTREAM TO DOWNSTREAM, THEN THE CONTRACTOR WILL TAKE FULL RISK AND LIABILITY OF ANY ISSUES THAT MIGHT ARISE FROM FLOWLINE ELEVATION DISCREPANCIES, UTILITY CONFLICTS, ETC.

CONTRACTOR IS RESPONSIBLE FOR THE STOCKPILING OF ANY EXCESS DIRT. ALL BIDS FROM CONTRACTOR SHOULD ACCOUNT FOR THE REMOVAL AND PLACEMENT OF ALL EARTHWORK TO INCLUDE STOCKPILING, EXPORT, IMPORT, ETC. IF A LOCATION OF PLACEMENT OF EXCESS DIRT IS NOT SHOWN ON THE PLANS, THEN CONTRACTOR SHALL CONTACT ENGINEER IMMEDIATELY TO DETERMINE THE MOST SUITABLE STOCKPILE LOCATION.

SHEET LIST TABLE	
SHEET NO.	SHEET TITLE
C0.00	COVER
C0.01	GENERAL NOTES (1 OF 2)
C0.02	GENERAL NOTES (2 OF 2)
C1.00	PLAT
C2.00	EXISTING DRAINAGE MAP
C2.01	PROPOSED DRAINAGE MAP
C3.00	DEMOLITION PLAN
C4.00	EROSION CONTROL PLAN
C4.01	EROSION DETAILS (1 OF 2)
C4.02	EROSION DETAILS (2 OF 2)
C5.00	SITE PLAN
C5.01	FIRE PROTECTION PLAN
C5.02	SITE DETAILS (1 OF 2)
C5.03	SITE DETAILS (2 OF 2)
C6.00	GRADING PLAN
C6.01	GRADING DETAILS
C7.00	OVERALL STORM
C7.01	STORM DRAIN LINE A PLAN AND PROFILE
C7.02	BATCH DETENTION BASIN
C7.03	COMBINED DETENTION & WATER QUALITY CROSS SECTIONS
C7.04	STORM DETAILS
C7.05	BASIN DETAILS
C8.00	OVERALL UTILITY PLAN
C8.01	UTILITY SITE PLAN (1 OF 2)
C8.02	UTILITY SITE PLAN (2 OF 2)
C8.03	UTILITY DETAILS (1 OF 2)
C8.04	UTILITY DETAILS (2 OF 2)

WATER IS A PRECIOUS COMMODITY IN THE STATE OF TEXAS AND NEW BRAUNFELS UTILITIES (NBU) IS PASSIONATE ABOUT PROTECTING THE LOCAL RESOURCE. NBU'S CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ACQUIRING A FIRE HYDRANT METER SO THAT ALL WATER USED FOR CONSTRUCTION OR TESTING PURPOSES ARE PROPERLY ACCOUNTED FOR. NBU WILL NOT TOLERATE ANY WATER THEFT, REGARDLESS OF THE AMOUNT. IF WATER THEFT IS DISCOVERED NBU'S CONTRACTOR SHALL BE SUBJECT TO MONETARY PENALTIES, CRIMINAL CHARGES, AND STOPPAGE OF ALL CONSTRUCTION ACTIVITIES RELATED TO THE PROJECT. COSTS ASSOCIATED WITH ANY WORK STOPPAGE RESULTING FROM WATER THEFT SHALL BE AT THE FULL EXPENSE OF THE CONTRACTOR.

KEITH WING TWO-STORY OFFICE  
CIVIL SITE CONSTRUCTION PLANS

HMT # 429.002



CITY OF NEW BRAUNFELS GENERAL NOTES

ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL COMPLY WITH:

A. CURRENT CITY OF NEW BRAUNFELS CONSTRUCTION SPECIFICATIONS AND STANDARDS AS OF THE DATE OF THIS CONTRACT

B. THE MOST CURRENT EDITION OF TEXAS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES."

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MOST CURRENT TEXAS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS, AND BRIDGES." ALONG WITH CURRENT CITY OF NEW BRAUNFELS AND COMAL COUNTY SPECIFICATIONS. ANY DISCREPANCIES BETWEEN SPECIFICATIONS SHALL BE RESOLVED BY THE ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION.

CONTRACTOR SHALL PROCURE ALL PERMITS AND LICENSES, PAY ALL CHARGES, FEES, AND TAXES AREA AND GIVE ALL NOTICES NECESSARY AND INCIDENTAL TO THE DUE AND LAWFUL PROSECUTION OF THE WORK.

ANY EXISTING OFF-SITE IMPROVEMENTS THAT ARE DAMAGED OR UNDERCUT BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED AS DIRECTED BY THE ENGINEER AND APPROVED BY THE OWNER OF THE EXISTING IMPROVEMENT AT THE CONTRACTOR'S EXPENSE. (NO SEPARATE PAY ITEM)

WORK COMPLETED BY THE CONTRACTOR WHICH HAS NOT RECEIVED A WORK ORDER OR CONSENT OF THE OWNER OR ENGINEER WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR.

CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL WASTE MATERIALS UPON PROJECT COMPLETION. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIAL IN THE 100YR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN DEVELOPMENT PERMIT.

BARRICADES AND WARNING SIGNS SHALL CONFORM TO THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" AND SHALL BE LOCATED TO PROVIDE MAXIMUM PROTECTION TO THE PUBLIC AS WELL AS CONSTRUCTION PERSONNEL AND EQUIPMENT WHILE PROVIDING CONTINUOUS TRAFFIC FLOW AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL DEVICES DURING CONSTRUCTION.

CONTRACTOR IS REQUIRED TO VERIFY PROJECT ELEVATIONS. THE TERM "MATCH EXISTING" SHALL BE UNDERSTOOD TO SIGNIFY BOTH HORIZONTAL AND VERTICAL ALIGNMENT.

WHEN MATCHING EXISTING PAVEMENTS, CURBS, DRIVES, AND WALKS, THEY SHALL BE SAW CUT FULL DEPTH AND REMOVED TO ALLOW FOR PROPOSED CONSTRUCTION. IF ANY EXISTING JOINT IS ENCOUNTERED, PRECAUTION SHALL BE TAKEN DURING REMOVAL OF CONCRETE SO AS NOT TO DAMAGE EXISTING DOWELS. ALL EXISTING DOWELS SHALL BE EXPOSED AND CLEANED.

ITEM OF WORK DESIGNATED "BY OTHERS" SHALL NOT BE CONSIDERED PART OF THIS CONTRACT.

ALL "COMPACTED SUBGRADE" SHALL CONSIST OF NATIVE MATERIAL SCARIFIED TO A MINIMUM DEPTH OF SIX INCHES AND COMPACTED TO 95% DENSITY ACCORDING TO DENSITY TEST METHOD TEX-115E OR ACCORDING TO ASTM D-698 AND TESTED BY ASTM D-2922.

ALL "FLEXIBLE BASE" SHALL BE TYPE "A", GRADE 4, ACCORDING TO TXDOT ITEM 247, COMPACTED TO 95% MODIFIED DENSITY AT A MOISTURE CONTENT BETWEEN -2 AND +3 OF OPTIMUM PERCENT MOISTURE ACCORDING TO ASTM D-1557 (MODIFIED PROCTOR) AND TESTED BY ASTM D-2922.

ASPHALT PAVEMENT SHALL BE THE TYPE SPECIFIED ON THE PLANS AND ACCORDING TO TXDOT ITEM 340 "HOT MIX ASPHALT CONCRETE PAVEMENT".

PRIME COAT USING MC-30 AT A RATE OF 0.2 GALLONS PER SQUARE YARD SHALL BE PLACED OVER PREPARED BASE AT LEAST ONE DAY PRIOR TO LAYING ASPHALTIC CONCRETE PAVEMENT. ANY NECESSARY TACK COAT SHALL BE MC-30 AT 0.05 GALLONS PER SQUARE YARD. IT IS REQUIRED THAT BOTH THE PRIME COAT AND THE TACK COAT BE APPLIED AT THE TEMPERATURE SPECIFIED UNDER TXDOT ITEM 300.3.

CONCRETE SHALL BE CLASS "A" ACCORDING TO TXDOT ITEM 421 UNLESS OTHERWISE ON PLANS.

REINFORCING STEEL SHALL BE FROM NEW BILLET AND SHALL CONFORM TO TXDOT ITEM 440. ALL DIMENSIONS RELATING TO REINFORCING STEEL ARE TO CENTER OF BARS EXCEPT WHEN REFERRING TO CLEARANCE.

ALL SAWED JOINTS SHALL BE SAWED WITHIN 24 HOURS OF POURING.

ABSOLUTELY NO WELDING OF REINFORCING BARS OR TORCHING TO BEND REINFORCING BARS SHALL BE ALLOWED WITHOUT THE SPECIFIC APPROVAL OF THE ENGINEER.

ORDINARY COMPACTION CONTROL IS REQUIRED ON THIS PROJECT.

ALL ROLLING FOR COMPACTION OF ASPHALTIC CONCRETE PAVEMENT SHALL BE COMPLETED BEFORE THE MIXTURE TEMPERATURE DROPS BELOW 175 DEG. (F).

ALL FILL MATERIAL SHALL BE SUBJECT TO THE ENGINEER'S APPROVAL.

CONTRACTOR AGREES TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND SHALL NOT BE LIMITED TO THE NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNERS AND THE ENGINEER AND HIS EMPLOYEES, PARTNERS, OFFICES, DIRECTORS, OR CONSULTANTS, HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF THE WORK ON THIS PROJECT, EXCEPTING FROM LIABILITY ARISING FROM SOLE NEGLIGENCE OF THE OWNER OR ENGINEER, ENGINEER'S DIRECTORS, OFFICERS, EMPLOYEES, OR CONSULTANTS.

ALL CMP (CORRUGATED METAL PIPE) USED ON THIS PROJECT SHALL HAVE A MANNING'S "N" VALUE OF 0.024., UNLESS OTHERWISE SHOWN ON PLANS.

CONTRACTOR WILL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTING PER CURRENT CITY OF NEW BRAUNFELS REQUIREMENTS. ALL TEST RESULTS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. ENGINEER AND OWNER RESERVE THE RIGHT TO HAVE THE CONTRACTOR REMOVE AND REPLACE ANY MATERIAL THAT WAS NOT TESTED OR FAILED TESTING. ALL COST ASSOCIATED WITH THE REMOVAL, REPLACEMENT AND TESTING SHALL BE PAID BY THE CONTRACTOR.

ALL PVC SLEEVES SHALL BE INSTALLED 3 FEET BELOW FINISHED GRADE AND ENDS SHALL BE MARKED SO THAT LOCATIONS OF SLEEVES CAN BE EASILY IDENTIFIED.

PRE-CONSTRUCTION CONFERENCE IS REQUIRED, ENGINEER WILL ARRANGE SUCH CONFERENCE IN COORDINATION WITH CITY OF NEW BRAUNFELS STREET INSPECTOR & NEW BRAUNFELS UTILITIES INSPECTOR. NO CONSTRUCTION MAY BEGIN PRIOR TO THE PRE-CONSTRUCTION CONFERENCE.

CONTRACTOR SHALL COORDINATE WITH DRY UTILITIES INSTALLERS AND SHARED TRENCHING SHALL BE UTILIZED. CUTTING THE STREETS AFTER COMPLETION BY DRY UTILITIES SHALL NOT BE ACCEPTABLE.

AS PER PLATTING ORDINANCE SECTION 11B-38M: WHEN ALL IMPROVEMENTS ARE FOUND TO BE CONSTRUCTED AND COMPLETED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS AND WITH THE CITY'S STANDARDS, AND UPON RECEIPT OF ONE SET OF "RECORD DRAWINGS" PLANS, AND A DIGITAL COPY OF ALL PLANS (AUTOCAD 2000 MINIMUM) THE CITY ENGINEER SHALL ACCEPT SUCH IMPROVEMENTS FOR THE CITY OF NEW BRAUNFELS, SUBJECT TO THE GUARANTY OF MATERIAL AND WORKMANSHIP PROVISIONS IN THIS SECTION.

EROSION / SEDIMENTATION CONTROL

AT A MINIMUM, THESE CONTROLS SHALL CONSIST OF ROCK BERMS AND/OR SILT FENCES CONSTRUCTED PARALLEL TO AND DOWN GRADIENT FROM THE TRENCHES. THE ROCK BERM OR SILT FENCES SHALL BE INSTALLED IN A MANNER SUCH THAT ANY RAINFALL RUNOFF SHALL BE FILTERED. HAY BALES SHALL NOT BE USED FOR TEMPORARY EROSION AND SEDIMENTATION CONTROLS.

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS MUST BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE MAINTAINED DURING CONSTRUCTION BY THE CONTRACTOR. THE CONTRACTOR SHALL REMOVE THE CONTROLS WHEN VEGETATION IS ESTABLISHED AND THE CONSTRUCTION AREA IS STABILIZED [31 TAC 313.5 (C)(12)]. ADDITIONAL PROTECTION MAY BE REQUIRED IF EXCESSIVE SOLIDS ARE BEING DISCHARGED FROM THE SITE.

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE REMOVED BY THE CONTRACTOR AT FINAL ACCEPTANCE OF THE PROJECT BY THE OWNER/ENGINEER.

PLACEMENT OF TEMPORARY EROSION AND SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION PLANS. ACTUAL LOCATIONS MAY VARY SLIGHTLY FROM THE PLANS, BUT WILL BE VERIFIED BY THE ENGINEER/INSPECTOR IN THE FIELD PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL INSPECT THE CONTROLS AT WEEKLY INTERVALS AND AFTER EVERY SIGNIFICANT RAINFALL TO INSURE DISTURBANCE OF THE STRUCTURES HAS NOT OCCURRED. SEDIMENT DEPOSITED AFTER A RAINFALL SHALL BE REMOVED FROM THE SITE OR PLACED IN AN ENGINEER APPROVED DESIGNATED DISPOSAL AREA.

CONTRACTOR SHALL BE RESPONSIBLE TO INSURE THAT NO EROSION CONTROL MEASURES BLOCK THE DRAINAGE SYSTEM FROM WORKING AS DESIGNED.

UTILITIES

LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL EXISTING UTILITIES ENCOUNTERED DURING CONSTRUCTION, INCLUDING THOSE NOT SHOWN ON THE DRAWINGS.

ANY EXISTING UTILITIES, ON OR OFF THE SITE, THAT ARE DAMAGED OR UNDERCUT BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED AS DIRECTED BY THE ENGINEER AND APPROVED BY THE RESPECTIVE UTILITY COMPANY AT THE CONTRACTOR'S EXPENSE.

CONTRACTOR SHALL NOTIFY APPROPRIATE UTILITY COMPANIES AND GOVERNMENTAL AGENCIES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION AT:

THE CONTRACTOR SHALL NOTIFY THE FOLLOWING UTILITY COMPANIES 48 HOURS PRIOR TO EXCAVATION

Table with columns for utility name, phone number, and address. Utilities listed include New Braunfels Utilities (Water and Sewer), Spectrum Cable, Texas One Call System, and Energy Transfer (Petroleum Pipeline).

CONTRACTOR SHALL REFERENCE NEW BRAUNFELS UTILITIES PLANS FOR FINAL ELECTRICAL LINE DESIGNS AND LAYOUT.

NBU WASTEWATER NOTES 03/02/2020

- List of 16 construction notes for wastewater systems, covering pipe installation, bedding, manholes, and trenching requirements.

ADDITIONAL NOTES

- List of 29 additional construction notes covering sewer systems, trenching, and pipe installation details.

WATER NOTES REVISED 5/16/19

- List of 17 construction notes for water systems, including pipe types, bedding, manholes, and trenching requirements.

SEQUENCE OF CONSTRUCTION

- List of 10 numbered items detailing the construction sequence from erosion controls to vegetation preservation.

GENERAL NBU NOTES

REVISED 3/31/11

- List of 17 numbered items detailing general construction requirements, safety, and utility protection.

CITY OF NEW BRAUNFELS CONSTRUCTION NOTES

REVISED 03/2020

IF CONSTRUCTION HAS NOT COMMENCED WITHIN ONE-YEAR OF CITY APPROVAL FOR CONSTRUCTION INSPECTION, THAT APPROVAL IS NO LONGER VALID.

THE MOST CURRENT EDITIONS OF THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS AND THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND BRIDGES SHALL BE FOLLOWED FOR ALL CONSTRUCTION EXCEPT AS AMENDED BY THE CITY OF NEW BRAUNFELS STANDARD DETAILS.

ALL RESPONSIBILITY FOR THE ADEQUACY OF THESE PLANS REMAINS WITH THE ENGINEER OF RECORD. IN ACCEPTING THESE PLANS, THE CITY OF NEW BRAUNFELS MUST RELY UPON THE ADEQUACY OF THE WORK OF THE ENGINEER OF RECORD.

PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE CITY OF NEW BRAUNFELS TO SCHEDULE A PRECONSTRUCTION MEETING.

- Checklist for public infrastructure permit or grading permit projects, including inspection scheduling and notification requirements.

FOR COMMERCIAL PERMIT (CP) PROJECTS:

- Checklist for commercial permit projects, including inspection scheduling and notification requirements.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO SEE THAT ALL TEMPORARY AND PERMANENT TRAFFIC CONTROL DEVICES ARE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE PLANS AND LATEST EDITION OF THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. IF, IN THE OPINION OF THE ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES AND SIGNS DO NOT CONFORM TO ESTABLISHED STANDARDS OR ARE INCORRECTLY PLACED OR ARE INSUFFICIENT IN QUANTITY TO PROTECT THE GENERAL PUBLIC, THE CONSTRUCTION INSPECTOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED. IF THE NEED ARISES, ADDITIONAL TEMPORARY TRAFFIC CONTROL DEVICES MAY BE ORDERED BY THE ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE.

A TXDOT TYPE II B-B BLUE REFLECTIVE RAISED PAVEMENT MARKER SHALL BE INSTALLED IN THE CENTER OF THE ROADWAY ADJACENT TO ALL FIRE HYDRANTS. IN LOCATIONS WHERE HYDRANTS ARE SITUATED ON CORNERS, BLUE REFLECTIVE RAISED PAVEMENT MARKERS SHALL BE INSTALLED ON BOTH APPROACHES WHICH FRONT THE HYDRANT. THE RAISED PAVEMENT MARKER SHALL MEET TXDOT MATERIAL, EPOXY AND ADHESIVE SPECIFICATIONS.

GROUNDWATER

IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER, CONTRACTOR, SUBCONTRACTORS, BUILDERS, GEO-TECHNICAL ENGINEER, AND PROJECT ENGINEER TO IMMEDIATELY NOTIFY THE OFFICE OF THE CITY ENGINEER AND PROJECT ENGINEER IF THE PRESENCE OF GROUNDWATER WITHIN THE SITE IS EVIDENT. UPON NOTIFICATION THE PROJECT ENGINEER SHALL RESPOND WITH PLAN REVISIONS FOR THE MITIGATION OF THE GROUNDWATER ISSUE.

RECORD DRAWINGS

AS PER PLATTING ORDINANCE SECTION 11B-38M: WHEN ALL OF THE IMPROVEMENTS ARE FOUND TO BE CONSTRUCTED AND COMPLETED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS AND WITH THE CITY'S STANDARDS, AND UPON RECEIPT OF ONE SET OF "RECORD DRAWING" PLANS, AND A DIGITAL COPY OF ALL PLANS (PDF COPY) THE CITY ENGINEER SHALL ACCEPT SUCH IMPROVEMENTS FOR THE CITY OF NEW BRAUNFELS, SUBJECT TO THE GUARANTY OF MATERIAL AND WORKMANSHIP PROVISIONS IN THIS SECTION.

CONSTRUCTION NOTE

ENGINEER OF RECORD IS RESPONSIBLE TO ENSURE THAT EROSION CONTROL MEASURES AND STORMWATER CONTROL SUFFICIENT TO MITIGATE OFF SITE IMPACTS ARE IN PLACE AT ALL STAGES OF CONSTRUCTION.

DRAINAGE NOTE

DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE THE IMPACT OF CONSTRUCTION SHALL BE INSTALLED PRIOR TO ADDING IMPERVIOUS COVER.

FINISHED FLOOR ELEVATIONS

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORMWATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO STORMWATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE A PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE GARAGE.

SOILS TESTING

PROCTORS SHALL BE SAMPLED FROM ON-SITE MATERIAL (ON-SITE IS DEFINED AS LIMITS OF CONSTRUCTION FOR THIS

PLAN SET) AND A COPY OF THE PROCTOR RESULTS SHALL BE DELIVERED TO THE CITY OF NEW BRAUNFELS STREET INSPECTOR PRIOR TO ANY DENSITY TESTS.

ROADWAY

ALL ROADWAY COMPACTION TESTS SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FLEXIBLE BASE OR FILL/EMBANKMENT MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED EIGHT INCHES (8") LOOSE. THE REQUIRED DENSITY FOR THE FILL/EMBANKMENT MATERIAL SHALL MEET THE REQUIREMENTS OF TXDOT'S SPECIFICATION ITEM 132. THE REQUIRED DENSITY FOR THE FLEXIBLE BASE MATERIAL SHALL MEET THE REQUIREMENTS OF TXDOT'S SPECIFICATION ITEM 247.


ITEM 340

ASPHALTIC CONCRETE PAVEMENT SHALL BE THE TYPE OF HOT MIX ASPHALT AS DEFINED IN TXDOT'S STANDARD SPECIFICATIONS FOR CURRENT TXDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREET AND BRIDGES.

THE CITY OF NEW BRAUNFELS WILL NOT ACCEPT THE USE OF RECYCLED ASPHALT PAVEMENT (RAP) OR RECYCLED ASPHALT SHINGLES (RAS) IN ASPHALT MIXTURES FOR NEW ROADWAYS. ANY DEBRIS INCLUSIONS WITHIN NEW ASPHALT PAVEMENTS WILL RESULT IN ASPHALT REMOVAL AND REPLACEMENT FROM CURB TO CURB FOR LIMITS TO BE DETERMINED BY THE CITY OF NEW BRAUNFELS.

THE ASPHALTIC CONCRETE PAVEMENT SURFACE COURSE SHALL BE PLANT MIXED, HOT LAID TYPE "D" MEETING THE SPECIFICATION REQUIREMENTS OF TXDOT ITEM 340. THE ASPHALTIC CONCRETE PAVEMENT SUB-SURFACE COURSES SHALL BE PLANT MIXED, HOT LAID TYPE "B" MEETING THE SPECIFICATION REQUIREMENTS OF TXDOT ITEM 340. THE MIXTURE SHALL BE DESIGNATED PER THE DESIGN REQUIREMENTS SPECIFIED IN TXDOT ITEM 340 AND SHALL BE COMPACTED TO BETWEEN 91 AND 95 PERCENT OF THE MAXIMUM THEORETICAL DENSITY AS DETERMINED BY TXDOT TEST METHOD TEX-227-F. PLACE THE MIXTURE WHEN THE ROADWAY SURFACE TEMPERATURE IS AT OR ABOVE 60°. COMPLETE ALL COMPACTION OPERATIONS BEFORE THE PAVEMENT TEMPERATURE DROPS BELOW 160°. THE ASPHALT CEMENT CONTENT BY PERCENT OF TOTAL MIXTURE WEIGHT SHALL FALL WITHIN A TOLERANCE OF +0.5 PERCENT FROM A SPECIFIC MIX DESIGN.

Project location and contact information: 290 S. CASTELL AVE., STE. 100, NEW BRAUNFELS, TX 78130. Contact: TBPE FIRM F-10961, TBPLS FIRM 1053600. Includes HMT Engineering & Surveying logo.



General Notes (1 of 2) and Project Name: KEITH WING TWO-STORY OFFICE NEW BRAUNFELS, TEXAS. Date: 1/24/2023.

Revision table with columns for Revision Number, Description, and Date.

Project Date: JANUARY 2023, Drawn By: WRC, Designed By: JTS, Reviewed By: JTS, HMT Project No.: 429.002.

SHEET

C0.01



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY  
WATER POLLUTION ABATEMENT PLAN  
GENERAL CONSTRUCTION NOTES

1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
  - THE NAME OF THE APPROVED PROJECT;
  - THE ACTIVITY START DATE; AND
  - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.
3. IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SINK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCEQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES NOT BE RESUMED UNTIL THE TCEQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.
4. NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATIONS (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
6. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STEAMS, SENSITIVE FEATURES, ETC.
7. SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
8. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
9. ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARD AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE SITE.
10. IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
11. THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
  - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR
  - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
  - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
12. THE HOLDER OF ANY APPROVED EDWARD AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
  - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
  - B. ANY CHANGE IN NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE IN WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
  - C. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

TCEQ-0592 (REV. JULY 15, 2015)

CITY OF NEW BRAUNFELS CONSTRUCTION NOTES (CONTINUED)  
REVISED 03/2020

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT/SIDEWALK SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEOTECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. DETERMINE THE MAXIMUM LIFT THICKNESS BASED ON THE ABILITY OF THE COMPACTING OPERATION AND EQUIPMENT USED TO MEET THE REQUIRED DENSITY. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEOTECHNICAL ENGINEER AND APPROVED BY THE CITY OF NEW BRAUNFELS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 200 LF FOR EACH LIFT AND EVERY OTHER SERVICE LINE. UPON COMPLETION OF TESTING THE GEOTECHNICAL ENGINEER SHALL PROVIDE THE CITY OF NEW BRAUNFELS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS. ADDITIONAL DENSITY TESTS MAY BE REQUESTED BY THE CITY OF NEW BRAUNFELS INSPECTOR.

CURB CUT DUE TO CONSTRUCTION OF NEW RIGHT-OF-WAY CONSTRUCTION

(INDICATE THE 2 OPTIONS ON THE CONSTRUCTION PLANS).

1. SAWCUT EXISTING STREET AND MATCH TO NEW CONSTRUCTION.
2. SAWCUT EXISTING CURB TO TIE INTO EXISTING CONSTRUCTION.

CONSTRUCTION STABILIZED ENTRANCE

SAWCUT CURB FOR CONSTRUCTION ENTRANCE.

STABILIZED CONSTRUCTION AREA SHALL BE CONSTRUCTED OF 3'X5" ROCK TO BE PLACED A MINIMUM LENGTH OF 25-FT. AND MAINTAINED SO THAT CONSTRUCTION DEBRIS DOES NOT FALL WITHIN THE CITY RIGHT-OF-WAY. RIGHTOF-WAY MUST BE CLEARED FROM MUD, ROCKS, ETC. AT ALL TIMES.

SIGNING AND PAVEMENT MARKING PLAN NOTES

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL REGULATORY AND WARNING SIGNS, STREETS NAME SIGNS AND SIGN MOUNTS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS. THE CITY WILL INSPECT ALL SIGNS AT FINAL INSPECTION.

THE CONTRACTOR SHALL INSTALL ALL PAVEMENT MARKINGS IN ACCORDANCE WITH APPROVED ENGINEERING PLANS.

THE CONTRACTOR SHALL NOTIFY THE CITY AT LEAST TWENTY-FOUR (24 HOURS PRIOR TO THE INSTALLATION OF ALL SEALER AND FINAL MARKINGS. THE CITY WILL INSPECT ALL MARKINGS AT FINAL APPLICATION.

SEEDING AND ESTABLISHMENT OF VEGETATION WITHIN EARTHEN CHANNELS, STORMWATER BASINS AND DISTURBED AREAS

SEEDING FOR THE PURPOSE OF ESTABLISHING VEGETATION WITHIN CONSTRUCTED EARTHEN CHANNELS, BASINS AND DISTURBED AREAS SHALL BE CONDUCTED IN ACCORDANCE WITH ITEM 164 (SEEDING FOR EROSION CONTROL OF TXDOT'S STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS AND BRIDGES MANUAL. ONLY SEED TYPES AND MIXES SPECIFIED FOR THE SAN ANTONIO DISTRICT (DISTRICT 15 IN TABLES 1 AND 2 UNDER ITEM 164 SHALL BE UTILIZED. DURING THE COOL SEASON (SEPT 1-NOV 30, CEREAL RYE AND SEED SPECIES SPECIFIED FOR THE SAN ANTONIO DISTRICT IN TABLE 3 MAY BE USED. FOR COOL SEASON SEEDING APPLICATIONS, COOL SEASON SEED MIXES SHALL BE USED IN CONJUNCTION WITH SEED MIXES FOR THE SAN ANTONIO DISTRICT AS SPECIFIED IN TABLE 1 AND 2 UNDER ITEM 164.


IT MAY BE DEEMED NECESSARY TO INCORPORATE TOPSOIL AND SOIL AMENDMENTS (I.E. COMPOST/ FERTILIZER INTO EXISTING SOIL IN ORDER TO FACILITATE VEGETATION GROWTH. TOPSOIL, COMPOST AND FERTILIZER ADDITIONS SHALL BE CONDUCTED ACCORDING TO ITEMS 160, 161 AND 166 OF TXDOT'S STANDARD SPECIFICATIONS MANUAL, RESPECTIVELY.

AREAS REQUIRING PERMANENT VEGETATION (EARTHEN CHANNELS, PONDS, ETC.) ARE REQUIRED TO MEET TXDOT SPECIFICATIONS FOR ITEM 160 TOPSOIL. TESTING PER TEX-128-E WILL BE REQUIRED AT THE CITY'S REQUEST.

WATERING MAY ALSO BE NECESSARY TO FACILITATE AND EXPEDITE THE SPROUTING AND GROWTH OF VEGETATION. ITEM 168 OF TXDOT'S STANDARD SPECIFICATIONS MANUAL SHALL BE ADHERED TO FOR VEGETATIVE WATERING.

IF EXTENDED DROUGHT CONDITIONS EXIST THAT HINDER OR PROHIBIT THE GROWTH AND ESTABLISHMENT OF VEGETATION, THE CONTRACTOR/ DEVELOPER SHALL PROVIDE A PLAN TO THE CITY OF NEW BRAUNFELS DESCRIBING THE MEASURES THAT WILL BE TAKEN TO STABILIZE EARTHEN DRAINAGE INFRASTRUCTURE UNTIL A TIME WHEN GROWING CONDITIONS BECOME MORE FAVORABLE.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023


GENERAL NOTES  
(2 OF 2)  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE:	JANUARY 2023
DRAWN BY:	WRC
DESIGNED BY:	JTS
REVIEWED BY:	JTS
HMT PROJECT NO.:	429.002

**SHEET**  
**C0.02**






Generated on 08/25/2021 at 10:54

F & F Microfilming, Inc. - © 2021

viewPlat v12.11

FOR REFERENCE ONLY

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

PLAT  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS  
HMT PROJECT NO.: 429.002

SHEET  
C1.00





Drawing Name: N:\Projects\29 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\DWG.dwg User: wllc Jan 24, 2023 - 10:11 am

**Table 1 - Existing Conditions Hydrology Calculations - City of New Braunfels**

Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
EX 1	Site Area to EX 1	EX 1	1.68	10.1	84.0	4.01	8.07	11.2	17.1
EX 2	Site Area to EX 2	EX 2	0.86	10.0	84.0	2.05	4.13	5.73	8.77

**Table 2 - Off-site Conditions Hydrology Calculations - City of New Braunfels**


Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
OS 1	Ridge Hill Dr. ROW	OS 1	0.07	10.0	84.0	0.17	0.34	0.47	0.71



- LEGEND**
- 700 --- EXISTING CONTOURS
  - 700 — PROPOSED CONTOURS
  - B.L. — BUILDING SETBACK LINE
  - U.E. — UTILITY EASEMENT
  - D.E. — DRAINAGE EASEMENT
  - SC — SOLUTION CAVITY
  - DA — DRAINAGE AREA
  - TC — TC — TIME OF CONCENTRATION
  - A-1 ○ POINT OF CONCENTRATION
  - DRAINAGE FLOW DIRECTION
  - DA ACRES ○ DRAINAGE AREA LABEL

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600

**HMT**  
 ENGINEERING & SURVEYING



1/24/2023

**EXISTING DRAINAGE MAP**  
 KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: **JANUARY 2023**  
 DRAWN BY: **WRC**  
 DESIGNED BY: **JTS**  
 REVIEWED BY: **JTS**  
 HMT PROJECT NO.: **429.002**

**SHEET**  
**C2.00**




Drawing Name: N:\Projects\23 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\429\002\_DRNG.dwg User: wllc Jan 24, 2023 - 10:11 am

**Table 3 - Ultimate Proposed Conditions Hydrology Calculations - City of New Braunfels**

Point of Concentration	Description	Drainage Area	Area	T <sub>c</sub>	CN	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
P 1	Contributing to Basin 1	P 1.1	1.24	10.0	93.0	3.83	6.77	9.00	13.3
P 1	Basin Area	P 1.2	0.27	10.0	93.0	0.83	1.48	1.96	2.89
P 1	Area outside Basin 1 to P 1	P 1.3	0.66	10.0	93.0	2.04	3.61	4.79	7.06
P 2	Area to P 2	P 2	0.36	10.0	93.0	1.11	1.97	2.61	3.85

**Table 4 - Existing to Proposed Comparison**

Point of Concentration	Drainage Area	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>100</sub> (cfs)
EX 1	1.68	4.01	8.07	11.2	17.1
P 1	1.51	2.04	4.16	10.4	16.8
Proposed is Less Than or Equal to Existing		YES	YES	YES	YES
EX 2	0.86	2.05	4.13	5.73	8.77
P 2	0.36	1.11	1.97	2.61	3.85
Proposed is Less Than or Equal to Existing		YES	YES	YES	YES



- LEGEND**
- 700 --- EXISTING CONTOURS
  - 700 --- PROPOSED CONTOURS
  - B.L. BUILDING SETBACK LINE
  - U.E. UTILITY EASEMENT
  - D.E. DRAINAGE EASEMENT
  - SC SOLUTION CAVITY
  - DA --- DRAINAGE AREA
  - TC --- TC --- TIME OF CONCENTRATION
  - A-1 ○ POINT OF CONCENTRATION
  - ← DRAINAGE FLOW DIRECTION
  - DA ○ ACRES DRAINAGE AREA LABEL

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600



1/24/2023

**PROPOSED DRAINAGE MAP**  
 KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS


NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
 DRAWN BY: WRC  
 DESIGNED BY: JTS  
 REVIEWED BY: JTS  
 HMT PROJECT NO.: 429.002

**SHEET C2.01**



Drawing Name: N:\Projects\429 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\429.002.DWG User: wllc Jan 24, 2023 - 10:11am



**LEGEND**

— 700 —	EXISTING CONTOURS
○	EXISTING TREE TO BE REMOVED
●	EXISTING TREE TO REMAIN
SC	SOLUTION CAVITY

TREE INDEX			
TAG NO.	TYPE	INDICATES MULTI TRUNK	
123	LO	11 22 33	(11.1)
INDIVIDUAL TRUNK DIA. (IN INCHES)		TOTAL (ROOT ZONE)	
CRITICAL ROOT ZONES (TREE CIRCLES) ARE SHOWN USING THE COA FORMULA FOR SINGLE AND MULTI TRUNK TEES.			
3000	LIVE OAK	15	(TO BE REMOVED)
3001	LIVE OAK	17	(TO BE REMOVED)
3002	ELM	9	(TO BE REMOVED)
3003	ELM	10	(TO BE REMOVED)
3004	LIVE OAK	14	(TO BE REMOVED)
3005	LIVE OAK	12	(TO REMAIN)
3006	ELM	11	(TO REMAIN)
3007	LIVE OAK	14	(TO REMAIN)
3008	LIVE OAK	13	(TO BE REMOVED)
3009	LIVE OAK	19	(TO BE REMOVED)
3010	LIVE OAK	9	(TO BE REMOVED)
3011	LIVE OAK	10	(TO BE REMOVED)
3012	LIVE OAK	16	(TO BE REMOVED)
3014	ELM	9	(TO REMAIN)
3015	LIVE OAK	10	(TO BE REMOVED)
3016	LIVE OAK	14	(TO BE REMOVED)
3017	LIVE OAK	14	(TO BE REMOVED)
3018	LIVE OAK	14	(TO BE REMOVED)
3019	LIVE OAK	10	(TO REMAIN)
3020	ELM	13	(TO REMAIN)
3021	LIVE OAK	10	(TO REMAIN)
3022	ELM	9	(TO REMAIN)
3023	ELM	10	(TO REMAIN)
3024	ELM	11	(TO REMAIN)
3025	ELM	12	(TO REMAIN)
3026	ELM	9	(TO REMAIN)
3027	LIVE OAK	14	(TO BE REMOVED)
3028	LIVE OAK	14	(TO REMAIN)
3029	ELM	12	(TO REMAIN)

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBP# FIRM F-10961  
TBP# FIRM 1053600



1/24/2023

**DEMOLITION PLAN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE



DATE: **JANUARY 2023**  
DRAWN BY: **WRC**  
DESIGNED BY: **JTS**  
REVIEWED BY: **JTS**

HMT PROJECT NO.: **429.002**

**SHEET**  
**C3.00**



Drawing Name: N:\Projects\29 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\429\002\_EROS.dwg User: willc Jan 25, 2023 - 11:48am



**LEGEND**

- 700 — EXISTING CONTOURS
- 700 — PROPOSED CONTOURS
- B.L. BUILDING SETBACK LINE
- U.E. UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- SC SOLUTION CAVITY
- DRAINAGE FLOW DIRECTION
- SF — SF — SILT FENCE
- LOC — LOC — LIMIT OF CONSTRUCTION
- TP — TP — TP — TREE PROTECTION
- [Brick Pattern] STABILIZED CONSTRUCTION ENTRANCE
- [Hatched Pattern] FILTER DIKE CURB INLET PROTECTION
- [Dotted Pattern] ROCK BERM

**NOTE:**

PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENT) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING DOES NOT CONSTITUTE AS STABILIZATION.


SILT FENCE AT PROPERTY LINE MAY BE SHOWN GRAPHICALLY OFFSET FROM PROPERTY LINE TO AVOID OVERLAP OF LINEWORK. CONTRACTOR SHALL NOT INSTALL EROSION CONTROL MEASURES BEYOND LIMITS OF CONSTRUCTION REGARDLESS OF GRAPHIC REPRESENTATION.

**SEQUENCE OF CONSTRUCTION**

1. INSTALL EROSION CONTROLS PER APPROVED PLAN.
2. TEMPORARY CONTROLS TO BE INSPECTED AND MAINTAINED WEEKLY AND PRIOR TO ANTICIPATED RAINFALL EVENTS, AND AFTER RAINFALL EVENTS, AS NEEDED. CONTRACTOR/OWNER SHALL PROVIDE A CONTACT NAME AND NUMBER FOR EROSION CONTROL ISSUES.
3. CONDUCT DEMOLITION ACTIVITIES, IF APPLICABLE.
4. CONSTRUCT DRAINAGE IMPROVEMENTS, IF APPLICABLE.
5. CONSTRUCT CURB INLET PROTECTION AT THE TIME OF CURB INLET INSTALLATION.
6. CONSTRUCT DEVELOPMENT PER APPROVED PLANS.
7. INSTALL STREETSCAPE AND/OR LANDSCAPING IMPROVEMENTS.
8. CONTRACTOR TO VEGETATE ANY DISTURBED AREAS ONCE FINAL GRADING IS COMPLETE, AND ESTABLISH A MIN OF 70% VEGETATION PRIOR TO COMPLETION. PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENT) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING DOES NOT CONSTITUTE AS STABILIZATION.
9. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**EROSION CONTROL PLAN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023

DRAWN BY: WRC

DESIGNED BY: JTS

REVIEWED BY: JTS

HMT PROJECT NO.:  
429.002

**SHEET**  
**C4.00**



**CONCRETE WASHOUT AREAS**

THE PURPOSE OF CONCRETE WASHOUT AREAS IS TO PREVENT OR REDUCE THE DISCHARGE OF POLLUTANTS TO STORMWATER FROM CONCRETE WASTE BY CONDUCTING WASHOUT OFFSITE, PERFORMING ONSITE WASHOUT IN A DESIGNATED AREA, AND TRAINING EMPLOYEES AND SUBCONTRACTORS.

THE FOLLOWING STEPS WILL HELP REDUCE STORMWATER POLLUTION FROM CONCRETE WASTES:


- INCORPORATE REQUIREMENTS FOR CONCRETE WASTE MANAGEMENT INTO MATERIAL SUPPLIER AND AGREEMENTS
- AVOID MIXING EXCESS AMOUNTS OF FRESH CONCRETE.
- PERFORM WASHOUT OF CONCRETE TRUCKS IN DESIGNATED AREAS ONLY.
- DO NOT WASH OUT CONCRETE TRUCKS INTO STORM DRAINS, OPEN DITCHES, STREETS, OR STREAMS.
- DO NOT ALLOW EXCESS CONCRETE TO BE DUMPED ONSITE, EXCEPT IN DESIGNATED AREAS.

**FOR ONSITE WASHOUT:**

- LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES, OR WATER BODIES; DO NOT ALLOW RUNOFF FROM THIS AREA BY CONSTRUCTING A TEMPORARY PIT OR BERMED AREA LARGE ENOUGH FOR LIQUID AND SOLID WASTE.
- WASH OUT WASTES INTO THE TEMPORARY PIT WHERE THE CONCRETE CAN SET, BE BROKEN UP, AND THEN DISPOSED PROPERLY.

BELOW GRADE CONCRETE WASHOUT FACILITIES ARE TYPICAL. THESE CONSIST OF A LINED EXCAVATION SUFFICIENTLY LARGE TO HOLD EXPECTED VOLUME OF WASHOUT MATERIAL. ABOVE GRADE FACILITIES ARE USED IF EXCAVATION IS NOT PRACTICAL. TEMPORARY CONCRETE WASHOUT FACILITY (TYPE ABOVE GRADE) SHOULD BE CONSTRUCTED AS SHOWN ON THE DETAILS AT THE END OF THIS SECTION, WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS. PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCE CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.



**CONCRETE WASHOUT PIT DETAIL**

TYPE "ABOVE GRADE"  
NOT TO SCALE

**STABILIZED CONSTRUCTION ENTRANCE / EXIT**

**MATERIALS:**


1. THE AGGREGATE SHOULD CONSIST OF 3 TO 5 INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN.
2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 8 INCHES.
3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2. A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.
4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4 INCH DIAMETER WASHED STONE OR COMMERCIAL RACK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OR BASIN.

**INSTALLATION:**

1. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.
2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.
3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG.
4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE, 6 TO 8 INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.
5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WEATHER CONDITIONS ARE ANTICIPATED.
6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.
7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.
8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.

**INSPECTION AND MAINTENANCE GUIDELINES:**

1. THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL PREVENT TRACKING OR LOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.
3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.
5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.




**CONSTRUCTION ENTRANCE DETAIL**

NOT TO SCALE

**ROCK BERM**

1. USE ONLY OPEN GRADED ROCK 3-5" DIAMETER.
2. THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 1" OPENINGS AND MINIMUM WIRE DIAMETER OF 20 GAUGE.
3. THE ROCK BERM SHALL BE INSPECTED WEEKLY OR AFTER EACH RAIN, AND THE STONE AND/OR FABRIC CORE-WOVEN WIRE SHEATHING SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED, DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT CONSTRUCTION TRAFFIC DAMAGE, ETC.
4. WHEN SILT REACHES A DEPTH EQUAL TO 6", THE SILT WILL BE REMOVED AND DISPOSED OF IN AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CREATE A SILTATION PROBLEM.
5. DAILY INSPECTION SHALL BE MADE ON SEVERE SERVICE ROCK BERMS.
6. WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.



**ROCK BERM DETAIL**

NOT TO SCALE

**SILT FENCE**

**MATERIALS:**


1. SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC WIDTH SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NO. 30.
2. FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR YBAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM NOMINAL WEIGHT 1.25 LB/FT2, AND BRINDELL HARDNESS EXCEEDING 140.
3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

**INSTALLATION:**

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF 1- FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.
2. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.
3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEP UNDER FENCE.
4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.
6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.


**INSPECTION AND MAINTENANCE GUIDELINES:**

1. INSPECT ALL FENCING WEEKLY, AND AFTER ANY RAINFALL.
2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.
3. REPLACE ANY TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.
4. REPLACE OR REPAIR ANY SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.
5. WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.




**SILT FENCE DETAIL**


NOT TO SCALE




**NBU** NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING  
 DRAWN BY: H Shaddock  
 APPROVED BY: [Signature]  
 STANDARD DRAWING: TREE PROTECTION FENCE LOCATIONS  
 UPDATES: 4-29-03  
 SCALE: N.T.S.  
 SHEET: 1 OF 1  
 DRAWING NO.: 510



**NBU** NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING  
 DRAWN BY: H Shaddock  
 APPROVED BY: [Signature]  
 STANDARD DRAWING: TREE PROTECTION FENCE TYPE A - CHAIN LINK  
 UPDATES: 4-29-03  
 SCALE: N.T.S.  
 SHEET: 1 OF 1  
 DRAWING NO.: 511




**NBU** NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING  
 DRAWN BY: H Shaddock  
 APPROVED BY: [Signature]  
 STANDARD DRAWING: FILTER DIKE CURB INLET PROTECTION  
 UPDATES: 4-29-03  
 SCALE: N.T.S.  
 SHEET: 1 OF 1  
 DRAWING NO.: 505



**NBU** NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING  
 DRAWN BY: H Shaddock  
 APPROVED BY: [Signature]  
 STANDARD DRAWING: DROP AREA INLET SEDIMENT TRAP DETAIL  
 UPDATES: 4-29-03  
 SCALE: N.T.S.  
 SHEET: 1 OF 1  
 DRAWING NO.: 506

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600



1/24/2023

**EROSION DETAILS**  
 (1 OF 2)  
 KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS


NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
 DRAWN BY: WRC  
 DESIGNED BY: JTS  
 REVIEWED BY: JTS  
 HMT PROJECT NO.: 429.002

**SHEET**  
**C4.01**

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.






JANUARY 2005  
CITY OF SAN ANTONIO  
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

**TEMPORARY EROSION, SEDIMENT & WATER POLLUTION CONTROL MEASURES STANDARDS 1**

NO. SUBMITTAL PROJECT NO. DATE  
DRAWN BY: S. VAZQUEZ DESIGN BY: CHD BY: SHEET NO. OF



JANUARY 2005  
CITY OF SAN ANTONIO  
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

**TEMPORARY EROSION, SEDIMENT & WATER POLLUTION CONTROL MEASURES STANDARDS 2**

NO. SUBMITTAL PROJECT NO. DATE  
DRAWN BY: S. VAZQUEZ DESIGN BY: CHD BY: SHEET NO. OF


### SEQUENCE OF CONSTRUCTION

- INSTALL EROSION CONTROLS PER APPROVED PLAN.
- TEMPORARY CONTROLS TO BE INSPECTED AND MAINTAINED WEEKLY AND PRIOR TO ANTICIPATED RAINFALL EVENTS, AND AFTER RAINFALL EVENTS, AS NEEDED. CONTRACTOR/OWNER SHALL PROVIDE A CONTACT NAME AND NUMBER FOR EROSION CONTROL ISSUES.
- CONDUCT DEMOLITION ACTIVITIES, IF APPLICABLE.
- CONSTRUCT DRAINAGE IMPROVEMENTS, IF APPLICABLE.
- CONSTRUCT CURB INLET PROTECTION AT THE TIME OF CURB INLET INSTALLATION.
- CONSTRUCT DEVELOPMENT PER APPROVED PLANS.
- INSTALL STREETSCAPE AND/OR LANDSCAPING IMPROVEMENTS.
- CONTRACTOR TO VEGETATE ANY DISTURBED AREAS ONCE FINAL GRADING IS COMPLETE, AND ESTABLISH A MIN OF 70% VEGETATION PRIOR TO COMPLETION. PER TPDES REQUIREMENTS, DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENTLY) SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES WITHIN 21 DAYS. SEEDING DOES NOT CONSTITUTE AS STABILIZATION.
- REMOVE ALL TEMPORARY EROSION CONTROL MEASURES.

NOTE:  
CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DISTURBED AREAS ON WHICH CONSTRUCTION ACTIVITIES HAVE CEASED (TEMPORARILY OR PERMANENT) AND SHALL BE STABILIZED WITHIN 14 DAYS UNLESS ACTIVITY RESUMES IN 21 DAYS, PER TPDES REQUIREMENTS.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBP# FIRM F-10961  
TBP# FIRM 1053600



1/24/2023


**EROSION DETAILS (2 OF 2)**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	DATE

DATE: **JANUARY 2023**  
DRAWN BY: **WRC**  
DESIGNED BY: **JTS**  
REVIEWED BY: **JTS**  
HMT PROJECT NO.: **429.002**  
**SHEET C4.02**



Drawing Name: N:\\_Projects\23 - Keith Wing Custom Builders\02 - Taylor Office Complex\02 SITE.dwg User: willc Jun 24, 2023 - 10:12am



**EXTERIOR LIGHTING NOTES:**  
 NO PORTION OF THE BULB OR DIRECT LAMP IMAGE MAY BE VISIBLE BEYOND A DISTANCE EQUAL TO OR GREATER THAN TWICE THE MOUNTING HEIGHT OF THE FIXTURE. EACH IRC REQUIRED EXTERIOR LIGHT AT UNIT EGRESS DOORS AND PARKING LOT LIGHTING ARE TO MEET CITY ORDINANCE SHIELDING REQUIREMENTS. REFERENCE THE CITY OF NEW BRAUNFELS MUNICIPAL CODE, SECTION 144-5.3-3(A)(2) FOR DETAILED EXTERIOR LIGHTING REQUIREMENTS.


FLEXIBLE PAVEMENT		
LOCATION	LIGHT DUTY AUTO PARKING	HEAVY DUTY ACCESS DRIVE
HOT MIX ASPHALTIC CONCRETE	2.0 IN	2.0 IN
LIMESTONE BASE MATERIAL (TXDOT ITEM 247 GRADE 2)	8.0 IN	12.0 IN
COMPACTED SUBGRADE	6.0 IN	6.0 IN

RIGID PAVEMENT		
LOCATION	LIGHT DUTY AUTO PARKING	HEAVY DUTY ACCESS DRIVE
REINFORCED CONCRETE	5.5 IN	6.0 IN

**NOTE:**

- ALL PAVEMENT CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE TO THE "SUBSURFACE EXPLORATION AND PAVEMENT ANALYSIS, BY ROCK ENGINEERING AND TESTING OF SAN ANTONIO, DATED MARCH 29, 2022."
- ALL PAVEMENT SECTIONS SHOWN ON THE ABOVE TABLE SHALL SUPERCEDE ANY STANDARD DETAILS WITH RESPECT TO DEPTH OF MATERIALS ASSOCIATED WITH THIS PROJECT.
- THE SUBGRADE SHOULD BE STABILIZED USING LIME IN ACCORDANCE WITH THE GEOTECHNICAL REPORT IN ORDER TO ACHIEVE THE FOLLOWING:
  - PLASTICITY INDEX OF **20** OR LESS
  - PH OF **12.4** OR GREATER
- THE SUBGRADE SOILS SHOULD BE TESTED FOR SOLUBLE SULPHATE CONTENT PRIOR TO INSTALLATION OF THE LIME OR CEMENT.






**KEY NOTES**

- ① ACCESS/FIRE LANE PAVEMENT
- ② APRON PAVEMENT
- # PARKING COUNT

**LEGEND**

- U.E. UTILITY EASEMENT
- B.L. BUILDING LINE
- D.E. DRAINAGE EASEMENT
- SC SOLUTION CAVITY
- PROPOSED BOUNDARY LINE
- PROPOSED FIRE LANE
- EDGE OF PAVEMENT
- MASONRY WALL
- PROPOSED FIRE HYDRANT
- EXISTING FIRE HYDRANT
- A.D.A. RAMPS
- A.D.A. PARKING
- TRANSFORMER
- WATER METER
- WATER VALVE
- WASTE WATER MANHOLE
- CLEAN OUT
- BENCHMARK
- O.P.R.C.C.T. OFFICIAL PUBLIC RECORDS OF COMAL COUNTY, TEXAS
- M.P.R.C.C.T. MAP AND PLAT RECORDS OF COMAL COUNTY, TEXAS



THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24- HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600

**HMT**  
 ENGINEERING & SURVEYING

JOSEPH T. SANDOVAL  
 110257  
 LICENSED PROFESSIONAL ENGINEER

1/24/2023

**SITE PLAN**

KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE



DATE: JANUARY 2023  
 DRAWN BY: WRC  
 DESIGNED BY: JTS  
 REVIEWED BY: JTS

HMT PROJECT NO.: 429.002

**SHEET**  
**C5.00**




Drawing Name: N:\Projects\429 - Keith Wing Custom Builders\02 - Taylor Office Complex\429.002\_SITE.dwg User: wilc Jun 24, 2023 - 10:12am



**FIRE LANE NOTES:**

- STRIPING - THE TOP FACE OF ROAD CURBS SHALL BE PAINTED UTILIZING RED TRAFFIC PAINT.
- IF NO CURBS ARE PRESENT, A SIX INCH (6") WIDE STRIPE PAINTED OF TRAFFIC RED PAINT SHALL BE PAINTED ON THE DRIVING SURFACE TO SHOW THE BOUNDARIES OF THE LANE.
  - THE WORDS "NO PARKING FIRE LANE" SHALL BE SPACED AT A MAXIMUM OF 25 FEET APART, ALONG THE LENGTH OF THE FIRE LANES. SEE ILLUSTRATION BELOW.



1 FIRE LANE DETAIL  
N.T.S.

**NOTES:**

- THE FDC FOR THE SPRINKLER SYSTEM SHALL HAVE A 5 INCH STORTZ CONNECTION ON A 30 DEGREE DOWNTURN WITH A KNOX BRAND LOCKING.
- INSTALL A SIGN ABOVE THE FIRE DEPARTMENT CONNECTION STATING "FDC" THE SIGN SHALL BE 7" ABOVE GRAD. THE SIGN SHALL HAVE REFLECTIVE WHITE LETTERS UPON A REFLECTIVE RED BACKGROUND. THE LETTERING SHALL BE MINIMUM 2 INCH STROKE AND MINIMUM 6 INCHES IN HEIGHT. THE SIGN SHALL ALSO HAVE THE ADDRESS/BUILDING NUMBER OF THE STRUCTURE PROTECTED IF A REMOTE FDC IS USED. THE ADDRESS SHALL BE A MINIMUM 2 INCH STROKE.
- FIRE DEPARTMENT CONNECTION SHALL BE LOCATED ON THE STREET SIDE OF THE BUILDING, FULLY VISIBLE AND RECOGNIZABLE FROM THE STREET OR NEAREST POINT OF THE FIRE DEPARTMENT VEHICLE ACCESS. 2012IFC912.2.1

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**FIRE PROTECTION PLAN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: NOVEMBER 2022

DRAWN BY: WRC


DESIGNED BY: JTS

REVIEWED BY: JTS

HMT PROJECT NO.:  
429.002

**SHEET**  
**C5.01**






NOTE:

- DUMPSTER ENCLOSURE DOORS SHALL BE NO LESS THEN THE ENCLOSURE OPENING.
- TO ALLOW THE ENCLOSURE DOORS TO OPEN 180°, THE BOTTOM OF THE DOORS SHALL BE 6" ABOVE GRADE.
- DUMPSTER PAD ENCLOSURE DETAIL FOUND IN CITY OF NEW BRAUNFELS CODE OF ORDINANCES: CHAPTER 110, ARTICLE 2, DIVISION, 2 SECTION 110-58 - CONTAINER PADS AND ENCLOSURES FOR COMMERCIAL CONTAINERS.





**SINGLE - WIDE CONTAINER ENCLOSURE CONFIGURATION**



MAY 2009  
CITY OF SAN ANTONIO  
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

**WHEELCHAIR RAMP STANDARDS**

NO. SUBMITTAL PROJECT NO. DATE:  
DRAWN BY: VASQUEZ, DESIGN BY: CHOI, BY: S.A. HOBBS, P.E. SHEET NO. OF



290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600

**HMT**  
ENGINEERING & SURVEYING

STATE OF TEXAS  
JOSEPH T. SANDOVAL  
110257  
LICENSED PROFESSIONAL ENGINEER

1/24/2023

**SITE DETAILS (1 OF 2)**

KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	DATE

DATE: NOVEMBER 2022  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS  
HMT PROJECT NO.: 429.002

**SHEET C5.02**


Drawing Name: N:\\_Projects\23 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\02 SITE.dwg User: wllc Jan 25, 2023 - 1:13pm










Drawing Name: N:\Projects\229 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\229\02\02\02.dwg User: mllc Jan 24, 2023 - 10:13am



DETAIL  
1" = 5'



DETAIL  
1" = 5'



LEGEND

- 700 --- EXISTING CONTOURS
- 700** PROPOSED CONTOURS
- B.L. BUILDING SETBACK LINE
- U.E. UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- M.E. MATCH EXISTING
- SC SOLUTION CAVITY
- 1.00% SLOPE DIRECTION
- FF=XXX.X MINIMUM FINISHED FLOOR ELEVATION
- TOW TOP OF WALL
- TP TOP OF PAVEMENT
- BOW BOTTOM OF WALL
- [Pattern] LANDING
- [Pattern] SIDEWALK
- [Pattern] DECOMPOSED GRANITE

EARTHWORK VOLUMES	
EXCAVATION & EMBANKMENT	VOLUME (CY)
CUT	1,207
FILL	10,087
NET	8,880 [FILL]

RETAINING WALL NOTE:  
RETAINING WALL STRUCTURAL ENGINEERING DESIGN SHALL BE PROVIDED BY CONTRACTOR PRIOR TO CONSTRUCTION. A SEPARATE COMMERCIAL PERMIT WILL BE REQUIRED FOR THE PROPOSED RETAINING WALLS. THE BASIN RETAINING WALLS MUST BE STRUCTURALLY DESIGNED TO WITHSTAND THE EXPECTED HYDROSTATIC AND HYDRODYNAMIC FORCES.

- NOTES:
- DRAINAGE IMPROVEMENTS SUFFICIENT TO MITIGATE OFFSITE IMPACT OF CONSTRUCTION MUST BE COMPLETED AND IN PLACE PRIOR TO ADDING IMPERVIOUS COVER TO THE SITE.
  - ALL FINISHED FLOOR ELEVATIONS SHALL MEET THE FOLLOWING REQUIREMENTS:  
2.A. DETAIL SHEET C6.01.
  - WHEN POSSIBLE, CONTRACTOR SHALL PHASE GRADING SO AS TO EXPOSE THE MINIMUM AMOUNT OF AREA TO SOIL EROSION FOR THE SHORTEST PERIOD OF TIME.
  - FOR ANY LOTS ADJACENT TO A DRAINAGE STRUCTURE, HOME BUILDER TO ENSURE FINISHED FLOOR HAS A MINIMUM ELEVATION AS LABELED OR AS PER NOTE 2 ABOVE, WHICHEVER IS GREATER.
  - STRIPPING OF VEGETATION FROM PROJECT SITES SHALL BE PHASED SO AS TO EXPOSE THE MINIMUM AMOUNT OF AREA TO SOIL EROSION FOR THE SHORTEST POSSIBLE PERIOD OF TIME PER THE NEW BRAUNFELS DRAINAGE AND EROSION CONTROL DESIGN MANUAL SEC. 12.2(N).
  - ALL SPOTS ARE TOP OF CURB. UNLESS OTHERWISE NOTED
  - ALL SIDEWALKS SHALL HAVE A CROSS SLOPE OF NO GREATER THAN 2.0%, AND A RUNNING SLOPE OF NO GREATER THAN 5%.

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**GRADING PLAN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	DATE


DATE: **JANUARY 2023**  
DRAWN BY: **WRC**  
DESIGNED BY: **JTS**  
REVIEWED BY: **JTS**  
HMT PROJECT NO.: **429.002**  
**SHEET**  
**C6.00**








Drawing Name: N:\Projects\23 - Keith Wing Custom Builders\02 - Taylor Office Complex\429.002\_STRM.dwg User: wllc Jan 24, 2023 - 10:13am



**LEGEND**

--- 700 ---	EXISTING CONTOURS
--- 700 ---	PROPOSED CONTOURS
B.L.	BUILDING SETBACK LINE
U.E.	UTILITY EASEMENT
D.E.	DRAINAGE EASEMENT
S.B.C.	SINGLE BOX CULVERT
SC	SOLUTION CAVITY
---	PROPOSED STORM DRAIN LINE
⊗	UTILITY CROSSING



**SEEDING AND ESTABLISHMENT OF VEGETATION WITHIN EARTHEN CHANNELS, STORMWATER BASINS AND DISTURBED AREAS**

SEEDING FOR THE PURPOSE OF ESTABLISHING VEGETATION WITHIN CONSTRUCTED EARTHEN CHANNELS, BASINS AND DISTURBED AREAS SHALL BE CONDUCTED IN ACCORDANCE WITH ITEM 164 (SEEDING FOR EROSION CONTROL OF TxDOT'S STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MAINTENANCE OF HIGHWAYS, STREETS AND BRIDGES MANUAL. ONLY SEED TYPES AND MIXES SPECIFIED FOR THE SAN ANTONIO DISTRICT (DISTRICT 15 IN TABLES 1 AND 2 UNDER ITEM 164 SHALL BE UTILIZED. DURING THE COOL SEASON (SEPT 1-NOV 30, CEREAL RYE AND SEED SPECIES SPECIFIED FOR THE SAN ANTONIO DISTRICT IN TABLE 3 MAY BE USED. FOR COOL SEASON SEEDING APPLICATIONS, COOL SEASON SEED MIXES SHALL BE USED IN CONJUNCTION WITH SEED MIXES FOR THE SAN ANTONIO DISTRICT AS SPECIFIED IN TABLE 1 AND 2 UNDER ITEM 164.

IT MAY BE DEEMED NECESSARY TO INCORPORATE TOPSOIL AND SOIL AMENDMENTS (I.E. COMPOST/ FERTILIZER INTO EXISTING SOIL IN ORDER TO FACILITATE VEGETATION GROWTH. TOPSOIL, COMPOST AND FERTILIZER ADDITIONS SHALL BE CONDUCTED ACCORDING TO ITEMS 160, 161 AND 166 OF TxDOT'S STANDARD SPECIFICATIONS MANUAL, RESPECTIVELY.

AREAS REQUIRING PERMANENT VEGETATION (EARTHEN CHANNELS, PONDS, ETC.) ARE REQUIRED TO MEET TxDOT SPECIFICATIONS FOR ITEM 160 TOPSOIL. TESTING PER TEX-128-E WILL BE REQUIRED AT THE CITY'S REQUEST.

WATERING MAY ALSO BE NECESSARY TO FACILITATE AND EXPEDITE THE SPROUTING AND GROWTH OF VEGETATION. ITEM 168 OF TxDOT'S STANDARD SPECIFICATIONS MANUAL SHALL BE ADHERED TO FOR VEGETATIVE WATERING.

IF EXTENDED DROUGHT CONDITIONS EXIST THAT HINDER OR PROHIBIT THE GROWTH AND ESTABLISHMENT OF VEGETATION, THE CONTRACTOR/ DEVELOPER SHALL PROVIDE A PLAN TO THE CITY OF NEW BRAUNFELS DESCRIBING THE MEASURES THAT WILL BE TAKEN TO STABILIZE EARTHEN DRAINAGE INFRASTRUCTURE UNTIL A TIME WHEN GROWING CONDITIONS BECOME MORE FAVORABLE.

**DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:**

SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.

- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- C. BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW (IE: NO STANDING WATER IS ALLOWED).
- E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- F. MAINTENANCE VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO LESSER SIZE.

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023


**OVERALL STORM**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE



DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS

HMT PROJECT NO.: 429.002  
**SHEET C7.00**





- LEGEND**
- 700 --- EXISTING CONTOURS
  - 700 --- PROPOSED CONTOURS
  - B.L. BUILDING SETBACK LINE
  - U.E. UTILITY EASEMENT
  - D.E. DRAINAGE EASEMENT
  - S.B.C. SINGLE BOX CULVERT
  - SC SOLUTION CAVITY
  - ==== PROPOSED STORM DRAIN LINE
  - ⊗ UTILITY CROSSING



**DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:**


- SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.
- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
  - B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
  - C. BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
  - D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW (IE: NO STANDING WATER IS ALLOWED).
  - E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
  - F. MAINTENANCE VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO LESSER SIZE.

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

Drawing Name: N:\Projects\329 - Keith Wing Custom Builders\02 - Taylor Office Complex\03\429.002\_STRM.dwg User: wllc Jan 24, 2023 - 10:13am

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**STORM DRAIN LINE A  
PLAN AND PROFILE**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS

HMT PROJECT NO.: 429.002

**SHEET  
C7.01**




Drawing Name: N:\Projects\329 - Keith Wing Complex\Bldg\02 - Taylor Office Complex\02\STRM.dwg User: wllc Jan 24, 2023 - 10:13am

**DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:**


SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.

- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- C. BASINS SHALL BE MOWED ANNUALLY BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW (I.E. NO STANDING WATER IS ALLOWED).
- E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- F. MAINTENANCE VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO LESSER SIZE.




① PILOT CHANNEL N.T.S.

- UTILITY NOTES:
- 1. ALL UTILITIES TO BE CONSTRUCTED PRIOR TO THE STREETS.
  - 2. NO VALVES, HYDRANTS, CLEANOUTS, ECT. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALK OR DRIVEWAYS.



**LEGEND**

	EXISTING CONTOURS
	PROPOSED CONTOURS
	B.L. BUILDING SETBACK LINE
	U.E. UTILITY EASEMENT
	D.E. DRAINAGE EASEMENT
	M.E. MATCH EXISTING
	S.B.C. SINGLE BOX CULVERT
	SC SOLUTION CAVITY
	PROPOSED STORM DRAIN LINE
	UTILITY CROSSING



**RETAINING WALL NOTE:**  
RETAINING WALL STRUCTURAL ENGINEERING DESIGN SHALL BE PROVIDED BY CONTRACTOR PRIOR TO CONSTRUCTION. A SEPARATE COMMERCIAL PERMIT WILL BE REQUIRED FOR THE PROPOSED RETAINING WALLS. THE BASIN RETAINING WALLS MUST BE STRUCTURALLY DESIGNED TO WITHSTAND THE EXPECTED HYDROSTATIC AND HYDRODYNAMIC FORCES.

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**BATCH DETENTION BASIN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE


DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS

HMT PROJECT NO.: 429.002

**SHEET C7.02**





Drawing Name: N:\\_Projects\329 - Keith Wing Custom Builders\02 - Taylor Office Complex\02 STRM.dwg User: wllc Jan 24, 2023 - 10:13am



**DRAINAGE FEATURES, DETENTION BASIN MAINTENANCE AND EQUIPMENT ACCESS REQUIREMENTS:**


SILT SHALL BE REMOVED AND THE BASIN RETURNED TO ORIGINAL LINES AND GRADES WHEN STANDING WATER CONDITIONS OCCUR OR THE BASIN STORAGE VOLUME IS REDUCED BY MORE THAN 10%.

- A. TO LIMIT EROSION, NO UNVEGETATED AREA SHALL EXCEED 10 SQ. FT. IN EXTENT.
- B. ACCUMULATED PAPER, TRASH, AND DEBRIS SHALL BE REMOVED EVERY 6 MONTHS OR AS NECESSARY TO MAINTAIN PROPER OPERATION.
- C. BASINS SHALL BE MOWED BETWEEN THE MONTHS OF JUNE AND SEPTEMBER.
- D. CORRECTIVE MAINTENANCE IS REQUIRED ANY TIME A BASIN DOES NOT DRAIN COMPLETELY WITHIN 60 HOURS OR CESSATION OF INFLOW (IE: NO STANDING WATER IS ALLOWED).
- E. STRUCTURAL INTEGRITY OF BASINS SHALL BE MAINTAINED AT ALL TIMES.
- F. MAINTENANCE VEHICLE FOR POND ACCESS SHOULD BE A BOBCAT S175 SKID STEER LOADER OR VEHICLE OF EQUAL TO LESSER SIZE.




- UTILITY NOTES:**
- ALL UTILITIES TO BE CONSTRUCTED PRIOR TO THE STREETS.
  - NO VALVES, HYDRANTS, CLEANOUTS, ECT. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALK OR DRIVEWAYS.



**BASIN SECTION A-A**  
1+60 - 3+20




**BASIN SECTION C-C**  
0+80 - 2+80



**BASIN SECTION B-B**  
0+80 - 3+60



**1 BASIN 1 OUTFALL SECTION**  
N.T.S.




**2 OUTFALL SECTION E-E**  
N.T.S.

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBP# FIRM F-10961  
TBP# FIRM 1053600



1/24/2023  
**COMBINED DETENTION & WATER QUALITY CROSS SECTIONS**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS


NO.	REVISION DESCRIPTION	REVISION DATE

DATE: **JANUARY 2023**  
DRAWN BY: **WRC**  
DESIGNED BY: **JTS**  
REVIEWED BY: **JTS**


HMT PROJECT NO.:  
**429.002**  
**SHEET C7.03**





Drawing Name: N:\\_Projects\29 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\DWG\NLS\_HB.dwg User: willc Jun 24, 2023 - 10:14am



DATE APPROVED: 07/2008	DWG. NO: ST-023	SCALE: N.T.S.	 <b>City of New Braunfels</b> ENGINEERING DEPARTMENT
DRAWN BY: RAS	SHEET: 1 OF 1		
FILENAME: RIPRAP HEADWALL			




 <b>Capital Precast</b> 6905 SOUTH OLD BASTROP HWY SAN MARCOS, TEXAS 78666 PH. (830) 686-6200	FOR 5' x 5' x var Grate Inlet							
	JOB							
	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>DRAWN: RW</td> <td>DATE: 12/1/2015</td> <td>Rev. No.</td> <td>SHEET</td> </tr> <tr> <td>FILE: catalog/grate inlets/5x5 Grate Inlet</td> <td></td> <td></td> <td style="text-align: center;">1 OF 1</td> </tr> </table>	DRAWN: RW	DATE: 12/1/2015	Rev. No.	SHEET	FILE: catalog/grate inlets/5x5 Grate Inlet		
DRAWN: RW	DATE: 12/1/2015	Rev. No.	SHEET					
FILE: catalog/grate inlets/5x5 Grate Inlet			1 OF 1					



 <b>ADS Nyloplast</b> 3138 VERONA AVE BUFORD, GA 30518 PHN (770) 932-2442 FAX (770) 932-2440 www.nyloplast-us.com	THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONFER, TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION SHOWN HEREIN.	DRAWN BY: NMH	MATERIAL: DUCTILE IRON FRAME BRONZE GRATE
	DATE: 7-25-19	DATE: 7-25-19	PROJECT NO: NAME
	DATE: 7-25-19	DATE: 7-25-19	TITLE: 8 IN BRONZE GRATE ASSEMBLY - TYPE B
DWG SIZE: A	SCALE: 1:4	SHEET: 1 OF 1	DWG NO.: 7001-110-061 REV: A

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**STORM DETAILS**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS


NO.	REVISION DESCRIPTION	REVISION DATE

DATE: **JANUARY 2023**  
 DRAWN BY: **WRC**  
 DESIGNED BY: **JTS**  
 REVIEWED BY: **JTS**  
 HMT PROJECT NO.: **429.002**  
**SHEET C7.04**




	Q <sub>2</sub> (cfs)	Q <sub>10</sub> (cfs)	Q <sub>25</sub> (cfs)	Q <sub>50</sub> (cfs)	Q <sub>100</sub> (cfs)
Discharge (cfs)	0.31	2.87	6.85	9.06	10.85
Volume	9908	25367	37312	48053	60444
Water Surface Elevation	825.60	826.57	827.85	827.12	827.39
Freeboard (ft)	3.40	2.43	2.15	1.88	1.61




	WQ Volume Required (CUFT)	WQ Volume Provided (CUFT)	WQTY Storage Depth (FT)	TSS Removal Required (LBS)	TSS Removed (LBS)	Efficiency
Batch Detention Basin A	4147	10031	2.00	996	1228	91%




① PILOT CHANNEL N.T.S.



② CONCRETE RIP-RAP N.T.S.




③ SLOPING CONCRETE HEADWALL N.T.S.



- STONE  
STONE FILL MATERIAL SHALL CONSIST OF HARD, DURABLE, CLEAN STONE OF THE SIZE INDICATED, 5 TO 8 INCHES IN SIZE OR AS APPROVED BY THE ENGINEER AND RESISTANT TO THE ACTION OF AIR AND WATER AND SUITABLE IN ALL RESPECTS FOR THE PURPOSE INTENDED.
- WIRE CONTAINERS  
WIRE MESH SHALL CONSIST OF PLASTIC COATED (P.V.C.) GALVANIZED WIRE 0.120 INCH IN DIAMETER MINIMUM AND SHALL EQUAL OR EXCEED FEDERAL SPECIFICATION QQ-W-461G, CLASS 3 UNLESS OTHERWISE INDICATED. OPENING OF THE MESH SHALL NOT EXCEED APPROXIMATELY 4 INCHES IN THE LONGEST DIMENSION. THE WIRE MESH IS TO BE FABRICATED IN SUCH MANNER AS TO BE NONRAVELING, TIE AND CONNECTING WIRE SHALL BE OF THE SAME TYPE AND SIZE AS THE BASKETS AND SHALL BE SUPPLIED IN SUFFICIENT QUANTITY FOR SECURELY FASTENING ALL EDGES OF THE GABION AND DIAPHRAGMS.
- FILTER FABRIC  
FILTER FABRIC SHALL BE NON-BIODEGRADABLE ULTRAVIOLET STABILIZED, INERT TO MOST SOIL CHEMICALS, UNAFFECTED BY MOISTURE WHICH ALLOWS WATER TO PASS THROUGH WHILE RETAINING SOIL PARTICLES AND SHALL CONFORM TO ITEM NO. 620, "FILTER FABRIC".

GABION MATTRESS DETAIL SCALE: N.T.S.



- NOTES:
- LINER AND PROTECTIVE GEOTEXTILE FABRIC, ARE TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
  - GEOMEMBRANE LINER SHALL HAVE A MINIMUM THICKNESS OF FORTY-FIVE (45) MILS.
  - SELECTION OF FINAL LINER WILL BE IDENTIFIED IN CERTIFICATION LETTER TO TCEQ AFTER COMPLETION OF BASIN CONSTRUCTION.

LINER DETAIL NOT-TO-SCALE

CLAY LINER SPECIFICATIONS (ALTERNATE FOR GEOMEMBRANE POLY LINER)

PROPERTY	TEST METHOD	SPECIFICATION
CLAY COMPACTION (%)	ASTM D 2434	
PLASTICITY INDEX OF CLAY (%)	ASTM D 423/30 424	NOT LESS THAN 15
PERMEABILITY (CM/SEC)	ASTM D 2216	NOT LESS THAN 30
CLAY PARTICLES PASSING (%)	ASTM D 422	NOT LESS THAN 30
LIQUID LIMIT OF CLAY (%)	ASTM D 2216	95% OF STANDARD PROCTOR DENSITY


- NOTES:
- THE CLAY LINER SHALL HAVE A MINIMUM THICKNESS OF TWELVE (12) INCHES.

GEOMEMBRANE POLY LINER

- ULTRAVIOLET RESISTANT
- THICKNESS = 45 MILS MINIMUM
- JOINTS SHALL BE WATER TIGHT AT SEAMS
- ANCHOR TO WALLS
- WATERTIGHT SEAL BETWEEN POLY LINER AND TRANSITION SURFACES
- BEDDING MATERIAL SHALL BE SUITABLY COMPACTED MATERIAL (NOT SAND) IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS
- PROTECTIVE GEOTEXTILE FABRIC TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS

REFER TO THE COVER SHEET FOR BENCHMARK INFORMATION.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24-HOURS PRIOR TO COMMENCING CONSTRUCTION.



NOTE: ENGINEER OF RECORD TO REVIEW, APPROVE AND ENDORSE FINAL SITE SPECIFIC DESIGN.

smartPOND Automated Stormwater Control

CONSTRUCTION ECO SERVICES

smartBATCH Valve with VERTICAL WALL

0 5/29/2020

PROGRAMMABLE LOGIC FLOW CHART

TRASH CAGE WITH PERFORATED RISER PIPE

PERFORATED RISER PIPE

smartPOND Valve with Berm

Parts List

CONSTRUCTION ECO SERVICES

smartPOND Automated Stormwater Control

CONVERGENT WATER TECHNOLOGIES

smartPOND Valve SPECIFICATION

Continuously Monitored Automated Stormwater System with Valve

1. Introduction

2. Components

3. Installation and Configuration

4. Operation

5. Maintenance

6. Troubleshooting

7. Safety

8. Warranty


9. Notes

CONSTRUCTION ECO SERVICES

smartPOND Valve Specifications

0 12/27/2021

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBP# FIRM F-10961  
TBP#LS FIRM 1053600



1/24/2023

BASIN DETAILS

KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023

DRAWN BY: WRC

DESIGNED BY: JTS



REVIEWED BY: JTS

HMT PROJECT NO.: 429.002

SHEET C7.05



Drawing Name: N:\\_Projects\29 - Keith Wing Custom Builders\02 - Taylor Office Complex\02 SITE.dwg User: wilc Jun 24, 2023 - 10:14am



**LEGEND**

- U.E. UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- B.L. BUILDING SETBACK LINE
- SC SOLUTION CAVITY
- EDGE OF PAVEMENT
- SEWER SERVICE
- WATER SERVICE
- OE OVERHEAD ELECTRIC
- UGE UNDERGROUND ELECTRIC
- EX W EXISTING WATER LINE
- WW EXISTING WASTEWATER LINE
- MASONRY FENCE
- PROPOSED FIRE HYDRANT
- EXISTING FIRE HYDRANT
- A.D.A. RAMPS
- A.D.A. PARKING
- TRANSFORMER
- WATER METER
- WATER VALVE
- EXISTING MANHOLE
- CLEAN OUT
- LIGHT POLE
- O.P.R.G.C.T. OFFICIAL PUBLIC RECORDS OF GUADALUPE COUNTY, TEXAS

**UTILITY NOTES:**

1. ALL UTILITIES TO BE CONSTRUCTED PRIOR TO THE STREETS.
2. NO VALVES, HYDRANTS, ETC. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALKS OR DRIVEWAYS.
3. THIS SITE IS IN THE KERLICK PRESSURE ZONE ACCORDING TO NEW BRAUNFELS UTILITIES PRESSURE RECORDER LOCATIONS.
4. CONTRACTOR TO VERIFY EXISTING LATERAL HAS A MINIMUM LONGITUDINAL SLOPE OF 2%.
5. POINT OF DELIVERY SHALL BE IN ACCORDANCE WITH NBU WATER AND WASTEWATER DESIGN CRITERIA MANUAL, SECTION 2.3.0.
6. MAXIMUM 6-HOUR SHUTDOWN AND NOTIFICATION OF NBU A MINIMUM OF A WEEK IN ADVANCE.
7. POINT OF DELIVERY IS WATER METER. NBU IS RESPONSIBLE FROM WATER MAIN TO WATER METER. CUSTOMER IS RESPONSIBLE FOR LINE FROM THE METER TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.
8. POINT OF DELIVERY IS DETERMINED BY NBU AND MAY NOT BE CLEANOUT, IT MAY BE A PROPERTY LINE OR EASEMENT BOUNDARY. NBU IS RESPONSIBLE FROM MAIN TO CLEANOUT OR PROPERTY LINE. CUSTOMER IS RESPONSIBLE FOR PIPE FROM THE CLEANOUT/PROPERTY LINE TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.
9. WASTEWATER SERVICE LATERALS SHALL BE LAID WITH AT LEAST 36 INCHES OF COVER.
10. WHERE NEW CONSTRUCTION CONNECTS TO AN EXISTING MANHOLE THAT IS NOT CONSTRUCTED OF A CORROSION-RESISTANT MATERIAL, THE EXISTING MANHOLE MUST BE LINED WITH OR REPLACED WITH A CORROSION-RESISTANT MATERIAL.

OVERALL WATER STRUCTURE TOTALS							
PIPE SIZE	PIPE LENGTH	METER SIZE (IN)	NUMBER OF METERS	VALVE SIZE (IN)	NUMBER OF VALVES	FIRE HYDRANTS	FIRE LINES
8	243	1.5	1	8	3	0	1
6	181	0	0	0	0	0	0
2	180	0	0	0	0	0	0

WASTEWATER STRUCTURE TOTALS		
PIPE SIZE (IN.)	PIPE LENGTH (FT)	MANHOLES
6	62	0

**TRENCH EXCAVATION SAFETY PROTECTION**

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24- HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**OVERALL UTILITY PLAN**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS



NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS  
HMT PROJECT NO.: 429.002

**SHEET**  
**C8.00**



Drawing Name: N:\\_Projects\29 - Keith Wing Custom Builders\02 - Taylor Office Complex\02\_Site.dwg User: willc Jan 25, 2023 - 11:40am



**LEGEND**


- U.E. UTILITY EASEMENT
- D.E. DRAINAGE EASEMENT
- B.L. BUILDING SETBACK LINE
- SC SOLUTION CAVITY
- EDGE OF PAVEMENT
- SEWER SERVICE
- WATER SERVICE
- OE OVERHEAD ELECTRIC
- UGE UNDERGROUND ELECTRIC
- EX W EXISTING WATER LINE
- WW EXISTING WASTEWATER LINE
- MASONRY FENCE
- PROPOSED FIRE HYDRANT
- EXISTING FIRE HYDRANT
- A.D.A. RAMPS
- A.D.A. PARKING
- TRANSFORMER
- WATER METER
- WATER VALVE
- EXISTING MANHOLE
- CLEAN OUT
- LIGHT POLE
- O.P.R.G.C.T. OFFICIAL PUBLIC RECORDS OF GUADALUPE COUNTY, TEXAS

**UTILITY NOTES:**

1. MAXIMUM 6-HOUR SHUTDOWN AND NOTIFICATION OF NBU A MINIMUM OF A WEEK IN ADVANCE.
2. POINT OF DELIVERY IS WATER METER. NBU IS RESPONSIBLE FROM WATER MAIN TO WATER METER. CUSTOMER IS RESPONSIBLE FOR LINE FROM THE METER TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.
3. POINT OF DELIVERY IS DETERMINED BY NBU AND MAY NOT BE CLEANOUT, IT MAY BE A PROPERTY LINE OR EASEMENT BOUNDARY. NBU IS RESPONSIBLE FROM MAIN TO CLEANOUT OR PROPERTY LINE. CUSTOMER IS RESPONSIBLE FOR PIPE FROM THE CLEANOUT/PROPERTY LINE TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24- HOURS PRIOR TO COMMENCING CONSTRUCTION.

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**UTILITY SITE PLAN  
(1 OF 2)  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS**





NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS

HMT PROJECT NO.: 429.002

**SHEET  
C8.01**





- LEGEND**
- U.E. UTILITY EASEMENT
  - D.E. DRAINAGE EASEMENT
  - B.L. BUILDING SETBACK LINE
  - SC SOLUTION CAVITY
  - EDGE OF PAVEMENT
  - SEWER SERVICE
  - WATER SERVICE
  - OE OVERHEAD ELECTRIC
  - UGE UNDERGROUND ELECTRIC
  - EX EXISTING WATER LINE
  - WV EXISTING WASTEWATER LINE
  - MASONRY FENCE
  - PROPOSED FIRE HYDRANT
  - EXISTING FIRE HYDRANT
  - A.D.A. RAMPS
  - A.D.A. PARKING
  - TRANSFORMER
  - WATER METER
  - WATER VALVE
  - EXISTING MANHOLE
  - CLEAN OUT
  - LIGHT POLE
  - O.P.R.G.C.T. OFFICIAL PUBLIC RECORDS OF GUADALUPE COUNTY, TEXAS

- UTILITY NOTES:**
- MAXIMUM 6-HOUR SHUTDOWN AND NOTIFICATION OF NBU A MINIMUM OF A WEEK IN ADVANCE
  - POINT OF DELIVERY IS WATER METER. NBU IS RESPONSIBLE FROM WATER MAIN TO WATER METER. CUSTOMER IS RESPONSIBLE FOR LINE FROM THE METER TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.
  - POINT OF DELIVERY IS DETERMINED BY NBU AND MAY NOT BE CLEANOUT. IT MAY BE A PROPERTY LINE OR EASEMENT BOUNDARY. NBU IS RESPONSIBLE FROM MAIN TO CLEANOUT OR PROPERTY LINE. CUSTOMER IS RESPONSIBLE FOR PIPE FROM THE CLEANOUT/PROPERTY LINE TO PRIVATE PLUMBING, INCLUDING DESIGN, CONSTRUCTION, OPERATION, AND COMPLIANCE WITH CITY CODES.
  - WASTEWATER SERVICE LATERALS SHALL BE LAID WITH AT LEAST 36 INCHES OF COVER.
  - WHERE NEW CONSTRUCTION CONNECTS TO AN EXISTING MANHOLE THAT IS NOT CONSTRUCTED OF A CORROSION-RESISTANT MATERIAL, THE EXISTING MANHOLE MUST BE LINED WITH OR REPLACED WITH A CORROSION-RESISTANT MATERIAL.
  - CONTRACTOR TO MATCH EXISTING SEWER INLET CROWN ELEVATION TO PROPOSED CROWN ELEVATION AT MANHOLE TIE-IN.

- RESTRAINED LENGTH NOTES:**
- CONTRACTOR TO COORDINATE WITH NEW BRAUNFELS UTILITIES (N.B.U.) FOR WATER, SEWER, AND ELECTRIC SERVICE TO THE SITE.
  - ALL DUCTILE IRON VALVES, BENDS & PLUGS SHALL BE RESTRAINED, RESTRAINT TO BE PROVIDED ON EACH SIDE OF THE VALVE, FITTING OR ANY REQUIRED JOINT.
  - RL=RESTRAINT LENGTH

**RESTRAINED LENGTH FOR PIPE**


PIPE INSIDE DIAMETER	MATERIAL	HORIZONTAL BENDS										VERTICAL BENDS					DEAD END/ INCLINE VALVES
		UPPER					LOWER					UPPER	LOWER	UPPER	LOWER		
		90°	45°	22.5°	11.25°	45°	22.5°	11.25°	45°	22.5°	11.25°						
8"	PVC	37	16	8	4	4.3	2.1	1.1	1.3	7	4	71					
8"	DUCTILE IRON	28	12	6	3	2.3	1.1	6	10	5	3	39					
12"	PVC	53	22	11	6	6.2	3.0	1.5	1.9	9	5	102					

**TEE**

PIPE INSIDE DIAMETER OF RUN	PIPE INSIDE DIAMETER OF BRANCH	MATERIAL	FT.
8"	8"	PVC	70
8"	8"	DUCTILE IRON	45
12"	8"	PVC	64

- NOTES:**
- LENGTHS SHOWN ABOVE WERE COMPUTED BASED ON THE FOLLOWING VALUES:
- SAFETY FACTOR = 1.5 TO 1
  - TEST PRESSURE = 200psi.
  - SOIL DESIGNATION = MANUFACTURED SAND
  - DEPTH OF COVER = 3.5 FEET (TYPICAL AND UPPER BEND)
  - DEPTH OF COVER = 5 FEET (LOWER BEND)
  - LENGTH ALONG RUN = 2 FEET

THE LOCATION OF ALL EXISTING UNDERGROUND UTILITIES ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. THE CONTRACTOR WILL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES, STRUCTURES OR FACILITIES. CONTRACTOR SHALL NOTIFY ENGINEER OF ANY DISCREPANCIES 24- HOURS PRIOR TO COMMENCING CONSTRUCTION.




1/24/2023

**UTILITY SITE PLAN  
(2 OF 2)**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS


NO.	REVISION DESCRIPTION	DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS





MATERIALS LIST	METER SIZE	
A. SERVICE CLAMP FOR CONNECTION - REQUIRED ON ALL PLASTIC AND ASBESTOS-CEMENT PIPE AND ALL IRON PIPE 1/2" AND SMALLER.	1-1/2"	2"
B. CORPORATION STOP - SERVICE PIPE OUTLET.	1-1/2"	2"
C. SERVICE PIPE.	1-1/2"	2"
D. COUPLING SERVICE PIPE TO MALE I.P.T. (COMPRESSION FITTING)	1-1/2"	2"
F. TEES, BRASS.	1-1/2"x1-1/2"x1"	2"x2"x1"
G. CLOSE-NIPPLE, BRASS.	1-1/2"	2"
H. ANGLE METER STOP, FEMALE I.P. THREAD INLET & FLANGE OUTLET.	1-1/2"	2"
I. WATER METER LENGTH WITH GASKETS.	13-1/2"	17-3/4"
J. FLANGE, BRASS, FEMALE I.P. THREAD.	1-1/2"	2"
K. NIPPLES, BRASS.	1-1/2" x 8"	2" x 8"
L. CUSTOMER'S CUT OFF VALVE.	1-1/2"	2"
M. NIPPLES, BRASS.	1"x 3"	1" x 3"
N. 90 DEGREE ELBOWS, BRASS.	1"	1"
O. NIPPLES, BRASS.	1" x 3"	1" x 3"
P. CURB STOP, BRASS, FEMALE I.P. THREAD	1"	1"
Q. COUPLINGS, BRASS, SERVICE PIPE TO MALE THREAD.	1"	1"
R. SERVICE PIPE.	1"	1"
S. ROUND OR RECTANGULAR METER BOX - EAST JORDAN IRON WORKS #2 METER BOX, NBU# 89004000003.		
T. LID		
U. CUSTOMER'S CUT-OFF VALVE BOX - MAY BE 1/2" PIECE SDR 26, 8" PVC		
V. METAL PIPE, 4" MINIMUM LENGTH.		



**Engineering Specification**

Job Name: \_\_\_\_\_ Contractor: \_\_\_\_\_  
 Job Location: \_\_\_\_\_ Approval: \_\_\_\_\_  
 Engineer: \_\_\_\_\_ Contractor's P.O. No.: \_\_\_\_\_  
 Approval: \_\_\_\_\_ Representative: \_\_\_\_\_

**Series 009 Reduced Pressure Zone Assemblies**

**Stops: 1/2" - 2"**

Series 009 Reduced Pressure Zone Assemblies are designed to protect potable water supplies in accordance with national plumbing codes and water authority requirements. This series is designed to protect drinking water supplies from dangerous cross-connections in accordance with national plumbing codes and water authority requirements for non-potable service applications such as irrigation, fountains, or industrial processing. The series features two in-line, independent check valves, captured springs and replaceable check seats with an intermediate relief valve. Its compact modular design facilitates easy maintenance and assembly access. Size 1/2" - 1" models have two handles.

**Features**

- Single access cover and modular check construction for ease of maintenance
- Top entry - all internals immediately accessible
- Captured springs for safe maintenance
- Internal relief valve for reduced installation clearances
- Replaceable seats for economical repair
- Bronze body construction for durability 1/2" - 2"
- Ball valve test codes - screwless access 1/2" - 2"
- Large body passages provides low pressure drop
- Compact, space saving design
- No special tools required for servicing

**Specifications**

A Reduced Pressure Zone Assembly shall be installed at each potential health hazard location to prevent backflow due to back-siphonage and/or backpressure. The assembly shall consist of an internal pressure differential relief valve located in a zone between two positive sealing check modules with captured springs and silicone seal discs. Seats and seal discs shall be replaceable in both check modules and the relief valve. There shall be no threads or access in the waterway exposed to the fluids. Service of all internal components shall be through a single access bronze cover secured with stainless steel bolts. The assembly shall also include two resilient seated isolation valves, four resilient seated test cocks and an air gap when fitted. The assembly shall meet the requirements of UL22, ASSE, Std. 1013; AWWA Std. C511-142; CSA B64.4. Seal be a Watts Series 008.

**Now Available WattsBox Insulated Enclosures.**  
For more information, visit our literature ES-361.

**NOTICE**  
The information contained herein is not intended to replace the full product installation and safety information available on the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

**WARNING**  
It is illegal to use this product in any plumbing system providing water for human consumption, such as drinking or dishwashing, in the United States. Before installing standard model product, consult your local water authority, building and plumbing codes.

**DOES NOT INDICATE APPROVAL STATUS. REFER TO PAGE 2 FOR APPROVED SIZES & MODELS.**

**NOTICE**  
Watts product specifications in U.S. customary units and metric are approximate and are provided for reference only. The precise measurement, please contact Watts Technical Service. Watts reserves the right to change or modify product design, construction, specifications, or materials with or without notice and without obligation to make any changes and modifications to already placed products or assemblies.

**WATTS**

**Available Models: 1/2" - 2"**

**Suffix:**  
 QT - quarter turn ball valves  
 S - bronze strainer  
 LF - without shaft valves  
 ADT - above fittings for 360° rotation  
 1/2" - 2" only  
 FC - Internal Polymer Coating  
 SH - stainless steel ball valve handles  
 HC - 2 1/2" in/outlet fire hydrant fitting (2" valve)  
**Profile:**  
 C - clean and check strainer 1/2" - 1" only  
 U - union connections (see ES-U009)

**Pressure / Temperature**  
 Series 009 1/2" - 2" Suitable for supply pressure up to 175psi (12.1 bar). Water temperature: 32°F - 180°F (0°C - 70°C).

**Standards**  
 USC  
 ASSE No. 1013  
 AWWA C511-142  
 CSA B64.4  
 WPMO File No. 1553.  
 \*Does not indicate approval status. See below for approved models.

**Approvals**  
 ASSE, AWWA, CSA, WPMO  
 Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California.  
 UL Classified for 1/2" - 2"  
 (LF models only except 009MLF)

**Dimensions and Weight: 1/2" - 2" 009**

**009 1/2" - 2"**

SIZE	DIMENSIONS (APPROX)						WEIGHT									
	A	B	C	D	E	F	A	B	C	D	E	F				
1/2"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
3/4"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
1"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
1 1/2"	150	275	51	127	39	89	176	38	606	171	306	61	276	70	6	3
2"	145	388	55	140	3	78	276	64	956	241	376	65	3	78	12	5
1 1/2"	175	441	5	192	35	89	256	64	1176	288	476	113	376	88	15	6
1 1/2"	175	454	5	192	35	89	256	64	1176	288	476	114	4	102	16	7
2"	270	543	75	197	4	114	324	81	1356	424	576	151	5	127	26	12

Suffix HC - Fire Hydrant Fittings dimension "A" - 2"

**Dimensions and Weight: 1/2" - 2" 009**

**009 1/2" - 2"**

SIZE	DIMENSIONS (APPROX)						WEIGHT									
	A	B	C	D	E	F	A	B	C	D	E	F				
1/2"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
3/4"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
1"	130	250	46	117	39	86	174	32	516	140	276	60	278	64	5	2
1 1/2"	150	275	51	127	39	89	176	38	606	171	306	61	276	70	6	3
2"	145	388	55	140	3	78	276	64	956	241	376	65	3	78	12	5
1 1/2"	175	441	5	192	35	89	256	64	1176	288	476	113	376	88	15	6
1 1/2"	175	454	5	192	35	89	256	64	1176	288	476	114	4	102	16	7
2"	270	543	75	197	4	114	324	81	1356	424	576	151	5	127	26	12

Suffix HC - Fire Hydrant Fittings dimension "A" - 2"

- UTILITY NOTES:
1. ALL UTILITIES TO BE CONSTRUCTED PRIOR TO THE STREETS.
  2. NO VALVES, HYDRANTS, ETC. SHALL BE CONSTRUCTED WITHIN CURBS, SIDEWALKS OR DRIVEWAYS.

290 S. CASTELL AVE., STE. 100  
 NEW BRAUNFELS, TX 78130  
 TBPE FIRM F-10961  
 TBPLS FIRM 1053600

**HMT**  
 ENGINEERING & SURVEYING

STATE OF TEXAS  
 JOSEPH T. SANDOVAL  
 110257  
 LICENSED PROFESSIONAL ENGINEER

1/24/2023





UTILITY DETAILS (1 OF 2)  
 KEITH WING TWO-STORY OFFICE  
 NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	DATE

DATE: JANUARY 2023  
 DRAWN BY: WRC  
 DESIGNED BY: JTS  
 REVIEWED BY: JTS  
 HMT PROJECT NO.: 429.002

**SHEET**  
**C8.03**






**GENERAL NOTES**

- ALL CONSTRUCTION AND MATERIALS SHALL BE IN STRICT CONFORMANCE WITH APPLICABLE PROVISIONS OF STANDARD SPECIFICATION FOR PUBLIC WORKS CONSTRUCTION.
- MANHOLE RINGS AND COVERS SHALL BE TRANS-TEX A7, OR EQUAL, WHEN WATER TIGHT MANHOLE RINGS AND COVERS ARE SPECIFIED. THEY SHALL BE TRANS-77 IF NBU OR APPROVED EQUAL.
- A MATERIALS FOR SANITARY SEWER PIPE SHALL BE THE SAME FROM MANHOLE TO MANHOLE. CHANGES IN TYPE OF PIPE MAY BE MADE ONLY AT MANHOLES OR SPECIAL STRUCTURES, EXCEPT AS APPROVED BY THE NBU PROJECT ENGINEER.
- MANHOLES AND SPECIAL STRUCTURES SHALL BE USED AS DIRECTED BY THE ENGINEER AND AS SHOWN BY THE NBU PROJECT ENGINEER.
- ALL FORCE MAINS SHALL BE PROVIDED WITH THRUST BLOCKS, WHERE CHANGES IN DIRECTION OCCUR AT TEES, BENDS, CROSSINGS, CHANGES IN SIZE, STOPS (CLOCKING), VALVES AND OR AS SHOWN BELOW OR AS DIRECTED BY THE ENGINEER.
- ALL CONCRETE USED FOR THRUST BLOCKS SHALL HAVE A MINIMUM CONCRETE STRENGTH OF 3000 PSI.
- ALL MANHOLES MUST BE APPROVED BY NBU CONSTRUCTION INSPECTIONS AND STAMPS BEFORE USE.
- SEE DRAWINGS TO THE NEW BRAUNFELS WATER SYSTEMS STANDARD DRAWINGS FOR SANITARY SEWER CONSTRUCTION.

**NOTES:**

- MATERIALS FOR SANITARY SEWER LATERAL SHALL CONFORM TO THE CITY OF NEW BRAUNFELS STANDARD SPECIFICATION FOR PRIVATE SEWER LATERALS. ALL FLEXIBLE PIPE SHALL CONFORM TO A MINIMUM OF ASTM DESIGNATION D-3034 (SOR IS OR BETTER) WITH COMPRESSION JOINT GASKETS OR SHALL BE SOLVENT JOINT.
- IF THE PROPERTY IS IN THE EDWARDS RECHARGE ZONE, TOSQ REQUIRES THAT A REGISTERED PROFESSIONAL ENGINEER, REGISTERED IN SANITARIAN, OR APPROPRIATE CITY INSPECTOR INSPECT AND CERTIFY THE SERVICE LATERAL PRIOR TO COVERING IN ACCORDANCE WITH 16C.0024-4 (B)(9). ALTHOUGH CERTIFICATION MUST BE SENT TO THE TOSQ NEW BRAUNFELS OFFICE.
- IF THE PROPERTY IS IN THE NEW BRAUNFELS CITY LIMITS, A PERMIT IS REQUIRED FROM THE CITY OF NEW BRAUNFELS BUILDING AND ZONING DEPARTMENT (3000 DDD).
- IF THE PROPERTY IS OUTSIDE NEW BRAUNFELS CITY LIMITS AND OVER THE EDWARDS RECHARGE ZONE, A PERMIT IS REQUIRED FROM THE NEW BRAUNFELS WATER SYSTEM (300 009-0415).

290 S. CASTELL AVE., STE. 100  
NEW BRAUNFELS, TX 78130  
TBPE FIRM F-10961  
TBPLS FIRM 1053600



1/24/2023

**UTILITY DETAILS (2 OF 2)**  
KEITH WING TWO-STORY OFFICE  
NEW BRAUNFELS, TEXAS

NO.	REVISION DESCRIPTION	REVISION DATE

DATE: JANUARY 2023  
DRAWN BY: WRC  
DESIGNED BY: JTS  
REVIEWED BY: JTS  
HMT PROJECT NO.: 429.002

**SHEET**  
**C8.04**



Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

2/14/2023



HMT  
Engineering  
and Surveying  
F-10961

Joseph Sandoval, P.E.

Additional information is provided for cells with a red triangle in the upper right corn  
Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG.  
Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will r

1. The Required Load Reduction for the total project:

Calculations from RG-348

Page 3-29 Equation 3.3:  $L_M = 27.2(A_N \times P)$

where:

$L_{M \text{ TOTAL PROJECT}}$  = Required TSS removal result  
 $A_N$  = Net increase in impervious area  
 $P$  = Average annual precipitation

Site Data: Determine Required Load Removal Based on the Entire Project

County =	Comal	
Total project area included in plan * =	2.54	acres
Predevelopment impervious area within the limits of the plan * =	0.05	acres
Total post-development impervious area within the limits of the plan* =	1.16	acres
Total post-development impervious cover fraction * =	0.46	
P =	33	inches

$L_{M \text{ TOTAL PROJECT}}$  = 996 lbs.

\* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = 1

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. =	1	
Total drainage basin/outfall area =	2.54	acres
Predevelopment impervious area within drainage basin/outfall area =	0.05	acres
Post-development impervious area within drainage basin/outfall area =	1.16	acres
Post-development impervious fraction within drainage basin/outfall area =	0.46	
$L_{M \text{ THIS BASIN}}$ =	996	lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Batch Detention Basin  
Removal efficiency = 91 percent

**4. Calculate Maximum TSS Load Removed (L<sub>R</sub>) for this Drainage Basin by the selected BMP Type.**

RG-348 Page 3-33 Equation 3.7:  $L_R = (\text{BMP efficiency}) \times P \times (A_I \times C)$

where:

A<sub>C</sub> = Total On-Site drainage area  
A<sub>I</sub> = Impervious area proposed in  
A<sub>P</sub> = Pervious area remaining in th  
L<sub>R</sub> = TSS Load removed from this

A<sub>C</sub> = **2.54** acres  
A<sub>I</sub> = **1.16** acres  
A<sub>P</sub> = **1.38** acres  
L<sub>R</sub> = **1228** lbs

**5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area**

Desired L<sub>M THIS BASIN</sub> = **996** lbs.

F = **0.81**

**6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.**

Rainfall Depth = **1.12** inches  
Post Development Runoff Coefficient = **0.33**  
On-site Water Quality Volume = **3456** cubic feet

Calculations from RG-348

Off-site area draining to BMP = **0.00** acres  
Off-site Impervious cover draining to BMP = **0.00** acres  
Impervious fraction of off-site area = **0**  
Off-site Runoff Coefficient = **0.00**  
Off-site Water Quality Volume = **0** cubic feet



Storage for Sediment = **691**  
Total Capture Volume (required water quality volume(s) x 1.20) = **4147** cubic feet

The following sections are used to calculate the required water quality volume(s) for the selected BMP  
The values for BMP Types not selected in cell C45 will show NA.

**7. Retention/Irrigation System** Designed as Required in RG

Required Water Quality Volume for retention basin = **NA** cubic feet

Irrigation Area Calculations:

Soil infiltration/permeability rate = **0.1** in/hr  
Irrigation area = **NA** square feet  
**NA** acres

**8. Extended Detention Basin System** Designed as Required in RG

Required Water Quality Volume for extended detention basin = **NA** cubic feet

**9. Filter area for Sand Filters** Designed as Required in RG

**9A. Full Sedimentation and Filtration System**

Water Quality Volume for sedimentation basin = **NA** cubic feet

Minimum filter basin area = **NA** square feet

Maximum sedimentation basin area = **NA** square feet

Minimum sedimentation basin area = **NA** square feet

**9B. Partial Sedimentation and Filtration System**

Water Quality Volume for combined basins = **NA** cubic feet

Minimum filter basin area = **NA** square feet

Maximum sedimentation basin area = **NA** square feet

Minimum sedimentation basin area = **NA** square feet

**10. Bioretention System** Designed as Required in RG

Required Water Quality Volume for Bioretention Basin = **NA** cubic feet

**11. Wet Basins** Designed as Required in RG

Required capacity of Permanent Pool = **NA** cubic feet

Required capacity at WQV Elevation = **NA** cubic feet

PERMANENT STORMWATER SECTION  
ATTACHMENT G  
Inspection, Maintenance, Repair and Retrofit Plan

The contractor will be directed to inspect and maintain all permanent BMPs during construction. One year after construction is complete the permanent BMPs will be turned over to the Keith Wing Custom Builders. Any deficiency noted must be corrected immediately by the Keith Wing Custom Builders. The maintenance guidelines were pulled from the TCEQ Document “Complying with the Edwards Aquifer Rules Technical Guidance on Best Management Practices” and its addendum sheet, the documents can be referenced for a more in-depth explanation of maintenance guidelines.

Maintenance and Inspection:

- (1) Specification of routine and non-routine maintenance activities to be performed;
  - a. Batch Detention Basins
    - i. Inspection- Inspect basin at least twice a year, once during wet weather to evaluate detention and drawdown time. The remaining inspections should occur between storms when the valve and controller can be verified. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. The outlet structure and the trash screen should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet(s) as described in previous sections. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately.
    - ii. Mowing- Grass areas in and around basins must be mowed at least twice annually to limit vegetation height to 18 inches. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and removed. Vegetation on the pond embankments should be mowed as appropriate to prevent the establishment of woody vegetation.
    - iii. Debris and Litter Removal- Debris and litter should be removed during regular mowing operations and inspections. Attention should be paid to floating debris that can eventually clog the control device or riser. The outlet should be checked for possible clogging or obstruction and debris removed.
    - iv. Erosion- During each inspection, erosion areas on basin side-slopes and embankments must be identified and repaired, regraded or revegetated immediately.
    - v. Nuisance Control- Standing water or soggy conditions may occur in the basin. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weed, odors, algae, etc.).
    - vi. Structural Repairs Replacement- With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, retaining walls, etc.) should be identified and repaired immediately. The



various inlet/outlet structures in a basin will eventually deteriorate and must be replaced.

- vii. Sediment Removal- Remove sediment when the depth reaches 6 inches or when the proper functioning of inlet and outlet structures is impaired. Sediment should be cleared from the inlet structure at least every year and from the basin at least every 5 years.
- viii. Logic Controller- The Logic Controller should be inspected as part of the twice-yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris. The solar panel should be inspected and any dust or debris on the panel should be carefully removed. The controller and all other circuitry and wiring should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. inspection.

(2) A schedule for maintenance activities;

- a. Inspection and maintenance will be held quarterly and after rainfall events of more than one inch

(3) The batch detention basin can be accessed by vehicle as they are directly adjacent to a paved roadway.

(4) Check Depth of Vegetation

- a. Grassy areas in and around the basin must be mowed at least twice annually. Vegetation in the basin shall not exceed 18-inches in depth. When vegetation needs to be cut, it shall be cut to an approximately 4-inch height. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and then removed. A written record will be kept of inspection results and maintenance performed.

(5) Removal of Debris and Trash

- a. Debris and litter will accumulate near the basin sump and should be removed during regular mowing operations and inspections. Particular attention should be paid to floating debris that can eventually clog the irrigation system. The basin and inlet structure shall be checked for the accumulation of debris and trash such as brush, limbs, leaves, paper cups, aluminum cans, plastic bottles etc. Accumulated trash and debris shall be raked or collected from the basin and inlet structure and disposed of properly. Written record will be kept of inspection results and maintenance performed.

(6) Cut-off Valve

- a. The cut-off valve shall be turned to confirm full opening and full closure. Prior to operating the valve, the valve setting shall be checked to determine the position to which the valve is to be returned (which should limit drawdown time of the basin between 24- hours and 72-hours). Count should be kept of number of turns to open and close the valve so that the valve can be reset to the starting position. Defects in the operation of the cut-off valve shall be corrected within 7 working days. A written record will be kept of inspection results and maintenance performed.

(7) Inlet Splash Pad

- a. The filter area around the inlet splash pad shall be checked for erosion and for the condition of the rock rubble. Erosion or disturbance of the rock rubble should be corrected by removal and/or replacement of the rock rubble. If the condition persists in subsequent inspections, the size of the rock rubble should be increased. Rubble should be placed to a density that minimizes the amount of exposed soil between the rock rubble. Deficiencies should be corrected within seven working days. A written record will be kept of inspection results and maintenance performed.

(8) Structural Integrity

- a. Observe the height of the confining berm for visible signs of erosion or potential breach. Signs of erosion and/or slumping of basin walls should be corrected within 2 weeks or immediately in case of emergency conditions. Regrading and vegetation may be required to correct the problems. Corrective measures include but are not limited to addition of topsoil or appropriate soil material so as to restore the original berm height of the basin. Restored areas shall be protected through placement of solid block sod. Written record will be kept of inspection results and maintenance performed.

(9) Discharge Pipe

- a. The basin discharge pipe shall be checked for accumulation of silt, debris or other obstructions, which could block flow. Soil accumulations, vegetative overgrowth and other blockages should be cleared from the pipe discharge point. Erosion at the point of discharge shall be monitored. If erosion occurs, the addition of rock rubble to disperse the flow should be accomplished. A written record will be kept of inspection results and corrective measures taken

(10) Detention Time

- a. The irrigation schedule should allow for complete drawdown of the water quality volume within 72 hours. Irrigation should not begin within 12 hours of the end of rainfall. If detention time exceeds 72 hours or begins prior to 12 hours after end of rainfall, check wet well and irrigation system. A written record of the inspection findings and corrective actions performed will be made.

(11) Irrigation Areas

- a. Vegetation must be maintained in the irrigation area such that it does not impede the spray of water from the irrigation heads. Tree and shrub trimmings and other large debris should be removed from the irrigation area. Written record will be kept of inspection results and maintenance performed.

(12) For Pump Stations

- a. Check wet well discharge pipe to confirm flow through the pump system. If flow is not present, allow sufficient time for pump to cycle on and off. If flow does not occur, the wet well should be checked for the level of water. The wet well should be opened and the on/off float switches should be moved up and down to activate the pump. If the pump does not start, a repair technician shall be called in to repair the malfunction within 5 working days.

Check the wet well for accumulation for trash, debris and silt. Trash and debris shall be removed and disposed of properly. Silt depth can be checked by probing the bottom of the wet well with a stick or PVC pipe. Silt accumulations should be



bottom. Silt can be removed by vacuum pump or other methods.

Visually check aboveground pump wiring and connections for damage. Damaged or loose connections should be repaired within 5 working days. Written record will be kept of inspection results and maintenance performed.

(13) Irrigation System

a. The irrigation system, including pumps, should be inspected and tested (or observed while in operation) to assure proper operation at least 6 times annually. Two of these inspections should occur during or immediately following wet weather. Any leaks, broken spray heads, or other malfunctions with the irrigation system should be repaired immediately. In particular, sprinkler heads must be checked to determine if they are broken, clogged, or not spraying properly. A written record will be kept of inspection results and the maintenance performed. All inspection and testing reports will be kept on site and accessible to inspectors.

(14) Visually Inspect Security Fencing for Damage or Breach

a. Check the basin maintenance access gates for proper operation. Damage to fencing or gates shall be repaired within 5 working days. A written record will be kept of inspection results and maintenance performed.

(15) Recordkeeping Procedures for Inspections, Maintenance, Repairs, and Retrofits

a. Written records shall be kept by the party responsible for maintenance or a designated representative.

b. Written records shall be retained for a minimum of five years.

(16) 4 Wing Holding, LLC will be in charge of the oversight and scheduling of inspections and maintenance. As long as 4 Wing Holding, LLC maintains ownership of the subject property, 4 Wing Holding will establish the inspection and maintenance plans for the Organization; and

(17) Inspection records will be maintained at the 4 Wing Holding, LLC offices.

*Joseph Sandone, P.E.*

Party Responsible for Maintenance

*Authorized Agent*

*Feb. 10, 2023*

Date

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I \_\_\_\_\_  
Keith Wing  
Print Name

\_\_\_\_\_ Member & Registered Agent  
Title - Owner/President/Other

of \_\_\_\_\_  
4 Wing Holding, LLC  
Corporation/Partnership/Entity Name

have authorized \_\_\_\_\_  
Joseph T. Sandoval, P.E.  
Print Name of Agent/Engineer

of \_\_\_\_\_  
HMT Engineering & Surveying, Inc.  
Print Name of Firm

to represent and act on the behalf of the above-named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.



SIGNATURE PAGE:

Keith Wing  
Applicant's Signature


1-16-23  
Date

THE STATE OF Texas §

County of Comal §

BEFORE ME, the undersigned authority, on this day personally appeared Keith Wing known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 16 day of January 2023



Jessica Kilgore  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: November 10, 2025

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Keith Wing Two-Story Office

Regulated Entity Location: 671 Ridge Hill Dr., New Braunfels, TX

Name of Customer: 4 Wing Holding LLC

Contact Person: Keith Wing

Phone: (830) 266-9464

Customer Reference Number (if issued):CN \_\_\_\_\_

Regulated Entity Reference Number (if issued):RN \_\_\_\_\_

### Austin Regional Office (3373)

Hays

Travis

Williamson

### San Antonio Regional Office (3362)

Bexar

Medina

Uvalde

Comal

Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

Austin Regional Office

San Antonio Regional Office

Mailed to: TCEQ - Cashier

Overnight Delivery to: TCEQ - Cashier

Revenues Section

12100 Park 35 Circle

Mail Code 214

Building A, 3rd Floor

P.O. Box 13088

Austin, TX 78753

Austin, TX 78711-3088

(512)239-0357

### Site Location (Check All That Apply):

Recharge Zone

Contributing Zone

Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	2.54 Acres	\$ 4,000
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Joseph Sandoval, P.E. Date: Feb. 10, 2023



# Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

## ***Water Pollution Abatement Plans and Modifications***

### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

### ***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150



TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
<b>2. Customer Reference Number (if issued)</b>	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a>	<b>3. Regulated Entity Reference Number (if issued)</b>
CN		RN

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)	
<input checked="" type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)		<input type="checkbox"/> Change in Regulated Entity Ownership	
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>			
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)		If new Customer, enter previous Customer below:	
4 Wing Holding, LLC			
<b>7. TX SOS/CPA Filing Number</b>	<b>8. TX State Tax ID</b> (11 digits)	<b>9. Federal Tax ID</b> (9 digits)	<b>10. DUNS Number</b> (if applicable)
0804701444	32086014704		
<b>11. Type of Customer:</b>	<input type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other	<input type="checkbox"/> Sole Proprietorship	<input checked="" type="checkbox"/> Other: LLC	
<b>12. Number of Employees</b>		<b>13. Independently Owned and Operated?</b>	
<input checked="" type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following			
<input type="checkbox"/> Owner		<input type="checkbox"/> Operator	
<input type="checkbox"/> Occupational Licensee		<input checked="" type="checkbox"/> Owner & Operator	
<input type="checkbox"/> Responsible Party		<input type="checkbox"/> Voluntary Cleanup Applicant	
<input type="checkbox"/> Other:			
<b>15. Mailing Address:</b>	2027 State Hwy 46 West		
	City	New Braunfels	State TX ZIP 78132 ZIP + 4
<b>16. Country Mailing Information</b> (if outside USA)		<b>17. E-Mail Address</b> (if applicable)	
		keith@keithwing.com	
<b>18. Telephone Number</b>	<b>19. Extension or Code</b>	<b>20. Fax Number</b> (if applicable)	
( 830 ) 226-9464	0	( N/A ) -	

## SECTION III: Regulated Entity Information

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)	
<input checked="" type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information	
<b>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</b>	
<b>22. Regulated Entity Name</b> (Enter name of the site where the regulated action is taking place.)	
Keith Wing Two-Story Office	



23. Street Address of the Regulated Entity: <i>(No PO Boxes)</i>	671 Ridge Hill Drive						
	City	New Braunfels	State	TX	ZIP	78130	ZIP + 4
24. County	Comal						

**Enter Physical Location Description if no street address is provided.**

25. Description to Physical Location:	Southeast corner of Loop 377 and Ridge Hill Drive.							
26. Nearest City	New Braunfels				State	TX	Nearest ZIP Code	78130
27. Latitude (N) In Decimal:	29.705569			28. Longitude (W) In Decimal:	-98.161918			
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds			
29	42	20.05	-98	9	42.90			
29. Primary SIC Code (4 digits)	30. Secondary SIC Code (4 digits)		31. Primary NAICS Code (5 or 6 digits)		32. Secondary NAICS Code (5 or 6 digits)			
1542			236220					
33. What is the Primary Business of this entity? <i>(Do not repeat the SIC or NAICS description.)</i>								
34. Mailing Address:								
	City		State		ZIP		ZIP + 4	
35. E-Mail Address:								
36. Telephone Number			37. Extension or Code		38. Fax Number <i>(if applicable)</i>			
( ) -					( ) -			

**39. TCEQ Programs and ID Numbers** Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

**SECTION IV: Preparer Information**

40. Name:	Joseph T. Sandoval, P.E.		41. Title:	Project Manager	
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address		
( 830 ) 625-8555	N/A	( N/A ) -	Josephs@hmtnb.com		

**SECTION V: Authorized Signature**

**46.** By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	HMT Enigneering & Surveying	Job Title:	Project Manager		
Name <i>(In Print)</i> :	Joseph T. Sandoval, P.E.			Phone:	( 830 ) 625- 8555

Signature:	Joseph Sandone, P.E.	Date:	2/3/2023
------------	----------------------	-------	----------