JOHNSON RANCH NORTH UNIT 9 REPLAT

Contributing Zone Plan Exception Request

March 2023





March 15, 2023

Ms. Lillian Butler Texas Commission on Environmental Quality (TCEQ) Region 13 14250 Judson Road San Antonio, Texas 78233-4480

Re:

Johnson Ranch North Unit 9 Replat Contributing Zone Exception Application

Dear Ms. Butler:

Please find included herein the Johnson Ranch North Unit 9 Replat Contributing Zone Exception Application. This Contributing Zone Exception Application has been prepared in accordance with the Texas Administrative Code (30 TAC 213) and current policies for development over the Edwards Aquifer Contributing Zone.

This Contributing Zone Exception Application applies to an approximate 1.76-acre site as identified by the project limits. Please review the plan information for the items it is intended to address. If acceptable, please provide a written approval of the plan in order that construction may begin at the earliest opportunity.

Appropriate review fees (\$500) and fee application are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,

Pape-Dawson Engineers, Inc.

Trey Dawson, P.E.

Executive Vice President

Attachments

P:\85\47\95\Word\Report\Exception\230309a1.docx

JOHNSON RANCH NORTH UNIT 9 REPLAT

Contributing Zone Plan Exception Request



March 2023



EDWARDS AQUIFER APPLICATION COVER PAGE (TCEQ-20705)

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- When an application is deemed administratively complete, the technical review period begins. The regional
 office will distribute copies of the application to the identified affected city, county, and groundwater
 conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
 to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name:				2. Regulated Entity No.:					
3. Customer Name:				4. Customer No.:					
5. Project Type: (Please circle/check one)	New		Modification		Extension		Exception		
6. Plan Type: (Please circle/check one)	WPAP	(CZP)	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Resider	ntial	Non-residential			8. Sit	e (acres):		
9. Application Fee:			10. P	ermai	nent l	BMP(s):		
11. SCS (Linear Ft.):			12. AST/UST (No			o. Tar	ıks):		
13. County:			14. Watershed:						

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region					
County:	Hays	Travis	Williamson		
Original (1 req.)		_			
Region (1 req.)		_	_		
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA		
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrellLeanderLiberty HillPflugervilleRound Rock		

	Sa	an Antonio Region			
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)					
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.
Trey Dawson, P.E.
Print Name of Customer/Authorized Agent
3/20/23
Signature of Customer/Authorized Agent Date

FOR TCEQ INTERNAL USE ONLY				
Date(s)Reviewed:	Da	Date Administratively Complete:		
Received From:	Co	Correct Number of Copies:		•
Received By:	Di	istributi	ion Date:	
EAPP File Number:	Co	omplex:		
Admin. Review(s) (No.):	No	o. AR Rounds:		
Delinquent Fees (Y/N):	Re	Review Time Spent:		
Lat./Long. Verified:	SC	OS Cust	omer Verification:	
Agent Authorization Complete/Notarized (Y/N):	Fe	ee	Payable to TCEQ (Y	(/N):
Core Data Form Complete (Y/N):	1	Check: Signed (Y/N):		
Core Data Form Incomplete Nos.:		-	Less than 90 days o	ld (Y/N):

CONTRIBUTING ZONE PLAN EXCEPTION REQUEST FORM (TCEQ10262)

Contributing Zone Exception Request Form

Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Exception Request Form** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Trey Dawson, P.E.

Date: ____ 3 10 13

Signature of Customer/Agent:

Regulated Entity Name: Johnson Ranch North Unit 9 Replat

Project Information

1. County: Comal

2. Stream Basin: Cibolo Creek

3. Groundwater Conservation District (if applicable): Edwards Aquifer Authority

4. Customer (Applicant):

Contact Person: Richard Mott

Entity: Lennar Homes of Texas land and Construction, LTD

Mailing Address: 100 NE Loop 410, Ste 1155

 City, State: San Antonio, TX
 Zip: 78216

 Telephone: (210) 403-2600
 Fax: ______

Email Address: richard.mott@lennar.com


5.	Agent/Representative (If any):
	Contact Person: Trey Dawson, P.E. Entity: Pape-Dawson Engineers, Inc. Mailing Address: 2000 NW Loop 410 City, State: San Antonio, TX Telephone: (210) 375-9000 Email Address: treydawson@pape-dawson.com
6.	Project Location
	 ☐ This project is inside the city limits of ☐ This project is outside the city limits but inside the ETJ (extra-territorial jurisdiction) of Bulverde. ☐ This project is not located within any city limits or ETJ.
7.	The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.
	From TCEQ's regional office, proceed right toward Judson Rd and travel approximately 2.6 miles to N Loop 1604 E. Travel east approximately 1.8 miles on Loop 1604 before taking the exit toward Bulverde Rd. Travel north on Bulverde road for approximately 7.3 miles before merging onto US-281 N. Travel north on US-281 N for 2.9 miles before turning right on Mustang Vista. In approximately 1 mile, turn left onto Stahl Lane. The project site is located 1,300 LF north of the Mustang Vista and Stahl Lane intersection.
8.	Attachment A - Road Map. A road map showing directions to and location of the project site is attached. The map clearly shows the boundary of the project site.
9.	Attachment B - USGS Quadrangle Map. A copy of the USGS Quadrangle Map (Scale: 1" = 2000') is attached. The map(s) should clearly show:
	☑ Project site boundaries.☑ USGS Quadrangle Name(s).
10.	Attachment C - Project Narrative. A detailed narrative description of the proposed project is provided at the end of this form. The project description is consistent throughout the application and contains, at a minimum, the following details:
	 Area of the site ○ Offsite areas ○ Impervious cover ○ Permanent BMP(s) ○ Proposed site use ○ Site history ○ Previous development ○ Area(s) to be demolished

11. Existing project site conditions are noted below:

	Existing commercial site
	Existing industrial site
\boxtimes	Existing residential site
\boxtimes	Existing paved and/or unpaved roads
\boxtimes	Undeveloped (Cleared)
	Undeveloped (Undisturbed/Not cleared) Other:
12.	Attachment D - Nature Of Exception. A narrative description of the nature of each exception requested is attached. All provisions of 30 TAC §213 Subchapter B for which an exception is being requested have been identified in the description.
13.	Attachment E - Equivalent Water Quality Protection . Documentation demonstrating equivalent water quality protection for surface streams which enter the Edwards Aquifer is attached.
Adm	ninistrative Information
14.	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
15.	The applicant understands that prior approval under this section must be obtained from the executive director for the exception to be authorized.

ATTACHMENT A






Pape-Dawson Engineers, Inc.

Date: Mar 09, 2023, 11:40am User ID: mgregory
File: P: \85\47\95\Design\ENV\RM 854795.dwg

ATTACHMENT A Road Map

ATTACHMENT B





ATTACHMENT C

Attachment C - Project Description

The Johnson Ranch North Unit 9 Replat was originally included in the Johnson Ranch Water Pollution Abatement Plan (WPAP) (ID No. 13-07082901), which was approved on October 24, 2004, as a residential development within a 751.3-acre project area, including single family homes, roadways, and an exemption from permanent BMPs. A subsequent WPAP Modification (ID No. 13-12082002) was approved on October 10, 2012, for an increase in the number of lots and an exemption from permanent BMPs. The Johnson Ranch North Contributing Zone Plan (CZP) (ID No. 13-13032701) was approved on July 1, 2013, which provided a new legal boundary that separated the regulated activities on the Contributing Zone from those proposed on the Recharge Zone. This new CZP was approved for a single-family development on 262.24 acres, and it included homes, driveways, sidewalks, a wastewater lift station and water intake facility, improvements to US Highway 281, associated streets and utilities, and an exemption from permanent BMPs. A CZP Modification (ID No. 13000453) was approved on October 26, 2017 for a change to the lot layouts, increase in units, and an increase in impervious cover, totaling 48.57 acres of impervious cover within the 262.24 acre site. This CZP Modification also approved an exemption for permanent BMPs due to having less than 20% impervious cover. A Request for an Exception to the requirements of a Contributing Zone Plan was approved on July 9, 2019 (ID No. 13000925), which approved additional road widening and sidewalk construction for an overall impervious cover of 49.58 acres, or 18.91% of the 262.24-acre site, which still complies with the 20% exemption.

This Johnson Ranch North Unit 9 Replat is being submitted for the relocation of two (2) previously approved home lots to construct a detention basin for better stormwater management on 1.76 acres within the previously approved project limits. Proposed regulated activities include clearing, grading, and excavation for the construction of the detention basin associated with the previously approved single-family residential development. No additional impervious cover is proposed, and therefore the total impervious cover for the previously approved 262.24-acre project limits remains at 49.58 acres (18.91%). Due to an overall impervious cover percentage below 20%, no Permanent Best Management Practices (BMPs) are required.

Please refer to the included exhibits for details of the proposed construction and relationship to the overall project.



ATTACHMENT D

Attachment D - Nature of Exception

The Johnson Ranch North Unit 9 Replat was originally included in the Johnson Ranch Water Pollution Abatement Plan (WPAP) (ID No. 13-07082901), which was approved on October 24, 2004, as a residential development within a 751.3-acre project area, including single family homes, roadways, and an exemption from permanent BMPs. A subsequent WPAP Modification (ID No. 13-12082002) was approved on October 10, 2012, for an increase in the number of lots and an exemption from permanent BMPs. The Johnson Ranch North Contributing Zone Plan (CZP) (ID No. 13-13032701) was approved on July 1, 2013, which provided a new legal boundary that separated the regulated activities on the Contributing Zone from those proposed on the Recharge Zone. This new CZP was approved for a single-family development on 262.24 acres, and it included homes, driveways, sidewalks, a wastewater lift station and water intake facility, improvements to US Highway 281, associated streets and utilities, and an exemption from permanent BMPs. A CZP Modification (ID No. 13000453) was approved on October 26, 2017 for a change to the lot layouts, increase in units, and an increase in impervious cover, totaling 48.57 acres of impervious cover within the 262.24 acre site. This CZP Modification also approved an exemption for permanent BMPs due to having less than 20% impervious cover. A Request for an Exception to the requirements of a Contributing Zone Plan was approved on July 9, 2019 (ID No. 13000925), which approved additional road widening and sidewalk construction for an overall impervious cover of 49.58 acres, or 18.91% of the 262.24-acre site, which still complies with the 20% exemption.

This Contributing Zone Exception Request is submitted as an exception from the Contributing Zone Plan Application. No additional impervious cover is proposed for the construction of the detention basin or lot layout change, which will maintain the compliance of the 20% impervious cover waiver.

ATTACHMENT E

Attachment E - Equivalent Water Quality Protection

The Johnson Ranch North Unit 9 Replat was originally included in the Johnson Ranch Water Pollution Abatement Plan (WPAP) (ID No. 13-07082901), which was approved on October 24, 2004, as a residential development within a 751.3-acre project area, including single family homes, roadways, and an exemption from permanent BMPs. A subsequent WPAP Modification (ID No. 13-12082002) was approved on October 10, 2012, for an increase in the number of lots and an exemption from permanent BMPs. The Johnson Ranch North Contributing Zone Plan (CZP) (ID No. 13-13032701) was approved on July 1, 2013, which provided a new legal boundary that separated the regulated activities on the Contributing Zone from those proposed on the Recharge Zone. This new CZP was approved for a single-family development on 262.24 acres, and it included homes, driveways, sidewalks, a wastewater lift station and water intake facility, improvements to US Highway 281, associated streets and utilities, and an exemption from permanent BMPs. A CZP Modification (ID No. 13000453) was approved on October 26, 2017 for a change to the lot layouts, increase in units, and an increase in impervious cover, totaling 48.57 acres of impervious cover within the 262.24 acre site. This CZP Modification also approved an exemption for permanent BMPs due to having less than 20% impervious cover. A Request for an Exception to the requirements of a Contributing Zone Plan was approved on July 9, 2019 (ID No. 13000925), which approved additional road widening and sidewalk construction for an overall impervious cover of 49.58 acres, or 18.91% of the 262.24-acre site, which still complies with the 20% exemption.

Proposed regulated activities include clearing, grading, and excavation for the construction of a detention basin associated with the previously approved single-family residential development. No additional impervious cover is proposed, which maintains compliance with the 20% impervious cover waiver. Equivalent water quality protection is accounted with the compliance of the 20% impervious cover exemption.

Due to the nature of the proposed construction, this exception request is proposed. Please refer to the included exhibits for additional details.



TEMPORARY STORMWATER SECTION (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Date: 3 20 23
Signature of Customer/Agent:
Regulated Entity Name: Johnson Ranch North Unit 9 Replat

Print Name of Customer/Agent: Trey Dawson, P.E.

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1.	Fuels for construction equipment and hazardous substances which will be used du	ıring
	construction:	V

The following fuels and/or hazardous substances will be stored on the site:	<u>construction</u>
staging area	

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less the	an 250
gallons will be stored on the site for less than one (1) year.	

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan
	application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
	Fuels and hazardous substances will not be stored on the site.
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.
S	equence of Construction
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6.	Name the receiving water(s) at or near the site which will be disturbed or which will

Temporary Best Management Practices (TBMPs)

receive discharges from disturbed areas of the project: Upper Cibolo Creek

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
	A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
	There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map . A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area
	disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. 🗌	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
	N/A
12. 🔀	Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. 🔀	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. 🔀	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. 🗌	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. 🔀	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
Soil	Stabilization Practices
mulchi	les: establishment of temporary vegetation, establishment of permanent vegetation, ng, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.
 Administrative Information
 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

proposed to protect the aquifer from any adverse impacts.

appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods

ATTACHMENT A

<u>Attachment A – Spill Response Actions</u>

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. https://www.tceq.texas.gov/response/spills/spill_rq.html
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.



- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction
 personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at
 the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.



ATTACHMENT B

Attachment B - Potential Sources of Contamination

Other potential sources of contamination during construction include:

Potential Source Preventative Measure

- Asphalt products used on this project.
- After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain.
- Potential Source •
- Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping.

Preventative Measure

- Vehicle maintenance when possible will be performed within the construction staging area.
- Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.
- Potential Source •
- Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.

Preventative Measure

- Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.
- Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.
- Hazardous materials and wastes shall be stored in covered containers and protected from vandalism.
- A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.
- Potential Source •
- Miscellaneous trash and litter from construction workers and material wrappings.

Preventive Measure

- Trash containers will be placed throughout the site to encourage proper trash disposal.
- Potential Source Preventive Measure
- Construction debris.
 - Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.



Potential Source • Preventative Measure

Spills/Overflow of waste from portable toilets

- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.



ATTACHMENT C

<u>Attachment C – Sequence of Major Activities</u>

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include installation of TBMPs, clearing and grubbing of vegetation where applicable. This will disturb approximately 1.76 acres. The second is construction that will include single-family residential homes, a detention basin, landscaping and site cleanup. This will disturb approximately 1.76 acres.



ATTACHMENT D

Attachment D – Temporary Best Management Practices and Measures

A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

Upgradient water will cross the site from undeveloped property adjacent to the site. All TBMPs are adequate for the drainage areas they serve.

b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

As this site is entirely over the Edwards Aquifer Contributing Zone, a Geologic Assessment was not conducted and is not required; therefore, no sensitive features were identified. There are no surface streams on or immediately adjacent to the site.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.



d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

Since the project is located entirely over the Edwards Contributing Zone, a Geologic Assessment was not conducted and is not required by 30 TAC 213 regulations. Therefore, no naturally-occurring sensitive features are known the exist on the site. 30 TAC 213(f)(2) only applies to projects over the Edwards Recharge Zone.



ATTACHMENT F

<u>Attachment F – Structural Practices</u>

The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 1 and illustrated in Exhibit 2.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 1, and illustrated on Exhibit 2.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

• Installation of concrete truck washout pit(s), as required and located on Exhibit 1 and illustrated on Exhibit 2.



ATTACHMENT G

Attachment G - Drainage Area Map

No more than ten (10) acres will be disturbed. All TBMPs utilized are adequate for the drainage areas served.



ATTACHMENT I

INSPECTIONS

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.

Pollution	.⊑ 。	Corrective Action Required					
Prevention	ted	Daniel de la companya	Data				
Measure	nspected Compliance	Description	Date Completed				
	Ë Ö	(use additional sheet if necessary)	Completed				
Best Management Practices							
Natural vegetation buffer strips							
Temporary vegetation							
Permanent vegetation							
Sediment control basin							
Silt fences							
Rock berms							
Gravel filter bags							
Drain inlet protection							
Other structural controls							
Vehicle exits (off-site tracking)							
Material storage areas (leakage)							
Equipment areas (leaks, spills)							
Concrete washout pit (leaks, failure)							
General site cleanliness							
Trash receptacles							
Evidence of Erosion							
Site preparation							
Roadway or parking lot construction							
Utility construction							
Drainage construction							
Building construction							
Major Observations							
Sediment discharges from site							
BMPs requiring maintenance							
BMPs requiring modification							
Additional BMPs required							
"I certify under penalty of law that this document and a system designed to assure that qualified personnel prop or persons who manage the system, or those persons dir	all attach erly gath ectly resp e. I am	ments were prepared under my direction or supervision in er and evaluate the information submitted. Based on my inconsible for gathering the information, the information submit aware there are significant penalties for submitting false info	uiry of the person itted is, to the best				
are possibility of the und imprisonment for knowing viol							
"I further certify I am an authorized signatory in accorda	nce with	the provisions of 30 TAC §305.128."					
Inspector's Name	nspector	's Signature Date					

PROJECT MILESTONE DATES

Date when major site grading activities begin: **Construction Activity** Date Installation of BMPs Dates when construction activities temporarily or permanently cease on all or a portion of the project: **Construction Activity** <u>Date</u> Dates when stabilization measures are initiated: **Stabilization Activity** Date

Removal of BMPs

ATTACHMENT J

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.

AGENT AUTHORIZATION FORM (TCEQ-0599)

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

l	Richard Mott	
	Print Name	
	VP of Land Development	
	Title - Owner/President/Other	
of	Lennar Homes of Texas Land and Construction, LTD	
	Corporation/Partnership/Entity Name	
have authorized	Pape-Dawson Engineers, Inc.	
_	Print Name of Agent/Engineer	
of	Pape-Dawson Engineers, Inc.	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SI	G١	IA	TL	JR	Ε	P	A	G	E	•
----	----	----	----	----	---	---	---	---	---	---

Richard Molt
Applicant Signature

3/14/2023 | 11:16 AM PDT Date

THE STATE OF TEXAS

§

County of Bexar

S

This instrument was acknowledged before me by means of an interactive two-way audio and video communication. The undersigned authority, <u>Richard Mott</u>, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed the same for the purposes and considerations therein expressed and in the capacity therein stated.

GIVEN under my hand and seal of office on this

on this ____ day of

MEGHAN JANE GRACE
Notary Public, State of Texas
Comm. Expires 01-07-2025
Notary ID 12081891

NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: __

APPLICATION FEE FORM (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality Name of Proposed Regulated Entity: Johnson Ranch North Unit 9 Replat Regulated Entity Location: 1,300 ft N of Mustang Vista and Stahl Lane intersection, Bulverde, TX Name of Customer: Lennar Homes of Texas Land and Construction, LTD Phone: (210) 403-2600 Contact Person: Richard Mott Customer Reference Number (if issued):CN 602412207 Regulated Entity Reference Number (if issued):RN 105332522 **Austin Regional Office (3373)** Williamson Travis Hays San Antonio Regional Office (3362) Uvalde Medina Bexar Kinney Comal 🔀 Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: San Antonio Regional Office **Austin Regional Office** Overnight Delivery to: TCEQ - Cashier Mailed to: TCEQ - Cashier 12100 Park 35 Circle **Revenues Section** Building A, 3rd Floor Mail Code 214 Austin, TX 78753 P.O. Box 13088 (512)239-0357 Austin, TX 78711-3088 Site Location (Check All That Apply): **Transition Zone** Contributing Zone Recharge Zone

Type of Plan	Size	Fee Due
Water Pollution Abatement Plan, Contributing Zone		
Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		<u>N</u>
Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone		
Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	1 Each	\$ 500
Extension of Time	Each	\$

Date: 3 12 123

Signature:

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	< 1	\$3,000
institutional, multi-family residential, schools, and	1 < 5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150

CORE DATA FORM (TCEQ-10400)



TCEQ Core Data Form

TCEQ Use Only

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.


SECTION I: General Information

1. Reason fo	r Submis	sion (If other is c	hecked please d	describe in s	space р	rovided.)				
New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)											
Renewa	l (Core Da	ta Form should b	e submitted with	h the renewa	al form)] 01	ther			
2. Customer	Reference	e Number <i>(if is</i> s	ued)	Follow this lin	k to sea	rch 3.	. Reg	ulated	Entity Reference	Number (i	f issued)
CN 6024	12207		<u>f</u>	for CN or RN numbers in Central Registry** RN 105332522							
SECTION	II: Cu	stomer Info	<u>ormation</u>								
4. General C	ustomer l	nformation	5. Effective D	ate for Cus	tomer	Informa	tion l	Update	es (mm/dd/yyyy)		
☐ New Cust			•	date to Cus						Regulated E	Entity Ownership
									Public Accounts)		
			_	•			•			rent and	active with the
		f State (SOS)		-		blic A					
6. Customer	Legal Na	ne (If an individua	l, print last name f	first: eg: Doe,	John)		<u>If n</u>	ew Cus	stomer, enter previ	ous Custome	<u>er below:</u>
Lennar Homes of Texas Land and Construction, LTD											
7. TX SOS/CI		Number	8. TX State Ta		ts)		9. I	Federa	I Tax ID (9 digits)	10. DUN	S Number (if applicable)
00114529	10		175279201	189							
11. Type of C	ustomer	☐ Corporati	on		Individu	ıal		Par	tnership: 🔲 Genera	al 🛛 Limited	
Government:	☐ City ☐	County 🔲 Federal 🗆	☐ State ☐ Other		Sole Pr	oprietor	ship		Other:		
12. Number o	of Employ 21-100	rees 101-250	<u></u>	☐ 501 ar	nd highe	er	13.	Indep Yes	endently Owned	and Opera	ted?
14. Custome	r Role (Pr	oposed or Actual) -	- as it relates to th	e Regulated	Entity lis	ted on th	is forn	n. Pleas	e check one of the	following	
Owner	<u> </u>	☐ Opera	tor	<u></u> ⊠ 0	wner &	Operato	r				
Occupatio	nal Licens	ee Respo	nsible Party	□ Vo	oluntary	Cleanu	р Арр	olicant	Other:		
	100 N	E Loop 410,	Ste 1155								
15. Mailing Address:											
Address.	City	San Antoni	0	State	TX	Z	ΊΡ	7821	.6	ZIP + 4	
16. Country I	Mailing In	formation (if outsi	de USA)	L		17. E-N	lail A	ddress	(if applicable)		
,		,	,						lennar.com		
18. Telephon	e Numbe	r	1	19. Extension	on or C	ode			20. Fax Numbe	r (if applicat	ole)
(210)40	3-2600								()	-	
SECTION	III. B	egulated En	tity Inform	nation							
					v" is sel	lected h	elow t	his for	m should he acco	mnanied hy	a permit application)
☐ New Regu	_		to Regulated Er						Entity Information		a pormit approaudit)
				· ·					-		lards (removal
•		ndings such	•	•							,
22. Regulate	d Entity N	ame (Enter name	of the site where t	the regulated	action is	s taking p	olace.)				
Johnson Ranch North Unit 9 Replat											

TCEQ-10400 (02/21) Page 1 of 2

23. Street Address the Regulated Ent														
(No PO Boxes)	Ci	ty			State			ZIP	T		ZIP +	4		
24. County	С	omal			'						•			
		Er	nter Phy	sical Lo	cation Descrip	tion if	no stre	eet addres	s is p	rovided.				
25. Description to Physical Location	: 1,	300 LI	F nortl	n of Mu	ıstang Vista	and	Stahl	Lane in	terse	ection				
26. Nearest City									Sta	te		Nea	rest ZIP Code	
Bulverde									TX			78 1	163	
27. Latitude (N) In	Decimal:		29.77	75278			28. Lo	ongitude (W) In	Decimal:	-98.41	314	41	
Degrees	Mir	nutes		S	econds		Degree	es		Minutes		\dashv	Seconds	
29		4	16		31.0		-98			24		47.3		
29. Primary SIC Co	ode (4 digits	30.	Second	lary SIC	Code (4 digits)		Primar or 6 digits	y NAICS ()	Code	32. S (5 or 6	econdary digits)	NA	ICS Code	
1521						23	6115							
33. What is the Pri	imary Bus	iness of	this er	ntity? (Do not repeat the SI	C or NA	AICS desc	cription.)						
Single family	resident	ial												
	****					100	NE Lo	op 410, St	e 115	5				
34. Mailing														
Address:		City	San	Antonio	State	State TX				78216	ZIP -	- 4		
35. E-Mail Ad	droce:	Oity	Oan	Antonio	Otato			ZIP .mott@ler	nar c	162 166,000 10 010		•		
	elephone	Number			37. Extens			.mott@ici	iiiui.c	38. Fax Nu	mber (if a	laa	icable)	
	210) 403-									() -	1-1	,	
39. TCEQ Programs	and ID Nu	ımbers C				ermits	/registrat	tion number	s that	will be affected	d by the upd	ates	submitted on this	
form. See the Core Data	Form instr			nal guidano				□ Emiss	iono li	aventon, Air	☐ Indu	otric	l Hazardous Waste	
☐ Dam Safety	L	Districts	8		⊠ Edwards Ac	quilei			510115 11	nventory Air		Suia	TTIAZAIUOUS YVASIE	
☐ Municipal Solid Wa	aste F	☐ New Sc	ource Re	view Air	OSSF			☐ Petroleum Storage Tank			□ PWS			
	LIGHT L			710177111							_			
Sludge		Storm Water			☐ Title V Air			☐ Tires	Tires			☐ Used Oil		
_ •														
☐ Voluntary Cleanup	. [☐ Waste	Water		☐ Wastewater Agriculture ☐ Water				ater Rights			Other:		
								. *						
SECTION IV:	Prepa	rer In	form	ation										
40. Jean Au	0					41	I. Title:	Seni	ior P	roject Eng	gineer			
Name: Scan Fig. 42. Telephone Num					Number		45. E-M	ail Addres	s					
(210) 375-9000		<u> </u>			375-9010					vson.com				
,		1	G:	•	7575 7010	•	jaarro.	gepupe	- uur	, 5011.00111				
SECTION V: 46. By my signature signature authority to identified in field 39.	below, I c	ertify, to	the best	of my kr	nowledge, that the tity specified in	he info Section	ormation on II, Fi	n provided eld 6 and/o	in thi	s form is true equired for th	and comp ne updates	lete, to th	and that I have ne ID numbers	
Company:	Pape-Dav	wson Eng	jineers,	Inc.	п	J	ob Title	: Exe	cutive	Vice Preside	ent			
Name (In Print):	Trey Daw							·		Phone:	(210)3	75-	9000	
Signature:							ý			Date:	2/2	6	23	
/				_							-	ı		

EXHIBITS



SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT

MATERIALS

THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN. 2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF

8-INCHES. 3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2, A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE

4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OF

INSTALLATION

1. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.

2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.

3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG. 4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H: V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.

SURFACE SMOOTH AND SLOPE FOR DRAINAGE. 7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A

6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE

SEDIMENT TRAP OR BASIN. PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD

GEOTEXTILE FABRIC TO STABILIZE FOUNDATION

ISOMETRIC PLAN VIEW

WOVEN WIRE

SHEATHING

ROCK BERMS

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

INSPECTION AND MAINTENANCE GUIDELINES

. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.

REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.

3. REPAIR ANY LOOSE WIRE SHEATHING.

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION

THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

MATERIALS

SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT 2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE

THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE

WOVEN WIRE SHEATHING

USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE

SECTION "A-A

NSTALLATION . LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH

2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER.

3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO

A HEIGHT NOT LESS THAN 18" 4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES. AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.

5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE

6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL. COMMON TROUBLE POINTS

. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING

AROUND ONE SIDE).

ROCK BERM DETAIL

NOT-TO-SCALE

STEEL FENCE POST SILT FENCE -MAX. 8' SPACING(**` MIN. HEIGHT 24" \Min . EMBEDMENT = 1 ABOVE EXISTING GROUND) WIRE MESH BACKING 4X4~W1.4xW1.4 MIN. FEET. (RG-348, SECTION 1.4.3) COMPACTED EARTH OR ROCK BACKFILL - ALLOWARLE TYPICAL CHAIN LINK FENCE FABRIC IS ACCEPTABLE TRENCH-


ISOMETRIC PLAN VIEW

**STEEL POSTS, WHICH SUPPORT THE SIL FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE, POST MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET C CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6

SHOOTS OR GRASS BLADES. GRASS SHOULD BE GREEN AND HEALTHY: MOWED AT A 2"-3" CUTTING HEIGHT. - THATCH- GRASS CLIPPINGS AND DEAD LEAVES, UP TO 1/2" THICK.

SOIL.

LAY SOD IN A STAGGERED PATTERN. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER. DO NOT LEAVE SPACES AND DO NOT OVERLAP. A SHARPENED MASON'S TROWEL IS A HANDY TOOL FOR TUCKING DOWN THE ENDS AND TRIMMING PIECES.



AUTOMATIC SOD CUTTER MUST BE MATCHED

MATERIALS

OF 36 HOURS.

SHOOT GROWTH AND THATCH.

SITE PREPARATION

TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.


SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.

TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.

INSTALLATION IN CHANNELS

TIGHTLY (SEE FIGURE ABOVE).

INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.



1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH

STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO

SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN

4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD

PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT

THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL

FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE

DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS

CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER

SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC,

FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE

SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE

. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO

RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER

NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL

DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS

IN CRITICAL AREAS, SECURE SOD

WITH THE GROUND. WITH NETTING. USE STAPLES. GENERAL INSTALLATION (VA. DEPT. OF CONSERVATION, 1992)

REDUCE ROOT BURNING AND DIEBACK.

(SEE FIGURE ABOVE).

(± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN. 2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND 2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY LENGTH. WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%. IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND

SECTION "A-A" OF A

CONSTRUCTION ENTRANCE/EXIT

STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY

PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC-EXTEND PAD BEYOND

4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING

5. UNSTABLE FOUNDATION - USE GEOTEXTILE FABRIC UNDER PAD AND/OR

. THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL

PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY.

THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS

CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES

2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC

3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT

4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED

WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR

5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN,

INCORRECT

SOD INSTALLATION

USE PEGS OR STAPLES TO FASTEN SOD

FIRMLY - AT THE ENDS OF STRIPS AND

IN THE CENTER, OR EVERY 3-4 FEET IF

THE STRIPS ARE LONG. WHEN READY TO

MOW, DRIVE PEGS OR STAPLES FLUSH

RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.

INSPECTION AND MAINTENANCE GUIDELINES

1. INADEQUATE RUNOFF CONTROL-SEDIMENT WASHES ONTO PUBLIC ROAD.

COMMON TROUBLE POINTS

CONDITION AS STONE IS PRESSED INTO SOIL.

IMPROVE FOUNDATION DRAINAGE.

USED TO TRAP SEDIMENT

SEDIMENT BASIN.

ROOT ZONE - SOIL AND ROOTS.

SHOULD BE 1/2"-3/4" THICK, WITH

DENSE ROOT MAT FOR STRENGTH.

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

NOT-TO-SCALE

APPEARANCE OF GOOD SOD

1. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE

2. WATER TO A DEPTH OF 4" AS NEEDED. WATER WELL AS

THE MINIMUM 50-FOOT LENGTH AS NECESSARY.

TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.

PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.

DITCH OR WATER COURSE BY USING APPROVED METHODS.

THE FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OF OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).

5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL. AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS

> UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4 8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY

> ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

INSPECTION AND MAINTENANCE GUIDELINES SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

IS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. THAT WAS STORED AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHER AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHER AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT'S AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT'S AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT'S AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT'S AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT'S AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE BY THE CONSULTANT BY THE CON

2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS SOON AS PRACTICAL.

SOD INSTALLATION DETAIL

NOT-TO-SCALE

SILT FENCE

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

. SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

INSTALLATION

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.

2. LAY OUT FENCING DOWN—SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.

TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL. 5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

COMMON TROUBLE POINTS

FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO CONCENTRATE AND FLOW OVER THE FENCE.

2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER

FENCE). 3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING

4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).

INSPECTION AND MAINTENANCE GUIDELINES 1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL

2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.


3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.

4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

SILT FENCE DETAIL

NOT-TO-SCALE



GENERAL NOTES

A MANNER THAT IT WILL NOT ERODE.

. CONTRACTOR TO INSTALL 2"x4"-W1.4xW1.4 WIRE MESH SUPPORTING FILTER FABRIC OVER THE INLET OPENING. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR WIRE TIES AT THIS LOCATION. SAND BAGS FILLED WITH WASHED PEA GRAVEL SHOULD BE PLACED ON TOP OF WIRE MESH ON TOP OF THE INLET AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SANDBAGS FILLED WITH WASHED PEA GRAVEL SHOULD ALSO BE PLACED ALONG THE GUTTER AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SAND BAGS TO BE STACKED TO FORM A CONTINUOUS BARRIER AROUND INLETS.

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.

INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE


2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH

3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND


4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING. 5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

BAGGED GRAVEL CURB INLET PROTECTION DETAIL

NOT-TO-SCALE



PLAN VIEW



GENERAL NOTES

DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE. 2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO

SECTION "A-A"

CONSTRUCTION TRAFFIC. S. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF. 4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES,

STORM DRAINS, OPEN DITCHES OR WATER BODIES. 6. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.

MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

MAINTENANCE


WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF. . MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT

. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED

CONCRETE TRUCK WASHOUT PIT DETAIL

NOT-TO-SCALE



WAY

DRIVE WAY

LOT TYPE-B

HOUSE PAD

LOT TYPE-C

TYPICAL HOUSE LOT LAYOUTS

NOT-TO-SCALE

NOTE: SILT FENCE TO BE INSTALLED PER


DOWNGRADIENT SIDE OF EACH LOT LINE

THESE DETAILS AND LOCATED ON THE

OR LIMITS OF CLEARING AS GENERALLY

SHOWN ON THE OVERALL SITE PLAN.

PLAN VIEW



PROPERT

LEGEND

-\\-\\- SILT FENCE

DRAINAGE FLO


SECTION "A-A"

THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.

THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). 3. SAND SHALL <u>NOT</u> BE USED TO FILL THE FILTER BAGS.

GRAVEL FILTER BAG DETAIL

NOT-TO-SCALE



CONSTRUCTION STAGING AREA

NOT-TO-SCALE

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

THIS SHEET HAS BEEN PREPARED FOI PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

SIGNER

8547-95 HECKED DW DRAWN

Jon Niermann, *Chairman*Emily Lindley, *Commissioner*Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

July 9, 2019

Mr. Brian Barron Lennar Homes of Texas Land and Construction, Ltd. 1922 Dry Creek Way, Ste. 101 San Antonio, Texas 78259

Re: Edwards Aquifer, Comal County

NAME OF PROJECT: Johnson Ranch North; Located along Mustang Vista between US Hwy 281 and Stahl Lane; Bulverde, Texas

TYPE OF PLAN: Request for an Exception to the Requirements of a Contributing Zone Plan (WPAP); 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program ID No. 13000925; Regulated Entity No. RN105332522

Dear Mr. Barron:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the Exception Request application for the above-referenced project submitted to the San Antonio Regional Office by the Pape-Dawson Engineers, Inc on behalf of Lennar Homes of Texas Land and Construction, Ltd. on May 24, 2019. As presented to the TCEQ, the Exception Request proposed in the submittal is in general compliance with the requirements of 30 TAC Chapter 213. Therefore, the request for exception is hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer Protection Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been requested.

BACKGROUND

Johnson Ranch North was originally included in the Johnson Ranch Water Pollution Abatement Plan (WPAP), RN105332522, Additional ID 13-07082901, approved on October 24, 2007. The project was a residential development within a 751.3-acre project area with 4.44 acres of impervious cover. The 751.3-acre site was in both the Recharge and Contributing Zone. An exemption from permanent BMPs was approved.

Johnson Ranch North Contributing Zone Plan (CZP), RN106650898, Additional ID 13-13032701, approved on July 1, 2013, provided a new legal boundary that separated the proposed regulated activities on the Contributing Zone from those being proposed on the Recharge Zone. The new CZP proposed a single-family residential development within 262.24 acres with 48 acres of impervious cover. The single-family residential site will not have more than 20 percent impervious cover. The regulated entity number associated with the Johnson Ranch North CZP, RN106650898 was merged with the existing regulated entity number RN105332522.

PROJECT DESCRIPTION

The proposed residential project will have an area of approximately 13.03 acres within the previously approved 262.24-acre development. It will include limited demolition, additional clearing, grading, excavation, and drainage improvements for construction of approximately 43,995 feet of road widening and sidewalk construction. The impervious cover will be 1.001 acres (7.6 percent). The overall project will have 49.58 acres (18.91 percent) of impervious cover. No wastewater will be generated by this project.

PERMANENT POLLUTION ABATEMENT MEASURES

This single-family residential project will not have more than 20 percent impervious cover.

EQUIVALENT WATER QUALITY PROTECTION

Lennar Homes of Texas Land and Construction, Ltd. requests an exception to submitting an Edwards Aquifer protection plan modification required by 30 TAC 213.5; however, proposes an exception under 30 TAC 213.9. The proposed development demonstrates equivalent water quality protection for the Edwards Aquifer.

SPECIAL CONDITIONS

- I. This exception is subject to all Special and Standard Conditions listed in the CZP/WPAP approval letters dated October 24, 2007, and July 1, 2013.
- II. The applicant requested a waiver to the requirement for other permanent BMPs for this single-family residential project because the development will have less than 20 percent impervious cover. Based on the TCEQ's Review of the proposed activities and the site conditions, the required waiver is hereby granted. If the percent impervious cover ever increases above 20 percent or the land use changes, the exemption for the whole site as described in the Exception Request may no longer apply and the property owner must notify the San Antonio Regional Office of these changes.

STANDARD CONDITIONS

- 1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
- 2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
- 3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

Mr. Brian Barron Page 3 July 9, 2019

Prior to Commencement of Construction:

- 4. Within 60 days of receiving written approval of an Edwards Aquifer Protection Plan, the applicant must submit to the San Antonio Regional Office, proof of recordation of notice in the county deed records, with the volume and page number(s) of the county deed records of the county in which the property is located. A description of the property boundaries shall be included in the deed recordation in the county deed records. A suggested form (Deed Recordation Affidavit, TCEQ-0625) that you may use to deed record the approved CZP is enclosed.
- 5. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved CZP and this notice of approval shall be maintained at the project location until all regulated activities are completed.
- 6. Modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.
- 7. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person. The executive director will use the notification to determine if the approved plan is eligible for an extension.
- 8. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved CZP, must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. If a water quality pond is proposed, it shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.
- 9. All borings with depths greater than or equal to 20 feet must be plugged with non-shrink grout from the bottom of the hole to within three (3) feet of the surface. The remainder of the hole must be backfilled with cuttings from the boring. All borings less than 20 feet must be backfilled with cuttings from the boring. All borings must be backfilled or plugged within four (4) days of completion of the drilling operation. Voids may be filled with gravel.

During Construction:

- 10. During the course of regulated activities related to this project, the applicant or agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
- 11. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 6, above.
- 12. If any sensitive feature (caves, solution cavities, sink holes, etc.) is discovered during construction, all regulated activities near the feature must be suspended immediately. The applicant or his agent must immediately notify the San Antonio Regional Office of the discovery of the feature. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality. The plan must be sealed, signed, and dated by a Texas Licensed Professional Engineer.
- 13. No wells exist on site. All water wells, including injection, dewatering, and monitoring wells must be in compliance with the requirements of the Texas Department of Licensing and

Mr. Brian Barron Page 4 July 9, 2019

Regulation under Title 16 TAC Chapter 76 (relating to Water Well Drillers and Pump Installers) and all other locally applicable rules, as appropriate.

- 14. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
- 15. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge will be filtered through appropriately selected best management practices. These may include vegetated filter strips, sediment traps, rock berms, silt fence rings, etc.
- 16. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 17. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

- 18. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the San Antonio Regional Office within 30 days of site completion.
- 19. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. The regulated entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through Austin Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
- 20. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Edwards Aquifer protection plan. If the new owner intends to commence any new regulated activity on the site, a new Edwards Aquifer protection plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.
- 21. An Edwards Aquifer protection plan approval or extension will expire, and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Edwards Aquifer protection plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
- 22. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

Mr. Brian Barron Page 5 July 9, 2019

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Ms. Neri De La Garza of the Edwards Aquifer Protection Program of the San Antonio Regional Office at (210) 403-4087.

Sincerely, Jilia Buth

Robert Sadlier, Section Manager

Edwards Aquifer Protection Program

Texas Commission on Environmental Quality

RCS/ndlg

Enclosures:

Deed Recordation Affidavit, Form TCEQ-0625

cc:

Mr. Trey Dawson, P.E., Pape-Dawson Engineers, Inc.

The Honorable Bill Krawietz, City of Bulverde Mr. Roland Ruiz, Edwards Aquifer Authority

Mr. Thomas H. Hornseth, P.E., Comal County

Mr. H.L. Saur, Comal Trinity Groundwater Conservation District