

BROOK STONE PHASE 1

Water Pollution Abatement Plan Modification

May 2023



BROOK STONE PHASE 1

Water Pollution Abatement Plan Modification

May 2023



5/18/2023

May 18, 2023

Ms. Lillian Butler
Texas Commission on Environmental Quality (TCEQ)
Region 13
14250 Judson Road
San Antonio, Texas 78233-4480

Re: Brook Stone Phase 1
Water Pollution Abatement Plan Modification

Dear Ms. Butler:

Please find attached one (1) original, one (1) digital, and one (1) copy of the Brook Stone Creek Phase 1 Water Pollution Abatement Plan Modification. This Water Pollution Abatement Plan Modification has been prepared to be consistent with the regulations of the Texas Commission on Environmental Quality (30 TAC 213) and current policies for development over the Edwards Aquifer Recharge Zone.

This Water Pollution Abatement Plan Modification applies to an approximate 33.05-acre site identified as the limits of the project. Please review the plan information for the items it is intended to address, and, if acceptable, provide a written approval of the plan in order that construction may begin at the earliest opportunity.

Appropriate review fees (\$4,000) and fee application are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,
Pape-Dawson Engineers, Inc.



Becky Carroll, P.E.
Vice President

Attachments

P:\120\93\04\Word\Reports\WPAP MOD\210315a1.docx

**EDWARDS AQUIFER
APPLICATION COVER PAGE
(TCEQ-20705)**

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Brook Stone Phase I					2. Regulated Entity No.: 111017802				
3. Customer Name: Continental Homes of Texas, L.P.					4. Customer No.: 601213523				
5. Project Type: (Please circle/check one)	New	Modification			Extension	Exception			
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential		Non-residential			8. Site (acres):		33.05	
9. Application Fee:	\$4000.00		10. Permanent BMP(s):			Batch Detention & Veg Filter Strips			
11. SCS (Linear Ft.):			12. AST/UST (No. Tanks):						
13. County:	Bexar		14. Watershed:			Elm Waterhole Creek/Salado Creek			

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	✓	—	—	—	—
Region (1 req.)	✓	—	—	—	—
County(ies)	✓	—	—	—	—
Groundwater Conservation District(s)	<input checked="" type="checkbox"/> Edwards Aquifer Authority <input checked="" type="checkbox"/> Trinity-Glen Rose	<input type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input checked="" type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Rebecca Ann Carroll, P.E.

Print Name of Customer/Authorized Agent

5/18/2023

Signature of Customer/Authorized Agent

Date

****FOR TCEQ INTERNAL USE ONLY****

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

**GENERAL INFORMATION
FORM (TCEQ-0587)**

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Becky Carroll, P.E.

Date: 5/18/2023

Signature of Customer/Agent:



Project Information

1. Regulated Entity Name: Brook Stone Phase 1 - Modification
2. County: Bexar
3. Stream Basin: Elm Waterhole Creek
4. Groundwater Conservation District (If applicable): Edwards Aquifer Authority
5. Edwards Aquifer Zone:
 Recharge Zone
 Transition Zone
6. Plan Type:
 WPAP
 SCS
 Modification
 AST
 UST
 Exception Request

7. Customer (Applicant):

Contact Person: Leslie Ostrander
Entity: Continental Homes of Texas L.P.
Mailing Address: 5419 N. Loop 1604
City, State: San Antonio, Texas Zip: 78247
Telephone: (210) 496-2668 FAX: _____
Email Address: LKOstrander@drhorton.com

8. Agent/Representative (If any):

Contact Person: Becky Carroll, P.E.
Entity: Pape-Dawson Engineers, Inc.
Mailing Address: 2000 NW Loop 410
City, State: San Antonio, Texas Zip: 78213
Telephone: (210) 375-9000 FAX: (210) 375-9010
Email Address: bcarroll@pape-dawson.com

9. Project Location:

- The project site is located inside the city limits of _____.
- The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of San Antonio.
- The project site is not located within any city's limits or ETJ.

10. The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

From TCEQ's regional office, head north on Judson Road approximately 2.5 miles to Loop 1604. Travel west on Loop 1604 approximately 1.8 miles and exit to Bulverde Road. Continue on Bulverde Road for 3.3 miles to Evans Road and turn right. Travel on Evans Road for 2.0 miles. The site is located south of Evans Road & Wortham Oaks intersection

11. **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12. **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- Project site boundaries.
 - USGS Quadrangle Name(s).
 - Boundaries of the Recharge Zone (and Transition Zone, if applicable).
 - Drainage path from the project site to the boundary of the Recharge Zone.
13. **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate

the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

Survey staking will be completed by this date: When advised by TCEQ of site visit.

14. **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- Area of the site
- Offsite areas
- Impervious cover
- Permanent BMP(s)
- Proposed site use
- Site history
- Previous development
- Area(s) to be demolished

15. Existing project site conditions are noted below:

- Existing commercial site
- Existing industrial site
- Existing residential site
- Existing paved and/or unpaved roads
- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Uncleared)
- Other: _____

Prohibited Activities

16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

18. The fee for the plan(s) is based on:

- For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
- For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
- For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
- A request for an exception to any substantive portion of the regulations related to the protection of water quality.
- A request for an extension to a previously approved plan.

19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:


- TCEQ cashier
- Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
- San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.


ATTACHMENT A

BROOK STONE PHASE I Water Pollution Abatement Plan Modification



ATTACHMENT B

BROOK STONE PHASE I
Water Pollution Abatement Plan Modification



Date: Jan 09, 2023, 11:14am User ID: ssepulveda
 File: P:\120193\04\Design\Exhibits\WPAP\001209304.dwg

GENERAL LOCATION MAP - BULVERDE, TX QUAD;
 LONGHORN, TX QUAD
 DRAINAGE FLOW 
 Pape-Dawson Engineers, Inc.


MATCHLINE See Sheet 2 of 2

USGS/EDWARDS RECHARGE ZONE MAP
 Sheet 1 Of 2
 ATTACHMENT B

BROOK STONE PHASE I
Water Pollution Abatement Plan Modification

MATCHLINE See Sheet 1 of 2


SCALE: 1" = 2000'



Date: Jun 23, 2021, 11:13am User ID: SSepulveda
File: P:\120193\04 Design Exhibits\WPAP\021209304.dwg

GENERAL LOCATION MAP - BULVERDE, TX QUAD;
LONGHORN, TX QUAD
DRAINAGE FLOW 
Pape-Dawson Engineers, Inc.

USGS/EDWARDS RECHARGE ZONE MAP
Sheet 2 Of 2
ATTACHMENT B

ATTACHMENT C

BROOK STONE PHASE 1

Water Pollution Abatement Plan Modification

Attachment C – Project Description

Brook Stone Phase I - Modification Water Pollution Abatement Plan (WPAP) proposes the construction of a single-family residential development on approximately 33.05-acres identified as the Project Limits. The project site is located outside the city limits of San Antonio, but within its extra-territorial jurisdiction in Bexar County, Texas. The entire site is located over the Edwards Aquifer Recharge Zone. The project site is located south of Evans Rd. and Wortham Oaks intersection. The site is partially cleared and undeveloped, is bound by the 100-year floodplain to the west, and no naturally-occurring sensitive features were identified in the geologic assessment.

The previously approved WPAP consisted of approximately 18.52 acres of impervious cover, with a total project limits of 94.40 acres. The WPAP proposed clearing, grading, mass grading for soils, excavation for installation of utilities and drainage improvements, roads, construction of 196 single-family homes, and two (2) batch detention basins.

This WPAP modification proposes clearing, grading, mass grading for soils, excavation for installation of utilities and drainage improvements, construction of 120 single-family homes, roads, and one (1) batch detention basin. Home lots will have approximately 3,000 SF of impervious cover to include the housepad, driveway, and concrete patio. Approximately 11.53 acres of impervious cover, or 34.89% of the 33.05 acre project limits, are proposed for construction in this WPAP modification.

One (1) Batch Detention Basin "C", one (1) fifteen-foot (15') engineered Vegetative Filter Strips (VFS) , and four (4) fifty-foot (50') natural Vegetative Filter Strips (VFS) are proposed as the Permanent Best Management Practices (PBMPs) for the improvements proposed with this WPAP. All PBMPs have been designed in accordance with the TCEQ'S Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site. Uncaptured areas have been accounted in overtreatment within the proposed PBMPs.

The permanent population associated with Brook Stone Phase I - Modification is estimated to be 480 people, based on four (4) persons per lot. Potable water service is to be provided by the San Antonio Water System (SAWS). The proposed development will generate approximately 28,800 gallons per day (average flow) of domestic wastewater based on the assumption of 1 EDU per lot at 240 gpd/EDU. The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by the San Antonio Water System (SAWS). Potable water will be supplied by SAWS.

GEOLOGIC ASSESSMENT FORM
(TCEQ-0585)

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Henry E. Stultz III

Telephone: 210-375-9000

Date: *March 20, 2020*

Fax: 210-375-9090

Representing: Pape-Dawson Engineers, Inc., Texas Board of Professional Geoscientists No. 50351
(Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



Regulated Entity Name: SCHWAB TRACT



Section 1.01 Project Information

1. Date(s) Geologic Assessment was performed: October 26, 2017; October 27, 2017; November 14, 2017; January 22, 2020
2. Type of Project:
 WPAP AST
 SCS UST
3. Location of Project:
 Recharge Zone
 Transition Zone
 Contributing Zone within the Transition Zone

SCHWAB TRACT

Geologic Assessment

4. **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

Soil Name	Group*	Thickness(feet)
Crawford and Bexar stoney soils (Cb)	D	2-4
Eckrant cobby clay, 5-15% slopes (TaC)	D	1-2

* Soil Group Definitions (Abbreviated)

- A. Soils having a high infiltration rate when thoroughly wetted.
 - B. Soils having a moderate infiltration rate when thoroughly wetted.
 - C. Soils having a slow infiltration rate when thoroughly wetted.
 - D. Soils having a very slow infiltration rate when thoroughly wetted.
6. **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
 7. **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
 8. **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'
 Applicant's Site Plan Scale: 1" = 200'
 Site Geologic Map Scale: 1" = 200'
 Site Soils Map Scale (if more than 1 soil type): 1" = 1000'
 9. Method of collecting positional data:
 - Global Positioning System (GPS) technology.
 - Other method(s). Please describe method of data collection:
 10. The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
 11. Surface geologic units are shown and labeled on the Site Geologic Map.

SCHWAB TRACT

Geologic Assessment

12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
- Geologic or manmade features were not discovered on the project site during the field investigation.
13. The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
- There are (4) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
- The wells are not in use and have been properly abandoned.
- The wells are not in use and will be properly abandoned.
- The wells are in use and comply with 16 TAC Chapter 76.
- There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A

PROJECT NAME: SCHWAB TRACT

GEOLOGIC ASSESSMENT TABLE

LOCATION		FEATURE CHARACTERISTICS										EVALUATION			PHYSICAL SETTING			
1A	1B*	1C*	2A	2B	3	4			5	5A	6	7	8A	8B	9	10	11	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIMENSIONS (FEET)			TEND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILLING	RELATIVE INFILTRATION RATE	TOTAL	SENSITIVITY	CATCHMENT AREA (ACRES)	TOPOGRAPHY
						X	Y	Z		10						<40	<1.6	
S-1	29.64154	-98.38388	SH	20	Kep	12	8	2	N10E				F,O	10	30	30	X	Hillside
S-2	29.64186	-98.39164	SC	20	Kep	1	1	3					F,O	10	30	30	X	Hillside
S-3	29.63944	-98.37818	SC	20	Kep	2.9	3.6	5.5	N40E	10			N,F,O	25	65	65	X	Hillside
S-5	29.63778	-98.38456	SC	20	Kep	1.5	0.7	2.0	S20E				F,O	10	30	30	X	Hillside
S-6	29.64051	-98.38639	C	30	Kep	4	3	10					N,F,S	35	65	65	X	Floodplain
S-7	29.64078	-98.38456	C	30	Kep	11	14	24	N80E				N,F,S,F	35	65	65	X	Hillside
S-8	29.63556	-98.39502	C	30	Kep	12	20	12					N,F,V	35	65	65	X	Drainage
S-10	29.63680	-98.39364	MB	30	Kep								N,X	20	50	50		Hillside
S-11	29.63418	-98.39178	MB	30	Kep								N,X	5	35	35	X	Hillside
S-12	29.63381	-98.39148	MB	30	Kep								N,X	5	35	35	X	Hilltop
S-13	29.63368	-98.39145	MB	30	Kep								N,X	5	35	35	X	Hilltop
S-14	29.63329	-98.39123	MB	30	Kep								N,X	5	35	35	X	Hilltop
S-15	29.63315	-98.39134	MB	30	Kep								N,X	5	35	35	X	Hilltop
S-16	29.63321	-98.39198	MB	30	Kep								N,X	5	35	35	X	Hillside
S-17	29.63978	-98.38297	MB	30	Kep	1710							F,C	20	50	50	X	Hillside
S-18	29.63908	-98.37828	F	20	Kep	<2000			N23E				F	5	25	25	X	Drainage
S-19	29.63814	-98.38229	F	20	Kep	<2000			N43E	10			F	5	35	35	X	Hillside
S-20	29.63888	-98.38367	F	20	Kep	<2000			N42E	10			F	5	35	35	X	Hillside
S-21	29.63995	-98.38597	F	20	Kep	<2000			N41E	10			F	5	35	35	X	Hillside

** DATUM: NAD 83

2A TYPE	TYPE	2B POINTS
C	Cave	30
SC	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
O	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
SW	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

8A INFILLING

N None, exposed bedrock
 C Coarse - cobbles, breakdown, sand, gravel
 O Loose or soft mud or soil, organics, leaves, sticks, dark colors
 F Fines, compacted clay-rich sediment, soil profile, gray or red colors
 V Vegetation. Give details in narrative description
 FS Flowstone, cements, cave deposits
 X Other materials

12 TOPOGRAPHY

Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed



I have read, I understand, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

[Handwritten Signature]

Date: March 29, 2020

ATTACHMENT B

SCHWAB TRACT Stratigraphic Column

Period	Epoch	Group	Formation	Member	Thickness	Lithology	Hydro-logic Unit	Hydrostratigraphic Unit	Hydrologic Function	Porosity	Cavern Development
Cretaceous	Early Cretaceous	Edwards	Person	Cyclic and marine, undivided	80-90	Pelletal limestone; ranges from chalk to mudstone and miliolid grainstone; thin to massive beds; some crossbedding evident; a packstone containing large caprinids is present near contact with the overlying Georgetown Formations; chert is common as beds and large nodules	Edwards Aquifer	II	Aquifer	MO, BU, VUG, BP, FR, CV	Many subsurface; might be associated with earlier karst development
				Leached and collapsed, undivided	70-90	Hard, dense, recrystallized limestone; mudstone, wackestone, packstone, and grainstone; contains chert as beds and large nodules; heavily bioturbated with iron-stained beds; often stromatolitic; <i>Toucasia</i> sp. Often found above contact with the underlying regional dense member; <i>Montastrea roemeriana</i> and oysters rare		III	Aquifer	BU, VUG, FR, BP, BR, CV	Extensive lateral development; large rooms
				Regional dense	20-24	Dense, shaly limestone; oyster shell mudstone and iron wackestone; wispy iron staining; chert nodules rarer than in the rest of the chert-bearing Edwards Group		IV	Confining	FR, CV	Very few; only vertical fracture enlargement
			Kainer	Grainstone	40-50	Hard, dense limestone that consists mostly of a tightly cemented miliolid skeletal fragment grainstone; contains interspersed chalky mudstone and wackestone; chert as beds and nodules; crossbedding and ripple marks are common primarily at the contact with the overlying regional dense bed		V	Aquifer	IP, IG, BU, FR, BP, CV	Few
				Kirschberg Evaporite	40-50	Highly altered crystalline limestone and chalky mudstone with occasional grainstone associated with tidal channels; chert as beds and nodules, boxwork molds are common, matrix recrystallized to a coarse grain spar; intervals of collapse breccia and travertine deposits		VI	Aquifer	IG, MO, VUG, FR, BR, CV	Probably extensive cave development
				Dolomitic	90-120	Hard, dense to granular, dolomitic limestone; chert as beds and nodules (absent in lower 20 ft); <i>Toucasia</i> sp. abundant; lower three-fourths composed of sucrosic dolomites and grainstones with hard, dense limestones interspersed; upper one-fourth composed mostly of hard, dense mudstone, wackestone, packstone, grainstone, and recrystallized dolomites with bioturbated beds		VII	Aquifer	IP, IC, IG, MO, BU, VUG, FR, BP, CV	Caves related to structure or bedding planes
				Basal nodular	40-50	Moderately hard, shaly, nodular, burrowed mudstone to miliolid grainstone that also contains dolomite; contains dark, spherical textural features known as black rotund bodies; <i>Ceratostreon texana</i> , <i>Caprina</i> sp., miliolids, and gastropods		VIII	Aquifer, confining unit in areas without caves	IP, MO, BU, BP, FR, CV	Large lateral caves at surface

Source: Clark, Golab, and Morris (2016); Cavern development modified from Stein and Ozuna (1995). Porosity types - Fabric selective: IP, interparticle porosity; IG, intergranular porosity; IC, intercrystalline porosity; SH, shelter porosity; MO, moldic porosity; BU, burrowed porosity; FE, fenestral; BP, bedding plane porosity. Not fabric selective: FR, fracture porosity; CH, channel porosity; BR, breccia; VUG, vug porosity; CV, cave porosity.

ATTACHMENT C

SCHWAB TRACT

Geologic Assessment

SUMMARY

The Schwab Tract is located in Bexar County, Texas along Evans Road south of the intersection with Cibolo Vista. The site is currently vacant. Historical aerial photographs indicate the site was predominantly agricultural rangeland with large trees.

Based on the results of the field survey conducted in accordance with *Instructions for Geologists for Geologic Assessments in the Edwards Aquifer Recharge/Transition Zones (TCEQ-0585 Instructions)*, four naturally occurring sensitive features were identified on site. Buffers around the sensitive features were created in accordance with *TCEQ RG-348 Complying with the Edwards Aquifer Rules Technical Guidance on Best Management Practices / Chapter 5 and RG-348 Addendum*. Based on the frequency distribution of sensitive features, the overall potential for fluid migration to the Edwards Aquifer for the site is moderate.

SITE GEOLOGY

As observed through field evidence, the subject site is located within the leached and collapsed (Keplc) member of the Person formation. The Keplc is characterized by interbedded, iron-stained, massive and bioturbated limestone with abundant chert. Karst development within the Keplc is generally characterized by large sinkholes. Caves often develop as large horizontal rooms. (Clark, 2016).

The predominant trend of faults in the vicinity of the site is approximately N45°E, based on faults identified during the previous mapping of the area.

FEATURE DESCRIPTIONS:

A description of the features observed onsite is provided below:

Feature S-1

Feature S-1 is a sinkhole with organics, fine infilling and a thick soil profile that may have been enlarged by animal burrow. No rim rock or bedrock was observed. Therefore, the probability for rapid infiltration is low.

Feature S-2 and S-5

Feature S-2 and S-5 are solution cavities that have been burrowed by animals. Fine and organic soil fill the features. Due to the likely karst origin and fine soil infilling, the probability for rapid infiltration is low.

Feature S-3

Feature S-3 is a vertical solution cavity near a natural drainage. Due to the karst origin, lack of infilling, and proximity to the stream, the probability for rapid infiltration is high.

Attachment C

SCHWAB TRACT

Geologic Assessment

Feature S-6

Feature S-6 is a cave located within the floodplain. Three openings at the surface, which are connected at depth mark the entrance to the cave. The largest entrance is an approximately 3 feet long by 2 feet wide shaft that drops to a 4 foot wide by 6 foot tall shaft. Because the feature is an open vertical shaft cave located within the floodplain, the probability of rapid infiltration is high.

Feature S-7

Feature S-7 is a cave located on a hillside. The entrance is approximately 3 feet long by 2 feet wide, and is roughly shaft shaped. The shaft drops 24 feet and is 11 foot wide by 14 foot long at the bottom. Because the feature is an open vertical shaft cave, the probability of rapid infiltration is high.

Feature S-8

Feature S-8 is a cave located within a drainage channel. The entrance is approximately 3 feet long by 2 feet wide and drops 12 feet to a 12 foot wide by 20 foot long room. Because the feature is an open cave located within a drainage channel, the probability of rapid infiltration is high.

Feature S-10

Feature S-10 is a water well that is located near a dilapidated ranch home. The well is constructed with steel casing extending above a concrete slab. The well is open, and airflow was observed coming from the well. Since the well is not capped but extends above the surface on a concrete slab, the probability for rapid infiltration is intermediate.

Features S-11, S-12, and S-13

Features S-11, S-12, and S-13 are existing water wells that extend approximately 1.5 feet above ground surface. Because of the unknown ages, integrity of casings, and location of casing above the ground surface, the probability for rapid infiltration is low.

Feature S-14, S-15, and S-16

Feature S-14, S-15, and S-16 are septic tanks. Due to the non-karst origin and the likelihood that the septic system is confined to the soil horizon, the probability for rapid infiltration to the aquifer is low.

Feature S-17

Feature S-17 is an existing sewer line that is not located beneath pavement. The sewer line has been trenched through bedrock and backfilled with a mix of fine and course fill material that may be more permeable than surrounding undisturbed areas. Therefore, the probability of rapid infiltration is intermediate.

SCHWAB TRACT

Geologic Assessment

Features S-18, S-19, S-20, and S-21

Features S-18, S-19, S-20, and S-21 are intraformational faults within the Keplc. The faults were identified through aerial photographs and field evidence. Fine infilling with no evidence of increased permeability were observed at the ground surface onsite, therefore the probability of rapid infiltration is low.


REFERENCES

Clark, A.K., Golab, J.A., and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers Within Northern Bexar and Comal Counties, Texas: U.S. Geological Survey Scientific Investigations Map 3366, scale 1:24,000, 20 p. pamphlet.


Nationwide Environmental Title Research, LLC. Historical Aerials. historicalaerials.com. Web. March 20, 2020.

Texas Water Development Board, Wells in TWDB Groundwater Database Viewer, <http://www2.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer>, March 20, 2020.

ATTACHMENT D



 Site Boundary




JOB NO. 12093-00
 DATE Mar 2020
 DESIGNER HS
 CHECKED HDJ DRAWN HS
 SHEET Attachment D

SCHWAB TRACT
SAN ANTONIO, TEXAS
SITE SOILS MAP


PAPE-DAWSON ENGINEERS

SAN ANTONIO | AUSTINI | HOUSTONI | FORT WORTH | DALLAS
 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028800

LEGEND	
	PROJECT LIMITS
	100 YEAR FLOODPLAIN
	STREAM
	SYMBOLS AND LINES
	POTENTIAL RECHARGE FEATURE
	CONTACT, LOCATED APPROXIMATELY
	CONTACT, INFERRED
	FAULT, LOCATED APPROXIMATELY (D, DOWNTHROWN SIDE; U, UPTHROWN SIDE)
	FAULT, EXTRAPOLATED
	FAULT, INFERRED
	STRIKE AND DIP OF BEDDING
	STRIKE AND DIP OF JOINTS
	STRIKE OF VERTICAL JOINTS
	CAVE
	SOLUTION CAVITY
	SANITARY SEWER LINE
	ALLUVIUM
	EAGLE FORD
	BUDA
	DEL RIO
	GEORGETOWN
	PERSON
	KAINER
	GLEN ROSE
	SOLUTION ENLARGED FRACTURE
	SWALLOW HOLE
	SINKHOLE
	NON-KARST CLOSED DEPRESSION
	ZONE
	OTHER NATURAL BEDROCK FEATURES
	SPRING/SEEP
	MAN-MADE FEATURE IN BEDROCK
	WATER WELL




DATE	
NO.	
REVISION	



NOTE: THE GEOSCIENTIST SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR PURPOSES OF GEOLOGIC INFORMATION. ALL OTHER INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SIGNED AND SEALED CIVIL ENGINEERING DRAWINGS.

NOTE: THE RECHARGE ZONE BOUNDARY IS NOT WITHIN THE AREA SHOWN ON THIS SHEET. THE SITE IS LOCATED ENTIRELY WITHIN THE RECHARGE ZONE.

NOTE: ONLY THOSE GEOLOGIC FEATURES WITHIN THE AREA OF THIS ASSESSMENT ARE INCLUDED. THEREFORE, THE FEATURES MAY NOT BE NUMBERED SEQUENTIALLY.




Notes: Mxd: 18_2020_14_26p.m User ID: H5Stu1z
 File: P:\12013\12013\ENR\CA\Attachments\GAL12093000 - Overall.dwg

PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TEPF FIRM REGISTRATION #470 | TEPF FIRM REGISTRATION #60351

SCHWAB TRACT
 SAN ANTONIO, TEXAS
 SITE GEOLOGIC MAP
 WATER POLLUTION ABATEMENT PLAN

JOB NO.	12093-00
DATE	MARCH 2020
DESIGNER	HS
CHECKED	HDJ DRAWN HE
ATTACHMENT D	



LEGEND	
	PROJECT LIMITS
	100 YEAR FLOODPLAIN
	STREAM
	SYMBOLS AND LINES
	POTENTIAL RECHARGE FEATURE
	CONTACT, LOCATED APPROXIMATELY
	CONTACT, INFERRED
	FAULT, LOCATED APPROXIMATELY (D, DOWNTHROWN SIDE; U, UP THROWN SIDE)
	FAULT, EXTRAPOLATED
	FAULT, INFERRED
	STRIKE AND DIP OF BEDDING
	STRIKE AND DIP OF JOINTS
	STRIKE OF VERTICAL JOINTS
	CAVE
	SOLUTION CAVITY
	Qal ALLUVIUM
	Kef EAGLE FORD
	Kbu BUDA
	Kdr DEL RIO
	Kgt GEORGETOWN
	Kep PERSON
	Kek KAINER
	Kgr GLEN ROSE
	S-1 SOLUTION ENLARGED FRACTURE
	S-2 SWALLOW HOLE
	S-3 SINKHOLE
	S-4 NON-KARST CLOSED DEPRESSION
	S-5 ZONE
	S-6 OTHER NATURAL BEDROCK FEATURES
	S-7 SPRING/SEEP
	S-8 MAN-MADE FEATURE IN BEDROCK
	S-9 WATER WELL
	S-10 SANITARY SEWER LINE



NO.	REVISION	DATE



PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TEPF FIRM REGISTRATION #470 | TEPF FIRM REGISTRATION #00351



NOTE: THE RECHARGE ZONE BOUNDARY IS NOT WITHIN THE AREA SHOWN ON THIS SHEET. THE SITE IS LOCATED ENTIRELY WITHIN THE RECHARGE ZONE.
 NOTE: ONLY THOSE GEOLOGIC FEATURES WITHIN THE AREA OF THIS ASSESSMENT ARE INCLUDED. THEREFORE, THE FEATURES MAY NOT BE NUMBERED SEQUENTIALLY.

BROOK STONE CREEK-PHASE 1 MOD
 SAN ANTONIO, TEXAS
 SITE GEOLOGIC MAP
 WATER POLLUTION ABATEMENT PLAN

JOB NO.	12093-00
DATE	MARCH 2020
DESIGNER	HS
CHECKED	HQJ DRAWN HE
ATTACHMENT D	

Plot: Job_06_2020_03_20.dwg User: ds_03/20/20 File: P:\2020\3\20\A\Design\Exhibits\MP\Map_C41209304.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE/UNLESS OTHERWISE NOTED. Imagery © 2016, CAROL/Digital Globe, Texas Orthology Program, USDA Farm Service Agency.

**MODIFICATION TO A
PREVIOUSLY APPROVED PLAN
(TCEQ-0590)**

Modification of a Previously Approved Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This request for a **Modification of a Previously Approved Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Becky Carroll, P.E.

Date: 5/18/2023

Signature of Customer/Agent:



Project Information

1. Current Regulated Entity Name: Brook Stone Phase I - Modification
Original Regulated Entity Name: Brook Stone Phase I
Regulated Entity Number(s) (RN): 111017802
Edwards Aquifer Protection Program ID Number(s): 113001111
 The applicant has not changed and the Customer Number (CN) is: 601213523
 The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
2. **Attachment A: Original Approval Letter and Approved Modification Letters.** A copy of the original approval letter and copies of any modification approval letters are attached.

3. A modification of a previously approved plan is requested for (check all that apply):
- Physical or operational modification of any water pollution abatement structure(s) including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
 - Change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
 - Development of land previously identified as undeveloped in the original water pollution abatement plan;
 - Physical modification of the approved organized sewage collection system;
 - Physical modification of the approved underground storage tank system;
 - Physical modification of the approved aboveground storage tank system.
4. Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

<i>WPAP Modification</i>	<i>Approved Project</i>	<i>Proposed Modification</i>
<i>Summary</i>		
Acres	<u>94.40</u>	<u>33.05</u>
Type of Development	<u>Single-Family Residential</u>	<u>Single-Family Residential</u>
Number of Residential Lots	<u>191</u>	<u>120</u>
Impervious Cover (acres)	<u>18.52</u>	<u>11.53</u>
Impervious Cover (%)	<u>19.6</u>	<u>34.90</u>
Permanent BMPs	<u>2 - Batch Detention Basins</u>	<u>1 - Batch Detention Basin</u>
Other	<u>7 - Natural VFS</u>	<u>1 - Eng VFS, 4 - Natural VFS</u>

<i>SCS Modification</i>	<i>Approved Project</i>	<i>Proposed Modification</i>
<i>Summary</i>		
Linear Feet	_____	_____
Pipe Diameter	_____	_____
Other	_____	_____

AST Modification	Approved Project	Proposed Modification
Summary		
Number of ASTs	_____	_____
Volume of ASTs	_____	_____
Other	_____	_____

UST Modification	Approved Project	Proposed Modification
Summary		
Number of USTs	_____	_____
Volume of USTs	_____	_____
Other	_____	_____

5. **Attachment B: Narrative of Proposed Modification.** A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved, including any previous modifications, and how this proposed modification will change the approved plan.

6. **Attachment C: Current Site Plan of the Approved Project.** A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.
 - The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.
 - The approved construction has commenced and has been completed. Attachment C illustrates that the site was **not** constructed as approved.
 - The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was constructed as approved.
 - The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was **not** constructed as approved.

7. The acreage of the approved plan has increased. A Geologic Assessment has been provided for the new acreage.
 - Acreage has not been added to or removed from the approved plan.

8. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A

Jon Niermann, *Chairman*
Emily Lindley, *Commissioner*
Bobby Janecka, *Commissioner*
Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

July 1, 2020

Mr. Leslie Ostrander
Continental Homes of Texas, LP
211 N Loop 1604 East, Ste. 130
San Antonio, Texas 78232

Re: Edwards Aquifer, Bexar County

NAME OF PROJECT: Brook Stone Phase I; Located south of Evans Rd. and Wortham Oaks intersection, Bexar County

TYPE OF PLAN: Request for an Approval of a Water Pollution Abatement Plan (WPAP); 30 Texas Administrative Code (TAC) Chapter 213 Subchapter B Edwards Aquifer

Regulated Entity No. RN111017802, Additional ID No. 13001111

Dear Mr. Ostrander:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the WPAP for the above-referenced project submitted to the San Antonio Regional Office by Pape-Dawson Engineers, Inc. on behalf of Continental Homes of Texas, LP on April 1, 2020. Final review of the WPAP modification was completed after additional material was received on June 5, 2020, June 18, 2020 and June 24, 2020. As presented to the TCEQ, the Temporary and Permanent Best Management Practices (BMPs) were selected and construction plans were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer Protection Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. *This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been requested.*

PROJECT DESCRIPTION

The project proposes a single-family residential development on 94.4 acres with 18.52 acres (19.6-percent) of impervious cover. The project proposes clearing, grading, excavation for installation of utilities, drainage improvements, and construction of 196 residential homes with

associated streets, access drives, and sidewalks. The project will be phased in two units (1A and 1B). Project wastewater will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by the San Antonio Water System (SAWS).

PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, two batch detention basins and seven natural vegetative filter strips, designed using the TCEQ technical guidance document, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices (2005), will treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 15,112 pounds of TSS generated from the 18.52 acres of impervious cover (IC). The approved measures meet the required 80 percent removal of the increased load in TSS caused by the project.

GEOLOGY

According to the geologic assessment included with the application, the project site is located within the leached and collapsed member of the Person formation. Two geologic sensitive features (S-3 and S-7), one sensitive manmade feature, and six non-sensitive geologic features were identified by the project geologist. A 0.33-acre buffer is proposed for sensitive feature S-3 and for sensitive feature S-7 a 0.78-acre buffer is proposed, both buffers are depicted on the application plan sheets and geologic assessment map. No regulated activities (such as construction or soil disturbing activities) will take place within the natural buffers. The size is generally based on the drainage area for each sensitive feature. The site assessment conducted on May 5, 2020 revealed that the site was generally as described in the application

SPECIAL CONDITIONS

- I. The permanent pollution abatement measures shall be operational prior to occupancy of the homes and streets within their respective drainage areas.
- II. All sediment and/or media removed from the batch detention basins during maintenance activities shall be properly disposed of according to 30 TAC 330 or 30 TAC 335, as applicable.

STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

Prior to Commencement of Construction:

4. Within 60 days of receiving written approval of an Edwards Aquifer Protection Plan, the applicant must submit to the San Antonio Regional Office, proof of recordation of notice in the county deed records, with the volume and page number(s) of the county deed records of the county in which the property is located. A description of the property boundaries shall be included in the deed recordation in the county deed records. A suggested form (Deed Recordation Affidavit, TCEQ-0625) that you may use to deed record the approved WPAP is enclosed.
5. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved WPAP and this notice of approval shall be maintained at the project location until all regulated activities are completed.
6. Modification to the activities described in the referenced WPAP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.
7. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person. The executive director will use the notification to determine if the approved plan is eligible for an extension.
8. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved WPAP, must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. If a water quality pond is proposed, it shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.
9. All borings with depths greater than or equal to 20 feet must be plugged with non-shrink grout from the bottom of the hole to within three (3) feet of the surface. The remainder of the hole must be backfilled with cuttings from the boring. All borings less than 20 feet must be backfilled with cuttings from the boring. All borings must be backfilled or plugged within four (4) days of completion of the drilling operation. Voids may be filled with gravel.

During Construction:

10. During the course of regulated activities related to this project, the applicant or agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
11. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 6, above.

12. If any sensitive feature (caves, solution cavities, sink holes, etc.) is discovered during construction, all regulated activities near the feature must be suspended immediately. The applicant or his agent must immediately notify the San Antonio Regional Office of the discovery of the feature. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality. The plan must be sealed, signed, and dated by a Texas Licensed Professional Engineer.
13. No wells exist on the site. All water wells, including injection, dewatering, and monitoring wells must be in compliance with the requirements of the Texas Department of Licensing and Regulation under Title 16 TAC Chapter 76 (relating to Water Well Drillers and Pump Installers) and all other locally applicable rules, as appropriate.
14. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
15. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge will be filtered through appropriately selected best management practices. These may include vegetated filter strips, sediment traps, rock berms, silt fence rings, etc.
16. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
17. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

18. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the San Antonio Regional Office within 30 days of site completion.
19. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. The regulated entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through San Antonio Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
20. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Edwards Aquifer protection plan. If the new owner intends to commence any new regulated activity on the site, a new Edwards Aquifer protection plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan

Mr. Leslie Ostrander

July 1, 2020

Page 5

for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.

21. An Edwards Aquifer protection plan approval or extension will expire, and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Edwards Aquifer protection plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
22. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Ms. Neri De La Garza of the Edwards Aquifer Protection Program of the San Antonio Regional Office at (210) 403-4087.

Sincerely,



Robert Sadlier, Section Manager
Edwards Aquifer Protection Program
Texas Commission on Environmental Quality

RCS/ndlg

Enclosure: Deed Recordation Affidavit, Form TCEQ-0625A
Change in Responsibility for Maintenance of Permanent BMPs, Form
TCEQ-10263

cc: Mr. Song Tan, P.E., Pape-Dawson Engineers, Inc.
Mr. Scott Halty, San Antonio Water System
Mr. Roland Ruiz, Edwards Aquifer Authority
Ms. Renee Green, P.E., Bexar County Public Works
Mr. George Wissmann, Trinity Glen Rose GW Conservation District

Deed Recordation Affidavit
Edwards Aquifer Protection Plan

THE STATE OF TEXAS §

County of Bexar §

BEFORE ME, the undersigned authority, on this day personally appeared Ruby Schwab who, being duly sworn by me, deposes and says:

- (1) That my name is Ruby Schwab and that I own the real property described below.
- (2) That said real property is subject to an EDWARDS AQUIFER PROTECTION PLAN which was required under the 30 Texas Administrative Code (TAC) Chapter 213.
- (3) That the EDWARDS AQUIFER PROTECTION PLAN for said real property was approved by the Texas Commission on Environmental Quality (TCEQ) on July 1st, 2020.

A copy of the letter of approval from the TCEQ is attached to this affidavit as Exhibit A and is incorporated herein by reference.

- (4) The said real property is located in Bexar County, Texas, and the legal description of the property is as follows: See Exhibit B, included herein.

LANDOWNER-AFFIANT

SWORN AND SUBSCRIBED TO before me, on this __ day of _____, _____.

NOTARY PUBLIC

THE STATE OF _____ §

County of _____ §

BEFORE ME, the undersigned authority, on this day personally appeared Leslie Ostrander known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this __ day of _____, _____.

NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: _____

**Change in Responsibility for Maintenance
on Permanent Best Management Practices and Measures**

The applicant is no longer responsible for maintaining the permanent best management practice (BMP) and other measures. The project information and the new entity responsible for maintenance is listed below.

Customer: _____

Regulated Entity Name: _____

Site Address: _____

City, Texas, Zip: _____

County: _____

Approval Letter Date: _____

BMPs for the project: _____

New Responsible Party: _____

Name of contact: _____

Mailing Address: _____

City, State: _____ Zip: _____

Telephone: _____ FAX: _____

Signature of New Responsible Party Date

I acknowledge and understand that I am assuming full responsibility for maintaining all permanent best management practices and measures approved by the TCEQ for the site, until another entity assumes such obligations in writing or ownership is transferred.

If you have questions on how to fill out this form or about the Edwards Aquifer protection program, please contact us at 210/490-3096 for projects located in the San Antonio Region or 512/339-2929 for projects located in the Austin Region.

Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at 512/239-3282.

ATTACHMENT B

BROOK STONE PHASE 1

Water Pollution Abatement Plan Application Modification

Attachment B – Narrative of Proposed Modification

Brook Stone Phase I - Modification Water Pollution Abatement Plan (WPAP) proposes the construction of a single-family residential development on approximately 33.05-acres identified as the Project Limits. The project site is located outside the city limits of San Antonio, but within its extra-territorial jurisdiction in Bexar County, Texas. The entire site is located over the Edwards Aquifer Recharge Zone. The project site is located south of Evans Rd. and Wortham Oaks intersection. The site is partially cleared and undeveloped, is bound by the 100-year floodplain to the west, and no naturally-occurring sensitive features were identified in the geologic assessment.

The previously approved WPAP consisted of approximately 18.52 acres of impervious cover, with a total project limits of 94.40 acres. The WPAP proposed clearing, grading, mass grading for soils, excavation for installation of utilities and drainage improvements, roads, construction of 196 single-family homes, and two (2) batch detention basins.

This WPAP modification proposes clearing, grading, mass grading for soils, excavation for installation of utilities and drainage improvements, construction of 120 single-family homes, roads, and one (1) batch detention basin. Home lots will have approximately 3,000 SF of impervious cover to include the housepad, driveway, and concrete patio. Approximately 11.53 acres of impervious cover, or 34.89% of the 33.05 acre project limits, are proposed for construction in this WPAP modification.

One (1) Batch Detention Basin "C", one (1) fifteen-foot (15') engineered Vegetative Filter Strips (VFS) , and four (4) fifty-foot (50') natural Vegetative Filter Strips (VFS) are proposed as the Permanent Best Management Practices (PBMPs) for the improvements proposed with this WPAP. All PBMPs have been designed in accordance with the TCEQ'S Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site. Uncaptured areas have been accounted in overtreatment within the proposed PBMPs.

The permanent population associated with Brook Stone Phase I - Modification is estimated to be 480 people, based on four (4) persons per lot. Potable water service is to be provided by the San Antonio Water System (SAWS). The proposed development will generate approximately 28,800 gallons per day (average flow) of domestic wastewater based on the assumption of 1 EDU per lot at 240 gpd/EDU. The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by the San Antonio Water System (SAWS). Potable water will be supplied by SAWS.

ATTACHMENT C


NO.	REVISION	DATE




Pape-Dawson Engineers
 SAN ANTONIO, TEXAS
 2020 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.225.0900
 TBP# FIRM REGISTRATION #720 | TBP#S FIRM REGISTRATION #1002800

BROOK STONE PHASE 1
 BEAR COUNTY, TEXAS
 PERMANENT POLLUTION ABATEMENT PLAN

PLAT NO. 20-1180007D
 JOB NO. 12093-00
 DATE FEBRUARY 2020
 DESIGNED ZJ
 CHECKED ZJ
 DRAWN ZJ
 SHEET 2 OF 2



- LEGEND:**
- BASIN WATERSHED BOUNDARY
 - VFS WATERSHED BOUNDARY
 - PROJECT LIMITS
 - EXISTING CONTOURS
 - EDWARDS AQUIFER RECHARGE ZONE
 - FLOW ARROW (PROPOSED)
 - FLOW ARROW (EXISTING)
 - VEGETATIVE FILTER STRIPS
 - AREAS COVERED BY SEPARATE C2P
 - UNCAPTURED IMPERVIOUS COVER



PERMANENT POLLUTION ABATEMENT MEASURES:


- PERMANENT BMP'S FOR THIS SITE INCLUDE TWO (2) BATCH DETENTION BASINS AND FIVE (5) 50' VEGETATIVE FILTER STRIPS. THESE PERMANENT MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE TCEQS TECHNICAL GUIDANCE MANUAL (TGM) PG-348 (2005).
- SILT FENCING AND ROCK BEAMS WHERE APPROPRIATE, WILL BE MAINTAINED THROUGHOUT CONSTRUCTION AND IMPROVEMENTS, AND BOUNDARY CONSTRUCTION ARE COMPLETED.
- ENERGY DISSIPATORS (TO HELP REDUCE EROSION) WILL BE PROVIDED AT EACH CONCENTRATED DISCHARGE WHERE EXCESSIVE VELOCITIES MAY BE ENCOUNTERED.

NOTES:

- CONTRACTOR SHALL INSTALL AND ESTABLISH VEGETATION FOR SOIL STABILIZATION PRIOR TO SITE CLOSURE.
- PERMANENT BMP'S MUST BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER.
- INDIVIDUAL LOTS VARY IN SIZE. VALUES PROVIDED ARE BASED ON TYPICAL LOT SIZES.

SUMMARY OF PERMANENT POLLUTION ABATEMENT MEASURES:


- TEMPORARY BMP'S WILL BE MAINTAINED UNTIL THE SITE IMPROVEMENTS ARE COMPLETED AND THE SITE HAS BEEN STABILIZED, INCLUDING SUFFICIENT VEGETATION BEING ESTABLISHED.
- MINIMIZE THE IMPACT OF SOIL DISTURBANCE. SOILS IN THE DISTURBED AREA SHALL BE REVEGETATED TO STABILIZE SOIL USING SOLID 500 IN A STAGGERED PATTERN. SOILS IN THE DISTURBED AREA SHALL BE REVEGETATED TO STABILIZE SOIL USING SOLID 500 IN A STAGGERED PATTERN. REFER TO SECTION 1.3.11 IN TCEQS TECHNICAL GUIDANCE MANUAL PG-48 (2005) FOR MORE INFORMATION. SOILS IN THE DISTURBED AREA SHALL BE REVEGETATED TO STABILIZE SOIL USING SOLID 500 IN A STAGGERED PATTERN. REFER TO SECTION 1.3.11 IN TCEQS TECHNICAL GUIDANCE MANUAL PG-48 (2005) FOR MORE INFORMATION. SOILS IN THE DISTURBED AREA SHALL BE REVEGETATED TO STABILIZE SOIL USING SOLID 500 IN A STAGGERED PATTERN. REFER TO SECTION 1.3.11 IN TCEQS TECHNICAL GUIDANCE MANUAL PG-48 (2005) FOR MORE INFORMATION.
- FOR DISTURBED AREAS WHERE INSUFFICIENT SOIL EXISTS TO ESTABLISH VEGETATION, CONTRACTOR SHALL PLACE A MINIMUM OF 6" OF TOPSOIL PRIOR TO REVEGETATION.
- TYPICAL SLOPES ON THIS PROJECT RANGE FROM APPROXIMATELY 1% TO 10%.



TYPICAL LOT DRAINAGE DETAIL FOR FHA TYPE C LOTS

NOTE: DRAINAGE PATTERN IS APPROXIMATE AND SUBJECT TO CHANGE. ROOF DRAINAGE SHALL BE INSTALLED AND DIRECTED TO THE DRIVEWAY, ROOF OR OTHER IMPERVIOUS SURFACES WITHIN THE LOT. DRAINAGE SHALL NOT BE DIRECTED TO THE VEGETATIVE FILTER STRIP. FINAL LOT DRAINAGE TO ALLOW FOR SHEET FLOW OVER VEGETATIVE FILTER STRIP.

Treatment Summary by Watershed	Total Watershed Area (Ac.)	Existing Impervious Cover (Ac.)	Proposed Impervious Cover (Ac.)	PMP Batch Detention Basin	Required TSS Removal (lbs)	TSS Removed Annually (lbs)
BA-A	13.26	0.00	6.56	"A"	5,353	5,697
BA-B	25.03	0.00	9.44	"B"	7,703	8,399
UNCAPTURED AREA A	0.29	0.07	0.22	Over treatment	380	0
UNCAPTURED AREA B	0.19	0.00	0.08	Over treatment	48	0
UNCAPTURED AREA C	0.38	0.00	0.12	Over treatment	58	0
UNCAPTURED AREA D	0.21	0.00	0.06	Over treatment	49	0
A	0.46	0.00	0.11	50' Natural VFS	90	102
B	0.64	0.00	0.22	50' Natural VFS	180	200
C	0.89	0.00	0.37	50' Natural VFS	302	334
D	1.08	0.00	0.47	50' Natural VFS	384	423
E	0.59	0.00	0.30	50' Natural VFS	245	269
F	0.77	0.00	0.31	50' Natural VFS	253	280
G	0.47	0.00	0.18	50' Natural VFS	147	163
TOTAL	44.21	0.07	18.82		15,112	15,837



THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT REQUIREMENTS OF THE TCEQS. THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED SHEETS IN THE CIVIL IMPROVEMENT PLAN SHALL BE REFERENCED TO THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLAN.

**WATER POLLUTION
ABATEMENT PLAN
APPLICATION FORM (TCEQ-
0584)**

Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Becky Carroll, P.E.

Date: 5/18/2023

Signature of Customer/Agent:



Regulated Entity Name: Brook Stone Phase I - Modification

Regulated Entity Information

1. The type of project is:

- Residential: Number of Lots: 120
- Residential: Number of Living Unit Equivalents: _____
- Commercial
- Industrial
- Other: _____

2. Total site acreage (size of property): 33.05

3. Estimated projected population: 4 persons/ home x 120 homes = 480

4. The amount and type of impervious cover expected after construction are shown below:

Table 1 - Impervious Cover Table

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	360,000.00	÷ 43,560 =	8.26
Parking	12,000.00	÷ 43,560 =	0.28
Other paved surfaces	130,379.98	÷ 43,560 =	2.99
Total Impervious Cover	502,379.98	÷ 43,560 =	11.53

Total Impervious Cover 11.53 ÷ Total Acreage 33.05 X 100 = 34.90% Impervious Cover

5. **Attachment A - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
6. Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

7. Type of project:

- TXDOT road project.
- County road or roads built to county specifications.
- City thoroughfare or roads to be dedicated to a municipality.
- Street or road providing access to private driveways.

8. Type of pavement or road surface to be used:

- Concrete
- Asphaltic concrete pavement
- Other: _____

9. Length of Right of Way (R.O.W.): _____ feet.

Width of R.O.W.: _____ feet.

L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.

10. Length of pavement area: _____ feet.

Width of pavement area: _____ feet.

L x W = _____ Ft² ÷ 43,560 Ft²/Acre = _____ acres.

Pavement area _____ acres ÷ R.O.W. area _____ acres x 100 = _____% impervious cover.

11. A rest stop will be included in this project.
- A rest stop will not be included in this project.

12. Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

13. **Attachment B - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

14. The character and volume of wastewater is shown below:

<u>100%</u> Domestic	_____ Gallons/day
_____ % Industrial	_____ Gallons/day
_____ % Commingled	_____ Gallons/day
TOTAL gallons/day <u>120 lots x 1 EDU/lot x 240 gpd/edu = 28,800 gpd (average)</u>	

15. Wastewater will be disposed of by:

On-Site Sewage Facility (OSSF/Septic Tank):

Attachment C - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

Sewage Collection System (Sewer Lines):

Private service laterals from the wastewater generating facilities will be connected to an existing SCS.

Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.

The SCS was previously submitted on 09/14/2021.

The SCS was submitted with this application.

The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

The sewage collection system will convey the wastewater to the Steven M. Clouse (name) Treatment Plant. The treatment facility is:

Existing.

Proposed.

16. All private service laterals will be inspected as required in 30 TAC §213.5.

Site Plan Requirements

Items 17 – 28 must be included on the Site Plan.

17. The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 200'.

18. 100-year floodplain boundaries:

Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.

No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): DFIRM (Digital Flood Insurance Rate Map for Bexar County, Texas and Incorporated Areas) Panel No. 48029C0145G, Dated 9/29/2021

19. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.

The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.

20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)

The wells are not in use and have been properly abandoned.

The wells are not in use and will be properly abandoned.

The wells are in use and comply with 16 TAC §76.

There are no wells or test holes of any kind known to exist on the project site.

21. Geologic or manmade features which are on the site:

All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.

No sensitive geologic or manmade features were identified in the Geologic Assessment.

- Attachment D - Exception to the Required Geologic Assessment.** A request and justification for an exception to a portion of the Geologic Assessment is attached.
22. The drainage patterns and approximate slopes anticipated after major grading activities.
23. Areas of soil disturbance and areas which will not be disturbed.
24. Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
25. Locations where soil stabilization practices are expected to occur.
26. Surface waters (including wetlands).
 N/A
27. Locations where stormwater discharges to surface water or sensitive features are to occur.
 There will be no discharges to surface water or sensitive features.
28. Legal boundaries of the site are shown.

Administrative Information

29. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
30. Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

ATTACHMENT A

BROOK STONE PHASE 1 - MODIFICATION

Water Pollution Abatement Application (TCEQ-0584)

Attachment A – Factors Affecting Water Quality

Potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the site during construction include:

- *Soil erosion due to the clearing of the site;*
- *Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle drippings;*
- *Hydrocarbons from asphalt paving operations;*
- *Miscellaneous trash and litter from construction workers and material wrappings;*
- *Concrete truck washout.*
- *Potential overflow/spills from portable toilets*

Potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the site after development include:

- *Oil, grease, fuel and hydraulic fluid contamination from vehicle drippings;*
- *Dirt and dust which may fall off vehicles; and*
- *Miscellaneous trash and litter.*

ATTACHMENT B

BROOK STONE PHASE 1

Water Pollution Abatement Plan Application Modification

Attachment B – Volume and Character of Stormwater

Stormwater runoff will increase as a result of this development. For a 25-year storm event, the overall project will generate approximately 134.8 cfs. The runoff coefficient for the site changes from approximately 0.49 before development to 0.69 after development. Values are based on the Rational Method using runoff coefficients per the City of San Antonio Unified Development Code.

**TEMPORARY STORMWATER
SECTION (TCEQ-0602)**

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Becky Carroll, P.E.

Date: 5/18/2023

Signature of Customer/Agent:



Regulated Entity Name: Brook Stone Phase I - Modification

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: Construction Staging Area

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
- 2. **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

- 5. **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Elm Waterhole Creek

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

- 7. **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
 - A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
 - A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
 - A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
 - There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

11. **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.

N/A

12. **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A

BROOK STONE PHASE 1

Water Pollution Abatement Plan Application Modification

Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

- The contractor will be required to report significant or hazardous spills in reportable quantities to:
 - the National Response Center at (800) 424-8802
 - the Edwards Aquifer Authority at (210) 222-2204
 - the TCEQ Regional Office (210) 490-3096 (if during business hours: 8 AM to 5 PM) or
 - the State Emergency Response Center (800) 832-8224 (if after hours)
- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

BROOK STONE PHASE 1

Water Pollution Abatement Plan Application Modification

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

ATTACHMENT B

BROOK STONE PHASE I - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment B – Potential Sources of Contamination

Other potential sources of contamination during construction include:

- | | | |
|----------------------|---|--|
| Potential Source | ● | Asphalt products used on this project. |
| Preventative Measure | ■ | After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain. |
| Potential Source | ● | Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping. |
| Preventative Measure | ■ | Vehicle maintenance when possible will be performed within the construction staging area. |
| | ■ | Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately. |
| Potential Source | ● | Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site. |
| Preventative Measure | ■ | Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures. |
| | ■ | Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures. |
| | ■ | Hazardous materials and wastes shall be stored in covered containers and protected from vandalism. |
| | ■ | A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible. |
| Potential Source | ● | Miscellaneous trash and litter from construction workers and material wrappings. |
| Preventive Measure | ■ | Trash containers will be placed throughout the site to encourage proper trash disposal. |
| Potential Source | ● | Construction debris. |
| Preventive Measure | ■ | Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring |

BROOK STONE PHASE I - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Potential Source
Preventative Measure

- immediate attention will be addressed on a case by case basis.
- Spills/Overflow of waste from portable toilets
- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

ATTACHMENT C

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment C – Sequence of Major Activities

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include clearing and grubbing of vegetation where applicable. This will disturb approximately 25 acres. The second is construction that will include construction of streets, utilities, drainage improvements, batch detention basins homes, construction of new pavement area, landscaping and site cleanup. This will disturb approximately 20 acres. Home construction will be based on market demand and may not be concurrent with infrastructure developments.

ATTACHMENT D

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment D – Temporary Best Management Practices and Measures

A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

Due to site topography, upgradient water will cross the site from the previously approved WPAP project limits northeast of the WPAP modification project limits. All TBMPs are adequate for the drainage areas they serve.

- b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

- c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

There are no naturally-occurring sensitive geological features identified in the Geologic Assessment for the WPAP modification project limits and no surface streams on or adjacent to the project limits. All temporary BMPs utilized are adequate for the drainage areas served.

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

- d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.

ATTACHMENT F

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment F – Structural Practices

The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 1 and illustrated in Exhibit 2.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 1, and illustrated on Exhibit 2.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

- Installation of concrete truck washout pit(s), as required and located on Exhibit 1 and illustrated on Exhibit 2.

ATTACHMENT G

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment G – Drainage Area Map

More than ten (10) acres will be disturbed within a common drainage area at one time therefore the proposed batch detention basins will be used as temporary sediment ponds until 70% stabilization is achieved at which time they will be converted to the intended batch detention ponds. Other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area. All TBMPs utilized are adequate for the drainage areas served.

ATTACHMENT H

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment H – Temporary Sedimentation Pond(s) Plans and Calculations

The proposed batch detention basins will be used as temporary sediment traps during site construction for each respective watershed. The basins will be converted to permanent basins after 70% of the pavement areas in each watershed have been paved. Other TBPMs and measures will be used in combination to protect downslope and side slope boundaries of the construction area including natural vegetative filter strips, silt fence, rock berms, etc.

Prior to final acceptance by the owner, the contractor will remove trash, debris and accumulated silt from each sedimentation/filtration basin and re-establish them to proper operating condition.

Basin C

Approximately 3.56 acres disturbed x 13,794 cf/acre disturbed = 49,107 cf

Volume of proposed basins exceeds requirement.

ATTACHMENT I

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment I - Inspections

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.

BROOK STONE PHASE 1 - MODIFICATION
Temporary Stormwater Section (TCEQ-0602)

Pollution Prevention Measure	Inspected in Compliance	Corrective Action Required	
		Description (use additional sheet if necessary)	Date Completed
Best Management Practices			
Natural vegetation buffer strips			
Temporary vegetation			
Permanent vegetation			
Sediment control basin			
Silt fences			
Rock berms			
Gravel filter bags			
Drain inlet protection			
Other structural controls			
Vehicle exits (off-site tracking)			
Material storage areas (leakage)			
Equipment areas (leaks, spills)			
Concrete washout pit (leaks, failure)			
General site cleanliness			
Trash receptacles			
Evidence of Erosion			
Site preparation			
Roadway or parking lot construction			
Utility construction			
Drainage construction			
Building construction			
Major Observations			
Sediment discharges from site			
BMPs requiring maintenance			
BMPs requiring modification			
Additional BMPs required			

_____ **A brief statement describing the qualifications of the inspector is included in this SWP3.**

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

"I further certify I am an authorized signatory in accordance with the provisions of 30 TAC §305.128."

Inspector's Name

Inspector's Signature

Date

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

PROJECT MILESTONE DATES

Date when major site grading activities begin:

<u>Construction Activity</u>	<u>Date</u>
Installation of BMPs	
_____	_____
_____	_____
_____	_____
_____	_____

Dates when construction activities temporarily or permanently cease on all or a portion of the project:

<u>Construction Activity</u>	<u>Date</u>
_____	_____
_____	_____
_____	_____
_____	_____

Dates when stabilization measures are initiated:

<u>Stabilization Activity</u>	<u>Date</u>
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
Removal of BMPs	_____

ATTACHMENT J

BROOK STONE PHASE 1 - MODIFICATION

Temporary Stormwater Section (TCEQ-0602)

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.

**PERMANENT STORMWATER
SECTION (TCEQ-0600)**

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(li), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Becky Carroll, P.E.

Date: 5/18/2023

Signature of Customer/Agent



Regulated Entity Name: Brook Stone Phase I - Modification

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

- Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.
 N/A
- These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.
 The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____

N/A

3. Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

N/A

4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

The site will be used for low density single-family residential development and has 20% or less impervious cover.

The site will be used for low density single-family residential development but has more than 20% impervious cover.

The site will not be used for low density single-family residential development.

5. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

Attachment A - 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.

The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.

The site will not be used for multi-family residential developments, schools, or small business sites.

6. **Attachment B - BMPs for Upgradient Stormwater.**

- A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
 - No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
 - Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.
7. **Attachment C - BMPs for On-site Stormwater.**
- A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
 - Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
8. **Attachment D - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.
- N/A
9. The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.
- The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.
 - Attachment E - Request to Seal Features.** A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
10. **Attachment F - Construction Plans.** All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
- Design calculations (TSS removal calculations)
 - TCEQ construction notes
 - All geologic features
 - All proposed structural BMP(s) plans and specifications
- N/A

11. **Attachment G - Inspection, Maintenance, Repair and Retrofit Plan.** A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:
- Prepared and certified by the engineer designing the permanent BMPs and measures
 - Signed by the owner or responsible party
 - Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
 - A discussion of record keeping procedures
- N/A
12. **Attachment H - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.
- N/A
13. **Attachment I -Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.
- N/A

Responsibility for Maintenance of Permanent BMP(s)

Responsibility for maintenance of best management practices and measures after construction is complete.

14. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
- N/A
15. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.
- N/A

ATTACHMENT B

BROOK STONE PHASE I - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

Attachment B – BMPs for Upgradient Stormwater

Due to site topography, upgradient stormwater within the FEMA 100-year floodplain drains through the site to the west of the proposed development. No development is proposed within the floodplain limits. Upstream runoff from the Brook Stone Phase I WPAP project limits flows onto the site and will be treated with Existing Batch Detention Basin "B".

One (1) Batch Detention Basin ("C"), Four (4) fifty-foot (50') natural vegetative filter strips (VFS) (VFS "1", "3", "4", "5"), and One (1) fifteen-foot (15') engineered VFS (VFS "2") are proposed as the Permanent Best Management Practices (PBMPs) for the improvements proposed with this WPAP Modification. All PBMPs have been designed in accordance with the TCEQ'S Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site. Uncaptured areas have been accounted in overtreatment within the proposed PBMPs.

ATTACHMENT C

BROOK STONE PHASE I - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

Attachment C – BMPs for On-Site Stormwater

One (1) Batch Detention Basin (“C”), Four (4) fifty-foot (50’) natural vegetative filter strips (VFS) (VFS “1”, “3”, “4”, “5”), and One (1) fifteen-foot (15’) engineered VFS (VFS “2”) are proposed as the Permanent Best Management Practices (PBMPs) for the improvements proposed with this WPAP Modification. All PBMPs have been designed in accordance with the TCEQ’S Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site. Uncaptured areas have been accounted in overtreatment within the proposed PBMPs.

ATTACHMENT D

BROOK STONE PHASE 1 - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

Attachment D – BMPs for Surface Streams

There are no naturally-occurring sensitive geological features identified in the Geologic Assessment on the site and no surface streams on or adjacent to the project limits. BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.

One (1) Batch Detention Basin (“C”), Four (4) fifty-foot (50’) natural vegetative filter strips (VFS) (VFS “1”, “3”, “4”, “5”), and One (1) fifteen-foot (15’) engineered VFS (VFS “2”) are proposed as the Permanent Best Management Practices (PBMPs) for the improvements proposed with this WPAP Modification. All PBMPs have been designed in accordance with the TCEQ’S Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site. Uncaptured areas have been accounted in overtreatment within the proposed PBMPs.

ATTACHMENT F

BROOK STONE PHASE I - MODIFICATION

Water Pollution Abatement Plan

Attachment F – Construction Plans

Please refer to the Exhibits section of this application for the Water Pollution Abatement Site Plans and Batch Detention Basin Plan.

ATTACHMENT G

BROOK STONE PHASE 1 - MODIFICATION
Permanent Stormwater Section (TCEQ-0600)

PERMANENT POLLUTION ABATEMENT MEASURES
MAINTENANCE SCHEDULE AND MAINTENANCE PROCEDURES

This document has been prepared to provide a description and schedule for the performance of maintenance on permanent pollution abatement measures. Maintenance measures to be performed will be dependent on what permanent pollution abatement measures are incorporated into the project. The project specific water pollution abatement plan should be reviewed to determine what permanent pollution abatement measures are incorporated into a project.

It should also be noted that the timing and procedures presented herein are general guidelines, adjustment to the timing and procedures may have to be made depending on project specific characteristics as well as weather related conditions but may not be altered without TCEQ approval.

Where a project is occupied by the owner, the owner may provide for maintenance with his own skilled forces or contract for recommended maintenance of Permanent Best Management Practices. Where a project is occupied or leased by a tenant, the owner shall require tenants to contract for such maintenance services either through a lease agreement, property owner's association covenants, or other binding document.

I understand that I am responsible for maintenance of the Permanent Pollution Abatement Measures included in this project until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or ownership is transferred.

I, the owner, have read and understand the requirements of the attached Maintenance Plan and Schedule.



Leslie Ostrander
Continental Homes of Texas, L.P.



Date

BROOK STONE PHASE 1 - MODIFICATION
Permanent Stormwater Section (TCEQ-0600)

**INSPECTION AND MAINTENANCE SCHEDULE
 FOR
 PERMANENT POLLUTION ABATEMENT MEASURES**

Recommended Frequency	Task to be Performed												
	1	2	3	4	5	6	7	8	9	10	11	12	13
After Rainfall	√							√			√		√
Biannually*	√	√	√	√	√	√	√	√	√	√	√	√	√

**At least one biannual inspection must occur during or immediately after a rainfall event.
 √Indicates maintenance procedure that applies to this specific site.*

See description of maintenance task to be performed on the following pages. Frequency of maintenance tasks may vary depending on amount of rainfall and other weather related conditions but may not be altered without TCEQ approval.

A written record should be kept of inspection results and maintenance performed.

<i>Task No. & Description</i>	<i>Included in this project</i>	
1. Mowing	Yes	No
2. Litter and Debris Removal	Yes	No
3. Erosion Control	Yes	No
4. Level Sensor	Yes	No
5. Nuisance Control	Yes	No
6. Structural Repairs and Replacement	Yes	No
7. Discharge Pipe	Yes	No
8. Detention and Drawdown Time	Yes	No
9. Sediment Removal	Yes	No
10. Logic Controller	Yes	No
11. Vegetated Filter Strips	Yes	No
12. Visually Inspect Security Fencing for Damage or Breach	Yes	No
13. Recordkeeping for Inspections, Maintenance, and Repairs	Yes	No

BROOK STONE PHASE 1 - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

MAINTENANCE PROCEDURES FOR PERMANENT POLLUTION ABATEMENT MEASURES

Note: Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 3.5.

Inspections. Inspections should take place a minimum of twice a year. One inspection should take place during wet weather to determine if the basin is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. The remaining inspections should occur between storm events so that manual operation of the valve and controller can be verified. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. The outlet structure and the trash screen should be inspected for signs of clogging. Debris and sediment should be removed from the orifice and outlet(s) as described in previous sections. Debris obstructing the valve should be removed. During each inspection, erosion areas inside and downstream of this BMP should be identified and repaired/revegetated immediately. *A written record should be kept of inspection results and corrective measures taken*

1. Mowing. The basin, basin side-slopes, and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas.
2. Litter and Debris Removal. Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for possible clogging or obstructions and any debris removed.
3. Erosion control. The basin side slopes and embankment all may periodically suffer from slumping and erosion. To correct these problems, corrective action, such as regrading and revegetation, may be necessary. Correction of erosion control should take place whenever required based on the periodic inspections.
4. Level Sensor. The level sensor in the basin should be inspected and any debris or sediment in the area should be removed. Litter and debris removal should take place at least twice a year, as part of the periodic mowing operations and inspections. Debris and litter should be removed from the surface of the basin.
5. Nuisance Control. Standing water or soggy conditions may occur in the basin. Some standing water may occur after a storm event since the valve may close with 2 to 3 inches of water in the basin. Some flow into the basin may also occur between storms due to spring flow and residential water use that enters the storm sewer system. Twice a year, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.).

BROOK STONE PHASE 1 - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

6. Structural Repairs and Replacement. With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, retaining walls, etc.) should be identified and repaired immediately. An example of this type of repair can include patching of cracked concrete, sealing of voids, removal of vegetation from cracks and joints. The various inlet/outlet structures in a basin will eventually deteriorate and must be replaced. *A written record should be kept of inspection results and corrective measures taken*
7. Discharge Pipe. The basin discharge pipe shall be checked for accumulation of silt, debris or other obstructions which could block flow. Soil accumulations, vegetative overgrowth and other blockages should be cleared from the pipe discharge point. Erosion at the point of discharge shall be monitored. If erosion occurs, the addition of rock rubble to disperse the flow should be accomplished. *A written record should be kept of inspection results and corrective measures taken*
8. Detention and Drawdown Time. One inspection should take place during wet weather to determine if the basin is meeting the target detention time of 12 hours and a drawdown time of no more than 48 hours. This characteristic can be a sign of the need for maintenance. The minimum drawdown time is 24 hours. If drawdown time is less than 24 hours, the actuator valve shall be checked and partially closed to limit the drawdown time. Extensive drawdown time greater than 48 hours may indicate blockage of the discharge pipe. Corrective actions should be performed and completed within 15 working days. *A written record of the inspection findings and corrective actions performed should be made.*
9. Sediment Removal. A properly designed batch detention basin will accumulate quantities of sediment over time. The accumulated sediment can detract from the appearance of the facility and reduce the pollutant removal performance of the facility. The sediment also tends to accumulate near the outlet structure and can interfere with the level sensor operation. Sediment shall be removed from the basin at least every 5 years, when sediment depth exceeds 6 inches, when the sediment interferes with the level sensor or when the basin does not drain within 48 hours. Care should be taken not to compromise the basin lining during maintenance.
10. Logic Controller. The Logic Controller should be inspected as part of the twice yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris. The solar panel should be inspected and any dust or debris on the panel should be carefully removed. The controller and all other circuitry and wiring should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. At the end of the inspection, the controller should be reset.
11. Vegetated Filter Strips. Vegetation height for native grasses shall be limited to no more than 18-inches. When vegetation exceeds that height, the filter strip shall be cut to a height of approximately 4 inches. Turf grass shall be limited to a height of 4-inches with regular maintenance that utilizes a mulching mower. Trash and debris shall be removed from filter strip prior to cutting. Check filter strip for signs of concentrated flow and erosion. Areas of filter strip showing signs of

BROOK STONE PHASE 1 - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

erosion shall be repaired by scarifying the eroded area, reshaping, regrading and placement of solid block sod over the affected area. *A written record of the inspection findings and corrective actions performed should be made*

12. Visually Inspect Security Fencing for Damage or Breach. Check maintenance access gates for proper operation. Damage to fencing or gates shall be repaired within 5 working days. *A written record should be kept of inspection results and maintenance performed.*
13. Recordkeeping Procedures for Inspections, Maintenance, Repairs, and Retrofits.
 - Written records shall be kept by the party responsible for maintenance or a designated representative.
 - Written records shall be retained for a minimum of five years.

ATTACHMENT I

BROOK STONE PHASE 1 - MODIFICATION

Permanent Stormwater Section (TCEQ-0600)

Attachment I – Measures for Minimizing Surface Stream Contamination

Any points where discharge from the site is concentrated and erosive velocities exist will include appropriately sized energy dissipators to reduce velocities to non-erosive levels.

**AGENT AUTHORIZATION FORM
(TCEQ-0599)**

Agent Authorization Form
For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I _____, Leslie Ostrander,
Print Name

_____ ,
Assistant Secretary
Title - Owner/President/Other

of _____, Continental Homes of Texas, L.P.,
Corporation/Partnership/Entity Name

have authorized _____, Pape-Dawson Engineers, Inc.,
Print Name of Agent/Engineer

of _____, Pape-Dawson Engineers, Inc.,
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Leslie Ortegón
Applicant's Signature


1/16/2023
Date

THE STATE OF Texas §

County of Brewer §

BEFORE ME, the undersigned authority, on this day personally appeared Leslie Ortegón known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 16 day of January, 2023



Robert Ortegón, Jr.
NOTARY PUBLIC
Robert Ortegón, Jr.
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 4-9-23

Owner Authorization Form

Texas Commission on Environmental Quality
for Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

Land Owner Authorization

I, Israel Fogiel of 114 Schwab Investments, Ltd.
Land Owner Signatory Name Land Owner Name (Legal Entity or Individual)

am the owner of the property located at
135.30-acre tract of land (Document # 20200307732)

Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

to conduct Site preparation, clearing, grading, utility installation, excavation (SCS), construction (streets, drains)
Description of the proposed regulated activities

at 4980 Evans Road, Bexar County, TX 79261
Precise location of the authorized regulated activities

Land Owner Acknowledgement

I understand that 114 Schwab Investments, Ltd.
Land Owner Name (Legal Entity or Individual)

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Land Owner Signature

[Signature]
Land Owner Signature

2/2/21
Date

THE STATE OF § TEXAS

County of § BEXAR

BEFORE ME, the undersigned authority, on this day personally appeared Israel Fogiel known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 12th day of February, 2021

[Signature]
NOTARY PUBLIC



Marian G. Adams
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 8/5/24

Attached: (Mark all that apply)

- Lease Agreement
- Signed Contract
- Deed Recorded Easement
- Other legally binding document

Applicant Acknowledgement

I, Leslie Ostrander of Continental Homes of Texas, LP
Applicant Signatory Name Applicant Name (Legal Entity or Individual)
acknowledge that 114 Schwab Investments, Ltd.

Land Owner Name (Legal Entity or Individual)
has provided Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

with the right to possess and control the property referenced in the Edwards Aquifer protection plan.
I understand that Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

is contractually responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation. I further understand that failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.


Applicant Signature

Leslie Ostrander 2/15/2021
Applicant Signature Date

THE STATE OF § TEXAS
County of § BEXAR

BEFORE ME, the undersigned authority, on this day personally appeared LESLIE OSTRANDER known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 15 day of FEBRUARY
RS



ROBERT E SWANN
NOTARY PUBLIC
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 7/26/2021

Owner Authorization Form

Texas Commission on Environmental Quality
for Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

Land Owner Authorization

I, Israel Fogiel of 114 Schwab Investments, Ltd.
Land Owner Signatory Name Land Owner Name (Legal Entity or Individual)

am the owner of the property located at
135.30-acre tract of land (Document # 20200307732)

Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

to conduct Site preparation, clearing, grading, utility installation, excavation (SCS), construction (streets, drains)

Description of the proposed regulated activities

at 4980 Evans Road, Bexar County, TX 79261
Precise location of the authorized regulated activities

Land Owner Acknowledgement

I understand that 114 Schwab Investments, Ltd.
Land Owner Name (Legal Entity or Individual)

is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Land Owner Signature

[Signature]
Land Owner Signature

2/12/21
Date

THE STATE OF § TEXAS

County of § BEXAR

BEFORE ME, the undersigned authority, on this day personally appeared Israel Fogiel known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 12th day of February, 20201

[Signature]
NOTARY PUBLIC

Marian G. Adams
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 8/5/24



Attached: (Mark all that apply)

- Lease Agreement
- Signed Contract
- Deed Recorded Easement
- Other legally binding document

Applicant Acknowledgement

I, Leslie Ostrander of Continental Homes of Texas, LP
Applicant Signatory Name Applicant Name (Legal Entity or Individual)

acknowledge that 114 Schwab Investments, Ltd.
Land Owner Name (Legal Entity or Individual)

has provided Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

with the right to possess and control the property referenced in the Edwards Aquifer protection plan.

I understand that Continental Homes of Texas, LP
Applicant Name (Legal Entity or Individual)

is contractually responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation. I further understand that failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Applicant Signature

Leslie Ostrander
Applicant Signature


2/15/2021
Date

THE STATE OF § TEXAS

County of § BEXAR

BEFORE ME, the undersigned authority, on this day personally appeared LESLIE OSTRANDER known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 15 day of FEBRUARY



[Signature]

NOTARY PUBLIC

ROBERT E SWANN

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 7/26/2021

**APPLICATION FEE FORM
(TCEQ-0574)**

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Brook Stone Phase I - Modification

Regulated Entity Location: South of Evans Road and Wortham Oaks

Name of Customer: Continental Homes of Texas, L.P.

Contact Person: Leslie Ostrander

Phone: (210) 496-2668

Customer Reference Number (if issued): CN 601213523

Regulated Entity Reference Number (if issued): RN 111017802

Austin Regional Office (3373)

Hays

Travis

Williamson

San Antonio Regional Office (3362)

Bexar

Medina

Uvalde

Comal

Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

Austin Regional Office

San Antonio Regional Office

Mailed to: TCEQ - Cashier

Overnight Delivery to: TCEQ - Cashier

Revenues Section

12100 Park 35 Circle

Mail Code 214

Building A, 3rd Floor

P.O. Box 13088

Austin, TX 78753

Austin, TX 78711-3088

(512)239-0357

Site Location (Check All That Apply):

Recharge Zone

Contributing Zone

Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	33.05 Acres	\$ 4,00.00
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Leslie Ostrander

Date: 1/16/2003

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

<i>Project</i>	<i>Project Area in Acres</i>	<i>Fee</i>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

<i>Project</i>	<i>Cost per Linear Foot</i>	<i>Minimum Fee- Maximum Fee</i>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

<i>Project</i>	<i>Cost per Tank or Piping System</i>	<i>Minimum Fee- Maximum Fee</i>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

<i>Project</i>	<i>Fee</i>
Exception Request	\$500

Extension of Time Requests

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150

**CORE DATA FORM
(TCEQ-10400)**



TCEQ Use Only

TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 601213523		RN 111017802

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)	
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)		<input type="checkbox"/> Change in Regulated Entity Ownership	
The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).			
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)		If new Customer, enter previous Customer below:	
Continental Homes of Texas, L.P.			
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number (if applicable)
		74-2791904	
11. Type of Customer:	<input type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other	<input type="checkbox"/> Sole Proprietorship	<input type="checkbox"/> Other:	
12. Number of Employees		13. Independently Owned and Operated?	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following:			
<input type="checkbox"/> Owner		<input type="checkbox"/> Operator	
<input type="checkbox"/> Occupational Licensee		<input checked="" type="checkbox"/> Owner & Operator	
<input type="checkbox"/> Responsible Party		<input type="checkbox"/> Voluntary Cleanup Applicant	
<input type="checkbox"/> Other:			
15. Mailing Address:	5419 North Loop 1604 East		
	City	San Antonio	State
	Texas	ZIP	78247
	ZIP + 4		
16. Country Mailing Information (if outside USA)		17. E-Mail Address (if applicable)	
18. Telephone Number		19. Extension or Code	
()			
		20. Fax Number (if applicable)	
		()	

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)	
<input type="checkbox"/> New Regulated Entity <input checked="" type="checkbox"/> Update to Regulated Entity Name <input type="checkbox"/> Update to Regulated Entity Information	
The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC.)	
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)	
Brook Stone Phase 1 Modification	

23. Street Address of the Regulated Entity: <i>(No PO Boxes)</i>	N/A							
	City		State		ZIP		ZIP + 4	
24. County								
Enter Physical Location Description if no street address is provided.								
25. Description to Physical Location:	0.48 miles southwest of Evans Road and Wortham Oaks intersection							
26. Nearest City	San Antonio			State	Texas		Nearest ZIP Code	78266
27. Latitude (N) In Decimal:	29.637873		28. Longitude (W) In Decimal:	-98.383530				
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds			
29	38	34	-98	23	01			
29. Primary SIC Code (4 digits)	30. Secondary SIC Code (4 digits)	31. Primary NAICS Code (5 or 6 digits)	32. Secondary NAICS Code (5 or 6 digits)					
1521	1623	23115	237110					
33. What is the Primary Business of this entity? <i>(Do not repeat the SIC or NAICS description.)</i>								
One phase of a single-family residential subdivision								
34. Mailing Address:	5419 North Loop 1604 East							
	City	San Antonio	State	Texas	ZIP	78247	ZIP + 4	
35. E-Mail Address:	LKOstrander@drhorton.com							
36. Telephone Number	37. Extension or Code	38. Fax Number <i>(if applicable)</i>						
(210) 496-2668		() -						

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name:	Seth Sepulveda	41. Title:	Engineer
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(210) 375-9000		(210) 375-9010	ssepulveda@pape-dawson.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Pape-Dawson Engineers, Inc.	Job Title:	Vice President
Name <i>(In Print)</i> :	Becky Carroll, P.E.	Phone:	(210) 375-9000
Signature:		Date:	5/18/2023

POLLUTANT LOAD AND REMOVAL CALCULATIONS

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: L_M TOTAL PROJECT = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project
 County = **Bexar**
 Total project area included in plan = **33.05** acres
 Predevelopment impervious area within the limits of the plan = **0.00** acres
 Total post-development impervious area within the limits of the plan = **11.53** acres
 Total post-development impervious cover fraction = **0.35**
 P = **30** inches

L_M TOTAL PROJECT = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin)

Drainage Basin/Outfall Area No. = **EX BATCH B**

Total drainage basin/outfall area = **27.67** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **14.66** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.53**
 L_M THIS BASIN = **11963** lbs.

3. Indicate the proposed BMP Code for this basin

Proposed BMP = **Extended Detention**
 Removal efficiency = **91** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **27.67** acres
 A_i = **14.66** acres
 A_p = **13.01** acres
 L_R = **14039** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall are

Desired L_M THIS BASIN = **12003** lbs.

F = **0.85**

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall are:

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = **1.32** inches
 Post Development Runoff Coefficient = **0.37**
 On-site Water Quality Volume = **49651** cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = **0.00** acres
 Off-site Impervious cover draining to BMP = **0.00** acres
 Impervious fraction of off-site area = **0**
 Off-site Runoff Coefficient = **0.00**
 Off-site Water Quality Volume = **0** cubic feet

Storage for Sediment = **9930**
 Total Capture Volume (required water quality volume(s) x 1.20) = **59581** cubic feet



Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where:

L_M TOTAL PROJECT = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan = **33.05** acres
 Predevelopment impervious area within the limits of the plan = **0.00** acres
 Total post-development impervious area within the limits of the plan = **11.53** acres
 Total post-development impervious cover fraction = **0.35**
 P = **30** inches

L_M TOTAL PROJECT = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin)

Drainage Basin/Outfall Area No. = **BATCH C**

Total drainage basin/outfall area = **3.56** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **2.39** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.67**
 L_M THIS BASIN = **1950** lbs.

3. Indicate the proposed BMP Code for this basin

Proposed BMP = **Extended Detention**
 Removal efficiency = **91** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault



4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where:

A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **3.56** acres
 A_i = **2.39** acres
 A_p = **1.17** acres
 L_R = **2275** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired L_M THIS BASIN = **1950** lbs.

F = **0.86**

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area:

Calculations from RG-348

Pages 3-34 to 3-36

Rainfall Depth = **1.38** inches
 Post Development Runoff Coefficient = **0.48**
 On-site Water Quality Volume = **8530** cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = **0.00** acres
 Off-site Impervious cover draining to BMP = **0.00** acres
 Impervious fraction of off-site area = **0**
 Off-site Runoff Coefficient = **0.00**
 Off-site Water Quality Volume = **0** cubic feet

Storage for Sediment = **1706**
 Total Capture Volume (required water quality volume(s) x 1.20) = **10236** cubic feet

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan * = **33.05** acres
 Predevelopment impervious area within the limits of the plan * = **0.00** acres
 Total post-development impervious area within the limits of the plan * = **11.53** acres
 Total post-development impervious cover fraction * = **0.35**
 P = **30** inches

$L_{M \text{ TOTAL PROJECT}}$ = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **VFS #1**
 Total drainage basin/outfall area = **2.05** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **1.03** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.50**
 $L_{M \text{ THIS BASIN}}$ = **840** lbs.



3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
 Removal efficiency = **85** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **2.05** acres
 A_i = **1.03** acres
 A_p = **1.02** acres
 L_R = **923** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **923** lbs.

F = **1.00**

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.
 Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.
 Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan * = **33.05** acres
 Predevelopment impervious area within the limits of the plan * = **0.00** acres
 Total post-development impervious area within the limits of the plan * = **11.53** acres
 Total post-development impervious cover fraction * = **0.35**
 P = **30** inches

$L_{M \text{ TOTAL PROJECT}}$ = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **VFS #2**
 Total drainage basin/outfall area = **1.36** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **0.76** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.56**
 $L_{M \text{ THIS BASIN}}$ = **620** lbs.



3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
 Removal efficiency = **85** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **1.36** acres
 A_i = **0.76** acres
 A_p = **0.60** acres
 L_R = **679** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **679** lbs.
 F = **1.00**

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.

Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan * = **33.05** acres
 Predevelopment impervious area within the limits of the plan * = **0.00** acres
 Total post-development impervious area within the limits of the plan * = **11.53** acres
 Total post-development impervious cover fraction * = **0.35**
 P = **30** inches

$L_{M \text{ TOTAL PROJECT}}$ = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **VFS #3**
 Total drainage basin/outfall area = **1.22** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **0.62** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.51**
 $L_{M \text{ THIS BASIN}}$ = **506** lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
 Removal efficiency = **85** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **1.22** acres
 A_i = **0.62** acres
 A_p = **0.60** acres
 L_R = **555** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **555** lbs.
 F = **1.00**



Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.
 Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan * = **33.05** acres
 Predevelopment impervious area within the limits of the plan * = **0.00** acres
 Total post-development impervious area within the limits of the plan * = **11.53** acres
 Total post-development impervious cover fraction * = **0.35**
 P = **30** inches

$L_{M \text{ TOTAL PROJECT}}$ = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **VFS #4**
 Total drainage basin/outfall area = **2.37** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **1.24** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.52**
 $L_{M \text{ THIS BASIN}}$ = **1012** lbs.



3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
 Removal efficiency = **85** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **2.37** acres
 A_i = **1.24** acres
 A_p = **1.13** acres
 L_R = **1110** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M \text{ THIS BASIN}}$ = **1100** lbs.
 F = **0.99**

Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.
 Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.

Characters shown in red are data entry fields.

Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.

1. The Required Load Reduction for the total project:

Calculations from RG-348

Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$

where: $L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 A_N = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project

County = **Bexar**
 Total project area included in plan * = **33.05** acres
 Predevelopment impervious area within the limits of the plan * = **0.00** acres
 Total post-development impervious area within the limits of the plan * = **11.53** acres
 Total post-development impervious cover fraction * = **0.35**
 P = **30** inches

$L_{M \text{ TOTAL PROJECT}}$ = **9408** lbs.

* The values entered in these fields should be for the total project area.

Number of drainage basins / outfalls areas leaving the plan area = **1**

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = **VFS #5**
 Total drainage basin/outfall area = **0.26** acres
 Predevelopment impervious area within drainage basin/outfall area = **0.00** acres
 Post-development impervious area within drainage basin/outfall area = **0.10** acres
 Post-development impervious fraction within drainage basin/outfall area = **0.38**
 $L_{M \text{ THIS BASIN}}$ = **82** lbs.



3. Indicate the proposed BMP Code for this basin.

Proposed BMP = **Vegetated Filter Strips**
 Removal efficiency = **85** percent

- Aqualogic Cartridge Filter
- Bioretention
- Contech StormFilter
- Constructed Wetland
- Extended Detention
- Grassy Swale
- Retention / Irrigation
- Sand Filter
- Stormceptor
- Vegetated Filter Strips
- Vortechs
- Wet Basin
- Wet Vault

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_i \times 34.6 + A_p \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_i = Impervious area proposed in the BMP catchment area
 A_p = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

A_C = **0.26** acres
 A_i = **0.10** acres
 A_p = **0.16** acres
 L_R = **90** lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area





Desired $L_{M \text{ THIS BASIN}}$ = **90** lbs.

F = **1.00**

EXHIBITS

1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
 - THE NAME OF THE APPROVED PROJECT;
 - THE ACTIVITY START DATE; AND
 - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.
3. IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SINK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCEQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES MAY NOT BE RESUMED UNTIL THE TCEQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.
4. NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
6. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
7. SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
8. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
9. ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARDS AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE OTHER SITE.
10. IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
11. THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
 - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
 - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
 - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
12. THE HOLDER OF ANY APPROVED EDWARD AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
 - A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
 - B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
 - C. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

SAN ANTONIO REGIONAL OFFICE
14250 JUDSON ROAD
SAN ANTONIO, TEXAS 78233-4480
PHONE (210) 490-3096
FAX (210) 545-4329



- GENERAL NOTES:**
1. DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION.
 2. LOCATIONS OF CONSTRUCTION ENTRANCE/EXITS, CONCRETE WASHOUT PITS, AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARDS TO BE DETERMINED IN THE FIELD.
 3. STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO BE MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. ALL MODIFICATIONS ARE TO BE NOTED ON THIS EXHIBIT AND SIGNED AND DATED BY THE RESPONSIBLE PARTY.
 4. RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY.
 5. ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES.
 6. CONTRACTOR, TO THE EXTENT PRACTICAL, SHALL MINIMIZE THE AMOUNT OF AREA DISTURBED. AS SOON AS PRACTICAL, ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.
 7. BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADIENT AREAS.
 8. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED.
 9. ALL TEMPORARY BMPs WILL BE REMOVED ONCE WATERSHED IS STABILIZED.
 10. MUD OR DIRT INADVERTENTLY TRACKED OFF-SITE AND ONTO EXISTING STREETS SHALL BE REMOVED IMMEDIATELY BY HAND OR MECHANICAL BROOM SWEEPING.
 11. PRIOR TO INITIATION OF SUBSEQUENT PHASES OF CONSTRUCTION, TEMPORARY BMPs INCLUDING SILT FENCING, CONSTRUCTION ENTRANCE/EXIT, CONCRETE WASHOUT PIT, AND CONSTRUCTION STAGING AREA SHALL BE FIELD LOCATED AS APPROPRIATE FOR THE AREA OF CONSTRUCTION.
 12. TEMPORARY POLLUTION ABATEMENT MEASURES SHOWN ON THE PLAN ARE FOR THE OVERALL DEVELOPMENT. TEMPORARY BMPs MAY REQUIRE ADJUSTMENT BASED ON PHASING OF CONSTRUCTION OF THE DEVELOPMENT. RECORDS OF ADJUSTMENTS AND REVISIONS SHALL BE MAINTAINED AS APPROPRIATE.
 13. TEMPORARY BMPs SHOWN ON THIS SHEET ARE FOR GRAPHICAL PURPOSES AND MAY NOT BE TO SCALE. BMPs SHALL BE LOCATED WITHIN THE PROJECT LIMITS.
 14. UPON COMPLETION OF THE PROJECT AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES.
 15. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND REMOVAL OF TEMPORARY POLLUTION ABATEMENT MEASURES THAT CONFLICT WITH SITE IMPROVEMENTS SUCH AS LANDSCAPING AND FENCES SO AS TO PREVENT SEDIMENT FROM ESCAPING THE PROJECT SITE.

TEMPORARY BMP MODIFICATIONS		
DATE	SIGNATURE	DESCRIPTION

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

WPAP EXHIBIT 1

NO.	REVISION	DATE



PARE-DAWSON ENGINEERS
SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TYPE FIRM REGISTRATION #470 | TYPE FIRM REGISTRATION #1008800

BROOK STONE PHASE I MOD
BEXAR COUNTY, TEXAS
WATER POLLUTION ABATEMENT PLAN MODIFICATION
TEMPORARY POLLUTION ABATEMENT PLAN




PLAT NO.	21-11800043
JOB NO.	12093-04
DATE	JANUARY 2023
DESIGNER	SS
CHECKED	DRAWN SS
SHEET	

PERMANENT POLLUTION ABATEMENT MEASURES:

1. PERMANENT BMP'S FOR THIS SITE INCLUDE TWO BATCH DETENTION BASINS, FOUR 50' VEGETATIVE FILTER STRIPS, TWO 15' ENGINEERED VEGETATIVE FILTER STRIPS, AND ONE INTERMEDIATE FILTER STRIP. THESE PERMANENT BMP'S HAVE BEEN DESIGNED TO REMOVE AT LEAST 80% OF THE INCREASED TOTAL SUSPENDED SOLIDS (TSS) IN ACCORDANCE WITH THE TCEQ'S TECHNICAL GUIDANCE MANUAL (TGM) RG-348 (2005).
2. SILT FENCING AND ROCK BERMS, WHERE APPROPRIATE, WILL BE MAINTAINED UNTIL THE ROADWAY, UTILITY, DRAINAGE IMPROVEMENTS, AND BUILDING CONSTRUCTION ARE COMPLETED.
3. ENERGY DISSIPATORS (TO HELP REDUCE EROSION) WILL BE PROVIDED AT POINTS OF CONCENTRATED DISCHARGE WHERE EXCESSIVE VELOCITIES MAY BE ENCOUNTERED.
4. TEMPORARY BMP'S WILL BE MAINTAINED UNTIL THE SITE IMPROVEMENTS ARE COMPLETED AND THE SITE HAS BEEN STABILIZED, INCLUDING SUFFICIENT VEGETATION BEING ESTABLISHED.
5. DURING CONSTRUCTION, TO THE EXTENT PRACTICAL, CONTRACTOR SHALL MINIMIZE THE AREA OF SOIL DISTURBANCE. AREAS OF DISTURBED SOIL SHALL BE REVEGETATED TO STABILIZE SOIL USING SOLID SOD IN A STAGGERED PATTERN. SEE DETAIL ON TEMPORARY POLLUTION ABATEMENT DETAIL SHEET AND REFER TO SECTION 1.3.11 IN TCEQ'S TECHNICAL GUIDANCE MANUAL RG-348 (2005). SOD SHOULD BE USED IN CHANNELS AND ON SLOPES > 15%. THE CONTRACTOR MAY SUBSTITUTE THE USE OF SOD WITH THE PLACEMENT OF TOP SOIL AND A FRIABLE SEED BED WITH A PROTECTIVE MATTING OR HYDRAULIC MULCH ALONG WITH WATERING UNTIL VEGETATION IS ESTABLISHED. APPLICATIONS AND PRODUCTS SHALL BE THOSE APPROVED BY TXDOT AS OF FEBRUARY 2001 AND IN COMPLIANCE WITH THE TGM RG-348 (2005). SEED MIXTURE AND/OR GRASS TYPE TO BE DETERMINED BY OWNER AND SHOULD BE IN COMPLIANCE WITH TGM RG-348 (2005) GUIDELINES. IRRIGATION MAY BE REQUIRED IN ORDER TO ESTABLISH SUFFICIENT VEGETATION.
6. FOR DISTURBED AREAS WHERE INSUFFICIENT SOIL EXISTS TO ESTABLISH VEGETATION, CONTRACTOR SHALL PLACE A MINIMUM OF 6" OF TOPSOIL PRIOR TO REVEGETATION.
7. TYPICAL SLOPES ON THIS PROJECT RANGE FROM APPROXIMATELY 1% TO 15%.

NOTES:

1. CONTRACTOR SHALL INSTALL AND ESTABLISH VEGETATION FOR SOIL STABILIZATION PRIOR TO SITE CLOSEOUT.
2. ALL PERMANENT BMP'S MUST BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER.
3. INDIVIDUAL LOTS VARY IN SIZE. VALUES PROVIDED ARE BASED ON TYPICAL LOT SIZES.




LEGEND

--- PROJECT LIMITS	--- EXISTING CONTOUR	--- PROPOSED CONTOUR	--- WATERSHED BOUNDARY	--- FEMA 1% ANNUAL-CHANCE FLOODPLAIN	--- FAULT, INFERRED
→ FLOW ARROW (PROPOSED)	Kek Kainer Formation	Kgru Glen Rose Formation (Upper)	S-1 Potential Recharge Feature	⊕ Strike of Vertical Joints	⊖ Non-Karst Closed Depression
⊕ Contact, Located Approximately	⊖ Sinkhole	⊖ Solution Cavity	⊖ Zone or Feature Extent	⊖ Water Well	⊖ Uncaptured Impervious Cover
⊖ Areas Covered by Separate WPAP	⊖ Vegetative Filter Strip	A, B, C	FHA Lot Grading Type		



Treatment Summary Table
Current Application - Brook Stone Creek - Phase 1 Mod

Watershed	Watershed Area (acres)	Previously Approved Impervious Cover (acres)	Total Proposed Impervious Cover (acres)	BMP	Required TSS Removal (lbs./yr.)	Designed TSS Removal (lbs./yr.)
BA-B	27.67	9.44	5.22	Existing Basin B	11963	12003
BA-C	3.56	0	2.39	Batch Detention Basin C	1950	2013
A	2.05	0	1.03	50' Natural Vegetative Filter Strip VFS #1	840	923
B	0.15	0	0.07	Uncaptured	57	0
C	1.36	0	0.76	15' Engineered Vegetative Filter Strip VFS #2	620	679
D	1.22	0	0.62	50' Natural Vegetative Filter Strip VFS #3	506	555
E	2.37	0	1.24	50' Natural Vegetative Filter Strip VFS #4	1012	1110
F	0.26	0	0.10	50' Natural Vegetative Filter Strip VFS #5	82	89
G	0.17	0	0.10	Uncaptured	82	0
Total	38.81	9.44	11.53		17112	17372



TYPICAL FHA LOT DRAINAGE DETAILS

NOTE: ROOF DRAINAGE PATTERN IS APPROXIMATE AND SUBJECT TO CHANGE BASED ON FINAL HOUSE PAD DESIGN. HOWEVER RUNOFF FROM DRIVEWAY, ROOF OR OTHER IMPERVIOUS SURFACES WITHIN THE LOT WILL NOT FLOW ACROSS MORE THAN 72' OF IMPERVIOUS SURFACE BEFORE REACHING THE PROPOSED 15' ENGINEERED VEGETATIVE FILTER STRIP. FINAL LOT GRADING TO ALLOW FOR SHEET FLOW OVER VEGETATIVE FILTER STRIP.



THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

WPAP EXHIBIT 3

DATE	
NO.	
REVISION	

05/18/2023

STATE OF TEXAS
REBECCA ANN CARROLL
92666
REGISTERED PROFESSIONAL ENGINEER

PAPE-DAWSON ENGINEERS

SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TYPE FIRM REGISTRATION #470 | TYPE FIRM REGISTRATION #1008880


BROOK STONE PHASE I MOD
BEXAR COUNTY, TEXAS

WATER POLLUTION ABATEMENT PLAN MODIFICATION
PERMANENT POLLUTION ABATEMENT PLAN

PLAT NO.	21-11800043
JOB NO.	12093-04
DATE	JANUARY 2023
DESIGNER	SS
CHECKED	DRAWN SS
SHEET	


Date: May 18, 2023, 4:02pm User: rsc@pape-dawson.com File: P:\2023\03\02\Design\Exhibits\WPAP\21032901 PM.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE/US UNLESS OTHERWISE NOTED. Imagery © 2016, COPCO, Digital Globe, Texas Orthology Program, USDA Farm Service Agency.




NOTES

- CONTRACTOR SHALL ENGAGE A TEXAS LICENSED STRUCTURAL ENGINEER TO PROVIDE A SIGNED AND SEALED SET OF STRUCTURAL PLANS, DETAILS AND SPECIFICATION FOR THE STRUCTURAL COMPONENTS OF THE POLLUTION ABATEMENT BASIN INCLUDING INLET DISCHARGE AND BYPASS COMPONENTS. CONTRACTOR SHALL ALSO PROVIDE FOR STRUCTURAL ENGINEER'S INSPECTION DURING BASIN CONSTRUCTION AND STRUCTURAL ENGINEER'S CONSTRUCTION CERTIFICATION UPON COMPLETION OF BASIN.
- UPON COMPLETION OF CONSTRUCTION, AND IN ACCORDANCE WITH TCEQ REGULATIONS, ALL PERMANENT BMP'S MUST BE CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER.
- ALL AREAS DISTURBED AS PART OF CONSTRUCTION OF BASIN SHALL BE REVEGETATED PRIOR TO COMPLETION.
- BASIN HAS BEEN DESIGNED USING TSS REMOVAL AND BMP SIZING CALCULATIONS AS PER THE TCEQ TGM RG-348 (2005).
- BASIN PLAN DEPICTS MINIMUM INTERIOR DIMENSIONS (LENGTH, WIDTH & HEIGHT FOR TCEQ REVIEW & APPROVAL. ACTUAL STRUCTURAL PLANS FOR CONSTRUCTION TO BE DESIGNED BY STRUCTURAL ENGINEER AT A LATER DATE.



BASIN DESIGN DATA	
BASIN WATERSHED AREA	= 3.82 AC.
RUN OFF DEPTH	= 1.50 IN
REQUIRED CAPTURE VOLUME	= 10,974 CF
BASIN STORM WATER DEPTH	= 3.00 FT
BASIN CAPTURE VOLUME	= 11,825 CF

OVERFLOW WEIR CALCULATIONS	
Q_{2s}	= $(Cw)(L)(h)^{3/2}$
Q_{2s}	= 16.7 cfs
C	= 3.087
L	= 22 ft
16.7	= $(3.087)(22)(h)^{3/2}$
h	= 0.40 ft




SEQUENCE OF OPERATION

BASIN DRAINDOWN IS CONTROLLED BY THE HORIZONTAL OUTFALL PIPE. BASIN DRAINDOWN WILL OCCUR IN APPROXIMATELY 6.00 HOURS.

CONTRACTOR TO SET VALVE TO FULLY CLOSED POSITION

UPON ACTIVATION OF FLOAT SWITCH, DDC CONTROLLER TO START DETENTION TIMER #1.

- DETECTION TIMER #1 TO BE MANUALLY SET TO 12.00 HOURS AND TO BE USER ADJUSTABLE VALUE.
- WHEN DETENTION TIMER #1 HAS ELAPSED, A 6\"/>




SECTION "A-A"
N.T.S.

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

WPAP EXHIBIT 4

NO.	REVISION	DATE



PAPE-PAWSON ENGINEERS

SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TPEL FIRM REGISTRATION #470 | TPEL FIRM REGISTRATION #10088800

BROOK STONE CREEK-UNIT 1C
BEXAR COUNTY, TEXAS

BASIN C

PLAT NO.	21-11800043
JOB NO.	12093-04
DATE	DECEMBER 2022
DESIGNER	SS
CHECKED	BAC DRAWN SS
SHEET	C9.00

