



O'Connor High School

Organized Sewage Collection System (OSCS) Plan

KCI Job # 762301481

Prepared for:

Northside Independent School District
5900 Evers Road
San Antonio, TX 78238

Prepared by:

KCI Technologies Inc.
Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
2806 W. Bitters Rd., Suite 218
San Antonio, TX 78248



September 2023

RISE TO THE
CHALLENGE

Texas Commission on Environmental Quality (TCEQ)

Organized Sewage Collection System (OSCS) Plan

O'Connor High School Agricultural Science and Technology

KCI Job # 762301481



Prepared by:

Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
Practice Leader \ Senior Associate

KCI Technologies, Inc.
2608 W. Bitters Road, Suite 218
San Antonio, TX 78248
Phone: (210) 641-9999
FAX: (210) 641-6440
Registration #F-10573 / #101943-65

Prepared for:

Northside Independent School District
5900 Evers Road
San Antonio, TX 38248

Table of Contents

- **Edwards Aquifer Application Cover (TCEQ-20705)**
- **General Information Form (TCEQ-0587)**
 - Attachment A – Road Map & Aerial Map
 - Attachment B – USGS Map / Edwards Recharge Zone Map
 - Attachment C – Project Description & Existing and Proposed Impervious Cover Exhibits
- **Geologic Assessment Report (TCEQ-0585)**
 - Attachment A – Geologic Assessment Table
 - Attachment B – Stratigraphic Column
 - Attachment C – Site Geology
 - Attachment D – Site Geology Map
- **Organized Sewage Collection System Plan (TCEQ-0582)**
 - Attachment A – SCS Engineering Design Report
 - Attachment E – Construction Plans
- **Temporary Stormwater Section (TCEQ-0602)**
 - Attachment A - Spill Response Actions
 - Attachment B - Potential Sources of Contamination
 - Attachment C - Sequence of Major Activities
 - Attachment D - Temporary Best Management Practices and Measures
 - Attachment F - Structural Practices
 - Attachment G - Drainage Area Maps
 - Attachment I - Inspection and Maintenance for temporary BMPs
 - Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices
 - Attachment K - SWPPP
- **Agent Authorization Form (TCEQ-0599)**
- **Application Fee Form (TCEQ-0574)**
- **Core Data Form (TCEQ-10400)**

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited.**
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: O’Connor High School Agricultural Area				2. Regulated Entity No.: 104754304					
3. Customer Name: Leroy San Miguel, Assistant Superintendent for Facilities and Operations				4. Customer No.: 601104169					
5. Project Type: (Please circle/check one)	New	Modification		Extension	Exception				
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential		Non-residential		8. Site (acres):		26.940 out of 157.652		
9. Application Fee:	\$650		10. Permanent BMP(s):			1			
11. SCS (Linear Ft.):	611		12. AST/UST (No. Tanks):			0			
13. County:	Bexar		14. Watershed:			Leon Creek			

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.


Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<input checked="" type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input checked="" type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Paul Mathis, PE, PMP, LEED Green Associate, MBA (KCI)

Print Name of Customer/Authorized Agent



September 21, 2023

Signature of Customer/Authorized Agent

Date

****FOR TCEQ INTERNAL USE ONLY****

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

General Information Form (TCEQ-0587)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
Practice Leader | Senior Associate

Date: 9/22/2023

Signature of Customer/Agent:



Project Information

1. Regulated Entity Name: O'Connor High School Agricultural Science and Technology
2. County: Bexar
3. Stream Basin: Helotes Creek
4. Groundwater Conservation District (If applicable): Edwards Aquifer Authority
5. Edwards Aquifer Zone:
 Recharge Zone
 Transition Zone
6. Plan Type:
 WPAP SCS

Modification
 AST

UST
 Exception Request

7. Customer (Applicant):

Contact Person: Jacob Villarreal, Executive Director of Construction and Engineering
Entity: Northside Independent School District
Mailing Address: 5900 Evers Road
City, State: San Antonio, TX Zip: 78238
Telephone: (210) 397-8500 FAX: (210) 397-8500
Email Address: jacob.villarreal@nisd.net

8. Agent/Representative (If any):

Contact Person: Paul A. Mathis, P.E. LEED Green Assoc., MBA, Praticce Leader \ Senior Associate
Entity: KCI Technolgies, Inc.
Mailing Address: 2806 W. Bitters Rd., Ste. 218
City, State: San Antonio, TX Zip: 78248
Telephone: (210) 641-9000 FAX: (210) 41-6440
Email Address: paul.mathis@kci.com

9. Project Location:

- The project site is located inside the city limits of Helotes.
 The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.
 The project site is not located within any city's limits or ETJ.

10. The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

O'Connor High School is located in southwest corner of intersection of Bandera Road and Leslie Road. The addition of the new buildings will be in the southwest corner of the school property.

11. **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12. **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- Project site boundaries.
 - USGS Quadrangle Name(s).
 - Boundaries of the Recharge Zone (and Transition Zone, if applicable).
 - Drainage path from the project site to the boundary of the Recharge Zone.

13. **The TCEQ must be able to inspect the project site or the application will be returned.**
Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

Survey staking will be completed by this date: _____

14. **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- Area of the site
- Offsite areas
- Impervious cover
- Permanent BMP(s)
- Proposed site use
- Site history
- Previous development
- Area(s) to be demolished

15. Existing project site conditions are noted below:

- Existing commercial site
- Existing industrial site
- Existing residential site
- Existing paved and/or unpaved roads
- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Uncleared)
- Other: Existing O'Connor High School Campus

Prohibited Activities

16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
 - (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
 - (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.


Administrative Information

18. The fee for the plan(s) is based on:
- For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
 - For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
 - For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
 - A request for an exception to any substantive portion of the regulations related to the protection of water quality.
 - A request for an extension to a previously approved plan.
19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:
- TCEQ cashier
 - Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
 - San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)
20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.


Attachment A

Road & Aerial Maps

Road Map



7/10/2023, 3:05:49 PM




BCAD, Esri, HERE, Garmin, INCREMENT P, NGA, USGS

USGS
2021 USGS


Attachment B

USGS & Edwards Recharge Zone Maps

USGS Map




7/10/2023, 3:58:39 PM



USGS The National Map: National Boundaries Dataset, 3DEP Elevation Program, Geographic Names Information System, National Hydrography Dataset, National Land Cover Database, National Structures


USGS
2021 USGS

Edwards Aquifer Map



9/21/2023, 8:23:39 AM

- | | | |
|---------------------------------------|------------------------------------|----------------------------|
| Edwards Aquifer Label | City/Place | TX Counties |
| Edwards Aquifer Boundary | Groundwater Conservation Districts | 7.5 Minute Quad Grid |
| Edwards Aquifer Boundary central line | Edwards Aquifer Authority | TCEQ_EDWARDS_OFFICIAL_MAPS |
| | Trinity Glen Rose GCD | |



TCEQ, BCAD, Texas Parks & Wildlife, Esri, HERE, Garmin, INCREMENT P, USGS, METINASA, EPA, USDA

Attachment C



Project Description

Project Overview






The Project is located inside O'Connor High School at 12221 Leslie Rd, Helotes, TX 78023 (Southwest corner of High School Property which is located at southwest corner of intersection of Bandera Road and Leslie Road), refer to the enclosed aerial photo. The project is within the City limits of Helotes with the legal description CB 4480B BLK 1 LOT 4 EXC NE IRR 5FT HELOTES AREA HIGH SCHOOL, Bexar County, Texas. The site is entirely located within Leon Creek Watershed. A portion of this tract is within the 100-year FEMA floodplain, Firm Panel 48029C0220G effective September 29, 2010, as shown in Exhibits A of this report.

Proposed Sewer Line

The addition of new buildings, a food science building, a barn, a general warehouse, a greenhouse, a storage, and a shop building will require extension of sewer line and laterals to these proposed new buildings and addition of a small lift station. The total length of the proposed 8-inch PVC SDR 26 sewer gravity line is 611 linear feet, and 1208 linear feet of 6-inch PVC SDR 26 sewer laterals. 3 new manholes will be added to the site with one intercepting the existing SCS as shown in enclosed Utility and Drainage Plan North (C5.02) and Utility and Drainage Plan Mid (C5.03).



LEGEND

	EXISTING IMPERVIOUS COVER CURRENTLY TREATED BY STUDENT PARKING LOT BASIN
	EXISTING IMPERVIOUS COVER CURRENTLY TREATED BY VEGETATED FILTER STRIP
	EXISTING IMPERVIOUS COVER (NOT TREATED)
	DRAINAGE AREA BOUNDARY
	DRAINAGE AREA NUMBER & ABRIDGE

PRE-DEVELOPMENT
EXISTING IMPERVIOUS COVER (IC) CALCULATIONS:
 1 - IC TREATED BY STUDENT PARKING LOT WATER QUALITY BASIN (DA-1, DA-2, AND DA-3) = 9.582 AC
 2 - IC TREATED VEGETATED FILTER STRIP (DA-4 AND DA-5) = 6.352 AC
 3 - IC NOT TREATED (DA-6 AND DA-7) = 1.116 AC

TOTAL EXISTING IMPERVIOUS COVER = 17.059 AC

	<p>KCI TECHNOLOGIES, INC. 12221 LESLIE RD. HELOTES, TX 78023 EXISTING IMPERVIOUS COVER</p>
	<p>O'CONNOR HIGH SCHOOL 12221 LESLIE RD. HELOTES, TX 78023 EXISTING IMPERVIOUS COVER</p>
<p>DATE: 08/14/2018 TIME: 10:00 AM SHEET: 01 OF 01</p>	<p>DATE: 08/14/2018 TIME: 10:00 AM SHEET: 01 OF 01</p>
<p>PROJECT: O'CONNOR HIGH SCHOOL LOCATION: 12221 LESLIE RD., HELOTES, TX 78023</p>	<p>PROJECT: O'CONNOR HIGH SCHOOL LOCATION: 12221 LESLIE RD., HELOTES, TX 78023</p>

Geologic Assessment (TCEQ-0585)

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Richard V. Klar, P.G.


Telephone: 210-699-9090

Date: October 25, 2023

Fax: 210-699-6426

Representing: Raba Kistner, Inc., TBPG Firm #50220 / TBPE Firm #3257 for KCI Technologies, Inc. on Behalf of Northside Independent School District (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



10/26/2023

Regulated Entity Name: O'Connor High School Water Pollution Abatement Plan (WPAP) Modification

Project Information

1. Date(s) of Geologic Assessment was performed: May 18, 2023

2. Type of Project:

WPAP

AST

SCS

UST

3. Location of Project:
 - Recharge Zone
 - Transition Zone
 - Contributing Zone within the Transition Zone
4. **Attachment A – Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the Site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

**Soil Group Definitions (Abbreviated)*

Soil Name	Group*	Thickness (feet)
Crawford Clay, 0 to 1 percent slopes (Ca)	D	~1 to 3
Crawford and Bexar stony soils, 0 to 5 percent slopes (Cb)	D	~1 to 3
Lewisville silty clay, 0 to 1 percent slopes (LvA)	B	~4+
Lewisville silty clay, 1 to 3 percent slopes (LvB)	B	~2 to 3
Patrick soils, 3 to 5 percent slopes (PaC)	B	~1 to 1.5

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6. **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thickness is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7. **Attachment C – Project Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.

8. **Attachment D – Project Geologic Map(s).** The Project Geologic Map must be the same scale as the applicant’s Site Plan. The minimum scale is 1”:400’.

Applicant’s Site Plan Scale: 1” = 80’

Project Geologic Map Scale: 1” = 80’

Site Soils Map Scale (if more than 1 soil type): 1” = 200’

9. Method of collecting positional data:

Global Positioning System (GPS) technology.

Other method(s). Please describe method of data collection: ____

10. The project site boundaries are clearly shown and labeled on the Project Geologic Map.

11. Surface geologic units are shown and labeled on the Project Geologic Map.

12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Project Geologic Map and are described in the attached Geologic Assessment Table.

Geologic or manmade features were not discovered on the project site during the field investigation.

13. The Recharge Zone boundary is shown and labeled, if appropriate.

14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.

There are 15 (#) test holes present on the project site and the locations are shown and labeled. (Check all of the following that apply.)

The test holes are not in use and have been properly abandoned.

The well is not in use and will be properly abandoned.

The well is in use and complies with 16 TAC Chapter 76.

There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

- Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENTS

ATTACHMENT A

**GEOLOGIC ASSESSMENT TABLE
(TCEQ-0585-TABLE)**

COMMENTS TO GEOLOGIC ASSESSMENT TABLE

SOIL PROFILE

PROJECT SOILS MAP

COMMENTS TO GEOLOGIC ASSESSMENT TABLE
O' Connor High School Water Pollution Abatement Plan (WPAP) Modification
Helotes, Bexar County, Texas

The locations of the following features are indicated on the *Project Geologic Map* provided as **Attachment D** of this report. The following utility trenches (i.e., sanitary sewer, potable water, electric, and natural gas), in addition to an extensive storm drain system were identified within the WPAP assessment area and plotted based on field observations of manholes, valves, meters and fire hydrants, in addition to storm drain inlets and water quality basins. The utility locations and storm drain segments were also taken from the Overall Utility and Drainage Exhibit (i.e., PDF) provided by the project engineer, KCI Technologies, Inc. (KCI, 2023).

Manmade Features in Bedrock (MB)

Feature S-1

Feature S-1 consists of a trench for an existing 6 to 8-inch sanitary sewer line owned by San Antonio Water System (SAWS). The location of this utility was identified based on review of the referenced utility exhibit (KCI, 2023), in addition to field observations of manholes and cleanouts. On the basis of our observations and available utility information, it is inferred that the trench hosting the utility line is approximately 3-4 feet wide and installed to approximately 8-10 feet terminating in the underlying Quaternary terrace deposits (Qt) and Person Formation (Kep). The combined length of the utility trench segment within the Project area is estimated on the order of 3,450 linear feet.



Feature S-2

Feature S-2 consists of a trench for an existing sanitary sewer line. The location of this utility was based on review of the referenced utility exhibit (KCI, 2023). On the basis of available utility information, it is inferred that the trench hosting the utility line is approximately 3-4 feet wide and installed to approximately 8-10 feet terminating in the underlying Person Formation (Kep). The length of the utility trench within the Project area is estimated on the order of 222 linear feet.

Feature S-3

Feature S-3 consists of trenches for existing 6- and 8-inch polyvinyl chloride (PVC) potable water lines owned by SAWS. The utility trenches were plotted based on review of the referenced utility exhibit (KCI, 2023) and field observations of fire hydrants and water meters near Buildings D and P. On the basis of our observations, it is inferred that the trenches hosting the utility lines are approximately 2-feet wide and installed 3-4 feet or more, terminating in the Qt and Kep. The length of the combined utility trenches within the project area is estimated on the order of 2,655 linear feet.



Feature S-4

Feature S-4 consists of trenches for electric lines owned by City Public Service (CPS) Energy. The utility trenches were identified based on observations of ground-mounted transformers during reconnaissance activities and review of the referenced utility exhibit (KCI, 2023). On the basis of our observations and available utility information, it is inferred that the trenches hosting the utility lines are approximately 2 feet wide and installed to approximately 2-3 feet, terminating in the underlying Qt and Kep. The trenches extend: (i) east from the Central Plant (Building D) to the agriculture barns; and (ii) north and south Buildings F and C, respectively. The length of the combined utility trenches within the Project area is estimated on the order of 3,394 linear feet.



Feature S-5

Feature S-5 consists of trenches for 1-1/4- and 4-inch natural gas lines owned by CPS Energy. The location of these utilities were based on observations of gas meters during reconnaissance activities and review of the referenced utility exhibit (KCI, 2023). On the basis of our observations and available utility information, it is inferred that the trenches hosting the utility lines are approximately 2 feet wide and installed to approximately 3-4 feet, terminating in the underlying Kep. The trenches extend from Building D to the west and follows main campus roadway to the agricultural barns. The combined length of the utility trenches within the Project area is estimated on the order of 2,208 linear feet.



Features S-6 through S-11

Features S-6, S-7, S-8, and S-10 consist of trenches hosting individual segments of a storm drain system that services the O' Connor High School campus. This drainage system discharges to water quality ponds, which ultimately discharge to Helotes Creek that is located approximately 1,230 to the southwest of the Project area. These trenches are inferred to be approximately 3-4 feet in depth, terminating into the underlying Qt and Kep.

- **Feature S-6** consists of an 18 and 24 inch storm drain reinforced concrete pipes (RCP) in various locations that extend from Building F and follow drainage swales south to a 24-inch corrugated metal pipe and daylights to an open drainage field located north of Water Quality Pond A (**Feature S-8**). The length of the utility trench segment within the Project area is estimated on the order of 830 linear feet.
- **Feature S-7** consists of a storm drain pipe mapped from a manhole near Building L, extending through the parking lots to the southwest to a diversion structure and into a 48-inch inlet pipe to Water Quality Pond A (**Feature S-9**). The length of the utility trench segment within the Project area is estimated on the order of 1,146 linear feet.
- **Feature S-8** consists of a storm drain pipe mapped from a grassy area at the south edge of the student parking lot that extends to the southwest manhole in the student parking lot that further extends west to an outlet that opens to a drainage field south of the Water Quality Pond A (**Feature S-9**). The length of the utility trench within the Project area is estimated on the order of 681 linear feet.
- **Feature S-10** consists of a 21-inch storm drain pipe mapped from manholes surrounding the agricultural barns, which are located near the southwest corner of the assessment area. The stormwater drains to Water Quality Pond B (**Feature S-11**). The length of the utility trench segment within the Project area is estimated on the order of 670 linear feet.

Features S-9 and S-11 consist of stormwater basins (i.e., water quality ponds). After treatment through sand filter media via either Water Quality Pond A or Water Quality Pond B, stormwater is ultimately discharged to Helotes Creek, which is located approximately 1,230 feet to the southwest.

- **Feature S-9** consists of a sedimentation and filtration pond system (Pond A). The dimensions for this feature are approximately 174 feet long and 75 feet wide. The floor of the basin is approximately 8 feet below the top of the concrete headwall through which the detention pond connects to the concrete-lined stormwater collection system. This stormwater basin is underlain by the Kep.



- **Feature S-11** consists of a sand filtration basin and detention pond (Pond B). The dimensions for this feature are approximately 70 feet long and 48 feet wide. The floor of the basin is approximately 4 feet below the top of the concrete headwall through which the detention pond connects to the concrete lined stormwater collection system. This stormwater basin is underlain by the Qt.

Features S-12 through S-26

Features S-12 through S-26 consist of test holes installed in June 2023 to support various proposed improvements within the WPAP assessment area at O' Connor High School (i.e., additional buildings, paved areas, and a retaining wall) by **Raba Kistner, Inc.** (i.e., Project No. ASA23-041-00). A total of fifteen borings were drilled using a straight flight auger and air rotary methods to depths ranging from approximately 8-1/2 to 39 feet below existing ground surface. In general, the majority of the borings encountered a surficial layer of dark brown clay approximately 1.25 to 4.5 feet in depth underlain by either a reddish-tan sandy silt, silty sand, or calcareous clay stratum to depths up to 16.5 feet. These strata are underlain by hard tan limestone comprising the top of the Limestone (Person Formation). Fill material consisting of brown clayey sand was encountered to depths ranging from 6 to 19.4 feet at several borings near the southwest portion of the WPAP assessment area, west and south of Buildings P and N, respectively. Shallow groundwater was not observed during drilling operations.

Based on the referenced geotechnical borings logs and observations in conjunction with field reconnaissance activities, the borings were effectively plugged and abandoned following completion of drilling activities using granular bentonite.

SOIL PROFILE
O' Connor High School Water Pollution Abatement Plan (WPAP) Modification
Helotes, Bexar County, Texas

SOIL SERIES	THICKNESS ON SITE	DESCRIPTION
Crawford	~1 to 3 feet	Crawford clay, 0 to 1 percent slopes (Ca): Crawford soil patches are scattered throughout the hard limestone area, mostly in the uplands with few in the valleys. The surface layer consists of dark brown or dark reddish-brown noncalcareous clay and is typically 8-10 inches thick. The subsurface layer is also noncalcareous and is redder than the surface layer. Limestone typically occurs at a depth of 24-36 inches.
	~1 to 3 feet	Crawford and Bexar stony soils, 0 to 5 percent slopes (Cb): These soils occur as large areas and form a nearly continuous belt extending to the west from the northeast portion of Bexar County to south of Helotes. Crawford Soils comprise approximately 51% of the series. The surface layer of Crawford soils is comprised of dark gray to dark reddish-brown, non-calcareous clay and is typically 8-9 inches thick. The subsoil contains chert fragments and limestone flags. Hard limestone below depth of 24-36 inches. Bexar soils comprise approximately 36% of the series. The surface layer is comprised of cherty clay loam and is on the order of 14-22 inches in thickness. The subsoil is cherty clay and is approximately 6-14 inches thick.
Lewisville	~4+ feet	Lewisville silty clay, 0 to 1 percent slopes (LvA): These soils occur as nearly level, broad terraces along rivers and creeks. The surface layer is approximately 24 inches thick and comprised of silty clay or light clay. The subsurface layer is a very firm but crumbly when moist brown silty clay, which is approximately 24 inches thick. This layer has a few worm casts and a few hard and soft lime concretions.
	~2 to 3 feet	Lewisville silty clay, 1 to 3 percent slopes (LvB): Lewisville soils occur along long narrow sloping areas that separate nearly level terrace from soils on the uplands and also occurs on slopes along drainageways. The surface layer consists of dark grayish brown clay and is typically 20 inches thick. The subsoil consists of firm but crumbly limy brown clay and is approximately 17 inches thick.
Patrick	~1 to 1.5 feet	Patrick soils, 3 to 5 percent slopes (PaC): Patrick soils occupy escarpments between terraces, above floodplains of streams that drain the limestone prairies. The slopes are moderate and complex. The surface layer is a grayish-brown to dark brown, calcareous clay loam approximately 12 inches thick. The subsurface layer is a brown, calcareous, granular clay loam approximately 5 inches thick. The layers are friable when moist.

The preceding table was prepared based on *Soil Survey of Bexar County, Texas (1962, reissued June 1991)* in addition to field observations. As presented on the attached **Project Soils Map**, native soils mapped from east to west at the Project are the Lewisville silty clay, 1-3% slopes (LvB), Crawford clay (Ca) soils, Crawford and Bexar stony soils (Cb), Patrick soils, 3 to 5 percent slopes (PaC), and Lewisville silty clay, 0 to 1% slopes (LvA). The soil types are not readily observable owing to existing landscaping, pavements, hardscapes, and buildings that comprise the O' Connor High School. Below is a brief description of the mapped soil units within the WPAP assessment area.

- LvB soils are mapped at the southeast portion of the assessment area along the O Connor High school roadway entrance, which is located south of the band parade ground. This soil unit is associated with older terrace deposits along primary drainage features (i.e., river and creeks) in Bexar County. Lewisville soils are characterized as having a moderately slow permeability ranging on the order of 1.0 to 2.0 inches per hour.
- Ca soils are mapped within the main portion of the high school campus extending from the north portion of the assessment to the southwest in the student parking lot. These soils are naturally well drained, water intake is slow, and water erosion is a hazard. In addition, Ca soils have a very slow permeability, ranging on the order of 0.2 to 0.5 inches per hour. This soil unit is also described as having a high shrink swell potential.
- Cb soils are mapped west of Ca soils within the assessment area that follows the main campus roadway. These soils are weakly-developed and relatively thin, occurring over weathered limestone units of the Person Formation (Kep). These soils have a measured permeability of 1.0 to 1.5 in./hr. and are described as slow. The Crawford Series is further described as having a high shrink-swell potential.
- PaC soils are mapped along Buildings N, O, and P. The parent material is calcareous clay loam. A typical vertical profile consists of a thin surface soil layer ranging from a veneer to a few feet in thickness, typically consisting of gravelly clay loam underlain at shallow depths by hard limestone. Patrick soils are characterized as having a moderate infiltration rate with permeability on the order of 2.0 to 3.0+ in./hr. These soils are more susceptible to erosion.
- LvA soils are mapped at the southwest portion of the WPAP assessment area. LvA soils are typically associated with terrace deposits along as rivers and creek. These soils are characterized as having slow to moderate permeability and infiltration capacity on the order of 1 to 1.2 inches per hour.

As native soils were not directly observable owing to existing improvements, the geotechnical report prepared by **Raba Kistner, Inc.** (2023) was reviewed to evaluate soil and rock conditions, which were generally consistent with the soil types and conditions described above.

ATTACHMENT B

STRATIGRAPHIC COLUMN

STRATIGRAPHIC COLUMN
O' Connor High School Water Pollution Abatement Plan (WPAP) Modification
Helotes, Bexar County, Texas

STRATIGRAPHIC FORMATION	THICKNESS	DESCRIPTION
Fluviatile Terrace Deposits (Qt)	~4–8 feet	Unit consists of sand, silt, and clay sediments and gravels that contain limestone, dolomite, and chert. <i>Not exposed in the WPAP assessment area owing to soil cover.</i>
Del Rio Clay (Kdr)	40-50 feet	Unit consists of blocky gray calcareous clay that weathers light gray to yellowish gray. Identified in the field by the presence of <i>Ilymatogyra arietina</i> . <i>Not exposed in the WPAP assessment area owing to soil cover.</i>
Edwards Aquifer <u>Georgetown Formation</u> (Kgt)	<10 feet	Unit consists of gray to light tan marly limestone. Identified in the field by the presence of <i>Waconella wacoensis</i> . <i>Not locally present in the WPAP assessment area.</i>
Edwards Limestone (Ked) <u>Person Formation</u> (Kep) <i>Cyclic and Marine Members, undivided</i>	180-224 feet 80-100 feet	Unit consists of massive mudstone to packstone; <i>miliolid</i> grainstone; and chert. Identified in the field by cycles of massive beds to relatively thin beds. <i>The Kep is inferred to underlie the majority of the WPAP assessment area. Isolated exposures observed along the north side of Building Q. Kep was reported in the geotechnical boring logs (RKI, 2023)</i>
<i>Leached and Collapsed Members, undivided</i>	80-100 feet	Unit consists of crystalline limestone, mudstone to grainstone and chert. Identified in the field by bioturbated iron-stained beds separated by massive limestone beds. <i>Reported to underlie the WPAP assessment area at depth.</i>
<i>Regional Dense Member</i>	20-24 feet	Unit consists of dense, argillaceous mudstone. Identified in the field by wispy iron-oxide stains. <i>Reported to underlie the WPAP assessment area at depth.</i>

Note: Stratigraphic Column adapted from Collins (2000).

ATTACHMENT C

NARRATIVE OF PROJECT SPECIFIC GEOLOGY

SITE GEOLOGY NARRATIVE
O' Connor High School Water Pollution Abatement Plan (WPAP) Modification
Helotes, Bexar County, Texas

Introduction

The following is a project-specific discussion of existing geological conditions and potential recharge features for the Edwards Aquifer identified within the west-central portion of the Sandra Day O' Connor High School campus that will host planned improvements (hereinafter referred to as Project or WPAP assessment area). The improvements will include a new greenhouse, shop, administrative and food science building, and animal pens. New pavement areas are proposed around the new shop and a retaining wall is proposed southeast of the new proposed animal pens. In addition, vegetation filter strip overlay in areas and the expansion of the student parking lot water quality basin is proposed for drainage improvements across the west side of the campus. This assessment was performed by **Raba Kistner, Inc. (RKI)** for KCI Technologies, Inc. (CLIENT) on behalf of Northside Independent School District (NISD) pursuant to applicable Edwards Aquifer Protection Program Rules as specified in *Title 30 of the Texas Administrative Code, Section 213 (30 TAC §213, effective April 24, 2008)*.

This assessment report is in the format required by the Texas Commission on Environmental Quality (TCEQ) for the Geologic Assessment portion of the Water Pollution Abatement Plan and Sewage Collection System (SCS) plan submittal and was prepared in accordance with the revised *Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zones (TCEQ-0585)*, which are applicable to submittals received by the TCEQ after October 1, 2004. This geologic assessment report documents conditions observed by **RKI** within the Project boundaries on October 9, 2023. As further discussed herein, no naturally-occurring geologic features were identified as a result of assessment activities.

Project Description

Project Location. The Project comprises approximately 38.8 acres of land within the west-central portion of the existing NISD Sandra Day O'Connor High School campus, which is locally addressed at 12221 Leslie Road in Helotes (Bexar County). In accordance with TCEQ requirements, the full extent of the Project and, including the proposed SCS alignment and surrounding 50-foot buffer zone, was fully assessed in conjunction with Geologic Assessment activities. The Project area is fully developed and currently hosts existing classroom and agricultural buildings, asphalt parking lots, roadways, hardscape and landscaping improvements, in addition to existing utilities and drainage systems (i.e., storm drains and water quality basins). The Project is bounded to the north by Helotes City Hall and Police Department, west by the Vulcan Materials Helotes Asphalt quarry, NISD tennis center to the south, and existing school classroom buildings/portables and a band parade ground to the east.

Based on review of official maps prepared by TCEQ that are available from the Edwards Aquifer Protection Program website (<http://www.tceq.texas.gov/field/eapp/program.html>), the north and southwest portions of the Project are located within the Edwards Aquifer Recharge Zone (EARZ) and the central portion of the assessment area is within the Edwards Aquifer Transition Zone (EATZ) as depicted on the **Project Geologic Map**. As such, the performance of a geologic assessment is required to facilitate planned

WPAP and SCS construction activities in accordance with applicable provisions set forth in the EAPP rules as specified in *Title 30 of the Texas Administrative Code, Section 213 (30 TAC 213, effective April 24, 2008)*.

Topography and Drainage. Topographic information for the Project was obtained from the *Helotes, Texas Topographic Quadrangle Map* prepared by the United States Geological Survey (USGS, 2022) and 2-foot topographic contours obtained from the City of San Antonio (CoSA, 2015). These sources indicate that the natural surface topography may be characterized as gently sloping to the south and southwest. The 2-foot topographic contours obtained from CoSA are provided on the attached **Project Geologic Map** and indicate an approximate 10-12 foot drop in elevation (i.e., 1004 to 992 feet relative to mean sea level) from north to south across the Project. A review of U.S. Federal Emergency Management Agency (FEMA) Flood Insurance Rate Maps (FIRM, Map Nos. 48029C0215G and 48029C0220G) indicate that no part of the Project is located within the designated 100-year floodplain, although 100-year floodplain associated with Helotes Creek is located approximately to the west within the adjacent quarry property. Surface runoff across the Project generally occurs as sheetflow to the southwest with connection to existing storm water conveyances that discharge to existing water quality basins located within the Sandra Day O'Connor High School campus with ultimate discharge to Helotes Creek

Historical Property Use. Although research pertaining historical land use activities was beyond the scope of this assessment, historical aerial imagery was reviewed to evaluate past property conditions and the presence of lineations that could indicate the presence of normal faulting. The following aerial photographs from United Aerial Mapping and Google Earth™ were reviewed: 1981, 1995, 2002 through 2006, 2008, 2010, and 2012 through 2023. Below is a list of land development activities observed within the Project area in the aerial photographs.

- The high school property was undeveloped in the 1981 and 1995 aerial photographs.
- The high school facility was completely developed in the 2002 aerial photograph.
- The 2004 and 2008 aerial photographs indicate the addition of several structures near the southwest portion of the Project.
- The 2010 aerial photograph indicates a fenced-in asphalt parking area (i.e., band equipment staging) along the north extent of the Project

Classification of Recharge Features: As further described herein, 26 manmade recharge features were identified within Project boundaries, which include sanitary sewer lines, potable water lines, underground electric lines, gas lines, retention ponds, storm drain system, in addition to test holes. The significance of these features was assessed using definitions and guidance provided in *Instructions to Geologists (TCEQ-0585-Instructions, revised October 1, 2004)*. All features within the Project that met the criteria presented in this reference were mapped. The characteristics of all mapped features and the assessments of these features, as defined by the TCEQ, are presented in the attached **Geologic Assessment Table (TCEQ-0585)**.

Stratigraphy

As presented in the attached **Stratigraphic Column**, information pertaining to the lithologies and thickness of geologic units underlying the Project was adapted from Collins (2000). Published data referenced indicate

that the Project is underlain by the following geological formations (youngest to oldest): Quaternary Terrace Deposits (Qt), Del Rio Clay (Kdr) formation, Georgetown Formation (Kgt), and the Upper Edwards Limestone (Person Formation [Kep]) as presented on **Project Geologic Map**. These formations are described below.

- Qt is mapped primarily within the southwest portion of the assessment area that is located adjacent (i.e., west of the Project limits) to the floodplain for Helotes Creek. Qt consists of varying proportions of gravel, sand, silt, and clay sediments, which are predominantly limestone, dolomite, and chert.
- Kdr overlies the Georgetown Formation and consists of calcareous, blocky, gray clay that weathers light gray to yellowish-gray. This unit is typically considered as an upper confining unit for the Edwards Aquifer in the San Antonio Area (Maclay, 1995).
- Kgt typically consists of thin exposures (i.e., erosional remnants) of gray to tan marly or shaley dense limestone sometimes exhibiting significant iron staining. The total thickness of the Kgt is typically on the order of 10 feet or less in Bexar County. No erosional remnants of the Kgt within Project boundaries and immediate surrounding area were identified or in the geotechnical boring logs.
- The Kep, which underlies the Kgt, is commonly divided into three distinct members: (i) Cyclic and Marine Member, undivided – mudstone to packstone, grainstone, and chert; (ii) Leached and Collapsed Member, undivided - unit includes crystalline limestone, mudstone to grainstone, and chert; and (iii) Regional Dense Member - unit consists of dense, carbonate mudstone. The total thickness of the Kep is on the order of 180 to 224 feet. The uppermost or Cyclic and Marine member of the Kep represents the portion of the Edwards Limestone directly underlying the west portion of the Project to depths on the order of 80 to 100 feet. Based upon the work of Maclay (1995), this unit contains many open fractures and possesses low matrix permeability with total porosity on the order of 5 to 10%. Patchy outcrops of the weathered Kep were observed north of sheep/goat barn (i.e., Building Q).

Structure

The Project is located within the Balcones Fault Zone and as such, limestone strata exposed within the vicinity possess a distinct structural trend. This zone consists of a northeast-southwest trending, *en echelon* normal fault system, which juxtaposes Upper Cretaceous lithologies in the southeast with Lower Cretaceous lithologies in the northwest. As a result of this larger-scale, regional faulting, minor internal fault sequences and fractures exist within this zone, which follow the same structural trend and accommodate localized displacement, particularly within the extent of the EARZ.

In order to evaluate the presence of normal fault zones that could transect property boundaries, **RKI** reviewed historical aerial photographs and published maps. No faults were mapped within the Project limits and no evidence of structural features (e.g., lineations in vegetation, changes in soil type, fractured rock exposures, etc.) were observed during reconnaissance activities. Field observations are consistent with most recently published geological information for the Project vicinity (Collins, 2000).

Karst

Although weathered exposures of the Kep were observed, north of the goat/sheep barn (i.e., Building Q), there were no potential recharge features identified within Project boundaries that may be attributed to karstification of the underlying limestone terrain. Owing to the presence of soil cover and existing improvements, limestone strata of the Kep, which are prone to karst forming processes, are not present within the near-surface interval at the Project. Reconnaissance efforts did not indicate the presence or indirect evidence of natural recharge features that may be attributed to karstification of the underlying limestone terrain.

Manmade Features

As presented on the *Project Geologic Map*, 26 manmade features were identified that may potentially serve to enhance the transmission of surface runoff to the subsurface. The features consist of trenches for underground utilities including the following: sanitary sewer, potable water, electric, and natural gas. Additionally, manmade features include existing storm drain systems and stormwater basins, in addition to plugged geotechnical borings. All of these features meet the criteria for assessment as manmade features in bedrock. Information regarding the locations of the existing manmade features was taken from field observations, review of geotechnical borings logs (RKI, July 2023), and utility plans provided by KCI Technologies, Inc. (October 2023). The following features were identified:

- **Feature S-1** consists of interconnected trenches for a 6- to 8-inch existing sanitary sewer lines owned by San Antonio Water System (SAWS).
- **Feature S-2** consists of a trench for an existing sanitary sewer line.
- **Feature S-3** consists of interconnected trenches for existing 6- to 8-inch polyvinyl chloride (PVC) potable water lines owned by City Public Service (CPS) Energy.
- **Feature S-4** consists of interconnected trenches for an existing natural gas utility CPS Energy.
- **Feature S-5** consists of interconnected trenches for existing 1-1/4- to 4-inch electrical utility owned CPS Energy.
- **Features S-6, S-7, S-8, and S-10** consists of trenches for storm drain pipes that service O'Connor High School campus.

Although not directly observable, it is inferred that the subgrade trenches for these subgrade installations are backfilled in accordance with standard construction practices that include the use of structural fill soils (e.g., base course materials, limestone gravel, compacted clay soils, etc.) overlain by native or fill soils, depending upon location and surface improvements. The trenches were not observed in conjunction with any naturally-occurring recharge features. Although the backfilled trenches may exhibit somewhat greater relative infiltration rate than the surrounding soil/rock strata underlying the project boundaries, these manmade features are collectively classified as not sensitive, having a low potential of preferentially transmitting fluids into the Edwards Aquifer. This classification is based upon the point assignment criteria presented in the *Geologic Assessment Table (TCEQ-0585)* and professional judgment.

RKI identified two stormwater basins, **Features S-9** and **S-11** that treat stormwater originating within the high school campus (i.e., parking lot and agriculture barn area). The probability for rapid infiltration into the subsurface is considered low for these best management practices (BMPs) as basins are designed to capture, filter, and convey water downstream with typical detention times on the order of 24-72 hours. Additionally, a stormwater basin within the Edwards Aquifer Recharge Zone are typically required to have an impermeable liner. As such, these features are classified as not sensitive

Features S-12 through S-26 consist of geotechnical borings installed as part of the recent geotechnical engineering study in support of proposed improvements (**RKI**, 2023). These were reportedly installed to depths ranging from 8-1/2 to 39 feet, terminating in limestone of the Kep. No shallow groundwater was observed during drilling operations. These borings were plugged with granular bentonite immediately following drilling activities. These features are collectively classified as not sensitive as they have been plugged and no longer exist.

Potential for Fluid Migration to the Edwards Aquifer

Based on a review of Project geology, topography and drainage conditions, and the results of our mapping efforts, the overall potential for direct fluid migration (i.e., surface-derived flow) to the Edwards Aquifer via infiltration is considered to be low to moderate. The following assessment findings support this conclusion:

- There were no naturally-occurring recharge features identified within the Project area that may be attributed to karstification of the underlying limestone terrain. The majority of the Project is overlain by clay soils approximately 2 feet or greater in thickness with reported slow to moderate infiltration rates (i.e., Group D and B soils, respectively). Owing to soil cover and improvements, limited exposures of the Kep were observed.
- Manmade features present at the Project are collectively classified as not sensitive based on consideration of typical construction details and application of point assignment criteria and professional judgment.
- The Project is almost completely developed with impervious cover and landscaping improvements, which is expected to promote runoff to established water quality basins and limit infiltration.

References

- Barnes, V. L., 1974 Revised 1983, Geologic Atlas of Texas San Antonio Sheet; Bureau of Economic Geology, The University of Texas at Austin, Austin, Texas.
- Collins, Edward W., 2000, Geologic Map of the New Braunfels, Texas, 30 X 60 Minute Quadrangle: Geologic Framework of an Urban-Growth Corridor along the Edwards Aquifer, South-Central Texas: Bureau of Economic Geology, The University of Texas at Austin, Austin, Texas.
- Maclay, R. W., 1995, Geology and hydrogeology of the Edwards aquifer in the San Antonio area, Texas: U.S. Geological Survey Water Resources Investigations Report 95-4186, 64 p.
- Google Earth Pro, Version 7.3.6.9345. Aerial images: January 1995, July 2002, December 2003, February 2004, October 2005, December 2006, May 2008, January 2010, April and November 2012, February 2013, February 2014, January and December 2015, May 2016, January 2017, December 2018, November 2019, April 2020, October 2021, and January 2022.
- National Flood Insurance Program, 2010, Flood Insurance Rate Map, Bexar County, Texas and Incorporated Areas; U.S. Federal Emergency Management Agency, Map Nos. 48029C0215G and 48029C0220G.
- Raba Kistner, Inc. (RKI), 2023, *Geotechnical Engineering Study For O'Connor High School Agriculture Science and Technology Center. Project No.: ASA23-041-00*. Report dated July 25, 2023.
- Stein, W. G., and G. B. Ozuna, 1996, Geologic framework and hydrogeologic characteristics of the Edwards aquifer recharge zone, Bexar County, Texas: U.S. Geological Survey Water Resources Investigations Report 95-4186.
- Texas Commission on Environmental Quality (TCEQ) Edwards Aquifer Protection Program, 1998, Edwards Aquifer Recharge Zone Map, Helotes Quadrangle; TNRCC, September 1998.
- Texas Water Development Board (TWDB), Water Data Interactive (WDI) Groundwater Data Viewer, <https://www2.twdb.texas.gov/apps/WaterDataInteractive/GroundwaterDataViewer/?map=sdr>, accessed October 16, 2023.
- United Aerial Mapping (UAM), Aerial Imagery: May 11, 1981.
- United States Geological Survey (USGS), 2022, Helotes Quadrangle; USGS, Denver, Colorado.
- United States Department of Agriculture (USDA), 1962, Soil Survey of Bexar County, Texas; USDA / Soil Conservation Service / Texas Agricultural Experiment Station, Reissued June 1991
- United States Department of Agriculture (USDA), 1986, Urban Hydrology for Small Watersheds; USDA / Natural Resource Conservation Service, Technical Release (TR-55), June 1986.

ATTACHMENT D

**FEATURE POSITION TABLE
(GPS COORDINATES)**



PROJECT GEOLOGIC MAP

FEATURE POSITION TABLE
O' Connor High School Water Pollution Abatement Plan (WPAP) Modification
Helotes, Bexar County, Texas
 RKI Project No. ASF23-091-00

Feature Designation	Feature Type	Date Collected	North Latitude	West Longitude	UTM Northing (meters)	UTM Easting (meters)
S-1	Manmade feature in bedrock (Sanitary Sewer Line)	10/9/2023	29°33'33.77"N	98°41'15.54"W	3270003	530258
S-2	Manmade feature in bedrock (Sanitary Sewer Line)	10/9/2023	29°33'29.28"N	98°41'18.05"W	3269865	530190
S-3	Manmade feature in bedrock (Water Line)	10/9/2023	29°33'34.40"N	98°41'17.62"W	3270023	530202
S-4	Manmade feature in bedrock (Electric Line)	10/9/2023	29°33'34.52"N	98°41'16.40"W	3270027	530234
S-5	Manmade feature in bedrock (Gas Line)	10/9/2023	29°33'32.66"N	98°41'20.17"W	3269969	530133
S-6	Manmade feature in bedrock (Storm Drain)	10/9/2023	29°33'37.98"N	98°41'18.71"W	3270133	530172
S-7	Manmade feature in bedrock (Storm Drain)	10/9/2023	29°33'27.90"N	98°41'14.84"W	3269823	530277
S-8	Manmade feature in bedrock (Storm Drain)	10/9/2023	29°33'25.94"N	98°41'13.79"W	3269763	530305
S-9	Manmade feature in bedrock (Water Quality Pond A)	10/9/2023	29°33'26.38"N	98°41'17.33"W	3269976	530210
S-10	Manmade feature in bedrock (Storm Drain)	10/9/2023	29°33'27.40"N	98°41'22.13"W	3269807	530082
S-11	Manmade feature in bedrock (Water Quality Pond A)	10/9/2023	29°33'26.11"N	98°41'24.36"W	3269768	530022
S-12	MB (test hole B-1)	6/21/2023	29°33'27.17"N	98°41'20.02"W	3269800	530138
S-13	MB (test hole B-2)	6/21/2023	29°33'26.75"N	98°41'21.81"W	3269787	530090
S-14	MB (test hole B-3)	6/16/2023	29°33'32.38"N	98°41'19.75"W	3269960	530145
S-15	MB (test hole B-4)	6/16/2023	29°33'33.82"N	98°41'20.40"W	3270005	530127
S-16	MB (test hole B-5)	6/23/2023	29°33'36.66"N	98°41'18.07"W	3270092	530189
S-17	MB (test hole B-6)	6/22/2023	29°33'33.43"N	98°41'17.11"W	3269993	530215
S-18	MB (test hole B-7)	6/20/2023	29°33'32.25"N	98°41'16.64"W	3269957	530228
S-19	MB (test hole B-8)	6/16/2023	29°33'33.15"N	98°41'17.99"W	3269984	530192
S-20	MB (test hole B-9)	6/20/2023	29°33'32.12"N	98°41'17.31"W	3269953	530210
S-21	MB (test hole P-1)	6/21/2023	29°33'30.99"N	98°41'22.89"W	3269917	530060
S-22	MB (test hole P-2)	6/23/2023	29°33'34.29"N	98°41'21.18"W	3270019	530106
S-23	MB (test hole P-3)	6/20/2023	29°33'33.96"N	98°41'18.30"W	3270009	530184
S-24	MB (test hole P-4)	6/20/2023	29°33'31.10"N	98°41'17.01"W	3269921	530219
S-25	MB (test hole RW-1)	6/21/2023	29°33'26.52"N	98°41'20.54"W	3269780	530124
S-26	MB (test hole RW-2)	6/21/2023	29°33'27.23"N	98°41'18.29"W	3269802	530184

NOTES:

1. Geographic coordinates are presented Degrees, Minutes, Decimal Seconds
2. Reference Datum is NAD 83
3. Data were collected utilizing a Garmin GPS 60cx Global Positioning System.
4. Horizontal Accuracy: RMS Value < 3 meter ground resolution
5. GPS data was collected by Rick Sample (RKI Project Professional).
6. June 2023 GPS data was collected for the test holes by a RKI Geotechnical Professional.
7. GPS coordinates correlate to the points on the map for each feature.



Notes:

1. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
2. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
3. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
4. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
5. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
6. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
7. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
8. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
9. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
10. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
11. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
12. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
13. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
14. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
15. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
16. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
17. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
18. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
19. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
20. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
21. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
22. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
23. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
24. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.
25. This map is based on the most current data available from the Texas Geological Survey and the Texas Department of Transportation.

NOTE: This drawing is provided for illustration only. It is not to scale and is not suitable for design or construction purposes.



REVISIONS:

NO.	DATE	DESCRIPTION

PROJECT No.: ASF23-091-00
 ISSUE DATE: 10/16/2023
 DRAWN BY: LAW
 CHECKED BY: SRS
 REVIEWED BY: PAK



Sewage Collection System Application - Checklist (TCEQ-0582)

Organized Sewage Collection System Application

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Northside Independent School District

1. **Attachment A – SCS Engineering Design Report.** This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

Customer Information

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Jacob Villarreal, Executive Director of Construction and Engineering

Entity: Northside Independent School District

Mailing Address: 5900 Evers Road

City, State: San Antonio, TX

Zip: 78238

Telephone: (210) 397-8500

Fax: (210) 397-8500

Email Address: jacob.villarreal@nisd.net

The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
Practice Leader | Senior Associate

Texas Licensed Professional Engineer's Number: 105075

Entity: KCI Technologies

Mailing Address: 2806 W Bitters Rd Suite 218

City, State: San Antonio, TX

Zip: 78248

Telephone: (210) 641-9999

Fax: (210) 641-6440

Email Address: paul.mathis@kci.com

Project Information

4. Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):

- Residential: Number of single-family lots: 0
- Multi-family: Number of residential units: 0
- Commercial
- Industrial
- Off-site system (not associated with any development)
- Other: Educational

5. The character and volume of wastewater is shown below:

<u>100%</u> Domestic	<u>1500</u> gallons/day
_____ % Industrial	_____ gallons/day
_____ % Commingled	_____ gallons/day
Total gallons/day: <u>1500</u>	

6. Existing and anticipated infiltration/inflow is 0 gallons/day. This will be addressed by: _____.

7. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.

- The WPAP application for this development was approved by letter dated _____. A copy of the approval letter is attached.
- The WPAP application for this development was submitted to the TCEQ on 9/22/2023, but has not been approved.
- A WPAP application is required for an associated project, but it has not been submitted.
- There is no associated project requiring a WPAP application.

8. Pipe description:

Table 1 - Pipe Description

<i>Pipe Diameter(Inches)</i>	<i>Linear Feet (1)</i>	<i>Pipe Material (2)</i>	<i>Specifications (3)</i>
8	611	PVC	SDR 26

Total Linear Feet: 611

(1) Linear feet - Include stub-outs and double service connections. Do not include private service laterals.

(2) Pipe Material - If PVC, state SDR value.

(3) Specifications - ASTM / ANSI / AWWA specification and class numbers should be included.

9. The sewage collection system will convey the wastewater to the Leon Creek (name) Treatment Plant. The treatment facility is:

- Existing
 Proposed

10. All components of this sewage collection system will comply with:

- The City of Helotes and SAWS standard specifications.
 Other. Specifications are attached.

11. No force main(s) and/or lift station(s) are associated with this sewage collection system.
 A force main(s) and/or lift station(s) is associated with this sewage collection system and the **Lift Station/Force Main System Application** form (TCEQ-0624) is included with this application.

Alignment

12. There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.

13. There are no deviations from straight alignment in this sewage collection system without manholes.

Attachment B - Justification and Calculations for Deviation in Straight Alignment without Manholes. A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.

For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.

Manholes and Cleanouts

14. Manholes or clean-outs exist at the end of each sewer line(s). These locations are listed below: (Please attach additional sheet if necessary)

Table 2 - Manholes and Cleanouts

<i>Line</i>	<i>Shown on Sheet</i>	<i>Station</i>	<i>Manhole or Clean-out?</i>
1	C5.03 Of Enclosed Construction Plans	0+00	MH-1
1	C5.02 Of Enclosed Construction Plans	4+92.80	MH-2
1	C5.02 Of Enclosed Construction Plans	6+11.49	MH-3

<i>Line</i>	<i>Shown on Sheet</i>	<i>Station</i>	<i>Manhole or Clean-out?</i>
	Of		
	Of		
	Of		
	Of		
	Of		
	Of		
	Of		

15. Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.
16. The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
≥54	2000

- Attachment C – Justification for Variance from Maximum Manhole Spacing.** The maximum spacing between manholes on this project (for each pipe diameter used) is greater than listed in the table above. A justification for any variance from the maximum spacing is attached, and must include a letter from the entity which will operate and maintain the system stating that it has the capability to maintain lines with manhole spacing greater than the allowed spacing.

17. All manholes will be monolithic, cast-in-place concrete.
- The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

Site Plan Requirements

Items 18 - 25 must be included on the Site Plan.

18. The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = 400'.
19. The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten

feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.

20. Lateral stub-outs:

- The location of all lateral stub-outs are shown and labeled.
- No lateral stub-outs will be installed during the construction of this sewer collection system.

21. Location of existing and proposed water lines:

- The entire water distribution system for this project is shown and labeled.
- If not shown on the Site Plan, a Utility Plan is provided showing the entire water and sewer systems.
- There will be no water lines associated with this project.

22. 100-year floodplain:

- After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)
- After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 3 - 100-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
	of	to
	of	to
	of	to
	of	to

23. 5-year floodplain:

- After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concrete-lined channels constructed above sewer lines.)
- After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
	of	to
	of	to

<i>Line</i>	<i>Sheet</i>	<i>Station</i>
	of	to
	of	to

24. Legal boundaries of the site are shown.
25. The **final plans and technical specifications** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must be included on the Plan and Profile sheets.

26. All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.
- There will be no water line crossings.
- There will be no water lines within 9 feet of proposed sewer lines.

Table 5 - Water Line Crossings

<i>Line</i>	<i>Station or Closest Point</i>	<i>Crossing or Parallel</i>	<i>Horizontal Separation Distance</i>	<i>Vertical Separation Distance</i>
1	5+20	Crossing	0'	4'
2	7+69	Crossing	0'	4'
3	9+64	Crossing	0'	4'
4	10+55.54	Crossing	0'	4'

27. Vented Manholes:
- No part** of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.
- A portion** of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.
- A portion** of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.

- A portion of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.

Table 6 - Vented Manholes

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>

28. Drop manholes:

- There are no drop manholes associated with this project.
- Sewer lines which enter new or existing manholes or "manhole structures" higher than 24 inches above the manhole invert are listed in the table below and labeled on the appropriate profile sheets. These lines meet the requirements of 30 TAC §217.55(l)(2)(H).

Table 7 - Drop Manholes

<i>Line</i>	<i>Manhole</i>	<i>Station</i>	<i>Sheet</i>

29. Sewer line stub-outs (For proposed extensions):

- The placement and markings of all sewer line stub-outs are shown and labeled.
- No sewer line stub-outs are to be installed during the construction of this sewage collection system.

30. Lateral stub-outs (For proposed private service connections):

- The placement and markings of all lateral stub-outs are shown and labeled.
- No lateral stub-outs are to be installed during the construction of this sewage collection system.

31. Minimum flow velocity (From Appendix A)

- Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.

32. Maximum flow velocity/slopes (From Appendix A)

- Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.
- Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.** Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

Table 8 - Flows Greater Than 10 Feet per Second

<i>Line</i>	<i>Profile Sheet</i>	<i>Station to Station</i>	<i>FPS</i>	<i>% Slope</i>	<i>Erosion/Shock Protection</i>

33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provisions noted below have been made to protect against pipe displacement by erosion and/or shock under 30 TAC §217.53(l)(2)(B).

- Concrete encasement shown on appropriate Plan and Profile sheets for the locations listed in the table above.
- Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on appropriate Plan and Profile sheets for the locations listed in the table above.
- N/A

Administrative Information

- 34. The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
- 35. Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

Table 9 - Standard Details

<i>Standard Details</i>	<i>Shown on Sheet</i>
Lateral stub-out marking [Required]	N/A of
Manhole, showing inverts comply with 30 TAC §217.55(l)(2) [Required]	C2.02 and C2.03 of Enclosed Construction Plans
Alternate method of joining lateral to existing SCS line for potential future connections [Required]	C2.01 of Enclosed Construction Plans

Standard Details	Shown on Sheet
Typical trench cross-sections [Required]	C2.05 of Enclosed Construction Plans
Bolted manholes [Required]	C2.05 of Enclosed Construction Plans
Sewer Service lateral standard details [Required]	C2.05 of Enclosed Construction Plans
Clean-out at end of line [Required, if used]	N/A of
Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps]	N/A of
Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed]	C2.08 of Enclosed Construction Plans
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used]	C2.05 of Enclosed Construction Plans
Drop manholes [Required, if a pipe entering a manhole is more than 24 inches above manhole invert]	N/A of

36. All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
37. All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
- Survey staking was completed on this date: _____
38. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
39. Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards

Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: Paul A. Mathis

Date: 9/22/2023

Place engineer's seal here:



Signature of Licensed Professional Engineer:

Paul A. Mathis

Appendix A-Flow Velocity Table

Flow Velocity (Flowing Full) All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Table 10 - Slope Velocity

Pipe Diameter(Inches)	% Slope required for minimum flow velocity of 2.0 fps	% Slope which produces flow velocity of 10.0 fps
6	0.50	12.35
8	0.33	8.40
10	0.25	6.23
12	0.20	4.88
15	0.15	3.62
18	0.11	2.83

<i>Pipe Diameter(Inches)</i>	<i>% Slope required for minimum flow velocity of 2.0 fps</i>	<i>% Slope which produces flow velocity of 10.0 fps</i>
21	0.09	2.30
24	0.08	1.93
27	0.06	1.65
30	0.055	1.43
33	0.05	1.26
36	0.045	1.12
39	0.04	1.01
>39	*	*

**For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.*

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

Where:

v = velocity (ft/sec)

*n = Manning's roughness coefficient
(0.013)*

R_h = hydraulic radius (ft)

S = slope (ft/ft)

Attachment A

SCS Engineering Report

APPENDIX A
SEWAGE COLLECTION SYSTEM
ENGINEERING REPORT FOR PVC SDR 26 PIPE
MAX DEPTH OF 20 FEET

FLEXIBLE PIPE COMPUTATIONS

The computations which follow validate 8-inch diameter PVC SDR 26 pipe design for direct burial of sewer gravity systems to a depth of 20 feet. Included in the computations are calculations for long term deflection, buckling, wall crushing, and strain. The Handbook of PVC Pipe, Design, and Construction by the Uni-Bell PVC Pipe Association, Formulae, Tables, and Constants were used in preparing this report.

Pipe Characteristics (SDR 26 Pipe):

1. Average Burial Depth (6-20')
2. Outside Pipe Diameter (8")
3. Pipe Wall Thickness (**0.332"**)
4. Trench Width (2.5 to 2.7') (Approximate)
5. Modulus of Elasticity (400,000 psi)
6. Pipe Stiffness (115 psi)

$$W = 135 \text{ lb/cf (dry unit weight)} \times 1.06 \text{ (moisture content)}$$

$$= 143 \text{ lb/cf}$$

Prism Load Calculation:

$$W_c = H * W * B_c \quad \text{(Martson's Equation)}$$

Where:	W_c	=	Load on Conduit (lb/lf)
	W	=	Unit Weight of Backfill (143 lb/cf)
	H	=	Depth at Which Pressure is Desired (20 ft)
	B_c	=	Horizontal Width of Conduit (varies)

8-inch Pipe: (up to 20 feet)

$$W_c = (20 \text{ ft}) (143 \text{ lb/ft}^3) (0.70 \text{ ft}) = 2002 \text{ lb/ft}$$

or in terms of soil pressure

$$P = W * H = \frac{W_c}{B_c} = \frac{(2002 \text{ lb/ft})}{(0.70 \text{ ft})} = \frac{(2974 \text{ lb/ft})}{(1.04 \text{ ft})} = \frac{(4462 \text{ lb/ft})}{(1.56 \text{ ft})} = 2,860 \frac{\text{lb}}{\text{sf}}$$

$$P = \frac{2,860 \text{ lb/sf}}{144 \text{ in}^2/\text{sf}} = 19.9 \text{ psi}$$

Live Load:

From Table 6.6, and based on the H20 Highway Loading and the Holl Equation for Live Loads, at a 6 ft. depth,

$$\text{Live Load} = 1.39 \text{ psi (max)}$$

$$\text{Live Load} = 0 \text{ psi at a depth of 20 ft.}$$

Long Term Deflection Calculation:

Employing Spangler's Modified Deflection Formula, and incorporating a deflection lag factor of 1.0. Long Term Deflection is calculated as follows at a depth of 20 ft.

$$\frac{\Delta Y}{D} = \frac{DL * K * P + K * W_1}{[2E/3(DR-1)^3] + 0.061E_1}$$

Where,

$$P = \text{Prism Load, (19.9 psi at 20')}$$

$$K = \text{Bedding Constant, (0.096 for } 90^\circ) \text{ (See Table 7.2)}$$

$$W_1 = \text{Live Load, at 20 Foot Depth (0 psi)}$$

$$DR = \text{Dimension Ratio (SDR 26)}$$

$$E = \text{PVC Modulus of Elasticity (400,000 psi)}$$

E1 = Modulus of Soil Reaction, (400 psi at 20') (See Table 7.3, Unibell Handbook of PVC Pipe Design and Construction" for slight <85% proctor, 40% relative density

DL = Deflection Lag Factor (1.0)

Up to 20'

$$\frac{\Delta Y}{D} = \frac{(1.0)(0.096)(19.9)+(0.096)(0)}{[2(400,000)/(3(26-1)^3)]+0.061(400)}$$

$$\frac{\Delta Y}{D} = 4.61\% \text{ Long Term Deflection}$$

As compared to an allowable long term deflection of 5%.

4.61% < 5.00%, Therefore O.K.

It should be noted that the effective modulus of soil reaction equates to the bedding reaction modulus since the natural soil (in this case rock) can sustain greater lateral loads than the bedding material can normally produce.

Buckling Calculation:

Employing the Timoshenko Equation below, the Critical Buckling Pressure (P_{cr}) for a circular ring subjected to a uniform external pressure or internal vacuum can be found as follows:

$$P_{cr} = \frac{2 * E}{(1 - \nu^2)(DR - 1)^3}$$

Where "ν" is Poisson's ratio of unit lateral contraction to unit axial elongation, (0.38 for PVC conduits).

$$P_{cr} = \frac{2 (400,000)}{(1 - (0.38)^2)(26 - 1)^3}$$

And compensating for soil resistance to buckling, the True Buckling Pressure, (P_b), is

$$P_b = 1.15\sqrt{P_{cr} * E_1} = 1.15\sqrt{59.8 * 400} = 178 \text{ psi}$$

$H = P_b / W$ Calculated Depth of Buckling

$$H = P_b / W = \frac{178 \text{ psi} * 144 \text{ in}^2 / \text{ft}^2}{143 \text{ lb/ft}} = 179'$$

for a failure soil pressure depth of approximately 179'.

20' < 179' Therefore O.K.

Wall Crushing Calculation:

In accordance with White and Layer's Ring Compression Theory for design of buried flexible pipe, and assuming a highly compacted backfill or minimal deflection, wall crushing can be defined as follows:

$$\sigma_c = \frac{P_y * D}{2 * A} = \frac{\text{Yield Strength}}{\text{Safety Factor}}$$

Where,

σ_c = Compressive Stress (4,000 psi)

P_y = Prism Load (19.9 psi)

A = Cross Sectional Area of Conduit Wall Per Unit Length

D = Outside Pipe Diameter (varies)

Solve for Cross Sectional Area of Conduit Wall Per Unit Length:
8-inch:

$$A = 0.323\text{in} * 12\text{in}/\text{ft}$$

$$A = 3.876\text{in}^2/\text{ft}$$

Solving for the Allowable P_y ,

8-inch:

$$P_y = \frac{\sigma_c * 2 * A}{D} = \frac{(4,000 \text{ lb}/\text{in}^2)(2)(3.876 \text{ in}^2/\text{ft})(1 \text{ ft}/12\text{in})}{8.4 \text{ in}} = 307.6 \text{ psi}$$

$H = P_y / W =$ Calculated Depth of Wall Crushing

$$H = \frac{(307.6 \text{ psi})(144 \text{ in}^2/\text{sf}^2)}{143 \text{ lb}/\text{cf}} = 310$$

for a crushing failure depth of approximately 310'.

$$20' \leq 310', \text{ O.K.}$$

Strain Calculation:

Strain is caused by the flexure of the pipe as it deforms and by hoop stress in the pipe wall. Strain is calculated as follows at a depth of 20 ft.:

$$\epsilon_h = \frac{P * D}{2 * t * E}, \text{ Where } \epsilon_h \text{ is the maximum hoop strain a 20 foot depth.}$$

8-inch:

$$\epsilon_h = \frac{(19.9)(8.4)}{2(0.323)(400,000)} = 0.00065 \text{ in}/\text{in}$$

$$\epsilon_f = \frac{t}{D} = \frac{[3 * \Delta Y / D]}{[1 - 2(\Delta Y / D)]}$$

Where ϵ_f is the maximum strain a pipe wall due to ring deflection or flexure

8-inch:

$$\epsilon_r = \frac{t}{D} = \frac{[3(.0461)]}{[1-2(.0461)]} = 0.0059 \text{ in/in}$$

In a buried pipeline, these strain components act simultaneously

$$\epsilon = \epsilon_r + \epsilon_h = 0.0066 \text{ in/in}$$

Deflection test samples have experienced a pipe wall strain of up to 0.025 in/in and have not “showed any cracks or failures”. Based on information from Uni-Bell PVC Pipe Association.

0.0066 in/in < 0.025 in/in Therefore O.K.

JOINTING MATERIAL

All polyvinyl chloride(PVC) sewer pipe and fittings shall be joined by a bell and spigot assembly and shall incorporate a rubber compression ring gasket at the pipe and pipe to manhole entrance interface.

All joints shall be in compliance with the requirements of ASTM D-3212. All gaskets shall be lock-in type meeting ASTM F-477. Solvent cement joints will not be permitted. Pipe and fittings shall conform to ASTM D-3034.

Pressure rated conduit specified for the project shall, at a minimum, conform to ASTM D2241 while fittings will meet or exceed ASTM D-3139.

PIPE AND MANHOLE TESTING

A low pressure air test and mandrel deflection test will be performed in accordance with TNRCC 317.2 (a) (4) and City of San Antonio Standard Specifications for Public Works Construction (1993 Rev.). Mandrel design and sizing information is contained within the standard detail sheet at the end of the submitted plans.

A manhole vacuum test specification has been included with this SCS submittal. (See SCS Exhibit Section for details.)

BEDDING AND BACKFILL

A minimum of 6-inch and maximum of 12-inch space shall be allowed between the outside diameter of the pipe and the trench wall.

Bedding and initial backfill material selection and installation will be carried out in accordance with ASTM D-2321 and applicable governing procedures contained within the City of San Antonio Standard Specifications for Public Works Construction (1993 Rev.).

For pipes at depths greater than 20', backfill must comply with San Antonio Water System Specification 804.4.

Secondary backfill, from a point 1 foot above the pipe to the finished surface, will be comprised of suitable material removed during excavation which is smaller than 6-inches in diameter. Brush, debris, and deleterious materials shall not be utilized as a backfilling material.

Trench compaction will be carried out in accordance with the City of Helotes Standard Specifications for Public Work Construction (1993 rev.).

Typical trench and pipe scenarios are addressed within the standard detail sheet included at the end of the design plans.

Attachment E

Construction Plans

SITE DESCRIPTION

PROJECT LOCATION: **SOUTH/EASTWEST SIDE OF THE EXISTING CAMPUS OF O'CONNOR HIGH SCHOOL, LOCATED AT 12021 LEBLANC ROAD, HOUSTON, TX 77023.**

PROJECT DESCRIPTION: **CONSTRUCTION OF ADDITIONAL SCHOOL BUILDINGS, PARKING, SIDEWALK, UTILITIES, AND DRAINAGE STRUCTURES, IN ADDITION, DEMOLITION OF AN EXISTING BUILDING, NEW DRIVE LANES, NEW PARKING LOTS, NEW WATER QUALITY BARR.**

MAJOR SOIL DISTURBING ACTIVITIES: **SITE GRADING, UTILITY AND DRAINAGE CONSTRUCTION, PAVEMENTS AND FLATWORK, AND FOUNDATION CONSTRUCTION.**

TOTAL PROJECT AREA: **~5.8 ACRES**

TOTAL AREA TO BE DISTURBED: **~5.8 ACRES**

WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): **0.70**

WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): **0.79**

EXISTING CONDITION OF SOIL & VEGETATIVE COVER: **NATIVE GRASS WITH TREES IN UNDEVELOPED AREAS AND SOME PREVIOUSLY DEVELOPED AREAS THAT HAVE PAVED, EXPOSED ABOUT 67% VEGETATED COVER WITH GRASSY CHANNELS, WATER QUALITY BARRS, VEGETATED TIE-UPS, AND GRAVE LANDSCAPE AREAS.**

NAME OF RECEIVING WATERS: **HELORES CREEK**

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES

- TEMPORARY SEEDING
- PERMANENT PLANTING, SOODING OR SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- SLOPE DICES
- PRESERVATION OF NATURAL RESOURCES

OTHER: _____

STRUCTURAL PRACTICES

- SALT FENCES
- RAY BARRS
- ROCK BARRS
- DIVERSION, INTERCEPTOR, OR PERMETER DICES
- DIVERSION, INTERCEPTOR, OR PERMETER DRALES
- DIVERSION DICE AND DRALE COMBINATIONS
- PIPE SLOPE DRAINS
- PAVED FLUMES
- ROCK BARRS AT CONSTRUCTION EXIT
- TAMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BARRS
- STORM INLET SEDIMENT TRAP
- STORM OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM BARRS
- VELOCITY CONTROL DEVICES
- GRAVEL FILTER BAGS

OTHER: _____

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

PHASE I

1. INSTALLATION OF SWEEP MEASURES

PHASE II

1. SITE CLEARING AND GRADING

PHASE III

FOUNDATIONS, DRAINAGE AND UTILITIES

PHASE IV

1. UTILITIES AND PARKING LOT CONSTRUCTION

2. BUILDING CONSTRUCTION

PHASE V

1. VEGETATION

STORM WATER MANAGEMENT: **TEMPORARY AND PERMANENT MEASURES TO PREVENT SEDIMENT TRANSPORT DOWNSTREAM.**

NON-STORM WATER DISCHARGE: **N/A**

OTHER EROSION AND SEDIMENT CONTROLS

MAINTENANCE: **All erosion and sediment controls will be maintained in good working order. If a repair is necessary, it will be done at the earliest date possible, but no later than 7 calendar days after the necessary amount of work has been completed to prevent further damage from heavy equipment. The areas subject to drainage shall have priority followed by those protecting storm sewer inlets.**

INSPECTION: **An inspection will be performed by the owner or contractor's representative every week or so after every half inch of rain (as recorded on a non-weather rain gauge) to be located at the Project Site. An Inspection and Maintenance Report will be made and each inspection. Based on the inspection results, the controls shall be revised per the Inspection Report.**

WASTE MATERIALS: **All waste materials will be collected and stored in a securely fenced metal dumpster. The dumpster will meet all state and local waste management regulations. All trash and construction debris from the site will be deposited in the dumpster. The dumpster will be emptied as necessary or as required by local regulations and the trash will be hauled to a local dump. No construction waste material will be buried on site.**

HAZARDOUS WASTE (INCLUDING SPILL REPORTING): **As a minimum, any products in the following categories are considered to be hazardous: paints, oils, the cleaning, masonry surfaces, cleaning solvents, sealants, products, chemical additives for asphalt or concrete curing compounds & additives. In the event of a hazardous material spill, the spill coordinator shall be contacted immediately.**

SANITARY WASTE: **All sanitary waste will be collected from portable units as necessary, or as required by local regulations by a Licensed Sanitary Waste Management Contractor.**

OFFSITE VEHICLE TRACKING

- HAUL ROADS PREPARED FOR DIRT CONTROL
- LOADED WALK TRUCKS TO BE COVERED WITH TARPAULIN
- STABILIZED CONSTRUCTION ENTRANCE

PERMITS

REMARKS: **Discard areas, sidewalks, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Discard areas shall not be located in any wetland, waterway, or streambed. Construction, storage areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of sediments. All entrance shall be cleared as soon as practicable of temporary embankment, temporary bridges, mudding, felsework, piping, debris or other obstructions placed during construction operations that are not a part of the finished work.**

CONTRACTOR CERTIFICATION

I hereby certify under penalty of perjury that the information and all attachments were prepared under my direction or supervision in accordance with the requirements of this permit and that I am a duly licensed professional engineer and registered in the State of Texas. I declare that the information provided in this permit application is true and correct to the best of my knowledge and belief. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas.

SIGNATURE: _____ DATE: _____

CONTRACTOR CERTIFICATION

I hereby certify under penalty of perjury that the information and all attachments of the permit have been prepared under my direction or supervision in accordance with the requirements of this permit and that I am a duly licensed professional engineer and registered in the State of Texas. I declare that the information provided in this permit application is true and correct to the best of my knowledge and belief. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas. I understand that any false information provided in this permit application may result in the denial of this permit and may constitute a criminal offense under the laws of the State of Texas.

SIGNATURE (Contractor): _____ DATE: _____

KCI TECHNOLOGIES, INC.
 1222 LEBLANC ROAD, HOUSTON, TX 77023
 (281) 460-1000
 www.kci.com

KCI TECHNOLOGIES
 PERMITTING AND EROSION CONTROL SERVICES

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

CONSTRUCTION/PERMIT DOCUMENTS






KARLSEN BOONHAIN GARCIA
 PROJECT MANAGER
 (281) 460-1000

Project No. T62301481
 Drawn By: **ENC**
 Date By: **11/AM**
 Date Issued: **09/06/23**

Revisions:




SHPPP NOTES

C2.00




GRAVEL FILTER BASIS

CONSTRUCTION EXIT - TYPE 1



TEMPORARY SEDIMENT CONTROL FENCE


1. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
2. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
3. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
4. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
5. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
6. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
7. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
8. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
9. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
10. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
11. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
12. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
13. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
14. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
15. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
16. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
17. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
18. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
19. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.
20. THE FENCE SHALL BE CONSTRUCTED TO PREVENT EROSION AND SEDIMENTATION FROM THE CONSTRUCTION SITE FROM ENTERING ADJACENT AREAS.



CONSTRUCTION/PERMIT DOCUMENTS

PROJECT NO.	150001
DATE	08/11/2011
DRAWN BY	ARCH
CHECKED BY	ARCH
DATE	08/11/2011
SCALE	AS SHOWN
PROJECT NAME	AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
PROJECT ADDRESS	12221 LESLIE ROAD, HELOTES, TX 78023
PROJECT CLIENT	KCI TECHNOLOGIES, INC.
PROJECT CONTACT	ARCH
PROJECT PHONE	(512) 464-6464
PROJECT FAX	(512) 464-6464
PROJECT EMAIL	ARCH@KCI.COM
PROJECT WEBSITE	WWW.KCI.COM
PROJECT ADDRESS	1500 W 10 WEST SUITE 300 SAN ANTONIO, TEXAS 78205-0357
PROJECT PHONE	(214) 516-0800
PROJECT FAX	(214) 516-6464
PROJECT EMAIL	ARCH@KCI.COM
PROJECT WEBSITE	WWW.KCI.COM



C2.02



AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023





SITE DIMENSION CHECK NOTES

- 1) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 2) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 3) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 4) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 5) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 6) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 7) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 8) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 9) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 10) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 11) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 12) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 13) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 14) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 15) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 16) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 17) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 18) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 19) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 20) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 21) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 22) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 23) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 24) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 25) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 26) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 27) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 28) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 29) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 30) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 31) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 32) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 33) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 34) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 35) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 36) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 37) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 38) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 39) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 40) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 41) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 42) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 43) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 44) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 45) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 46) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 47) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 48) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 49) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 50) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 51) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 52) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 53) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 54) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 55) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 56) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 57) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 58) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 59) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 60) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 61) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 62) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 63) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 64) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 65) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 66) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 67) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 68) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 69) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 70) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 71) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 72) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 73) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 74) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 75) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 76) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 77) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 78) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 79) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 80) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 81) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 82) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 83) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 84) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 85) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 86) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 87) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 88) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 89) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 90) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 91) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 92) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 93) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 94) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 95) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 96) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 97) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 98) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 99) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE
- 100) 1'00" FROM WEST SIDE OF EXISTING CONC. DRIVE

	KCI TECHNOLOGIES, INC. 11500 W. 10 WEST, SUITE 300 SAN ANTONIO, TEXAS 78204-0157 PHONE: (214) 541-6800 FAX: (214) 541-6443 REGISTRATION #F-10573 #F101943-03	DESIGNER: PARR DRAWN BY: LANG APPROVED: PARR JOB NO.: 7000014001	
	THE SEAL, APPROVED BY THE BOARD OF ENGINEERING EXAMINERS OF THE STATE OF TEXAS, IS VALID FOR THE STATE OF TEXAS ONLY.		
	NO EXPIRATION DATE.		
	DATE		

CONSTRUCTION/PERMIT DOCUMENTS


C3.00

OWNER: ARCHITECT: ENGINEER:		KAARLSEN NOONAN BITTMANN GARCIA
-----------------------------------	--	--

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES


NORTHERN HEMISPHERE SCHOOL DISTRICT

12221 LESLIE ROAD, HELOTES, TX 78023



SEE MATCH LINE SHEET C303

SEE MATCH LINE SHEET C304



CONSTRUCTION/PERMIT DOCUMENTS

C302

DATE: 11/11/2011	PROJECT: AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS
DRAWN BY: J. KAARLSEN	CHECKED BY: J. KAARLSEN
DESIGNED BY: J. KAARLSEN	APPROVED BY: J. KAARLSEN
SCALE: AS SHOWN	

INTEGRITY ARCH
 KAARLSEN
 NOONAN
 RITTMANN
 GARCIA
 12221 LESLIE ROAD, HELOTES, TEXAS 78023
 PH: 512.941.4444
 FAX: 512.941.4444

KCI TECHNOLOGIES, INC.
 1100 W. 10 WEST, SUITE 300
 SAN ANTONIO, TEXAS 78203-0337
 PHONE: (210) 441-0000
 FAX: (210) 541-6443
 REGISTRATION #1-10573 #101943-03


OWNER: PAM
DESIGN: LNO
APPROVE: PAM
APP NO: 708001401




AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023





SHEET MATCHLINE SHEET C3.02



GENERAL NOTE:
 ALL IMPROVEMENTS SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE TEXAS STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

LEGEND:

- PROPOSED
- EXISTING
- CONCRETE
- ASPHALT
- GRAVEL
- LIGHT BENT ASPHALT PAVEMENT
- GRAVEL WITH ASPHALT PAVEMENT
- SEE SHEET C3.01 FOR GRAVEL DRIVE

SCALE: 1/8" = 1'-0" (SEE SHEET C3.01 FOR SHEET C3.02 FOR THE AREA)

KCI TECHNOLOGIES, INC.
 11550 W. 16 WEST, SUITE 306
 SAN ANTONIO, TEXAS 78240-0337
 PHONE: (210) 541-9449 FAX: (210) 541-9445
 REGISTRATION #P-10573 #P151943-83

DESIGNED BY: PAM
DRAWN BY: LWO
CHECKED BY: PAM
DATE: 04.06.2011



CONSTRUCTION/PERMIT DOCUMENTS



C3.03

	KAARLSEN NOONAN RITTIMANN GARCIA CIVIL ENGINEERS AND ARCHITECTS 2122 W. LAMAR STREET SUITE 200 AUSTIN, TEXAS 78705
--	--

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023





CONSTRUCTION/PERMIT DOCUMENTS

C304

GENERAL
ALTERNATE PLAN

Project No.	1500
Sheet No.	304
Date	09/05/2003
Client	KCI TECHNOLOGIES, INC.
Contract No.	
Contract Date	
Contract Value	
Contract Status	
Contract Description	
Contract Location	

KAARLSEN
NOONAN
PITTMANN
GARCIA

CONSTRUCTION AND PROJECT MANAGEMENT SERVICES

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES



KCI TECHNOLOGIES, INC.
1100 N 10 WEST, SUITE 300
SAN ANTONIO, TEXAS 78228-0327
PHONE: (210) 943-8989
FAX: (210) 943-6663
REGISTRATION #1-18753 | #121943-63

DESIGNED BY: PAM
DRAWN BY: LNC
APPROVED: PAM



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY:
PAUL B. BAHR, P.E.
NO. #056076
ON **SEPTEMBER 06, 2003**
DATE

N
NORTHERN HEBBESBERRY SCHOOL DISTRICT



CONSTRUCTION/PERMIT DOCUMENTS


C4.00

DATE	DESCRIPTION

ARCH
 KAARLSEN
 NOGNAN
 RITTMANN
 GARCIA
 ARCHITECTS
 12221 LESLIE ROAD, HELOTES, TX 78023
 TEL: 512.941.4444
 FAX: 512.941.4444



KCI TECHNOLOGIES, INC.
 11500 W. 10TH WEST, SUITE 300
 SAN ANTONIO, TEXAS 78249-0337
 PHONE: (210) 541-6666
 FAX: (210) 541-6665
 REGISTRATION #1-10573 / #101943-03

DESIGNED BY	PARR
DRAWN BY	LARG
CHECKED BY	PARR
DATE	08/11/2011



AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
 12221 LESLIE ROAD, HELOTES, TX 78023





KCI TECHNOLOGIES, INC.
 11550 N. 10 WEST, SUITE 300
 SAN ANTONIO, TEXAS 78230-0557
 PHONE: (210) 541-6660
 FAX: (210) 541-6665
 REGISTRATION #F-10573 / #151943-03

ENGINEER OF RECORD
ARCHITECT OF RECORD
REGISTERED PROFESSIONAL ENGINEER
REGISTERED PROFESSIONAL ARCHITECT
STATE OF TEXAS
NO. 1000014801

CONSTRUCTION/PERMIT DOCUMENTS

INTEGRAL ARCH
 KAARLSEN
 NOONAN
 RITTMANN
 GARCIA
 2000 BANCROFT FRO KCI2
 HOUSTON, TEXAS 77057
 212.944.1111
 #151943-03


ARCHITECT OF RECORD
 STATE OF TEXAS
 NO. 1000014801

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
 12221 LESLIE ROAD, HELOTES, TX 78023

THE SEAL OFFICER OF THE BOARD OF ARCHITECTS AND ENGINEERS OF THE STATE OF TEXAS
 REGISTERED PROFESSIONAL ENGINEER
 REGISTERED PROFESSIONAL ARCHITECT
 STATE OF TEXAS
 NO. 1000014801

C4.01

DATE	DESCRIPTION



CONSTRUCTION/PERMIT DOCUMENTS

PROJECT NO.	DATE	BY	CHECKED

INTEGRITY ARCH

KAARLSEN
NOONAN
RITTMANN
GARCIA

OWNER: SANDRA DAY O'CONNOR HS
PROJECT: AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
12221 LESLIE ROAD, HELOTES, TX 78023

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023

KCI TECHNOLOGIES, INC.

1100 N. 10 WEST, SUITE 300
SAN ANTONIO, TEXAS 78201-0107
PHONE: (210) 491-0000
FAX: (210) 541-6463
REGISTRATION #1-10573 / #101943-03

OWNER: PAM
DESIGNER: LNO
APPROVER: PAM


AM #1-708801481

THE SEAL APPROVED BY THE BOARD OF ARCHITECTS OF THE STATE OF TEXAS

REGISTERED ARCHITECT


NORTH HEBBARD SCHOOL DISTRICT

C4.02



SEE MATCHLINE SHEET C4.02

- LEGEND:**
- PROPOSED BUILDING FOOTPRINT
 - PROPOSED BUILDING EXTERIOR WALL
 - PROPOSED SIDEWALK
 - PROPOSED DRIVEWAY
 - PROPOSED CURB
 - PROPOSED PAVEMENT
 - PROPOSED GRASS
 - PROPOSED ASPHALT
 - PROPOSED CONCRETE
 - PROPOSED WATER TREATMENT PLANT
 - PROPOSED WATER TREATMENT PLANT EXTERIOR WALL
 - PROPOSED WATER TREATMENT PLANT INTERIOR WALL
 - PROPOSED WATER TREATMENT PLANT FLOOR
 - PROPOSED WATER TREATMENT PLANT ROOF
 - PROPOSED WATER TREATMENT PLANT CEILING
 - PROPOSED WATER TREATMENT PLANT LIGHTING
 - PROPOSED WATER TREATMENT PLANT VENTILATION
 - PROPOSED WATER TREATMENT PLANT MECHANICAL
 - PROPOSED WATER TREATMENT PLANT ELECTRICAL
 - PROPOSED WATER TREATMENT PLANT TELECOMMUNICATIONS
 - PROPOSED WATER TREATMENT PLANT SECURITY
 - PROPOSED WATER TREATMENT PLANT FURNITURE
 - PROPOSED WATER TREATMENT PLANT FIXTURES
 - PROPOSED WATER TREATMENT PLANT EQUIPMENT
 - PROPOSED WATER TREATMENT PLANT SUPPLIES
 - PROPOSED WATER TREATMENT PLANT MATERIALS
 - PROPOSED WATER TREATMENT PLANT LABOR
 - PROPOSED WATER TREATMENT PLANT SUBCONTRACTORS
 - PROPOSED WATER TREATMENT PLANT PERMITS
 - PROPOSED WATER TREATMENT PLANT INSURANCE
 - PROPOSED WATER TREATMENT PLANT BONDING
 - PROPOSED WATER TREATMENT PLANT SCHEDULING
 - PROPOSED WATER TREATMENT PLANT RISK MANAGEMENT
 - PROPOSED WATER TREATMENT PLANT QUALITY CONTROL
 - PROPOSED WATER TREATMENT PLANT SAFETY
 - PROPOSED WATER TREATMENT PLANT ENVIRONMENTAL
 - PROPOSED WATER TREATMENT PLANT HISTORIC PRESERVATION
 - PROPOSED WATER TREATMENT PLANT ARCHITECTURAL
 - PROPOSED WATER TREATMENT PLANT INTERIOR DESIGN
 - PROPOSED WATER TREATMENT PLANT LANDSCAPE ARCHITECTURE
 - PROPOSED WATER TREATMENT PLANT CIVIL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT ELECTRICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT MECHANICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT PLUMBING ENGINEERING
 - PROPOSED WATER TREATMENT PLANT CHEMICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT ENVIRONMENTAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT INDUSTRIAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT METALLURGICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AEROSPACE ENGINEERING
 - PROPOSED WATER TREATMENT PLANT NUCLEAR ENGINEERING
 - PROPOSED WATER TREATMENT PLANT BIOMEDICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AGRICULTURAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT MARINE ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AERONAUTICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT ASTRONAUTICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT CHEMICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT ENVIRONMENTAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT INDUSTRIAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT METALLURGICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AEROSPACE ENGINEERING
 - PROPOSED WATER TREATMENT PLANT NUCLEAR ENGINEERING
 - PROPOSED WATER TREATMENT PLANT BIOMEDICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AGRICULTURAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT MARINE ENGINEERING
 - PROPOSED WATER TREATMENT PLANT AERONAUTICAL ENGINEERING
 - PROPOSED WATER TREATMENT PLANT ASTRONAUTICAL ENGINEERING



KCI TECHNOLOGIES, INC.
 1100 W. 10th Street, Suite 300
 San Antonio, Texas 78203-0337
 Phone: (214) 341-6666
 Fax: (214) 341-6665
 Registration #10573 #101943-03

DESIGNED BY	PAM
DRAWN BY	LAW
CHECKED BY	PAM
DATE	04/03/2011



CONSTRUCTION/PERMIT DOCUMENTS


C4.03

INTEGRITY ARCH
 KAARLSEN
 NOONAN
 RITTMANN
 GARCIA
 1000 BANCROFT FRO K02
 HOUSTON TEXAS 77002
 2820 WILLOW
 HOUSTON TEXAS 77002

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023






A-1

ASPHALTIC PAVEMENT SECTION




A-2

CONCRETE PAVEMENT SECTION



A-3

PAVEMENT JUNCTION DETAILS



A-4


CONCRETE/ASPHALT PAVEMENT JUNCTION DETAIL



A-5


CONCRETE FLATWORK

1. THE 4" MIN. 100% ASPHALT, 4" MIN. 90% ASPHALT, 4" MIN. 80% ASPHALT, 4" MIN. 70% ASPHALT, 4" MIN. 60% ASPHALT, 4" MIN. 50% ASPHALT, 4" MIN. 40% ASPHALT, 4" MIN. 30% ASPHALT, 4" MIN. 20% ASPHALT, 4" MIN. 10% ASPHALT, AND 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
2. THE 4" MIN. 100% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
3. THE 4" MIN. 90% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
4. THE 4" MIN. 80% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
5. THE 4" MIN. 70% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
6. THE 4" MIN. 60% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
7. THE 4" MIN. 50% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
8. THE 4" MIN. 40% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
9. THE 4" MIN. 30% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
10. THE 4" MIN. 20% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
11. THE 4" MIN. 10% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
12. THE 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.




A-6

CONCRETE SIDEWALK




A-7

CONCRETE SIDEWALK ADJOINING CURB SECTION




A-8

SIDEWALK ADJACENT TO BUILDING



A-9

SIDEWALK ADJACENT TO COVERED WALK



A-10

CONCRETE PAVEMENT CONTROL JOINT DETAIL


1. THE 4" MIN. 100% ASPHALT, 4" MIN. 90% ASPHALT, 4" MIN. 80% ASPHALT, 4" MIN. 70% ASPHALT, 4" MIN. 60% ASPHALT, 4" MIN. 50% ASPHALT, 4" MIN. 40% ASPHALT, 4" MIN. 30% ASPHALT, 4" MIN. 20% ASPHALT, 4" MIN. 10% ASPHALT, AND 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
2. THE 4" MIN. 100% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
3. THE 4" MIN. 90% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
4. THE 4" MIN. 80% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
5. THE 4" MIN. 70% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
6. THE 4" MIN. 60% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
7. THE 4" MIN. 50% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
8. THE 4" MIN. 40% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
9. THE 4" MIN. 30% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
10. THE 4" MIN. 20% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
11. THE 4" MIN. 10% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
12. THE 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.

A-11




EDGE OF PAVEMENT (NO CURB)

N.T.S.




A-12

SIDEWALK AT ASPHALT




A-13

CONCRETE PAVEMENT COVERED WALK DETAIL (6" CURB)




A-14

CONCRETE PAVEMENT COVERED WALK DETAIL (FLUSH CURB)



A-15

PAVEMENT EXPANSION JOINT SMOOTH DOWEL




A-16

SIDEWALK DRAIN AND COVER - PRIVATE WORK


1. THE 4" MIN. 100% ASPHALT, 4" MIN. 90% ASPHALT, 4" MIN. 80% ASPHALT, 4" MIN. 70% ASPHALT, 4" MIN. 60% ASPHALT, 4" MIN. 50% ASPHALT, 4" MIN. 40% ASPHALT, 4" MIN. 30% ASPHALT, 4" MIN. 20% ASPHALT, 4" MIN. 10% ASPHALT, AND 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
2. THE 4" MIN. 100% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
3. THE 4" MIN. 90% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
4. THE 4" MIN. 80% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
5. THE 4" MIN. 70% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
6. THE 4" MIN. 60% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
7. THE 4" MIN. 50% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
8. THE 4" MIN. 40% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
9. THE 4" MIN. 30% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
10. THE 4" MIN. 20% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
11. THE 4" MIN. 10% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.
12. THE 4" MIN. 0% ASPHALT SHALL BE PLACED IN THE ORDER SHOWN.

N.T.S.



A-17

CONCRETE WHEEL STOP



A-18

CONCRETE WHEEL STOP

KCI TECHNOLOGIES, INC.
1500 W. 10TH STREET, SUITE 300
SAN ANTONIO, TEXAS 78205-0357
PHONE: (214) 594-6600
FAX: (214) 541-6443
REGISTRATION #1-0573 #103493-03

DESIGNED BY: PAM
DRAWN BY: LNC
APPROVED: PAM
JOB NO: 762301481



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY: P. A. M., P.E. NO. 105075
ON SEPTEMBER 06, 2003 DATE




AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023


CONSTRUCTION/PERMIT DOCUMENTS

PROJECT NO.	10000000000000000000
DATE	09/06/03
SCALE	N.T.S.
DRAWN BY	LNC
CHECKED BY	PAM
APPROVED BY	PAM
DATE	09/06/03
PROJECT NAME	AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
PROJECT LOCATION	12221 LESLIE ROAD, HELOTES, TX 78023
PROJECT OWNER	NORTHWEST INDEPENDENT SCHOOL DISTRICT
PROJECT ARCHITECT	KCI TECHNOLOGIES, INC.
PROJECT ENGINEER	P. A. M., P.E.
PROJECT SURVEYOR	
PROJECT GEOLOGIST	
PROJECT CIVIL ENGINEER	
PROJECT ELECTRICAL ENGINEER	
PROJECT MECHANICAL ENGINEER	
PROJECT PLUMBING ENGINEER	
PROJECT ROOFING ENGINEER	
PROJECT STRUCTURAL ENGINEER	
PROJECT THERMAL ENGINEER	
PROJECT TRANSPORTATION ENGINEER	
PROJECT WATER RESOURCES ENGINEER	
PROJECT WIND ENGINEER	
PROJECT ENVIRONMENTAL ENGINEER	
PROJECT SAFETY ENGINEER	
PROJECT SPECIALTY ENGINEER	
PROJECT OTHER ENGINEER	
PROJECT OTHER PROFESSIONAL	
PROJECT OTHER	


C4.04




B-1 PUBLIC WHEEL CHAIR RAMPS
SCALE




B-5 MACHINE LAID CURB COMMERCIAL USE
SCALE



B-2 18" RIBBON CURB DETAIL
SCALE




B-6
SCALE




B-7
SCALE


B-12 CONCRETE PAD TURN DOWN WHERE LANDSCAPE IS LOWER CONCRETE PAD WITH HANDRAIL/FENCE
SCALE 1/8"




B-3
SCALE




B-8
SCALE




B-4
SCALE




B-9
SCALE




B-11
SCALE 1/8"



B-10
SCALE



C-1 GATES/CHAIN LINK FENCE DETAIL
SCALE



KCI TECHNOLOGIES, INC.
1100 W. 10 WEST SUITE 300
SAN ANTONIO, TEXAS 78201-0307
PHONE: (210) 541-6600
FAX: (210) 541-6660
REGISTRATION #1-10573 #101943-03

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
12221 LESLIE ROAD, HELOTES, TX 78023

CONSTRUCTION/PERMIT DOCUMENTS

C4.05

DATE: 11/11/2024

PROJECT: AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

CLIENT: KCI TECHNOLOGIES, INC.

DESIGNER: KCI TECHNOLOGIES, INC.

CHECKER: KCI TECHNOLOGIES, INC.

APPROVER: KCI TECHNOLOGIES, INC.

SCALE: AS SHOWN

PROJECT NO: 24-0000000000

DATE: 11/11/2024

PROJECT: AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

CLIENT: KCI TECHNOLOGIES, INC.

DESIGNER: KCI TECHNOLOGIES, INC.


CHECKER: KCI TECHNOLOGIES, INC.

APPROVER: KCI TECHNOLOGIES, INC.

SCALE: AS SHOWN

PROJECT NO: 24-0000000000

DATE: 11/11/2024



SEE MATCH LINE SHEET CS-04


SEE MATCH LINE SHEET CS-02

PLAN NOTES

- 1. ALL DIMENSIONS UNLESS OTHERWISE SPECIFIED.
- 2. SEE MATCH LINE SHEET CS-04
- 3. SEE MATCH LINE SHEET CS-02

LEGEND

- | | | | |
|----------|-------------------------|----------|-------------------------|
| (Symbol) | EXISTING WATER MAIN | (Symbol) | EXISTING WATER MAIN |
| (Symbol) | EXISTING SANITARY SEWER | (Symbol) | EXISTING SANITARY SEWER |
| (Symbol) | EXISTING ELECTRICAL | (Symbol) | EXISTING ELECTRICAL |
| (Symbol) | EXISTING SIDEWALK | (Symbol) | EXISTING SIDEWALK |
| (Symbol) | EXISTING DRIVEWAY | (Symbol) | EXISTING DRIVEWAY |
| (Symbol) | PROPOSED WATER MAIN | (Symbol) | PROPOSED WATER MAIN |
| (Symbol) | PROPOSED SANITARY SEWER | (Symbol) | PROPOSED SANITARY SEWER |
| (Symbol) | PROPOSED ELECTRICAL | (Symbol) | PROPOSED ELECTRICAL |
| (Symbol) | PROPOSED SIDEWALK | (Symbol) | PROPOSED SIDEWALK |
| (Symbol) | PROPOSED DRIVEWAY | (Symbol) | PROPOSED DRIVEWAY |



CONSTRUCTION/PERMIT DOCUMENTS

CS-03	ARCH	
	KAARLSEN NOONAN RITTIMANN GARCIA ARCHITECTS 2000 BARBERS RD HOUSTON, TEXAS 77057 PH: 713-961-1111 FAX: 713-961-1112	INTEGRITY ENGINEERING 2000 BARBERS RD HOUSTON, TEXAS 77057 PH: 713-961-1111 FAX: 713-961-1112

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023



	KCI TECHNOLOGIES, INC. 1100 W. 10 WEST, SUITE 300 SAN ANTONIO, TEXAS 78201-0337 PHONE: (210) 541-0000 FAX: (210) 541-6443 REGISTRATION #1-10573 #101943-03
--	--

DESIGNED BY: PAM
 DRAWN BY: LNC
 APPROVED: PAM
 JOB NO: 762301481

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY:

PAUL W. BECKER, P.E.
 REG. NO. #05075
 ON SEPTEMBER 16, 2023

NORTHERN HEBBESBROUGH SCHOOL DISTRICT



- PLAN NOTES**
- 1. REFER TO ALL SHEETS FOR CONDUIT SIZES.
 - 2. REFER TO ALL SHEETS FOR CONDUIT TYPES.
 - 3. REFER TO ALL SHEETS FOR CONDUIT SIZES.
 - 4. REFER TO ALL SHEETS FOR CONDUIT TYPES.
 - 5. REFER TO ALL SHEETS FOR CONDUIT SIZES.
 - 6. REFER TO ALL SHEETS FOR CONDUIT TYPES.
 - 7. REFER TO ALL SHEETS FOR CONDUIT SIZES.
 - 8. REFER TO ALL SHEETS FOR CONDUIT TYPES.
 - 9. REFER TO ALL SHEETS FOR CONDUIT SIZES.
 - 10. REFER TO ALL SHEETS FOR CONDUIT TYPES.
- LEGEND**
- 1. ELECTRICAL RACEWAY
 - 2. ELECTRICAL RACEWAY
 - 3. ELECTRICAL RACEWAY
 - 4. ELECTRICAL RACEWAY
 - 5. ELECTRICAL RACEWAY
 - 6. ELECTRICAL RACEWAY
 - 7. ELECTRICAL RACEWAY
 - 8. ELECTRICAL RACEWAY
 - 9. ELECTRICAL RACEWAY
 - 10. ELECTRICAL RACEWAY
 - 11. ELECTRICAL RACEWAY
 - 12. ELECTRICAL RACEWAY
 - 13. ELECTRICAL RACEWAY
 - 14. ELECTRICAL RACEWAY
 - 15. ELECTRICAL RACEWAY
 - 16. ELECTRICAL RACEWAY
 - 17. ELECTRICAL RACEWAY
 - 18. ELECTRICAL RACEWAY
 - 19. ELECTRICAL RACEWAY
 - 20. ELECTRICAL RACEWAY
 - 21. ELECTRICAL RACEWAY
 - 22. ELECTRICAL RACEWAY
 - 23. ELECTRICAL RACEWAY
 - 24. ELECTRICAL RACEWAY
 - 25. ELECTRICAL RACEWAY
 - 26. ELECTRICAL RACEWAY
 - 27. ELECTRICAL RACEWAY
 - 28. ELECTRICAL RACEWAY
 - 29. ELECTRICAL RACEWAY
 - 30. ELECTRICAL RACEWAY
 - 31. ELECTRICAL RACEWAY
 - 32. ELECTRICAL RACEWAY
 - 33. ELECTRICAL RACEWAY
 - 34. ELECTRICAL RACEWAY
 - 35. ELECTRICAL RACEWAY
 - 36. ELECTRICAL RACEWAY
 - 37. ELECTRICAL RACEWAY
 - 38. ELECTRICAL RACEWAY
 - 39. ELECTRICAL RACEWAY
 - 40. ELECTRICAL RACEWAY
 - 41. ELECTRICAL RACEWAY
 - 42. ELECTRICAL RACEWAY
 - 43. ELECTRICAL RACEWAY
 - 44. ELECTRICAL RACEWAY
 - 45. ELECTRICAL RACEWAY
 - 46. ELECTRICAL RACEWAY
 - 47. ELECTRICAL RACEWAY
 - 48. ELECTRICAL RACEWAY
 - 49. ELECTRICAL RACEWAY
 - 50. ELECTRICAL RACEWAY
 - 51. ELECTRICAL RACEWAY
 - 52. ELECTRICAL RACEWAY
 - 53. ELECTRICAL RACEWAY
 - 54. ELECTRICAL RACEWAY
 - 55. ELECTRICAL RACEWAY
 - 56. ELECTRICAL RACEWAY
 - 57. ELECTRICAL RACEWAY
 - 58. ELECTRICAL RACEWAY
 - 59. ELECTRICAL RACEWAY
 - 60. ELECTRICAL RACEWAY
 - 61. ELECTRICAL RACEWAY
 - 62. ELECTRICAL RACEWAY
 - 63. ELECTRICAL RACEWAY
 - 64. ELECTRICAL RACEWAY
 - 65. ELECTRICAL RACEWAY
 - 66. ELECTRICAL RACEWAY
 - 67. ELECTRICAL RACEWAY
 - 68. ELECTRICAL RACEWAY
 - 69. ELECTRICAL RACEWAY
 - 70. ELECTRICAL RACEWAY
 - 71. ELECTRICAL RACEWAY
 - 72. ELECTRICAL RACEWAY
 - 73. ELECTRICAL RACEWAY
 - 74. ELECTRICAL RACEWAY
 - 75. ELECTRICAL RACEWAY
 - 76. ELECTRICAL RACEWAY
 - 77. ELECTRICAL RACEWAY
 - 78. ELECTRICAL RACEWAY
 - 79. ELECTRICAL RACEWAY
 - 80. ELECTRICAL RACEWAY
 - 81. ELECTRICAL RACEWAY
 - 82. ELECTRICAL RACEWAY
 - 83. ELECTRICAL RACEWAY
 - 84. ELECTRICAL RACEWAY
 - 85. ELECTRICAL RACEWAY
 - 86. ELECTRICAL RACEWAY
 - 87. ELECTRICAL RACEWAY
 - 88. ELECTRICAL RACEWAY
 - 89. ELECTRICAL RACEWAY
 - 90. ELECTRICAL RACEWAY
 - 91. ELECTRICAL RACEWAY
 - 92. ELECTRICAL RACEWAY
 - 93. ELECTRICAL RACEWAY
 - 94. ELECTRICAL RACEWAY
 - 95. ELECTRICAL RACEWAY
 - 96. ELECTRICAL RACEWAY
 - 97. ELECTRICAL RACEWAY
 - 98. ELECTRICAL RACEWAY
 - 99. ELECTRICAL RACEWAY
 - 100. ELECTRICAL RACEWAY

CONSTRUCTION/PERMIT DOCUMENTS

C5.05

DATE	DESCRIPTION

ARCH
KARLSEN
NOONAN
RITTMANN
GARCIA
ARCHITECTS
12221 LESLIE ROAD, HELOTES, TX 78023
PH: 512.434.1000
FAX: 512.434.1001

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023

KCI TECHNOLOGIES, INC.
11500 W 10 WEST, SUITE 300
SAN ANTONIO, TEXAS 78243-0337
PHONE: (210) 494-0888
FAX: (210) 541-6443
REGISTRATION #1-10573 / #121943-03

DESIGNED BY	P.A.M.
DRAWN BY	L.M.D.
CHECKED BY	P.A.M.
APP. NO.	7088014601









TABLE 5.7 GEOTEXTILE FABRIC SPECIFICATIONS - CITY OF AUSTIN 2004

PROPERTY	TEST METHOD	UNIT	SPECIFICATION MIN
LINE WEIGHT	Q301	LB/YD	8
ELUTRATION RATE	INTEC	IN/SEC	0.08
FUNCTIOE STRENGTH	ASTM D-2511	LBSS	125
MILLEN BURST STRENGTH	ASTM D-2511	PFI	450
TENSILE STRENGTH	ASTM D-2511	LBSS	1.55
EQUIVALENT OPENING SIZE	US STANDARD SIEVE	NO.	40

NOTE:
 VALUE REQUIRED: 14.4 LB OF 1" SHALE PROPOSED: 16.4 LB OF 1" SHALE
 VALUE REQUIRED: 13.8 LB OF 1" SHALE PROPOSED: 15.1 LB OF 1" SHALE

AVAILABLE GEOTEXTILE FABRIC SHALL BE IDENTIFIED TO THE FABRIC AND MEET SPECIFICATIONS IN TABLE 5.7. CONTRACTOR'S FABRIC SHALL BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION. A 1' X 1' SECTION IS REQUIRED.



OUTLETS FOR BASIN PIPING DETAIL

CONCRETE COLLAR OF BRASS PIPE WITH CONCRETE FILL BOLT. BRASS COLLAR TO BE 1/2" THICK. CONCRETE TO BE 3" MIN. THICK. COLLAR TO BE SET ON TOP OF CLEANOUT PIPE.

WOB LATERAL PROFILE DATA

PROPOSED CLEANOUTS:

- POINT 1: 100' STATION AT CLEANOUT 100.00 FT
- POINT 2: 100' STATION AT CLEANOUT 100.00 FT
- POINT 3: 100' STATION AT CLEANOUT 100.00 FT
- POINT 4: 100' STATION AT CLEANOUT 100.00 FT
- POINT 5: 100' STATION AT CLEANOUT 100.00 FT
- POINT 6: 100' STATION AT CLEANOUT 100.00 FT
- POINT 7: 100' STATION AT CLEANOUT 100.00 FT
- POINT 8: 100' STATION AT CLEANOUT 100.00 FT
- POINT 9: 100' STATION AT CLEANOUT 100.00 FT
- POINT 10: 100' STATION AT CLEANOUT 100.00 FT
- POINT 11: 100' STATION AT CLEANOUT 100.00 FT
- POINT 12: 100' STATION AT CLEANOUT 100.00 FT
- POINT 13: 100' STATION AT CLEANOUT 100.00 FT
- POINT 14: 100' STATION AT CLEANOUT 100.00 FT
- POINT 15: 100' STATION AT CLEANOUT 100.00 FT
- POINT 16: 100' STATION AT CLEANOUT 100.00 FT
- POINT 17: 100' STATION AT CLEANOUT 100.00 FT
- POINT 18: 100' STATION AT CLEANOUT 100.00 FT
- POINT 19: 100' STATION AT CLEANOUT 100.00 FT
- POINT 20: 100' STATION AT CLEANOUT 100.00 FT

CLAY LINER SPECIFICATIONS

1.5" MIN. THICKNESS

1.5" MIN. WIDTH

1.5" MIN. HEIGHT

1.5" MIN. LENGTH

1.5" MIN. SPACING

1.5" MIN. OVERLAP

1.5" MIN. JOINT

1.5" MIN. GROUND

1.5" MIN. SURFACE

1.5" MIN. BARRIER

1.5" MIN. FENCE

1.5" MIN. NOTE

1.5" MIN. REFERENCE

1.5" MIN. SHEET

1.5" MIN. C&G

TRENCH EXCAVATION SAFETY PROTECTION

CONSTRUCTION SHALL MAINTAIN PROTECTION OF EXISTING UTILITIES AND STRUCTURES. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS. CONTRACTOR SHALL MAINTAIN CLEAR ACCESS TO ALL ADJACENT PROPERTIES AND PUBLIC AREAS. CONTRACTOR SHALL MAINTAIN ALL NECESSARY SAFETY MEASURES IN PLACE AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL SAFETY MEASURES AND RESTORING THE AREA TO ORIGINAL CONDITION UPON COMPLETION OF WORK.

THE SEAL, APPROVED ON: [DATE]
 REGISTERED PROFESSIONAL ENGINEER
 STATE OF TEXAS
 PROJECT NO. [PROJECT NO.]
 SHEET NO. [SHEET NO.]
 DATE: [DATE]


















PROJECT NO. [PROJECT NO.]
 SHEET NO. [SHEET NO.]
 DATE: [DATE]

KCI TECHNOLOGIES, INC.
 1222 LEBLANC ROAD, WACO, TEXAS 76702
 (817) 871-1111

AGRICULTURE SCIENCE &
 TECHNOLOGY ACADEMY AT
 SANDRA DAY O'CONNOR HS UPGRADES
 1222 LEBLANC ROAD, WACO, TEXAS 76702

CONSTRUCTION/PERMIT DOCUMENTS

Project No. [PROJECT NO.]
 Sheet No. [SHEET NO.]
 Date Issued: [DATE]



KCI TECHNOLOGIES, INC.
 1500 N. HOUSTON SUITE 300
 SAN ANTONIO, TEXAS 78204-3037
 PHONE: (214) 594-6600
 FAX: (214) 594-6640
 REGISTRATION # 10573 # 1054943-03

DESIGNED BY: PARR
 DRAWN BY: LANG
 APPROVED BY: PARR
 DATE: 04/18/00

THE SEAL, APPROVED BY, AND SIGNATURE OF THE REGISTERED PROFESSIONAL ENGINEER ARE REQUIRED FOR ALL PERMITS AND CONTRACTS.

REGISTERED PROFESSIONAL ENGINEER
 STATE OF TEXAS
 NUMBER: 10573
 EXPIRES: 04/18/00

CONSTRUCTION/PERMIT DOCUMENTS

C5 07

UNIFORM DRAWING DETAILS

INTEGRITY


KAARLSEN
 NOONAN
 RITTMANN
 GARCIA

ON-SITE SUPERVISOR
 PROJECT MANAGER
 PROJECT ENGINEER
 PROJECT SUPERVISOR


AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023


NORTHERN HEBBESBROTHERS



H-9



H-10



H-11



H-13

KCI TECHNOLOGIES, INC.

1500 N. 10 WEST SUITE 300
SAN ANTONIO, TEXAS 78201-3937
PHONE: (210) 593-8800
FAX: (210) 541-6465
REGISTRATION #1-10573 #103493-03

REGISTERED PROFESSIONAL ENGINEER

STATE OF TEXAS
NO. 103493-03
EXPIRES 09/01/2023


LIFT STATION COMPARTMENT ROOM SIZE & GENERAL NOTES

1. THE COMPARTMENT SHALL BE CONCRETE ON GRADE. THE CONCRETE SHALL BE 28 DAY COMPRESSIVE STRENGTH OF 4000 PSI. ALL REINFORCEMENT SHALL BE A305 GRADE. ALL REINFORCEMENT SHALL BE EPOXY COATED UNLESS OTHERWISE NOTED. ALL REINFORCEMENT SHALL BE PLACED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.

REINFORCING BARS

1	CONCRETE	1.00	CU YD
2	STEEL REINFORCEMENT	1.00	TON


H-12



H-12

TRENCH DRAIN NOTES

1. TRENCH DRAIN SHALL BE INSTALLED WITH THE SLOPE ON THE TRENCH SIDE.
2. TRENCH DRAIN SHALL BE INSTALLED WITH THE SLOPE ON THE TRENCH SIDE.
3. TRENCH DRAIN SHALL BE INSTALLED WITH THE SLOPE ON THE TRENCH SIDE.
4. TRENCH DRAIN SHALL BE INSTALLED WITH THE SLOPE ON THE TRENCH SIDE.



H-14

ARCH

KARLSEN
NOONAN
GRIFFIN
GARCIA









ARCHITECTS

1500 N. 10 WEST SUITE 300
SAN ANTONIO, TEXAS 78201-3937
PHONE: (210) 593-8800
FAX: (210) 541-6465
REGISTRATION #1-10573 #103493-03

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023

NORTHERN METROIST SOCIAL DISTRICT



KCI TECHNOLOGIES, INC.
 1500 W 10 WEST SUITE 300
 SAN ANTONIO, TEXAS 78201-0357
 PHONE: (214) 541-6600
 FAX: (214) 541-6443
 REGISTRATION #F-10573 #F105493-03

SEAL
 I AM AN ENGINEER IN THE STATE OF TEXAS
 REGISTERED PROFESSIONAL ENGINEER
 NO. 10481
 EXPIRES 09/01/2011

THE SEAL, OFFERING TO BE USED BY ANY OTHER PERSON WITHOUT THE WRITTEN CONSENT OF THE ENGINEER, IS UNLAWFUL.

SMALL SERVICE LINE, DOUBLE METERS
 RELEASE SYSTEM
 SERVICE MANAGEMENT
 DD-534-05
 1 OF 1

3\"/>
 DD-534-06
 1 OF 1

SMALL SERVICE LINE, DOUBLE METERS
 RELEASE SYSTEM
 SERVICE MANAGEMENT
 DD-534-07
 1 OF 1

SMALL SERVICE LINE, DOUBLE METERS
 RELEASE SYSTEM
 SERVICE MANAGEMENT
 DD-534-07
 1 OF 1

CONSTRUCTION/PERMIT DOCUMENTS

C5 09

DATE: 08/11/10
 SHEET: 09 OF 10
 PROJECT: AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES







INTEGRATED ARCHITECTURE
 KAARLSEN
 NOONAN
 GITTANN
 GARCIA

12221 LESLIE ROAD, HELOTES, TX 78023

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023

NORTHERN METROPOST SCHOOL DISTRICT



KCI TECHNOLOGIES, INC.
SAN ANTONIO, TEXAS 78201
1222 FLEISHER ROAD, RELECTOS, TX 78023









AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

1222 FLEISHER ROAD, RELECTOS, TX 78023

PROJECT NO. 762301481
DRAWN BY: ENL
DATE: 09/06/23
REVISIONS:

SAWS WATER DETAILS 2

C5.10



CONSTRUCTION/PERMIT DOCUMENTS

C511

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LESLIE ROAD, HELOTES, TX 78023

KCI TECHNOLOGIES, INC.
 1500 W 10 WEST, SUITE 300
 SAN ANTONIO, TEXAS 78203-0337
 PHONE: (210) 641-6600
 FAX: (210) 641-6663
 REGISTRATION #1-0573 #191943-03

DESIGNER: PAM
 DRAWN BY: LMO
 APPROVED: PAM
 APP. NO.: 7068014601



CONTRACTOR	
DETAILS	

PROJECT NO.	1500
DATE	12/15/11
SCALE	AS SHOWN
DESIGNED BY	ARCH
CHECKED BY	ARCH
APPROVED BY	ARCH

ARCH
 KAARLSEN
 NOONAN
 RITTMANN
 GARCIA
 1500 W. WEST, SUITE 300
 SAN ANTONIO, TEXAS 78205-0357
 PH: (210) 541-6669
 FAX: (210) 541-6663
 REGISTRATION #1-10573 #121943-03

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES



12221 LESLIE ROAD, HELOTES, TX 78023

KCI TECHNOLOGIES, INC.
 1500 W. WEST, SUITE 300
 SAN ANTONIO, TEXAS 78205-0357
 PH: (210) 541-6669
 FAX: (210) 541-6663
 REGISTRATION #1-10573 #121943-03

DESIGNED BY: PAM
 DRAWN BY: LMO
 APPROVED BY: PAM
 JOB NO.: 7080014001



THE SEAL, SIGNATURE AND EXPIRATION DATE OF THIS SEAL ARE REQUIRED FOR ALL PERMITS AND CONTRACTS.
 EXPIRES 06/30/14



Temporary Stormwater Section (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
Practice Leader | Senior Associate

Date: 9/22/2023

Signature of Customer/Agent:



Regulated Entity Name: O'Connor High School Agricultural Science and Technology

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

- Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.
 - Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
 - Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- Fuels and hazardous substances will not be stored on the site.
2. **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
 4. **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Helotes Creek

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
 - A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
 - A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
 - A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
 - There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- N/A
12. **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

Attachment A

Spill Response Actions

The spill response actions are to prevent or reduce the discharge of pollutants to drainage systems or watercourses from leaks and spills by reducing the chance for spills, stopping the source of spills, containing and cleaning up spills, properly disposing of spill materials, and training employees. *Adapted from RG-348, Section 1.4.16.*

Education

- Be aware that different materials pollute in different amounts. Make sure that each employee knows what a “significant spill” is for each material they use, and what is the appropriate response for “significant” and “insignificant” spills.
- Employees should also be aware of when spill must be reported to the TCEQ.
- Educate employees and subcontractors on potential dangers from spills and leaks.
- Incorporate into regular safety meetings the proper disposal procedures.
- Have contractor’s superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

- To the extent that the work can be accomplished safely, spills of oil, petroleum products, and substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- Store hazardous materials and wastes in covered containers and protect from vandalism.
- Place a stockpile of spill cleanup materials where it will be readily accessible.
- Train employees in spill prevention and cleanup.
- Designate responsible individuals to oversee and enforce control measures.
- Spills should be covered and protected from storm water during rainfall to the extent that it doesn’t compromise cleanup activities.
- Do not bury or wash spills with water.
- Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations. Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- Keep waste storage areas clean, well organized, and equipped with ample cleanup
- Supplies as appropriate for the materials being stored.
- Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

Cleanup

- Clean up leaks and spills immediately.

Minor Spills

- Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill. Use absorbent materials on small spills rather than hosing down or burying the spill. Absorbent materials should be promptly removed and disposed of properly.
- Follow the practice below for a minor spill:
 - Contain the spread of the spill.
 - Recover spilled materials.
 - Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

- Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc.
- Spills should be cleaned up immediately:
 - Contain spread of the spill.
 - Notify the project foreman immediately.
 - If the spill occurs on paved or impermeable surfaces, clean up using "dry" methods (absorbent materials, cat litter and/or rags).
 - If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
 - If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

- For significant or hazardous spills that are in reportable quantities:
- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110, 119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

Vehicle and Equipment Maintenance

- If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runoff of storm water and the runoff of spills. Regularly inspect onsite vehicles and equipment for leaks and repair immediately.
- Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- Place drip pans or absorbent materials under paving equipment when not in use.
- Use absorbent materials on small spills rather than hosing down or burying the spill. Remove promptly and dispose of properly.
- Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- Oil filters disposed of in trashcans or dumpsters can leak oil and pollute storm water. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal.
- Store cracked batteries in a non-leaking secondary container.

Vehicle and Equipment Fueling

- If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runoff of storm water and the runoff of spills.
- Discourage "topping off" of fuel tanks.
- Always use secondary containment, such as a drain pan, when fueling to catch spills / leaks.

Product Specific Practices

- Petroleum Products: All on site vehicles will be monitored for leaks and will receive regular preventive maintenance to reduce the chance of leakage. If petroleum products will be present at the site, they will be stored in tightly sealed containers which are clearly labeled. Any asphalt substances used on site will be applied according to the manufacturer's recommendations.
- Concrete trucks: Ready/Transit Mix Trucks will not be allowed to wash out or discharge surplus concrete or drum wash water except in the designated location on site as shown on the SW3P site plan.
- Paints: All containers will be tightly sealed and stored when not required for use. Excess paint will not be poured into the storm sewer system or drainage channels, but will be properly disposed of according to manufacturers' instructions or state/local regulations.
- Fertilizers: Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to storm water. The fertilizer will be stored in a covered area, and any partially used bags will be transferred to a sealable plastic bin to avoid spills.

Attachment B

Potential Sources of Contamination

Potential Sources of Contamination

Potential sources not described in Attachment A.

Potential Source: Stock piled top soil, and fill material.

Preventive Measure: Stock piles shall be placed away from any steep slopes, sensitive features, surface or groundwater. The down gradient side shall be protected with silt fencing.

Potential Source: Miscellaneous litter and debris from construction workers and construction materials.

Preventive Measure: Trash receptacles will be placed on site for proper disposal. Receptacles will be emptied or replaced by a registered trash hauler as necessary.

Potential Source: Petroleum Products (diesel, oil, hydraulic fluid, gun grease).

Preventive Measure: All on site vehicles will be monitored for leaks and will receive regular preventive maintenance to reduce the chance of leakage. No petroleum products will be stored onsite. Service vehicles will come on site to fuel all equipment. All oil, hydraulic fluid, and gun grease will be stored on work or service vehicles in original sealed containers.

Potential Source: Concrete.

Preventive Measure: Concrete trucks: Ready/Transit Mix Trucks will not be allowed to wash out or discharge surplus concrete or drum wash water except in the designated concrete washout area as shown on the SW3P site plan.

Potential Source: Paint.

Preventive Measure: All containers will be tightly sealed and stored when not required for use. Excess paint will not be poured into the storm sewer system or drainage channels, but will be properly disposed of according to manufacturers' instructions or state/local regulations.

Potential Source: Asphalt & Asphaltic Products.

Preventive Measure: All asphalt paving, roofing, and sealers may be brought onsite only as it is being applied. Application will be in accordance to the manufacturer's recommendations and City of San Antonio specifications.

Potential Source: Fertilizer.

Preventive Measure: Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Revegetated areas that are seeded and fertilized will be protected by a hydraulic mulch, hay and tackifier or binder, or erosion control mat. Fertilizer will not be stored onsite.

Potential Source: Sewage from Portable Toilets and / or Collection Tanks on Construction Trailer.

Preventive Measure: Sewage from the units will be properly removed on a regular basis, will be inspected on a regular basis, and will be disposed of by a licensed waste collection service. Note that any spills should be contained within the respective BMP installed and any spill outside the containment area will be cleaned up in accordance with current state / local regulations as well as reported to TCEQ.

Attachment C

Sequence of Major Activities

Sequence of Major Activities

Construction Sequencing:

- A. Installation of Temporary BMPs as shown on the “Storm Water Pollution Prevention Plan (SWPPP) / Erosion and Sediment Control Plan, Storm Water Pollution Prevention Plan (SWPPP) Details / Erosion and Sediment Control Details, the Tree Protection Details and the “Water Pollution Abatement Plan sheets.
- B. Site clearing including the removal of select trees / trimming of trees and rough grading of the entire proposed site.
- C. Excavation and preparation of basins.
- D. Demolition of some of the existing areas (sidewalks, curbs, and pavement) and trenching activities for utility and drainage work associated with this project.
- E. Excavation and preparation of subgrade.
- F. Trenching for services on-site / extension of utilities to the site.
 - a. Installation of electric, communication, data, and other dry utility services to the new parking lots.
 - b. Installation of water main for domestic and fire protection of the site.
 - c. Installation of the on-site sewer facility (OSSF).
 - d. Reestablishment of vegetation in areas beyond the parking lot and office building within the construction envelope(s).
- G. Excavation and construction of structural footings and foundations for ramps and buildings respectively.
- H. Installation of drainage infrastructure.
- I. Installation of base material / construction of parking lots and roadway.
- J. Erection and construction of building, including finish out while site work is on-going.
- K. Installation of concrete curbs.
- L. Drill and pour concrete footings for structures such as light standards, cameras, bollards, etc.
- M. Application of prime and tack coats.
- N. Construction of sidewalks.
- O. Installation of asphalt pavement and installation of ADA truncated domes.
- P. Finish out items such as erecting light standards and cameras.
- Q. Finish grading as indicated on plans.
- R. Landscaping / sodding / seeding to reestablish vegetation on all remaining disturbed areas.
- S. Removal of temporary BMPs once area is established or when the particular temporary BMP measure is no longer required (i.e. Construction Exit and Concrete Washout Pit)

Attachment D

Temporary Best Management Practices and Measures

Temporary Best Management Practices and Measures

There are no significant recharge features identified by the Geologic Assessment that will be adversely affected by the construction of this project as it is identified on the geological report. Please reference the Geological Assessment attached. Refer to the "Storm Water Pollution Prevention Plan (SWPPP) / Erosion and Sediment Control Plan, Storm Water Pollution Prevention Plan (SWPPP) Details / Erosion and Sediment Control Details, the Tree Protection Details and the "Water Pollution Abatement Plan (WPAP) sheets for BMPs to protect the general site areas, including tree protection measures, during construction activities and after.

Temporary BMPs, such as sediment control rolls, sediment control / silt fencing, gravel filter bags, inlet protection with filter fabric placed around the on-site and adjacent curb inlets, and high service rock berms will be implemented to control the runoff and prevent sediment transport downstream onto the existing roadways, swales, storm drains, and channels until vegetation is reestablished for the area. Silt fencing will be placed downstream in a manner not to exceed 1 acre of contributing area to also trap sediment before reaching the roadway and channels where feasible. Triangular filter dikes will also be used at existing paved areas, such as roadways and sidewalks where silt fence post cannot be installed.

Any upgradient runoff that will enter the site and downstream conditions will be addressed.

Attachment F

Structural Practices




Structural Practices

Refer to Water Pollution Abatement Plan (WPAP), Stormwater Pollution Prevention Plan (SWPPP) / Erosion and Sedimentation Control Plan, Stormwater Pollution Prevention Plan (SWPPP) / Erosion and Sedimentation Control Plan Details.

The permanent BMPs will be excavated and used to trap sediment construction as well as those other details noted above.

Attachment G

Drainage Area Maps



KCI TECHNOLOGIES, INC.
1500 W 10 WEST, SUITE 300
SAN ANTONIO, TEXAS 78203-0307
PHONE: (214) 343-0999
FAX: (214) 343-6465
REGISTRATION #F-10573 / #101943483

DESIGNED BY: PAM
DRAWN BY: LNC
APPROVED: PAM

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY: PAUL B. BECKER, P.E. NO. #105075 ON SEPTEMBER 19, 2003 DATE

REGISTRATION #F-10573 / #101943483

HYD 1.0

EXISTING HYDROLOGY PLAN

ENR/ARCH

KAARLSEN
NOONAN
RITTMANN
GARCIA

CHUCK BANCHEK AND KEOI PROFFER, TEXAS PECS PROFESSIONALS

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES


12221 LESLIE ROAD, HELOTES, TX 78023





LEGEND

- PROPOSED SUB AREA NAME
- PROPOSED COLLECTION POINT
- PROPOSED SHARPLESS FLOW
- PROPOSED SHARPLESS LOTS
- EXISTING CONDUITS
- SHEET FLOW LINE OF CONCENTRATION
- SHARPLESS CONCENTRATION LINE OF CONCENTRATION
- PIPE LINE OF CONCENTRATION



KCI TECHNOLOGIES, INC.
 1100 W 10 WEST SUITE 300
 SAN ANTONIO, TEXAS 78203-0300
 PHONE: (214) 341-0000
 FAX: (214) 341-6460
 REGISTRATION #F-10573 #F01943483

DESIGNED BY: PAM
 DRAWN BY: LNC
 APPROVED: PAM

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY: PAUL B. BECKER, P.E. NO. #05079 ON SEPTEMBER 19, 2003 DATE

HYD 2.0

PROPOSED HYDROLOGY PLAN

ENR
 ENGINEERING & ARCHITECTURE

KAARLSEN
 NOONAN
 RITTMANN
 GARCIA

12221 LESLIE ROAD, HELOTES, TX 78023

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES



Attachment I

Inspection and Maintenance for temporary BMPs

Inspection and Maintenance for Temporary BMP's

There will be several types of Temporary BMPs used for this project: Silt Fencing, Rock Berms, Area Inlet Protection, Gravel Filter Bags, Triangular Dikes, Temporary Construction Entrance/Exit, and a Concrete Washout Pit. Items listed below must be inspected every 7 days and within 24 hours of a rainfall event of 0.5 inches or more. These inspections and if any maintenance is performed on such BMPs, it must be documented within the inspection and maintenance report form and kept on site. The forms can be found at the end of this section.

Silt Fencing, Rock Berms, Area Inlet Protection, Gravel Filter Bags, & Triangular Filter Dikes

Refer to TCEQ "Edwards Aquifer Technical Guidance Manual" RevJul05, pages 1-66 to 1-68 (Silt Fencing), pages 1-72 to 1-74 (Rock Berms), pages 1-89 to 1-92 (Area Inlet Protection), pages 1-98 to 1-100 (Gravel Filter Bags), pages 1-69 to 1-71 (Triangular Filter Dikes), pages 1-63 to 1-65 (Construction Entrance/Exit), pages 1-124 to 1-125 (Concrete Washout) for standards, and also refer to Sheets C01B and C05 through C05D.1 for the Erosion Control Plan and Sheets C05E through C05G for the Erosion Control Details of the construction plans for locations/details/guidance.

Contractor shall maintain log and document following items for silt fencing, rock berms, gravel filter bags, inlet protection, triangular dikes and any other approved temporary BMP:

- 1) Inspection of all fencing/berms/bags/dikes weekly, and after any rainfall event.
- 2) Removal of sediment when buildup reaches 6" on any temporary BMP, or the installation of a second line of fencing parallel to the old fence. Dispose of the accumulated silt of in an approved manner.
- 3) Replacement of any torn fabric or installation of a second line of fencing parallel to the old fence.
- 4) Replacement/repair of any sections crushed, torn, or collapsed temporary BMPs in the course of construction activity. If a section of fence/berm is obstructing vehicular access, document the relocation to a spot where it will provide equal protection, but will not obstruct vehicles.
- 5) The contractor may use Triangular Filter Dikes in areas where fencing is impractical due to existing pavement or concrete flatwork.
- 6) For installations of rock berms in streambeds, additional daily inspections should be made.
- 7) For rock berms, any lose wire sheathing shall be repaired or replaced as needed and the berm reshaped as needed during inspection.
- 8) Any rock berms are to be replaced when the structure ceases to function as intended due to silt accumulation among the rocks, washout, construction traffic damage, etc.
- 9) Any rock berm shall be left in place until all upstream areas are stabilized, and accumulated silt removed.
- 10) Any gravel filter bags torn allowing gravel to come out of the constraints of the bag shall be replaced immediately.

These temporary BMPs as shown on the “Storm Water Pollution Prevention Plan (SWPPP) / Erosion and Sediment Control Plan / Details” (Sheets C01B and C05 through C05G) and “Water Pollution Abatement Plan (WPAP)” (Sheets WPAP 1, WPAP 2, WPAP 3, and WPAP 4) will intercept any storm water borne pollutants originating onsite, including upstream offsite runoff, therefore preventing them from entering Geological Features, roadways, drainage features, and other drainage structures such as the existing WQBs.

Temporary Construction Entrance/Exit

Contractor shall establish and maintain a Temporary Construction Entrance/Exit throughout the construction period to protect the site from pollutants brought onto the site from other sources or leaving the site. Contractor to insure rocks are maintained free of trash and sediment.

Concrete Washout Pit

Contractor shall insure concrete washout pit is maintained at all times during construction and removed appropriately at the end of construction.

The concrete washout pit will be inspected on a weekly basis and after any rainfall event. The sediment build up will be removed when it reaches 6”. Upon removal the area of the washout pit shall be revegetated to prevent erosion of the area.

Construction Lay Down Area

Contractor shall insure silt fencing, rock berms, area inlet protection, gravel filter bags, triangular dikes, temporary construction entrance/exit, and concrete washout pit are maintained as stated above. This construction lay down area shall be used for construction trailers, supplies storage, machinery, temporary parking, etc. needed for construction. The lay down areas will need to be shown on sheets C05 through C05G or other applicable exhibit by the contractor and these areas will be revegetated upon completion of construction. This includes any off-site laydown area within an existing paved area, it shall be cleaned of any debris or sediment prior to removal of any temporary BMP surrounding it.

Tree Protection

All trees that will remain shall be protected in accordance with the details as shown on Sheet C05F. In addition to the drip line of the trees being fenced as shown within the details, other measures to protect the existing trees and to minimize disturbance are specifically noted in the plans.

Attachment J

Inspection and Maintenance for temporary BMPs

Schedule of Interim and Permanent Soil Stabilization Practices

Interim Practices

All temporary BMPs as described in Attachment I. This also includes the construction of the WQBs to act as the temporary basins during construction.

Permanent Practices

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporary or permanently cease is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of the site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable.

Refer to "Water Pollution Abatement Plan (WPAP) for all areas to be sodded within the project limits that are designated as VFS or earthen channels or at the back of curbs. All other areas are to be landscaped or hydromulched at a minimum, which includes all other offsite disturbed areas associated with this project (utility installation) beyond the parking areas, walkways, and other paved areas. Landscaping plans also accompany the construction plans for this project for reestablishment of vegetation.

Attachment K

SWPPP

SITE DESCRIPTION

PROJECT LOCATION: **SOUTH/WESTERN SIDE OF THE EXISTING CAMPUS OF O'CONNOR HIGH SCHOOL, LOCATED AT 12221 LEBLANC ROAD, HOUSTON, TX 77023.**

PROJECT DESCRIPTION: **CONSTRUCTION OF ADDITIONAL SCHOOL BUILDINGS, PARKING, SIDEWALK, UTILITIES, AND DRAINAGE STRUCTURES, IN ADDITION, DEMOLITION OF AN EXISTING BUILDING, NEW DRIVE LANES, NEW PARKING LOTS, NEW WATER QUALITY BARR.**

MAJOR SOIL DISTURBING ACTIVITIES: **SITE GRADING, UTILITY AND DRAINAGE CONSTRUCTION, PAVEMENTS AND FLATWORK, AND FOUNDATION CONSTRUCTION.**

TOTAL PROJECT AREA: **~5.8 ACRES**

TOTAL AREA TO BE DISTURBED: **~5.8 ACRES**

WEIGHTED RUNOFF COEFFICIENT (PRE-CONSTRUCTION): **0.70**

WEIGHTED RUNOFF COEFFICIENT (POST-CONSTRUCTION): **0.79**

EXISTING CONDITION OF SOIL & VEGETATION: **MAINT. GRASS WITH TREES IN UNDEVELOPED AREAS AND SOME RECENTLY DEVELOPED AREAS THAT HAVE PAVED, EXPOSED ABOUT 67% VEGETATED COVER WITH FERTILIZER CHANNELS, WATER QUALITY BARRS, VEGETATED TIE-UPS, AND GRAVE LANDSCAPE AREAS.**

NAME OF RECEIVING WATERS: **HELORES CREEK**

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES

- TEMPORARY SEEDING
- PERMANENT PLANTING, SOODING OR SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- SLOPE DICES
- PRESERVATION OF NATURAL RESOURCES

OTHER: _____

STRUCTURAL PRACTICES

- SALT FENCES
- RAY BARRS
- ROCK BARRS
- DIVERSION, INTERCEPTOR, OR PERIMETER DICES
- DIVERSION, INTERCEPTOR, OR PERIMETER DRALES
- DIVERSION DICE AND DRALE COMBINATIONS
- PIPE SLOPE DRAINS
- PAVED FLUMES
- ROCK SEEDING AT CONSTRUCTION EXIT
- TAMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BARRS
- STORM INLET SEDIMENT TRAP
- STORM OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM BARRS
- VELOCITY CONTROL DEVICES
- GRAVEL FILTER BAGS

OTHER: _____

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

PHASE I

1. INSTALLATION OF SWEEP MEASURES

PHASE II

1. SITE CLEARING AND GRADING

PHASE III

FOUNDATIONS, DRAINAGE AND UTILITIES

PHASE IV

1. UTILITIES AND PARKING LOT CONSTRUCTION

2. BUILDING CONSTRUCTION

PHASE V

1. VEGETATION

STORM WATER MANAGEMENT: **TEMPORARY AND PERMANENT MEASURES TO PREVENT SEDIMENT TRANSPORT DOWNSTREAM.**

NON-STORM WATER DISCHARGE: **N/A**

OTHER EROSION AND SEDIMENT CONTROLS

MAINTENANCE: **All erosion and sediment controls will be maintained in good working order. If a repair is necessary, it will be done at the earliest date possible, but no later than 7 calendar days after the necessary amount of work has been completed to prevent further damage from heavy equipment. The areas subject to drainage shall have priority followed by those protecting storm sewer inlets.**

INSPECTION: **An inspection will be performed by the owner or contractor's representative every week or so after every half inch of rain (as recorded on a non-weather rain gauge) to be located at the Project Site. An Inspection and Maintenance Report will be made and each inspection. Based on the inspection results, the controls shall be revised per the Inspection Report.**

WASTE MATERIALS: **All waste materials will be collected and stored in a securely fenced waste dumpster. The dumpster will meet all state and local waste management regulations. All trash and construction debris from the site will be deposited in the dumpster. The dumpster will be emptied as necessary or as required by local regulations and the trash will be hauled to a local dump. No construction waste material will be buried on site.**

HAZARDOUS WASTE (INCLUDING SPILL REPORTING): **As a minimum, any products in the following categories are considered to be hazardous: paints, oils, the cleaning, masonry surfaces, cleaning solvents, sealants, products, chemical additives for asphalt or concrete curing compounds & additives. In the event of a hazardous material spill, the spill coordinator shall be contacted immediately.**

SANITARY WASTE: **All sanitary waste will be collected from portable units, as necessary, or as required by local regulations by a Licensed Sanitary Waste Management Contractor.**

OFFSITE VEHICLE TRACKING

- HAUL ROADS PREPARED FOR DIRT CONTROL
- LOADED WALK TRUCKS TO BE COVERED WITH TARPAULIN
- EXCESS DIRT ON ROAD REMOVED DAILY
- STABILIZED CONSTRUCTION ENTRANCE

PERMITS: _____

REMARKS: **Discard areas, sidewalks, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Discard areas shall not be located in any wetland, waterway, or streambed. Construction, storage areas and vehicle maintenance areas shall be constructed by the Contractor in a manner to minimize the runoff of sediments. All entrance shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, timbering, piling, debris or other obstructions placed during construction operations that are not a part of the finished work.**

CONTRACTOR CERTIFICATION

I certify under penalty of law that I am the owner and all applicants were prepared under my direction to submit to the State and to comply with the provisions of the Texas Water Pollution Control Act and to maintain the information required by the Act. I am not aware of any person or persons who are not registered under the Act. I am aware that there are appropriate penalties for submitting false information, including the possibility of imprisonment for knowingly submitting false information.

SIGNATURE: _____ DATE: _____

CONTRACTOR CERTIFICATION

I certify under penalty of law that I am the owner and all applicants were prepared under my direction to submit to the State and to comply with the provisions of the Texas Water Pollution Control Act and to maintain the information required by the Act. I am not aware of any person or persons who are not registered under the Act. I am aware that there are appropriate penalties for submitting false information, including the possibility of imprisonment for knowingly submitting false information.

SIGNATURE (Contractor): _____ DATE: _____

KCI TECHNOLOGIES, INC.
 12221 LEBLANC ROAD, SUITE 100
 HOUSTON, TEXAS 77023
 PHONE: 281.410.1100
 FAX: 281.410.1101
 WWW.KCI-TECH.COM

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

CONSTRUCTION/PERMIT DOCUMENTS

KARLSEN BOONAN GARCIA

PROJECT NO. T22301481

Drawn By: ENE



Scale: 1" = 10' AM

Date Issued: 09/06/23

Revisions:

SWPPP NOTES

C2.00



KCI TECHNOLOGIES, INC.
 11500 W. 10 WEST, SUITE 300
 SAN ANTONIO, TEXAS 78230-0337
 PHONE: (210) 541-0880
 FAX: (210) 541-6443
 REGISTRATION #1-10573 / #101943-03

OWNER: PAM
DESIGNER: LMO
APPROVER: PAM
DATE: 08/08/04

THE SEAL, SIGNATURE AND EXPIRATION DATE OF THE REGISTERED PROFESSIONAL ENGINEER ARE REQUIRED FOR ALL PERMITS AND CONTRACTS.

CONSTRUCTION/PERMIT DOCUMENTS

PROJECT NO.	0201
DATE	08/08/04
SCALE	AS SHOWN
PROJECT NAME	AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES
PROJECT LOCATION	12221 LEBLUE ROAD, HELOTES, TX 78023
PROJECT OWNER	PAM
PROJECT MANAGER	LMO
PROJECT ENGINEER	PAM
PROJECT ARCHITECT	ARCH
PROJECT CONTRACTOR	
PROJECT SUBCONTRACTOR	
PROJECT SCHEDULE	
PROJECT BUDGET	
PROJECT STATUS	

ARCHITECT
KAARLSEN
NOONAN
RITTMANN
GARCIA
 ARCHITECTS
 12001 BANCROFT FRODO
 FORT WORTH, TEXAS 76133
 P.O. BOX 14711
 FORT WORTH, TEXAS 76114

AGRICULTURE SCIENCE & TECHNOLOGY ACADEMY AT SANDRA DAY O'CONNOR HS UPGRADES

12221 LEBLUE ROAD, HELOTES, TX 78023



C2.01

Agent Authorization Form (TCEQ-0599)

Agent Authorization Form
For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I Jacob Villarreal, P.E. _____
Print Name

Executive Director of Construction and Engineering _____
Title - Owner/President/Other

of Northside Independent School District _____
Corporation/Partnership/Entity Name

have authorized Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA
Practice Leader | Senior Associate _____
Print Name of Agent/Engineer

Of KCI Technolgies _____
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:


Applicant's Signature

8/16/23
Date

THE STATE OF Texas §

County of Bexar §

BEFORE ME, the undersigned authority, on this day personally appeared Jacob Villarreal known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 16 day of August, 2023.

Yvonne M. Carter
NOTARY PUBLIC

Yvonne M. Carter
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 12/08/2026

Application Fee Form (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: O'connor High School agricultural science and technology

Regulated Entity Location: 12221 Leslie Rd, Helotes, TX 78023

Name of Customer: Northside Independent School District

Contact Person: Paul A. Mathis, P.E., PMP Phone: (210) 641-9999

Customer Reference Number (if issued): CN 601104169

Regulated Entity Reference Number (if issued): RN 104754304

Austin Regional Office (3373)

Hays

Travis

Williamson

San Antonio Regional Office (3362)

Bexar

Medina

Uvalde

Comal

Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

Austin Regional Office

San Antonio Regional Office

Mailed to: TCEQ - Cashier

Overnight Delivery to: TCEQ - Cashier

Revenues Section

12100 Park 35 Circle

Mail Code 214

Building A, 3rd Floor

P.O. Box 13088

Austin, TX 78753

Austin, TX 78711-3088

(512)239-0357

Site Location (Check All That Apply):

Recharge Zone

Contributing Zone

Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	611 L.F.	\$ 650
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: 

Date: 9/22/2023

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150

Core Data Form (TCEQ-10400)



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission <i>(If other is checked please describe in space provided.)</i>		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization <i>(Core Data Form should be submitted with the program application.)</i>		
<input type="checkbox"/> Renewal <i>(Core Data Form should be submitted with the renewal form)</i>	<input type="checkbox"/> Other	
2. Customer Reference Number <i>(if issued)</i>	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number <i>(if issued)</i>
CN 601104169		RN 104754304

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)	
<input type="checkbox"/> New Customer <input type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership <input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)			
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>			
6. Customer Legal Name <i>(If an individual, print last name first: eg: Doe, John)</i>		<i>If new Customer, enter previous Customer below:</i>	
Northside Independent School District			
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number <i>(if applicable)</i>
11. Type of Customer:	<input type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input checked="" type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship	<input type="checkbox"/> Other:
12. Number of Employees		13. Independently Owned and Operated?	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input checked="" type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – <i>as it relates to the Regulated Entity listed on this form. Please check one of the following</i>			
<input checked="" type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator <input type="checkbox"/> Other: <input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant			
15. Mailing Address:	Northside Independent School District		
	5900 Evers Road		
	City	San Antonio	State TX ZIP 78238 ZIP + 4
16. Country Mailing Information <i>(if outside USA)</i>		17. E-Mail Address <i>(if applicable)</i>	
		info@nisd.net	
18. Telephone Number	19. Extension or Code	20. Fax Number <i>(if applicable)</i>	

SECTION III: Regulated Entity Information**21. General Regulated Entity Information** (If 'New Regulated Entity' is selected, a new permit application is also required.)

New Regulated Entity Update to Regulated Entity Name Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

O'Connor High School

23. Street Address of the Regulated Entity:

O'Connor High School

12221 Leslie Road

(No PO Boxes)**City**

Helotes

State

TX

ZIP

78023

ZIP + 4**24. County**

Bexar

If no Street Address is provided, fields 25-28 are required.

25. Description to**Physical Location:****26. Nearest City****State****Nearest ZIP Code**

Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).

27. Latitude (N) In Decimal:**28. Longitude (W) In Decimal:**

Degrees

Minutes

Seconds

Degrees

Minutes

Seconds

29. Primary SIC Code**30. Secondary SIC Code****31. Primary NAICS Code****32. Secondary NAICS Code**

(4 digits)

(4 digits)

(5 or 6 digits)

(5 or 6 digits)

1623

611110

33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)

Education

34. Mailing

Northsdie ISD

Address:

5900 Evers Road

City

San Antonio

State**ZIP**

78238

ZIP + 4**35. E-Mail Address:**

info@nisd.net

36. Telephone Number**37. Extension or Code****38. Fax Number** (if applicable)

(210) 397-8500

() -

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
		13-90071601B		
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name:	Paul A. Mathis, P.E., PMP, LEED Green Assoc., MBA	41. Title:	Practice Leader / Senior Associat
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(210) 641-9999		(210) 641-6440	paul.mathis@kci.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	KCI Technologies, Inc.	Job Title:	Practice Leader / Senior Associate
Name (In Print):	Paul A. Mathis (Submitted on behalf of Northside ISD)	Phone:	(210) 641- 9999
Signature:		Date:	9/22/2023