RIDGEWOOD LOT 13

Aboveground Storage Tank Application

September 2023





September 18, 2023

Ms. Lillian Butler
Texas Commission on Environmental Quality (TCEQ)
Region 13
14250 Judson Road
San Antonio, Texas 78233-4480

Re:

Ridgewood Lot 13

Aboveground Storage Tank Application

Dear Ms. Butler:

Please find included herein the Ridgewood Lot 13 Aboveground Storage Tank Application. This Aboveground Storage Tank Application has been prepared to be consistent with the Texas Administrative Code (30 TAC 213) and current policies for development over the Edwards Aquifer Recharge Zone.

This Aboveground Storage Tank Application applies to one (1) aboveground storage tank included in the project. Please review the plan information for the items it is intended to address. If acceptable, provide a written approval of the application in order that construction may begin at the earliest opportunity.

Appropriate review fees (\$650) and fee application form are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,
Pape-Dawson Consulting Engineers, LLC

Dennis Rion, P.E. Executive Vice President


Attachments

P:\64\35\83\Word\AST\230413a1.docx



RIDGEWOOD LOT 13

Aboveground Storage Tank Application



September 2023



EDWARDS AQUIFER APPLICATION COVER PAGE (TCEQ-20705)

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
 - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
 - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- When an application is deemed administratively complete, the technical review period begins. The regional
 office will distribute copies of the application to the identified affected city, county, and groundwater
 conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
 to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name:			2. Regulated Entity No.:						
3. Customer Name:						4. Cı	ıstom	er No.:	
5. Project Type: (Please circle/check one)	New		Modif	icatior	1	Exter	nsion	Exception	
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST	(AST)	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Resider	ntial	Non-r	esiden	tial		8. Sit	te (acres):	
9. Application Fee:			10. P	ermai	nent I	BMP(s):		
11. SCS (Linear Ft.):			12. A	ST/US	ST (No	o. Tar	ıks):		
13. County:			14. W	aters	hed:				

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region				
County:	Hays	Travis	Williamson	
Original (1 req.)		_		
Region (1 req.)		_	_	
County(ies)				
Groundwater Conservation District(s)	Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA	
City(ies) Jurisdiction	AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek	AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills	AustinCedar ParkFlorenceGeorgetownJerrellLeanderLiberty HillPflugervilleRound Rock	

	San Antonio Region				
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)					
Region (1 req.)					
County(ies)					
Groundwater Conservation District(s)	Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde
City(ies) Jurisdiction	Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.
Dennis Rion, P.E.
Print Name of Customer/Authorized Agent
9-18-23
Signature of Customer/Authorized Agent Date
Print Name of Customer/Authorized Agent 9-18-23

FOR TCEQ INTERNAL USE ONLY	
Date(s)Reviewed:	Date Administratively Complete:
Received From:	Correct Number of Copies:
Received By:	Distribution Date:
EAPP File Number:	Complex:
Admin. Review(s) (No.):	No. AR Rounds:
Delinquent Fees (Y/N):	Review Time Spent:
Lat./Long. Verified:	SOS Customer Verification:
Agent Authorization Complete/Notarized (Y/N):	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):	Check: Signed (Y/N):
Core Data Form Incomplete Nos.:	Less than 90 days old (Y/N):

GENERAL INFORMATION FORM (TCEQ-0587)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Dennis Rion, P.E.

Date: 9-18-03

Signature of Customer/Agent:

Project Information

Regulated Entity Name: <u>Ridgewood Lot 13</u>
County: Bexar
Stream Basin: Mud Creek/Salado Creek
Groundwater Conservation District (If applicable): Edwards Aquifer/Trinity Glen Rose
Edwards Aquifer Zone:

5.	Edwards Aquiter Zone:	
	Recharge Zone Transition Zone	
6.	Plan Type:	
	WPAP SCS	☐ Modification ☐ AST

1 of 4

	UST	Exception Request
7.	Customer (Applicant):	
	Contact Person: Ronald Bullock Entity: Sonterra Medical Management Group, Inc. Mailing Address: 19138 US Hwy 281N City, State: San Antonio, TX Telephone: (210) 489-7278 Email Address: rbullock@tsaog.com	Zip: <u>78258</u> FAX: <u>(210)</u> <u>582-2677</u>
8.	Agent/Representative (If any):	
	Contact Person: <u>Dennis Rion, P.E.</u> Entity: <u>Pape-Dawson Engineers, Inc.</u> Mailing Address: <u>2000 NW Loop 410</u> City, State: <u>San Antonio, Texas</u> Telephone: <u>(210) 375-9000</u> Email Address: <u>drion@pape-dawson.com</u>	Zip: <u>78213</u> FAX: <u>(210) 375-9010</u>
9.	Project Location:	
	The project site is located inside the city limits of the project site is located outside the city limits jurisdiction) of The project site is not located within any city's limits and the project site is not located within any city's limits.	but inside the ETJ (extra-territorial
10.	The location of the project site is described belongeral and clarity so that the TCEQ's Regional st boundaries for a field investigation.	
	From TCEQ's regional office, proceed approxim Loop 1604 and turn left to travel west. Proc and turn right to travel north. Drive approxi the right. The site is located approximately Ridgewood Pkwy intersection.	eed approximately 4.9 miles to US 281 mately 0.6 miles to the project site on
11.	Attachment A – Road Map. A road map showing project site is attached. The project location and the map.	_
12.	Attachment B - USGS / Edwards Recharge Zone USGS Quadrangle Map (Scale: 1" = 2000') of the The map(s) clearly show:	
	 ☑ Project site boundaries. ☑ USGS Quadrangle Name(s). ☑ Boundaries of the Recharge Zone (and Tran ☑ Drainage path from the project site to the boundaries 	

13. 🔀	The TCEQ must be able to inspect the project site or the application will be returned. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.
	Survey staking will be completed by this date: completed
14.	Attachment C – Project Description . Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
	Area of the site Offsite areas Impervious cover Permanent BMP(s) Proposed site use Site history Previous development Area(s) to be demolished
15. Exis	sting project site conditions are noted below:
	Existing commercial site Existing industrial site Existing residential site Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Uncleared) Other:
Proh	nibited Activities
16. 🔀	I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
	(1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
	(2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
	(3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
	(4) The use of sewage holding tanks as parts of organized collection systems; and
	(5) New municipal solid waste landfill facilities required to meet and comply with Type I

(6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types

of Municipal Solid Waste Facilities).

17. | I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project: (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control); (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title. Administrative Information 18. The fee for the plan(s) is based on: For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur. For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines. For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems. A request for an exception to any substantive portion of the regulations related to the protection of water quality. A request for an extension to a previously approved plan. 19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's: X TCEQ cashier Austin Regional Office (for projects in Hays, Travis, and Williamson Counties) San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties) 20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional

copies to these jurisdictions. The copies must be submitted to the appropriate regional


21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

office.

ATTACHMENT A

RIDGEWOOD - LOT 13 Water Pollution Abatement Plan





Pape-Dawson Engineers, Inc.


Date: Oct 04, 2018, 9: 38am User ID: ROllvarez

File: P:\64\35\73\Design\Environmental\WPAP\RM-64357J.dwg

ATTACHMENT A Road Map

ATTACHMENT B





GENERAL LOCATION MAP - LONGHORN, TX QUAD

 USGS/EDWARDS RECHARGE ZONE MAP

ATTACHMENT C

RIDGEWOOD LOT 13

Aboveground Storage Tank Facility Plan

Attachment C – Project Description

The Ridgewood Lot 13 Aboveground Storage Tank (AST) Facility Plan is a 0.02-acre site located within the previously approved 16.55-acre Ridgewood Lot 13 Water Pollution Abatement Plan Modification (EAPP ID No. 13000827). This project site is located approximately 500 ft northeast of Dry Creek Way and Ridgewood Parkway intersection, in the City of San Antonio, Bexar County, Texas. The site is developed as a commercial development with medical office buildings, lies within the Upper Salado Creek watershed, and is adjacent to the 100-year floodplain to the south. There were no naturally occurring sensitive geological features identified in the Geologic Assessment.

This Ridgewood Lot 13 Aboveground Storage Tank Facility Plan proposes the addition of an aboveground storage tank onto a previously approved generator pad (EAPP ID No. 13000827). The proposed AST to be used at Ridgewood Lot 13 is a base-mounted, double-wall, steel construction with sealed interstitial spaces. The proposed useable fuel capacity is 531 gallons (600 gallons total capacity) to provide runtime for the standby generator. This application is for self-reporting of installation of the base-mounted fuel tank.

Fuel Tank Description

The proposed AST will be used to store diesel fuel for an onsite generator utilized by The San Antonio Orthopedic Group (TSAOG), owned by Sonterra Medical Management Group, Inc. The concrete pad is within a locked enclosure located between the parking garage building and MOB building, as shown on Exhibit 3. The double-walled fuel tank is constructed to the UL-2085 standard and is fire safe with an additional 5-gallon spill containment bucket for overfill protection during fueling. The proposed piping is directly connected from the base-mounted diesel tank to the generator within the weather and sound enclosure, so the piping system is not exposed. The proposed AST is double walled for protected secondary containment as required by TCEQ, and the interstitial space is filled with lightweight, chemically hardened concrete for additional protection.

The tank is constructed of materials that are compatible with the liquids stored within (diesel) and have appropriate safety equipment such as primary and emergency venting, overfill protection, and fire valves.

The primary tank is wholly contained within a secondary tank, and the interstitial space is completely sealed with concrete. Therefore, if a failure occurs in the primary tank, all fuel will be trapped in the secondary tank. Additionally, because the interstice is sealed, storm water cannot enter the interstice and reduce the available containment volume. An interstitial space monitor will be placed in the interstice of the AST to alert the operator of a primary tank failure. The 5-gallon spill containment bucket will serve as overfill protection and secondary containment in the event of a minor spill during refueling.

The concrete generator pad construction was approved with the Ridgewood Lot 13 WPAP MOD (EAPP ID No. 13000827). A spill kit capable of containing 25 gallons of fuel shall be placed adjacent to the fill point at the tanker offloading area. The AST is located in the Watershed "B", draining to the existing Basin "D" (EAPP ID No. 2686.00). The tank's secondary containment drains to a point convenient for collection within the tank.



GEOLOGIC ASSESSMENT FORM (TCEQ-0585)

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Henry Stultz III	Telephone: <u>210-375-9000</u>
Date: June 27, 2018	Fax: <u>210-375-9090</u>
Representing: <u>Pape-Dawson Engineers, Inc.</u> <u>Texas Board of Professional Geoscientists No. 5035</u> registration number)	(Name of Company and TBPG or TBPE
Signature of Geologist:	TE A
Regulated Entity Name: Ridgewood Lot 13 - Phase	HENRY STULTZ III GEOLOGY 12121
Project Information	White the state of
1. Date(s) Geologic Assessment was performed: <u>F</u> 2018	ebruary 28, March 1 and 3, 2006; June 25,
2. Type of Project:	
WPAPSCSLocation of Project:	AST UST
Recharge Zone Transition Zone	

Contributing Zo	ne within	the Trans	ition Zone

- 4. Attachment A Geologic Assessment Table. Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
- 5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

Soil Name	Group*	Thickness(feet)
Anhalt clay, 0 to 2 percent slopes (Ca)	D	0-5
Crawford and Bexar stoney soils (Cb)	D	2-4
Trinity and Frio soils, frequently flooded (Tf)	С	4-12

Soil Name	Group*	Thickness(feet)

- * Soil Group Definitions (Abbreviated)
 - A. Soils having a high infiltration rate when thoroughly wetted.
 - B. Soils having a moderate infiltration rate when thoroughly wetted.
 - C. Soils having a slow infiltration rate when thoroughly wetted.
 - D. Soils having a very slow infiltration rate when thoroughly wetted.
- 6. Attachment B Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
- 7. Attachment C Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
- 8. Attachment D Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale: 1" = 50'

Site Geologic Map Scale: 1'' = 50'

Site Soils Map Scale (if more than 1 soil type): 1" = 200'

9. Method of collecting positional data:

		Global Positioning System (GPS) technology. Other method(s). Please describe method of data collection:
10.		The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11.	\boxtimes	Surface geologic units are shown and labeled on the Site Geologic Map.
12.		Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
		Geologic or manmade features were not discovered on the project site during the field investigation.
13.	\boxtimes	The Recharge Zone boundary is shown and labeled, if appropriate.
14.		known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If olicable, the information must agree with Item No. 20 of the WPAP Application Section.
		There are <u>0</u> (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.) The wells are not in use and have been properly abandoned. The wells are not in use and will be properly abandoned. The wells are in use and comply with 16 TAC Chapter 76. There are no wells or test holes of any kind known to exist on the project site.
A	dm	ninistrative Information
15.		Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional

copies to these jurisdictions. The copies must be submitted to the appropriate regional

office.

ATTACHMENT A

GEOLO	GEOLOGIC ASSESSMENT TABLE	AENT TABLE				2.2			PROJECT NAME: Ridgewood Lot 13 - Phase 1	Æ: I	Ridgewood Lo	ot 13 - Phase	11					1		
	LOCATION	N						FE	FEATURE CHARACTERISTICS	ACT	ERISTICS				EV	EVALUATION	NOI		HYSIC	PHYSICAL SETTING
1A	18.	10.	7 2	28	en .	_	4		5	ð	9	7	8A	88	6		10		-	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POWIE	FORMATION		DOMEN BACHYS (FEET)	EET)	THEND (DEGREES)	2	DENSITY (NOFT)	APERTURE (PECT) INFILLING	MHILIMO	RELATIVE INFILTRATION RATE	1012	SEM	SEMBITMIT	CATCHE	CATCHELENT APEA (ACPES)	THAMPOONED.
						×	<u>}</u>	2		2						09%	뮋	110	77	
S-1	29.61741	-98.46419	MB	30	Kep	387				_			F,C	20	52		20		×	Hillside/Floodplain
S-2	29.61776	-98.46166	MB	30	Kep								D,H	ഹ	35	35			×	Drainage
										_										
	2					_				_										
										L										
						L				L										
** DATIIM: NAD 83	· NAD 83																			

DATUM: NAD 83

Note: Only those geologic and man-made features within that area of the assessment are included. Therefore, the features may not be numbered sequentially.

2A TYPE	TYPE	2B POINTS		8A INFILLING
ပ	Саув	30	z	None, exposed bedrock
SC	Solution cavity	20	ပ	Coarse - cobbles, breakdown, sand, gravel
SF	Solution-enlarged fracture(s)	20	0	Loose or soft mud or soil, organics, feaves, sticks, dark colors
ı	Fault	20	Ľ	Fines, compacted clav-rich sediment, soil profile, gray or red colors
0	Other natural bedrock features	ιΩ	>	Vegetation. Give details in narrative description
MB	Manmade feature in bedrock	30	S.	Flowstone, cements, cave deposits
SW	Swallow hofe	8	×	Other materials
SH	Sinkhale	20		
9	Non-karst closed depression	£C)		12 TOPOGRAPHY
7	Zone, clustered or aligned features	30	Cit.	Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed



I have read, I understood, and I have followed the Texas Commission on Environmental Quafity's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

TCEQ-0585-Table (Rev. 10-01-10)

ATTACHMENT B

Ridgewood Lot 13 - Phase 1 Stratigraphic Column

Period	Epoch	Group	Formation	Member	Thickness	Lithology	Hydro- logic Unit	Hydrostratigr aphic Unit	Hydrologic Function	Porosity	Cavern Development	
		Edwards	Kainer	Basal nodular	40–50	Moderately hard, shaly, nodular, burrowed mudstone to miliolid grainstone that also contains dolomite; contains dark, spherical textural features known as black rotund bodies; Ceratostreon texana, Caprina sp., miliolids, and gastropods	Edwards Aquifer	VIII	Aquifer, confining unit in areas without caves	IP, MO, BU, BP, FR, CV	Large lateral caves at surface	
					0–120 (absent in northern Comal Co.)		s aquifer	Cavernous	Aquifer	MO, BR, BP, FR, CV		
	:			Upper Glen	120–230 (thicker in northern Comal Co.)	Alternating resistant and nonresistant beds of blue shale, nodular marl, and impure, fossiliferous limestone; gray to yellowish gray; stair-step topography; contains two distinct	Upper Trinity Lower confining unit to the Edwards aquifer	Camp Bullis	Confining	BU, BP, FR, occasional CV	Some surface	
				Rose	0-10	evaporite zones; distinct <i>Corbula</i> sp. bed marks the contact with the underlying lower member of the Glen Rose	Upper Trinity ig unit to the E	Upper evaporite	Aquifer	IP, MO, BU, BR	cave development	
					0-40	Limestone; Orbitulina texana	U Duffining	Fossil- Upper	Aquifer	MO, BU, FR, CV		
snos	Early Cretaceous				80–150		wer coi	iferous Lower	Confining	MO, BU, FR		
Cretaceous	ly Cre				8–10		Lo	Lower evaporite	Aquifer	IP, MO, BU, BR		
	Ea	Trinity	Glen Rose Limestone		30-40 (typ. 30)			Bulverde	Semi- confining	MO, BR BP, FR		
					30-40 (typ. 30)			Little Blanco	Aquifer	MO, BU, BP, FR		
				Lower	10-66 (typ. 30)	Massive, fossiliferous limestone grading upward into thin beds of limestone, dolomite, marl, and shale; numerous	rinity	Twin Sisters	Semi- confining, confining shale beds	ſΡ		
				Glen Rose	40-80 (typ. 40)	caves and reefs occur in the lower portion of the member; Orbitulina texana, Caprina sp., Toucasia sp., Trigonia sp., Turritella sp., miliolids, and various corals common;	Middle	Middle Trinity Doeppen- schmidt	Aquifer	IP, MO, BU, BP, FR, CV		
					4070 (typ. 40)	contains trace fossil burrows, oysters, pectens, and shell fragments		Rust	Semi- confining	IP, FR, CV		
				sh and Marsia (201		45–60 (typ. 55)	w Spin and Owne (1995). Recently three - Februar election ID interpretials recen		Honey Creek	Aquifer	IP, MO, BU, BP, FR, CH, CV	

Source: Clark, Golab, and Morris (2016); Cavern development modified from Stein and Ozuna (1995). Porosity types - Fabric selective: IP, interparticle porosity; IG, intergranular porosity; IC, intercrystalline porosity; SH, shelter porosity; MO, moldic porosity; BU, burrowed porosity; FE, fenestral; BP, bedding plane porosity. Not fabric selective: FR, fracture porosity; CH, channel porosity; BR, breccia; VUG, vug porosity; CV, cave porosity.

ATTACHMENT C

Ridgewood Lot 13 - Phase 1 Site Geology

NARRATIVE SUMMARY:

The overall potential for fluid migration to the Edwards Aquifer for the site is low. The dominant trend for the site is N55°E, based on an average of the trends of faults on site and in the surrounding area.

The site is located in the leached and collapsed (Keplc) and regional dense (Keprd) members of the Person Formation and the grainstone (Kekg) member of the Kainer Formation. The Keplc is characterized by interbedded, iron-stained, massive and bioturbated limestone with abundant chert. The Keprd is a dense, thinly-bedded, argillaceous mudstone. The Kekg is characterized by a white, crossbedded, milliolid grainstone and mudstone.

Karst development within the Keplc is characterized by very large sinkholes and a combination of lateral and vertical caves. Cave development within the regional dense member is uncommon. Furthermore, the Keprd may act as a vertical barrier to most cave development within the thin overlying portion of the leached and collapsed members. Karst development within the Kekg is characterized by few caves.

No sensitive karst features were observed on site during site reconnaissance.

FEATURE DESCRIPTIONS:

Features S-1

Feature S-1 is an existing sewer line that is not located beneath pavement. The sewer line has been trenched through bedrock and backfilled with a mix of fine and course fill material that may be more permeable than surrounding undisturbed areas. Therefore, the probability of rapid infiltration is intermediate.

Features S-2

Feature S-2 is an existing storm drain that is beneath pavement. Therefore, the probability of rapid infiltration is low.

REFERENCES:

Clark, A.K., Golab, J.A., and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers Within Northern Bexar and Comal Counties, Texas: U.S. Geological Survey Scientific Investigations Map 3366, scale 1:24,000, 20 p. pamphlet.

Nationwide Environmental Title Research, LLC. *Historical Aerials*. <u>historicalaerials.com</u>. Web. 10/24/2017.

Stein, W.G. and Ozuna, G.B., 1995, Geologic Framework and Hydrogeologic Characteristics of the Edwards Aquifer Recharge Zone, Bexar County, Texas: U.S. Geological Survey, Water-Resources Investigations Report 95-4030, 8 pp., 1 fig., 1 pl.


Texas Water Development Board, Wells in TWDB Groundwater Database Viewer,

Ridgewood Lot 13 - Phase 1 Site Geology


http://www2.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer, 10/24/2017.

United States Geological Survey. <u>US Topo: Bulverde Quadrangle</u>. 7.5-Minute Series. Denver, CO: USGS, 2016.

ATTACHMENT D



Date: Jun 21, 2018 10:57:07 AM User: HSI



ABOVEGROUND STORAGE TANK FACILITY PLAN (TCEQ-0575)

Aboveground Storage Tank Facility Plan Application

Texas Commission on Environmental Quality

For Permanent Storage on The Edwards Aquifer Recharge and Transition Zones And Relating to 30 TAC §213.5(e), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Aboveground Storage Tank Facility Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: <u>Dennis Rion, P.E.</u>

Date: 9-18-23

Signature of Customer/Agent:

Regulated Entity Name: Ridgewood Lot 13

Aboveground Storage Tank (AST) Facility Information

1. Tanks and substance stored:

Table 1 - Tank and Substance Storage

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
1	600	Diesel	Steel (DW)
2			
3			
4			

AST Number	Size (Gallons)	Substance to be Stored	Tank Material
5			

Total x 1.5 = 900 Gallons

- 2. The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.
 - Attachment A Alternative Methods of Secondary Containment. Alternative methods for providing secondary containment are proposed. Specifications that show equivalent protection for the Edwards Aquifer are attached.
- 3. Inside dimensions and capacity of containment structure(s):

Table 2 - Secondary Containment

Length (L) (Ft.)	Width (W) (Ft.)	Height (H) (Ft.)	L x W x H = (Ft3)	Gallons
16.33	5.83	2.58	245.6	1,837

Total: 1,837 Gallons

	10tan <u>1,007</u> danor
4.	All piping, hoses, and dispensers will be located inside the containment structure.
	 Some of the piping to dispensers or equipment will extend outside the containment structure. ☐ The piping will be aboveground ☐ The piping will be underground
5.	The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of double walled steel.
5.	Attachment B - Scaled Drawing(s) of Containment Structure. A scaled drawing of the containment structure that shows the following is attached:
	 ✓ Interior dimensions (length, width, depth and wall and floor thickness). ✓ Internal drainage to a point convenient for the collection of any spillage. ✓ Tanks clearly labeled. ✓ Piping clearly labeled. ✓ Dispenser clearly labeled.

Site Plan Requirements

Items 7 - 18 must be included on the Site Plan.

7.	\square The Site Plan must have a minimum scale of 1" = 400'.
	Site Plan Scale: 1" = <u>50</u> '.
8.	100-year floodplain boundaries:
	 Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled. No part of the project site is located within the 100-year floodplain.
	The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): <u>DFIRM for Bexar County, Texas panel 48029C0255G, effective 09/29/2010 and LOMR 10-06-3707P, effective 12/8/210</u> .
_	
9.	The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Show lots, recreation centers, buildings, roads, etc.
	The layout of the development is shown with existing contours. Finished topographic contours will not differ from the existing topographic configuration and are not shown.
10.	. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):
	There are (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply):
	The wells are not in use and have been properly abandoned.
	The wells are not in use and will be properly abandoned.The wells are in use and comply with 16 TAC § 76.
	There are no wells or test holes of any kind known to exist on the project site.
11.	. Geologic or manmade features which are on the site:
	All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.
	No sensitive geologic or manmade features were identified in the Geologic Assessment.
	Attachment C - Exception to the Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached.
12.	. $igstyle igstyle igy igstyle igy igstyle igy igstyle igy igy igstyle igy igy igy igy igy igy igstyle igy igy igy igy igy igy igy igy$
13.	. Areas of soil disturbance and areas which will not be disturbed.
14.	. \(\sum \) Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.

15.	\times Locations where soil stabilization practices are expected to occur.
16.	Surface waters (including wetlands). N/A
17.	☐ Locations where stormwater discharges to surface water or sensitive features.☐ There will be no discharges to surface water or sensitive features.
18.	Legal boundaries of the site are shown.
В	est Management Practices
19.	Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.
	 In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly. In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.
20.	 ✓ All stormwater accumulating inside the containment structure will be disposed of through an authorized waste disposal contractor. ✓ Containment area will be covered by a roof. ✓ Containment area will not be covered by a roof.
	A description of the alternate method of stormwater disposal is submitted for the executive director's review and approval and is attached.
21.	Attachment D - Spill and Overfill Control. A site-specific description of the methods to be used at the facility for spill and overfill control is attached.
22.	Attachment E - Response Actions to Spills. A site-specific description of the planned response actions to spills that will take place at the facility is attached.
A	dministrative Information
23.	A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.
	 The WPAP application for this project was approved by letter dated <u>03/27/2019</u>. A copy of the approval letter is attached at the end of this application. The WPAP application for this project was submitted to the TCEQ on, but has not been approved. A WPAP application is required for an associated project, but it has not been submitted.

	 There will be no building or structure associated with this project. In the event a building or structure is needed in the future, the required WPAP will be submitted to the TCEQ. The proposed AST is located on the Transition Zone and a WPAP is not required. Information requested in 30 TAC 213.5 subsection (b) (4)(B) and (C) and (5) is provided with this application. (Forms TCEQ-0600 Permanent Stormwater Section and TCEQ-0602 Temporary Stormwater Section or Stormwater Pollution Prevention Plan/SW3P).
24. 🔀	This facility is subject to the requirements for the reporting and cleanup of surface spills and overfills pursuant to 30 TAC 334 Subchapter D relating to Release Reporting and Corrective Action.
25. 🔀	Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
26. 🔀	Any modification of this AST Facility Plan application will require executive director approval, prior to construction, and may require submission of a revised application, with appropriate fees.

ATTACHMENT A

RIDGEWOOD LOT 13

Aboveground Storage Tank Facility Plan

Attachment A - Alternative Methods of Secondary Containment

The proposed Aboveground Storage Tank (AST) to be used at Ridgewood Lot 13 is a base-mounted, double-wall, steel construction with sealed interstitial spaces. The proposed useable fuel capacity is 531 gallons to provide runtime for the standby generator.

Fuel Tank Description

The proposed AST will be used to store diesel fuel for an onsite generator utilized by TSAOG. The concrete pad is within a locked enclosure between the parking garage building and MOB Building, as shown in the Exhibits section. The double-walled fuel tank is constructed to the UL-2085 standard and is fire safe with an additional 5-gallon spill containment bucket for overfill protection during fueling. The proposed piping is directly connected from the base-mounted diesel tank to the generator within the weather and sound enclosure, so the piping system is not exposed. The proposed AST is double walled for secondary containment as required by TCEQ, and the interstitial space is filled with lightweight, chemically hardened concrete.

The tank is constructed of materials that are compatible with the liquids stored within (diesel) and have the appropriate safety equipment such as primary and emergency venting, overfill protection, and fire valves.

The primary tank is wholly containing within a secondary tank, and the interstitial space is completely sealed with concrete. Therefore, if a failure occurs in the primary tank, all fuel will be trapped in the secondary tank. Additionally, because the interstice is sealed, storm water cannot enter the interstice and reduce the available containment volume. An interstitial space monitor will be placed in the interstice of the AST to alert the operator of a primary tank failure. The 5-gallon spill containment bucket will serve as overfill protection and secondary containment in the event of a minor spill during refueling.



ATTACHMENT B

Superior 274 County Rd 287
Systems & MeNed TX 79536
Technologies 1325-690 CO28 Fax: -4111

DRAWN BY: F.Ontiveros 1321-11-19

SHEET: 1 OF 1

JOB NAME: RIDGEWOOD MOB

P.O.#: ---- GENSET: C18-600
NAME: ---- LBS

APPROVED AS IS: Manufacturing may proceed

APPROVED WITH NOTED CHANGES: Resubmit drawing: manufacturing may proceed.

APPROVED WITH NOTED CHANGES: Resubmit drawing: manufacturing may proceed.

DATE: 12-11-19

SHEET: 1 OF 1

JOB NAME: RIDGEWOOD MOB

REVISION: B

DRAWING #: SBGVT-600-07127 REV2

NOT APPROVED: Correct drawing as noted and resubmit for approval before manufacturing begins.

Bill of Materials:

Quantity	Description
1	EPA STATIONARY EMERGENCY
1	60HZ 480 VOLT (WYE)
1	600ekW, 60Hz, 1800rpm
1	C18 D600GC PGS
1	UL 2200 LISTED PACKAGE GEN SET
1	ENGLISH INSTRUCTION LANGUAGE
1	STANDARD WARRANTY
1	ADEM A4 GOVERNOR
1	SPACE HEATER
1	ALT M3175L4 SE DW
1	FULL POWER
1	C18 WIDE BASE
1	C18 SOUND ATTENUATED LVL2 (WHITE) w/MUFFLER
1	600 GALLON, UL2085, SUB BASE TANK
1	ENCLOSURE LIGHTS
1	NFPA BUNDLE
1	GEN RUNNING & FAULT RELAY
1	PANEL MOUNTED AUDIBLE ALARM
1	EXTERNAL EMERGENCY STOP
1	1000CCA WET BAT 90A/HR INSTAL
1	BATTERY CHARGER 10 AMP DUAL
1	JACKET WATER HTR (PUMP STYLE)
1	1000:5 CT RATIO
1	800A LSI BREAKER (DIALED DOWN TO 600A)
1	400A LSI BREAKER
1	100A LSI BREAKER
1	STANDARD RADIATOR
1	REMOTE E-STOP BUTTON 16LIGHT NFPA 99/110 ANNUNCIAT
1	STD TEST - PKG GEN SET 0.8 PF
1	ALTERNATOR TEST REPORT
1	PGS TEST REPORT @ 0.8 PF
1	PGS IEST KEPOKT W U.8 PF

- Qty. 1 **600A**, Open Transition Automatic Transfer Switch, 4 pole, 480V, 3 Phase, supplied in a NEMA 1 Enclosure
- Qty. 1 **400A**, Open Transition Automatic Transfer Switch, 4 pole, 480V, 3 Phase, supplied in a NEMA 1 Enclosure
- Qty. 1 **100A**, Open Transition Automatic Transfer Switch, 4 pole, 480V, 3 Phase, supplied in a NEMA 1 Enclosure
- Qty. 1 **100A**, **Trystar Docking Station**, 480V, 3 Phase supplied in a NEMA 3R Enclosure

Cat® C18 GC DIESEL GENERATOR SETS



Standby: 60Hz, 480V & 600V



Engine Model	Cat® C18 ACERT™ In-line 6, 4-cycle diesel
Bore x Stroke	145mm x 183mm (5.7in x 7.2in)
Displacement	18.1 L (1106 in³)
Compression Ratio	14.5:1
Aspiration	Turbocharged Air-to-Air Aftercooled
Fuel Injection System	MEUI
Governor	Electronic ADEM™A4

PACKAGE PERFORMANCE

Standby	Performance Strategy
COO - L/M/ 7EO L/M	EPA Certified for Stationary
600 ekW, 750 kVA	Emergency Application

Performance	Stand	by				
Frequency	60 Hz	60 Hz				
Genset Power Rating	750 kV	'A				
Gen set power rating with fan @ 0.8 power factor	600 ek					
Fuelling strategy	TIER	II				
Performance Number	DM85	18				
Fuel Consumption						
100% load withfan	161.1 L/hr	35.4 gal/hr				
75% load with fan	129.6 L/hr	28.5 gal/hr				
50% load with fan	91.7 L/hr	20.2 gal/hr				
25% load with fan	46.8 L/hr	12.3 gal/hr				
Cooling System ¹						
Radiatorair flow restriction (system)	0.12 kPa	0.48 in. Water				
Radiatorair flow	803 m3/min	28357 cfm				
Engine coolant capacity	20.8 L	5.5 gal				
Radiatorcoolantcapacity	61 L	16 gal				
Total coolant capacity	82 L	22 gal				
Inlet Air						
Combustion air inlet flow rate	47.8 m³/min	994.3 cfm				
Max. Allowable Combustion Air Inlet Temp	49 ° C	122°F				
Exhaust System						
Exhaust stack gas temperature	534.6°C	994.3°F				
Exhaust gas flow rate	135.5 m³/min	4784.4 cfm				
Exhaust system backpressure (maximum allowable)	10.0 kPa	40.0 in. water				
Heat Rejection						
Heat rejection to jacket water	180 kW	10236 Btu/min				
Heat rejection to exhaust (total)	595 kW	33837 Btu/min				
Heat rejection to aftercooler	141 kW	8019 Btu/min				
Heat rejection to atmosphere from engine	77 kW	4379 Btu/min				
Heat rejection from alternator	33 kW	1854 Btu/min				

LEHE2013-04 1/2

Cat® C18 GC DIESEL GENERATOR SETS



ARFP

234°F


130°

Emissions(Nominal) ²	Stand	lby
NOx	2703.5 mg/Nm ³	5.5 g/hp-hr
CO	161.0 mg/Nm ³	0.3 g/hp-hr
HC	4.6 mg/Nm³	0.01 g/hp-hr
PM	13.2 mg/Nm³	0.03 g/hp-hr
Alternator ³	Stand	lby
Voltages	480V	600V
Motor Starting Capability @ 30% Voltage Dip	1199	1292
Current	902.1	721.7
Frame Size	M3175L4	M3156L4

WEIGHTS & DIMENSIONS – OPEN SET

Excitation

Temperature Rise




Base	Dim "A" mm (in)	Dim "B" mm (in)	Dim "C" mm (in)	Generator Set Weight kg (lb)
Skid (Wide Base)	4980 (196.1)	1865 (73.4)	2009 (79.1)	4064 (8959.6)
Integral Tank base	4815 (189.6)	1630 (64.2)	2560 (100.8)	5283 (11647.0)

189°

Shunt Excitation

105°C



DEFINITIONS AND CONDITIONS:

¹ For ambient and altitude capabilities consult your Cat dealer. Air flow restriction (system) is added to existing restriction from factory.

² Emissions data measurement procedures are consistent with those described in EPA CFR 40 Part 89, Subpart D & E and ISO8178-1 for measuring HC, CO, PM, NOx. Data shown is based on steady state operating conditions of 77° F, 28.42 in HG and number 2 diesel fuel with 35° API and LHV of 18,390 BTU/lb. The nominal emissions data shown is subject to instrumentation, measurement, facility and engine to engine variations. Emissions data is based on 100% load and thus cannot be used to compare to EPA regulations which use values based on a weighted cycle.

³UL 2200 Listed packages may have oversized generators with a different temperature rise and motor starting characteristics. Generator temperature rise is based on a 40° C ambient per NEMA MG1-32.

APPLICABLE CODES AND STANDARDS:

AS1359, CSA C22.2 No100-04, UL142, UL489, UL869, UL2200, NFPA37, NFPA70, NFPA99, NFPA110, IBC, IEC60034-1, ISO3046, ISO8528, NEMA MG1-22, NEMA MG1-33, 2006/95/EC, 2006/42/EC, 2004/108/EC.

Note: Codes may not be available in all model configurations. Please consult your local Cat Dealer representative for availability.

STANDBY: Output available with varying load for the duration of the interruption of the normal source power. Average power output is 70% of the standby power rating. Typical operation is 200 hours per year, with maximum expected usage of 500 hours per year.

RATINGS: Ratings are based on SAE J1349 standard conditions. These ratings also apply at ISO3046 standard conditions.

Fuel Rates are based on fuel oil of 35° API [16° C (60° F)] gravity having an LHV of 42 780 kJ/kg (18,390 Btu/lb) when used at 29° C (85° F) and weighing 838.9 g/litre (7.001 lbs/U.S. gal.). Additional ratings may be available for specific customer requirements, contact your Caterpillar representative for details. For information recarding Low Sulfur fuel and Biodiesel capability, please consult your Cat dealer.



LEHE2013-04 (11-19)

Cat® GC Control Panel





Image shown might not reflect actual configuration

GCCP 1.2 - Control Panel

GCCP 1.2 is an auto Start Control Module suitable for a wide variety of diesel genset applications. Monitoring an extensive number of engine parameters, the modules will display warnings, shutdown and engine status information on the backlit LCD screen, illuminated LEDs and remote PC.

FEATURES

- 4-line back-lit LCD text display
- Multiple display languages
- Five-key menu navigation
- LCD alarm indication
- Customisable power-up text and images
- Data logging facility
- Internal PLC editor
- · Protections disable feature
- Fully configurable via PC using USB & RS485 communication
- Front panel configuration with PIN protection
- Power save mode
- 3-phase generator sensing and protection
- Generator current and power monitoring (kW, kvar, kVA, pf)
- kW and kvar overload and reverse power alarms
- Over current protection
- Unbalanced load protection
- Breaker control via fascia buttons
- Fuel and start outputs configurable when using CAN
- Support for 0 V to 10 V & 4 mA to 20 mA sensors
- 8 configurable digital inputs (3 available for Customer use)
- 8 configurable digital outputs (5 available for Customer use)
- 4 configurable analogue outputs (3 available for Customer Use)
- CAN, MPU and alternator frequency speed sensing in one variant
- Real time clock
- Engine pre-heat and post-heat functions
- Engine run-time scheduler
- Engine idle control for starting & stopping
- Fuel usage monitor and low fuel level alarms
- 3 configurable maintenance alarms

BENEFITS

- Hours counter provides accurate information for monitoring and maintenance periods
- User-friendly set-up and button layout for ease of use
- Multiple parameters are monitored & displayed simultaneously for full visibility
- The module can be configured to suit a wide range of applications for user flexibility
- PLC editor allows user configurable functions to meet user specific application requirements.
- RS485 Communication port can be used for the Remote Monitoring Communication (Compatible with Cat PLG)

SPECIFICATION

DC SUPPLY

CONTINUOUS VOLTAGE RATING

8 V to 35 V Continuous 5 V for upto 1 minute

CRANKING DROPOUTS

Able to survive 0 V for 100 mS, providing supply was at least 10 V before dropout and supply recovers to 5 V. This is achieved without the need for internal batteries.

LEDs and backlight will not be maintained during cranking.

MAXIMUM OPERATING CURRENT

260 mA at 12 V. 150 mA at 24 V

MAXIMUM STANDBY CURRENT

145 mA at 12 V, 85 mA at 24 V

CHARGE FAIL/EXCITATION RANGE

0 V to 35 V

GENERATOR & MAINS (UTILITY) VOLTAGE RANGE

15 V to 415 V AC (Ph to N) 26 V to 719 V AC (Ph to Ph)

FREQUENCY RANGE

3.5 Hz to 75 Hz

MAGNETIC PICKUP VOLTAGE RANGE

+/- 0.5 V to 70 V

FREQUENCY RANGE

10.000 Hz (max)

INPUTS DIGITAL INPUTS A TO H

Negative switching

ANALOGUE INPUTS A & D

Configurable as:

Negative switching digital input 0 V to 10 V sensor 4 mA to 20 mA sensor Resistive sensor

ANALOGUE INPUTS B & C

Configurable as:

Negative switching digital input Resistive sensor

OUTPUTS OUTPUT A & B (FUEL & START)

15 A DC at supply voltage

117

AUXILIARY OUTPUTS C, D, E, F, G & H 2 A DC at supply voltage

DIMENSIONS OVERALL

216 mm x 158 mm x 43 mm 8.5" x 6.2" x 1.5"

PANEL CUT-OUT

184 mm x 137 mm

MAXIMUM PANEL THICKNESS

8 mm

STORAGE TEMPERATURE RANGE

-40°C to +85°C -40 °F to +185 °F

OPERATING TEMPERATURE RANGE

-30°C to +70°C -22 °F to +158 °F

LEHE2017-01 (11-19)

Cat® GC Control Panel Options





Remote Annunciator Module

It is an LED expansion module that can be used with compatible control modules. The module has been designed to display a maximum of eight individual LED indications up to a maximum distance of 1 KM (0.6miles).

The Annunciator will consist of two modules to provide a 16 Channel Fault annunciation.

It is presented in a vertical enclosure. It includes an alarm sounder that is triggered when the host controller detects an alarm condition. The alarm can be muted using the front push button.

The Panels will be fitted with removable label cards which can be used to identify the standard NFPA alarms. If desired

It includes individual LEDs for each channel and a 'Power On' LED that flashes when the link with the host controller is lost.

FEATURES

- The Remote annunciator has an integral Sounder / Horn
- Eight configurable LEDs (per module)
- Works up to 1 KM (0.6 miles) from the host controller
- A single Controller can support five Caterpillar Configured remote annunciator control boxes

ENVIRONMENTAL TESTING STANDARDS

ELECTRO-MAGNETIC COMPATIBILITY

BS EN 61000-6-2

EMC Generic Immunity Standard for the Industrial Environment BS EN 61000-6-4

EMC Generic Emission Standard for the Industrial Environment

ELECTRICAL SAFETY

BS FN 60950

Safety of Information Technology Equipment, including Electrical Business Equipment

TEMPERATURE

BS EN 60068-2-1

Ab/Ae Cold Test -30 °C BS EN 60068-2-2 Bb/Be Dry Heat+70°C

VIBRATION

BS EN 60068-2-6

Ten sweeps in each of three major axes 5 Hz to 8 Hz @ +/-7.5 mm, 8 Hz to 500 Hz @ 2 gn

SHOCK

BS EN 60068-2-27

Three shocks in each of three major axes 15 gn in 11 Ms

HUMIDITY

BS EN 60068-2-30

Db Damp Heat Cyclic 20/55 $\,^{\circ}\text{C}$ @ 95% RH 48 Hours BS EN 60068-2-78

Cab Damp Heat Static 40 °C @ 93% RH 48 Hours

<u>DEGREES OF PROTECTION PROVIDED BY ENCLOSURES BS EN</u> 60529

IP65 - Front of module when installed into the control panel with the supplied sealing gasket.

SPECIFICATION

CONTINUOUS VOLTAGE RATING

8 V to 35 V Continuous

CRANKING DROPOUTS

Able to survive 0 V for 50 mS, providing supply was at least 10 V before dropout and supply recovers to 5 V. This is achieved without the need for internal batteries. LEDs and backlight will not be maintained during cranking.

MAXIMUM OPERATING CURRENT

112 mA at 12 V, 53 mA at 24 V

MAXIMUM STANDBY CURRENT

74 mA at 12 V, 35 mA at 24 V

DIMENSIONS OVERALL

275.5 mm x 214.2 mm x 108.8 mm 10.85" x 8.43" x 4.28"

MAXIMUM PANELTHICKNESS

 $8\;\text{mm}$

0.3"

Cat® GC ENCLOSURES





SOUND ATTENUATED LEVEL 2 ENCLOSURES D250GC - D600GC 60 Hz

FEATURES

Robust / Highly Corrosion Resistant Construction

- Factory installed on skid base or tanks base
- Environmentally friendly, polyester powder baked paint
- Enclosure constructed with 18-gauge steel
- Interior zinc plated fasteners
- Internally mounted exhaust silencing system
- Comply with ASCE/SEI 7 for Wind loads up to 100mph
- Designed and tested to comply with UL 2200 Listed generator set package

Excellent Access

- Large cable entry area for installation ease.
- Accommodates side mounted single or multiple breakers.
- Two doors on both sides.
- Vertically hinged allow 180° opening rotation
- Radiator fill cover.

Security and Safety

- Lockable access doors which give full access to control panel and breaker.
- Cooling fan and battery charging alternator fully guarded.
- Fuel fill, oil fill and battery can only be reached via lockable access.
- Externally mounted emergency stop button (Optional).
- Designed for spreader bar lifting to ensure safety.
- Stub-up area is rodent proof.

Sound Attenuated Level 2

- Caterpillar white paint
- UL Listed integral fuel tank with 24 hours running time capacity (Optional).
- DC lighting package (Optional)

Cat® GC ENCLOSURES




Enclosure Package Operating Characteristics


Enclosure Type	Standby ekW	Cooling Ra	Ambient Capability*		Sound Pressure Levels (dBA) at 7m (23 ft)	
		m³/s	cfm	°C	°F	100% Load
Level 2 Sound Attenuated Enclosure (Steel)	250	6.4	13561	57	135	74
	300	6.4	13561	51	125	74
	350	7.4	15680	57	134	71
	400	7.4	15680	53	127	71
	450	8.4	17692	54	130	73
	500	8.4	17692	50	122	73
	550	11.2	23731	56	133	73
	600	11.2	23731	53	127	73

^{*}Cooling system performance at sea level. Consult your Cat® dealer for site specific ambient and altitude capabilities.

Note: Sound level measurements are subject to instrumentation, installation and manufacturing variability, as well as ambient site conditions.

DIMENSIONS





Sound Attenuated Enclosure on Skid Base





Image shown might not reflect actual configuration



Sound Attenuated Enclosure on a UL Listed Integral Fuel Tank Base

Cat® GC ENCLOSURES



WEIGHTS & DIMENSIONS

Enclosure Type	Standby Ratings,	Length, L		Width,W		Height, H		Package Weights	
	ekW	mm	in	mm	in	mm	in	kg	lb
Sound Attenuated Enclosure on	250	3958	155.8	1440	56.7	1991	78.4	2857	6298.6
Skid Base	300	3330	100.8	1440	50.7	1331	70.4	2945	6492.6
	350	4633	182.4	1630	64.2	2227	87.7	3983	8781.0
	400	4033	182.4	1030	04.2	2221	07.7	4017	8856.0
	450	4823	189.8	1630	64.2	2777	109.3	4408	9718.0
	500	4823						4457	9826.0
	550	4000	100.1	1005	70.4	2722	107.0	4754	10480.8
	600	4980	196.1	1865	73.4	2723	107.2	4837	10663.8
Sound Attenuated Enclosure on	250	2050	155.8	1440	56.7	2487	97.9	3497	7709.6
UL Listed Integral Fuel Tank	300	3958	100.0	1440	30.7	2407	97.9	3585	7903.6
Base	350	4633	182.4	1630	64.2	1.2 2644	104.1	4765	10505.0
	400	4033			04.2			4799	10580.0
	450	4823	189.8	1630	64.2	2777	109.3	5345	11783.7
	500	4023	109.0	1030	04.2	2///	109.5	5394	11891.7
	550	4000	106 1	1005	70.4	2722	107.2	5973	13168.2
	600	4980	196.1	1865	73.4	2723	107.2	6056	13351.2

LET'S DO THE WORK.

LEHE2014-02 (09-19)





Remote Emergency Stop Button


Image shown may not reflect actual configuration.


Features and Benefits

- Enclosure degree of protection IP 66 Type 1, 3R, 4, 4X, 12, 13
- UL Listed (NKCR)
- Assembled enclosure with shroud
- 40 mm mushroom emergency stop
- Twist release
- 2NC horizontally mounted

Dimensions


Net Width: 0.065 m
Net Height: 0.078 m
Net Depth: 0.065 m
Net Weight: 0.124 kg






THIS DIAGRAM IS FOR GC GENSET MODELS (250kW to 600kW) FOR USE WITH: C9, C13, C15 & C18 ENGINES 6310 CONTROLLER













INDEX TABLE

NOTE A: FACTORY WIRING NOT PROVIDED AS STANDARD, REFER TO MANUFACTURER INSTALLATION INSTRUCTION
NOTE B: CONTACT OPEN IN DE-ENERGIZED STATE OR FAULT CONDITION.
NOTE C. DESIGNAD TO BE DEMOVED IS ADDITIONAL EVIDADIONAL MODULE OF ADS CONNECTED.












ADDITIONAL INFORMATION - COMPONENT DETAILS & CUSTOMER CONNECTIONS







ATTACHMENT D

RIDGEWOOD LOT 13

Aboveground Storage Tank Facility Plan

Attachment D - Spill and Overfill Control

The proposed Aboveground Storage Tank (AST) to be used at Ridgewood Lot 13 is a base-mounted, double-wall, steel construction with sealed interstitial spaces. The proposed useable fuel capacity is 531 gallons to provide runtime for the standby generator.

Fuel Tank Description

The proposed AST will be used to store diesel fuel for an onsite generator utilized by TSAOG. The concrete pad is within a locked enclosure located between the parking garage building and MOB building, as shown in the Exhibits section. The double-walled fuel tank is constructed to the UL-2085 standard and is fire safe with an additional 5-gallon spill containment bucket for overfill protection during fueling. The proposed piping is directly connected from the base-mounted diesel tank to the generator within the weather and sound enclosure, so the piping system is not exposed. The proposed AST is double walled for secondary containment as required by TCEQ, and the interstitial space is filled with lightweight, chemically hardened concrete.

The tank is constructed of materials that are compatible with the liquids stored within (diesel) and have appropriate safety equipment such as primary and emergency venting, overfill protection, and fire valves.

The primary tank is wholly contained within a secondary tank, and the interstitial space is completely sealed with concrete. Therefore, if a failure occurs in the primary tank, all fuel will be trapped in the secondary tank. Additional, because the interstice is sealed, storm water cannot enter the interstice and educe available containment volume. An interstitial space monitor will be placed in the interstice of the AST to alert the operator of a primary tank failure. The 5-gallon spill containment bucket will serve as overfill protection and secondary containment in the event of a minor spill during refueling.

There is a leak detection switch installed in the interstitial space of the tank inside the stub up area. This is programmed to alarm at the generator control panel and secondary annunciator panel located at the nurse's station where it is continuously monitored

Additional details of the Fuel Storage and Safety equipment specifications can be found in the AST Facility Plan Application section.

Base-Mounted Fuel Tank Factory installed and piped, complying with the UL-2085 fuel tank includes the following features:

- a. Double-wall, steel construction piping and tanks
- b. Mechanical fuel level gauge
- c. 5-gallon spill containment bucket
- d. Containment Provisions comply with UL-2085
- e. A manual shutoff valve on the common engine supply line and a drain valve
- f. All interconnecting pipes and hoses; threaded pipe connections
- g. Interstitial space leak detectors and rupture alarm contacts
- h. Low-level alarm sensor
- i. Emergency vents on primary and secondary tanks sized in accordance with NFPA 30



RIDGEWOOD LOT 13

Aboveground Storage Tank Facility Plan

AST Filling

Spill prevention for the AST filling will be achieved at the fuel filling with a lockable cap and 5-gallon spill containment box with lockable hinge. This system includes all valves and fittings necessary for hose connection from the pumper truck.

Human presence and observation of the filling process is another means to prevent spills and overfills. There shall be an experienced trained person at the fill point at all times that a fill operation is taking place. The refueling tanker trucks are equipped with fuel spill containment kits for minor spills.



ATTACHMENT E

RIDGEWOOD LOT 13

Aboveground Storage Tank Facility Plan

Attachment E – Response Actions to Spills

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

- The contractor will be required to report significant or hazardous spills in reportable quantities to:
 - the National Response Center at (800) 424-8802
 - the Edwards Aquifer Authority at (210) 222-2204
 - the TCEQ Regional Office (210) 490-3096 (if during business hours: 8 AM to 5 PM) or
 - the State Emergency Response Center (800) 832-8224 (if after hours)
- Contaminated soils will be sampled for waste characterization. When the analysis results are known
 the contaminated soils will be removed from the site and disposed in a permitted landfill in
 accordance with applicable regulations.




RIDGEWOOD LOT 13 Aboveground Storage Tank Facility Plan

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.



SITE PLAN



TEMPORARY STORMWATER SECTION (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC $\S213.5(b)(4)(A)$, (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Dennis Rion, P.E.

Date: 9-18-23

Signature of Customer/Agent:

Regulated Entity Name: Ridgewood Lot 13

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: <u>construction</u> staging area

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

	 Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year. Aboveground storage tanks with a cumulative storage capacity of 500 gallons or 			
	more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.			
	Fuels and hazardous substances will not be stored on the site.			
2.	Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.			
3.	Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.			
4.	Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.			
Sequence of Construction				
5.	Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.			
	 For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given. For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented. 			
ŝ.	Name the receiving water(s) at or near the site which will be disturbed or which will			

Temporary Best Management Practices (TBMPs)

receive discharges from disturbed areas of the project: Salado Creek

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

	A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
	A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
	A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
	A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8.	The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
	Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
	There will be no temporary sealing of naturally-occurring sensitive features on the site.
9.	Attachment F - Structural Practices . A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10.	Attachment G - Drainage Area Map . A drainage area map supporting the following requirements is attached:
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
	For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
	For areas that will have more than 10 acres within a common drainage area
	disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

	There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. 🗌	Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
\boxtimes	N/A
12. 🔀	Attachment I - Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. 🔀	All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. 🔀	If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. 🗌	Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. 🔀	Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
Soil	Stabilization Practices
mulchi	les: establishment of temporary vegetation, establishment of permanent vegetation, ng, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or

17. Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A

Aboveground Storage Tank Facility Plan

Attachment A - Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in
 the event of a significant hazardous/reportable quantity spill. Additional notifications as required by
 the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. https://www.tceq.texas.gov/response/spills/spill_rq.html
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.



Aboveground Storage Tank Facility Plan

- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction
 personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at
 the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.



ATTACHMENT B

Aboveground Storage Tank Facility Plan

Attachment B - Potential Sources of Contamination

Other potential sources of contamination during construction include:

Potential Source

- Asphalt products used on this project.
- Preventative Measure
- After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain.
- Potential Source Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping.

Preventative Measure

- Vehicle maintenance when possible will be performed within the construction staging area.
- Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.
- Potential Source Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.

Preventative Measure

- Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.
- Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.
- Hazardous materials and wastes shall be stored in covered containers and protected from vandalism.
- A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.
- Potential Source Miscellaneous trash and litter from construction workers and material wrappings.
- Preventive Measure Trash containers will be placed throughout the site to encourage proper trash disposal.
- Potential Source Preventive Measure
- Construction debris.
 - Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.



Aboveground Storage Tank Facility Plan

Potential Source • Spills/Overflow of waste from portable toilets

Preventative Measure

- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

ATTACHMENT C

RIDGEWOOD LOT 13 Aboveground Storage Tank Facility Plan

Attachment C – Sequence of Major Activities

The overall site is fully constructed and was at the time of AST installation, however as part of the construction activities these practices were employed.

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include installation of TBMPs, clearing and grubbing of vegetation where applicable. This will disturb approximately 0.02 acres. The second is construction that will include installation of the aboveground storage tank. This will disturb approximately 0.02 acres.



ATTACHMENT D

Aboveground Storage Tank Facility Plan

Attachment D – Temporary Best Management Practices and Measures

The overall site is fully constructed, however as part of the construction activities these practices were employed.

a. A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

No upgradient water will cross the site. All TBMPs are adequate for the drainage areas they serve.

b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.



Aboveground Storage Tank Facility Plan

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.



ATTACHMENT F

Aboveground Storage Tank Facility Plan

Attachment F - Structural Practices

The overall site is fully constructed; however, the following structural measures would be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 1 and illustrated in Exhibit 2.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 1, and illustrated on Exhibit 2.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

• Installation of concrete truck washout pit(s), as required and located on Exhibit 1 and illustrated on Exhibit 2.



ATTACHMENT G

RIDGEWOOD LOT 13 Aboveground Storage Tank Facility Plan

Attachment G - Drainage Area Map

No more than ten (10) acres will be disturbed for the proposed project. All TBMPs utilized are adequate for the drainage areas served.



ATTACHMENT I

Aboveground Storage Tank Facility Plan

INSPECTIONS

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.



Aboveground Storage Tank Facility Plan

Pollution		Corrective Action Required						
Prevention		Description.	Data					
Measure		Description	Date Completed					
	Inspected	(use additional sheet if necessary)	Completed					
Best Management Practices								
Natural vegetation buffer strips								
Temporary vegetation								
Permanent vegetation								
Sediment control basin								
Silt fences								
Rock berms								
Gravel filter bags								
Drain inlet protection								
Other structural controls								
Vehicle exits (off-site tracking)								
Material storage areas (leakage)								
Equipment areas (leaks, spills)								
Concrete washout pit (leaks, failure)								
General site cleanliness								
Trash receptacles								
Evidence of Erosion			·					
Site preparation								
Roadway or parking lot construction								
Utility construction								
Drainage construction								
Building construction								
Major Observations								
Sediment discharges from site								
BMPs requiring maintenance								
BMPs requiring modification								
Additional BMPs required								
A brief statement describing the qualifications of the inspector is included in this SWP3. "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including								
the possibility of fine and imprisonment for knowing v		the provisions of 20 TAC \$205 420 "						
"I further certify I am an authorized signatory in accor	uance willi	the provisions of 30 TMC 3303.120.						
Inspector's Name	Inspector	's Signature Date						

RIDGEWOOD LOT 13 Aboveground Storage Tank Facility Plan

PROJECT MILESTONE DATES

Date when major site grading activities begin: **Construction Activity** Date Installation of BMPs Dates when construction activities temporarily or permanently cease on all or a portion of the project: **Construction Activity** <u>Date</u> Dates when stabilization measures are initiated: **Stabilization Activity** Date

Removal of BMPs

ATTACHMENT J

RIDGEWOOD LOT 13 Aboveground Storage Tank Facility Plan

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.



AGENT AUTHORIZATION FORM (TCEQ-0599)

Agent Authorization Form

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I	Ronald Bullock	
	Print Name	
	Chief, Surgical Services	
	Title - Owner/President/Other	
of	Sonterra Medical Management Group, Inc.	
	Corporation/Partnership/Entity Name	
have authorized	Pape-Dawson Engineers, Inc.	
	Print Name of Agent/Engineer	
of	Pape-Dawson Engineers, Inc.	
	Print Name of Firm	

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Applicant's Signature Date

THE STATE OF Leveus §
County of beginn §

BEFORE ME, the undersigned authority, on this day personally appeared London Bull known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 3nd day of May, 2023

VIKKI J. GOMEZ

Notary Public, State of Texas

Comm. Expires 07-01-2026

Notary ID 11802436

NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 07 01 202

Owner Authorization Form

Texas Commission on Environmental Quality

for Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Land Owner Authorization

ı, of	
Land Owner Signatory Name	Land Owner Name (Legal Entity or Individual)
am the owner of the property located at	
Legal description of the	property referenced in the application
	$\S213.4(c)(2)$ and $\S213.4(d)(1)$ or $\S213.23(c)(2)$ and n application, signatory authority, and proof of authorized
I do hereby authorize	
Applicant	t Name (Legal Entity or Individual)
to conduct	
Description of t	the proposed regulated activities
at	<u>.</u>
Precise location of	f the authorized regulated activities
Land Owner Acknowledger	nent
I understand that	

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Land Owner Name (Legal Entity or Individual)

Land Owner Signature VP of Property Management of AHP Management 2, L.L.C., authorized agent of CPI/AHP Ridgewood San Antonio MOB 9.4.23 Date Land Owner Signature THE STATE OF & Kenneske County of § Dickson Moore BEFORE ME, the undersigned authority, on this day personally appeared _ known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed. GIVEN under my hand and seal of office on this _____ day of **NOTARY PUBLIC** Typed or Printed Name of Notary MY COMMISSION EXPIRES: 16-20-2026 Attached: (Mark all that apply) STATE OF Lease Agreement TENNESSEE NOTARY **Signed Contract**

Deed Recorded Easement

Y Other legally binding document

Applicant Acknowledgement

I, Ronald Bullock of	Sonterra Medical Management Group, Inc.							
Applicant Signatory Name	Applicant Name (Legal Entity or Individual)							
acknowledge that CPI/AHP Ridgewood San Antonio MOB Owner, LP								
Land Owner Name (Legal	Entity or Individual)							
has provided Sonterra Medical Management Group,	Inc.							
Applicant Name (Legal E	intity or Individual)							
with the right to possess and control the property refe								
I understand that Sonterra Medical Management Gro	oup, Inc.							
Applicant Name (Lega	l Entity or Individual)							
is contractually responsible for compliance with the ap Aquifer protection plan and any special conditions of t implementation. I further understand that failure to c director's approval is a violation is subject to administrunder §213.10 (relating to Enforcement). Such violation injunction.	he approved plan through all phases of plan omply with any condition of the executive rative rule or orders and penalties as provided							
Applicant Signature								
Applicant Signature	9-/4-2023 Date							
THE STATE OF § 908								
County of § Beylin	0 100 11-01							
BEFORE ME, the undersigned authority, on this day pe known to me to be the person whose name is subscrib acknowledged to me that (s)he executed same for the GIVEN under my hand and seal of office on this	purpose and consideration therein expressed.							
VIKKI J. GOMEZ Notary Public, State of Texas Comm. Expires 07-01-2026 Notary ID 11802436	Typed or Printed Name of Notary MY COMMISSION EXPIRES: 01 01 2026							

APPLICATION FEE FORM (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality Name of Proposed Regulated Entity: Ridgewood Lot 13 Regulated Entity Location: 19138 US Hwy 281 N, San Antonio, TX 78258 Name of Customer: Sonterra Medical Management Group, Inc. Contact Person: Ronald Bullock Phone: (210) 489-7278 Customer Reference Number (if issued):CN Regulated Entity Reference Number (if issued):RN 105282206 **Austin Regional Office (3373)** Williamson Hays **Travis** San Antonio Regional Office (3362) Uvalde ⋉ Bexar Medina Comal Kinney Application fees must be paid by check, certified check, or money order, payable to the **Texas** Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: **Austin Regional Office** San Antonio Regional Office Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier **Revenues Section** 12100 Park 35 Circle Mail Code 214 Building A, 3rd Floor P.O. Box 13088 Austin, TX 78753 Austin, TX 78711-3088 (512)239-0357 Site Location (Check All That Apply): Recharge Zone **Contributing Zone Transition Zone** Type of Plan Size Fee Due Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling Acres Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks Acres Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential Acres Sewage Collection System L.F. Acres | \$ Lift Stations without sewer lines Underground or Aboveground Storage Tank Facility 1 Tanks | \$ 650

Each | \$

Each

Piping System(s)(only)

Exception

Type of Plan	Size	Fee Due	
Extension of Time	Each	\$	



Date: 9-13-23

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Contributing Lone Flans and Floameatiens	Project Area in	
Project	Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial,	<1	\$3,000
institutional, multi-family residential, schools, and	1<5	\$4,000
other sites where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
·	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

	Cost per Linear	Minimum Fee-		
Project	Foot	Maximum Fee		
Sewage Collection Systems	\$0.50	\$650 - \$6,500		

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee
Exception Request	\$500

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150

CORE DATA FORM (TCEQ-10400)



TCEQ Use Only

TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)											
New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)											
Renewal (Core Data Form should be submitted with the renewal form)											
2. Customer	2. Customer Reference Number (if issued) Follow this link to search 3. Regulated Entity Reference Number (if issued)										
CN	for CN or RN numbers in										
SECTION	II: Cu	stomer Info	<u>ormation</u>								
4. General C	ustomer l	nformation	5. Effective D	ate for Cu	stomer	Inform	atio	n Updat	es (mm/dd/yyyy)		
New Cust		ne (Verifiable wit	- •	odate to Cus					Change in Public Accounts)	Regulated E	Entity Ownership
		•		<u> </u>						rrent and	active with the
		State (SOS)	-	•			•				
6. Customer	Legal Nar	ne (If an individua	, print last name i	first: eg: Doe,	John)			If new Cu	stomer, enter previ	ous Custome	er below:
Sonterra N	/ledical	Management	Group, Inc								
7. TX SOS/CI	_	Number	8. TX State T		ts)				al Tax ID (9 digits)	10. DUN	S Number (if applicable)
01630924	00		320034734	413				74-300	6020		
11. Type of C	ustomer:		on		Individ	ual		Pai	rtnership: 🗌 Gener	al Limited	
Government:	City (County Federal	☐ State ☐ Other		Sole P	roprieto	rshi	р 🗆	Other:		
12. Number o □ 0-20 ▷	of Employ 21-100	ees 101-250	<u> 251-500</u>	☐ 501 ar	nd high	er		13. Indep Yes	pendently Owned	and Opera	ted?
14. Custome	r Role (Pro	oposed or Actual) -	as it relates to th	ne Regulated	Entity li	sted on	this f	orm. Pleas	se check one of the	following	
Owner			or	□ 0	wner &	Operat	tor				
Occupatio	nal Licens	ee Respo	nsible Party	□ V	oluntar	y Clean	up A	Applicant	Other:		
45 84 99	19138	US Hwy 28	l N								
15. Mailing Address:											
	City	San Antonio	o	State	TX		ZIP	7825	58	ZIP + 4	
16. Country I	Mailing In	formation (if outsi	de USA)			17. E-	Mail	l Addres:	S (if applicable)		
						rbull	ock	x@tsao	_		
18. Telephon	e Numbe	•		19. Extensi	on or (Code			20. Fax Numbe	r (if applicat	ole)
(210)48	(210) 489-7278 (210) 582-2677										
SECTION III: Regulated Entity Information											
21. General Regulated Entity Information (If 'New Regulated Entity" is selected below this form should be accompanied by a permit application)											
□ New Regulated Entity □ Update to Regulated Entity Name □ Update to Regulated Entity Information											
The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal											
of organizational endings such as Inc, LP, or LLC).											
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)											
Ridgewood Lot 13											


TCEQ-10400 (02/21) Page 1 of 2

23. Street Address	1	19138 US Hwy 281 N											
the Regulated Entit													
(No PO Boxes)	· -	ity	SanAnton		State	TX	ZIP	78	258	ZIP	+ 4		
24. County		Bexar	Sum III	CIIIO	- Clare	171		170	200				
			nter Physic	al I or	cation Description	n if no str	eet ad	dress is n	rovided	_			
AT D			iller i riyote	ai Loc	sation bescriptic)	oot uu	idi coo io p	TOTIGOGI				
25. Description to Physical Location:			,							*1			
26. Nearest City								Stat				rest ZIP Code	
San Antonio				<u>i</u>		TX			782				
27. Latitude (N) In Decimal							28. Longitude (W) In			-98.4625		5-5-82	
Degrees	Mi	inutes			econds	Degree	Degrees		Minutes			Seconds	
29		37			04.8		-98		27			45.2	
29. Primary SIC Code (4 digits)			Secondary	SIC	Code (4 digits)	31. Primary No. (5 or 6 digits)		ICS Code	32. S (5 or 6	econdary NAICS Code digits)			
1542	8011				236220			621111					
33. What is the Pri					o not repeat the SIC	or NAICS des	cription.)					
Aboveground s	storage	tank fo	or medic	al off	fice building								
24 Mailing					i i	19138 l	JS Hw	y 281 N					
34. Mailing Address:													
Address.		City San Anton		itonio	State	TX	Z	IP.	78258		+ 4		
35. E-Mail Add	dress:		1			rbull	lock@	tsaog.con	n			•	
36. Te	elephone	e Numbe	ř		37. Extensio	n or Code			38. Fax Nu	ımber <i>(it</i>	appl	icable)	
(2		(210) 582-2677											
39. TCEQ Programs a						rmits/registra	ation nu	imbers that	will be affected	d by the u	pdates	submitted on this	
☐ Dam Safety		Districts			⊠ Edwards Aqui	ifer		☐ Emissions Inventory		☐ Industrial Hazardous Waste			
☐ Municipal Solid Waste		☐ New Source Review Air			OSSF		☐ Petroleum Sto		Storage Tank	☐ PWS			
Sludge		Storm Water			☐ Title V Air		Tires		Us		Jsed Oil		
		DW					Mater Diele		-		Oll		
☐ Voluntary Cleanup		Waste Water			☐ Wastewater A	Agriculture	<u> LL</u>	☐ Water Rights		Other:			
SECTION IV:	Prep	arer Iı	nformat	tion									
40. Jean Au	Jean Autrey P.F. CESSWI					41. Title: Project			Manager				
42. Telephone Number 43. Ext./Code 44. Fax Number						45 F-N	45. E-Mail Address						
(210) 375-9000	504					jautrey@pape-dawson.com							
SECTION V:	Auth	<u>orized</u>	Signat	ure									
46. By my signature signature authority to identified in field 39.	below, I submit th	certify, to	the best of on behalf of	my kr	nowledge, that the tity specified in S	informatio lection II, F	on prov ield 6	vided in thi and/or as r	s form is true required for the	e and con he update	aplete es to t	, and that I have he ID numbers	
Company:	Pape-Da	Dawson Engineers, Inc.				Job Title	e:	Executive	e Vice President				
Name (In Print):	•	nis Rion, P.E.								(210) 375-9000			
Signature: Date: 9-18-23											-23		

TCEQ-10400 (02/21) Page 2 of 2

EXHIBITS





SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT

. THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN. 2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS

A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2, A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE. 4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OR

AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE. . THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE

FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER. 3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG. 4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE, 4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD. 5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN,

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED. 6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE. 7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A

SEDIMENT TRAP OR BASIN. 8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD

SECTION "A-A" OF A CONSTRUCTION ENTRANCE/EXIT

COMMON TROUBLE POINTS 1. INADEQUATE RUNOFF CONTROL-SEDIMENT WASHES ONTO PUBLIC ROAD. 2. STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY CONDITION AS STONE IS PRESSED INTO SOIL. 3. PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC-EXTEND PAD BEYOND THE MINIMUM 50-FOOT LENGTH AS NECESSARY. TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.

4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING 5. UNSTABLE FOUNDATION - USE GEOTEXTILE FABRIC UNDER PAD AND/OR IMPROVE FOUNDATION DRAINAGE. INSPECTION AND MAINTENANCE GUIDELINES THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL

PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY.

PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.

DITCH OR WATER COURSE BY USING APPROVED METHODS.

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

NOT-TO-SCALE

THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ARE STABILIZED AND ACCUMULATED SILT REMOVED. 2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR. 3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT

CORRECT

SECTION "A-A"

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER

ISOMETRIC PLAN VIEW

INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.

EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

2. REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION. 3. REPAIR ANY LOOSE WIRE SHEATHING.

. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC. 3. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS

PLAN VIEW

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION.

SAND BAGS WITH

SEE GRAVEL FILTER_

FILTER FABRIC-

BAG DETAIL

THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE

INSTALLATION I. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH 2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER. 3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18". 4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON. 5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE. 6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.

COMMON TROUBLE POINTS INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM). 2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

. CONTRACTOR TO INSTALL 2"x4"-W1.4xW1.4 WIRE MESH SUPPORTING FILTER

FABRIC OVER THE INLET OPENING. FABRIC MUST BE SECURED TO WIRE BACKING

WITH CLIPS OR WIRE TIES AT THIS LOCATION. SAND BAGS FILLED WITH WASHED

WITH WASHED PEA GRAVEL SHOULD ALSO BE PLACED ALONG THE GUTTER AS

STACKED TO FORM A CONTINUOUS BARRIER AROUND INLETS.

RUNOFF FROM FLOWING BETWEEN THE BAGS.

A MANNER THAT IT WILL NOT ERODE.

SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SAND BAGS TO BE

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT

REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH


CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND

5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING.

THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE



. THE SANDBAGS SHOULD BE FILLED WITH WASHED PEA GRAVEL AND STACKED TO FORM A CONTINUOUS BARRIER ABOUT 1 FOOT HIGH AROUND

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS. INSPECTION AND MAINTENANCE GUIDELINES 1. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.

2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MATTER THAT IT WILL NOT ERODE 3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR 5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

BAGGED GRAVEL GRATE INLET PROTECTION DETAIL NOT-TO-SCALE

SEDIMENT CONTROL ROLLSSediment Control Rolls are elongated tubes of compacted **CONTROL APPLICATION** straw and/or other fibers that are installed along contours or at the base of slopes to help reduce soil erosion and retain sediment. They function by shortening slope length, reducing

WATER FLOW

WORK AREA

Core material: Core materials shall be biodegradable nad noxious weed free. Material may be compost, mulch, aspen excelsior wood fibers, chipped site vegetation, agricultural rice or wheat straw, coconut fiber, or other 100% biodegradable Containment mesh: containment mesh shall be 100% biodegradable, photodegradable or recyclable such as burlap

twine, UV photodegradable plastic or polyester. Use biodegradable or photodegradable mesh when wattle will remain in place as part of a vegetative system. Use recyclable mesh for temporary installations. Wattles shall have a minimum diameter of 8 inches and a maximum diameter of 20 inches. No more than 5% of the fill material shall be permitted to escape from the containing mesh. Mesh shall be 0.5" x 0.5" high density polyethylene and ethyly vinyl acetate and contain ultra-violet inhibitors. Wattle ends shall be tied closed.

runoff water velocity, trapping dislodged soil particles and reducing the effects of slope steepness.

CROSS-SECTION

MENT CONTROL ROLLS IN A TEMPORARY EROSION CONTROL APPLICATION When no longer required for the intended purpose, temporary rolls shall be removed from the site. As an option, the straw rolls may be slit down the length of the netting and the straw may be used on slopes or other areas.

Trenches, depressions or any other ground disturbances caused by the removal of the temporary straw rolls shall be backfilled and repaired with the excess sediment captured by the rolls, prior to spreading the straw or other final erosion control

Leave rolls as installed to photodegrade or biodegrade over time as native and applied vegetation ultimately stabilize the

PLAN VIEW

STAKES PLACED 10" O.C

DENNIS R. RION

67109

AREA TO BE PROTECTED


repaired site. I. Remove all rocks, clods, vegetation or other obstructions so that the installed rolls will have direct contact with the soil. 2. A small trench, 2-4 inches in depth should be excavated on the slope contour and perpendicular to water flow. Soil from the excavation should be placed upslope next to the

3. Install the rolls in the trench, insuring that no gaps exist between the soil and the bottom of the roll. Roll should be lapped 6" minimum to prevent sediment passing through the 4. Wooden stakes should be used to fasten the rolls to the soil. When conditions warrant, a straight metal bar can be used to drive a "pilot hole" through the roll and into the soil. 5. Wooden stakes should be placed 6" from the roll end angled towards the adjacent roll and spaced at 4 feet centers leaving less than 1-2 inches of stake exposed above the roll. Alternately, stakes may be placed on each side of the roll tying across with with a natural fiber twine or staking in a crossing manner ensuring direct soil contact at all times. 6. Terminal ends of rolls may be "dog legged" up slope to ensure containment and prevent channeling of sediment.

7. Backfill the upslope length of the roll with the excavated soil and compact. 8. Care shall be taken during installation so as to avoid damage occurring to the roll as a result of the installation process. Should the roll be damaged during installation, a wooden stake shall be placed either side of the damaged area terminating the log segment.

1. The Sediment Control Rolls shall be inspected after installation to insure that they are trenched—in and that no gaps exist under the rolls or between adjacent ends of the 2. Rolls shall be inspected after significant rainfall events. Rills or gullies upslope of the roll and any undercutting is to be

SEDIMENT CONTROL ROLLS



NOT-TO-SCALE

SECTION "A-A BAGGED GRAVEL CURB INLET PROTECTION DETAIL NOT-TO-SCALE

FILTER FABRIC-

2"x 4"-W1.4x W1.4

SUPPORTING FABRIC

-WIRE MESH

ROCK BERM DETAIL

NOT-TO-SCALE

STEEL FENCE POST MAX. 6' SPACING, SILT FENCE MIN. EMBEDMENT = 1'(MIN. HEIGHT 24" (SEE INSTALLATION NOTE 1) ABOVE EXISTING GROUND) WIRE MESH BACKING COMPACTED FARTH 4X4~W1.4xW1.4 MIN. OR ROCK BACKFILL - ALLOWABLE TYPICAL CHAIN LINK FENCE FABRIC IS ACCEPTABLE

ISOMETRIC PLAN VIEW

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE. THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE I USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW. SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY

ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE

PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED

1. SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

2. FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS 3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

2. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.


3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP BACKFILLED WITH COMPACTED MATERIAL. ENDS OF FABRIC MEET. STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE. COMMON TROUBLE POINTS CONCENTRATE AND FLOW OVER THE FENCE. AROUND SIDES). 4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).

1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL. 2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES. 3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A

TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS. ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF. 4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES. 5. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS. **MATERIALS** PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL. MAINTENANCE 1. WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT

PIT DETAIL




PLAN VIEW

. THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND

SECTION "A-A"

ULTRAVIOLET STABILITY EXCEEDING 70%. 2. THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). 3. SAND SHALL NOT BE USED TO FILL THE FILTER BAGS.

GRAVEL FILTER BAG DETAIL NOT-TO-SCALE



19138 N. US HWY 281 SAN ANTONIO, TEXAS 78259

EGAL DESCRIPTION: BLOCK 5 N.C.B. 15671

PLAT NO. 070497

JOB NO. 6435-73 DATE OCTOBER 2018 DESIGNER DM/RW CHECKED_____ DRAWN_JF/R EX 2

SOD INSTALLATION DETAIL

NOT-TO-SCALE

-ROOT ZONE- SOIL AND ROOTS. SHOULD BE 1/2"-3/4" THICK, WITH DENSE ROOT MAT FOR STRENGTH. APPEARANCE OF GOOD SOD INCORRECT I. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE SOD INSTALLATION WATER TO A DEPTH OF 4" AS NEEDED. WATER WELL AS SOON AS THE SOD IS LAID. 3. MOW WHEN THE SOD IS ESTABLISHED - IN 2-3 WEEKS. SET THE MOWER HIGH (2"-3"). USE PEGS OR STAPLES TO FASTEN SOD TRMLY - AT THE ENDS OF STRIPS AND N THE CENTER, OR EVERY 3-4 FEET IF THE STRIPS ARE LONG. WHEN READY TO MOW, DRIVE PEGS OR STAPLES FLUSH IN CRITICAL AREAS, SECURE SOD WITH THE GROUND. WITH NETTING. USE STAPLES.

-SHOOTS OR GRASS BLADES.

CUTTING HEIGHT.

GRASS SHOULD BE GREEN AND

HEALTHY; MOWED AT A 2"-3"

— THATCH— GRASS CLIPPINGS AND

DEAD LEAVES, UP TO 1/2" THICK.

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH (± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE SHOOT GROWTH AND THATCH. 2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND LENGTH, WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%. TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE. 3. STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION. 4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD

LAY SOD IN A STAGGERED PATTERN. BUTT

THE STRIPS TIGHTLY AGAINST EACH OTHER.

DO NOT LEAVE SPACES AND DO NOT

OVERLAP. A SHARPENED MASON'S TROWEL

IS A HANDY TOOL FOR TUCKING DOWN THE

<u>BUTTING</u> — ANGLED ENDS CAUSED BY THE AUTOMATIC SOD CUTTER MUST BE MATCHED

ENDS AND TRIMMING PIECES.

LAY SOD ACROSS THE

CORRECTLY.

OF 36 HOURS.

SITE PREPARATION PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN. 2. THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS. FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

INSTALLATION IN CHANNELS 1. SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS TIGHTLY (SEE FIGURE ABOVE). 2. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL

GENERAL INSTALLATION (VA. DEPT. OF CONSERVATION, 1992) SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER.

SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN. 2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND REDUCE ROOT BURNING AND DIEBACK. 3. THE FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM SROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT

IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OR OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR). 5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL. . AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS 7. UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED. IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4

. SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO

2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE

RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS

LOCATE AND REPAIR ANY DAMAGE.

DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery ® 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

SOON AS PRACTICAL.

8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED. USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING. INSPECTION AND MAINTENANCE GUIDELINES

> INSTALLATION 1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.

WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM 4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND . SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER 3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING

INSPECTION AND MAINTENANCE GUIDELINES

5. WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE

SILT FENCE DETAIL

NOT-TO-SCALE

MIN. 10 MIL PLASTIC LATH AND FLAGGING ON ALL SIDES -SAND BAGS (TYP.) PIT PLAN VIEW MIN. 10 MIL PLASTIC -SAND BAGS (TYP.)

FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

NOT-TO-SCALE

SECTION "A-A"

CONCRETE TRUCK WASHOUT

CONSTRUCTION

FLOW ARROWS CONSTRUCTION STAGING AREA NOT-TO-SCALE

THIS SHEET HAS BEEN PREPARED FOR PURPOSES

ENGINEERING RELATED INFORMATION SHOULD BE

ACQUIRED FROM THE APPROPRIATE SHEET IN TH

CIVIL IMPROVEMENT PLANS.

OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON

ENVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL **EXHIBIT 2** PLAT # 070497 PROJECT VISION, ENCLAVE