

SAWS E-54 TEMPORARY LIFT STATION

**Sewage Collection System Modification & Lift
Station Application**

January 2024



January 9, 2024

Ms. Lillian Butler
Texas Commission on Environmental Quality
Region 13
14250 Judson Road
San Antonio, Texas 78233-4480

Re: SAWS E-54 Temporary Lift Station
Sewage Collection System Modification and Lift Station Application

Dear Ms. Butler:

Please find included herein the SAWS E-54 Temporary Lift Station Sewage Collection System Modification and Lift Station Application. This Sewage Collection System Modification Application has been prepared to be consistent with the regulations of the Texas Administrative Code (30 TAC 213, 217 and 290) and current policies for development over the Edwards Aquifer Recharge Zone.

This Sewage Collection System Modification and Lift Station Application applies to the approximately 0.51-acre project limits. Please review the plan information for the items it is intended to address. If acceptable, provide a written approval of the plan in order that construction may begin at the earliest opportunity.

Appropriate review fees (\$650) and fee application form are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,
Pape-Dawson Engineers



Jason T. Diamond, P.E.
Vice President

Attachments

P:\115\00\51\Word\Reports\SCS - LS\240105a1.Docx

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification & Lift Station Application

January 2024



**EDWARDS AQUIFER
APPLICATION COVER PAGE
(TCEQ-20705)**

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name:				2. Regulated Entity No.:					
3. Customer Name:				4. Customer No.:					
5. Project Type: (Please circle/check one)	New	<u>Modification</u>		Extension	Exception				
6. Plan Type: (Please circle/check one)	WPAP	CZP	<u>SCS</u>	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Residential		<u>Non-residential</u>		8. Site (acres):				
9. Application Fee:			10. Permanent BMP(s):						
11. SCS (Linear Ft.):			12. AST/UST (No. Tanks):						
13. County:			14. Watershed:						

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	—	—	—	—
Region (1 req.)	—	—	—	—	—
County(ies)	—	—	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Print Name of Customer/Authorized Agent

Jason T. Diamond

01/16/2024

Signature of Customer/Authorized Agent

Date

****FOR TCEQ INTERNAL USE ONLY****

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

**GENERAL INFORMATION
FORM (TCEQ-0585)**

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Jason T. Diamond, P.E.

Date: 01/16/2024

Signature of Customer/Agent:

Jason T. Diamond

Project Information

1. Regulated Entity Name: SAWS E-54 Temporary Lift Station
2. County: Bexar
3. Stream Basin: Upper Salado Creek
4. Groundwater Conservation District (If applicable): Edwards Aquifer; Trinity-Glen Rose
5. Edwards Aquifer Zone:
 Recharge Zone
 Transition Zone
6. Plan Type:
 WPAP
 SCS
 Modification
 AST
 UST
 Exception Request

7. Customer (Applicant):

Contact Person: Cristina Brantley, P.E.

Entity: San Antonio Water System (SAWS)

Mailing Address: 2800 US Hwy 281

City, State: San Antonio, TX

Zip: 78212

Telephone: (210) 233-3939

FAX: (210) 233-4966

Email Address: cristina.brantley@saws.org

8. Agent/Representative (If any):

Contact Person: Jason T. Diamond, P.E.

Entity: Pape-Dawson Engineers

Mailing Address: 2000 NW Loop 410

City, State: San Antonio, TX

Zip: 78213

Telephone: (210) 375-9000

FAX: (210) 375-9010

Email Address: jdiamond@pape-dawson.com

9. Project Location:

- The project site is located inside the city limits of San Antonio.
- The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of _____.
- The project site is not located within any city's limits or ETJ.

10. The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

From TCEQ's regional office, head north on Judson Road approximately 2.5 miles to Loop 1604. Proceed north on Loop 1604 approximately 1.8 miles and turn right on Bulverde Road. Proceed north on Bulverde Road approximately 1.1 miles and turn right on Gold Canyon. The project site is located approximately 2,500 feet east of the intersectino of Bulverde Road and Gold Canyon.

11. **Attachment A – Road Map.** A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
12. **Attachment B - USGS / Edwards Recharge Zone Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:
- Project site boundaries.
 - USGS Quadrangle Name(s).
 - Boundaries of the Recharge Zone (and Transition Zone, if applicable).
 - Drainage path from the project site to the boundary of the Recharge Zone.
13. **The TCEQ must be able to inspect the project site or the application will be returned.** Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate

the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

Survey staking will be completed by this date: When advised by TCEQ of site visit

14. **Attachment C – Project Description.** Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

- Area of the site
- Offsite areas
- Impervious cover
- Permanent BMP(s)
- Proposed site use
- Site history
- Previous development
- Area(s) to be demolished

15. Existing project site conditions are noted below:

- Existing commercial site
- Existing industrial site
- Existing residential site
- Existing paved and/or unpaved roads
- Undeveloped (Cleared)
- Undeveloped (Undisturbed/Uncleared)
- Other: _____

Prohibited Activities

16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
- (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
- (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
- (4) The use of sewage holding tanks as parts of organized collection systems; and
- (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
- (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

18. The fee for the plan(s) is based on:

- For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
- For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
- For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
- A request for an exception to any substantive portion of the regulations related to the protection of water quality.
- A request for an extension to a previously approved plan.

19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:


- TCEQ cashier
- Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
- San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21. No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

ATTACHMENT A


SAWS E-54 SANITARY SEWER PROJECT Sewage Collection System Modification



ATTACHMENT B

SAWS E-54 SANITARY SEWER PROJECT
Sewage Collection System Modification


SCALE: 1" = 2000'



Date: Jun 13, 2022, 3:51pm, User ID: cally
File: P:\15\00\51\Design\Environmental\SCS\SCS_M02_00150051.dwg


GENERAL LOCATION MAP - LONGHORN, TX QUAD
DRAINAGE FLOW 
Pape-Dawson Engineers, Inc.

Matchline - See Sheet 2 of 2

USGS/EDWARDS RECHARGE ZONE MAP
Sheet 1 of 2
ATTACHMENT B

SAWS E-54 SANITARY SEWER PROJECT
Sewage Collection System Modification

Matchline - See Sheet 1 of 2



Date: Jun 13, 2022, 3:51pm User ID: cally
File: P:\115\00\51\Design\Environmental\SCS\SCS_M02_001150051.dwg

GENERAL LOCATION MAP - LONGHORN, TX QUAD
DRAINAGE FLOW → → →
Pape-Dawson Engineers, Inc.

USGS/EDWARDS RECHARGE ZONE MAP
Sheet 2 of 2
ATTACHMENT B

ATTACHMENT C

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification & Lift Station Application

Attachment C – Project Description

The SAWS E-54 Temporary Lift Station and Sewage Collection System Modification (SCS MOD) is a modification of the previously approved SAWS E-54 Sanitary Sewer Project SCS MOD (EAPP ID No 13001558), approved on July 22, 2022. The approved SAWS E-54 Sanitary Sewer Project has been designed to handle SAWS-provided flows from four existing lift stations north of the project limits (Fox Grove, Fossil Ridge, Cibolo Canyons, and Fischer). The project lies within the Upper Salado Creek watershed over the Edwards Aquifer Recharge Zone. No naturally occurring sensitive features were identified within the SCS envelope in the Geological Assessment.

This SAWS E-54 Temporary Lift Station is intended to temporarily bypass flows from the proposed Brookstone residential subdivision development to the existing SAWS Fox Grove Lift Station until such time that the SAWS E-54 Regional Lift Station (currently under construction) is put into service. When the E-54 Regional Lift Station is put into service, flows from the Brookstone development will be conveyed conventionally through a gravity main to the E-54 Regional Lift Station, and the E-54 Temporary Lift Station pumps and force main will be taken out of service and removed from the site. The E-54 Temporary Lift Station wetwell will consist of a four-foot (4') diameter fiberglass reinforced plastic (FRP) wetwell that has been constructed and hydro-statically tested as part of the SAWS E-54 Sanitary Sewer Project. Two Xylem/Gould submersible pumps will be placed in the manhole to temporarily convey the Brookstone sanitary sewer flow to the Fox Grove lift station via two (2) temporary 3-inch (3") PVC force mains. Each force main will convey the flow from each pump in the wetwell. At peak flow rates, the proposed submersible pumps will operate concurrently and discharge flow through their respective force mains. No permanent modifications to the existing, approved sewer plans are proposed with this application.

Approximately 201 EDUs will flow to the temporary lift station, for an average daily flow of 40,200 gallons (201 EDU x 200 gpd/EDU = 40,200 gpd). The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by SAWS. Potable water will be supplied by SAWS.

GEOLOGIC ASSESSMENT FORM
(TCEQ-0585)

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Henry E. Stultz III, P.G.

Telephone: 210-375-9000

Date: June 10, 2021

Fax: 210-375-9090

Representing: Pape-Dawson Engineers, Inc., TBPB registration number 50351

Signature of Geologist:





Regulated Entity Name: E-54 Sanitary Sewer

Project Information

1. Date(s) Geologic Assessment was performed: January 2019; April 22, and May 12, 2021

2. Type of Project:

WPAP

AST

SCS

UST

3. Location of Project:

Recharge Zone

Transition Zone

Contributing Zone within the Transition Zone

4. **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

Soil Name	Group*	Thickness(feet)
Crawford, stony and Bexar soils, 0-5 % slopes (Cb)	D	1-3
Eckrant cobbly clay, 1-8 % slopes (TaB)	D	0-1
Eckrant very cobbly clay, 5-15 % slopes (TaC)	D	0-1

* Soil Group Definitions (Abbreviated)

- A. Soils having a high infiltration rate when thoroughly wetted.
- B. Soils having a moderate infiltration rate when thoroughly wetted.
- C. Soils having a slow infiltration rate when thoroughly wetted.
- D. Soils having a very slow infiltration rate when thoroughly wetted.

6. **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
7. **Attachment C – Site Geology.** A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
8. **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'
 Applicant's Site Plan Scale: 1" = 200'
 Site Geologic Map Scale: 1" = 200'
 Site Soils Map Scale (if more than 1 soil type): 1" = 2000'
9. Method of collecting positional data:
 - Global Positioning System (GPS) technology.
 - Other method(s). Please describe method of data collection: _____
10. The project site and boundaries are clearly shown and labeled on the Site Geologic Map.
11. Surface geologic units are shown and labeled on the Site Geologic Map.

12. Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.
- Geologic or manmade features were not discovered on the project site during the field investigation.
13. The Recharge Zone boundary is shown and labeled, if appropriate.
14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.
- There are ____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
- The wells are not in use and have been properly abandoned.
- The wells are not in use and will be properly abandoned.
- The wells are in use and comply with 16 TAC Chapter 76.
- There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A
Geologic Assessment Table

GEOLOGIC ASSESSMENT TABLE

PROJECT NAME: E-54 Sanitary Sewer

LOCATION		FEATURE CHARACTERISTICS										EVALUATION			PHYSICAL SETTING			
1A	1B*	1C*	2A	2B	3	4			5	5A	6	7	8A	8B	9	10	11	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIMENSIONS (FEET)			TREND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	SENSITIVITY	CATCHMENT AREA (ACRES)	TOPOGRAPHY
						X	Y	Z								<40	<1.6	
S-1	29.60266	-98.41322	MB	30	Kep					10			F,C	20	50	50	X	Hillside, Floodplain
S-2	29.60548	-98.41314	F	20	Kep				N50E	10			F	5	35	35		Hillside, Floodplain
S-3	29.60916	-98.41320	F	20	Kep				N45E	10			F	5	35	35		Hillside, Floodplain
S-4	29.60999	-98.41489	F	20	Kep				N50E	10			F	5	35	35		Hillside, Floodplain
S-5	29.62454	-98.41266	F	20	Kep				N42E	10			F	5	35	35		Hillside, Floodplain
S-6	29.63606	-98.41127	F	20	Kep				N50E	10			F	5	35	35		Hillside, Floodplain
S-9	29.63995	-98.38597	F	20	Kep				N41E	10			F	5	35	35		Hillside, Floodplain
S-10	29.64507	-98.39879	MB	30	Kep								F,C	20	50	50	X	Hillside, Floodplain
S-11	29.64365	-98.39353	MB	30	Kep								F,C	20	50	50	X	Hillside, Floodplain
S-12	29.64236	-98.38641	MB	30	Kep								F,C	20	50	50	X	Hillside, Floodplain
S-13	29.63936	-98.40012	MB	30	Kep								F,C	20	50	50	X	Hillside, Floodplain
S-14	29.63892	-98.39743	MB	30	Kep								F,C	20	50	50	X	Hillside, Floodplain

** DATUM: NAD 83

2A TYPE	TYPE	2B POINTS
C	Cave	30
SC	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
O	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
SW	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

8A INFILLING

N None, exposed bedrock
 C Coarse - cobbles, breakdown, sand, gravel
 O Loose or soft mud or soil, organics, leaves, sticks, dark colors
 F Fines, compacted clay-rich sediment, soil profile, gray or red colors
 V Vegetation. Give details in narrative description
 FS Flowstone, cements, cave deposits
 X Other materials

12 TOPOGRAPHY

Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed

I have read, I understand, and I have followed the Texas Commission on Environmental Quality's instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

[Signature]

Date June 19, 2021



ATTACHMENT B
Stratigraphic Column

E-54 SANITARY SEWER Geologic Assessment (TCEQ-0585)

Attachment B – Stratigraphic Column

Period	Epoch	Group	Formation	Member	Thickness	Lithology	Hydro-logic Unit	Hydro-stratigraphic Unit	Hydrologic Function	Porosity	Cavern Development
Cretaceous	Early Cretaceous	Edwards	Person	Cyclic and marine, undivided	80–90	Pelletal limestone; ranges from chalk to mudstone and milliolid grainstone; thin to massive beds; some crossbedding evident; a packstone containing large caprinids is present near contact with the overlying Georgetown Formations; chert is common as beds and large nodules	Edwards Aquifer	II	Aquifer	MO, BU, VUG, BP, FR, CV	Many subsurface; might be associated with earlier karst development
				Leached and collapsed, undivided	70–90	Hard, dense, recrystallized limestone; mudstone, wackestone, packstone, and grainstone; contains chert as beds and large nodules; heavily bioturbated with iron-stained beds; often stromatolitic; <i>Toucasia</i> sp. Often found above contact with the underlying regional dense member; <i>Montastrea roemeriana</i> and oysters rare		III	Aquifer	BU, VUG, FR, BP, BR, CV	Extensive lateral development; large rooms
				Regional dense	20–24	Dense, shaly limestone; oyster shell mudstone and iron wackestone; wispy iron staining; chert nodules rarer than in the rest of the chert-bearing Edwards Group		IV	Confining	FR, CV	Very few; only vertical fracture enlargement
			Kainer	Grainstone	40–50	Hard, dense limestone that consists mostly of a tightly cemented milliolid skeletal fragment grainstone; contains interspersed chalky mudstone and wackestone; chert as beds and nodules; crossbedding and ripple marks are common primarily at the contact with the overlying regional dense bed		V	Aquifer	IP, IG, BU, FR, BP, CV	Few
				Kirsch-berg Evaporite	40–50	Highly altered crystalline limestone and chalky mudstone with occasional grainstone associated with tidal channels; chert as beds and nodules, boxwork molds are common, matrix recrystallized to a coarse grain spar; intervals of collapse breccia and travertine deposits		VI	Aquifer	IG, MO, VUG, FR, BR, CV	Probably extensive cave development
				Dolomitic	90–120	Hard, dense to granular, dolomitic limestone; chert as beds and nodules (absent in lower 20 ft); <i>Toucasia</i> sp. abundant; lower three-fourths composed of sucrosic dolomites and grainstones with hard, dense limestones interspersed; upper one-fourth composed mostly of hard, dense mudstone, wackestone, packstone, grainstone, and recrystallized dolomites with bioturbated beds		VII	Aquifer	IP, IC, IG, MO, BU, VUG, FR, BP, CV	Cave development as shafts with minor horizontal extent
				Basal nodular	40–50	Moderately hard, shaly, nodular, burrowed mudstone to milliolid grainstone that also contains dolomite; contains dark, spherical textural features known as black rotund bodies; <i>Ceratostreon texana</i> , <i>Caprina</i> sp., milliolids, and gastropods		VIII	Aquifer, confining unit in areas without caves	IP, MO, BU, BP, FR, CV	Large lateral caves at surface

Source: Clark, Golab, and Morris (2016); Cavern development modified from Stein and Ozuna (1995). Porosity types - Fabric selective: IP, Interparticle porosity; IG, Intergranular porosity; IC, Intercrystalline porosity; SH, shelter porosity; MO, moldic porosity; BU, burrowed porosity; FE, fenestral; BP, bedding plane porosity. Not fabric selective: FR, fracture porosity; CH, channel porosity; BR, breccia; VUG, vug porosity; CV, cave porosity.

ATTACHMENT C
Site Geology

E-54 SANITARY SEWER Geologic Assessment

Attachment C – Site Geology

SUMMARY

The E-54 Sanitary Sewer project site is located from Evans Road to the SAWS E-4 project located east of Bulverde Road just north of Loop 1604 in Bexar County, Texas. This assessment was prepared through a compilation of other Geologic Assessments prepared by Pape-Dawson, and conducting field survey where appropriate.

Based on the results of the field survey conducted in accordance with *Instructions for Geologists for Geologic Assessments in the Edwards Aquifer Recharge/Transition Zones (TCEQ-0585 Instructions)*, no naturally occurring sensitive features were identified on site. The overall potential for fluid migration to the Edwards Aquifer for the site is low.

SITE GEOLOGY

As observed through field evidence, the geologic formations which outcrop at the surface within the project limits is the cyclic and marine (Kepcm), the leached and collapsed (Keplc), and the regional dense (Keprd) members of the Person formation, and the grainstone (Kekg) member of the Kainer formation. These formations are described in further detail below:

- The Kepcm is characterized by a mudstone to pack stone miliolid grainstone, and chert. Karst development within the Kepcm is characterized by small sinkholes and caves developed as vertical shafts as well as lateral rooms.
- The Keplc is characterized by interbedded, iron-stained, massive and bioturbated limestone with abundant chert. Karst development within the Keplc is generally characterized by large sinkholes. Caves often develop as large horizontal rooms.
- The Keprd is a dense, thinly-bedded, argillaceous mudstone. Karst development within the Keprd member is uncommon. Vertical fracture enlargement is possible. The Keprd may act as a vertical barrier to most cave development within the thin overlying portion of the leached and collapsed members.
- The Kekg is characterized by a white, cross bedded, miliolid grainstone and mudstone. Karst development within the Kekg is uncommon.

E-54 SANITARY SEWER Geologic Assessment

The predominant trend of faults in the vicinity of the site is approximately N50°E, based on faults identified during the previous mapping of the area.

FEATURE DESCRIPTIONS:

A description of the features observed onsite is provided below:

Features S-1, S-10, S-11, S-12, S-13, and S-14

Features S-1, S-10, S-11, S-12, S-13, and S-14 are a series of existing sewer lines that are partially located beneath pavement. The sewer lines have been trenched through bedrock and backfilled with a mix of fine and coarse fill material that may be more permeable than surrounding undisturbed areas. Therefore, the probability of rapid infiltration is intermediate.

Features S-2, S-3, S-4, S-5, S-6, and S-9

Features S-2, S-3, S-4, S-5, S-6, and S-9 are intraformational faults within the Kep. They were identified in review of aerial photographs and published maps. Lack of evidence of areas of enhanced permeability and the presence of fine-grained soil cover suggests a low probability for rapid infiltration.

REFERENCES

Clark, A.K., Golab, J.A., and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers Within Northern Bexar and Comal Counties, Texas: U.S. Geological Survey Scientific Investigations Map 3366, scale 1:24,000, 20 p. pamphlet.

Nationwide Environmental Title Research, LLC. Historical Aerials, HistoricAerials.com. <https://www.historicaerials.com/viewer>, June 25, 2021.

Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Web Soil Survey. <http://websoilsurvey.sc.egov.usda.gov/>, June 25, 2021.


E-54 SANITARY SEWER Geologic Assessment

Stein, W.G., and Ozuna, G.B., 1995, Geologic framework and hydrogeologic characteristics of the Edwards Aquifer recharge zone, Bexar County, Texas: U.S. Geological Survey Water-Resources Investigations Report 95-4030, 8 p.

Texas Water Development Board, Wells in TWDB Groundwater Database Viewer, <https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer>, June 25, 2021.

U.S. Geological Survey, National Water Information System: Mapper, <https://maps.waterdata.usgs.gov/mapper/index.html>, May 10, 2021. June 25, 2021.

ATTACHMENT D
Site Geologic Map(s)






Date: May 20, 2021 3:30:37 PM User: HStultz
File: P:\175005\175005\Drawings\Site\Site150001.mxd


JOB NO.	11500-51
DATE	May 2021
DESIGNER	HS
CHECKED	HDJ
DRAWN	HS
SHEET	Attachment D

E-54 SANITARY SEWER
BEXAR COUNTY, TEXAS
SITE SOILS MAP

PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028800




LOCATION MAP
NOT-TO-SCALE




LEGEND			
PROJECT LIMITS			
[Red line]	100 YEAR FLOODPLAIN		
[Dashed blue line]	STREAM		
GEOLOGIC FORMATIONS			
[Qal]	ALLUVIUM	[Kgt]	GEORGETOWN
[Kef]	EAGLE FORD	[Kep]	PERSON
[Kbu]	BUDA	[Kek]	KAINER
[Kdr]	DEL RIO	[Kgr]	GLEN ROSE
SYMBOLS AND LINES			
[S-1]	POTENTIAL RECHARGE FEATURE	[Red dashed line]	CONTACT, LOCATED APPROXIMATELY
[Red dashed line]	CONTACT, LOCATED APPROXIMATELY	[Red dashed line]	CONTACT, INFERRED
[U]	FAULT, LOCATED APPROXIMATELY (U, DOWNTHROWN SIDE; U, UPTHROWN SIDE)	[Red dashed line]	FAULT, EXTRAPOLATED
[Red dashed line]	FAULT, EXTRAPOLATED	[Red dashed line]	FAULT, INFERRED
[Red dashed line]	FAULT, INFERRED	[Red dashed line]	STRIKE AND DIP OF BEDDING
[Red dashed line]	STRIKE AND DIP OF BEDDING	[Red dashed line]	STRIKE AND DIP OF JOINTS
[Red dashed line]	STRIKE AND DIP OF JOINTS	[Red dashed line]	STRIKE OF VERTICAL JOINTS
[Red dashed line]	STRIKE OF VERTICAL JOINTS	[Red dashed line]	CAVE
[Red dashed line]	CAVE	[Red dashed line]	SOLUTION CAVITY
[Red dashed line]	SOLUTION CAVITY	[Red dashed line]	SOLUTION ENLARGED FRACTURE
[Red dashed line]	SOLUTION ENLARGED FRACTURE	[Red dashed line]	SWALLOW HOLE
[Red dashed line]	SWALLOW HOLE	[Red dashed line]	SINKHOLE
[Red dashed line]	SINKHOLE	[Red dashed line]	NON-KARST CLOSED DEPRESSION
[Red dashed line]	NON-KARST CLOSED DEPRESSION	[Red dashed line]	ZONE
[Red dashed line]	ZONE	[Red dashed line]	OTHER NATURAL BEDROCK FEATURES
[Red dashed line]	OTHER NATURAL BEDROCK FEATURES	[Red dashed line]	SPRING/SEEP
[Red dashed line]	SPRING/SEEP	[Red dashed line]	MAN-MADE FEATURE IN BEDROCK
[Red dashed line]	MAN-MADE FEATURE IN BEDROCK	[Red dashed line]	WATER WELL
[Red dashed line]	WATER WELL	[Red dashed line]	SANITARY SEWER LINE
[Red dashed line]	SANITARY SEWER LINE		

NOTE: THE GEOSCIENTIST SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR PURPOSES OF GEOLOGIC INFORMATION. ALL OTHER INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SIGNED AND SEALED CIVIL ENGINEERING DRAWINGS.



SHEET 1 OF 3

NO.	REVISION	DATE






PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.376.9000
 TDD: 210.376.9000 FAX: 210.376.9000

E-54 SANITARY SEWER
 BEXAR COUNTY, TEXAS
 SITE GEOLOGIC MAP
 ORGANIZED SEWAGE COLLECTION SYSTEM


JOB NO. 11500-51
 DATE MAY 2021
 DESIGNER HS
 CHECKED HDJ DRAWN HS
 ATTACHMENT D

Date: Jun 07, 2021, 1:10pm User ID: HStultz File: F:\11500\GIS\NEW\GIS\Attachments\GAT150051 - Ver2.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADEQUATELY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



LOCATION MAP
NOT-TO-SCALE




LEGEND

PROJECT LIMITS		100 YEAR FLOODPLAIN	
STREAM		GEOLOGIC FORMATIONS	
Qal	ALLUVIUM	Kgt	GEORGETOWN
Kef	EAGLE FORD	Kep	PERSON
Kbu	BUDA	KeK	KAINER
Kdr	DEL RIO	Kgr	GLEN ROSE
SYMBOLS AND LINES			
S-1	POTENTIAL RECHARGE FEATURE		
- - -	CONTACT, LOCATED APPROXIMATELY		
- - -	CONTACT, INFERRED		
- - -	FAULT, LOCATED APPROXIMATELY (D, DOWNTHROW SIDE; U, UPTHROW SIDE)		
- - -	FAULT, EXTRAPOLATED		
- - -	FAULT, INFERRED		
- - -	STRIKE AND DIP OF BEDDING		
- - -	STRIKE AND DIP OF JOINTS		
- - -	STRIKE OF VERTICAL JOINTS		
○	CAVE		
○	SOLUTION CAVITY		
○	SOLUTION ENLARGED FRACTURE		
○	SWALLOW HOLE		
○	SINKHOLE		
○	NON-KARST CLOSED DEPRESSION		
○	ZONE		
○	OTHER NATURAL BEDROCK FEATURES		
○	SPRING/SEEP		
○	MAN-MADE FEATURE IN BEDROCK		
○	WATER WELL		
- - -	SANITARY SEWER LINE		

NOTE: THE GEOSCIENTIST SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR PURPOSES OF GEOLOGIC INFORMATION. ALL OTHER INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SIGNED AND SEALED CIVIL ENGINEERING DRAWINGS.

SHEET INDEX
NOT-TO-SCALE



SHEET 2 OF 3

NO.	REVISION	DATE



PAPE-DAWSON ENGINEERS
SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TYPE III REGISTERED PROFESSIONAL ENGINEERS | TEXAS REGISTRATION NO. 14680000


E-54 SANITARY SEWER
BEXAR COUNTY, TEXAS
SITE GEOLOGIC MAP
ORGANIZED SEWAGE COLLECTION SYSTEM

JOB NO. 11500-51
DATE MAY 2021
DESIGNER HS
CHECKED HDJ DRAWN HS
ATTACHMENT D


Date: Jun 07, 2021, 11:44am User: D: HSchultz
File: P:\11500\51\ENV\GAI\Attachments\GAI150051 - Ver2.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADEQUATELY ALIGNED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.


Plot: Jun 25, 2021, 10:17am User: ID: HSK/ltf
 File: P:\113\001\ENR\GA Attachments\GA150051 - Ver2.dwg



VIEW E



LOCATION MAP
NOT-TO-SCALE




LEGEND

- PROJECT LIMITS
- 100 YEAR FLOODPLAIN
- STREAM
- GEOLOGIC FORMATIONS
 - Qal ALLUVIUM
 - Kef EAGLE FORD
 - Kbu BUDA
 - Kdr DEL RIO
 - Kgt GEORGETOWN
 - Kep PERSON
 - Kek KAINER
 - Kgr GLEN ROSE
- SYMBOLS AND LINES
 - S-1 POTENTIAL RECHARGE FEATURE
 - CONTACT, LOCATED APPROXIMATELY
 - CONTACT, INFERRED
 - FAULT, LOCATED APPROXIMATELY (D, DOWNTHROW SIDE; U, UPRIFTHROW SIDE)
 - FAULT, EXTRAPOLATED
 - FAULT, INFERRED
 - STRIKE AND DIP OF BEDDING
 - STRIKE AND DIP OF JOINTS
 - STRIKE OF VERTICAL JOINTS
 - CAVE
 - SOLUTION CAVITY
 - SOLUTION ENLARGED FRACTURE
 - SWALLOW HOLE
 - SINKHOLE
 - NON-KARST CLOSED DEPRESSION
 - ZONE
 - OTHER NATURAL BEDROCK FEATURES
 - SPRING/SEEP
 - MAN-MADE FEATURE IN BEDROCK
 - WATER WELL
 - SS SANITARY SEWER LINE


NOTE: THE GEOSCIENTIST SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR PURPOSES OF GEOLOGIC INFORMATION. ALL OTHER INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SIGNED AND SEALED CIVIL ENGINEERING DRAWINGS.

SHEET INDEX
NOT-TO-SCALE



SHEET 3 OF 3

NO.	REVISION	DATE



PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TDD: 210.375.9000

E-54 SANITARY SEWER
 BEXAR COUNTY, TEXAS
 SITE GEOLOGIC MAP
 ORGANIZED SEWAGE COLLECTION SYSTEM

JOB NO. 11500-51
 DATE MAY 2021
 DESIGNER HS
 CHECKED HDJ DRAWN HS
 ATTACHMENT D

**MODIFICATION OF A PREVIOUSLY
APPROVED PLAN (TCEQ-0590)**

Modification of a Previously Approved Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.


Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This request for a **Modification of a Previously Approved Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Jason T. Diamond, P.E.

Date: 01/16/2024

Signature of Customer/Agent:



Project Information

1. Current Regulated Entity Name: SAWS E-54 Temporary Lift Station
Original Regulated Entity Name: SAWS E-54 Sanitary Sewer Project
Regulated Entity Number(s) (RN): 111376935
Edwards Aquifer Protection Program ID Number(s): 13001558
 The applicant has not changed and the Customer Number (CN) is: 600529069
 The applicant or Regulated Entity has changed. A new Core Data Form has been provided.
2. **Attachment A: Original Approval Letter and Approved Modification Letters.** A copy of the original approval letter and copies of any modification approval letters are attached.

3. A modification of a previously approved plan is requested for (check all that apply):
- Physical or operational modification of any water pollution abatement structure(s) including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
 - Change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
 - Development of land previously identified as undeveloped in the original water pollution abatement plan;
 - Physical modification of the approved organized sewage collection system;
 - Physical modification of the approved underground storage tank system;
 - Physical modification of the approved aboveground storage tank system.
4. Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

<i>WPAP Modification</i>	<i>Approved Project</i>	<i>Proposed Modification</i>
<i>Summary</i>		
Acres	<u>N/A</u>	<u>N/A</u>
Type of Development	_____	_____
Number of Residential Lots	_____	_____
Impervious Cover (acres)	_____	_____
Impervious Cover (%)	_____	_____
Permanent BMPs	_____	_____
Other	_____	_____

<i>SCS Modification</i>	<i>Approved Project</i>	<i>Proposed Modification</i>
<i>Summary</i>		
Linear Feet	<u>32,183</u>	<u>32,183</u>
Pipe Diameter	<u>18", 20", 21", 24", 30", 36"</u>	<u>18", 20", 21", 24", 30", 36"</u>
Other	_____	<u>temporary lift station</u>

ATTACHMENT A

Jon Niermann, *Chairman*
Emily Lindley, *Commissioner*
Bobby Janecka, *Commissioner*
Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

July 22, 2022

Ms. Cristina Brantley, PE
San Antonio Water System
2800 US Highway 281
San Antonio, Texas 78212

Re: Edwards Aquifer, Bexar County

NAME OF PROJECT: SAWS E-54 Sanitary Sewer Project; Located approximately 0.3 miles east of Bulverde Rd and Gold Canyon Rd intersection; San Antonio, Texas

TYPE OF PLAN: Request for Modification of an Approved Organized Sewage Collection System (SCS) Plan; 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Regulated Entity No. RN111376935; Additional ID No. 13001558

Dear Ms. Brantley:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the organized sewage collection system plans and specifications for the referenced project submitted to the San Antonio Regional Office on behalf of San Antonio Water System (SAWS) by Pape-Dawson Engineers, Inc. on June 20, 2022. As presented to the TCEQ, the construction documents were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213 and Chapter 217. Therefore, based on the Texas Licensed Professional Engineer's concurrence of compliance, the planning materials for construction of the proposed sewage collection system and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer protection plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. *This approval expires (2) two years from the date of this letter unless, prior to the expiration date, more than 10 percent of construction has commenced, or an extension of time has been requested.*

BACKGROUND

On February 18, 2022, the Texas Commission on Environmental Quality (TCEQ) approved the SAWS E-54 Sanitary Sewer Project Sewage Collection System (EAPP ID No 13001446), which included construction of 32,183 LF of sanitary sewer main, of which 3,631 LF was to be tunneled/bored in casing.

PROJECT DESCRIPTION

This SCS MOD proposes the installation of 120.40 linear feet (LF) of 30-inch FRP SN 72, ASTM D-3262 (ASTM D4161 Joint) gravity sewer main by jack and bore methods in a steel encasement across the limits of the future Gold Canyon roadway from Station 70+61.22 to Station 71+81.62. The 120.40 LF of proposed construction was originally approved by the TCEQ to be

installed by open cut excavation prior to the extension of Gold Canyon. The proposed sewage collection system will provide disposal service for residential and commercial development.

The system will be connected to an existing SAWS wastewater line for conveyance to the Steven M. Clouse Water Recycling Center for treatment and disposal. The project is located within the City of San Antonio and San Antonio ETJ and will conform to all applicable codes, ordinances, and requirements of the City of San Antonio and SAWS.

GEOLOGY

According to the geologic assessment included with the application, the project site is underlain by the cyclic and marine, leached and collapsed, and regional dense members of the Person formation; and the grainstone member of the Kainer formation. The geologic assessment indicates that no sensitive geologic features were identified within 50 feet of the proposed sewer line for this unit by the project geologist. The site assessment conducted on July 19, 2022, revealed the site was generally as described in the application.

SPECIAL CONDITIONS

- I. This modification is subject to all Special and Standard Conditions listed in the WPAP approval letter dated February 18, 2022.

STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

Prior to Commencement of Construction:

4. All contractors conducting regulated activities at the project location shall be provided a copy of this notice of approval. At least one complete copy of the approved SCS plan and this notice of approval shall be maintained at the project location until all regulated activities are completed.
5. Modification to the activities described in the referenced SCS application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.
6. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person. The executive director will use the notification to determine if the approved plan is eligible for an extension.

7. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

8. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213 and Chapter 217. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity, upon which that person or entity shall assume responsibility for all provisions and conditions of this approval.
9. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
10. If any sensitive feature (caves, solution cavities, sink holes, etc.) is discovered during construction, all regulated activities near the feature must be suspended immediately. The applicant or his agent must immediately notify the San Antonio Regional Office of the discovery of the feature. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality. The plan must be sealed, signed, and dated by a Texas Licensed Professional Engineer.
11. The following records shall be maintained by the applicant and made available to the executive director upon request: the dates trenching activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated and completed.
12. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.
13. Intentional discharges of sediment laden stormwater during construction are not allowed. If dewatering of excavated areas becomes necessary, the discharge will be filtered through appropriately selected temporary best management practices. These may include vegetative filter strips, sediment traps, rock berms, silt fence rings, etc.
14. No part of the system shall be used as a holding tank for a pump-and-haul operation.

After Completion of Construction:

15. Certification by a Texas Licensed Professional Engineer of the testing of sewage collection systems required by 30 TAC Chapter 213 and Chapter 217 shall be submitted to the San Antonio Regional Office within 30 days of test completion and prior to the new sewage collection system being put into service. The certification should include the project name as it appeared on the approved application, the program ID number, and two copies of a

Ms. Cristina Brantley, PE

Page 4

July 22, 2022

site plan sheet(s) indicating the wastewater lines and manholes that were tested and are being certified as complying with the appropriate regulations. The engineer must certify in writing that all wastewater lines have passed all required testing to the appropriate regional office within 30 days of test completion and prior to use of the new collection system. Should any test result fail to meet passing test criteria and then subsequently pass testing, the result(s) and an explanation of what repair, adjustment, or other means were taken to facilitate a subsequent passing result shall be provided.

16. Every five years after the initial certification, the sewage collection system shall be retested. Any lines that fail the test must be repaired and retested. Certification that the system continues to meet the requirements of 30 TAC Chapter 213 and Chapter 217 shall be submitted to the San Antonio Regional Office. The certification should include the project name as it appeared on the approved application, the program ID number and two copies of a site plan sheet(s) indicating the wastewater lines and manholes that were tested and are being certified as complying with the appropriate regulations. Should any test result fail to meet passing test criteria, and then subsequently pass testing, the result(s) and an explanation of what repair, adjustment, or other means were taken to facilitate a subsequent passing result shall be provided.
17. If ownership of this organized sewage collection system is legally transferred (e.g., developer to city or Municipal Utility District), the new owner(s) is required to comply with all terms of the approved Edwards Aquifer protection plan. If the new owner intends to commence any new regulated activity on the site, a new Edwards Aquifer protection plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.
18. An Edwards Aquifer protection plan approval or extension will expire, and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Edwards Aquifer protection plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Don Vandertulip, PE, BCEE of the Edwards Aquifer Protection Program of the San Antonio Regional Office at (210) 403-4057.

Sincerely,



Lillian Butler, Section Manager
Edwards Aquifer Protection Program
Texas Commission on Environmental Quality

LIB/dv

cc: Mr. Jason Diamond, PE, Pape-Dawson Engineers, Inc.

ATTACHMENT B

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification & Lift Station Application


Attachment B – Modification Summary

The SAWS E-54 Temporary Lift Station and Sewage Collection System Modification (SCS MOD) is a modification of the previously approved SAWS E-54 Sanitary Sewer Project SCS MOD (EAPP ID No 13001558), approved on July 22, 2022. The approved SAWS E-54 Sanitary Sewer Project has been designed to handle SAWS-provided flows from four existing lift stations north of the project limits (Fox Grove, Fossil Ridge, Cibolo Canyons, and Fischer). The project lies within the Upper Salado Creek watershed over the Edwards Aquifer Recharge Zone. No naturally occurring sensitive features were identified within the SCS envelope in the Geological Assessment.


This SAWS E-54 Temporary Lift Station is intended to temporarily bypass flows from the proposed Brookstone residential subdivision development to the existing SAWS Fox Grove Lift Station until such time that the SAWS E-54 Regional Lift Station (currently under construction) is put into service. When the E-54 Regional Lift Station is put into service, flows from the Brookstone development will be conveyed conventionally through a gravity main to the E-54 Regional Lift Station, and the E-54 Temporary Lift Station pumps and force main will be taken out of service and removed from the site. The E-54 Temporary Lift Station wetwell will consist of a four-foot (4') diameter fiberglass reinforced plastic (FRP) wetwell that has been constructed and hydro-statically tested as part of the SAWS E-54 Sanitary Sewer Project. Two Xylem/Gould submersible pumps will be placed in the manhole to temporarily convey the Brookstone sanitary sewer flow to the Fox Grove lift station via two (2) temporary 3-inch (3") PVC force mains. Each force main will convey the flow from each pump in the wetwell. At peak flow rates, the proposed submersible pumps will operate concurrently and discharge flow through their respective force mains. No permanent modifications to the existing, approved sewer plans are proposed with this application.

Approximately 201 EDUs will flow to the temporary lift station, for an average daily flow of 40,200 gallons (201 EDU x 200 gpd/EDU = 40,200 gpd). The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by SAWS. Potable water will be supplied by SAWS.

ATTACHMENT C



LEGEND



OVERALL QUANTITY TABLE

ITEM NO	ITEM DESCRIPTION	UNIT	QUANTITY
505	RIP RAP 24-INCHES THICK	CY	22
507	FENCE GATE 16' TYPE 1	EA	1
508	REMOVE AND REPLACE EXISTING FENCING	LF	50
540	TEMPORARY EROSION, SEDIMENTATION AND WATER POLLUTION PREVENTION AND CONTROL	LS	1
550	TRENCH EXCAVATION PROTECTION	LF	4,451
850	DOGHOUSE MANHOLE STRUCTURE	EA	1
852	4' DIA. FRP SANITARY SEWER MANHOLE	EA	10
852A	EXTRA DEPTH MANHOLE	VF	140
853	VENTED 4' DIA. FRP SANITARY SEWER MANHOLE	EA	4
848A	24" PVC SDR 26 (OPEN CUT 5'-10')	LF	33
848A	24" PVC SDR 26 (OPEN CUT 10'-15')	LF	340
848A	24" PVC SDR 26 (OPEN CUT 15'-20')	LF	154
848A	24" PVC SDR 26 (OPEN CUT 20'-25')	LF	118
848A	21" PVC SDR 26 (OPEN CUT 5'-10')	LF	677
848A	21" PVC SDR 26 (OPEN CUT 10'-15')	LF	2,196
848A	21" PVC SDR 26 (OPEN CUT 15'-20')	LF	832
848A	21" PVC SDR 26 (OPEN CUT 20'-25')	LF	101
857	TESTING AND ACCEPTANCE OF FRP GRAVITY SEWER (ALL SIZES AND DEPTHS) (SEGMENT B)	LS	1
858	CLASS B - 2,000 PSI CONCRETE ENCASEMENT (SEGMENT B)	CY	812
866	SEWER MAIN TV INSPECTION, POST (ALL SIZES) (SEGMENT B)	LF	4,451
02300-I	TUNNEL EXCAVATIONS OF VISTA RIDGE PIPELINE (JB-4, SEG B)	LF	93
02300-J	TUNNEL EXCAVATIONS OF EVANS ROAD (JB-5, SEG B)	LF	129
02360-H	JACK AND BORE PITS FOR JB-4 (INCLUDES 2 EA)	LS	1
02360-I	JACK AND BORE PITS FOR JB-5 (INCLUDES 2 EA)	LS	1
02420-I	INSTALLATION OF CARRIER PIPE IN JB-4 (21" PVC SDR 26)	LF	93
02420-J	INSTALLATION OF CARRIER PIPE IN JB-5 (21" PVC SDR 26)	LF	129

CONTROL POINTS

POINT #	NORTHING	EASTING	ELEVATION	RAW DESCRIPTION	FULL DESCRIPTION
11	13784497.26	2160813.33	954.14	SIRCTV	SET I.R. REDCAP (TRAV)
12	13784405.79	2161218.55	954.64	SIRCTV	SET I.R. REDCAP (TRAV)
15	13783264.99	2161551.12	946.78	SIRCTV	SET I.R. REDCAP (TRAV)
22	13784019.66	2163542.73	979.15	SIRCTV	SET I.R. REDCAP (TRAV)
23	13783963.48	2163763.62	958.54	SIRCTV	SET I.R. REDCAP (TRAV)

DATE	NO.	REVISION



PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TYPE FIRM REGISTRATION #470 | TYPE FIRM REGISTRATION #1008800

SAWS E-54 SANITARY SEWER PROJECT
 BEXAR COUNTY, TEXAS
 SEGMENT B
 OVERALL SHEET

SAWS JOB NO. 21-4404
 JOB NO. 11500-51
 DATE OCTOBER 2021
 DESIGNER MP
 CHECKED JD DRAWN BS
 SHEET **C2.00B**

Notes: File: 06_2022_3-00.dwg User: ID: cally Date: 11/15/2021 11:50:05 AM Project: C:\Users\cally\OneDrive\Desktop\B\04B1-1150051.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

**LIFT STATION/FORCE MAIN
SYSTEM APPLICATION (TCEQ-
0624)**

Lift Station/Force Main System Application

Texas Commission on Environmental Quality

for Regulated Activities On the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c)(3)(B)and(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: SAWS E-54 Temporary Lift Station

Customer Information

(If different than customer information provided on core data form)

1. The person(s) responsible for providing the engineering certification to the TCEQ pursuant to 30 TAC §213.5(f)(2)(C) during construction and 30 TAC §213.5 (c)(3)(D) upon completion of construction is:

Contact Person: Cristina Brantley P.E.

Entity: San Antonio Water System (SAWS)

Mailing Address: 2800 US Hwy 281

City, State: San Antonio, Texas

Zip: 78212

Telephone: (210) 233-3939

Fax: _____

Email Address: Cristina.Brantley@saws.org

2. The engineer responsible for the design of this lift station and force main:

Contact Person: Kim Keefer, P.E.

Entity: Pape-Dawson Engineers, Inc.

Mailing Address: 2000 NW Loop 410

City, State: San Antonio, Texas

Zip: 78213

Telephone: (210) 375-9000

Fax: (210) 375-9010

Email Address: kkeefer@pape-dawson.com

Texas Licensed Professional Engineer's Serial Number: 117744

Project Information

3. This project is for the construction or replacement of:

Lift Station only.

- Lift Station and Force Main system.
 - Lift Station, Force Main, and Gravity system.
4. The sewage collection system will convey the wastewater to the Steven M. Clouse Water Recycling Center (name) Treatment Plant. The treatment facility is:
- Existing
 - Proposed
5. All components of this lift station/force main system will comply with:
- The City of San Antonio/SAWS standard specifications.
 - Other. Specifications are attached.

Site Plan Requirements

Items 6-14 must be included on the Site Plan.

- 6. The Site Plan must have a minimum scale of 1" = 400'.
Site Plan Scale: 1" = 50'.
- 7. Lift station/force main system layout meets all requirements of 30 TAC Chapter 217.
- 8. Geologic or Manmade Features:
 - No geologic or manmade features were identified in the Geologic Assessment.
 - All geologic or manmade features identified in the Geologic Assessment (caves, solution openings, sinkholes, fractures, joints, porous zones, etc.) which exist at the site of the proposed lift station and along the path(s) or within **50 feet of each side** of a proposed force main line are shown on the Site Plan and are listed in the table below. Designs used to protect the integrity of the sewer line crossing each feature are described and labeled on the attached page. A detailed design drawing for each feature is shown on Plan Sheet NA of NA.
 - No Geologic Assessment is required for this project.

Table 1 - Geologic or Manmade Features

<i>Line</i>	<i>Station to Station</i>	<i>Type of Feature</i>
Force Main	N/A to N/A (Sheet C2.00)	Existing Sewer Line
Lift Station Site	N/A to N/A (Sheet C2.00)	Existing Sewer Line
	to	

9. Existing topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
10. Finished topographic contours are shown and labeled. The contour interval is 1 feet. (Contour interval must not be greater than 5 feet).
- Finished topographic contours will not differ from the existing topographic configuration and are not shown.

11. 100-year floodplain boundaries

- Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date of material) source(s): FEMA FIRM Panel 48029C0145G (September 29, 2010)

12. 5-year floodplain:

- After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above sewer lines.)
- After construction is complete, all sections of the force main located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 2 - 5-Year Floodplain

<i>Line</i>	<i>Sheet</i>	<i>Station to Station</i>
	of	to

13. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):

If applicable, this must agree with Item No. 15 on the Geologic Assessment Form.

- There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)
- The wells are not in use and have been properly plugged.
- The wells are not in use and will be properly plugged.
- The wells are in use and comply with 16 TAC Chapter 76.
- There are no wells or test holes of any kind known to exist on the project site.

14. Legal boundaries of the site are shown.

Plan and Profile Sheets

The construction drawings and technical specifications will not be considered for review unless they are the **final plans and technical specifications** which will be used by the contractor for bidding and construction.

Items 15 – 18 must be included on the Plan and Profile sheets.

15. The equipment installation construction plans must have a minimum scale of 1" = 10'.
Plan sheet scale: 1" = 20 '.
16. Locations, descriptions and elevations of all required equipment and piping for the lift station and force main are shown and labeled.
17. Air Release/Vacuum Valves will be provided at all peaks in elevation of the proposed force main. These locations are listed in the table below and labeled on the appropriate plan and profile sheets.

Table 3 - Air Release/Vacuum Valves

<i>Line</i>	<i>Station</i>	<i>Sheet</i>
		of

18. The **final plans and technical specifications** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
19. **Attachment A - Engineering Design Report.** An engineering design report with the following required items is attached:
 - The report is dated, signed, and sealed by a Texas Licensed Professional Engineer.
 - Calculations for sizing system.
 - Pump head calculations, including, but not limited to, system head and pump capacity curves, head loss calculations, and minimum and maximum static head C values for normal and peak operational conditions.
 - 100-year and 25-year flood considerations.
 - Total lift station pumping capacity with the largest pump out of service.
 - Type of pumps, including standby units.
 - Type of pump controllers, including standby air supply for bubbler controllers, as applicable.

- Pump cycle time.
- Type of wet well ventilation; include number of air changes for mechanical ventilation.
- Minimum and maximum flow velocities for the force main.
- Lift station security.
- Lift station emergency provisions and reliability.

Administrative Information

- 20. Upon completion of the wet well excavation, a geologist must certify that the excavation was inspected for the presence of sensitive features and submit the signed, sealed, and dated certification to the appropriate regional office.
- 21. The TCEQ Lift Stations and Force Mains General Construction Notes (TCEQ-0591) are included on the General Notes Sheet of the Final Construction Plans for this lift station and/or force main system.
- 22. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 23. Any modification of this lift station/force main system application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Lift Station/Force Main System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c)(3)(C) and 30 TAC Chapter 217, and prepared by:

Print Name of Licensed Professional Engineer: Kim Keefer, P.E.

Place engineer's seal here:



Date: 1/15/2024

Signature of Licensed Professional Engineer:



ATTACHMENT A

E-54 TEMPORARY LIFT STATION

Engineering Design Report



December 2023



E-54 TEMPORARY LIFT STATION

Engineering Design Report

TABLE OF CONTENTS

SEWER SYSTEM INFORMATION	1
PUMP STATION AND FORCE MAIN DESIGN CALCULATIONS	1
Net Positive Suction Head (NPSH)	6
Force Main Velocity	6
Surge Pressures	7
Buoyancy Calculations	8

TABLES

Table 1. K Value Calculations (One Pump in Service)	4
Table 2. TDH Equation Variables and Values (One Pump in Service)	5
Table 3. Buoyancy Force Calculation	9
Table 4. Lift Station Weight Calculation	9

EXHIBITS

- EXHIBIT 1 – Location Map
- EXHIBIT 2 – Pump Curve and Supporting Information

E-54 TEMPORARY LIFT STATION

Engineering Design Report

SEWER SYSTEM INFORMATION

Introduction

The E-54 Temporary Lift Station is intended to temporarily bypass flows from the proposed Brookstone residential subdivision development (201 EDU, 37 acres) to the existing San Antonio Water System (SAWS) Fox Grove Lift Station until such time that the SAWS E-54 Regional Lift Station (currently under construction) is put into service. When the E-54 Regional Lift Station is put into service, flows from the Brookstone development will be conveyed conventionally through a gravity main to the E-54 Regional Lift Station, and the E-54 Temporary Lift Station pumps and force main will be taken out of service and removed from the site. The E-54 Temporary Lift Station will be located approximately 135 feet south of the proposed E-54 Regional Lift Station wetwell, and approximately 81 feet north, north east of the existing Fox Grove Lift Station in San Antonio, Texas (Exhibit 1). The E-54 Temporary Lift Station wetwell will consist of a four (4) foot diameter fiberglass reinforced plastic (FRP) wetwell that has been constructed and hydro-statically tested as part of the SAWS E-54 Sanitary Sewer Project. Two Xylem/Gould submersible pumps will be placed in the manhole to temporarily convey the Brookstone sanitary sewer flow to the Fox Grove lift station via two temporary 3" PVC force mains. Each force main will convey the flow from each pump in the wetwell. At peak flow rates, the proposed submersible pumps will operate concurrently and discharge flow through their respective force mains.

CPS Energy will be providing power to the lift station. A portable generator will be available for use for emergency backup power by the E-54 Regional Lift Station contractor in the event of a CPS Energy power outage. The portable generator will be located within the E-54 Regional Lift Station construction trailer, which is located approximately 150 feet from the E-54 Temporary Lift Station wetwell. The temporary lift station will also be equipped with an auto-dialer for remote lift station monitoring and to alert the contractor of loss of power at the temporary lift station.

PUMP STATION AND FORCE MAIN DESIGN CALCULATIONS

Average Dry Weather Flow

A total of 201 EDUs will flow to the temporary lift station. For each EDU, the average daily flow is 200 gallons per day (gpd). This yields an average daily flow into the lift station of 40,200 gallons (201 EDUs x

E-54 TEMPORARY LIFT STATION Engineering Design Report

200 gpd). Dividing by 1,440 minutes/day gives a flow of 28 gallons per minute (gpm).

Peak Dry Weather Flow

To determine peak flows for the collection system a peaking factor of 2.5 (SAWS Utility Service Regulations 11.3.1) is applied to the average daily flow for each phase. This yields a peak flow of 100,500 gpd (201 EDU x 200 gpd x 2.5). Dividing by 1,440 minutes/day gives a design peak dry weather flow of approximately 70 gpm.

Peak Wet Weather Flow

To determine peak wet weather flow, a component must be added to the peak dry weather flow to account for inflow and infiltration to the collection system. This inflow and infiltration is computed based on the SAWS value of 600 gpd per acre of land in the service area. The service area for the proposed lift station is approximately 37 acres. This yields an inflow and infiltration allowance of 22,200 gpd (37 acres x 600 gpd/acre). Adding this to the peak dry weather flow of 100,500 gpd gives a daily peak wet weather flow of 122,700 gpd. Dividing by 1,440 minutes/day gives a flow of approximately 85 gpm.

Minimum Dry Weather Flow

The minimum dry weather flow is used to determine the maximum detention time in the wet well. The formula for computing the minimum dry weather flow (as given in the SAWS lift station Design and Construction Guidelines, dated January 2012) is:

$$\text{MDWF} = 0.2 \times (0.0144 \times \text{ADF})^{.198} \times \text{ADF},$$

where:

MDWF = minimum dry weather flow, gpm
ADF = average dry weather flow, gpm

Using the above equation and an average dry weather flow of 28 gpm gives a value of approximately 5 gpm for the minimum dry weather flow.

E-54 TEMPORARY LIFT STATION

Engineering Design Report

Minimum Pump Requirements

It is anticipated that as residential connections are made, sanitary sewer flows will increase to the eventual maximum of 201 connections. Initially, flows will be lower as construction and home sales begin in the Brookstone development. For the proposed temporary lift station, two submersible pumps will be used to convey the flow during the temporary pumping period. Each pump will have a pumping capacity of approximately 54 gpm. When operating concurrently, the two pumps will have a capacity of 108 gpm. Each pump will discharge through a three-inch PVC force main.

The total dynamic head (TDH) can be described by the following equation:

$$TDH = H_s + L_f + L_M$$

where:

H_s	=	static head
L_f	=	loss due to friction in the force main pipe
L_M	=	minor loss in the force main pipe

The static head can be described by the following equation:

$$H_s = E_H - E_L$$

where:

E_H	=	maximum elevation of the proposed force main, feet
E_{L1}	=	low water elevation of the wet well, feet

Per SAWS Lift Station Design & Construction Guidelines dated January 2012, a static head must be computed using the lowest water elevation in the wet well which is the "All Pumps Off" Elevation (E_{L1}).

Frictional and minor losses are shown in the following paragraphs. The computations for these are for 3-inch force main under the condition where the pumps are operating at a combined discharge rate of 54 gpm.

E-54 TEMPORARY LIFT STATION Engineering Design Report

The frictional losses (L_f) in the force main pipe can be described by the following equation:

$$L_f = L \times \left(\frac{2.313 \times Q}{C \times D^{2.63}} \right)^{1.85}$$

where:

- L = length of force main, feet
- Q = flow, cubic feet per second (cfs)
- C = Hazen-Williams factor of the pipe
- D = diameter of the force main, feet

Per SAWS lift station Design & Construction Guidelines dated January 2012, the losses due to friction must be computed using a C value of 140.

The minor losses in the force main pipe can be described by the following equation:

$$L_M = \frac{Kv^2}{2g}$$

where:

- K = headloss coefficient for the minor losses
- v = velocity in the force main $\left(\frac{Q}{\pi(D/2)^2} \right)$, feet per second
- g = gravitational constant (32.2 ft²/sec)

See Table 1 below for the K value calculations.

Table 1. K Value Calculations (One Pump in Service)

Minor Loss Item	K-Value	Qty.	Total
Discharge Into Manhole	1.00	1	1.00
90° Bend	0.54	3	1.62
Tee/Wye Bend	1.08	3	1.08

E-54 TEMPORARY LIFT STATION Engineering Design Report

Minor Loss Item	K-Value	Qty.	Total
Gate Valve	0.14	1	0.14
Check Valve	1.80	1	1.80
Reducers	0.50	1	0.50
		K _(total)	6.14

Thus, the equation for determining TDH can be written as follows:

$$TDH = E_H - E_L + L \times \left(\frac{2.313 \times Q}{C \times D^{2.63}} \right)^{1.85} + \frac{K}{2g} \times \left(\frac{Q}{\pi(D/2)^2} \right)^2$$

Using the C value (C=140), the TDH value will be determined. Table 2 contains the remaining variables from the TDH equation and the resulting TDH value.

Table 2. TDH Equation Variables and Values (One Pump in Service)

Variable	Value
E _n (ft) – Elevation Head	939.75
E _{L1} (ft) – All Pumps Off Elevation	918.00
E _{L2} (ft) – First Pump On Elevation	918.50
L (ft) – Force Main Length	85
Q (cfs) – Flow (each pump)	0.12
C	140
D (ft) – Force Main Inner Diameter	0.25
K	6.14
TDH (ft)	23.1

The flow (Q) to be used in these equations is determined using pump curves selected for the conditions in this lift station and pump information provided by the pump manufacturer. In addition, the force main alignment and bends in the proposed 3-inch force main between the proposed temporary lift station location, and the proposed force main discharge location were used. A Q value of 54 gpm (0.12 cfs) for

E-54 TEMPORARY LIFT STATION

Engineering Design Report

each pump operating independently was determined. When both pumps are operating and discharging flow concurrently through their respective force mains, the total discharge from the E-54 Temporary Lift Station will be approximately 108 gpm.

The design point for each of the E-54 temporary lift station submersible pumps will have a flow of 54 gallons/minute and a total dynamic head of 23.1 feet. As noted earlier, the design intent of the E-54 Temporary Lift Station is for the pumps to operate concurrently during peak wet weather flow periods and to discharge flow through their respective force mains. The flow value is anticipated to result in a flow velocity of approximately 2.45 feet per second in each of the two 3-inch Schedule 80 PVC force mains that will be constructed.

Exhibit 2 contains pump curves and supporting information for a Xylem/Gould Pump, model VTX05. Exhibit 2 also contains graphs of the system curves and the proposed pump curves condition. The pump curve is based on the information supplied by Xylem/Gould for the VTX0511 pump with a 0.5-horsepower motor. The intersection of these curves indicates the operating point for each pump is: 54 gpm at 24 feet of TDH, and a total capacity of 108 gpm when both pumps are operating concurrently.

Net Positive Suction Head (NPSH)

NPSH calculations are not critical for submersible pumps. Since the E-54 temporary lift station will use two submersible pumps, NPSH calculations are not required.

Force Main Velocity

The proposed force main for the E-54 lift station is a 3-inch Schedule 80 PVC force main. The velocity (v) in the PVC force main can be described by the following equation:

$$v = \frac{Q}{A}$$

where:

- | | | |
|---|---|---|
| Q | = | flow in the force main, cfs |
| A | = | area of the force main $[\pi(D/2)^2]$, square feet |

E-54 TEMPORARY LIFT STATION Engineering Design Report

For the proposed Schedule 80 PVC force mains, the inner diameter is 3.0 inches, and the cross-section area is approximately 0.05 square feet. Converting the design flow in each force main of 54 gpm to cfs gives a flow of 0.12 cfs [54 gpm / (7.480519 gallons/cubic foot x 60 seconds / minute)]. This yields a velocity in the force main of 2.45 feet per second.

Surge Pressures

Surge pressures in a force main system are the result of a sudden change in liquid velocity. This can be caused by the pump suddenly starting or stopping or a valve in the system being quickly closed. As the fluid suddenly starts or stops, a shock wave is created in the force main. The velocity of that wave can be described by the following equation:

Equation 1

$$a = \frac{4660}{\sqrt{1 + \frac{kd}{Et}}}$$

where:

- a = wave velocity, feet per second
- k = fluid bulk modulus (300,000 psi for water), pounds per square inch
- d = pipe ID, inches
- E = modulus of elasticity of the pipe (360,000 psi for Schedule 80 PVC pipe), pounds per square inch
- t = wall thickness, inches

The maximum pressure surge may be calculated using Equation 2 below:

Equation 2

$$P = \frac{aV}{2.31g}$$

where:

- V = maximum velocity change, feet per second
- g = gravitational constant (32.2 ft²/sec)
- P = pressure surge, pounds per square inch

E-54 TEMPORARY LIFT STATION Engineering Design Report

Using a pipe diameter (d) of 3.0 inches and wall thickness (t) of 0.3 inches and solving for wave velocity (a) yields:

$$a = \frac{4660}{\sqrt{1 + \frac{(300,000 \text{ psi})(3.0 \text{ in})}{(360,000 \text{ psi})(0.3 \text{ in})}}} = \pm 1,525.34 \text{ ft/sec}$$

Inserting this value into Equation 2 along with a maximum velocity change (V) of 2.45 ft/s (assuming instantaneous stoppage of flow) yields:

$$P = \frac{(1,525.34 \text{ ft/sec})(2.45 \text{ ft/sec})}{(2.31)(32.2) \text{ ft/sec}} = 61.52 \text{ psi}$$

Based on the normal operating pressure of approximately 10.02 psi (total operating head of 23.1 ft x 0.4329 psi/ft), the system may be subjected to a maximum pressure of approximately 71.54 psi (10.02 psi normal pressure + 61.52 psi surge pressure). The force main is rated at 370 psi and therefore will be capable of completely containing the surge pressures within the system.

Buoyancy Calculations

The SAWS lift station Guidelines (Rule J.2.C.9) require that a buoyancy check be completed for all wet wells. It must be shown that the combined weight of the wet well, pumps and concrete slabs is greater than the maximum buoyancy force that the system can encounter. The force of buoyancy (F_B) can be described by the following equation:

$$F_B = W_G \pi \left(\frac{D}{2} \right)^2 d$$

where:

- W_G = specific weight of water (approximately 62.4 lbs/ft³)
- D = diameter of the wet well, feet
- d = empty depth of the wet well, feet.

E-54 TEMPORARY LIFT STATION Engineering Design Report

See Table 3 below for the calculation of the buoyancy force that the lift station could be subject to.

Table 3. Buoyancy Force Calculation

Item (units)	Value
Specific Weight of Water (lb/ft ³)	62.4
All Pumps Off Elevation (ft)	918.00
Top of Temporary Wet Well Elevation (ft)	938.90
Temporary Wet well Diameter (ft)	4.0
Buoyancy Force (lb)	15,761

The lift station is comprised of several components whose weight will counteract the buoyancy force calculated in Table 3 above. These components are the weight of the concrete slabs that constitute the top and bottom of the temporary wet well, the weight of the temporary fiberglass wet well, the weight of the stored sewage, the weight of concrete above the foundation of the temporary wet well, etc. See Table 4 for calculations of these weights and the total weight of the lift station.

Table 4. Lift Station Weight Calculation

Item (units)	Value
Bottom Slab Length and Width (ft)	5
Bottom Slab Thickness (in)	12
Specific Weight of Concrete (lb/ft ³)	144
Wet Well Depth (ft)	20
Temporary Wet well Unit Weight (lb/ft of depth)	35
All Pumps Off Elevation (ft)	918.00
Temporary Wet well Invert Elevation (ft)	917.40
Temporary Wet well Diameter (ft)	4
Volume of Concrete/Flowable Fill above Bottom Slab (ft ³)	506
Specific Weight of Concrete (lb/ft ³)	144
Weight of Temporary Wet Well (lb)	756

E-54 TEMPORARY LIFT STATION

Engineering Design Report

Item (units)	Value
Total Weight of Concrete Slabs (lb)	5,184
Weight of Concrete/Flowable Fill (lb)	72,888
Total Lift Station Weight (lb)	78,828


The buoyancy force was calculated in Table 3 to be approximately 15,761 pounds. The total lift station weight was calculated in Table 4 to be approximately 78,828 pounds. It appears that the lift station will not float if it is submerged.

EXHIBITS

EXHIBIT 1
Location Map

AERIAL IMAGERY PROVIDED BY GOOGLE © UNLESS OTHERWISE NOTED. Imagery ©2021, CARPOG, Digital Globe, Texas Orthometry Program, USDA Farm Service Agency.

Date: Oct 25, 2021 9:40:40 AM User: CDilly
File: P:\1150051\Design\GIS\MXD\S211005 Regional Lift Station Location Map.mxd



JOB NO.	11500-51
DATE	Oct 2021
DESIGNER	RM
CHECKED	MP
DRAWN	CD
SHEET	1.0

E-54 TEMPORARY LIFT STATION
SAN ANTONIO, TX
LOCATION MAP

PAPE-DAWSON ENGINEERS

SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #10028800

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

EXHIBIT 2
Pump Curve and Supporting
Information



VTX Series

SUBMERSIBLE SEWAGE PUMP

FEATURES

Impeller: Cast iron, multivane, vortex style

Casing: Cast iron volute for maximum efficiency. Designed for easy installation on A10-20 slide rail or base elbow rail systems.

Mechanical Seal: SILICON CARBIDE VS. SILICON CARBIDE sealing faces for superior abrasive resistance, stainless steel metal parts, BUNA-N elastomers.

Shaft: Corrosion-resistant, 300 series stainless steel. Threaded design. Locknut on all models to guard against component damage on accidental reverse rotation.

Fasteners: 300 series stainless steel

Capable of running dry without damage to components.

Designed for continuous operation when fully submerged.

EXTENDED WARRANTY AVAILABLE FOR RESIDENTIAL APPLICATIONS.

APPLICATIONS

Specifically designed for the following uses:

- Homes
- Sewage systems
- Dewatering/Effluent
- Water transfer
- Light industrial
- Commercial applications

Anywhere waste or drainage must be disposed of quickly, quietly and efficiently.

SPECIFICATIONS

Pump

- Solids handling capabilities: 2" maximum
- Capacities: up to 208 GPM
- Total heads: up to 66 feet TDH
- Discharge size: 2" NPT threaded as standard.
- Temperature: 104°F (40°C) continuous
140°F (60°C) intermittent.

MOTORS

- Fully submerged in high grade turbine oil for lubrication and efficient heat transfer. All ratings are within the working limits of the motor.

Class B insulation on ½, ¾, 1, 1½, 2 HP models.

Single phase (60 Hz):

- PSC motors for improved reliability with no starting switches and low start & running current.
- Built-in overload with automatic reset.
- SJTOW severe duty oil and water resistant power cords, 20' length.
- ½ - 2 HP models have NEMA three prong grounding plugs.


AGENCY LISTINGS



Tested to UL 778 and CSA 22.2 108 Standards
By Canadian Standards Association
File #LR38549



MOTOR AND MODEL INFORMATION

Order Number	HP	Phase	Volts	RPM	Impeller Diameter (in.)	Maximum Amps	Locked Rotor Amps	KVA Code	Full Load Motor Efficiency %	Resistance Main (White - black)	Resistance Phase (white-brown)
VTX0511	0.50	1	115	3500	3.13	12.5	62.6	J	71	0.45 - 0.50	4.2 - 4.6
VTX0512	230		7.7			35.7	K	71	1.6 - 1.8		
VTX0712	0.75		230		8.5	3.50	45.2	B	75	1.2 - 1.3	3.2 - 4.6
VTX1012	1.00		230		9.5	3.75		B	78		
VTX1512	1.50		230		13.0	4.06		B	83		
VTX2012	2.00		230		16.0	4.31		B	82		



DIMENSIONS

(All dimensions are in inches.
Do not use for construction purposes.)



**TEMPORARY STORMWATER
SECTION (TCEQ-0602)**

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Jason T. Diamond, P.E.

Date: 01/16/2024

Signature of Customer/Agent:



Regulated Entity Name: SAWS E-54 Temporary Lift Station

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

- Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
 - Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
 - Fuels and hazardous substances will not be stored on the site.
2. **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
 3. Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
 4. **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
6. Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Elm Creek

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
 - A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
 - A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
 - A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
 - There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- N/A
12. **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment A – Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. https://www.tceq.texas.gov/response/spills/spill_rq.html
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

ATTACHMENT B

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment B – Potential Sources of Contamination

Other potential sources of contamination during construction include:

- | | | |
|----------------------|---|--|
| Potential Source | ● | Asphalt products used on this project. |
| Preventative Measure | ■ | After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain. |
| Potential Source | ● | Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping. |
| Preventative Measure | ■ | Vehicle maintenance when possible will be performed within the construction staging area. |
| | ■ | Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately. |
| Potential Source | ● | Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site. |
| Preventative Measure | ■ | Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures. |
| | ■ | Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures. |
| | ■ | Hazardous materials and wastes shall be stored in covered containers and protected from vandalism. |
| | ■ | A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible. |
| Potential Source | ● | Miscellaneous trash and litter from construction workers and material wrappings. |
| Preventive Measure | ■ | Trash containers will be placed throughout the site to encourage proper trash disposal. |
| Potential Source | ● | Construction debris. |
| Preventive Measure | ■ | Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring |

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Potential Source
Preventative Measure

- immediate attention will be addressed on a case by case basis.
- Spills/Overflow of waste from portable toilets
- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

ATTACHMENT C

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment C – Sequence of Major Activities

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include installation of TBMPs as illustrated on Exhibits, clearing and grubbing of vegetation where applicable. This will disturb approximately 0.51 acres. The second is construction activities in previously cleared areas, which will include temporary bypass pumping and site clean up of excess material. This will disturb approximately 0.51 acres.

ATTACHMENT D

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment D – Temporary Best Management Practices and Measures

- a. A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

Due to site topography, upgradient stormwater will cross the project limits from along adjacent portions of the site. All TBMPs provided are adequate for the drainage areas served.

- b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

- c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

- d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.

ATTACHMENT F

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment F – Structural Practices

The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 1 and illustrated in Exhibit 2.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 1, and illustrated on Exhibit 2.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

- Installation of concrete truck washout pit(s), as required and located on Exhibit 1 and illustrated on Exhibit 2.

ATTACHMENT G

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment G – Drainage Area Map

No more than ten (10) acres will be disturbed for this proposed construction. All TBMPs utilized are adequate for the drainage areas served.

ATTACHMENT I

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

INSPECTIONS

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Pollution Prevention Measure	Inspected in Compliance	Corrective Action Required	
		Description (use additional sheet if necessary)	Date Completed
Best Management Practices			
Natural vegetation buffer strips			
Temporary vegetation			
Permanent vegetation			
Sediment control basin			
Silt fences			
Rock berms			
Gravel filter bags			
Drain inlet protection			
Other structural controls			
Vehicle exits (off-site tracking)			
Material storage areas (leakage)			
Equipment areas (leaks, spills)			
Concrete washout pit (leaks, failure)			
General site cleanliness			
Trash receptacles			
Evidence of Erosion			
Site preparation			
Roadway or parking lot construction			
Utility construction			
Drainage construction			
Building construction			
Major Observations			
Sediment discharges from site			
BMPs requiring maintenance			
BMPs requiring modification			
Additional BMPs required			

_____ A brief statement describing the qualifications of the inspector is included in this SWP3.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

"I further certify I am an authorized signatory in accordance with the provisions of 30 TAC §305.128."

Inspector's Name

Inspector's Signature

Date

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

PROJECT MILESTONE DATES

Date when major site grading activities begin:

<u>Construction Activity</u>	<u>Date</u>
Installation of BMPs	
_____	_____
_____	_____
_____	_____
_____	_____

Dates when construction activities temporarily or permanently cease on all or a portion of the project:

<u>Construction Activity</u>	<u>Date</u>
_____	_____
_____	_____
_____	_____
_____	_____

Dates when stabilization measures are initiated:

<u>Stabilization Activity</u>	<u>Date</u>
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
Removal of BMPs	
_____	_____

ATTACHMENT J

SAWS E-54 TEMPORARY LIFT STATION

Sewage Collection System Modification and Lift Station Application

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.

**AGENT AUTHORIZATION FORM
(TCEQ-0599)**

Agent Authorization Form
For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I _____ Cristina Brantley, P.E. _____
Print Name

_____ Director of Engineering _____
Title - Owner/President/Other

of _____ San Antonio Water System _____
Corporation/Partnership/Entity Name

have authorized _____ Pape-Dawson Engineers, Inc. _____
Print Name of Agent/Engineer

of _____ Pape-Dawson Engineers, Inc. _____
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application (E-54 Sanitary Sewer Project, SAWS Job No. 21-4404) to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Cristina Bantley
Applicant's Signature

6/17/22
Date

THE STATE OF Texas §
County of Brewer §


BEFORE ME, the undersigned authority, on this day personally appeared Cristina Bantley known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 17 day of June 2022

Kathy Bernal
NOTARY PUBLIC

Kathy Bernal
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 9.19.2023



**APPLICATION FEE FORM
(TCEQ-0574)**

Application Fee Form

Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: SAWS E-54 Temporary Lift Station

Regulated Entity Location: Approx. 0.3 mi. east of intersection of Bulverde Rd & Gold Canyon Rd

Name of Customer: SAWS

Contact Person: Cristina Brantley, P.E.

Phone: (210) 233-3939

Customer Reference Number (if issued): CN 600529069

Regulated Entity Reference Number (if issued): RN 111376935

Austin Regional Office (3373)

Hays

Travis

Williamson

San Antonio Regional Office (3362)

Bexar

Medina

Uvalde

Comal

Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

Austin Regional Office

San Antonio Regional Office

Mailed to: TCEQ - Cashier

Overnight Delivery to: TCEQ - Cashier

Revenues Section

12100 Park 35 Circle

Mail Code 214

Building A, 3rd Floor

P.O. Box 13088

Austin, TX 78753

Austin, TX 78711-3088

(512)239-0357

Site Location (Check All That Apply):

Recharge Zone

Contributing Zone

Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	0.51 Acres	\$ 650
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Jason T. Diamond

Date: 01/16/2024

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

<i>Project</i>	<i>Project Area in Acres</i>	<i>Fee</i>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

<i>Project</i>	<i>Cost per Linear Foot</i>	<i>Minimum Fee- Maximum Fee</i>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

<i>Project</i>	<i>Cost per Tank or Piping System</i>	<i>Minimum Fee- Maximum Fee</i>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

<i>Project</i>	<i>Fee</i>
Exception Request	\$500

Extension of Time Requests

<i>Project</i>	<i>Fee</i>
Extension of Time Request	\$150

**CORE DATA FORM
(TCEQ-10400)**



TCEQ Use Only

TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 600529069		RN 111376935

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)	
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)		<input type="checkbox"/> Change in Regulated Entity Ownership	
The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).			
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)		If new Customer, enter previous Customer below:	
San Antonio Water System			
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number (if applicable)
11. Type of Customer:	<input type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other	<input type="checkbox"/> Sole Proprietorship	<input type="checkbox"/> Other:	
12. Number of Employees		13. Independently Owned and Operated?	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following			
<input type="checkbox"/> Owner		<input type="checkbox"/> Operator	
<input type="checkbox"/> Occupational Licensee		<input type="checkbox"/> Responsible Party	
		<input type="checkbox"/> Owner & Operator	
		<input type="checkbox"/> Voluntary Cleanup Applicant	
		<input type="checkbox"/> Other:	
15. Mailing Address:			
	City	State	ZIP
16. Country Mailing Information (if outside USA)		17. E-Mail Address (if applicable)	
18. Telephone Number	19. Extension or Code	20. Fax Number (if applicable)	
() -		() -	

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)
<input type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input checked="" type="checkbox"/> Update to Regulated Entity Information
The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)
SAWS E-54 Temporary Lift Station

23. Street Address of the Regulated Entity: <i>(No PO Boxes)</i>							
	City		State		ZIP		ZIP + 4
24. County	Bexar						

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:	Approx. 0.3 mi. east of intersection of Bulverde Rd & Gold Canyon Rd						
26. Nearest City	San Antonio			State	TX	Nearest ZIP Code	78259
27. Latitude (N) In Decimal:	29.617572		28. Longitude (W) In Decimal:	-98.417546			
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds		
29	37	03.3	-98	25	03.2		
29. Primary SIC Code (4 digits)	1623	30. Secondary SIC Code (4 digits)		31. Primary NAICS Code (5 or 6 digits)	237110	32. Secondary NAICS Code (5 or 6 digits)	
33. What is the Primary Business of this entity? <i>(Do not repeat the SIC or NAICS description.)</i>							
Temporary Bypass Pumping							
34. Mailing Address:							
	City		State		ZIP		ZIP + 4
35. E-Mail Address:	cristina.brantley@saws.org						
36. Telephone Number		37. Extension or Code		38. Fax Number (if applicable)			
() -				() -			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input checked="" type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information


40. Name:	Jean Autrey, P.E., CESSWI	41. Title:	Project Manager
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
(210) 375-9000		(210) 375-9010	jautrey@pape-dawson.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.


Company:	Pape-Dawson Engineers	Job Title:	Vice President
Name (In Print):	Jason T. Diamond, P.E.	Phone:	(210) 375- 9000
Signature:		Date:	01/16/2024

**FINAL PLAN AND PROFILE
SHEETS**



E-54 TEMPORARY LIFT STATION

SAWS JOB NO. 22-2502
SOLICITATION NO. CO-00652



D.R. HORTON
211 NORTH LOOP 1604, SUITE 130
SAN ANTONIO, TEXAS 78232

DECEMBER 2023



SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TBPE FIRM REGISTRATION #470 | TBPLS FIRM REGISTRATION #10028800




SHEET C0.00

Date: Dec 14, 2023, 2:17pm, User: k_eefer@pds, File: P:\15100\151\Design\Civil\Sewer\151\Station\Temp_Lift_Station\CS-1150051-TLS.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

PD JOB NO. 11500-51 SAWS JOB NO. 22-2502 E-54 TEMPORARY LIFT STATION



PUMP INFORMATION TABLE	
SERVICE	TEMPORARY WASTEWATER LIFT STATION
TYPE	SUBMERSIBLE PUMPS
FLOW	54 gpm (EACH), 108 gpm (TOTAL)
TDH	23.1 FEET
MOTOR RATED POWER	0.5 HP
VOLTAGE	115V
MOTOR SPEED	3,500 RPM
MANUFACTURER	XYLEM/GOULDS VTX0511 (2)

xylem
Let's Solve Water



TECHNICAL BROCHURE
BVTXSERIES R2


VTX Series

SUBMERSIBLE SEWAGE PUMP


GOULDS
WATER TECHNOLOGY
a xylem brand

Goolds Water Technology

Wastewater



DIMENSIONS
(All dimensions are in inches. Do not use for construction purposes.)



Wastewater

Goolds Water Technology

FEATURES

- Impeller: Cast iron, multivane, vortex style
- Casing: Cast iron volute for maximum efficiency. Designed for easy installation on A10-20 slide rail or base elbow rail systems.
- Mechanical Seal: SILICON CARBIDE VS. SILICON CARBIDE sealing faces for superior abrasive resistance, stainless steel metal parts, BUNA-N elastomers.

Shaft: Corrosion-resistant, 300 series stainless steel. Threaded design. Locknut on all models to guard against component damage on accidental reverse rotation.

Fasteners: 300 series stainless steel
Capable of running dry without damage to components.
Designed for continuous operation when fully submerged.

EXTENDED WARRANTY AVAILABLE FOR RESIDENTIAL APPLICATIONS.

APPLICATIONS

- Specifically designed for the following uses:
 - Homes
 - Water transfer
 - Sewage systems
 - Light industrial
 - Dewatering/Effluent
 - Commercial applications
- Anywhere waste or drainage must be disposed of quickly, quietly and efficiently.

SPECIFICATIONS

- Pump**
- Solids handling capabilities: 2" maximum
 - Capacities: up to 208 GPM
 - Total heads: up to 66 feet TDH
 - Discharge size: 2" NPT threaded as standard.
 - Temperature: 104°F (40°C) continuous, 140°F (60°C) intermittent.

MOTORS

- Fully submerged in high grade turbine oil for lubrication and efficient heat transfer. All ratings are within the working limits of the motor.
- Class B insulation on ½, ¾, 1, 1½, 2 HP models.
- Single phase (60 Hz):**
 - PSC motors for improved reliability with no starting switches and low start & running current.
 - Built-in overload with automatic reset.
 - SJTOW severe duty oil and water resistant power cords, 20' length.
 - ½ - 2 HP models have NEMA three prong grounding plugs.

AGENCY LISTINGS

Tested to UL 778 and CSA 22.2 108 Standards
By Canadian Standards Association
us File #LR38549

MOTOR AND MODEL INFORMATION

Order Number	HP	Phase	Volts	RPM	Impeller Diameter (in.)	Maximum Amps	Locked Rotor Amps	KVA Code	Full Load Motor Efficiency %	Resistance Main (White-black)	Resistance Phase (White-brown)
VTX0511	0.50	1	115	3500	3.13	12.5	62.6	J	71	0.45 - 0.50	4.2 - 4.6
VTX0512	0.75	1	230	3500	3.13	7.7	35.7	K	71	1.6 - 1.8	3.7 - 4.0
VTX0712	1.00	1	230	3500	3.50	8.5	B	75	B	1.2 - 1.3	3.2 - 4.6
VTX1512	1.50	1	230	3500	3.75	9.5	B	78	B	1.2 - 1.3	3.2 - 4.6
VTX2012	2.00	1	230	3500	4.06	13.0	B	83	B	1.2 - 1.3	3.2 - 4.6

PAGE 2

STANDARD PANEL OPTIONS

Pump Order Number	K-Series		Boulay Series	
	Simplex	Duplex	Simplex	Duplex
VTX0511	KS19020WF	KD19020WF	S10020	D10020
VTX0512	KS19020WF	KD19020WF	S10020	D10020
VTX0712	KS19020WF	KD19020WF	S10020	D10020
VTX1012	KS19020WF	KD19020WF	S10020	D10020
VTX1512	KS19020WF	KD19020WF	S10020	D10020
VTX2012	KS19020WF	KD19020WF	S10020	D10020

Note: Boulay Series part numbers have additional available features, see below for more information.
Note: K Series panel part numbers include floats, to order without float switches, remove the "WF" suffix. Boulay Series panels do not include float switches.



K-SERIES

- NEMA 4X dead front outdoor rated enclosure
- Red LED alarm beacon
- HOA selector switch
- Single phase models handle 120, 208 and 230V service
- Three phase models handle 200, 230 and 460V service
- Requires separate control/alarm power feed

BOULAY SERIES


- NEMA 4X outdoor rated enclosure
- Red alarm beacon
- HOA selector switch
- Through door pump run light(s)
- Through door alarm test and horn silence button
- Single phase models handle 120, 208 and 230V service
- Three phase models handle 200, 230, 460 and 575V service

xylem
Let's Solve Water

Xylem Inc.
2881 East Bayard Street Ext., Suite A
Seneca Falls, NY 13148
Phone: (866) 325-4210 • Fax: (888) 322-5877
www.xylem.com/goolds
Goolds is a registered trademark of Goolds Pumps, Inc. and is used under license.
© 2019 Xylem Inc. BVTXSERIES R2 October 2019

PAGE 3

DATE	NO.	REVISION







PAPE-DAWSON ENGINEERS
SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TYPE FIRM REGISTRATION #470 | TYPE FIRM REGISTRATION #1008880

E-54 TEMPORARY LIFT STATION
TEMPORARY WETWELL DETAIL AND PUMP INFORMATION

SAWS JOB NO.	22-2502
JOB NO.	11500-51
DATE	DECEMBER 2023
DESIGNER	RM
CHECKED	DRAWN
SHEET	C3.00

EXHIBITS




LEGEND

	PROJECT LIMITS
	EXISTING GRADE
	PROPOSED GRADE
	100 YEAR FEMA FLOODPLAIN
	5 YEAR FEMA FLOODPLAIN
	TREES TO REMAIN
	SILT FENCE
	FLOW ARROW (EXISTING)
	FLOW ARROW (PROPOSED)
	ROCK BERM
	GRAVEL FILTER BAGS
	SEDIMENT CONTROL ROLLS
	STABILIZED CONSTRUCTION ENTRANCE/EXIT (FIELD LOCATE)
	CONSTRUCTION EQUIPMENT, VEHICLE & MATERIALS STORAGE AREA (FIELD LOCATE)
	CONCRETE TRUCK WASH-OUT PIT (FIELD LOCATE)
	AREA OF DISTURBANCE

NOTE:
 AREAS IN OR NEAR THE SITE AREA ARE CLASSIFIED AS R4SBA (RIVERINE, INTERMITTENT, STREAMBED, TEMPORARILY FLOODED) PER THE US FISH AND WILDLIFE SERVICE NATIONAL WETLANDS INVENTORY MAP. FIELD INVESTIGATIONS DETERMINED ONE JURISDICTIONAL WATER CROSSING. PLEASE REFER TO TPDES FOR DETAILS.

- GENERAL NOTES**
- DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION.
 - CONSTRUCTION ENTRANCE/EXIT LOCATION, CONCRETE WASH-OUT PIT, AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD TO BE DETERMINED IN THE FIELD.
 - STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO BE MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. ALL MODIFICATIONS ARE TO BE NOTED ON THIS EXHIBIT AND SIGNED AND DATED BY THE RESPONSIBLE PARTY.
 - RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY.
 - ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES.
 - FOR A COMPLETE LISTING OF TEMPORARY STORM WATER POLLUTION PREVENTION CONTROLS REFER TO THE TPDES STORM WATER POLLUTION PREVENTION PLAN.
 - STORM WATER POLLUTION PREVENTION STRUCTURES SHOULD BE CONSTRUCTED WITHIN THE SITE BOUNDARIES. SOME OF THESE FEATURES MAY BE SHOWN OUTSIDE THE SITE BOUNDARIES ON THIS PLAN FOR VISUAL CLARITY.
 - AS SOON AS PRACTICAL, ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.
 - BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADIENT AREAS.
 - BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED IN ACCORDANCE WITH TPDES REQUIREMENTS.
 - UPON COMPLETION OF THE PROJECT, INCLUDING SITE STABILIZATION, AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES, PAYING SPECIAL ATTENTION TO ROCK BERMS IN DRAINAGE FEATURES.
 - WHERE VEGETATED FILTER STRIPS ARE INDICATED, CONTRACTOR SHALL VERIFY THAT SUFFICIENT VEGETATION EXISTS. OTHERWISE CONTRACTOR SHALL PLACE SILT FENCING IN LIEU OF VEGETATED FILTER STRIP.
 - SHADED AREA DENOTES LIMITS OF DISTURBED AREAS. OTHER AREAS WITHIN THE PROJECT LIMITS, WITH THE EXCEPTION OF A CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD, ARE NOT A PART OF THIS TPDES STORM WATER POLLUTION PREVENTION PLAN (SWP3) AND WILL NOT BE DISTURBED BY CIVIL CONSTRUCTION ACTIVITIES. HOUSE CONSTRUCTION ACTIVITIES WILL REQUIRE A SEPARATE STORM WATER POLLUTION PREVENTION PLAN.
 - PRIOR TO BEGINNING CONSTRUCTION, CONTRACTOR SHALL COORDINATE PLACEMENT OF TEMPORARY BEST MANAGEMENT PRACTICES WITHIN TxDOT RIGHT-OF-WAY WITH TxDOT.
 - CPS ENERGY WILL FUNCTION AS A SECONDARY OPERATOR ON THIS PROJECT AND WILL BE INSTALLING ELECTRIC UTILITIES FOR ON-SITE CONSTRUCTION AND OFF-SITE FEED TO THE PROJECT.
- THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.



SWP3 MODIFICATIONS

DATE	SIGNATURE	DESCRIPTION

DATE	
NO.	
REVISION	



PAPE-DAWSON ENGINEERS
 SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TYPE FIRM REGISTRATION #470 | TYPE FIRM REGISTRATION #1008880

SAWS E-54 SANITARY SEWER PROJECT
 BEXAR COUNTY, TEXAS
 SEGMENT B
 STORMWATER POLLUTION PREVENTION PLAN
 STA 1+00 TO STA 23+00

SAWS JOB NO. 21-4404
 JOB NO. 11500-51
 DATE OCTOBER 2021
 DESIGNER MP
 CHECKED JD DRAWN BS
 SHEET C5.00B



EXHIBIT 2

Date: Nov 23, 2021, 3:43pm, User: JD, E:\Energy, File: P:\145\000\51\Drawings\GIS\Sanitary\Segment B\TPES-11500051\2.dwg
 THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.

TEMPORARY BMP MODIFICATIONS		
DATE	SIGNATURE	DESCRIPTION

LEGEND

- PROJECT LIMITS
- EXISTING GRADE
- PROPOSED GRADE
- FLOW ARROW (EXISTING)
- FLOW ARROW (PROPOSED)
- SILT FENCE
- ROCK BERM
- GRAVEL FILTER BAGS
- STABILIZED CONSTRUCTION ENTRANCE/EXIT (FIELD LOCATE)
- CONSTRUCTION EQUIPMENT, VEHICLE & MATERIALS STORAGE AREA (FIELD LOCATE)
- CONCRETE TRUCK WASH-OUT PIT (FIELD LOCATE)
- GEOLOGIC FORMATIONS
- PERSON
- SYMBOLS AND LINES
- POTENTIAL RECHARGE FEATURE



LOCATION MAP
NOT-TO-SCALE

GENERAL NOTES

- DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION.
- LOCATIONS OF CONSTRUCTION ENTRANCE/EXITS, CONCRETE WASHOUT PITS, AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARDS TO BE DETERMINED IN THE FIELD.
- STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO BE MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. ALL MODIFICATIONS ARE TO BE NOTED ON THIS EXHIBIT AND SIGNED AND DATED BY THE RESPONSIBLE PARTY.
- RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY.
- ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES.
- CONTRACTOR, TO THE EXTENT PRACTICAL, SHALL MINIMIZE THE AMOUNT OF AREA DISTURBED AS SOON AS CONSTRUCTION ENDS. ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.
- BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADE AREAS.
- BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED.
- ALL TEMPORARY BMPs WILL BE REMOVED ONCE WATERSHED IS STABILIZED.
- MUD OR DIRT INADVERTENTLY TRACKED OFF-SITE AND ONTO EXISTING STREETS SHALL BE REMOVED IMMEDIATELY BY HAND OR MECHANICAL BROOM SWEEPING.
- PRIOR TO INITIATION OF SUBSEQUENT PHASES OF CONSTRUCTION, TEMPORARY BMPs INCLUDING SILT FENCING, CONSTRUCTION ENTRANCE/EXIT, CONCRETE WASHOUT PIT, AND CONSTRUCTION STAGING AREA SHALL BE FIELD LOCATED AS APPROPRIATE FOR THE AREA OF CONSTRUCTION.
- TEMPORARY POLLUTION ABATEMENT MEASURES SHOWN ON THE PLAN ARE FOR THE OVERALL DEVELOPMENT. TEMPORARY BMPs MAY REQUIRE ADJUSTMENT BASED ON PHASING OF CONSTRUCTION OF THE DEVELOPMENT. RECORDS OF ADJUSTMENTS AND REVISIONS SHALL BE MAINTAINED AS APPROPRIATE.
- TEMPORARY BMPs SHOWN ON THIS SHEET ARE FOR GRAPHICAL PURPOSES AND MAY NOT BE TO SCALE. BMPs SHALL BE LOCATED WITHIN THE PROJECT LIMITS.
- UPON COMPLETION OF THE PROJECT AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SEQUENCING AND REMOVAL OF TEMPORARY POLLUTION ABATEMENT MEASURES THAT CONFLICT WITH SITE IMPROVEMENTS SUCH AS LANDSCAPING AND FENCES SO AS TO PREVENT SEDIMENT FROM ESCAPING THE PROJECT SITE.



TCEQ WATER POLLUTION ABATEMENT PLAN
GENERAL CONSTRUCTION NOTES


- A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
 - THE NAME OF THE APPROVED PROJECT;
 - THE ACTIVITY START DATE; AND
 - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.
- IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SNK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCEQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES MAY NOT BE RESUMED UNTIL THE TCEQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.
- NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.
- PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
- ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.
- SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.
- LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.
- ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARDS AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE OTHER SITE.
- IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.
- THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
 - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
 - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
 - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.
- THE HOLDER OF ANY APPROVED EDWARDS AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
 - ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
 - ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
 - ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

SAN ANTONIO REGIONAL OFFICE
14250 JUDSON ROAD
SAN ANTONIO, TEXAS 78233-4480
PHONE (210) 490-3096
FAX (210) 545-4329

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUAL.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

EXHIBIT 1




Date: Jan 15, 2024, 2:25pm User ID: mcsweeney File: P:\145\100\51\Design\Environmental\WPAP\WPAP_TJ1150051.dwg

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT HAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARD COPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.


NO.	REVISION	DATE

E-54 REGIONAL LIFT STATION
WATER POLLUTION ABATEMENT PLAN
TEMPORARY WATER POLLUTION ABATEMENT PLAN

SAWS JOB NO.	22-2502
JOB NO.	11500-51
DATE	JANUARY 2023
DESIGNER	RM
CHECKED	JD DRAWN
SHEET	1 of 1



SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT



SECTION "A-A" OF A CONSTRUCTION ENTRANCE/EXIT

MATERIALS

1. THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN.
2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 8-INCHES.
3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD², A MULLEN BURST RATING OF 140 LB/IN², AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.
4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OR BASIN.

INSTALLATION


1. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.
2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.
3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG.
4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE, 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.
5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.
6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.
7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.
8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.

COMMON TROUBLE POINTS


1. INADEQUATE RUNOFF CONTROL—SEDIMENT WASHES ONTO PUBLIC ROAD.
2. STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY CONDITION AS STONE IS PRESSED INTO SOIL.
3. PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC—EXTEND PAD BEYOND THE MINIMUM 50-FOOT LENGTH AS NECESSARY.
4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.
5. UNSTABLE FOUNDATION — USE GEOTEXTILE FABRIC UNDER PAD AND/OR IMPROVE FOUNDATION DRAINAGE.

INSPECTION AND MAINTENANCE GUIDELINES

1. THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.
3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.
5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.



ISOMETRIC PLAN VIEW



SECTION "A-A"

ROCK BERMS

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.
2. REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.
3. REPAIR ANY LOOSE WIRE SHEATHING.
4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION.
5. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

MATERIALS

1. THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOT RINGS.
2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE USED.


INSTALLATION

1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH OPENINGS.
2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER.
3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18".
4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH THE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.
5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE.
6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.

COMMON TROUBLE POINTS

1. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).
2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL NOT-TO-SCALE



MATERIALS

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH (± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE SHOOT GROWTH AND THATCH.
2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND LENGTH, WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5% TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.
3. STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO SUPPORT THEIR OWN WEIGHT AND THEIR SIZE AND SHAPE WHEN SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.
4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD OF 36 HOURS.

SITE PREPARATION

1. PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.
2. THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL ROOTS, BRUSH, WIRE GRADE STAKES AND OTHER OBJECTS THAT WOULD INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.
3. FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT ON SLOPING LAND, THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

INSTALLATION IN CHANNELS

1. SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS TIGHTLY (SEE FIGURE ABOVE).
2. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL AREAS.


GENERAL INSTALLATION (VA. DEPT. OF CONSERVATION, 1992)

1. SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN.
2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND REDUCE ROOT BURNING AND DIEBACK.
3. THE FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS (SEE FIGURE ABOVE).
4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OR OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).
5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL.
6. AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS THOROUGHLY WET.
7. UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4 INCHES.
8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

INSPECTION AND MAINTENANCE GUIDELINES

1. SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.
2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS SOON AS PRACTICAL.

ROCK BERM DETAIL NOT-TO-SCALE



SILT FENCE

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

MATERIALS

1. SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN², ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.
2. FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS EXCEEDING 140.
3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

INSTALLATION

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER, WHERE WATER CONCENTRATES. THE MAXIMUM SPACING SHOULD BE 6 FEET.
2. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.
4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.
5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.
6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

COMMON TROUBLE POINTS


1. FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO CONCENTRATE AND FLOW OVER THE FENCE.
2. FABRIC NOT SEALED SECURELY TO GROUND (RUNOFF PASSING UNDER FENCE).
3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND SIDES).
4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL.
2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.
3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TRENCH SECTION.
4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.
5. WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

SOD INSTALLATION DETAIL NOT-TO-SCALE

THIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL.



GRAVEL FILTER BAG DETAIL NOT-TO-SCALE

GENERAL NOTES

1. THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.
2. THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER).
3. SAND SHALL NOT BE USED TO FILL THE FILTER BAGS.


MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

MAINTENANCE

1. WHEN "TEMPORARY" CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF.
2. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF.
3. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

CONCRETE TRUCK WASHOUT PIT DETAIL NOT-TO-SCALE



CONSTRUCTION STAGING AREA NOT-TO-SCALE

GENERAL NOTES

1. DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.
2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.
3. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.
4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES.
5. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.

MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

MAINTENANCE

1. WHEN "TEMPORARY" CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF.
2. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF.
3. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

CONCRETE TRUCK WASHOUT PIT DETAIL NOT-TO-SCALE

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

NO.	REVISION	DATE



PAPE-DAWSON ENGINEERS

SAN ANTONIO | AUSTIN | HOUSTON | FORT WORTH | DALLAS
 2000 HW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
 TEXAS FIRM REGISTRATION #470 | TBPUS FIRM REGISTRATION #008890

SAWS E-54 SANITARY SEWER PROJECT
 BEXAR COUNTY, TEXAS

WATER POLLUTION ABATEMENT PLAN
TEMPORARY WATER POLLUTION ABATEMENT PLAN DETAILS

SAWS JOB NO. 21-4404
 JOB NO. 11500-51
 DATE: OCTOBER 2021
 DESIGNER: CD
 CHECKED: MP DRAWN: BS
 SHEET 1 of 1