OAKWOOD BAPTIST CHURCH

Sewage Collection System Modification Application

October 2024

PAPE-DAWSON ENGINEERS

Transportation | Water Resources | Land Development | Surveying | Environmental

OAKWOOD BAPTIST CHURCH

Sewage Collection System Modification Application

October 2024

PAPE-DAWSON ENGINEERS

October 15, 2024

Ms. Monica Reyes
Texas Commission on Environmental Quality
Region 13
14250 Judson Road
San Antonio, Texas 78233-4480

Re: Oakwood Baptist Church
Sewage Collection System Modification Application

Dear Ms. Reyes:

Please find included herein the Oakwood Baptist Church Sewage Collection System Modification Application. This Sewage Collection System Modification Application has been prepared to be consistent with the regulations of the Texas Administrative Code (30 TAC 213, 217 and 290) and current policies for development over the Edwards Aquifer Recharge Zone.

This Sewage Collection System Modification Application applies to the 1,159 linear feet of sewer main proposed as part of this project. Please review the plan information for the items it is intended to address. If acceptable, provide a written approval of the plan in order that construction may begin at the earliest opportunity.

Appropriate review fees ($650) and fee application form are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,
Pape-Dawson Consulting Engineers, LLC



Caleb Chance, P.E.
Vice President

Attachments

\\Pape-Dawson.Com\Sat-Pd\118\63\02\Word\Reports\SCS MOD\240917a1.Docx

EDWARDS AQUIFER APPLICATION COVER PAGE (TCEQ-20705)

Texas Commission on Environmental Quality

Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

Administrative Review

1. Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

   To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: http://www.tceq.texas.gov/field/eapp.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.

3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.

4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

   An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.

6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.

2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.

4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Oakwood Baptist Church						**2. Regulated Entity No.:** 102744802			
3. Customer Name: Oakwood Baptist Church						**4. Customer No.:** 601399199			
5. Project Type: **(Please circle/check one)**	New		Modification			Extension		Exception	
6. Plan Type: **(Please circle/check one)**	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: **(Please circle/check one)**	Residential		Non-residential			**8. Site (acres):**		36.16	
9. Application Fee:	$650.00		**10. Permanent BMP(s):**			(2) Batch Detention Basins and (1) VFS			
11. SCS (Linear Ft.):	1140		**12. AST/UST (No. Tanks):**						
13. County:	Comal		**14. Watershed:**			Blieders Creek			

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	**Hays**	**Travis**	**Williamson**
Original (1 req.)	☐	☐	☐
Region (1 req.)	☐	☐	☐
County(ies)	☐	☐	☐
Groundwater Conservation District(s)	☐ Edwards Aquifer Authority ☐ Barton Springs/ Edwards Aquifer ☐ Hays Trinity ☐ Plum Creek	☐ Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	☐ Austin ☐ Buda ☐ Dripping Springs ☐ Kyle ☐ Mountain City ☐ San Marcos ☐ Wimberley ☐ Woodcreek	☐ Austin ☐ Bee Cave ☐ Pflugerville ☐ Rollingwood ☐ Round Rock ☐ Sunset Valley ☐ West Lake Hills	☐ Austin ☐ Cedar Park ☐ Florence ☐ Georgetown ☐ Jerrell ☐ Leander ☐ Liberty Hill ☐ Pflugerville ☐ Round Rock

San Antonio Region					
County:	**Bexar**	**Comal**	**Kinney**	**Medina**	**Uvalde**
Original (1 req.)	☐	✔	☐	☐	☐
Region (1 req.)	☐	✔	☐	☐	☐
County(ies)	☐	✔	☐	☐	☐
Groundwater Conservation District(s)	☐ Edwards Aquifer Authority ☐ Trinity-Glen Rose	✔ Edwards Aquifer Authority	☐ Kinney	☐ EAA ☐ Medina	☐ EAA ☐ Uvalde
City(ies) Jurisdiction	☐ Castle Hills ☐ Fair Oaks Ranch ☐ Helotes ☐ Hill Country Village ☐ Hollywood Park ☐ San Antonio (SAWS) ☐ Shavano Park	☐ Bulverde ☐ Fair Oaks Ranch ☐ Garden Ridge ✔ New Braunfels ☐ Schertz	NA	☐ San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review. CALEB CHANCE
Print Name of Customer/Authorized Agent
Signature of Customer/Authorized Agent 10/17/24 Date

FOR TCEQ INTERNAL USE ONLY				
Date(s)Reviewed:		Date Administratively Complete:		
Received From:		Correct Number of Copies:		
Received By:		Distribution Date:		
EAPP File Number:		Complex:		
Admin. Review(s) (No.):		No. AR Rounds:		
Delinquent Fees (Y/N):		Review Time Spent:		
Lat./Long. Verified:		SOS Customer Verification:		
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):	
Core Data Form Complete (Y/N):			Signed (Y/N):	
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):	

GENERAL INFORMATION FORM (TCEQ-0585)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: Caleb Chance, P.E.

Date: 10/15/2024

Signature of Customer/Agent:



Project Information

1. Regulated Entity Name: Oakwood Baptist Church
2. County: Comal
3. Stream Basin: Blieders Creek
4. Groundwater Conservation District (If applicable): Edwards Aquifer/ Comal Trinity
5. Edwards Aquifer Zone:

   ☒ Recharge Zone
   ☐ Transition Zone

6. Plan Type:

   ☐ WPAP
   ☒ SCS
   ☒ Modification
   ☐ AST
   ☐ UST
   ☐ Exception Request

7. Customer (Applicant):

   Contact Person: Roxi Vanstory
   Entity: Oakwood Baptist Church
   Mailing Address: 2154 Loop 337
   City, State: New Braunfels, Texas Zip: 78130
   Telephone: (830) 625 -0267 FAX: (830) 625-1151
   Email Address: roxi.vanstory@oakwoodnb.com

8. Agent/Representative (If any):

   Contact Person: Caleb Chance, P.E.
   Entity: Pape-Dawson Engineers, Inc.
   Mailing Address: 2000 NW Loop 410
   City, State: San Antonio, Texas Zip: 78213
   Telephone: (210) 375-9000 FAX: (210) 375-9010
   Email Address: cchance@pape-dawson.com

9. Project Location:

   ☒ The project site is located inside the city limits of New Braunfels.
   ☒ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of New Braunfels.
   ☐ The project site is not located within any city's limits or ETJ.

10. ☒ The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

    From TCEQ regional office proceed approximately 1.5 miles south on Judson Road to I35 north and turn left to travel northeast. Proceed approximately 14.5 miles to TX-337 Loop and turn left to travel north. Drive approximately 4.7 miles to the site is located on your left. The site is located approximately 650 ft northeast of Loop 337 and Oakwood Blvd intersection. Site address is 2154 TX-337Loop, New Braunfels TX, 78130.

11. ☒ **Attachment A – Road Map**. A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.

12. ☒ **Attachment B - USGS / Edwards Recharge Zone Map**. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:

    ☒ Project site boundaries.
    ☒ USGS Quadrangle Name(s).
    ☒ Boundaries of the Recharge Zone (and Transition Zone, if applicable).
    ☒ Drainage path from the project site to the boundary of the Recharge Zone.

13. ☒ **The TCEQ must be able to inspect the project site or the application will be returned**. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.

☒ Survey staking will be completed by this date: When advised by TCEQ of site visit

14. ☒ **Attachment C – Project Description**. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:

☒ Area of the site
☐ Offsite areas
☐ Impervious cover
☐ Permanent BMP(s)
☒ Proposed site use
☐ Site history
☐ Previous development
☐ Area(s) to be demolished

15. Existing project site conditions are noted below:

☐ Existing commercial site
☐ Existing industrial site
☐ Existing residential site
☐ Existing paved and/or unpaved roads
☐ Undeveloped (Cleared)
☐ Undeveloped (Undisturbed/Uncleared)
☒ Other: Church

Prohibited Activities

16. ☒ I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:

(1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);

(2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;

(3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;

(4) The use of sewage holding tanks as parts of organized collection systems; and

(5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).

(6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.

17. ☐ I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:

(1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);

(2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

18. The fee for the plan(s) is based on:

☐ For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
☒ For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
☐ For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
☐ A request for an exception to any substantive portion of the regulations related to the protection of water quality.
☐ A request for an extension to a previously approved plan.

19. ☒ Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:

☐ TCEQ cashier
☐ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)
☒ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

20. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

21. ☒ No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.

ATTACHMENT A

OAKWOOD BAPTIST CHURCH
New Braunfels, Texas

Sewer Collection System Plan

N
NOT TO SCALE



Pape-Dawson Engineers, Inc.

Date: Oct 15, 2024, 11:54am User ID: SShrestha
File: \\pape-dawson.com\sat-pd\118\63\02\Design\Environmental\SCS\RM1186302.dwg

ATTACHMENT A
Road Map

ATTACHMENT B

OAKWOOD BAPTIST CHURCH
Sewage Collection System Application

N

SCALE: 1" = 2000'



Date: Oct 15, 2024, 11:52am User ID: SShrestha
File: \\pape-dawson.com\sat-pd\178\63\02\Design\Environmental\SCS\20178302.dwg

GENERAL LOCATION MAP - NEW BRAUNFELS WEST, TX QUAD;
NEW BRAUNFELS EAST, TX QUAD
DRAINAGE FLOW → →

Pape–Dawson Engineers, Inc.

USGS/EDWARDS RECHARGE ZONE MAP

ATTACHMENT B

ATTACHMENT C

OAKWOOD BAPTIST CHURCH
Sewage Collection System Modification Plan

Attachment C – Project Description

The Oakwood Baptist Church is a commercial development on an approximately 36.44 acres within the city of New Braunfels in Comal County, Texas. The site is located approximately 650 ft northeast of the TX-337 Loop and Oakwood Blvd intersection and is currently developed as a church and lies within the Blieders Creek watershed and does not contain 100-year floodplain.

The Oakwood Baptist Sewage Collection System (SCS) was approved by the Texas Commission on Environmental Quality on February 6, 2012 for construction of a total of 2262 linear feet (LF) of sewer main to serve the church. The alignment approved 1062 LF of 8-inch (8") PVC, SDR 26 gravity sewer main, 40 LF of 8-inch (8") PVC, SDR 26, 1160 LF of 6-inch (6") PVC, SDR 26, 160-psi pressure-rated sewer main centered at water line crossings. This proposed SCS Modification will remove 2 existing onsite lift stations to provide a gravity solution for the entire Oakwood Baptist Church Campus.

The Oakwood Baptist Church-Worship Center Expansion Sewage Collection System (SCS) Application proposes the construction of a total of approximately 1159 linear feet (LF) of sanitary sewer main to serve the proposed commercial development over the Edwards Aquifer Recharge Zone. The proposed alignment will consist of approximately 1159 linear feet (LF) of 8-inch (8") polyvinyl chloride (PVC), SDR 26 gravity sewer main, see included plan and profile exhibits for details. Regulated activities proposed include excavation, construction of sewer mains, manholes, backfill, and compaction. Approximately 2.80 acres may be disturbed as identified by the limits of the fifty foot (50') SCS/GA envelope shown on the plans; however additional grading will disturb approximately 18.25 acres as part of development of the overall unit as approved in the Oakwood Baptist Church Expansion WPAP (EAPP ID# 13001965).

This project will result in an estimated additional 26 Living Unit Equivalent (LUEs). This is based on the additional seating capacity of 1,833 from the proposed Worship Center. Approximately 21,000 gallons per day (average daily dry weather flow) of domestic wastewater are estimated to be generated by this project which includes the existing flow as well. The proposed sanitary sewer main will tie into an existing manhole.

The sewage flow will be disposed of by conveyance to the existing Gruene Road Sewage Treatment Plant Water Recycling Center operated by the New Braunfels Utility (NBU). Potable water will be supplied by NBU. No naturally occurring sensitive features were identified with the SCS envelope in the Geological Assessment.

GEOLOGIC ASSESSMENT FORM (TCEQ-0585)

GEOLOGIC ASSESSMENT (WPAP)

OAKWOOD BAPTIST CHURCH TRACT
+/- 39 ACRES
NEW BRAUNFELS, TEXAS

FROST GEOSCIENCES, INC. PROJECT NO.: FGS-E19135
MARCH 25, 2019

Prepared exclusively for

Oakwood Baptist Church
2154 Loop 337
New Braunfels, Texas 78130

Frost GeoSciences
Geotechnical ▪ Construction Materials
Geologic ▪ Environmental

Frost GeoSciences
Geotechnical ▪ Construction Materials
Geologic ▪ Environmental

Frost Geosciences, Inc.
13406 Western Oak
Helotes, Texas 78023
Office (210)-372-1315
Fax (210)-372-1318
www.frostgeosciences.com
TBPE Firm Registration # F-9227
TBPG Firm Registration # 50040

March 25, 2019

Oakwood Baptist Church
2154 Loop 337
New Braunfels, Texas 78130

Attn: Ms. Roxi Vanstory, Executive Administrator

SUBJECT:
Geologic Assessment (WPAP)
for the Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
+/- 39 Acres
New Braunfels, Texas
FGS Project Nº FGS-E19135

Dear Ms. Roxi Vanstory:

Frost GeoSciences, Inc., (FGS) is pleased to submit the enclosed Geologic Assessment completed for the above referenced project site as it relates to 30 TAC §213.5(b)(3), effective June 1, 1999. Our investigation was conducted, and this report was prepared in general accordance with the "Instructions to Geologists", TCEQ-0585-Instructions (Rev. 10-1-04).

If you have any questions regarding this report, or if Frost GeoSciences, Inc. may be of additional assistance to you on this project, please feel free to call our office. It has been a pleasure to work with you and we wish to thank you for the opportunity to be of service to you on this project. We look forward to being of continued service.

We appreciate the opportunity to perform these services for Oakwood Baptist Church. Please contact the undersigned if you have questions regarding this report.

Respectfully submitted,
Frost GeoSciences, Inc.

STATE OF TEXAS
Christopher Wickman
Geology
10403
LICENSED PROFESSIONAL GEOSCIENTIST

Hunter Patterson
Project Manager

Chris Wickman, P.G.
Senior Geologist

Copies Submitted:
(1) Ms. Roxi Vanstory; Oakwood Baptist Church
(6) Pape Dawson Engineers
(1) Electronic (pdf) Copy

TABLE OF CONTENTS

LOCATION

The project site is located along and north of Texas Loop 337 approximately 0.90 miles west of the intersection Texas Loop 337 and River Road in New Braunfels, Texas. The address of the project site is 2154 Texas Loop 337 in New Braunfels, Texas. An overall view of the area is shown on copies of the site plan, a street map, the U.S.G.S. Topographic Map, the EAA-Edwards Aquifer Recharge Zone and Contributing Zone Map, the FIRM Map, the Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties Map, the Bureau of Economic Geology: Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle, a 2018 aerial photograph at a scale of 1"=500', a 2018 aerial photograph at a scale of 1"=200', and a 1973 aerial photograph at a scale of 1"=500' and are included on Figures 1 through 9 in Appendix A.

METHODOLOGY

The Geologic Assessment was performed by Chris Wickman, P.G., Senior Geologist and Hunter Patterson with Frost GeoSciences, Inc. Mr. Wickman is a Licensed Professional Geoscientist in the State of Texas (License # 10403).

Frost GeoSciences, Inc. researched the geology of the area west of the intersection of TX Loop 337 and River Road. The research included, but was not limited to, the Geologic Atlas of Texas, San Antonio Sheet, FEMA maps, Edwards Aquifer Recharge Zone Maps, U.S.G.S. 7.5 Minute Quadrangle Maps, the Bureau of Economic Geology-Geologic Atlas of Texas, the Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas, the Geologic Framework and Hydrogeologic Characteristics of the Edwards Aquifer Outcrop, Comal County, Texas, U.S. Geological Survey Water Resources Investigations Report 94-4117, and the U.S.D.A. Soil Survey of Comal and Hays Counties, Texas.

After reviewing the available information, a field investigation was performed to identify any geologic or man-made Potential Recharge Features (PRFs). A transect spacing of approximately 50 feet, or less depending on vegetation thickness, was used to inspect the project area. A 2018 aerial photograph, in conjunction with a hand-held Garmin GPS 72H Global Positioning System with an Estimated Potential Error ranging from 10 to 14 feet, was used to navigate around the property and identify the locations of PRFs, as recommended in the "Instructions to Geologists", TCEQ-0585-Instructions (Rev. 10-1-04). The Site Geologic Map, indicating the limits of the project site, and the locations of PRFs and rock outcrops noted on the project site, is included in Appendix C. A copy of a 2018 Aerial Photograph at an approximate scale of 1" =200' indicating the limits of the project site, and the locations of PRFs and rock outcrops noted on the project site, is included on Figure 9 in Appendix A. The Geologic Assessment Form TCEQ-0585, (Rev. 2-11-15), Stratigraphic Column, and the Geologic Assessment Table have been filled with the appropriate information for this project site and are included as Attachments at the end of this report.

RESEARCH & OBSERVATIONS

7.5 Minute Quadrangle Map Review

According to the U.S.G.S. 7.5 Minute Quadrangle Map, New Braunfels West, Texas Sheet (1992), the elevation across the project site ranges from 750 to 790 feet above mean sea level. The project site has a total relief of approximately 40 feet. Runoff from the project site flows north and northeast into unnamed tributary of Blieders Creek. The topographic map depicts the project site as largely undeveloped with a church building located in the southern portion of the project site. Texas Loop 337 is located along the southeastern property line of the project site. A copy of the U.S.G.S. 7.5 Minute Quadrangle Map indicating the location of the project site is included on Figure 3 in Appendix A.

Recharge/Transition Zone

According to the E.A.A. Edwards Aquifer Recharge Zone and Contributing Zone Map, New Braunfels West, Texas (2014), the Official Edwards Aquifer Recharge Zone Map, New Braunfels West, Texas Sheet (1994) and the Texas Commission on Environmental Quality (TCEQ) website: Edwards Aquifer Viewer – https://tceq.maps.arcgis.com/apps/webappviewer/index.html, the project site is located within the Recharge Zone of the Edwards Aquifer. A copy of the E.A.A. Edwards Aquifer Recharge Zone and Contributing Zone Map indicating the location of the project site is included on Figure 4 in Appendix A.

100-Year Floodplain

The Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map, Community Panel Number 4891C0435F, dated September 2, 2009 was reviewed to determine if the project site is located in areas prone to flooding. A review of the above-mentioned Panel No. indicates that the project site is located within "Zone X". According to the Panel Legend, Zone X represents areas determined to be outside the 0.2% annual chance floodplain. A copy of the above referenced FIRM panel indicating the location of the project site is included on Figure 5 in Appendix A.

Soils

According to the United States Department of Agriculture, Soil Conservation Service, Soil Survey of Comal & Hays Counties, Texas, issued (1984), the project site is located on the Comfort-Rock outcrop complex, undulating (CrD) and the Rumple-Comfort Association (RUD). A copy of the 1973 aerial photo (approximate scale: 1" =500') from the U.S.D.A. Soil Survey of Comal & Hays Counties, Texas indicating the location of the project site and the soil types is included on Figure 6 in Appendix A.

- The Comfort-Rock Outcrop Complex consists of shallow, clayey soils and Rock Outcrop on side slopes and on hilltops and ridgetops on uplands in the Edwards Plateau Land Resource Area. The Comfort Extremely Stony Clay makes up 49 to more than 95 percent of the complex, but on the average, it makes up 70 percent. Rock Outcrop and areas of soil less than 4 inches deep make up 5 to 36 percent, but the average is 15 percent. Typically, the surface layer of the Comfort soil is dark brown extremely stony clay about 6

inches thick. Cobbles and stones as much as 4 feet across cover about 45 percent of the surface. The subsoil extends to a depth of 13 inches. It is dark reddish brown extremely stony clay. The underlying material is indurated fractured limestone. The soil is mildly alkaline and noncalcareous throughout. The Comfort Soil is well drained. Surface runoff is slow to medium. Permeability is slow, and the available water capacity is very low. Water erosion is a slight hazard. This soil has a USDA Texture Classification of extremely stony clay, stony clay, very stony clay, and weathered bedrock. The Unified Classification is CH, GC, CL, or SC. The AASHO Classification is A-2-7, and A-7-6. This soil has an average permeability from 0.6 to 0.2 inches/hour.

- The Rumple-Comfort Association (RUD) consists of shallow and moderately deep soils on uplands in the Edwards Plateau Land Resource Area. The surface layer of the Rumple Soil is dark reddish brown very cherty clay loam about 10 inches thick. Rounded chert and limestone cobbles and gravel cover about 20 percent of the surface. The subsoil to a depth of 14 inches is dark reddish-brown very cherty clay, and to a depth of 28 inches it is dark reddish-brown extremely stony clay. The underlying material is indurated fractured limestone. The Comfort Soil is dark brown, neutral, extremely stony clay about 7 inches thick. The subsoil to a depth of 12 inches is dark reddish-brown, mildly alkaline, extremely stony clay. The underlying material is indurated fractured limestone. The soil is non-calcareous throughout. The soils in this association are well drained. Surface runoff is medium, but varies due to the occurrence of caves, fracture zones, and sinks. Permeability is moderately slow. Water erosion is a moderate hazard. This soil has a USDA Texture Classification of that ranges from very cherty clay loam to very cherty clay, extremely stony clay and extremely stony clay, stony clay to very stony clay and extremely stony clay. The Unified Classification is GC, CL, SC and CH, GC, SC and CL. The AASHO Classification is A-2-6, A-6, A-2-7 and A-7-6. This soil has an average permeability from 0.2 to 0.6 and 0.06 to 0.2 inches/hour.

Narrative Description of the Site Geology

Based on a visual inspection of the ground surface, the overall potential for fluid flow from the project site into the Edwards Aquifer appears to be low. The locations of the PRFs are identified on the 2018 aerial photograph on Figure 9 in Appendix A, and on the Site Geologic Map provided in the Attachments at the end of the report. Color photos of the project site and some of the PRFs are included in Appendix B.

Potential Recharge Feature #s S-1, S-2, and S-3 are manmade features in bedrock. These features are storm water detention ponds. The detention ponds receive storm water runoff from the parking area associated with the Oakwood Baptist Church. PRF #S-1 is the largest of the three and was observed in the central portion of the project site. The entire feature was approximately 530 feet long, 130 feet wide and ranged approximately in depth from 3 to 8 feet.

PRF #S-2 consisted of an outlet channel associated with PRF #S-1. This feature was approximately 140 feet long and 30 feet wide. The feature was about 7 feet deep. The channel discharged to the off-site property north of the project site. PRF #S-3 was observed in the western portion of the project site. The feature was about 60 feet wide and 150 feet long. The feature was approximately 6 feet deep. Storm water inlets were observed adjacent to the larger detention pond (S-1) and are discussed in the following paragraph. Frost GeoSciences, Inc. rates the relative infiltration of these features as low on figure 1 of the TCEQ-0585-Instructions (Rev. 10-01-04). The features score a 35 on the sensitivity scale, column 10 in the Geologic Assessment Table included within the Attachments at the end of this report. Frost GeoSciences, Inc. does not consider these manmade features to be sensitive.

Potential Recharge Feature #s S-4, S-5, and S-7 are manmade features in bedrock. These features are storm-water inlets associated with the large detention pond (PRF #S-1). The features consisted of rectangular slabs of concrete with a circular metal manhole cover. Frost GeoSciences, Inc. rates the relative infiltration of these features as low on figure 1 of the TCEQ-0585-Instructions (Rev. 10-01-04). The features score a 35 on the sensitivity scale, column 10 in the Geologic Assessment Table included within the Attachments at the end of this report. Frost GeoSciences, Inc. does not consider these manmade features to be sensitive.

PRF #s S-6, S-9, S-10, S-11 and S-2 are manmade features in bedrock. These PRFs are sanitary sewer manhole vaults associated with the City of New Braunfels, Texas sanitary sewer utilities. Frost GeoSciences, Inc. rates the relative infiltration of the features as low on figure 1 of the TCEQ-0585-Instructions (Rev. 10-01-04). The features score a 35 on the sensitivity scale, column 10 in the Geologic Assessment Table included within the Attachments at the end of this report. Frost GeoSciences, Inc. does not consider this manmade feature to be sensitive.

According to signage observed on adjacent electrical/plumbing equipment, PRF #S-8 is a lift station. The perimeter of the lift station facility was surrounded by a chain-link fence topped with barbed wire. The lift station appears to be associated with PRF #S-1 and is operated by the Oakwood Baptist church. The equipment appeared to be well maintained and in working order. No obvious visual indications of releases or spills were observed from the lift station at the time of the site inspection and no significant odors were detected emanating from the lift station. Based on the observations of the lift station from the perimeter fence surrounding the equipment, Frost GeoSciences, Inc. rates the facility as low on Figure 1 of the TCEQ-0585-Instructions (Rev. 10-01-04). The feature scores a 35 on the sensitivity scale, column 10 in the Geologic Assessment Table included within the Attachments at the end of this report. Frost GeoSciences, Inc. does not consider the septic tank to be sensitive.

PRF #S-13 was a manmade feature in bedrock. PRF #S-13 appeared to be a septic system tank located in the south portion of the Site. Frost GeoSciences, Inc. rates this feature as low on Figure 1 of the TCEQ-0585-Instructions (Rev. 10-01-04). This PRF scores a 35 on the sensitivity scale, column 10 in the Geologic Assessment Table included within the Attachments at the end of this report. Frost GeoSciences, Inc. does not consider the septic tank to be sensitive.

Oakwood Baptist Church with associated asphalt-paved parking areas covered the southern and southwestern portions of the project site. The remaining areas of the project site consisted largely of open grassy land with a sparse stand of oak trees observed in the southeastern portion of the project site. Site visit photos indicating the condition of the property at the time of the on-site inspection are included in Appendix B. The variations in the vegetative cover on the property are visible in the 2018 aerial photo on Figures 8 and 9 in Appendix A. A copy of the site layout indicating the boundary of the project site and the elevations is included on Figure 1 in Appendix A.

According to the U.S. Geological Survey, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas, Science Investigations Map 3366 and the Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle, the project site is located on the Cretaceous Edwards Person Limestone. The Science Investigations Map 3366 further delineates the Edwards Person into three members which include: the cyclic and marine, undivided member, the leached and collapsed member and the regional dense member. Review of the Science Investigations Map 3366 puts the project site over the leached and collapsed member of the Edwards Person limestone with an area of the cyclic and marine, undivided member occurring in the southwestern portion of the project site. A copy of the Science Investigations Map 3366 and the Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle are included on Figures 7A and 7B in Appendix A. A copy of the Stratigraphic Column highlighting the outcropping formations is included on in the Attachment at the end of this report.

- The Cylic Marine Member of the Person Formation (Kpcm) consists of limestone, dolomitic limestone, dolomite, and lesser argiliaceous limestone; approximately equivalent to Segovia Formation of eastern Edwards Plateau.

- The Leached and Collapsed Member of the Edwards Person Limestone consists of crystalline limestone, mudstone to grainstone with chert, and collapsed breccia. This member is stromatolitic limestone. The Leached and Collapsed Member is characterized by bioturbated iron stained beds separated by massive limestone beds. This member is typically one of the most permeable and has extensive lateral development with large rooms. Overall thickness ranges from 70 to 90 feet thick

According to the site plan provided by Pape Dawson Engineers, the surveyed elevations on the project site range from 750 to 794 feet. According to this survey, the total relief on the project site is approximately 44 feet. A copy of the site plan indicating the boundary of the project site and the elevations is included on the Site Plan on Figure 1 in Appendix A and the Site Geologic Map included in the Attachments at the end of this report.

BEST MANAGEMENT PRACTICES

Based on a visual inspection of the ground surface, the overall potential for fluid flow from the project site into the Edwards Aquifer appears to range from low to moderate. The potential always exists to encounter solution cavities within the subsurface during excavating activities. Frost GeoSciences, Inc. is of the opinion that it is very important for construction personnel to be informed of the potential to encounter cavities in the subsurface that lack a surface expression. Construction personnel should also be informed of the proper protocol to follow in the event a karst feature is encountered during the development of the project site.

DISCLAIMER

This report has been prepared in general accordance with the "Instructions to Geologists", TCEQ-0585-Instructions (Rev. 10-1-04) by a Licensed Texas Professional Geoscientist. All areas of the project site were carefully inspected for features that could contribute to the recharge of the Edwards Aquifer; however, this survey cannot preclude the presence of subsurface karst features that lack surface expression. This report is not intended to be a definitive investigation of all possible geologic or karst features at this site. All conclusions, opinions, and recommendations for Best Management Practices (BMP's) in this report are based on information obtained while researching the project and on the site conditions at the time of our field investigation.

This report has been prepared for the exclusive use of Oakwood Baptist Church. This report is based on available known records, a visual inspection of the project site, and the work generally accepted for a Geologic Assessment for Regulated Activities / Developments on the Edwards Aquifer Recharge / Transition Zone, relating to 30 TAC §213.5(b)(3), effective June 1, 1999.

REFERENCES

1. USGS - 7.5 Minute Topographic Quadrangle of New Braunfels West, Texas, 1994

2. E.A.A. Edwards Aquifer Recharge Zone and Contributing Zone Map, New Braunfels West, Texas, 2014.

3. The Texas Commission on Environmental Quality (TCEQ) website: Edwards Aquifer Viewer – https://tceq.maps.arcgis.com/apps/webappviewer/index.html.

4. Clark, A.K., Golab, J.A. and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas, Science Investigations Map 3366, United States Geological Survey.

5. Clark, A.K., Golab, J.A. and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas, United States Geological Survey.

6. Collins, Edward, W., 2000, Geologic Map of the New Braunfels 30 X 60 Minute Quadrangle, Bureau of Economic Geology, The University of Texas at Austin, Texas.

7. Small, T.A. and Hanson, J.A., 1994, Geologic Framework and Hydrogeologic Characteristics of the Edwards Aquifer Outcrop, Comal County, Texas, U.S. Geological Survey Water Resources Investigations Report 94-4117.

8. Barnes, V.L., 1982, Geologic Atlas of Texas, San Antonio Sheet, Bureau of Economic Geology and University of Texas at Austin, Geologic Atlas of Texas.

9. Federal Emergency Management Agency, Federal Insurance Administration, National Flood Insurance Program, Flood Insurance Map, Community Panel Number 4891C0435F, dated September 2, 2009.

10. United States Department of Agriculture Soil Conservation Service Soil Survey of Comal County 1973.

11. USDA NRCS Web Soil Survey (WSS) website: https://websoilsurvey.nrcs.usda.gov (2014)

12. TCEQ-0585-Instructions (Rev. 10-1-04), "Instructions to Geologists for Geologic Assessments on the Edwards Aquifer Recharge/Transition Zone".

APPENDIX A

SITE LOCATION FIGURES

Frost GeoSciences



PROJECT NAME:
Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
New Braunfels, Texas

Site Layout

PROJECT NO.: FGS-E19135

DATE: March 25, 2019



PROJECT NAME: Geologic Site Assessment (WPAP) for Regulated Activities / Development on the Edwards Aquifer Recharge / Transition Zone Oakwood Baptist Church Tract New Braunfels, Texas	Street Map
	PROJECT NO.: FGS-E19135 / **DATE:** March 25, 2019



PROJECT NAME:

Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
New Braunfels, Texas

U.S.G.S. 7.5 Minute Quadrangle Map
New Braunfels West, Texas Sheet (1988)

PROJECT NO.:	DATE:
FGS-E19135	March 25, 2019



PROJECT NAME: Geologic Site Assessment (WPAP) for Regulated Activities / Development on the Edwards Aquifer Recharge / Transition Zone Oakwood Baptist Church Tract New Braunfels, Texas	Official Edwards Aquifer Recharge Zone Map New Braunfels West, Texas Sheet (1994)
PROJECT NO.: FGS-E19135	**DATE:** March 25, 2019



PROJECT NAME: Geologic Site Assessment (WPAP) for Regulated Activities / Development on the Edwards Aquifer Recharge / Transition Zone Oakwood Baptist Church Tract New Braunfels, Texas	Flood Insurance Rate Map (FIRM) Community Panel # 48091C0435F (Revised 9/02/09)
PROJECT NO.: FGS-E19135	**DATE:** March 25, 2019



PROJECT NAME:
Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
New Braunfels, Texas

1973 Aerial Photograph

United States Department of Agriculture

PROJECT NO.:	DATE:
FGS-E19135	March 25, 2019



PROJECT NAME:	U.S.Geological Survey Scientific Investigations Map 3366 2016	
Geologic Site Assessment (WPAP) for Regulated Activities / Development on the Edwards Aquifer Recharge / Transition Zone Oakwood Baptist Church Tract New Braunfels, Texas	PROJECT NO.: FGS-E19135	DATE: March 25, 2019



PROJECT NAME:	Bureau of Economic Geology Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle (2000)	
Geologic Site Assessment (WPAP) for Regulated Activities / Development on the Edwards Aquifer Recharge / Transition Zone Oakwood Baptist Church Tract New Braunfels, Texas	PROJECT NO.: FGS-E19135	DATE: March 25, 2019



PROJECT NAME:
Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
New Braunfels, Texas

2018 Aerial Photograph
Google Earth

PROJECT NO.:	DATE:
FGS-E19135	March 25, 2019



PROJECT NAME:
Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
Oakwood Baptist Church Tract
New Braunfels, Texas

2018 Aerial Photograph with PRF's
Google Earth

PROJECT NO.: FGS-E19135

DATE: March 25, 2019

APPENDIX B

SITE PHOTOGRAPHS



Photo #1 – View of the parking area associated with Oakwood Baptist Church.



Photo #2 – View of the structural improvements comprising Oakwood Baptist Church.

Photo #3 – View of the eastern end of PRF #S-1.



Photo #4 – Additional view of PRF #S-1.

FGS Project Nº FGS-E19135



Photo #5 – View to the west across the western portion of PRF #S-1.

Photo #6 – View to the east across the western portion of PRF #S-1.

Photo #7 – View of PRF #S-2.

Photo #8 – View to the west across the northern portion of the project site from PRF #S-2.



Photo #9 – View to the south across the north-central portion of the project site.

Photo #10 – View of PRF #S-3.

Photo #11 – View to the southeast across the western portion of the project site.

Photo #12 – View to the east across the northwestern portion of the project site.

Photo #13 – View of PRF #S-4.

Photo #14 – View of PRF #S-5.

Photo #15 – View of PRF #S-6.

Photo #16 – View of PRF #S-7.



Photo #17 – View of PRF #S-8.

Photo #18 – View of the electrical box adjacent the PRF #S-8.

Photo #19 – View of PRF #S-9.

Photo #20 – View of PRF #S-10.

Photo #21 – View of PRF #S-11.

Photo #22 – View of the general vicinity near PRF #S-11.

Photo #23 – View of PRF #S-12.



Photo #24 – View of the general vicinity near PRF #S-12.



Photo #25 – View of PRF #S-13.

Photo #26 – View of the general vicinity near PRF #S-13.

ATTACHMENTS

GEOLOGIC FORM TCEQ 0585

STRATIGRAPHIC COLUMN

GEOLOGIC ASSESSMENT TABLE

SITE GEOLOGIC MAP

FGS Project Nº FGS-E19135

ATTACHMENT A

GEOLOGIC FORM TCEQ 0585

FGS Project Nº FGS-E19135

Geologic Assessment

Texas Commission on Environmental Quality

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Chris Wickman Telephone: (210) 372-1315

Date: March 25, 2019 Fax: (210) 372-1518

Representing: Frost GeoSciences, Inc. Registration Number 50040 (Name of Company and TBPG or TBPE registration number)

Signature of Geologist:



Regulated Entity Name: Oakwood Baptist Church

Project Information

1. Date(s) Geologic Assessment was performed: March 21, 2019
2. Type of Project:
   - ☒ WPAP
   - ☐ SCS
   - ☐ AST
   - ☐ UST
3. Location of Project:
   - ☒ Recharge Zone
   - ☐ Transition Zone
   - ☐ Contributing Zone within the Transition Zone

4. ☒ **Attachment A - Geologic Assessment Table.** Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.

5. ☒ Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

Soil Name	Group*	Thickness(feet)
Rumple	C	0-2
Comfort	D	0-2

** Soil Group Definitions (Abbreviated)*

A. Soils having a high infiltration rate when thoroughly wetted.

B. Soils having a moderate infiltration rate when thoroughly wetted.

C. Soils having a slow infiltration rate when thoroughly wetted.

D. Soils having a very slow infiltration rate when thoroughly wetted.

6. ☒ **Attachment B – Stratigraphic Column.** A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.

7. ☒ **Attachment C – Site Geology**. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.

8. ☒ **Attachment D – Site Geologic Map(s).** The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

   Applicant's Site Plan Scale: 1" = 100'
   Site Geologic Map Scale: 1" = 100'
   Site Soils Map Scale (if more than 1 soil type): 1" = 500'

9. Method of collecting positional data:

   ☒ Global Positioning System (GPS) technology.
   ☒ Other method(s). Please describe method of data collection: 2018 Aerial Photograph

10. ☒ The project site and boundaries are clearly shown and labeled on the Site Geologic Map.

11. ☒ Surface geologic units are shown and labeled on the Site Geologic Map.

12. ☒ Geologic or manmade features were discovered on the project site during the field investigation. They are shown and labeled on the Site Geologic Map and are described in the attached Geologic Assessment Table.

    ☐ Geologic or manmade features were not discovered on the project site during the field investigation.

13. ☒ The Recharge Zone boundary is shown and labeled, if appropriate.

14. All known wells (test holes, water, oil, unplugged, capped and/or abandoned, etc.): If applicable, the information must agree with Item No. 20 of the WPAP Application Section.

    ☐ There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply.)
    - ☐ The wells are not in use and have been properly abandoned.
    - ☐ The wells are not in use and will be properly abandoned.
    - ☐ The wells are in use and comply with 16 TAC Chapter 76.

    ☒ There are no wells or test holes of any kind known to exist on the project site.

Administrative Information

15. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT B

STRATIGRAPHIC COLUMN

FGS Project Nº FGS-E19135

STRATIGRAPHIC COLUMN

EXPLANATION OF HYDROSTRATIGRAPHIC UNITS

Group or Formation	Formal and informal member		Hydrologic unit or Informal hydrostratigraphic unit
Taylor Group (Pecan Gap)		Kpg	Upper Confining Unit (UCU)
Austin Group		Ka	
Eagle Ford Group		Kef	
Buda Limestone		Kb	
Del Rio Clay		Kdr	
Georgetown Formation		Kg	I
Person Formation	Cyclic and marine, undivided	Kpcm	II
	Leached and collapsed	Kplc	III
	Regional dense member	Kprd	IV
Kainer Formation	Grainstone	Kkg	V
	Kirschberg evaporite	Kkke	VI
	Dolomitic	Kkd	VII
	Basal nodular	Kkbn	VIII
Glen Rose Limestone	Upper Glen Rose Limestone	Kgrc	Cavernous
		Kgrcb	Camp Bullis
		Kgrue	Upper evaporite
		Kgrut	Fossiliferous Upper
		Kgrlf	Lower
		Kgrle	Lower evaporite
	Lower Glen Rose Limestone	Kgrb	Bulverde
		Kgrdb	Little Blanco
		Kgrts	Twin Sisters
		Kgrd	Doeppenschmidt
		Kgrr	Rust
		Kgrhc	Honey Creek
Pearsall Formation	Hensell Sand	Khch	Hensell
	Cow Creek Limestone	Kcccc	Cow Creek
	Hammett Shale	Khah	Hammett

Kgrf

FGS Project Nº FGS-E19135

ATTACHMENT C

GEOLOGIC ASSESSMENT TABLE

FGS Project Nº FGS-E19135

Frost GeoSciences

GEOLOGIC ASSESSMENT TABLE

PROJECT NAME: Oakwood Baptist Church Tract | **PROJECT NUMBER: FGS-E19135**

LOCATION			FEATURE CHARACTERISTICS											EVALUATION			PHYSICAL SETTING		
1A	1B *	1C*	2A	2B	3	4			5	5A	6	7	8A	8B	9	10		11	12
FEATURE ID	LATITUDE	LONGITUDE	FEATURE TYPE	POINTS	FORMATION	DIMENSIONS (FEET)			TREND (DEGREES)	DOM	DENSITY (NO/FT)	APERTURE (FEET)	INFILL	RELATIVE INFILTRATION RATE	TOTAL	SENSITIVITY		CATCHMENT AREA (ACRES)	TOPOGRAPHY
						X	Y	Z		10						<40	>40	<1.6	>1.6	
S-1	29° 43' 42.42"	-98° 8' 26.09"	MB	30	Kplc	130	530	7-10	-	-	-	-	CFO	5	35	35		YES		HILLSIDE
S-2	29° 43' 42.85"	-98° 8' 25.91"	MB	30	Kplc	30	140	5-7	-	-	-	-	CFO	5	35	35		YES		HILLSIDE
S-3	29° 43' 37.96"	-98° 8' 35.77"	MB	30	Kplc	60	150	5	-	-	-	-	CFO	5	35	35		YES		HILLSIDE
S-4	29° 43' 41.30"	-98° 8' 29.04"	MB	30	Kplc	4	4	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-5	29° 43' 40.19"	-98° 8' 27.74"	MB	30	Kplc	4	4	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-6	29° 43' 40.08"	-98° 8' 26.63"	MB	30	Kplc	3	3	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-7	29° 43' 40.48"	-98° 8' 25.01"	MB	30	Kplc	4	4	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-8	29° 43' 40.22"	-98° 8' 24.83"	MB	30	Kplc	5	5	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-9	29° 43' 40.73"	-98° 8' 29.94"	MB	30	Kplc	3	3	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-10	29° 43' 40.01"	-98° 8' 30.62"	MB	30	Kplc	3	3	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-11	29° 43' 38.39"	-98° 8' 33.86"	MB	30	Kplc	3	3	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-12	29° 43' 36.77"	-98° 8' 32.86"	MB	30	Kplc	3	3	?	-	-	-	-	X	5	35	35		YES		HILLSIDE
S-13	29° 43' 35.26"	-98° 8' 28"	MB	30	Kplc	5	6	?	-	-	-	-	CFO	5	35	35		YES		HILLSIDE

Datum: NAD 83

2A TYPE	TYPE	2B POINTS
C	Cave	30
SC	Solution cavity	20
SF	Solution-enlarged fracture(s)	20
F	Fault	20
O	Other natural bedrock features	5
MB	Manmade feature in bedrock	30
SW	Swallow hole	30
SH	Sinkhole	20
CD	Non-karst closed depression	5
Z	Zone, clustered or aligned features	30

8A INFILLING	
N	None, exposed bedrock
C	Coarse - cobbles, breakdown, sand, gravel
O	Loose or soft mud or soil, organics, leaves, sticks, dark colors
F	Fines, compacted clay-rich sediment, soil profile, gray or red colors
V	Vegetation. Give details in narrative description
FS	Flowstone, cements, cave deposits
X	Other materials

12 TOPOGRAPHY
Cliff, Hilltop, Hillside, Floodplain, Streambed

STATE OF TEXAS
Christopher Wickman
Geology
10403
LICENSED PROFESSIONAL GEOSCIENTIST

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists.
The information presented here complies with that document and is a true representation of the conditions observed in the field.
My signature certifies that I am qualified as a geologist as defined by 30 TAC 213.

Chris Wickman, P.G.

Date: March 25, 2019

TCEQ-0585-Table (Rev. 10-01-04)

Sheet 1 of 1

FGS Project Nº FGS-E19135

ATTACHMENT D

Location Map



Signature of Texas Licensed Geoscientist
Chris Wickman License No. 10403

Frost GeoSciences
Geotechnical ▪ Construction Materials
Geologic ▪ Environmental
13406 Western Oak ▪ Helotes, Texas 78023
Phone: (210) 372-1315 ▪ Fax: (210) 372-1318

Site Geologic Map

Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
for the

Oakwood Baptist Church
+/- 39 Acres
New Braunfels, Texas

Frost GeoSciences, Inc. Control # FGS-19135

Kpcm - Edwards Person Limestone Cylic Marine Member
Kplc - Edwards Person Limestone Leached and Collapesed Member

S-# - Potential Recharge Feature (PRF)
- Edwards Person Limestone Contact Boundary

Floodplain Information Obtained From FIRM: Flood Insurance Rate Map
Comal County, Texas: Panel # 48091C0435F Revised 9/2/2009

Fault Information Obtained From:
Bureau of Economic Geology, Geologic Atlas of Texas, San Antonio Sheet (1983)
U.S. Geological Survey, Water Resources Investigations Report 94-4117 (1994)
Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle (2000)
U.S. Geological Survey Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas (2016)

Graphic Scale

100 0 50 100 200

(In Feet)

1 inch = 100 feet
Representative Fraction 1:1200

Contour Interval - 2 foot

Location Map



Signature of Texas Licensed Geoscientist
Chris Wickman License No. 10403

Frost GeoSciences
Geotechnical • Construction Materials
Geologic • Environmental
13406 Western Oak • Helotes, Texas 78023
Phone: (210) 372-1315 • Fax: (210) 372-1318

Site Geologic Map

Geologic Site Assessment (WPAP)
for Regulated Activities / Development on the
Edwards Aquifer Recharge / Transition Zone
for the

Oakwood Baptist Church
+/- 39 Acres
New Braunfels, Texas

Frost GeoSciences, Inc. Control # FGS-19135

Kpcm - Edwards Person Limestone Cylic Marine Member
Kplc - Edwards Person Limestone Leached and Collapesed Member

S-# - Potential Recharge Feature (PRF)
- - - - - Edwards Person Limestone Contact Boundary

Floodplain Information Obtained From FIRM: Flood Insurance Rate Map
Comal County, Texas: Panel # 48091C0435F Revised 9/2/2009

Fault Information Obtained From:
Bureau of Economic Geology, Geologic Atlas of Texas, San Antonio Sheet (1983)
U.S. Geological Survey, Water Resources Investigations Report 94-4117 (1994)
Geologic Map of the New Braunfels, Texas 30 X 60 Minute Quadrangle (2000)
U.S. Geological Survey Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers within Northern Bexar and Comal Counties, Texas (2016)

Graphic Scale

100 0 50 100 200

In Feet

1 inch = 100 feet
Representative Fraction 1:1200

Contour Interval - 2 foot

MODIFICATION OF A PREVIOUSLY APPROVED SEWAGE COLLECTION SYSTEM PLAN (TCEQ-0590)

Modification of a Previously Approved Plan

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Transition Zone and Relating to 30 TAC 213.4(j), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This request for a **Modification of a Previously Approved Plan** is hereby submitted for TCEQ review and executive director approval. The request was prepared by:

Print Name of Customer/Agent: Caleb Chance, P.E.

Date: 10/15/2024

Signature of Customer/Agent:



Project Information

1. Current Regulated Entity Name: Oakwood Baptist Church
   Original Regulated Entity Name: Oakwood Baptist Church
   Regulated Entity Number(s) (RN): 102744802
   Edwards Aquifer Protection Program ID Number(s): 1085.03
   ☒ The applicant has not changed and the Customer Number (CN) is: 601399199
   ☐ The applicant or Regulated Entity has changed. A new Core Data Form has been provided.

2. ☒ **Attachment A: Original Approval Letter and Approved Modification Letters**. A copy of the original approval letter and copies of any modification approval letters are attached.

3. A modification of a previously approved plan is requested for (check all that apply):
   - ☐ Physical or operational modification of any water pollution abatement structure(s) including but not limited to ponds, dams, berms, sewage treatment plants, and diversionary structures;
   - ☐ Change in the nature or character of the regulated activity from that which was originally approved or a change which would significantly impact the ability of the plan to prevent pollution of the Edwards Aquifer;
   - ☐ Development of land previously identified as undeveloped in the original water pollution abatement plan;
   - ☒ Physical modification of the approved organized sewage collection system;
   - ☐ Physical modification of the approved underground storage tank system;
   - ☐ Physical modification of the approved aboveground storage tank system.

4. ☒ Summary of Proposed Modifications (select plan type being modified). If the approved plan has been modified more than once, copy the appropriate table below, as necessary, and complete the information for each additional modification.

WPAP Modification Summary	***Approved Project***	***Proposed Modification***
Acres	_____	_____
Type of Development	_____	_____
Number of Residential Lots	_____	_____
Impervious Cover (acres)	_____	_____
Impervious Cover (%	_____	_____
Permanent BMPs	_____	_____
Other	_____	_____

SCS Modification Summary	***Approved Project***	***Proposed Modification***
Linear Feet	1,062 LF/40 LF	1,159 LF
Pipe Diameter	8-in Gravity/8-in Pressure	8-inch Gravity Sewer
Other	1,160 LF /6-in Pressure	_____

AST Modification Summary	***Approved Project***	***Proposed Modification***
Number of ASTs	_____	_____
Volume of ASTs	_____	_____
Other	_____	_____

UST Modification Summary	***Approved Project***	***Proposed Modification***
Number of USTs	_____	_____
Volume of USTs	_____	_____
Other	_____	_____

5. ☒ **Attachment B: Narrative of Proposed Modification**. A detailed narrative description of the nature of the proposed modification is attached. It discusses what was approved, including any previous modifications, and how this proposed modification will change the approved plan.

6. ☒ **Attachment C: Current Site Plan of the Approved Project**. A current site plan showing the existing site development (i.e., current site layout) at the time this application for modification is attached. A site plan detailing the changes proposed in the submitted modification is required elsewhere.
   - ☐ The approved construction has not commenced. The original approval letter and any subsequent modification approval letters are included as Attachment A to document that the approval has not expired.
   - ☒ The approved construction has commenced and has been completed. Attachment C illustrates that the site was constructed as approved.
   - ☐ The approved construction has commenced and has been completed. Attachment C illustrates that the site was **not** constructed as approved.
   - ☐ The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was constructed as approved.
   - ☐ The approved construction has commenced and has **not** been completed. Attachment C illustrates that, thus far, the site was **not** constructed as approved.

7. ☐ The acreage of the approved plan has increased. A Geologic Assessment has been provided for the new acreage.
   ☒ Acreage has not been added to or removed from the approved plan.

8. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

ATTACHMENT A

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

February 6, 2012

Ms. Roxi Vanstory
Oakwood Baptist Church
2154 Loop 337
New Braunfels, TX 78130

Re: Edwards Aquifer, Comal County

Name of Plan: Oakwood Baptist Church Sewer Line & Force Main; Located at 2154 Loop 337; New Braunfels, Texas

Type of Plan: Request for Approval of an Organized Sewage Collection System (SCS) Plan; 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program San Antonio File No. 1085.03; Investigation No. 970279; Regulated Entity No. RN102744802

Dear Ms. Vanstory:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the organized sewage collection system plans and specifications for the referenced project submitted to the San Antonio Regional Office on behalf of Oakwood Baptist Church by The Schultz Group, Inc. on November 17, 2011. Final review of the SCS was completed after additional material was received on January 10, 2012, January 22, 2012, and January 30, 2012. As presented to the TCEQ, the construction documents were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213 and Chapter 217. Therefore, based on the Texas Licensed Professional Engineer's concurrence of compliance, the planning materials for construction of the proposed sewage collection system and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer protection plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. *This approval expires (2) two years from the date of this letter unless, prior to the expiration date, more than 10 percent of construction has commenced, or an extension of time has been requested.*

Project Description

The proposed sewage collection system consists of 1,062 linear feet of 8-inch diameter SDR 26 PVC pipe (ASTM D3034), 40 linear feet of 8-inch SDR 26 PVC pipe (ASTM D2241), 1,160 linear feet of 6-inch diameter SDR 26, 160-psi pressure rated force main pipe (ASTM D2241), 5 manholes, and appropriate appurtenances. The proposed sewage collection system will provide

disposal service for the expansion of the existing Oakwood Baptist Church Campus to include a proposed multi-story youth center and the future addition of a sanctuary.

The proposed lift station consists of a six-foot diameter precast wet well with an approximate depth of 13 feet, two Smith & Loveless, Inc., 7.5 Hp, 1,170 RPM, Model 4B3B pumps , and one portable emergency power generator. Each pump will have a pumping capacity of 280 gallons per minute (gpm) at a total dynamic head (TDH) of 40.5 feet. Additional equipment will include a control panel, an audio visual alarm, auto-dial telemetry, hoisting equipment, level pump controllers, pump supports and discharge piping with valves, and a security fence with controlled access.

The system will be connected to an existing City of New Braunfels wastewater line for conveyance to the Gruene Road Sewage Treatment Plant for treatment and disposal. The project is located within the City of New Braunfels and will conform to all applicable codes, ordinances, and requirements of the City of New Braunfels.

Geology

According to the geologic assessment included with the application, the site consists of the Rumple-Comfort Association (RUD) and the Comfort-Rock Outcrop Complex (CrD). Portions of the proposed sewer line and force main will be located under an existing asphalt parking lot. The geologic assessment indicates that no features were identified on the site within 50 feet of the SCS. A site investigation was conducted by a representative of the San Antonio Regional Office on January 17, 2012 to document the conditions at the site and revealed that the site was adequately described by the geologic assessment.

Special Conditions

1. It is emphasized that where wastewater lines must bridge faults, caverns, sinkholes, or solution features the lines shall be constructed in a manner that will maintain the structural integrity of the pipe. When such sensitive feature area is encountered, 30 TAC §213.5(f)(2) requires that all regulated activities near the feature must be immediately suspended and the owner/developer shall immediately notify the San Antonio Regional Office. Additionally, when such geologic features are encountered which are bridged by construction, the location and extent of those features must be assessed by a geologist and must be reported to the San Antonio Regional Office in writing within two working days of discovery as required by 30 TAC §213.5(c)(3)(K). Construction may not resume in the area of the feature until the executive director has reviewed and approved the methods proposed to protect the aquifer from any potential adverse impacts. See Standard Condition 10 below.

2. The lift station shall be designed and constructed to help ensure that bypassing of any sewage does not occur. All lift stations must be designed to meet the requirements of 30 TAC §217.63.

3. Upon completion of any lift station excavation, a geologist shall certify that the excavation has been inspected for the presence of sensitive features. Certification that the excavation has been inspected must be submitted to the San Antonio Regional Office.

4. Owner shall have an operator that is knowledgeable in operation of the portable generators and pumps and the operator shall be on call 24 hours per day every day.

Standard Conditions

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.

2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.

3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

Prior to Commencement of Construction:

4. All contractors conducting regulated activities at the project location shall be provided a copy of this notice of approval. At least one complete copy of the approved SCS plan and this notice of approval shall be maintained at the project location until all regulated activities are completed.

5. Modification to the activities described in the referenced SCS and lift station applications following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.

6. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person. The executive director will use the notification to determine if the approved plan is eligible for an extension.

7. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved application, must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

8. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213 and Chapter 217. The applicant shall remain responsible for the provisions and conditions of this approval until

such responsibility is legally transferred to another person or entity, upon which that person or entity shall assume responsibility for all provisions and conditions of this approval.

9. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.

10. If any sensitive feature (caves, solution cavities, sink holes, etc.) is discovered during construction, all regulated activities near the feature must be suspended immediately. The applicant or his agent must immediately notify the San Antonio Regional Office of the discovery of the feature. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality. The plan must be sealed, signed, and dated by a Texas Licensed Professional Engineer.

11. The following records shall be maintained by the applicant and made available to the executive director upon request: the dates trenching activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated and completed.

12. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

13. Intentional discharges of sediment laden stormwater during construction are not allowed. If dewatering of excavated areas becomes necessary, the discharge will be filtered through appropriately selected temporary best management practices. These may include vegetative filter strips, sediment traps, rock berms, sit fence rings, etc.

14. No part of the system shall be used as a holding tank for a pump-and-haul operation.

After Completion of Construction:

15. Certification by a Texas Licensed Professional Engineer of the testing of sewage collection systems required by 30 TAC Chapter 213 and Chapter 217 shall be submitted to the San Antonio Regional Office within 30 days of test completion and prior to the new sewage collection system being put into service. The certification should include the project name as it appeared on the approved application, the program ID number, and two copies of a site plan sheet(s) indicating the wastewater lines that were tested and are being certified as complying with the appropriate regulations.

16. Every five years after the initial certification, the sewage collection system shall be retested. Any lines that fail the test must be repaired and retested. Certification that the system continues to meet the requirements of 30 TAC Chapter 213 and Chapter 217 shall be submitted to the San Antonio Regional Office. The certification should include the project name as it appeared on the approved application, the program ID number and two copies of

a site plan sheet(s) indicating the wastewater lines that were tested and are being certified as complying with the appropriate regulations.

17. If ownership of this organized sewage collection system is legally transferred (e.g., developer to city or Municipal Utility District), the new owner(s) is required to comply with all terms of the approved Edwards Aquifer protection plan. If the new owner intends to commence any new regulated activity on the site, a new Edwards Aquifer protection plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.

18. An Edwards Aquifer protection plan approval or extension will expire and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Edwards Aquifer protection plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.

If you have any questions or require additional information, please contact Mr. Lianxiang Du of the Edwards Aquifer Protection Program of the San Antonio Regional Office at (210) 403-4057.

Sincerely,

for

Mark R. Vickery, P.G., Executive Director
Texas Commission on Environmental Quality

MRV/LD/eg

cc: Mr. Michael G. Short, P.E., the Schultz Group, Inc.
Mr. James C. Klein, P.E., City Engineer, City of New Braunfels
Mr. Tom Hornseth, P.E., Comal County
Mr. Karl Dreher, General Manager, Edwards Aquifer Authority
TCEQ Central Records, Building F, MC 212

ATTACHMENT B

OAKWOOD BAPTIST CHURCH EXPANSION
Sewage Collection System Modification Plan

Attachment B – Narrative of Proposed Modification

The Oakwood Baptist Sewage Collection System (SCS) was approved by the Texas Commission on Environmental Quality on February 6, 2012, for construction of a total of 2262 linear feet (LF) of sewer main to serve the church. The alignment approved 1062 LF of 8-inch (8") PVC, SDR 26 gravity sewer main, 40 LF of 8-inch (8") PVC, SDR 26, 1160 LF of 6-inch (6”) PVC, SDR 26, 160-psi pressure-rated sewer main centered at water line crossings. This proposed SCS Modification will remove 2 existing onsite lift stations and add approximately 1159 linear feet (LF) of 8-inch (8”) polyvinyl chloride (PVC), SDR 26 gravity sewer main to provide a gravity solution for the entire Oakwood Baptist Church Campus.

This project will result in an estimated additional 26 Living Unit Equivalent (LUEs). This is based on the additional seating capacity of 1,833 from the proposed Worship Center. Approximately 21,000 gallons per day (average daily dry weather flow) of domestic wastewater are estimated to be generated by this project which includes the existing flow as well. The proposed sanitary sewer main will tie into an existing manhole.

The sewage flow will be disposed of by conveyance to the existing Gruene Road Sewage Treatment Plant Water Recycling Center operated by the New Braunfels Utility (NBU). Potable water will be supplied by NBU. Refer to included EDR and SCS application for additional details.

ATTACHMENT C



WATER/WASTEWATER CONSTRUCTION NOTES:

1. SEE MECHANICAL/PLUMBING FOR CONTINUATION.
2. INSTALL 3" TEE, 3" VALVE, VALVE BOX AND 3" SERVICE LINE
3. INSTALL 2-3"x2" REDUCERS, 2" METER AND METER BOX PER NBU STD. DWG. 203 AND 3" SERVICE LINE
4. INSTALL 3" REDUCED PRESSURE ASSEMBLY FEBCO 860 OR EQUIVALENT AND 3" SERVICE LINE
5. CONTRACTOR TO VERIFY HORIZONTAL AND VERTICAL LOCATION OF EXISTING UTILITY PRIOR TO CONSTRUCTION
6. INSTALL 8"x6'" TEE, 6" GATE VALVE, VALVE BOX AND CAP FOR FUTURE FIRE HYDRANT
7. INSTALL 8"x6" TEE, 6" GATE VALVE, VALVE BOX AND FIRE HYDRANT ASSEMBLY
8. CUT AND CAP EXISTING
9. CUT AND TIE TO EXISTING
10. REFER TO WATER SEWER CROSSING DETAIL ENSURE SEPARATION REQUIREMENTS ARE MET PER UTILITY NOTES AND DETAILS
11. EXISTING LINE TO BE REMOVED AS REQUIRED OR ABANDON IN PLACE
12. 2 ~ 2" SCH 40 PVC UTILITY SLEEVES
13. RESTORE PAVEMENT CUT PER NBU STD. DWG. 430
14. WATER LINE PIPE WITHIN AREA INDICATED SHALL HAVE A MINIMUM 8-FT OF COVER FROM EXISTING FOR FUTURE GRADE ADJUSTMENTS

LEGEND

- PROPERTY LINE
- EXISTING WASTEWATER LINE
- EXISTING WATER LINE
- EXISTING GAS LINE
- EXISTING FIRE HYDRANT
- EXISTING GATE VALVE
- EXISTING WATER METER
- EXISTING SEWER MANHOLE
- PROPOSED WATER LINE
- PROPOSED WATER METER
- PROPOSED BLOW OFF
- PROPOSED SEWER CLEANOUT
- PROPOSED SEWER SERVICE LATERAL

POINT TABLE			
POINT NUMBER	NORTHING	EASTING	DESCRIPTION
7175	13814927.99	2240888.24	MH
7176	13815096.57	2241172.84	MH
7177	13815165.29	2241244.90	MH
7178	13815178.33	2241526.90	MH
7179	13815110.96	2241669.29	MH
7180	13814358.09	2241166.87	F.M.
7189	13814977.69	2241776.97	F.M.
7190	13814683.90	2241743.88	F.M.
7191	13814509.17	2241331.91	F.M.
7192	13814482.40	2241320.85	F.M.
7193	13814396.10	2241184.48	F.M.
7194	13815126.10	2241276.23	C.O.
7195	13815015.47	2241076.54	C.O.

UTILITY NOTES:

CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING NEAR FIBER OPTIC CABLE AND GAS FACILITIES AND UNDERGROUND LINES.

SURFACE FEATURES OF UTILITIES WERE IDENTIFIED WITHIN THIS REFERENCE SITE, NO UNDERGROUND UTILITIES WERE LOCATED. UNLESS SPECIFIED BY NEW BRAUNFELS UTILITIES (NBU) OR TEXAS ONE-CALL/DIG-TESS LOCATE

UTILITY LOCATE REQUESTED ON MARCH 15, 2011, GEOCALL LOCATE TICKET NUMBER INFORMATION-110750075.

LEVEL 3 COMMUNICATIONS
TIME WARNER CABLE
NEW BRAUNFELS UTILITIES (ELECTRIC ONLY)
NEW BRAUNFELS UTILITIES
TXSW - ATT/D

REVISIONS

DATE	DESCRIPTION

UTILITY PLAN FOR OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS

THE Schultz Group, INC.
TEXAS REGISTERED ENGINEERING FIRM F-532
TEXAS LICENSED SURVEYING FIRM 100059-00
CONSULTING ENGINEERS & LAND SURVEYORS
2461 LOOP 337 NEW BRAUNFELS, TEXAS 78130
PHONE (830) 606-3913 FAX (830) 625-2204

DRAWN BY: D.C.
CHECKED BY: M.G.S.
DATE: DECEMBER 2010
JOB NO.: 100410

C11

ORGANIZED SEWAGE COLLECTION SYSTEM PLAN (TCEQ-0582)

Organized Sewage Collection System Application

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Oakwood Baptist Church

1. ☒ **Attachment A – SCS Engineering Design Report**. This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

Customer Information

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

   Contact Person: Roxi Vanstory.
   Entity: Oakwood Baptist Church
   Mailing Address: 2154 Loop 337
   City, State: New Braunfels, Texas Zip: 78130
   Telephone: (830) 625 -0267 Fax: 830) 625-1151
   Email Address: roxi.vanstory@oakwoodnb.com
   The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

   Contact Person: Caleb Chance, P.E.
   Texas Licensed Professional Engineer's Number: 98401
   Entity: Pape-Dawson Engineers, Inc.
   Mailing Address: 2000 NW Loop 410
   City, State:2000 NW Loop 410 Zip: 78213
   Telephone:(210) 375-9000 Fax:(210) 375-9010
   Email Address:cchance@pape-dawson.com

Project Information

4. Anticipated type of development to be served (estimated future population to be served, plus adequate allowance for institutional and commercial flows):

   ☐ Residential: Number of single-family lots: _____
   ☐ Multi-family: Number of residential units: _____
   ☐ Commercial
   ☐ Industrial
   ☐ Off-site system (not associated with any development)
   ☒ Other: Church

5. The character and volume of wastewater is shown below:

100% Domestic	21,000 gallons/day
_____% Industrial	_____ gallons/day
_____% Commingled	_____ gallons/day

   Total gallons/day: 21,000

6. Existing and anticipated infiltration/inflow is 21,000 gallons/day. This will be addressed by: adequate sizing of sewer main.

7. A Water Pollution Abatement Plan (WPAP) is required for construction of any associated commercial, industrial or residential project located on the Recharge Zone.

   ☒ The WPAP application for this development was approved by letter dated August 30, 2024. A copy of the approval letter is attached.
   ☐ The WPAP application for this development was submitted to the TCEQ on _____, but has not been approved.
   ☐ A WPAP application is required for an associated project, but it has not been submitted.
   ☐ There is no associated project requiring a WPAP application.

8. Pipe description:

Table 1 - Pipe Description

Pipe Diameter(Inches)	*Linear Feet (1)*	*Pipe Material (2)*	*Specifications (3)*
8	1159	SDR 26	ASTM D3034

Total Linear Feet: 1159

(1) Linear feet - Include stub-outs and double service connections. Do not include private service laterals.
(2) Pipe Material - If PVC, state SDR value.
(3) Specifications - ASTM / ANSI / AWWA specification and class numbers should be included.

9. The sewage collection system will convey the wastewater to the Gruene Road Sewage (name) Treatment Plant. The treatment facility is:

   ☒ Existing
   ☐ Proposed

10. All components of this sewage collection system will comply with:

   ☒ The City of New Braunfels standard specifications.
   ☐ Other. Specifications are attached.

11. ☒ No force main(s) and/or lift station(s) are associated with this sewage collection system.

   ☐ A force main(s) and/or lift station(s) is associated with this sewage collection system and the **Lift Station/Force Main System Application** form (TCEQ-0624) is included with this application.

Alignment

12. ☒ There are no deviations from uniform grade in this sewage collection system without manholes and with open cut construction.

13. ☒ There are no deviations from straight alignment in this sewage collection system without manholes.

   ☐ **Attachment B - Justification and Calculations for Deviation in Straight Alignment without Manholes**. A justification for deviations from straight alignment in this sewage collection system without manholes with documentation from pipe manufacturer allowing pipe curvature is attached.

   ☐ For curved sewer lines, all curved sewer line notes (TCEQ-0596) are included on the construction plans for the wastewater collection system.

Manholes and Cleanouts

14. ☒ Manholes or clean-outs exist at the end of each sewer line(s). These locations are listed below: (Please attach additional sheet if necessary)

Table 2 - Manholes and Cleanouts

Line	*Shown on Sheet*	*Station*	*Manhole or Clean-out?*
A	C1.20 Of	1+20.57	Manhole Existing
A	C1.20 Of	2+52.66	Manhole A-1
A	C1.20 Of	4+68.85	Manhole A-3
A	C1.20 Of	6+56.05	Manhole A-4
A	C1.20 Of	7+88.36	Manhole A-6
A	C1.20 Of	9+83.42	Manhole A-7
A	C1.20 Of	11+31.62	Manhole A-8

Line	*Shown on Sheet*	*Station*	*Manhole or Clean-out?*
A	C1.20 Of	12+79.30	Manhole A-9
	Of		
	Of		

15. ☐ Manholes are installed at all Points of Curvature and Points of Termination of a sewer line.

16. ☒ The maximum spacing between manholes on this project for each pipe diameter is no greater than:

Pipe Diameter (inches)	Max. Manhole Spacing (feet)
6 - 15	500
16 - 30	800
36 - 48	1000
≥54	2000

☐ **Attachment C – Justification for Variance from Maximum Manhole Spacing**. The maximum spacing between manholes on this project (for each pipe diameter used) is greater than listed in the table above. A justification for any variance from the maximum spacing is attached, and must include a letter from the entity which will operate and maintain the system stating that it has the capability to maintain lines with manhole spacing greater than the allowed spacing.

17. ☐ All manholes will be monolithic, cast-in-place concrete.

☐ The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

Site Plan Requirements

Items 18 - 25 must be included on the Site Plan.

18. ☒ The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = 50'.

19. ☒ The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.

20. Lateral stub-outs:

☐ The location of all lateral stub-outs are shown and labeled.
☒ No lateral stub-outs will be installed during the construction of this sewer collection system.

21. Location of existing and proposed water lines:

☐ The entire water distribution system for this project is shown and labeled.
☒ If not shown on the Site Plan, a Utility Plan is provided showing the entire water and sewer systems.
☐ There will be no water lines associated with this project.

22. 100-year floodplain:

☒ After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)
☐ After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 3 - 100-Year Floodplain

Line	*Sheet*	*Station*
	of	to
	of	to
	of	to
	of	to

23. 5-year floodplain:

☐ After construction is complete, no part of this project will be in or cross a 5-year floodplain, either naturally occurring or man-made. (Do not include streets or concrete-lined channels constructed above sewer lines.)
☐ After construction is complete, all sections located within the 5-year floodplain will be encased in concrete or capped with concrete. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.)

Table 4 - 5-Year Floodplain

Line	*Sheet*	*Station*
	of	to
	of	to
	of	to
	of	to

24. ☐ Legal boundaries of the site are shown.

25. ☐ The ***final plans and technical specifications*** are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

Items 26 - 33 must be included on the Plan and Profile sheets.

26. ☒ All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.

☐ There will be no water line crossings.
☒ There will be no water lines within 9 feet of proposed sewer lines.

Table 5 - Water Line Crossings

Line	*Station or Closest Point*	*Crossing or Parallel*	*Horizontal Separation Distance*	*Vertical Separation Distance*
A	4+47.96	Crossing		3.7'
A	5+11.54	Crossing		5.6'
A	5+16.53	Crossing		5.3'
A	9+64.33	Crossing		2.3'
A	11+12.93	Crossing		2.3'

27. Vented Manholes:

☒ **No part** of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.
☐ **A portion** of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.
☐ **A portion** of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.
☐ **A portion** of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.

Table 6 - Vented Manholes

Line	*Manhole*	*Station*	*Sheet*

Line	*Manhole*	*Station*	*Sheet*

28. Drop manholes:

☐ There are no drop manholes associated with this project.
☒ Sewer lines which enter new or existing manholes or "manhole structures" higher than 24 inches above the manhole invert are listed in the table below and labeled on the appropriate profile sheets. These lines meet the requirements of 30 TAC §217.55(l)(2)(H).

Table 7 - Drop Manholes

Line	*Manhole*	*Station*	*Sheet*
A	A-3	4+68.85	C1.20

29. Sewer line stub-outs (For proposed extensions):

☐ The placement and markings of all sewer line stub-outs are shown and labeled.
☒ No sewer line stub-outs are to be installed during the construction of this sewage collection system.

30. Lateral stub-outs (For proposed private service connections):

☒ The placement and markings of all lateral stub-outs are shown and labeled.
☐ No lateral stub-outs are to be installed during the construction of this sewage collection system.

31. Minimum flow velocity (From Appendix A)

☒ Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line.

32. Maximum flow velocity/slopes (From Appendix A)

☒ Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.
☐ **Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.** Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.

Table 8 - Flows Greater Than 10 Feet per Second

Line	*Profile Sheet*	*Station to Station*	*FPS*	*% Slope*	*Erosion/Shock Protection*

33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the provisions noted below have been made to protect against pipe displacement by erosion and/or shock under 30 TAC §217.53(l)(2)(B).

☐ Concrete encasement shown on appropriate Plan and Profile sheets for the locations listed in the table above.
☐ Steel-reinforced, anchored concrete baffles/retards placed every 50 feet shown on appropriate Plan and Profile sheets for the locations listed in the table above.
☒ N/A

Administrative Information

34. ☒ The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.

35. ☒ Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

Table 9 - Standard Details

Standard Details	*Shown on Sheet*
Lateral stub-out marking **[Required]**	C1.40 of
Manhole, showing inverts comply with 30 TAC §217.55(l)(2) **[Required]**	C1.40 of
Alternate method of joining lateral to existing SCS line for potential future connections **[Required]**	C1.40 of
Typical trench cross-sections **[Required]**	C1.40 of
Bolted manholes **[Required]**	C1.40 of
Sewer Service lateral standard details **[Required]**	C1.40 of
Clean-out at end of line **[Required, if used]**	C1.40 of
Baffles or concrete encasement for shock/erosion protection **[Required, if flow velocity of any section of pipe >10 fps]**	C1.40 of
Detail showing Wastewater Line/Water Line Crossing **[Required, if crossings are proposed]**	C1.40 of
Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) **[Required, if Flexible Pipe is used]**	C1.40 of

Standard Details	*Shown on Sheet*
Drop manholes **[Required, if a pipe entering a manhole is more than 24 inches above manhole invert]**	C1.40 of

36. ☒ All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.

37. ☐ All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.

    ☒ Survey staking was completed on this date: Once Advised of TCEQ site visit

38. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

39. ☒ Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: CALEB CHANCE

Date: 10/17/24

Place engineer's seal here:



Signature of Licensed Professional Engineer:

Appendix A-Flow Velocity Table

Flow Velocity (Flowing Full) All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

Table 10 - Slope Velocity

Pipe Diameter(Inches)	*% Slope required for minimum flow velocity of 2.0 fps*	*% Slope which produces flow velocity of 10.0 fps*
6	0.50	12.35
8	0.33	8.40
10	0.25	6.23
12	0.20	4.88
15	0.15	3.62
18	0.11	2.83
21	0.09	2.30
24	0.08	1.93
27	0.06	1.65
30	0.055	1.43
33	0.05	1.26
36	0.045	1.12
39	0.04	1.01
>39	*	*

**For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.*

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

Where:

v = velocity (ft/sec)
n = Manning's roughness coefficient (0.013)
Rh = hydraulic radius (ft)
S = slope (ft/ft)

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

August 30, 2024

Ms. Roxi Vanstory
Oakwood Baptist Church
2154 Loop 337
New Braunfels, Texas 78130-4078

Re: Modification of an approved Water Pollution Abatement Plan (WPAP)
Oakwood Baptist Church Expansion; Located at 2154 Loop 337; New Braunfels, Comal County, Texas
Edwards Aquifer Protection Program ID: 13001965, Regulated Entity No. RN102744802

Dear Ms. Roxi Vanstory:

The Texas Commission on Environmental Quality (TCEQ) has completed its review on the application for the above-referenced project submitted to the Edwards Aquifer Protection Program (EAPP) by Pape-Dawson Engineers, Inc. on behalf of the applicant, Oakwood Baptist Church on July 8, 2024. Final review of the application was completed after additional material was received on August 16, 2024, and August 28, 2024.

As presented to the TCEQ, the application was prepared in general compliance with the requirements of 30 Texas Administrative Codes (TAC) Chapter §213. The permanent best management practices (BMPs) and measures represented in the application were prepared by a Texas licensed professional engineer (PE). All construction plans and design information were sealed, signed, and dated by a Texas licensed PE. Therefore, the application for the construction of the proposed project and methods to protect the Edwards Aquifer are **approved,** subject to applicable state rules and the conditions in this letter.

This approval expires two years from the date of this letter, unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been officially requested. This approval or extension will expire, and no extension will be granted if more than 50 percent of the project has not been completed within ten years from the date of this letter.

The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer protection plan. A motion for reconsideration must be filed in accordance with 30 TAC §50.139.

BACKGROUND

The initial development began in November 1983 for the construction of a church on a 3.498-acre lot consisting of 1.44-acres of impervious cover. Treatment of stormwater runoff from the 1.44-acres of impervious cover was not required.

The original application for Phase II and III of the development were approved by letter dated January 5, 1999, for the expansion of the site to 7.06 acres containing 4.27 acres of impervious cover. A sand filter basin designed in accordance with City of Austin Environmental Design Manual was approved and constructed for the treatment of stormwater.

A modification of the approved plan was approved by letter dated August 25, 2008, for the expansion of the site to 24.20 acres with 17.81 acres of impervious cover. The modification included additional buildings, parking lots, and the removal of the sand filter basin previously approved by the January 5, 1999, letter. A new sand filter basin, designed using the Edwards Aquifer Technical Guidance on Best Management Practices (2005), was approved for treatment of the stormwater runoff.

A modification of the approved plan was approved by letter dated October 28, 2011, for the 24.20-acre site. The modification included additional buildings with associated parking areas, sidewalks, one water quality pond, and an off-site stormwater detention pond. Total impervious cover for the project was approved at 17.13-acres. A partial sedimentation filtration basin was approved for treatment of the stormwater.

A modification of the approved plan was approved by letter dated July 5, 2012, for the 24.20 acres site. The development included relocation of the offsite detention pond to within the site, reconfiguration of the water quality pond, and reduction of the previously approved impervious cover to 16.74-acres. A partial sedimentation filtration basin was approved for treatment of the stormwater.

The most recent modification of the plan was approved by letter dated May 10, 2019, for a 36.16-acre site that added 11.96-acres to the development. This project included clearing, grading, construction of two access drives and designation of two natural vegetated filter strips (NVFS) for an adjusted impervious cover of 17.11-acres. During construction, 5.36-acres of concrete islands were not constructed and remained pervious.

PROJECT DESCRIPTION

The proposed commercial project will have an area of approximately 36.16-acres. This modification will include demolition of the existing sedimentation/filtration basin and detention basin to accommodate better onsite parking, construction of additional Church facilities, construction of a Batch Detention Basin A along Word Parkway, construction of Batch Detention Basin B along the west property line and construction of one Vegetative Filter Strip (VFS) (Watershed C). The impervious cover will increase to 20.10-acres (55.59-percent). No additional wastewater will be generated by this project.

PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, two Batch Detention Basins and one VFS proposed, designed using the TCEQ technical guidance, *RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices,* will be constructed to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 18,042 pounds of TSS generated from the 20.10-acres of impervious cover. The approved permanent BMPs and measures meet the required 80 percent removal of the increased load in TSS caused by the project.

The permanent BMPS shall be operational prior to occupancy or use of the proposed project. Inspection, maintenance, repair, and retrofit of the permanent BMPs shall be in accordance with the approved application.

GEOLOGY

According to the Geologic Assessment (GA) included with the application, the surficial units of the site are the Cyclic and Marine Members of the Person Formation. No sensitive geologic features were identified in the GA. The site assessment conducted on August 14, 2024, by TCEQ staff determined the site to be generally as described by the GA.

STANDARD CONDITIONS

1. The plan holder (applicant) must comply with all provisions of 30 TAC Chapter §213 and all technical specifications in the approved plan. The plan holder should also acquire and comply with additional and separate approvals, permits, registrations or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, Dam Safety, Underground Injection Control) as required based on the specifics of the plan.

2. In addition to the rules of the Commission, the plan holder must also comply with state and local ordinances and regulations providing for the protection of water quality as applicable.

Prior to Commencement of Construction:

3. Within 60 days of receiving written approval of an Edwards Aquifer protection plan, the plan holder must submit to the EAPP proof of recordation of notice in the county deed records, with the volume and page number(s) of the county record. A description of the property boundaries shall be included in the deed recordation in the county deed records. TCEQ form, Deed Recordation Affidavit (TCEQ-0625), may be used.

4. The plan holder of any approved Edwards Aquifer protection plan must notify the EAPP and obtain approval from the executive director prior to initiating any modification to the activities described in the referenced application following the date of the approval.

5. The plan holder must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the EAPP no later than 48 hours prior to commencement of the regulated activity. Notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person.

6. Temporary erosion and sedimentation (E&S) controls as described in the referenced application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

7. All borings with depths greater than or equal to 20 feet must be plugged with non-shrink grout from the bottom of the hole to within three (3) feet of the surface. The remainder of the hole must be backfilled with cuttings from the boring or gravel. All borings less than 20 feet must be backfilled with cuttings from the boring. All borings must be backfilled or plugged within four (4) days of completion of the drilling operation.

During Construction:

8. This approval does not authorize the installation of temporary or permanent aboveground storage tanks on this project that will have a total storage capacity of five hundred gallons or more of static hydrocarbons or hazardous substances without prior approval of an Aboveground Storage Tank facility application.

9. If any sensitive feature is encountered during construction, replacement, or rehabilitation on this project, all regulated activities must be **immediately** suspended near it and notification must be made to TCEQ EAPP staff. Temporary BMPs must be installed and

maintained to protect the feature from pollution and contamination. Regulated activities near the feature may not proceed until the executive director has reviewed and approved the methods proposed to protect the feature and the aquifer from potentially adverse impacts to water quality.

10. All water wells, including injection, dewatering, and monitoring wells shall be identified in the geologic assessment and must be in compliance with the requirements of the Texas Department of Licensing and Regulation 16 TAC Chapter §76 and all other locally applicable rules, as appropriate.

11. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.

12. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge must be filtered through appropriately selected BMPs.

13. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.

14. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

<u>After Completion of Construction:</u>

15. Owners of permanent BMPs and temporary measures must ensure that the BMPs and measures are constructed and function as designed. A Texas licensed PE must certify in writing that the **permanent** BMPs or measures were constructed as designed. The certification letter must be submitted to the EAPP within 30 days of site completion.

16. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or the ownership of the property is transferred to the entity. A copy of the transfer of responsibility must be filed with the executive director through the EAPP within 30 days of the transfer. TCEQ form, Change in Responsibility for Maintenance on Permanent BMPs and Measures (TCEQ-10263), may be used.

The holder of the approved Edwards Aquifer protection plan is responsible for compliance with Chapter §213 and any condition of the approved plan through all phases of plan implementation. Failure to comply with any condition within this approval letter is a violation of Chapter §213 and is subject to administrative rule or orders and penalties as provided under §213.10 of this title (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. Upon legal transfer of this property, the new owner is required to comply with all terms of the approved Edwards Aquifer protection plan.

This action is taken as delegated by the executive director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Don Vandertulip, PE, BCEE of the Edwards Aquifer Protection Program at 210-403-4057 or the regional office at 512-339-2929.

Sincerely,

Monica Reyes, Section Manager
Edwards Aquifer Protection Program
Texas Commission on Environmental Quality

MR/dv

cc: Mr. Caleb Chance, PE, Pape-Dawson Engineers, Inc.

ATTACHMENT A
(Engineering Design Report)

OAKWOOD BAPTIST CHURCH
Engineering Design Report
8” PVC SDR 26

TABLE OF CONTENTS

OAKWOOD BAPTIST CHURCH
Engineering Design Report
8" PVC SDR 26

This Engineering Design Report has been prepared to comply with the Texas Commission on Environmental Quality's Design Criteria for Domestic Wastewater Systems (30 TAC 217), and regulations over the Edwards Aquifer Recharge Zone (30 TAC 213). Please note, throughout this application, the more stringent of New Braunfels Utilities (NBU) or TCEQ regulations shall apply.

PROJECT INFORMATION

The Oakwood Baptist Church is a commercial development on an approximately 36.44 acres within the city of New Braunfels in Comal County, Texas. The site is located approximately 650 ft northeast of the TX-337 Loop and Oakwood Blvd intersection and is currently developed as a church and lies within the Blieders Creek watershed and does not contain 100-year floodplain. The site is located within the City of New Braunfels in Comal County, Texas, and entirely over the Edwards Aquifer Recharge Zone.

The Oakwood Baptist Church Sewage Collection System (SCS) Modification Application proposes the construction of a total of approximately 1,159 linear feet (LF) of sewer main to serve the future worship center. The proposed alignment will consist of approximately 1,159 LF of 8-inch (8") PVC, SDR 26 gravity sewer main. Regulated activities proposed include excavation, construction of sewer mains, backfill and compaction. Approximately 2.80 acres of the project site may be disturbed for this SCS installation as identified by the limits of the fifty-foot (50') SCS/GA envelope shown on the plans, concurrent with the overall civil infrastructure for the 36.16 acres project limits included in the WPAP.

This project will result in an estimated additional 26 Living Unit Equivalent (LUEs). The overall LUEs from the development is calculated to be 105 LUE which includes the calculated 79 from the approved 2012 SCS. The contributing acreage for inflow and infiltration is 36.16 acres. The sewage flow will be disposed of by conveyance to the existing Gruene Road Sewage Treatment Plant operated by the New Braunfels Utilities (NBU). No naturally occurring sensitive features were identified in the Geologic Assessment.

Please refer to Sheets C1.10-C1.20 of the attached sewer plans, which show the proposed service area and its topographic features. For information regarding the capability of the existing system and facilities to handle this increased flow. This system is designed to have a minimum structural life of 50 years.

Safety considerations are the responsibility of the contractor. Safety protection shall be accomplished in accordance with the most recent requirements of the Occupational Safety and Health Administration (OSHA) Standards and Interpretations.

GRAVITY SANITARY SEWER PIPING: FLOW & CAPACITY ANALYSIS

Basis for average flow used for design of collection system (**check one or more**):

Per Capita Contributions:	_____
Service Connections:	✓
Land Area and Use:	✓
Fixture Analysis:	_____

Odor Control

Odor Control is not necessary on this project as it is a gravity line and there will be no conditions where sewage is standing and will become septic.

Flow Calculation

Peaking Factor used for design: ***([18+(0.0206 x F)$^{0.5}$]/ (4+(0.0206 x F)$^{0.5}$) x F***

F= 200 (gal/LUE/day) x (#LUE) / 1440

Peaking Factor is based on: **NBU Specifications for peak dry weather flow (from NBU 10.3)**

Total LUEs = 105

1 LUE = 200 gallons per day (average sewage flow)

Avg. Daily Dry Weather Flow *=105 LUEs x (200 gpd/LUE) = 21,000 gpd =* ***14.58 gpm***

F = 200 (gal/LUE/day) x (105 LUE)/1440 = 14.58 gpm

Peak Dry Weather Flow *= ([18+(0.0206 x 14.58)$^{0.5}$]/ [4+(0.0206 x 14.58) $^{0.5}$]) x 14.58 =* ***62.05 gpm***

Infiltration = 750 gallons per acre served

Avg. Daily Wet Weather Flow *= 14.58 gpm + [(750 gpd/acre) x 36.16 acres] / 1440 =* ***33.41 gpm***

Peak Wet Weather Flow *= 62.05 gpm + [(750 gpd/acre) x 36.16 acres] / 1440 =* ***80.88 gpm***

Please note that capacities are determined using Manning's equation for pipes flowing full with an "n" value of 0.013. A reference for Manning's Equation can be found in "The Uni-Bell Handbook of PVC Pipe: Design and Construction".

Capacity Calculation

Characteristics of 8" ASTM D3034, SDR 26, PVC Sewer Pipe:

Nominal Size = 8"

Outer Diameter (D_o) = 8.40"

Minimum Wall Thickness (t) = 0.323"

Inner Diameter (D_i) = 7.75"

Manning's Equation:

$Q = (k/n)(A)(R^{2/3})(S^{1/2})$

$v = Q/A$

Where:

Q = Discharge (cfs)

k = Constant [(1.49 $ft^{1/3}$)/sec.]

n = Manning's roughness coefficient (unitless)

A = Flow area (ft^2)

R = Hydraulic Radius (ft)

= A/P = Cross sectional area of flow (ft^2)/Wetted perimeter (ft.)

S = Slope (ft/ft)

v = Velocity of flow (ft/s)

n = 0.013 [as required by 30 TAC 213.53 A(i)]

Calculations for 8" ASTM D3034, SDR 26, PVC Sewer Pipe:

$A = \pi(D_i^2)/4 = \pi(7.75\ in)^2/4 = 47.17\ in^2 = 0.33\ ft^2$

$P = \pi(D_i) = \pi(7.75\ in) = 24.35\ in = 2.03\ ft$

$R = A/P = 0.33\ ft^2/2.03\ ft. = 0.16\ ft$

S = 0.0055

Q = [(1.49 ft$^{1/3}$/sec)/0.013](0.33 ft^2)(0.16 ft)$^{2/3}$(0.0055)$^{1/2}$

*Q = **0.82 cfs=** Q-full*

*Q-full = 0.82 cfs (7.48 gallons/1 cf)(60 sec/1 min.)=**368.02 gpm***

*v = 0.82 cfs/0.33 ft^2=**2.48 ft/s***

*Qmax at 85% of full flow capacity= 0.82 cfs (0.85)(7.48 gallons/1 cf)(60 sec/1 min.)=**312.81 gpm***

*Qmax at 65% of full flow capacity= 0.82 cfs (0.65)(7.48 gallons/1 cf)(60 sec/1 min.)=**239.21 gpm***

Nominal Main Size (in)	Outer Diameter (in)	Minimum Slope (%)	Area (ft^2)	Hydraulic Radius (A/P) ft	R$^{2/3}$	S$^{1/2}$	Q-Full (cfs)	Max Pipe (%)	Velocity (ft/s)	Q-Max (gpm)
8	*8.40*	*0.55*	*0.33*	*0.16*	*0.26*	*0.074*	*0.82*	*85*	*2.48*	*312.81*
8	*8.40*	*0.55*	*0.33*	*0.16*	*0.26*	*0.074*	*0.82*	*65*	*2.48*	*239.21*

***When rounding of velocities is considered all velocities are at, or above, the required 2 fps.**

Conclusion

The proposed 8" pipe (NR & 160 psi) with a minimum slope of 0.55%, have sufficient capacity to convey the projected average and peak flows.

GENERAL STRUCTURAL COMPONENTS

Project Materials (Pipe and Joints):

Nominal Pipe Diameter (in)	Linear Feet	Pipe Material	National Standard Specification for Pipe Material	National Standard for Pipe Joints
8 (NR)	*1,159*	*PVC SDR 26*	*ASTM D3034*	*ASTM D3212*

Note: Section 217.53 (j)(4) requires a minimum pipe diameter of 6 inches for all gravity sanitary sewer collection system piping.

Watertight, size on size resilient connectors conforming to ASTM C-923 have been specified for connecting pipe to manholes. See NBU Standard Specification for Construction Detail.

Where a collection system parallels a water supply pipe and a nine-foot separation distance cannot be achieved, Section 217.53 (d)(3)(A)(i) requires a collection system pipe be constructed of cast iron, ductile iron, or PVC meeting ASTM specifications with at least a 150 pounds per square inch (psi) rating for both the pipe and joints. The proposed project will comply with these requirements.

Where a collection system pipe crosses a water supply line and a nine-foot separation distance cannot be achieved, Section 217.53(d)(3)(B)(i) requires the collection system pipe be constructed of cast iron, ductile iron, or PVC with a minimum pressure rating of 150 psi. The proposed project will comply with this requirement and that of 217.53(d)(3)(B)(iii).

Project Materials (Bedding):

The specified bedding will comply with ASTM D2321-11 Class I, II or III for materials and densification. A minimum of 6 inches of bedding is required for all pipe.

Pipe Diameter (in)	Pipe Material	Bedding Class
8	*PVC*	*Class I & Class III*

The selection of bedding class is based on NBU detail for sanitary sewer pipe laid in a trench. Initial backfill for the pipe sizes shown above will be Class I. Secondary backfill will be Class III. See Table 2 of ASTM D2321-11 "Soil Classes" in Appendix A of this subsection.

Project Materials (Manholes):

Section 217.55 (f) prohibits the use of bricks to adjust a manhole cover to grade or construct a manhole. The proposed project will comply with this requirement.

The inside diameter of a manhole must be no less than 48 inches.

Section 217.55 (n) requires watertight, size-on-size resilient connectors that allow for differential settlement and must conform to American Society for Testing and Materials C-923. The proposed project complies with this requirement.

Under 30 TAC 213.5(C)(3)(A), all manholes over the Recharge Zone must be watertight, with watertight rings and covers. The proposed project complies with this requirement.

The materials specified for manhole construction are precast concrete.

Project Materials (Manhole Covers):

Manhole covers must be constructed of impervious materials. If personnel entry is required, a minimum 30-inch diameter clear opening must be provided. Inclusion of steps in a manhole is prohibited. If a manhole must be located within a 100-year floodplain then a means of preventing inflow is required. A manhole cover that is located in a roadway must meet or exceed the American Association of State Highways and Transportation Officials Standard M-306 for load bearing.

Under 30 TAC 213.5 (c)(3)(A), all manholes over the Edwards Aquifer Recharge Zone must be watertight, with watertight rings and covers. This proposed project complies with this requirement.

Minimum and Maximum Slopes

Note: All pipes are designed with a slope that will provide a velocity of at least 2 ft/s flowing full, as calculated using Manning's equation with an "n" value of 0.013. Additionally, the collection system is designed to ensure that, with pipes flowing full, the velocities will be less than 10 feet per second.

The following are the minimum and maximum slopes for each pipe diameter:

Pipe Diameter: ***8" (NR)*** Min. Slope: ***0.55%*** Max. Slope: ***4.00%***

Backfill

Note: The backfill will be free of stones greater than 6 inches in diameter and free of organic or any other unstable material. See NBU details for additional specifications.

Trenching

Note: The trench width will be minimized while still allowing adequate width for proper compaction of backfill, and while still ensuring that at least 6 inches of backfill exists below and on each side of the pipe. The trench walls will be vertical to at least one foot above the pipe.

Trenching will occur over the Recharge Zone and will comply with 30 TAC 213.5.

Minimum and Maximum Trench Width

Based on NBU Standard Drawing and 30 TAC 217.54:

Pipe Diameter: ***8" (NR)*** Min. Trench Width: ***22***" Max. Trench Width: ***34"***

These trench widths account for the bell diameter.

Corrosion Prevention

Proposed collection system components (pipes, manholes, etc.) will not be susceptible to deterioration through the corrosive effects of an anaerobic sewage environment. The interior of the manholes, however, are to be coated with a NBU approved sewer structural coating. Epoxy coating specifically approved. The epoxy coating on the interior walls of the manhole provide interior corrosion protection.

Manholes (General)

Note: Manholes are provided at all changes in size, grade or alignment of pipe, at the intersection of all pipes and at the end of all lines that may be extended at a future date. A clean-out with watertight plugs may be installed instead of a manhole if no extensions are anticipated. Clean outs must pass all testing requirements outlined for gravity collection pipes.

The project complies with the maximum manhole spacing allowed by the TCEQ:

Pipe Diameter (in)	Max. Manhole Spacing (ft)
6 - 15	500
18 - 30	800
36 - 48	1000
54 or larger	2000

Manhole Spacing:

Pipe Diameter: ***8"*** Max. Spacing: ***216 LF***

Manholes (Inverts)

The bottom of a manhole must contain a U-shaped channel, which is a smooth continuation of the inlet, and outlet pipes. The bench above the channel must be sloped a minimum of 0.5 inches per foot. Note, a manhole connected to a pipe less than 15 inches in diameter must have a channel depth equal to at least half the largest pipe's diameter.

Manholes (Ventilation)

Vented manholes are not proposed for this SCS.

FLEXIBLE PIPE COMPUTATIONS

Please note, all flexible pipe computations are based on engineering principles and practices for the design of buried PVC pipe systems. Equations used can be found in "The Uni-Bell PVC Pipe Association Handbook of PVC Pipe: Design and Construction". Please note, the equations used may be in a different format than shown in the Uni-Bell Handbook. Throughout this application "160 psi" pipe refers to the pressure rating of the ASTM 2241, Class 160, SDR 26 pipe used at waterline crossings in the SCS.

Live Load Calculations

Minimum burial depth without concrete encasement is seven (7) feet. Based on Table 6-6 Live Loads on PVC pipe (from Uni-Bell Handbook for PVC) for this sewer line would be 1.22 psi.

Buckling Pressure Calculations

This area of the Edwards Aquifer is unsaturated; consequently, there are no anticipated areas where sewer pipe will be placed below the water table. The value of hw=0 as there will be no height or time period of perched water or groundwater above the pipe crowns of the proposed sewer line.

The value of H for use in these calculations is fifteen (15) feet as it exceeds the maximum burial depth for this line. The value of γ_s equals 143 pcf is a conservative value based on a dry unit weight of 135 pcf and a moisture content of 6%. This value is conservative as it corresponds to saturated unit weights of commonly used backfill materials. Please see information from Raba-Kistner provided in Appendix C.

Allowable Buckling Pressure:

$$q_a = 0.4 * \sqrt[2]{32 * R_w * B' * E_b * (E * I / D^3)}$$ *Equation 1*

$$q_a = 0.4 * \sqrt[2]{32 * 1 * 0.4 * 400(400{,}000 * 0.003/8.08^3)} = 43.17\ psi\ (8"\ PVC\ SDR\ 26, NR)$$

$$q_a = 0.4 * \sqrt[2]{32 * 1 * 0.4 * 400(400{,}000 * 0.003/8.29^3)} = 41.54\ psi\ (8"\ PVC\ SDR\ 26, 160\ psi)$$

$$R_w = 1 - 0.33 * (h_w / h)$$ *Equation 2*

$$R_w = 1 - 0.33 * (0/240) = 1$$

$$B' = \frac{1}{1+4*e^{-0.065H}}$$ *Equation 3*

$$B' = \frac{1}{1+4*e^{-0.065(15)}} = 0.40$$

$$I = (t^3/12) * (inches^4/linear\ inch)$$ *Equation 4*

$$I = (0.323^3/12) = 0.003 in^3 (8"PVC, SDR, NR)$$

$$I = (0.332^3/12) = 0.003 in^3 (8"PVC, SDR26, 160psi)$$

$$D = D_o - t$$ *Equation 5*

$$D = 8.40\ inches - 0.323\ inches = 8.08\ inches (8"PVC, SDR26, NR)$$

$$D = 8.62\ 5 inches - 0.332\ inches = 8.29\ inches (8"PVC, SDR26, 160\ psi)$$

Where:

q_a = Allowable buckling pressure, pounds per square inch (psi)

h = Height of soil surface above top of pipe in inches (in)

h_w = Height of water surface above top of pipe in inches (in) (groundwater elevation)

R_w = Water buoyancy factor. If hw = 0, Rw = 1. If 0 ≤ hw ≤ h (groundwater elevation is between the top of the pipe and the ground surface), calculate Rw with Equation 2

H = Depth of burial in feet (ft) from ground surface to crown of pipe.

B' = Empirical coefficient of elastic support

E_b = Modulus of soil reaction for the bedding material (psi)

E = Modulus of elasticity of the pipe material (psi)

I = Moment of inertia of the pipe wall cross section per linear inch of pipe, inch4/lineal inch = inch3. For solid wall pipe, "I" can be calculated with Equation 4

t = Pipe structural wall thickness (in)

D = Mean pipe diameter (in)

D_o = Pipe outer diameter (in)

Pressure Under Installed Conditions

$$q_p = \gamma_w * h_w + R_w * (W_c/D) + L_l$$ *Equation 6*

$$q_p = 0.0361 * 0 + 1 * (125.17/8.08) + 1.22 = 16.71 psi\ (8"PVC, SDR26, NR)$$

$$q_p = 0.0361 * 0 + 1 * (128.43/8.29) + 1.22 = 16.71 psi\ (8"PVC, SDR26, 160psi)$$

Where:

q_p = Pressure applied to pipe under installed conditions (psi)

γ_w = 0.0361 pounds per cubic inch (pci), specific weight of water

W_c = Vertical soil load on the pipe per unit length in pounds per linear inch (lb/in)

L_l = Live load (lbs)

$$W_c = \gamma_s * H * (D+t)/144$$ *Equation 7*

$W_c = 143 * 15 * (8.08 + 0.323)/144 = 125.17\ lb/in$ $(8"PVC, SDR26, NR)$

$W_c = 143 * 15 * (8.29 + 0.332)/144 = 128.43\ lb/in$ $(8"PVC, SDR26{,}160psi)$

γs = Specific weight of soil in pounds per cubic foot (pcf)

D = Mean pipe diameter (in)

Pipe Diameter: ***8" (NR)*** Pipe Material: ***PVC, SDR 26*** q_a: ***43.17*** q_p: ***16.71***

Since $q_a \geq q_p$, the specific pipe is acceptable for the proposed installation.

Wall Crushing Calculations

No portion of the proposed sewer line is located in the 5-year floodplain.

$$H = (24 * P_c * A)/(\gamma_s * D_o)$$ (*Equation 8)*

$$A = t(in) \times 12(in/ft)$$ (*Equation 9)*

H=(24*4,000*3.876)/(143*8.4) = 309.77 (8"PVC,SDR26, NR)

$A = 0.323(in) \times 12(in/ft) = 3.876$

D_o = outside pipe diameter, in.

P_c = compressive stress or hydrostatic design basis (HDB). For typical PVC pipe assume 4,000 psi. For any other pipe material, the HDB must be supplied by the pipe manufacturer.

A = surface area of the pipe wall, $in.^2/ft$ [conversion factor of 12 applied to change from ft. to in.]

γ_s = specific weight of soil in pounds per cubic foot (pcf)

H = Depth of burial in feet (ft) from ground surface to crown of pipe.

24 = conversions and coefficients

Installation Temperature Effects

Flexible pipe will be installed under favorable ambient conditions, per pipe manufacturer's specifications.

Tensile Strength

The information below is from "The Uni-Bell Handbook of PVC Pipe: Design and Construction" Table 2.1 pages 14-15. This applies to all PVC SDR-26 pipe.

Pipe Material: ***PVC SDR 26*** Tensile Strength: ***7,000*** Cell Class (PVC only) ***12454***

Strain

The conditions of this installation are such that strain-related failure will not be a problem. Strain is generally not a performance-limiting factor for buried PVC pipe or a design-limiting criterion for PVC pipes according to the Uni-Bell Handbook of PVC Pipe (Chapter VII, Pages 255 and 257). As pipe deflection will be below 5%, strain-related failure is not anticipated.

Modulus of Soil Reaction

The modulus of soil reaction for the bedding material, E_b, is **400 psi**.

This value was determined using the "Table 1: Soil Classification Chart" and "Table 2: Soil Classes" from ASTM D2321-11 and "Average Values of Modulus of Soil Reaction, E" Table 7.3 from "The Uni-Bell Handbook of PVC Pipe: Design and Construction" attached in Appendix A of this subsection. Based on NBU detail, Class III material was chosen. As the secondary backfill (Class III) has a lower Modulus of Soil Reaction than initial backfill (Class I), its value was used in the calculations that follow. Class III on Table

2 corresponds to coarse-grained soils with fines (GM, GC, SM or SC) and sandy or gravelly fine-grained soils (CL or ML). On Table 7.3, coarse-grained soils with fines at a slight compaction have an E' equal to 400 psi.

The modulus of soil reaction for the in-situ soil, E'_n, is **3,000 psi**

This value was determined using the "Table 1: Soil Classification Chart" and "Table 2: Soil Classes" from ASTM D 2321-11 and "Average Values of Modulus of Soil Reaction, E" Table 7.3 from "The Uni-Bell Handbook of PVC Pipe: Design and Construction" attached in Appendix A of this subsection. Based on NBU detail, Class I material was chosen, which includes crushed rock as shown on Table 2. Compacted crushed rock on Table 7.3 has an E' equal to 3,000 psi. Values in Table 7.3 are based on empirical data and derived from laboratory and field tests for buried pipe.

Bedding to in-situ soil modulus of soil reaction ratio = E_b/E'_n = **400 psi/3,000 psi = 0.13**

Zeta Calculation

Where native soil is significantly weaker than bedding material, or where predicted deflection approaches 5%, the effect of native soil must be quantified using Leonhardt's Zeta factor. If the ration of bedding modulus to soil modulus is not equal to 1.0, a zeta factor must be calculated by using the equations below, where zeta is a factor, which corrects for the effect of in-situ soil on pipe stability (Uni-Bell Handbook of Pipe, page 267). To calculate zeta, directly use the formulas below. The calculations that are done to determine the zeta factors for the different pipe diameters must be included with this submittal.

$$zeta = \frac{1.44}{f + (1.44 - f) * (E_b / E_{n'})} \qquad \textit{(Equation 9)}$$

$$zeta = \frac{1.44}{1.22 + (1.44 - 1.22) * 0.13} = 1.15(8" PVC SDR26, NR)$$

$$zeta = \frac{1.44}{1.22 + (1.44 - 1.22) * 0.13} = 1.15(8" PVC SDR26, 160 psi)$$

$$f = \frac{b/d_a - 1}{1.154 + 0.444*(b/d_a - 1)}$$ *(Equation 10)*

$$f = \frac{34/8.40 - 1}{1.154 + 0.444*(34/8.40 - 1)} = 1.22 (8" PVC, SDR26, NR)$$

$$f = \frac{35/8.625 - 1}{1.154 + 0.444*(35/8.625 - 1)} = 1.22 (8" PVC, SDR26, 160 psi)$$

Where:

- f = Pipe/trench width coefficient
- b = Trench width (in)
- d_a = Pipe diameter (in)
- E_b = Modulus of soil reaction for the bedding material (psi)
- E'_n = Modulus of soil reaction for the in-situ soil (psi)

Pipe Diameter: ***8" (NR)*** Trench Width: ***34"*** Zeta: ***1.15***

Pipe Stiffness

Ps is based on National Reference Standards and manufacturer's data. Please see Table 7.1 of the "The Uni-Bell Handbook of PVC Pipe: Design and Construction" listing the pipe stiffness of 8" PVC SDR 26 as 115 psi for E = 400,000 psi.

Pipe Diameter: ***8"*** Pipe Material: ***PVC SDR 26*** Ps: ***115 psi***

Deflection

Maximum allowable deflection in installed lines is 5% (per 30 TAC 217), as determined by the deflection analysis and verified by a mandrel test. It is recommended that the percent of vertical deflection is below this range; however, a 7.5% deflection limit (recommended by ASTM D3034) provides a conservative factor of safety against structural failure (Handbook of PVC Pipe, page 249).

Note: Per Table 7.2 attached in Appendix A of the SCS Application, K = 0.096 when the bedding angle is 90 degrees. A bedding angle of 90 degrees is required as shown on NBU detail.

$$\Delta Y / D(\%) = \frac{K * (L_p + L_1) * 100}{(0.149 * P_s) + (0.061 * zeta * E_b)}$$ *(Equation 11)*

$$\Delta Y/D(\%) = \frac{(0.096)(14.9+1.22)*100}{(0.149*115)+(0.061*1.15*400)} = 3.42\% \; for \; 8" \; NR \; pipe$$

$$\Delta Y/D(\%) = \frac{(0.096)(14.9+.22)*100}{(0.149*115)+(0.061*1.15*400)} = 3.42\% \; for \; 8" \; 160 \; psi \; pipe$$

$$L_p = \frac{\gamma_s * H}{144}$$ *(Equation 12)*

$$L_p = \frac{143 * 15}{144} = 14.9 \; psi$$

%ΔY/D = Predicted % vertical deflection under load

ΔY = Change in vertical pipe diameter under load

D = Undeflected mean pipe diameter (in)

K = Bedding angle constant

γ_s = Unit weight of soil (pcf)

H = Depth of burial (ft) from ground surface to crown of pipe

L_p = Prism load (psi)

Type of Pipe Material	P_s (psi)	Zeta Factor Assumed or Calculated	E_b (psi)	% Deflection
8" PVC SDR 26 (NR)	*115*	*1.15*	*400*	*3.42*

All pipes proposed for this project have a maximum predicted deflection below 5.0%

Signature, Seal and Date of the Texas Professional Engineer Below:

APPENDIX A (TABLES)

Raba Kistner

January 14, 2009

Raba-Kistner Consultants, Inc.
12821 W. Golden Lane
P.O. Box 690287, San Antonio, TX 78269-0287
(210) 699-9090 • FAX (210) 699-6426
www.rkci.com

Charles P. "Frosty" Forster, P.E., P.G.
Pape Dawson Engineers
555 East Ramsey
San Antonio, Texas 78216

RE: Soil Unit Weight Values for Backfill Materials
Various Projects
San Antonio, Texas

Dear Mr. Forster:

Raba-Kistner Consultants Inc. (R-K) is pleased to submit this letter providing general guidance for selecting design soil unit weights for use in utility trench design.

In general, the following table contains a list of the frequently used trench backfill materials in the San Antonio area. The table also contains approximate values for the soil dry unit weight, moist unit weight and saturated unit weight for these materials assuming 90 to 95 percent compaction utilizing a standard Proctor (ASTM D 698.)

MATERIAL DESCRIPTION	DRY UNIT WEIGHT, PCF	MOIST UNIT WEIGHT, PCF	SATURATED UNIT WEIGHT, PCF
TxDOT TEX-113E Type A, Gr. 1 or 2	130	137	143
TxDOT TEX-113E Type A, Gr. 3 thru 5	128	135	143
Limestone Millings	115	124	134
Gravelly Clay	110	120	132
Clay	100	120	127
Clayey Sand	95	106	123
Gravel (Clean)	115	120	134
Sand (Clean)	92	98	120
Pit Run Gravel	127	137	142

We appreciate the opportunity to be of service to you. If you have any questions or need additional assistance, please call.

Very truly yours,

RABA-KISTNER CONSULTANTS, INC.

STATE OF TEXAS
CHRIS L. SCHULTZ
80680
LICENSED
PROFESSIONAL ENGINEER

1/14/09

Chris L. Schultz, P.E.
Senior Vice President

CLS/mem

O:\Admin - Non Project\San Antonio\PD back fill letter.doc

SOIL CLASSIFICATION CHART

From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

TABLE 1 Soil Classification Chart (see Classification D2487)

	Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests[A]				Soil Classification	
					Group Symbol	Group Name[B]
Coarse-Grained Soils	Gravels	Clean gravels	C ≥ 4 and 1 ≤ Cc ≤ 3[C]		GW	Well-graded gravel[D]
More than 50% retained on No. 200 sieve	More than 50% of coarse fraction retained on No. 4 sieve	Less than 5% of fines[E]	Cu < 4 and/or 1> Cc>3[C]		GP	Poorly graded gravel[D]
		Gravels with more than 12% fines[E]	Fines classify as ML or MH		GM	Silty gravel[DFG]
			Fines classify as CL or CH		GC	Clayey gravel[DFG]
	Sands	Clean sands	Cu ≥ 6 and 1 ≤ Cc ≤ 3[C]		SW	Well-graded sand[H]
	50% or more of coarse fraction passes on No. 4 sieve	Less than 5% fines[I]	Cu < 6 and/or 1 > Cc > 3[C]		SP	Poorly graded sand[H]
		Sand with fines	Fines classify as ML or MH		SM	Silty sand[FGH]
		More than 12% fines[I]	Fines classify as CL or CH		SC	Clayey sand[FGH]
Fine-Grained Soils	Silts and clays	Inorganic	PI > 7 and plots on or above "A" line[J]		CL	Lean clay[KLM]
50% or more passes the No. 200 Sieve	Liquid limit less than 50		PI < 4 and plots below "A" line[J]		ML	silt[KLM]
		Organic	Liquid Limit-Oven dried	<0.75	OL	Organic clay[KLMN]
			Liquid Limit-Not dried			Organic silt[KLMO]
	Silts and clays	Inorganic	PI plots on or above "A" line		CH	Fat clay[KLM]
	Liquid limit 50 or more		Plots below "A" line		MH	Elastic silt[KLM]
		Organic	Liquid Limit-Oven Dried	<0.75	OH	Organic clay[KLMP]
			Liquid Limit-Not Dried			Organic silt[KLMQ]
Highly organic soils	Primarily organic matter, dark in color, and organic odor				PT	peat

[A] Based on the material passing the 3-in. (75-mm) sieve.
[B] If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.
[C] $Cu = D_{60} / D_{10}$

$$Cc = \frac{(D_{30})^2}{D_{10} x D_{60}}$$

[D] If soil contains ≥15 % sand, add "with sand" to group name.
[E] Gravels with 5 to 12 % fines require dual symbols:
GW-GM well-graded gravel with silt:
GW-GC well-graded gravel with clay
GP-GM poorly graded gravel with silt
GP-GC poorly graded gravel with clay
[F] If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.
[G] If fines are organic, add "with organic fines" to group name.
[H] If soil contains ≥ 15 % gravel, add "with gravel" to group name.
[I] Sands with 5 to 12 % fines require dual symbols:
SW-SM well graded sand with silt
SW-SC well-graded sand with clay
SP-SM poorly graded sand with silt
SP-SC poorly graded sand with clay
[J] If Atterberg limits plot in hatched area, soil is a CL-ML, silty clay (see Test Method D4318).
[K] If soil contains 15 to 29 % plus No. 200, add "with sand" or "with gravel", whichever is predominant.
[L] If soil contains ≥ 30 % plus No. 200, predominantly sand, add "sandy" to group name.
[M] If soil contains ≥ 30 % plus No. 200, predominantly gravel, add "gravelly" to group name.
[N] PI ≥ 4 and plots on or above "A" line.
[O] PI < 4 or plots below "A" line.
[P] PI plots on or above "A" line.
[Q] PI plots below "A" line.

SOIL CLASSIFICATION CHART

From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

TABLE 2 Soil Classes

Soil Group [A,B]	Soil Class	American Association of State Highway and Transportation Officials (AASHTO) Soil Groups [C]
Crushed rock, angular [D], 100% passing 1-1/2 in. sieve, </=15 % passing #4 sieve, </= 25 % passing 3/8 in. sieve and </= 12 % passing #200 sieve	Class I	--
Clean, coarse grained soils: SW, SP, GW, GP or any soil beginning with one of these symbols with </= 12 % passing #200 sieve[E,F]	Class II	A1, A3
Coarse grained soils with fines: GM, GC, SM, SC or any soil beginning with one of these symbols, containing > 12 % passing #200 sieve; Sandy or gravelly fine-grained soils: CL, ML, or any soil beginning with one of these symbols, with >/= 30 % retained on #200 sieve	Class III	A-2-4, A-2-5, A-2-6, or A-4 or A-6 soils with more than 30% retained on #200 sieve
Fine-grained soils: CL, ML, or any soil beginning with one of these symbols, with <30 % retained on #200 sieve	Class IV	A-2-7, or A-4, or A-6 soils with 30% or less retained on #200 sieve
MH, CH, OL, OH, PT	Class V Not for use as embedment	A5, A7

[A] See Classification D2487, Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).
[B] Limits may be imposed on the soil group to meet project or local requirements if the specified soil remains within the group. For example, some project applications require a Class I material with minimal fines to address specific structural or hydraulic conditions and the specification may read "Use Class I soil with a maximum of 5% passing the #200 sieve."
[C] AASHTO M145, Classification of Soils and Soil Aggregate Mixtures.
[D] All particle face shall be fractured.
[E] Materials such as broken coral, shells, and recycled concrete, with $\leq$ = 12% passing a No. 200 sieve, are considered to be Class II materials. These materials should only be used when evaluated and approved by the Engineer.
[F] Uniform fine sands (SP) with more than 50% passing a No. 100 sieve (0.006 in., 0.15 mm) are very sensitive to moisture and should not be used as backfill unless specifically allowed in the contract documents. If use of these materials is allowed, compaction and handling procedures should follow the guidelines for Class III materials.

SOIL CLASSIFICATION CHART

From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

TABLE 3 Recommendations for Installation and Use of Soils and Aggregates for Foundation and Pipe-Zone Embedment

Soil Class[A]	Class I[B]	Class II	Class III	Class IV
General Recommendations and Restrictions	Acceptable and common where no migration is probable or when combined with a geotextile filter media. Suitable for use as a drainage blanket and under drain where adjacent material is suitably graded or when used with a geotextile filter fabric (see X1.8).	Where hydraulic gradient exists check gradation to minimize migration. Clean groups are suitable for use as a drainage blanket and underdrain (see Table 2). Uniform fine sands (SP) with more than 50 % passing a #100 sieve (0.006 in., 0.15 mm) behave like silts and should be treated as Class IV soils.	Do not use where water conditions in trench prevent proper placement and compaction. Not recommended for use with pipes with stiffness of 9 psi or less.	Difficult to achieve high-soil stiffness. Do not use where water conditions in trench prevent proper placement and compaction. Not recommended for use with pipes with stiffness of 9 psi or less.
Foundation	Suitable as foundation and for replacing over-excavated and unstable trench bottom as restricted above.	Suitable as foundation and for replacing over-excavated and unstable trench bottom as restricted above. Install and compact in 12 in. (300 mm) maximum layers.	Suitable for replacing over-excavated trench bottom as restricted above. Install and compact in 6 in. (150 mm) maximum layers.	Suitable for replacing over-excavated trench bottom as restricted above. Install and compact in 6-in (150 mm) maximum layers.
Pipe Embedment	Suitable as restricted above. Work material under pipe to provide uniform haunch support.	Suitable as restricted above. Work material under pipe to provide uniform haunch support.	Suitable as restricted above. Difficult to place and compact in the haunch zone.	Suitable as restricted above. Difficult to place and compact in the haunch zone.
Embedment Compaction: Min Recommended Percent Compaction, SPD[D]	See Note[C]	85 % (SW and SP soils) For GW and GP soils See Note[E]	90 %	95 %
Relative Compactive Effort Required to Achieve Minimum Percent Compaction	Low	Moderate	High	Very high
Compaction Methods	Vibration or impact	Vibration or impact	Impact	Impact
Required Moisture Control	None	None	Maintain near optimum to minimize compactive effort	Maintain near optimum to minimize compactive effort

[A] Class V materials are unsuitable as embedment. They may be used as final backfill as permitted by the engineer.
[B] Class I materials have higher stiffness than Class II materials, but data on specific soil stiffness of placed, uncompacted Class I materials can be taken equivalent to Class II materials compacted to 95% of maximum standard Proctor density (SPD95), and the soil stiffness of compacted Class I materials can be taken equivalent to Class II materials compacted to 100% of maximum standard Proctor density (SPD100). Even if placed uncompacted (that is, dumped), Class I materials should always be worked into the haunch zone to assure completed placement.
[C] Suitable compaction typically achieved by dumped placement (that is, uncompacted but worked into haunch zone to ensure complete placement).
[D] SPD is standard Proctor density as determined by Test Method D698.
[E] Place and compact GW and GP soils with at least two passes of compaction equipment.

TABLE 6.6
LIVE LOADS ON PVC PIPE
From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)

Height of Cover (ft)	Live Load Transferred to Pipe, lb/in^2			Height of Cover (ft)	Live Load Transferred to Pipe, lb/in^2		
	Highway H20[1]	Railway E80[2]	Airport [3]		Highway H20[1]	Railway E80[2]	Airport [3]
1	12.50			14	*	4.17	3.06
2	5.56	26.39	13.14	16	*	3.47	2.29
3	4.17	23.61	12.28	18	*	2.78	1.91
4	2.78	18.40	11.27	20	*	2.08	1.53
5	1.74	16.67	10.09	22	*	1.91	1.14
6	1.39	15.63	8.79	24	*	1.74	1.05
7	1.22	12.15	7.85	26	*	1.39	*
8	0.69	11.11	6.93	28	*	1.04	*
10	*	7.64	6.09	30	*	0.69	*
12	*	5.56	4.76	35	*	*	*
				40	*	*	*

[1] *Simulates 20 ton truck traffic + impact (Source: ASTM A 796)*
[2] *Simulates 80,000 lb/ft railway load + impact (Source: ASTM A 796)*
[3] *180,000 lbs. dual tandem gear assembly. 26 inch spacing between tires and 66 inch center-to-center spacing between fore and aft tires under a rigid pavement 12 inches thick + impact.*
** Negligible live load influence.*

FIGURE 7.4
BEDDING ANGLE
From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)



TABLE 7.2
VALUES OF BEDDING CONSTANT, K

BEDDING ANGLE (DEGREES)	K
0	0.110
30	0.108
45	0.105
60	0.102
90	0.096
120	0.090
180	0.083

APPENDIX B (SOIL UNIT WEIGHT VALUES)

TABLE 7.3
AVERAGE VALUES OF MODULUS OF SOIL REACTION, E'
(For Initial Flexible Pipe Deflection)
From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)

Soil type-pipe bedding material (Unified Classification System[a]) (1)	E' for Degree of Compaction of Bedding, in pounds per square inch			
	Dumped (2)	Slight, < 85% Proctor, <40% relative density (3)	Moderate, 85%-95% Proctor, 40%-70% relative density (4)	High, >95% Proctor, >70% relative density (5)
Fine-grained Soils (LL>50)[b] Soils with medium to high plasticity, CH, MH, CH-MH	No data available; consult a competent soils engineer; Otherwise use E' = 0			
Fine-grained Soils (LL<50) Soils with medium to no plasticity, CL, ML, ML-CL, with less than 25% coarse-grained particles	50	200	400	1,000
Fine-grained Soils (LL<50) Soils with medium to no plasticity, CL, ML, ML-CL, with more than 25% coarse-grained particles Coarse-grained Soils with Fines GM, GC, SM, SC[c] contains more than 12% fines	100	400	1,000	2,000
Coarse-grained Soils with Little or no Fines GW, GP, SW, SP[c] contains less than 12% fines	200	1,000	2,000	3,000
Crushed Rock	1,000	3,000	3,000	3,000
Accuracy in Terms of Percentage Deflection[d]	± 2	± 2	± 1	± 0.5

[a]ASTM Designation D 2487, USBR Designation E-3.
[b]LL = Liquid limit.
[c]Or any borderline soil beginning with one of these symbols (i.e. GM-GC, GC-SC).
[d]For ± 1% accuracy and predicted deflection of 3%, actual deflection would be between 2% and 4%

Note: Values applicable only for fills less than 50 ft (15 m). Table does not include any safety factor. For use in predicting initial deflections only, appropriate Deflection Lag Factor must be applied for long-term deflections. If bedding falls on the borderline between two compaction categories, select lower E' value or average the two values. Percentage Proctor based on laboratory maximum dry density from test standards using about 12,500 ft-lb/cu ft (598,000 J/m^3) (ASTM D 698, AASHTO T-99, USBR Designation E-11). 1 psi = 6.9 kPa.

SOURCE: "Soil Reaction for Buried Flexible Pipe" by Amster K. Howard, U.S. Bureau of Reclamation, Denver, Colorado. Reprinted with permission from American Society of Civil Engineers.

30 TAC 217 regulations will apply where more stringent than the following SAWS Specifications

Specification 852: Sanitary Sewer Manholes
https://apps.saws.org/business_center/specs/constspecs/docs/conspecs_2021/ITEM%20NO.%20852%20Sanitary%20Sewer%20Manholes.pdf

Specification 854: Sanitary Sewer Laterals
https://apps.saws.org/business_center/specs/constspecs/docs/conspecs_2021/ITEM%20NO.%20854%20Sanitary%20Sewer%20Laterals.pdf

Specification 804: Excavation, Trenching and Backfill
https://apps.saws.org/business_center/specs/constspecs/docs/conspecs_2021/ITEM%20NO.%20804%20Excavation%20Trenching%20and%20Backfill.pdf

APPENDIX C (STANDARD SPECS AND PRE-CAST MANHOLES SPECS)

PRE-CAST MANHOLE DRAWINGS & SPECIFICATIONS

\APPROVAL\CONCENTRIC.DWG



(7R JOINT)

REF. FORM DWG. 3-303-5561

INTERNATIONAL PIPE MACHINERY

QUINN

MACHINE & FOUNDRY CORP.

A MEMBER OF THE BESSER FAMILY OF COMPANIES

BOONE, IOWA U.S.A.

CHARLOTTES

48 x 5 x 34 1/2 x 8 x 36 & 18

CONCENTRIC CONCRETE SECTION

DRAFTER	JJK	4/19/02	CONCENTRIC	REV.
CHECKED				
SCALE:	1/12" = 1"			



Flattop Illustration
for Shallow Manhole



Section View
4' I.D. Manhole - Regular Base
with Reducing Cone

Materials & Features

HOLES AS SPECIFIED: Max diameter = 32"
CONCRETE: 5,000 PSI, 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
Average weight of 24" depth base w/8" invert = 4,500 lbs.
Estimated weight of riser and cone sections = 870 lbs. / vt. ft.

* - Extended base is available to meet local requirements.

In the event a boot is loose contact your Hanson representative to resolve.

"Manufactured to your specifications."

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
4' I.D. Manhole **Regular Base w/ Reducing Cone**	All Plants	TX	5.5	08-15-06	Hanson



Flattop Illustration
for Shallow Manhole



Section View
5'/4' & 6'/4' I.D. Manhole
Extended Base with Reducing Cone

Materials & Features

HOLES AS SPECIFIED: for 5' I.D. max diameter = 40"
for 6' I.D. max diameter = 54"
CONCRETE: 5,000 PSI, 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
Average weight of 24" depth base w/8" invert:
for 5' I.D. = 7,500 lbs.
for 6' I.D. = 10,600 lbs.
Estimated weight of riser and sections:
for 5' I.D. = 1,325 lbs. / vt. ft.
for 6' I.D. = 1,800 lbs. / vt. ft.
For pipe sizes 15" and larger, invert shall be equal to the larger pipe diameter.
* - Extended base shown; Regular base also available."
In the event a boot is loose contact your Hanson representative to resolve.

"Manufactured to your specifications."

Pipe Size	I.D. "A"	O.D. "B"	Wall Thk. "C"
5'	5' - 0"	6' - 0"	6"
6'	6' - 0"	7' - 2"	7"

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION-PAGE	DATE
5'/4' & 6'/4'I.D. Manhole **Extended Base w/Reducing Cone**	All Plants	TX	5.6	08-15-06

Hanson

Precast Manholes

For Pipe Entering the Manhole at Excessive Depths Above the Flow Line Out, the Contractor May be Responsible for Grout Work Necessary to Bring Channel up to Flow Line on Inlet Pipe.





Plan View



Section View

Pipe Size	I.D. "A"	O.D. "B"	Wall Thk. "C"
4'	4' - 0"	4' - 10"	5"
5'	5' - 0"	6' - 0"	6"
6'	6' - 0"	7' - 2"	7"

Materials & Features

HOLES AS SPECIFIED:
- For 4' I.D. max. diameter = 32"
- For 5' I.D. max. diameter = 40"
- For 6' I.D. max. diameter = 54"

CONCRETE: 5,000 PSI, 28 day strength
REINFORCING: Meets or exceeds ASTM C478 requirements.
Average weight of 24" depth base w/8" invert = 4,500 lbs.
Water-tight gaskets at all pipe connections.
* - Regular base shown: Extended base also available.
In the event a boot is loose contact your Hanson representative to resolve.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
Details: 4', 5' & 6' I.D. Precast Regular Manhole Base	All Plants	TX	5.7	08-15-06	Hanson

Contact Hanson | Go to Index | EXIT



Plan View



Section View

Materials & Features

CONCRETE. 5,000 PSI. 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
CONSTRUCTION OF PRECAST is in accordance with ASTM C478.
Concrete is poured according to ACI-500.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
5' x 4' Conical Adaptor	Waco	TX	5 8	08-15-06	Hanson



Concentric Cone
24" ø Opening



Eccentric Cone
24" ø Opening



Concentric Cone
34 1/2" ø Opening



Eccentric Cone
34 1/2" ø Opening

Materials & Features

CONCRETE: 5,000 PSI, 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
30" ø also available in North Texas.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION/PAGE	DATE
Hanson 48" Manhole Reducing Cone Detail	Waco Houston	TX	5.9	08-15-06

Hanson

Precast Manholes



w/ Precast Base

Section A-A

Base Slab Reinforcing

30' Deep Structure
60"ø - 6" Thick Slab min. - #5 @ 8" ea.way
72"ø - 8" Thick Slab min. - #5 @ 8" ea.way
84"ø - 8" Thick Slab min. - #5 @ 6" ea.way
96"ø - 10" Thick Slab min. - #5 @ 6" ea.way

45' Deep Structure
60"ø - 8" Thick Slab min. - #5 @ 8" ea.way
72"ø - 8" Thick Slab min. - #5 @ 8" ea.way
84"ø - 10" Thick Slab min. - #5 @ 6" ea.way
96"ø - 12" Thick Slab min. - #5 @ 6" ea.way

All Reinforcing has $1\frac{1}{2}$" cover from top of slab.



Isometric View

Materials & Features

CONCRETE: 5,000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615, Grade 60.

REINFORCING to meet AASHTO HS 20-44 Loading.

DESIGN EQUAL TO OR EXCEEDS ASTM C-478

In the event a boot is loose contact your Hanson representative to resolve.

Note:

- Inverts shall be specifically sized for connecting pipes; and shall be U-Shaped with the min. depth 3/4 of the largest pipe diameter.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
30 & 45 Ft. Depth 60" thru 96"Large Base Manhole	Houston San Antonio	TX	5.10	08-15-06	Hanson



Side View



Isometric View

Materials & Features

CONCRETE: 5,000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615 / A-185

REINFORCING to meet AASHTO HS 20-44 Loading.

BASE DESIGN EQUAL TO OR EXCEEDS ASTM C-357

RISER DESIGN EQUAL TO OR EXCEEDS ASTM C-478

In the event a boot is loose contact your Hanson representative to resolve.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION, PAGE	DATE	
Type "C" Manhole	Houston San Antonio	TX	5.11	08-15-06	Hanson



Profile **Joint Detail**

Materials & Features

CONCRETE: 5,000 PSI in 28 days.
REINFORCING STEEL: per ASTM A-615, Grade 60.
REINFORCING to meet AASHTO HS 20-44 Loading.
DESIGN EQUAL TO OR EXCEEDS ASTM C-478

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
ASTM C-478 Special Base	Houston	TX	5.12	08-15-06	Hanson

Precast Manholes



Section View
(Base configuration for 60", 72" & 84")



Isometric View

Product Dimensions			
A	B	C	D
60"			
72"			
84"			
96"			
108"			
120"			
132"			
144"			

Contact your local Hanson representative for product dimensions.



Section View
Base configuration for 96"



Section View
Base configuration for 108"-144"

Materials & Features

CONCRETE: 5,000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615 / A-185

REINFORCING to meet AASHTO HS 20-44 Loading.

BASE DESIGN EQUAL TO OR EXCEEDS ASTM C-357

RISER DESIGN EQUAL TO OR EXCEEDS ASTM C-478

(A). Hatches as specified by Engineer.

In the event a boot is loose contact your Hanson representative to resolve.

-No Scale-
All dimensions subject to allowable specification tolerances.

TITLE	PLANT	STATE	SECTION.PAGE	DATE	
Typical Wetwells - Various Diameters	All Plants	TX	5.13	08-15-06	Hanson

① "O"-Ring Gasket



Carefully clean all dirt & foreign objects from the joining surface of the bell or groove end of pipe.

Carefully clean spigot or tongue end of pipe, including the gasket recess. Inspect the bell and spigot ends of each section to make sure they are free from cracks, chips or voids that will interfere with gasket.

Improperly prepared bell and spigot surfaces may prevent homing of the pipe or keep the gasket from sealing.

②



Lubricate bell joint surface liberally, covering entire inside surface using proper pipe gasket lubricant.

③

Lubricate the gasket throughly before it is placed on the spigot or tongue.

Bell and Gasket not lubricated or improperly lubricated may cause the gasket to roll and leak or possibly damage the bell.

④



****IMPORTANT****

Fit the gasket carefully, equalizing the rubber gasket stretch by running a smooth, round object (inserted between the gasket & spigot) around the entire circumference several times.

Unequal stretch could cause bunching of the gasket and may cause leaks in the joint or crack the bell.

⑤



Align the bell & spigot to be joined. Before homing the joint, check that the gasket is in contact with the bell end entrance taper around the entire circumference.

Do not force sections together. If sections do not seat properly, unstack and contact your Hanson Sales Representative.

Improper alignment can dislodge gasket, causing leaks or possibly breaking the bell.

Profile Gasket

1. Manhole sections should be handed with extreme caution to avoid chipping of the bell or spigot ends. Proper lifting devices must be used on all sections.
2. Inspect gasket sealing area for any voids or rough edges that may interfere with the seal.
3. Place the 4-G Gasket in the step of the spigot. (Making sure that the pointed end of the gasket is toward the end of the pipe as shown in Fig A.)
4. ****IMPORTANT**** Equalize the stretch on the gasket by pulling the sealing lube away from the spigot at least one inch and then releasing the gasket. Repeat this every three or four inches around the circumference of the pipe. Equalization of stretch makes sure that the gasket has the same stretched cross-section and tension throughout. **Do not lube the gasket or spigot end of the pipe.**
5. Remove all dirt and other foreign matter from the inside surface of the bell. Apply lube to the inner surface of the bell including the lead-in taper surface on the outer edge of the bell. Align spigot with the bell. Gasket should touch lead-in taper around the entire circumference before pushing the pipe home.
6. Push the manhole section carefully, until the spigot is all the way home. (Fig B) Do not force sections together. If sections do not seat properly, unstack and contact your Hanson Sales Representative.
7. Every manhole will not come home exactly the same. Differences in application, consistency of lubricants, dimensions in the spigot and groove will cause variations in installation. If joining problems arise, please contact the manhole manufacturer immediately rather than forcing manhole sections together with subsequent damage to the manhole.
8. All testing should be performed prior to backfill of the manhole. Problems can not be detected after the manhole is backfilled. **Testing the manhole after backfill voids all warranties.**



Fig. A



Fig. B

Note: *Manholes in excess of 30' in depth must be vacuum tested prior to backfill. The loads presented by soils and possible groundwater at 30' in addition to the load from the vacuum may exceed the design capacity of the pipe to manhole connector.*

TITLE	PLANT	STATE	SECTION.PAGE	DATE
O-Ring & Profile Gasket Installation on Manholes	All Plants	TX	5.14	08-15-06

Hanson



Single Clamp



Multiple Clamps



Instructions

1. Clean pipe and boot to ensure no dirt or foreign materials are present.
2. Clamping surface on pipe must be clean and smooth.
3. Center pipe in opening and insert until pipe is at least equal to the inside plane of the manhole.
4. Attach take-up clamps(s) and stagger screw(s) of clamps(s) around the groove of the gasket so that take-up pressure will be equalized. Make sure each clamp is completely in the correct groove.
5. Using a torque ratchet or torque wrench, gradually tighten all screw(s) of clamp(s) in an alternating pattern to 60 lbs/in torque.
6. After reaching 60 lbs/in torque on final screw, check all screws again to ensure equal compression of all clamps.
7. If system is to be tested, testing shall be completed prior to backfilling, following all recommendations and requirements of the test system manufacturer. Vacuum testing shall be conducted in accordance with ASTM C-1244.
8. Adjust pipe to line and grade. Use proper bedding, backfill materials and techniques so that pipe deflection and deformation is minimized.
9. Any pipe stubs installed in the manhole must be positively restrained from movement.
10. Vacuum testing after backfill voids warranty.

For more information contact yor local Hanson Representative.



Rinker MATERIALS Moor-Tex
2735 HWY. 36 NORTH
MAILING: P.O. BOX 1088
SEALY, TEXAS 77474
PH: (979) 885-7403
(281) 375-6121
FAX:(979) 885-7001

REV.	DESCRIPTION	DATE
DATE: 8-09-02	SCALE: 3/4"=1'-0"	BY: RB

48" PRECAST CONCENTRIC MANHOLE WITH MOORBASE

JOB: 2002	FILE: 48CM	DWG. NO. 48CM

TEMPORARY STORMWATER SECTION (TCEQ-0602)

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Caleb Chance, P.E.

Date: 11/01/2024

Signature of Customer/Agent:

Regulated Entity Name: Oakwood Baptist Church

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

   ☒ The following fuels and/or hazardous substances will be stored on the site: Construction Staging Area

   These fuels and/or hazardous substances will be stored in:

   ☒ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.

☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.

☐ Fuels and hazardous substances will not be stored on the site.

2. ☒ **Attachment A - Spill Response Actions**. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.

3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.

4. ☒ **Attachment B - Potential Sources of Contamination**. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

5. ☒ **Attachment C - Sequence of Major Activities**. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.

   ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.

   ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.

6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Blieders Creek

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. ☒ **Attachment D – Temporary Best Management Practices and Measures**. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.

☐ **Attachment E - Request to Temporarily Seal a Feature**. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.

☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.

9. ☒ **Attachment F - Structural Practices**. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.

10. ☒ **Attachment G - Drainage Area Map**. A drainage area map supporting the following requirements is attached:

☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.

☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.

☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.

☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

☒ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations**. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.

☒ N/A

12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.

13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.

14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).

15. ☐ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.

16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices**. A schedule of the interim and permanent soil stabilization practices for the site is attached.

18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.

19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.

21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.

22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

ATTACHMENT A

OAKWOOD BAPTIST CHURCH
Sewage Collection System Modification Plan

Attachment A – Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. https://www.tceq.texas.gov/response/spills/spill_rq.html
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.

- Notification should first be made by telephone and followed up with a written report.

- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.

- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

ATTACHMENT B

Attachment B – Potential Sources of Contamination

Other potential sources of contamination during construction include:

Potential Source	Preventative Measure
Asphalt products used on this project.	▪ After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain.
Oil, grease, fuel, and hydraulic fluid contamination from construction equipment and vehicle dripping.	▪ Vehicle maintenance when possible, will be performed within the construction staging area. ▪ Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.
Accidental leaks or spills of oil, petroleum products, and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.	▪ Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures. ▪ Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures. ▪ Hazardous materials and wastes shall be stored in covered containers and protected from vandalism. ▪ A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.
Miscellaneous trash and litter from construction workers and material wrappings.	▪ Trash containers will be placed throughout the site to encourage proper trash disposal.
Construction debris.	▪ Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case-by-case basis.
Spills/Overflow of waste from portable toilets	▪ Portable toilets will be placed away from high-traffic vehicular areas and storm drain inlets. ▪ Portable toilets will be placed on a level ground surface. ▪ Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

ATTACHMENT C

Attachment C – Sequence of Major Activities

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include clearing and grubbing of vegetation where applicable to include additional grading outside of the sewer alignment. This will disturb approximately 8.35 acres. The second is construction activities in previously cleared areas, which will include construction of sewer trenches, installation of sewer manholes, pipe, backfilling, and site cleanup, including removal of excess material. This will disturb approximately 2.80 acres as noted by the 50' sewer envelope.

ATTACHMENT D

Attachment D – Temporary Best Management Practices and Measures

a. A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

No upgradient water will cross the site. Upgradient water will be intercepted through earthen channels around the site. All TBMPs are adequate for the drainage areas they serve.

b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) Installation of gravel bags and drain inlet protection at inlets and downgradient areas of construction activities for sediment control (4) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (5) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.

ATTACHMENT F

Attachment F – Structural Practices

The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 2 and illustrated in Exhibit 3.
- Installation of gravel bags and drain inlet protection at inlets and downgradient areas of construction activities, as located on Exhibit 2 and illustrated in Exhibit 3.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 2, and illustrated on Exhibit 3.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

- Installation of concrete truck washout pit(s), as required and located on Exhibit 2 and illustrated on Exhibit 3.

ATTACHMENT G

Attachment G – Drainage Area Map

No more than ten (10) acres will be disturbed within a common drainage area at one time as construction of civil infrastructure (utilities, roads, drainage, etc.) will precede home building construction. All TBMPs utilized are adequate for the drainage areas served.

ATTACHMENT I

Attachment I – Inspections

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.

OAKWOOD BAPTIST CHURCH
Sewage Collection System Modification Plan

Pollution Prevention Measure	Inspected in Compliance	Corrective Action Required	
		Description (use additional sheet if necessary)	Date Completed
Best Management Practices			
Natural vegetation buffer strips			
Temporary vegetation			
Permanent vegetation			
Sediment control basin			
Silt fences			
Rock berms			
Gravel filter bags			
Drain inlet protection			
Other structural controls			
Vehicle exits (off-site tracking)			
Material storage areas (leakage)			
Equipment areas (leaks, spills)			
Concrete washout pit (leaks, failure)			
General site cleanliness			
Trash receptacles			
Evidence of Erosion			
Site preparation			
Roadway or parking lot construction			
Utility construction			
Drainage construction			
Building construction			
Major Observations			
Sediment discharges from site			
BMPs requiring maintenance			
BMPs requiring modification			
Additional BMPs required			

_____ A brief statement describing the qualifications of the inspector is included in this SWP3.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

"I further certify I am an authorized signatory in accordance with the provisions of 30 TAC §305.128."

Inspector's Name _____ Inspector's Signature _____ Date _____

PROJECT MILESTONE DATES

Date when major site grading activities begin:

Construction Activity	Date
Installation of BMPs	

Dates when construction activities temporarily or permanently cease on all or a portion of the project:

Construction Activity	Date

Dates when stabilization measures are initiated:

Stabilization Activity	Date
Removal of BMPs	

ATTACHMENT J

Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.

EXHIBIT 2
Storm Water Pollution Prevention Temporary Water Pollution Abatement Plan

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY WATER POLLUTION ABATEMENT PLAN GENERAL CONSTRUCTION NOTES

1. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
   - THE NAME OF THE APPROVED PROJECT;
   - THE ACTIVITY START DATE; AND
   - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.

2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROJECT MUST BE PROVIDED WITH COMPLETE COPIES OF THE APPROVED WATER POLLUTION ABATEMENT PLAN (WPAP) AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS ARE REQUIRED TO KEEP ON-SITE COPIES OF THE APPROVED PLAN AND APPROVAL LETTER.

3. IF ANY SENSITIVE FEATURE(S) (CAVES, SOLUTION CAVITY, SINK HOLE, ETC.) IS DISCOVERED DURING CONSTRUCTION, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPROPRIATE TCEQ REGIONAL OFFICE MUST BE IMMEDIATELY NOTIFIED OF ANY SENSITIVE FEATURES ENCOUNTERED DURING CONSTRUCTION. CONSTRUCTION ACTIVITIES MAY NOT BE RESUMED UNTIL THE TCEQ HAS REVIEWED AND APPROVED THE APPROPRIATE PROTECTIVE MEASURES IN ORDER TO PROTECT ANY SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY.

4. NO TEMPORARY OR PERMANENT HAZARDOUS SUBSTANCE STORAGE TANK SHALL BE INSTALLED WITHIN 150 FEET OF A WATER SUPPLY SOURCE, DISTRIBUTION SYSTEM, WELL, OR SENSITIVE FEATURE.

5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED PLANS AND MANUFACTURERS SPECIFICATIONS. IF INSPECTIONS INDICATE A CONTROL HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE APPLICANT MUST REPLACE OR MODIFY THE CONTROL FOR SITE SITUATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.

6. ANY SEDIMENT THAT ESCAPES THE CONSTRUCTION SITE MUST BE COLLECTED AND PROPERLY DISPOSED OF BEFORE THE NEXT RAIN EVENT TO ENSURE IT IS NOT WASHED INTO SURFACE STREAMS, SENSITIVE FEATURES, ETC.

7. SEDIMENT MUST BE REMOVED FROM THE SEDIMENT TRAPS OR SEDIMENTATION BASINS NOT LATER THAN WHEN IT OCCUPIES 50% OF THE BASIN'S DESIGN CAPACITY.

8. LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BEING DISCHARGED OFFSITE.

9. ALL SPOILS (EXCAVATED MATERIAL) GENERATED FROM THE PROJECT SITE MUST BE STORED ON-SITE WITH PROPER E&S CONTROLS. FOR STORAGE OR DISPOSAL OF SPOILS AT ANOTHER SITE ON THE EDWARDS AQUIFER RECHARGE ZONE, THE OWNER OF THE SITE MUST RECEIVE APPROVAL OF A WATER POLLUTION ABATEMENT PLAN FOR THE PLACEMENT OF FILL MATERIAL OR MASS GRADING PRIOR TO THE PLACEMENT OF SPOILS AT THE OTHER SITE.

10. IF PORTIONS OF THE SITE WILL HAVE A TEMPORARY OR PERMANENT CEASE IN CONSTRUCTION ACTIVITY LASTING LONGER THAN 14 DAYS, SOIL STABILIZATION IN THOSE AREAS SHALL BE INITIATED AS SOON AS POSSIBLE PRIOR TO THE 14TH DAY OF INACTIVITY. IF ACTIVITY WILL RESUME PRIOR TO THE 21ST DAY, STABILIZATION MEASURES ARE NOT REQUIRED. IF DROUGHT CONDITIONS OR INCLEMENT WEATHER PREVENT ACTION BY THE 14TH DAY, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE.

11. THE FOLLOWING RECORDS SHALL BE MAINTAINED AND MADE AVAILABLE TO THE TCEQ UPON REQUEST:
   - THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR;
   - THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; AND
   - THE DATES WHEN STABILIZATION MEASURES ARE INITIATED.

12. THE HOLDER OF ANY APPROVED EDWARD AQUIFER PROTECTION PLAN MUST NOTIFY THE APPROPRIATE REGIONAL OFFICE IN WRITING AND OBTAIN APPROVAL FROM THE EXECUTIVE DIRECTOR PRIOR TO INITIATING ANY OF THE FOLLOWING:
   A. ANY PHYSICAL OR OPERATIONAL MODIFICATION OF ANY WATER POLLUTION ABATEMENT STRUCTURE(S), INCLUDING BUT NOT LIMITED TO PONDS, DAMS, BERMS, SEWAGE TREATMENT PLANTS, AND DIVERSIONARY STRUCTURES;
   B. ANY CHANGE IN THE NATURE OR CHARACTER OF THE REGULATED ACTIVITY FROM THAT WHICH WAS ORIGINALLY APPROVED OR A CHANGE WHICH WOULD SIGNIFICANTLY IMPACT THE ABILITY OF THE PLAN TO PREVENT POLLUTION OF THE EDWARDS AQUIFER;
   C. ANY DEVELOPMENT OF LAND PREVIOUSLY IDENTIFIED AS UNDEVELOPED IN THE ORIGINAL WATER POLLUTION ABATEMENT PLAN.

SAN ANTONIO REGIONAL OFFICE
14250 JUDSON ROAD
SAN ANTONIO, TEXAS 78233-4480
PHONE (210) 490-3096
FAX (210) 545-4329



SCALE: 1"= 100'
0' 100' 200' 300'

LEGEND

GEOLOGIC FORMATION

Kpcm	CYLIC MARINE (PERSON FORMATION)
Kplc	PERSON FORMATION
S-1	POTENTIAL RECHARGE FEATURE



LOCATION MAP

NOT-TO-SCALE

LEGAL DESCRIPTION:
LOT: 1R, BLOCK: 1,
(PLAT DOC. NO. 200806032437)

ADDRESS:
2154 LOOP 337
NEW BRAUNFELS, TEXAS 78130

LEGEND

- PROJECT LIMITS
- 976 EXISTING CONTOUR
- 970 PROPOSED CONTOUR
- FLOW ARROW (EXISTING)
- FLOW ARROW (PROPOSED)
- SILT FENCE
- ROCK BERM
- GRAVEL FILTER BAGS
- GRATE INLET PROTECTION
- SEDIMENT CONTROL ROLLS
- LIMITS OF DISTURBED AREA
- STABILIZED CONSTRUCTION ENTRANCE/EXIT (FIELD LOCATE)
- CONSTRUCTION EQUIPMENT, VEHICLE & MATERIALS STORAGE AREA (FIELD LOCATE)
- CONCRETE TRUCK WASH-OUT PIT (FIELD LOCATE)
- 50' NATURAL VEGETATIVE BUFFER

GENERAL NOTES

1. DO NOT DISTURB VEGETATED AREAS (TREES, GRASS, WEEDS, BRUSH, ETC.) ANY MORE THAN NECESSARY FOR CONSTRUCTION.

2. CONSTRUCTION ENTRANCE/EXIT LOCATION, CONCRETE WASH-OUT PIT, AND CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD TO BE DETERMINED IN THE FIELD.

3. STORM WATER POLLUTION PREVENTION CONTROLS MAY NEED TO BE MODIFIED IN THE FIELD TO ACCOMPLISH THE DESIRED EFFECT. ALL MODIFICATIONS ARE TO BE NOTED ON THIS EXHIBIT AND SIGNED AND DATED BY THE RESPONSIBLE PARTY.

4. RESTRICT ENTRY/EXIT TO THE PROJECT SITE TO DESIGNATED LOCATIONS BY USE OF ADEQUATE FENCING, IF NECESSARY.

5. ALL STORM WATER POLLUTION PREVENTION CONTROLS ARE TO BE MAINTAINED AND IN WORKING CONDITIONS AT ALL TIMES.

6. FOR A COMPLETE LISTING OF TEMPORARY STORM WATER POLLUTION PREVENTION CONTROLS REFER TO THE TPDES STORM WATER POLLUTION PREVENTION PLAN.

7. STORM WATER POLLUTION PREVENTION STRUCTURES SHOULD BE CONSTRUCTED WITHIN THE SITE BOUNDARIES. SOME OF THESE FEATURES MAY BE SHOWN OUTSIDE THE SITE BOUNDARIES ON THIS PLAN FOR VISUAL CLARITY.

8. AS SOON AS PRACTICAL, ALL DISTURBED SOIL THAT WILL NOT BE COVERED BY IMPERVIOUS COVER SUCH AS PARKWAY AREAS, EASEMENT AREAS, EMBANKMENT SLOPES, ETC. WILL BE STABILIZED PER APPLICABLE PROJECT SPECIFICATIONS.

9. BEST MANAGEMENT PRACTICES MAY BE INSTALLED IN STAGES TO COINCIDE WITH THE DISTURBANCE OF UPGRADIENT AREAS.

10. BEST MANAGEMENT PRACTICES MAY BE REMOVED IN STAGES ONCE THE WATERSHED FOR THAT PORTION CONTROLLED BY THE BEST MANAGEMENT PRACTICES HAS BEEN STABILIZED IN ACCORDANCE WITH TPDES REQUIREMENTS.

11. UPON COMPLETION OF THE PROJECT, INCLUDING SITE STABILIZATION, AND BEFORE FINAL PAYMENT IS ISSUED, CONTRACTOR SHALL REMOVE ALL SEDIMENT AND EROSION CONTROL MEASURES, PAYING SPECIAL ATTENTION TO ROCK BERMS IN DRAINAGE FEATURES.

12. WHERE VEGETATED FILTER STRIPS ARE INDICATED, CONTRACTOR SHALL VERIFY THAT SUFFICIENT VEGETATION EXISTS, OTHERWISE CONTRACTOR SHALL PLACE SILT FENCING IN LIEU OF VEGETATED FILTER STRIP.

13. SHADED AREA ▭ DENOTES LIMITS OF DISTURBED AREAS. OTHER AREAS WITHIN THE PROJECT LIMITS, WITH THE EXCEPTION OF A CONSTRUCTION EQUIPMENT AND MATERIAL STORAGE YARD, ARE NOT A PART OF THIS TPDES STORM WATER POLLUTION PREVENTION PLAN (SWP3) AND WILL NOT BE DISTURBED BY CIVIL CONSTRUCTION ACTIVITIES. HOUSE CONSTRUCTION ACTIVITIES WILL REQUIRE A SEPARATE STORM WATER POLLUTION PREVENTION PLAN.

14. PRIOR TO BEGINNING CONSTRUCTION, CONTRACTOR SHALL COORDINATE PLACEMENT OF TEMPORARY BEST MANAGEMENT PRACTICES WITHIN TXDOT RIGHT-OF-WAY WITH TXDOT.

15. CPS ENERGY MAY FUNCTION AS A SECONDARY OPERATOR ON THIS PROJECT AND MAY BE INSTALLING ELECTRIC UTILITIES FOR ON-SITE CONSTRUCTION AND OFF-SITE FEED TO THE PROJECT.

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES-STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

EXHIBIT 2

TEMPORARY BMP MODIFICATIONS

DATE	SIGNATURE	DESCRIPTION

NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED PROFESSIONAL ENGINEER
8/27/24

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #100288-00

OAKWOOD BAPTIST CHURCH
NEW BRAUNFELS, TEXAS

STORM WATER POLLUTION PREVENTION
TEMPORARY WATER POLLUTION ABATEMENT PLAN

PLAT NO. -
JOB NO. 11863-02
DATE AUGUST 2024
DESIGNER RG
CHECKED BL DRAWN RG
SHEET C0.20

Date: Sep 16, 2024, 10:50am User ID: lfigarro
File: P:\118\63\02\Design\Civil\TM-1186302.dwg

EXHIBIT 3
Storm Water Pollution Prevention Details
Typical Details



SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT



SECTION "A-A" OF A CONSTRUCTION ENTRANCE/EXIT

MATERIALS

1. THE AGGREGATE SHOULD CONSIST OF 4–INCH TO 8–INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN.

2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF 8–INCHES.

3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD², A MULLEN BURST RATING OF 140 LB/IN², AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.

4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4–INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OR BASIN.

INSTALLATION

1. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE.

2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER.

3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG.

4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE, 6–INCHES TO 8–INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.

6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPE FOR DRAINAGE.

7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.

8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD DRAINAGE.

COMMON TROUBLE POINTS

1. INADEQUATE RUNOFF CONTROL–SEDIMENT WASHES ONTO PUBLIC ROAD.

2. STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY CONDITION AS STONE IS PRESSED INTO SOIL.

3. PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC–EXTEND PAD BEYOND THE MINIMUM 50–FOOT LENGTH AS NECESSARY.

4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD.

5. UNSTABLE FOUNDATION – USE GEOTEXTILE FABRIC UNDER PAD AND/OR IMPROVE FOUNDATION DRAINAGE.

INSPECTION AND MAINTENANCE GUIDELINES

1. THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION, WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS–OF–WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS–OF–WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR.

3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT–OF–WAY.

4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.

STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

NOT–TO–SCALE



ISOMETRIC PLAN VIEW

SECTION "A-A"

ROCK BERMS

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT–LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.

2. REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.

3. REPAIR ANY LOOSE WIRE SHEATHING.

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION.

5. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

MATERIALS

1. THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT RINGS.

2. CLEAN, OPEN GRADED 3–INCH TO 5–INCH DIAMETER ROCK SHOULD BE USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5–INCH TO 8–INCH DIAMETER ROCKS MAY BE USED.

INSTALLATION

1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE. THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH OPENINGS.

2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES BEING 2:1 (H:V) OR FLATTER.

3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18".

4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.

5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE OR AS NEAR AS POSSIBLE.

6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4 INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.

COMMON TROUBLE POINTS

1. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

ROCK BERM DETAIL

NOT–TO–SCALE



LAY SOD IN A STAGGERED PATTERN. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER. DO NOT LEAVE SPACES AND DO NOT OVERLAP. A SHARPENED MASON'S TROWEL IS A HANDY TOOL FOR TUCKING DOWN THE ENDS AND TRIMMING PIECES.

BUTTING – ANGLED ENDS CAUSED BY THE AUTOMATIC SOD CUTTER MUST BE MATCHED CORRECTLY.



APPEARANCE OF GOOD SOD

NOTES:
1. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE SOIL.

2. WATER TO A DEPTH OF 4" AS NEEDED. WATER WELL AS SOON AS THE SOD IS LAID.

3. MOW WHEN THE SOD IS ESTABLISHED – IN 2–3 WEEKS. SET THE MOWER HIGH (2"–3").



SOD INSTALLATION





USE PEGS OR STAPLES TO FASTEN SOD FIRMLY – AT THE ENDS OF STRIPS AND IN THE CENTER, OR EVERY 3–4 FEET IF THE STRIPS ARE LONG. WHEN READY TO MOW, DRIVE PEGS OR STAPLES FLUSH WITH THE GROUND.

MATERIALS

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH (± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE SHOOT GROWTH AND THATCH.

2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND LENGTH, WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%. TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.

3. STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.

4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD OF 36 HOURS.

SITE PREPARATION

1. PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.

2. THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.

3. FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

INSTALLATION IN CHANNELS

1. SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS TIGHTLY (SEE FIGURE ABOVE).

2. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL AREAS.

GENERAL INSTALLATION (VA. DEPT. OF CONSERVATION, 1992)

1. SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN.

2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND REDUCE ROOT BURNING AND DIEBACK.

3. THE FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS (SEE FIGURE ABOVE).

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM, SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OR OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).

5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL.

6. AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS THOROUGHLY WET.

7. UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4 INCHES.

8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2–3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

INSPECTION AND MAINTENANCE GUIDELINES

1. SOD SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS SOON AS PRACTICAL.

SOD INSTALLATION DETAIL

NOT–TO–SCALE



ISOMETRIC PLAN VIEW

SILT FENCE

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER–BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

MATERIALS

1. SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

2. FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y–BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS EXCEEDING 140.

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN–SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.

5. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE POST. THERE SHOULD BE A 3–FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

COMMON TROUBLE POINTS

1. FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO CONCENTRATE AND FLOW OVER THE FENCE.

2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER FENCE).

3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND SIDES).

4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW (RUNOFF OVERTOPS OR COLLAPSES FENCE).

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL.

2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.

3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL TO THE TORN SECTION.

4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

5. WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

SILT FENCE DETAIL

NOT–TO–SCALE



PLAN VIEW

SECTION "A-A"

GENERAL NOTES

1. CONTRACTOR TO INSTALL 2"x4"–W1.4xW1.4 WIRE MESH SUPPORTING FILTER FABRIC OVER THE INLET OPENING. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR WIRE TIES AT THIS LOCATION. SAND BAGS FILLED WITH WASHED PEA GRAVEL SHOULD BE PLACED ON TOP OF WIRE MESH ON TOP OF THE INLET AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SANDBAGS FILLED WITH WASHED PEA GRAVEL SHOULD ALSO BE PLACED ALONG THE GUTTER AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SAND BAGS TO BE STACKED TO FORM A CONTINUOUS BARRIER AROUND INLETS.

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.

2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.

3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND CURB.

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING.

5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

BAGGED GRAVEL CURB INLET PROTECTION DETAIL

NOT–TO–SCALE



PLAN VIEW

SECTION "A-A"

GENERAL NOTES

1. THE SANDBAGS SHOULD BE FILLED WITH WASHED PEA GRAVEL AND STACKED TO FORM A CONTINUOUS BARRIER ABOUT 1 FOOT HIGH AROUND INLETS.

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.

INSPECTION AND MAINTENANCE GUIDELINES

1. INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.

2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MATTER THAT IT WILL NOT ERODE.

3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND CURB.

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING.

5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

BAGGED GRAVEL GRATE INLET PROTECTION DETAIL

NOT–TO–SCALE



PLAN VIEW



SECTION "A-A"

GENERAL NOTES

1. DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.

2. WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.

3. WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.

4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES.

5. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.

MATERIALS

PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

MAINTENANCE

1. WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF.

2. MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED OF.

3. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.

CONCRETE TRUCK WASHOUT PIT DETAIL

NOT–TO–SCALE



PLAN VIEW

SECTION "A-A"

NOTES:
1. THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70%.

2. THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER).

3. SAND SHALL NOT BE USED TO FILL THE FILTER BAGS.

GRAVEL FILTER BAG DETAIL

NOT–TO–SCALE



CONSTRUCTION STAGING AREA

NOT–TO–SCALE

THE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE TPDES–STORM WATER POLLUTION PREVENTION PLAN (SWP3) REGULATIONS.

THIS SHEET HAS BEEN PREPARED FOR PURPOSES OF THE SWP3 ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN THE CIVIL IMPROVEMENT PLANS.

EXHIBIT 3

NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED
PROFESSIONAL ENGINEER
8/27/24

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #10028800

OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS

STORM WATER POLLUTION PREVENTION DETAILS
TYPICAL DETAILS

PLAT NO. –
JOB NO. 11863–02
DATE AUGUST 2024
DESIGNER RG
CHECKED BL DRAWN GM
SHEET C0.30

Date: Sep 16, 2024, 10:50am User ID: lfcorro
File: P:\11863\03\02\Design\Civil\TPDT–11863102.dwg

AGENT AUTHORIZATION FORM (TCEQ-0599)

Agent Authorization Form
For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

I Roxi Vanstory,
Print Name

Executive Administrator,
Title - Owner/President/Other

of Oakwood Baptist Church,
Corporation/Partnership/Entity Name

have authorized **Pape-Dawson Engineers, Inc.**
Print Name of Agent/Engineer

of **Pape-Dawson Engineers, Inc.**
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to $10,000 per day per violation.

2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.

3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.

4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.

5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Roxi Vanstory
Applicant's Signature

10/8/24
Date

THE STATE OF Texas §

County of Comal §

BEFORE ME, the undersigned authority, on this day personally appeared Roxi Vanstory known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 8 day of October, 2024.

Rhonda L. Jones
NOTARY PUBLIC

RHONDA L JONES
Notary ID #6445251
My Commission Expires
July 5, 2026

Rhonda L. Jones
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 7/5/2026

APPLICATION FEE FORM (TCEQ-0574)

Application Fee Form

Texas Commission on Environmental Quality
Name of Proposed Regulated Entity: Oakwood Baptist Church Expansion
Regulated Entity Location: 2154 Loop 337, New Braunfels, Texas 78130
Name of Customer: Oakwood Baptist Church
Contact Person: Roxi Vanstory Phone: (830) 625-0267
Customer Reference Number (if issued):CN 601399199
Regulated Entity Reference Number (if issued):RN 102744802

Austin Regional Office (3373)

☐ Hays ☐ Travis ☐ Williamson

San Antonio Regional Office (3362)

☐ Bexar ☐ Medina ☐ Uvalde
☒ Comal ☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment**. This payment is being submitted to:

☐ Austin Regional Office
☐ Mailed to: TCEQ - Cashier
Revenues Section
Mail Code 214
P.O. Box 13088
Austin, TX 78711-3088

☒ San Antonio Regional Office
☐ Overnight Delivery to: TCEQ - Cashier
12100 Park 35 Circle
Building A, 3rd Floor
Austin, TX 78753
(512)239-0357

Site Location (Check All That Apply):

☒ Recharge Zone ☐ Contributing Zone ☐ Transition Zone

Type of Plan	*Size*	*Fee Due*
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	Acres	$
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	$
Sewage Collection System	1159 L.F.	$ 650
Lift Stations without sewer lines	Acres	$
Underground or Aboveground Storage Tank Facility	Tanks	$
Piping System(s)(only)	Each	$
Exception	Each	$
Extension of Time	Each	$

Signature: 

Date: 10/03/2024

Application Fee Schedule

Texas Commission on Environmental Quality
Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	*Project Area in Acres*	*Fee*
One Single Family Residential Dwelling	< 5	$650
Multiple Single Family Residential and Parks	< 5 5 < 10 10 < 40 40 < 100 100 < 500 ≥ 500	$1,500 $3,000 $4,000 $6,500 $8,000 $10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1 1 < 5 5 < 10 10 < 40 40 < 100 ≥ 100	$3,000 $4,000 $5,000 $6,500 $8,000 $10,000

Organized Sewage Collection Systems and Modifications

Project	*Cost per Linear Foot*	*Minimum Fee-Maximum Fee*
Sewage Collection Systems	$0.50	$650 - $6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	*Cost per Tank or Piping System*	*Minimum Fee-Maximum Fee*
Underground and Aboveground Storage Tank Facility	$650	$650 - $6,500

Exception Requests

Project	*Fee*
Exception Request	$500

Extension of Time Requests

Project	***Fee***
Extension of Time Request	$150

CORE DATA FORM
(TCEQ-10400)

TCEQ Core Data Form

TCEQ Use Only

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (*If other is checked please describe in space provided.*)

☒ New Permit, Registration or Authorization (*Core Data Form should be submitted with the program application.*)

☐ Renewal (*Core Data Form should be submitted with the renewal form*) ☐ Other

2. Customer Reference Number *(if issued)*	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number *(if issued)*
CN 601399199		RN

SECTION II: Customer Information

4. General Customer Information | **5. Effective Date for Customer Information Updates** (mm/dd/yyyy)

☐ New Customer ☐ Update to Customer Information ☐ Change in Regulated Entity Ownership
☐ Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)

The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).

6. Customer Legal Name (*If an individual, print last name first: eg: Doe, John*) *If new Customer, enter previous Customer below:*

Oakwood Baptist Church

7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number *(if applicable)*

11. Type of Customer: ☐ Corporation ☐ Individual Partnership: ☐ General ☐ Limited
Government: ☐ City ☐ County ☐ Federal ☐ State ☐ Other ☐ Sole Proprietorship ☐ Other:

12. Number of Employees
☐ 0-20 ☐ 21-100 ☐ 101-250 ☐ 251-500 ☐ 501 and higher

13. Independently Owned and Operated?
☐ **Yes** ☐ **No**

14. Customer Role (Proposed or Actual) – *as it relates to the Regulated Entity listed on this form. Please check one of the following*

☐ Owner ☐ Operator ☐ Owner & Operator
☐ Occupational Licensee ☐ Responsible Party ☐ Voluntary Cleanup Applicant ☐ Other:

15. Mailing Address: 2154 Loop 337

City	New Braunfels	State	TX	ZIP	78130	ZIP + 4	

16. Country Mailing Information *(if outside USA)*	17. E-Mail Address *(if applicable)*

18. Telephone Number	19. Extension or Code	20. Fax Number *(if applicable)*
(830) 625-0267		(830) 625-1151

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (*If 'New Regulated Entity" is selected below this form should be accompanied by a permit application*)

☐ New Regulated Entity ☐ Update to Regulated Entity Name ☒ Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (*Enter name of the site where the regulated action is taking place.*)

23. Street Address of the Regulated Entity: *(No PO Boxes)*	2154 Loop 337							
	City	NewBraunfels	**State**	TX	**ZIP**	78130	**ZIP + 4**	
24. County								

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:								
26. Nearest City						**State**		**Nearest ZIP Code**

27. Latitude (N) In Decimal:	29.726688 N			**28. Longitude (W) In Decimal:**	-98.141921 W			
Degrees	Minutes		Seconds	Degrees		Minutes		Seconds
29	43		36.07	-98		8		30.92

29. Primary SIC Code (4 digits)	**30. Secondary SIC Code** (4 digits)	**31. Primary NAICS Code** (5 or 6 digits)	**32. Secondary NAICS Code** (5 or 6 digits)
8661		813110	

33. What is the Primary Business of this entity? *(Do not repeat the SIC or NAICS description.)*

34. Mailing Address:	**2154 Loop 337**							
	City	**New Braunfels**	**State**	**TX**	**ZIP**	**78130**	**ZIP + 4**	
35. E-Mail Address:								

36. Telephone Number	**37. Extension or Code**	**38. Fax Number** *(if applicable)*
(830) 625-267		**(830) 625-1151**

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

☐ Dam Safety	☐ Districts	☐ Edwards Aquifer	☐ Emissions Inventory Air	☐ Industrial Hazardous Waste
☐ Municipal Solid Waste	☐ New Source Review Air	☐ OSSF	☐ Petroleum Storage Tank	☐ PWS
☐ Sludge	☐ Storm Water	☐ Title V Air	☐ Tires	☐ Used Oil
☐ Voluntary Cleanup	☐ Waste Water	☐ Wastewater Agriculture	☐ Water Rights	☐ Other:

SECTION IV: Preparer Information

40. Name:	Jean Autrey, P.E., CESSWI	**41. Title:**	Project Manager

42. Telephone Number	**43. Ext./Code**	**44. Fax Number**	**45. E-Mail Address**
(210) 375-9000		(210) 975-9010	jautrey@pape-dawson.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Pape-Dawson Consulting Engineers, LLC	**Job Title:**	Vice President
Name *(In Print):*	Caleb Chance, P.E.	**Phone:**	(210) 375 - 9000
Signature:		**Date:**	11/1/24

FINAL PLAN AND PROFILE SHEETS

TCEQ - ORGANIZED SEWAGE COLLECTION SYSTEM GENERAL CONSTRUCTION NOTES

1. THIS ORGANIZED SEWAGE COLLECTION SYSTEM (SCS) MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.5(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S (TCEQ) EDWARDS AQUIFER RULES AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.

2. ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROPOSED REGULATED PROJECT MUST BE PROVIDED WITH COPIES OF THE SCS PLAN AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES, THE CONTRACTORS MUST BE REQUIRED TO KEEP ON-SITE COPIES OF THE PLAN AND THE APPROVAL LETTER.

3. A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES. THIS NOTICE MUST INCLUDE:
   - THE NAME OF THE APPROVED PROJECT;
   - THE ACTIVITY START DATE; AND
   - THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.

4. ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED SCS APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF AN SCS APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND APPROVAL.

5. PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.

6. IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERED. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING AND THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRUCTURAL INTEGRITY OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.

7. SEWER LINES LOCATED WITHIN OR CROSSING THE 5-YEAR FLOODPLAIN OF A DRAINAGE WAY WILL BE PROTECTED FROM INUNDATION AND STREAM VELOCITIES WHICH COULD CAUSE EROSION AND SCOURING OF BACKFILL. THE TRENCH MUST BE CAPPED WITH CONCRETE TO PREVENT SCOURING OF BACKFILL, OR THE SEWER LINES MUST BE ENCASED IN CONCRETE. ALL CONCRETE SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES.

8. BLASTING PROCEDURES FOR PROTECTION OF EXISTING SEWER LINES AND OTHER UTILITIES WILL BE IN ACCORDANCE WITH THE NATIONAL FIRE PROTECTION ASSOCIATION CRITERIA. SAND IS NOT ALLOWED AS BEDDING OR BACKFILL IN TRENCHES THAT HAVE BEEN BLASTED. IF ANY EXISTING SEWER LINES ARE DAMAGED, THE LINES MUST BE REPAIRED AND RETESTED.

9. ALL MANHOLES CONSTRUCTED OR REHABILITATED ON THIS PROJECT MUST HAVE WATERTIGHT SIZE ON SIZE RESILIENT CONNECTORS ALLOWING FOR DIFFERENTIAL SETTLEMENT. IF MANHOLES ARE CONSTRUCTED WITHIN THE 100-YEAR FLOODPLAIN, THE COVER MUST HAVE A GASKET AND BE BOLTED TO THE RING. WHERE GASKETED MANHOLE COVERS ARE REQUIRED FOR MORE THAN THREE MANHOLES IN SEQUENCE OR FOR MORE THAN 1500 FEET, ALTERNATE MEANS OF VENTING WILL BE PROVIDED. BRICKS ARE NOT AN ACCEPTABLE CONSTRUCTION MATERIAL FOR ANY PORTION OF THE MANHOLE.

   THE DIAMETER OF THE MANHOLES MUST BE A MINIMUM OF FOUR FEET AND THE MANHOLE FOR ENTRY MUST HAVE A MINIMUM CLEAR OPENING DIAMETER OF 30 INCHES. THESE DIMENSIONS AND OTHER DETAILS SHOWING COMPLIANCE WITH THE COMMISSION'S RULES CONCERNING MANHOLES AND SEWER LINE/MANHOLE INVERTS DESCRIBED IN 30 TAC §217.55 ARE INCLUDED ON PLAN SHEET C4.05.

   IT IS SUGGESTED THAT ENTRANCE INTO MANHOLES IN EXCESS OF FOUR FEET DEEP BE ACCOMPLISHED BY MEANS OF A PORTABLE LADDER. THE INCLUSION OF STEPS IN A MANHOLE IS PROHIBITED.

10. WHERE WATER LINES AND NEW SEWER LINE ARE INSTALLED WITH A SEPARATION DISTANCE CLOSER THAN NINE FEET (I.E., WATER LINES CROSSING WASTEWATER LINES, WATER LINES PARALLELING WASTEWATER LINES, OR WATER LINES NEXT TO MANHOLES) THE INSTALLATION MUST MEET THE REQUIREMENTS OF 30 TAC §217.53(D) (PIPE DESIGN) AND 30 TAC §290.44(E) (WATER DISTRIBUTION).

11. WHERE SEWERS LINES DEVIATE FROM STRAIGHT ALIGNMENT AND UNIFORM GRADE ALL CURVATURE OF SEWER PIPE MUST BE ACHIEVED BY THE FOLLOWING PROCEDURE WHICH IS RECOMMENDED BY THE PIPE MANUFACTURER: N/A

    IF PIPE FLEXURE IS PROPOSED, THE FOLLOWING METHOD OF PREVENTING DEFLECTION OF THE JOINT MUST BE USED: N/A

    SPECIFIC CARE MUST BE TAKEN TO ENSURE THAT THE JOINT IS PLACED IN THE CENTER OF THE TRENCH AND PROPERLY BEDDED IN ACCORDANCE WITH 30 TAC §217.54.

12. NEW SEWAGE COLLECTION SYSTEM LINES MUST BE CONSTRUCTED WITH STUB OUTS FOR THE CONNECTION OF ANTICIPATED EXTENSIONS. THE LOCATION OF SUCH STUB OUTS MUST BE MARKED ON THE GROUND SUCH THAT THEIR LOCATION CAN BE EASILY DETERMINED AT THE TIME OF CONNECTION OF THE EXTENSIONS. SUCH STUB OUTS MUST BE MANUFACTURED WYES OR TEES THAT ARE COMPATIBLE IN SIZE AND MATERIAL WITH BOTH THE SEWER LINE AND THE EXTENSION. AT THE TIME OF ORIGINAL CONSTRUCTION, NEW STUB-OUTS MUST BE CONSTRUCTED SUFFICIENTLY TO EXTEND BEYOND THE END OF THE STREET PAVEMENT. ALL STUB-OUTS MUST BE SEALED WITH A MANUFACTURED CAP TO PREVENT LEAKAGE. EXTENSIONS THAT WERE NOT ANTICIPATED AT THE TIME OF ORIGINAL CONSTRUCTION OR THAT ARE TO BE CONNECTED TO AN EXISTING SEWER LINE NOT FURNISHED WITH STUB OUTS MUST BE CONNECTED USING A MANUFACTURED SADDLE AND IN ACCORDANCE WITH ACCEPTED PLUMBING TECHNIQUES.

    IF NO STUB-OUT IS PRESENT AN ALTERNATE METHOD OF JOINING LATERALS IS SHOWN IN THE DETAIL ON SHEET C3.04. (FOR POTENTIAL FUTURE LATERALS).

    THE PRIVATE SERVICE LATERAL STUB-OUTS MUST BE INSTALLED AS SHOWN ON THE PLAN AND PROFILE SHEETS ON PLAN SHEET C4.01 TO C4.04 AND MARKED AFTER BACKFILLING AS SHOWN IN THE DETAIL ON PLAN SHEET C3.03

13. TRENCHING, BEDDING AND BACKFILL MUST CONFORM WITH 30 TAC §217.54. THE BEDDING AND BACKFILL FOR FLEXIBLE PIPE MUST COMPLY WITH THE STANDARDS OF ASTM D-2321, CLASSES IA, IB, II OR III. RIGID PIPE BEDDING MUST COMPLY WITH THE REQUIREMENTS OF ASTM C 12 (ANSI A 106.2) CLASSES A, B OR C.

14. SEWER LINES MUST BE TESTED FROM MANHOLE TO MANHOLE. WHEN A NEW SEWER LINE IS CONNECTED TO AN EXISTING STUB OR CLEAN-OUT, IT MUST BE TESTED FROM EXISTING MANHOLE TO NEW MANHOLE. IF A STUB OR CLEAN-OUT IS USED AT THE END OF THE PROPOSED SEWER LINE, NO PRIVATE SERVICE ATTACHMENTS MAY BE CONNECTED BETWEEN THE LAST MANHOLE AND THE CLEANOUT UNLESS IT CAN BE CERTIFIED AS CONFORMING WITH THE PROVISIONS OF 30 TAC §213.5(C)(3)(E).

15. ALL SEWER LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC §217.57. THE ENGINEER MUST RETAIN COPIES OF ALL TEST RESULTS WHICH MUST BE MADE AVAILABLE TO THE EXECUTIVE DIRECTOR UPON REQUEST. THE ENGINEER MUST CERTIFY IN WRITING THAT ALL WASTEWATER LINES HAVE PASSED ALL REQUIRED TESTING TO THE APPROPRIATE REGIONAL OFFICE WITHIN 30 DAYS OF TEST COMPLETION AND PRIOR TO USE OF THE NEW COLLECTION SYSTEM. TESTING METHOD WILL BE:

(a) FOR A COLLECTION SYSTEM PIPE THAT WILL TRANSPORT WASTEWATER BY GRAVITY FLOW, THE DESIGN MUST SPECIFY AN INFILTRATION AND EXFILTRATION TEST OR A LOW-PRESSURE AIR TEST. A TEST MUST CONFORM TO THE FOLLOWING REQUIREMENTS:

(1) LOW PRESSURE AIR TEST.

(A) A LOW PRESSURE AIR TEST MUST FOLLOW THE PROCEDURES DESCRIBED IN AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) C-828, ASTM C-924, OR ASTM F-1417 OR OTHER PROCEDURE APPROVED BY THE EXECUTIVE DIRECTOR, EXCEPT AS TO TESTING TIMES AS REQUIRED IN TABLE C.3 INSUBPARAGRAPH (C) OF THIS PARAGRAPH OR EQUATION C.3 IN SUBPARAGRAPH (B)(II) OF THIS PARAGRAPH.

(B) FOR SECTIONS OF COLLECTION SYSTEM PIPE LESS THAN 36 INCH AVERAGE INSIDE DIAMETER, THE FOLLOWNG PROCEDURE MUST APPLY, UNLESS A PIPE IS TO BE TESTED AS REQUIRED BY PARAGRAPH (2) OF THIS SUBSECTION.

(I) A PIPE MUST BE PRESSURIZED TO 3.5 POUNDS PER SQUARE INCH (PSI) GREATER THAN THE PRESSURE EXERTED BY GROUNDWATER ABOVE THE PIPE.

(ii) ONCE THE PRESSURE IS STABILIZED, THE MINIMUM TIME ALLOWABLE FOR THE PRESSURE TO DROP FROM 3.5 PSI GAUGE TO 2.5 PSI GAUGE IS COMPUTED FROM THE FOLLOWING EQUATION:

EQUATION C.3

WHERE: T= (0.085 * D * K)/Q

T = TIME FOR PRESSURE TO DROP 1.0 POUND PER SQUARE INCH GAUGE IN SECONDS
K = 0.000419 X D X L, BUT NOT LESS THAN 1.0
D = AVERAGE INSIDE PIPE DIAMETER IN INCHES
L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET
Q = RATE OF LOSS, 0.0015 CUBIC FEET PER MINUTE PER SQUARE FOOT INTERNAL SURFACE

(C) SINCE A K VALUE OF LESS THAN 1.0 MAY NOT BE USED, THE MINIMUM TESTING TIME FOR EACH PIPE DIAMETER IS SHOWN IN THE FOLLOWING TABLE C.3:

PIPE DIAMETER (INCHES)	MIN. TIME (SECONDS)	LENGTH FOR MIN. (FEET)	TIME, LONGER LENGTH (SECONDS)
6	340	398	0.855(L)
8	454	298	1.520(L)
10	567	239	2.374(L)
12	680	199	3.419(L)
15	850	159	5.342(L)
18	1020	133	7.693(L)
21	1190	114	10.471(L)
24	1360	100	13.676(L)
27	1530	88	17.309(L)
30	1700	80	21.369(L)
33	1870	72	25.856(L)

(D) AN OWNER MAY STOP A TEST IF NO PRESSURE LOSS HAS OCCURRED DURING THE FIRST 25% OF THE CALCULATED TESTING TIME.

(E) IF ANY PRESSURE LOSS OR LEAKAGE HAS OCCURRED DURING THE FIRST 25% OF A TESTING PERIOD, THEN THE TEST MUST CONTINUE FOR THE ENTIRE TEST DURATION AS OUTLINED ABOVE OR UNTIL FAILURE.

(F) WASTEWATER COLLECTION SYSTEM PIPES WITH A 27 INCH OR LARGER AVERAGE INSIDE DIAMETER MAY BE AIR TESTED AT EACH JOINT INSTEAD OF FOLLOWING THE PROCEDURE OUTLINED IN THIS SECTION.

(G) A TESTING PROCEDURE FOR PIPE WITH AN INSIDE DIAMETER GREATER THAN 33 INCHES MUST BE APPROVED BY THE EXECUTIVE DIRECTOR.

(2) INFILTRATION/EXFILTRATION TEST.

(A) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE.

(B) AN OWNER SHALL USE AN INFILTRATION TEST IN LIEU OF AN EXFILTRATION TEST WHEN PIPES ARE INSTALLED BELOW THE GROUNDWATER LEVEL.

(C) THE TOTAL EXFILTRATION, AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF TWO FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE, OR AT LEAST TWO FEET ABOVE EXISTING GROUNDWATER LEVEL, WHICHEVER IS GREATER.

(D) FOR CONSTRUCTION WITHIN A 25-YEAR FLOOD PLAIN, THE INFILTRATION OR EXFILTRATION MUST NOT EXCEED 10 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT THE SAME MINIMUM TEST HEAD AS IN SUBPARAGRAPH (C) OF THIS PARAGRAPH.

(E) IF THE QUANTITY OF INFILTRATION OR EXFILTRATION EXCEEDS THE MAXIMUM QUANTITY SPECIFIED, AN OWNER SHALL UNDERTAKE REMEDIAL ACTION IN ORDER TO REDUCE THE INFILTRATION OR EXFILTRATION TO AN AMOUNT WITHIN THE LIMITS SPECIFIED. AN OWNER SHALL RETEST A PIPE FOLLOWING A REMEDIATION ACTION.

(b) IF A GRAVITY COLLECTION PIPE IS COMPOSED OF FLEXIBLE PIPE, DEFLECTION TESTING IS ALSO REQUIRED. THE FOLLOWING PROCEDURES MUST BE FOLLOWED:

(1) FOR A COLLECTION PIPE WITH INSIDE DIAMETER LESS THAN 27 INCHES, DEFLECTION MEASUREMENT REQUIRES A RIGID MANDREL.

(A) MANDREL SIZING.

(i) A RIGID MANDREL MUST HAVE AN OUTSIDE DIAMETER (OD) NOT LESS THAN 95% OF THE BASE INSIDE DIAMETER (ID) OR AVERAGE ID OF A PIPE, AS SPECIFIED IN THE APPROPRIATE STANDARD BY THE ASTMS, AMERICAN WATER WORKS ASSOCIATION, UNI-BELL, OR AMERICAN NATIONAL STANDARDS INSTITUTE, OR ANY RELATED APPENDIX.

(ii) IF A MANDREL SIZING DIAMETER IS NOT SPECIFIED IN THE APPROPRIATE STANDARD, THE MANDREL MUST HAVE AN OD EQUAL TO 95% OF THE ID OF A PIPE. IN THIS CASE, THE ID OF THE PIPE, FOR THE PURPOSE OF DETERMINING THE OD OF THE MANDREL, MUST EQUAL BE THE AVERAGE OUTSIDE DIAMETER MINUS TWO MINIMUM WALL THICKNESSES FOR OD CONTROLLED PIPE AND THE AVERAGE INSIDE DIAMETER FOR ID CONTROLLED PIPE.

(iii) ALL DIMENSIONS MUST MEET THE APPROPRIATE STANDARD.

(B) MANDREL DESIGN.

(i) A RIGID MANDREL MUST BE CONSTRUCTED OF A METAL OR A RIGID PLASTIC MATERIAL THAT CAN WITHSTAND 200 PSI WITHOUT BEING DEFORMED.

(ii) A MANDREL MUST HAVE NINE OR MORE ODD NUMBER OF RUNNERS OR LEGS.

(iii) A BARREL SECTION LENGTH MUST EQUAL AT LEAST 75% OF THE INSIDE DIAMETER OF A PIPE.

(iv) EACH SIZE MANDREL MUST USE A SEPARATE PROVING RING.

(C) METHOD OPTIONS.

(i) AN ADJUSTABLE OR FLEXIBLE MANDREL IS PROHIBITED.

(ii) A TEST MAY NOT USE TELEVISION INSPECTION AS A SUBSTITUTE FOR A DEFLECTION TEST.

(iii) IF REQUESTED, THE EXECUTIVE DIRECTOR MAY APPROVE THE USE OF A DEFLECTOMETER OR A MANDREL WITH REMOVABLE LEGS OR RUNNERS ON A CASE-BY-CASE BASIS.

(2) FOR A GRAVITY COLLECTION SYSTEM PIPE WITH AN INSIDE DIAMETER 27 INCHES AND GREATER, OTHER TEST METHODS MAY BE USED TO DETERMINE VERTICAL DEFLECTION. A DEFLECTION TEST METHOD MUST BE ACCURATE TO WITHIN PLUS OR MINUS 0.2% DEFLECTION.

(3) AN OWNER SHALL NOT CONDUCT A DEFLECTION TEST UNTIL AT LEAST 30 DAYS AFTER THE FINAL BACKFILL.

(4) GRAVITY COLLECTION SYSTEM PIPE DEFLECTION MUST NOT EXCEED FIVE PERCENT (5%).

(5) IF A PIPE SECTION FAILS A DEFLECTION TEST, AN OWNER SHALL CORRECT THE PROBLEM AND CONDUCT A SECOND TEST AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS.

16. ALL MANHOLES MUST BE TESTED TO MEET OR EXCEED THE REQUIREMENTS OF 30 TAC §217.58.

(a) ALL MANHOLES MUST PASS A LEAKAGE TEST.

(b) AN OWNER SHALL TEST EACH MANHOLE (AFTER ASSEMBLY AND BACKFILLING) FOR LEAKAGE, SEPARATE AND INDEPENDENT OF THE COLLECTION SYSTEM PIPES, BY HYDROSTATIC EXFILTRATION TESTING, VACUUM TESTING, OR OTHER METHOD APPROVED BY THE EXECUTIVE DIRECTOR.

(1) HYDROSTATIC TESTING.

(A) THE MAXIMUM LEAKAGE FOR HYDROSTATIC TESTING OR ANY ALTERNATIVE TEST METHODS IS 0.025 GALLONS PER FOOT DIAMETER PER FOOT OF MANHOLE DEPTH PER HOUR.

(B) TO PERFORM A HYDROSTATIC EXFILTRATION TEST, AN OWNER SHALL SEAL ALL WASTEWATER PIPES COMING INTO A MANHOLE WITH AN INTERNAL PIPE PLUG, FILL THE MANHOLE WITH WATER, AND MAINTAIN THE TEST FOR AT LEAST ONE HOUR.

(C) A TEST FOR CONCRETE MANHOLES MAY USE A 24-HOUR WETTING PERIOD BEFORE TESTING TO ALLOW SATURATION OF THE CONCRETE.

(2) VACUUM TESTING.

(A) TO PERFORM A VACUUM TEST, AN OWNER SHALL PLUG ALL LIFT HOLES AND EXTERIOR JOINTS WITH A NON-SHRINK GROUT AND PLUG ALL PIPES ENTERING A MANHOLE.

(B) NO GROUT MUST BE PLACED IN HORIZONTAL JOINTS BEFORE TESTING.

(C) STUB-OUTS, MANHOLE BOOTS, AND PIPE PLUGS MUST BE SECURED TO PREVENT MOVEMENT WHILE A VACUUM IS DRAWN.

(D) AN OWNER SHALL USE A MINIMUM 60 INCH/LB TORQUE WRENCH TO TIGHTEN THE EXTERNAL CLAMPS THAT SECURE A TEST COVER TO THE TOP OF A MANHOLE.

(E) A TEST HEAD MUST BE PLACED AT THE INSIDE OF THE TOP OF A CONE SECTION, AND THE SEAL INFLATED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

(F) THERE MUST BE A VACUUM OF 10 INCHES OF MERCURY INSIDE A MANHOLE TO PERFORM A VALID TEST.

(G) A TEST DOES NOT BEGIN UNTIL AFTER THE VACUUM PUMP IS OFF.

(H) A MANHOLE PASSES THE TEST IF AFTER 2.0 MINUTES AND WITH ALL VALVES CLOSED, THE VACUUM IS AT LEAST 9.0 INCHES OF MERCURY.

17. ALL PRIVATE SERVICE LATERALS MUST BE INSPECTED AND CERTIFIED IN ACCORDANCE WITH 30 TAC §213.5(C)(3)(I). AFTER INSTALLATION OF AND, PRIOR TO COVERING AND CONNECTING A PRIVATE SERVICE LATERAL TO AN EXISTING ORGANIZED SEWAGE COLLECTION SYSTEM, A TEXAS LICENSED PROFESSIONAL ENGINEER, TEXAS REGISTERED SANITARIAN, OR APPROPRIATE CITY INSPECTOR MUST VISUALLY INSPECT THE PRIVATE SERVICE LATERAL AND THE CONNECTION TO THE SEWAGE COLLECTION SYSTEM, AND CERTIFY THAT IT IS CONSTRUCTED IN CONFORMITY WITH THE APPLICABLE PROVISIONS OF THIS SECTION. THE OWNER OF THE COLLECTION SYSTEM MUST MAINTAIN SUCH CERTIFICATIONS FOR FIVE YEARS AND FORWARD COPIES TO THE APPROPRIATE REGIONAL OFFICE UPON REQUEST. CONNECTIONS MAY ONLY BE MADE TO AN APPROVED SEWAGE COLLECTION SYSTEM.

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

PROJECT SEWER NOTES

1. ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND SHALL BE EXTENDED TO 10' PAST THE PROPERTY LINE AND CAPPED AND SEALED. CONTRACTOR SHALL INSTALL A 2" X 4" STAKE, FOUR (4) FEET LONG, TWO (2) FEET DEEP INTO THE GROUND AT THE END OF EACH SERVICE. NO SEPARATE PAY ITEM.
2. CONTRACTOR TO INSTALL CLEANOUTS AT THE END OF ALL SEWER LATERALS, PER LATERAL DETAIL SHEET C5.10
3. NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.
4. ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO THE PROPERTY LINE.
5. WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 150 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE VICINITY OF WATER MAINS.
6. CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 6" ABOVE FINISHED GRADE WITH CONCRETE RING ENCASEMENT.
7. ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE NOTED.
8. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE FROM INVERT SHOWN ON PLANS.
9. CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE.
10. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
11. CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES AND, WITHIN LIMITS OF PAVEMENT, BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.
12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55.
13. ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC PIPE.
14. IF THE GIVEN TOP OF MANHOLE ELEVATION DOES NOT AGREE ON ACTUAL GROUND SURFACE OR FINISH PAVEMENT, THE CONTRACTOR SHALL ADJUST ELEVATIONS SUCH THAT THE TOP OF MANHOLE SHALL BE 0.5' ABOVE EXISTING GROUND, OR FLUSH TO FINISH ASPHALT PAVEMENT.
15. ALL MANHOLES CONSTRUCTED OVER THE EDWARDS AQUIFER RECHARGE ZONE SHOULD BE WATERTIGHT.

NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED PROFESSIONAL ENGINEER
10/17/24

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TEXAS ENGINEERING FIRM 470 | TEXAS SURVEYING FIRM #10028800

OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS
SEWAGE COLLECTION SYSTEM
SANITARY SEWER GENERAL NOTES

PLAT NO. -
JOB NO. 11863-02
DATE OCTOBER 2024
DESIGNER
CHECKED - DRAWN JF
SHEET C1.10





LOCATION MAP

NOT-TO-SCALE

LEGAL DESCRIPTION:
LOT: 1R, BLOCK: 1,
(PLAT DOC. NO. 200806032437)

ADDRESS:
2154 LOOP 337
NEW BRAUNFELS, TEXAS 78130

SCALE: 1"= 50'
0' 50' 100' 150'

LEGEND

- PROPERTY LINE
- LOT LINE
- EXISTING GAS LINE
- EXISTING SEWER LINE
- EXISTING WATER LINE
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- EXISTING SANITARY SEWER MANHOLE
- PROPOSED SANITARY SEWER LINE
- PROPOSED SANITARY SEWER MANHOLE
- 100' TCEQ SEWER ENVELOPE
- PROPOSED STORM DRAINAGE

CONTRACTOR'S NOTE:

SPILLS, OVERFLOWS OR DISCHARGES OF WASTEWATER

ATTENTION CONTRACTORS: ALL SPILLS, OVERFLOW, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO YOUR COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE – REGARDLESS OF SIZE. YOUR COMPLIANCE WILL ENABLE SAWS TO FULFILL REGULATORY REPORTING REQUIREMENTS.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTROL SEWER FLOWS SO THAT A SPILL, OVERFLOW OR DISCHARGE DOES NOT OCCUR. IN THE EVENT THAT A SPILL, OVERFLOW, OR DISCHARGE OCCURS, THE CONTRACTOR MAY LIABLE FOR:

1. ALL FINES, PENALTIES, OR OTHER COSTS THAT ASSESSED TO OR AGAINST SAWS BY ANY STATE, FEDERAL, OR OTHER GOVERNMENTAL AGENCY.

2. SAWS STAFF AND MATERIAL COST TO RESPOND TO THE SPILL, OVERFLOW, OR DISCHARGE, OR TO THE MITIGATE THE EFFECTS OF THE SPILL, OVERFLOW OR DISCHARGE, OR TO SUPPORT THE CLEANUP EFFORT.

3. ALL DAMAGES CAUSE TO SAWS, OR ANY OTHER PERSONS OR ENTITIES THAT RESULT OF THE SPILL, OVERFLOW OR DISCHARGE.

CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED PROFESSIONAL ENGINEER
10/17/24

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX. 78213 | 210.375.9000
TEXAS ENGINEERING FIRM #470 | TEXAS SURVEYING FIRM #10028800

OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS
SEWAGE COLLECTION SYSTEM
OVERALL SANITARY SEWER PLAN

PLAT NO. -
JOB NO. 11863-02
DATE OCTOBER 2024
DESIGNER
CHECKED - DRAWN JF
SHEET **C1.20**

Date: Oct 14, 2024, 4:00pm User ID: jferriz
File: P:\118\63\02\Design\Environmental\SCS\SSOA-1186302.dwg







LOCATION MAP

NOT-TO-SCALE

LEGAL DESCRIPTION:
LOT: 1R, BLOCK: 1,
(PLAT DOC. NO. 2008060032437)

ADDRESS:
2154 LOOP 337
NEW BRAUNFELS, TEXAS 78130

LEGEND

- PROPERTY LINE
- LOT LINE
- EXISTING GAS LINE
- EXISTING SEWER LINE
- EXISTING WATER LINE
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- EXISTING SANITARY SEWER MANHOLE
- PROPOSED SANITARY SEWER LINE
- PROPOSED SANITARY SEWER MANHOLE
- 100' TCEQ SEWER ENVELOPE
- PROPOSED STORM DRAINAGE

NOTE

SEE SHEET C1.00 FOR ADDITIONAL GENERAL NOTES.

98% COMPACTION NOTE:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL AND PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTER, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

GENERAL SEWER NOTES

1. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 P.S.I. AND MEET THE REQUIREMENTS OF ASTM D2241 WITH ONE 20' JOINT CENTERED AT WATER MAIN.
2. NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.
3. ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO THE PROPERTY LINE.
4. WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 150 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE VICINITY OF WATER MAINS. (SEE SEWER NOTES SHEET C4.10)
5. CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 3" ABOVE FINISHED GRADE WITH CONCRETE RING ENCASEMENT.
6. ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE NOTED.
7. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE FROM INVERT SHOWN ON PLANS.
8. CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE.
9. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
10. SEE THIS SHEET FOR TYPICAL SANITARY SEWER/WATER CROSSING DETAIL.
11. CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES AND, WITHIN LIMITS OF PAVEMENT, BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.
12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55.
13. ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC PIPE.

SCALE: 1"= 50'
0' 50' 100' 150'

SANITARY SEWER LINE "A" (STA. 1+00 TO END)

VERTICAL SCALE: 1" = 5'
HORIZONTAL SCALE: 1" = 50'



NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED PROFESSIONAL ENGINEER
10/17/24

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX 78213 | 210.375.9000
TEXAS ENGINEERING FIRM 1470 | TEXAS SURVEYING FIRM #10028800

OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS
SEWAGE COLLECTION SYSTEM
SANITARY SEWER PLAN AND PROFILE ~ LINE "A"

PLAT NO. -
JOB NO. 11863-02
DATE OCTOBER 2024
DESIGNER
CHECKED -- DRAWN JF
SHEET **C1.30**

Date: Oct 14, 2024, 4:03pm User ID: jferniz
File: P:\118\63\02\Design\Environmental\SCS\SSPP-1186302.dwg



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	WASTEWATER MANHOLE W/ DROP INLET ON PRECAST BASE
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 325



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	WASTEWATER MANHOLE ON PRECAST BASE
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 328



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	GO, NO GO DEFLECTION TESTING MANDREL
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 350



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	WASTEWATER MANHOLE ON CAST IN PLACE FOUNDATION
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 327



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
JT Amaro	MANHOLE INVERT PLAN
APPROVED BY	
4-16-03	SCALE: N.T.S. SHEET: 1 OF 2 DRAWING NO.: 320



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
H Shadrock	STANDARD MANHOLE MANHOLE FLOOR PLAN
APPROVED BY	
A. Willard	
8/17/21	UPDATED: 5-3-03 SCALE: N.T.S. SHEET: 2 OF 2 DRAWING NO.: 320



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	NEW MANHOLE CONSTRUCTION AND MINOR MANHOLE ADJUSTMENT
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 322



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	SANITARY SEWER MANHOLE COVER
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 331



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	VENTED SANITARY SEWER MANHOLE COVER
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 334



NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
JT Amaro	CONCRETE ENCASEMENT
APPROVED BY	
JF	
4-16-03	UPDATED: 4-16-03 SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 310

NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	WASTEWATER DEEP SERVICE CONNECTION DETAIL
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 1 DRAWING NO.: 301

NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	SINGLE WASTEWATER SERVICE CONNECTION DETAIL
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 1 OF 2 DRAWING NO.: 302

NOTES:

1. UTILITY CONTRACTOR, DURING SUBDIVISION CONSTRUCTION, SHALL INSTALL WASTEWATER CONNECTION TO MAIN, 6" STUB WITH 6" SERVICE BRANCH WITH 2-WAY CLEANOUT, CONCRETE SUPPORT (MIN. 18"Wx18"Lx6"H), RISER FOR CLEAN OUT (CAPPED), UTILITY SHROUD, 7' EXTENSION, AND PLUG. ALL WASTEWATER PIPING SHALL HAVE ELASTOMERIC GASKET TYPE JOINTS AND SHALL SLOPE DOWNWARD TO MAIN 2%, 1/4" PER FOOT, MINIMUM TO 45° MAXIMUM. DEPTH OF SERVICE STUB AT PROPERTY LINE WILL BE SHOWN ON PLANS BY ENGINEER OR DESIGNATED REPRESENTATIVE IF GREATER THAN 4', OTHERWISE, THE INSTALLED DEPTH WILL TYPICALLY BE 4' TO 6'. IF WASTEWATER SERVICE LINE TO MAIN REQUIRES DEFLECTION EXCEEDING 45°, REFER TO DETAIL DRAWING 301. ALL INSTALLATIONS SHALL BE MADE IN ACCORDANCE WITH INFORMATION SHOWN ON APPLICABLE STANDARD DRAWINGS AND WILL BE INSPECTED BY NBU CONSTRUCTION INSPECTION PERSONNEL.
2. CUSTOMER SHALL REMOVE PLUG, INSTALL 4" WASTEWATER LINE (EXTEND 4" PIPE 6" MINIMUM INTO 6" PIPE AND JOINT WITH FLEXIBLE ADAPTOR). IF WASTEWATER WILL NOT SATISFACTORILY FLOW BY GRAVITY TO SEWER MAIN ADJACENT TO PROPERTY, PUMP EQUIPMENT MUST BE PROVIDED BY THE CUSTOMER AS PART OF CUSTOMER'S WASTEWATER SYSTEM.
3. CUSTOMER IS RESPONSIBLE FOR PIPING SYSTEM UNTIL WASTEWATER IS CONNECTED. ANY MISSING OR DAMAGED PARTS SHALL BE REINSTALLED BY CUSTOMER WHO SHALL GUARANTEE, FOR A PERIOD OF TWO (2) YEARS FROM DATE OF FINAL ACCEPTANCE, CONNECTIONS TO NBU SYSTEMS ARE FREE FROM DEFECTS IN WORKMANSHIP OR MATERIALS. CUSTOMER ALSO HAS THE RESPONSIBILITY TO ASSURE THAT 2-WAY CLEANOUTS REMAIN CLEAR OF SIDEWALKS AND OTHER OBSTRUCTIONS.
4. NBU ACTIVITY IS LIMITED TO INSPECTION OF CONNECTIONS TO NBU'S WASTEWATER SYSTEM. FOR MAINTENANCE PURPOSES, NBU'S RESPONSIBILITY ENDS AT THE CUSTOMER'S WASTEWATER CONNECTION TO THE 2-WAY CLEANOUT OR THE PROPERTY LINE, WHICHEVER IS CLOSER TO WASTEWATER MAIN.
5. PIPING IN STREET RIGHT-OF-WAY AND IN EASEMENT AREA SHALL BE BEDDED IN GRANULAR MATERIALS AS REQUIRED BY NBU STANDARD SPECIFICATION; MATERIALS SHALL BE AS SPECIFIED; BACKFILL ABOVE THE GRANULAR BEDDING. SERVICE LINES IN THESE AREAS SHALL HAVE A MINIMUM COVER BELOW FINAL STREET GRADE OF 42"; ANY EXCEPTION MUST BE SPECIFICALLY APPROVED BY THE ENGINEER.

NBU — NEW BRAUNFELS UTILITIES WATER SYSTEMS ENGINEERING

DRAWN BY	STANDARD DRAWING
A. Willard	SINGLE WASTEWATER SERVICE CONNECTION DETAIL
APPROVED BY	
A. Willard	
8/17/21	SCALE: N.T.S. SHEET: 2 OF 2 DRAWING NO.: 302

UTILITY & STORM DRAINAGE TRENCH

NOT-TO-SCALE

TYPICAL SANITARY SEWER/WATER CROSSING DETAIL

NOT-TO-SCALE

PAPE-DAWSON ENGINEERS
2000 NW LOOP 410 | SAN ANTONIO, TX. 78213 | 210.375.9000
TEXAS ENGINEERING FIRM 1470 | TEXAS SURVEYING FIRM #10028800

NO.	REVISION	DATE

STATE OF TEXAS
CALEB M. CHANCE
98401
LICENSED PROFESSIONAL ENGINEER
10/17/24

OAKWOOD BAPTIST CHURCH

NEW BRAUNFELS, TEXAS
SEWAGE COLLECTION SYSTEM
SANITARY SEWER DETAILS

PLAT NO. -
JOB NO. 11863-02
DATE OCTOBER 2024
DESIGNER
CHECKED - DRAWN JF
SHEET **C1.40**

Date: Oct 14, 2024, 4:03pm User ID: jfernandez
File: P:\1118\63\02\Design\Environmental\SCS\SSDT-1186302_SCS.dwg