



## Transmittal

Date: November 8, 2024

To: TCEQ Reviewer

From: Stacy Mulholland

Reference: Canyon Ranch Unit 4 CZP Application

---

Item No.	Number of Copies	Description
1	1	Edwards Aquifer Application Cover Page
2	1	Contributing Zone Plan Application
3	1	Temporary Stormwater Section
4	1	Agent Authorization Form
5	1	Owner Authorization Form
6	1	Application Fee Form
7	1	TCEQ Client Core Data Form
8	1	TCEQ Owner Core Data Form
9	1	Unit 1 TCEQ Approval Letter
10	1	Unit 2 TCEQ Approval Letter
11	1	Unit 3 TCEQ Approval Letter
12	1	Unit 4 Construction Plan Set

Comments:



# Texas Commission on Environmental Quality

## Edwards Aquifer Application Cover Page

---

### Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with [30 TAC 213](#).

### Administrative Review

1. [Edwards Aquifer applications](#) must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <http://www.tceq.texas.gov/field/eapp>.

2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
6. If the geologic assessment was completed before October 1, 2004 and the site contains “possibly sensitive” features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

### Technical Review

1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

### Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a “Mid-Review Modification”. Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ’s Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ’s San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

<b>1. Regulated Entity Name:</b> Canyon Ranch Unit 4					<b>2. Regulated Entity No.:</b>				
<b>3. Customer Name:</b> Lennar Homes of Texas Land and Construction, LTD					<b>4. Customer No.:</b> CN 602412207				
<b>5. Project Type:</b> (Please circle/check one)	New <input checked="" type="checkbox"/> X		Modification			Extension		Exception	
<b>6. Plan Type:</b> (Please circle/check one)	WPAP	CZP <input checked="" type="checkbox"/> X	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
<b>7. Land Use:</b> (Please circle/check one)	Residential <input checked="" type="checkbox"/> X		Non-residential			<b>8. Site (acres):</b>		30.70	
<b>9. Application Fee:</b>	\$4,000		<b>10. Permanent BMP(s):</b>				Batch Detention Ponds, Filter Strips		
<b>11. SCS (Linear Ft.):</b>	N/A		<b>12. AST/UST (No. Tanks):</b>						
<b>13. County:</b>	Comal		<b>14. Watershed:</b>				Guadalupe River		

# Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the “Texas Groundwater Conservation Districts within the EAPP Boundaries” map found at:

[http://www.tceq.texas.gov/assets/public/compliance/field\\_ops/eapp/EAPP%20GWCD%20map.pdf](http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf)

For more detailed boundaries, please contact the conservation district directly.

Austin Region			
County:	Hays	Travis	Williamson
Original (1 req.)	—	—	—
Region (1 req.)	—	—	—
County(ies)	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Barton Springs/ Edwards Aquifer <input type="checkbox"/> Hays Trinity <input type="checkbox"/> Plum Creek	<input type="checkbox"/> Barton Springs/ Edwards Aquifer	NA
City(ies) Jurisdiction	<input type="checkbox"/> Austin <input type="checkbox"/> Buda <input type="checkbox"/> Dripping Springs <input type="checkbox"/> Kyle <input type="checkbox"/> Mountain City <input type="checkbox"/> San Marcos <input type="checkbox"/> Wimberley <input type="checkbox"/> Woodcreek	<input type="checkbox"/> Austin <input type="checkbox"/> Bee Cave <input type="checkbox"/> Pflugerville <input type="checkbox"/> Rollingwood <input type="checkbox"/> Round Rock <input type="checkbox"/> Sunset Valley <input type="checkbox"/> West Lake Hills	<input type="checkbox"/> Austin <input type="checkbox"/> Cedar Park <input type="checkbox"/> Florence <input type="checkbox"/> Georgetown <input type="checkbox"/> Jerrell <input type="checkbox"/> Leander <input type="checkbox"/> Liberty Hill <input type="checkbox"/> Pflugerville <input type="checkbox"/> Round Rock

San Antonio Region					
County:	Bexar	Comal	Kinney	Medina	Uvalde
Original (1 req.)	—	<u>X</u>	—	—	—
Region (1 req.)	—	<u>X</u>	—	—	—
County(ies)	—	<u>X</u>	—	—	—
Groundwater Conservation District(s)	<input type="checkbox"/> Edwards Aquifer Authority <input type="checkbox"/> Trinity-Glen Rose	<input checked="" type="checkbox"/> Edwards Aquifer Authority	<input type="checkbox"/> Kinney	<input type="checkbox"/> EAA <input type="checkbox"/> Medina	<input type="checkbox"/> EAA <input type="checkbox"/> Uvalde
City(ies) Jurisdiction	<input type="checkbox"/> Castle Hills <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Helotes <input type="checkbox"/> Hill Country Village <input type="checkbox"/> Hollywood Park <input type="checkbox"/> San Antonio (SAWS) <input type="checkbox"/> Shavano Park	<input type="checkbox"/> Bulverde <input type="checkbox"/> Fair Oaks Ranch <input type="checkbox"/> Garden Ridge <input type="checkbox"/> New Braunfels <input type="checkbox"/> Schertz	NA	<input type="checkbox"/> San Antonio ETJ (SAWS)	NA

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Stacy Mulholland

Print Name of Customer/Authorized Agent



11/08/2024

Signature of Customer/Authorized Agent

Date

**\*\*FOR TCEQ INTERNAL USE ONLY\*\***

Date(s) Reviewed:		Date Administratively Complete:	
Received From:		Correct Number of Copies:	
Received By:		Distribution Date:	
EAPP File Number:		Complex:	
Admin. Review(s) (No.):		No. AR Rounds:	
Delinquent Fees (Y/N):		Review Time Spent:	
Lat./Long. Verified:		SOS Customer Verification:	
Agent Authorization Complete/Notarized (Y/N):		Fee Check:	Payable to TCEQ (Y/N):
Core Data Form Complete (Y/N):			Signed (Y/N):
Core Data Form Incomplete Nos.:			Less than 90 days old (Y/N):

# Contributing Zone Plan Application

## Texas Commission on Environmental Quality

for Regulated Activities on the Contributing Zone to the Edwards Aquifer and Relating to 30 TAC §213.24(1), Effective June 1, 1999

*To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.*

*Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.*

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Contributing Zone Plan Application** is hereby submitted for TCEQ review and Executive Director approval. The application was prepared by:

Print Name of Customer/Agent: Stacy Mulholland

Date: 10/14/2024

Signature of Customer/Agent:

 \_\_\_\_\_

Regulated Entity Name: Canyon Ranch Unit 4

## Project Information

1. County: Comal
2. Stream Basin: Guadalupe River
3. Groundwater Conservation District (if applicable): \_\_\_\_\_
4. Customer (Applicant):

Contact Person: Richard Mott

Entity: Lennar Homes of Texas Land and Construction LTD

Mailing Address: 100 NE Loop 410, Suite 1155

City, State: San Antonio, TX

Zip: 78216

Telephone: 210-889-5516

Fax: \_\_\_\_\_

Email Address: richard.mott@lennar.com

5. Agent/Representative (If any):

Contact Person: Stacy Mulholland

Entity: BGE Inc

Mailing Address: 7330 San Pedro Ave, Suite 202

City, State: San Antonio, TX

Zip: 78216

Telephone: 210-581-3637

Fax: \_\_\_\_\_

Email Address: smulholland@bgeinc.com

6. Project Location:

- ☐ The project site is located inside the city limits of \_\_\_\_.
- ☐ The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of \_\_\_\_.
- ☒ The project site is not located within any city's limits or ETJ.

7. ☐ The location of the project site is described below. Sufficient detail and clarity has been provided so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

\_\_\_\_\_

8. ☒ **Attachment A - Road Map.** A road map showing directions to and the location of the project site is attached. The map clearly shows the boundary of the project site.
9. ☒ **Attachment B - USGS Quadrangle Map.** A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000") is attached. The map(s) clearly show:
- ☒ Project site boundaries.
- ☒ USGS Quadrangle Name(s).
10. ☒ **Attachment C - Project Narrative.** A detailed narrative description of the proposed project is attached. The project description is consistent throughout the application and contains, at a minimum, the following details:
- ☒ Area of the site
- ☒ Offsite areas
- ☒ Impervious cover
- ☒ Permanent BMP(s)
- ☒ Proposed site use
- ☒ Site history
- ☒ Previous development
- ☒ Area(s) to be demolished

11. Existing project site conditions are noted below:

- ☐ Existing commercial site
- ☐ Existing industrial site
- ☐ Existing residential site

- ☐ Existing paved and/or unpaved roads  
☐ Undeveloped (Cleared)  
☒ Undeveloped (Undisturbed/Not cleared)  
☐ Other: \_\_\_\_\_

12. The type of project is:

- ☒ Residential: # of Lots: 177  
☐ Residential: # of Living Unit Equivalents: \_\_\_\_\_  
☐ Commercial  
☐ Industrial  
☐ Other: \_\_\_\_\_

13. Total project area (size of site): 30.70 Acres

Total disturbed area: 42.80 Acres

14. Estimated projected population: \_\_\_\_\_

15. The amount and type of impervious cover expected after construction is complete is shown below:

**Table 1 - Impervious Cover**

<i><b>Impervious Cover of Proposed Project</b></i>	<i><b>Sq. Ft.</b></i>	<i><b>Sq. Ft./Acre</b></i>	<i><b>Acres</b></i>
Structures/Rooftops	619,500	÷ 43,560 =	14.22
Parking	225,098	÷ 43,560 =	5.17
Other paved surfaces	5,340	÷ 43,560 =	0.12
Total Impervious Cover	849,938	÷ 43,560 =	19.51

**Total Impervious Cover  $19.51 \div \text{Total Acreage } 30.70 \times 100 = 63.55\%$  Impervious Cover**

16. ☒ **Attachment D - Factors Affecting Surface Water Quality.** A detailed description of all factors that could affect surface water quality is attached. If applicable, this includes the location and description of any discharge associated with industrial activity other than construction.

17. ☐ Only inert materials as defined by 30 TAC 330.2 will be used as fill material.

### ***For Road Projects Only***

***Complete questions 18 - 23 if this application is exclusively for a road project.***

☒ N/A

18. Type of project:

- ☐ TXDOT road project.
- ☐ County road or roads built to county specifications.
- ☐ City thoroughfare or roads to be dedicated to a municipality.
- ☐ Street or road providing access to private driveways.

19. Type of pavement or road surface to be used:

- ☐ Concrete
- ☐ Asphaltic concrete pavement
- ☐ Other: \_\_\_\_\_

20. Right of Way (R.O.W.):

Length of R.O.W.: \_\_\_\_\_ feet.

Width of R.O.W.: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

21. Pavement Area:

Length of pavement area: \_\_\_\_\_ feet.

Width of pavement area: \_\_\_\_\_ feet.

$L \times W = \text{_____ Ft}^2 \div 43,560 \text{ Ft}^2/\text{Acre} = \text{_____ acres.}$

Pavement area \_\_\_\_\_ acres  $\div$  R.O.W. area \_\_\_\_\_ acres  $\times 100 = \text{_____ \%}$  impervious cover.

22. ☐ A rest stop will be included in this project.
- ☐ A rest stop will not be included in this project.
23. ☐ Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

***Stormwater to be generated by the Proposed Project***

24. ☒ **Attachment E - Volume and Character of Stormwater.** A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

***Wastewater to be generated by the Proposed Project***

25. ☒ Wastewater is to be discharged in the contributing zone. Requirements under 30 TAC §213.6(c) relating to Wastewater Treatment and Disposal Systems have been satisfied.
- ☐ N/A



26. Wastewater will be disposed of by:

☐ On-Site Sewage Facility (OSSF/Septic Tank):

☐ **Attachment F - Suitability Letter from Authorized Agent.** An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

☐ Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

☒ Sewage Collection System (Sewer Lines):

The sewage collection system will convey the wastewater to the Canyon Ranch (name) Treatment Plant. The treatment facility is:

☐ Existing.

☒ Proposed.

☐ N/A

### ***Permanent Aboveground Storage Tanks(ASTs) ≥ 500 Gallons***

***Complete questions 27 - 33 if this project includes the installation of AST(s) with volume(s) greater than or equal to 500 gallons.***

☒ N/A

27. Tanks and substance stored:

**Table 2 - Tanks and Substance Storage**

<b><i>AST Number</i></b>	<b><i>Size (Gallons)</i></b>	<b><i>Substance to be Stored</i></b>	<b><i>Tank Material</i></b>
1			
2			
3			
4			
5			

**Total x 1.5 = \_\_\_\_\_ Gallons**

28. ☐ The AST will be placed within a containment structure that is sized to capture one and one-half (1 1/2) times the storage capacity of the system. For facilities with more than

one tank system, the containment structure is sized to capture one and one-half (1 1/2) times the cumulative storage capacity of all systems.

- ☐ **Attachment G - Alternative Secondary Containment Methods.** Alternative methods for providing secondary containment are proposed. Specifications showing equivalent protection for the Edwards Aquifer are attached.

29. Inside dimensions and capacity of containment structure(s):

**Table 3 - Secondary Containment**

<i>Length (L)(Ft.)</i>	<i>Width(W)(Ft.)</i>	<i>Height (H)(Ft.)</i>	<i>L x W x H = (Ft3)</i>	<i>Gallons</i>

**Total: \_\_\_\_\_ Gallons**

30. Piping:

- ☐ All piping, hoses, and dispensers will be located inside the containment structure.
- ☐ Some of the piping to dispensers or equipment will extend outside the containment structure.
- ☐ The piping will be aboveground
- ☐ The piping will be underground

31. ☐ The containment area must be constructed of and in a material impervious to the substance(s) being stored. The proposed containment structure will be constructed of: \_\_\_\_\_.

32. ☐ **Attachment H - AST Containment Structure Drawings.** A scaled drawing of the containment structure is attached that shows the following:

- ☐ Interior dimensions (length, width, depth and wall and floor thickness).
- ☐ Internal drainage to a point convenient for the collection of any spillage.
- ☐ Tanks clearly labeled
- ☐ Piping clearly labeled
- ☐ Dispenser clearly labeled

33. ☐ Any spills must be directed to a point convenient for collection and recovery. Spills from storage tank facilities must be removed from the controlled drainage area for disposal within 24 hours of the spill.

- ☐ In the event of a spill, any spillage will be removed from the containment structure within 24 hours of the spill and disposed of properly.

- ☐ In the event of a spill, any spillage will be drained from the containment structure through a drain and valve within 24 hours of the spill and disposed of properly. The drain and valve system are shown in detail on the scaled drawing.

## **Site Plan Requirements**

**Items 34 - 46 must be included on the Site Plan.**

34. ☒ The Site Plan must have a minimum scale of 1" = 400'.  
Site Plan Scale: 1" = 60'.
35. 100-year floodplain boundaries:
- ☐ Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
- ☒ No part of the project site is located within the 100-year floodplain.  
The 100-year floodplain boundaries are based on the following specific (including date of material) sources(s): FEMA FIRM Panel 48091C0080F, effective 9/02/2009.
36. ☒ The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
- ☐ The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot contour intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, etc. are shown on the site plan.
37. ☒ A drainage plan showing all paths of drainage from the site to surface streams.
38. ☒ The drainage patterns and approximate slopes anticipated after major grading activities.
39. ☒ Areas of soil disturbance and areas which will not be disturbed.
40. ☒ Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
41. ☒ Locations where soil stabilization practices are expected to occur.
42. ☒ Surface waters (including wetlands).  
☐ N/A
43. ☒ Locations where stormwater discharges to surface water.  
☐ There will be no discharges to surface water.
44. ☐ Temporary aboveground storage tank facilities.  
☒ Temporary aboveground storage tank facilities will not be located on this site.

45. ☐ Permanent aboveground storage tank facilities.  
☒ Permanent aboveground storage tank facilities will not be located on this site.
46. ☒ Legal boundaries of the site are shown.

### ***Permanent Best Management Practices (BMPs)***

#### ***Practices and measures that will be used during and after construction is completed.***

47. ☒ Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.  
☐ N/A
48. ☒ These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.  
☒ The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.  
☐ A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: \_\_\_\_\_.  
☐ N/A
49. ☒ Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.  
☐ N/A
50. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.  
☐ The site will be used for low density single-family residential development and has 20% or less impervious cover.  
☐ The site will be used for low density single-family residential development but has more than 20% impervious cover.  
☒ The site will not be used for low density single-family residential development.

51. The executive director may waive the requirement for other permanent BMPs for multi-family residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.

- ☐ **Attachment I - 20% or Less Impervious Cover Waiver.** The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
- ☐ The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
- ☒ The site will not be used for multi-family residential developments, schools, or small business sites.

52. ☒ **Attachment J - BMPs for Upgradient Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.
- ☐ No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

53. ☒ **Attachment K - BMPs for On-site Stormwater.**

- ☐ A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- ☒ Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.

54. ☒ **Attachment L - BMPs for Surface Streams.** A description of the BMPs and measures that prevent pollutants from entering surface streams is attached.

☐ N/A

55. ☒ **Attachment M - Construction Plans.** Construction plans and design calculations for the proposed permanent BMPs and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. Construction plans for the proposed permanent BMPs and measures are

attached and include: Design calculations, TCEQ Construction Notes, all proposed structural plans and specifications, and appropriate details.

☐ N/A

56. ☒ **Attachment N - Inspection, Maintenance, Repair and Retrofit Plan.** A site and BMP specific plan for the inspection, maintenance, repair, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan fulfills all of the following:

- ☒ Prepared and certified by the engineer designing the permanent BMPs and measures
- ☒ Signed by the owner or responsible party
- ☒ Outlines specific procedures for documenting inspections, maintenance, repairs, and, if necessary, retrofit.
- ☒ Contains a discussion of record keeping procedures

☐ N/A

57. ☐ **Attachment O - Pilot-Scale Field Testing Plan.** Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.

☒ N/A

58. ☒ **Attachment P - Measures for Minimizing Surface Stream Contamination.** A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that result in water quality degradation.

☐ N/A

***Responsibility for Maintenance of Permanent BMPs and Measures after Construction is Complete.***

59. ☒ The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.
60. ☒ A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development,

or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

### ***Administrative Information***

- 61. ☒ Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions.
- 62. ☒ Any modification of this Contributing Zone Plan may require TCEQ review and Executive Director approval prior to construction, and may require submission of a revised application, with appropriate fees.
- 63. ☐ The site description, controls, maintenance, and inspection requirements for the storm water pollution prevention plan (SWPPP) developed under the EPA NPDES general permits for stormwater discharges have been submitted to fulfill paragraphs 30 TAC §213.24(1-5) of the technical report. All requirements of 30 TAC §213.24(1-5) have been met by the SWPPP document.
- ☒ The Temporary Stormwater Section (TCEQ-0602) is included with the application.



# ATTACHMENT A


## ROAD MAP



Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



\\geoinc\data\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\05\_Deliverables\01 - Submittals\04\_TCEQ\01\_TCEQ Unit 4 Submittal 1\03\_Attachments\ATTACHMENT A - ROAD MAP.dwg Layout: Layout1 Plotted: 10/14/2024 11:06:36 AM By: Lhuck



CANYON RANCH UNIT 4		ATTACHMENT A – ROAD MAP	
		 BGE, INC. 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 214.883.3600 www.bgeinc.com TXPE Registration No. F-1046	
DESIGNED BY:	LNH	REV	DESCRIPTION
REVIEWED BY:	SSM	DATE	
DRAWN BY:	LNH	APR	







# ATTACHMENT B

## USGS QUADRANGLE MAP

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)





CANYON RANCH UNIT 4	
ATTACHMENT B	
DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	LNH

**BGE INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-981-3360 www.bgeingray.com  
TXPE Registration No. P-1046

STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET

DATE	DESCRIPTION
APR	





# ATTACHMENT C

## PROJECT DESCRIPTION

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## Canyon Ranch Unit 4

### Contributing Zone Plan Application (TCEQ-10257)

#### Attachment C — Project Narrative

Canyon Ranch Unit 4 is located at the northwest corner of the FM 306 and Mystic Canyon intersection. The undeveloped 30.70 acres will be developed into multiple single family residential sites. The project lies within the Guadalupe River – Canyon Lake Watershed and does not contain any FEMA 100-yr floodplains.

Canyon Ranch Unit 4 will contain 177 single family residential units and associated roadway access. This project's scope includes clearing, grubbing, and grading of the overall site, as well as the installation of water, wastewater, and storm sewer lines. Sewage will be disposed of by conveyance to the Canyon Ranch WWTP owned and operated by Corix Utilities (Texas) (Permit Number WQ0015866001). The impervious cover will increase from natural conditions to 63.55%, or 19.51 acres of the 30.70 acre site. The permanent BMPs that will be utilized will be two batch detention ponds and engineered vegetative filter strips. Both batch detention ponds are located outside of the Unit 4 platted boundary but are proposed to be fully built with Unit 4. The first proposed batch detention pond, called Unit 4 pond, is located along the south unit boundary and will treat 7.79 acres of impervious cover. The other batch detention pond that treats Unit 4 flow is located northeast of the unit 4 boundary, contained in a drainage easement. This pond will be called the Unit 5 batch detention pond, since the pond is located in the future Unit 5 of the subdivision. The proposed Unit 5 batch detention pond will treat 7.74 acres of impervious cover flowing from Unit 4. There is 2.01 acres of impervious cover that will be treated by vegetative filters strips located along the eastern property boundary and the south-western unit boundary. The Unit 4 pond will provide 8,125 lbs of TSS removal and the Unit 5 pond will provide 8,065 lbs of TSS removal. The vegetative filters strips will provide the remaining 1,456 lbs of TSS removal for a total of 17,646 lbs of provided TSS removal in Unit 4. The required water quality volume for the Unit 4 pond is 95,702 CF and 95,702 CF is provided. For the Unit 5 pond, the required water quality volume is 188,691 CF and the provided water quality volume is 239,350 CF. Both the Unit 4 and Unit 5 ponds have been built for anticipation of future units.

#### ATTACHMENT C

#### Contributing Zone Plan Application

The construction plans submitted with this application include no plans for demolition. Most of the storm water will flow to the Unit 4 and 5 ponds through curb and gutter inlet storm drain systems. The stormwater flowing to the Vegetative Filter Strips will sheet flow to the engineered vegetative filter strips. Any uncaptured flow will be accounted for by the overtreatment by the proposed BMPs. All PBMPs have been designed in accordance with the Texas Commission on Environmental Quality's (TCEQ) Technical Guidance Manual (TGM) RG-348 (2005).

Both the Unit 4 and Unit 5 batch detention ponds, fully constructed in Unit 4, are designed to receive drainage from future development and overtreat flow for ultimate development conditions. This application package only reflects the impervious cover proposed in Unit 4, however, the future TSS removal has been considered to ensure both ponds are built for the ultimate conditions. The tables below summarize the TSS removal calculations to show the overall project satisfies TSS removal.

Unit 4 BMP Summary					
BMP	BMP Basin (AC)	Existing IC (AC)	Proposed IC (AC)	Required TSS Removal	Provided TSS Removal
Unit 4 Pond	12.16	0	7.79	6,992	8,125
Unit 5 Pond	11.59	0	7.74	6,947	8,065
Uncaptured - Unit 4	2.30	0	1.97	1,768	-
Unit 4 VFS	4.65	0	2.01	1,804	1,456
<b>TOTAL</b>	<b>30.70</b>	<b>0</b>	<b>19.51</b>	<b>17,511</b>	<b>17,646</b>

**Table 1 – Unit 4 Pond Summary:** The table above summarizes the Unit 4 Pond TSS removal calculations by BMP.

## ATTACHMENT C

### Project Narrative

<b>BMP Summary</b>				
<b>BMP</b>	<b>BMP Basin (AC)</b>	<b>IC (AC)</b>	<b>TSS Required</b>	<b>TSS Provided</b>
Unit 1 Pond	42.19	23.47	21,067	23,825
Unit 1 FM 306 VFS	1.44	0.60	539	609
Unit 1 Flores VFS	1.14	0.40	359	399
Unit 2 Pond	17.73	7.80	7,001	7,925
Unit 2 FM 306 VFS	0.66	0.20	180	201
Unit 3 Pond	58.83	24.40	21,901	24,226
Unit 4 Pond	17.73	9.10	8,168	9,451
Unit 4 VFS - uncap	4.65	2.01	1,804	1,456
Unit 1 Uncaptured	11.06	1.87	1,679	---
Unit 2 Uncaptured	2.72	1.10	987	---
Unit 3 Uncaptured*	8.08	2.94	2,639	---
Unit 4 Uncaptured	2.30	1.97	1,768	---
<b>Total</b>	<b>168.52</b>	<b>75.86</b>	<b>68,092</b>	<b>68,092</b>

**Table 2 – BMP Summary:** This table summarizes the TSS removal calculations by BMP once Unit 4 has been fully constructed. Future treatment has been estimated in this table to ensure the overall project satisfies TSS removal requirements. This table is to be updated with further submittals as development conditions are further refined.

## ATTACHMENT C

### Project Narrative

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



# ATTACHMENT D

## FACTORS AFFECTING WATER SURFACE QUALITY

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)





## CANYON RANCH UNIT 4

### Contributing Zone Plan Application (TCEQ-10257)

#### Attachment D— Factors Affecting Surface Water Quality

Potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the site during construction include:

- *Soil erosion due to the clearing of the site;*
- *Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle drippings;*
- *Hydrocarbons from asphalt paving operations;*
- *Miscellaneous trash and litter from construction workers and material wrappings;*
- *Concrete truck washout.*
- *Potential overflow/spills from portable toilets*

Potential sources of pollution that may reasonably be expected to affect the quality of storm water discharges from the site after development include:

- *Oil, grease, fuel and hydraulic fluid contamination from vehicle drippings;*
- *Dirt and dust which may fall off vehicles; and*
- *Miscellaneous trash and litter.*

#### ATTACHMENT D

#### Contributing Zone Plan Application



# ATTACHMENT E

## VOLUME AND CHARACTER OF STORMWATER

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Contributing Zone Plan Application (TCEQ-10257)

#### Attachment E— Volume and Character of Stormwater

The total drainage area accounted for is 30.70 acres. Proposed impervious cover accounts for 19.51 acres of the total drainage area (no existing impervious cover). 7.79 acres of impervious cover will be treated by the batch detention pond called the Unit 4 pond, located along the southern unit boundary. 7.74 acres of impervious cover will be treated by the Unit 5 batch detention pond that is located along the northeastern unit boundary. Both batch detention ponds are located outside of the Unit 4 platted boundary but are proposed to be fully built with Unit 4. 2.01 acres of impervious cover will be treated by engineered vegetated filter strips located along the eastern property boundary and southwestern unit boundary in Unit 4. 1.97 acres of impervious cover is uncaptured in Unit 4. The Unit 4 pond will provide 8,125 lbs of TSS removal and the Unit 5 pond will provide 8,065 lbs of TSS removal.

Drainage area map and calculations for the site are provided with this application.

For an overview of sub-drainage basins on site, please refer to the included drainage map.

#### ATTACHMENT E

#### Contributing Zone Plan Application



# ATTACHMENT J

## BMPS FOR UPGRADIENT STORMWATER

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Contributing Zone Plan Application (TCEQ-10257)

#### Attachment J- BMPs for Upgradient Stormwater

*An internal underground storm drain system and open channels will convey upgradient storm water into the Devil's Hollow Tributary 1. The stormwater will not be treated within the proposed subdivision.*

#### ATTACHMENT J

#### Contributing Zone Plan Application

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



# ATTACHMENT K

## BMPS FOR ON-SITE STORMWATER

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Contributing Zone Plan Application (TCEQ-10257)

#### Attachment K- BMPs for Onsite Stormwater



*Silt control fences are to be installed to prevent stormwater from carrying sediment offsite during construction. Construction entrances are to be placed to facilitate the arrival and departure of construction vehicles without the addition of undue erosion. Batch detention ponds are to be installed in accordance with construction plans to treat pollutant areas of Unit 4. All PBMPs have been designed in accordance with the TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) to remove 80% of the increase in TSS from the site.*

#### ATTACHMENT K

#### Contributing Zone Plan Application



G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\118 - Unit 4\03\_CADD\04\_ Exhibits\FIG 5.0 PERMANENT BMP FLOW MAP.dwg Layout: Layout1 Plotted: 10/17/2024 7:40:25 AM By: Lhuck



- LEGEND
- 1202 2' PROPOSED CONTOURS
  - 1210 10' PROPOSED CONTOURS
  - 1202 2' EXISTING CONTOURS
  - 1210 10' EXISTING CONTOURS
  - PROPERTY BOUNDARY
  - UNIT BOUNDARY
  - FLOW TO UNIT 4 POND
  - FLOW TO UNIT 5 POND
  - VEGETATIVE FILTER STRIPS IN UNIT 4
  - UNCAPTURED FLOW, ACCOUNTED FOR IN UNIT 4
  - UNIT 4 FLOW TO UNIT 4 POND
  - UNIT 4 FLOW TO UNIT 5 POND
  - UNIT 4 VFS FLOW ARROWS
  - UNIT 4 UNCAPTURED FLOW ARROWS
  - FUTURE UNIT FLOW TO UNIT 4 POND
  - FUTURE UNIT FLOW TO UNIT 5 POND


Unit 4 BMP Summary					
BMP	BMP Basin (AC)	Existing IC (AC)	Proposed IC (AC)	Required TSS Removal	Provided TSS Removal
Unit 4 Pond	12.16	0	7.79	6,992	8,125
Unit 5 Pond	11.59	0	7.74	6,947	8,065
Uncaptured - Unit 4	2.30	0	1.97	1,768	-
Unit 4 VFS	4.65	0	2.01	1,804	1,456
TOTAL	30.70	0	19.51	17,511	17,646

DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH

REVIEWED BY: SSM

DRAWN BY: LNH




BGE, INC.

7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-883-3600 www.bgeenergy.com  
EPA Registration No. P-1046

CANYON RANCH UNIT 4

PERMANENT BMP FLOW MAP



11/08/2024

SHEET

FIG 5.0





# ATTACHMENT L

## BMPs for SURFACE STREAMS

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## **CANYON RANCH UNIT 4**

### **Contributing Zone Plan Application (TCEQ-10257)**

#### **Attachment L- BMPs for Surface Streams**

No BMPs are proposed specifically for surface streams. Proposed on-site BMPs and drainage systems are designed to maintain existing flow patterns.

#### **ATTACHMENT L**

#### **Contributing Zone Plan Application**

**Serving. Leading. Solving.™**

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



# ATTACHMENT M

## CONSTRUCTION PLANS

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## **CANYON RANCH UNIT 4**

### **Contributing Zone Plan Application (TCEQ-10257)**

#### **Attachment M- Construction Plan**

Construction plans for both temporary and permanent BMPs are attached in the complete plan set.

#### **ATTACHMENT M**

#### **Contributing Zone Plan Application**

**Serving. Leading. Solving.™**

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



# ATTACHMENT N

## INSPECTION, MAINTENANCE, REPAIR & RETROFIT PLAN

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Contributing Zone Plan Application (TCEQ-10257)


#### Attachment N- Inspection, Maintenance, Repair, and Retrofit Plan

This document has been prepared to provide a description and schedule for the performance of maintenance on permanent pollution abatement measures. Maintenance measures to be performed will be dependent on what permanent pollution abatement measures are incorporated into the project. The project specific water pollution abatement plan should be reviewed to determine what permanent pollution abatement measures are incorporated into a project. It should also be noted that the timing and procedures presented herein are general guidelines. Adjustment to the timing and procedures may have to be made depending on project specific characteristics as well as weather related conditions but may not be altered without TCEQ approval.

Where a project is occupied by the owner, the owner may provide for maintenance with his own skilled forces or contract for recommended maintenance of Permanent Best Management Practices. Where a project is occupied or leased by a tenant, the owner shall require tenants to contract for such maintenance services either through a lease agreement, property owners association covenants, or other binding document.

I understand that I am responsible for maintenance of the Permanent Pollution Abatement Measures included in this project until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or ownership is transferred.

I, the owner, have read and understand the requirements of the attached Maintenance Plan and Schedule.

  
Signature

11/25/2024  
Date

#### ATTACHMENT N

#### Contributing Zone Plan Application

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • www.bgeinc.com



## **CANYON RANCH UNIT 4**

### **Contributing Zone Plan Application (TCEQ-10257)**

#### **BATCH DETENTION POND**

Inspections should occur at least twice a year. If possible these inspections should be conducted during wet weather to determine if the pond is meeting target detention times. Inspections should check for clogging of the primary outfall mechanism, as well as erosion problems in the upper stage pilot channel, all flow paths, and any erodible areas inside and downstream of the basin. If any slumping or erosion is discovered, immediate regrading or revegetation should be performed to correct the problems. Structural faults discovered during inspection should be identified and repaired immediately. Faults to check for include cracked concrete, sealing of voids, and removal of vegetation from cracks and joints. All inlet/outlet and riser pipes will eventually deteriorate and require replacement.

The basin, basin side-slopes, and embankment of the basin must be mowed to prevent woody growth and control weeds. A mulching mower should be used, or the grass clippings should be caught and removed. Mowing should take place at least twice a year, or more frequently if vegetation exceeds 18 inches in height. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas. At the time of mowing, litter and debris should be removed from the surface of the basin. Particular attention should be paid to floatable debris around the outlet structure. The outlet should be checked for possible clogging or obstructions and any debris removed. Additionally at this time, the facility should be evaluated in terms of nuisance control (insects, weeds, odors, algae, etc.).

With each inspection, any damage to structural elements of the basin (pipes, concrete drainage structures, retaining walls, etc.) should be identified and repaired immediately. An example of this type of repair can include patching of cracked concrete, sealing of voids, removal of vegetation from cracks and joints. The various inlet/outlet structures in a basin will eventually deteriorate and must be replaced.

Sediment shall be removed from the basin at least every 5 years, when sediment depth exceeds 6 inches, when the sediment interferes with the level sensor or when the basin does not drain within 48 hours. Care should be taken not to compromise the basin lining during maintenance.

#### **ATTACHMENT N**

#### **Contributing Zone Plan Application**

**Serving. Leading. Solving.™**

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## **CANYON RANCH UNIT 4**

### **Contributing Zone Plan Application (TCEQ-10257)**

The Logic Controller should be inspected as part of the twice yearly investigations. Verify that the external indicators (active, cycle in progress) are operating properly by turning the controller off and on, and by initiating a cycle by triggering the level sensor in the basin. The valve should be manually opened and closed using the open/close switch to verify valve operation and to assist in inspecting the valve for debris. The solar panel should be inspected and any dust or debris on the panel should be carefully removed. The controller and all other circuitry and wiring should be inspected for signs of corrosion, damage from insects, water leaks, or other damage. At the end of the inspection, the controller should be reset.

#### **VEGETATED FILTER STRIPS**

Inspection of the VFS for erosion and damage to vegetation should occur at least twice per year; additional inspection periods, however, should occur after heavy rainfall. The BMPs should be checked for uniformity of grass cover, debris and litter, and areas of sediment accumulation. If areas are found that have bare spots or that need restoration, those areas should be replanted to meet the TCEQ requirements.

Inspections for debris and litter removal should be performed twice per year, at the minimum. Routine periodic checks are preferred. The filter strips should be kept free of obstructions and debris to allow for proper usage and minimal blockage. Additionally, monitoring to ensure channels and preferential flow paths have not developed should be conducted during routine inspection.

Grass areas in and around basins must be mowed at least four times a year to limit vegetation height to 18 inches. More frequent mowing to maintain aesthetic appeal may be necessary in landscaped areas. When mowing is performed, a mulching mower should be used, or grass clippings should be caught and removed. Regular mowing should also include weed control practices; herbicide usage, however, should be kept to a minimum.

\*All inspection and maintenance records must be kept at the office of the operator for the previous three years.

## **ATTACHMENT N**

### **Contributing Zone Plan Application**

**Serving. Leading. Solving.™**

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)





# ATTACHMENT P

## MEASURES FOR MINIMISING SURFACE STREAM CONTAMINATION

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



**CANYON RANCH UNIT 4**  
**CONTRIBUTING ZONE PLAN APPLICATION (TCEQ-10257)**

**Attachment P - Measures Minimizing Surface Stream Contamination**

*Any points where discharge from the site is concentrated and erosive velocities exist will include appropriately sized energy dissipators to reduce velocities to non-erosive levels.*

**ATTACHMENT P**

**Contributing Zone Plan Application**

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)

# Temporary Stormwater Section

## Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

***To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.***

***Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.***

## Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Stacy Mulholland

Date: 10/17/2024

Signature of Customer/Agent:



Regulated Entity Name: Canyon Ranch

## Project Information

### Potential Sources of Contamination

*Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.*

1. Fuels for construction equipment and hazardous substances which will be used during construction:

☐ The following fuels and/or hazardous substances will be stored on the site: \_\_\_\_\_

These fuels and/or hazardous substances will be stored in:

- ☐ Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

- ☐ Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.
- ☐ Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- ☒ Fuels and hazardous substances will not be stored on the site.
- 2. ☒ **Attachment A - Spill Response Actions.** A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. ☒ Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. ☒ **Attachment B - Potential Sources of Contamination.** A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

### ***Sequence of Construction***

- 5. ☒ **Attachment C - Sequence of Major Activities.** A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
  - ☒ For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
  - ☒ For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. ☒ Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: Guadalupe River, Canyon Lake

### ***Temporary Best Management Practices (TBMPs)***

*Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.*

- 7. ☒ **Attachment D – Temporary Best Management Practices and Measures.** TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- ☒ A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
  - ☒ A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
  - ☒ A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
  - ☒ A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
8. ☒ The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
- ☐ **Attachment E - Request to Temporarily Seal a Feature.** A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
- ☒ There will be no temporary sealing of naturally-occurring sensitive features on the site.
9. ☒ **Attachment F - Structural Practices.** A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
10. ☒ **Attachment G - Drainage Area Map.** A drainage area map supporting the following requirements is attached:
- ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
  - ☐ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
  - ☒ For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
  - ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

- ☐ There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.
11. ☐ **Attachment H - Temporary Sediment Pond(s) Plans and Calculations.** Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
- ☒ N/A
12. ☒ **Attachment I - Inspection and Maintenance for BMPs.** A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
13. ☒ All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
14. ☒ If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
15. ☒ Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
16. ☒ Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

## ***Soil Stabilization Practices***

*Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.*

17. ☒ **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices.** A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. ☒ Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. ☒ Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

### ***Administrative Information***

- 20. ☒ All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. ☒ If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. ☒ Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



# ATTACHMENT A

## SPILL RESPONSE

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)





## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment A — Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.

#### ATTACHMENT A

#### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

- Contaminated soils and cleanup materials will be sampled for waste characterization. When the analysis results are known the contaminated soils and cleanup materials will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

- The contractor will be required to report significant or hazardous spills in reportable quantities to:

Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490—3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.

- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110, 119, and 302, the contractor should notify the National Response Center at (800) 424-8802.

Notification should first be made by telephone and followed up with a written report.

The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.

Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.

## ATTACHMENT A

### Temporary Stormwater Section



## **CANYON RANCH UNIT 4**

### **Temporary Stormwater Section (TCEQ-0602)**

- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.

## **ATTACHMENT A**

### **Temporary Stormwater Section**



# ATTACHMENT B

## POTENTIAL SOURCES OF CONTAMINATION

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment B — Potential Sources of Contamination

Other potential sources of contamination during construction include:

*Potential Source*

- Asphalt products used on this project.

*Preventative Measure*

- After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a foretasted rain.

*Potential Source*

- Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle dripping.

*Preventative Measure*

- Vehicle maintenance when possible will be performed within the construction staging area.
- Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.

#### ATTACHMENT B

#### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### *Potential Source*

- Accidental leaks or spills of oil, petroleum products and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site.

#### *Preventative Measure*

- Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.
- Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.
- Hazardous materials and wastes shall be stored in covered containers and protected from vandalism.
- A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.

#### *Potential Source*

- Miscellaneous trash and litter from construction workers and material wrappings.

#### *Preventative Measure*

- Trash containers will be placed throughout the site to encourage proper trash disposal.

#### *Potential Source*

- Construction debris.

#### *Preventative Measure*

- Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case by case basis.

## ATTACHMENT B

### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

*Potential Source*

- Spills/Overflow of waste from portable toilets.

*Preventative Measure*

- Portable toilets will be placed away from high traffic vehicular areas and storm drain inlets.
- Portable toilets will be placed on a level ground surface.
- Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.

## ATTACHMENT B

### Temporary Stormwater Section



# ATTACHMENT C

## SEQUENCE OF MAJOR ACTIVITIES

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)





## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment C- Sequence of Major Activities

- A. Unit 4 Lot Development (Approximately 30.70 Acres)
1. *Install temporary erosion and sediment controls and stabilized construction entrance as indicated on erosion control plan.*
  2. *Rough grade all streets.*
  3. *Install all utilities in the right of way.*
  4. *Regrade and compact subgrade.*
  5. *Ensure all underground utility crossings are in place and install first course of base.*
  6. *Install curbs, rip-rap, and miscellaneous concrete.*
  7. *Install second base course.*
  8. *Prior to paving, mandrel, low pressure, hydrostatic, vacuum, and a camera golf ball test must be complete prior to paving.*
  9. *Lay asphalt.*
  10. *Camera inspection to ensure wastewater system is free of debris.*
  11. *Final grade any ditches and parkways.*
  12. *Revegetate disturbed areas, dispose of spoil.*
  13. *Final inspection.*
  14. *Removal of temporary erosion controls.*

#### ATTACHMENT C

#### Temporary Stormwater Section



# ATTACHMENT D

## TEMPORARY BMPS

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment D — Temporary Best Management Practices and Measures

- a. A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

***Upgradient water will be intercepted by curb inlets and routed around the project limits. All TBMPs are adequate for the drainage areas they serve.***

- b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

***Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of gravel filter bags downgradient of construction activities for temporary erosion and sedimentation controls (4) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (5) installation of construction staging area(s).***

#### ATTACHMENT D

#### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

***Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.***

***Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the Site, they will not enter surface streams and/or sensitive features.***

- c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

***There were no naturally-occurring sensitive features observed on the site and no surface streams on, or adjacent, to the project limits. All Temporary BMPs utilized are adequate for the drainage areas served.***

***Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.***

- d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

***There were no naturally-occurring sensitive features observed on the site and no surface streams on, or adjacent, to the project limits. All Temporary BMPs utilized are adequate for the drainage areas served.***

#### ATTACHMENT D

#### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

*Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.*

#### ATTACHMENT D

#### Temporary Stormwater Section



# ATTACHMENT F

## STRUCTURAL PRACTICES

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment F - Structural Practices

The following structural measures will be installed prior to the initiation of site preparation activities:

- *Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on sheet C02.10 Erosion & Sedimentation Control Plan.*
- *Installation of inlet protection at downgradient inlets of construction activities, as located on sheet C02.10.*
- *Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on sheet C02.10.*

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

- *Installation of concrete truck washout pit(s), as required and located on sheet C02.10.*

#### ATTACHMENT F

#### Temporary Stormwater Section





# ATTACHMENT I

## BMP MAINTENANCE

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### Attachment I - Inspection and Maintenance for BMPs

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) Check sediment basin's embankment, spillways, and outlet for erosion damage, and inspect the embankment for piping and settlement. Repair should be made promptly as needed by the contractor. Trash and other debris within the basins should be removed after each rainfall to prevent clogging of the outlet structure. Accumulated silt within the basins should be removed and the basin should be re-graded to its original dimensions at such point that the capacity of the impoundment has been reduced to 75% of its original storage capacity. The removed sediment should be stockpiled or redistributed in areas that are protected from erosion.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.

#### ATTACHMENT I

#### Temporary Stormwater Section



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

Pollution Prevention Measure	Inspected in Compliance	Corrective Action Required	
		Description (use additional sheet if necessary)	Date Completed
<b>Best Management Practices</b>			
Natural vegetation buffer strips			
Temporary vegetation			
Permanent vegetation			
Sediment control basin			
Silt fences			
Rock berms			
Gravel filter bags			
Drain inlet protection			
Other structural controls			
Vehicle exits (off-site tracking)			
Material storage areas (leakage)			
Equipment areas (leaks, spills)			
Concrete washout pit (leaks, failure)			
General site cleanliness			
Trash receptacles			
<b>Evidence of Erosion</b>			
Site preparation			
Roadway or parking lot construction			
Utility construction			
Drainage construction			
Building construction			
<b>Major Observations</b>			
Sediment discharges from site			
BMPs requiring maintenance			
BMPs requiring modification			
Additional BMPs required			

\_\_\_\_\_ A brief statement describing the qualifications of the inspector is included in this SWP3.

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

"I further certify I am an authorized signatory in accordance with the provisions of 30 TAC §305.128."

\_\_\_\_\_  
Inspector's Name

\_\_\_\_\_  
Inspector's Signature

\_\_\_\_\_  
Date

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • www.bgeinc.com



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### PROJECT MILESTONE DATES

Date when major site grading activities begin:

<u>Construction Activity</u>	<u>Date</u>
<u>Installation of BMPs</u>	

Dates when construction activities temporarily or permanently cease on all or a portion of the project:

<u>Construction Activity</u>	<u>Date</u>

Dates when stabilization measures are initiated:

<u>Stabilization Activity</u>	<u>Date</u>

Removal of BMPs

Temporary Stormwater Section



# ATTACHMENT J

## SCHEDULE OF INTERIM & PERMANENT SOIL STABILIZATION PRACTICES

Serving. Leading. Solving.™

BGE, Inc. • 7330 San Pedro, Suite 202 • San Antonio, Texas 78216 • 210-581-3600 • [www.bgeinc.com](http://www.bgeinc.com)



## CANYON RANCH UNIT 4

### Temporary Stormwater Section (TCEQ-0602)

#### **Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices**

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable. Stabilization measures in this instance shall comply with temporary stabilization as defined in TXR150000 or as defined otherwise in the landscape plans where applicable.

#### **ATTACHMENT J**

#### **Temporary Stormwater Section**

**Agent Authorization Form**  
For Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

I Richard Mott  
Print Name

Authorization Agent  
Title - Owner/President/Other

of Lennar Homes of Texas Land and Construction, LTD  
Corporation/Partnership/Entity Name

have authorized BGE, Inc.  
Print Name of Agent/Engineer

of BGE, Inc.  
Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.



SIGNATURE PAGE:

  
Applicant's Signature


10/22/2024  
Date

THE STATE OF Texas §

County of Bexar §

BEFORE ME, the undersigned authority, on this day personally appeared RICHARD MOTT known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 22 day of OCTOBER, 2024.



  
NOTARY PUBLIC

Robert D. Oestreich  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 6-10-2028

# Owner Authorization Form

Texas Commission on Environmental Quality  
for Required Signature  
Edwards Aquifer Protection Program  
Relating to 30 TAC Chapter 213  
Effective June 1, 1999

## Land Owner Authorization

I, Kelly Leach of Canyon Ranch 400 LP  
Land Owner Signatory Name Land Owner Name (Legal Entity or Individual)

am the owner of the property located at

North of FM 306 between Loma Ranch Road and Mystic Canyon, approx 3 miles from US Highway 281 and the FM 306 Intersection

Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory.

I do hereby authorize Lennar Homes of Texas Land and Construction, LTD  
Applicant Name (Legal Entity or Individual)

to conduct regulated activities allowed by the approved CZP

Description of the proposed regulated activities

at North of FM 306 between Loma Ranch Road and Mystic Canyon, approx 3 miles from US Highway 281 and the FM 306 Intersection

Precise location of the authorized regulated activities

## Land Owner Acknowledgement

I understand that Canyon Ranch 400 LP  
Land Owner Name (Legal Entity or Individual)

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

**Land Owner Signature**

Kelly Leach

Land Owner Signature

THE STATE OF § TEXAS


County of § Bexar

Oct 21 2024

Date

BEFORE ME, the undersigned authority, on this day personally appeared Kelly Leach known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 21 day of October 2024



Rosa Mayra Vincent NOTARY PUBLIC

Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 2/18/2026

Attached: (Mark all that apply)

- ☐ Lease Agreement
- ☐ Signed Contract
- ☐ Deed Recorded Easement
- ☐ Other legally binding document

## ***Applicant Acknowledgement***

I, Richard Mott of Lennar Homes of Texas Land and Construction, LTD  
Applicant Signatory Name Applicant Name (Legal Entity or Individual)  
acknowledge that Canyon Ranch 400 LP  
Land Owner Name (Legal Entity or Individual)  
has provided Lennar Homes of Texas Land and Construction, LTD  
Applicant Name (Legal Entity or Individual)  
with the right to possess and control the property referenced in the Edwards Aquifer protection plan.  
I understand that Lennar Homes of Texas Land and Construction, LTD  
Applicant Name (Legal Entity or Individual)  
is contractually responsible for compliance with the approved or conditionally approved Edwards  
Aquifer protection plan and any special conditions of the approved plan through all phases of plan  
implementation. I further understand that failure to comply with any condition of the executive  
director's approval is a violation is subject to administrative rule or orders and penalties as provided  
under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and  
injunction.

## ***Applicant Signature***

[Signature]  
Applicant Signature


10/22/2024  
Date

THE STATE OF § TEXAS

County of § BEXAR

BEFORE ME, the undersigned authority, on this day personally appeared Richard Mott  
known to me to be the person whose name is subscribed to the foregoing instrument, and  
acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 22 day of OCTOBER



[Signature]  
NOTARY PUBLIC

Robert D. Oestreich  
Typed or Printed Name of Notary

MY COMMISSION EXPIRES: 6-10-2028

# Application Fee Form

## Texas Commission on Environmental Quality

Name of Proposed Regulated Entity: Canyon Ranch Unit 4

Regulated Entity Location: North of FM 306 between Loma Ranch Road and Mystic Canyon,  
approximately 3 miles from the US Highway 281 and FM 306 intersection.

Name of Customer: Lennar Homes of Texas Land and Construction, LTD

Contact Person: Richard Mott

Phone: (210) 889-5516

Customer Reference Number (if issued): CN 602412207

Regulated Entity Reference Number (if issued): RN \_\_\_\_\_

### Austin Regional Office (3373)

☐ Hays

☐ Travis

☐ Williamson

### San Antonio Regional Office (3362)

☐ Bexar

☐ Medina

☐ Uvalde

☒ Comal

☐ Kinney

Application fees must be paid by check, certified check, or money order, payable to the **Texas Commission on Environmental Quality**. Your canceled check will serve as your receipt. **This form must be submitted with your fee payment.** This payment is being submitted to:

☐ Austin Regional Office

☒ San Antonio Regional Office

☐ Mailed to: TCEQ - Cashier

☐ Overnight Delivery to: TCEQ - Cashier

Revenues Section

Mail Code 214

P.O. Box 13088

Austin, TX 78711-3088

12100 Park 35 Circle

Building A, 3rd Floor

Austin, TX 78753

(512)239-0357

### Site Location (Check All That Apply):

☐ Recharge Zone

☒ Contributing Zone

☐ Transition Zone

<i>Type of Plan</i>	<i>Size</i>	<i>Fee Due</i>
Water Pollution Abatement Plan, Contributing Zone Plan: One Single Family Residential Dwelling	Acres	\$
Water Pollution Abatement Plan, Contributing Zone Plan: Multiple Single Family Residential and Parks	30.70 Acres	\$ 4,000
Water Pollution Abatement Plan, Contributing Zone Plan: Non-residential	Acres	\$
Sewage Collection System	L.F.	\$
Lift Stations without sewer lines	Acres	\$
Underground or Aboveground Storage Tank Facility	Tanks	\$
Piping System(s)(only)	Each	\$
Exception	Each	\$
Extension of Time	Each	\$

Signature: Date: 12/22/2024

## Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

### ***Water Pollution Abatement Plans and Modifications***

#### ***Contributing Zone Plans and Modifications***

<b><i>Project</i></b>	<b><i>Project Area in Acres</i></b>	<b><i>Fee</i></b>
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional, multi-family residential, schools, and other sites where regulated activities will occur)	< 1	\$3,000
	1 < 5	\$4,000
	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

#### ***Organized Sewage Collection Systems and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Linear Foot</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Sewage Collection Systems	\$0.50	\$650 - \$6,500

#### ***Underground and Aboveground Storage Tank System Facility Plans and Modifications***

<b><i>Project</i></b>	<b><i>Cost per Tank or Piping System</i></b>	<b><i>Minimum Fee- Maximum Fee</i></b>
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

#### ***Exception Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Exception Request	\$500

***Extension of Time Requests***

<b><i>Project</i></b>	<b><i>Fee</i></b>
Extension of Time Request	\$150





TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

<b>1. Reason for Submission</b> (If other is checked please describe in space provided.) <input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.) <input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form) <input type="checkbox"/> Other	
<b>2. Customer Reference Number (if issued)</b>  CN 602412207	<a href="#">Follow this link to search for CN or RN numbers in Central Registry**</a> <b>3. Regulated Entity Reference Number (if issued)</b>  RN 111592846

## SECTION II: Customer Information

<b>4. General Customer Information</b>		<b>5. Effective Date for Customer Information Updates</b> (mm/dd/yyyy)					
<input type="checkbox"/> New Customer <input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)		<input type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership					
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>							
<b>6. Customer Legal Name</b> (If an individual, print last name first: eg: Doe, John)		If new Customer, enter previous Customer below:					
Lennar Homes of Texas Land and Construction, LTD							
<b>7. TX SOS/CPA Filing Number</b>	<b>8. TX State Tax ID</b> (11 digits)	<b>9. Federal Tax ID</b> (9 digits)	<b>10. DUNS Number</b> (if applicable)				
		95 - 4 3 3 7 4 9 0					
<b>11. Type of Customer:</b>	<input checked="" type="checkbox"/> Corporation <input type="checkbox"/> Individual <input type="checkbox"/> Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other <input type="checkbox"/> Sole Proprietorship <input type="checkbox"/> Other:						
<b>12. Number of Employees</b> <input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input checked="" type="checkbox"/> 501 and higher		<b>13. Independently Owned and Operated?</b> <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No					
<b>14. Customer Role</b> (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following <input type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator <input type="checkbox"/> Occupational Licensee <input checked="" type="checkbox"/> Responsible Party <input type="checkbox"/> Voluntary Cleanup Applicant <input type="checkbox"/> Other:							
<b>15. Mailing Address:</b>	100 NE Loop 410, Suite 1155						
	City	San Antonio	State	TX	ZIP	78216	ZIP + 4
<b>16. Country Mailing Information</b> (if outside USA)				<b>17. E-Mail Address</b> (if applicable)			
				richard.mott@lennar.com			
<b>18. Telephone Number</b> ( 210 ) 889-5516		<b>19. Extension or Code</b>		<b>20. Fax Number</b> (if applicable) ( ) -			

## SECTION III: Regulated Entity Information

<b>21. General Regulated Entity Information</b> (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application) <input type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input checked="" type="checkbox"/> Update to Regulated Entity Information <b>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</b>
<b>22. Regulated Entity Name</b> (Enter name of the site where the regulated action is taking place.)  Canyon Ranch Unit 4



23. Street Address of the Regulated Entity: (No PO Boxes)							
	City		State		ZIP		ZIP + 4
24. County	Comal						

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:	Approximately 3.68 miles northeast of Highway 281 and FM 306 intersection.										
26. Nearest City	Fischer				State	TX		Nearest ZIP Code	78070		
27. Latitude (N) In Decimal:	29.955			28. Longitude (W) In Decimal:	98.35278						
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds						
29	57	18	98	21	10						
29. Primary SIC Code (4 digits)	1521		30. Secondary SIC Code (4 digits)			31. Primary NAICS Code (5 or 6 digits)	236117		32. Secondary NAICS Code (5 or 6 digits)		
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)											
Single family residential housing.											
34. Mailing Address:											
	City		State		ZIP		ZIP + 4				
35. E-Mail Address:											
36. Telephone Number			37. Extension or Code			38. Fax Number (if applicable)					
( ) -						( ) -					

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

#### SECTION IV: Preparer Information

40. Name:	Stacy Mulholland		41. Title:	PE	
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address		
(210) 581-3637		( ) -	smulholland@bgeinc.com		

#### SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Lennar Homes of Texas Land & Construction, LTD		Job Title:		
Name (In Print):	Ruthless Moon			Phone:	(210) 889 5516
Signature:				Date:	10/22/2021



TCEQ Use Only

# TCEQ Core Data Form

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

## SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input checked="" type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)	<input type="checkbox"/> Other	
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 605941475		RN 111592846

## SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)			
<input type="checkbox"/> New Customer		<input type="checkbox"/> Update to Customer Information		<input type="checkbox"/> Change in Regulated Entity Ownership	
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)					
<b>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</b>					
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)				If new Customer, enter previous Customer below:	
Canyon Ranch 400 LP					
7. TX SOS/CPA Filing Number		8. TX State Tax ID (11 digits)		9. Federal Tax ID (9 digits)	
0803641552		32074563134		742791904	
10. DUNS Number (if applicable)					
11. Type of Customer:		<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual	
Partnership: <input type="checkbox"/> General <input checked="" type="checkbox"/> Limited					
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship		<input type="checkbox"/> Other:	
12. Number of Employees		<input checked="" type="checkbox"/> Yes		<input type="checkbox"/> No	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher					
13. Independently Owned and Operated?					
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following					
<input checked="" type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator					
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> Voluntary Cleanup Applicant <input type="checkbox"/> Other:					
15. Mailing Address:					
1141 N Loop 1604 E, Suite 105-114					
City San Antonio State TX ZIP 78232 ZIP + 4					
16. Country Mailing Information (if outside USA)				17. E-Mail Address (if applicable)	
				kelly.welovedirt@gmail.com	
18. Telephone Number		19. Extension or Code		20. Fax Number (if applicable)	
( 210 ) 827-7918				( ) -	

## SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity' is selected below this form should be accompanied by a permit application)	
<input type="checkbox"/> New Regulated Entity <input type="checkbox"/> Update to Regulated Entity Name <input checked="" type="checkbox"/> Update to Regulated Entity Information	
<b>The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal of organizational endings such as Inc, LP, or LLC).</b>	
22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)	
Canyon Ranch Unit 4	

23. Street Address of the Regulated Entity: (No PO Boxes)							
	City		State		ZIP		ZIP + 4
24. County	Comal						

Enter Physical Location Description if no street address is provided.

25. Description to Physical Location:	Approximately 3.68 miles northeast of Highway 281 and FM 306 intersection.						
26. Nearest City	Fischer				State	TX	Nearest ZIP Code
						78070	
27. Latitude (N) In Decimal:	29.955		28. Longitude (W) In Decimal:	98.35278			
Degrees	Minutes	Seconds	Degrees	Minutes	Seconds		
29	57	18	98	21	10		
29. Primary SIC Code (4 digits)	30. Secondary SIC Code (4 digits)		31. Primary NAICS Code (5 or 6 digits)	32. Secondary NAICS Code (5 or 6 digits)			
1521			236117				
33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)							
Single family residential housing.							
34. Mailing Address:							
	City		State		ZIP		ZIP + 4
35. E-Mail Address:							
36. Telephone Number		37. Extension or Code		38. Fax Number (if applicable)			
( ) -				( ) -			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Waste Water	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

#### SECTION IV: Preparer Information

40. Name:	Stacy Mulholland		41. Title:	PE
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address	
(210) 581-3637		( ) -	smulholland@bgeinc.com	

#### SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Canyon Ranch 400 LP	Job Title:	
Name (In Print):	Kelly Leach	Phone:	( ) -
Signature:		Date:	07/21/2024

Jon Niermann, *Chairman*  
Emily Lindley, *Commissioner*  
Bobby Janecka, *Commissioner*  
Toby Baker, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

September 9, 2022

Kelly Leach  
Gram Vikas Partners, Inc.  
141 N. Loop 1604, 105-114  
San Antonio, Texas 78232

Re: Edwards Aquifer, Comal County

NAME OF PROJECT: Canyon Ranch Unit 1; Located approximately 3.66-miles northeast of US Highway 281 and FM 306 intersection; Comal County, Texas

TYPE OF PLAN: Request for Modification of an Approved Contributing Zone Plan (CZP); 30 Texas Administrative Code (TAC) Chapter 213 Subchapter B Edwards Aquifer

Regulated Entity No. RN111346102; Additional ID No. 13001556

Dear Kelly Leach:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the CZP Modification for the above-referenced project submitted to the San Antonio Regional Office by BGE, Inc. on behalf of Gram Vikas Partners, Inc. on June 15, 2022. Final review of the CZP was completed after additional material was received on August 11, 2022, and September 1, 2022. As presented to the TCEQ, the Temporary and Permanent Best Management Practices (BMPs) were selected and construction plans were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer Protection Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. *This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been requested.*

### BACKGROUND

The TCEQ approved the original CZP application titled Canyon Ranch Unit 1 by letter dated January 21, 2021 (13001410).

#### PROJECT DESCRIPTION

The proposed single-family residential project will have an area increased from 26.02-acres approved January 21, 2021, to 32.34-acres in this project. It will include 112 residential lots and modification to the batch detention pond and adding one (1) vegetative filter strip. The impervious cover will be reduced from 14.04-acres to 13.85-acres (43 percent). Project wastewater will be disposed of by conveyance to the approved Canyon Ranch Wastewater Treatment Plant owned by Gram Vikas Partners, Inc.

#### PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, one existing (13001410) (1) batch detention basin, one existing VFS (13001410), and one newly proposed VFS, designed using the TCEQ technical guidance document, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices (2005), will be utilized to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 12,432 pounds of TSS generated from the 13.85- acres of impervious cover. The approved measures meet the required 80 percent removal of the increased load in TSS caused by the project.

#### SPECIAL CONDITIONS

- I. This modification is subject to all Special and Standard Conditions listed in the CZP approval letter dated January 21, 2021.
- II. All permanent pollution abatement measures shall be operational prior to occupancy of the facilities within their respective drainage areas.
- III. All sediment and/or media removed from the water quality basin during maintenance activities shall be properly disposed of according to 30 TAC 330 or 30 TAC 335, as applicable.

#### STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

#### Prior to Commencement of Construction:

4. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved Contributing Zone Plan and this notice of approval shall be maintained at the project location until all regulated activities are completed.
5. Any modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.

6. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the name of the approved plan and file number for the regulated activity, the date on which the regulated activity will commence, and the name of the prime contractor with the name and telephone number of the contact person.
7. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved Storm Water Pollution Prevention Plan (SWPPP) must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. If a water quality pond is proposed, it shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

8. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
9. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been significantly reduced. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
10. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge will be filtered through appropriately selected best management practices. These may include vegetated filter strips, sediment traps, rock berms, silt fence rings, etc.
11. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
12. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.
13. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 5, above.

After Completion of Construction:

14. Owners of permanent BMPs and measures must insure that the BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the San Antonio Regional Office within 30 days of site completion.



15. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through the San Antonio Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
16. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Contributing Zone Plan. If the new owner intends to commence any new regulated activity on the site, a new Contributing Zone Plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.
17. A Contributing Zone Plan approval or extension will expire, and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Contributing Zone Plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
18. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Drew Evans of the Edwards Aquifer Protection Program of the San Antonio Regional Office at (210) 403-4053.

Sincerely,



Lillian Butler, Section Manager  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality

LIB/de

Enclosures: Change in Responsibility for Maintenance of Permanent BMPs, Form TCEQ-10263

cc: Mr. Aaron Neumann, P.E., BGE, Inc.  
Ms. Stacy Mulholland, EIT, BGE, Inc

**Change in Responsibility for Maintenance  
on Permanent Best Management Practices and Measures**

The applicant is no longer responsible for maintaining the permanent best management practice (BMP) and other measures. The project information and the new entity responsible for maintenance is listed below.

Customer: \_\_\_\_\_

Regulated Entity Name: \_\_\_\_\_

Site Address: \_\_\_\_\_

City, Texas, Zip: \_\_\_\_\_

County: \_\_\_\_\_

Approval Letter Date: \_\_\_\_\_

BMPs for the project: \_\_\_\_\_

New Responsible Party: \_\_\_\_\_

Name of contact: \_\_\_\_\_

Mailing Address: \_\_\_\_\_

City, State: \_\_\_\_\_ Zip: \_\_\_\_\_

Telephone: \_\_\_\_\_ FAX: \_\_\_\_\_

\_\_\_\_\_  
Signature of New Responsible Party      Date

I acknowledge and understand that I am assuming full responsibility for maintaining all permanent best management practices and measures approved by the TCEQ for the site, until another entity assumes such obligations in writing or ownership is transferred.

**If you have questions on how to fill out this form or about the Edwards Aquifer protection program, please contact us at 210/490-3096 for projects located in the San Antonio Region or 512/339-2929 for projects located in the Austin Region.**

Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at 512/239-3282.



Jon Niermann, *Chairman*  
Emily Lindley, *Commissioner*  
Bobby Janecka, *Commissioner*  
Toby Baker, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

August 26, 2022

Mr. Kelly Leach  
Gram Vikas Partners, Inc  
1141 N Loop 1604, 105-114  
San Antonio, Texas 78232

Re: Edwards Aquifer, Comal County

NAME OF PROJECT: Canyon Ranch Unit 2; Located approximately 3.66 miles northeast of the US Hwy 281 and FM 306 intersection; Comal County, Texas

TYPE OF PLAN: Request for Modification of an Approved Contributing Zone Plan (CZP); 30 Texas Administrative Code (TAC) Chapter 213 Subchapter B Edwards Aquifer

Regulated Entity No. RN111356259; Additional ID No. 13001557

Dear Mr. Leach:

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the CZP Modification for the above-referenced project submitted to the San Antonio Regional Office by BGE, Inc. on behalf of Gram Vikas Partners, Inc. on June 15, 2022. Final review of the CZP Modification was completed after additional material was received on August 3, 2022, and August 18, 2022. As presented to the TCEQ, the Temporary and Permanent Best Management Practices (BMPs) were selected and construction plans were prepared by a Texas Licensed Professional Engineer to be in general compliance with the requirements of 30 TAC Chapter 213. These planning materials were sealed, signed and dated by a Texas Licensed Professional Engineer. Therefore, based on the engineer's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in this letter. The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this Edwards Aquifer Protection Plan. A motion for reconsideration must be filed no later than 23 days after the date of this approval letter. *This approval expires two (2) years from the date of this letter unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been requested.*

### BACKGROUND

The original Canyon Ranch Unit 2 CZP (13001422) was approved by letter, dated January 28, 2022. The residential project had a site area of 14.55 acres and included the construction of 49 single-family residential lots with associated roadways. The impervious cover was approved to be 8.72 acres. One previously approved batch detention basin (13001410), one new batch detention basin, and one new engineered vegetative filter strip (VFS) were approved to treat stormwater generated by the project.

### PROJECT DESCRIPTION

The proposed residential project will have an area of approximately 14.55 acres. It will include the construction of 46 single-family lots with associated roadways and modifications to the previously approved batch detention basin (13001422) and engineered VFS (13001422). The impervious cover will be 6.03 acres (41.44 percent). Project wastewater will be disposed of by conveyance to the existing Canyon Ranch Wastewater Treatment Plant owned by the Canyon Ranch Municipal Utility District.

### PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, one batch detention basin from Unit 1 (13001410), a second batch detention basin and an engineered VFS, designed using the TCEQ technical guidance document, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices (2005), will be utilized and constructed to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 5,413 pounds of TSS generated from the 6.03 acres of impervious cover. The approved measures meet the required 80 percent removal of the increased load in TSS caused by the project.

### SPECIAL CONDITIONS

- I. This modification is subject to all Special and Standard Conditions listed in the CZP approval letter dated January 28, 2022.
- II. All permanent pollution abatement measures shall be operational prior to first occupancy of the homes within their respective drainage areas.
- III. All sediment and/or media removed from the water quality basins during maintenance activities shall be properly disposed of according to 30 TAC 330 or 30 TAC 335, as applicable.

### STANDARD CONDITIONS

1. Pursuant to Chapter 7 Subchapter C of the Texas Water Code, any violations of the requirements in 30 TAC Chapter 213 may result in administrative penalties.
2. The holder of the approved Edwards Aquifer protection plan must comply with all provisions of 30 TAC Chapter 213 and all best management practices and measures contained in the approved plan. Additional and separate approvals, permits, registrations and/or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, UIC) can be required depending on the specifics of the plan.
3. In addition to the rules of the Commission, the applicant may also be required to comply with state and local ordinances and regulations providing for the protection of water quality.

#### Prior to Commencement of Construction:

4. All contractors conducting regulated activities at the referenced project location shall be provided a copy of this notice of approval. At least one complete copy of the approved Contributing Zone Plan and this notice of approval shall be maintained at the project location until all regulated activities are completed.
5. Any modification to the activities described in the referenced CZP application following the date of approval may require the submittal of a plan to modify this approval, including the payment of appropriate fees and all information necessary for its review and approval prior to initiating construction of the modifications.

6. The applicant must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the San Antonio Regional Office no later than 48 hours prior to commencement of the regulated activity. Written notification must include the name of the approved plan and file number for the regulated activity, the date on which the regulated activity will commence, and the name of the prime contractor with the name and telephone number of the contact person.
7. Temporary erosion and sedimentation (E&S) controls, i.e., silt fences, rock berms, stabilized construction entrances, or other controls described in the approved Storm Water Pollution Prevention Plan (SWPPP) must be installed prior to construction and maintained during construction. Temporary E&S controls may be removed when vegetation is established and the construction area is stabilized. If a water quality pond is proposed, it shall be used as a sedimentation basin during construction. The TCEQ may monitor stormwater discharges from the site to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

8. During the course of regulated activities related to this project, the applicant or his agent shall comply with all applicable provisions of 30 TAC Chapter 213, Edwards Aquifer. The applicant shall remain responsible for the provisions and conditions of this approval until such responsibility is legally transferred to another person or entity.
9. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been significantly reduced. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).
10. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge will be filtered through appropriately selected best management practices. These may include vegetated filter strips, sediment traps, rock berms, silt fence rings, etc.
11. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
12. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.
13. This approval does not authorize the installation of temporary aboveground storage tanks on this project. If the contractor desires to install a temporary aboveground storage tank for use during construction, an application to modify this approval must be submitted and approved prior to installation. The application must include information related to tank location and spill containment. Refer to Standard Condition No. 5, above.

After Completion of Construction:

14. Owners of permanent BMPs and measures must insure that the BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the San Antonio Regional Office within 30 days of site completion.

15. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred. A copy of the transfer of responsibility must be filed with the executive director through the San Antonio Regional Office within 30 days of the transfer. A copy of the transfer form (TCEQ-10263) is enclosed.
16. Upon legal transfer of this property, the new owner(s) is required to comply with all terms of the approved Contributing Zone Plan. If the new owner intends to commence any new regulated activity on the site, a new Contributing Zone Plan that specifically addresses the new activity must be submitted to the executive director. Approval of the plan for the new regulated activity by the executive director is required prior to commencement of the new regulated activity.
17. A Contributing Zone Plan approval or extension will expire and no extension will be granted if more than 50 percent of the total construction has not been completed within ten years from the initial approval of a plan. A new Contributing Zone Plan must be submitted to the San Antonio Regional Office with the appropriate fees for review and approval by the executive director prior to commencing any additional regulated activities.
18. At project locations where construction is initiated and abandoned, or not completed, the site shall be returned to a condition such that the aquifer is protected from potential contamination.

This action is taken under authority delegated by the Executive Director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Mr. Joshua Vacek of the Edwards Aquifer Protection Program of the San Antonio Regional Office at 210-403-4028.

Sincerely,



Lillian Butler, Section Manager  
Edwards Aquifer Protection Program  
Texas Commission on Environmental Quality

LIB/jv

Enclosures: Change in Responsibility for Maintenance of Permanent BMPs, Form TCEQ-10263

cc: Ms. Stacy Mulholland, EIT, BGE, Inc.



**Change in Responsibility for Maintenance  
on Permanent Best Management Practices and Measures**

The applicant is no longer responsible for maintaining the permanent best management practice (BMP) and other measures. The project information and the new entity responsible for maintenance is listed below.

Customer: \_\_\_\_\_

Regulated Entity Name: \_\_\_\_\_

Site Address: \_\_\_\_\_

City, Texas, Zip: \_\_\_\_\_

County: \_\_\_\_\_

Approval Letter Date: \_\_\_\_\_

BMPs for the project: \_\_\_\_\_

New Responsible Party: \_\_\_\_\_

Name of contact: \_\_\_\_\_

Mailing Address: \_\_\_\_\_

City, State: \_\_\_\_\_ Zip: \_\_\_\_\_

Telephone: \_\_\_\_\_ FAX: \_\_\_\_\_

\_\_\_\_\_  
Signature of New Responsible Party      Date

I acknowledge and understand that I am assuming full responsibility for maintaining all permanent best management practices and measures approved by the TCEQ for the site, until another entity assumes such obligations in writing or ownership is transferred.

**If you have questions on how to fill out this form or about the Edwards Aquifer protection program, please contact us at 210/490-3096 for projects located in the San Antonio Region or 512/339-2929 for projects located in the Austin Region.**

Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at 512/239-3282.

Jon Niermann, *Chairman*  
Bobby Janecka, *Commissioner*  
Catarina R. Gonzales, *Commissioner*  
Kelly Keel, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

June 14, 2024

Ms. Kelly Leach  
Gram Vikas Partners, Inc.  
1141 N Loop 1604  
San Antonio, Texas, 78232

Re: Approval of a Modification of an approved Contributing Zone Plan (CZPMOD)  
Canyon Ranch Unit 3; Located approximately 3.68 miles northeast of Hwy 281 and FM  
306 intersection; Comal County, Texas  
Edwards Aquifer Protection Program ID: 13001922, Regulated Entity No. RN111592846

Dear Ms. Leach:

The Texas Commission on Environmental Quality (TCEQ) has completed its review on the application for the above-referenced project submitted to the Edwards Aquifer Protection Program (EAPP) by BGE, Inc. on behalf of the applicant, Gram Vikas Partners, Inc. on April 24, 2024. Final review of the application was completed after additional material was received on June 11, 2024.

As presented to the TCEQ, the application was prepared in general compliance with the requirements of 30 Texas Administrative Codes (TAC) Chapter §213. The permanent best management practices (BMPs) and measures represented in the application were prepared by a Texas licensed professional engineer (PE). All construction plans and design information were sealed, signed, and dated by a Texas licensed PE. Therefore, the application for the construction of the proposed project and methods to protect the Edwards Aquifer are **approved**, subject to applicable state rules and the conditions in this letter.

**This approval expires two years from the date of this letter**, unless, prior to the expiration date, more than 10 percent of the construction has commenced on the project or an extension of time has been officially requested. This approval or extension will expire, and no extension will be granted if more than 50 percent of the project has not been completed within ten years from the date of this letter.

The applicant or a person affected may file with the chief clerk a motion for reconsideration of the executive director's final action on this contributing zone plan or modification to a plan. A motion for reconsideration must be filed in accordance with 30 TAC §50.139.

### BACKGROUND

The original Canyon Ranch Unit 3 was approved by letter dated December 16, 2022. The 46.56-acre site was approved to consist of 24.28-acres of impervious cover. One (1) batch detention basin (Unit 3 Pond) was approved to treat stormwater generated by the project.

### PROJECT DESCRIPTION

The current modification proposes to decrease the impervious cover and increase the weir structure length to the Unit 3 batch detention basin. The impervious cover will now be 23.26-acres (49.96 percent). Project wastewater will be disposed of by conveyance to the existing Canyon Ranch Wastewater Treatment Plant owned and operated by Corix Utilities of Texas.

### PERMANENT POLLUTION ABATEMENT MEASURES

To prevent the pollution of stormwater runoff originating on-site or upgradient of the site and potentially flowing across and off the site after construction, one (1) previously approved batch detention basin (Unit 3 Pond - AI: 13001650), designed using the TCEQ technical guidance, *RG-348, Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices*, will be implemented to treat stormwater runoff. The required total suspended solids (TSS) treatment for this project is 20,878 pounds of TSS generated from the 23.26-acres of impervious cover. The approved permanent BMPs and measures meet the required 80 percent removal of the increased load in TSS caused by the project.

**The permanent BMPs shall be operational prior to occupancy or use of the proposed project.** Inspection, maintenance, repair, and retrofit of the permanent BMPs shall be in accordance with the approved application.

### SPECIAL CONDITIONS

- I. This modification is subject to all the special and standard conditions listed in the approval letter dated December 16, 2022.

### STANDARD CONDITIONS

1. The plan holder (applicant) must comply with all provisions of 30 TAC Chapter §213 and all technical specifications in the approved plan. The plan holder should also acquire and comply with additional and separate approvals, permits, registrations or authorizations from other TCEQ Programs (i.e., Stormwater, Water Rights, Dam Safety, Underground Injection Control) as required based on the specifics of the plan.
2. In addition to the rules of the Commission, the plan holder must also comply with state and local ordinances and regulations providing for the protection of water quality as applicable.

### Prior to Commencement of Construction:

3. The plan holder of any approved contributing zone plan must notify the EAPP and obtain approval from the executive director prior to initiating any modification to the activities described in the referenced application following the date of the approval.
4. The plan holder must provide written notification of intent to commence construction, replacement, or rehabilitation of the referenced project. Notification must be submitted to the EAPP no later than 48 hours prior to commencement of the regulated activity. Notification must include the date on which the regulated activity will commence, the name of the approved plan and program ID number for the regulated activity, and the name of the prime contractor with the name and telephone number of the contact person.
5. Temporary erosion and sedimentation (E&S) controls as described in the referenced application, must be installed prior to construction, and maintained during construction. Temporary E&S controls may be removed when vegetation is established, and the construction area is stabilized. The TCEQ may monitor stormwater discharges from the site

to evaluate the adequacy of temporary E&S control measures. Additional controls may be necessary if excessive solids are being discharged from the site.

During Construction:

6. The application must indicate the placement of permanent aboveground storage tanks facilities for static hydrocarbons and hazardous substances with cumulative storage capacity of 500 gallons or more. Subsequent permanent storage tanks on this project site require a modification to be submitted and approved prior to installation.
7. If sediment escapes the construction site, the sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain). Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50 percent. Litter, construction debris, and construction chemicals shall be prevented from becoming stormwater discharge pollutants.
8. Intentional discharges of sediment laden water are not allowed. If dewatering becomes necessary, the discharge must be filtered through appropriately selected BMPs.
9. The following records shall be maintained and made available to the executive director upon request: the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
10. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and construction activities will not resume within 21 days. When the initiation of stabilization measures by the 14th day is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable.

After Completion of Construction:

11. Owners of permanent BMPs and temporary measures must ensure that the BMPs and measures are constructed and function as designed. A Texas licensed PE **must certify** in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the EAPP within 30 days of site completion.
12. The applicant shall be responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property or the ownership of the property is transferred to the entity. A copy of the transfer of responsibility must be filed with the executive director through the EAPP within 30 days of the transfer. TCEQ form, Change in Responsibility for Maintenance on Permanent BMPs and Measures (TCEQ-10263), may be used.



Ms. Kelly Leach  
Page 4  
June 14, 2024

The holder of the approved contributing zone plan is responsible for compliance with Chapter §213 subchapter B and any condition of the approved plan through all phases of plan implementation. Failure to comply with any condition within this approval letter is a violation of Chapter §213 subchapter B and is subject to administrative rule or orders and penalties as provided under §213.25 of this title (relating to Enforcement). Such violations may also be subject to civil penalties and injunction. Upon legal transfer of this property, the new owner is required to comply with all terms of the approved contributing zone plan.

This action is taken as delegated by the executive director of the Texas Commission on Environmental Quality. If you have any questions or require additional information, please contact Mr. Hunter Patterson of the Edwards Aquifer Protection Program at (210) 403-4026 or the regional office at 512-339-2929.

Sincerely,  


Lori Wilson, Regional Director  
Austin Region  
Texas Commission on Environmental Quality

LW/hhp

cc: Ms. Stacy Mulholland, P.E., BGE, Inc.

# CANYON RANCH UNIT 4

## COMAL COUNTY

### CIVIL CONSTRUCTION DRAWINGS

### WATER, SEWER, STREET AND DRAINAGE IMPROVEMENTS

NOVEMBER 2024

STREETS - COMAL COUNTY  
WATER - TEXAS WATER COMPANY, SJWTX  
DRAINAGE - COMAL COUNTY  
WASTEWATER - CANYON RANCH MUD OF COMAL COUNTY

FEMA PANEL: #48091C0080F, DATED SEPTEMBER 9, 2009  
TRACT SIZE: 30.698 ACRES  
TYPE: SINGLE FAMILY RESIDENTIAL

CONTACT INFORMATION FOR COORDINATION AND EMERGENCY

COMAL COUNTY ENGINEER'S OFFICE : (830) 608-2090  
ELECTRIC UTILITY: PEDERNALES ELECTRIC COOPERATIVE: (512) 262-2161  
WATER UTILITY: TEXAS WATER COMPANY, SJWTX: (830) 312-4600  
WASTEWATER UTILITY: CANYON RANCH MUD OF COMAL COUNTY: (512) 328-2008  
TEXAS DEPARTMENT OF TRANSPORTATION: (512) 832-7000  
FIRE DEPARTMENT: COMAL COUNTY ESD #1 & #4: (830) 228-4501

BENCHMARK


BM #101: MAG NAIL SET IN ASPHALT DRIVEWAY APRON LOCATED ON THE SOUTH SIDE OF FARM TO MARKET 306, ±614' FROM THE SOUTHWEST CORNER OF THE 400.00 ACRE PARENT TRACT, ELEVATION: 1,228.08'

BM #102: MAG NAIL SET 2' SOUTH FROM THE EDGE OF ASPHALT PAVEMENT OF FARM TO MARKET 306, ± 278' FROM THE SOUTEAST CORNER OF THE 400.00 ACRE PARENT TRACT, ELEVATION: 1,195.17'

ACCEPTED FOR CONSTRUCTION:

COMAL COUNTY	DATE
TEXAS WATER COMPANY, SJWTX	DATE
CANYON RANCH MUD	DATE

VICINITY MAP



NAME: CANYON RANCH UNIT 4

OWNER: CANYON RANCH 400  
CONTACT: KELLY LEACH, PRESIDENT  
1141 N. LOOP 1604  
SUITE 105-114  
SAN ANTONIO, TEXAS 78232  
PHONE: (210) 827-7918

ENGINEER: BGE, INC., TBPE-1046  
CONTACT: STACY MULHOLLAND  
EMAIL: SMULHOLLAND@BGEINC.COM  
7330 SAN PEDRO AVENUE SUITE 202  
SAN ANTONIO, TEXAS 78216  
PHONE: (210) 581-3600

WATER: TEXAS WATER COMPANY, SJWTX  
1399 SATTLER RD  
NEW BRAUNFELS, TEXAS 78132  
PHONE: (830) 312-4600

ELECTRIC: PEDERNALES COOP, INC.  
PO BOX 1  
JOHNSON CITY, TEXAS 78636  
PHONE: (877) 372-0391

DEVELOPER: LENNAR  
CONTACT: RICHARD MOTT  
100 NE LP 410, SUITE 1155  
SUITE 1155  
SAN ANTONIO, TX 78216  
PHONE: (210) 403-8200

LAND SURVEYOR: BGE INC., TBPE F1046  
CONTACT: DION ALBERTSON R.P.L.S.  
7330 SAN PEDRO AVE SUITE 202  
SAN ANTONIO, TX 78216  
PHONE: (210) 581-3600

WASTEWATER: CANYON RANCH MUD OF  
COMAL COUNTY  
ATTN: MCLEAN & HOWARD LLP  
901 SOUTHMOPAR SUITE 225  
AUSTIN, TX 78746  
PHONE: (512) 328-2008

REVISIONS/CORRECTIONS

SHEET LIST	DESCRIPTION	DATE	REVISE (R) ADD (A) VOID (V) SHEET NO.'S	ACCEPTED BY	APPROVAL DATE

SHEET INDEX

SHEET NUMBER	SHEET TITLE		
C00.00	COVER SHEET	C06.06	STORM DRAIN LINE B PLAN AND PROFILE STA 3+50 TO END
C00.01	GENERAL NOTES	C06.07	STORM DRAIN LINE C PLAN AND PROFILE STA 1+00 TO 4+50
C00.10	EXISTING CONDITIONS SURVEY (SHEET 1 OF 3)	C06.08	STORM DRAIN LINE C PLAN AND PROFILE STA 4+50 TO END
C00.11	EXISTING CONDITIONS SURVEY (SHEET 2 OF 3)	C06.09	STORM DRAIN LINE D PLAN AND PROFILE
C00.12	EXISTING CONDITIONS SURVEY (SHEET 3 OF 3)	C06.10	STORM DRAIN LINE E PLAN AND PROFILE STA 1+00 TO 5+00
C00.20	SUBDIVISION PLAT (SHEET 1 OF 5)	C06.11	STORM DRAIN LINE E PLAN AND PROFILE STA 5+00 TO 9+50
C00.21	SUBDIVISION PLAT (SHEET 2 OF 5)	C06.12	STORM DRAIN LINE E PLAN AND PROFILE STA 9+50 TO END
C00.22	SUBDIVISION PLAT (SHEET 3 OF 5)	C06.13	STORM DRAIN LINE F PLAN AND PROFILE STA 1+00 TO 4+50
C00.23	SUBDIVISION PLAT (SHEET 4 OF 5)	C06.14	STORM DRAIN LINE F PLAN AND PROFILE STA 4+50 TO END
C00.24	SUBDIVISION PLAT (SHEET 5 OF 5)	C06.15	STORM DRAIN LINE G PLAN AND PROFILE
C01.00	OVERALL SITE PLAN	C06.16	STORM DRAIN LINE H PLAN AND PROFILE
C01.10	DETAILED SITE PLAN (SHEET 1 OF 3)	C06.17	STORM DRAIN LINE I PLAN AND PROFILE STA 1+00 TO 4+50
C01.11	DETAILED SITE PLAN (SHEET 2 OF 3)	C06.18	STORM DRAIN LINE I PLAN AND PROFILE STA 4+50 TO END
C01.12	DETAILED SITE PLAN (SHEET 3 OF 3)	C06.19	STORM DRAIN LINE J PLAN AND PROFILE
C02.00	EROSION & SEDIMENTATION CONTROL PLAN (SHEET 1 OF 3)	C06.20	STORM DRAIN LATERAL PROFILES (SHEET 1 OF 2)
C02.01	EROSION & SEDIMENTATION CONTROL PLAN (SHEET 2 OF 3)	C06.21	STORM DRAIN LATERAL PROFILES (SHEET 2 OF 2)
C02.02	EROSION & SEDIMENTATION CONTROL PLAN (SHEET 3 OF 3)	C06.30	INTERCEPTOR CHANNEL C1 PLAN AND PROFILE STA 0+50 TO 4+50
C02.20	EROSION & SEDIMENTATION CONTROL DETAILS (SHEET 1 OF 2)	C06.31	INTERCEPTOR CHANNEL C1 PLAN AND PROFILE STA 4+50 TO END
C02.21	EROSION & SEDIMENTATION CONTROL DETAILS (SHEET 2 OF 2)	C06.32	INTERCEPTOR CHANNEL E1 PLAN AND PROFILE
C03.00	ONSITE DRAINAGE PLAN (SHEET 1 OF 3)	C06.33	INTERCEPTOR CHANNEL H1 PLAN AND PROFILE
C03.01	ONSITE DRAINAGE PLAN (SHEET 2 OF 3)	C06.34	INTERCEPTOR CHANNEL I1 PLAN AND PROFILE
C03.02	ONSITE DRAINAGE PLAN (SHEET 3 OF 3)	C06.35	INTERCEPTOR CHANNEL J1 PLAN AND PROFILE
C03.03	ONSITE DRAINAGE CALCULATIONS (SHEET 1 OF 2)	C06.50	STREET AND DRAINAGE DETAILS (SHEET 1 OF 6)
C03.04	ONSITE DRAINAGE CALCULATIONS (SHEET 2 OF 2)	C06.51	STREET AND DRAINAGE DETAILS (SHEET 2 OF 6)
C03.10	OVERALL GRADING PLAN (SHEET 1 OF 3)	C06.52	STREET AND DRAINAGE DETAILS (SHEET 3 OF 6)
C03.11	OVERALL GRADING PLAN (SHEET 2 OF 3)	C06.53	STREET AND DRAINAGE DETAILS (SHEET 4 OF 6)
C03.12	OVERALL GRADING PLAN (SHEET 3 OF 3)	C06.54	STREET AND DRAINAGE DETAILS (SHEET 5 OF 6)
C04.00	UN04 DETENTION AND WATER QUALITY POND PLAN	C06.55	STREET AND DRAINAGE DETAILS (SHEET 6 OF 6)
C04.01	UN04 POND SECTIONS (SHEET 1 OF 3)	C07.00	ONSITE UTILITY PLAN (SHEET 1 OF 3)
C04.02	UN04 POND SECTIONS (SHEET 2 OF 3)	C07.01	ONSITE UTILITY PLAN (SHEET 2 OF 3)
C04.03	UN04 POND SECTIONS (SHEET 3 OF 3)	C07.02	ONSITE UTILITY PLAN (SHEET 3 OF 3)
C04.04	UN04 POND DETAILS	C08.00	WATER DISTRIBUTION PLAN (SHEET 1 OF 2)
C04.10	UN05 DETENTION AND WATER QUALITY POND PLAN	C08.01	WATER DISTRIBUTION PLAN (SHEET 2 OF 2)
C04.11	UN05 POND SECTIONS (SHEET 1 OF 3)	C08.10	WATERLINE A PLAN & PROFILE
C04.12	UN05 POND SECTIONS (SHEET 2 OF 3)	C08.11	WATERLINE B PLAN AND PROFILE
C04.13	UN05 POND SECTIONS (SHEET 3 OF 3)	C08.12	WATERLINE C PLAN AND PROFILE
C04.14	UN05 POND DETAILS	C08.13	WATERLINE F PLAN AND PROFILE
C05.00	ALMERIA AVE PLAN AND PROFILE STA 15+00 TO 19+00	C09.00	SANITARY SEWER COLLECTION PLAN (SHEET 1 OF 2)
C05.01	ALMERIA AVE PLAN AND PROFILE STA 19+00 TO END	C09.01	SANITARY SEWER COLLECTION PLAN (SHEET 2 OF 2)
C05.02	BARCELONA CV PLAN AND PROFILE	C09.10	SANITARY SEWER LINE A PLAN AND PROFILE STA 0+50 TO 6+50
C05.03	CADIZ PKWY PLAN AND PROFILE STA 0+50 TO 7+00	C09.11	SANITARY SEWER LINE A PLAN AND PROFILE STA 6+50 TO 12+50
C05.04	CADIZ PKWY PLAN AND PROFILE STA 7+00 TO 13+00	C09.12	SANITARY SEWER LINE A PLAN AND PROFILE STA 12+50 TO 18+50
C05.05	CADIZ PKWY PLAN AND PROFILE STA 13+00 TO 19+00	C09.13	SANITARY SEWER LINE A PLAN AND PROFILE STA 18+50 TO 24+50
C05.06	CANYON LOOP PLAN AND PROFILE STA 12+50 TO 17+00	C09.14	SANITARY SEWER LINE A PLAN AND PROFILE STA 24+50 TO END
C05.07	CANYON LOOP PLAN AND PROFILE STA 17+00 TO 21+50	C09.15	SANITARY SEWER LINE B PLAN AND PROFILE
C05.08	MADRID WAY PLAN AND PROFILE STA 0+50 TO 5+00	C09.16	SANITARY SEWER LINE C PLAN AND PROFILE
C05.09	MADRID WAY PLAN AND PROFILE STA 5+00 TO END	C10.00	CIVIL UTILITY DETAILS (SHEET 1 OF 9)
C05.10	MARBELLA ST PLAN AND PROFILE STA 0+50 TO 4+00	C10.01	CIVIL UTILITY DETAILS (SHEET 2 OF 9)
C05.11	MARBELLA ST PLAN AND PROFILE STA 4+00 TO END	C10.02	CIVIL UTILITY DETAILS (SHEET 3 OF 9)
C05.12	PALAMA PT PLAN AND PROFILE	C10.03	CIVIL UTILITY DETAILS (SHEET 4 OF 9)
C05.13	ROSWINEED DR PLAN AND PROFILE	C10.04	CIVIL UTILITY DETAILS (SHEET 5 OF 9)
C05.14	TOLEDO DR PLAN AND PROFILE	C10.05	CIVIL UTILITY DETAILS (SHEET 6 OF 9)
C05.15	CUL-DE-SAC AND KNUCKLE DETAIL SHEET	C10.06	CIVIL UTILITY DETAILS (SHEET 7 OF 9)
C06.00	STORM DRAIN COLLECTION PLAN (SHEET 1 OF 3)	C10.07	CIVIL UTILITY DETAILS (SHEET 8 OF 9)
C06.01	STORM DRAIN COLLECTION PLAN (SHEET 2 OF 3)	C10.08	CIVIL UTILITY DETAILS (SHEET 9 OF 9)
C06.02	STORM DRAIN COLLECTION PLAN (SHEET 3 OF 3)	C11.00	SIGNAGE, STRIPING AND LIGHTING PLAN (SHEET 1 OF 2)
C06.03	STORM DRAIN LINE A PLAN AND PROFILE STA 1+00 TO 4+00	C11.01	SIGNAGE, STRIPING AND LIGHTING PLAN (SHEET 2 OF 2)
C06.04	STORM DRAIN LINE A PLAN AND PROFILE STA 4+00 TO END	C11.10	TRAFFIC CONTROL DETAILS (SHEET 1 OF 4)
C06.05	STORM DRAIN LINE B PLAN AND PROFILE STA 1+00 TO 3+50	C11.11	TRAFFIC CONTROL DETAILS (SHEET 2 OF 4)
		C11.12	TRAFFIC CONTROL DETAILS (SHEET 3 OF 4)
		C11.13	TRAFFIC CONTROL DETAILS (SHEET 4 OF 4)

SUBMITTED BY



STACY S. MULHOLLAND, P.E.  
BGE, INC. TBPE NO. 146417  
7330 SAN PEDRO AVENUE  
SUITE 202  
SAN ANTONIO, TEXAS 78216  
(210) 581-3600 (MAIN)



BGE, Inc.  
7330 San Pedro Ave., Suite 202  
San Antonio, TX 78216  
Tel: 210-581-3600 • www.browngay.com  
TBPE Registration No. F-1046



Know what's below.  
Call before you dig.



THE LOCATION OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. HE AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.











G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C00.10 - EXISTING CONDITIONS SURVEY.dwg Layout C00.10 EXISTING CONDITIONS SURVEY (SHEET 1 OF 3) Plotted: 11/7/2024 9:29:09 AM By: Arath



CANYON RANCH UNIT 4		EXISTING CONDITIONS SURVEY		DATE		DESCRIPTION	
CANYON RANCH UNIT 4		EXISTING CONDITIONS SURVEY		11/08/2024		APR	
EXISTING CONDITIONS SURVEY		(SHEET 1 OF 3)		REV		REV	
DESIGNED BY: RRA		REVIEWED BY: SSM		DRAWN BY: RRA		DESCRIPTION	
BGE, INC. 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 210-581-3380 www.bgeinc.com TXE Registration No. P-1046							





	CANYON RANCH UNIT 4				△	
	EXISTING CONDITIONS SURVEY		BGE, INC. 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 214.345.6789 TBPE Registration No. F-1046		△	
	(SHEET 2 OF 3)				△	
					△	
SHEET		DESIGNED BY:	RRR	REV	DESCRIPTION	DATE
C00.11		REVIEWED BY:	SSM			
		DRAWN BY:	RRR			














**GENERAL SITE PLAN NOTES**

- THIS DEVELOPMENT SHALL COMPLY WITH THE COMAL COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS MANUAL AND THE DEVELOPMENT MANUAL.
- THIS SITE PLAN SHALL MEET THE COMAL COUNTY STORM WATER REQUIREMENTS.
- A HOMEOWNER'S ASSOCIATION WILL BE ESTABLISHED FOR THIS DEVELOPMENT.
- WATER SERVICE IS TO BE PROVIDED BY THE TEXAS WATER COMPANY.
- ALL ROADS WILL BE PUBLICLY OWNED
- ELECTRIC SERVICE TO BE PROVIDED BY PEDERNALES ELECTRIC COOPERATIVE.
- SANITARY SEWER SERVICE IS TO BE PROVIDED BY CANYON RANCH MUD OF COMAL COUNTY.
- NO PORTION OF THIS SUBDIVISION IS WITHIN SPECIAL FLOOD HAZARD ZONE AS DELINEATED ON THE FLOOD INSURANCE MAP (FIRM) FOR COMAL COUNTY, TEXAS ON MAP NUMBER 48081C0080F RESPECTIVELY, DATED SEPTEMBER 9, 2009 AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)
- DURING THE BUILDING PERMIT STAGE, THE INDIVIDUAL HOME BUILDER/OWNER SHALL BE RESPONSIBLE FOR CONSTRUCTION OF A 4' CONCRETE SIDEWALK ALONG THE FRONTAGE OF THE INDIVIDUAL LOT. THE DEVELOPER OF THIS PROJECT SHALL BE RESPONSIBLE FOR CONSTRUCTION OF CONCRETE SIDEWALK AT COMMON AREAS, DRAINAGE EASEMENT, AND ALL OTHER AREAS WHERE SIDEWALK IS REQUIRED TO BE CONSTRUCTED (SEE TYPICAL STREET SECTION FOR PLACEMENT OF SIDEWALK)
- MAINTENANCE OF DRAINAGE EASEMENTS DESIGNATED WITHIN A LOT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER, ANY USE, OF ANY EASEMENT, OR ANY PORTION OF IT, INCLUDING LANDSCAPING OR DRAINAGE FEATURES IS SUBJECT TO AND SHALL NOT CONFLICT WITH THE TERMS AND CONDITIONS OF IN THE EASEMENT, MUST NOT ENDANGER OR INTERFERE WITH THE RIGHTS GRANTED BY THE EASEMENT TO THE UTILITIES, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE SUBJECT TO APPLICABLE PERMIT REQUIREMENTS OF HAYS COUNTY OR ANY OTHER GOVERNING BODY, THE PROPERTY OWNER MUST OBTAIN, IN ADVANCE, WRITTEN AGREEMENT WITH THE UTILITIES TO UTILIZE THE EASEMENT, OR ANY PART OF IT.
- ALL STREETS WITHIN THE CANYON RANCH SUBDIVISION WILL BE BUILT TO THE COMAL COUNTY SPECIFICATIONS AND WILL BE DEDICATED TO THE COUNTY UPON COMPLETION AND ACCEPTANCE.
- CONTRACTOR SHALL REFER TO THE RECOMMENDATIONS CONTAINED WITHIN THE GEOTECHNICAL INVESTIGATION REPORTS PREPARED BY INTEC (PROJECT NO. S201370) & PROFESSIONAL SERVICE INDUSTRIES, INC. (PROJECT NO. 0312-3287).

**UTILITIES:**

- WATER PROVIDED BY: THE TEXAS WATER COMPANY
- WASTEWATER: CANYON RANCH MUD OF COMAL COUNTY
- ELECTRIC: PEDERNALES ELECTRIC COOPERATIVE

**ENGINEER:**  
BGE INC.  
7330 SAN PEDRO AVE., SUITE 202  
SAN ANTONIO, TX 78216  
PHONE: 210-581-3600

**DEVELOPER:**  
LENNAR  
CONTACT: RICHARD MOTT  
100 NE LP 410, SUITE 1155  
SUITE 1155  
SAN ANTONIO, TX 78216  
PHONE: (210) 403-8200

**TOTAL ACREAGE: 30.698 ACRES**

\*COMAL COUNTY TO APPROVE, INSPECT, AND MAINTAIN ALL ROADWAY PAVEMENT

NOTE: SEE PLAT FOR EASEMENT DIMENSIONS & BUILDING SETBACKS


NOTE: REFERENCE C01.00 FOR REPORT INFORMATION AND ADDITIONAL NOTES.

UNIT 4 PROJECT LAND SUMMARY		
SITE ACREAGE	30.7 AC.	
SINGLE FAMILY RESIDENTIAL LOTS:	177	
LOCAL STREET (LF):	5,375 LF	
COLLECTOR STREET (LF):	584 LF	
DENSITY (LOT/AC):	5.77 LOT/AC	
















STREET CLASSIFICATION TABLE		
STREET NAME	CLASSIFICATION	LF
ALMERIA AVE	LOCAL STREET	734
BARCELONA COVE	LOCAL STREET	570
CADIZ PKWY	LOCAL STREET	1,693
CANYON LOOP	COLLECTOR STREET	584
MADRID WAY	LOCAL STREET	841
MARBELLA STREET	LOCAL STREET	620
PALAMA POINT	LOCAL STREET	391
ROSINWEED DRIVE	LOCAL STREET	217
TOLEDO DRIVE	LOCAL STREET	310

[illegible]





### LEGEND

- |   |                         |
|---|-------------------------|
|  | PROPERTY BOUNDARY       |
|  | UNIT BOUNDARY           |
|  | BUILDING SETBACK        |
|  | PROPOSED LOT LINES      |
|  | PROPOSED EASEMENT       |
|  | CONTRACTOR SIDEWALK     |
|  | HOME BUILDER SIDEWALK   |
|  | RAMP (SEE SHEET CXX.XX) |
|  | CONCRETE VALLEY GUTTER  |
|  | RETAINING WALL          |
|  | METAL BEAM GUARD FENCE  |
|  | CHAIN LINK FENCE        |
|  | LOT NUMBER              |
|  | ENGINEERED FILTER STRIP |
|  | JURISDICTIONAL WATERS   |

## GENERAL SITE PLAN NOTES

1. THIS DEVELOPMENT SHALL COMPLY WITH THE COMAL COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS MANUAL AND THE DEVELOPMENT MANUAL.
2. THIS SITE PLAN SHALL MEET THE COMAL COUNTY STORM WATER REQUIREMENTS.
3. A HOMEOWNERS ASSOCIATION WILL BE ESTABLISHED FOR THIS DEVELOPMENT.
4. WATER OR SEWER IS TO BE PROVIDED BY THE TEXAS WATER COMPANY.
5. ALL ROADS WILL BE PUBLICLY OWNED.
6. ELECTRIC SERVICE TO BE PROVIDED BY FEDERALERS ELECTRIC COOPERATIVE.
7. SANITARY SEWER SERVICE IS TO BE PROVIDED BY CANYON RANCH MUD OF COMAL COUNTY.
8. NO PORTION OF THIS SUBDIVISION IS WITHIN SPECIAL FLOOD HAZARD ZONE AS DELINEATED ON THE FLOOD INSURANCE MAP (FIRM) FOR COMAL COUNTY, TEXAS ON MAP NUMBER 4901C0080F RESPECTIVELY, DATED SEPTEMBER 9, 2009 AS PREPARED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.
9. DURING THE BUILDING PERMIT STAGE, THE INDIVIDUAL HOME BUILDER/OWNER SHALL BE RESPONSIBLE FOR CONSTRUCTION OF A 4' CONCRETE SIDEWALK ALONG THE FRONTAGE OF THE INDIVIDUAL LOT. THE DEVELOPER OF THIS PROJECT SHALL BE RESPONSIBLE FOR CONSTRUCTION OF CONCRETE SIDEWALK AT COMMON AREAS, DRAINAGE EASEMENT, AND ALL OTHER AREAS WHERE SIDEWALK IS REQUIRED TO BE CONSTRUCTED(SEE TYPICAL STREET SECTION FOR PLACEMENT OF SIDEWALK)
10. MAINTENANCE OF DRAINAGE EASEMENTS DESIGNATED WITH IN A LOT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER, ANY USE, OF AN EASEMENT, OR ANY PORTION OF IT, INCLUDING LANDSCAPING OR DRAINAGE FEATURES IS SUBJECT TO AND SHALL NOT CONFLICT WITH THE TERMS AND CONDITIONS OF IN THE EASEMENT, MUST NOT ENDANGER OR INTERFERE WITH THE RIGHTS GRANTED BY THE EASEMENT TO THE UTILITIES, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE SUBJECT TO APPLICABLE PERMIT REQUIREMENTS OF HAYS COUNTY OR ANY OTHER GOVERNING BODY. THE PROPERTY OWNER MUST OBTAIN, IN ADVANCE, WRITTEN AGREEMENT WITH THE UTILITIES TO UTILIZE THE EASEMENT, OR ANY PART OF IT.
11. ALL STREETS WITHIN THE CANYON RANCH SUBDIVISION WILL BE BUILT TO THE COMAL COUNTY SPECIFICATIONS AND WILL BE DEDICATED TO THE COUNTY UPON COMPLETION AND ACCEPTANCE.
12. CONTRACTOR SHALL REFER TO THE RECOMMENDATIONS CONTAINED WITHIN THE GEOTECHNICAL INVESTIGATION REPORTS PREPARED BY INTEC (PROJECT NO. S2013070) & PROFESSIONAL SERVICE INDUSTRIES, INC. (PROJECT NO. 0312-3287).

## UTILITIES

- WATER PROVIDED BY: THE TEXAS WATER COMPANY
- WASTEWATER: CANYON RANCH MUD OF COMAL COUNTY
- ELECTRIC: PEDERNALES ELECTRIC COOPERATIVE

ENGINEER:

BGE INC.  
7330 SAN PEDRO AVENUE, SUITE 200  
SAN ANTONIO, TX 78216  
PHONE: 210-581-3600

TOTAL ACREAGE: 30.698 ACRES

\*COMAL COUNTY TO APPROVE, INSPECT, AND MAINTAIN ALL ROADWAY PAVEMENT

NOTE: SEE PLAT FOR EASEMENT DIMENSIONS &  
BUILDING SETBACKS

NOTE: REFERENCE C01.00 FOR REPORT INFORMATION AND ADDITIONAL NOTES

UNIT 4 PROJECT LAND SUMMARY	
SITE ACREAGE	30.7 AC.
SINGLE FAMILY RESIDENTIAL LOTS:	177
LOCAL STREET (LF):	5,375 LF
COLLECTOR STREET (LF):	584 LF
DENSITY (LOT/AC):	5.77 LOT/AC

STREET CLASSIFICATION TABLE			
	STREET NAME	CLASSIFICATION	LF
	ALMERIA AVE	LOCAL STREET	734
	BARCELONA COVE	LOCAL STREET	570
	CADIZ PKWY	LOCAL STREET	1,693
	CANYON LOOP	COLLECTOR STREET	584
	MADRID WAY	LOCAL STREET	841
	MARBELLA STREET	LOCAL STREET	620
	PALAMA POINT	LOCAL STREET	391
	ROSINWEED DRIVE	LOCAL STREET	217
	TOLEDO DRIVE	LOCAL STREET	310

CANYON RANCH UNIT 4

DETAILED SITE PLAN (SHEET 2 OF 3)



SHEET

CO1.11



[illegible]
















◀	◀	◀	◀	◀	REV
DESIGNED BY: ####					
REVIEWED BY: ####					
DRAWN BY: ####					



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 [www.browning.com](http://www.browning.com)





- |   |                         |
|---|-------------------------|
|  | PROPERTY BOUNDARY       |
|  | UNIT BOUNDARY           |
|  | BUILDING SETBACK        |
|  | PROPOSED LOT LINES      |
|  | PROPOSED EASEMENT       |
|  | CONTRACTOR SIDEWALK     |
|  | HOME BUILDER SIDEWALK   |
|  | RAMP (SEE SHEET CXX.XX) |
|  | CONCRETE VALLEY GUTTER  |
|  | RETAINING WALL          |
|  | METAL BEAM GUARD FENCE  |
|  | CHAIN LINK FENCE        |
|  | LOT NUMBER              |
|  | ENGINEERED FILTER STRIP |
|  | JURISDICTIONAL WATERS   |

### GENERAL SITE PLAN NOTE

1. THIS DEVELOPMENT SHALL COMPLY WITH THE COMAL COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS MANUAL AND THE DEVELOPMENT MANUAL.
2. THIS SITE PLAN SHALL MEET THE COMAL COUNTY STORM WATER REQUIREMENTS. A HOMEOWNERS ASSOCIATION WILL BE ESTABLISHED FOR THIS DEVELOPMENT.
3. WHEN THE PROJECT IS COMPLETED, THE TEXAS WATER COMPANY, ALL ROADS WILL BE PUBLICLY OWNED
4. ELECTRIC SERVICE TO BE PROVIDED BY FERNERLE'S ELECTRIC COOPERATIVE.
5. SANITARY SEWER SERVICE IS TO BE PROVIDED BY CANYON RANCH MUD OF COMAL COUNTY.
6. NO PORTION OF THIS SUBDIVISION IS WITHIN SPECIAL FLOOD HAZARD ZONE AS DELINEATED ON THE FLOOD INSURANCE MAP (FIRM) FOR COMAL COUNTY, TEXAS ON MAP NUMBER 46081C0080F RESPECTIVELY, DATED SEPTEMBER 9, 2008 AS PREPARED BY THE TEXAS FLOOD EMERGENCY MANAGEMENT AGENCY.
7. DURING THE BUILDING PERMIT STAGE, THE INDIVIDUAL HOME BUILDER/OWNER SHALL BE RESPONSIBLE FOR CONSTRUCTION OF A 4' CONCRETE SIDEWALK ALONG THE FRONTAGE OF THE INDIVIDUAL LOT. THE DEVELOPER OF THIS PROJECT SHALL BE RESPONSIBLE FOR CONSTRUCTION OF CONCRETE SIDEWALK AT COMMON AREAS, DRAINAGE EASEMENT, AND ALL OTHER AREAS WHERE SIDEWALK IS REQUIRED TO BE CONSTRUCTED(SEE TYPICAL STREET SECTION FOR PLACEMENT OF SIDEWALK)
10. MAINTENANCE OF DRAINAGE EASEMENTS DESIGNATED WITH IN A LOT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER. ANY USE, OF ANY EASEMENT, OR ANY PORTION OF IT, INCLUDING LANDSCAPING OR DRAINAGE FEATURES IS SUBJECT TO AND SHALL NOT CONFLICT WITH THE TERMS AND CONDITIONS OF IN THE EASEMENT, MUST NOT ENDANGER OR INTERFERE WITH THE RIGHTS GRANTED BY THE EASEMENT TO THE UTILITIES, ITS SUCCESSORS AND ASSIGNS, AND SHALL BE SUBJECT TO APPLICABLE PERMIT REQUIREMENTS OF HAYS COUNTY OR ANY OTHER GOVERNING BODY. THE PROPERTY OWNER MUST OBTAIN, IN ADVANCE, WRITTEN AGREEMENT WITH THE UTILITIES TO UTILIZE THE EASEMENT, OR ANY PART OF IT.
11. ALL STREETS WITHIN THE CANYON RANCH SUBDIVISION WILL BE BUILT TO THE COMAL COUNTY SPECIFICATIONS AND WILL BE DEDICATED TO THE COUNTY UPON COMPLETION AND ACCEPTANCE.
12. CONTRACTOR SHALL REFER TO THE RECOMMENDATIONS CONTAINED WITHIN THE GEOTECHNICAL INVESTIGATION REPORTS PREPARED BY INTEC (PROJECT NO. 5201370) & PROFESSIONAL SERVICE INDUSTRIES, INC. (PROJECT NO. 031-327-328).

## UTILITIES

- WATER PROVIDED BY: THE TEXAS WATER COMPANY
- WASTEWATER: CANYON RANCH MUD OF COMAL COUNTY
- ELECTRIC: PEDERNALES ELECTRIC COOPERATIVE

## ENGINEER

BGE INC.  
7330 SAN PEDRO AVENUE, SUITE 200  
SAN ANTONIO, TX 78216  
PHONE: 210-581-3600

## DEVELOPER

LENNAR  
CONTACT: RICHARD MOT  
100 NE LP 410, SUITE 1155  
SUITE 1155  
SAN ANTONIO, TX 78216  
PHONE: (210) 403-6200

TOTAL ACREAGE: 30,698 ACRES

\*COMAL COUNTY TO APPROVE, INSPECT, AND MAINTAIN ALL ROADWAY PAVEMENT

NOTE: SEE PLAT FOR EASEMENT DIMENSIONS & BUILDING SETBACKS

NOTE: REFERENCE C01.00 FOR REPORT INFORMATION AND ADDITIONAL NOTES


UNIT 4 PROJECT LAND SUMMARY	
SITE ACREAGE	30.7 AC.
SINGLE FAMILY RESIDENTIAL LOTS:	177
LOCAL STREET (LF):	5,375 LF
COLLECTOR STREET (LF):	584 LF
DENSITY (LOT/AC):	5.77 LOT/AC

STREET CLASSIFICATION TABLE		
STREET NAME	CLASSIFICATION	LF
ALMERIA AVE	LOCAL STREET	734
BARCELONA COVE	LOCAL STREET	570
CADIZ PKWY	LOCAL STREET	1,693
CANYON LOOP	COLLECTOR STREET	584
MADRID WAY	LOCAL STREET	841
MARBELLA STREET	LOCAL STREET	620
PALAMIA POINT	LOCAL STREET	391
ROSWOODE DRIVE	LOCAL STREET	217
JOLI FND DRIVE	LOCAL STREET	310













1. INTERIM OR FINAL GRADING MUST BE COMPLETED PRIOR TO SEEDING, MINIMIZING ALL STEEP SLOPES.
2. FERTILIZER SHOULD BE APPLIED AT THE RATE OF 40 POUNDS OF NITROGEN AND 40 POUNDS OF PHOSPHORUS PER ACRE. COMPOST CAN BE USED INSTEAD OF FERTILIZER AND APPLIED AT THE SAME TIME AS THE SEED.
3. ALL DISTURBED AREAS SHALL BE PERMANENTLY SEEDDED OR OTHERWISE STABILIZED WITHIN 14 CALENDAR DAYS AFTER FINAL GRADING OR WHERE TEMPORARY CONSTRUCTION ACTIVITY HAS CEASED FOR MORE THAN 21 DAYS.
4. ADD 3 HOOKS PER CITY OF AUSTIN DETAIL, ALONG THE SILT FENCE.
5. A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) MUST BE PREPARED/AMENDED BY A TX PE, CPESC, OR QPSWPP [CITY CODE SECTION 86.529(B)(2) OR 86.529(C)(3)], IMPLEMENTED, AND UPDATED TO MATCH SITE CONDITIONS DURING THE PROJECT. THE ASSOCIATED TPDES CONSTRUCTION SITE NOTICE MUST BE POSTED IN PUBLIC VIEW, PER TXR150000 PART III.D.2.
6. HAVE A CISEC, CESSWI, OR QGIS CONDUCT WEEKLY SWPPP INSPECTIONS AND DOCUMENT PER CITY CODE SECTIONS 86.523 AND 86.529(B)(9) OR 86.529(C)(10). MAINTAIN ALL ESC INSPECTIONS AND ADDRESS ALL IDENTIFIED CORRECTIVE ACTIONS PER CITY CODE SECTION 86.529(C)(1).
7. THE LIMITS OF CONSTRUCTION (LOC) SHALL BE ADJUSTED AS NEEDED DURING THE PROJECT TO COVER ALL AREAS DISTURBED DURING DEMOLITION, GRADING, CONSTRUCTION, STORAGE, STOCKPILING, PARKING, ETC., PER TXR150000 PARTS I AND II.G.4.(C) AND (D), ADDITIONAL EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED.
8. PER TXR150000 PART III.F.1.(M), LOCATIONS OF THE FOLLOWING, AS APPLICABLE, MUST BE MARKED ON THIS ESPC IN THE FIELD: THE TYPES CONSTRUCTION SITE NOTICE POSTING IN PUBLIC VIEW, STAGING, SPOILS STORAGE, CONCRETE WASHOUT, DUMPSTERS, PORTABLE TOILET(S), FUELING POINT(S), AND/OR OTHER POTENTIAL CONTAMINANT SOURCES. THIS ESPC MUST ALSO BE UPDATED AS THESE POTENTIAL CONTAMINANT SOURCES MOVE OR OTHER CHANGES OCCUR ONSITE. PEN AND INK CHANGES ARE EXPECTED AND WILL BE REQUIRED FOR RESUBMITAL. JUST DATE AND INITIAL IF THERE ARE AREAS OF MORE THAN 14 DAYS DURING THE PROJECT WHERE NO DIRT WORK IS DONE ON A SITE PORTION(S) WITHIN THE LIMITS OF CONSTRUCTION, TEMPORARY (OR PERMANENT) STABILIZATION IS REQUIRED PER TXR150000 PART III.F.2.(B).III.CITY CODE SECTION 86.529(A)(1)(G), SUCH DIRT WORK STOPPAGE INCLUDES TIME PERIODS BETWEEN ROUGH GRADING COMPLETION AND CONSTRUCTION START, DURING CONSTRUCTION, BETWEEN CONSTRUCTION AND FINAL STABILIZATION, ETC. USE TEMPORARY (OR PERMANENT) SEEDING, ROCK, GRAVEL (1" MINIMUM), CONCRETE RIP-RAP, DEGRADABLE STRAW MATTING, SHREDDED HARDWOOD MULCH, DEGRADABLE SOIL RETENTION BLANKETS, OR SIMILAR. NOTE THAT MATTING, MULCH, OR BLANKETS REQUIRE ONGOING MAINTENANCE.
9. ANY EXISTING STORM WATER INLETS WITHIN 200' OF THE LOC MUST HAVE INLET PROTECTION. STORM WATER INLET PROTECTION IS ALSO REQUIRED AS NEW STORM WATER INLETS ARE ADDED TO THE SITE, IF APPLICABLE.
10. POND OR OTHER DISTURBED SLOPES 3:1 OR FLATTER MUST BE STABILIZED WITH BIODEGRADABLE SOIL RETENTION BLANKETS WITH NO PLASTIC NETTING. DISTURBED SLOPES EXCEEDING 3:1 REQUIRE BLANKETS OR EQUIVALENT UNTIL RE-VEGETATION IS ESTABLISHED OR SOD.
11. DO NOT DISTURB THE JURISDICTIONAL STREAM, ANY DISTURBANCE TO THE STREAM WILL NEED TO BE RECTIFIED IMMEDIATELY.

ALL DISTURBED AREAS SHALL BE PERMANENTLY SEEDED OR OTHERWISE STABILIZED WITHIN 14 CALENDAR DAYS AFTER FINAL GRADING OR WHERE TEMPORARY CONSTRUCTION ACTIVITY HAS CEASED FOR MORE THAN 21 DAYS

 <p><b>BGE, INC.</b> 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 214-343-7899 TXBE Registration No. E-1048</p>	DESIGNED BY:	LNH	DATE	APR
	REVIEWED BY:	SSM	REV	
	DRAWN BY:	JDC	DESCRIPTION	
<p>CANYON RANCH UNIT 4</p> <p>EROSION &amp; SEDIMENTATION CONTROL PLAN</p> <p>(SHEET 2 OF 3)</p>				
 <p>SHEET 11/08/2024</p> <p>C02.01</p>				






	PROPERTY BOUNDARY
	UNIT BOUNDARY
	EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED MAJOR CONTOUR
	LIMITS OF CONSTRUCTION
	SILT FENCE
	SILT FENCE/LIMITS OF CONSTRUCTION
	FLOW ARROW
	CONSTRUCTION ENTRANCE
	CONCRETE WASHOUT AREA
	CONSTRUCTION STAGING AREA
	INLET PROTECTION
	ROCK BERM
	J HOOKS
	100 YEAR FEMA FLOODPLAIN
	RIPARIAN BUFFER
	JURISDICTIONAL WATERS OF THE US
	PROPOSED RETAINING WALL

NOTES:

1. INTERIM OR FINAL GRADING MUST BE COMPLETED PRIOR TO SEEDING, MINIMIZING ALL STEEP SLOPES.
2. FERTILIZER SHOULD BE APPLIED AT THE RATE OF 40 POUNDS OF NITROGEN AND 40 POUNDS OF PHOSPHORUS PER ACRE. COMPOST CAN BE USED INSTEAD OF FERTILIZER AND APPLIED AT THE SAME TIME AS THE SEED.
3. ALL DISTURBED AREAS SHALL BE PERMANENTLY SEEDED OR OTHERWISE STABILIZED WITHIN 14 CALENDAR DAYS AFTER FINAL GRADING OR WHERE TEMPORARY CONSTRUCTION ACTIVITY HAS CEASED FOR MORE THAN 21 DAYS.
4. ADJ. HOOKS PER CITY OF AUSTIN DETAIL ALONG THE SILT FENCE.
5. A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) MUST BE PREPARED/ADOPTED BY A TX P.E. (P.E. OR QPSWPPP CITY CODE SECTION 86.529(B)(2) OR 86.529(C)(3)), IMPLEMENTED, AND UPDATED TO MATCH SITE CONDITIONS DURING THE PROJECT. THE ASSOCIATED TPDES CONSTRUCTION SITE NOTICE MUST BE POSTED IN PUBLIC VIEW, TXR150000 PART III.D.2.
6. HAVE A CISEC, CESSWI, OR CUIS CONDUCT WEEKLY SWPPP INSPECTIONS AND DOCUMENT PER CITY CODE SECTIONS 86.523 AND 86.529(B)(9) OR 86.529(C)(10). MAINTAIN ALL ESC MEASURES AND ADDRESS ALL IDENTIFIED CORRECTIVE ACTIONS PER CITY CODE SECTION 86.529(C)(11).
7. THE LIMITS OF CONSTRUCTION (LOC) SHALL BE ADJUSTED AS NEEDED DURING THE PROJECT TO COVER ALL AREAS DISTURBED DURING DEMOLITION, GRADING, CONSTRUCTION, STORAGE, STOCKPILING, PARKING, ETC. PER TXR150000 PARTS I AND II.B.4.(C) AND (D). ADDITIONAL EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED.
8. PER TXR150000 PART III.F.1.(M), LOCATIONS OF THE FOLLOWING, AS APPLICABLE, MUST BE MARKED ON THIS ESPC IN THE FIELD: THE TPDES CONSTRUCTION SITE NOTICE POSTING IN PUBLIC VIEW, STAGING, SPOILS STORAGE, CONCRETE WASHOUT, DUMPSTERS, PORTABLE TOILET(S), FUELING POINT(S), AND/OR OTHER POTENTIAL CONTAMINANT SOURCES. THIS ESPC MUST ALSO BE UPDATED AS THESE POTENTIAL CONTAMINANT SOURCES MOVE OR OTHER CHANGES OCCUR ON-SITE. PEN AND INK CHANGES ARE EXPECTED AND DON'T REQUIRE RESUBMITAL, JUST DATE AND INITIAL.
9. IF THERE IS A BREAK OF MORE THAN 14 DAYS DURING THE PROJECT WHERE NO DIRT WORK IS DONE ON A SITE PORTION(S) WITHIN THE LIMITS OF CONSTRUCTION, CONSTRUCTION (OR PERMANENT) STABILIZATION IS REQUIRED PER TXR150000 PART III.D.2.(B). (CITY CODE SECTION 86.529(A)(1)(G), SUCH DIRT WORK STOPPAGE INCLUDES TIME PERIODS BETWEEN ROUGH GRADING COMPLETION AND CONSTRUCTION START, DURING CONSTRUCTION, BETWEEN CONSTRUCTION AND FINAL STABILIZATION, ETC. USE TEMPORARY (OR PERMANENT) SEEDING, ROCK, GRAVEL (1" MINIMUM), CONCRETE RIP-RAP, DEGRADABLE STRAW MATTING, SHREDDED HARDWOOD MULCH, DEGRADABLE ROCK RETENTION BLANKETS, OR SIMILAR, NOTE THAT MATTING, MULCH, OR BLANKETS REQUIRE ONGOING MAINTENANCE.
10. ANY EXISTING STORM WATER INLETS WITHIN 200' OF THE LOC MUST HAVE INLET PROTECTION. STORM WATER INLET PROTECTION IS ALSO REQUIRED AS NEW STORM WATER INLETS ARE SCHEDULED TO BE CONSTRUCTED.
11. POND OR OTHER DISTURBED SLOPES 3:1 OR FLATTER MUST BE STABILIZED WITH BIODEGRADABLE ROCK RETENTION BLANKETS WITH NO PLASTIC NETTING. DISTURBED SLOPES EXCEEDING 3:1 REQUIRE BLANKETS OR EQUIVALENT UNTIL RE-VEGETATION IS ESTABLISHED OR SOD.
12. DO NOT DISTURB THE JURISDICTIONAL STREAM. ANY DISTURBANCE TO THE STREAM WILL NEED TO BE RECTIFIED IMMEDIATELY.

ALL DISTURBED AREAS SHALL BE PERMANENTLY SEEDED OR OTHERWISE STABILIZED WITHIN 14 CALENDAR DAYS AFTER FINAL GRADING OR WHERE TEMPORARY CONSTRUCTION ACTIVITY HAS CEASED FOR MORE THAN 21 DAYS






NOTES:

1. USE ONLY OPEN GRADED ROCK 4-8 INCHES DIAMETER FOR STREAM FLOW CONDITION; USE OPEN GRADED ROCK 3-5 INCHES DIAMETER FOR OTHER CONDITIONS.
2. THE ROCK BERM SHALL BE SECURED WITH A WOVEN WIRE SHEATHING HAVING MAXIMUM 1 INCH OPENING AND MINIMUM WIRE DIAMETER OF 1/32 INCH.
3. THE ROCK BERM SHALL BE INSPECTED WEEKLY OR AFTER EACH RAIN, AND THE STONE AND/OR FABRIC CORE-WOVEN WIRE SHEATHING SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED, DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
4. WHEN SILT REACHES A DEPTH EQUAL TO 50 PERCENT OF THE HEIGHT OF THE BERM OR 12 INCHES, WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF AT AN APPROVED SITE AND IN A MANNER AS TO NOT CREATE A SILTATION PROBLEM.
5. DAILY INSPECTION SHALL BE MADE ON SERVICE SERVICE ROCK BERMS; SILT SHALL BE REMOVED WHEN ACCUMULATION REACHES 6 INCHES.
6. WHEN THE SITE IS COMPLETELY STABILIZED, THE BERM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.

### ROCK BERM DETAIL

N.T.S.



CONCRETE WASHOUT NOTES:


1. THE LINED WASHOUT PIT SHALL BE SUFFICIENTLY LARGE ENOUGH TO HOLD EXPECTED VOLUME OF WASHOUT MATERIAL.
2. WHEN FACILITY IS NO LONGER REQUIRED, HARDENED CONCRETE SHALL PROPERLY REMOVED AND DISPOSED OF.
3. CONTRACTOR TO BACKFILL PIT UPON REMOVAL OF LINING.

SAND BAG NOTES:

1. THE SAND BAG MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, POLYAMIDE OR COTTON BURLAP WOVEN FABRIC, MINIMUM UNIT WEIGHT 4 OZ/YD<sup>2</sup>, MULLEN BURST STRENGTH EXCEEDING 300 PSI AND ULTRAVIOLET STABILITY EXCEEDING 70 PERCENT. BAGS SHOULD BE 24 INCHES LONG, 24 TO 30 INCHES WIDE, WITH SEAMS AND THICKNESS SHOULD BE 6 TO 8 INCHES.
2. SANDBAGS SHOULD BE FILLED WITH COARSE GRADE SAND, FREE FROM DELETERIOUS MATERIAL. ALL SAND SHOULD PASS THROUGH A NO. 10 SIEVE. THE FILLETED BAG SHOULD HAVE AN OPENING OF 1/2 INCHES.
3. OUTLET PIPE SHOULD BE SCHEDULE 40 OR STRONGER POLYVINYL CHLORIDE (PVC) HAVING A NOMINAL INTERNAL DIAMETER OF 4 INCHES.

## IN-GROUND CONCRETE WASHOUT PIT DETAIL

N.T.S



### COMPLIANCE CHECKLIST:

1. **PERIMETER CONTROLS:** INSTALL ESC'S (EROSION SEDIMENT CONTROLS) AROUND THE BACK OF THE CURB AND ALONG THE LOT LINE OF ADJACENT PROPERTIES, WHICH ARE DOWNHILL AND RECEIVE RUNOFF FROM YOUR LOT. FOLLOWING SIDEWALK INSTALLATION, ESC'S SHOULD BE REMOVED TO THE BACK OF THE SIDEWALK TO PREVENT SEDIMENT FROM REACHING THE SIDEWALK. MAINTAIN ESC'S TO ENSURE PROPER FUNCTION, INCLUDING REPAIR OR REPLACEMENT OF TORN, DEGRADED OR OTHERWISE INEFFECTIVE MATERIALS. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE PROTECTION.
2. **STOCKPILES:** INSTALL SEDIMENT CONTROLS AROUND STOCKPILES TO PREVENT SEDIMENT FROM REACHING THE STREET AND ADJACENT PROPERTIES. LOCATE STOCKPILES AWAY FROM THE STREET, PROPERTY LINES AND DRAINAGE WAYS.
3. **LOT ACCESS:** REQUIRED FOR EACH INDIVIDUAL LOT. MAINTAIN A SURFACE SUITABLE FOR PARKING AND UNLOADING TO PREVENT THE TRACKING OF MUD AND ROCK ONTO THE STREET. A MINIMUM 6-INCH DEPTH OF 3- TO 5-INCH AGGREGATE IS SUGGESTED. ALL VEHICLES THAT ACCESS THE LOT MUST USE THE CONSTRUCTION ENTRANCE. ANY SOILS THAT ARE TRUCKED ONTO THE STREET MUST BE REMOVED BY THE END OF THE DAY.
4. **INTERMEDIATE CONTROL:** LONG OR STEEP DRAINAGE PATHS MAY REQUIRE INTERMEDIATE OR INTERIOR ESC'S TO HELP SLOW THE FLOW OF RUNOFF. FAILURE OF PERIMETER CONTROLS DUE TO THE FORCE OF RUNOFF OFTEN DETERMINE THE NEED FOR INTERMEDIATE CONTROLS.
5. **HOUSEKEEPING:** PROVIDE ADEQUATE SANITARY FACILITIES, TRASH/REFUSE BINS, AND DESIGNATED CONCRETE WASHOUT.

CONTRACTOR/BUILDERS RESPONSIBILITY:


1. INSTALL NEEDED EROSION AND SEDIMENT CONTROL PRACTICES PRIOR TO ANY LAND DISTURBANCE TO PREVENT EXCESSIVE SEDIMENT FROM LEAVING THE SITE.
2. PERIODIC INSPECTION AND MAINTENANCE ARE VITAL TO THE PERFORMANCE OF EROSION AND SEDIMENT CONTROLS. IT IS RECOMMENDED THAT ALL TEMPORARY EROSION CONTROLS BE INSPECTED WEEKLY AND AFTER EVERY RAINFALL.
3. MAINTENANCE: ESC (EROSION SEDIMENT CONTROLS) SHOULD BE ROUTINELY INSPECTED AND MAINTAINED UNTIL SITE IS PERMANENTLY VEGETATED. SOMETIMES ROUTINE INSPECTIONS MAY SHOW A NEED FOR ADJUSTMENTS OR ADDITIONAL ESC'S.
4. SUBMIT A NOTICE OF TERMINATION (NOT) TO THE TCEQ AND LOCAL MSA WHEN CONSTRUCTION IS COMPLETE.
5. REVEGETATE THE SITE: PREVENT EROSION ON INDIVIDUAL LOTS WITH GROUND COVER. EXISTING TREES AND VEGETATION SHOULD BE PROTECTED TO HELP MAINTAIN A STABLE GROUND SURFACE AND PREVENT LOSS OF VALUABLE TOPSOIL. EROSION CONTROL BLANKETS, MATTING AND MULCHES CAN HELP STABILIZE THE AREA UNTIL PERMANENT VEGETATION IS ESTABLISHED. THE SITE NEEDS TO HAVE AT LEAST 70 PERCENT COVER OF PERMANENT VEGETATION BEFORE ESC'S CAN BE REMOVED.

## ENGINEERING FILTER STRIPS





1. THE FILTER STRIP SHOULD EXTEND ALONG THE ENTIRE LENGTH OF THE CONTRIBUTING AREA AND THE SLOPE SHOULD NOT EXCEED 20%. THE MINIMUM DIMENSION OF THE FILTER STRIP (IN THE DIRECTION OF FLOW) SHOULD BE NO LESS THAN 15 FEET. THE MAXIMUM WIDTH (IN THE FLOW OF DIRECTION) OF THE CONTRIBUTING IMPERVIOUS AREA SHOULD NOT EXCEED 72 FEET. FOR ROADWAYS WITH A VEGETATED STRIP ALONG BOTH SIDES OF THE TOTAL WIDTH OF THE ROADWAY SHOULD NOT EXCEED 144 FEET.
2. THE MINIMUM VEGETATED COVER FOR ENGINEERED STRIPS IS 80%.
3. THE AREA CONTRIBUTING RUNOFF TO A FILTER STRIP SHOULD BE RELATIVELY FLAT SO THAT THE RUNOFF IS DISTRIBUTED EVENLY TO THE VEGETATED AREA WITHOUT THE USE OF A LEVEL SPREADER.
4. THE AREA TO BE USED FOR THE STRIP SHOULD BE FREE OF GULLIES OR RILLS THAT CAN CONCENTRATE OVERLAND FLOW.
5. THE TOP EDGE OF THE FILTER STRIP ALONG THE PAVEMENT WILL BE DESIGNED TO AVOID THE SITUATION WHERE RUNOFF WOULD TRAVEL ALONG THE TOP OF THE FILTER STRIP, RATHER THAN THROUGH IT.
6. THE TOP EDGE OF THE FILTER STRIP SHOULD BE LEVEL, OTHERWISE RUNOFF WILL TEND TO FORM A CHANNEL IN THE LOW SPOT. A LEVEL SPREADER SHOULD NOT BE USED TO DISTRIBUTE RUNOFF TO AND ENGINEERED FILTER STRIP.
7. FILTER STRIPS SHOULD BE LANDSCAPED AFTER OTHER PORTIONS OF THE PROJECT ARE COMPLETED.

## INTERIM FILTER STRIPS

1. THE FILTER STRIP AREA MUST BE 50% OF THE SIZE OF THE CONTRIBUTING IMPERVIOUS COVER.
2. TOP EDGE OF THE FILTER STRIP SHOULD BE LEVEL; OTHERWISE, RUNOFF WILL TEND TO FORM A CHANNEL IN THE LOW SPOT. IF A LEVEL SPREADER IS USED (IS ONLY ALLOWED FOR INTERIM USE) TO DISTRIBUTE RUNOFF TO THE FILTER STRIP, IT MUST BE LINED OR BE CONSTRUCTED OF IMPERMEABLE MATERIALS (CONCRETE).
3. THE AREA TO BE USED FOR THE STRIP SHOULD BE FREE OF GULLIES OR RILLS THAT CAN CONCENTRATE OVERLAND FLOW.
4. FILTER STRIPS SHOULD BE LANDSCAPED AFTER OTHER PORTIONS OF THE PROJECT ARE COMPLETED AND VEGETATION COVERAGE SHOULD BE AT LEAST 80%.


<div><p><b>BGE, INC.</b> 7330 S. Highway 82 Sugar Land, TX 75080 TEL: 281-481-3600 www.browning.com TBEPE Registration No. F-1046</p></div>		CANYON RANCH UNIT 4		EROSION & SEDIMENTATION CONTROL		DETAILS (SHEET 1 OF 2)	
DESIGNED BY:	NA	△					
REVIEWED BY:	ACR	△					
DRAWN BY:	SSM	△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					
		△					








G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C03.00 - ONSITE DRAINAGE PLAN.dwg Layout: ONSITE DRAINAGE PLAN (SHEET 1 OF 3) Plotted: 11/7/2024 9:33:36 AM By: Lhuck



- NOTE:
1. PROPOSED DRAINAGE PATTERNS ARE TO FOLLOW THE FINISHED LOT/PAD GRADING BASED ON THE LOT TYPE DESIGNATION AND DETAIL SHOWN ON SHEET C03.11.
  2. REFERENCE GRADING DETAIL ON SHEET C03.11



DATE		APR
DESCRIPTION		REV
DESIGNED BY:	LNH	
REVIEWED BY:	SSM	
DRAWN BY:	JDC	

**BGE INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-3800 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

ONSITE DRAINAGE PLAN (SHEET 1 OF 3)

STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024

SHEET


C03.00








G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C03.00 - ONSITE DRAINAGE PLAN.dwg Layout: ONSITE DRAINAGE PLAN (SHEET 3 OF 3) Plotted: 11/7/2024 9:33:45 AM By: Lhuck



- NOTE:
1. PROPOSED DRAINAGE PATTERNS ARE TO FOLLOW THE FINISHED LOT/PAD GRADING BASED ON THE LOT TYPE DESIGNATION AND DETAIL SHOWN ON SHEET C03.11.
  2. REFERENCE GRADING DETAIL ON SHEET C03.11



CANYON RANCH UNIT 4		ONSITE DRAINAGE PLAN (SHEET 3 OF 3)		STATE OF TEXAS STACY MULHOLLAND 146417 LICENSED PROFESSIONAL ENGINEER 11/08/2024 SHEET C03.02	
BGE, INC. 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 214-581-3680 www.bgeinc.com EPA Registration No. F-1046		DESIGNED BY: LNH REVIEWED BY: SSM DRAWN BY: JDC		DATE: APR	
BGE		REVISIONS		DESCRIPTION	
1		2		3	
4		5		6	
7		8		9	
10		11		12	
13		14		15	
16		17		18	
19		20		21	
22		23		24	
25		26		27	
28		29		30	
31		32		33	
34		35		36	
37		38		39	
40		41		42	
43		44		45	
46		47		48	
49		50		51	
52		53		54	
55		56		57	
58		59		60	
61		62		63	
64		65		66	
67		68		69	
70		71		72	
73		74		75	
76		77		78	
79		80		81	
82		83		84	
85		86		87	
88		89		90	
91		92		93	
94		95		96	
97		98		99	
100		101		102	
103		104		105	
106		107		108	
109		110		111	
112		113		114	
115		116		117	
118		119		120	
121		122		123	
124		125		126	
127		128		129	
130		131		132	
133		134		135	
136		137		138	
139		140		141	
142		143		144	
145		146		147	
148		149		150	
151		152		153	
154		155		156	
157		158		159	
160		161		162	
163		164		165	
166		167		168	
169		170		171	
172		173		174	
175		176		177	
178		179		180	
181		182		183	
184		185		186	
187		188		189	
190		191		192	
193		194		195	
196		197		198	
199		200		201	
202		203		204	
205		206		207	
208		209		210	
211		212		213	
214		215		216	
217		218		219	
220		221		222	
223		224		225	
226		227		228	
229		230		231	
232		233		234	
235		236		237	
238		239		240	
241		242		243	
244		245		246	
247		248		249	
250		251		252	
253		254		255	
256		257		258	
259		260		261	
262		263		264	
265		266		267	
268		269		270	
271		272		273	
274		275		276	
277		278		279	
280		281		282	
283		284		285	
286		287		288	
289		290		291	
292		293		294	
295		296		297	
298		299		300	
301		302		303	
304		305		306	
307		308		309	
310		311		312	
313		314		315	
316		317		318	
319		320		321	
322		323		324	
325		326		327	
328		329		330	
331		332		333	
334		335		336	
337		338		339	
340		341		342	
343		344		345	
346		347		348	
349		350		351	
352		353		354	
355		356		357	
358		359		360	
361		362		363	
364		365		366	
367		368		369	
370		371		372	
373		374		375	
376		377		378	
379		380		381	
382		383		384	
385		386		387	
388		389		390	
391		392		393	
394		395		396	
397		398		399	
400		401		402	
403		404		405	
406		407		408	
409		410		411	
412		413		414	
415		416		417	
418		419		420	
421		422		423	
424		425		426	
427		428		429	
430		431		432	
433		434		435	
436		437		438	
439		440		441	
442		443		444	
445		446		447	
448		449		450	
451		452		453	
454		455		456	
457		458		459	
460		461		462	
463		464		465	
466		467		468	
469		470		471	
472		473		474	
475		476		477	
478		479		480	
481		482		483	
484		485		486	
487		488		489	
490		491		492	
493		494		495	
496		497		498	
499		500		501	
502		503		504	
505		506		507	
508		509		510	
511		512		513	
514		515		516	
517		518		519	
520		521		522	
523		524		525	
526		527		528	
529		530		531	
532		533		534	
535		536		537	
538		539		540	
541		542		543	
544		545		546	
547		548		549	
550		551		552	
553		554		555	
556		557		558	
559		560		561	
562		563		564	
565		566		567	
568		569		570	
571		572		573	
574		575		576	
577		578		579	
580		581		582	
583		584		585	
586		587		588	
589		590		591	
592		593		594	
595		596		597	
598		599		600	
601		602		603	
604		605		606	
607		608		609	
610		611		612	
613		614		615	
616		617		618	
619		620		621	
622		623		624	
625		626		627	
628		629		630	
631		632		633	
634		635		636	
637		638		639	
640		641		642	
643		644		645	
646		647		648	
649		650		651	
652		653		654	
655		656		657	
658		659		660	
661		662		663	
664		665		666	
667		668		669	
670		671		672	
673		674		675	
676		677		678	
679		680		681	
682		683		684	
685		686		687	
688		689		690	
691		692		693	
694		695		696	
697		698		699	
700		701		702	
703		704		705	
706		707		708	
709		710		711	
712		713		714	
715		716		717	
718		719		720	
721		722		723	
724		725		726	
727		728		729	
730		731		732	
733		734		735	
736		737		738	
739		740		741	
742		743		744	
745		746		747	
748		749		750	
751		752		753	
754		755		756	
757		758		759	
760		761		762	
763		764		765	
766		767		768	
769		770		771	
772		773		774	
775		776		777	
778		779		780	
781		782		783	
784		785		786	
787		788		789	
790		791		792	
793		794		795	
796		797		798	
799		800		801	
802		803		804	
805		806		807	
808		809		810	
811		812		813	
814		815		816	
817		818		819	
820		821		822	
823		824		825	
826		827		828	
829		830		831	
832		833		834	
835		836		837	
838		839		840	
841		842		843	
844		845		846	
847		848		849	
850		851		852	
853		854		855	
856		857		858	
859		860		861	
862		863		864	
865		866		867	
868		869		870	
871		872		873	
874		875		876	
877		878		879	
880		881		882	
883		884		885	
886		887		888	
889		890		891	
892		893		894	
895		896		897	
898		899		900	
901		902		903	
904		905		906	
907		908		909	
910		911		912	
913		914		915	
916		917		918	
919		920		921	
922		923		924	
925		926		927	



G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C03.00 - ONSITE DRAINAGE PLAN.dwg Layout: ONSITE DRAINAGE CALCULATIONS (SHEET 1 OF 2) Plotted: 11/7/2024 9:33:46 AM By: Llvuck

Runoff Coefficients	10 Yr	25 Yr	100 Yr
Asphalt	0.81	0.86	0.95
Conc. / Roof	0.83	0.88	0.97
Grass (2-7%) good	0.35	0.39	0.46

Avg. Imperv. per lot
4,000 sf

			STREET									IMPERVIOUS				GRASS					
Drainage Area	Total Area (Ac)	Total Area (sf)	Street Width (ft)	Sidewalk Width (ft)	% of Street	Street Length (ft)	Sidewalk Length (ft)	Area Street (sf)	Area Street (Ac)	Area Street (%)	Num Homes in Area	Area Imper. (sf)	Area Imper. (Ac)	Area Imper. (%)	Area Grass (sf)	Area Grass (Ac)	Area Grass (%)	Composite 10 Yr "C"	Composite 25 Yr "C"	Composite 100 Yr "C"	
A1	0.68	29,621	51	4	50%	565	565	16,678	0.38	56.3%	0	0	0.00	0.0%	12,943	0.30	43.7%	0.61	0.65	0.74	
A2	0.50	21,780	31	4	50%	701	782	13,989	0.32	64.2%	0	0	0.00	0.0%	7,791	0.18	35.8%	0.65	0.69	0.77	
A3	1.46	63,598	31	4	65%	564	529	14,027	0.32	22.1%	7	28,000	0.64	44.0%	21,571	0.50	33.9%	0.66	0.71	0.79	
A4	1.00	43,560	31	4	50%	237	0	3,667	0.08	8.4%	6	24,000	0.55	55.1%	15,893	0.36	36.5%	0.65	0.70	0.78	
B1	1.07	46,609	31	4	50%	118	124	8,405	0.19	18.0%	5	20,000	0.46	42.9%	18,204	0.42	39.1%	0.64	0.69	0.77	
			51	4	50%	238	0														
			31	4	50%	136	136														2,643
B3	1.40	60,984	31	4	100%	159	93	12,246	0.28	20.1%	5	20,000	0.46	32.8%	28,738	0.66	47.1%	0.60	0.65	0.73	
			51	4	50%	258	0														
B4	1.31	57,064	51	4	50%	290	0	7,406	0.17	13.0%	2	8,000	0.18	14.0%	41,658	0.96	73.0%	0.48	0.52	0.60	
C1	1.69	73,616	31	4	100%	342	250	12,619	0.29	17.1%	10.5	42,000	0.96	57.1%	18,998	0.44	25.8%	0.70	0.75	0.83	
C2	0.93	40,511	31	4	61%	535	339	11,720	0.27	28.9%	5	20,000	0.46	49.4%	8,790	0.20	21.7%	0.72	0.77	0.85	
C3	0.36	15,682	31	4	50%	624	0	9,666	0.22	61.6%	0	0	0.00	0.0%	6,015	0.14	38.4%	0.63	0.68	0.76	
C4	1.08	47,045	31	4	50%	342	342	6,673	0.15	14.2%	8	32,000	0.73	68.0%	8,372	0.19	17.8%	0.74	0.79	0.88	
C5	4.04	175,982	31	4	100%	173	413	8,680	0.20	4.9%	7	28,000	0.64	15.9%	139,303	3.20	79.2%	0.45	0.49	0.57	
D1	0.21	9,148	31	4	50%	367	0	5,685	0.13	62.2%	0	0	0.00	0.0%	3,462	0.08	37.8%	0.64	0.68	0.76	
D2	0.80	34,848	31	4	50%	247	247	4,813	0.11	13.8%	6	24,000	0.55	68.9%	6,035	0.14	17.3%	0.74	0.79	0.88	
E1	1.66	72,310	31	4	100%	541	576	21,368	0.49	29.6%	3	12,000	0.28	16.6%	38,942	0.89	53.9%	0.57	0.61	0.69	
E2	0.53	23,087	31	4	50%	160	160	3,120	0.07	13.5%	4	16,000	0.37	69.3%	3,967	0.09	17.2%	0.74	0.79	0.88	
E3	0.79	34,412	31	4	50%	120	0	1,860	0.04	5.4%	6	24,000	0.55	69.7%	8,552	0.20	24.9%	0.71	0.76	0.84	
E4	1.05	45,738	31	4	50%	160	0	2,480	0.06	5.4%	8	32,000	0.73	70.0%	11,258	0.26	24.6%	0.71	0.76	0.84	
E5	0.68	29,621	31	4	50%	205	205	3,998	0.09	13.5%	5	20,000	0.46	67.5%	5,623	0.13	19.0%	0.74	0.78	0.87	
E6	1.09	47,480	31	4	50%	400	0	6,200	0.14	13.1%	6	24,000	0.55	50.5%	17,280	0.40	36.4%	0.65	0.70	0.78	
E7	1.19	51,836	31	4	50%	214	299	4,510	0.10	8.7%	7	28,000	0.64	54.0%	19,326	0.44	37.3%	0.65	0.70	0.78	
E8	0.95	41,382	31	4	50%	218	251	4,381	0.10	10.6%	0	0	0.00	0.0%	37,001	0.85	89.4%	0.40	0.44	0.51	
E9	4.71	205,168	31	4	50%	1,159	1,123	22,449	0.52	10.9%	13	52,000	1.19	25.3%	130,719	3.00	63.7%	0.52	0.57	0.64	
E10	3.29	143,312	31	4	50%	0	0	0	0.00	0.0%	9	36,000	0.83	25.1%	107,312	2.46	74.9%	0.47	0.51	0.59	
F1-L	0.61	26,572	31	4	71%	292	246	7,788	0.18	29.3%	2	8,000	0.18	30.1%	10,784	0.25	40.6%	0.63	0.68	0.76	
F1-R	0.30	13,068	31	4	61%	106	106	2,530	0.06	19.4%	2	8,000	0.18	61.2%	2,538	0.06	19.4%	0.73	0.78	0.87	
F2-L	0.14	6,098	31	4	50%	243	34	3,906	0.09	64.0%	0	0	0.00	0.0%	2,193	0.05	36.0%	0.64	0.69	0.77	
F2-R	0.27	11,761	31	4	50%	486	0	7,540	0.17	64.1%	0	0	0.00	0.0%	4,221	0.10	35.9%	0.64	0.69	0.77	
F3	0.81	35,284	31	4	50%	526	357	9,583	0.22	27.2%	4	16,000	0.37	45.3%	9,701	0.22	27.5%	0.69	0.74	0.82	
F4	0.55	23,958	31	4	50%	165	165	3,218	0.07	13.4%	4	16,000	0.37	66.8%	4,741	0.11	19.8%	0.73	0.78	0.87	
F5	0.65	28,314	31	4	50%	180	180	3,516	0.08	12.4%	5	20,000	0.46	70.6%	4,798	0.11	16.9%	0.75	0.79	0.88	
SAW	0.17	7,405	31	4	50%	313	0	4,855	0.11	65.6%	0	0	0.00	0.0%	2,550	0.06	34.4%	0.65	0.70	0.78	
G1	1.90	82,764	31	4	50%	310	310	6,048	0.14	7.3%	3	12,000	0.28	14.5%	64,716	1.49	78.2%	0.45	0.50	0.57	
G2	0.92	40,075	31	4	50%	287	287	5,598	0.13	14.0%	5	20,000	0.46	49.9%	14,477	0.33	36.1%	0.65	0.70	0.78	
H1	2.93	127,631	31	4	0%	0	0	0	0.00	0.0%	11	44,000	1.01	34.5%	83,631	1.92	65.5%	0.52	0.56	0.64	
I1	0.93	40,511	31	4	50%	240	240	4,680	0.11	11.6%	6	24,000	0.55	59.2%	11,831	0.27	29.2%	0.69	0.73	0.82	
I2	0.25	10,890	31	4	50%	441	441	8,592	0.20	78.9%	0	0	0.00	0.0%	2,298	0.05	21.1%	0.71	0.76	0.85	
I3	1.35	58,806	31	4	50%	237	240	4,626	0.11	7.9%	6	24,000	0.55	40.8%	30,180	0.69	51.3%	0.58	0.63	0.71	
I4	0.51	22,216	31	4	0%	0	0	0	0.00	0.0%	2	8,000	0.18	36.0%	14,216	0.33	64.0%	0.52	0.57	0.64	
J1	3.11	135,472	31	4	100%	238	526	11,577	0.27	8.5%	3	12,000	0.28	8.9%	111,894	2.57	82.6%	0.43	0.47	0.55	
UNCAP 1	0.31	13,504	31	4	100%	79	39	2,761	0.06	20.4%	1	4,000	0.09	29.6%	6,742	0.15	49.9%	0.59	0.63	0.71	
UNCAP 2	2.61	113,692	31	4	0%	0	0	0	0.00	0.0%	16	64,000	1.47	56.3%	49,692	1.14	43.7%	0.62	0.67	0.75	
UNCAP 3	0.09	3,920	51	4	61%	88	19	2,803	0.06	71.5%	0	0	0.00	0.0%	1,117	0.03	28.5%	0.68	0.73	0.81	
UNCAP 4	4.21	183,388	31	4	69%	411	0	8,845	0.20	4.8%	30	120,000	2.75	65.4%	54,542	1.25	29.7%	0.69	0.73	0.82	

STREET FLOW AND INLET CALCULATIONS																															
10 YEAR STORM																															
						STREET CAPACITY					INLET ON GRADE CAPACITY										SUMP INLET CAPACITY										
Drainage Area	Inlet	Area (Ac)	Q <sub>(10)</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Q <sub>(basin)</sub> (cfs)	FOC to FOC (ft)	Crown Type	Street Slope (ft/ft)	a (ft)	Z	Y <sub>o</sub> (ft)	Ponded Width (ft)	Reduction Factor (%)	Q <sub>a</sub> /L <sub>a</sub> (ft)	L <sub>a</sub> (ft)	Length (ft)	L/L <sub>a</sub>	a/Y <sub>o</sub>	Q/Q <sub>a</sub>	Q <sub>a</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Pass to Inlet #	Clogging Factor (%)	Q <sub>(total)</sub> (cfs)	Length (ft)	W (ft)	Opening Height (ft)	C <sub>w</sub>	C <sub>o</sub>	h (ft)	
A1	ON GRADE	0.68	3.11	0.00	3.11	50	S	0.064	0.58	50	0.14	7.21	0%	0.93	3.34	10	2.99	4.05	0.33	9.3	0.00										
A2	SUMP	0.50	2.42	0.00	2.42	30	S	0.070	0.58	50	0.13	6.45												10%	2.4	10	2	0.583	2.3	0.67	0.19
A3	ON GRADE	1.46	7.26	0.00	7.26	30	S	0.070	0.58	50	0.19	9.74	0%	0.99	7.37	10	1.36	3.00	0.74	9.9	0.00										
A4	ON GRADE	1.00	4.90	0.00	4.90	30	S	0.040	0.58	50	0.19	9.33	0%	0.98	5.02	10	1.99	3.13	0.50	9.8	0.00										
B1	ON GRADE	1.07	5.13	0.00	5.13	30	S		0.58	50																					
						50		0.064	0.58	50	0.17	8.70	0%	0.96	5.33	15	2.82	3.35	0.36	14.4	0.00										
B2	ON GRADE	0.87	4.64	0.00	4.64	30	S	0.010	0.58	50	0.24	11.86	0%	1.03	4.49	10	2.22	2.46	0.45	10.3	0.00										
B3	ON GRADE	1.40	6.30	0.00	6.30	30	S		0.58	50																					
						50		0.064	0.58	50	0.19	9.39	0%	0.98	6.44	10	1.55	3.11	0.64	9.8	0.00										
B4	ON GRADE	1.31	4.69	0.00	4.69	50	S	0.030	0.58	50	0.19	9.70	0%	0.98	4.76	10	2.10	3.01	0.48	9.8	0.00										
C1	SUMP	1.69	8.91	0.00	8.91	30	S	0.008	0.58	50	0.32	15.98												10%	8.9	15	2	0.583	2.3	0.67	0.22
C2	ON GRADE	0.93	5.02	0.00	5.02	30	S	0.065	0.58	50	0.17	8.60	0%	0.96	5.23	10	1.91	3.39	0.52	9.6	0.00										
C3	ON GRADE	0.36	1.71	0.00	1.71	30	S	0.065	0.58	50	0.11	5.74	0%	0.90	1.90	10	5.25	5.08	0.19	9.0	0.00										
C4	ON GRADE	1.08	6.01	0.00	6.01	30	S	0.028	0.58	50	0.22	10.81	0%	1.01	5.95	10	1.68	2.70	0.60	10.1	0.00										
D1	ON GRADE	0.21	1.00	0.00	1.00	30	S	0.023	0.58	50	0.11	5.73	0%	0.90	1.11	10	8.97	5.09	0.11	9.0	0.00										
D2	ON GRADE	0.80	4.46	0.00	4.46	30	S	0.023	0.58	50	0.20	10.04	0%	0.99	4.50	10	2.22	2.91	0.45	9.9	0.00										
E1	ON GRADE	1.66	7.04	0.00	7.04	30	S	0.038	0.58	50	0.22	10.81	0%	1.01	6.98	10	1.43	2.70	0.70	10.1	0.00										
E2	ON GRADE	0.53	2.96	0.00	2.96	30	S	0.008	0.58	50	0.21	10.57	0%	1.00	2.95	10	3.39	2.76	0.29	10.0	0.00										
E3	ON GRADE	0.79	4.20	0.00	4.20	30	S	0.008	0.58	50	0.24	12.06	0%	1.04	4.05	10	2.47	2.42	0.41	10.4	0.00										
E4	ON GRADE	1.05	5.60	0.00	5.60	30	S	0.044	0.58	50	0.19	9.62	0%	0.98	5.70	10	1.76	3.03	0.57	9.8	0.00										
E5	ON GRADE	0.68	3.75	0.00	3.75	30	S	0.044	0.58	50	0.17	8.28	0%	0.95	3.94	10	2.54	3.52	0.39	9.5	0.00										
E6	ON GRADE	1.09	5.34	0.00	5.34	30	S	0.044	0.58	50	0.19	9.46	0%	0.98	5.45	10	1.84	3.08	0.54	9.8	0.00										
E7	ON GRADE	1.19	5.80	0.00	5.80	30	S	0.020	0.58	50	0.23	11.32	0%	1.02	5.68	10	1.76	2.58	0.57	10.2	0.00										
E8	ON GRADE	0.95	2.84	0.00	2.84	30	S	0.080	0.58	50	0.13	6.68	0%	0.92	3.09	10	3.23	4.37	0.31	9.2	0.00										
F1-L	SUMP	0.61	2.88	0.00	2.88	30	S	0.008	0.58	50	0.21	10.46												10%	4.5	10	2	0.583	2.3	0.67	0.30
F1-R	SUMP	0.30	1.65	0.00	1.65	30	S	0.008	0.58	50	0.17	8.49																			
F2-L	SUMP	0.14	0.68	0.00	0.68	30	S	0.008	0.58	50	0.12	6.08												10%	2.0	10	2	0.583	2.3	0.67	0.17
F2-R	SUMP	0.27	1.31	0.00	1.31	30	S	0.008	0.58	50	0.16	7.78																			
F3	ON GRADE	0.81	4.21	0.00	4.21	30	S	0.040	0.58	50	0.18	8.81	0%	0.96	4.36	10	2.29	3.31	0.44	9.6	0.00										
F4	ON GRADE	0.55	3.02	0.00	3.02	30	S	0.008	0.58	50	0.21	10.65	0%	1.01	3.00	10	3.33	2.74	0.30	10.1	0.00										
F5	ON GRADE	0.65	3.64	0.00	3.64	30	S	0.008	0.58	50	0.23	11.42	0%	1.02	3.56	10	2.81	2.55	0.36	10.2	0.00										
G1	ON GRADE	1.90	6.46	0.00	6.46	30	S	0.055	0.58	50	0.19	9.75	0%	0.99	6.55	10	1.53	2.99	0.66	9.9	0.00										
G2	ON GRADE	0.92	4.19	0.00	4.19	30	S	0.055	0.58	50	0.17	8.29	0%	0.95	4.40	10	2.27	3.52	0.44	9.5	0.00										
I1	ON GRADE	0.93	4.80	0.00	4.80	30	S	0.450	0.58	50	0.12	5.88	0%	0.90	5.32	10	1.88	4.96	0.53	9.0	0.00										
I2	ON GRADE	0.25	1.34	0.00	1.34	30	S	0.450	0.58	50	0.07	3.64	0%	0.85	1.56	10	6.39	8.01	0.16	8.5	0.00										
I3	ON GRADE	1.35	5.89	0.00	5.89	30	S	0.018	0.58	50	0.23	11.68	0%	1.03	5.73	10	1.75	2.50	0.57	10.3	0.00										
SAW	---	0.17	0.83	0.00	0.83																										
UNCAP 1	---	0.31	1.36	0.00	1.36																										
UNCAP 2	---	2.61	12.14	0.00	12.14																										
UNCAP 3	---	0.09	0.46	0.00	0.46																										
UNCAP 4	---	4.21	21.67	0.00	21.67																										




G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C03.00 - ONSITE DRAINAGE CALCULATIONS (SHEET 2 OF 2) Plotted: 11/7/2024 9:33:48 AM By: Llvuck

STREET FLOW AND INLET CALCULATIONS																															
25 YEAR STORM																															
						STREET CAPACITY						INLET ON GRADE CAPACITY										SUMP INLET CAPACITY									
Drainage Area	Inlet	Area (Ac)	Q <sub>(25)</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Q <sub>(basin)</sub> (cfs)	FOC to FOC (ft)	Crown Type	Street Slope (ft/ft)	a (ft)	Z	Y <sub>o</sub> (ft)	Ponded Width (ft)	Reduction Factor (%)	Q <sub>s</sub> /L <sub>a</sub> (ft)	L <sub>a</sub> (ft)	Length (ft)	L/L <sub>a</sub>	a/Y <sub>o</sub>	Q/Q <sub>a</sub>	Q <sub>a</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Pass to Inlet #	Clogging Factor (%)	Q <sub>(total)</sub> (cfs)	Length (ft)	W (ft)	Opening Height (ft)	C <sub>w</sub>	C <sub>o</sub>	h (ft)	
A1	ON GRADE	0.68	4.06	0.00	4.06	50	S	0.064	0.58	50	0.16	7.97	0%	0.95	4.29	10	2.33	3.66	0.43	9.5	0.00			10%	3.2	10	2	0.583	2.3	0.67	0.23
A2	SUMP	0.50	3.15	0.00	3.15	30	S	0.070	0.58	50	0.14	7.12																			
A3	ON GRADE	1.46	9.45	0.00	9.45	30	S	0.070	0.58	50	0.21	10.75	0%	1.01	9.37	10	1.07	2.71	0.94	10.1	0.00										
A4	ON GRADE	1.00	6.38	0.00	6.38	30	S	0.040	0.58	50	0.21	10.30	0%	1.00	6.39	10	1.56	2.83	0.64	10.0	0.00										
B1	ON GRADE	1.07	6.68	0.00	6.68	30	S		0.58	50																					
						50		0.064	0.58	50	0.19	9.61	0%	0.98	6.80	15	2.20	3.04	0.45	14.7	0.00										
B2	ON GRADE	0.87	6.02	0.00	6.02	30	S	0.010	0.58	50	0.26	13.07	0%	1.06	5.68	10	1.76	2.23	0.57	10.6	0.00										
B3	ON GRADE	1.40	8.24	0.00	8.24	30	S		0.58	50																					
						50		0.064	0.58	50	0.21	10.39	0%	1.00	8.24	10	1.21	2.81	0.82	10.0	0.00										
B4	ON GRADE	1.31	6.21	0.00	6.21	50	S	0.030	0.58	50	0.22	10.78	0%	1.01	6.16	10	1.62	2.70	0.62	10.1	0.00										
C1	SUMP	1.69	11.56	0.00	11.56	30	S	0.008	0.58	50	0.35	17.62												10%	11.6	15	2	0.583	2.3	0.67	0.29
C2	ON GRADE	0.93	6.51	0.00	6.51	30	S	0.065	0.58	50	0.19	9.48	0%	0.98	6.65	10	1.50	3.08	0.66	9.8	0.00										
C3	ON GRADE	0.36	2.23	0.00	2.23	30	S	0.065	0.58	50	0.13	6.34	0%	0.91	2.45	10	4.08	4.60	0.24	9.1	0.00										
C4	ON GRADE	1.08	7.78	0.00	7.78	30	S	0.028	0.58	50	0.24	11.91	0%	1.03	7.53	10	1.33	2.45	0.75	10.3	0.00										
D1	ON GRADE	0.21	1.31	0.00	1.31	30	S	0.023	0.58	50	0.13	6.33	0%	0.91	1.43	10	6.97	4.61	0.14	9.1	0.00										
D2	ON GRADE	0.80	5.78	0.00	5.78	30	S	0.023	0.58	50	0.22	11.06	0%	1.01	5.70	10	1.76	2.64	0.57	10.1	0.00										
E1	ON GRADE	1.66	9.24	0.00	9.24	30	S	0.038	0.58	50	0.24	11.97	0%	1.04	8.92	10	1.12	2.44	0.89	10.4	0.00										
E2	ON GRADE	0.53	3.83	0.00	3.83	30	S	0.008	0.58	50	0.23	11.65	0%	1.03	3.73	10	2.68	2.50	0.37	10.3	0.00										
E3	ON GRADE	0.79	5.46	0.00	5.46	30	S	0.008	0.58	50	0.27	13.30	0%	1.07	5.12	10	1.95	2.19	0.51	10.7	0.00										
E4	ON GRADE	1.05	7.26	0.00	7.26	30	S	0.044	0.58	50	0.21	10.61	0%	1.00	7.23	10	1.38	2.75	0.72	10.0	0.00										
E5	ON GRADE	0.68	4.86	0.00	4.86	30	S	0.044	0.58	50	0.18	9.13	0%	0.97	5.00	10	2.00	3.19	0.50	9.7	0.00										
E6	ON GRADE	1.09	6.95	0.00	6.95	30	S	0.044	0.58	50	0.21	10.45	0%	1.00	6.94	10	1.44	2.79	0.69	10.0	0.00										
E7	ON GRADE	1.19	7.55	0.00	7.55	30	S	0.020	0.58	50	0.25	12.50	0%	1.05	7.21	10	1.39	2.33	0.72	10.5	0.00										
E8	ON GRADE	0.95	3.81	0.00	3.81	30	S	0.080	0.58	50	0.15	7.46	0%	0.94	4.07	10	2.45	3.91	0.41	9.4	0.00										
F1-L	SUMP	0.61	3.76	0.00	3.76	30	S	0.008	0.58	50	0.23	11.56												10%	5.9	10	2	0.583	2.3	0.67	0.35
F1-R	SUMP	0.30	2.14	0.00	2.14	30	S	0.008	0.58	50	0.19	9.36																			
F2-L	SUMP	0.14	0.88	0.00	0.88	30	S	0.008	0.58	50	0.13	6.71												10%	2.6	10	2	0.583	2.3	0.67	0.20
F2-R	SUMP	0.27	1.70	0.00	1.70	30	S	0.008	0.58	50	0.17	8.59																			
F3	ON GRADE	0.81	5.47	0.00	5.47	30	S	0.040	0.58	50	0.19	9.72	0%	0.98	5.55	10	1.80	3.00	0.55	9.8	0.00										
F4	ON GRADE	0.55	3.91	0.00	3.91	30	S	0.008	0.58	50	0.23	11.74	0%	1.03	3.80	10	2.63	2.48	0.38	10.3	0.00										
F5	ON GRADE	0.65	4.71	0.00	4.71	30	S	0.008	0.58	50	0.25	12.58	0%	1.05	4.49	10	2.23	2.32	0.45	10.5	0.00										
G1	ON GRADE	1.90	8.58	0.00	8.58	30	S	0.055	0.58	50	0.22	10.85	0%	1.01	8.50	10	1.18	2.69	0.85	10.1	0.00										
G2	ON GRADE	0.92	5.44	0.00	5.44	30	S	0.055	0.58	50	0.18	9.14	0%	0.97	5.60	10	1.79	3.19	0.56	9.7	0.00										
I1	ON GRADE	0.93	6.23	0.00	6.23	30	S	0.450	0.58	50	0.13	6.49	0%	0.91	6.81	10	1.47	4.50	0.68	9.1	0.00										
I2	ON GRADE	0.25	1.73	0.00	1.73	30	S	0.450	0.58	50	0.08	4.02	0%	0.86	2.01	10	4.97	7.26	0.20	8.6	0.00										
I3	ON GRADE	1.35	7.72	0.00	7.72	30	S	0.018	0.58	50	0.26	12.92	0%	1.06	7.30	10	1.37	2.26	0.73	10.6	0.00										
SAW	---	0.17	1.08	0.00	1.08																										
UNCAP 1	---	0.31	1.78	0.00	1.78																										
UNCAP 2	---	2.61	15.85	0.00	15.85																										
UNCAP 3	---	0.09	0.60	0.00	0.60																										
UNCAP 4	---	4.21	28.16	0.00	28.16																										

STREET FLOW AND INLET CALCULATIONS																															
100 YEAR STORM																															
						STREET CAPACITY				INLET ON GRADE CAPACITY											SUMP INLET CAPACITY										
Drainage Area	Inlet	Area (Ac)	Q <sub>(100)</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Q <sub>(basin)</sub> (cfs)	FOC to FOC (ft)	Crown Type	Street Slope (ft/ft)	a (ft)	Z	Y <sub>o</sub> (ft)	Ponded Width (ft)	Reduction Factor (%)	Q <sub>a</sub> /L <sub>a</sub> (ft)	L <sub>a</sub> (ft)	Length (ft)	L/L <sub>a</sub>	a/Y <sub>o</sub>	Q/Q <sub>a</sub>	Q <sub>a</sub> (cfs)	Q <sub>(pass)</sub> (cfs)	Pass to Inlet #	Clogging Factor (%)	Q <sub>(total)</sub> (cfs)	Length (ft)	W (ft)	Opening Height (ft)	C <sub>w</sub>	C <sub>o</sub>	h (ft)	
A1	ON GRADE	0.68	5.85	0.00	5.85	50	S	0.064	0.58	50	0.18	9.14	0%	0.97	6.02	10	1.66	3.19	0.60	9.7	0.00										
A2	SUMP	0.50	4.53	3.11	7.64	30	S	0.070	0.58	50	0.20	9.93												10%	7.6	10	2	0.583	2.3	0.67	0.42
A3	ON GRADE	1.46	13.54	0.00	13.54	30	S	0.070	0.58	50	0.25	12.30	0%	1.04	12.98	10	0.77	2.37	1.30	10.4	3.11	A2									
A4	ON GRADE	1.00	9.15	0.00	9.15	30	S	0.040	0.58	50	0.24	11.79	0%	1.03	8.87	10	1.13	2.47	0.89	10.3	0.00										
B1	ON GRADE	1.07	9.60	1.54	11.15	30	S		0.58	50																					
						50		0.064	0.58	50	0.23	11.64	0%	1.03	12.22	15	1.23	2.51	0.81	15.4	0.00										
B2	ON GRADE	0.87	8.59	0.00	8.59	30	S	0.010	0.58	50	0.30	14.94	0%	1.10	6.51	10	1.54	1.95	0.65	11.0	0.00										
B3	ON GRADE	1.40	11.89	0.00	11.89	30	S		0.58	50																					
						50		0.064	0.58	50	0.24	11.92	0%	1.03	11.49	10	0.87	2.45	1.15	10.3	1.54	B1									
B4	ON GRADE	1.31	9.12	0.00	9.12	50	S	0.030	0.58	50	0.25	12.46	0%	1.05	8.72	10	1.15	2.34	0.87	10.5	0.00										
C1	SUMP	1.69	16.51	0.00	16.51	30	S	0.008	0.58	50	0.40	20.14												10%	16.5	15	2	0.583	2.3	0.67	0.41
C2	ON GRADE	0.93	9.29	0.35	9.64	30	S	0.065	0.58	50	0.22	10.98	0%	1.01	9.52	10	1.05	2.66	0.95	10.1	0.00										
C3	ON GRADE	0.36	3.21	0.00	3.21	30	S	0.065	0.58	50	0.15	7.27	0%	0.93	3.45	10	2.90	4.01	0.34	9.3	0.00										
C4	ON GRADE	1.08	11.07	0.00	11.07	30	S	0.028	0.58	50	0.27	13.59	0%	1.07	10.33	10	0.97	2.15	1.03	10.7	0.35	C2									
D1	ON GRADE	0.21	1.88	0.00	1.88	30	S	0.023	0.58	50	0.15	7.26	0%	0.93	2.02	10	4.96	4.02	0.20	9.3	0.00										
D2	ON GRADE	0.80	8.23	0.00	8.23	30	S	0.023	0.58	50	0.25	12.62	0%	1.05	7.83	10	1.28	2.31	0.78	10.5	0.00										
E1	ON GRADE	1.66	13.39	0.00	13.39	30	S	0.038	0.58	50	0.28	13.75	0%	1.08	12.44	15	1.21	2.12	0.83	16.1	0.00										
E2	ON GRADE	0.53	5.45	0.00	5.45	30	S	0.008	0.58	50	0.27	13.30	0%	1.07	5.12	10	1.95	2.19	0.51	10.7	0.00										
E3	ON GRADE	0.79	7.78	0.00	7.78	30	S	0.008	0.58	50	0.30	15.19	0%	1.11	5.61	10	1.78	1.92	0.56	11.1	0.00										
E4	ON GRADE	1.05	10.36	0.00	10.36	30	S	0.044	0.58	50	0.24	12.12	0%	1.04	9.97	10	1.00	2.41	1.00	10.4	0.00										
E5	ON GRADE	0.68	6.93	0.00	6.93	30	S	0.044	0.58	50	0.21	10.42	0%	1.00	7.60	10	1.32	2.80	0.76	10.0	0.00										
E6	ON GRADE	1.09	9.97	0.00	9.97	30	S	0.044	0.58	50	0.24	11.96	0%	1.04	9.63	10	1.04	2.44	0.96	10.4	0.00										
E7	ON GRADE	1.19	10.83	0.00	10.83	30	S	0.020	0.58	50	0.29	14.31	0%	1.09	9.33	10	1.07	2.04	0.93	10.9	0.00										
E8	ON GRADE	0.95	5.69	0.00	5.69	30	S	0.080	0.58	50	0.17	8.67	0%	0.96	5.92	10	1.69	3.37	0.59	9.6	0.00										
F1-L	SUMP	0.61	5.40	2.18	7.58	30	S	0.008	0.58	50	0.30	15.05												10%	12.2	10	2	0.583	2.3	0.67	0.57
F1-R	SUMP	0.30	3.04	0.00	3.04	30	S	0.008	0.58	50	0.21	10.68																			
F2-L	SUMP	0.14	1.27	0.00	1.27	30	S	0.008	0.58	50	0.15	7.69												10%	3.7	10	2	0.583	2.3	0.67	0.26
F2-R	SUMP	0.27	2.45	0.00	2.45	30	S	0.008	0.58	50	0.20	9.84																			
F3	ON GRADE	0.81	7.81	1.22	9.03	30	S	0.040	0.58	50	0.23	11.74	0%	1.03	8.77	10	1.14	2.48	0.88	10.3	0.00										
F4	ON GRADE	0.55	5.58	0.00	5.58	30	S	0.008	0.58	50	0.27	13.41	0%	1.07	5.67	10	1.76	2.18	0.57	10.7	0.00										
F5	ON GRADE	0.65	6.70	0.00	6.70	30	S	0.008	0.58	50	0.29	14.36	0%	1.09	5.71	10	1.75	2.03	0.57	10.9	0.00										
G1	ON GRADE	1.90	12.67	0.00	12.67	30	S	0.055	0.58	50	0.25	12.55	0%	1.05	12.08	10	0.83	2.32	1.21	10.5	2.18	F1-L									
G2	ON GRADE	0.92	7.80	0.00	7.80	30	S	0.055	0.58	50	0.21	10.47	0%	1.00	7.79	10	1.28	2.79	0.78	10.0	0.00										
I1	ON GRADE	0.93	8.91	0.00	8.91	30	S	0.450	0.58	50	0.15	7.42	0%	0.93	11.31	10	0.88	3.93	1.13	9.3	1.22	F3									
I2	ON GRADE	0.25	2.48	0.00	2.48	30	S	0.450	0.58	50	0.09	4.59	0%	0.87	2.83	10	3.53	6.36	0.28	8.7	0.00										
I3	ON GRADE	1.35	11.16	0.00	11.16	30	S	0.018	0.58	50	0.30	14.84	0%	1.10	8.63	10	1.16	1.97	0.86	11.0	0.00										
SAW	---	0.17	1.55	0.00	1.55																										
UNCAP 1	---	0.31	2.58	0.00	2.58																										
UNCAP 2	---	2.61	22.81	0.00	22.81																										
UNCAP 3	---	0.09	0.85	0.00	0.85																										
UNCAP 4	---	4.21	40.26	0.00	40.26																										






1. HOME BUILDER SHALL REFER TO THE APPROVED SUBDIVISION PLAT TO CONFIRM ALL BUILDING SETBACKS PRIOR TO ANY FOUNDATION WORK.
2. AS SOON AS PRACTICAL, HOME BUILDER SHALL ESTABLISH VEGETATION (HYDRUMULCH, SEEDING, SODDING, ETC.,...) TO PREVENT EROSION FROM OCCURRING.
3. CONTRACTOR SHALL CONTACT ENGINEER REGARDING ANY QUESTIONS ON THE INTENT OF THIS PLAN.
4. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS AND TOWARDS THE PROPER DRAINAGE EASEMENT OF STREET RIGHT OF WAY ACCORDING TO THE MAJOR DRAINAGE PLAN FOR THE PROJECT.
5. CONTRACTOR SHOULD TAKE THE NECESSARY MEASURES TO ALLOW PONDING OF WATER. GRADING PLAN IS INTENDED FOR USE IN LOT GRADING ONLY. CONTRACTOR SHOULD REFER TO CONSTRUCTION DRAWINGS FOR ALL OTHER GRADES, INCLUDING, BUT NOT LIMITED TO, CHANNELS, ROADS, AND DETENTION PONDS.
6. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ALL SWALES.
7. EARTHEN GRADING SLOPES SHALL BE NO GREATER THAN 3:1.
8. SLOPES GREATER THAN 3:1 ARE ASSUMED TO BE MILLED ROCK. IF SITE CONDITIONS VARY FROM THIS, NOTIFY ENGINEER IMMEDIATELY.
9. SEE SHEET C03.12 FOR TYPICAL LOT GRADING TYPE DETAILS


1. ALL LOTS WITH FILL SHALL BE COMPACTED IN ACCORDANCE WITH THE 79G PROCEDURE THAT MEETS THE REQUIREMENTS OF THE FHA DATA SHEET. DOCUMENTATION AND THE EVIDENCE OF COMPACTED SHALL BE FURNISHED TO THE ENGINEER & OWNER.

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND OR FINISHED FLOOR ELEVATION WHICH EVER IS HIGHER, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORM WATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO THE STORM WATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE PROPERLY SIZED CROSS SLOPE PREVENTING RUNOFF FROM ENTERING THE STRUCTURE.


DESIGNED BY:	ACR
REVIEWED BY:	SSM
DRAWN BY:	ACR



OVERALL GRADING PLAN (SHEET 1 OF 3)







GENERAL NOTES:

1. HOME BUILDER SHALL REFER TO THE APPROVED SUBDIVISION PLAN TO CONFIRM ALL BUILDING SETBACKS PRIOR TO ANY FOUNDATION WORK.
2. AS SOON AS PRACTICAL, HOME BUILDER SHALL ESTABLISH VEGETATION (HYDROMULCH, SEEDING, SODDING, ETC...) TO PREVENT EROSION FROM OCCURRING.
3. CONTRACTOR SHALL CONTACT ENGINEER REGARDING ANY QUESTIONS ON THE INTENT OF THIS PLAN.
4. POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS AND TOWARDS THE PROPER DRAINAGE EASEMENT OF STREET RIGHT OF WAY ACCORDING TO THE MASTER DRAINAGE PLAN FOR THE PROJECT.
5. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NOT TO ALLOW PONDING OF WATER.
6. GRADING PLAN IS INTENDED FOR USE IN LOT GRADING ONLY. CONTRACTOR SHOULD REFER TO CONSTRUCTION DRAWINGS FOR ALL OTHER GRADES, INCLUDING, BUT NOT LIMITED TO, CHANNELS, ROADS, AND DETENTION PONDS.
7. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ALL SWALES.
8. EARTHEN GRADING SLOPES SHALL BE NO GREATER THAN 3:1.
9. SLOPES GREATER THAN 3:1 ARE ASSUMED TO BE MILLED ROCK. IF SITE CONDITIONS VARY FROM THIS, NOTIFY ENGINEER IMMEDIATELY.
10. SEE SHEET C03.12 FOR TYPICAL LOT GRADING TYPE DETAILS

**LOT FILL NOTES:**

1. ALL LOTS WITH FILL SHALL BE COMPACTED IN ACCORDANCE WITH THE 79G PROCEDURE THAT MEETS THE REQUIREMENTS OF THE FHA DATA SHEET. DOCUMENTATION AND THE EVIDENCE OF COMPACTED SHALL BE FURNISHED TO THE ENGINEER & OWNER.

## FINISHED FLOOR ELEVATIONS

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND OR FINISHED FLOOR ELEVATION WHICH EVER IS HIGHER, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORM WATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO THE STORM WATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE STRUCTURE.

[illegible]

DESIGNED BY:	ACR
REVIEWED BY:	SSM
DRAWN BY:	ACR



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 [www.browning.com](http://www.browning.com)

CANYON RANCH UNIT 4

OVERALL GRADING PLAN (SHEET 2 OF 3)





11/08/2024

SHEET  
C03.11



G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C03.10 - OVERALL GRADING PLAN.dwg Layout: C03.12 OVERALL GRADING PLAN (SHEET 3 OF 3) Plotted: 11/7/2024 9:37:01 AM By: Arath



- GENERAL NOTES:**
- HOME BUILDER SHALL REFER TO THE APPROVED SUBDIVISION PLAT TO CONFIRM ALL BUILDING SETBACKS PRIOR TO ANY FOUNDATION WORK.
  - AS SOON AS PRACTICAL, HOME BUILDER SHALL ESTABLISH VEGETATION (HYDROMULCH, SEEDING, SODDING, ETC...) TO PREVENT EROSION FROM OCCURRING. CONTRACTOR SHALL CONTACT ENGINEER REGARDING ANY QUESTIONS ON THE INTENT OF THIS PLAN.
  - POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL SURFACE AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS AND TOWARDS THE PROPER DRAINAGE EASEMENT OF STREET RIGHT OF WAY ACCORDING TO THE MASTER DRAINAGE PLAN FOR THE PROJECT. CONTRACTOR SHOULD TAKE PRECAUTIONS NOT TO ALLOW PONDING OF WATER.
  - GRADING PLAN IS INTENDED FOR USE IN LOT GRADING ONLY. CONTRACTOR SHOULD REFER TO CONSTRUCTION DRAWINGS FOR ALL OTHER GRADES, INCLUDING, BUT NOT LIMITED TO, CHANNELS, ROADS, AND DETENTION PONDS.
  - CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ALL SWALES.
  - EARTHEN GRADING SLOPES SHALL BE NO GREATER THAN 3:1.
  - SLOPES GREATER THAN 3:1 ARE ASSUMED TO BE MILLED ROCK. IF SITE CONDITIONS VARY FROM THIS, NOTIFY ENGINEER IMMEDIATELY.
  - SEE SHEET C03.12 FOR TYPICAL LOT GRADING TYPE DETAILS

- LOT FILL NOTES:**
- ALL LOTS WITH FILL SHALL BE COMPACTED IN ACCORDANCE WITH THE 79G PROCEDURE THAT MEETS THE REQUIREMENTS OF THE FHA DATA SHEET. DOCUMENTATION AND THE EVIDENCE OF COMPACTED SHALL BE FURNISHED TO THE ENGINEER & OWNER.

**FINISHED FLOOR ELEVATIONS**

THE ELEVATION OF THE LOWEST FLOOR SHALL BE AT LEAST 10 INCHES ABOVE THE FINISHED GRADE OF THE SURROUNDING GROUND OR FINISHED FLOOR ELEVATION WHICH EVER IS HIGHER, WHICH SHALL BE SLOPED IN A FASHION SO AS TO DIRECT STORM WATER AWAY FROM THE STRUCTURE. PROPERTIES ADJACENT TO THE STORM WATER CONVEYANCE STRUCTURES MUST HAVE FLOOR SLAB ELEVATION OR BOTTOM OF FLOOR JOISTS A MINIMUM OF ONE FOOT ABOVE THE 100-YEAR WATER FLOW ELEVATION IN THE STRUCTURE. DRIVEWAYS SERVING HOUSES ON THE DOWNHILL SIDE OF THE STREET SHALL HAVE PROPERLY SIZED CROSS SWALE PREVENTING RUNOFF FROM ENTERING THE STRUCTURE.

DATE	REV	DESCRIPTION
APR		

DESIGNED BY: ACR  
REVIEWED BY: SSM  
DRAWN BY: ACR


**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-3600 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

OVERALL GRADING PLAN (SHEET 3 OF 3)

STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C03.12





Stage (ft msl)	Pond Depth (ft)	Cumulative Pond Depth (sf)	Surface Area (sf)	Volume (cf)	Cumulative Volume (cf)
1197.30	0.00	0.00	11	0	0
1198.00	0.70	0.70	2,301	576	576
1199.00	1.00	1.70	12,135	6,574	7,150
1200.00	1.00	2.70	29,597	20,228	27,378
1201.00	1.00	3.70	53,484	40,956	68,334
1201.43	0.43	4.13	74,379	27,367	95,702
1202.00	0.57	4.70	74,621	36,393	132,094
1203.00	1.00	5.70	86,700	80,585	212,680
1204.00	1.00	6.70	90,384	88,536	301,215
1205.00	1.00	7.70	93,932	92,152	393,367
1206.00	1.00	8.70	97,482	95,702	489,069

WQE

NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

- POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
- POND IS TO HAVE 12" TOPSOIL BOTTOM.
- THE REQUIRED WATER QUALITY VOLUME IS 95,702 CF AND THE PROVIDED WATER QUALITY VOLUME IS 95,702 CF.

BATCH DETENTION NOTES:

- OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
- VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HAND CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
- THE VALVE IS A KEYSTONE 6-INCH (100MM) BUTTERFLY VALVE MATED WITH A EPI-8 12VDC ACTUATOR. THE EPI-8 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
- CONTROLLER SYSTEM SPECIFICATIONS:
  - POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - PROGRAMMABILITY - THE CONTROLLER SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS. IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISE THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - RELIABILITY - 40,000 HOURS (4.6 YEARS) OR GREATER.
- CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC. TO ENGINEER FOR REVIEW AND APPROVAL.

DATE	DESCRIPTION
APR	

DESIGNED BY: ACR

REVIEWED BY: SSM

DRAWN BY: ACR

BGE, INC.

7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-261-3800 www.bgeinc.com  
TXPE Registration No. F-1406

CANYON RANCH UNIT 4

UN04 DETENTION AND WATER QUALITY POND PLAN

STATE OF TEXAS

STACY MULHOLLAND

146417


LICENSED PROFESSIONAL ENGINEER

11/08/2024


SHEET

C04.00





SCALE:  
HORIZ: 1"=30'  
VERT: 1"=3'



NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

1. POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
2. POND IS TO HAVE 12" TOPSOIL BOTTOM.
3. THE REQUIRED WATER QUALITY VOLUME IS 95,702 CF AND THE PROVIDED WATER QUALITY VOLUME IS 95,702 CF.

BATCH DETENTION NOTES:

1. OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
2. VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HAND CLANK ALLOWS A BUTTERFLY OVERRIDE OF THE VALVE SYSTEM.
3. THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH AN EP61 12VDC ACTUATOR. THE EP61 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
4. CONTROLLER SYSTEM SPECIFICATIONS:
  - 4.1. POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - 4.2. PROGRAMMABILITY - THE CONTROLLED SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAW-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - 4.3. EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - 4.4. ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - 4.5. SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISED THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - 4.6. MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - 4.7. RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC.TO ENGINEER FOR REVIEW AND APPROVAL.

△			
△			
△			
△			
△			
REV	DESCRIPTION	DATE	APR

DESIGNED BY: ACR

REVIEWED BY: SSM

DRAWN BY: ACR



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 [www.browngay.com](http://www.browngay.com)  
TDS Designation No. E-1045

CANYON RANCH UNIT 4


UN04 POND SECTIONS (SHEET 1 OF 3)



11/08/2024

C04.01





STATE OF TEXAS

STACY MULHOLLAND

146417

PROFESSIONAL ENGINEER




11/08/2024

SHEET

C04.02



G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C04.00 - UN04 DETENTION AND WATER QUALITY POND PLAN.dwg Layout: C04.03 UN04 POND SECTIONS (SHEET 3 OF 3) Plotted: 11/7/2024 9:39:02 AM By: Arath




NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

- POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
- POND IS TO HAVE 12" TOPSOIL BOTTOM.
- THE REQUIRED WATER QUALITY VOLUME IS 95,702 CF AND THE PROVIDED WATER QUALITY VOLUME IS 95,702 CF.

BATCH DETENTION NOTES:

- OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
- VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HAND CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
- THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH A EPI-8 12VDC ACTUATOR. THE EPI-8 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
- CONTROLLER SYSTEM SPECIFICATIONS:
  - POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - PROGRAMMABILITY - THE CONTROLLER SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISE THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
- CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC. TO ENGINEER FOR REVIEW AND APPROVAL.




DESIGNED BY:	ACR
REVIEWED BY:	SSM
DRAWN BY:	ACR
DATE	APR
REV	
DESCRIPTION	



BGE, INC.  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

UN04 POND SECTIONS (SHEET 3 OF 3)








11/08/2024  
SHEET  
C04.03



Texas Commission on Environmental Quality		UNIT 4 POND- UNIT 4 CONDITIONS	
<b>TSS Removal Calculations 04-20-2009</b>		Project Name: <b>Canyon Ranch</b> Date Prepared: <b>9/11/2024</b>	
<p>Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.</p> <p>Characters shown in red are data entry fields.</p> <p>Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.</p>			
<b>1. The Required Load Reduction for the total project:</b>		Calculations from RG-348	Pages 3-27 to 3-30
Page 3-29 Equation 3.3: $L_{M} = 27.2(A_N \times P)$			
where:	$L_{M \text{ TOTAL PROJECT}}$ = Required TSS removal resulting from the proposed development = 80% of increased load $A_N$ = Net increase in impervious area for the project $P$ = Average annual precipitation, inches		
Site Data: Determine Required Load Removal Based on the Entire Project			
County =	Comal		
Total project area included in plan *	30.69	acres	
Predevelopment impervious area within the limits of the plan *	0.00	acres	
Total post-development impervious area within the limits of the plan *	19.51	acres	
Total post-development impervious cover fraction *	0.64		
$P$	33	inches	
$L_{M \text{ TOTAL PROJECT}}$	17512	lbs.	
* The values entered in these fields should be for the total project area.			
Number of drainage basins / outfalls areas leaving the plan area =	1		
<b>2. Drainage Basin Parameters (This information should be provided for each basin):</b>			
Drainage Basin/Outfall Area No. =	Unit 4 pond		
Total drainage basin/outfall area =	12.16	acres	
Predevelopment impervious area within drainage basin/outfall area =	0.00	acres	
Post-development impervious area within drainage basin/outfall area =	7.79	acres	
Post-development impervious fraction within drainage basin/outfall area =	0.64		
$L_{M \text{ THIS BASIN}}$	6992	lbs.	
<b>3. Indicate the proposed BMP Code for this basin.</b>			
Proposed BMP =	Batch Detention		
Removal efficiency =	91	percent	
<b>4. Calculate Maximum TSS Load Removed (<math>L_R</math>) for this Drainage Basin by the selected BMP Type.</b>			
RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_C \times 34.6 + A_P \times 0.54)$			
where:	$A_C$ = Total On-Site drainage area in the BMP catchment area $A_I$ = Impervious area proposed in the BMP catchment area $A_P$ = Pervious area remaining in the BMP catchment area $L_R$ = TSS Load removed from this catchment area by the proposed BMP		
$A_C$	12.16	acres	
$A_I$	7.79	acres	
$A_P$	4.37	acres	
$L_R$	8165	lbs	
<b>5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area</b>			
Desired $L_{M \text{ THIS BASIN}}$	8125	lbs.	
$F$	1.00		
<b>6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.</b>		Calculations from RG-348	Pages 3-34 to 3-36
Rainfall Depth =	4.00	inches	
Post Development Runoff Coefficient =	0.45		
On-site Water Quality Volume =	79752	cubic feet	
Calculations from RG-348 Pages 3-36 to 3-37			
Off-site area draining to BMP =	0.00	acres	
Off-site Impervious cover draining to BMP =	0.00	acres	
Impervious fraction of off-site area =	0		
Off-site Runoff Coefficient =	0.00		
Off-site Water Quality Volume =	0	cubic feet	
Storage for Sediment =	15950		
Total Capture Volume (required water quality volume(s) x 1.20) =	95702	cubic feet	
The following sections are used to calculate the required water quality volume(s) for the selected BMP. The values for BMP Types not selected in cell C45 will show NA.			

Texas Commission on Environmental Quality		UNIT 4 VFS - CADIZ	
TSS Removal Calculations 04-20-2009		Project Name: <b>Canyon Ranch</b> Date Prepared: <b>9/11/2024</b>	
<p>Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell.</p> <p>Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.</p> <p>Characters shown in red are data entry fields.</p> <p>Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.</p>			
<b>1. The Required Load Reduction for the total project:</b>		Calculations from RG-348	Pages 3-27 to 3-30
Page 3-29 Equation 3.3: $L_M = 27.2(A_N \times P)$			
where:	$L_M$ TOTAL PROJECT = Required TSS removal resulting from the proposed development = 80% of increased load $A_N$ = Net increase in impervious area for the project $P$ = Average annual precipitation, inches		
Site Data: Determine Required Load Removal Based on the Entire Project			
		County =	
		Total project area included in plan *	<b>30.69</b> acres
		Predevelopment impervious area within the limits of the plan *	<b>0.00</b> acres
		Total post-development impervious area within the limits of the plan *	<b>19.51</b> acres
		Total post-development impervious cover fraction *	<b>0.64</b>
		P =	<b>33</b> inches
		$L_M$ TOTAL PROJECT =	<b>17512</b> lbs.
* The values entered in these fields should be for the total project area.			
		Number of drainage basins / outfalls areas leaving the plan area =	<b>1</b>
<b>2. Drainage Basin Parameters (This information should be provided for each basin):</b>			
Drainage Basin/Outfall Area No. = <b>U4 cadiz VFS</b>			
		Total drainage basin/outfall area =	<b>4.64</b> acres
		Predevelopment impervious area within drainage basin/outfall area =	<b>0.00</b> acres
		Post-development impervious area within drainage basin/outfall area =	<b>2.01</b> acres
		Post-development impervious fraction within drainage basin/outfall area =	<b>0.43</b>
		$L_M$ THIS BASIN =	<b>1804</b> lbs.
<b>3. Indicate the proposed BMP Code for this basin.</b>			
		Proposed BMP =	<b>Vegetated Filter Strips</b>
		Removal efficiency =	<b>85</b> percent
<b>4. Calculate Maximum TSS Load Removed (<math>L_R</math>) for this Drainage Basin by the selected BMP Type.</b>			
RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_N \times 34.6 + A_P \times 0.54)$			
where:	$A_C$ = Total On-Site drainage area in the BMP catchment area $A_N$ = Impervious area proposed in the BMP catchment area $A_P$ = Pervious area remaining in the BMP catchment area $L_R$ = TSS Load removed from this catchment area by the proposed BMP		
	$A_C$ =	<b>4.64</b>	acres
	$A_N$ =	<b>2.01</b>	acres
	$A_P$ =	<b>2.63</b>	acres
	$L_R$ =	<b>1991</b>	lbs.
<b>5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area</b>			
	Desired $L_M$ THIS BASIN =	<b>1456</b>	lbs.
	F =	<b>0.73</b>	




<div style="text-align: center;">  <p><b>BGE, INC.</b>  7330 San Pedro, Suite 202  San Antonio, TX 78216  TEL: 214-350-1100 <a href="http://www.bgeinc.com">www.bgeinc.com</a>  TBE Registration No. 1-1046</p> </div>	DESIGNED BY:	ACR	△
	REVIEWED BY:	SSM	△
	DRAWN BY:	ACR	△
	REV		△
	DESCRIPTION		
	DATE	APR	

CANYON RANCH UNIT 4

---

UN04 POND DETAILS




11/08/2024

SHEET

C04.04



G:\TX\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C04.10 - UN05 DETENTION AND WATER QUALITY POND PLAN.dwg Layout: C04.10 UN05 DETENTION AND WATER QUALITY POND PLAN Plotted: 11/7/2024 9:40:30 AM By: Arath



Stage (ft msl)	Pond Depth	Cumulative Pond Depth	Surface Area	Volume	Cumulative
(Elevation)	(ft)	(ft)	(sf)	(cf)	Volume (cf)
1190.30	0.00	0.00	36	0	0
1191.00	0.70	0.70	8,908	2,218	2,218
1192.00	1.00	1.70	44,678	24,512	26,730
1193.00	1.00	2.70	73,279	58,392	85,122
1194.00	1.00	3.70	77,148	75,205	160,327
1195.00	1.00	4.70	80,915	79,023	239,350
1196.00	1.00	5.70	84,710	82,805	322,155
1197.00	1.00	6.70	88,533	86,614	408,769
1198.00	1.00	7.70	92,384	90,451	499,221
1199.00	1.00	8.70	96,267	94,319	593,540
1200.00	1.00	9.70	100,191	98,222	691,762
1201.00	1.00	10.70	118,760	109,344	801,106



NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

- POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
- POND IS TO HAVE 12" TOPSOIL BOTTOM.
- THE REQUIRED WATER QUALITY VOLUME IS 188,691 CF AND THE PROVIDED WATER QUALITY VOLUME IS 239,350 CF.

BATCH DETENTION NOTES:

- OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
- VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HAND CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
- THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH A EPI-8 12VDC ACTUATOR. THE EPI-8 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
- CONTROLLER SYSTEM SPECIFICATIONS:
  - POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - PROGRAMMABILITY - THE CONTROLLED SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISE THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE. TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
- CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC. TO ENGINEER FOR REVIEW AND APPROVAL.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: ACR

REVIEWED BY: SSM

DRAWN BY: ACR

BGE, INC.

7330 San Pedro, Suite 202

San Antonio, TX 78216

TEL: 210-581-3680 www.bgeenergy.com

TXPE Registration No. F-1046

CANYON RANCH UNIT 4

UN05 DETENTION AND WATER QUALITY POND PLAN

STATE OF TEXAS

STACY MULHOLLAND

146417


REGISTERED PROFESSIONAL ENGINEER

11/08/2024

SHEET

C04.10






NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

1. POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
2. POND IS TO HAVE 12" TOPSOIL BOTTOM.
3. THE REQUIRED WATER QUALITY VOLUME IS 188,691 CF AND THE PROVIDED WATER QUALITY VOLUME IS 239,350 CF.


BATCH DETENTION NOTES

1. OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
2. VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMA112VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. 3. MECHANICAL HANG CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
3. THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH A EP616 12VDC ACTUATOR. THE EP616 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
4. CONTROLLER SYSTEM SPECIFICATIONS:
  - 4.1. POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - 4.2. PROGRAMMABILITY - THE CONTROLLED SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - 4.3. EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - 4.4. ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
5. SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISED THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
6. MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
7. RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC. TO ENGINEER FOR REVIEW AND APPROVAL.

<div style="text-align: center;">  <p><b>BGE INC.</b>  7330 San Pedro, Suite 202  San Antonio, TX 78216  TEL: 210-581-3600 www.browning.com  TBEPE Registration No. F-1046</p> </div>	DESIGNED BY:	ACR	Δ		
	REVIEWED BY:	SSM	Δ		
	DRAWN BY:	ACR	Δ		
			Δ		
			Δ		
		REV		DESCRIPTION	APR



CANYON RANCH UNIT 4

UN05 POND SECTIONS (SHEET 1 OF 3)



SHEET  
C04.11







NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.

NOTES:

1. POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
2. POND IS TO HAVE 12" TOPSOIL BOTTOM.
3. THE REQUIRED WATER QUALITY VOLUME IS 188,691 CF AND THE PROVIDED WATER QUALITY VOLUME IS 239,350 CF.

BATCH DETENTION NOTES


1. OVERVIEW: THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
2. VALVE/ACTUATOR: THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BY MOVING THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HANG CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
3. THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH A EP46 12VDC ACTUATOR. THE EP46 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHOT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
4. CONTROLLER SYSTEM SPECIFICATIONS:
  - 4.1. POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - 4.2. PROGRAMMABILITY - THE CONTROLLED SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - 4.3. EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - 4.4. ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - 4.5. SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISE THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - 4.6. MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROLLER PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - 4.7. RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
5. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC.TO ENGINEER FOR REVIEW AND APPROVAL.

	<p>CANYON RANCH UNIT 4</p> <p>UN05 POND SECTIONS (SHEET 2 OF 3)</p>	 <p><b>BGE, INC.</b>  7330 San Pedro, Suite 202  San Antonio, TX 78216  Tel: 210-350-0000  www.bgeinc.com  TBEPE Registration No. E-1046</p>		<input type="checkbox"/>	<input type="checkbox"/>
		DESIGNED BY:	ACR	<input type="checkbox"/>	<input type="checkbox"/>
		REVIEWED BY:	SSM	<input type="checkbox"/>	<input type="checkbox"/>
		DRAWN BY:	ACR	<input type="checkbox"/>	<input type="checkbox"/>
			REV	DESCRIPTION	DATE
SHEET					APR
C04.12					

G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C04-10 - UN05 DETENTION AND WATER QUALITY POND PLAN.dwg Layout: C04.13 UN05 POND SECTIONS (SHEET 3 OF 3) Plotted: 11/7/2024 9:41:00 AM By: Arath


CR - UN05 - POND SECT D-D  
POND ACCESS DRIVE

SCALE:  
HORIZ. 1"=30'  
VERT. 1"=3'




CR - UN05 - POND SECT E-E  
POND ACCESS DRIVE

SCALE:  
HORIZ. 1"=30'  
VERT. 1"=3'



CR - UN05 - WQ OUTFALL

SCALE:  
HORIZ. 1"=30'  
VERT. 1"=3'




NOTE: UPON COMPLETION OF THE PROPOSED SITE IMPROVEMENTS, AND PRIOR TO THE RELEASE OF THE CERTIFICATE OF ACCEPTANCE OR OCCUPANCY BY THE PERMIT CENTER, THE DESIGN ENGINEER SHALL CERTIFY IN WRITING THAT THE PROPOSED DETENTION FACILITY, FILTRATION FACILITIES AND/OR WATER QUALITY FACILITIES WERE CONSTRUCTED IN CONFORMANCE WITH THE APPROVED PLANS.



NOTES:

- POND SHALL MAINTAINED BY CANYON RANCH MUD OF COMAL COUNTY.
- POND IS TO HAVE 12" TOPSOIL BOTTOM.
- THE REQUIRED WATER QUALITY VOLUME IS 188,691 CF AND THE PROVIDED WATER QUALITY VOLUME IS 239,350 CF.

BATCH DETENTION NOTES:





- OVERVIEW - THE BASIN IS TYPICALLY FILLED QUICKLY BY STORMWATER CONVEYED THROUGH A STORM DRAIN, MAKING THE INFLOW TIME RELATIVELY SHORT. THE RESIDENCE TIME OF THE STORMWATER IS 12 HOURS AND IS CONTROLLED BY THE CONTROL VALVE (NORMALLY SHUT OFF) AND ACTUATOR INSTALLED ON THE OUTLET STRUCTURE. THE CONTROL VALVE OPENS ONCE THE DESIRED RESIDENCE TIME IS ACHIEVED AFTER A STORM EVENT. THE TREATED WATER IS RELEASED SLOWLY OVER A TIME OF 24 TO 48 HOURS.
- VALVE/ACTUATOR - THE VALVE/ACTUATOR ASSEMBLY CONSISTS OF A BUTTERFLY VALVE WITH A SMALL 12VDC ACTUATOR. THE VALVE IS A QUARTER TURN VALVE. THE ACTUATOR OPERATES THE VALVE BETWEEN THE FULL OPEN AND FULL CLOSED POSITIONS. A MECHANICAL HAND CLANK ALLOWS A PHYSICAL OVERRIDE OF THE VALVE SYSTEM.
- THE VALVE IS A KEYSTONE 6-INCH(100MM) BUTTERFLY VALVE MATED WITH A EPI-8 12VDC ACTUATOR. THE EPI-8 ACTUATOR REQUIRES AN OPEN OR CLOSE SIGNAL OF 10 SECONDS. THE ACTUATOR HAS LIMIT SWITCHES THAT DETECT END OF TRAVEL AND SHUT OFF THE INCOMING OPEN OR CLOSE SIGNAL TO THE ACTUATOR ONCE THE VALVES REACHES THE FULL OPEN OR CLOSED POSITION. OVER TORQUE SENSORS WILL SHUT DOWN THE ACTUATOR IN THE EVENT OF AN OVER TORQUE SITUATION.
- CONTROLLER SYSTEM SPECIFICATIONS:
  - POWER - THE CONTROLLER SHALL BE POWERED BY A SHIELD-CONTAINED RENEWABLE POWER SOURCE (SUCH AS SOLAR POWER) IF ELECTRICAL POWER IS NOT AVAILABLE. A SINGLE SUPPLY VOLTAGE FOR ALL COMPONENTS IS DESIRABLE.
  - PROGRAMMABILITY - THE CONTROLLER SHALL BE PROGRAMMABLE. IT SHALL BE POSSIBLE TO UPDATE PROGRAMS IN THE FIELD. THE DETENTION TIME AND DRAIN-DOWN TIME SHALL BE ADJUSTABLE IN HOURS FROM 0 HOURS TO 72 HOURS.
  - EVENT SENSING - THE CONTROLLER SHALL BE ABLE TO SENSE THE BEGINNING OF A STORM (WATER FILLING THE BASIN), AND THE END OF A STORM (WATER HAS DRAINED FROM THE BASIN).
  - ENVIRONMENT - THE CONTROLLER SHALL OPERATE IN TEMPERATURES FROM 0 DEGREES CELSIUS TO 55 DEGREES CELSIUS, IN HUMIDITY FROM 10% TO 90% (NON-CONDENSING). THE CONTROLLER SHALL OPERATE DURING PERIODS OF RAINFALL.
  - SAFETY/SECURITY - THE SYSTEM COMPONENTS SHALL BE LOCKED IN ENCLOSURE TO PREVENT ACCIDENTAL CONTACT THAT COULD COMPROMISED THE FUNCTION OF THE APPARATUS OR CAUSE INJURY.
  - MAINTENANCE - THE CONTROLLER SHALL REQUIRE MINIMAL PERIODIC MAINTENANCE TO CONTROL THE PROGRAM SHALL BE FIELD UPGRADEABLE. THE ABILITY TO MANUALLY OPERATE THE VALVE SHALL BE PROVIDED.
  - RELIABILITY - 40,000 HOURS(4.6 YEARS) OR GREATER.
- CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND DESIGN OF SENSOR, AUTOMATIC VALVE, CONTROLLER, ETC. TO ENGINEER FOR REVIEW AND APPROVAL.



DESIGNED BY:	ACR
REVIEWED BY:	SSM
DRAWN BY:	ACR
 BGE, INC. 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 210-581-3600 www.bgeinc.com EPA Registration No. F-1040	
 STACY MULHOLLAND 146417 PROFESSIONAL ENGINEER 11/08/2024	
DATE	APR





Texas Commission on Environmental Quality		UNIT 5 POND - UNIT 1 CONDITIONS	
TSS Removal Calculations 04-20-2009		Project Name: <b>Canyon Ranch</b> Date Prepared: <b>9/11/2024</b>	
<p>Additional information is provided for cells with a red triangle in the upper right corner. Place the cursor over the cell. Text shown in blue indicate location of instructions in the Technical Guidance Manual - RG-348.</p> <p>Characters shown in red are data entry fields.</p> <p>Characters shown in black (Bold) are calculated fields. Changes to these fields will remove the equations used in the spreadsheet.</p>			
<b>1. The Required Load Reduction for the total project:</b>		Calculations from RG-348	Pages 3-27 to 3-30
<p>Page 3-29 Equation 3.3: <math>L_M = 27.2(A_N \times P)</math></p> <p>where: <math>L_{M \text{ TOTAL PROJECT}}</math> = Required TSS removal resulting from the proposed development = 80% of increased load</p> <p><math>A_N</math> = Net increase in impervious area for the project</p> <p><math>P</math> = Average annual precipitation, inches</p>			
<p>Site Data: Determine Required Load Removal Based on the Entire Project</p> <p>County = <b>Comal</b></p> <p>Total project area included in plan = <b>30.69</b> acres</p> <p>Predevelopment impervious area within the limits of the plan = <b>0.00</b> acres</p> <p>Total post-development impervious area within the limits of the plan = <b>19.51</b> acres</p> <p>Total post-development impervious cover fraction = <b>0.64</b></p> <p><math>P</math> = <b>33</b> inches</p>			
$L_{M \text{ TOTAL PROJECT}}$ = <b>17512</b> lbs.			
* The values entered in these fields should be for the total project area.			
Number of drainage basins / outfalls areas leaving the plan area = <b>1</b>			
<b>2. Drainage Basin Parameters (This information should be provided for each basin):</b>			
Drainage Basin/Outfall Area No. = <b>unit 5 pond</b>			
Total drainage basin/outfall area = <b>11.59</b> acres			
Predevelopment impervious area within drainage basin/outfall area = <b>0.00</b> acres			
Post-development impervious area within drainage basin/outfall area = <b>7.74</b> acres			
Post-development impervious fraction within drainage basin/outfall area = <b>0.67</b>			
$L_{M \text{ THIS BASIN}}$ = <b>6947</b> lbs.			
<b>3. Indicate the proposed BMP Code for this basin.</b>			
Proposed BMP = <b>Batch Detention</b>			
Removal efficiency = <b>91</b> percent			
<b>4. Calculate Maximum TSS Load Removed (<math>L_R</math>) for this Drainage Basin by the selected BMP Type.</b>			
RG-348 Page 3-33 Equation 3.7: $L_R = (\text{BMP efficiency}) \times P \times (A_N \times 34.6 + A_P \times 0.54)$			
where:		<p><math>A_C</math> = Total On-Site drainage area in the BMP catchment area</p> <p><math>A_I</math> = Impervious area proposed in the BMP catchment area</p> <p><math>A_P</math> = Pervious area remaining in the BMP catchment area</p> <p><math>L_R</math> = TSS Load removed from this catchment area by the proposed BMP</p>	
$A_C$ = <b>11.59</b> acres			
$A_I$ = <b>7.74</b> acres			
$A_P$ = <b>3.85</b> acres			
$L_R$ = <b>8105</b> lbs			
<b>5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area</b>			
Desired $L_{M \text{ THIS BASIN}}$ = <b>8065</b> lbs.			
$F$ = <b>1.00</b>			
<b>6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.</b>		Calculations from RG-348	Pages 3-34 to 3-36
Rainfall Depth = <b>4.00</b> inches			
Post Development Runoff Coefficient = <b>0.48</b>			
On-site Water Quality Volume = <b>79954</b> cubic feet			
		Calculations from RG-348	Pages 3-36 to 3-37
Off-site area draining to BMP = <b>0.00</b> acres			
Off-site Impervious cover draining to BMP = <b>0.00</b> acres			
Impervious fraction of off-site area = <b>0</b>			
Off-site Runoff Coefficient = <b>0.00</b>			
Off-site Water Quality Volume = <b>0</b> cubic feet			
Storage for Sediment = <b>15991</b>			
Total Capture Volume (required water quality volume(s) $\times 1.20$ ) = <b>95945</b> cubic feet			
<p>The following sections are used to calculate the required water quality volume(s) for the selected BMP.</p> <p>The values for BMP Types not selected in cell C45 will show NA.</p>			





MATCH LINE - SEE SHEET C06.01



LEGEND

- PROPERTY BOUNDARY
- UNIT BOUNDARY
- EASEMENT
- EXISTING MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- PROPOSED MAJOR CONTOUR
- PROPOSED STORM DRAIN w/ MANHOLE
- PROPOSED CURB INLET
- PROPOSED WASTEWATER LINE
- PROPOSED WATER LINE
- EXISTING FORCE MAIN
- PROPOSED ELECTRIC
- PROPOSED GAS LINE
- PROPOSED WASTEWATER SERVICES
- PROPOSED WATER SERVICES
- UTILITY CROSSING
- PROPOSED SWALE FLOWLINE
- JURISDICTIONAL WATERS

\* ALL WATER/WASTEWATER SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO DETAILS SHOWN IN THIS PLAN SET.

NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

DATE	REV	DESCRIPTION
APR		

DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	JDC

**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-281-3600 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

STORM DRAIN COLLECTION PLAN

(SHEET 1 OF 3)


STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER

11/08/2024

SHEET  
C06.00



G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.00 - STORM DRAIN COLLECTION PLAN.dwg Layout: C06.01 STORM DRAIN COLLECTION PLAN (SHEET 2 OF 3) Plotted: 11/7/2024 10:42:38 AM By: Mhernandez



LEGEND	
	PROPERTY BOUNDARY
	UNIT BOUNDARY
	EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED MAJOR CONTOUR
	PROPOSED STORM DRAIN w/ MANHOLE
	PROPOSED CURB INLET
	PROPOSED WASTEWATER LINE
	PROPOSED WATER LINE
	EXISTING FORCE MAIN
	PROPOSED ELECTRIC
	PROPOSED GAS LINE
	PROPOSED WASTEWATER SERVICES
	PROPOSED WATER SERVICES
	UTILITY CROSSING
	PROPOSED SWALE FLOWLINE
	JURISDICTIONAL WATERS

\* ALL WATER/WASTEWATER SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO DETAILS SHOWN IN THIS PLAN SET.

NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

DATE	REV	DESCRIPTION
APR		

DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	JDC

**BGE**  
BGE, INC.  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-481-3800 www.bgeinc.com  
TXPE Registration No. F-1046



CANYON RANCH UNIT 4

STORM DRAIN COLLECTION PLAN  
(SHEET 2 OF 3)

11/08/2024  
SHEET  
C06.01



G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.00 - STORM DRAIN COLLECTION PLAN.dwg Layout: C06.02 STORM DRAIN COLLECTION PLAN (SHEET 3 OF 3) Plotted: 11/7/2024 10:42:46 AM By: Mhernandez




- \* ALL WATER/WASTEWATER SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO DETAILS SHOWN IN THIS PLAN SET.
- NOTES:**
1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
  4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
  5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION**  
CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

CANYON RANCH UNIT 4		STORM DRAIN COLLECTION PLAN (SHEET 3 OF 3)	
DESIGNED BY:	LNH	DATE	APR
REVIEWED BY:	SSM	REV	DESCRIPTION
DRAWN BY:	JDC		

**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 www.bgeenergy.com  
TDE Registration No. F-1046



11/08/2024  
SHEET  
C06.02






STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED  
PROFESSIONAL ENGINEER  
11/08/2024





PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRMA-E	9.06	11.99	2.42
STRMA-F	9.23	11.98	0.67
STRMA-G	9.23	12.11	1.62

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM A-E	6.33	10.81	1.92
STRM A-F	6.45	10.89	0.55
STRM A-G	6.46	11.01	1.31



- NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OFFSHORE TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.



## UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") THICK. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS T-99-13.1E, T-99-14.1E, T-99-15.1E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER. THE TESTS SHALL BE CONDUCTED BY A QUALIFIED FIELD INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

## TRENCH EXCAVATION SAFETY PROTECTION


CONTRACTOR AND/OR CONTRACTORS INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO DETERMINE CONTRACTORS' TRENCH EXCAVATION PROGRAMS AND PROCEDURES AND/OR PREPARED FOR THE PROJECTS. THE PROGRAMS DESCRIBED IN THE CONTRACT DOCUMENTS, THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTORS INDEPENDENTLY RETAINED EMPLOYEE OR CONSULTANT SHALL DEVELOP AND IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.





PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM B-A	38.37	9.54	2.02
STRM B-B	38.39	7.82	2.98
STRM B-C	29.28	5.97	3.69
STRM B-D	20.94	15.27	1.09

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM B-A	26.61	8.92	1.64
STRM B-B	26.62	8.88	2.36
STRM B-C	20.20	8.32	2.69
STRM B-D	14.33	14.15	0.84



- NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20' SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

### UTILITY TRENCH COMPACTION


ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS T-113-E, T-114-E, T-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER. THE CITY OF SAN MARCOS STREET INSPECTOR AT A MINIMUM TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING, THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

## TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE TRENCH WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEM, PROGRAMS AND PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SUBCONSULTANT SHALL BE RESPONSIBLE FOR THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.





G:\TXC\Projects\San Antonio Projects\17278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.05 - STORM DRAIN LINE B PLAN AND PROFILE.dwg Layout: STORM DRAIN LINE B PLAN AND PROFILE STA 3+50 TO END Plotted: 11/7/2024 10:46:11 AM By: Mhernandez




PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM B-D	20.94	15.27	1.09
STRM B-E	9.12	5.16	3.12
STRM B-F	9.20	11.69	1.66
STRM B-G	9.25	12.20	0.67

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM B-D	14.33	14.15	0.84
STRM B-E	6.15	3.48	2.21
STRM B-F	6.21	10.53	0.55
STRM B-G	6.25	10.98	0.54



0 20' 40' 80'  
SCALE: 1" = 40'



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH  
REVIEWED BY: SSM  
DRAWN BY: JDC




**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-5360 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4



STORM DRAIN LINE B PLAN AND PROFILE  
STA 3+50 TO END

STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C06.06









1. COMPLETION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.



UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTOR TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGNING/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION STEPS WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTORS' TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.






PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM D-A	10.12	10.89	2.48
STRM D-B	10.12	10.89	1.72
STRM D-C	8.33	10.37	1.87


PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM D-A	7.07	9.93	1.68
STRM D-B	7.07	9.93	1.38
STRM D-C	5.83	9.42	1.38



- NOTES:**
1. REPAIRMENT OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  2. CONTRACTOR TO DEFLECT STORM SEWER -1 DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
  4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE COMPLETED.
  5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTATION**
- ALL UTILITY TRENCH COMPACTATION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") THICK. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL, HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION**
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGNER/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION STEPS WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS, SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.






G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.10 - STORM DRAIN LINE E PLAN AND PROFILE.dwg Layout: STORM DRAIN LINE E PLAN AND PROFILE STA 1+00 TO 5+00 Plotted: 11/7/2024 10:51:49 AM By: Mhernandez



PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM E-A	216.33	13.60	6.03
STRM E-B	216.87	13.64	4.14
STRM E-C	205.96	14.01	4.11
STRM E-D	207.23	13.99	3.96
STRM E-E	208.55	13.94	4.01

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM E-A	150.36	9.45	5.46
STRM E-B	150.74	13.63	3.17
STRM E-C	143.20	13.49	3.01
STRM E-D	144.12	13.51	2.96
STRM E-E	145.08	13.52	2.97



NOTES:


- COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
- CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
- CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
- CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
- CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH  
REVIEWED BY: SSM  
DRAWN BY: JDC



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3680 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

STORM DRAIN LINE E PLAN AND PROFILE  
STA 1+00 TO 5+00



STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C06.10





- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SUBCONSULTANT SHALL BE RESPONSIBLE FOR THE DEVELOPMENT AND IMPLEMENTATION OF OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.







1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

### TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROGRAM. PROJECT DESIGN, PROJECT SPECIFICATIONS, AND PROJECT DOCUMENTS IN THE CONTRACT DOCUMENTS, THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL DEVELOP AND IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.











PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM F-A	73.50	10.40	4.79
STRM F-B	73.84	10.45	5.98
STRM F-C	62.79	8.88	7.20
STRM F-D	56.08	7.93	7.69

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM F-A	50.67	11.52	3.40
STRM F-B	50.88	11.52	3.43
STRM F-C	43.09	11.09	3.51
STRM F-D	38.25	10.77	2.92




- NOTES:
1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  2. CONTRACTOR TO DEFLECT STREET SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  3. CONTRACTOR TO CONNECT PROPOSED STREET SEWER OUTFALL TO POND.
  4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STREET WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
  5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTION
- ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. ALL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION STEPS WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.









- 
- STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED  
PROFESSIONAL ENGINEER  
11/08/2024





PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM G-A	16.96	9.60	1.97
STRM G-B	16.98	9.61	3.13
STRM G-C	17.00	9.62	4.50

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM G-A	11.81	6.68	1.31
STRM G-B	11.83	6.69	1.93
STRM G-C	11.84	6.70	2.50



NOTES:

- COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
- CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
- CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
- CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
- CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

DATE	REV	DESCRIPTION
APR		

DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	JDC

**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-3600 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4



STORM DRAIN LINE G PLAN AND PROFILE

11/08/2024


SHEET

C06.15











PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM I-A	25.22	13.25	1.37
STRM I-B	25.30	13.27	2.63
STRM I-C	14.45	11.53	2.64
STRM I-D	14.63	10.23	1.13
STRM I-E	3.79	7.39	2.25

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM I-A	17.41	12.11	1.09
STRM I-B	17.47	12.12	2.05
STRM I-C	9.96	10.42	2.06
STRM I-D	10.09	9.54	0.87
STRM I-E	2.63	6.66	1.72



### NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.


UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE COMPACTED TO A MINIMUM OF 12" TO EXCEED 12" LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEST-113-E, TEST-114-E, TEST-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100' FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS WITH THE FOLLOWING: PROPER LOGGING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

### TRENCH EXCAVATION SAFETY PROTECTION





CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGNER/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES AND CONDITIONS IN ORDER TO IMPLEMENT CONTROLS FOR TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY PROFESSIONAL SHALL PRESENT AND/OR REVIEW THE PRESENCE AND ACTIVITIES WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.





PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM I-E	3.79	7.39	2.25
STRM I-F	3.82	7.41	0.96
STRM I-G	3.85	9.80	1.04
STRM I-H	3.86	11.58	0.38
STRM I-I	3.86	11.59	0.43
STRM I-J	3.87	9.96	0.42

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM I-E	2.63	6.66	1.72
STRM I-F	2.65	6.68	0.79
STRM I-G	2.67	8.82	0.85
STRM I-H	2.68	10.41	0.31
STRM I-I	2.68	10.42	0.34
STRM I-J	2.69	8.96	0.34



NOTES:


- COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
- CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
- CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
- CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
- CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

**TRENCH TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

**TRENCH EXCAVATION SAFETY PROTECTION**



CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

















PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRMJ-A	20.03	6.38	3.12
STRMJ-B	20.16	12.50	3.15

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRMJ-A	13.33	11.53	2.36
STRMJ-B	13.43	11.24	2.04




- NOTES:**
1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
  4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
  5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTION**
- ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") THICK. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION**
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION STEPS WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS, SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.





PIPE IDENTIFICATION	FLOW 100 (CFS)	VELOCITY 100 (FPS)	DEPTH 100 (FT)
STRM LAT A1	5.94	1.89	4.41
STRM LAT A2	4.54	2.57	2.05
STRM LAT A3	13.63	7.71	1.92
STRM LAT B1	9.71	5.49	2.69
STRM LAT B2-A	8.60	7.01	1.03
STRM LAT B2-B	8.65	7.02	1.55
STRM LAT B2-C	8.66	7.02	1.56
STRM LAT B2-D	8.67	4.90	1.77
STRM LAT B3	12.02	6.80	3.12
STRM LAT C2-A	12.46	7.05	3.15
STRM LAT C2-B	3.21	8.62	1.51
STRM LAT C4-A	11.24	3.58	3.67
STRM LAT C4-B	11.26	3.58	3.21
STRM LAT D1	1.89	8.40	1.87
STRM LAT E1-A	13.47	16.78	0.94
STRM LAT E1-B	13.49	16.74	2.11
STRM LAT E2-A	13.24	7.49	5.10
STRM LAT E2-B	7.78	4.40	3.26
STRM LAT E4	10.37	5.87	3.32

PIPE IDENTIFICATION	FLOW 25 (CFS)	VELOCITY 25 (FPS)	DEPTH 25 (FT)
STRM LAT A1	4.07	7.04	3.38
STRM LAT A2	3.17	4.04	0.68
STRM LAT A3	9.55	9.49	1.42
STRM LAT B1	6.78	14.54	1.69
STRM LAT B2-A	6.06	6.48	0.83
STRM LAT B2-B	6.10	6.49	1.26
STRM LAT B2-C	6.11	6.50	1.26
STRM LAT B2-D	6.11	6.50	1.30
STRM LAT B3	8.35	17.54	2.21
STRM LAT C2-A	8.76	18.23	2.11
STRM LAT C2-B	2.24	7.77	0.65
STRM LAT C4-A	7.88	2.51	2.66
STRM LAT C4-B	7.88	16.14	2.12
STRM LAT D1	1.32	7.55	1.38
STRM LAT E1-A	9.28	15.19	0.75
STRM LAT E1-B	9.29	15.16	1.63
STRM LAT E2-A	9.32	19.69	1.43
STRM LAT E2-B	5.49	7.25	0.68
STRM LAT E4	7.31	7.49	1.20






- NOTES:
1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
  4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
  5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTION
- ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT, UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.







G:\TXC\Projects\San Antonio Projects\17278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C06.30 - INTERCEPTOR CHANNEL C1 PLAN AND PROFILE.dwg Layout: C06.30 INTERCEPTOR CHANNEL C1 PLAN AND PROFILE STA 0+50 TO 4+50 Plotted: 11/7/2024 11:04:14 AM By: Arath




NOTES:

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

**TRENCH EXCAVATION SAFETY PROTECTION**

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH

REVIEWED BY: SSM

DRAWN BY: JDC

**BGE, INC.**

7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-5380 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

INTERCEPTOR CHANNEL C1 PLAN AND PROFILE STA 0+50 TO 4+50




STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER

11/08/2024

SHEET  
C06.30



G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.30 - INTERCEPTOR CHANNEL C1 PLAN AND PROFILE.dwg Layout: C06.31 INTERCEPTOR CHANNEL C1 PLAN AND PROFILE STA 4+50 TO END Plotted: 11/7/2024 11:04:27 AM By: Arath




**NOTES:**

1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

**TRENCH EXCAVATION SAFETY PROTECTION**

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH  
REVIEWED BY: SSM  
DRAWN BY: JDC



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4  
INTERCEPTOR CHANNEL C1 PLAN AND  
PROFILE STA 4+50 TO END

STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C06.31



G:\TXC\Projects\San Antonio Projects\17278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C06.32 - INTERCEPTOR CHANNEL E1 PLAN AND PROFILE.dwg Layout: C06.32 INTERCEPTOR CHANNEL E1 PLAN AND PROFILE Plotted: 11/7/2024 11:05:58 AM By: Mhennandez



0 20' 40' 80'  
SCALE: 1" = 40'

LEGEND

	PROPERTY BOUNDARY
	UNIT BOUNDARY
	EASEMENT
	EXISTING MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED MAJOR CONTOUR
	PROPOSED STORM DRAIN w/ MANHOLE
	PROPOSED CURB INLET
	PROPOSED WASTEWATER LINE
	PROPOSED WATER LINE
	EXISTING FORCE MAIN
	PROPOSED ELECTRIC
	PROPOSED GAS LINE
	PROPOSED WASTEWATER SERVICES
	PROPOSED WATER SERVICES
	UTILITY CROSSING
	PROPOSED SWALE FLOWLINE
	JURISDICTIONAL WATERS

PROFILE LEGEND

	PROPOSED STORM PIPE
	PROPOSED GROUND
	PROPOSED SUBGRADE
	EXISTING GROUND
	25/100 YEAR HGL

\* ALL WATER/WASTEWATER SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO DETAILS SHOWN IN THIS PLAN SET.

NOTES:


1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



TRAPEZOIDAL CHANNEL  
TYPICAL SECTION

CHANNEL E1  
CAPACITY VERIFICATION  
SECTION "AA"  
 $Q_{25YR} = 15.4 \text{ cfs}$   
 $n = 0.030$   
 $S = 0.25\%$   
 $D_n = 0.36 \text{ ft}$   
 $V_n = 1.87 \text{ fps}$   
 $D = 1.25 \text{ ft}$   
 $BW = 7.00 \text{ ft}$

CHANNEL E1  
CAPACITY VERIFICATION  
SECTION "BB" SECTION "CC"  
 $Q_{25YR} = 24.3 \text{ cfs}$   
 $n = 0.030$   
 $S = 5.00\%$   
 $D_n = 0.48 \text{ ft}$   
 $V_n = 6.00 \text{ fps}$   
 $D = 1.25 \text{ ft}$   
 $BW = 7.00 \text{ ft}$

DATE	REV	DESCRIPTION
APR		

DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	JDC



BGE, INC.  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-360-3600 www.bgeenergy.com  
TXEPE Registration No. F-1040

CANYON RANCH UNIT 4

INTERCEPTOR CHANNEL E1 PLAN AND  
PROFILE






11/08/2024

SHEET

C06.32






- NOTES:



1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL. IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVING SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE COMPACTED TO A MINIMUM OF 95% DENSITY. THE TOP 4 INCHES (12 CM) OF EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS T-99, T-113-E, T-114-E, T-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCO STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE REQUIRED EVERY 100' OF LENGTH. HIGH FLOW COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCO WITH ALL TESTING DATA, INCLUDING TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

## TRENCH EXCAVATION SAFETY PROTECTION






CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION STEPS WITHIN THE WORK AREA, IN ORDER TO IMPLEMENT THE CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEM, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL TAKE THE FOLLOWING ACTIONS TO COMPLY WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.




 11/08/2024	SHEET C06.33	CANYON RANCH UNIT 4		 <b>BGE, INC.</b> 7392 San Pedro, Suite 202 San Pedro, CA 90731 TEL: 210-581-3800 www.bgeinc.com TBPE Registration No. F-1046				
		INTERCEPTOR CHANNEL H1 PLAN AND PROFILE		△	REV	DESCRIPTION	DATE	APP
				△				
				△				
				△				
				DESIGNED BY:	LNH			
				REVIEWED BY:	SSM			
				DRAWN BY:	JDC			



G:\TXC\Projects\San Antonio Projects\12728-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C06.34 - INTERCEPTOR CHANNEL I1 PLAN AND PROFILE.dwg Layout: C06.34 INTERCEPTOR CHANNEL I1 PLAN AND PROFILE Plotted: 11/7/2024 11:08:52 AM By: Mhermandez



- NOTES:
- COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
  - CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
  - CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
  - CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
  - CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.
- UTILITY TRENCH COMPACTION
- ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.
- TRENCH EXCAVATION SAFETY PROTECTION
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY: LNH  
REVIEWED BY: SSM  
DRAWN BY: JDC


**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 www.bgeinc.com  
TXPE Registration No. F-1040

CANYON RANCH UNIT 4  
INTERCEPTOR CHANNEL I1 PLAN AND PROFILE


STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C06.34



G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.35 - INTERCEPTOR CHANNEL J1 PLAN AND PROFILE.dwg Layout: C06.35 INTERCEPTOR CHANNEL J1 PLAN AND PROFILE.dwg Plotted: 11/7/2024 11:10:21 AM By: Mhernandez



UN04 - SWALE J1



0 20' 40' 80'

SCALE: 1" = 40'

LEGEND

---	PROPERTY BOUNDARY
- - - -	UNIT BOUNDARY
- - - -	EASEMENT
- - - -	EXISTING MINOR CONTOUR
- - - -	EXISTING MAJOR CONTOUR
- - - -	PROPOSED MINOR CONTOUR
- - - -	PROPOSED MAJOR CONTOUR
- - - -	PROPOSED STORM DRAIN w/ MANHOLE
- - - -	PROPOSED CURB INLET
- - - -	PROPOSED WASTEWATER LINE
- - - -	PROPOSED WATER LINE
- - - -	EXISTING FORCE MAIN
- - - -	PROPOSED ELECTRIC
- - - -	PROPOSED GAS LINE
- - - -	* PROPOSED WASTEWATER SERVICES
- - - -	* PROPOSED WATER SERVICES
- - - -	UTILITY CROSSING
- - - -	PROPOSED SWALE FLOWLINE
- - - -	JURISDICTIONAL WATERS

PROFILE LEGEND

---	PROPOSED STORM PIPE
---	PROPOSED GROUND
---	PROPOSED SUBGRADE
---	EXISTING GROUND
---	25/100 YEAR HGL
*	ALL WATER/WASTEWATER SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO DETAILS SHOWN IN THIS PLAN SET.

NOTES:


1. COMPACTION OF TRENCH UNDER PROPOSED PAVING SHOULD USE APPROPRIATE REPLACEMENT GRANULAR MATERIAL IF UNSUITABLE SOIL IS EXCAVATED FROM TRENCH.
2. CONTRACTOR TO DEFLECT STORM SEWER 1-DEGREE EACH 20 FT SEGMENT AS REQUIRED.
3. CONTRACTOR TO CONNECT PROPOSED STORM SEWER OUTFALL TO POND.
4. CONTRACTOR TO ENSURE THAT ALL OFF-SITE STORM WATER RUNOFF IS BYPASSED UNTIL PROPOSED DRAINAGE IMPROVEMENTS ARE CONSTRUCTED.
5. CONTRACTOR TO ADJUST MANHOLE RIM ELEVATIONS AS NEEDED TO ENSURE FLUSHNESS WITH PROPOSED GRADING.

UTILITY TRENCH COMPACTION

ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE CITY OF SAN MARCOS STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE CITY OF SAN MARCOS STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.



DATE	REV	DESCRIPTION
APR		

DESIGNED BY:	LNH
REVIEWED BY:	SSM
DRAWN BY:	JDC

**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-3680 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

INTERCEPTOR CHANNEL J1 PLAN AND PROFILE


STACY MULHOLLAND  
146417  
PROFESSIONAL ENGINEER  
11/08/2024

SHEET

C06.35


G:\TXC\Projects\San Antonio Projects\7278-00 - Canyon Ranch\118 - Unit 4\03\_CADD\01\_Shts\C06.50 - STREET AND DRAINAGE DETAILS.dwg Layout: STREET AND DRAINAGE DETAILS (SHEET 1 OF 6) Plotted: 11/7/2024 12:09:46 PM By: Lhuck



SUBSURFACE EXPLORATION AND PAVEMENT ANALYSIS  
PROPOSED NEW STREETS FOR CANYON RANCH UNIT 4  
SPRING BRANCH, TEXAS  
REPORT FOR LENNAR  
OCTOBER 22, 2024  
BY PROFESSIONAL SERVICE INDUSTRIES, INC  
REPORT NUMBER: 0312-3287-1R  
SUMMARY OF RECOMMENDED OPTIONS  
MINIMUM FLEXIBLE PAVEMENT RECOMMENDATIONS - CBR = 3.0\*\*

STREET CLASSIFICATION	ASPHALTIC CONCRETE TYPE D, INCHES	ASPHALTIC CONCRETE TYPE B, INCHES	AGGREGATE BASE INCHES	GEOGRID	SUBGRADE INCHES	STRUCTURAL NUMBER
LOCAL STREET (NO BUS TRAFFIC)	2.5	-	7.00	NO	-	-

NOTE: CONTRACTOR MUST REFERENCE THE SIGNED AND SEALED GEOTECH REPORT



SUBSURFACE EXPLORATION AND PAVEMENT ANALYSIS  
PROPOSED NEW STREETS  
CANYON RANCH SUBDIVISION  
COMAL COUNTY, TEXAS  
REPORT FOR GRAM VIKAS PARTNERS, INC  
DECEMBER 10, 2020  
BY INTEC OF SAN ANTONIO, LP.  
12028 RADIUM  
SAN ANTONIO, TX 78216  
SUMMARY OF RECOMMENDED OPTIONS  
MINIMUM FLEXIBLE PAVEMENT RECOMMENDATIONS - CBR = 3.0\*\*

STREET CLASSIFICATION	ASPHALTIC CONCRETE TYPE D, INCHES	ASPHALTIC CONCRETE TYPE B, INCHES	AGGREGATE BASE INCHES	GEOGRID	SUBGRADE INCHES	STRUCTURAL NUMBER
LOCAL STREET (NO BUS TRAFFIC)	2.5	-	7.00	NO	-	2.07
RESIDENTIAL LOCAL	3.00	-	15.00	NO	-	4.01
RESIDENTIAL COLLECTOR	3.00	-	15.00	YES	-	3.95
				NO		4.08

SUMMARY OF RECOMMENDED OPTIONS - RIDGID PAVEMENT\*\*

STREET CLASSIFICATION	REINFORCED CONCRETE, INCHES	SUBGRADE THICKNESS, INCHES
RESIDENTIAL LOCAL (NO BUS TRAFFIC)	6.00	-
RESIDENTIAL COLLECTOR	10.00	-

NOTE: CONTRACTOR MUST REFERENCE THE SIGNED AND SEALED GEOTECH REPORT

DATE	REV	DESCRIPTION
APR		

DESIGNED BY: NA  
REVIEWED BY: ACR  
DRAWN BY: SSM







**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-5360 www.bgeinc.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4  
STREET AND DRAINAGE DETAILS  
(SHEET 1 OF 6)




STATE OF TEXAS  
STACY MULHOLLAND  
146417  
LICENSED PROFESSIONAL ENGINEER  
11/08/2024  
SHEET  
C06.50









G:\TXC\Projects\San Antonio Projects\17278-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C06.50 - STREET AND DRAINAGE DETAILS.dwg Layout: STREET AND DRAINAGE DETAILS (SHEET 2 OF 6) Plotted: 11/7/2024 11:10:32 AM By: Mhernandez









[illegible]



[illegible]






**TABLE OF VARIABLE DIMENSIONS AND QUANTITIES FOR ONE HEADWALL**

Values for One Pipe


Slope	W	X	Y	L	Reinf (lbs)	Conc (CY)	Reinf (lbs)	Conc (CY)
12°	4'-7 1/2"	2'-6"	2'-10"	3'-3 1/2"	88	0.6	1'-9"	20
15°	5'-3 1/2"	2'-9 1/2"	2'-0"	3'-10 1/2"	103	0.7	2'-2"	24
18°	6'-4 1/2"	3'-1"	3'-10"	4'-5"	124	0.9	2'-8"	32
21°	7'-2 1/2"	3'-4 1/2"	4'-4"	5'-0"	143	1.1	3'-1"	43
24°	8'-2 1/2"	3'-9 1/2"	4'-10"	5'-7"	164	1.3	3'-7"	50
27°	9'-1"	4'-1"	5'-4"	6'-2"	179	1.5	3'-11"	56
30°	9'-11 1/2"	4'-4 1/2"	5'-10"	6'-8 1/2"	203	1.7	4'-4"	65
33°	10'-10"	4'-8"	6'-4"	7'-3 1/2"	224	2.0	4'-8"	71
36°	11'-8 1/2"	4'-11 1/2"	6'-10"	7'-10 1/2"	249	2.2	5'-1"	81
42°	13'-5 1/2"	5'-6 1/2"	7'-10"	9'-0 1/2"	298	2.8	5'-10"	97
48°	15'-9"	6'-1 1/2"	8'-4"	10'-9 1/2"	360	3.6	6'-7"	117
54°	17'-5 1/2"	6'-8 1/2"	10'-4"	11'-11 1/2"	427	4.5	7'-0"	151
60°	19'-2 1/2"	7'-3 1/2"	11'-4"	13'-1"	481	5.3	8'-3"	174
66°	20'-11 1/2"	7'-10 1/2"	12'-4"	14'-3"	544	6.2	8'-9"	194
72°	22'-8 1/2"	8'-5 1/2"	12'-4"	15'-4 1/2"	601	7.1	9'-4"	213
12°	6'-3"	2'-6"	4'-3"	4'-11"	118	0.8	1'-9"	22
15°	7'-5"	2'-9 1/2"	5'-0"	5'-9 1/2"	137	1.1	2'-2"	28
18°	8'-6 3/4"	3'-1"	5'-9"	6'-7 3/4"	170	1.3	2'-8"	37
21°	9'-8 3/4"	3'-4 1/2"	6'-6"	7'-6"	195	1.6	3'-1"	48
24°	11'-0"	3'-9 1/2"	7'-3"	8'-4 1/2"	227	2.0	3'-7"	58
27°	12'-2"	4'-1"	8'-0"	9'-2 1/2"	251	2.3	3'-11"	67
30°	12'-4"	4'-4 1/2"	8'-9"	10'-1 1/2"	283	2.7	4'-4"	77
33°	14'-5 1/2"	4'-8"	9'-6"	10'-11 1/2"	318	3.1	4'-8"	84
36°	15'-7 1/2"	4'-11 1/2"	10'-3"	11'-10"	351	3.5	5'-1"	96
42°	17'-11 1/2"	5'-6 1/2"	11'-9"	13'-6 1/2"	432	4.5	5'-10"	119
48°	21'-1 1/2"	6'-1 1/2"	14'-0"	16'-2"	537	6.1	6'-7"	146
54°	23'-5 1/2"	6'-8 1/2"	15'-6"	17'-10 1/2"	630	7.3	7'-0"	186
60°	25'-9 1/2"	7'-3 1/2"	17'-0"	19'-7 1/2"	719	8.7	8'-3"	219
66°	28'-1"	7'-10 1/2"	18'-6"	21'-4 1/2"	811	10.1	8'-9"	242
72°	30'-4 1/2"	8'-5 1/2"	20'-0"	23'-1 1/2"	924	11.7	9'-4"	272
12°	7'-10 1/2"	2'-6"	5'-8"	6'-6 1/2"	148	1.1	1'-9"	24
15°	9'-4"	2'-9 1/2"	6'-8"	7'-9 1/2"	171	1.5	2'-2"	32
18°	10'-9 1/2"	3'-1"	7'-8"	8'-10 1/2"	221	1.9	2'-8"	42
21°	12'-2 1/2"	3'-4 1/2"	8'-6"	10'-0"	260	2.3	3'-1"	57
24°	13'-9 1/2"	3'-9 1/2"	9'-8"	11'-2"	301	2.8	3'-7"	67
27°	15'-3"	4'-1"	10'-8"	12'-3 1/2"	334	3.3	3'-11"	77
30°	16'-8 1/2"	4'-4 1/2"	11'-6"	13'-5 1/2"	385	3.8	4'-4"	89
33°	18'-1 1/2"	4'-8"	12'-8"	14'-7 1/2"	425	4.5	4'-8"	101
36°	19'-7"	4'-11 1/2"	13'-8"	15'-9 1/2"	472	5.1	5'-1"	115
42°	22'-5 1/2"	5'-6 1/2"	15'-8"	18'-1"	583	6.5	5'-10"	141
48°	26'-6 1/2"	6'-1 1/2"	18'-8"	21'-6 1/2"	730	8.9	6'-7"	175
54°	29'-5 1/2"	6'-8 1/2"	20'-8"	23'-10 1/2"	875	10.7	7'-0"	226
60°	32'-3 1/2"	7'-3 1/2"	22'-8"	26'-2"	996	12.7	8'-3"	264
66°	35'-2 1/2"	7'-10 1/2"	24'-8"	28'-5 1/2"	1,140	14.9	8'-9"	300
72°	38'-1 1/2"	8'-5 1/2"	26'-8"	30'-9 1/2"	1,297	17.3	9'-4"	334
12°	11'-2"	2'-6"	8'-6"	9'-9 3/2"	224	1.9	1'-9"	28
15°	13'-2 1/2"	2'-9 1/2"	10'-0"	11'-6 1/2"	268	2.5	2'-2"	37
18°	15'-2 1/2"	3'-1"	11'-0"	13'-3 1/2"	330	3.2	2'-8"	50
21°	17'-2 1/2"	3'-4 1/2"	13'-0"	15'-0 1/2"	387	3.9	3'-1"	69
24°	19'-4 1/2"	3'-9 1/2"	14'-6"	16'-9"	453	4.8	3'-7"	80
27°	21'-4 1/2"	4'-1"	16'-0"	18'-5 1/2"	512	5.7	3'-11"	96
30°	23'-5 1/2"	4'-4 1/2"	17'-6"	20'-2 1/2"	593	6.7	4'-4"	110
33°	25'-5 1/2"	4'-8"	19'-0"	21'-11 1/2"	675	7.8	4'-8"	127
36°	27'-5 1/2"	4'-11 1/2"	20'-6"	23'-8"	735	9.0	5'-1"	144
42°	31'-6 1/2"	5'-6 1/2"	23'-6"	27'-1 1/2"	922	11.5	5'-10"	179
48°	37'-3 1/2"	6'-1 1/2"	28'-0"	32'-4"	1,191	15.9	6'-7"	231
54°	41'-4 1/2"	6'-8 1/2"	31'-0"	35'-9 1/2"	1,424	19.2	7'-0"	280
60°	45'-4 1/2"	7'-3 1/2"	34'-0"	39'-3"	1,631	22.9	8'-9"	353

DISCLAIMER: This document is prepared by an Engineer, Registered Professional Engineer, State of Texas, License No. 12000. It is the responsibility of the user to verify the accuracy of the information contained herein and to ensure that the information is used in accordance with the intended purpose. The user shall be responsible for any errors or omissions in this document.

DATE: 12/9/08







PIPE END TREATMENT  
N.T.S.



11/08/2024  
SHEET  
C06.55

CANYON RANCH UNIT 4  
STREET AND DRAINAGE DETAILS  
(SHEET 6 OF 6)

**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-581-3800 [www.bgeingony.com](http://www.bgeingony.com)  
TX PE Registration No. F-1046




DESIGNED BY: NA  
REVIEWED BY: ACR  
DRAWN BY: SSM

REVISIONS

NO.	DESCRIPTION	DATE	APR
1	REV		
2	REV		
3	REV		
4	REV		
5	REV		



G:\TXC\Projects\San Antonio Projects\2728-00 - Canyon Ranch\18 - Unit 4\03\_CADD\01\_Shts\C07.00 - ONSITE UTILITY PLAN.dwg Layout: 11/7/2024 10:51:20 AM By: Mhemandez



MYSTIC SHORES 12, LOT 1408  
PROPERTY ID: 138169  
CURTIS & JACQUELINE MAGEE

20' GVTC  
TELE ESMT  
9806000146,  
O.R.C.C


MYSTIC SHORES 12, LOT 1407  
PROPERTY ID: 138168  
THOMAS & LORI TYE TRUST 7-19-22

MYSTIC SHORE U-12  
DOC # 200506010160, M.P.R.C.C.

MYSTIC SHORES 12, LOT 1406  
PROPERTY ID: 138167  
JOHN & THERESA HALL

MYSTIC SHORES 12, LOT 1405  
PROPERTY ID: 138166  
JUSTIN & SARA MEIER

MYSTIC SHORES 12, LOT 1404  
PROPERTY ID: 138165  
ANNA GOODWIN



LEGEND	
	PROPERTY BOUNDARY
	UNIT BOUNDARY
	BUILDING SETBACK
	PROPOSED LOT LINES
	PROPOSED EASEMENT
	100 YEAR FEMA FLOODPLAIN
	PROPOSED WATER MAIN
	DUAL/SINGLE WATER SERVICES
	PROPOSED FIRE HYDRANT
	PROPOSED GATE VALVE
	PROPOSED SANITARY SEWER
	WASTEWATER SERVICES
	PROPOSED STORM LINE WITH MANHOLE
	PROPOSED CURB INLET
	PROPOSED NATURAL GAS LINE
	PROPOSED ELECTRIC LINE
	PROPOSED FIBER OPTIC LINE
	EXISTING FORCE MAIN
	PROPOSED STREET LIGHT
	RAISED REFLECTIVE HYDRANT MARKER

UTILITY GENERAL NOTES:  
1. 2" WATERLINES SHALL BE ASTM D2241, SDR 21 UNLESS OTHERWISE APPROVED. ALL WATERLINES LARGER THAN 8" SHALL BE AWWA C900 DR 18.  
2. ALL MAINS SHALL BE FLUSHED, HYDROSTATICALLY TESTED, AND DISINFECTED BY THE CONTRACTOR. SEE "CONNECTION TO EXISTING WATER SYSTEM" NOTE BELOW

CONTRACTOR TO TIE INTO EXISTING WATER MAIN AFTER ALL NEW MAINS HAVE BEEN DISINFECTED AND PASSED ALL TESTS AND HAVE BEEN APPROVED BY AUQA TEXAS, INC. FOR CHLORINATION INJECTION:  
1 - 1" CORPORATION STOP C.C. X I.P.  
1 - 1" COMP X 1R" CPL, CURB STOP  
1 - 1" 1/4" THD SOLID CAP FOR MACHINE CHLORINATION  
1 - 1" COPPER TUBING, CUT AS REQ'D  
CONTRACTOR TO PROVIDE A 2' JUMPER CONNECTION TO LOAD NEW MAIN

- THE LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
- ALL GARBAGE OR SPOIL MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, AT HIS EXPENSE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT.
- ALL ITEMS NOT SPECIFICALLY CALLED FOR ON THE PLANS, OR IN THE SPECIFICATIONS, BUT NECESSARY TO REASONABLY CONSTRUCT THE FACILITY OR IMPROVEMENT, SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT AND NO SEPARATE PAYMENTS WILL BE MADE FOR THESE ITEMS.
- DEPTH OF BURY FOR ALL PIPE SHALL BE A MINIMUM OF 4' UNLESS OTHERWISE NOTED OR APPROVED BY TEXAS WATER COMPANY.
- CONTRACTOR TO GRADE SITE TO WITHIN  $\pm 0.10'$  BEFORE THE INSTALLATION OF UTILITIES TO ENSURE PROPER COVER IS ACHIEVED.
- THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES REGARDING THE LOCATION OF THE EXISTING FACILITIES PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL EXCAVATE AROUND EXISTING UTILITIES WHICH INTERSECT THE PROPOSED ALIGNMENT OF THE SERVICES AND NOTIFY THE ENGINEER OF POTENTIAL CONFLICTS, PRIOR TO ANY CONSTRUCTION IN THE AREA.
- ALL DISTURBED AREAS WITHIN THE EASEMENTS SHALL BE HYDRO-MULCHED IN ACCORDANCE WITH TADCR SPECIFICATIONS.
- FOR WATER METER SERVICED DETAIL, SEE SHEET C10.00
- SEE SHEET C10.00 THROUGH C10.06 FOR UTILITY DETAILS
- IF THE MAXIMUM STATIC PRESSURE EXCEEDS 80 PSI, A PRV WILL BE REQUIRED ON THE PROPERTY OWNER'S SIDE OF THE WATER METER

GENERAL UTILITY LOCATION NOTES:  
TYPICAL QUALITY LEVEL OF THE UTILITY INFORMATION SHOWN ON THESE PLANS IS SHOWN IN THE TABLE BELOW. SPECIFIC NOTES ON THE PLANS INDICATE LOCATIONS WHERE THE UTILITY INFORMATION SHOWN IS KNOWN TO FALL SHORT OF OR EXCEED THE STATED QUALITY LEVEL.

ABANDONED MAINS	QL D
NATURAL GAS MAINS	QL D
OVERHEAD ELECTRIC LINES	QL C
UNDERGROUND CATV LINES	QL D
UNDERGROUND TELECOMMUNICATION LINES	QL D
ALL UNDERGROUND UTILITY SERVICE LINES	QL D

NOTE:  
UTILITY SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO UTILITY DETAIL SHEETS C10.00 - C10.08.

**TRENCH EXCAVATION SAFETY PROTECTION**  
CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-E, TEX-114-E, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE HAYS COUNTY STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100LF FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE HAYS COUNTY STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

DATE	REV	DESCRIPTION
APR		

DESIGNED BY: STAFF

REVIEWED BY: SSM

DRAWN BY: ACR

BGE, INC.

7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 214-361-3600 www.bgeenergy.com  
TXPE Registration No. F-1046

CANYON RANCH UNIT 4

ONSITE UTILITY PLAN (SHEET 1 OF 3)

STATE OF TEXAS

STACY MULHOLLAND

146417


PROFESSIONAL ENGINEER

11/08/2024

SHEET

C07.00





UTILITY GENERAL NOTES:

1. 2" WATERLINES SHALL BE ASTM D2241, SDR 21 UNLESS OTHERWISE APPROVED. ALL WATERLINES LARGER THAN 8" SHALL BE AWWA C900 DR 18.
2. ALL MAINS SHALL BE FLUSHED, HYDROSTATICALLY TESTED, AND DISINFECTED BY THE CONTRACTOR. SEE "CONNECTION TO EXISTING WATER SYSTEM" NOTE BELOW


CONTRACTOR TO TIE INTO EXISTING WATER MAIN AFTER ALL NEW MAINS HAVE BEEN  
DISINFECTED AND PASSED ALL TESTS AND HAVE BEEN APPROVED BY AUQA TEXAS, INC.  
FOR CHLORINATION INJECTION:  
1 - 1" CORPORATION STOP C.C. X I.P.  
1 - 1" COMP X 1R" CPL, CURB STOP  
1 - 1" 1/4" THD SOLID CAP FOR MACHINE CHLORINATION  
1 - 1" COPPER TUBING, CUT AS REQ'D  
CONTRACTOR TO PROVIDE A 2" JUMPER CONNECTION TO LOAD NEW MAIN





















3. THE LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
4. ALL GARBAGE OR SPOIL MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR AT HIS EXPENSE.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT.
6. ALL ITEMS NOT SPECIFICALLY CALLED FOR ON THE PLANS, OR IN THE SPECIFICATIONS, BUT NECESSARY TO REASONABLY CONSTRUCT THE FACILITY OR IMPROVEMENT, SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT AND NO SEPARATE PAYMENTS WILL BE MADE FOR THESE ITEMS.
7. METHOD OF BURY FOR ALL PIPE SHALL BE A MINIMUM OF 4' UNLESS OTHERWISE NOTED OR APPROVED BY TEXAS WATER COMPANY.
8. CONTRACTOR TO GRADE SITE TO WITHIN  $\pm 0.10'$  BEFORE THE INSTALLATION OF UTILITIES TO ENSURE PROPER COVER IS ACHIEVED.
9. THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES REGARDING THE LOCATION OF THE EXISTING FACILITIES PRIOR TO CONSTRUCTION.
10. THE CONTRACTOR SHALL EXCAVATE AROUND EXISTING UTILITIES, WHICH INTERSECT THE PROPOSED ALIGNMENT OF THE SERVICES AND NOTIFY THE ENGINEER OF POTENTIAL CONFLICTS, PRIOR TO ANY CONSTRUCTION IN THE AREA.
11. ALL DISTURBED AREAS WITHIN THE EASEMENTS SHALL BE HYDRO-MULCHED IN ACCORDANCE WITH TxDOT SPECIFICATIONS.
12. FOR WATER METER SERVED DETAIL, SEE SHEET C110.00.
13. SEE SHEET C110.00 THROUGH C110.06 FOR UTILITY DETAILS.
14. IF THE MAXIMUM STATIC PRESSURE EXCEEDS 80 PSI, A PRV WILL BE REQUIRED ON THE PROPERTY OWNER'S SIDE OF THE WATER METER.



GENERAL UTILITY LOCATION NOTES:  
TYPICAL QUALITY LEVEL OF THE UTILITY INFORMATION SHOWN ON THESE PLANS IS SHOWN IN THE TABLE BELOW. SPECIFIC NOTES ON THE PLANS INDICATE LOCATIONS WHERE THE UTILITY INFORMATION SHOWN IS KNOWN TO FALL SHORT OF OR EXCEED THE STATED QUALITY LEVEL.

ABANDONED MAINS	QL D
NATURAL GAS MAINS	QL D
OVERHEAD ELECTRIC LINES	QL C
UNDERGROUND CATV LINES	QL D
UNDERGROUND TELECOMMUNICATION LINES	QL D
ALL UNDERGROUND UTILITY SERVICE LINES	QL D


**NOTE:**  
UTILITY SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER  
UTILITY DETAIL SHEETS C10.00 - C10.08.



	PROPERTY BOUNDARY
	UNIT BOUNDARY
	BUILDING SETBACK
	PROPOSED LOT LINES
	PROPOSED EASEMENT
	100 YEAR FEMA FLOODPLAIN
	PROPOSED WATER MAIN
	DUAL/SINGLE WATER SERVICES
	PROPOSED FIRE HYDRANT
	PROPOSED GATE VALVE
	PROPOSED SANITARY SEWER
	WASTEWATER SERVICES
	PROPOSED STORM LINE WITH MANHOLE
	PROPOSED CURB INLET
	PROPOSED NATURAL GAS LINE
	PROPOSED ELECTRIC LINE
	PROPOSED FIBER OPTIC LINE
	EXISTING FORCE MAIN
	PROPOSED STREET LIGHT
	RAISED REFLECTIVE HYDRANT MARKER

 <p><b>BGE, INC.</b> 7330 San Pedro, Suite 202 San Antonio, TX 78216 TEL: 214-343-8800 TBPB Registration No. F-1046</p>	CANYON RANCH UNIT 4			DESIGNED BY: STAFF	APR
	ONSITE UTILITY PLAN (SHEET 2 OF 3)			REVIEWED BY: SSM	DATE
				DRAWN BY: ACR	REV
					DESCRIPTION





**TRENCH EXCAVATION SAFETY PROTECTION**  
CONTRACTOR AND/OR CONTRACTORS INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE QUALITY ASSURANCE PROGRAM FOR THE PROJECT WORK AREA. CONTRACTOR SHALL IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTORS INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL DEVELOP AND IMPLEMENT A TRENCH EXCAVATION SAFETY PROTECTION PROGRAM IN ACCORDANCE WITH OSHA STANDARDS COVERING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATIONS.

**UTILITY TRENCH COMPACTION**  
ALL UTILITY TRENCH COMPACTION TESTS WITHIN THE STREET PAVEMENT SECTION SHALL BE THE RESPONSIBILITY OF THE DEVELOPER'S GEO-TECHNICAL ENGINEER. FILL MATERIAL SHALL BE PLACED IN UNIFORM LAYERS NOT TO EXCEED TWELVE INCHES (12") LOOSE. EACH LAYER OF MATERIAL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY AND TESTED FOR DENSITY AND MOISTURE IN ACCORDANCE WITH TEST METHODS TEX-113-C, TEX-114-C, TEX-115-E. THE NUMBER AND LOCATION OF REQUIRED TESTS SHALL BE DETERMINED BY THE GEO-TECHNICAL ENGINEER AND APPROVED BY THE HAYS COUNTY STREET INSPECTOR. AT A MINIMUM, TESTS SHALL BE TAKEN EVERY 100' FOR EACH LIFT. UPON COMPLETION OF TESTING THE GEO-TECHNICAL ENGINEER SHALL PROVIDE THE HAYS COUNTY STREET INSPECTOR WITH ALL TESTING DOCUMENTATION AND A CERTIFICATION STATING THAT THE PLACEMENT OF FILL MATERIAL HAS BEEN COMPLETED IN ACCORDANCE WITH THE PLANS.

**Legend**

- PROPERTY BOUNDARY
- UNIT BOUNDARY
- BUILDING SETBACK
- PROPOSED LOT LINES
- PROPOSED EASEMENT
- 100 YEAR FEMA FLOODPLAIN
- PROPOSED WATER MAIN
- DUAL/SINGLE WATER SERVICES
- PROPOSED FIRE HYDRANT
- PROPOSED GATE VALVE
- PROPOSED SANITARY SEWER
- WASTEWATER SERVICES
- PROPOSED STORM LINE WITH MANHOLE
- PROPOSED CURB INLET
- PROPOSED NATURAL GAS LINE
- PROPOSED ELECTRIC LINE
- PROPOSED FIBER OPTIC LINE
- EXISTING FORCE MAIN
- PROPOSED STREET LIGHT
- RAISED REFLECTIVE HYDRANT MARKER

- UTILITY GENERAL NOTES:**
2. WATER LINES SHALL BE ASTM D2241, SDR 21 UNLESS OTHERWISE APPROVED. ALL WATER LINES LARGER THAN 8" SHALL BE AWWA C900 DR 18.
  2. ALL MAINS SHALL BE FLUSHED, HYDROSTATICALLY TESTED, AND DISINFECTED BY THE CONTRACTOR. SEE "CONNECTION TO EXISTING WATER SYSTEM" NOTE BELOW.

CONTRACTOR TO THE INTO EXISTING WATER MAIN AFTER ALL NEW MAINS HAVE BEEN DISINFECTED AND PASSED ALL TESTS AND HAVE BEEN APPROVED BY AQA TEXAS, INC. FOR CHLORINATION INJECTION. 1 - 1" CORPORATION STOP C.C. XLP. 1 - 1" COMP X 1R" CPL CURB STOP 1 - 1" 1/4" THD SOLID CAP FOR MACHINE CHLORINATION 1 - 1" COPPER TUBING, CUT AS REQ'D CONTRACTOR TO PROVIDE A 2" JUMPER CONNECTION TO LOAD NEW MAIN
--
  3. THE LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.
  4. ALL GARBAGE OR SPOIL MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, AT HIS EXPENSE.
  5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJECT.
  6. ALL ITEMS NOT SPECIFICALLY CALLED FOR ON THE PLANS, OR IN THE SPECIFICATIONS, BUT NECESSARY TO REASONABLY CONSTRUCT THE FACILITY OR IMPROVEMENT, SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT AND NO SEPARATE PAYMENTS WILL BE MADE FOR THESE ITEMS.
  7. DEPTH OF BURY FOR ALL PIPE SHALL BE A MINIMUM OF 4' UNLESS OTHERWISE NOTED OR APPROVED BY TEXAS WATER COMPANY.
  8. CONTRACTOR TO GRADE SITE TO WITHIN  $\pm 0.10'$  BEFORE THE INSTALLATION OF UTILITIES TO GRADE.
  9. THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES REGARDING THE LOCATION OF THE EXISTING FACILITIES PRIOR TO CONSTRUCTION.
  10. THE CONTRACTOR SHALL EXCAVATE AROUND EXISTING UTILITIES WHICH INTERSECT THE PROPOSED ALIGNMENT OF THE SERVICES AND NOTIFY THE ENGINEER OF POTENTIAL CONFLICTS, PRIOR TO ANY CONSTRUCTION IN THE AREA.
  11. ALL DISTURBED AREAS WITHIN THE EASEMENTS SHALL BE HYDRO-MULCHED IN ACCORDANCE WITH TxDOT SPECIFICATIONS.
  12. FOR WATER METER SERVICED DETAIL, SEE SHEET C10.00
  13. SEE SHEET C10.00 THROUGH C10.06 FOR UTILITY DETAILS.
  14. IF THE MAXIMUM STATIC PRESSURE EXCEEDS 80 PSI, A PRV WILL BE REQUIRED ON THE PROPERTY OWNER'S SIDE OF THE WATER METER.

GENERAL UTILITY LOCATION NOTES:  
TYPICAL QUALITY LEVEL OF THE UTILITY INFORMATION SHOWN ON THESE PLANS IS SHOWN IN THE TABLE BELOW. SPECIFIC NOTES ON THE PLANS INDICATE LOCATIONS WHERE THE UTILITY INFORMATION SHOWN IS KNOWN TO FALL SHORT OF OR EXCEED THE STATED QUALITY LEVEL.

ABANDONED MAINS	QL D
NATURAL GAS MAINS	QL D
OVERHEAD ELECTRIC LINES	QL C
UNDERGROUND CATV LINES	QL E
UNDERGROUND TELECOMMUNICATION LINES	QL D
ALL UNDERGROUND UTILITY SERVICE LINES	QL D

**NOTE:**  
UTILITY SYMBOLS ARE NOT TO SCALE, AND ARE ONLY SHOWN FOR ILLUSTRATION PURPOSES. REFER TO  
UTILITY DETAIL SHEETS C10.00 - C10.08.

[illegible]

DESIGNED BY:	STAFF
REVIEWED BY:	SSM
DRAWN BY:	ACR



**BGE, INC.**  
7330 San Pedro, Suite 202  
San Antonio, TX 78216  
TEL: 210-581-3600 [www.browngay.com](http://www.browngay.com)  
TBBE Registration No. E 1046

CANYON RANCH UNIT 4

ONSITE UTILITY PLAN (SHEET 3 OF 3)



11/08/2024

SHEET

C07.02