

January 16, 2025

Texas Commission on Environmental Quality Attn: Franklin Anciano 14250 Judson Rd, San Antonio, TX 78233

RE: 5727 Farinon Drive, San Antonio, Bexar County, Texas 78249 Ethium Building – WPAP Application Comment Response Letter – Update #1

Dear Mr. Anciano,

The following comment response letter is regarding comments dated December 11, 2023, for the Ethium Building WPAP Application.

Franklin Anciano. – (512) 239-7017 – Franklin.Anciano@tceq.texas.gov

- 1) Is there a previous EAPP approval for this project site? If so, a WPAP modification may need to be submitted.
 - Response: The only previous EAPP approval for the site that was received from TCEQ ORR was for improvements outside of the Recharge Zone and a WPAP was not required. Attached on Section 11 is an email correspondence on the previous improvement from Doc/Num: 97-0106935, Book: D (Vol. 07158, Pg. 00117).

Edwards Aquifer Application Cover Page (TCEQ-20705):

- 2) Line 9. Please provide information.
 - Response: Line 9 has been revised/updated.
- 3) Line 3. Customer information does not match the parcel/landowner as shown on the Bexar Central Appraisal District map. If the parcel/land ownership has recently changed, please provide documentation from the county.
 - Response: Customer information has been updated/revised accordingly to match parcel/landowner as shown on the Bexar Central Appraisal District map.

General Information Form (TCEQ-0587):

- 4) Please print and sign name of Customer/Agent.
 - Response: Customer/Agent signature and named provided on the General Information Form.
- 5) Line 10. Please provide a project site description.
 - Response: Line 10. Has been revised/updated accordingly.
- 6) Attachment C Project Description.
 - Response: Attachment C has been revised/updated accordingly.



Geologic Assessment Form (TCEQ-0585):

- Please include any previous correspondence from EAPP stating that a Geologic Assessment is not required. If not, please include either a Geologic Assessment or Water Pollution Abatement Plan Application Form (TCEQ-0584) Attachment D – Exception to the Required Geologic Assessment.
 - Response: CN603978057 as attached on the Exception to the Required Geologic Assessment (located in Section 4) shows the exception to the requirement of submitting a geologic assessment based upon the existing site conditions.

Water Pollution Abatement Plan Application Form (TCEQ-0584):

- 8) Line 14. Please provide information.
 - Response: Line 14 has been revised/updated accordingly.
- 9) Line 15. Please provide information.
 - Response: Line 15 has been updated accordingly. Does not apply to this submittal.
- 10) Attachment D Exception to the Required Geologic Assessment. Please see Administrative NOD Item #7.
 - Response: CN603978057 as attached on the Exception to the Required Geologic Assessment (located in Section 4) shows the exception to the requirement of submitting a geologic assessment based upon the existing site conditions.

Permanent Stormwater Section (TCEQ-0600):

- 11) Please provide Regulated Entity Name
 - Response: Sheet has been updated accordingly.
- 12) Line 5. Please make only one selection.
 - Response: Line 5 has been updated accordingly.

Agent Authorization Form (TCEQ-0599):

- 13) Please see Administrative NOD Item #3.
 - Response: Customer information has been updated/revised accordingly to match parcel/landowner as shown on the Bexar Central Appraisal District map.

If you should have any questions about the information contained herein, please do not hesitate to contact our office for clarification.

Regards,

WGI

Texas Engineering Firm No. F-15085

Le

Amanda Saldivar, P.E. Project Manager

John Mauser - Re: SWBC-Farinon

From:John MauserTo:Villagomez, JoseDate:8/24/2006 3:15 PMSubject:Re: SWBC-Farinon

Jose,

Only the storage of regulated quantities of hydrocarbons and hazardous substances (Aboveground: 500 or more gallons, Underground: all tanks) are reguated on the Transition Zone. A WPAP is not required on the Transiton Zone.

J.

>>> "Jose Villagomez" <Jvillagomez@slayengineering.com> 8/24/2006 2:21 PM >>> John:

I met with the our client today, to discuss the SWBC-Farinon parking lot expansion. We have decided to move all of the parking lot expansion out of the recharge zone, leaving all the expansion over the transition zone. If we are expanding on the piece of parking lot that is not over the recharge zone are we in the clear? Does the expansion which is not over the recharge zone trigger any requirements for the area of parking lot which exists over the recharge zone that was constructed prior to the WPAP process?

Thanks for your help.

Jose Slay Engineering Co., Inc.

12

Water Pollution Abatement Plan Application

(WPAP)

For

Ethium Building

5727 Farinon Drive,

San Antonio, Texas 78249



Prepared for:

ECONTROLS, LLC 5757 Farinon Dr., San Antonio, TX 78249

Table of Contents

Section 1: Edwards Aquifer Application Cover Page (TCEQ-20705)

• Section 2: General Information Form (TCEQ-0587)

- a. Attachment A: Road Map
- b. Attachment B: USGS/Edwards Recharge Zone Map
- c. Attachment C: Project Description

• Section 3: Geologic Assessment Form (TCEQ-0585)

- a. Attachment A: Geologic Assessment Table (TCEQ-0585-Table)
- b. Attachment B: Stratigraphic Column
- c. Attachment C: Site Geology
- d. Attachment D: Site Geologic Map(s)

• Section 4: Water Pollution Abatement Plan Application (TCEQ-0584)

- a. Attachment A: Factors Affecting Surface Water Quality
- b. Attachment B: Volume and Character of Storm Water
- c. Attachment C: Suitability Letter from Authorized Agent (if OSSF is proposed)
- d. Attachment D: Exception to the Required Geologic Assessment (if requested)

• Section 5: Temporary Stormwater Section (TCEQ-0602)

- a. Attachment A: Spill Response Actions
- b. Attachment B: Potential Sources of Contamination
- c. Attachment C: Sequence of Major Activities
- d. Attachment D: Temporary Best Management Practices and Measures
- e. Attachment E: Request to Temporary Seal a Feature (if requested)
- f. Attachment F: Structural Practices
- g. Attachment G: Drainage Area Map
- h. Attachment H: Temporary Sediments Pond(s) Plans and Calculations
- i. Attachment I: Inspection and Maintenance of BMPs
- j. Attachment J: Schedule of Interim and Permanent Soil Stabilization Practices

• Section 6: Permanent Stormwater Section (TCEQ-0600)

- a. Attachment A: 20% or Less Impervious Cover Waiver
- b. Attachment B: BMPs for Upgradient Stormwater
- c. Attachment C: BMPs for On-site Stormwater
- d. Attachment D: BMPs for Surface Streams
- e. Attachment E: Request to Seal Features
- f. Attachment F: Construction Plans
- g. Attachment G: Inspection, Maintenance, Repair and Retrofit Plan
- h. Attachment H: Pilot-Scale Field Testing Plan (if proposed)
- i. Attachment I: Measures for Minimizing Surface Stream Contamination
- Section 7: Agent Authorization Form (TCEQ-0599)

- Section 8: Application Fee Form (TCEQ-0574)
- Section 9: Check Payable to "Texas Commission on Environmental Quality"
- Section 10: Core Data Form (TCEQ-10400)
- Section 11: Additional Information



SECTION 1: Edwards Aquifer Application Cover Page (TCEQ-20705)

Texas Commission on Environmental Quality Edwards Aquifer Application Cover Page

Our Review of Your Application

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with <u>30 TAC 213</u>.

Administrative Review

1. <u>Edwards Aquifer applications</u> must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.

To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <u>http://www.tceq.texas.gov/field/eapp</u>.

- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.

An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.

- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

Technical Review

- 1. When an application is deemed administratively complete, the technical review period begins. The regional office will distribute copies of the application to the identified affected city, county, and groundwater conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.

- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

Mid-Review Modifications

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

1. Regulated Entity Name: Ethium Building				2. Regulated Entity No.:					
3. Customer Name: GTD Development LLC				4. Customer No.:					
5. Project Type: (Please circle/check one)	New		Modification		Extension		Exception		
6. Plan Type: (Please circle/check one)	WPAP	CZP	SCS	UST	AST	EXP	EXT	Technical Clarification	Optional Enhanced Measures
7. Land Use: (Please circle/check one)	Resider	ntial	Non-residential		8. Site (acres		e (acres):	±7.59	
9. Application Fee:	\$5,00	0	10. Permanent B			BMP(s):	Jellyfish filte	r
11. SCS (Linear Ft.):	N/A		12. AST/UST (No			o. Tar	o. Tanks): N/A		
13. County:	Bexa	-	14. Watershed:				Upper Leon	Creek	

Application Distribution

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

Austin Region						
County:	Hays	Travis	Williamson			
Original (1 req.)			—			
Region (1 req.)						
County(ies)						
Groundwater Conservation District(s)	Edwards Aquifer Authority Barton Springs/ Edwards Aquifer Hays Trinity Plum Creek	Barton Springs/ Edwards Aquifer	NA			
City(ies) Jurisdiction	Austin Buda Dripping Springs Kyle Mountain City San Marcos Wimberley Woodcreek	Austin Bee Cave Pflugerville Rollingwood Round Rock Sunset Valley West Lake Hills	Austin Cedar Park Florence Georgetown Jerrell Leander Liberty Hill Pflugerville Round Rock			

San Antonio Region							
County:	Bexar	Comal	Kinney	Medina	Uvalde		
Original (1 req.)	<u>X</u>						
Region (1 req.)	<u></u>						
County(ies)							
Groundwater Conservation District(s)	X Edwards Aquifer Authority Trinity-Glen Rose	Edwards Aquifer Authority	Kinney	EAA Medina	EAA Uvalde		
City(ies) Jurisdiction	Castle Hills Fair Oaks Ranch Helotes Hill Country Village Hollywood Park X San Antonio (SAWS) Shavano Park	Bulverde Fair Oaks Ranch Garden Ridge New Braunfels Schertz	NA	San Antonio ETJ (SAWS)	NA		

I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review.

Guglielmo ennon Print Name of Customer/Authorized Agent

Signature of Customer/Authorized Agent

8-28-2023 Date

FOR TCEQ INTERNAL USE ONLY					
Date(s)Reviewed:	D	Date Administratively Complete:			
Received From:	C	Correct Number of Copies:			
Received By:	D	Distribution Date:			
EAPP File Number:	0	Complex:			
Admin. Review(s) (No.):	N	No. AR Rounds:			
Delinquent Fees (Y/N):	R	Review Time Spent:			
Lat./Long. Verified:	S	SOS Customer Verification:			
Agent Authorization Complete/Notarized (Y/N):	Fe		Payable to TCEQ (Y/	'N):	
Core Data Form Complete (Y/N):	Cł	Check: Signed (Y/N):			
Core Data Form Incomplete Nos.:			Less than 90 days old	d (Y/N):	

TCEQ-20705 (Rev. 02-17-17)

General Information Form

Texas Commission on Environmental Quality

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

Print Name of Customer/Agent: _____

Date: January 14, 2025

Signature of Customer/Agent:

Project Information

- 1. Regulated Entity Name: Ethium Building
- 2. County: Bexar
- 3. Stream Basin: Upper Leon Creek
- 4. Groundwater Conservation District (If applicable): _____
- 5. Edwards Aquifer Zone:

Х	Recharge Zone
\times	Transition Zone

6. Plan Type:

X WPAP	AST
SCS	
Modification	Exception Request

7. Customer (Applicant):

Contact Person: <u>Kennon Guglielmo</u> Entity: <u>ECONTROLS</u>, LLC Mailing Address: <u>5757</u> Farinon Drive City, State: <u>San</u> Antonio, TX Telephone: <u>_____</u> Email Address: <u>Kgug</u>@econtrols.com

Zip: <u>7824</u>9 FAX: ____

- 8. Agent/Representative (If any): Contact Person: Erin Sandoval Entity: WGI Mailing Address: 755 E. Mulberry Ave, Suite 501 City, State: San Antonio, TX Zip: 78212 Telephone: (210)860-9224 FAX: Email Address: jose.cantu@wginc.com
- 9. Project Location:

The project site is located inside the city limits of <u>San</u> Antonio

The project site is located outside the city limits but inside the ETJ (extra-territorial jurisdiction) of ______.

- The project site is not located within any city's limits or ETJ.
- 10. X The location of the project site is described below. The description provides sufficient detail and clarity so that the TCEQ's Regional staff can easily locate the project and site boundaries for a field investigation.

The project site is located at 5727 Farinon Drive, San Antonio, Bexar County, Texas 78249. Property ID: 1048181

- 11. X Attachment A Road Map. A road map showing directions to and the location of the project site is attached. The project location and site boundaries are clearly shown on the map.
- 12. X Attachment B USGS / Edwards Recharge Zone Map. A copy of the official 7 ½ minute USGS Quadrangle Map (Scale: 1" = 2000') of the Edwards Recharge Zone is attached. The map(s) clearly show:

Project site boundaries.

USGS Quadrangle Name(s).

Boundaries of the Recharge Zone (and Transition Zone, if applicable).

Drainage path from the project site to the boundary of the Recharge Zone.

- 13. X **The TCEQ must be able to inspect the project site or the application will be returned**. Sufficient survey staking is provided on the project to allow TCEQ regional staff to locate the boundaries and alignment of the regulated activities and the geologic or manmade features noted in the Geologic Assessment.
 - Survey staking will be completed by this date: <u>May</u> 11, 2023

- 14. X Attachment C Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent throughout the application and contains, at a minimum, the following details:
 - Area of the site
 - X Offsite areas
 - Impervious cover
 - Permanent BMP(s)
 - \times Proposed site use
 - Site history
 - Previous development
 - 🔀 Area(s) to be demolished
- 15. Existing project site conditions are noted below:
 - Existing commercial site
 Existing industrial site
 Existing residential site
 Existing paved and/or unpaved roads
 Undeveloped (Cleared)
 Undeveloped (Undisturbed/Uncleared)
 Other: _____

Prohibited Activities

- 16. I am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to Underground Injection Control);
 - (2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;
 - (3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;
 - (4) The use of sewage holding tanks as parts of organized collection systems; and
 - (5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).
 - (6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.
- 17. I am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:
 - (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
 - (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and

(3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.

Administrative Information

- 18. The fee for the plan(s) is based on:
 - For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.
 - For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.
 - For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.
 - A request for an exception to any substantive portion of the regulations related to the protection of water quality.
 - A request for an extension to a previously approved plan.
- 19. Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:

Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)

San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)

- 20. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 21. X No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.



ATTACHMENT A ROAD MAP





DRAWING: P:\8000\8066.00 Ethium Building\CIVIL\06-Design\SWMP\0n-Site\Exhibits\Aerial Exhibits.

AERIAL LOCATION MAP

ETHIUM BUILDING 5727 FARINON DIVE, SAN ANTONIO, TEXAS 78249 EXHIBIT





SECTION 2: General Information Form (TCEQ-0587) ATTACHMENT B USGS/EDWARDS RECHARGE ZONE MAP





SECTION 2: General Information Form (TCEQ-0587)

ATTACHMENT C

PROJECT DESCRIPTION

Ethium Building is an existing industrial development site on \pm 7.59 acres in Bexar County located at 5727 Farinon Drive, San Antonio, Bexar County, Texas 78249. The site is located at Silicon Drive and Farinon Drive intersection. The site is bound to the north by Farinon Subdivision Replat (Plat No. 050318), to the east Farinon Drive, to the south Ethium Building (Plat No. 22-11800284), and by Gold Tooth Development, LLC (Vol. 16787, Pg. 1153) to the west.

This development will consist of a paving expansion and jellyfish filter for permanent BMP to serve the existing development. The overall increase in impervious cover will be $\pm 25,582$ Square Feet (± 0.59 Acres). The existing site is currently zoned as industrial and is located within the Upper Leon Creek Watershed.

Ultimately, runoff generated from the site in existing and proposed condition will continue to drain into Leon Creek, a San Antonio River Authority right-of-way (ROW). All runoff generated from the proposed development will ultimately outfall to the Upper Leon Creek (TCEQ Segment #1907). A jellyfish filter is proposed for the treatment of the storm water runoff from the development.



This attachment does not apply to this submittal. An exception to the required Geologic Assessment is not required based on Inv. # - 964415 as shown below. A Geological Assessment was not completed and included in this submittal.

SUB EDAQ - Bexar - EControls LLC - 10/31/2011 Texas Commission on Environmental Quality Investigation Report

EControls, LLC CN603978057

ECONTROLLS LLC

RN102763380

Investigation #964415

Investigator: CHARLYNE FRITZ

Incident #

Site Classification COMMERCIAL

SIC Code: 8711 NAIC Code: 334513

Conducted: 10/31/2011 -- 01/19/2012

Program(s): EDWARDS AQUIFER

Investigation Type : Site Assessment File Review

Additional ID(s): 13-11103101

Address: 5727 FARINON DR; SAN ANTONIO, TX 78249 Location: .25 ML W OF IH 10 NEAR DE ZAVALA RD

Phone Work

Fax

Fax

Work

Activity Type : REGION 13 - SAN ANTONIO EAPPGRAST - EAPP Grant AST Plan Review

Principal(s) :

Role

RESPONDENT

ECONTROLS LLC

Name

Title

PE

ENTERPRISE

Name

GROUP MANAGER

<u>Contact(s) :</u>

Role

Regulated Entity Mail Contact

Regulated Entity Contact

Other Staff Member(s) : Role

Supervisor

Investigator Investigator QA Reviewer Supervisor LYNN BUMGUARDNER ELAINE GROSENHEIDE

ELAINE GROSENHEIDER AGNIESZKA HOBSON JAVIER ANGUIANO TODD JONES

Name

MR VINCE

FORSTER

LAMOUREUX

MR CHARLES P

Unit Name

Associated Check List

Checklist Name

PH HB 2191 POM

(210) 495-9772

(210) 495-9791

(210) 698-5544

(210) 698-5544

Investigation Comments :

Name of Project: EControls Inc.; Located on the west side of Farinon Drive, southwest of Silicon Dr. at 5757 Farinon Dr., San Antonio, Texas

Type of Plan: Request for the Approval of a Aboveground Storage Tank Facility (AST); 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program San Antonio File No. 520.00; Investigation No. 964415; Regulated Entity No. RN102763380

ECONTROLLS LLC - SAN ANTONIO

10/31/2011 to 1/19/2012 Inv. # - 964415

Page 2 of 3

INTRODUCTION

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the AST application for the above-referenced project submitted to the San Antonio Regional Office by Forster Engineering on behalf of EControls, LLC on October 31, 2011. Final review of the AST was completed after additional material was received on January 3, 2012. As presented to the TCEQ, the AST Facility Plan proposed in the application was prepared to be in general compliance with the requirements of 30 TAC §213.5(e). Therefore, based on the applicant's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in the approval letter.

BACKGROUND

The ASTs are to be located on a 13.779 acre site. The larger site is located on the Edwards Aquifer recharge zone, contributing zone within the transition zone, and the transition zone. A water pollution abatement plan (WPAP) was approved by letter dated July 11, 1997 for a driveway entrance to De Zavala Rd., which was located on the recharge zone. No additional regulated development has occurred on the recharge zone or the transition zone within the contributing zone.

GENERAL FACILITY INFORMATION

Project Description

The project site is located on the Edwards Aquifer Transition Zone. The proposed AST Facility Plan includes the items listed in the table below.

AST Gallons Tank Material Contents of Tank

1 1,000 Steel Gasoline

2 1,000 Steel Gasoline

3 1,000 Steel Diesel Fuel

Total 3,000

Equivalent Protection

The described ASTs are double walled tanks with an internal steel tank surrounded by an HDPE liner and an external concrete layer (UL 142, ConVault Protected AST). The tank consists of a primary tank within a sealed secondary tank. Each tank's outer dimensions will be 11 feet in width, 5.6667 feet in width, and 4.333 feet in height. The 30 mil HDPE liner is separated from the steel tank by ¼ inch Styrofoam insulation. The HDPE liner and concrete liner will contain any product leaks from the primary tank. The tanks will also be equipped with a leak detection system.

The double-walled piping will extend outside the tank area and slope towards the adjacent building. The piping will be aboveground and in an open trench that is covered by a steel plate. Spill and overfill control will be provided by quarterly visual inspections of the tank and piping system and by having personnel onsite and actively watching the unloading and refueling activities. The planned spill response that will take place at the facility is provided in Attachment "E" (enclosed) of the AST Facility Plan Application (Response Actions to Spills).

Geology

An exception to submitting a geologic assessment was requested with the application. According to the request, the new tanks will be placed on existing concrete flatwork within the transition zone of the Edwards Aquifer. No new soil disturbance is necessary to install the tanks or the piping structure. The exception to the requirement of submitting a geologic assessment is granted based upon the existing site conditions.

ADDITIONAL INFORMATION

NOD 1 Sent: 12/08/2011; Received: 01/03/2012; Attached No Violations Associated to this Investigation **ECONTROLLS LLC - SAN ANTONIO** 10/31/2011 to 1/19/2012 Inv. # - 964415 Page 3 of 3

Signed Environmental Investigator

Date $\frac{1}{18/12}$

Signed upervisor

Date

Attachments: (in order of final report submittal)

- ____Enforcement Action Request (EAR)
- Letter to Facility (specify type) : ______

Investigation Report

- ____Sample Analysis Results
- ___Manifests
- _NOR

Maps, Plans, Sketches

Photographs

Correspondence from the facility

X Other (specify) : pplication



SECTION 3: GEOLOGIC ASSESSMENT FORM (TCEQ-0585) ATTACHMENT B STRATIGRAPHIC COLUMN

Ethium Building



SECTION 3: GEOLOGIC ASSESSMENT FORM (TCEQ-0585) ATTACHMENT C SITE GEOLOGY

Ethium Building



SECTION 3: GEOLOGIC ASSESSMENT FORM (TCEQ-0585) ATTACHMENT D SITE GEOLOGIC MAP(S)

Water Pollution Abatement Plan Application

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Water Pollution Abatement Plan Application Form** is hereby submitted for TCEQ review and Executive Director approval. The form was prepared by:

Print Name of Customer/Agent: Kennon Gug liz land

Date: 8-28-2023

Signature of Customer/Agent:

Regulated Entity Name: Ethium Building

Regulated Entity Information

1. The type of project is:

Residential: Number of Lots:_____

- Residential: Number of Living Unit Equivalents:
- Commercial
- 📐 Industrial
- Other:____
- 2. Total site acreage (size of property): ± 7.59
- 3. Estimated projected population:
- 4. The amount and type of impervious cover expected after construction are shown below:

TCEQ-0584 (Rev. 02-11-15)

1 of 5

Impervious Cover of Proposed Project	Sq. Ft.	Sq. Ft./Acre	Acres
Structures/Rooftops	9632.50	÷ 43,560 =	0.22
Parking	0	÷ 43,560 =	
Other paved surfaces	15949.50	÷ 43,560 =	0.37
Total Impervious Cover	25582	÷ 43,560 =	0.59

Table 1 - Impervious Cover Table

Total Impervious Cover $\underline{0.59}$ ÷ Total Acreage $\underline{1.59}$ X 100 = $\underline{37.1}$ % Impervious Cover

- 5. X Attachment A Factors Affecting Surface Water Quality. A detailed description of all factors that could affect surface water and groundwater quality that addresses ultimate land use is attached.
- 6. X Only inert materials as defined by 30 TAC §330.2 will be used as fill material.

For Road Projects Only

Complete questions 7 - 12 if this application is exclusively for a road project.

7. Type of project:

NA TXDOT road project.

^{N/A}County road or roads built to county specifications.

^{N/A}City thoroughfare or roads to be dedicated to a municipality.

^{N/A}Street or road providing access to private driveways.

8. Type of pavement or road surface to be used:

```
MA Concrete
A Asphaltic concrete pavement
A Other: _____
```

9. Length of Right of Way (R.O.W.): _____ feet.

Width of R.O.W.: <u>N/A</u> feet. L x W = <u>N/A</u> $Ft^2 \div 43,560 Ft^2/Acre = N/A$ acres.

10. Length of pavement area: <u>N/A</u> feet.

Width of pavement area: _____ feet. L x W = _____ $Ft^2 \div 43,560 Ft^2/Acre = _____ acres.$ Pavement area ______ acres \div R.O.W. area _____ acres x 100 = _____ % impervious cover.

11. $\mathbb{N}^{\mathbb{A}}$ A rest stop will be included in this project.

 $\mathbb{N}^{\mathbb{A}}$ A rest stop will not be included in this project.

12. MA Maintenance and repair of existing roadways that do not require approval from the TCEQ Executive Director. Modifications to existing roadways such as widening roads/adding shoulders totaling more than one-half (1/2) the width of one (1) existing lane require prior approval from the TCEQ.

Stormwater to be generated by the Proposed Project

13. Attachment B - Volume and Character of Stormwater. A detailed description of the volume (quantity) and character (quality) of the stormwater runoff which is expected to occur from the proposed project is attached. The estimates of stormwater runoff quality and quantity are based on the area and type of impervious cover. Include the runoff coefficient of the site for both pre-construction and post-construction conditions.

Wastewater to be generated by the Proposed Project

14. The character and volume of wastewater is shown below:

<u> </u>	Gallons/day
0 % Industrial	Gallons/day
<u>0</u> % Commingled	Gallons/day
TOTAL gallons/day	

15. Wastewater will be disposed of by:

MA On-Site Sewage Facility (OSSF/Septic Tank):

Attachment C - Suitability Letter from Authorized Agent. An on-site sewage facility will be used to treat and dispose of the wastewater from this site. The appropriate licensing authority's (authorized agent) written approval is attached. It states that the land is suitable for the use of private sewage facilities and will meet or exceed the requirements for on-site sewage facilities as specified under 30 TAC Chapter 285 relating to On-site Sewage Facilities.

NA Each lot in this project/development is at least one (1) acre (43,560 square feet) in size. The system will be designed by a licensed professional engineer or registered sanitarian and installed by a licensed installer in compliance with 30 TAC Chapter 285.

NA Sewage Collection System (Sewer Lines):

- MA Private service laterals from the wastewater generating facilities will be connected to an existing SCS.
- NA Private service laterals from the wastewater generating facilities will be connected to a proposed SCS.
- MA The SCS was previously submitted on_____.
- MA The SCS was submitted with this application.
- MA The SCS will be submitted at a later date. The owner is aware that the SCS may not be installed prior to Executive Director approval.

MA The sewage collection system will convey the wastewater to the _____ (name) Treatment Plant. The treatment facility is:

N/A	Existing.
N/A	Proposed

16. \square All private service laterals will be inspected as required in 30 TAC §213.5.

Site Plan Requirements

Items 17 – 28 must be included on the Site Plan.

17. \square The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = <u>80</u>'.

- 18. 100-year floodplain boundaries:
 - Some part(s) of the project site is located within the 100-year floodplain. The floodplain is shown and labeled.
 - No part of the project site is located within the 100-year floodplain.

The 100-year floodplain boundaries are based on the following specific (including date o	сf
material) sources(s):	

- 19. The layout of the development is shown with existing and finished contours at appropriate, but not greater than ten-foot contour intervals. Lots, recreation centers, buildings, roads, open space, etc. are shown on the plan.
 - The layout of the development is shown with existing contours at appropriate, but not greater than ten-foot intervals. Finished topographic contours will not differ from the existing topographic configuration and are not shown. Lots, recreation centers, buildings, roads, open space, etc. are shown on the site plan.
- 20. All known wells (oil, water, unplugged, capped and/or abandoned, test holes, etc.):
 - MA There are _____ (#) wells present on the project site and the locations are shown and labeled. (Check all of the following that apply)
 - MA The wells are not in use and have been properly abandoned.
 - MA The wells are not in use and will be properly abandoned.
 - $\overline{\mathbb{N}/\mathbb{A}}$ The wells are in use and comply with 16 TAC §76.
 - There are no wells or test holes of any kind known to exist on the project site.
- 21. Geologic or manmade features which are on the site:
 - All sensitive geologic or manmade features identified in the Geologic Assessment are shown and labeled.
 - No sensitive geologic or manmade features were identified in the Geologic Assessment.
 - Attachment D Exception to the Required Geologic Assessment. A request and justification for an exception to a portion of the Geologic Assessment is attached.

- 22. X The drainage patterns and approximate slopes anticipated after major grading activities.
- 23. 🔀 Areas of soil disturbance and areas which will not be disturbed.
- 24. 🔀 Locations of major structural and nonstructural controls. These are the temporary and permanent best management practices.
- 25. 🔀 Locations where soil stabilization practices are expected to occur.
- 26. MA Surface waters (including wetlands).

N/A

27. NA Locations where stormwater discharges to surface water or sensitive features are to occur.

There will be no discharges to surface water or sensitive features.

28. 🔀 Legal boundaries of the site are shown.

Administrative Information

- 29. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 30. Any modification of this WPAP will require Executive Director approval, prior to construction, and may require submission of a revised application, with appropriate fees.



SECTION 4: WATER POLLUTION ABATEMENT APPLICATION FORM (TCEQ-0584) ATTACHMENT A

FACTORS AFFECTING SURFACE WATER QUALITY

Potential Sources of Pollutants During Construction:

- 1. Soil, erosion due to construction.
- 2. Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle drippings.
- 3. Hydrocarbons from asphalt paving operations.
- 4. Miscellaneous trash and debris from construction and material wrappings.
- 1. Proposed sewer connection.
- 2. Portable toilet spills.

Potential Sources of Pollutants After Construction:

- 1. Traffic related pollutants from cars, roads, and driveways.
- 2. Improper disposal of trash.
- 3. Pesticides, herbicides and fertilizers.



SECTION 4: WATER POLLUTION ABATEMENT APPLICATION FORM (TCEQ-0584) ATTACHMENT B

VOLUME AND CHARACTER OF STORM WATER

In existing conditions, the 7.59-acre site is mostly underdeveloped except for approximately 32,303 SF of existing impervious cover within the Limits of Construction. Based on existing topography the site is divided into Existing and Proposed Drainage Areas. Existing having one and proposed having three drainage areas. Where it is ultimately discharged onto Upper Leon Creek.

In proposed conditions, the drainage areas will be similar to existing conditions. The weighted runoff coefficients, time of concentration, and storm water runoff generated from each drainage area in existing and proposed conditions are described below.

PRE-CONSTRUCTION CONDITIONS FOR 25-YEAR RAINFALL EVENT (EA-1)

Rational Method (Q=ciA)

- Area (A) = 2.19 Acres
- Runoff Coefficient (c) = 0.58
- Time of Concentration (tc) = 14.1
- Rainfall Intensity (i) = 7.57

Runoff Volume (Q) = (0.58)(7.57)(2.19) = 9.62 cfs

PRE-CONSTRUCTION CONDITIONS FOR 25-YEAR RAINFALL EVENT (EA-2)

Rational Method (Q=ciA)

- Area (A) = 1.26 Acres
- Runoff Coefficient (c) = 0.96
- Time of Concentration (tc) = 5.0
- Rainfall Intensity (i) = 11

Runoff Volume (Q) = (0.96)(11)(1.26) = 12.99 cfs
POST-CONSTRUCTION CONDITIONS FOR 25-YEAR RAINFALL EVENT (UA-1)

Rational Method (Q=ciA)

- Area (A) = 2.19 Acres
- Runoff Coefficient (c) = 0.74
- Time of Concentration (tc) = 14.1
- Rainfall Intensity (i) = 7.57

Runoff Volume (Q) = (0.74)(7.57)(2.19) = 12.26 cfs

POST-CONSTRUCTION CONDITIONS FOR 25-YEAR RAINFALL EVENT (UA-2)

Rational Method (Q=ciA)

- Area (A) = 1.23 Acres
- Runoff Coefficient (c) = 0.96
- Time of Concentration (tc) = 5
- Rainfall Intensity (i) = 11

Runoff Volume (Q) = (0.96)(11)(1.23) = 12.99 cfs



SECTION 4: WATER POLLUTION ABATEMENT APPLICATION FORM (TCEQ-0584) ATTACHMENT C

SUITABILITY LETTER FROM AUTHORIZED AGENT

This attachment does not apply to this submittal. There will be no OSSF on this site.



SECTION 4: WATER POLLUTION ABATEMENT APPLICATION FORM (TCEQ-0584) ATTACHMENT D

EXCEPTION TO THE REQUIRED GEOLOGIC ASSESSMENT

Ethium Building

SUB EDAQ - Bexar - EControls LLC - 10/31/2011 Texas Commission on Environmental Quality Investigation Report

EControls, LLC CN603978057

ECONTROLLS LLC

RN102763380

Investigation #964415

Investigator: CHARLYNE FRITZ

Incident #

Site Classification COMMERCIAL

SIC Code: 8711 NAIC Code: 334513

Conducted: 10/31/2011 -- 01/19/2012

Program(s): EDWARDS AQUIFER

Investigation Type : Site Assessment File Review

Additional ID(s): 13-11103101

Address: 5727 FARINON DR; SAN ANTONIO, TX 78249 Location: .25 ML W OF IH 10 NEAR DE ZAVALA RD

Phone Work

Fax

Fax

Work

Activity Type : REGION 13 - SAN ANTONIO EAPPGRAST - EAPP Grant AST Plan Review

Principal(s) :

Role

RESPONDENT

ECONTROLS LLC

Name

Title

PE

ENTERPRISE

Name

GROUP MANAGER

<u>Contact(s) :</u>

Role

Regulated Entity Mail Contact

Regulated Entity Contact

Other Staff Member(s) : Role

Supervisor

Investigator Investigator QA Reviewer Supervisor LYNN BUMGUARDNER ELAINE GROSENHEIDE

ELAINE GROSENHEIDER AGNIESZKA HOBSON JAVIER ANGUIANO TODD JONES

Name

MR VINCE

FORSTER

LAMOUREUX

MR CHARLES P

Unit Name

Associated Check List

Checklist Name

PH HB 3200 HE POON

(210) 495-9772

(210) 495-9791

(210) 698-5544

(210) 698-5544

Investigation Comments :

Name of Project: EControls Inc.; Located on the west side of Farinon Drive, southwest of Silicon Dr. at 5757 Farinon Dr., San Antonio, Texas

Type of Plan: Request for the Approval of a Aboveground Storage Tank Facility (AST); 30 Texas Administrative Code (TAC) Chapter 213 Edwards Aquifer

Edwards Aquifer Protection Program San Antonio File No. 520.00; Investigation No. 964415; Regulated Entity No. RN102763380

ECONTROLLS LLC - SAN ANTONIO

10/31/2011 to 1/19/2012 Inv. # - 964415

Page 2 of 3

INTRODUCTION

The Texas Commission on Environmental Quality (TCEQ) has completed its review of the AST application for the above-referenced project submitted to the San Antonio Regional Office by Forster Engineering on behalf of EControls, LLC on October 31, 2011. Final review of the AST was completed after additional material was received on January 3, 2012. As presented to the TCEQ, the AST Facility Plan proposed in the application was prepared to be in general compliance with the requirements of 30 TAC §213.5(e). Therefore, based on the applicant's concurrence of compliance, the planning materials for construction of the proposed project and pollution abatement measures are hereby approved subject to applicable state rules and the conditions in the approval letter.

BACKGROUND

The ASTs are to be located on a 13.779 acre site. The larger site is located on the Edwards Aquifer recharge zone, contributing zone within the transition zone, and the transition zone. A water pollution abatement plan (WPAP) was approved by letter dated July 11, 1997 for a driveway entrance to De Zavala Rd., which was located on the recharge zone. No additional regulated development has occurred on the recharge zone or the transition zone within the contributing zone.

GENERAL FACILITY INFORMATION

Project Description

The project site is located on the Edwards Aquifer Transition Zone. The proposed AST Facility Plan includes the items listed in the table below.

AST Gallons Tank Material Contents of Tank

1 1,000 Steel Gasoline

2 1,000 Steel Gasoline

3 1,000 Steel Diesel Fuel

Total 3,000

Equivalent Protection

The described ASTs are double walled tanks with an internal steel tank surrounded by an HDPE liner and an external concrete layer (UL 142, ConVault Protected AST). The tank consists of a primary tank within a sealed secondary tank. Each tank's outer dimensions will be 11 feet in width, 5.6667 feet in width, and 4.333 feet in height. The 30 mil HDPE liner is separated from the steel tank by ¼ inch Styrofoam insulation. The HDPE liner and concrete liner will contain any product leaks from the primary tank. The tanks will also be equipped with a leak detection system.

The double-walled piping will extend outside the tank area and slope towards the adjacent building. The piping will be aboveground and in an open trench that is covered by a steel plate. Spill and overfill control will be provided by quarterly visual inspections of the tank and piping system and by having personnel onsite and actively watching the unloading and refueling activities. The planned spill response that will take place at the facility is provided in Attachment "E" (enclosed) of the AST Facility Plan Application (Response Actions to Spills).

Geology

An exception to submitting a geologic assessment was requested with the application. According to the request, the new tanks will be placed on existing concrete flatwork within the transition zone of the Edwards Aquifer. No new soil disturbance is necessary to install the tanks or the piping structure. The exception to the requirement of submitting a geologic assessment is granted based upon the existing site conditions.

ADDITIONAL INFORMATION

NOD 1 Sent: 12/08/2011; Received: 01/03/2012; Attached No Violations Associated to this Investigation **ECONTROLLS LLC - SAN ANTONIO** 10/31/2011 to 1/19/2012 Inv. # - 964415 Page 3 of 3

Signed Environmental Investigator

Date $\frac{1}{18/12}$

Signed upervisor

Date

Attachments: (in order of final report submittal)

- ____Enforcement Action Request (EAR)
- Letter to Facility (specify type) : ______

Investigation Report

- ____Sample Analysis Results
- ___Manifests
- _NOR

Maps, Plans, Sketches

Photographs

Correspondence from the facility

X Other (specify) : pplication

Temporary Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Kennon Gug lielno Date: 8-28-2023

Signature of Customer/Agent:

Regulated Entity Name: Ethium Building

Project Information

Potential Sources of Contamination

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

1. Fuels for construction equipment and hazardous substances which will be used during construction:

The following fuels and/or hazardous substances will be stored on the site: _____

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

TCEQ-0602 (Rev. 02-11-15)

1 of 5

Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.

- Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.
- K Fuels and hazardous substances will not be stored on the site.
- 2. X Attachment A Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.
- 3. Ma Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.
- 4. X Attachment B Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.

Sequence of Construction

- 5. X Attachment C Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.
 - For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.
 - For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.
- 6. X Name the receiving water(s) at or near the site which will be disturbed or which will receive discharges from disturbed areas of the project: <u>Upper Leon Creek</u>

Temporary Best Management Practices (TBMPs)

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. X Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

- A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.
- A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.
- A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.
- A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.
- 8. X The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.
 - Attachment E Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.
 - There will be no temporary sealing of naturally-occurring sensitive features on the site.
- 9. X Attachment F Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided.
- 10. X Attachment G Drainage Area Map. A drainage area map supporting the following requirements is attached:
 - If areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.
 - **WA** For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.
 - For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.
 - There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.

There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.

- 11. MA Attachment H Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached.
 - X N/A
- 12. X Attachment I Inspection and Maintenance for BMPs. A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.
- 13. All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.
- 14. X If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).
- 15. X Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.
- 16. X Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).

Soil Stabilization Practices

Examples: establishment of temporary vegetation, establishment of permanent vegetation, mulching, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or preservation of mature vegetation.

17. X Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. X Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. X Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

Administrative Information

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. X If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. X Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT A SPILL RESPONSE ACTIONS

In the event of accidental spills of hazardous materials or hydrocarbons, the contractor will be required to maintain a stockpile of sand material in the construction staging area. This sand material will be used to provide a dike to contain large spills and to provide an absorbent material that can be disposed of off the Edwards Aquifer Recharge, Contributing and Transition Zones during the cleanup process. The contractor will be required to contact the owner, who will notify the Texas Commission on Environmental Quality (TCEQ) in the event of a spill. It is required that all contaminated soils be removed from the project site and disposed of in accordance with applicable regulations off of the Edwards Aquifer Recharge, Contributing and Transition Zones. Below are measures outlined by TCEQ for spill prevention and response.

Education

- Be aware that different materials pollute in different amounts. Make sure that each employee knows what a "significant spill" is for each material they use, and what is the appropriate response for "significant" and "insignificant" spills. Employees should also be aware of when spills must be reported to the TCEQ. Information is available in 30 TAC 327.4 and 40 CFR 302.4.
- 2. Educate employees and subcontractors on potential dangers to humans and the environment from spills and leaks.
- 3. Hold regular meetings to discuss and reinforce appropriate disposal procedures (incorporate into regular safety meetings).
- 4. Establish a continuing education program to indoctrinate new employees.
- 5. Have contractor's superintendent or representative oversee and enforce proper spill prevention and control measures.

General Measures

- 1. To the extent that the work can be accomplished safely, spills of oil, petroleum products, substances listed under 40 CFR parts 110,117, and 302, and sanitary and septic wastes should be contained and cleaned up immediately.
- 2. Store hazardous materials and wastes in covered containers and protect from vandalism.
- 3. Place a stockpile of spill cleanup materials where it will be readily accessible.
- 4. Train employees in spill prevention and cleanup.
- 5. Designate responsible individuals to oversee and enforce control measures.
- 6. Spills should be covered and protected from stormwater runoff during rainfall to the extent that it doesn't compromise clean-up activities.
- 7. Do not bury or wash spills with water.
- 8. Store and dispose of used clean up materials, contaminated materials, and recovered spill material that is no longer suitable for the intended purpose in conformance with the provisions in applicable BMPs.
- Do not allow water used for cleaning and decontamination to enter storm drains or watercourses. Collect and dispose of contaminated water in accordance with applicable regulations.
- 10. Contain water overflow or minor water spillage and do not allow it to discharge into drainage facilities or watercourses.
- 11. Place Material Safety Data Sheets (MSDS), as well as proper storage, cleanup, and spill reporting instructions for hazardous materials stored or used on the project site in an open, conspicuous, and accessible location.
- 12. Keep waste storage areas clean, well-organized, and equipped with ample cleanup supplies as appropriate for the materials being stored. Perimeter controls, containment structures, covers, and liners should be repaired or replaced as needed to maintain proper function.

Cleanup

- 1. Clean up leaks and spills immediately.
- 2. Use a rag for small spills on paved surfaces, a damp mop for general cleanup, and

absorbent material for larger spills. If the spilled material is hazardous, then the used cleanup materials are also hazardous and must be disposed of as hazardous waste.

3. Never hose down or bury dry material spills. Clean up as much of the material as possible and dispose of properly. See the waste management BMPs in this section for specific information.

Minor Spills

- 1. Minor spills typically involve small quantities of oil, gasoline, paint, etc. which can be controlled by the first responder at the discovery of the spill.
- 2. Use absorbent materials on small spills rather than hosing down or burying the spill.
- 3. Absorbent materials should be promptly removed and disposed of properly.
- 4. Follow the practice below for a minor spill:
 - a. Contain the spread of the spill.
 - b. Recover spilled materials.
 - c. Clean the contaminated area and properly dispose of contaminated materials.

Semi-Significant Spills

Semi-significant spills still can be controlled by the first responder along with the aid of other personnel such as laborers and the foreman, etc. This response may require the cessation of all other activities. Spills should be cleaned up immediately:

- 1. Contain spread of the spill.
- 2. Notify the project foreman immediately.
- 3. If the spill occurs on paved or impermeable surfaces, clean up using "dry methods (absorbent materials, cat litter and/or rags). Contain the spill by encircling with absorbent materials and do not let the spill spread widely.
- 4. If the spill occurs in dirt areas, immediately contain the spill by constructing an earthen dike. Dig up and properly dispose of contaminated soil.
- 5. If the spill occurs during rain, cover spill with tarps or other material to prevent contaminating runoff.

Significant/Hazardous Spills

For significant or hazardous spills that are in reportable quantities:

1. Notify the TCEQ by telephone as soon as possible and within 24 hours at 512- 339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site.

- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.
- 3. Notification should first be made by telephone and followed up with a written report.
- 4. The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- 5. Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- 6. More information on spill rules and appropriate responses is available on the TCEQ website at: http://www.tnrcc.state.tx.us/enforcement/emergency_response.html

Vehicle and Equipment Maintenance

- 1. If maintenance must occur onsite, use a designated area and a secondary containment, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- 2. Regularly inspect onsite vehicles and equipment for leaks and repair immediately
- 3. Check incoming vehicles and equipment (including delivery trucks, and employee and subcontractor vehicles) for leaking oil and fluids. Do not allow leaking vehicles or equipment onsite.
- 4. Always use secondary containment, such as a drain pan or drop cloth, to catch spills or leaks when removing or changing fluids.
- 5. Place drip pans or absorbent materials under paving equipment when not in use.
- 6. Use absorbent materials on small spills rather than hosing down or burying the spill. Remove the absorbent materials promptly and dispose of properly.
- 7. Promptly transfer used fluids to the proper waste or recycling drums. Don't leave full drip pans or other open containers lying around.
- 8. Oil filters disposed of in trashcans or dumpsters can leak oil and pollute stormwater. Place the oil filter in a funnel over a waste oil-recycling drum to drain excess oil before disposal. Oil filters can also be recycled. Ask the oil supplier or recycler about recycling

oil filters.

9. Store cracked batteries in a non-leaking secondary container. Do this with all cracked batteries even if you think all the acid has drained out. If you drop a battery, treat it as if it is cracked. Put it into the containment area until you are sure it is not leaking.

Vehicle and Equipment Fueling

- 1. If fueling must occur on site, use designated areas, located away from drainage courses, to prevent the runon of stormwater and the runoff of spills.
- 2. Discourage "topping off" of fuel tanks.
- 3. Always use secondary containment, such as a drain pan, when fueling to catch spills/ leaks.



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602)

ATTACHMENT B

POTENTIAL SOURCES OF CONTAMINATION

Potential Sources of Pollutants During Construction:

- 5. Soil, erosion due to construction.
- 6. Oil, grease, fuel and hydraulic fluid contamination from construction equipment and vehicle drippings.
- 7. Hydrocarbons from asphalt paving operations.
- 8. Miscellaneous trash and debris from construction and material wrappings.
- 3. Proposed sewer connection.
- 4. Portable toilet spills.

Potential Sources of Pollutants After Construction:

- 4. Traffic related pollutants from cars, roads, and driveways.
- 5. Improper disposal of trash.
- 6. Pesticides, herbicides and fertilizers.



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT C SEQUENCE OF MAJOR ACTIVITIES

Intended Schedule or Sequence of Major Activities:

- 1. Installation of temporary BMPs
- 2. Site clearing Activities (Approximately 13.33 Acres)
- 3. Subgrade Preparation (earthwork, grading, street and drainage excavation and embankment) (Approximately 7.97 Acres)
- 4. Wet and Dry Utility Construction
- 5. Installation of Base Materials (Approximately 7.97 Acres)
- 6. Concrete (foundations, curbs, flatwork) (Approximately 0.274 Acres)
- 7. Building Construction
- 8. Topsoil, Irrigation and Landscaping (5.36 acres)
- 9. Site cleanup and Removal of temporary BMPs

SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT D

TEMPORARY BEST MANAGEMENT PRACTICES AND MEASURES

Silt fencing, construction staging area, concrete truck wash-out pit, and a temporary construction entrance/exit will be used in accordance with the latest edition TCEQ Technical Guidance Manual details and criteria, to prevent pollution of surface water and groundwater that originates both up-gradient and on-site.

Silt fence, construction entrance/exit, and a concrete truck wash-out pit shall be in place before the first phase of construction for the commercial site is to begin. The temporary construction entrance/exit, construction staging area and concrete washout-out pit will prevent sediments from flowing into public rights-of-way. The fencing will be installed downstream of cut/fill areas. The locations of the silt fence were based on the criteria to limit the drainage area of disturbed soil to ¼ acres per 100 linear feet of fencing.

No known wells were located during the Geologic Assessment Report. The Temporary and Permanent Pollution Abatement measures for construction are included in this section.



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT E

REQUEST TO TEMPORARY SEAL A FEATURE

This attachment does not apply to our submittal. There were no sensitive geologic features on the site.

Ethium Building



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT F STRUCTURAL PRACTICES

Structural BMPs will be used to limit runoff discharge of pollutants from exposed areas of the site. BMPs will be installed prior to soil disturbing construction activity. Silt fencing will be placed along the down-gradient sides of the property to prevent silt from escaping the construction area. Inlet protection will be placed on all storm water inlets to prevent pollutants from entering the stormwater drainage system. A temporary construction entrance will be placed at the site entry/exit point to reduce tracking onto adjoining streets. A construction staging area will be used onsite to perform all vehicle maintenance and for equipment and material storage. A concrete truck wash-out pit will be placed on site to provide containment and easier cleanup of waste from concrete operations. The location of all structural temporary BMP's is shown on the site plan within the attachments.



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602)

ATTACHMENT G

DRAINAGE AREA MAP

Ethium Building



as14	s14 Existing Time of Concentration Table PA_3												
Shall	ow Con	Concentrated Flow 1 Shallow Concentrated Flow 2 Channel Flow							Total				
edł ved	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	P ave dł Unpave d	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	L (ft)	T _c (min)		
aved	40	4.4	16.13	0.2	Paved	335	1.5	20.32	2.3	0	0	0.0	14.1
aved	0	1.0	16.13	0.0	Paved	0	1.0	20.32	0.0			0.0	5.0
$T_{sc} = \frac{L_{sc}}{3600 \text{KS}_{sc}^{0.5}} \qquad T_{ch} = \frac{L_{cl}}{3600}$						L _{ch} 3600 * V		T _t +T _{sc} +T _{ch}					

E Controls Atlas14 Existing Q Flow Table PA_3											
Drainage Area	l	Coefficient	Intensity				Q Flow				
Are a(s)	A (ac.)	С	l ₁ (in/hr)	l ₅ (in/hr)	l ₂₅ (In/hr)	l ₁₀₀ (in/hr)	Q ₁ (ft³/s)	Q ₅ (ft ³ /s)	Q ₂₅ (ft ³ /s)	Q ₁₀₀ (ft ³ /s)	
EA1	2.19	0.58	3.72	5.45	7.57	9.44	4.72	6.92	9.62	11.99	
EA2	1.23	0.96	5.34	7.88	11.00	13.79	6.31	9.31	12.99	16.28	
Q = CIA											



EA-#

X.XX ac

 $\langle X \rangle$

EXISTING DRAINAGE AREA # DRAINAGE AREA (Ac.)

EXISTING CONTOURS DRAINAGE AREA BOUNDARY PROJECT SITE BOUNDARY TIME OF CONCENTRATION 100 YEAR FLOODPLAIN ANALYSIS POINT

AUTHORIZED FOR N PRIOR APPROV/ NOI CIT ; NOT AUTI CONSTRUC FORMAL C 0 WGINC.COM PRELIMINARY NOT FOR CONSTRUCTION BIDDING, OR PERMIT PURPOSES. PREPARED UNDER THE SUPERVISION OF <u>WGI, INC.</u> ON 2024-11-06 49 AREA MAP AS ECONTROLS 5727 FARINON DRIVE ≻` ANTONIO, BEXAR COUNT EXISTING DRAINAGE Z EXH

0

AL



as14	s14 Proposed Time of Concentration Table PA_3												
Shall	hallow Concentrated Flow 1 Shallow Concentrated Flow 2 Channel Flow							ow	Total				
vedł aved	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	Pavedł Unpaved	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	L (ft)	V (ft/sec)	T _{ch} (min)	T _c (min)
aved	40	4.4	16.13	0.2	Paved	335	1.5	20.32	2.2	0	0	0.0	14.1
aved	0	1.0	16.13	0.0	Paved	0	1.0	20.32	0.0			0.0	5.0
$T_{sc} = \frac{L_{sc}}{3600 \text{KS}_{sc}^{0.5}}$										T _{ch} =	L _{ch} 3600 * V		T _t +T _{sc} +T _{ch}

E Controls Atlas14 Proposed Q Flow Table PA_3											
Drainage Are	a	Coefficient		nsity	Q Row						
Area(s)	A (ac.)	С	l ₁ (in/hr)	l ₅ (in/hr)	l ₂₅ (In/hr)	l ₁₀₀ (in/hr)	Q ₁ (ft³/s)	Q ₅ Q ₂₅ Q ₁₀₀ (ft ³ /s) (ft ³ /s) (ft ³ /s)			
PA1	2.19	0.69	3.72	5.46	7.58	9.46	5.62	8.24	11.46	14.29	
PA2	1.23	0.96	5.34	7.88	11.00	13.79	6.31	9.31	12.99	16.28	
Q = CIA											



PA-#	
X.XX ac	
 620	
Tc	
$\langle \mathbf{x} \rangle$	

PROPOSED DRAINAGE AREA # DRAINAGE AREA (Ac.)

EXISTING CONTOURS DRAINAGE AREA BOUNDARY PROJECT SITE BOUNDARY TIME OF CONCENTRATION 100 YEAR FLOODPLAIN ANALYSIS POINT

0 A AUTHORIZED FOR **APPROV** PRIOR ION E -RUC NOT AU CONSTRU FORMAL 6 WGINC.COM PRELIMINARY NOT FOR CONSTRUCTION BIDDING, OR PERMIT PURPOSES. PREPARED UNDER THE SUPERVISION OF <u>WGI, INC.</u> ON 2024-11-06 **4**9 MAP AREA AS ECONTROLS 5727 FARINON DRIVE VIO, BEXAR COUNTY, PROPOSED DRAINAGE Ъ ANTON Z

EXH



//				
2. 11				t in the second s
- 13 5-				
e com				
A STATE				
Sec.	1. A.L. I. Van			
	1 11174-21418			
				1
				1
380	- 367			
		A BASSING		
		8		
		8°		1
·	<i>i</i> ,	1 8		
			126	
1 1 2 AL				
	3		973-	
And the second s	900		6	1
967				•
	1.14	1.90		
968	4-2 1			
8 - 969			1 1 m (975
	·969	JLa	-07 1 013	
970				
200'			PSI	
on the		Ast 4	26	1.6
		200		
		A B B		
57		A E A A	12 CV	
			I THE	22
Se all		- 07, 01 ×		973-
972				11110
UA2			197	1/1/
1.23 ac				5 5 ST.
				11/1/
ALCA			/ / // .	11/1
		1 and 1		///
			R K	50
			, ² / ⁵	0 .011
				-
				1///
				////
		``		
			1//	
			X //	
		1///		

las14	Is14 Ultimate Time of Concentration Table PA_3												
Shall	ow Con	nce ntra t	ted Flow	v 1	Shalle	ow Con	ce ntra t	ed Flow	2	Cha	Total		
vedł aved	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	P ave dł Unpave d	L _{sc} (ft)	S _{sc} %	k	T _{sc} (min)	L (ft)	V (ft/sec)	T _{ch} (min)	T _c (min)
aved	37	4.4	16.13	0.2	Paved	346	1.5	20.32	2.3	0	0	0.0	14.1
aved	0	1.0	<mark>16.13</mark>	0.0	Paved	0	1.0	20.32	0.0			0.0	5.0
T _{sc} =	$T_{ch} = \frac{L_{sc}}{3600 \text{KS}_{sc}^{0.5}} \qquad T_{ch} = \frac{L_{ch}}{3600 \text{ * V}}$							T _t +T _{sc} +T _{ch}					

			,							
E Controls Atlas14 Ultimate Q Flow Table P										
Drainage Area	Drainage Area Coefficient Intensity									
Area(s)	A (ac.)	С	l ₁ (in/hr)	l ₅ (in/hr)	l ₂₅ (In/hr)	l ₁₀₀ (in/hr)	Q ₁ (ft ³ /s)			
UA1	2.19	0.74	3.71	5.45	7.57	9.44	6.02			
UA2	1.23	0.96	5.34	7.88	11.00	13.79	6.31			
Q = CIA										





SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT H

TEMPORARY SEDIMENTS POND(S) PLANS AND CALCULATIONS

This attachment does not apply to this submittal. There are no drainage areas with disturbed areas greater than 10 acres.

Ethium Building



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602) ATTACHMENT I INSPECTION AND MAINTENANCE OF BMPS

Inspection

Designated and qualified person(s) should inspect the Pollution Control Measures every seven (7) days and after each rainfall event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations and actions that will be taken as a result of the inspection should be kept with the TPDES data for the project. The general contractor will be responsible to review and reference sections 1.3 and 1.4 of "Complying with the Edwards Aquifer Rules: Technical Guidance on Best Management Practices" (TCEQ RG-348) for erosion and sedimentation control and maintenance as applicable.

Construction Entrance/Exit and Construction Staging Area Maintenance

- The entrance should be maintained in a condition, which will prevent tracking or flowing of sediment onto public right-of-way. This may require periodic top dressing with additional stone as conditions demand and repair and/or clean out of any measures used to trap sediment.
- 2. All sediment spilled, dropped, washed or tracked on to public right-of-ways should be removed immediately be the contractor.
- 3. When necessary, wheels should be cleaned to remove sediment prior to entrance onto public right-of-ways.
- 4. When washing is required, it should be done on an area stabilized with crushed stone that drains into an approved sediment trap or sediment basin.
- 5. All sediment should be prevented from entering any storm drain, ditch or watercourse by using approved methods.

Sediment Filter Structure Maintenance

- 1. Inspect all fencing weekly, and after any rainfall.
- 2. Remove sediment when buildup reaches 6 inches.
- 3. Replace any torn fabric or install a second line of fencing parallel to the torn section.

- 4. Replace or repair any sections crushed or collapsed in the course of construction activity. If a section of fence is obstructing vehicular access, consider relocating it to a spot where it will provide equal protection, but will not obstruct vehicles. A triangular filter dike may be preferable to a silt fence at common vehicle access points.
- 5. When construction is complete, the sediment should be disposed of in a manner that will not cause additional siltation and the prior location of the silt fence should be revegetated. The fence itself should be disposed of in an approved landfill.

SAMPLE INSPECTION REPORT

Name & Qualification of Inspector:

Date of Inspection:

Inspectors shall observe the following items on each inspection:

- Disturbed areas that have not been fully stabilized
- Areas used for storage of materials that are exposed to precipitation
- Control measures outlined in the site plan
- Locations where vehicles enter/exit the site

Inspectors shall denote if any corrective actions are required and when the action was completed.

Major Observations:

Corrective Actions Required:

Corrective Actions Performed:

Signature



SECTION 5: TEMPORARY STORMWATER SECTION (TCEQ-0602)

ATTACHMENT J

SCHEDULE OF INTERIM AND PERMANENT SOIL STABILIZATION PRACTICES

Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion in that portion of the site has temporarily or permanently ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporary or permanently ceased is precluded by weather conditions, stabilization measures shall be initiated as soon as practicable. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within 21 days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14th day after construction activity has temporarily or permanently ceased is precluded by seasonal arid conditions, stabilization measures shall be initiated as soon as practicable. Below are guidelines from TCEQ for the installation of sod to stabilized exposed areas.

Materials:

- Hydraulic Mulches: Wood fiber mulch can be applied alone or as a component of hydraulic matrices. Wood fiber applied alone is typically applied at the rate of 2,000 to 4,000 lb/acre. Wood fiber mulch is manufactured from wood or wood waste from lumber mills or from urban sources.
- Hydraulic Matrices: Hydraulic matrices include a mixture of wood fiber and acrylic polymer or other tackifier as binder. Apply as a liquid slurry using a hydraulic application machine (i.e., hydro seeder) at the following minimum rates, or as specified by the manufacturer to achieve complete coverage of the target area: 2,000 to 4,000 lb/acre wood fiber mulch, and 5 to 10% (by weight) of tackifier (acrylic copolymer, guar, psyllium, etc.)
- Bonded Fiber Matrix: Bonded fiber matrix (BFM) is a hydraulically applied system of fibers and adhesives that upon drying forms an erosion resistant blanket that promotes

vegetation and prevents soil erosion. BFMs are typically applied at rates from 3,000 lb/acre to 4,000 lb/acre based on the manufacturer's recommendation. A biodegradable BFM is composed of materials that are 100% biodegradable. The binder in the BFM should also be biodegradable and should not dissolve or disperse upon re-wetting. Typically, biodegradable BFMs should not be applied immediately before, during or immediately after rainfall if the soil is saturated. Depending on the product, BFMs typically require 12 to 24 hours to dry and become effective.

Installation:

- 1. Prior to application, roughen embankment and fill areas by rolling with a crimping or punching type roller or by track walking. Track walking shall only be used where other methods are impractical.
- 2. To be effective, hydraulic matrices require 24 hours to dry before rainfall occurs.
- 3. Avoid mulch over spray onto roads, sidewalks, drainage channels, existing vegetation, etc.

Inspection and Maintenance Guidelines:

- 1. Mulched areas should be inspected weekly and after each rain event to locate and repair any damage.
- 2. Areas damaged by storms or normal construction activities should be regarded and hydraulic mulch reapplied as soon as practical.

Permanent Stormwater Section

Texas Commission on Environmental Quality

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(C), (D)(II), (E), and (5), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Permanent Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: Kennon Guglielma Date: 8-28-7023

Signature of Customer/Agent

Regulated Entity Name: Ethium Building

Permanent Best Management Practices (BMPs)

Permanent best management practices and measures that will be used during and after construction is completed.

1. X Permanent BMPs and measures must be implemented to control the discharge of pollution from regulated activities after the completion of construction.

^{™A} N/A

2. X These practices and measures have been designed, and will be constructed, operated, and maintained to insure that 80% of the incremental increase in the annual mass loading of total suspended solids (TSS) from the site caused by the regulated activity is removed. These quantities have been calculated in accordance with technical guidance prepared or accepted by the executive director.

The TCEQ Technical Guidance Manual (TGM) was used to design permanent BMPs and measures for this site.

TCEQ-0600 (Rev. 02-11-15)

A technical guidance other than the TCEQ TGM was used to design permanent BMPs and measures for this site. The complete citation for the technical guidance that was used is: _____

^{N∕A} N∕A

3. X Owners must insure that permanent BMPs and measures are constructed and function as designed. A Texas Licensed Professional Engineer must certify in writing that the permanent BMPs or measures were constructed as designed. The certification letter must be submitted to the appropriate regional office within 30 days of site completion.

<mark>№A</mark> N/A

- 4. Where a site is used for low density single-family residential development and has 20 % or less impervious cover, other permanent BMPs are not required. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
 - The site will be used for low density single-family residential development and has 20% or less impervious cover.
 - The site will be used for low density single-family residential development but has more than 20% impervious cover.
 - The site will not be used for low density single-family residential development.
- 5. The executive director may waive the requirement for other permanent BMPs for multifamily residential developments, schools, or small business sites where 20% or less impervious cover is used at the site. This exemption from permanent BMPs must be recorded in the county deed records, with a notice that if the percent impervious cover increases above 20% or land use changes, the exemption for the whole site as described in the property boundaries required by 30 TAC §213.4(g) (relating to Application Processing and Approval), may no longer apply and the property owner must notify the appropriate regional office of these changes.
 - Attachment A 20% or Less Impervious Cover Waiver. The site will be used for multi-family residential developments, schools, or small business sites and has 20% or less impervious cover. A request to waive the requirements for other permanent BMPs and measures is attached.
 - MA The site will be used for multi-family residential developments, schools, or small business sites but has more than 20% impervious cover.
 - MA The site will not be used for multi-family residential developments, schools, or small business sites.
- 6. Attachment B BMPs for Upgradient Stormwater.

VA A description of the BMPs and measures that will be used to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site is attached.

|X| No surface water, groundwater or stormwater originates upgradient from the site and flows across the site, and an explanation is attached.

WA Permanent BMPs or measures are not required to prevent pollution of surface water, groundwater, or stormwater that originates upgradient from the site and flows across the site, and an explanation is attached.

7. X Attachment C - BMPs for On-site Stormwater.

- \times A description of the BMPs and measures that will be used to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff from the site is attached.
- WA Permanent BMPs or measures are not required to prevent pollution of surface water or groundwater that originates on-site or flows off the site, including pollution caused by contaminated stormwater runoff, and an explanation is attached.
- 8. NA Attachment D BMPs for Surface Streams. A description of the BMPs and measures that prevent pollutants from entering surface streams, sensitive features, or the aquifer is attached. Each feature identified in the Geologic Assessment as sensitive has been addressed.

X N/A

9. X The applicant understands that to the extent practicable, BMPs and measures must maintain flow to naturally occurring sensitive features identified in either the geologic assessment, executive director review, or during excavation, blasting, or construction.

 \times The permanent sealing of or diversion of flow from a naturally-occurring sensitive feature that accepts recharge to the Edwards Aquifer as a permanent pollution abatement measure has not been proposed.

- MA Attachment E Request to Seal Features. A request to seal a naturally-occurring sensitive feature, that includes, for each feature, a justification as to why no reasonable and practicable alternative exists, is attached.
- 10. X Attachment F Construction Plans. All construction plans and design calculations for the proposed permanent BMP(s) and measures have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer, and are signed, sealed, and dated. The plans are attached and, if applicable include:
 - Design calculations (TSS removal calculations)
 - TCEQ construction notes
 - All geologic features
 - All proposed structural BMP(s) plans and specifications

^{№/4} N/A

11. X Attachment G - Inspection, Maintenance, Repair and Retrofit Plan. A plan for the inspection, maintenance, repairs, and, if necessary, retrofit of the permanent BMPs and measures is attached. The plan includes all of the following:

Prepared and certified by the engineer designing the permanent BMPs and measures

- Signed by the owner or responsible party
- Procedures for documenting inspections, maintenance, repairs, and, if necessary retrofit
- X A discussion of record keeping procedures

N/A N/A

12. WA Attachment H - Pilot-Scale Field Testing Plan. Pilot studies for BMPs that are not recognized by the Executive Director require prior approval from the TCEQ. A plan for pilot-scale field testing is attached.

X N/A

13. Attachment I -Measures for Minimizing Surface Stream Contamination. A description of the measures that will be used to avoid or minimize surface stream contamination and changes in the way in which water enters a stream as a result of the construction and development is attached. The measures address increased stream flashing, the creation of stronger flows and in-stream velocities, and other in-stream effects caused by the regulated activity, which increase erosion that results in water quality degradation.

N∕A N/A

Responsibility for Maintenance of Permanent BMP(s)

Responsibility for maintenance of best management practices and measures after construction is complete.

14. The applicant is responsible for maintaining the permanent BMPs after construction until such time as the maintenance obligation is either assumed in writing by another entity having ownership or control of the property (such as without limitation, an owner's association, a new property owner or lessee, a district, or municipality) or the ownership of the property is transferred to the entity. Such entity shall then be responsible for maintenance until another entity assumes such obligations in writing or ownership is transferred.

^{N∕A} N/A

15. A copy of the transfer of responsibility must be filed with the executive director at the appropriate regional office within 30 days of the transfer if the site is for use as a multiple single-family residential development, a multi-family residential development, or a non-residential development such as commercial, industrial, institutional, schools, and other sites where regulated activities occur.

N/A N/A



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600)

ATTACHMENT A

20% OR LESS IMPERVIOUS COVER WAIVER

The proposed development does not generate less than 20% of impervious cover,

therefore, this attachment does not apply.


SECTION 6: Permanent Stormwater Section (TCEQ-0600) ATTACHMENT B

BMPS FOR UPGRADIENT STORMWATER

The proposed site is a local highpoint and as such, no runoff is expected to discharge onto the site originating from upgradient of the development.



SECTION 6: Permanent Stormwater Section (TCEQ-0600) ATTACHMENT C

BMPS FOR ON-SITE STORMWATER

The stormwater runoff generated from the site will be treated by a Vegetative Strip quality system. This System was designed according to the TCEQ Technical Guidance on Best Management Practices Manual.



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600)

ATTACHMENT D

BMPS FOR SURFACE STREAMS

This attachment does not apply to our submittal. There are no surface streams existing on site.



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600) ATTACHMENT E

REQUEST TO SEAL FEATURES

This attachment does not apply to our submittal. There were no sensitive geologic

features on the site.



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600)

ATTACHMENT F CONSTRUCTION PLANS

_	G			F	
	<u>OWNER / DEVELOPER</u> ECONTROLS 5757 FARINON DRIVE SAN ANTONIO, TEXAS 78249	ARCHITECT: STUDIO ELES 4926 SPICEWOOE AUSTIN, TEXAS 7) SPRINGS RD SUITE 101 8759		
	(210) 302-7720 CONTACT: BUZ LAMOUREAUX	(512) 750-8988 CONTACT: JEFF L	ANGHAM, AIA		
	CIVIL ENGINEER:	LANDSCAPE AF	RCHITECT:		
5	WGI, INC. 755 E. MULBERRY AVENUE, SUITE 501 SAN ANTONIO, TEXAS 78212 (210) 860-9224 CONTACT: AMANDA SALDIVAR, P.E.	WGI 4700 MUELLER BL AUSTIN, TX 7872 CONTACT: DARCY	LVD, SUITE 300 3 7 NUFFER, RLA		ECO
	SURVEYOR: D.A. MAWYER LAND SURVEYING 5151 W SH 46 NEW BRAUNFELS, TEXAS, 78132 CONTACT: DREW A. MAWYER, R.P.L.S				
4					
_					
3					
	THIS PROPERTY IS LOCATED WITHIN ZON	E "X", AREAS DETERI	MINED TO BE OF MINIMAL	FLOOD HAZARD, AS SHOWN ON F.I.R.N	1. PANEL NO. 48029C0404H,
	2002, ZONE "A" AND "X"				
	THIS FLOOD STATEMENT DOES NOT IMPLY FLOOD STATEMENT SHALL NOT CREATE LI	(THAT THE PROPER ABILITY ON THE PAF	TY AND/OR STRUCTURES T RT OF THE SURVEYOR.	HEREON WILL BE FREE FROM FLOODI	IG OR FLOOD DAMAGE. THIS
	WATERSHED: THIS PROPERTY IS LOCATED WITHIN THE	UPPER SAN ANTONI	O WATERSHED.		
		OFFER SAN ANTONI	o watekshed.		
	SURVEY BASIS: ALL BEARINGS ARE BASED THE TEXAS COO SURFACE USING A COMBINED SCALE FACT	ORDINATE SYSTEM, (OR OF 1.0001664081	GRID NORTH, SOUTH CENT 109.	RAL ZONE (4204), NAD83. ALL DISTAN	CES WERE ADJUSTED TO
	LOT 8 BLOCK 1 N.C.B. 14876 OF THE FARIN	NON SUBDIVISION, A	IS RECORDED IN BEXAR CO	DUNTY PLAT BOOK 9567 PAGE 87.	
2	UTILITY PROVIDERS:				
2	GAS: CPS ENERGY 500 McCULLOUGH AVENUE SAN ANTONIO, TX 78215 (210) 353-2376	WATER:	SAN ANTONIO WATER SY 2800 US HWY 281 NORTH SAN ANTONIO, TX 78298 (210) 704-7297	FIEM (SAWS) P.O. BOX 2449	
	ELECTRIC: CPS ENERGY 500 McCULLOUGH AVENUE SAN ANTONIO, TX 78215 (210) 353-2376	WASTEWATER:	SAN ANTONIO WATER SY 2800 US HWY 281 NORTH SAN ANTONIO, TX 78298 (210) 704-7297	STEM (SAWS) P.O. BOX 2449	
_	LAND USE SUMMARY: ZONING: I-1 WITH DETAIL PROPOSED SITE USE: INDUSTRIAL DEVELOPMENT AREA: 8.560 ACRES	UZROW AND OVERL	AY ERZD		
бмр	NOTES: 1. RELEASE OF THIS APPLICATION DOES APPLICANT. THE ENGINEER OF RECOM OR NOT THE APPLICATION IS REVIEW	NOT CONSTITUTE RD IS SOLELY RESPO /ED FOR CODE COMF	A VERIFICATION OF ALL DA NSIBLE FOR THE COMPLET PLIANCE BY CITY ENGINEER	ATA, INFORMATION, AND CALCULATION ENESS, ACCURACY, AND ADEQUACY OF RS.	NS SUPPLIED BY THE THEIR SUBMITTAL, WHETHER
533.00-C001-Cover_Sheet.	2. BY THE ACT OF SUBMITTING A BID FO MATERIAL SUPPLIERS THEY INTEND T CONTRACT DOCUMENTS AND HAVE FO BIDDER FURTHER WARRANTS THAT T SPECIFIED OR INDICATED HEREIN AR	or the proposed c o use have carefu dund them comple o the best of the e acceptable for a	ONTRACT, THE BIDDER WA JLLY AND THOROUGHLY RE TE AND FREE FROM ANY A IR SUBCONTRACTORS AND ALL APPLICABLE CODES AN	ARRANTS THAT THE BIDDER AND ALL S VIEWED THE DRAWINGS AND SPECIFI MBIGUITIES AND SUFFICIENT FOR THE MATERIAL SUPPLIERS KNOWLEDGE AL D AUTHORITIES.	UBCONTRACTORS AND CATIONS AND OTHER E PURPOSE INTENDED. THE L MATERIALS AND PRODUCTS
JIVIL\10-CAD\20-Shts\96	3. THE LOCATION OF ALL EXISTING UTI MAY NOT MATCH LOCATIONS AS CON INDIVIDUAL UTILITY, FOR ASSISTANC FIELD VERIFY LOCATIONS OF UTILITY	LITIES SHOWN ON T STRUCTED. THE CON TE IN DETERMINING CROSSING PRIOR T	HESE PLANS HAS BEEN BAS NTRACTOR SHALL CONTACT EXISTING UTILITY LOCATION O BEGINNING CONSTRUCT	GED UPON RECORD INFORMATION AND T THE "ONE CALL" SYSTEM @ 811, OR T ONS PRIOR TO BEGINNING CONSTRUC ION.	/or a field survey, and The owner of each Tion. Contractor shall
+ 3:42 PM TU 3.00 EControls North\C.	4. ALL CONSTRUCTION OPERATIONS SH HEALTH ADMINISTRATION. (OSHA ST REFERENCE MATERIALS MAY BE PURC 78207-4559).	ALL BE ACCOMPLISH ANDARDS MAY BE PL HASED FROM OSHA,	ED IN ACCORDANCE WITH JRCHASED FROM THE GOVI WASHINGTON SQUARE BL	APPLICABLE REGULATIONS OF THE U. ERNMENT PRINTING OFFICE; INFORMA VD, SUITE 203, 800 DOLOROSA ST, SA	5. OCCUPATIONS SAFETY AND TION AND RELATED N ANTONIO, TEXAS
0T DATE: 11/19/2024 0TTED BY: JOSE CAN AWING: P:\9600\9633	5. CONTRACTOR SHALL RESTORE ALL SI CONSTRUCTION. CONTRACTORS SHAL DIMENSIONS AND COLORS.	GNS AND PAVEMENT LL REFER TO THE TE	MARKINGS TO EXISTING (XAS MANUAL ON UNIFORM	CONDITIONS FOLLOWING THE COMPLE TRAFFIC CONTROL DEVICES (TMUTCD	TION OF EACH PHASE OF) FOR SIGN AND MARKING

ਨੋਟੋਟੋਟੋ

CONSTRUCTION DOCUMENTS FOR NTROLS - SITE WORK PERMIT

5711 FARINON DR. SAN ANTONIO, TEXAS 78249



SUBMITTAL DATE: NOVEMBER 19, 2024

SUBMITTED BY :

AMANDA SALDIVAR, P.E.

WGI, INC.

11/19/2024 LICENSED PROFESSIONAL ENGINEER NO. 146190 755 E. MULBERRY AVENUE, SUITE 501 SAN ANTONIO, TEXAS 78212



210.860.9224 I CERTIFY THAT THESE ENGINEERING DOCUMENTS ARE COMPLETE, ACCURATE AND ADEQUATE FOR THE INTENDED PURPOSES, INCLUDING CONSTRUCTION, BUT ARE NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO FORMAL CITY APPROVAL.



Call before you did

 $(\)$

OR

CIVIL SHEET INDEX				
SHEET NO.	SHEET NAME			
01	COVER SHEET			
02	PLAT			
03	GENERAL NOTES			
04	EXISTING CONDITIONS			
05	EROSION CONTROL PLAN			
06	DEMOLITION PLAN			
07	SITE & PAVING PLAN			
08	STORM & GRADING PLAN			
09	EROSION CONTROL DETAILS			
10	SITE DETAILS			
11	SITE DETAILS			

NOT AUTHORIZED FOC CONSTRUCTION PRIO	FORMAL CITY APPRO
210.860.9224 FIRM NO: F-15085	5710 WEST HAUSMAN ROAD, SUITE 115, SAN ANTONIO, TEXAS 78249
ECONTROLS - SITE WORK PERMIT 5711 FARINON DR. SAN ANTONIO, TEXAS 78249	COVER SHEET
SHEET	

01 OF 11

CAUTION: CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE LOCATION OF UNDERGROUND UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR AVOIDING ALL EXISTING UTILITIES BY CALLING DIGTESS @ 1-800-DIG-TESS FOR LOCATION OF ALL UTILITIES, AT LEAST 2 WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION.

5	253	22255: 0087 222012:0050225838 23/20/2095 8:84AA ERRY RICHIFF COUNTY CLERK EXRR CCUITY EXRR CCUITY ECCODICS EC	DE ZAVALA ROAD DE ZAVALA ROAD SANITA SEWER- EASEM I I I I I I I I I I I I I
_		арацор асесо	NORTH SCALE N.T.S. PROJECT SITE
			LOCATION MAP
4		-	C2 24'45'20" 760.00' 166.79' 328 37' 325 82' 53 C3 88'25'35" 15.00' 14 59' 23 15' 20.92' 53 C4 21'22'45" 730 00' 137 80' 272 39' 270 81' 53 C5 19'48'01" 730 00' 127 41' 252 27' 251 02' 53 C6 00'26'17" 1015 00' 3 88' 7.76' 7.76' 53
			SURVEY NOTES. COORDINATES ARE BASED ON 1983 NORTH AMERICAN DATUM FOR THE TEXAS SOL CENTRAL ZONE. BEARINGS BASED ON PLAT OF TECHNOLOGY PARK UNIT 1, RECORDED IN VOLU 9000, PAGES 80-82 DEED AND PLAT RECORDS, BEXAR COUNTY, TEXAS.
			STREETSCAPE NOTE. NO BUILDING PERMIT WILL BE ISSUED FOR THIS SITE UNTIL A STREETSCA PLAN HAS BEEN APPROVED IN ACCORDANCE WITH SECTION 35-512 OF T CITY OF SAN ANTONIO UNIFIED DEVELOPMENT CODE.
	•		THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (E.D.U.S) PA FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE AT THE SAN ANTONIO WAT SYSTEM UNDER THE PLAT NUMBER ISSUED BY DEVELOPMENT SERVICES. EDWARDS AQUIFER NOTE APPROXIMATELY 1.36 ACRES OF THIS SUBDIVISION IS WITHIN THE EDWAR
			AQUIFER RECHARGE ZONE.NO PERSON SHALL COMMENCE THE CONSTRUCTION OF ANY REGULATED ACTIVITY UNTIL AN EDWARDS AQUIFER PROTECTION PL ("WATER POLLUTION ABATEMENT PLAN" OR "WPAP") OR MODIFICATION TO APPROVED PLAN AS REQUIRED BY 30 TAC 213.5 OF THE TEXAS WATER COL OR LATEST REVISION THEREOF BEEN FILED WITH THE APPROPRIATE REGION TCEQ OFFICE, AND THE APPLICATION HAS BEEN APPROVED BY THE EXECUTI DIRECTOR OF THE TCEQ.
			CP3 NOTES. THE CITY OF SAN ANTONIO AS A PART OF ITS ELECTRIC AND GAS SYSTI (CITY PUBLIC SERVICE BOARD) IS HEREBY DEDICATED THE EASEMENTS AN RIGHT-OF-WAY FOR ELECTRIC AND GAS DISTRIBUTION AND SERVICE FACIL ITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT" "GAS EASEMENT", "ANCHOR EASEMENT", "SERVICE EASEMENT", "OVERHAN EASEMENT", "UTILITY EASEMENT" AND "TRANSFORMER EASEMENT", FOR T
			PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAININ REMOVING, INSPECTING, PATROLLING AND ERECTING POLES, HANGING O BURYING WIRES, CABLES, CONDUITS, PIPELINES OR TRANSFORMERS, EAU WITH ITS NECESSARY APPURTENANCES, TOGETHER WITH THE RIGHT OF IN GRESS AND EGRESS OVER SAID GRANTOR'S ADJACENT LAND, THE RIGHT RELOCATE SAID FACILITIES WITHIN SAID EASEMENT AND RIGHT-OF-WAY AREA AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THER OF OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WI
			THE EFFICIENCY OF SAID LINES OR APPURTENANCES THERETO. IT IS AGRE AND UNDERSTOOD THAT NO BUILDINGS, CONCRETE SLABS, OR WALLS WI BE PLACED WITHIN SAID EASEMENT AREAS. ANY C.P.S. MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED (C.P.S. EQUIPMENT, LOCATED WITHIN SAID EASEMENT, DUE TO CHANGES (GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON (
			PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUN ELEVATION ALTERATION. THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT AN EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CAB EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANG TO SUCH EASEMENTS ARE DESCRIBED BELOW:
			NONE AFFECTED DRAINAGE NOTES NO STRUCTURES, FENCES, WALLS OR OTHER OBSTRUCTIONS OF ANY KIND SHA BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS OR R.O.W. SHO ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS WHI
			ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENT AS APPROVE SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBL WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE TH RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY REMOVE ANY OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAN U EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SA
			Image Easements. Image Easements.



Bexar County Plat Book 9567 Page 87

В	А		
AT NO. Ø50318 LAT ESTABLISHING N SUBDIVISION ES OF LAND, MORE OR LESS, OUT OF A I FURTHER DESCRIBED AS TECHNOLOGY RDED IN VOLUME 9000, PAGES 80-82 TRACT FURTHER DESCRIBED AS TECHNOLOGY RDED IN VOLUME 9537, PAGE 148, RECORDS, BEXAR COUNTY, TEXAS.		NOT AUTHORIZED FOR CONSTRUCTION PRIOR TO	FORMAL CITY APPROVAL
SECTIONS OF THE DRAINAGE EASEMENT AS APPROVED, T THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. AND BEXAR COUNTY SHALL HAVE THE RIGHT OF IN- R GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY THIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND I OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS. R ELEVATION FOR RESIDENTIAL AND COMMERCIAL LOTS LEAST 1 FOOT HIGHER THAN THE COMPUTED WATER THE 100-YEAR ULTIMATE DEVELOPMENT FLOOD.		FIRM NO: F-15085	GINC.COM 15, SAN ANTONIO, TEXAS 78249
WAS PREVIOUSLY PLATIED AS TECHNOLOGY PARK UNIT-1 OLUME 9000, PAGES 80-82, AND AS HARRIS SUB- ED IN VOLUME 9537, PAGE 148, BEXAR COUNTY DEED E PROPERTY SHOWN ON THIS REPLAT HEREBY CERTIFY THAT WEND OR REMOVE ANY COVENANTS OR RESTRICTIONS. AT NO PORTION OF THIS REPLAT WAS LIMITED DURING THE BY AN INTERIM OR PERMANENT ZONING CLASSIFI- FOR NOT MORE THAT TWO RESIDENTIAL UNITS PER LOT, OR CEEDING PLAT WAS LIMITED BY DEED RESTRICTIONS TO MORE THAN TWO RESIDENTIAL UNITS PER LOT.			5710 WEST HAUSMAN ROAD, SUITE 1
ARINON SUBDIVISION ARINON SUBDIVISION ARINON ARINON SUBDIVISION ARINON		AMANDA SALDIV AMANDA	11/19/2024
A.D., 20 CHAIRMAN SECRETARY CHAIRMAN SECRETARY COUNTY CLERK OF BEXAR COUNTY, DO HEREBY AS FILED FOR RECORD IN MY OFFICE ON THE 2014 AS FILED FOR RECORD IN MY OFFICE ON THE 2014 AS FILED FOR RECORD IN MY OFFICE ON THE 2014 AS FILED FOR RECORD IN MY OFFICE ON THE 2014 AS FILED FOR RECORD IN MY OFFICE ON THE 2014 AS FILED FOR RECORD IN MY OFFICE ON THE 2014 TY, IN BOOK/VOLUME SUBJ ON PAGE SZ ITNESS MY HAND AND OFFICIAL SEAL OF OFFICE, THIS A.D., 20 CL. COUNTY CLERK, BEXAR COUNTY, TEXAS AD, 20 CL. COUNTY CLERK, BEXAR COUNTY, TEXAS MIDDIA MAN PREPARED BY PREPARED BY EVING ROAD ST 0152 DOB DOB DOB DOB DOB DOB DOB DOB		ECONTROLS - SITE WORK PERMIT 5711 FARINON DR. SAN ANTONIO, TEXAS 78249	PLAT
		SHEET	

C002

02 OF 11

GENERAL CONTRUCTION NOTES:	GENERAL UTILITY NOTES:
ENERAL NOTES: ALL CONSTRUCTION SHALL CONFORM TO THE CURRENT BEXAR COUNTY STANDARD SPECIFICATIONS FOR CONSTRUCTION.	1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL COMPLY TO ALL APPLICABLE CITY OF SAN ANTONIO R REQUIREMENTS FOR STREETS, SIDEWALKS, ALLEYS AND ROADWAY DESIGN (LATEST EDITIONS), THE TEXAS DEPARTMENT OF TRANSPORTATION STANDA (LATEST EDITIONS) THE SAN ANTONIO WATER SYSTEM (SAWS) SPECIFICATIONS FOR WATER WORKS CONSTRUCTION (LATEST EDITION)
NO EXTRA PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR IN THE PLANS, BUT NOT INCLUDED IN THE BID PROPOSAL. THIS INCIDENTAL WORK WILL BE REQUIRED AND HALL BE INCLUDED IN THE PAY ITEM TO WHICH IT RELATES.	2. THE LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE UNES AS REQUIRED FOR
THE CONTRACTOR SHALL PROVIDE ACCESS FOR THE DELIVERY OF MAIL BY THE U.S. POSTAL SERVICE.	NOTIFY THE ENGINEER OF ANY CONFLICTS IMMEDIATELY. ANY DAMAGE BY THE CONTRACTOR TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
AVING, CURBS, SHRUBS, BUSHES OR DRIVEWAYS. (NO SEPARATE PAY ITEM.)	3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCT PROJECT.
ECIDED UPON IN THE FIELD BY THE CONTRACTOR, USING THE "TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES." THE CITY'S CONSTRUCTION INSPECTOR AND TRAFFIC NGINEERING IN THE OPINION OF THE TRAFFIC ENGINEERING REPRESENTATIVE WILL ONLY BE RESPONSIBLE TO INSPECT BARRICADES AND SIGNS. IF, IN THE OPINION OF THE	4. CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE SYSTEMS WHETHER SHOWN ON PLANS OR NOT.
RAFFIC ENGINEERING REPRESENTATIVE AND THE CONSTRUCTION INSPECTOR, THE BARRICADES DO NOT CONFORM TO ESTABLISHED STANDARDS OR PUBLIC, THE CONSTRUCT ISPECTOR SHALL HAVE THE OPTION TO STOP OPERATIONS UNTIL SUCH TIME AS THE CONDITIONS ARE CORRECTED.	 5. ALL UTILITIES SHALL BE INSTALLED PRIOR TO PAVEMENT CONSTRUCTION. 6. ALL UTILITY CONNECTIONS SHALL BE COORDINATED WITH THE MECHANICAL AND ELECTRICAL PLANS. NOTIFY ENGINEER OF ANY CONFLICTS PRIOR TO CONF
IF THE NEED ARISES, ADDITIONAL BARRICADES AND DIRECTIONAL DEVICES MAY BE ORDERED BY THE TRAFFIC ENGINEERING REPRESENTATIVE AT THE CONTRACTOR'S XPENSE.	7. THE CONTRACTOR SHALL INSTALL ANY BENDS, FITTINGS, ETC. IN THE WATER & SEWER MAIN AS REQUIRED TO AVOID CONFLICTS WITH OTHER UTILITIES.
DUE TO FEDERAL REGULATIONS TITLE 49, PART 192.171 C.P.S. MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST PROTECT AND WORK AROUN NY GAS VALVES THAT ARE IN THE PROJECT AREA.	 NO WATER JETTING TO BACKFILL TRENCHES WILL BE ALLOWED ON THIS PROJECT. POLYVINYL CHLORIDE (PVC) SEWER PIPE SHALL BE SDR 26 FITTINGS AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JUNCTURES AND JOINTS JOIN
CONTRACTOR SHALL NOTIFY THE CITY INSPECTOR TWENTY FOR (24) HOURS PRIOR TO BACKFILL OF ANY UTILITY TRENCHES TO SCHEDULE FOR DENSITY TEST AS REQUIRED CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES, MARKS, ETC. IF ANY ARE DESTROYED OR REMOVED BY THE CONTRACTOR OR HIS EMPLOYEES, THEY SHALL E	D. USED. BE 10. WHEN SEWER LINES ARE INSTALLED IN THE VICINITY OF WATER MAINS, SUCH INSTALLATIONS SHALL BE IN ACCORDANCE WITH THE TEXAS COMMISSION
EPLACED AT THE CONTRACTOR'S EXPENSE.	QUALITY (TCEQ).
SAN ANTONIO WATER SYSTEM (SAWS) 233-2010	PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.
BEXAR METROPOLITAN WATER DISTRICT (BEXAR MET) 210-354-6538 210-357-5741	 ALL SPOIL AND OTHER UNSUITABLE MATERIAL FROM THIS WORK SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, AT HIS EXPENSE. ALL SERVICES ARE BROUGHT TO WITHIN 5 FEET OF THE BUILDING UNLESS OTHERWISE NOTED. REFERENCE MEP PLANS FOR UTILITY CONNECTIONS AT
• COSA DRAINAGE 210-207-8048 • TEXAS STATE WIDE ONE CALL LOCATOR 1-800-344-8377	14. WHETHER SHOWN ON THE PLANS OR NOT ALL CLEANOUT TOPS AND MANHOLES SHALL BE INSTALLED AT LEAST 3" ABOVE FINISHED GRADE OUTSIDE PAY WITH FINISHED GRADE WITHIN THE PAVEMENT AREAS. TOPS WITHIN PAVEMENT SHALL BE TRAFFIC RATED.
-CITY PUBLIC SERVICE ENERGY -TIME WARNER	15. SANITARY SEWER SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE INTERNATIONAL PLUMBING CODE AND THE SAN ANTONIO WATER SYSTEM PL SPECIFICATIONS, AND AS DIRECTED BY THE PLUMBING INSPECTOR.
-AT&T	16. THRUST BLOCKING SHALL BE INSTALLED IN ACCORDANCE WITH SAN ANTONIO WATER SYSTEM SPECIFICATIONS.
-MCI 1. THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM AVAILABLE RECORDS AND ARE NOT GUARANTEED, BUT SHALL BE INVESTIGATED AND VEDICED BY THE CONTRACTOR REFORM AVAILABLE AND SOLD AND SOLD THE MUNITENANCE FOR ANY DAMAGE TO	17. UTILITY CONTRACTOR SHALL COORDINATE WITH CPS ENERGY FOR THE GAS AND ELECTRICAL SERVICE.
IN LOTIGATED AND VERIFIED DT THE CONTRACTOR DEFORE STARTING WORK. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY DAMAGE TO AND FOR THE MAINTENANC ND PROTECTION OF THE EXISTING UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS. LOCATION AND DEPTH OF EXISTING UTILITIES SHOWN HERE ARE APPROXIMATE ONL CTUAL LOCATIONS AND DEPTHS MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION AND HE SHALL BE RESPONSIBLE FOR PROTECTION OF SAME DURING	Y. 19. DOMESTIC WATER SHALL BE PVC C900 FOR PIPES < 12" OR C905 FOR PIPES \ge 12" OR COPPER TUBING AS SPECIFIED IN THE SAWS STANDARD SPECIFICA?
ONSTRUCTION. 2. ALL WASTE MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE HIS SOLE RESPONSIBILITY TO DISPOSE OF THIS MATERIAL OFF THE LIMITS OF THE	20. CLEANOUTS SHALL BE TWO-WAYS AND INSTALLED IN ACCORDANCE WITH COSA PLUMBING CODE (EVERY 100') & AS DIRECTED BY PLUMBING INSPECTOR
ROJECT. NO WASTE MATERIAL SHALL BE PLACED IN EXISTING LOWS THAT WILL BLOCK OR ALTER FLOW LIMITS OF EXISTING ARTIFICIAL OR NATURAL DRAINAGE.	21. FIRE LINE SHALL BE PVC C900, CLASS 200 AND SHALL COMPLY WITH AWWA STANDARDS AND SHALL WITHSTAND A WORKING PRESSURE OF NOT LESS TH 22. CONTRACTOR SHALL MAINTAIN "AS-BUILT" DRAWINGS THROUGHOUT THE COURSE OF CONSTRUCTION & SHALL SUBMIT SAME TO THE ENGINEER FOR AP
4. THE CONTRACTOR SHALL MAINTAIN ALL ADJOINING STREETS AND TRAVELLED ROUTES FREE FROM SPILLED AND/OR TRACKED CONSTRUCTION MATERIALS AND/OR DEBRIS.	FINAL ACCEPTANCE BY OWNER.
2. IN THE CONTRACTOR ENCOUNTERS ANT ARCHAEOLOGICAL DEPOSITS DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR MUST STOP EXCAVATION IMMEDIATELY, ONTACT THE CITY INSPECTOR, AND CALL THE CITY HISTORIC PRESERVATION OFFICE AT 207-7306 OR 207-3327 FOR AN ARCHAEOLOGICAL INVESTIGATION. THE CONTRACTOR ANNOT BEGIN EXCAVATION AGAIN WITHOUT WRITTEN PERMISSION FROM THE CITY.	SAWS GENERAL SEWER NOTES
• IF MORE THAN THREE (3) DAYS ARE REQUIRED FOR INVESTIGATION (NOT INCLUDING HOLIDAY AND WEEKENDS) AND IF THE CONTRACTOR IS UNABLE TO WORK IN OTHER AREAS, THEN THE CONTRACTOR WILL BE ALLOWED TO NEGOTIATE FOR ADDITIONAL CONSTRUCTION TIME UPON WRITTEN REQUEST WITHIN TEN (10) DAYS AFTER THE FIL	RST GENERAL SECTION
NOTICE TO THE CITY OF ARCHAEOLOGICAL INVESTIGATION FOR EACH EVENT. • IF THE TIME REQUIRED FOR INVESTIGATION IS LESS THAN OR EQUAL TO THREE (3) DAYS FOR EACH EVENT, CONTRACT DURATION WILL NOT BE EXTENDED.	1. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:
5. IF SUSPECTED CONTAMINATION IS ENCOUNTERED DURING CONSTRUCTION OPERATIONS, BEXAR COUNTY SHALL BE NOTIFIED IMMEDIATELY WHEN CONTAMINATED SOILS ND/OR GROUNDWATER ARE ENCOUNTERED AT LOCATIONS NOT IDENTIFIED IN THE PLANS. THE NOTIFICATION SHOULD INCLUDE THE STATION NUMBER, TYPE OF CONTAMINATED EDIA, EVIDENCE OF CONTAMINATION AND MEASURES TAKEN TO CONTAIN THE CONTAMINATED MEDIA AND PREVENT PUBLIC ACCESS. THE CONTAMINATED SOIL AND/OR ROUNDWATER SHALL NOT BE REMOVED FROM THE LOCATION WITHOUT PRIOR BEXAR COUNTY APPROVAL.	 A. CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTR TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290. B. CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE." C. CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION." D. CURPENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION."
• THE CONTRACTOR MUST STOP THE EXCAVATION IMMEDIATELY AND CONTACT THE BEXAR COUNTY INSPECTOR. THE CONTRACTOR CANNOT BEGIN EXCAVATION ACTIVITI WITHOUT WRITTEN PERMISSION FROM THE CITY.	ES E. CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).
7. CONTRACTOR IS TO INCLUDE A MAILBOX POST BLOCKOUT FOR VACANT LOTS AND ALL RESIDENCES WHICH DO NOT HAVE MAILBOXES AT THE CURB. BLOCKOUTS ARE PROV OR FUTURE USE BY THE POST OFFICE.	10ED 2. THE CONTRACTOR SHALL OBTAIN SAWS STANDARD DETAILS FROM SAWS WEBSITE, HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHER DESIGN PLANS.
3. CONTRACTOR SHALL NOT REMOVE OR ADJUST ANY VIA FACILITIES. THE CONTRACTOR MUST CONTRACT VIA FOURTEEN DAYS PRIOR, FOR THE REMOVAL OF BENCHES, STOI OLES, OR ANY OTHER VIA FACILITIES THAT MAY BE PRESENT. PLEASE PROVIDE THIRTY DAYS PRIOR NOTICE FOR SHELTER REMOVAL (TELEPHONE NOS: (210) 362-2155 OR (210) 62-2096). THE CONTRACTOR WILL BE LIABLE FOR ANY DAMAGES TO VIA FACILITIES NOT REMOVED BY THE VIA. THE CONTRACTOR IS REQUIRED TO REPLACE ALL FLATWORK	 THE CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 233-3500, AND PROVIDE NOTIFIC/ THE CONTRACTOR WILL USE TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO EXCAVATION.
EMOVED OR DAMAGED IN THE COURSE OF EXECUTING THE CONTRACT UNLESS OTHERWISE NOTED BY VIA. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROTECTING VIA ACILITIES IF ADJACENT TO THE WORK AREA.	4. LOCATIONS AND DEPTHS OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCA MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCA LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS
GENERAL GRADING & DRAINAGE NOTES: ALL GRADES AND CONTOURS SHOWN ARE FINAL, TOP OF FINISHED SURFACE ELEVATIONS, CONTRACTOR SHALL SUBTRACT PAVEMENT, BASE, TOPSOIL, MULCH, ETC. TO OBTAIN PROPER SUBGRADE ELEVATIONS.	 THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CON SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FO INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
POSITIVE DRAINAGE SHALL BE MAINTAINED ON ALL AREAS WITHIN THE SCOPE OF THIS PROJECT. DRAINAGE SHALL BE DIRECTED AWAY FROM ALL BUILDING FOUNDATIONS. CONTRACTOR SHOULD TAKE PRECAUTIONS NO TO ALLOW ANY PONDING OF WATER. MINIMUM SLOPE 0.50%.	SAN ANTONIO WATER SYSTEM: SAWS UTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES
NO ABRUPT CHANGE OF GRADE SHALL OCCUR.	COSA DRAINAGE 207-8048 COSA TRAFFIC SIGNAL OPERATIONS 207-7720
ALL DISTURBED AREAS SHALL BE REVEGETATED, BY THE CONTRACTOR, IN ACCORDANCE WITH PROJECT SPECIFICATIONS, AND LANDSCAPE ARCHITECTURAL PLANS. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL EXISTING DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLAN OR NOT. THE	TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811
CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHAL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE. ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT WHERE NOT SPECIFICALLY COVERED IN THE PROJECT SPECIFICATIONS SHALL	 OR BETTER CONDITION AS A RESULT OF DAMAGES DONE BY THE PROJECT'S CONSTRUCTION. ALL WORK IN TEXAS HIGHWAY DEPARTMENT AND BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION S PERMIT.
CONFORM TO ALL APPLICABLE CITY OF SAN ANTONIO SPECIFICATIONS FOR CONSTRUCTION, TXDOT STANDARD SPECIFICATIONS, AND/OR BEXAR COUNTY PUBLIC WORKS STANDARD SPECIFICATIONS.	8. THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TR
THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH NECESSARY UTILITY COMPANIES FOR PROVIDING TEMPORARY UTILITY SERVICES DURING CONSTRUCT CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY QUESTIONS THAT MAY ARISE CONCERNING THE INTENT, PLACEMENT, OR LIMITS, OF DIMENSIONS OR GRAD	10N. 9. THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PE
NECESSARY FOR CONSTRUCTION OF THIS PROJECT. THE CONTRACTOR SHALL SAW CUT EXISTING PAVEMENT AT NEW PAVEMENT AND CURB JUNCTURES. NO JAGGED OR IRREGULAR CUTS IN PAVEMENT WILL BE ACCEPTED	10. ANY WORK COMPLETED WITHOUT PRIOR WRITTEN AUTHORIZATION WHICH IS NOT INCLUDED IN THESE PLANS AND SPECIFICATIONS WILL NOT BE COMPE ANTONIO WATER SYSTEM.
). THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS PROJE	CT. 11. HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO
	CONSTWORKREQ@SAWS.ORG. WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST
3. SEE CIVIL COVER SHEET FOR PROJECT BENCHMARK.	REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.
4. CONTRACTOR TO RAISE/LOWER ALL UTILITY BOXES, COVERS, GRATES, VALVES BOXES, MANHOLES, CLEANOUTS, ETC., TO MATCH PROPOSED FINISHED GRADE ELEVATIONS.	ANT AND ALL SAVIS UTLITT WORK INSTALLED WITHOUT HULIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION
ALL DISTURBED AREAS WHICH ARE NOT TO BE PAVED SHALL BE COVERED WITH 6" MIN. CLEAN TOPSOIL UNLESS OTHERWISE NOTED. CUT OR FILL SHALL BE ADJUSTED TO ALLOW FOR TOPSOIL IN ORDER TO MAINTAIN PROPOSED ELEVATIONS. AREAS FOR LANDSCAPING SHOULD BE IN ACCORDANCE WITH THE LANDSCAPE ARCHITECTS PLANS.	
 PROVIDE THE REQUIRED MINIMUM DENSITY AND MOISTURE CONTENT OF COMPACTED FILL IN ACCORDANCE WITH THE SOILS REPORT AND THE REQUIREMENTS OF THE PROFESSIONAL ENGINEER (GEOTECH AND CIVIL). FOR SOILS INFORMATION REFER TO GEOTECHNICAL REPORT PREPARED BY RABA KISTNER, INC. DATED APRIL 23, 2017, PROJECT #ASA-20-013-00. 	 PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS INSPECTION AND/OR SAWS PRODUCTION ONE WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THI COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY. SAWS PRODUCTION CONTROL CENTER 233-2016
	13. ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS-CONTAINING MATERIAL (ACM), MAYBE LOCATE LIMITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURB
ACCESSIBILITY REQUIREMENTS	OCCURS, PAYMENT FOR SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFICATION FOR HANDLING ASBESTOS
CCESSABILITY REQUIREMENTS THE CONTRACTOR SHALL PROVIDE AND MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES TO LOCAL RESIDENCES AND BUSINESSES	WITH A CAP/PLUG. (NSPI)
WHEN THE WORK REQUIRES THE EXCAVATION OF THE STREET AND THE REMOVAL OF THE EXISTING DRIVEWAY APPROACHES AND SIDEWALKS, THE CONTRACTOR SHALL BI ESPONSIBLE FOR PROVIDING TEMPORARY ALL-WEATHER ACCESS TO THE BUSINESSES AND RESIDENCES. THE TEMPORARY DRIVEWAY APPROACHES SHALL BE CONSTRUCTED	E
ITH FLEXIBLE BASE OR GRAVEL MATERIAL AT NO SEPARATE COST TO THE CITY. PRIOR TO INITIATING THE CONSTRUCTION OF NEW DRIVEWAY APPROACHES, CONTRACTOR SHALL GIVE ADVANCE WARNING IN PERSON, OR IN WRITING. OF AT LEAST 48 HO	RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:
O EACH RESIDENCE THAT WILL BE IMMEDIATELY AFFECTED, SO THAT ALTERNATE PLANS MAY BE MADE BY THE RESIDENTS. FOR BUSINESSES WITH MORE THAN ONE DRIVEWAY, AT LEAST ONE DRIVEWAY SHALL REMAIN OPEN WHILE THE OTHER NEW DRIVEWAY APPROACHES ARE CONSTRUCTED. I USINESSES WITH ONLY ONE DRIVEWAY, THE NEW DRIVEWAY APPROACH SHALL BE CONSTRUCTED IN HALF WIDTHS, UNLESS A TEMPORARY ASPHALT DRIVEWAY IS FIRST INSTAL T NO SEPARATE COST TO THE CITY.	 A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210)233-2015. PROVIDE THE ADD AND AN ESTIMATED VOLUME OR FLOW. FOR B. ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO. C. CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS. D. CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOI
	 E. CLEAN THE AFFECTED SEVER MAINS AND REMOVE ANY DEBRIS. F. MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MA DIRECTION) WITHIN 24 HOURS. SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION. THEY WILL BE RESPONSIBLE FOR ALL COSTS INCLUSION.
	 INCLUDING ANY FINES FROM EPA. 16. THE CONTRACTOR SHALL PROVIDE BYPASS PUMPING OF SEWAGE AROUND EACH SEGMENT OF PIPE TO BE REPLACED, IN ACCORDANCE WITH SAWS S' SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING". PAYMENT FOR SUCH WORK WILL BE MADE UNDI "SANITARY SEWEP (BYPASS PUMPING)" (LIMP SIM) AS DED SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING". PAYMENT FOR SUCH WORK WILL BE MADE UNDI "SANITARY SEWEP (BYPASS PUMPING)" (LIMP SIM) AS DED SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING". PAYMENT FOR SUCH WORK WILL BE MADE UNDI "SANITARY SEWEP (BYPASS PUMPING)" (LIMP SIM) AS DED SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEVER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING". PAYMENT FOR SUCH WORK WILL BE MADE UNDI "SANITARY SEVER CONSTRUCTION, AS DED SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEVER CONSTRUCTION."
	SANTIARY SEWER (BYPASS PUMPING)" (LUMP SUM) AS PER SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM PUMPING".
	17. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIV AND/OR SAWS PRODUCTION GROUPS AT LEAST ONE WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQU RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUEN

RAL UTILITY NOTES:

JIREMENTS FOR STREETS, SIDEWALKS, ALLEYS AND ROADWAY DESIGN (LATEST EDITIONS), THE TEXAS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION EST EDITIONS), THE SAN ANTONIO WATER SYSTEM (SAWS) SPECIFICATIONS FOR WATER WORKS CONSTRUCTION (LATEST EDITION) LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES MUST BE VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND IFY THE ENGINEER OF ANY CONFLICTS IMMEDIATELY. ANY DAMAGE BY THE CONTRACTOR TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OF NOT, SHALL BE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ALL PERMITS, TESTS, APPROVALS AND ACCEPTANCES REQUIRED TO COMPLETE CONSTRUCTION OF THIS

UTILITY CONNECTIONS SHALL BE COORDINATED WITH THE MECHANICAL AND ELECTRICAL PLANS. NOTIFY ENGINEER OF ANY CONFLICTS PRIOR TO CONSTRUCTION. E CONTRACTOR SHALL INSTALL ANY BENDS, FITTINGS, ETC. IN THE WATER & SEWER MAIN AS REQUIRED TO AVOID CONFLICTS WITH OTHER UTILITIES. (NO SEPARATE PA

YVINYL CHLORIDE (PVC) SEWER PIPE SHALL BE SDR 26. FITTINGS AND JOINTS SHALL CONFORM TO COMPATIBLE SDR 26 PIPE. SOLVENT CEMENTS JOINTS SHALL NOT BE

IEN SEWER LINES ARE INSTALLED IN THE VICINITY OF WATER MAINS, SUCH INSTALLATIONS SHALL BE IN ACCORDANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL

TO FEDERAL REGULATION TITLE 49, PART 192.181, CITY PUBLIC SERVICE ENERGY (CPS) MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTOR MUST DTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.

ATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY TH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:

CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290.

- CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE. CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION."
- CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION." CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).

CONTRACTOR SHALL OBTAIN SAWS STANDARD DETAILS FROM SAWS WEBSITE, HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS. UNLESS OTHERWISE NOTED WITHIN GIGN PLANS.

CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 233-3500, AND PROVIDE NOTIFICATION PROCEDURES CONTRACTOR WILL USE TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO EXCAVATION.

ATIONS AND DEPTHS OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS T BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE

CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER DWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT ORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES

SA TRAFFIC SIGNAL OPERATIONS 207-7720 XAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811

CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGIN. BETTER CONDITION AS A RESULT OF DAMAGES DONE BY THE PROJECT'S CONSTRUCTION.

WORK IN TEXAS HIGHWAY DEPARTMENT AND BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND

WORK COMPLETED WITHOUT PRIOR WRITTEN AUTHORIZATION WHICH IS NOT INCLUDED IN THESE PLANS AND SPECIFICATIONS WILL NOT BE COMPENSATED BY THE SAN

LIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO STWORKREQ@SAWS.ORG

R SECTION:

IOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS INSPECTION AND/OR SAWS PRODUCTION GROUPS AT LEAST WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL T TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.

WS PRODUCTION CONTROL CENTER 233-2016

BESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS-CONTAINING MATERIAL (ACM), MAYBE LOCATED WITHIN THE PROJEC ITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURBANCE OF THIS PIPE CURS, PAYMENT FOR SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFICATION FOR HANDLING ASBESTOS CEMENT PIPE".

LVE REMOVAL: WHERE THE CONTRACTOR IS TO ABANDON A WATER MAIN, THE CONTROL VALVE LOCATED ON THE ABANDONING BRANCH WILL BE REMOVED AND REPLACE TH A CAP/PLUG. (NSPI)

R SECTION:

- IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210)233-2015. PROVIDE THE ADDRESS OF THE SPILL
- AND AN ESTIMATED VOLUME OR FLOW. ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.
- CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS. CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS. CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS
- MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

IOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT 233-3500 D/OR SAWS PRODUCTION GROUPS AT LEAST ONE WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS ATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK

SAWS CRITERIA FOR SEWER MAIN CONSTRUCT WHERE A SEWER MAIN CROSSES OVER A WATER MAIN AND THE SEPAR THE WATER LINE SHALL BE CONSTRUCTED USING 150 PSI PRESSURE RA PRESSURE RING GASKET CONNECTIONS OR CORROSION PROTECTED M 150 PSI PRESSURE RATED PIPE AT LEAST EIGHTEEN (18) FEET IN LENGT

WHERE A SEMI-RIGID OR RIGID SEWER MAIN CROSSES UNDER A WATER THE INITIAL BACKFILL SHALL BE CEMENT STABILIZED SAND (TWO OR MOI NINE FEET OF THE WATER MAIN.

SEPARATE PAY ITEM).

- WHERE A SEWER MAIN CROSSES UNDER A WATER MAIN AND THE SEPAR IRON, DUCTILE IRON, OR PVC WITH A MINIMUM PRESSURE RATING OF 150 CENTERED ON THE WATER MAIN, SHALL BE PLACED NO CLOSER THAN S CONNECTIONS OR CORROSION PROTECTED MECHANICAL COUPLING DE PIPE OF A LENGTH GREATER THAN EIGHTEEN (18) FEET MAY BE CENTER
- WHERE A SEWER MAIN PARALLELS A WATER MAIN AND THE SEPARATIO SHALL BE CONSTRUCTED OF CAST IRON, DUCTILE IRON, OR PVC WITH A
- FEET BEYOND THE POINT OF CONFLICT. SHALL MAINTAIN A MINIMUM SE HORIZONTALLY, AND SHALL BE JOINED WITH PRESSURE RING GASKET C OR DUCTILE IRON MATERIAL.
- SANITARY SEWER MANHOLES SHALL NOT BE INSTALLED ANY CLOSER TH CORROSION PROTECTED MECHANICAL COUPLING DEVICES SHALL BE O

- SUPPLEMENTARY & ADDITIONAL WATER NOT NO EXTRA-PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON T
- REQUIRED AND SHALL BE INCLUDED UNDER THE PAY ITEM TO WHICH IT
- THE DEVELOPER DEDICATES THE WATER MAINS UPON COMPLETION BY WATER SYSTEM WILL OWN AND MAINTAIN SAID WATER MAINS WHICH AF
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPL SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION INFORMATICA INFORMATION INFORMATION IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PR IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES WITH AS A MINIMUM. OSHA STANDARDS FOR TRENCH EXCAVATIONS. SP SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM
- INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. WORK COMPLETED BY THE CONTRACTOR WHICH HAS NOT RECEIVED / CONSTRUCTION INSPECTION DIVISION WILL BE SUBJECT TO REMOVAL
- THE CONTRACTOR WILL KEEP THE AREA ON TOP OF AND AROUND THE W WATER SYSTEM TO BE COMPLETELY RESTRAINED. RESTRAINED LENGTI
- EXTENDING TO THE TOP OF THE PIPE. THE NATIVE SOIL MATERIAL IS ASS FEET.

THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINE INSTALLATION. SEE SAWS SPECIFICATION BOOK.

ADDITIONAL WATER NOTES:

ALL VALVES SHALL READ "OPEN RIGHT".

- LEAD FREE FIRE HYDRANTS: "SAWS REQUIRES GCPS AND COUNTER PERMITS TO USE LEAD FREE (< 0
- 98% COMPACTION NOTE THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPAC
- THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCA ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET / REQUIREMENT BEING MET AND VERIFIED BY PRVIDING ALL NECESSARY DOCUMENTED TEST RESULTS. PIPE DISINFECTION WITH DRY HTH FOR PROJECTS LESS THAN 800 LINEAR FEET. (ITEM #847):
- MEASURE TO PROTECT HIS PERSONNEL DURING DISINFECTION OPERATIONS.
- SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER
- OVERFLOW, OR DISCHARGE OCCURS, THE CONTRACTOR MAY LIABLE FOR: ALL FINES, PENALTIES, OR OTHER COSTS ASSESSED TO OR AGAINST SAWS BY ANY STATE, FEDERAL, OR OTHER GOVERNMENTAL AGENCY.
- DISCHARGE, OR TO SUPPORT THE CLEANUP EFFORT.
- ALL DAMAGES CAUSED TO SAWS, OR ANY OTHER PERSONS OR ENTITIES THAT RESULT FROM THE SPILL, OVERFLOW OR DISCHARGE.
- BACK FLOW PREVENTION DEVICES FOR RESIDENTIAL SUBDIVISIONS

TRENCH EXCAVATION SAFETY PROTECTION CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMA AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFE DESCRIBED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR'S IMPLEMEN

FOR ADEQUATE TRENCH EXCAVATIONS SAFETY PROTECTION THAT COMPLY CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYE ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND AC

TREE PROTECTION AND PRESERVATION GENERAL NOTES

TREE PROTECTION AND PRESERVATION GENERAL NOTES NO UTILITY OR STREET EXCAVATION WORK SHALL BEGIN IN AREAS WHERE TREE PRESERVATION AND TREATMENT MEASURES HAVE NOT BEEN COMPLETED AND

- APPROVED
- PROTECTION ZONE (NO SEPARATE PAY ITEM.)
- ROOTS WILL BE CUT WITH A ROCK SAW OR BY HAND NOT BY AN EXCAVATOR OR OTHER ROAD CONSTRUCTION EQUIPMENT.
- ALL CURB AND SIDEWALK WORK SHALL USE ALTERNATIVE CONSTRUCTION METHODS TO MINIMIZE EXTENSIVE ROOT DAMAGE TO TREES (REFER TO DETAILS).
- PROTECTION ZONE IS 1 FOOT OF RADIUS PER INCH OF TREE'S DIAMETER. A 10-INCH DIAMETER TREE WOULD HAVE A 10 FOOT RADIUS ROOT PROTECTION ZONE WOUND SHALL BE PAINTED OVER WITHIN 20 MINUTES TO PREVENT OAK WILT. SAPLINGS, SHRUBS, OR BUSHES TO BE CLEARED FROM THE PROTECTED ROOT ZONE AREA OF A LARGE TREE SHALL BE REMOVED BY HAND AS DESIGNATED BY THE
- INSPECTOR NO WIRES, NAILS, OR OTHER MATERIAL MAY BE ATTACHED TO PROTECTED TREES.
- MANAGEMENT THROUGH THE INSPECTOR.
- NO EXCESSIVE TREE TRIMMING WILL BE PERMITTED.
- DISPOSED OF PROPERLY (NO SEPARATE PAY ITEM).
- PROJECT
- ANY TREE REMOVAL SHALL BE APPROVED BY THE CITY ARBORIST. (207-8053)
- EQUAL SIZE AND SPECIES.

	_
CTION IN THE VICINITY OF WATER MAINS	
ATION DISTANCE IS LESS THAN 9 FEET, ALL PORTIONS OF THE SEWER MAIN WITHIN NINE FEET (ATED DUCTILE IRON, CAST IRON OR PVC PIPE AND JOINED WITH EQUALLY PRESSURE RATED IECHANICAL COUPLING DEVICES OF A CAST IRON OR DUCTILE IRON MATERIAL. A SECTION OF H MAY BE CENTERED ON THE WATER MAIN IN LIEU OF PIPE CONNECTION REQUIREMENTS. (NO	OF
MAIN AND THE SEPARATION DISTANCE IS LESS THAN NINE FEET BUT GREATER THAN TWO FEE BAGS OF CEMENT PER CUBIC YARD OF SAND) FOR ALL SECTIONS OF THE SEWER WITHIN	ΞT,
RATION DISTANCE IS LESS THAN TWO FEET, THE SEWER MAIN SHALL BE CONSTRUCTED OF CAS 50 PSI WITHIN NINE FEET OF THE WATER MAIN, SHALL HAVE A SEGMENT OF SEWER PIPE SIX INCHES BETWEEN OUTER DIAMETERS, AND SHALL BE JOINED WITH PRESSURE RING GASKE EVICES OF A CAST IRON OR DUCTILE IRON MATERIAL. A SECTION OF 150 PSI PRESSURE RATED RED ON THE WATER MAIN IN LIEU OF PIPE CONNECTION REQUIREMENTS. (NO SEPARATE PAY	ST T
N DISTANCE IS LESS THAN NINE FEET, THE SEWER MAIN SHALL BE BELOW THE WATER MAIN, MINIMUM PRESSURE RATING OF 150 PSI FOR BOTH PIPE AND JOINTS FOR A DISTANCE OF NINE PARATION DISTANCE BETWEEN OUTER DIAMETERS OF TWO FEET VERTICALLY AND FOUR FEET CONNECTIONS OR CORROSION PROTECTED MECHANICAL COUPLING DEVICES OF A CAST IRON	= -
HAN NINE FEET TO WATER MAINS.	
F A CAST IRON MATERIAL.	
F	
TES:	٦
HE PLANS BUT NOT INCLUDED ON THE BID SCHEDULE. THIS INCIDENTAL WORK WILL BE	
THE DEVELOPER AND ACCEPTANCE BY THE SAN ANTONIO WATER SYSTEM. THE SAN ANTONIO RE LOCATED WITHIN THIS PARTICULAR SUBDIVISION. (AS APPLICABLE)	
LOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, TION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES 'ECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF	R
WORK ORDER OR THE NOTICE TO PROCEED WITH THE SAN ATNONIO WATER SYSTEM ND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR.	
NATER METER BOX FREE OF ALL OBJECTS AND DEBRIS.	
TH CALCULATIONS ARE FOR P.V.C. PIPE BEDDED IN COMPACTED GRANULAR MATERIAL SUMED TO BE INORGANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 4	
ED LENGTHS SHALL BE DESIGNED BASED UPON THE CONDITIONS ENCOUNTERED DURING THE	Ξ
0.25% LEAD) FIRE HYDRANTS."	
CTION ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS TO BE PERFORMED BY A ATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE SAWS INSPECTOR/TEST AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS	ч Г З

MAINS SHALL BE DISINFECTED WITH DRY HTH WHERE SHOWN IN THE CONTRACT DOCUMENTS OR AS DIRECTED BY THE INSPECTOR, AND SHALL NOT EXCEED A TOTA LENGTH OF 800 FEET. THIS METHOD OF DISINFECTION WILL ALSO BE FOLLOWED FOR MAIN REPAIRS. THE CONTRACTOR SHALL UTILIZE ALL APPROPRIATE SAFETY

ATTENTION CONTRACTORS: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO YOUR COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE - REGARDLESS OF SIZE. YOUR COMPLIANCE WILL ENABLE SAWS TO FULFILL REGULATORY REPORTING REQUIREMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTROL SEWER FLOWS SO THAT A SPILL OVERFLOW, OR DISCHARGE DOES NOT OCCUR. IN THE EVENT THAT A SPILL

SAWS STAFF AND MATERIAL COSTS TO RESPOND TO THE SPILL, OVERFLOW, OR DISCHARGE, OR TO MITIGATE THE EFFECTS OF THE SPILL, OVERFLOW, OR

ALL IRRIGATION SERVICES WITHIN RESIDENTIAL AREAS ARE REQUIRED TO HAVE BACK FLOW PREVENTION DEVICES

EE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF TION AND THE ANTICIPATED INSTALLATIONS SITE(S) WITHIN THE PROJECT WORK TY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES FOR THE PROJECT ITATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, EE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN TIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.	

TREE PROTECTION FENCING SHALL BE REQUIRED. TREE PROTECTION FENCING SHALL BE INSTALLED, MAINTAINED, AND REPAIRED BY THE CONTRACTOR DURING THE SITE CONSTRUCTION. DURING CONSTRUCTION ACTIVITY, AT LEAST A SIX-INCH LAYER OF COURSE MULCH SHALL BE PLACED AND MAINTAINED OVER THE ROOT

THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAN ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES. EXCAVATION IN THE VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY INSPECTOR FOR GUIDANCE.

EXPOSED ROOTS SHALL BE COVERED AT THE END OF THE DAY USING TECHNIQUES SUCH AS COVERING WITH SOIL, MULCH, OR WET BURLAP. NO EQUIPMENT, VEHICLES, OR MATERIALS SHALL OPERATE OR BE STORED WITHIN THE ROOT PROTECTION ZONE OF ANY TREE NEAR THE PROJECT. ROOT

AROUND THE TREE. ROOTS OR BRANCHES IN A CONFLICT WITH THE CONSTRUCTION SHALL BE CUT CLEANLY ACCORDING TO PROPER PRUNING METHODS. OAK

TREES, TREE LIMBS, BUSHES, AND SHRUBS LOCATED IN THE CITY STREET OR ALLEY RIGHT-OF-WAY OR PERMANENT EASEMENTS WHICH INTERFERE WITH PROPOSEI CONSTRUCTION ACTIVITIES SHALL BE PROPERLY PRUNED FOLLOWING THE ANSI A-300 STANDARDS FOR PRUNING. ALL TREE PRUNING SHALL BE COMPLETED BY A CITY OF SAN ANTONIO TREE MAINTENANCE LICENSED CONTRACTOR (ARTICLE 21-171, CITY CODE) ONLY AFTER APPROVAL FROM THE CAPITAL PROJECTS

ALL DEBRIS GENERATED BY THE PRUNING AND TRIMMING OF THE TREES AND/OR BUSHES SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE

TREES MUST BE MAINTAINED IN GOOD HEALTH THROUGHOUT THE CONSTRUCTION PROCESS. MAINTENANCE MAY INCLUDE, BUT NOT LIMITED TO: WATERING THE

ROOT PROTECTION ZONE, WASHING THE FOLIAGE, FERTILIZATION, PRUNING, ADDITIONAL MULCH APPLICATIONS AND OTHER MAINTENANCE AS NEEDED ON THE

TREES WHICH ARE DAMAGED OR LOST DUE TO THE CONTRACTOR'S NEGLIGENCE DURING CONSTRUCTION SHALL BE MITIGATED TO THE CITY'S SATISFACTION. TREE PLANTING FOR MITIGATION OR ENHANCEMENT: ALL PLANTED TREES SHALL BE MAINTAINED IN A HEALTHY CONDITION AT ALL TIMES. THIS INCLUDES IRRIGATION FERTILIZING, PRUNING, AND OTHER MAINTENANCE AS NEEDED ON THE PROJECT. TREES THAT DIE WITHIN TWELVE (12) MONTHS SHALL BE REPLACED WITH A TREE OI

ABBREVIA	ATIONS: ABBREVIATIONS LISTED BELOW D IN THIS PLAN SET.	C
ABBREVIA NOTE: SOME A ARE NOT USE AC APPROX ASPH BFD BGN BLDG BVCE BVCS CO CONC CWQZ DCDV DI DIA E ELEV EOP ESC EXST / EX FDC FFC FFE FG FH FND FOC FOC FP	ACTE ADDRESS AND A CONTROL OF CONTROL	IOT AUTHORIZED FOR
GRND GV GW HDPE HORIZ HP	GROUND GATE VALVE FINISHED GRADE AT WALL HIGH-DENSITY POLYETHYLENE HORIZONTAL HIGH POINT	
HT INFO IP IR LAT LF LOC LP LT LUP MEP MH MIN N: No NTS / N.T.S. OC O/S OU P PC PCC PG PI POB PROP PT PVC PVC PVC PVC PVC PVC PVC PVC PC REF RIM RDZ ROW / R/W RSGV RT	HEIGHT INFORMATION STORM INLET PROTECTION IRON ROD LATERAL LINEAR FEET LIMITS OF CONSTRUCTION LOW POINT LEFT LAND USE PLAN MECHANICAL, ELECTRICAL & PLUMBING MANHOLE MINIMUM NORTHING NUMBER NOT TO SCALE ON CENTER OFFSET OVERHEAD UTILITY PIPELINE TANGENT - CURB INTERSECTION POINT OF CURB INTERSECT PAGE TANGENT - TANGENT INTERSECTION POINT OF BEGINNING PROPOSED CURVE - TANGENT INTERSECTION POLYVINYL CHLORIDE PAVEMENT RADIUS ROCK BERM REINFORCED CONCRETE PIPE REFERENCE TOP OF MANHOLE LID ELEVATION REDUCED PRESSURE ZONE R.O.W RIGHT OF WAY RESILIENT SEAT GATE VALVE RIGHT	210.860.9224 FIRM NO: F-15085
SD / STM SF SHT SHTS SQ. FT. STA T TBM TC TC TM TP TOB TW TYP UE UNK UT VERT VOL W W W W W W W W W W W W W W W W W W W	STORM DRAIN STORM DRAIN SILT FENCE SHEET SHEETS SQUARE FEET STATION TELEPHONE TEMPORARY BENCHMARK TOP OF CURB TIME OF CONCENTRATION TOP OF MEDIA TREE PROTECTION TOP OF MALL TYPICAL UNDERGROUND ELECTRIC UNKNOWN UNDERGROUND TELEPHONE VERTICAL VOLUME WATER WATER LINE WITH WATER METER WATER QUALITY TRANSITION ZONE WATER SURFACE ELEVATION WATER VALVE WASTEWATER YARD DRAIN YEAR	AMANDA S



C003

03 OF 11

PRIOR TO BEGINNING CONSTRUCTION.

ONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND IORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE INGINEER IMMEDIATELY OF ANY DISCREPANCIES. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE OCATION OF UNDERGROUND UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR AVOIDING ALL EXISTING UTILITIES BY CALLING DIGTESS @

-800-DIG-TESS FOR LOCATION OF ALL UTILITIES, AT LEAST 2 WORKING DAYS



В	A Conversion of the second se	CONSTRUCTION PRIOR TO	
	Image: Strain of the strai	TION MAIL FIGURE STORES	Proceeding and the second surface of the second sec
Estation of the second se	 NOTES: 1. EXISTING CONDITIONS SURVEY PREPARED BY D.A.MAWYER SURVEYING, INC. WERE MADE IN AUGUST OF 2023. 2. ONLY VISIBLE IMPROVEMENTS & UTILITIES WERE PROVIDED FROM SURVEY (THE SURVEYOR/ENGINEER HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES, LOCATIONS OF EXISTING UTILITIES, SOME OF WHICH MAY NOT BE SHOWN, COULD IMPACT CONSTRUCTION MEANS AND METHODS. CONTRACTOR TO VERIEY ALL EXISTING CONTINUTION TO HORIZOTATLY PROFINE OF BID & CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES. THE CONTRACTOR TO CONTACT THE OWNEOF EACH INDIVIDUAL UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO BID & CONSTRUCTION, AND SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES. THE CONTRACTOR TO CONTACT THE OWNEOF EACH INDIVIDUAL UTILITY FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS. 3. THE SIZE AND LOCATION OF UTILITY STRUCTURES, (IF SHOWN), MAY BE EXAGGERATED FOR GRAPHICAL CLARITY. THE SURVEY SHOWS FIELD MEASURED SIZES AND DEPTHS AS OBSERVED FROM GROUND LEVEL OPENINGS. 4. REFERENCE COVER SHEET AND TREE LIST FOR ADDITIONAL INFORMATION. 	ECONTROLS - SITE WORK PERMIT 5711 FARINON DR. SAN ANTONIO, TEXAS 78249	EXISTING CONDITIONS
	CONTROL PLAN" SHEET. CAUTION: CONTRACTOR TO VERIFY ALL EXISTING UTILITIES VERTICALLY AND HORIZONTALLY PRIOR TO CONSTRUCTION. CONTRACTOR TO NOTIFY THE ENGINEER IMMEDIATELY OF ANY DISCREPANCIES. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE LOCATION OF UNDERGROUND UTILITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR AVOIDING ALL EXISTING UTILITIES BY CALLING DIGTESS @ 1-800-DIG-TESS FOR LOCATION OF ALL UTILITIES, AT LEAST 2 WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION.	SHEET C100 04 OF 1 	.1









Ś

ר)

 \cap

(Truck Parking and Driveways)



1	G		F	
				NOTES FOR TREE AND NATURAL
	(* * *			PROTECTION FENCE SHALL BE CHAIN LIF ALL TREES AND NATURAL APPEAR SHOWN
	×)			ALL TREES AND INFLURAL AREAS SHOWN DURING CONSTRUCTION WITH TEMPORA PROTECTIVE FENCES SHALL BE ERECTE
	(<u>20'-0"</u> −O			PROTECTION. 4. PROTECTIVE FENCES SHALL BE INSTALL
				WORK (CLEARING, GRUBBING OR GRADI PHASES OF THE CONSTRUCTION PROJE
	* *			A MANNER WHICH DOES NOT RESULT IN PROTECTIVE FENCES SHALL SURROUNE
				LOCATED AT THE OUTERMOST LIMIT OF PROTECTIVE FENCES SHALL FOLLOW TI PREVENT THE FOLLOWING:
	PLAN VIEW 20" DIAMETER TREE			(A) SOIL COMPACTION IN THE ROO OR STORAGE OF EQUIPMENT C (B) ROOT ZONE DISTUBRANCES DI
	СНА			(C) WOUNDS TO EXPOSED ROOTS, (C) WOUNDS TO EXPOSED ROOTS, (D) OTHER ACTIVITIES DETRIMENT.
	K.XXX			TRUCK CLEANING, AND FIRES. 7. EXCEPTIONS TO INSTALLING FENCES A
				FOLLOWING CASES: (A) WHERE THERE IS TO BE AN API SUBSACE TREE WELL OR OTH
				APPROXIMATELY 2 TO 4 FEET E (B) WHERE PERMEABLE PAVING IS THE FENCE AT THE OUTER LIM
		10'-0" MAX.		GRADING SO THAT THIS AREA I INSTALLATION TO MINIMIZED R (C) WHERE TREES ARE CLOSE TO
		FENCE LOCATION (LIMITS OF CRITICA	L ROOT ZONE)	6 TO TO FEET OF WORK SPACE (D) WHERE THERE ARE SEVERE SF SPECIAL REQUIREMENTS.
	-	RA	DIUS = 1 FT. PER INCH OF TRUNK DIA.	SPECIAL NOTE: FOR THE PROTECTION OF FENCES AT THE LIMIT OF CONSTRUCTION
9	TREE PROTECTI	[ON		
SCALE: N.T.S.		/ENTION DI ANI / TODES:		
	NSTALL TEMPORARY AND PERMANENT S	TORM WATER POLLUTION PREVENTION CON	ROL MEASURES SHOWN IN THE PLANS. CO	ONSTRUCT IMPROVEMENTS IN COMPLIANCE
WITH THE INTE	NT OF SUCH POLLUTION CONTROL MEAS	JURES, TPDES PERMITS, OR OTHER LOCAL W	ATERWAY DEVELOPMENT PERMITS. ORM WATER POLITITION PREVENTION PLA	N (SWPPP)
2. SUBMIT A	STORM WATER TPDES GENERAL PERMIT	NOTICE OF INTENT (NOI) AT LEAST TWO DAYS	S PRIOR TO START OF CONSTRUCTION TO	THE APPROPRIATE AGENCY SHOWN ON THE
SWPPP. 3. POST SIGN	IED AND COMPLETED NOI POSTING NOTI	CE OR CONSTRUCTION SITE NOTICE (CSN) AT	THE CONSTRUCTION ENTRANCE FOR PUB	LIC VIEWING, AND KEEP A COPY OF THE
SWPPP AT	THE JOB SITE AT ALL TIMES.	()		
+. INSTALL AI	אין אואוא דאוא POLLU FION CONTROL MEAS	STRUCTION ENTRANCE WITH MANUFACTURE	R 5 SPECIFICATIONS AND WITH PROJECT S	N. POLLUTION CONTROL MEASURES SHALL BE
REPAIRED	REESTABLISHED, ADJUSTED OR REINST	ALLED WITH EACH SUBSEQUENT PHASE OF C	CONSTRUCTION IN ACCORDANCE WITH THE	
. CONTRAC	SEDIMENT TRAPS OR SEDIMENTATION BA	ASINS.	ND SHALL REMOVE THE ACCUMULATION C	OFF-SITE SEDIMENT PROMPTLY.
. OFF-SITE	ATERIAL STORAGE AREAS USED SOLEL	Y BY THE PROJECT ARE CONSIDERED PART C	F THE PROJECT.	
MAINTAIN	RECORDS OF PROJECT MILESTONE DATE	ES AND FIELD CHANGES AS REQUIRED BY THE	SWPPP.	
INSPECT P RECORDE	OLLUTION CONTROL MEASURES EVERY O AS REQUIRED BY THE SWPPP.	14 DAYS AND WITHIN 24 HOURS AFTER A STO	RM EVENT GREATER THAN 0.5 INCHES OF F	RAINFALL. AN INSPECTION REPORT SHALL BE
1. DEFICIENC			I SEVEN CALENDAR DAYS OR BEFORE THE	NEXT ANTICIPATED STORM EVENT.
TPDES RE	CONSTRUCTION, MAKE CERTAIN THE NO PORT AND SWPPP ARE AVAILABLE AT THI	E TRAILER.	E NOTICE (CSN) HAS BEEN FILED AND POS	TED ONSITE FOR PUBLIC VIEWING AND THE
INSTALL S	FORM WATER POLLUTION PREVENTION C 6, GRUBBING, EXCAVATION).	ONTROLS PRIOR TO ANY SITE PREPARATION	WORK	
. THE PLACI THE APPR	EMENT OF STORM WATER POLLUTION PR OVED STORM WATER POLLUTION PREVE	EVENTION CONTROLS SHALL BE IN ACCORDANTION CONTROL PLAN.	NCE WITH	
A PRE-COM	NSTRUCTION CONFERENCE SHALL BE HE	LD ON-SITE WITH THE CONTRACTOR AND EN	GINEER AFTER INSTALLATION OF THE STOP	RM WATER POLLUTION PREVENTION CONTROL
ANY MAJO	R VARIATION IN MATERIALS OR LOCATION	NS OF CONTROLS OR FENCES FROM THOSE S	HOWN ON THE APPROVED PLANS WILL R	
ENGINEER	DURING THE COURSE OF CONSTRUCTIO	IN TO CORRECT CONTROL INADEQUACIES.	STORM WATER POLLUTION PREVENTION	CONTROL PLAN MAT DE REQUIRED DT THE
. THE CONT EVENTS TO NECESSAF	RACTOR IS REQUIRED TO INSPECT THE O DINSURE THAT THEY ARE FUNCTIONING RY REPAIRS TO DAMAGED AREAS. SILT AC	CONTROLS AND FENCES AT INTERVALS OF AT PROPERLY. THE PERSON(S) RESPONSIBLE FC CCUMULATION AT CONTROLS MUST BE REMO	LEAST ONCE EVERY TWO (2) WEEKS AND OR MAINTENANCE OF CONTROLS AND FENO VED WHEN THE DEPTH REACHES SIX (6) IN	IMMEDIATELY AFTER SIGNIFICANT RAINFALL CES SHALL IMMEDIATELY MAKE ANY CHES.
3. PRIOR TO SEDIMENT	FINAL ACCEPTANCE BY THE CITY, HAUL F REMOVED FROM THE WATERWAY AND T	ROADS AND WATERWAY CROSSINGS CONSTR THE AREA RESTORED TO THE ORIGINAL GRAD	UCTED FOR TEMPORARY CONTRACTOR AGE AND REVEGETATED. ALL LAND CLEARING	CCESS MUST BE REMOVED, ACCUMULATED G DEBRIS SHALL BE DISPOSED OF PROPERLY.
	T FENCE CANNOT BE PROPERLY INSTAL	LED USE TRIANGULAR FILTRATION DIKE.	OF LAND REQUIRED FOR THE CLEARING A	ND GRADING ACTIVITY AND FOR THE
CONSTRU	CTION ACTIVITY, FOR THE SHORTEST PR	ACTICAL PERIOD OF TIME.		
1. STABILIZA AND EXCE PERMANEI	TION MEASURES WILL BE INITIATED AS SO PT AS PROVIDED BELOW, WILL BE INITIAT NTLY CEASED.	SON AS PRACTICABLE IN PORTIONS OF THE S FED NO MORE THAN FOURTEEN (14) DAYS AFT	TE WHERE CONSTRUCTION ACTIVITIES HAT ER THE CONSTRUCTION ACTIVITY IN THAT	AVE TEMPORARILY OR PERMANENTLY CEASED PORTION OF THE SITE HAS TEMPORARILY OR
2. WHERE CO TEMPORA	DNSTRUCTION ACTIVITY ON A PORTION O RY STABILIZATION MEASURES DO NOT HA	IF THE SITE IS TEMPORARILY CEASED, AND EA	ARTH DISTURBING ACTIVITIES WILL BE RES TE.	UMED WITHIN TWENTY-ONE (21) DAYS,
23. TRAFFIC L	EAVING THE CONSTRUCTION SITE WILL E	EXIT THROUGH A STABILIZED CONSTRUCTION	EXIT AS LOCATED ON THE PLANS. WHEN S WILL BE CLEANED AND REESTABLISHED F	OILS HAVE COLLECTED ON THE STABILIZED
4. MUD/DIRT	INADVERTENTLY TRACKED OFF-SITE AND) ONTO PUBLIC STREETS SHALL BE REMOVED	IMMEDIATELY.	
5. PERMANEI	NT EROSION CONTROL: REFER TO LANDS	CAPE PLAN FOR PLATING REQUIREMENTS. IF	NOT ADDRESSED BY LANDSCAPE PLAN, T	HE FOLLOWING SHALL APPLY:
ALL DISTU		OTED BELOW. UNLESS OTHERWISE STATED IN	I THE LANDSCAPE PLANS.	
(A) A M	E SEEDING FOR PERMANENT EROSION CO	ONTROL SHALL BE APPLIED OVER AREAS DI	STURBED BY CONSTRUCTION AS FOLLOWS	UNLESS SPECIFIED OTHERWISE BY THE
PR	DJECT'S LANDSCAPE PLAN: DRAINAG	E CHANNELS (EXCEPT ROCK) AND BETWEEN	THE CURB AND RIGHT-OF-WAY LINE.	
I. FRO	DM SEPTEMBER 15 TO MARCH 1, SEEDING TH A PURITY OF 95% WITH 90% GERMINAT	3 SHALL BE WITH A COMBINATION OF 2 POUN TION.	DS PER 1000 SF OF UNHULLED BERMUDA A	ND 7 POUNDS PER 1000 SF OF WINTER RYE
II. FRO	DM MARCH 2 TO SEPTEMBER 14, SEEDING	3 SHALL BE WITH HULLED BERMUDA AT A RAT	E OF 2 POUNDS PER 1000 SF WITH A PURIT	TY OF 95% WITH 85% GERMINATION.
(A) FEF EST	RTILIZER SHALL BE A PELLETED OR GRAN FABLISHMENT AT A RATE OF 1 POUND PE	JULAR SLOW RELEASE WITH AN ANALYSIS OF R 1000 SF.	15- 15-15 TO BE APPLIED ONCE AT PLANTIN	NG AND ONCE DURING THE PERIOD OF
(B) MU	LCH TYPE USED SHALL BE HAY, STRAW C)R MULCH APPLIED AT A RATE		
I. FRO	<u>DRAULIC SEEDING:</u> DM SEPTEMBER 15 TO MARCH 1, SEEDING URITY OF 95% WITH 90% GERMINATION	G SHALL BE WITH A COMBINATION OF 1 POUN	D PER 1000 SF OF UNHULLED BERMUDA AN	ID 7 POUNDS PER 1000 SF OF WINTER RYE WIT
II. FRO	DM MARCH 2 TO SEPTEMBER 14, SEEDING	G SHALL BE WITH HULLED BERMUDA AT A RAT	E OF 1 POUND PER 1000 SF WITH A PURITY	OF 95% WITH 85% GERMINATION.
(A) FEF		ERTILIZER WITH AN ANALYSIS OF 15-15-15 AT A	A RATE 1.5 POUNDS PER 1000 SF.	
(B) MU (C) THI THI	LCH TYPE USED SHALL BE HAY, STRAW C E PLANTED AREA SHALL BE IRRIGATED O E IRRIGATION SHALL OCCUR AT TEN-DAY	OR MULCH APPLIED AT A RATE OF 45 POUNDS R SPRINKLED IN A MANNER THAT WILL NOT E (INTERVALS DURING THE FIRST TWO MONTH)	PER 1000 SF, WITH SOIL TACKIFIER AT A R RODE THE TOPSOIL, BUT WILL SUFFICIENT S RAINFALL OCCURRENCES OF 1/2 INCH OF	ATE OF 1.4 POUNDS PER 1000 SF. LY SOAK THE SOIL TO A DEPTH OF SIX INCHES R MORE SHALL POSTPONE THE WATERING
(D) RES	HEDULE FOR ONE WEEK. (COORDINATE V	VITH IRRIGATION PLAN) IN THE GRASS HAS GROWN AT LEAST 1 1/2 IN(CHES HIGH WITH 95% COVERAGE, PROVIDE	ED NO BARE SPOTS LARGER THAN 16 SQUARE
FEE (E) SEI	ELEXIST. EDING SHALL APPLY TO ALL AREAS WITH	IN DISTURBED PROJECT AREA NOT COVERED	BY PAVEMENT, BUILDING PAD OR PROJEC	T LANDSCAPING PLANS.
(F) TW	O SEEDINGS SHOULD OCCUR DURING PR	ROJECT. FIRST SHOULD OCCUR WITHIN 14 DA	YS AFTER PONDS ARE GRADED AND SECO	ND BY FINAL PUNCH LIST.
:0. THE EPA C INSTALLED CUBIC FEE	DEINERAL PERMIT REQUIRES THAT A TEMP IN ANY DRAINAGE LOCATION WHERE MO T OF STORAGE FOR EVERY ACRE IF LAN	CORARY OR PERMANENT SEDIMENT BASIN BE DRE THAN 10 ACRES IN THE UPSTREAM DRAIN D, WHICH IT DRAINS.	IAGE ARE DISTURBED AT ONE TIME. THE S	EDIMENT BASIN MUST PROVIDE AT LEAST 3,600
?7. CONTRAC TO REFER	TOR TO FOLLOW APPROVED TCEQ WPAP TO WPAP IF DISCREPANCY EXISTS BETW	FOR EROSION CONTROL. CONTRACTOR		
10				
LU SCALE: NTS		KUL NUTES		













0

R \overline{O}

PRI

Ζ

A

>

Ó

PPR

A

OR

Ľ.

ZED



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600)

ATTACHMENT G

INSPECTION, MAINTENANCE, REPAIR AND RETROFIT PLAN



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600) ATTACHMENT H

PILOT-SCALE FIELD TESTING PLAN

This attachment does not apply to this submittal. The TNRCC (TCEQ) Technical Guidance Manual (TGM) was used to design permanent BMPs and measures on site, and therefore a Pilot-Scale Field Testing Plan is not required.



SECTION 6: PERMANENT STORMWATER SECTION (TCEQ-0600)

ATTACHMENT I

MEASURES FOR MINIMIZING SURFACE STREAM CONTAMINATION

This attachment does not apply to this submittal. There are no surface streams existing on site.



Agent Authorization Form

For Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Kennon Guglielmo

Print Name

Owner

Title - Owner/President/Other

of _____

ECONTROLS, LLC

Corporation/Partnership/Entity Name

have authorized

Jose Luis Cantu Print Name of Agent/Engineer

of

WGI

Print Name of Firm

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- 3. Application fees are due and payable at the time the application is submitted. The application fee must be sent to the TCEQ cashier or to the appropriate regional office. The application will not be considered until the correct fee is received by the commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

SIGNATURE PAGE:

Applicant's Signature

8-28-2023

Date

THE STATE OF

County of Bevar

BEFORE ME, the undersigned authority, on this day personally appeared <u>Kinnen Giglie Inknown</u> to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this <u>28</u> day of <u>Au aut</u> 2023

NOTARY PUBLIC

Jo Ann Conley Typed or Printed Name of Notary

MY COMMISSION EXPIRES: July 29, 2026



JOANN ADAMS CONLEE My Notary ID # 7964544 Expires July 29, 2026

Owner Authorization Form

Texas Commission on Environmental Quality for Required Signature Edwards Aquifer Protection Program Relating to 30 TAC Chapter 213 Effective June 1, 1999

Land Owner Authorization

	Kennon Guglielmo	
l;"		of

GTD Development, LLC

Land Owner Signatory Name

Land Owner Name (Legal Entity or Individual)

am the owner of the property located at

5727 Farinon Drive. San Antonio, Bexar County, 78249

Legal description of the property referenced in the application

and am duly authorized in accordance with §213.4(c)(2) and §213.4(d)(1) or §213.23(c)(2) and §213.23(d) relating to the right to submit an application, signatory authority, and proof of authorized signatory. ECONTROLS, LLC

I do hereby authorize _____

Applicant Name (Legal Entity or Individual)

to conduct ____

Description of the proposed regulated activities

at 5727 Farinon Drive

Precise location of the authorized regulated activities

Land Owner Acknowledgement

I understand that _____

GTD Development, LLC

Land Owner Name (Legal Entity or Individual)

Is ultimately responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation even if the responsibility for compliance and the right to possess and control the property referenced in the application has been contractually assumed by another legal entity. I further understand that any failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Land Owner Signature

Land Owner Signature

THE STATE OF § <u>Jercas</u> County of § <u>Berlan</u> 8-28-2023 Date

BEFORE ME, the undersigned authority, on this day personally appeared <u>Kennon Guglelme</u> known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 20 day of 40

NOTARY PUBLIC mala.0 Typed or Printed Name of Notary

MY COMMISSION EXPIRES: July 29, 2021



JOANN ADAMS CONLEE My Notary ID # 7964544 Expires July 29, 2026

Attached: (Mark all that apply)

Lease Agreement

Signed Contract

Deed Recorded Easement

Other legally binding document

Applicant Acknowledgement

Kennon Guglie	elmo	of	ECONTROLS, LLC
Applicant Signato	ry Name	_	Applicant Name (Legal Entity or Individual)
acknowledge that _	GTD Develop	ment, LLC	
	Land Ow	ner Name (Leg	gal Entity or Individual)
has provided <u>E</u>	CONTROLS, LL	.C	
	Applica	int Name (Lega	l Entity or Individual)
with the right to po	ssess and control	the property re	ferenced in the Edwards Aquifer protection plan.
I understand that	ECONTROLS,	LLC	
	Appli	cant Name (Le	gal Entity or Individual)

is contractually responsible for compliance with the approved or conditionally approved Edwards Aquifer protection plan and any special conditions of the approved plan through all phases of plan implementation. I further understand that failure to comply with any condition of the executive director's approval is a violation is subject to administrative rule or orders and penalties as provided under §213.10 (relating to Enforcement). Such violation may also be subject to civil penalties and injunction.

Applicant Signature

8-28-2023

Applicant Signature THE STATE OF § <u>JULAP</u> County of § <u>BULAN</u> Date

BEFORE ME, the undersigned authority, on this day personally appeared <u>Kennon Guglicino</u> known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that (s)he executed same for the purpose and consideration therein expressed.

GIVEN under my hand and seal of office on this 28 day of A

NOTARY PUBLIC

Typed or Printed Name of Notary MY COMMISSION EXPIRES:



3 of 3

TCEQ-XXXXX



SECTION 8: APPLICATION FEE FORM (TCEQ-0574)

Application Fee Form

Texas Commission on Environme	ental Quality						
Name of Proposed Regulated Entity: Ethium Building							
Regulated Entity Location: 5711	Farinon Drive						
Name of Customer: Kennon Gu	uglielmo						
Contact Person: Erin Sandova	l Pho	ne: (210)640-4467					
Customer Reference Number (if i							
Regulated Entity Reference Num	per (if issued):RN <u>NA</u>	_					
Austin Regional Office (3373)							
Hays	Travis	v	/illiamson				
San Antonio Regional Office (336	52)						
🔀 Bexar	🛄 Medina	U 🗌	valde				
Comal	Kinney						
Application fees must be paid by	check, certified check,	or money order, payal	ble to the Texas				
Commission on Environmental Q	uality. Your canceled	check will serve as you	ır receipt. This				
form must be submitted with yo	ur fee payment. This p	ayment is being subm	itted to:				
Austin Regional Office	X	San Antonio Regional (Office				
Mailed to: TCEQ - Cashier		Overnight Delivery to:	TCEQ - Cashier				
Revenues Section		12100 Park 35 Circle	•				
Mail Code 214	-	Building A. 3rd Floor					
P.O. Box 13088	-	Austin, TX 78753					
Austin, TX 78711-3088	(512)239-0357					
Site Location (Check All That App	lv):	,,					
			· · · · · · · · · · · · · · · · · · ·				
Kecharge Zone	Contributing Zone		Ition Zone				
Type of Pla	n	Size	Fee Due				
Water Pollution Abatement Plan,	Contributing Zone						
Plan: One Single Family Residentia	l Dwelling	Acres	\$				
Water Pollution Abatement Plan,	Contributing Zone						
Plan: Multiple Single Family Reside	ential and Parks	Acres	\$				
Water Pollution Abatement Plan,	1750 4 848 8	5 000 00					
Plan: Non-residential	I 7.59 Acres	\$ 3,000.00					
Sewage Collection System		L.F.	\$				
Lift Stations without sewer lines		Acres	\$				
Underground or Aboveground Sto	rage Tank Facility	Tanks	\$				
Piping System(s)(only)		Each	\$				
Exception		Each	\$				
Extension of Time	Each	Ś					

Signature:

Date: 8-29-2023

TCEQ-0574 (Rev. 02-24-15)

Application Fee Schedule

Texas Commission on Environmental Quality

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

Water Pollution Abatement Plans and Modifications

Contributing Zone Plans and Modifications

Project	Project Area in Acres	Fee
One Single Family Residential Dwelling	< 5	\$650
Multiple Single Family Residential and Parks	< 5	\$1,500
	5 < 10	\$3,000
	10 < 40	\$4,000
	40 < 100	\$6,500
	100 < 500	\$8,000
	≥ 500	\$10,000
Non-residential (Commercial, industrial, institutional,	< 1	\$3,000
multi-family residential, schools, and other sites	1 < 5	\$4,000
where regulated activities will occur)	5 < 10	\$5,000
	10 < 40	\$6,500
	40 < 100	\$8,000
	≥ 100	\$10,000

Organized Sewage Collection Systems and Modifications

Project	Cost per Linear Foot	Minimum Fee- Maximum Fee
Sewage Collection Systems	\$0.50	\$650 - \$6,500

Underground and Aboveground Storage Tank System Facility Plans and Modifications

Project	Cost per Tank or Piping System	Minimum Fee- Maximum Fee
Underground and Aboveground Storage Tank Facility	\$650	\$650 - \$6,500

Exception Requests

Project	Fee		
Exception Request	\$500		

Extension of Time Requests

Project	Fee
Extension of Time Request	\$150



SECTION 9: CHECK PAYABLE TO "TEXAS COMMISSION ON ENVIRONMENTAL QUALITY"



SECTION 10: CORE DATA FORM (TCEQ-10400)

TCEQ Use Only



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)						
New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)						
Renewal (Core Data Form should be submitted with the renewal form)						
2. Customer Reference Number (if issued) Follow this link to search						
CN Central Registry** RN						

SECTION II: Customer Information

4. General C	ustomer Information	5. Effective	Date for Custor	ner lı	nformation	Updates (mm/dd	/уууу)		
🔀 New Custo	omer 🗌 L	Ipdate to Custo	mer Information		Char	nge in Regulated Er	itity Own	ership	-
Change in	Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)								
The Custom	The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State								
(SOS) or Tex	as Comptroller of Public Accou	ints (CPA).							
6. Customer	Legal Name (If an individual, pri	nt last name firs	st: eg: Doe, John)			<u>If new Customer,</u>	enter pr	evious Custome	r <u>below;</u>
Gugliel	mo, kennon								
7. TX SOS/CI	A Filing Number	8. TX State 1	ax ID (11 digits)			9. Federal Tax	D	10. DUNS N	lumber (//
						(0. dtin-)		applicable)	
						(a cilitiz)			
							1	<u> </u>	
11. Type of C	ustomer: Corporat	ion			Individ	ual	Partne	ership: 🗌 Gene	eral 🔀 Limited
Government: [🗌 City 🛄 County 🔲 Federal 🛄	Local 🔲 State	Other		Sole Pr	oprietorship	Oti	her:	
12. Number	of Employees					13. Independe	ntiy Ow	ned and Oper	ated?
X 0-20	21-100 🔲 101-250 🔲 251-:	500 🗌 501 a	nd higher			X Yes	No 🗌		
14. Custome	r Role (Proposed or Actual) — as it	relates to the R	egulated Entity II	sted o	n this form. I	Please check one of	the follo	wing	
XOwner	Operator	🗌 Owr	er & Operator						
Occupation	al Licensee 🔲 Responsible Par	ty 🗌 Vi	CP/BSA Applicant			U Other:			
15. Mailing	5757 Farinon Driv	е							ma t
Address:	City		State		710			71D ± 4	
	San Antonio TX				() 21F 78249 21F + 4				
16. Country N	Nailing Information (If outside U	ISA)		17	17. E-Mail Address (if applicable)				
				K	Kgug@econtrols.com				
18. Telephone Number 19. Extension or Code 20. Fax Number (if applicable)									

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)

🔀 New Regulated Entity 🚺 Update to Regulated Entity Name 🔲 Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

Ethium Building							
23. Street Address of the Regulated Entity:	5711	Farinon Driv	8				
(No PO Boxes)	City	San Antonio	State	ТХ	ZIP	78249	ZIP + 4
24. County	Bexar						

If no Street Address is provided, fields 25-28 are required.

25. Description to	A	vine tels 0.4	7 miles Mar			and Casimon Dr		
Physical Location:	Approx	kimately 0. i	/ miles wes		Y I-10 a	no Farinon Dr	ive inter	Section.
26. Nearest City	1					State	Nea	arest ZIP Code
San Antonio TX 78249								
Latitude/Longitude are n used to supply coordinate	equired and es where no	may be added/u ne have been pro	ipdated to meet i ovided or to gain	TCEQ Core D accuracy).	ata Standa	rds. (Geocoding of t	he Physical	Address may be
27. Latitude (N) In Decima	al:	29.5620	79	28. Lo	ongitude (W	V) in Decimai:	-98	.594051
Degrees	Minutes	Se	econds	Degree	es	Minutes		Seconds
29	33		35	-98	8	35		44
29. Primary SIC Code	30.	Secondary SIC Co	de	31. Primar	y NAICS Col	de 32. Seco	ondary NAI	CS Code
(4 digits)	(4 di	gits)		(5 or 6 digit:	s)	(5 ar 6 di	igits)	
33. What is the Primary B	usiness of ti	nis entity? (Do n	ot repeat the SIC or	r NAICS descrij	ption.)			
24 Mailing	T		5757 F	Farinon [Drive			
Addraces								
ADDIESS:	City	San Antonic	O State	ТХ	ZIP	78249	ZIP + 4	
35. E-Mail Address:			Kgug@ecc	ontrols.co	om			
36. Telephone Number		3	37. Extension or (Code	38. Fa	x Number (if applicat	ole)	
(210)860-9224	4				()	-		

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

Dam Safety	Districts	Edwards Aquifer	Emissions Inventory Air	Industrial Hazardous Waste
Municipal Solid Waste	New Source Review Air	OSSF	Petroleum Storage Tank	D PWS
Sludge	Storm Water	Title V Air	Tires	Used Oil
Voluntary Cleanup	Wastewater	Wastewater Agriculture	Water Rights	Other:

SECTION IV: Preparer Information

40. Name:	Erin Sandoval			41. Title:	Senior Graduate Engineer
42. Telephone Number		43. Ext./Code	44. Fax Number	45. E-Mail /	Address
(210)860-9224		() -	Erin.S	andoval@wginc.com	

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	ECONTROLS, LLC	Job Title:	CEC	2	
Name (In Print):	Kennon Guglielmo			Phone:	210 6022873
Signature:	1 B			Date:	8-28-2023



SECTION 11: Additional Information

John Mauser - Re: SWBC-Farinon

From:John MauserTo:Villagomez, JoseDate:8/24/2006 3:15 PMSubject:Re: SWBC-Farinon

Jose,

Only the storage of regulated quantities of hydrocarbons and hazardous substances (Aboveground: 500 or more gallons, Underground: all tanks) are reguated on the Transition Zone. A WPAP is not required on the Transiton Zone.

J.

>>> "Jose Villagomez" <Jvillagomez@slayengineering.com> 8/24/2006 2:21 PM >>> John:

I met with the our client today, to discuss the SWBC-Farinon parking lot expansion. We have decided to move all of the parking lot expansion out of the recharge zone, leaving all the expansion over the transition zone. If we are expanding on the piece of parking lot that is not over the recharge zone are we in the clear? Does the expansion which is not over the recharge zone trigger any requirements for the area of parking lot which exists over the recharge zone that was constructed prior to the WPAP process?

Thanks for your help.

Jose Slay Engineering Co., Inc.

