### **CANYON GOLF RETAIL**

**Sewage Collection System Application** 



### **CANYON GOLF RETAIL**

**Sewage Collection System Application** 





August 12, 2025

Ms. Monica Reyes Texas Commission on Environmental Quality Region 13 14250 Judson Road San Antonio, Texas 78233-4480

Re: Canyon Golf Retail

**Sewage Collection System Application** 

Dear Ms. Reyes:

Please find included herein the Canyon Golf Retail Sewage Collection System Application. This Sewage Collection System Application has been prepared to be consistent with the regulations of the Texas Administrative Code (30 TAC 213, 217 and 290) and current policies for development over the Edwards Aquifer Recharge Zone.

This Sewage Collection System Application applies to the 537 linear feet of 8-inch sewer main proposed as part of this project. Please review the plan information for the items it is intended to address. If acceptable, provide a written approval of the plan in order that construction may begin at the earliest opportunity.

Appropriate review fees \$6,500.00 and fee application form are included. If you have questions or require additional information, please do not hesitate to contact me at your earliest convenience.

Sincerely,

Pape-Dawson Consulting Engineers, LLC

aid E. Martin

David Martinez, P.E.

Vice President

Attachments

DAVID E. MARTINEZ

94900

CENSE

08/12/25

# EDWARDS AQUIFER APPLICATION COVER PAGE (TCEQ-20705)

#### Texas Commission on Environmental Quality

### **Edwards Aquifer Application Cover Page**

#### **Our Review of Your Application**

The Edwards Aquifer Program staff conducts an administrative and technical review of all applications. The turnaround time for administrative review can be up to 30 days as outlined in 30 TAC 213.4(e). Generally administrative completeness is determined during the intake meeting or within a few days of receipt. The turnaround time for technical review of an administratively complete Edwards Aquifer application is 90 days as outlined in 30 TAC 213.4(e). Please know that the review and approval time is directly impacted by the quality and completeness of the initial application that is received. In order to conduct a timely review, it is imperative that the information provided in an Edwards Aquifer application include final plans, be accurate, complete, and in compliance with 30 TAC 213.

#### **Administrative Review**

- Edwards Aquifer applications must be deemed administratively complete before a technical review can begin. To be considered administratively complete, the application must contain completed forms and attachments, provide the requested information, and meet all the site plan requirements. The submitted application and plan sheets should be final plans. Please submit one full-size set of plan sheets with the original application, and half-size sets with the additional copies.
  - To ensure that all applicable documents are included in the application, the program has developed tools to guide you and web pages to provide all forms, checklists, and guidance. Please visit the below website for assistance: <a href="http://www.tceq.texas.gov/field/eapp">http://www.tceq.texas.gov/field/eapp</a>.
- 2. This Edwards Aquifer Application Cover Page form (certified by the applicant or agent) must be included in the application and brought to the administrative review meeting.
- 3. Administrative reviews are scheduled with program staff who will conduct the review. Applicants or their authorized agent should call the appropriate regional office, according to the county in which the project is located, to schedule a review. The average meeting time is one hour.
- 4. In the meeting, the application is examined for administrative completeness. Deficiencies will be noted by staff and emailed or faxed to the applicant and authorized agent at the end of the meeting, or shortly after. Administrative deficiencies will cause the application to be deemed incomplete and returned.
  - An appointment should be made to resubmit the application. The application is re-examined to ensure all deficiencies are resolved. The application will only be deemed administratively complete when all administrative deficiencies are addressed.
- 5. If an application is received by mail, courier service, or otherwise submitted without a review meeting, the administrative review will be conducted within 30 days. The applicant and agent will be contacted with the results of the administrative review. If the application is found to be administratively incomplete, it can be retrieved from the regional office or returned by regular mail. If returned by mail, the regional office may require arrangements for return shipping.
- 6. If the geologic assessment was completed before October 1, 2004 and the site contains "possibly sensitive" features, the assessment must be updated in accordance with the *Instructions to Geologists* (TCEQ-0585 Instructions).

#### **Technical Review**

- When an application is deemed administratively complete, the technical review period begins. The regional
  office will distribute copies of the application to the identified affected city, county, and groundwater
  conservation district whose jurisdiction includes the subject site. These entities and the public have 30 days
  to provide comments on the application to the regional office. All comments received are reviewed by TCEQ.
- 2. A site assessment is usually conducted as part of the technical review, to evaluate the geologic assessment and observe existing site conditions. The site must be accessible to our staff. The site boundaries should be

- clearly marked, features identified in the geologic assessment should be flagged, roadways marked and the alignment of the Sewage Collection System and manholes should be staked at the time the application is submitted. If the site is not marked the application may be returned.
- 3. We evaluate the application for technical completeness and contact the applicant and agent via Notice of Deficiency (NOD) to request additional information and identify technical deficiencies. There are two deficiency response periods available to the applicant. There are 14 days to resolve deficiencies noted in the first NOD. If a second NOD is issued, there is an additional 14 days to resolve deficiencies. If the response to the second notice is not received, is incomplete or inadequate, or provides new information that is incomplete or inadequate, the application must be withdrawn or will be denied. Please note that because the technical review is underway, whether the application is withdrawn or denied **the application fee will be forfeited**.
- 4. The program has 90 calendar days to complete the technical review of the application. If the application is technically adequate, such that it complies with the Edwards Aquifer rules, and is protective of the Edwards Aquifer during and after construction, an approval letter will be issued. Construction or other regulated activity may not begin until an approval is issued.

#### **Mid-Review Modifications**

It is important to have final site plans prior to beginning the permitting process with TCEQ to avoid delays.

Occasionally, circumstances arise where you may have significant design and/or site plan changes after your Edwards Aquifer application has been deemed administratively complete by TCEQ. This is considered a "Mid-Review Modification". Mid-Review Modifications may require redistribution of an application that includes the proposed modifications for public comment.

If you are proposing a Mid-Review Modification, two options are available:

- If the technical review has begun your application can be denied/withdrawn, your fees will be forfeited, and the plan will have to be resubmitted.
- TCEQ can continue the technical review of the application as it was submitted, and a modification application can be submitted at a later time.

If the application is denied/withdrawn, the resubmitted application will be subject to the administrative and technical review processes and will be treated as a new application. The application will be redistributed to the affected jurisdictions.

Please contact the regional office if you have questions. If your project is located in Williamson, Travis, or Hays County, contact TCEQ's Austin Regional Office at 512-339-2929. If your project is in Comal, Bexar, Medina, Uvalde, or Kinney County, contact TCEQ's San Antonio Regional Office at 210-490-3096

Please fill out all required fields below and submit with your application.

| 1. Regulated Entity Name:                                |         |           |                 |                  | 2. Regulated Entity No.: |        |        |                            |                               |
|--|---------|-----------|-----------------|------------------|--------------------------|--------|--------|----------------------------|-------------------------------|
| 3. Customer Name:  |         |           |                 | 4. Customer No.: |                          |        |        |                            |                               |
| 5. Project Type: (Please circle/check one)  Modification |         | Extension |                 | Exception        |                          |        |        |                            |                               |
| 6. Plan Type:<br>(Please circle/check one)               | WPAP    | CZP       | SCS             | UST              | AST                      | EXP    | EXT    | Technical<br>Clarification | Optional Enhanced<br>Measures |
| 7. Land Use:<br>(Please circle/check one)                | Resider | ntial     | Non-r           | esiden           | tial                     |        | 8. Sit | e (acres):                 |                               |
| 9. Application Fee:                                      |         |           | 10. P           | ermai            | nent I                   | BMP(   | s):    |                            |                               |
| 11. SCS (Linear Ft.):                                    |         |           | 12. AST/UST (No |                  |                          | o. Tar | ıks):  |                            |                               |
| 13. County:  |         |           | 14. W           | aters            | hed:                     |        |        |                            |                               |

#### **Application Distribution**

Instructions: Use the table below to determine the number of applications required. One original and one copy of the application, plus additional copies (as needed) for each affected incorporated city, county, and groundwater conservation district are required. Linear projects or large projects, which cross into multiple jurisdictions, can require additional copies. Refer to the "Texas Groundwater Conservation Districts within the EAPP Boundaries" map found at:

http://www.tceq.texas.gov/assets/public/compliance/field\_ops/eapp/EAPP%20GWCD%20map.pdf

For more detailed boundaries, please contact the conservation district directly.

| Austin Region                           |   |   |  |  |  |
|---|---|---|--|--|--|
| County:                                 | Hays  | Travis  | Williamson   |  |  |
| Original (1 req.)                       |   | _   |  |  |  |
| Region (1 req.)                         |   | _   | _  |  |  |
| County(ies)                             |   |   |  |  |  |
| Groundwater Conservation<br>District(s) | Edwards Aquifer AuthorityBarton Springs/ Edwards AquiferHays Trinity Plum Creek | Barton Springs/<br>Edwards Aquifer  | NA   |  |  |
| City(ies) Jurisdiction                  | AustinBudaDripping SpringsKyleMountain CitySan MarcosWimberleyWoodcreek         | AustinBee CavePflugervilleRollingwoodRound RockSunset ValleyWest Lake Hills | AustinCedar ParkFlorenceGeorgetownJerrellLeanderLiberty HillPflugervilleRound Rock |  |  |

| San Antonio Region                         |  |   |        |                              |               |  |
|--|--|---|--------|------------------------------|---------------|--|
| County:                                    | Bexar  | Comal   | Kinney | Medina                       | Uvalde        |  |
| Original (1 req.)                          |  |   |        |                              |               |  |
| Region (1 req.)                            |  |   |        |                              |               |  |
| County(ies)                                |  |   |        |                              |               |  |
| Groundwater<br>Conservation<br>District(s) | Edwards Aquifer<br>Authority<br>Trinity-Glen Rose  | Edwards Aquifer<br>Authority  | Kinney | EAA<br>Medina                | EAA<br>Uvalde |  |
| City(ies)<br>Jurisdiction                  | Castle HillsFair Oaks RanchHelotesHill Country VillageHollywood ParkSan Antonio (SAWS)Shavano Park | Bulverde<br>Fair Oaks Ranch<br>Garden Ridge<br>New Braunfels<br>Schertz | NA     | San<br>Antonio ETJ<br>(SAWS) | NA            |  |

| I certify that to the best of my knowledge, that the application is complete and accurate. This application is hereby submitted to TCEQ for administrative review and technical review. |      |  |  |  |
|---|------|--|--|--|
|   |      |  |  |  |
| Print Name of Customer/Authorized Agent   |      |  |  |  |
| David E. Martin   |      |  |  |  |
| Signature of Customer/Authorized Agent  | Date |  |  |  |

| **FOR TCEQ INTERNAL USE ONLY**                   |                              |  |  |  |  |
|--|------------------------------|--|--|--|--|
| Date(s)Reviewed: Date Administratively Complete: |                              |  |  |  |  |
| Received From:                                   | Correct Number of Copies:    |  |  |  |  |
| Received By:                                     | Distribution Date:           |  |  |  |  |
| EAPP File Number:                                | Complex:                     |  |  |  |  |
| Admin. Review(s) (No.):                          | No. AR Rounds:               |  |  |  |  |
| Delinquent Fees (Y/N):                           | Review Time Spent:           |  |  |  |  |
| Lat./Long. Verified:                             | SOS Customer Verification:   |  |  |  |  |
| Agent Authorization<br>Complete/Notarized (Y/N): | Payable to TCEQ (Y/N):       |  |  |  |  |
| Core Data Form Complete (Y/N):                   | Check: Signed (Y/N):         |  |  |  |  |
| Core Data Form Incomplete Nos.:                  | Less than 90 days old (Y/N): |  |  |  |  |

## GENERAL INFORMATION FORM (TCEQ-0587)

#### **General Information Form**

**Texas Commission on Environmental Quality** 

Print Name of Customer/Agent: <u>David Martinez</u>, P.E.

For Regulated Activities on the Edwards Aquifer Recharge and Transition Zones and Relating to 30 TAC §213.4(b) & §213.5(b)(2)(A), (B) Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

#### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **General Information Form** is hereby submitted for TCEQ review. The application was prepared by:

| Da  | te: <u>08/12/2025</u>   |  |
|-----|---|--|
| Sig | nature of Customer/Agent:   |  |
| 1   | David E. Martin   |  |
| P   | roject Information  |  |
| 1.  | Regulated Entity Name: Canyon Golf Retail   |  |
| 2.  | County: Bexar   |  |
| 3.  | Stream Basin: <u>Upper Salado Creek</u>   |  |
| 4.  | Groundwater Conservation District (If applicable): Edwards Aquifer Authority                  |  |
| 5.  | Edwards Aquifer Zone:   |  |
|     | Recharge Zone Transition Zone   |  |
| 6.  | Plan Type:  |  |
|     | <ul><li>WPAP</li><li>SCS</li><li>UST</li><li>Modification</li><li>Exception Request</li></ul> |  |

| 7.  | Customer (Applicant):  |   |
|-----|--|---|
|     | Contact Person: Mr. Bernardo Serra Oliver Entity: Balearia, LLC Mailing Address: 15555 Tradesman, #400 City, State: San Antonio, TX Telephone: Email Address: bernardoserrao@me.com  | Zip: <u>78249</u><br>FAX:   |
| 8.  | Agent/Representative (If any):   |   |
|     | Contact Person: <u>David Martinez</u> , <u>P.E.</u> Entity: <u>Pape-Dawson Engineers</u> Mailing Address: <u>2000 Northwest Loop 410</u> City, State: <u>San Antonio</u> , <u>TX</u> Telephone: <u>210-375-9000</u> Email Address: <u>dmartinez@pape-dawson.com</u>  | Zip: <u>78213</u><br>FAX:   |
| 9.  | Project Location:  |   |
|     | <ul> <li>☐ The project site is located inside the city lim</li> <li>☐ The project site is located outside the city light jurisdiction) of</li> <li>☐ The project site is not located within any city</li> </ul>  | mits but inside the ETJ (extra-territorial  |
| 10. | The location of the project site is described detail and clarity so that the TCEQ's Region boundaries for a field investigation.   | below. The description provides sufficient al staff can easily locate the project and site  |
|     | north on US-281 for about 5.5 miles, th  | es to merge onto US-281 North. Continue<br>en exit onto Stone Oak Parkway. Travel west<br>ly 1.2 miles; the Canyon Golf Retail will be to |
| 11. | Attachment A – Road Map. A road map sh project site is attached. The project locatio the map.  |   |
| 12. | Attachment B - USGS / Edwards Recharge USGS Quadrangle Map (Scale: 1" = 2000') o The map(s) clearly show:  | <b>Zone Map</b> . A copy of the official 7 ½ minute of the Edwards Recharge Zone is attached.   |
|     | <ul> <li>Project site boundaries.</li> <li>USGS Quadrangle Name(s).</li> <li>Boundaries of the Recharge Zone (and Drainage path from the project site to the site to the site to the site to the project site to the site site to the site site to the site site to the site site site site site site site sit</li></ul> |   |
| 13. | The TCEQ must be able to inspect the project Sufficient survey staking is provided on the  | ect site or the application will be returned.  project to allow TCEQ regional staff to locate   |

|               | he boundaries and alignment of the regulated activities and the geologic or manmade eatures noted in the Geologic Assessment.  |
|---------------|--|
| $\boxtimes$ s | urvey staking will be completed by this date: When advised by TCEQ of site visit.  |
| r             | Attachment C – Project Description. Attached at the end of this form is a detailed narrative description of the proposed project. The project description is consistent hroughout the application and contains, at a minimum, the following details: |
|               | Area of the site Offsite areas Impervious cover Permanent BMP(s) Proposed site use Site history Previous development Area(s) to be demolished  |
| 15. Exist     | ing project site conditions are noted below:   |
|               | Existing commercial site Existing industrial site Existing residential site Existing paved and/or unpaved roads Undeveloped (Cleared) Undeveloped (Undisturbed/Uncleared) Other:   |
| Prohi         | ibited Activities  |
|               | am aware that the following activities are prohibited on the Recharge Zone and are not proposed for this project:  |
| (             | <ol> <li>Waste disposal wells regulated under 30 TAC Chapter 331 of this title (relating to<br/>Underground Injection Control);</li> </ol>   |
| (             | 2) New feedlot/concentrated animal feeding operations, as defined in 30 TAC §213.3;  |
| (             | 3) Land disposal of Class I wastes, as defined in 30 TAC §335.1;   |
| (-            | 4) The use of sewage holding tanks as parts of organized collection systems; and   |
| (             | 5) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41(b), (c), and (d) of this title (relating to Types of Municipal Solid Waste Facilities).                              |
| (             | 6) New municipal and industrial wastewater discharges into or adjacent to water in the state that would create additional pollutant loading.   |
|               | am aware that the following activities are prohibited on the Transition Zone and are not proposed for this project:  |

- (1) Waste disposal wells regulated under 30 TAC Chapter 331 (relating to Underground Injection Control);
- (2) Land disposal of Class I wastes, as defined in 30 TAC §335.1; and
- (3) New municipal solid waste landfill facilities required to meet and comply with Type I standards which are defined in §330.41 (b), (c), and (d) of this title.


#### **Administrative Information**

| 18. The | e fee for the plan(s) is based on:   |
|---------|--|
|         | For a Water Pollution Abatement Plan or Modification, the total acreage of the site where regulated activities will occur.  For an Organized Sewage Collection System Plan or Modification, the total linear footage of all collection system lines.  For a UST Facility Plan or Modification or an AST Facility Plan or Modification, the total number of tanks or piping systems.  A request for an exception to any substantive portion of the regulations related to the protection of water quality.  A request for an extension to a previously approved plan. |
| 19. 🔀   | Application fees are due and payable at the time the application is filed. If the correct fee is not submitted, the TCEQ is not required to consider the application until the correct fee is submitted. Both the fee and the Edwards Aquifer Fee Form have been sent to the Commission's:   |
|         | <ul> <li>☐ TCEQ cashier</li> <li>☐ Austin Regional Office (for projects in Hays, Travis, and Williamson Counties)</li> <li>☐ San Antonio Regional Office (for projects in Bexar, Comal, Kinney, Medina, and Uvalde Counties)</li> </ul>  |
| 20.     | Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regiona office.  |
| 21. 🔀   | No person shall commence any regulated activity until the Edwards Aquifer Protection Plan(s) for the activity has been filed with and approved by the Executive Director.  |

## **ATTACHMENT A**

## **CANYON GOLF/STONE OAK PARKWAY-RETAIL Sewer Collection System Plan**





Pape-Dawson Engineers, Inc.


Date: Apr 22, 2025, 3:53pm User ID: SShrestha
File: P:\73\28\21\Design\Environmental\SCS\RM 732821.dwg

ATTACHMENT A Road Map

## **ATTACHMENT B**

#### **CANYON GOLF/STONE OAK PARKWAY RETAIL Sewage Collection System Application**





DRAINAGE FLOW ----Pape-Dawson Engineers, Inc.


MATCHLINE See Sheet 2 of 2

USGS/EDWARDS RECHARGE ZONE MAP ATTACHMENT B

## CANYON GOLF/STONE OAK PARKWAY-RETAIL Sewage Collection System Application



MATCHLINE See Sheet 1 of 2



USGS/EDWARDS RECHARGE ZONE MAP ATTACHMENT B

## **ATTACHMENT C**

### CANYON GOLF RETAIL Sewage Collection System Plan

#### Attachment C - Project Description

The Canyon Golf Retail project is a commercial development on an approximately 11.12 acres within the city of San Antonio in Bexar County, Texas. The site is located approximately northeast of the intersection of Canyon Golf and Stone Oak Parkway intersection and is currently cleared /undeveloped and lies within the Upper Salado Creek watershed, and completely over the Edwards Recharge Zone.

The Canyon Golf Retail Sewage Collection System (SCS) Application proposes the construction of a total of approximately 524 linear feet (LF) of sanitary sewer main to serve the proposed commercial development over the Edwards Aquifer Recharge Zone. The proposed alignment will consist of approximately 524 linear feet (LF) of 8-inch (8") polyvinyl chloride (PVC), SDR 26 gravity sewer main centered at water line crossings, see included plan and profile exhibits for details. Regulated activities proposed include excavation, construction of sewer mains, manholes, backfill, and compaction. Approximately 1.25 acres may be disturbed as identified by the limits of the fifty-foot (50') SCS/GA envelope shown on the plans; however additional grading will disturb approximately 11.118 acres as part of development of the overall unit as approved in the Canyon Golf Retail WPAP (EAPP ID#13001858)

This project will result in an estimated additional 150 Equivalent Dwelling Units (EDUs). Approximately 43,500 gallons per day (average flow) of domestic wastewater are estimated to be generated by this project. No Stub-outs are proposed with this SCS as this will complete this phase of the single-family development.

The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center Water Recycling Center operated by the San Antonio Water System (SAWS). Potable water will be supplied by SAWS. No naturally occurring sensitive features were identified with the SCS envelope in the Geological Assessment.



## GEOLOGIC ASSESSMENT FORM (TCEQ-0585)

#### **Geologic Assessment**

**Texas Commission on Environmental Quality** 

For Regulated Activities on The Edwards Aquifer Recharge/transition Zones and Relating to 30 TAC §213.5(b)(3), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

#### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Print Name of Geologist: Henry E. Stultz III, P.G. Telephone: 210-375-9000

|     | T/ 0.2.02  |                  |  |
|-----|--|------------------|--|
| Dat | e: February 9, 2023  | Fax:             | 210-375-9090   |
| Rep | presenting: Pape-Dawson Engineers, Inc., TBPG                              | registration nur | mber 50351   |
| Sig | nature of Geologist:   |                  | OF TELY OF THE PROPERTY OF THE |
| 0   | 133  |                  | HENRY STULTZ III  RO GEOLOGY 12121  CENSE  |
| Reg | gulated Entity Name: <u>STONE OAK / CANYON G</u>                           | OLF NEC          | Walker CE Constitution   |
| Pi  | oject Information  |                  |  |
| 1.  | Date(s) Geologic Assessment was performed:                                 | February 2, 2023 |  |
| 2.  | Type of Project:   |                  |  |
| 3.  | WPAP SCS Location of Project:  | ☐ AST<br>☐ UST   |  |
|     | Recharge Zone Transition Zone Contributing Zone within the Transition Zone | e                |  |

- 4. Attachment A Geologic Assessment Table. Completed Geologic Assessment Table (Form TCEQ-0585-Table) is attached.
- 5. Soil cover on the project site is summarized in the table below and uses the SCS Hydrologic Soil Groups\* (Urban Hydrology for Small Watersheds, Technical Release No. 55, Appendix A, Soil Conservation Service, 1986). If there is more than one soil type on the project site, show each soil type on the site Geologic Map or a separate soils map.

Table 1 - Soil Units, Infiltration Characteristics and Thickness

| Soil Name  | Group* | Thickness(feet) |
|--|--------|-----------------|
| Krum clay, 1 to 5 percent slopes                               | С      | 3-4             |
| Eckrant-Rock outcrop<br>association, 8 to 30<br>percent slopes | D      | 0-1             |
|  |        |                 |

- \* Soil Group Definitions (Abbreviated)
  - A. Soils having a high infiltration rate when thoroughly wetted.
  - B. Soils having a moderate infiltration rate when thoroughly wetted.
  - C. Soils having a slow infiltration rate when thoroughly wetted.
  - D. Soils having a very slow infiltration rate when thoroughly wetted.
- 6. Attachment B Stratigraphic Column. A stratigraphic column showing formations, members, and thicknesses is attached. The outcropping unit, if present, should be at the top of the stratigraphic column. Otherwise, the uppermost unit should be at the top of the stratigraphic column.
- 7. Attachment C Site Geology. A narrative description of the site specific geology including any features identified in the Geologic Assessment Table, a discussion of the potential for fluid movement to the Edwards Aquifer, stratigraphy, structure(s), and karst characteristics is attached.
- 8. Attachment D Site Geologic Map(s). The Site Geologic Map must be the same scale as the applicant's Site Plan. The minimum scale is 1": 400'

Applicant's Site Plan Scale:  $1'' = \underline{40'}$ Site Geologic Map Scale:  $1'' = \underline{40'}$ 

Site Soils Map Scale (if more than 1 soil type): 1'' = 200'

9. Method of collecting positional data:

☐ Global Positioning System (GPS) technology.

Other method(s). Please describe method of data collection:\_\_\_\_\_

10. The project site and boundaries are clearly shown and labeled on the Site Geologic Map.

11. Surface geologic units are shown and labeled on the Site Geologic Map.

| 12. | <ol> <li>Geologic or manmade features were discovered on the project site dur<br/>investigation. They are shown and labeled on the Site Geologic Map and are<br/>the attached Geologic Assessment Table.</li> </ol>   |               |
|-----|---|---------------|
|     | Geologic or manmade features were not discovered on the project site durinvestigation.  | ing the field |
| 13. | 3. 🔀 The Recharge Zone boundary is shown and labeled, if appropriate.   |               |
| 14. | <ol> <li>All known wells (test holes, water, oil, unplugged, capped and/or abandor<br/>applicable, the information must agree with Item No. 20 of the WPAP Application</li> </ol>   |               |
|     | There is one (1) well present on the project site and the location is shown (Check all of the following that apply.)  The wells are not in use and have been properly abandoned.  The wells are not in use and will be properly abandoned.  The wells are in use and comply with 16 TAC Chapter 76. | ·             |
|     | There are no wells or test holes of any kind known to exist on the project sit  | 6             |

#### **Administrative Information**

15. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.

## ATTACHMENT A Geologic Assessment Table

| GEOLOGIC ASSESSMENT TABLE |          |           |                 |              |           |       |     | PROJECT NAME: STONE OAK / CANYON GOLF NEC |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|---------------------------|----------|-----------|-----------------|--------------|-----------|-------|-----|---|--------------------|-----|--------------------|--------------------|--------|----------------------------------|------------|-------------|------|---------------------------|------|------------|
| LOCATION                  |          |           |                 |              |           |       | FE/ | FEATURE CHARACTERISTICS                   |                    |     |                    |                    |        |                                  | EVALUATION |             | TION | PHYSICAL SETTING          |      |            |
| 1A                        | 1B *     | 1C*       | 2A              | 2B<br>POINTS | 3         |       |     | 4   |                    | 5A  | 6                  | 7                  | 8A     | 8B                               | 9          | 10          |      | 11                        |      | 12         |
| FEATURE ID                | LATITUDE | LONGITUDE | FEATURE<br>TYPE |              | FORMATION |       |     | FEET)                                     | TREND<br>(DEGREES) | ром | DENSITY<br>(NO/FT) | APERTURE<br>(FEET) | INFILL | RELATIVE<br>INFILTRATION<br>RATE | TOTAL      | SENSITIVITY |      | CATCHMENT AREA<br>(ACRES) |      | TOPOGRAPHY |
|                           |          |           | C Comment       |              |           | Х     | Υ   | Z   | المحيدات أنسا      | 10  |                    |                    |        | l au                             | 17.        | <40         | >40  | <1.6                      | >1.6 |            |
| S-1                       | 29.64496 | -98.47943 | MB              | 30           | Kek       |       |     |   |                    |     |                    |                    | F,C    | 20                               | 50         |             | 50   |                           | X    | Hillside   |
| S-2                       | 29.64554 | -98.48001 | CD              | 5            | Kek       | 10    | 60  | 1.5                                       | N50°W              |     |                    |                    | N      | 5                                | 10         | 10          |      |                           | Х    | Drainage   |
| S-3                       | 29.64564 | -98.47961 | CD              | 5            | Kek       | 80    | 80  | 7   |                    |     |                    |                    | F      | 5                                | 10         | 10          |      | X                         |      | Hillside   |
| S-4                       | 29.64448 | -98.47920 | F               | 20           | Kek       | >2000 |     |   | N45°E              | 10  |                    |                    | F      | 5                                | 35         | 35          |      | Х                         |      | Hillside   |
| S-5                       | 29.64534 | -98.48050 | MB              | 30           | Kek       |       |     | 310                                       |                    |     |                    |                    | Χ      | 5                                | 35         | 35          |      | Х                         |      | Hillside   |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      | -                         |      |            |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|                           |          |           |                 | -            |           | _     |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |
|                           |          |           |                 |              |           |       |     |   |                    |     |                    |                    |        |                                  |            |             |      |                           |      |            |

<sup>\*\*</sup> DATUM: NAD 83



| 2A TYPE | TYPE                                | 2B POINTS |
|---------|-------------------------------------|-----------|
| С       | Cave                                | 30        |
| sc      | Solution cavity                     | 20        |
| SF      | Solution-enlarged fracture(s)       | 20        |
| F       | Fault                               | 20        |
| 0       | Other natural bedrock features      | 5         |
| МВ      | Manmade feature in bedrock          | 30        |
| sw      | Swallow hole                        | 30        |
| SH      | Sinkhole                            | 20        |
| CD      | Non-karst closed depression         | 5         |
| z       | Zone, clustered or aligned features | 30        |

|    | 8A INFILLING  |
|----|---|
| N  | None, exposed bedrock   |
| С  | Coarse - cobbles, breakdown, sand, gravel                             |
| 0  | Loose or soft mud or soil, organics, leaves, sticks, dark colors      |
| F  | Fines, compacted clay-rich sediment, soil profile, gray or red colors |
| V  | Vegetation. Give details in narrative description                     |
| FS | Flowstone, cements, cave deposits                                     |
| X  | Other materials   |

I have read, I understood, and I have followed the Texas Commission on Environmental Quality's Instructions to Geologists. The information presented here complies with that document and is a true representation of the conditions observed in the field. My signature certifies that I am qualified as a geologist as defined by 30 TAC Chapter 213.

Date February 9, 2023

Cliff, Hilltop, Hillside, Drainage, Floodplain, Streambed

## ATTACHMENT B Stratigraphic Column

## STONE OAK / CANYON GOLF NEC Geologic Assessment (TCEQ-0585)

#### <u>Attachment B – Stratigraphic Column</u>

| Period     | Epoch            | Group   | Formation              | Member                   | Thickness                                     | Lithology   | Hydro-<br>logic<br>Unit           | Hydro-<br>stratigraphic<br>Unit                              | Hydrologic<br>Function                                  | Porosity                                     | Cavern<br>Development  |
|------------|------------------|---------|------------------------|--------------------------|---|---|-----------------------------------|--|---|--|--|
|            |                  | Edwards | Kainer                 | Grainstone               | 40–50   | Hard, dense limestone that consists mostly of a tightly cemented miliolid skeletal fragment grainstone; contains interspersed chalky mudstone and wackestone; chert as beds and nodules; crossbedding and ripple marks are common primarily at the contact with the overlying regional dense bed  | quifer                            | v  | Aquifer   | IP, IG, BU,<br>FR, BP, CV                    | Few  |
|            |                  |         |                        | Kirsch-berg<br>Evaporite | 40–50   | Highly altered crystalline limestone and chalky mudstone with occasional grainstone associated with tidal channels; chert as beds and nodules, boxwork molds are common, matrix recrystallized to a coarse grain spar; intervals of collapse breccia and travertine deposits  |                                   | VI   | Aquifer   | IG, MO,<br>VUG, FR,<br>BR, CV                | Probably<br>extensive cave<br>development                              |
|            |                  |         |                        | Dolomitic                | 90–120  | Hard, dense to granular, dolomitic limestone; chert as beds and nodules (absent in lower 20 ft); Toucasia sp. abundant; lower three-fourths composed of sucrosic dolomites and grainstones with hard, dense limestones linterspersed; upper one-fourth composed mostly of hard, dense mudstone, wackestone, packstone, grainstone, and recrystallized dolomites with bioturbated beds | Edwards Aquifer                   | VII  | Aquifer   | IP, IC, IG,<br>MO, BU,<br>VUG, FR,<br>BP, CV | Cave<br>development as<br>shafts with<br>minor<br>horizontal<br>extent |
| Cretaceous | Early Cretaceous |         |                        | Basal<br>nodular         | 40–50   | Moderately hard, shaly, nodular, burrowed mudstone to miliolid grainstone that also contains dolomite; contains dark, spherical textural features known as black rotund bodies; Ceratostreon texana, Caprina sp., miliolids, and gastropods   |                                   | VIII   | Aquifer,<br>confining unit<br>in areas<br>without caves | IP, MO,<br>BU, BP,<br>FR, CV                 | Large lateral caves at surface   |
|            |                  |         | Glen Rose<br>Limestone |                          | 0–120<br>(absent in<br>northern<br>Comal Co.) |   |                                   | Cavernous  | Aquifer   | MO, BR,<br>BP, FR, CV                        |  |
|            |                  |         |                        |                          |   | 120–230<br>(thicker in<br>northern<br>Comal Co.)  | n<br>n                            | Upper Trinity<br>Lower confining unit to the Edwards aquifer | Camp Bullis   | Confining                                    | BU, BP,<br>FR,<br>occasional<br>CV                                     |
|            |                  | Trinity |                        | Upper Glen<br>Rose       | 0–10  | nodular marl, and Impure, fossiliferous limestone; gray to yellowish gray; stair-step topography; contains two distinct evaporite zones; distinct Corbula sp. bed marks the contact with the underlying lower member of the Glen  | Upper Trinity<br>3 unit to the Ed | Upper evaporite  | Aquifer   | IP, MO,<br>BU, BR                            | Some surface<br>cave<br>development                                    |
|            |                  |         |                        |                          | 0–40  | Rose Limestone; <i>Orbitulina texana</i>  | Confining                         | Fossil-  | Aquifer   | MO, BU,<br>FR, CV                            |  |
|            |                  |         |                        |                          | 80–150  |   | Lower                             | iferous<br>Lower   | Confining   | MO, BU,<br>FR                                |  |
|            |                  |         |                        |                          | 8–10  | ed from Stein and Ozuna (1995). Porosity types - Fabric selective: IP, Interparti   |                                   | Lower evaporite  |   | IP, MO,<br>BU, BR                            |  |

Source: Clark, Golab, and Morris (2016); Cavern development modified from Stein and Ozuna (1995). Porosity types - Fabric selective: IP, Interparticle porosity; IG, Intergranular porosity; IC, Intercrystalline porosity; SH, shelter porosity; MO, moldic porosity; BU, burrowed porosity; FF, fenestral; BP, bedding plane porosity. Not fabric selective: FR, fracture porosity; CH, channel porosity; BR, breccia; VUG, vug porosity; CV, cave porosity.



## ATTACHMENT C Site Geology

STONE OAK / CANYON GOLF NEC Geologic Assessment

<u>Attachment C – Site Geology</u>

**SUMMARY** 

The ±11.089-acre Stone Oak / Canyon Golf NEC site is located within Bexar County within the City of San

Antonio. It is located near the northeast corner of Stone Oak Pkwy. and Canyon Golf Rd.

Based on the results of the field survey conducted in accordance with Instructions for Geologists for

Geologic Assessments in the Edwards Aquifer Recharge/Transition Zones (TCEQ-0585 Instructions), no

naturally occurring sensitive features were identified on site. The overall potential for fluid migration to

the Edwards Aquifer for the site is low.

**SITE GEOLOGY** 

As observed through field evidence, the geologic formation which outcrops at the surface within the

subject site is the dolomitic (Kekd) is characterized as massively bedded, mudstone to grainstone,

crystalline limestone. Karst development in the Kekd is characterized by few small sinkholes and caves

developed as vertical shafts.

The predominant trend of faults in the vicinity of the site is approximately N45°E, based on faults identified

during the previous mapping of the area.

**FEATURE DESCRIPTIONS:** 

A description of the features observed onsite is provided below:

Feature S-1

Feature S-1 is a series of existing sewer lines. The sewer lines have been trenched through bedrock and

backfilled with a mix of fine and course fill material that may be more permeable than surrounding

undisturbed areas. Therefore, the probability of rapid infiltration is intermediate.

Feature S-2

Feature S-2 is a non-karst closed depression created by stream scour within intact limestone. Due to the

non-karst origin, the probability for rapid infiltration is low.

PAPE-DAWSON ENGINEERS

## STONE OAK / CANYON GOLF NEC Geologic Assessment

#### Feature S-3

Feature S-3 is a man-made non-karst closed depression within a raised berm. The depression appears to be a dry stock tank. Due to the non-karst origin, the probability of rapid infiltration is low.

#### Feature S-4

Feature S-4 is an intraformational fault within the Kek. It was identified by review of aerial photography and published maps. Due to the lack of evidence of enhanced permeability and the presence of fine-grained soil cover, the probability of rapid infiltration is low.

#### Feature S-5

Feature S-5 is a well that was identified on the Texas Water Development Board's Groundwater Database Viewer as State of Texas Well 6821702. The well casing was observed extending 1.5 feet above the ground surface, however the well appeared to be plugged as concrete was observed on the casing and up to the ground level within the casing. Water was observed pooled within the casing on top of the concrete. No plugging report was identified. Since water was observed pooled on top of the concrete within the well, the probability of rapid infiltration is low.

#### **REFERENCES**

Clark, A.K., Golab, J.A., and Morris, R.R., 2016, Geologic Framework and Hydrostratigraphy of the Edwards and Trinity Aquifers Within Northern Bexar and Comal Counties, Texas: U.S. Geological Survey Scientific Investigations Map 3366, scale 1:24,000, 20 p. pamphlet.

Nationwide Environmental Title Research, LLC. Historical Aerials, HistoricAerials.com. https://www.historicaerials.com/viewer, September 29, 2023.

Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Web Soil Survey. http://websoilsurvey.sc.egov.usda.gov/, September 29, 2023.

Stein, W.G., and Ozuna, G.B., 1995, Geologic framework and hydrogeologic characteristics of the Edwards Aquifer recharge zone, Bexar County, Texas: U.S. Geological Survey Water-Resources Investigations Report 95–4030, 8 p.

Texas Water Development Board, Wells in TWDB Groundwater Database Viewer, https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer, September 29, 2023.




## STONE OAK / CANYON GOLF NEC Geologic Assessment

U.S. Geological Survey, National Water Information System: Mapper, https://maps.waterdata.usgs.gov/mapper/index.html, September 29, 2023.



## ATTACHMENT D Site Geologic Map(s)



# ORGANIZED SEWAGE COLLECTION SYSTEM PLAN (TCEQ-0582)

## Organized Sewage Collection System Application

#### **Texas Commission on Environmental Quality**

For Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(c), Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

Regulated Entity Name: Canyon Golf Retail

1. Attachment A – SCS Engineering Design Report. This Engineering Design Report is provided to fulfill the requirements of 30 TAC Chapter 217, including 217.10 of Subchapter A, §§217.51 – 217.70 of Subchapter C, and Subchapter D as applicable, and is required to be submitted with this SCS Application Form.

#### **Customer Information**

2. The entity and contact person responsible for providing the required engineering certification of testing for this sewage collection system upon completion (including private service connections) and every five years thereafter to the appropriate TCEQ region office pursuant to 30 TAC §213.5(c) is:

Contact Person: Miguel Serra
Entity: Stone Oak 11 Acres, LLC

Mailing Address: 15555 Tradesman Dr, Ste 400

City, State: San Antonio Zip: 78249

Telephone: (210) 375-9000 Fax: (210) 375-9000

Email Address: crosstimber@me.com

The appropriate regional office must be informed of any changes in this information within 30 days of the change.

3. The engineer responsible for the design of this sewage collection system is:

Contact Person: David Martinez, P.E.

Texas Licensed Professional Engineer's Number: 94900

Entity: <u>Pape-Dawson Engineers, Inc.</u> Mailing Address: 2000 NW Loop 410

City, State: San Antonio, TX Zip: 78213

Telephone: (210) 375-9000 Fax: (210) 375-9010

Email Address:dmartinez@pape-dawson.com

#### **Project Information**

| 4.         | Anticipated type of development to be separate allowance for institutional a   | rved (estimated future population to be served, and commercial flows):            |
|------------|--|---|
|            | Residential: Number of single-fami Multi-family: Number of residentia Commercial Industrial Off-site system (not associated wit Other: | l units:  |
| 5.         | The character and volume of wastewater   | is shown below:   |
|            |  | <u>30,000</u> gallons/day   |
|            | % Industrial   | gallons/day   |
|            | % Commingled   | gallons/day   |
|            | Total gallons/day: <u>30,000 (150 EDU * 2</u>  | 200 GPD/EDU) = 30,000   |
| 6.         | Existing and anticipated infiltration/inflow adequate sizing of sewer main.  | is <u>3,000</u> gallons/day. This will be addressed by:                           |
| 7.         | A Water Pollution Abatement Plan (WPAP commercial, industrial or residential proje   | ) is required for construction of any associated ct located on the Recharge Zone. |
|            | copy of the approval letter is attached  |   |
|            |  | ment was submitted to the TCEQ on, but  |
|            | has not been approved.   |   |
|            | There is no associated project requirin  | associated project, but it has not been submitted.<br>g a WPAP application.       |
| 8.         | Pipe description:  |   |
| <u>T</u> a | able 1 - Pipe Description  |   |
|            | Dina   |   |

| Pipe             | •               |                   |                    |
|------------------|-----------------|-------------------|--------------------|
| Diameter(Inches) | Linear Feet (1) | Pipe Material (2) | Specifications (3) |
|                  |                 |                   | ASTM D3034, ASTM   |
| 8" Gravity       | 537             | PVC SDR 26        | D3212              |
|                  |                 |                   |                    |
|                  |                 |                   |                    |
|                  |                 |                   |                    |
|                  |                 |                   |                    |

**Total Linear Feet**: <u>537</u>

- (1) Linear feet Include stub-outs and double service connections. Do not include private service laterals.
- (2) Pipe Material If PVC, state SDR value.

|              |   |   | Manhole or Clean-                        |
|--------------|---|---|--|
| <u>Tab</u> l | e 2 - Manholes and Cleanouts  |   |  |
| 14.          | Manholes or clean-outs exist at the end<br>below: (Please attach additional sheet i   |   | ese locations are listed                 |
| Ма           | nholes and Cleanouts  |   |  |
| [            | Attachment B - Justification and Calcul without Manholes. A justification for decollection system without manholes with allowing pipe curvature is attached.  For curved sewer lines, all curved sewer construction plans for the wastewater of   | eviations from straight alight documentation from pige line notes (TCEQ-0596) and | gnment in this sewage<br>pe manufacturer |
| 13.          | There are no deviations from straight al without manholes.  | ignment in this sewage co   | llection system                          |
| 12. [        | There are no deviations from uniform g manholes and with open cut construction  |   | cion system without                      |
| Ali          | gnment  |   |  |
|              | A force main(s) and/or lift station(s) is a the Lift Station/Force Main System App application.   | _   |  |
| 11.          | igstyle igytyle igstyle igytyle | e associated with this sew  | vage collection system.                  |
| 10. <i>A</i> | All components of this sewage collection sy  The City of San Antonio standard sp  Other. Specifications are attached.   | • •   |  |
|              | Existing Proposed   |   |  |
|              | The sewage collection system will convey the reatment Plant. The treatment facility is:   | ne wastewater to the <u>Stev</u>  | en M. Clouse (name)                      |
|              | (3) Specifications - ASTM / ANSI / AWWA s   | pecification and class number   | ers should be included.                  |

| Line     | Shown on Sheet | Station | Manhole or Clean-<br>out? |
|----------|----------------|---------|---------------------------|
| Line "A" | C5.11 Of       | 6+36.54 | Cleanout                  |
|          | Of             |         |                           |

| Line | Shown on Sheet | Station | Manhole or Clean-<br>out? |
|------|----------------|---------|---------------------------|
|      | Of             |         |                           |

| <b>15</b> . 🛭 | Manholes are installed at all Points of Curvature and Points of Termination of a sev | ver |
|---------------|--|-----|
|               | line.  |     |

16. The maximum spacing between manholes on this project for each pipe diameter is no greater than:

| Pipe Diameter (inches) | Max. Manhole Spacing (feet) |
|------------------------|-----------------------------|
| 6 - 15                 | 500                         |
| 16 - 30                | 800                         |
| 36 - 48                | 1000                        |
| >54                    | 2000                        |

| Attachment C – Justification for Variance from Maximum Manhole Spacing. The               |
|---|
| maximum spacing between manholes on this project (for each pipe diameter used) is         |
| greater than listed in the table above. A justification for any variance from the         |
| maximum spacing is attached, and must include a letter from the entity which will         |
| operate and maintain the system stating that it has the capability to maintain lines with |
| manhole spacing greater than the allowed spacing.   |

17. All manholes will be monolithic, cast-in-place concrete.

The use of pre-cast manholes is requested for this project. The manufacturer's specifications and construction drawings, showing the method of sealing the joints, are attached.

#### Site Plan Requirements

#### Items 18 - 25 must be included on the Site Plan.

18.  $\square$  The Site Plan must have a minimum scale of 1" = 400'.

Site Plan Scale: 1" = <u>40</u>'.

- 19. The Site Plan must include the sewage collection system general layout, including manholes with station numbers, and sewer pipe stub outs (if any). Site plan must be overlain by topographic contour lines, using a contour interval of not greater than ten feet and showing the area within both the five-year floodplain and the 100-year floodplain of any drainage way.
- 20. Lateral stub-outs:

The location of all lateral stub-outs are shown and labeled.

| No lateral stub-outs will be installed during the construction of this sewer collection system.   |   |   |  |  |
|---|---|---|--|--|
| 21. Location of existing and prop   | posed water lines:  |   |  |  |
| If not shown on the Site sewer systems.   | ition system for this project is sho<br>Plan, a Utility Plan is provided sho<br>nes associated with this project.   |   |  |  |
| 22. 100-year floodplain:  |   |   |  |  |
| After construction is complete, no part of this project will be in or cross a 100-year floodplain, either naturally occurring or manmade. (Do not include streets or concrete-lined channels constructed above of sewer lines.)  After construction is complete, all sections located within the 100-year floodplain will have water-tight manholes. These locations are listed in the table below and are shown and labeled on the Site Plan. (Do not include streets or concrete-lined channels constructed above sewer lines.) |   |   |  |  |
| Table 2 100 Veer Fleedale   | !   |   |  |  |
| Table 3 - 100-Year Floodpla  Line   | in<br>Sheet   | Station   |  |  |
|   |   | <b>Station</b> to   |  |  |
|   | Sheet   |   |  |  |
|   | <b>Sheet</b><br>of  | to  |  |  |
|   | Sheet<br>of<br>of   | to<br>to  |  |  |
| 23. 5-year floodplain:  After construction is comfloodplain, either naturalined channels construct  After construction is comencased in concrete or construct of the second plain and are shown and lined channels construct.  Table 4 - 5-Year Floodplain  | of applete, no part of this project will lly occurring or man-made. (Do need above sewer lines.) applete, all sections located within apped with concrete. These located diabeled on the Site Plan. (Do not ed above sewer lines.) | to to to to  to  be in or cross a 5-year not include streets or concrete- the 5-year floodplain will be tions are listed in the table of include streets or concrete- |  |  |
| 23. 5-year floodplain:  After construction is comfloodplain, either naturalined channels construct  After construction is comencased in concrete or construction and are shown an lined channels construct  | of of of of of of of of applete, no part of this project will lly occurring or man-made. (Do need above sewer lines.) applete, all sections located within apped with concrete. These located diabeled on the Site Plan. (Do not                              | to t  |  |  |

of

of

| 24. | ⊠ Leg | al boun | daries | of the | site ar | e shown. |
|-----|-------|---------|--------|--------|---------|----------|

to

to

| 25. The <i>final plans and technical specifications</i> are submitted for the TCEQ's review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.  |  |                 |            |                                      |       |
|---|--|-----------------|------------|--------------------------------------|-------|
| Items 26 - 33 musi  | t be included on the   | Plan and P      | Profile sh | eets.                                |       |
| sewer lines<br>rated pipe<br>variance fro<br>approval fr  | <ul> <li>26. All existing or proposed water line crossings and any parallel water lines within 9 feet of sewer lines are listed in the table below. These lines must have the type of pressure rated pipe to be installed shown on the plan and profile sheets. Any request for a variance from the required pressure rated piping at crossings must include a variance approval from 30 TAC Chapter 290.</li> </ul> |                 |            |                                      |       |
|   | pe no water line cros<br>pe no water lines wit   | _               | of propos  | sed sewer lines                      |       |
| Table 5 - Water   |  |                 | ' '        |                                      |       |
| Line  | Station or<br>Closest Point  | Crossir<br>Para | _          | Horizontal<br>Separation<br>Distance |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
| 27. Vented Manho  |  |                 |            |                                      |       |
| <ul> <li>No part of this sewer line is within the 100-year floodplain and vented manholes are not required by 30 TAC Chapter 217.</li> <li>□ A portion of this sewer line is within the 100-year floodplain and vented manholes will be provided at less than 1500 foot intervals. These water-tight manholes are listed in the table below and labeled on the appropriate profile sheets.</li> <li>□ A portion of this sewer line is within the 100-year floodplain and an alternative means of venting shall be provided at less than 1500 feet intervals. A description of the alternative means is described on the following page.</li> <li>□ A portion of this sewer line is within the 100-year floodplain; however, there is no interval longer than 1500 feet located within. No vented manholes will be used.</li> <li>Table 6 - Vented Manholes</li> </ul> |  |                 |            |                                      |       |
| Line  | Manho  | ole             | S          | tation                               | Sheet |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |
|   |  |                 |            |                                      |       |

|  |   | 1  |                    |  |  |
|--|---|--|--------------------|--|--|
| Line   | Manhole   | Station  | Sheet              |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
| 28. Drop manholes:   |   |  |                    |  |  |
| Sewer lines which Sewer lines which Sewer lines which seems above  | the manhole invert are file sheets. These lines r   | vith this project.<br>manholes or "manhole st<br>listed in the table below<br>neet the requirements of | and labeled on the |  |  |
| Table 7 - Drop Manh  |   |  |                    |  |  |
| Line   | Manhole   | Station  | Sheet              |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
|  |   |  |                    |  |  |
| 29. Sewer line stub-out  | s (For proposed extension   | ons):  |                    |  |  |
|  | ub-outs are to be installe  | r line stub-outs are show<br>ed during the constructio   |                    |  |  |
| 30. Lateral stub-outs (Fo  | or proposed private serv  | ice connections):  |                    |  |  |
| The placement a  | 30. Lateral stub-outs (For proposed private service connections):  The placement and markings of all lateral stub-outs are shown and labeled.  No lateral stub-outs are to be installed during the construction of this sewage collection system.   |  |                    |  |  |
| 31. Minimum flow velocity (From Appendix A)  |   |  |                    |  |  |
| Assuming pipes are flowing full; all slopes are designed to produce flows equal to or greater than 2.0 feet per second for this system/line. |   |  |                    |  |  |
| 32. Maximum flow velo  | city/slopes (From Apper   | ndix A)  |                    |  |  |
| Assuming pipes less than or equ Attachment D – Assuming pipes  | <ul> <li>32. Maximum flow velocity/slopes (From Appendix A)</li> <li>Assuming pipes are flowing full, all slopes are designed to produce maximum flows of less than or equal to 10 feet per second for this system/line.</li> <li>Attachment D – Calculations for Slopes for Flows Greater Than 10.0 Feet per Second.         Assuming pipes are flowing full, some slopes produce flows which are greater than 10 feet per second. These locations are listed in the table below. Calculations are attached.     </li> </ul> |  |                    |  |  |

Table 8 - Flows Greater Than 10 Feet per Second

| Line | Profile Sheet | Station to Station | FPS | % Slope | Erosion/Shock<br>Protection |
|------|---------------|--------------------|-----|---------|-----------------------------|
|      |               |                    |     |         |                             |
|      |               |                    |     |         |                             |
|      |               |                    |     |         |                             |

| 33. Assuming pipes are flowing full, where flows are ≥ 10 feet per second, the pr below have been made to protect against pipe displacement by erosion and/30 TAC §217.53(I)(2)(B).  |          |
|--|----------|
| <ul> <li>□ Concrete encasement shown on appropriate Plan and Profile sheets for t listed in the table above.</li> <li>□ Steel-reinforced, anchored concrete baffles/retards placed every 50 feet appropriate Plan and Profile sheets for the locations listed in the table ab N/A</li> </ul> | shown on |

#### **Administrative Information**

- 34. The final plans and technical specifications are submitted for TCEQ review. Each sheet of the construction plans and specifications are dated, signed, and sealed by the Texas Licensed Professional Engineer responsible for the design on each sheet.
- 35. Standard details are shown on the detail sheets, which are dated, signed, and sealed by the Texas Licensed Professional Engineer, as listed in the table below:

**Table 9 - Standard Details** 

| Standard Details  | Shown on Sheet        |
|---|-----------------------|
| Lateral stub-out marking [Required]   | of C5.10              |
| Manhole, showing inverts comply with 30 TAC §217.55(I)(2) [Required]  | DD-852-01 of<br>C5.15 |
| Alternate method of joining lateral to existing SCS line for potential future connections [Required]                    | N/A of                |
| Typical trench cross-sections [Required]  | DD-804-01 of<br>C5.15 |
| Bolted manholes [Required]  | DD-852-07 of<br>C5.15 |
| Sewer Service lateral standard details [Required]   | DD-854-03 of<br>C5.15 |
| Clean-out at end of line [Required, if used]  | DD-854-02 of<br>C5.15 |
| Baffles or concrete encasement for shock/erosion protection [Required, if flow velocity of any section of pipe >10 fps] | N/A of                |

| Standard Details  | Shown on Sheet |
|---|----------------|
| Detail showing Wastewater Line/Water Line Crossing [Required, if crossings are proposed]                                | N/A of         |
| Mandrel detail or specifications showing compliance with 30 TAC §217.57(b) and (c) [Required, if Flexible Pipe is used] | N/A of         |
| Drop manholes [Required, if a pipe entering a manhole is more than 24 inches above manhole invert]                      | N/A of         |

- 36. All organized sewage collection system general construction notes (TCEQ-0596) are included on the construction plans for this sewage collection system.
- 37. All proposed sewer lines will be sufficiently surveyed/staked to allow an assessment prior to TCEQ executive director approval. If the alignments of the proposed sewer lines are not walkable on that date, the application will be deemed incomplete and returned.
  - Survey staking was completed on this date: Once advised of TCEQ site visit
- 38. Submit one (1) original and one (1) copy of the application, plus additional copies as needed for each affected incorporated city, groundwater conservation district, and county in which the project will be located. The TCEQ will distribute the additional copies to these jurisdictions. The copies must be submitted to the appropriate regional office.
- 39. Any modification of this SCS application will require TCEQ approval, prior to construction, and may require submission of a revised application, with appropriate fees.

#### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Organized Sewage Collection System Application** is hereby submitted for TCEQ review and executive director approval. The system was designed in accordance with the requirements of 30 TAC §213.5(c) and 30 TAC §217 and prepared by:

Print Name of Licensed Professional Engineer: David Martinez, P.E.

Date: 08/12/25

Place engineer's seal here:

DAVID E. MARTINEZ

94900

1/CENSE

Signature of Licensed Professional Engineer:

#### Appendix A-Flow Velocity Table

**Flow Velocity (Flowing Full)** All gravity sewer lines on the Edwards Aquifer Recharge Zone shall be designed and constructed with hydraulic slopes sufficient to give a velocity when flowing full of not less than 2.0 feet per second, and not greater than 10 feet per second. The grades shown in the following table are based on Manning's formula and an n factor of 0.013 and shall be the minimum and maximum acceptable slopes unless provisions are made otherwise.

**Table 10 - Slope Velocity** 

| Pipe Diameter(Inches) | % Slope required for minimum flow velocity of 2.0 fps | % Slope which produces flow velocity of 10.0 fps |
|-----------------------|---|--|
| 6                     | 0.50  | 12.35  |
| 8                     | 0.33  | 8.40   |
| 10                    | 0.25  | 6.23   |
| 12                    | 0.20  | 4.88   |
| 15                    | 0.15  | 3.62   |
| 18                    | 0.11  | 2.83   |
| 21                    | 0.09  | 2.30   |
| 24                    | 0.08  | 1.93   |
| 27                    | 0.06  | 1.65   |
| 30                    | 0.055   | 1.43   |
| 33                    | 0.05  | 1.26   |
| 36                    | 0.045   | 1.12   |
| 39                    | 0.04  | 1.01   |
| >39                   | *   | *  |

<sup>\*</sup>For lines larger than 39 inches in diameter, the slope may be determined by Manning's formula (as shown below) to maintain a minimum velocity greater than 2.0 feet per second when flowing full and a maximum velocity less than 10 feet per second when flowing full.

$$v = \frac{1.49}{n} \times R_h^{0.67} \times \sqrt{S}$$

Figure 1 - Manning's Formula

#### Where:

v = velocity (ft/sec)
n = Manning's roughness coefficient
(0.013)
Rh = hydraulic radius (ft)
S = slope (ft/ft)

# ATTACHMENT A (Engineering Design Report)

#### **TABLE OF CONTENTS**

| Odor Control   | 2  |
|--|----|
| Flow Calculation   | 2  |
| Capacity Calculation   | 3  |
| *When rounding of velocities is considered all velocities are at, or above, the required 2 fps | 4  |
| Conclusion   | 4  |
| Project Materials (Pipe and Joints):   | 4  |
| Project Materials (Bedding):   | 5  |
| Project Materials (Manholes):  | 5  |
| Project Materials (Manhole Covers):  | 6  |
| Minimum and Maximum Slopes   | 6  |
| Backfill   | 6  |
| Trenching  | 7  |
| Minimum and Maximum Trench Width   | 7  |
| Corrosion Prevention   | 7  |
| Manholes (General)   | 7  |
| Manholes (Inverts)   | 8  |
| Manholes (Ventilation)   | 8  |
| Live Load Calculations   | S  |
| Buckling Pressure Calculations   | S  |
| Allowable Buckling Pressure:   | g  |
| Pressure Under Installed Conditions  | 10 |
| Wall Crushing Calculations   | 11 |
| Installation Temperature Effects   | 12 |
| Tensile Strength   | 12 |
| Strain   | 12 |
| Modulus of Soil Reaction   | 12 |
| Zeta Calculation   | 13 |
| Pipe Stiffness   | 14 |
| Deflection   | 14 |



This Engineering Design Report has been prepared to comply with the Texas Commission on Environmental Quality's Design Criteria for Domestic Wastewater Systems (30 TAC 217), and regulations over the Edwards Aquifer Recharge Zone (30 TAC 213). Please note, throughout this application, the more stringent of City of San Antonio (COSA), San Antonio Water System or TCEQ regulations shall apply.

#### **PROJECT INFORMATION**

The Canyon Golf Retail project is a commercial development on approximately 11.12 acres within the city of San Antonio in Bexar County, Texas. The subject tract is located northeast of the intersection of Canyon Golf Road and Stone Oak Parkway and is currently undeveloped and in design phase for a future commercial development project. The subject tract lies entirely over the Edwards Recharge Zone and contains a 100-year floodplain.

The Canyon Golf Retail Sewage Collection System (SCS) proposes the construction of a total of approximately 524 linear feet (LF) of 8" sewer gravity main to serve the future retail center. The proposed alignment will consist of approximately 524 LF of 8-inch PVC, SDR 26 gravity sewer main. Regulated activities proposed include excavation, construction of sewer mains, backfill and compaction. Approximately 1.25 acres of the project site may be disturbed for this SCS installation as identified by the limits of the fifty-foot (50') SCS/GA envelope shown on the plans, concurrent with the overall civil infrastructure for the 8.66 acres project limits included in the WPAP.

This project will result in an estimated 150 Equivalent Dwelling Units (EDUs). The contributing acreage for inflow and infiltration is 11.12 acres. The sewage flow will be disposed of by conveyance to the existing Steven M. Clouse Water Recycling Center operated by SAWS. No naturally occurring sensitive features were identified in the Geologic Assessment.

Please refer to Sheets C5.10-C5.11 of the attached sewer plans, which show the proposed service area and its topographic features, for information regarding the capability of the existing system and facilities to handle this increased flow. This system is designed to have a minimum structural life of 50 years. Safety considerations are the responsibility of the contractor. Safety protection shall be accomplished in

accordance with the most recent requirements of the Occupational Safety and Health Administration (OSHA) Standards and Interpretations.

#### **GRAVITY SANITARY SEWER PIPING: FLOW & CAPACITY ANALYSIS**

| Basis for average flow used for design of collection system (check one or more):  |
|---|
| Per Capita Contributions:   |
| Service Connections:  |
| Land Area and Use:  |
| Fixture Analysis:   |
| Odor Control  |
| Odor Control is not necessary on this project as it is a gravity line and there will be no conditions where               |
| sewage is standing and will become septic.  |
| Flow Calculation  |
| Peaking Factor used for design: <u>3.0</u>  |
| Peaking Factor is based on: SAWS Specifications for peak dry weather flow (from SAWS USR 13.3.4)                          |
| Total EDUs = <u>150*</u> EDUs   |
| *The total number of EDUs includes flow from both currently proposed and anticipated future                               |
| construction, as based on SAWS criteria.  |
| Current:  |
| Undeveloped = 0 EDUs Future:  |
| 1 EDU = 200 gallons per day (average sewage flow)   |
| 150 EDUs x 200 gpd = 30,000 gallons per day (average sewage flow)   |
| Infiltration = 300 gallons per acre served  |
| Average flow = $[150.0 \text{ EDUs } \times (200 \text{ gpd/EDU})] + [(300 \text{ gpd/acre}) \times 11.12 \text{ acres}]$ |
| = 33,336 gpd = <b>23.15 gpm</b><br>Peak flow = [150.0 EDUs x (600 gpd/EDU)] + [(300 gpd/acre) x 11.12 acres]              |
| = 93,336  gpd = 64.82  gpm  |



Please note that capacities are determined using Manning's equation for pipes flowing full with an "n" value of 0.013. A reference for Manning's Equation can be found in "The Uni-Bell Handbook of PVC Pipe: Design and Construction".

#### **Capacity Calculation**

```
Characteristics of 8" ASTM D3034, SDR 26, PVC Sewer Pipe:
```

Nominal Size = 8"

Outer Diameter  $(D_o) = 8.40"$ 

Minimum Wall Thickness (t) = 0.323"

Inner Diameter  $(D_i) = 7.75$ "

#### Manning's Equation:

 $Q = (k/n)(A)(R^{2/3})(S^{1/2})$ 

v = Q/A

#### Where:

Q = Discharge (cfs)

 $k = Constant [(1.49 ft^{1/3})/sec.]$ 

*n* = Manning's roughness coefficient (unitless)

 $A = Flow area (ft^2)$ 

R = Hydraulic Radius (ft)

= A/P = Cross sectional area of flow ( $ft^2$ )/Wetted perimeter (ft.)

S = Slope (ft/ft)

v = Velocity of flow (ft/s)

n = 0.013 [as required by 30 TAC 213.53 A(i)]

#### Calculations for 8" ASTM D3034, SDR 26, PVC Sewer Pipe:

 $A = \pi(D_i^2)/4 = \pi(7.75 \text{ in})^2/4 = 47.17 \text{ in}^2 = 0.33 \text{ ft}^2$ 

 $P = \pi(D_i) = \pi(7.75 \text{ in}) = 24.35 \text{ in} = 2.03 \text{ ft}$ 

 $R = A/P = 0.33 \text{ ft}^2/2.03 \text{ ft.}=0.16 \text{ ft}$ 

S = 0.005

 $Q = [(1.49 \text{ ft}^{1/3}/\text{sec})/0.013](0.33 \text{ ft}^2)(0.16 \text{ ft})^{2/3}(0.005)^{1/2}$ 

Q = 0.738 cfs = Q-full

Q-full = 0.738 cfs (7.48 gallons/1 cf)(60 sec/1 min.)=**331.21 gpm** 

 $v = 0.738 \text{ cfs}/0.33 \text{ ft}^2 = 2.24 \text{ ft/s}$ 

Qmax at 85% of full flow capacity= 0.783 cfs (0.85)(7.48 gallons/1 cf)(60 sec/1 min.)=281.53 gpm

Qmax at 65% of full flow capacity= 0.82 cfs (0.65)(7.48 gallons/1 cf)(60 sec/1 min.)=215.29 gpm

| Nomina<br>Main Siz<br>(in) |      | Minimum<br>Slope (%) | Area (ft²) | Hydraulic<br>Radius (A/P)<br>ft | R <sup>2/3</sup> | S <sup>1/2</sup> | Q-Full<br>(cfs) | Max Pipe<br>(%) | Velocity<br>(ft/s) | Q-Max<br>(gpm) |
|----------------------------|------|----------------------|------------|---------------------------------|------------------|------------------|-----------------|-----------------|--------------------|----------------|
| 8                          | 8.40 | 0.5                  | 0.33       | 0.16                            | 0.29             | 0.071            | 0.738           | 85              | 2.24               | 281.53         |
| 8                          | 8.40 | 0.5                  | 0.33       | 0.16                            | 0.29             | 0.071            | 0.738           | 65              | 2.24               | 215.29         |

<sup>\*</sup>When rounding of velocities is considered all velocities are at, or above, the required 2 fps.

#### Conclusion

The proposed 8" pipe (NR & 160 psi) with a minimum slope of 0.5%, has sufficient capacity to convey the projected average and peak flows.

#### **GENERAL STRUCTURAL COMPONENTS**

#### **Project Materials (Pipe and Joints):**

| Nominal Pipe<br>Diameter (in) | Linear Feet | Pipe Material | National Standard Specification for Pipe Material | National Standard for<br>Pipe Joints |
|-------------------------------|-------------|---------------|---|--------------------------------------|
| 8 (NR)                        | 524         | PVC SDR 26    | ASTM D3034  | ASTM D3212                           |

Note: Section 217.53 (j)(4) requires a minimum pipe diameter of 6 inches for all gravity sanitary sewer collection system piping.



Watertight, size on size resilient connectors conforming to ASTM C-923 have been specified for connecting pipe to manholes. See SAWS Standard Specification for Construction Detail DD 852-01.

Where a collection system parallels a water supply pipe and a nine-foot separation distance cannot be achieved, Section 217.53 (d)(3)(A)(i) requires a collection system pipe be constructed of cast iron, ductile iron, or PVC meeting ASTM specifications with at least a 150 pounds per square inch (psi) rating for both the pipe and joints. The proposed project will comply with these requirements.

Where a collection system pipe crosses a water supply line and a nine-foot separation distance cannot be achieved, Section 217.53(d)(3)(B)(i) requires the collection system pipe be constructed of cast iron, ductile iron, or PVC with a minimum pressure rating of 150 psi. The proposed project will comply with this requirement and that of 217.53(d)(3)(B)(iii).

#### **Project Materials (Bedding):**

The specified bedding will comply with ASTM D2321-11 Class I, II or III for materials and densification. A minimum of 6 inches of bedding is required for all pipe.

| Pipe Diameter (in) | Pipe Material | Bedding Class       |  |
|--------------------|---------------|---------------------|--|
| 8                  | PVC           | Class I & Class III |  |

The selection of bedding class is based on SAWS detail DD-804-01 for sanitary sewer pipe laid in a trench. Initial backfill for the pipe sizes shown above will be Class I. Secondary backfill will be Class III. See Table 1 of ASTM D2321-11 "Soil Classes" in Appendix A of this subsection.

#### **Project Materials (Manholes):**

Section 217.55 (f) prohibits the use of bricks to adjust a manhole cover to grade or construct a manhole. The proposed project will comply with this requirement.

The inside diameter of a manhole must be no less than 48 inches.



**Engineering Design Report** 

8" PVC SDR 26

Section 217.55 (n) requires watertight, size-on-size resilient connectors that allow for differential

settlement and must conform to American Society for Testing and Materials C-923. The proposed project

complies with this requirement.

Under 30 TAC 213.5(C)(3)(A), all manholes over the Recharge Zone must be watertight, with watertight

rings and covers. The proposed project complies with this requirement.

The materials specified for manhole construction are **precast concrete**.

**Project Materials (Manhole Covers):** 

Manhole covers must be constructed of impervious materials. If personnel entry is required, a minimum

30-inch diameter clear opening must be provided. Inclusion of steps in a manhole is prohibited. If a

manhole must be located within a 100-year floodplain then a means of preventing inflow is required. A

manhole cover that is located in a roadway must meet or exceed the American Association of State

Highways and Transportation Officials Standard M-306 for load bearing.

Under 30 TAC 213.5 (c)(3)(A), all manholes over the Edwards Aquifer Recharge Zone must be watertight,

with watertight rings and covers. This proposed project complies with this requirement.

**Minimum and Maximum Slopes** 

Note: All pipes are designed with a slope that will provide a velocity of at least 2 ft/s flowing full, as

calculated using Manning's equation with an "n" value of 0.013. Additionally, the collection

system is designed to ensure that, with pipes flowing full, the velocities will be less than 10 feet

per second.

The following are the minimum and maximum slopes for each pipe diameter:

Pipe Diameter: 8" (NR)

Min. Slope: **0.5%** Max. Slope: **0.5%** 

**Backfill** 

Note: The backfill will be free of stones greater than 6 inches in diameter and free of organic or any

other unstable material. See SAWS Item No. 704 for additional specifications.

**Engineering Design Report** 

8" PVC SDR 26

**Trenching** 

Note: The trench width will be minimized while still allowing adequate width for proper compaction of

backfill, and while still ensuring that at least 6 inches of backfill exists below and on each side of

the pipe. The trench walls will be vertical to at least one foot above the pipe.

Trenching will occur over the Recharge Zone and will comply with 30 TAC 213.5.

**Minimum and Maximum Trench Width** 

Based on SAWS Standard Drawing DD-804.01 and 30 TAC 217.54:

These trench widths account for the bell diameter.

Pipe Diameter: 8" Min. Trench Width: 22" Max. Trench Width: 34"

**Corrosion Prevention** 

Proposed collection system components (pipes, manholes, etc.) will not be susceptible to deterioration

through the corrosive effects of an anaerobic sewage environment. The interior of the manholes,

however, are to be coated with a SAWS approved sewer structural coating per SAWS June 2009 Standard

Specifications (Item No. 52, Section 852.2, Item 6). Epoxy coating specifically approved. The epoxy coating

on the interior walls of the manhole provide interior corrosion protection.

**Manholes (General)** 

Note: Manholes are provided at all changes in size, grade or alignment of pipe, at the intersection of all

pipes and at the end of all lines that may be extended at a future date. A clean-out with watertight

plugs may be installed instead of a manhole if no extensions are anticipated. Clean outs must

pass all testing requirements outlined for gravity collection pipes.

The project complies with the maximum manhole spacing allowed by the TCEQ:

| Pipe Diameter (in) | Max. Manhole Spacing (ft) |
|--------------------|---------------------------|
| 6 - 15             | 500                       |
| 18 - 30            | 800                       |
| 36 - 48            | 1000                      |
| 54 or larger       | 2000                      |

| Manhole Spacing | •              |  |
|-----------------|----------------|--|
| Pipe Diameter:  | 8"             | Max. Spacing: 200 LF                                   |
| See SAWS Standa | rd Specificati | on in Appendix C for additional manhole specifications |

#### Manholes (Inverts)

The bottom of a manhole must contain a U-shaped channel, which is a smooth continuation of the inlet, and outlet pipes. The bench above the channel must be sloped a minimum of 0.5 inches per foot. See SAWS detail DD-852-01, which complies with these requirements. Note, a manhole connected to a pipe less than 15 inches in diameter must have a channel depth equal to at least half the largest pipe's diameter.

#### **Manholes (Ventilation)**

Vented manholes are not proposed for this SCS.

#### **FLEXIBLE PIPE COMPUTATIONS**

Please note, all flexible pipe computations are based on engineering principles and practices for the design of buried PVC pipe systems. Equations used can be found in "The Uni-Bell PVC Pipe Association Handbook of PVC Pipe: Design and Construction". Please note, the equations used may be in a different format than shown in the Uni-Bell Handbook. Throughout this application "160 psi" pipe refers to the pressure rating of the ASTM 2241, Class 160, SDR 26 pipe used at waterline crossings in the SCS.



#### **Live Load Calculations**

Minimum burial depth without concrete encasement is seven (7) feet. Based on Table 6-6 Live Loads on PVC pipe (from Uni-Bell Handbook for PVC) for this sewer line would be 1.22 psi.

#### **Buckling Pressure Calculations**

This area of the Edwards Aquifer is unsaturated; consequently, there are no anticipated areas where sewer pipe will be placed below the water table. The value of hw=0 as there will be no height or time period of perched water or groundwater above the pipe crowns of the proposed sewer line.

The value of H for use in these calculations is 10.5 feet as it reflects the actual burial depth for this line. The value of  $\gamma_s$  equals 143 pcf is a conservative value based on a dry unit weight of 135 pcf and a moisture content of 6%. This value is conservative as it corresponds to saturated unit weights of commonly used backfill materials. Please see information from Raba-Kistner provided in Appendix B.

#### **Allowable Buckling Pressure:**

$$q_a = 0.4*\sqrt[2]{32*R_w*B'*E_b*(E*I/D^3)}$$
 Equation 1 
$$q_a = 0.4*\sqrt[2]{32*1*0.4*400(400,000*0.003/8.08^3)} = 43.17 \ psi \ (8"\ PVC\ SDR\ 26, NR)$$
 
$$q_a = 0.4*\sqrt[2]{32*1*0.4*400(400,000*0.003/8.29^3)} = 41.54 \ psi \ (8"\ PVC\ SDR\ 26, 160 \ psi)$$

$$R_{w} = 1 - 0.33 * (h_{w}/h)$$
 Equation 2
$$R_{w} = 1 - 0.33 * (0/240) = 1$$

$$B' = \frac{1}{1 + 4 * e^{-0.065H}}$$
 Equation 3

$$B' = \frac{1}{1 + 4 \cdot e^{-0.065(5.1)}} = 0.258$$

$$I = (t^3/12) * (inches^4/linear inch)$$
 Equation 4

### **Engineering Design Report**

#### 8" PVC SDR 26

$$I = (0.323^{-3}/12) = 0.003in^{-3} (8" PVC, SDR, NR)$$
  
 $I = (0.332^{3}/12) = 0.003in^{3} (8" PVC, SDR 26, 160 psi)$ 

$$D=D_o-t$$
 Equation 5

D = 8.40 inches - 0.323 inches = 8.08 inches(8"PVC, SDR26, NR)

D = 8.62 5inches - 0.332 inches = 8.29 inches(8"PVC, SDR26, 160 psi)

#### Where:

q<sub>a</sub> = Allowable buckling pressure, pounds per square inch (psi)

h = Height of soil surface above top of pipe in inches (in)

h<sub>w</sub> = Height of water surface above top of pipe in inches (in) (groundwater elevation)

 $R_w$  = Water buoyancy factor. If hw = 0, Rw = 1. If  $0 \le hw \le h$  (groundwater elevation is between the top of the pipe and the ground surface), calculate Rw with Equation 2

H = Depth of burial in feet (ft) from ground surface to crown of pipe.

B' = Empirical coefficient of elastic support

E<sub>b</sub> = Modulus of soil reaction for the bedding material (psi)

E = Modulus of elasticity of the pipe material (psi)

I = Moment of inertia of the pipe wall cross section per linear inch of pipe, inch4/lineal inch = inch3. For solid wall pipe, "I" can be calculated with Equation 4

t = Pipe structural wall thickness (in)

D = Mean pipe diameter (in)

D<sub>o</sub> = Pipe outer diameter (in)

#### **Pressure Under Installed Conditions**

$$q_p = \gamma_w * h_w + R_w * (W_c/D) + L_l$$

Equation 6

$$q_p = 0.0361 * 0 + 1 * (125.17/8.08) + 1.22 = 16.71psi (8"PVC, SDR26, NR)$$

$$q_p = 0.0361*0 + 1*(128.43/8.29) + 1.22 = 16.71psi\ (8"PVC, SDR26, 160psi)$$

Where:

#### **Engineering Design Report**

#### 8" PVC SDR 26

q<sub>p</sub> = Pressure applied to pipe under installed conditions (psi)

 $\gamma_w = 0.0361$  pounds per cubic inch (pci), specific weight of water

W<sub>c</sub> = Vertical soil load on the pipe per unit length in pounds per linear inch (lb/in)

 $L_{l}$  = Live load (lbs)

$$W_c = \gamma_s * H * (D + t)/144$$

Equation 7

$$W_c = 143 * 15 * (8.08 + 0.323)/144 = 125.17 lb/in (8"PVC, SDR26, NR)$$

$$W_c = 143 * 15 * (8.29 + 0.332)/144 = 128.43 lb/in (8"PVC, SDR26, 160psi)$$

ys = Specific weight of soil in pounds per cubic foot (pcf)

D = Mean pipe diameter (in)

Pipe Diameter: **8" (NR)** Pipe Material: **PVC, SDR 26** g<sub>a</sub>: **43.17** g<sub>p</sub>: **16.71** 

Since  $q_a \ge q_p$ , the specific pipe is acceptable for the proposed installation.

#### **Wall Crushing Calculations**

No portion of the proposed sewer line is located in the 5-year floodplain.

$$H = (24 * P_c * A)/(\gamma_s * D_o)$$
 (Equation 8)

$$A = t(in) \times 12(in/ft)$$
 (Equation 9)

$$H=(24*4,000*3.876)/(143*8.4) = 309.77 (8"PVC,SDR26, NR)$$

$$A = 0.323(in) \times 12(in/ft) = 3.876$$

 $D_0$  = outside pipe diameter, in.

P<sub>c</sub> = compressive stress or hydrostatic design basis (HDB). For typical PVC pipe assume 4,000 psi. For any other pipe material, the HDB must be supplied by the pipe manufacturer.

#### **Engineering Design Report**

#### 8" PVC SDR 26

A = surface area of the pipe wall, in.2/ft [conversion factor of 12 applied to change from ft. to

in.]

 $\gamma_s$  = specific weight of soil in pounds per cubic foot (pcf)

H = Depth of burial in feet (ft) from ground surface to crown of pipe.

24 = conversions and coefficients

#### **Installation Temperature Effects**

Flexible pipe will be installed under favorable ambient conditions, per pipe manufacturer's specifications.

#### **Tensile Strength**

The information below is from "The Uni-Bell Handbook of PVC Pipe: Design and Construction" Table 2.1 pages 14-15. This applies to all PVC SDR-26 pipe.

Pipe Material: <u>PVC SDR 26</u> Tensile Strength: <u>7,000</u> Cell Class (PVC only) <u>12454</u>

#### **Strain**

The conditions of this installation are such that strain-related failure will not be a problem. Strain is generally not a performance-limiting factor for buried PVC pipe or a design-limiting criterion for PVC pipes according to the Uni-Bell Handbook of PVC Pipe (Chapter VII, Pages 255 and 257). As pipe deflection will be below 5%, strain-related failure is not anticipated.

#### **Modulus of Soil Reaction**

The modulus of soil reaction for the bedding material, Eb, is 400 psi.

This value was determined using the "Table 1: Soil Classification Chart" and "Table 2: Soil Classes" from ASTM D2321-11 and "Average Values of Modulus of Soil Reaction, E" Table 7.3 from "The Uni-Bell Handbook of PVC Pipe: Design and Construction". Based on SAWS detail DD-804-01, Class III material was chosen. As the secondary backfill (Class III) has a lower Modulus of Soil Reaction than initial backfill (Class II), its value was used in the calculations that follow. Class III on Table 2 corresponds to coarse-grained



soils with fines (GM, GC, SM or SC) and sandy or gravelly fine-grained soils (CL or ML). On Table 7.3, coarse-grained soils with fines at a slight compaction have an E' equal to 400 psi.

The modulus of soil reaction for the in-situ soil, E'n, is 3,000 psi

This value was determined using the "Table 1: Soil Classification Chart" and "Table 2: Soil Classes" from ASTM D 2321-11 and "Average Values of Modulus of Soil Reaction, E" Table 7.3 from "The Uni-Bell Handbook of PVC Pipe: Design and Construction". Based on SAWS detail DD-804-01, Class I material was chosen, which includes crushed rock as shown on Table 2. Compacted crushed rock on Table 7.3 has an E' equal to 3,000 psi. Values in Table 7.3 are based on empirical data and derived from laboratory and field tests for buried pipe.

Bedding to in-situ soil modulus of soil reaction ratio =  $E_b/E'_n = 400 \text{ psi}/3,000 \text{ psi} = 0.13$ 

#### **Zeta Calculation**

Where native soil is significantly weaker than bedding material, or where predicted deflection approaches 5%, the effect of native soil must be quantified using Leonhardt's Zeta factor. If the ration of bedding modulus to soil modulus is not equal to 1.0, a zeta factor must be calculated by using the equations below, where zeta is a factor, which corrects for the effect of in-situ soil on pipe stability (Uni-Bell Handbook of Pipe, page 267). To calculate zeta, directly use the formulas below. The calculations that are done to determine the zeta factors for the different pipe diameters must be included with this submittal.

$$zeta = \frac{1.44}{f + (1.44 - f)^* (E_b / E_{n'})}$$

$$zeta = \frac{1.44}{1.22 + (1.44 - 1.22)^* 0.13} = 1.15(8" PVC SDR 26, NR)$$

$$zeta = \frac{1.44}{1.22 + (1.44 - 1.22)^* 0.13} = 1.15(8" PVC SDR 26, 160 psi)$$

$$f = \frac{b/d_a - 1}{1.154 + 0.444 * (b/d_a - 1)}$$

$$f = \frac{34/8.40 - 1}{1.154 + 0.444 * (34/8.40 - 1)} = 1.22 (8" PVC, SDR 26, NR)$$

$$f = \frac{35/8.625 - 1}{1.154 + 0.444 * (35/8.625 - 1)} = 1.22 (8" PVC, SDR 26, 160 psi)$$

Where:

f = Pipe/trench width coefficient

b = Trench width (in)

d<sub>a</sub> = Pipe diameter (in)

E<sub>b</sub> = Modulus of soil reaction for the bedding material (psi)

E'<sub>n</sub> = Modulus of soil reaction for the in-situ soil (psi)

Pipe Diameter: 8" (NR) Trench Width: 34" Zeta: 1.15

#### **Pipe Stiffness**

Ps is based on National Reference Standards and manufacturer's data. Please see Table 7.1 of the "The Uni-Bell Handbook of PVC Pipe: Design and Construction" listing the pipe stiffness of 8" PVC SDR 26 as 115 psi for E = 400,000 psi.

Pipe Diameter: 8" Pipe Material: PVC SDR 26 Ps: 115 psi

#### **Deflection**

Maximum allowable deflection in installed lines is 5% (per 30 TAC 217), as determined by the deflection analysis and verified by a mandrel test. It is recommended that the percent of vertical deflection is below this range; however, a 7.5% deflection limit (recommended by ASTM D3034) provides a conservative factor of safety against structural failure (Handbook of PVC Pipe, page 249).

Note: Per Table 7.2 attached in Appendix A of the SCS Application, K = 0.096 when the bedding angle is 90 degrees. A bedding angle of 90 degrees is required as shown on SAWS detail DD-804-01.

$$\Delta Y/D(\%) = \frac{K*(L_p + L_1)*100}{(0.149*P_s) + (0.061*zeta*E_b)}$$
 (Equation 11)

$$\Delta Y/D(\%) = \frac{(0.096)(5.06)*100}{(0.149*115)+(0.061*1.15*400)} = 1.07\%$$
 for 8" 160 psi pipe

$$L_p = \frac{\gamma_s * H}{144}$$
 (Equation 12)

$$L_p = \frac{143*5.1}{144} = 5.06psi$$

 $\%\Delta Y/D$  = Predicted % vertical deflection under load

 $\Delta Y$  = Change in vertical pipe diameter under load

D = Undeflected mean pipe diameter (in)

K = Bedding angle constant

 $y_s$  = Unit weight of soil (pcf)

H = Depth of burial (ft) from ground surface to crown of pipe

 $L_p$  = Prism load (psi)

| Type of Pipe Material | P <sub>s</sub> (psi) | Zeta Factor Assumed or Calculated | Eь (psi) | % Deflection |
|-----------------------|----------------------|-----------------------------------|----------|--------------|
| 8" PVC SDR 26 (NR)    | 115                  | 1.15                              | 400      | 1.07%        |

All pipes proposed for this project have a maximum predicted deflection below 5.0%

Signature, Seal and Date of the Texas Professional Engineer Below:

# **APPENDIX A (TABLES)**



January 14, 2009

Raba-Kistner Consultants, Inc. 12821 W. Golden Lane P.O. Box 690287, San Antonio, TX 78269-0287 (210) 699-9090 • FAX (210) 699-6426 www.rkci.com

Charles P. "Frosty" Forster, P.E., P.G. Pape Dawson Engineers 555 East Ramsey San Antonio, Texas 78216

RE: Soil Unit Weight Values for Backfill Materials

Various Projects San Antonio, Texas

Dear Mr. Forster:

Raba-Kistner Consultants Inc. (R-K) is pleased to submit this letter providing general guidance for selecting design soil unit weights for use in utility trench design.

In general, the following table contains a list of the frequently used trench backfill materials in the San Antonio area. The table also contains approximate values for the soil dry unit weight, moist unit weight and saturated unit weight for these materials assuming 90 to 95 percent compaction utilizing a standard Proctor (ASTM D 698.)

| MATERIAL DESCRIPTION                | DRY UNIT<br>WEIGHT, PCF | MOIST UNIT<br>WEIGHT, PCF | SATURATED UNIT<br>WEIGHT, PCF |
|-------------------------------------|-------------------------|---------------------------|-------------------------------|
| TxDOT TEX-113E Type A, Gr. 1 or 2   | 130                     | 137                       | 143                           |
| TxDOT TEX-113E Type A, Gr. 3 thru 5 | 128                     | 135                       | 143                           |
| Limestone Millings                  | 115                     | 124                       | 134                           |
| Gravelly Clay                       | 110                     | 120                       | 132                           |
| Clay                                | 100                     | 120                       | 127                           |
| Clayey Sand                         | 95                      | 106                       | 123                           |
| Gravel (Clean)                      | 115                     | 120                       | 134                           |
| Sand (Clean)                        | 92                      | 98                        | 120                           |
| Pit Run Gravel                      | 127                     | 137                       | 142                           |

We appreciate the opportunity to be of service to you. If you have any questions or need additional assistance, please call.

Very truly yours,

RABA-KISTNER CONST

Chris L. Schultz, P. Senior Vice Presider

CLS/mem

#### SOIL CLASSIFICATION CHART

# From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

TABLE 1 Soil Classification Chart (see Classification D2487)

|   | Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests <sup>A</sup> |                                     |  | Soil Classification |                 |                                   |
|---|--|-------------------------------------|--|---------------------|-----------------|-----------------------------------|
|   |  |                                     |  |                     | Group<br>Symbol | Group Name <sup>B</sup>           |
| Coarse-Grained Soils                    | Gravels  | Clean gravels                       | C ≥ 4 and 1 ≤ Cc ≤ 3 <sup>C</sup>                  |                     | GW              | Well-graded gravel <sup>D</sup>   |
| More than 50% retained on No. 200 sieve | More than 50% of coarse fraction retained on No. 4 sieve                                 | Less than 5% of fines <sup>E</sup>  | Cu < 4 and/or 1> Cc>3 <sup>c</sup>                 |                     | GP              | Poorly graded gravel <sup>D</sup> |
|   | _  | Gravels with                        | Fines classify as ML or MH                         |                     | GM              | Silty gravel <sup>DFG</sup>       |
|   |  | more than<br>12% fines <sup>E</sup> | Fines classify as CL or CH                         |                     | GC              | Clayey gravel <sup>DFG</sup>      |
|   | Sands  | Clean sands                         | Cu ≥ 6 and 1 ≤ Cc ≤ 3 <sup>C</sup>                 |                     | SW              | Well-graded sand <sup>H</sup>     |
|   | 50% or more of coarse fraction passes on No. 4 sieve                                     | Less than 5% fines <sup>1</sup>     | Cu < 6 and/or 1 > Cc > 3 <sup>C</sup>              |                     | SP              | Poorly graded sand <sup>H</sup>   |
|   | <del>-</del>   | Sand with fines                     | Fines classify as ML or MH                         |                     | SM              | Silty sand <sup>FGH</sup>         |
|   | _  | More than 12% fines <sup>1</sup>    | Fines classify as CL or CH                         |                     | SC              | Clayey sand <sup>FGH</sup>        |
| Fine-Grained Soils                      | Silts and clays  | Inorganic                           | PI > 7 and plots on or above "A" line <sup>J</sup> |                     | CL              | Lean clay <sup>KLM</sup>          |
| 50% or more passes the No. 200 Sieve    | Liquid limit<br>less than 50   |                                     | PI < 4 and plots below "A" line <sup>J</sup>       |                     | ML              | silt <sup>KLM</sup>               |
|   | _  | Organic                             | Liquid Limit-Oven dried                            | <0.75               | OL              | Organic clay <sup>KLMN</sup>      |
|   |  |                                     | Liquid Limit-Not dried                             |                     |                 | Organic silt <sup>KLMO</sup>      |
|   | Silts and clays  | Inorganic                           | PI plots on or above "A" line                      |                     | СН              | Fat clay <sup>KLM</sup>           |
|   | Liquid limit<br>50 or more   |                                     | Plots below "A" line                               | _                   | MH              | Elastic silt <sup>KLM</sup>       |
|   | _  | Organic                             | Liquid Limit-Oven Dried                            | <0.75               | ОН              | Organic clay <sup>KLMP</sup>      |
|   |  |                                     | Liquid Limit-Not Dried                             | _                   |                 | Organic silt <sup>KLMQ</sup>      |
| Highly organic soils                    | Primarily organic matter, dark in c  | olor, and organic odor              |  |                     | PT              | peat                              |

<sup>&</sup>lt;sup>A</sup> Based on the material passing the 3-in. (75-mm) sieve.

$$Cc = \frac{(D_3)^2}{D_1 \otimes D_6}$$

GW-GM well-graded gravel with silt:

GW-GC well-graded gravel with clay

GP-GM poorly graded gravel with silt

GP-GC poorly graded gravel with clay

- <sup>F</sup> If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.
- <sup>G</sup> If fines are organic, add "with organic fines" to group name.
- $^{H}$  If soil contains  $\geq$  15 % gravel, add "with gravel" to group name.
- Sands with 5 to 12 % fines require dual symbols:

SW-SM well graded sand with silt

SW-SC well-graded sand with clay

SP-SM poorly graded sand with silt

SP-SC poorly graded sand with clay

- <sup>J</sup> If Atterberg limits plot in hatched area, soil is a CL-ML, silty clay (see Test Method D4318).
- K If soil contains 15 to 29 % plus No. 200, add "with sand" or "with gravel", whichever is predominant.
- $^{L}$  If soil contains  $\geq$  30 % plus No. 200, predominantly sand, add "sandy" to group name.
- $^{M}$  If soil contains  $\geq$  30 % plus No. 200, predominantly gravel, add "gravelly" to group name.
- $^{N}$  PI  $\geq$  4 and plots on or above "A" line.
- ° PI < 4 or plots below "A" line.
- P PI plots on or above "A" line.
- <sup>Q</sup> PI plots below "A" line.

<sup>&</sup>lt;sup>B</sup> If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

 $<sup>^{</sup>C}$  Cu = D<sub>60</sub> /  $\dot{D}_{10}$ 

 $<sup>^{</sup>D}$  If soil contains  $\geq$ 15 % sand, add "with sand" to group name.

<sup>&</sup>lt;sup>E</sup>Gravels with 5 to 12 % fines require dual symbols:

#### SOIL CLASSIFICATION CHART

# From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

#### **TABLE 2 Soil Classes**

| Soil Group <sup>A,B</sup>   | Soil Class                          | American Association of<br>State Highway and<br>Transportation Officials<br>(AASHTO) Soil Groups <sup>C</sup> |
|---|-------------------------------------|---|
| Crushed rock, angular <sup>D</sup> , 100% passing 1-1/2 in. sieve, =15 % passing #4 sieve, </= 25 % passing 3/8 in. sieve and </= 12 % passing #200 sieve</td <td>Class I</td> <td>-<b></b></td>    | Class I                             | - <b></b>   |
| Clean, coarse grained soils:<br>SW, SP, GW, GP or any soil beginning<br>with one of these symbols with = 12<br % passing #200 sieve <sup>E,F</sup>  | Class II                            | A1, A3  |
| Coarse grained soils with fines:<br>GM, GC, SM, SC or any soil beginning<br>with one of these symbols, containing ><br>12 % passing #200 sieve; Sandy or<br>gravelly fine-grained soils: CL, ML, or | Class III                           | A-2-4, A-2-5, A-2-6, or A-4 or A-6 soils<br>with more than 30% retained on #200<br>sieve                      |
| any soil beginning with one of these symbols, with >/= 30 % retained on #200 sieve  |                                     |   |
| Fine-grained soils:<br>CL, ML, or any soil beginning with one<br>of these symbols, with <30 % retained<br>on #200 sieve   | Class IV                            | A-2-7, or A-4, or A-6 soils with 30% or<br>less retained on #200 sieve  |
| MH, CH, OL, OH, PT  | Class V<br>Not for use as embedment | A5, A7  |

<sup>&</sup>lt;sup>A</sup> See Classification D2487, Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).

<sup>&</sup>lt;sup>B</sup> Limits may be imposed on the soil group to meet project or local requirements if the specified soil remains within the group. For example, some project applications require a Class I material with minimal fines to address specific structural or hydraulic conditions and the specification may read "Use Class I soil with a maximum of 5% passing the #200 sieve."

c AASHTO M145, Classification of Soils and Soil Aggregate Mixtures.

<sup>&</sup>lt;sup>D</sup> All particle face shall be fractured.

<sup>&</sup>lt;sup>E</sup> Materials such as broken coral, shells, and recycled concrete, with  $\leq$  = 12% passing a No. 200 sieve, are considered to be Class II materials. These materials should only be used when evaluated and approved by the Engineer.

F Uniform fine sands (SP) with more than 50% passing a No. 100 sieve (0.006 in., 0.15 mm) are very sensitive to moisture and should not be used as backfill unless specifically allowed in the contract documents. If use of these materials is allowed, compaction and handling procedures should follow the guidelines for Class III materials.

#### SOIL CLASSIFICATION CHART

#### From ASTM D2321-11: Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications

TABLE 3 Recommendations for Installation and Use of Soils and Aggregates for Foundation and Pipe-Zone Embedment

| Soil Class <sup>A</sup>   | Class I <sup>B</sup>   | Class II  | Class III  | Class IV   |
|---|--|---|--|--|
| General<br>Recommendations<br>and Restrictions                                      | Acceptable and common where no migration is probable or when combined with a geotextile filter media. Suitable for use as a drainage blanket and under drain where adjacent material is suitably graded or when used with a geotextile filter fabric (see X1.8). | Where hydraulic gradient exists check gradation to minimize migration. Clean groups are suitable for use as a drainage blanket and underdrain (see Table 2). Uniform fine sands (SP) with more than 50 % passing a #100 sieve (0.006 in., 0.15 mm) behave like silts and should be treated as Class IV soils. | Do not use where water conditions in trench prevent proper placement and compaction. Not recommended for use with pipes with stiffness of 9 psi or less. | Difficult to achieve high-soil stiffness. Do not use where water conditions in trench prevent proper placement and compaction. Not recommended for use with pipes with stiffness of 9 psi or less. |
| Foundation  | Suitable as foundation and for replacing over-excavated and unstable trench bottom as restricted above.  | Suitable as foundation and for replacing over-excavated and unstable trench bottom as restricted above. Install and compact in 12 in. (300 mm) maximum layers.  | Suitable for replacing over-<br>excavated trench bottom as<br>restricted above. Install and<br>compact in 6 in. (150 mm)<br>maximum layers.              | Suitable for replacing over-<br>excavated trench bottom as<br>restricted above.<br>Install and compact in 6-in<br>(150 mm) maximum layers.   |
| Pipe<br>Embedment   | Suitable as restricted above.<br>Work material under pipe to<br>provide uniform haunch<br>support.   | Suitable as restricted above.<br>Work material under pipe to<br>provide uniform haunch<br>support.  | Suitable as restricted above.<br>Difficult to place and compact<br>in the haunch zone.   | Suitable as restricted above. Difficult to place and compact in the haunch zone.   |
| Embedment<br>Compaction:<br>Min Recommended<br>Percent Compaction, SPD <sup>o</sup> | See Note <sup>c</sup>  | 85 % (SW and SP soils)<br>For GW and GP soils<br>See Note <sup>E</sup>  | 90 %   | 95 %   |
| Relative Compactive<br>Effort Required<br>to Achieve Minimum<br>Percent Compaction  | Low  | Moderate  | High   | Very high  |
| Compaction<br>Methods   | Vibration or impact  | Vibration or impact   | Impact   | Impact   |
| Required Moisture<br>Control  | None   | None  | Maintain near optimum to minimize compactive effort  | Maintain near optimum to minimize compactive effort  |

A Class V materials are unsuitable as embedment. They may be used as final backfill as permitted by the engineer.

B Class I materials have higher stiffness than Class II materials, but data on specific soil stiffness of placed, uncompacted Class I materials can be taken equivalent to Class II materials compacted to 95% of maximum standard Proctor density (SPD95), and the soil stiffness of compacted Class I materials can be taken equivalent to Class II materials compacted to 100% of maximum standard Proctor density (SPD100). Even if placed uncompacted (that is, dumped), Class I materials should always be worked into the haunch zone to assure completed placement.

C Suitable compaction typically achieved by dumped placement (that is, uncompacted but worked into haunch zone to ensure complete placement).

D SPD is standard Proctor density as determined by Test Method D609.

SPD is standard Proctor density as determined by Test Method D698.
 Place and compact GW and GP soils with at least two passes of compaction equipment.

**TABLE 6.6** LIVE LOADS ON PVC PIPE From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)

| Height              | Live Load Transferred to Pipe, lb/in <sup>2</sup> |                             | Height  | Live Load Transferred to Pipe, lb/in <sup>2</sup> |                             | Pipe, Ib/in <sup>2</sup> |           |
|---------------------|---|-----------------------------|---------|---|-----------------------------|--------------------------|-----------|
| of<br>Cover<br>(ft) | Highway<br>H20 <sup>1</sup>                       | Railway<br>E80 <sup>2</sup> | Airport | of<br>Cover<br>(ft)                               | Highway<br>H20 <sup>1</sup> | Railway<br>E80²          | Airport 3 |
| 1                   | 12.50   |                             |         | 14  | *                           | 4.17                     | 3.06      |
| 2                   | 5.56  | 26.39                       | 13.14   | 16  | *                           | 3.47                     | 2.29      |
| 3                   | 4.17  | 23.61                       | 12.28   | 18  | *                           | 2.78                     | 1.91      |
| 4                   | 2.78  | 18.40                       | 11.27   | 20  | *                           | 2.08                     | 1.53      |
| 5                   | 1.74  | 16.67                       | 10.09   | 22  | *                           | 1.91                     | 1.14      |
| 6                   | 1.39  | 15.63                       | 8.79    | 24  | *                           | 1.74                     | 1.05      |
| 7                   | 1.22  | 12.15                       | 7.85    | 26  | *                           | 1.39                     | *         |
| 8                   | 0.69  | 11.11                       | 6.93    | 28  | *                           | 1.04                     | *         |
| 10                  | *   | 7.64                        | 6.09    | 30  | *                           | 0.69                     | *         |
| 12                  | *   | 5.56                        | 4.76    | 35  | *                           | *                        | *         |
|                     |   |                             |         | 40  | *                           | *                        | *         |
|                     |   |                             |         |   |                             | -                        |           |

\* Negligible live load influence.

<sup>&</sup>lt;sup>1</sup> Simulates 20 ton truck traffic + impact (Source: ASTM A 796)
<sup>2</sup> Simulates 80,000 lb/ft railway load + impact (Source: ASTM A 796)
<sup>3</sup> 180,000 lbs. dual tandem gear assembly. 26 inch spacing between tires and 66 inch center-to-center spacing between fore and aft tires under a rigid pavement 12 inches thick + impact.

#### FIGURE 7.4 BEDDING ANGLE

From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)




TABLE 7.2 VALUES OF BEDDING CONSTANT, K

| BEDDING ANGLE (DEGREES) | <u>K</u> |
|-------------------------|----------|
| 0                       | 0.110    |
| 30                      | 0.108    |
| 45                      | 0.105    |
| 60                      | 0.102    |
| 90                      | 0.096    |
| 120                     | 0.090    |
| 180                     | 0.083    |

## APPENDIX B (SOIL UNIT WEIGHT VALUES)

#### **TABLE 7.3**

#### AVERAGE VALUES OF MODULUS OF SOIL REACTION, E'

(For Initial Flexible Pipe Deflection)

From Uni-Bell Handbook of PVC Pipe: Design and Construction, Fourth Edition (2001)

|  | E' for Degree of Compaction of Bedding, in pounds per square inch           |               |                |                |  |  |  |
|--|---|---------------|----------------|----------------|--|--|--|
|  |   | High,<br>>95% |                |                |  |  |  |
|  |   | Proctor,      | Proctor,       | Proctor,       |  |  |  |
| Soil type pine hadding material  |   | <40%          | 40%-70%        | >70%           |  |  |  |
| Soil type-pipe bedding material (Unified Classification System <sup>a</sup> )  | Dumnad  | relative      | relative       | relative       |  |  |  |
| (1)  | Dumped (2)  | density (3)   | density<br>(4) | density<br>(5) |  |  |  |
| Fine-grained Soils (LL>50) <sup>b</sup> Soils with medium to high plasticity, CH, MH, CH-MH  | No data available; consult a competent soils engineer; Otherwise use E' = 0 |               |                |                |  |  |  |
| Fine-grained Soils (LL<50) Soils with medium to no plasticity, CL, ML, ML-CL, with less than 25% coarse- grained particles   | 50  | 200           | 400            | 1,000          |  |  |  |
| Fine-grained Soils (LL<50) Soils with medium to no plasticity, CL, ML, ML-CL, with more than 25% coarse-grained particles Coarse-grained Soils with Fines GM, GC, SM, SC° contains more than 12% fines | 100   | 400           | 1,000          | 2,000          |  |  |  |
| Coarse-grained Soils with Little or no Fines GW, GP, SW, SP <sup>c</sup> contains less than 12%  |   |               |                |                |  |  |  |
| fines  | 200   | 1,000         | 2,000          | 3,000          |  |  |  |
| Crushed Rock   | 1,000   | 3,000         | 3,000          | 3,000          |  |  |  |
| Accuracy in Terms of Percentage Deflection <sup>d</sup>  | ±2  | ±2            | ±1             | ± 0.5          |  |  |  |

<sup>&</sup>lt;sup>a</sup>ASTM Designation D 2487, USBR Designation E-3.

Note: Values applicable only for fills less than 50 ft (15 m). Table does not include any safety factor. For use in predicting initial deflections only, appropriate Deflection Lag Factor must be applied for long-term deflections. If bedding falls on the borderline between two compaction categories, select lower E' value or average the two values. Percentage Proctor based on laboratory maximum dry density from test standards using about 12,500 ft-lb/cu ft (598,000 J/m³) (ASTM D 698, AASHTO T-99, USBR Designation E-11). 1 psi = 6.9 kPa.

SOURCE: "Soil Reaction for Buried Flexible Pipe" by Amster K. Howard, U.S. Bureau of Reclamation, Denver, Colorado. Reprinted with permission from American Society of Civil Engineers.

<sup>&</sup>lt;sup>b</sup>LL = Liquid limit.

<sup>°</sup>Or any borderline soil beginning with one of these symbols (i.e. GM-GC, GC-SC).

 $<sup>^{\</sup>rm d}\text{For}\pm1\%$  accuracy and predicted deflection of 3%, actual deflection would be between 2% and 4%

## 30 TAC 217 regulations will apply where more stringent than the following SAWS Specifications

Specification 852: Sanitary Sewer Manholes

https://apps.saws.org/business\_center/specs/constspecs/docs/conspecs\_2021/ITEM%20NO.%20852%20Sanitary%20Sewer%20Manholes.pdf

Specification 854: Sanitary Sewer Laterals

https://apps.saws.org/business\_center/specs/constspecs/docs/conspecs\_2021/ITEM%20NO.%20854%20Sanitary%20Sewer%20Laterals.pdf


Specification 804: Excavation, Trenching and Backfill

https://apps.saws.org/business\_center/specs/constspecs/docs/conspecs\_2021/ITEM%20NO.%20804%20Excavation%20Trenching%20and%20Backfill.pdf




# APPENDIX C (STANDARD SPECS AND PRE-CAST MANHOLES SPECS)


# PRE-CAST MANHOLE DRAWINGS & SPECIFICATIONS



(7R JOINT) REF. FORM DWG. 3-303-5561



#### **Precast Manholes**



### Illustrated: Concentric Cone Available: Eccentric Cone Rubber Gaskets at all Joints Typical Lifting Inserts in all Riser and Cone Sections Invert Channel - Shall be Water-Tight "U"-Shaped: Sloped Min. Gaskets @ all of 1" per 12". Pipe Connections - Varies Varies 4' - 10"

Varies →

#### Section View

4' I.D. Manhole - Regular Base with Reducing Cone

#### **Materials & Features**

HOLES AS SPECIFIED: Max diameter = 32" CONCRETE: 5,000 PSI, 28 day strength.

Flattop Illustration

for Shallow Manhole

REINFORCING: Meets or exceeds ASTM C478 requirements. Average weight of 24" depth base w/8" invert = 4,500 lbs. Estimated weight of riser and cone sections = 870 lbs. / vt. ft.


★ - Extended base is available to meet local requirements.

In the event a boot is loose contact your Hanson representative to resolve.

"Manufactured to your specifications."

#### -No Scale-

| TITLE   | PLANT      | STATE | SECTION. PAGE | DATE     |                       |
|---|------------|-------|---------------|----------|-----------------------|
| 4' I.D. Manhole<br>Regular Base w/Reducing Cone | Ail Plants | ТХ    | 5.5           | 08-15-06 | <sup>iii</sup> Hanson |



HOLES AS SPECIFIED: for 5' I.D. max diameter = 40"

for 6' I.D. max diameter = 54"

CONCRETE: 5,000 PSI, 28 day strength.

REINFORCING: Meets or exceeds ASTM C478 requirements.

Average weight of 24" depth base w/8" invert:

for 5' I.D. = 7.500 lbs.

for 6' I.D. = 10,600 lbs.

Estimated weight of riser and sections:

for 5' I D = 1 325 lbs. / vt ft

for 6' I.D. = 1.800 lbs. / vt. ft.

For pipe sizes 15" and larger, invert shall be equal to the larger pipe diameter.

★ - Extended base shown: Regular base also available.

In the event a boot is loose contact your Hanson representative to resolve.

"Manufactured to your specifications."

#### **Section View**

5'/4' & 6'/4' I.D. Manhole Extended Base with Reducing Cone


| Pipe I.D.<br>Size "A" |                 | O.D.    | Wall<br>Thk.<br>"C" |  |  |
|-----------------------|-----------------|---------|---------------------|--|--|
| 5'                    | 5' - 0 <b>"</b> | 6' - 0" | 6"                  |  |  |
| 6'                    | 6' - 0"         | 7' - 2" |                     |  |  |

#### -No Scale-


| TITLE  | PLANT      | STATE | SECTION PAGE | DATE     |                       |
|--|------------|-------|--------------|----------|-----------------------|
| 5'/4' & 6'/4'I.D. Manhole<br>Extended Base w/Reducing Cone | All Plants | ΤX    | 5.6          | 08-15-06 | <sup>ili</sup> Hanson |

#### **Precast Manholes**

For Pipe Entering the Manhole at Excessive Depths Above the Flow Line Out, the Contractor May be Responsible for Grout Work Necessary to Bring Channel up to Flow Line on Inlet Pipe.



Grouted Invert w/ Offset to Match Flowline of Pipe. Slight Field Adjustments May Be Necessary.



Invert Channel - Shall be
"U"-Shaped: Sloped Min.
of 1" per 12".

Varies

Pipe Max.
in notes

Varies

Plan View

Section View

#### **Materials & Features**

HOLES AS SPECIFIED:

For 4' I.D. max. diameter = 32"

For 5' I.D. max. diameter = 40"

For 6' I.D. max. diameter = 54"

CONCRETE: 5.000 PSI, 28 day strength

REINFORCING: Meets or exceeds ASTM C478 requirements.

Average weight of 24" depth base w/8" invert = 4,500 lbs

Water-tight gaskets at all pipe connections.


★ - Regular base shown: Extended base also available.

In the event a boot is loose contact your Hanson representative to resolve.


| Pipe<br>Size | 1.D.    | O.D.     | Wall<br>Thk.<br>"C" |
|--------------|---------|----------|---------------------|
| 4'           | 4' - 0" | 4' - 10" | 5*                  |
| 5'           | 5' - 0" | 6' - 0"  | 6*                  |
| 6'           | 6' - 0" | 7' - 2"  | 7"                  |

#### -No Scale-

| TITLE   | PLANT      | STATE | SECTION, PAGE | DATE     |                      |
|---|------------|-------|---------------|----------|----------------------|
| Details: 4', 5' & 6' I.D. Precast<br>Regular Manhole Base | All Plants | ΤX    | 5.7           | 08-15-06 | <sup>i</sup> 'Hanson |



#### **Plan View**



#### **Section View**

#### **Materials & Features**


CONCRETE. 5.000 PSI, 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
CONSTRUCTION OF PRECAST is in accordance with ASTM C478.
Concrete is poured according to ACI-500.

#### -No Scale-

| TITLE                   | PLANT | STATE | SECTION.PAGE | DATE     |     |
|-------------------------|-------|-------|--------------|----------|-----|
| 5' x 4' Conical Adaptor | Waco  | ТХ    | 5 8          | 08-15-06 | *** |



#### **Precast Manholes**





Varies

Lifting
Inserts

Concentric Cone 24" ø Opening

Eccentric Cone 24" ø Opening





Concentric Cone
34 1/2" ø Opening

Eccentric Cone 34 <sup>1</sup>/<sub>2</sub>" ø Opening

#### Materials & Features

CONCRETE: 5.000 PSI, 28 day strength.
REINFORCING: Meets or exceeds ASTM C478 requirements.
30" ø also available in North Texas.

#### -No Scale-

| TITLE                                   | PLANT           | STATE | SECTION.PAGE | DATE     |                      |
|---|-----------------|-------|--------------|----------|----------------------|
| Hanson 48" Manhole Reducing Cone Detail | Waco<br>Houston | TX    | 5.9          | 08-15-06 | <sup>i</sup> 'Hanson |

#### **Precast Manholes** Std. City Ring and Cover (24" or 32" Dia.) Installed by Contractor. Grade Ring(s) for Adjustment to Final Grade. Ξ 25 or 40 Vert. Joint & Gasket Detailed on Page 5.6 60" thru 120" **Pipe Connectors RCP** Usual Are Kor-N-Seal I 5 to 8 Vert. Ft. or II by NPC or Approved Equal

#### w/ Precast Base

#### Base Slab Reinforcing




60°ø - 6° Thick Slab min. - #5 @ 8° ea.way 72°o - 8° Thick Slab min. - #5 @ 8° ea.way 84°ø - 8° Thick Slab min. - #5 @ 6° ea.way 96°ø - 10° Thick Slab min. - #5 @ 6° ea.way

45' Deep Structure

60°o - 8° Thick Slab min. - #5 @ 8" ea.way 72°ø - 8" Thick Slab min. - #5 @ 8" ea.way 84°o - 10" Thick Slab min. - #5 @ 6" ea.way

96"ø - 12" Thick Slab min. - #5 @ 6" ea.way

All Reinforcing has 1 1/2" cover from top of slab.



**Isometric View** 

#### Materials & Features

CONCRETE: 5,000 PSI in 28 days.

Section A-A

REINFORCING STEEL, per ASTM A-615, Grade 60.

REINFORCING to meet AASHTO HS 20-44 Loading.

DESIGN EQUAL TO OR EXCEEDS ASTM C-478

In the event a boot is loose contact your Hanson representative to resolve.

#### Note:


 Inverts shall be specifically sized for connecting pipes; and shall be U-Shaped with the min, depth 3/4 of the largest pipe diameter.

#### No Scale-

All dimensions subject to allowable specification tolerances.

| TITLE   | PLANT                  | STATE | SECTION.PAGE | DATE     |
|---|------------------------|-------|--------------|----------|
| 30 & 45 Ft. Depth<br>60" thru 96"Large Base Manhole | Houston<br>San Antonio | ТХ    | 5.10         | 08-15-06 |

iii Hanson



**Isometric View** 

#### **Materials & Features**

CONCRETE: 5,000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615 / A-185

REINFORCING to meet AASHTO HS 20-44 Loading.


BASE DESIGN EQUAL TO OR EXCEEDS ASTM C-357

RISER DESIGN EQUAL TO OR EXCEEDS ASTM C-478

In the event a boot is loose contact your Hanson representative to resolve.

#### -No Scale-

| TITLE            | PLANT                  | STATE | SECTION, PAGE | DATE     |                       |
|------------------|------------------------|-------|---------------|----------|-----------------------|
| Type "C" Manhole | Houston<br>San Antonio | ΤX    | 5.11          | 08-15-06 | <sup>ili</sup> Hanson |



#### Materials & Features

CONCRETE: 5.000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615, Grade 60.


REINFORCING to meet AASHTO HS 20-44 Loading.

DESIGN EQUAL TO OR EXCEEDS ASTM C-478

#### -No Scale-

| TITLE                   | PLANT   | STATE | SECTION.PAGE | DATE     |                       |
|-------------------------|---------|-------|--------------|----------|-----------------------|
| ASTM C-478 Special Base | Houston | ΤX    | 5.12         | 08-15-06 | <sup>i'i</sup> Hanson |

#### **Precast Manholes**



**Section View** 

(Base configuration for 60", 72" & 84")

|      | Product Dimensions |                           |         |          |   |  |  |  |  |
|------|--------------------|---------------------------|---------|----------|---|--|--|--|--|
| Α    | В                  | С                         | D       |          |   |  |  |  |  |
| 60"  |                    |                           |         | <u> </u> | 7 |  |  |  |  |
| 72"  | П                  |                           |         |          |   |  |  |  |  |
| 84*  | Co                 | Contact your local Hanson |         |          |   |  |  |  |  |
| 96"  | rep                | resentat                  | ive for |          |   |  |  |  |  |
| 108" | dim                | nensions                  | •       |          |   |  |  |  |  |
| 120" |                    |                           |         |          | П |  |  |  |  |
| 132" | ~                  |                           |         |          |   |  |  |  |  |
| 144" |                    | 1                         |         |          | 」 |  |  |  |  |

#### **Materials & Features**

CONCRETE: 5.000 PSI in 28 days.

REINFORCING STEEL: per ASTM A-615 / A-185


REINFORCING to meet AASHTO HS 20-44 Loading.

BASE DESIGN EQUAL TO OR EXCEEDS ASTM C-357


RISER DESIGN EQUAL TO OR EXCEEDS ASTM C-478

(A). Hatches as specified by Engineer.

In the event a boot is loose contact your Hanson representative to resolve.




**Isometric View** 



**Section View** 

Base configuration for 96"




Section View

Base configuration for 108\*-144\*

#### -No Scale-

| TITLE                                | PLANT      | STATE | SECTION.PAGE | DATE     |        |
|--------------------------------------|------------|-------|--------------|----------|--------|
| Typical Wetwells - Various Diameters | All Plants | ΤX    | 5.13         | 08-15-06 | Hanson |


#### (1)"O"-Ring Gasket



Carefully clean all dirt & foreign objects from the joining surface of the bell or groove end of pipe.

Carefully clean spigot or tongue end of pipe, including the gasket recess. Inspect the bell and spigot ends of each section to make sure they are free from cracks, chips or voids that will interfere with gasket.


improperly prepared bell and spigot surfaces may prevent homing of the pipe or keep the gasket from sealing.



#### \*\*IMPORTANT\*\*

Fit the gasket carefully, equalizing the rubber gasket stretch by running a smooth, round object (inserted between the gasket & spigot) around the entire circumference several times.

Unequal stretch could cause bunching of the gasket and may cause leaks in the joint or crack the bell.




Lubricate bell joint surface liberally, covering entire inside surface using proper pipe gasket lubricant.



Lubricate the gasket throughly before it is placed on the spigot or tongue.

Bell and Gasket not lubricated or improperly lubricated may cause the gasket to roll and leak or possibly damage the bell.



Align the bell & spigot to be joined. Before homing the joint, check that the gasket is in contact with the bell end entrance taper around the entire circumference.

Do not force sections together. If sections do not seat properly, unstack and contact your Hanson Sales Representative.

Improper alignment can dislodge gasket, causing leaks or possibly breaking the bell.

#### **Profile Gasket**

- 1. Manhole sections should be handed with extreme caution to avoid chipping of the bell or spigot ends. Proper lifting devices must be used on all sections.
- 2. Inspect gasket sealing area for any voids or rough edges that may interfere with the seal.
- 3. Place the 4-G Gasket in the step of the spigot. (Making sure that the pointed end of the gasket is toward the end of the pipe as shown in Fig A.)
- 4. \*\* IMPORTANT \*\* Equalize the stretch on the gasket by pulling the sealing lube away from the spigot at least one inch and then releasing the gasket. Repeat this every three or four inches around the circumference of the pipe. Equalization of stretch makes sure that the gasket has the same stretched crosssection and tension throughout. \*\*Do not lube the gasket or spigot end of the pipe. \*\*
- 5. Remove all dirt and other foreign matter from the inside surface of the bell. Apply lube to the inner surface of the beil including the

exceed the design capacity of the pipe to manhole connector.

lead-in taper surface on the outer edge of the

- 6. Push the manhole section carefully, until the spigot is all the way home. (Fig B) Do not force sections together. If sections do not seat properly, unstack and contact your Hanson Sales Representative.
- 7. Every manhole will not come home exactly the same. Differences in application, consistency of lubricants, dimensions in the spigot and groove will cause variations in installation. If joining problems arise, please contact the manhole manufacturer immediately rather than forcing manhole sections together with subsequent damage to the manhole.
- 8. All testing should be performed prior to backfill of the manhole. Problems can not be detected after the manhole is backfilled.

bell. Align spigot with the bell. Gasket should touch lead-in taper around the entire circumference before pushing the pipe home.



Fig. A




Fig. B

Testing the manhole after backfill voids all warranties. Note: Manholes in excess of 30' in depth must be vacuum tested prior to backfill. The loads

| TITLE                    | PLANT      | Ja    | I             | <del></del> |                       |
|--------------------------|------------|-------|---------------|-------------|-----------------------|
|                          | FLANT      | SIAIE | SECTION. PAGE | DATE        |                       |
| O-Ring & Profile Gasket  |            |       |               |             |                       |
| Installation on Manholes | All Plants | TX    | 5.14          | 08-15-06    | <sup>iii</sup> Hanson |

presented by soils and possible groundwater at 30' in addition to the load from the vacuum may


#### **Precast Manholes**











**Multiple Clamps** 

#### **Instructions**

- 1. Clean pipe and boot to ensure no dirt or foreign materials are present.
- 2. Clamping surface on pipe must be clean and smooth.
- 3. Center pipe in opening and insert until pipe is at least equal to the inside plane of the manhole.
- 4. Attach take-up clamps(s) and stagger screw(s) of clamps(s) around the groove of the gasket so that take-up pressure will be equalized. Make sure each clamp is completely in the correct groove.
- 5. Using a torque ratchet or torque wrench, gradually tighten all screw(s) of clamp(s) in an alternating pattern to 60 lbs/in torque.
- 6. After reaching 60 lbs/in torque on final screw, check all screws again to ensure equal compression of all clamps.
- If system is to be tested, testing shall be completed prior to backfilling, following all recommendations and requirements of the test system manufacturer. Vacuum testing shall be conducted in accordance with ASTM C-1244.
- 8. Adjust pipe to line and grade. Use proper bedding, backfill materials and techniques so that pipe deflection and deformation is minimized.
- 9. Any pipe stubs installed in the manhole must be positively restrained from movement.
- 10. Vacuum testing after backfill voids warranty.


For more information contact yor local Hanson Representative.

PLANT STATE SECTION.PAGE DATE

Pipe to Manhole Connector
Installation Guide

PLANT STATE SECTION.PAGE DATE

All Plants TX 5.15 08-15-06 Hanson



## TEMPORARY STORMWATER SECTION (TCEQ-0602)

#### **Temporary Stormwater Section**

**Texas Commission on Environmental Quality** 

for Regulated Activities on the Edwards Aquifer Recharge Zone and Relating to 30 TAC §213.5(b)(4)(A), (B), (D)(I) and (G); Effective June 1, 1999

To ensure that the application is administratively complete, confirm that all fields in the form are complete, verify that all requested information is provided, consistently reference the same site and contact person in all forms in the application, and ensure forms are signed by the appropriate party.

Note: Including all the information requested in the form and attachments contributes to more streamlined technical reviews.

#### Signature

To the best of my knowledge, the responses to this form accurately reflect all information requested concerning the proposed regulated activities and methods to protect the Edwards Aquifer. This **Temporary Stormwater Section** is hereby submitted for TCEQ review and executive director approval. The application was prepared by:

Print Name of Customer/Agent: David Martinez, P.E.

Date: <u>08/12/25</u>

Signature of Customer/Agent:

Regulated Entity Name: Stone Oak 11 Acres, LLC

David E. Mortin

#### **Project Information**

#### **Potential Sources of Contamination**

Examples: Fuel storage and use, chemical storage and use, use of asphaltic products, construction vehicles tracking onto public roads, and existing solid waste.

| Τ. | rueis for construction equipment and nazardous substances which will be used during      |
|----|--|
|    | construction:  |
|    | The following fuels and/or hazardous substances will be stored on the site: Construction |
|    | Staging Area   |

Eugls for construction againment and hazardous substances which will be used during

These fuels and/or hazardous substances will be stored in:

Aboveground storage tanks with a cumulative storage capacity of less than 250 gallons will be stored on the site for less than one (1) year.

|    | <ul> <li>Aboveground storage tanks with a cumulative storage capacity between 250 gallons and 499 gallons will be stored on the site for less than one (1) year.</li> <li>Aboveground storage tanks with a cumulative storage capacity of 500 gallons or more will be stored on the site. An Aboveground Storage Tank Facility Plan application must be submitted to the appropriate regional office of the TCEQ prior to moving the tanks onto the project.</li> </ul> |
|----|---|
|    | Fuels and hazardous substances will not be stored on the site.  |
| 2. | Attachment A - Spill Response Actions. A site specific description of the measures to be taken to contain any spill of hydrocarbons or hazardous substances is attached.  |
| 3. | Temporary aboveground storage tank systems of 250 gallons or more cumulative storage capacity must be located a minimum horizontal distance of 150 feet from any domestic, industrial, irrigation, or public water supply well, or other sensitive feature.   |
| 4. | Attachment B - Potential Sources of Contamination. A description of any activities or processes which may be a potential source of contamination affecting surface water quality is attached.   |
| Se | equence of Construction   |
| 5. | Attachment C - Sequence of Major Activities. A description of the sequence of major activities which will disturb soils for major portions of the site (grubbing, excavation, grading, utilities, and infrastructure installation) is attached.   |
|    | <ul> <li>For each activity described, an estimate (in acres) of the total area of the site to be disturbed by each activity is given.</li> <li>For each activity described, include a description of appropriate temporary control measures and the general timing (or sequence) during the construction process that the measures will be implemented.</li> </ul>  |
| 6. | Name the receiving water(s) at or near the site which will be disturbed or which will   |

#### Temporary Best Management Practices (TBMPs)

receive discharges from disturbed areas of the project: Salado Creek

Erosion control examples: tree protection, interceptor swales, level spreaders, outlet stabilization, blankets or matting, mulch, and sod. Sediment control examples: stabilized construction exit, silt fence, filter dikes, rock berms, buffer strips, sediment traps, and sediment basins. Please refer to the Technical Guidance Manual for guidelines and specifications. All structural BMPs must be shown on the site plan.

7. Attachment D – Temporary Best Management Practices and Measures. TBMPs and measures will prevent pollution of surface water, groundwater, and stormwater. The construction-phase BMPs for erosion and sediment controls have been designed to retain sediment on site to the extent practicable. The following information is attached:

|      | A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.   |
|------|---|
|      | A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.  |
|      | A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.   |
|      | A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.  |
| 8. 🔀 | The temporary sealing of a naturally-occurring sensitive feature which accepts recharge to the Edwards Aquifer as a temporary pollution abatement measure during active construction should be avoided.   |
|      | Attachment E - Request to Temporarily Seal a Feature. A request to temporarily seal a feature is attached. The request includes justification as to why no reasonable and practicable alternative exists for each feature.  |
|      | There will be no temporary sealing of naturally-occurring sensitive features on the site.   |
| 9.   | Attachment F - Structural Practices. A description of the structural practices that will be used to divert flows away from exposed soils, to store flows, or to otherwise limit runoff discharge of pollutants from exposed areas of the site is attached. Placement of structural practices in floodplains has been avoided. |
| 10.  | Attachment G - Drainage Area Map. A drainage area map supporting the following requirements is attached:  |
|      | For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin will be provided.   |
|      | For areas that will have more than 10 acres within a common drainage area disturbed at one time, a smaller sediment basin and/or sediment trap(s) will be used.   |
|      | For areas that will have more than 10 acres within a common drainage area disturbed at one time, a sediment basin or other equivalent controls are not  |
|      | attainable, but other TBMPs and measures will be used in combination to protect down slope and side slope boundaries of the construction area.  |
|      | There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. A smaller sediment basin and/or sediment trap(s) will be used in combination with other erosion and sediment controls within each disturbed drainage area.   |

|             | There are no areas greater than 10 acres within a common drainage area that will be disturbed at one time. Erosion and sediment controls other than sediment basins or sediment traps within each disturbed drainage area will be used.   |
|-------------|---|
| 11. 🗌       | Attachment H - Temporary Sediment Pond(s) Plans and Calculations. Temporary sediment pond or basin construction plans and design calculations for a proposed temporary BMP or measure have been prepared by or under the direct supervision of a Texas Licensed Professional Engineer. All construction plans and design information must be signed, sealed, and dated by the Texas Licensed Professional Engineer. Construction plans for the proposed temporary BMPs and measures are attached. |
| $\boxtimes$ | N/A   |
| 12. 🔀       | <b>Attachment I - Inspection and Maintenance for BMPs.</b> A plan for the inspection of each temporary BMP(s) and measure(s) and for their timely maintenance, repairs, and, if necessary, retrofit is attached. A description of the documentation procedures, recordkeeping practices, and inspection frequency are included in the plan and are specific to the site and/or BMP.   |
| 13. 🔀       | All control measures must be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices. If periodic inspections by the applicant or the executive director, or other information indicate a control has been used inappropriately, or incorrectly, the applicant must replace or modify the control for site situations.   |
| 14. 🔀       | If sediment escapes the construction site, off-site accumulations of sediment must be removed at a frequency sufficient to minimize offsite impacts to water quality (e.g., fugitive sediment in street being washed into surface streams or sensitive features by the next rain).  |
| 15. 🗌       | Sediment must be removed from sediment traps or sedimentation ponds not later than when design capacity has been reduced by 50%. A permanent stake will be provided that can indicate when the sediment occupies 50% of the basin volume.   |
| 16. 🛚       | Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls, picked up daily).  |
| Soil        | Stabilization Practices   |
| mulchi      | les: establishment of temporary vegetation, establishment of permanent vegetation, ng, geotextiles, sod stabilization, vegetative buffer strips, protection of trees, or vation of mature vegetation.   |

17. X Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices. A schedule of the interim and permanent soil stabilization practices for the site is attached.

- 18. Records must be kept at the site of the dates when major grading activities occur, the dates when construction activities temporarily or permanently cease on a portion of the site, and the dates when stabilization measures are initiated.
- 19. Stabilization practices must be initiated as soon as practicable where construction activities have temporarily or permanently ceased.

#### **Administrative Information**

- 20. All structural controls will be inspected and maintained according to the submitted and approved operation and maintenance plan for the project.
- 21. If any geologic or manmade features, such as caves, faults, sinkholes, etc., are discovered, all regulated activities near the feature will be immediately suspended. The appropriate TCEQ Regional Office shall be immediately notified. Regulated activities must cease and not continue until the TCEQ has reviewed and approved the methods proposed to protect the aquifer from any adverse impacts.
- 22. Silt fences, diversion berms, and other temporary erosion and sediment controls will be constructed and maintained as appropriate to prevent pollutants from entering sensitive features discovered during construction.

## **ATTACHMENT A**

#### Attachment A - Spill Response Actions

In the event of an accidental leak or spill:

- Spill must be contained and cleaned up immediately.
- Spills will not be merely buried or washed with water.
- Contractor shall take action to contain spill. Contractor may use sand or other absorbent material stockpiled on site to absorb spill. Absorbent material should be spread over the spill area to absorb the spilled product.
- In the event of an uncontained discharge the contractor shall utilize onsite equipment to construct berms downgradient of the spill with sand or other absorbent material to contain and absorb the spilled product.
- Spill containment/absorbent materials along with impacted media must be collected and stored in such a way so as not to continue to affect additional media (soil/water). Once the spill has been contained, collected material should be placed on poly or plastic sheeting until removed from the site. The impacted media and cleanup materials should be covered with plastic sheeting and the edges weighed down with paving bricks or other similarly dense objects as the material is being accumulated. This will prevent the impacted media and cleanup materials from becoming airborne in windy conditions or impacting runoff during a rain event. The stockpiled materials should not be located within an area of concentrated runoff such as along a curb line or within a swale.
- Contaminated soils and cleanup materials will be sampled for waste characterization. When the
  analysis results are known the contaminated soils and cleanup materials will be removed from the
  site and disposed in a permitted landfill in accordance with applicable regulations.
- The contractor will be required to notify the owner, who will in turn contact TCEQ to notify them in the event of a significant hazardous/reportable quantity spill. Additional notifications as required by the type and amount of spill will be conducted by owner or owner's representative.

In the event of an accidental significant or hazardous spill:

The contractor will be required to report significant or hazardous spills in reportable quantities to:

- Notify the TCEQ by telephone as soon as possible and within 24 hours at 512-339-2929 (Austin) or 210-490-3096 (San Antonio) between 8 AM and 5 PM. After hours, contact the Environmental Release Hotline at 1-800-832-8224. It is the contractor's responsibility to have all emergency phone numbers at the construction site. <a href="https://www.tceq.texas.gov/response/spills/spill\_rq.html">https://www.tceq.texas.gov/response/spills/spill\_rq.html</a>
- For spills of federal reportable quantities, in conformance with the requirements in 40 CFR parts 110,119, and 302, the contractor should notify the National Response Center at (800) 424-8802.



- Notification should first be made by telephone and followed up with a written report.
- The services of a spills contractor or a Haz-Mat team should be obtained immediately. Construction personnel should not attempt to clean up until the appropriate and qualified staffs have arrived at the job site.
- Other agencies which may need to be consulted include, but are not limited to, the City Police Department, County Sheriff Office, Fire Departments, etc.
- Contaminated soils will be sampled for waste characterization. When the analysis results are known the contaminated soils will be removed from the site and disposed in a permitted landfill in accordance with applicable regulations.

Additional guidance can be obtained from TCEQ's Technical Guidance Manual (TGM) RG-348 (2005) Section 1.4.16. Contractor shall review this section.



## **ATTACHMENT B**

#### <u>Attachment B – Potential Sources of Contamination</u>

Other potential sources of contamination during construction include:

| Potential Source  | Preventative Measure   |
|---|--|
| Asphalt products used on this project.  | After placement of asphalt, emulsion or coatings, the contractor will be responsible for immediate cleanup should an unexpected rain occur. For the duration of the asphalt product curing time, the contractor will maintain standby personnel and equipment to contain any asphalt wash-off should an unexpected rain occur. The contractor will be instructed not to place asphalt products on the ground within 48 hours of a forecasted rain.   |
| Oil, grease, fuel, and hydraulic fluid contamination  | <ul> <li>Vehicle maintenance when possible, will be</li> </ul>   |
| from construction equipment and vehicle dripping.   | <ul> <li>performed within the construction staging area.</li> <li>Construction vehicles and equipment shall be checked regularly for leaks and repaired immediately.</li> </ul>  |
| Accidental leaks or spills of oil, petroleum products, and substances listed under 40 CFR parts 110, 117, and 302 used or stored temporarily on site. | <ul> <li>Contractor to incorporate into regular safety meetings, a discussion of spill prevention and appropriate disposal procedures.</li> <li>Contractor's superintendent or representative overseer shall enforce proper spill prevention and control measures.</li> <li>Hazardous materials and wastes shall be stored in covered containers and protected from vandalism.</li> <li>A stockpile of spill cleanup materials shall be stored on site where it will be readily accessible.</li> </ul> |
| Miscellaneous trash and litter from construction  | Trash containers will be placed throughout the   |
| workers and material wrappings.  Construction debris.   | <ul> <li>site to encourage proper trash disposal.</li> <li>Construction debris will be monitored daily by contractor. Debris will be collected weekly and placed in disposal bins. Situations requiring immediate attention will be addressed on a case-by-case basis.</li> </ul>  |
| Spills/Overflow of waste from portable toilets  | <ul> <li>Portable toilets will be placed away from high-traffic vehicular areas and storm drain inlets.</li> <li>Portable toilets will be placed on a level ground surface.</li> <li>Portable toilets will be inspected regularly for leaks and will be serviced and sanitized at time intervals that will maintain sanitary conditions.</li> </ul>  |



## **ATTACHMENT C**

#### <u>Attachment C – Sequence of Major Activities</u>

The sequence of major activities which disturb soil during construction on this site will be divided into two stages. The first is site preparation that will include clearing and grubbing of vegetation where applicable to include additional grading outside of the sewer alignment. This will disturb approximately 8.4 acres. The second is construction activities in previously cleared areas, which will include construction of sewer trenches, installation of sewer manholes, pipe, backfilling, and site cleanup, including removal of excess material. This will disturb approximately .75 acres as noted by the 50' sewer envelope.



## **ATTACHMENT D**

#### Attachment D – Temporary Best Management Practices and Measures

a. A description of how BMPs and measures will prevent pollution of surface water, groundwater or stormwater that originates upgradient from the site and flows across the site.

No upgradient water will cross the site.

b. A description of how BMPs and measures will prevent pollution of surface water or groundwater that originates on-site or flows off site, including pollution caused by contaminated stormwater runoff from the site.

Site preparation, which is the initiation of all activity on the project, will disturb the largest amount of soil. Therefore, before any of this work can begin, the clearing and grading contractor will be responsible for the installation of all on-site control measures. The methodology for pollution prevention of on-site stormwater will include: (1) erection of silt fences along the downgradient boundary of construction activities for temporary erosion and sedimentation controls, (2) installation of rock berms with silt fencing downgradient from areas of concentrated stormwater flow for temporary erosion control, (3) installation of stabilized construction entrance/exit(s) to reduce the dispersion of sediment from the site, and (4) installation of construction staging area(s).

Prior to the initiation of construction, all previously installed control measures will be repaired or reestablished for their designed or intended purpose. This work, which is the remainder of all activity on the project, may also disturb additional soil. The construction contractor will be responsible for the installation of all remaining on-site control measures that includes installation of the concrete truck washout pit(s), as construction phasing warrants.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.

c. A description of how BMPs and measures will prevent pollutants from entering surface streams, sensitive features, or the aquifer.

Temporary measures are intended to provide a method of slowing the flow of runoff from the construction site in order to allow sediment and suspended solids to settle out of the runoff. By containing the sediment and solids within the site, they will not enter surface streams and/or sensitive features.



d. A description of how, to the maximum extent practicable, BMPs and measures will maintain flow to naturally-occurring sensitive features identified in either the geologic assessment, TCEQ inspections, or during excavation, blasting, or construction.

BMP measures utilized in this plan are intended to allow stormwater to continue downstream after passing through the BMPs. This will allow stormwater runoff to continue downgradient to streams or features that may exist downstream of the site.

## **ATTACHMENT E**

Attachment E – Request to Temporarily Seal a Feature



#### **ATTACHMENT F**

#### **Attachment F – Structural Practices**

The following structural measures will be installed prior to the initiation of site preparation activities:

- Erection of silt fences along the downgradient boundary of construction activities and rock berms with silt fence for secondary protection, as located on Exhibit 1 and illustrated in Exhibit 2.
- Installation of stabilized construction entrance/exit(s) and construction staging area(s), as located on Exhibit 1, and illustrated on Exhibit 2.

The following structural measures will be installed at the initiation of construction activities or as appropriate based on the construction sequencing:

• Installation of concrete truck washout pit(s), as required and located on Exhibit 1 and illustrated on Exhibit 2.



#### **ATTACHMENT G**

#### Attachment G - Drainage Area Map

No more than ten (10) acres will be disturbed within a common drainage area at one time as construction of civil infrastructure (utilities, roads, drainage, etc.) will precede home building construction. All TBMPs utilized are adequate for the drainage areas served.



#### **ATTACHMENT H**

#### <u>Attachment H – Temporary Sedimentation Pond(s) Plans and Calculations</u>

The proposed sedimentation/filtration basins will be used as temporary sediment traps during site construction for each respective watershed. The basins will be converted to permanent basins and filter media installed after 70% of the pavement areas in each watershed have been paved.

Prior to final acceptance by the owner, the contractor will remove trash, debris and accumulated silt from each sedimentation/filtration basin and re-establish them to proper operating condition.

The minimum drain time for a full sedimentation/filtration basin is 24 hours. The contractor shall restrict the flow through the sedimentation/filtration basin by adjusting the valve on the discharge pipe so as to provide a minimum 24-hour and maximum 48-hour draw down time.



#### **ATTACHMENT I**

#### Attachment I – INSPECTIONS

Designated and qualified person(s) shall inspect Pollution Control Measures weekly and within 24 hours after a storm event. An inspection report that summarizes the scope of the inspection, names and qualifications of personnel conducting the inspection, date of the inspection, major observations, and actions taken as a result of the inspection shall be recorded and maintained as part of Storm Water TPDES data for a period of three years after the Notice of Termination (NOT) has been filed. A copy of the Inspection Report Form is provided in this Storm Water Pollution Prevention Plan.

As a minimum, the inspector shall observe: (1) significant disturbed areas for evidence of erosion, (2) storage areas for evidence of leakage from the exposed stored materials, (3) structural controls (rock berm outlets, silt fences, drainage swales, etc.) for evidence of failure or excess siltation (over 6 inches deep), (4) vehicle exit point for evidence of off-site sediment tracking, (5) vehicle storage areas for signs of leaking equipment or spills, (6) concrete truck rinse-out pit for signs of potential failure, (7) embankment, spillways, and outlet of sediment basin (where applicable) for erosion damage, and (8) sediment basins (where applicable) for evidence that basin has accumulated 50% of its volume in silt. Deficiencies noted during the inspection will be corrected and documented within seven calendar days following the inspection or before the next anticipated storm event if practicable.

Contractor shall review Sections 1.3 and 1.4 of TCEQ's Technical Guidance Manual for additional BMP inspection and maintenance requirements.



| Pollution  | ه ع                    | Corrective Action Required             |                   |  |  |  |  |
|--|------------------------|--|-------------------|--|--|--|--|
| Prevention   | nspected<br>Compliance |  | _                 |  |  |  |  |
| Measure  |                        | Description                            | Date<br>Completed |  |  |  |  |
|  | ≌ 8                    | (use additional sheet if necessary)    | Completed         |  |  |  |  |
| Best Management Practices  |                        |  |                   |  |  |  |  |
| Natural vegetation buffer strips   |                        |  |                   |  |  |  |  |
| Temporary vegetation   |                        |  |                   |  |  |  |  |
| Permanent vegetation   |                        |  |                   |  |  |  |  |
| Sediment control basin   |                        |  |                   |  |  |  |  |
| Silt fences  |                        |  |                   |  |  |  |  |
| Rock berms   |                        |  |                   |  |  |  |  |
| Gravel filter bags   |                        |  |                   |  |  |  |  |
| Drain inlet protection   |                        |  |                   |  |  |  |  |
| Other structural controls  |                        |  |                   |  |  |  |  |
| Vehicle exits (off-site tracking)  |                        |  |                   |  |  |  |  |
| Material storage areas (leakage)   |                        |  |                   |  |  |  |  |
| Equipment areas (leaks, spills)  |                        |  |                   |  |  |  |  |
| Concrete washout pit (leaks, failure)  |                        |  |                   |  |  |  |  |
| General site cleanliness   |                        |  |                   |  |  |  |  |
| Trash receptacles  |                        |  |                   |  |  |  |  |
| Evidence of Erosion  |                        |  |                   |  |  |  |  |
| Site preparation   |                        |  |                   |  |  |  |  |
| Roadway or parking lot construction  |                        |  |                   |  |  |  |  |
| Utility construction   |                        |  |                   |  |  |  |  |
| Drainage construction  |                        |  |                   |  |  |  |  |
| Building construction  |                        |  |                   |  |  |  |  |
| Major Observations   |                        |  |                   |  |  |  |  |
| Sediment discharges from site  |                        |  |                   |  |  |  |  |
| BMPs requiring maintenance   |                        |  |                   |  |  |  |  |
| BMPs requiring modification  |                        |  |                   |  |  |  |  |
| Additional BMPs required   |                        |  |                   |  |  |  |  |
| A brief statement describing the qualifications of the inspector is included in this SWP3.  "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."  "I further certify I am an authorized signatory in accordance with the provisions of 30 TAC §305.128." |                        |  |                   |  |  |  |  |
|  | .50 771011             | 5.5 p. 5. 1.5 or 15 or 17 of 3505.120. |                   |  |  |  |  |
| Inspector's Name   | nspector               | 's Signature Date                      |                   |  |  |  |  |

#### **PROJECT MILESTONE DATES**

Date when major site grading activities begin: **Construction Activity** Date Installation of BMPs Dates when construction activities temporarily or permanently cease on all or a portion of the project: **Construction Activity** Date Dates when stabilization measures are initiated: **Stabilization Activity** <u>Date</u>

Removal of BMPs

#### **ATTACHMENT J**


#### Attachment J - Schedule of Interim and Permanent Soil Stabilization Practices

Interim on-site stabilization measures, which are continuous, will include minimizing soil disturbances by exposing the smallest practical area of land required for the shortest period of time and maximizing use of natural vegetation. As soon as practical, all disturbed soil will be stabilized as per project specifications in accordance with pages 1-35 to 1-60 of TCEQ's Technical Guidance Manual (TGM) RG-348 (2005). Mulching, netting, erosion blankets and seeding are acceptable.

Stabilization measures will be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, and except as provided below, will be initiated no more than fourteen (14) days after the construction activity in that portion of the site has temporarily or permanently ceased. Where construction activity on a portion of the site is temporarily ceased, and earth disturbing activities will be resumed within twenty-one (21) days, temporary stabilization measures do not have to be initiated on that portion of site. In areas experiencing droughts where the initiation of stabilization measures by the 14<sup>th</sup> day after construction activity has temporarily or permanently ceased is precluded by seasonably arid conditions, stabilization measures must be initiated as soon as practicable.



# Storm Water Pollution Prevention Temporary Water Pollution Abatement Plan



HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

# EXHIBIT 2 Storm Water Pollution Prevention Details Typical Details

#### SCHEMATIC OF TEMPORARY CONSTRUCTION ENTRANCE/EXIT

#### MATERIALS

8-INCHES.

1. THE AGGREGATE SHOULD CONSIST OF 4-INCH TO 8-INCH WASHED STONE OVER A STABLE FOUNDATION AS SPECIFIED IN THE PLAN. 2. THE AGGREGATE SHOULD BE PLACED WITH A MINIMUM THICKNESS OF

3. THE GEOTEXTILE FABRIC SHOULD BE DESIGNED SPECIFICALLY FOR USE AS A SOIL FILTRATION MEDIA WITH AN APPROXIMATE WEIGHT OF 6 OZ/YD2, A MULLEN BURST RATING OF 140 LB/IN2, AND AN EQUIVALENT OPENING SIZE GREATER THAN A NUMBER 50 SIEVE.

4. IF A WASHING FACILITY IS REQUIRED, A LEVEL AREA WITH A MINIMUM OF 4-INCH DIAMETER WASHED STONE OR COMMERCIAL ROCK SHOULD BE INCLUDED IN THE PLANS. DIVERT WASTEWATER TO A SEDIMENT TRAP OF

#### INSTALLATION

1. AVOID CURVES ON PUBLIC ROADS AND STEEP SLOPES. REMOVE VEGETATION AND OTHER OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA. GRADE CROWN FOUNDATION FOR POSITIVE DRAINAGE. 2. THE MINIMUM WIDTH OF THE ENTRANCE/EXIT SHOULD BE 12 FEET OR THE

FULL WIDTH OF EXIT ROADWAY, WHICHEVER IS GREATER 3. THE CONSTRUCTION ENTRANCE SHOULD BE AT LEAST 50 FEET LONG.

4. IF THE SLOPE TOWARD THE ROAD EXCEEDS 2%, CONSTRUCT A RIDGE 6-INCHES TO 8-INCHES HIGH WITH 3:1 (H:V) SIDE SLOPES, ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE ENTRANCE TO DIVERT RUNOFF AWAY FROM THE PUBLIC ROAD.

5. PLACE GEOTEXTILE FABRIC AND GRADE FOUNDATION TO IMPROVE STABILITY, ESPECIALLY WHERE WET CONDITIONS ARE ANTICIPATED.

6. PLACE STONE TO DIMENSIONS AND GRADE SHOWN ON PLANS. LEAVE

SURFACE SMOOTH AND SLOPE FOR DRAINAGE. 7. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE STONE PAD TO A SEDIMENT TRAP OR BASIN.

8. INSTALL PIPE UNDER PAD AS NEEDED TO MAINTAIN PROPER PUBLIC ROAD

## STABILIZE FOUNDATION

#### SECTION "A-A" OF A CONSTRUCTION ENTRANCE/EXIT

#### COMMON TROUBLE POINTS

1. INADEQUATE RUNOFF CONTROL-SEDIMENT WASHES ONTO PUBLIC ROAD. . STONE TOO SMALL OR GEOTEXTILE FABRIC ABSENT, RESULTS IN MUDDY CONDITION AS STONE IS PRESSED INTO SOIL.

5. PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC-EXTEND PAD BEYOND THE MINIMUM 50-FOOT LENGTH AS NECESSARY. 4. PAD NOT FLARED SUFFICIENTLY AT ROAD SURFACE, RESULTS IN MUD BEING

TRACKED ON TO ROAD AND POSSIBLE DAMAGE TO ROAD. 5. UNSTABLE FOUNDATION - USE GEOTEXTILE FABRIC UNDER PAD AND/OR IMPROVE FOUNDATION DRAINAGE.

#### INSPECTION AND MAINTENANCE GUIDELINES THE ENTRANCE SHOULD BE MAINTAINED IN A CONDITION. WHICH WILL

PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

2. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC

RIGHTS-OF-WAY SHOULD BE REMOVED IMMEDIATELY BY CONTRACTOR. 3. WHEN NECESSARY, WHEELS SHOULD BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.

4. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN

INCORRECT

SOD INSTALLATION

USE PEGS OR STAPLES TO FASTEN SOD


FIRMLY - AT THE ENDS OF STRIPS AND

IN THE CENTER, OR EVERY 3-4 FEET IF

MOW. DRIVE PEGS OR STAPLES FLUSH

THE STRIPS ARE LONG. WHEN READY TO

5. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATER COURSE BY USING APPROVED METHODS.



ISOMETRIC PLAN VIEW

#### **ROCK BERMS**

THE PURPOSE OF A ROCK BERM IS TO SERVE AS A CHECK DAM IN AREAS OF CONCENTRATED FLOW, TO INTERCEPT SEDIMENT-LADEN RUNOFF, DETAIN THE SEDIMENT AND RELEASE THE WATER IN SHEET FLOW. THE ROCK BERM SHOULD BE USED WHEN THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 5 ACRES. ROCK BERMS ARE USED IN AREAS WHERE THE VOLUME OF RUNOFF IS TOO GREAT FOR A SILT FENCE TO CONTAIN. THEY ARE LESS EFFECTIVE FOR SEDIMENT REMOVAL THAN SILT FENCES, PARTICULARLY FOR FINE PARTICLES, BUT ARE ABLE TO WITHSTAND HIGHER FLOWS THAN A SILT FENCE. AS SUCH, ROCK BERMS ARE OFTEN USED IN AREAS OF CHANNEL FLOWS (DITCHES, GULLIES, ETC.). ROCK BERMS ARE MOST EFFECTIVE AT REDUCING BED LOAD IN CHANNELS AND SHOULD NOT BE SUBSTITUTED FOR OTHER EROSION AND SEDIMENT CONTROL MEASURES FARTHER UP THE WATERSHED.

#### INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL BY THE RESPONSIBLE PARTY. FOR INSTALLATIONS IN STREAMBEDS, ADDITIONAL DAILY INSPECTIONS SHOULD BE MADE.

REMOVE SEDIMENT AND OTHER DEBRIS WHEN BUILDUP REACHES 6 INCHES AND DISPOSE OF THE ACCUMULATED SILT IN AN APPROVED MANNER THAT WILL NOT CAUSE ANY ADDITIONAL SILTATION.

3. REPAIR ANY LOOSE WIRE SHEATHING.

4. THE BERM SHOULD BE RESHAPED AS NEEDED DURING INSPECTION

5. THE BERM SHOULD BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.

6. THE ROCK BERM SHOULD BE LEFT IN PLACE UNTIL ALL UPSTREAM AREAS ARE STABILIZED AND ACCUMULATED SILT REMOVED.

### WOVEN WIRE SHEATHING SECTION "A-A"

#### THE BERM STRUCTURE SHOULD BE SECURED WITH A WOVEN WIRE

SHEATHING HAVING MAXIMUM OPENING OF 1 INCH AND A MINIMUM WIRE DIAMETER OF 20 GAUGE GALVANIZED AND SHOULD BE SECURED WITH SHOAT 2. CLEAN, OPEN GRADED 3-INCH TO 5-INCH DIAMETER ROCK SHOULD BE

USED, EXCEPT IN AREAS WHERE HIGH VELOCITIES OR LARGE VOLUMES OF FLOW ARE EXPECTED, WHERE 5-INCH TO 8-INCH DIAMETER ROCKS MAY BE

#### INSTALLATION 1. LAY OUT THE WOVEN WIRE SHEATHING PERPENDICULAR TO THE FLOW LINE.

THE SHEATHING SHOULD BE 20 GAUGE WOVEN WIRE MESH WITH 1 INCH 2. BERM SHOULD HAVE A TOP WIDTH OF 2 FEET MINIMUM WITH SIDE SLOPES

BEING 2:1 (H: V) OR FLATTER. 3. PLACE THE ROCK ALONG THE SHEATHING AS SHOWN IN THE DIAGRAM TO A HEIGHT NOT LESS THAN 18".

4. WRAP THE WIRE SHEATHING AROUND THE ROCK AND SECURE WITH TIE WIRE SO THAT THE ENDS OF THE SHEATHING OVERLAP AT LEAST 2 INCHES, AND THE BERM RETAINS ITS SHAPE WHEN WALKED UPON.

OR AS NEAR AS POSSIBLE. 6. THE ENDS OF THE BERM SHOULD BE TIED INTO EXISTING UPSLOPE GRADE AND THE BERM SHOULD BE BURIED IN A TRENCH APPROXIMATELY 3 TO 4

5. BERM SHOULD BE BUILT ALONG THE CONTOUR AT ZERO PERCENT GRADE

#### COMMON TROUBLE POINTS

INCHES DEEP TO PREVENT FAILURE OF THE CONTROL.

1. INSUFFICIENT BERM HEIGHT OR LENGTH (RUNOFF QUICKLY ESCAPES OVER THE TOP OR AROUND THE SIDES OF BERM).

2. BERM NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND ONE SIDE).

#### **ROCK BERM DETAIL**

NOT-TO-SCALE

#### STEEL FENCE POST MAX. 6' SPACING, SILT FENCE $\overline{}$ MIN. EMBEDMENT = 1' (MIN. HEIGHT 24" (SEE INSTALLATION NOTE 1) ABOVE EXISTING GROUND) WIRE MESH BACKING SUPPORT COMPACTED EARTH 4X4~W1.4xW1.4 MIN OR ROCK BACKFILL - ALLOWABLE TYPICAL CHAIN LINK FENCE FABRIC IS ACCEPTABLE TRENCH-

ISOMETRIC PLAN VIEW

ENDS OF FABRIC MEET.

#### STABILIZED CONSTRUCTION ENTRANCE/EXIT DETAIL

SHOOTS OR GRASS BLADES.

GRASS SHOULD BE GREEN AND

-THATCH- GRASS CLIPPINGS AND

ROOT ZONE- SOIL AND ROOTS.

DEAD LEAVES, UP TO 1/2" THICK.

SHOULD BE 1/2"-3/4" THICK, WITH

DENSE ROOT MAT FOR STRENGTH.

HEALTHY: MOWED AT A 2"-3"

1. SOD SHOULD BE MACHINE CUT AT A UNIFORM SOIL THICKNESS OF 3/4" INCH

(± 1/4" INCH) AT THE TIME OF CUTTING. THIS THICKNESS SHOULD EXCLUDE

2. PIECES OF SOD SHOULD BE CUT TO THE SUPPLIER'S STANDARD WIDTH AND

LENGTH. WITH A MAXIMUM ALLOWABLE DEVIATION IN ANY DIMENSION OF 5%.

STANDARD SIZE SECTIONS OF SOD SHOULD BE STRONG ENOUGH TO

SUPPORT THEIR OWN WEIGHT AND RETAIN THEIR SIZE AND SHAPE WHEN

4. SOD SHOULD BE HARVESTED, DELIVERED, AND INSTALLED WITHIN A PERIOD

PRIOR TO SOIL PREPARATION, AREAS TO BE SODDED SHOULD BE BROUGHT

THE SURFACE SHOULD BE CLEARED OF ALL TRASH, DEBRIS AND OF ALL

FERTILIZE ACCORDING TO SOIL TESTS. FERTILIZER NEEDS CAN BE

ROOTS, BRUSH, WIRE, GRADE STAKES AND OTHER OBJECTS THAT WOULD

DETERMINED BY A SOIL TESTING LABORATORY OR REGIONAL RECOMMENDATIONS CAN BE MADE BY COUNTY AGRICULTURAL EXTENSION AGENTS. FERTILIZER

SHOULD BE WORKED INTO THE SOIL TO A DEPTH OF 3 INCHES WITH A DISC

FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE CONTOUR.

SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. ON SLOPING LAND, THE

SOD STRIPS IN WATERWAYS SHOULD BE LAID PERPENDICULAR TO THE

. AFTER ROLLING OR TAMPING, SOD SHOULD BE PEGGED OR STAPLED TO

RESIST WASHOUT DURING THE ESTABLISHMENT PERIOD. MESH OR OTHER

NETTING MAY BE PEGGED OVER THE SOD FOR EXTRA PROTECTION IN CRITICAL

DIRECTION OF FLOW. CARE SHOULD BE TAKEN TO BUTT ENDS OF STRIPS

TORN OR UNEVEN PADS SHOULD NOT BE ACCEPTABLE.

SUSPENDED FROM A FIRM GRASP ON ONE END OF THE SECTION.

TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLAN.

INSTALLATION IN CHANNELS

TIGHTLY (SEE FIGURE ABOVE).

INTERFERE WITH PLANTING, FERTILIZING OR MAINTENANCE OPERATIONS.

LAY SOD IN A STAGGERED PATTERN. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER. DO NOT LEAVE SPACES AND DO NOT OVERLAP. A SHARPENED MASON'S TROWEL IS A HANDY TOOL FOR TUCKING DOWN THE ENDS AND TRIMMING PIECES.

AUTOMATIC SOD CUTTER MUST BE MATCHED

LAY SOD ACROSS THE DIRECTION OF FLOW


**MATERIALS** 

OF 36 HOURS.

SHOOT GROWTH AND THATCH.

SITE PREPARATION

ANGLED ENDS CAUSED BY THE



IN CRITICAL AREAS, SECURE SOD WITH NETTING, USE STAPLES.

NOT-TO-SCALE

APPEARANCE OF GOOD SOD

ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE

#### GENERAL INSTALLATION (VA. DEPT. OF

CONSERVATION, 1992 SOD SHOULD NOT BE CUT OR LAID IN EXCESSIVELY WET OR DRY WEATHER. SOD ALSO SHOULD NOT BE LAID ON SOIL SURFACES THAT ARE FROZEN.

2. DURING PERIODS OF HIGH TEMPERATURE, THE SOIL SHOULD BE LIGHTLY IRRIGATED IMMEDIATELY PRIOR TO LAYING THE SOD, TO COOL THE SOIL AND REDUCE ROOT BURNING AND DIEBACK.

WITH THE GROUND

FIRST ROW OF SOD SHOULD BE LAID IN A STRAIGHT LINE WITH SUBSEQUENT ROWS PLACED PARALLEL TO AND BUTTING TIGHTLY AGAINST EACH OTHER. LATERAL JOINTS SHOULD BE STAGGERED TO PROMOTE MORE UNIFORM GROWTH AND STRENGTH. CARE SHOULD BE EXERCISED TO ENSURE THAT SOD IS NOT STRETCHED OR OVERLAPPED AND THAT ALL JOINTS ARE BUTTED TIGHT IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE ROOTS (SEE FIGURE ABOVE).

4. ON SLOPES 3:1 OR GREATER, OR WHEREVER EROSION MAY BE A PROBLEM SOD SHOULD BE LAID WITH STAGGERED JOINTS AND SECURED BY STAPLING OF OTHER APPROVED METHODS. SOD SHOULD BE INSTALLED WITH THE LENGTH PERPENDICULAR TO THE SLOPE (ON CONTOUR).

5. AS SODDING OF CLEARLY DEFINED AREAS IS COMPLETED, SOD SHOULD BE ROLLED OR TAMPED TO PROVIDE FIRM CONTACT BETWEEN ROOTS AND SOIL.

6. AFTER ROLLING, SOD SHOULD BE IRRIGATED TO A DEPTH SUFFICIENT THAT THE UNDERSIDE OF THE SOD PAD AND THE SOIL 4 INCHES BELOW THE SOD IS UNTIL SUCH TIME A GOOD ROOT SYSTEM BECOMES DEVELOPED, IN THE

ABSENCE OF ADEQUATE RAINFALL, WATERING SHOULD BE PERFORMED AS

OFTEN AS NECESSARY TO MAINTAIN MOIST SOIL TO A DEPTH OF AT LEAST 4 8. THE FIRST MOWING SHOULD NOT BE ATTEMPTED UNTIL THE SOD IS FIRMLY ROOTED, USUALLY 2-3 WEEKS. NOT MORE THAN ONE THIRD OF THE GRASS LEAF SHOULD BE REMOVED AT ANY ONE CUTTING.

INSPECTION AND MAINTENANCE GUIDELINES SHOULD BE INSPECTED WEEKLY AND AFTER EACH RAIN EVENT TO LOCATE AND REPAIR ANY DAMAGE.

2. DAMAGE FROM STORMS OR NORMAL CONSTRUCTION ACTIVITIES SUCH AS TIRE RUTS OR DISTURBANCE OF SWALE STABILIZATION SHOULD BE REPAIRED AS

SOD INSTALLATION DETAIL

NOT-TO-SCALE

#### SOON AS PRACTICAL.

HIS DOCUMENT HAS BEEN PRODUCED FROM MATERIAL THAT WAS STORED AND/OR TRANSMITTED ELECTRONICALLY AND MAY HAVE BEEN INADVERTENTLY ALTERED. RELY ONLY ON FINAL HARDCOPY MATERIALS BEARING THE CONSULTANT'S ORIGINAL SIGNATURE AND SEAL. AERIAL IMAGERY PROVIDED BY GOOGLE® UNLESS OTHERWISE NOTED. Imagery © 2016,CAPCOG,Digital Globe,Texas Orthoimagery Program, USDA Farm Service Agency.

#### SILT FENCE

PEG OR

STAPLI

A SILT FENCE IS A BARRIER CONSISTING OF GEOTEXTILE FABRIC SUPPORTED BY METAL POSTS TO PREVENT SOIL AND SEDIMENT LOSS FROM A SITE. WHEN PROPERLY USED, SILT FENCES CAN BE HIGHLY EFFECTIVE AT CONTROLLING SEDIMENT FROM DISTURBED AREAS. THEY CAUSE RUNOFF TO POND, ALLOWING HEAVIER SOLIDS TO SETTLE OUT. IF NOT PROPERLY INSTALLED, SILT FENCES ARE NOT LIKELY TO BE EFFECTIVE.

THE PURPOSE OF A SILT FENCE IS TO INTERCEPT AND DETAIN WATER-BORN SEDIMENT FROM UNPROTECTED AREAS OF A LIMITED EXTENT. SILT FENCE IS USED DURING THE PERIOD OF CONSTRUCTION NEAR THE PERIMETER OF A DISTURBED AREA TO INTERCEPT SEDIMENT WHILE ALLOWING WATER TO PERCOLATE THROUGH. THIS FENCE SHOULD REMAIN IN PLACE UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED. SILT FENCE SHOULD NOT BE USED WHERE THERE IS A CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY. IF CONCENTRATED FLOW OCCURS AFTER INSTALLATION, CORRECTIVE ACTION MUST BE TAKEN SUCH AS PLACING A ROCK BERM IN THE AREAS OF CONCENTRATED FLOW.

SILT FENCING WITHIN THE SITE MAY BE TEMPORARILY MOVED DURING THE DAY TO ALLOW CONSTRUCTION ACTIVITY PROVIDED IT IS REPLACED AND PROPERLY ANCHORED TO THE GROUND AT THE END OF THE DAY. SILT FENCES ON THE PERIMETER OF THE SITE OR AROUND DRAINAGE WAYS SHOULD NOT BE MOVED AT ANY TIME.

#### SILT FENCE MATERIAL SHOULD BE POLYPROPYLENE, POLYETHYLENE, OR

POLYAMIDE WOVEN OR NONWOVEN FABRIC. THE FABRIC SHOULD BE 36 INCHES, WITH A MINIMUM UNIT WEIGHT OF 4.5 OZ/YD, MULLEN BURST STRENGTH EXCEEDING 190 LB/IN2, ULTRAVIOLET STABILITY EXCEEDING 70%, AND MINIMUM APPARENT OPENING SIZE OF U.S. SIEVE NUMBER 30.

. FENCE POSTS SHOULD BE MADE OF HOT ROLLED STEEL, AT LEAST 4 FEET LONG WITH TEE OR Y-BAR CROSS SECTION, SURFACE PAINTED OR GALVANIZED, MINIMUM WEIGHT 1.25 LB/FT, AND BRINDELL HARDNESS

3. WOVEN WIRE BACKING TO SUPPORT THE FABRIC SHOULD BE GALVANIZED 2" X 4" WELDED WIRE, 12 GAUGE MINIMUM.

1. STEEL POSTS, WHICH SUPPORT THE SILT FENCE, SHOULD BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POSTS MUST BE EMBEDDED A MINIMUM OF 1-FOOT DEEP AND SPACED NOT MORE THAN 8 FEET ON CENTER. WHERE WATER CONCENTRATES, THE MAXIMUM SPACING SHOULD BE 6 FEET.

2. LAY OUT FENCING DOWN-SLOPE OF DISTURBED AREA, FOLLOWING THE CONTOUR AS CLOSELY AS POSSIBLE. THE FENCE SHOULD BE SITED SO THAT THE MAXIMUM DRAINAGE AREA IS 1/4 ACRE/100 FEET OF FENCE.

3. THE TOE OF THE SILT FENCE SHOULD BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWN-SLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW. WHERE FENCE CANNOT BE TRENCHED IN (E.G., PAVEMENT OR ROCK OUTCROP), WEIGHT FABRIC FLAP WITH 3 INCHES OF PEA GRAVEL ON UPHILL SIDE TO PREVENT FLOW FROM SEEPING UNDER FENCE.

4. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH STEEL SUPPORT POST OR TO WOVEN WIRE, WHICH IS IN TURN ATTACHED TO THE STEEL FENCE

POST. THERE SHOULD BE A 3-FOOT OVERLAP, SECURELY FASTENED WHERE

6. SILT FENCE SHOULD BE REMOVED WHEN THE SITE IS COMPLETELY STABILIZED SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

#### COMMON TROUBLE POINTS FENCE NOT INSTALLED ALONG THE CONTOUR CAUSING WATER TO CONCENTRATE AND FLOW OVER THE FENCE.

2. FABRIC NOT SEATED SECURELY TO GROUND (RUNOFF PASSING UNDER FENCE).

3. FENCE NOT INSTALLED PERPENDICULAR TO FLOW LINE (RUNOFF ESCAPING AROUND SIDES) 4. FENCE TREATING TOO LARGE AN AREA, OR EXCESSIVE CHANNEL FLOW


#### (RUNOFF OVERTOPS OR COLLAPSES FENCE).

3. REPLACE TORN FABRIC OR INSTALL A SECOND LINE OF FENCING PARALLEL

TO THE TORN SECTION. 4. REPLACE OR REPAIR SECTIONS CRUSHED OR COLLAPSED IN THE COURSE OF CONSTRUCTION ACTIVITY. IF A SECTION OF FENCE IS OBSTRUCTING VEHICULAR ACCESS, CONSIDER RELOCATING IT TO A SPOT WHERE IT WILL PROVIDE EQUAL PROTECTION, BUT WILL NOT OBSTRUCT VEHICLES. A

#### SILT FENCE DETAIL

NOT-TO-SCALE



#### GENERAL NOTES

CONTRACTOR TO INSTALL 2"x4"-W1.4xW1.4 WIRE MESH SUPPORTING FILTER FABRIC OVER THE INLET OPENING. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR WIRE TIES AT THIS LOCATION, SAND BAGS FILLED WITH WASHED PEA GRAVEL SHOULD BE PLACED ON TOP OF WIRE MESH ON TOP OF THE INLET AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SANDBAGS FILLED WITH WASHED PEA GRAVEL SHOULD ALSO BE PLACED ALONG THE GUTTER AS SHOWN ON THIS DETAIL TO HOLD WIRE MESH IN PLACE. SAND BAGS TO BE STACKED TO FORM A CONTINUOUS BARRIER AROUND INLETS.

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS.

INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL. REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY THE

2. REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.

4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR MISSING.


5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER

3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND

#### **BAGGED GRAVEL CURB INLET** PROTECTION DETAIL


THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

NOT-TO-SCALE



#### NATURAL VEGETATIVE **BUFFER DETAIL**

NOT-TO-SCALE



#### GENERAL NOTES

SIZE DEPENDING ON EXPECTED FREQUENCY OF USE.

WASHOUT PIT SHALL NOT BE LOCATED IN AREAS SUBJECT TO INUNDATION FROM STORM WATER RUNOFF.

TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE CONSTRUCTED WITH SUFFICIENT QUANTITY AND VOLUME TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS.

#### MATERIALS PLASTIC LINING MATERIAL SHOULD BE A MINIMUM OF 10 MIL IN POLYETHYLENE

**MAINTENANCE** WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER

MATERIALS USED TO CONSTRUCT TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE REMOVED FROM THE SITE OF THE WORK AND DISPOSED

CONCRETE TRUCK WASHOUT

**PLAN VIEW** -WASHED PEA GRAVEL FILLER GRATE DRAIN INLET SEE GRAVEL FILTER BAG DETAIL FILTER FABRIC-SECTION "A-A"

#### GENERAL NOTES

THE SANDBAGS SHOULD BE FILLED WITH WASHED PEA GRAVEL AND STACKED TO FORM A CONTINUOUS BARRIER ABOUT 1 FOOT HIGH AROUND

2. THE BAGS SHOULD BE TIGHTLY ABUTTED AGAINST EACH OTHER TO

PREVENT RUNOFF FROM FLOWING BETWEEN THE BAGS. INSPECTION AND MAINTENANCE GUIDELINES . INSPECTION SHOULD BE MADE WEEKLY AND AFTER EACH RAINFALL REPAIR OR REPLACEMENT SHOULD BE MADE PROMPTLY AS NEEDED BY


THE CONTRACTOR. . REMOVE SEDIMENT WHEN BUILDUP REACHES A DEPTH OF 3 INCHES. REMOVED SEDIMENT SHOULD BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MATTER THAT IT WILL NOT ERODE.


3. CHECK PLACEMENT OF DEVICE TO PREVENT GAPS BETWEEN DEVICE AND CURB. 4. INSPECT FILTER FABRIC AND PATCH OR REPLACE IF TORN OR

5. STRUCTURES SHOULD BE REMOVED AND THE AREA STABILIZED ONLY AFTER THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

#### BAGGED GRAVEL GRATE INLET PROTECTION DETAIL

NOT-TO-SCALE





DETAIL ABOVE ILLUSTRATES MINIMUM DIMENSIONS. PIT CAN BE INCREASED IN WASHOUT PIT SHALL BE LOCATED IN AN AREA EASILY ACCESSIBLE TO CONSTRUCTION TRAFFIC.


4. LOCATE WASHOUT AREA AT LEAST 50 FEET FROM SENSITIVE FEATURES, STORM DRAINS, OPEN DITCHES OR WATER BODIES.

#### SHEETING AND SHOULD BE FREE OF HOLES, TEARS, OR OTHER DEFECTS THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL

REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHOULD BE REMOVED AND DISPOSED OF.

3. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCES CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE BACKFILLED AND REPAIRED.


PIT DETAIL



THE FILTER BAG MATERIAL SHALL BE MADE OF POLYPROPYLENE, POLYETHYLENE OR POLYAMIDE WOVEN FABRIC, MIN. UNIT WEIGHT OF 4 OUNCES/SY, HAVE A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND JLTRAVIOLET STABILITY EXCEEDING 70%.

THE FILTER BAG SHALL BE FILLED WITH CLEAN, MEDIUM WASHED PEA GRAVEL TO COARSE GRAVEL (0.31 TO 0.75 INCH DIAMETER). . SAND SHALL <u>NOT</u> BE USED TO FILL THE FILTER BAGS.

#### GRAVEL FILTER BAG DETAIL



#### CONSTRUCTION STAGING AREA NOT-TO-SCALE

IE ENGINEERING SEAL HAS BEEN AFFIXED TO THIS SHEET ONLY FOR THE PURPOSE OF DEMONSTRATING COMPLIANCE WITH THE POLLUTION ABATEMENT SIZING AND TREATMENT REQUIREMENTS OF THE TEXAS COMMISSION ON NVIRONMENTAL QUALITY'S EDWARDS AQUIFER TECHNICAL GUIDANCE MANUA

IIS SHEET HAS BEEN PREPARED FOR PURPOSE OF POLLUTION ABATEMENT ONLY. ALL OTHER CIVIL ENGINEERING RELATED INFORMATION SHOULD BE ACQUIRED FROM THE APPROPRIATE SHEET IN TH CIVIL IMPROVEMENT PLANS.

MARCH 2025 SIGNER . DRAWN . EX-2

7328-21

**PRELIMINARY** 

Z

#### INSPECTION AND MAINTENANCE GUIDELINES 1. INSPECT ALL FENCING WEEKLY, AND AFTER RAINFALL 2. REMOVE SEDIMENT WHEN BUILDUP REACHES 6 INCHES.

TRIANGULAR FILTER DIKE MAY BE PREFERABLE TO A SILT FENCE AT COMMON VEHICLE ACCESS POINTS.

WHEN CONSTRUCTION IS COMPLETE, THE SEDIMENT SHOULD BE DISPOSED OF IN A MANNER THAT WILL NOT CAUSE ADDITIONAL SILTATION AND THE PRIOR LOCATION OF THE SILT FENCE SHOULD BE REVEGETATED. THE FENCE ITSELF SHOULD BE DISPOSED OF IN AN APPROVED LANDFILL.

# AGENT AUTHORIZATION FORM (TCEQ-0599)

#### **Agent Authorization Form**

For Required Signature
Edwards Aquifer Protection Program
Relating to 30 TAC Chapter 213
Effective June 1, 1999

| ľ               | Miguel Serra  |        |  |  |  |  |
|-----------------|---|--------|--|--|--|--|
| *               | Print Name  |        |  |  |  |  |
| 0.000           | Owner   |        |  |  |  |  |
|                 | Title - Owner/President/Other                               |        |  |  |  |  |
| of              | Stone Oak 11 Acres, LLC Corporation/Partnership/Entity Name | * #*** |  |  |  |  |
| have authorized | Pape-Dawson Engineers, Inc. Print Name of Agent/Engineer    |        |  |  |  |  |
| of              | Pape-Dawson Engineers, Inc. Print Name of Firm              |        |  |  |  |  |

to represent and act on the behalf of the above named Corporation, Partnership, or Entity for the purpose of preparing and submitting this plan application to the Texas Commission on Environmental Quality (TCEQ) for the review and approval consideration of regulated activities.

#### I also understand that:

- 1. The applicant is responsible for compliance with 30 Texas Administrative Code Chapter 213 and any condition of the TCEQ's approval letter. The TCEQ is authorized to assess administrative penalties of up to \$10,000 per day per violation.
- 2. For those submitting an application who are not the property owner, but who have the right to control and possess the property, additional authorization is required from the owner.
- Application fees are due and payable at the time the application is submitted. The
  application fee must be sent to the TCEQ cashier or to the appropriate regional office.
  The application will not be considered until the correct fee is received by the
  commission.
- 4. A notarized copy of the Agent Authorization Form must be provided for the person preparing the application, and this form must accompany the completed application.
- 5. No person shall commence any regulated activity on the Edwards Aquifer Recharge Zone, Contributing Zone or Transition Zone until the appropriate application for the activity has been filed with and approved by the Executive Director.

#### SIGNATURE PAGE:

Notary ID 130072954

MY COMMISSION EXPIRES: 8/29/2024

# APPLICATION FEE FORM (TCEQ-0574)

#### **Application Fee Form**

#### **Texas Commission on Environmental Quality** Name of Proposed Regulated Entity: Canyon Golf Retail Regulated Entity Location: NE Corner of Canyon Golf And Stone Oak Parkway Intersection Name of Customer: Stone Oak 11 Acres, LLC Contact Person: Miguel Serra Phone: <u>210-265-1773</u> Customer Reference Number (if issued):CN 606205409 Regulated Entity Reference Number (if issued):RN <u>111851572</u> **Austin Regional Office (3373)** Hays Travis Williamson San Antonio Regional Office (3362) Medina Uvalde Comal Kinney Application fees must be paid by check, certified check, or money order, payable to the Texas Commission on Environmental Quality. Your canceled check will serve as your receipt. This form must be submitted with your fee payment. This payment is being submitted to: San Antonio Regional Office **Austin Regional Office** Mailed to: TCEQ - Cashier Overnight Delivery to: TCEQ - Cashier **Revenues Section** 12100 Park 35 Circle Mail Code 214 Building A, 3rd Floor P.O. Box 13088 Austin, TX 78753 Austin, TX 78711-3088 (512)239-0357 Site Location (Check All That Apply): Recharge Zone Contributing Zone **Transition Zone**

| Type of Plan                                       | Size     | Fee Due   |
|--|----------|-----------|
| Water Pollution Abatement Plan, Contributing Zone  |          |           |
| Plan: One Single Family Residential Dwelling       | Acres    | \$        |
| Water Pollution Abatement Plan, Contributing Zone  |          |           |
| Plan: Multiple Single Family Residential and Parks | Acres    | \$        |
| Water Pollution Abatement Plan, Contributing Zone  |          |           |
| Plan: Non-residential                              | Acres    | \$        |
| Sewage Collection System                           | 524 L.F. | \$ 650.00 |
| Lift Stations without sewer lines                  | Acres    | \$        |
| Underground or Aboveground Storage Tank Facility   | Tanks    | \$        |
| Piping System(s)(only)                             | Each     | \$        |
| Exception  | Each     | \$        |
| Extension of Time                                  | Each     | \$        |

| Date: |  |
|-------|--|
|       |  |

#### **Application Fee Schedule**

**Texas Commission on Environmental Quality** 

Edwards Aquifer Protection Program 30 TAC Chapter 213 (effective 05/01/2008)

#### Water Pollution Abatement Plans and Modifications

**Contributing Zone Plans and Modifications** 

|   | Project Area in |          |
|---|-----------------|----------|
| Project   | Acres           | Fee      |
| One Single Family Residential Dwelling                | < 5             | \$650    |
| Multiple Single Family Residential and Parks          | < 5             | \$1,500  |
|   | 5 < 10          | \$3,000  |
|   | 10 < 40         | \$4,000  |
|   | 40 < 100        | \$6,500  |
|   | 100 < 500       | \$8,000  |
|   | ≥ 500           | \$10,000 |
| Non-residential (Commercial, industrial,              | < 1             | \$3,000  |
| institutional, multi-family residential, schools, and | 1 < 5           | \$4,000  |
| other sites where regulated activities will occur)    | 5 < 10          | \$5,000  |
|   | 10 < 40         | \$6,500  |
|   | 40 < 100        | \$8,000  |
|   | ≥ 100           | \$10,000 |

Organized Sewage Collection Systems and Modifications

| Project                   | Cost per Linear<br>Foot | Minimum Fee-<br>Maximum Fee |  |
|---------------------------|-------------------------|-----------------------------|--|
| Sewage Collection Systems | \$0.50                  | \$650 - \$6,500             |  |

#### Underground and Aboveground Storage Tank System Facility Plans and Modifications

| Project   | Cost per Tank or<br>Piping System | Minimum Fee-<br>Maximum Fee |  |
|---|-----------------------------------|-----------------------------|--|
| Underground and Aboveground Storage Tank Facility | \$650                             | \$650 - \$6,500             |  |

**Exception Requests** 

| Project           | Fee   |
|-------------------|-------|
| Exception Request | \$500 |

**Extension of Time Requests** 

| Project                   | Fee   |
|---------------------------|-------|
| Extension of Time Request | \$150 |

# CORE DATA FORM (TCEQ-10400)



**TCEQ Core Data Form** 

| TCEQ Use Only |  |
|---------------|--|
|               |  |

For detailed instructions regarding completion of this form, please read the Core Data Form Instructions or call 512-239-5175.

#### **SECTION I: General Information**

| 1. Reason for Submission (If other is checked please describe in space provided.)  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
|--|---------------------|--------------------------|------------------------|--------------------------|-----------|----------|----------|------------------------------|----------------------------------|--------------------|--------------------------|
| New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)                                   |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| Renewal (Core Data Form should be submitted with the renewal form)   |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| 2. Customer  | Referenc            | e Number <i>(if i</i> ss | ued) Fo                | ollow this lin           | ık to sea | arch     | 3. Re    | egulated                     | <b>Entity Reference</b>          | e Number <i>(i</i> | if issued)               |
| CN 6062  | 05409               |                          | fo                     | r CN or RN<br>Central Re |           |          | RN       | N 1118                       | 51572                            |                    |                          |
| <b>SECTION</b>   | II: Cu              | stomer Info              | <u>ormation</u>        |                          |           |          |          |                              |                                  |                    |                          |
| 4. General C   | ustomer I           | nformation               | 5. Effective Da        | ite for Cus              | stomer    | r Inform | atio     | n Updat                      | es (mm/dd/yyyy)                  |                    |                          |
| ☐ New Cust☐ Change in  |                     | ne (Verifiable wit       |                        | date to Cus              |           |          |          | otroller of                  | Change in Public Accounts)       | Regulated E        | Entity Ownership         |
|  |                     |                          |                        | <u>·</u>                 |           |          |          |                              |                                  | rrent and          | active with the          |
|  |                     |                          | or Texas Con           | •                        |           |          | •        |                              |                                  |                    |                          |
| 6. Customer  | Legal Nai           | me (If an individua      | l, print last name fir | st: eg: Doe,             | John)     |          | <u> </u> | f new Cu                     | stomer, enter previ              | ous Custome        | er below:                |
| Stone Oak  | 11 Acr              | es, LLC                  |                        |                          |           |          |          |                              |                                  |                    |                          |
| 7. TX SOS/CI   | PA Filing           | Number                   | 8. TX State Tax        | x ID (11 digit           | ts)       |          | Ş        | ). Federa                    | al Tax ID (9 digits)             | 10. DUN            | S Number (if applicable) |
| 08045389   | 60                  | _                        | 320842844              | 99                       |           |          | 9        | 920288                       | 3436                             |                    |                          |
| 11. Type of C  | Customer:           |                          | on                     |                          | Individ   | ual      |          | Pai                          | Partnership: ☐ General ☒ Limited |                    |                          |
| Government:  | ☐ City ☐            | County 🔲 Federal 🗆       | ☐ State ☐ Other        |                          | Sole P    | roprieto | rship    |                              | Other:                           |                    |                          |
| <b>12. Number  ⊙</b> 0-20  | of Employ<br>21-100 | ees 101-250              | 251-500                | 501 ar                   | nd high   | er       | (        | 13. Indep                    | endently Owned                   | and Opera          | ted?                     |
| 14. Custome  | <b>r Role</b> (Pr   | oposed or Actual) -      | - as it relates to the |                          |           |          | this fo  | orm. Pleas                   | se check one of the              | following          |                          |
| Owner  |                     | Operat                   | tor                    | ⊠ O                      | wner &    | Opera    | tor      |                              |                                  |                    |                          |
| Occupatio  | nal Licens          | ee Respo                 | nsible Party           | ☐ Vo                     | oluntar   | y Clean  | up A     | pplicant                     | Other:                           |                    |                          |
|  | 15555               | Tradesman I              | Or, Ste 400            |                          |           |          |          |                              |                                  |                    |                          |
| 15. Mailing<br>Address:  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| Address.   | City                | San Antoni               | 0                      | State                    | TX        |          | ZIP      | 7824                         | 49                               | ZIP + 4            |                          |
| 16. Country  | Mailing In          | formation (if outsi      | de USA)                | 17. E-M                  |           |          | Mail     | Mail Address (if applicable) |                                  |                    |                          |
|  | crosstimber@me.com  |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| 18. Telephon   | e Numbe             | •                        | 19                     | 9. Extensi               | on or (   | Code     |          |                              | 20. Fax Numbe                    | r (if applical     | ble)                     |
| ( 210 ) 265-1773   |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| SECTION III: Regulated Entity Information  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| 21. General Regulated Entity Information (If 'New Regulated Entity" is selected below this form should be accompanied by a permit application) |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| New Regulated Entity ☐ Update to Regulated Entity Name ☐ Update to Regulated Entity Information  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| The Regulated Entity Name submitted may be updated in order to meet TCEQ Agency Data Standards (removal  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| of organizational endings such as Inc, LP, or LLC).  |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| 22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)   |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |
| Canyon Golf Retail   |                     |                          |                        |                          |           |          |          |                              |                                  |                    |                          |

TCEQ-10400 (02/21) Page 1 of 2

| 22 Stre  | 23. Street Address of  |  |  |  |   |                    |                                      |   |                                      |                            |                                    |   |
|--|--|--|--|--|---|--------------------|--------------------------------------|---|--------------------------------------|----------------------------|------------------------------------|---|
|  | gulated Entity:  |  |  |  |   |                    |                                      |   |                                      |                            |                                    |   |
| (No PO   | Boxes)   | City   |  |  | State   |                    |                                      | ZIP   |                                      |                            | ZIP + 4                            |   |
| 24. Cou  | ınty   |  |  |  | l   | <u> </u>           |                                      |   |                                      |                            |                                    |   |
|  | -  | <u> </u>   | En   | ter Physical   | Location Desc   | ription            | if no stre                           | et address                                    | is provid                            | led.                       |                                    |   |
|  | scription to<br>al Location:   | Nort   |  |  | Canyon Go   |                    |                                      |   |                                      |                            | etion                              |   |
| 26. Nea  | rest City  |  |  |  |   |                    |                                      |   | State                                |                            | Ne                                 | arest ZIP Code                            |
| San A  | Intonio  |  |  |  |   |                    |                                      |   | TX                                   |                            | 78                                 | 258                                       |
| 27. Lati   | itude (N) In Decir   | nal:   |  | 29.645919  | N   |                    | 28. Lo                               | ngitude (V                                    | V) In Deci                           | mal:                       | -98.4797                           | '16 W                                     |
| Degrees  |  | Minutes  |  |  | Seconds   |                    | Degrees                              | 3   | Mir                                  | nutes                      |                                    | Seconds                                   |
|  | 29   |  | 3  | 8  | 45.3  |                    |                                      | -98   |                                      | 2                          | 28                                 | 47.0                                      |
| 29. Prir   | mary SIC Code (4   | digits)  | 30. S  | Secondary SI   | C Code (4 digits)   |                    | 1. Primary 5 or 6 digits)            | / NAICS C                                     | ode                                  | <b>32. S</b> 6 (5 or 6     | econdary NA                        | AICS Code                                 |
| 1542   |  |  | 162  | 3  |   | 2                  | 236220                               |   |                                      | 2371                       | 110                                |   |
| 33. Wh   | at is the Primary  | Busines  | ss of  | this entity?   | (Do not repeat the  | SIC or             | NAICS descr                          | iption.)                                      |                                      |                            |                                    |   |
| Comr   | nercial Retail   |  |  | •  |   |                    |                                      |   |                                      |                            |                                    |   |
|  |  |  |  |  |   | 155                | 555 Trades                           | sman Dr, S                                    | ite 400                              |                            |                                    |   |
| 3  | 34. Mailing  |  |  |  |   |                    |                                      | <u> </u>                                      |                                      |                            |                                    |   |
|  | Address:   | Cit  | w  | San Anton  | io State  |                    | ТХ                                   | ZIP   | ZIP 78249                            |                            | ZIP + 4                            |   |
| 35   | . E-Mail Address   | 1  | .y   | Our Anton  | otate   |                    |                                      |   |                                      | L-1-J                      | ZII · Ŧ                            |   |
|  |  |  |  |  |   |                    | crosst                               | imher <i>(a</i> )me                           | COM                                  |                            |                                    |   |
| 33   |  | -  | nber   |  | 37. Exte  | nsion              |                                      | imber@me                                      |                                      | Fax Nui                    | mber <i>(if app</i>                | licable)                                  |
| 33   | 36. Teleph   | one Nur  |  |  | 37. Exte  | nsion              |                                      | imber@me                                      |                                      | Fax Nui                    | mber <i>(if app</i>                | licable)                                  |
| 9. TCEQ  | 36. Telepho<br>( 210 ) 2<br>Programs and II  | one Nur<br>265-1773<br>) Numbe   | 3<br>ers Ch  |  | ns and write in th  |                    | or Code                              |   | 38.                                  | (                          | ) -                                | •   |
| 9. TCEQ  | 36. Telepho<br>( 210 ) 2<br>Programs and II<br>he Core Data Form   | 265-1773<br>Number<br>Instruction  | 3<br>ers Ch  | additional guida   | ns and write in th  | e permi            | or Code                              | on numbers                                    | 38. that will be                     | (<br>affected              | ) -<br>by the update               | •   |
| 9. TCEQ  | 36. Telepho<br>( 210 ) 2<br>Programs and II  | 265-1773<br>Number<br>Instruction  | 3<br>ers Ch  | additional guida   | ns and write in th  | e permi            | or Code                              | on numbers                                    | 38.                                  | (<br>affected              | ) -<br>by the update               | s submitted on this                       |
| 9. TCEQ orm. See tl  | 36. Telepho<br>( 210 ) 2<br>Programs and II<br>he Core Data Form   | 265-1773  Number instructio  | ers Chans for istricts   | additional guida   | ns and write in thance.                                       | e permi            | or Code                              | on numbers                                    | 38. that will be                     | (<br>affected              | ) -<br>by the update               | s submitted on this                       |
| 9. TCEQ orm. See tl  | 36. Telepho<br>( 210 ) 2<br>Programs and II<br>the Core Data Form<br>Safety  | 265-1773  Number instructio  | ers Chans for istricts   | additional guida   | ns and write in thance.                                       | e permi            | or Code                              | on numbers                                    | that will be                         | (<br>affected              | by the update                      | s submitted on this                       |
| 9. TCEQ orm. See tl  | 36. Telepho<br>( 210 ) 2<br>Programs and IE<br>he Core Data Form<br>Safety   | 265-1773  Number Diagram Diagr | ers Chans for istricts   | additional guida   | ns and write in thance.                                       | e permi<br>Aquifer | or Code                              | on numbers                                    | that will be                         | (<br>affected              | by the update                      | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See the Dam see   | 36. Telepho<br>( 210 ) 2<br>Programs and IE<br>he Core Data Form<br>Safety   | 265-1773  Number Diagram Diagr | ers Chans for districts  | additional guida   | ms and write in the ance.  Edwards  OSSF                      | e permi<br>Aquifer | or Code                              | on numbers  Emissio                           | that will be                         | (<br>affected              | by the update                      | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See tl Dam  | 36. Telepho<br>( 210 ) 2<br>Programs and IE<br>he Core Data Form<br>Safety   | Dine Number  | ers Chans for districts  | additional guida<br>urce Review Air<br>/ater               | ms and write in the ance.  Edwards  OSSF                      | e permi<br>Aquifer | or Code                              | on numbers  Emissio                           | that will be ons Inventor            | (<br>affected              | by the update                      | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See tl Dam  | 36. Telepho<br>( 210 ) 2<br>Programs and II<br>he Core Data Form<br>Safety<br>cipal Solid Waste  | Dine Number  | ers Chans for istricts ew Soutorm W  | additional guida<br>urce Review Air<br>/ater               | ms and write in the ance.    Edwards   OSSF   Title V Ai      | e permi<br>Aquifer | or Code                              | on numbers  Emission  Petrole  Tires          | that will be ons Inventor            | (<br>affected              | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See tl Dam  | 36. Telepho<br>( 210 ) 2<br>Programs and II<br>he Core Data Form<br>Safety<br>cipal Solid Waste  | Done Number Diagram    | ers Chans for istricts ew Soutorm Waste W  | additional guida urce Review Air /ater                     | ms and write in the ance.  Edwards  OSSF  Title V Ai          | e permi<br>Aquifer | or Code                              | on numbers  Emission  Petrole  Tires          | that will be ons Inventor            | (<br>affected              | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See tl Dam  | 36. Telepho (210) 2 Programs and II he Core Data Form Safety  sipal Solid Waste  | Di Di Di St  | ers Chans for istricts ew Soutorm Waste W  | additional guida urce Review Air /ater                     | ms and write in the ance.  Edwards  OSSF  Title V Ai          | e permi<br>Aquifer | or Code                              | on numbers  Emission  Petrole  Tires  Water F | that will be ons Inventor            | affected<br>ry Air<br>Tank | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See tl Dam: Sludg Volun SECTI 40. Name:   | 36. Telepho (210) 2 Programs and III he Core Data Form Safety Cipal Solid Waste  The Core Data Form Safety  Cipal Solid Waste  The Core Data Form Safety | Diagram National Nati | ers Chans for istricts ew Soutorm Waste Wa | additional guida urce Review Air /ater Vater               | ms and write in the ance.  Edwards  OSSF  Title V Ai          | e permi<br>Aquifer | its/registration                     | on numbers  Emission  Petrole  Tires  Water F | that will be ons Inventor um Storage | affected<br>ry Air<br>Tank | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See th Dam s  Sludg Volun  SECTI 40. Name:  | 36. Telepho (210) 2 Programs and II he Core Data Form Safety  cipal Solid Waste  tele tary Cleanup  ION IV: Pre  | Diagram National Nati | ers Chans for istricts ew Soutorm Waste Wa | additional guida  urce Review Air  /ater  Vater  formation | ms and write in the ance.    Edwards     OSSF     Title V Ai  | e permi<br>Aquifer | its/registration iculture 41. Title: | on numbers  Emission  Petrole  Tires  Water F | that will be ons Inventor um Storage | affected ry Air Tank ager  | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |
| 9. TCEQ orm. See the Dam see t | 36. Telepho (210) 2 Programs and II he Core Data Form Safety  sipal Solid Waste  e tary Cleanup  ION IV: Pre Joshua Ficar phone Number                   | Done Number Diagram New Parcel W   | ers Chans for istricts ew Southern Waste W | additional guida  urce Review Air  /ater  Vater  6 44. Fa  | ms and write in the ance.  Edwards  OSSF  Title V Ai  Wastewa | e permi<br>Aquifer | its/registration iculture 41. Title: | on numbers  Emission  Petrole  Tires  Water F | that will be ons Inventor um Storage | affected ry Air Tank ager  | by the update Industria PWS Used O | s submitted on this<br>al Hazardous Waste |

| Company:         | Pape-Dawson Engineers | Job Title: | Vice Pres | sident |                          |
|------------------|-----------------------|------------|-----------|--------|--------------------------|
| Name (In Print): | David Martinez, P.E.  |            |           | Phone: | ( 210 ) 375- <b>9000</b> |
| Signature:       | David E. Martin       |            |           | Date:  | 08/12/25                 |

TCEQ-10400 (02/21) Page 2 of 2

# FINAL PLAN AND PROFILE SHEETS

# SANITARY SEWER EXTENSION CANYON GOLF/STONE OAK PKWY - RETAIL SEWAGE COLLECTION SYSTEM

# SAN ANTONIO, TEXAS CIVIL CONSTRUCTION PLANS

SAWS JOB NO. 25-1531



LOCATION MAP

NOT-TO-SCALE

PREPARED FOR:

BALEARIA, LLC 15555 TRADESMAN DR., SUITE 400 SAN ANTONIO, TEXAS 78249

**APRIL 2025** 





| Sheet Description                    | Sheet No. |
|--------------------------------------|-----------|
| COVER SHEET                          | C5.00     |
| GENERAL CONSTRUCTION NOTES           | C5.05     |
| OVERALL SANITARY SEWER PLAN-LINE A   | C5.10     |
| SANITARY SEWER PLAN & PROFILE-LINE A | C5.11     |
| SANITARY SEWER DISTRIBUTION DETAILS  | C5.15     |

#### SEWERSHED: SALADO CREEK

| DEVELOPER'S NAME: BALEARIA, LLC   |
|---|
| ADDRESS: 15555 TRADESMAN DR., SUITE 400                                       |
| CITY: SAN ANTONIO STATE: TEXAS ZIP: 78249                                     |
| PHONE# FAX#   |
| SAWS BLOCK MAP# 164-658 TOTAL EDU'S 150 TOTAL ACREAGE 11.12                   |
| TOTAL LINEAR FOOTAGE OF PIPE: $8" \sim 537 \text{ LF}$ PLAT NO. $25-11800090$ |
| NUMBER OF LOTS <u>5</u> SAWS JOB NO. <u>25-1531</u>                           |



LEGAL DESCRIPTION: LOT 7 - 11, BLOCK 3, N.C.B 19218 CANYON GOLF RETAIL (11.12 ACRES) PLAT NO. 25-11800090 ADDRESS: 21902 CANYON GOLF ROAD SAN ANTONIO, TX 78258

<sub>неет</sub> <u>С5.00</u>

#### TCEQ - ORGANIZED SEWAGE COLLECTION SYSTEM GENERAL CONSTRUCTION NOTES

THIS ORGANIZED SEWAGE COLLECTION SYSTEM (SCS) MUST BE CONSTRUCTED IN ACCORDANCE WITH 30 TEXAS ADMINISTRATIVE CODE (TAC) §213.5(C), THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY'S (TCEQ) EDWARDS AQUIFER RULES AND ANY LOCAL GOVERNMENT STANDARD SPECIFICATIONS.

- ALL CONTRACTORS CONDUCTING REGULATED ACTIVITIES ASSOCIATED WITH THIS PROPOSED REGULATED PROJECT MUST BE PROVIDED WITH COPIES OF THE SCS PLAN AND THE TCEQ LETTER INDICATING THE SPECIFIC CONDITIONS OF ITS APPROVAL. DURING THE COURSE OF THESE REGULATED ACTIVITIES. THE CONTRACTORS MUST BE REQUIRED TO KEEP ON-SITE COPIES OF THE PLAN AND THE APPROVAL LETTER.
- A WRITTEN NOTICE OF CONSTRUCTION MUST BE SUBMITTED TO THE PRESIDING TCEQ REGIONAL OFFICE AT LEAST 48 HOURS PRIOR TO THE START OF ANY REGULATED ACTIVITIES THIS NOTICE MUST INCLUDE: THE NAME OF THE APPROVED PROJECT:
- THE ACTIVITY START DATE; AND THE CONTACT INFORMATION OF THE PRIME CONTRACTOR.
- ANY MODIFICATION TO THE ACTIVITIES DESCRIBED IN THE REFERENCED SCS APPLICATION FOLLOWING THE DATE OF APPROVAL MAY REQUIRE THE SUBMITTAL OF AN SCS APPLICATION TO MODIFY THIS APPROVAL, INCLUDING THE PAYMENT OF APPROPRIATE FEES AND ALL INFORMATION NECESSARY FOR ITS REVIEW AND
- PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ALL TEMPORARY EROSION AND SEDIMENTATION (E&S) CONTROL MEASURES MUST BE PROPERLY INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. THESE CONTROLS MUST REMAIN IN PLACE UNTIL THE DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.
- IF ANY SENSITIVE FEATURES ARE DISCOVERED DURING THE WASTEWATER LINE TRENCHING ACTIVITIES, ALL REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MUST BE SUSPENDED IMMEDIATELY. THE APPLICANT MUST IMMEDIATELY NOTIFY THE APPROPRIATE REGIONAL OFFICE OF THE TCEQ OF THE FEATURE DISCOVERED. A GEOLOGIST'S ASSESSMENT OF THE LOCATION AND EXTENT OF THE FEATURE DISCOVERED MUST BE REPORTED TO THAT REGIONAL OFFICE IN WRITING AND THE APPLICANT MUST SUBMIT A PLAN FOR ENSURING THE STRUCTURAL INTEGRITY OF THE SEWER LINE OR FOR MODIFYING THE PROPOSED COLLECTION SYSTEM ALIGNMENT AROUND THE FEATURE. THE REGULATED ACTIVITIES NEAR THE SENSITIVE FEATURE MAY NOT PROCEED UNTIL THE EXECUTIVE DIRECTOR HAS REVIEWED AND APPROVED THE METHODS PROPOSED TO PROTECT THE SENSITIVE FEATURE AND THE EDWARDS AQUIFER FROM ANY POTENTIALLY ADVERSE IMPACTS TO WATER QUALITY WHILE MAINTAINING THE STRUCTURAL INTEGRITY OF THE LINE.
- SEWER LINES LOCATED WITHIN OR CROSSING THE 5-YEAR FLOODPLAIN OF A DRAINAGE WAY WILL BE PROTECTED FROM INJUNDATION AND STREAM VELOCITIES WHICH COULD CAUSE EROSION AND SCOURING OF BACKFILL. THE TRENCH MUST BE CAPPED WITH CONCRETE TO PREVENT SCOURING OF BACKFILL, OR THE SEWER LINES MUST BE ENCASED IN CONCRETE. ALL CONCRETE SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES.
- BLASTING PROCEDURES FOR PROTECTION OF EXISTING SEWER LINES AND OTHER UTILITIES WILL BE IN ACCORDANCE WITH THE NATIONAL FIRE PROTECTION ASSOCIATION CRITERIA. SAND IS NOT ALLOWED AS BEDDING OR BACKFILL IN TRENCHES THAT HAVE BEEN BLASTED. IF ANY EXISTING SEWER LINES ARE DAMAGED, THE LINES MUST BE REPAIRED AND RETESTED.
- ALL MANHOLES CONSTRUCTED OR REHABILITATED ON THIS PROJECT MUST HAVE WATERTIGHT SIZE ON SIZE RESILIENT CONNECTORS ALLOWING FOR DIFFERENTIAL SETTLEMENT. IF MANHOLES ARE CONSTRUCTED WITHIN THE 100-YEAR FLOODPLAIN, THE COVER MUST HAVE A GASKET AND BE BOLTED TO THE RING. WHERE GASKETED MANHOLE COVERS ARE REQUIRED FOR MORE THAN THREE MANHOLES IN SEQUENCE OR FOR MORE THAN 1500 FEET, ALTERNATE MEANS OF VENTING WILL BE PROVIDED. BRICKS ARE NOT AN ACCEPTABLE CONSTRUCTION MATERIAL FOR ANY PORTION OF THE MANHOLE.

THE DIAMETER OF THE MANHOLES MUST BE A MINIMUM OF FOUR FEET AND THE MANHOLE FOR ENTRY MUST HAVE A MINIMUM CLEAR OPENING DIAMETER OF 30 INCHES. THESE DIMENSIONS AND OTHER DETAILS SHOWING COMPLIANCE WITH THE COMMISSION'S RULES CONCERNING MANHOLES AND SEWER LINE/MANHOLE INVERTS DESCRIBED IN 30 TAC §217.55 ARE INCLUDED ON PLAN SHEET C4.05.

IT IS SUGGESTED THAT ENTRANCE INTO MANHOLES IN EXCESS OF FOUR FEET DEEP BE ACCOMPLISHED BY MEANS OF A PORTABLE LADDER. THE INCLUSION OF STEPS IN A MANHOLE IS PROHIBITED.

- . WHERE WATER LINES AND NEW SEWER LINE ARE INSTALLED WITH A SEPARATION DISTANCE CLOSER THAN NINE FEET (I.E., WATER LINES CROSSING WASTEWATER LINES, WATER LINES PARALLELING WASTEWATER LINES, OR WATER LINES NEXT TO THE INSTALLATION MUST MEET THE REQUIREMENTS OF 30 TAIL \$217.53(D) (PIPE DESIGN) AND 30 TAC \$290.44(E) (WATER DISTRIBUTION).
- WHERE SEWERS LINES DEVIATE FROM STRAIGHT ALIGNMENT AND UNIFORM GRADE ALL CURVATURE OF SEWER PIPE MUST BE ACHIEVED BY THE FOLLOWING PROCEDURE WHICH IS RECOMMENDED BY THE PIPE MANUFACTURER: \_\_\_\_\_N/A\_\_

IF PIPE FLEXURE IS PROPOSED, THE FOLLOWING METHOD OF PREVENTING DEFLECTION OF THE JOINT MUST BE USED: N/A

SPECIFIC CARE MUST BE TAKEN TO ENSURE THAT THE JOINT IS PLACED IN THE CENTER OF THE TRENCH AND PROPERLY BEDDED IN ACCORDANCE WITH 30 TAC

. NEW SEWAGE COLLECTION SYSTEM LINES MUST BE CONSTRUCTED WITH STUB OUTS FOR THE CONNECTION OF ANTICIPATED EXTENSIONS. THE LOCATION OF SUCH STUB OUTS MUST BE MARKED ON THE GROUND SUCH THAT THEIR LOCATION CAN BE EASILY DETERMINED AT THE TIME OF CONNECTION OF THE EXTENSIONS. SUCH STUB OUTS MUST BE MANUFACTURED WYES OR TEES THAT ARE COMPATIBLE IN SIZE AND MATERIAL WITH BOTH THE SEWER LINE AND THE EXTENSION. AT THE TIME OF ORIGINAL CONSTRUCTION, NEW STUB-OUTS MUST BE CONSTRUCTED SUFFICIENTLY TO EXTEND BEYOND THE END OF THE STREET PAVEMENT. ALL STUR-OUTS MUST BE SEALED WITH A MANUFACTURED CAP TO PREVENT LEAKAGE EXTENSIONS THAT WERE NOT ANTICIPATED AT THE TIME OF ORIGINAL CONSTRUCTION OR THAT ARE TO BE CONNECTED TO AN EXISTING SEWER LINE NOT FURNISHED WITH STUB OUTS MUST BE CONNECTED USING A MANUFACTURED SADDLE AND IN ACCORDANCE WITH ACCEPTED PLUMBING TECHNIQUES.

IF NO STUB-OUT IS PRESENT AN ALTERNATE METHOD OF JOINING LATERALS IS SHOWN IN THE DETAIL ON SHEET C3.04. (FOR POTENTIAL FUTURE LATERALS).

THE PRIVATE SERVICE LATERAL STUB-OUTS MUST BE INSTALLED AS SHOWN ON THE PLAN AND PROFILE SHEETS ON PLAN SHEET C4.01 TO C4.04 AND MARKED AFTER BACKFILLING AS SHOWN IN THE DETAIL ON PLAN SHEET <u>C3.03</u>

- TRENCHING, BEDDING AND BACKFILL MUST CONFORM WITH 30 TAC \$217.54. THE BEDDING AND BACKFILL FOR FLEXIBLE PIPE MUST COMPLY WITH THE STANDARDS OF ASTM D-2321. CLASSES IA, IB, II OR III. RIGID PIPE BEDDING MUST COMPLY WITH THE REQUIREMENTS OF ASTM C 12 (ANSI A 106.2) CLASSES A, B OR C.
- 4. SEWER LINES MUST BE TESTED FROM MANHOLE TO MANHOLE. WHEN A NEW SEWER LINE IS CONNECTED TO AN EXISTING STUB OR CLEAN-OUT. IT MUST BE TESTED FROM EXISTING MANHOLE TO NEW MANHOLE. IF A STUB OR CLEAN-OUT IS USED AT THE END OF THE PROPOSED SEWER LINE, NO PRIVATE SERVICE ATTACHMENTS MAY BE CONNECTED BETWEEN THE LAST MANHOLE AND THE CLEANOUT UNLESS IT CAN BE CERTIFIED AS CONFORMING WITH THE PROVISIONS OF 30 TAC
- . ALL SEWER LINES MUST BE TESTED IN ACCORDANCE WITH 30 TAC \$217.57. THE ENGINEER MUST RETAIN COPIES OF ALL TEST RESULTS WHICH MUST BE MADE AVAILABLE TO THE EXECUTIVE DIRECTOR UPON REQUEST. THE ENGINEER MUST CERTIFY IN WRITING THAT ALL WASTEWATER LINES HAVE PASSED ALL REQUIRED. TESTING TO THE APPROPRIATE REGIONAL OFFICE WITHIN 30 DAYS OF TEST COMPLETION AND PRIOR TO USE OF THE NEW COLLECTION SYSTEM. TESTING
- ) FOR A COLLECTION SYSTEM PIPE THAT WILL TRANSPORT WASTEWATER BY GRAVITY FLOW. THE DESIGN MUST SPECIFY AN INFILTRATION AND EXFILTRATION TEST OR A LOW-PRESSURE AIR TEST. A TEST MUST CONFORM TO THE FOLLOWING REQUIREMENTS: ) LOW PRESSURE AIR TEST.
- (A) A LOW PRESSURE AIR TEST MUST FOLLOW THE PROCEDURES DESCRIBED IN AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) C-828, ASTM C-924, OR ASTM F-1417 OR OTHER PROCEDURE APPROVED BY THE EXECUTIVE DIRECTOR, EXCEPT AS TO TESTING TIMES AS REQUIRED IN TABLE C.3 INSUBPARAGRAPH (C) OF THIS PARAGRAPH OR EQUATION C.3 IN SUBPARAGRAPH (B)(II) OF THIS
- B) FOR SECTIONS OF COLLECTION SYSTEM PIPE LESS THAN 36 INCH AVERAGE INSIDE DIAMETER, THE FOLLOWING PROCEDURE MUST APPLY, UNLESS A PIPE IS TO BE TESTED AS REQUIRED BY PARAGRAPH (2) OF THIS SUBSECTION ) A PIPE MUST BE PRESSURIZED TO 3.5 POUNDS PER SQUARE INCH (PSI) GREATER

THAN THE PRESSURE EXERTED BY GROUNDWATER ABOVE THE PIPE. ONCE THE PRESSURE IS STABILIZED, THE MINIMUM TIME ALLOWABLE FOR THE PRESSURE TO DROP FROM 3.5 PSI GAUGE TO 2.5 PSI GAUGE IS COMPUTED FROM THE FOLLOWING EQUATION:

EQUATION C.3

WHERE: T = (0.085 \* D \* K)/Q

T = TIME FOR PRESSURE TO DROP 1.0 POUND PER SQUARE INCH GAUGE IN SECONDS  $K = 0.000419 \times D \times L$ , BUT NOT LESS THAN 1.0 D = AVERAGE INSIDE PIPE DIAMETER IN INCHES

L = LENGTH OF LINE OF SAME SIZE BEING TESTED, IN FEET Q = RATE OF LOSS, 0.0015 CUBIC FEET PER MINUTE PER SQUARE FOOT INTERNAL SURFACE ) SINCE A K VALUE OF LESS THAN 1.0 MAY NOT BE USED. THE MINIMUM TESTING

TIME FOR EACH PIPE DIAMETER IS SHOWN IN THE FOLLOWING TABLE C.3:

| PIPE DIAMETER<br>(INCHES) | MIN. TIME<br>(SECONDS) | LENGTH FOR MIN.<br>(FEET) | TIME, LONGER LENGTH (SECONDS) |
|---------------------------|------------------------|---------------------------|-------------------------------|
| 6                         | 340                    | 398                       | 0.855(L)                      |
| 8                         | 454                    | 298                       | 1.520(L)                      |
| 10                        | 567                    | 239                       | 2.374(L)                      |
| 12                        | 680                    | 199                       | 3.419(L)                      |
| 15                        | 850                    | 159                       | 5.342(L)                      |
| 18                        | 1020                   | 133                       | 7.693(L)                      |
| 21                        | 1190                   | 114                       | 10.471(L)                     |
| 24                        | 1360                   | 100                       | 13.676(L)                     |
| 27                        | 1530                   | 88                        | 17.309(L)                     |
| 30                        | 1700                   | 80                        | 21.369(L)                     |
| 33                        | 1870                   | 72                        | 25.856(L)                     |

- D) AN OWNER MAY STOP A TEST IF NO PRESSURE LOSS HAS OCCURRED DURING THE FIRST 25% OF THE CALCULATED TESTING TIME. () IF ANY PRESSURE LOSS OR LEAKAGE HAS OCCURRED DURING THE FIRST 25% OF A TESTING PERIOD, THEN THE TEST MUST CONTINUE FOR THE ENTIRE TEST
- DURATION AS OUTLINED ABOVE OR UNTIL FAILURE. ) WASTEWATER COLLECTION SYSTEM PIPES WITH A 27 INCH OR LARGER AVERAGE INSIDE DIAMETER MAY BE AIR TESTED AT EACH JOINT INSTEAD OF FOLLOWING THE PROCEDURE OUTLINED IN THIS SECTION.

NOT EXCEED 50 GALLONS PER INCH OF DIAMETER PER MILE OF PIPE PER 24

- 3) A TESTING PROCEDURE FOR PIPE WITH AN INSIDE DIAMETER GREATER THAN 33 INCHES MUST BE APPROVED BY THE EXECUTIVE DIRECTOR. ) INFILTRATION / FXFILTRATION TEST ) THE TOTAL EXFILTRATION. AS DETERMINED BY A HYDROSTATIC HEAD TEST, MUST
- HOURS AT A MINIMUM TEST HEAD OF 2.0 FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE. B) AN OWNER SHALL USE AN INFILTRATION TEST IN LIEU OF AN EXFILTRATION TEST WHEN PIPES ARE INSTALLED BELOW THE GROUNDWATER LEVEL. THE TOTAL EXFILTRATION. AS DETERMINED BY A HYDROSTATIC HEAD TEST. MUST
- NOT EXCEED 50 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT A MINIMUM TEST HEAD OF TWO FEET ABOVE THE CROWN OF A PIPE AT AN UPSTREAM MANHOLE, OR AT LEAST TWO FEET ABOVE EXISTING GROUNDWATER LEVEL. WHICHEVER IS GREATER.
- ) FOR CONSTRUCTION WITHIN A 25-YEAR FLOOD PLAIN, THE INFILTRATION OR EXFILTRATION MUST NOT EXCEED 10 GALLONS PER INCH DIAMETER PER MILE OF PIPE PER 24 HOURS AT THE SAME MINIMUM TEST HEAD AS IN SUBPARAGRAPH (C) OF THIS PARAGRAPH
- E) IF THE QUANTITY OF INFILTRATION OR EXFILTRATION EXCEEDS THE MAXIMUM QUANTITY SPECIFIED, AN OWNER SHALL UNDERTAKE REMEDIAL ACTION IN ORDER TO REDUCE THE INFILTRATION OR EXFILTRATION TO AN AMOUNT WITHIN THE LIMITS SPECIFIED. AN OWNER SHALL RETEST A PIPE FOLLOWING A REMEDIATION ACTION.
- ) IF A GRAVITY COLLECTION PIPE IS COMPOSED OF FLEXIBLE PIPE, DEFLECTION TESTING IS ALSO REQUIRED. THE FOLLOWING PROCEDURES MUST BE FOLLOWED: ) FOR A COLLECTION PIPE WITH INSIDE DIAMETER LESS THAN 27 INCHES, DEFLECTION MEASUREMENT REQUIRES A RIGID MANDREL.
- A) MANDREL SIZING. A RIGID MANDREL MUST HAVE AN OUTSIDE DIAMETER (OD) NOT LESS THAN 95% OF THE BASE INSIDE DIAMETER (ID) OR AVERAGE ID OF A PIPE, AS SPECIFIED IN THE APPROPRIATE STANDARD BY THE ASTMS. AMERICAN WATER WORKS ASSOCIATION, UNI-BELL, OR AMERICAN NATIONAL STANDARDS INSTITUTE, OR ANY RELATED APPENDIX.
- ) IF A MANDREL SIZING DIAMETER IS NOT SPECIFIED IN THE APPROPRIATE STANDARD, THE MANDREL MUST HAVE AN OD EQUAL TO 95% OF THE ID OF A PIPE. IN THIS CASE, THE ID OF THE PIPE, FOR THE PURPOSE OF DETERMINING THE OD OF THE MANDREL. MUST EQUAL BE THE AVERAGE OUTSIDE DIAMETER MINUS TWO MINIMUM WALL THICKNESSES FOR OD CONTROLLED PIPE AND THE AVERAGE INSIDE DIAMETER FOR ID CONTROLLED PIPE. i) ALL DIMENSIONS MUST MEET THE APPROPRIATE STANDARD.
- R) MANDREL DESIGN A RIGID MANDREL MUST BE CONSTRUCTED OF A METAL OR A RIGID PLASTIC MATERIAL THAT CAN WITHSTAND 200 PSI WITHOUT BEING DEFORMED.
- ) A MANDREL MUST HAVE NINE OR MORE ODD NUMBER OF RUNNERS OR LEGS. iii) A BARREL SECTION LENGTH MUST EQUAL AT LEAST 75% OF THE INSIDE DIAMETER
- v) EACH SIZE MANDREL MUST USE A SEPARATE PROVING RING. ) METHOD OPTIONS.
- AN ADJUSTABLE OR FLEXIBLE MANDREL IS PROHIBITED. i) A TEST MAY NOT USE TELEVISION INSPECTION AS A SUBSTITUTE FOR A
- DEFLECTION TEST. ii) IF REQUESTED, THE EXECUTIVE DIRECTOR MAY APPROVE THE USE OF A
- DEFLECTOMETER OR A MANDREL WITH REMOVABLE LEGS OR RUNNERS ON A CASE-BY-CASE BASIS. 2) FOR A GRAVITY COLLECTION SYSTEM PIPE WITH AN INSIDE DIAMETER 27 INCHES AND GREATER, OTHER TEST METHODS MAY BE USED TO DETERMINE VERTICAL
- DEFLECTION, A DEFLECTION TEST METHOD MUST BE ACCURATE TO WITHIN PLUS OR MINUS 0.2% DEFLECTION S) AN OWNER SHALL NOT CONDUCT A DEFLECTION TEST UNTIL AT LEAST 30 DAYS AFTER THE FINAL BACKFILL. ) GRAVITY COLLECTION SYSTEM PIPE DEFLECTION MUST NOT EXCEED FIVE PERCENT
- 5) IF A PIPE SECTION FAILS A DEFLECTION TEST, AN OWNER SHALL CORRECT THE
- PROBLEM AND CONDUCT A SECOND TEST AFTER THE FINAL BACKFILL HAS BEEN IN PLACE AT LEAST 30 DAYS. 3. ALL MANHOLES MUST BE TESTED TO MEET OR EXCEED THE REQUIREMENTS OF 30
- TAC \$217.58. ) ALL MANHOLES MUST PASS A LEAKAGE TEST. ) AN OWNER SHALL TEST EACH MANHOLE (AFTER ASSEMBLY AND BACKFILLING) FOR LEAKAGE, SEPARATE AND INDEPENDENT OF THE COLLECTION SYSTEM PIPES, BY HYDROSTATIC EXFILTRATION TESTING, VACUUM TESTING, OR OTHER METHOD APPROVED BY THE EXECUTIVE DIRECTOR.
- HYDROSTATIC TESTING ) THE MAXIMUM LEAKAGE FOR HYDROSTATIC TESTING OR ANY ALTERNATIVE TEST
- METHODS IS 0.025 GALLONS PER FOOT DIAMETER PER FOOT OF MANHOLE DEPTH ) TO PERFORM A HYDROSTATIC EXFILTRATION TEST, AN OWNER SHALL SEAL ALL WASTEWATER PIPES COMING INTO A MANHOLE WITH AN INTERNAL PIPE PLUG, FILL THE MANHOLE WITH WATER, AND MAINTAIN THE TEST FOR AT LEAST ONE HOUR. ) A TEST FOR CONCRETE MANHOLES MAY USE A 24-HOUR WETTING PERIOD BEFORE TESTING TO ALLOW SATURATION OF THE CONCRETE.
- N) TO PERFORM A VACUUM TEST, AN OWNER SHALL PLUG ALL LIFT HOLES AND EXTERIOR JOINTS WITH A NON-SHRINK GROUT AND PLUG ALL PIPES ENTERING A

) VACUUM TESTING.

- B) NO GROUT MUST BE PLACED IN HORIZONTAL JOINTS BEFORE TESTING. C) STUB-OUTS, MANHOLE BOOTS, AND PIPE PLUGS MUST BE SECURED TO PREVENT MOVEMENT WHILE A VACUUM IS DRAWN.
- AN OWNER SHALL USE A MINIMUM 60 INCH/LB TORQUE WRENCH TO TIGHTEN THE EXTERNAL CLAMPS THAT SECURE A TEST COVER TO THE TOP OF A MANHOLE. E) A TEST HEAD MUST BE PLACED AT THE INSIDE OF THE TOP OF A CONE SECTION, AND THE SEAL INFLATED IN ACCORDANCE WITH THE MANUFACTURER'S
- RECOMMENDATIONS. ) THERE MUST BE A VACUUM OF 10 INCHES OF MERCURY INSIDE A MANHOLE TO PERFORM A VALID TEST.
- ) A TEST DOES NOT BEGIN UNTIL AFTER THE VACUUM PUMP IS OFF. ) A MANHOLE PASSES THE TEST IF AFTER 2.0 MINUTES AND WITH ALL VALVES CLOSED, THE VACUUM IS AT LEAST 9.0 INCHES OF MERCURY.
- ALL PRIVATE SERVICE LATERALS MUST BE INSPECTED AND CERTIFIED IN ACCORDANCE WITH 30 TAC \$213.5(C)(3)(I). AFTER INSTALLATION OF AND, PRIOR TO COVERING AND CONNECTING A PRIVATE SERVICE LATERAL TO AN EXISTING ORGANIZED SEWAGE COLLECTION SYSTEM. A TEXAS LICENSED PROFESSIONAL ENGINEER. TEXAS REGISTERED SANITARIAN. OR APPROPRIATE CITY INSPECTOR MUST VISUALLY INSPECT THE PRIVATE SERVICE LATERAL AND THE CONNECTION TO THE SEWAGE COLLECTION SYSTEM, AND CERTIFY THAT IT IS CONSTRUCTED IN CONFORMITY WITH THE APPLICABLE PROVISIONS OF THIS SECTION. THE OWNER OF THE COLLECTION SYSTEM MUST MAINTAIN SUCH CERTIFICATIONS FOR FIVE YEARS AND FORWARD COPIES TO THE APPROPRIATE REGIONAL OFFICE UPON REQUEST. CONNECTIONS MAY ONLY BE MADE TO AN APPROVED SEWAGE COLLECTION

THESE GENERAL CONSTRUCTION NOTES MUST BE INCLUDED ON THE CONSTRUCTION PLANS PROVIDED TO THE CONTRACTOR AND ALL SUBCONTRACTORS.

#### PROJECT SEWER NOTES

VICINITY OF WATER MAINS.

INVERT SHOWN ON PLANS.

- ALL RESIDENTIAL SEWER SERVICE LATERALS ARE 6" DIA. AND SHALL BE EXTENDED TO 10' PAST THE PROPERTY LINE AND CAPPED AND SEALED. CONTRACTOR SHALL INSTALL A 2" X 4" STAKE, FOUR (4) FEET LONG, TWO (2) FEET DEEP INTO THE GROUND AT THE END OF EACH SERVICE. NO
- CONTRACTOR TO INSTALL CLEANOUTS AT THE END OF ALL SEWER LATERALS, PER LATERAL DETAIL SHEET C5.10
- NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.
- ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO THE PROPERTY LINE.
- WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 150 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE
- CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 6" ABOVE FINISHED GRADE WITH CONCRETE
- . ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE NOTED. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE FROM
- CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE.
- O. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.
- CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES AND. WITHIN LIMITS OF PAVEMENT, BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.
- 12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55.
- 13. ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC PIPE. 14. IF THE GIVEN TOP OF MANHOLE ELEVATION DOES NOT AGREE ON ACTUAL GROUND SURFACE OR FINISH PAVEMENT, THE CONTRACTOR SHALL ADJUST

ELEVATIONS SUCH THAT THE TOP OF MANHOLE SHALL BE 0.5' ABOVE

6. ALL MANHOLES CONSTRUCTED OVER THE EDWARDS AQUIFER RECHARGE ZONE SHOULD BE WATERTIGHT

EXISTING GROUND, OR FLUSH TO FINISH ASPHALT PAVEMENT.

#### SAWS GENERAL SECTION

- ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:
- A.CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) "DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM", TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC
- DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290. B.CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF
- HIGHWAYS, STREETS AND DRAINAGE' C.CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR
- WATER AND SANITARY SEWER CONSTRUCTION". D.CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION"
- E. CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL"
- THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE APPROVED COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP) FROM THE CONSULTANT AND HAS BEEN NOTIFIED BY SAWS CONSTRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK REQUIREMENTS. WORK COMPLETED BY THE CONTRACTOR WITHOUT AN APPROVED COUNTER PERMIT AND/OR A GCP WILL BE SUBJECT TO REMOVAL AND REPLACEMENT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER.
- THE CONTRACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS WEBSITE, HTTP: //WWW.SAWS.ORG/BUSINESS\_CENTER/SPECS. UNLESS OTHERWISE NOTED WITHIN THE DESIGN PLANS
- THE CONTRACTOR IS TO MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973. ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO BEGINNING ANY WORK.
- LOCATION AND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
- SAWS UTILITY LOCATES: HTTP://WWW.SAWS.ORG/SERVICE/LOCATES
- COSA DRAINAGE (210) 207-0724 OR (210) 207-6026
- COSA TRAFFIC SIGNAL OPERATIONS (210) 206-8480 COSA TRAFFIC SIGNAL DAMAGES (210) 207-3951
- \* TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811 THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS
- ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION. ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE
- CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS. THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- . THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- . HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.
- WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO CONSTWORKREQ@SAWS.ORG.
- ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.
- 4. COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING THE COMPACTION RÉQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY, COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE SAWS INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEFT AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.
- 5. A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO SAWS CONSTRUCTION INSPECTION DIVISION.

TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR

STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY,

SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND

THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN

ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION

SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S

IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL

PROVIDE FOR ADEQUATE TRENCH EXCAVATION, SAFETY PROTECTION THAT

COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS.

SPECIFICALLY CONTRACTOR AND /OR CONTRACTOR'S INDEPENDENTLY RETAINED

EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY

PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE

AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION. NOTE MUST BE ON ALL PLAN & PROFILE SHEETS

#### SAWS SEWER NOTES


TCEQ AND SAWS.

- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:
- A. IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210) 233-2014.
- PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR B.ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.
- C.CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS.
- D.CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.
- E.CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS. F.MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.

SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA, TCEQ AND/OR ANY OTHER FEDERAL, STATE OR LOCAL AGENCIES.

NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE

- IF BYPASS PUMPING IS REQUIRED, THE CONTRACTOR SHALL PERFORM SUCH WORK IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING".
- PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973 AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS: THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
- SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241, TAC 217.53 AND TCEQ 290.44(E)(4)(B). CONTRACTOR SHALL CENTER A 20' JOINT OF 160 PSI PRESSURÉ RATED PVC AT THE PROPOSED WATER CROSSING.
- ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSPI)
- SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY O THE SAWS INSPECTOR ASSIGNED TO THE COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE REGARDLESS OF SIZE.
- MANHOLE AND ALL PIPE TESTING (INCLUDING THE TV INSPECTION) MUST BE PERFORMED AND PASSED PRIOR TO FINAL FIELD ACCEPTANCE BY SAWS CONSTRUCTION INSPECTION DIVISION, AS PER THE SAWS SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.
- ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.





TON!

#### SEWERSHED: SALADO CREEK

DEVELOPER'S NAME: BALEARIA, LLC ADDRESS: 15555 TRADESMAN DR., SUITE 400 SAN ANTONIO STATE: TEXAS ZIP: 78249

NUMBER OF LOTS 5 SAWS JOB NO. 25-1531


PHONE# \_\_\_ SAWS BLOCK MAP# 164-658 TOTAL EDU'S 150 TOTAL ACREAGE 11.12 TOTAL LINEAR FOOTAGE OF PIPE: 8" ~ 537 LF PLAT NO. 25-11800090


NO 25-1180009 7328-21 ESIGNER

Z

C5.05

HECKED DM DRAWN SS





**LOCATION MAP** 

NOT-TO-SCALE

LEGAL DESCRIPTION: LOT 7 - 11, BLOCK 3, N.C.B 19218 CANYON GOLF RETAIL (11.12 ACRES) PLAT NO. 25-11800090

ADDRESS: 21902 CANYON GOLF ROAD SAN ANTONIO, TX 78258

DAVID E. MARTINEZ

94900

— — PROPERTY LINE --- 1100- --- EXISTING CONTOUR PROPOSED CONTOUR EXISTING WATER EXISTING OVERHEAD ELECTRIC EXISTING SANITARY SEWER PROPOSED SANITARY SEWER LINE PROPOSED WATER MAIN

EFFECTIVE (EXISTING) FEMA 1% ANNUAL CHANCE (100-YR) FLOODPLAIN 100' TCEQ SEWER ENVELOPE

#### CONTRACTOR'S NOTE:

#### SPILLS, OVERFLOWS OR DISCHARGES OF WASTEWATER

ATTENTION CONTRACTORS: ALL SPILLS, OVERFLOW, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO YOUR COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE REGARDLESS OF SIZE. YOUR COMPLIANCE WILL ENABLE SAWS TO FULFILL

IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTROL SEWER FLOWS SO THAT A SPILL, OVERFLOW OR DISCHARGE DOES NOT OCCUR. IN THE EVENT THAT A SPILL, OVERFLOW, OR DISCHARGE OCCURS, THE CONTRACTOR MAY LIABLE FOR:

1. ALL FINES, PENALTIES, OR OTHER COSTS THAT ASSESSED TO OR AGAINST SAWS BY ANY STATE, FEDERAL, OR OTHER GOVERNMENTAL

2. SAWS STAFF AND MATERIAL COST TO RESPOND TO THE SPILL, OVERFLOW, OR DISCHARGE, OR TO THE MITIGATE THE EFFECTS OF THE SPILL, OVERFLOW OR DISCHARGE, OR TO SUPPORT THE CLEANUP EFFORT.

3. ALL DAMAGES CAUSE TO SAWS, OR ANY OTHER PERSONS OR ENTITIES THAT RESULT OF THE SPILL, OVERFLOW OR DISCHARGE.

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTO SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO T START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL E THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL E AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN (

#### TRENCH EXCAVATION SAFETY PROTECTION

CONTRACTOR AND/ OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOY OR STRUCTURAL DESIGN/ GEOTECHNICAL/ SAFETY/EQUIPMENT CONSULTANT IF ANY, SHALL REVIEW THESE PLANS AND ANY AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITES WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENC EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND /C PROCEDURES FOR THE PROJECT DESCRIBED IN THE CONTRACT DOCUMENTS THE CONTRACTOR'S IMPLEMENTATION OF THESE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFÉTY PROTECTION THAT COMPLY WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFET CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM II ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AN ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

#### **CAUTION UNDERGROUND UTILITIES** THE LOCATIONS AND DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLAN


ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS OF UTILITIES MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT SHALL BE REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.

#### **CAUTION OVERHEAD UTILITIES**

CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN WORKING UNDER "HIC VOLTAGE TRANSMISSION LINES". A WORKING HEIGHT OF 30' FROM GROUND ELEVATION WILL BE OBSERVED WHEN WORKING UNDER THE HIGH VOLTAGE LINE. COORDINATE ALL WORK WITH THE LOCAL UTILITY PROVIDER.

NO 25-1180009 7328-21 APRIL 2025 ESIGNER HECKED DM DRAWN SS

C5.10



SEWERSHED: SALADO CREEK DEVELOPER'S NAME: BALEARIA. LLC ADDRESS: 15555 TRADESMAN DR., SUITE 400 SAN ANTONIO STATE: TEXAS ZIP: 78249 SAWS BLOCK MAP# 164-658 TOTAL EDU'S 150 TOTAL ACREAGE 11.12


TOTAL LINEAR FOOTAGE OF PIPE: 8" ~ 537 LF PLAT NO. 25-11800090

\_\_\_\_\_ SAWS JOB NO. <u>25-1531</u>


CITY OF LOOP 1604 SAN ANTONIO **LOCATION MAP** 

#### NOT-TO-SCALE

ADDRESS: 21902 CANYON GOLF ROAD LEGAL DESCRIPTION: LOT 7 - 11, BLOCK 3, N.C.B 19218 CANYON GOLF RETAIL (11.12 ACRES) SAN ANTONIO, TX 78258 PLAT NO. 25-11800090



#### LEGEND



#### <u>NOTE</u>

SEE SHEET C5.05 FOR ADDITIONAL GENERAL NOTES.

#### 98% COMPACTION NOTE:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION OF ALL TRENCH BACKFILL AND PAYING FOR THE TESTS TO BE PERFORMED BY THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION PO RANDOMLY SELECTED OR AS INDICATED BY THE SAWS INSPECTOR/TE ADMINISTER, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALI NECESSARY DOCUMENTED TEST RESULTS.

#### CAUTION!!

CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITING TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCTBANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

#### **GENERAL SEWER NOTES**

. SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 P.S.I. AND MEET THE REQUIREMENTS OF ASTM D2241 WITH ONE 20' JOINT CENTERED AT WATER MAIN.

2. NO VERTICAL STACKS ALLOWED FOR ANY LOTS UNLESS OTHERWISE SPECIFIED BY THE ENGINEER.

3. ALL 6" SEWER LATERALS WILL BE SET AT 2% GRADE FROM THE MAIN TO THE PROPERTY LINE.

4. WHEN HORIZONTAL DISTANCE BETWEEN SEWER PIPES AND WATER MAIN IS LESS THAN 9 FOOT OF SEPARATION, SEWER MAIN SHALL BE INSTALLED WITH 150 PSI (MIN) PRESSURE PIPE AND FITTINGS IN ACCORDANCE WITH SAWS CONSTRUCTION CRITERIA FOR CONSTRUCTION OF SEWER MAINS IN THE VICINITY OF WATER MAINS. (SEE SEWER NOTES SHEET C4.10)

5. CONTRACTOR SHALL ENSURE THAT MANHOLES OUTSIDE OF PAVED AREAS ARE SET WITH TOP ELEVATIONS 3" ABOVE FINISHED GRADE WITH CONCRETE RING ENCASEMENT.

6. ALL SEWER PIPES SHALL BE 8" PVC (SDR 26), UNLESS OTHERWISE 7. CONTRACTOR IS TO VERIFY EXISTING INVERT OF EXISTING SANITARY

FROM INVERT SHOWN ON PLANS.

SEWER MAINS AND ALERT ENGINEER IMMEDIATELY OF ANY DIFFERENCE

8. CONTRACTOR SHALL PROTECT ALL EXISTING FENCES. ANY FENCE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR EXPENSE.

9. THE CONTRACTOR WILL BE RESPONSIBLE FOR DETERMINING EXACT LOCATION OF ALL UTILITIES AND DRAINAGE STRUCTURES WHETHER SHOWN ON THE PLANS OR NOT. THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY SIZE, GRADE, AND LOCATION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY DEVIATIONS FROM PLANS PRIOR TO BEGINNING CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, WHETHER SHOWN ON THE PLANS OR NOT, SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR, AT HIS EXPENSE.

10.SEE THIS SHEET FOR TYPICAL SANITARY SEWER/WATER CROSSING

1. CONCRETE RING ENCASEMENT TO BE INSTALLED ON ALL MANHOLES, AND WITHIN LIMITS OF PAVEMENT BE INSTALLED TO THE TOP OF THE BASE LAYER WITH A MINIMUM OF 2" OF ASPHALT ON TOP OF THE RING ENCASEMENT.

12. MANHOLE OPENING INCREASED TO 30" AS PER TAC CHAPTER 217.55. 13.ALL SEWER PIPE LATERALS SHALL BE SDR 26 (CLASS 160) PVC DAVID E. MARTINEZ 94900

SO


SAN ANTONIO, TEXAS SEWAGE COLLECTION S TARY SEWER PLAN & PRO


NO 25-1180009 7328-21 APRIL 2025 DESIGNER


CHECKED DM DRAWN SS


C5.11


Z





























JOINT RESTRAINTS SHALL BE APPROVED AS SPECIFIED IN MATERIAL SPECIFICATION ITEM 95-10. **CASING DETAIL** 




#### TYPICAL SANITARY SEWER/WATER CROSSING DETAIL (NOT TO SCALE)




| DEVELOPER'  | S NAME: BALEARI | A. II.C            |                 |                          |
|-------------|-----------------|--------------------|-----------------|--------------------------|
|             | 15555 TRADESMA  |                    | ITE 400         |                          |
| CITY:       | SAN ANTONIO     | _STATE:            | TEXAS           | ZIP: <u>78249</u>        |
| PHONE#      |                 |                    | FAX#            |                          |
|             |                 |                    |                 | OTAL ACREAGE 11.1        |
| TOTAL LINEA | R FOOTAGE OF P  | IPE: <u>8" ~ 5</u> | <u>37 LF</u> PL | AT NO. <u>25-1180009</u> |
| NUMBER OF   | LOTS 5          | SAWS               | JOB NO2         | 25-1531                  |





DAVID E. MARTINEZ

94900



ANY

ESIGNER

NO. 25-11800090

CHECKED DM DRAWN SS

C5.15

7328-21