

March 12, 2025  
SCS Project No. 16224067.00

Mr. Arten Avakian  
MSW Permits Section – MC 124  
Texas Commission on Environmental Quality  
P.O. Box 13087  
Austin, Texas 78711

Subject: City of Uvalde MSW Landfill - Uvalde County  
Municipal Solid Waste - Permit No. 1725  
Permit Modification Application – Landfill Gas Management Plan  
RN102803921 / CN600648455

Dear Mr. Avakian:

On behalf of City of Uvalde (City), SCS Engineers (SCS) has prepared the attached permit modification application of Attachment 14 - Landfill Gas Management Plan (LGMP), as requested by Texas Commission on Environmental Quality (TCEQ) in letters dated August 23, 2024 (Tracking Nos. 29886183 and 30043922) and December 6, 2024 (Tracking No. 30360699). This permit modification has been prepared to address specific questions and/or comments provided by you in an email dated June 30, 2024 and addressed to Mr. Brett DeVries, P.E., Ph.D, as described below. Specifically, the purpose of this permit modification is to update the LGMP to reflect current site conditions and incorporate complete documentation on the landfill gas (LFG) monitoring system, including temporary probes, vents, and the gas extraction system (descriptive text, tables, drawings, and appendices containing logs and construction details), specifically related to the LFG remediation efforts for GMP-4. As such, this permit modification is being submitted consistent with the 30 TAC §305.70(k)(3), related to installation of a landfill gas management system for a landfill gas remediation plan, which requires public notice.

In response to your June 30, 2024 email, the following summarizes the revisions made to the LGMP, as described below in response to your questions/comments:

- Section 1.1, Site Description – Reference to prior Figure 1.3 (dated 10/21/2016) was **removed** since it is now combined with **new** Figure 1.2 (replaced prior Figure 1.2, dated 10/21/2016). Reference to prior Figure 1.4 has been corrected to the **new** Figure 3.1 (replaced prior Figure 3.1, dated 10/21/2016).
- Section 2.5, Facility Boundaries (Permitted Area) – Added the definition for the acronym, EAP – Exceedance Action Plan.
- Section 3.1, Landfill Gas Monitoring System – Removed an unnecessary reference to a previous superseded LGMP (replaced due to permit modification dated 10/21/2016) and added a reference to the added Table 2.0, Gas Monitoring Probe/Vent Completion Details; clarified what changes would be made to the LGMP should an EAP be required.
- Section 3.2.1 Gas Probe Monitoring Procedures – Identified which buildings would be monitored and referenced the monitoring form added as Appendix C.
- Section 3.2.4 Backup Monitoring Plan – Added text regarding the timeframe in which damaged/failed gas monitoring features would be repaired/replaced and what documentation would be provided and kept in the Site Operating Record, as well as when a permit modification would be necessary for such changes.

Received Waste Permits Division: 03/14/2025  
Tracking No.: 31432047



# Texas Commission on Environmental Quality Waste Permits Division Correspondence Cover Sheet

Date: March 12, 2025

Facility Name: City of Uvalde Landfill

Permit or Registration No.: 1725

Nature of Correspondence:

Initial/New

Response/Revision to TCEQ Tracking No.:  
\_\_\_\_\_ (from subject line of TCEQ letter  
regarding initial submission)

Affix this cover sheet to the front of your submission to the Waste Permits Division. Check appropriate box for type of correspondence. Contact WPD at (512) 239-2335 if you have questions regarding this form.

**Table 1 - Municipal Solid Waste Correspondence**

Applications	Reports and Notifications
<input type="checkbox"/> New Notice of Intent	<input type="checkbox"/> Alternative Daily Cover Report
<input type="checkbox"/> Notice of Intent Revision	<input type="checkbox"/> Closure Report
<input type="checkbox"/> New Permit (including Subchapter T)	<input type="checkbox"/> Compost Report
<input type="checkbox"/> New Registration (including Subchapter T)	<input type="checkbox"/> Groundwater Alternate Source Demonstration
<input type="checkbox"/> Major Amendment	<input type="checkbox"/> Groundwater Corrective Action
<input type="checkbox"/> Minor Amendment	<input type="checkbox"/> Groundwater Monitoring Report
<input type="checkbox"/> Limited Scope Major Amendment	<input type="checkbox"/> Groundwater Background Evaluation
<input checked="" type="checkbox"/> Notice Modification	<input type="checkbox"/> Landfill Gas Corrective Action
<input type="checkbox"/> Non-Notice Modification	<input type="checkbox"/> Landfill Gas Monitoring
<input type="checkbox"/> Transfer/Name Change Modification	<input type="checkbox"/> Liner Evaluation Report
<input type="checkbox"/> Temporary Authorization	<input type="checkbox"/> Soil Boring Plan
<input type="checkbox"/> Voluntary Revocation	<input type="checkbox"/> Special Waste Request
<input type="checkbox"/> Subchapter T Disturbance Non-Enclosed Structure	<input type="checkbox"/> Other:
<input type="checkbox"/> Other:	

**Table 2 - Industrial & Hazardous Waste Correspondence**

Applications	Reports and Responses
<input type="checkbox"/> New	<input type="checkbox"/> Annual/Biennial Site Activity Report
<input type="checkbox"/> Renewal	<input type="checkbox"/> CPT Plan/Result
<input type="checkbox"/> Post-Closure Order	<input type="checkbox"/> Closure Certification/Report
<input type="checkbox"/> Major Amendment	<input type="checkbox"/> Construction Certification/Report
<input type="checkbox"/> Minor Amendment	<input type="checkbox"/> CPT Plan/Result
<input type="checkbox"/> CCR Registration	<input type="checkbox"/> Extension Request
<input type="checkbox"/> CCR Registration Major Amendment	<input type="checkbox"/> Groundwater Monitoring Report
<input type="checkbox"/> CCR Registration Minor Amendment	<input type="checkbox"/> Interim Status Change
<input type="checkbox"/> Class 3 Modification	<input type="checkbox"/> Interim Status Closure Plan
<input type="checkbox"/> Class 2 Modification	<input type="checkbox"/> Soil Core Monitoring Report
<input type="checkbox"/> Class 1 ED Modification	<input type="checkbox"/> Treatability Study
<input type="checkbox"/> Class 1 Modification	<input type="checkbox"/> Trial Burn Plan/Result
<input type="checkbox"/> Endorsement	<input type="checkbox"/> Unsaturated Zone Monitoring Report
<input type="checkbox"/> Temporary Authorization	<input type="checkbox"/> Waste Minimization Report
<input type="checkbox"/> Voluntary Revocation	<input type="checkbox"/> Other:
<input type="checkbox"/> 335.6 Notification	
<input type="checkbox"/> Other:	

- Section 4.1.1 Passive Vents – Added section with information of passive gas vent remediation efforts implemented-to-date.
- Section 4.1.2 Backup/Temporary Monitoring Probes – Added section with information pertaining to backup and temporary monitoring probes installed for remediation efforts-to-date.
- Section 4.1.3 Initial Gas Collection System – Added section with information pertaining to the initial gas collection system installed for continued remediation efforts.
- Figure 1.1 – USGS Site Location Map: Map was **replaced** to show the City of Uvalde as a reference point.
- Figure 1.2 – Potential Offsite Residences: Map was **replaced** and renamed “Regulatory Distances” to incorporate the regulatory distances shown in prior Figure 1.3 (dated 10/21/2016, removed from this permit modification, as noted above), as well as the offsite residences shown in prior Figure 1.2 (dated 10/21/2016).
- Figure 1.3 – Regulatory Distances: Map was removed and the information added to **new** Figure 1.2.
- Figure 1.4 – General Landfill Facility Layout: Map was **removed** and the information incorporated into **new** Figure 3.1 – GMP and GV Location Map.
- Figure 3.1 – GMP and GV Location Map: Map has been renamed “Gas Monitoring Features Location Map” and replaced with a new updated map showing the location of all gas monitoring probes, remediation features incorporated into the Landfill Gas Management System, as well as showing information included in prior Figure 1.4 (dated 10/21/2016, removed from this permit modification, as noted above).
- Appendix A – Methane Monitoring Form: Appendix and form have been added to the LGMP
- Appendix B – Landfill Gas Remediation Plans: Appendix has been added to the document for reference of implemented remediation plans.
- Appendix C – Vertical Extraction Vents/Wells: Appendix has been added to reflect all available boring logs and completion records of gas passive/active extraction wells and vents.

In response to your questions/comments provided in your email dated July 30, 2024, we have included your original comment, followed by our response and/or revision in **bold/italics**.

A1a. [Table of Contents] Add entries in TOC for appendices. Examples:

- Appendix A: Gas Monitoring Probe Boring Logs and Completion Logs
- Appendix B: BGMP and TGMP Boring Logs and Completion Logs
- Appendix C: Temporary gas investigations probes
- Appendix D: UGV and TV Construction Details, Drawings
- Appendix E: Gas extraction system
- Appendix F: Summary of all gas monitoring measurements.

***Appendix B: Gas Remediation Plans have been added to the LGMP.***

***Appendix C: Vertical Extraction Vents/Wells has been added to the LGMP. The appendix includes boring logs and completion details for vertical extraction wells and vents.***

***The Uvalde Gas Vent/Temporary Vent details as well as the gas extraction system details are included in Appendix B. Gas measurements have not been included in the LGMP since it is not a requirement per the current regulations. The measurements are located in the Site Operating Record as referenced in the LGMP.***

A1b. [Table of Contents] Are all remediation features through Phase 4.0 installed/implemented?

***Phase 4.0, as referenced in the landfill gas remediation plan dated September 2, 2022, has not been implemented or installed at this time. The City is currently evaluating other remediation options and will provide an updated remediation plan under a separate transmittal cover letter.***

A1c. [Table of Contents] Any thoughts on why gas being generated?

***The gas is being generated from the decaying waste, but the migration seems to be related to the Pre-Subtitle D, Stage A cell.***

A1d. [Table of Contents] Any leachate in the landfill?

***Leachate is collected and stored onsite in an above ground storage tank on the south side of the landfill.***

A2. [Table of Contents] Add table or tables of completion details, including installation dates:

- Gas monitoring probes
- BGMPs, TGMPs, GMP #.#s, UGVs, TVs, etc.
- Vents in waste
- Gas extraction wells

***Two tables have been added to the LGMP with information that is available: Table 2.0, Gas Monitoring Probe Completion Details and Table 3.0, Gas Extraction Well/Vent Completion Details.***

A3. [Section 1.1 Site Description] One structure looks like it may be within 1,000 ft.

***The closest structure is just outside the 1,000-foot distance from the waste placement boundary, as shown on the new Figure 1.2.***

A4. [Section 2.5 Facility Boundaries] What is EAP?

***The definition for EAP, Exceedance Action Plan, has been added to Section 2.5 Facility Boundaries (Permitted Area).***

A5. [Section 3.1 Landfill Gas Monitoring System] Reference table listing probes and details.

***A reference to Table 2.0, Gas Monitoring Probe Completion Details, has been added to the text Section 3.1 Landfill Gas Monitoring System.***

A6. [Section 3.1 Landfill Gas Monitoring System] Is this text necessary?

***The text in question has been removed as it is not necessary since it references a previous superseded LGMP (replaced due to permit modification dated 10/21/2016) and added a reference to the added Table 2.0, Gas Monitoring Probe/Vent Completion Details.***

- A7. [Section 3.1 Landfill Gas Monitoring System] Modify to add something to the effect of:  
If additional monitoring points or gas management features are needed, this LGMP will be modified to document and incorporate those details in the permit.

***A clarification of what would be included in the modified LGMP should an EAP be necessary has been added to the text.***

- A8a. [Section 3.2.1 Gas Probe Monitoring Procedures] Which building?

***Clarifying text has been added to specifically identify any building(s) being monitored.***

- A8b. [Section 3.2.1 Gas Probe Monitoring Procedures] Do the buildings have automatic, continuous methane sensors that will sound an audible alarm if methane is detected?

***The buildings do not have automatic, continuous methane sensors with alarms, but are sampled during the quarterly monitoring periods using a portable methane gas detector as described in Section 3.2.1 Gas Probe Monitoring Procedures.***

- A9. [Section 3.2.4 Backup Monitoring Plan] Clarify what the mod would be for . . . install replacement and plug old probe if it cannot be repaired?

***The statement has been clarified to address what measures would be taken in the event of a gas monitoring system feature damage or failure.***

- A10. [Section 4.0 Exceedance Action Plan] Do we have a map of current landowners within 1,000 ft?

***A current landowners map and list have been included for the permit modification submittal as required for public notice modifications.***

- A11. [Figure 1.1] Is this City of Uvalde? Label to provide a point of reference on the map.

***Figure 1.1, USGS Site Location Map, has been replaced to include identification of the City of Uvalde for a point of reference.***

- A12. [Figure 1.2] The location of these structures does not quite seem to match current, as seen in aerial photo, and one may be within 1,000 ft of waste unit boundary.

***Figure 1.2 has been replaced with an aerial version to depict any habitable structures within 1,000 feet and 3,000 feet of the waste placement boundary. The closest structure is just outside the 1,000-foot boundary.***

- A13. [Figure 1.3] Same comment re structures.

***Figure 1.3 has been removed from the LGMP and combined with the new Figure 1.2 referenced in the previous comment.***

A14a. [Figure 1.4] Just FYI right now:  
MW-11, Jan 2023 cis-1,2-dichloroethene detected; not yet resampled.

***It is acknowledged that in January 2023, cis- 1,2-dichloroethene was detected in MW-11 and has not been resampled.***

A14b. [Figure 1.4] Just FYI right now:  
MW-12, Initial detections of benzene and cis-1,2-dichloroethene in July 2022; not detected in verification resamples.

***It is acknowledged that initial detections of benzene and cis- 1,2-dichloroethene in July 2022 were not detected in verification resamples.***

A15. [Figure 1.4] Would be good to have gas probe here, between waste unit boundary and facility structures outside permit boundary.

***Given no historical methane exceedance readings in GMP-2 or the structures, and no further exceedance readings in GMP-3 since 2004, as well as the spacing of GMP-2 and GMP-3 following the current LGMP, an additional probe is not proposed between the waste unit boundary and the structures at this time.***

A16. [Figure 1.4] Is MW-7 checked for methane? May not be useful as it is likely completed at depths below zones of potential gas migration.

***MW-7 is not checked for methane. The necessity for methane testing in MW-7 is not suggested based on the same reasoning stated above.***

A17. [Figure 1.4] Do structures have continuous gas monitors?

***The structures do not have continuous gas monitors. Please refer to the response to comment A8b.***

A18. [Figure 1.4] Modify monitoring point labels to be consistent with current terminology.

***Figure 1.4, General Landfill Facility Layout, has been removed and the information is incorporated into the updated and replaced Figure 3.1, Gas Monitoring Features Location Map. The monitoring point labels have been updated for consistency in the replaced Figure 3.1.***

A19. [Figure 3.1] Replace with drawing showing all of the gas monitoring and management features. Label monitoring point consistent with current terminology.

***Figure 3.1, GMP & GV Location Map, has been renamed Gas Monitoring Features Location Map and replaced with an updated map of the current gas monitoring system and features, including the general facility layout information previously shown in Figure 1.4, General Landfill Facility Layout, as well as updated terminology.***

A20. [Figure 3.2] Confirm:  
Is this how probes were constructed (flush completion, no casing "stickup")?

***The detail shown on Figure 3.2 is applicable to the installation of the GMPs and BGMPs.***

A21. [Appendix 1997 Landfill Gas Management Plan] A lot of good information here that should be brought forward and merged into current LGMP (figures, tables, forms, etc.).

***The figures and tables in the 1997 LGMP can either be found in the Geology Report (Attachment 4 of the Site Development Plan) or have been updated and included in this modification. Appendix A, Methane Monitoring and Recording Form has been added to include a current Methane Monitoring Form. All other information has been superseded by the current LGMP and the modifications herein, and therefore not necessary for inclusion in the LGMP as an Appendix.***

Consistent with TCEQ regulations we have included Form TCEQ-2065, related to Application Form for MSW Permit or Registration Modification or Temporary Authorization, in Attachment A. Additionally, in accordance with 30 TAC §305.70(k)(9), this permit modification will require public notice consistent with §39.106 and §39.413. As such, we have included a landowner's map and list for properties within ¼-mile of the landfill property boundary (see Attachment B). Consistent with 30 TAC §305.70(d), this submittal addresses minor changes to the landfill that do not substantially alter the permit conditions and do not reduce the capability of the facility to protect human health and the environment. Furthermore, consistent with §330.59(f), we have submitted one original and two copies of the permit modification, with one of the copies marked to clearly show the above-described revisions (see Attachment C for marked version and Attachment D for unmarked version for replacement pages within the approved landfill permit application).

Lastly, in accordance with 30 TAC §330.59(h)(1), SCS has also remitted payment of the \$150.00 application fee through e-Pay (see attached receipt in Attachment A).

We appreciate your review of this permit application. If you or your staff have any questions, please do not hesitate to call Jennifer Brown at 817-358-6130.

Sincerely,



Jennifer Brown P.E.  
Project Manager  
**SCS ENGINEERS**  
TBPE Registration No. F-3407



Ryan Kuntz, P.E.  
Vice President/Satellite Office Manager  
**SCS ENGINEERS**

Attachments: Attachment A – Permit Modification Application Form and e-Pay receipt  
Attachment B – Landowner's Map and List  
Attachment C – Permit Revisions (Marked)  
Attachment D – Permit Revisions (Unmarked)

cc: Mr. Juan Zamora, City of Uvalde  
TCEQ Region Office 13

**ATTACHMENT A**

**PERMIT MODIFICATION APPLICATION FORM**



# Texas Commission on Environmental Quality Application Form for Municipal Solid Waste Permit or Registration Modification or Temporary Authorization

## Application Tracking Information

Facility Name: City of Uvalde Landfill  
Permittee or Registrant Name: City of Uvalde  
MSW Authorization Number: 1725  
Initial Submission Date: 03/12/2025  
Revision Date: \_\_\_\_\_

Instructions for completing this form are provided in [form TCEQ-20650-instr](#)<sup>1</sup>. If you have questions, contact the Municipal Solid Waste Permits Section by email to [mswper@tceq.texas.gov](mailto:mswper@tceq.texas.gov), or by phone at 512-239-2335.

## Application Data

<b>1. Submission Type</b>
<input checked="" type="checkbox"/> Initial Submission <input type="checkbox"/> Notice of Deficiency (NOD) Response
<b>2. Authorization Type</b>
<input checked="" type="checkbox"/> Permit <input type="checkbox"/> Registration
<b>3. Application Type</b>
<input checked="" type="checkbox"/> Modification with Public Notice <input type="checkbox"/> Modification without Public Notice <input type="checkbox"/> Temporary Authorization (TA) <input type="checkbox"/> Modification for Name Change or Transfer
<b>4. Application Fee</b>
<b>Amount</b> The application fee for a modification or temporary authorization is \$150.
<b>Payment Method</b>
<input type="checkbox"/> Check <input checked="" type="checkbox"/> Online through ePay portal <a href="http://www3.tceq.texas.gov/epay/">www3.tceq.texas.gov/epay/</a>
If paid online, enter ePay Trace Number: <u>582EA000658903</u>

<sup>1</sup> [www.tceq.texas.gov/downloads/permitting/waste-permits/msw/forms/20650-instr.pdf](http://www.tceq.texas.gov/downloads/permitting/waste-permits/msw/forms/20650-instr.pdf)

## 5. Electronic Versions of Application

For modifications that require notice, TCEQ will publish electronic versions of the application online. Applicants must provide a clean copy of the administratively complete application and technically complete application. TCEQ will also publish electronic versions of NOD responses online.

## 6. Party Responsible for Mailing Notice

For modifications that require notice, indicate who will be responsible for mailing notice:

Applicant  Agent in Service  Consultant

Contact Name: Jennifer Brown

Title: Project Manager

Email Address: [REDACTED]

## 7. Confidential Documents

Does the application contain confidential documents?

Yes  No

If "Yes", reference the confidential documents in the application, but submit the confidential documents as an attachment in a separate binder marked "CONFIDENTIAL."

## 8. Facility General Information

Facility Name: City of Uvalde Landfill

Contact Name: Juan Zamora Title: Director of Public Works

MSW Authorization Number (if existing): 1725

Regulated Entity Reference Number: **RN** 102803921

Physical or Street Address: 3774 FM 481

City: Uvalde County: Uvalde State: TX Zip Code: 78801

Phone Number: (830) 278-3315

Latitude (Degrees, Minutes, Seconds): 29° 10' 19.92"

Longitude (Degrees, Minutes, Seconds): 99° 51' 35.28"

## 9. Facility Types

Type I  Type IV  Type V  
 Type IAE  Type IVAE  Type VI

## 10. Description of the Revisions to the Facility

Provide a brief description of revisions to permit or registration conditions and supporting documents referred to by the permit or registration, and a reference to the specific provisions under which the modification or temporary authorization application is being made. Also, provide an explanation of why the modification or temporary authorization is needed:

The purpose of this permit modification is to update the LGMP to reflect current site conditions and incorporate complete documentation on the landfill gas (LFG) monitoring system, including temporary probes, vents, and the gas extraction system (descriptive text, tables, drawings, and appendices containing logs and construction details), specifically related to the LFG remediation efforts for GMP-4, consistent with the 30 TAC §305.70(k)(3), related to installation of a landfill gas management system for a landfill gas remediation plan.

## 11. Facility Contact Information

### Site Operator (Permittee or Registrant)

Name: City of Uvalde

Customer Reference Number: **CN** 600648455

Contact Name: Juan Zamora Title: Director of Public Works

Mailing Address: P.O. Box 799

City: Uvalde County: Uvalde State: TX Zip Code: 78802

Phone Number: (830) 278-3315

Email Address: zamora@uvaldetx.gov

Texas Secretary of State (SOS) Filing Number: \_\_\_\_\_

### Operator (if different from Site Operator)

Name: \_\_\_\_\_

Customer Reference Number: **CN** \_\_\_\_\_

Contact Name: \_\_\_\_\_ Title: \_\_\_\_\_

Mailing Address: \_\_\_\_\_

City: \_\_\_\_\_ County: \_\_\_\_\_ State: \_\_\_\_\_ Zip Code: \_\_\_\_\_

Phone Number: \_\_\_\_\_

Email Address: \_\_\_\_\_

Texas Secretary of State (SOS) Filing Number: \_\_\_\_\_

**Consultant (if applicable)**

Firm Name: SCS Engineers  
Consultant Name: Jennifer Brown  
Texas Board of Professional Engineers Firm Registration Number: F-3407  
Contact Name: Jennifer Brown Title: Project Manager  
Mailing Address: 1901 Central Drive, Suite 550  
City: Bedford County: Tarrant State: TX Zip Code: 76021  
Phone Number: (817) 358-6130  
Email Address: [REDACTED]

**Agent in Service (required for out-of-state applicants)**

Name: \_\_\_\_\_  
Mailing Address: \_\_\_\_\_  
City: \_\_\_\_\_ County: \_\_\_\_\_ State: TX Zip Code: \_\_\_\_\_  
Phone Number: \_\_\_\_\_  
Email Address: \_\_\_\_\_

**12. Ownership Status of the Facility**

Is this a modification that changes the legal description, the property owner, or the Site Operator (Permittee or Registrant)?

Yes  No

If the answer is "No", skip this section.

Does the Site Operator (Permittee or Registrant) own all the facility units and all the facility property?

Yes  No

If "No", provide the following information for other owners.

Owner Name: \_\_\_\_\_  
Mailing Address: \_\_\_\_\_  
City: \_\_\_\_\_ County: \_\_\_\_\_ State: TX Zip Code: \_\_\_\_\_  
Phone Number: \_\_\_\_\_  
Email Address: \_\_\_\_\_


## Signature Page

### Site Operator or Authorized Signatory

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name: Juan Zamora Title: Director of Public Works

Email Address: zamora@uvaldetx.gov

Signature:  Date: 3-12-25

### Operator or Principal Executive Officer Designation of Authorized Signatory

*To be completed by the operator if the application is signed by an authorized representative for the operator.*

I hereby designate \_\_\_\_\_ as my representative and hereby authorize said representative to sign any application, submit additional information as may be requested by the Commission; and/or appear for me at any hearing or before the Texas Commission on Environmental Quality in conjunction with this request for a Texas Water Code or Texas Solid Waste Disposal Act permit. I further understand that I am responsible for the contents of this application, for oral statements given by my authorized representative in support of the application, and for compliance with the terms and conditions of any permit which might be issued based upon this application.

Operator or Principal Executive Officer Name: \_\_\_\_\_

Email Address: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

### Notary


SUBSCRIBED AND SWORN to before me by the said Juan Zamora

On this 12<sup>th</sup> day of March, 2025

My commission expires on the 30<sup>th</sup> day of June, 2027

LeeAnn m. Ortiz, 

Notary Public in and for  
Walde County, Texas



Note: Application Must Bear Signature and Seal of Notary Public

## Attachments for Permit or Registration Modification with Public Notice

Refer to instruction document **200650-instr** for professional engineer seal requirements.

### **Attachments Table 1. Required attachments.**

<b>Required Attachments</b>	<b>Attachment Number</b>
Land Ownership Map	B
Landowners List	B
Marked (Redline/Strikeout) Pages	C
Unmarked Revised Pages	D

### **Attachments Table 2. Additional attachments as applicable.**

<b>Additional Attachments as Applicable (select all that apply and add others as needed)</b>	<b>Attachment Number</b>
<input type="checkbox"/> TCEQ Core Data Form(s)	N/A
<input checked="" type="checkbox"/> Signatory Authority Delegation	A
<input checked="" type="checkbox"/> Fee Payment Receipt	A
<input type="checkbox"/> Confidential Documents	N/A

## Attachments for Permit or Registration Modification without Public Notice, or Temporary Authorization

Refer to instruction document **200650-instr** for professional engineer seal requirements.

### ***Attachments Table 3. Required attachments for modifications.***

<b>Required Attachments for Modification</b>	<b>Attachment Number</b>
Marked (Redline/Strikeout) Pages	N/A
Unmarked Revised Pages	N/A

### ***Attachments Table 4. Additional attachments for modifications and temporary authorizations, as applicable.***

<b>Additional Attachments as Applicable (select all that apply and add others as needed)</b>	<b>Attachment Number</b>
<input type="checkbox"/> TCEQ Core Data Form(s)	N/A
<input type="checkbox"/> Signatory Authority Delegation	N/A
<input type="checkbox"/> Fee Payment Receipt	N/A
<input type="checkbox"/> Confidential Documents	N/A

## Attachments for Permit or Registration Name Change or Transfer Modification

Refer to instruction document **200650-instr** for professional engineer seal requirements.

### **Attachments Table 5. Required attachments.**

<b>Required Attachments</b>	<b>Attachment Number</b>
TCEQ Core Data Form(s)	N/A
Property Legal Description	N/A
Property Metes and Bounds Description	N/A
Metes and Bounds Drawings	N/A
On-Site Easements Drawing	N/A
Land Ownership Map	N/A
Land Ownership List	N/A
Property Owner Affidavit	N/A
Verification of Legal Status	N/A
Evidence of Competency	N/A

### **Attachments Table 6. Additional attachments as applicable.**

<b>Additional Attachments as Applicable (select all that apply and add others as needed)</b>	<b>Attachment Number</b>
<input type="checkbox"/> Signatory Authority Delegation	N/A
<input type="checkbox"/> Fee Payment Receipt	N/A
<input type="checkbox"/> Confidential Documents	N/A
<input type="checkbox"/> Final Plat Record of Property	N/A
<input type="checkbox"/> Assumed Name Certificate	N/A



Your transaction is complete. Thank you for using TCEQ ePay.

**Note: It may take up to 3 working days for this electronic payment to be processed and be reflected in the TCEQ ePay system. Print this receipt and the vouchers for your records. An email receipt has also been sent.**

**Transaction Information**

**Trace Number:** 582EA000658903  
**Date:** 03/11/2025 03:26 PM  
**Payment Method:** CC - Authorization 0000053200  
**ePay Actor:** KRYSTAL L KUNTZ  
**Actor Email:** [REDACTED]  
**IP:** 99.48.161.145  
**TCEQ Amount:** \$150.00  
**Texas.gov Price:** \$153.63\*

\* This service is provided by Texas.gov, the official website of Texas. The price of this service includes funds that support the ongoing operations and enhancements of Texas.gov, which is provided by a third party in partnership with the State.

**Payment Contact Information**

**Name:** JENNIFER BROWN  
**Company:** SCS ENGINEERS  
**Address:** 1901 CENTRAL DRIVE SUITE 550, BEDFORD, TX 76021  
**Phone:** 817-798-0733

**Cart Items**

Click on the voucher number to see the voucher details.

Voucher	Fee Description	AR Number	Amount
<a href="#">757051</a>	NONHAZARDOUS WASTE PERMIT - MODIFICATIONS		\$100.00
<a href="#">757052</a>	30 TAC 305.53B HWP NOTIFICATION FEE		\$50.00
<b>TCEQ Amount:</b>			<b>\$150.00</b>



[ePay Again](#)

[Exit ePay](#)

**Note: It may take up to 3 working days for this electronic payment to be processed and be reflected in the TCEQ ePay system. Print this receipt for your records.**

**ATTACHMENT B**

**LANDOWNER'S MAP AND LIST**



**LEGEND**

- PROPERTY BOUNDARY
- . - . - . PERMIT BOUNDARY
- - - - - ADJACENT PROPERTY BOUNDARY
- 1/4 MILE RADIUS
- 96°55'30"--- LATITUDE/LONGITUDE LINES

**NOTES:**

1. (X) CORRESPONDS TO LANDOWNERS LISTED ON LANDOWNERS LIST.
2. PROPERTY OWNERS WITHIN 1/4 MILE OF THE PERMIT BOUNDARY ARE SHOWN.
3. LANDOWNER PROPERTY BOUNDARIES INDICATED ARE APPROXIMATE.

**LANDOWNER'S LIST**

- |  |   |
|--|---|
| <p>1. CITY OF UVALDE<br/>P.O. BOX 799<br/>UVALDE, TEXAS 78802-0799<br/>PROPERTY ID: 125012</p> <p>2. KESSLER HWY 90 RANCH LTD.<br/>200 EAST NOPAL ST., SUITE 200<br/>UVALDE, TEXAS 78801-5332<br/>PROPERTY ID: 18069</p> <p>3. EGBERT JIM GUY ET UX. HEATHER<br/>430 S. SANTA ROSA<br/>SAN ANTONIO, TEXAS 78207<br/>PROPERTY ID: 18071</p> <p>4. MIRASOL RANCH FAMILY LTD. PARTNERSHIP<br/>C/O DULLNIG ROBERT AND JEAN<br/>315 BURR ROAD<br/>SAN ANTONIO, TEXAS 78209<br/>PROPERTY ID: 20422</p> <p>5. JUAN MARTINEZ, JR. AND MARIA DAVILA<br/>1698 WINDMILL ROAD<br/>UVALDE, TEXAS 78801<br/>PROPERTY ID: 123452</p> <p>6. ROBERT M. DULLNIG<br/>315 BURR ROAD<br/>SAN ANTONIO, TEXAS 78209<br/>PROPERTY ID: 122946</p> | <p>7. FLYING W PROPERTIES LTD.<br/>P.O. BOX 2109<br/>SAN MARCOS, TEXAS 78667<br/>PROPERTY ID: 18233</p> <p>8. MINYARD INVESTMENTS LP<br/>1004 CEDAR PARK DRIVE<br/>CEDAR PARK, TEXAS 78613<br/>PROPERTY ID: 18294</p> <p>9. SORRELLS KENNETH D. JR.<br/>ET UX. LISA W<br/>102 OLD SAN ANTONIO ROAD<br/>BOERNE, TEXAS 78006<br/>PROPERTY ID: 117039</p> <p>10. SORRELLS KENNETH D. JR.<br/>102 OLD SAN ANTONIO ROAD<br/>BOERNE, TEXAS 78006<br/>PROPERTY ID: 18295</p> <p>11. FLYING W PROPERTIES LTD.<br/>P.O. BOX 2109<br/>SAN MARCOS, TEXAS 78667-2109<br/>PROPERTY ID: 18293</p> <p>12. FLYING W PROPERTIES LTD.<br/>P.O. BOX 2109<br/>SAN MARCOS, TEXAS 78667-2109<br/>PROPERTY ID: 18292</p> |
|--|---|

SOURCE: UVALDE COUNTY APPRAISAL DISTRICT-UVALDE CAD PROPERTY SEARCH  
LAST ACCESSED ON 01/10/2025. NO MINERAL INTEREST OWNERSHIP WAS  
IDENTIFIED ON THE UVALDE COUNTY APPRAISAL DISTRICT FOR THE LAND WHERE  
THE LANDFILL IS LOCATED.



*Jennifer R. Brown*  
03/12/25

3/11/2025 12:05 PM G:\UVALDE\16224057.DWG - TYPE I MAJOR PERMIT DWG\ATT 6\Phase\ELC\_1\_Landowners Map

DRAWING TITLE	LANDOWNERS MAP
PROJECT TITLE	CITY OF UVALDE LANDFILL PERMIT MODIFICATION
CLIENT	CITY OF UVALDE 3774 FM 481 UVALDE, TEXAS 78801
CONTRACT NO.	SCS ENGINEERS STEARN, CONRAD AND SCHMIDT CONSULTING ENGINEERS 1901 CENTRAL DRIVE, SUITE 550, BEDFORD, TX 76021 PH (817) 571-2288 FAX NO. (817) 571-2188
DATE	02/2025
SCALE	AS SHOWN
EXHIBIT	1

REV	DATE	DESCRIPTION

DRAWN BY: JLB  
CHK. BY: JRB  
APP. BY: RPK  
S/A R/W BY: JLB  
C/S R/W BY: JLB

TEXAS BOARD OF PROFESSIONAL ENGINEERS REG. NO. F-3407

**ATTACHMENT C**  
**MARKED VERSION**

**ATTACHMENT 14**  
**LANDFILL GAS MANAGEMENT PLAN**

**CITY OF UVALDE  
MUNICIPAL SOLID WASTE LANDFILL  
TCEQ PERMIT NO. 1725  
UVALDE, TEXAS**

**Prepared by**  
**~~Forbes Environmental~~**  
**~~EngineeringSCS Engineers~~**  
**Texas Board of Professional Engineers, Reg. No. F-3407**  
**Dallas/Fort Worth Office**  
**1901 Central Drive, Suite 550**  
**San Antonio Bedford, Texas**  
**7821676021**  
**817/571-2288**



*[Note: This Plan (LGMP #34) relies on information presented in previous LGMP completed and sealed by other engineers and approved by Texas Natural Resource Conservation Commission/Texas Commission on Environmental Quality and is accepted as presented, but ~~Forbes Environmental EngineeringSCS Engineers~~ cannot attest to its accuracy.]*

Version #~~3~~4  
(~~10/21/16~~03/12/25)  
~~Forbes Environmental EngrgSCS~~  
Engineers

**TABLE OF CONTENTS**

Page No.

<b>1.0</b>	<b>INTRODUCTION</b>	<b>1</b>
1.1	Site Description and Purpose	1
<b>2.0</b>	<b>LANDFILL GAS MONITORING PROGRAM</b>	<b>2</b>
2.1	Soil	2
2.2	Geology	2
2.2.1	Quaternary Alluvium	3
2.2.1.1	Uvalde Gravel	3
2.2.2	Anacacho Clay	3
2.2.3	Austin Chalk	3
2.2.4	Eagle Ford	4
2.2.5	Faults	4
2.3	Hydrogeology	4
2.4	Landfill Gas Monitoring Strata	4
2.5	Property Boundaries	5
2.6	Location of Easement and Underground Utilities	5
<b>3.0</b>	<b>LANDFILL METHANE GAS MONITORING PROGRAM</b>	<b>5</b>
3.1	Landfill Gas Monitoring System	6
3.2	GMP Design and Installation	7
3.2.1	Gas Probe Monitoring Procedures	7
3.2.2	Backup GMP	8
3.2.3	Maintenance Procedures	8
3.2.4	Backup Monitoring Plan	8
3.2.5	Recordkeeping	9
<b>4.0</b>	<b>EXCEEDANCE ACTION PLAN</b>	<b>9</b>
4.1	Remediation Plan	10
4.1.1	Passive Vents	11
4.1.2	Backup/Temporary Monitoring Probes	11
4.1.3	Gas Collection and Control System	12
<b>5.0</b>	<b>POST CLOSURE REQUIREMENTS</b>	<b>112</b>



**FIGURES AND TABLES**

<b>Figure 1.1</b>	<b>General Location Map</b>	<b>1214</b>
<b>Figure 1.2</b>	<del>Potential Offsite Residences</del> <u>Regulatory Distances</u>	<u>1315</u>
<del>Figure 1.3</del>	<del>Regulatory Distances</del>	<del>14</del>
<del>Figure 1.4</del>	<del>General Landfill Layout</del>	<del>15</del>
<b>Figure 2.1</b>	Predominant Soils at the Site	16
<b>Figure 2.2</b>	General Stratigraphic Column for the Site	17
<b>Figure 3.1</b>	Gas Monitoring <del>Probe (GMP)</del> <u>Features</u> Location <u>Map</u>	<u>18</u>
<b>Figure 3.2</b>	Typical GMP Design Details	19
<b>Figure 4.1</b>	Typical Gas Vent Design Details	20

**TABLES**

<b>Table 1.0 - Soil Table</b>	<u>21</u> <del>22</del>
<b>Table 2.0 - Gas Monitoring Probe Completion Details.</b>	<u>23</u>
<b>Table 3.0 - Gas Extraction Well/Vent Completion Details</b>	<u>24</u>



*Jennifer R. Brown* 03/12/25

**SCS Engineers**  
**TBPE Reg. # F-3407**

**APPENDICES**

**Appendix A – Methane Monitoring and Recording Form**

**Appendix B – Landfill Gas Remediation Plans**

**Appendix C – Vertical Extraction Vents/Wells**



**SCS Engineers  
TBPE Reg. # F-3407**

**LANDFILL GAS MANAGEMENT PLAN**  
**City of Uvalde Municipal Solid Waste Landfill**  
**TCEQ Permit No.1725**  
**Uvalde, Texas**

## **1.0 INTRODUCTION**

The purpose of this Landfill Gas Monitoring Plan (LGMP) Version #3 is to provide guidelines for the management of the landfill gas at the City of Uvalde Municipal Solid Waste Landfill (MSWLF) in accordance with Subchapter I (Landfill Gas Management) 30 TAC §330.371 and to update LGMP Version #2 requirements per §330.371(g). Specific relevant TAC chapters and sections are cited in brackets, subchapters and paragraphs are not included, except when specific reference may help confirm or clarify change. All figures are included at the end of text.

### **1.1 Site Description**

The Uvalde MSWLF is located in Uvalde County approximately 3.8 miles southwest of the City Uvalde and 3.3 miles of the intersection of U.S. Highway 90 and Texas F.M. 481. Figure 1.1 shows general location of the Site. The predominant land use in the vicinity of and adjacent to the Site is undeveloped rangeland used for grazing cattle. There reportedly 6 habitable building located within 3,000 feet of the facility waste placement boundary, but they are not located within a 1,000 feet radius of the waste boundary. See Figure 1.2 and 1.3. Figure 1.4.1 shows the Site Layout.

The landfill development plan calls for three Stages (A, B, C) of development. Stage A was completed before Subtitle D design regulations came into effect and was completed to a greater depth than Stages B or C (i.e. nominally 917msl to 935msl respectively with respect to bottom of buried waste). This LGMP applies for all landfill Stages during final phase of landfill operation.

For purposes of clarity, this LGMP specifically addresses regulated activities within the facility boundary (permitted area). The MSWLF *facility boundary* is defined "by the legal description in the permit" per §330.371(b)(2), that is considered to herein analogous "*permitted area*". This

includes regulated activity and facilities (landfill, ground water monitor wells and gas probes, leachate tank etc.) located within the 57.50 acre permitted area defined by the permit facility boundary. The legal description of the permitted area is found in the original approved permit and shown in Figure [1.43.1](#).

## **2.0 LANDFILL GAS MONITORING PROGRAM {§330.371(b)}**

The method and frequency of landfill gas monitoring is based on site-specific physical conditions in accordance with reference regulations. These conditions are discussed at length in the Permit *Geology Report* located in Section 4.0 of the Permit Site Development Plan, and summarized below as relates to the LGMP, which provides the basis for determining the monitoring program criteria {§330.371(b)(1)}.

### **2.1 Soil**

The soils identified at the Site are shown in Figure 2.1. The predominant soils are HYD and KnA, which make-up the upper stratum overlaying geologic Quaternary Alluvium formation discussed below. The soil characteristics are summarized in Table 1.0. The general depth of the soils ranges from 0-60" based on drilling log.

### **2.2 Site Geology**

The principal formations at the Site from youngest to oldest are:

- Quaternary Alluvium (Qtu) which includes Uvalde Gravel
- Anacacho (Kac)
- Austin Chalk (Kau- which contains the permit designated uppermost aquifer)
- Eagle Ford (Kef).

Stage A portion of the landfill is completed in Anacacho Clay, which would most likely serve as barrier to migration.

Based on these conditions, it was determined that the maximum spacing between permanent gas monitoring probes (GMP) placed around the landfill perimeter should be no greater than 1000 feet apart and completed to depths equivalent to the depth of waste buried in the vicinity of the nearest gas monitoring probes (GMP), with casing screen and sand filter of sufficient height to capture gas from highest level of waste and still allow an adequate annulus seal at surface.

## **2.5 Facility Boundaries (Permitted Area)**

The Site and facility boundaries were discussed earlier in Section 1.1 and shown in Figure 1.4. No building structures are located within the facility boundary. Two buildings are located within the Site boundary outside the permitted area, as shown in figure. One building is the small landfill gate/scale house and the other is the landfill maintenance/operations office building. The buildings are located outside the permitted area and are not considered likely to be exposed to gases released from the landfill. However, they are included in the quarterly monitoring program, and gas monitoring of these structures may be conducted using portable gas monitoring detectors in accordance with [the Exceedance Action Plan](#), EAP (Section 4.0), when and if gas exceedances are reported in GMP within 1,000-ft of buildings.

## **2.6 Location of Easement and Underground Utilities**

There are no easements, buildings, subsurface vaults, utilities, or other areas where methane gas buildup would be a concern within the area bounded by the approved landfill gas monitoring system.

## **3.0 LANDFILL METHANE GAS MONITORING PROGRAM {§330.371(b)}**

A routine methane gas-monitoring program has been implemented as required to ensure that the following standards are met:

- (1) The concentration of methane gas generated by the facility does not exceed 1.25% by volume in the facility structures located within facility boundary, excluding gas control or recovery components (§330.371(a)(1)); and
- (2) The concentration of methane gas does not exceed 5% by volume in monitoring points, probes, subsurface soils, or other matrices at the facility boundary as defined by the legal description in the permit (§330.371 (a)(2)).

The monitoring network design also includes provisions for monitoring facility structures (i.e. buildings, subsurface vaults, utilities) or any other areas within the permitted area that would be of concern per §330.371(i). *While both ancillary structures are not located within the facility boundary, they are included in the quarterly gas monitoring program with the GMP, and will be measured in accordance with the Exceedance Action Plan (EAP) discussed in Section 4.0.*

### **3.1 Landfill Gas Monitoring System §330.371(g)(2)**

The existing permanent gas monitoring probe system includes GMP-1 through GMP-7, ~~which were installed in accordance with the previous LGMP #2, approved by the TNRCC (currently the TCEQ) and accepted accordingly~~ see Table 2.0, Gas Monitoring Probe Completion Details. These GMP comprise the landfill gas monitoring points to be monitored on a quarterly basis. GMP Design and installation criteria are discussed in Section 3.1.1.

Figure 3.1 shows the location of current Landfill Gas Monitoring facilities within the permitted area. Based on the site-specific physical conditions discussed in Section 2, *gas-monitoring probes will be placed around the landfill perimeters at distances not to exceed 1,000-ft.*

While additional GMP or increased monitoring frequency is not anticipated, they could become necessary as part of the EAP, should methane gas exceedances occur in the future. These GMP will be completed in accordance with the Methane Gas Monitoring Probe Design Details as shown in Figure 3.2 and summarized in the following section. If additional permanent GMPs or other gas management features are installed, the LGMP will be modified accordingly to document and incorporate the changes with the TCEQ concurrence per the EAP.

### 3.2 GMP Design and Installation {16TAC§76}

At a minimum, the GMP will be designed to meet the applicable governing rules for monitoring wells (16TAC§76) as applied to gas monitoring probes. See Figure 2.4. The landfill GMP should be installed to the maximum depth of the buried waste in the vicinity of the probe and screened from the bottom cap to a few feet below the surface to allow sufficient room to construct surface completion. Surface completion should meet no less than the minimum surface completion requirements per 16TAC§76.1 00(f)(4), such as waterproof protective collar or vault extending 2" above the surface with a minimum 12" radius (or 2x2-ft) sloping cement sloping pad. The casing should be capped with locking cap such as expandable compression plug or equivalent to seal casing between monitoring events and allow access for taking measurements. Where GMP are located in areas of heavy traffic or site activity, one to three 4"-bollard posts will be placed around the GMP to protect it from damage.

#### 3.2.1 Gas Probe Monitoring Procedures

Monitoring the GMP system consists of measuring methane gas in each of the probes conducted by or under the supervision of a qualified and trained landfill operator to ensure methane limits and concentrations are not exceeded as follows:

- Monitoring of the GMP system, ~~and~~ the Gate House, and Maintenance building will be conducted on a quarterly basis, unless monitoring landfill gas exceedance has occurred as discussed in the EAP (Section 4.0).
- Methane gas will be measured in each GMP (GMP 1 through 7) and structures *using industry standard portable methane gas detectors, such as or equivalent to ENMET CGS-90R or Gas Measurement Instruments, GasSurveyor 6, et.al.:*
  - o Monitoring equipment will be calibrated in accordance with manufacturer's instructions, prior to each monitoring event.

- Methane concentrations as % volume will be measured and recorded at each GMP on the Methane Monitoring and Recording Form (Appendix C) or similar form.
- Probe condition will be visually inspected and recorded.
  - Gas monitoring recordkeeping will be maintained per Section 3.2.5.

- **Exceedance Action Plan will be initiated when gas-monitoring readings confirm that methane gas concentrations > 5% volume are recorded at facility boundary.** See Section 3.0.

### 3.2.2 Backup GMP (BGMP)

As discussed in the Exceedance Action Plan (EAP-Section 4.0), probes installed to assess gas migration serve as backup-GMP (BGMP). They are located relative to the location of a reported exceedance and are not monitored unless an exceedance has occurred. Figure 3.1 shows the location of current Landfill Gas Monitoring facilities within (GMP/BGMP). Gas monitoring probe design and installation criteria are discussed in Section 3.2.

### 3.2.3 Maintenance Procedures

The permanent GMP system will be inspected on a quarterly basis during regularly scheduled monitoring events. Each probe and vent will be inspected for damage to protective barrier, casing, cap, working pad, and covers. The general maintenance conditions will be noted in the field sampling record and all damage will be repaired as soon as practical and duly recorded. Major damage to monitoring system will be reported and appropriate authorities notified in accordance with following section.

### 3.2.4 Backup Monitoring Plan

The purpose of this Backup Plan is to provide a plan of action in the event that the main monitoring system breaks down or it becomes ineffective in accordance to §330.371(g)(3).

In the event a gas monitoring probe/vent failure has been damaged and is inoperative, they will be repaired or replaced within 60 days of discovery. Upon completion of a replacement GMP/vent, an installation report including boring logs and/or construction details will be maintained in the landfill Site Operating Record. A permit modification will be submitted to the TCEQ within 60 days of noticing the failure GMP/vent replacement if located more than 100 feet from initial location, in accordance with applicable regulations.

landfill gas migration. Copies of the action plan will be placed in the operating record and sent to the TCEQ. The following subsections summarize the remediation efforts at the landfill, including installation of passive vents, backup/temporary monitoring probes and gas collection and control systems.

#### 4.1.1 Passive Vents

[2004 LFG Vents in waste] To control LFG migration at GMP-1 and GMP-3 four passive gas monitoring vents (GMV-1 through GMV-4 as shown on Figure 2.0 of Appendix B, Remediation Plan (05/08/18)) were installed in Stage A to release pressure in the storage cells, see Table 3.0 for gas extraction well/vent completion information.

[2010 LFG Vents in waste] Two additional vents (one in Stage A and one in Stage B) were installed to control LFG migration at GMP-4. GMV-5 and GMV-6 are shown on Figure 2.0 of Appendix B, Remediation Plan (05/08/18).

[2018 Temporary LFG Vents outside waste] To continue with remediation efforts, three additional vents were installed as part of Phase 1.0 of the Remediation Plan submitted to TCEQ dated May 5, 2018, included in Appendix B. Temporary vents TV-1, TV-2 and TV-3 are shown on Figure 3.0 of the 2018 Remediation Plan.

[2018 LFG vents in waste] To continue with remediation efforts, five additional vents were installed as part of Phase 2.0 of the Remediation Plan dated May 5, 2018. The gas vents are shown as GV-7, GV-7a, GV-8, GV-9 and GV-10 on Figure 1.0 in Appendix B, Remediation Plan Update (01/17/22).

#### 4.1.2 Backup/Temporary Monitoring Probes

[2010 Backup Monitoring Probes] Four backup gas monitoring probes were installed in the vicinity of GMP-4, designated as BGMP-4.1, 4.2, 4.3 & 4.4, as shown in Figure 2.0 of Appendix B, Remediation Plan (05/08/18), to identify the gas migration path.

[2018 Temporary Gas Monitoring Probes] To continue the identification of the landfill gas migration path, five temporary gas monitoring probes were installed at various depths along the north property line outside the Stage B limits of waste. Figure 3.0 of

Appendix B, Remediation Plan (05/08/18) depicts the locations of TGMP-1, TGMP-2 and TGMP-3.1, 3.2, 3.3.

#### 4.1.3 Gas Collection and Control System

[2023 Vertical LFG Extraction Wells] In order to reduce gas emissions and further minimize the potential for offsite migration, an initial landfill gas collection system (GCS) was installed as shown on Drawing 1 of Appendix B, Remediation plan (09/02/22). The initial GCS included installing four vertical LFG extraction wells connected by lateral piping and routed to localized blowers and solar vent flares.


### **5.0 POST CLOSURE REQUIREMENTS {§330.371(e)&(f)}**

This LGMP or its future approved renditions will be in place for a period of 30 years after certification of final closure of the facility. A reduction in the monitoring and control period may be approved by the TCEQ or its predecessors upon demonstration that there is no potential for gas migration beyond the property boundary or on-site structures.


Post-closure land use at the Site should not interfere with the gas monitoring and control systems and underground utilities trenches crossing the landfill boundary should be vented and monitored regularly.

**FIGURES**






Source: USGS Uvalde Quadrangle  
7.5 Minute Series




FORBES ENVIRONMENTAL ENGINEERING  
USGS SITE LOCATION MAP  
CITY OF UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 1.1





NOTE: 1,000 Ft. measured from waste placement boundary.



FORBES ENVIRONMENTAL ENGINEERING

POTENTIAL OFFSITE RESIDENCES  
UVALDE LANDFILL  
UVALDE, TEXAS


FIGURE 1.2



**LEGEND**

	PROPERTY BOUNDARY
	PERMIT BOUNDARY
	PERMITTED AREA
	LIMITS OF WASTE
	LIMITS OF WASTE RADIAL MARKER
	LATITUDE/LONGITUDE LINES

**NOTE:**  
 1. AERIAL SHOWN WAS SOURCED FROM THE GOOGLE EARTH DATED JUNE 21, 2023.



**INSET**  
 1" = 200'

3/11/2025 12:05 PM G:\UVALDE\16224057.00 - TYPE 1 MAJOR PERMIT DWG\ATT 6\Plan\1.2 Regulatory Distances Map

REV	DATE	DESCRIPTION	BY								
DRAWING TITLE		<b>REGULATORY DISTANCES</b>									
PROJECT TITLE		<b>CITY OF UVALDE LANDFILL PERMIT MODIFICATION</b>									
CLIENT		<b>CITY OF UVALDE 3774 FM 481 UVALDE, TEXAS 78801</b>									
SCS ENGINEERS STEARNS, CONRAD AND SCHMIDT CONSULTING ENGINEERS 1901 CENTRAL DRIVE, SUITE 550, BEDFORD, TX 76021 PH (817) 571-2288 FAX NO. (817) 571-2188		<table border="1"> <tr> <td>PROJ. NO.</td> <td>DWN. BY: JJJ</td> <td>CHECKED BY: JRB</td> <td>APP. BY: PRK</td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>		PROJ. NO.	DWN. BY: JJJ	CHECKED BY: JRB	APP. BY: PRK				
PROJ. NO.	DWN. BY: JJJ	CHECKED BY: JRB	APP. BY: PRK								
CADD FILE: 1.2 REGULATORY DISTANCES MAP		DATE: 02/2025									
SCALE: AS SHOWN		FIGURE: <b>1.2</b>									
TEXAS BOARD OF PROFESSIONAL ENGINEERS REG. NO. F-3407											







FIGURE 1.3



PROPERTY BOUNDARY

LEGEND:

- Monitor Wells (MW)
- ⊕ Gas Monitoring Probes (GMP)
- Gas Vents (GV)
- Backup Gas Monitoring Probes (BGMP)




FORBES ENVIRONMENTAL ENGINEERING

GENERAL LANDFILL FACILITY LAYOUT  
UVALDE LANDFILL  
UVALDE, TEXAS



FIGURE 1.4





**LEGEND:**

- Monitor Wells (MW)
- ⊕ Gas Monitoring Probes (GMP)
- Gas Vents (GV)
- Backup Gas Monitoring Probes (BGMP)



FORBES ENVIRONMENTAL ENGINEERING

GMP & GV LOCATION MAP  
UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 3.1

|

**TABLES**

Table 1.0 MSWLF Soils Map Adapted from Uvalde County, Texas (Source: Natural Resource Conservation Service)						
Hindes&Yolgo soils, undulating (HYB)						
Map Unit Characteristics	Hindes	Yolgo	Knippa (KnA)	MoA Montell Clay	OLB Olmos	UvA Uvalde Clay
Acres/% in Area of Interest (AOI)	70.7ac/56.5%		7ac/5.6%	16.1ac/12.9%	26.9ac/21.5%	1.4ac/2.4%
Parent material	Gravelly, loamy alluvium	NR	Calcareous clayey alluvium	Calcareous clayey alluvium	Calcareous loamy alluvium	Calcareous alluvium
Typical profile						
H1 or Ap/A	O-8 inches gravelly sandy clay loam	0- 5" gravelly loam	H1 - 0 to 18 inches: clay	Ap - 0 to 8 inches: clay	H1 - 0 to 13 inches: very gravelly loam	A - 0 to 17 inches: clay loam
H2 or Bnss	8-31 very gravelly clay	5-12" very gravelly clay loam	H2 - 18 to 35 inches: clay	Bnss - 8 to 32 inches: clay	H2 - 13 to 14 inches: cemented material	Bk1 - 17 to 34 inches: clay loam
H3 or Bknss	21-60 clay loam	12-14" Cemented material	H3 - 35 to 60 inches: clay loam	Bknss - 32 to 58 inches: clay	H3 - 14 to 26 inches: very gravelly loam	Bk2 - 34 to 50 inches: clay loam
H4 or Bkny	Not reported	H4: 14 to 16"	Not reported	Bkny: 58 to 80 inches: clay	H4 - 26 to 60 inches: gravelly loam	Bk3 - 50 to 80 inches: silty clay loam
Properties and qualities						
Slope: 1 to 8 percent	1-8 %	1-8%	0-1%	0-1%	1-8%	0-1%
Depth to restrictive feature	>80 inches	>80"	>80"	>80"	10 to 20" to petrocalcic	>80"
Runoff Class	NR	NR	NR	High	High	Low
Natural drainage class	Well drained	well drained	well drained	Moderately well drained	Well drained	Well Drained
Capacity to transmit water (Ksat)	Moderately high	Mod low to Mod High	Moderately high	Mod low to Mod High	Very low	Mod High to high
Available water storage in profile	Low	very low	High	Moderate		
Interpretive groups						
Hydrologic Soil Group:	C	D	C	D	D	C
Hydric soil	No	No	No	no	No	No

NR= not rated

**ATTACHMENT D**  
**UNMARKED VERSION**

**ATTACHMENT 14  
LANDFILL GAS MANAGEMENT PLAN**

**CITY OF UVALDE  
MUNICIPAL SOLID WASTE LANDFILL  
TCEQ PERMIT NO. 1725  
UVALDE, TEXAS**

**Prepared by  
SCS Engineers  
Texas Board of Professional Engineers, Reg. No. F-3407  
Dallas/Fort Worth Office  
1901 Central Drive, Suite 550  
Bedford, Texas 76021  
817/571-2288**



*[Note: This Plan (LGMP #4) relies on information presented in previous LGMP completed and sealed by other engineers and approved by Texas Natural Resource Conservation Commission/Texas Commission on Environmental Quality and is accepted as presented, but SCS Engineers cannot attest to its accuracy.]*

Version #4 (03/12/25)  
SCS Engineers

**TABLE OF CONTENTS**

Page No.

<b>1.0</b>	<b>INTRODUCTION</b>	.	.	<b>1</b>
1.1	Site Description and Purpose	.	.	1
<b>2.0</b>	<b>LANDFILL GAS MONITORING PROGRAM</b>	.	.	<b>2</b>
2.1	Soil	.	.	2
2.2	Geology	.	.	2
2.2.1	Quaternary Alluvium	.	.	3
2.2.1.1	Uvalde Gravel	.	.	3
2.2.2	Anacacho Clay	.	.	3
2.2.3	Austin Chalk	.	.	3
2.2.4	Eagle Ford	.	.	4
2.2.5	Faults	.	.	4
2.3	Hydrogeology	.	.	4
2.4	Landfill Gas Monitoring Strata	.	.	4
2.5	Property Boundaries	.	.	5
2.6	Location of Easement and Underground Utilities	.	.	5
<b>3.0</b>	<b>LANDFILL METHANE GAS MONITORING PROGRAM</b>	.	.	<b>5</b>
3.1	Landfill Gas Monitoring System	.	.	6
3.2	GMP Design and Installation	.	.	7
3.2.1	Gas Probe Monitoring Procedures	.	.	7
3.2.2	Backup GMP	.	.	8
3.2.3	Maintenance Procedures	.	.	8
3.2.4	Backup Monitoring Plan	.	.	8
3.2.5	Recordkeeping	.	.	9
<b>4.0</b>	<b>EXCEEDANCE ACTION PLAN</b>	.	.	<b>9</b>
4.1	Remediation Plan	.	.	10
4.1.1	Passive Vents	.	.	11
4.1.2	Backup/Temporary Monitoring Probes	.	.	11
4.1.3	Gas Collection and Control System	.	.	12
<b>5.0</b>	<b>POST CLOSURE REQUIREMENTS</b>	.	.	<b>12</b>



**FIGURES**

<b>Figure 1.1</b>	General Location Map	.	.	14
<b>Figure 1.2</b>	Regulatory Distances	.	.	15
<b>Figure 2.1</b>	Predominant Soils at the Site	.	.	16
<b>Figure 2.2</b>	General Stratigraphic Column for the Site	.	.	17
<b>Figure 3.1</b>	Gas Monitoring Features Location Map.	.	.	18
<b>Figure 3.2</b>	Typical GMP Design Details	.	.	19
<b>Figure 4.1</b>	Typical Gas Vent Design Details	.	.	20

**TABLES**

<b>Table 1.0</b>	Soil Table	.	.	22
<b>Table 2.0</b>	Gas Monitoring Probe Completion Details.	.	.	23
<b>Table 3.0</b>	Gas Extraction Well/Vent Completion Details	.	.	24

## APPENDICES

**Appendix A – Methane Monitoring and Recording Form**

**Appendix B – Landfill Gas Remediation Plans**

**Appendix C – Vertical Extraction Vents/Wells**



**SCS Engineers  
TBPE Reg. # F-3407**

**LANDFILL GAS MANAGEMENT PLAN**  
**City of Uvalde Municipal Solid Waste Landfill**  
**TCEQ Permit No.1725**  
**Uvalde, Texas**

**1.0 INTRODUCTION**

The purpose of this Landfill Gas Monitoring Plan (LGMP) Version #3 is to provide guidelines for the management of the landfill gas at the City of Uvalde Municipal Solid Waste Landfill (MSWLF) in accordance with Subchapter I (Landfill Gas Management) 30 TAC §330.371 and to update LGMP Version #2 requirements per §330.371(g). Specific relevant TAC chapters and sections are cited in brackets, subchapters and paragraphs are not included, except when specific reference may help confirm or clarify change. All figures are included at the end of text.

**1.1 Site Description**

The Uvalde MSWLF is located in Uvalde County approximately 3.8 miles southwest of the City Uvalde and 3.3 miles of the intersection of U.S. Highway 90 and Texas F.M. 481. Figure 1.1 shows general location of the Site. The predominant land use in the vicinity of and adjacent to the Site is undeveloped rangeland used for grazing cattle. There reportedly 6 habitable building located within 3,000 feet of the facility waste placement boundary, but they are not located within a 1,000 feet radius of the waste boundary, see Figure 1.2. Figure 3.1 shows the Site Layout.

The landfill development plan calls for three Stages (A, B, C) of development. Stage A was completed before Subtitle D design regulations came into effect and was completed to a greater depth than Stages B or C (i.e. nominally 917msl to 935msl respectively with respect to bottom of buried waste). This LGMP applies for all landfill Stages during final phase of landfill operation.

For purposes of clarity, this LGMP specifically addresses regulated activities within the facility boundary (permitted area). The MSWLF *facility boundary* is defined "*by the legal description in the permit*" per §330.371(b)(2), that is considered to herein analogous "*permitted area*". This

includes regulated activity and facilities (landfill, ground water monitor wells and gas probes, leachate tank etc.) located within the 57.50 acre permitted area defined by the permit facility boundary. The legal description of the permitted area is found in the original approved permit and shown in Figure 3.1.

## **2.0 LANDFILL GAS MONITORING PROGRAM {§330.371(b)}**

The method and frequency of landfill gas monitoring is based on site-specific physical conditions in accordance with reference regulations. These conditions are discussed at length in the Permit *Geology Report* located in Section 4.0 of the Permit Site Development Plan, and summarized below as relates to the LGMP, which provides the basis for determining the monitoring program criteria {§330.371(b)(1)}.

### **2.1 Soil**

The soils identified at the Site are shown in Figure 2.1. The predominant soils are HYD and KnA, which make-up the upper stratum overlaying geologic Quaternary Alluvium formation discussed below. The soil characteristics are summarized in Table 1.0. The general depth of the soils ranges from 0-60" based on drilling log.

### **2.2 Site Geology**

The principal formations at the Site from youngest to oldest are:

- Quaternary Alluvium (Qtu) which includes Uvalde Gravel
- Anacacho (Kac)
- Austin Chalk (Kau- which contains the permit designated uppermost aquifer)
- Eagle Ford (Kef).

Stage A portion of the landfill is completed in Anacacho Clay, which would most likely serve as barrier to migration.

Based on these conditions, it was determined that the maximum spacing between permanent gas monitoring probes (GMP) placed around the landfill perimeter should be no greater than 1000 feet apart and completed to depths equivalent to the depth of waste buried in the vicinity of the nearest gas monitoring probes (GMP), with casing screen and sand filter of sufficient height to capture gas from highest level of waste and still allow an adequate annulus seal at surface.

## **2.5 Facility Boundaries (Permitted Area)**

The Site and facility boundaries were discussed earlier in Section 1.1 and shown in Figure 1.4. No building structures are located within the facility boundary. Two buildings are located within the Site boundary outside the permitted area, as shown in figure. One building is the small landfill gate/scale house and the other is the landfill maintenance/operations office building. The buildings are located outside the permitted area and are not considered likely to be exposed to gases released from the landfill. However, they are included in the quarterly monitoring program, and gas monitoring of these structures may be conducted using portable gas monitoring detectors in accordance with the Exceedance Action Plan, EAP (Section 4.0), when and if gas exceedances are reported in GMP within 1,000-ft of buildings.

## **2.6 Location of Easement and Underground Utilities**

There are no easements, buildings, subsurface vaults, utilities, or other areas where methane gas buildup would be a concern within the area bounded by the approved landfill gas monitoring system.

## **3.0 LANDFILL METHANE GAS MONITORING PROGRAM** {§330.371(b)}

A routine methane gas-monitoring program has been implemented as required to ensure that the following standards are met:

- (1) The concentration of methane gas generated by the facility does not exceed 1.25% by volume in the facility structures located within facility boundary, excluding gas control or recovery components (§330.371(a)(1)); and
- (2) The concentration of methane gas does not exceed 5% by volume in monitoring points, probes, subsurface soils, or other matrices at the facility boundary as defined by the legal description in the permit (§330.371 (a)(2)).

The monitoring network design also includes provisions for monitoring facility structures (i.e. buildings, subsurface vaults, utilities) or any other areas within the permitted area that would be of concern per §330.371(i). *While both ancillary structures are not located within the facility boundary, they are included in the quarterly gas monitoring program with the GMP, and will be measured in accordance with the Exceedance Action Plan (EAP) discussed in Section 4.0.*

### **3.1 Landfill Gas Monitoring System §330.371(g)(2)**

The existing permanent gas monitoring probe system includes GMP-1 through GMP-7, see Table 2.0, Gas Monitoring Probe Completion Details. These GMP comprise the landfill gas monitoring points to be monitored on a quarterly basis. GMP Design and installation criteria are discussed in Section 3.1.1.

Figure 3.1 shows the location of current Landfill Gas Monitoring facilities within the permitted area. Based on the site-specific physical conditions discussed in Section 2, *gas-monitoring probes will be placed around the landfill perimeters at distances not to exceed 1,000-ft.*

While additional GMP or increased monitoring frequency is not anticipated, they could become necessary as part of the EAP, should methane gas exceedances occur in the future. These GMP will be completed in accordance with the Methane Gas Monitoring Probe Design Details as shown in Figure 3.2 and summarized in the following section. If additional permanent GMPs or other gas management features are installed, the LGMP will be modified accordingly to document and incorporate the changes with the TCEQ concurrence per the EAP.

### **3.2 GMP Design and Installation {16TAC§76}**

At a minimum, the GMP will be designed to meet the applicable governing rules for monitoring wells (16TAC§76) as applied to gas monitoring probes. See Figure 2.4. The landfill GMP should be installed to the maximum depth of the buried waste in the vicinity of the probe and screened from the bottom cap to a few feet below the surface to allow sufficient room to construct surface completion. Surface completion should meet no less than the minimum surface completion requirements per 16TAC§76.1 00(f)(4), such as waterproof protective collar or vault extending 2" above the surface with a minimum 12" radius (or 2x2-ft) sloping cement sloping pad. The casing should be capped with locking cap such as expandable compression plug or equivalent to seal casing between monitoring events and allow access for taking measurements. Where GMP are located in areas of heavy traffic or site activity, one to three 4"-bollard posts will be placed around the GMP to protect it from damage.

#### **3.2.1 Gas Probe Monitoring Procedures**

Monitoring the GMP system consists of measuring methane gas in each of the probes conducted by or under the supervision of a qualified and trained landfill operator to ensure methane limits and concentrations are not exceeded as follows:

- Monitoring of the GMP system, the Gate House, and Maintenance building will be conducted on a quarterly basis, unless monitoring landfill gas exceedance has occurred as discussed in the EAP (Section 4.0).
- Methane gas will be measured in each GMP (GMP 1 through 7) and structures *using industry standard portable methane gas detectors, such as or equivalent to ENMET CGS-90R or Gas Measurement Instruments, GasSurveyor 6, et.al.:*
  - o Monitoring equipment will be calibrated in accordance with manufacturer's instructions, prior to each monitoring event.

- Methane concentrations as % volume will be measured and recorded at each GMP on the Methane Monitoring and Recording Form (Appendix C) or similar form.
- Probe condition will be visually inspected and recorded.
  - Gas monitoring recordkeeping will be maintained per Section 3.2.5.

- **Exceedance Action Plan will be initiated when gas-monitoring readings confirm that methane gas concentrations > 5% volume are recorded at facility boundary.** See Section 3.0.

### 3.2.2 Backup GMP (BGMP)

As discussed in the Exceedance Action Plan (EAP-Section 4.0), probes installed to assess gas migration serve as backup-GMP (BGMP). They are located relative to the location of a reported exceedance and are not monitored unless an exceedance has occurred. Figure 3.1 shows the location of current Landfill Gas Monitoring facilities within (GMP/BGMP). Gas monitoring probe design and installation criteria are discussed in Section 3.2.

### 3.2.3 Maintenance Procedures

The permanent GMP system will be inspected on a quarterly basis during regularly scheduled monitoring events. Each probe and vent will be inspected for damage to protective barrier, casing, cap, working pad, and covers. The general maintenance conditions will be noted in the field sampling record and all damage will be repaired as soon as practical and duly recorded. Major damage to monitoring system will be reported and appropriate authorities notified in accordance with following section.

### 3.2.4 Backup Monitoring Plan

The purpose of this Backup Plan is to provide a plan of action in the event that the main monitoring system breaks down or it becomes ineffective in accordance to §330.371(g)(3).

In the event a gas monitoring probe/vent failure has been damaged and is inoperative, they will be repaired or replaced within 60 days of discovery. Upon completion of a replacement GMP/vent, an installation report including boring logs and/or construction details will be maintained in the landfill Site Operating Record. A permit modification will be submitted to the TCEQ within 60 days of GMP/vent replacement if located more than 100 feet from initial location, in accordance with applicable regulations.

landfill gas migration. Copies of the action plan will be placed in the operating record and sent to the TCEQ. The following subsections summarize the remediation efforts at the landfill, including installation of passive vents, backup/temporary monitoring probes and gas collection and control systems.

#### 4.1.1 Passive Vents

[2004 LFG Vents in waste] To control LFG migration at GMP-1 and GMP-3 four passive gas monitoring vents (GMV-1 through GMV-4 as shown on Figure 2.0 of Appendix B, Remediation Plan (05/08/18)) were installed in Stage A to release pressure in the storage cells, see Table 3.0 for gas extraction well/vent completion information.

[2010 LFG Vents in waste] Two additional vents (one in Stage A and one in Stage B) were installed to control LFG migration at GMP-4. GMV-5 and GMV-6 are shown on Figure 2.0 of Appendix B, Remediation Plan (05/08/18).

[2018 Temporary LFG Vents outside waste] To continue with remediation efforts, three additional vents were installed as part of Phase 1.0 of the Remediation Plan submitted to TCEQ dated May 5, 2018, included in Appendix B. Temporary vents TV-1, TV-2 and TV-3 are shown on Figure 3.0 of the 2018 Remediation Plan.

[2018 LFG vents in waste] To continue with remediation efforts, five additional vents were installed as part of Phase 2.0 of the Remediation Plan dated May 5, 2018. The gas vents are shown as GV-7, GV-7a, GV-8, GV-9 and GV-10 on Figure 1.0 in Appendix B, Remediation Plan Update (01/17/22).

#### 4.1.2 Backup/Temporary Monitoring Probes

[2010 Backup Monitoring Probes] Four backup gas monitoring probes were installed in the vicinity of GMP-4, designated as BGMP-4.1, 4.2, 4.3 & 4.4, as shown in Figure 2.0 of Appendix B, Remediation Plan (05/08/18), to identify the gas migration path.

[2018 Temporary Gas Monitoring Probes] To continue the identification of the landfill gas migration path, five temporary gas monitoring probes were installed at various depths along the north property line outside the Stage B limits of waste. Figure 3.0 of

Appendix B, Remediation Plan (05/08/18) depicts the locations of TGMP-1, TGMP-2 and TGMP-3.1, 3.2, 3.3.

#### 4.1.3 Gas Collection and Control System

[2023 Vertical LFG Extraction Wells] In order to reduce gas emissions and further minimize the potential for offsite migration, an initial landfill gas collection system (GCS) was installed as shown on Drawing 1 of Appendix B, Remediation plan (09/02/22). The initial GCS included installing four vertical LFG extraction wells connected by lateral piping and routed to localized blowers and solar vent flares.

### **5.0 POST CLOSURE REQUIREMENTS** §§330.371(e)&(f)


This LGMP or its future approved renditions will be in place for a period of 30 years after certification of final closure of the facility. A reduction in the monitoring and control period may be approved by the TCEQ or its predecessors upon demonstration that there is no potential for gas migration beyond the property boundary or on-site structures.

Post-closure land use at the Site should not interfere with the gas monitoring and control systems and underground utilities trenches crossing the landfill boundary should be vented and monitored regularly.

## **FIGURES**



3/17/2025 12:05 PM G:\UVALDE\16224057.00 - TYPE 1 MAJOR PERMIT DWG\1.2 Regulatory Distances Map




0 500 1000  
SCALE IN FEET

**LEGEND**

	PROPERTY BOUNDARY
	PERMIT BOUNDARY
	PERMITTED AREA
	LIMITS OF WASTE
	LIMITS OF WASTE RADIAL MARKER
	LATITUDE/LONGITUDE LINES

**NOTE:**

1. AERIAL SHOWN WAS SOURCED FROM THE GOOGLE EARTH DATED JUNE 21, 2023.



**INSET**  
1" = 200'

REV	DATE	DESCRIPTION	BY

<b>DRAWING TITLE</b>	<b>REGULATORY DISTANCES</b>
<b>PROJECT TITLE</b>	<b>CITY OF UVALDE LANDFILL PERMIT MODIFICATION</b>

<b>CLIENT</b>	<b>CITY OF UVALDE</b> 3774 FM 481 UVALDE, TEXAS 78801
---------------	---

<b>SCS ENGINEERS</b> STEARNS, CONRAD AND SCHMIDT CONSULTING ENGINEERS 1901 CENTRAL DRIVE, SUITE 550, BEDFORD, TX 76021 PH (817) 571-2288 FAX NO. (817) 571-2188	<b>PROJ. NO.</b>	<b>DWN. BY:</b> JJJ	<b>CHEK. BY:</b> JRB	<b>S/A R/W BY:</b> RPK	<b>APP. BY:</b> RPK
---	------------------	---------------------	----------------------	------------------------	---------------------

<b>CADD FILE:</b>	1.2 REGULATORY DISTANCES MAP
<b>DATE:</b>	02/2025
<b>SCALE:</b>	AS SHOWN
<b>FIGURE:</b>	1.2



## **TABLES**

<b>Table 1.0 MSWLF Soils Map Adapted from Uvalde County, Texas (Source: Natural Resource Conservation Service)</b>						
<b>Hindes&amp;Yolgo soils, undulating (HYB)</b>						
<b>Map Unit Characteristics</b>	Hindes	Yologo	Knippa (KnA)	MoA Montell Clay	OLB Olmos	UvA Uvalde Clay
Acres/% in Area of Interest (AOI)	70.7ac/56.5%		7ac/5.6%	16.1ac/12.9%	26.9ac/21.5%	1.4ac/2.4%
<b>Parent material</b>	Gravelly, loamy alluvium	NR	Calcareous clayey alluvium	Calcareous clayey alluvium	Calcareous loamy alluvium	Calcareous alluvium
<b>Typical profile</b>						
H1 or Ap/A	O-8 inches gravelly sandy clay loam	0- 5" gravelly loam	H1 - 0 to 18 inches: clay	Ap - 0 to 8 inches: clay	H1 - 0 to 13 inches: very gravelly loam	A - 0 to 17 inches: clay loam
H2 or Bnss	8-31 very gravelly clay	5-12" very gravelly clay loam	H2 - 18 to 35 inches: clay	Bnss - 8 to 32 inches: clay	H2 - 13 to 14 inches: cemented material	Bk1 - 17 to 34 inches: clay loam
H3 or Bknss	21-60 clay loam	12-14" Cemented material	H3 - 35 to 60 inches: clay loam	Bknss - 32 to 58 inches: clay	H3 - 14 to 26 inches: very gravelly loam	Bk2 - 34 to 50 inches: clay loam
H4 or Bkny	Not reported	H4: 14 to 16"	Not reported	Bkny: 58 to 80 inches: clay	H4 - 26 to 60 inches: gravelly loam	Bk3 - 50 to 80 inches: silty clay loam
<b>Properties and qualities</b>						
Slope: 1 to 8 percent	1-8 %	1-8%	0-1%	0-1%	1-8%	0-1%
Depth to restrictive feature	>80 inches	>80"	>80"	>80"	10 to 20" to petrocalcic	>80"
Runoff Class	NR	NR	NR	High	Low	Low
Natural drainage class	Well drained	well drained	well drained	Moderately well drained	Well drained	Well Drained
Capacity to transmit water (Ksat)	Moderately high	Mod low to Mod High	Moderately high	Mod low to Mod High	Very low	Mod High to high
Available water storage in profile	Low	very low	High	Moderate		
<b>Interpretive groups</b>						
Hydrologic Soil Group:	C	D	C	D	D	C
Hydric soil	No	No	No	no	No	No

NR= not rated

**TABLE 2.0**  
**GAS MONITORING PROBE COMPLETION DETAILS**

**LANDFILL GAS MANAGEMENT PLAN**

Probe No.	Installation Date **	TOC (msl)	BOC (msl)	Probe Depth (fbgs)	Screen Interval (ft)	Notes
GMP-1*	1986	N/A	N/A	19.9	N/A	
GMP-2*	1986	N/A	N/A	19.3	N/A	
GMP-3*	2002	N/A	N/A	39.8	N/A	
GMP-4*	2002	N/A	N/A	50	N/A	Converted to a vent on 06/08/18
GMP-5*	2011	N/A	N/A	36.7	N/A	
GMP-6*	2011	N/A	N/A	39.8	N/A	
GMP-7*	2011	N/A	N/A	40	N/A	
BGMP-1.1*	2004	N/A	N/A	39.3	N/A	
BGMP-1.2*	2004	N/A	N/A	37.9	N/A	
BGMP-1.3*	2004	N/A	N/A	39.7	N/A	
BGMP-1.4*	2004	N/A	N/A	40	N/A	
BGMP-1.5*	2004	N/A	N/A	38.8	N/A	
BGMP-3.1*	2004	N/A	N/A	39.9	N/A	
BGMP-3.2*	2004	N/A	N/A	34.5	N/A	
BGMP-3.3*	2004	N/A	N/A	38.9	N/A	
BGMP-4.1*	2009	N/A	N/A	26	N/A	
BGMP-4.2*	2009	N/A	N/A	20	N/A	Converted to a vent on 06/08/18
BGMP-4.3*	2009	N/A	N/A	38	N/A	Converted to a vent on 06/08/18
BGMP-4.4*	2009	N/A	N/A	62	N/A	
BGMP-12.1*	2009	N/A	N/A	47.4	N/A	
TGMP-1	5/2/18	967.00	947.00	20	10 - 20	Refusal hit at 20' (conglomerate)
TGMP-2	5/2/18	966.00	946.00	20	10 - 20	Refusal hit at 20' (conglomerate)
TGMP-3.1	5/3/18	966.00	926.00	40	20 - 40	Drilled with air rotary. Completed in Anacacho
TGMP-3.2	5/3/18	966.00	936.00	30	25 - 30	Drilled using air rotary. Completed in Uvalde Gravel
TGMP-3.3	5/3/18	966.00	958.00	8	0 - 5	Completed in Uvalde Gravel

\*Probe/vent depth was field measured due to limited available information

\*\*When exact dates are unavailable, approximate year is provided

GMP= Gas Monitoring Probe

BGMP= Backup Gas Monitoring Probe

TGMP= Temporary Gas Monitoring Probe

N/A= Not Available

**TABLE 3.0**  
**GAS EXTRACTION WELL/VENT COMPLETION DETAILS**

**LANDFILL GAS MANAGEMENT PLAN**

Well No.	Installation Date	TOC (msl)	BOC (msl)	Probe Depth (fbgs)	Screen Interval (ft)	Notes
GMV-1*	2004	N/A	N/A	45	N/A	
GMV-2*	2004	N/A	N/A	33	N/A	
GMV-3*	2004	N/A	N/A	23	N/A	Abandoned on 08/01/23
GMV-4*	2004	N/A	N/A	50	N/A	
GMV-5*	2009	N/A	N/A	24	N/A	Abandoned on 07/31/23
GMV-6*	2009	N/A	N/A	57	N/A	Abandoned on 08/05/23
GV-7*	7/29/18	N/A	N/A	50	N/A	Abandoned on 08/04/23
GV-7a*	7/29/18	N/A	N/A	57	N/A	Abandoned on 08/04/23
GV-8*	7/29/18	N/A	N/A	50	N/A	
GV-9*	7/29/18	N/A	N/A	60	N/A	
GV-10*	7/29/18	N/A	N/A	59	N/A	
TV-1*	5/16/18	N/A	N/A	15	N/A	
TV-2*	5/16/18	N/A	N/A	13	N/A	
TV-3*	5/16/18	N/A	N/A	26	N/A	
EW-11	45139	992	952	40	20 - 40	
EW-12	45139	986.4	947.4	39	20 - 39	
EW-13	45139	994.7	947.7	47	20 - 47	
EW-14	45140	994	947	47	20 - 47	

\*Probe/vent depth was field measured due to limited available information

GMV= Gas Monitoring Vent

GV= Gas Vent

TV= Temporary Vent

EW= Extraction Well

Appendix A  
Methane Monitoring and Recording Form

### Methane Monitoring and Recording Form

**S11100**

Quarter / Year: _____		Weather: _____		
Instrument/Make: _____		Model: _____		
READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				
<u>TGMP</u>				
<u>TV</u>				

Reading recorded by: _____	Date: _____	
----------------------------	-------------	--

- Notes:**
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

Appendix B  
Landfill Gas Remediation Plans

# Landfill Gas Remediation Plan

Dated May 8, 2018

Jon Niermann, *Chairman*  
Emily Lindley, *Commissioner*  
Toby Baker, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

September 5, 2018

Mr. Vince DiPiazza  
Uvalde City Manager  
City of Uvalde  
P.O. Box 799  
Uvalde, Texas 78802

Re: City of Uvalde Landfill - Uvalde County  
Municipal Solid Waste (MSW) - Permit No. 1725  
Landfill Gas Remediation Plan (LGRP)  
Tracking No. 22850073; RN102803921/CN600648455

Dear Mr. DiPiazza:

The MSW Permits Section has received a Landfill Gas Remediation Plan (LGRP). The LGRP is dated May 8, 2018 and was prepared by Steve Forbes, PhD, P.E., P.G., with Forbes Environmental Engineering & Associates on your behalf. Thank you for your submittal. The LGRP documents gas levels in GMP-4 that were above the action level and indicates that notification was performed to Texas Commission of Environmental Quality (TCEQ) central and regional offices, city and county officials, emergency response, and landowners within 1,000 feet of GMP-4. Daily monitoring was being conducted at GMP-4 and three other probes in its vicinity. Temporary gas investigation probes were installed to identify the breadth of the perimeter where gas action levels were being exceeded.

The LGRP includes a three-phased approach. In Phase 1, three two-inch vents were to be installed on a 200-foot spacing, screened in the upper 10 feet of the Uvalde Gravel. Phase 2, to be implemented if Phase 1 is ineffective, includes installation of two six-inch vents in the Stage B waste, screened to one foot above the bottom liner. Phase 3, to be implemented if Phases 1 and 2 are ineffective, includes installation of a passive diversion trench between the landfill and remediation probes installed in Phase 1. Once landfill gas exceedances have been addressed, a notice modification will be submitted in accordance with 30 TAC §305.70(k)(3).

I received an email from Stephen Forbes on August 2, 2018. This email notes that all daily readings in all remediation area probes and vents are decreasing, but concentrations in the temporary probes are decreasing at a much slower rate and the area affected by landfill gas has diminished by approximately 50%. The email indicates that one or two four-inch vents will be installed in the center of the area affected by landfill gas and two vents of four to six inches will be installed in both Stage A and B to further reduce landfill gas concentrations at the perimeter of the facility.

If you have any questions concerning this letter, please contact me at (512) 239-4568, or at the address on our letterhead, please include mail code MC 124.

Sincerely,

A handwritten signature in black ink that reads "Steve Odil".

Steve Odil, P.E.  
Municipal Solid Waste Permits Section  
Waste Permits Division

SPO/arm

cc: Mr. Stephen Forbes, Ph.D., P.E., P.G., Forbes Environmental Engineering, San Antonio

P.O. Box 13087 • Austin, Texas 78711-3087 • 512-239-1000 • [tceq.texas.gov](http://tceq.texas.gov)

How is our customer service? [tceq.texas.gov/customersurvey](http://tceq.texas.gov/customersurvey)

printed on recycled paper



**TO:** Mr. Steve Odil, P.E.  
Waste Permit Division, MSW Permits Section  
Texas Commission on Environmental Quality  
P.O. Box 13087  
Austin, Texas 78711-3087

**DATE:** May 8, 2018

**CC:** Mr. Juan Zamora – City of Uvalde, Director of Public Works  
Mr. Cameron Diaz – TCEQ Region 13

**SUBJECT:** Uvalde Landfill Gas Remediation Plan (LGRP)

---

The attached LGRP provides a remediation plan to address the recent methane gas exceedance (i.e. above 5% methane gas) reported by City landfill staff. The exceedance was reported in GMP-4 during the quarterly gas monitoring event conducted on March 8, 2018 at the City of Uvalde Municipal Solid Waste Landfill facility.

The attached provides the initial actions taken (EAP) and includes the landfill gas remediation plan (LGRP) to address the landfill gas exceedance in accordance with the facilities approved Permit 1725 Landfill Gas Management Plan (LGMP). The LGRP will be submitted to the TCEQ on May 8, 2018 in accordance 30 TAC §330.371 (c)(3). (Landfill Gas Management).

The following is a summary of the actions conducted after the date of the initial reading in GMP-4 that exceeded the maximum allowable methane gas limit:

- Initiated steps to ensure protection of human health by restricting landfill operations in the vicinity of GMP-4, and staff was informed of potential risks of and warned against smoking in area. Public access to the landfill is restricted to disposal area.
- Notified the TCEQ central and regional offices as well as city and county officials, emergency response, and adjacent landowners within 1000 feet of GMP-4.
- Conducted daily gas monitoring in GMP-4, BGMP-4.1 through BGMP-4.4 and MW-11, and reported weekly findings to TCEQ central and regional offices.
- Installed temporary gas investigations probes to identify the potential migration pathway and strata. The initial findings identified the apparent breath of gas concentrations ranging from west of TGMP-2 to east of BGMP-4.4 approximately 600 feet, contained within the upper permeable gravel bed approximately 3-8 feet below surface within the Uvalde Gravel formation. Based on these findings prepared landfill gas remediation plan, as outlined below; figures are included with report.

**Landfill Gas Remediation Plan Summary**

The LGRP strategy is a three-phased approach building upon the results obtained during the previous phases to progressively and effectively, control and mitigate offsite migration in a practical and expedient

time frame. Because of the proximity of GMP-4 to the property line, Phase 1.0 focus on controlling gas migration before it reaches the probes as soon as practical. It is anticipated that Phase 1.0 will be sufficient, but if not the adjustments will be made to increase efficiency (e.g. turbine ventilators) and/or initiate subsequent Phases 2 and/or 3 to achieve objectives. If all three phases are not adequate, more aggressive alternatives will be addressed and discussed with TCEQ.

- Phase 1.0: Install 3 2-inch vents on 200 foot spacing, screened within the upper 10 ft of the Uvalde Gravel in the relatively uniform gravel in which the current gas exceedances appear to occur. The screen zone with a 10' riser above the surface will divert and dissipate the gas before reaches primary remediation monitoring probes (GMP-4, BGMP-4.1 through BGMP-4.4, and TGMP-1, TGMP-2 and TGMP-3.1 through TGMP-3.3).
  - Monitor remediation monitoring probes on a weekly basis for a period of one (1) month to determine response and trend of gas concentrations with respect to the 5% CH<sub>4</sub> limit.
    - If CH<sub>4</sub> concentration exhibits a decreasing trend, continue monitoring on a monthly basis until concentrations are less than the CH<sub>4</sub> limit for at least 3 consecutive months, and then return to normal gas monitoring quarterly monitoring and reporting schedule. Monthly reports to TCEQ will be submitted until return to quarterly monitoring period.
    - If gas readings in monitoring probes do not exhibit a decreasing trend within a month after installing vents or a stabilized trend does not reach sustained CH<sub>4</sub> concentration limits within a 3-month period, Phase 2.0 will be initiated.
- Phase 2.0: Install 2 6-inch PVC vents in Stage B waste screened to one foot above bottom liner. This has been the practice at the Site in the past, including previous exceedance in GMP-4 in 2009. Gas always decreased, but over an extended period until the current exceedance.
  - Monitor remediation monitoring probes on same schedule as Phase 1.0.
- Phase 3: Install a passive diversion trench between the landfill and remediation monitoring probes connected to Phase 1.0 vents. The length and depth of the trench will be determined based on findings of Phase 1 and 2 and bar-hole test boring. The trench design will be filled with gravel inset with 2-inch screened probe connected to the existing vents. The gravel will be capped with bentonite barrier above gravel, with upgradient side lined with geosynthetic liner. Details and schedule will be discussed with TCEQ at the time.
- A permit Modification will be submitted with public notice in accordance with 30 TAC §330.371 (k)(3) upon completion of implementation LGRP.

Please contact me at (210) 323-7313, if you have any questions or need additional information. Thank you for your assistance and consideration.



Stephen Forbes, PhD, P.E. P.G.

**LANDFILL GAS REMEDIATION PLAN  
FOR GMP-4**

**CITY OF UVALDE  
MUNICIPAL SOLID WASTE LANDFILL  
PERMIT NO. 1725**

Prepared for:

City of Uvalde  
Uvalde, Texas

Prepared by:

Forbes Environmental Engineering  
San Antonio, Texas 78216

May 2018



05/08/18

## TABLE OF CONTENTS

	PAGE
<b>1.0 Gas Release Description .....</b>	<b>1</b>
1.1 History.....	1
<b>2.0 Exceedance Action Plan (EAP) .....</b>	<b>1</b>
2.1 Initial GMP-4 Exceedance Evaluation Findings.....	4
<b>3.0 Landfill Gas Remediation Plan .....</b>	<b>5</b>

## LIST OF FIGURES

Figure 1.0	Site Location and offsite 1000 foot distance .....	7
Figure 2.0	Existing Site Gas Monitoring System.....	8
Figure 3.0	Current EAP/ LGRP Study Area.....	9
Figure 4.0	Typical EAP TGMP Design with Generalized Lithology.....	10
Figure 5.0	EAP/LGRP Area Geology Cross Section.....	11
Figure 6.0	Passive Uvalde Gravel Vent.....	12
Figure 7.0	Typical Landfill Gas Vent.....	13

## LIST OF TABLES

Table 1.0	EAP Assessment Gas Monitoring Results.....	14
Table 2.0	EAP Assessment TGMP Completion Details .....	14

## APPENDIX

Appendix A.1: City of Uvalde Exceedance Notice

Appendix A.2: Landfill Gas Reading Logs



# LANDFILL GAS REMEDIATION PLAN FOR GMP-4

## 1.0 Gas Release Description

A landfill gas exceedance (i.e. methane gas concentration greater than 5% by volume) was reported in gas monitoring probe GMP-4 during the quarterly gas monitoring event conducted on March 8, 2018. The Site is located in a sparsely populated area with no residents or habitable buildings within 1000 feet of the property boundaries. See Figure 1.0. GMP-4 is located on the north side of the currently permitted landfill, within a few feet of the northern property line and permit boundary (Refer to Figure 2.0 which shows the Existing Site Gas Monitoring System). No other exceedances were reported in any of the gas monitoring probes along the south, east and west property lines during this quarterly gas monitoring event, nor in the Site Operations building and Scale house.

### 1.1 History

Two gas exceedance events have occurred at the landfill since placed in operations. The first occurred in 2004 and was reported in GMP-1 and GMP-3. Investigative probes indicated the releases were local to the respective probes and as suggested by the TCEQ, four vents were installed in Stage A to release pressure in the storage cells. Once stabilized below LEL, no further gas exceedance occurred until 2009 reported in GMP-4. Once again vents were installed, one in Stage A and the other in Stage B. While the Stage B vent was not very productive, the exceedances receded to compliance levels and methane has not been reported above 5% by volume since, until the recent occurrence.

## 2.0 Exceedance Action Plan (EAP)

Due to the recent methane gas exceedance reported in GMP-4, an exceedance action plan (EAP) was implemented in accordance with the current permit's recently revised Landfill Gas Management Plan (LGMP) approved in February of 2017. The EAP response actions to date include:

- Taking all the necessary steps to ensure protection of human health, such as:
  - Post warning signs at GMP-4
  - Ensure GMP-4 secure

- Prevent public access to GMP-4 vicinity
  - Restrict landfill equipment traffic within GMP-4 vicinity
  - Implement standard health and safety precautions within close proximity of GMP-4
- Immediately notifying the TCEQ central and regional offices, local and county officials, emergency response officials and adjacent landowners within 1000 feet of GMP-4. There are no residences within 1000 feet of the Site. See Appendix A.1.
  - Within seven days of detection (3/15/18), all the information regarding the initial reading (concentration of methane gas, date, location) along with a description of the response actions to protect human health was placed in the SOR, as well as all subsequent information generated to date.
  - In order to determine the nature and extent of the methane gas migration and to ensure protection of human health, GMP-4 and existing BGMP (GMP-4.1 through GMP-4.4) and MW-11 (over a distance of approximately 380 feet) were monitored on a weekly basis and monitoring results were provided to the TCEQ.
  - Three temporary gas monitoring probes, including one cluster of probes were completed at three different depths from the nominal bottom of the landfill to the surface. See below.
  - Within 60 days of detection, a remediation plan to address the methane gas exceedances should be implemented, and a copy of the plan should be placed in the SOR. In addition, by submittal of this LGRP, notify the TCEQ that the remediation plan is being implemented and provide a copy of the plan.

Table 1.0 summarizes the gas monitoring results collected during the initial exceedance action plan (EAP) and LGRP. Landfill gas was monitored in GMP-4 and corresponding BGMP (BGMP-4.1-4.4), installed in 2010 to depths equivalent to bottom of the Stage B landfill liner (935 feet msl or 42 fbgs) and screened from TD to 10' bentonite seal below the surface. Table 2.0 is compilation of the EAP assessment probes completion details.

Since the initial reported exceedance, landfill gas readings in GMP-4 have not been consistent, ranging from 0 to 47%. No methane gas has been detected in BGMP-4.1, which is approximately 15 feet to the west of GMP-4, nor was gas initially reported in BGMP-4.2, 4.3, and 4.4. However, subsequent readings during installation of EAP probe did report gas exceedances in

BGMP-4.2, and BGMP-4.4. This may have been due to disturbances caused by drilling, which could be indicative to the potential migration paths and rates. Gas readings were taken in monitoring wells MW-10, MW-11, and MW-12. Exceedances were only reported in MW-11, and therefore MW-10 and MW-12 were dropped from monitoring schedule, although BPMP-12.1 was maintained as furthest study area data point to the east, since it is consistently reporting CH<sub>4</sub> concentrations below the 5% CH<sub>4</sub> limit.

Due to lack of availability of drilling rigs, initial site field gas evaluation survey was conducted on May 2, 2018, using Direct Push Technology (DPT) to determine the extent of a potential gas release as well as to mitigate the potential for gas migration in the vicinity of gas monitoring probe GMP-4.

The intent of installation of temporary gas monitoring probes was to set the probes at 40± feet depth equivalent to waste depth in Stage B, and a three-GMP cluster with each probe completed at different depths to identify depth of measured gas. However, the DPT rig reached point of refusal (POF) at 17.5 feet (TGMP-1) and 23 feet (TGMP-2). These boring were converted to temporary gas monitoring probes. Fortunately, the drilling company was able to make a rotary rig available to install the cluster probes to 40, 30, and 8 feet (TGMP-3.1, TGMP-3.2, and TGMP-3.3, respectively). Five foot PVC screens were placed at the different elevations. These temporary probes in conjunction with the existing GMP and BGMP provided sufficient data points to identify the general delineation of the gas migration in the vicinity of the property line from TGMP-1 to BGMP-4.4. Gas was reported at the upper elevation (3-8 fbgs), but was not reported at the lower depths. Figure 2.0 shows the Existing Site Gas Monitoring System and indicates the general ongoing EAP/LGRP study area, while Figure 3.0 focuses on the assessment area. Figure 4.0 shows the typical gas monitoring probe design details. Table 3.0 tabulates the TGPM completion details.

The gas readings in these primary monitoring probes were measured over two days during temporary installation as tabulated in Table 1.0. While these readings are sufficient to provide relative concentrations for qualitative comparison, continued monitoring over time is necessary to establish a gas migration trend and additional temporary GMP might be necessary depending

on results and final remediation efforts as summarized in the Landfill Gas Remediation Plan (LGRP) outlined below.

### 2.1 Initial EAP Evaluation Findings

Based on the EAP gas readings shown in Table 1.0, it appears that the gas migration above 5% CH<sub>4</sub> is not constant nor migrates in a predictable linear direction, but is characteristic of gas flow as it meanders about following the paths of least resistance subject to the permeability of medium.

Based on the landfill permit and confirmed by recent ongoing geologic studies, the Uvalde Gravel is the upper most formation overlying the Site. For the most part it does not retain water, although there are isolated perched zones and the shallow depths are generally silty gravel to depths of 15 to 20 feet, which provide paths for migration. In general, the Uvalde Gravel lithology is comprised of an irregular matrix of sedimentary crossbedding ranging from pebble to boulder size, well to poorly sorted gravels, which in many places are cemented and difficult to drill (See Figure 4.0 and 5.0). The field boring cuttings logged during field survey are typical of the Uvalde Gravel. Due to the hardness of the formation, the boring had to be drilled with air to reach target depth at the bottom of Stage B landfill.

Figure 5.0 is a draft cross-section of the geology prepared for an ongoing major permit amendment application showing general lithology and projected landfill bottom from MW-3 in the northwest corner to MW-2 in the northeast corner along the north property line. Stage A was permitted prior to Subtitle D liner requirements, while Stages B and C were permitted in accordance with Subtitle D liner requirements. Stages A and B are separated by a berm with a geosynthetic clay liner (GCL) on the Stage B side, but it is not known if GCL was used on the Stage A side. For the most part all the Stages are completed in the Uvalde Gravel, underlain by the Anacacho, which is nearly 70 feet of essentially impermeable clay. Stage B provides an unlikely pathway for gas migration because of the geosynthetic liner. On the other hand, Stage A, completed without an HDPE liner is a possible source, especially at the upper elevations of the Uvalde Gravel exposed to narrow lens of poorly sorted pebble gravel, such as that encountered in the temporary gas monitoring borings.

### 3.0 Landfill Gas Remediation Plan

Consistent with 30 TAC §330.371(c)(3), a remediation plan (LGRP) to address the methane gas release should be implemented within 60 days of detection and the TCEQ duly notified and a copy placed in the SOR. Initially, the EAP was implemented as a precursor to the LGRP and is essentially the preliminary assessment phase of the LGRP. Using the findings determined by the EAP, a remediation strategy was identified.


The LGRP is a three-phased approach building upon the results obtained during the previous phase to progressively and effectively, control and prevent offsite migration in a practical and expedient time frame. Because of the proximity of GMP-4 to the property line, Phase 1.0 focus on controlling gas migration before it reaches the probes as soon as practical.

It is anticipated that Phase 1.0 will be sufficient, due to the relatively loosely packed gravel strata from approximately 3-8 feet below the surface. However, if this not the case, the subsequent Phases 2 and/or 3 will be implemented to achieve objectives. Otherwise, more aggressive alternatives will be addressed and discussed with the TCEQ.

- Phase 1.0: Install 3 2-inch vents on approximate 200 foot spacing screened in the upper Uvalde Gravel with a 10-ft riser to intercept and divert the gas before it reaches primary remediation monitoring probes (GMP-4, BGMP-4.1 through BGMP-4.4, and TGMP-1 through TBMP-3.3). Figure 6.0 shows the general passive Uvalde Gravel vent completion and Figure 3.0 shows the locations. (Spacing may be adjusted in the field depending on drilling and gas concentrations.)
  - Monitor remediation monitoring probes on a weekly basis for a period of 1 month to determine response and trend of gas concentrations with respect to the 5% CH<sub>4</sub> limit.
    - If concentration exhibits a decreasing trend, continue monitoring monthly until concentrations are less than the CH<sub>4</sub> limit for at least 3 consecutive months, and then return to normal gas quarterly monitoring and reporting schedule. Monthly reports to the TCEQ will be submitted until return to quarterly monitoring period.
    - If initial readings in GMP do not exhibit a decreasing trend within a month after installing vents or stabilized trend does not reach sustained CH<sub>4</sub> concentration

limits within a 3-month period, additional vents may be installed and/or Phase 2.0 will be initiated.

- Phase 2.0: Install 2 6-inch PVC vents in Stage B waste screened to one foot above bottom liner. This has been the practice at the Site in the past, including previous exceedance in GMP-4 back in 2009. Gas concentration always decreased, but over an extended period. The vents will be placed in the northwest corner and center of Stage B. Figure 7.0 shows the typical landfill gas vent completion. The locations are shown Figure 3.0—if necessary.
  - Monitor remediation monitoring probes on same schedule as Phase 1.0.
- Phase 3.0: Install a passive diversion trench upgradient of remediation monitoring probes tied into Phase 1.0 vents. If needed, the trench design will be typical of passive diversion trenches filled with gravel capped with bentonite barrier above gravel, with north side lined with geosynthetic barrier line. The location, length and depth of the trench will be determined based on findings of Phase 1 and 2 and bar-hole test boring. Details and schedule will be discussed with the TCEQ at the time.
- A Permit Modification will be submitted with public notice in accordance with 30 TAC §330.371 (k)(3) upon completion of implementation LGRP.



UNDEVELOPED

UNDEVELOPED

Mixed Undeveloped  
With Rural Residential

UNDEVELOPED





05/08/18

UNDEVELOPED

UNDEVELOPED


- LEGEND:**
-  Habitable Single Family Residence
  -  Ancillary Operation Buildings



FORBES ENVIRONMENTAL ENGINEERING



LANDFILL 1,000 FT RADIUS  
UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 1.0



**LEGEND:**


- Monitor Wells (MW)
- ⊕ Gas Monitoring Probes (GMP)
- Gas Vents (GV)
- ▣ Backup Gas Monitoring Probes (BGMP)
- Temporary Gas Monitoring Probes (TGMP)  
(Installed May 2 & 3, 2018)





FORBES ENVIRONMENTAL ENGINEERING

EXISTING SITE GAS MONITORING SYSTEM  
UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 2.0



- LEGEND:**
- Monitor Wells (MW)
  - ◐ Gas Monitoring Probes (GMP)
  - Existing Gas Monitoring Vents (GMV)
  - ◐ Backup Gas Monitoring Probes (BGMP)
  - Temporary Gas Monitoring Probes (TGMP)  
(Installed May 2 & 3, 2018)  
TGMP Locations approximate




FORBES ENVIRONMENTAL ENGINEERING

---

EAP/LGMP STUDY AREA  
UVALDE LANDFILL  
UVALDE, TEXAS

---

FIGURE 3.0




05/08/18




FORBES ENVIRONMENTAL ENGINEERING

TYPICAL EAP TGMP DESIGN  
CITY OF UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 4.0




LITHOLOGY					
	Caliche		Gravel		Shale
	Clay		Marl		
	Limestone		Conglomerate		



**DRAFT**



- Perimeter Berm
- Projected Landfill Bottom (from construction drawings)



FORBES ENVIRONMENTAL ENGINEERING

GEOLOGIC CROSS SECTION A-A'  
 UVALDE LANDFILL  
 UVALDE, TEXAS

FIGURE 5.0

Rain Cover or  
Suitable Alternative

Approximately 10 feet  
above Surface

Steel Protective Collar

Surface approx. 970 msl

Surface Soils

2'

12" concrete

12" bentonite

Gray GRAVEL

2" dia Sch 40 PVC Slotted Screen  
Hand or Machined Slots  
Glued or Threaded Joints

Gravelly CLAY

7'


2" dia. Schedule 40  
PVC Casing

Gravel

Cap




05/08/18



FORBES ENVIRONMENTAL ENGINEERING

TYPICAL UVALDE GRAVEL VENT  
CITY OF UVALDE LANDFILL  
UVALDE, TEXAS


FIGURE 6.0



Depth of vent will vary with depth of underlying buried waste; care should be taken to avoid disturbing liner protective cover.



05/08/18



FORBES ENVIRONMENTAL ENGINEERING

TYPICAL LANDFILL VENT  
CITY OF UVALDE LANDFILL  
UVALDE, TEXAS

FIGURE 7.0

**TABLE 1.0**  
**EAP Gas Readings, in % volume CH4**  
**LANDFILL GAS REMEDIATION PLAN**

Probe No.	5/2/18 am, pm	5/3/18 am, pm
TGMP-1	6,40	45, 39
GMP 4.0	0,28	0,19
BGMP 4.1	0, 0	0,0
MW-11	14, 11	14, 12
BGMP 4.2	0,0	18, 12
BGMP 4.3	0,12	0,0
BGMP 4.4	0,6	29, 22
BGMP 12.1	0,10	0, 0
MW-12	--, 0	0,0
TGMP-2	9,0	18,10
TGMP 3.1	NA	0,0
TGMP 3.2	NA	0,0
TGMP 3.3	NA	0, 21

NA=probes not installed

**TABLE 2.0**  
**EAP ASSESSMENT GAS MONITORING PROBE COMPLETION DETAILS**  
**LANDFILL GAS REMEDIATION PLAN**

Probe No.	Installation Date	TOC (msl)	BOC (msl)	Probe Depth (fbgs)	Screen Interval (ft)	Notes
TGMP-1	5/2/18	967.00	947.00	20	10 - 20	Refusal hit at 20' (conglomerate)
TGMP-2	5/2/18	966.00	946.00	20	10 - 20	Refusal hit at 20' (conglomerate)
TGMP-3.1	5/3/18	966.00	926.00	40	20 - 40	Drilled with air rotary. Completed in Anacacho
TGMP-3.2	5/3/18	966.00	936.00	30	25 - 30	Drilled using air rotary. Completed in Uvalde Gravel
TGMP-3.3	5/3/18	966.00	958.00	8	0 - 5	Completed in Uvalde Gravel

See Figure 4.0 for Typical Probe Design and general geology.

TGMP= Temporary Gas Monitoring Probe


 05/08/18

**APPENDIX A.1**

**CITY OF UVALDE GAS EXCEEDANCE NOTICE**



**CITY OF UVALDE**  
*Uvalde, Texas*

P.O. Box 799, 78802-0799  
(830) 278-3315  
FAX: (830) 591-2685

City of Uvalde  
Uvalde County  
Uvalde Emergency Response Department

Date: March 13, 2018

To whom it may concern:

In accordance with Texas Commission on Environmental Quality (TCEQ) regulation 30 TAC §330.371 Subchapter I regarding Landfill Gas Management, this letter is to notify you that a reading of 8% methane gas was measured in gas monitoring probe (GMP-4) at the City of Uvalde's Municipal Solid Waste Landfill (MSWLF) on March 8, 2018. This is above the landfill's permitted limit of 5% by volume.

As outlined in the cited regulations, the MSWLF must take appropriate action to ensure protection of public health. The last such exceedance occurred 2010, which was satisfactorily resolved. The facility is in the process of implementing a similar plan of action in accordance with its permit, all of which will be coordinated with the TCEQ.

Please to not hesitate to call Juan Zamora at (830)-275-1785 if you have any questions.

Sincerely Yours,

Juan Zamora  
Director of Public Works

**APPENDIX A.2**

**LANDFILL GAS READING LOGS**

CITY OF UVALDE MSWLF  
 PERMIT NO. 1725  
 UVALDE COUNTY, TEXAS

SUMMARY OF QUARTERLY GAS MONITORING DATA  
 FOR 2017 CALENDAR QUARTER OF 1<sup>st</sup>

GMP ID NUMBER	DATE	TIME	PRESSURE (in. WC)	GAS TEMP (C/F)	%CH4	%LEL
█	2-8-17	<del>10:00 AM</del> 9:00 AM	29.99			0%
█	2-8-17	10:00 AM	29.99			0%
GMP-3	2-8-17	10:15 AM	29.99			0%
GMP-4	2-8-17	10:23 AM	29.99			0%
GMP-5	2-8-17	10:38 AM	29.99			0%
GMP-6	2-8-17	10:47 AM	29.99			0%
GMP-7	2-8-17	10:56 AM	29.99			0%

Notes:  
 Form to be submitted with each quarterly gas monitoring event.  
 If methane is detected, also include field sampling form and graph.  
 GMP Forms to file in Site Operating Records, and not submitted to TCEQ unless an exceedance occurs.

CITY OF UVALDE MSWLF  
 PERMIT NO. 1725  
 UVALDE COUNTY, TEXAS

SUMMARY OF QUARTERLY GAS MONITORING DATA  
 FOR 2017 CALENDAR QUARTER OF 2nd

GMP ID NUMBER	DATE	TIME	PRESSURE (In. WC)	GAS TEMP (C/F)	%CH4	%LEL
█	6-15-17	1055Am	29.98			0%
█	6-15-17	1110Am	29.98			0%
GMP-3	6-15-17	1177Am	29.98			0%
GMP-4	6-15-17	1124Am	29.98			0%
GMP-5	6-15-17	1137Am	29.98			0%
GMP-6	6-15-17	1146Am	29.98			0%
GMP-7	6-15-17	1155Am	29.98			0%

Notes:  
 Form to be submitted with each quarterly gas monitoring event.  
 If methane is detected, also include field sampling form and graph.  
 GMP Forms to file in Site Operating Records, and not submitted to TCEQ unless an exceedance occurs.

CITY OF UVALDE MSWLF  
 PERMIT NO. 1725  
 UVALDE COUNTY, TEXAS

SUMMARY OF QUARTERLY GAS MONITORING DATA  
 FOR 2017 CALENDAR QUARTER OF 3rd

GMP ID NUMBER	DATE	TIME	PRESSURE (In. WC)	GAS TEMP (C/F)	%CH4	%LEL
█	8-18-17	9:15AM	29.96			0%
█	8-18-17	9:20AM	29.96			0%
GMP-3	8-18-17	9:25AM	29.96			0%
GMP-4	8-18-17	9:40AM	29.96			0%
GMP-5	8-18-17	9:50AM	29.96			0%
GMP-6	8-18-17	9:59AM	29.96			0%
GMP-7	8-18-17	10:05AM	29.96			0%

Notes:  
 Form to be submitted with each quarterly gas monitoring event.  
 If methane is detected, also include field sampling form and graph.  
 GMP Forms to file in Site Operating Records, and not submitted to TCEQ unless an exceedance occurs.

CITY OF UVALDE MSWLF  
 PERMIT NO. 1725  
 UVALDE COUNTY, TEXAS

SUMMARY OF QUARTERLY GAS MONITORING DATA  
 FOR ~~4th~~ 2017 CALENDAR QUARTER OF 4th

GMP ID NUMBER	DATE	TIME	PRESSURE (In. WC)	GAS TEMP (C/F)	%CH4	%LEL
█	12-13-17	9:44	29.92			0%
█	12-13-17	9:10 AM	29.92			0%
GMP-3	12-13-17	9:20 AM	29.92			0%
GMP-4	12-13-17	9:25 AM	29.92			0%
GMP-5	12-13-17	9:40 AM	29.92			0%
GMP-6	12-13-17	9:44 AM	29.92			0%
GMP-7	12-13-17	9:50 AM	29.92			0%

Notes:  
 Form to be submitted with each quarterly gas monitoring event.  
 If methane is detected, also include field sampling form and graph.  
 GMP Forms to file in Site Operating Records, and not submitted to TCEQ unless an exceedance occurs.

CITY OF UVALDE MSWLF  
 PERMIT NO. 1725  
 UVALDE COUNTY TEXAS

SUMMARY OF WEEKLEY GAS MONITORING DATA  
 FOR 2018 CALENDAR QUARTER OF 1<sup>ST</sup>

FACILITY STRUCTURES BUILDING ID:	DATE	TIME	TEMP(C/F)	%CH4	%LEL
<b>GATE HOUSE</b>	3				
NORTH WALL	3-8-18				0%
EAST WALL	3-08-18				0%
SOUTH WALL	3-08-18				0%
WEST WALL	3-08-18				0%
<b>MAINTENANCE BUILDING</b>					
NORTH WALL	3-08-18	9: AM			0%
EAST WALL	3-08-18	9: AM			0%
SOUTH WALL	3-08-18	9: AM			0%
WEST WALL	3-08-18	9: AM			0%
					0%

**Notes:**

Form to be submitted with each weekly gas monitoring event.  
 If methane is detected, also include field sampling form and graph.

GMP Forms to file in Site Operating Records, and not submitted to TCEQ unless an exceedance occurs

**Summary of Quarterly Gas Monitoring Data**

Quarter 1<sup>st</sup> Year 2018 Weather: Fair, Sunny, Part cloudy  
 Instrument: Make: \_\_\_\_\_; Model: \_\_\_\_\_

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	<u>3-15-18</u>	<u>930AM</u>	<u>0%</u>	
East Wall	<u>3-15-18</u>	<u>930AM</u>	<u>0%</u>	
South Wall	<u>3-15-18</u>	<u>930AM</u>	<u>0%</u>	
West Wall	<u>3-15-18</u>	<u>931AM</u>	<u>0%</u>	
<u>Maintenance Building</u>				
North Wall	<u>3-15-18</u>	<u>944AM</u>	<u>0%</u>	
East Wall	<u>3-15-18</u>	<u>944AM</u>	<u>0%</u>	
South Wall	<u>3-15-18</u>	<u>944AM</u>	<u>0%</u>	
West Wall	<u>3-15-18</u>	<u>944AM</u>	<u>0%</u>	
<u>BGMP</u>				
Reading recorded by: <u>[Signature]</u>			Date <u>3-15-18</u>	

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL.
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 1st- 2018

Weather: \_\_\_\_\_

Instrument/Make: \_\_\_\_\_

GMI \_\_\_\_\_

Model: \_\_\_\_\_

GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				29.90 pressure
GMP-1				
GMP-2				
GMP-3				
GMP-4	3/15/2018	11:20a	21 gas	
GMP-4.1				
MW #11				
BGMP 12.1				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>TGMP</u>				
#2				
#1				
3.1				
3.2				
3.3				

Reading recorded by: *Carl King*

Date: 3/15/2018

Notes:

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter 1<sup>st</sup> Year 2018 Weather: Mostly Cloudy  
 Instrument: Make: GMI; Model: Gasurveyor 500 Series

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	<u>3-15-18</u>	<u>11:20AM</u>	<u>21 gas</u>	
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				

Reading recorded by: [Signature] Date 3-15-18

- Notes:**
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

**UVALDE MSW LANDFILL INCIDENT RECORD**

Completed by: Carl Mirelez Date: 3-15-18

Incident Check One:

- Prohibited Waste
- Fire
- Pond Water
- Site Security Breach
- Erosion
- Groundwater
- Surface Water Drainage
- Gas Monitoring
- Other: \_\_\_\_\_

Date of occurrence: 3-15-18

Location: Landfill

Conditions (e.g. weather, etc.): Cool 58°

Description: Read Methane gas on GMP4  
21 gas

Cause: \_\_\_\_\_

Action taken: Notified Regional, state and site  
manager of Reedin

Current Status: Still Monitoring

		Date	Contact
Notification (check and date):	<input checked="" type="checkbox"/> Site Manager	<u>3-15-18</u>	<u>Juan Zam</u>
Agency:	<input checked="" type="checkbox"/> Local agencies	<u>3-15-18</u>	<u>City, County Fire Dep</u>
	<input checked="" type="checkbox"/> TCEQ	<u>3-15-18</u>	<u>Regional + State</u>
Identify:	<input type="checkbox"/> Other		

Additional information and comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 1st 2018 weekly      Weather: 76 \* cloudy  
 Instrument/Make: GMI      Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	3/23/2018	3:04pm	0%	
East Wall	3/23/2018	3:04pm	0%	
South Wall	3/23/2018	3:04pm	0%	
West Wall	3/23/2018	3:04pm	0%	
<u>Maintenance Building</u>				
North Wall	3/23/2018	3:09pm	0%	
East Wall	3/23/2018	3:09pm	0%	
South Wall	3/23/2018	3:09pm	0%	
West Wall	3/23/2018	3:09pm	0%	
<u>BGMP</u>				
4.1				
4.2				

Reading recorded by: *Carl King*      Date: 3/23/2018

- Notes:**
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL.
  - BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 1st 2018 Weather: 56\* Foggy  
 Instrument/Make: GMI Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	3/29/2018	8:30pm	0 GAS	
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				

Reading recorded by: *Carl King* Date: 3/29/2018

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL.
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 1st 2018- weekly Weather: 76\*f PARTLY CLOUDY  
 Instrument/Make: GMI Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<b><u>GMP</u></b>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<b><u>Gate House</u></b>				
North Wall	3/29/2018	3:30pm	0 gas	
East Wall	3/29/2018	3:30pm	0 gas	
South Wall	3/29/2018	3:30pm	0 gas	
West Wall	3/29/2018	3:30pm	0 gas	
<b><u>Maintenance Building</u></b>				
North Wall	3/29/2018	3:35pm	0 gas	
East Wall	3/29/2018	3:35pm	0 gas	
South Wall	3/29/2018	3:35pm	0 gas	
West Wall	3/29/2018	3:35pm	0 gas	
<b><u>BGMP</u></b>				

Reading recorded by: *Carl King* Date: 3/29/2018

- Notes:**
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

Quarter / Year: <sup>2nd</sup> 1st 2018-WEEKLY		Weather: 61*f PARTLY CLOUDY		
Instrument/Make: GMI		Model: GASSURVEYOR 500 SERIES		
<b>READING LOCATION</b>	<b>Date</b>	<b>Time</b>	<b>Reading in % CH4</b>	<b>Comment</b>
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	4/5/2018	9:54AM	0%	
East Wall	4/5/2018	9:54AM	0%	
South Wall	4/5/2018	9:54AM	0%	
West Wall	4/5/2018	9:54AM	0%	
<u>Maintenance Building</u>				
North Wall	4/5/2018	10:00AM	0%	
East Wall	4/5/2018	10:00AM	0%	
South Wall	4/5/2018	10:00AM	0%	
West Wall	4/5/2018	10:00AM	0%	
<u>BGMP</u>				
4.1	4/5/2018	9:10AM	0	
4.2	4/5/2018	9:10AM	0	
Reading recorded by: <i>Carl King</i> Date: 4/5/2018				

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL.
- BGMP if exceedances reported.

Quarter / Year: <sup>2nd</sup> <del>1st</del> 2018		Weather: <u>S11100</u>		61*f PARTLY CLOUDY
Instrument/Make: GMI		Model: GASSURVEYOR 500 SERIES		
READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	4/5/2018	9:02AM	16 GAS	
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				
4.1	4/5/2018	9:10AM	0	
4.2	4/5/2018	9:10AM	0	
Reading recorded by: <i>Carl King</i>		Date: 4/5/2018		

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

Quarter / Year: <u>2nd</u> <del>1st</del> 2018		Weather: <u>61*f PARTLY CLOUDY</u>		
Instrument/Make: <u>GMI</u>		Model: <u>GASSURVEYOR 500 SERIES</u>		
<b>READING LOCATION</b>	<b>Date</b>	<b>Time</b>	<b>Reading in % CH4</b>	<b>Comment</b>
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	4/12/2018	9:25AM	47 GAS	
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				
Reading recorded by: <u>Carl King</u>		Date: <u>4/12/2018</u>		

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

Quarter / Year: <sup>2nd</sup> <del>1st</del> 2018-WEEKLY		Weather: 61*f CLOUDY		
Instrument/Make: GMI		Model: GASSURVEYOR 500 SERIES		
<b>READING LOCATION</b>	<b>Date</b>	<b>Time</b>	<b>Reading in % CH4</b>	<b>Comment</b>
<b>GMP</b>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<b>Gate House</b>				
North Wall	4/12/2018	10:27AM	0 GAS	
East Wall	4/12/2018	10:27AM	0 GAS	
South Wall	4/12/2018	10:27AM	0 GAS	
West Wall	4/12/2018	10:27AM	0 GAS	
<b>Maintenance Building</b>				
North Wall	4/12/2018	10:35AM	0 GAS	
East Wall	4/12/2018	10:35AM	0 GAS	
South Wall	4/12/2018	10:35AM	0 GAS	
West Wall	4/12/2018	10:35AM	0 GAS	
<b>BGMP</b>				
Reading recorded by: <i>Carl King</i>		Date: 4/12/2018		

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL.
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 2nd- 2018 Weather: \_\_\_\_\_  
 Instrument/Make: \_\_\_\_\_ GMI Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				29.90 pressure
GMP-1				
GMP-2				
GMP-3				
GMP-4	4/19/2018	8:40a	0 Gas	
GMP-4.1				
MW #11				
BGMP 12.1				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				
4.1	4/19/2018	8:42a	0 Gas	
MW #11	4/19/2018	8:45a	16 Gas	
MW #12	4/19/2018	8:48a	0 Gas	

Reading recorded by: *Carl King* Date: 4/19/2018

- Notes:
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

Quarter / Year: <sup>2nd</sup> <del>1st</del> 2018-WEEKLY		Weather: 63* MOSTLY CLOUDY		
Instrument/Make: GMI		Model: S11100 GASSURVEYOR 500 SERIES		
READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	4/19/2008	9:29AM	0 GAS	
East Wall	4/19/2008	9:30AM	0 GAS	
South Wall	4/19/2008	9:33AM	0 GAS	
West Wall	4/19/2008	9:35AM	0 GAS	
<u>Maintenance Building</u>				
North Wall	4/19/2008	9:41AM	0 GAS	
East Wall	4/19/2008	9:43AM	0 GAS	
South Wall	4/19/2008	9:50AM	0 GAS	
West Wall	4/19/2008	9:51AM	0 GAS	
<u>BGMP</u>				
Reading recorded by: <i>Carl King</i>		Date: 4/19/2018		

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: <u>2nd- 2018</u>		Weather: _____		
Instrument/Make: _____		GMI	Model:	GASSURVEYOR 500 SERIES
READING LOCATION	Date	Time	Reading in % CH4	Comment 29.90 pressure
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	4/26/2018	8:24a	12 Gas	
GMP-4.1				
MW #11				
BGMP 12.1				
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>BGMP</u>				
4.1	4/26/2018	8:26a	0	
MW #11	4/26/2018	8:29a	29 Gas	
MW #12	4/26/2018	8:31a	0 Gas	

Reading recorded by: *Carl King* Date: 4/19/2018

- Notes:
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

**S11100**

Quarter / Year: 2nd 2018- weekly

Weather:

61\*f PARTLY CLOUDY

Instrument/Make:

GMI

Model:

GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	4/26/2018	10:19AM	0	
East Wall	4/26/2018	10:19AM	0	
South Wall	4/26/2018	10:21AM	0	
West Wall	4/26/2018	10:22AM	0	
<u>Maintenance Building</u>				
North Wall	4/26/2018	10:25AM	0	
East Wall	4/26/2018	10:27AM	0	
South Wall	4/26/2018	10:28AM	0	
West Wall	4/26/2018	10:29AM	0	
<u>BGMP</u>				

Reading recorded by:

*Carl Miss*

Date:

4/26/2018

Notes:

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

**S11100**

Quarter / Year: 2ND 2018-WEEKLY

Weather: 90\* SUNNY

Instrument/Make: GMI

Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4				
GMP-5				
GMP-6				
GMP-7				
<u>Gate House</u>				
North Wall	5/3/2018	4:00PM	0	
East Wall	5/3/2018	4:02PM	0	
South Wall	5/3/2018	4:05PM	0	
West Wall	5/3/2018	4:06PM	0	
<u>Maintenance Building</u>				
North Wall	5/3/2018	4:08PM	0	
East Wall	5/3/2018	4:10PM	0	
South Wall	5/3/2018	4:11PM	0	
West Wall	5/3/2018	4:12PM	0	
<u>BGMP</u>				

Reading recorded by:

*Carl King*

Date:

5/3/2018

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 2nd 2018

Weather: 90\* Sunny

Instrument/Make: GMI

Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
<b>GMP</b>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	5/3/2018	4:24PM	37 GAS	
GMP-4.1	5/3/2018	4:20PM	15 GAS	
MW #11	5/3/2018	4:28PM	31 GAS	
BGMP 12.1	5/3/2018	4:40PM	10 GAS	
<b>Gate House</b>				
North Wall				
East Wall				
South Wall				
West Wall				
<b>Maintenance Building</b>				
North Wall				
East Wall				
South Wall				
West Wall				
<b>TGMP</b>				
#2	5/3/2018	4:19PM	12 GAS	
#1	5/3/2018	4:26PM	47 GAS	
3.1	5/3/2018	4:30PM	0	
3.2	5/3/2018	4:32PM	0	
3.3	5/3/2018	4:34PM	32 GAS	

Reading recorded by:

*Cal King*

Date:

5/3/2018

**Notes:**

- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
- Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
- Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
- All readings should be recorded as for CH4 by volume, not % LEL .
- BGMP if exceedances reported.

**Summary of Quarterly Gas Monitoring Data**

Quarter / Year: 2nd 2018 Weather: 63\* partly cloudy  
 Instrument/Make: GMI Model: GASSURVEYOR 500 SERIES

READING LOCATION	Date	Time	Reading in % CH4	Comment
29.90 pressure				
<u>GMP</u>				
GMP-1				
GMP-2				
GMP-3				
GMP-4	5/7/2018	8:20AM	0	
GMP-4.1	5/7/2018	8:17AM	31 GAS	
MW #11	5/7/2018	8:26AM	27	
BGMP 12.1	5/7/2018	8:40AM	0	
<u>Gate House</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>Maintenance Building</u>				
North Wall				
East Wall				
South Wall				
West Wall				
<u>TGMP</u>				
#2	5/7/2018	8:15AM	0	
#1	5/7/2018	8:24AM	0	
3.1	5/7/2018	8:36AM	0	
3.2	5/7/2018	8:35AM	0	
3.3	5/7/2018	8:37AM	0	

Reading recorded by: *Carl King* Date: 5/7/2018

- Notes:
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP.
  - Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported.
  - Exceedance: greater than 5% methane (CH4) by volume in GMP, or 1.25% in Buildings.
  - All readings should be recorded as for CH4 by volume, not % LEL .
  - BGMP if exceedances reported.

Landfill Gas Remediation Plan Update

Dated January 17, 2022

**FORBES  
ENVIRONMENTAL  
ENGINEERING & ASSOCIATES**



11839 Parliament St., #813  
San Antonio, Texas 78216  
Phone (210)323-7313


**TO:** Mr. Robert C. Pedersen, P.E.,  
Project Manager  
Municipal Solid Waste Permits Section – MC 124  
Texas Commission on Environmental Quality  
P.O. Box 13087  
Austin, Texas 78711-3087

**DATE:** January 17, 2022

**CC:** Mr. Juan Zamora – Director of Public Works, City of Uvalde

**FROM:** Stephen Forbes, P.E.

**SUBJECT:** City of Uvalde Landfill MWS Permit No. 2019–2021 Gas Monitoring  
Quarterly Reports (TCEQ Tracking No. 26649876, RN102803921/CN60064855)



Dear Mr. Pedersen:

As authorized by the City of Uvalde (City), this Landfill Gas Remediation Plan (LGRP) Update is submitted by Forbes Environmental Engineering on behalf of the City in response to TCEQ's letter dated October 28, 2021, Tracking No. 26649876. Relevant tables and figures are included at the end of text.

Gas monitoring reports were submitted by the City of Uvalde on May 3, 2021 for 2019, 2020, and first quarter of 2021. The TCEQ requested additional information in letter dated May 10, 2021 (Tracking No. 2609384), to which the City's responded with letter report dated May 17, 2021 ("5/17/21 Report").

The quarterly monitoring reports for 2021 were submitted to the TCEQ by the City of Uvalde including quarterly methane gas readings from GMP-1 through GMP-7, facility Gate House and Maintenance Building. The TCEQ responded by its letter dated October 28, 2021, requesting the following information. The City's response is provided in italics, with the 5/17/21 Report incorporated by reference.

1. Provide landfill gas monitoring readings for Backup Gas Monitoring Probes BGMP-4.1, 4.2, 4.3, and 4.4 since an exceedance was reported in GMP-4 [on 5/2/18], per approved Landfill Gas Monitoring Plan.

*GMP-4 was converted to open vent on 6/8/18 to alleviate offsite migration at the property line. Landfill gas monitoring readings were initially provided in the May 5/17/21 Report. See attached Tables 1.0 and 2.0, which have been updated to include landfill gas monitoring data to date.*

2. Provide available data for monthly gas probe monitoring performed per your Landfill Gas Remediation Plan dated May 18, 2018.

*See Attached Tables 1.0 and 2.0 as well as Charts 1.1 through 1.15.*

3. Provide the locations, location numbers, and observed methane values for temporary probes and vents installed during Phases 1 and 2 of the Landfill Gas Remediation Plan

*See attached location map (Figure 1.0) showing location of investigation probes and remediation vents. Five additional vents were installed in Stage B of inactive landfill in August 2018 in an attempt to increase ventilation and retain lateral gas migration (Refer to 5/17/21 Report) within landfill perimeter. Methane values to date for temporary probes and vents are provided in Table 2.0.*

4. Provide your schedule to implement the passive landfill gas diversion trench a defined as Phase 3 of your Landfill Gas Remediation Plan Dated May 18, 2018 as a way to lower methane levels below 5% by volume at the perimeter gas monitoring probes.

*The excavation of a passive diversion ditch was delayed to monitor the effectiveness of additional vents, and determine trench location. Depth of a diversion is limited by a hard substrata preventing reaching uniform depths. Figure 2.0 shows the projected gas plume.*

*In addition to the actions addressed above, the City is in process of purchasing the property adjacent to the north Landfill property. This will expand the investigation limits and provide the space needed to install an effective passive collection system. The purchase transaction is in the appraisal process. In the event that the transaction does not close, a landfill passive gas diversion trench will be installed, subject to independent engineer review and feedback as well as TCEQ notification.*

*In the meantime, the facility is seeking professional and contractor support services to evaluate conditions and propose efficient and effective mitigation controls and construction. Once retained the LGMR plan will be revised for review by TCEQ.*

5. Provide your response in one original and two copies for distribution.

*One original and two copies of response have been provided.*

In addition, the TCEQ advised to be aware that changes to the existing LFG collection system pertaining to the remediation plan require a permit modification with notice in

accordance with 30 TAC §305.70(k)(3) and must be submitted within 60 days of detection.

*A permit modification was issued on 2/27/2017 to update the current permit's Landfill Gas Management Plan (LGMP) which includes landfill Gas Management Remediation Plan (LGMRP) which has been followed to date as remediation efforts were evaluated. A permit modification will be submitted with public notice upon completion of current remediation action, unless the TCEQ requires sooner.*

It is hoped this response adequately satisfies TCEQ request to address items 1 through 5 of the above referenced TCEQ notice (dated October 28, 2021). If you have any questions, need additional information, or require further clarification and/or action, please contact me at (210) 323-7313 or Mr. Juan Zamora, City of Uvalde Director of Public works at (830) 278-8883. In the meantime, the City will continue monthly LGRP monitoring, and to take additional action to mitigate LGMP conditions subject to independent review and guidance.

Thank you for your assistance.


Sincerely yours,



Stephen Forbes, PE


Attachments

- Figures
- Tables
- Charts



**LEGEND**

- Monitor Well (MW)
- ⊠ Gas Monitoring Probes (GMP)
- Existing Gas Vents (GMV)
- Backup Gas Monitoring Probes (BGMP)
- Temporary Gas Monitoring Probes (TGMP) installed on May 2 & 3, 2018.
- Temporary Gas Vents (TV) installed on May 16, 2018 (LGRP Phase 1).
- Additional Gas Vents (GV) installed on July 29, 2018 (LGRP Phase 2).





NOTES:  
 EAP: Exceedance Action Plan  
 LGRP: Landfill Gas Remediation Plan



FORBES ENVIRONMENTAL ENGINEERING

EAP/LGRP GAS MONITORING PROBES  
 & GAS VENTS LOCATION  
 UVALDE LANDFILL  
 UVALDE, TEXAS

FIGURE 1.0



STATE OF TEXAS  
 PROFESSIONAL ENGINEER  
 STEPHEN FORBES  
 7/21/2018



FORBES ENVIRONMENTAL ENGINEERING

LGRP PROJECTED GAS PLUME  
 UVALDE LANDFILL  
 UVALDE, TEXAS

FIGURE 2.0

**TABLE 1.0 - LANDFILL GAS MONITORING RESULTS**

( Reported as % methane gas by volume)

Exceedance Action Plan - TGMP-1, TGMP2, and TGMP 3.1 - 3.3 Installed on May 2 and 3, 2018.															
Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3			
5/2/18	38	26				28									
5/3/18	37	15				31	10	12	47						
5/4/18	34	27				29	0	0	0						
5/7/18	0	31				27	0	0	0						
5/8/18	48	47				35	0	38	48	41	41	46			
5/9/18	49	50				27	0	15	38	42	45	47			
5/10/18	31	45				26	0	19	26	49	48	46			
5/11/18	48	46				22	11	44	48	53	52	48			
5/14/18	47	43				22	19	46	47	55	51	48			
5/15/18						23	14								
5/16/18								43	49						
Landfill Gas Remediation Plan Phase 1 - TV-1, TV-2 and TV-3 Installed on May 16, 2018.															
Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
5/17/18	48	48				35	23	44	50	47	52	49	0	29	12
5/18/18	49	45				33	25	41	50	52	53	49	0	33	8
5/22/18	47	47				31	0	40	49	56	52	47	8	28	6
5/23/18	42	37				30	0	31	49	55	50	47	9	20	0
5/24/18	41	34				28	0	33	50	54	50	47	6	24	7
5/25/18	49	49				33	0	43	50	55	52	48	9	42	18
5/29/18	48	45	50	47	51	38	0	42	50	56	52	49	5	25	12
5/30/18	47	42	43	41	36	23	46	27	50	54	52	49	0	29	13
5/31/18	37	27	32	26	32	29	0	30	50	55	52	48	5	33	11
6/1/18	6	16	10	0	28	29	0	13	48	52	45	46	0	5	0
6/4/18	47	38	48	36	19	25	6	35	50	57	52	49	8	38	42
6/5/18	49	49	52	48	46	25	29	37	50	57	52	56	10	30	30
6/6/18	48	48	51	47	22	23	33	35	49	51	48	47	8	35	41
6/7/18	30	25	8	21	8	28	21	28	49	57	52	47	0	19	0
6/8/18	32	14	15	28	0	19	0	29	50	52	43	43	0	17	5
6/11/18	48	46	57	20	46	4.6	11	44	31	51	53	48	31	48	10
6/12/18	43	28	17	36	36	4	12	13	50	38	45	47	24	42	36
6/13/18	38	32	17	23	16	4	0.03	37	48	38	48	47	22	43	28
6/14/18	47	12	41	43	24	3.4	9	36	50	58	51	48	28	47	9
6/15/18	48	25	49	47	33	2	13	29	49	53	25	41	30	47	44
6/18/18	48	26	45	45	27	5	7	37	47	54	52	47	32	47	43
6/19/18	48	34	46	48	26	5	10	32	48	55	52	47	30	42	27
6/20/18	48	33	15	34	9	5	0	28	48	56	53	47	28	46	44
6/21/18	42	0	0	29	9	5	0	22	48	55	51	47	26	46	32
6/22/18	46	48	23	42	46	0.08	1.3	26	47	55	51	46	27	41	40
6/25/18	36	1.5	6	19	1	1.2	0	9	45	43	51	47	22	43	26
6/26/18	33	0.05	9	28	0.7	0.25	0	10	48	55	51	47	23	44	32
6/27/18	45	0.15	21	42	13	1.25	0	17	46	53	52	46	24	45	32
6/28/18	43	1.4	18	45	14	0.75	1.65	28	47	54	53	46	24	44	37
6/29/18	44	1.5	21	45	10	0.5	2.35	27	47	50	53	45	22	45	41
7/2/18	38	0.15	34	34	19	8	1.3	17	48	48	52	46	21	44	37
7/3/18	43	0.6	36	43	26	0.6	0.15	30	48	54	52	46	21	30	37
7/5/18	15	0	0	12	8	1.35	0.01	0.13	20	41	46	44	19	30	14
7/6/18	34	0	23	28	0.75	0.2	0	21	45	52	49	43	30	42	30
7/9/18	31	2.35	44	25	9	1.05	0	10	44	52	48	41	28	41	11
7/10/18	41	1.2	24	39	6	0.95	1.1	24	45	54	51	42	29	43	36
7/11/18	45	3.05	22	46	32	1.25	11	19	46	53	51	43	30	45	29
7/12/18	43	4	25	35	14	0.3	0.6	15	45	54	50	43	30	44	30
7/13/18	39	1.5	18	30	9	1.1	0.35	15	42	54	49	43	30	43	33
7/16/18	40	2	24	30	16	0.45	0.5	14	45	55	50	44	27	44	31

Notes:

\* Originally monitoring probes converted to vents

\*Some readings taken on 7/25/19 were unusually low, so resampled was conducted on 7/29/19

**TABLE 1.0 - LANDFILL GAS MONITORING RESULTS (CONT.)**

( Reported as % methane gas by volume)

Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
7/17/18	32	8	17	0	38	1.2	5	6	17	48	50	43	12	15	1.75
7/18/18	44	2.3	26	29	34	0.95	0.7	17	46	56	48	44	29	47	32
7/19/18	44	21	23	47	29	0.6	2.75	24	43	53	53	45	24	45	33
7/20/18	44	43	18	35	5	0.8	1	28	46	57	52	45	31	45	30
7/23/18	46	6	20	48	16	0.6	2	15	45	55	53	46	33	46	20
7/24/18	41	3.1	29	32	30	1.15	2	22	45	54	45	44	16	29	25
7/25/18	40	0.45	20	29	3	0.35	0.1	23	46	56	48	44	32	44	26
7/26/18	43	2.4	22	35	4	2.1	0.15	9	45	54	49	44	27	37	31
7/27/18	41	1	13	27	5	0.65	0.45	11	45	54	51	44	28	45	30
7/30/18	45	17	31	42	37	4.7	8	14	46	55	50	44	17	36	27
7/31/18	29	0.15	6	23	6	0.2	0.02	9	24	46	49	43	19	31	12
8/1/18	44	11	38	40	20	0.1	11	19	30	56	54	45	17	36	20
8/2/18	41	12	27	38	35	0.3	10	20	45	57	52	43	33	45	30
8/8/18	36	0	7	28	12	0.25	1.2	2.95	40	50	47	42	29	43	27
8/15/18	31	17	6	27	11	1.25	8	7	40	53	46	43	20	30	13
8/22/18	36	0.15	21	28	2.75	0.2	0.4	18	45	55	49	45	30	43	25
8/29/18	36	0.6	19	27	5	1.25	0.8	48	51	46	9	46	19	40	26
9/6/18	44	17	15	29	8	0.5	1.05	8	40	47	50	43	21	30	24
9/13/18	49	25	20	40	18	0.4	0.9	30	48	51	48	50	29	48	26
9/20/18	39	16	16	35	11	0.85	1.5	23	46	46	40	42	24	42	23
9/27/18	49	6	28	37	5	0.25	1	38	51	56	52	51	46	50	35
10/3/18	49	6	18	46	15	0.6	0.05	34	49	47	12	50	41	48	40
10/11/18	45	4.7	10	25	1.45	0.25	1.15	21	50	40	50	50	31	48	24
10/17/18	51	5	15	22	2.85	1.6	0	45	52	55	52	51	49	49	22
10/30/18	50	19	20	50	15	0.4	0.7	35	50	55	52	51	24	50	38
11/7/18	50	7	19	40	3.25	0.05	0	23	50	53	51	51	39	50	27
11/15/18	51	15	23	36	10	1.15	0.15	37	52	57	52	49	45	51	37
11/27/18	41	7	18	28	10	2.75	0.05	41	53	55	50	50	48	48	35
12/6/18	49	10	20	15	5	1.75	0.5	19	48	48	52	49	38	50	37
12/13/18	0	0	0	0	0	1.8	0	0	0	0	0	0.05	38	0	0
12/14/18	15	0	0.05	4.15	0	0.9	0	17	25	0.05	0.15	54	40	39	18
12/21/18	47	12	28	32	19	1.5	15	53	25	48	51	51	48	49	41
12/26/18	51	14	23	50	16	6	0	45	51	56	52	51	50	50	36
1/4/19	52	6	28	31	10	2.4	0	27	52	53	53	52	40	50	27
1/11/19	53	14	21	47	10	11	0	52	52	57	54	52	52	52	48
1/16/19	52	15	19	44	13	9	7	39	52	57	53	52	45	51	41
1/23/19	13	0	12	40	10	3	0.65	38	38	57	47	46	43	35	46
1/30/19	40	6	20	41	11	7	0	28	51	56	47	49	42	47	38
2/6/19	50	35	45	49	37	12	23	41	50	54	51	50	30	49	37
2/15/19	50	13	20	48	12	5	0	35	50	55	50	55	48	49	36
2/20/19	42	16	36	30	17	30	15	37	51	55	51	50	35	46	30
2/28/19	47	4	13	27	1	7	2.15	17	47	29	33	50	39	48	23
3/7/19	49	15	22	31	1.4	6	1.4	32	50	52	51	49	44	49	46
3/15/19	1.75	0	0	1.7	0	4.45	0	14	51	0	45	38	36	24	6
3/22/19	46	5	26	42	11	9	8	15	45	18	49	48	44	48	45
3/29/19	49	12	26	48	12	9	6	20	49	41	50	48	44	48	44
4/5/19	48	32	48	45	23	20	18	46	44	48	50	47	32	48	40
4/12/19	40	5	11	30	9	3.5	0.6	45	49	54	49	47	48	45	34
4/17/19	47	20	24	45	15	18	8	45	49	54	49	49	49	47	43
4/25/19	47	17	21	34	0.95	7	0	38	48	54	49	49	46	46	44
5/1/19	47	7	14	40	0.85	11	0	38	49	52	49	48	40	47	27
5/13/19	46	11	1.2	23	35	6	0	44	49	54	49	49	49	48	33
5/22/19	44	6	15	29	32	11	0	35	49	48	48	48	48	45	29
5/29/19	48	16	21	50	13	7	1.5	37	48	52	49	48	39	48	43

Notes:

\*Some readings taken on 7/25/19 were unusually low, so resampled was conducted on 7/29/19

\* Originally monitoring probes converted to vents

TABLE 1.0 - LANDFILL GAS MONITORING RESULTS (CONT.)

(Reported as % methane gas by volume)

Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
6/5/19	48	23	10	40	20	13	0	43	48	53	47	47	47	47	35
6/12/19	48	3.25	1.7	39	13	7	0	43	48	52	47	47	49	45	38
6/19/19	48	18	21	40	24	8	0.45	45	48	53	48	48	44	48	39
6/26/19	23	8	7	31	19	6	0	44	46	52	48	46	43	45	29
7/3/19	47	18	16	49	16	7	1.65	47	48	53	49	48	47	47	41
7/10/19	48	12	24	42	3.2	7	1	46	48	52	49	47	44	47	32
7/18/19	48	27	32	47	27	31	8	43	48	54	49	47	40	49	37
7/25/2019*	14	0.85	0	0	0	6	0.2	12	19	31	29	39	31	25	0
7/29/2019*	12	0.45	4.5	0.05	0.1	10	0.15	8	0.9	3	0	0	23	9	0.05
8/7/19	48	8	17	36	19	4.2	1.25	33	48	53	48	44	40	45	29
8/14/19	44	1.9	0.25	29	4	4.85	0.75	31	45	53	49	43	38	38	24
8/21/19	45	1	1.4	29	5	1.5	0.2	24	36	45	48	38	30	38	24
8/28/19	32	0.15	0.05	21	1.6	0.55	0.9	38	37	48	44	35	29	38	19
9/6/19	44	3.85	6	36	7	4.7	0.4	43	38	47	45	34	35	35	27
9/11/19	36	0.2	0.7	23	5	2.2	0.1	17	25	39	43	33	31	24	17
9/27/19	44	6	4.25	43	17	3.4	4	35	36	44	47	34	16	42	32
10/3/19	35	0.15	1.45	27	4.1	5	0.95	29	34	46	41	32	31	25	20
10/10/19	44	4	16	40	19	6	4.4	28	37	44	49	34	39	42	36
10/16/19	25	4	0	4.25	0.1	2.75	1.5	29	33	46	43	29	49	44	33
10/23/19	40	11	7	28	8	0.95	0.05	45	38	44	43	34	44	38	24
11/1/19	35	8	10	22	12	0.8	0	31	39	40	41	33	37	34	26
11/8/19	32	0.1	0	11	0.2	3.95	0.2	30	39	30	41	36	50	36	10
11/15/19	30	1.55	1.6	14	1.45	0.95	0.2	45	41	46	41	36	43	37	12
11/20/19	48	13	16	26	10	1	0.8	39	43	33	23	38	43	43	12
11/27/19	47	2.35	0	2.65	0	2.5	0	39	46	39	34	43	40	25	18
12/4/19	44	5	7	22	4	2.1	0.45	32	45	43	45	41	34	30	11
12/14/19	49	5	18	34	7	1.05	2	27	40	46	49	43	39	44	54
12/18/19	19	0	5	11	0.45	0.85	0	33	41	43	38	37	39	33	11
1/2/20	49	7	12	14	7	6	3.75	24	47	38	49	43	28	41	17
1/8/20	43	6	15	23	5	1.6	0.6	47	47	47	46	37	41	43	25
1/15/20	46	41	8	24	4	0.6	0.5	17	43	45	45	37	42	29	12
1/23/20	49	10	16	23	3.45	2	1.85	40	45	44	48	43	37	36	17
1/31/20	37	4	0.7	7	0.7	2.7	0	31	27	39	48	33	39	22	5
2/6/20	47	6	9	23	5	1.7	1.3	48	49	50	51	46	47	44	19
2/12/20	49	11	12	28	8	3.4	0.6	36	39	43	51	45	40	44	17
2/19/20	31	0	1.9	14	0	4.4	0	46	49	51	47	42	40	37	16
2/27/20	35	0.2	12	17	33	1.25	0	40	48	52	43	40	42	38	17
3/5/20	10	0	0	4	0.15	0.4	0	24	31	45	45	41	30	28	3
3/11/20	49	14	23	33	20	2	1.2	50	48	52	50	42	44	46	28
3/19/20	49	10	19	33	13	4.4	0.9	49	48	49	49	43	38	44	32
3/26/20	50	11	21	38	7	2.5	0	41	48	52	50	45	46	47	39
4/16/20	44	10	14	30	23	8	0.45	50	48	43	49	45	44	48	30
4/29/20	34	0	0	0	0	1.8	0	39	39	33	37	41	23	14	0
5/23/20	10	0	0.7	0.1	0.05	4.3	0	6	3	10	0	0	32	0	0
6/10/20	12	0	0	12	0.15	4.45	0.3	37	49	42	47	43	42	31	10
6/25/20	15	0.15	0.05	0	1.6	4.2	0.25	12	10	11	18	15	23	25	0
7/15/20	44	2.1	40	30	5	1.2	0.3	26	43	36	45	32	47	37	23
8/7/20	46	2.3	3.5	39	4.3	0.15	0.2	33	41	43	44	38	38	42	24
8/24/20	43	1.1	1.25	29	4	0.1	4	36	40	42	44	35	46	40	24
9/18/20	40	2.75	3	27	2.65	9	0.2	47	35	39	38	28	41	37	24
9/30/20	33	9	1.2	22	1.8	1.05	0.05	46	35	43	40	28	37	36	21
10/23/20	31	0	1.25	7	3.2	0.5	0.15	26	23	23	37	25	30	28	8
11/19/20	36	1.5	2.35	22	2.4	0.65	0	33	21	32	30	21	31	24	17
12/17/20	25	0.9	0	14	0.75	1.4	0.05	44	36	36	37	33	44	32	11
1/15/21	21	0.06	0	13	0.21	2.1	0	47	45	21	43	45	44	36	7
2/10/21	52	9	2.9	31	10.00	3.75	0.35	53	51	50	50	44	49	48	34
3/26/21	39														

Notes:

\* Originally monitoring probes converted to vents

\*Some readings taken on 7/25/19 were unusually low, so resampled was conducted on 7/29/19

**TABLE 2.0 - QUARTERLY LANDFILL GAS MONITORING RESULTS**  
(2019 - 2020 & 1<sup>st</sup> Quarter 2021)

READING LOCATION	1 <sup>st</sup> Quarter 2019 (Date taken: 3/22/2019)		2 <sup>nd</sup> Quarter 2019 (Date taken: 6/19/2019)		3 <sup>rd</sup> Quarter 2019 (Date taken: 9/20/2019)		4 <sup>th</sup> Quarter 2019 (Date taken: 12/19/2019)		1 <sup>st</sup> Quarter 2020 (Date taken: 3/16/2020)		2 <sup>nd</sup> Quarter 2020 (Date taken: 6/25/2020)		3 <sup>rd</sup> Quarter 2020 (Date taken: 9/30/2020)		4 <sup>th</sup> Quarter 2020 (Date taken: 12/17/2020)		1 <sup>st</sup> Quarter 2021 (Date taken: 3/26/2021)			
	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume		
GMP																				
GMP-1	10:27AM	0	1:00PM	0	1:08PM	0	10:37AM	0	1:05PM	0	10:27AM	0	1:02PM	0	1:54PM	0	1:45PM	0		
GMP-2	11:09AM	0	1:09PM	0	1:13PM	0	10:41AM	0	1:10PM	0	10:11AM	0	1:09PM	0	1:08PM	0	1:47PM	0	1:47PM	0
GMP-3	11:08AM	0	1:25PM	0	1:21PM	4.3	10:48AM	2	1:16PM	0.11	10:33AM	0	1:48PM	0.1	4:13PM	1.4	4:13PM	0	3:54PM	0
GMP-4*	11:36AM	46	1:36PM	48	1:53PM	36	10:51AM	48	1:44PM	50	10:58AM	15	1:44PM	33	4:29PM	36	4:18PM	30	4:18PM	30
GMP-5	11:11AM	0	1:30PM	0	1:28PM	0	11:00AM	0	1:21PM	0	10:38AM	0	1:20PM	0	4:39PM	0	1:58PM	0	1:58PM	0
GMP-6	11:17AM	0	1:34PM	0	1:29PM	0	11:05AM	0	1:23PM	0	10:42AM	0	1:23PM	0	4:24PM	0	4:04PM	0	4:04PM	0
GMP-7	11:21AM	0	1:37PM	0	1:32PM	0	11:06AM	0	1:30PM	0	10:55AM	0	1:30PM	0	4:16PM	0	4:09PM	0	4:09PM	0
Site House																				
North Wall	2:08PM	0	1:16PM	0	2:20PM	0	11:17AM	0	3:15PM	0	11:40AM	0	2:59PM	0	3:30PM	0	3:25PM	0	3:25PM	0
East Wall	2:02PM	0	3:08PM	0	2:32PM	0	11:19AM	0	3:18PM	0	11:42AM	0	2:52PM	0	3:29PM	0	3:27PM	0	3:27PM	0
South Wall	2:04PM	0	3:20PM	0	2:36PM	0	11:21AM	0	3:20PM	0	11:44AM	0	2:56PM	0	3:34PM	0	3:29PM	0	3:29PM	0
West Wall	2:04PM	0	3:21PM	0	2:36PM	0	11:23AM	0	3:22PM	0	11:46AM	0	2:58PM	0	3:36PM	0	3:31PM	0	3:31PM	0
Maintenance Building																				
North Wall	2:13PM	0	3:23PM	0	2:33PM	0	11:28AM	0	3:23PM	0	11:48AM	0	2:43PM	0	3:38PM	0	3:33PM	0	3:33PM	0
East Wall	2:15PM	0	3:27PM	0	2:35PM	0	11:30AM	0	3:27PM	0	11:50AM	0	2:45PM	0	3:40PM	0	3:35PM	0	3:35PM	0
South Wall	2:17PM	0	3:29PM	0	2:37PM	0	11:32AM	0	3:29PM	0	11:52AM	0	2:47PM	0	3:42PM	0	3:37PM	0	3:37PM	0
West Wall	2:19PM	0	3:31PM	0	2:39PM	0	11:34AM	0	3:31PM	0	11:54AM	0	2:49PM	0	3:44PM	0	3:39PM	0	3:39PM	0
Comments	Weather: 76°F Cloudy Pressure: 29.11		Weather: 100°F Sunny Pressure: 29.90		Weather: 93°F Cloudy Pressure: 28.07		Weather: 52°F Sunny Pressure: 29.33		Weather: 84°F Sunny Pressure: 28.76		Weather: 66°F Sunny Pressure: 29.04		Weather: 86°F Sunny Pressure: 29.05		Weather: 62°F Sunny Pressure: 29.14		Weather: 87°F Sunny Pressure: 28.77			

**Notes:**  
 — Instrument/Make: GMI; Model: Gassurveyor 500 Series  
 — This form is to be completed for each quarterly monitoring event and for additional monitoring per LGRP  
 — Completed forms are to be filed with Site Operating Records; not to be submitted to TCEQ unless an exceedance reported  
 — Exceedance: greater than 5% methane (CH<sub>4</sub>) by volume in GMP, or 1.25% in Buildings.  
 — All readings should be recorded as % CH<sub>4</sub> by volume, not % LEL.  
 — Adapted from LPTM Form 8 & 9 Revised 3/10/18

\* Converted to Vent as part of LGRP

**TABLE 1.0 - QUARTERLY LANDFILL GAS MONITORING RESULTS**  
(2019 - 2020 & 1<sup>st</sup> Quarter 2021)

READING LOCATION	1 <sup>st</sup> Quarter 2019 (Date taken: 3/22/2019)		2 <sup>nd</sup> Quarter 2019 (Date taken: 6/19/2019)		3 <sup>rd</sup> Quarter 2019 (Date taken: 9/20/2019)		4 <sup>th</sup> Quarter 2019 (Date taken: 12/19/2019)		1 <sup>st</sup> Quarter 2020 (Date taken: 3/26/2020)		2 <sup>nd</sup> Quarter 2020 (Date taken: 6/25/2020)		3 <sup>rd</sup> Quarter 2020 (Date taken: 9/30/2020)		4 <sup>th</sup> Quarter 2020 (Date taken: 12/17/2020)		1 <sup>st</sup> Quarter 2021 (Date taken: 3/26/2021)	
	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume	Time	% CH <sub>4</sub> by volume
GMP																		
GMP-1	10:27AM	0	1:00PM	0	1:08PM	0	10:37AM	0	1:05PM	0	10:27AM	0	1:02PM	0	3:54PM	0	3:45PM	0
GMP-2	11:03AM	0	1:09PM	0	1:12PM	0	10:43AM	0	1:10PM	0	10:31AM	0	1:08PM	0	4:00PM	0	3:49PM	0
GMP-3	11:08AM	0	1:25PM	2	1:21PM	4.3	10:48AM	2	1:16PM	0.11	10:33AM	0	1:44PM	0.1	4:37PM	1.4	3:54PM	0
GMP-4*	11:26AM	46	1:56PM	48	1:43PM	36	10:53AM	48	1:44PM	50	10:58AM	15	1:44PM	33	4:29PM	36	4:19PM	39
GMP-5	11:13AM	0	1:30PM	0	1:25PM	0	11:00AM	0	1:21PM	0	10:58AM	0	1:20PM	0	4:09PM	0	3:58PM	0
GMP-6	11:17AM	0	1:34PM	0	1:29PM	0	11:05AM	0	1:25PM	0	10:42AM	0	1:25PM	0	4:12PM	0	4:03PM	0
GMP-7	11:21AM	0	1:37PM	0	1:32PM	0	11:10AM	0	1:30PM	0	10:45AM	0	1:30PM	0	4:16PM	0	4:05PM	0
Gate House																		
North Wall	2:00PM	0	3:16PM	0	2:30PM	0	11:17AM	0	3:16PM	0	11:40AM	0	2:30PM	0	3:30PM	0	3:25PM	0
East Wall	2:02PM	0	3:18PM	0	2:32PM	0	11:19AM	0	3:18PM	0	11:42AM	0	2:32PM	0	3:32PM	0	3:27PM	0
South Wall	2:04PM	0	3:20PM	0	2:36PM	0	11:21AM	0	3:20PM	0	11:44AM	0	2:36PM	0	3:34PM	0	3:29PM	0
West Wall	2:06PM	0	3:22PM	0	2:38PM	0	11:23AM	0	3:22PM	0	11:46AM	0	2:38PM	0	3:36PM	0	3:31PM	0
Maintenance Building																		
North Wall	2:13PM	0	3:25PM	0	2:43PM	0	11:28AM	0	3:25PM	0	11:48AM	0	2:43PM	0	3:38PM	0	3:33PM	0
East Wall	2:15PM	0	3:27PM	0	2:45PM	0	11:30AM	0	3:27PM	0	11:50AM	0	2:45PM	0	3:40PM	0	3:35PM	0
South Wall	2:17PM	0	3:29PM	0	2:47PM	0	11:32AM	0	3:29PM	0	11:52AM	0	2:47PM	0	3:42PM	0	3:37PM	0
West Wall	2:19PM	0	3:31PM	0	2:49PM	0	11:34AM	0	3:31PM	0	11:54AM	0	2:49PM	0	3:44PM	0	3:39PM	0
Comments:	Weather 76°F Cloudy Pressure: 29.11		Weather 100°F Sunny Pressure: 29.80		Weather 93°F Cloudy Pressure: 28.07		Weather 52°F Sunny Pressure: 29.33		Weather 84°F Sunny Pressure: 28.76		Weather 88°F Sunny Pressure: 29.04		Weather 86°F Sunny Pressure: 29.05		Weather 62°F Sunny Pressure: 29.14		Weather 87°F Sunny Pressure: 28.77	

**Notes:**

- \* Converted to vent as part of LGRP
- Instrument/Make: GMI; Model Gassurveyor 500 Series
- This form is to be completed for each quarterly monitoring event and for additional monitoring per LGMP
- Completed forms are to be filed with Site Operating Records, not to be submitted to TCEQ unless an exceedance reported
- Exceedance: greater than 5% methane (CH<sub>4</sub>) by volume in GMP, or 1.25% in Buildings
- All readings should be recorded as % CH<sub>4</sub> by volume, not % LEL
- Adapted from LPOTM Form 8 & 9 Revised 3/10/18

TABLE 2.0 - LANDFILL GAS MONITORING RESULTS

( Reported as % methane gas by volume)

Exceedance Action Plan - TGMP-1, TGMP2, and TGMP 3.1 - 3.3 Installed on May 2 and 3, 2018.															
Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3			
5/2/18	38	26				28									
5/3/18	37	15				31	10	12	47						
5/4/18	34	27				29	0	0	0						
5/7/18	0	31				27	0	0	0						
5/8/18	48	47				35	0	38	48	41	41	46			
5/9/18	49	50				27	0	15	38	42	45	47			
5/10/18	31	45				26	0	19	26	49	48	46			
5/11/18	48	46				22	11	44	48	53	52	48			
5/14/18	47	43				22	19	46	47	55	51	48			
5/15/18						23	14								
5/16/18								43	49						
Landfill Gas Remediation Plan Phase 1 - TV-1, TV-2 and TV-3 Installed on May 16, 2018.															
Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
5/17/18	48	48				35	23	44	50	47	52	49	0	29	12
5/18/18	49	45				33	25	41	50	52	53	49	0	33	8
5/22/18	47	47				31	0	40	49	56	52	47	8	28	6
5/23/18	42	37				30	0	31	49	55	50	47	9	20	0
5/24/18	41	34				28	0	33	50	54	50	47	6	24	7
5/25/18	49	49				33	0	43	50	55	52	48	9	42	18
5/29/18	48	45	50	47	51	38	0	42	50	56	52	49	5	25	12
5/30/18	47	42	43	41	36	23	46	27	50	54	52	49	0	29	13
5/31/18	37	27	32	26	32	29	0	30	50	55	52	48	5	33	11
6/1/18	6	16	10	0	28	29	0	13	48	52	45	46	0	5	0
6/4/18	47	38	48	36	19	25	6	35	50	57	52	49	8	38	42
6/5/18	49	49	52	48	46	25	29	37	50	57	52	56	10	30	30
6/6/18	48	48	51	47	22	23	33	35	49	51	48	47	8	35	41
6/7/18	30	25	8	21	8	28	21	28	49	57	52	47	0	19	0
6/8/18	32	14	15	28	0	19	0	29	50	52	43	43	0	17	5
6/11/18	48	46	57	20	46	4.6	11	44	31	51	53	48	31	48	10
6/12/18	43	28	17	36	36	4	12	13	50	38	45	47	24	42	36
6/13/18	38	32	17	23	16	4	0.03	37	48	38	48	47	22	43	28
6/14/18	47	12	41	43	24	3.4	9	36	50	58	51	48	28	47	9
6/15/18	48	25	49	47	33	2	13	29	49	53	25	41	30	47	44
6/18/18	48	26	45	45	27	5	7	37	47	54	52	47	32	47	43
6/19/18	48	34	46	48	26	5	10	32	48	55	52	47	30	42	27
6/20/18	48	33	15	34	9	5	0	28	48	56	53	47	28	46	44
6/21/18	42	0	0	29	9	5	0	22	48	55	51	47	26	46	32
6/22/18	46	48	23	42	46	0.08	1.3	26	47	55	51	46	27	41	40
6/25/18	36	1.5	6	19	1	1.2	0	9	45	43	51	47	22	43	26
6/26/18	33	0.05	9	28	0.7	0.25	0	10	48	55	51	47	23	44	32
6/27/18	45	0.15	21	42	13	1.25	0	17	46	53	52	46	24	45	32
6/28/18	43	1.4	18	45	14	0.75	1.65	28	47	54	53	46	24	44	37
6/29/18	44	1.5	21	45	10	0.5	2.35	27	47	50	53	45	22	45	41
7/2/18	38	0.15	34	34	19	8	1.3	17	48	48	52	46	21	44	37
7/3/18	43	0.6	36	43	26	0.6	0.15	30	48	54	52	46	21	30	37
7/5/18	15	0	0	12	8	1.35	0.01	0.13	20	41	46	44	19	30	14
7/6/18	34	0	23	28	0.75	0.2	0	21	45	52	49	43	30	42	30
7/9/18	31	2.35	44	25	9	1.05	0	10	44	52	48	41	28	41	11
7/10/18	41	1.2	24	39	6	0.95	1.1	24	45	54	51	42	29	43	36
7/11/18	45	3.05	22	46	32	1.25	1.1	19	46	53	51	43	30	45	29
7/12/18	43	4	25	35	14	0.3	0.6	15	45	54	50	43	30	44	30
7/13/18	39	1.5	18	30	9	1.1	0.35	15	42	54	49	43	30	43	33
7/16/18	40	2	24	30	16	0.45	0.5	14	45	55	50	44	27	44	31

Notes:

\* Originally monitoring probes converted to vents

**TABLE 2.0 - LANDFILL GAS MONITORING RESULTS (CONT.)**

( Reported as % methane gas by volume)

Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
7/17/18	32	8	17	0	38	1.2	5	6	17	48	50	43	12	15	1.75
7/18/18	44	2.3	26	29	34	0.95	0.7	17	46	56	48	44	29	47	32
7/19/18	44	21	23	47	29	0.6	2.75	24	43	53	53	45	24	45	33
7/20/18	44	43	18	35	5	0.8	1	28	46	57	52	45	31	45	30
7/23/18	46	6	20	48	16	0.6	2	15	45	55	53	46	33	46	20
7/24/18	41	3.1	29	32	30	1.15	2	22	45	54	45	44	16	29	25
7/25/18	40	0.45	20	29	3	0.35	0.1	23	46	56	48	44	32	44	26
7/26/18	43	2.4	22	35	4	2.1	0.15	9	45	54	49	44	27	37	31
7/27/18	41	1	13	27	5	0.65	0.45	11	45	54	51	44	28	45	30
7/30/18	45	17	31	42	37	4.7	8	14	46	55	50	44	17	36	27
7/31/18	29	0.15	6	23	6	0.2	0.02	9	24	46	49	43	19	31	12
8/1/18	44	11	38	40	20	0.1	11	19	30	56	54	45	17	36	20
8/2/18	41	12	27	38	35	0.3	10	20	45	57	52	43	33	45	30
8/8/18	36	0	7	28	12	0.25	1.2	2.95	40	50	47	42	29	43	27
8/15/18	31	17	6	27	11	1.25	8	7	40	53	46	43	20	30	13
8/22/18	36	0.15	21	28	2.75	0.2	0.4	18	45	55	49	45	30	43	25
8/29/18	36	0.6	19	27	5	1.25	0.8	48	51	46	9	46	19	40	26
9/6/18	44	17	15	29	8	0.5	1.05	8	40	47	50	43	21	30	24
9/13/18	49	25	20	40	18	0.4	0.9	30	48	51	48	50	29	48	26
9/20/18	39	16	16	35	11	0.85	1.5	23	46	46	40	42	24	42	23
9/27/18	49	6	28	37	5	0.25	1	38	51	56	52	51	46	50	35
10/3/18	49	6	18	46	15	0.6	0.05	34	49	47	12	50	41	48	40
10/11/18	45	4.7	10	25	1.45	0.25	1.15	21	50	40	50	50	31	48	24
10/17/18	51	5	15	22	2.85	1.6	0	45	52	55	52	51	49	49	22
10/30/18	50	19	20	50	15	0.4	0.7	35	50	55	52	51	24	50	38
11/7/18	50	7	19	40	3.25	0.05	0	23	50	53	51	51	39	50	27
11/15/18	51	15	23	36	10	1.15	0.15	37	52	57	52	49	45	51	37
11/27/18	41	7	18	28	10	2.75	0.05	41	53	55	50	50	48	48	35
12/6/18	49	10	20	15	5	1.75	0.5	19	48	48	52	49	38	50	37
12/13/18	0	0	0	0	0	1.8	0	0	0	0	0	0.05	38	0	0
12/14/18	15	0	0.05	4.15	0	0.9	0	17	25	0.05	0.15	54	40	39	18
12/21/18	47	12	28	32	19	1.5	15	53	25	48	51	51	48	49	41
12/26/18	51	14	23	50	16	6	0	45	51	56	52	51	50	50	36
1/4/19	52	6	28	31	10	2.4	0	27	52	53	53	52	40	50	27
1/11/19	53	14	21	47	10	11	0	52	52	57	54	52	52	52	48
1/16/19	52	15	19	44	13	9	7	39	52	57	53	52	45	51	41
1/23/19	13	0	12	40	10	3	0.65	38	38	57	47	46	43	35	46
1/30/19	40	6	20	41	11	7	0	28	51	56	47	49	42	47	38
2/6/19	50	35	45	49	37	12	23	41	50	54	51	50	30	49	37
2/15/19	50	13	20	48	12	5	0	35	50	55	50	55	48	49	36
2/20/19	42	16	36	30	17	30	15	37	51	55	51	50	35	46	30
2/28/19	47	4	13	27	1	7	2.15	17	47	29	33	50	39	48	23
3/7/19	49	15	22	31	1.4	6	1.4	32	50	52	51	49	44	49	46
3/15/19	1.75	0	0	1.7	0	4.45	0	14	51	0	45	38	36	24	6
3/22/19	46	5	26	42	11	9	8	15	45	18	49	48	44	48	45
3/29/19	49	12	26	48	12	9	6	20	49	41	50	48	44	48	44
4/5/19	48	32	48	45	23	20	18	46	44	48	50	47	32	48	40
4/12/19	40	5	11	30	9	3.5	0.6	45	49	54	49	47	48	45	34
4/17/19	47	20	24	45	15	18	8	45	49	54	49	47	49	47	43
4/25/19	47	17	21	34	0.95	7	0	38	48	54	49	49	46	46	44
5/1/19	47	7	14	40	0.85	11	0	38	49	52	49	48	40	47	27
5/13/19	46	11	1.2	23	35	6	0	44	49	54	49	49	49	48	33
5/22/19	44	6	15	29	32	11	0	35	49	48	48	48	48	45	29
5/29/19	48	16	21	50	13	7	1.5	37	48	52	49	48	39	48	43

Notes:

\* Originally monitoring probes converted to vents

TABLE 2.0 - LANDFILL GAS MONITORING RESULTS (CONT.)




( Reported as % methane gas by volume)

Date	GMP-4*	BGMP-4.1	BGMP-4.2*	BGMP-4.3*	BGMP-4.4	MW-11	BGMP-12.1	TGMP #2	TGMP #1	TGMP-3.1	TGMP-3.2	TGMP-3.3	TV-1	TV-2	TV-3
6/5/19	48	23	10	40	20	13	0	43	48	53	47	47	47	47	35
6/12/19	48	3.25	1.7	39	13	7	0	43	48	52	47	47	49	45	38
6/19/19	48	18	21	40	24	8	0.45	45	48	53	48	48	44	48	39
6/26/19	23	8	7	31	19	6	0	44	46	52	48	46	43	45	29
7/3/19	47	18	16	49	16	7	1.65	47	48	53	49	48	47	47	41
7/10/19	48	12	24	42	3.2	7	1	46	48	52	49	47	44	47	32
7/18/19	48	27	32	47	27	31	8	43	48	54	49	47	40	49	37
7/25/2019**	14	0.85	0	0	0	6	0.2	12	19	31	29	39	31	25	0
7/29/2019**	12	0.45	4.5	0.05	0.1	10	0.15	8	0.9	3	0	0	23	9	0.05
8/7/19	48	8	17	36	19	4.2	1.25	33	48	53	48	44	40	45	29
8/14/19	44	1.9	0.25	29	4	4.85	0.75	31	45	53	49	43	38	38	24
8/21/19	45	1	1.4	29	5	1.5	0.2	24	36	45	48	38	30	38	24
8/28/19	32	0.15	0.05	21	1.6	0.55	0.9	38	37	48	44	35	29	38	19
9/6/19	44	3.85	6	36	7	4.7	0.4	43	38	47	45	34	35	35	27
9/11/19	36	0.2	0.7	23	5	2.2	0.1	17	25	39	43	33	31	24	17
9/27/19	44	6	4.25	43	17	3.4	4	35	36	44	47	34	16	42	32
10/3/19	35	0.15	1.45	27	4.1	5	0.95	29	34	46	41	32	31	25	20
10/10/19	44	4	16	40	19	6	4.4	28	37	44	49	34	39	42	36
10/16/19	25	4	0	4.25	0.1	2.75	1.5	29	33	46	43	29	49	44	33
10/23/19	40	11	7	28	8	0.95	0.05	45	38	44	43	34	44	38	24
11/1/19	35	8	10	22	12	0.8	0	31	39	40	41	33	37	34	26
11/8/19	32	0.1	0	11	0.2	3.95	0.2	30	39	30	41	36	50	36	10
11/15/19	30	1.55	1.6	14	1.45	0.95	0.2	45	41	46	41	36	43	37	12
11/20/19	48	13	16	26	10	1	0.8	39	43	33	23	38	43	43	12
11/27/19	47	2.35	0	2.65	0	2.5	0	39	46	39	34	43	40	25	18
12/4/19	44	5	7	22	4	2.1	0.45	32	45	43	45	41	34	30	11
12/14/19	49	5	18	34	7	1.05	2	27	40	46	49	43	39	44	54
12/18/19	19	0	5	11	0.45	0.85	0	33	41	43	38	37	39	33	11
1/2/20	49	7	12	14	7	6	3.75	24	47	38	49	43	28	41	17
1/8/20	43	6	15	23	5	1.6	0.6	47	47	47	46	37	41	43	25
1/15/20	46	41	8	24	4	0.6	0.5	17	43	45	45	37	42	29	12
1/23/20	49	10	16	23	3.45	2	1.85	40	45	44	48	43	37	36	17
1/31/20	37	4	0.7	7	0.7	2.7	0	31	27	39	48	33	39	22	5
2/6/20	47	6	9	23	5	1.7	1.3	48	49	50	51	46	47	44	19
2/12/20	49	11	12	28	8	3.4	0.6	36	39	43	51	45	40	44	17
2/19/20	31	0	1.9	14	0	4.4	0	46	49	51	47	42	40	37	16
2/27/20	35	0.2	12	17	33	1.25	0	40	48	52	43	40	42	38	17
3/5/20	10	0	0	4	0.15	0.4	0	24	31	45	45	41	30	28	3
3/11/20	49	14	23	33	20	2	1.2	50	48	52	50	42	44	46	28
3/19/20	49	10	19	33	13	4.4	0.9	49	48	49	49	43	38	44	32
3/26/20	50	11	21	38	7	2.5	0	41	48	52	50	45	46	47	39
4/16/20	44	10	14	30	23	8	0.45	50	48	43	49	45	44	48	30
4/29/20	34	0	0	0	0	1.8	0	39	39	33	37	41	23	14	0
5/23/20	10	0	0.7	0.1	0.05	4.3	0	6	3	10	0	0	22	0	0
6/10/20	12	0	0	12	0.15	4.45	0.3	37	49	42	47	43	42	31	10
6/25/20	15	0.15	0.05	0	1.6	4.2	0.25	12	10	11	18	15	23	25	0
7/15/20	44	2.1	40	30	5	1.2	0.3	26	43	36	45	32	47	37	23
8/7/20	46	2.3	3.5	39	4.3	0.15	0.2	33	41	43	44	38	38	42	24
8/24/20	43	1.1	1.25	29	4	0.1	4	36	40	42	44	35	46	40	24
9/18/20	40	2.75	3	27	2.65	9	0.2	47	35	39	38	28	41	37	24
9/30/20	33	9	1.2	22	1.8	1.05	0.05	46	35	43	40	28	37	36	21
10/23/20	31	0	1.25	7	3.2	0.5	0.15	26	23	23	37	25	30	28	8
11/19/20	36	1.5	2.35	22	2.4	0.65	0	33	21	32	30	21	31	24	17
12/17/20	25	0.9	0	14	0.75	1.4	0.05	44	36	36	37	33	44	32	11
1/15/21	21	0.06	0	13	0.21	2.1	0	47	45	21	43	45	44	36	7
2/10/21	52	9	2.9	31	10.00	3.75	0.35	53	51	50	50	44	49	48	34
3/26/21	39														



Notes:



\* Originally monitoring probes converted to vents

\*\*Some readings taken on 7/25/19 were unusually low, so resampled was conducted on 7/29/19



\*Some readings taken on 7/27/19 were manually low as recorded on 7/29/19 (14.0% shown instead of 10.0% shown) and 8/1/19 (14.0% shown instead of 10.0% shown) as indicated.





\*New analytical station 72317 was installed for monitoring the methane on 7/27/19. On 7/27/19, the methane concentration was 10.4%.

CHART 1.8 - TGM #2 Monitoring Results











CHART 1.9 - TGM #1 Monitoring Results







# Landfill Gas Remediation Plan

Dated September 2, 2022

Jon Niermann, *Chairman*  
Emily Lindley, *Commissioner*  
Bobby Janecka, *Commissioner*  
Toby Baker, *Executive Director*



## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

*Protecting Texas by Reducing and Preventing Pollution*

September 22, 2022

Mr. Juan Zamora  
Public Works Director  
City of Uvalde  
P.O. Box 799  
Uvalde, Texas 78802-0799

Via Email

Re: City of Uvalde Landfill - Uvalde County  
Municipal Solid Waste (MSW) - Permit No. 1725  
Landfill Gas Remediation Plan for GMP-4 - September 2, 2022  
Tracking No. 27810539; RN102803921/CN600648455

Dear Mr. Zamora:

We received your Landfill Gas Remediation Plan for GMP-4 for the above-referenced facility on September 12, 2022. The plan was dated September 2, 2022 and prepared on your behalf by Dr. Brett DeVries, Ph.D., P.E. of SCS Engineers, Bedford. The update responds to our letter dated October 28, 2021 on your methane monitoring results for the 3rd quarter of 2021.

We have the following comments:

1. We have not received quarterly or monthly methane monitoring data for 2022.
2. We have not received monthly methane concentrations newer than February 2021 despite our requests dated May 10, 2021, October 28, 2021, and April 1, 2022 and your references to monthly monitoring in your May 2021 update and January 2022 update.
3. Methane concentrations along the property line north of at least Phase B continue to exceed the regulatory limit of 5% defined in 30 TAC §330.371(a)(2) in spite of the additional gas vents installed in Phases A and B during August 2019.

Please do the following as requested in our letter dated April 1, 2022 on your Landfill Gas Remediation Plan Update dated January 17, 2022:


- Define the extent of methane concentrations above 5% in the ground by monitoring west of TGMP-2 and east of BGMP-4.4 as you proposed in your May 2021 update.
- As noted in your Landfill Gas Management Plan approved February 27, 2017, submit a permit modification under 30 TAC §305.70(k)(3) to update your Landfill Gas Management Plan.
  - a. Include the locations and construction details of landfill gas monitoring points and vents added since 2016.
  - b. Include your Landfill Gas Remediation Plan dated May 8, 2018.
  - c. Include your Landfill Gas Remediation Plan for GMP-4 dated September 2, 2022.

Mr. Juan Zamora  
Page 2  
September 22, 2022

You should continue landfill gas remediation activities under 30 TAC §330.371(c) without waiting to submit or receive approval of your upcoming permit modification.

If you have questions regarding this letter, please contact me at (512) 239-2580 or in writing at either [robert.pedersen@tceq.texas.gov](mailto:robert.pedersen@tceq.texas.gov) or the address on our letterhead (please include mail code MC 124 on the first line).

Sincerely,

A handwritten signature in black ink, appearing to read "Robert C. Pedersen". The signature is fluid and cursive, with a long horizontal stroke at the end.

Robert C. Pedersen, P.E., Project Manager  
Municipal Solid Waste Permits Section  
Waste Permits Division  
Texas Commission on Environmental Quality

RCP/tw

cc: Dr. Brett DeVries, Ph.D., P.E., SCS Engineers, Bedford  
Dr. Stephen Forbes, Ph.D., P.E., P.G., Forbes Environmental Engineering, San Antonio

September 2, 2022  
SCS Project No. 16222029.00

Mr. Charlie Fritz  
Section Manager  
MSW Permits Section (MC-124)  
Texas Commission on Environmental Quality  
12100 Park 35 Circle, Bldg. F  
Austin, Texas 78753

Re: Landfill Gas Remediation Plan for GMP-4  
City of Uvalde Landfill – Permit No. MSW-1725  
Uvalde County, Texas  
RN102803921/CN600648455

Dear Mr. Fritz:

On behalf of the City of Uvalde Landfill, SCS Engineers (SCS) is providing this letter to the Texas Commission on Environmental Quality (TCEQ) as a continuation and update of the landfill gas (LFG) remediation plan (LGRP) for perimeter gas monitoring probe GMP-4 (dated May 8, 2018) and TCEQ letter dated October 28, 2021 (Tracking No. 26649876) for the City of Uvalde Landfill (MSW-1725).

The prior LGRP was dated May 8, 2018 and developed by Forbes Environmental Engineering & Associates. As indicated in the plan, methane concentrations above the regulatory limit (i.e., five (5) percent by volume methane in accordance with 30 Texas Administrative Code (TAC) §330.371(a)(2)) was detected in gas monitoring probe GMP-4 during a quarterly gas probe monitoring event on March 8, 2018.

Following the May 2018 LGRP and generally consistent with the plan, the following remediation efforts were completed:

- Monitoring of methane in the GMPs, gas monitoring vents (GMV), backup gas monitoring probes (BGMP), temporary gas monitoring probes (TGMP), temporary vents (TV), monitoring wells (MW) in proximity to GMP-4 on an at least monthly basis (see Drawing No. 1 for approximate locations). Monitoring results were provided in the response to TCEQ's letter dated October 28, 2021.
- Phase 1.0 of the LGRP: installation of three, 2-inch vents on a general 200 foot spacing, with the vents screened in the upper Uvalde Gravel with a 10-foot riser to intercept and divert the gas before reaching the primary remediation probes.
- Phase 2.0 of the LGRP: five, PVC passive vents in Stage B (Subtitle D area) screened to approximately one foot above bottom liner were installed in August 2019.

As indicated in the response to TCEQ's letter dated October 28, 2021, the size of the LFG plume has decreased following installation of TV-1, 2, and 3, and conversion of BGMP-4.0, 4.2, and 4.3 to vents; however, methane concentrations above the regulatory limit remain in GMP-4; BGMP-4.1, 4.3, and

4.4; TGMP-1, 2, 3.1, 3.2, 3.3; and TV-1, 2, and 3 as of February 2021. As a result of methane concentration readings above the regulatory limit, this plan documents remediation efforts to be implemented in an effort to mitigate methane concentrations above the regulatory limit in GMP-4.

## LFG Remediation Plan

As described above, the City has conducted remediation efforts for GMP-4, and vents/probes near GMP-4 have been monitored on at least monthly basis to evaluate the effects of the remediation efforts. Additionally, the City will perform further remediation efforts in 2022/2023 and 2023/2024, as necessary, to mitigate methane levels above the regulatory limit in GMP-4 as discussed in the subsequent sections.

Based on review of historical information and existing site conditions, it is believed that the LFG migration is originating from the Pre-Subtitle D area (Stage A), and potentially migrating along and under the GCL installed in Stage A and Subtitle D liner installed in Stage B where a separation berm between Stage A and B was constructed. As a result, the remediation efforts proposed in the subsequent sections focus on controlling LFG at the edge of the GCL in Stage A. Internal gas pressure is known to be a driving force behind LFG migration. As such, the proposed remediation efforts focuses on extracting LFG from its source (i.e., the landfill), relieving pressure buildup and reducing the potential of LFG migration.

## Passive Gas System Installation, Monitoring, and Evaluation

To continue the remediation efforts at the landfill, the City will proceed with a two phase approach (Phase 3.0 and 4.0). Phase 3.0 will be completed in 2022 or beginning of 2023 and Phase 4.0 will be completed following the Phase 3.0 evaluation period (anticipated in forth quarter of 2023 or beginning of 2024, if needed). Details related to Phases 3.0 and 4.0 are described below:

- **Phase 3.0:** installation of four passive LFG extraction wells east of the GCL termination in Stage A on the north side of the landfill (nearest the LFG migration). These four wells will be connected by lateral piping and routed to blowers and solar vent flares. The permit level plan-view and detail drawings are provided in Attachment A. Following completion of construction, methane concentrations will be monitored on a monthly basis in GMP-4, BGMP-4, TGMP-3.1, 3.2, and 3.3, and TGMP-2 for a twelve-month evaluation period. If these probes are not able to demonstrate six consecutive monthly readings below the regulatory limit, then the City will continue with Phase 4.0.
- **Phase 4.0:** installation of three passive LFG extraction wells east of the GCL termination in Stage A, south of the Phase 3.0 extraction wells. These three wells will be connected by lateral piping and routed to a blower and solar vent flare. The permit level plan-view and detail drawings are provided in Attachment A. Following completion of construction, methane concentrations will be monitored on a monthly basis in GMP-4, BGMP-4.4, TGMP-3.1, 3.2, and 3.3, and TGMP-2 for a twelve-month evaluation period. If these probes are not able to demonstrate six consecutive monthly readings below the regulatory limit, then the City will pursue other remediation efforts and an update to this remediation plan will be submitted to TCEQ.

Following completion of Phase 3.0 and/or 4.0, methane concentrations will be monitored on a monthly basis in GMP-4, BGMP-4.4, TGMP-3.1, 3.2, and 3.3, and TGMP-2, and results will be submitted to

Mr. Charlie Fritz  
September 2, 2022  
Page 3

TCEQ on a quarterly basis. If GMP-4 is able to demonstrate six consecutive monthly readings below the regulatory limit, then the probe will be considered remediated and will return to quarterly monitoring.

As described in the May 2018 LGRP, a permit modification of the Landfill Gas Management Plan (LGMP) will be submitted to TCEQ in accordance with 30 TAC §305.70(k)(3), to incorporate the remediation efforts into the LGMP once remediation efforts have been completed.

## Closing

One original and two copies of this plan are provided for your use and distribution. In addition, a copy has been provided to the TCEQ Region 13 office and placed in the site operations record. If you have any questions or need additional information, please contact Brett DeVries, Ph.D., P.E. at (817) 358-6110.

Sincerely,



Brett DeVries, Ph.D., P.E.  
Project Manager  
SCS Engineers  
TBPE Registration No. F-3407

Ryan Kuntz, P.E.  
Vice President / Satellite Office Manager  
SCS Engineers

## Attachment

cc: Mr. Juan Zamora – Director of Public Works, City of Uvalde  
Mr. Stephen Forbes, Ph.D., P.E., P.G.  
TCEQ Region 13

**ATTACHMENT A**  
**PASSIVE GAS SYSTEM DRAWINGS**






Appendix C  
Vertical Extraction Vents/Wells



**GAS EXTRACTION WELL INSTALLATION RECORD**

<b>Project Name</b>	<b>Uvalde Stage 1 LFG Remediation Effort</b>		
<b>Project Number:</b>	16222099.00	<b>Boring Depth</b>	41
<b>Date</b>	8/1/2023	<b>Boring Diameter</b>	36
<b>CQA Technician</b>	J Lewallen	<b>Pipe Spec.</b>	SDR 11 HDPE
<b>Well Number ID</b>	GV-11	<b>Pipe Diameter</b>	6"




NOTES:



**GAS EXTRACTION WELL INSTALLATION RECORD**

<b>Project Name</b>	<b>Uvalde Stage 1 LFG Remediation Effort</b>		
<b>Project Number:</b>	16222099.00	<b>Boring Depth</b>	40
<b>Date</b>	8/1/2023	<b>Boring Diameter</b>	36"
<b>CQA Technician</b>	J Lewallen	<b>Pipe Spec.</b>	HDPE SDR 11
<b>Well Number ID</b>	GV-12	<b>Pipe Diameter</b>	6"




NOTES:	



**GAS EXTRACTION WELL INSTALLATION RECORD**

<b>Project Name</b>	<b>Uvalde Stage 1 LFG Remediation Effort</b>		
<b>Project Number:</b>	16222099.00	<b>Boring Depth</b>	48
<b>Date</b>	8/1/2023	<b>Boring Diameter</b>	36"
<b>CQA Technician</b>	J Lewallen	<b>Pipe Spec.</b>	HDPE SDR 11
<b>Well Number ID</b>	GV-13	<b>Pipe Diameter</b>	6"




NOTES:



**GAS EXTRACTION WELL INSTALLATION RECORD**

<b>Project Name</b>	<b>Uvalde Stage 1 LFG Remediation Effort</b>		
<b>Project Number:</b>	16222099.00	<b>Boring Depth</b>	48
<b>Date</b>	8/2/2023	<b>Boring Diameter</b>	36"
<b>CQA Technician</b>	J Lewallen	<b>Pipe Spec.</b>	HDPE SDR 11
<b>Well Number ID</b>	GV-14	<b>Pipe Diameter</b>	6"



NOTES: