

Administrative Package Cover Page

This file contains the following documents:

- 1. Summary of application (in plain language)
- 2. First Notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
- 3. Application Materials

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Lajitas Municipal Services Company LLC (CN-603406604) operates the Lajitas Water Treatment Plant (RN-102079365) a 0.3mgd groundwater treatment EDR membrane drinking water plant. The facility is located about 500 feet south of SH-170 and about 0.13 miles southeast of the intersection of Comanche Mesa Drive and Texas Mountain Trail, in the unincorporated resort community town of Lajitas, Brewster County, Texas, 79852. Lajitas is proposing to dispose of membrane wastewater by irrigation on the Lajitas Golf Course. This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are concentrated from the Santa Elena source aquifer, and include chloride, sulfate, iron, calcium, other typical groundwater mineral, and naturally occurring radioactive material (NORM) constituents present in the source aquifer. The source water is treated by electro-dialysis reversal (EDR) membranes to produce a safe drinking water supply, and the process wastewater contains only the source water concentrates.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT

PROPOSED PERMIT NO. WQ0005496000

APPLICATION. Lajitas Municipal Services Company LLC, 14241 Dallas Parkway, Suite 800, Dallas, Texas 75254, which owns a water treatment plant, has applied to the Texas Commission on Environmental Quality (TCEQ) for proposed Texas Land Application Permit (TLAP) No. WQ0005496000 to authorize the disposal of treated wastewater at a volume not to exceed a daily average flow of 65,000 gallons per day via irrigation on 53.6 acres of land. The facility and disposal area will be located approximately 0.13 miles southeast of the intersection of Comanche Mesa Drive and Texas Mountain Trail, near the city of Lajitas, in Brewster County, Texas 79852. Authorization to discharge was previously permitted by expired Permit No. WQ0004378000. TCEQ received this application on July 14, 2025. The permit application will be available for viewing and copying at Big Bend State Par, Barton Warnock Center, 21800 Farm-to-Market Road 170, Terlingua, Texas prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-103.7708,29.261388&level=18

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. Notice of the Application and Preliminary Decision will be published and mailed to those who are on the countywide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a

response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at https://www14.tceq.texas.gov/epic/eComment/, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will

become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from Lajitas Municipal Services Company LLC at the address stated above or by calling Scott Vetter, Facilities Manager/Lajitas Golf Resort, at 281-467-3467.

Issuance Date: September 3, 2025

From: Mark Roetzel
To: Abesha Michael

Cc: Ron Holmes; Scott Vetter; R. Gary Call

Subject: Lajitas Municipal Services Company - Permit Application Public Viewing Location

Date: Wednesday, September 3, 2025 9:20:12 AM

Attachments: <u>image001.jpg</u>

Abesha:

Thanks for visiting with me to discuss the LMSC permit application public viewing location. We have confirmed with the facility superintendent that the application can be displayed for public viewing at:

Big Bend State Park Barton Warnock Center 21800 FM 170, Terlingua, TX 79852 (432) 424-3327

I understand that this will now allow the application to be declared Administratively Complete. Please advise if you need any additional information.

Mark Roetzel, P.E., RPLS, CFM Utility Services Manager



100 NE Loop 410, Ste. 300 | San Antonio, TX 78216 -TBPE No. F-1733 | TBPLS No. 100495-0 O: (210) 581-1111 | C: (210) 867-8323 www.CDSMuery.com

Connect with us: LinkedIn | Facebook | Instagram

From: Mark Roetzel

To: Abesha Michael; ron@theholmesfirm.com

Subject: RE: Application for Proposed Permit No. WQ0005496000 - Notice of Deficiency Letter

Date: Monday, August 11, 2025 1:06:07 PM

Attachments: Attachments.txt

Abesha:

We have uploaded the updated TLAP application to the TCEQ portal (<u>WQ-ARPTeam@tceq.texas.gov</u>) and are attaching here also for your review addressing your NOD letter comments below. The updated MS-Word, Avery 6150 Landowners' Addresses are also attached.

Regarding the NORI, we offer only the following requested revision. At the text new reading "....near/in the city of (Pending -name of city)," please revise to ".....near/in the unincorporated resort community of Lajitas, Brewster County, Texas 79852."

Please advise if you need any additional information to complete the administrative completeness review. Thanks.

ShareFile Attachments	Expires November 9, 2025
Lajitas WTP - TLAP Application, 8-25.pdf	16.1 MB
TCEQ Landowners' List, 6-25.docx	14.3 KB
Download Attachments	
Mark Roetzel uses ShareFile to share documents securely	<i>r</i> .

Mark Roetzel, P.E., RPLS, CFM Utility Services Manager



From: Abesha Michael <Abesha.Michael@tceq.texas.gov>

Sent: Wednesday, July 23, 2025 1:35 PM

To: ron@theholmesfirm.com

Cc: Mark Roetzel <mark.roetzel@cdsmuery.com>

Subject: Application for Proposed Permit No. WQ0005496000 - Notice of Deficiency Letter

You don't often get email from abesha.michael@tceq.texas.gov. Learn why this is important

Dear Ron Holmes:

The attached Notice of Deficiency letter sent on July 23, 2025, requests additional information needed to declare the application administratively complete. Please send the complete response to my attention by August 6, 2025.

Thank you,



Abesha H. Michael Applications Review & Processing Team Water Quality Division Support Section Water Quality Division, MC 148 PO Box 13087

Austin, Texas 78711 Phone: 0: 512-239-4912

Email: abesha.michael@tceq.texas.gov

How is our customer service? Fill out our online customer satisfaction survey at www.tceq.texas.gov/customersurvey

Lajitas Municipal Services Company LLC 14241 Dallas Parkway, Ste 800 Dallas, Texas 75254

Water Treatment Plant
TLAP Permit Application
July, 2025



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION CHECKLIST

Complete and submit this checklist with the industrial wastewater permit application.

APPLICANT NAME: <u>Lajitas Municipal Services Company LLC</u>
PERMIT NUMBER (If new, leave blank): WQ00 Click to enter text.

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0			Worksheet 8.0		\boxtimes
Administrative Report 1.1	\boxtimes		Worksheet 9.0		
SPIF		\boxtimes	Worksheet 10.0		\boxtimes
Core Data Form	\boxtimes		Worksheet 11.0		
Summary of Application (PLS)			Worksheet 11.1		
Public Involvement Plan Form	\boxtimes		Worksheet 11.2		\boxtimes
Technical Report 1.0	\boxtimes		Worksheet 11.3		
Worksheet 1.0		\boxtimes	Original USGS Map	\boxtimes	
Worksheet 2.0		\boxtimes	Affected Landowners Map	\boxtimes	
Worksheet 3.0			Landowner Disk or Labels	\boxtimes	
Worksheet 3.1	\boxtimes		Flow Diagram	\boxtimes	
Worksheet 3.2		\boxtimes	Site Drawing	\boxtimes	
Worksheet 3.3		\boxtimes	Original Photographs	\boxtimes	
Worksheet 4.0			Design Calculations		\boxtimes
Worksheet 4.1			Solids Management Plan		
Worksheet 5.0		\boxtimes	Water Balance	\boxtimes	
Worksheet 6.0		\boxtimes			
Worksheet 7.0		\boxtimes			
For TCEQ Use Only					

County

Expiration Date ______Region _____

Segment Number

ermit Number



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

This report is required for all applications for TPDES permits and TLAPs, except applications for oil and gas extraction operations subject to 40 CFR Part 435. Contact the Applications Review and Processing Team at 512-239-4671 with any questions about completing this report.

Applications for oil and gas extraction operations subject to 40 CFR Part 435 must use Oil and Gas Exploration and Production Administrative Report (TCEO Form-20893 and 20893-inst).

It	em 1.	Applicat	ion Informa	tion and Fees (Instructions, Page 26)			
a.	Comple	te each field	with the reque	sted information, if applicable.			
	Applica	Applicant Name: Lajitas Municipal Services Company LLC					
	Permit l	Permit No.: WQ000Click to enter text.					
	EPA ID	No.: TXOClick	cto enter text.				
	Expirati	on Date: <u>Clic</u>	k to enter text.				
b.	Check t	he box next t	the appropri	ate authorization type.			
	⊠ Indu	strial Wastew	ater (wastewat	er and stormwater)			
	□ Indu	strial Stormw	ater (stormwat	er only)			
	□ Reve	rse Osmosis	Water Treatme	nt (reverse osmosis water treatment wastewaters only)			
Ç.	Check t	he box next t	o the appropri	ate facility status.			
	⊠ Activ	re	☐ Inactive				
d.	Check t	he box next t	o the appropri	ate permit type.			
	☐ TPDE	S Permit	□ TLAP	☐ TPDES with TLAP component			
e.	Check t	Check the box next to the appropriate application type.					
	⊠ New						
	□ Rene	wal with chai	nges	☐ Renewal without changes			
	☐ Majo	r amendment	t with renewal	☐ Major amendment without renewal			
	☐ Minor amendment without renewal						
	☐ Mino	r modificatio	n without rene	wal			
f.	If apply	ing for an an	nendment or m	odification, describe the request: Click to enter text.			
Foi	r TCEQ Us	e Only					
Seg	ment Nu	mber	C	ounty			
	piration D mit Numl			egion			

¹ https://www.tceq.texas.gov/publications/search_forms.html

g. Application Fee

EPA Classification	New	Major Amend. (with or without renewal)	Renewal (with or without changes)	Minor Amend. / Minor Mod. (without renewal)
Minor facility not subject to EPA categorical effluent guidelines (40 CFR Parts 400-471)	⊠ \$350	□ \$350	□ \$315	□ \$150
Minor facility subject to EPA categorical effluent guidelines (40 CFR Parts 400-471)	□ \$1,250	□ \$1,250	□ \$1,215	□ \$150
Major facility	N/A ²	□ \$2,050	□ \$2,015	□ \$450

h. Payment Information

Mailed

Check or money order No.: Click to enter text.

Check or money order amt.: Click to enter text.

Named printed on check or money order: Click to enter text.

Epay

Voucher number: Click to enter text.

Copy of voucher attachment: Click to enter text.

Item 2. Applicant Information (Instructions, Pages 26)

- a. Customer Number, if applicant is an existing customer: <u>CN603406604</u>
 Note: Locate the customer number using the <u>TCEO's Central Registry Customer Search</u>³.
- b. Legal name of the entity (applicant) applying for this permit: <u>Lajitas Municipal Services</u> <u>Company LLC</u>

Note: The owner of the facility must apply for the permit. The legal name must be spelled exactly as filed with the TX SOS, Texas Comptroller of Public Accounts, County, or in the legal documents forming the entity.

c. Name and title of the person signing the application. (Note: The person must be an executive official that meets signatory requirements in 30 TAC § 305.44.)

Prefix: Click to enter text. Full Name (Last/First Name): Aube, Sonia

Title: <u>Vice President</u> Credential: <u>Click to enter text.</u>

d. Will the applicant have overall financial responsibility for the facility?

⊠ Yes □ No

² All facilities are designated as minors until formally classified as a major by EPA.

³ https://www15.tceq.texas.gov/crpub/index.cfm?fuseaction=cust.CustSearch

Note: The entity with overall financial responsibility for the facility must apply as a coapplicant, if not the facility owner.

Item 3. Co-applicant Information (Instructions, Page 27)

☑ Check this box if there is no co-applicant.; otherwise, complete the below questions.

- a. Legal name of the entity (co-applicant) applying for this permit: Click to enter text.
 - Note: The legal name must be spelled exactly as filed with the TX SOS, Texas Comptroller of Public Accounts, County, or in the legal documents forming the entity.
- b. Customer Number (if applicant is an existing customer): CNClick to enter text.

Note: Locate the customer number using the TCEQ's Central Registry Customer Search.

c. Name and title of the person signing the application. (Note: The person must be an executive official that meets signatory requirements in 30 TAC § 305.44.)

Prefix: Click to enter text.

Full Name (Last/First Name): Click to enter text.

Title: Click to enter text.

Credential: Click to enter text.

d. Will the co-applicant have overall financial responsibility for the facility?

☐ Yes ☐ No

Note: The entity with overall financial responsibility for the facility must apply as a coapplicant, if not the facility owner.

Item 4. Core Data Form (Instructions, Pages 27)

a. Complete and attach one Core Data Form (TCEQ Form 10400) for each customer (applicant and co-applicant(s)). If the customer type selected on the Core Data Form is Individual, complete Attachment 1 of the Administrative Report. Attachment: A

Item 5. Application Contact Information (Instructions, Page 27)

Provide names of two individuals who can be contacted about this application. Indicate if the individual can be contacted about administrative or technical information, or both.

a.

Administrative Contact

.

Technical Contact

Prefix: Click to enter text.

Full Name (Last/First Name): Holmes, Ron

Title: Counsel

Credential: Click to enter text.

Organization Name: The Holmes Firm PC

Mailing Address: 14241 Dallas Parkway, Ste 800

City/State/Zip: Dallas, TX 75254

Phone No: 214-981-0758

Email: wsbeasley@outlook.com

b. □ Administrative Contact

☑ Technical Contact

Prefix: Click to enter text.

Full Name (Last/First Name): Roetzel, Mark

Title: Project Engineer

Credential: P.E.

Organization Name: CDS Muery

Mailing Address: 100 NE Loop 410, Ste 300

City/State/Zip: San Antonio, TX 78216

Phone No: 210-581-1111 Fmail: mark.roetzel@cdsmuery.com

Attachment: Click to enter text.

Permit Contact Information (Instructions, Page 28) Item 6.

Provide two names of individuals that can be contacted throughout the permit term.

a. Prefix: Click to enter text.

Full Name (Last/First Name): Beasley, Scott

Title: President

Credential: Click to enter text.

Organization Name: WSB Resorts and Clubs, Inc.

Mailing Address: 3738 Oak Lawn

City/State/Zip: Dallas, TX 75219

Phone No: 214-981-0758

Email: wsbeasley@outlook.com

b. Prefix: Click to enter text.

Full Name (Last/First Name): Perry, Scott

Title: Plant Manager

Credential: Click to enter text.

Organization Name: Lajitas Municipal Services Company LLC

Mailing Address: 21707 FM 170

City/State/Zip: Lajitas, TX 79852-5015

Phone No: 432-424-5132

Email: Sperry@lajitasgolfresorts.com

Attachment: Click to enter text.

Billing Contact Information (Instructions, Page 28) Item 7.

The permittee is responsible for paying the annual fee. The annual fee will be assessed for permits in effect on September 1 of each year. The TCEO will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (form TCEQ-20029).

Provide the complete mailing address where the annual fee invoice should be mailed and the name and phone number of the permittee's representative responsible for payment of the invoice.

Prefix: Click to enter text.

Full Name (Last/First Name): Beasley, Scott

Title: President

Credential: Click to enter text.

Organization Name: WSB Resorts and Clubs, Inc.

Mailing Address: 3738 Oak Lawn

City/State/Zip: Dallas, TX 79852

Phone No: 214-981-0758

Email: wsbeaslev@outlook.com

Item 8. DMR/MER Contact Information (Instructions, Page 28)

Provide the name and mailing address of the person delegated to receive and submit DMRs or MERs. Note: DMR data must be submitted through the NetDMR system. An electronic reporting account can be established once the facility has obtained the permit number.

Prefix: Click to enter text.

Full Name (Last/First Name): Perry, Scott

Title: Plant Manager

Credential: Click to enter text.

Organization Name: Lajitas Municipal Services Company LLC

Mailing Address: 21707 FM 170

City/State/Zip: Lajitas, TX 79852-5015

Phone No: Click to enter text. Email: Click to enter text.

Item 9. Notice Information (Instructions, Pages 28)

a. Individual Publishing the Notices

Prefix: Click to enter text. Full Name (Last/First Name): Vetter, Scott

Title: <u>Facilities Manager</u> Credential: <u>Click to enter text.</u>

Organization Name: Lajitas Golf Resort

Mailing Address: 21707 FM 170 City/State/Zip: Lajitas, TX 79852-5015

Phone No: 281-467-3467 Email: SVetter@lajitasgolfresort.com

b. Method for Receiving Notice of Receipt and Intent to Obtain a Water Quality Permit Package

(only for NORI, NAPD will be sent via regular mail)

☑ E-mail: SVetter@lajitasgolfresort.com

☐ Fax: Click to enter text.

☐ Regular Mail (USPS)

Mailing Address: Click to enter text.

City/State/Zip Code: Click to enter text.

c. Contact in the Notice

Prefix: Click to enter text. Full Name (Last/First Name): Vetter, Scott

Title: Facilities Manager Credential: Click to enter text.

Organization Name: Lajitas Golf Resort

Phone No: 281-467-3467 Email: SVetter@lajitasgolfresort.com

d. Public Viewing Location Information

Note: If the facility or outfall is located in more than one county, provide a public viewing place for each county.

Public building name: Terlingua Fire & EMS Location within the building: Lobby

Physical Address of Building: 23250 FM-170

City: Terlingua County: Brester

e. Bilingual Notice Requirements

This information is required for new, major amendment, minor amendment or minor modification, and renewal applications.

This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.

Call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine if an alternative language notice(s) is required.

1. Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?

		□ Yes ⊠ No
		If no, publication of an alternative language notice is not required; skip to Item 8 (Regulated Entity and Permitted Site Information.)
	2.	Are the students who attend either the elementary school or the middle school enrolled in a bilingual education program at that school?
		□ Yes □ No
	3.	Do the students at these schools attend a bilingual education program at another location?
		□ Yes □ No
	4.	Would the school be required to provide a bilingual education program, but the school has waived out of this requirement under 19 TAC §89.1205(g)?
		□ Yes □ No □ N/A
	5.	If the answer is yes to question 1, 2, 3, or 4, public notices in an alternative language are required. Which language is required by the bilingual program? Click to enter text.
f	A_{j}	ummary of Application in Plain Language Template - Complete and attach the Summary of pplication in Plain Language Template (TCEQ Form 20972), also known as the plain nguage summary or PLS. Attachment: \underline{B}
8		omplete and attach one Public Involvement Plan (PIP) Form (TCEQ Form 20960) for each oplication for a new permit or major amendment. Attachment: <u>C</u>
	tem	10. Regulated Entity and Permitted Site Information (Instructions Page 29)
8	a. T0	CEQ issued Regulated Entity Number (RN), if available: RN102079365
	m th	ote: If your business site is part of a larger business site, a Regulated Entity Number (RN) ay already be assigned for the larger site. Use the RN assigned for the larger site. Search to TCEQ's Central Registry to determine the RN or to see if the larger site may already be gistered as a Regulated Entity. If the site is found, provide the assigned RN.
t		ame of project or site (name known by the community where located): <u>Lajitas Water</u> <u>reatment Plant</u>
Ć	. Is	the location address of the facility in the existing permit the same?
		Yes □ No ☒ N/A (new permit)
	W	ote: If the facility is located in Bexar, Comal, Hays, Kinney, Medina, Travis, Uvalde, or illiamson County, additional information concerning protection of the Edwards Aquifer ay be required.
C	l. O	wner of treatment facility:
	Pr	efix: <u>Click to enter text.</u> Full Name (Last/First Name): <u>Click to enter text.</u>
	or	Organization Name: Lajitas Municipal Services Company LLC
	M	ailing Address: <u>14241 Dallas Parkway, Ste 800</u> City/State/Zip: <u>Dallas, TX 75254</u>
	Ph	ione No: <u>214-981-0758</u> Email: <u>sonia.aube@energytransfer.com</u>

e.	Ownership of facility: $\ \square$ Pul	olic 🛮 Priva	te 🗆 Both	☐ Federal
f.	Owner of land where treatme	nt facility is or wil	be: <u>Lajitas Municí</u> j	oal Services Company
	Prefix: Click to enter text.	Full Name (Last/F	irst Name): <u>Click to</u>	enter text.
	or Organization Name: Lajitas	Municipal Service	s Company LLC	
	Mailing Address: 14241 Dalla	s Parkway, Ste 800	City/State/Zip: [Dallas, TX 75254
	Phone No: <u>214-981-0758</u>	Email: sonia.aube	<u>@energytransfer.co</u>	<u>om</u>
	Note: If not the same as the fat least six years (In some case) Click to enter text.			
g.	Owner of effluent TLAP dispo	sal site (if applica	ole): <u>Lajitas Capital</u>	<u>Partners</u>
	Prefix: Click to enter text.	Full Name (Last/F	irst Name): <u>Click to</u>	enter text.
	or Organization Name: Lajitas	Capital Partners		
	Mailing Address: 8111 Westel	nester Dr. Ste 600	City/State/Zip: <u>[</u>	Dallas, TX 75225
	Phone No: <u>214-981-0758</u>	Email: <u>SBeasley@</u>	outlook.com	
	Note: If not the same as the fat least six years. Attachment		h a long-term lease	agreement in effect for
h.	Owner of sewage sludge disp	osal site (if applica	ble):	
	Prefix: N/A Full Name	e (Last/First Name	: Click to enter text	<u>t.</u>
	or Organization Name: Click t	o enter text.		
	Mailing Address: Click to ente	er text.	City/State/Zip: (Click to enter text.
	Phone No: Click to enter text.	Email: <u>Click to ent</u>	er text.	
	Note: If not the same as the fa at least six years. Attachment			agreement in effect for
Ite	em 11. TDPES Discharg 31)	e/TLAP Dispos	al Information	(Instructions, Page
a.	Is the facility located on or do	es the treated effl	uent cross Native A	merican Land?
	☐ Yes ☒ No			
b.	Attach an original full size US renewal or amendment applicant item below to confirm it	ations) with all red	uired information.	
	⊠ One-mile radius	□T	hree-miles downstr	eam information
	⊠ Applicant's property bound	daries 🛮 🗷 T	reatment facility bo	oundaries
	☐ Labeled point(s) of discharg	ge □ H	ighlighted discharg	ge route(s)
	⊠ Effluent disposal site boun	daries 🛮 🖾 A	ll wastewater pond	S
	☐ Sewage sludge disposal site	n □ N	ew and future cons	truction

	Attachment: <u>E</u>
c.	Is the location of the sewage sludge disposal site in the existing permit accurate? \Box Yes \boxtimes No or New Permit
	If no, or a new application, provide an accurate location description: <u>Lajitas Golf Course – Attachment</u>
d.	Are the point(s) of discharge in the existing permit correct? ☐ Yes ☒ No or New Permit
	If no, or a new application, provide an accurate location description: $\underline{N/A}$ - \underline{TLAP}
ę.	Are the discharge route(s) in the existing permit correct? ☐ Yes ☒ No or New Permit
	If no, or a new permit, provide an accurate description of the discharge route: $N/A - TLAP$
f.	City nearest the outfall(s): <u>N/A</u>
g.	County in which the outfalls(s) is/are located: $\underline{N/A}$
h.	Is or will the treated wastewater discharge to a city, county, or state highway right-of-way or a flood control district drainage ditch?
	□ Yes ⊠ No
	If yes, indicate by a check mark if: \Box Authorization granted \Box Authorization pending
	For new and amendment applications, attach copies of letters that show proof of contact and provide the approval letter upon receipt. Attachment: <u>Click to enter text.</u>
	For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge: Click to enter text.
i.	For TLAPs, is the location of the effluent disposal site in the existing permit accurate?
	☐ Yes No or New Permit ☒ <u>New TLAP Permit</u>
	If no, or a new application, provide an accurate location description: Lajitas Golf Course = Exhibit F
j.	City nearest the disposal site: <u>Terlingua</u>
k.	County in which the disposal site is located: <u>Brewster</u>
1.	For TLAPs, describe how effluent is/will be routed from the treatment facility to the disposal site: Routed by closed pipe to bentonite clay lined golf course lake (liner previously certified under expired TLAP permit), then blended with groundwater for irrigation

m. For TLAPs, identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained: <u>Rio Grande River</u>

Item 12. Miscellaneous Information (Instructions. Page 33)

a.	Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?
	□ Yes ⊠ No
	If yes, list each person: <u>Click to enter text.</u>
b.	Do you owe any fees to the TCEQ?
	□ Yes ⊠ No
	If yes, provide the following information:
	Account no.: Click to enter text.
	Total amount due: <u>Click to enter text.</u>
C,	Do you owe any penalties to the TCEQ?
	□ Yes ⊠ No
	If yes, provide the following information:
	Enforcement order no.: Click to enter text.
	Amount due: <u>Click to enter text.</u>

Item 13. Signature Page (Instructions, Page 33)

Permit No: WO000Click to enter text.

Applicant Name: Lajitas Municipal Services Company LLC

Certification: I, Sonia Aube, certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

I further certify that I am authorized under 30 Texas Administrative Code §305.44 to sign and submit this document and can provide documentation in proof of such authorization upon request.

Signatory name (typed or printed): Sonia Aube

Signatory title: Authorize	ed Representative	1		
	se blue ink)	<u></u>		7/2025
Subscribed and Sworn to	before me by the s	aid <u>SMM</u>	ANDE	
on this	Mth		June	, 20 29.
My commission expires o	n the 7-tw	day of _	January	
Notary Public DAIAS	VIHERINE MORGAN 7 Public, State of Texas M. Expires 01-07-2028 Mary ID 132303899	Com Com	[SEAL]	
County, Texas				

Note: If co-applicants are necessary, each entity must submit an original, separate signature page.

INDUSTRIAL WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.1

The following information is required for new and amendment applications.

a.

b.

Item 1. Affected Landowner Information (Instructions, Page 35)

Attach a landowner map or drawing, with scale, as applicable. Check the box next to each item to confirm it has been provided.
☑ The applicant's property boundaries.
oxtimes The facility site boundaries within the applicant's property boundaries.
☑ The distance the buffer zone falls into adjacent properties and the property boundaries of the landowners located within the buffer zone.
☑ The property boundaries of all landowners surrounding the applicant's property. (Note: if the application is a major amendment for a lignite mine, the map must include the property boundaries of all landowners adjacent to the new facility (ponds).)
\square The point(s) of discharge and highlighted discharge route(s) clearly shown for one mile downstream.
☐ The property boundaries of the landowners located on both sides of the discharge route for one full stream mile downstream of the point of discharge.
☐ The property boundaries of the landowners along the watercourse for a one-half mile radius from the point of discharge if the point of discharge is into a lake, bay, estuary, affected by tides.
☑ The boundaries of the effluent disposal site (e.g., irrigation area or subsurface drainfield site) and all evaporation/holding ponds within the applicant's property.
☑ The property boundaries of all landowners surrounding the applicant's property boundaries where the effluent disposal site is located.
☐ The boundaries of the sludge land application site (for land application of sewage sludge for beneficial use) and the property boundaries of landowners within one-quarter mile of the applicant's property boundaries where the sewage sludge land application site is located.
☐ The property boundaries of landowners within one-half mile in all directions from the applicant's property boundaries where the sewage sludge disposal site (e.g., sludge surface disposal site or sludge monofil) is located.
Attachment: <u>G</u>
oxtimes that the landowners list has also been provided as mailing labels in electronic format (Avery 5160).
Check this box to confirm a separate list with the landowners' names and mailing addresses cross-referenced to the landowner's map has been provided. Provide the source

of the landowners' names and mailing addresses: Brewster County Property Records

e.	As required by Texas Water Code \S 5.115, is any permanent school fund land affected by this application?
	□ Yes ⊠ No
	If yes, provide the location and foreseeable impacts and effects this application has on the land(s): <u>Click to enter text.</u>
It	m 2. Original Photographs (Instructions, Page 37)
	vide original ground level photographs. Check the box next to each of the following items ndicate it is included.
	At least one original photograph of the new or expanded treatment unit location.
	At least two photographs of the existing/proposed point of discharge and as much area downstream (photo 1) and upstream (photo 2) as can be captured. If the discharge is to an open water body (e.g., lake, bay), the point of discharge should be in the right or left edge cach photograph showing the open water and with as much area on each respective side of the discharge as can be captured.
\boxtimes	at least one photograph of the existing/proposed effluent disposal site.
\boxtimes	a plot plan or map showing the location and direction of each photograph.
At	achment: H

INDUSTRIAL WASTEWATER PERMIT APPLICATION SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: N/A

WATER OUALITY PERMIT

PAYMENT SUBMITTAL FORM

Use this form to submit the Application Fee, if mailing the payment. (Instructions, Page 36-37)

- Complete items 1 through 5 below.
- Staple the check or money order in the space provided at the bottom of this document.
- Do not mail this form with the application form.
- Do not mail this form to the same address as the application.
- Do not submit a copy of the application with this form as it could cause duplicate permit entries.

Mail this form and the check or money order to:

BY REGULAR U.S. MAIL

BY OVERNIGHT/EXPRESS MAIL

Texas Commission on Environmental Quality Texas Commission on Environmental Quality

Financial Administration Division

Cashier's Office, MC-214

P.O. Box 13088

Austin, Texas 78711-3088

Financial Administration Division

Cashier's Office, MC-214 12100 Park 35 Circle

Austin, Texas 78753

Permit No: WQ000Lajitas Industrial Waste Water Application Fee Code: WOP

1. Check or Money Order Number: 4544

2. Check or Money Order Amount: \$350.00

3. Date of Check or Money Order: June 17, 2025

4. Name on Check or Money Order: Lajitas Capital Partners

5. APPLICATION INFORMATION

Name of Project or Site: Lajitas WTP

Physical Address of Project or Site: HC 70, Box 400, Lajitas, TX 79852

If the check is for more than one application, attach a list which includes the name of each Project or Site (RE) and Physical Address, exactly as provided on the application.

Attachment: Click to enter text.

ATTACHMENT 1

INDIVIDUAL INFORMATION

Item 1. Individual information (Instructions, Page 38)

Complete this attachment if the facility applicant or co-applicant is an individual. Make additional copies of this attachment if both are individuals.

Prefix (Mr., Ms., or Miss): Click to enter text.

Full legal name (first, middle, and last): Click to enter text.

Driver's License or State Identification Number: Click to enter text.

Date of Birth: Click to enter text.

Mailing Address: Click to enter text.

City, State, and Zip Code: Click to enter text.

Phone No.: Click to enter text.

Fax No.: Click to enter text.

E-mail Address: Click to enter text.

CN: Click to enter text.

INDUSTRIAL WASTEWATER PERMIT APPLICATION CHECKLIST OF COMMON DEFICIENCIES

Below is a list of common deficiencies found during the administrative review of industrial wastewater permit applications. To ensure the timely processing of this application, please review the items below and indicate each item is complete and in accordance applicable rules at 30 TAC Chapters 21, 281, and 305 by checking the box next to the item. If an item is not required this application, indicate by checking N/A where appropriate. Please do not submit the application until all items below are addressed.

- □ Core Data Form (TCEQ Form No. 10400)
 (Required for all applications types. Must be completed in its entirety and signed.
 Note: Form may be signed by applicant representative.)
- ☑ Correct and Current Industrial Wastewater Permit Application Forms (TCEQ Form Nos. 10055 and 10411. Version dated 5/10/2019 or later.)
- ☑ Water Quality Permit Payment Submittal Form (Page 14)

 (Original payment sent to TCEQ Revenue Section. See instructions for mailing address.)
- ☑ 7.5 Minute USGS Quadrangle Topographic Map Attached (Full-size map if seeking "New" permit. 8 ½ x 11 acceptable for Renewals and Amendments.)
- □ N/A ⊠ Current/Non-Expired, Executed Lease Agreement or Easement Attached
- ☐ N/A ☒ Landowners Map
 (See instructions for landowner requirements.)

Things to Know:

- All the items shown on the map must be labeled.
- The applicant's complete property boundaries must be delineated which includes boundaries of contiguous property owned by the applicant.
- The applicant cannot be its own adjacent landowner. You must identify the landowners immediately adjacent to their property, regardless of how far they are from the actual facility.
- If the applicant's property is adjacent to a road, creek, or stream, the landowners on the opposite side must be identified. Although the properties are not adjacent to applicant's property boundary, they are considered potentially affected landowners. If the adjacent road is a divided highway as identified on the USGS topographic map, the applicant does not have to identify the landowners on the opposite side of the highway.
- □ N/A ☑ Landowners Labels and Cross Reference List (See instructions for landowner requirements.)
- ⊠ Electronic Application Submittal
 (See application submittal requirements on page 23 of the instructions.)
- ☑ Original signature per 30 TAC § 305.44 Blue Ink Preferred (If signature page is not signed by an elected official or principle executive officer, a copy of signature authority/delegation letter must be attached.)

☑ Summary of Application (in Plain Language)

COMMISSION COMMISSION

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

The following information is required for all applications for a TLAP or an individual TPDES discharge permit.

For additional information or clarification on the requested information, please refer to the <u>Instructions for Completing the Industrial Wastewater Permit Application</u> available on the TCEQ website. Please contact the Industrial Permits Team at 512-239-4671 with any questions about this form.

If more than one outfall is included in the application, provide applicable information for each individual outfall. If an item does not apply to the facility, enter N/A to indicate that the item has been considered. Include separate reports or additional sheets as clearly cross-referenced attachments and provide the attachment number in the space provided for the item the attachment addresses.

NOTE: This application is for an industrial wastewater permit only. Additional authorizations from the TCEQ Waste Permits Division or the TCEQ Air Permits Division may be needed.

Item 1. Facility/Site Information (Instructions, Page 39)

a. Describe the general nature of the business and type(s) of industrial and commercial activities. Include all applicable SIC codes (up to 4).

Lajitas WTP is a groundwater EDR membrane plant serving the Lajitas Golf Resort community in Brewster County, Texas. The 0.3mgd membrane plant produces a process wastewater stream of up to 0.065mgd. This process wastewater is disposed of by irrigation of the golf course after blending with a larger groundwater irrigation volume. The plant has operated under a TLAP permit since about 2000. However, that permit expired in May 2025, requiring a New Permit application to continue facility operations. No changes are proposed from that previous TLAP permit.

b. Describe all wastewater-generating processes at the facility.

The o.3mgd EDR membrane groundwater plant produces a process waste stream of up to 0.065mgd, consisting of EDR reversal reject concentrate, multi-media iron reduction filter backwash and periodic membrane clean-in-place (CIP) acid backwash. No chemicals are added to the groundwater process stream except for chlorine used for iron oxidation and cationic polymer used to enhance iron removal. The source groundwater (Santa Elena Aquifer) has a TDS concentration of about 1,400mg/l, including NORM constituents (Uranium, Radium226-228), These dissolved solids are concentrated to an average waste stream TDS of about 6,000mg/l. The process waste stream is stored in a below-grade basin at the WTP and then transferred by closed pipe to the golf course irrigation pump station Lake E (including a 1-ft bentonite clay liner certified with the original TLAP permit), blended with irrigation groundwater (averaging about 110,000gpd annually) and then applied to 56.3 acres of irrigated golf course turf.

https://www.tceq.texas.gov/permitting/wastewater/industrial/TPDES_industrial_wastewater_steps.html

c. Provide a list of raw materials, major intermediates, and final products handled at the facility. **Materials List** Intermediate Products **Final Products** Raw Materials Potable water N/A -Groundwater EDR WTP Attachment: N/A – Groundwater EDR membrane plant **d.** Attach a facility map (drawn to scale) with the following information: Production areas, maintenance areas, materials-handling areas, waste-disposal areas, and water intake structures. The location of each unit of the WWTP including the location of wastewater collection sumps, impoundments, outfalls, and sampling points, if significantly different from outfall locations. Attachment: I e. Is this a new permit application for an existing facility? \boxtimes Yes No If yes, provide background discussion: Previous TLAP Permit expired May 2025. This application is to continue facility operations and TLAP irrigation disposal. f. Is/will the treatment facility/disposal site be located above the 100-year frequency flood level Yes No X List source(s) used to determine 100-year frequency flood plain: FIRM - 4800841400B If no, provide the elevation of the 100-year frequency flood plain and describe what protective measures are used/proposed to prevent flooding (including tail water and rainfall run-on controls) of the treatment facility and disposal area: The WTP and golf course

disposal area are located above the 100-yr floodplain

Attachment: Click to enter text.

g. For new or major amendment permit applications, will any construction operations result in a discharge of fill material into a water in the state?

		Yes	\boxtimes	No		N/A (renewal only)
h.	If yes to		1.g, ha	as the ap	oplica	ant applied for a USACE CWA Chapter 404 Dredge and Fill
		Yes		No		
	If yes,	provide	e the p	ermit ni	umbei	er: Click to enter text.
	If no, p	provide	an ap	proxima	te dat	te of application submittal to the USACE: Click to enter
It	em 2.	Tre	atme	ent Sy	ster	m (Instructions, Page 40)
a.	wastev	vater at	this fa	acility. I	nclud	ological treatment process(es) used/proposed to treat le a description of each treatment process, starting with the outfall/point of disposal.
	oxidate Pre-trace revers with a mecha added to a begolf colored.	ion and eated wa ed TDS i e polaric hydrocl mically for secon clow-gra ourse irr ion disp	cationicater the including and including the	ic polymon passes in passe	er. The thround consumer to the town ion print out. blending action acti	ultimedia pressure filter where iron is removed using chlorine he sand filter periodically backwashes to removed oxidized iron. In the two-stage electrodialysis (EDR) membrane unit to estituents (Uranium and Radium). The EDR unit periodically trate to waste. The unit is periodically cleaned-in-place (CIP) or remove scale. Treated water then passes through a ver to remove radon gas and raise pH. Free chlorine is then rior to distribution. The combined process waste streams drain taide of the plant building and are them pump transferred to the ling with a larger groundwater volume for golf course irrigation. The since facility start-up in about 2000 under a TLAP permit, and 2025 and is being re-instated through this application.
b.	flow in	to the f	facility		vater :	rater balance showing all sources of water and wastewater flow into and from each treatment unit, and wastewater bosal.
	Attach	ment: <u>J</u>				
It	em 3.	Imp	oun	dmen	ts (I	Instructions, Page 40)
Do	es the f	acility ı	use or	plan to	use ai	ny wastewater impoundments (e.g., lagoons or ponds?)
	⊠ Ye	es 🗆	No			
3.6	for nev	v or pro	posed	limpou	ndme	olete Item 3.a for existing impoundments and Items 3.a - ents. NOTE: See instructions, Pages 40-42, for additional uired by Items 3.a – 3.e.
a.						wing information for each existing, new, or proposed

Use Designation: Indicate the use designation for each impoundment as Treatment (T), Disposal (D), Containment (C), or Evaporation (E).

Associated Outfall Number: Provide an outfall number if a discharge occurs or will occur.

Liner Type: Indicate the liner type as Compacted clay liner (C), In-situ clay liner (I), Synthetic/plastic/rubber liner (S), or Alternate liner (A). NOTE: See instructions for further detail on liner specifications. If an alternate liner (A) is selected, include an attachment that provides a description of the alternate liner and any additional technical information necessary for an evaluation.

Leak Detection System: If any leak detection systems are in place/planned, enter Y for yes. Otherwise, enter N for no.

Groundwater Monitoring Wells and Data: If groundwater monitoring wells are in place/planned, enter Y for yes. Otherwise, enter N for no. Attach any existing groundwater monitoring data.

Dimensions: Provide the dimensions, freeboard, surface area, storage capacity of the impoundments, and the maximum depth (not including freeboard). For impoundments with irregular shapes, submit surface area instead of length and width.

Compliance with 40 CFR Part 257, Subpart D: If the impoundment is required to be in compliance with 40 CFR Part 257, Subpart D, enter Y for yes. Otherwise, enter N for no.

Date of Construction: Enter the date construction of the impoundment commenced (mm/dd/yy).

Impoundment Information

Parameter	Pond #	Pond #	Pond #	Pond #
Use Designation: (T) (D) (C) or (E)	С			
Associated Outfall Number	N/A-TLAP			
Liner Type (C) (I) (S) or (A)	С			
Alt. Liner Attachment Reference				
Leak Detection System, Y/N	N			
Groundwater Monitoring Wells, Y/N	N			
Groundwater Monitoring Data Attachment				
Pond Bottom Located Above The Seasonal High-Water Table, Y/N	Y			
Length (ft)	750			
Width (ft)	250			
Max Depth From Water Surface (ft), Not Including Freeboard	5			
Freeboard (ft)	2			
Surface Area (acres)	2.4			
Storage Capacity (gallons)	3.1MG			
40 CFR Part 257, Subpart D, Y/N	N			
Date of Construction	06/01/2000			

Attachment: Click to enter text.

The following information (Items 3.b - 3.e) is required only for new or proposed impoundments.

- b. For new or proposed impoundments, attach any available information on the following items. If attached, check yes in the appropriate box. Otherwise, check no or not yet designed.
 - 1. Liner data

		Yes		No		Not yet	designe
--	--	-----	--	----	--	---------	---------

2. Leak detection system or groundwater monitoring data

-	Yes	-	A T	_	AT .	t designed
	VAC		No	100	NOT TO	CACIMBAC
	1 5 5		111		TYUL VE	UCSIELICU

3. Groundwater impacts

	37		AT-		A T - A	t designed
5.0	Yes		No		NOT VE	r aesionea
	A ~ ~ U	-	110	لنسا	1100	CUCULATION

NOTE: Item b.3 is required if the bottom of the pond is not above the seasonal highwater table in the shallowest water-bearing zone.

Attachment: Click to enter text.

For TLAP applications: Items 3.c – 3.e are not required, continue to Item 4.

c. Attach a USGS map or a color copy of original quality and scale which accurately locates and identifies all known water supply wells and monitor wells within ½-mile of the impoundments.

Attachment: Click to enter text.

d. Attach copies of State Water Well Reports (e.g., driller's logs, completion data, etc.), and data on depths to groundwater for all known water supply wells including a description of how the depths to groundwater were obtained.

Attachment: Click to enter text.

e. Attach information pertaining to the groundwater, soils, geology, pond liner, etc. used to assess the potential for migration of wastes from the impoundments or the potential for contamination of groundwater or surface water.

Attachment: Click to enter text.

Item 4. Outfall/Disposal Method Information (Instructions, Page 42)

Complete the following tables to describe the location and wastewater discharge or disposal operations for each outfall for discharge, and for each point of disposal for TLAP operations.

If there are more outfalls/points of disposal at the facility than the spaces provided, copies of pages 6 and/0r numbered accordingly (i.e., page 6a, 6b, etc.) may be used to provide information on the additional outfalls.

For TLAP applications: Indicate the disposal method and each individual irrigation area I, evaporation pond E, or subsurface drainage system S by providing the appropriate letter designation for the disposal method followed by a numerical designation for each disposal

area in the space provided for Outfall number (e.g. E1 for evaporation pond 1, I2 for irrigation area No. 2, etc.).

Outfall Longitude and Latitude

Latitude (Decimal Degrees)	Longitude (Decimal Degrees)
29.257	103.773

Outfall Location Description

Outfall No.	Location Description					

Description of Sampling Point(s) (if different from Outfall location)

Outfall No.	Description of sampling point	

Outfall Flow Information - Permitted and Proposed

Outfall No.	Permitted Daily Avg Flow (MGD)	Permitted Daily Max Flow (MGD)	Proposed Daily Avg Flow (MGD)	Proposed Daily Max Flow (MGD)	Anticipated Discharge Date (mm/dd/yy)
I1			0.065	0.065	06/01/2000

Outfall Discharge - Method and Measurement

Outfall No.	Pumped Discharge? Y/N	Gravity Discharge? Y/N	Type of Flow Measurement Device Used
11	Y	N	Doppler Flow Meter

Outfall Discharge - Flow Characteristics

Outfall No.	Intermittent	Continuous	Seasonal	Discharge	Discharge	Discharge
	Discharge?	Discharge?	Discharge?	Duration	Duration	Duration
	Y/N	Y/N	Y/N	(hrs/day)	(days/mo)	(mo/yr)
11	Y	N	N	4	30	12

Outfall No.	Continuous Discharge? Y/N	Discharge Duration (hrs/day)	Discharge Duration (days/mo)	Discharge Duration (mo/yr)

Outfall Wastestream Contributions

Outfall No. I1

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow
EDR Wastewater	0.05	75
Multimedia Filter Backwash	0.015	25
EDR CIP (Periodic)	0.001	<1

Outfall No. Click to enter text.

Volume (MGD)	Percent (%) of Total Flow
•	
	Volume (MGD)

Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

Attachment: Click to enter text.

Item 5. Blowdown and Once-Through Cooling Water Discharges (Instructions, Page 43)

- a. Indicate if the facility currently or proposes to:
 - ☐ Yes ☒ No Use cooling towers that discharge blowdown or other wastestreams
 - ☐ Yes ☒ No Use boilers that discharge blowdown or other wastestreams
 - ☐ Yes ☒ No Discharge once-through cooling water

NOTE: If the facility uses or plans to use cooling towers or once-through cooling water, Item 12 is required.

- b. If yes to any of the above, attach an SDS with the following information for each chemical additive.
 - Manufacturers Product Identification Number
 - Product use (e.g., biocide, fungicide, corrosion inhibitor, etc.)
 - Chemical composition including CASRN for each ingredient
 - · Classify product as non-persistent, persistent, or bioaccumulative
 - Product or active ingredient half-life
 - Frequency of product use (e.g., 2 hours/day once every two weeks)
 - Product toxicity data specific to fish and aquatic invertebrate organisms
 - Concentration of whole product or active ingredient, as appropriate, in wastestream.

In addition to each SDS, attach a summary of the above information for each specific wastestream and the associated chemical additives. Specify which outfalls are affected.

Attachment: Click to enter text.

c. Cooling Towers and Boilers

If the facility currently or proposes to use cooling towers or boilers that discharge blowdown or other wastestreams to the outfall(s), complete the following table.

Cooling Towers and Boilers

Type of Unit	Number of Units	Daily Avg Blowdown (gallons/day)	Daily Max Blowdown (gallons/day)
Cooling Towers			
Boilers			

Item 6. Stormwater Management (Instructions, Page 44)					
Will any existing/proposed outfalls discharge stormwater associated with industrial activate as defined at $40\ CFR\ \S\ 122.26(b)(14)$, commingled with any other wastestream?	ities,				
□ Yes ⊠ No					
If yes, briefly describe the industrial processes and activities that occur outdoors or in a manner which may result in exposure of the activities or materials to stormwater: Click tenter text.	O				
Item 7. Domestic Sewage, Sewage Sludge, and Septage Management and Disposal (Instructions, Page 44)					
Domestic Sewage - Waste and wastewater from humans or household operations that is discharged to a wastewater collection system or otherwise enters a treatment works.	S				
a. Check the box next to the appropriate method of domestic sewage and domestic sewage sludge treatment or disposal. Complete Worksheet 5.0 or Item 7.b if directed to do so	_				
☑ Domestic sewage is routed (i.e., connected to or transported to) to a WWTP permitt receive domestic sewage for treatment, disposal, or both. Complete Item 7.b.	ed to				
□ Domestic sewage disposed of by an on-site septic tank and drainfield system. Comp Item 7.b.	olete				
\square Domestic and industrial treatment sludge ARE commingled prior to use or disposal					
☐ Industrial wastewater and domestic sewage are treated separately, and the respective sludge IS NOT commingled prior to sludge use or disposal. Complete Worksheet 5.0					
☐ Facility is a POTW. Complete Worksheet 5.0.					
☐ Domestic sewage is not generated on-site.					
\square Other (e.g., portable toilets), specify and Complete Item 7.b: Click to enter text.					
b. Provide the name and TCEQ, NPDES, or TPDES Permit No. of the waste-disposal facility which receives the domestic sewage/septage. If hauled by motorized vehicle, provide name and TCEQ Registration No. of the hauler.					
Domestic Sewage Plant/Hauler Name					
Plant/Hauler Name Permit/Registration No.					
Lajitas Municipal WWTP WQ0014282001					
Item 8. Improvements or Compliance/Enforcement Requirements (Instructions, Page 45)					
 a. Is the permittee currently required to meet any implementation schedule for compliant enforcement? □ Yes ⋈ No 	ice or				

b. Has the permittee completed or planned for any improvements or construction projects?

L 163 2 140	
c. If yes to either 8.a or 8.b, provide a brief summary of the requirements and a status upd Click to enter text.	ate
Item 9. Toxicity Testing (Instructions, Page 45)	
Have any biological tests for acute or chronic toxicity been made on any of the discharges of on a receiving water in relation to the discharge within the last three years?	r
□ Yes ⊠ No	
If yes, identify the tests and describe their purposes: Click to enter text.	
Additionally, attach a copy of all tests performed which have not been submitted to the TCF or EPA. Attachment: Click to enter text.	EQ
Item 10. Off-Site/Third Party Wastes (Instructions, Page 45)	
a. Does or will the facility receive wastes from off-site sources for treatment at the facility, disposal on-site via land application, or discharge via a permitted outfall?	
□ Yes ⊠ No	
If yes, provide responses to Items 10.b through 10.d below.	
If no, proceed to Item 11.	
b. Attach the following information to the application:	
 List of wastes received (including volumes, characterization, and capability with on-si- wastes). 	ite
 Identify the sources of wastes received (including the legal name and addresses of th generators). 	e
 Description of the relationship of waste source(s) with the facility's activities. 	
Attachment: Click to enter text.	
c. Is or will wastewater from another TCEQ, NPDES, or TPDES permitted facility commingle with this facility's wastewater after final treatment and prior to discharge via the final outfall/point of disposal?	d
□ Yes ⊠ No	
If yes, provide the name, address, and TCEQ, NPDES, or TPDES permit number of the contributing facility and a copy of any agreements or contracts relating to this activity.	
Attachment: Click to enter text.	
d. Is this facility a POTW that accepts/will accept process wastewater from any SIU and has required to have an approved pretreatment program under the NPDES/TPDES program?	/is
□ Yes ⊠ N•	
If yes, Worksheet 6.0 of this application is required.	

Item 11. Radioactive Materials (Instructions, Page 46) a. Are/will radioactive materials be mined, used, stored, or processed at this facility? Yes If ves, use the following table to provide the results of one analysis of the effluent for all radioactive materials that may be present. Provide results in pCi/L. Radioactive Materials Mined, Used, Stored, or Processed Radioactive Material Name Concentration (pCi/L) b. Does the applicant or anyone at the facility have any knowledge or reason to believe that radioactive materials may be present in the discharge, including naturally occurring radioactive materials in the source waters or on the facility property? Yes No \boxtimes If yes, use the following table to provide the results of one analysis of the effluent for all radioactive materials that may be present. Provide results in pCi/L. Do not include information provided in response to Item 11.a. Radioactive Materials Present in the Discharge Radioactive Material Name Concentration (pCi/L) Uranium 300 Radium 226 60 Radium 228 60 Item 12. Cooling Water (Instructions, Page 46) a. Does the facility use or propose to use water for cooling purposes? 40 Yes X No Decommissioned: Click to enter text.

If yes, complete Items 12.b thru 12.f. If no, stop here.

To Be Decommissioned: Click to enter text.

If decommissioned, provide the date operation ceased and stop here.

If to be decommissioned, provide the date operation is anticipated to cease and stop here.

b. Cooling water is/will be obtained from a groundwater source (e.g., on-site well).

The Ionics EDR membrane system removes charged particles by applying a direct current (DC) electric field between alternating cationic and anionic semi-permeable membrane plates. Removal efficiency varies somewhat based on particle mass, surface charge and several other factors. Ionic's design process model predicts about a 65% removal efficiency for total dissolved solids (TDS) reduction of the Sante Elena feed water (1450mg/l TDS design feed producing a ÷/- 500mg/l TDS product water). Removal efficiency for radionuclide metals has been confirmed as being comparable to overall TDS efficiency.

Four consecutive weekly composite samples were collected between March 2 and April 1, 2011 to better define the blended wastewater quality produced by the plant. While EDR wastewater quality remains relatively constant (about 6.500mg/1 TDS), the blended waste stream quality varies considerably depending on the relative amount of sand filter media filter backwash generated during any sampling period. Table 1 presents a summary of this composite sampling exercise.

Table No.1 WTP Wastewater – Composite Sampling						
Date	TDS (mg/L)	Gross A (piC/L)	Gross B (piC/L)	Rad-226 (piC/L)	Rad-228 (piC/L)	Uranium (ug/L)
3/9/11		114	120	33.8	2.68	14.3
3/18/11	5300	131	97	28.9	2.02	29.6
3/25/11	3300	110	103	20.0	1.33	37.5
4/01/11	3200	81	74	32.3	2.77	36
Avg.	3930	109	99	28.8	2.20	29.4
GW Well	1450	19.3	17.2	8.54	0.62	6.1

Review of this data indicates several conclusions, including:

- Blended water quality as generally indicated by TDS is quite variable, depending largely on the sand filter media backwash volume during any sampling period.
- The relationship between TDS and radionuclides does not appear linear, at times inversely proportionate to TDS shifts, suggesting additional influencing variables.
- Results suggest that reasonable wastewater quality goals can be established, and managed through adjustment of media backwashing volume over time, including:
 - o TDS -4,000mg/l
 - o Gross Alpha 110piC/L
 - o Gross Beta 100piC/L
 - o Radium 226 30piC/L.
 - o Radium 228 3piC/L
 - o Uranium 30ug/L

Alternately to the 1680mg/I TDS injectate quality, we propose that about 15% of the potable production be used for media filter backwash (considerably in excess of the 3-5% anticipated for effective backwashing of the iron removal filters), resulting in a blended

	If	yes, stop h	ere. If n e	o, con	tinue.			
c.	Co	oling Wate	r Suppli	er				
	1.	l. Provide the name of the owner(s) and operator(s) for the CWIS that supplies or will supply water for cooling purposes to the facility.						
Co	olin	g Water Inta	ake Struc	ture(s)	Owner(s) and Op	erator(s)		
C	WIS	S ID						
0	wn	er						
0	pei	ator						
	2.	Cooling w	ater is/v	will bo	obtained from	a Public W	ater Supplier (PWS	S)
			No		Yes; PWS No.:			,
							n No. and stop he	ere.
	2				obtained from			
	٥.	Cooming w	No No		Yes; Auth No.:			
					a series series		ation No. and stop	n here
								p nere,
	4.	Cooling w		will b€	obtained from			
			No		Yes; AIF: Click	to enter te	xt.	
							ual intake flow of ter for cooling pu	the Independent rposes and proceed.
d.	31	6(b) Gener	al Criter	ia				
	1.				ovide water for o			ity has or will have a
			Yes		No			
	2.				l water withdrav purposes on an			used at the facility
			Yes		No			
	3.						vater for cooling p of the United Stat	
			Yes		No. Explanatio	n:_Click to	enter text.	
					nation of how th ates in <i>40 CFR</i> s		y does not meet t	he definition of
							ts the minimum coceed to Item 12.5	riteria to be subject f.

□ Yes

No

sul	ojec	o any of the questions in Item 12.d, the facility does not meet the minimum criteria to be at to the full requirements of Section 316(b) of the CWA; however, a determination is ed based upon BPJ. Proceed to Item 12.e.				
e.	The facility does not meet the minimum requirements to be subject to the fill requirements of Section 316(b) and uses/proposes to use cooling towers.					
		Yes □ No				
		yes, stop here. If no, complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.b.1, and 3.a to ow for a determination based upon BPJ.				
f.	Oil	and Gas Exploration and Production				
	1.	The facility is subject to requirements at 40 CFR Part 435, Subparts A or D.				
		□ Yes ⊠ No				
		If yes, continue. If no, skip to Item 12.g.				
	2.	The facility is an existing facility as defined at $40\ CFR\ \S\ 125.92(k)$ or a new unit at an existing facility as defined at $40\ CFR\ \S\ 125.92(u)$.				
		□ Yes □ No				
		If yes, complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.b.1, and 3.a to allow for a determination based upon BPJ. If no, skip to Item 12.g.3.				
g.	Co	mpliance Phase and Track Selection				
	1.	Phase I - New facility subject to 40 CFR Part 125, Subpart I				
		□ Yes ⊠ No				
		If yes, check the box next to the compliance track selection, attach the requested information, and complete Worksheet 11.0, Items 2 and 3, and Worksheet 11.2.				
		□ Track I - AIF greater than 2 MGD, but less than 10 MGD				
		 Attach information required by 40 CFR §§ 125.86(b)(2)-(4). 				
		□ Track I – AIF greater than 10 MGD				
		 Attach information required by 40 CFR § 125.86(b). 				
		□ Track II				
		 Attach information required by 40 CFR § 125.86(c). 				
		Attachment: Click to enter text.				
	2.	Phase II - Existing facility subject to 40 CFR Part 125, Subpart J				
		□ Yes □ No				
		If yes, complete Worksheets 11.0 through 11.3, as applicable.				
	3.	Phase III – New facility subject to 40 CFR Part 125, Subpart N				
		□ Yes □ No				
		If yes, check the box next to the compliance track selection and provide the requested information				

	Track I – Fixed facility
	 Attach information required by 40 CFR § 125.136(b) and complete Worksheet 11.0, Items 2 and 3, and Worksheet 11.2.
	Track I – Not a fixed facility
	 Attach information required by 40 CFR § 125.136(b) and complete Worksheet 11.0, Item 2 (except CWIS latitude/longitude under Item 2.a).
	Track II - Fixed facility
	 Attach information required by 40 CFR § 125.136(c) and complete Worksheet 11.0, Items 2 and 3.
At	tachment: Click to enter text.
Item 1	3. Permit Change Requests (Instructions, Page 48)
	is only applicable to existing permitted facilities.
a. Is the	facility requesting a major amendment of an existing permit?
	Yes ⊠ No
inforn	list each request individually and provide the following information: 1) detailed nation regarding the scope of each request and 2) a justification for each request. In any supplemental information or additional data to support each request.
Click	to enter text.
b. Is the	facility requesting any minor amendments to the permit?
	Yes ⊠ No
If yes,	list and describe each change individually.
Click	to enter text.
c. Is the	facility requesting any minor modifications to the permit?
	Yes ⊠ No
If yes,	list and describe each change individually.

All laboratory tests performed must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - o periodically inspected by the TCEQ; or
 - located in another state and is accredited or inspected by that state;
 or
 - o performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review *30 TAC Chapter 25* for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: <u>Click to enter text.</u>	
Title: Click to enter text.	Note: The Laboratory Accreditation will be submitted with the pending effluent and so
Signature:	sampling reports. However, the TLAP
Date:	application is being submitted to begin the Administrative Review since the past TLAF Permit has now expired.

Click to enter text.	

Item 14. Laboratory Accreditation (Instructions, Page 49)

All laboratory tests performed must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - periodically inspected by the TCEQ; or
 - o located in another state and is accredited or inspected by that state; or
 - o performing work for another company with a unit located in the same site; or
 - o performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

Date:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: <u>Click to enter text.</u>

Title: Click to enter text.

Signature: ______

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 1.0: EPA CATEGORICAL EFFLUENT GUIDELINES

This worksheet is required for all applications for TPDES permits for discharges of wastewaters subject to EPA categorical effluent limitation guidelines (ELGs).

Item 1. Cate	gorical Industries	(Instructions, Pag	ge 53)
Is this facility subj	ject to any 40 CFR categori	cal ELGs outlined on pag	ge 53 of the instructions?
□ Yes ⊠	No		
If no, this workshe	eet is not required. If yes , p	rovide the appropriate i	nformation below.
40 CFR Effluent Guid	deline		
Industry	-	4	0 CFR Part
			w
NOTE: For all TPDI of oil and gas expl	luction/Process Da ES permit applications requioration and production wander the Oil and Gas Extraction 2 instead.	esting individual permi stewater (discharges int	t coverage for discharges o or adjacent to water in
a. Production Dat			
	a te data for effluent guidelir	nes with production-has	ad affluent limitations
Constitution in the same steam.	te data for enfluent guidem	ies with production-base	ed errident inintations.
Production Data Subcategory	Actual Quantity/Day	Design Quantity/Day	Units
Subcutegory	Actual Quantity/Day	Design Quantity/Duy	
		-	
	-		

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND APPLICATION OF EFFLUENT

This worksheet is required for all applications for a permit to disposal of wastewater by land application (i.e., TLAP)).

Item 1. Type of Disposal System (Instructions, Page 69)

Check the box next to the type of land disposal requested by this application:

\boxtimes	Irrigation	Subsurface application
	Evaporation	Subsurface soils absorption
	Evapotranspiration beds	Surface application
	Drip irrigation system	Other, specify: Click to enter text.

Item 2. Land Application Area (Instructions, Page 69)

Land Application Area Information

Effluent Application (gallons/day)	Irrigation Acreage (acres)	Describe land use & indicate type(s) of crop(s)	Public Access? (Y/N)
65,000 (Process WWTR)			
110,000 (Irrigation GW – Yearly Average)	53.6	Golf Course - Turf	Y (Private Course)

Item 3. Annual Cropping Plan (Instructions, Page 69)

Attach the required cropping plan that includes each of the following:

- Cool and warm season plant species
- Breakdown of acreage and percent of total acreage for each crop
- Crop growing season
- Harvesting method/number of harvests
- Minimum/maximum harvest height
- Crop yield goals
- · Soils map
- Nitrogen requirements per crop
- Additional fertilizer requirements
- Supplemental watering requirements
- Crop salt tolerances
- Justification for not removing existing vegetation to be irrigated

Attachment: K

Item 4. Well and Map Information (Instructions, Page 70)

- a. Check each box to confirm the required information is shown and labeled on the attached USGS map:
 - ☐ The exact boundaries of the land application area

 - Waste-disposal or treatment facilities
 - ☑ Effluent storage and tailwater control facilities
 - ☒ Buffer zones
 - All surface waters in the state onsite and within 500 feet of the property boundaries
 - △ All water wells within ½-mile of the disposal site, wastewater ponds, or property boundaries
 - All springs and seeps onsite and within 500 feet of the property boundaries Attachment: L
- b. List and cross reference all water wells located on or within 500 feet of the disposal site, wastewater ponds, or property boundaries in the following table. Attach additional pages as necessary to include all of the wells.

Well and Map Information Table

Well ID	Well Use	Producing? Y/N/U	Open, cased, capped, or plugged?	Proposed Best Management Practice
N/A				

Attachment: Click to enter text.

C.	Groundwater monitoring wells or lysimeters are/will be installed around the land
	application site or wastewater ponds.

□ Yes ⊠ No

If yes, provide the existing/proposed location of the monitoring wells or lysimeters on the site map attached for Item 4.a. Additionally, attach information on the depth of the wells or lysimeters, sampling schedule, and monitoring parameters for TCEQ review, possible modification, and approval.

Attachment: M (Groundwater Report Below)

d. Attach a short groundwater technical report using 30 TAC § 309.20(a)(4) as guidance. Attachment:

Item 5. Soil Map and Soil Information (Instructions, Page 71)

Check each box to confirm that the following information is attached:

- a. 🗵 USDA NRCS Soil Survey Map depicting the area to be used for land application with the locations identified by fields and crops.
- b.

 □ Breakdown of acreage and percent of total acreage for each soil type.
- c. 🛛 Copies of laboratory soil analyses. Attachment: N

Item 6. Effluent Monitoring Data (Instructions, Page 72)

a. Completion of Table 14 is required for all renewal and major amendment applications. Complete the table with monitoring data for the previous two years for all parameters regulated in the current permit. An additional table has been provided with blank headers for parameters regulated in the current permit which are not listed in Table 14.

Date (mo/yr)	Daily Avg Flow (gpd)	BOD5 (mg/L)	TSS (mg/L)	Nitrogen (mg/L)	Conductivity (mmhos/cm)	Total acres irrigated	Hydraulic Application rate (acre-feet/month)

Date (mo/yr)	Daily Avg Flow (gpd)	BOD5 (mg/L)	TSS (mg/L)	Nitrogen (mg/L)	Conductivity (mmhos/cm)	Total acres irrigated	Hydraulic Application rate (acre-feet/month)

b. Use this table to provide effluent analysis for parameters regulated in the current permit which are not listed in Table 14.

Additional Parameter Effluent Analysis

Date (mo/yr)			
10-2 10-2			
			-

c. Attach an explanation of all persistent excursions to permitted parameters and corrective actions taken. Attachment: <u>Click to enter text.</u>

Item 7. Pollutant Analysis (Instructions, Page 72)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): Click to enter text.
- b. \boxtimes Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Complete Tables 15 and 16.

Pollutant	Sample 1 (mg/L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
BOD (5-day)				
CBOD (5-day)				
Chemical oxygen demand			1	
Total organic carbon				
Diss•lved oxygen				
Amm•nia nitrogen				
Total suspended s●lids	Note: The Po	llutant Analys	sis and Soil An	alvsis
Nitrate nitrogen	are pending a	nd will be sul	ornitted once	
Total organic nitrogen			cation is being hinistrative Rev	ic M
Total phosphorus			t has now expir	
Oil and grease				
Total residual chlorine				
Total dissolved solids				
Sulfate				
Chloride				
Fluoride				
Total alkalinity (mg/L as CaCO3)				
Temperature (°F)				
pH (standard units)			1	

Table 16 for Outfall No.: Click to enter text. Samples are (check one): ☐ Composite □ Grab Sample 4 **Pollutant** Sample 1 Sample 2 Sample 3 MAL (µg/L) $(\mu g/L)$ $(\mu g/L)$ $(\mu g/L)$ $(\mu g/L)$ 2.5 Aluminum, total 5 Antimony, total Arsenic, total 0.5 3 Barium, total

Item 7. Pollutant Analysis (Instructions, Page 72)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): Click to enter text.
- b. \boxtimes Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Complete Tables 15 and 16.

Pollutant		San (mg	iple 1 /L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
BOD (5-day)						
CBOD (5-day)						
Chemical oxygen dema	and					
Total organic carbon						
Dissolved oxygen						
Ammonia nitrogen						
Total suspended solids	S					
Nitrate nitrogen						
Total organic nitrogen						
Total phosphorus						
Oil and grease						
Total residual chlorine						
Total dissolved solids						
Sulfate						
Chloride						
Fluoride						
Total alkalinity (mg/L	as CaCO3)					
Temperature (°F)						
pH (standard units)						
Table 16 for Outfall No.: (lick to enter	text.	Samples a	re (check one)	: □ Composi	ite 🗆 Grat
Pollutant	Sample (µg/L)	2 1	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (µg/L)
Aluminum, total						2.5
Antimony, total						5
Arsenic, total						0.5
Barium, total						3

Pollutant	Sample 1 (µg/L)	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (μg/L)
Beryllium, total					0.5
Cadmium, total					1
Chromium, total					3
Chromium, hexavalent					3
Chromium, trivalent					N/A
Copper, total				1	2
Cyanide, available					2/10
Lead, total					0.5
Mercury, total					0.005/0.0005
Nickel, total			ě		2
Selenium, total					5
Silver, total					0.5
Thallium, total					0.5
Zinc, total					5.0

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 3.1: SURFACE LAND APPLICATION AND APPLICATION

This worksheet **is required** for all applications for a permit to disposal of wastewater by surface land application or evaporation.

Item 1. Edwards Aquifer (Instructions, Page 73)

a. Is the facility subject to 30 TAC Chapter 213, Edwards Aquifer Rules? No Yes X If no, proceed to Item 2. If yes, complete Items 1.b and 1.c. b. Check the box next to the subchapter applicable to the facility. 30 TAC Chapter 213, Subchapter A 30 TAC Chapter 213, Subchapter B c. If 30 TAC Chapter 213, Subchapter A applies, attach either: 1) a Geologic Assessment (if conducted in accordance with 30 TAC § 213.5) or 2) a report that contains the following: A description of the surface geological units within the proposed land application site and wastewater pond area. The location and extent of any sensitive recharge features in the land application site and wastewater pond area • A list of any proposed BMPs to protect the recharge features. Attachment: Click to enter text. Item 2. Surface Spray/Irrigation (Instructions, Page 73) a. Provide the following information on the irrigation operations: Area under irrigation (acres): 53.6 Design application rate (acre-ft/acre/vr): 1.35 (Process WWTR – not including GW irrigation) Design application frequency (hours/day): 4 Design application frequency (days/week): 7 Design total nitrogen loading rate (lbs nitrogen/acre/year): N/A (Grndwtr EDR waste – Not including fertilizer applied to gold course) Average slope of the application area (percent): o (Golf course) Maximum slope of the application area (percent): o (Golf course) Irrigation efficiency (percent): 65 – Desert conditions Effluent conductivity (mmhos/cm): (Pending) Soil conductivity (mmhos/cm): (Pending) Curve number: Click to enter text.

Describe the application method and equipment: Golf course irrigation - Low angle spray

b. Attach a detailed engineering report which includes a water balance, storage volume calculations, and a nitrogen balance. Attachment: O

Item 3. Evaporation Ponds (Instructions, Page 74)

- a. Daily average effluent flow into ponds: Click to enter text. gallons per day
- b. Attach a separate engineering report of evaporation calculations for average long-term and worst-case critical conditions. Attachment: Click to enter text.

Item 4. Evapotranspiration Beds (Instructions, Page 74)

a. Provide the following information on the evapotranspiration beds:

Number of beds: Click to enter text.

Area of bed(s) (acres): <u>Click to enter text.</u>

Depth of bed(s) (feet): <u>Click to enter text.</u>

Void ratio of soil in the beds: Click to enter text.

Storage volume within the beds (include units): <u>Click to enter text.</u>

Description of any lining to protect groundwater: <u>Click to enter text.</u>

- b. Attach a certification by a licensed Texas professional engineer that the liner meets TCEQ requirements. Attachment: Click to enter text.
- c. Attach a separate engineering report with water balance, storage volume calculations, and description of the liner. Attachment: <u>Click to enter text.</u>

Item 5. Overland Flow (Instructions, Page 74)

a. Provide the following information on the overland flow:

Area used for application (acres): Click to enter text.

Slopes for application area (percent): Click to enter text.

Design application rate (gpm/foot of slope width): Click to enter text.

Slope length (feet): Click to enter text.

Design BOD5 loading rate (lbs BOD5/acre/day): Click to enter text.

Design application frequency (hours/day): Click to enter text.

Design application frequency (days/week): Click to enter text.

b. Attach a separate engineering report with the method of application and design requirements according to *30 TAC § 217.212*. Attachment: Click to enter text.

Lajitas Water Treatment Plant

TLAP Permit Application

Exhibits Listing

Exhibit A Core Data Form

Exhibit B Plain Language Template

Exhibit C Public Involvement Plan

Exhibit D TLAP Disposal Area Lease Agreement

Exhibit E USGS Map

Exhibit F TLAP Disposal Area

Exhibit G Landowners' Map

Exhibit H Original Photos

Exhibit I Facility Map

Exhibit J Flow Schematic

Exhibit K Annual Cropping Plan

Exhibit L Well and Map Information

Exhibit M Groundwater Technical Report

Exhibit N Soil Map and Soil Information

Exhibit O Water Balance

Exhibit A Core Data Form

TCEQ Use Only



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call \$12-239-5175.

SECTION I: General Information

			100100		ith the or	narom application			
						Regulated Entity	Reference	Number	(if issued)
				200		N 102079365			
NII	: C <u>ustom</u> e	r Inforn	<u>natio</u>	<u>n</u>					
Customer	Information	5. Effective	Date for	Customer In	ormatio	n Updates (mm/	'dd/yyyy)		
omer Legal Nam	And the second s						Entity Owner	rship	
			utomatica	ally based o	what is	current and act	tive with the	e Texas Si	acretary of State
r Legal Na	ame (If on individual,	print last name fir	st: eg: Doe,	, John)		I <u>[new Custom</u>	er, enter prev	vious Custo	omer below:
ipal Service	es Company LLC			\$					
PA Filing	Number		8. TX State Tax ID (11 digits) 32034356587			9. Federal Tax ID (9 digits) 32-0225678		10. DUNS Number (if applicable)	
Customer	r: 🛛 🖂 Corpo	ration			ndiv	idual	Partners	hip: 🔲 G	eneral 🔲 Limited
City [County 🔲 Federal (Local State	Other		☐ Sole	Proprietorship	Othe	ır:	
		51-500 🗌 501 :	and higher			13. Independ	lently Owne	ed and O	perated?
r Role (Pr	oposed or Actual) - o	is it relotes to the f	Regulated E	Intity listed on	this form	. Please check one	of the follow	ing	
al License	Operator Responsible					Othe	er;		
15. Mailing 14241 Dallas Parkway, Ste 800									
City Dallas State TX						ZIP 75254 ZIP + 4			
Mailing	formation /if outside	to UCA)	1	1.5					
	r Reference of Customer Legal Name of Comp Legal Name of Comp Legal Name of Comp Legal Name of Comp City Customer City City City City City	rmit, Registration or Authorizated (Care Data Form should be such a (Care Data Form should be such	ermit, Registration or Authorization (Care Data Formal (Care Data Form should be submitted with the real (Care Data Form should be submitted with the real Reference Number (if issued) Source	rmit, Registration or Authorization (Care Data Form should be all (Core Data Form should be submitted with the renewal for Reference Number (if issued) Follow the for CN or Central IN II: Customer Information S. Effective Date for Update to Customer Information Customer Information S. Effective Date for Owner Submitted here may be updated automatically as Comptroller of Public Accounts (CPA). Legal Name (If an individual, print last name first: eg: Doe pal Services Company LLC PA Filling Number 8. TX State Tax ID (11 32034356587) Customer: Corporation City County Federal Local State Other of Employees 21-100 101-250 251-500 501 and higher Role (Proposed or Actual) – as it relates to the Regulated it Income Responsible Party VCP/BSA Ap 14241 Dallas Parkway, Ste 800 City Dallas State	Follow this link to search for CN or RN numbers in Central Registry** Should be submitted with the renewal form) Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Should be for Customer Information Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for CN or RN numbers in Central Registry** Follow this link to search for Customer Information Follow this	rmit, Registration or Authorization (Care Data Form should be submitted with the profile (Care Data Form should be submitted with the renewal form) r Reference Number (if issued) r Reference Number (if issued) for CN or RN numbers in Central Registry** RM DN II: Customer Information Customer Information 5. Effective Date for Customer Information customer (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts (CPA). r Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts (CPA). r Legal Name (If on individual, print last name first: eg: Doe, John) pal Services Company LLC PA Filling Number 8. TX State Tax ID (11 digits) 32034356587 Customer: Corporation Individual individual print last name first: eg: Doe, John) The customer: Corporation Customer: Custome	rmit, Registration or Authorization (Care Data Form should be submitted with the program application (Care Data Form should be submitted with the renewal form) r Reference Number (if issued) r Reference Number (if issued) follow this link to search for CN or RN numbers in Central Registry** RN 102079365 IN II: Customer Information S. Effective Date for Customer Information Updates (mm/ Change in Regulated Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts) er Name submitted here may be updated automatically based on what is current and act as Comptroller of Public Accounts (CPA). Legal Name (If an individual, print last name first: eg: Doe, John) I I new Customer PA Filling Number 8. TX State Tax ID (11 digits) 32:034356587 9. Federal Tax (9 digits) 32:0225678 Customer: City County Federal Local State Other Sole Proprietorship of Employees 21:100 101:250 251:500 501 and higher r Role (Proposed or Actual) - as it relates to the Regulated Entity listed on this form. Fleose check one of County Count	In the program application of Authorization (Care Data Form should be submitted with the program application.) Content Core Data Form should be submitted with the renewal form Content	In the program application. If Care Data Form should be submitted with the renewal farm. If Reference Number (if issued) If Pollow this link to search for CN of RN numbers in Central Resistor* If RN 102079365 IN II: Customer Information S. Effective Date for Customer Information Updates (mm/dd/yyyy) Customer Information

18, Telephone Number	19. Extension or Code	20. Fax Number (if applicable)	
(469) 317-3424		() -	

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If 'New Regulated Entity" is selected, a new permit application is also required.)

New Regulated Entity	☐ Update	to Regulated Entit	y Name 🔀 Updai	te to Regulat	ed Entity Infor	mation			
The Regulated Entity No as Inc, LP, or LLC).	ame submit	ted may be upd	ated, in arder to n	neet TCEQ	Core Data St	andards (removal o	f organizatio	nal endings such	
22. Regulated Entity Na	me (Enter n	ame of the site who	ere the regulated act	lon is taking	place.)				
Lajitas Water Treatment Pla	ant								
23. Street Address of the Regulated Entity:	New wet	and is located abo	ut 700-ft north of FN	1-170 and at	oout 0.5 miles	northeast of the Mave	rick R anch RV I	ark entrance,	
(No PO Boxes)	City	Lajitas	State	ТХ	ZIP	79852	ZIP + 4		
24. County	Brewster			1			1		
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		If no Stre	eet Address is prov	ided, field	s 25-28 are r	equired.			
25. Description to Physical Location:	hotels, as	shown on the app	lication exhibits. The	facility is al	so located app	outh of SH-170 and abo proximately 0.31 miles t town of Lajitas, Brew	southeast of th	e intersection of	
26. Nearest City						State	Nea	rest ZIP Code	
aJitas (Private Resort Comn	nunity)					TX	798	52	
.atitude/Longitude are i ised to supply coordinat						ards. (Geocoding of	the Physical	Address may be	
27. Latitude (N) In Decim	nal:	29.261		28.	Longitude (W) In Decimal:	103.771		
egrees	Minutes		Seconds	Deg	rees	Minutes		Seconds	
29		15	40.7		103	4	46 15.4		
9. Primary SIC Code I digits)		. Secondary SIC digits)	Code	31. Prim (5 or 6 di	ary NAICS Co	32. Sec (5 or 6	condary NAIC	S Cade	
941	49	45		221310		221320			
3. What is the Primary I	Business of	this entity? (D	o not repeat the SIC o	or NAICS des	cription.)				
esort community and golf o	ourse								
4. Mailing	14241 Da	llas Parkway, Ste &	300						
ddress:	City	Dallas	State	TX	ZIP	75254	ZIP+4		
5. E-Mail Address:		n@thehalmesfirm							
5. Telephone Number			37. Extension or	Code	38. F	ax Number (if applica	able)		
167) 317-3424				-	1,		-		
,									

ignature:			hely			Date:	16/25	
lame (In Print):	Sonia Au	be	1			Phone:	(214) 981-700	
ompany:	Lajitas M	unicipal Services Compa	ny LIC	Job Titl	le:	Vice President Authorized Repu	Representative	
By my signature	below, I certif		viedge, that the inform			als form is true and comple adates to the ID numbers ic	te, and that I have signature autho entified in field 39.	
	\/. A.		(210)581-5555	mark.i	OELZEI	@casmoery.com		
2. Telephone Number 210) 581-1111			_	45. E-Mail Address mark.roetzel@cdsmuery.com				
ECTION IV: Preparer Information O. Name: Mark Roetzel, P.E.			ormation	41. Title	6 '	Project Engineer		
☐ Voluntary Cle	anup		☐ Wastewater Agriculture		☐ Water Rights		Other:	
Sludge		Storm Water	☐ Title V Air		☐ Tires		Used Oil	
Municipal Solid Waste		Review Air	OSSF		Petroleum Storage Tank		☐ PWS	
		New Source						

TCEQ-10400 (11/22) Page 3 of 3

Unanimous Consent in Lieu of Special Meeting of the Sole Member of Lajitas Municipal Services Company LLC

March 6, 2024

The undersigned, being the sole Member of LAJITAS MUNICIPAL SERVICES COMPANY LLC (the "Company"), does hereby consent to and adopt in all respects the following resolutions and such consent shall have the same force and effect as if such action was taken at a duly called and convened special meeting:

RESOLVED, that the sole Member of the Company hereby authorizes, approves and empowers the following individual to serve as Authorized Representative of the Company, to make sign, execute, endorse and deliver in the name of and on behalf of the Company, any and all documents, including, but not limited to, written instruments, agreements, contracts, deeds, powers of attorney, transfers, assignments, obligations, certificates and other instruments of any other nature, entered into by the Company:

Sonia W. Aube

FURTHER RESOLVED, that the consent contemplated by the foregoing resolution is reasonably expected to benefit the Company, both directly and indirectly.

IN WITNESS WHEREOF, the undersigned has executed this Consent to be effective as of the day, month and year first above written.

SOLE MEMBER:

Lajitas Capital Partners LLC, a Texas limited liability company

By: Warren Lajitas Interests LLC, a Texas limited liability company,

its Managing Member

Kelcy L. Warren, Managing Member

Exhibit B Plain Language Template


The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Lajitas Municipal Services Company LLC (CN-603406604) operates the Lajitas Water Treatment Plant (RN-102079365) a 0.3mgd groundwater treatment EDR membrane drinking water plant. The facility is located about 500 feet south of SH-170 and about 0.13 miles southeast of the intersection of Comanche Mesa Drive and Texas Mountain Trail, in the unincorporated resort community town of Lajitas, Brewster County, Texas, 79852. Lajitas is proposing to dispose of membrane wastewater by irrigation on the Lajitas Golf Course. This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are concentrated from the Santa Elena source aquifer, and include chloride, sulfate, iron, calcium, other typical groundwater mineral, and naturally occurring radioactive material (NORM) constituents present in the source aquifer. The source water is treated by electro-dialysis reversal (EDR) membranes to produce a safe drinking water supply, and the process wastewater contains only the source water concentrates.

Exhibit C Public Involvement Plan

.



Public Involvement Plan Form for Permit and Registration Applications

The Public Involvement Plan is intended to provide applicants and the agency with information about how public outreach will be accomplished for certain types of applications in certain geographical areas of the state. It is intended to apply to new activities; major changes at existing plants, facilities, and processes; and to activities which are likely to have significant interest from the public. This preliminary screening is designed to identify applications that will benefit from an initial assessment of the need for enhanced public outreach.

All applicable sections of this form should be completed and submitted with the permit or registration application. For instructions on how to complete this form, see TCEQ-20960-inst.

Section 1. Preliminary Screening							
New Permit or Registration Application New Activity – modification, registration, amendment, facility, etc. (see instructions)							
Section 2. Secondary Screening							
Requires public notice,							
Considered to have significant public interest, and							
Located within any of the following geographical locations:							
 Austin Dallas Fort Worth Houston San Antonio West Texas Texas Panhandle Along the Texas/Mexico Border Other geographical locations should be decided on a case-by-case basis 							
If all the above boxes are not checked, a Public Involvement Plan is not necessary. Stop after Section 2 and submit the form.							
Public Involvement Plan net applicable to this application. Provide brief explanation.							
Past (and currently proposed) TLAP permit is for irrigation disposal of Lajitas groundwater WTP mem							

Exhibit D TLAP Disposal Area Lease Agreement

WHEN RECORDED, RETURN TO:

RONALD L. HOLMES HOLMES FIRM PC 14241 North Dallas Parkway Suite 800 Dallas, Texas 75254

ACCESS, STORAGE AND DISPOSAL EASEMENT AGREEMENT

STATE OF TEXAS	§ §	Know All Men By These Presents:
COUNTY OF BREWSTER	§	

THIS ACCESS, STORAGE AND DISPOSAL EASEMENT AGREEMENT (this "Agreement"), is made and entered into by and between LAJITAS CAPITAL PARTNERS LLC a Texas limited liability company ("Grantor"), and LAJITAS MUNICIPAL SERVICES COMPANY LLC, a Texas limited liability company ("Grantee"), as of the date last herein written.

RECITALS:

- Grantor is the owner of that certain real property located in the unincorporated area of Laiitas, Texas commonly known as the Laiitas Golf Resort and Spa ("Laiitas"), within which is located the golf course known as Black Jack's Crossing, a portion of which golf course, described in **EXHIBIT** "A" attached hereto, serves as a disposal area, by irrigation, of the waste water effluent from Grantee's Water Treatment Plant (the "Irrigated Area").
- Grantee has requested, and Grantor is amendable to, providing to Grantee easements for the purposes (the "Easement Purposes") of: (i) laying, repairing and replacing a transport line (the "Transport Line Easement") from Grantee's Water Treatment Plant to the Irrigated Area over, under, upon and across that portion of Grantor's lands within Lajitas as described in Exhibit "B" attached hereto (the "Transport Line Easement Area"); (ii) access upon and use of the Irrigated Area for the storage and disposal, by irrigation, of the waste water effluent from Grantee's Water Treatment Plant (the "Disposal Fasement") onto the Irrigated Area; and (iii) access over and use of Grantor's lands (the "Ancillary Area") in the immediate area of the Irrigated Area and the Transport Line Easement Area reasonably necessary to effectively carry out the Easement Purposes (the "Ancillary Easement").
- NOW, THEREFORE, for and in consideration of the sum of TEN DOLLARS (\$10.00) and other good and valuable consideration paid by Grantee, the receipt and sufficiency of which are hereby acknowledged and confessed by the parties hereto, Grantor and Grantee do hereby agree as follows:
 - 1. Grantor has GRANTED, and by these presents does hereby GRANT, unto Grantee

for the benefit of Grantee, on a non-exclusive, perpetual, and limited basis the Transport Line Easement, the Disposal Easement and the Ancillary Easement (together, the "Easements") in, over, upon, across and under, respectively, the Transport Line Easement Area, the Irrigated Area and the Ancillary Area (together, the "Easement Areas") for the Easement Purposes.

- TO HAVE AND TO HOLD the Easements unto Grantee, its successors and assigns, forever; and Grantor does hereby bind itself, and its successors and assigns, to warrant and forever defend all and singular the Easements granted herein, unto Grantee, and its successors and assigns, against every person whomsoever lawfully claiming or to claim the same or any part thereof, by, through or under Grantor, but not otherwise, but subject to all matters of public record which are and remain valid and enforceable as to the Easement Areas.
- 3. Grantor hereby reserves and retains unto itself, its successors and assigns, the nonexclusive right to use the Easement Areas for the playing of golf and the maintenance, repair and replacement of the golf course within the Irrigated Area. In furtherance of the forgoing, Grantee shall provide to Grantor, in advance and on a routine basis, a schedule of activities to be conducted in the Easement Areas, shall coordinate those activities in advance with the General Manager of Black Jack's Crossing, and shall conduct such activities in a manner to minimize interference with the players within the Irrigated Area and the maintenance, repair and replacement of the Irrigated Area by Grantor.
- Grantee shall provide to Grantor evidence of insurance, insuring Grantee against claims for personal injury and property damage, in amounts, with coverages and by issuers reasonably acceptable to Grantor, naming Grantor as additional insured by endorsement, and shall do so at least thirty (30) days prior to expiration of the current term thereof.
- 5. Grantee shall be responsible for maintaining all of Grantee's property within the Easement Areas in good working condition. To the extent any of such property is visible above ground, Grantee shall cause same to be painted or screened in a manner reasonably acceptable to Grantor.
- Grantee acknowledges that working within, on or around a golf course presents certain inherent risks, such as golf balls travelling at high speeds and sometimes in errant directions not consistent with the golf course design. Grantee hereby assumes such risks when working within, on or around the Irrigated Area and hereby indemnifies, holds harmless and agrees to defend Grantor from and against any and all claims for personal injury or property damage of those employed or engaged by Grantee to perform work or services for Grantee within, on or around the Irrigated area.
- 7. This Agreement may be executed in any number of counterparts, each of which shall be an original, and all of such counterparts together shall be deemed to constitute one original agreement.

- 8. This Agreement constitutes the entire agreement between Grantor and Grantee relating to the subject matter hereof. Any oral representations or agreements made prior to or contemporaneously with this Agreement are superseded by this Agreement. Any amendment to this Agreement must be in writing and signed by Grantor and Grantee.
- 9. In the event any controversy, claim or dispute arises relating to this Agreement, then the prevailing party in any judicial proceeding concerning such controversy, claim or dispute shall be entitled, in addition to any other remedies to which it may be entitled, at law or in equity, to recover its reasonable attorneys' fees and costs of court.
- 10. This Agreement shall be governed and construed in accordance with laws of the state of Texas. All obligations of the parties hereto shall be performed in Brewster County, Texas.

DATED effective as of

GRANTOR:

LAJITAS CAPITAL PARTNERS LLC
a Texas limited liability company

Name: Sonia Aube

Its: Authorized Representative

GRANTEE:

By:

LAJITAS MUNICIPAL SERVICES COMPANY LLC

a Texas limited liability company

Name: Sonia Aube

Its: Authorized Representative

STATE OF TEXAS	§
	Ş
COUNTY OF DALLAS	§

This instrument was acknowledged before me on the Anday of Toly, 2025, by SONIA AUBE, an authorized representative of LAJITAS CAPITAL PARTNERS LLC, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed same for the purposes therein expressed and the capacity therein stated.



My Commission Expires:

STATE OF TEXAS COUNTY OF DALLAS

This instrument was acknowledged before me on the Moday of Jin 2025, by SONIA AUBE, an authorized representative of LAJITAS MUNICIPAL SERVICES LLC, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed same for the purposes therein expressed and the capacity therein stated.



Notary Public, State of Texas

My Commission Expires:

EXHIBIT "A"

IRRIGATED AREA



LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

EXHIBIT "A"

BEING a 188.44 acre (8,208,337 square feet) tract of land lying in the T.C. RR. Co. Section 37, Block 341, Abstract 5162, the T.C. RR. Co. Section 100, Block 341, Abstract 9053, same being a portion of a tract of land as described as "Exhibit A" in a deed to Lajitas Capital Partners, LLC, and recorded in volume 265, page 127, Official Public Records, Brewster County, Texas, same also being described by a drawing (Lajitas Easement.dwg dated June 25, 2025) attached to and made part hereof and more particularly described as follows:

COMMENCING at a brass cap found in concrete for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of Big Bend National Park, the northwest corner of the T.C. RR. Co. Section 39, Block 341, Abstract 1556 and the southwest corner of the aforementioned T.C. RR. Co. Section 100;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract, N44°27'55"W a distance of 35.37 feet to a point for the **POINT OF BEGINNING** and an interior angle corner of the herein described 188.44 acre tract:

THENCE across the lands of the aforementioned Lajitas Capital Partners tract the following thirty-four (34) courses:

S00°31'33"W a distance of 3,105.00 feet to a point;

S20°05'31"W a distance of 1,110.74 feet to a point;

\$10°53'10"E a distance of 622.55 feet to a point;

S32°31'16"W a distance of 309.93 feet to a point;

N53°39'45"W a distance of 566.76 feet to a point;

S84°52'18"W a distance of 289.07 feet to a point;

N83*12'51"W a distance of 393.52 feet to a point;

N88°47'31"W a distance of 357.17 feet to a point;

N75°54'08"W a distance of 115.19 feet to a point;

N19°09'36"E a distance of 125.04 feet to a point;

N74°17'23"E a distance of 185.57 feet to a point;

N46°53'35"E a distance of 333.48 feet to a point;

Page 1 of 5 Lajitas Variable Width Easement.docx June 26, 2025 LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

N36°52'25"E a distance of 486.01 feet to a point of curvature;

Along a curve to the left having a radius of 613.81', length 344.55', delta 32°09'43" and a chord that bears N07°58'43"E a distance of 340.05 feet to a point of reverse curvature;

Along a curve to the right having a radius of 793.71', length 231.18', delta 16°41'17" and a chord that bears N19°55'00"E a distance of 230.36 feet to a point of reverse curvature;

Along a curve to the left having a radius of 2,957.09', length 454.60', delta 08°48'30" and a chord that bears N18°58'39" E a distance of 454.15 feet to a point of compound curvature;

Along a curve to the left having a radius of 771.42', length 580.20', delta 43°05'34" and a chord that bears N25°21'06"W a distance of 566.62 feet to a point of reverse curvature;

Along a curve to the right having a radius of 13,234.87', length 449.02', delta 01°56'38" and a chord that bears N37°53'11"W a distance of 448.99 feet to a point of compound curvature;

Along a curve to the right having a radius of 457.58', length 180.00', delta 22°32'16" and a chord that bears N23°26'47" W a distance of 178.84 feet to a point of compound curvature;

Along a curve to the right having a radius of 174.16', length 122.00', delta 40°08'12" and a chord that bears N11°33'05"E a distance of 119.52 feet to a point of tangency;

N31°30'40"E a distance of 720.19 feet to a point of curvature;

Along a curve to the left having a radius of 450.76°, length 349.77°, delta 44°27'33" and a chord that bears N14°07'43"E a distance of 341.06 feet to a point of tangency;

N14°48'12"W a distance of 258.02 feet to a point;

N16°53'51"W a distance of 428.69 feet to a point;

N35°14'13"W a distance of 1,333.96 feet to a point;

N21°52'16"W a distance of 540.03 feet to a point of curvature;

Along a curve to the right having a radius of 81.77', length 151.08', delta 105°51'27" and a chord that bears N32°16'35"E a distance of 130.49 feet to a point of compound curvature;

Along a curve to the right having a radius of 1,612.53', length 372.61', delta 13°14'22" and a chord that bears \$89°36'01"E a distance of 371.78 feet to a point of compound curvature;

Page 2 of 5 Lajitas Variable Width Easement.docx June 26, 2025 LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

Along a curve to the right having a radius of 2,051.03', length 1,033.12', delta 28°51'37" and a chord that bears \$68°56'14"E a distance of 1,022.23 feet to a point of reverse curvature:

Along a curve to the left having a radius of 2,666.96', length 558.25', delta 11°59'35" and a chord that bears S38°32'54"E a distance of 557.23 feet to a point of compound curvature:

Along a curve to the left having a radius of 3,252.14', length 599.22', delta 10°33'25" and a chord that bears \$52°20'45" E a distance of 598.37 feet to a point of compound curvature;

Along a curve to the left having a radius of 1,477.45', length 428.69', delta 16°37'28" and a chord that bears \$67°22'49"E a distance of 427.18 feet to a point of tangency;

S00°58'05"W a distance of 259.52 feet to a point;

N89°27'23"W a distance of 304.09 feet to the PLACE OF BEGINNING and containing 188.44 acres (8,208,336 square feet) of land.

The bearing basis for this survey is Grid North, Texas State Plane Coordinate System, NAD 1983(2011), South Central Zone. All distances and coordinates are surface, (Grid X 1.00024 = Surface). U.S. Survey Feet.

THE STATE OF TEXAS X

KNOWN TO ALL MEN BY THESE PRESENTS:

COUNTY OF BEXAR X

I, Darryl L. Zercher, a Registered Professional Land Surveyor, do hereby certify that the above field notes were prepared using information obtained by an on the ground survey made under my direction and supervision from March of 2024 thru May of 2025.

Date 27 day of June 2025 A.D.


X

Darryl L. Zercher

Registered Professional Land Surveyor


No. 5609 - State of Texas

Page 3 of 5 Lajitas Variable Width Easement.docx June 26, 2025



CURVE	RADIUS	LENGTH	DELTA	CHORD BEARING	CHORD LENGTH
Ç9	81.77'	151.08	105'51'27"	N32'16'35"£	130.49'
C10	1,612.53	372.61	13'14'22"	S89'36'01"E	371.78
C11	2,051.03	1,033.12	28'51'37"	S68'56'14"E	1,022.23
C12	2,666.96	558.25	11'59'35"	\$38'32'54"E	557.23'
C13	3,252.14	599.22'	10"33'25"	S52°20′45"E	598.37'
C14	1,477.45	428.69'	16'37'28"	S67'22'49"E	427.18'

LINE	BEARING	DISTANCE
L1	N44'27'55'W	35.37'
L13	N16'53'51"W	428.69
L14	N35'14'13'W	1,333.96
L15	N21°52'16"W	540.03'
L16	\$00'58'05"W	259.52'
L17	N89°27'23"W	304.09








SCALE IN FEET 1"=500"

DRAWN BY: DATE:
J.R.F. 06/26/2025
DRAWING NAME:

_LAJITAS EASEMENT.DWG

188.44 ACRES BREWSTER COUNTY, TEXAS



Ехнівіт "В"

TRANSPORT LINE EASEMENT AREA



LAJITAS CAPITAL PARTNERS, LLC
10' WIDE PERMANENT WATERLINE EASEMENT
BREWSTER COUNTY, TEXAS
0.286 OF AN ACRE TRACT

EXHIBIT ">"

BEING a 0.286 of an acre (12,454 square feet) tract of land lying in the T.C. RR. Co. Section 37, Block 341, Abstract 5162, Brewster County, Texas, same being a portion of a tract of land as described as "Exhibit A" in a deed to Lajitas Capital Partners, LLC, and recorded in volume 265, page 127, Official Public Records, Brewster County, Texas, same also being described by a drawing (121166.26 Lajitas 10' Water Easement.dwg dated June 24, 2025) attached to and made part hereof and more particularly described as follows:

COMMENCING at a brass cap found in concrete for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of Big Bend National Park, the northwest corner of the T.C. RR. Co. Section 39, Block 341, Abstract 1556 and the southwest corner of the T.C. RR. Co. Section 100, Block 341, Abstract 9053;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract, N36°45'09"W a distance of 1,556.85 feet to a point for the **POINT OF BEGINNING** and the most southerly southeast corner of the herein described 0.286 of an acre tract:

THENCE across the lands of the aforementioned Lajitas Capital Partners tract the following nine (9) courses:

N54°44'49"W a distance of 17.18 fect to a point;

N19°08'06"W a distance of 300.80 feet to a point;

N43°24'57"E a distance of 210.20 feet to a point;

N81°30'59"E a distance of 287.93 feet to a point;

N65°28'57"E a distance of 447.42 feet to a point,

S26°44'25"E a distance of 10.01 feet to a point, from which a brass disk found in concrete bears \$55°39'25"E a distance of 3,435.94 feet for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of the aforementioned Big Bend National Park, the southeast corner of the aforementioned T.C. RR. Co. Section 100, the northeast corner of the aforementioned T.C. RR. Co. Section 39, and an angle corner of the Thomas V. Skaggs Survey 92, Block 341, Abstract 9050;

\$65°28'57"W a distance of 449.22 feet to a point;

\$81°30'59W" a distance of 285.89 feet to a point;

S43°24'57"W a distance of 200.67 feet to a point;

Page 1 of 3 Lajitas 10' Waterline Basement.docx June 24, 2025 LAJITAS CAPITAL PARTNERS, LLC 10' WIDE PERMANENT WATERLINE EASEMENT BREWSTER COUNTY, TEXAS 0.286 OF AN ACRE TRACT

\$19°08'06"E a distance of 308.69 feet to the PLACE OF BEGINNING and containing 0.286 of an acre (12,454 square feet) of land.

The bearing basis for this survey is Grid North, Texas State Plane Coordinate System, NAD 1983(2011), South Central Zone. All distances and coordinates are surface, (Grid X 1.00024 = Surface). U.S. Survey Feet.

THE STATE OF TEXAS X

X KNOWN TO ALL MEN BY THESE PRESENTS:

COUNTY OF BEXAR X

1, Darryl L. Zercher, a Registered Professional Land Surveyor, do hereby certify that the above field notes were prepared using information obtained by an on the ground survey made under my direction and supervision from March of 2024 thru May of 2025.

Date 27 day of June 2025 A.D.



Darryl L! Zercher Registered Professional Land Surveyor No. 5609 - State of Texas




Exhibit E USGS Map





Exhibit F TLAP Disposal Area




TLAP DISPOSAL AREA





SCALE: AS NOTED DATE: JUNE 2025 DRAWN BY: CDSm REV.


TLAP PERMIT EXHIBITS.DWG EXHIBIT - F

Exhibit G Landowners' Map









Lajitas TLAP Permit-Landowners

- 1 Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- National Park Service
 Land Resources Program Center
 P.O. Box 25287
 Denver, Co. 80225
- 3 Mickey and Michelle MorganP.O. Box 260Aubrey, Tx. 76227
- 4 Pitbull Properties LLC 6 Desta Drive, Ste 1000 Midland, Texas 79705
- 5 Lajitas Amigos LLC940 Mary PreissNew Braunfels, Tx. 78132
- 6 Studio Lajitas LLC 1300 W. Lynn St. Ste. 110 Austin, Tx. 78703
- Lajitas Capital Partners LLC
 8111 Westchester Drive, Ste. 600
 Dallas, Tx. 75225
- 8 Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225

- 9 Lajitas Capital Partners LLC
 8111 Westchester Drive, Ste. 600
 Dallas, Tx. 75225
- 10 Wittmann Pete 4814 Kelsey Dallas, Tx. 75229
- Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- 12 Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- 14 Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- Lajitas Capital Partners LLC8111 Westchester Drive, Ste. 600Dallas, Tx. 75225
- 16 Katthage Godfrey C & Rizuam M KatthageRevocable Trust10 County Road 3663Splendora, Tx. 77372

17 Ortiz Manuel C and Nadia Hernandez P.O. Box 29 Iraan, Tx. 79744 Exhibit H Original Photos




















Exhibit I Facility Map




Exhibit J Flow Schematic






Exhibit K Annual Cropping Plan

Attach the required cropping plan that includes each of the following:

- 1) Cool and warm season plant species
 - a) Paspalum Bermuda grass
- 2) Breakdown of acreage and percent of total acreage for each crop
 - a) 53.59 acres of Paspalum Bermuda grass
- 3) Crop growing season
 - a) March November
- 4) Harvesting method/number of harvests
 - a) No harvesting, only mowing
- 5) Minimum/maximum harvest height
 - a) Mow from 1/8" to 2"
- 6) Crop yield goals
 - a) None
- 7) Soils map
 - a)
- 8) Nitrogen requirements per crop
 - a) .05 pounds of Nitrogen per acre per year.
- 9) Additional fertilizer requirements
 - a) .05 pounds of phosphorus per acre per year.
 - b) .05 pounds of potassium per acre per year.
- 10)Supplemental watering requirements
 - a) 103.49 Acer feet of water per year
- 11)Crop salt tolerances
 - a) High tolerance 5500 ppm to 10,000 ppm.
- 12) Justification for not removing existing vegetation to be irrigated
 - a) Golf Course requires grass.

Exhibit L Well and Map Information





STATE OF TEXAS WELL REPORT for Tracking #2114 Owner: WW-3 Owner Well #: Lajitas Resort, Ltd. Address: HC 70, Box 400 Grid #: 73-42-9 Terlingua, TX 79852 Latitude: 29° 15' 41" N Well Location: Lajitas Resort Lajitas, TX 79852 Longitude: 103° 46' 23" W Well County: Brewster No Data Elevation: Type of Work: New Well Proposed Use: Irrigation

Drilling Start Date: 3/8/2001

Drilling End Date: 8/1/2001

Borehole:

Diameter (in.)	Top Depth (ft.)	Bollom Dopth (ft.)	
18	0	41	
12	41	1015	
7.875	1015	1040	

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

	Annul	ar Seal	Data:
--	-------	---------	-------

Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
0	20	10
Mar.		

Seal Method: Gravity

Distance to Property Line (ft.): No Data

Sealed By: Geoprojects

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Sleeve Installed

Water Level:

67 ft. below land surface on 2001-08-01

Measurement Method: Unknown

Packers:

#1 Spring Steel Basket 1004

#2 Formation 10

Type of Pump:

Submersible

Well Tests:

Pump

Yield: 400 GPM with 6 ft. drawdown after 36 hours

Page 1 of 2

Water Quality:

Strata Depth (ft.)	Water Type
1020	Santa Elena

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which

contained injurious constituents?:

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: Geoprojects International, Inc.

8834 Circle Drive Austin, TX 78736

Driller Name:

Benito Hinojosa

License Number: 3127

Comments:

7/30/2025 9:21:08 AM

TWDB SWN 73-42-903

Lithology: **DESCRIPTION & COLOR OF FORMATION MATERIAL**

Casing: BLANK PIPE & WELL SCREEN DATA

Top (ft.)	Bottom (ft.)	Description
0	685	Interbedded Limestone and Shale, moderately hard to hard-dry
685	795	White Limestone, hard (Buda)
795	1004	Interbedded Black Shale and Clay with Limestone stringers (Del Rio Clay)
1004	1040	Hard Tan Limestone, hit water @ 1020 (Santa Elena Limestone)

Dia. (in.)	New/Used	Type	Setting From/To (ft.)	
14 New	Steel Cas	sing 0	- 41	
8 5/8 N	ew Steel C	asing	0 - 1015	

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157 Austin, TX 78711 (512) 334-5540

Submitted on: 8/30/2001

Well Report Tracking Number 2114

Page 2 of 2

STATE OF TEXAS WELL REPORT for Tracking #2076 Owner: Owner Well #: WW-2 Lajitas Resort HC 70, Box 400 Address: Grid #: 73-42-9 Terlingua, TX 79852 Latitude: 29° 15' 39" N Well Location: **HWY 170** Lajitas, TX 79852 103° 46' 22" W Longitude: Well County: Brewster Elevation: No Data Type of Work: New Well Proposed Use: Irrigation

Drilling Start Date: 2/26/2001

Drilling End Date: 7/15/2001

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
18	0	41
12	41	985
7.875	985	1040

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

Annular Seal Data:

Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
0	40	10

Seal Method: Gravity

Distance to Property Line (ft.): No Data

Sealed By: Geoprojects

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Slab Installed

Water Level:

165 ft. below land surface on 2001-07-15 Measurement Method: Unknown

Packers:

#1 Spring Steel Basket 975

Type of Pump:

Submersible

Pump Depth (ft.): 400

Well Tests:

Pump

Yield: 450 GPM with 5 ft. drawdown after 36 hours

Page 1 of 2

Water Quality:

Strata Depth (ft.)	Water Type
975	Santa Elena

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?:

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: Geoprojects International, Inc.

8834 Circle Drive Austin, TX 78736

Driller Name:

Benito Hinojosa

License Number: 3127

Comments:

No Data

Lithology: **DESCRIPTION & COLOR OF FORMATION MATERIAL**

Casing: BLANK PIPE & WELL SCREEN DATA

Top (ft.)	Bottom (ft.)	Description
0	655	Dark Shaley Limestone with hard stringers of limestone (Boquillas)
655	773	Hard White Limestone (Buda)
773	975	Black Shaley Limestone with 6"-1 beds of limestone (Del Rio Clay)
975	1040	Tan to White Hard Limestone encounter large volume of water @ 1022. Water temp. = 106 F (Santa Elena Limestone)

Dia. (in.)	New/Used	Type	Setting From/To (ft.)
14" Ne	w Steel Ca	sing 0	- 41
8 5/8 N	ew Steel C	Casing	0 - 985

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157 Austin, TX 78711 (512) 334-5540

STATE OF TEXAS WELL REPORT for Tracking #4099			
Owner:	LAJITAS RESORT	Owner Well #:	PWS-1
Address:	HC 70, BOX 400 TERLINGUA, TX 79852	Grid #:	73-42-9
Well Location:	HIGHWAY 170	Latitude:	29° 15' 37" N
VVCII EGGGIIGITI.	LAJITAS, TX 79852	Longitude:	103° 46' 20" W
Well County:	Brewster	Elevation:	No Data
Type of Work:	New Well	Proposed Use:	Public Supply

Drilling Start Date: 4/4/2001

Drilling End Date: 11/30/2001

Plans Approved by TCEQ - YES

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
18	0	20
12	20	945
7.875	945	1160

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

	TOP Deptit (it.)	6
Annular Seal Data:	0	

Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
0	903	284 Cem/6%Gel

Seal Method: POSITIVE DISPLACEMENT

Distance to Property Line (ft.): No Data

Sealed By: TRIPLE N SERVICES

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Slab Installed

Water Level:

165 ft. below land surface on 2001-09-30 Measurement Method: Unknown

Packers:

NONE

Type of Pump:

Submersible

Pump Depth (ft.): 400

Well Tests:

Pump

Yield: 250 GPM with 10 ft. drawdown after 36 hours

Page 1 of 3

Water Quality:

Strata Depth (ft.)	Water Type	
1050	SANTA ELENA	

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: Unknown

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: GEOPROJECTS INTERNATIONAL

8834 CIRCLE DRIVE **AUSTIN, TX 78736**

Driller Name:

BENNY HINOJOSA

License Number: 3127

Comments:

Lat long entered: 291562 and 1034633

Convert to dddmmss by TWDB TWDB SWN 73-42-905

Lithology: **DESCRIPTION & COLOR OF FORMATION MATERIAL**

Casing: BLANK PIPE & WELL SCREEN DATA

Top (ft.)	Bottom (ft.)	Description
0	620	INTERBEDDED LIMESTONE AND SHALE, MODERATELY HARD (BOQUILLAS)
620	792	MASSIVE HARD WHITE LIMESTONE (BUDA LIMESTONE)
792	927	INTERBEDDED SHALE & CLAY, DARK BROWN TO BLACK, UP TO 1 THICK LIMESTONE STRINGERS (DEL RIO CLAY)
927	1160	FRACTURED, HARD, TAN TO WHITE LIMESTONE, ENCOUNERED WATER @ 1050 (SANTA ELENA LIMESTONE)


Dia. (in.) New/Used	Туре	Setting From/To (ft.)
14 NEW STEEL S	URFA	CE CASING 0 - 20
8 5/8 NEW STEE	L SURF	FACE CASING 0 - 935

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157
Austin, TX 78711
(512) 334-5540



STATE OF TEXAS WELL REPORT for Tracking #4101 Owner: **LAJITAS RESORT** Owner Well #: PWS-2 HC 70, BOX 400 Address: Grid #: 73-42-9 TERLINGUA, TX 79852 Latitude: 29° 15' 36" N Well Location: **HIGHWAY 170** LAJITAS, TX 79852 Longitude: 103° 46' 15" W Well County: **Brewster** Elevation: No Data Type of Work: New Well Proposed Use: **Public Supply**

Drilling Start Date: 4/28/2001

Drilling End Date: 11/30/2001

Plans Approved by TCEQ - YES

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
12.25	0	977
7.875	977	983
	The Admitted Straight	

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

Annular Seal Data:

Top Depth (ft.) Bottom Depth (ft.)		Description (number of sacks & material)
0	977	285 Cem/6% gel
u 1	1	100

Seal Method: POSITIVE DISPLACEMENT

CEMENT

Distance to Property Line (ft.): No Data

Sealed By: TRIPLE N SERVICES

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Slab Installed

Water Level:

165.6 ft. below land surface on 2001-05-

Measurement Method: Unknown

16

Packers:

NONE

Type of Pump:

Submersible

Pump Depth (ft.): 400

Well Tests:

Pump

Yield: 250 GPM with 10 ft. drawdown after 36 hours

Water Quality:

Strata Depth (ft.)	Water Type
980	SANTA ELENA

Chemical Analysis Made: Yes

Did the driller knowingly penetrate any strata which contained injurious constituents?: No

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: GEOPROJECTS INTERNATIONAL

8834 CIRCLE DRIVE **AUSTIN, TX 78736**

Driller Name:

BENITO HINOJOSA

License Number: 3127

Comments:

Lat long entered: 291560 and 1034625

Convert to dddmmss by TWDB TWDB SWN 73-42-906

Lithology: **DESCRIPTION & COLOR OF FORMATION MATERIAL**

Casing: BLANK PIPE & WELL SCREEN DATA

Top (fl.)	Bottom (ft.)	Description
0	645	INTERBEDDED BLACK LIMESTONE AND SHALE. MODERATELY HARD (BOQUILLAS)
645	736	MASSIVE WHITE LIMESTONE, HARD, DRY (BUDA LIMESTONE)
736	967	INTERBEDDED BLACK SHALE AND CLAY, UP TO 1 THICK LIMESTONE STRINGERS (DEL RIO CLAY)
967	983	FRACTURED TAN TO WHITE LIMESTONE (SANTA ELENA LIMESTONEEE)

14 3/4 NEW STEEL CASING 0 - 20
8 5/8 NEW STEEL CASING 0 - 977

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC, CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157
Austin, TX 78711
(512) 334-5540

7/30/2025 9:21:59 AM

Well Report Tracking Number 4101 Submitted on: 1/3/2002 Page 3 of 3

STATE OF TEXAS WELL REPORT for Tracking #2077

Owner:

Lajitas Resort

Owner Well #: WW-1

Address:

HC 70, Box 400

Grid #:

73-42-9

Well Location:

Lajitas Resort

Terlingua, TX 79852

Latitude:

29° 15' 35" N

103° 46' 10" W

Lajitas, TX 79852

Longitude:

Well County: **Brewster**

Elevation:

No Data

Type of Work: New Well

Proposed Use:

Irrigation

Drilling Start Date: 1/30/2001

Drilling End Date: 7/30/2001

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
18	0	10
12	10	960
7.875	960	984

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

Annular Seal Data:

Top Depth (ft.) Bottom Depth (ft.)		Description (number of sacks & material)
0	40	10

Seal Method: Gravity

Distance to Property Line (ft.): No Data

Sealed By: Geoprojects

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Slab Installed

Water Level:

167 ft. below land surface on 2001-07-30

Measurement Method: Unknown

Packers:

#1 Spring Steel Basket 955

Type of Pump:

Submersible

Pump Depth (ft.): 400

Well Tests:

Pump

Yield: 450 GPM with 5 ft. drawdown after 36 hours

Water Quality:

Strata Dopth (ft.)	Water Type
No Data	No Data

Chemical Analysis Made: Unknown

contained injurious constituents?: No

Did the driller knowingly penetrate any strata which

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Geoprojects Internation, Inc.

8834 Circle Drive Austin, TX 78736

Driller Name:

Benito Hinojosa

License Number: 3127

Comments:

TWDB SWN 73-42-907

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Casing:
BLANK PIPE & WELL SCREEN DATA

Top (ft.)	Bottom (ft.)	Description		
0	655	Interbedded Black Limestone and Shaley Limestone (boquillas Flagstone) small quantity of water		
655	755	Hard White massive Limestone (Buda Limestone) no water		
755	955	Moderately hard to soft Shale with 6"-1 thick Limestone stringers (Del Rio Clay)		
955	984	Hard White to Tan Limestone large quantity of water (Santa Elena Limestone)		

New Surface Casing 0 - 10
5/8 New Steel Casing 0 - 960

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157 Austin, TX 78711 (512) 334-5540

Exhibit M Groundwater Technical Report



GROUNDWATER TECHNICAL REPORT

RE:

TLAP PERMIT APPLICATION, EXHIBIT M

BY:

MARK ROETZEL, P.E.

SUBJECT:

SANTA ELENA AQUIFER NEAR LAJITAS. TEXAS

DATE;

7/30/2025 (REV 1)

The private golf resort of Lajitas is located in south central Brewster County on State Hwy 170, about 15 miles west of Stude Butte and bordered by the Rio Grande River to the south. The resort encompasses over 20,000 acres with most of the development near the historic unincorporated town of Lajitas. The Santa Elena aquifer is present in the southern region of Brewster County and is source of Lajitas' Public Water System (PWS) supply and golf course irrigation supply.

Land use in the area is very sparce, with Lajitas Resort including a golf course, hotel and light commercial shops, and single-family residential development. Lajitas currently applies EDR membrane concentrate wastewater from its PWS plant and reclaimed water from its constructed wetland municipal WWTP on the golf course, blended with a much larger volume of raw Santa Elena groundwater. These waters are stored in a clay lined golf course pond certified with the original constructed wetland TPDES permit in about 2000.

The Santa Elena is a Cretaceous Edwards Aquifer associated complex, confined aquifer with a formation top depth of about 1000ft bgl near Lajitas, and a static water level of about 70ft bgl. Ground elevation near the old Town developed area is about 2300-ft msl. Total depth of the aquifer is unknown, with few wells drilled in the area, but generally believed to be about 500 to 800 feet thick. The aquifer is overlaid with about 200 ft of interbedded shale and clays (Del Rio Clay), below about 100 ff of hard limestone (Buda), below about 700 feet of interbedded limestone and shales. Santa Elena groundwater is moderately saline (about 1,4000mg/l near Lajitas) including elevated calcium, sulfate, iron, and low-level NORM radionuclides above the Primary Drinking Water Standard.

Excerpts from the 1990 TWDB Report 323 – Hydrogeology of the Terlingua Area, Teas follow.

There are three wells in the study area completed in the Santa Elena Limestone (73-44-402, 73-44-405, and 73-44-504). All of the wells produce slightly saline (1,130-1,303 mgll dissolved solids) water that has a very distinctive sodium-mixed anion hydrochemical

signature and a basic pH range between 7.8 and 8.3. Concentrations of chloride (341-358 mgll) and fluoride (1.8-3.1) in water from the three wells commonly exceed Texas Department of Health secondary safe drinking standards limits of 300 mg/l chloride and 2.1 mall fluoride. The Santa Elena water is also very hard, with concentrations of calcium carbonate measuring between 341 an 358 mall. Significantly, radioactivity has also been detected in water recovered from the Santa Elena Limestone aguifer at levels higher than is considered safe by the Texas Department of Health for drinking purposes. A preliminary scan of water obtained from well 73-44-402 in July 1988 showed it to have a 21 ± 4 picocuries per liter (pCill) of alpha-particle activity, and 35 ± 5 pCi/l of beta-particle activity. with more detailed analyses revealing 10 ± 1 pCi/1 of radium-226 and 1.3 ± 0.4 pCi/1 of radium-228 in the water. Well 73-44-405 was subsequently sampled for radioactivity in August 1988, with its water proving to have even higher levels of gross radiation, i.e., 56 ± 6 pCi/1 of alpha-particle activity and 70 ± 11 pCi/1 of beta-particle activity. Also, water in well 73-44-504 proved to be radioactive when it was sampled and tested in 1978 (Bob Cook. 1988, personal communication). Radioactive elements in the Santa Elena Limestone aguifer may be related to igneous intrusions in the Terlingua area and concentrated only locally within the regional ground-water system. Radionuclides as trace elements are commonly found in igneous rocks and are formed principally by the radioactive decay of uranium-238 and thorium-232. The most common radionuclides in ground water are radon-222. radium-226. uranium-238, and uranium-234 of the uranium-238 decay series, and radium-228 of the thorium-232 decay series (Zapecza and Szabo, 1986)

Water from wells 73-44-402 and 73-44-405 has also been analyzed to determine heavy metal content. Findings from these analyses indicated that water from both wells was potable with respect to all metals tested at the Texas Department of Health labs, including mercury which has been produced at nearby mines in Terlingua and Study Butte (Table 4). However, the Mel LaVergne well was also tested in 1972, with the results showing it to have 0.0024 mgll mercury, an amount slightly above the maximum contaminant level (0.002 mgll) recommended to be safe for drinking.

Although no wells in the study area penetrate Cretaceous formations below the Santa Elena Limestone, there is still reason to believe that aquifers exist. Outcrop exposures of the Del Carmen Limestone and the Glen Rose Limestone along the Terlingua fault escarpment immediately southwest of the study area indicate that the formations have sufficient fracture porosity to contain relatively large volumes of ground water, with the Del Carmen Limestone possibly even having well developed solution cavities in rudistid-bearing facies and along larger fracture systems on the south flank ofthe Terlingua uplift.

Geology near Lajitas is highly irregular, with volcanic intrusions penetrating to the surface. The Santa Elena is a high production aquifer in the Lajitas area, with several resort irrigation and potable supply wells located at the resort.

The quality of water in the Del Carmen Limestone and the Glen Rose Limestone is probably equal to or poorer than the quality of water in the Santa Elena Limestone, especially if A minor low production, shallow brackish aquifer (Boquillas, about 6,500mg/l) is present in the area, being perched groundwater in the surficial shale and limestone. This aquifer has no know uses or outfalls, balanced amounts of sodium and chloride in Santa Elena water indicate either dilution of original formation water (manne saltwater) or dissolution of natural salt precipitated from sea water. More specifically, if the Santa Elena Limestone has not

.

been flushed completely with fresh meteoric water since it was deposited in marine seas, then it is unlikely that formations below it have been flushed either, leaving only saline water to fill the deeper aquifers. Exceptions may occur, however, on the Terlingua uplift where fresh meteoric recharge has infiltrated into deeper Cretaceous aquifers

Three irrigation wells and two PWS supply wells were developed in the Santa Elena Aquifer in Lajitas about 2001, providing better definition of the local hydrogeology. All five wells are within ½-mile of the proposed irrigation disposal site, and the Driller's Logs for these wells are included with Exhibit L – Well and Map Information.

A 2003 TWDB analysis report from one of the Lajitas Irrigation Supply well follows, more completely defining basic water quality (not including NORM radionuclides).

Texas Water Development Board

Wordnesday, March 15, 2023

Texas Water Development Board (TWDB)
Groundwater Database (GWDB)
Well Information Report for State Well Number

groundwater

Page 3 of 5

	Water Quality Ana	lysis		
Sample Date:	5/21/2003 Sample Time: 1433 Sample Number: 1	Collection Entit	A: Lexus Motor	Development Board
iupA beigmai	ler: Same Elena Umesterie			
Inslyzed Lab:	LCRA - Lower Colorado River Authority Reliab	Ility: Sampled using	TWDB protocols)
alleation Ren		• •		
Paremeter Code	Parameter Description	Flag	Velue*	Units Plus/Minu
39086	ALKALINITY FIELD DISSOLVED AS CAGOS		204	mg/L
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		o	mg/L
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		201	mg/L
01106	ALUMINUM, DISSOLVED (UG)L AS AL)		٠ 4	ug/L
01025	ANTIMONY, DISSOLVED (UG/L AS SB)			ug/L
01000	AMSENIC, DISSOLVED (UG/L AS AS)			ug/L
01005	BARIUM, DISSOLVED (UQ/L AS BA)			ug/L
01010	BERYLLIUM, DISSOLVED (UCUL AS BE)			ug/L
00440	BICARBONATE ION. CALCULATED IMG/L AS HC@3)		245.29	•
01020	BORON, DISSOLVED (UG.), AS B)			uo/L
71870	BROMIDE, DISSOLVED, (MG/L AS BA)		0.32	mg/L
01025	GADMIUM, DISSOLVED (USA: AS CD)			ար/ե
M915	CALCIUM, DISSOLVED (MG/L AS CA)			mg/l,
20148	CARBONATE ION, CALCULATED IMEA, AS COST			mp/L
50941	CHLORIDE, DISSOLVED (MGALAS CI.)			mg/l
01030	CHROMIUM, DISSOLVED (UGAL AS CR)			ug/L
32015	COBALT, DISSOLVED (UG/L AS CO)			ug/L
31040	COPPER, DISSOLVED (UGA, AS CU)			Mary
10950	FLUORIDE, DISSOLVED (MG/L AS F)			mgsl.
ON O NO	HANDNESS, TOTAL, CALCULATED (MCM. AS CACOS)			mg/t.
11040	IRON, DISSOLVED (UGAL AS FE)			ug.t.
01049	LEAD, DISSOLVED (UG/L AS PB)			ng.t.
01130	LITHIUM, DISSOLVED (LIGAL AS LI)			ug/L
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)			Mo/F
)1056	MANGANESE, DISSOLVED (UGIL AS MN)			work
31060 31050				-
1065	MOLYBDÉNIM, DISSOLVED (LIGIL AS MO)		4.85 1.69	_
71851	NICKEL DISSOLVED (UG/LAS NI)	25		mo/L
7141≏17 NOG311	NITRATE NITROGEN, DISSOLVED, GALCULATED (MG/L AS NO.	2)		. •
	NITRITE PLUS NITRATE, DISSOLVED (MG/L AS N)		0.112	•
10400	PH (STANDARD UNITS), FIELD		7.01	
00935	POTASSIUM, DISSOLVED (MG/L AS K)			mp/L
1860	RESIDUAL SODIUM CARBONATE, CALCULATED		C .	
1145	SELENIUM, DISSOLVED (UG/L AS SE) SILICA, DISSOLVED (MG/L AS SIO?)		% 4 32,7	up/L
00968				

State Well Number 73-43-401

3

Texas Water
Development Board

Texas Water Development Board (TWDB) Groundwater Database (GWDB) Well Information Report for State Well Number 73-43-401



Parameter Code	Parameter Description	Fleg	Yalue*		Unita	Plus/Minus
00932	SODIUM, GALCULATED, PERCENT			6 6	PCT	
00930	SODIUM, DISSOLVED (ME/L AS NA)			223	mg∕L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/GM AT 25C)			1667	МІСЫ	
01680	STRONTIUM, DISSOLVED (UG/L AS SA)			2950	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)			157	mg∕L	
D0010	TEMPERATURE, WATER (CELSIUS)			41.7	C	
01057	THALLIUM, DISSOLVED (UG/L AS TL)		<	1	ug/L	
703D1	TOTAL DISSOLVED SOLIDS, SLIM OF CONSTITUENTS (MG/L)			949	mg/L	
07012	TRITIUM IN WATER (TRITIUM UNITS)			0.01	TU	0.09
01085	VANADIUM, DISSOLVED (UG/L AS V)			1.7	uņ.'L	
01090	ZINC. DISSOLVED (UGAL AS ZN)			9,81	ugs	

While there are no known wells developed in the shallow Boquillas perched aquifer above the Santa Elena, reported water quality is brackish (about 7,000mg/l TDS) with no reported uses.

The closest known other user of the Santa Elena Aquifer in the region is the town of Terlingua about 14 miles east of Lajitas. Both Lajitas and Terlingua membrane treat this supply for potable use. Lajitas also uses raw groundwater for golf course irrigation.

Reported basic water quality of the Santa Elena at Lajitas has not changed over the past 25 years, remaining at about 1,400mg/l TDS. This is as expected, being a large volume limestone aquifer with very limited withdrawal. The raw groundwater is suitable for irrigation, with the golf course using salt-tolerant Bermuda grass blends and practicing annual soils conditioning. Combined Nitrite/Nitrate source water levels are quite low as shown on the preceding TWDB report.



Exhibit N Soil Map and Soil Information

1039 46' 48" W



Soil Map—Big Bend National Park, Texas, and Brewster County, Texas (Main Part)

03° 45' 54"

£ 51 46

MAP LEGEND

Spoil Area

Stony Spot

Wet Spot

Other

Very Stony Spot

Special Line Features

Streams and Canals

Interstate Highways

US Routes

Major Roads

Local Roads

Aerial Photography

è

(2)

19

۵

Water Features

Transportation

Background

Area of Interest (AQI)

Area of Interest (AOI)

Soils

Ш

Soil Map Unit Polygons



Seil Map Unit Points

Special Point Features

Bloward (1) \boxtimes

Borrow Pit

Clay Spot ×

Closed Depression \Diamond

Gravel Pit ፠

Gravely Spot 4

Landfill ₩

Lava Flow À

Marsh or swamp 业 Mine or Quarry

究 Miscellaneous Water

0 Perennial Water 0

Rock Outcrop 5.0

Saline Spot

Sandy Spot Severely Eroded Spot

Sinkhole Ġ

₽

Saide or Saip ž

Sodic Spot

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at scales ranging from 1:24,000 to 1:31,700.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Big Bend National Park, Texas Survey Area Data: Version 29, Aug 30, 2024

Soil Survey Area: Brewster County, Texas (Main Part) Survey Area Date: Version 33, Sep 10, 2024

Your area of interest (AOI) includes more than one soil survey area. These survey areas may have been mapped at different scales, with a different land use in mind, at different times, or at different levels of detail. This may result in map unit symbols, soil properties, and interpretations that do not completely agree across soil survey area boundaries.

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Mar 5, 2021—Mar 18, 2021



Web Soil Survey National Cooperative Soil Survey

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
TOA	Tornillo loam, 0 to 2 percent slopes, occasionally flooded	21.9	13.6%
Subtotals for Soil Survey Area		21.9	13.6%
Totals for Area of Interest		161,8	100.0%

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
COC	Corazones very gravelly sandy loam, 1 to 8 percent slopes	0.7	0.4%
MDE	Mariscal-Rock outcrop complex, 10 to 30 percent slopes	20.6	12.7%
NOA	Ninepoint silty clay loam, 0 to 2 percent slopes, frequently flooded	75.2	46.5%
VCA	Vicente, Lomapelona, and Castolon soils, 0 to 1 percent slopes, occasionally flooded	43.3	26.8%
Subtotals for Soll Survey A	rea	139.8	86.4%
Totals for Area of Interest		161.8	100.0%



Brewster County, Texas (Main Part)

NOA-Ninepoint silty clay loam, 0 to 2 percent slopes, frequently flooded

Map Unit Setting

National map unit symbol: 223sn Elevation: 1,800 to 4,000 feet

Mean annual precipitation: 10 to 13 inches Mean annual air temperature: 68 to 72 degrees F

Frost-free period: 240 to 280 days

Farmland classification: Not prime farmland

Map Unit Composition

Ninepoint, frequently flooded, and similar soils: 75 percent

Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of

the mapunit.

Description of Ninepoint, Frequently Flooded

Setting

Landform: Alluvial flats Down-slope shape: Linear Across-slope shape: Linear

Parent material: Holocene-age fine-silty alluvium derived from

limestone and shale

Typical profile

A - 0 to 4 inches: silty clay loam Bw - 4 to 80 inches: silty clay

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.57 in/hr)

Depth to water table. More than 80 inches

Frequency of flooding: Frequent

Frequency of ponding: None

Calcium carbonate, maximum content: 35 percent

Gypsum, maximum content: 2 percent

Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0

mmhos/cm)

Sodium adsorption ratio, maximum: 5.0

Available water supply, 0 to 60 inches: High (about 11.3 inches)

Interpretive groups

Land capability classification (irrigated): 3e Land capability classification (nonirrigated): 7c



Hydrologic Soil Group: C

Ecological site: R042AB738TX - Loamy, Hot Desert Shrub

Hydric soil rating: No

Minor Components

Riverwash

Percent of map unit: 9 percent Hydric soil rating: No

Tornillo

Percent of map unit: 9 percent

Ecological site: R042AB738TX - Loamy, Hot Desert Shrub

Hydric soil rating: No

Unnamed

Percent of map unit: 7 percent Hydric soil rating: No

Data Source Information

Soil Survey Area: Big Bend National Park, Texas Survey Area Data: Version 29, Aug 30, 2024

Soil Survey Area: Brewster County, Texas (Main Part)

Survey Area Data: Version 33, Sep 10, 2024

- a. Provide analyses of the soil in the land application area for the following constituents:
 - pH [2:1 (volume/volume) water/soil mixture];
 - electrical conductivity [2:1 (volume/volume) water/soil mixture];
 - sodium adsorption ratio (SAR-not to exceed 10) from a water saturated paste and its constituent parameters (water-soluble Na, Ca and Mg reported in mg/L);
 - total Kjeldahl nitrogen (TKN);
 - total nitrogen (organic-nitrogen + nitrate-nitrogen + ammonium-nitrogen);
 - nitrate-nitrogen (from a 1 N KCl soil extract);
 - potassium;
 - phosphorus;
 - calcium;
 - magnesium;
 - sulfur; and
 - sodium.

Analyze the nutrient parameters on a plant-available basis. Analyze phosphorus according to the Mehlich III procedure with inductively coupled plasma; potassium, calcium, magnesium, sodium, and sulfur may also be analyzed in the Mehlich III soil extract. Report plant-available phosphorus, potassium, calcium, magnesium, sodium, and sulfur on a dryweight basis in mg/kg. Report electrical conductivity in mmho/cm [same as deciSiemens/meter (dS/m)]. Report pH in standard units. When reporting the results, include all information concerning fertilizer recommendations. Provide a copy of this plan to the analytical laberatory prior to sample analysis.

NOTE: Composite or benchmark sampling techniques should be used when sampling the soils of the wastewater application area. Individual soil types, as defined by the USDA NRCS Soil Survey, should be sampled individually at zones 0-6, 6-18, and 18-30 inches. Each composite sample shall represent no more than 80 acres, with no less than 15 subsamples representing each composite sample. Each benchmark sample shall represent no more than 80 acres with at least 7 subsamples for each benchmark composite sample. Subsamples shall be composited by individual site, zone, and soil type for analysis and reporting.

NOTE; The Soil Analysis is pending. For the 53.6-Ac irrigated area this will be a composite soil sample for 0-6", a second composite soil sample for 6-18", and a third composite sample for 18-30". The subsample locations used to create the composite will be shown on a markup of the irrigated area. The TLAP Permit Application is submitted to begin the Administrative Review since the past TLAP Permit has now expired.

Exhibit O Water Balance

550

Month	{1} Evaporation Inches (2)	{2} Worst 25Yr Rainfall - Inches (3)	{3} Net Hydrologic Balance -In [{1} - {2}]	{4} Process Wastewater Input - Inches (4)	{5} Net Stored Water Balance - In [{4}-{3}]	(6) Net Stored Water Balance (Gal) (5)		{8} Net Storage Difference (Gal) [{6}-{7}]	{9} Required MakeUp Irrigation Groundwater
Jan	2.76	0.98	1.78	29.9	28.12	1453804	3,940,000	-2486196	2486196
Feb	4.54	1.12	3.42	29.9	26.48	1369016	3,940,000	- <mark>257098</mark> 4	2570984
Mar	8.27	0.95	7.32	29.9	22.58	1167386	3,940,000	-2772614	2772614
Apr	10.53	0.96	9.57	29.9	20.33	1051061	3,940,000	-2888939	2888939
May	12.61	1.66	10.95	29.9	18.95	979715	6,560,000	-5580285	5580285
Jun	12.7	1.48	11.22	29.9	18.68	965756	6,560,000	-5594244	5594244
Jul	11.25	1.58	9.67	29.9	20.23	1045891	6,560,000	-5514109	5514109
Aug	10.99	1.53	9.46	29.9	20.44	1056748	6,560,000	-5 503252	5503252
Sep	8.4	2.02	6.38	29.9	23.52	1215984	6,560,000	-5344016	5,344,016
Oct	4.97	1.45	3.52	29.9	26.38	1363846	6,560,000	-5196154	5,196,154
Nov	4.01	1.14	2.87	29.9	27.03	1397451	3,940,000	-254 254 9	2542549
Dec	2.85	0.9	1.95	29.9	27.95	1445015	3,940,000	-2494985	2494985
Total:	93.88	15.77	78.1 1	358.8	280.69	14511673	63,000,000	-48488327	48488327

Notes:

- (1) The 2.4-acre pond holds 3.1MG (9.5ac-ft) of water, far in excess of the process wastewater input. An average additional groundwater flow of 110,000gpd is added to the pond for the 53.6-acre irrigated golf course watering needs.
- (2) TWDB Climatologic Data Pan Evaporation Rate, Presideo, TX (1961 Lowest Year)
- (3) TWDB Climate of Texas, Chapter 5, Presideo, TX
- (4) 65,000gpd x 30days/month stored in 2.4 acre pond convertted to inches per month
- (5) {5}/12x[(2.4).(43,560).(7.48)]
- (6) Monthly total irrigation water applied to 56.3-acre golf course area, averaging 175,000gpd (0.8in/week). Includes 65,000gpd of WTP process wastewatgyer blended with groundwater

Lajitas Municipal Services Company LLC 14241 Dallas Parkway, Ste 800 Dallas, Texas 75254

Water Treatment Plant
TLAP Permit Application
July, 2025



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION CHECKLIST

Complete and submit this checklist with the industrial wastewater permit application.

APPLICANT NAME: Lajitas Municipal Services Company LLC

PERMIT NUMBER (If new, leave blank): WQ00 Click to enter text.

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0	\boxtimes		Worksheet 8.0		\boxtimes
Administrative Report 1.1	\boxtimes		Worksheet 9.0		\boxtimes
SPIF		\boxtimes	Worksheet 10.0		\boxtimes
Core Data Form	\boxtimes		Worksheet 11.0		\boxtimes
Summary of Application (PLS)	\boxtimes		Worksheet 11.1		\boxtimes
Public Involvement Plan Form	\boxtimes		Worksheet 11.2		\boxtimes
Technical Report 1.0	\boxtimes		Worksheet 11.3		
Worksheet 1.0		\boxtimes	Original USGS Map	\boxtimes	
Worksheet 2.0		\boxtimes	Affected Landowners Map	\boxtimes	
Worksheet 3.0	\boxtimes		Landowner Disk or Labels		
Worksheet 3.1	\boxtimes		Flow Diagram	\boxtimes	
Worksheet 3.2		\boxtimes	Site Drawing	\boxtimes	
Worksheet 3.3		\boxtimes	Original Photographs	\boxtimes	
Worksheet 4.0		\boxtimes	Design Calculations		\boxtimes
Worksheet 4.1		\boxtimes	Solids Management Plan		\boxtimes
Worksheet 5.0		\boxtimes	Water Balance	\boxtimes	
Worksheet 6.0		\boxtimes			
Worksheet 7.0		\boxtimes			

For TCEQ Use Only		
Segment Number	County	
Expiration Date	Region	

Noncode commission in the Commission of Comm		
Permit Number	 	



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

This report is required for all applications for TPDES permits and TLAPs, except applications for oil and gas extraction operations subject to 40 CFR Part 435. Contact the Applications Review and Processing Team at 512-239-4671 with any questions about completing this report.

Applications for oil and gas extraction operations subject to 40 CFR Part 435 must use Oil and Gas Exploration and Production Administrative Report (TCEO Form-20893 and 20893-inst).

It	em 1. Application Information and Fees (Instructions, Page 26)
a.	
	Applicant Name: Lajitas Municipal Services Company LLC
	Permit No.: WQ000Click to enter text.
	EPA ID No.: TX0Click to enter text.
	Expiration Date: Click to enter text.
b.	Check the box next to the appropriate authorization type.
	☑ Industrial Wastewater (wastewater and stormwater)
	□ Industrial Stormwater (stormwater only)
	☐ Reverse Osmosis Water Treatment (reverse osmosis water treatment wastewaters only)
c.	Check the box next to the appropriate facility status.
	☑ Active ☐ Inactive
d.	Check the box next to the appropriate permit type.
	☐ TPDES Permit ☐ TLAP ☐ TPDES with TLAP component
e.	Check the box next to the appropriate application type.
	⊠ New
	☐ Renewal with changes ☐ Renewal without changes
	☐ Major amendment with renewal ☐ Major amendment without renewal
	☐ Minor amendment without renewal
	☐ Minor modification without renewal
ř.	If applying for an amendment or modification, describe the request: Click to enter text.
	TCEQ Use Only
xp	ment NumberCounty piration DateRegion mit Number

¹ https://www.tceq.texas.gov/publications/search_forms.html TCEQ-10411 (09/13/2024) Industrial Wastewater Application Administrative Report

g. Application Fee

EPA Classification	New	Major Amend. (with or without renewal)	Renewal (with or without changes)	Minor Amend. / Minor Mod. (without renewal)
Minor facility not subject to EPA categorical effluent guidelines (40 CFR Parts 400-471)	⊠ \$350	□ \$350	□ \$315	□ \$150
Minor facility subject to EPA categorical effluent guidelines (40 CFR Parts 400-471)	□ \$1,250	□ \$1,250	□ \$1,215	□ \$150
Major facility	N/A ²	□ \$2,050	□ \$2,015	□ \$450

h. Payment Information

Mailed

Check or money order No.: <u>4544</u> Check or money order amt.: 350

Named printed on check or money order: Lajitas Capital Partners

Epay

Voucher number: Click to enter text.

Copy of voucher attachment: Click to enter text.

Item 2. Applicant Information (Instructions, Pages 26)

a. Customer Number, if applicant is an existing customer: <u>CN603406604</u>
 Note: Locate the customer number using the <u>TCEO's Central Registry Customer Search</u>³.

b. Legal name of the entity (applicant) applying for this permit: <u>Lajitas Municipal Services</u> <u>Company LLC</u>

Note: The owner of the facility must apply for the permit. The legal name must be spelled exactly as filed with the TX SOS, Texas Comptroller of Public Accounts, County, or in the legal documents forming the entity.

c. Name and title of the person signing the application. (Note: The person must be an executive official that meets signatory requirements in 30 TAC § 305.44.)

Prefix: Click to enter text.	Full Name (Last/First Name): Aube, Sonia
Title: Authorized Representat	ive Credential: Click to enter text

d. Will the applicant have overall financial responsibility for the facility?

\boxtimes	Yes		No
-------------	-----	--	----

² All facilities are designated as minors until formally classified as a major by EPA.

³ https://www15.tceq.texas.gov/crpub/index.cfm?fuseaction=cust.CustSearch

Note: The entity with overall financial responsibility for the facility must apply as a coapplicant, if not the facility owner.

Item 3. Co-applicant Information (Instructions, Page 27)

☑ Check this box if there is no co-applicant.; otherwise, complete the below questions.

a. Legal name of the entity (co-applicant) applying for this permit: Click to enter text.

Note: The legal name must be spelled exactly as filed with the TX SOS, Texas Comptroller of Public Accounts, County, or in the legal documents forming the entity.

b. Customer Number (if applicant is an existing customer): <u>CNClick to enter text.</u>

Note: Locate the customer number using the TCEQ's Central Registry Customer Search.

c. Name and title of the person signing the application. (Note: The person must be an executive official that meets signatory requirements in 30 TAC § 305.44.)

Prefix: Click to enter text.

Full Name (Last/First Name): Click to enter text.

Title: Click to enter text.

Credential: Click to enter text.

d. Will the co-applicant have overall financial responsibility for the facility?

☐ Yes ☐ No

Note: The entity with overall financial responsibility for the facility must apply as a coapplicant, if not the facility owner.

Item 4. Core Data Form (Instructions, Pages 27)

a. Complete and attach one Core Data Form (TCEQ Form 10400) for each customer (applicant and co-applicant(s)). If the customer type selected on the Core Data Form is Individual, complete Attachment 1 of the Administrative Report. Attachment: A

Item 5. Application Contact Information (Instructions, Page 27)

Provide names of two individuals who can be contacted about this application. Indicate if the individual can be contacted about administrative or technical information, or both.

a. 🛛 Administrative Contact

.

Technical Contact

Prefix: Click to enter text.

Full Name (Last/First Name): Holmes, Ron

Title: Counsel

Credential: Click to enter text.

Organization Name: Holmes Firm PC

Mailing Address: 14241 Dallas Parkway, Ste 800

City/State/Zip: Dallas, TX 75254

Phone No: 469-317-3470 Email: ron@theholmesfirm.com

b. □ Administrative Contact

□ Technical Contact

Prefix: Click to enter text.

Full Name (Last/First Name): Roetzel, Mark

Title: Project Engineer

Credential: P.E.

Organization Name: CDS Muery

Mailing Address: 100 NE Loop 410, Ste 300

City/State/Zip: San Antonio, TX 78216

Phone No: 210-581-1111 Email: mark.roetzel@cdsmuery.com

Attachment: Click to enter text.

Item 6. Permit Contact Information (Instructions, Page 28)

Provide two names of individuals that can be contacted throughout the permit term.

a. Prefix: Click to enter text. Full Name (Last/First Name): Beasley, Scott

Title: President Credential: Click to enter text.

Organization Name: WSB Resorts and Clubs, Inc.

Mailing Address: 8111 Westchester Dr. Ste 600 City/State/Zip: Dallas, TX 75225

Phone No: <u>214-534-6565</u> Email: <u>wsbeasley@wsbresortsandclubs.com</u>

b. Prefix: Click to enter text. Full Name (Last/First Name): Perry, Scott

Title: <u>Plant Manager</u> Credential: <u>Click to enter text.</u>
Organization Name: <u>Lajitas Municipal Services Company LLC</u>

Mailing Address: HC 70 Box 400 City/State/Zip: Lajitas, TX 79219

Phone No: 432-424-5132 Email: Sperry@lajitasgolfresorts.com

Attachment: Click to enter text.

Item 7. Billing Contact Information (Instructions, Page 28)

The permittee is responsible for paying the annual fee. The annual fee will be assessed for permits in effect on September 1 of each year. The TCEQ will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (form TCEQ-20029).

Provide the complete mailing address where the annual fee invoice should be mailed and the name and phone number of the permittee's representative responsible for payment of the invoice.

Prefix: Click to enter text. Full Name (Last/First Name): Beasley, Scott

Title: <u>President</u> Credential: <u>Click to enter text.</u>

Organization Name: WSB Resorts and Clubs, Inc.

Mailing Address: 8111 Westchester Dr., Ste 600 City/State/Zip: Dallas, TX 75225

Phone No: 214-534-6565 Email: wsbeasley@wsbresoprtsandclubs.com

Item 8. DMR/MER Contact Information (Instructions, Page 28)

Provide the name and mailing address of the person delegated to receive and submit DMRs or MERs. Note: DMR data must be submitted through the NetDMR system. An electronic reporting account can be established once the facility has obtained the permit number.

Prefix: Click to enter text. Full Name (Last/First Name): Perry, Scott

Title: <u>Plant Manager</u> Credential: <u>Click to enter text.</u>
Organization Name: <u>Lajitas Municipal Services Company LLC</u>

Mailing Address: HC 70, Box 400 City/State/Zip: Lajitas, TX 79852

Phone No: Click to enter text. Email: Click to enter text.

Item 9. Notice Information (Instructions, Pages 28)

a. Individual Publishing the Notices

Prefix: Click to enter text.

Full Name (Last/First Name): Vetter, Scott

Title: Facilities Manager

Credential: Click to enter text.

Organization Name: Lajitas Golf Resort

Mailing Address: HC 70, Box 400

City/State/Zip: Lajitas, TX 79852

Phone No: 281-467-3467

Email: SVetter@lajitasgolfresort.com

b. Method for Receiving Notice of Receipt and Intent to Obtain a Water Quality Permit Package (only for NORI, NAPD will be sent via regular mail)

☑ E-mail: SVetter@lajitasgolfresort.com

☐ Fax: Click to enter text.

☐ Regular Mail (USPS)

Mailing Address: Click to enter text.

City/State/Zip Code: Click to enter text.

c. Contact in the Notice

Prefix: Click to enter text.

Full Name (Last/First Name): Vetter, Scott

Title: Facilities Manager

Credential: Click to enter text.

Organization Name: Lajitas Golf Resort

Phone No: 281-467-3467

Email: SVetter@laiitasgolfresort.com

d. Public Viewing Location Information

Note: If the facility or outfall is located in more than one county, provide a public viewing place for each county.

Public building name: Terlingua Fire & EMS Location within the building: Lobby

Physical Address of Building: 23250 FM-170

City: Terlingua County: Brewster

e. Bilingual Notice Requirements

This information is required for new, major amendment, minor amendment or minor modification, and renewal applications.

This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.

Call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine if an alternative language notice(s) is required.

1. Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?

		□ Yes ⋈ No		
		If no, publication of an alternative language notice is not required; skip to Item 8 (Regulated Entity and Permitted Site Information.)		
	2.	Are the students who attend either the elementary school or the middle school enrolled in a bilingual education program at that school?		
		□ Yes □ No		
	3.	Do the students at these schools attend a bilingual education program at another location?		
		□ Yes □ No		
	4.	Would the school be required to provide a bilingual education program, but the school has waived out of this requirement under 19 TAC §89.1205(g)?		
		□ Yes □ No □ N/A		
	5.	If the answer is yes to question 1, 2, 3, or 4, public notices in an alternative language are required. Which language is required by the bilingual program? <u>Click to enter text.</u>		
f.	Summary of Application in Plain Language Template – Complete and attach the Summary of Application in Plain Language Template (TCEQ Form 20972), also known as the plain language summary or PLS. Attachment: <u>B</u>			
g.		mplete and attach one Public Involvement Plan (PIP) Form (TCEQ Form 20960) for each plication for a new permit or major amendment. Attachment: \underline{C}		
It	em	10. Regulated Entity and Permitted Site Information (Instructions Page 29)		
a.	TC	EQ issued Regulated Entity Number (RN), if available: RN102079365		
	No ma the	te: If your business site is part of a larger business site, a Regulated Entity Number (RN) by already be assigned for the larger site. Use the RN assigned for the larger site. Search e TCEQ's Central Registry to determine the RN or to see if the larger site may already be distered as a Regulated Entity. If the site is found, provide the assigned RN.		
b.		me of project or site (name known by the community where located): <u>Lajitas Water</u> eatment Plant		
c.	Is t	the location address of the facility in the existing permit the same?		
		Yes □ No ☒ N/A (new permit)		
	Wil	te: If the facility is located in Bexar, Comal, Hays, Kinney, Medina, Travis, Uvalde, or liamson County, additional information concerning protection of the Edwards Aquifer y be required.		
d.	Ow	mer of treatment facility:		
	Pre	fix: Click to enter text. Full Name (Last/First Name): Click to enter text.		
	or	Organization Name: Lajitas Municipal Services Company LLC		
	Ma	iling Address: 8111 Westchester Dr. Ste 500 City/State/Zip: Dallas, TX 75225		
		one No: 214-981-0722 Fmail: sonia aube@energytransfer.com		

e.	Ownership of facility: Pul	olic 🗵 Priv	ate 🗆 Both	ı 🗆 Federal
f.	Owner of land where treatme	nt facility is or wi	l be <u>: Lajitas Mun</u>	icipal Services Company
	Prefix: Click to enter text.	Full Name (Last/	First Name): <u>Click</u>	to enter text.
	or Organization Name: <u>Lajita</u>	Municipal Servic	es Company LLC	
	Mailing Address: 8111 Westel	nester Dr. Ste 600	City/State/Zip	o: <u>Dallas, TX 752525</u>
	Phone No: <u>214-981-0722</u>	Email: <u>sonia.aub</u>	@energytransfer	.com
	Note: If not the same as the fat least six years (In some cas Click to enter text.	acility owner, atta es, a lease may no	ch a long-term lea t suffice - see ins	ase agreement in effect for structions). Attachment:
g.	Owner of effluent TLAP dispo	sal site (if applica	ble): <u>Lajitas Muni</u>	cipal Services Company LLC
	Prefix: Click to enter text.	Full Name (Last/	irst Name): <u>Click</u>	to enter text.
	or Organization Name: <u>Lajitas</u>	Municipal Service	es Company LLC	
	Mailing Address: 8111 Westch	nester Dr. Ste 600	City/State/Zip	o: <u>Dallas, TX 75225</u>
	Phone No: <u>214-981-0722</u>	Email: sonia.aube	@energytransfer	.com
	Note: If not the same as the fa at least six years. Attachment		ch a long-term lea	ase agreement in effect for
h.	Owner of sewage sludge disp	osal site (if applica	able):	
	Prefix: N/A Full Name	e (Last/First Name): Click to enter t	ext.
	or Organization Name: Click t	o enter text.		
	Mailing Address: Click to ente	er text.	City/State/Zip	click to enter text.
	Phone No: Click to enter text.	Email: Click to ent	er text.	
	Note: If not the same as the fa at least six years. Attachment			ase agreement in effect for
Ite	em 11. TDPES Discharg 31)	e/TLAP Dispo	sal Informatio	on (Instructions, Page
a.	Is the facility located on or do ☐ Yes ☒ No	es the treated eff	uent cross Nativo	e American Land?
b. Attach an original full size USGS Topographic Map (or an 8.5"×11" reproduced renewal or amendment applications) with all required information. Check the leach item below to confirm it has been included on the map.				
	☑ One-mile radius	П	hree-miles down	stream information
	☑ Applicant's property bound	laries 🗵 T	reatment facility	boundaries
	☐ Labeled point(s) of discharg	ge 🗆 F	ighlighted disch	arge route(s)
	⊠ Effluent disposal site boun	daries 🗵 🖊	ll wastewater po	nds
	☐ Sewage sludge disposal site		ew and future co	nstruction

	Attachment: <u>E</u>
c.	Is the location of the sewage sludge disposal site in the existing permit accurate?
	☐ Yes ☒ No or New Permit
	If no, or a new application, provide an accurate location description: <u>Lajitas Golf Course</u> – <u>Attachment</u>
d.	Are the point(s) of discharge in the existing permit correct?
	☐ Yes \boxtimes No or New Permit If no, or a new application, provide an accurate location description: $\underline{N/A}$ - \underline{TLAP}
e.	Are the discharge route(s) in the existing permit correct?
	☐ Yes ☒ No or New Permit
	If no, or a new permit, provide an accurate description of the discharge route: $N/A - TIAP$
f.	City nearest the outfall(s): N/A
g.	County in which the outfalls(s) is/are located: N/A
h.	Is or will the treated wastewater discharge to a city, county, or state highway right-of-way or a flood control district drainage ditch?
	□ Yes ⊠ No
	If yes, indicate by a check mark if: \square Authorization granted \square Authorization pending
	For new and amendment applications, attach copies of letters that show proof of contact and provide the approval letter upon receipt. Attachment: Click to enter text.
	For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge: <u>Click to enter text.</u>
i.	For TLAPs, is the location of the effluent disposal site in the existing permit accurate?
	☐ Yes No or New Permit ☒ New TLAP Permit
	If no, or a new application, provide an accurate location description: Lajítas Golf Course = Exhibit F
j.	City nearest the disposal site: <u>Terlingua</u>
k.	County in which the disposal site is located: <u>Brewster</u>
l.	For TLAPs, describe how effluent is/will be routed from the treatment facility to the disposal site: Routed by closed pipe to bentonite clay lined golf course lake (liner previously certified under expired TLAP permit), then blended with groundwater for irrigation
m.	For TLAPs, identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained: <u>Rio Grande River</u>

Item 12. Miscellaneous Information (Instructions, Page 33)

a.	Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?
	□ Yes ⋈ No
	If yes, list each person: Click to enter text.
b.	Do you owe any fees to the TCEQ?
	□ Yes ⋈ No
	If yes, provide the following information:
	Account no.: Click to enter text.
	Total amount due: Click to enter text.
c.	Do you owe any penalties to the TCEQ?
	□ Yes ⋈ No
	If yes, provide the following information:
	Enforcement order no.: Click to enter text.
	Amount due: Click to enter text.

Item 13. Signature Page (Instructions, Page 33)

Permit No: WO000Click to enter text.

County, Texas

Applicant Name: Lajitas Municipal Services Company LLC

Certification: I, <u>Sonia Aube</u>, certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

I further certify that I am authorized under 30 Texas Administrative Code §305.44 to sign and submit this document and can provide documentation in proof of such authorization upon request.

=				
Signatory name (typed or p	rinted): <u>Sonia Aube</u>			
Signatory title: <u>Authorized</u>	Representative	/		
Signature: (Use	blue ink)		Date: <u><i>Lef 1</i></u>	7/2025
Subscribed and Sworn to be	fore me by the said	Somia	ANDe	
on this	17th	day of	Inne	, 20 <u>29</u> .
My commission expires on	the7+W_	day of	TANNAN	
Notary Public 12/1/45	KATHERINE MORGAN Votery Public, State of Texas Motery ID 132303899		[SEAL]	

Note: If co-applicants are necessary, each entity must submit an original, separate signature page.

INDUSTRIAL WASTEWATER PERMIT APPLICATION **ADMINISTRATIVE REPORT 1.1**

The following information is required for new and amendment applications.

b.

<u>Property</u> Records

Affected Landowner Information (Instructions, Page 35) Item 1.

a.	Attach a landowner map or drawing, with scale, as applicable. Check the box next to each item to confirm it has been provided.
	☐ The applicant's property boundaries.
	oxtimes The facility site boundaries within the applicant's property boundaries.
	riangle The distance the buffer zone falls into adjacent properties and the property boundaries of the landowners located within the buffer zone.
	☑ The property boundaries of all landowners surrounding the applicant's property. (Note: if the application is a major amendment for a lignite mine, the map must include the property boundaries of all landowners adjacent to the new facility (ponds).)
	☐ The point(s) of discharge and highlighted discharge route(s) clearly shown for one mile downstream.
	☐ The property boundaries of the landowners located on both sides of the discharge route for one full stream mile downstream of the point of discharge.
	☐ The property boundaries of the landowners along the watercourse for a one-half mile radius from the point of discharge if the point of discharge is into a lake, bay, estuary, or affected by tides.
	☑ The boundaries of the effluent disposal site (e.g., irrigation area or subsurface drainfield site) and all evaporation/holding ponds within the applicant's property.
	☑ The property boundaries of all landowners surrounding the applicant's property boundaries where the effluent disposal site is located.
	☐ The boundaries of the sludge land application site (for land application of sewage sludge for beneficial use) and the property boundaries of landowners within one-quarter mile of the applicant's property boundaries where the sewage sludge land application site is located.
	☐ The property boundaries of landowners within one-half mile in all directions from the applicant's property boundaries where the sewage sludge disposal site (e.g., sludge surface disposal site or sludge monofil) is located.
	Attachment: <u>G</u>
b.	\boxtimes that the landowners list has also been provided as mailing labels in electronic format (Avery 516 $ullet$).
c.	Check this box to confirm a separate list with the landowners' names and mailing

addresses cross-referenced to the landowner's map has been provided.

d. Provide the source of the landowners' names and mailing addresses: Brewster County

e.	As required by Texas Water Code § 5.115, is any permanent school fund land affected by this application?
	□ Yes ⋈ No
	If yes, provide the location and foreseeable impacts and effects this application has on tland(s): Click to enter text.
It	m 2. Original Photographs (Instructions, Page 37)
Pr to	vide original ground level photographs. Check the box next to each of the following item ndicate it is included.
	At least one original photograph of the new or expanded treatment unit location.
	At least two photographs of the existing/proposed point of discharge and as much area lownstream (photo 1) and upstream (photo 2) as can be captured. If the discharge is to an open water body (e.g., lake, bay), the point of discharge should be in the right or left edge ach photograph showing the open water and with as much area on each respective side on the discharge as can be captured.
\boxtimes	at least one photograph of the existing/proposed effluent disposal site.
\boxtimes	a plot plan or map showing the location and direction of each photograph.
Αţ	achment: <u>H</u>

INDUSTRIAL WASTEWATER PERMIT APPLICATION SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: N/A

WATER QUALITY PERMIT

PAYMENT SUBMITTAL FORM

Use this form to submit the Application Fee, if mailing the payment, (Instructions, Page 36-37)

- Complete items 1 through 5 below.
- Staple the check or money order in the space provided at the bottom of this document.
- Do not mail this form with the application form.
- Do not mail this form to the same address as the application.
- Do not submit a copy of the application with this form as it could cause duplicate permit entries.

Mail this form and the check or money order to:

BY REGULAR U.S. MAIL

BY OVERNIGHT/EXPRESS MAIL.

Texas Commission on Environmental Quality Texas Commission on Environmental Quality

Financial Administration Division

Financial Administration Division

Cashier's Office, MC-214

Cashier's Office, MC-214

P.O. Box 13088

12100 Park 35 Circle

Austin, Texas 78711-3088

Austin, Texas 78753

Permit No: WO000Lajitas Industrial Waste Water Application Fee Code: WOP

1. Check or Money Order Number: 4544

2. Check or Money Order Amount: \$350.00

3. Date of Check or Money Order: June 17, 2025

4. Name on Check or Money Order: Lajitas Capital Partners

5. APPLICATION INFORMATION

Name of Project or Site: Lajitas WTP

Physical Address of Project or Site: HC 70, Box 400, Lajitas, TX 79852

If the check is for more than one application, attach a list which includes the name of each Project or Site (RE) and Physical Address, exactly as provided on the application.

Attachment: Click to enter text.

LAJITAS CAPITAL PARTNERS

8111 WESTCHESTER DR. SUITE 600 DALLAS, TX 75219

4544

DATE June 17, 2025

ATTACHMENT 1

INDIVIDUAL INFORMATION

Item 1. Individual information (Instructions, Page 38)

Complete this attachment if the facility applicant or co-applicant is an individual. Make additional copies of this attachment if both are individuals.

Prefix (Mr., Ms., or Miss): Click to enter text.

Full legal name (first, middle, and last): Click to enter text.

Driver's License or State Identification Number: Click to enter text.

Date of Birth: Click to enter text.

Mailing Address: Click to enter text.

City, State, and Zip Code: Click to enter text.

Phone No.: Click to enter text.

Fax No.: Click to enter text.

E-mail Address: Click to enter text.

CN: Click to enter text.

5 884

INDUSTRIAL WASTEWATER PERMIT APPLICATION CHECKLIST OF COMMON DEFICIENCIES

Below is a list of common deficiencies found during the administrative review of industrial wastewater permit applications. To ensure the timely processing of this application, please review the items below and indicate each item is complete and in accordance applicable rules at 30 TAC Chapters 21, 281, and 305 by checking the box next to the item. If an item is not required this application, indicate by checking N/A where appropriate. Please do not submit the application until all items below are addressed.

- □ Core Data Form (TCEQ Form No. 10400)
 (Required for all applications types. Must be completed in its entirety and signed. Note: Form may be signed by applicant representative.)
- ☑ Correct and Current Industrial Wastewater Permit Application Forms (TCEQ Form Nos. 10055 and 10411. Version dated 5/10/2019 or later.)
- □ Water Quality Permit Payment Submittal Form (Page 14)
 (Original payment sent to TCEQ Revenue Section. See instructions for mailing address.)
- □ 7.5 Minute USGS Quadrangle Topographic Map Attached (Full-size map if seeking "New" permit. 8 ½ x 11 acceptable for Renewals and Amendments.)
- □ N/A ⊠ Current/Non-Expired, Executed Lease Agreement or Easement Attached
- □ N/A ⊠ Landowners Map
 (See instructions for landowner requirements.)

Things to Know:

- · All the items shown on the map must be labeled.
- The applicant's complete property boundaries must be delineated which includes boundaries of contiguous property owned by the applicant.
- The applicant cannot be its own adjacent landowner. You must identify the landowners immediately adjacent to their property, regardless of how far they are from the actual facility.
- If the applicant's property is adjacent to a road, creek, or stream, the
 landowners on the opposite side must be identified. Although the properties
 are not adjacent to applicant's property boundary, they are considered
 potentially affected landowners. If the adjacent road is a divided highway as
 identified on the USGS topographic map, the applicant does not have to
 identify the landowners on the opposite side of the highway.
- □ N/A ☑ Landowners Labels and Cross Reference List (See instructions for landowner requirements.)
- ⊠ Electronic Application Submittal
 (See application submittal requirements on page 23 of the instructions.)
- ☑ Original signature per 30 TAC § 305.44 Blue Ink Preferred (If signature page is not signed by an elected official or principle executive officer, a copy of signature authority/delegation letter must be attached.)

Summary of Application (in Plain Language)	

COMMISSION OF THE PROPERTY OF

TEXAS COMMISSION ON ENVIRONMENTAL OUALITY

INDUSTRIAL WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

The following information is required for all applications for a TLAP or an individual TPDES discharge permit.

For additional information or clarification on the requested information, please refer to the Instructions for Completing the Industrial Wastewater Permit Application¹ available on the TCEQ website. Please contact the Industrial Permits Team at 512-239-4671 with any questions about this form.

If more than one outfall is included in the application, provide applicable information for each individual outfall. If an item does not apply to the facility, enter N/A to indicate that the item has been considered. Include separate reports or additional sheets as clearly cross-referenced attachments and provide the attachment number in the space provided for the item the attachment addresses.

NOTE: This application is for an industrial wastewater permit only. Additional authorizations from the TCEQ Waste Permits Division or the TCEQ Air Permits Division may be needed.

Item 1. Facility/Site Information (Instructions, Page 39)

 Describe the general nature of the business and type(s) of industrial and commercial activities. Include all applicable SIC codes (up to 4).

Lajitas WTP is a groundwater EDR membrane plant serving the Lajitas Golf Resort community in Brewster County, Texas. The 0.3mgd membrane plant produces a process wastewater stream of up to 0.065mgd. This process wastewater is disposed of by irrigation of the golf course after blending with a larger groundwater irrigation volume. The plant has operated under a TLAP permit since about 2000. However, that permit expired in May 2025, requiring a New Permit application to continue facility operations. No changes are proposed from that previous TLAP permit.

b. Describe all wastewater-generating processes at the facility.

The o.3mgd EDR membrane groundwater plant produces a process waste stream of up to 0.065mgd, consisting of EDR reversal reject concentrate, multi-media iron reduction filter backwash and periodic membrane clean-in-place (CIP) acid backwash. No chemicals are added to the groundwater process stream except for chlorine used for iron oxidation and cationic polymer used to enhance iron removal. The source groundwater (Santa Elena Aquifer) has a TDS concentration of about 1,400mg/l, including NORM constituents (Uranium, Radium226-228), These dissolved solids are concentrated to an average waste stream TDS of about 6,000mg/l. The process waste stream is stored in a below-grade basin at the WTP and then transferred by closed pipe to the golf course irrigation pump station Lake E (including a 1-ft bentonite clay liner certified with the original TLAP permit), blended with irrigation groundwater (averaging about 110,000gpd annually) and then applied to 56.3 acres of irrigated golf course turf.

 $https://www.tceq.texas.gov/permitting/wastewater/industrial/TPDES_industrial_wastewater_steps.html\\$

c. Provide a list of raw materials, major intermediates, and final products handled at the facility. Materials List **Raw Materials** Intermediate Products **Final Products** N/A -Groundwater EDR WTP Potable water Attachment: N/A - Groundwater EDR membrane plant d. Attach a facility map (drawn to scale) with the following information: Production areas, maintenance areas, materials-handling areas, waste-disposal areas. and water intake structures. The location of each unit of the WWTP including the location of wastewater collection sumps, impoundments, outfalls, and sampling points, if significantly different from outfall locations. Attachment: I e. Is this a new permit application for an existing facility? Yes No If yes, provide background discussion: Previous TLAP Permit expired May 2025. This application is to continue facility operations and TLAP irrigation disposal. f. Is/will the treatment facility/disposal site be located above the 100-year frequency flood level. 100 X Yes No List source(s) used to determine 100-year frequency flood plain: FIRM - 4800841400B If **no**, provide the elevation of the 100-year frequency flood plain and describe what protective measures are used/proposed to prevent flooding (including tail water and

rainfall run-on controls) of the treatment facility and disposal area: The WTP and golf course disposal area are located above the 100-yr floodplain

Attachment: Click to enter text.

g. For **new** or **major amendment** permit applications, will any construction operations result in a discharge of fill material into a water in the state?

		Yes	\boxtimes	No		N/A (renewal only)
h.	If yes		1.g, ha	s the ap	plica	nt applied for a USACE CWA Chapter 404 Dredge and Fill
		Yes		No		
	If yes,	provide	the p	ermit nı	ımbei	r: Click to enter text.
	and the same					te of application submittal to the USACE: Click to enter
It	em 2.	Trea	atme	nt Sy	sten	n (Instructions, Page 40)
a.	wastev	vater at	this fa	acility. In	nclud	plogical treatment process(es) used/proposed to treat e a description of each treatment process, starting with the outfall/point of disposal.
	oxidate Pre-treduce revers with a mecha added to a begolf colored.	tion and eated wa ed TDS i e polarit hydrock anically v for seco elow-gra ourse irri tion disp	cationiater the ncludiry and relationic a ventilate one de concigation to sal ha	c polyme n passes ng NORM ejects co cid solut ed packe disinfect crete bas lake for is been p	er. The throu force to	e sand filter periodically backwashes to removed oxidized iron. Igh the two-stage electrodialysis (EDR) membrane unit to Intituents (Uranium and Radium). The EDR unit periodically Irate to waste, The unit is periodically cleaned-in-place (CIP) Iremove scale. Treated water then passes through a Ire to remove radon gas and raise pH. Free chlorine is then If to distribution. The combined process waste streams drain If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and the plant building and are them pump transferred to the If the plant building and the plant building and are them pump transferred to the If the plant building and the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to the If the plant building and are them pump transferred to
b.	flow in	ito the f	acility utfall/		vater :	ater balance showing all sources of water and wastewater flow into and from each treatment unit, and wastewater osal.
T+.		NATION STATES		J	4 /T	notwestions Done (0)
W-17075	Principal Billians Section 1947					nstructions, Page 40)
Do		acility ι es □	ise or No	plan to	use aı	ny wastewater impoundments (e.g., lagoons or ponds?)
3.e	no, proc for nev	eed to l	item 4.	impour	ndme	lete Item 3.a for existing impoundments and Items 3.a - nts. NOTE: See instructions, Pages 40-42, for additional ired by Items 3.a – 3.e.
a.						wing information for each existing, new, or proposed copies of the Impoundment Information table, if needed.

Use Designation: Indicate the use designation for each impoundment as Treatment (T), Disposal (D), Containment (C), or Evaporation (E).

Associated Outfall Number: Provide an outfall number if a discharge occurs or will occur.

Liner Type: Indicate the liner type as Compacted clay liner (C), In-situ clay liner (I), Synthetic/plastic/rubber liner (S), or Alternate liner (A). NOTE: See instructions for further detail on liner specifications. If an alternate liner (A) is selected, include an attachment that provides a description of the alternate liner and any additional technical information necessary for an evaluation.

Leak Detection System: If any leak detection systems are in place/planned, enter Y for yes. Otherwise, enter N for no.

Groundwater Monitoring Wells and Data: If groundwater monitoring wells are in place/planned, enter Y for yes. Otherwise, enter N for no. Attach any existing groundwater monitoring data.

Dimensions: Provide the dimensions, freeboard, surface area, storage capacity of the impoundments, and the maximum depth (not including freeboard). For impoundments with irregular shapes, submit surface area instead of length and width.

Compliance with 40 CFR Part 257, Subpart D: If the impoundment is required to be in compliance with 40 CFR Part 257, Subpart D, enter Y for yes. Otherwise, enter N for no.

Date of Construction: Enter the date construction of the impoundment commenced (mm/dd/yy).

Impoundment Information

Parameter	Pond #	Pond #	Pond #	Pond #
Use Designation: (T) (D) (C) or (E)	С			
Associated Outfall Number	N/A-TLAP			
Liner Type (C) (I) (S) or (A)	C			
Alt. Liner Attachment Reference				
Leak Detection System, Y/N	N			
Groundwater Monitoring Wells, Y/N	N	100		
Groundwater Monitoring Data Attachment				
Pond Bottom Located Above The Seasonal High-Water Table, Y/N	Y			
Length (ft)	750			
Width (ft)	250			
Max Depth From Water Surface (ft), Not Including Freeboard	5			
Freeboard (ft)	2			
Surface Area (acres)	2.4			
Storage Capacity (gallons)	3.1MG			
40 CFR Part 257, Subpart D, Y/N	N	5		
Date of Construction	06/01/2000	1 2116		

Attachment: Click to enter text.

The following information (Items 3.b - 3.e) is required only for new or proposed impoundments.

b.	ite	For new or proposed impoundments, attach any available information on the following items. If attached, check yes in the appropriate box. Otherwise, check no or not yet designed .							
	1.	Liner data							
			Yes		No		Not yet designed		
	2.	Lea	ık detect	ion s	stem or	grou	ndwater monitoring data		
			Yes		No		Not yet designed		
3. Groundwater impacts									
			Yes		No		Not yet designed		
							he bottom of the pond is not above the seasonal high- vater-bearing zone.		
	At	tach	ment: 🖸	lick to	enter to	ext.			
Fo	r TI	.AP	applicati	ions: l	Items 3.	c - 3.e	are not required , continue to Item 4.		
c.	an	d id		all ƙn			y of original quality and scale which accurately locates oply wells and monitor wells within ½-mile of the		
	At	tach	ment: 🖰	ick to	enter to	ext.			
d.	da	ta o	n depths	to gr	oundwa	ter fo	Reports (e.g., driller's logs, completion data, etc.), and rall known water supply wells including a description of ere obtained.		

Attachment: Click to enter text.

e. Attach information pertaining to the groundwater, soils, geology, pond liner, etc. used to assess the potential for migration of wastes from the impoundments or the potential for contamination of groundwater or surface water.

Attachment: Click to enter text.

Item 4. Outfall/Disposal Method Information (Instructions, Page 42)

Complete the following tables to describe the location and wastewater discharge or disposal operations for each outfall for discharge, and for each point of disposal for TLAP operations.

If there are more outfalls/points of disposal at the facility than the spaces provided, copies of pages 6 and/0r numbered accordingly (i.e., page 6a, 6b, etc.) may be used to provide information on the additional outfalls.

For TLAP applications: Indicate the disposal method and each individual irrigation area I, evaporation pond E, or subsurface drainage system S by providing the appropriate letter designation for the disposal method followed by a numerical designation for each disposal

area in the space provided for Outfall number (e.g. E1 for evaporation pond 1, I2 for irrigation area No. 2, etc.).

Outfall Longitude and Latitude

Latitude (Decimal Degrees)	Longitude (Decimal Degrees)
29.257	103.773

Outfall Location Description

Outfall No.	Location Description						

Description of Sampling Point(s) (if different from Outfall location)

Outfall No.	Description of sampling point						

Outfall Flow Information - Permitted and Proposed

Outfall No.	Permitted Daily Avg Flow (MGD)	Permitted Daily Max Flow (MGD)	Proposed Daily Avg Flow (MGD)	Proposed Daily Max Flow (MGD)	Anticipated Discharge Date (mm/dd/yy)
II			0.065	0.065	06/01/2000

Outfall Discharge - Method and Measurement

Outfall No.	Pumped Discharge? Y/N	Gravity Discharge? Y/N	Type of Flow Measurement Device Used
I1	Y	N	Doppler Flow Meter

Outfall Discharge - Flow Characteristics

Outfall No.	Intermittent Discharge? Y/N	Continuous Discharge? Y/N	Seasonal Discharge? Y/N	Discharge Duration (hrs/day)	Discharge Duration (days/mo)	Discharge Duration (mo/yr)
I1	Y	N	N	4	30	12

Outfall No.	Intermittent	Continuous	Seasonal	Discharge	Discharge	Discharge
	Discharge?	Discharge?	Discharge?	Duration	Duration	Duration
	Y/N	Y/N	Y/N	(hrs/day)	(days/mo)	(mo/yr)
Outfall Waste	estream Contril	outions				

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow
EDR Wastewater	0.05	75
Multimedia Filter Backwash	0.015	25
EDR CIP (Periodic)	0.001	<1
5		-

Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow
	*	

Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

Attachment: Click to enter text.

Item 5. Blowdown and Once-Through Cooling Water Discharges (Instructions, Page 43)

a. Indicate if the facility currently or propose	oses t	O.
--	--------	----

- □ Yes ⋈ No
 Use cooling towers that discharge blowdown or other wastestreams
 □ Yes ⋈ No
 Use boilers that discharge blowdown or other wastestreams
- ☐ Yes ☒ No Discharge once-through cooling water

NOTE: If the facility uses or plans to use cooling towers or once-through cooling water, Item 12 is required.

- b. If **yes** to any of the above, attach an SDS with the following information for each chemical additive.
 - Manufacturers Product Identification Number
 - Product use (e.g., biocide, fungicide, corrosion inhibitor, etc.)
 - Chemical composition including CASRN for each ingredient
 - Classify product as non-persistent, persistent, or bioaccumulative
 - Product or active ingredient half-life
 - Frequency of product use (e.g., 2 hours/day once every two weeks)
 - Product toxicity data specific to fish and aquatic invertebrate organisms
 - Concentration of whole product or active ingredient, as appropriate, in wastestream.

In addition to each SDS, attach a summary of the above information for each specific wastestream and the associated chemical additives. Specify which outfalls are affected.

Attachment: Click to enter text.

c. Cooling Towers and Boilers

If the facility currently or proposes to use cooling towers or boilers that discharge blowdown or other wastestreams to the outfall(s), complete the following table.

Cooling Towers and Boilers

Type of Unit	Number of Units	Daily Avg Blowdown (gallons/day)	Daily Max Blowdown (gallons/day)
Cooling Towers			
Boilers			

Item 6. Stormwater Managemen	it (Instructions, Page 44)				
Will any existing/proposed outfalls discharge as defined at 40 CFR § 122.26(b)(14), commin	stormwater associated with industrial activities, agled with any other wastestream?				
□ Yes ⊠ No					
If yes, briefly describe the industrial processes manner which may result in exposure of the acenter text.					
Item 7. Domestic Sewage, Sewage Management and Dispos	ge Sludge, and Septage sal (Instructions, Page 44)				
Domestic Sewage - Waste and wastewater fred discharged to a wastewater collection system of					
a. Check the box next to the appropriate meth sludge treatment or disposal. Complete Wo	hod of domestic sewage and domestic sewage orksheet 5.0 or Item 7.b if directed to do so.				
☑ Domestic sewage is routed (i.e., connected to or transported to) to a WWTP permitted to receive domestic sewage for treatment, disposal, or both. Complete Item 7.b.					
$\hfill\square$ Domestic sewage disposed of by an on-site septic tank and drainfield system. Complete Item 7.b.					
□ Domestic and industrial treatment sludge ARE commingled prior to use or disposal.					
	☐ Industrial wastewater and domestic sewage are treated separately, and the respective sludge IS NOT commingled prior to sludge use or disposal. Complete Worksheet 5.0.				
☐ Facility is a POTW. Complete Worksheet	5.0.				
☐ Domestic sewage is not generated on-site	e.				
☐ Other (e.g., portable toilets), specify and	Complete Item 7.b: Click to enter text.				
 Provide the name and TCEQ, NPDES, or TPD which receives the domestic sewage/septagename and TCEQ Registration No. of the hau 	ge. If hauled by motorized vehicle, provide the				
Domestic Sewage Plant/Hauler Name					
Plant/Hauler Name	Permit/Registration No.				
Lajitas Municipal WWTP	WQ0014282001				
Item 8. Improvements or Comp	liance/Enforcement				
Requirements (Instruction					
 a. Is the permittee currently required to meet enforcement? Yes No 	any implementation schedule for compliance or				
96034 ASPRINTS Deel201 139/10004	or any improvements or construction projects?				

	□ Yes ⊠ No
c.	If yes to either 8.a or 8.b, provide a brief summary of the requirements and a status update Click to enter text.
It	em 9. Toxicity Testing (Instructions, Page 45)
	ave any biological tests for acute or chronic toxicity been made on any of the discharges or a receiving water in relation to the discharge within the last three years? □ Yes ☑ No
If	yes, identify the tests and describe their purposes: Click to enter text.
	dditionally, attach a copy of all tests performed which have not been submitted to the TCEQ EPA. Attachment: Click to enter text.
It	em 10. Off-Site/Third Party Wastes (Instructions, Page 45)
a.	Does or will the facility receive wastes from off-site sources for treatment at the facility, disposal on-site via land application, or discharge via a permitted outfall?
	□ Yes ⊠ No
	If yes, provide responses to Items 10.b through 10.d below.
	If no , proceed to Item 11.
b.	Attach the following information to the application:
	 List of wastes received (including volumes, characterization, and capability with on-site wastes).
	 Identify the sources of wastes received (including the legal name and addresses of the generators).
	 Description of the relationship of waste source(s) with the facility's activities.
	Attachment: Click to enter text.
c.	Is or will wastewater from another TCEQ, NPDES, or TPDES permitted facility commingled with this facility's wastewater after final treatment and prior to discharge via the final outfall/point of disposal?
	□ Yes ⊠ No
	If yes , provide the name, address, and TCEQ, NPDES, or TPDES permit number of the contributing facility and a copy of any agreements or contracts relating to this activity.
	Attachment: Click to enter text.
d.	Is this facility a POTW that accepts/will accept process wastewater from any SIU and has/is required to have an approved pretreatment program under the NPDES/TPDES program?
	□ Yes ⊠ No
If	yes, Worksheet 6.0 of this application is required.

Item 11. Radioactive Materials (Instructions, Page 46) a. Are/will radioactive materials be mined, used, stored, or processed at this facility? Yes X No If yes, use the following table to provide the results of one analysis of the effluent for all radioactive materials that may be present. Provide results in pCi/L. Radioactive Materials Mined, Used, Stored, or Processed Radioactive Material Name Concentration (pCi/L) b. Does the applicant or anyone at the facility have any knowledge or reason to believe that radioactive materials may be present in the discharge, including naturally occurring radioactive materials in the source waters or on the facility property? Yes No \boxtimes If yes, use the following table to provide the results of one analysis of the effluent for all radioactive materials that may be present. Provide results in pCi/L. Do not include information provided in response to Item 11.a. Radioactive Materials Present in the Discharge Radioactive Material Name Concentration (pCi/L) Uranium 300 60 Radium 226 Radium 228 60 Item 12. Cooling Water (Instructions, Page 46) a. Does the facility use or propose to use water for cooling purposes? П Yes X No Decommissioned: Click to enter text.

If yes, complete Items 12.b thru 12.f. If no, stop here.

To Be Decommissioned: Click to enter text.

If **decommissioned**, provide the date operation ceased and stop here.

If to be decommissioned, provide the date operation is anticipated to cease and stop here.

b. Cooling water is/will be obtained from a groundwater source (e.g., on-site well).

The Ionics EDR membrane system removes charged particles by applying a direct current (DC) electric field between alternating cationic and anionic semi-permeable membrane plates. Removal efficiency varies somewhat based on particle mass, surface charge and several other factors. Ionic's design process model predicts about a 65% removal efficiency for total dissolved solids (TDS) reduction of the Sante Elena feed water (1450mg/l TDS design feed producing a +/- 500mg/l TDS product water). Removal efficiency for radionuclide metals has been confirmed as being comparable to overall TDS efficiency.

Four consecutive weekly composite samples were collected between March 2 and April 1, 2011 to better define the blended wastewater quality produced by the plant. While EDR wastewater quality remains relatively constant (about 6,500mg/l TDS), the blended waste stream quality varies considerably depending on the relative amount of sand filter media filter backwash generated during any sampling period. Table 1 presents a summary of this composite sampling exercise.

Table No.1 WTP Wastewater – Composite Sampling						
Date	TDS (mg/L)	Gross A (piC/L)	Gross B (piC/L)	Rad-226 (piC/L)	Rad-228 (piC/L)	Uranium (ug/L)
3/9/11	(1115/27)	114	120	33.8	2.68	14.3
3/18/11	5300	131	97	28.9	2.02	29.6
3/25/11	3300	110	103	20.0	1.33	37.5
4/01/11	3200	81	74	32.3	2.77	36
Avg.	3930	109	99	28.8	2.20	29.4
GW Well	1450	19.3	17.2	8.54	0.62	6.1

Review of this data indicates several conclusions, including:

- Blended water quality as generally indicated by TDS is quite variable, depending largely on the sand filter media backwash volume during any sampling period.
- The relationship between TDS and radionuclides does not appear linear, at times inversely proportionate to TDS shifts, suggesting additional influencing variables.
- Results suggest that reasonable wastewater quality goals can be established, and managed through adjustment of media backwashing volume over time, including:
 - o TDS 4,000mg/l
 - o Gross Alpha 110piC/L
 - o Gross Beta 100piC/L
 - o Radium 226 30piC/L
 - o Radium 228 3piC/L
 - Uranium 30ug/L

Alternately to the 1680mg/l TDS injectate quality, we propose that about 15% of the potable production be used for media filter backwash (considerably in excess of the 3-5% anticipated for effective backwashing of the iron removal filters), resulting in a blended

	If y	y es , stop her	e. If no ,	cont	inue.				
c.	Co	oling Water	Supplier	į.					
	1.	Provide the supply wate						or the CWIS that	supplies or will
Cod	lin	g Water Intak	e Structu	re(s)	Owner(s	and Operat	or(s)		
CV	VIS	ID							
Ov	vn€	er							
OI	per	ator						-110	
	2.	Cooling wat	ter is/wi	ll be	obtaine	d from a Pu	ıblic Wa	ter Supplier (PW	S)
			No		Yes; PV	VS No.: Click	k to ente	er text.	
		If no , contin	nue. If ye	es, p	rovide t	he PWS Reg	istratior	n No. and stop he	ere.
	3.	Cooling wat	ter is/wi	ll be	obtaine	d from a re	claimed	water source?	
			No		Yes; Au	th No.: Clic	k to ent	er text.	
		If no , contin	nue. If y e	es, p	rovide t	he Reuse Ai	ıthoriza	tion No. and sto	p here.
	4.	Cooling wat	ter is/wi	ll be	obtaine	d from an I	ndepen	dent Supplier	
		<u> </u>	No		Yes; AI	F:_Click to e	nter tex	at.	
									the Independent rposes and proceed.
d.	31	6(b) General	Criteria						
	1.	The CWIS(s) cumulative							ity has or will have a
		<u> </u>	Yes		No				
	2.	At least 25% exclusively							used at the facility
			Yes		No				
	3.							ater for cooling p of the United Stat	
			Yes		No. Exp	lanation:_C	lick to e	nter text.	
		If no , provid Waters of th						does not meet t	he definition of
£ **	00	to all three c	moetics	o in l	tom 10	d the facili	tu maat	a tha minimum a	mitaria ta ha auhiaat

Yes

No

If yes to all three questions in Item 12.d, the facility meets the minimum criteria to be subject to the full requirements of Section 316(b) of the CWA. Proceed to Item 12.f.

su	bje	to any of the questions in Item 12.d, the facility does not meet the minimum criteria to be ct to the full requirements of Section 316(b) of the CWA; however, a determination is red based upon BPJ. Proceed to Item 12.e.
e.		ne facility does not meet the minimum requirements to be subject to the fill requirements. Section 316(b) and uses/proposes to use cooling towers.
		Yes □ No
		yes, stop here. If no , complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.b.1, and 3.a to ow for a determination based upon BPJ.
f.	Oil	l and Gas Exploration and Production
	1.	The facility is subject to requirements at 40 CFR Part 435, Subparts A or D.
		□ Yes ⊠ No
		If yes, continue. If no, skip to Item 12.g.
	2.	The facility is an existing facility as defined at 40 CFR § 125.92(k) or a new unit at an existing facility as defined at 40 CFR § 125.92(u).
		□ Yes □ No
		If yes , complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.b.1, and 3.a to allow for a determination based upon BPJ. If no , skip to Item 12.g.3.
g.	Co	empliance Phase and Track Selection
	1.	Phase I – New facility subject to 40 CFR Part 125, Subpart I
		□ Yes ⊠ No
		If yes, check the box next to the compliance track selection, attach the requested information, and complete Worksheet 11.0, Items 2 and 3, and Worksheet 11.2.
		□ Track I – AIF greater than 2 MGD, but less than 10 MGD
		 Attach information required by 40 CFR §§ 125.86(b)(2)-(4).
		□ Track I - AIF greater than 10 MGD
		 Attach information required by 40 CFR § 125.86(b).
		□ Track II
		 Attach information required by 40 CFR § 125.86(c).
		Attachment: Click to enter text.
	2.	Phase II – Existing facility subject to 40 CFR Part 125, Subpart J
		□ Yes □ No
		If yes, complete Worksheets 11.0 through 11.3, as applicable.
	3.	Phase III – New facility subject to 40 CFR Part 125, Subpart N
		□ Yes □ No
		If yes, check the box next to the compliance track selection and provide the requested information.

□ Track I - Fixed facility
 Attach information required by 40 CFR § 125.136(b) and complete Worksheet 11.0, Items 2 and 3, and Worksheet 11.2.
□ Track I – Not a fixed facility
 Attach information required by 40 CFR § 125.136(b) and complete Worksheet 11.0, Item 2 (except CWIS latitude/longitude under Item 2.a).
□ Track II – Fixed facility
 Attach information required by 40 CFR § 125.136(c) and complete Worksheet 11.0, Items 2 and 3.
Attachment: Click to enter text.
Item 13. Permit Change Requests (Instructions, Page 48)
This item is only applicable to existing permitted facilities.
a. Is the facility requesting a major amendment of an existing permit?
□ Yes ⊠ No
If yes , list each request individually and provide the following information: 1) detailed information regarding the scope of each request and 2) a justification for each request. Attach any supplemental information or additional data to support each request.
b. Is the facility requesting any minor amendments to the permit?
☐ Yes ☐ No
If yes, list and describe each change individually.
Click to enter text.
Chek to enter text.
c. Is the facility requesting any minor modifications to the permit? ☐ Yes ☑ No
If yes, list and describe each change individually.

All laboratory tests performed must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - periodically inspected by the TCEQ; or
 - located in another state and is accredited or inspected by that state;
 or
 - performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Accicultation and cermication.	
Printed Name: Click to enter text.	
Title: Click to enter text.	Note: The Laboratory Accreditation will be submitted with the pending effluent and soi
Signature:	sampling reports. However, the TLAP
Date:	application is being submitted to begin the Administrative Review since the past TLAF Permit has now expired.

Click to enter text.		

Item 14. Laboratory Accreditation (Instructions, Page 49)

All laboratory tests performed must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - periodically inspected by the TCEQ; or
 - located in another state and is accredited or inspected by that state; or
 - o performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: Click to enter text.

Title: Click to enter text.

Signature: ______

Date: _____

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 1.0: EPA CATEGORICAL EFFLUENT GUIDELINES

This worksheet is required for all applications for TPDES permits for discharges of wastewaters subject to EPA categorical effluent limitation guidelines (ELGs).

Item 1. Cate	gorical Industries	(Instructions, Pag	ge 53)
Is this facility subj	ect to any 40 CFR categorie	cal ELGs outlined on pag	e 53 of the instructions?
□ Yes ⊠	No		
If no , this workshe	et is not required. If yes , p	rovide the appropriate ir	nformation below.
40 CFR Effluent Guid	deline		
Industry	4. 20 aprendicts 20 C	40	CFR Part
*			
0 8 11-23-23-23-23-23-23-23-23-23-23-23-23-23-			<u> </u>
			46- 6-
r. 0 D 1	A	. /*	60 50 E A
item 2. Prod	uction/Process Da	ta (instructions, i	Page 54)
of oil and gas expl	ES permit applications requon- oration and production wander the Oil and Gas Extrace and 2 instead.	stewater (discharges into	or adjacent to water in
a. Production Dat	a		
	e data for effluent guidelir	nes with production-base	d effluent limitations.
Production Data		REMANDE - ROUGHERMAN - L era (1924) before en forsa mina, el antigenante	
Subcategory	Actual Quantity/Day	Design Quantity/Day	Units

<u></u>			

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND APPLICATION OF EFFLUENT

This worksheet is required for all applications for a permit to disposal of wastewater by land application (i.e., TLAP)).

Item 1. Type of Disposal System (Instructions, Page 69)

Check the box next to the type of land disposal requested by this application:

\boxtimes	Irrigation	☐ Subsurface application	
	Evaporation	 Subsurface soils absorption 	
	Evapotranspiration beds	☐ Surface application	
	Drip irrigation system	☐ Other, specify: <u>Click to enter text.</u>	1

Item 2. Land Application Area (Instructions, Page 69)

Land Application Area Information

Effluent Application (gallons/day)	Irrigation Acreage (acres)	Describe land use & indicate type(s) of crop(s)	Public Access? (Y/N)
65,000 (Process WWTR)			
110,000 (Irrigation GW – Yearly Average)	53.6	Golf Course - Turf	Y (Private Course)

Item 3. Annual Cropping Plan (Instructions, Page 69)

Attach the required cropping plan that includes each of the following:

- Cool and warm season plant species
- Breakdown of acreage and percent of total acreage for each crop
- Crop growing season
- Harvesting method/number of harvests
- Minimum/maximum harvest height
- Crop yield goals
- Soils map
- Nitrogen requirements per crop
- Additional fertilizer requirements
- Supplemental watering requirements
- Crop salt tolerances
- Justification for not removing existing vegetation to be irrigated

Item 4. Well and Map Information (Instructions, Page 70)

a. Check each box to confirm the required information is shown and labeled on the attached USGS map: The exact boundaries of the land application area X On-site buildings Waste-disposal or treatment facilities Effluent storage and tailwater control facilities ∇ Buffer zones All surface waters in the state onsite and within 500 feet of the property boundaries All water wells within ½-mile of the disposal site, wastewater ponds, or property boundaries All springs and seeps onsite and within 500 feet of the property boundaries Attachment: L b. List and cross reference all water wells located on or within 500 feet of the disposal site. wastewater ponds, or property boundaries in the following table. Attach additional pages as necessary to include all of the wells.

Well and Map Information Table

Well ID	Well Use	Producing? Y/N/U	Open, cased, capped, or plugged?	Proposed Best Management Practice
N/A				
=====	4 8 8			

Attachment: Click to enter text.

c.	Groundwater monitoring wells or lysimeters are/will be installed around the land
	application site or wastewater ponds.

Yes No

If yes, provide the existing/proposed location of the monitoring wells or lysimeters on the site map attached for Item 4.a. Additionally, attach information on the depth of the wells or lysimeters, sampling schedule, and monitoring parameters for TCEQ review, possible modification, and approval.

Attachment: M (Groundwater Report Below)

d. Attach a short groundwater technical report using 30 TAC § 309.20(a)(4) as guidance. Attachment:

Item 5. Soil Map and Soil Information (Instructions, Page 71)

Check each box to confirm that the following information is attached:

- a.

 USDA NRCS Soil Survey Map depicting the area to be used for land application with the locations identified by fields and crops.
- b.

 Breakdown of acreage and percent of total acreage for each soil type.
- c. \(\Bigcirc \) Copies of laboratory soil analyses. Attachment: \(\bar{N} \)

Item 6. Effluent Monitoring Data (Instructions, Page 72)

a. Completion of Table 14 is required for all renewal and major amendment applications. Complete the table with monitoring data for the previous two years for all parameters regulated in the current permit. An additional table has been provided with blank headers for parameters regulated in the current permit which are not listed in Table 14.

Date Daily Avg BOD5 TSS				Nitrogen	c (check one): Conductivity	Composite Total	Hydraulic
(mo/yr)	Daily Avg Flow (gpd)	(mg/L)	(mg/L)	(mg/L)	(mmhos/cm)	acres irrigated	Application rate (acre-feet/month)
					2		
				*			
					ř.		
			-				-

Date (mo/yr)	Daily Avg Flow (gpd)	BOD5 (mg/L)	TSS (mg/L)	Nitrogen (mg/L)	Conductivity (mmhos/cm)	Total acres irrigated	Hydraulic Application rate (acre-feet/month)
41-2-2							

b. Use this table to provide effluent analysis for parameters regulated in the current permit which are not listed in Table 14.

Additional Parameter Effluent Analysis

Date (mo/yr)						11
			-			
).
	- 17 					
			2			
		=				
		<u> </u>				
						_
7(6					_	

c. Attach an explanation of all persistent excursions to permitted parameters and corrective actions taken. Attachment: <u>Click to enter text.</u>

Item 7. Pollutant Analysis (Instructions, Page 72)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): Click to enter text.
- b.

 Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Complete Tables 15 and 16.

Pollutant		Sar (mg	nple 1 g/L)		ample 2 ng/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
BOD (5-day)	2	+		(%			
CBOD (5-day)							
Chemical oxygen dema	nd		0.00				
Total organic carbon							
Dissolved oxygen							
Ammonia nitrogen							
Total suspended solids		No	te: The P	allu	tant Analysis	and Soil An	alvsis
Nitrate nitrogen		are	e pending a	and	will be subr	nitted once	
Total organic nitrogen						t ion is being nistrative Rev	view.
Total phosphorus						as now expi	
Oil and grease							
Total residual chlorine							
Total dissolved solids						**************************************	
Sulfate							
Chloride							
Fluoride				Г			
Total alkalinity (mg/L a	s CaCO3)			1			
Temperature (°F)							
pH (standard units)							
Fable 16 for Outfall No.: Cl	ick to enter	text.	Samples	are	(check one):	□ Composi	ite 🗆 Grab
Pollutant	Sample (µg/L)		Sample 2 (µg/L)		Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (µg/L)
Aluminum, total							2.5
Antimony, total							5
Arsenic, total							0.5
Barium, total							3

Item 7. Pollutant Analysis (Instructions, Page 72)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): Click to enter text.
- b. \square Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Complete Tables 15 and 16.

Pollutant		San (mg	aple 1 g/L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
BOD (5-day)						
CBOD (5-day)						
Chemical oxygen deman	d					
Total organic carbon						
Dissolved oxygen	W					
Ammonia nitrogen						
Total suspended solids						
Nitrate nitrogen						
Total organic nitrogen						
Total phosphorus						
Oil and grease						
Total residual chlorine						
Total dissolved solids						
Sulfate						
Chloride						
Fluoride						
Total alkalinity (mg/L as	CaCO3)					
Temperature (°F)						
pH (standard units)						
Table 16 for Outfall No.: Cli	ck to enter	text.	Samples a	are (check one)): Compos	ite 🗆 Grab
Pollutant	Sample (µg/L)	e 1	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (µg/L)
Aluminum, total						2.5
Antimony, total						5
Arsenic, total						0.5
Barium, total						3

Pollutant	Sample 1 (µg/L)	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (µg/L)
Beryllium, total					0.5
Cadmium, total	5				1
Chromium, total				İ	3
Chromium, hexavalent					3
Chromium, trivalent					N/A
Copper, total					2
Cyanide, available					2/10
Lead, total					0.5
Mercury, total					0.005/0.0005
Nickel, total					2
Selenium, total					5
Silver, total					0.5
Thallium, total					0.5
Zinc, total					5.0

INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 3.1: SURFACE LAND APPLICATION AND APPLICATION

This worksheet **is required** for all applications for a permit to disposal of wastewater by surface land application or evaporation.

Item 1. Edwards Aquifer (Instructions, Page 73)

a. Is the facility subject to 30 TAC Chapter 213, Edwards Aquifer Rules? Yes \times No If no, proceed to Item 2. If yes, complete Items 1.b and 1.c. b. Check the box next to the subchapter applicable to the facility. 30 TAC Chapter 213, Subchapter A 30 TAC Chapter 213, Subchapter B c. If 30 TAC Chapter 213, Subchapter A applies, attach either: 1) a Geologic Assessment (if conducted in accordance with 30 TAC § 213.5) or 2) a report that contains the following: A description of the surface geological units within the proposed land application site and wastewater pond area. The location and extent of any sensitive recharge features in the land application site and wastewater pond area • A list of any proposed BMPs to protect the recharge features. Attachment: Click to enter text. Item 2. Surface Spray/Irrigation (Instructions, Page 73) a. Provide the following information on the irrigation operations: Area under irrigation (acres): 53.6 Design application rate (acre-ft/acre/yr): 1.35 (Process WWTR – not including GW irrigation) Design application frequency (hours/day): 4 Design application frequency (days/week): 7 Design total nitrogen loading rate (lbs nitrogen/acre/year): N/A (Grndwtr EDR waste - Not including fertilizer applied to gold course) Average slope of the application area (percent): o (Golf course) Maximum slope of the application area (percent): o (Golf course) Irrigation efficiency (percent): 65 - Desert conditions Effluent conductivity (mmhos/cm): (Pending) Soil conductivity (mmhos/cm): (Pending) Curve number: Click to enter text.

Describe the application method and equipment: Golf course irrigation – Low angle spray

b. Attach a detailed engineering report which includes a water balance, storage volume calculations, and a nitrogen balance. Attachment: O

Item 3. Evaporation Ponds (Instructions, Page 74)

- a. Daily average effluent flow into ponds: Click to enter text. gallons per day
- Attach a separate engineering report of evaporation calculations for average long-term and worst-case critical conditions. Attachment: Click to enter text.

Item 4. Evapotranspiration Beds (Instructions, Page 74)

a. Provide the following information on the evapotranspiration beds:

Number of beds: Click to enter text.

Area of bed(s) (acres): <u>Click to enter text.</u>

Depth of bed(s) (feet): <u>Click to enter text.</u>

Void ratio of soil in the beds: Click to enter text.

Storage volume within the beds (include units): <u>Click to enter text.</u>

Description of any lining to protect groundwater: <u>Click to enter text.</u>

- b. Attach a certification by a licensed Texas professional engineer that the liner meets TCEQ requirements. Attachment: Click to enter text.
- c. Attach a separate engineering report with water balance, storage volume calculations, and description of the liner. Attachment: <u>Click to enter text.</u>

Item 5. Overland Flow (Instructions, Page 74)

a. Provide the following information on the overland flow:

Area used for application (acres): Click to enter text.

Slopes for application area (percent): Click to enter text.

Design application rate (gpm/foot of slope width): Click to enter text.

Slope length (feet): Click to enter text.

Design BOD5 loading rate (lbs BOD5/acre/day): Click to enter text.

Design application frequency (hours/day): Click to enter text.

Design application frequency (days/week): Click to enter text.

b. Attach a separate engineering report with the method of application and design requirements according to 30 TAC § 217.212. Attachment: Click to enter text.

Lajitas Water Treatment Plant

TLAP Permit Application

Exhibits Listing

Exhibit A Core Data Form

Exhibit B Plain Language Template

Exhibit C Public Involvement Plan

Exhibit D TLAP Disposal Area Lease Agreement

Exhibit E USGS Map

Exhibit F TLAP Disposal Area

Exhibit G Landowners' Map

Exhibit H Original Photos

Exhibit I Facility Map

Exhibit J Flow Schematic

Exhibit K Annual Cropping Plan

Exhibit L Well and Map Information

Exhibit M Groundwater Technical Report

Exhibit N Soil Map and Soil Information

Exhibit O Water Balance

Exhibit A Core Data Form

TCEQ Use Only



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)

Renewal	(Core Date	Form should be subm	itted with the rei	newal form)		Other				
2. Customer Reference Number (if issued) CN 603406604 Follow this link for CN or RN n Central Reg						3. Regulated Entity Reference Number (if issued)					
				Central Registry**			102079	365			
ECTIO	N II:	Customer	Inform	ation	1						
1. General C	ustomer l	nformation	5. Effective I	Date for C	ustomer In	formation	Update	es (mm/dd/yyyy)			
New Custo	mer	⊠ t	Jpdate to Custon	ner Informa	ation	Cha	nge in Re	gulated Entity Own	ership	0	
Change in I	egal Name	(Verifiable with the Te	exas Secretary of	State or Te	xas Comptro			7			
rl. c											
		ubmitted here may		tomatica	lly based o	n what is	current (and active with t	he Texas Secr	etary of State	
SOS) or Text	is Compti	roller of Public Acco	unts (CPA).								
5. Customer	Legal Na	me (If an individual, pr	int last name firs	t: eg: Doe,	John)		<u>If new</u>	Customer, enter pr	evious Custom	er below:	
Lajitas Municij	oal Service	s Company LLC									
7. TX SOS/CI	A Filing N	lumber	8. TX State T	ax ID (11 c	digits)		9. Federal Tax ID		10. DUNS	10. DUNS Number (if	
				,			applicable)		.,		
800913868			32034356587				(9 digits)				
							32-02	25678			
1. Type of C	ustomer	⊠ Corpora	tion			☐ Indivi	dual	Partne	ership: 🔲 Gen	eral 🔲 Limited	
		County Federal	Local State	Other		Sole Proprietorship Other:					
l2. Number							_	dependently Ow		rated?	
And the second		Carried Client - Santine		luni d					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1-1-11	
⊠ 0-20 ⊔	21-100	101-250 251	-500 5 01 a	nd higher			⊠ Ye	s No			
4. Custome	r Role (Pro	oposed or Actual) – as	it relates to the R	Reaulated E	ntity listed o	n this form	Please c	heck one of the follo	owina		
									····· y		
Owner		Operator		ner & Oper				Other:			
Occupation	al Licensee	Responsible Pa	irty UV	CP/BSA App	plicant						
15. Mailing											
	14241 Dallas Parkway, Ste 800										
Address:	City Dallas			State TX ZIP		75254		ZIP+4			
	City	341144		State	1.6	211	. 52,54		EII (7		
l6. Country	Mailing Ir	formation (if outside	USA)		17	. E-Mail A	ddress (if applicable)			
18. Telephon	e Numbe	r	10	Fytensi	on or Code		T	20. Fax Number	(if applicable)		

TCEQ-10400 (11/22) Page 1 of 3

SECTION III: Regulated Entity Information

21. General Regulated En	tity Informa	ition (If 'New Re	gulated Entity" is sele	ected, a new	permit	applica	ition is also	required.)		Î
	3	Regulated Entity		to Regulate						
The Regulated Entity Namas Inc, LP, or LLC).	ne submitte	d may be upda	ted, in order to m	eet TCEQ C	ore Dat	ta Stai	ndards (re	moval of or	ganizatio	nal endings such
22. Regulated Entity Nam	ne (Enter nam	e of the site when	re the regulated action	on is taking p	olace.)					
Lajitas Water Treatment Plan	t									
23. Street Address of the Regulated Entity:	New wetlan	d is located abou	t 700-ft north of FM	-1 7 0 and ab	out 0.5 r	niles n	ortheast of	the Maverick	Ranch RV F	Park entrance.
(No PO Boxes)	City	Lajitas	State	ТХ	ZIP		79852		ZIP + 4	
24. County	Brewster		.*		-		7		,	
		If no Stre	et Address is prov	ided, fields	25-28	are re	quired.		-	
25. Description to Physical Location:		P located in Lajita nown on the appl	is, Texas. The WTP is ication exhibits.	located abo	ut 500 f	eet sou	ith of SH-17	0 and about (0.3 miles ea	ast of the resort
26. Nearest City		-		13			State		Nea	rest ZIP Code
Lajitas (Private Resort Comm	unity)						ТХ		798	52
Latitude/Longitude are re used to supply coordinate						itando	ırds. (Geo	coding of the	e Physical	Address may be
27. Latitude (N) In Decima	al:	29.261		28.	Longit	ude (V	V) In Deci	mal:	103.771	
Degrees	Minutes		Seconds	Degrees		M	Minutes		Seconds	
29		15	40.7		1	03		46		15.4
29. Primary SIC Code (4 digits)		Secondary SIC	Code	31. Primary NAICS Code (5 or 6 digits) 32. Seconda (5 or 6 digits)				C\$ Code		
4941	494	5		221310				221320		
33. What is the Primary B	Business of t	his entity? (D	o not repeat the SIC	or NAICS des	cription.)		1-,		
Resort community and golf co	ourse	-								
14241 Dallas Parkway, Ste 800 34. Mailing										
Address:	City	Dallas	State	тх	7	ZIP	75254		ZIP + 4	
35. E-Mail Address:	Ron	@theholmesfirm	n.com							I
36. Telephone Number			37. Extension or	r Code		38. F	ax Numbe	er (if applicabl	le)	
(469) 317-3470						() -			

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

Dam Safety		Districts	Edwards Aquife	(Emissions Inventory Air	☐ Industrial Hazardous Waste
☐ Municipal Solid Waste		New Source Review Air	□ OSSF		Petroleum Storage Tank	□ PWS
Sludge		Storm Water	☐ Title V Air		☐ Tires	Used Oil
☐ Voluntary	Cleanup	⊠ Wastewater	☐ Wastewater Agri	iculture	☐ Water Rights	Other:
SECTIO	N IV: Pr	eparer In	formation			L
40. Name:	40. Name: Mark Roetzel, P.E.			41. Title:	Project Engineer	
42. Telephon	e Number	43. Ext./Code	44. Fax Number	45. E-Ma	ail Address	
210) 581-1111			(210)581-5555	mark.roetzel@cdsmuery.com		

Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Lajitas Municipal Services Company LLC	Job Title:	Authorized Representat	ive
Name (In Print):	Sonia Aube	7	Phone:	(214) 981- 9722
Signature:	5 Lehr		Date:	61712025

TCEQ-10400 (11/22) Page 3 of 3

UNANIMOUS CONSENT IN LIEU OF SPECIAL MEETING OF THE SOLE MEMBER OF LAJITAS MUNICIPAL SERVICES COMPANY LLC

March 6, 2024

The undersigned, being the sole Member of LAJITAS MUNICIPAL SERVICES COMPANY LLC (the "Company"), does hereby consent to and adopt in all respects the following resolutions and such consent shall have the same force and effect as if such action was taken at a duly called and convened special meeting:

RESOLVED, that the sole Member of the Company hereby authorizes, approves and empowers the following individual to serve as Authorized Representative of the Company, to make sign, execute, endorse and deliver in the name of and on behalf of the Company, any and all documents, including, but not limited to, written instruments, agreements, contracts, deeds, powers of attorney, transfers, assignments, obligations, certificates and other instruments of any other nature, entered into by the Company:

Sonia W. Aube

FURTHER RESOLVED, that the consent contemplated by the foregoing resolution is reasonably expected to benefit the Company, both directly and indirectly.

IN WITNESS WHEREOF, the undersigned has executed this Consent to be effective as of the day, month and year first above written.

SOLE MEMBER:

LAJITAS CAPITAL PARTNERS LLC, a Texas limited liability company

By: Warren Lajitas Interests LLC,

a Texas limited liability company,

its Managing Member

Y: Walan Managina Man

Exhibit B Plain Language Template

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Lajitas Municipal Services Company LLC (CN-603406604) operates the Lajitas Water Treatment Plant (RN-102079365) a 0.3mgd groundwater treatment EDR membrane drinking water plant. The facility is located about 500 feet south of SH-170 in Lajitas, Brewster County, Texas, 79852. Lajitas is proposing to dispose of membrane wastewater by irrigation on the Lajitas Golf Course. This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are concentrated from the Santa Elena source aquifer, and include chloride, sulfate, iron, calcium, other typical groundwater mineral, and naturally occurring radioactive material (NORM) constituents present in the source aquifer. The source water is treated by electro-dialysis reversal (EDR) membranes to produce a safe drinking water supply, and the process wastewater contains only the source water concentrates.

Exhibit C Public Involvement Plan



Public Involvement Plan Form for Permit and Registration Applications

The Public Involvement Plan is intended to provide applicants and the agency with information about how public outreach will be accomplished for certain types of applications in certain geographical areas of the state. It is intended to apply to new activities; major changes at existing plants, facilities, and processes; and to activities which are likely to have significant interest from the public. This preliminary screening is designed to identify applications that will benefit from an initial assessment of the need for enhanced public outreach.

All applicable sections of this form should be completed and submitted with the permit or registration application. For instructions on how to complete this form, see TCEQ-20960-inst.

Section 1. Preliminary Screening
New Permit or Registration Application New Activity – modification, registration, amendment, facility, etc. (see instructions)
If neither of the above boxes are checked, completion of the form is not required and does not need to be submitted.
Section 2 Secondary Severaling
Section 2. Secondary Screening
Requires public notice,
Considered to have significant public interest, and
Located within any of the following geographical locations:
 Austin Dallas Fort Worth Houston San Antonio West Texas Texas Panhandle Along the Texas/Mexico Border Other geographical locations should be decided on a case-by-case basis
If all the above boxes are not checked, a Public Involvement Plan is not necessary. Stop after Section 2 and submit the form.
Public Involvement Plan not applicable to this application. Provide brief explanation.
Past (and currently proposed) TLAP permit is for irrigation disposal of Lajitas groundwater WTP mem

Exhibit D TLAP Disposal Area Lease Agreement

WHEN RECORDED, RETURN TO:

RONALD L. HOLMES HOLMES FIRM PC 14241 North Dallas Parkway Suite 800 Dallas, Texas 75254

ACCESS, STORAGE AND DISPOSAL EASEMENT AGREEMENT

STATE OF TEXAS	§	
	§	KNOW ALL MEN BY THESE PRESENTS:
COUNTY OF BREWSTER	§	

THIS ACCESS, STORAGE AND DISPOSAL EASEMENT AGREEMENT (this "Agreement"), is made and entered into by and between LAJITAS CAPITAL PARTNERS LLC a Texas limited liability company ("Grantor"), and LAJITAS MUNICIPAL SERVICES COMPANY LLC, a Texas limited liability company ("Grantee"), as of the date last herein written.

RECITALS:

- A. Grantor is the owner of that certain real property located in the unincorporated area of Lajitas, Texas commonly known as the Lajitas Golf Resort and Spa ("<u>Lajitas</u>"), within which is located the golf course known as Black Jack's Crossing, a portion of which golf course, described in <u>Exhibit "A"</u> attached hereto, serves as a disposal area, by irrigation, of the waste water effluent from Grantee's Water Treatment Plant (the "<u>Irrigated Area</u>").
- B. Grantee has requested, and Grantor is amendable to, providing to Grantee easements for the purposes (the "Easement Purposes") of: (i) laying, repairing and replacing a transport line (the "Transport Line Easement") from Grantee's Water Treatment Plant to the Irrigated Area over, under, upon and across that portion of Grantor's lands within Lajitas as described in Exhibit "B" attached hereto (the "Transport Line Easement Area"); (ii) access upon and use of the Irrigated Area for the storage and disposal, by irrigation, of the waste water effluent from Grantee's Water Treatment Plant (the "Disposal Easement") onto the Irrigated Area; and (iii) access over and use of Grantor's lands (the "Ancillary Area") in the immediate area of the Irrigated Area and the Transport Line Easement Area reasonably necessary to effectively carry out the Easement Purposes (the "Ancillary Easement").
- NOW, THEREFORE, for and in consideration of the sum of TEN DOLLARS (\$10.00) and other good and valuable consideration paid by Grantee, the receipt and sufficiency of which are hereby acknowledged and confessed by the parties hereto, Grantor and Grantee do hereby agree as follows:
 - Grantor has GRANTED, and by these presents does hereby GRANT, unto Grantee

for the benefit of Grantee, on a non-exclusive, perpetual, and limited basis the Transport Line Easement, the Disposal Easement and the Ancillary Easement (together, the "Easements") in, over, upon, across and under, respectively, the Transport Line Easement Area, the Irrigated Area and the Ancillary Area (together, the "Easement Areas") for the Easement Purposes.

- TO HAVE AND TO HOLD the Easements unto Grantee, its successors and assigns, forever; and Grantor does hereby bind itself, and its successors and assigns, to warrant and forever defend all and singular the Easements granted herein, unto Grantee, and its successors and assigns, against every person whomsoever lawfully claiming or to claim the same or any part thereof, by, through or under Grantor, but not otherwise, but subject to all matters of public record which are and remain valid and enforceable as to the Easement Areas.
- Grantor hereby reserves and retains unto itself, its successors and assigns, the nonexclusive right to use the Easement Areas for the playing of golf and the maintenance, repair and replacement of the golf course within the Irrigated Area. In furtherance of the forgoing, Grantee shall provide to Grantor, in advance and on a routine basis, a schedule of activities to be conducted in the Easement Areas, shall coordinate those activities in advance with the General Manager of Black Jack's Crossing, and shall conduct such activities in a manner to minimize interference with the players within the Irrigated Area and the maintenance, repair and replacement of the Irrigated Area by Grantor.
- 4 Grantee shall provide to Grantor evidence of insurance, insuring Grantee against claims for personal injury and property damage, in amounts, with coverages and by issuers reasonably acceptable to Grantor, naming Grantor as additional insured by endorsement, and shall do so at least thirty (30) days prior to expiration of the current term thereof.
- 5. Grantee shall be responsible for maintaining all of Grantee's property within the Easement Areas in good working condition. To the extent any of such property is visible above ground, Grantee shall cause same to be painted or screened in a manner reasonably acceptable to Grantor.
- Grantee acknowledges that working within, on or around a golf course presents 6. certain inherent risks, such as golf balls travelling at high speeds and sometimes in errant directions not consistent with the golf course design. Grantee hereby assumes such risks when working within, on or around the Irrigated Area and hereby indemnifies, holds harmless and agrees to defend Grantor from and against any and all claims for personal injury or property damage of those employed or engaged by Grantee to perform work or services for Grantee within, on or around the Irrigated area.
- 7. This Agreement may be executed in any number of counterparts, each of which shall be an original, and all of such counterparts together shall be deemed to constitute one original agreement.

- 8. This Agreement constitutes the entire agreement between Grantor and Grantee relating to the subject matter hereof. Any oral representations or agreements made prior to or contemporaneously with this Agreement are superseded by this Agreement. Any amendment to this Agreement must be in writing and signed by Grantor and Grantee.
- 9. In the event any controversy, claim or dispute arises relating to this Agreement, then the prevailing party in any judicial proceeding concerning such controversy, claim or dispute shall be entitled, in addition to any other remedies to which it may be entitled, at law or in equity, to recover its reasonable attorneys' fees and costs of court.
- 10. This Agreement shall be governed and construed in accordance with laws of the state of Texas. All obligations of the parties hereto shall be performed in Brewster County, Texas.

DATED effective as of

GRANTOR:

LAJITAS CAPITAL PARTNERS LLC
a Texas limited liability company

Name: Sonia Aube

Its: Authorized Representative

GRANTEE:

By:

LAJITAS MUNICIPAL SERVICES COMPANY LLC

a Texas limited liability company

Name: Sonia Aube

Its: Authorized Representative

STATE OF TEXAS	
COUNTY OF DALLAS	

§ §

This instrument was acknowledged before me on the day of www., 2025, by SONIA AUBE, an authorized representative of LAJITAS CAPITAL PARTNERS LLC, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed same for the purposes therein expressed and the capacity therein stated.



Notary Public, State of Texas

KATULY INC. MAY JAM

[Print or Type Name of Notary]

My Commission Expires:

01/07/2028

STATE OF TEXAS

COUNTY OF DALLAS

This instrument was acknowledged before me on the May of May of May of Sonia Aube, an authorized representative of Lajitas Municipal Services LLC, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed same for the purposes therein expressed and the capacity therein stated.



Notary Public, State of Texas

KATWAINE MOVEAN

[Print or Type Name of Notary]

My Commission Expires:

01/07/2028

EXHIBIT "A"

IRRIGATED AREA



LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

EXHIBIT "A"

BEING a 188.44 acre (8,208,337 square feet) tract of land lying in the T.C. RR. Co. Section 37, Block 341, Abstract 5162, the T.C. RR. Co. Section 100, Block 341, Abstract 9053, same being a portion of a tract of land as described as "Exhibit A" in a deed to Lajitas Capital Partners, LLC, and recorded in volume 265, page 127, Official Public Records, Brewster County, Texas, same also being described by a drawing (_Lajitas Easement.dwg dated June 25, 2025) attached to and made part hereof and more particularly described as follows:

COMMENCING at a brass cap found in concrete for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of Big Bend National Park, the northwest corner of the T.C. RR. Co. Section 39, Block 341, Abstract 1556 and the southwest corner of the aforementioned T.C. RR. Co. Section 100;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract, N44°27'55"W a distance of 35.37 feet to a point for the **POINT OF BEGINNING** and an interior angle corner of the herein described 188.44 acre tract;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract the following thirty-four (34) courses:

S00°31'33"W a distance of 3,105.00 feet to a point;

S20°05'31"W a distance of 1,110.74 feet to a point;

S10°53'10"E a distance of 622.55 feet to a point;

S32°31'16"W a distance of 309.93 feet to a point;

N53°39'45"W a distance of 566.76 feet to a point;

S84°52'18"W a distance of 289.07 feet to a point;

N83°12'51"W a distance of 393.52 feet to a point;

N88°47'31"W a distance of 357.17 feet to a point;

N75°54'08"W a distance of 115.19 feet to a point;

N19°09'36"E a distance of 125.04 feet to a point;

N74°17'23"E a distance of 185.57 feet to a point;

N46°53'35"E a distance of 333.48 feet to a point;

Page 1 of 5 Lajitas Variable Width Easement.docx June 26, 2025 LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

N36°52'25"E a distance of 486.01 feet to a point of curvature;

Along a curve to the left having a radius of 613.81', length 344.55', delta 32°09'43" and a chord that bears N07°58'43"E a distance of 340.05 feet to a point of reverse curvature;

Along a curve to the right having a radius of 793.71', length 231.18', delta 16°41'17" and a chord that bears N19°55'00"E a distance of 230.36 feet to a point of reverse curvature;

Along a curve to the left having a radius of 2,957.09', length 454.60', delta 08°48'30" and a chord that bears N18°58'39"E a distance of 454.15 feet to a point of compound curvature;

Along a curve to the left having a radius of 771.42', length 580.20', delta 43°05'34" and a chord that bears N25°21'06"W a distance of 566.62 feet to a point of reverse curvature;

Along a curve to the right having a radius of 13,234.87', length 449.02', delta 01°56'38" and a chord that bears N37°53'11"W a distance of 448.99 feet to a point of compound curvature;

Along a curve to the right having a radius of 457.58', length 180.00', delta 22°32'16" and a chord that bears N23°26'47"W a distance of 178.84 feet to a point of compound curvature;

Along a curve to the right having a radius of 174.16', length 122.00', delta 40°08'12" and a chord that bears N11°33'05"E a distance of 119.52 feet to a point of tangency;

N31°30'40"E a distance of 720.19 feet to a point of curvature;

Along a curve to the left having a radius of 450.76', length 349.77', delta 44°27'33" and a chord that bears N14°07'43"E a distance of 341.06 feet to a point of tangency;

N14°48'12"W a distance of 258.02 feet to a point;

N16°53'51"W a distance of 428.69 feet to a point;

N35°14'13"W a distance of 1,333.96 feet to a point;

N21°52'16"W a distance of 540.03 feet to a point of curvature;

Along a curve to the right having a radius of 81.77', length 151.08', delta 105°51'27" and a chord that bears N32°16'35"E a distance of 130.49 feet to a point of compound curvature;

Along a curve to the right having a radius of 1,612.53', length 372.61', delta 13°14'22" and a chord that bears S89°36'01"E a distance of 371.78 feet to a point of compound curvature;

Page 2 of 5 Lajitas Variable Width Easement.docx June 26, 2025 LAJITAS CAPITAL PARTNERS, LLC VARIABLE WIDTH EASEMENT BREWSTER COUNTY, TEXAS 188.44 ACRE TRACT

Along a curve to the right having a radius of 2.051.03', length 1,033.12', delta 28°51'37" and a chord that bears S68°56'14"E a distance of 1,022.23 feet to a point of reverse curvature;

Along a curve to the left having a radius of 2,666.96', length 558.25', delta 11°59'35" and a chord that bears S38°32'54"E a distance of 557.23 feet to a point of compound curvature;

Along a curve to the left having a radius of 3,252.14', length 599.22', delta 10°33'25" and a chord that bears S52°20'45"E a distance of 598.37 feet to a point of compound curvature;

Along a curve to the left having a radius of 1,477.45', length 428.69', delta 16°37'28" and a chord that bears S67°22'49"E a distance of 427.18 feet to a point of tangency;

S00°58'05"W a distance of 259.52 feet to a point;

N89°27'23"W a distance of 304.09 feet to the PLACE OF BEGINNING and containing 188.44 acres (8,208,336 square feet) of land.

The bearing basis for this survey is Grid North, Texas State Plane Coordinate System, NAD 1983(2011), South Central Zone. All distances and coordinates are surface, (Grid X 1,00024 = Surface). U.S. Survey Feet.

THE STATE OF TEXAS

X

x

X KNOWN TO ALL MEN BY THESE PRESENTS:

COUNTY OF BEXAR

I, Darryl L. Zercher, a Registered Professional Land Surveyor, do hereby certify that the above field notes were prepared using information obtained by an on the ground survey made under my direction and supervision from March of 2024 thru May of 2025.

Date 27 day of June


2025 A.D.

Darryl L. Zercher

Registered Professional Land Surveyor


No. 5609 - State of Texas

Page 3 of 5 Lajitas Variable Width Easement.docx June 26, 2025



CURVE	RADIUS	LENGTH	DELTA	CHORD BEARING	CHORD LENGTH
С9	81.77'	151.08'	105'51'27"	N32*16'35"E	130.49'
C10	1,612.53	372.61	13'14'22"	S89'36'01"E	371.78'
C11	2,051.03	1,033.12	28'51'37"	S68'56'14"E	1,022.23'
C12	2,666.96	558.25'	11'59'35"	S38'32'54"E	557.23'
C13	3,252.14	599.22'	10"33"25"	S52'20'45"E	598.37'
C14	1,477.45'	428.69'	16'37'28"	S67"22"49"E	427.18'

UNE	BEARING	DISTANCE
L1	N44°27'55°W	35.37
L13	N16'53'51"W	428.69
L14	N35*14'13"W	1,333.96
L15	N21'52'16"W	540.03
L16	S00°58'05"W	259.52'
L17	N89'27'23"W	304.09'







1"=500"


DRAWN BY: DATE:

J.R.F. 06/26/2025

DRAWING NAME:

_LAJITAS EASEMENT.DWG

188.44 ACRES BREWSTER COUNTY TEXAS



Ехнівіт "В"

TRANSPORT LINE EASEMENT AREA



LAJITAS CAPITAL PARTNERS, LLC 10' WIDE PERMANENT WATERLINE EASEMENT BREWSTER COUNTY, TEXAS 0.286 OF AN ACRE TRACT

EXHIBIT "?"

BEING a 0.286 of an acre (12,454 square feet) tract of land lying in the T.C. RR. Co. Section 37, Block 341, Abstract 5162, Brewster County, Texas, same being a portion of a tract of land as described as "Exhibit A" in a deed to Lajitas Capital Partners, LLC, and recorded in volume 265, page 127, Official Public Records, Brewster County, Texas, same also being described by a drawing (121166.26_Lajitas 10' Water Easement.dwg dated June 24, 2025) attached to and made part hereof and more particularly described as follows:

COMMENCING at a brass cap found in concrete for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of Big Bend National Park, the northwest corner of the T.C. RR. Co. Section 39, Block 341, Abstract 1556 and the southwest corner of the T.C. RR. Co. Section 100, Block 341, Abstract 9053;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract, N36°45'09"W a distance of 1,556.85 feet to a point for the POINT OF BEGINNING and the most southerly southeast corner of the herein described 0.286 of an acre tract;

THENCE across the lands of the aforementioned Lajitas Capital Partners tract the following nine (9) courses:

N54°44'49"W a distance of 17.18 feet to a point;

N19°08'06"W a distance of 300.80 feet to a point;

N43°24'57"E a distance of 210.20 feet to a point;

N81°30'59"E a distance of 287.93 feet to a point;

N65°28'57"E a distance of 447.42 feet to a point;

S26°44'25"E a distance of 10.01 feet to a point, from which a brass disk found in concrete bears S55°39'25"E a distance of 3,435.94 feet for an interior angle corner of the aforementioned Lajitas Capital Partners tract, an exterior angle corner of the aforementioned Big Bend National Park, the southeast corner of the aforementioned T.C. RR. Co. Section 100, the northeast corner of the aforementioned T.C. RR. Co. Section 39, and an angle corner of the Thomas V. Skaggs Survey 92, Block 341, Abstract 9050;

S65°28'57"W a distance of 449.22 feet to a point;

S81°30'59W" a distance of 285.89 feet to a point;

S43°24'57"W a distance of 200.67 feet to a point;

Page 1 of 3 Lajitas 10' Waterline Easement.docx June 24, 2025 LAJITAS CAPITAL PARTNERS, LLC 10' WIDE PERMANENT WATERLINE EASEMENT BREWSTER COUNTY, TEXAS 0.286 OF AN ACRE TRACT

\$19°08'06"E a distance of 308.69 feet to the PLAČE OF BEGINNING and containing 0.286 of an acre (12,454 square feet) of land.

The bearing basis for this survey is Grid North, Texas State Plane Coordinate System, NAD 1983(2011), South Central Zone. All distances and coordinates are surface, (Grid X 1.00024 = Surface).

U.S. Survey Feet.

THE STATE OF TEXAS X

X KNOWN TO ALL MEN BY THESE PRESENTS:

COUNTY OF BEXAR

x

I, Darryl L. Zercher, a Registered Professional Land Surveyor, do hereby certify that the above field notes were prepared using information obtained by an on the ground survey made under my direction and supervision from March of 2024 thru May of 2025.

Date 27 day of June 2025 A.D.



Darryl L! Zercher Registered Professional Land Surveyor

No. 5609 - State of Texas




Exhibit E USGS Map





Exhibit F TLAP Disposal Area



TLAP DISPOSAL AREA



SCALE: AS NOTED DATE: JUNE 2025
DRAWN BY: CDSm REV.
TLAP PERMIT EXHIBITS.DWG EXHIBIT - F

Exhibit G Landowners' Map

LAJITAS CAPITAL PARTNERS, LLC 14241 DALLAS PARKWAY, STE 800 DALLAS, TX 75254




Exhibit H Original Photos

+








Exhibit I Facility Map




Exhibit J Flow Schematic




Exhibit K Annual Cropping Plan

8

Attach the required cropping plan that includes each of the following:

- 1) Cool and warm season plant species
 - a) Paspalum Bermuda grass
- 2) Breakdown of acreage and percent of total acreage for each crop
 - a) 53.59 acres of Paspalum Bermuda grass
- 3) Crop growing season
 - a) March November
- 4) Harvesting method/number of harvests
 - a) No harvesting, only mowing
- 5) Minimum/maximum harvest height
 - a) Mow from 1/8" to 2"
- 6) Crop yield goals
 - a) None
- 7) Soils map
 - a)
- 8) Nitrogen requirements per crop
 - a) .05 pounds of Nitrogen per acre per year.
- 9) Additional fertilizer requirements
 - a) .05 pounds of phosphorus per acre per year.
 - b) .05 pounds of potassium per acre per year.
- 10)Supplemental watering requirements
 - a) 103.49 Acer feet of water per year
- 11)Crop salt tolerances
 - a) High tolerance 5500 ppm to 10,000 ppm.
- 12) Justification for not removing existing vegetation to be irrigated
 - a) Golf Course requires grass.

Exhibit L Well and Map Information

27




Exhibit M Groundwater Technical Report



GROUNDWATER TECHNICAL REPORT

RE:

TLAP PERMIT APPLICATION, EXHIBIT M

BY:

MARK ROETZEL, P.E.

SUBJECT:

SANTA ELENA AQUIFER NEAR LAJITAS, TEXAS

DATE:

6/16/2025

Lajitas Resort obtains its groundwater supply for irrigation and potable use from the Santa Elena aquifer. The Santa Elena is an Edwards associated complex, confined aquifer with a formation top depth of about 1000ft bgl near Lajitas, and a static water level of about 70ft bgl. Total depth of the aquifer is unknown, with few wells drilled in the area, but generally believed to be about 500 to 800 feet thick. It is overlaid with about 200 ft of interbedded shale and clays (Del Rio Clay), below about 100 ff of hard limestone (Buda), below about 700 feet of interbedded limestone and shales. Santa Elena groundwater is moderately saline (about 1,4000mg/l) including elevated calcium, sulfate, iron, and low-level NORM radionuclides above the Primary Drinking Water Standard.

Geology near Lajitas is highly irregular, with volcanic intrusions penetrating to the surface. The Santa Elena is a high production aquifer in the Lajitas area, with several resort irrigation and potable supply wells located at the resort.

A minor low production, shallow brackish aquifer (Boquillas, about 6,500mg/l) is present in the area, being perched groundwater in the surficial shale and limestone. This aquifer has no know uses or outfalls.

The Driller's Log for Lajitas Irrigation Well No.1 installed in 2001 is attached.

STATE OF TEXAS WELL REPORT for Tracking #2114

Owner:

Lajitas Resort, Ltd.

WW-3

Address:

HC 70, Box 400

Grid #:

Owner Well #:

73-42-9

Terlingua, TX 79852

Latitude:

Well Location:

Lajitas Resort

Lajitas, TX 79852

Longitude:

29° 15' 41" N

103° 46' 23" W

Well County:

Brewster

Elevation:

No Data

Type of Work:

New Well

Proposed Use:

Irrigation

(Well No. 1)

Drilling Start Date: 3/8/2001

Drilling End Date: 8/1/2001

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
18	0	41
12	41	1015
7.875	1015	1040

Drilling Method:

Air Rotary

Borehole Completion:

Open Hole

Annular Seal Data:

Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
0	20	10

Seal Method: Gravity

Distance to Property Line (ft.): No Data

Sealed By: Geoprojects

Distance to Septic Field or other concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): No Data

Method of Verification: No Data

Surface Completion:

Surface Sleeve Installed

Water Level:

67 ft. below land surface on 2001-08-01

Measurement Method: Unknown

Packers:

#1 Spring Steel Basket 1004

#2 Formation 10

Type of Pump:

Submersible

Well Tests:

Pump

Yield: 400 GPM with 6 ft, drawdown after 36 hours

Water Quality:

Strata Depth (ft.)	Water Type
1020	Santa Elena

Chemical Analysis Made:

Did the driller knowingly penetrate any strata which contained injurious constituents?:

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information:

Geoprojects International, Inc.

8834 Circle Drive Austin, TX 78736

Driller Name:

Benito Hinojosa

License Number:

3127

Comments:

TWDB SWN 73-42-903

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.) Bottom (ft.) Description Interbedded Limestone and Shale, moderately hard to 0 685 hard-dry 685 795 White Limestone, hard (Buda) Interbedded Black Shale and 795 1004 Clay with Limestone stringers (Del Rio Clay) Hard Tan Limestone, hit water 1004 1040 @ 1020 (Santa Elena

Limestone)

Casing: BLANK PIPE & WELL SCREEN DATA

No

No

Dia. (in.)	New/Used	Туре	Setting From/To (ft.)	
14 New	Steel Cas	ing 0	- 41	
8 5/8 Ne	ew Steel C	asing	0 - 1015	

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157 Austin, TX 78711 (512) 334-5540 Exhibit N Soil Map and Soil Information

29° 15'33" N

103° 46' 48" W















29° 15'33' N

103° 45' 54" W

75° 15'3" N

103° 45' 54" W

39° 15'3" N

Comanche Creek

103° 46' 48" W

USDA

Natural Resources Conservation Service

0 300 600 1200 Map projection: Web Mercator Corner coordinates: WGS84

MAP LEGEND

Spoil Area	Stony Spot	Wery Stony Spot		△ Other	 Special Line Features 	Water Features	Streams and Canals	Transportation	H++ Rails Interstate Highways	US Routes	Major Roads	Local Roads	Background	Aerial Photography						
rea of Interest (AOI)	Area of Interest (AOI)	Soil Man Unit Dollaron	Soil Man Unit Lines	Soil Man Unit Points	Special Point Features	Blowout	Borrow Pit	Clay Spot	Closed Depression	Gravel Pit	Gravelly Spot	Landfill	Lava Flow	Marsh or swamp	Mine or Quarry	Miscellaneous Water	Perennial Water	Rock Outcrop	Saline Spot	
rrea of Int		sios []]	} •	Special	(0)	<u> </u>	1 30	(0	×	*:	0	×	-:	ek	0	0	Þ	+	

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at scales ranging from 1:24,000 to 1:31,700.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL: Coordinate System: Web Mercator (EPSG:3857) Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Big Bend National Park, Texas Survey Area Data: Version 29, Aug 30, 2024

Soil Survey Area: Brewster County, Texas (Main Part) Survey Area Data: Version 33, Sep 10, 2024 Your area of interest (AOI) includes more than one soil survey area. These survey areas may have been mapped at different scales, with a different land use in mind, at different times, or at different levels of detail. This may result in map unit symbols, soil properties, and interpretations that do not completely agree across soil survey area boundaries.

Severely Eroded Spot

Sandy Spot

Slide or Slip

O.A.

Sinkhole

Sodic Spot

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Mar 5, 2021—Mar 18, 2021

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
TOA	Tornillo loam, 0 to 2 percent slopes, occasionally flooded	21.9	13,6%
Subtotals for Soil Survey A	rea	21.9	13.6%
Totals for Area of Interest		161.8	100.0%

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
COC	Corazones very gravelly sandy loam, 1 to 8 percent slopes	0.7	0.4%
MDE	Mariscal-Rock outcrop complex, 10 to 30 percent slopes	20.6	12.7%
NOA	Ninepoint silty clay loam, 0 to 2 percent slopes, frequently flooded	75.2	46.5%
VCA	Vicente, Lomapelona, and Castolon soils, 0 to 1 percent slopes, occasionally flooded	43.3	26.8%
Subtotals for Soil Survey A	rea	139.8	86.4%
Totals for Area of Interest		161.8	100.0%

Brewster County, Texas (Main Part)

NOA—Ninepoint silty clay loam, 0 to 2 percent slopes, frequently flooded

Map Unit Setting

National map unit symbol: 223sn Elevation: 1,800 to 4,000 feet

Mean annual precipitation: 10 to 13 inches Mean annual air temperature: 68 to 72 degrees F

Frost-free period: 240 to 280 days

Farmland classification: Not prime farmland

Map Unit Composition

Ninepoint, frequently flooded, and similar soils: 75 percent

Minor components: 25 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ninepoint, Frequently Flooded

Setting

Landform: Alluvial flats Down-slope shape: Linear Across-slope shape: Linear

Parent material: Holocene-age fine-silty alluvium derived from

limestone and shale

Typical profile

A - 0 to 4 inches: silty clay loam Bw - 4 to 80 inches: silty clay

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.57 in/hr)
Depth to water table: More than 80 inches

Frequency of flooding: Frequent Frequency of ponding: None

Calcium carbonate, maximum content: 35 percent

Gypsum, maximum content: 2 percent

Maximum salinity: Nonsaline to slightly saline (0.0 to 4.0

mmhos/cm)

Sodium adsorption ratio, maximum: 5.0

Available water supply, 0 to 60 inches: High (about 11.3 inches)

Interpretive groups

Land capability classification (irrigated): 3e Land capability classification (nonirrigated): 7c Hydrologic Soil Group: C

Ecological site: R042AB738TX - Loamy, Hot Desert Shrub

Hydric soil rating: No

Minor Components

Riverwash

Percent of map unit: 9 percent Hydric soil rating: No

Tornillo

Percent of map unit: 9 percent

Ecological site: R042AB738TX - Loamy, Hot Desert Shrub

Hydric soil rating: No

Unnamed

Percent of map unit: 7 percent Hydric soil rating: No

Data Source Information

Soil Survey Area: Big Bend National Park, Texas Survey Area Data: Version 29, Aug 30, 2024

Soil Survey Area: Brewster County, Texas (Main Part)

Survey Area Data: Version 33, Sep 10, 2024

- a. Provide analyses of the soil in the land application area for the following constituents:
 - pH [2:1 (volume/volume) water/soil mixture];
 - electrical conductivity [2:1 (volume/volume) water/soil mixture];
 - sodium adsorption ratio (SAR-not to exceed 10) from a water saturated paste and its constituent parameters (water-soluble Na, Ca and Mg reported in mg/L);
 - total Kjeldahl nitrogen (TKN);
 - total nitrogen (organic-nitrogen + nitrate-nitrogen + ammonium-nitrogen);
 - nitrate-nitrogen (from a 1 N KCl soil extract);
 - potassium;
 - phosphorus;
 - calcium:
 - magnesium;
 - sulfur; and
 - sodium.

Analyze the nutrient parameters on a plant-available basis. Analyze phosphorus according to the Mehlich III procedure with inductively coupled plasma; potassium, calcium, magnesium, sodium, and sulfur may also be analyzed in the Mehlich III soil extract. Report plant-available phosphorus, potassium, calcium, magnesium, sodium, and sulfur on a dryweight basis in mg/kg. Report electrical conductivity in mmho/cm [same as deciSiemens/meter (dS/m)]. Report pH in standard units. When reporting the results, include all information concerning fertilizer recommendations. Provide a copy of this plan to the analytical laboratory prior to sample analysis.

NOTE: Composite or benchmark sampling techniques should be used when sampling the soils of the wastewater application area. Individual soil types, as defined by the USDA NRCS Soil Survey, should be sampled individually at zones 0-6, 6-18, and 18-30 inches. Each composite sample shall represent no more than 80 acres, with no less than 15 subsamples representing each composite sample. Each benchmark sample shall represent no more than 80 acres with at least 7 subsamples for each benchmark composite sample. Subsamples shall be composited by individual site, zone, and soil type for analysis and reporting.

NOTE; The Soil Analysis is pending. For the 53.6-Ac irrigated area this will be a composite soil sample for 0-6", a second composite soil sample for 6-18", and a third composite sample for 18-30". The subsample locations used to create the composite will be shown on a markup of the irrigated area. The TLAP Permit Application is submitted to begin the Administrative Review since the past TLAP Permit has now expired.

Exhibit O Water Balance

			Lajitas WTP	P - Process Wastewater Storage Pond Water Balance (1)	water Storage	Pond Water Ba	lance (1)		
			{3} Net	{4} Process	{5} Net Stored		{7} Monthly		
	(1)	{2} Worst	Hydrologic	Wastewater	Water	(6) Net Stored	Irrigation	{8} Net Storage	(9) Required
	Evaporation	25Yr Rainfall -	Balance -In	Input - Inches	Balance - In	Water Balance Demand (Gal)	Demand (Gal)	Difference (Gal)	MakeUp Irrigation
Month	Inches (2)	Inches (3)	[{1}-{2}]	(4)	[{4}-{3}]	(Gal) (5)	(9)	[{e}-{7}]	Groundwater
Jan	2.76	0.98	1.78	29.9	28.12	1453804	3,940,000	-2486196	2486196
Feb	4.54	1.12	3.42	29.9	26.48	1369016	3,940,000	-2570984	2570984
Mar	8.27	0.95	7.32	29.9	22.58	1167386	3,940,000	-2772614	2772614
Apr	10.53	96:0	9.57	29.9	20.33	1051061	3,940,000	-2888939	2888939
May	12.61	1.66	10.95	29.9	18.95	979715	6,560,000	-5580285	5580285
Jun	12.7	1.48	11.22	29.9	18.68	965756	6,560,000	-5594244	5594244
Inf	11.25	1.58	6.67	29.9	20.23	1045891	6,560,000	-5514109	5514109
Aug	10.99	1.53	9.46	29.9	20.44	1056748	6,560,000	-5503252	5503252
Sep	8.4	2.02	6.38	29.9	23.52	1215984	6,560,000	-5344016	5,344,016
Oct	4.97	1.45	3.52	29.9	26.38	1363846	6,560,000	-5196154	5,196,154
Nov	4.01	1.14	2.87	29.9	27.03	1397451	3,940,000	-2542549	2542549
Dec	2.85	0.0	1.95	29.9	27.95	1445015	3,940,000	-2494985	2494985
Total:	93.88	15.77	78.11	358.8	280.69	14511673	63,000,000	-48488327	48488327

Notes:

(1) The 2.4-acre pond holds 3.1MG (9.5ac-ft) of water, far in excess of the process wastewater input. An average additional groundwater flow of 110,000gpd is added to the pond for the 53.6-acre irrigated golf course watering

- (2) TWDB Climatologic Data Pan Evaporation Rate, Presideo, TX (1961 Lowest Year)
- (3) TWDB Climate of Texas, Chapter 5, Presideo, TX
- (4) 65,000gpd x 30days/month stored in 2.4 acre pond convertted to inches per month
- (5) {5}/12x[(2.4).(43,560).(7.48)](6) Monthly total irrigation water applied to 56.3-acre golf course area, averaging 175,000gpd (0.8in/week). Includes 65,000gpd of WTP process wastewatgyer blended with groundwater