

This file contains the following documents:

- 1. Summary of application (in plain language)
 - English
 - Alternative Language (Spanish)
- 2. First notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
 - English
 - Alternative Language (Spanish)
- 3. Second notice (NAPD-Notice of Preliminary Decision)
 - English
 - Alternative Language (Spanish)
- 4. Application materials
- 5. Draft permit
- 6. Technical summary or fact sheet



Este archivo contiene los siguientes documentos:

- 1. Resumen de la solicitud (en lenguaje sencillo)
 - Inglés
 - Idioma alternativo (español)
- 2. Primer aviso (NORI, Aviso de Recepción de Solicitud e Intención de Obtener un Permiso)
 - Inglés
 - Idioma alternativo (español)
- 3. Segundo aviso (NAPD, Aviso de Decisión Preliminar)
 - Inglés
 - Idioma alternativo (español)
- 4. Materiales de la solicitud
- 5. Proyecto de permiso
- 6. Resumen técnico u hoja de datos



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

SUMMARY OF APPLICATION IN PLAIN LANGUAGE FOR TPDES OR TLAP PERMIT APPLICATIONS

Summary of Application (in plain language) Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

City of Runge (CN600737357) operates the City of Runge Wastewater Treatment Plant (RN: 101917839), a treatment plant with a primary settling pond system that consists of a bar screen, facultative lagoon, effluent storage pond, and irrigation fields. The facility is located at <u>400 W. Lyons</u>, in the City of Runge, Karnes County, Texas 78151. This request is to renew the Texas Land Application Permit (TLAP). This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are expected to contain CBOD5, suspended solids, ammonia nitrogen, nitrate nitrogen, kjeldahl nitrogen, sulfate, chloride, phosphorus, E. coli, and dissolved solids. The irrigated effluent is treated by a bar screen and pumped via a wet well and lift station to a facultative lagoon for settling. The treated effluent is then conveyed to a storage pond and pumped to the irrigation field.

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

AGUAS RESIDUALES DOMÉSTICAS /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

La ciudad de Runge (CN600737357) opera la planta de tratamiento de aguas residuals de la ciudad de Runge (RN: 101917839, una planta de tratamiento con un sistema de estanque de sedimentación primario que consta de una pantalla de barras, una laguna facultativa, un estanque de alacenamiento de efluentes y campos de riego.. La instalación está ubicada en 400 W. Lyons, en la ciudad de Runge, Condado de Karnes, Texas 78151. Este solicitud es para renovar el Permiso de solicitud de tierras de Texas (TLAP). Este permiso no autorizará una descarga de contaminantes en el agua en el estado.

Se espera que las descargas de la instalación contengan CBOD5, sólidos suspendidos, nitrógeno amoniacal, nitrógeno nitrato, nitrógeno kjeldahl, sulfato, cloruro, fósforo, E. coli y sólidos disueltos. El efluente irrigado . está tratado por mediante una rejilla de barras y bombeado a través de un pozo húmedo y una estación de bombeo hacia una laguna facultativa para su sedimentación. Luego, el efluente tratado se transporta a un estanque de almacenamiento y se bombea al campo de riego.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT RENEWAL.

PERMIT NO. WQ0010266001

APPLICATION. City of Runge, P.O. Box 206, Runge, Texas 78151, has applied to the Texas Commission on Environmental Quality (TCEQ) to renew Texas Land Application Permit (TLAP) No. WQ0010266001 to authorize the disposal of treated wastewater at a volume not to exceed a daily average flow of 110,000 gallons per day via surface irrigation on 42 acres. The domestic wastewater treatment facility and disposal site is located at 301 East Cleveland Street, in the City of Runge, in Karnes County, Texas 78151. TCEQ received this application on February 14, 2025. The permit application will be available for viewing and copying at Runge City Hall, 109 North Helena Street, Runge, in Karnes County, Texas, prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceg.texas.gov/LocationMapper/?marker=-97.707777,28.881111&level=18

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. El aviso de idioma alternativo en español está disponible en https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. Notice of the Application and Preliminary Decision will be published and mailed to those who are on the countywide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.

TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at https://www14.tceq.texas.gov/epic/eComment/, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from City of Runge at the address stated above or by calling Mr. Homer Lott, Mayor at 830-239-4121.

Issuance Date: March 13, 2025

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE RECIBO DE LA SOLICITUD E INTENCION DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA RENOVACION

PERMISO NO. WQ0010266001

SOLICITUD. Ciudad de Runge, P.O. Box 206, Runge, Texas 78151, ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para renovar el Permiso No. WQ0010266001 de disposición de aguas residuales para autorizar Planta de tratamiento de aguas residuales de la ciudad de Runge la disposición de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 110,000 galones por día por medio de riego superficial en 42 acres. La planta de tratamiento de aguas domésticos residuales y el área de disposición están ubicados en 301 Este Calle Cleveland, en la ciudad de Runge en el Condado de Karnes, Texas. La TCEQ recibió esta solicitud el día 14 de febrero de 2025. La solicitud para el permiso estará disponible para leerla y copiarla en 109 Norte Calle de Helena, en la ciudad de Runge, en el condado de Karnes, Texas 78151 antes de la fecha de publicación de este aviso en el periódico. La aplicación incluidas las actualizaciones y los avisos asociados están disponibles electrónicamente en la siguiente pagina web: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación exacta, consulte la solicitud.

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications

AVISO ADICIONAL. El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. El aviso de la solicitud y la decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud. El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO.

Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro: identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

CONTACTOS E INFORMACIÓN A LA AGENCIA. Todos los comentarios públicos y solicitudes deben ser presentadas electrónicamente vía http://www14.tceq.texas.gov/epic/eComment/ o por escrito dirigidos a la Comisión de Texas de Calidad Ambiental, Oficial de la Secretaría (Office of Chief Clerk), MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Para obtener más información acerca de esta solicitud de permiso o el proceso de permisos, llame al programa de educación pública de la TCEQ, gratis, al 1-800-687-4040. Si desea información en Español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional del ciudad de Runge a la dirección indicada arriba o llamando a Alcalde, Homer Lott al 830-239-4121

Fecha de emisión 13 de marzo de 2025

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF APPLICATION AND PRELIMINARY DECISION FOR WATER QUALITY LAND APPLICATION PERMIT FOR MUNICIPAL WASTEWATER

RENEWAL

PERMIT NO. WQ0010266001

APPLICATION AND PRELIMINARY DECISION. City of Runge, P.O. Box 206, Runge, Texas 78151, has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of TCEQ Permit No. WQ0010266001 which authorizes the disposal of treated domestic wastewater at a daily average flow not to exceed 110,000 gallons per day via surface irrigation of 42 acres of non-public access agricultural land. This permit will not authorize a discharge of pollutants into water in the state. TCEQ received this application on February 14, 2025.

The wastewater treatment facility and disposal site are located at 301 East Cleveland Street, in the City of Runge, in Karnes County, Texas 78151. The wastewater treatment facility and disposal site are located in the drainage basin of Lower San Antonio River in Segment No. 1901 of the San Antonio River Basin. This link to an electronic map of the site or facility's general location is provided as a public courtesy and is not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.707777,28.881111&level=18

The TCEQ Executive Director has completed the technical review of the application and prepared a draft permit. The draft permit, if approved, would establish the conditions under which the facility must operate. The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The permit application, Executive Director's preliminary decision, and draft permit are available for viewing and copying at Runge City Hall, 109 North Helena Street, Runge, in Karnes County, Texas. The application, including any updates, and associated notices are available electronically at the following webpage: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at https://www.tceq.texas.gov/permitting/wastewater/plain-language-summaries-and-public-notices. El aviso de idioma alternativo en español está disponible en https://www.tceq.texas.gov/permitting/wastewater/plain-language-summaries-and-public-notices.

notices.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting about this application.] The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ holds a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting a contested case hearing or reconsideration of the Executive Director's decision. A contested case hearing is a legal proceeding similar to a civil trial in a state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period; and the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period. TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

EXECUTIVE DIRECTOR ACTION. The Executive Director may issue final approval of the application unless a timely contested case hearing request or request for reconsideration is filed. If a timely hearing request or request for reconsideration is filed, the Executive Director will not issue final approval of the permit and will forward the application and request to the TCEQ

Commissioners for their consideration at a scheduled Commission meeting.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

All written public comments and public meeting requests must be submitted to the Office of the Chief Clerk, MC 105, Texas Commission on Environmental Quality, P.O. Box 13087, Austin, TX 78711-3087 or electronically at www.tceq.texas.gov/goto/comment within 30 days from the date of newspaper publication of this notice.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. Public comments and requests must be submitted either electronically at www.tceq.texas.gov/goto/comment, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC 105, P.O. Box 13087, Austin, Texas 78711-3087. Any personal information you submit to the TCEQ will become part of the agency's record; this includes email addresses. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from City of Runge at the address stated above or by calling Mr. Christopher Parker, Mayor at 830-239-4121

Issuance Date: September 17, 2025

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE LA SOLICITUD Y DECISIÓN PRELIMINAR PARA EL PARA LA CALIDAD DEL AGUAS RESIDUALES MUNICIPALES

RENOVACION

PERMISO NO. WQ0010266001

SOLICITUD Y DECISIÓN PRELIMINAR. Ciudad de Runge, P.O. Box 206, Runge, Texas 78151, ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para renovar el Permiso No. WQ0010266001 de disposición de aguas residuales para autorizar Planta de tratamiento de aguas residuales de la ciudad de Runge la disposición de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 110,000 galones por día por medio de riego superficial en 42 acres. La planta de tratamiento de aguas domésticos residuales y el área de disposición están ubicados en 301 East Cleveland St., en la ciudad de Runge en el Condado de Karnes, Texas. La TCEQ recibió esta solicitud el día 14 de febrero de 2025. La solicitud para el permiso estará disponible para leerla y copiarla en 400 West Lyons, en la ciudad de Runge, en el condado de Karnes, Texas 78151 antes de la fecha de publicación de este aviso en el periódico. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.707777,28.881111&level=18

El Director Ejecutivo de la TCEQ ha completado la revisión técnica de la solicitud y ha preparado un borrador del permiso. El borrador del permiso, si es aprobado, establecería las condiciones bajo las cuales la instalación debe operar. El Director Ejecutivo ha tomado una decisión preliminar que si este permiso es emitido, cumple con todos los requisitos normativos y legales. La solicitud del permiso, la decisión preliminar del Director Ejecutivo y el borrador del permiso están disponibles para leer y copiar en Ayuntamiento de Runge, 109 North Helena Street, en la ciudad de Runge, en el condado de Karnes, Texas 78151. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

AVISO DE IDIOMA ALTERNATIVO El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. **El aviso de la solicitud y la**

decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.

COMENTARIO PUBLICO / REUNION PUBLICA. El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE **UNA AUDIENCIA ADMINISTRATIVA** DE LO **CONTENCIOSO.** Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud hava sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de **lo contencioso.** Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO. USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la

Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

ACCIÓN DEL DIRECTOR EJECUTIVO. El Director Ejecutivo puede emitir una aprobación final de la solicitud a menos que exista un pedido antes del plazo de vencimiento de una audiencia administrativa de lo contencioso o se ha presentado un pedido de reconsideración. Si un pedido ha llegado antes del plazo de vencimiento de la audiencia o el pedido de reconsideración ha sido presentado, el Director Ejecutivo no emitirá una aprobación final sobre el permiso y enviará la solicitud y el pedido a los Comisionados de la TECQ para consideración en una reunión programada de la Comisión.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

Todos los comentarios escritos del público y los pedidos una reunión deben ser presentados durante los 30 días después de la publicación del aviso a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 or por el internet a www.tceq.texas.gov/about/comments.html. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia.

CONTACTOS E INFORMACIÓN DE LA AGENCIA. Los comentarios y solicitudes públicas deben enviarse electrónicamente a https://www14.tceq.texas.gov/epic/eComment/, o por escrito a Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Cualquier información personal que envíe a al TCEQ pasará a formar parte del registro de la agencia; esto incluye las direcciones de correo electrónico. Para obtener más información sobre esta solicitud de permiso o el proceso de permisos, llame al Programa de Educación Pública de la TCEQ, sin cargo, al 1-800-687-4040 o visite su sitio web en www.tceq.texas.gov/goto/pep. Si desea información en español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional del <u>ciudad de Runge</u> a la dirección indicada arriba o llamando a <u>Alcalde, Christopher Parker</u> al <u>830-239-4121</u>

Fecha de emisión: 17 de Septiembre de 2025

THE COMMISSION OF THE PROPERTY OF THE PROPERTY

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST

Complete and submit this checklist with the application.

APPLICANT NAME: City of	<u>r Kunge</u>
DEDMIT MILLADED /If	loars blooks WOOO 10066001

PERMIT NUMBER (If new, leave blank): WQ00 <u>10266001</u>

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0	\boxtimes		Original USGS Map	\boxtimes	
Administrative Report 1.1		\boxtimes	Affected Landowners Map		\boxtimes
SPIF	[3]	\boxtimes	Landowner Disk or Labels		\boxtimes
Core Data Form	\boxtimes		Buffer Zone Map		\boxtimes
Public Involvement Plan Form		\boxtimes	Flow Diagram	\boxtimes	
Technical Report 1.0	\boxtimes		Site Drawing	\boxtimes	
Technical Report 1.1		\boxtimes	Original Photographs		\boxtimes
Worksheet 2.0		\boxtimes	Design Calculations		\boxtimes
Worksheet 2.1		\boxtimes	Solids Management Plan	23531 237 207	\boxtimes
Worksheet 3.0	\boxtimes		Water Balance		\boxtimes
Worksheet 3.1					
Worksheet 3.2		\boxtimes			
Worksheet 3.3		\boxtimes			
Worksheet 4.0		\boxtimes			
Worksheet 5.0		\boxtimes			
Worksheet 6.0	\boxtimes				
Worksheet 7.0		\boxtimes			

For TCEQ Use Only	
Segment Number	County
Expiration Date	Region
Permit Number	

STATE OF THE PROPERTY OF THE P

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

For any questions about this form, please contact the Applications Review and Processing Team at 512-239-4671.

Section 1. Application Fees (Instructions Page 26)

Indicate the amount submitted for the application fee (check only one).

Flow	New/Major Amendment	Renewal
< 0.05 MGD	\$350.00 □	\$315.00 □
≥0.05 but <0.10 MC	GD \$550.00 □	\$515.00 □
≥0.10 but <0.25 MC	GD \$850.00 □	\$815.00 ☒
≥0.25 but <0.50 MC	GD \$1,250.00 □	\$1,215.00 □
≥0.50 but <1.0 MGI	9 \$1,650.00 □	\$1,615.00 □
≥1.0 MGD	\$2,050.00 □	\$2,015.00
Minor Amendment (Payment Information	for any flow) \$150.00 🗆	
Mailed	Check/Money Order Number: <u>26617</u>	
	Check/Money Order Amount: <u>\$815.00</u>	
	Name Printed on Check: City of Runge	
EPAY	Voucher Number: <u>N/A</u>	
Copy of Paym	nent Voucher enclosed? Yes 🗆	

Section 2. Type of Application (Instructions Page 26)

a.	Che	neck the box next to the appropriate aut	horization type.
	\boxtimes	Publicly-Owned Domestic Wastewater	
		Privately-Owned Domestic Wastewate	r
		Conventional Wastewater Treatment	
b.	Che	neck the box next to the appropriate faci	lity status.
	\boxtimes	Active Inactive	

c.	Che	eck the box next to the appropriate permit typ	e.	
		TPDES Permit		
	\boxtimes	TLAP		
		TPDES Permit with TLAP component		
		Subsurface Area Drip Dispersal System (SAD	DS)	
d.	Che	eck the box next to the appropriate application	ı typ	e
		New		
		Major Amendment <u>with</u> Renewal		Minor Amendment with Renewal
		Major Amendment <u>without</u> Renewal		Minor Amendment without Renewal
	\boxtimes	Renewal without changes		Minor Modification of permit
e.	For	amendments or modifications, describe the p	ropo	osed changes: Click to enter text.
f.	For	existing permits:		
	Peri	mit Number: WQ00 <u>10266001</u>		
	EPA	I.D. (TPDES only): TX Click to enter text.		
	Exp	iration Date: March 1, 2025		
So	ctio	on 3. Facility Owner (Applicant) a	nd	Co-Applicant Information
Je	cur	(Instructions Page 26)	mu	Co-Applicant information
Α.	The	e owner of the facility must apply for the per	rmit.	
		at is the Legal Name of the entity (applicant) a		
	City	of Runge		
		e legal name must be spelled exactly as filed w legal documents forming the entity.)	ith th	he Texas Secretary of State, County, or ir
		ne applicant is currently a customer with the T n may search for your CN on the TCEQ website		
	(CN: <u>600737357</u>		
			at <u>I</u>	ittp://www15.tceq.tex

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in *30 TAC § 305.44*.

Prefix: Mr. Last Name, First Name: Lott, Homer

Title: <u>Mayor</u> Credential: Click to enter text.

B. Co-applicant information. Complete this section only if another person or entity is required to apply as a co-permittee.

What is the Legal Name of the co-applicant applying for this permit?

Click to enter text.

(The legal name must be spelled exactly as filed with the TX SOS, with the County, or in the legal documents forming the entity.)

If the co-applicant is currently a customer with the TCEQ, what is the Customer Number (CN)? You may search for your CN on the TCEQ website at: http://www15.tceq.texas.gov/crpub/

CN: Click to enter text.

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in *30 TAC § 305.44*.

Prefix: Click to enter text. Last Name, First Name: Click to enter text.

Title: Click to enter text. Credential: Click to enter text.

Provide a brief description of the need for a co-permittee: Click to enter text.

C. Core Data Form

Complete the Core Data Form for each customer and include as an attachment. If the customer type selected on the Core Data Form is **Individual**, complete **Attachment 1** of Administrative Report 1.0. Click to enter text.

Section 4. Application Contact Information (Instructions Page 27)

This is the person(s) TCEQ will contact if additional information is needed about this application. Provide a contact for administrative questions and technical questions.

A. Prefix: Mr. Last Name, First Name: Stoner, Kyle

Title: <u>Graduate Engineer</u> Credential: <u>E.I.T.</u>

Organization Name: Cope Engineering, Inc.

Mailing Address: 8611 Botts Lane City, State, Zip Code: San Antonio, TX., 78217

Phone No.: 210-828-7070 E-mail Address: kyle@copeengineeringtx.com

Check one or both: oximes Administrative Contact oximes Technical Contact

B. Prefix: Mr. Last Name, First Name: Cope, Brian

Title: <u>Vice President</u> Credential: <u>P.E.</u>

Organization Name: <u>Cope Engineering, Inc.</u>

Mailing Address: 8611 Botts Lane City, State, Zip Code: San Antonio, TX., 78217

Phone No.: <u>210-828-7070</u> E-mail Address: <u>brian@copeengineeringtx.com</u>

Check one or both:

Administrative Contact

Technical Contact

Section 5. Permit Contact Information (Instructions Page 27)

Provide the names and contact information for two individuals that can be contacted throughout the permit term.

A. Prefix: Mr. Last Name, First Name: Lott, Homer

Title: Mayor Credential: Click to enter text.

Organization Name: <u>City of Runge</u>

Mailing Address: P.O. Box 206 City, State, Zip Code: Runge, TX., 78151

Phone No.: 830-239-4121 E-mail Address: city.of.runge@sbcglobal.net

B. Prefix: Ms. Last Name, First Name: Castro, Esmeralda

Title: <u>City Secretary</u> Credential: <u>Click to enter text.</u>

Organization Name: City of Runge

Mailing Address: P.O. Box 206 City, State, Zip Code: Runge, TX. 78151

Phone No.: 830-239-4121 E-mail Address: city.of.runge@sbcglobal.net

Section 6. Billing Contact Information (Instructions Page 27)

The permittee is responsible for paying the annual fee. The annual fee will be assessed to permits *in effect on September 1 of each year*. The TCEQ will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (using form TCEQ-20029).

Prefix: Ms. Last Name, First Name: Castro, Esmeralda

Title: <u>City Secretary</u> Credential: <u>Click to enter text.</u>

Organization Name: City of Runge

Mailing Address: P.O. Box 206 City, State, Zip Code: Runge, TX., 78151

Phone No.: 830-239-4121 E-mail Address: city.of.runge@sbcglobal.net

Section 7. DMR/MER Contact Information (Instructions Page 27)

Provide the name and complete mailing address of the person delegated to receive and submit Discharge Monitoring Reports (DMR) (EPA 3320-1) or maintain Monthly Effluent Reports (MER).

Prefix: Mr. Last Name, First Name: Lott, Homer

Title: Mayor Credential: Click to enter text.

Organization Name: <u>City of Runge</u>

Mailing Address: P.O. Box 206 City, State, Zip Code: Runge, TX., 78151

Phone No.: 830-239-4121 E-mail Address: city.of.runge@sbcglobal.net

Section 8. Public Notice Information (Instructions Page 27)

A. Individual Publishing the Notices

Prefix: Mr. Last Name, First Name: Lott, Homer

Title: Mayor Credential: Click to enter text.

Organization Name: City of Runge

Mailing Address: P.O. Box 206 City, State, Zip Code: Runge, TX., 78151

Phone No.: 830-239-4121 E-mail Address: city.of.runge@sbcglobal.net

B.		thod fo	r Receiving	Noti	ce of Receipt and Intent to Obtain a Water Quality Permit	
	Inc	licate by	y a check ma	ark th	e preferred method for receiving the first notice and instructions:	
		E-mai	l Address			
		Fax				
	\boxtimes	Regul	ar Mail			
C.	Co	ntact p	ermit to be	listed	l in the Notices	
		efix: <u>Mr.</u>			Last Name, First Name: <u>Lott, Homer</u>	
	Tit	le: <u>Mayo</u>	<u>or</u>		Credential: Click to enter text.	
	Or	ganizati	ion Name: <u>C</u> i	ity of	Runge	
	Ma	iling Ac	ldress: <u>P.O. I</u>	Box 20	City, State, Zip Code: Runge, TX., 78151	
	Ph	one No.	830-239-41	21	E-mail Address: city.of.runge@sbcglobal.net	
D.	Pu	blic Vie	wing Inforn	natio	n	
			ity or outfall ist be provid		cated in more than one county, a public viewing place for each	
	Pu	blic buil	lding name:	City I	<u>Hall</u>	
	Lo	cation w	vithin the bu	ildin	g: <u>Lobby</u>	
	Ph	ysical A	ddress of Bu	ıildin	g: <u>109 N. Helena St.</u>	
	Cit	y: Rung	<u>e</u>		County: <u>Karnes</u>	
	Contact (Last Name, First Name): <u>Lott, Homer</u>					
	Ph	one No.	830-239-41	21 Ex	t.: Click to enter text.	
E.	Bilingual Notice Requirements					
	This information is required for new, major amendment, minor amendment or minor modification, and renewal applications.					
	This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.					
	Please call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine whether an alternative language notices are required.					
	1.				program required by the Texas Education Code at the elementary to the facility or proposed facility?	
		\boxtimes	Yes	(200) (20) (20)	No	
		If no , p	oublication o	of an	alternative language notice is not required; skip to Section 9	
	2.				tend either the elementary school or the middle school enrolled ir ogram at that school?	
		\boxtimes	Yes		No	

	3.	Do the locatio		these	schools attend a bilingual education program at another
			Yes	\boxtimes	No
	4.				uired to provide a bilingual education program but the school has rement under 19 TAC §89.1205(g)?
			Yes	\boxtimes	No
	5.				uestion 1, 2, 3, or 4 , public notices in an alternative language are the is required by the bilingual program? Click to enter text.
F.	Pla	in Lang	guage Summ	ary 7	Template
	Co	mplete	the Plain Laı	nguag	ge Summary (TCEQ Form 20972) and include as an attachment.
	At	tachme	nt:		
G.	Pu	blic Inv	olvement P	lan Fo	orm
	Co	mplete	the Public In	ivolve	ement Plan Form (TCEQ Form 20960) for each application for a
	ne	w perm	it or major	amen	dment to a permit and include as an attachment.
	At	tachme	nt: <u>N/A</u>		
Ca	ot-	on O	Dogulos	tod I	Entity and Daymitted Cita Information (Instructions
S e	CU	on 9.	Page 29		Entity and Permitted Site Information (Instructions
A.				regul	ated by TCEQ, provide the Regulated Entity Number (RN) issued to
			e TCEQ's Cer currently re		Registry at http://www15.tceq.texas.gov/crpub/ to determine if ed by TCEQ.
B.	Na	me of p	roject or sit	e (the	name known by the community where located):
	<u>Cit</u>	y of Run	ige Wastewate	er Trea	atment Plant
C.	Ov	vner of	treatment fa	cility	: City of Runge
	Ov	vnershij	of Facility:	\boxtimes	Public \square Private \square Both \square Federal
D.	Ov	vner of	land where t	reatn	nent facility is or will be:
	Pre	efix: Cli	ck to enter to	ext.	Last Name, First Name: <u>City of Runge</u>
	Tit	le: Clicl	k to enter te	xt.	Credential: Click to enter text.
	Or	ganizat	ion Name: <u>C</u> i	ity of l	<u>Runge</u>
	Ma	iling Ao	ddress: <u>P.O. l</u>	Box 20	City, State, Zip Code: Runge, TX., 78151
	Ph	one No.	: <u>830-239-41</u>	<u>21</u>	E-mail Address: city.of.runge@sbcglobal.net
					same person as the facility owner or co-applicant, attach a lease d easement. See instructions.
		Attach	ment: <u>N/A</u>		

Ľ.	Owner of effluent disposal site:	
	Prefix: Click to enter text.	Last Name, First Name: <u>City of Runge</u>
	Title: Click to enter text.	Credential: Click to enter text.
	Organization Name: City of Runge	
	Mailing Address: P.O. Box 206	City, State, Zip Code: Runge, TX., 78151
	Phone No.: <u>830-239-4121</u>	E-mail Address: city.of.runge@sbcglobal.net
	If the landowner is not the same agreement or deed recorded ease	person as the facility owner or co-applicant, attach a lease ement. See instructions.
	Attachment: N/A	
F.	Owner sewage sludge disposal si property owned or controlled by	te (if authorization is requested for sludge disposal on the applicant)::
	Prefix: Click to enter text.	Last Name, First Name: Click to enter text.
	Title: Click to enter text,	Credential: Click to enter text.
	Organization Name: Click to ente	er text.
	Mailing Address: Click to enter to	ext. City, State, Zip Code: Click to enter text.
	Phone No.: Click to enter text!	E-mail Address: Click to enter text:
	If the landowner is not the same agreement or deed recorded ease	person as the facility owner or co-applicant, attach a lease ement. See instructions.
	Attachment: <u>N/A</u>	
Se	ction 10. TPDES Dischar	ge Information (Instructions Page 31)
A.	Is the wastewater treatment facil	ity location in the existing permit accurate?
	🔲 Yes 🗒 No	
	If no, or a new permit application	on, please give an accurate description:
	Click to enter text.	
B.	Are the point(s) of discharge and	the discharge route(s) in the existing permit correct?
	☐ Yes ☐ No	
	If no, or a new or amendment p	ermit application, provide an accurate description of the
	point of discharge and the disch	arge route to the nearest classified segment as defined in 30
	TAC Chapter 307: Click to enter text	
	City nearest the outfall(s): <u>City of</u>	Runge
	County in which the outfalls(s) is	s/are located: <u>Karnes</u>
C.	Is or will the treated wastewater a flood control district drainage	discharge to a city, county, or state highway right-of-way, or ditch?

	If yes , indicate by a check mark if:
	☐ Authorization granted ☐ Authorization pending
	For new and amendment applications, provide copies of letters that show proof of contact and the approval letter upon receipt.
	Attachment: <u>N/A</u>
D.	For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge: Click to enter text.
Se	ction 11. TLAP Disposal Information (Instructions Page 32)
A.	For TLAPs, is the location of the effluent disposal site in the existing permit accurate?
	🛛 Yes 🖂 No
	If no, or a new or amendment permit application , provide an accurate description of the disposal site location:
	Click to enter text
n	City pages the disposal city Program Toron
	City nearest the disposal site: Runge, Texas
	County in which the disposal site is located: <u>Karnes</u> For TLAPs , describe the routing of effluent from the treatment facility to the disposal site:
D.	The treated effluent is pumped from the storage pond to the irrigation area approximately 300 feet
	south of the facility.
E.	For TLAPs , please identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained: <u>Ojo de Agua Creek</u>
Se	ection 12. Miscellaneous Information (Instructions Page 32)
	Is the facility located on or does the treated effluent cross American Indian Land?
	☐ Yes 🗵 No
В.	If the existing permit contains an onsite sludge disposal authorization, is the location of the sewage sludge disposal site in the existing permit accurate?
	Yes 🖂 No 🔯 Not Applicable
	If No, or if a new onsite sludge disposal authorization is being requested in this permit application, provide an accurate location description of the sewage sludge disposal site.
	Click to enter text,

C.	Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?
	□ Yes ☒ No
	If yes, list each person formerly employed by the TCEQ who represented your company and was paid for service regarding the application: Click to enter text.
D.	Do you owe any fees to the TCEQ?
	☐ Yes ☒ No
	If yes , provide the following information:
	Account number: Click to enter text.
	Amount past due: Click to enter text
E.	Do you owe any penalties to the TCEQ?
	□ Yes ⊠ No
	If yes , please provide the following information:
	Enforcement order number: Click to enter text
	Amount past due: Click to enter text
S€	ection 13. Attachments (Instructions Page 33)
Inc	dicate which attachments are included with the Administrative Report. Check all that apply:
	Lease agreement or deed recorded easement, if the land where the treatment facility is located or the effluent disposal site are not owned by the applicant or co-applicant.
\boxtimes	Original full-size USGS Topographic Map with the following information:
	 Applicant's property boundary Treatment facility boundary Labeled point of discharge for each discharge point (TPDES only) Highlighted discharge route for each discharge point (TPDES only) Onsite sewage sludge disposal site (if applicable) Effluent disposal site boundaries (TLAP only) New and future construction (if applicable) 1 mile radius information 3 miles downstream information (TPDES only) All ponds.
Ц	Attachment 1 for Individuals as co-applicants
	Other Attachments. Please specify: Click to enter text.

Section 14. Signature Page (Instructions Page 34)

If co-applicants are necessary, each entity must submit an original, separate signature page. Permit Number: Click to enter text. WQ 0010 266001 Applicant: City of Runge Certification: I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further certify that I am authorized under 30 Texas Administrative Code § 305.44 to sign and submit this document, and can provide documentation in proof of such authorization upon request. Signatory name (typed or printed): Homer Lott Signatory title: Mayor Subscribed and Sworn to before me by the said Mayor Homer day of <u>September</u> on this day of My commission expires on the Notary Public [SEAL] DOUGLAS WOLFE Notary Public, State of Texas

Comm. Expires 01-16-2028

Notary ID 126365618

County, Texas

DOMESTIC WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

The following information is required for new and amendment applications.

Section 1. Affected Landowner Information (Instructions Page 36)

Α.		icate by a check mark that the landowners map or drawing, with scale, includes the owing information, as applicable:
		The applicant's property boundaries
		The facility site boundaries within the applicant's property boundaries
	SATURE SATURE STATES	The distance the buffer zone falls into adjacent properties and the property boundaries of the landowners located within the buffer zone
		The property boundaries of all landowners surrounding the applicant's property (Note: if the application is a major amendment for a lignite mine, the map must include the property boundaries of all landowners adjacent to the new facility (ponds).)
		The point(s) of discharge and highlighted discharge route(s) clearly shown for one mile downstream
	CONTRACTOR OF THE PARTY OF THE	The property boundaries of the landowners located on both sides of the discharge route for one full stream mile downstream of the point of discharge
		The property boundaries of the landowners along the watercourse for a one-half mile radius from the point of discharge if the point of discharge is into a lake, bay, estuary, or affected by tides
		The boundaries of the effluent disposal site (for example, irrigation area or subsurface drainfield site) and all evaporation/holding ponds within the applicant's property
		The property boundaries of all landowners surrounding the effluent disposal site
		The boundaries of the sludge land application site (for land application of sewage sludge for beneficial use) and the property boundaries of landowners surrounding the applicant's property boundaries where the sewage sludge land application site is located
		The property boundaries of landowners within one-half mile in all directions from the applicant's property boundaries where the sewage sludge disposal site (for example, sludge surface disposal site or sludge monofill) is located
В.	0.0000	Indicate by a check mark that a separate list with the landowners' names and mailing resses cross-referenced to the landowner's map has been provided.
C.	Indi	cate by a check mark in which format the landowners list is submitted:
	Ē	☐ USB Drive ☐ Four sets of labels
D.	Prov	vide the source of the landowners' names and mailing addresses: Click to enter text.
Е.		required by $Texas\ Water\ Code\ \S\ 5.115$, is any permanent school fund land affected by application?
	<u> </u>	□ Yes □ No

	If yes , provide the location and foreseeable impacts and effects this application has on the land(s):
	Click to enter text.
Co	action 2 Original Photography (Instruction Press 20)
	ection 2. Original Photographs (Instructions Page 38)
	ovide original ground level photographs. Indicate with checkmarks that the following formation is provided.
	At least one original photograph of the new or expanded treatment unit location
	At least two photographs of the existing/proposed point of discharge and as much area downstream (photo 1) and upstream (photo 2) as can be captured. If the discharge is to an open water body (e.g., lake, bay), the point of discharge should be in the right or left edge of each photograph showing the open water and with as much area on each respective side of the discharge as can be captured.
	At least one photograph of the existing/proposed effluent disposal site
	A plot plan or map showing the location and direction of each photograph
Se	ection 3. Buffer Zone Map (Instructions Page 38)
A.	Buffer zone map. Provide a buffer zone map on 8.5×11 -inch paper with all of the following information. The applicant's property line and the buffer zone line may be distinguished by using dashes or symbols and appropriate labels.
	 The applicant's property boundary; The required buffer zone; and Each treatment unit; and The distance from each treatment unit to the property boundaries.
В.	Buffer zone compliance method. Indicate how the buffer zone requirements will be met. Check all that apply.
	Ownership
	Restrictive easement
	Nuisance odor control
	[] Variance
C.	Unsuitable site characteristics. Does the facility comply with the requirements regarding unsuitable site characteristic found in 30 TAC § 309.13(a) through (d)?
	Yes 🛱 No

DOMESTIC WASTEWATER PERMIT APPLICATION SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: Click to enter text

ATTACHMENT 1

INDIVIDUAL INFORMATION

Section 1. Individual Information (Instructions Page 41)

Complete this attachment if the facility applicant or co-applicant is an individual. Make additional copies of this attachment if both are individuals.

Prefix (Mr., Ms., Miss): Click to enter text.

Full legal name (Last Name, First Name, Middle Initial): Click to enter text.

Driver's License or State Identification Number: Click to enter text.

Date of Birth: Click to enter text.

Mailing Address: Click to enter text.

City, State, and Zip Code: Click to enter text.

Phone Number: Click to enter text. Fax Number: Click to enter text.

E-mail Address: Click to enter text

CN: Click to enter text.

For Commission Use Only:

Customer Number:

Regulated Entity Number:

Permit Number:

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST OF COMMON DEFICIENCIES

Below is a list of common deficiencies found during the administrative review of domestic wastewater permit applications. To ensure the timely processing of this application, please review the items below and indicate by checking Yes that each item is complete and in accordance applicable rules at 30 TAC Chapters 21, 281, and 305. If an item is not required this application, indicate by checking N/A where appropriate. Please do not submit the application until the items below have been addressed.

application until the fields below have been a	iddi essed.					
Core Data Form (TCEQ Form No. 10400) (Required for all application types. Must be completed in its entirety and signed. Note: Form may be signed by applicant representative.)						
Correct and Current Industrial Wastewater Po (TCEQ Form Nos. 10053 and 10054. Version of	\boxtimes	Yes				
Water Quality Permit Payment Submittal Form (Original payment sent to TCEQ Revenue Sect	⊠ dress	Yes				
7.5 Minute USGS Quadrangle Topographic Map Attached (Full-size map if seeking "New" permit. 8 ½ x 11 acceptable for Renewals and Amendments)						
Current/Non-Expired, Executed Lease Agreen		Yes				
Landowners Map (See instructions for landowner requirements)					Yes	
 Things to Know: All the items shown on the map must be labeled. The applicant's complete property boundaries must be delineated which includes boundaries of contiguous property owned by the applicant. The applicant cannot be its own adjacent landowner. You must identify the landowners immediately adjacent to their property, regardless of how far they are from the actual facility. If the applicant's property is adjacent to a road, creek, or stream, the landowners on the opposite side must be identified. Although the properties are not adjacent applicant's property boundary, they are considered potentially affected landowner If the adjacent road is a divided highway as identified on the USGS topographic map, the applicant does not have to identify the landowners on the opposite side of the highway. 						
Landowners Cross Reference List (See instructions for landowner requirements)			N/A		Yes	
Landowners Labels or USB Drive attached (See instructions for landowner requirements)					Yes	
Original signature per 30 TAC § 305.44 - Blu (If signature page is not signed by an elected a copy of signature authority/delegation lette	official or principle exec	cutiv	e officei	⊠ r,	Yes	
Plain Language Summary				\boxtimes	Yes	

ON THE PROPERTY OF THE PROPERT

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

For any questions about this form, please contact the Domestic Wastewater Permitting Team at 512-239-4671.

The following information is required for all renewal, new, and amendment applications.

Section 1. Permitted or Proposed Flows (Instructions Page 43)

A. Existing/Interim I Phase

Design Flow (MGD): <u>0.110</u>

2-Hr Peak Flow (MGD): 0.300

Estimated construction start date: Existing

Estimated waste disposal start date: Existing

B. Interim II Phase

Design Flow (MGD): N/A

2-Hr Peak Flow (MGD): N/A

Estimated construction start date: N/A

Estimated waste disposal start date: N/A

C. Final Phase

Design Flow (MGD): N/A

2-Hr Peak Flow (MGD): N/A

Estimated construction start date: N/A

Estimated waste disposal start date: N/A

D. Current Operating Phase

Provide the startup date of the facility: <u>July, 1996</u>

Section 2. Treatment Process (Instructions Page 43)

A. Current Operating Phase

Provide a detailed description of the treatment process. **Include the type of treatment plant, mode of operation, and all treatment units.** Start with the plant's head works and

finish with the point of discharge. Include all sludge processing and drying units. If more than one phase exists or is proposed, a description of each phase must be provided.

The treatment process is a primary settling pond system that consists of a bar screen, facultative lagoon, effluent storage pond, and irrigation field. Sewage effluent enters the bar screen and is pump (via a wet well and lift station) to a facultative lagoon for settling. The treated effluent is then conveyed to a storage pond and pumped to an irrigation area approximately 300 feet south of the facility for disposal by means of surface irrigation on non-public access agricultural land.

B. Treatment Units

In Table 1.0(1), provide the treatment unit type, the number of units, and dimensions (length, width, depth) of each treatment unit, accounting for all phases of operation.

Table 1.0(1) - Treatment Units

Treatment Unit Type	Number of Units	Dimensions (L x W x D)		
Facultative Pond (Existing)	1	363'Lx121'Wx8'd & 12'd		
Storage Pond (Existing)	1	537'Lx179'Wx6'd		
Irrigation Area (Existing)	1	42 Acres		

C. Process Flow Diagram

Provide flow diagrams for the existing facilities and **each** proposed phase of construction.

Attachment: No. 4

Site Information and Drawing (Instructions Page 44) Section 3.

Provide the TPDES discharge outfall latitude and longitude. Enter N/A if not applicable.

Latitude: N/A

Longitude: N/A

Provide the TLAP disposal site latitude and longitude. Enter N/A if not applicable.

Latitude: 28d52'32"N

Longitude: 97d42'15"W

Provide a site drawing for the facility that shows the following:

- The boundaries of the treatment facility;
- The boundaries of the area served by the treatment facility;
- If land disposal of effluent, the boundaries of the disposal site and all storage/holding ponds; and
- If sludge disposal is authorized in the permit, the boundaries of the land application or disposal site.

Attachment: No. 5

The treatment facility serves to commercial development.	the City of Runge, a +	-/- 760 acre area composed	of residential and					
Collection System Information for wastewater TPDES permits only: Provide information for each uniquely owned collection system, existing and new, served by this facility, including satellite collection systems. Please see the instructions for a detailed explanation and examples.								
Collection System Informatio								
Collection System Name	Owner Name	Owner Type	Population Serve					
		Choose an item.						
		Choose an item.						
		Choose an item.						
		Choose an item.						
If yes, provide a detailed di Failure to provide sufficier recommending denial of the	nt justification may	y result in the Executive	the unbuilt phase. e Directo r					
The permit allows for a design o.065 MGD. However, the exadditional expansion is needed	n flow not to exceed o	D.11 MGD. The facility is cugned for maximum capacit						
Section 5. Closure I	Plans (Instructi	ions Page 45)						
Have any treatment units be out of service in the next fix		rvice permanently, or wi	ll any units be taken					

II y	es, was a closure plan submitted to the TCEQ?
	☐ Yes ☐ No
If y	ves, provide a brief description of the closure and the date of plan approval.
	ction 6. Permit Specific Requirements (Instructions Page 45)
For	applicants with an existing permit, check the Other Requirements or Special ovisions of the permit.
A.	Summary transmittal
	Have plans and specifications been approved for the existing facilities and each proposed phase? Yes No
	If yes, provide the date(s) of approval for each phase: 10/05/99
	Provide information, including dates, on any actions taken to meet a <i>requirement or provision</i> pertaining to the submission of a summary transmittal letter. Provide a copy of an approval letter from the TCEQ, if applicable.
	Click to enter text.
B.	Buffer zones
	Have the buffer zone requirements been met?
	⊠ Yes □ No
	Provide information below, including dates, on any actions taken to meet the conditions of the buffer zone. If available, provide any new documentation relevant to maintaining the buffer zones.
	The required buffer zones of 150' around all wastewater treatment plant structures and 500' around the facultative lagoon are maintained within the property boundaries or land owned by the City of Runge.

C. Other actions required by the current permit Does the Other Requirements or Special Provisions section in the existing permit require submission of any other information or other required actions? Examples include Notification of Completion, progress reports, soil monitoring data, etc. Yes 🏻 \boxtimes If yes, provide information below on the status of any actions taken to meet the conditions of an Other Requirement or Special Provision. -facility is maintained and operated by a City employee holding a Category D license. -flow meters are used to monitor effluent flow and quality five times a week. -irrigation site is monitored and maintained by the City of Runge for ponding or contamination. -a meter is used to monitor volume of effluent applied for irrigation. -analysis of representative soil sample from disposal site is taken annually. -a right of way easement agreement with owner(s) of irrigation site is executed. D. Grit and grease treatment 1. Acceptance of grit and grease waste Does the facility have a grit and/or grease processing facility onsite that treats and decants or accepts transported loads of grit and grease waste that are discharged directly to the wastewater treatment plant prior to any treatment? X Yes No If No, stop here and continue with Subsection E. Stormwater Management. 2. Grit and grease processing Describe below how the grit and grease waste is treated at the facility. In your description, include how and where the grit and grease is introduced to the treatment works and how it is separated or processed. Provide a flow diagram showing how grit and grease is processed at the facility. Click to enter text. 3. Grit disposal Does the facility have a Municipal Solid Waste (MSW) registration or permit for grit disposal?

If No, contact the TCEQ Municipal Solid Waste team at 512-239-2335. Note: A registration or permit is required for grit disposal. Grit shall not be combined with treatment plant sludge. See the instruction booklet for additional information on grit disposal requirements and restrictions.

Yes 🗓 No

	Describe the method of grit disposal.
	Click to enter text.
4.	Grease and decanted liquid disposal
	Note: A registration or permit is required for grease disposal. Grease shall not be combined with treatment plant sludge. For more information, contact the TCEQ Municipal Solid Waste team at 512-239-2335.
	Describe how the decant and grease are treated and disposed of after grit separation.
	Click to enter text.
Sto	ormwater management
1.	Applicability
	Does the facility have a design flow of 1.0 MGD or greater in any phase?
	□ Yes ⊠ No
	Does the facility have an approved pretreatment program, under 40 CFR Part 403?
	🛱 Yes 🕱 No
	If no to both of the above, then skip to Subsection F, Other Wastes Received.
2.	MSGP coverage
	Is the stormwater runoff from the WWTP and dedicated lands for sewage disposal currently permitted under the TPDES Multi-Sector General Permit (MSGP), TXR050000?
	Yes C No
	If yes, please provide MSGP Authorization Number and skip to Subsection F, Other Wastes Received:
	TXR05 Click to enter text, or TXRNE Click to enter text,
	If no, do you intend to seek coverage under TXR050000?
	T Yes T No
3.	Conditional exclusion
	Alternatively, do you intend to apply for a conditional exclusion from permitting based TXR050000 (Multi Sector General Permit) Part II B.2 or TXR050000 (Multi Sector General Permit) Part V, Sector T 3(b)?
	🖺 Yes 🗒 No

E.

	If yes, please explain below then proceed to Subsection F, Other Wastes Received:
	Click to enter text.
4.	Existing coverage in individual permit
	Is your stormwater discharge currently permitted through this individual TPDES or TLAP permit?
	🗖 Yes 🗖 No
	If yes, provide a description of stormwater runoff management practices at the site that are authorized in the wastewater permit then skip to Subsection F, Other Wastes Received.
	Click to enter text.
5 .	Zero stormwater discharge
	Do you intend to have no discharge of stormwater via use of evaporation or other means?
	🖺 Yes 🗒 No
	If yes, explain below then skip to Subsection F. Other Wastes Received.
	Click to enter text;
	Note: If there is a potential to discharge any stormwater to surface water in the state as the result of any storm event, then permit coverage is required under the MSGP or an individual discharge permit. This requirement applies to all areas of facilities with treatment plants or systems that treat, store, recycle, or reclaim domestic sewage, wastewater or sewage sludge (including dedicated lands for sewage sludge disposal located within the onsite property boundaries) that meet the applicability criteria of above. You have the option of obtaining coverage under the MSGP for direct discharges, (recommended), or obtaining coverage under this individual permit.
<i>6.</i>	Request for coverage in individual permit
	Are you requesting coverage of stormwater discharges associated with your treatment plant under this individual permit?
	☐ Yes ☐ No
	If yes, provide a description of stormwater runoff management practices at the site for which you are requesting authorization in this individual wastewater permit and describe whether you intend to comingle this discharge with your treated effluent or discharge it via a separate dedicated stormwater outfall. Please also indicate if you

		intend to divert stormwater to the treatment plant headworks and indirectly discharge it to water in the state.
		Click to enter text.
		Note: Direct stormwater discharges to waters in the state authorized through this individual permit will require the development and implementation of a stormwater pollution prevention plan (SWPPP) and will be subject to additional monitoring and reporting requirements. Indirect discharges of stormwater via headworks recycling will require compliance with all individual permit requirements including 2-hour peak flow limitations. All stormwater discharge authorization requests will require additional information during the technical review of your application.
F.	Di	scharges to the Lake Houston Watershed
	Do	es the facility discharge in the Lake Houston watershed?
		☐ Yes ☒ No
	E response, e	yes, attach a Sewage Sludge Solids Management Plan. See Example 5 in the instructions.
G.	Ot	her wastes received including sludge from other WWTPs and septic waste
	1.	Acceptance of sludge from other WWTPs
		Does or will the facility accept sludge from other treatment plants at the facility site?
		☐ Yes ☒ No
		If yes, attach sewage sludge solids management plan. See Example 5 of instructions.
		In addition, provide the date the plant started or is anticipated to start accepting sludge, an estimate of monthly sludge acceptance (gallons or millions of gallons), an
		estimate of the BOD ₅ concentration of the sludge, and the design BOD ₅ concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.
		Click to enter text.
		Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.
	2.	Acceptance of septic waste
		Is the facility accepting or will it accept septic waste?
		☐ Yes ☑ No
		If yes, does the facility have a Type V processing unit?
		🗖 Yes 🗏 No
		If yes, does the unit have a Municipal Solid Waste permit?
		Yes No

accepting septic waste, an estimate of monthly septic waste acceptance (gallons or millions of gallons), an estimate of the BOD ₅ concentration of the septic waste, and the
design BOD_5 concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.
Click to enter text.
Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.
3. Acceptance of other wastes (not including septic, grease, grit, or RCRA, CERCLA or as discharged by IUs listed in Worksheet 6)
Is or will the facility accept wastes that are not domestic in nature excluding the categories listed above?
□ Yes ⊠ No
If yes, provide the date that the plant started accepting the waste, an estimate how much waste is accepted on a monthly basis (gallons or millions of gallons), a description of the entities generating the waste, and any distinguishing chemical or other physical characteristic of the waste. Also note if this information has or has not changed since the last permit action.
Click to enter text.
Section 7. Pollutant Analysis of Treated Effluent (Instructions Page 50)
Is the facility in operation?
⊠ Yes □ No
If no, this section is not applicable. Proceed to Section 8.
If yes, provide effluent analysis data for the listed pollutants. <i>Wastewater treatment facilities</i> complete Table 1.0(2). <i>Water treatment facilities</i> discharging filter backwash water.

If yes to any of the above, provide the date the plant started or is anticipated to start

Note: The sample date must be within 1 year of application submission.

complete Table 1.0(3). Provide copies of the laboratory results sheets. **These tables are not applicable for a minor amendment without renewal.** See the instructions for guidance.

Table 1.0(2) - Pollutant Analysis for Wastewater Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
CBOD ₅ , mg/l		14.8	1	Grab	1/14/25
Total Suspended Solids, mg/l		39	1	Grab	1/14/25
Ammonia Nitrogen, mg/l		3.36	1	Grab	1/14/25
Nitrate Nitrogen, mg/l		0.989	1	Grab	1/14/25
Total Kjeldahl Nitrogen, mg/l		4.48	1	Grab	1/14/25
Sulfate, mg/l		43.4	1	Grab	1/14/25
Chloride, mg/l		276	1	Grab	1/14/25
Total Phosphorus, mg/l		1.58	1	Grab	1/14/25
pH, standard units		7.8	1	Grab	1/14/25
Dissolved Oxygen*, mg/l			N/A		
Chlorine Residual, mg/l		<0.1	1	Grab	1/14/25
<i>E.coli</i> (CFU/100ml) freshwater		770	1	Grab	1/14/25
Entercocci (CFU/100ml) saltwater		,	N/A		
Total Dissolved Solids, mg/l		856	1	Grab	1/14/25
Electrical Conductivity, µmohs/cm, †		1550	1	Grab	1/14/25
Oil & Grease, mg/l			N/A		
Alkalinity (CaCO ₃)*, mg/l			N/A		

^{*}TPDES permits only †TLAP permits only

Table 1.0(3) - Pollutant Analysis for Water Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Total Suspended Solids, mg/l					
Total Dissolved Solids, mg/l					
pH, standard units					
Fluoride, mg/l					
Aluminum, mg/l					
Alkalinity (CaCO ₃), mg/l					

Section 8. Facility Operator (Instructions Page 50)

Facility Operator Name: Jesse Sandoval

Facility Operator's License Classification and Level: Waste Water Treatment Class D Operator

Facility Operator's License Number: WW0052079

Section 9. Sludge and Biosolids Management and Disposal (Instructions Page 51)

A.	ww	TP's Biosolids Management Facility Type
	Che	ck all that apply. See instructions for guidance
		Design flow>= 1 MGD
		Serves >= 10,000 people
		Class I Sludge Management Facility (per 40 CFR § 503.9)
		Biosolids generator
		Biosolids end user – land application (onsite)
		Biosolids end user – surface disposal (onsite)
	AND THE PERSON NAMED IN	Biosolids end user – incinerator (onsite)
B.	ww	TP's Biosolids Treatment Process
	Che	ck all that apply. See instructions for guidance.
		Aerobic Digestion
		Air Drying (or sludge drying beds)
		Lower Temperature Composting
		Lime Stabilization
		Higher Temperature Composting
		Heat Drying
		Thermophilic Aerobic Digestion
		Beta Ray Irradiation
	The state of the s	Gamma Ray Irradiation
	MANUE MANUE	Pasteurization
		Preliminary Operation (e.g. grinding, de-gritting, blending)
		Thickening (e.g. gravity thickening, centrifugation, filter press, vacuum filter)
		Sludge Lagoon
		Temporary Storage (< 2 years)
		Long Term Storage (>= 2 years)
	50000 50000 50000	Methane or Biogas Recovery
	⊠ facu	Other Treatment Process: <u>The City of Runge does not produce enough sludge from the ltative pond to haul off at this time.</u>

C. Biosolids Management

Provide information on the *intended* biosolids management practice. Do not enter every management practice that you want authorized in the permit, as the permit will authorize

all biosolids management practices listed in the instructions. Rather indicate the management practice the facility plans to use.

Biosolids Management

Management Practice	Handler or Preparer Type	Bulk or Bag Container	Amount (dry metric tons)	Pathogen Reduction Options	Vector Attraction Reduction Option
Choose an item.	Choose an item.	Choose an item.		Choose an item.	Choose an item.
Choose an item.	Choose an item.	Choose an item.		Choose an item.	Choose an item.
Choose an item.	Choose an item.	Choose an item.		Choose an item.	Choose an item.

If "Other" is selected for Management Practice, please explain (e.g. monofill or transport to another WWTP): The City of Runge does not produce enough sludge from the facultative pond to haul off at this time.

D. Disposal site

Disposal site name: <u>Cl</u>	ick to enter text.
-------------------------------	--------------------

TCEQ permit or registration number: <u>Click to enter text</u>.

County where disposal site is located: Click to enter text.

E. Transportation method

Method of transportation	n (truck, tra	in, pipe, oth	er): Clicl	k to enter text.
--------------------------	---------------	---------------	------------	------------------

Name of the hauler: Click to enter text.

Hauler registration number: Click to enter text.

Sludge is transported as a:

mquag com nquag com conag cona;	Liquid 🗒	semi-liquid 🗒	semi-solid 🗒	solid 🗒
---------------------------------	----------	---------------	--------------	---------

Section 10. Permit Authorization for Sewage Sludge Disposal (Instructions Page 53)

A. Beneficial use authorization

Does the existing permit include authorization for land application of sewage sludge for beneficial use?

Yes 🛛 No

If yes, are you requesting to continue this authorization to land apply sewage sludge for beneficial use?

☐ Yes ☐ No

If yes, is the completed Application for Permit for Beneficial Land Use of Sewage Sludge (TCEQ Form No. 10451) attached to this permit application (see the instructions for details)?

THE REAL PROPERTY.	Yes □ No					
B. Sludge	processing authorization					
	he existing permit include authorization fo e or disposal options?	r an	y of the	follow	ving sludge processing,	
Slu	dge Composting		Yes	\boxtimes	No	
Ma	rketing and Distribution of sludge		Yes		No	
Slu	dge Surface Disposal or Sludge Monofill		Yes		No	
Ter	mporary storage in sludge lagoons		Yes	\boxtimes	No	
author	to any of the above sludge options and the rization, is the completed Domestic Waster ical Report (TCEQ Form No. 10056) attach	vate	r Permi	t Appl	ication: Sewage Sludge	
Section	11. Sewage Sludge Lagoons (Ins	tru	ctions	Page	e 53)	
Does this	facility include sewage sludge lagoons?					
⊠ Ye	es 🗆 No					
If yes, con	nplete the remainder of this section. If no,	proc	eed to S	Section	12.	
A. Location	on information					
	llowing maps are required to be submitted e the Attachment Number.	as p	oart of t	he app	lication. For each map,	
•	 Original General Highway (County) Map: 					
	Attachment: No. 6					
•	USDA Natural Resources Conservation Ser	vice	Soil Ma _l) :		
	Attachment: No. 7					
•	Federal Emergency Management Map:					
	Attachment: No. 8					
•	Site map:					
	Attachment: No. 9					
Discus apply.	ss in a description if any of the following ex	cist v	vithin tl	ne lago	oon area. Check all that	
	Overlap a designated 100-year frequency	floo	d plain			
	Soils with flooding classification					
	Overlap an unstable area					
A COUNTY	Wetlands					
Section 1	Located less than 60 meters from a fault					
\boxtimes	None of the above					
Att	achment: Click to enter text.					

Click to enter text.
Temporary storage information
Provide the results for the pollutant screening of sludge lagoons. These results are in addition to pollutant results in $Section\ 7$ of $Technical\ Report\ 1.0$.
Nitrate Nitrogen, mg/kg: Click to enter text.
Total Kjeldahl Nitrogen, mg/kg: <u>Click to enter text</u> .
Total Nitrogen (=nitrate nitrogen + TKN), mg/kg: Click to enter text.
Phosphorus, mg/kg: <u>Click to enter text</u> .
Potassium, mg/kg: Click to enter text
pH, standard units: <u>Click to enter text</u>
Ammonia Nitrogen mg/kg: Click to enter text.
Arsenic: Click to enter text.
Cadmium: Click to enter text.
Chromium: Click to enter text.
Copper: Click to enter text.
Lead: Click to enter text
Mercury: Click to enter text
Molybdenum: Click to enter text.
Nickel: Click to enter text.
Selenium: <u>Click to enter text.</u>
Zinc: Click to enter text.
Total PCBs: <u>Click to enter text</u> .
Provide the following information:
Volume and frequency of sludge to the lagoon(s): Click to enter text.
Total dry tons stored in the lagoons(s) per 365-day period: Click to enter text.
Total dry tons stored in the lagoons(s) over the life of the unit: Click to enter text.
Liner information
Does the active/proposed sludge lagoon(s) have a liner with a maximum hydraulic conductivity of 1x10 ⁻⁷ cm/sec?
☐ Yes ☐ No

	If yes	s, describe the liner below. Please note that a liner is required.
	Clicl	to enter text.
D.	Site d	evelopment plan
	Provi	de a detailed description of the methods used to deposit sludge in the lagoon(s):
	Click	to enter text.
	Attac	h the following documents to the application.
	•	Plan view and cross-section of the sludge lagoon(s)
		Attachment: Click to enter text.
	•	Copy of the closure plan
		Attachment: Click to enter text.
	•	Copy of deed recordation for the site
		Attachment: Click to enter text,
	•	Size of the sludge lagoon(s) in surface acres and capacity in cubic feet and gallons
		Attachment: Click to enter text
	•	Description of the method of controlling infiltration of groundwater and surface water from entering the site
		Attachment: Click to enter text.
	•	Procedures to prevent the occurrence of nuisance conditions
		Attachment: Click to enter text.
E.	Grou	ndwater monitoring
	groun	undwater monitoring currently conducted at this site, or are any wells available for idwater monitoring, or are groundwater monitoring data otherwise available for the e lagoon(s)?
		Yes ⊠ No
		undwater monitoring data are available, provide a copy. Provide a profile of soil encountered down to the groundwater table and the depth to the shallowest

groundwater as a separate attachment.

Attachment: Click to enter text.

Section 12. Authorizations/Compliance/Enforcement (Instructions Page 55)

Α.	Additional authorizations
	Does the permittee have additional authorizations for this facility, such as reuse authorization, sludge permit, etc?
	□ Yes ⊠ No
	If yes, provide the TCEQ authorization number and description of the authorization:
C	lick to enter text.
В.	Permittee enforcement status
	Is the permittee currently under enforcement for this facility?
	🖺 Yes 🛭 No
	Is the permittee required to meet an implementation schedule for compliance or enforcement?
	□ Yes ⊠ No
	If yes to either question, provide a brief summary of the enforcement, the implementation schedule, and the current status:
C	lick to enter text.
Ca	ection 12 DCDA/CEDCIA Wester (Instructions Dags EE)
<u> 26</u>	ection 13. RCRA/CERCLA Wastes (Instructions Page 55)
A.	RCRA hazardous wastes Has the facility received in the past three years, does it currently receive, or will it receive RCRA hazardous waste? Yes No

B. Remediation activity wastewater

Has the facility received in the past three years, does it currently receive, or will it receive CERCLA wastewater, RCRA remediation/corrective action wastewater or other remediation activity wastewater?

□ Yes ⊠ No

C. Details about wastes received

If yes to either Subsection A or B above, provide detailed information concerning these wastes with the application.

Attachment: N/A

Section 14. Laboratory Accreditation (Instructions Page 56)

All laboratory tests performed must meet the requirements of *30 TAC Chapter 25*, *Environmental Testing Laboratory Accreditation and Certification*, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - o periodically inspected by the TCEQ; or
 - o located in another state and is accredited or inspected by that state; or
 - o performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the Signature Page section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: Homer Lott

Title: Mayor

Signature:

Date:

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND DISPOSAL OF EFFLUENT

The following is required for renewal, new, and amendment permit applications.

Section 1. Type of Disposal System (Instructions Page 68)

Identif	ly the method of land disposal:		
\boxtimes	Surface application	口	Subsurface application
	Irrigation	Ц	Subsurface soils absorption
	Drip irrigation system	Ц	Subsurface area drip dispersal system
	Evaporation		Evapotranspiration beds
	Other (describe in detail): Click	to er	iter text.
	All applicants without authoriza complete and submit Worksheet		or proposing new/amended subsurface disposal
_			-K WY T

For existing authorizations, provide Registration Number: N/A

Section 2. Land Application Site(s) (Instructions Page 68)

In table 3.0(1), provide the requested information for the land application sites. Include the agricultural or cover crop type (wheat, cotton, alfalfa, bermuda grass, native grasses, etc.), land use (golf course, hayland, pastureland, park, row crop, etc.), irrigation area, amount of effluent applied, and whether or not the public has access to the area. Specify the amount of land area and the amount of effluent that will be allotted to each agricultural or cover crop, if more than one crop will be used.

Table 3.0(1) - Land Application Site Crops

Crop Type & Land Use	Irrigation Area (acres)	Effluent Application (GPD)	Public Access? Y/N
Agricultural Land – Bermuda grass	42	65,000	N
			9

Section 3. Storage and Evaporation Lagoons/Ponds (Instructions Page 68)

Table 3.0(2) - Storage and Evaporation Ponds

Pond Number	Surface Area (acres)	Storage Volume (acre-feet)	Dimensions	Liner Type
1	2.21	11.8	6'dx179'Wx537'L	Clay (compacted)
Name have				
-				

		·····		
	f a liner certifica sional engineer f		ared, signed, and seale	d by a Texas
Attachment				
Section 4.	Flood and R	unoff Protectio	on (Instructions P	age 68)
Is the land appl	ication site <u>withi</u>	n the 100-year freq	uency flood level?	
🛛 Yes 🗀	No			
If yes, describe	how the site will	be protected from	inundation.	
	rea is not irrigated e tributary of Ojo d		A portion of the irrigation	on area is in the
Provide the sou	rce used to dete	mine the 100-year	frequency flood level:	
NFIP FIMA Firm	n Map No. 48255(Co300C and Map No.	48255C0425C, Effective	e October 19, 2010
	0 .7		6-11 ava a a	3.0 .3 1 1

Provide a description of tailwater controls and rainfall run-on controls used for the land application site.

 Λ berm is constructed along the irrigation boundary area to prevent any run on from Ojo de Aqua Creek.

Section 5. Annual Cropping Plan (Instructions Page 68)

Attach an Annual Cropping Plan which includes a discussion of each of the following items. If not applicable, provide a detailed explanation indicating why. **Attachment**: No. 10

- Soils map with crops
- Cool and warm season plant species
- Crop yield goals
- Crop growing season
- Crop nutrient requirements
- Additional fertilizer requirements
- Minimum/maximum harvest height (for grass crops)
- · Supplemental watering requirements
- Crop salt tolerances
- Harvesting method/number of harvests
- Justification for not removing existing vegetation to be irrigated

Section 6. Well and Map Information (Instructions Page 69)

Attach a USGS map with the following information shown and labeled. If not applicable, provide a detailed explanation indicating why. **Attachment:** No. 11

- The boundaries of the land application site(s)
- Waste disposal or treatment facility site(s)
- On-site buildings
- Buffer zones
- Effluent storage and tailwater control facilities
- All water wells within 1-mile radius of the disposal site or property boundaries
- All springs and seeps onsite and within 500 feet of the property boundaries
- All surface waters in the state onsite and within 500 feet of the property boundaries
- All faults and sinkholes onsite and within 500 feet of the property

List and cross reference all water wells located within a half-mile radius of the disposal site or property boundaries shown on the USGS map in the following table. Attach additional pages as necessary to include all of the wells.

Table 3.0(3) - Water Weil Data

Well ID	Well Use	Producing? Y/N	Open, cased, capped, or plugged?	Proposed Best Management Practice
7903704	Public	Y	Open	Outside buffer
7903705	Public	N	Plugged	Outside buffer
7903707	Public	Y	Cased	Outside buffer
7903708	Public	Y	Cased	Outside buffer
7911204	Private	Y	Open	Outside buffer

If water quality data or well log information is available please include the information in an attachment listed by Well ID.

Attachment: No. 12

Section 7. Groundwater Quality (Instructions Page 69)

Attach a Groundwater Quality Technical Report which assesses the impact of the wastewater disposal system on groundwater. This report shall include an evaluation of the water wells (including the information in the well table provided in Item 6. above), the wastewater application rate, and pond liners. Indicate by a check mark that this report is provided.

Attachment: No. 13

Are groundwater m	onite	oring v	wells av	ailable on	isite?		Yes	\boxtimes	No	
Do you plan to inst				nonitoring	g wells	or	lysimete	ers aro	und ti	he land
application site?		Yes	X	No						

If yes, provide the proposed location of the monitoring wells or lysimeters on a site map.

Attachment: N/A

Section 8. Soil Map and Soil Analyses (Instructions Page 70)

A. Soil map

Attach a USDA Soil Survey map that shows the area to be used for effluent disposal.

Attachment: No. 14

B. Soil analyses

Attach the laboratory results sheets from the soil analyses. **Note**: for renewal applications, the current annual soil analyses required by the permit are acceptable as long as the test date is less than one year prior to the submission of the application.

Attachment: No. 15

List all USDA designated soil series on the proposed land application site. Attach additional pages as necessary.

Table 3.0(4) - Soil Data

Soil Series	Depth from Surface	Permeability	Available Water Capacity	Curve Number
Schattel Clay Shc	0-80"	Slow	low	71
Coy Clay Loam	0-80"	Very slow	high	71
Pernitas Sandy Clay Loam	0-80"	Moderate	moderate	58
Weesatche Fine Sandy Loam	0-80"	Moderate	high	58
Colibro Sandy Clay Loam	0-80"	High	moderate	30
,				

Section 9. Effluent Monitoring Data (Instructions Page 71)

Is the facility in operation?

⊠ Yes □ No

If no, this section is not applicable and the worksheet is complete.

If yes, provide the effluent monitoring data for the parameters regulated in the existing permit. If a parameter is not regulated in the existing permit, enter N/A.

Table 3.0(5) - Effluent Monitoring Data

Date	30 Day Avg Flow MGD	BOD5 mg/l	TSS mg/l	pН	Chlorine Residual mg/l	Acres irrigated
June 2022	.0061	24	N/A	8.9	N/A	42
July 2022	.0261	19	N/A	9.0	N/A	42
Aug. 2022	.0218	19	N/A	8.4	N/A	42
Sept. 2022	.0385	38	N/A	7.3	N/A	42
Oct. 2022	.0192	25	N/A	8.8	N/A	42
Nov. 2022	.0351	53	N/A	8.8	N/A	42
Dec. 2022	.0366	76	N/A	8.6	N/A	42
Feb. 2023	.0399	96	N/A	6.8	N/A	42
April 2023	.0649	15	N/A	9.3	N/A	42
May 2023	.0752	21	N/A	9.8	N/A	42
July 2023	.0392	15	N/A	8.3	N/A	42
Aug. 2023	.0437	20	N/A	8.2	N/A	42
Oct. 2023	.0316	35	N/A	8.8	N/A	42
Nov. 2023	.0162	24	N/A	8.7	N/A	42
Dec. 2023	.0494	44	N/A	8.3	N/A	42
Jan. 2024	.0475	25	N/A	8.8	N/A	42
Feb. 2024	.0479	17	N/A	8.9	N/A	42
Mar. 2024	.0409	21	N/A	9.0	N/A	42
April 2024	.0522	21	N/A	9.1	N/A	42
May 2024	.0470	12	N/A	8.6	N/A	42
June 2024	.0422	13	N/A	8.1	N/A	42
July 2024	.0343	13	N/A	8.5	N/A	42
Aug. 2024	.0312	20	N/A	9.0	N/A	42
Oct. 2024	.0000	18	N/A	9.0	N/A	42

lick to enter text.		, , , , , , , , , , , , , , , , , , ,	

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 6.0: INDUSTRIAL WASTE CONTRIBUTION

The following is required for all publicly owned treatment works.

Section 1. All POTWs (Instructions Page 89)

A. Industrial users (IUs)

Provide the number of each of the following types of industrial users (IUs) that discharge to your POTW and the daily flows from each user. See the Instructions for definitions of Categorical IUs, Significant IUs – non-categorical, and Other IUs.

If there are no users, enter 0 (zero).

Categorical IUs:

Number of IUs: o (zero)

Average Daily Flows, in MGD: o (zero)

Significant IUs - non-categorical:

Number of IUs: o (zero)

Average Daily Flows, in MGD: o (zero)

Other IUs:

Number of IUs: o (zero)

Average Daily Flows, in MGD: o (zero)

B. Treatment plant interference

In the past three years, has your POTW experienced treatment plant interference (see instructions)?

🖺 Yes 🗵 No

If yes, identify the dates, duration, description of interference, and probable cause(s) and possible source(s) of each interference event. Include the names of the IUs that may have caused the interference.

Click to enter text.

C.	Treatment plant pass through
	In the past three years, has your POTW experienced pass through (see instructions)?
	□ Yes ⊠ No
	If yes, identify the dates, duration, a description of the pollutants passing through the treatment plant, and probable cause(s) and possible source(s) of each pass through event. Include the names of the IUs that may have caused pass through.
	Click to enter text.
D.	Pretreatment program
	Does your POTW have an approved pretreatment program?
	☐ Yes ☒ No
	If yes, complete Section 2 only of this Worksheet.
	Is your POTW required to develop an approved pretreatment program?
	☐ Yes ☒ No
	If yes, complete Section 2.c. and 2.d. only, and skip Section 3.
	If no to either question above , skip Section 2 and complete Section 3 for each significant industrial user and categorical industrial user.
Se	ection 2. POTWs with Approved Programs or Those Required to Develop a Program (Instructions Page 90)
A.	Substantial modifications
	Have there been any substantial modifications to the approved pretreatment program
	that have not been submitted to the TCEQ for approval according to 40 CFR §403.18?
	□ Yes □ No
	If yes , identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.
	Click to enter text.

B.	Non-substantial n	nodifications									
	Have there been any non-substantial modifications to the approved pretreatment program that have not been submitted to TCEQ for review and acceptance?										
	🛚 Yes 🗓	No									
	If yes, identify all non-substantial modifications that have not been submitted to TCEQ, including the purpose of the modification.										
	Click to enter text.										
C.	Effluent paramete	ers above the MAL									
	In Table 6.0(1), list	t all parameters me	asured above	the MAL in the PO	TW's effluent						
	monitoring during	the last three year	s. Submit an	attachment if neces	ssary.						
Tal	ble 6.0(1) – Parame	ters Above the MAL									
P	ollutant	Units	Date								
-		:									
D.	Industrial user in	terruptions		•							
				d to any problems he past three years							
	🗓 Yes 🗒 No										
	If yes, identify the industry, describe each episode, including dates, duration, description of the problems, and probable pollutants.										
	Click to enter tex										

Significant Industrial User (SIU) Information and Categorical Industrial User (CIU) (Instructions Page 90) Section 3.

A.	General information
	Company Name: Click to enter text.
	SIC Code: Click to enter text.
	Contact name: Click to enter text.
	Address: Click to enter text.
	City, State, and Zip Code: Click to enter text.
	Telephone number: <u>Click to enter text.</u>
	Email address: Click to enter text.
B.	Process information
	Describe the industrial processes or other activities that affect or contribute to the SIU(s) or CIU(s) discharge (i.e., process and non-process wastewater).
	Click to enter text.
C.	Product and service information
C.	Product and service information Provide a description of the principal product(s) or services performed.
C.	
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
	Provide a description of the principal product(s) or services performed. Click to enter text.
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater."
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater:
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: Click to enter text.
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: Click to enter text. Discharge Type: Continuous Batch Intermittent
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: Click to enter text. Discharge Type: Continuous Batch Intermittent Non-Process Wastewater:
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: Click to enter text. Discharge Type: Continuous Batch Intermittent

E.

F.

ATTACHMENT No. 1

ADMINISTRATIVE REPORT 1.0 SECTION 3

CORE DATA FORM

TCEQ	Use	Only



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

∇ n 1/2 =				with the program application.)						
Renewal (Core Data Form should be submitted with the renewal form)						Other				
2. Customer Reference Number (if issued) CN 600737357 Follow this link to for CN or RN num Central Registr										
										ECTION II
4. General Custome	r Information	5. Effective D	ate for Cu	stomer	Information	Updates (mm/dd	/уууу)			
New Customer		pdate to Custom	er Informat	ion	Cha	nge in Regulated Er	ntity Owne	ership		
	ne (Verifiable with the Te				1000000	100	60			
The Customer Name	submitted here may	be updated aut	tomaticall	y based	on what is o	current and activ	e with th	e Texas Secr	etary of State	
(SOS) or Texas Comp	troller of Public Accou	ınts (CPA).								
6. Customer Legal N	ame (If an individual, pri	int last name first	: eg: Doe, Jo	ohn)		If new Customer	, enter pre	evious Custom	er below:	
City of Runge										
7. TX SOS/CPA Filing	Number	8. TX State Ta	ID (11 di	gits)		9. Federal Tax (9 digits) 746002019	ID	10. DUNS I applicable)	Number (if	
11. Type of Customo	er: Corpora	tion			☐ Indivi	dual	Partne	L ership: ☐ Gen	eral 🔲 Limited	
	County Federal		Other			Sole Proprietorship Other:				
12. Number of Emp						13. Independe	ently Ow	ned and Ope	erated?	
□ 0-20 □ 21-100	101-250 251	-500 🔲 501 ar	nd higher			⊠ Yes	☐ No			
14. Customer Role (Proposed or Actual) – as	it relates to the Re	egulated En	ntity listed	d on this form.	Please check one	of the follo	owing		
☐Owner ☐Occupational Licens	Operator ee Responsible Pa		er & Opera CP/BSA App			Othe	r:			
P.O. B	ox 206									
Address: City	Runge		State	TX	ZIP	78151		ZIP + 4		
					47 5 84-11 4	ddana (:C				
16. Country Mailing	Information (if outside	USA)		- 13	17. E-IVIAII A	ddress (if applica	bie)			
16. Country Mailing	Information (if outside	USA)				Osbcglobal.net	bie)			

19. Extension or Code

Page 1 of 3

20. Fax Number (if applicable)

18. Telephone Number

(830) 239-4121		() -
------------------	--	-------

SECTION III: Regulated Entity Information

21. General Regulated E	ntity Informa	ation (If 'New Re	gulated Entity" is sele	cted, a new p	ermit applica	tion is also required.)		
☐ New Regulated Entity	Update to	Regulated Entity	Name Update	to Regulated	Entity Inform	ation		
The Regulated Entity Na as Inc, LP, or LLC).	ıme submitte	d may be updo	ated, in order to me	et TCEQ Co	re Data Star	ndards (removal of o	rganization	al endings such
22. Regulated Entity Na	me (Enter nam	ne of the site whe	re the regulated actio	n is taking pl	lace.)			
City of Runge Wastewaster	Treatment Plar	nt						
23. Street Address of the Regulated Entity:	400 W. Lyon	ns						
(No PO Boxes)	City	Runge	State	TX	ZIP	78151	ZIP + 4	
24. County	Karnes							
		If no Stre	et Address is provi	ded, fields	25-28 are re	quired.		
25. Description to Physical Location:								
26. Nearest City						State	Nea	rest ZIP Code
Latitude/Longitude are used to supply coordina	tes where no	ne have been	8 8	accuracy).				
27. Latitude (N) In Decin		28.87556				V) In Decimal:	97.70417	
Degrees	Minutes	52	Seconds	Degi		Minutes		Seconds
28 29. Primary SIC Code	20	Secondary SIC	32 Code		97	42 33 Soci	ondary NAIG	15
(4 digits)		ligits)	Code	31. Prima (5 or 6 dig	ary NAICS Co	ode (5 or 6 di		es code
33. What is the Primary	Business of	this entity? (Do not repeat the SIC o	or NAICS desc	cription.)			
A wastewater treatment pla	ant for Runge							
34. Mailing	P.O. Box 2	06						
Address:	City	Runge	State	тх	ZIP	78151	ZIP + 4	
35. E-Mail Address:	city	.of.runge@sbcgl	obal.net				1	-
36. Telephone Number			37. Extension or	r Code	38. F	Fax Number (if applica	ible)	
(830) 239-4121					() -		

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.

TCEQ-10400 (11/22) Page 2 of 3

☐ Dam Safety ☐ Municipal Solid Waste ☐ Sludge		Districts	Edwards Aquifer		Emissions Inventory Air	☐ Industrial Hazardous Waste	
		New Source Review Air	☐ OSSF		Petroleum Storage Tank	☐ PWS	
		Storm Water			Tires		
☐ Voluntary Clea	nup	☑ Wastewater	☐ Wastewater Agricu	ture	Water Rights	Other:	
CECTION	TV. D.	WQ0010266001					
129/30/10/06/12/08	/le Stoner	<u>eparer Inf</u>	<u>Offination</u>	41. Title:	Graduate Engineer		
42. Telephone Nu	ımber	43. Ext./Code	44. Fax Number	45. E-Mail A	Address		
(210)828-7070			() -	kyle@copeer	ngineeringtx.com		
SECTION	V: Au	<u>ıthorized S</u>	<u>ignature</u>				
16. By my signature b			wledge, that the informati tion II, Field 6 and/or as re			te, and that I have signature authority lentified in field 39.	
16. By my signature b	n behalf of th						
16. By my signature to submit this form or	n behalf of th	ne entity specified in Sec	tion II, Field 6 and/or as re	quired for the up	dates to the ID numbers in		

Page 3 of 3

ATTACHMENT No. 2

ADMINISTRATIVE REPORT 1.0 SECTION 8

PLAIN LANGUAGE SUMMARY



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

SUMMARY OF APPLICATION IN PLAIN LANGUAGE FOR TPDES OR TLAP PERMIT APPLICATIONS

Summary of Application (in plain language) Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.


City of Runge (CN600737357) operates the City of Runge Wastewater Treatment Plant (RN: 101917839), a treatment plant with a primary settling pond system that consists of a bar screen, facultative lagoon, effluent storage pond, and irrigation fields. The facility is located at <u>400 W. Lyons</u>, in the City of Runge, Karnes County, Texas 78151. This request is to renew the Texas Land Application Permit (TLAP). This permit will not authorize a discharge of pollutants into water in the state.


Discharges from the facility are expected to contain CBOD5, suspended solids, ammonia nitrogen, nitrate nitrogen, kjeldahl nitrogen, sulfate, chloride, phosphorus, E. coli, and dissolved solids. The irrigated effluent is treated by a bar screen and pumped via a wet well and lift station to a facultative lagoon for settling. The treated effluent is then conveyed to a storage pond and pumped to the irrigation field.

ATTACHMENT No. 3

ADMINISTRATIVE REPORT 1.0 SECTION 13

USGS TOPOGRAPHIC MAP






ATTACHMENT No. 4

DOMESTIC TECHNICAL REPORT 1.0 ITEM 2C

FLOW DIAGRAM





COPE ENGINEERNG, INC. 8611 BOTTS LANE SAN ANTONIO, TX 78217 (210) 828-7070 OFFICE

TEXAS REG. #F-16078


FLOW DIAGRAM DOMESTIC TECHNICAL REPORT 1.0 ITEM 2C **TEXAS** CITY OF RUNGE

SHT

OF 1


DOMESTIC TECHNICAL REPORT 1.0 SECTION 3

SITE DRAWING




DOMESTIC TECHNICAL REPORT 1.0 ITEM 11A

GENERAL HIGHWAY (COUNTY) MAP



DOMESTIC TECHNICAL REPORT 1.0 ITEM 11A

USDA NATURAL RESOURCES CONSERVATION SERVICE SOIL MAP



MAP LEGEND

Soils Area of Interest (AOI) Special Point Features 4 0 沙 > 0 Soil Map Unit Polygons Miscellaneous Water Landfill Gravelly Spot Gravel Pit Closed Depression Clay Spot Borrow Pit Blowout Soil Map Unit Points Soil Map Unit Lines Area of Interest (AOI) Saline Spot Rock Outcrop Perennial Water Mine or Quarry Marsh or swamp Lava Flow Background Transportation Water Features Ī . 8 c(3 O m Rails Other Streams and Canals Wet Spot Aerial Photography Major Roads Special Line Features Very Stony Spot Stony Spot Local Roads **US** Routes Interstate Highways Spoil Area

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at

Enlargement of maps beyond the scale of mapping can cause Warning: Soil Map may not be valid at this scale.

misunderstanding of the detail of mapping and accuracy of soil

line placement. The maps do not show the small areas of

Please rely on the bar scale on each map sheet for map contrasting soils that could have been shown at a more detailed

Source of Map: Natural Resources Conservation Service measurements.

Coordinate System: Web Mercator (EPSG:3857) Web Soil Survey URL:

accurate calculations of distance or area are required. Maps from the Web Soil Survey are based on the Web Mercator Albers equal-area conic projection, should be used if more distance and area. A projection that preserves area, such as the projection, which preserves direction and shape but distorts

of the version date(s) listed below. This product is generated from the USDA-NRCS certified data as

Survey Area Data: Soil Survey Area: Karnes County, Texas Version 21, Aug 30, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 28, 2010—Oct

imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. compiled and digitized probably differs from the background The orthophoto or other base map on which the soil lines were

Ŵ

Severely Eroded Spot

Sandy Spot


8 0

Sodic Spot Slide or Slip Sinkhole

Natural Resources Conservation Service

Map Unit Legend

%0.001	1.71		Totals for Area of Interest
%1.0	0.0	Pernitas sandy clay loam, 2 to 5 percent slopes	DuC
%6.8£	8.8	Monteola clay, 0 to 1 percent slopes	AoM
%9'Z	≯. .0	Coy clay loam, 1 to 3 percent slopes	CoB
% t .83	0.01	Clareville clay loam, 0 to 1 percent slopes	AnO
Percent of AOI	Acres in AOI	emsM tinU qsM	Map Unit Symbol



MAP LEGEND

Soils Area of Interest (AOI) Special Point Features 5< 冷 0 0 Ŵ 0 8 Blowout Soil Map Unit Points Area of Interest (AOI) Sodic Spot Slide or Slip Sinkhole Severely Eroded Spot Sandy Spot Saline Spot Rock Outcrop Perennial Water Miscellaneous Water Mine or Quarry Marsh or swamp Lava Flow Landfill Gravelly Spot Gravel Pit Closed Depression Clay Spot Borrow Pit Soil Map Unit Lines Soil Map Unit Polygons Background Water Features Transportation . 8 **C** O m Rails Streams and Canals Aerial Photography Other Wet Spot Local Roads Major Roads **US** Routes Interstate Highways Special Line Features Very Stony Spot Stony Spot Spoil Area

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at

Warning: Soil Map may not be valid at this scale.

line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator accurate calculations of distance or area are required. Albers equal-area conic projection, should be used if more projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the

of the version date(s) listed below. This product is generated from the USDA-NRCS certified data as

Survey Area Data: Version 21, Aug 30, 2024 Soil Survey Area: Karnes County, Texas

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 28, 2010—Oct

imagery displayed on these maps. As a result, some minor compiled and digitized probably differs from the background shifting of map unit boundaries may be evident. The orthophoto or other base map on which the soil lines were


Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CbC	Collibro sandy clay loam, 3 to 5 percent slopes	0.0	0.0%
СоВ	Coy clay loam, 1 to 3 percent slopes	5.8	14.7%
PnC	Pernitas sandy clay loam, 2 to 5 percent slopes	26.4	67.5%
ShC	Schattel clay loam, 2 to 5 percent slopes	2.0	5.2%
WaC	Weesatche fine sandy loam, 2 to 5 percent slopes	4.9	12.5%
Totals for Area of Interest		39.1	100.0%

DOMESTIC TECHNICAL REPORT 1.0 ITEM 11A

FEDERAL EMERGENCY MANAGEMENT MAP

DOMESTIC TECHNICAL REPORT T.U




DOMESTIC TECHNICAL REPORT 1.0 ITEM IIA This is an official copy of a portion of the above referenced flood map. It was extracted using F-MiT On-Line. This map does not reflect changes or a mendiments which map have been mades subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps, check the FEMA Flood Map Store at www.mac.fema.gov 4000 FEET MAP NUMBER 48255C0425C **EFFECTIVE DATE** OCTOBER 19, 2010 Federal Emergency Management Agency Motes Is User: The Map Number stoom before should be used when placing map unders; the Commandy Number stoom commands to used on treasures application for the activate contradity. FLOOD INSURANCE RATE MAP (SEE MAP INDEX FOR FIRM PANEL LAYOUT) SUFFIX uО AND INCORPORATED AREAS PAPEL PANEL 0425C KARNES COUNTY, MAP SCALE 1" = 2000" NUMBER Z1124 ફ PANEL 425 OF 550 KARALIS COUNTY RUNGE, TOMPHOF TEXAS COMMUNITY CONTAINS NYLIONYT EFOOD INZINISYNCE 8 JOINS PANEL 0300 ⁶28^{000m} E Vales Creek ZONE A ⁶27^{000™} E Ojo de Agua Creek ZONE .Ojo de Agua Creek -ZONE A 8 526 MAT LIMIT OF DETAILED STUDY PROFILE BASE LINE ZONE 266 885 CR 122 CITY OF RUNGE 481120 ⁶25^{000m} E

K

E

DOMESTIC TECHNICAL REPORT 1.0 ITEM 11A

SITE MAP



DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

SECTION 5

ANNUAL CROPPING PLAN

DOMESTIC WORKSHEET 3.0 SECTION 5

ANNUAL CROPPING PLAN

The irrigation site is composed of 42 acres used for agricultural pasture land.


The predominant soil on the surface at the irrigation site is Pernitas sandy clay loam (PnC). See attached USDA NRCS Soil Map in the attachments of this application.


The predominant cover is Coastal Bermuda grass. The minimum harvest height is 4" and the maximum harvest height is 24". It is harvested twice a year for the typical hay bailing activity. It has high salt tolerance and requires no supplemental watering. The growing season 8 out of 10 years is about 350 days per year for temperature above 24°F. No additional fertilizers are required.

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

SECTION 6

NEARBY WELL & MAP INFORMATION (USGS MAP)





DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

SECTION 6

WELL ID INFORMATION





GWDB Reports and Downloa	ads W	ell Basic Details	Scanned Documents
State Well Number	7903704	Well Type	Withdrawal of Water
County	Karnes	Well Use	Public Supply
River Basin	San Antonio	Water Level Observation	Miscellaneous Measurements
Groundwater Management Area	15	Water Quality Available	Yes
Regional Water Planning Area	L - South Central Texas	Pump	Submersible
Groundwater Conservation District	Evergreen UWCD	Pump Depth (feet below land surface)	
Latitude (decimal degrees)	28.881389	Power Type	Electric Motor
Latitude (degrees minutes seconds)	28° 52' 53" N	Annular Seal Method	
Longitude (decimal degrees)	-97.712778	Surface Completion	
Longitude (degrees minutes seconds)	097° 42' 46" W	Owner	City of Runge well # 2
Coordinate Source	Global Positioning System - G	Driller	Layne-Texas Co.
Aguifer Code	122JSPR - Jasper Aquifer	Other Data Available	Drillers Log
Aquifer	Gulf Coast	Well Report Tracking Number	
Aquifer Pick Method	Guil Coast	Plugging Report Tracking Numbe	r
Land Surface Elevation (feet above	310	U.S. Geological Survey Site Number	
sea level) Land Surface Elevation Method	Interpolated From Topo Map	Texas Commission on Environmental Quality Source Id	G1280003B
Well Depth (feet below land surface)	212	Groundwater Conservation	
Well Depth Source	Driller's Log	District Well Number	
Drilling Start Date		Owner Well Number	
Drilling End Date	0/0/1935	Other Well Number	
Drilling Method		Previous State Well Number	
Borehole Completion		Reporting Agency	Texas Water Development Board
		Created Date	6/21/2001
		Last Update Date	10/4/2006

Remarks Reported yield, 132 gpm. Drawdown 26 ft. Screened from 156 to 190 ft

188 SAND 212 CLAY

Casing - No Data

Test Type

Well Tests Test Date

	Unknown	132	26	0
Lithology				
Top Depth (ft.)	Bottom Depth (ft.)	Description		
0	4	SURFACE SOIL		
4	66	HARD YELLOW CLAY		
66	67	ROCK		
67	96	HARD CLAY		
96	116	CLAY AND BOULDERS		
116	136	CLAY		
136	154	HARD CLAY AND BOU	LDERS	

Yield (gallons per minute) Drawdown (ft.)

Test Hours

154

188






Annular Seal Range - No Data		
Borehole - No Data	Plugged Bad	ck - No Data
Filter Pack - No Data		Packers - No Data







Status Code	Date	Time	Water Level (ft. below land surface)	Change value in () indicates rise in level	Water Elevation (ft. above sea level)	Meas #	Measuring Agency	Method	Remark ID	Comments
Р	0/0/1935		95		215	1	Other or Source of Measurement Unknown	Unknown		
Χ	8/7/2006					1	Texas Water Development Board	Steel Tape	28	

Code Descriptions

Status Code	Status Description	Remark ID	Remark Description
P	Publishable	28	Uncertain of reason for no measurement
Χ	No Measurement		





Water Quality Analysis

Sample Date: 3/31/1937 Sample Time: 0000 Sample Number: 1 Collection Entity: U.S. Geological Survey

Sampled Aquifer: Jasper Aquifer

Analyzed Lab: U.S. Geological Survey Lab Reliability: From a report; unknown sample collection & preservation

Collection Remarks: Analysis taken from M-151

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		85.25	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		104.03	mg/L	
00910	CALCIUM (MG/L)		54	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		312	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		266	mg/L as CACO 3	
00920	MAGNESIUM (MG/L)		32	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		3.44		
00932	SODIUM, CALCULATED, PERCENT		51	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)	calculate d		mg/L	
00945	SULFATE, TOTAL (MG/L AS SO4)		23	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS, SUM OF CONSTITUENTS (MG/L)		601	mg/L	





Water Quality Analysis

Sample Date: 4/18/1954

Sample Time:

0000

Sample Number: 1

Collection Entity: U.S. Geological Survey

Sampled Aquifer:

Jasper Aquifer

Analyzed Lab:

Reliability: From a report; unknown sample collection & preservation

Collection Remarks:

B-6007

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		231.15	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		282.08	mg/L	
00910	CALCIUM (MG/L)		130	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		315	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		1	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		472	mg/L as CACO 3	
01045	IRON, TOTAL (UG/L AS FE)		200	ug/L	
00920	MAGNESIUM (MG/L)		36	mg/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		6.7	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		7.1	SU	
00937	POTASSIUM, TOTAL (MG/L AS K)		27	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		20	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		1.96		
00932	SODIUM, CALCULATED, PERCENT	ANNUAL DE PROPERTIES DE LA CONTRACTION DE LA CON	31	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		98	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1540	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		36	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		808	mg/L	





Water Quality Analysis

Sample Date: 10/0/1955 Sample Time: 0000 Sample Number: 1 Collection Entity: U.S. Geological Survey

Sampled Aquifer: Jasper Aquifer

Analyzed Lab: Reliability: From a report; unknown sample collection & preservation

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		234.43	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		286.09	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		300	ug/L	
00910	CALCIUM (MG/L)		121	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		312	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.5	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		425	mg/L as CACO 3	
01045	IRON, TOTAL (UG/L AS FE)	<	10	ug/L	
00920	MAGNESIUM (MG/L)		30	mg/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		5.1	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		7.6	SU	
00937	POTASSIUM, TOTAL (MG/L AS K)		7.8	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		37	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.7		
00932	SODIUM, CALCULATED, PERCENT		39	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		128	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1450	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		35	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		817	mg/L	





Water Quality Analysis

Sample Date: 7/23/1981 Sample Time: 0000 Sample Number: 1 Collection Entity: Texas Water Development Board

Sampled Aquifer: Jasper Aquifer

Analyzed Lab: Texas Department of Health Reliability: Collected from pumped well, but not filtered or preserved

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		205	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		250.17	mg/L	
00910	CALCIUM (MG/L)		131	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		353	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.6	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		454	mg/L as CACO 3	
00920	MAGNESIUM (MG/L)		31	mg/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		7.3	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		8	SU	
00937	POTASSIUM, TOTAL (MG/L AS K)		8	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		31	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.67		
00932	SODIUM, CALCULATED, PERCENT		38	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		131	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1659	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		36	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		28	С	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		851	mg/L	





Water Quality Analysis

Sample Date: 6/21/2001

Sample Time:

1500

Sample Number: 1

Collection Entity: Texas Water Development Board

Sampled Aquifer:

Jasper Aquifer

Analyzed Lab: LCRA - Lower Colorado River Authority

Reliability: Sampled using TWDB protocols

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39086	ALKALINITY FIELD DISSOLVED AS CACO3		229	mg/L as CACO 3	
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		222	mg/L as CACO 3	
01106	ALUMINUM, DISSOLVED (UG/L AS AL)	<	4	ug/L	
01095	ANTIMONY, DISSOLVED (UG/L AS SB)	<	1	ug/L	
01000	ARSENIC, DISSOLVED (UG/L AS AS)	<	2	ug/L	
01005	BARIUM, DISSOLVED (UG/L AS BA)		141	ug/L	
01010	BERYLLIUM, DISSOLVED (UG/L AS BE)	<	1	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		270.92	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		379	ug/L	
71870	BROMIDE, DISSOLVED, (MG/L AS BR)		1.42	mg/L	
01025	CADMIUM, DISSOLVED (UG/L AS CD)	<	1	ug/L	
00915	CALCIUM, DISSOLVED (MG/L AS CA)		133	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00941	CHLORIDE, DISSOLVED (MG/L AS CL)		340	mg/L	
01030	CHROMIUM, DISSOLVED (UG/L AS CR)	<	1	ug/L	
01035	COBALT, DISSOLVED (UG/L AS CO)	<	1	ug/L	
01040	COPPER, DISSOLVED (UG/L AS CU)	<	2	ug/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.67	mg/L	
04241	GROSS ALPHA RADIATION, TOTAL, PRODUCED WATER(pCi/L)		7.3	pCi/L	
04242	GROSS BETA RADIATION, TOTAL, PRODUCED WATER(pCi/L)		10	pCi/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		482	mg/L as CACO 3	
01046	IRON, DISSOLVED (UG/L AS FE)	<	51	ug/L	
01049	LEAD, DISSOLVED (UG/L AS PB)	<	1	ug/L	
01130	LITHIUM, DISSOLVED (UG/L AS LI)		32.8	ug/L	
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)		35.9	mg/L	
01056	MANGANESE, DISSOLVED (UG/L AS MN)	<	1	ug/L	
01060	MOLYBDENUM, DISSOLVED (UG/L AS MO)	<	1	ug/L	
01065	NICKEL, DISSOLVED (UG/L AS NI)		1.65	ug/L	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		7.61	mg/L as NO3	
00631	NITRITE PLUS NITRATE, DISSOLVED (MG/L AS N)		1.72	mg/L as N	
00400	PH (STANDARD UNITS), FIELD		7.1	SU	
00935	POTASSIUM, DISSOLVED (MG/L AS K)		7.92	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
01145	SELENIUM, DISSOLVED (UG/L AS SE)	<	4	ug/L	
00955	SILICA, DISSOLVED (MG/L AS SI02)		31.7	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.66		
00932	SODIUM, CALCULATED, PERCENT		37	PCT	
00930	SODIUM, DISSOLVED (MG/L AS NA)		134	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1584	MICR	
01080	STRONTIUM, DISSOLVED (UG/L AS SR)		2750	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)		35.8	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		25.3	С	
01057	THALLIUM, DISSOLVED (UG/L AS TL)	<	1	ug/L	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		862	mg/L	
01085	VANADIUM, DISSOLVED (UG/L AS V)		8.29	ug/L	
01090	ZINC, DISSOLVED (UG/L AS ZN)		175	ug/L	





Water Quality Analysis

Sample Date: 6/21/2001

Sample Time:

Sample Number:

Collection Entity: Texas Commission on Environmental

Quality

Sampled Aquifer:

Jasper Aquifer

Analyzed Lab: Immunoassay at TCEQ

Reliability: Sampled using TWDB protocols, but NOT filtered

Collection Remarks:

No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39033	ATRAZINE, TOTAL, UG/L	<	0.05	ug/L	
82612	METOLACHLOR, WHOLE WATER, TOTAL RECOVERABLE, UG/L	<	0.05	ug/L	





Water Quality Analysis

Sample Date: 8/7/2006 Sample Time: 0838 Sample Number: 1 Collection Entity: Texas Water Development Board

Sampled Aquifer: Jasper Aquifer

Analyzed Lab: Energy Labs Inc.

Reliability: Sampled using TWDB protocols

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39086	ALKALINITY FIELD DISSOLVED AS CACO3		224	mg/L as CACO 3	
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)	<	1	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		284	mg/L as CACO 3	
01503	ALPHA, DISSOLVED (PC/L)		9	PC/L	0.0
01106	ALUMINUM, DISSOLVED (UG/L AS AL)	<	1	ug/L	
01095	ANTIMONY, DISSOLVED (UG/L AS SB)	<	1	ug/L	
01000	ARSENIC, DISSOLVED (UG/L AS AS)		2	ug/L	
01005	BARIUM, DISSOLVED (UG/L AS BA)		138	ug/L	
01010	BERYLLIUM, DISSOLVED (UG/L AS BE)	<	1	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		346.57	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		360	ug/L	
71870	BROMIDE, DISSOLVED, (MG/L AS BR)		1.7	mg/L	
01025	CADMIUM, DISSOLVED (UG/L AS CD)	<	1	ug/L	
00915	CALCIUM, DISSOLVED (MG/L AS CA)		130	mg/L	
28004	CARBON-14 DISS APPARENT AGE (YEARS BP)		12160	Y-BP	70
82172	CARBON-14 FRACTION MODERN		0.22		0.001
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00941	CHLORIDE, DISSOLVED (MG/L AS CL)		353	mg/L	
01030	CHROMIUM, DISSOLVED (UG/L AS CR)		2	ug/L	
01035	COBALT, DISSOLVED (UG/L AS CO)	<	1	ug/L	
01040	COPPER, DISSOLVED (UG/L AS CU)		1	ug/L	
82081	DELTA CARBON 13 C13/C12 PER MIL		-7.2	0/00	
50791	DEUTERIUM, EXPRESSED AS PERMIL VSMOW		-25	0/00	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.6	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		472	mg/L as CACO 3	
01046	IRON, DISSOLVED (UG/L AS FE)		167	ug/L	
01049	LEAD, DISSOLVED (UG/L AS PB)		1	ug/L	
01130	LITHIUM, DISSOLVED (UG/L AS LI)		42	ug/L	
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)		35	mg/L	
01056	MANGANESE, DISSOLVED (UG/L AS MN)		5	ug/L	
01060	MOLYBDENUM, DISSOLVED (UG/L AS MO)		1	ug/L	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		7.08	mg/L as NO3	
00631	NITRITE PLUS NITRATE, DISSOLVED (MG/L AS N)		1.6	mg/L as N	
50790	OXYGEN-18, EXPRESSED AS PERMIL VSMOW		-4.7	0/00	0.3
50982	OXYGEN-18/OXYGEN-16 OF SULFATE (RATIO PER MIL)		4.5	0/00	0.4
00400	PH (STANDARD UNITS), FIELD		6.94	SU	
00935	POTASSIUM, DISSOLVED (MG/L AS K)		8.3	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
01145	SELENIUM, DISSOLVED (UG/L AS SE)		6	ug/L	
00955	SILICA, DISSOLVED (MG/L AS SI02)		30.2	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.63		
00932	SODIUM, CALCULATED, PERCENT		38	PCT	
00930	SODIUM, DISSOLVED (MG/L AS NA)		131	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1468	MICR	
01080	STRONTIUM, DISSOLVED (UG/L AS SR)		2480	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)		39	mg/L as SO4	
49932	SULFUR-34/32 OF SULFATE, DISSOLVED, PER MIL		11	0/00	0.3
00010	TEMPERATURE, WATER (CELSIUS)		25	С	
01057	THALLIUM, DISSOLVED (UG/L AS TL)		< 1	ug/L	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		907	mg/L	
07012	TRITIUM IN WATER (TRITIUM UNITS)		0.1	TU	0.0
01085	VANADIUM, DISSOLVED (UG/L AS V)		9	ug/L	
01090	ZINC, DISSOLVED (UG/L AS ZN)		251	ug/L	

^{*} Value may not display all significant digits for parameter in results, check Scanned Documents for laboratory paperwork..

GWDB DISCLAIMER: Except where noted, all of the information provided in the Texas Water Development Board (TWDB) Groundwater Database (https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp) is believed to be accurate and reliable; however, the TWDB assumes no responsibility for any errors appearing in rules or otherwise. Further, TWDB assumes no responsibility for the use of the information provided. PLEASE NOTE that users of these data are responsible for checking the accuracy, completeness, currency and/or suitability of all information themselves. TWDB makes no guarantees or warranties as to the accuracy, completeness, currency, or suitability of the information provided with the Groundwater Database (GWDB). TWDB specifically disclaims any and all liability for any claims or damages that may result from providing GWDB data or the information it contains. For additional information or answers to questions concerning the TWDB GWDB, contact the Groundwater Data Team at GroundwaterData@twdb.texas.gov.

TEXAS DEPARTMENT OF WATER RESOURCES

WELL SCHEDULE

	Adulfer(s) Sand Stank Project No. F - 39	State Well No. 79_	03-704
	Field No./Owner's Well No.# 2		
}.	Location: ±, ±, Section , Block , Survey		,
2.	Owner: City of Runger Address:		
	Tenant (other): Address:		
	Driller: Leyne Texas Address:		
3.	Land Surface Elevation: 300 ft. above msl determined by J. D.O.	0	
4.	Drilled: 19.3.5; Dug, Cable Tool, Rotary, Air,		
5.	Depth: Rept. 2)2 ft. Measft.	CASING, BLANK I	PIPE & WELL SCREEN ft. to ft.
	Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed	Diam. Type	Setting (feet)
7.	Pump: Hfr. Type Turbing	(In.)	from to
	No. Stages, Bowls Diamin., Settingft.	10	0 212
	Column Diamin., Length Tailpipeft.	Screen	156 190
8.	Motor: Mfr. Fuel Flec HP. JO		
	Yield: Flowgpm, Pump 132 gpm, Heas. (Rept.), EstDate		
10.	Performance Test: Date Length of Test Made by		
	Static Levelft. Pumping Levelft. Drawdown 26ft.		
	Productiongpm Specific Capacitygpm/ft.	RECEIVED	
11.	Quality: (Remarks on taste, odor, color, etc.)	AUG 17 1981	
	Analyses		
779	F Date 10 / 55 Laboratory TDSSp Cond	CKITOWE	
	Date_7/13/81 LaboratoryTDSSp Cond		
12.	Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log,		
	Formation Samples, Geophysical Log(s)(type)		
13.	Water Level(s): 95 ft. rept. 1935 below 15 D 19 above meas. 19 above below 19 below 19 below 19 below 19 below 19	which isft.	above below Land Surface above Land Surface
			below
	Use: Dom., Stock, Public Supply, Ind., Irr., Observation, Other (Test Hole, Oil		7/2-12-
	Recorded by: D Jones Source of data: B - 6007	Date:	1/20/21
16.	Remarks:		
2020			
17.	Location or Skatch: Next Page		

W/L Obs. Well W/Q Obs. Well State Well No. 79 -03-704

TE S C ARTMENT OF WATER REST RCF

BY	DATE	_ DIVISION		SHEET NO	OF
CHKD	DATE	JOB NAME 28-	79-03-7		
			JOB NO. E - 39	PROG. CODE.	Well #
	(Gate	a.	en e		
	Water				
Bu'll	ding	4 2			
	-0#3 		81		
				//	
			72		
		72		South on and Street the right.	81 to
		a.	Inset () ATT	CHMENT	
er.					
	· P	Z 79-0.	2 70.1		
T. on	1 2	- 19-0.	3-10 7		i

TDWR-0738

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756

TDWR-0148 (Rev. 1-8-80)

	TDWR ONLY	
Organization N	No. 4)0 Lab No. 01	
Work No	6040	

Addition, 1 and 7 by 60	
CHEMICAL	WATER ANALYSIS REPORT
Send report to:	RECEIVED County 126
Data Collection and Evaluation Section	MAR 3 1 1982 State Well No. 79 63 70 9
Texas Department of Water Resources P.O. Box 13087	ORATO Well No.
Austin, Texas 78711	Date Collected OT 23 811
Location	Sample No. By
Source (type of well) ILLY h. Flor Owner	City of Russe
Date Drilled ft. WBF	
Producing intervals Water level	
Sampled after pumping 5 M. hrs. Yie	/
Point of collection Fave 8 Use Public Remarks	Appearance D clear D turbid D Scharety D other
	\$EP 2 1981
(FC PABORATORY USE ONLY) CHE	AUC 7 1 10 f
	eceived 1111 2 7 1981 Date Reported
MG/L ME/L	MG/L ME/L
Silica · · · 00955 · · · 3/	Carbonate · · 00445 · ·
Calcium · · · 00915 · · · / / 3 /	57 Bicarbonate . 00440 250 4 10
Magnesium · · 00925 · · · 3 / 2	F3 Sulfate · · · 00945 · · 3 6 0 25
Sodium · · · 00929 · · · //3 // 5	79 Chioride · · 00940 · · 353 9 55
Total	Fluoride · · 00951 · 0 6 0 03
Li Potassium : 00907 : 1	20 Nitrate · · · 71850 · 7 3
Manganesa · 01055 · · · %Na	pH · · · · 00403 · · 8 0 Total , 4 95
□ Boron 01022	¹ Dissolved Solids (residue at 180°C) · 70300 · 96 2
Total Iron - 01045 RSC	Phenolphthalein Alkalinity as C aCO ₃ · 00415 · · · O
(other) MG/L	Total Alkanoity as CaCO3 00410 205
Specific Conductance (micromhos/cm ³) - 00095 -	20 Total Hardness as CaCO ₃ 00900
Diluted Conductance (micromhos/cm ³) 21 x 79	Ammonia - N · · · · · · · · · · · · · · · · · ·
" items will be analyzed if checked. 1659	Nitrite - N · · · · · · · · · · · · · · · · · ·
¹ The bicarbonate reported in this analysis can be converted computation (multiplying by 0.4917) to an equivalent amoun	by Nitrate - N
carbonate, and the carbonate figure used in the computation dissolved solids. Nitrogen cycle requires separate sample. Total Iron and Manganese require separate sample.	Organic Nitrogen · · · · ·

Analyst _____ Checked By ____

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

	TDV	VR ONL	Y r-	_
Organizati	on No	Lat	No.	
Work No				

CHEMICAL WATER AN

Send report to:

Silice

	Organization No Lab No
Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756	Work No
CHEMICAL WATER AN	County ZB KARNES
Send report to:	1701-121-1701-d
Data Collection and Evaluation Section Texas Department of Water Resources P.O. Box 13087 Austin, Texas 78711	Date Collected
Location	Sample NoBy
Source (type of well) Owner	
Date Drilled Depth ft. WBF	
Producing intervals Water level	ft. Sample depth ft.
Sampled after pumpinghrs. Yield	GPM est. Temperature *F ** C
Point of collection	Appearance clear turbid colored cother
Use Remarks	
(FOR LABORATORY USE ONLY)	
CHEMICAL AN	IALYSIS KEY PUNCHED
Laboratory No Date Received	
MG/LME/L	MG/L ME/L
Silice · · · 00955 · · ·	Carbonate · · · 00445 · ·
Calcium · · · 00915 · · · / 2/	Bicarbonate · 00440 · · 286
Magnesium · 00925 · · · 30	Sulfate · · · 00945 · ·
Gadium · · · 00929 · · · 1/28	Chloride · · 00940 · · 3/2
Total	Fluoride · · 00951 ·
□ Potessium - 00937 - · · 7 - 8	Nitrate · · · 71850 ·
☐ Menganese · 01055 · · · 8 8Na <u>39</u>	рн 00403 Тота
Boron 01022	Dissolved Solids (residue at 180°C) · 70300 · 9/3
□ Total Iron - 01045	Phenolphthalain Alkalinity as C aCO ₃ · 00415 · ·
(other) MG/L	Total Alkalinity as C aCO3 · · · . 00410 · .
Specific Conductance (micromhos/cm³) · 00095 · 1856	Total Hardness as C sCO ₃ · · · · 00900 · · · · · · · · · · · · ·
Diluted Conductance (micromhos/cm ³)	Ammonia - N · · · · · · · · 00610 ·
" items will be analyzed if checked.	Nitrite - N / · · · · · · · · · · · 00615 ·
The bicarbonate reported in this analysis can be converted by computation (multiplying by 0.4917) to an equivalent amount of carbonate, and the carbonate figure used in the computation of discovery solids.	Nitrate - N
dissolved solids. Nitrogen cycle requires separate sample. Total Iron and Manganese require separate sample.	Analyst Checked By
	Analyst Checked By

¹ The bicarbonate reported in this analysis can be converted by computation (multiplying by 0.4917) to an equivalent amount of carbonate, and the carbonate figure used in the computation of dissolved solids.

³ Total Iron and Manganese require separate sample.

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use bell point pen

	TDWR ONLY
Organization	NoLab No.
Work No	

_____ Checked By _

Analyst __

Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756	Work No
DISTANCE WATER	
CHEMICAL WAT	ER ANALYSIS REPORT
Sand report to:	County 128 / ARNES
Data Collection and Evaluation Section	State Well No. 2013 7014
Texas Department of Water Resources	
P.O. Box 13087 Austin, Texas 78711	Date Collected
, , , , , , , , , , , , , , , , , , , ,	Date Collected ————————————————————————————————————
Location	Sample No By
Source (type of well) Owner	
Date Drilled Depth ft. WBF	
Producing intervals Water level	ft. Sample depthft.
Sampled after pumpinghrs. Yield	GPM mees, Temperature F
Point of collection	Appearance
UseRemarks	07
(FOR LABORATORY USE ONLY)	
	AL ANALYSIS KEY PUNCHED
Laboratory No Date Receive	ed Date Reported
MG/L ME/L	MG/L ME/L
Silica · · · 00955 · · ·	Carbonate · · 00445 · ·
Calcium · · · 00915 · · · / 30	Bicarbonate · 00440 · · 282
Magnesium · · 00925 · · · 36	Sulfate · · · 00945 · · 36
Sodium · · · 00929 · · ·	Chloride · · 00940 · · 3/5
Total	Fluoride · · 00951 ·
Potassium · 00937 · · · 27	Nitrate 71850
³ ☐ Manganese · 01055 · · · %Na 36	pH · · · · 00403 · · Total
Boron 01022	Dissolved Solids (residue at 180°C) · 70300 · 96
Total Iron • 01045 · · · RSC	Phenolphthalein Alkalinity as C aCO3 · 00415
1 lother) MG/L	Total Alkalinity as C aCO3
Specific Conductance (micromhos/cm ³) · 00095 ·	Total Hardness as C aCO ₃ · · · · 00900 · ·
Diluted Conductance (micromhos/cm ³)	Ammonia - N · · · · · · · · · 00610 ·
" Items will be analyzed if checked.	Nitrite - N · · · · · · · · · · · · · · · · · ·
¹ The bicarbonate reported in this analysis can be converted by computation (multiplying by 0.4917) to an equivalent amount of	Nitrate - N
carbonate, and the carbonate figure used in the computation of dissolved solids. ² Nitrogen cycle requires separate sample. ³ Total Iron and Manganese require separate sample.	Organic Nitrogen · · · · ·

TDWR-0148 (Rev. 1-8-80)

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

Texas Department of Health Laboratories

	TDWR ONLY
Program No	Lab No.
Work No.	

1100 West 49th Street Austin, Texas 78756 **CHEMICAL WATER ANALYSIS REPORT** Send report to: State Well No. 7 **Data Collection and Evaluation Section** Texas Department of Water Resources P.O. Box 13087 Austin, Texas 78711 Date Collected Location _____ Owner <u>City of Runal</u> Source (type of well) ____ Date Drilled 1935 Depth 212 ft. WBF DAKVILLE SANDSTONE _____ ft. Sample depth Producing intervels ____ ____ Water level ____ hrs. Yield _____ hrs. Yield _____ 132 GPM meas. Temperature Sampled after pumping ____ _____Appearance C clear C turbid C colored C other Point of collection Use_ P. S. ____ Remarks __ (FOR LABORATORY USE ONLY) **CHEMICAL ANALYSIS** W. MAKE Date Reported _ Laboratory No. _ Date Received .. MG/L ME/L MG/L ME/L Silica Carbonate -Calcium · Bicarbonate 0 Sulfate . . 3 Magnesium Chloride 3 1 Sodium · Fluorida Potassium - - - -3 ☐ Manganesa • Total ☐ Boron . Dissolved Solids (residue at 180°C) · · · ³ ☐ Total Iron • Phenolphthalein Alkalinity as C aCD3 · · · · · MG/L (other) _ Total Alkalinity as C aCO3 · · · · · Specific Conductance (micromhos/cm3) . Total Hardness es C aCO₃ · · · · Z 6 5 ² Nitrogen Cycle Diluted Conductance (micromhos/cm³) " \(\sigma\) " items will be analyzed if checked. ¹ The bicarbonate reported in this analysis can be converted by Nitrata - N computation (multiplying by 0.4917) to an equivalent amount of carbonate, and the carbonate figure used in the computation of dissolved solids. Organic Nitrogen · · · · ² Nitrogen cycle requires separate sample.

Analyst

__ Checked By ___

TDWR-0148 (Rev.7-78)

³ Total Iron and Manganese require separate sample.

Table 6.- Drillers' logs of wells in Karnes County--Continued

Thickne (feet		Depth (feet)		kness et)	Depth (feet)
		Well	E-39		
Owner: City of Runge, well 2	2. 1	Driller:	Layne-Texas Co.	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
Surface soil	4~	4	Clay	50	136
Clay, hard, yellow	62	66	Clay, hard and boulders -	18	154
Rock	1	.67	Sand	. 314	188
Clay, hard	29	96	Clay	24	515
Clay and boulders	20	116			
		<u> </u>		9-03	-704

TWDB Water Quality Field Data Sheet

Data Entered By Sampler Into Database:					
Balanced: S			25.6	25,2	Conductivity Temperature (Celsius):
Calculated TDS (mg/L): 862			1584	1582	Conductivity (uS/cm):
Total Hardness:			25.3	25,0	Temperature (Celsius):
Items Below Calculated Later From Results:			7.10	7,09	pH:
			1500	1450	Time:
	Final Readings:		Table	tion Parameters	Nater Quality Stabilization Parameters Table
2/0068M:		hand pump Nine	Filter pressure:	1500	Sample Time:
Notes:)			
Field Phenol Alkalinity: mg/L		302	Elevation:	m	Power:
Field Total Alkalinity:		94 Ch Lb	Longitude:	S	Lift:
Items below calculated from ml. acid added data:		28 5a 54	Latitude: 28	PUBLIC	Well Use:
ml. Acid added for Phenol		٠		> '	
1,45ml. Acid added for Total		TAN	Sampling Point:	POA	Pumping Since: PD A
50 ml. Sample Size		-) (
7.11 Start pH 4,50 End pH			W.L. remark:	MOA	N. L. depth from LSD (ft.): PDA
Field Alkalinity Titration:					
		1535	Time Out:	1440	Time In:
5000		served to drop the pH to 2.	Add enough of the proper acid to each bottle that is preserved to drop the pH to 2.	nough of the proper a	
2000 2000	10 ml Nitric (HNO3)	no preservative	0.5 ml Sulfuric (H2SO4)	1ml Nitric (HNO3)	no preservative
1000 (00)	Radioactivity	Atrazine	Nitrate/Nitrite	Cations	Anions / Total Alkalinity
Conductivity 500 50/	1 gallon (filtered)	40 ml (not filtered)	250mi (milered)	500ml (filtered)	500ml (filtered)
	5	4 (on ice)	3 (on ice)	2	1 (on ice)
4 or 10 10.0		4.	CIRCLE BOTTLES TAKEN:	CI	
PH 7 1/0		<u>ي</u>	Well Number:		
Daily Meter Calibration:	78151			1	Aquifer Id:
	RUNGE	80x 206	Mailing Address:	01	Aquifer Code:
Sampler(s): M &			Attention:	- 1	County Code:
Date: 6-2/-0/			_	KARNES	County:
Sample Number: 1049	36E	CITY OF RUNGE		B	State Well Number:
Type of Sample: (LCRA) HACH		Owner / Lessee	Send Results To: Owner / Lessee	ves / no	New Well:

LCRA Environmental Laboratory Services

Date: 17-Jul-01

CLIENT:

Lab ID:

Texas Water Development Board

B - Analyte detected in the associated Method Blank

* - Value exceeds Maximum Contaminant Level

Client Sample ID: 79-03-704

Lab Order:

0106204

File No: 16418

Project:

TWDB 00-01B 0106204-13

Collection Date: 06/21/2001 3:00:00 PM

Matrix: GROUNDWATER

Lub ibi							2			
Analyses	Storet	Result	PQL Qu	al Units	DF	BatchID	Date Analyzed			
CP METALS DI	SSOLVED		E200.7				Analyst: SW			
Calcium		133	0.204	mg/L	1.02	R9416	07/05/2001			
Magnesium		35.9	0.204	mg/L	1.02	R9416	07/05/2001			
Potassium		7.92	0.204	mg/L	1.02	R9416	07/05/2001			
Sodium		134	0.714	mg/L	1.02	R9416	07/05/2001			
CP METALS DI	SSOLVED		E200.7				Analyst: SW			
Boron		379	51.0	μg/L	1.02	R9418	07/05/2001			
Iron		ND	51.0	μg/L	1.02	R9418	07/05/2001			
Strontium		2750	20.4	μg/L	1.02	R9418	07/05/2001			
CPMS DISSOL	VED METALS		E200.8				Analyst: PJN			
Aluminum		ND	4.00	μg/L	1	R9366	07/03/2001			
Antimony		ND	1.00	μg/L	1	R9366	07/03/2001			
Arsenic		ND	2.00	μg/L	1	R9366	07/03/2001			
Barium		141	1.00	μg/L	1	R9366	07/03/2001			
Beryllium		ND	1.00	μg/L	1	R9366	07/03/2001			
Cadmium		ND	1.00	μ g /L	1	R9366	07/03/2001			
Chromium		ND	1.00	μg/L	1	R9366	07/03/2001			
Cobalt		ND	1.00	μg/L	1	R9366	07/03/2001			
Copper		ND	2.00	μg/L	1	R9366	07/03/2001			
Lead		ND	1.00	μg/L	1	R9366	07/03/2001			
Lithium		32.8	2.00	μg/L	1	R9366	07/03/2001			
Manganese		ND	1.00	µg/L	1	R9366	07/03/2001			
Molybdenum		ND	1.00	μg/L	1	R9366	07/03/2001			
Nickel		1.65	1.00	μg/L	1	R9366	07/03/2001			
Selenium		ND	4.00	μg/L	1	R9366	07/03/2001			
Thallium		ND	1.00	μg/L	1	R9366	07/03/2001			
Vanadium		8.29	1.00	μg/L	1	R9366	07/03/2001			
Zinc		175	4.00	μg/L	1	R9366	07/03/2001			
CATION/ANION Cation/Anion Bal		Balanced	CALCULATION	Date	1	R9482	Analyst: AM . 07/11/2001			
RADIOLOGICAL	_S		RADIOCHEM				Analyst: SB			
ALPHA, Gross		7.3		pci/L	1	R9444	07/02/2001			
BETA, Gross		10		pci/L	1	R9444	07/02/2001			
Qualifiers:	ND - Not Detected at the Re	porting Limit		S - Spike Re	S - Spike Recovery outside accepted recovery limits					
	J - Analyte detected below q	uanititation lin	nits	R - RPD outs	side accep	ted recovery	limits			

E - Value above quantitation range

LCRA Environmental Laboratory Services

Date: 17-Jul-01

CLIENT:

Texas Water Development Board

Client Sample ID: 79-03-704

Lab Order:

0106204

File No: 16418

Project:

Lab ID:

TWDB 00-01B

0106204-13

Collection Date: 06/21/2001 3:00:00 PM

Matrix: GROUNDWATER

Analyses	Storet	Result	PQL	Qual	Units	DF	BatchID	Date Analyze	d
ANIONS BY ION CHROMAT	OGRAPHY		E300					Analyst:	AMJ
Bromide Dissolved		1.42	0.100		mg/L	5	R9465B	07/10/2001	
Chloride Dissolved		340	5.00		mg/L	5	R9465B	07/10/2001	
Fluoride Dissolved		0.673	0.0500		mg/L	5	R9465B	07/10/2001	
Sulfate Dissolved		35 8	5.00		mg/L	5	R9465B	07/10/2001	
ALKALINITY			M2320 B					Analyst:	WM
Alkalinity, Phenolphthalein		ND			mg/L CaCO	1	R9253	06/27/2001	
Alkalinity, Total (As CaCO3)		222	2.00		mg/L CaCO	1	R9253	06/27/2001	
NITRATE AND NITRITE			E353.2					Analyst:	WR
Nitrogen, Nitrate & Nitrite		1.72	0.0200		mg/L	1	R9315H	06/29/2001	
SILICA			E370.1					Analyst:	WR
Silica, Dissolved (as SiO2)		31.7	0.500		mg/L	1	R9509A	07/12/2001	

Qualifiers:

ND - Not Detected at the Reporting Limit

J - Analyte detected below quanititation limits

B - Analyte detected in the associated Method Blank

* - Value exceeds Maximum Contaminant Level

S - Spike Recovery outside accepted recovery limits

R - RPD outside accepted recovery limits

E - Value above quantitation range

Newly Inventoried Well 452	1D Number: 22-2 Date: 2-7-06 Sampler(s): 0 C-14.1c.113	n Verification	pH2/6.5 4 or 10 = 10.00	SIP 95 6	1000 = 996 2000 = 191		Field Alkalinity Titration:	723 Start pH 4 4 GEnd pH	mL Sample Size mL Acid Phenol (> 8.3)	ed x 20	Phenol Alkalinity (82244): mg/L	Total Alkalinity (39086): 2 24 mg/L	Items Below Calculated Later From Results:	Hardness (as CaCO3): 4772 Balanced:				Data Entered By Sampler Into Databas (1965) / NO)
TWDB Water Quality Field Data Sheet	Address PO Bov 200	,	Well Name or #: 4 5 6 7 8 9 10 11	500ml filtered 1 Lunfiltered 1 Lunfiltered 2 Lunfiltered 3 Lunfiltered 4 Lunfiltered 5	lce → ₩2SO4 None NaOH (*) (HNO3) rNone None None None Nońe	Time Out: G. 20		W.L. remark:	Sampling Point: FAU	FIELD G.P.S. readings	Latitude 28°52 53.7"	Longitude: 97 ° 42 46.5-"	Casing Size: 10 "	(Filter pressure: hand pump / line / spring	Water Quality Stabilization Parameters Table (At least 3 readings @ 5 min. intervals)	95			
st FY06	19.63 KARN 2555	15 - 5 S Per	2 3	250ml filtered 500ml filtered 5		Time In Q O CO		POP		Well Use: PuBlic Supply	<u>.</u> S	'n	Steel	6838	Water Quality Stabilization P.	0820 0825	5000		
Gulf Coast FY06	SWN: County:	Aquifer Code: Aquifer Id:	-	250 ml unfiltered O.\e	Deuterium	Time In))	Water Level:	Pumping time:	Well Use:	Lift	Power	Casing Type:	Sample Time:		Time	Celsius Temn	Conductivity	



LABORATORY ANALYTICAL REPORT

Client:

Texas Water Development Board

Project:

TWDB

Lab ID:

C06080705-012

Client Sample ID: 7903704 (852)

Report Date: 09/19/06

Collection Date: 08/07/06 08:38

DateReceived: 08/15/06

Matrix: Aqueous

Analyses	Result	Units	Qualifiers	RL	MCL/ QCL	Method	Analysis Date / By
MAJOR IONS			1				
Alkalinity, Phenolphthalein as CaCO3	ND	mg/L		1		A2320 B	08/17/06 14:44 / th
Alkalinity, Total as CaCO3	284	mg/L	•	,1		A2320 B	08/17/06 14:44 / th
Bromide	1.7	mg/L		0.10		E300.0	08/19/06 01:51 / eli-b
Calcium	130	mg/L	•	0.5		E200.7	08/28/06 21:09 / ts
Chloride	353	mg/L		1		A4500-CI B	08/16/06 15:02 / jl
Fluoride	0.6	mg/L	•	0.1		A4500-F C	08/16/06 14:01 / th
Magnesium	35.0	mg/L		0.5		E200.7	08/28/06 21:09 / ts
Nitrogen, Nitrate+Nitrite as N	1.6	mg/L		.0.1		E353.2	08/21/06 13:22 / jal
Potassium	8.3	mg/L	•	0.5		E200.7	08/28/06 21:09 / ts
Silica	30.2	mg/L		0.1		E200.7	08/28/06 21:09 / ts
Sodium	131	mg/L		0.5		E200.7	08/28/06 21:09 / ts
Sulfate	39	mg/L		1		A4500-SO4 E	08/18/06 15:41 / bm
NON-METALS	,						
lodide	ND	mg/l.		0.10		E300.0	08/23/06 03:35 / eli-b
METALS - DISSOLVED							
Aluminum	ND	ug/L	·	1		E200.8	08/23/06 04:08 / sml
Antimony	ND	ug/L		1		E200.8	08/22/06 04:40 / bws
Arsenic	2	ug/L		1		E200.8	08/22/06 04:40 / bws
Barium	138	ug/L		1		E200.8	08/22/06 04:40 / bws
Beryllium	ND	ug/L		1		E200.8	08/22/06 04:40 / bws
Boron	360	ug/L.	•	100		E200.7	08/28/06 21:09 / ts
Cadmium	ND	ug/L		1		E200.8	08/22/06 04:40 / bws
Chromium	2	ug/L	•	1		E200.8	08/22/06 04:40 / bws
Cobalt	ND.	ug/L		1		E200.8	08/22/06 04:40 / bws
Copper	1	ug/L		1		E200.8	08/22/06 04:40 / bws
Iron	167	ug/L	•	30		E200.7	08/28/06 21:09 / ts
Lead	1	ug/L		1		E200.8	08/22/06 04:40 / bws
Lithium	42	ug/L		1		E200.8	08/26/06 13:53 / bws
Manganese	5	ug/L		1		E200.8	08/22/06 04:40 / bws
Molybdenum	1	ug/L		1		E200.8	08/22/06 04:40 / bws
Selenium	6	ug/L	•	1		E200.8	08/22/06 04:40 / bws
Strontium	2480	ug/L		1		E200,8	08/22/06 04:40 / bws
Thallium:	ND	ug/L.	•	1		E200.8	08/22/06 04:40 / bw:
Vanadium	9	ug/L		1		E200.8	08/22/06 04:40 / bws
Zinc	251	ug/L	·	1		E200.8	08/22/06 04:40 / bws
RADIONUCLIDES - DISSOLVED							
Gross Alpha	9.0	pCi/L	-	1.0		E900,0	09/03/06 00:16 / rs
Gross Alpha precision (±)	0.8	pCi/L				E900.0	09/03/06 00:16 / rs
Radium 226	0.5	pCi/L	•	0.2		E903.0	09/11/06 10:44 / trs

Report

RL - Analyte reporting limit.

Definitions: QCL - Quality control limit.

MCL - Maximum contaminant level.

ND - Not detected at the reporting limit.



LABORATORY ANALYTICAL REPORT

Client:

Texas Water Development Board

Project:

TWDB

Lab ID:

C06080705-012

Client Sample ID: 7903704 (852)

C06080705-012

Report Date: 09/19/06

Collection Date: 08/07/06 08:38

DateReceived: 08/15/06

Matrix: Aqueous

Analyses	Result	Units	Qualifiers	RL	MCL/ QCL	Method	Analysis Date / By
RADIONUCLIDES - DISSOLVED			*				
Radium 226 precision (±)	0.2	pCi/L				E903.0	09/11/06 10:44 / trs
Radium 228	ND	pCi/L		1.0		RA-05	08/29/06 11:43 / pj
Uranium 234	3.5	pCi/L		0.2		E907.0	09/05/06 11:00 / df
Uranium 234 precision (±)	0.8	pCi/L				E907.0	09/05/06 11:00 / df
Uranium 235	ND	pCi/L		0.2		E907.0	09/05/06 11:00 / df
Uranium 238	3.0	pCi/L		0.2		E907.0	09/05/06 11:00 / df
Uranium 238 precision (±)	0.7	pCi/L				E907.0	09/05/06 11:00 / df
DATA QUALITY							
A/C Balance (± 5)	-4.00	%				Calculation	08/31/06 15:48 / cp
Anions	16.6	meq/L				Calculation	08/31/06 15:48 / cp
Cations	15.3	meq/L	19			Calculation	08/31/06 15:48 / cp

Report

RL - Analyte reporting limit.

Definitions: QCL - Quality control limit.

MCL - Maximum contaminant level.

ND - Not detected at the reporting limit.



BETA ANALYTIC INC.

DR. M.A. TAMERS and MR. D.G. HOOD

UNIVERSITY BRANCH 4985 S.W. 74 COURT MIAMI, FLORIDA, USA 33155 PH: 305/667-5167 FAX: 305/663-0964 E-MAIL: beta@radiocarbon.com

REPORT OF RADIOCARBON DATING ANALYSES

Dr. Sheryl Garling

Report Date: 9/29/2006

Energy Laboratories, Inc.

Material Received: 8/28/2006

Sample Data

Apparent C14 Age (fraction modern)

C13/C12

Ratio

Beta - 220278

17320 +/- 90 BP

(Fmdn 0.1157 +/- 0.0013)

-10.6 o/oo

SAMPLE: C06080938-001C

ANALYSIS: AMS-Standard delivery

MATERIAL/PRETREATMENT: (water DIC): carbonate precipitation

MATERIAL/PRETREATMENT: (water DIC): carbonate precipitation

MATERIAL/PRETREATMENT: (water DIC): carbonate precipitation

Beta - 220279

2950 +/- 40 BP

-10.9 0/00

SAMPLE: C06080938-002C

ANALYSIS: AMS-Standard delivery

(Fmdn 0.6923 +/- 0.0034)

78 - 39 - 804

Beta - 220280

26580 +/- 170 BP

-10.9 o/oo

SAMPLE: C06080938-003C

ANALYSIS: AMS-Standard delivery

(Fmdn 0.0365 +/- 0.0008)

78-48-302

12160 +/- 70 BP

-7.2 o/oo

Beta - 220281

(Fmdn 0.2200 +/- 0.0019)

SAMPLE: C06080938-004C

ANALYSIS: AMS-Standard delivery

Karnes

MATERIAL/PRETREATMENT: (water DIC): carbonate precipitation

79-03-704

Beta - 220282

16910 +/- 90 BP

-8.3 o/oo

SAMPLE: C06080938-005C

(Fmdn 0.1218 +/- 0.0014)

79-49-505

ANALYSIS: AMS-Standard delivery

MATERIAL/PRETREATMENT: (water DIC): carbonate precipitation

Dates are reported as RCYBP (raduicarbon years before present, "present" = 1950A.D.). By International convention, the modern reference standard was 95% of the C14 content of the National Bureau of Standards' Oxalic Acid & calculated using the Libby C14 half life (5568 years). Quoted errors represent 1 standard deviation statistics (68% probability) & are based on combined measurements of the sample, background, and modern reference standards.

Measured C13/C12 ratios were calculated relative to the PDB-1 international standard and the RCYBP ages were normalized to -25 per mil. If the ratio and age are accompanied by an (*), then the C13/C12 value was estimated, based on values typical of the material type. The quoted results are NOT calibrated to calendar years. Calibration to calendar years should be calculated using the Conventional C14 age.

Client: ENERGY LABORATORIES, INC.

Purchase Order: 1643

Recvd: 06/08/28

Contact: S. Dobos 307/235-0515 2393 Salt Creek Hwy, PO Box 3258

Job# : 2251

Final: 06/10/27

Casper, WY 82602 07012

	*				0,0	1
Cust LABEL INFO	JOB.SX	REFDATE	QUANT	ELYS	TU	eTU
C06080938-001B	2251.01	060803	1000	275	-0.01	0.09
C06080938-002B	2251.02	060803	1000	275	0.07	0.09
C06080938-003B	2251.03	060804	1000	275	0.07	0.09
C06080938-004B	2251.04	060807	1000	275	0.10	0.09
C06080938-005B	2251.05	060803	1000	275	0.00	0.09
C06080938-006B	2251.06	060803	1000	275	-0.04	0.09
C06080938-007B	2251.07	060807	1000	275	3.94	0.13
C06080938-008B	2251.08	060808	1000	275	0.08	0.09
C06080938-009B	2251.09	060808	1000	275	-0.08	0.09
C06080938-010B	2251.10	060808	1000	275	-0.01	0.09
C06080938-011B	2251.11	060809	1000	275	-0.04	0.09
C06080938-012B	2251.12	060809	1000	275	0.11	0.09
000000000000000000000000000000000000000						

Sample ID	Client Sample ID	Collect Date	Receive Da	te Matrix	Test
C06080938-001	7848403 (847)	08/03/06 9:08	08/18/06	Aqueous	Subcontracted, Beta Analytic Subcontracted, Tritium Laboratory Subcontracted, ZymaX
C06080938-002	7839804 (848)	08/03/06 11:10	08/18/06	Aqueous	Same As Above
C06080938-003	7848302 (851)	08/04/06 9:05	08/18/06	Aqueous	Same As Above
C06080938-004	7903704 (852)	08/07/06 8:38	08/18/06	Aqueous	Same As Above
C06080938-005	7949505 (849)	08/03/06 14:20	08/18/06	Aqueous	Same As Above
C06080938-006	7957206 (850)	08/03/06 16:08	08/18/06	Aqueous	Same As Above
C06080938-007	7902505 (853)	08/07/06 10:10	08/18/06	Aqueous	Same As Above
C06080938-008	8035807 (854)	08/08/06 9:28	08/18/06	Aqueous	Same As Above
C06080938-009	8035808 (855)	08/08/06 10:28	08/18/06	Aqueous	Same As Above
C06080938-010	7912703 (856)	08/08/06 14:18	08/18/06	Aqueous	Same As Above
C06080938-011	8304210 (857)	08/09/06 9:05	08/18/06	Aqueous	Same As Above
C06080938-012	7960702 (858)	08/09/06 11:40	08/18/06	Aqueous	Same As Above

There were no problems with the analyses and all data for associated QC met EPA or laboratory specifications except where noted in the Case Narrative or Report.

If you have any questions regarding these tests results, please call.

Report Approved By: R.a. Reaching



REPORT OF ANALYTICAL RESULTS

Client: C Wagner

Energy Laboratories, Inc. 2393 Salt Creek Hwy Casper, WY 82602

Lab Number:

40210

Received:

8/24/2006

Matrix:

Water

Sample Description: Project:

See Below

	Project Number: Collected by: Client		Analyze Method		
		δ ³	⁴ S δ ¹⁸ O	4993	2 50982
Γ	LAB	SAMPLE		δ ³⁴ S	δ ¹⁸ Ο
	NUMBER	DESCRIPTION		%	% o
	40210-1	C06080938-001	A	12.4	11.3
	40210-2	C06080938-002		13.3	6.8
	40210-3	C06080938-003		NR	NR
	40210-4	C06080938-004		11.0	4.5
	40210-5	C06080938-005		NR	NR
	40210-6	C06080938-006		12.4	6.6
	40210-7	C06080938-007		10.2	4.7
	40210-8	C06080938-008		19.8	17.0
	40210-9	C06080938-009		17.1	16.7
	40210-10	C06080938-010		9.5	5.7
	40210-11	C06080938-011		11.8	8.8
-	40210-12	C06080938-012	.A	12.4	6.6
		£			
	Analytical Precision			0.3	0.4
	(1-sigma)				
npie i	Client Sample ID	Collect Date Rec	ceive Date	Matrix Test	
	8-001 7848403 (847)	08/03/06 9:08 08/	18/06 Aque	Subcontrac	cted, Beta Analytic cted, Tritium Laboratory cted, ZymaX
608093	8-002 7839804 (848)	08/03/06 11:10 08/	18/06 Aque	ous Same As A	bove
808093	8-003 7848302 (851)	08/04/06 9:05 08/	18/06 Aque	ous Same As A	bove
6080938	8-004 7903704 (852)	08/07/06 8:38 08/	18/06 Aque	ous Same As A	bove
080938	8-005 7949505 (849)	08/03/06 14:20 08/	18/06 Aque	ous Same As A	bove
	8-006 7957206 (850)	08/03/06 16:08 08/	18/06 Aque	ous Same As A	bove
080938	8-007 7902505 (853)	08/07/06 10:10 08/	18/06 Aque	ous Same As A	bove
080938	8-008 8035807 (854)	08/08/06 9:28 08/	18/06 Aque	ous Same As A	bove
	8-009 8035808 (855)	08/08/06 10:28 08/	18/06 Aque	ous Same As A	bove
080938	3-010 7912703 (856)	08/08/06 14:18 08/	18/06 Aque	ous Same As A	bove
	3-011 8304210 (857)	08/09/06 9:05 08/	18/06 Aque	ous Same As A	bove
	3-012 7960702 (858)	08/09/06 11:40 08/1			

There were no problems with the analyses and all data for associated QC met EPA or laboratory specifications except where noted in the Case Narrative or Report.



REPORT OF ANALYTICAL RESULTS

Client: C Wagner Energy Laboratories, Inc. 2393 Salt Creek Hwy Casper, WY 82602

Received: Matrix:

Lab Number:

40210

08/24/06 Water

Project:

Project Number:

Collected by:

Client

Sample Description:

See Below

Analyzed: Method:

09/30/06 **CF-IRMS**

	δ ¹⁸ Ο	δD	50790	50791
LAB	SAMPLE		δ ¹⁸ O	δD
NUMBER	DESCRIPTION		%	‰
40210-1	C06080938-001A		-5.3	-26
40210-2	C06080938-002A		-4.2	-21
40210-3	C06080938-003A		-4.3	-25
40210-4	C06080938-004A		-4.7	-25
40210-5	C06080938-005A		-4.5	-26
40210-6	C06080938-006A		-4.0	-24
40210-7	C06080938-007A		-3.9	-21
40210-8	C06080938-008A		-4.0	-20
40210-9	C06080938-009A	*	-3.7	-20
40210-10	C06080938-010A		-4.1	-22
40210-11	C06080938-011A		-4.1	-21
40210-12	C06080938-012A		-3.9	-21
Analytical Precision		¥.	0.3	1.0
(1-sigma)				

Sample ID	Client Sample ID	Collect Date	Receive Date	e Matrix	Test
C06080938-001	7848403 (847)	08/03/06 9:08	08/18/06 A	Aqueous	Subcontracted, Beta Analytic Subcontracted, Tritium Laboratory Subcontracted, ZymaX
C06080938-002	7839804 (848)	08/03/06 11:10	08/18/06 A	queous	Same As Above
C06080938-003	7848302 (851)	08/04/06 9:05	08/18/06 A	queous	Same As Above
C06080938-004	7903704 (852)	08/07/06 8:38	08/18/06 A	queous .	Same As Above
C06080938-005	7949505 (849)	08/03/06 14:20	08/18/06 A	Aqueous	Same As Above
C06080938-006	7957206 (850)	08/03/06 16:08	08/18/06 A	Aqueous	Same As Above
C06080938-007	7902505 (853)	08/07/06 10:10	08/18/06 A	Aqueous	Same As Above
C06080938-008	8035807 (854)	08/08/06 9:28	08/18/06 A	Aqueous	Same As Above
C06080938-009	8035808 (855)	08/08/06 10:28	08/18/06 A	Aqueous	Same As Above
C06080938-010	7912703 (856)	08/08/06 14:18	08/18/06 A	Aqueous	Same As Above
C06080938-011	8304210 (857)	08/09/06 9:05	08/18/06 A	Aqueous	Same As Above
C06080938-012	7960702 (858)	08/09/06 11:40	08/18/06 A	Aqueous	Same As Above

There were no problems with the analyses and all data for associated QC met EPA or laboratory specifications except where noted in the Case Narrative or Report.





Texas Water Development Board

5/20/1997

5/27/2011

Well Basic Details **GWDB** Reports and Downloads Scanned Documents State Well Number 7903705 Well Type Withdrawal of Water Well Use Unused County Karnes River Basin San Antonio Water Level Observation Miscellaneous Measurements Water Quality Available **Groundwater Management Area** Yes L - South Central Texas Regional Water Planning Area Pump Evergreen UWCD Pump Depth (feet below land surface) **Groundwater Conservation** District **Power Type** Latitude (decimal degrees) 28.881667 **Annular Seal Method** 28° 52' 54" N Latitude (degrees minutes seconds) **Surface Completion** -97.713056 Longitude (decimal degrees) Owner City of RungeWell #1 Longitude (degrees minutes seconds) 097° 42' 47" W Unknown Driller **Coordinate Source** +/- 1 Second Other Data Available **Aquifer Test** 122JSPR - Jasper Aquifer **Aquifer Code** Well Report Tracking Number **Gulf Coast** Aquifer **Plugging Report Tracking Number Aquifer Pick Method** U.S. Geological Survey Site 310 Land Surface Elevation (feet above Number G1280003A Texas Commission on Interpolated From Topo Map Land Surface Elevation Method **Environmental Quality Source Id** Well Depth (feet below land surface) **Groundwater Conservation District Well Number Well Depth Source** Another Government Agency E-40 Owner Well Number **Drilling Start Date** Other Well Number 0/0/1914 **Drilling End Date Previous State Well Number**

Remarks Well E-40 in TBWE B-6007. Reported yield 67.5 GPM in 1956. Aquifer test results in TWDB R-98. No test data in TWDB files.

Reporting Agency

Last Update Date

Created Date

Casing - No Data

Borehole Completion

Well Tests

Drilling Method

Test Date	Test Type	Yield (gallons per minute)	Drawdown (ft.)	Test Hours
0/0/1956	Unknown	68		0
1956-01-20	Unknown	68		0

Cable Tool





Lithology	.ithology									
Top Depth (ft.)	Bottom Depth (ft.)	Description								
0	4	SURFACE SOIL								
4	66	HARD YELLOW CLAY								
66	67	ROCK								
67	96	HARD CLAY								
96	116	CLAY AND BOULDERS								
116	136	CLAY								
136	154	HARD CLAY AND BOULDERS								
154	188	SAND								
188	212	CLAY								


Annular Seal Range - No Data

Borehole - No Data Plugged Back - No Data

Filter Pack - No Data Packers - No Data







Status Code	Date	Time	Water Level (ft. below land surface)	Change value in () indicates rise in level	Water Elevation (ft. above sea level)		Measuring Agency	Method	Remark ID	Comments
Р	12/20/1955		93.3		216.7	1	Other or Source of Measurement Unknown	Unknown		

Code Descriptions

Status Code Status Description

Р

Publishable





Water Quality Analysis

Sample Date: 10/0/1955 Sample Time: 0000 Sample Number: 1 Collection Entity: U.S. Geological Survey

Sampled Aquifer: Jasper Aquifer

Analyzed Lab: Reliability: From a report; unknown sample collection & preservation

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		221.31	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		270.07	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		300	ug/L	
00910	CALCIUM (MG/L)		141	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		388	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.5	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		491	mg/L as CACO 3	
01045	IRON, TOTAL (UG/L AS FE)		200	ug/L	
00920	MAGNESIUM (MG/L)		34	mg/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		5.6	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		7.6	SU	
00937	POTASSIUM, TOTAL (MG/L AS K)		8.5	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		35	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.79		
00932	SODIUM, CALCULATED, PERCENT		38	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		142	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1670	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		36	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		923	mg/L	

^{*} Value may not display all significant digits for parameter in results, check Scanned Documents for laboratory paperwork..





GWDB DISCLAIMER: Except where noted, all of the information provided in the Texas Water Development Board (TWDB) Groundwater Database (https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp) is believed to be accurate and reliable; however, the TWDB assumes no responsibility for any errors appearing in rules or otherwise. Further, TWDB assumes no responsibility for the use of the information provided. PLEASE NOTE that users of these data are responsible for checking the accuracy, completeness, currency and/or suitability of all information themselves. TWDB makes no guarantees or warranties as to the accuracy, completeness, currency, or suitability of the information provided via the Groundwater Database (GWDB). TWDB specifically disclaims any and all liability for any claims or damages that may result from providing GWDB data or the information it contains. For additional information or answers to questions concerning the TWDB GWDB, contact the Groundwater Data Team at GroundwaterData@twdb.texas.gov.

TEXAS DEPARTMENT OF WATER RESOURCES


WELL SCHEDULE

	Ockrille Aquifer(s) Sandstane Project No. = -40 s	State Well No. 79	-03-705
	Field No./Owner's Well No.	County Karnes	(228)
Ι,	Location:t,t,Section,Block,Survey	, lat. 28 <u>-</u> 52-53	N. Long. 97-43-46 K
2.	Owner: City of Bunge Address:		
	Tenant (other): Address:		
	Driller:Address:		
3.	Land Surface Elevation: 300 ft. above msl determined by		
	Drilled: 19 14; Dug, Cable Tool, Rotary, Air,		
	Depth: Rept. 156 ft. Heasft.		PIPE & WELL SCREEN
6.	Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed	Diam. Type	ft. toft.
	Pump: Mfr. Type Jurbine	(in.)	from to
	No. Stages, Bowls DiamIn., Settingft.		
	Column Diamin., Length Tailpipeft.		
8.	Motor: Mfr. Fuel E)&C HP. 15		
	Yield: Flowgpm, Pumpgpm, Heas., Rept., EstDate		
10.	Performance Test: DateLength of TestMade by		
	Static Levelft. Pumping Levelft. Drawdownft.		
	Productiongpm Specific Capacitygpm/ft.	ļ	
11.	Quality: (Remarks on taste, odor, color, etc.)	 	
	Analyses		
70	P Date LO -55 Laboratory TDS Sp Cond	ļ	
	DateLaboratoryTDSSp Cond		
12.	Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log,		
	Formation Samples, Geophysical Log(s) (type)		
13.	Water Level(s): 93 3 ft. rest. 12 120 1955 above	_which isf	above below Land Surface
	ft. rept 19 above		
	Use: Dom., Stock, Public Supply, Ind., Irr., Observation, Other (Test Hole, Oil		
15.	Recorded by: D. JonesSource of data: B - 6007	Date:_	7/-30/21
16.	Remarks:		
500705**		h£Gŧ	TV:
17.	Location or Sketch: Next Page	NOV 1	8 1982
		CB	

W/L Obs. Well W/Q Obs. Well State Well No. 79 - 03-705

T S DEPARTMENT OF WATER RE 3CES

BY	_DATE	DIVISION				SHEET NO	_OF
CHKD	DATE	JOB NAME _	128		79-03-705		
				IOR NO	E-40	PROG CODE#	= 1



Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

Texas Department of Health Laboratories

т	DWR ONLY	
Organization No	Lab No.	
Work No.		

1100 West 49th Street Austin, Texas 78756	Work No
CHEMICAL WATER AN	170 Kupuss
Send report to:	County
Data Collection and Evaluation Section Texas Department of Water Resources P.O. Box 13087 Austin, Texas 78711	State Well No. Well No.
Location	Sample No. By
Source (type of well)Owner	
Date Drilled Depth ft. WBF	—— IIII
Sempled after pumping hrs. Yield Point of collection	
Use Remarks	
(FOR LABORATORY USE ONLY) CHEMICAL AN Laboratory No Date Received	KEY PUNCHED
MG/L ME/L	MG/L ME/L
Silica · · · 00955 · · ·	Carbonate 00445
Calcium · · · 00915 · · ·	Bicsrbonate · 00440 · · 270
Magnesium · · 00925 · · · 34	Sulfate 00945 36
Sodium 00929 1/4/2	Chloride · · 00940 · · 309
Total	Fluoride · · 00951 ·
□ Potessium · 00937 · · ·	Nitrete · · · 71850 ·
□ Manganese · 01055 · · · · · · · · · · · · · · · · · ·	pH · · · · 00403 · · Total
□ Boron 01022	Dissolved Solids (residue at 180°C) · 70300 ·
□ Total Iron · 01045 · · · □ □ RSC □	Phenolphthelein Alkalinity as C aCO ₃ · 00415 · .
(other) MG/L	Total Alkalinity as C sCO3 00410
Specific Conductance (micromhos/cm³) · 00095 · 1670	Total Hardness as C aCO ₃ · · · · 00900 · ·
Diluted Conductance (micromhos/cm ³)	Ammonia - N · · · · · · · · · 00610 ·
" items will be analyzed if checked.	Nitrite - N · · · · · · · · · · · · · · · · · ·
¹ The bicarbonate reported in this analysis can be converted by	Nitrate - N

Organic Nitrogen


__ Checked By _

Analyst ...

computation (multiplying by 0.4917) to an equivalent amount of carbonate, and the carbonate figure used in the computation of dissolved solids.

Nitrogen cycle requires separate sample.

Total Iron and Manganese require separate sample.







GWDB Reports and Downloads

Well Basic Details

Scanned Documents

State Well Number	7903707	Well Type	Withdrawal of Water
County	Karnes	Well Use	Public Supply
River Basin	San Antonio	Water Level Observation	None
Groundwater Management Area	15	Water Quality Available	Yes
Regional Water Planning Area	L - South Central Texas	Pump	Submersible
Groundwater Conservation District	Evergreen UWCD	Pump Depth (feet below land surface) Power Type	Electric Motor
Latitude (decimal degrees)	28.881111		Electric Motor
Latitude (degrees minutes seconds)	28° 52' 52" N	Annular Seal Method	
Longitude (decimal degrees)	-97.712778	Surface Completion	Other C. D.
Longitude (degrees minutes seconds)	097° 42' 46" W	Owner	City of Runge
Coordinate Source	+/- 1 Second	Driller	Layne-Texas
Aquifer Code	121EVGL - Evangeline Aquifer	Other Data Available	Drillers Log
Aquifer	Gulf Coast	Well Report Tracking Number	
Aguifer Pick Method		Plugging Report Tracking Number	
Land Surface Elevation (feet above sea level)	310	U.S. Geological Survey Site Number	
Land Surface Elevation Method	Interpolated From Topo Map	Texas Commission on Environmental Quality Source Id	G1280003C
Well Depth (feet below land surface)	211	Groundwater Conservation	
Well Depth Source	Driller's Log	District Well Number	
Drilling Start Date		Owner Well Number	
Drilling End Date	1/31/1977	Other Well Number	
Drilling Method	Mud (Hydraulic) Rotary	Previous State Well Number	
Borehole Completion		Reporting Agency	Texas Water Development Board
		Created Date	5/20/1997
		Last Update Date	6/6/1997

Remarks

Casing

Diameter (in.)	Casing Type	Casing Material	Schedule	Gauge	Top Depth (ft.)	Botton	n Depth (ft.)
12	Blank	Steel				0	145
8	Blank	Steel				0	155
8	Screen	Stainless Steel			1	55	190
8	Blank	Steel			1	90	195
8	Screen	Stainless Steel			1	95	200
8	Blank	Steel			2	00	208
8	Screen	Stainless Steel			2	.08	210

Well Tests - No Data

Lithology - No Data

Annular Seal Range - No Data

Borehole - No Data

Plugged Back - No Data





Filter Pack - No Data	Packers - No Data	





Water Level Measurements	-
No Data Available	***************************************





Water Quality Analysis

Sample Date: 3/14/1977

Sample Time:

0000

Sample Number:

Collection Entity: Registered Water Well Driller

Sampled Aquifer:

Evangeline Aquifer

Analyzed Lab: Pope Testing Lab

Reliability: Reliability unknown or not available

Collection Remarks:

No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		248	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		302.65	mg/L	
00910	CALCIUM (MG/L)		123	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		294	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.6	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		418	mg/L as CACO 3	
01045	IRON, TOTAL (UG/L AS FE)		100	ug/L	
00920	MAGNESIUM (MG/L)		27	mg/L	
01055	MANGANESE, TOTAL (UG/L AS MN)		0	ug/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		5.6	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		7.2	SU	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		26	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.68		
00932	SODIUM, CALCULATED, PERCENT		39	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)	calculate d		mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1440	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		0	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		751	mg/L	





Water Quality Analysis

Sample Date: 9/15/1983

Sample Time:

0000

Sample Number: 1

Collection Entity: Texas Water Development Board

Sampled Aquifer:

Evangeline Aquifer

Analyzed Lab: Texas Department of Health

Reliability: Collected from pumped well, but not filtered or preserved

Collection Remarks:

No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		209	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		255.05	mg/L	
00910	CALCIUM (MG/L)		118	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		314	mg/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.6	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		413	mg/L as CACO 3	
00920	MAGNESIUM (MG/L)		29	mg/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		5.89	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		8	SU	
00937	POTASSIUM, TOTAL (MG/L AS K)		9	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00955	SILICA, DISSOLVED (MG/L AS SI02)		61	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		2.76		
00932	SODIUM, CALCULATED, PERCENT		40	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		129	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1639	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		36	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		26	С	
70301	TOTAL DISSOLVED SOLIDS, SUM OF CONSTITUENTS (MG/L)		827	mg/L	





Water Quality Analysis

Sample Date: 5/23/1990

Sample Time:

1540

Sample Number: 1

Collection Entity: Texas Water Development Board

Sampled Aquifer:

Evangeline Aquifer

Analyzed Lab: Texas Department of Health

Reliability: Sampled using TWDB protocols

Collection Remarks:

No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39740	2,4,5-T, TOTAL, UG/L	<	5	ug/L	
39045	2,4,5-TP INCLUDES ACIDS & SALTS IN WATER, UG/L	<	5	ug/L	
39730	2,4-D, TOTAL, UG/L	<	20	ug/L	
34253	A-BHC-ALPHA, TOTAL, UG/L	<	0.03	ug/L	
77825	ALACHLOR, TOTAL, UG/L	<	0.1	ug/L	
39330	ALDRIN, TOTAL, UG/L	<	0.2	ug/L	
39086	ALKALINITY FIELD DISSOLVED AS CACO3		220	mg/L as CACO 3	
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		234	mg/L as CACO 3	
01106	ALUMINUM, DISSOLVED (UG/L AS AL)	<	50	ug/L	
01000	ARSENIC, DISSOLVED (UG/L AS AS)	<	10	ug/L	
82052	BANVEL (DICAMBA), TOTAL, UG/L	************************************	1	ug/L	
01005	BARIUM, DISSOLVED (UG/L AS BA)		151	ug/L	
34255	B-BHC-BETA, TOTAL, UG/L		0.03	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		285.56	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		610	ug/L	
71870	BROMIDE, DISSOLVED, (MG/L AS BR)		0.17	mg/L	
01025	CADMIUM, DISSOLVED (UG/L AS CD)	•	10	ug/L	
00915	CALCIUM, DISSOLVED (MG/L AS CA)		107	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
39350	CHLORDANE, TOTAL, UG/L	<	0.2	ug/L	
00941	CHLORIDE, DISSOLVED (MG/L AS CL)		302	mg/L	
01030	CHROMIUM, DISSOLVED (UG/L AS CR)	.<	< 20	ug/L	
01040	COPPER, DISSOLVED (UG/L AS CU)		< 20	ug/L	
39770	DACTHAL (DCPA), TOTAL, UG/L		< 0.05	ug/L	
39360	DDD, TOTAL, UG/L		0.15	ug/L	
39365	DDE, TOTAL, UG/L		0.1	ug/L	
39370	DDT, TOTAL, UG/L	•	< 0.15	ug/L	
46323	DELTA-BHC, TOTAL, UG/L		< 0.03	ug/L	
39570	DIAZINON, TOTAL, UG/L		< 0.3	ug/L	
39380	DIELDRIN, TOTAL, UG/L		< 0.1	ug/L	
81403	DURSBAN (CHLOROPYRIFOS), TOTAL, UG/L		< 0.6	ug/L	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
34351	ENDOSULFAN SULFATE, TOTAL, UG/L	<	0.2	ug/L	
39388	ENDOSULFAN, TOTAL, UG/L	<	0.2	ug/L	
39390	ENDRIN, TOTAL, UG/L	<	0.2	ug/L	
46315	ETHYL PARATHION, TOTAL, UG/L	<	0.25	ug/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.68	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		401	mg/L as CACO 3	
39420	HEPTACHLOR EPOXIDE, TOTAL, UG/L	<	0.06	ug/L	
39410	HEPTACHLOR, TOTAL, UG/L	<	0.02	ug/L	
39700	HEXACHLOROBENZENE (HCB), TOTAL, UG/L	<	0.02	ug/L	
71865	IODIDE (MG/L AS I)	<	0.1	mg/L	
01046	IRON, DISSOLVED (UG/L AS FE)	<	20	ug/L	
01049	LEAD, DISSOLVED (UG/L AS PB)	<	50	ug/L	
39782	LINDANE, TOTAL, UG/L	<	0.03	ug/L	
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)		32	mg/L	
39530	MALATHION, TOTAL, UG/L	<	0.4	ug/L	
01056	MANGANESE, DISSOLVED (UG/L AS MN)	<	20	ug/L	
71890	MERCURY, DISSOLVED (UG/L AS HG)	<	0.2	ug/L	
39480	METHOXYCHLOR, TOTAL, UG/L	<	0.5	ug/L	
39600	METHYL PARATHION, TOTAL, UG/L	<	0.25	ug/L	
01060	MOLYBDENUM, DISSOLVED (UG/L AS MO)	<	20	ug/L	
00618	NITRATE NITROGEN, DISSOLVED (MG/L AS N)		1.37	mg/L as N	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		6.06	mg/L as NO3	
00613	NITRITE NITROGEN, DISSOLVED (MG/L AS N)	<		mg/L as N	
00608	NITROGEN, AMMONIA, DISSOLVED (MG/L AS N)	<		mg/L as N	
00623	NITROGEN, KJELDAHL, DISSOLVED (MG/L AS N)	<	0.1	mg/L as N	
00090	OXIDATION REDUCTION POTENTIAL (ORP), MILLIVOLTS		234.7	MV	
39488	PCB - 1221, TOTAL, UG/L	<	1	ug/L	
39492	PCB - 1232, TOTAL, UG/L	<	0.8	ug/L	
39496	PCB - 1242, TOTAL, UG/L	<	0.5	ug/L	
39500	PCB - 1248, TOTAL, UG/L	<	0.5	ug/L	
39504	PCB - 1254, TOTAL, UG/L	<	8.0	ug/L	
39508	PCB - 1260, TOTAL, UG/L	<	0.8	ug/L	
81649	PCB - 1262 (ARACLOR), TOTAL, UG/L	<	0.8	ug/L	
34671	PCB- 1016, TOTAL, UG/L	<	0.6	ug/L	
39032	PENTACHLOROPHENOL (PCP), TOTAL, UG/L	<	2	ug/L	
00400	PH (STANDARD UNITS), FIELD		7.02	su	
00671	PHOSPHORUS, DISSOLVED ORTHOPHOSPHATE (MG/L AS P)		0.01	mg/L as P	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39720	PICLORAM, TOTAL, UG/L	<	3	ug/L	
82068	POTASSIUM 40 (K-40), DISSOLVED, PC/L		6.3	PC/L	
00935	POTASSIUM, DISSOLVED (MG/L AS K)		9	mg/L	
09503	RADIUM 226, DISSOLVED, PC/L		0.6	PC/L	0.1
81366	RADIUM 228, DISSOLVED (PC/L AS RA-228)		0.4	PC/L	1.8
82305	RADON 222, DISSOLVED, PC/L		154	PC/L	6
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
01145	SELENIUM, DISSOLVED (UG/L AS SE)		4	ug/L	
00955	SILICA, DISSOLVED (MG/L AS SI02)		29	mg/L as SIO2	
01075	SILVER, DISSOLVED (UG/L AS AG)	<	10	ug/L	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		3.03		
00932	SODIUM, CALCULATED, PERCENT		43	PCT	
00930	SODIUM, DISSOLVED (MG/L AS NA)		139	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1478	MICR	
01080	STRONTIUM, DISSOLVED (UG/L AS SR)		2300	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)		32	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		25	С	
26403	THORIUM, NATURAL, DISSOLVED PC/L		-0.2	PC/L	0.4
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		799	mg/L	
39400	TOXAPHENE, TOTAL, UG/L	<	5	ug/L	
22703	URANIUM, NATURAL, DISSOLVED (UG/L AS U)		6	ug/L	
01085	VANADIUM, DISSOLVED (UG/L AS V)		20	ug/L	
01090	ZINC, DISSOLVED (UG/L AS ZN)		121	ug/L	

^{*} Value may not display all significant digits for parameter in results, check Scanned Documents for laboratory paperwork..

GWDB DISCLAIMER: Except where noted, all of the information provided in the Texas Water Development Board (TWDB) Groundwater Database (https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp) is believed to be accurate and reliable; however, the TWDB assumes no responsibility for any errors appearing in rules or otherwise. Further, TWDB assumes no responsibility for the use of the information provided. PLEASE NOTE that users of these data are responsible for checking the accuracy, completeness, currency and/or suitability of all information themselves. TWDB makes no guarantees or warranties as to the accuracy, completeness, currency, or suitability of the information provided via the Groundwater Database (GWDB). TWDB specifically disclaims any and all liability for any claims or damages that may result from providing GWDB data or the information it contains. For additional information or answers to questions concerning the TWDB GWDB, contact the Groundwater Data Team at GroundwaterData@twdb.texas.gov.

TEXAS DEPARTMENT OF WATER RESOURCES WELL SCHEDULE

	WELL SCHEDULE		38	17- 343	3	0.9
	Aquifer(s) Project No	State We	11 No. 79	-03	707	
	Field No./Owner's Well No3					
1.	Location: 4, 4,Section ,Block ,Survey					ı
2.	Owner: City of Runge Address: Bex 20	6R	unge .	Tex. 7	8151_	
	Tenant (other): de Address: d	0				
	Driller: Layne- Taxas Address: P.O. Box	546.	5 How	ton Tex	77011	
3.	Land Surface Elevation: 309 ft. above msl determined by					
4.	Drilled: 01/3119_77_; Dug, Cable Tool, Rotary, Air,					
5.	Depth: Rept. 211ft. Measft.		SING, BLANI ted From	Ft. to	SCREEN ft.	
6.	Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed	Diam.		Setting		
7.	Pump: Mfr. Type / C.r.b.	(in.)	74.	from	to	
	No. Stages, Bowls Diamin., Settingft.		Steel	+2.0	14.5	
	Column Diamin., Length Tailpipeft.	8-3		+1.0	310	
	Motor: MfrFuelHP	5.		100-		
	Yield: Flowgpm, Pump 125 gpm, Meas., Rept., EstDate3/14/77	Dere	en	155	190	
10.	Performance Test: Date 3/14/7] Length of Test /2 hrs. Made by Legge Texas			195	200	
	Static Level¶&_o_ft. Pumping Level <u>J\$5_0</u> ft. Drawdown_\$7.0_ft.					
	Productiongpm Specific Capacitygpm/ft.			<u> </u>		
11.	Quality: (Remarks on taste, odor, color, etc.)	-				
	Analyses			<u> </u>		
_	Date_03/14/77_Laboratory_Ed ne Wood_TDSSp Cond	· -				
	8°Date 09 15/83 LaboratoryTOS Sp Cond			<u> </u>		
12.	Other data available (as circled): Pumping Test Ower & Yield Test Orillers Log,					
	Formation Samples, Geophysical Log(s) (type)					
3.	Water Level(s): 28.0 ft. (type) above L.S.D	_which	is f	below Land	Surface	
	ft. rept. 19 above helow	_which	lsft	above Land	! Surface	
	Use: Dom., Stock, Public Supply Ind., Irr., Observation, Other (Test Hole, Oil				7- -	
15.	Recorded by: D.R. Joses Source of data: Drillens Log		Date:_	92/15/	83	
6.	Remarks:	-				
200						
7.	Location or Sketch: Hwy 73		6	0		
			L -	log		
	Storage Elou. Huy w		- F.R. !	020		
	TP 0 #2 81 0.05	Water State of the	· · ·], /	- 40		
	#) 00	W/L	Obs. Well	W/Q Obs.	Well W	Wee
rDV	VR-0308 in 81d3			79 -03		
	# 1					
	1 1					

id original copy by tified mail to the as Water Development Board	State of	Texas		For TWDB us Well No. 79 Located on	7-03- 7A
0. Box 12386 crin, Texas 78711	WATER WELL	REPORT		Received:	
OWNER: Person having well drilled C.59	y Runge	Address Po Da	or RFD)	Runge Ten	7/157 (State)
Landowner(Name)	Address (Street o	or RFD)	(City)	(State)
LOCATION OF WELL:	,mile	s in	direction from_		
Locate by sketch map showing landmar hiway number, etc.*	ks, roads, creeks,	adjacent section	s or survey lines	(To s and directions	from
Sz - 478461	North	Block		Survey	
(Use reverse side if necessa	ry)	(NW); NEY; SWY; SE	() of Section		
TYPE OF WORK (Check): New Hall Deepening Reconditioning Plugging	4)PROPOSED USE (Check): Domestic Industr Irrigation Test W	ial (Municipal)	S) TYPE OF WELL Rotary Cable	Driven	Dug
WELL LOG:					1 21 60
Diameter of holein. D	epth drilledft.			ft. Date drilled_	1-31-77
	ction and color of mation material	9) Casing: Type: Old	New Steel	Plastic	Other
		Cemented from		ft, to	ft.
	25	Diameter (inches)	Setting From (ft.)	To (ft.)	Gage
12 atte	bus				
Constell	<u></u>	10) SCREEN:			
Pla	w.T	TypePerforated		Slotted	
F - C		Diameter (inches)	Setting From (ft.)	To (ft.)	Slot Size
(Use reverse side if r	neceptary)				
CUMPLETION (Check):		11) WELL TESTS:			
Straight wall Gravel packed Under reamed Open Hol	Other	Was a pump test i			by whom?
WATER LEVEL: Static level ft. below lan	nd surface Date			ft. drawdown ai	and the second
Artesian pressurelbs. per so	and the second s	Artesian flow			
Depth to pump bawls, cylinder, jet,	, etc.,ft.	Temperature of w	ater		
below land surface.		12) WATER QUALITY: Was a chemical a	nalysis made?	Yes N	ŧο
:		367 91 W VE	ontain undesirable		No
I North o	ertify that this well was drille		unorulator) and t		
	ll of the statements herein are		knowledge and be		
ADDRESS POBLE S4	15 /h	un on 1	un.	77011	
Signed) (Street, or RFD)	Kauson (City)	Layer	Texas ((State)	
(Water Well Dr.	. 1	oformation, if availabl	e. PZ 7		707

FORM NO. 28.

LAYNE TEXAS COMPANY, HOUSTON ---

DALLAS

REPORT NO. S. O.

1402-7085 PAGE 1 of 1

FILE NO. 3849 DATE 1/31/77

WELL LOG

CUSTOMER LOCATION	WELL DATA	
FOR City of Runge	NAME WELL WELL NO. 3	
Charlest 4	ELEVATION DATUM	
LOCATION WELL St. Mary St.		
50-00-000 SA SASSAGE - CO-00-000	TEST HOLE SIZE 7-7/8" TD 211'	
BURVEY	DATE STARTED DRILLING 1/29/77	
	DATE FINISHED DRILLING 1/31/77	
county Karnes state Texas	DRILLER Atchinson RIGNO. 20	
	TYPE MUD Gel NO. SACKS 8	
OTHER LAND MARKS	ELECTRIC LOG YES TYPE Widco	
	SURVEY Eastman TYPE Single Shot	
	OTHER	

DEPTH	EACH DESCRIPTION SOUMATION		SAMPLES			
STRATA	STRATUM	DESCRIPTION FORMATION	DEPTH	TYPE	NUMBER	
0		Surface	1 1			
1'	1'	Top Soil	1 1			
6'	5'	Clay	i			
67'	61'	Yellow Shale	1 1			
74 1	7'	Sandy shale w/hard stks.				
106,	32'	Shale w/hard stks.				
107'	1'	Rock	1 1			
112'	5'	Shale w/hard stks.	1 1			
126'	14'	Sandy shale w/hard stks.	1			
154'	28'	Shale w/hard stks. & sand	1 1			
190'	36'	Sand w/shale & hard stks.				
195'	5'	Shale w/sand stks.			U.	
200'	5'	Sand & hard stks.				
211'	11'	Shale w/sandy stks.				
	•		4			
		İ	1			
	1					
	l .		1			
			1			
	ĺ		1			
	ĺ				Į	
*					,	
			1			
	Į		Į i			
					l	
		1			ł	
	1	2	\		}	
			i		1	
•]	1]		70	
	12		-		h ~~	
	1	1,	12Z	79-03	15 = 30	
	+	*				
	1	1	\	179-03	17/7	

WATER TECHNOLOGISTS . . CHEMIS . . MICROBIOLOGISTS

25 March 1977

Layne Texas Company

P. G. Bon 9469

50 \$1402-7065

Sample marked: City of Runge, Kernes County, Taxes. Taken: 3-14-77 after

12 hours pumping at 125 gpm. Static Hand: 98'
Pumping Level: 155' Screened: 155' - 190', 195' - 200'

D. E. Atchiege

Received: 3-16-77

WATER ANALYSIS results in parts per million (mg/1) except as noted

Dissolved Residue at 3	50°C	842*	Conductance, micromhos/cm, 25°C	1,440
Total Dissolved Solids, actual†		9960	Color, units	4
Total Dissolved Solids,	calc.	920	Turbidity, units	•
Silica	SiO ₂	26	As Calcium Carbonate, CaCO ₃ :	
Calcium	Ca	123	Phenolphthalein Alkalinity	•
Magnesium	Mg	27	Total Alkalinity	248
Sodium (diff.) Na + K	as Na	125	Total Hardness	418
Carbonate	CO3	•	Free Carbon Dioxide CO ₂	31
Bicarbonate	HCO₃	303	рН 7.18	
Sulfate	5O ₄	•	HYPOTHETICAL COMBINATIONS	
Chloride Ortho-Phosphate Total Fluoride	0-70 ₄	294 15 0.6	Calcium Bicarbonate Calcium Chloride Hagnesium Chloride Sadium Chloride	403 65 105 287
Total Nitrate	NO ₃	5.6	Sodium Phosphate Sodium Fluoride	26
Total Manganese	Mn	< 0.02	Sedium Hitrate Silica	7 26
Total Iron	Fe	0.07	41164	29
Iron, filtered sample	Fe	-	Total Disselved Solids, calc.	920
Sample is hygreses giving high values			KEY PUNCHED	

†Total Dissolved Solids, actual = Dissolved Residue + 50.8% of bicarbonate (HCO₃) ion

EDNA WOOD LABORATORIES, INC.

PZ 79-03-707

79.03.70 HOUSTON, TEXAS 77021

Total Hardness (46570) Total Anions (-) Dissolved Solids (70301) Total Cations (+) Total ALK (00431) Bicarbonate (00453) Carbonate (00452) Phenol ALK (82244) Eh (00090) Specific Conductance (00094) pH (00400) Temperature (00010) 25.3 Water Level SWN: Aquifer(s): County: Preserve with: スなアングと 7-03-707 234.7 Bottle 1 7.02 1 liter 1.892 Mon Cations/HIM (Nitric) Bottle 2 1W7 µmhos/cm Radioactivity (OM! Bottle 3 (Nitrie) 1 gallon Water Quality Sampling Run CITY OF RUNGER REMARKS: PH= PH CAL: WEATHER COND HOT HUMIN SUMS TIME OUT 41/5 PM AIR TEMP 5/1, O °C Notes & Calculations TIME IN 3.00P Pump Stack POA PADON SAMP TIME: 3:37 PM SAMP TIME: 3:40 PM Samp to 124 travet at well head H₃SO₄ (Sulfuric) Vail Phosphate Bottle 4 Nitrate ML H2SO4 @ PH 4,50 FOR BICARBONATE 37.8 SAFTER BROMCRESOL3/0 ML H2SO4 @ PH AT START 30,8 S. S. A. A. C. C. 1 Qt.(glass) (TOC) Organics unfiltered Bottle 5 (Sodium Hydroxide) By: Sample No. JCB-1990-069 500 ml Cyanide FOR CARBONATE IF PRESENT Bottle 6 NaOH 50 ML OF SAMPLE Bottle 7 SOL. Sub-Samples stipulated All filtered Total otherwise All on ice unless B-160068

JORDAN LABORATORIES, INC. CHEMISTS AND ENGINEERS CORPUS CHRISTI, TEXAS JULY 5, 1990

TEXAS WATER DEVELOPMENT BOARD P.O. BOX 13231 AUSTIN, TEXAS 78711-3231

REPORT OF ANALYSIS

RAD-JLB-1990-069

STATE WELL NUMBER: CITY WELL #3

79-03-707

DATE AND TIME: 15:40 5-23-90

ADDRESS: BOX 206 RUNGE, TX 78151

SAMPLED AFTER PUMPING P.O.A. HRS.

YIELD: --- GPM

COLLECTION POINT: WELL HEAD

COUNTY: KARNES

OWNER: CITY OF RUNGE .

DATE DRILLED: 1-31-77

DEPTH: 2111

PH: 7.02

USE: PUBLIC S. TEMP.: 25.3 DEG.C. SPEC. COND.: 1478

		ANALYSIS DATE
POTASSIUM 40, PCI/L	6.3	06-29-90
URANIUM (NATURAL), MG/L	0.006	05-29-90
RADON 222, PCI/L	154*	05-25-90
COUNTING ERROR, PCI/L+/-	6*	
RADIUM 226, PCI/L	0.6	06-05-90
COUNTING ERROR, PCI/L+/-	0.1	
THORIUM 232, PCI/L	-0.2	07-02-90
COUNTING ERROR, PCI/L+/-	0.4	
RADIUM 228, PCI/L	-0.4	06-11-90
COUNTING ERROR, PCI/L+/-	1.8	

* VALUE REFLECTS RADON 222 CONTENT AS OF 3:37 PM 5-23-90.

LAB. NO. M28-3649

MAY PUNCHED

RESPECTFULLY SUBMITTED,

acopinion

CARL F. CROWNOVER

HM = Heavy Trace and Alkaline-Earth Metals TWDB Use Only Work No. 370-3707 Send Reply To: Ground Water Unit IAC No. MEY PUNCHED Texas Water Development Board P.O. Box 13231 Austin, Texas 78711 Attention: ERIC ADIDAS State Well Number: Date & Time: 05 RUNGE Send Copy To Owner Sampled After Pumping: Hours **GPM** ☐ Measured ☐ Estimated Temperature: Specific Conductance: Requested Chery MAY 251990 JUL J 1030 Date Received: Date Reported: Laboratory No .:

Calcium	(00915)	me/l	mg/l <i>i07</i>	Sodium	(00930)	me/l	mg/l
Magnesium	(00925)		32	Potassium	(00935)		9.0
		μ g /l				μ <i>g</i> /l	
Aluminum	(01106)	<u> < 50</u>		Manganese	(01056)	< 2-0	
Arsenic	(01000)	<10		Mercury	(71890)	<0.2	
Barium	(01005)	151	•	Molybdenum*	(01062)	<u>~20</u>	
Cadmium	(01025)	<10		Selenium	(01145)	4_	
Chromium	(01030)	< 20		Silver	(01075)	<10	
Copper	(01040)	< 20	•	Strontium*	(01080)	<u> </u>	
Iron	(01046)	< 20	,	Vanadium*	(01085)	<20	
Lead	(01049)	_<50_		Zinc	(01090)	121	

^{*} Do not analyze unless it is checked.

Note: Crossout those elements not to be analyzed.

GWR-JCB 1990 069

	(Anions)	TWDB Use Only
		Work No. 370-370Z
Send Reply To: Ground Water Unit		IAC No.
Texas Water Development Board	Man annual day	
P.O. Box 13231 Austin, Texas 78711	MEY PUNCHED	City Well #3
Attention: ERIC ADIDAS	State Well Number:	79-03-707
County: KARNES	Date & Time:	T-73-1990 15:40
Owner: CITYOF RUNGE	Send Copy To (Owner
Address: BOX 206 RUNGE T	X 78/5/ Sampled After Pump	ing: POA Hours
Date Drilled: OF3/-P17Depth: 2	Yield:	GPM O Measured O Estimated
Collection Point: WELLHEADH 7	02 Uno: PUDIC	5 Temperature: 25.3 °C
(BV: Vimo Remula	Specific Conductance	: 1478
Requested Chemical Analysis and the second		
	a Received: MAY 251990	D - D
Laboratory No.: Date	e Received: WAY 20 1990	Date Reported: JUN 2 0 1990
IND DEMINISTE ALL TO THE PROPERTY OF THE PROPE	te Received 05/25/90 MG/L	Date Reported 06/18/90 MEQ/L MG/L
Silica (00955)	29	
	Sulfate (0094 Chloride (0094	
	Chloride (0094 Fluoride (0095	
p ppalimity(00415) 0.00	0	
P. Akalimity(00415) 0.00 T. Akalimity(00410) 4.68	234	
THE PERSON AND ADDRESS OF THE STREET		Todide (71865) (0.1
		Boron (****) 0.61 Bromide (71870) 0.17
		DICHAGE CLASSICS STATE

GWNJUB_P	Pn 069
(Nitrog	en Cycle) TWDB Use Only
Send Reply To: Ground Water Unit Texas Water Development Board	Work No. 370-3707
P.O. Box 13231 Austin, Texas 78711	CHYWEII#3
Attention: ERIC ADIDAS	State Well Number: 79-03-707
County: KARNES	Date & Time: 05-23-1990 15:40
OWNER: CITY OF RUNGE	Send Copy To Owner
Address: BOX206 RUNGETX 7815/	Sampled After Pumping: POA Hours
Date Drilled: 01-31-1977 Depth: 211	Yield: GPM G Measured G Estimated
Collection Point: WEU HEAD pH 7.02	Use: Public 5 Temperature: 25.3 °C
By: /mas Beaukonf	Specific Conductance: 1478
Requested Chemical Analysis	MAY 2.5 190r
Laboratory No.: Date Received:	Date Reported: JUN 1 1990
THD-Sample No. EBO 1347 Date Receive	d 05/25/90 Date Reported 06/01/90 MG/L
Nitrate as N (00618) 1.37 KJB as N (00623) < 0.1	Ammonia as N (00608) < 0.02 Nitrite as N (00613) < 0.01 Orthophosphate as P(00671) 0.01

TWDB Use Only Work No. 320-3702 Send Reply To: Ground Water Unit IAC No. Texas Water Development Board MEY PUNCHED P.O. Box 13231 Austin, Texas 78711 ERIC ADIDAS Attention: State Well Number: Date & Time: Send Copy To Owner Sampled After Pumping: Hours Date Drilled: 6 Yield: **GPM** Estimated Collection Point: Temperature: Specific Conductance: _ Requested Chemical Analys MAY 251990 Laboratory No.: Date Received: Date Reported: CODE 5970 ORGANICS SCREENS

Texas Depart ant of Health Pesticide Re, rt Form Nickel 63 Detector

Analyst History	Bourda	Lab ID numbe	= EBO-1318
Approved Tue		Submitter I	
Cample type: water (circle one) Units: micrograms/1	liquid w		issue other
p,p' DDT		Lindane	20.00
p,p' DDD	20.15	L'Indaile.	20.00
p.p' DDE	< 0.15	 	
Aldrin	10,1		
Dieldrin	20,2		
Endrin	20,1		
Chlordane	20,2		
Heptachlor	40,02	Polychlorine	ated biphenyls
Heptachlor epox.	20.06	Aroclor 1016 <0.6	
Methoxychlor	40.5	Aroclor 1221	
Toxaphene	25.0	Aroclor 1232	
Hexachlorobenzene	20.02	Aroclor 1242	
Malathion	20.4	Aroclor 1248	
Ethyl Parathion	20,25	Aroclor 1254	20,8
Methyl parathion	20,25	Aroclor 1260	
Diazinon	20.3	Aroclor 1262	2 <0.8
Chloropyrifos	20,6	Acid extract	ible herbicides
Endosulfan	40,2	2,4 - D	120
Endosulfan sulfate	40.2	2,4,5 - T	25.0
Alachlor	40.1	2,4,5 - TP (silvex) 25.0
Dacthal	40.05	Pentachlorph	
alpha BHC	20.03	Dicamba	41.0
beta BHC	40,07	Picloram	< 3,0
delta BHC	40.03		

Comments:

MEX PUNCHED

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756

TDWR-0148 (Rev. 6-20-83)

	TOWR ONLY	
Organization N	10. 410 Lab No.	
Work No	6040	

Ī	CHEMICAL WATER A	ANALYSIS REPORT			V
Send report to:			County	, NKIN	Karnes
Data Collection and Evaluation Section			State V	Vell No. 79	03707
Texas Department of Water Resources					11 No. 3
P.O. Box 13087					
Austin, Texas 78711		Copy 10/20/83	Date Co	ollected 09	112 83
Dwner City of Runge		Send copy to own	ner Sample No.	By D. I	B. Jones
Address Box 206 Runge Is	Ex 95 78151		Well Location_		
	The second second				
-7 7 	ft. W8F		1 1	ource (type of w	ell) Luxleine
Producing intervals Water I		ft. Sample depth L_	——————————————————————————————————————	4-1-1	
		GPM	est. Temp	erature 07	ذFLLL °C
Point of collection Faucet at we		Арре	arance 🖫 clea	r 🛘 turbid 🗖	colored 🔲 other
Use Liblic Supply Remarks					
(FOR LABORAT	OMPANIO A LA	NAL VOIC	EY PUNCHED		
	CHEMICAL A	MAL 1919			
Laboratory No.	Date Received	CP 2 8 1983	Date	Reported 0(CT 1 2 1983
128	HATER ANALY	ere			
State Well No. 79-03-707	Date: 10128;		Cample	No : El/4-2	254
MG/L	ME/L	?	Saubre	MG/L	ME/L
Silica: 00955: 61	- Time - The C	Carbonate: 0	0445;	0	0
Calcium:00910: 118	5.9	Bicarbonate: 0	0440:	255	4.18
Magnesium: 00920: 29	2.42	Sulfate: 0	0945:	36	. 75
Sodium:00929: 129	5.61	Chloride:0	0940:	314	8.85 (
T.Cations	14.16	Fluoride:0		. 6	. 0.3
Potassium:00937: 9	. 23	Nitrate:7		5.89	, 1
[Mandanese:01055:	ZNa		nions		13.91
D01077	CAD	ø pH:l	00403:	8	
Boron:01022;	SAR		0.300 •	826	
Total Iron: 01045:	RSC	P. Alk.: 0		0	1
A-1	And are the same and the same about some about	T. Alk.:0		209	1
(Specific Cond.:00095:	1150	T. Hardness:0		416	L
Diluted Conductance (micromh	ios/cm3)				
$11 \times 149 = 1639$		1: N-einommA		WEV NING	MIPM
\perp items will be analyzed if	`checked.	Nitrite-N:0		KEY PUNC	ANEL
	~	Nitrate-N:0			
	ura.	anicNitrogen:0			
Diluted Conductance (micromhos/cm ³);	_ [Ammonia - N · · ·	litrogen Cycle	00610 .	
X		Suniodia - M		00010	
" " items will be analyzed if checked.		Nitrite - N · · · ·		00615 .	
¹ The bicarbonate reported in this analysis can computation (multiplying by 0.4917) to an equi carbonate, and the carbonate figure used in the	valent amount of	Nitrate - N		00620 .	
carbonate, and the carbonate rigure used in the dissolved solids. Nitrogen cycle requires separate sample. Total Iron and Manganese require separate sample.	S COMPARATION OF	Organic Nitrogen · ·		00605 .	Ш.Ш
TOWR-0148 (Rev 6-20-83)		Analyst	CI	necked By	

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

	TOWE	ONLY		
Organization	No	Lab N	10.	
Work No				

_____ Checked By __

Analyst ____

Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756 **CHEMICAL WATER ANALYSIS REPORT** Send report to: **Data Collection and Evaluation Section** Texas Department of Water Resources P.O. Box 13087 Date Collected Austin, Texas 78711 Send copy to owner Sample No. Owner _ Well Location_ Address _ Date Drilled _____ Depth ______ ft. WBF _____ Source (type of well) __ Producing intervals ______ ft. Sample depth hrs. Yield _____ GPM meas. Temperature Sampled after pumping _____ _____Appearance cleer turbid colored other Point of collection ___ Remarks __ (FOR LABORATORY USE ONLY) **CHEMICAL ANALYSIS** KEY PUNCHED Date Received_ Date Reported _ Laboratory No. _ ME/L ME/L Carbonate · · 00445 · · · · 00955 · · Silica . 00440 . Calcium · · · 00910 · · · Bicarbonate Magnesium · · 00920 · · · . 00945 . Sulfate . . 00940 . Sodium · · · 00929 · · Chloride . 00951 Fluorida D Potassium - 00937 - . · 71850 · Nitrate · pH · · · · 00403 · ³☐ Mangenese · 01055 · · · ☐ Boron . . 01022 · . . 70300 ¹ Dissolved Solids (residue at 180°C) ³ ☐ Total Iron · 01045 · · 00415 Phenolphthalein Alkalinity as C aCO3 . 00410 Total Alkalinity as CaCO3 · · · · O (other) ___ Specific Conductance (micromhos/cm³) . Total Hardness as C aCO3 · · · · 00900 ² Nitrogen Cycle Ammonia - N · · · · · · · · 00610 Diluted Conductance (micromhos/cm³) 00615 " " items will be analyzed if checked. ¹ The bicarbonate reported in this analysis can be converted by computation (multiplying by 0.4917) to an equivalent amount of 00620 carbonate, and the carbonate figure used in the computation of 00605 Organic Nitrogen · · · · · dissolved solids.

TDWR-0148 (Rev. 12-29-82)

Nitrogen cycle requires separate sample.
 Total Iron and Manganese require separate sample.

TEXAS DEPARTMENT OF WATER RESOURCES

	Jasper Aquiser WELL SCHEDULE		
	Aquifer(s) (Ogliville 55) Project No.	State Well No. 79 -03 -70	6
	Field No./Owner's Well No.##3	County (128)	
1.	Location: 4, 4, Section ,Block ,Survey		4 1 2
			<u> </u>
2.	Owner: Address:		
	Tenant (other):Address:		-
	Driller: Layne Texas Address:		
3.	Land Surface Elevation: 300 _ ft. above msl determined by	120	
4.	Drilled:	,	
5.	Depth: Rept. 315 ft. Heasft.	CASING, BLANK PIPE & WELL SCREE	(1) (1) (1) (1) (1) (1) (1) (1) (1) (1)
6.	Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed	Cemented From ft. to Diam. Type Setting (feet)	ft.
7.	Pump: Mfr. Type I wrbine	(in.) from to	
	No. Stages, Bowls Diamin., Settingft.	1234 Sur. Csg +2 145	
	Column Diamin., Length Tailpipeft.	87/2 BJ, Lymont 1 155	~
8.	Motor: Afr. Fuel E & C HP.	85x mil 310t 155 19	~
9.	Yield: Flowgpm, Pumpgpm, Heas., Rept., EstDate		2
10.	Performance Test: DateLength of TestMade by	lor lo	20
	Static Levelft. Pumping Levelft. Drawdownft.	858 Bl Jugar 200 20	
	Productiongpm Specific Capacitygpm/ft.	85/8 Set Wind 208 21	0
11.	Quality: (Remarks on taste, odor, color, etc.)		
	Analyses		-
	Date 3-14-77 Laboratory Edna Wood TDS 996 Sp Cond 1440		
	DateLaboratoryTOSSp Cond		-
12.	Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log,		
	Formation Samples, Geophysical Log(s) (type)		
13.	Water Level(s):ft. rept19below	which isft. below Land Surfa	ce
	ft. rept. 19below		
14.	Use: Dom., Stock, Public Supply, Ind., Irr., Observation, Other (Test Hole, Oil	Test, etc.)	
15.	Use: Dom., Stock, Public Supply, Ind., Irr., Observation, Other (Test Hole, Oil Recorded by: D. Jore 5Source of data:	Date: 7/30/81	
16.	Remarks:	· 	
17.	Location or Sketch: Nex+ Page	RECEIVED	
		NOV 1 8 1982	
		MAN TO 1205	

CR/10...

T S DEPARTMENT OF WATER RET REES

	_ DATE		70 02 -	7.00	SHEET NO	OF.
СНКО	_ DATE	JOB NAME	JOB NO		PROG. CODE	
Ruild.	Gate Varion Town Town Town Town Town Town Town To	Q#2 	125	2	not h on 8 and Street he right.	1 0

A

TEXAS DEPARTMENT OF WATER RESOURCES

WELL SCHEDULE

Field No./Owner's Well No. # 3 County Kares (128) 1. Location: t, t, Section , Block , Survey , Lat28-52-51N Long. 97-42. 2. Owner:	,	Aquifer(s) Project No.	State We	11 No. 79	-03:	706
1. location: t, i, Section , Block , Survey , Lat28-22-51M, Long, 97-42- 2. Owner: Address:		Field No./Owner's Well No. # 3	County_	Karnes	\cdot \cdot \cdot	28)
2. Owner:	1. 1		17.			
2. Owner: Address: Tenant (other): Address: Driller: Address: Driller: Address: 3. Land Surface Elevation: 300 ft. above msl determined by						
Driller: 3. Land Surface Elevation: 300 ft. above msl determined by 4. Drilled: 5 10 1977; Dug, Cable Tool, Rotary, Air, 5. Depth: Rept. ft. Meas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Hfr. Type ft. 8. Motor: Mfr. ft. 8. Motor: Mfr. full file ft. 8. Motor: Mfr. gpm, Pump gpm, Heas., Rept., Est. Date 9. Yield: Flow gpm, Pump gpm, Heas., Rept., Est. Date 10. Performance Test: Date Length of Test Made by Static Level ft. Pumping Level ft. Drawdown ft. Production gpm Specific Capacity gpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Mater Level(s): ft. rept. gabove which is ft. below Land Surfa	_					
Driller: 3. Land Surface Elevation: 300 ft. above ms1 determined by 4. Drilled: 5 10 1977; Dug, Cable Tool, Rotary, Air, 5. Depth: Rept. ft. Meas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr. Type ft. 8. Motor: Mfr. ft. 8. Motor: Mfr. full flow gpm, Pump gpm, Heas., Rept., Est. Date 9. Vield: Flow gpm, Pump gpm, Heas., Rept., Est. Date 10. Performance Test: Date Length of Test Made by Static Level ft. Pumping Level ft. Drawdown ft. Production gpm Specific Lapacity gpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) ft. meas. 19 below which is ft. below Land Surfa ft. meas. fept. below which is ft. below Land Surfa below Land Surfa below which is ft. below Land Surfa below Land Surfa below Land Surfa below which is ft. below Land Surfa below Land Surf	2. (Dwner: (ity of) nige Address:				
3. Land Surface Elevation: 300 ft. above ms1 determined by 1 000 4. Drilled: 5 10 19 77; Dug, Cable Tool, Rotary, Alr, 5. Depth: Rept. ft. Heas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr. Type ft. Type ft. 8. Mo. Stages Nowls Diam. in., Setting ft. 6. Hotor: Mfr. ft. ft. 9. Yield: Flow gpm, Pump gpm, Heas., Rept., Est. Date 10. Performance Test: Date Length of Test Nade by Static Level ft. Pumping Level ft. Drawdown ft. Production gpm Specific Capacity gpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.) Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. meas. 19 below which is ft. above Land Surfa	•	Tenant (other):				
4. Drilled: 5 10 1977; Dug, Cable Tool, Rotary, Air, 5. Depth: Rept. ft. Meas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr. Type from to No. Stages Nowls Diam. in., Setting ft. Column Diam. in., Length Tailpipe ft. 8. Motor: Mfr. pumping Level ft. Date 0. Performance Test: Date Length of Test Nade by Static Level ft. Pumping Level ft. Drawdown ft. Production gpm Specific Lapacity gpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level (s): ft. rept. meas. 19 above below which is ft. above Land Surfa	ı	Driller:Address:				
4. Drilled: 5 10 1977; Dug, Cable Tool, Rotary, Air, 5. Depth: Rept. ft. Meas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr. Type from to No. Stages Nowls Diam. in., Setting ft. Column Diam. in., Length Tailpipe ft. 8. Motor: Mfr. pumping Level ft. Date 0. Performance Test: Date Length of Test Nade by Static Level ft. Pumping Level ft. Drawdown ft. Production gpm Specific Lapacity gpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level (s): ft. rept. meas. 19 above below which is ft. above Land Surfa	3. 1	Land Surface Elevation: 300ft. above ms1 determined by	120			
5. Depth: Rept. ft. Meas. ft. 6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr. Type Setting (feet) 1. No. Stages Bowls Diam. in., Setting ft. 1. Column Diam. in., Length Tailpipe ft. 8. Motor: Mfr. Fuel Flow gpm, Pump gpm, Meas., Rept., Est. Date 9. Yield: Flow gpm, Pump gpm, Meas., Rept., Est. Date 10. Performance Test: Date Length of Test Made by 11. Quality: (Remerks on taste, odor, color, etc.) 12. Analyses 13. Date Laboratory TDS Sp Cond 14. Date Laboratory TDS Sp Cond 15. Tops Sp Cond 16. Tops Sp Cond 17. Pumping Level Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) 18. Water Level (s): ft. rept. Bobow Which Is ft. above Land Surfa Bove Below Land Surfa Bove Below Which Is ft. above Land Surfa Bove Below Which Is ft. Below Which Is ft. Below Which Is ft. Below Surfa Bove Below Which Is ft. Below W	4. [Drilled: 5/10/ 1977; Dug, Cable Tool, Rotary, Alr,				
6. Borehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed 7. Pump: Mfr		, ,			PIPE & WELL	
No. Stages, Bowls Diamin., Settingft. Column Diamin., Length Tailpipeft. 8. Motor: Mfrgpm, Pumpgpm, Heas., Rept., EstDate	6. [Forehole Completion: Open Hole, Straight Wall, Underreamed, Gravel Packed				ft.
Column Diam. in., Length Tailpipe ft. 8. Hotor: Hfr. Fuel	7- <u>F</u>	Pump: MfrType	(In.)		from	to
8. Motor: Mfr. Fuel		No. Stages, Bowls Diamin., Settingft.	-			
9. Yield: Flowgpm, Pumpgpm, Heas., Rept., EstDate		Column Diamin., Length Tailpipeft.	-			
O. Performance Test: DateLength of TestMade by	8. 4	fotor: Mfr. Fuel E				
Static Levelft. Pumping Levelft. Drawdownft. Productiongpm Specific Capacitygpm/ft. 1. Quality: (Remerks on taste, odor, color, etc.)	9. \	/[eld: Flowgpm, Pumpgpm, Heas., Rept., EstDate				
Production gpm Specific Capacity gpm/ft. 1. Quality: (Remarks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond Date Leboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa	0. <u>I</u>	Performance Test: DateLength of TestMade by				
Production gpm Specific Capacity gpm/ft. 1. Quality: (Remarks on taste, odor, color, etc.) Analyses Date Laboratory TDS Sp Cond Date Leboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa		Static Levelft. Pumping Levelft. Drawdownft.		AUG 12		
Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above below which is ft. below Land Surfa ft. rept. 19 above below which is ft. below Land Surfa		Productiongpm Specific Capacitygpm/ft.			-WO/	
Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level (s): ft. rept. 19 above below which is ft. below Land Surfa ft. meas. 19 above which is ft. above Land Surfa	1. 9	Quality: (Remarks on taste, odor, color, etc.)		CHILL		
Date Laboratory TDS Sp Cond 2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above below which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa		Analyses	-			
2. Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log, Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa		DateLaboratoryTDSSp Cond				
Formation Samples, Geophysical Log(s) (type) 3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa		DateLeboratoryTDSSp Cond				
(type) 3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa ft. meas. 19 above which is ft. below Land Surfa	2. (Other data available (as circled): Pumping Test, Power & Yield Test, Drillers Log,				<u> </u>
3. Water Level(s): ft. rept. 19 above which is ft. below Land Surfa ft. rept. 19 above which is ft. above Land Surfa	F	formation Samples, Geophysical Log(s)				LJ
ft. rept. 19 above which is ft. below Land Surfa	3. <u>y</u>	dater Level(s): ft. rept. 19 above	_which	isft.	above Land	Surface
5. Recorded by: D Juries Source of data: Date: 7/30/81	4. <u>L</u>					
	5. 1	Accorded by: D Jerie S Source of data:		Date:	7/30	51
6. Remarks:	6. I	Remarks:	. – – – –		/ /	
	-					
	-		. – – –			
7. Location or Sketch: Nex+ Dage	7. !	ocation or sketch: Nex+ Dage				

W/L Obs. Well W/Q Obs. Well State Well No. 79-03-706

Typewrite (Black ribbon) or Print Plainly (soft pencil or black ink) Do not use ball point pen

TDWR-0148 (Rev. 7-78)

	TDWR ONLY
Program No	Lab No. 05
Work No	

Texas Department of Health Laboratories 1100 West 49th Street Austin, Texas 78756 **CHEMICAL WATER ANALYSIS REPORT** Send report to: Data Collection and Evaluation Section Texas Department of Water Resources P.O. Box 13087 Austin, Texas 78711 Location Lat 28-52' 51"N. Long 97° Source (type of well) Owner City Date Drilled 1-31-77 Depth 210 ft. WBF Water level __ ft. Sample depth _ GPM THEST __ hrs. Yield __ Sampled after pumping ____ Temperature Appearance Clear Cl turbid Cl colored Cl other AST PUNCHED (FOR LABORATORY USE ONLY) **CHEMICAL ANALYSIS** Laboratory No. _ Date Received_ Date Reported _ ME/L MG/L ME/L Sitica Carbonate -Calcium · Bicarbonate Magnesium Sulfate . Sodium · Chloride Total Fluoride Potassium . . . ³ ☐ Manganese -Boron . Dissolved Solids (residue at 180°C) 3 Total Iron . Phenolphthalsin Alkalinity as C aCO3 · · · · · · (other)_ Total Alkalinity as C aCO3 · · · · · · · · Specific Conductence (micromhos/cm3) . . . Total Hardness as CaCO3 · · · · ² Nitrogen Cycle Diluted Conductance (micromhos/cm³) " " items will be analyzed if checked. Nitrite - N ¹ The bicarbonate reported in this analysis can be converted by computation (multiplying by 0.4917) to an equivalent amount of carbonate, and the carbonate figure used in the computation of dissolved solids. Organic Nitrogen · · · · Nitrogen cycle requires separate sample. Total Iron and Manganese require separate sample.

Analyst.

____ Checked By ___





GWDB Reports and Downloa	ads Well Ba	asic Details	Scanned Documents
State Well Number	7903708	Well Type	Withdrawal of Water
County	Karnes	Well Use	Public Supply
River Basin	San Antonio	Water Level Observation	None
Groundwater Management Area	15	Water Quality Available	Yes
Regional Water Planning Area	L - South Central Texas	Pump	Submersible
Groundwater Conservation District	Evergreen UWCD	Pump Depth (feet below land surface)	
Latitude (decimal degrees)	28.881111	Power Type	Electric Motor
Latitude (degrees minutes seconds)	28° 52' 52" N	Annular Seal Method	
Longitude (decimal degrees)	-97.712501	Surface Completion	
Longitude (degrees minutes seconds)	097° 42' 45" W	Owner	City of Runge Well #4
Coordinate Source	+/- 1 Second	Driller	Cude Drilling Inc.
Aquifer Code	122CTHL - Catahoula Formation	Other Data Available	Drillers Log
Aquifer	Gulf Coast	Well Report Tracking Number	
Aguifer Pick Method		Plugging Report Tracking Number	
Land Surface Elevation (feet above sea level)	310	U.S. Geological Survey Site Number	
Land Surface Elevation Method	Interpolated From Topo Map	Texas Commission on Environmental Quality Source Id	G1280003D
Well Depth (feet below land surface)	720	Groundwater Conservation	
Well Depth Source	Driller's Log	District Well Number	
Drilling Start Date		Owner Well Number	
Drilling End Date	10/6/1994	Other Well Number	
Drilling Method	Mud (Hydraulic) Rotary	Previous State Well Number	
Borehole Completion		Reporting Agency	Texas Water Development Board
		Created Date	5/20/1997

Remarks Drilled to 1,100 ft. Pluged back to 720 ft.

Casing

Diameter (in.)	Casing Type	Casing Material	Schedule	Gauge	Top Depth (ft.)	Bottom Depth (ft.)
12	Blank	Steel			0	315
8	Blank	Steel			315	340
8	Screen	Steel			340	400
8	Blank	Steel			400	620
8	Screen	Steel			620	700
8	Blank	Steel			700	710

Well Tests - No Data

Lithology - No Data

Annular Seal Range - No Data

Borehole - No Data

Plugged Back - No Data

Last Update Date

6/6/1997

Filter Pack - No Data


Packers - No Data











Status Code	Date	Time	Water Level (ft. below land surface)	Change value in () indicates rise in level	Water Elevation (ft. above sea level)	1.5	Measuring Agency	Method	Remark ID	Comments
X	3/22/2005					1	Texas Water Development Board		20	

Code	Descript	ione
Couc	Describe	10113

Status Code Status Description		Remark ID	Remark Description
Χ	No Measurement	20	Unable to insert tape into well





Water Quality Analysis

Sample Date: 1/29/1997 Sample Time: 0000 Sample Number: 1 Collection Entity: Texas Commission on Environmental

Quality

Sampled Aquifer: Catahoula Formation

Analyzed Lab: Texas Department of Health Reliability: By TCEQ staff with their QA-QC procedures

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		289	mg/L as CACO 3	
01105	ALUMINUM, TOTAL (UG/L AS AL)	<	40	ug/L	
01097	ANTIMONY, TOTAL (UG/L AS SB)	<	2	ug/L	
01002	ARSENIC, TOTAL (UG/L AS AS)		13.6	ug/L	
01007	BARIUM, TOTAL (UG/L AS BA)		86.99	ug/L	
01012	BERYLLIUM, TOTAL (UG/L AS BE)	<	1	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		352.68	mg/L	
01027	CADMIUM, TOTAL (UG/L)	<	0.2	ug/L	
00910	CALCIUM (MG/L)		40	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		104	mg/L	
01034	CHROMIUM, TOTAL (UG/L AS CR)		20	ug/L	
01042	COPPER, TOTAL (UG/L AS CU)	<	6	ug/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.5	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		149	mg/L as CACO 3	
01045	IRON, TOTAL (UG/L AS FE)	<	10	ug/L	
01051	LEAD, TOTAL (UG/L AS PB)	<	1	ug/L	
00920	MAGNESIUM (MG/L)		12	mg/L	
01055	MANGANESE, TOTAL (UG/L AS MN)	<	8	ug/L	
71900	MERCURY, TOTAL (UG/L AS HG)	<	0.27	ug/L	
01067	NICKEL, TOTAL (UG/L AS NI)	<	20	ug/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		4.12	mg/L as NO3	
00400	PH (STANDARD UNITS), FIELD		7.9	SU	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		2.79		
01147	SELENIUM, TOTAL (UG/L)		5.4	ug/L	
01077	SILVER, TOTAL (UG/L AS AG)	<	10	ug/L	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		5.24		
00932	SODIUM, CALCULATED, PERCENT		68	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)		147	mg/L	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		994	MICR	
00945	SULFATE, TOTAL (MG/L AS SO4)		44	mg/L as SO4	
01059	THALLIUM, TOTAL (UG/L AS TL)	<	1	ug/L	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		525	mg/L	
01092	ZINC, TOTAL (UG/L AS ZN)	<	20	ug/L	





Water Quality Analysis

Sample Date: 5/20/1997 Sample Time: 1550 Sample Number: 1 Collection Entity: Texas Water Development Board

Sampled Aquifer: Catahoula Formation

Analyzed Lab: LCRA - Lower Colorado River Authority Reliability: Sampled using TWDB protocols

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39086	ALKALINITY FIELD DISSOLVED AS CACO3		296	mg/L as CACO 3	
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		296	mg/L as CACO 3	
01106	ALUMINUM, DISSOLVED (UG/L AS AL)	<	1.5	ug/L	
01095	ANTIMONY, DISSOLVED (UG/L AS SB)	<	1	ug/L	
01000	ARSENIC, DISSOLVED (UG/L AS AS)		10.2	ug/L	
01005	BARIUM, DISSOLVED (UG/L AS BA)		91	ug/L	
01010	BERYLLIUM, DISSOLVED (UG/L AS BE)	<	1	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		361.22	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		412	ug/L	
71870	BROMIDE, DISSOLVED, (MG/L AS BR)		0.58	mg/L	
00915	CALCIUM, DISSOLVED (MG/L AS CA)		34.6	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00941	CHLORIDE, DISSOLVED (MG/L AS CL)		99.2	mg/L	
01035	COBALT, DISSOLVED (UG/L AS CO)	<	1	ug/L	
01040	COPPER, DISSOLVED (UG/L AS CU)	<	1	ug/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.46	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		126	mg/L as CACO 3	
71865	IODIDE (MG/L AS I)	<	0.15	mg/L	
01046	IRON, DISSOLVED (UG/L AS FE)	<	15	ug/L	
01049	LEAD, DISSOLVED (UG/L AS PB)	<	1	ug/L	
01130	LITHIUM, DISSOLVED (UG/L AS LI)		51.7	ug/L	
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)		9.5	mg/L	
01056	MANGANESE, DISSOLVED (UG/L AS MN)	<	1	ug/L	
01060	MOLYBDENUM, DISSOLVED (UG/L AS MO)		1.9	ug/L	
01065	NICKEL, DISSOLVED (UG/L AS NI)	<	1	ug/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		4.17	mg/L as NO3	
00631	NITRITE PLUS NITRATE, DISSOLVED (MG/L AS N)		0.942	mg/L as N	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00608	NITROGEN, AMMONIA, DISSOLVED (MG/L AS N)	<	0.1	mg/L as N	
00623	NITROGEN, KJELDAHL, DISSOLVED (MG/L AS N)	<	0.5	mg/L as N	
00090	OXIDATION REDUCTION POTENTIAL (ORP), MILLIVOLTS		73.3	MV	
00400	PH (STANDARD UNITS), FIELD		7.27	SU	
00935	POTASSIUM, DISSOLVED (MG/L AS K)		7.23	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		3.41		
01145	SELENIUM, DISSOLVED (UG/L AS SE)	<	6	ug/L	
00955	SILICA, DISSOLVED (MG/L AS SI02)		48.7	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		5.87		
00932	SODIUM, CALCULATED, PERCENT		72	PCT	
00930	SODIUM, DISSOLVED (MG/L AS NA)		151	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		863	MICR	
01080	STRONTIUM, DISSOLVED (UG/L AS SR)		920	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)		40.4	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		26.6	С	
01057	THALLIUM, DISSOLVED (UG/L AS TL)	<	1	ug/L	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		573	mg/L	
01085	VANADIUM, DISSOLVED (UG/L AS V)		31.5	ug/L	
01090	ZINC, DISSOLVED (UG/L AS ZN)		38.7	ug/L	





Collection Entity: Texas Water Development Board

Water Quality Analysis

Sample Date: 3/22/2005 Sample Time:

Sampled Aquifer: Catahoula Formation

Analyzed Lab: LCRA - Lower Colorado River Authority Reliability: Sampled using TWDB protocols

Sample Number: 1

1442

Collection Remarks: No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39086	ALKALINITY FIELD DISSOLVED AS CACO3		304	mg/L as CACO 3	
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		292	mg/L as CACO 3	
01106	ALUMINUM, DISSOLVED (UG/L AS AL)	<	4.08	ug/L	
01095	ANTIMONY, DISSOLVED (UG/L AS SB)	<	1.02	ug/L	
01000	ARSENIC, DISSOLVED (UG/L AS AS)		12.7	ug/L	
01005	BARIUM, DISSOLVED (UG/L AS BA)		79.3	ug/L	
01010	BERYLLIUM, DISSOLVED (UG/L AS BE)	<	1.02	ug/L	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		356.34	mg/L	
01020	BORON, DISSOLVED (UG/L AS B)		697	ug/L	
71870	BROMIDE, DISSOLVED, (MG/L AS BR)		0.4	mg/L	
01025	CADMIUM, DISSOLVED (UG/L AS CD)	<	1.02	ug/L	
00915	CALCIUM, DISSOLVED (MG/L AS CA)		38.1	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00941	CHLORIDE, DISSOLVED (MG/L AS CL)		109	mg/L	
01030	CHROMIUM, DISSOLVED (UG/L AS CR)		13	ug/L	
01035	COBALT, DISSOLVED (UG/L AS CO)	<	1.02	ug/L	
01040	COPPER, DISSOLVED (UG/L AS CU)		4.5	ug/L	
00950	FLUORIDE, DISSOLVED (MG/L AS F)		0.64	mg/L	
04241	GROSS ALPHA RADIATION, TOTAL, PRODUCED WATER(pCi/L)		16	pCi/L	
04242	GROSS BETA RADIATION, TOTAL, PRODUCED WATER(pCi/L)		15	pCi/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		139	mg/L as CACO 3	
01046	IRON, DISSOLVED (UG/L AS FE)	<	51	ug/L	
01049	LEAD, DISSOLVED (UG/L AS PB)	<	1.02	ug/L	
01130	LITHIUM, DISSOLVED (UG/L AS LI)		54.3	ug/L	
00925	MAGNESIUM, DISSOLVED (MG/L AS MG)		10.4	mg/L	
01056	MANGANESE, DISSOLVED (UG/L AS MN)		2.29	ug/L	
01060	MOLYBDENUM, DISSOLVED (UG/L AS MO)		3.36	ug/L	
71851	NITRATE NITROGEN, DISSOLVED, CALCULATED (MG/L AS NO3)		3.82	mg/L as NO3	





Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00631	NITRITE PLUS NITRATE, DISSOLVED (MG/L AS N)		0.8626	mg/L as N	
00400	PH (STANDARD UNITS), FIELD		7.51	SU	
00935	POTASSIUM, DISSOLVED (MG/L AS K)		9.09	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		3.08		
01145	SELENIUM, DISSOLVED (UG/L AS SE)	<	4.08	ug/L	
00955	SILICA, DISSOLVED (MG/L AS SI02)		50.8	mg/L as SIO2	
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		6.18		
00932	SODIUM, CALCULATED, PERCENT		72	PCT	
00930	SODIUM, DISSOLVED (MG/L AS NA)		167	mg/L	
00094	SPECIFIC CONDUCTANCE, FIELD (UMHOS/CM AT 25C)		1012	MICR	
01080	STRONTIUM, DISSOLVED (UG/L AS SR)		1180	ug/L	
00946	SULFATE, DISSOLVED (MG/L AS SO4)		56.4	mg/L as SO4	
00010	TEMPERATURE, WATER (CELSIUS)		26.5	С	
01057	THALLIUM, DISSOLVED (UG/L AS TL)	<	1.02	ug/L	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		622	mg/L	
01085	VANADIUM, DISSOLVED (UG/L AS V)		27.3	ug/L	
01090	ZINC, DISSOLVED (UG/L AS ZN)		10.2	ug/L	





Water Quality Analysis

Sample Date: 3/22/2005

Sample Time:

Sample Number: 1

Collection Entity: Texas Commission on Environmental

Quality

Sampled Aquifer:

Catahoula Formation

Analyzed Lab: Immunoassay at TCEQ

Reliability: Sampled using TWDB protocols, but NOT filtered

Collection Remarks:

No Data

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
39033	ATRAZINE, TOTAL, UG/L	<	0.05	ug/L	
82612	METOLACHLOR, WHOLE WATER, TOTAL RECOVERABLE, UG/L	<	0.05	ug/L	


^{*} Value may not display all significant digits for parameter in results, check Scanned Documents for laboratory paperwork..

GWDB DISCLAIMER: Except where noted, all of the information provided in the Texas Water Development Board (TWDB) Groundwater Database (https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp) is believed to be accurate and reliable; however, the TWDB assumes no responsibility for any errors appearing in rules or otherwise. Further, TWDB assumes no responsibility for the use of the information provided. PLEASE NOTE that users of these data are responsible for checking the accuracy, completeness, currency and/or suitability of all information themselves. TWDB makes no guarantees or warranties as to the accuracy, completeness, currency, or suitability of the information provided via the Groundwater Database (GWDB). TWDB specifically disclaims any and all liability for any errors damages that may result from providing GWDB data or the information it contains. For additional information or answers to questions concerning the TWDB GWDB, contact the Groundwater Data Team at GroundwaterData@twdb.texas.gov.

Texas Water Development Board Well Schedule

State Well No. 29 03 708 Previous Well No. County Karnes 255
River Basin San Antonio 09 Zone Z Lat. 285251 Long. 097 42 49 Coord I
Owner's Well No. #4 Location
Owner City of Runge Driller Cude Drilling Inc
Address 306 N. Heleng St Runge Tx 78/5/ Tenant/Oper.
Date Drilled 06 06. 1994 Depth 720 Depth Detum D Akitude 3/0 Alt. Datum
Aquifer Catabox la Tiff 12207/AV Type W User 253800
Well Construction Method Mud Rotage H Material Steel 5
Completion Screen Sixe Screen Steel S Well Screen or Slotted Zone (S) Open Hole (O)
Life Data Pump Mfr. Type Subm S No. Stages Camented from O to 315 Diam. Setting (feet)
Bowls Diam. in. Serting ft.Column Diam. in. (in.) From To
Mosor Mfr. Fuel or Flec E Horsepower 1 . COS 3/5 340
Yield Flow GPM Pump GPM Mess., Rept., Est Date , COS 400 G20
Performance Test Date Length of Test Production GPM
Static Level — ft. Pumping Level — ft. Drawdown — ft. Sp.Cap. — GPM/ft. 6 COS 700 710
Quality (Remarks
Water Use Primary Rublic P Secondary Tertiary s
Other Data Water Water Quality Logs Ocher Data
Daco 0923 1994 Mess 911 . 00 Belowhed. By Driller.
Wacer Date Mess. 12
Dane 19 19 19 19 19
· · · · · · · · · · · · · · · · · · ·
"
Recorded By Ron Mohn Date Record Collected 0.5 20 11997 (20 max) Reporting Agency 0.1
Remarks Drilled to 1000 Ft Pluced back to
720 94
Aquifer Cataboula Well No. 29.03.208
*(
93-0384 2993

ATTENTION OWNER: Confidentiality Privilege Notice on Reverse Side	ALL VILLE		State WELL	of Tex					P.	er Well Drille O. Box 12067 In, Texas 757	7
1) OWNER City of Ru: 2) LOCATION OF WELL: County Karnes	(Neme)					N. Helen: (Street or RFD (Street or RFD)	Runge, (Ch	n	(State)	(Zip)
Driller must complete the legal descript Cuarter- or Half-Scale Texas County G LEGAL DESCRIPTION: Section No Block I Distance and direction from two in XXI SER ATTACHED MAP	eneral Highway Map a	and attach 1	he map to this	form.							Motel
3) TYPE OF WORK (Check): XIXI New Well	4) PROPOSED Domestic trigation	UBE (Che Indus Test \	trial OMo			Public Supply De-Watering	XIO	LLING METH Aud Rotary C Mr Rotary C	Air Hamma	r 🗆 Jetted	
6) WELL LOQ: Date Drilling: Started 8-08 1994 Completed 10-06 1994	Dis. (in.) Fro	M OF HOL m (ft.) rincs	To (RL) 320 720	7	C	OREHOLE COM Open Hole Gravel Packet Gravel Packet Gravel Packet	XXIs	Straight Wall Other			
From (ft.) To (ft.)	Description and color of	of formation	n meterial	6		ABING, BLANK	-	D WELL SCR			
والمناف والمناف والمناف والمناف والمنافق والمناف	op Soil lay & Sand			Dia. (in.)	or Use	Perf., Slot	ted, etc.	nercial	From	g (ft.) To	Gage Cesting Screen
101 - 122 C	lay & Rocks			234	N	Stee1			0	315	
	and & Shale			8	N	Steel			315	340	005
	and & Shale			8	N	Screen Steel			340 400	400 620	.025
	and a Share					Screen		and the second	620	700	.018
398 - 460 S	and & Shale	ME	CE	W L	司	EMENTING DA	TA [Rule	287.44(1)]	700	710	
460 - 611 S	hale W/ Sand]		emented from _	315	t. to	ft. No. of Se	acks Used _	195
(Over)		-M	101110	hona			850 Press		R. No. of S	actus Useed _	35
13) TYPE PUMP: N/A	e side if necessary)	HH	NOV 18	11994	-	MADIOG CHARG		burton S	ervices	s-Pleas	anton
	☐ Submersible ☐	-	NATUNAL			TO THE PARTY OF TH					
Other		CARS	NOLTAVE	COM	利、尺	HIGHER COM	PLETION				
Depth to pump bowle, cylinder, jet,		n				Specified Surf	1000	100			
14) WELL TESTS:				1.		Specified Stee Pitiess Adapt	2 (SE)	70 (30.00)) }	
	Beller	XXX E	Estingued	1	200	Approved Alte				1]	
Yield: 458 gpm with 1	87 ft. drawdown	eter <u>36</u>	hrs.			4450m 4 6950					
15) WATER QUALITY:	44,			1 '	•	ATER LEVEL:	1	t. below lend s	urfaca	Dente 9-2	3-94
Did you knowingly penetrate any	strata which contained	undesirabi	lo	1		rtesian flow		gpr		Date	
constituents?	THILL TREPORT OF UND	ESIDADI E	WATER-	H-,	70 P	ACKERS:		Typ		Depth	
Type of water? Good				<u> </u>	4 7	2	_	Bask		320	
Was a chemical enalysis made?	XZ Yes □ No (520 -	700		_	2		Bask		610	
I hereby certify that this well was drilled by that failure to complete items 1 thru 15 will	me (or under my supe result in the log(s) bein	ervision) an	d that each an I for completion	d all of the	ne sta rubmi	demonts herein (are true to	the best of my	knowledge a	nd belief, 1 u	nderstand
	ling, Inc.			MEL	L DF	VILLER'S LICEN	BE NO.	3130 V	PKL		
ADDRESS P. O. Box 8		1	Ple	asant			T	exas	COLUMN TO THE REAL PROPERTY AND ADDRESS OF THE PARTY AND ADDRESS OF THE	78064	
(Bigned) 10-5	GAFD)	L		(City			!	(Sta		(Zip)	
(Licens	ed Well Driller)			u cet ida				Registered Dri			
Please ligach electric log, chemical analys	ls, and other pertinent	information	n, if avallable .			For TWC use	only: We	No. 7903	Z Loca	ted on map	



Texas Water Development Board

Ву		Division	70. A?_ 7	20 20
Chkd.	Date	Well Number _	79-03-7	08
County Karne	S			
	1,1,1	er Plan	4	
	Wate	rran		
	Ground Storage	# 4 ©- 708	-0 [#] 3 707	
	Storge	708	707	
	#200 C			
6	4704	Ground Storage		
13		71-75		
13				
	(Water)		Romp House	
	(Tower)		#1 1	
			Plused-P	
			705	
			W472	
	77	hm41	1-1-1-1-	
98-0502	annunga, etterning antilling at tyler i Washingsonische Hausturgsprong, at für ein der grünnigen erner Entwer	a erre waste - de sek ra gregor rejektiva vangin erre va prilate sektoragingen er sek ku		704
			79-	03-707
			'	~~ 709

Water Quality Field Data

79-03-708 County: Aquifer(s):

SWN:

Name: Address:

Sample No. 58/ Date: 5-20-

owner's well # 4

Bottle Bottle	N	Bottle 3	Bottle 4 Bottle 5		Bottle 6	Bottle	1 0		Total		
			<		2				SE PE	7	
500 ml	1 liter	250 ml	1 Nor					Ø	Samples	7	
Anions Ca	Cations	Nitrate	Radioactivity		×						7
2	2 ml	0.5 ml	& ml					4	All filtered	_	
I	HNO	H SO	HNO			×		5	unless other-	<u>-</u>	
	(Nitric)	(Sulfuric)	(Nitric)					wise	wise stipulated	D	
		Time in	5/5/ uje					Starting pH	Hd Bi	25	20
Water Level LSD Rem	Remark	中	Time out //6/5	Sample time	me	1550	۲.	14.8	14.8 ml. of 0.02N to	.02N	۵.
Temperature (00010)	26,6 €	Weather	VI	well use	ISB A	S	1	20	SO ml. of Sample	sample	
Specific Conductance (00094)	863 umhos/cm Outside Temp	s/cm Outside	Temp 80					Endir	Ending pH	34	7
PH (00400) 7,27		Sampli	Sampling point Fouceton WH	in Wh						ł	
Eh (00090) 73.3 mv.		Time:	1530 1535 1540 154 1550	154 15	22	ml.	£	Ē	표	Ë	핌
Phenol ALK (82244)	d mg	- F	[25 727 727]	727		4	222	B	6.10		
	296 mg/1	-,	979 877 /	1976		1	203	14	5.74		
₩ Wed	d mg/	ä			73.3	5	6,9314.5	14.5	5.19		
29	med/ 36/,2 mg/l	Cond	1988981	698		9	98'9	9.	2.96		
C			other notes:	Mes:		7	6.79	رد	4,60		
Total Anions (-)		***************************************				8	6.71	3	137		
(00600)						8	19.9				
		·-				0)	5,56				
						-	44				
						1	1				

FINAL ANALYSIS REPORT

LAB ID: 9704777 SAMPLE DESCRIPTION: Groundwater

FACILITY: TWDB SAMPLE DATE: 05/20/97

ACCT NO: TWDB SAMPLE TIME: 1550

TX WATER DEV. BOARD

DATE RECEIVED: 05/23/97

REPORT DATE: 08/19/97

LOCATION ID: 79-03-708

				PQL in	DATE
PARAMETER	RESULTS	UNITS	STORET #	WATER	ANALYZED
~~~~~					
Alkalinity, Phenol.	<1	mg/L	00415	1	05/29/97
Alkalinity, Total	268	mg/L	00410	1	05/29/97
Bromide	0.58	mg/L	71870	0.05	05/28/97
Chloride	99.2	mg/L	00941	0.1	05/28/97
Fluoride	0.46	mg/L	00950	0.02	05/28/97
Iodide, Laboratory	<0.15	mg/L	71965	0.05	05/27/97
Nit.,Nitrate/Nitrite	0.942	mg/L	00630	0.020	06/06/97
Nitrogen, Kjeldahl	<0.500	mg/L	00623	0.010	06/05/97
Nitrogen, ammonia	<0.100	mg/L	00608	0.010	06/09/97
Silica	48.70	mg/L	00955	0.01	06/02/97
Sulfate	40.40	mg/L	00946	0.10	05/28/97
Aluminum, Dis. ICPMS	<1.5	ug/L	01106	1.0	07/15/97
Antimony, Dis. ICPMS	<1.0	ug/L	01095	1.0	07/15/97
Arsenic, Diss. ICPMS	10.2	ug/L	01000	1.0	07/15/97
Barium, Diss. ICPMS	91.0	ug/L	01005	1.0	07/15/97
Beryllium, Dis ICPMS	<1.0	ug/L	01010	1.0	07/15/97
Boron, Diss. ICPMS	412.0	ug/L	01020	1.0	07/15/97
Calcium, Dissolved	34.60	mg/L	00915	0.50	06/11/97
Cobalt, Diss. ICPMS	<1.0	ug/L	01035	1.0	07/15/97
Copper, Diss. ICPMS	<1.0	ug/L	01040	1.0	07/15/97
Iron-AA, Dissolved	<15.00	ug/L	01046	15.00	06/19/97
Lead, Diss. ICPMS	<1.0	ug/L	01049	1.0	07/15/97
Lithium, Diss. ICPMS	51.7	ug/L	01130	1.0	07/15/97
Magnesium, Dissolved	9.50	mg/L	00925	0.05	06/11/97
Manganese, Dis ICPMS	<1.0	ug/L	01056	1.0	07/15/97
Molybdenum Dis ICPMS	1.9	ug/L	01060	1.0	07/15/97
Nickel, Diss. ICPMS	<1.0	ug/L	01065	1.0	07/15/97
Potassium, Dissolved	7.23	mg/L	00935	1.00	06/11/97
Selenium, Dis. ICPMS	<6.0	ug/L	01145	4.0	07/15/97

#### FINAL ANALYSIS REPORT

LAB ID: 9704777 SAMPLE DESCRIPTION: Groundwater

FACILITY: TWDB SAMPLE DATE: 05/20/97

ACCT NO: TWDB SAMPLE TIME: 1550

TX WATER DEV. BOARD

DATE RECEIVED: 05/23/97

REPORT DATE: 08/19/97

LOCATION ID: 79-03-708

PARAMETER	RESULTS	UNITS	STORET #	PQL in WATER	DATE ANALYZED
Sodium, Dissolved	151.00	mg/L	00930	0.10	06/11/97
Strontium, Dis ICPMS	920.0	ug/L	01080	1.0	07/15/97
Thallium, Diss ICPMS	<1.0	ug/L	01057	1.0	07/15/97
Vanadium, Diss ICPMS	31.5	ug/L	01085	1.0	07/15/97
Zinc, Diss. ICPMS	38.7	ug/L	01090	1.0	07/15/97

COMMENTS: Silica, NH3, TKN, NO3/NO2 subcontracted.

# TWDB Water Quality Field Data Sheet

Newly Inventoried Well 入ご

Anions / Total Alk. Proper Cation, Nutrient, and Alpha/Beta preservation requires adding enough of the correct acid to each sample fraction to bring the pH below 2.0 500ml (filtered) State Well Number: 17 ce Aquifer Code: County Code: Aquifer Id: County: 500ml (filtered) CAUKS -03-708 Nitric (HNO3) Cations CIRCLE EACH SAMPLE FRACTION COLLECTED: 250ml (filtered) ice + H2SO4 Well Name or #: Phone Number: Nutrient 3 Attention: Address: Name: City of RUMGE (878) 2 P. O. Box 40 ml (unfiltered) ice and in dark C 1 1 1 5 5 5 5 Atrazine 9 シアノーリング 5000 X 1 L (unfiltered) **Tritium** None S 5 Alpha & Beta 1 L (unfiltered) Nitric (HNO3) တ

Sample ID Number: 327Date: 312205Sampler(s): D. Wuerch

Calibration Verification Readings

pH 7 = 7.05A or 10 = 10.07SLP = 17.27 1000 = 10072000 = 19.70

5000 =

	1.2%	Time: 14:18 14:23 14:28
0	ble (at least 3 readings at five minute intervals) Notes:	Water Quality Stabilization Parameters Table
Hardness (as CaCO3): 139 Balanced: りょう	Filter pressure: hand pump(line)	Sample Time: 14:47
Items Below Calculated Later From Results:	Casing Size: "	Casing Type:
Phenol Alkalinity (82244): mg/L Total Alkalinity (39088): 554 mg/L	Latitude: <u>78°52'52.</u> " Longitude: <u>97°42'46."</u>	Lift: S  Power: E
tems below calculated from: mL acid added x 20 = Alkalinity	ā T	Well Use:
mL Acid added for Phenol (> 8.3)	Sampling Point: FALJ (wst. Nod)	Pumping Since: 14:08
7.57 Start pH 1.50 End pH	W.L. remark: 42 M.P. = 7	W. L. depth from LSD (ft.):
d Alkalinity Titration	Time Out: 14:50	Time In: しいっこ

Celsius Temp. (00010) 1

Conductivity (uS/cm):

00

Data Entered By Sampler Into Database

(yes)/ no

6.5

2,017

File No: 36899

CLIENT: Texas Water Development Board

Lab Order: 050

0503486

Client Sample ID: 79-03-708

Project:

TWDB FY05

Collection Date: 3/22/2005 2:42:00 PM

Date: 14-Apr-05

Lab ID:

0503486-006

Matrix: GROUNDWATER

Lab ID:	0503486-006					л. С	ROUND	WAILK	
Analyses		Storet	Result Q	ual PQ	L Units	DF	Batch II	Date A	nalyzed
ICP METALS D	ISSOLVED		1	E200.7				Analyst:	TH
Calcium			38.1	0.204	mg/L	1	32938	4/11/2005 4:2	
Magnesium			10.4	0.204	mg/L	1	32938	4/11/2005 4:2	5:35 PM
Potassium			9.09	0.204	mg/L	1	32938	4/11/2005 4:2	5:35 PM
Sodium			167	0.714	mg/L	1	32938	4/11/2005 4:2	5:35 PM
ICP METALS D	ISSOLVED		1	E200.7				Analyst:	TH
Boron			697	51	μg/L	1	32939	4/11/2005 4:2	5:35 PM
Iron			ND	51	μg/L	1	32939	4/11/2005 4:2	5:35 PM
Strontium			1180	20	μg/L	1	32939	4/11/2005 4:2	5:35 PM
ICPMS DISSOL	VED METALS		9	E200.8				Analyst:	sw
Aluminum			ND	4.08	μg/L	1	32738	3/30/2005	
Antimony			ND	1.02	μg/L	1	32738	3/30/2005	
Arsenic			12.7	2.04	μg/L	1	32738	3/30/2005	
Barium			79.3	1.02	μg/L	1	32738	3/30/2005	
Beryllium			ND	1.02	µg/L	1	32738	3/30/2005	
Cadmium			ND	1.02	μg/L	1	32738	3/30/2005	
Chromium			13.0	1.02	μg/L	1	32738	3/30/2005	
Cobalt			ND	1.02	μg/L	1	32738	3/30/2005	
Copper			4.50	1.02	μg/L	1	32738	3/30/2005	
Lead			ND	1.02	μg/L	1	32738	3/30/2005	
Lithium			54.3	2.04	μg/L	1	32738	3/30/2005	
Manganese			2.29	1.02	μg/L	1	32738	3/30/2005	
Molybdenum			3.36	1.02	μg/L	1	32738	3/30/2005	
Selenium			ND	4.08	μg/L	1	32738	3/30/2005	
Thallium			ND	1.02	μg/L	1	32738	3/30/2005	
Vanadium			27.3	1.02	μg/L	1	32738	3/30/2005	
Zinc			10.2	4.08	μg/L	1	32738	3/30/2005	
CATION/ANION	BALANCES		CAL	CULATION				Analyst:	AMJ
Cation/Anion Ba	alance	Ba	lanced	0	Date	1	32978	4/13/2005	
ANIONS BY IO	N CHROMATOGRAP	HY, DISSOLVE		E300				Analyst:	WR
Bromide Dissolv	ved		0.40	0.10	mg/L	5	32861	4/7/2005 1:06	:00 AM
Chloride Dissolv	/ed		109	5.00	mg/L	5	32861	4/7/2005 1:06	:00 AM
Fluoride Dissolv	/ed		0.64	0.05	mg/L	5	32861	4/7/2005 1:06	:00 AM
Sulfate Dissolve	ed		56.4	5.00	mg/L	5	32861	4/7/2005 1:06	:00 AM
ALKALINITY			N	12320 B				Analyst:	WR
Alkalinity, Phen	olphthalein		ND	0	mg/L CaCO	3 1	32774	4/1/2005	
Alkalinity, Total			292	2	mg/L CaCO		32774	4/1/2005	
NITRATE AND	NITRITE			E353.2				Analyst:	I W

Qualifiers:

- * Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- J Analyte detected below quantitation limits
- S Spike Recovery outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit

Date: 14-Apr-05

CLIENT: Lab Order: Texas Water Development Board

0503486

File No: 36899

Project:

TWDB FY05

0503486-006

Client Sample ID: 79-03-708

Collection Date: 3/22/2005 2:42:00 PM

Lab ID:	0503486-006				Matr	ix: G	ROUND	WATER	
Analyses		Storet	Result Qu	al PQL	Units	DF	Batch I	D Date A	nalyzed
NITRATE AND	- 11의 시간(1) (1) (		0.8626	353.2 0.0200	mg/L	1	32719	Analyst: 3/31/2005	LW
SILICA	ace a Mulle			370.1	mgrc	•	02713	Analyst:	LW
Silica, Dissolv	red (as SiO2)		50.8	0.50	mg/L	1	32714	3/30/2005	

#### Qualifiers:

- Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- Analyte detected below quantitation limits
- Spike Recovery outside accepted recovery limits
- Analyte detected in the associated Method Blank В
- H Holding times for preparation or analysis exceeded
- Not Detected at the Reporting Limit

Texas Water Development Board

Lab Order:

0503497

File No: 36910

Client Sample ID: 79-03-708

Project: Lab ID:

CLIENT:

TWDB FY05 0503497-006

Collection Date: 3/22/2005 2:42:00 PM

Matrix: GROUNDWATER

Date: 13-Apr-05

Analyses	Storet	Result Qual	PQL	Units	DF	Batch I	D Date A	nalyzed
RADIOLOGICALS		RADIOCI	HEM				Analyst:	SB
ALPHA, Gross	Sub	contracted	0	pcl/L	1	32946	3/31/2005	
BETA, Gross	Sub	contracted	0	pci/L	1	32946	3/31/2005	

Qualifiers:

Value exceeds Maximum Contaminant Level

E Value above quantitation range

Analyte detected below quantitation limits

Spike Recovery outside accepted recovery limits

Н

Analyte detected in the associated Method Brains
Holding times for preparation or analysis exceeded
Not Detected at the Reporting Limit

Page 6 of 14

79 03 70

Date: 13-Apr-05

CLIENT:	Texas Water Development	Board

Project: TWDB FY05

Lab Order: 0503497

#### **Work Order Sample Summary**

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
0503497-001A	79-10-408		3/21/2005 1:32:00 PM	3/25/2005
0503497-002A	78-16-609		3/21/2005 2:52:00 PM	3/25/2005
0503497-003A	66-33-510		3/22/2005 9:56:00 AM	3/25/2005
0503497-004A	67-47-607		3/22/2005 11:09:00 AM	3/25/2005
0503497-005A	67-54-204		3/22/2005 12:50:00 PM	3/25/2005
0503497-006A	79-03-708		3/22/2005 2:42:00 PM	3/25/2005
0503497-007A	67-40-503		3/23/2005 9:46:00 AM	3/25/2005
0503497-008A	67-39-517		3/23/2005 11:22:00 AM	3/25/2005
0503497-009A	67-31-602		3/23/2005 1:38:00 PM	3/25/2005
0503497-010A	67-32-704		3/23/2005 2:40:00 PM	3/25/2005
0503497-011A	67-40-301		3/23/2005 3:51:00 PM	3/25/2005
0503497-012A	66-43-812		3/24/2005 10:22:00 AM	3/25/2005
0503497-013A	66-34-207		3/24/2005 11:42:00 AM	3/25/2005
0503497-014A	66-25-103		3/24/2005 2:11:00 PM	3/25/2005

# JORDAN LABORATORIES, INCORPORATED ANALYTICAL & ENVIRONMENTAL CHEMISTS CORPUS CHRISTI, TEXAS April 05, 2005

LCRA ENVIRONMENTAL LAB 3505 Montopolis, EL 101 Austin, Texas 78744-1417

Report of Analysis

STORET

				04241	04242
Lab. No.	Identification	n		*Gross Alpha	*Gross Beta
			Date	Activity	Activity
		Time	(05)	pci/L	pci/L
79 10 408 M43-1176	0503497-001A	1:32 PM	3-21	25 +/- 8	28 +/- 5
78 16 609 M43-1177	0503497-002A			24 +/- 6	28 +/- 3
66 33510 M43-1178	0503497-003A	9:56 AM	3-22	3.0 +/- 4.0	4.8 +/- 2.5
67 47 60 7M43-1179	0503497-004A	11:09 AM	3-22	6.1 + / - 3.7	8.8 +/- 2.4
67 54 204 M43-1180	0503497-005A	12:50 PM	3-22	4.5 +/- 3.1	11 +/- 2
79 03708 M43-1181	0503497-006A	2:42 PM	3-22	16 +/- 4	15 +/- 2
67 40 503 M43-1182	0503497-007A	9:46 AM	3-23	1.2 +/- 2.6	7.2 +/- 2.1
67 395/7 M43-1183	0503497-008A	11:20 AM	3-23	4.7 + / - 4.1	12 +/- 3
9731602 M43-1184	0503497-009A	1:38 PM	3-23	6.9 +/- 3.6	16 +/- 3
6732 704 M43-1185	0503497-010A	2:40 PM	3-23	10 +/- 5	11 +/- 2
6740301 M43-1186	0503497-011A	3:51 PM	3-23	17 +/- 4	5.5 +/- 1.7
66 43 812 M43-1187	0503497-012A	10:22 AM	3-24	4.6 +/- 2.1	3.3 +/- 1.1
66 34 207 M43-1188	0503497-013A	11:42 AM	3-24	6.6 +/- 3.8	4.6 +/- 2.8
66 25 103 M43-1189	0503497-014A	2:11 PM	3-24	9.0 +/- 3.4	5.3 +/- 1.7

Analysts: Nixon/Moore

Analysis Date: 3-30-05, 3-31-05

Method: 900.0 Calibration: Alpha - Th230 Beta - Cs137

*Note: EPA Method 900.0 is a drinking water screening procedure. Its application to waters of high total dissolved solids may result in unacceptably high counting errors due to limitation on sample size. Recommended max is 500 mg/L.

Alternate method for determining activity may be considered.

Respectfully Submitted,

CIC

Carl F. Crownover, Pres.

form: S1-50

7903708



#### Texas Water Development Board (TWDB) Groundwater Database (GWDB) Well Information Report for State Well Number 79-11-204



State Well Number County River Basin Groundwater Management Area Regional Water Planning Area Groundwater Conservation District	7911204 Karnes San Antonio 15 L - South Central Texas Evergreen UWCD	Well Type Well Use Water Level Observation Water Quality Available	Withdrawal of Water Domestic Miscellaneous Measurements
River Basin  Groundwater Management Area  Regional Water Planning Area  Groundwater Conservation	San Antonio 15 L - South Central Texas	Water Level Observation	Anadra construction of the control o
Groundwater Management Area Regional Water Planning Area Groundwater Conservation	15 L - South Central Texas		Miscellaneous Measurements
Regional Water Planning Area Groundwater Conservation	L - South Central Texas	Water Quality Available	
Groundwater Conservation			Yes
1 THE 1 TO TO TO THE SHOULD IN THE SHOULD IN NOT THE SHOULD IN THE SHOU	Evergreen UWCD	Pump	Piston
	-	Pump Depth (feet below land surface)	W/m danill
Latitude (decimal degrees)	28.8725	Power Type	Windmill
Latitude (degrees minutes seconds)	28° 52' 21" N	Annular Seal Method	
Longitude (decimal degrees)	-97.705834	Surface Completion Owner	Paul Natho
Longitude (degrees minutes seconds)	097° 42' 21" W	Driller	raui Natrio
Coordinate Source	+/- 10 Seconds	Other Data Available	
Aquifer Code	1220KVL - Oakville Sandstone		
Aquifer	Gulf Coast	Well Report Tracking Number	
Aquifer Pick Method		Plugging Report Tracking Number	
Land Surface Elevation (feet above sea level)	300	U.S. Geological Survey Site Number	
Land Surface Elevation Method	Interpolated From Topo Map	Texas Commission on Environmental Quality Source Id	
Well Depth (feet below land surface)	57	Groundwater Conservation	
Well Depth Source	Another Government Agency	District Well Number	
Drilling Start Date		Owner Well Number	
Drilling End Date		Other Well Number	
Drilling Method		Previous State Well Number	
Borehole Completion		Reporting Agency	U.S. Geological Survey
		Created Date	9/9/1999
		Last Update Date	9/9/1999
Remarks			
Casing - No Data			
Well Tests - No Data			
Lithology - No Data			
Annular Seal Range - No D	)ata		
Borehole - No Data	P	lugged Back - No Data	


Filter Pack - No Data

Packers - No Data



## Texas Water Development Board (TWDB) Groundwater Database (GWDB) Well Information Report for State Well Number 79-11-204





Status Code	Date	Time	Water Level (ft. below land surface)	Change value in ( ) indicates rise in level	Water Elevation (ft. above sea level)	Meas #	Measuring Agency	Method	Remark ID	Comments
Р	4/21/1956		38	3	262	1	U.S. Geological Survey	Steel Tape	1	

#### **Code Descriptions**

Status Code Status Description

Р

Publishable



#### **Texas Water Development Board (TWDB) Groundwater Database (GWDB)** Well Information Report for State Well Number 79-11-204



#### Water Quality Analysis

Sample Date: 4/6/1937

Sample Time:

0000

Sample Number:

Collection Entity: Other Federal Agencies

Sampled Aquifer:

Oakville Sandstone

Analyzed Lab: WPA

Reliability: From a report; unknown sample collection & preservation

Collection Remarks:

Analysis taken from M-151

Parameter Code	Parameter Description	Flag	Value*	Units	Plus/Minus
00415	ALKALINITY, PHENOLPHTHALEIN (MG/L)		0	mg/L	
00410	ALKALINITY, TOTAL (MG/L AS CACO3)		299.91	mg/L as CACO 3	
00440	BICARBONATE ION, CALCULATED (MG/L AS HCO3)		366	mg/L	
00910	CALCIUM (MG/L)		121	mg/L	
00445	CARBONATE ION, CALCULATED (MG/L AS CO3)		0	mg/L	
00940	CHLORIDE, TOTAL (MG/L AS CL)		250	mg/L	
00900	HARDNESS, TOTAL, CALCULATED (MG/L AS CACO3)		380	mg/L as CACO 3	
00920	MAGNESIUM (MG/L)		19	mg/L	
71860	RESIDUAL SODIUM CARBONATE, CALCULATED		0		
00931	SODIUM ADSORPTION RATIO, CALCULATED (SAR)		3.35		
00932	SODIUM, CALCULATED, PERCENT		46	PCT	
00929	SODIUM, TOTAL (MG/L AS NA)	calculate d		mg/L	
00945	SULFATE, TOTAL (MG/L AS SO4)		54	mg/L as SO4	
70301	TOTAL DISSOLVED SOLIDS , SUM OF CONSTITUENTS (MG/L)		773	mg/L	

^{*} Value may not display all significant digits for parameter in results, check Scanned Documents for laboratory paperwork..

GWDB DISCLAIMER: Except where noted, all of the information provided in the Texas Water Development Board (TWDB) Groundwater Database (https://www.twdb.texas.gov/groundwater/data/gwdbrpt.asp) is believed to be accurate and reliable; however, the TWDB assumes no responsibility for any errors appearing in rules or otherwise. Further, TWDB assumes no responsibility for the use of the information provided. PLEASE NOTE that users of these data are responsible for checking the accuracy, completeness, currency and/or suitability of all information themselves. TWDB makes no guarantees or warranties as to the accuracy, completeness, currency, or suitability of the information provided via the Groundwater Database (GWDB). TWDB specifically disclaims any and all liability for any claims or damages that may result from providing GWDB data or the information it contains. For additional information or answers to questions concerning the TWDB GWDB, contact the Groundwater Data Team at GroundwaterData@twdb.texas.gov.

#### Texas Water Development Board Well Schedule

State Well No. 79 11 204 Previous Well No. E-37 396 County	Kar	nes 255
River Basin San Autonio 79 Zone 2 Lat. 2852 20 Long.	097 42	20 20 3
Owner's Well No Location 1/4 1.4. Section, Block	, s	птька
Owner Paul Watho		
T	<u> </u>	
Address	300	Source of Alt. Datum
MI 1/2 CE Well I	User [	Alt. Datum
Aquifer ID \( \sqrt{5} \) \\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	_	
Well Const Casing	_	
Construction Method Matenai	Well Screen or	k Pipe (C) Slotted Zone (S)
Screen	Open Hole (O) Cemented from	
Completion Material	Diam.	Setting (feet)
Lift Data Pump Mfr. Type windmill P Setting	06	
)		
Yield FlowGPM PumpGPM Mean_Rept_Est Date	ШШ	
Performance Test Date Length of Test Production GPM ,	$\Box$	
Static Levelft. Pumping Levelft. Drawdownft. Sp.Cap GPM/ft. 。		
Water Use Primary dom. H Secondary Stock S Terriary		
Quality (Remarks)		
Other Data Water Water Available Love Quality Logs Data		<del></del>
		++++
Date 04 21 / 956 Meas. 38 · 0 0565		
Water Date Meas.		
Date Date Meas.		
	1-1-1-	
19	' <del>                                     </del>	
Recorded By PLN Date Record Collected or Updated		
necorded by 7277	Omax) Repo	orting Agency 02
Remarks	++++	1
<del></del>		4
1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		1
		Dat villa
		Aquiter <u>Oakville</u> Well No. 7911204
17.0402-77-07	: <u>!</u>	Twell Lot () [] DEO.

#### **ATTACHMENT No. 13**

#### DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

#### **SECTION 7**

#### GROUND WATER QUALITY TECHNICAL REPORT

### DOMESTIC WORKSHEET 3.0 SECTION 7

#### GROUND WATER QUALITY TECHNICAL REPORT


The nearby private water wells are outside the 250' buffer zone required by 30 TAC Section 309.13(c). The nearest well is +/-550' from the land disposal site; however, the land disposal site does not drain to the well. The storage pond liner consists of two feet of clay meeting liner permeability requirements in 30 TAC 217.203(d). Therefore, the impact of the waste disposal site on the groundwater is negligible.

#### **ATTACHMENT No. 14**

## DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

#### **SECTION 8**

**USDA SOIL SURVEY MAP** 



Soils

Soil Map Unit Polygons

Soil Map Unit Points Soil Map Unit Lines

Special Point Features

Blowout Borrow Pit

**Gravel Pit** Closed Depression

Clay Spot

Landfill **Gravelly Spot** 

Lava Flow

Marsh or swamp

0 Miscellaneous Water Mine or Quarry

Perennial Water

8

Rock Outcrop

Saline Spot

Severely Eroded Spot Sandy Spot

Sinkhole

8 Slide or Slip

Sodic Spot

23 Very Stony Spot Stony Spot

Other

Wet Spot

Special Line Features

contrasting soils that could have been shown at a more detailed misunderstanding of the detail of mapping and accuracy of soil

line placement. The maps do not show the small areas of

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause

The soil surveys that comprise your AOI were mapped at

MAP INFORMATION

Streams and Canals

Water Features

Transportation + Rails

**US** Routes

Major Roads

Local Roads

Background

Interstate Highways

Aerial Photography

of the version date(s) listed below.

This product is generated from the USDA-NRCS certified data as

Albers equal-area conic projection, should be used if more

distance and area. A projection that preserves area, such as the projection, which preserves direction and shape but distorts

accurate calculations of distance or area are required

Maps from the Web Soil Survey are based on the Web Mercator

Coordinate System: Web Mercator (EPSG:3857)

Web Soil Survey URL:

Source of Map: Natural Resources Conservation Service

measurements.

Please rely on the bar scale on each map sheet for map

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Survey Area Data: Version 21, Aug 30, 2024

Karnes County, Texas

Soil Survey Area:

Date(s) aerial images were photographed: May 28, 2010—Oct 17, 2017

compiled and digitized probably differs from the background shifting of map unit boundaries may be evident. imagery displayed on these maps. As a result, some minor The orthophoto or other base map on which the soil lines were

#### **Map Unit Legend**

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CbC	Colibro sandy clay loam, 3 to 5 percent slopes	0.0	0.0%
СоВ	Coy clay loam, 1 to 3 percent slopes	5.8	14.7%
PnC	Pernitas sandy clay loam, 2 to 5 percent slopes	26,4	67.5%
ShC	Schattel clay loam, 2 to 5 percent slopes	2.0	5.2%
WaC	Weesatche fine sandy loam, 2 to 5 percent slopes	4.9	12.5%
Totals for Area of Interest		39.1	100.0%

#### **ATTACHMENT No. 15**

## DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0 LAND DISPOSAL OF EFFLUENT

**SECTION 8** 

**SOIL ANALYSIS** 





October 11, 2024

**Brian Cope** 

Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio, TX 78217

SATL Report No.:

2410011

RE: City of Runge Irrigation Site

Dear Brian Cope

SATL received 9 Sample(s) on 10/01/2024 for analyses identified on the chain of custody. The analyses were performed using methods indicated on the laboratory report. Any deviations observed at sample receiving are notated on the Sample Receipt Checklist and/or Chain of Custody documents attached as part of this analytical report.

Sincerely,

For San Antonio Testing Laboratory, Inc.

Marcela G. Hawk,

President

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

1610 S. Laredo Street, San Antonio, Texas 78207-7029

(210) 229-9920

Fax (210) 229-9921

www.satestinglab.com

Project Number: [none] Additional Notes:

10/01/24 11:24

Report No. 2410011





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported:

10/11/24 14:30 **Received:** 

#### SAMPLE SUMMARY

Total Samples received in this work order:

9

The following samples were requested for analysis as per the CoC. Any re-runs or re-analyses requested are identified as such.

Sample ID	Laboratory ID	Matrix	Sampling Method	Date Sampled	Date Received
Schattel Clay Shc 0-6"	2410011-01	Solid	Grab	10/01/24 08:00	10/01/24 11:24
Schattel Clay Shc 6-18"	2410011-02	Solid	Grab	10/01/24 08:05	10/01/24 11:24
Schattel Clay Shc 18-30"	2410011-03	Solid	Grab	10/01/24 08:10	10/01/24 11:24
Pernitas Sandy Clay 0-6"	2410011-04	Solid	Grab	10/01/24 08:15	10/01/24 11:24
Pernitas Sandy Clay 6-18"	2410011-05	Solid	Grab	10/01/24 08:20	10/01/24 11:24
Pernitas Sandy Clay 18-30"	2410011-06	Solid	Grab	10/01/24 08:25	10/01/24 11:24
Coy Clay Loam 0-6"	2410011-07	Solid	Grab	10/01/24 08:30	10/01/24 11:24
Coy Clay Loam 6-18"	2410011-08	Solid	Grab	10/01/24 08:35	10/01/24 11:24
Coy Clay Loam 18-30"	2410011-09	Solid	Grab	10/01/24 08:40	10/01/24 11:24

#### Notes

All quality control samples and checks are within acceptance limits unless otherwise indicated.

Test results pertain only to those items tested.

All samples were in good condition when received by the laboratory unless otherwise noted.

Page 2 of 16

Project Number: [none]

Additional Notes:				Magnesium *		427	mg/kg dry	20.0	
1 Identification of the state o				Magnesium, Available 427	mg/kg dry 20.0				
				Potassium, Available		196	mg/kg dry	100	
				Sodium *		433	mg/kg dry	20.0	
				Sodium, Available *		433	mg/kg dry	20.0	
Sample ID #: Schattel Clay Shc 0-6" Sample Matrix: Solid				Sulfur		204	mg/kg dry	20.0	
Analyte	Result	Units	PQL	Sulfur, Available		204	mg/kg dry	20.0	
General Chemistry				\$1.500 CO 100 St 100 100 CO 10			10/01/24 11	:24	
% Solids	93.7	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	521	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:10	USDAHB60	JA	
Ammonia-Nitrogen *	50.4	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 13:00	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	975	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:03	EPA 351.3	SG	
Total Nitrogen	1040	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:03	CALC	SG	
SoilpH measured in H20@ Cbelow	7.46	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:10	EPA 9045D	DD	Н
pH measured @Temperature >>	20	C	0.10	EPA 9045D	B441167	10/07/24 12:10	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.16	mg/kg	0.10	EPA 300.0	B441221	10/08/24 21:11	EPA 300.0	JA	
Nitrate as N *	2.53	mg/kg	0.10	EPA 300.0	B441221	10/08/24 21:11	EPA 300.0	JA	
Available Metals by Mehlich III l	Extraction								
Calcium *	20000	mg/kg dry	20.0			R	eport No. 2410	0011	
Calcium, Available	20000	mg/kg dry	20.0	L					





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217

Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported:

10/11/24 14:30

Received:

Sampling Method: Grab	Lab Sample ID #: 2410011-01
Date/Time Collected: 10/01	/24 08:00

Notes

Prep Method	Batch	Analy
r rep memou	Dutti	2 2 2 2 2 2 3

Method Analyst vzed

Genera	Chemistry	
--------	-----------	--

Calcium *	21300	mg/kg dry	20.0
Calcium, Available	21300	mg/kg dry	20.0
Magnesium *	443	mg/kg dry	20.0
Magnesium, Available 443 mg/kg dry 20.0 l	Phosphorus, Ava	ailable <20.0 mg/kg	g dry 20.0
Potassium, Available	186	mg/kg dry	100
Sodium *	524	mg/kg dry	20.0
Sodium, Available *	524	mg/kg dry	20.0
Sulfur	273	mg/kg dry	20.0
Sulfur, Available	273	mg/kg dry	20.0
		10/01/24 11	:24

Report No. 2410011

	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
Page 3 of 16	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SJ
	Mehlich-III	B441192	10/08/24 16:34	M-III/6010	SI

(210) 229-9920

Project Number: [none]

Additional Notes:

Sampling Method: Grab Lab Sample ID #: 2410011-02 Date/Time Collected: 10/01/24 08:05

Method Analyst Notes Prep Method Analyzed Batch B441192 10/08/24 17:07 M-III/6010 Mehlich-III SJ Sample ID #: Schattel Clay Shc 6-18" Sample Matrix: Solid Mehlich-III B441192 10/08/24 17:07 M-III/6010 SJ Analyte Units **PQL** Result Mehlich-III B441192 10/08/24 17:07 M-III/6010 SJ M-III/6010 Mehlich-III B441192 10/08/24 17:07 SJ % Calc B441163 10/08/24 09:35 ASTM D2216 % Solids 91.5 % by Wt. 0.100 TW SM2510B B441263 10/07/24 12:11 USDAHB60 Conductivity (@25C) 387 umhos/cm 1.00 JA SM4500NH3B 10/10/24 13:10 SM4500NH3C Ammonia-Nitrogen * 44.8 mg/kg 10.0 B441261 SG Total Kjeldahl Nitrogen mg/kg 1.00 EPA 351.3 B441275 10/10/24 12:05 EPA 351.3 SG 846 Total Nitrogen 927 mg/kg dry 1.20 [CALC] [CALC] 10/10/24 12:05 CALC SG pH Units EPA 9045D B441167 10/07/24 12:11 EPA 9045D Н SoilpH measured in H20@ Cbelow 8.34 0.10 DD C EPA 9045D B441167 10/07/24 12:11 EPA 170.1 Н pH measured @Temperature >> 21 0.10 DD Anions by Ion Chromatography EPA 300.0 EPA 300.0 Nitrite as N * 0.20 mg/kg 0.10 B441221 10/08/24 21:29 JA EPA 300.0 Nitrate as N * 2.06 mg/kg 0.10 EPA 300.0 B441221 10/08/24 21:29 JA

www.satestinglab.com

Available Metals by Mc10c6IIL Fredre Street, San Antonio, Texas 78207-7029

Fax (210) 229-9921





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope Project: City of Runge Irrigation Site **Reported:** 10/11/24 14:30

Received:

Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:07	M-III/6010	SJ
			Page 4 of 16	i

Sampling Method: Grab Lab Sample ID #: 2410011-03 Date/Time Collected: 10/01/24 08:10

Prep Method Batch

Analyzed Method Analyst Notes

Project Number: [none]

Additional Notes:

Sample ID #: Schattel Clay Shc 18-30" Sample Matrix: Solid

Analyte	Result	Units	PQL						
General Chemistry									
% Solids	90.6	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	336	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:12	USDAHB60	JA	
Ammonia-Nitrogen *	28.0	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 13:20	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	549	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:08	EPA 351.3	SG	
Total Nitrogen	607	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:08	CALC	SG	
SoilpH measured in H20@ Cbelow	8.27	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:12	EPA 9045D	DD	Н
pH measured @Temperature >>	21	C	0.10	EPA 9045D	B441167	10/07/24 12:12	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.18	mg/kg	0.10	EPA 300.0	B441221	10/08/24 21:47	EPA 300.0	JA	_
Nitrate as N *	0.80	mg/kg	0.10	EPA 300.0	B441221	10/08/24 21:47	EPA 300.0	JA	
Available Metals by Mehlich III E	xtraction								
Calcium *	26200	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Calcium, Available	26200	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Magnesium *	400	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Magnesium, Available 400 mg/kg dry 20.0	Phosphorus A		g/kg dry	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
20.0	r nospnorus, r	17 dil do 10 - 20 - 0 - 11	5 ng ur j	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
	120		100	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Potassium, Available	130	mg/kg dry	100	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Sodium *	594	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Sodium, Available *	594	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Sulfur	266	mg/kg dry	20.0	Mehlich-III	B441192	10/08/24 17:13	M-III/6010	SJ	
Sulfur, Available	266	mg/kg dry	20.0				Page	e 5 of 16	j

Project Number: [none]

Report No. 2410011

10/01/24 11:24

Additional Notes:





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope

Project: City of Runge Irrigation Site

**Reported:** 10/11/24 14:30

Received:

Project Number: [none]

Sample ID #: Pernitas Sandy Cla	y 0-6" Sample	e Matrix: Solid					Pag	ge 6 of 16	,
Analyte	Result	Units	PQL						
General Chemistry				Additional Notes:					
% Solids	92.3	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	259	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:13	USDAHB60	JA	
Ammonia-Nitrogen *	50.4	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 13:40	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	1290	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:09	EPA 351.3	SG	
Total Nitrogen	1400	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:09	CALC	SG	
SoilpH measured in H20@ Cbelow	7.85	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:13	EPA 9045D	DD	Н
pH measured @Temperature >>	21	C	0.10	EPA 9045D	B441167	10/07/24 12:13	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.16	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:04	EPA 300.0	JA	
Nitrate as N*	4.03	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:04	EPA 300.0	JA	
Available Metals by Mehlich III	Extraction								
Calcium *	3820	mg/kg dry	20.0	Sample ID #: Pernitas	Sandy Cla	y 6-18" Sample	Matrix: Solid		
Calcium, Available 3820 mg/kg dry 20.0	Magnesium * 16	62 mg/kg dry 20.0		Analyte		Result	Units	PQL	
Magnesium, Available 162 mg/kg dry 20	.0 Phosphorus, A	wailable 46.9 mg/	kg dry						
20.0									
Potassium, Available	364	mg/kg dry	100						
Sodium *	352	mg/kg dry	20.0						
Sodium, Available *	352	mg/kg dry	20.0						
Sulfur	316	mg/kg dry	20.0						
Sulfur, Available	316	mg/kg dry	20.0						
	1	0/01/24 11:24							

Report No. 2410011

Sampling Method: Grab Lab Sample ID #: 2410011-04

Date/Time Collected: 10/01/24 08:15

Prep Method Notes	Batch	Analyzed	Method An	alyst
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:19	M-III/6010	SJ





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope

Project: City of Runge Irrigation Site

**Reported:** 10/11/24 14:30 **Received:** 

General Chemistry				Additional Notes:					
% Solids	92.5	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	247	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:14	USDAHB60	JA	
Ammonia-Nitrogen *	50.4	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 13:50	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	863	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:10	EPA 351.3	SG	
Total Nitrogen	936	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:10	CALC	SG	
SoilpH measured in H20@ Cbelow	7.49	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:14	EPA 9045D	DD	Н
pH measured @Temperature >>	20	C	0.10	EPA 9045D	B441167	10/07/24 12:14	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.17	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:22	EPA 300.0	JA	
Nitrate as N *	2.96	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:22	EPA 300.0	JA	
Available Metals by Mehlich III	Extraction								
Calcium *	4840	mg/kg dry	20.0	Sample ID #: Pernitas	Sandy Cla	y 18-30" Sampl	e Matrix: Soli	d	
Calcium, Available 4840 mg/kg dry 20.0	Magnesium *	165 mg/kg dry 20.0		Analyte		Result	Units	PQL	
Magnesium, Available 165 mg/kg dry 20	.0 Phosphorus,	Available 34.5 mg/	kg dry						
20.0									
Potassium, Available	380	mg/kg dry	100						
Sodium *	346	mg/kg dry	20.0						
Sodium, Available *	346	mg/kg dry	20.0						
Sulfur	335	mg/kg dry	20.0						
Sulfur, Available	335	mg/kg dry	20.0						
		10/01/24 11:24							

Report No. 2410011

Sampling Method: Grab Lab Sample ID #: 2410011-05

Date/Time Collected: 10/01/24 08:20

Prep Method Notes	Batch	Analyzed	Method A	Analyst
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:41	M-III/6010	SJ
			Page 7 of	16

Project Number: [none]





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217

Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported: 10/11/24 14:30 Received:

General Chemistry				Additional Notes:					
% Solids	91.2	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	196	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:15	USDAHB60	JA	
Ammonia-Nitrogen *	28.0	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 14:00	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	1140	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:11	EPA 351.3	SG	
Total Nitrogen	1250	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:11	CALC	SG	
SoilpH measured in H20@ Cbelow	7.97	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:15	EPA 9045D	DD	Н
pH measured @Temperature >>	20	C	0.10	EPA 9045D	B441167	10/07/24 12:15	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.13	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:40	EPA 300.0	JA	
Nitrate as N *	1.07	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:40	EPA 300.0	JA	
Available Metals by Mehlich III	Extraction								
Calcium *	5430	mg/kg dry	20.0	Sample ID #: Coy Cla	y Loam 0-6	" Sample Matri	x: Solid		
Calcium, Available 5430 mg/kg dry 20.0	Magnesium * 1	55 mg/kg dry 20.0		Analyte		Result	Units	<b>PQL</b>	
Magnesium, Available 155 mg/kg dry 20.	.0 Phosphorus, A	Available 31.0 mg/	kg dry						
20.0									
Potassium, Available	407	mg/kg dry	100						
Sodium *	352	mg/kg dry	20.0						
Sodium, Available *	352	mg/kg dry	20.0						
Sulfur	473	mg/kg dry	20.0						
Sulfur, Available	473	mg/kg dry	20.0						
	1	0/01/24 11:24							

Report No. 2410011

Sampling Method: Grab Lab Sample ID #: 2410011-06 Date/Time Collected: 10/01/24 08:25

B441192

Mehlich-III

Prep Method Batch Analyzed Method Analyst Notes Mehlich-III B441192 10/08/24 17:46 M-III/6010 SJ Mehlich-III B441192 10/08/24 17:46 M-III/6010 SJ Mehlich-III M-III/6010 B441192 10/08/24 17:46 SJ Mehlich-III B441192 10/08/24 17:46 M-III/6010 SJ Mehlich-III B441192 M-III/6010 10/08/24 17:46 SJ Mehlich-III B441192 10/08/24 17:46 M-III/6010

10/08/24 17:46

M-III/6010 Page 8 of 16

Project Number: [none]

SJ

SJ





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope Project: City of Runge Irrigation Site Reported: 10/11/24 14:30 Received:

General Chemistry				Additional Notes:					
% Solids	93.6	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	247	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:16	USDAHB60	JA	
Ammonia-Nitrogen *	50.4	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 14:10	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	605	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:12	EPA 351.3	SG	
Total Nitrogen	648	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:12	CALC	SG	
SoilpH measured in H20@ Cbelow	7.42	pH Units	0.10	EPA 9045D	B441167	10/07/24 12:16	EPA 9045D	DD	Н
pH measured @Temperature >>	20	C	0.10	EPA 9045D	B441167	10/07/24 12:16	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.19	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:58	EPA 300.0	JA	
Nitrate as N *	0.66	mg/kg	0.10	EPA 300.0	B441221	10/08/24 22:58	EPA 300.0	JA	
Available Metals by Mehlich III I	Extraction								
Calcium *	4080	mg/kg dry	20.0	Sample ID #: Coy Clay	Loam 6-1	8" Sample Mat	rix: Solid		
Calcium, Available 4080 mg/kg dry 20.0	Magnesium * 1	67 mg/kg dry 20.0		Analyte		Result	Units	PQL	
Magnesium, Available 167 mg/kg dry 20.	0 Phosphorus,	Available <20.0 m	g/kg dry						
20.0									
Potassium, Available	232	mg/kg dry	100						
Sodium *	338	mg/kg dry	20.0						
Sodium, Available *	338	mg/kg dry	20.0						
Sulfur	297	mg/kg dry	20.0						
Sulfur, Available	297	mg/kg dry	20.0						
	1	10/01/24 11:24							

Report No. 2410011

Sampling Method: Grab Lab Sample ID #: 2410011-07

Date/Time Collected: 10/01/24 08:30

Prep Method Notes	Batch	Analyzed	Method	Analyst
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:52	M-III/6010	SJ
			Page 9 of	16

Project Number: [none]





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported: 10/11/24 14:30 Received:

General Chemistry				Additional Notes:					
% Solids	91.0	% by Wt.	0.100	% Calc	B441163	10/08/24 09:35	ASTM D2216	TW	
Conductivity (@25C)	156	umhos/cm	1.00	SM2510B	B441263	10/07/24 12:17	USDAHB60	JA	
Ammonia-Nitrogen *	44.8	mg/kg	10.0	SM4500NH3B	B441261	10/10/24 14:20	SM4500NH3C	SG	
Total Kjeldahl Nitrogen	840	mg/kg	1.00	EPA 351.3	B441275	10/10/24 12:13	EPA 351.3	SG	
Total Nitrogen	924	mg/kg dry	1.20	[CALC]	[CALC]	10/10/24 12:13	CALC	SG	
SoilpH measured in H20@ Cbelow	7.86	pH Units	0.10	EPA 9045D	B441206	10/07/24 12:17	EPA 9045D	DD	Н
pH measured @Temperature >>	21	C	0.10	EPA 9045D	B441206	10/07/24 12:17	EPA 170.1	DD	Н
Anions by Ion Chromatography									
Nitrite as N *	0.14	mg/kg	0.10	EPA 300.0	B441221	10/08/24 23:16	EPA 300.0	JA	
Nitrate as N *	0.17	mg/kg	0.10	EPA 300.0	B441221	10/08/24 23:16	EPA 300.0	JA	
Available Metals by Mehlich III	Extraction								
Calcium *	5090	mg/kg dry	20.0	Sample ID #: Coy Cla	y Loam 18-	30" Sample Ma	trix: Solid		
Calcium, Available 5090 mg/kg dry 20.0	Magnesium * 2	28 mg/kg dry 20.0		Analyte		Result	Units	PQL	
Magnesium, Available 228 mg/kg dry 20	.0 Phosphorus,	Available <20.0 m	g/kg dry						
20.0									
Potassium, Available	238	mg/kg dry	100						
Sodium *	351	mg/kg dry	20.0						
Sodium, Available *	351	mg/kg dry	20.0						
Sulfur	315	mg/kg dry	20.0						
Sulfur, Available	315	mg/kg dry	20.0						
	1	0/01/24 11:24							

Report No. 2410011

Sampling Method: Grab Lab Sample ID #: 2410011-08

Date/Time Collected: 10/01/24 08:35

Prep Method Notes	Batch	Analyzed	Method	Analyst
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
Mehlich-III	B441192	10/08/24 17:57	M-III/6010	SJ
			Page 10 o	of 16

Project Number: [none]





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported: 10/11/24 14:30 Received:

**General Chemistry** Sampling Method: Grab Lab Sample ID #: 2410011-09 Date/Time 10/08/24 09:35 **ASTM D2216** % by Wt. B441163 % Solids 90.6 0.100 % Calc TW Conductivity (@25C) 169 umhos/cm 1.00 SM2510B B441263 10/07/24 12:19 USDAHB60 JA SM4500NH3C Ammonia-Nitrogen * 11.2 mg/kg 10.0 SM4500NH3B B441261 10/10/24 14:30 SG mg/kg EPA 351.3 B441275 10/10/24 12:14 EPA 351.3 Total Kjeldahl Nitrogen 650 1.00 SG Total Nitrogen 718 mg/kg dry 1.20 [CALC] [CALC] 10/10/24 12:14 CALC SG pH Units EPA 9045D B441206 10/07/24 12:19 EPA 9045D H SoilpH measured in H20@ Cbelow 7.53 0.10 DD C B441206 10/07/24 12:19 EPA 170.1 H pH measured @Temperature >> 0.10 EPA 9045D 20 DD Anions by Ion Chromatography Nitrite as N * 10/08/24 23:34 EPA 300.0 0.12 mg/kg 0.10 EPA 300.0 B441221 JA Nitrate as N * < 0.10 mg/kg 0.10 EPA 300.0 B441221 10/08/24 23:34 EPA 300.0 JA Available Metals by Mehlich III Extraction Calcium * 20.0 Collected: 10/01/24 08:40 mg/kg dry Calcium, Available 6820 mg/kg dry 20.0 Magnesium * 186 mg/kg dry 20.0 Method Analyst Notes Prep Method Batch Analyzed Magnesium, Available 186 mg/kg dry 20.0 Phosphorus, Available <20.0 mg/kg dry 20.0 Mehlich-III B441192 10/08/24 18:03 M-III/6010 SI Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ Potassium, Available 156 100 mg/kg dry Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ Sodium * 358 20.0 mg/kg dry Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ Sodium, Available * 358 mg/kg dry 20.0 Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ Sulfur 495 20.0 mg/kg dry Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ Sulfur, Available 495 mg/kg dry 20.0 Mehlich-III B441192 10/08/24 18:03 M-III/6010 SJ 10/01/24 11:24 Mehlich-III B441192 M-III/6010 10/08/24 18:03 SJ

Page 11 of 16

SJ

SJ

Project Number: [none] Additional Notes:

10/01/24 11:24

10/08/24 18:03

10/08/24 18:03

B441192

B441192

Mehlich-III

Mehlich-III

Report No. 2410011

M-III/6010

M-III/6010

General Chemistry - Quality Control

		Reporting		Spike	Source		%REC		RPD	
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit	
Analyte	Result									

#### Batch B441167 - EPA 9045D

LCS (B441167-BS1)		Prepared: 10/07/24 08:45 Analyzed: 10/07/24 08:45							
SoilpH measured in H20@ Cbelow	7.05	0.10	pH Units	17.5	40	97.5-102.5	L		
pH measured @Temperature >>	20.2	0.10	C			0-200			

Duplicate (B441167-DUP1)

Source: 2409443-17

Report No. 2410011

Prepared: 10/07/24 12:00 Analyzed: 10/07/24 12:01





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217		1277.5	Manager: B City of Rur	rian Cope nge Irrigation Site				Repor 10/11/24 Receiv	14:30
SoilpH measured in H20@ Cbelow	9.70	0.10	pH Units	9.69			0.1	20	Н
pH measured @Temperature >>	20.5	0.10	C	20.5			0	30	Н
Batch B441206 - EPA 9045D									
LCS (B441206-BS1)				Prepared: 10/07/24 0	8:45 Analyz	:d: 10/07/24	0 ::45		
SoilpH measured in H20@ Cbelow	7.05	0.10	pH Units	7.00	101	97.5-102.5			
pH measured @Temperature >>	20.2	0.10	С			0-200			
Duplicate (B441206-DUP1)		Source: 24100	11-08	Prepared: 10/07/24 1	2:00 Analyz	:d: 10/07/24	1 :18		
SoilpH measured in H20@ Cbelow	7.87	0.10	pH Units	7.86			0.1	20	Н
pH measured @Temperature >>	20.6	0.10	C	20.6			0	30	Н
Batch B441261 - SM4500NH3B									
Blank (B441261-BLK1)				Prepared: 10/09/24 1	0:00 Analyze	d: 10/10/24	12:00		
Ammonia-Nitrogen	<10.0	10.0	mg/kg						
LCS (B441261-BS1)				Prepared: 10/09/24 1	0:00 Analyze	d: 10/10/24	12:30		
Ammonia-Nitrogen	202	10.0	mg/kg	200	101	80-120			
LCS Dup (B441261-BSD1)				Prepared: 10/09/24 1	0:00 Analyze	d: 10/10/24	12:40		
Ammonia-Nitrogen	213	10.0	mg/kg	200	106	80-120	5	20	
Duplicate (B441261-DUP1)		Source: 24100	11-01	Prepared: 10/09/24 1	0:00 Analyze	ed: 10/10/24	12:50		
Ammonia-Nitrogen	56.0	10.0	mg/kg	50.4			11	20	
Matrix Spike (B441261-MS1)		Source: 24100	11-01	Prepared: 10/09/24 1	0:00 Analyze	ed: 10/10/24	14:40		
Ammonia-Nitrogen	241	10.0	mg/kg	200 50.4	95	80-120			
Matrix Spike Dup (B441261-MSD1)		Source: 24100	11-01	Prepared: 10/09/24 1	0:00 Analyze	ed: 10/10/24	14:50		
Ammonia-Nitrogen	241	10.0	mg/kg	200 50.4	95	80-120	0	20	
Batch B441263 - SM2510B				Prepared: 10/07/24 0	8:45 Analyze	ed: 10/07/24	08:45		
LCS (B441263-BS1)								1	Page 12 of
		Project N	Number: [no	ne] <u>Additional Notes</u>	:10.	/01/24 11:	24	·	12 01

**General Chemistry - Quality Control** 

		Reporting		Spike	Source		%REC		RPD
		Limit	Units	Level	Result	%REC	Limits	RPD	Limit
Analyte	1610 S. Laredo Street, San	Antonio Tex	vas 78207.		(210) 229	0_0020	Fax (21	0) 229-0	0021





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope Project: City of Runge Irrigation Site Reported: 10/11/24 14:30 Received:

LCS (B441263-BS1)				Prepared:	10/07/24 08:4	45 Analyze	ed: 10/07/24	4 08:45		
Conductivity (@25C)	1030	1.00	umhos/cm	1000		103	80-120			
Duplicate (B441263-DUP1)		Source: 24100	11-08	Prepared:	10/07/24 08:4	15 Analyzo	ed: 10/10/2	4 12:18		
Conductivity (@25C)	190	1.00	umhos/cm		156			20	20	
Batch B441275 - EPA 351.3										
Blank (B441275-BLK1)				Prepared:	10/09/24 11:1	13 Analyze	ed: 10/10/24	4 12:00		
Total Kjeldahl Nitrogen	<1.00	1.00	mg/kg							
LCS (B441275-BS1)				Prepared:	10/09/24 11:	3 Analyze	ed: 10/10/2	4 12:01		
Total Kjeldahl Nitrogen	224	1.00	mg/kg	200		112	80-120			
LCS Dup (B441275-BSD1)				Prepared:	10/09/24 11:1	3 Analyzo	ed: 10/10/2	4 12:02		
Total Kjeldahl Nitrogen	224	1.00	mg/kg	200		112	80-120	0	20	
Duplicate (B441275-DUP1)		Source: 24100	11-01	Prepared:	10/09/24 11:	13 Analyzo	ed: 10/10/2	4 12:04		
Total Kjeldahl Nitrogen	1010	1.00	mg/kg		975	<del></del>		3	20	
Matrix Spike (B441275-MS1)		Source: 2410011-01		Prepared:	10/09/24 11:	13 Analyzo	ed: 10/10/2	4 12:06		
Total Kjeldahl Nitrogen	1200	1.00	mg/kg	200	975	112	80-120			
Matrix Spike Dup (B441275-MSD1)		Source: 24100	11-01	Prepared:	10/09/24 11:	13 Analyzo	ed: 10/10/2	4 12:07		
				5980000			00 120	7	19000	
Total Kjeldahl Nitrogen	1290	1.00	mg/kg	200	975	157	80-120	/	20	ı
Total Kjeldahl Nitrogen Anions by Ion Chromatograpl			mg/kg	Spike	Source		%REC		RPD	
		ontrol Reporting	mg/kg Units			157 %REC		RPD		ľ
Anions by Ion Chromatograph	ny - Quality C	ontrol Reporting		Spike	Source		%REC		RPD	
Anions by Ion Chromatograph  Analyte  Batch B441221 - EPA 300.0	ny - Quality C	ontrol Reporting		Spike Level	Source	%REC	%REC Limits	RPD	RPD	
Anions by Ion Chromatograph  Analyte  Batch B441221 - EPA 300.0  Blank (B441221-BLK1)	ny - Quality C	ontrol Reporting		Spike Level	Source Result	%REC	%REC Limits	RPD	RPD	
Anions by Ion Chromatograph  Analyte  Batch B441221 - EPA 300.0  Blank (B441221-BLK1)  Nitrite as N	ny - Quality C	Ontrol  Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD	
Anions by Ion Chromatograph	Result	Reporting Limit	Units mg/kg	Spike Level Prepared:	Source Result	%REC	%REC Limits	RPD 4 17:54	RPD	

Project Number: [none] Additional Notes:

10/01/24 11:24

1610 S. Laredo Street, San Antonio, Texas 78207-7029 (210) 229-9920 Fax (210) 229-9921 Report No. 2410011

Page 13 of 16





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope Project: City of Runge Irrigation Site Reported: 10/11/24 14:30 Received:

Anions by Ion Chromatography - Quality Control

		Reporting	Spike	Source		%REC		RPD	
		Limit	Level	Result	%REC	Limits	RPD	Limit	
Analyte	Result	Unit	S						

Batch B441221 - EPA 300.0											
LCS Dup (B441221-BSD1)			Prepared: 10/08/24 16:00 Analyzed: 10/08/24 18:30								
Nitrite as N	46.7	0.10	mg/kg	50.0	93	90-110	1	30			
Nitrate as N	48.5	0.10	mg/kg	50.0	97	90-110	0.3	30			
Duplicate (B441221-DUP1)		Source: 24101	70-01	Prepared: 10/08/24 16:00 Analyzed: 10/08/24 19:06							
Nitrite as N	<5.00	5.00	mg/kg	<5.0	0			20			
Nitrate as N	<5.00	5.00	mg/kg	<5.0	0			20			
Matrix Spike (B441221-MS1)		Source: 24101	70-01	Prepared: 10/08	8/24 16:00 Analy	zed: 10/08/2	4 19:24				
Nitrite as N	43.5	0.10	mg/kg	50.0 <0.1	0 87	80-120					
Nitrate as N	49.3	0.10	mg/kg	50.0 <0.1	0 99	80-120					
Matrix Spike Dup (B441221-MSD1)		Source: 24101	70-01	Prepared: 10/08	8/24 16:00 Analy	zed: 10/08/2	4 19:42				

mg/kg

mg/kg

Page 14 of 16

Project Number: [none] Additional Notes:

50.0

50.0

< 0.10

< 0.10

88

99

10/01/24 11:24

80-120

80-120

0.9

0.1

Report No. 2410011

20

20

#### SAMPLE QUALIFIERS

This parameter should be analyzed within 15 minutes of sample collection. Due to transportation, hold time has been exceeded.

0.10

0.10

#### **DEFINITIONS**

Nitrite as N

Nitrate as N

TNI / NELAC accredited analyte

PQL Practical Quantitation Limit MCL

Maximum Contaminant Level

mg/Kg Milligrams per Kilogram (Parts per Million) mg/L

Milligrams per Liter (Parts per Million)

PPM Parts per Million

L LCS recovery is outside QC acceptance limits, the results may have a slight bias.

43.9

49.4

M MS recovery is outside QC limits, the results may have a slight bias due to possible matrix interferences.

NR Not Recovered due to source sample concentration exceeds spiked concentration.

RMCCL Recommended Maximum Concentration of Contaminants Level Surr L

Surrogate recovery is low outside QC limits.

Surr H Surrogate recovery is high outside QC limits.

HT Sample received past holdtime

IC Improper Container for this analyte(s)

IP Improper preservation for this analyte(s) IT

Improper Temperature 1610 S. Laredo Street, San Antonio, Texas 78207-7029 (210) 229-9920 Fax (210) 229-9921





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217

Project Manager: Brian Cope

Project: City of Runge Irrigation Site

Reported: 10/11/24 14:30 Received:

Inssuficient Volume

В

Sample collected in Bulk RPD is outside QC limits.

VOA Vial contained air bubbles.

OP

ortho-Phosphate was not filtered in the field within 15minutes of collection.

CCV

Continuing Calibration Verification Standard. ICV

Initial Calibration Verification Standard.

Test Methods followed by the laboratory are referenced in the following approved methodology, unless otherwise specified.

Standard Methods for the Examination of Water and Wastewater, 23rd Edition, 2017

Methods for Chemical Analysis of Water and Wastes, EPA 600/4-79-020, Rev. March 1983

EPA SW Test Methods for the Examination of Solid Waste, SW-846, 1996

Page 15 of 16

Project Number: [none] Additional Notes:

10/01/24 11:24

Report No. 2410011

Aimee Landon For Marcela Gracia Hawk, President For

Marcela G. Hawk, President

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.





Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX, 78217 Project Manager: Brian Cope Project: City of Runge Irrigation Site **Reported:** 10/11/24 14:30 **Received:** 

Page 16 of 16

Datowlott @ AC ( NET AUTHORIZE TO ON TSDF Class 2 LI REMARKS PRESERVED PERMIT J SAME DAY WHEN POSSIBLE NVES. 9/8/7 # .O.A CUSTODY SEAL IN PLACE & INTACT :Dup: BOAY YES KNO 634399 2500 830-339-4/3/ THE TURNAROUND TIME FOR SAMPLES RECEIVED AFTER 3:00 PM SHALL BEGIN AT 8:00 AM THE FOLLOWING BUSINESS DAY /SPECIAL REQ. J Next Day INSUFFICIENT SAMPLE AMOUNT FOR (TCLP/SFIF NO. INITIAL HERE TO AUTHORIZE ANALYSIS) DATE / TIME 19/2 / 11:24 DATE / THME CHAIN-OF-CUSTODY RECORD LPST PCLS LOW LEVEL J 2 DAYS INVOICE TO: of Munge 30K X08 THRP 13 LA APPENDIX A LI Homer Runge 5035 ADDRESS D.C. Field: pH: DATE / TIME | METHOD OF SHIPMENT CANARY - CLIENT ALIN. BULK J (Initial) Post-Bag Prest-Bug Past Bug Past Bag Plest BAG Plast-Bug Plost Bag SAMPLE TEMPERATURE WITHIN COMPLIANCE (> 0.0.5 o.0.) J. YES. AND PROPER CONTAINERS. J. NO. Past Bug Post Bac 718877 SAMPLE ICED 210-828-700 COMPANY Klein + COPE Engineering Inc. 9 . 0 say DATE / TIME WHITE - LAB GUN # HRC L Other (Specify) L 15-30" 18-30 181-7 181-1 1000 T 19-0 Shc 0-6" REPORT TO COMPECTED JEMP NOLLYOLLINE 1 (194 GITY San Antonio ADDRESS 8611 BOHIS REQUESTED TURNAHOUND'TIME IN BUSINESS DAYS & SURCHARGE Scordy Clay Login Loam RECEIVED BY (PRINT NAME) RECEIVED BY (SIGNATURE) Schaffel Clay Sand Land Clay lar ATTN. Brign DATA TO TCEQ = Coy Clay 161 Pernitus Pernitus. Schaffel Schattel Pernitus 0 10-01-34 9:00 AV Area DATE / TIME DATE / TIME DISH ONOLY ZES LOST MADO 1610 S. Laredo Street, San Antonio, Texas 78207 sity of Aunge Irrigation LABORATORY, LLC Phone (210) 229-9920 Fax (210) 229-9921 Homes www.satestinglab.com Sesse Sandova FORM: COC REV 04/2022 RELINQUISHED BY (PRINT NAME) RELINQUISHED BY (SIGNATURE) PROJECT NAME/LOCATION/SITE RELINQUISHED BY (SIGNATURE 10/01/24 8:00 AM M 50:840/10/0 DIOI/24 8:10 AM IDIVIDA 8:15 AM 10/01/24 8:30 A.M 10/0/34 8:25 AM M108:38 HZ/10/01 10/01/24 8:35 AM 0/01/348:40 AM JAZ CHILDE EWIL RELINGUISHED BY ELVC -PROJECT NO. SAMPLED BY Z- En 11/0 4

#### ATTACHMENT No. 16

# ADMINISTRATIVE REPORT 1.0 SECTION 7 EFFLUENT ANALYSIS





January 23, 2025

**Brian Cope** 

Cope Engineering 8611 Bott Lane San Antonio, TX 78217

**SATL Report No.:** 

2501201

RE: Pollutant Analysis for Wastewater Treatment

**Project Number:** 

Facilities

Dear Brian Cope

SATL received 8 Sample(s) on 01/14/2025 for analyses identified on the chain of custody. The analyses were performed using methods indicated on the laboratory report. Any deviations observed at sample receiving are notated on the Sample Receipt Checklist and/or Chain of Custody documents attached as part of this analytical report.

Sincerely,

For San Antonio Testing Laboratory, Inc.

Marcela G. Hawk,

Mespank

President

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

San Antonio TX, 78217
Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received: 01/14/25 11:20

Report No. 2501201

#### SAMPLE SUMMARY

Total Samples received in this work order:

8

The following samples were requested for analysis as per the CoC. Any re-runs or re-analyses requested are identified as such.

Sample ID	<u>Laboratory ID</u>	<u>Matrix</u>	Sampling Method	Date Sampled	Date Received
001, TSS	2501201-01	Liquid	Grab	01/14/25 08:30	01/14/25 11:20
002, TDS	2501201-02	Liquid	Grab	01/14/25 08:40	01/14/25 11:20
003, Chem / Metals	2501201-03	Liquid	Grab	01/14/25 08:50	01/14/25 11:20
004, TKN Amm N T Phoph	2501201-04	Liquid	Grab	01/14/25 09:00	01/14/25 11:20
005, Ecoli	2501201-05	Liquid	Grab	01/14/25 09:15	01/14/25 11:20
0-6"	2501201-06	Solid	Grab	01/14/25 09:30	01/14/25 11:20
6"-18"	2501201-07	Solid	Grab	01/14/25 09:45	01/14/25 11:20
18"-30"	2501201-08	Solid	Grab	01/14/25 10:00	01/14/25 11:20

#### Notes

All quality control samples and checks are within acceptance limits unless otherwise indicated.

Test results pertain only to those items tested.

All samples were in good condition when received by the laboratory unless otherwise noted.





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received: 01/14/25 11:20

Report No. 2501201

Sample ID #: 001, TSS

Sampling Method: Grab

Lab Sample ID #: 2501201-01

Sample Matrix: Liquid

Date/Time Collected: 01/14/25 08:30 Prep Method

Method Analyst Notes

**General Chemistry** Total Suspended Solids *

Analyte

Units

mg/L

Result

39.0

PQL

12.5

SM2540D

B503151

Batch

01/14/25 14:30

Analyzed

SM2540D

DD





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

5.00

Reported:

01/23/25 17:19 Received:

01/14/25 11:20

Report No. 2501201

Sample ID #: 002, TDS

Sampling Method: Grab

Lab Sample ID #: 2501201-02

Sample Matrix: Liquid

Date/Time Collected: 01/14/25 08:40 Prep Method

Method Analyst Notes

**General Chemistry** Total Dissolved Solids *

Analyte

Result Units PQL

mg/L

856

SM2540C

B503203

Batch

01/14/25 17:04

Analyzed

SM2540C

DD





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received:

01/14/25 11:20

Report No. 2501201

Sample ID #: 003, Chem / Metals

Sampling Method: Grab

Lab Sample ID #: 2501201-03

Date/Time Collected: 01/14/25 08:50 Sample Matrix: Liquid

Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method	Analyst	Notes
General Chemistry									
Total Alkalinity *	283	mg/L as CaCO3	20.0	SM2320B	B503275	01/17/25 15:12	SM2320B	DD	
Conductivity (@25C) *	1550	umhos/cm	1.00	SM2510B	B504199	01/15/25 10:12	SM2510B	JA	
CBOD *	14.8	mg/L	2.00	SM5210B	B504174	01/20/25 10:18	SM5210B	JA	
Anions by Ion Chromatography									
Fluoride *	0.294	mg/L	0.020	EPA 300.0	B503274	01/15/25 14:37	EPA 300.0	JA	
Chloride *	276	mg/L	2.50	EPA 300.0	B503274	01/15/25 14:37	EPA 300.0	JA	
Nitrate as N *	0.989	mg/L	0.100	EPA 300.0	B503274	01/15/25 14:37	EPA 300.0	JA	
Sulfate *	43.4	mg/L	2.50	EPA 300.0	B503274	01/15/25 14:37	EPA 300.0	JA	
Total Metals By ICP									P1
Aluminum *	0.147	mg/L	0.050	EPA 200.7	B503226	01/23/25 13:25	EPA 200.7	SJ	
Field Parameters									
рН	7.8	s.u.							





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 

01/14/25 11:20

Report No. 2501201

Sample ID #: 004, TKN Amm N T Phoph

Sampling Method: Grab

Lab Sample ID #: 2501201-04

Sample Matrix: Liquid Date/Time Collected: 01/14/25 09:00

Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method A	nalyst Notes
General Chemistry								
Ammonia-Nitrogen *	3.36	mg/L	1.00	SM4500NH3B	B504213	01/23/25 13:36	SM4500NH3C	DD
Total Kjeldahl Nitrogen *	4.48	mg/L	1.00	EPA 351.3	B504212	01/23/25 16:08	EPA 351.3	DD
Total Phosphorous *	1.58	mg/L	0.05	EPA 365.3	B504210	01/22/25 15:10	EPA 365.3	JA





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received:

01/14/25 11:20

Report No. 2501201

Sample ID #: 005, Ecoli

Sampling Method: Grab

Lab Sample ID #: 2501201-05

Sample Matrix: Liquid

Analyte

E. Coli *

Result

**PQL** 

Units

Date/Time Collected: 01/14/25 09:15 Prep Method

Batch

Analyzed

Method Analyst Notes

Microbiological Parameters

MPN/100 mL 770

1.00

Start 01/14/25 12:39/End 01/15/25 13:36

Colilert-QTray

DD



14.1

#### LABORATORY REPORT



Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received:

01/14/25 11:20

Report No. 2501201

Sample ID #: 0-6"

Sulfur, Available

Sampling Method: Grab

Mehlich-III

B503229

01/17/25 12:27

M-III/6010

SJ

Lab Sample ID #: 2501201-06

Sample Matrix: Solid				Date/Time Collected: 01	/14/25 09:	30			
Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method	Analyst	Notes
General Chemistry									
% Solids	79.5	% by Wt.	0.100	% Calc	B503204	01/16/25 08:27	ASTM D2216	TW	
Conductivity (@25C)	2230	umhos/cm	1.00	USDA60	B504232	01/23/25 11:34	USDAHB60	JA	
Ammonia-Nitrogen *	<10.0	mg/kg	10.0	SM4500NH3B	B504243	01/23/25 16:03	SM4500NH3C	DD DD	
Total Kjeldahl Nitrogen	314	mg/kg	1.00	EPA 351.3	B504233	01/23/25 13:04	EPA 351.3	DD	
Total Nitrogen	396	mg/kg dry	1.40	[CALC]	[CALC]	01/23/25 13:04	CALC	DD	
SoilpH measured in H20@°Cbelow	7.93	pH Units	0.10	EPA 9045D	B504230	01/23/25 11:34	EPA 9045D	JA	Н
pH measured @Temperature >>	20	°C	0.10	EPA 9045D	B504230	01/23/25 11:34	EPA 170.1	JA	H
Anions by Ion Chromatography									
Nitrite as N *	0.44	mg/kg	0.20	EPA 300.0	B504192	01/21/25 14:39	EPA 300.0	JA	
Nitrate as N *	1.05	mg/kg	0.20	EPA 300.0	B504192	01/21/25 14:39	EPA 300.0	JA	
Available Metals by Mehlich III Ext	raction								
Calcium *	2950	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Calcium, Available	2950	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Magnesium *	144	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Magnesium, Available	144	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Phosphorus, Available	<10.0	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Potassium, Available	90.7	mg/kg dry	50.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Sodium *	934	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Sodium, Available *	934	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	
Sulfur	14.1	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:27	M-III/6010	SJ	

10.0

mg/kg dry





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 

01/14/25 11:20

Report No. 2501201

Sample ID #: 6''-18''

Sampling Method: Grab

Lab Sample ID #: 2501201-07

Sample Matrix: Solid Date/Time Collected: 01/14/25 09:45

Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method A	nalyst	Notes
General Chemistry									
% Solids	80.5	% by Wt.	0.100	% Calc	B503204	01/16/25 08:27	ASTM D2216	TW	
Conductivity (@25C)	1450	umhos/cm	1.00	USDA60	B504232	01/23/25 11:36	USDAHB60	JA	
Ammonia-Nitrogen *	22.4	mg/kg	10.0	SM4500NH3B	B504243	01/23/25 16:06	SM4500NH3C	DD	
Total Kjeldahl Nitrogen	521	mg/kg	1.00	EPA 351.3	B504233	01/23/25 13:06	EPA 351.3	DD	
Total Nitrogen	649	mg/kg dry	1.40	[CALC]	[CALC]	01/23/25 13:06	CALC	DD	
SoilpH measured in H20@°Cbelow	8.11	pH Units	0.10	EPA 9045D	B504230	01/23/25 11:35	EPA 9045D	JA	Н
pH measured @Temperature >>	20	°C	0.10	EPA 9045D	B504230	01/23/25 11:35	EPA 170.1	JA	Н
Anions by Ion Chromatography									
Nitrite as N *	0.82	mg/kg	0.20	EPA 300.0	B504192	01/21/25 14:56	EPA 300.0	JA	
Nitrate as N *	0.57	mg/kg	0.20	EPA 300.0	B504192	01/21/25 14:56	EPA 300.0	JA	
Available Metals by Mehlich III Ex	traction								
Calcium *	3950	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Calcium, Available	3950	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Magnesium *	217	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Magnesium, Available	217	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Phosphorus, Available	<10.0	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Potassium, Available	104	mg/kg dry	50.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Sodium *	1060	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Sodium, Available *	1060	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Sulfur	12.5	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	
Sulfur, Available	12.5	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:33	M-III/6010	SJ	





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 

01/14/25 11:20

Report No. 2501201

Sample ID #: 18"-30" Sampling N

Sampling Method: Grab

Lab Sample ID #: 2501201-08

Sample Matrix: Solid	Date/Time Collected: 01/14/25 10:00

Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method A	Analyst	Notes
General Chemistry									
% Solids	83.5	% by Wt.	0.100	% Calc	B503204	01/16/25 08:27	ASTM D2216	TW	
Conductivity (@25C)	1210	umhos/cm	1.00	USDA60	B504232	01/23/25 11:38	USDAHB60	JA	
Ammonia-Nitrogen *	16.8	mg/kg	10.0	SM4500NH3B	B504243	01/23/25 16:07	SM4500NH3C	DD	
Total Kjeldahl Nitrogen	448	mg/kg	1.00	EPA 351.3	B504233	01/23/25 13:07	EPA 351.3	DD	
Total Nitrogen	540	mg/kg dry	1.40	[CALC]	[CALC]	01/23/25 13:07	CALC	DD	
SoilpH measured in H20@°Cbelow	8.43	pH Units	0.10	EPA 9045D	B504230	01/23/25 11:38	EPA 9045D	JA	Н
pH measured @Temperature >>	20	°C	0.10	EPA 9045D	B504230	01/23/25 11:38	EPA 170.1	JA	Н
Anions by Ion Chromatography									
Nitrite as N *	1.54	mg/kg	0.20	EPA 300.0	B504192	01/21/25 15:14	EPA 300.0	JA	
Nitrate as N *	1.21	mg/kg	0.20	EPA 300.0	B504192	01/21/25 15:14	EPA 300.0	JA	
Available Metals by Mehlich III Ex	ktraction								
Calcium *	829	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Calcium, Available	829	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Magnesium *	129	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Magnesium, Available	129	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Phosphorus, Available	<10.0	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Potassium, Available	<50.0	mg/kg dry	50.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Sodium *	795	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Sodium, Available *	795	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Sulfur	15.0	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	
Sulfur, Available	15.0	mg/kg dry	10.0	Mehlich-III	B503229	01/17/25 12:38	M-III/6010	SJ	





Cope Engineering 8611 Bott Lane San Antonio TX, 78217 Additional Notes: Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported: 01/23/25 17:19 Received: 01/14/25 11:20

Report No. 2501201

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	
	Kesuit	Limit	Ollits	Level	Result	70REC	Limits	Krb	Lillit	
Batch B503151 - SM2540D										
Blank (B503151-BLK1)				Prepared: 0	1/13/25 10:	45 Analyz	ed: 01/13/2	5 12:50		
Total Suspended Solids	<2.50	2.50	mg/L							
LCS (B503151-BS1)				Prepared: 0	1/13/25 10:	45 Analyz	ed: 01/13/2	5 12:51		
Total Suspended Solids	86.0	25.0	mg/L	100		86	80-120			
LCS Dup (B503151-BSD1)				Prepared: 0	1/13/25 10:	45 Analyz	ed: 01/13/2	5 12:52		
Total Suspended Solids	92.0	25.0	mg/L	100		92	80-120	7	20	
Ouplicate (B503151-DUP1)		Source: 2501	146-02	Prepared: 0	1/13/25 10:	45 Analyz	ed: 01/13/2	5 12:55		
Total Suspended Solids	160	16.7	mg/L		166			4	20	
Batch B503203 - SM2540C			A-CONTRACTOR OF THE CONTRACTOR							
Blank (B503203-BLK1)				Prepared: 0	)1/13/25 11:	00 Analyz	ed: 01/14/2	5 14:00		
Total Dissolved Solids	<2.50	2.50	mg/L							
LCS (B503203-BS1)				Prepared: 0	1/13/25 11:	00 Analyz	ed: 01/14/2	5 14:01		
Total Dissolved Solids	99.0	2.50	mg/L	100		99	80-120			
LCS Dup (B503203-BSD1)				Prepared: 0	1/13/25 11:	00 Analyz	ed: 01/14/2	5 14:02		
Total Dissolved Solids	111	2.50	mg/L	100		111	80-120	11	20	
Duplicate (B503203-DUP1)		Source: 2501	193-01	Prepared: 0	1/14/25 10:	00 Analyz	ed: 01/14/2	5 17:05		
Total Dissolved Solids	942	2.50	mg/L		884			6	20	
Batch B503275 - SM2320B										
Blank (B503275-BLK1)				Prepared: 0	1/17/25 12:	20 Analyz	ed: 01/17/2	5 12:27		
Total Alkalinity	<20.0	20.0	mg/L as CaCO3							
LCS (B503275-BS1)				Prepared: 0	1/17/25 12:	30 Analyz	ed: 01/17/2	5 13:10		
Total Alkalinity	108	20.0	mg/L as CaCO3	100		108	80-120			
CS Dup (B503275-BSD1)				Prepared: 0	1/17/25 12:	30 Analyz	ed: 01/17/2	5 13:12	a'i	
Total Alkalinity	104	20.0	mg/L as CaCO3	100		104	80-120	4	20	
Ouplicate (B503275-DUP1)		Source: 2501	201-03	Prepared: 0	1/17/25 12:	30 Analyz	ed: 01/17/2	5 15:14		
Total Alkalinity	260	20.0	mg/L as CaCO3	1	283			8	20	
Batch B504174 - SM5210B										





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 01/14/25 11:20

Report No. 2501201

	D. L	Reporting	***	Spike	Source	a/DEC	%REC	DDD	RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	
Batch B504174 - SM5210B										
Blank (B504174-BLK1)				Prepared: (	01/15/25 09:	30 Analyz	zed: 01/20/2	5 10:00		
CBOD	<2.00	2.00	mg/L							
LCS (B504174-BS1)				Prepared: (	01/15/25 09:	30 Analyz	zed: 01/20/2	5 10:10		
CBOD	195	2.00	mg/L	200		98	80-120			
LCS (B504174-BS2)			a titlete	Prepared: (	01/15/25 09:	30 Analyz	zed: 01/20/2	5 10:12		
CBOD	188	2.00	mg/L	200		94	80-120			
LCS (B504174-BS3)				Prepared: (	01/15/25 09:	:30 Analyz	zed: 01/20/2	5 10:14		
CBOD	198	2.00	mg/L	200		99	80-120			
Duplicate (B504174-DUP1)		Source: 25012	01-03	Prepared: (	01/15/25 09:	30 Analyz	zed: 01/20/2	5 10:16		
CBOD	12.1	2.00	mg/L		14.8			20	20	
Batch B504199 - SM2510B			Milaka mili marana in makan							
LCS (B504199-BS1)				Prepared: (	01/15/25 10:	:00 Analyz	zed: 01/15/2	5 10:00		
Conductivity (@25C)	1030	1.00	umhos/cm	1000		103	80-120			
Duplicate (B504199-DUP1)		Source: 25012	01-03	Prepared: (	01/15/25 10	:00 Analyz	zed: 01/15/2	5 10:14		
Conductivity (@25C)	1540	1.00	umhos/cm		1550			0.8	20	
Batch B504210 - EPA 365.3										
Blank (B504210-BLK1)				Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	5 15:00		
Total Phosphorous	< 0.05	0.05	mg/L							
LCS (B504210-BS1)				Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	5 15:00		
Total Phosphorous	0.478	0.05	mg/L	0.500		96	80-120			
LCS Dup (B504210-BSD1)				Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	25 15:00		
Total Phosphorous	0.476	0.05	mg/L	0.500		95	80-120	0.4	20	
Duplicate (B504210-DUP1)		Source: 25012	01-04	Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	25 15:20		
Total Phosphorous	1.54	0.05	mg/L		1.58			3	20	
Matrix Spike (B504210-MS1)		Source: 25012	01-04	Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	5 15:20		
Total Phosphorous	1.20	0.05	mg/L	0.500	1.58	NR	80-120			M
Matrix Spike Dup (B504210-MSD1)		Source: 25012	01-04	Prepared: (	01/22/25 12	:00 Analyz	zed: 01/22/2	5 15:20		





Cope Engineering 8611 Bott Lane San Antonio TX, 78217 Additional Notes: Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported: 01/23/25 17:19 Received: 01/14/25 11:20

Report No. 2501201

						-				
Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	
Batch B504210 - EPA 365.3										
Matrix Spike Dup (B504210-MSD1)		Source: 250120	01-04	Prepared:	01/22/25 12:0	00 Analyz	zed: 01/22/2	5 15:20		
Total Phosphorous	1.21	0.05	mg/L	0.500	1.58	NR	80-120	1	20	M
Batch B504212 - EPA 351.3										
Blank (B504212-BLK1)				Prepared:	01/22/25 08:3	0 Analy:	zed: 01/22/2	5 15:00		
Total Kjeldahl Nitrogen	<1.00	1.00	mg/L							
LCS (B504212-BS1)				Prepared:	01/22/25 08:3	0 Analy	zed: 01/22/2	5 15:02		
Total Kjeldahl Nitrogen	19.1	1.00	mg/L	20.0		95	80-120			
LCS Dup (B504212-BSD1)				Prepared:	01/22/25 08:3	0 Analy	zed: 01/22/2	5 15:04		
Total Kjeldahl Nitrogen	21.9	1.00	mg/L	20.0		109	80-120	14	20	
Duplicate (B504212-DUP1)		Source: 250114	46-02	Prepared:	01/22/25 08:3	0 Analy	zed: 01/22/2	5 15:07		
Total Kjeldahl Nitrogen	9.53	1.00	mg/L		9.53			0	20	
Matrix Spike (B504212-MS1)		Source: 250114	46-02	Prepared:	01/22/25 08:3	0 Analy	zed: 01/22/2	5 15:10		
Total Kjeldahl Nitrogen	35.3	1.00	mg/L	20.0	9.53	129	80-120			М
Batch B504213 - SM4500NH3B										
Blank (B504213-BLK1)				Prepared:	01/22/25 08:3	30 Analy:	zed: 01/22/2	5 16:30		
Ammonia-Nitrogen	<1.00	1.00	mg/L							
LCS (B504213-BS1)				Prepared:	01/22/25 08:3	30 Analy	zed: 01/22/2	5 16:32		
Ammonia-Nitrogen	20.7	1.00	mg/L	20.0		104	80-120			
LCS Dup (B504213-BSD1)				Prepared:	01/22/25 08:3	30 Analy:	zed: 01/22/2	5 16:34		
Ammonia-Nitrogen	20.7	1.00	mg/L	20.0		104	80-120	0	20	
Duplicate (B504213-DUP1)		Source: 250114	44-01	Prepared:	01/22/25 08:3	30 Analy:	zed: 01/22/2	5 16:36		
Ammonia-Nitrogen	<1.00	1.00	mg/L		<1.00				20	
Matrix Spike (B504213-MS1)		Source: 250114	44-01	Prepared:	01/22/25 08:3	30 Analy	zed: 01/22/2	5 16:40		
Ammonia-Nitrogen	20.2	1.00	mg/L	20.0	<1.00	101	80-120			
Batch B504230 - EPA 9045D										
LCS (B504230-BS1)				Prepared:	01/23/25 10:0	00 Analy:	zed: 01/23/2	5 10:00		
SoilpH measured in H20@°Cbelow	7.01	0.10	pH Units	7.00		100	97.5-102.5			
2011pt. Invitation in F120th Covidw	7.01	0.10	PITOMIS	7.00		100	7.5 102.5			





Cope Engineering 8611 Bott Lane San Antonio TX, 78217 Additional Notes: Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported: 01/23/25 17:19 Received: 01/14/25 11:20

Report No. 2501201

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC	RPD	RPD Limit	
	resure	Billit	Omts	Dever	resur	/MCDC	Ziiiiko	10.0		
Batch B504230 - EPA 9045D							1 04/00/0		w	
LCS (B504230-BS1)				Prepared:	01/23/25 10:	:00 Analyz		5 10:00		
pH measured @Temperature >>	17.4	0.10	°C				0-200			
Duplicate (B504230-DUP1)		Source: 25012	01-08	Prepared:	01/23/25 10:	:00 Analyz	ed: 01/23/2	5 12:00		
SoilpH measured in H20@°Cbelow	8.31	0.10	pH Units		8.43			1	20	Н
pH measured @Temperature >>	20.1	0.10	°C		20.1			0	30	Н
Batch B504232 - USDA60										
LCS (B504232-BS1)				Prepared:	01/23/25 10:	:00 Analyz	zed: 01/23/2	5 10:00		
Conductivity (@25C)	1040	1.00	umhos/cm	1000		104	80-120			
Duplicate (B504232-DUP1)		Source: 25012	01-08	Prepared:	01/23/25 10:	:00 Analyz	zed: 01/23/2	5 11:40		
Conductivity (@25C)	1140	1.00	umhos/cm		1210			6	20	
Batch B504233 - EPA 351.3							161			
Blank (B504233-BLK1)				Prepared:	01/22/25 08	:30 Analyz	zed: 01/23/2	5 13:00		
Total Kjeldahl Nitrogen	<1.00	1.00	mg/kg							
LCS (B504233-BS1)				Prepared:	01/22/25 08	:30 Analyz	zed: 01/23/2	5 13:01		
Total Kjeldahl Nitrogen	196	1.00	mg/kg	200		98	80-120			
LCS Dup (B504233-BSD1)				Prepared:	01/22/25 08	:30 Analyz	zed: 01/23/2	5 13:02		
Total Kjeldahl Nitrogen	219	1.00	mg/kg	200		109	80-120	11	20	
Duplicate (B504233-DUP1)		Source: 25012	01-06	Prepared:	01/22/25 08	:30 Analyz	zed: 01/23/2	25 13:03		
Total Kjeldahl Nitrogen	336	1.00	mg/kg		314			7	20	
Matrix Spike (B504233-MS1)		Source: 25012	01-06	Prepared:	01/22/25 08	:30 Analy	zed: 01/23/2	25 13:05		
Total Kjeldahl Nitrogen	560	1.00	mg/kg	200	314	123	80-120			M
Batch B504243 - SM4500NH3B										
Blank (B504243-BLK1)				Prepared:	01/22/25 08	:30 Analy	zed: 01/23/2	25 16:00		
Ammonia-Nitrogen	<10.0	10.0	mg/kg							
LCS (B504243-BS1)				Prepared:	01/22/25 08	:30 Analy:	zed: 01/23/2	25 16:01		
Ammonia-Nitrogen	196	10.0	mg/kg	200		98	80-120			
LCS Dup (B504243-BSD1)				Prepared:	01/22/25 08	:30 Analy	zed: 01/23/2	25 16:02		





Cope Engineering 8611 Bott Lane San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 

01/14/25 11:20

Report No. 2501201

#### General Chemistry - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	
Batch B504243 - SM4500NH3B		***************************************								
LCS Dup (B504243-BSD1)				Prepared: 0	01/22/25 08	:30 Analyz	zed: 01/23/2	5 16:02		
Ammonia-Nitrogen	202	10.0	mg/kg	200		101	80-120	3	20	
Duplicate (B504243-DUP1)		Source: 250120	1-06	Prepared: 0	01/22/25 08	:30 Analyz	zed: 01/23/2	5 16:04		
Ammonia-Nitrogen	11.2	10.0	mg/kg		5.60			67	20	S
Matrix Spike (B504243-MS1)		Source: 250120	1-06	Prepared: 0	01/22/25 08	:30 Analyz	zed: 01/23/2	5 16:05		
Ammonia-Nitrogen	224	10.0	mg/kg	200	5.60	109	80-120			

#### Anions by Ion Chromatography - Quality Control

Amons by 10th Chromatograp	, ,								
Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit
Batch B503274 - EPA 300.0									
Blank (B503274-BLK1)				Prepared: (	01/14/25 16	:00 Analyz	ed: 01/14/2:	5 17:33	
Fluoride	< 0.020	0.020	mg/L						
Chloride	< 0.100	0.100	mg/L						
Nitrate as N	< 0.100	0.100	mg/L						
Sulfate	< 0.10	0.10	mg/L						
LCS (B503274-BS1)				Prepared: (	01/14/25 16	:00 Analyz	ed: 01/14/2:	5 17:51	
Fluoride	1.01	0.020	mg/L	1.00		101	90-110		
Chloride	4.83	0.100	mg/L	5.00		97	90-110		
Nitrate as N	5.09	0.100	mg/L	5.00		102	90-110		
Sulfate	4.93	0.10	mg/L	5.00		99	90-110		
LCS Dup (B503274-BSD1)				Prepared: (	01/14/25 16	:00 Analyz	ed: 01/14/2:	5 18:09	
Fluoride	1.01	0.020	mg/L	1.00		101	90-110	0.02	20
Chloride	4.85	0.100	mg/L	5.00		97	90-110	0.3	20
Nitrate as N	5.11	0.100	mg/L	5.00		102	90-110	0.3	20
Sulfate	4.94	0.10	mg/L	5.00		99	90-110	0.3	20
Duplicate (B503274-DUP1)		Source: 250120	1-03	Prepared: (	01/14/25 16	:00 Analyz	ed: 01/15/2:	5 14:55	
Fluoride	0.281	0.020	mg/L		0.294			4	20
Chloride	278	2.50	mg/L		276			0.6	20
Nitrate as N	0.968	0.100	mg/L		0.989			2	20





Cope Engineering 8611 Bott Lane San Antonio TX, 78217 Additional Notes: Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported: 01/23/25 17:19 Received: 01/14/25 11:20

Report No. 2501201

#### Anions by Ion Chromatography - Quality Control

Analyta	Result	Reporting Limit	Units	Spike Level	Source	%REC	%REC	RPD	RPD Limit	
Analyte	Resuit	Limit	Units	Level	Result	70KEU	Limits	KrD	Limit	
Batch B503274 - EPA 300.0										
Duplicate (B503274-DUP1)		Source: 250120	1-03	Prepared:	01/14/25 16:	:00 Analyz	zed: 01/15/2	5 14:55		
Sulfate	43.8	2.50	mg/L		43.4			0.9	20	
Matrix Spike (B503274-MS1)		Source: 250120	1-03	Prepared:	01/14/25 16	:00 Analyz	zed: 01/15/2	5 15:13		
Fluoride	1.25	0.020	mg/L	1.00	0.294	95	80-120			
Chloride	192	0.100	mg/L	5.00	276	NR	80-120			M
Nitrate as N	6.11	0.100	mg/L	5.00	0.989	102	80-120			
Sulfate	56.4	0.10	mg/L	5.00	43.4	261	80-120			M
Matrix Spike Dup (B503274-MSD1)		Source: 250120	1-03	Prepared:	01/14/25 16	:00 Analyz	zed: 01/15/2	5 15:31		
Fluoride	1.25	0.020	mg/L	1.00	0.294	96	80-120	0.4	20	
Chloride	192	0.100	mg/L	5.00	276	NR	80-120	0.1	20	M
Nitrate as N	6.11	0.100	mg/L	5.00	0.989	102	80-120	0.04	20	
Sulfate	56.4	0.10	mg/L	5.00	43.4	260	80-120	0.1	20	M
Batch B504192 - EPA 300.0										
Blank (B504192-BLK1)				Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	5 16:43		
Nitrite as N	< 0.10	0.10	mg/kg							
Nitrate as N	< 0.10	0.10	mg/kg							
LCS (B504192-BS1)				Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	5 17:01		
Nitrite as N	45.4	0.10	mg/kg	50.0		91	90-110			
Nitrate as N	50.3	0.10	mg/kg	50.0		101	90-110			
LCS Dup (B504192-BSD1)				Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	5 17:19		
Nitrite as N	45.6	0.10	mg/kg	50.0		91	90-110	0.4	30	
Nitrate as N	48.8	0.10	mg/kg	50.0		98	90-110	3	30	
Duplicate (B504192-DUP1)		Source: 250128	31-01	Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	25 20:35		
Nitrite as N	<2.50	2.50	mg/kg		<2.50				20	
Nitrate as N	6.48	2.50	mg/kg		5.80			11	20	
Matrix Spike (B504192-MS1)		Source: 250128	31-01	Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	25 21:47		
Nitrite as N	41.7	0.10	mg/kg	50.0	< 0.10	83	80-120			
Nitrate as N	53.9	0.10	mg/kg	50.0	5.80	96	80-120			
Matrix Spike Dup (B504192-MSD1)	31-01	Prepared:	01/20/25 16	:00 Analyz	zed: 01/20/2	25 22:05				
Nitrite as N	41.7	0.10	mg/kg	50.0	<0.10	83	80-120	0.01	20	
Nitrate as N	53.8	0.10	mg/kg	50.0	5.80	96	80-120	0.1	20	

1610 S. Laredo Street, San Antonio, Texas 78207-7029

(210) 229-9920

Fax (210) 229-9921

www.satestinglab.com





Cope Engineering 8611 Bott Lane San Antonio TX, 78217 Additional Notes: Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

**Reported:** 01/23/25 17:19 **Received:** 

01/14/25 11:20

Report No. 2501201

#### **Total Metals By ICP - Quality Control**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	
Batch B503226 - EPA 200.7		to the second								
Blank (B503226-BLK1)				Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/17/2	5 11:37		
Aluminum	< 0.050	0.050	mg/L							
LCS (B503226-BS1)				Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/17/2	5 11:48		
Aluminum	1.93	0.050	mg/L	2.00		97	85-115			
LCS Dup (B503226-BSD1)				Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/17/2	5 11:54		
Aluminum	1.91	0.050	mg/L	2.00		96	85-115	1	20	
Duplicate (B503226-DUP1)		Source: 2501201	1-03	Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/23/2	5 13:31		
Aluminum	0.153	0.050	mg/L		0.147			4	20	
Matrix Spike (B503226-MS1)		Source: 2501201	1-03	Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/23/2	5 13:37		
Aluminum	2.44	0.050	mg/L	2.00	0.147	115	75-125			
Matrix Spike Dup (B503226-MSD1)		Source: 2501201	1-03	Prepared: 0	01/16/25 08:	55 Analyz	ed: 01/23/2	5 13:43		
Aluminum	2.51	0.050	mg/L	2.00	0.147	118	75-125	3	20	





Cope Engineering 8611 Bott Lane

San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received:

01/14/25 11:20

Report No. 2501201

#### SAMPLE QUALIFIERS

P1 Sample was received at a pH of greater 2.0.

H This parameter should be analyzed within 15 minutes of sample collection. Due to transportation, hold time has been exceeded.

#### DEFINITIONS

AB

* TNI / NELAC accredited analyte

PQL Practical Quantitation Limit

MCL Maximum Contaminant Level

mg/Kg Milligrams per Kilogram (Parts per Million) mg/L Milligrams per Liter (Parts per Million)

PPM Parts per Million

L LCS recovery is outside QC acceptance limits, the results may have a slight bias.

M MS recovery is outside QC limits, the results may have a slight bias due to possible matrix interferences.

NR Not Recovered due to source sample concentration exceeds spiked concentration.

RMCCL Recommended Maximum Concentration of Contaminants Level

Surr L Surrogate recovery is low outside QC limits.
Surr H Surrogate recovery is high outside QC limits.

HT Sample received past holdtime
IC Improper Container for this analyte(s)
IP Improper preservation for this analyte(s)

IT Improper Temperature

V Inssuficient Volume

B Sample collected in Bulk

S RPD is outside QC limits.

OP ortho-Phosphate was not filtered in the field within 15minutes of collection.

CCV Continuing Calibration Verification Standard.
ICV Initial Calibration Verification Standard.

VOA Vial contained air bubbles.

Test Methods followed by the laboratory are referenced in the following approved methodology, unless otherwise specified.

Standard Methods for the Examination of Water and Wastewater, 23rd Edition, 2017

Methods for Chemical Analysis of Water and Wastes, EPA 600/4-79-020, Rev. March 1983

EPA SW Test Methods for the Examination of Solid Waste, SW-846, 1996





Cope Engineering 8611 Bott Lane

San Antonio TX, 78217

Additional Notes:

Project Manager: Brian Cope

Project: Pollutant Analysis for Wastewater Treatment

Project Number: Facilities

Reported:

01/23/25 17:19

Received:

01/14/25 11:20

Report No. 2501201

Aimee Landon For Marissa Esquivel, Lab Manager For

Marcela G. Hawk, President

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.

JAN PAG/72025 9 **AUTHORIZE TO** 200 REMARKS TSDF Class 2 U PERMIT U かって PRESERVED WITH REPORT NUMBER D YES ☐ SAME DAY WHEN POSSIBLE : Dup: CUSTODY SEAL IN PLACE & INTACT 1 P.O. # REQUESTED U YES PST 198119 SPECIAL REQ. INSUFFICIENT SAMPLE AMOUNT FOR (TCLP/SPLP/OTHER): IF NO, INITIAL HERE TO AUTHORIZE ANALYSIS D Next Day ICIL "C; LCS/D; ANALYSIS CHAIN-OF-CUSTODY RECORD KUNGE PHONE # THE TURNAROUND TIME FOR SAMPLES RECEIVED AFTER 3:00 PM SHALL BEGIN AT 8:00 AM THE FOLLOWING BUSINESS DAY LPST PCLS LOW LEVEL 206 U 2 DAYS INVOICE TO: 3 .Temp: DATE TIME RELINDUSHED BY (SIGNIFFEE)

DATE TIME RELINDUSHED BY PHINT NAMES

DATE TIME RELINDUSHED BY PHINT NAMES かった S S S Lot J 3 DAYS Field: pH: 7.9 ATTN: Homer 1.4 TRRP 13 CAPPENDIX A D Rungo 5035 ☐ 4 Days CANARY - CLIENT COMPANY ADDRESS BULK (Initial) 9 Q CITY Besh 8287878 1 344 GUN # SAMPLE ICED 210-838 7007 78217 OKES S O 5 Days DATE / TIME SAMPLE TEMPERATURE WITHIN COMPLIANCE (> 0°C ≤ 6°C)
PROPER CONTAINERS
OBSERVED TEMP (**) 235844 OF WHITE - LAB 7-10 Days REG RRC L Other (Specify) L 705 - Car REPORT TO: COMPANY COPE FAG, APECING сонявстер(теме. IDENTIFICATION REQUESTED TURNAROUND TIME IN BUSINESS DAYS & SURCHARGE Both NAME) CITY Saw Antonio RECEIVED BY (PRINT NAME) RECEIVED BY (SIGNATURE) RECEIVED BY (SIGNATOR Brian 1198 DATA TO TCEQ L 18"-30" 6-18" 50 ADDRESS 750 TKD 10-0 E S 10:10-AMDATE/TIME 10:10-14-30-55 DATE / TIME Facilites SAN ANTONIO TESTING 002408-F= 0440 004= 1610 S. Laredo Street, San Antonio, Texas 78207 Phone (210) 229-9920 Fax (210) 229-9921 Foli 0-cp-r-c-z>pap 0-cp-r-c-z>pap 0-cp-r-c-z>pap 0-cp-ram LABORATORY, LLC PROJECT NAME LOCATION SITE

POLIU FAINT HOLALYSIS Wustewater Treatment PROJECT NO. S MFESHON SON EMNQUISHED BY (PRINT NAME) FORM: COC REV 04/2022 ELINQUISHED BY (PRINT NAME) www.satestinglab.com JISHED BY (SIGNATURE 9:28 13:01 14/25 8:30 AM M125 8:50 PM 14/35 9:00 AM 14/25 8:40 MM かんからっていた 205 July 135 09 15 かっち COLLECTED TIME 76/11/25 DATE SAMPLED BY SATIL 1000 500 500 780 NAZGIM Page 20 of 23 tre

Table 1.0(2) - Pollutant Analysis for Wastewater Treatment Facilities

	Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
1	CBOD ₅ , mg/l					
V	Total Suspended Solids, mg/l					
V	Ammonia Nitrogen, mg/l					
V	Nitrate Nitrogen, mg/l					
V	Total Kjeldahl Nitrogen, mg/l					
V	Sulfate, mg/l					
1	Chloride, mg/l					
V	Total Phosphorus, mg/l					
V	pH, standard units 👫 🍾	ce in fiel	Ď ·			
	Dissolved Oxygen*, mg/l					
1	Chlorine Residual, mg/l 🏓 Ţ	LEC IN FIR	D ·			
V	<i>E.coli</i> (CFU/100ml) freshwater .					
	Entercocci (CFU/100ml) saltwater					
1	Total Dissolved Solids, mg/l					
1	Electrical Conductivity, µmohs/cm, †					
	Oil & Grease, mg/l					
	Alkalinty (CaCO ₃ )*, mg/l					

^{*}TPDES permits only †TLAP permits only

#### Table 1.0(3) - Pollutant Analysis for Water Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Total Suspended Solids, mg/l					
Total Dissolved Solids, mg/l					
pH, standard units					
Fluoride, mg/l					
Aluminum, mg/l					
Alkalinity (CaCO ₃ ), mg/l					

# Section 8. Facility Operator (Instructions Page 50)

Facility Operator Name: Click to enter text.

Facility Operator's License Classification and Level: Click to enter text.

Facility Operator's License Number: Click to enter text.





Cert. No. T104704360-13-9

Klein & Cope Engineering 8611 Botts Lane, Ste. 101 San Antonio TX. 78217

Project: City of Runge Irrigation Area

Project Number: [none]

Project Manager: Nadia Sanchez

Reported:

04/17/15 17:45 Received:

04/02/15 17:14

Report No. 1504058

Sample ID #: Schattel Clay 0-6"

Date/Time Collected: 04/02/15 14:05

Lab Sample ID #: 1504058-01

Sample Matrix: Solid		Date/Time Collected: 04/02/15 14:05							
Analyte	Result	Units	PQL	Prep Method	Batch	Analyzed	Method	Analyst	Notes
General Chemistry							4.01	NE:	
% Solids	86 4	% by Weight	1 00	% Solids	B516055	04/14/15 13:19	% ('alc	XE	
Ammonia	<100	mg/kg	100		B515145	04/10/15 17:12	4500NH3CB	SS	
Nitrite as N *	<1.00	mg/kg	1.00	EPA 300 0	B515110	04/09/15 14:33	EPA 300 0	SS	
Nitrate as N *	9.78	mg/kg	1.00	EPA 300 0	B515110	04/09/15 14:33	EPA 300 0	SS	
	730	umhos/cm	1.00		B516037	04/13/15 16:40	SM2510B	Л.	
Specific conductance	9.02	pH Units	1.00		B514173	04/03/15 15:00	9045(*	SS	11
pH *	22	°C	1.0		B514173	04/03/15 15:00	I-PA 170 I	SS	11
pH measured 'a: Temperature >>	11.2	mg/kg	1.00		B515133	04/08/15 16:35	351.3	SS	
Fotal Kjeldahl Nitrogen Fotal Nitrogen	21.0	mg/kg	3.00	[CALC]	[CALC]	04/09/15 14:33	T-Nitrogen	SS	
Available Metals by Mehlich III	Extraction								
Sodium, Available *	172000	mg/kg dry	2500	3050B	B516063	04/15/15 12:34	M-III:6010	xe	
Potassium, Available	618	mg/kg dry	200	30.50B	B516063	04/14/15 16:02	M-III/6010	xe	
	83.7	mg/kg dry	20.0	3050B	B516063	04/14/15 16:02	M-III/6010	xc	
Sulfur	<20.0	mg/kg dry	20 0	3050B	B516063	04/14/15 16:02	VI-111/0010	xe	
Magnesium, Available	1190	mg/kg dry	500	3050B	B516063	04/14/15 16:02	M-111:0010	xe	
Calcium, Available Phosphorus, Available	341	mg/kg dry	20.0	3050B	B516063	04/14/15 16:02	M-III/6010	xe	



# Sample Receipt Checklist

Client: Cope Engineering	Project Manager: Marissa Esquivel
Project: Pollutant Analysis for Wastewater Treatment	Project Number: Facilites
Report To:	
Brian Cope	SATL Report Number: 2501201
Work Order Due by: 01/23/25 17:00 (7 day TAT)	
Received By: Aimee Landon	Date Received: 01/14/25 11:20
Logged In By: Aimee Landon	Date Logged In: 01/14/25 12:17
Sample(s) Received on ICE/evidence of Ice (cooler with me	elted ice,etc):
Sample temperature at receipt *:	1.1°C
Custody Seals Present:	No
All containers intact:	Yes
Sample labels/COC agree:	Yes
Samples Received within Holding time :	Yes
Samples appropriately preserved **:	Yes
Containers received broken/damaged/leaking:	No
Air bubbles present in VOA vials for VOC/TPH analyses, if	f applicable: Not Applicable
TRRP 13 Reporting requested?	No
BacT Sample bottles filled to volume (100mL mark), if appl	licable: Not Applicable
LCR Sample bottles filled to volume (1 Liter mark), if appli	
Subcontracting required for any analyses:	No
RUSH turnaround time requested:	No
Requested Turnaround Time:	No
Samples delivered via :	Hand Delivered
Air bill included if Samples were shipped:	No
Other deviations not meeting SATL sample acceptance crite	ria notated on CoC: Notated on CoC, if any
Notes:  * Samples delivered to the laboratory on the same day that they a but are acceptable, if they arrive on ice.  ** If improperly preserved, notate client authorization on CoC to	re collected may not meet thermal preservation criteria (>0°C but <6°C) proceed with analysis.
Checked By: Aimee Lendon I	Date: 01/14/25 11:20 SATL#F0001 Revised 09/15/2022

#### Francesca Findlay

**From:** Kyle Stoner < kyle@copeengineeringtx.com>

Sent: Friday, February 21, 2025 1:58 PM

**To:** Francesca Findlay **Cc:** Brian Cope

**Subject:** WQ0010266001 City of Runge WWTP Renewal Application

Attachments: Municipal Disposal Renewal Spanish NORI.docx; Plain Language Summary - Spanish.pdf;

Comment Response Letter - TCEQ.pdf

#### Good afternoon,

Per your request, please find attached the completed Spanish NORI in Microsoft Word, a copy of the plain language summary in Spanish and a comment response letter.

Let me know if you have any questions or need anything else.

Thank you,

Kyle Stoner E.I.T. Graduate Engineer



Tex. Frm. Reg. # F-16078 8611 Botts Lane San Antonio, Texas 78217 210.828.7070 (phone) 210.828.7076 (fax)



February 21, 2025

Texas Commission on Environmental Quality Applications Review and Processing Team (MC148) Water Quality Division P.O. Box 13087 Austin, Texas 78711-3087

Re: Application to Renew Permit No. WQ0010266001

Issued to City of Runge

CN600737357; RN101917839

Ms. Francesca Findlay:

The following responses have been completed in reference to the TCEQ comment letter dated February 20, 2025:

1. Please provide the Plain Language Summary in Spanish.

Plain Language Summary in Spanish is attached.

 The following is a portion of the NORI which contains information relevant to your application. Please read it carefully and indicate if it contains any errors or omissions. The complete notice will be sent to you once the application is declared administratively complete.

APPLICATION. City of Runge, P.O. Box 206, Runge, Texas 78151, has applied to the Texas Commission on Environmental Quality (TCEQ) to renew Texas Land Application Permit (TLAP) No. WQ0010266001 to authorize the disposal of treated wastewater at a volume not to exceed a daily average flow of 110,000 gallons per day via surface irrigation on 42 acres. The domestic wastewater treatment facility and disposal site is located at 400 West Lyons, in the city of Runge, in Karnes County, Texas 78151. TCEQ received this application on February 14, 2025. The permit application will be available for viewing and copying at Runge City Hall, 109 North Helena Street, Runge, in Karnes County, Texas, prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.707777,28.881111&level=18

Further information may also be obtained from City of Runge at the address stated above or by calling Mr. Homer Lott, Major, at 830-239-4121.

I found one error and it is highlighted in red. It should read Mayor, Homer Lott.

3. The application indicates that public notices in Spanish are required. After confirming the portion of the NORI above does not contain any errors or omissions, please use the attached template to translate the NORI into Spanish. Only the first and last paragraphs are unique to this application and require translation. Please provide the translated Spanish NORI in a Microsoft Word document.

With the correction made above in red, the NORI has been translated into Spanish and is attached as a Word document.

If you have any further questions and/or comments, please let us know.

Thank You.

Kyle Stoner, E.I.T. Cope Engineering, Inc.

/attachments

#### Francesca Findlay

**From:** city of runge <city.of.runge@sbcglobal.net>

**Sent:** Tuesday, March 18, 2025 12:10 PM

**To:** Kyle Stoner; Francesca Findlay; Homer Lott; Lola Wozniak

**Subject:** Re: Nori WQ0010266001 City of Runge

Follow Up Flag: Follow up Flag Status: Flagged

To be Corrected:

#### **English**

The domestic wastewater treatment facility and disposal site is located at 301 E. Cleveland St.

#### Spanish

(La solicitud para el permiso estará disponible para leerla y copiarla en 109 N. Helena St.)

Please give me a call.

Thanks,

Esmeralda B. Castro City Secretary

City of Runge P.O. Box 206 Runge, TX 78151 830-239-4121 830-239-4804 830-299-8006 cell

[IMPORTANT]: The information contained within this email may contain confidential information and is meant solely for the individual or entity which it is addressed. Accessing this email by anyone else is strictly prohibited. If you are not the intended recipient or feel you have received this email in error, please notify the sender and delete this email from your system.

From: city of runge <city.of.runge@sbcglobal.net>

Sent: Tuesday, March 18, 2025 9:50 AM

To: Kyle Stoner <kyle@copeengineeringtx.com>

Cc: Francesca Findlay <Francesca.Findlay@tceq.texas.gov>; Homer Lott <patronlott@att.net>; Lola Wozniak

<loal><loal.wozniak@yahoo.com>

Subject: Re: Nori WQ0010266001 City of Runge

Received the Spanish notice with correct address, English notice needs correction as well.

#### Thanks,

Esmeralda B. Castro City Secretary

City of Runge P.O. Box 206 Runge, 7X 78151 830-239-4121

[IMPORTANT]: The information contained within this email may contain confidential information and is meant solely for the individual or entity which it is addressed. Accessing this email by anyone else is strictly prohibited. If you are not the intended recipient or feel you have received this email in error, please notify the sender and delete this email from your system.

From: Kyle Stoner <kyle@copeengineeringtx.com>

Sent: Tuesday, March 18, 2025 9:00 AM

To: Francesca Findlay <Francesca.Findlay@tceq.texas.gov>; city.of.runge@sbcglobal.net <city.of.runge@sbcglobal.net>

Cc: Brian Cope <bri> copeengineeringtx.com>; Homer Lott <patronlott@att.net>

Subject: RE: Nori WQ0010266001 City of Runge

#### Good morning Francesca,

It was brought to my attention that the address of 400 W. Lyons listed for the wastewater treatment plant is incorrect. The correct address is 301 East Cleveland St. I have corrected the Spanish NORI, see attached. Please let me know if I need to correct and send over additional documents or if you need assistance with anything else. Thank you,

Kyle Stoner, E.I.T. Cope Engineering, Inc.

From: Francesca Findlay < Francesca. Findlay@tceq.texas.gov>

Sent: Thursday, March 13, 2025 5:43 PM

To: city.of.runge@sbcglobal.net

Cc: Brian Cope <bri> Stoner <kyle@copeengineeringtx.com>; Kyle Stoner <kyle@copeengineeringtx.com>

Subject: FW: Nori WQ0010266001 City of Runge

Importance: High

Good afternoon,

Permit No. WQ0010266001

Applicants are required to publish the Notice of Receipt of Application and Intent to Obtain a Water Quality Permit within 30 days of the application being declared administratively complete.

#### Attached is:

- Letter of Declaration of Administrative Completeness
- Instructions of Public Notice
- Notice of Receipt of Application and Intent to Obtain a Water Quality Permit
- Affidavit of Publication
- Public Notice Verification Form
- Notice of Receipt of Application and Intent to Obtain a Water Quality Permit in Spanish Language (if applicable)

#### Thank you,

Francesca Findlay
License & Permit Specialist
ARP Team | Water Quality Division
512-239-2441
Texas Commission on Environmental Quality



Please consider whether it is necessary to print this e-mail

How is our customer service? Fill out our online customer satisfaction survey at <a href="http://www.tceg.texas.gov/customersurvey">http://www.tceg.texas.gov/customersurvey</a>.

 From:
 Andrew Gorton

 To:
 Kyle Stoner

 Cc:
 Sara Holmes

Subject: Re: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

**Date:** Friday, March 7, 2025 2:17:57 PM

Thank you Kyle, we will take a look at what you sent as soon as we can and let you know if we have additional questions or need more information. Have a good weekend also!

Thank you,

-Andy

Andrew Gorton, P.G.
Texas Commission on Environmental Quality
MC-150
PO Box 13087
Austin, TX 78711-3087
512.239.4585
Andrew.Gorton@tceq.texas.gov

**From:** Kyle Stoner <kyle@copeengineeringtx.com>

**Sent:** Friday, March 7, 2025 2:12 PM

**To:** Andrew Gorton < Andrew.Gorton@Tceq.Texas.Gov>

**Cc:** Sara Holmes <Sara.Holmes@tceq.texas.gov>

Subject: RE: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

Good afternoon Andrew,

Please see attached a comment response letter for the comments issued by you and Sara.

The revised pages are attached to the letter. Please let me know if I need to address anything further and I will be happy to do so. Enjoy your weekend!

Thank you,

Kyle Stoner, E.I.T.

Cope Engineering, Inc.

**From:** Andrew Gorton <Andrew.Gorton@Tceq.Texas.Gov>

**Sent:** Friday, February 21, 2025 11:19 AM

To: Brian Cope <br/> <br/> Strian@copeengineeringtx.com>; Kyle Stoner <kyle@copeengineeringtx.com>

**Cc:** Sara Holmes <Sara.Holmes@tceq.texas.gov>

Subject: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

Good morning Mr. Cope and Mr. Stoner,

The Water Quality Assessment (WQA) Team of the Texas Commission on Environmental Quality has completed a preliminary review of the permit application information and identified deficiencies (attached) that must be addressed before the WQA Team can continue with the technical review. The deficient item(s) will require your response in a timely, complete, and accurate manner.

An accurate and complete revised permit application is essential for making recommendations to the commission regarding whether this permit should be issued. Based on the information provided in the application, the executive director does not have sufficient information to make a recommendation. Therefore, you must send updated technically complete and accurate information within **14 days** (March 7, 2025) of the date of this email.

Any revisions can be sent electronically to me (WQA Team Geologist) or Sara Holmes (WQA Team Agronomist). If you have any questions, please feel free to contact either me or Sara.

Thank you,

-Andy

Andrew Gorton, P.G.
Texas Commission on Environmental Quality
MC-150
PO Box 13087
Austin, TX 78711-3087
512.239.4585
Andrew.Gorton@tceq.texas.gov



March 07, 2025

Texas Commission on Environmental Quality Applications Review and Processing Team (MC148) Water Quality Division P.O. Box 13087 Austin, Texas 78711-3087

Re: Application to Renew Permit No. WQ0010266001 Issued to City of Runge CN600737357; RN101917839

Andrew Gorton & Sara Holmes:

The following responses have been completed in reference to the TCEQ comment letter dated February 21, 2025:

#### Geology:

1. Domestic Worksheet 3.0, Section 6 and Attachment A – Well and Map Information: This reviewer identified approximately 12 water wells within one mile of the facility wastewater ponds and irrigation fields (with 6 being within one-half mile of the facility wastewater ponds and irrigation fields). Please confirm (or deny) this. If confirmed, please include these wells on the USGS topographic map or well map. Note that monitor wells and rig supply wells were not included in this count. Complete Table 3.0(3) and provide the well logs for wells within one-half mile of the facility wastewater ponds and irrigation fields. Note – the "TWDB Groundwater" and "Well Reports" layers must be activated to see each water well. See the Texas Water Development Board Water Data Interactive website for water well information:

https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer#.

12 water wells were identified also and Table 3.0(3) has been updated to reflect the additional well inside the half mile radius. See the revised table in the attachments.

2. Domestic Worksheet 3.0, Section 6 and Attachment 11 – USGS Well Map: The well map is not readable as presented in the application. It is acceptable to submit a portion of the well map that clearly identifies each well.

The USGS Well Map has been updated to reflect the 12 water wells identified and zoomed in to be readable for the application. See revised map in the attachments.

3. Domestic Worksheet 3.0, Section 7 and Attachment 13 – Groundwater Technical Report: This Report must assess the impact (if any) of the wastewater disposal system on

groundwater. This report shall include an evaluation of water wells in the area (e.g., depth to groundwater, etc.), the aquifer(s) under the proposed facility, and use of groundwater in the area (e.g., irrigation public supply, domestic, etc.), the wastewater application rate, and any wastewater pond liners. An example Groundwater Quality Technical Report can be provided upon request.

The groundwater technical report has been revised to address the topics listed above. See report in attachment.

#### SOILS & AGRONOMY

1. Domestic Worksheet 3.0, Section 2. Land Application Site(s) – Although the facility is currently operating at 0.065MGD, please replace this with the flow the permittee is approved for (0.110MGD).

Land application has been updated from 0.065MGD to 0.110MGD. See revised Section 2 in the attachments.

- 2. Domestic Worksheet 3.0, Section 5. Annual Cropping Plan Please include the following information into the cropping plan:
  - a. Please note that if year-round irrigation is intended, a cool season crop must be maintained on the irrigation site.
  - b. Crop nutrient requirements A TCEQ recommended source for obtaining this information: Nutrient Management Planning Tools (tamu.edu). Please refer to the S Crops Table provided by the Texas A&M AgriLife Extension on Nutrient Management.

The information listed above in bullet point a. and bullet point b. has been included in the revised Annual Cropping Plan. See revised Annual Cropping Plan in the attachments.

I have attached only the revised pages that pertain to the comments above. If I need to include these revised pages in the entire report and send that over I can do that as well.

If you have any further questions and/or comments, please let us know.

Thank You,

Kyle Stoner, E.I.T. Cope Engineering, Inc.

/attachments

# Section 5. Annual Cropping Plan (Instructions Page 68)

Attach an Annual Cropping Plan which includes a discussion of each of the following items. If not applicable, provide a detailed explanation indicating why. **Attachment**: No. 10

- Soils map with crops
- Cool and warm season plant species
- Crop yield goals
- Crop growing season
- Crop nutrient requirements
- Additional fertilizer requirements
- Minimum/maximum harvest height (for grass crops)
- Supplemental watering requirements
- Crop salt tolerances
- Harvesting method/number of harvests
- Justification for not removing existing vegetation to be irrigated

## Section 6. Well and Map Information (Instructions Page 69)

Attach a USGS map with the following information shown and labeled. If not applicable, provide a detailed explanation indicating why. **Attachment**: No. 11

- The boundaries of the land application site(s)
- Waste disposal or treatment facility site(s)
- On-site buildings
- Buffer zones
- Effluent storage and tailwater control facilities
- All water wells within 1-mile radius of the disposal site or property boundaries
- All springs and seeps onsite and within 500 feet of the property boundaries
- All surface waters in the state onsite and within 500 feet of the property boundaries
- All faults and sinkholes onsite and within 500 feet of the property

List and cross reference all water wells located within a half-mile radius of the disposal site or property boundaries shown on the USGS map in the following table. Attach additional pages as necessary to include all of the wells.

Table 3.0(3) - Water Well Data

Well ID	Well Use	Producing? Y/N	Open, cased, capped, or plugged?	Proposed Best Management Practice
7903704	Public	Y	Open	Outside buffer
7903705	Public	N	Plugged	Outside buffer
7903707	Public	Y	Cased	Outside buffer
7903708	Public	Y	Cased	Outside buffer
7911204	Private	Y	Open	Outside buffer

Well ID	Well Use	Producing? Y/N	Open, cased, capped, or plugged?	Proposed Best Management Practice
422793	Private	Y	Cased	Outside buffer

If water quality data or well log information is available please include the information in an attachment listed by Well ID.

Attachment: No. 12

## Section 7. Groundwater Quality (Instructions Page 69)

Attach a Groundwater Quality Technical Report which assesses the impact of the wastewater disposal system on groundwater. This report shall include an evaluation of the water wells (including the information in the well table provided in Item 6. above), the wastewater application rate, and pond liners. Indicate by a check mark that this report is provided.

Attachment: No. 13

Are groundwater n	onite	oring v	vells a	vailable ons	site?		Yes	$\boxtimes$	No
Do you plan to inst	all gr	round	water	monitoring	wells	or l	ysimeters	arou	and the land
application site?		Yes	$\boxtimes$	No					

If yes, provide the proposed location of the monitoring wells or lysimeters on a site map.

Attachment: N/A

# Section 8. Soil Map and Soil Analyses (Instructions Page 70)

#### A. Soil map

Attach a USDA Soil Survey map that shows the area to be used for effluent disposal.

Attachment: No. 14

## **B.** Soil analyses

Attach the laboratory results sheets from the soil analyses. **Note**: for renewal applications, the current annual soil analyses required by the permit are acceptable as long as the test date is less than one year prior to the submission of the application.

Attachment: No. 15

List all USDA designated soil series on the proposed land application site. Attach additional pages as necessary.

#### Table 3.0(4) - Soil Data

Soil Series	Depth from Surface	Permeability	Available Water Capacity	Curve Number
Schattel Clay Shc	0-80"	Slow	low	71
Coy Clay Loam	0-80"	Very slow	high	71
Pernitas Sandy Clay Loam	0-80"	Moderate	moderate	58
Weesatche Fine Sandy Loam	0-80"	Moderate	high	58

Soil Series	Depth from Surface	Permeability	Available Water Capacity	Curve Number
Colibro Sandy Clay Loam	0-80"	High	moderate	30

# Section 9. Effluent Monitoring Data (Instructions Page 71)

Is the facility in operation?

⊠ Yes □ No

If no, this section is not applicable and the worksheet is complete.

**If yes**, provide the effluent monitoring data for the parameters regulated in the existing permit. If a parameter is not regulated in the existing permit, enter N/A.

Table 3.0(5) - Effluent Monitoring Data

Date	30 Day Avg Flow MGD	BOD5 mg/l	TSS mg/l	рН	Chlorine Residual mg/l	Acres irrigated
June 2022	.0061	24	N/A	8.9	N/A	42
July 2022	.0261	19	N/A	9.0	N/A	42
Aug. 2022	.0218	19	N/A	8.4	N/A	42
Sept. 2022	.0385	38	N/A	7.3	N/A	42
Oct. 2022	.0192	25	N/A	8.8	N/A	42
Nov. 2022	.0351	53	N/A	8.8	N/A	42
Dec. 2022	.0366	76	N/A	8.6	N/A	42
Feb. 2023	.0399	96	N/A	6.8	N/A	42
April 2023	.0649	15	N/A	9.3	N/A	42
May 2023	.0752	21	N/A	9.8	N/A	42
July 2023	.0392	15	N/A	8.3	N/A	42
Aug. 2023	.0437	20	N/A	8.2	N/A	42
Oct. 2023	.0316	35	N/A	8.8	N/A	42
Nov. 2023	.0162	24	N/A	8.7	N/A	42
Dec. 2023	.0494	44	N/A	8.3	N/A	42
Jan. 2024	.0475	25	N/A	8.8	N/A	42
Feb. 2024	.0479	17	N/A	8.9	N/A	42
Mar. 2024	.0409	21	N/A	9.0	N/A	42

Date	30 Day Avg Flow MGD	BOD5 mg/l	TSS mg/l	рН	Chlorine Residual mg/l	Acres irrigated
April 2024	.0522	21	N/A	9.1	N/A	42
May 2024	.0470	12	N/A	8.6	N/A	42
June 2024	.0422	13	N/A	8.1	N/A	42
July 2024	.0343	13	N/A	8.5	N/A	42
Aug. 2024	.0312	20	N/A	9.0	N/A	42
Oct. 2024	.0000	18	N/A	9.0	N/A	42

Provide a discussion of all persistent excursions above the permitted limits and any corrective actions taken.

### **STATE OF TEXAS WELL REPORT for Tracking #422793**

Owner:

**Robert & Erica Jones** 

Owner Well #: 1

Address:

1221 S. Fm81

Runge, TX 78141

79-11-2

Well Location:

corner of fm81 & cr118 travel on cr

118 for about 100' to gate on left with new house, well is located 50' to the

north of the house.

Runge, TX 78141

Latitude:

Grid #:

28° 52' 13.14" N

Longitude:

097° 42' 12.12" W

Elevation:

326 ft. above sea level

Well County:

Karnes

Type of Work: New Well

Proposed Use:

**Domestic** 

Drilling Start Date: 3/25/2016

Drilling End Date: 3/30/2016

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)		
7.875	0	10		
6.75	10	168		

**Drilling Method:** 

Mud (Hydraulic) Rotary

Borehole Completion:

Annular Seal Data:

Straight Wall

T 5 " ")	5 " 5 " "	Description (complete of a selection)	
Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)	
-2	10	Cement 5 Bags/Sacks	

Seal Method: Slurry

Distance to Property Line (ft.): 150+

Sealed By: Driller

Distance to Septic Field or other

concentrated contamination (ft.): 150+

Distance to Septic Tank (ft.): 150+

Method of Verification: vissuale

Surface Completion:

Surface Sleeve Installed

**Surface Completion by Driller** 

Water Level:

90 ft. below land surface on 2016-03-30

Measurement Method: Weighted Line

Packers:

Plastic at 10 ft.

Plastic at 135 ft.

Type of Pump:

Submersible

Pump Depth (ft.): 150

Well Tests:

Pump

Yield: 8 GPM with 50 ft. drawdown after 1/2 hours

Water Quality:	Strata Depth (ft.)	Water Type		
	135 - 165	good		
		Chemical Analysis Made:	No	y.
		wingly penetrate any strata which contained injurious constituents?:	No	

Certification Data:

The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information:

**Borth Water Well** 

PO Box 954

Yorktown, TX 78164

Driller Name:

Joe D. Cliffe II

License Number:

58208

Comments:

No Data

# Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

# Casing: BLANK PIPE & WELL SCREEN DATA


Top (ft.)	Bottom (ft.)	Description	Dla (in.)	Type	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
0	1	sand	4.5		New Plastic		-2.5	140
1	5	colletche			(PVC)			
5	65	sand	4.5		New Plastic (PVC)	0.016	135	165
65	130	sand/clay mix	4 New Plastic (PVC)			165	168	
130	168	sand			(FVC)			

#### IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY


TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation P.O. Box 12157 Austin, TX 78711 (512) 334-5540



WORKSHEET 3.0 SECTION 6



# DOMESTIC WORKSHEET 3.0 ITEM 6

#### WATER QUALITY ASSESSMENT

The City of Runge's wastewater treatment plant and irrigation field are in Karnes County and located southeast of town. They sit over two major aquifers, the southern edge of the Carrizo-Wilcox Aquifer and the northern edge of the Gulf Coast Aquifer. However, the nearby wells in the area have all been drilled into the Gulf Coast Aquifer. The depth of these wells ranged from 57 feet to 720 feet deep with a water surface elevation of 38 feet below ground to 95 feet below ground.

There is a total of twelve water wells located within the one-mile radius of the wastewater treatment plant and the irrigation fields. Of those twelve water wells, five are used as domestic wells for private residences, four public supply wells used by the City of Runge (only two are in production), and three are used for livestock purposes. Within the one-half mile radius, there are six nearby wells consisting of four public supply wells owned by the City of Runge and two private domestic wells. The nearby private water wells are outside the 250' buffer zone required by 30 TAC Section 309.13(c). The nearest well is +/-550' from the land disposal site; however, the land disposal site does not drain to the nearest well.

The wastewater treatment plant contains a facultative lagoon and effluent storage pond. The effluent storage pond has a liner consisting of two feet of clay meeting liner permeability requirements in 30 TAC 217.203(d) to prevent treated effluent from percolating into the groundwater below. The current wastewater application rate is 65,000 GPD, although the site is permitted for an application rate of 110,000 GPD. Therefore, with the nearest water wells being 550 feet away, upstream of the treatment area, and the facility operating at nearly have of the application rate than allowed the impact of the waste disposal site on the groundwater is negligible.

# DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND DISPOSAL OF EFFLUENT

The following is required for renewal, new, and amendment permit applications.

# Section 1. Type of Disposal System (Instructions Page 68)

Identify the method of land disposal: Surface application Subsurface application Irrigation Subsurface soils absorption Subsurface area drip dispersal system Drip irrigation system Evaporation Evapotranspiration beds Other (describe in detail): Click to enter text. NOTE: All applicants without authorization or proposing new/amended subsurface disposal MUST complete and submit Worksheet 7.0.

For existing authorizations, provide Registration Number: N/A

# Section 2. Land Application Site(s) (Instructions Page 68)

In table 3.0(1), provide the requested information for the land application sites. Include the agricultural or cover crop type (wheat, cotton, alfalfa, bermuda grass, native grasses, etc.), land use (golf course, hayland, pastureland, park, row crop, etc.), irrigation area, amount of effluent applied, and whether or not the public has access to the area. Specify the amount of land area and the amount of effluent that will be allotted to each agricultural or cover crop, if more than one crop will be used.

#### Table 3.0(1) - Land Application Site Crops

Crop Type & Land Use	Irrigation Area (acres)	Effluent Application (GPD)	Public Access? Y/N
Agricultural Land - Bermuda grass	42	110,000	N
*			

# DOMESTIC WORKSHEET 3.0 Section 5

#### ANNUAL CROPPING PLAN

The irrigation site is composed of 42 acres used for agricultural pasture land.

The predominant soil on the surface at the irrigation site is Pernitas sandy clay loam (PnC). See attached USDA NRCS Soil Map in the attachments of this application.

The predominant cover is Coastal Bermuda grass. The minimum harvest height is 4" and the maximum harvest height is 24". It is harvested twice a year for the typical hay bailing activity. It has high salt tolerance and requires no supplemental watering. The growing season 8 out of 10 years is about 350 days per year for temperature above 24°F. No additional fertilizers are required.

The crop nutrient requirements for Coastal Bermuda grass with a hay cutting of 3 is 300 lbs of Nitrogen, 125 lbs of P205, and a crop removal rate of 238 of Nitrogen and 74 of P205.

Since irrigation is performed on the site year-round, when the Costal Bermuda grass is dormant, wild clover and winter rye grass provide cover across the field before the weather becomes warm enough for the coastal to grow again.

From: Kyle Stoner

To: Sara Holmes; Andrew Gorton

Subject: RE: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

**Date:** Monday, March 10, 2025 3:52:00 PM **Attachments:** Worsheet 3.0 Table 3.0(1).pdf

Hi Sara,

Please find attached the page containing Table 3.01(1) updated to reflect the cool season crops.

Thank you for the prompt response.

-Kyle

**From:** Sara Holmes <Sara.Holmes@tceq.texas.gov>

**Sent:** Monday, March 10, 2025 2:06 PM

**To:** Andrew Gorton <Andrew.Gorton@Tceq.Texas.Gov>; Kyle Stoner

<kyle@copeengineeringtx.com>

Subject: RE: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

Hi Kyle,

Thank you for those responses. I just have one follow-up comment. With the addition of the winter ryegrass and wild clover during the cooler months, could you please update and submit page 1 of Worksheet 3.0 to include these as additional crop types along with the Bermuda grass in Table 3.01(1)? That is all I need to continue my review.

Thank you,

Sara Holmes
Natural Resource Specialist II
Water Quality Assessment Team
12100 Park 35 Circle
Austin, TX 78753
512-239-4534

**From:** Andrew Gorton <<u>Andrew.Gorton@Tceg.Texas.Gov</u>>

**Sent:** Friday, March 7, 2025 2:18 PM

**To:** Kyle Stoner < kyle@copeengineeringtx.com > **Cc:** Sara Holmes < Sara.Holmes@tceg.texas.gov >

Subject: Re: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

Thank you Kyle, we will take a look at what you sent as soon as we can and let you know if

we have additional questions or need more information. Have a good weekend also!

Thank you,

-Andy

Andrew Gorton, P.G.

Texas Commission on Environmental Quality

MC-150

PO Box 13087

Austin, TX 78711-3087

512.239.4585

#### Andrew.Gorton@tceq.texas.gov

**From:** Kyle Stoner < kyle@copeengineeringtx.com>

**Sent:** Friday, March 7, 2025 2:12 PM

**To:** Andrew Gorton < <u>Andrew.Gorton@Tceg.Texas.Gov</u>>

**Cc:** Sara Holmes <<u>Sara.Holmes@tceq.texas.gov</u>>

Subject: RE: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

#### Good afternoon Andrew,

Please see attached a comment response letter for the comments issued by you and Sara. The revised pages are attached to the letter. Please let me know if I need to address anything further and I will be happy to do so. Enjoy your weekend!

Thank you,

Kyle Stoner, E.I.T.

Cope Engineering, Inc.

**From:** Andrew Gorton < <u>Andrew.Gorton@Tceg.Texas.Gov</u>>

**Sent:** Friday, February 21, 2025 11:19 AM

**To:** Brian Cope < brian@copeengineeringtx.com>; Kyle Stoner < kyle@copeengineeringtx.com>

**Cc:** Sara Holmes <<u>Sara.Holmes@tceq.texas.gov</u>>

Subject: City of Runge WWTF, Application for Renewal, Permit No. WQ0010266001

Good morning Mr. Cope and Mr. Stoner,

The Water Quality Assessment (WQA) Team of the Texas Commission on Environmental Quality has completed a preliminary review of the permit application information and identified deficiencies (attached) that must be addressed before the WQA Team can

continue with the technical review. The deficient item(s) will require your response in a timely, complete, and accurate manner.

An accurate and complete revised permit application is essential for making recommendations to the commission regarding whether this permit should be issued. Based on the information provided in the application, the executive director does not have sufficient information to make a recommendation. Therefore, you must send updated technically complete and accurate information within **14 days** (March 7, 2025) of the date of this email.

Any revisions can be sent electronically to me (WQA Team Geologist) or Sara Holmes (WQA Team Agronomist). If you have any questions, please feel free to contact either me or Sara.

Thank you,

-Andy

Andrew Gorton, P.G.

Texas Commission on Environmental Quality

MC-150

PO Box 13087

Austin, TX 78711-3087

512.239.4585

Andrew.Gorton@tceq.texas.gov

# DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND DISPOSAL OF EFFLUENT

The following is required for renewal, new, and amendment permit applications.

# Section 1. Type of Disposal System (Instructions Page 68)

Identif	y the method of land disposal:		
$\boxtimes$	Surface application		Subsurface application
	Irrigation		Subsurface soils absorption
	Drip irrigation system		Subsurface area drip dispersal system
	Evaporation		Evapotranspiration beds
	Other (describe in detail): Click to enter text.		
NOTE: All applicants without authorization or proposing new/amended subsurface disposal MUST complete and submit Worksheet 7.0.			

For existing authorizations, provide Registration Number: N/A

# Section 2. Land Application Site(s) (Instructions Page 68)

In table 3.0(1), provide the requested information for the land application sites. Include the agricultural or cover crop type (wheat, cotton, alfalfa, bermuda grass, native grasses, etc.), land use (golf course, hayland, pastureland, park, row crop, etc.), irrigation area, amount of effluent applied, and whether or not the public has access to the area. Specify the amount of land area and the amount of effluent that will be allotted to each agricultural or cover crop, if more than one crop will be used.

Table 3.0(1) - Land Application Site Crops

Crop Type & Land Use	Irrigation Area (acres)	Effluent Application (GPD)	Public Access? Y/N
Agricultural Land - Bermuda Grass	42	110,000	N
Agricultural Land - Winter Rye Grass (Cool Season)	42	110,000	N
Agricultural Land - Wild Clover (Cool Season)	42	110,000	N
			M
		- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	



# TEXAS COMMISSION ON ENVIRONMENTAL QUALITY P.O. Box 13087 Austin, Texas 78711-3087

This is a renewal of Permit No. WQ0010266001 issued on August 22, 2005.

# PERMIT TO DISCHARGE WASTES

under provisions of Chapter 26 of the Texas Water Code

City of Runge

whose mailing address is

P.O. Box 206 Runge, Texas 78151

Nature of Business Producing Waste: Domestic wastewater treatment operation, SIC Code 4952.

General Description and Location of Waste Disposal System:

Description: The City of Runge Wastewater Treatment Facility consists of a primary settling pond system. Treatment units include a facultative lagoon with a surface area of 1.01 acres and volume of 10.1 acre-feet. The permittee is authorized to dispose of treated domestic wastewater effluent at a daily average flow not to exceed 0.110 million gallons per day (MGD) via surface irrigation of 42 acres of non-public access agricultural land. The facility includes a storage pond with a total surface area of 2.21 acres and total capacity of 13.02 acre-feet for storage of treated effluent prior to irrigation. Application rates to the irrigated land shall not exceed 2.93 acre-feet per year per acre irrigated.

Location: The wastewater treatment facility and disposal site are located approximately 2,300 feet south and 1,600 feet east of the intersection of U.S. Highway 81 and U.S. Highway 72, in the City of Runge, in Karnes County, Texas 78151. (See Attachment A.)

Drainage Area: The wastewater treatment facility and disposal site are located in the drainage basin of the Lower San Antonio River in Segment No. 1901 of the San Antonio River Basin. No discharge of pollutants into water in the State is authorized by this permit.

This permit and the authorization contained herein shall expire at midnight on March 1, 2025.

ISSUED DATE: September 4, 2015

For the Commission

# EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS

# Conditions of the Permit: No discharge of pollutants into water in the State is authorized.

# A. Effluent Limitations

Character: Treated I

Treated Domestic Sewage Effluent

Volume:

Daily Average Flow – 0.110 MGD from the treatment system

Quality:

The following effluent limitations are required:

	Effluent Concentrations		
	(Not to Exceed)		
	Daily	Single	
<u>Parameter</u>	<u>Average</u>	<u>Grab</u>	
	mg/l	mg/l	
Biochemical Oxygen Demand (5-day)	N/A	100	

The pH shall not be less than 6.0 standard units nor greater than 9.0 standard units.

# B. <u>Monitoring Requirements</u>:

<u>Parameter</u>	<b>Monitoring Frequency</b>	<u>Sample Type</u>
Flow	Five/week	Instantaneous
Biochemical Oxygen	One/month	Grab
Demand (5-day)		
На	One/month	Grab

The monitoring shall be done after the final treatment unit and prior to irrigation. These records shall be maintained on a monthly basis and be available at the plant site for inspection by authorized representatives of the Commission for at least three years.

#### STANDARD PERMIT CONDITIONS

This permit is granted in accordance with the Texas Water Code and the rules and other Orders of the Commission and the laws of the State of Texas.

#### **DEFINITIONS**

All definitions in Section 26.001 of the Texas Water Code and 30 TAC Chapter 305 shall apply to this permit and are incorporated by reference. Some specific definitions of words or phrases used in this permit are as follows:

#### 1. Flow Measurements

- a. Daily average flow the arithmetic average of all determinations of the daily flow within a period of one calendar month. The daily average flow determination shall consist of determinations made on at least four separate days. If instantaneous measurements are used to determine the daily flow, the determination shall be the arithmetic average of all instantaneous measurements taken during that month. Daily average flow determination for intermittent discharges shall consist of a minimum of three flow determinations on days of discharge.
- b. Annual average flow the arithmetic average of all daily flow determinations taken within the preceding 12 consecutive calendar months. The annual average flow determination shall consist of daily flow volume determinations made by a totalizing meter, charted on a chart recorder and limited to major domestic wastewater discharge facilities with 1 million gallons per day or greater permitted flow.
- c. Instantaneous flow the measured flow during the minimum time required to interpret the flow measuring device.

# 2. Concentration Measurements

- a. Daily average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar month, consisting of at least four separate representative measurements.
  - i. For domestic wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values in the previous four consecutive month period consisting of at least four measurements shall be utilized as the daily average concentration.
  - ii. For all other wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values taken during the month shall be utilized as the daily average concentration.
- b. 7-day average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar week, Sunday through Saturday.
- c. Daily maximum concentration the maximum concentration measured on a single day, by the sample type specified in the permit, within a period of one calendar month.

#### 3. Sample Type

- a. Composite sample For domestic wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (a). For industrial wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (b).
- b. Grab sample an individual sample collected in less than 15 minutes.
- 4. Treatment Facility (facility) wastewater facilities used in the conveyance, storage, treatment, recycling, reclamation and/or disposal of domestic sewage, industrial wastes, agricultural wastes, recreational wastes, or other wastes including sludge handling or disposal facilities under the jurisdiction of the Commission.
- 5. The term "sewage sludge" is defined as solid, semi-solid, or liquid residue generated during the treatment of domestic sewage in 30 TAC Chapter 312. This includes the solids which have not been classified as hazardous waste separated from wastewater by unit processes.
- 6. Bypass the intentional diversion of a waste stream from any portion of a treatment facility.

# MONITORING REQUIREMENTS

#### 1. Monitoring Requirements

Monitoring results shall be collected at the intervals specified in the permit. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall conduct effluent sampling in accordance with 30 TAC §§ 319.4 - 319.12.

As provided by state law, the permittee is subject to administrative, civil and criminal penalties, as applicable, for negligently or knowingly violating the Texas Water Code, Chapters 26, 27, and 28, and Texas Health and Safety Code, Chapter 361, including but not limited to knowingly making any false statement, representation, or certification on any report, record or other document submitted or required to be maintained under this permit, including monitoring reports, records or reports of compliance or noncompliance, or falsifying, tampering with or knowingly rendering inaccurate any monitoring device or method required by this permit or violating any other requirement imposed by state or federal regulations.

# 2. Test Procedures

- a. Unless otherwise specified in this permit, test procedures for the analysis of pollutants shall comply with procedures specified in 30 TAC §§ 319.11 319.12. Measurements, tests and calculations shall be accurately accomplished in a representative manner.
- b. All laboratory tests submitted to demonstrate compliance with this permit must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

#### 3. Records of Results

- a. Monitoring samples and measurements shall be taken at times and in a manner so as to be representative of the monitored activity.
- b. Except for records of monitoring information required by this permit related to the permittee's sewage sludge use and disposal activities, which shall be retained for a period of at least five years, monitoring and reporting records, including strip charts and records of calibration and maintenance, copies of all records required by this permit, and records of all data used to complete the application for this permit shall be retained at the facility site, or shall be readily available for review by a TCEQ representative for a period of three years from the date of the record or sample, measurement, report, or application. This period shall be extended at the request of the Executive Director.
- c. Records of monitoring activities shall include the following:
  - i. date, time and place of sample or measurement;
  - ii. identity of individual who collected the sample or made the measurement.
  - iii. date and time of analysis;
  - iv. identity of the individual and laboratory who performed the analysis;
  - v. the technique or method of analysis; and
  - vi. the results of the analysis or measurement and quality assurance/quality control records.

The period during which records are required to be kept shall be automatically extended to the date of the final disposition of any administrative or judicial enforcement action that may be instituted against the permittee.

# 4. Additional Monitoring by Permittee

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit using approved analytical methods as specified above, all results of such monitoring shall be included in determining compliance with permit requirements.

#### 5. Calibration of Instruments

All automatic flow measuring or recording devices and all totalizing meters for measuring flows shall be accurately calibrated by a trained person at plant start-up and as often thereafter as necessary to ensure accuracy, but not less often than annually unless authorized by the Executive Director for a longer period. Such person shall verify in writing that the device is operating properly and giving accurate results. Copies of the verification shall be retained at the facility site and/or shall be readily available for review by a TCEQ representative for a period of three years.

# 6. Compliance Schedule Reports

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date to the Regional Office and the Enforcement Division (MC 224).

# 7. Noncompliance Notification

- a. In accordance with 30 TAC § 305.125(9), any noncompliance which may endanger human health or safety, or the environment shall be reported by the permittee to the TCEQ. Report of such information shall be provided orally or by facsimile transmission (FAX) to the Regional Office within 24 hours of becoming aware of the noncompliance. A written submission of such information shall also be provided by the permittee to the Regional Office and the Enforcement Division (MC 224) within five working days of becoming aware of the noncompliance. The written submission shall contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
- b. The following violations shall be reported under Monitoring and Reporting Requirement 7.a.:
  - i. Unauthorized discharges as defined in Permit Condition 2(g).
  - ii. Any unanticipated bypass which exceeds any effluent limitation in the permit.
- c. In addition to the above, any effluent violation which deviates from the permitted effluent limitation by more than 40% shall be reported by the permittee in writing to the Regional Office and the Enforcement Division (MC 224) within 5 working days of becoming aware of the noncompliance.
- d. Any noncompliance other than that specified in this section, or any required information not submitted or submitted incorrectly, shall be reported to the Enforcement Division (MC 224) as promptly as possible.
- 8. In accordance with the procedures described in 30 TAC §§ 35.301 35.303 (relating to Water Quality Emergency and Temporary Orders) if the permittee knows in advance of the need for a bypass, it shall submit prior notice by applying for such authorization.
- 9. Changes in Discharges of Toxic Substances

All existing manufacturing, commercial, mining, and silvicultural permittees shall notify the Regional Office, orally or by facsimile transmission within 24 hours, and both the Regional Office and the Enforcement Division (MC 224) in writing within five (5) working days, after becoming aware of or having reason to believe:

- a. That any activity has occurred or will occur which would result in the discharge, on a routine or frequent basis, of any toxic pollutant listed at 40 CFR Part 122, Appendix D, Tables II and III (excluding Total Phenols) which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
  - i. One hundred micrograms per liter (100 µg/L);
  - ii. Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;

- iii. Five (5) times the maximum concentration value reported for that pollutant in the permit application; or
- iv. The level established by the TCEQ.
- b. That any activity has occurred or will occur which would result in any discharge, on a nonroutine or infrequent basis, of a toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
  - i. Five hundred micrograms per liter (500 μg/L);
  - ii. One milligram per liter (1 mg/L) for antimony;
  - iii. Ten (10) times the maximum concentration value reported for that pollutant in the permit application; or
  - iv. The level established by the TCEQ.

#### 10. Signatories to Reports

All reports and other information requested by the Executive Director shall be signed by the person and in the manner required by 30 TAC § 305.128 (relating to Signatories to Reports).

#### PERMIT CONDITIONS

#### 1. General

- a. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in an application or in any report to the Executive Director, it shall promptly submit such facts or information.
- b. This permit is granted on the basis of the information supplied and representations made by the permittee during action on an application, and relying upon the accuracy and completeness of that information and those representations. After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked, in whole or in part, in accordance with 30 TAC Chapter 305, Subchapter D, during its term for good cause including, but not limited to, the following:
  - i. Violation of any terms or conditions of this permit;
  - ii. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
  - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- c. The permittee shall furnish to the Executive Director, upon request and within a reasonable time, any information to determine whether cause exists for amending, revoking, suspending or terminating the permit. The permittee shall also furnish to the Executive Director, upon request, copies of records required to be kept by the permit.

#### 2. Compliance

a. Acceptance of the permit by the person to whom it is issued constitutes acknowledgment and agreement that such person will comply with all the terms and conditions embodied in the permit, and the rules and other orders of the Commission.

- b. The permittee has a duty to comply with all conditions of the permit. Failure to comply with any permit condition constitutes a violation of the permit and the Texas Water Code or the Texas Health and Safety Code, and is grounds for enforcement action, for permit amendment, revocation or suspension, or for denial of a permit renewal application or an application for a permit for another facility.
- c. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit.
- d. The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal or other permit violation which has a reasonable likelihood of adversely affecting human health or the environment.
- e. Authorization from the Commission is required before beginning any change in the permitted facility or activity that may result in noncompliance with any permit requirements.
- f. A permit may be amended, suspended and reissued, or revoked for cause in accordance with 30 TAC §§ 305.62 and 305.66 and Texas Water Code Section 7.302. The filing of a request by the permittee for a permit amendment, suspension and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.
- g. There shall be no unauthorized discharge of wastewater or any other waste. For the purpose of this permit, an unauthorized discharge is considered to be any discharge of wastewater into or adjacent to water in the state at any location not permitted as an outfall or otherwise defined in the Special Provisions section of this permit.
- h. The permittee is subject to administrative, civil, and criminal penalties, as applicable, under Texas Water Code §§ 7.051 7.075 (relating to Administrative Penalties), 7.101 7.111 (relating to Civil Penalties), and 7.141 7.202 (relating to Criminal Offenses and Penalties).

#### 3. Inspections and Entry

- a. Inspection and entry shall be allowed as prescribed in the Texas Water Code Chapters 26, 27, and 28, and Texas Health and Safety Code Chapter 361.
- b. The members of the Commission and employees and agents of the Commission are entitled to enter any public or private property at any reasonable time for the purpose of inspecting and investigating conditions relating to the quality of water in the state or the compliance with any rule, regulation, permit or other order of the Commission. Members, employees, or agents of the Commission and Commission contractors are entitled to enter public or private property at any reasonable time to investigate or monitor or, if the responsible party is not responsive or there is an immediate danger to public health or the environment, to remove or remediate a condition related to the quality of water in the state. Members, employees, Commission contractors, or agents acting under this authority who enter private property shall observe the establishment's rules and regulations concerning safety, internal security, and fire protection, and if the property has management in residence, shall notify management or the person then in

charge of his presence and shall exhibit proper credentials. If any member, employee, Commission contractor, or agent is refused the right to enter in or on public or private property under this authority, the Executive Director may invoke the remedies authorized in Texas Water Code Section 7.002. The statement above, that Commission entry shall occur in accordance with an establishment's rules and regulations concerning safety, internal security, and fire protection, is not grounds for denial or restriction of entry to any part of the facility, but merely describes the Commission's duty to observe appropriate rules and regulations during an inspection.

# 4. Permit Amendment and/or Renewal

- a. The permittee shall give notice to the Executive Director as soon as possible of any planned physical alterations or additions to the permitted facility if such alterations or additions would require a permit amendment or result in a violation of permit requirements. Notice shall also be required under this paragraph when:
  - i. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements in Monitoring and Reporting Requirements No. 9;
  - ii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan.
- b. Prior to any facility modifications, additions, or expansions that will increase the plant capacity beyond the permitted flow, the permittee must apply for and obtain proper authorization from the Commission before commencing construction.
- c. The permittee must apply for an amendment or renewal at least 180 days prior to expiration of the existing permit in order to continue a permitted activity after the expiration date of the permit. If an application is submitted prior to the expiration date of the permit, the existing permit shall remain in effect until the application is approved, denied, or returned. If the application is returned or denied, authorization to continue such activity shall terminate upon the effective date of the action. If an application is not submitted prior to the expiration date of the permit, the permit shall expire and authorization to continue such activity shall terminate.
- d. Prior to accepting or generating wastes which are not described in the permit application or which would result in a significant change in the quantity or quality of the existing discharge, the permittee must report the proposed changes to the Commission. The permittee must apply for a permit amendment reflecting any necessary changes in permit conditions, including effluent limitations for pollutants not identified and limited by this permit.
- e. In accordance with the Texas Water Code § 26.029(b), after a public hearing, notice of which shall be given to the permittee, the Commission may require the permittee, from time to time, for good cause, in accordance with applicable laws, to conform to new or additional conditions.

#### 5. Permit Transfer

- a. Prior to any transfer of this permit, Commission approval must be obtained. The Commission shall be notified in writing of any change in control or ownership of facilities authorized by this permit. Such notification should be sent to the Applications Review and Processing Team (MC 148) of the Water Quality Division.
- b. A permit may be transferred only according to the provisions of 30 TAC § 305.64 (relating to Transfer of Permits) and 30 TAC § 50.133 (relating to Executive Director Action on Application or WQMP update).

# 6. Relationship to Hazardous Waste Activities

This permit does not authorize any activity of hazardous waste storage, processing, or disposal which requires a permit or other authorization pursuant to the Texas Health and Safety Code.

# 7. Property Rights

A permit does not convey any property rights of any sort, or any exclusive privilege.

# 8. Permit Enforceability

The conditions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

# 9. Relationship to Permit Application

The application pursuant to which the permit has been issued is incorporated herein; provided, however, that in the event of a conflict between the provisions of this permit and the application, the provisions of the permit shall control.

#### 10. Notice of Bankruptcy.

- a. Each permittee shall notify the Executive Director, in writing, immediately following the filing of a voluntary or involuntary petition for bankruptcy under any chapter of Title 11 (Bankruptcy) of the United States Code (11 USC) by or against:
  - i. the permittee;
  - ii. an entity (as that term is defined in 11 USC, § 101(14)) controlling the permittee or listing the permit or permittee as property of the estate; or
  - iii. an affiliate (as that term is defined in 11 USC, § 101(2)) of the permittee.

# b. This notification must indicate:

- i. the name of the permittee;
- ii. the permit number(s);
- iii. the bankruptcy court in which the petition for bankruptcy was filed; and
- iv. the date of filing of the petition.

#### **OPERATIONAL REQUIREMENTS**

- 1. The permittee shall at all times ensure that the facility and all of its systems of collection, treatment, and disposal are properly operated and maintained. This includes, but is not limited to, the regular, periodic examination of wastewater solids within the treatment plant by the operator in order to maintain an appropriate quantity and quality of solids inventory as described in the various operator training manuals and according to accepted industry standards for process control. Process control, maintenance, and operations records shall be retained at the facility site, or shall be readily available for review by a TCEQ representative, for a period of three years.
- 2. Upon request by the Executive Director, the permittee shall take appropriate samples and provide proper analysis in order to demonstrate compliance with Commission rules. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall comply with all applicable provisions of 30 TAC Chapter 312 concerning sewage sludge use and disposal and 30 TAC §§ 319.21 319.29 concerning the discharge of certain hazardous metals.
- 3. Domestic wastewater treatment facilities shall comply with the following provisions:
  - a. The permittee shall notify the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, in writing, of any facility expansion at least 90 days prior to conducting such activity.
  - b. The permittee shall submit a closure plan for review and approval to the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, for any closure activity at least 90 days prior to conducting such activity. Closure is the act of permanently taking a waste management unit or treatment facility out of service and includes the permanent removal from service of any pit, tank, pond, lagoon, surface impoundment and/or other treatment unit regulated by this permit.
- 4. The permittee is responsible for installing prior to plant start-up, and subsequently maintaining, adequate safeguards to prevent the discharge of untreated or inadequately treated wastes during electrical power failures by means of alternate power sources, standby generators, and/or retention of inadequately treated wastewater.
- 5. Unless otherwise specified, the permittee shall provide a readily accessible sampling point and, where applicable, an effluent flow measuring device or other acceptable means by which effluent flow may be determined.
- 6. The permittee shall remit an annual water quality fee to the Commission as required by 30 TAC Chapter 21. Failure to pay the fee may result in revocation of this permit under Texas Water Code § 7.302(b)(6).

# 7. Documentation

For all written notifications to the Commission required of the permittee by this permit, the permittee shall keep and make available a copy of each such notification under the same conditions as self-monitoring data are required to be kept and made available. Except for information specified as not confidential in 30 TAC § 1.5(d), any information submitted pursuant to this permit may be claimed as confidential by the submitter. Any such claim

must be asserted in the manner prescribed in the application form or by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, information may be made available to the public without further notice. If the Commission or Executive Director agrees with the designation of confidentiality, the TCEQ will not provide the information for public inspection unless required by the Texas Attorney General or a court pursuant to an open records request. If the Executive Director does not agree with the designation of confidentiality, the person submitting the information will be notified.

- 8. Facilities which generate domestic wastewater shall comply with the following provisions; domestic wastewater treatment facilities at permitted industrial sites are excluded.
  - a. Whenever flow measurements for any domestic sewage treatment facility reach 75 percent of the permitted daily average or annual average flow for three consecutive months, the permittee must initiate engineering and financial planning for expansion and/or upgrading of the domestic wastewater treatment and/or collection facilities. Whenever the flow reaches 90 percent of the permitted daily average or annual average flow for three consecutive months, the permittee shall obtain necessary authorization from the Commission to commence construction of the necessary additional treatment and/or collection facilities. In the case of a domestic wastewater treatment facility which reaches 75 percent of the permitted daily average or annual average flow for three consecutive months, and the planned population to be served or the quantity of waste produced is not expected to exceed the design limitations of the treatment facility, the permittee shall submit an engineering report supporting this claim to the Executive Director of the Commission.

If in the judgement of the Executive Director the population to be served will not cause permit noncompliance, then the requirement of this section may be waived. To be effective, any waiver must be in writing and signed by the Director of the Enforcement Division (MC 169) of the Commission, and such waiver of these requirements will be reviewed upon expiration of the existing permit; however, any such waiver shall not be interpreted as condoning or excusing any violation of any permit parameter.

- b. The plans and specifications for domestic sewage collection and treatment works associated with any domestic permit must be approved by the Commission, and failure to secure approval before commencing construction of such works or making a discharge is a violation of this permit and each day is an additional violation until approval has been secured.
- c. Permits for domestic wastewater treatment plants are granted subject to the policy of the Commission to encourage the development of area-wide waste collection, treatment and disposal systems. The Commission reserves the right to amend any domestic wastewater permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an area-wide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such area-wide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.

- 9. Domestic wastewater treatment plants shall be operated and maintained by sewage plant operators holding a valid certificate of competency at the required level as defined in 30 TAC Chapter 30.
- 10. Facilities which generate industrial solid waste as defined in 30 TAC § 335.1 shall comply with these provisions:
  - a. Any solid waste, as defined in 30 TAC § 335.1 (including but not limited to such wastes as garbage, refuse, sludge from a waste treatment, water supply treatment plant or air pollution control facility, discarded materials, discarded materials to be recycled, whether the waste is solid, liquid, or semisolid), generated by the permittee during the management and treatment of wastewater, must be managed in accordance with all applicable provisions of 30 TAC Chapter 335, relating to Industrial Solid Waste Management.
  - b. Industrial wastewater that is being collected, accumulated, stored, or processed before discharge through any final discharge outfall, specified by this permit, is considered to be industrial solid waste until the wastewater passes through the actual point source discharge and must be managed in accordance with all applicable provisions of 30 TAC Chapter 335.
  - c. The permittee shall provide written notification, pursuant to the requirements of 30 TAC § 335.8(b)(1), to the Environmental Cleanup Section (MC 127) of the Remediation Division informing the Commission of any closure activity involving an Industrial Solid Waste Management Unit, at least 90 days prior to conducting such an activity.
  - d. Construction of any industrial solid waste management unit requires the prior written notification of the proposed activity to the Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division. No person shall dispose of industrial solid waste, including sludge or other solids from wastewater treatment processes, prior to fulfilling the deed recordation requirements of 30 TAC § 335.5.
  - e. The term "industrial solid waste management unit" means a landfill, surface impoundment, waste-pile, industrial furnace, incinerator, cement kiln, injection well, container, drum, salt dome waste containment cavern, or any other structure vessel, appurtenance, or other improvement on land used to manage industrial solid waste.
  - f. The permittee shall keep management records for all sludge (or other waste) removed from any wastewater treatment process. These records shall fulfill all applicable requirements of 30 TAC Chapter 335 and must include the following, as it pertains to wastewater treatment and discharge:
    - i. Volume of waste and date(s) generated from treatment process;
    - ii. Volume of waste disposed of on-site or shipped off-site;
    - iii. Date(s) of disposal;
    - iv. Identity of hauler or transporter;
    - v. Location of disposal site; and
    - vi. Method of final disposal.

The above records shall be maintained on a monthly basis. The records shall be retained at the facility site, or shall be readily available for review by authorized representatives of

the TCEQ for at least five years.

11. For industrial facilities to which the requirements of 30 TAC Chapter 335 do not apply, sludge and solid wastes, including tank cleaning and contaminated solids for disposal, shall be disposed of in accordance with Chapter 361 of the Texas Health and Safety Code.

TCEQ Revision 06/2008

#### SLUDGE PROVISIONS

The permittee is authorized to dispose of sludge only at a Texas Commission on Environmental Quality (TCEQ) authorized land application site or co-disposal landfill. The disposal of sludge by land application on property owned, leased or under the direct control of the permittee is a violation of the permit unless the site is authorized with the TCEQ. This provision does not authorize Distribution and Marketing of sludge. This provision does not authorize land application of Class A or Class AB Sewage Sludge. This provision does not authorize the permittee to land apply sludge on property owned, leased or under the direct control of the permittee.

# SECTION I. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE LAND APPLICATION

# A. General Requirements

- 1. The permittee shall handle and dispose of sewage sludge in accordance with 30 TAC § 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge.
- 2. In all cases, if the person (permit holder) who prepares the sewage sludge supplies the sewage sludge to another person for land application use or to the owner or lease holder of the land, the permit holder shall provide necessary information to the parties who receive the sludge to assure compliance with these regulations.
- 3. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.

# **B.** Testing Requirements

1. Sewage sludge shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I [Toxicity Characteristic Leaching Procedure (TCLP)] or other method that receives the prior approval of the TCEQ for the contaminants listed in 40 CFR Part 261.24, Table 1. Sewage sludge failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal. Following failure of any TCLP test, the management or disposal of sewage sludge at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division and the Regional Director (MC Region 13) within seven (7) days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Registration, Review, and Reporting Division (MC 129), Texas Commission on Environmental Quality, P.O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 13) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30th of each year.

2. Sewage sludge shall not be applied to the land if the concentration of the pollutants exceeds the pollutant concentration criteria in Table 1. The frequency of testing for pollutants in Table 1 is found in Section I.C.

TABLE 1

<u>Pollutant</u>	<u>Ceiling Concentration</u> ( <u>Milligrams per kilogram</u> )*
Arsenic	75
Cadmium	85
Chromium	3000
Copper	4300
Lead	840
Mercury	57
Molybdenum	75
Nickel	420
PCBs	49
Selenium	100
Zine	7500

^{*} Dry weight basis

# 3. Pathogen Control

All sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site must be treated by one of the following methods to ensure that the sludge meets either the Class A, Class AB or Class B pathogen requirements.

a. For sewage sludge to be classified as Class A with respect to pathogens, the density of fecal coliform in the sewage sludge be less than 1,000 most probable number (MPN) per gram of total solids (dry weight basis), or the density of Salmonella sp. bacteria in the sewage sludge be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met.

Alternative 1 - The temperature of the sewage sludge that is used or disposed shall be maintained at or above a specific value for a period of time. See 30 TAC § 312.82(a)(2)(A) for specific information.

Alternative 5 (PFRP) - Sewage sludge that is used or disposed of must be treated in one of the Processes to Further Reduce Pathogens (PFRP) described in 40 CFR Part 503, Appendix B. PFRP include composting, heat drying, heat treatment, and thermophilic aerobic digestion.

Alternative 6 (PFRP Equivalent) - Sewage sludge that is used or disposed of must be treated in a process that has been approved by the U. S. Environmental Protection Agency as being equivalent to those in Alternative 5.

b. For sewage sludge to be classified as Class AB with respect to pathogens, the density of fecal coliform in the sewage sludge be less than 1,000 MPN per gram of total solids (dry weight basis), or the density of Salmonella sp. bacteria in the sewage sludge be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met.

Alternative 2 - The pH of the sewage sludge that is used or disposed shall be raised to above 12 std. units and shall remain above 12 std. units for 72 hours.

The temperature of the sewage sludge shall be above 52° Celsius for 12 hours or longer during the period that the pH of the sewage sludge is above 12 std. units.

At the end of the 72-hour period during which the pH of the sewage sludge is above 12 std. units, the sewage sludge shall be air dried to achieve a percent solids in the sewage sludge greater than 50%.

Alternative 3 - The sewage sludge shall be analyzed for enteric viruses prior to pathogen treatment. The limit for enteric viruses is less than one Plaque-forming Unit per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(i-iii) for specific information. The sewage sludge shall be analyzed for viable helminth ova prior to pathogen treatment. The limit for viable helminth ova is less than one per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(iv-vi) for specific information.

Alternative 4 - The density of enteric viruses in the sewage sludge shall be less than one Plaque-forming Unit per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. The density of viable helminth ova in the sewage sludge shall be less than one per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed.

- c. Sewage sludge that meets the requirements of Class AB sewage sludge may be classified a Class A sewage sludge if a variance request is submitted in writing that is supported by substantial documentation demonstrating equivalent methods for reducing odors and written approval is granted by the executive director. The executive director may deny the variance request or revoke that approved variance if it is determined that the variance may potentially endanger human health or the environment, or create nuisance odor conditions.
- d. Three alternatives are available to demonstrate compliance with Class B criteria for sewage sludge.

#### Alternative 1

- i. A minimum of seven random samples of the sewage sludge shall be collected within 48 hours of the time the sewage sludge is used or disposed of during each monitoring episode for the sewage sludge.
- ii. The geometric mean of the density of fecal coliform in the samples collected shall be less than either 2,000,000 MPN per gram of total solids (dry weight basis) or 2,000,000 Colony Forming Units per gram of total solids (dry weight basis).

<u>Alternative 2</u> - Sewage sludge that is used or disposed of shall be treated in one of the Processes to Significantly Reduce Pathogens (PSRP) described in 40 CFR Part 503, Appendix B, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;
- ii. An independent Texas Licensed Professional Engineer must make a certification to the generator of a sewage sludge that the wastewater treatment facility generating the sewage sludge is designed to achieve one of the PSRP at the permitted design loading of the facility. The certification need only be repeated if the design loading of the facility is increased. The certification shall include a statement indicating the design meets all the applicable standards specified in Appendix B of 40 CFR Part 503;
- iii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iv. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review; and
- v. If the sewage sludge is generated from a mixture of sources, resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the PSRP, and shall meet the certification, operation, and record keeping requirements of this paragraph.

<u>Alternative 3</u> - Sewage sludge shall be treated in an equivalent process that has been approved by the U.S. Environmental Protection Agency, so long as all of the following requirements are met by the generator of the sewage sludge.

i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;

- ii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iii. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review;
- iv. The Executive Director will accept from the U.S. Environmental Protection Agency a finding of equivalency to the defined PSRP; and
- v. If the sewage sludge is generated from a mixture of sources resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the Processes to Significantly Reduce Pathogens, and shall meet the certification, operation, and record keeping requirements of this paragraph.

<u>In addition</u>, the following site restrictions must be met if Class B sludge is land applied:

- i. Food crops with harvested parts that touch the sewage sludge/soil mixture and are totally above the land surface shall not be harvested for 14 months after application of sewage sludge.
- ii. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after application of sewage sludge when the sewage sludge remains on the land surface for 4 months or longer prior to incorporation into the soil.
- iii. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months after application of sewage sludge when the sewage sludge remains on the land surface for less than 4 months prior to incorporation into the soil.
- iv. Food crops, feed crops, and fiber crops shall not be harvested for 30 days after application of sewage sludge.
- v. Animals shall not be allowed to graze on the land for 30 days after application of sewage sludge.
- vi. Turf grown on land where sewage sludge is applied shall not be harvested for 1 year after application of the sewage sludge when the harvested turf is placed on either land with a high potential for public exposure or a lawn.
- vii. Public access to land with a high potential for public exposure shall be restricted for 1 year after application of sewage sludge.

- viii. Public access to land with a low potential for public exposure shall be restricted for 30 days after application of sewage sludge.
- ix. Land application of sludge shall be in accordance with the buffer zone requirements found in 30 TAC § 312.44.
- 4. Vector Attraction Reduction Requirements

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site shall be treated by one of the following Alternatives 1 through 10 for vector attraction reduction.

- Alternative 1 The mass of volatile solids in the sewage sludge shall be reduced by a minimum of 38%.
- Alternative 2 If Alternative 1 cannot be met for an anaerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge anaerobically in the laboratory in a bench-scale unit for 40 additional days at a temperature between 30° and 37° Celsius. Volatile solids must be reduced by less than 17% to demonstrate compliance.
- Alternative 3 If Alternative 1 cannot be met for an aerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge with percent solids of two percent or less aerobically in the laboratory in a bench-scale unit for 30 additional days at 20° Celsius. Volatile solids must be reduced by less than 15% to demonstrate compliance.
- Alternative 4 The specific oxygen uptake rate (SOUR) for sewage sludge treated in an aerobic process shall be equal to or less than 1.5 milligrams of oxygen per hour per gram of total solids (dry weight basis) at a temperature of 20° Celsius.
- Alternative 5 Sewage sludge shall be treated in an aerobic process for 14 days or longer. During that time, the temperature of the sewage sludge shall be higher than 40° Celsius and the average temperature of the sewage sludge shall be higher than 45° Celsius.
- Alternative 6 The pH of sewage sludge shall be raised to 12 or higher by alkali addition and, without the addition of more alkali shall remain at 12 or higher for two hours and then remain at a pH of 11.5 or higher for an additional 22 hours at the time the sewage sludge is prepared for sale or given away in a bag or other container.
- Alternative 7 The percent solids of sewage sludge that does not contain unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 75% based on the moisture content and total solids prior to mixing with other materials. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

#### Alternative 8 -

The percent solids of sewage sludge that contains unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 90% based on the moisture content and total solids prior to mixing with other materials at the time the sludge is used. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

# Alternative 9 -

- i. Sewage sludge shall be injected below the surface of the land.
- ii. No significant amount of the sewage sludge shall be present on the land surface within one hour after the sewage sludge is injected.
- iii. When sewage sludge that is injected below the surface of the land is Class A or Class AB with respect to pathogens, the sewage sludge shall be injected below the land surface within eight hours after being discharged from the pathogen treatment process.

#### Alternative 10-

- i. Sewage sludge applied to the land surface or placed on a surface disposal site shall be incorporated into the soil within six hours after application to or placement on the land.
- ii. When sewage sludge that is incorporated into the soil is Class A or Class AB with respect to pathogens, the sewage sludge shall be applied to or placed on the land within eight hours after being discharged from the pathogen treatment process.

# C. Monitoring Requirements

Toxicity Characteristic Leaching Procedure - once during the term of this permit (TCLP) Test
PCBs - once during the term of this permit

All metal constituents and fecal coliform or <u>Salmonella</u> sp. bacteria shall be monitored at the appropriate frequency shown below, pursuant to 30 TAC § 312.46(a)(1):

Amount of sewage sludge (*) metric tons per 365-day period	Monitoring Frequency
o to less than 290	Once/Year
290 to less than 1,500	Once/Quarter
1,500 to less than 15,000	Once/Two Months
15,000 or greater	Once/Month

(*) The amount of bulk sewage sludge applied to the land (dry wt. basis).

Representative samples of sewage sludge shall be collected and analyzed in accordance with the methods referenced in 30 TAC § 312.7

#### SECTION II.

REQUIREMENTS SPECIFIC TO BULK SEWAGE SLUDGE FOR APPLICATION TO THE LAND MEETING CLASS A, CLASS AB or B PATHOGEN REDUCTION AND THE CUMULATIVE LOADING RATES IN TABLE 2, OR CLASS B PATHOGEN REDUCTION AND THE POLLUTANT CONCENTRATIONS IN TABLE 3

For those permittees meeting Class A, Class AB or B pathogen reduction requirements and that meet the cumulative loading rates in Table 2 below, or the Class B pathogen reduction requirements and contain concentrations of pollutants below listed in Table 3, the following conditions apply:

# A. Pollutant Limits

#### Table 2

	Cumulative Pollutant Loading Rate
D 11	
<u>Pollutant</u>	(pounds per acre)*
Arsenic	36
Cadmium	35
Chromium	2677
Copper	1339
Lead	268
Mercury	15
Molybdenum	Report Only
Nickel	375
Selenium	89
Zinc	2500

# Table 3

	Monthly Average	
	Concentration	
<u>Pollutant</u>	( <u>milligrams per kilogra</u>	<u>n</u> )*
Arsenic	41	
Cadmium	39	
Chromium	1200	
Copper	1500	
Lead	300	
Mercury	17	
Molybdenum	Report Only	
Nickel	420	
Selenium	36	
Zinc	2800	
	*Dry weight basis	

# **B.** Pathogen Control

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, a reclamation site, shall be treated by either Class A, Class AB or Class B pathogen reduction requirements as defined above in Section I.B.3.

# C. Management Practices

- 1. Bulk sewage sludge shall not be applied to agricultural land, forest, a public contact site, or a reclamation site that is flooded, frozen, or snow-covered so that the bulk sewage sludge enters a wetland or other waters in the State.
- 2. Bulk sewage sludge not meeting Class A requirements shall be land applied in a manner which complies with Applicability in accordance with 30 TAC §312.41 and the Management Requirements in accordance with 30 TAC § 312.44.
- 3. Bulk sewage sludge shall be applied at or below the agronomic rate of the cover crop.
- 4. An information sheet shall be provided to the person who receives bulk sewage sludge sold or given away. The information sheet shall contain the following information:
  - a. The name and address of the person who prepared the sewage sludge that is sold or given away in a bag or other container for application to the land.
  - b. A statement that application of the sewage sludge to the land is prohibited except in accordance with the instruction on the label or information sheet.
  - c. The annual whole sludge application rate for the sewage sludge application rate for the sewage sludge that does not cause any of the cumulative pollutant loading rates in Table 2 above to be exceeded, unless the pollutant concentrations in Table 3 found in Section II above are met.

# **D.** Notification Requirements

- 1. If bulk sewage sludge is applied to land in a State other than Texas, written notice shall be provided prior to the initial land application to the permitting authority for the State in which the bulk sewage sludge is proposed to be applied. The notice shall include:
  - a. The location, by street address, and specific latitude and longitude, of each land application site.
  - b. The approximate time period bulk sewage sludge will be applied to the site.
  - c. The name, address, telephone number, and National Pollutant Discharge Elimination System permit number (if appropriate) for the person who will apply the bulk sewage sludge.
- 2. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.

#### E. Record keeping Requirements

The sludge documents will be retained at the facility site and/or shall be readily available for review by a TCEQ representative. The person who prepares bulk sewage sludge or a sewage sludge material shall develop the following information and shall retain the information at

the facility site and/or shall be readily available for review by a TCEQ representative for a period of <u>five years</u>. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply.

- 1. The concentration (mg/kg) in the sludge of each pollutant listed in Table 3 above and the applicable pollutant concentration criteria (mg/kg), or the applicable cumulative pollutant loading rate and the applicable cumulative pollutant loading rate limit (lbs/ac) listed in Table 2 above.
- 2. A description of how the pathogen reduction requirements are met (including site restrictions for Class AB and Class B sludge, if applicable).
- 3. A description of how the vector attraction reduction requirements are met.
- 4. A description of how the management practices listed above in Section II.C are being met.
- 5. The following certification statement:
  - "I certify, under penalty of law, that the applicable pathogen requirements in 30 TAC § 312.82(a) or (b) and the vector attraction reduction requirements in 30 TAC § 312.83(b) have been met for each site on which bulk sewage sludge is applied. This determination has been made under my direction and supervision in accordance with the system designed to ensure that qualified personnel properly gather and evaluate the information used to determine that the management practices have been met. I am aware that there are significant penalties for false certification including fine and imprisonment."
- 6. The recommended agronomic loading rate from the references listed in Section II.C.3. above, as well as the actual agronomic loading rate shall be retained. The person who applies bulk sewage sludge or a sewage sludge material shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative indefinitely. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply:
  - a. A certification statement that all applicable requirements (specifically listed) have been met, and that the permittee understands that there are significant penalties for false certification including fine and imprisonment. See 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii), as applicable, and to the permittee's specific sludge treatment activities.
  - b. The location, by street address, and specific latitude and longitude, of each site on which sludge is applied.
  - c. The number of acres in each site on which bulk sludge is applied.
  - d. The date and time sludge is applied to each site.

- e. The cumulative amount of each pollutant in pounds/acre listed in Table 2 applied to each site.
- f. The total amount of sludge applied to each site in dry tons.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

#### F. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 13) and Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division, by September 30th of each year the following information:

- 1. Results of tests performed for pollutants found in either Table 2 or 3 as appropriate for the permittee's land application practices.
- 2. The frequency of monitoring listed in Section I.C. that applies to the permittee.
- 3. Toxicity Characteristic Leaching Procedure (TCLP) results.
- 4. Identity of hauler(s) and TCEQ transporter number.
- 5. PCB concentration in sludge in mg/kg.
- 6. Date(s) of disposal.
- 7. Owner of disposal site(s).
- 8. Texas Commission on Environmental Quality registration number, if applicable.
- 9. Amount of sludge disposal dry weight (lbs/acre) at each disposal site.
- 10. The concentration (mg/kg) in the sludge of each pollutant listed in Table 1 (defined as a monthly average) as well as the applicable pollutant concentration criteria (mg/kg) listed in Table 3 above, or the applicable pollutant loading rate limit (lbs/acre) listed in Table 2 above if it exceeds 90% of the limit.
- 11. Level of pathogen reduction achieved (Class A, Class AB or Class B).
- 12. Alternative used as listed in Section I.B.3.(a. or b.). Alternatives describe how the pathogen reduction requirements are met. If Class B sludge, include information on how site restrictions were met.
- 13. Vector attraction reduction alternative used as listed in Section I.B.4.
- 14. Annual sludge production in dry tons/year.
- 15. Amount of sludge land applied in dry tons/year.
- 16. The certification statement listed in either 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii) as applicable to the permittee's sludge treatment activities, shall be attached to the annual reporting form.

- 17. When the amount of any pollutant applied to the land exceeds 90% of the cumulative pollutant loading rate for that pollutant, as described in Table 2, the permittee shall report the following information as an attachment to the annual reporting form.
  - a. The location, by street address, and specific latitude and longitude.
  - b. The number of acres in each site on which bulk sewage sludge is applied.
  - c. The date and time bulk sewage sludge is applied to each site.
  - d. The cumulative amount of each pollutant (i.e., pounds/acre) listed in Table 2 in the bulk sewage sludge applied to each site.
  - e. The amount of sewage sludge (i.e., dry tons) applied to each site.

The above records shall be maintained on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

# SECTION III. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE DISPOSED IN A MUNICIPAL SOLID WASTE LANDFILL

- A. The permittee shall handle and dispose of sewage sludge in accordance with 30 TAC § 330 and all other applicable state and federal regulations to protect public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present. The permittee shall ensure that the sewage sludge meets the requirements in 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- B. If the permittee generates sewage sludge and supplies that sewage sludge to the owner or operator of a municipal solid waste landfill (MSWLF) for disposal, the permittee shall provide to the owner or operator of the MSWLF appropriate information needed to be in compliance with the provisions of this permit.
- C. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.
- D. Sewage sludge shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I (Toxicity Characteristic Leaching Procedure) or other method, which receives the prior approval of the TCEQ for contaminants listed in Table 1 of 40 CFR § 261.24. Sewage sludge failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal.

Following failure of any TCLP test, the management or disposal of sewage sludge at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division and the Regional Director (MC Region 13) of the appropriate TCEQ field office within 7 days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Registration, Review, and Reporting Division (MC 129), Texas Commission on Environmental Quality, P. O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 13) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30th of each year.

- E. Sewage sludge shall be tested as needed, in accordance with the requirements of 30 TAC § 330.
- F. Record keeping Requirements

The permittee shall develop the following information and shall retain the information for five years.

- 1. The description (including procedures followed and the results) of all liquid Paint Filter Tests performed.
- 2. The description (including procedures followed and results) of all TCLP tests performed.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

#### G. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 13) and Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30th of each year the following information:

- 1. Toxicity Characteristic Leaching Procedure (TCLP) results.
- 2. Annual sludge production in dry tons/year.
- 3. Amount of sludge disposed in a municipal solid waste landfill in dry tons/year.
- 4. Amount of sludge transported interstate in dry tons/year.
- 5. A certification that the sewage sludge meets the requirements of 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- 6. Identity of hauler(s) and transporter registration number.
- 7. Owner of disposal site(s).
- 8. Location of disposal site(s).
- 9. Date(s) of disposal.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

# SECTION IV. REQUIREMENTS APPLYING TO SLUDGE TRANSPORTED TO ANOTHER FACILITY FOR FURTHER PROCESSING

These provisions apply to sludge that is transported to another wastewater treatment facility or facility that further processes sludge. These provisions are intended to allow transport of sludge to facilities that have been authorized to accept sludge. These provisions do not limit the ability of the receiving facility to determine whether to accept the sludge, nor do they limit the ability of the receiving facility to request additional testing or documentation.

# A. General Requirements

- 1. The permittee shall handle and dispose of sewage sludge in accordance with 30 TAC Chapter 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge.
- 2. Sludge may only be transported using a registered transporter or using an approved pipeline.

# **B.** Record Keeping Requirements

- 1. For sludge transported by an approved pipeline, the permittee must maintain records of the following:
  - a. the amount of sludge transported;
  - b. the date of transport;
  - c. the name and TCEQ permit number of the receiving facility or facilities;
  - d. the location of the receiving facility or facilities;
  - e. the name and TCEQ permit number of the facility that generated the waste; and
  - f. copy of the written agreement between the permittee and the receiving facility to accept sludge.
- 2. For sludge transported by a registered transporter, the permittee must maintain records of the completed trip tickets in accordance with 30 TAC § 312.145(a)(1)-(7) and amount of sludge transported.
- 3. The above records shall be maintained on-site on a monthly basis and shall be made available to the TCEQ upon request. These records shall be retained for at least five years.

# C. Reporting Requirements

The permittee shall report the following information annually to the TCEQ Regional Office (MC Region 13) and Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division, by September 30th of each year:

- 1. the annual sludge production;
- 2. the amount of sludge transported;
- 3. the owner of each receiving facility;
- 4. the location of each receiving facility; and
- 5. the date(s) of disposal at each receiving facility.

TCEQ Revision 2/2015

#### SPECIAL PROVISIONS:

- 1. This permit is granted subject to the policy of the Commission to encourage the development of areawide waste collection, treatment and disposal systems. The Commission reserves the right to amend this permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an areawide system, if an areawide system is developed; to require the delivery of the wastes authorized to be collected in, treated by, or discharged from the system, to an areawide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment, or disposal system.
- 2. The permittee shall employ or contract with one or more licensed wastewater treatment facility operators or wastewater system operations companies holding a valid license or registration according to the requirements of 30 TAC § 30, Occupational Licenses and Registrations and in particular 30 TAC § 30, Subchapter J, Wastewater Operators and Operations Companies.
  - This Category D facility must be operated by a chief operator or an operator holding a Category D license or higher. The facility must be operated a minimum of five days per week by the licensed chief operator or an operator holding the required level of license or higher. The licensed chief operator or operator holding the required level of license or higher must be available by telephone or pager seven days per week. Where shift operation of the wastewater treatment facility is necessary, each shift which does not have the on-site supervision of the licensed chief operator must be supervised by an operator in charge who is licensed not less than one level below the category for the facility.
- 3. The permittee shall maintain and operate the treatment facility in order to achieve optimum efficiency of treatment capability. This shall include required monitoring of effluent flow and quality as well as appropriate grounds and building maintenance.
- 4. Irrigation practices shall be designed and managed so as to prevent ponding of effluent or contamination of ground and surface waters and to prevent the occurrence of nuisance conditions in the area. Tailwater control facilities shall be provided as necessary to prevent the discharge of any effluent from the irrigated land.
- 5. Waste water shall not be applied for irrigation during rainfall events or when the ground is frozen or saturated.
- 6. Application rates to the irrigated land shall not exceed 2.93 acre-feet per year per acre irrigated. The permittee is responsible for providing equipment to determine application rates and maintaining accurate records of the volume of effluent applied. These records shall be made available for review by the Texas Commission on Environmental Quality and shall be maintained for at least three years.
- 7. Holding ponds shall conform to the Texas Commission on Environmental Quality "Design Criteria for Sewerage Systems" requirement for stabilization ponds with regard to construction and levee design, and a minimum of 2 feet of freeboard shall be maintained.

8. The permittee shall obtain representative soil samples from the root zones of the land application area receiving wastewater. Composite sampling techniques shall be used. Each composite sample shall represent no more than 42 acres subsamples representing each composite sample. Subsamples shall be composited by like sampling depth and soil type for analysis and reporting. Soil types are soils that have like topsoil or plow layer textures. These soils shall be sampled individually from 0 to 6 inches, 6 inches to 18 inches and 18 inches to 30 inches below ground level. The permittee shall sample and analyze soils in September of each year. Soil samples shall be analyzed within 30 days of sample procurement.

The permittee shall provide annual soil analyses of the land application area according to the following table:

Parameter	Method	Minimum Analytical Level (MAL)	Reporting units
рН	2:1 (v/v) water to soil mixture		Reported to 0.1 pH units after calibration of pH meter
Electrical Conductivity	2:1 (v/v) water to soil mixture	0.01	dS/m (same as mmho/cm)
Nitrate- nitrogen Ammonium- nitrogen	From a 1 <u>N</u> KCl soil extract	1	mg/kg (dry weight basis)
Total Kjeldahl Nitrogen (TKN)	For determination of Organic plus Ammonium Nitrogen. Procedures that use Mercury (Hg) are not acceptable.	20	mg/kg (dry weight basis)
Total Nitrogen	= TKN + nitrate-nitrogen (same as, organic-nitrogen + ammonium-nitrogen + nitrate-nitrogen)		mg/kg (dry weight basis)
Plant- available: Phosphorus	Mehlich III with inductively coupled plasma	1	mg/kg (dry weight basis)
Plant- available: Potassium	May be determined in the same Mehlich III extract with inductively coupled plasma	5 (K)	mg/kg (dry weight basis)
Amendment addition, e.g., gypsum	Recommendation from analytical laboratory		Report in <i>short</i> tons/acre in the year effected

The permittee shall provide a copy of this plan to the analytical laboratory prior to sample


analysis. The permittee shall submit the results of the annual soil sample analyses with copies of the laboratory reports and a map depicting the areas that have received wastewater within the permanent land application fields to the TCEQ Regional Office (MC Region 13) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division no later than end of September following the sampling date of each year. If wastewater is not applied in a particular year, the permittee shall notify the same TCEQ offices and indicate that wastewater and/or sludge has not been applied on the approved land disposal sites during that year.

- 9. The permittee shall maintain a long term contract with the owner(s) of the land application site which is authorized for use in this permit, or own the land authorized for land application of treated effluent.
- 10. The permittee shall erect adequate signs stating that the irrigation water is from a non-potable water supply for any area where treated effluent is stored or where there exist hose bibs or faucets. Signs shall consist of a red slash superimposed over the international symbol for drinking water accompanied by the message "DO NOT DRINK THE WATER" in both English and Spanish. All piping transporting the effluent shall be clearly marked with these same signs.
- 11. Spray fixtures for the irrigation system shall be of such design that they cannot be operated by unauthorized personnel.
- 12. Irrigation with effluent shall be accomplished only when the area specified is not in use.
- 13. Permanent transmission lines shall be installed from the holding pond to each tract of the land to be irrigated utilizing effluent from that pond
- 14. Facilities for the retention or storage of treated or untreated wastewater shall be adequately lined to control seepage. The following methods of pond lining are acceptable.
  - a. In-situ clay soils or placed and compacted clay soils meeting the following requirements:
    - 1) More than 30% passing a No. 200 mesh sieve
    - 2) Liquid limit greater than 30%
    - 3) Plasticity index greater than 15%
    - 4) A minimum thickness of 2 feet
    - 5) Permeability equal to or less than 1x10⁻⁷ cm/sec (*)
    - 6) Soil compaction will be 95% standard proctor at optimum moisture content (*)
      - (*) For new and/or modified ponds only
  - b. Membrane lining with a minimum thickness of 20 mils, and an underdrain leak detection system.
  - c. An alternate method of pond lining may be utilized with prior approval from the Executive Director.

The permittee submitted certification by a Texas Licensed Professional Engineer that the completed pond lining meets the appropriate above criteria. A copy of the certification is on the file.

- 15. By ownership, the permittee shall maintain a minimum buffer zone of 500 feet from lagoons with zones of anaerobic activity (e.g. facultative lagoons) and 150 feet from all other wastewater treatment plant structures or process units, excluding lift stations, to the nearest property.
- 16. The permittee shall comply with the requirements of 30 TAC § 309.13(a) through (d). In addition, by ownership of the required buffer zone area, the permittee shall comply with the requirements of 30 TAC § 309.13(e).
- 17. The permittee shall provide facilities for the protection of its wastewater treatment facility from a 100-year flood.

# ATTACHMENT A SITE MAP



# TECHNICAL SUMMARY AND EXECUTIVE DIRECTOR'S PRELIMINARY DECISION

#### DESCRIPTION OF APPLICATION

Applicant: City of Runge

TCEQ Permit No. WQ0010266001

Regulated Activity: Domestic Wastewater Permit

Type of Application: Renewal

Request: Renewal with no changes

Authority: Texas Water Code (TWC) § 26.027; 30 Texas Administrative

Code (TAC) Chapters 305, 309, 312, 319, and 30; and

Commission policies.

#### EXECUTIVE DIRECTOR RECOMMENDATION

The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The draft permit includes an expiration date of **ten years from the date of issuance**, according to 30 TAC Section 305.127(1)(C)(ii)(III), Conditions to be Determined for Individual Permits.

# REASON FOR PROJECT PROPOSED

The City of Runge has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of Permit No. WQ0010266001 to authorize the disposal of treated domestic wastewater at a daily average flow not to exceed 0.110 million gallons per day (MGD) via surface irrigation of 42 acres of non-public access agricultural land. The facility includes a storage pond with a total surface area of 2.21 acres and total capacity of 13.02 acre-feet for storage of treated effluent prior to irrigation. The existing wastewater treatment facility serves the City of Runge.

#### PROJECT DESCRIPTION AND LOCATION

The City of Runge Wastewater Treatment Facility consists of a primary settling pnd system. Treatment units include a bar screen and a facultative lagoon with a surface area of 1.0 acre and volume of 10.1 acre-feet. The facility is in operation.

The facility is a pond system and sludge from the ponds has not been removed for sludge disposal to date. The draft permit authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

The wastewater treatment facility and disposal site are located approximately 2,300 feet south and 1,600 feet eaast fo the intersection of U.S.highway 81 and U.S. Highway 71, in the City of Runge in Karnes County, Texas 78151. The wastewater treatment facility and disposal site are located in the drainage basin of Lower San Antonio River in Segment No. 1901 of the San Antonio River Basin. No discharge of pollutants into water in the state is authorized by this

City of Runge Permit No. WQ0010266001 Statement of Basis/Technical Summary and Executive Director's Preliminary Decision

permit.

#### SUMMARY OF EFFLUENT DATA

The following is a summary of the applicant's effluent monitoring data for the period June 2022 to October 2024. The average of Daily Average value is computed by averaging of all 30-day average values for the reporting period for each parameter: flow and five-day biochemical oxygen demand ( $BOD_5$ ).

<u>Parameter</u> <u>Average of Daily Average</u>

Flow, MGD 0.038 BOD₅, mg/l 34

#### DRAFT PERMIT CONDITIONS

The draft permit authorizes the disposal of treated domestic wastewater effluent at a daily average flow not to exceed 0.110 MGD via surface irrigation of 42 acres of non-public access agricultural land. Treatment units include a facultative lagoon with a surface area of 1.01 acres and an effluent storage pond wiith a capacity of 13.02 acre-feet. Application rates to the irrigated land shall not exceed 2.93 acre-feet per year per acre irrigated. The irrigated crops include non-public access agricultural land consisting of Coastal Bermuda grass, Winter Rye grass (cool season) or Wild Clover (cool season).

The effluent limitation in the draft permit, based on a single grab, is 100 mg/l biochemical oxygen demand (BOD₅).

The draft permit includes Sludge Provisions according to the requirements of 30 TAC Chapter 312, Sludge Use, Disposal, and Transportation. The draft permit authorizes the disposal of sludge at a TCEQ authorized land application site or co-disposal landfill.

# **SUMMARY OF CHANGES FROM APPLICATION**

None.

# SUMMARY OF CHANGES FROM EXISTING PERMIT

Special provisions 4, 8, 10 and 14 have been revised. Special provisions 15-17 in the existing permit were renumbered to 19-21 to allow for the addition of special provisions now numbered as 15-18 for additional geologic requirements. Special provisions 22 and 23 were added for additional agronomic requirements.

Certain accidental discharges or spills of treated or untreated wastewater from wastewater treatment facilities or collection systems owned or operated by a local government may be reported on a monthly basis in accordance with 30 TAC § 305.132.

The draft permit includes all updates based on the 30 TAC 312 rule change effective April 23, 2020.

City of Runge Permit No. WQ0010266001 Statement of Basis/Technical Summary and Executive Director's Preliminary Decision

#### BASIS FOR DRAFT PERMIT

The following items were considered in developing the draft permit:

- 1. Application received on Febuary 14, 2025, and additional information received on August 5, 2025.
- 2. Existing TCEQ permit: Permit No. WQ0010266001 issued on September 4, 2015.
- 3. Interoffice Memorandum from the Water Quality Assessment Team, Water Quality Assessment & Standards Section, Water Quality Division.

#### PROCEDURES FOR FINAL DECISION

When an application is declared administratively complete, the Chief Clerk sends a letter to the applicant advising the applicant to publish the Notice of Receipt of Application and Intent to Obtain Permit in the newspaper. In addition, the Chief Clerk instructs the applicant to place a copy of the application in a public place for review and copying in the county where the facility is or will be located. This application will be in a public place throughout the comment period. The Chief Clerk also mails this notice to any interested persons and, if required, to landowners identified in the permit application. This notice informs the public about the application and provides that an interested person may file comments on the application or request a contested case hearing or a public meeting.

Once a draft permit is completed, it is sent, along with the Executive Director's preliminary decision, as contained in the technical summary or fact sheet, to the Chief Clerk. At that time, the Notice of Application and Preliminary Decision will be mailed to the same people and published in the same newspaper as the prior notice. This notice sets a deadline for making public comments. The applicant must place a copy of the Executive Director's preliminary decision and draft permit in the public place with the application.

Any interested person may request a public meeting on the application until the deadline for filing public comments. A public meeting is intended for the taking of public comment and is not a contested case proceeding.

After the public comment deadline, the Executive Director prepares a response to all significant public comments on the application or the draft permit raised during the public comment period. The Chief Clerk then mails the Executive Director's response to comments and final decision to people who have filed comments, requested a contested case hearing, or requested to be on the mailing list. This notice provides that if a person is not satisfied with the Executive Director's response and decision, they can request a contested case hearing or file a request to reconsider the Executive Director's decision within 30 days after the notice is mailed.

The Executive Director will issue the permit unless a written hearing request or request for reconsideration is filed within 30 days after the Executive Director's response to comments and final decision is mailed. If a hearing request or request for reconsideration is filed, the Executive Director will not issue the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting. If a contested case hearing is held, it will be a legal proceeding similar to a civil trial in state district court.

City of Runge Permit No. WQ0010266001 Statement of Basis/Technical Summary and Executive Director's Preliminary Decision

If the Executive Director calls a public meeting or the Commission grants a contested case hearing as described above, the Commission will give notice of the date, time, and place of the meeting or hearing. If a hearing request or request for reconsideration is made, the Commission will consider all public comments in making its decision and shall either adopt the Executive Director's response to public comments or prepare its own response.

For additional information about this application, contact Chris Graf, P.E. at (512) 239-4541.

Chris Graf
Chris Graf, P.E.
Municipal Permits Team
Wastewater Permitting Section (MC 148)

August 6, 2025

Date