

This file contains the following documents:

- 1. Summary of application (in plain language)
 - English
 - Alternative Language (Spanish)
- 2. First notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
 - English
 - Alternative Language (Spanish)
- 3. Second notice (NAPD-Notice of Preliminary Decision)
 - English
 - Alternative Language (Spanish)
- 4. Application materials
- 5. Draft permit
- 6. Technical summary or fact sheet



Este archivo contiene los siguientes documentos:

- 1. Resumen de la solicitud (en lenguaje sencillo)
 - Inglés
 - Idioma alternativo (español)
- 2. Primer aviso (NORI, Aviso de Recepción de Solicitud e Intención de Obtener un Permiso)
 - Inglés
 - Idioma alternativo (español)
- 3. Segundo aviso (NAPD, Aviso de Decisión Preliminar)
 - Inglés
 - Idioma alternativo (español)
- 4. Materiales de la solicitud
- 5. Proyecto de permiso
- 6. Resumen técnico u hoja de datos

TCEQ

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

PLAIN LANGUAGE SUMMARY FOR TPDES OR TLAP PERMIT APPLICATIONS

Plain Language Summary Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary as required by <u>Title 30, Texas Administrative Code (30 TAC), Chapter 39, Subchapter H</u>. Applicants may modify the template as necessary to accurately describe their facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how the applicant will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements.

If you are subject to the alternative language notice requirements in 30 TAC Section 39.426, you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package. For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS DOMESTIC WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Hays County MUD No. 4 (C6026906612) operates Hays County MUD No. 4 Wastewater Treatment Plant (RN103897567), a public wastewater treatment facility. The facility is located at Ledge Stone subdivision, in Austin, Hays County, Texas 78737. This application will apply for the renewal of the existing permit for land application of treated wastewater effluent onto defined areas within the district's boundaries. This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are expected to contain no significant amount of pollutants. Wastewater is discharged in the form of treated effluent for irrigation or stored in a sludge dewatering box and hauled to a license facility and is treated by aeration, clarification, chlorination and chlorine contact.

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

AGUAS RESIDUALES Introduzca 'INDUSTRIALES' o 'DOMÉSTICAS' aquí /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

Hays County MUD No. 4 (C6026906612)) opera la Planta de Tratamiento de Aguas Residuales Hays County MUD No. 4 RN103897567), una instalación pública de tratamiento de aguas residuales. La instalación está ubicada en la subdivisión Ledge Stone, en Austin, Condado de Hays, Texas 78737. Esta solicitud se aplicará para la renovación del permiso existente para la aplicación de tierra del efluente de aguas residuales tratadas en áreas definidas dentro de los límites del distrito.. Este permiso no autorizará una descarga de contaminantes en el agua en el estado.

Se espera que las descargas de la instalación contengan se espera que no contenga una cantidad significativa de contaminantes. Las aguas residuales se descargan en forma de efluente. está tratado por riego o se almacenan en una caja de deshidratación de lodos y se transportan a una instalación con licencia y se tratan mediante aireación, clarificación, cloración y contacto con cloro.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT RENEWAL

PERMIT NO. WQ0014309001

APPLICATION. Hays County Municipal Utility District No. 4, 600 West 5th Street, Suite 900, Austin, Texas 78701, has applied to the Texas Commission on Environmental Quality (TCEQ) to renew Texas Land Application Permit (TLAP) No. WQ0014309001 to authorize the disposal of treated wastewater at a volume not to exceed a daily average flow of 150,000 gallons per day via: subsurface area drip dispersal irrigation of 34.44 acres of land. The domestic wastewater treatment facility and disposal area are located approximately 608 feet north and 2,950 feet west of the intersection of Nutty Brown Road and U.S. Highway 290, in the city of Dripping Springs, in Hays County, Texas 78737. TCEQ received this application on August 29, 2024. The permit application will be available for viewing and copying at Dripping Springs City Hall, 511 Mercer Street, Dripping Springs, in Hays County, Texas prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.98279,30.210416&level=18

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. El aviso de idioma alternativo en español está disponible en https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. Notice of the Application and Preliminary Decision will be published and mailed to those who are on the countywide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.

TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at https://www14.tceq.texas.gov/epic/eComment/, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105,

P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from Hays County Municipal Utility District No. 4 at the address stated above or by calling Mr. Jacob Valentien, P.E., Senior Project Manager, Westwood Professional Services, at 512-485-0831.

Issuance Date: November 15, 2024

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE RECIBO DE LA SOLICITUD Y EL INTENTO DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA RENOVACION

PERMISO NO. WQ0014309001

SOLICITUD. Hays County Municipal Utility District No. 4, 600 West 5th Street, Suite 900, Austin, Texas 78701, ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para el propuesto Permiso No. WQ0014309001 de disposición de aguas residuales] para autorizar la disposición de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 150,000 galones por día por medio de irrigación por goteo de dispersión en área subsuperficial de 34.44 acres de tierra. La planta de tratamiento de aguas domésticos residuales y el área de disposición están ubicados en aproximadamente 608 pies al norte y 2950 pies al oeste de la intersección de la US 290 y Nutty Brown Road en el Condado de Hays, Texas. La TCEQ recibió esta solicitud el día agosto 29, 2024. La solicitud para el permiso está disponible para leer y copiar en Dripping Springs City Hall, 511 Mercer Street, Dripping Springs, en Hays County, Texas. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.98279,30.210416&level=18

AVISO ADICIONAL. El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. El aviso de la solicitud y la decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud. El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO.

Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro: identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

CONTACTOS E INFORMACIÓN DE LA TCEQ. Todos los comentarios escritos del

público y los para pedidos una reunión deben ser presentados a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 o por el internet at www.tceq.texas.gov/about/comments.html. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Si necesita más información en Español sobre esta solicitud para un permiso o el proceso del permiso, por favor llame a El Programa de Educación Pública de la TCEQ, sin cobro, al 1-800-687-4040. La información general sobre la TCEQ puede ser encontrada en nuestro sitio de la red: www.tceq.texas.gov.

También se puede obtener información adicional del Hays County Municipal Utility District No. 4 a la dirección indicada arriba o llamando a Westwood Professional Services al (512) 485-0831.

Fecha de emission: 15 de noviembre de 2024

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



COMBINED

NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT (NORI)

AND

NOTICE OF APPLICATION AND PRELIMINARY DECISION FOR WATER QUALITY LAND APPLICATION PERMIT FOR MUNICIPAL WASTEWATER

RENEWAL

PERMIT NO. WQ0014309001

APPLICATION AND PRELIMINARY DECISION. Hays County Municipal Utility District No. 4, 1715 S. Capital of Texas HWY., Suite 150D, Austin, Texas 78746, has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of TCEQ Permit No. WQ0014309001 which authorizes the disposal of treated domestic wastewater at a daily average flow not to exceed 150,000 gallons per day via public access subsurface area drip dispersal system with a minimum area of 34.44 acres. This permit will not authorize a discharge of pollutants into waters in the State. TCEQ received this application on August 29, 2024.

This combined notice is being issued to change the applicant's mailing address from what was stated in the NORI.

The wastewater treatment facility and disposal site are located approximately 608 feet north and 2,950 feet west of the intersection of Nutty Brown Road and U.S. Highway 290, in the City of Dripping Springs, Hays County, Texas 78737. The wastewater treatment facility and disposal site are located in the drainage basin of Barton Creek in Segment No. 1430 of the Colorado River Basin. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For exact location, refer to application. https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.98277,30.210277&level=18

The TCEQ Executive Director has completed the technical review of the application and prepared a draft permit. The draft permit, if approved, would establish the conditions under which the facility must operate. The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The permit application, Executive Director's preliminary decision, and draft permit are available for viewing and copying at Dripping Springs City Hall, 511 Mercer Street, Dripping Springs, in Hays County, Texas. The application, including any updates, and associated notices are available electronically at the following webpage: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at https://www.tceq.texas.gov/permitting/wastewater/plain-language-summaries-and-public-notices.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting about this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ holds a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting a contested case hearing or reconsideration of the Executive Director's decision. A contested case hearing is a legal proceeding similar to a civil trial in a state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period; and the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period. TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

EXECUTIVE DIRECTOR ACTION. The Executive Director may issue final approval of the application unless a timely contested case hearing request or request for reconsideration is filed. If a timely hearing request or request for reconsideration is filed, the Executive Director will not issue final approval of the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

All written public comments and public meeting requests must be submitted to the Office of the Chief Clerk, MC 105, Texas Commission on Environmental Quality, P.O. Box 13087, Austin, TX 78711-3087 or electronically at www.tceq.texas.gov/goto/comment within 30 days from the date of newspaper publication of this notice.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. Public comments and requests must be submitted either electronically at www.tceq.texas.gov/goto/comment, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC 105, P.O. Box 13087, Austin, Texas 78711-3087. Any personal information you submit to the TCEQ will become part of the agency's record; this includes email addresses. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from Hays County Municipal Utility District No. 4 at the address stated above or by calling Mr. Jacob Valentien, P.E., Senior Project Manager, Westwood Professional Services at 512-485-0831.

Issuance Date: August 28, 2025

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE RECIBO DE LA SOLICITUD E INTENCION DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA RENOVACION

 \mathbf{E}

AVISO DE RECIBO DE LA SOLICITUD E INTENCION DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA

RENOVACION

PERMISO PROPUESTO NO. WQoo14309001

SOLICITUD. Hays County Municipal Utility District No. 4, 1715 S. Capital of Texas Hwy., Suite 105D, Austin, Texas 78746, ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para el propuesto Permiso No.WQ0014309001 de disposición de aguas residuales] para autorizar la disposición de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 150,000 galones por día por medio de irrigación por goteo de dispersión en área subsuperficial de 34.44 acres de tierra. Este permiso no autorizará una descarga de contaminantes a las aguas del estado. La TCEQ recibió esta solicitud el día agosto 29, 2024.

Esta combinación de avisos se emite para cambiar la dirección de correo declarada en el Aviso de Recibo de la Solicitud e Intención de Obtener Permiso para la Calidad del Agua Renovación

La planta de tratamiento de aguas domésticos residuales y el área de disposición están ubicados en aproximadamente 608 pies al norte y 2950 pies al oeste de la intersección de la US 290 y Nutty Brown Road, en el Condado de Hays, Texas. La planta y el sitio de disposición están ubicados en la cuenca de drenaje de Barton Creek en el Segmento No. 1430 de la Cuenca del Río Colorado. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud. https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.98279,30.210416&level=18

El Director Ejecutivo de la TCEQ ha completado la revisión técnica de la solicitud y ha preparado un borrador del permiso. El borrador del permiso, si es aprobado, establecería las condiciones bajo las cuales la instalación debe operar. El Director Ejecutivo ha tomado una decisión preliminar que si este permiso es emitido, cumple con todos los requisitos normativos y legales. La solicitud del permiso, la decisión preliminar del Director Ejecutivo y el borrador del permiso están disponibles para leer y copiar en Dripping Springs City Hall, 511 Mercer Street, Dripping Springs, en Hays County, Texas. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web: https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications

AVISO DE IDIOMA ALTERNATIVO. El aviso de idioma alternativo en español está disponible en https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud. El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO.

Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión.

La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

ACCIÓN DEL DIRECTOR EJECUTIVO. El Director Ejecutivo puede emitir una aprobación final de la solicitud a menos que exista un pedido antes del plazo de vencimiento de una audiencia administrativa de lo contencioso o se ha presentado un pedido de reconsideración. Si un pedido ha llegado antes del plazo de vencimiento de la audiencia o el pedido de reconsideración ha sido presentado, el Director Ejecutivo no emitirá una aprobación final sobre el permiso y enviará la solicitud y el pedido a los Comisionados de la TECQ para consideración en una reunión programada de la Comisión.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

Todos los comentarios escritos del público y los pedidos una reunión deben ser presentados durante los 30 días después de la publicación del aviso a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 or por el internet a www.tceq.texas.gov/about/comments.html.

INFORMACIÓN DISPONIBLE EN LÍNEA. Para detalles sobre el estado de la solicitud, favor de visitar la Base de Datos Integrada de los Comisionados en www.tceq.texas.gov/goto/cid. Para buscar en la base de datos, utilizar el número de permiso para esta solicitud que aparece en la parte superior de este aviso.

CONTACTOS E INFORMACIÓN DE LA TCEQ. Todos los comentarios escritos del público y los para pedidos una reunión deben ser presentados a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 o por el internet at www.tceq.texas.gov/about/comments.html. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Si necesita más información en Español sobre esta solicitud para un permiso o el proceso del permiso, por favor llame a El Programa de Educación Pública de la TCEQ, sin cobro, al 1-800-687-4040. La información general sobre la TCEQ puede ser encontrada en nuestro sitio de la red: www.tceq.texas.gov.

También se puede obtener información adicional del Hays County Municipal Utility District No. 4 a la dirección indicada arriba o llamando a Westwood Professional Services al (512) 485-0831.

Fecha de emission: el día agosto 28, 2025

August 28, 2024

Project No.: R0052766.00

Texas Commission on Environmental Quality Water Quality Division

Applications Review and Processing Team (MC 148) Building F, Room 2101 12100 Park 35 Circle Austin, Texas 78753

Texas Commission on Environmental Quality Water Quality Division

Applications Review and Processing Team (MC 148) PO Box 13087 Austin, Texas 78711-3087

Re: TCEQ PERMIT RENEWAL APPLICATION

TCEQ Permit Number WQ0014309001 Westwood Job Number: 0052766.00 – ID 08

Dear Review Team,

Westwood Professional Services has completed the above referenced permit renewal application for Hays County Municipal Utility District No. 4. Enclosed, please find the original completed form and three (3) copies. The application fee is being submitted under separate cover as requested.

The District understands that the current permit expiration date is September 1, 2024 and kindly request an administrative extension pending review of this permit renewal application.

The District does not represent that all land currently permitted for drip irrigation will be used for drip irrigation. The District is currently evaluating additional land within the District for use as permitted drip irrigation area, and intends to submit an application for a major amendment to include them and remove areas that will not be utilized at a later date. This application is to renew the current permit.

If you have questions concerning this application please contact me at (512) 485-0831.

Sincerely,

Jacob W. Valentien, P.E.

District Engineer

CC: Matt Kutac – Law Office of Matthew B. Kutac

Texas Commission on Environmental Quality Domestic Wastewater Permit Renewal Application for

Hays County MUD No. 4 Permit Number WQ0014309001

Hays County, Texas

Prepared for:

Hays County MUD No. 4
3321 Bee Caves Rd, Suite 203
Austin, TX, 78746

Prepared by:

Westwood Professional Services 8701 N Mopac Expy, Suite 320 Austin, TX, 78759

August 2024

Firm Registration No. F-11756 WW Job No: 0052766.00 – WW01

THE TONMENTAL OUR LEVEL OF THE TON THE

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST

Complete and submit this checklist with the application.

APPLICANT NAME:	Hays Count	y Municipal l	Utility Distric	t No. 4
		_	•	

PERMIT NUMBER (If new, leave blank): <u>WQ0014309001</u>

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0	\boxtimes		Original USGS Map	\boxtimes	
Administrative Report 1.1		\boxtimes	Affected Landowners Map		\boxtimes
SPIF		\boxtimes	Landowner Disk or Labels		\boxtimes
Core Data Form	\boxtimes		Buffer Zone Map		\boxtimes
Public Involvement Plan Form	\boxtimes		Flow Diagram	\boxtimes	
Technical Report 1.0	\boxtimes		Site Drawing	\boxtimes	
Technical Report 1.1		\boxtimes	Original Photographs		\boxtimes
Worksheet 2.0		\boxtimes	Design Calculations		\boxtimes
Worksheet 2.1		\boxtimes	Solids Management Plan		\boxtimes
Worksheet 3.0	\boxtimes		Water Balance		\boxtimes
Worksheet 3.1		\boxtimes			
Worksheet 3.2		\boxtimes			
Worksheet 3.3		\boxtimes			
Worksheet 4.0		\boxtimes			
Worksheet 5.0		\boxtimes			
Worksheet 6.0	\boxtimes				
Worksheet 7.0	\boxtimes				

For TCEQ Use Only	
Segment Number	•
Expiration Date	Region
Permit Number	

THE THE PARTY OF T

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

For any questions about this form, please contact the Applications Review and Processing Team at 512-239-4671.

Section 1. Application Fees (Instructions Page 26)

Indicate the amount submitted for the application fee (check only one).

Flow	New/Major Amendment	Renewal
<0.05 MGD	\$350.00 □	\$315.00 □
≥0.05 but <0.10 MGD	\$550.00 □	\$515.00 □
≥0.10 but <0.25 MGD	\$850.00	\$815.00 ⊠
≥0.25 but <0.50 MGD	\$1,250.00	\$1,215.00 □
≥0.50 but <1.0 MGD	\$1,650.00 □	\$1,615.00
≥1.0 MGD	\$2,050.00 □	\$2,015.00

Minor Amendment (for any flow) \$150.00 □

Pay	ment	Inform	nation [.]
Iay	<i>y</i> 1111 <i>C</i> 111 <i>U</i>	шиоги	เฉนบน

Mailed Check/Money Order Number: 205821

Check/Money Order Amount: \$815

Name Printed on Check: Westwood Professional Services, Inc.

EPAY Voucher Number: N/A

Copy of Payment Voucher enclosed? Yes \square

Section 2. Type of Application (Instructions Page 26)

a.	Che	ck the box next to the appropriate authorization type.
	\boxtimes	Publicly-Owned Domestic Wastewater

- ☐ Privately-Owned Domestic Wastewater
- ☐ Conventional Wastewater Treatment
- **b.** Check the box next to the appropriate facility status.
 - □ Inactive

C.	Che	eck the box next to the appropriate permit ty	pe.	
		TPDES Permit		
	\boxtimes	TLAP		
		TPDES Permit with TLAP component		
		Subsurface Area Drip Dispersal System (SA	DDS)	
d.	Che	eck the box next to the appropriate application	on typ	e
		New		
		Major Amendment with Renewal		Minor Amendment with Renewal
		Major Amendment without Renewal		Minor Amendment without Renewal
	\boxtimes	Renewal without changes		Minor Modification of permit
e.	For	amendments or modifications, describe the	propo	osed changes: <u>N/A</u>
f.	For	existing permits: <u>WQ0014309001</u>		
	EPA	A I.D. (TPDES only): TX <u>N/A</u>		
	Exp	oiration Date: 09/01/2024		

Section 3. Facility Owner (Applicant) and Co-Applicant Information (Instructions Page 26)

A. The owner of the facility must apply for the permit.

What is the Legal Name of the entity (applicant) applying for this permit?

Hays County Municipal Utility District No. 4

(The legal name must be spelled exactly as filed with the Texas Secretary of State, County, or in the legal documents forming the entity.)

If the applicant is currently a customer with the TCEQ, what is the Customer Number (CN)? You may search for your CN on the TCEQ website at http://www15.tceq.texas.gov/crpub/

CN: 602690661

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in *30 TAC § 305.44*.

Prefix: <u>Mr</u> Last Name, First Name: <u>McColloch, Craig</u>

Title: <u>Board President</u> Credential: <u>P.E</u>

B. Co-applicant information. Complete this section only if another person or entity is required to apply as a co-permittee.

What is the Legal Name of the co-applicant applying for this permit?

N/A

(The legal name must be spelled exactly as filed with the TX SOS, with the County, or in the legal documents forming the entity.)

If the co-applicant is currently a customer with the TCEQ, what is the Customer Number (CN)?

You may search for your CN on the TCEQ website at: http://www15.tceq.texas.gov/crpub/

CN: N/A

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in *30 TAC § 305.44*.

Prefix: <u>N/A</u> Last Name, First Name: <u>N/A</u>

Title: <u>N/A</u> Credential: <u>N/A</u>

Provide a brief description of the need for a co-permittee: N/A

C. Core Data Form

Complete the Core Data Form for each customer and include as an attachment. If the customer type selected on the Core Data Form is **Individual**, complete **Attachment 1** of Administrative Report 1.0. <u>Attachment: 1</u>

Section 4. Application Contact Information (Instructions Page 27)

This is the person(s) TCEQ will contact if additional information is needed about this application. Provide a contact for administrative questions and technical questions.

A. Prefix: Mr. Last Name, First Name: Valentien, Jacob

B. Title: <u>Senior Project Manager</u> Credential: <u>P.E</u>

Organization Name: Westwood Professional Services

Mailing Address: 8701 N Mopac Expressway, Suite 320 City, State, Zip Code: Austin, TX 78759

Phone No.: c E-mail Address: Jacob.valentien@westwoodps.com Check one or

both:

Administrative Contact

Technical Contact

C. Prefix: Mr. Last Name, First Name: Kutac, Matthew

Title: Attorney Credential: Click to enter text.

Organization Name: Law Office of Matthew B. Kutac

Mailing Address: 3321 Bee Caves Rd, Suite 203 City, State, Zip Code: Austin, TX 78746

Phone No.: 512-615-0503 E-mail Address: MKutac@mbkfirm.com

Check one or both: \square Administrative Contact \square Technical Contact

Section 5. Permit Contact Information (Instructions Page 27)

Provide the names and contact information for two individuals that can be contacted throughout the permit term.

A. Prefix: Mr. Last Name, First Name: Valentien, Jacob

Title: <u>Senior Project Manager</u> Credential: <u>P.E</u>
Organization Name: Westwood Professional Services

Mailing Address: 8701 N. Mopac Expressway Suite 320 City, State, Zip Code: Austin, TX, 78759

Phone No.: 512-485-0831 E-mail Address: Jacob.valentien@westwoodps.com

B. Prefix: Mr. Last Name, First Name: McColloch, Craig

Title: <u>Board President</u> Credential: <u>P.E.</u>

Organization Name: Hays County MUD No. 4

Mailing Address: 3321 Bee Caves Rd City, State, Zip Code: Austin, Texas 78746

Phone No.: <u>(512)</u> 615-0503 E-mail Address: <u>N/A</u>

Section 6. Billing Contact Information (Instructions Page 27)

The permittee is responsible for paying the annual fee. The annual fee will be assessed to permits *in effect on September 1 of each year*. The TCEQ will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (using form TCEQ-20029).

Prefix: Mrs. Last Name, First Name: Carden, Tiffany

Title: District Bookkeeper Credential: Click to enter text.

Organization Name: L&S District Services, LLC

Mailing Address: <u>305 Peach St</u> City, State, Zip Code: <u>Tomball, TX, 77375</u>

Phone No.: <u>281-356-7542</u> E-mail Address: <u>tiffany.n.loggins@gmail.com</u>

Section 7. DMR/MER Contact Information (Instructions Page 27)

Provide the name and complete mailing address of the person delegated to receive and submit Discharge Monitoring Reports (DMR) (EPA 3320-1) or maintain Monthly Effluent Reports (MER).

Prefix: Mr. Last Name, First Name: Wright, Lonnie

Title: <u>District Operator</u> Credential: Click to enter text.

Organization Name: Municipal Operations & Consultants, LLC

Mailing Address: 20141 Schiel Road City, State, Zip Code: Cypress, TX, 77433

Phone No.:281-367-5511 E-mail Address: lwright@municpalops.com

Section 8. Public Notice Information (Instructions Page 27)

A. Individual Publishing the Notices

Prefix: Mr. Last Name, First Name: Valentien, Jacob

Title: <u>Senior Project Manager</u> Credential: <u>P.E</u>
Organization Name: Westwood Professional Services

Mailing Address: 8701 N Mopac Expressway, Suite 320 City, State, Zip Code: Austin, Tx 78759

Phone No.: <u>512-485-0831</u> E-mail Address: <u>Jacob.valentien@westwoodps.com</u>

В.	Method for Receiving Notice of Receipt and Intent to Obtain a Water Quality Permit Package
	Indicate by a check mark the preferred method for receiving the first notice and instructions
	□ Fax
	⊠ Regular Mail
C.	Contact permit to be listed in the Notices
	Prefix: Mr. Last Name, First Name: Valentien, Jacob
	Title: <u>Senior Project Manager</u> Credential: <u>P.E</u>
	Organization Name: Westwood Professional Services
	Mailing Address: <u>8701 N Mopac Expressway, Suite 320</u> City, State, Zip Code: <u>Austin, Tx 78759</u>
	Phone No.: <u>512-485-0831</u> E-mail Address: <u>Jacob.valentien@westwoodps.com</u>
D.	Public Viewing Information
	If the facility or outfall is located in more than one county, a public viewing place for each county must be provided.
	Public building name: <u>Dripping Springs City Hall</u>
	Location within the building: <u>Front Desk</u>
	Physical Address of Building: <u>511 Mercer St</u>
	City: <u>Dripping Springs</u> County: <u>Hays</u>
	Contact (Last Name, First Name): Click to enter text.
	Phone No.: <u>512-858-4725</u> Ext.: Click to enter text.
E.	Bilingual Notice Requirements
	This information is required for new, major amendment, minor amendment or minor modification, and renewal applications.
	This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.
	Please call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine whether an alternative language notices are required.
	1. Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?

If **no**, publication of an alternative language notice is not required; **skip to** Section 9

2. Are the students who attend either the elementary school or the middle school enrolled in

a bilingual education program at that school?

No

No

Yes

Yes

below.

 \boxtimes

	3.	Do the locatio		at these	schools atte	nd a bili	ingual e	duca	tion prog	gram a	t another	
		\boxtimes	Yes		No							
	4.				iired to prov ement undei					gram b	out the school has	;
			Yes	\boxtimes	No							
	5.				lestion 1, 2, e is required						tive language are	
F.	Pla	in Lang	guage Su	mmary T	emplate							
	Co	mplete	the Plain	Language	e Summary (TCEQ Fo	orm 209	72) a	nd inclu	de as a	ın attachment.	
	At	tachme	nt: <u>2</u>									
G.	Pu	blic Inv	olvemer	ıt Plan Fo	rm							
	Co	mplete	the Publi	c Involvei	ment Plan Fo	orm (TCI	EQ Form	ı 209	60) for e	ach ap	plication for a	
	ne	w perm	iit or maj	or amend	dment to a p	ermit a	nd inclu	ide a	s an atta	chmen	t.	
	At	tachme	nt: <u>N/A</u>									
Co	oʻt:	0.72	Dogu	lated E	ntity and	Downs	ttod 0	'ita I	[reference	ation	(Instructions	
36	CU	on 9.	Regu Page		iiiiy allu	Periii	illeu s	nte	ШОШ	allOII	(Instructions	
Α.				tly regula	ted by TCEC), provid	le the Re	egula	ted Entit	y Num	ber (RN) issued to)
					egistry at <u>ht</u> d by TCEQ.	tp://ww	w15.tce	<u>q.tex</u>	as.gov/c	rpub/	to determine if	
B.	Na	me of p	roject or	site (the	name knowr	by the	commu	nity	where lo	cated):		
	<u>Ha</u>	ys Coun	ty Mud No	o.4 WWTP	•							
C.	Ov	vner of	treatmen	t facility:	Hays County	MUD No	<u>). 4</u>					
	Ov	vnership	of Facil	ity: 🖂	Public	□ Priv	ate		Both		Federal	
D.	Ov	vner of	land whe	re treatm	ent facility is	s or will	be:					
	Pre	efix: <u>N/</u>	<u>A</u>		Last Na	ame, Fir	st Name	e: <u>Ha</u> y	s County	MUD N	<u>Vo. 4</u>	
	Tit	le: <u>Own</u>	<u>er</u>		Creder	ıtial: <u>N/</u>	<u>A</u>					
	Or	ganizat	ion Name	: Hays Co	unty MUD N	0.4						
	Ma	iling Ac	ddress: <u>3</u>	321 Bee Ca	ves Road, Sui	<u>te 203</u>	City,	State	, Zip Coc	le: <u>Aust</u>	tin, TX, 78746	
	Ph	one No.	: 512-615-	0503	E-mail	Addres	s: <u>mkut</u>	ac@n	nbkfirm.c	<u>om</u>		
					ame person easement. S				or co-ap	plican	t, attach a lease	
		Attach	ment: <u>N</u> /	<u>'A</u>								

F.

	Prefix: <u>N/A</u>	Last Name, First Name: <u>N/A</u>
	Title: <u>District</u>	Credential:
	Organization Name: <u>Hays County</u>	MUD No. 4
	Mailing Address: 3321 Bee Caves I	Rd, Suite 203 City, State, Zip Code: Austin, TX, 78746
	Phone No.: (512) 615-0503	E-mail Address: Mkutac@mbkfirm.com
	If the landowner is not the same agreement or deed recorded eas	person as the facility owner or co-applicant, attach a lease ement. See instructions.
	Attachment: 3	
F.	Owner sewage sludge disposal so property owned or controlled by	ite (if authorization is requested for sludge disposal on the applicant)::
	Prefix: <u>N/A</u>	Last Name, First Name: <u>N/A</u>
	Title: <u>N/A</u>	Credential: Click to enter text.
	Organization Name: <u>N/A</u>	
	Mailing Address: <u>N/A</u>	City, State, Zip Code: <u>N/A</u> E-mail Address: <u>N/A</u>
	If the landowner is not the same agreement or deed recorded east	person as the facility owner or co-applicant, attach a lease ement. See instructions.
	Attachment: <u>N/A</u>	
Se	ection 10. TPDES Dischar	ge Information (Instructions Page 31)
Α.	Is the wastewater treatment faci	lity location in the existing permit accurate?
	⊠ Yes □ No	
		on, please give an accurate description:
	N/A	
В.	Are the point(s) of discharge and	the discharge route(s) in the existing permit correct?
	□ Yes □ No	
		permit application, provide an accurate description of the
	TAC Chapter 307:	arge route to the nearest classified segment as defined in 30
	N/A	
	City nearest the outfall(s): Click	to enter text.
	•	s/are located: Click to enter text.
C.	-	discharge to a city, county, or state highway right-of-way, or
	a flood control district drainage	
	□ Yes ⊠ No	

E. Owner of effluent disposal site:

	□ Authorization granted □ Authorization pending
	For new and amendment applications, provide copies of letters that show proof of contact and the approval letter upon receipt.
	Attachment: <u>N/A</u>
D.	For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge: $\underline{N/A}$
Se	ection 11. TLAP Disposal Information (Instructions Page 32)
A.	For TLAPs, is the location of the effluent disposal site in the existing permit accurate?
	⊠ Yes □ No
	If no, or a new or amendment permit application , provide an accurate description of the disposal site location:
	N/A
В.	City nearest the disposal site: <u>City of Dripping Springs ETJ</u>
C.	
	Disposal Site Latitude: N 30.21024 Longitude: W 97.98285
	For TLAPs , describe the routing of effluent from the treatment facility to the disposal site:
	Treated effluent flows to a storage tank located at the WWTP and is then pumped to adjacent disposal areas. The effluent subsurface drip irrigation disposal site is located around the existing WWTP, and at beneficial reuse sites within the Ledge Stone subdivision/ Hays County MUD No. 4.
F.	For TLAPs , please identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained: <u>An unnamed tributary of Long Branch.</u>
Se	ection 12. Miscellaneous Information (Instructions Page 32)
A.	Is the facility located on or does the treated effluent cross American Indian Land?
	□ Yes ⊠ No
В.	If the existing permit contains an onsite sludge disposal authorization, is the location of the sewage sludge disposal site in the existing permit accurate?
	□ Yes □ No ⊠ Not Applicable
	If No, or if a new onsite sludge disposal authorization is being requested in this permit application, provide an accurate location description of the sewage sludge disposal site.
	N/A

C.	Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?
	□ Yes ⊠ No
	If yes, list each person formerly employed by the TCEQ who represented your company and was paid for service regarding the application: $\underline{N/A}$
D.	Do you owe any fees to the TCEQ?
	□ Yes ⊠ No
	If yes , provide the following information:
	Account number: <u>N/A</u>
	Amount past due: <u>N/A</u>
E.	Do you owe any penalties to the TCEQ?
	□ Yes ⊠ No
	If yes , please provide the following information:
	Enforcement order number: N/A
	Amount past due: N/A
Se	ection 13. Attachments (Instructions Page 33)
Inc	dicate which attachments are included with the Administrative Report. Check all that apply:
	Lease agreement or deed recorded easement, if the land where the treatment facility is located or the effluent disposal site are not owned by the applicant or co-applicant.
\boxtimes	Original full-size USGS Topographic Map with the following information:
	 Applicant's property boundary Treatment facility boundary Labeled point of discharge for each discharge point (TPDES only) Highlighted discharge route for each discharge point (TPDES only) Onsite sewage sludge disposal site (if applicable) Effluent disposal site boundaries (TLAP only) New and future construction (if applicable) 1 mile radius information 3 miles downstream information (TPDES only) All ponds.
	Attachment 1 for Individuals as co-applicants
\boxtimes	Other Attachments. Please specify: Core Data Form and USGS Topographic Map

Section 14. Signature Page (Instructions Page 34)

If co-applicants are necessary, each entity must submit an original, separate signature page.

Permit Number: <u>WQ0014309001</u> Applicant: <u>Hays County MUD No. 4</u>

Certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

I further certify that I am authorized under 30 Texas Administrative Code § 305.44 to sign and submit this document, and can provide documentation in proof of such authorization upon request.

Signatory name	/ <u>-</u>		O - 1 - 1 1
Nighalory name	HVDPO	or printeat	traid Michalloch
DIEHUCOLY HUHIC	(LYDCU	or printed.	. Clais Miccomodii

Signatory title: **Board President**

Signature:	Crac Milallod	Date:	26	24	
_	(Use blue ink)		1		

Subscribed	d and Sworn to before	me by the	said Craig	McColloch	
on this	26th	day of	August	, 20 <u>24</u> .	
My commi	ssion evnires on the	E +h	day of Nove	mber 20 24	

HOLLIS ANN SCHEFFLER
Notary Public, State of Texas
Comm. Expires 11-05-20 SHAL
Notary ID 132767781

Notary Public

Travis
County, Texas

DOMESTIC WASTEWATER PERMIT APPLICATION SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: N/A

ATTACHMENT 1

INDIVIDUAL INFORMATION

Section 1. Individual Information (Instructions Page 41)

Complete this attachment if the facility applicant or co-applicant is an individual. Make additional copies of this attachment if both are individuals.

Prefix (Mr., Ms., Miss): N/A

Full legal name (Last Name, First Name, Middle Initial): N/A

Driver's License or State Identification Number: N/A

Date of Birth: <u>N/A</u>
Mailing Address: <u>N/A</u>

City, State, and Zip Code: N/A

Phone Number: N/A Fax Number: N/A

E-mail Address: N/A

CN: <u>N/A</u>

For Commission Use Only:

Customer Number:

Regulated Entity Number:

Permit Number:

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST OF COMMON DEFICIENCIES

Below is a list of common deficiencies found during the administrative review of domestic wastewater permit applications. To ensure the timely processing of this application, please review the items below and indicate by checking Yes that each item is complete and in accordance applicable rules at 30 TAC Chapters 21, 281, and 305. If an item is not required this application, indicate by checking N/A where appropriate. Please do not submit the application until the items below have been addressed.

application until the items below have been addressed.				
Core Data Form (TCEQ Form No. 10400) (Required for all application types. Must be completed in its entirety Note: Form may be signed by applicant representative.)	and s	igned.		Yes
Correct and Current Industrial Wastewater Permit Application Form (TCEQ Form Nos. 10053 and 10054. Version dated 6/25/2018 or late			\boxtimes	Yes
Water Quality Permit Payment Submittal Form (Page 19) (Original payment sent to TCEQ Revenue Section. See instructions fo	r mai	iling ad	⊠ dress	Yes
7.5 Minute USGS Quadrangle Topographic Map Attached (Full-size map if seeking "New" permit. 8½ x 11 acceptable for Renewals and Amendments)				Yes
Current/Non-Expired, Executed Lease Agreement or Easement	\boxtimes	N/A		Yes
Landowners Map (See instructions for landowner requirements)	\boxtimes	N/A		Yes
 Things to Know: All the items shown on the map must be labeled. The applicant's complete property boundaries must be do boundaries of contiguous property owned by the applicant. The applicant cannot be its own adjacent landowner. You landowners immediately adjacent to their property, regar from the actual facility. If the applicant's property is adjacent to a road, creek, or on the opposite side must be identified. Although the property applicant's property boundary, they are considered poter If the adjacent road is a divided highway as identified on map, the applicant does not have to identify the landown the highway. 	nt. mus dless strea operti itially the U	t identi of hov m, the es are i affecto JSGS to	fy th v far lando not a ed lar pogra	e they are owners djacent to idowners. aphic
Landowners Cross Reference List (See instructions for landowner requirements)	\boxtimes	N/A		Yes
Landowners Labels or USB Drive attached (See instructions for landowner requirements)	\boxtimes	N/A		Yes
Original signature per 30 TAC § 305.44 - Blue Ink Preferred			\boxtimes	Yes

a copy of signature authority/delegation letter must be attached)

Plain Language Summary

(If signature page is not signed by an elected official or principle executive officer,

Yes

THE TONMENTAL OUR THE

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

For any questions about this form, please contact the Domestic Wastewater Permitting Team at 512-239-4671.

The following information is required for all renewal, new, and amendment applications.

Section 1. Permitted or Proposed Flows (Instructions Page 43)

A. Existing/Interim I Phase

Design Flow (MGD): <u>o.o75 MGD</u> 2-Hr Peak Flow (MGD): <u>o.3 MGD</u>

Estimated construction start date: <u>CONSTRUCTED</u> Estimated waste disposal start date: <u>ON-GOING</u>

B. Interim II Phase

Design Flow (MGD): <u>.100 MGD</u> 2-Hr Peak Flow (MGD): <u>0.4 MGD</u>

Estimated construction start date: <u>CONSTRUCTED</u> Estimated waste disposal start date: <u>ON-GOING</u>

C. Final Phase

Design Flow (MGD): <u>0.150 MGD</u> 2-Hr Peak Flow (MGD): <u>0.6 MGD</u>

Estimated construction start date: <u>August 2025</u> Estimated waste disposal start date: <u>August 2026</u>

D. Current Operating Phase: Interim II Phase

Provide the startup date of the facility: September 9, 2009

Section 2. Treatment Process (Instructions Page 43)

A. Current Operating Phase

Provide a detailed description of the treatment process. **Include the type of treatment plant, mode of operation, and all treatment units.** Start with the plant's head works and

Attachment 6

finish with the point of discharge. Include all sludge processing and drying units. If more

B. Treatment Units

In Table 1.0(1), provide the treatment unit type, the number of units, and dimensions (length, width, depth) of each treatment unit, accounting for *all* phases of operation.

Table 1.0(1) - Treatment Units

Treatment Unit Type	Number of Units	Dimensions (L x W x D)
Attachment 7		

C. Process Flow Diagram

Provide flow diagrams for the existing facilities and **each** proposed phase of construction.

Attachment: 8

Section 3. Site Information and Drawing (Instructions Page 44)

Provide the TPDES discharge outfall latitude and longitude. Enter N/A if not applicable.

Latitude: N/ALongitude: N/A

Provide the TLAP disposal site latitude and longitude. Enter N/A if not applicable.

Latitude: <u>30.21024</u>Longitude: <u>97.98285</u>

Provide a site drawing for the facility that shows the following:

- The boundaries of the treatment facility;
- The boundaries of the area served by the treatment facility;
- If land disposal of effluent, the boundaries of the disposal site and all storage/holding ponds; and
- If sludge disposal is authorized in the permit, the boundaries of the land application or disposal site.

Attachment: 9

The sewer service area includes a mixture of single family, multifamily and commercial buildings located within the Hays County MUD No. 4 district boundaries, located NW of the intersection of Highway 290 and Nutty Brown Rd. Section 4. Unbuilt Phases (Instructions Page 45) Is the application for a renewal of a permit that contains an unbuilt phase or phases? Yes □ If yes, does the existing permit contain a phase that has not been constructed within five **vears** of being authorized by the TCEO? Yes □ No If yes, provide a detailed discussion regarding the continued need for the unbuilt phase. Failure to provide sufficient justification may result in the Executive Director recommending denial of the unbuilt phase or phases. The District is currently reviewing potential sites for drip field expansion within the District that will require a major permit amendment and to enter the final phase of the Permit at 0.150 MGD. After this current permit is renewed, the District will submit a major permit amendment to expand the drip field areas to obtain 0.150 MGD capacity and upon approval of that major permit amendment, the District will submit a project summary transmittal letter to the TCEO for additional drip field expansion to accommodate necessary wastewater demand. Section 5. Closure Plans (Instructions Page 45) Have any treatment units been taken out of service permanently, or will any units be taken out of service in the next five years? Yes 🗵 No **If yes,** was a closure plan submitted to the TCEQ? Yes □ No If yes, provide a brief description of the closure and the date of plan approval. N/A

Provide the name **and** a description of the area served by the treatment facility.

Section 6. Permit Specific Requirements (Instructions Page 45)

For applicants with an existing permit, check the Other Requirements or Special Provisions of the permit.

A. Summary transmittal

Have plans and specifications been approved for the existing facilities and each proposed phase?

⊠ Yes □ No

If yes, provide the date(s) of approval for each phase: 12/20/2006 and 12/3/2020

Provide information, including dates, on any actions taken to meet a *requirement or provision* pertaining to the submission of a summary transmittal letter. **Provide a copy of** an approval letter from the TCEQ, if applicable.

See Attachment 10 and 11 for TCEQ approval letters.

B. Buffer zones

Have the buffer zone requirements been met?

⊠ Yes □ No

Provide information below, including dates, on any actions taken to meet the conditions of the buffer zone. If available, provide any new documentation relevant to maintaining the buffer zones.

See Attachment #9 for site layout that indicates the current buffer zone area. At the construction of the WWTP, nuisance odor controlled was installed and the treatment facility is located 150 ft away from any habitable properties.

C. Other actions required by the current permit

Does the *Other Requirements* or *Special Provisions* section in the existing permit require submission of any other information or other required actions? Examples include Notification of Completion, progress reports, soil monitoring data, etc.

⊠ Yes □ No

If yes, provide information below on the status of any actions taken to meet the conditions of an *Other Requirement* or *Special Provision*.

		oil monitoring requirements have been met and buffer zone for odor abatement has been oproved by TCEQ.
D.	Gr	it and grease treatment
	1.	Acceptance of grit and grease waste
		Does the facility have a grit and/or grease processing facility onsite that treats and decants or accepts transported loads of grit and grease waste that are discharged directly to the wastewater treatment plant prior to any treatment?
		□ Yes ⊠ No
		If No, stop here and continue with Subsection E. Stormwater Management.
	<i>2.</i>	Grit and grease processing
		Describe below how the grit and grease waste is treated at the facility. In your description, include how and where the grit and grease is introduced to the treatment works and how it is separated or processed. Provide a flow diagram showing how grit and grease is processed at the facility.
	3.	Grit disposal
		Does the facility have a Municipal Solid Waste (MSW) registration or permit for grit disposal?
		□ Yes ⊠ No
		If No , contact the TCEQ Municipal Solid Waste team at 512-239-2335. Note: A registration or permit is required for grit disposal. Grit shall not be combined with treatment plant sludge. See the instruction booklet for additional information on grit disposal requirements and restrictions.
		Describe the method of grit disposal.
		N/A

4. (Grease	and	decanted	liauid	disposal
------	--------	-----	----------	--------	----------

Note: A registration or permit is required for grease disposal. Grease shall not be combined with treatment plant sludge. For more information, contact the TCEQ Municipal Solid Waste team at 512-239-2335.

Describe how the decant and	grease are treated and d	lisposed of after	grit separation.

N/A	eparation.
rmwater management	
Analicability	

E. Sto

1. Applicability

Does the facility have a design flow of 1.0 MGD or greater in any phase?								
	Yes	\boxtimes	No					
Does tl	ne fac	ility l	nave an approved pretreatment program, under 40 CFR Part 403?					
	Yes	\boxtimes	No					

If no to both of the above, then skip to Subsection F. Other Wastes Received.

2. MSGP coverage

Is the stormwater runoff from the WWTP and dedicated lands for sewage disposal currently permitted under the TPDES Multi-Sector General Permit (MSGP), TXR050000?

Yes ⊠ No

If yes, please provide MSGP Authorization Number and skip to Subsection F, Other Wastes Received:

TXR05 Click to enter text. or TXRNE

If no, do you intend to seek coverage under TXR050000?

Yes \square No

3. Conditional exclusion

Alternatively, do you intend to apply for a conditional exclusion from permitting based TXR050000 (Multi Sector General Permit) Part II B.2 or TXR050000 (Multi Sector General Permit) Part V, Sector T 3(b)?

Yes 🗵 No

If yes, please explain below then proceed to Subsection F, Other Wastes Received:

N/A			

4.	Existing coverage in individual permit
	Is your stormwater discharge currently permitted through this individual TPDES or TLAP permit?
	□ Yes ⊠ No
	If yes , provide a description of stormwater runoff management practices at the site that are authorized in the wastewater permit then skip to Subsection F, Other Wastes Received.
	N/A
<i>5.</i>	Zero stormwater discharge
	Do you intend to have no discharge of stormwater via use of evaporation or other means?
	□ Yes □ No
	If yes, explain below then skip to Subsection F. Other Wastes Received.
	N/A
	Note: If there is a potential to discharge any stormwater to surface water in the state as the result of any storm event, then permit coverage is required under the MSGP or an individual discharge permit. This requirement applies to all areas of facilities with treatment plants or systems that treat, store, recycle, or reclaim domestic sewage, wastewater or sewage sludge (including dedicated lands for sewage sludge disposal located within the onsite property boundaries) that meet the applicability criteria of above. You have the option of obtaining coverage under the MSGP for direct discharges, (recommended), or obtaining coverage under this individual permit.
<i>6.</i>	Request for coverage in individual permit
	Are you requesting coverage of stormwater discharges associated with your treatment plant under this individual permit?

☐ Yes ☒ No

If yes, provide a description of stormwater runoff management practices at the site for which you are requesting authorization in this individual wastewater permit and describe whether you intend to comingle this discharge with your treated effluent or

discharge it via a separate dedicated stormwater outfall. Please also indicate if you

		intend to divert stormwater to the treatment plant headworks and indirectly discharge it to water in the state.
		Click to enter text.
		Note: Direct stormwater discharges to waters in the state authorized through this individual permit will require the development and implementation of a stormwater pollution prevention plan (SWPPP) and will be subject to additional monitoring and reporting requirements. Indirect discharges of stormwater via headworks recycling will require compliance with all individual permit requirements including 2-hour peak flow limitations. All stormwater discharge authorization requests will require additional information during the technical review of your application.
F.	Dis	scharges to the Lake Houston Watershed
	Do	es the facility discharge in the Lake Houston watershed?
		□ Yes ⊠ No
		yes, attach a Sewage Sludge Solids Management Plan. See Example 5 in the instructions. ck to enter text.
G.	Ot	her wastes received including sludge from other WWTPs and septic waste
	1.	Acceptance of sludge from other WWTPs
		Does or will the facility accept sludge from other treatment plants at the facility site?
		□ Yes ⊠ No
		If yes, attach sewage sludge solids management plan. See Example 5 of instructions.
		In addition, provide the date the plant started or is anticipated to start accepting sludge, an estimate of monthly sludge acceptance (gallons or millions of gallons), an
		estimate of the BOD_5 concentration of the sludge, and the design BOD_5 concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.
		N/A
		Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.
	2.	Acceptance of septic waste
		Is the facility accepting or will it accept septic waste?
		□ Yes ⊠ No
		If yes, does the facility have a Type V processing unit?
		□ Yes □ No
		If yes, does the unit have a Municipal Solid Waste permit?
		□ Yes □ No

	accepting septic waste, an estimate of monthly septic waste acceptance (gallons or millions of gallons), an estimate of the BOD_5 concentration of the septic waste, and the design BOD_5 concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action. N/A
	Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.
3.	Acceptance of other wastes (not including septic, grease, grit, or RCRA, CERCLA or as discharged by IUs listed in Worksheet 6)
	Is or will the facility accept wastes that are not domestic in nature excluding the categories listed above?
	□ Yes ⊠ No
	If yes, provide the date that the plant started accepting the waste, an estimate how much waste is accepted on a monthly basis (gallons or millions of gallons), a description of the entities generating the waste, and any distinguishing chemical or other physical characteristic of the waste. Also note if this information has or has not changed since the last permit action.
	N/A
Secti	on 7. Pollutant Analysis of Treated Effluent (Instructions Page 50)
Is the	facility in operation?
\boxtimes	Yes □ No
If no.	this section is not applicable. Proceed to Section 8.

If yes to any of the above, provide the date the plant started or is anticipated to start

If no,

If yes, provide effluent analysis data for the listed pollutants. *Wastewater treatment facilities* complete Table 1.0(2). *Water treatment facilities* discharging filter backwash water, complete Table 1.0(3). Provide copies of the laboratory results sheets. **These tables are not** applicable for a minor amendment without renewal. See the instructions for guidance.

Note: The sample date must be within 1 year of application submission.

Table1.0(2) - Pollutant Analysis for Wastewater Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
CBOD ₅ , mg/l	<3.00		1	grab	1/26/2024 10:18 A.M.
Total Suspended Solids, mg/l	11.2		1	grab	1/26/2024 10:18 A.M.
Ammonia Nitrogen, mg/l	.0611		1	grab	1/26/2024 10:18 A.M.
Nitrate Nitrogen, mg/l	14.0		1	grab	1/26/2024 10:18 A.M.
Total Kjeldahl Nitrogen, mg/l	<1.00		1	Grab	1/26/2024 10:18 A.M.
Sulfate, mg/l	40.5		1	Grab	1/26/2024 10:18 A.M.
Chloride, mg/l	129		1	Grab	1/26/2024 10:18 A.M.
Total Phosphorus, mg/l	4.05		1	Grab	1/26/2024 10:18 A.M.
pH, standard units	7.00		1	Grab	1/26/2024 10:18 A.M.
Dissolved Oxygen*, mg/l	7.46		1	Grab	
Chlorine Residual, mg/l	1.06		1	grab	1/26/2024 10:18 A.M.
E.coli (CFU/100ml) freshwater	4.10		1	Grab	1/26/2024 10:18 A.M.
Entercocci (CFU/100ml) saltwater					
Total Dissolved Solids, mg/l	452		1	Grab	1/26/2024 10:18 A.M.
Electrical Conductivity, µmohs/cm, †	894		1	Grab	1/26/2024 10:18 A.M.
Oil & Grease, mg/l	<5.0		1	Grab	1/26/2024 10:18 A.M.
Alkalinity (CaCO ₃)*, mg/l	109		1	Grab	1/26/2024 10:18 A.M.

^{*}TPDES permits only †TLAP permits only

Table1.0(3) - Pollutant Analysis for Water Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Total Suspended Solids, mg/l					
Total Dissolved Solids, mg/l					
pH, standard units					

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Fluoride, mg/l					
Aluminum, mg/l					
Alkalinity (CaCO ₃), mg/l					

Section 8. Facility Operator (Instructions Page 50)

Facility Operator Name: Christopher Sanchez

Facility Operator's License Classification and Level: Wastewater Treatment operator B

Facility Operator's License Number: <u>WWoo59670</u>

Section 9. Sludge and Biosolids Management and Disposal (Instructions Page 51)

(instructions Page 51)

Α.	ww	TP's Biosolids Management Facility Type
		ck all that apply. See instructions for guidance
		Design flow>= 1 MGD
		Serves >= 10,000 people
		Class I Sludge Management Facility (per 40 CFR § 503.9)
		Biosolids generator
		Biosolids end user – land application (onsite)
		Biosolids end user – surface disposal (onsite)
		Biosolids end user – incinerator (onsite)
D	TAITAI	
В.		TP's Biosolids Treatment Process
	Che	ck all that apply. See instructions for guidance.
		Aerobic Digestion
		Air Drying (or sludge drying beds)
		Lower Temperature Composting
		Lime Stabilization
		Higher Temperature Composting
		Heat Drying
		Thermophilic Aerobic Digestion
		Beta Ray Irradiation
		Gamma Ray Irradiation
		Pasteurization
		Preliminary Operation (e.g. grinding, de-gritting, blending)

	Thickening (e.g. gravity thickening, centrifugation, filter press, vacuum filter)
	Sludge Lagoon
	Temporary Storage (< 2 years)
	Long Term Storage (>= 2 years)
	Methane or Biogas Recovery
\boxtimes	Other Treatment Process: Sludge dewatering box

C. Biosolids Management

Provide information on the *intended* biosolids management practice. Do not enter every management practice that you want authorized in the permit, as the permit will authorize all biosolids management practices listed in the instructions. Rather indicate the management practice the facility plans to use.

Biosolids Management

Management Practice	Handler or Preparer Type	Bulk or Bag Container	Amount (dry metric tons)	Pathogen Reduction Options	Vector Attraction Reduction Option
Disposal in Landfill	Off-site Third-Party Handler or Preparer	Bulk	3.71	Class B: PSRP Lime Stabilization	Option 4: SOUR <=1.5 mg 02/hr/g total solids at 20C (<2% solids)
Disposal in Landfill	Off-site Third-Party Handler or Preparer	Bulk	125.3	Class B: PSRP Lime Stabilization	Option 4: SOUR <=1.5 mg 02/hr/g total solids at 20C (<2% solids)

If "Other" is selected for Management Practice, please explain (e.g. monofill or transport to another WWTP): N/A

D. Disposal site

Disposal site name: Wastewater Residuals Management, LLC

TCEQ permit or registration number: <u>2384</u> County where disposal site is located: Travis

Disposal site name: <u>J-V Dirt & Loam</u>

TCEQ permit or registration number: <u>2310</u> County where disposal site is located: <u>Travis</u>

E. Transportation method

Method of transportation (truck, train, pipe, other): <u>Truck</u>

	Name of the ha	uler: <u>Wastewater Trans</u>	port & Sherida	an Er	vironm	<u>ental</u>	
	Hauler registration number: 24343						
	Sludge is trans	ported as a:					
	Liquid □	semi-liquid ⊠	semi-solid		soli	d 🗆	
Se		ermit Authorizati nstructions Page		wag	e Slu	lge D	isposal
	(II	iistructions rage	<i>JJ)</i>				
Α.	Beneficial use	authorization					
	Does the existing beneficial use?	ng permit include auth	orization fo	r lan	d appli	cation	of sewage sludge for
	□ Yes ⊠	No No					
	If yes , are you beneficial use?	requesting to continue	e this author	izati	on to la	nd app	oly sewage sludge for
	□ Yes □	l No					
		ompleted Application in 0. 10451) attached to					Use of Sewage Sludge instructions for
	□ Yes □	l No					
B.	Sludge process	sing authorization					
	Does the existing storage or disp		orization fo	r any	of the	follow	ing sludge processing,
	Sludge Com	posting			Yes	\boxtimes	No
	Marketing a	and Distribution of slu	dge		Yes	\boxtimes	No
	Sludge Surf	ace Disposal or Sludge	Monofill		Yes	\boxtimes	No
	Temporary	storage in sludge lago	ons		Yes	\boxtimes	No
	authorization,	f the above sludge opti is the completed Dom o ort (TCEQ Form No. 1 0	estic Wastev	vatei	Permi	t Appli	ication: Sewage Sludge
	□ Yes □	l No					
Se	ection 11 Se	ewage Sludge Lag	oons (Ins	friid	rtions	Ρασε	53)
				ши	-0.0.118	ı ağc	. 33)
DU	oes this facility include sewage sludge lagoons? □ Yes ⊠ No						
If v		no le remainder of this se	ction If no 1	roce	ed to S	ection	12
-			C	J1 () ((ca to s	CCHOII	
Α.	A. Location information						

The following maps are required to be submitted as part of the application. For each map, provide the Attachment Number.

Original General Highway (County) Map:

If

Attachment: N/A

• USDA Natural Resources Conservation Service Soil Map:

Attachment: N/A

• Federal Emergency Management Map:

Attachment: N/A

• Site map:

Attachment: N/A

Discuss in a description if any of the following exist within the lagoon area. Check all that apply.

☐ Overlap a designated 100-year frequency flood plain

☐ Soils with flooding classification

□ Overlap an unstable area

□ Wetlands

□ Located less than 60 meters from a fault

 \square None of the above

Attachment: N/A

If a portion of the lagoon(s) is located within the 100-year frequency flood plain, provide the protective measures to be utilized including type and size of protective structures:

N/A

B. Temporary storage information

Provide the results for the pollutant screening of sludge lagoons. These results are in addition to pollutant results in *Section 7 of Technical Report 1.0.*

Nitrate Nitrogen, mg/kg: Click to enter text.

Total Kjeldahl Nitrogen, mg/kg: Click to enter text.

Total Nitrogen (=nitrate nitrogen + TKN), mg/kg: Click to enter text.

Phosphorus, mg/kg: Click to enter text.

Potassium, mg/kg: <u>Click to enter text.</u> pH, standard units: Click to enter text.

Ammonia Nitrogen mg/kg: Click to enter text.

Arsenic: Click to enter text.

Cadmium: Click to enter text.

Chromium: <u>Click to enter text.</u>

	Lead: Click to enter text.
	Mercury: Click to enter text.
	Molybdenum: Click to enter text.
	Nickel: Click to enter text.
	Selenium: <u>Click to enter text.</u>
	Zinc: Click to enter text.
	Total PCBs: Click to enter text.
	Provide the following information:
	Volume and frequency of sludge to the lagoon(s): Click to enter text.
	Total dry tons stored in the lagoons(s) per 365-day period: Click to enter text.
	Total dry tons stored in the lagoons(s) over the life of the unit: Click to enter text.
C.	Liner information
	Does the active/proposed sludge lagoon(s) have a liner with a maximum hydraulic conductivity of $1x10^{-7}$ cm/sec?
	□ Yes □ No
	If yes, describe the liner below. Please note that a liner is required.
	Click to enter text.
_	
D.	Site development plan
	Provide a detailed description of the methods used to deposit sludge in the lagoon(s):
	Click to enter text.
	Attach the following documents to the application.
	Plan view and cross-section of the sludge lagoon(s)
	Attachment: Click to enter text.
	Copy of the closure plan
	Attachment: Click to enter text

• Size of the sludge lagoon(s) in surface acres and capacity in cubic feet and gallons

• Copy of deed recordation for the site Attachment: <u>Click to enter text.</u> Attachment: Click to enter text.

• Description of the method of controlling infiltration of groundwater and surface water from entering the site

Attachment: Click to enter text.

Procedures to prevent the occurrence of nuisance conditions

Attachment: Click to enter text.

E. Groundwater monitoring

Is groundwater monitoring currently conducted at this site, or are any wells available for groundwater monitoring, or are groundwater monitoring data otherwise available for the sludge lagoon(s)?

□ Yes □ No

If groundwater monitoring data are available, provide a copy. Provide a profile of soil types encountered down to the groundwater table and the depth to the shallowest groundwater as a separate attachment.

Attachment: Click to enter text.

Section 12. Authorizations/Compliance/Enforcement (Instructions Page 55)

A. Additional authorizations

Does the permittee have additional authorizations for this facility, such as reu	ıse
authorization, sludge permit, etc?	

⊠ Yes □ No

If yes, provide the TCEQ authorization number and description of the authorization:

R14309-001, 210 Beneficial reuse for irrigation and water quality pond make up water. See
Attachment 14

B. Permittee enforcement status

Is the permittee currently under enforcement for this facility?

□ Yes ⊠ No

Is the permittee required to meet an implementation schedule for compliance or enforcement?

□ Yes ⊠ No

If yes to either question, provide a brief summary of the enforcement, the implementation schedule, and the current status:

Click to enter text.

Section 13. RCRA/CERCLA Wastes (Instructions Page 55)

A. RCRA hazardous wastes

Has the facility received in the past three years, does it currently receive, or will it receive RCRA hazardous waste?

□ Yes ⊠ No

B. Remediation activity wastewater

Has the facility received in the past three years, does it currently receive, or will it receive CERCLA wastewater, RCRA remediation/corrective action wastewater or other remediation activity wastewater?

□ Yes ⊠ No

C. Details about wastes received

If yes to either Subsection A or B above, provide detailed information concerning these wastes with the application.

Attachment: Click to enter text.

Section 14. Laboratory Accreditation (Instructions Page 56)

All laboratory tests performed must meet the requirements of *30 TAC Chapter 25*, *Environmental Testing Laboratory Accreditation and Certification*, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - o periodically inspected by the TCEQ; or
 - o located in another state and is accredited or inspected by that state; or
 - o performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the Signature Page section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: Craig McColloch

Title: District Director

Signature:

Meden

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND DISPOSAL OF EFFLUENT

The following is required for renewal, new, and amendment permit applications.

Section 1. Type of Disposal System (Instructions Page 68)

	,		
	Surface application		Subsurface application
	Irrigation		Subsurface soils absorption
	Drip irrigation system	\boxtimes	Subsurface area drip dispersal system
	Evaporation		Evapotranspiration beds
	Other (describe in detail): Click	to er	nter text.
TE:	All applicants without authoriza	ation	or proposing new/amended subsurface dispo

NOTE: All applicants without authorization or proposing new/amended subsurface disposal MUST complete and submit Worksheet 7.0.

For existing authorizations, provide Registration Number: 103897567

Section 2. Land Application Site(s) (Instructions Page 68)

In table 3.0(1), provide the requested information for the land application sites. Include the agricultural or cover crop type (wheat, cotton, alfalfa, bermuda grass, native grasses, etc.), land use (golf course, hayland, pastureland, park, row crop, etc.), irrigation area, amount of effluent applied, and whether or not the public has access to the area. Specify the amount of land area and the amount of effluent that will be allotted to each agricultural or cover crop, if more than one crop will be used.

Table 3.0(1) - Land Application Site Crops

Identify the method of land disposal:

Crop Type & Land Use	Irrigation Area (acres)	Effluent Application (GPD)	Public Access? Y/N
Bermuda and Rye Grass	27.2	119,566	Y

Section 3. Storage and Evaporation Lagoons/Ponds (Instructions Page **68)**

Table 3.0(2) - Storage and Evaporation Ponds

Pond Number	Surface Area (acres)	Storage Volume (acre-feet)	Dimensions	Liner Type
Tank		1.022	333,000	Bolted Steel

Attach a copy of a liner certification that was prepared, signed, and sealed by a Texas licensed professional engineer for each pond.

Attachment: No ponds planned. Tank is provided to accommodate two days of storage at design flow for final phase.

	Section 4.	Flood and Runoff Protection (Instructions P	age 68)
--	------------	-------------------------------	----------------	---------

Section 4. Flood and Runoii Protection (instructions Page 68)
Is the land application site $\underline{\text{within}}$ the 100-year frequency flood level? \square Yes \boxtimes No
If yes, describe how the site will be protected from inundation.
N/A
Provide the source used to determine the 100-year frequency flood level:
FEMA Flood Insurance Rate Map Number 48209C0128F Dated September 2, 2005

Provide a description of tailwater controls and rainfall run-on controls used for the land application site.

Irrigation management and visual observation of the irrigation system will be performed to reduce tailwater, and irrigation will not take place during rainfall events. Tailwater is not anticipated for subsurface drip irrigation facilities.

Section 5. Annual Cropping Plan (Instructions Page 68)

Attach an Annual Cropping Plan which includes a discussion of each of the following items. If not applicable, provide a detailed explanation indicating why. **Attachment**: 15

- Soils map with crops
- Cool and warm season plant species
- Crop yield goals
- Crop growing season
- Crop nutrient requirements
- Additional fertilizer requirements
- Minimum/maximum harvest height (for grass crops)
- Supplemental watering requirements
- Crop salt tolerances
- Harvesting method/number of harvests
- Justification for not removing existing vegetation to be irrigated

Section 6. Well and Map Information (Instructions Page 69)

Attach a USGS map with the following information shown and labeled. If not applicable, provide a detailed explanation indicating why. **Attachment**: 4

- The boundaries of the land application site(s)
- Waste disposal or treatment facility site(s)
- On-site buildings
- Buffer zones
- Effluent storage and tailwater control facilities
- All water wells within 1-mile radius of the disposal site or property boundaries
- All springs and seeps onsite and within 500 feet of the property boundaries
- All surface waters in the state onsite and within 500 feet of the property boundaries
- All faults and sinkholes onsite and within 500 feet of the property

List and cross reference all water wells located within a half-mile radius of the disposal site or property boundaries shown on the USGS map in the following table. Attach additional pages as necessary to include all of the wells.

Table 3.0(3) - Water Well Data

Well ID	Well Use	Producing? Y/N		Proposed Best Management Practice
			Choose an item.	

Well ID	Well Use	Producing? Y/N	Open, cased, capped, or plugged?	Proposed Best Management Practice
			Choose an item.	
			Choose an item.	
			Choose an item.	
			Choose an item.	

If water quality data or well log information is available please include the information in an attachment listed by Well ID.

Attachment: N/A

Section 7. Groundwater Quality (Instructions Page 69)

Attach a Groundwater Quality Technical Report which assesses the impact of the wastewater disposal system on groundwater. This report shall include an evaluation of the water wells (including the information in the well table provided in Item 6. above), the wastewater application rate, and pond liners. Indicate by a check mark that this report is provided.

Attachment: N/A – This is an existing permit
Are groundwater monitoring wells available onsite? \square Yes \boxtimes No
Do you plan to install ground water monitoring wells or lysimeters around the land application site? \square Yes \boxtimes No
If yes, provide the proposed location of the monitoring wells or lysimeters on a site map.
Attachment: <u>N/A</u>

Section 8. Soil Map and Soil Analyses (Instructions Page 70)

A. Soil map

Attach a USDA Soil Survey map that shows the area to be used for effluent disposal.

Attachment: 16

B. Soil analyses

Attach the laboratory results sheets from the soil analyses. **Note**: for renewal applications, the current annual soil analyses required by the permit are acceptable as long as the test date is less than one year prior to the submission of the application.

Attachment: 17

List all USDA designated soil series on the proposed land application site. Attach additional pages as necessary.

Table 3.0(4) - Soil Data

Soil Series	Depth from Surface	Permeability	Available Water Capacity	Curve Number
Brackett - BtD	0-18"	0.2-0.6 in/hr	0.1-0.2	85
Brackett - BtG	0-18"	0.2-0.6 in/hr	0.1-0.2	85

Section 9. Effluent Monitoring Data (Instructions Page 71)

Is t	the	facility	in in	operation?
------	-----	----------	-------	------------

⊠ Yes □ No

If no, this section is not applicable and the worksheet is complete.

If yes, provide the effluent monitoring data for the parameters regulated in the existing permit. If a parameter is not regulated in the existing permit, enter N/A.

Table 3.0(5) - Effluent Monitoring Data

Date	30 Day Avg Flow MGD	BOD5 mg/l	TSS mg/l	рН	Chlorine Residual mg/l	Acres irrigated
See	Attachment	12				

Date	30 Day Avg Flow MGD	BOD5 mg/l	TSS mg/l	рН	Chlorine Residual mg/l	Acres irrigated

Provide a discussion of all persistent excursions above the permitted limits and any corrective actions taken.

S <u>ee Attachment 18.</u>	

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 6.0: INDUSTRIAL WASTE CONTRIBUTION

The following is required for all publicly owned treatment works.

Section 1. All POTWs (Instructions Page 89)

A. Industrial users (IUs)

Provide the number of each of the following types of industrial users (IUs) that discharge to your POTW and the daily flows from each user. See the Instructions for definitions of Categorical IUs, Significant IUs – non-categorical, and Other IUs.

If there are no users, enter 0 (zero).

Categorical IUs:
Number of IUs: <u>o</u>
Average Daily Flows, in MGD: Click to enter text.
Significant IUs - non-categorical:
Number of IUs: Click to enter text.
Average Daily Flows, in MGD: Click to enter text.
Other IUs:
Number of IUs: Click to enter text.
Average Daily Flows, in MGD: Click to enter text.

B. Treatment plant interference

In the past three years, has your POTW experienced treatment plant interference (see instructions)?

□ Yes ⊠ No

If yes, identify the dates, duration, description of interference, and probable cause(s) and possible source(s) of each interference event. Include the names of the IUs that may have caused the interference.

Cli	ck to enter text.			
<u></u>				

	In the past three years, has your POTW experienced pass through (see instructions)?
	□ Yes ⊠ No
	If yes , identify the dates, duration, a description of the pollutants passing through the treatment plant, and probable cause(s) and possible source(s) of each pass through event. Include the names of the IUs that may have caused pass through.
	Click to enter text.
D.	Pretreatment program
ν.	Does your POTW have an approved pretreatment program?
	□ Yes ⊠ No
	If yes, complete Section 2 only of this Worksheet.
	Is your POTW required to develop an approved pretreatment program?
	□ Yes ⊠ No
	If yes, complete Section 2.c. and 2.d. only, and skip Section 3.
	If no to either question above , skip Section 2 and complete Section 3 for each significant industrial user and categorical industrial user.
	ation 2 DOTMs with Assessed Decayance on Those Descriped to
Se	ection 2. POTWs with Approved Programs or Those Required to Develop a Program (Instructions Page 90)
	Develop a Program (Instructions Page 90)
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.
	Develop a Program (Instructions Page 90) Substantial modifications Have there been any substantial modifications to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18? Yes No If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.

C. Treatment plant pass through

	Have there been any non-substantial modifications to the approved pretreatment program that have not been submitted to TCEQ for review and acceptance?										
	□ Yes □ No										
	If yes, identify all non-substantial modifications that have not been submitted to TCEC including the purpose of the modification.										
	Click to enter text.										
C.	Effluent paramete	ers above the MAL									
Tal		all parameters meanth the last three years									
P	ollutant	Concentration	MAL	Units	Date						
D.	Industrial user int	terruptions									
		or other IU caused o ass throughs) at you			luding						
	□ Yes □ I	No									
		industry, describe nd probable polluta		luding dates, dura	ation, description						
	Click to enter text										

B. Non-substantial modifications

Section 3. Significant Industrial User (SIU) Information and Categorical Industrial User (CIU) (Instructions Page 90)

A. General information

	Company Name: <u>N/A</u>
	SIC Code: Click to enter text.
	Contact name: Click to enter text.
	Address: Click to enter text.
	City, State, and Zip Code: Click to enter text.
	Telephone number: <u>Click to enter text.</u>
	Email address: Click to enter text.
В.	Process information
	Describe the industrial processes or other activities that affect or contribute to the SIU(s) or CIU(s) discharge (i.e., process and non-process wastewater).
	Click to enter text.
C.	Product and service information
C.	Product and service information Provide a description of the principal product(s) or services performed.
C.	
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
C.	Provide a description of the principal product(s) or services performed.
	Provide a description of the principal product(s) or services performed.
	Provide a description of the principal product(s) or services performed. Click to enter text.
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater."
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: N/A
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: N/A
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: N/A Discharge Type: Continuous Batch Intermittent Non-Process Wastewater:
	Provide a description of the principal product(s) or services performed. Click to enter text. Flow rate information See the Instructions for definitions of "process" and "non-process wastewater." Process Wastewater: Discharge, in gallons/day: N/A Discharge Type: Continuous Batch Intermittent

Pretreatment standards
Is the SIU or CIU subject to technically based local limits as defined in the <i>i</i> nstructions?
□ Yes □ No
Is the SIU or CIU subject to categorical pretreatment standards found in 40 CFR Parts 405 - 471 ?
□ Yes □ No
If subject to categorical pretreatment standards , indicate the applicable category and subcategory for each categorical process.
Category: Subcategories: Click to enter text.
Click or tap here to enter text. Click to enter text.
Category: Click to enter text.
Subcategories: <u>Click to enter text.</u>
Category: Click to enter text.
Subcategories: <u>Click to enter text.</u>
Category: Click to enter text.
Subcategories: <u>Click to enter text.</u>
Category: Click to enter text.
Subcategories: <u>Click to enter text.</u>
Industrial user interruptions
Has the SIU or CIU caused or contributed to any problems (e.g., interferences, pass through, odors, corrosion, blockages) at your POTW in the past three years?
□ Yes □ No
If yes , identify the SIU, describe each episode, including dates, duration, description of problems, and probable pollutants.
Click to enter text.

E.

F.

WORKSHEET 7.0

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

CLASS V INJECTION WELL INVENTORY/AUTHORIZATION FORM

Submit the completed form to:

TCEQ IUC Permits Team Radioactive Materials Division MC-233 PO Box 13087 Austin, Texas 78711-3087 512-239-6466

For TCEQ Use Only
Reg. No
Date Received
Date Authorized

Section 1. General Information (Instructions Page 92)

1. TCEQ Program Area

Program Area (PST, VCP, IHW, etc.): <u>SADDS</u> Program ID: Municipal Wastewater Permitting

Contact Name: <u>Firoj Vahora</u> Phone Number: <u>512-239-4540</u>

2. Agent/Consultant Contact Information

Contact Name: <u>Jacob Valentien</u>, <u>PE</u> Address: 8701 N Mopac Exp Suite 320

City, State, and Zip Code: Austin, TX 78759

Phone Number: <u>512-485-0831</u>

3. Owner/Operator Contact Information

□ Owner ⊠ Operator

Owner/Operator Name: Municipal Operations Company, Inc

Contact Name: <u>Lonnie Wright</u> Address: 20141 Schiel Road

City, State, and Zip Code: Cypress, TX 77433

Phone Number: <u>281-367-5511</u> **Facility Contact Information**

4.

Facility Name: Hays County MUD No. 4 WWTP

Address: Click to enter text.

City, State, and Zip Code: Click to enter text.

Location description (if no address is available): Bush Ranch Phase 1, Block A, Lot 63

Facility Contact Person: Christopher Sanchez

Phone Number: <u>281-367-5511</u>

5. Latitude and Longitude, in degrees-minutes-seconds Latitude: 30.21024 Longitude: <u>97.98285</u> Method of determination (GPS, TOPO, etc.): GPS See Attachment 4 Attach topographic quadrangle map as attachment A. 6. **Well Information** Type of Well Construction, select one: Vertical Injection Subsurface Fluid Distribution System **Infiltration Gallery Temporary Injection Points** Other, Specify: Click to enter text. Number of Injection Wells: Click to enter text. 7. **Purpose** Detailed Description regarding purpose of Injection System: Disposal of treated effluent to irrigate drip fields. Attach a Site Map as Attachment B (Attach the Approved Remediation Plan, if appropriate.) Water Well Driller/Installer 8. Water Well Driller/Installer Name: N/A City, State, and Zip Code: Click to enter text. Phone Number: Click to enter text.

Phone Number: <u>Click to enter text.</u> License Number: <u>Click to enter text.</u>

Section 2. Proposed Down Hole Design

Attach a diagram signed and sealed by a licensed engineer as Attachment C.

Table 7.0(1) - Down Hole Design Table

Name of String	Size	Setting Depth	Sacks Cement/Grout - Slurry Volume - Top of Cement	Hole Size	Weight (lbs/ft) PVC/Steel
Casing			N/A		
Tubing					
Screen					

Section 3. Proposed Trench System, Subsurface Fluid Distribution System, or Infiltration Gallery

Attach a diagram signed and sealed by a licensed engineer as Attachment D.

System(s) Dimensions: N/A
System(s) Construction: N/A

Section 4. Site Hydrogeological and Injection Zone Data

- 1. Name of Contaminated Aquifer: N/A
- 2. Receiving Formation Name of Injection Zone: N/A
- **3.** Well/Trench Total Depth: <u>6"</u>
- 4. Surface Elevation: <u>Varies</u>
- **5.** Depth to Ground Water: >300'
- **6.** Injection Zone Depth: <u>N/A</u>
- 7. Injection Zone vertically isolated geologically? ☐ Yes ☒ No Impervious Strata between Injection Zone and nearest Underground Source of Drinking Water:

Name: Click to enter text.

Thickness: Click to enter text.

- **8.** Provide a list of contaminants and the levels (ppm) in contaminated aquifer Attach as Attachment E.
- **9.** Horizontal and Vertical extent of contamination and injection plume Attach as Attachment F.
- **10.** Formation (Injection Zone) Water Chemistry (Background levels) TDS, etc. Attach as Attachment G.
- **11.** Injection Fluid Chemistry in PPM at point of injection Attach as Attachment H.
- 12. Lowest Known Depth of Ground Water with < 10,000 PPM TDS: N/A
- 13. Maximum injection Rate/Volume/Pressure: <u>o.61 gph per emitter @ 60 psi</u>
- **14.** Water wells within 1/4 mile radius (attach map as Attachment I): N/A
- 15. Injection wells within 1/4 mile radius (attach map as Attachment J): N/A
- 16. Monitor wells within 1/4 mile radius (attach drillers logs and map as Attachment K): N/A
- 17. Sampling frequency: N/A
- 18. Known hazardous components in injection fluid: N/A

Section 5. Site History

- 1. Type of Facility: N/A
- **2.** Contamination Dates: Click to enter text.
- 3. Original Contamination (VOCs, TPH, BTEX, etc.) and Concentrations (attach as Attachment L): <u>Click to enter text.</u>
- **4.** Previous Remediation (attach results of any previous remediation as attachment M): Click to enter text.

NOTE: Authorization Form should be completed in detail and authorization given by the TCEQ before construction, operation, and/or conversion can begin. Attach additional pages as necessary.

Class V Injection Well Designations

- 5A07 Heat Pump/AC return (IW used for groundwater to heat and/or cool buildings)
- 5A19 Industrial Cooling Water Return Flow (IW used to cool industrial process equipment)
- 5B22 Salt Water Intrusion Barrier (IW used to inject fluids to prevent the intrusion of salt water into an aquifer)
- 5D02 Storm Water Drainage (IW designed for the disposal of rain water)
- 5D04 Industrial Stormwater Drainage Wells (IW designed for the disposal of rain water associated with industrial facilities)
- 5F01 Agricultural Drainage (IW that receive agricultural runoff)
- 5R21 Aquifer Recharge (IW used to inject fluids to recharge an aquifer)
- 5S23 Subsidence Control Wells (IW used to control land subsidence caused by ground water withdrawal)
- 5W09 Untreated Sewage
- 5W10 Large Capacity Cesspools (Cesspools that are designed for 5,000 gpd or greater)
- 5W11 Large Capacity Septic systems (Septic systems designed for 5,000 gpd or greater)
- 5W12 WTTP disposal
- 5W20 Industrial Process Waste Disposal Wells
- 5W31 Septic System (Well Disposal method)
- 5W32 Septic System Drainfield Disposal
- 5X13 Mine Backfill (IW used to control subsidence, dispose of mining byproducts, and/or fill sections of a mine)
- 5X25 Experimental Wells (Pilot Test) (IW used to test new technologies or tracer dye studies)
- 5X26 Aguifer Remediation (IW used to clean up, treat, or prevent contamination of a USDW)
- 5X27 Other Wells
- 5X28 Motor Vehicle Waste Disposal Wells (IW used to dispose of waste from a motor vehicle site These are currently banned)
- 5X29 Abandoned Drinking Water Wells (waste disposal)

Hays County Municipal Utility District No. 4

TCEQ Domestic Wastewater Permit Renewal Application

List of Attachments

Attachment #1 − TCEQ Core Data Form

Attachment #2 — Plain Language Summary Template

Attachment #3 — Effluent Disposal Site Owners

Attachment #4 — USGS Map

Attachment #5 — Proposed Flows by Phase

Attachment #6 — Treatment Process Description

Attachment #7 — Treatment Units

Attachment #8 — Process Flow Diagrams

Attachment #9 — Site Drawing

Attachment #10 — TCEQ Approval Letter for Drip Field Expansion

Attachment #11 - TCEQ Approval Letters

Attachment #12 — Pollutant Analysis of Treated Effluent

Attachment #13 — Sludge Acceptance Agreement

Attachment #14 — TCEQ Approval Letters for 210 Beneficial Reuse

Attachment #15 — Annual Cropping Plan

Attachment #16 — Soil Map

Attachment #17 — Soil Analysis

Attachment #18 — Excursions Details

Attachment #19 — Wind Rose

Westwood

ATTACHMENT #1 - CORE DATA FORM



TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

		nission (If other is	-		-	-						
		stration or Author							the progr	am app	plication.)	
 □ Renewal (Core Data Form should be submitted with the renewal form) □ Other 2. Customer Reference Number (if issued) Follow this link to 3. Regulated Entity Reference Number (if issued) 										show (if issued)		
2. Custome	er Keiere	ence Number (II	issuea)	<u>Follow this link to</u> <u>search for CN or RN</u>		RN	3. Ke	guiat	ea Enuty	Kerei	rence Nun	nber (if issuea)
CN 6026	590661			numbers Regis	in Cent stry**	<u>tral</u>	rn 103897567					
SECTIO	N II:	<u>Customer</u>	Inforr	<u>mation</u>	L							
4. General Customer Information 5. Effective Date for Customer Information Updates (mm/dd/yyyy)												
☐ New Cust☐ Change in		me (Verifiable with		date to Cust Secretary of				ptrolle		_	-	l Entity Ownership
		ne submitted he State (SOS) or T	-	-			-			currei	nt and act	ive with the
6. Custome	er Legal	Name (If an indiv	idual, print	last name fi	rst: eg:	: Doe, J	ohn)	If ne	w Custome	er, ente	r previous (Customer below:
Hays (County	Municipal Uti	lity Distri	ct No. 4								
7. TX SOS/	CPA Fili	ng Number	8. TX Sta	te Tax ID	(11 dig	gits)		9. Fe	e deral Ta gits)	x ID	10. DUN applicable	S Number (if
11. Type o	f Custon	ner: Corpor	ation				Indiv	idual		Partn	ership: 🔲 (General 🗌 Limited
Government	: 🗌 City [☐ County ☐ Fede	ral 🗌 Local	☐ State 🛚	Other	r 🗆] Sole I	Proprie	etorship	☐ Ot	her:	
12. Number 12. 0-20	r of Emp] 21-100		251-500	☐ 501 a	nd higl	her		13. I □ Ye		lently		nd Operated?
14. Custon	ier Role	(Proposed or Actu	al) <i>- as it re</i>	lates to the	Regula	ated En	tity list	ed on t	his form.	Please (check one o	f the following
□Owner □Occupatio	nal Licen	☐ Operato				& Oper SA App			Other	:		
15.	3321	Bee Caves F	load, Su	ite 203								
Mailing												
Address:	City	Austin		State	State TX		ZIP	78746			ZIP + 4	
16. Countr	y Mailin	g Information (i	f outside US.	A)					ess (if app)	
								mbk	firm.cor			
18. Teleph				19. Extension or Code			e	20. Fax Number (if applicable)				cable)
(512) 615	- 0503								()	-		
SECTIO	V III:	Regulate	<u>d Entit</u>	ty Info	rma	<u>atio</u>	<u>n</u>					
21. Genera ☐ New Regu		ted Entity Informity Update to							ew permit ed Entity I			required.)
The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).												
22. Regula	22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)											
Hays (County	Municipal Uti	lity Distri	ct No. 4								

TCEQ-10400 (11/22) Page 1 of 2

23. Street Address of the Regulated Entity:												
(No PO Boxes)	City		State		ZIP			ZIP + 4				
24. County			I			1						
]	If no Street	Address is provi	ded, field	ls 25-28 aı	re requi	ired.					
_o. z coerrp don to		•	050 feet north f US 290 with					•	les west of			
26. Nearest City					1	State		Nea	rest ZIP Code			
Dripping Springs						TX		787				
Latitude/Longitude a Physical Address ma				e none h	ave been p	provide	d or to ga	iin accura	cy).			
27. Latitude (N) In De		30.21024			Longitude			97.982				
Degrees 30	Minutes	10	Seconds	Deg		1	Minutes 58	<u> </u>	Seconds			
29. Primary SIC Code		12 D. Secondary	36.87	21 Drin	97 nary NAIC	Code			58.26 IAICS Code			
(4 digits)		digits)	sic code	(5 or 6 d		.5 Coue	(5 or 6		AICS Code			
4952					22132							
33. What is the Prima	ry Busin	ess of this e	entity? (Do not r	epeat the S	SIC or NAIC	S descrip	otion.)					
24 Mailing		3321 Bee Caves, Suite 203										
34. Mailing Address:												
riddi cosi	City	Austin	State	TX	ZIP	7	8746	ZIP + 4				
35. E-Mail Address:				MKuta	c@mbkf	irm.co	m					
36. Telephone Numb	er		37. Extension	or Code	38.	Fax Nui	mber (if a	pplicable)				
(512) 615- 0503					() -						
9. TCEQ Programs and pdates submitted on this	l ID Num form. See	lbers Check a the Core Data	all Programs and wi a Form instructions	rite in the p for additio	permits/reg onal guidan	istration ce.	numbers t	that will be	affected by the			
☐ Dam Safety	☐ Di	stricts	☐ Edwards Aquife	er	☐ Emissio	ons Inve	ntory Air	☐ Industr Waste	rial Hazardous			
☐ Municipal Solid Wast		ew Source w Air	□ OSSF		☐ Petrole	um Stora	age Tank	☐ PWS				
	Revie											
☐ Sludge	☐ St	orm Water	☐ Title V Air		☐ Tires			☐ Used C	il			
☐ Voluntary Cleanup	X W	astewater	☐ Wastewater Agricult		ture		☐ Other:					
	WQ0	014309001										
SECTION IV: P	repar	er Info	<u>rmation</u>									
40. Name: Jacob V	alentier	n, PE		41. Tit	le: Seni	or Pro	ject Maı	nager				
42. Telephone Numbe			4. Fax Number	45. E-	Mail Addr							
(512) 485-0831		() -	jacob	valentie	en@we	estwood	lps.com				
SECTION V: A												
	UTNOF	ized Sid	Inatiire									
6. By my signature below		-		t the infor	mation pro	vided in	this form i	s true and a	complete, and			

Company:	Hays County MUD No. 4	t Engineer			
Name (In Print):	Print): Jacob Valentien, PE				(512) 485-0831
Signature:	Jacob Valentin			Date:	08/28/2024

TCEQ-10400 (11/22) Page 2 of 2

Westwood

ATTACHMENT #2 – PLAIN LANGUAGE SUMMARY

TCEQ

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

PLAIN LANGUAGE SUMMARY FOR TPDES OR TLAP PERMIT APPLICATIONS

Plain Language Summary Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary as required by <u>Title 30, Texas Administrative Code (30 TAC), Chapter 39, Subchapter H</u>. Applicants may modify the template as necessary to accurately describe their facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how the applicant will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements.

If you are subject to the alternative language notice requirements in 30 TAC Section 39.426, you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package. For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS DOMESTIC WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Hays County MUD No. 4 (C6026906612) operates Hays County MUD No. 4 Wastewater Treatment Plant (RN103897567), a public wastewater treatment facility. The facility is located at Ledge Stone subdivision, in Austin, Hays County, Texas 78737. This application will apply for the renewal of the existing permit for land application of treated wastewater effluent onto defined areas within the district's boundaries. This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are expected to contain no significant amount of pollutants. Wastewater is discharged in the form of treated effluent for irrigation or stored in a sludge dewatering box and hauled to a license facility and is treated by aeration, clarification, chlorination and chlorine contact.

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

AGUAS RESIDUALES Introduzca 'INDUSTRIALES' o 'DOMÉSTICAS' aquí /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

Hays County MUD No. 4 (C6026906612)) opera la Planta de Tratamiento de Aguas Residuales Hays County MUD No. 4 RN103897567), una instalación pública de tratamiento de aguas residuales. La instalación está ubicada en la subdivisión Ledge Stone, en Austin, Condado de Hays, Texas 78737. Esta solicitud se aplicará para la renovación del permiso existente para la aplicación de tierra del efluente de aguas residuales tratadas en áreas definidas dentro de los límites del distrito.. Este permiso no autorizará una descarga de contaminantes en el agua en el estado.


Se espera que las descargas de la instalación contengan se espera que no contenga una cantidad significativa de contaminantes. Las aguas residuales se descargan en forma de efluente. está tratado por riego o se almacenan en una caja de deshidratación de lodos y se transportan a una instalación con licencia y se tratan mediante aireación, clarificación, cloración y contacto con cloro.

 ${\bf ATTACHMENT~\#_3-EFFLUENT~DISPOSAL~SITE~OWNERS}$

Attachment 3 Effluent Disposal Site Owners

Hays County Municipal Utility District No. 4 3321 Bee Caves Road, Suite 203 West Lake Hills, Texas 78746 (512) 615 - 0503

ATTACHMENT #4 – USGS MAP



ATTACHMENT #5 – Proposed Flows by Phase

Hays County MUD No. 4 WQ0014309-001 Domestic Wastewater Permit Renewal Application

Attachment #5 Proposed Flows by Phase

Permit Phase	WWTP Phasing (GPD)	Outfall 1 Subsurface Irrigation Phase (GPD)	Total Irrigation (GPD)
Interim Phase II	100,000	100,000	100,000
Final Phase	150,000		

ATTACHMENT #6 - TREATMENT PROCESS DESCRIPTION

Hays County MUD No. 4 WQ0014309-001 Domestic Wastewater Permit Renewal Application

Attachment #6 Treatment Process Description

Two train packaged, single stage nitrification, activated sludge process including headworks (bar screening/ flow splitting), aeration, clarification, chlorination, chlorine contact, and sludge dewatering box. Treated effluent will be stored in holding tanks prior to disposal, using subsurface drip irrigation near the treatment plant on land owned and leased by the applicant. Sludge will be disposed by hauling off-site, by a licensed hauler, to a permitted wastewater treatment plant or sludge processing facility.

ATTACHMENT #7 – TREATMENT UNITS


Hays County MUD No. 4 WQ0014309-001 Domestic Wastewater Permit Amendment Application With Major Amendment Technical Report 1.0

Attachment 10 Dimensions of Treatment Units

All Phases

Treatment Unit	Units	Dimensions
Manual Screen/ Flow Splitter	1	1/4" Bars w/ 1" Spacers
Aeration Basin	2	12' x 28' x 10.5'
Clarification	2	18' Diameter x 10.5' Deep
Chlorine Contact	2	12' x 5' x 9'
Sludge Dewatering Box	1	23.42' x 8.5' x 7.33'

ATTACHMENT #8 – FLOW PROCESS DIAGRAMS




ATTACHMENT #9 – SITE DRAWING





EMD



estwoo Westwood Professional Services, Inc.

Phone (512) 485-0831

Toll Free (888) 937-5150

8701 N. Mopac Expy, Suite 320

Austin, TX 78759 westwoodps.com

SCALE DRAWN BY CHECKED BY JWV

08/07/2024 1"=2000'

JOB NUMBER R0052766 HAYS COUNTY MUD NO.4 ATTACHMENT 9 - SITE DRAWING

TPBE FIRM REGISTRATION NO. F-11756 TBPLS FIRM REGISTRATION NO. LS-10074301

ATTACHMENT #10 – TCEQ APPROVAL FOR DRIP FIELD EXPANSION

Jon Niermann, *Chairman* Emily Lindley, *Commissioner* Bobby Janecka, *Commissioner* Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

September 21, 2022

James F. Prochaska, M.S., P.E. Lighthouse Water Resource Engineering, LLC P.O. Box 5667 Bryan, Tx 77805

Re:

Hays County MUD 4

Phase II Drip Irrigation System Expansion To 100,000 Gpd

Permit No. Wqoo14309-001 WWPR Log No. 0622/026 Cn602690661, Rn103897567

Hays County

Dear Mr. Prochaska:

We have received the project summary transmittal letter dated June 5, 2022. The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, Design Criteria for Wastewater Systems.

The project consists of adding seventeen new drip irrigation zone for a total of 252,084 square feet on 5.786 acres. This will expand the treatment/disposal capacity of the treatment plant to 100,000 gallons per day. Based on our review the expand is approved.

Below are provisions of the Chapter 217 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

• You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §217.6(d). Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 217.

James F. Prochaska, M.S., P.E. Page 2 September 21, 2022

• Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

If you have any questions or if we can be of any further assistance, please call me at (512) 239-4552.

Sincerely,

Louis C. Herrin, III, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

LCHIII/tc

cc: TCEQ, Region 11 Office

Jon Niermann, *Chairman*Emily Lindley, *Commissioner*Bobby Janecka, *Commissioner*Toby Baker, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

December 3, 2020

Robert P. Callegari, P.E. CMA ENGINEERING INC. 235 Ledge Stone Drive Austin, TX 78737

Re:

Hays County MOD 4
Phase II Drip Irrigation System Expansion to 100,000 GPD
Permit No. WQ0014309-001
WWPR Log No. 1220/015
CN602690661, RN103897567
Hays County

Dear Mr. Callegari:

We have received the project summary transmittal letter dated 11/19/2020.

The tules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, Design Criteria for Wastewater Systems.

Section 217.6(d), relating to case-by-case reviews, states in part that upon submittal of a summary transmittal letter, the executive director may approve of the project without reviewing a complete set of plans and specifications.

Under the authority of §217.6(e) a technical review of complete plans and specifications is not required. However, the project proposed in the summary transmittal letter is approved for construction. Please note, that this conditional approval does not relieve the applicant of any responsibilities to obtain all other necessary permits or authorizations, such as wastewater treatment permit or other authorization as required by Chapter 26 of the Texas Water Code. Below are provisions of the Chapter 217 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §217.6(c). Additionally, the engineering report must include all constants, graphs,

Robert P. Callegari, P.E. Page 2 December 3, 2020

equations, and calculations needed to show substantial compliance with Chapter 217. The items which shall be included in the summary transmittal letter are addressed in $\S217.6(c)(1)-(10)$.

- Any deviations from Chapter 217 shall be disclosed in the summary transmittal letter and the technical justifications for those deviations shall be provided in the engineering report. Any deviations from Chapter 217 shall be based on the best professional judgement of the licensed professional engineer sealing the materials and the engineer's judgement that the design would not result in a threat to public health or the environment.
- Any variance from a Chapter 217 requirement disclosed in your summary transmittal letter is approved. If in the future, additional variances from the Chapter 217 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting a written approval to the variance from the rules for the specific project and the specific circumstances.
- Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of 30 TAC §217.7(a) of the rules which states, "Approval given by the executive director or other authorized review authority does not relieve an owner of any liability or responsibility with respect to designing, constructing, or operating a collection system or treatment facility in accordance with applicable commission rules and the associated wastewater permit".

If you have any questions or if we can be of any further assistance, please call me at (512) 239-4552.

Sincerely

Louis C. Herrin, III, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

LCHIII/tc

cc: TCEQ, Region 11 Office

ATTACHMENT #11 – TCEQ APPROVAL LETTERS

Kathleen Hartnett White, Chairman R. B. "Ralph" Marquez, Commissioner Larry R. Soward, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

March 27, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Highway 290, Bldg. 600 Austin, Texas 78737

Re: 194 Bush, Ltd.

TCEQ Permit No. WQ0014309001 (CN601457716, RN103897567)

Dear Mr. Callegari:

We acknowledge receipt of your letter dated March 10, 2006 with attachments proposing to revise the permitted drip irrigation area alignment within the permittee's property without change in acreage or location.

Your letter indicates that the vegetation, soil type and depth and topography will remain the same. Mr. Mike Chadwick of the TCEQ Water Quality Assessment Team evaluated your request and does not pose any objection to the proposed revision. Hence, the irrigation area for the subject permit shall be as shown in Attachment A of this letter.

If you have any questions regarding this matter, please do not hesitate to contact me at (512) 239-4540 or if by correspondence include MC 148 in the letterhead address following my name.

Sincerely,

Firoj Valora, Team Leader Municipal Permits Team Wastewater Permitting Section

Yaho.

Water Quality Division

FV/ms

Enclosure

ccs: Mr. Michael Chadwick, TCEQ Water Quality Assessment Section, (MC 150)

TCEQ, Region 11

Kathleen Hartnett White, Chairman R. B. "Ralph" Marquez, Commissioner Larry R. Soward, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

March 27, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Highway 290, Bldg. 600 Austin, Texas 78737

Re: 194 Bush, Ltd.

TCEQ Permit No. WQ0014309001 (CN601457716, RN103897567)

Dear Mr. Callegari:

We acknowledge receipt of your letter dated March 10, 2006 with attachments proposing to revise the permitted drip irrigation area alignment within the permittee's property without change in acreage or location.

Your letter indicates that the vegetation, soil type and depth and topography will remain the same. Mr. Mike Chadwick of the TCEQ Water Quality Assessment Team evaluated your request and does not pose any objection to the proposed revision. Hence, the irrigation area for the subject permit shall be as shown in Attachment A of this letter.

If you have any questions regarding this matter, please do not hesitate to contact me at (512) 239-4540 or if by correspondence include MC 148 in the letterhead address following my name.

Sincerely,

Firoj Valora, Team Leader Municipal Permits Team

Wastewater Permitting Section


Water Quality Division

FV/ms

Enclosure

ccs: Mr. Michael Chadwick, TCEQ Water Quality Assessment Section, (MC 150)

TCEQ, Region 11



CMA Engineering, Inc.

Min)/1/309-20//14

Robert P. Callegari, P.E. Felix J. Manka, P.E.

June 22, 2006

Louis C. Herrin, III, P.E.
Texas Commission on Environmental Quality
Wastewater Permitting Section
Plans and Specifications Review
MC-148
P.O. Box 13087
Austin, Texas 78711-3087

JULY 2 6 2006
WILST CONCENTIONS

Re: 194 Bush, Ltd.

Ledge Stone Development (Formerly Bush Ranch)

TCEO Permit No. 14309-001

Proposed Wastewater System Improvements

Phase 1 - 75,000 GPD Extended Aeration WWTP, 333,000 Gallon Effluent Holding Tank, 75,000 GPD Subsurface Drip Irrigation System, and Lift Stations 1 and 2

CMA Job Number 1177-001

Dear Plans and Specifications Reviewer:

Below is the information requested in Chapter 317.1(a)(3)(D) regarding submittal requirements for new domestic sewage collection, treatment, and disposal systems. Please note that an Engineering Report has been previously submitted as part of the permit application.

- (i) Name and address of the design firm: CMA Engineering, Inc., 14101 West Highway 290, Building 600, Austin, Texas 78737.
- (ii) Name, phone number and facsimile number of the design engineer:
 - 75,000 GPD wastewater treatment plant, 333,000 gallon effluent holding tank, Lift Stations 1 and 2, and force mains: Robert P. Callegari, P.E. (Texas Registration Number 68913), phone number 512/894-3230, facsimile 512/894-3225.
- (iii) County in which the project will be located with an identifying name for the project: Hays County, 294 Ranch, Ltd., 75,000 GPD Extended Aeration WWTP, 333,000 gallon effluent holding tank, 75,000 GPD Subsurface Drip Irrigation System, and Lift Stations 1 and 2.
- (iv) Name of the entity which proposes to own, operate, and maintain the project through its design life: The facility is owned by 294 Bush, Ltd. and will serve Hays County MUD No. 4. The owner has not selected a operator for the facilities to perform contract operations of the wastewater facilities.

Louis C. Herrin, III, P.E. Texas Commission on Environmental Quality Wastewater Permitting Section Plans and Specifications Review June 22, 2006 Page 2

- (v) Permit name and permit number of the relevant wastewater treatment facility: 194 Bush, Ltd., TCEQ Permit No. 14309-001.
- (vi) CMA verifies that the plans and specifications are in substantial compliance with all the requirements of Chapter 317.
- (vii) The purpose of the proposed wastewater system improvements is to provide wastewater service to the Ledge Stone development (formerly the Bush Ranch) within the boundaries of Hays County MUD No. 4. This project will consist of constructing a wastewater treatment plant, effluent holding tank, subsurface drip irrigation system, and two lift stations. TCEQ Permit Number 14309-001 allows for a two phase approach to wastewater treatment and disposal with the initial phase being 75,000 gallon per day (GPD) and the final phase being 150,000 GPD. More specifically, the project consists of the following:
 - 1. A 75,000 GPD extended aeration WWTP
 - 2. A 75,000 GPD subsurface drip irrigation system
 - 3. One 333,000 gallon effluent holding tank
 - 4. One duplex lift station (Lift Station No. 1) with a pumping capacity of approximately 68,750 GPD
 - 5. One duplex lift station (Lift Station No. 2) with a pumping capacity of approximately 34,000 GPD


-22-06

It is anticipated that construction for new WWTP and collection facilities will begin in August 2006. If you have any questions or comments please call me at 894-3230.

Very truly yours,

Robert P. Callegari, P.E. Principal

Xc: Phil Haag, Attorney for Hays County MUD No. 4 Mike Schoenfeld, 290 Ranch, Ltd. Ed McCarthy, Jackson, Sjoberg, McCarthy, & Wilson, L.L.P. TCEQ Region 11 Office Kathleen Hartnett White, Chairman Larry R. Soward, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

August 31, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Hwy 290, Bldg. 600 Austin, Texas 78737 SEP 07 2006

Re:

194 Bush, Ltd.

Proposed Wastewater System Improvements

Texas Commission on Environmental Quality Permit No. 14309-001

WWPR Log No. 0806/207 CN601457716 RN103897567

Hays County

Dear Mr. Callegari:

We have received the project summary transmittal letter dated June 22, 2006.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 317, of the Texas Commission on Environmental Quality (TCEQ) rules titled, <u>Design Criteria for Sewerage Systems</u>.

Section 317.1(a)(3)(D), relating to case-by-case reviews, states in part that upon submittal of a summary transmittal letter, the executive director may approve of the project without reviewing a complete set of plans and specifications.

Under the authority of §317.1(a)(3)(D) a technical review of complete plans and specifications is not required. However, the project proposed in the summary transmittal letter is approved for construction. Please note, that this conditional approval does not relieve the applicant of any responsibilities to obtain all other necessary permits or authorizations, such as wastewater treatment permit or other authorization as required by Chapter 26 of the Texas Water Code. Below are provisions of the Chapter 317 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

1. You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 317. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §317.1(c)-(d). Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 317. The items which shall be included in the summary transmittal letter are addressed in §317.1(a)(3)(D).

Mr. Robert P. Callegari, P.E. Page 2 August 31, 2006

- 2. Any deviations from Chapter 317 shall be disclosed in the summary transmittal letter and the technical justifications for those deviations shall be provided in the engineering report. Any deviations from Chapter 317 shall be based on the best professional judgement of the licensed professional engineer sealing the materials and the engineer's judgement that the design would not result in a threat to public health or the environment.
- 3. Any variance from a Chapter 317 requirement disclosed in your summary transmittal letter is approved. If in the future, additional variances from the Chapter 317 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting a written approval to the variance from the rules for the specific project and the specific circumstances.
- 4. Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of §317.1(a)(2) of the rules which states, "Approval given by the executive director...shall not relieve the sewerage system owner or the design engineer of any liabilities or responsibilities with respect to the proper design, construction, or authorized operation of the project in accordance with applicable commission rules."

If you have any questions or if we can be of any further assistance, please call me at (512) 239-4552.

Sincerely,

Louis C. Herrin, III, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

LCH/ms

cc: TCEQ, Region 11 Office

CMA Engineering, Inc.

RECEIVED
OCT 1 1 2006
MUNICIPAL PERINTS

Robert P. Callegari, P.E. Felix J. Manka, P.E.

Via facsimile (512)239-4430

October 6, 2006

Firoj Vahora
Wastewater Permitting Section (MC 148)
Water Quality Division
Texas Commission on Environmental Quality
P.O. Box 13087
Austin, Texas 78711-3087

Re:

194 Bush, Ltd.

Ledge Stone Development (Formerly Bush Ranch)

TCEQ Permit No. 14309-001

Request for WWTP Process Change

CMA Job Number 1177-001


Dear Firoj:

We are proposing to change the wastewater treatment plant (WWTP) process for the above referenced facility. The General Description of permit states that "The wastewater treatment facilities consist of an activated sludge process plant using the extended aeration mode in the interim and final phases. Treatment units in the interim phase will include a 0.075 millions gallons per day (MGD) module consisting of an aeration basin, a final clarifier, and aerobic digester and a chlorine contact chamber. Treatment units in the final phase will include and additional 0.075 MGD module."

We are proposing to change the process from the extended aeration mode of the activated sludge process to single stage nitrification. Treatment unit will still consist of a bar screen, an aeration basin, final clarifier, aerobic digester, and a chlorine contact chamber, but the mode of operation will change. The WWTP will be designed with a peaking factor of 4.0. Attached are the unit sizing calculations for the single stage nitrification WWTP. The plant will be designed so that the effluent requirements of 20 mg/L BOD and 20 mg/L TSS will be met.

The location of the WWTP will be as originally permitted and all TCEQ buffers will be met. Attached are exhibits A & B of the WWTP site layout. Exhibit A shows the permitted WWTP buffer zone map and Exhibit B shows the buffer zone map of the proposed single stage nitrification WWTP.

It was previously planned that an emergency generator would supply auxiliary power to the wastewater plant and onsite lift station; however, we are now requesting an acceptable alternative to auxiliary power for the WWTP. As of April 2006, the longest outage in the last 2 years has been 128 minutes which occurred in August 2004. In the initial phase, the influent wet well at



Firoj Vahora TCEQ Municipal Permits Team TCEQ Permit No. 14309-001 October 6, 2006 Page 2 of 2

the WWTP site will be sized so that there will be no discharge of untreated wastewater during the longest outage in the past 24 months. In addition, this wastewater treatment facility utilizes subsurface drip irrigation for the disposal of treated effluent, and utilizes an effluent holding tank with a minimum two days of storage at the maximum permitted flow. In the event of an outage, raw wastewater would not be pumped to the WWTP from the onsite lift station. In addition, air would not be supplied to the WWTP. For the duration of the outage, the plant would sit idle. The lack of air to the WWTP during such an outage would not greatly affect treatment. When power is restored and the WWTP is back in service, any wastewater that will be pumped to the WWTP during an outage will go directly to the aeration basin, which would flow through the clarifier, to the chlorine contact chamber, and then to the effluent holding tank. Any effluent leaving the chlorine contact chamber will have been treated.

Please note that this facility was approved for construction on August 31, 2006 (see attached letter).

Thank you for attention to this matter. It is anticipated that construction for new WWTP and collection facilities will be completed in April of 2006. If you have any questions or comments, please call me at 894-3230.

Very truly yours,

Robert P. Callegari, P.E.

Principal

Attachments

Xc: Phil Haag, Attorney for Hays County MUD No. 4

Mike Schoenfeld, 290 Ranch, Ltd.

Ed McCarthy, Jackson, Sjoberg, McCarthy, & Wilson, L.L.P.

TCEQ Region 11 Office

LEDGESTONE SUBDIVISION

Hays County MUD No. 4

WWTP Design Calculations

Final Phase - 0.075 MGD WASTEWATER TREATMENT PLANT DESIGN SINGLE STAGE NITRIFICATION



BASIC DESIGN PARAMETERS:

Final Phase:

Design Flow: 2-Hour Peak Flow (4 x Design Flow):

BODs:

TSS:

0.0750 MGD 0.300 MGD

> 208 GPM 200 mg/l

200 mg/l

125 lbs/day 125 lbs/day

PRELIMINARY TREATMENT:

Manually cleaned bar screen.

SINGLE STAGE NITRIFICATION:

Essential TNRCC Requirements:

Maximum Aerator Organic Loading = 35 lbs. BODs/ 1000cf/day Minimum Aerator Depth for Diffused Aeration = 8 ft.

35 IDS.BOD./1000ct/day

Required Aeration Volume (@35 lb influent BOD₅/1,000 cf): Volume Provided

3.571 cf

3,584 cf

ENHANCED SECONDARY CLARIFICATION:

Essential TNRCC Requirements:

Weir Loading for peak flows of 1.0 MGD or less: < 20,0000 g/ft/day Weir Loading for peak flows > 1.0 MGD: < 30,0000 g/ft/day

Solids Loading of floor: < 50 lbs. SS/ft2/day

Minimum Clarifier Side Water Depth (SWD) = 8 ft. - Use 10 ft for Design

When Diameter ≥ 40 ft., Minimum Clarifier Side Water Depth (SWD) = 10 ft

For Secondary with Clarifiers Having SWD ≥ 10 ft.:

Maximum Surface Loading Rate @ Peak 2-Hr Flow = Maximum Surface Loading Rate @ Design Flow = Minimum Detention Time @ Peak 2-Hr Flow = Minimum Detention Time @ Design Flow =

1200 g/day/sf 600 q/ft/day 1.5 hours

3 hours

Final Phase:

Required Volume (@ 1.5 Hr. D.T. for 2-Hr Peak Flow): 18,750 gal. 2.507 cf Required Surface Area (overflow rate of 1200 g/sf/day @ peak 250 sf Required Volume (@ 1200 g/sf/day @ peak flow w/ 10' SWD) 2,500 cf Required Volume (@ min detention time @ design flow): 9,375 gal 1,253 cf Minimum diameter (Volume x 4 ÷10 x π)0.5 17.84 ft. Minimum Weir Length Required 15 ft Volume Provided: 2.545 cf Diameter Provided: 18 ft.

DISINFECTION USING CHLORINE:

Essential TNRCC Requirements:

Minimum Detention Time @ Peak 2-Hr Flow = 20 Minutes

Rapid Mixing with G > 500/sec. & with Detention Time of 3 to 15

Seconds or the Contact Chamber Must Have a Flow Length to Width

Ratio ≥ 40 and a Flow Depth to Width Ratio of ≤ 1.

Final Phase:

Required Volume @ 20 Min. D. T. For Peak 2-Hr. Flow: 4.167 gal. 557 cf Volume Provided: 620 cf

CHLORINE FEEDER CAPACITY

Probable Chlorine Dose	7 to 9 mg/i
Final Phase:	

Chlorine Feed Rate (Use 9 mg/l to Averge Flow of 0.162 MGD): 5.6 PPD Chlorine Feed Rate (Use 9 mg/l to Peak Flow of 0.648 MGD): 0.9 PPH

WASTE SLUDGE PRODUCTION:

-				
	Assume 97.5% BOD ₅ Removal & 97.5% SS Removal ¹ :		0.9	0.9
	Assume 35% of BOD ₅ is Removed with SS Removal ² :	0.35	0.65	
	Assume 0.5 lbs SS Produced per lb BOD ₅ Removed ² :		0.5	
	Assume 80% of Secondary SS are Volatile ² :		0.8	
	Assume 65% of Primary SS are Volatile ² :		0.65	
	Assume 30% Reduction of Raw SS in Aeration	0.3	0.7	
	Assume 1.25% SS Concentration in Waste Sludge ² :		0.0125	
	Allow VSS loading of 0.055 lb/cf ² :		0.055	
4	Decedes Decided Filliand October 1 DOD 100			

1. Based on Required Effluent Quality of 20/20 mg/l - BOD₅/SS.

2. A reasonable estimate of BOD5 Removal from Wastewater Engineering by Metcalf & Eddy, Ten State Standards, and Others.

Percent of Interim Phase Flow Final Phase: 100% 75% 50%

Final Phase:	100%	75%	50%	25%
BOD Removed (lbs BOD/day)	113	84	56	28
Primary SS Removed (lb SS/day):	113	84	56	28
Primary VSS Removed (lb VSS/day):	73	55	37	18
Secondary SS Produced from BOD ₅ Removed (lb SS/day):	37	27	18	9
Secondary VSS Produced from BOD ₅ Removed (lb VSS/day):	29	22	15	7
Total SS Produced (lb SS/day):	115	86	58	29
Total VSS Produced (lb VSS/day):	102	77	51	26
Total SS Wasted (lb SS/day)	115	86	58	29
Total Volume SS Wasted (gal/day)	1,106	830	553	277

SLUDGE DIGESTION USING AEROBIC DIGESTION:

Essential TNRCC Requirements:

- I. Minimum Volume = 20 cf/lb of BODs
- II. Minimum Retention Time = 15 days.

Other accepted Design Requirements:

III. Volatile SS Loading (Wastewater Engineering by Metcalf & Eddy):

Final Phase:

Required Volume (Based on 20 cf/lb, BODs); 2.500 cf Required Volume (Based on 15 Days Sludge D. T.) 2.218 cf Required Volume (VSS Loading) 1.024 cf Volume Provided: 2,560 cf

DIGESTER SLUDGE DETENTION TIME:

Final Phase:

Hydraulic Retention Time:

17.31 Days

0.1 lbs/cf

DIGESTER SLUDGE REMOVAL SCHEDULE:

Based on 40% reduction of SS in Aerobic Digestion Assume Concentration of Sludge in Digester at 1.5% 0.6

	Pe	Percent of Phase Flow			
E. O. D. Service	100%	75%	50%	25%	
Final Phase: Days between Sludge Removal:	34	46	69	138	

AIR REQUIREMENTS:

AERATION USING COARSE-BUBBLE DIFFUSED AERATION:

Essential TNRCC Requirements for Nitrification:

- ≥ 2.2 lbs. O₂/lb. BOD₅
- ≥ 3200 scf Air/lb. BOD₅ (Based on 4.0% O₂ T.E.)
- ≥ 2110 scf Air/lb. BOD₅ (By Ashbrook Certified Efficiency of 9.3% O₂ T.E. clean water at 13.75 ft Submergence) {(1lb. BOD₅ x2.2 lbs. O₂/lb. BOD₅)/(0.01725 lbs. O₂/cf air x 0.093 x 0.65 transfer efficiency)=2110 scfm/lb BOD.

Final Phase:

Required Air Volume (@ 4.0% O2 T.E.): 278 scfm Required Air Volume (@ 9.3% O2 T.E. @ 13.75 ft. submergence

and 25 scfm, by Ashbrook):

183 scfm

30 scfm/1000cf

AEROBIC DIGESTION:

Essential TNRCC Requirements:

≥ 30 scfm/1,000 cf of Digester Volume

Final Phase:

Required Air Volume: 77 sctm

AIR LIFT PUMPING (Manufacuter Recommendation):

Final Phase:

Required Air Volume: 60 scfm

CHLORINE BASIN AGITATION:


= 5 scfm/1,000 cf of Basin Volume 5 scfm/1000cf


Final Phase:

Required Air Volume: 3 scfm

MINIMUM TOTAL AIR REQUIRED:

Interim Phase: (Based on Manf. Certified 9.3% O2 T.E.) 323 scfm





Kathleen Hartnett White, Chairman Larry R. Soward, Commissioner Martin A. Hubert, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

November 10, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Highway 290, Bldg. 600 Austin, Texas 78737

Re:

194 Bush, Ltd., TCEQ Permit No. WQ0014309001 (CN601457716, RN103897567)

Dear Mr. Callegari:

We acknowledge receipt of your letter dated October 6, 2006 proposing a change in the mode of operation of the activated sludge plant from extended aeration, as stated in the permit, to a single stage nitrification. We understand that there no other changes in the permit. We pose no objection to the proposed change.

When an application for permit renewal is filed, please make a note in the application that a renewal with changes is being requested and refer to your letter of October 6, 2006 and this letter as supporting documents. Please provide a separate letter of notification of this change to Mr. Louis C. Herrin III, P.E., to amend your summary transmittal letter of June 22, 2006. As regards auxiliary power, we recommend that the on-site lift station and the wastewater treatment facility be wired to accept a generator in the event of power outages longer than anticipated.

We notice that your letter states that the construction of the new wastewater treatment facility and collection is expected to be completed by April of 2006. Craig Gonzales of your office verified that this should be April 2007. In this regard, please be reminded of the notification requirements of the current permit and the approval letter dated August 31, 2006 for the proposed project described in the June 22, 2006 summary transmittal letter.

If you have any questions regarding this matter, please do not hesitate to contact me at (512) 239-4540 or if by correspondence include MC 148 in the letterhead address following my name.

Sincerely.

Firoj Vabora, Team Leader Municipal Permits Team

Vahos

Water Quality Division

FV/JDC/sp

cc:

Mr. Louis C. Herrin III, P.E., Wastewater Permitting Section (MC 148)

TCEQ Region 11

CMA Engineering, Inc.

NOP/017

Robert P. Callegari, P.E. Felix J. Manka, P.E.

November 15, 2006

Louis C. Herrin, III, P.E.
Texas Commission on Environmental Quality
Wastewater Permitting Section
Plans and Specifications Review
MC-148
P.O. Box 13087
Austin, Texas 78711-3087

RECEIVED

NOV 21 2006

WASTEWATER PLANS AND SPECIFICATIONS

Re:

194 Bush, Ltd.

Ledge Stone Development (Formerly Bush Ranch)

TCEQ Permit No. 14309-001

Proposed Wastewater System Improvements

Phase 1 - 75,000 GPD Extended Aeration WWTP, 333,000 Gallon Effluent Holding

Tank, 75,000 GPD Subsurface Drip Irrigation System, and Lift Stations 1 and 2

CMA Job Number 1177-001

Dear Louis:

As requested by Mr. Firoj Vahora via his November 10, 2006 letter (attached), we are notifying you of the change in mode of operation of the above referenced WWTP from the extended aeration to single stage nitrification. Treatment units will still consist of a bar screen, an aeration basin, final clarifier, aerobic digester, and a chlorine contact chamber, but the mode of operation will change. Please accept this letter as an amendment to our June 2, 2006 summary transmittal letter (also attached).

Construction for new WWTP facilities will begin this month and are expected to be completed in April 2007. If you have any questions or comments please call me at 894-3230.

Very truly yours.

Robert P. Callegari, P.E.

Principal

Attachments

Xc: Phil Haag, Attorney for Hays County MUD No. 4


Mike Schoenfeld, 290 Ranch, Ltd.

Ed McCarthy, Jackson, Sjoberg, McCarthy, & Wilson, L.L.P.

TCEQ Region 11 Office

14101 West Highway 290, Bldg. 600 Phone: (512) 894-3230

Austin, Texas 78737 Fax: (512) 894-3225 Kathleen Hartnett White, Chairman Larry R. Soward, Commissioner Martin A. Hubert, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

December 20, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Highway 290, Bldg. 600 Austin, Texas 78737 RECEIVED

JAN 12 2007

CENTRALFILEROOM

Re:

Ledge Stone, Ltd.

Proposed Wastewater System Improvements

Texas Commission on Environmental Quality Permit No. 14309-001

WWPR Log No. 1206/017 CN601457716 RN103897567

Hays County

Dear Mr. Callegari:

We have received the project summary transmittal letter dated November 15, 2006.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 317, of the Texas Commission on Environmental Quality (TCEQ) rules titled, <u>Design Criteria for Sewerage Systems</u>.

Section 317.1(a)(3)(D), relating to case-by-case reviews, states in part that upon submittal of a summary transmittal letter, the executive director may approve of the project without reviewing a complete set of plans and specifications.

Under the authority of §317.1(a)(3)(D) a technical review of complete plans and specifications is not required. However, the project proposed in the summary transmittal letter is approved for construction. Please note, that this conditional approval does not relieve the applicant of any responsibilities to obtain all other necessary permits or authorizations, such as wastewater treatment permit or other authorization as required by Chapter 26 of the Texas Water Code. Below are provisions of the Chapter 317 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

1. You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 317. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §317.1(c)-(d). Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 317. The items which shall be included in the summary transmittal letter are addressed in §317.1(a)(3)(D).

- 2. Any deviations from Chapter 317 shall be disclosed in the summary transmittal letter and the technical justifications for those deviations shall be provided in the engineering report. Any deviations from Chapter 317 shall be based on the best professional judgement of the licensed professional engineer sealing the materials and the engineer's judgement that the design would not result in a threat to public health or the environment.
- 3. Any variance from a Chapter 317 requirement disclosed in your summary transmittal letter is approved. If in the future, additional variances from the Chapter 317 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting a written approval to the variance from the rules for the specific project and the specific circumstances.
- 4. Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of §317.1(a)(2) of the rules which states, "Approval given by the executive director...shall not relieve the sewerage system owner or the design engineer of any liabilities or responsibilities with respect to the proper design, construction, or authorized operation of the project in accordance with applicable commission rules."

If you have any questions or if we can be of any further assistance, please call me at (512) 239-4552.

Sincerely,

Louis C. Herrin, III, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

LCH/ms

cc: TCEQ, Region 11 Office

Bryan W. Shaw, Ph.D., Chairman Carlos Rubinstein, Commissioner Toby Baker, Commissioner Zak Covar, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

October 12, 2012

ROBERT P. CALLEGARI, P.E. CMA ENGINEERING INC. 235 LEDGE STONE DRIVE AUSTIN, TEXAS 78737

Re: HAYS COUNTY MUD NO. 4
NUISANCE ODOR PREVENTION AND NOISE ABATEMENT PLAN
PERMIT NO. WQ0014309-001
WWPR LOG NO. 0612/029
CN601457716 RRN103897567
HAYS COUNTY

Dear Mr. Callegari:

On June 14, 2012, the Texas Commission on Environmental Quality (TCEQ) received a Nuisance Odor Prevention and Noise Abatement Plan (Plan), dated June 13, 2012, for the Hays County Municipal District No. 4 Wastewater Treatment Plant (WWTP) in Hays County which included:

- Summary of WWTP operations and sources of odor;
- Discussions of climatic conditions and surrounding land uses;
- WWTP Buffer Zone map;
- Proposed 210 Reuse Areas map; and
- Wind Rose Data from nearby Austin Airport (Station 13958);

The review of this Plan identified a need for a variance from the buffer zones specifically: the 146-foot distance from the onsite lift station to the western property line which exceeds the 150-foot requirement [30 TAC §309.13(e)]. In order to mitigate the existing encroachment, the Plan proposes to use activated carbon canisters at the lift station's vent.

This review of the Plan grants conditional approval of this variance request. However; if the activated carbon canisters are ineffective in preventing odor or noise complaints the issue may be reopened.

Mr. Callegari, P.E. Page 2 10/12/12

If you have any comments or questions, please contact me at (512) 239-0486, or email at <u>ron.crane@tceq.texas.gov</u>; or Louis C. Herrin III, P.E. at (512) 239-4552.

Sincerely,

Ron Crane, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

RC/MC

cc: TCEQ, Region 11, Water Section

Bryan W. Shaw, Ph.D., P.E., Chairman
Toby Baker, Commissioner
Jon Niermann, Commissioner
Stephanie Bergeron Perdue, Interim Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

April 19, 2018

Mr. Robert P. Callegari, P.E. CMA Engineering Inc. 235 Ledge Stone Drive Austin, Texas 78737

Re:

Hays County Municipal Utility District 4

Hays County MUD No. 4, Sludge Dewatering Box Installation

Permit No. WQ0014309001 WWPR Log No. 0318/067 CN602690661, RN103897567

Hays County

Dear Mr. Callegari:

TCEQ received the project summary transmittal letter dated March 13, 2018.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, <u>Design Criteria</u> for Wastewater Systems.

Section 217.6(d), relating to case-by-case reviews, states in part that upon submittal of a summary transmittal letter, the executive director may approve of the project without reviewing a complete set of plans and specifications.

Under the authority of §217.6(e) a technical review of complete plans and specifications is not required. However, the project proposed in the summary transmittal letter is approved for construction. Please note, that this conditional approval does not relieve the applicant of any responsibilities to obtain all other necessary permits or authorizations, such as wastewater treatment permit or other authorization as required by Chapter 26 of the Texas Water Code. Below are provisions of the Chapter 217 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

• You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §217.6(c). Additionally, the engineering report must include all constants, graphs,

Mr. Robert P. Callegari, P.E. Page 2 April 19, 2018

equations, and calculations needed to show substantial compliance with Chapter 217. The items which shall be included in the summary transmittal letter are addressed in \$217.6(c)(1)-(10).

- Any deviations from Chapter 217 shall be disclosed in the summary transmittal letter and the
 technical justifications for those deviations shall be provided in the engineering report. Any
 deviations from Chapter 217 shall be based on the best professional judgement of the
 licensed professional engineer sealing the materials and the engineer's judgement that the
 design would not result in a threat to public health or the environment.
- Any variance from a Chapter 217 requirement disclosed in your summary transmittal letter
 is approved. If in the future, additional variances from the Chapter 217 requirements are
 desired for the project, each variance must be requested in writing by the design engineer.
 Then, the TCEQ will consider granting a written approval to the variance from the rules for
 the specific project and the specific circumstances.
- Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of 30 TAC \$217.7(a) of the rules which states, "Approval given by the executive director or other authorized review authority does not relieve an owner of any liability or responsibility with respect to designing, constructing, or operating a collection system or treatment facility in accordance with applicable commission rules and the associated wastewater permit".

If you have any questions, or if we can be of any further assistance, please call me at (512) 239-1372.

Sircerel Qa. Brilli

Paul A. Brochi, P.E. Wastewater Permits Section (MC 148) Water Quality Division Texas Commission on Environmental Quality

PAB/lb

cc: TCEQ, Region 11 Office

Bryan W. Shaw, Ph.D., P.E., *Chairman*Toby Baker, *Commissioner*Jon Niermann, *Commissioner*Stephanie Bergeron Perdue, *Interim Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

May 1, 2018

Mr. Robert P. Callegari, P.E. CMA Engineering Inc. 235 Ledge Stone Drive Austin, Texas 78737

Re:

Hays County Municipal Utility District No. 4 Phase II WWTP Expansion to 150,000 GPD Clarifier Side Water Depth Variance Request Permit No. WQ0014309001 WWPR Log No. 0418/062 CN602690661, RN103897567 Hays County

Dear Mr. Callegari:

On April 13, 2108, TCEQ received the project summary transmittal letter dated April 12, 2018, for Phase II wastewater treatment plant expansion for Hay County Municipal Utility District No. 4. The project is increase the treatment capacity from 75,000 gpd to 100,000 gpd. The Hays County MUD No. 4 plant is regulated by Water Quality permit WQ0014309001. The permit effluent concentration limits are 20 mg/l of BOD5 and 20 mg/l of TSS with pH of between 6.0 and 9.0 inclusive. The specific work within the scope of this project is detailed below.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, Design Criteria for Wastewater Systems.

The specific work being completed within the scope of this project is as follows:

- Converting the existing phase I digester to an aeration basin
- Increasing the size of the manual bar screen and adding a flow splitter box
- Installing a blower assembly
- Increasing the size of the impellers on the two influent submersible pumps
- Installing a previous approved sludge dewatering box (WWPR Project 0318/067)
- Installing various piping and airlift pumps
- Installing piping and electric additions as necessary

The summary transmittal letter also included a request for variance of 217.152(g)(2)(A) which requires a 10-ft. side water depth for a clarifier with a mechanical sludge collector. The engineer is proposing a 9.25 side water depth which will be identical to the because the existing clarifier designed under 30 TAC Chapter 317 requirements was design with the 9.25 side water depth and the desire is to keep the hydraulics of the plants identical; and there have been no issues with the existing clarifier. This variance is granted.

Mr. Robert P. Callegari, P.E. Page 2 May 1, 2018

The TCEQ review of this project seems to indicate that the project meets at least the minimum requirements of 30 TAC Chapter 217: Design Criteria for Wastewater Systems. This project is conditionally approved for completion based on all work being completed according to 30 TAC Chapter 217 requirements except for the variance granted.

You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §217.6(c). Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 217. The items which shall be included in the summary transmittal letter are addressed in §217.6(c)(1)-(10).

If in the future, additional variances from the Chapter 217 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting a written approval to the variance from the rules for the specific project and the specific circumstances.

Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of 30 TAC \$217.7(a) of the rules which states, "Approval given by the executive director or other authorized review authority does not relieve an owner of any liability or responsibility with respect to designing, constructing, or operating a collection system or treatment facility in accordance with applicable commission rules and the associated wastewater permit".

Mr. Robert P. Callegari, P.E. Page 3 May 1, 2018

If you have any questions, or if we can be of any further assistance, please call me at (512) 239-1372.



Paul A. Brochi, P.E. Wastewater Permits Section (MC 148) Water Quality Division Texas Commission on Environmental Quality

PAB/lb

cc: TCEQ, Region 11 Office

Jon Niermann, Chairman Emily Lindley, Commissioner Toby Baker, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

August 9, 2019

Robert P. Callegari, P.E. CMA Engineering Inc. 235 Ledge Stone Drive Austin, Texas 78737-

Re: Ha

Hays County MUD 4
Phase II WWTP Expansion to 100,000 GPD
Permit No. WQ0014309-001 1780
WWPR Log No. 0819/004
CN602690661, RN103897567
Hays County

Dear Mr. Callegari:

On August 2, 2019 TCEQ received the project summary transmittal letter dated July 30,2019 for the expansion of the Hays County MUD No. 4 to the 100,000 GPD Interim II phase and the construction of the tankage for the future 150,000 GPD final phase of the plant. The items being constructed within the scope of the project are listed below.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, Design Criteria for Wastewater Systems.

The items being constructed within the scope of the project are as follows:

- Expansion of the current capacity from a 75,000 GPD WWTP to a 100,000 GPD WWTP
- Tankage for the future 150,000 GPD WWTP final phase.
- Replacement of the current bar screen with a larger manual bar screen and a flow splitter box.
- Installation of an additional blower assembly for Interim II phase.
- Replacement of two influent submersible lift station pump impellers.
- Installation of piping, diffusers, and airlift pumps for the WWTP expansion.
- Piping and electrical additions as necessary.

Based on the results of the TCEQ review of the submitted information, the project is conditionally approved for construction. The condition being that the owner of the proposed wastewater treatment plant implements facilities to meet emergency power requirements set forth in 30 TAC Chapter 217.36 Emergency Power Requirements and Chapter 217.37 Disinfection System Power Reliability.

Robert P. Callegari, P.E. Page 2 August 9, 2019

You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report are discussed in §217.6(d). Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 217. The items which shall be included in the summary transmittal letter are addressed in §217.6(d)(1)-(9).

Any deviations from Chapter 217 shall be disclosed in the summary transmittal letter and the technical justifications for those deviations shall be provided in the engineering report. Any deviations from Chapter 217 shall be based on the best professional judgement of the licensed professional engineer sealing the materials and the engineer's judgement that the design would not result in a threat to public health or the environment.

No variances of any Chapter 217 requirements were requested or permitted as part of this project review. If in the future, any variances from Chapter 217 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting written approval to the variance from the rules for the specific project and circumstances.

Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

Please be reminded of 30 TAC §217.7(a) of the rules which states, "Approval given by the executive director or other authorized review authority does not relieve an owner of any liability or responsibility with respect to designing, constructing, or operating a collection system or treatment facility in accordance with applicable commission rules and the associated wastewater permit".

If you have any questions, or if we can be of any further assistance, please call me at (512) 239-4924.

Sincerely,

Eric Barnes,

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

Baltazz Lucero-Ramirez, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

BLR/tc

cc: TCEQ, Region 11 Office

Kathleen Hartnett White, Chairman Larry R. Soward, Commissioner Martin A. Hubert, Commissioner Glenn Shankle, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

November 10, 2006

Mr. Robert P. Callegari, P.E. CMA Engineering, Inc. 14101 West Highway 290, Bldg. 600 Austin, Texas 78737

Re:

194 Bush, Ltd., TCEQ Permit No. WQ0014309001 (CN601457716, RN103897567)

Dear Mr. Callegari:

We acknowledge receipt of your letter dated October 6, 2006 proposing a change in the mode of operation of the activated sludge plant from extended aeration, as stated in the permit, to a single stage nitrification. We understand that there no other changes in the permit. We pose no objection to the proposed change.

When an application for permit renewal is filed, please make a note in the application that a renewal with changes is being requested and refer to your letter of October 6, 2006 and this letter as supporting documents. Please provide a separate letter of notification of this change to Mr. Louis C. Herrin III, P.E., to amend your summary transmittal letter of June 22, 2006. As regards auxiliary power, we recommend that the on-site lift station and the wastewater treatment facility be wired to accept a generator in the event of power outages longer than anticipated.

We notice that your letter states that the construction of the new wastewater treatment facility and collection is expected to be completed by April of 2006. Craig Gonzales of your office verified that this should be April 2007. In this regard, please be reminded of the notification requirements of the current permit and the approval letter dated August 31, 2006 for the proposed project described in the June 22, 2006 summary transmittal letter.

If you have any questions regarding this matter, please do not hesitate to contact me at (512) 239-4540 or if by correspondence include MC 148 in the letterhead address following my name.

Sincerely,

Firoj Valvora, Team Leader Municipal Permits Team

Water Quality Division

FV/JDC/sp

cc: Mr. Louis C. Herrin III, P.E., Wastewater Permitting Section (MC 148)

TCEQ Region 11

Westwood

ATTACHMENT #12 – POLLUTANT ANALYSIS OF TREATED EFFLUENT

www. NWDLS.com



February 08, 2024

Laboratory Report

John Montgomery Municipal Operations and Consulting 27316 Spectrum Way Oak Ridge, TX 77385

Report ID: 20240208133253DLH

The following test results meet all NELAP requirements for analytes for which certification is available. Any deviations from our quality system will be noted in the case narrative. All analyses performed by North Water District Laboratory Services, Inc. unless noted.

For questions regarding this report, contact Monica Martin at 936-321-6060.

Sincerely,

Deena Higginbotham

Director of Client Services

Opena Higginborham





Hays County 4 - Permit Renewal

Reported: 02/08/2024 13:32

Sample Results

Client Sample ID: Lab Sample ID: Outfall 001

24A5702-01

Sample Matrix:

Waste Water

Date Collected: 01/26/2

01/26/2024 10:18

[none]

Collected by: Cesar Guevara

M-14-4	Analida	*	Donully C	Lleite	DE	CDI	LDI	Patch	Analigod	Analyst
Method	Analyte		Result Q	Units	DF	SDL	LRL	Batch	Analyzed	Analyst
General Chemi	istry									
SM 2320 B	Alkalinity as CaCO3	Α	109	mg/L	1	10.0	10.0	BHA4553	01/29/2024 14:06	AKA
SM 5210 B	Biochemical Oxygen Demand (BOD)	Α	<2.40U	mg/L	1.2	2.40	2.40	BHA4497	02/01/2024 10:16	AMM
SM 5210 B	Carbonaceous BOD (CBOD)	Α	<3.00U	mg/L	1.5	3.00	3.00	BHA4498	02/01/2024 11:07	AMM
SM 2510 B	Conductivity	Α	894	umhos/cm @ 25 °C	1	2.00	2.00	BHA4553	01/29/2024 14:06	AKA
EPA 350.1	Ammonia as N	Α	0.0611	mg/L	1	0.0200	0.0500	BHA4683	01/30/2024 10:29	GJG
EPA 1664A	n-Hexane Extractable Material (O&G)	Α	<5.00U	mg/L	1	5.00	5,00	BHB0505	02/03/2024 09:49	ARW
EPA 300.0	Sulfate	Α	40.5	mg/L	1	0.0341	1.00	BHA4363	01/26/2024 23:19	ORP
SM 2540 C	Residue-filterable (TDS)	Α	452B1	mg/L	1	10.0	10.0	BHA4560	01/31/2024 10:34	BP
SM 4500-NH3 C	Total Kjeldahl Nitrogen - (TKN)	Α	<1.00U	mg/L	1	0.100	1.00	BHA4697	01/30/2024 09:00	GIW
EPA 365.1	Total Phosphorus	Α	4.05	mg/L	1	0.117	0.200	BHA4621	01/31/2024 09:50	TBB
SM 2540 D	Residue-nonfilterable (TSS)	Α	11.2	mg/L	1	1.00	1.00	BHA4584	01/29/2024 16:15	ENR
Microbiology										
SM 9223 B (Colllert Quanti-Tray)	Escherichia coli (E. coli)	Α	4.10	MPN/100 mL	1	1.00	1.00	BHA4474	01/27/2024 16:14	ORP
Field										
Hach 10360	DO Field	N	7.46	mg/L	1	1.00	1.00	BHA4599	01/26/2024 10:18	CGJ
Calc	Flow Field	N	0.0500	MGD	1	0.00	0.00	BHA4599	01/26/2024 10:18	CGJ
SM 4500-H+ B	рН	Α	7.00	pH Units @ 25 °C	1	1.00	1.00	BHA4599	01/26/2024 10:18	CGJ
SM 4500-CI G	Total Residual Chlorine	Α	1.06	mg/L	1	0.25	0.25	BHA4599	01/26/2024 10:18	CGJ

A = Accredited, N = Not Accredited or Accreditation not available





Reported:

02/08/2024 13:32

Sample Results (Continued)

Client Sample ID:

Lab Sample ID:

Outfall 001

24A5702-01RE1

Sample Matrix:

Waste Water

Date Collected:

01/26/2024 10:18

Hays County 4 - Permit Renewal

[none]

Collected by:

Cesar Guevara

Method	Analyte	*	Result Q	Units	DF	SDL	LRL	Batch	Analyzed	Analyst
General Che	emistry									
EPA 300.0	Chloride (Rerun)	А	129	mg/L	5	0.172	5.00	BHA4499	01/27/2024 14:10	ORP
EPA 300.0	Nitrate as N (Rerun)	Α	14.0	mg/L	5	0.0710	0.500	BHA4499	01/27/2024 14:10	ORP

 $A = Accredited, \, N = Not \, Accredited \, or \, Accreditation \, not \, available$



Reported: 02/08/2024 13:32

TCEQ T104704238-23-39

Quality Control

General Chemistry

Analyte	Result Qual	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit
Batch: BHA4363 - EPA 300.0									
Duplicate (BHA4363-DUP1)	Sou	rce: 24A0694-01		Prepared &	Analyzed: 01	./26/2024			
Sulfate	138	10.0	mg/L		138			0.507	15
Nitrate as N	0.610 U	1.00	mg/L		0.590			3,33	15
Chloride	95.8	10.0	mg/L		96.4			0.645	15
Duplicate (BHA4363-DUP2)	Sou	rce: 24A5569-01		Prepared &	Analyzed: 01	/26/2024			
Chloride	109	10.0	mg/L		110			1.57	15
Nitrate as N	12.3	1.00	mg/L		12.5			1.45	15
Sulfate	19.5	1.00	mg/L		19.5			0.354	15
MRL Check (BHA4363-MRL1)				Prepared &	Analyzed: 01	./26/2024			
Chloride	1.10	1.00	mg/L	1.00		110	50-150		
Sulfate =	1.18	1.00	mg/L	1.00		118	50-150		
Nitrate as N	0.121	0,100	mg/L	0.100		121	50-150		
Matrix Spike (BHA4363-MS1)	Sou	rce: 24A0694-01		Prepared &	Analyzed: 01	./26/2024			
Sulfate	159	11.1	mg/L	22.2	138	92.8	80-120		
Nitrate as N	2.82	1.11	mg/L	2.22	0.590	100	80-120		
Chloride	110 J1	11.1	mg/L	11.1	96.4	121	80-120		
Matrix Spike (BHA4363-MS2)	Sou	rce: 24A5569-01		Prepared &	Analyzed: 01	/26/2024			
Chloride	129 J1	11,1	mg/L	11.1	110	167	80-120		
Sulfate	41.8	1.11	mg/L	22.2	19.5	100	80-120		
Nitrate as N	15.6 J1	1,11	mg/L	2.22	12,5	138	80-120		

 LCS (BHA4497-BS1)
 Prepared: 01/27/2024 Analyzed: 02/01/2024

 Biochemical Oxygen Demand (BOD)
 170
 mg/L
 198
 85.7
 85-115

^{*} A = Accredited, N = Not Accredited or Accreditation not available



Reported: 02/08/2024 13:32

Quality Control (Continued)

Analyte	Result	Qual	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit
Batch: BHA4497 - BOD-5210 (Continued)									
Duplicate (BHA4497-DUP1)	-	Source: 2	4A5699-02	Pre	pared: 01/27/	/2024 Analyze	d: 02/01/202	4		
Biochemical Oxygen Demand (BOD)	<2.40	U, J4	2.40	mg/L		<2.40				40
Duplicate (BHA4497-DUP2)		Source: 2	4A5530-02	Pre	pared: 01/27/	/2024 Analyze	d: 02/01/202	4		
Biochemical Oxygen Demand (BOD)	4.09		2.40	mg/L		6.13			40.0	40
Duplicate (BHA4497-DUP3)		Source: 2	4A0555-01	Pre	pared: 01/27/	/2024 Analyze	d: 02/01/202	!4		
Biochemical Oxygen Demand (BOD)	<2.40	U	2.40	mg/L		<2.40				40
Duplicate (BHA4497-DUP4)		Source: 2	4A0278-01	Pre	oared: 01/27/	/2024 Analyze	d: 02/01/202	' 4		
Biochemical Oxygen Demand (BOD)	14.6		2.40	mg/L		17.1			16.2	20
Duplicate (BHA4497-DUP5)		Source: 2	4A5599-04	Pre	oared: 01/27,	/2024 Analyze	d: 02/01/202	'4		
Biochemical Oxygen Demand (BOD)	82.6		50.0	mg/L		85.8			3.76	20
Duplicate (BHA4497-DUP6)		Source: 2	4A5550-07	Pre	pared: 01/27,	/2024 Analyze	d: 02/01/202	'4		
Biochemical Oxygen Demand (BOD)	122		50.0	mg/L		143			15.9	20
Duplicate (BHA4497-DUP7)		Source: 2	4A5523-02	Pre	pared: 01/27,	/2024 Analyze	d: 02/01/202	'4		
Biochemical Oxygen Demand (BOD)	220		50.0	mg/L		229			4.12	20
Duplicate (BHA4497-DUP8)		Source: 2	4A0612-03	Pre	pared: 01/27,	/2024 Analyze	d: 02/01/202	<u>'</u> 4		
Biochemical Oxygen Demand (BOD)	<50.0		50.0	mg/L		<50.0				20
Duplicate (BHA4497-DUP9)		Source: 2	4A4416-01	Pre	pared: 01/27,	/2024 Analyze	d: 02/01/202	<u>'</u> 4		
Biochemical Oxygen Demand (BOD)	488		100	mg/L		481			1.45	20
Duplicate (BHA4497-DUPA)		Source: 2	4A4428-01	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	14		
Biochemical Oxygen Demand (BOD)	968	-	100	mg/L		869	•		10.8	20

^{*} A = Accredited, N = Not Accredited or Accreditation not available



Reported: 02/08/2024 13:32

Quality Control (Continued)

Analyte	Result	Qual	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit
Batch: BHA4498 - CBOD-5210										
LCS (BHA4498-BS1)				Pre	pared: 01/27,	/2024 Analyze	d: 02/01/202	!4		
Carbonaceous BOD (CBOD)	164	J1		mg/L	198		82.7	85-115		
Duplicate (BHA4498-DUP1)		Source: 2	24A5627-01	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	!4		
Carbonaceous BOD (CBOD)	<2.40	J4, U	2.40	mg/L		<2.40				40
Duplicate (BHA4498-DUP2)		Source: 2	24A5512-02	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	<u>'</u> 4		
Carbonaceous BOD (CBOD)	2.56		2.40	mg/L		<2.40			200	40
Duplicate (BHA4498-DUP3)		Source: 2	24A5483-01	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	!4		
Carbonaceous BOD (CBOD)	2.89		2.40	mg/L		3.93			30.5	40
Duplicate (BHA4498-DUP4)		Source: 2	24A5699-01	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	<u>!</u> 4		
Carbonaceous BOD (CBOD)	<2.40	J4, U	2.40	mg/L		<2.40				40
Duplicate (BHA4498-DUP5)		Source: 2	24A5504-02	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	24		
Carbonaceous BOD (CBOD)	<2.40	U	2.40	mg/L		<2.40				40
Duplicate (BHA4498-DUP6)		Source: 2	24A5546-05	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	24		
Carbonaceous BOD (CBOD)	2.53		2.40	mg/L		<2.40			200	40
Duplicate (BHA4498-DUP7)		Source: 2	24A5584-02	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	24		
Carbonaceous BOD (CBOD)	<2.40	U	2.40	mg/L		<2.40				40
Duplicate (BHA4498-DUP8)		Source: 2	24A5701-04	Pre	pared: 01/27	/2024 Analyze	d: 02/01/202	24		
Carbonaceous BOD (CBOD)	159		50.0	mg/L		156			1.85	20
Batch: BHA4499 - EPA 300.0		Source:	24A4906-02		Drenared ®	k Analyzed: 01,	/27/2024			
Duplicate (BHA4499-DUP1) Chloride	94.1	Source: A	2 4A4906-02 10.0	mg/L	riepaied c	97.1	(6) / 2027		3.19	15
Nitrate as N	94.1 14,7		1.00	mg/L		15.1			2.95	15

^{*} A = Accredited, N = Not Accredited or Accreditation not available



Reported: 02/08/2024 13:32

Quality Control (Continued)

		Reporting		Spike	Source		%REC		RPD
Analyte	Result Qual	Limit	Units	Level	Result	%REC	Limits	RPD	Limit
Batch: BHA4499 - EPA 300.0 (Co	ntinued)								
MRL Check (BHA4499-MRL1)				Prepared 8	k Analyzed: 01	/27/2024			
Nitrate as N	0.105	0.100	mg/L	0.100		105	50-150		
Chloride	1.11	1.00	mg/L	1.00		111	50-150		
Matrix Spike (BHA4499-MS1)	Source:	24A4906-02		Prepared 8	k Analyzed: 01	/27/2024			
Chloride	112 J1	11.1	mg/L	11.1	97.1	135	80-120		
Nitrate as N	16.6 J1	1.11	mg/L	2.22	15,1	65.7	80-120		
D-1-1- D1144550 411-11-11-									
Batch: BHA4553 - Alkalinity									
Blank (BHA4553-BLK1)				Prepared 8	& Analyzed: 01	/29/2024			
Conductivity	<2.00 U	2,00	umhos/cm @ 25 °C						
LCS (BHA4553-BS1)				Prepared 8	& Analyzed: 01	/29/2024			
Conductivity	1420		umhos/cm @ 25 °C	1410		100	90-110		
QSC (BHA4553-BS2)				Prepared 8	& Analyzed: 01	/29/2024			
Conductivity	522		umhos/cm @ 25 °C	500		104	90-110		
LCS (BHA4553-BS4)				Prepared 8	& Analyzed: 01	/29/2024			
Alkalinity as CaCO3	101		mg/L	100		101	90-110		
Duplicate (BHA4553-DUP1)	Source:	24A4763-03		Prepared 8	& Analyzed: 01	/29/2024			
Alkalinity as CaCO3	254	10.0	mg/L		250			1.65	15
Conductivity	1210	2,00	umhos/cm @ 25 °C		1190			1.33	15
Duplicate (BHA4553-DUP2)	Source:	24A5579-01		Prepared 8	& Analyzed: 01	/29/2024			
Alkalinity as CaCO3	69.2	10.0	mg/L		70.4			1.72	15
Conductivity	629	2.00	umhos/cm @ 25 °C		626			0.478	15

A = Accredited, N = Not Accredited or Accreditation not available





Reported: 02/08/2024 13:32

Quality Control (Continued)

					$\overline{}$			-	
		Reporting		Spike	Source		%REC		RPD
Analyte	Result Qual	Limit	Units	Level	Result	%REC	Limits	RPD	Limit
Batch: BHA4560 - TDS									
Blank (BHA4560-BLK1)			Pre	pared: 01/29,	/2024 Analyze	d: 01/31/20.	24		
Residue-filterable (TDS)	<10,0 U	10.0	mg/L						
LCS (BHA4560-BS1)			Pre	pared: 01/29,	/2024 Analyze	d: 01/31/20.	24		
Residue-filterable (TDS)	148	10.0	mg/L	150		98.7	90-110		
Duplicate (BHA4560-DUP1)	Source: 2	24A0064-01	Pre	pared: 01/29,	/2024 Analyze	d: 01/31/20.	24		
Residue-filterable (TDS)	246	10.0	mg/L		248			0.810	10
Batch: BHA4584 - TSS									
Blank (BHA4584-BLK1)				Prépared &	k Analyzed: 01,	/29/2024			
Residue-nonfilterable (TSS)	<1.00 U	1.00	mg/L						
LCS (BHA4584-BS1)				Prepared &	k Analyzed: 01,	/29/2024			
Residue-nonfilterable (TSS)	98.9	1.00	mg/L	100		98.9	85-115		
Duplicate (BHA4584-DUP1)	Source: 2	4A5496-02		Prepared &	k Analyzed: 01,	/29/2024			
Residue-nonfilterable (TSS)	2.32 J1	1.00	mg/L		1.89			20.0	10
Duplicate (BHA4584-DUP2)	Source: 2	4A5567-01		Prepared &	k Analyzed: 01,	/29/2024			
Residue-nonfilterable (TSS)	1.89	1.00	mg/L		1,89			0.00	10
Batch: BHA4621 - Phosphorus	F EPA 365.1								
LCS (BHA4621-BS1)			Pre	pared: 01/29,	/2024 Analyze	d: 01/31/20	24		
Total Phosphorus	0.229	0.0100	mg/L	0.250		91.5	90-110		

^{*} A = Accredited, N = Not Accredited or Accreditation not available



Reported: 02/08/2024 13:32

TCEQ T104704238-23-39

Quality Control (Continued)

Analyte	Result Qual	Reporting Limit	Units	Spīke Level	Source Result	%REC	%REC Limits	RPD	RPD Limit
Batch: BHA4621 - Phosphorus EP	——————————————————————————————————————	 ied)							
Matrix Spike (BHA4621-MS1)	-	24A5432-02	Pre	pared: 01/29	/2024 Analyze	d: 01/31/20	24		
Total Phosphorus	7.50	0.200	mg/L	5.00	2.72	95.5	80-120		
Matrix Spike (BHA4621-MS2)	Source: 2	24A5706-01	Pre	epared: 01/29	/2024 Analyze	d: 01/31/20	24		
Total Phosphorus	7.83	0,200	mg/L	5.00	3.27	91.3	80-120		
Matrix Spike Dup (BHA4621-MSD1)	Source: 2	24A5432-02	Pre	epared: 01/29	/2024 Analyze	ed: 01/31/20	24		
Total Phosphorus	7.54	0.200	mg/L	5.00	2.72	96.3	80-120	0.532	20
Matrix Spike Dup (BHA4621-MSD2)	Source: 2	24A5706-01	Pre	epared: 01/29	/2024 Analyze	ed: 01/31/20	24		
Total Phosphorus	7.95	0.200	mg/L	5.00	3,27	93.8	80-120	1.55	20
Matrix Spike (BHA4683-MS1) Ammonia as N		24A5706-01 0.0500	ma/L		Analyzed: 01 0.0523	/30/2024 102	90-110		
Ammonia as N	0.459	0.0500	mg/L	0.400	0.0523	102	90-110		
Matrix Spike (BHA4683-MS2)									
	Source: 2	24A5478-01		Prepared 8	Analyzed: 01	/30/2024			
Ammonia as N	Source: 2 0.450	24A5478-01 0.0500	mg/L	Prepared 8 0.400	Analyzed: 01 0.0522	/30/2024 99.5	90-110		
	0.450		mg/L	0.400	,	99.5	90-110		
	0.450	0.0500	mg/L	0.400	0.0522	99.5	90-110 90-110	1.11	20
Matrix Spike Dup (BHA4683-MSD1)	0.450 Source: 2 0.464	0.0500 24A5706-01		0.400 Prepared 8 0.400	0.0522 Analyzed: 01	99.5 /30/2024 103		1.11	20
Matrix Spike Dup (BHA4683-MSD1) Ammonia as N	0.450 Source: 2 0.464	0.0500 24A5706-01 0.0500		0.400 Prepared 8 0.400	0.0522 Analyzed: 01 0.0523	99.5 /30/2024 103		1.11	20
Matrix Spike Dup (BHA4683-MSD1) Ammonia as N Matrix Spike Dup (BHA4683-MSD2) Ammonia as N	0.450 Source: 2 0.464 Source: 2	0.0500 24A5706-01 0.0500 24A5478-01	mg/L	0.400 Prepared 8 0.400 Prepared 8	0.0522 Analyzed: 01 0.0523 Analyzed: 01	99.5 /30/2024 103 /30/2024	90-110		
Matrix Spike Dup (BHA4683-MSD1) Ammonia as N Matrix Spike Dup (BHA4683-MSD2) Ammonia as N Batch: BHA4697 - TKN T	0.450 Source: 2 0.464 Source: 2	0.0500 24A5706-01 0.0500 24A5478-01	mg/L	0.400 Prepared 8 0.400 Prepared 8 0.400	0.0522 A Analyzed: 01 0.0523 A Analyzed: 01 0.0522	99.5 /30/2024 103 /30/2024 97.2	90-110		
Matrix Spike Dup (BHA4683-MSD1) Ammonia as N Matrix Spike Dup (BHA4683-MSD2)	0.450 Source: 2 0.464 Source: 2	0.0500 24A5706-01 0.0500 24A5478-01	mg/L	0.400 Prepared 8 0.400 Prepared 8	0.0522 A Analyzed: 01 0.0523 A Analyzed: 01 0.0522	99.5 /30/2024 103 /30/2024 97.2	90-110		

^{*} A = Accredited, N = Not Accredited or Accreditation not available





Reported: 02/08/2024 13:32

Quality Control (Continued)

A b A .	Barrella Orrell	Reporting	Lleite	Spike	Source	%REC	%REC Limits	RPD	RPD Limit
Analyte	Result Qual	Limit	Units	Level	Result	70KEC	Limits	KPD	Limit
Batch: BHA4697 - TKN T (Cont	inued)								
LCS (BHA4697-BS1)			Pre	epared: 01/29	/2024 Analyzed	1: 01/30/20	024		
Total Kjeldahl Nitrogen - (TKN)	1.79	1.00	mg/L	2,02		88.7	85-115		
Duplicate (BHA4697-DUP1)	Source:	24A0437-01	Pre	epared: 01/29	/2024 Analyze	d: 01/30/20	024		
Total Kjeldahl Nitrogen - (TKN)	4.59	1.00	mg/L		5.38			15.7	20
Matrix Spike (BHA4697-MS1)	Source:	24A0437-01	Pre	epared: 01/29	/2024 Analyze	1: 01/30/2	024		
Total Kieldahl Nitrogen - (TKN)	8.96	1.00	mg/L	4.00	5.38	89.6	85-115		
	<u></u>								
Batch: BHB0505 - EPA 1664	3,70								
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1)		5.00	mg/L	Prepared 8	k Analyzed: 02/	03/2024			
Batch: BHB0505 - EPA 1664	<5.00 U	5.00	mg/L	Prepared 8	k Analyzed: 02/	03/2024			
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1) n-Hexane Extractable Material (O&G)		5.00	mg/L		k Analyzed: 02/ k Analyzed: 02/				
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1) n-Hexane Extractable Material (O&G)		5.00 5.00	mg/L mg/L				77.5-114.5		
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1) n-Hexane Extractable Material (O&G) LCS (BHB0505-BS1)	<5.00 U			Prepared 8		03/2024	77.5-114.5		
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1) n-Hexane Extractable Material (O&G) LCS (BHB0505-BS1) n-Hexane Extractable Material (O&G)	<5.00 U			Prepared 8	k Analyzed: 02/	03/2024	77.5-114.5 77.5-114.5	2.43	20
Batch: BHB0505 - EPA 1664 Blank (BHB0505-BLK1) n-Hexane Extractable Material (O&G) LCS (BHB0505-BS1) n-Hexane Extractable Material (O&G) LCS Dup (BHB0505-BSD1)	<5.00 U 43.1 42.1	5.00	mg/L	Prepared 8 40.0 Prepared 8 40.0	k Analyzed: 02/	03/2024 108 03/2024 105		2,43	20

^{*} A = Accredited, N = Not Accredited or Accreditation not available



www. NWDLS.com TCEQ T104704238-23-39



Municipal Operations and Consulting 27316 Spectrum Way Oak Ridge, TX 77385

Reported: 02/08/2024 13:32

.

Quality Control (Continued)

Microbiology

Reporting Spike Source %REC RPD
Analyte Result Qual Limit Units Level Result %REC Limits RPD Limit

Batch: BHA4474 - TC EC Quantitray

Blank (BHA4474-BLK1) Escherichia coli (E. coli) Prepared: 01/26/2024 Analyzed: 01/27/2024

<1.00 U

1.00 MPN/100

Duplicate (BHA4474-DUP1)

Source: 24A5705-01

Prepared: 01/26/2024 Analyzed: 01/27/2024


Escherichia coli (E. coli)

<1.00 U

1.00 MPN/100 mL <1.00

200

^{*} A = Accredited, N = Not Accredited or Accreditation not available





Reported: 02/08/2024 13:32

Sample Condition Checklist

Work Order: 24A5702

Check Points

No Custody Seals
Yes Containers Intact
Yes COC/Labels Agree
Yes Received On Ice
Yes Appropriate Containers
Yes Appropriate Sample Volume
Yes Coolers Intact
Yes Samples Accepted





Item

Definition

Reported: 02/08/2024 13:32

Term and Qualifier Definitions

B1	Associated method blank is lower than the established quality control criteria.
J1	Estimated value - The reported value is outside the established quality control criteria for accuracy and/or precision.
J4	Estimated value and sample is less than value - No dilution produced a depletion of 2 mg/L of DO or greater, oxygen demand of sample was less than anticipated.
U	Non-detected compound.
RPD	Relative Percent Difference
%REC	Percent Recovery
Source	Sample that was matrix spiked or duplicated
*	A = Accredited, N = Not Accredited or Accreditation not available
DF	Dilution Factor - the factor applied to the reported data due to sample preparation, dilution, or moisture content
MDL	Method Detection Limit - The minimum concentration of a substance (or analyte) that can be measured and reported with 99% confidence that the
	analyte concentration is greater than zero. Based on standard deviation of replicate spiked samples take through all steps of the analytical
	procedure following 40 CFR Part 136 Appendix B.
SDL	Sample Detection Limit - The minimum concentration of a substance (analyte) that can be measured and reported with 99% confidence that the
	analyte concentration is greater than zero. The SDL is an adjusted limit thus sample specific and accounts for preparation weights and volumes,
	dilutions, and moisture content of soil/sediments. If there are no sample specific parameters, the MDL = SDL.
MRL	Method Reporting Limit - Analyte concentration that corresponds to the lowest level lab reports with confidence in accuracy of quantitation and
	without qualification (i.e. J-flagged). The MRL is at or above the lowest calibration standard.
LRL	Laboratory Reporting Limit - Analyte concentration that corresponds to the lowest level lab reports with confidence in accuracy of quantitation and
LKL	without qualification (i.e. J-flagged). The LRL is an adjusted limit thus sample specific and accounts for preparation weights and volumes, dilutions,
	without qualification (i.e. 3-hagged). The tirt is an adjusted limit drus sample specific and accounts for preparation weights and volumes, dilutions,

and moisture content of soil/sediments. If there are no sample specific parameters, the MRL = LRL.





CHAIN OF CUSTODY RECORD
North Water District Laboratory Services
130 S. Trade Center Pkwy, Conroe Tx 77385
(936) 321-6060 - lab@nwdis.com TCEQ T104704238-23-39

Lab PM : De	Lab PM: Deena Higginbotham	Pro	Project Name: Hays County 4 - Permit Renewal	inty 4 - Permit Rene	wal			Schedule	Schedule Comments:
Municipal Operations a John Montgomery 27316 Spectrum Way Oak Ridge, TX 77385 Phone: (281) 367-5511	Municipal Operations and Consulting John Montgomery 27316 Spectrum Way Oak Ridge, TX 77385 Phone: (281) 367-5511		Project Comments: Driveway to plant is between 143 & 151 Terrace Ct - Austin 78737 Code: 0701 Call Chris Sanchez - 713-206-8652 30min before arrival DO must be recorded before 9am. If CL2 not between 1.0-4.0 Call Office Mark out Duplicated Outfall samples on reg chain	y to plant is between 1 1 Call Chris Sanchez 9am. If CL2 not betwe butfall samples on reg	43 & 151 Terrace - 713-206-8652 en 1.0- 4.0 Call chain				
Sample ID	Sample ID Collection Point	Date/Time Begin	Date/Time Sampled	Sample Type	Container	Analysis/Preservation	ation	Field Results	
24A5702-01 Outfall 001	Outfall 001		1/26/2024/018	AQ Grab	A HDPE 250mL B HDPE 1L	TC EC-9223	Na2S2O3 <10°C	DO Field Flow MGD Field	0.05
			•		C HDPE 250mL H2SO4	O&G-1664	HCI 4°C	pH Field	7.00
		11			D HDPE 250mL	Alkalinity-2320	4°C	Total Chlorine	1.06
					E Glass Wide 1L w/	BOD-5210	4°C	Residual WW Field	
		×				CBOD-5210	4°C		
					F HDPE S250mL	Chloride IC 300.0	4°C		
					Nazszo3	Conductivity-2510	4°C		
						NH3-N SEAL-350.1	H2SO4 4°C		7.=
						Nitrate as N IC 300.0	4°C		
					1 HOPE 11	Sulfate IC 300.0	4°C		
			7		, ,	TDS-2540	4°C		
						TKN T-4500 C	H2SO4 4°C		
						Total Phosphorus-365.1-H2SO4 4°C	1-H2SO4 4°C		
						TSS-2540	4°C		

Field Remarks:			ab Preservation: H2SO4	SO4 HNO3	NaOH Other:	ar.
			(Circle and Write ID Below)			
Sampler (Signature)	Relinquished By: (Signature)		Date/Time	Received By: (Signature)		Date/Time
Print Name / Cosa (newsa	Relinquished By: (Signature)		Date/Time	Received By: (Signature)		Date/Time
Affiliation UNDLY	Relinquished To Lab By: (Signature))-26.24 H/SS R	Received for Laboratory By: (Signature)	MANC	Date/Time 1458
Custody Seal: Yes / No Container Intact: Yes / No	COC Labels Agree: Yes / No Appropriate Containers: Yes / No	Appropriate Volume: Yes / No Coolers Intact: Yes / No	&)	Received on Ice: Yes / No Samples Accepted: Yes / No	Temperature: Thermometer ID:	ů
New Braunfels					wko_NWDLS_COC_LS Revision 4.1 Effective: 2/17/2022	sion 4.1 Effective: 2/17/2022

New Braunfels

Westwood

ATTACHMENT #13 - SLUDGE ACCEPTANCE AGREEMENT



Austin Wastewater Processing Facility 826 Linger Ln Austin, Texas 78721 (512) 973-8484

Waste Stream Acceptance

01/03/2023

Wastewater Residuals Management, LLC, an affiliate of Wastewater Transport Services, LLC, owns and operates the Austin Wastewater Processing Facility. This facility has been permitted by the TCEQ and assigned permit number MSW 2384. The disposal facility is expected to be open for at least the next 5 years.

The facility has been permitted as a Centralized Waste Treatment Facility able to revice to receive the following categorical and non-categorical waste streams:

- Wastewater Treatment Plant Sludge
- Water Treatment Plant Sludge
- Leachate
- Septic
- Sanitary Sewer
- Storm Water
- Food Service Grease
- Car Wash Grit Trap
- Other Class II Non-Hazardous Liquid Waste

***Please note that analytical may be required before the waste stream will be accepted.

Wastewater Residuals Management, LLC agrees to accept any of the above waste streams from the below listed generator.

Generator: Hays County MUD WWTP

Identifying Info: WQ0014309001

Corv R. Juby

Environmental Compliance

Wastewater Residuals Management reserves the right to discontinue acceptance of the below mentioned waste at any time.

Westwood

ATTACHMENT #14- TCEQ APPOVAL LETTERS FOR 210 REUSE

Bryan W. Shaw, Ph.D., Chairman Carlos Rubinstein, Commissioner Toby Baker, Commissioner Zak Covar, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

October 17, 2012

Mr. Robert P. Callegari, PE CMA Engineering, Inc. 235 Ledge Stone Drive Austin, Texas 78737

Re:

Hays County MUD No. 4

Amendment to Hays County MUD No. 4

Reclaimed Authorization and Purple Pipe Variance

TCEQ Authorization No R14309-001 CN600688246 RN103897567

Hays County

Dear Mr. Callegari:

We have completed our review of your requests to add Type I uses to the authorization and for a variance to the purple pipe rule on the irrigation systems under the commission reclaimed water program (30 TAC Chapter 210). You are requesting that the commission grandfather a portion of the existing irrigation system that was built before the purple pipe requirements.

The variance request is granted with the following conditions:

- 1. The district must certify that the irrigation system does not have any cross-connection with a potable water supply.
- 2. Any repairs, replacements or realignment of this portion of the irrigation system shall meet the purple pipe requirements.

Thank you for your cooperation during this review process. If you have any questions, please contact Louis C. Herrin, HI of my staff at louis.herrin@tceq.texas.gov or (512) 239-4552.

Sincerely

Chris Linendoll, E.I.T., Manager Wastewater Permitting Section

Water Quality Division

CL/LCH/sp

AUTHORIZATION FOR RECLAIMED WATER



Authorization No. R14309001 This authorization supersedes and replaces Authorization No. R14309001 approved March 23, 2010

Producer:

Hays County Municipal Utility District No. 4

600 Congress Street, Suite 2100 Austin, Texas 78701-2986

Provider:

Havs County Municipal Utility District No. 4

600 Congress Street, Suite 2100 Austin, Texas 78701-2986

User:

Any user within the service area authorized by the provider

Location:

The wastewater treatment facility is located approximately 2,960 feet westnorthwest of the intersection of U.S. Highway 290 and County Road 163 (Nutty Brown Road); approximately 640 feet southwest of the intersection of Terrace Court and Ledge Stone Drive, Hays County, Texas.

Authorization: Type I and Type II reclaimed water from the Hays County MUD No. 4's Wastewater Treatment Facility (TPDES Permit No. WQ0014309001) to be used for: irrigation of open space/greenbelt areas, parks, landscape areas, and rightof-ways within the Ledge Stone Development; for make-up water in off-channel water quality ponds, and potentially for commercial process and cooling tower makeup water in the future within the Ledge Stone Development. The reclaimed water will also be used for construction water, soil compaction and dust control, and for re-vegetation of disturbed areas both inside and outside the Ledge Stone Development/Hays County MUD No. 4 boundaries. The service area is as shown in Section XI, Service Area Map.

This authorization contains the conditions that apply for the use of reclaimed water. The approval of reclaimed water use under Chapter 210 does not affect any existing water rights. If applicable, a reclaimed water use authorization in no way affects the need of a producer, provider, or user to obtain a separate water right authorization from the commission. This authorization does not allow irrigation of any area authorized for irrigation under a Texas Land Application Permit.

Issue Date: October 17, 2012

Zak Covar, Executive Director

I. General Requirements

- A. No producer or provider may transfer reclaimed water to a user without first notifying the commission.
- B. Reuse of untreated wastewater is prohibited.
- C. Food crops that may be consumed raw by humans must not be spray irrigated. Food crops including orchard crops that will be substantially processed prior to human consumption may be spray irrigated. Other types of irrigation that avoid contact of reclaimed water with edible portions of food crops are acceptable.
- D. There must be no nuisance conditions resulting from the distribution, the use, or storage of reclaimed water.
- E. Reclaimed water must not be used in a way that degrades groundwater quality to a degree adversely affecting its actual or potential uses.
- F. Reclaimed water stored in ponds must be prevented from discharging into waters in the state, except for discharges directly resulting from rainfall events or in accordance with a permit issued by the commission. All other discharges are unauthorized.
- G. If an overflow of a holding pond occurs causing discharge into or adjacent to water in the state, the user or provider, as appropriate, shall report the noncompliance. A written submission of pertinent information must be provided to the TCEQ Region 11 office in Austin and to the TCEQ Enforcement Division (MC-149) in Austin, within five (5) working days after becoming aware of the overflow. The submission must contain:
 - a description of the noncompliance and its cause;
 - the potential danger to human health or safety, or the environment;
 - 3. the period of noncompliance, including exact dates and times;
 - 4. if the noncompliance has not been corrected, the anticipated time it is expected to continue; and
 - 5. steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
- H. Unless otherwise provided in this authorization, there must be no off-site discharge, either airborne or surface runoff of reclaimed water from the user's property except to a wastewater treatment collection system or wastewater treatment facility unless the reclaimed water user applies for and obtains a permit from the commission that authorizes discharge of the water.
- I. All reclaimed water piping must be separated from potable water piping when trenched by a distance of at least nine feet for Type II effluent and four feet For Type I. All buried pipe must be manufactured in purple, painted purple, taped with purple metallic tape or bagged in purple. All exposed piping, hose bibs and faucets must be painted purple, designed to prevent connection to a standard water hose, and stenciled with a warning reading "NON-POTABLE WATER."
- J. The design of any new distribution system that will convey reclaimed water to a user requires the approval of the executive director. Materials must be submitted to the executive director in accordance with the Texas Engineering Practice Act (Article 3271a, Vernon's Annotated Texas Statutes). The plans and specifications for any new

distribution system constructed pursuant to this authorization must be approved by the executive director. Failure to secure approval before commencing construction or making a transfer of reclaimed water is a violation of this authorization. Each day of a transfer is a separate violation until approval has been secured.

- K. Nothing in this authorization modifies any requirements in 30 TAC Chapter 290, Public Drinking Water.
- L. A major change from a prior notification for use of reclaimed water must be approved by the executive director before it can be implemented. A major change includes:
 - 1. a change in the boundary of the approved service area, not including the conversion of individual lots within a subdivision to reclaimed water use;
 - 2. the addition of a new provider;
 - a major change in the intended use, such as conversion from irrigation of a golf course to residential irrigation; or
 - 4. a change from either Type I or Type II use to the other.
- M. The reclaimed water producer, provider, and user shall maintain current operation and maintenance plans on the sites over which they have operational control. The operation and maintenance plan must contain the following, as a minimum:
 - 1. a copy of the signed contract between the user and provider and a copy of the signed contract between the provider and the producer, as applicable;
 - 2. a labeling and separation plan for the prevention of cross connections between reclaimed water distribution lines and potable water lines;
 - 3. the measures that will be implemented to prevent unauthorized access to reclaimed water facilities (e.g., secured valves);
 - 4. procedures for monitoring reclaimed water;
 - 5. a plan for how reclaimed water use will be scheduled to minimize the risk of inadvertent human exposure;
 - 6. schedules for routine maintenance;
 - 7. a plan for worker training and safety; and
 - 8. contingency plan for system failure or upsets.
- N. One of the following requirements must be met by the user or provider, for any area where reclaimed water is stored or where there are hose bibs or faucets:
 - 1. Signs having a minimum size of eight inches by eight inches must be posted at all storage areas and on all hose bibs and faucets reading, in both English and Spanish, "Reclaimed Water, Do Not Drink" or similar warning.
 - 2. The area must be secured to prevent access by the public.
- O. Where a reclaimed water line parallels a sewer line, the reclaimed water line must be constructed in accordance with subsection (p) or (q) of this section. The horizontal separation distance must be three feet (outside to outside) with the reclaimed water line at the level of or above the sewer line. Reclaimed water lines that parallel sewer lines may be placed in the same benched trench. Where a reclaimed water line crosses a sewer line,

Hays County Municipal Utility District No 4 Reclaimed Authorization No. R14309-001

the requirement of 30 TAC §290.44(e)(4)(B), Water Line Installation—crossing lines, must be followed with the reclaimed water line substituted for the water line.

- P. Reclaimed water pipes must meet the following requirements:
 - Lines that transport reclaimed water under pressure must be sized according to acceptable engineering practices for the needs of the reclaimed water users.
 - 2. Reclaimed water force mains must have an expected life of at least as long as that of the associated lift station and must be suitable for the reclaimed water being pumped and operating pressure to which it will be subjected.
 - 3. Pipes must be identified in the technical specifications with appropriate American Society for Testing and Materials, American National Standard Institute, or American Water Works Association standard numbers for both quality control (dimensions, tolerance, and installation such as bedding or backfill).
 - 4. Pipes and fittings must have a minimum working pressure rating of 150 pounds per square inch.
 - 5. Final plans and specifications must describe required pressure testing for all installed reclaimed water force mains.
 - 6. Minimum test pressure must be 1.5 times the maximum design pressure. Allowable leakage rates must be determined as described in 30 TAC §217.97, Pressure Sewer Systems.
 - 7. Gravity flow reclaimed water lines must meet the requirements of 30 TAC Chapter 217, Subchapter C, Conventional Collection Systems. The provider shall prevent high velocity scouring and maintain adequate fluid velocity to prevent the deposition of solids in the lines.
- Q. All exposed piping and piping within a building must be either purple pipe or painted purple. All exposed piping should be stenciled in white with a warning reading "NON-POTABLE WATER". All exposed or buried reclaimed water piping constructed at a wastewater treatment facility is exempt from the color-coding requirement of this section.
- R. When applicable, in accordance with 30 TAC Chapter 217, Design Criteria for Domestic Wastewater Systems, the design of the distribution systems that will-convey reclaimed water to a user must be submitted to the executive director and must receive an approval before the distribution system may be constructed. The design of the distribution systems must meet the criteria of 30 TAC Chapter 217, Design Criteria for Domestic Wastewater Systems. When a municipality is the plan review authority for certain sewer systems that transport primarily domestic waste, in lieu of the commission, design submittal will not be subject to submittal to the commission and instead must be approved by the municipality.
- S. All ground level and elevated storage tanks must be designed, installed, and constructed in accordance with current AWWA standards with reference to materials to be used and construction practices to be followed, except for health-based standards strictly related to potable water storage and contact practices, where appropriately less restrictive standards may be applied.

II. Storage Requirements for Reclaimed Water

- A. Storage facilities for retaining reclaimed water prior to use must not be located within a floodway.
- B. Storage ponds must be hydraulically separated from waters in the state.
- C. Any holding pond designed to contain Type I effluent or Type II effluent that is located within a DRASTIC Pollution Potential Index Zone of less than 110, shall conform to the following requirements:
 - 1. Ponds with an earthen liner must meet the following requirements
 - a. A permeability of less than 1 x 10⁻⁴ cm/sec;
 - b. The ponds must be designed and constructed to prevent groundwater contamination;
 - c. Soils used for pond lining must be free from foreign material such as paper, brush, trees, and large rocks; and
 - All soil liners must be of compacted material, at least 24 inches thick, compacted in lifts no greater than 6 inches thick and compacted to 95% of Standard Proctor Density;
 - e. Soil liners must meet the following particle size gradation and Atterberg limits:
 - i. 30% or more passing a number 200 mesh sieve; and
 - ii. a liquid limit of 30% or greater; and
 - iii. a plasticity index of 15 or greater;
 - f. In situ liners at least 24 inches thick meeting a permeability less than or equal to 1 X 10⁻⁴ cm/sec are acceptable alternatives; In-situ clay soils meeting the soils liner requirements must be excavated and re-compacted a minimum of 6 inches below planned grade to assure a uniformly compacted finished surface.
- D. Any holding pond containing reclaimed water located within the recharge zone of the Edward Aquifer or designed to contain Type II effluent and that is located within a DRASTIC Pollution Potential Index Zone of 110 or greater, shall conform to the following requirements:
 - 1. Ponds with an earthen liner must meet the following requirements
 - a. A permeability of less than 1 x 10⁻⁷ cm/sec;
 - b. The ponds must be designed and constructed to prevent groundwater contamination;
 - c. Soils used for pond lining must be free from foreign material such as paper, brush, trees, and large rocks; and
 - All soil liners must be of compacted material, at least 24 inches thick, compacted in lifts no greater than 6 inches thick and compacted to 95% of Standard Proctor Density;
 - e. Soil liners must meet the following particle size gradation and Atterberg limits:
 - i. 30% or more passing a number 200 mesh sieve; and
 - ii. a liquid limit of 30% or greater; and
 - iii. a plasticity index of 15 or greater;

- f. In situ liners at least 24 inches thick meeting a permeability less than or equal to 1 X 10⁻⁷ cm/sec are acceptable alternatives; In-situ clay soils meeting the soils liner requirements must be excavated and re-compacted a minimum of 6 inches below planned grade to assure a uniformly compacted finished surface.
- E. Synthetic membrane linings must have a minimum thickness of 40 mils and have a leak detection system;
- F. Certification by a Texas licensed professional engineer must be furnished stating that the pond liner meets the appropriate criteria prior to use of the facilities;
- G. Soil embankment walls must have a top width of at least five feet. The interior and exterior slopes of soil embankment walls must be no steeper than one foot vertical to three feet horizontal unless alternate methods of slope stabilization are used. All soil embankment walls must be protected by a vegetative cover or other stabilizing material to prevent erosion. Erosion stops and water seals must be installed on all pipe penetrating the embankments; and
- H. An alternative method of pond lining that provides equivalent or better water quality protection than provided under this section may be utilized with the prior approval of the executive director; and
- I. Reclaimed water may be stored in leak-proof, fabricated tanks;
- J. Subsequent holding ponds utilized for the receipt and storage of reclaimed water of a quality that could cause or causes a violation of a surface water quality standard or impairment of groundwater for its actual or intended use will be also subject to the storage requirements of this section.

III. Specific Uses and Quality Standards for Reclaimed Water

- A. Numerical parameter limits pertaining to specific reclaimed water use categories are contained in this section. These limits apply to reclaimed water before discharge to initial holding ponds or a reclaimed water distribution system.
- B. The reclaimed water producer shall establish that the reclaimed water meets the quality limits at the sample point for the intended use in accordance with the monitoring requirements identified in Section IV, Sampling and Analysis.
- C. Types and quality standards for reclaimed water.
 - Type I Reclaimed Water Use. The use of Type I reclaimed water is for situations
 where the public may come in contact with the reclaimed water. The uses allowed by
 this authorization are:
 - a. Irrigation of right-of-ways, parks, open space/greenbelt areas, parks, landscape areas.
 - b. Make up water in off-channel water quality ponds.
 - c. Type I reclaimed water may also be used for any of the Type II.
 - 2. The following conditions apply to Type I use of reclaimed water. At a minimum, the reclaimed water producer shall transfer only reclaimed water of the following quality

as described for Type I reclaimed water use. Type I reclaimed water on a 30-day average must have a quality of no more than:

Table 1. Type I Quality Requirements

14010 11 13 10 1 4 1		
Parameter	Limit	Limit Type
Turbidity	3 NTUs	30-day average
CBOD ₅	5 mg/l	30-day average
Fecal coliform or E. coli	20/100 ml	30-day geometric mean (MPN or CFU)
Fecal coliform or E. coli	75/100 ml	maximum single grab sample (MPN or CFU)

- 3. Type II Reclaimed Water Use. The use of Type II reclaimed water is for situations where the public will not be exposed to the reclaimed water. The uses allowed by this authorization are:
 - a. Irrigation of right-of-ways, parks, open space/greenbelt areas, landscape areas where human access is restricted or unlikely to occur, or when the sites are not used by the public when times of irrigation operations are in progress
 - b. Make up water in water quality ponds where direct human contact is not likely
 - c. Commercial process and cooling tower makeup water
 - d. Construction water, soil compaction and dust control where application procedures minimize aerosol drift to public areas
 - e. Re-vegetation of disturbed areas where application procedures minimize aerosol drift to public areas.
- 4. The following conditions apply to Type II use of reclaimed water. At a minimum, the reclaimed water producer shall transfer only reclaimed water of the following quality. Type II reclaimed water on a 30-day average must have a quality of no more than:

Table 2. Type II Quality Requirements

Table 2. Type II	Quanty Kequirem	lents
Parameter	Limit	Limit Type
CBOD ₅	15, mg/l	30-day average
Fecal coliform or E. coli	200/100 ml	30-day geometric mean (MPN or CFU)
Fecal coliform or E. coli	800/100 ml	maximum single grab sample (MPN or CFU)

-D.-Test-Procedures -- -- -

- Test procedures for the analysis of pollutants must comply with procedures specified in 30 TAC §§319.11 - 319.12. Measurements, tests, and calculations must accurately represent the reclaimed water.
- 2. All laboratory tests submitted to demonstrate compliance with this authorization must meet the requirements of 30 TAC Chapter 25, *Environmental Testing Laboratory Accreditation and Certification*.

IV. Sampling and Analysis

- A. The reclaimed water producer shall sample the reclaimed water prior to distribution to the entity that first received the reclaimed water after it leaves the wastewater treatment facility (provider or user) to assure that the water quality meets the standard for the contracted use.
- B. Analytical methods must be in compliance with 30 TAC Chapter 319, Monitoring and

Reporting.

- C. The minimum sampling and analysis frequency for Type I reclaimed water is twice per week when reclaimed water is being produced and shall be reported as outfall 800.
- D. The minimum sampling and analysis frequency for Type II reclaimed water is once per week when reclaimed water is being produced and shall be reported as outfall 900.
- E. The monitoring must be done after the final treatment unit.
- F. The records of the monitoring must be kept on a monthly basis and be available at the facility site for inspection by representatives of the Commission for at least five years.

V. Record Keeping and Reporting

- A. The reclaimed water provider and user shall maintain records on site for a period of at least five years.
- B. The producer shall maintain the following records:
 - 1. copies of notifications made to the commission concerning reclaimed water projects;
 - 2. as applicable, copies of contracts with each reclaimed water user (this requirement does not include reclaimed water users at residences that have separate distribution lines for potable water);
 - 3. records of the volume of water delivered to each reclaimed water user per delivery (this requirement does not apply to reclaimed water users at residences that have separate distribution lines for potable water); and
 - 4. reclaimed water quality analyses.
- C. The reclaimed water producer shall report to the commission on a monthly basis the following information on forms furnished by the executive director. The reports are due by the 20th day of the month following the reporting period.
 - 1. volume of reclaimed water delivered to each user; and
 - quality of reclaimed water delivered to a user or provider reported as a monthly average for each quality criteria, except those listed as "not to exceed" that must be reported as individual analyses..

VI. Transfer of Reclaimed Water

- A. Reclaimed water must be transferred from a provider to a user on a demand only basis. A reclaimed water user may refuse delivery of reclaimed water at any time.
- B. All reclaimed water transferred to a user must be of at least the quality specified in Section IV, Sampling and Analysis.
- C. Transfer must be by pipes or tank trucks.
- D. The transfer of reclaimed water must be terminated immediately if a provider becomes aware of the misuse of the reclaimed water by the user, regardless of contract provisions.

VII. Restrictions

- A. This authorization does not convey any property right and does not grant any exclusive privilege.
- B. This authorization does not allow the use of reclaimed water on land that is authorize as a disposal site under either a Texas Pollutant Discharge Elimination System (TPDES) permit or a Texas Land Application Permit (TLAP).

VIII. Responsibilities and Contracts

- A. The producer of reclaimed water is not liable for misapplication of reclaimed water by users, except as provided in this section. Both the reclaimed water provider and user have at least but are not limited to the following responsibilities:
 - 1. The reclaimed water producer shall:
 - a. transfer reclaimed water of at least the minimum quality required by this chapter at the point of delivery to the user;
 - sample and analyze the reclaimed water and report the analyses in accordance with Section IV, Sampling and Analysis, and Section V, Recordkeeping and Reporting; and
 - c. notify the executive director in writing within five (5) days after obtaining knowledge of reclaimed water use not authorized by the executive director.
 - 2. The reclaimed water provider shall:
 - ensure construction of reclaimed water distribution systems in accordance with 30 TAC Chapter 217, Design of Domestic Wastewater Systems, and in accordance with approved plans and specifications;
 - b. transfer reclaimed water of at least the minimum quality required by this authorization at the point of delivery to the user;
 - c. notify the executive director in writing within five (5) days after obtaining knowledge of reclaimed water use not authorized by the executive director; and
 - d. not be found in violation of this chapter for the misuse of the reclaimed water by the user if transfer of such water is shut off promptly upon knowledge of misuse regardless of contract provisions.
 - 3. The reclaimed water user shall:
 - a. use the reclaimed water in accordance with this authorization; and
 - maintain and provide records as required by Section V, Record Keeping and Reporting.

IX. Enforcement

If the producer, provider, or user fail to comply with the terms of this authorization, the executive director may take enforcement action provided by the Texas Water Code §26.019 and §26.0136.


X. Standard Provisions

- A. This authorization is granted in accordance with the rules and orders of the commission and the laws of the state of Texas.
- B. Acceptance of this authorization constitutes an acknowledgment and agreement that the producer, provider and user will comply with all the terms, provisions, conditions, limitations and restrictions embodied in this authorization and with the rules and other orders of the commission and the laws of the state of Texas. Agreement is a condition precedent to the granting of this authorization.

amende da est, est précione tentre de le se de dada direjo de l'accepto aduat que po Poseeron desert Autro Volendo da est est de la companya de l'ouve dag se paradolistica.

างร้อง ซีซึ่ง มีของที่สาม **เมือง**ร้องสุดเลอ เหลืาของทำนางสุดเกลียา และส่งรัฐรายสามารถหลุดเรื่อง เล

XI. Service Area Map



Bryan W. Shaw, Ph.D., Chairman Carlos Rubinstein, Commissioner Toby Baker, Commissioner Zak Covar, Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

July 9, 2012

MR ROBERT P CALLEGARI PE CMA ENGINEERING INC 235 LEDGE STONE DRIVE AUSTIN, TEXAS 78737

Re:

HAYS COUNTY MUD NO 4

LEDGE STONE SUBDIVISION RECLAIMED WATER PUMP STATION

PERMIT NO 14309-001 WWPR LOG NO 0712/015 CN602690661 RN103897567

HAYS COUNTY

Dear Mr. Callegari:

We have received the project summary transmittal letter date July 6, 2012.

The rules which regulate the design, installation and testing of domestic wastewater projects are found in 30 TAC, Chapter 217, of the Texas Commission on Environmental Quality (TCEQ) rules titled, <u>Design Criteria for Wastewater Systems</u>.

Section 217.6(d), relating to case-by-case reviews, states in part that upon submittal of a summary transmittal letter, the executive director may approve of the project without reviewing a complete set of plans and specifications.

Under the authority of §217.6(e) a technical review of complete plans and specifications is not required. However, the project proposed in the summary transmittal letter is approved for construction. Please note, that this conditional approval does not relieve the applicant of any responsibilities to obtain all other necessary permits or authorizations, such as wastewater treatment permit or other authorization as required by Chapter 26 of the Texas Water Code. Below are provisions of the Chapter 217 regulations, which must be met as a condition of approval. These items are provided as a reminder. If you have already met these requirements, please disregard this additional notice.

1. You must keep certain materials on file for the life of the project and provide them to TCEQ upon request. These materials include an engineering report, test results, a summary transmittal letter, and the final version of the project plans and specifications. These materials shall be prepared and sealed by a Professional Engineer licensed in the State of Texas and must show substantial compliance with Chapter 217. All plans and specifications must conform to any waste discharge requirements authorized in a permit by the TCEQ. Certain specific items which shall be addressed in the engineering report

MR Robert P Callegari PE Page 2 July 9, 2012

are discussed in $\S217.6(c)$. Additionally, the engineering report must include all constants, graphs, equations, and calculations needed to show substantial compliance with Chapter 217. The items which shall be included in the summary transmittal letter are addressed in $\S217.6(c)(1)$ -(10).

- 2. Any deviations from Chapter 217 shall be disclosed in the summary transmittal letter and the technical justifications for those deviations shall be provided in the engineering report. Any deviations from Chapter 217 shall be based on the best professional judgement of the licensed professional engineer sealing the materials and the engineer's judgement that the design would not result in a threat to public health or the environment.
- 3. Any variance from a Chapter 217 requirement disclosed in your summary transmittal letter is approved. If in the future, additional variances from the Chapter 217 requirements are desired for the project, each variance must be requested in writing by the design engineer. Then, the TCEQ will consider granting a written approval to the variance from the rules for the specific project and the specific circumstances.
- 4. Within 60 days of the completion of construction, an appointed engineer shall notify both the Wastewater Permits Section of the TCEQ and the appropriate Region Office of the date of completion. The engineer shall also provide written certification that all construction, materials, and equipment were substantially in accordance with the approved project, the rules of the TCEQ, and any change orders filed with the TCEQ. All notifications, certifications, and change orders must include the signed and dated seal of a Professional Engineer licensed in the State of Texas.

This approval does not mean that future projects will be approved without a complete plans and specifications review. The TCEQ will provide a notification of intent to review whenever a project is to undergo a complete plans and specifications review. Please be reminded of §217.5 of the rules which states, "Approval given by the executive director...shall not relieve the sewerage system owner or the design engineer of any liabilities or responsibilities with respect to the proper design, construction, or authorized operation of the project in accordance with applicable commission rules."

If you have any questions or if we can be of any further assistance, please call me at (512) 239-4552.

Sincerely

Louis C. Herrin, III, P.E.

Wastewater Permits Section (MC 148)

Water Quality Division

Texas Commission on Environmental Quality

LCH/mac

cc: TCEQ, Region 11 Office

Bryan W. Shaw, Ph.D., Chairman Buddy Garcia, Commissioner Carlos Rubinstein, Commissioner Mark R. Vickery, P.G., Executive Director



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

March 23, 2010

Ms. Christina McCutchin, President Havs County Municipal Utility District 4 600 Congress Street, Suite 2100 Austin, Texas 78701-2986

Re:

Hays County Municipal Utility District 4 Reuse Authorization No. R14309001 CN602690661, RN1103897567 Hays County

Dear Ms. McCutchin:

The Texas Commission on Environmental Quality has completed its review of the application for the above referenced authorization. The authorization allows the reuse of Type II wastewater effluent from Hays County MUD 4 wastewater treatment facility.

Notify this office and the appropriate regional office at least 30 days before reclaimed water from this facility is distributed. If the plans and specifications for the project have been approved, the authorization will be activated and the facility will be issued monthly effluent report (MER) forms for reporting quality and quantity of reclaimed water used. See Requirement V(b) on page 9 of the attached authorization.

Thank you for your cooperation during this review process. If you have any questions, please contact Sherry Smith of my staff at shesmith@tceq.state.tx.us or (512) 239-0571.

Sincerely

Chris Linendoll, Manager Wastewater Permitting Section

Water Quality Division

CL/SS/ms



AUTHORIZATION FOR RECLAIMED WATER

Producer:

Hays County Municipal Utility District 4

600 Congress Street, Suite 2100 Austin, Texas 78701-2986

CN602690661

Provider:

Hays County Municipal Utility District 4

600 Congress Street, Suite 2100 Austin, Texas 78701-2986

RN103897567

User:

Hays County Municipal Utility District 4

600 Congress Street, Suite 2100 Austin, Texas 78701-2986

Location:

The wastewater treatment facilities and disposal site are located approximately 2,050 feet

north of U.S. Highway 290 and approximately 7.2 miles west of the intersection of U.S.

Highway 290 with Texas Highway 71 in Hays County, Texas.

Authorization: Type II reclaimed water from the Hays County MUD 4's Wastewater Treatment Facility

(TPDES Permit No. WQ0014309001) to be used for irrigation and industrial process water.

The service area is Ledge Stone development as shown in Attachment A.

This authorization contains the conditions that apply for the use of reclaimed water. The approval of a reclaimed water use project under Chapter 210 does not affect any existing water rights. If applicable, a reclaimed water use authorization in no way affects the need of a producer, provider, or user to obtain a separate water right authorization from the commission. This authorization does not allow irrigation of any area authorized for irrigation under a Texas Land Application Permit.

This action is taken under authority of the Executive Director of the Texas Commission on Environmental Quality.

Issue Date: March 23, 2010

Hays County MUD 4 Reclaimed Water Authorization No. R14309001 Page 2

The authorization is subject to the following requirements:

I. General Requirements

- (a) No producer or provider may begin transferring reclaimed water to a user without first notifying the commission.
- (b) Reuse of untreated wastewater is prohibited.
- (c) Food crops that may be consumed raw by humans must not be spray irrigated. Food crops including orchard crops that will be substantially processed prior to human consumption may be spray irrigated. Other types of irrigation that avoid contact of reclaimed water with edible portions of food crops are acceptable.
- (d) There must be no nuisance conditions resulting from the distribution, the use, and/or storage of reclaimed water.
- (e) Reclaimed water must not be used in a way that degrades groundwater quality to a degree adversely affecting its actual or potential uses.
- (f) Reclaimed water stored in ponds must be prevented from discharging into waters in the state, except for discharges directly resulting from rainfall events, in accordance with a permit issued by the commission, or as authorized under the Hays County MUD 4 wastewater treatment facility (TPDES No. WQ0014309001). All other discharges are unauthorized. If an overflow of a holding pond occurs causing discharge into or adjacent to waters in the state, the user or provider, as appropriate, shall report the noncompliance. A written submission of pertinent information must be provided to the TCEQ Region 11 office in Austin and to the TCEQ Enforcement Division (MC-149) in Austin, within five (5) working days after becoming aware of the overflow. The written submission must contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the anticipated time it is expected to continue; and, steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
- (g) Unless otherwise provided in this authorization, there must be no off-site discharge, either airborne or surface runoff, of reclaimed water from the user's property except to a wastewater treatment collection system or wastewater treatment facility unless the reclaimed water user applies for and obtains a permit from the commission that authorizes discharge of the water.
- (h) All reclaimed water piping must be separated from potable water piping when trenched by a distance of at least nine feet. All buried pipe must be manufactured in purple, painted purple, taped with purple metallic tape or bagged in purple. All exposed piping, hose bibs and faucets must be painted purple, designed to prevent connection to a standard water hose, and stenciled with a warning reading "NON-POTABLE WATER."

- (i) The design of any new distribution system that will convey reclaimed water to a user requires the approval of the executive director. Materials must be submitted to the executive director in accordance with the Texas Engineering Practice Act (Article 3271a, Vernon's Annotated Texas Statutes). The plans and specifications for any new distribution system constructed pursuant to this authorization must be approved by the executive director. Failure to secure approval before commencing construction or making a transfer of reclaimed water is a violation of this authorization. Each day of a transfer is a separate violation until approval has been secured.
- (j) Nothing in this authorization modifies any requirements in 30 TAC Chapter 290, Public Drinking Water.
- (k) A major change from a prior notification for use of reclaimed water must be approved by the executive director before it can be implemented. A major change includes:
 - (1) a change in the boundary of the approved service area, not including the conversion of individual lots within a subdivision to reclaimed water use;
 - (2) the addition of a new producer;
 - (3) a major change in the intended use, such as conversion from irrigation of a golf course to residential irrigation; or
 - (4) a change from either Type I or Type II use to the other.
- (l) The reclaimed water producer, provider, and user shall maintain current operation and maintenance plans on the sites over which they have operational control. The operation and maintenance plan must contain the following, as a minimum:
 - (1) a copy of the signed contract between the user and provider and/or a copy of the signed contract between the provider and the producer;
 - (2) a labeling and separation plan for the prevention of cross connections between reclaimed water distribution lines and potable water lines;
 - (3) the measures that will be implemented to prevent unauthorized access to reclaimed water facilities (e.g., secured valves);
 - (4) procedures for monitoring reclaimed water;
 - (5) a plan for how reclaimed water use will be scheduled to minimize the risk of inadvertent human exposure;
 - (6) schedules for routine maintenance;
 - (7) a plan for worker training and safety; and
 - (8) contingency plan for system failure or upsets.

- (m) One of the following requirements must be met by the user or provider, for any area where reclaimed water is stored or where there are hose bibs or faucets:
 - (1) Signs having a minimum size of eight inches by eight inches must be posted at all storage areas and on all hose bibs and faucets reading, in both English and Spanish, "Reclaimed Water, Do Not Drink" or similar warning.
 - (2) The area must be secured to prevent access by the public.
- (n) Where a reclaimed water line parallels a sewer line, the reclaimed water line must be constructed in accordance with subsection (p) or (q) of this section. The horizontal separation distance must be three feet (outside to outside) with the reclaimed water line at the level of or above the sewer line. Reclaimed water lines that parallel sewer lines may be placed in the same benched trench. Where a reclaimed water line crosses a sewer line, the requirement of 30 TAC §290.44(e)(4)(B), Water Line Installation—crossing lines, must be followed with the reclaimed water line substituted for the water line.
- (o) Reclaimed water lines that transport reclaimed water under pressure must be sized according to acceptable engineering practices for the needs of the reclaimed water users. The provider shall prevent high velocity scouring and maintain adequate fluid velocity to prevent the deposition of solids in the lines. Pipe specified for reclaimed water force mains must have an expected life of at least as long as that of the associated lift station and must be suitable for the reclaimed water being pumped and operating pressure to which it will be subjected. All pipe must be identified in the technical specifications with appropriate American Society for Testing and Materials, American National Standard Institute, or American Water Works Association standard numbers for both quality control (dimensions, tolerance, and installation such as bedding or backfill). All pipes and fittings must have a minimum working pressure rating of 150 pounds per square inch. Final plans and specifications must describe required pressure testing for all installed reclaimed water force mains. Minimum test pressure must be 1.5 times the maximum design pressure. Allowable leakage rates must be determined as described in 30 TAC §217.97, *Pressure Sewer Systems*.
- (p) Gravity flow reclaimed water lines must meet the requirements of 30 TAC Chapter 217, Subchapter C, Conventional Collection Systems. The provider shall prevent high velocity scouring and maintain adequate fluid velocity to prevent the deposition of solids in the lines.
- (q) All exposed piping and piping within a building must be either purple pipe or painted purple. All exposed piping should be stenciled in white with a warning reading "NON-POTABLE WATER." All exposed or buried reclaimed water piping constructed at a wastewater treatment facility is exempt from the color-coding requirement of this section.
- (r) When applicable, in accordance with 30 TAC Chapter 217, Design Criteria for Domestic Wastewater Systems, the design of the distribution systems that will convey reclaimed water to a user must be submitted to the executive director and must receive an approval before the distribution system may be constructed. The design of the distribution systems must meet the criteria of 30 TAC Chapter 217, Design Criteria for Domestic Wastewater Systems. When a municipality is the plan review authority for certain sewer systems that transport primarily

- domestic waste, in lieu of the commission, design submittal will not be subject to submittal to the commission and instead must be approved by the municipality.
- (s) All ground level and elevated storage tanks must be designed, installed, and constructed in accordance with current AWWA standards with reference to materials to be used and construction practices to be followed, except for health-based standards strictly related to potable water storage and contact practices, where appropriately less restrictive standards may be applied.

II. Storage Requirements for Reclaimed Water

- (a) Storage facilities for retaining reclaimed water prior to use must not be located within a floodway.
- (b) Outside the Edwards Aquifer Recharge Zone and the DRASTIC Zone
 - (1) Any holding pond designed to contain Type I or Type II effluent must have a lining with a permeability of no more than 1 x 10⁻⁴cm/sc and conform to the following requirements:
 - (A) The ponds must be designed and constructed to prevent groundwater contamination;
 - (B) Soils used for pond lining must be free from foreign material such as paper, brush, trees, and large rocks; and
 - (C) All soil liners must be of compacted material, at least 24 inches thick, compacted in lifts no greater than 6 inches thick and compacted to 95% of Standard Proctor Density. In-situ clay soils meeting the soils liner requirements must be excavated and re-compacted a minimum of 6 inches below planned grade to assure a uniformly compacted finished surface.
 - (D) Soil liners must meet the following particle size gradation and Atterberg limits:
 - (i) 30% or more passing a number 200 mesh sieve; and
 - (ii) a liquid limit of 30% or greater; and a plasticity index of 15 or greater and have a permeability less than or equal to 1 X 10⁻⁴ cm/sec;
 - (E) Synthetic membrane linings must have a minimum thickness of 40 mils and have a leak detection system. In situ liners at least 24 inches thick meeting a permeability less than or equal to 1 X 10⁻⁴ cm/sec are acceptable alternatives;

- (F) Certification by a Texas licensed professional engineer must be furnished stating that the pond liner meets the appropriate criteria prior to use of the facilities;
- (G) Soil embankment walls must have a top width of at least five feet. The interior and exterior slopes of soil embankment walls must be no steeper than one foot vertical to three feet horizontal unless alternate methods of slope stabilization are used. All soil embankment walls must be protected by a vegetative cover or other stabilizing material to prevent erosion. Erosion stops and water seals must be installed on all pipe penetrating the embankments; and
- (H) An alternative method of pond lining that provides equivalent or better water quality protection than provided under this section may be used with the prior approval of the executive director.
- (2) Reclaimed water may be stored in leak-proof, fabricated tanks.
- (3) Subsequent holding ponds used for the receipt and storage of reclaimed water of a quality that could cause or causes a violation of a surface water quality standard or impairment of groundwater for its actual or intended use will be also subject to the storage requirements of this section.

III. Specific Uses and Quality Standards for Reclaimed Water

- (a) Numerical parameter limits pertaining to specific reclaimed water use categories are contained in this section. These limits apply to reclaimed water before discharge to initial holding ponds or a reclaimed water distribution system.
- (b) The reclaimed water producer shall establish that the reclaimed water meets the quality limits at the sample point for the intended use in accordance with the monitoring requirements identified in Section IV, Sampling and Analysis.
- (c) Types and quality standards for reclaimed water.
 - (1) Type II Reclaimed Water Use. The use of Type II reclaimed water is for situations where the public will not come in contact with the reclaimed water. The uses allowed by this authorization are:
 - Irrigation of sod farms, silviculture, limited access highway rights of way, and other areas where human access is restricted or unlikely to occur. The methods of restricting access to areas under irrigation with reclaimed water could include the following:
 - The irrigation site is considered to be remote.

- The irrigation site is bordered by walls or fences and access to the site is controlled by the owner/operator of the irrigation site.
- The irrigation site is not used by the public during the times when irrigation operations are in progress. Such sites may include golf courses, cemeteries, and landscaped areas surrounding commercial or industrial complexes. The "syringing" or "wetting" of greens and tees on golf courses is allowable under Type II so long as the "syringing" is done with hand-held hoses as opposed to automatic irrigation equipment. The public need not be excluded from areas where irrigation is not taking place. For example, irrigation of golf course fairways at night would not prohibit the use of club house or other facilities located a sufficient distance from the irrigation.
- The irrigation site is restricted from public access by local ordinance or law with specific standards to achieve such a purpose.
- Irrigation of food crops if the reclaimed water is not likely to have direct contact
 with the edible part of the crop, or if the food crop undergoes pasteurization
 prior to distribution for consumption.
- o Irrigation of animal feed crops other than pasture for milking animals.
- Maintenance of impoundments or natural water bodies where direct human contact is not likely.
- Soil compaction or dust control in construction areas where application procedures minimize aerosol drift to public areas.
- O Cooling tower makeup water. Use for cooling towers that produce significant aerosols adjacent to public access areas may have special requirements.
- Irrigation or other non-potable uses of reclaimed water at a wastewater treatment facility.
- Type I reclaimed water may also be used for any of the Type II uses identified in 30 TAC §210.32.
- (2) The following conditions apply to Type II use of reclaimed water. At a minimum, the reclaimed water producer shall transfer only reclaimed water of the following quality. Type II reclaimed water on a 30-day average must have a quality of no more than:

CBOD₅

20 mg/l

Fecal coliform or E. coli

200 CFU/100 ml*

Fecal coliform or E. coli

800 CFU/100 ml**

- * 30-day geometric mean
- ** maximum single grab sample

(d) Test Procedures

- (1) Test procedures for the analysis of pollutants must comply with procedures specified in 30 TAC §§319.11 319.12. Measurements, tests, and calculations must accurately represent the reclaimed water.
- (2) All laboratory tests submitted to demonstrate compliance with this authorization must meet the requirements of 30 TAC Chapter 25, *Environmental Testing Laboratory Accreditation and Certification*.

IV. Sampling and Analysis

- (a) The reclaimed water producer shall sample the reclaimed water prior to distribution to the entity that first received the reclaimed water after it leaves the wastewater treatment facility (provider or user) to assure that the water quality meets the standard for the contracted use.
- (b) Analytical methods must be in compliance with 30 TAC Chapter 319, Monitoring and Reporting.
- (c) The minimum sampling and analysis frequency for Type II reclaimed water is once per week.
- (d) The monitoring must be done after the final treatment unit.
- (e) The records of the monitoring must be kept on a monthly basis and be available at the facility site for inspection by representatives of the Commission for at least five years.

V. Record Keeping and Reporting

- (a) The reclaimed water provider and user shall maintain records on site for a period of at least five years.
- (b) Records to be maintained by the provider include:
 - (1) copies of notifications made to the commission concerning reclaimed water projects;

- (2) as applicable, copies of contracts with each reclaimed water user (this requirement does not include reclaimed water users at residences that have separate distribution lines for potable water);
- (3) records of the volume of water delivered to each reclaimed water user per delivery (this requirement does not apply to reclaimed water users at residences that have separate distribution lines for potable water); and
- (4) reclaimed water quality analyses.
- (c) The reclaimed water provider or producer shall report to the commission on a monthly basis the following information on forms furnished by the executive director. The reports are due by the 20th day of the month following the reporting period.
 - (1) volume of reclaimed water delivered to provider; and
 - (2) quality of reclaimed water delivered to a user or provider reported as a monthly average for each quality criteria, except those listed as "not to exceed" that must be reported as individual analyses.
- (d) The provider shall provide written notice to the Water Quality Application Team (MC 148) and the appropriate TCEQ regional office at least thirty (30) days prior to transfer of reclaimed water.

VI. Transfer of Reclaimed Water

- (a) Reclaimed water transferred from a provider to a user must be done on a demand only basis.

 A reclaimed water user may refuse delivery of reclaimed water at any time.
- (b) All reclaimed water transferred to a user must be of at least the quality specified in Section IV, Sampling and Analysis.
- (c) Transfer must be accomplished by pipes or tank trucks.
- (d) The transfer of reclaimed water must be terminated immediately if a provider becomes aware of the misuse of the reclaimed water by the user, regardless of contract provisions.

VII. Restrictions

- (a) This authorization does not convey any property right and does not grant any exclusive privilege.
- (b) This authorization does not allow the use of reclaimed water on a land that is authorized as a disposal site under either a Texas Discharge Pollutant Elimination System (TPDES) permit or a Texas Land Application Permit (TLAP).

VIII. Responsibilities and Contracts

- (a) The producer of reclaimed water is not liable for misapplication of reclaimed water by users, except as provided in this section. Both the reclaimed water provider and user have at least but are not limited to the following responsibilities:
 - (1) The reclaimed water producer shall:
 - (A) transfer reclaimed water of at least the minimum quality required by this chapter at the point of delivery to the user;
 - (B) sample and analyze the reclaimed water and report the analyses in accordance with Section IV, Sampling and Analysis, and Section V, Recordkeeping and Reporting; and
 - (C) notify the executive director in writing within five (5) days after obtaining knowledge of reclaimed water use not authorized by the executive director.
 - (2) The reclaimed water provider shall:
 - (A) ensure construction of reclaimed water distribution lines/systems in accordance with 30 TAC Chapter 217, Design of Domestic Wastewater Systems, and in accordance with approved plans and specifications;
 - (B) transfer reclaimed water of at least the minimum quality required by this authorization at the point of delivery to the user;
 - (C) notify the executive director in writing within five (5) days after obtaining knowledge of reclaimed water use not authorized by the executive director; and
 - (D) not be found in violation of this chapter for the misuse of the reclaimed water by the user if transfer of such water is shut off promptly upon knowledge of misuse regardless of contract provisions.
 - (3) The reclaimed water user shall:
 - (A) use the reclaimed water in accordance with this authorization; and
 - (B) maintain and provide records as required by Section V, Record Keeping and Reporting.

Hays County MUD 4 Reclaimed Water Authorization No. R14309001 Page 11


IX. Enforcement

If the producer, provider, or user fail to comply with the terms of this authorization, the executive director may take enforcement action provided by the Texas Water Code §26.019 and §26.136.

X. Standard Provisions

- (a) This authorization is granted in accordance with the rules and orders of the commission and the laws of the state of Texas.
- (b) Acceptance of this authorization constitutes an acknowledgment and agreement that the provider and user will comply with all the terms, provisions, conditions, limitations and restrictions embodied in this authorization and with the rules and other orders of the commission and the laws of the state of Texas. Agreement is a condition precedent to the granting of this authorization.

Attachment A



Westwood

ATTACHMENT #15 – ANNUAL CROPPING PLAN

Annual Cropping Plan

The proposed cropping and maintenance plan for the wastewater application areas (subsurface area drip disposal system) is to remove any small trees in the field area, smooth the fields, install the dripper lines, place soil if needed, and overseed with Bermuda grass. The fields will be over seeded with winter rye grass during the cool season to ensure year round uptake of water and nutrients. The Bermuda grass will grow from March to October. The Rye grass will grow from November to February. The fields will be mowed regularly and maintain a vegetative height of approximately 3- 6 inches, to ensure that the grasses will be actively growing at all times. No supplemental irrigation will be needed.

There are no plans to fertilize the grasses other than natural germination. Fertility recommendations for the grasses to be used at this site are generally 100-150 lbs/acre of Nitrogen. The grasses will be fertilized for germination and it is not anticipated that future fertilization will be required.

Turf grasses are very salt tolerant and this site is not expected develop salinity problems.

The grass will only be harvested to maintain vigorous growth in the fields. This will be done when the operator determines that there is stress on the fields.

Site Preparation Plan

The items below have been prepared in accordance with 30 TAC Chapter 222.75.

- (1) A site plan to minimize rainfall run-on and maximize rainfall runoff from the dispersal zones. Berms or swales will be constructed upstream of the drip irrigation fields to avoid rainfall run-on. Subsurface drip irrigation lines will not be constructed in areas that evidence of rainfall channeling can be seen. Any grading changes necessary to prevent the drip irrigation areas from receiving and retaining stormwater runoff will be made.
- (2) Design criteria to compensate for any restrictive horizons within the soil column. A restrictive horizon was encountered in one soil profile hole. In these areas of shallow soils, soil will be imported to ensure that the soil column is of the appropriate depth.
- (3) Soil importation with descriptions of the chemical and physical characteristics of the proposed import material. Sandy Loam will be imported to the site.
- (4) Any planned removal of existing vegetation. There are minimal trees in the proposed drip disposal areas. In those areas that do contain trees, small trees will be removed from the site and the large trees will remain. The entire site will be overseeded with turf grass.

Westwood

ATTACHMENT #16 - SOIL MAP

Westwood

ATTACHMENT #17- SOIL ANALYSIS



Hays County MUD 4 Municipal Operations and Consulting 20141 Schiel Road Cypress, TX 77433

P.O. Box 1089 Coldspring Tx 77331 Website: eastexlabs.com Email: eastexlab@eastex.net Tel: 936 653 3249



LABORATORY ANALYTICAL REPORT

Project: Hay County MUD 4 Drip Fields

Sample Site: Sample Type:	Soil Depth 0-6 Composite			Sample Numb 4350695-0				llector: npled:	AG 08/27/2024	10:21
Sample Matrix:	Waste						Re	eived:	08/27/2024	15:50
Client Matrix:	Soil									
			Reporting		Nelac					
Analyte		Result	Limit	Units	Status	Batch	Analyzed	Analyst	Method	Notes
Conductivity 2:1 E	xtract	398	10	μmhos/cm @25C	Α	B4H4210	08/28/2024 19:4	I ARB	EPA SW 846-9050A	
NH4-N mg/kg		4.04	0.0120	mg/Kg dry	N	B4H4133	08/29/2024 14:3	0 LAN	EPA 350.2 KCI extract	
Nitrate as N		49.9	0.6	mg/Kg dry	N	B4H4241	08/28/2024 19:5	0 OCR	SM 4500 NO3F KCI extract	9
Percent Solid		83.2	0.1	%	Α	B4H4209	08/28/2024 16:0	6 ARB	SM 2540G	
pH Soil		7.2		std unit	A	B4H4437	08/29/2024 18:5	0 CNS	EPA SW 846-9045	
Phosphorus, Extrac	et - mg/Kg	3.05	0.120	mg/Kg dry	Α	B4H3645	08/28/2024 15:0	4 KJH	EPA SW 846-6010, 3050	
Potassium, Extract	mg/Kg	293	0.601	mg/Kg dry	A	B4H3643	08/28/2024 13:1	9 КЈН	EPA SW 846-6010, 3050	
TKN, soil		17.2	12.0	mg/Kg dry	N	B4H4193	08/29/2024 08:0	0 TDS	EPA 351.2	
Total Nitrogen		67.1		mg/Kg		B4H4435	08/30/2024 11:1	8 TMH	-	





Hays County MUD 4 Municipal Operations and Consulting 20141 Schiel Road Cypress, TX 77433

Sample Site: Soil Depth 6-18 Sample Type: Composite			Sample Numb				lector:	AG 08/27/2024	10:21
Sample Matrix: Waste Client Matrix: Soil			4330093-0	4			eived:	08/27/2024	
Analyte	Result	Reporting Limit	Units	Nelac Status	Batch	Analyzed	Analyst	Method	Notes
Conductivity 2:1 Extract	336	10	μmhos/cm @25C	A	B4H4210	08/28/2024 19:41	ARB	EPA SW 846-9050A	
NH4-N mg/kg	2.70	0.0121	mg/Kg dry	Ν	B4H4133	08/29/2024 14:30	LAN	EPA 350.2 KCI extract	
Nitrate as N	42.9	0.6	mg/Kg dry	$V_{\bar{i}}$	B4H4241	08/28/2024 19:50	OCR	SM 4500 NO3F KCl extract	94
Percent Solid	82.9	0.1	%	Α	B4H4209	08/28/2024 16:06	ARB	SM 2540G	
pH Soil	7.4		std unit	A	B4H4437	08/29/2024 18:50) CNS	EPA SW 846-9045	
Phosphorus, Extract - mg/Kg	2.47	0.121	mg/Kg dry	A	B4H3645	08/28/2024 15:05	КЈН	EPA SW 846-6010, 3050	
Potassium, Extract mg/Kg	234	0.603	mg/Kg dry	A	B4H3643	08/28/2024 13:23	КЈН	EPA SW 846-6010, 3050	
TKN, soil	35.2	12.1	mg/Kg dry	N	B4H4193	08/29/2024 08:00	TDS	EPA 351.2	
Total Nitrogen	78.1		mg/Kg		B4H4435	08/30/2024 11:18	ТМН	-	
Sample Site: Soil Depth 18-30)		Sample Numb			Col	lector:	AG	
Sample Type: Composite			4350695-0	3		San	npled:	08/27/2024	10:21
Sample Matrix: Waste									
						Rec	eived:	08/27/2024	15:50
Client Matrix: Soil						Rec	eived:		15:50
Client Matrix: Soil Analyte	Result	Reporting Limit	Units	Nelac Status	Batch		eived:		15:50 Notes
	Result		μmhos/cm		Batch B4H4210		Analyst	08/27/2024 Method EPA SW	
Analyte	· · · · · · · · · · · · · · · · · · ·	Limit		Status		Analyzed	Analyst ARB	08/27/2024 Method EPA SW 846-9050A EPA 350.2 KCI	
Analyte Conductivity 2:1 Extract	280	Limit 10	μmhos/cm @25C	Status	B4H4210	Analyzed 08/28/2024 19:41	Analyst ARB LAN	Method EPA SW 846-9050A EPA 350.2 KC1 extract SM 4500 NO3F	
Analyte Conductivity 2:1 Extract NH4-N mg/kg	280 2.71	Limit 10 0.0121	μπhos/cm @25C mg/Kg dry	Status A N	B4H4210 B4H4133	Analyzed 08/28/2024 19:41 08/29/2024 14:30	Analyst ARB LAN OCR	08/27/2024 Method EPA SW 846-9050A EPA 350.2 KCl extract	Notes
Analyte Conductivity 2:1 Extract NH4-N mg/kg Nitrate as N	280 2.71 60.6	Limit 10 0.0121 0.6	µmhos/cm @25C mg/Kg dry mg/Kg dry	Status A N N	B4H4210 B4H4133 B4H4241	Analyzed 08/28/2024 19:44 08/29/2024 14:36 08/28/2024 16:06 08/28/2024 18:56	Analyst ARB LAN OCR ARB CNS	Method EPA SW 846-9050A EPA 350.2 KCI extract SM 4500 NO3F KCI extract	Notes
Analyte Conductivity 2:1 Extract NH4-N mg/kg Nitrate as N Percent Solid	280 2.71 60.6 82.6	Limit 10 0.0121 0.6	μmhos/cm @25C mg/Kg dry mg/Kg dry	A N N A	B4H4210 B4H4133 B4H4241 B4H4209	Analyzed 08/28/2024 19:41 08/29/2024 14:3(08/28/2024 19:5(08/28/2024 16:06	Analyst ARB LAN OCR ARB CNS	Method EPA SW 846-9050A EPA 350.2 KCI extract SM 4500 NO3F KCI extract SM 2540G EPA SW	Notes
Analyte Conductivity 2:1 Extract NH4-N mg/kg Nitrate as N Percent Solid pH Soil	280 2.71 60.6 82.6 7.8	Limit 10 0.0121 0.6 0.1	µmhos/cm @25C mg/Kg dry mg/Kg dry % std unit	A N N A A	B4H4210 B4H4133 B4H4241 B4H4209 B4H4437	Analyzed 08/28/2024 19:44 08/29/2024 14:36 08/28/2024 16:06 08/28/2024 18:56	Analyst ARB ARB CRA ARB CRA CRA ARB ARB	Method EPA SW 846-9050A EPA 350.2 KC1 extract SM 4500 NO3F KC1 extract SM 2540G EPA SW 846-9045 EPA SW 846-6010, 3050 EPA SW	Notes
Analyte Conductivity 2:1 Extract NH4-N mg/kg Nitrate as N Percent Solid pH Soil Phosphorus, Extract - mg/Kg	280 2.71 60.6 82.6 7.8 0.982	Limit 10 0.0121 0.6 0.1	µmhos/cm @25C mg/Kg dry mg/Kg dry % std unit mg/Kg dry	A N N A A A	B4H4210 B4H4133 B4H4241 B4H4209 B4H4437 B4H3645	Analyzed 08/28/2024 19:44 08/29/2024 14:36 08/28/2024 19:56 08/28/2024 16:06 08/29/2024 18:56	Analyst ARB ARB CR CR ARB CR KJH	Method EPA SW 846-9050A EPA 350.2 KCI extract SM 4500 NO3F KCI extract SM 2540G EPA SW 846-9045 EPA SW 846-6010, 3050	Notes





Hays County MUD 4 Municipal Operations and Consulting 20141 Schiel Road Cypress, TX 77433

EPA SW 846-6010, 3050 - Quality Control

Eastex Environmental Laboratory - Coldspring

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch B4H3643 - Mehlich Extraction										
Blank (B4H3643-BLK1)				Prepared: (08/27/24 A	nalyzed: 08	3/28/24			
Potassium, Extract mg/Kg	ND	0.500	mg/Kg wet					· · · · · · · · · · · · · · · · · · ·		
LCS (B4H3643-BS1)				Prepared: (08/27/24 A	malyzed: 08	8/28/24			
Potassium, Extract mg/Kg	24.3		mg/L	25.0		97.2	80-120			
LCS Dup (B4H3643-BSD1)				Prepared: (08/27/24 A	.nalyzed: 08	3/28/24			
Potassium, Extract mg/Kg	24.7		mg/L	25.0		98.8	80-120	1.63	20	
Batch B4H3645 - Mehlich Extraction										
Blank (B4H3645-BLK1)				Prepared &	k Analyzed	: 08/28/24				
Phosphorus, Extract - mg/Kg	ND	0.100	mg/Kg wet		*******			······		
LCS (B4H3645-BS1)				Prepared &	k Analyzed	: 08/28/24				
Phosphorus, Extract - mg/Kg	24.065	0.100	mg/Kg wet	25.2		95.5	80-120			
LCS Dup (B4H3645-BSD1)				Prepared &	t Analyzed	: 08/28/24				
Phosphorus, Extract - mg/Kg	24.22	0.100	mg/Kg wet	25.2		96.1	80-120	0.642	20	
Batch B4H4133 - No Prep										
Blank (B4H4133-BLK1)				Prepared &	t Analyzed	: 08/29/24				W. S. W. S. C. C.
NH4-N mg/kg	ND	0.0100	mg/Kg wet		***************************************				····	
LCS (B4H4133-BS1)				Prepared &	k Analyzed	: 08/29/24				
NH4-N mg/kg	9.97	0.0100	mg/Kg wet				80-120		***************************************	····
Matrix Spike (B4H4133-MS1)	Sou	rce: 4350695	-01	Prepared &	k Analyzed	: 08/29/24				
NH4-N mg/kg	106.3702	0.0120	mg/Kg dry		4.038462	*****	80-120			*/
Matrix Spike Dup (B4H4133-MSD1)	Sou	rce: 4350695	-01	Prepared &	Ł Analyzed	: 08/29/24				
NH4-N mg/kg	118.5096	0.0120	mg/Kg dry		4.038462	***************************************	80-120	10.8	20	





Hays County MUD 4 Municipal Operations and Consulting 20141 Schiel Road Cypress, TX 77433

EPA 351.2 - Quality Control

Eastex Environmental Laboratory - Coldspring

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	D DD	RPD	
Batch B4H4193 - SM 4500 Norg C	Mesuit	Limit	Omts	LCVCI	Result	MICEC	Limis	RPD	Limit	Notes
Blank (B4H4193-BLK1)				Pranarad A	& Analyzed:	08/20/24				
TKN, soil	ND	10.0	mg/Kg wet	- repared c	x maryzeu.	VOI 2 71 24				
	ND	10.0	mg/K.g wet							
LCS (B4H4193-BS1)				*	& Analyzed:					
TKN, soil	10.6		mg/L	10.0		106	80-120			
Matrix Spike (B4H4193-MS1)	Source	e: 4350695-	01	Prepared &	& Analyzed:	08/29/24				
TKN, soil	20.32452	12.0	mg/Kg dry	3.00	17.23558	103	80-120			·
Matrix Spike Dup (B4H4193-MSD1)	Sourc	e: 4350695-	-01	Prepared &	& Analyzed:	08/29/24				
TKN, soil	20.19231	12.0	mg/Kg dry	3.00	17.23558	98.4	80-120	0.653	20	
Batch B4H4209 - No Prep										
Blank (B4H4209-BLK1)			.,	Prepared &	& Analyzed:	08/28/24		*****	******************	***************************************
Percent Solid	ND	0.1	%		***************************************					
Duplicate (B4H4209-DUP1)	Sourc	e: 4350695-	-01	Prepared &	& Analyzed:	08/28/24				
Percent Solid	84.6	0.1	%	material state of control of	83.2		····	1.67	20	
Batch B4H4210 - No Prep										
Blank (B4H4210-BLK1)				Prepared &	& Analyzed:	08/28/24				***************************************
Conductivity 2:1 Extract	ND	10	μmhos/cm @25C							
LCS (B4H4210-BS1)				Prepared &	& Analyzed:	08/28/24				
Conductivity 2:1 Extract	1000	.,,,,,	μmhos/cm @25C	1000		100	80-120			
Duplicate (B4H4210-DUP1)	Sourc	e: 4350695-	-01	Prepared &	& Analyzed:	08/28/24				
Conductivity 2:1 Extract	398	10	μmhos/cm @25C		398			0.00	20	





Hays County MUD 4 Municipal Operations and Consulting 20141 Schiel Road Cypress, TX 77433

SM 4500 NO3F KCl extract - Quality Control

Eastex Environmental Laboratory - Coldspring

		Reporting		Spike	Source		%REC		RPD	
Analyte	Result	Limit	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Batch B4H4241 - No Prep										
Blank (B4H4241-BLK1)				Prepared &	k Analyzed:	08/28/24				
Nitrate as N	ND	0.5	mg/Kg wet						~	
LCS (B4H4241-BS1)				Prepared &	k Analyzed:	08/28/24				
Nitrate as N	1.62		mg/L	1.50		108	80-120			
Matrix Spike (B4H4241-MS1)	Sour	rce: C4F8399-	-01	Prepared &	k Analyzed:	08/28/24				
Nitrate as N	675	41.7	mg/Kg dry	625	76.4	95.7	80-120			
Matrix Spike Dup (B4H4241-MSD1)	Sour	rce: C4F8399	-01	Prepared &	k Analyzed:	08/28/24				
Nitrate as N	680	41.7	mg/Kg dry	625	76.4	96.5	80-120	0.727	20	
Batch B4H4437 - No Prep										
LCS (B4H4437-BS1)				Prepared &	& Analyzed:	08/29/24				
pH Soil	6.80		std unit	6.86		99.1	80-120			
Duplicate (B4H4437-DUP1)	Sour	rce: 4350695-	01	Prepared &	& Analyzed:	08/29/24				
pH Seil	7.20		std unit		7.17		****	0.348	20	

Mar Bougéois

Mark Bourgeois, Special Projects Manager

Qualifiers

94 Sample analyzed by equivalent method.



EASTEX ENVIRONMENTAL LABORATORY, INC. 30x 1089 * Coldspring, TX 77331 P.O. Box 631375 * Naccogdoches. TX 75963-1375 Yellow Copy-Laboratory (936) 653-3249 * (800) 525-0508 (936) 569-8879 * FAX (936) 569-8951 White Copy-Follows Samples Yellow Copy-Laboratory Pink Copy-Client Copy

P.O. Box 1089 * Coldspring, TX 77331 (936) 653-3249 * (800) 525-0508

www.eastexlabs.com

Alternate Check In:	reiniquisned by:	Relinquished By:	Reiriquisned By.			en e			anticonflorge.	4350695	Work Order ID	Project Name:	Campiel a digname.	Sampler's Signature:	Sampler's Name (print):		# C	Email:	Phone#:	Attn:	on file	Address:	Company: MOC	REPORT TO:
Silles							Soil 18-30	Soil 6-18		Soil 0-8	Sample ID	HAYS CO MUD 4			1):						lle		С	
Sample Condition Acceptable.		The state of the s		- Contraction of the Contraction			8-21	8-27		8,27	Date	4					THE COMMISSION OF THE PARTY OF							
Date							1021	1021		1021	Time		Preservatives:		Contair	Matrix:	C or G:	INSTR	Phone#	Attn:		Address:	Com	INVO
able.	X ecesved	Received By:	Received by:				SO	 So		50			atives:		Container Size:			INSTRUCTIONS:	le#:			ess:	Company:	INVOICE TO:
(FO	Received by alloydr Checked in by	ed By:	ed By:				0	C		0	Matrix C or G		C=Chille	P= Plast	1=Gallor 6=125ml	DW=Drir	C= Composite	S:				on file		
Time	Checked in										DO	and a mode	d S=Su	c G= G	2=1/2 ·	nking Wat						,,		
	By.										рН	Field Data	C=Chilled S=Sulfuric Acid N=Nitric Acid B=Base/Caustic ST=Sortium Thiosulfate H=HCl O= Other	P= Plastic G= Glass T= Teflon S= Sterile	1=Gallon 2=1/2 Gallon 3=Quart/Liter 4=500mL 5= 6=125mL (4oz) 7=60mL (2 oz) 8= 40mL Vial 9=Other	DW=Drinking Water WW=Wastewater SO=Soil/Sludge OT= Other	G= Grab							
											CI2	Data	N=Nitr	eflon S=	=Quart/Li oz) 8= 4	=Wastewa								
lemp C	**										Flow		ic Acid	Sterile	ter 4=50 IOmL Vial	ater SO:								
_	-										Temp		3=Base/C		4=500mL 5=250mL L Vial 9=Other	=Soil/Slud			4	R)	Remarks:	
		Date	Date				 <u>ო</u>	<u>w</u>	十四天	<u>رن</u>	# Size	00			=250mL r	ige OT:) 	•	ks:	
	\sim 1	e	6				0	0	٢	9	ze Type	Containers	Z= Zn Acetate			: Other			1	//		<u>/</u>	-	
Logged III by	24						0	 0		0	e Pres	ST	tate							/	~			
Ÿ	ime	Time	lime	!			×	×		×	con	duct	tivity,	NF	1 3, %	so	lid,	NA	LYSI	S RE	QUE	STE	D	
	1550						×	×		×	Pri,	FIIC	os, ex	tra	ct, Po	otas	Sit	ımı	extr	act,	TKA	d. TI	4	
c L	Rece	Rece	Rece									The state of the s												
りはら	Received Iced:	Received Iced:	Received Iced:																					
اللانة اللانة	(YES)	YES /	YES /							7.1				-										
匚	NO NO	S	NO			- 1			l						-									

1	
ļ	
i	
ı	and the same of
ı	Ž
ı	1
1	~)
1	1
1	0.
ı	نہ
ı	~
ı	
ı	
	age.
ı	
	سلب
-	ない
	な
	30
	30
	S
	3500
	3500
	3500
	30

			Mehlich 3 CNR [SUB] Mehlich 3 CNR [SUB]	K TAMU Plant Available Mehlich 3 CNR [SUB] NO3N TAMU Extractable Mehlich 3 CNR [SUB] Solids, Dry Weight	[SUB] R]	Cond SL (1:2) Probe TAMU CNR [SUB] N Total TAMU CALC ENTRY [CNR] pH SL TAMU (1:2) CNR [SUB] Y Billing N Total Calc	Cond SL (N Total TA pH SL TAI Y Billing N	A TS SL Grav SM2540 G [NEL] N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehlich 3 CNR [SUB] TKN SL AUTO SM4500 NH3 G [CNR]	ATS SL Grav SM2540 G [NE N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehli TKN SL AUTO SM4500 NH3
H028214-03	図 A 1 gal Plastic Bag	S	Comp	1021	42/72/34	85 <i>b</i>	8/127/24	Hays County MUD 4 WWTP Soil 18-30 Inches	Hays County Inches
		_	Mehlich 3 CNR [SUB] Mehlich 3 CNR [SUB]	K TAMU Plant Available Mehlich 3 CNR [SUB] NO3N TAMU Extractable Mehlich 3 CNR [SUB] Solids, Dry Weight	(SUB) R]	Cond SL (1:2) Probe TAMU CNR [SUB] N Total TAMU CALC ENTRY [CNR] pH SL TAMU (1:2) CNR [SUB] Y Billing N Total Calc	Cond SL (N Total TA pH SL TAI Y Billing N	A TS SL Grav SM2540 G [NEL] N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehlich 3 CNR [SUB] TKN SL AUTO SM4500 NH3 G [CNR]	A TS SL Grav SM2540 G [NE N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehlir TKN SL AUTO SM4500 NH3
H028214-02	☑ A 1 gal Plastic Bag	S	Comp	1021	42/22/24	856	&1271/24	Hays County MUD 4 WWTP Soil 6-18 Inches	Hays County Inches
		_	Mehlich 3 CNR [SUB] Mehlich 3 CNR [SUB]	Cond SL (1:2) Probe TAMU CNR [SUB] N Total TAMU CALC ENTRY [CNR] PH SL TAMU (1:2) CNR [SUB] Y Billing Fuel Fee Y Billing Route Stop >62 min -PER HR (Add Comment Y Billing Ship to Sub-Contract Lab	R] R HR (Add Commen	Cond SL (1:2) Probe TAMU CNR [SUB] N Total TAMU CALC ENTRY [CNR] pH SL TAMU (1:2) CNR [SUB] Y Billing Fuel Fee Y Billing Route Stop >62 min -PER HR Y Billing Ship to Sub-Contract Lab	Cond SL (N Total TA pH SL TAI Y Billing F Y Billing F Y Billing R	A TS SL Grav SM2540 G [NEL] N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehlich 3 CNR [SUB] TKN SL AUTO SM4500 NH3 G [CNR] Y Billing Rental Fee Y Billing Second Sampler	A TS SL Grav SM2540 G [NE N Total SL PKG TAMU [CNR] P TAMU Plant Available Mehil TKN SL AUTO SM4500 NH3 Y Billing Rental Fee Y Billing Second Sampler
H028214-01	M A 1 gal Plastic Bag	S	Comp		8/27/24	656	8/27/24	Hays County MUD 4 WWTP Soil 0-6 Inches	Hays County Inches
Lab ID	Container (Checked box indicates bottle arrived in lab) (Volume - Type - Preservative)	Sample Matrix	Composite Type	[o2]	End Date	Start Time	Date	Field Sample ID	Pic
Cond Good	DateLab Time		Receiv- ed (print & sign)	er ID:	pH Paper ID:				
CM / CTU /	Citient Date ATL Field Time		quished (print & sign)	ntives: ter ID:	Post-Preservatives: Thermometer ID:				
□ cm / ctu	C7 へがとっ、	1tonio	1	T (C):	Temperature - CT (C):				CONTRACTOR
ূঁ ব	Client Date C/21/2	7	Receiv-	LAB RECEIPT -	- LAE				Comments:
2Y □ Iced/Refrig 7 □ CM/CTU	Dete 8/27/	me,	Relin- sy quished SWZMML sy (print & sign) SWZM	L's FoA will be subcontracted requiring accreditation will be trequiring accreditation will be d'column. The client approve st.	nnod that is not within Allails. Other analytes not the "Analysis Requested the "Analysis Requested ontract lab."	L.A.P rields of accreditation (FoA). Analytes requiring an accredited method that is not within A L.I ted for that method. Clients will be notified of the subcontract lab's details. Other analytes not retained for the specific method is required, the client will note the method in the "Analysis Requested" all method modifications documented by ATL or the subcontract lab. A current list of ATL's NELAC fields of accreditation and other methods are available on request.	tion (FoA). Analytes refers will be notified a code is required, the clip od modifications documents.	metriod that is within ALLS NELAP rieids or accreditation (FoA), Analytes requiring an accredited metriod that is not within ALLS FoA will be subcontracted to a NELAP lab that is accredited for that method. Clients will be notified of the subcontract lab's details. Other analytes not requiring accreditation will be analyzed by a compendial method. If a specific method is required, the client will note the method in the "Analysis Requested" column. The client approves all method modifications documented by ATL or the subcontract lab. A current list of ATL's NELAC fields of accreditation and other methods are available on request.	a NELAP lab a Net ap lab analyzed by a c
CM/CTU	MINDENS CONTROL NOTE TIME 1105		(print & NECION sign)	tified) Samples will be analyzed by a	= Informational only (not NELAC certified) the client agrees to the following terms. Sample, the client agrees to the following terms.	[NF] = Informational only (not NELAC certified) [NF] = Informational only (not NELAC certified) [NF] : (ATL), the client agrees to the following terms. Samples will.)	ameter Tech laboratories, In	NELAP accredited subcontracted parameter NelaP accredited subcontracted parameter NelaP accredited subcontracted parameter NelaP accredited subcontracted parameter	[SUB] = NELA By relinquishi
	ATLField Time 1005	180	_	ed by [SUB].	ocontracted, indicate sthod.	"A" prefix indicates Austin, all others Bryan or Subcontracted, indicated by [SUB]. Name format: Analysis-Matrix-Technology-Method.	fix indicates Austir me format: Analysi	Analyses Requested: "A" pre Na NEI AD accredited parameter	H
24 Iced / Refrig	Sample Custody Second Sampler Date 4/27/) Andrew	Relin- KODION quished (print &	en	Custody Maintained Custody Transfer Unbroken Corrected Temperature	CT C	74	ne (281) 367-5511 ail	
rte_ATL COC 012723.rpt	requirements unless stated otherwise.	<u> </u>	TCEQ LAB ID: T104704371	available upon request.	Non-Potable Water Solid		77433	20141 Schiel Road Cypress TX Zip	ontact ormation City State
H028214 Page 1 of 1	Austin Bryan 3512 Montopolis Dr. 635 Phil Gramm Blvd. Austin, TX 78744 Bryan, TX 77807 512.301.9559 979.778.3707	35	TNI		WTP Soil	Municipal Ops and Consulting Hays County MUD 4 WWTP Soil DW Drinking Water	Ha Mu	me:	Client / Project Name:
C-O-C #	ch laborato	Aq	SHAN WCCHEO	Request		Chain-of-Custody and Analysis	hain-of-C		AQUA-TECH

Westwood

ATTACHMENT #18 – EXCURSION DETAILS

□: Unauthorized Discharge ⊠: Reportable Effluent Violation □: Other
General Information
Entity Name: Hays County MUD 4 Telephone No: 512-461-5007
⊠: Permittee □: Subscriber
TCEQ Region: 11 County: Hays *Permit Number: WQ0014309001
Noncompliance Summary
Description of Noncompliance: Exceeded daily average, daily max, and 7 day average on effluent TSS
Excursion: TSS , Date of Excursion: Month of August, Permit Parameter: Daily Average, Permit Value: 20 mg/l, Actual Value: 28 mg/l Excursion: TSS, Date of Excursion: 8/02/2022, Permit Parameter: Daily Max, Permit Value: 45 mg/l, Actual Value: 53 mg/l Excursion: TSS, Date of Excursion: Week of 8/01/2022, Permit Parameter: 7 day Average, Permit Value: 30 mg/l, Actual Value: 53 mg/l
Cause of Noncompliance: Treatment plant upset due to clarifier cleaning last month.
Duration: Start Date and Time: 8/1/2022 12:00 AM End Date and Time: 8/31/2022 11:59 PM
Or Date Expected to be Corrected: [NSExpectedCorrected]
Potential Danger to Human Health and Safety or the Environment: No dangers identified at this time
Actions Taken
Monitoring Data: Data should be attached or submitted to TCEQ when available.
No Field Measurements Yes Laboratory Samples No Fish Kill If yes, estimated number killed: 0
Actions Taken to Mitigate Adverse Effects: N/A
Actions Taken to Correct the Problem and Prevent Recurrence: Reviewed operational changes made through the month and continuing to monitor effluent quality.
Verification Information
Information Reported By (Name/Title): <u>Jeremy Weber -Sr. Operations Manager</u>
and
Date Reported: 9/6/2022 Signature:
Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ

Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

□: Unauthorized Discharge ⊠: Reportable Effluent Violation □: Other
General Information
Entity Name: Big Sky MUD Telephone No: 512-201-3595
⊠: Permittee □: Subscriber
TCEQ Region: 4 County: Denton *Permit Number: WQ0015479001
Noncompliance Summary
Description of Noncompliance: See table below.
Excursion: Ammonia- Daily Max, Date of Excursion: 2/02/2023, Permit Parameter: Permit Value:10 mg/L, Actual Value: 14.4 mg/L
Excursion: Ammonia- 7 day avg, Date of Excursion: Week of 2/02/2023, Permit Parameter: Permit Value: 6 mg/L, Actual Value: 14.4 mg/L
Excursion: Ammonia- Daily Max, Date of Excursion: 2/07/2023, Permit Parameter: Permit Value:10 mg/L, Actual Value: 14.5 mg/L
Excursion: Ammonia- 7 day avg, Date of Excursion: Week of 2/07/2023, Permit Parameter: Permit Value: 6 mg/L, Actual Value: 14.5 mg/L
Excursion: Ammonia- Daily Max, Date of Excursion: Permit Parameter: Permit Value:10 mg/L, Actual Value: 13.9
mg/L Excursion: Ammonia- 7 day avg, Date of Excursion: Permit Parameter: Permit Value: 6 mg/L, Actual Value: 13.9 mg/L
Cause of Noncompliance: High solids in the treatment plant caused the ammonia levels to spike. Was not able to sufficiently empty digesters due to the road conditions to the facility not adequately accessible by haul trucks.
Duration: Start Date and Time: 2/2/2023 12:00 AM End Date and Time: 2/14/2023 12:00 AM
Or Date Expected to be Corrected: [NSExpectedCorrected]
Potential Danger to Human Health and Safety or the Environment: None anticipated at this time.
Actions Taken
Monitoring Data: Data should be attached or submitted to TCEQ when available.
No Field Measurements Yes Laboratory Samples No Fish Kill If yes, estimated number killed: 0
Actions Taken to Mitigate Adverse Effects: District engineers has been notified the road to the facility needs repairs to be able to properly access the treatment plant.
Actions Taken to Correct the Problem and Prevent Recurrence: Roads have since been repaired and sludge hauls have been completed to be able to properly waste the sludge.
Verification Information
Information Reported By (Name/Title): Zachary Willeford - Operations Manager
Date Reported: 2/27/2023 Signature:
Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

Guidance - Water Quality Noncompliance Notification Form

□: Unauthorized Discharge ⊠: Reportable Effluent Violation □: Other
General Information
Entity Name: Hays County MUD4 Telephone No: 512-461-5007
⊠: Permittee □: Subscriber
TCEQ Region: 11 County: Hays *Permit Number: WQ0014309001
Noncompliance Summary
Description of Noncompliance: [NSDescription]
Excursion: Flow-Daily Avg., Date of Excursion: Month of Oct. 2022, Permit Parameter: MGD, Permit Value: 0.75 MGD, Actual Value: 0.88 MGD
Cause of Noncompliance: [NSCause]
Duration: Start Date and Time: 10/1/2022 12:00 AM End Date and Time: 10/31/2022 12:00 AM
Or Date Expected to be Corrected: [NSExpectedCorrected]
Potential Danger to Human Health and Safety or the Environment: No dangers identified at this time.
Actions Taken
Monitoring Data: Data should be attached or submitted to TCEQ when available.
Yes Field Measurements
No Laboratory Samples No Fish Kill If yes, estimated number killed: 0
Actions Taken to Mitigate Adverse Effects: .
Actions Taken to Correct the Problem and Prevent Recurrence: We are working with the District Engineer to increase the permitted capacity.
Verification Information
Information Reported By (Name/Title): <u>Jesse Black - Operations Manager</u>
Poto Borrostodo 2/20/2022
Signature.

Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

□: Unauthorized Discharge ⊠: Reportable Effluent Violation □: Other
General Information
Entity Name: Hays County Mud 4 Telephone No: 512-461-5007Telephone No: 512-461-5007
⊠: Permittee □: Subscriber
TCEQ Region: 11 County: Hays *Permit Number: WQ0014309001
Noncompliance Summary
Description of Noncompliance: [NSDescription]
Excursion: Flow-Daily Avg, Date of Excursion: Month of November 2022, Permit Parameter: MGD, Permit Value: 0.75 MGD, Actual Value: 0.82 MGD
Cause of Noncompliance: [NSCause]
Duration: Start Date and Time: 11/1/2022 12:00 AM End Date and Time: 11/30/2022 12:00 AM Or Date Expected to be Corrected: [NSExpectedCorrected] Potential Danger to Human Health and Safety or the Environment: No dangers identified at this time.
Actions Taken
Monitoring Data: Data should be attached or submitted to TCEQ when available.
Yes Field Measurements No Laboratory Samples No Fish Kill If yes, estimated number killed: 0
Actions Taken to Mitigate Adverse Effects: [ATMitigate]
Actions Taken to Correct the Problem and Prevent Recurrence: We are working with the District Engineer to increase the permitted capacity.
Verification Information
Information Reported By (Name/Title): <u>Jesse Black - Operations Manager</u>
Date Reported: 2/28/2023 Signature:
Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ. Compliance Monitoring Team (MC224). Enforcement Division

P.O. Box 13087, Austin, TX 78711-3087.

^{*} If the noncompliance is an unauthorized discharge from a wastewater collection system, use the permit number of the treatment plant to which the collection system is tied. If you are uncertain of this permit number, you may call the TCEQ Regional Office for assistance.

☐ Unauthori	zed Discharge	⊠ Reporta	able Effluent Violatio	on 🗆 Other	
General Inf	ormation				
Entity Name:	Hays County MUD	04 Tel	ephone No: (512) 2	201-3595	
⊠ Pei	rmittee 🗌 S	Subscriber			
TCEQ Region	: Region 11	Cou	unty: Hays	*Permit Number:	: WQ0014309001
Noncomplia	nce Summary				
Description o	f Noncompliance (i	include location	discharge route and		
Parameter	Туре	include location,	Date	estimated volume of unau	Popertod Value
TSS	Daily Max		9/22/2021	45	Reported Value 46
TSS	7 Day Avg.		k of 9/20/2021	30	46
E. Coli	Single Grab Max		9/22/2021	800	866
flow over into to Duration:	the contact basin.		tion of Noncompliance	causing the solids to bulk	to the surface and
	End Date and Time	e: ed to be Correc			
Potential Dan Actions Take		th and Safety	or the Environment:	: None anticipated at this	time.
Monitoring Da	ata: Data should be	e attached or s	submitted to TCEQ w	hen available.	
	☐ Yes 🗵 No F	Field Measuren	ments		
	🛛 Yes 🗌 No L	Laboratory Sar	mples s, estimated number	r killed:	
Actions Taker Electrician foun	to Mitigate Advers	se Effects:	s ordered and installed		
Contact basin v	to Correct the Provas pumped back into knock down the rema	the bar screen	to clear any solids acc	cumulated on the bottom	. Clarifier was
Verification 1	Information				
Information R	eported By (Name,	/Title):	Zachary Willeford, (Operations Manager	
			20		
Date Reported	i: 10/4/2021_	Signature:			_
<u>Note</u> : If this fo Region Office,	orm is being used for and the original to	or a 5-day wri	tten report, a copy o	of the form should be s am (MC224), Enforcen	ent to the TCEQ

P.O. Box 13087, Austin, TX 78711-3087.

Trate.	Quality Holicompliance No	circation	
☐: Unauthorized Discharge	oxtimes: Reportable Effluent Violation	\Box : Other	
General Information			
Entity Name: Hays County MUD 4 Substitute	Telephone No: 512-201-359	95	
2 c	DSC(IDE)		
TCEQ Region: 11 County: Hays	*Permit Number: WQ0014	309001	
Noncompliance Summary			
Description of Noncompliance: [NS	Description]		
Parameter Type	Date	Permitted Value	Reported Value
E. Coli Single Grab [NSDescription]	10/19/2021	800	2420
End Date and Time: Or Date Expected	to be Corrected: [NSExpectedCorrected Safety or the Environment: No	1	time.
Monitoring Data: Data should be a	ttached or submitted to TCEQ when	n available.	
No Field Measure Yes Laboratory Sa No Fish Kill If y e			
Actions Taken to Mitigate Adverse	Effects: We are currently investigating	g the issue.	
Actions Taken to Correct the Proble and retrain personnel on proper sample	em and Prevent Recurrence: As a pe collection.	recautionary measure	e, we will review
Verification Information			
Information Reported By (Name/T	itle): Zachary Willeford -Operation	ons manager	
	Je-		
Date Reported: <u>11/12/2021</u>	Signature:		
Note: If this form is being used for Region Office, and the original to:	a 5-day written report, a copy of the CCE, Compliance Monitoring Team	he form should be s (MC224), Enforcer	ent to the TCEQ nent Division,

P.O. Box 13087, Austin, TX 78711-3087.

^{*} If the noncompliance is an unauthorized discharge from a wastewater collection system, use the permit number of the treatment plant to which the collection system is tied. If you are uncertain of this permit number, you may call the TCEQ Regional Office for assistance.

□: Unauthori	zed Dis	charge	⊠: Re _l	portable Effluen	t Violation	□: Oth	er
General Info	rmatio	n					
Entity Name: Telephone No							
⊠: Per	rmittee	: □: St	ubscriber	r			
TCEQ Region:	11	County: Hay	s	*Permit Number	er: R14309-001		
Noncompliar	nce Sur	nmary					
Description of	f Nonco	ompliance: [NS	5Descripti	onl			
Parameter		Туре		Date	Permitted Val	ue I	Reported Value
E. Coli		Single Grab		12/07/2021	800	uc	
			7	1	1 000		1300
[NSDescription Cause of None over to the chlo	complia	ance: Drastic de	rop in tem	nperature caused	the solids to bulk in	the clarifie	r allowing them to flow
Duration:	Start [End Da	Date and Time ate and Time:	12/7/20:	021 12:00:00 AM 21 12:00:00 AM			
	Or D	ate Expected	to be Co	rrected: INSEx	(pectedCorrected)		
	ger to I				onment: None antic	cipated at th	nis time.
Actions Take	n						
Monitoring Da	ita: Da	ta should be a	attached	or submitted to	TCEQ when availa	able.	
	No	Field Measure					
		Laboratory S					
	No	Fish Kill If y	es, estin	nated number k	illed: [ATFishKill	Num]	
Actions Taken chlorine contact	to Miti t chamb	igate Adverse er to return an	Effects: y solids th	Washed down class at accumulated b	arifier of any floating back to the head of t	solids and he plant.	pumped down the
Actions Taken in the Clarifier.	to Cor	rect the Probl	em and I	Prevent Recurre	nce: Adjusted the I	RAS to lowe	er the number of solids
Verification I	Informa	ation	***************************************				
Information R	eporte	d By (Name/T	Γitle): <u>Z</u>	Zachary Willefor	d -Operations Ma	nager	
					0		
Date Reported	1/14	4/2022	Signatu	ire:			
Note: If this for Region Office, P.O. Box 1308	and th	e original to:	TCEO. Co	written report, ompliance Monit	a copy of the form oring Team (MC22	n should be 24), Enforc	e sent to the TCEQ cement Division,

	,		
☐: Unauthorized Discharge	⊠: Reportable Effluent Violation	\Box : Other	
General Information			
Entity Name: Hays County M Telephone No: 512-201-3595			
211 crimetee	Subscriber		
TCEQ Region: 11 County	y: Hays *Permit Number: WQ00143	309001	
Noncompliance Summary			
Noncompliance Summary			
Description of Noncomplian	ce: [NSDescription]		
Parameter Type	Date	Permitted Value	Reported Value
TSS Daily Avg.	Month of December	20	22.25
Potential Danger to Human Actions Taken	Health and Safety or the Environment: No	ne expected at this ti	me.
Monitoring Data: Data shou	ld be attached or submitted to TCEQ when	n available.	
Yes Labora	leasurements itory Samples Il If yes, estimated number killed:		
	iverse Effects: Wash down clarifier daily to k	rnock down solids	
	Problem and Prevent Recurrence: Adjust		the amount of
Verification Information			20
Information Reported By (N	ame/Title): Zachary Willeford -Operation	ons Manager	
	70		
Date Reported: 1/13/2022	Signature:		
Note: If this form is being us Region Office, and the origin P.O. Box 13087, Austin, TX 7	sed for a 5-day written report, a copy of the last to: TCEQ, Compliance Monitoring Team	ne form should be s (MC224), Enforcer	ent to the TCEQ nent Division,

^{*} If the noncompliance is an unauthorized discharge from a wastewater collection system, use the permit number of the treatment plant to which the collection system is tied. If you are uncertain of this permit number, you may call the TCEQ Regional Office for assistance.

	wate	er Quality Noncompli	ance Notification	
□: Unauthori	zed Discharge	⊠: Reportable Effluent	Violation □:	Other
General Info	rmation			
Entity Name:	Hays County MUD 4	Telephor	ne No: 512-201-3595	
⊠: Pe	rmittee :	Subscriber		
TCEQ Region:	11 County: Ha	ays *Permit	Number: WQ001430900	1
Noncomplia	nce Summary			
Description of	f Noncompliance:	NSDescription]		
Parameter	Туре	Date	Permitted Value	Reported Value
TSS	7 Day AVG	Week of 3/28/2022	2 30	446
TSS	Single Grab	3/29/2022	65	446
TSS	Daily Max	3/29/2022	45	446
BOD	Daily Max	3/29/2022	45	185
BOD	7 Day AVG	Week of 3/28/2022	2 30	185
BOD	Single Grab	3/29/2022	65	185
E-coli	Single Grab	3/29/2022	800	2420
organic loading Duration:	start Date and Time End Date and Time Or Date Expecte	ed to be Corrected: [NSEx	ompliance pectedCorrected]	
Potential Dan		th and Safety or the Enviro	nment: None anticipated	at this time.
ACTIONS TAKE				
Monitoring Da	ta: Data should be	attached or submitted to	TCEQ when available.	
	No Field Meason Yes Laboratory No Fish Kill In		lled:	

Actions Taken to Mitigate Adverse Effects: DO and chlorine feed were adjusted to help treat the increased flows, organic loading, and debris that were being received.

Actions Taken to Correct the Problem and Prevent Recurrence: Collection system is still in the process of being cleaned but once it is complete, we will return the plant back into normal operations.

Verification Information

Information Reported By (Name/Title): Zachary Willeford -Operations Manager

Date Reported: 4/7/2022 Signature:

Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

^{*} If the noncompliance is an unauthorized discharge from a wastewater collection system, use the permit number of the treatment plant to which the collection system is tied. If you are uncertain of this permit number, you may call the TCEQ Regional Office for assistance.

	water Q	dancy NonCompila	nce Notification	
□: Unauthorized Di	scharge	oxtimes : Reportable Effluent V	iolation \square : (Other
General Informati	on			
Entity Name: Hays Telephone No: 512-	201-3595			
□: Permitte	e □: Subs	scriber		
TCEQ Region: 11 Noncompliance Su	County: Hays	*Permit Number:	WQ0014309001	
Description of Name				
Parameter Parameter	Type	Date	Permitted Value	Donostad Value
TSS	7 Day Avg	Week of 4/2/22	30	Reported Value
TSS	Daily Max	4/5/22	45	49
Or Potential Danger to		be Corrected: [NSExpe	1	this time.
Actions Taken				
No	Field Measurem		EQ when available.	
No No	Laboratory Sam Fish Kill If yes	ples , estimated number kille	d:	
Actions Taken to Mit organic loading, and d	t igate Adverse Ef ebris that were bei	fects: DO and chlorine feeing received.	d were adjusted to help t	treat the increased flows,
Actions Taken to Cocleaned but once it is	rrect the Problem complete, we will re	and Prevent Recurrence eturn the plant back into no	e: Collection system is sormal operations.	till in the process of being
Verification Inform	ation			
Information Reporte	ed By (Name/Title	e): Zachary Willeford -	Operations Manager	_
		2		
Date Reported: _5/1	<u>18/2022</u> S i	ignature:		
Note: If this form is	heing used for a	5-day written report a	ony of the form of and	1 h

Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

^{*} If the noncompliance is an unauthorized discharge from a wastewater collection system, use the permit number of the treatment plant to which the collection system is tied. If you are uncertain of this permit number, you may call the TCEQ Regional Office for assistance.

□: Unauthorize	d Discharge	⊠: Rep	ortable Effluent	Violation	□: Other
General Inform	nation				
Entity Name: Hatelephone No: 2	281-840-9973	#4			
TCEQ Region: 11	County:	Hays	*Permit Number	: WQ0014309001	1
Noncompliance	Summary				
Description of N	oncompliance				
Parameter	Туре	Date	Permitted Value		
E.Coli	Single Grab	5/17/2022	800	value 2420	
Duration: St	et clarifier. The start Date and T and Date and Ting Date Expe	ime: See des ne: cted to be Co	ocated on this comscription above rrected: [NSExp	nmon line.	contact basins and the storage
	No Field Mea	surements ry Samples	or submitted to i		lable.
Actions Taken to	Mitigate Adve	rse Effects:	[ATMitigate]		
Actions Taken to from the center we and the storage ta	ell causing short	roblem and F circuiting. So	Prevent Recurrent liciting contractor	ice: Drained the o to clean the transf	clarifier to clean any rags or debris fer line between the contact basins
Verification Inf	ormation				
Information Rep	orted By (Nam	e/Title): <u>J</u>	eremy Weber -S	r. Operations Ma	anager
Date Reported:	6/14/2022	Signatu	re:		
Note: If this form	n is being used	for a 5-day	written report, a	copy of the form	m should be sent to the TCEO

Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.

□: Unauthorized Discharge	⊠: Reportable Effluent Violation □: Other
General Information	
Entity Name: Hays County MUD 4	Telephone No: 512-461-5007
⊠: Permittee □:	Subscriber
TCEQ Region: 11 County: Ha	*Permit Number: WQ0014309001
Noncompliance Summary	

Description of Noncompliance: See Below

Parameter	Туре	Date	Permitted Value	Reported Value
BOD	Single Grab	6/28/2022	65	73
BOD	Daily Max	6/28/2022	45	73
BOD	7 Day Average	Week of 6/27/2022	30	73
BOD	Daily Avg	Month of 6/2022	20	21.75
E. coli	Daily Max	6/28/2022	800	2420

Cause of Noncompliance: Blower failure morning of sampling caused a loss of mixing and dissolved oxygen in aeration basins

Duration:

Start Date and Time: 6/27/2022 5:00:00 AM **End Date and Time:** 6/30/2022 5:00:00 AM **Or Date Expected to be Corrected:** 6/30/2022

Potential Danger to Human Health and Safety or the Environment: None

Actions Taken

Monitoring Data: Data should be attached or submitted to TCEQ when available.

No Field Measurements
Yes Laboratory Samples

No Fish Kill If yes, estimated number killed:

Actions Taken to Mitigate Adverse Effects: Contact basin was pumped back into the bar screen to clear any solids accumulated on the bottom. Clarifier was hosed down to knock down the remainder of the solids

Actions Taken to Correct the Problem and Prevent Recurrence: Aeration blower was repaired same day and returned to normal operations.

Verification Information

Information Reported By (Name/Title): <u>Jesse Black - Operations Manager</u>


Date Reported: 7/7/2021 Signature:


Note: If this form is being used for a 5-day written report, a copy of the form should be sent to the TCEQ Region Office, and the original to: TCEQ, Compliance Monitoring Team (MC224), Enforcement Division, P.O. Box 13087, Austin, TX 78711-3087.


La martine.


Westwood


ATTACHMENT #19 – WIND ROSE
































Erwin Madrid

From: Jacob Valentien < Jacob. Valentien@westwoodps.com>

Sent: Tuesday, November 5, 2024 10:43 AM

To: Erwin Madrid

Cc: Nick Pena; Matthew Kutac

Subject: RE: Application for Permit No. WQ0014309001 - Notice of Deficiency Letter

Attachments: Permit Renewal Application - Worksheet 3.0 Page 1.pdf; Permit Renewal Application -

Updated Site Location Page.pdf; NORI -Spanish Version Complete.docx; Permit Renewal

Application Deficiency Notice Response 20241105.pdf

Erwin,

Please see attached for our response to the NOD letter sent on October 22, 2024.

If you have any additional questions or comments, please let us know and we can address/remedy promptly.

Thanks,

Jacob Valentien

Public Infrastructure Market Lead jacob.valentien@westwoodps.com

direct (512) 485-0831 main 512.485.0831 cell (713) 829-6003

Westwood

8701 N. Mopac Expy Suite 320 Austin, TX 78759

westwoodps.com (888) 937-5150

From: Erwin Madrid < Erwin. Madrid@tceq.texas.gov>

Sent: Tuesday, October 22, 2024 5:20 PM

To: Jacob Valentien < Jacob. Valentien@westwoodps.com>

Cc: Matthew Kutac <mkutac@mbkfirm.com>; Erwin Madrid <Erwin.Madrid@tceq.texas.gov>

Subject: Application for Permit No. WQ0014309001 - Notice of Deficiency Letter

Importance: High

CAUTION: External Sender. Please do not click on links or open attachments from senders you do not trust.

Dear applicant,

The attached Notice of Deficiency letter sent on **October 22, 2024**, requests additional information needed to declare the application administratively complete. Please send the complete response to my attention by **November 5, 2024**.

Regards,

Erwin Madrid
Team Lead
ARP Team | Water Quality Division
512-239-2191
Texas Commission on Environmental Quality



Please consider whether it is necessary to print this e-mail.

November 5, 2024 Project No.: R0052766.00

Texas Commission on Environmental Quality Water Quality Division

Erwin Madrid Building F, Room 2101 12100 Park 35 Circle Austin, Texas 78753

Texas Commission on Environmental Quality Water Quality Division

Erwin Madrid PO Box 13087 Austin, Texas 78711-3087

Re: TCEQ PERMIT RENEWAL APPLICATION DEFICIENCY RESPONSE

TCEQ Permit Number WQ0014309001 Westwood Job Number: 0052766.00 – ID 08

Dear Erwin Madrid,

This document will serve as our response to the items that you brought to our attention when checking for the completeness of our Permit Renewal Application. All comments are addressed and the updated pages from the document are attached below.

If you have questions concerning this response please contact me at (512) 485-0831.

Sincerely,

Jacob W. Valentien, P.E. District Engineer

CC: Matt Kutac – Law Office of Matthew B. Kutac

Response to Comment 1:

Comment from Reviewer: Section III, question 25, on page 2 of the TCEQ Core Data Form: Our requirements for describing the facility location in the permit have changed. The description must include the distance in feet or miles from a major road intersection. Please provide a revised facility location description that uses the road intersections.

Response from Westwood: The updated facility description is as follows: "Approximately 608 feet north and 2950 feet west of the intersection of US 290 and Nutty Brown Road." This intersection is closer to the wastewater treatment plant so should be easier to locate. We've attached a pdf of the specific page where this information is located and has been updated.

Response to Comment 2:

Comment from Reviewer: Worksheet 3.0 of the Technical Report: The current permit authorizes the disposal of 150,000 MGD via subsurface area drip dispersal on 34.44 acres of land. The information supplied on the Worksheet 3.0 indicates that the disposal area is 27.2 acres and 119,566 MGD. Please confirm if you are requesting to reduce the acres for disposal and a reduction in permitted average daily flow.

Response from Westwood: We are **not** requesting a reduction in disposal acres or permitted average daily flow. The facility currently operates in the interim II phase of 100,000 gpd. The facility currently has 100,000 gpd of drip field disposal area constructed. The District will construct additional drip field disposal areas to expand the facility to the ultimate phase of 150,000 gpd over time. The worksheet has been revised to reflect the phases of the permit.

The District is currently working on evaluating additional areas for drip field disposal area expansion and will ultimately file a major permit amendment with the TCEQ to revise the disposal areas of the permit and additional interim phases to ultimately reach the 150,000 gpd limit of the current permit.

Response to Comment 3:

Comment from Reviewer: The following is a portion of the NORI which contains information relevant to your application. Please read it carefully and indicate if it contains any errors or omissions. The complete notice will be sent to you once the application is declared administratively complete.

Response from Westwood: All information presented is accurate and complete including the revision to the wastewater treatment plant location description per comment 1.

Response to Comment 4:

Comment from Reviewer: The application indicates that public notices in Spanish are required. After confirming the portion of the NORI above does not contain any errors or omissions, please use the attached template to translate the NORI into Spanish. Only the first and last paragraphs are unique to this application and require translation. Please provide the translated Spanish NORI in a Microsoft Word document.

Response from Westwood: The NORI has been translated and the Spanish NORI is attached.

23. Street Address of the Regulated								
Entity: (No PO Boxes)							T	
	City		State		ZIP		ZIP + 4	
24. County		TC . C.			1 25 22	. ,		
25. Description to	Approx		t Address is proving feet north and 29				IS 200 and	Nutty Brown
Physical Location:	Road	Allitately 000	ieet north and 29	JU IEEL W	est of the lift	lersection of C	3 290 and	Nully Diowii
26. Nearest City						State	Ne	arest ZIP Code
Dripping Springs						ГХ	78	737
Latitude/Longitude a Physical Address ma								
27. Latitude (N) In De	cimal:	30.2102		28.	Longitude (W) In Decima	l: 97.982	
Degrees 30	Minute		Seconds	Deg	grees	Minutes	:0	Seconds 58.26
29. Primary SIC Code		12 30. Secondar	36.87	31 Prir	97 nary NAICS		58 econdary 1	NAICS Code
(4 digits)		(4 digits)	., Die coue	(5 or 6 o			6 digits)	THE COUC
4952					22132			
33. What is the Prima	ry Bus	iness of this	entity? (Do not i	repeat the	SIC or NAICS	description.)		
			000	14 D	00000	ita 000		
34. Mailing	3321 Bee Caves, Suite 203							
Address:								
	City	y Austir	State	TX	ZIP	78746	ZIP + 4	
35. E-Mail Address:				MKuta	ac@mbkfir	m.com		
36. Telephone Numb	er		37. Extension	or Code	38. Fa	ax Number (if	applicable)	
(512) 615- 0503					()	-		
9. TCEQ Programs and pdates submitted on this	l ID Nu form. Se	ımbers Check ee the Core Da	t all Programs and water tall Programs and water to the tall and tall	rite in the for additi	permits/regis onal guidance	tration numbers	that will be	affected by the
☐ Dam Safety		Districts	☐ Edwards Aquif	er	☐ Emission	ns Inventory Air	☐ Indust Waste	rial Hazardous
	-	New Source	Посст					
☐ Municipal Solid Waste		view Air	OSSF		☐ Petroleu	m Storage Tank	☐ PWS	
Sludge		Storm Water	☐ Title V Air		Tires		☐ Used (Dil
☐ Voluntary Cleanup	IXI	Wastewater	☐ Wastewater Ag	riculture	☐ Water Ri	ghts	☐ Other:	
<u> </u>		Q0014309001		,		<i></i>		
SECTION IV: P			ormation		1		1	
	-		<u>Jimation</u>	41 75	Sonio	r Project M	nagar	
40. Name: Jacob V 42. Telephone Numbe		•	44. Fax Number	41. Tit	Mail Addres	r Project Ma	anayer	
(512) 485-0831	1 43.	·				n@westwoo	dns com	
			() -	Jacoi	o.vaieriliei	IW WESLWOO	ap3.00111	
SECTION V: A				1		1 1 .1 . 2		1
By my signature below nat I have signature author								

that I have signature authority to submit uns round updates to the ID numbers identified in field 39.

Company:	Hays County MUD No. 4 Job Title: District			t Engineer		
Name (In Print):	Jacob Valentien, PE			Phone:	(512) 485-0831	
Signature:	Cases Valentin			Date:	08/28/2024	

TCEQ-10400 (11/22) Page 2 of 2

DOMESTIC WASTEWATER PERMIT APPLICATION WORKSHEET 3.0: LAND DISPOSAL OF EFFLUENT

The following is required for renewal, new, and amendment permit applications.

Section 1. Type of Disposal System (Instructions Page 68)

□ Surface application
 □ Irrigation
 □ Drip irrigation system
 □ Evaporation
 □ Evapotranspiration beds
 □ Other (describe in detail): Click to enter text.

NOTE: All applicants without authorization or proposing new/amended subsurface disposal MUST complete and submit Worksheet 7.0.

For existing authorizations, provide Registration Number: 103897567

Section 2. Land Application Site(s) (Instructions Page 68)

In table 3.0(1), provide the requested information for the land application sites. Include the agricultural or cover crop type (wheat, cotton, alfalfa, bermuda grass, native grasses, etc.), land use (golf course, hayland, pastureland, park, row crop, etc.), irrigation area, amount of effluent applied, and whether or not the public has access to the area. Specify the amount of land area and the amount of effluent that will be allotted to each agricultural or cover crop, if more than one crop will be used.

Table 3.0(1) - Land Application Site Crops

Identify the method of land disposal:

Crop Type & Land Use	Irrigation Area (acres)	Effluent Application (GPD)	Public Access? Y/N
Phase 1 - Bermuda and Rye Grass	17.22	75,000	Υ
Interim II - Bermuda and Rye Grass	5.74	25,000	Υ
Final - Bermuda and Rye Grass	11.48	50,000	Υ

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE RECIBO DE LA SOLICITUD E INTENCION DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA

PERMISO PROPUESTO NO. WQoo14309001

SOLICITUD. Hays County Municipal Utility District No. 4, 3321 Bee Caves Road, Suite 203, Austin, Texas 78746 ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para el propuesto Permiso No.WQ0014309001 de disposición de aguas residuales] para autorizar la disposición de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 150,000 galones por día por medio de irrigación por goteo de dispersión en área subsuperficial de 34.44 acres de tierra. La planta de tratamiento de aguas domésticos residuales y el área de disposición están ubicados en aproximadamente 608 pies al norte y 2950 pies al oeste de la intersección de la US 290 y Nutty Brown Road en el Condado de Hays, Texas. La TCEQ recibió esta solicitud el día agosto 29, 2024. La solicitud para el permiso está disponible para leer y copiar en Dripping Springs City Hall, 511 Mercer Street, Dripping Springs, en Hays County, Texas. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tlap-applications. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-97.98279,30.210416&level=18

AVISO ADICIONAL. El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. El aviso de la solicitud y la decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud. El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el

Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO

CONTENCIOSO. Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de

derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado especifico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

CONTACTOS E INFORMACIÓN DE LA TCEQ. Todos los comentarios escritos del público y los para pedidos una reunión deben ser presentados a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 o por el internet at www.tceq.texas.gov/about/comments.html. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Si necesita más información en Español sobre esta solicitud para un permiso o el proceso del permiso, por favor llame a El Programa de Educación Pública de la TCEQ, sin cobro, al 1-800-687-4040. La información general sobre la TCEQ puede ser encontrada en nuestro sitio de la red: www.tceq.texas.gov.

También se puede obtener información adicional del Hays County Municipal Utility District No. 4 a la dirección indicada arriba o llamando a Westwood Professional Services al (512) 485-0831.

n 1 1	Fm	17
Fecha de emisión	ΓDate notice issued	/ /

ATTACHMENT #21 – Groundwater Quality Technical Report

Groundwater Quality Technical Report

In accordance with 30 TAC § 309.20(a)(4)(A and B) this report provides an assessment of the impact of the wastewater disposal operation on the uses of local groundwater resources.

The MUD's disposal areas are above the Trinity Aquifer and within the contributing zone of the Edwards Aquifer. The depth of groundwater in the area varies between around 80-800 feet from the ground surface. Groundwater use in the surrounding area is majority domestic, with some public supply and irrigation usage as well.

There are 9 active wells or sources of water within a 0.5 mile radius of the HCMUD No. 4 permitted wastewater disposal areas. These have been identified and have depths varying between 450 to 850 feet below ground surface. Based on well reports, the wells were completed in the Trinity Aquifer. Attachment 20 can give further detail on these wells. The appropriate buffer distances have and will be maintained. There are no proposed monitor wells around the site.

The site contains two storm water retention ponds that divert excess stormwater drainage away from the MUD's disposal areas.


The MUD's subsurface drip field does not exceed the disposal rate of 0.1 gal/sq. ft./day per 30 TAC § 309.20(a)(4)(B). The application rate per the permit ensures that potential contaminants do not migrate below the rooting zone. The MUD's disposal areas are at least 1,500 feet from any part of the nearest body of water, the Colorado River.

The MUD stores treated effluent in a welded steel tank being used instead of wastewater ponds protects the area from any potential seepage.

The MUD's disposal facilities are protective of local groundwater by being more than half a mile from any ground water or surface water source, by diverting stormwater drainage away from the disposal areas, maintaining a maximum disposal rate of 0.1 gal/sq. ft./day that limits the amount of effluent disposed within the area each day, and storing the treated effluent in a welded steel tank.

Due to the measures noted above, the depth of the subsurface drip field, and the location of the disposal areas that are in accordance with the Texas Commission on Environmental Quality's minimum standards it is unlikely to present a concern for ground water.

ATTACHMENT #20 – Well and Map Information



Owner: Rick Nelson Owner Well #: No Data

Address: 15 Long Creek Rd Grid #: 58-49-1

Austin, TX 78737

Well Location: 15 Long Creek Rd

Austin, TX 78737 Longitude: 097° 59' 00" W

Well County: Hays Elevation: 1085 ft. above sea level

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 6/9/2022 Drilling End Date: 6/9/2022

Borehole:

Diameter (in.)
Top Depth (ft.)
Bottom Depth (ft.)

0
100

6.125 100 850

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

Cement 12 Bags/Sacks

Seal Method: **Pressure** Distance to Property Line (ft.): **50**

Sealed By: **Driller**Distance to Septic Field or other

concentrated contamination (ft.): 100

Distance to Septic Tank (ft.): 50

Method of Verification: Owner

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: No Data

Packers: Burlap at 100 ft.

Burlap/Plastic at 120 ft. Burlap/Plastic at 300 ft. Burlap/Plastic at 500 ft. Burlap/Plastic at 600 ft. Burlap/Plastic at 740 ft.

Type of Pump: Submersible

Well Tests: Jetted Yield: 30 GPM

Water Quality:

Strata Depth (ft.)	Water Type
740 - 840	Lower Trinity

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Centex Pump & Supply, Inc.

2520 Hwy. 290 West

Dripping Springs, TX 78620

Driller Name: Martin Lingle License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	1	Rock
1	14	Caliche
14	16	Blue
16	25	Gray
25	330	Gray & Tan
330	580	Tan
580	630	Gray w/ Clay
630	690	Gray & Tan
690	770	Red Brown & Tan
770	840	Conglomerate
840	850	Gray w/ Clay

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
4.5	Blank	New Plastic (PVC)	SDR17	2	740
4.5	Perforated or Slotted	New Plastic (PVC)	SDR17	740	840
4.5	Blank	New Plastic (PVC)	SDR17	840	850

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Owner: Rachel & Peter Linden Owner Well #: No Data

Address: 6 Long Creek Road Grid #: 58-49-1

Austin, TX 78737

Well Location: 6 Long Creek Road

Austin, TX 78737 Longitude: 097° 59' 05.39" W

Well County: Hays Elevation: No Data

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 11/17/2023 Drilling End Date: 11/17/2023

 Diameter (in.)
 Top Depth (ft.)
 Bottom Depth (ft.)

 Borehole:
 8.75
 0
 100

 6.25
 100
 910

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

100

10 cement, 4 Benseal Bags/Sacks

Seal Method: **Pressure Tremie** Distance to Property Line (ft.): **30**

Sealed By: **Driller** Distance to Septic Field or other

concentrated contamination (ft.): +100

Distance to Septic Tank (ft.): +100

Method of Verification: Owner

30° 12' 56.77" N

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 558 ft. below land surface on 2023-11-17 Measurement Method: Sonic/Radar

Packers: **Burlap & PVC 750', 730'**

Burlap & Rubber 100'

Type of Pump: Submersible

Well Tests: Estimated Yield: 15-20 GPM

Water Quality: Strata Depth (ft.) Water Type

Water Quality: 558 - 910 Hosston Trinity

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Associated Drilling Inc

PO BOX 673

Dripping Springs, TX 78620

Driller Name: James Benoit License Number: 4064

Comments: Drilled for Wiley Water Well Service. Hays Trinity Groundwater District Permit

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.) Bottom (ft.) Description 0 3 topsoil 3 10 tan clay & lime 10 435 blue lime 435 505 tan limestone 505 555 gray limestone 605 555 gray lime & shale 605 710 gray white limestone 710 740 red clay 740 790 red sandstone 790 850 tan white limestone 850 890 multi color limestone 890 910 yellow limestone & clay

Dla (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
4.5	Blank	New Plastic (PVC)	SDR17	-3	830
4.5	Screen	New Plastic (PVC)	SDR17 0.020	830	890
4.5	Blank	New Plastic (PVC)	SDR17	890	910

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Owner: HAYDEN NOBLE Owner Well #: No Data

Address: 26 TALL OAK TRAIL Grid #: 58-49-1

AUSTIN, TX 78737

Well Location: 26 TALL OAKS TRAIL

AUSTIN, TX 78737

Latitude: 30° 13' 07.2" N

Longitude: 097° 59' 25.26" W

Well County: Hays Elevation: No Data

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 12/13/2016 Drilling End Date: 12/13/2016

Borehole:

Diameter (in.)

Top Depth (ft.)

Bottom Depth (ft.)

100

6.125 100 850

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

Cement 14 Bags/Sacks

100
100
Bentonite 2 Bags/Sacks

Seal Method: **Slurry** Distance to Property Line (ft.): **53**

Sealed By: **Driller**Distance to Septic Field or other

concentrated contamination (ft.): 200+

Distance to Septic Tank (ft.): 250+

Method of Verification: TAPE MEASURE

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 500 ft. below land surface on 2016-12-13 Measurement Method: Electric Line

Packers: Burlap at 100 ft.

BURLAP & PVC at 640 ft. BURLAP & PVC at 660 ft. BURLAP & PVC at 680 ft. BURLAP & PVC at 700 ft.

Type of Pump: Submersible Pump Depth (ft.): 760

Well Tests: Jetted Yield: 40 GPM

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which

contained injurious constituents?: No

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Centex Pump & Supply, Inc.

2520 Hwy. 290 West

Dripping Springs, TX 78620

Driller Name: MARTIN DALE LINGLE, JR. License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	1	TOP SOIL
1	10	CALICHE
10	225	GRAY LIMESTONE
225	230	GRAY LIMESTONE
230	350	GRAY & TAN LIMESTONE
350	355	GRAY LIMESTONE & GRAY CLAY
360	430	TAN & GRAY LIMESTONE
430	590	TAN LIMESTONE
590	635	GRAY/TAN W/BROWN LIMESTONE
635	680	HAMMETT CLAY
680	695	HAMMETT CLAY W/RED CLAY
695	755	GRAY/TAN LIMESTONE
755	850	SAND

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
5	Blank	New Plastic (PVC)	SDR17	3	750
5	Perforated or Slotted		SDR17 SLOT	750	850

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.



Owner: Treaty Oak Homes:Greg Hammond Owner Well #:

Address: 5701 W. Slaughter Ln A-130-362 Grid #: 58-49-1

Austin, TX 78749

Well Location: 3 Long Creek Rd

Austin, TX 78737

Latitude: 30° 13' 04" N

#1

Longitude: 097° 59' 03" W

Well County: Hays Elevation: 1064 ft. above sea level

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 7/31/2015 Drilling End Date: 8/12/2015

Diameter (in.) Top Depth (ft.) Bottom Depth (ft.)

Borehole: 7.875 0 880

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

12 Cement

50

60

4 Bentonite

Seal Method: **Pos. Displacement** Distance to Property Line (ft.): **51**

Sealed By: **Driller**Distance to Septic Field or other concentrated contamination (ft.): **N/A**

Distance to Septic Tank (ft.): No Data

Method of Verification: Measured

Surface Completion: Surface Sleeve Installed

Water Level: 475 ft. below land surface on 2015-08-03 Measurement Method: Unknown

Packers: Shale Packer 60

6Mil Poly 63
Shale Packer 70
6Mil Poly 73
6Mil Poly 300
6Mil Poly 500
Shale Packer 605
6Mil Poly 610
Shale Packer 615

6Mil Poly 618

Type of Pump: Submersible Pump Depth (ft.): 700

Well Tests: Jetted Yield: 30 GPM

Water Quality: Strata Depth (ft.) Water Type

660/880 Good TDS 700

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Whisenant & Lyle Water Services

PO Box 525

Dripping Springs, TX 78620

Driller Name: Martin Lingle License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

From (ft) To (ft) Description					
0 to 1 Topsoil					
1-5 Brown clay limestone					
5-85 Gray limestone					
85-130 Tan limestone					
130-185 Light gray limestone					
185-310 Gray tan limestone					
310-400 Tan limestone					
400-425 Gray limestone					
425-440 Gray limestone shale					
440-490 Tan limestone					
490-560 Gray tan limestone					
560-590 Gray clay					
590-630 Brown limestone					
630-640 Brown tan limestone					

Dia. (in.)	New/Used	Туре	Setting From/To (ft.)		
4.5 Nev	v PVC-SDI	R 17IB	+2/780		
4.5 New PVC-17 Slotted 780/860 .032					
Open F	lole 860/88	30			

640-680 Red brown sandstone
680-720 Red sandstone
720-740 Conglomerate
740-760 Red brown sandstone
760-875 Conglomerate
875-880 Black Rock
Water bearing 660-880

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Owner: KEVIN BADEEN (AART'S JOB) Owner Well #: No Data

Address: 5 LONG CREEK RD. Grid #: 58-49-1

AUSTIN, TX 78737

Well Location: 5 LONG CREEK RD.

Latitude: 30° 13' 03.12" N

AUSTIN, TX 78737 Longitude: 097° 59' 00.6" W

Well County: Hays Elevation: No Data

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 1/27/2021 Drilling End Date: 1/27/2021

Borehole:

Diameter (in.)
Top Depth (ft.)
Bottom Depth (ft.)

0
100

6.125 100 850

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

PORTLAND CEMENT 14 Bags/Sacks

Seal Method: **Pressure** Distance to Property Line (ft.): **100+**

Sealed By: **Driller** Distance to Septic Field or other

concentrated contamination (ft.): 100+

Distance to Septic Tank (ft.): 75+

Method of Verification: **OWNER**

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 514 ft. below land surface on 2021-01-27 Measurement Method: Electric Line

Packers: Burlap at 100 ft.

BURLAP & PLASTIC at 120 ft. BURLAP & PLASTIC at 500 ft. BURLAP & PLASTIC at 600 ft. BURLAP & PLASTIC at 730 ft. BURLAP & PLASTIC at 750 ft.

Type of Pump: Submersible

Well Tests: Jetted Yield: 40 GPM

Water Quality:

750 - 850	LOWER TRINITY
Strata Depth (ft.)	Water Type

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Centex Pump & Supply, Inc.

2520 Hwy. 290 West

Dripping Springs, TX 78620

Driller Name: MARTIN DALE LINGLE License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description		
0	2	ROCK		
2	15	CALICHE		
15	17	BLUE LIMESTONE		
17	23	BROWN LIMESTONE		
23	48	GRAY LIMESTONE		
48	51	BROWN LIMESTONE		
51	370	GRAY LIMESTONE		
370	400	TAN LIMESTONE		
400	430	GRAY LIMESTONE		
430	570	TAN/BROWN LIMESTONE		
570	590	GRAY LIMESTONE		
590	630	GRAY CLAY		
630	650	GRAY/TAN LIMESTONE		
650	670	GRAY/TAN LIMESTONE		
670	690	RED SANDSTONE SAND		
690	710	RED SANDSTONE SAND		
710	730	RED SANDSTONE SAND		
730	750	BROWN SANDSTONE SAND		

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
4.5	Blank	New Plastic (PVC)	SDR17	2	750
4.5	Perforated or Slotted	New Plastic (PVC)	SDR17	750	850

750	770	BROWN/RED LIMESTONE W/GRAVEL
770	790	BROWN/RED SAND
790	810	CONGLOMERATE
810	830	CONGLOMERATE
830	850	RED SANDSTONE W/CLAY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.



Owner: GASTON BROYLES Owner Well #: No Data

Address: 11800 OAK BRANCH DRIVE Grid #: 58-49-1

AUSTIN, TX 78737

Well Location: 11800 OAK BRANCH DRIVE

AUSTIN, TX 78737

Latitude:

30° 13' 13.08" N

Longitude: 097° 58' 49.92" W

Well County: Travis Elevation: No Data

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 8/19/2015 Drilling End Date: 8/19/2015

Borehole:

Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
9	0	100
6.5	100	830

Drilling Method: Air Rotary

Borehole Completion: CASED

Annular Seal Data:

Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
0	100	Cement 16 Bags/Sacks
0	100	Bentonite 4 Bags/Sacks
580	600	Cement 3 Bags/Sacks

Seal Method: **Tremie** Distance to Property Line (ft.): **55+**

Sealed By: **Driller** Distance to Septic Field or other

concentrated contamination (ft.): 100+

Distance to Septic Tank (ft.): 100+

Method of Verification: OWNER

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 531 ft. below land surface on 2015-08-20 Measurement Method: JETTED

Packers: BURLAP & PVC at 100 ft.

BURLAP & PVC at 600 ft. BURLAP & PVC at 620 ft. BURLAP & PVC at 640 ft. BURLAP & PVC at 660 ft. BURLAP & PVC at 680 ft. BURLAP & PVC at 700 ft. Type of Pump: Submersible Pump Depth (ft.): 740

Well Tests: No Test Data Specified

Water Type
Water Quality: 80 - 830 TRINITY

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: **CENTEX PUMP & SUPPLY, INC.**

2520 HWY. 290 WEST

DRIPPING SPRINGS, TX 78620

Driller Name: AARON GLASS License Number: 4227

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	1	TOP SOIL
1	20	CALICHE
20	25	BLUE/GRAY LIMESTONE
25	160	GRAY LIMESTONE
160	320	GRAY/TAN LIMESTONE
320	390	TAN/GRAY LIMESTONE W/CLAY STRIPS
390	470	TAN LIMESTONE
470	570	TAN W/GRAY LIMESTONE
570	605	BROWN LIMESTONE
605	670	GRAY LIMESTONE W/HAMMETT CLAY
670	710	GRAY/TAN LIMESTONE

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
5	Blank	New Plastic (PVC)	120	3	830
5	Perforated or Slotted	New Plastic (PVC)	120 0.032	720	820

710	820	RED/TAN SANDSTONE
820	830	RED/BLUE CLAY STRIPS

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.



Owner: Robert Hardy Owner Well #: No Data

Address: 11408 Southwest Oaks Grid #: 58-49-1

Austin, TX 78737

Well Location: 11408 Southwest Oaks

Latitude: 30° 13' 10" N

Austin, TX 78737 Longitude: 097° 58' 29" W

Well County: Travis Elevation: No Data

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 4/8/2015 Drilling End Date: 4/8/2015

 Diameter (in.)
 Top Depth (ft.)
 Bottom Depth (ft.)

 Borehole:
 9
 0
 50

 6.25
 50
 890

Drilling Method: Air Rotary

Borehole Completion: cased; Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

7cmt 2gel

Seal Method: hand poured Distance to Property Line (ft.): >60

Sealed By: **ADC**Distance to Septic Field or other concentrated contamination (ft.): **n/a**

concentrated contamination (it.): II/a

Distance to Septic Tank (ft.): No Data

Method of Verification: well drilled first

Surface Completion: Surface Sleeve Installed

Water Level: 513 ft. below land surface on 2015-04-08 Measurement Method: Unknown

Packers: burlap,plastic,rubber @ 730,725,630,50

Type of Pump: No Data

Well Tests: Jetted Yield: 20-25 GPM

Water Type
Water Quality: 513-890 Trinity Hoston

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Associated Drilling Inc.

PO Box 673

Dripping Springs, TX 78620

Driller Name: James Benoit License Number: 4064

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	15	white chalk
15	515	gray lime
515	560	tan white limestone
560	640	gray white limestone
640	670	gray shale
670	715	tan white limestone
715	750	red sandstone
750	760	red white sandstone (h2o)
760	860	red sandstone
860	880	multi-colored limestones (h2o)
880	890	yellow limestone

Dia. (in.)	New/Used	Type	Setting From/To (ft.)
5 od ne	w sdr17 p	vc -3 to	o 790
5 od new sdr17 pvc (.032) screen 790 to 870			
5 od new sdr17 pvc 870 to 890			

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Owner: Adan & Misty Arredondo Owner Well #: No Data

Address: 11120 Shady Hollow Dr. Grid #: 58-49-1

Austin, TX 78748

Well Location: 11201 Southwest Oaks

Austin, TX 78737

Latitude: 30° 12' 59" N

Longitude: 097° 58' 17" W

Well County: Travis Elevation: 1138 ft. above sea level

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 10/22/2021 Drilling End Date: 10/22/2021

6.125

Borehole:

Diameter (in.)
Top Depth (ft.)
Bottom Depth (ft.)

0 100

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data:

Top Depth (ft.)

Bottom Depth (ft.)

Description (number of sacks & material)

Portland 12 Bags/Sacks

100

Seal Method: **Pressure** Distance to Property Line (ft.): **50**

Sealed By: **Driller**Distance to Septic Field or other

concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): N/A

Method of Verification: Well drilled first

890

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 567.8 ft. below land surface, and 50 GPM Measurement Method: Electric Line

artesian flow on 2021-11-05

Packers: Burlap at 100 ft.

Burlap/Plastic at 120 ft. Burlap/Plastic at 300 ft. Burlap/Plastic at 600 ft. Burlap/Plastic at 750 ft. Burlap/Plastic at 790 ft.

Type of Pump: Submersible Pump Depth (ft.): 740

Well Tests: Jetted Yield: 50 GPM

Water Quality: Strata Depth (ft.) Water Type

Value Trinity

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Centex Pump & Supply, Inc.

2520 Hwy. 290 West

Dripping Springs, TX 78620

Driller Name: Martin Lingle License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	15	Caliche
15	16	Blue
16	95	Gray
95	405	Gray Tan
405	650	Tan
650	710	Gray w/ Clay
710	730	Gray
730	750	Brown Tan
750	770	Red Brown Gray
770	790	Brown Sand
790	810	Gray Tan Brown Red
810	830	Gray Tan Brown Red
830	850	Brown Sand Stone
850	870	Red Brown
870	890	Red w/ Clay

Casing: BLANK PIPE & WELL SCREEN DATA

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
4.5	Blank	New Plastic (PVC)	SDR17	2	790
4.5	Perforated or Slotted	New Plastic (PVC)	SDR17	790	890

Page 2 of 3

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Owner: Shawn Oatis Owner Well #: No Data

Address: 8 Long Creek Rd. Grid #: 58-49-4

Austin, TX 78737

Well Location: 8 Long Creek Rd.

Austin, TX 78737

Latitude: 30° 12' 00.94" N

Longitude: 097° 59' 00.09" W

Well County: Hays Elevation: 1036 ft. above sea level

Type of Work: New Well Proposed Use: Domestic

Drilling Start Date: 12/29/2021 Drilling End Date: 12/29/2021

 Diameter (in.)
 Top Depth (ft.)
 Bottom Depth (ft.)

 Borehole:
 9
 0
 100

 6.125
 100
 850

Drilling Method: Air Rotary

Borehole Completion: Straight Wall

Annular Seal Data: No Data

Seal Method: **Pressure** Distance to Property Line (ft.): **10**

Sealed By: **Driller** Distance to Septic Field or other

concentrated contamination (ft.): N/A

Distance to Septic Tank (ft.): N/A

Method of Verification: Well drilled 1st

Surface Completion: Surface Sleeve Installed Surface Completion by Driller

Water Level: 489.6 ft. below land surface, and 30 GPM Measurement Method: Electric Line

artesian flow on 2021-12-29

Packers: Burlap at 100 ft.

Burlap/Plastic at 120 ft. Burlap/Plastic at 300 ft. Burlap/Plastic at 500 ft. Burlap/Plastic at 700 ft. Burlap/Plastic at 750 ft.

Type of Pump: Submersible Pump Depth (ft.): 720

Well Tests: Jetted Yield: 25 GPM

Water Quality:

Strata Depth (ft.)	Water Type
750 - 850	Lower Trinity

Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which

contained injurious constituents?: No

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the

driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in

the report(s) being returned for completion and resubmittal.

Company Information: Centex Pump & Supply, Inc.

2520 Hwy. 290 West

Dripping Springs, TX 78620

Driller Name: Martin Lingle License Number: 54813

Comments: No Data

Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL

Top (ft.)	Bottom (ft.)	Description
0	2	Top Soil
2	16	Caliche
16	48	Gray
48	52	Brown
52	370	Gray Tan
370	430	Gray
430	550	Tan Gray
550	580	Gray Clay
580	615	Gray Brown
615	690	Red Sandstone
690	700	Gray Tan
700	745	Red Sandstone
745	847	Multi - Colored
847	850	Black Rock

DIa (in.)	Туре	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
4.5	Blank	New Plastic (PVC)	SDR17	2	750
4.5	Perforated or Slotted	New Plastic (PVC)	SDR17	750	850

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

November 13, 2024 Project No.: R0052766.00

Texas Commission on Environmental Quality

Andrew Gorton, P.G.

Water Quality Division

Applications Review and Processing Team (MC150)

P.O. Box 13087

Austin, Texas 78711-3087

Texas Commission on Environmental Quality

Alan Barraza
Water Quality Division
Applications Review and Processing Team (MC150)
P.O. Box 13087
Austin, Texas 78711-3087

Re: TCEQ PERMIT RENEWAL APPLICATION NOD Response Letter

TCEQ Permit Number WQ0014309001 Westwood Job Number: 0052766.00 – ID 08

Dear Andrew Gorton, P.G. and Alan Barraza,

This document will serve as our response to the items that you brought to our attention when checking for the preliminary technical completeness review of our Permit Renewal Application. All comments are addressed and the updated pages from the document are attached below.

If you have questions concerning this response please contact me at (512) 485-0831.

Sincerely,

Jacob Valentien, P.E.

aus Talentin

Andrew Gorton, P.G. & Alan Barraza Permit No. WQ0014309001 November 13, 2024 Page 2

NOD COMMENT RESPONSE LETTER

Response to Geology/Ground Water Item Comment No. 1:

Comment from Reviewer: Domestic Worksheet Section 3. Storage and Evaporation Lagoons/Ponds – Please note that a subsurface area drip dispersal system (SADDS) is required to have three days of storage, not two.

Response from Westwood: The worksheet has been revised to address this comment. The worksheet was also revised to address previously received administrative completeness comments. The current quantity of storage provides more than 3 days of storage for the current phase of the permit which is at 100,000 gpd. The District is evaluating expanding their storage capacity and including that with future expansion plans at that time, when necessary.

Response to Geology/Ground Water Item Comment No. 2:

Comment from Reviewer: Domestic Worksheet Section 6. Well and Map Information – This reviewer identified approximately 60 water wells 10 within <u>one mile</u> of the disposal sites. Please confirm (or deny) this. If confirmed, please include these wells on the USGS topographic map or well map.

Response from Westwood: All water wells located within the <u>one mile</u> radius of the MUD's disposal sites have been indicated on the map, see revised Attachment 20.

Response to Geology/Ground Water Item Comment No. 3:

Comment from Reviewer: This reviewer identified 19 water wells that were installed after the current permit was issued in December 2014. These wells include:

394577	404319
407580	442967
536743	536763
548438	556724
567555	572798
583434	588849
595039	612782
644817	648124
655481	655862
668213	

Please show these wells on the USGS topographic map or well map. Complete Table 3.0(3) and provide the well logs for these each of the 19 wells that are within <u>one-half mile</u> of the property or disposal area. Note – the "TWDB Groundwater" and "Well Reports" layers must be activated to see each water well. See the Texas Water Development Board Water Data Interactive website for water well information:

https://www3.twdb.texas.gov/apps/waterdatainteractive/groundwaterdataviewer#.

Andrew Gorton, P.G. & Alan Barraza Permit No. WQ0014309001 November 13, 2024 Page 3

Response from Westwood: Of the 19 identified wells that were installed after the current permit was issued in December 2014, 9 were identified to be within the <u>one-half mile</u> radius of the MUD's disposal areas. These 9 wells are identified on Attachment 20 and the associated well reports are attached. Table 3.0(3) was revised and completed.

Response to Geology/Ground Water Item Comment No. 4:

Comment from Reviewer: For Best Management Practices regarding water wells, please indicate on Table 3.0(3) that the minimum buffer distances of 150 feet (for domestic wells), and 500 feet (for public supply wells), will be maintained between the water wells and the wastewater ponds and effluent irrigation areas.

Response from Westwood: The section for Best Management Practices has been revised. All the wells within the <u>one-half mile</u> radius of the site are for domestic use and meet the required 150' buffer.

Response to Geology/Ground Water Item Comment No. 5:

Comment from Reviewer: Domestic Worksheet 3.0, Section 7. Groundwater Quality: The Groundwater Quality Technical Report was not identified in the application. This Report must assess the impact of the wastewater disposal system on groundwater. This report shall include an evaluation of the water wells, the aquifer at the proposed facility, and use of groundwater in the area (e.g., irrigation public supply, domestic, etc.), the wastewater application rate, and any wastewater pond liners. An example Groundwater Quality Technical Report can be provided upon request.

Response from Westwood: See Attachment 21, this provides a Groundwater Quality Technical Report for the site.

Response to Soils/Agronomy Item Comment No. 1:

Comment from Reviewer: Domestic Worksheet 3.0, Section 2 – Land Application Site: Please list all Phases with their corresponding acreage and effluent volume in Table 3.0(1). The submitted irrigation area and flow do not match any of the currently authorized phases. Changes to acreage and flow are not permitted in renewal applications.

Response from Westwood: This comment was similarly made during Administrative Review and was addressed in our response to those comments. Worksheet 3.0 Table 3.0(1) has been revised.

We are **not** requesting a change to acreage or flow. The facility currently operates in the interim II phase of 100,000 gpd. The facility currently has 100,000 gpd of drip field disposal area constructed. The District will construct additional drip field disposal areas to expand the facility to the ultimate phase of 150,000 gpd over time. The worksheet has been revised to reflect the phases of the permit.

The District is currently working on evaluating additional areas for drip field disposal area expansion and will ultimately file a major permit amendment with the TCEQ to revise the disposal areas of the permit and additional interim phases to ultimately reach the 150,000 gpd limit of the current permit.



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY P.O. Box 13087 Austin, Texas 78711-3087

This is a renewal of Permit No. WQ0014309001 issued March 26, 2010.

PERMIT TO DISCHARGE WASTES

under provisions of Chapter 26 of the Texas Water Code

Hays County Municipal Utility District No. 4

whose mailing address is

c/o Mr. Phil Haag McGinnis Lochridge & Kilgore LLP 600 Congress Avenue, Suite 2100 Austin, Texas 78701

Nature of Business Producing Waste: Domestic wastewater treatment operation, SIC Code 4952.

General Description and Location of Waste Disposal System:

Description: The Hays County Municipal Utility District No. 4 Wastewater Treatment Facility consists of a single stage nitrification activated sludge process. Treatment units in the Interim I phase include a bar screen, an aeration basin, a final clarifier, an aerobic sludge digester, and a chlorine contact chamber. The Interim II and Final phase facilities will include two of each treatment unit listed for the Interim I phase. The permittee is authorized to dispose of treated domestic wastewater effluent at a daily average flow not to exceed 0.075 million gallons per day (MGD) via drip irrigation of 17.22 acres of public access land in the Interim I phase, 0.100 MGD via drip irrigation of 22.96 acres of public access land in the Interim II phase, and 0.150 MGD via drip irrigation of 34.44 acres of public access land in the Final phase. The facility includes one storage tank with a total capacity of 333,000 gallons for storage of treated effluent prior to subsurface drip irrigation. Application rates shall not exceed 0.1 gallons per square foot per day. The irrigated crops include Bermuda grass overseeded with turf grasses on the disposal site.

Location: The wastewater treatment facility and disposal site are located approximately 2,050 feet north of U.S. Highway 290 and approximately 7.2 miles west of the intersection of U.S. Highway 290 with Texas Highway 71, in Hays County, Texas 78737. (See Attachment A.)

Drainage Area: The wastewater treatment facility and disposal site are located in the drainage basin of Barton Creek in Segment No. 1430 of the Colorado River Basin. No discharge of pollutants into water in the State is authorized by this permit.

This permit and the authorization contained herein shall expire at midnight on **September 1**, **2024**.

ISSUED DATE: December 23, 2014

For the Commission

EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTS

Conditions of the Permit: No discharge of pollutants into water in the State is authorized.

A. Effluent Limitations

Character: Treated Domestic Sewage Effluent

<u>Volume</u>: Interim I: Daily Average Flow – 0.075 MGD from the

treatment system

Interim II: Daily Average Flow - 0.100 MGD from the

treatment system

Final: Daily Average Flow – 0.150 MGD from the

treatment system

Quality:

The following effluent limitations shall be required:

	Effluent Concentrations (Not to Exceed)			
	Daily	7-Day	Daily	Single
<u>Parameter</u>	<u>Average</u>	<u>Average</u>	<u>Maximum</u>	<u>Grab</u>
	mg/l	mg/l	mg/	mg/l
Biochemical Oxygen Demand (5-day)	20	30	45	65
Total Suspended Solids	20	30	45	65

The pH shall not be less than 6.0 standard units nor greater than 9.0 standard units.

The effluent shall be chlorinated in a chlorine contact chamber to a residual of 1.0 mg/l with a minimum detention time of 20 minutes.

B. Monitoring Requirements:

<u>Parameter</u>	Monitoring Frequency	Sample Type
Flow (Interim I)	Five/week	Instantaneous
Flow (Interim II and Final)	Continuous	Totalizing Meter
Biochemical Oxygen	One/week	Grab
Demand (5-day)	·	
Total Suspended Solids	One/week	Grab
pH	One/month	Grab
Chlorine Residual	Five/week	Grab

The monitoring shall be done after the final treatment unit and prior to storage of the treated effluent. If the effluent is land applied directly from the treatment system, monitoring shall be done after the final treatment unit and prior to land application. These records shall be maintained on a monthly basis and be available at the plant site for inspection by authorized representatives of the Commission for at least three years.

STANDARD PERMIT CONDITIONS

This permit is granted in accordance with the Texas Water Code and the rules and other Orders of the Commission and the laws of the State of Texas.

DEFINITIONS

All definitions in Section 26.001 of the Texas Water Code and 30 TAC Chapter 305 shall apply to this permit and are incorporated by reference. Some specific definitions of words or phrases used in this permit are as follows:

1. Flow Measurements

- a. Daily average flow the arithmetic average of all determinations of the daily flow within a period of one calendar month. The daily average flow determination shall consist of determinations made on at least four separate days. If instantaneous measurements are used to determine the daily flow, the determination shall be the arithmetic average of all instantaneous measurements taken during that month. Daily average flow determination for intermittent discharges shall consist of a minimum of three flow determinations on days of discharge.
- b. Annual average flow the arithmetic average of all daily flow determinations taken within the preceding 12 consecutive calendar months. The annual average flow determination shall consist of daily flow volume determinations made by a totalizing meter, charted on a chart recorder and limited to major domestic wastewater discharge facilities with 1 million gallons per day or greater permitted flow.
- c. Instantaneous flow the measured flow during the minimum time required to interpret the flow measuring device.

2. Concentration Measurements

- a. Daily average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar month, consisting of at least four separate representative measurements.
 - i. For domestic wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values in the previous four consecutive month period consisting of at least four measurements shall be utilized as the daily average concentration.
 - ii. For all other wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values taken during the month shall be utilized as the daily average concentration.
- b. 7-day average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar week, Sunday through Saturday.
- c. Daily maximum concentration the maximum concentration measured on a single day, by the sample type specified in the permit, within a period of one calendar month.

3. Sample Type

- a. Composite sample For domestic wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (a). For industrial wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (b).
- b. Grab sample an individual sample collected in less than 15 minutes.
- 4. Treatment Facility (facility) wastewater facilities used in the conveyance, storage, treatment, recycling, reclamation and/or disposal of domestic sewage, industrial wastes, agricultural wastes, recreational wastes, or other wastes including sludge handling or disposal facilities under the jurisdiction of the Commission.
- 5. The term "sewage sludge" is defined as solid, semi-solid, or liquid residue generated during the treatment of domestic sewage in 30 TAC Chapter 312. This includes the solids which have not been classified as hazardous waste separated from wastewater by unit processes.
- 6. Bypass the intentional diversion of a waste stream from any portion of a treatment facility.

MONITORING REQUIREMENTS

1. Monitoring Requirements

Monitoring results shall be collected at the intervals specified in the permit. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall conduct effluent sampling in accordance with 30 TAC §§ 319.4 - 319.12.

As provided by state law, the permittee is subject to administrative, civil and criminal penalties, as applicable, for negligently or knowingly violating the Texas Water Code, Chapters 26, 27, and 28, and Texas Health and Safety Code, Chapter 361, including but not limited to knowingly making any false statement, representation, or certification on any report, record or other document submitted or required to be maintained under this permit, including monitoring reports, records or reports of compliance or noncompliance, or falsifying, tampering with or knowingly rendering inaccurate any monitoring device or method required by this permit or violating any other requirement imposed by state or federal regulations.

2. Test Procedures

- a. Unless otherwise specified in this permit, test procedures for the analysis of pollutants shall comply with procedures specified in 30 TAC §§ 319.11 319.12. Measurements, tests and calculations shall be accurately accomplished in a representative manner.
- b. All laboratory tests submitted to demonstrate compliance with this permit must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

3. Records of Results

- a. Monitoring samples and measurements shall be taken at times and in a manner so as to be representative of the monitored activity.
- b. Except for records of monitoring information required by this permit related to the permittee's sewage sludge use and disposal activities, which shall be retained for a period of at least five years, monitoring and reporting records, including strip charts and records of calibration and maintenance, copies of all records required by this permit, and records of all data used to complete the application for this permit shall be retained at the facility site, or shall be readily available for review by a TCEQ representative for a period of three years from the date of the record or sample, measurement, report, or application. This period shall be extended at the request of the Executive Director.
- c. Records of monitoring activities shall include the following:
 - i. date, time and place of sample or measurement;
 - ii. identity of individual who collected the sample or made the measurement.
 - iii. date and time of analysis;
 - iv. identity of the individual and laboratory who performed the analysis;
 - v. the technique or method of analysis; and
 - vi. the results of the analysis or measurement and quality assurance/quality control records.

The period during which records are required to be kept shall be automatically extended to the date of the final disposition of any administrative or judicial enforcement action that may be instituted against the permittee.

4. Additional Monitoring by Permittee

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit using approved analytical methods as specified above, all results of such monitoring shall be included in determining compliance with permit requirements.

5. Calibration of Instruments

All automatic flow measuring or recording devices and all totalizing meters for measuring flows shall be accurately calibrated by a trained person at plant start-up and as often thereafter as necessary to ensure accuracy, but not less often than annually unless authorized by the Executive Director for a longer period. Such person shall verify in writing that the device is operating properly and giving accurate results. Copies of the verification shall be retained at the facility site and/or shall be readily available for review by a TCEQ representative for a period of three years.

6. Compliance Schedule Reports

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date to the Regional Office and the Enforcement Division (MC 224).

7. Noncompliance Notification

- a. In accordance with 30 TAC § 305.125(9), any noncompliance which may endanger human health or safety, or the environment shall be reported by the permittee to the TCEQ. Report of such information shall be provided orally or by facsimile transmission (FAX) to the Regional Office within 24 hours of becoming aware of the noncompliance. A written submission of such information shall also be provided by the permittee to the Regional Office and the Enforcement Division (MC 224) within five working days of becoming aware of the noncompliance. The written submission shall contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
- b. The following violations shall be reported under Monitoring and Reporting Requirement 7.a.:
 - i. Unauthorized discharges as defined in Permit Condition 2(g).
 - ii. Any unanticipated bypass which exceeds any effluent limitation in the permit.
- c. In addition to the above, any effluent violation which deviates from the permitted effluent limitation by more than 40% shall be reported by the permittee in writing to the Regional Office and the Enforcement Division (MC 224) within 5 working days of becoming aware of the noncompliance.
- d. Any noncompliance other than that specified in this section, or any required information not submitted or submitted incorrectly, shall be reported to the Enforcement Division (MC 224) as promptly as possible.
- 8. In accordance with the procedures described in 30 TAC §§ 35.301 35.303 (relating to Water Quality Emergency and Temporary Orders) if the permittee knows in advance of the need for a bypass, it shall submit prior notice by applying for such authorization.
- 9. Changes in Discharges of Toxic Substances

All existing manufacturing, commercial, mining, and silvicultural permittees shall notify the Regional Office, orally or by facsimile transmission within 24 hours, and both the Regional Office and the Enforcement Division (MC 224) in writing within five (5) working days, after becoming aware of or having reason to believe:

- a. That any activity has occurred or will occur which would result in the discharge, on a routine or frequent basis, of any toxic pollutant listed at 40 CFR Part 122, Appendix D, Tables II and III (excluding Total Phenols) which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
 - i. One hundred micrograms per liter (100 µg/L);
 - ii. Two hundred micrograms per liter (200 μg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 μg/L) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;

- iii. Five (5) times the maximum concentration value reported for that pollutant in the permit application; or
- iv. The level established by the TCEQ.
- b. That any activity has occurred or will occur which would result in any discharge, on a nonroutine or infrequent basis, of a toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
 - i. Five hundred micrograms per liter (500 μ g/L);
 - ii. One milligram per liter (1 mg/L) for antimony;
 - iii. Ten (10) times the maximum concentration value reported for that pollutant in the permit application; or
 - iv. The level established by the TCEQ.

10. Signatories to Reports

All reports and other information requested by the Executive Director shall be signed by the person and in the manner required by 30 TAC § 305.128 (relating to Signatories to Reports).

PERMIT CONDITIONS

1. General

- a. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in an application or in any report to the Executive Director, it shall promptly submit such facts or information.
- b. This permit is granted on the basis of the information supplied and representations made by the permittee during action on an application, and relying upon the accuracy and completeness of that information and those representations. After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked, in whole or in part, in accordance with 30 TAC Chapter 305, Subchapter D, during its term for good cause including, but not limited to, the following:
 - i. Violation of any terms or conditions of this permit;
 - ii. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
 - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- c. The permittee shall furnish to the Executive Director, upon request and within a reasonable time, any information to determine whether cause exists for amending, revoking, suspending or terminating the permit. The permittee shall also furnish to the Executive Director, upon request, copies of records required to be kept by the permit.

2. Compliance

a. Acceptance of the permit by the person to whom it is issued constitutes acknowledgment and agreement that such person will comply with all the terms and conditions embodied in the permit, and the rules and other orders of the Commission.

- b. The permittee has a duty to comply with all conditions of the permit. Failure to comply with any permit condition constitutes a violation of the permit and the Texas Water Code or the Texas Health and Safety Code, and is grounds for enforcement action, for permit amendment, revocation or suspension, or for denial of a permit renewal application or an application for a permit for another facility.
- c. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit.
- d. The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal or other permit violation which has a reasonable likelihood of adversely affecting human health or the environment.
- e. Authorization from the Commission is required before beginning any change in the permitted facility or activity that may result in noncompliance with any permit requirements.
- f. A permit may be amended, suspended and reissued, or revoked for cause in accordance with 30 TAC §§ 305.62 and 305.66 and Texas Water Code Section 7.302. The filing of a request by the permittee for a permit amendment, suspension and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.
- g. There shall be no unauthorized discharge of wastewater or any other waste. For the purpose of this permit, an unauthorized discharge is considered to be any discharge of wastewater into or adjacent to water in the state at any location not permitted as an outfall or otherwise defined in the Special Provisions section of this permit.
- h. The permittee is subject to administrative, civil, and criminal penalties, as applicable, under Texas Water Code §§ 7.051 7.075 (relating to Administrative Penalties), 7.101 7.111 (relating to Civil Penalties), and 7.141 7.202 (relating to Criminal Offenses and Penalties).

3. Inspections and Entry

- a. Inspection and entry shall be allowed as prescribed in the Texas Water Code Chapters 26, 27, and 28, and Texas Health and Safety Code Chapter 361.
- b. The members of the Commission and employees and agents of the Commission are entitled to enter any public or private property at any reasonable time for the purpose of inspecting and investigating conditions relating to the quality of water in the state or the compliance with any rule, regulation, permit or other order of the Commission. Members, employees, or agents of the Commission and Commission contractors are entitled to enter public or private property at any reasonable time to investigate or monitor or, if the responsible party is not responsive or there is an immediate danger to public health or the environment, to remove or remediate a condition related to the quality of water in the state. Members, employees, Commission contractors, or agents acting under this authority who enter private property shall observe the establishment's rules and regulations concerning safety, internal security, and fire protection, and if the property has management in residence, shall notify management or the person then in

charge of his presence and shall exhibit proper credentials. If any member, employee, Commission contractor, or agent is refused the right to enter in or on public or private property under this authority, the Executive Director may invoke the remedies authorized in Texas Water Code Section 7.002. The statement above, that Commission entry shall occur in accordance with an establishment's rules and regulations concerning safety, internal security, and fire protection, is not grounds for denial or restriction of entry to any part of the facility, but merely describes the Commission's duty to observe appropriate rules and regulations during an inspection.

4. Permit Amendment and/or Renewal

- a. The permittee shall give notice to the Executive Director as soon as possible of any planned physical alterations or additions to the permitted facility if such alterations or additions would require a permit amendment or result in a violation of permit requirements. Notice shall also be required under this paragraph when:
 - i. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants which are subject neither to effluent limitations in the permit, nor to notification requirements in Monitoring and Reporting Requirements No. 9;
 - ii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan.
- b. Prior to any facility modifications, additions, or expansions that will increase the plant capacity beyond the permitted flow, the permittee must apply for and obtain proper authorization from the Commission before commencing construction.
- c. The permittee must apply for an amendment or renewal at least 180 days prior to expiration of the existing permit in order to continue a permitted activity after the expiration date of the permit. If an application is submitted prior to the expiration date of the permit, the existing permit shall remain in effect until the application is approved, denied, or returned. If the application is returned or denied, authorization to continue such activity shall terminate upon the effective date of the action. If an application is not submitted prior to the expiration date of the permit, the permit shall expire and authorization to continue such activity shall terminate.
- d. Prior to accepting or generating wastes which are not described in the permit application or which would result in a significant change in the quantity or quality of the existing discharge, the permittee must report the proposed changes to the Commission. The permittee must apply for a permit amendment reflecting any necessary changes in permit conditions, including effluent limitations for pollutants not identified and limited by this permit.
- e. In accordance with the Texas Water Code § 26.029(b), after a public hearing, notice of which shall be given to the permittee, the Commission may require the permittee, from time to time, for good cause, in accordance with applicable laws, to conform to new or additional conditions.

5. Permit Transfer

- a. Prior to any transfer of this permit, Commission approval must be obtained. The Commission shall be notified in writing of any change in control or ownership of facilities authorized by this permit. Such notification should be sent to the Applications Review and Processing Team (MC 148) of the Water Quality Division.
- b. A permit may be transferred only according to the provisions of 30 TAC § 305.64 (relating to Transfer of Permits) and 30 TAC § 50.133 (relating to Executive Director Action on Application or WQMP update).

6. Relationship to Hazardous Waste Activities

This permit does not authorize any activity of hazardous waste storage, processing, or disposal which requires a permit or other authorization pursuant to the Texas Health and Safety Code.

7. Property Rights

A permit does not convey any property rights of any sort, or any exclusive privilege.

8. Permit Enforceability

The conditions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

9. Relationship to Permit Application

The application pursuant to which the permit has been issued is incorporated herein; provided, however, that in the event of a conflict between the provisions of this permit and the application, the provisions of the permit shall control.

10. Notice of Bankruptcy.

- a. Each permittee shall notify the Executive Director, in writing, immediately following the filing of a voluntary or involuntary petition for bankruptcy under any chapter of Title 11 (Bankruptcy) of the United States Code (11 USC) by or against:
 - i. the permittee;
 - ii. an entity (as that term is defined in 11 USC, § 101(14)) controlling the permittee or listing the permit or permittee as property of the estate; or
 - iii. an affiliate (as that term is defined in 11 USC, § 101(2)) of the permittee.

b. This notification must indicate:

- i. the name of the permittee;
- ii. the permit number(s);
- iii. the bankruptcy court in which the petition for bankruptcy was filed; and
- iv. the date of filing of the petition.

OPERATIONAL REQUIREMENTS

- 1. The permittee shall at all times ensure that the facility and all of its systems of collection, treatment, and disposal are properly operated and maintained. This includes, but is not limited to, the regular, periodic examination of wastewater solids within the treatment plant by the operator in order to maintain an appropriate quantity and quality of solids inventory as described in the various operator training manuals and according to accepted industry standards for process control. Process control, maintenance, and operations records shall be retained at the facility site, or shall be readily available for review by a TCEQ representative, for a period of three years.
- 2. Upon request by the Executive Director, the permittee shall take appropriate samples and provide proper analysis in order to demonstrate compliance with Commission rules. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall comply with all applicable provisions of 30 TAC Chapter 312 concerning sewage sludge use and disposal and 30 TAC §§ 319.21 319.29 concerning the discharge of certain hazardous metals.
- 3. Domestic wastewater treatment facilities shall comply with the following provisions:
 - a. The permittee shall notify the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, in writing, of any facility expansion at least 90 days prior to conducting such activity.
 - b. The permittee shall submit a closure plan for review and approval to the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, for any closure activity at least 90 days prior to conducting such activity. Closure is the act of permanently taking a waste management unit or treatment facility out of service and includes the permanent removal from service of any pit, tank, pond, lagoon, surface impoundment and/or other treatment unit regulated by this permit.
- 4. The permittee is responsible for installing prior to plant start-up, and subsequently maintaining, adequate safeguards to prevent the discharge of untreated or inadequately treated wastes during electrical power failures by means of alternate power sources, standby generators, and/or retention of inadequately treated wastewater.
- 5. Unless otherwise specified, the permittee shall provide a readily accessible sampling point and, where applicable, an effluent flow measuring device or other acceptable means by which effluent flow may be determined.
- 6. The permittee shall remit an annual water quality fee to the Commission as required by 30 TAC Chapter 21. Failure to pay the fee may result in revocation of this permit under Texas Water Code § 7.302(b)(6).

7. Documentation

For all written notifications to the Commission required of the permittee by this permit, the permittee shall keep and make available a copy of each such notification under the same conditions as self-monitoring data are required to be kept and made available. Except for information specified as not confidential in 30 TAC § 1.5(d), any information submitted pursuant to this permit may be claimed as confidential by the submitter. Any such claim

must be asserted in the manner prescribed in the application form or by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, information may be made available to the public without further notice. If the Commission or Executive Director agrees with the designation of confidentiality, the TCEQ will not provide the information for public inspection unless required by the Texas Attorney General or a court pursuant to an open records request. If the Executive Director does not agree with the designation of confidentiality, the person submitting the information will be notified.

- 8. Facilities which generate domestic wastewater shall comply with the following provisions; domestic wastewater treatment facilities at permitted industrial sites are excluded.
 - a. Whenever flow measurements for any domestic sewage treatment facility reach 75 percent of the permitted daily average or annual average flow for three consecutive months, the permittee must initiate engineering and financial planning for expansion and/or upgrading of the domestic wastewater treatment and/or collection facilities. Whenever the flow reaches 90 percent of the permitted daily average or annual average flow for three consecutive months, the permittee shall obtain necessary authorization from the Commission to commence construction of the necessary additional treatment and/or collection facilities. In the case of a domestic wastewater treatment facility which reaches 75 percent of the permitted daily average or annual average flow for three consecutive months, and the planned population to be served or the quantity of waste produced is not expected to exceed the design limitations of the treatment facility, the permittee shall submit an engineering report supporting this claim to the Executive Director of the Commission.

If in the judgement of the Executive Director the population to be served will not cause permit noncompliance, then the requirement of this section may be waived. To be effective, any waiver must be in writing and signed by the Director of the Enforcement Division (MC 169) of the Commission, and such waiver of these requirements will be reviewed upon expiration of the existing permit; however, any such waiver shall not be interpreted as condoning or excusing any violation of any permit parameter.

- b. The plans and specifications for domestic sewage collection and treatment works associated with any domestic permit must be approved by the Commission, and failure to secure approval before commencing construction of such works or making a discharge is a violation of this permit and each day is an additional violation until approval has been secured.
- c. Permits for domestic wastewater treatment plants are granted subject to the policy of the Commission to encourage the development of area-wide waste collection, treatment and disposal systems. The Commission reserves the right to amend any domestic wastewater permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an area-wide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such area-wide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.

- 9. Domestic wastewater treatment plants shall be operated and maintained by sewage plant operators holding a valid certificate of competency at the required level as defined in 30 TAC Chapter 30.
- 10. Facilities which generate industrial solid waste as defined in 30 TAC § 335.1 shall comply with these provisions:
 - a. Any solid waste, as defined in 30 TAC § 335.1 (including but not limited to such wastes as garbage, refuse, sludge from a waste treatment, water supply treatment plant or air pollution control facility, discarded materials, discarded materials to be recycled, whether the waste is solid, liquid, or semisolid), generated by the permittee during the management and treatment of wastewater, must be managed in accordance with all applicable provisions of 30 TAC Chapter 335, relating to Industrial Solid Waste Management.
 - b. Industrial wastewater that is being collected, accumulated, stored, or processed before discharge through any final discharge outfall, specified by this permit, is considered to be industrial solid waste until the wastewater passes through the actual point source discharge and must be managed in accordance with all applicable provisions of 30 TAC Chapter 335.
 - c. The permittee shall provide written notification, pursuant to the requirements of 30 TAC § 335.8(b)(1), to the Environmental Cleanup Section (MC 127) of the Remediation Division informing the Commission of any closure activity involving an Industrial Solid Waste Management Unit, at least 90 days prior to conducting such an activity.
 - d. Construction of any industrial solid waste management unit requires the prior written notification of the proposed activity to the Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division. No person shall dispose of industrial solid waste, including sludge or other solids from wastewater treatment processes, prior to fulfilling the deed recordation requirements of 30 TAC § 335.5.
 - e. The term "industrial solid waste management unit" means a landfill, surface impoundment, waste-pile, industrial furnace, incinerator, cement kiln, injection well, container, drum, salt dome waste containment cavern, or any other structure vessel, appurtenance, or other improvement on land used to manage industrial solid waste.
 - f. The permittee shall keep management records for all sludge (or other waste) removed from any wastewater treatment process. These records shall fulfill all applicable requirements of 30 TAC Chapter 335 and must include the following, as it pertains to wastewater treatment and discharge:
 - i. Volume of waste and date(s) generated from treatment process;
 - ii. Volume of waste disposed of on-site or shipped off-site;
 - iii. Date(s) of disposal;
 - iv. Identity of hauler or transporter;
 - v. Location of disposal site; and
 - vi. Method of final disposal.

The above records shall be maintained on a monthly basis. The records shall be retained at the facility site, or shall be readily available for review by authorized representatives of

the TCEQ for at least five years.

11. For industrial facilities to which the requirements of 30 TAC Chapter 335 do not apply, sludge and solid wastes, including tank cleaning and contaminated solids for disposal, shall be disposed of in accordance with Chapter 361 of the Texas Health and Safety Code.

TCEQ Revision o6/2008

SLUDGE PROVISIONS

The permittee is authorized to dispose of sludge only at a Texas Commission on Environmental Quality (TCEQ) authorized land application site or co-disposal landfill. The disposal of sludge by land application on property owned, leased or under the direct control of the permittee is a violation of the permit unless the site is authorized by the TCEQ. This provision does not authorize Distribution and Marketing of sludge. This provision does not authorize land application of Class A Sludge. This provision does not authorize the permittee to land apply sludge on property owned, leased or under the direct control of the permittee.

SECTION I. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE LAND APPLICATION

A. General Requirements

- 1. The permittee shall handle and dispose of sewage sludge in accordance with 30 TAC Chapter 312 and all other applicable state and federal regulations in a manner which protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants which may be present in the sludge.
- 2. In all cases, if the person (permit holder) who prepares the sewage sludge supplies the sewage sludge to another person for land application use or to the owner or lease holder of the land, the permit holder shall provide necessary information to the parties who receive the sludge to assure compliance with these regulations.
- 3. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.

B. Testing Requirements

1. Sewage sludge shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I [Toxicity Characteristic Leaching Procedure (TCLP)] or other method, which receives the prior approval of the TCEQ for the contaminants listed in Table 1 of 40 CFR Section 261.24. Sewage sludge failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal. Following failure of any TCLP test, the management or disposal of sewage sludge at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division and the Regional Director (MC Region 11) within 7 days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to:

Director, Permitting and Remediation Support Division (MC 129), Texas Commission on Environmental Quality, P. O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 11) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30 of each year.

2. Sewage sludge shall not be applied to the land if the concentration of the pollutants exceed the pollutant concentration criteria in Table 1. The frequency of testing for pollutants in Table 1 is found in Section I.C.

TABLE 1

<u>Pollutant</u>	Ceiling Concentration
	(Milligrams per kilogram)*
Arsenic	75
Cadmium	85
Chromium	3000
Copper	4300
Lead	840
Mercury	57
Molybdenum	<i>7</i> 5
Nickel	420
PCBs	49
Selenium	100
Zinc	7500

^{*} Dry weight basis

3. Pathogen Control

All sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site shall be treated by one of the following methods to ensure that the sludge meets either the Class A or Class B pathogen requirements.

a. Six alternatives are available to demonstrate compliance with Class A sewage sludge. The first 4 options require either the density of fecal coliform in the sewage sludge be less than 1000 Most Probable Number (MPN) per gram of total solids (dry weight basis), or the density of Salmonella sp. bacteria in the sewage sludge be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. Below are the <u>additional</u> requirements necessary to meet the definition of a Class A sludge.

Alternative 1 - The temperature of the sewage sludge that is used or disposed shall be maintained at or above a specific value for a period of time. See 30 TAC Section 312.82(a)(2)(A) for specific information.

<u>Alternative 2</u> - The pH of the sewage sludge that is used or disposed shall be raised to above 12 std. units and shall remain above 12 std. units for 72 hours.

The temperature of the sewage sludge shall be above 52 degrees Celsius for 12 hours or longer during the period that the pH of the sewage sludge is above 12 std. units.

At the end of the 72-hour period during which the pH of the sewage sludge is above 12 std. units, the sewage sludge shall be air dried to achieve a percent solids in the sewage sludge greater than 50 percent.

Alternative 3 - The sewage sludge shall be analyzed for enteric viruses prior to pathogen treatment. The limit for enteric viruses is less than one Plaque-forming Unit per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC Section 312.82(a)(2)(C)(i-iii) for specific information. The sewage sludge shall be analyzed for viable helminth ova prior to pathogen treatment. The limit for viable helminth ova is less than one per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC Section 312.82(a)(2)(C)(iv-vi) for specific information.

Alternative 4 - The density of enteric viruses in the sewage sludge shall be less than one Plaque-forming Unit per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. The density of viable helminth ova in the sewage sludge shall be less than one per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed.

Alternative 5 (PFRP) - Sewage sludge that is used or disposed of shall be treated in one of the processes to Further Reduce Pathogens (PFRP) described in 40 CFR Part 503, Appendix B. PFRP include composting, heat drying, heat treatment, and thermophilic aerobic digestion.

<u>Alternative 6</u> (PFRP Equivalent) - Sewage sludge that is used or disposed of shall be treated in a process that has been approved by the U.S. Environmental Protection Agency as being equivalent to those in Alternative 5.

b. Three alternatives are available to demonstrate compliance with Class B criteria for sewage sludge.

Alternative 1 -

- i. A minimum of seven random samples of the sewage sludge shall be collected within 48 hours of the time the sewage sludge is used or disposed of during each monitoring episode for the sewage sludge.
- ii. The geometric mean of the density of fecal coliform in the samples collected shall be less than either 2,000,000 MPN per gram of total solids (dry weight basis) or 2,000,000 Colony Forming Units per gram of total solids (dry weight basis).

<u>Alternative 2</u> - Sewage sludge that is used or disposed of shall be treated in one of the Processes to Significantly Reduce Pathogens (PSRP) described in 40 CFR Part 503, Appendix B, so long as all of the following requirements are met by the generator of the sewage sludge.

i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;

- ii. An independent Texas Licensed Professional Engineer must make a certification to the generator of sewage sludge that the wastewater treatment facility generating the sewage sludge is designed to achieve one of the PSRP at the permitted design loading of the facility. The certification need only be repeated if the design loading of the facility is increased. The certification shall include a statement indicating the design meets all the applicable standards specified in Appendix B of 40 CFR Part 503;
- iii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iv. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review; and
- v. If the sewage sludge is generated from a mixture of sources, resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the PSRP, and shall meet the certification, operation, and record keeping requirements of this paragraph.

<u>Alternative 3</u> - Sewage sludge shall be treated in an equivalent process that has been approved by the U.S. Environmental Protection Agency, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;
- ii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iii. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review;
- iv. The Executive Director will accept from the U.S. Environmental Protection Agency a finding of equivalency to the defined PSRP; and

- v. If the sewage sludge is generated from a mixture of sources resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the Processes to Significantly Reduce Pathogens, and shall meet the certification, operation, and record keeping requirements of this paragraph.
 - In addition, the following site restrictions must be met if Class B sludge is land applied:
- i. Food crops with harvested parts that touch the sewage sludge/soil mixture and are totally above the land surface shall not be harvested for 14 months after application of sewage sludge.
- ii. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after application of sewage sludge when the sewage sludge remains on the land surface for 4 months or longer prior to incorporation into the soil.
- iii. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months after application of sewage sludge when the sewage sludge remains on the land surface for less than 4 months prior to incorporation into the soil.
- iv. Food crops, feed crops, and fiber crops shall not be harvested for 30 days after application of sewage sludge.
- v. Animals shall not be allowed to graze on the land for 30 days after application of sewage sludge.
- vi. Turf grown on land where sewage sludge is applied shall not be harvested for 1 year after application of the sewage sludge when the harvested turf is placed on either land with a high potential for public exposure or a lawn.
- vii. Public access to land with a high potential for public exposure shall be restricted for 1 year after application of sewage sludge.
- viii. Public access to land with a low potential for public exposure shall be restricted for 30 days after application of sewage sludge.
- ix. Land application of sludge shall be in accordance with the buffer zone requirements found in 30 TAC Section 312.44.
- 4. Vector Attraction Reduction Requirements

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site shall be treated by one of the following alternatives 1 through 10 for Vector Attraction Reduction.

Alternative 1 - The mass of volatile solids in the sewage sludge shall be reduced by a minimum of 38 percent.

Alternative 2 -

If Alternative 1 cannot be met for an anaerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge anaerobically in the laboratory in a bench-scale unit for 40 additional days at a temperature between 30 and 37 degrees Celsius. Volatile solids must be reduced by less than 17 percent to demonstrate compliance.

Alternative 3 -

If Alternative 1 cannot be met for an aerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge with percent solids of two percent or less aerobically in the laboratory in a bench-scale unit for 30 additional days at 20 degrees Celsius. Volatile solids must be reduced by less than 15 percent to demonstrate compliance.

Alternative 4 -

The specific oxygen uptake rate (SOUR) for sewage sludge treated in an aerobic process shall be equal to or less than 1.5 milligrams of oxygen per hour per gram of total solids (dry weight basis) at a temperature of 20 degrees Celsius.

Alternative 5 -

Sewage sludge shall be treated in an aerobic process for 14 days or longer. During that time, the temperature of the sewage sludge shall be higher than 40 degrees Celsius and the average temperature of the sewage sludge shall be higher than 45 degrees Celsius.

Alternative 6 -

The pH of sewage sludge shall be raised to 12 or higher by alkali addition and, without the addition of more alkali shall remain at 12 or higher for two hours and then remain at a pH of 11.5 or higher for an additional 22 hours at the time the sewage sludge is prepared for sale or given away in a bag or other container.

Alternative 7 -

The percent solids of sewage sludge that does not contain unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 75 percent based on the moisture content and total solids prior to mixing with other materials. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

Alternative 8 -

The percent solids of sewage sludge that contains unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 90 percent based on the moisture content and total solids prior to mixing with other materials at the time the sludge is used. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

Alternative 9 -

- i. Sewage sludge shall be injected below the surface of the land.
- ii. No significant amount of the sewage sludge shall be present on the land surface within one hour after the sewage sludge is injected.

iii. When sewage sludge that is injected below the surface of the land is Class A with respect to pathogens, the sewage sludge shall be injected below the land surface within eight hours after being discharged from the pathogen treatment process.

Alternative 10-

- i. Sewage sludge applied to the land surface or placed on a surface disposal site shall be incorporated into the soil within six hours after application to or placement on the land.
- ii. When sewage sludge that is incorporated into the soil is Class A with respect to pathogens, the sewage sludge shall be applied to or placed on the land within eight hours after being discharged from the pathogen treatment process.

C. Monitoring Requirements

Toxicity Characteristic Leaching Procedure (TCLP) Test

- once during the term of this permit

PCBs

- once during the term of this permit

All metal constituents and fecal coliform or Salmonella sp. bacteria shall be monitored at the appropriate frequency shown below, pursuant to 30 TAC § 312.46(a)(1):

Amount of sewage sludge (*) metric tons per 365-day period	Monitoring Frequency
o to less than 290	Once/Year
290 to less than 1,500	Once/Quarter
1,500 to less than 15,000	Once/Two Months
15,000 or greater	Once/Month

(*) The amount of bulk sewage sludge applied to the land (dry weight basis).

Representative samples of sewage sludge shall be collected and analyzed in accordance with the methods referenced in 30 TAC § 312.7

SECTION II.

REQUIREMENTS SPECIFIC TO BULK SEWAGE SLUDGE FOR APPLICATION TO THE LAND MEETING CLASS A or B PATHOGEN REDUCTION AND THE CUMULATIVE LOADING RATES IN TABLE 2, OR CLASS B PATHOGEN REDUCTION AND THE POLLUTANT CONCENTRATIONS IN TABLE 3

For those permittees meeting Class A or B pathogen reduction requirements and that meet the cumulative loading rates in Table 2 below, or the Class B pathogen reduction requirements and contain concentrations of pollutants below listed in Table 3, the following conditions apply:

A. Pollutant Limits

Table 2

Pollutant Arsenic Cadmium Chromium Copper Lead Mercury Molybdenum Nickel Selenium	Cumulative Pollutant Loading Rate (pounds per acre)* 36 35 2677 1339 268 15 Report Only 375 89
	<u> </u>
Zinc	2500

Table 3

	Monthly Average Concentration	
<u>Pollutant</u>	(milligrams per kilogram)*	
Arsenic	41	
Cadmium	39	
Chromium	1200	
Copper	1500	
Lead	300	
Mercury	17	
Molybdenum	Report Only	
Nickel	420	
Selenium	36	
Zinc	2800	
*Dry weight basis		

B. Pathogen Control

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, a reclamation site, shall be treated by either Class A or Class B pathogen reduction requirements as defined above in Section I.B.3.

C. Management Practices

- 1. Bulk sewage sludge shall not be applied to agricultural land, forest, a public contact site, or a reclamation site that is flooded, frozen, or snow-covered so that the bulk sewage sludge enters a wetland or other waters in the State.
- 2. Bulk sewage sludge not meeting Class A requirements shall be land applied in a manner which complies with the Management Requirements in accordance with 30 TAC Section 312.44.
- 3. Bulk sewage sludge shall be applied at or below the agronomic rate of the cover crop.
- 4. An information sheet shall be provided to the person who receives bulk sewage sludge sold or given away. The information sheet shall contain the following information:
 - a. The name and address of the person who prepared the sewage sludge that is sold or given away in a bag or other container for application to the land.
 - b. A statement that application of the sewage sludge to the land is prohibited except in accordance with the instruction on the label or information sheet.
 - c. The annual whole sludge application rate for the sewage sludge application rate for the sewage sludge that does not cause any of the cumulative pollutant loading rates in Table 2 above to be exceeded, unless the pollutant concentrations in Table 3 found in Section II above are met.

D. Notification Requirements

- 1. If bulk sewage sludge is applied to land in a State other than Texas, written notice shall be provided prior to the initial land application to the permitting authority for the State in which the bulk sewage sludge is proposed to be applied. The notice shall include:
 - a. The location, by street address, and specific latitude and longitude, of each land application site.
 - b. The approximate time period bulk sewage sludge will be applied to the site.
 - c. The name, address, telephone number, and National Pollutant Discharge Elimination System permit number (if appropriate) for the person who will apply the bulk sewage sludge.
- 2. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.

E. Record keeping Requirements

The sludge documents will be retained at the facility site and/or shall be readily available for review by a TCEQ representative. The person who prepares bulk sewage sludge or a sewage sludge material shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative for a

period of five years. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC Section 312.47 for persons who land apply.

- 1. The concentration (mg/kg) in the sludge of each pollutant listed in Table 3 above and the applicable pollutant concentration criteria (mg/kg), or the applicable cumulative pollutant loading rate and the applicable cumulative pollutant loading rate limit (lbs/ac) listed in Table 2 above.
- 2. A description of how the pathogen reduction requirements are met (including site restrictions for Class B sludges, if applicable).
- 3. A description of how the vector attraction reduction requirements are met.
- 4. A description of how the management practices listed above in Section II.C are being met.
- 5. The following certification statement:

"I certify, under penalty of law, that the applicable pathogen requirements in 30 TAC Section 312.82(a) or (b) and the vector attraction reduction requirements in 30 TAC Section 312.83(b) have been met for each site on which bulk sewage sludge is applied. This determination has been made under my direction and supervision in accordance with the system designed to ensure that qualified personnel properly gather and evaluate the information used to determine that the management practices have been met. I am aware that there are significant penalties for false certification including fine and imprisonment."

6. The recommended agronomic loading rate from the references listed in Section II.C.3. above, as well as the actual agronomic loading rate shall be retained.

The person who applies bulk sewage sludge or a sewage sludge material shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative indefinitely. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC Section 312.47 for persons who land apply.

- a. A certification statement that all applicable requirements (specifically listed) have been met, and that the permittee understands that there are significant penalties for false certification including fine and imprisonment. See 30 TAC Section 312.47(a)(4)(A)(ii) or 30 TAC Section 312.47(a)(5)(A)(ii), as applicable, and to the permittee's specific sludge treatment activities.
- b. The location, by street address, and specific latitude and longitude, of each site on which sludge is applied.
- c. The number of acres in each site on which bulk sludge is applied.
- d. The date and time sludge is applied to each site.

- e. The cumulative amount of each pollutant in pounds/acre listed in Table 2 applied to each site.
- f. The total amount of sludge applied to each site in dry tons.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

F. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 11) and Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division, by September 30 of each year the following information:

- 1. Results of tests performed for pollutants found in either Table 2 or 3 as appropriate for the permittee's land application practices.
- 2. The frequency of monitoring listed in Section I.C. which applies to the permittee.
- 3. Toxicity Characteristic Leaching Procedure (TCLP) results.
- 4. Identity of hauler(s) and TCEO transporter number.
- 5. PCB concentration in sludge in mg/kg.
- 6. Date(s) of disposal.
- 7. Owner of disposal site(s).
- 8. Texas Commission on Environmental Quality registration number, if applicable.
- 9. Amount of sludge disposal dry weight (lbs/acre) at each disposal site.
- 10. The concentration (mg/kg) in the sludge of each pollutant listed in Table 1 (defined as a monthly average) as well as the applicable pollutant concentration criteria (mg/kg) listed in Table 3 above, or the applicable pollutant loading rate limit (lbs/acre) listed in Table 2 above if it exceeds 90% of the limit.
- 11. Level of pathogen reduction achieved (Class A or Class B).
- 12. Alternative used as listed in Section I.B.3.(a. or b.). Alternatives describe how the pathogen reduction requirements are met. If Class B sludge, include information on how site restrictions were met.
- 13. Vector attraction reduction alternative used as listed in Section I.B.4.
- 14. Annual sludge production in dry tons/year.
- 15. Amount of sludge land applied in dry tons/year.

- 16. The certification statement listed in either 30 TAC Section 312.47(a)(4)(A)(ii) or 30 TAC Section 312.47(a)(5)(A)(ii) as applicable to the permittee's sludge treatment activities, shall be attached to the annual reporting form.
- 17. When the amount of any pollutant applied to the land exceeds 90% of the cumulative pollutant loading rate for that pollutant, as described in Table 2, the permittee shall report the following information as an attachment to the annual reporting form.
 - a. The location, by street address, and specific latitude and longitude.
 - b. The number of acres in each site on which bulk sewage sludge is applied.
 - c. The date and time bulk sewage sludge is applied to each site.
 - d. The cumulative amount of each pollutant (i.e., pounds/acre) listed in Table 2 in the bulk sewage sludge applied to each site.
 - e. The amount of sewage sludge (i.e., dry tons) applied to each site.

The above records shall be maintained on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SECTION III. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE DISPOSED IN A MUNICIPAL SOLID WASTE LANDFILL

- A. The permittee shall handle and dispose of sewage sludge in accordance with 30 TAC Chapter 330 and all other applicable state and federal regulations to protect public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present. The permittee shall ensure that the sewage sludge meets the requirements in 30 TAC Chapter 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- B. If the permittee generates sewage sludge and supplies that sewage sludge to the owner or operator of a Municipal Solid Waste Landfill (MSWLF) for disposal, the permittee shall provide to the owner or operator of the MSWLF appropriate information needed to be in compliance with the provisions of this permit.
- C. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge disposal practice.
- D. Sewage sludge shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I (Toxicity Characteristic Leaching Procedure) or other method, which receives the prior approval of the TCEQ for contaminants listed in Table 1 of 40 CFR Section 261.24. Sewage sludge failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal.

Following failure of any TCLP test, the management or disposal of sewage sludge at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division and the Regional Director (MC Region 11) of the appropriate TCEQ field office within 7 days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Permitting and Remediation Support Division (MC 129), Texas Commission on Environmental Quality, P. O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 11) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30 of each year.

E. Sewage sludge shall be tested as needed, in accordance with the requirements of 30 TAC Chapter 330.

F. Record keeping Requirements

The permittee shall develop the following information and shall retain the information for five years.

- 1. The description (including procedures followed and the results) of all liquid Paint Filter Tests performed.
- 2. The description (including procedures followed and results) of all TCLP tests performed.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

G. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 11) and Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30 of each year the following information:

- 1. Toxicity Characteristic Leaching Procedure (TCLP) results.
- 2. Annual sludge production in dry tons/year.
- 3. Amount of sludge disposed in a municipal solid waste landfill in dry tons/year.
- 4. Amount of sludge transported interstate in dry tons/year.
- 5. A certification that the sewage sludge meets the requirements of 30 TAC Chapter 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- 6. Identity of hauler(s) and transporter registration number.
- 7. Owner of disposal site(s).
- 8. Location of disposal site(s).
- 9. Date(s) of disposal.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SPECIAL PROVISIONS:

- this permit is granted subject to the policy of the Commission to encourage the development of areawide waste collection, treatment and disposal systems. The Commission reserves the right to amend this permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an areawide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such areawide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.
- 2. The permittee shall employ or contract with one or more licensed wastewater treatment facility operators or wastewater system operations companies holding a valid license or registration according to the requirements of 30 TAC Chapter 30, Occupational Licenses and Registrations and in particular 30 TAC Chapter 30, Subchapter J, Wastewater Operators and Operations Companies.
 - This Category C facility must be operated by a chief operator or an operator holding a Category C license or higher. The facility must be operated a minimum of five days per week by the licensed chief operator or an operator holding the required level of license or higher. The licensed chief operator or operator holding the required level of license or higher must be available by telephone or pager seven days per week. Where shift operation of the wastewater treatment facility is necessary, each shift which does not have the on-site supervision of the licensed chief operator must be supervised by an operator in charge who is licensed not less than one level below the category for the facility.
- 3. The permittee shall maintain and operate the treatment facility in order to achieve optimum efficiency of treatment capability. This shall include required monitoring of effluent flow and quality as well as appropriate grounds and building maintenance.
- 4. The subsurface drainfield shall be designed and managed so as to prevent ponding or surfacing of effluent or contamination of ground and surface waters and to prevent the occurrence of nuisance conditions in the area. Bermuda grass overseeded with other turf grasses shall be established and well maintained in the irrigation area throughout the year for effluent and nutrient uptake by the crop and to prevent pathways for effluent surfacing.
- 5. Effluent shall not be applied for irrigation when the ground is saturated.
- 6. The irrigated crops include Bermuda grass overseeded with other turf grasses on the disposal site. Application rates shall not exceed 0.1 gallons per square foot per day. The permittee is responsible for providing equipment to determine application rates and maintaining accurate records of the volume of effluent applied. These records shall be made available for review by the Texas Commission on Environmental Quality and shall be maintained for at least three years.
- 7. The permittee shall provide facilities for the protection of its wastewater treatment facilities from a 100-year flood.

- 8. Prior to construction of the Interim II and Final phase wastewater treatment facilities, the permittee shall submit to the TCEQ Wastewater Permitting Section (MC 148) of the Water Quality Division, a summary submittal letter according to the requirements in 30 TAC Section 217.6(c). If requested by the Wastewater Permitting Section, the permittee shall submit plans, specifications and a final engineering design report which comply with the requirements of 30 TAC Chapter 217, Design Criteria for Wastewater Treatment Systems. The permittee shall clearly show how the treatment system will meet the final permitted effluent limitations required on Page 2 of the permit.
- 9. The permittee shall obtain representative soil samples from the root zones of the land application area receiving wastewater. Composite sampling techniques shall be used. Each composite sample shall represent no more than 34.44 acres with no less than 10 to 15 subsamples representing each composite sample. Subsamples shall be composited by like sampling depth and soil type for analysis and reporting. Soil types are soils that have like topsoil or plow layer textures. These soils shall be sampled individually from 0 to 6 inches, 6 inches to 18 inches and 18 inches to 30 inches below ground level. The permittee shall sample and analyze soils in December to February of each year. Soil samples shall be analyzed within 30 days of sample procurement.

The permittee shall provide annual soil analyses of the land application area according to the following table:

Parameter	Method	Minimum Analytical Level (MAL)	Reporting units
рН	2:1 (v/v) water to soil mixture		Reported to 0.1 pH units after calibration of pH meter
Electrical Conductivity	2:1 (v/v) water to soil mixture	0.01	dS/m (same as mmho/cm)
Nitrate- nitrogen	From a 1 N KCl soil extract	1	mg/kg (dry weight basis)
Total Kjeldahl Nitrogen (TKN)	For determination of Organic plus Ammonium Nitrogen. Procedures that use Mercury (Hg) are not acceptable.	20	mg/kg (dry weight basis)
Total Nitrogen	= TKN + nitrate-nitrogen (same as, organic-nitrogen + ammonium-nitrogen + nitrate-nitrogen)		mg/kg (dry weight basis)
Plant- available: Phosphorus	Mehlich III with inductively coupled plasma	1	mg/kg (dry weight basis)

Parameter	Method	Minimum Analytical Level (MAL)	Reporting units
Plant- available: Potassium	May be determined in the same Mehlich III extract with inductively coupled plasma	5 (K)	mg/kg (dry weight basis)
Amendment addition, e.g., gypsum	Recommendation from analytical laboratory		Report in <i>short</i> tons/acre in the year effected

The permittee shall provide a copy of this plan to the analytical laboratory prior to sample analysis. The permittee shall submit the results of the annual soil sample analyses with copies of the laboratory reports and a map depicting the areas that have received wastewater within the permanent land application fields to the TCEQ Regional Office (MC Region 11) and the Water Quality Compliance Monitoring Team (MC 224) of the Enforcement Division no later than end of September following the sampling date of each year. If wastewater is not applied in a particular year, the permittee shall notify the same TCEQ offices and indicate that wastewater and/or sludge has not been applied on the approved land disposal sites during that year.


- 10. The permittee shall maintain a long term contract with the owner(s) of the land application site which is authorized for use in this permit, or own the land authorized for land application of treated effluent.
- 11. Treatment preceding disposal shall remove sufficient total suspended solids from the wastewater to preclude plugging of the drip-emitters.
- 12. Pressure reducing devices (drip-emitters) shall be spaced at 24-inch minimum intervals along the drainfield distribution lines. Distribution line spacing shall be two feet.
- 13. Soil shall be imported to alleviate the existing soil limitations of shallow depth to bedrock. Soil thickness and classification will be determined after importation by a licensed professional engineer or soil scientist.
- 14. Drip irrigation lines shall be placed between 6 and 12 inches of the rooting zone of surface soils. There shall be at least 12 inches of soil suitable for wastewater absorption and root penetration beneath the drip lines.

15. The permittee shall maintain the following separation distances:

	Process Units (ft)	Soil Absorptive System (ft)
Private Water Wells	250	150
Public Water Wells	500	500
Water Supply Lines	10	10
Surface Water Bodies	75	. 75
Sharp Slopes, Breaks	50	10
Swimming Pools	150	50

- 16. At least 60 days prior to commencing the closure of this on-site wastewater management system, the permittee shall provide notice to the TCEQ Region 11 Office of the expected closure schedule.
- 17. Vehicle traffic, except for mowers, shall be prohibited from the subsurface drip-emitter drainfield area.
- 18. An audio-visual alarm shall be provided for the system to monitor pump tank high water levels, power failure and pump failure. The alarm system shall be capable of notifying the treatment system operator during all hours of operation, including drainfield dosing and backwash.
- 19. Permanent transmission lines shall be installed from the pump tank to each tract of land to be irrigated utilizing effluent from that tank.
- 20. The permittee shall comply with the requirements of 30 TAC Section 309.13(a) through (d). In addition, by ownership of the required buffer zone area, the permittee shall comply with the requirements of 30 TAC Section 309.13(e).
- 21. The permittee shall secure written approval form the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division before accepting for treatment in this facility any wastes significantly different from normal domestic wastewater. Before providing such approval, the Executive Director may require additional information regarding the nature, quantity, and treatability of the wastes.
- 22. The permittee shall notify the TCEQ Regional Office (MC Region 11) and the Applications Review and Processing Team (MC 148) of the Water Quality Division in writing at least forty-five (45) days prior to the completion of the Interim II and Final phases on Notification of Completion Form 20007.
- 23. The permittee shall pump and haul wastewater from the facility to prevent the discharge of treated or untreated wastewater if complete shutdown of the wastewater treatment facility becomes necessary or if the storage capacity is exceeded.

- 24. Irrigation with effluent shall be accomplished only when the area specified is not in use.
- 25. The permittee shall erect adequate signs stating that the irrigation water is from a non-potable water supply for any area where treated effluent is stored or where there exist hose bibs or faucets. Signs shall consist of a red slash superimposed over the international symbol for drinking water accompanied by the message "DO NOT DRINK THE WATER" in both English and Spanish. All piping transporting the effluent shall be clearly marked with these same signs.



TECHNICAL SUMMARY AND EXECUTIVE DIRECTOR'S PRELIMINARY DECISION

DESCRIPTION OF APPLICATION

Applicant: Hays County Municipal Utility District No. 4

TCEQ Permit No. WQ0014309001

Regulated Activity: Domestic Wastewater Permit

Type of Application: Renewal

Request: Renewal with changes

Authority: Texas Water Code (TWC) § 26.027; 30 Texas Administrative

Code (TAC) Chapters 222, 305, 309, 312, 319, and 30; and

Commission policies.

EXECUTIVE DIRECTOR RECOMMENDATION

The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The draft permit includes an expiration date of **ten years from the date of issuance**, according to 30 TAC § 305.127(1)(C)(ii)(III), Conditions to be Determined for Individual Permits.

REASON FOR PROJECT PROPOSED

Hays County Municipal Utility District No. 4 has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of Permit No. WQ0014309001 to authorize the disposal of treated domestic wastewater at a daily average flow not to exceed 0.10 million gallons per day (MGD) via public access subsurface area drip dispersal system with a minimum area of 23.05 acres in the Interim I phase, 0.12 MGD via public access subsurface area drip dispersal system with a minimum area of 27.74 acres in the Interim II phase, 0.13 MGD via public access subsurface area drip dispersal system with a minimum area of 30.19 acres in the Interim III phase, and 0.15 MGD via public access subsurface area drip dispersal system with a minimum area of 34.44 acres in the Final phase. The existing wastewater treatment facility serves the Hays County MUD No. 4 district boundaries.

PROJECT DESCRIPTION AND LOCATION

The Hays County MUD No. 4 Wastewater Treatment Facility consists of an single stage nitrification activated sludge process plant. Treatment units in the Interim I phase, Interim II phase, Interim III phase and Final phase include two bar screens, two aeration basins, two final clarifiers, one sludge dwatering box, and two chlorine contact chambers. The applicant has a current storage capacity of 333,000 gallons and is in the procress of designing additional effluent storage capacity to provide a minimum of 450,000 gallons. The permittee is required to provide at least three days of temporary storage for times when the facility is out of service due to an emergency or for scheduled maintenance. The facility is operating in the Interim I phase.

Sludge generated from the treatment facility is hauled by a registered transporter and disposed of at a TCEQ permitted landfill, Austin Wastewater Processing Facility, MSW Permit No. 2384,

in Travis County and J-V Dirt & Loam, MSW Permit No. 2310, in Travis County. The draft permit authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

The wastewater treatment facility and disposal site are located approximately 608 feet north and 2,950 feet west of the intersection of Nutty Brown Road and U.S. Highway 290, in the City of Dripping Springs, Hays County, Texas 78737.

The wastewater treatment facility and disposal site are located in the drainage basin of Barton Creek in Segment No. 1430 of the Colorado River Basin. No discharge of pollutants into water in the State is authorized by this permit.

SUMMARY OF EFFLUENT DATA

The following is a summary of the applicant's effluent monitoring data for the period April 2023 through March 2025. The average of Daily Average value is computed by the averaging of all 30-day average values for the reporting period for each parameter: flow, five-day biochemical oxygen demand (BOD₅), and total suspended solids (TSS).

<u>Parameter</u>	Average of Daily Average
Flow, MGD	0.08
BOD_5 , mg/l	2.2
TSS, mg/l	7.0

DRAFT PERMIT CONDITIONS

The draft permit authorizes the disposal of treated domestic wastewater effluent at a daily average flow not to exceed 0.10 MGD via public access subsurface area drip dispersal system with a minimum area of 23.05 acres in the Interim I phase, 0.12 MGD via public access subsurface area drip dispersal system with a minimum area of 27.74 acres in the Interim II phase, 0.13 MGD via public access subsurface area drip dispersal system with a minimum area of 30.19 acres in the Interim III phase, and 0.15 MGD via public access subsurface area drip disperal system with a minimum area of 34.44 acres in the Final phase. The applicant has current storage capacity of 333,000 gallons and is in the procress of designing additional effluent storage capacity to provide a minimum of 450,000 gallons. The permittee is required to provide at least three days of temporary storage for times when the facility is out of service due to an emergency or for scheduled maintenance. Application rates shall not exceed 0.1 gallons per square foot per day. The permittee will maintain the Bermuda grass overseeded with Rye grass on the disposal site.

The effluent limitations in the draft permit, based on a daily average, are 20 mg/l biochemical oxygen demand (BOD_5), 20 mg/l total suspended solids (TSS), and a single grab limit of 126 colony forming units (CFU) or most probable number (MPN) of *E. coli* per 100 ml. The effluent shall contain a total chlorine residual of at least 1.0 mg/l after a detention time of at least 20 minutes based on peak flow.

The draft permit includes Sludge Provisions according to the requirements of 30 TAC Chapter 312, Sludge Use, Disposal and Transportation. Sludge generated from the treatment facility is hauled by a registered transporter and disposed of at a TCEQ permitted landfill, Austin

Wastewater Processing Facility, MSW Permit No. 2384, in Travis County and J-V Dirt & Loam, MSW Permit No. 2310, in Travis County. The draft permit authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

SUMMARY OF CHANGES FROM APPLICATION

The applicant requested a renewal of the existing permit with changes and the existing permit includes effluent limits of 20 mg/l BOD $_5$, and 20 mg/l TSS, in the Interim phase and Final phases. However, the effluent limits in the draft permit, based on a daily average, are 20 mg/l BOD $_5$, and 20 mg/l TSS; **126 CFU or MPN of** *E. coli* **per 100 ml** based on a single grab. The draft permit includes disinfection requirements where the effluent shall contain a total chlorine residual of at least 1.0 mg/l after a detention time of at least 20 minutes based on peak flow.

SUMMARY OF CHANGES FROM EXISTING PERMIT

The Sludge Provisions, Special Provisions and Standard Provisions have been revised in the draft permit.

SECTION IV, REQUIREMENTS APPLYING TO SLUDGE OR BIOSOLIDS TRANSPORTED TO ANOTHER FACILITY FOR FURTHER PROCESSING, has been added to the Sludge Provisions of the draft permit to allow the transportation of sludge or biosolids to another facility.

Certain accidental discharges or spills of treated or untreated wastewater from wastewater treatment facilities or collection systems owned or operated by a local government may be reported on a monthly basis in accordance with 30 TAC § 305.132.

A single grab E. coli limit of 126 CFU or MPN per 100 ml has been added to the draft permit.

The Interim I phase in the existing permit of 0.075 MGD has been removed from the draft permit.

An Interim II phase of 0.12 MGD and an Interim III phase of 0.13 MGD has been added to the draft permit.

The acreage for the Interim I phase of the draft permit has been updated from the existing permit from 22.96 acres to 23.05 acres.

Special Provisions Nos. 4, 5, 6, 8, 9, 13, and 21 have been updated from the existing permit.

Special Provisions Nos. 25, 26, 27, 28, and 29 have been added to the draft permit.

The applicant has a current storage capacity of 333,000 gallons and is in the procress of designing additional effluent storage capacity to provide a minimum of 450,000 gallons. The permittee is required to provide at least three days of temporary storage for times when the facility is out of service due to an emergency or for scheduled maintenance.

The applicant's mailing address has been updated in the draft permit from c/o Mr. Phil Haag, McGinnis Lochridge & Kilgore LLP, 600 Congress Avenue, Suite 2100, Austin, Texas 78701 to

1715 S. Capital of Texas HWY., Suite 150D, Austin, Texas 78746.

The draft permit includes all updates based on the 30 TAC § 312 rule change effective April 23, 2020.

BASIS FOR DRAFT PERMIT

The following items were considered in developing the draft permit:

- 1. Application submitted with letter dated August 29, 2024 and additional information submitted with letter dated November 15, 2024, July 9, 2025, July 10, 2025, and July 18, 2025.
- 2. Existing TCEQ permit: Permit No. WQ0014309001 issued December 23, 2014.
- 3. Interoffice Memorandum from the Water Quality Assessment Team, Water Quality Assessment & Standards Section, Water Quality Division.

PROCEDURES FOR FINAL DECISION

When an application is declared administratively complete, the Chief Clerk sends a letter to the applicant advising the applicant to publish the Notice of Receipt of Application and Intent to Obtain Permit in the newspaper. In addition, the Chief Clerk instructs the applicant to place a copy of the application in a public place for review and copying in the county where the facility is or will be located. This application will be in a public place throughout the comment period. The Chief Clerk also mails this notice to any interested persons and, if required, to landowners identified in the permit application. This notice informs the public about the application, and provides that an interested person may file comments on the application or request a contested case hearing or a public meeting.

Once a draft permit is completed, it is sent, along with the Executive Director's preliminary decision, as contained in the technical summary or fact sheet, to the Chief Clerk. At that time, Notice of Application and Preliminary Decision will be mailed to the same people and published in the same newspaper as the prior notice. This notice sets a deadline for making public comments. The applicant must place a copy of the Executive Director's preliminary decision and draft permit in the public place with the application.

Any interested person may request a public meeting on the application until the deadline for filing public comments. A public meeting is intended for the taking of public comment, and is not a contested case proceeding.

After the public comment deadline, the Executive Director prepares a response to all significant public comments on the application or the draft permit raised during the public comment period. The Chief Clerk then mails the Executive Director's Response to Comments and Final Decision to people who have filed comments, requested a contested case hearing, or requested to be on the mailing list. This notice provides that if a person is not satisfied with the Executive Director's response and decision, they can request a contested case hearing or file a request to reconsider the Executive Director's decision within 30 days after the notice is mailed.

The Executive Director will issue the permit unless a written hearing request or request for reconsideration is filed within 30 days after the Executive Director's Response to Comments and Final Decision is mailed. If a hearing request or request for reconsideration is filed, the Executive Director will not issue the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting. If a contested case hearing is held, it will be a legal proceeding similar to a civil trial in state district court.

If the Executive Director calls a public meeting or the Commission grants a contested case hearing as described above, the Commission will give notice of the date, time, and place of the meeting or hearing. If a hearing request or request for reconsideration is made, the Commission will consider all public comments in making its decision and shall either adopt the Executive Director's response to public comments or prepare its own response.

Director's response to public comments or prepare its own re	esponse.		
For additional information about this application, contact Garrison Layne at (512) 239-0849.			
Garrison Layne	Date		
Municipal Permits Team			
Wastewater Permitting Section (MC 148)			