

#### This file contains the following documents:

- 1. Summary of application (in plain language)
  - English
  - Alternative Language (Spanish)
- 2. First notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
  - English
  - Alternative Language (Spanish)
- 3. Second notice (NAPD-Notice of Preliminary Decision)
  - English
  - Alternative Language (Spanish)
- 4. Application materials
- 5. Draft permit
- 6. Technical summary or fact sheet



#### Este archivo contiene los siguientes documentos:

- 1. Resumen de la solicitud (en lenguaje sencillo)
  - Inglés
  - Idioma alternativo (español)
- 2. Primer aviso (NORI, Aviso de Recepción de Solicitud e Intención de Obtener un Permiso)
  - Inglés
  - Idioma alternativo (español)
- 3. Segundo aviso (NAPD, Aviso de Decisión Preliminar)
  - Inglés
  - Idioma alternativo (español)
- 4. Materiales de la solicitud
- 5. Proyecto de permiso
- 6. Resumen técnico u hoja de datos



#### TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

# SUMMARY OF APPLICATION IN PLAIN LANGUAGE FOR TPDES OR TLAP PERMIT APPLICATIONS

# Summary of Application (in plain language) Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary of your facility and application as required by Title 30, Texas Administrative Code (30 TAC), Chapter 39, Subchapter H. You may modify the template as necessary to accurately describe your facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how you will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements. After filling in the information for your facility delete these instructions.

If you are subject to the alternative language notice requirements in 30 TAC Section 39.426, you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package. For your convenience, a Spanish template has been provided below.

# ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS INDUSTRIAL WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Energy Transfer GC NGL Fractionators LLC (CN604309419) operates MB Frac VI and VIII (RN109902494), a Energy Transfer GC NGL Fractionators LLC operates an existing Natural Gas processing plant that fractionates Y-grade natural gas liquids into ethane, propane, butane, and natural gasoline. The process uses a low vapor pressure heating medium and cooling is provided using Wet Surface Air Cooling (WSAC) technology. The feedstock and products of the facility are stored in off-site salt dome caverns and transported to and from the facility via pipelines, eliminating the need for on-site feedstock or product storage. The facility is approximately 0.25 miles south of FM 1942 and 0.75 miles east of Cedar Bayou, in Chambers County, Texas. Applicable SIC Code is 1321. The facility discharges through Outfall 001. The facility is located at 8774 FM 1942, in Baytown, Chambers County, Texas 77521. This permit application seeks to remove the WET analysis requirement. We have not failed any WET test since obtaining this permit. If eliminating the WET testing is not possible we request the

frequency of testing be changed to once a year instead of quarterly testing. This permit will not authorize the discharge of pollutants into water in the state.

Discharges from the facility are expected to contain TDS, traces of chloride and traces of TPH. Reverse osmosis reject water, fire system testing, emergency showers, fan cleaning water, non-contact stormwater, air dryer condensate, non-contact cooling water and occasionally hydrostatic test water is treated by using carbon dioxide to control pH and using hydrogen peroxide to control residual chlorine.

# PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

#### AGUAS RESIDUALES INDUSTRIALES /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

Energy Transfer GC NGL Fractionators, LLC (CN604309419) opera MB Frac VI and VIII (RN109602494), una planta de procesamiento de gas natural existente que fracciona líquidos de gas natural de grado Y en etano, propano, butano y gasolina natural. El proceso utiliza un medio de calefacción de baja presión de vapor y el enfriamiento se proporciona utilizando la tecnología de Enfriamiento de Aire de Superficie Húmeda (WSAC). La materia prima y los productos de la instalación se almacenan en cavidades de domo salino fuera del sitio y se transportan hacia y desde la instalación a través de tuberías, eliminando la necesidad de almacenamiento de materia prima o producto en el lugar. La instalación está aproximadamente a 0.25 millas al sur de FM 1942 y a 0.75 millas al este de Cedar Bayou, en el condado de Chambers, Texas. El código SIC aplicable es 1321. La instalación descarga a través de la Salida 001. La instalación está ubicada en 8774 FM 1942, en Baytown, Condado de Chambers, Texas 77521. Esta solicitud de permiso busca eliminar el requisito de análisis WET. No hemos fallado en ninguna prueba WET desde que obtuvimos este permiso. Si no es posible eliminar las pruebas WET, solicitamos que la frecuencia de las pruebas se cambie a una vez al año en lugar de pruebas trimestrales. No se solicitan otros cambios a este permiso. Este permiso no autorizará una descarga de contaminantes en el agua en el estado.

Se espera que las descargas de la instalación contengan TDS, trazas de cloruro y trazas de TPH. Agua de rechazo de ósmosis inversa, pruebas del sistema de incendios, duchas de emergencia, agua de limpieza de ventiladores, aguas pluviales sin contacto, condensado de secadores de aire, agua de enfriamiento sin contacto y ocasionalmente agua de prueba hidrostática está tratado por el uso de dióxido de carbono para controlar el pH y utilizando peróxido de hidrógeno para controlar el cloro residual.

## TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



# NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT AMENDMENT

#### PERMIT NO. WQ0005350000

APPLICATION. Energy Transfer GC NGL Fractionators LLC, 12353 Eagle Pointe Drive, Mont Belvieu, Texas 77535, which owns a natural gas processing plant, has applied to the Texas Commission on Environmental Quality (TCEQ) to amend Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0005350000 (EPA I.D. No. TX0134068) to authorize the removal of the Whole Effluent Toxicity (WET) testing requirement. The facility is located at 8774 Farm-to-Market Road 1942, in Chambers County, Texas 77521. The discharge route is from the plant site to an unnamed tributary; thence to Cedar Bayou Above Tidal. TCEQ received this application on July 31, 2025. The permit application will be available for viewing and copying at Sam and Carmena Goss Memorial Branch Library, 1 John Hall Drive, Mont Belvieu, in Chambers County, Texas prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-94.92944,29.845277&level=18

The application is subject to the goals and policies of the Texas Coastal Management Program and must be consistent with the applicable Coastal Management Program goals and policies.

**ALTERNATIVE LANGUAGE NOTICE.** Alternative language notice in Spanish is available at: <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications</a>. El aviso de idioma alternativo en español está disponible en <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications</a>.

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. Notice of the Application and Preliminary Decision will be published and mailed to those who are on the countywide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. Unless the application is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

**INFORMATION AVAILABLE ONLINE.** For details about the status of the application, visit the Commissioners' Integrated Database at <a href="www.tceq.texas.gov/goto/cid">www.tceq.texas.gov/goto/cid</a>. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at <a href="https://www14.tceq.texas.gov/epic/eComment/">https://www14.tceq.texas.gov/epic/eComment/</a>, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at <a href="www.tceq.texas.gov/goto/pep">www.tceq.texas.gov/goto/pep</a>. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from Energy Transfer GC NGL Fractionators LLC at the address stated above or by calling Ms. Desiree Crenshaw, Environmental Supervisor, at 281-638-4012.

Issuance Date: August 11, 2025

#### Comisión de Calidad Ambiental del Estado de Texas



#### AVISO DE RECIBO DE LA SOLICITUD Y EL INTENTO DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA PERMISO MODIFICACION

#### PERMISO NO. WQ0005350000

SOLICITUD. Energy Transfer GC NGL Fractionators LLC, 12353 Eagle Pointe Drive, Mont Belvieu, Texas 77535, que posee una planta de procesamiento de gas natural, ha solicitado a la Comisión de Calidad Ambiental de Texas (TCEQ) para modificar el Permiso No. WQ0005350000 (EPA I.D. No. TX 0134068) para autorizar la eliminación del requisito de prueba de toxicidad de efluentes totales (WET). La planta está ubicada en el 8774 Farm-to-Market Road 1942 en el Condado de Chambers, Texas 77521. La ruta de descarga es del sitio de la planta a un afluente sin nombre; de allí a Cedar Bayou por encima de la marea. La TCEQ recibió esta solicitud el 31 de julio de 2025. La solicitud para el permiso estará disponible para leerla y copiarla en la biblioteca Sam and Carmena Goss Memorial Branch antes de la fecha de publicación de este aviso en el periódico. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web: <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications</a>. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-94.92944,29.845277&level=18

La solicitud está sujeta a los objetivos y políticas del Programa de Manejo Costero de Texas y debe ser consistente con los objetivos y políticas aplicables del Programa de Manejo Costero.

**AVISO DE IDIOMA ALTERNATIVO.** El aviso de idioma alternativo en español está disponible en <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permitts/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permitts/tpdes-applications</a>.

AVISO ADICIONAL. El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. El aviso de la solicitud y la decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud. El propósito de una reunión pública es dar

la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO. Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión.

La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios.

**LISTA DE CORREO.** Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la

solicitud. Además, puede pedir que la TCEQ ponga su nombre en una o más de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos del solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envía por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

**INFORMACIÓN DISPONIBLE EN LÍNEA.** Para detalles sobre el estado de la solicitud, favor de visitar la Base de Datos Integrada de los Comisionados en <a href="www.tceq.texas.gov/goto/cid">www.tceq.texas.gov/goto/cid</a>. Para buscar en la base de datos, utilizar el número de permiso para esta solicitud que aparece en la parte superior de este aviso.

CONTACTOS E INFORMACIÓN A LA AGENCIA. Todos los comentarios públicos y solicitudes deben ser presentadas electrónicamente vía <a href="http://www14.tceq.texas.gov/epic/eComment/">http://www14.tceq.texas.gov/epic/eComment/</a> o por escrito dirigidos a la Comisión de Texas de Calidad Ambiental, Oficial de la Secretaría (Office of Chief Clerk), MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Para obtener más información acerca de esta solicitud de permiso o el proceso de permisos, llame al programa de educación pública de la TCEQ, gratis, al 1-800-687-4040. Si desea información en español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional de Energy Transfer GC NGL Fractionators LLC a la dirección indicada arriba o llamando a Ms. Desiree Crenshaw, Supervisora Ambiental al 281-638-4012.

Fecha de emisión: 11 de agosto de 2025

#### TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



# NOTICE OF APPLICATION AND PRELIMINARY DECISION FOR TPDES PERMIT FOR INDUSTRIAL WASTEWATER

#### **AMENDMENT**

Permit No. WQ0005350000

**APPLICATION AND PRELIMINARY DECISION.** Energy Transfer GC NGL Fractionators LLC, 12353 Eagle Pointe Drive, Mont Belvieu, Texas 77535, which operates MB Frac VI and VIII, a natural gas processing plant, has applied to the Texas Commission on Environmental Quality (TCEQ) for a major amendment of Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0005350000 to authorize the removal of the Whole Effluent Toxicity (WET) testing requirements. The draft permit authorizes the discharge of water treatment wastes, surface air cooler blowdown, utility wastewater, hydostatic test water, and stormwater at a daily average dry weather flow not to exceed 936,000 gallons per day via Outfall 001. The TCEQ received this application on July 31, 2025.

The facility is located at 8774 Farm-to-Market Road 1942, near the City of Mont Belvieu, Chambers County, Texas 77521. This link to an electronic map of the site or facility's general location is provided as a public courtesy and is not part of the application or notice. For the exact location, refer to the application.

https://gisweb.tceg.texas.gov/LocationMapper/?marker=-94.92944,29.845277&level=18

The effluent is discharged to an unnamed tributary, thence to Cedar Bayou Above Tidal in Segment No. 0902 of the Trinity-San Jacinto Coastal Basin. The unclassified receiving water use is minimal aquatic life use for the unnamed tributary. The designated uses for Segment No. 0902 are primary contact recreation and high aquatic life use.

In accordance with Title 30 Texas Administrative Code Section 307.5 and TCEQ's *Procedures to Implement the Texas Surface Water Quality Standards* (June 2010), an antidegradation review of the receiving waters was performed. A Tier 1 antidegradation review has preliminarily determined that existing water quality uses will not be impaired by this permit action. Numerical and narrative criteria to protect existing uses will be maintained. A Tier 2 review has preliminarily determined that no significant degradation of water quality is expected in Cedar Bayou Above Tidal, which has been identified as having high aquatic life use. Existing uses will be maintained and protected. The preliminary determination can be reexamined and may be modified if new information is received.

The TCEQ Executive Director reviewed this action for consistency with the Texas Coastal Management Program (CMP) goals and policies in accordance with the regulations of the General Land Office and has determined that the action is consistent with the applicable CMP goals and policies.

The TCEQ Executive Director has completed the technical review of the application and prepared a draft permit. The draft permit, if approved, would establish the conditions under which the facility must operate. The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The permit application, Executive Director's preliminary decision, and draft permit are available for viewing and copying at Sam and Carmena Goss Memorial Branch Library, 1 John Hall Drive, Mont Belvieu, in Chambers County, Texas. The application, including any updates, and associated notices are available electronically at the following webpage:

https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications

**ALTERNATIVE LANGUAGE NOTICE.** Alternative language notice in Spanish is available at https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications. El aviso de idioma alternativo en español está disponible en https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications.

**PUBLIC COMMENT / PUBLIC MEETING.** You may submit public comments or request a public meeting about this application. The purpose of a public meeting is to provide the opportunity to submit written or oral comment or to ask questions about the application. Generally, the TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for public comments, the Executive Director will consider the comments and prepare a response to all relevant and material, or significant public comments. The response to comments, along with the Executive Director's decision on the application, will be mailed to everyone who submitted public comments or who requested to be on a mailing list for this application. If comments are received, the mailing will also provide instructions for requesting a contested case hearing or reconsideration of the Executive Director's decision. A contested case hearing is a legal proceeding similar to a civil trial in a state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period; and the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.

**EXECUTIVE DIRECTOR ACTION.** The Executive Director may issue final approval of the application unless a timely contested case hearing request or a timely request for reconsideration is filed. If a timely hearing request or request for reconsideration is filed, the Executive Director will not issue final approval of the permit and will forward the application and requests to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

**MAILING LIST.** If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be added to: (1) the permanent list for a specific applicant name and permit number; and (2) the mailing list for a specific county. If you wish to be placed on the permanent and the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

All written public comments and public meeting requests must be submitted to the Office of the Chief Clerk, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 or electronically at <a href="https://www.tceq.texas.gov/goto/comment">https://www.tceq.texas.gov/goto/comment</a> within 30 days from the date of newspaper publication of this notice.

**INFORMATION AVAILABLE ONLINE.** For details about the status of the application, visit the Commissioners' Integrated Database at <a href="https://www.tceq.texas.gov/goto/cid/">https://www.tceq.texas.gov/goto/cid/</a>. Search the database using the permit number for this application, which is provided at the top of this notice.

**AGENCY CONTACTS AND INFORMATION.** Public comments and requests must be submitted either electronically at <a href="https://www.tceq.texas.gov/goto/comment">https://www.tceq.texas.gov/goto/comment</a>, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address, and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, toll free, at 1-800-687-4040 or visit their website at <a href="https://www.tceq.texas.gov/agency/decisions/participation/permitting-participation">https://www.tceq.texas.gov/agency/decisions/participation/permitting-participation</a>. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from Energy Transfer GC NGL Fractionators LLC at the address stated above or by calling Ms. Desiree Crenshaw, Environmental Sipervisor, at 281-638-4012.

Issued: November 12, 2025

#### Comisión De Calidad Ambiental Del Estado De Texas



#### AVISO DE LA SOLICITUD Y DECISIÓN PRELIMINAR PARA EL PERMISO DEL SISTEMA DE ELIMINACION DE DESCARGAS DE CONTAMINANTES DE TEXAS (TPDES) PARA AGUAS RESIDUALES MUNICIPALES

#### RENOVACIÓN

#### PERMISO NO. WQooo5350000

**SOLICITUD Y DECISIÓN PRELIMINAR.** Energy Transfer GC NGL Fractionators LLC ha solicitado a la Comisión de Calidad Ambiental del Estado de Texas (TCEQ) una renovación para autorizar Fractionator VI & VII. La TCEQ recibió esta solicitud el 31 de julio de 2025.

La solicitud también incluye un pedido para una exención provisional de las normas existentes de la calidad del agua para el. La exención autorizaría un período de tres años durante el cual se realizaría un estudio de la calidad del agua de a la cual es descargada las aguas tratadas residuales domésticas. El estudio mostraría si se justifica una modificación específica del sitio a la norma de la calidad del agua. Antes de la expiración del periodo de exención de tres años, la TCEQ considerará las normas específicas del sitio y determinará si tiene que adoptar las normas o mantener en efecto las normas existentes de calidad del agua.

El solicitante también ha solicitado a la TCEQ la aprobación de modificaciones significativos al programa de pretratamiento bajo el programa TPDES. La aprobación al pedido de modificación al programa de pretratamiento permitirá al solicitante revisar los límites locales técnicamente basados y continuar la regulación de las descargas de contaminantes por usuarios industriales en las plantas de tratamiento, para realizar inspecciones, vigilancias y monitorea para determinar el cumplimiento con las normas y los requisitos pertinentes de pretratamiento y para aplicar la ley a las medidas contra los usuarios industriales incumplidores. El pedido de aprobación cumple con los requisitos estatales y federales. La modificación principal será aprobada sin cambio si no se reciben comentarios significativos dentro de treinta (30) días del aviso de publicación o al fin del periodo para comentarios del público si una reunión pública es realizada.

La planta está ubicada en 8774 FM 1942 en el Condado de Chambers, Texas. El efluente tratado es descargado al Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

https://gisweb.tceq.texas.gov/LocationMapper/?marker=-94.92944,29.845277&level=18

El efluente tratado es descargado al Cedar Bayou above tidal en el Segmento No. 0902 de la Cuenca del Río Trinity-San Jacinto Basin. Los usos no clasificados de las aguas receptoras son usos de la vida acuática para Minimal. Los usos designados para el Segmento No. 0902 son no significativos, limitados, intermedios, elevados, o uso excepcional de vida acuática; abastecimiento de agua potable, provisión de agua a la industria, agua para ostras, navegación y recreación sin contacto.

El Director Ejecutivo de la TCEQ ha revisado esta medida para ver si está de acuerdo con los objetivos y las regulaciones del Programa de Administración Costero de Texas (CMP) de acuerdo con las regulaciones del Consejo Coordinador de la Costa (CCC) y ha determinado que la acción es conforme con las metas y regulaciones pertinentes de el CMP.

El Director Ejecutivo de la TCEQ ha completado la revisión técnica de la solicitud y ha preparado un borrador del permiso. El borrador del permiso, si es aprobado, establecería las condiciones bajo las cuales la instalación debe operar. El Director Ejecutivo ha tomado una decisión preliminar que si este permiso es emitido, cumple con todos los requisitos normativos y legales. La solicitud del permiso, la decisión preliminar del Director Ejecutivo y el borrador del permiso están disponibles para leer y copiar en 1 John Hall Dr, Mont BElvieu, Tx 77580. La solicitud está disponible para su consulta y reproducción a través del siguiente enlace: <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications</a>

**AVISO DE IDIOMA ALTERNATIVO.** El aviso de idioma alternativo en español está disponible en <a href="https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications">https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications</a>.

COMENTARIO PUBLICO / REUNION PUBLICA. La TCEQ ha realizado una reunión pública a las y en. Usted puede presentar comentarios públicos adicionales o pedir una reunión pública sobre esta solicitud. Usted puede presentar comentarios públicos o pedir una reunión pública sobre esta solicitud.

El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

#### OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO

CONTENCIOSO. Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso. Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso para descargar aguas residuales sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

**ACCIÓN DEL DIRECTOR EJECUTIVO.** El Director Ejecutivo puede emitir una aprobación final de la solicitud a menos que exista un pedido antes del plazo de vencimiento de una audiencia administrativa de lo contencioso o se ha presentado un pedido de reconsideración. Si un pedido ha llegado antes del plazo de vencimiento de la audiencia o el pedido de reconsideración ha sido presentado, el Director Ejecutivo no emitirá una aprobación final sobre el permiso y enviará la solicitud y el pedido a los Comisionados de la TECQ para consideración en una reunión programada de la Comisión.

**LISTA DE CORREO.** Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Ademas, puede pedir que la TCEQ ponga su nombre en una or mas de las listas correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agrega su nombre en una de las listas designe cual lista(s) y envia por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

Todos los comentarios escritos del público y los pedidos una reunión deben ser presentados durante los 30 días después de la publicación del aviso a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 or por el internet a <a href="https://www.tceq.texas.gov/goto/comment">https://www.tceq.texas.gov/goto/comment</a>. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia.

**INFORMACIÓN DISPONIBLE EN LÍNEA.** Para obtener detalles sobre el estado de la solicitud, visite la Base de Datos Integrada de los Comisionados en <a href="https://www.tceq.texas.gov/goto/cid/">https://www.tceq.texas.gov/goto/cid/</a>. Busque en la base de datos utilizando el número de permiso para esta solicitud, que se proporciona en la parte superior de este aviso.

**CONTACTOS E INFORMACIÓN DE LA AGENCIA.** Los comentarios y solicitudes públicas deben enviarse electrónicamente a <a href="https://www.tceq.texas.gov/goto/comment">https://www.tceq.texas.gov/goto/comment</a>, o por escrito a Texas Commission on Environmental Quality, Office of the Chief Clerk, MC105, P.O. Box 13087, Austin, Texas 78711-3087. Cualquier información personal que envíe a al TCEQ pasará a formar parte del registro de la agencia; esto incluye las direcciones de correo electrónico. Para obtener más información sobre esta solicitud de permiso o el proceso de permisos, llame al Programa de Educación Pública de la TCEQ, sin cargo, al 1-800-687-4040 o visite su sitio web en <a href="https://www.tceq.texas.gov/agency/decisions/participation/permitting-participation">https://www.tceq.texas.gov/agency/decisions/participation/permitting-participation</a>. Si desea

información en español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional del Energy Transfer GC NGL Fractionators LLC a la dirección indicada arriba o llamando a Desiree Crenshaw al 281-576-3617.

Fecha de emisión 12 de noviembre de 2025

Brooke T. Paup, *Chairwoman*Bobby Janecka, *Commissioner*Catarina R. Gonzales, *Commissioner*Kelly Keel, *Executive Director* 



# TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

July 31, 2025

Re: Confirmation of Submission of the Major Amendment with Renewal for Industrial Wastewater Authorization.

Dear Applicant:

This is an acknowledgement that you have successfully completed Major Amendment with Renewal for the Industrial Wastewater authorization.

ER Account Number: ER090112

Application Reference Number: 794864 Authorization Number: WQ0005350000

Site Name: Mb Frac Vi And Viii

Regulated Entity: RN109902494 - Mb Frac Vi And Viii

Customer(s): CN604309419 - Energy Transfer Gc Ngl Fractionators LLC

Please be aware that TCEQ staff may contact your designated contact for any additional information.

If you have any questions, you may contact the Applications Review and Processing Team by email at WQ-ARPTeam@tceq.texas.gov or by telephone at (512) 239-4671.

Sincerely, Applications Review and Processing Team Water Quality Division

#### **Texas Commission on Environmental Quality**

Update Domestic or Industrial Individual Permit WQ0005350000

#### Site Information (Regulated Entity)

What is the name of the site to be authorized?

MB FRAC VI AND VIII

Does the site have a physical address?

Because there is no physical address, describe how to locate this site: 8774 FM 1942 MONT BELVIEU TX 77521

City MONT BELVIEU

State TX

ZIP 77521

County CHAMBERS

Latitude (N) (##.#####) 29.845277

Longitude (W) (-###.#####) -94.929444

Primary SIC Code

Secondary SIC Code

Primary NAICS Code

Secondary NAICS Code

**Regulated Entity Site Information** 

What is the Regulated Entity's Number (RN)? RN109902494

What is the name of the Regulated Entity (RE)?

MB FRAC VI AND VIII

Does the RE site have a physical address?

**Physical Address** 

Number and Street 8774 FM 1942

City BAYTOWN

State TX

ZIP 77521

County CHAMBERS

Latitude (N) (##.#####) 29.845277

Longitude (W) (-###.#####) -94.929444

Facility NAICS Code

What is the primary business of this entity? FRACTIONATION OF NATURAL GAS LIQUIDS

Energy -Customer (Applicant) Information (Owner Operator)

How is this applicant associated with this site? Owner Operator CN604309419 What is the applicant's Customer Number (CN)? Type of Customer Corporation Full legal name of the applicant: Energy Transfer GC NGL Fractionators LLC Legal Name Texas SOS Filing Number 801444322 Federal Tax ID State Franchise Tax ID 32044534058 State Sales Tax ID Local Tax ID **DUNS Number** 795483853 Number of Employees 101-250 Independently Owned and Operated? Yes I certify that the full legal name of the entity applying for this permit has been provided and is Yes legally authorized to do business in Texas. **Responsible Authority Contact** Organization Name Energy Transfer GC NGL Fractionators LLC Prefix MR First Brad Middle Last Widener Suffix Credentials Title Vice President of Operations **Responsible Authority Mailing Address** Enter new address or copy one from list: Address Type Domestic Mailing Address (include Suite or Bldg. here, if applicable) 12353 EAGLE POINTE DR Routing (such as Mail Code, Dept., or Attn:) City MONT BELVIEU State TX ZIP 77535 Phone (###-###-####) 2813853571 Extension Alternate Phone (###-###-) Fax (###-###-###)

brad.widener@energytransfer.com

E-mail

#### **Billing Contact**

Responsible contact for receiving billing statements:

Select the permittee that is responsible for payment of the annual fee. CN604309419, Energy Transfer GC NGL

Fractionators LLC

Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

Prefix MS

First DESIREE

Middle

Last CRENSHAW

Suffix Credentials

Crodornalo

Title ENVIRONMENTAL SUPERVISOR

Enter new address or copy one from list:

**Mailing Address** 

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable)

12353 EAGLE POINTE DR

Routing (such as Mail Code, Dept., or Attn:)

City MONT BELVIEU

State TX

ZIP 77535

Phone (###-####) 2816384012

Extension

Alternate Phone (###-###-###)

Fax (###-####)

E-mail wylene.crenshaw@ENERGYTRANSFER.COM

#### **Application Contact**

#### Person TCEQ should contact for questions about this application:

Same as another contact?

Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

Prefix MS

First DESIREE

Middle

Last CRENSHAW

Suffix

Credentials

Title ENVIRONMENTAL SUPERVISOR

Enter new address or copy one from list:

**Mailing Address** 

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable)

12353 EAGLE POINTE DR

Routing (such as Mail Code, Dept., or Attn:)

City MONT BELVIEU

State TX

ZIP 77535

Phone (###-####) 2816384012

Extension

Alternate Phone (###-###-###)

Fax (###-###-####)

E-mail WYLENE.CRENSHAW@ENERGYTRANSFER.COM

#### **Technical Contact**

#### Person TCEQ should contact for questions about this application:

Same as another contact?

Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

Prefix MS

First CYNTHIA

Middle M

Last SEXTON

Suffix

Credentials

Title ASSOCIATE-ENVIRONMENTAL SPECIALIST

Enter new address or copy one from list:

**Mailing Address** 

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable)

12353 EAGLE POINTE DR

Routing (such as Mail Code, Dept., or Attn:)

City MONT BELVIEU

State TX

ZIP 77535

Phone (###-####) 2815763616

Extension

Alternate Phone (###-###-###)

Fax (###-####)

E-mail CYNTHIA.SEXTON@ENERGYTRANSFER.COM

#### **DMR Contact**

Person responsible for submitting Discharge Monitoring Report Forms:

Same as another contact?

Billing Contact

Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

Prefix MS

First DESIREE

Middle

Last CRENSHAW

Suffix

Credentials

Title ENVIRONMENTAL SUPERVISOR

Enter new address or copy one from list:

Mailing Address:

Address Type Domestic

Mailing Address (include Suite or Bldg. here, if applicable)

12353 EAGLE POINTE DR

Routing (such as Mail Code, Dept., or Attn:)

City MONT BELVIEU

State TX

ZIP 77535

Phone (###-####) 2816384012

Extension

Alternate Phone (###-###-###)

Fax (###-###-####)

E-mail wylene.crenshaw@ENERGYTRANSFER.COM

Section 1# Permit Contact

#### Permit Contact#: 1

Person TCEQ should contact throughout the permit term.

1) Same as another contact?

DMR Contact

2) Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

3) Prefix MS

4) First DESIREE

5) Middle

6) Last CRENSHAW

7) Suffix

8) Credentials

9) Title ENVIRONMENTAL SUPERVISOR

**Mailing Address** 

10) Enter new address or copy one from list

11) Address Type Domestic

11.1) Mailing Address (include Suite or Bldg. here, if applicable) 12353 EAGLE POINTE DR

11.2) Routing (such as Mail Code, Dept., or Attn:)

11.3) City MONT BELVIEU

11.4) State TX

11.5) ZIP 77535

12) Phone (###-###-###) 2816384012

13) Extension

14) Alternate Phone (###-###-####)

15) Fax (###-###-###)

16) E-mail WYLENE.CRENSHAW@ENERGYTRANSFER.COM

#### Section 2# Permit Contact

#### Permit Contact#: 2

 $\label{personTCEQ} \textbf{Person TCEQ should contact throughout the permit term.}$ 

1) Same as another contact?

Technical Contact

2) Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

3) Prefix MS

4) First CYNTHIA

5) Middle M

6) Last SEXTON

7) Suffix

8) Credentials

9) Title ASSOCIATE-ENVIRONMENTAL SPECIALIST

**Mailing Address** 

10) Enter new address or copy one from list

11) Address Type Domestic

11.1) Mailing Address (include Suite or Bldg. here, if applicable) 12353 EAGLE POINTE DR

11.2) Routing (such as Mail Code, Dept., or Attn:)

11.3) City MONT BELVIEU

11.4) State TX

11.5) ZIP 77535

12) Phone (###-###-###) 2815763616

13) Extension

14) Alternate Phone (###-###-####)

15) Fax (###-###-###)

16) E-mail CYNTHIA.SEXTON@ENERGYTRANSFER.COM

#### **Owner Information**

#### **Owner of Treatment Facility**

1) Prefix

2) First and Last Name BRAD WIDENER

3) Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

TX

Mont Belvieu

4) Mailing Address 12353 Eagle Pointe Drive

5) City

6) State

7) Zip Code 77535

8) Phone (###-####) 2813853571

9) Extension

10) Email brad.widener@energytransfer.com

11) What is ownership of the treatment facility?

Owner of Land (where treatment facility is or will be)

12) Prefix

13) First and Last Name BRAD WIDENER

14) Organization Name ENERGY TRANSFER GC NGL FRACTIONATORS

LLC

15) Mailing Address 12353 Eagle Pointe Drive 16) City Mont Belvieu 17) State TX 18) Zip Code 77535 19) Phone (###-###-###) 2813853571 20) Extension 21) Email brad.widener@energytransfer.com 22) Is the landowner the same person as the facility owner or co-applicant? Yes General Information Renewal-Amendment 01/30/2026 1) Current authorization expiration date: 2) Current Facility operational status: Active 3) Is the facility located on or does the treated effluent cross American Indian Land? No 4) What is the application type that you are seeking? Major Amendment with Renewal 4.1) Describe the proposed changes: This permit application amendment seeks to remove the WET analysis requirement. We have not failed any WET test since obtaining this permit. WET tests have been carried out from EPA NPDES original permit, but Fracs VI/VIII has been complying with them and understand that they are not necessary due to the type of operation at the site. 5) Current Authorization type: Industrial Wastewater 5.1) What is your EPA facility classification? Minor 5.1.1) Are the discharges at your facility subjected to federal effluent limitation guidelines (ELG) No 40 CFR Part 400-471? 5.1.1.1) Select the applicable fee for the Minor facility that is not subjected to 40 CFR 400-471: Major Amendment - \$350 6) What is the classification for your authorization? **TPDES** 6.1) What is the EPA Identification Number? TX0134068 Yes 6.2) Is the wastewater treatment facility location in the existing permit accurate? 6.3) Are the point(s) of discharge and the discharge route(s) in the existing permit correct? Yes 6.4) City nearest the outfall(s): Mont Belvieu 6.5) County where the outfalls are located: **CHAMBERS** 6.6) Is or will the treated wastewater discharge to a city, county, or state highway right-of-way, or No a flood control district drainage ditch? 6.7) Is the daily average discharge at your facility of 5 MGD or more? No

Nο

7) Did any person formerly employed by the TCEQ represent your company and get paid for

service regarding this application?

### Public Notice Information

Individual Publishing the Notices	
1) Prefix	MS
2) First and Last Name	CYNTHIA M SEXTON
3) Credential	
4) Title	ASSOCIATE-ENVIRONMENTAL SPECIALIST
5) Organization Name	ENERGY TRANSFER GC NGL FRACTIONATORS LLC
6) Mailing Address	12353 EAGLE POINTE DR
7) Address Line 2	
8) City	MONT BELVIEU
9) State	TX
10) Zip Code	77535
11) Phone (###-###-)	2815763616
12) Extension	
13) Fax (###-###-###)	
14) Email	cynthia.sexton@energytransfer.com
Contact person to be listed in the Notices	
15) Prefix	MS
16) First and Last Name	DESIREE CRENSHAW
17) Credential	
18) Title	Environmental Supervisor
19) Organization Name	ENERGY TRANSFER GC NGL FRACTIONATORS LLC
20) Phone (###-###)	2816384012
21) Fax (###-####)	
22) Email	WYLENE.CRENSHAW@ENERGYTRANSFER.COM
Bilingual Notice Requirements	
23) Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?	Yes
23.1) Are the students who attend either the elementary school or the middle school enrolled in a bilingual education program at that school?	No
23.2) Do the students at these schools attend a bilingual education program at another location?	No
23.3) Would the school be required to provide a bilingual education program but the school has waived out of this requirement under 19 TAC 89.1205(g)?	No
23.4) Which language is required by the bilingual program?	Spanish

#### Section 1# Public Viewing Information

#### County#: 1

1) County CHAMBERS

2) Public building name SAM AND CARMENA GOSS MEMORIAL BRANCH

LIBRARY

MONT BELVIEU

3) Location within the building

4) Physical Address of Building 1 JOHN HALL DR.

5) City

6) Contact Name YOLIE BELT
7) Phone (###-####) 2815762245

8) Extension

9) Is the location open to the public?

#### Plain Language

1) Plain Language

[File Properties]

File Name

LANG\_Attachment No. 2 - Plain Language Summary.docx

Hash 1514D7EDD10E82F6680162611162E944467BFBC351F1D39DFA89D1C06A76DB79

MIME-Type application/vnd.openxmlformats-

officedocument.wordprocessingml.document

#### Supplemental Permit Information Form

1) Supplemental Permit Information Form (SPIF)

[File Properties]

File Name SPIF\_Attachment 8 - Suplemental Permit Information Form.docx

Hash F6830A9A31F22C6BD5FB33B6668CC3F094B57725F1ADE9E2459BB1A5DEA54BF4

MIME-Type application/vnd.openxmlformats-

officedocument.wordprocessingml.document

#### **Industrial Attachments**

1) Attach an 8.5"x11", reproduced portion of the most current and original USGS Topographic Quadrangle Map(s) that meets the 1:24,000 scale.

[File Properties]

File Name MAP Attachment No. 4 - USGS Map.pdf 80638D02287D09A5084796C7D3E71A0FA2AF8850B8303A6A167DCA872C3AC035 Hash MIME-Type application/pdf 2) Public Involvement Plan (TCEQ Form 20960) [File Properties] File Name PIP\_Attachment 3 - PIP Form.draft.pdf Hash 451CFCE5779F73EBB9B1FD6C6BAEC61374F0AA4AFE4AA98EAB761319EB28A8A7 MIME-Type application/pdf 3) Administrative Report 1.1 [File Properties] File Name ARPT Administrative Report 1.1 Draft\_.pdf Hash 7E0BF56629A279D8A9B065A5C3CC073925640BEF565634F66F1DCE244EBC8914 MIME-Type application/pdf 4) I confirm that all required sections of Technical Report 1.0 are complete and will be included in Yes the Technical Attachment. 4.1) I confirm that Worksheet 2.0 (Pollutant Analyses Requirements) is complete and included in Yes the Technical Attachment. 4.2) I confirm that Worksheet 4.0 (Receiving Waters) is complete and included in the Technical Yes Attachment. 4.3) Are you planning to include Worksheet 4.1 (Waterbody Physical Characteristics) in the No Technical Attachment? 4.4) Are you planning to include Worksheet 6.0 (Industrial Waste Contribution) in the Technical No Attachment? 4.5) Are you planning to include Worksheet 7.0 (Stormwater Discharges Associated with Yes Industrial Activities) to the Technical Attachment? 4.6) Are you planning to include Worksheet 8.0 (Aquaculture) in the Technical Attachment? No 4.7) Are you planning to include Worksheet 9.0 (Class V Injection Well Inventory/Authorization) No in the Technical Attachment? 4.8) Are you planning to include Worksheet 10.0 (Quarries in the John Graves Scenic Riverway) No in the Technical Attachment? 4.9) Are you planning to include Worksheet 11.0 (Cooling Water System Information) in the No Technical Attachment? 4.10) Are you planning to include Worksheet 11.1 (Impingement Mortality) in the Technical No Attachment? 4.11) Are you planning to include Worksheet 11.2 (Source Water Biological Data) in the No Technical Attachment? 4.12) Are you planning to include Worksheet 11.3 (Entrainment) in the Technical Attachment? Nο 4.13) Technical Attachment

[File Properties] File Name TECH\_Tech Report 1.0\_Rev 1 Steers.pdf BE5C6577AE855D63CF9BD8E1D6D52815A7777A9D80648994057657FDB18B7F0E Hash MIME-Type application/pdf 5) Affected Landowners Map [File Properties] File Name LANDMP Attachment No. 5 - Adjacent Landowners.pdf C87F6219F603386B5E6E72395327B6FD7E78A4BD9C4C0AFE5FA97A374FE3FB03 Hash MIME-Type application/pdf 6) Landowners Cross Reference List [File Properties] File Name LANDCRL Attachment AR-6 - Adjacent Landowners List.pdf Hash D62A8F7ACAEC32A066A301F8F072482B6DF308C2798451202303942BEEE5DD4F MIME-Type application/pdf 7) Landowner Avery Template [File Properties] File Name LANDAT Attachment No. 6 - Adjacent Landowners Labels.docx Hash 11B2F4257CE2880DA49E129E369D94D9432378AC936611752B201B071700E098 MIME-Type application/vnd.openxmlformatsofficedocument.wordprocessingml.document 8) Flow Diagram [File Properties] File Name FLDIA Attachment TR-3 - Water Balance Flow Diagram Revised.pdf Hash 578385AEE337DC49AB41BF821A5D297191A933091CA4138781E642D042A0D02E MIME-Type application/pdf 9) Site Drawing [File Properties] File Name SITEDR Attachment TR-1 - Facility Map.pdf 4849C0A030475B974522F972CE547670DC64A516FDF9054DFFE3964A5F7A3C22 Hash MIME-Type application/pdf

10) Original Photographs

[File Properties]

File Name ORIGPH\_Attachment No. 7 - Original Photographs.pdf

Hash 74262BF9D3D1BD026A2F7CAB88C787D2BB62DA9648B34A30137B8BC1A03A4327

MIME-Type application/pdf

11) Design Calculations

[File Properties]

File Name DES\_CAL\_No calculations.pdf

Hash 73B6F4B08431AC63971576FE9EE59D3B5C71B045F627B6521AD2B66D639945F4

MIME-Type application/pdf

12) Solids Management Plan

13) Water Balance

[File Properties]

File Name

WB\_Attachment TR-3 - Water Balance Flow Diagram Revised.pdf

Hash 578385AEE337DC49AB41BF821A5D297191A933091CA4138781E642D042A0D02E

MIME-Type application/pdf

14) Other Attachments

[File Properties]

File Name OTHER Attachment TR-4 - List of Water Treatment Chemicals.pdf

Hash FA6149E70095664D29EFC30D2BF89F10611681AE3BA917657C5DBEE4837251A9

MIME-Type application/pdf

[File Properties]

File Name OTHER Attachment AR-7 - photo log map.pdf

Hash E066CD64737D57F3E0F5BAAA7462BD7E335B6AB9B02BAEEE745491B4323A6DD0

MIME-Type application/pdf

[File Properties]

File Name OTHER\_Attachment AR-8 - SPIF\_USGS\_map\_.pdf

Hash 45DC6AE32D8FDD3A551D17594DFFEE2244D70B4F864361AF881236AA6740462F

MIME-Type application/pdf

#### Certification

I certify that I am authorized under 30 Texas Administrative Code 305.44 to sign this document and can provide documentation in proof of such authorization upon request.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

- 1. I am Brad Widener, the owner of the STEERS account ER050998.
- 2. I have the authority to sign this data on behalf of the applicant named above.
- 3. I have personally examined the foregoing and am familiar with its content and the content of any attachments, and based upon my personal knowledge and/or inquiry of any individual responsible for information contained herein, that this information is true, accurate, and complete.
- 4. I further certify that I have not violated any term in my TCEQ STEERS participation agreement and that I have no reason to believe that the confidentiality or use of my password has been compromised at any time.
- 5. I understand that use of my password constitutes an electronic signature legally equivalent to my written signature.
- 6. I also understand that the attestations of fact contained herein pertain to the implementation, oversight and enforcement of a state and/or federal environmental program and must be true and complete to the best of my knowledge.
- 7. I am aware that criminal penalties may be imposed for statements or omissions that I know or have reason to believe are untrue or misleading.
- 8. I am knowingly and intentionally signing Update Domestic or Industrial Individual Permit WQ0005350000.
- 9. My signature indicates that I am in agreement with the information on this form, and authorize its submittal to the TCEQ.

OWNER OPERATOR Signature: Brad Widener OWNER OPERATOR

Customer Number: CN604309419

Legal Name: Energy Transfer GC NGL Fractionators LLC

Account Number: ER050998
Signature IP Address: 63.105.50.19
Signature Date: 2025-07-31

Signature Hash: F70E5BA2D6AA73672309049F7B6CCEBD46951A9669729BEE355B1BDAD6DF0209

Form Hash Code at time of Signature: 63DAD8C4A06CF8A40F177964050BB656D94AA88AE70CE015F4558870C1311CE7

#### Fee Payment

Transaction by:

The application fee payment transaction was made by

ER090112/Hope B Davila

Paid by:

The application fee was paid by CYNTHIA SEXTON

Fee Amount: \$300.00

Paid Date: The application fee was paid on 2025-07-31

Transaction/Voucher number: The transaction number is 582EA000678931 and the voucher

number is 777440

#### Submission

Reference Number: The application reference number is 794864

Submitted by:

The application was submitted by ER090112/Hope B Davila

Submitted Timestamp: The application was submitted on 2025-07-31 at 13:46:55 CDT

Submitted From: The application was submitted from IP address 63.105.50.19

Confirmation Number:	The confirmation number is 668312
Steers Version:	The STEERS version is 6.92
Permit Number:	The permit number is WQ0005350000

# Additional Information

Application Creator: This account was created by Edwin C Centeno

### INDUSTRIAL WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.1

The following information is required for new and amendment applications.

#### Item 1. Affected Landowner Information (Instructions, Page 35)

- a. Attach a landowner map or drawing, with scale, as applicable. Check the box next to each item to confirm it has been provided. ☑ The applicant's property boundaries. ☐ The facility site boundaries within the applicant's property boundaries. ☐ The distance the buffer zone falls into adjacent properties and the property boundaries of the landowners located within the buffer zone. ☑ The property boundaries of all landowners surrounding the applicant's property. (Note: if the application is a major amendment for a lignite mine, the map must include the property boundaries of all landowners adjacent to the new facility (ponds).) ☑ The point(s) of discharge and highlighted discharge route(s) clearly shown for one mile downstream. ☑ The property boundaries of the landowners located on both sides of the discharge route for one full stream mile downstream of the point of discharge. ☐ The property boundaries of the landowners along the watercourse for a one-half mile radius from the point of discharge if the point of discharge is into a lake, bay, estuary, or affected by tides. ☐ The boundaries of the effluent disposal site (e.g., irrigation area or subsurface drainfield site) and all evaporation/holding ponds within the applicant's property. ☐ The property boundaries of all landowners surrounding the applicant's property boundaries where the effluent disposal site is located. ☐ The boundaries of the sludge land application site (for land application of sewage sludge for beneficial use) and the property boundaries of landowners within onequarter mile of the applicant's property boundaries where the sewage sludge land application site is located. ☐ The property boundaries of landowners within one-half mile in all directions from the applicant's property boundaries where the sewage sludge disposal site (e.g., sludge surface disposal site or sludge monofil) is located. Attachment: AR-5
- b.  $\boxtimes$  that the landowners list has also been provided as mailing labels in electronic format (Avery 5160).
- c. Check this box to confirm a separate list with the landowners' names and mailing addresses cross-referenced to the landowner's map has been provided. Provide the source of the landowners' names and mailing addresses: <a href="https://doi.org/10.1007/journal.com/">Attachment AR-6</a>

e. As required by Texas Water Code § 5.115, is any permanent school fund land affected by this application?

□ Yes ⊠ No

If yes, provide the location and foreseeable impacts and effects this application has on the land(s): Click to enter text.

#### Item 2. Original Photographs (Instructions, Page 37)

Provide original ground level photographs. Check the box next to each of the following items to indicate it is included.

- ☐ At least one original photograph of the new or expanded treatment unit location.
- At least two photographs of the existing/proposed point of discharge and as much area downstream (photo 1) and upstream (photo 2) as can be captured. If the discharge is to an open water body (e.g., lake, bay), the point of discharge should be in the right or left edge of each photograph showing the open water and with as much area on each respective side of the discharge as can be captured.
- ☐ At least one photograph of the existing/proposed effluent disposal site.
- 🛮 A plot plan or map showing the location and direction of each photograph.

Attachment: AR-7

# INDUSTRIAL WASTEWATER PERMIT APPLICATION SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: AR-8

# Attachment No. 10

# List of chemicals and SDSs

Manufacturers Product ID	Product Use	CASRN/Chemical Composition		CASRN/Chemical Composition		duct Use CASRN/Chemical Composition		Product Use CASRN/Chemical Composition		Product Classification	Active Ingredient half- life	Frequency of product use	Product Toxicity Data	Concentration in Waste stream
AC-455	Corrosion Inhibitor	7681-57-4	sodium metabisulphite	<20%	Non-persistent	Not Available	Continuously	No relevant information available	Very low					
AC-777	Membrane anti-scalent inhibitor	20592-85-2	Phosphonic acid,P,P',P"- [nitrilotris(methylene)]tris-, sodium salt	10-20%	Non-persistent	Not Available	Continuously	No relevant information available	Very low					
		1310-58-3	Potassium hydroxide	<2%										
CL427	Dechlorinator	7722-84-1	Hydrogen Peroxide	10-30%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
CL456	Corrosion Inhibitor	Trade secret			Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
CI 2020	NATA A International Alabata	5538-94-3	N, N-Dioctyl-N,N-dimethylammonium chloride	50%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
CL2030	Micro biocide and Algicide	Proprietary solve	ent											
		2809-21-4	1-Hydroxyethylidene-1,1-diphosphoric acid	1-5%										
CL5430	Corrosion Inhibitor	7664-38-2	Phosphoric Acid	7-13%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
		95-14-7	Benzotriazole	1-5%	1 '			production is	,					
		64665-57-2	Tolyltriazole, sodium salt	1-5%										
CL5570 Scale Inh	Scale Inhibitor	64-02-8	Ethylene diamine tetraacetic acid, tetrasodium salt	1-5%	Non-persistent	Not Available	Continuously	Not determined	Very Low					
		1310-73-2	Sodium hydroxide	5-10%										
CL5640	Corrosion Inhibitor	37971-36-1	2-Phosphono-1,2,4-butane tricarboxylic acid	7-13%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
CL5644	Corrosion Inhibitor	77-92-9	Citric acid	5-10%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
FlexPro CL5737 Corro	Corrosion Inhibitor	77-92-9	Citric acid	1-5%	Non parcistant	·	Continuously	See Section 12 of product SDS	Very low					
FIEXPIO CL3737	Corrosion inhibitor	7664-93-9	Sulfuric acid	1-5%	Non-persistent		Continuously		,					
DF20	Foam Control	Proprietary			Non-persistent	Not Available	Continuously	Not determined	Very Low					
FFC1	Fin Cleaning Solution	1569-01-3	Propylene glycol n-Propyl Ether (PNP)	<20%	Non-persistent	Not Available	Continuously	Not determined	Very Low					
FFCLC	Fin Cleaning Solution	1569-01-3	Propylene glycol n-Propyl Ether (PNP)	<20%	Non-persistent	Not Available	Continuously	Not determined	Very Low					
FO120	Defoamer	68002-96-0	Alcohols, C16–18, Ethoxylated Propoxylated	1-5%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
FO180	Defoamer	Trade secret		_	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
	Defoamer	63148-62-9	Polydimethylsiloxane	10-40%		Not Available	Continuously	See Section 12 of product SDS						
FO220		64742-47-8	Petroleum distillate hydrotreated light	<10%	Non-persistent				Very low					
		112926-00-8	Silicon dioxide	<5%										
P873L	Water Clarification Agent	Trade secret	1		Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
P893L	Water Clarification Agent	1327-41-9	Polyaluminum chloride	60-100%	Not Available	Not Available	Continuously	See Section 12 of product SDS	Very low					
RL9075	Reverse Osmosis Treatment	22042-96-2	Diethylenetriamine penta methylene phosphonic acid, sodium salt	1-5%	Non-persistent		Continuously	See Section 12 of product SDS	Vandow					
KL30/3		7631-90-5	Sodium bisulfite	10-30%		Not Available			Very low					
		37971-36-1	2-Phosphono-1,2,4-butane tricarboxylic acid	1-5%										
Carbon Dioxide	pH Control	124-38-9	Carbon Dioxide	100%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					
Sodium Bisulfite	Residual Chlorine Control	7631-90-5	Sodium Bisulfite	10-30%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low					



# Page: 1/8

Safety Data Sheet
Acc. to OSHA HCS (29 CFR 1910.1200)

Printing date: May 01, 2018 Revision: May 01, 2018

#### 1 Identification

· Product identifier

· Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

Product code: AC-455

· Recommended use and restriction on use

· Recommended use: Water treatment

· Restrictions on use: No relevant information available.

Details of the supplier of the Safety Data Sheet

· Manufacturer/Supplier:

Agua Clear Water Treatment Specialists

8451 Miralani Drive San Diego, CA 92126 Phone: (858) 270-7655

· Emergency telephone number:

ChemTel Inc.

(800)255-3924 (North America)

+1 (813)248-0585 (International)

# 2 Hazard(s) identification

· Classification of the substance or mixture

Eye Dam. 1 H318 Causes serious eye damage.

· Additional information: Contact with acids liberates toxic gas.

- Label elements
- · GHS label elements

The product is classified and labeled according to the Globally Harmonized System (GHS).

Hazard pictograms:



GHS05

· Signal word: Danger

· Hazard statements:

H318 Causes serious eye damage.

· Precautionary statements:

P280 Wear eye protection.

P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if

present and easy to do. Continue rinsing.

P310 Immediately call a poison center/doctor.

· Additional information: Contact with acids liberates toxic gas.

Other hazards There are no other hazards not otherwise classified that have been identified.

# 3 Composition/information on ingredients

· Chemical characterization: Mixtures

(Cont'd. on page 2)





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 1)

· Components:

7681-57-4 sodium metabisulphite

Eye Dam. 1, H318 1 Acute Tox. 4, H302 <20%

Additional information:

For the listed ingredient(s), the identity and/or exact percentage(s) are being withheld as a trade secret. For the wording of the listed Hazard Statements, refer to section 16.

## 4 First-aid measures

- Description of first aid measures
- · After inhalation: Supply fresh air; consult doctor in case of complaints.
- · After skin contact:

Immediately rinse with water.

If skin irritation is experienced, consult a doctor.

· After eye contact:

Protect unharmed eye.

Remove contact lenses if worn.

Rinse opened eye for several minutes under running water. Then consult a doctor.

· After swallowing:

Rinse out mouth and then drink plenty of water.

Do not induce vomiting; immediately call for medical help.

· Most important symptoms and effects, both acute and delayed:

Irritating to eyes.

Causes mild skin irritation.

- · Danger: Causes serious eye damage.
- Indication of any immediate medical attention and special treatment needed: Treat symptomatically.

### 5 Fire-fighting measures

- Extinguishing media
- · Suitable extinguishing agents:

The product is not flammable.

Use fire fighting measures that suit the environment.

- · For safety reasons unsuitable extinguishing agents: None.
- Special hazards arising from the substance or mixture

During heating or in case of fire poisonous gases are produced.

- Advice for firefighters
- · Protective equipment:

Wear self-contained respiratory protective device.

Wear fully protective suit.

## 6 Accidental release measures

Personal precautions, protective equipment and emergency procedures

Wear protective equipment. Keep unprotected persons away.

For large spills, use respiratory protective device against the effects of fumes/dust/aerosol.

(Cont'd. on page 3)





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 2)

Ensure adequate ventilation.

#### Environmental precautions

Do not allow undiluted product or large quantities of it to reach ground water, water course or sewage system.

#### · Methods and material for containment and cleaning up

Towel or mop up material and collect in a suitable container.

For larger spills, add sawdust, chalk or other inert binding material, then sweep up and discard.

Send for recovery or disposal in suitable receptacles.

### Reference to other sections

See Section 7 for information on safe handling.

See Section 8 for information on personal protection equipment.

See Section 13 for disposal information.

# 7 Handling and storage

- · Handling
- · Precautions for safe handling:

Avoid splashes or spray in enclosed areas.

Use only in well ventilated areas.

Handle with care.

- · Information about protection against explosions and fires: No special measures required.
- Conditions for safe storage, including any incompatibilities
- Requirements to be met by storerooms and receptacles:

Avoid storage near extreme heat.

Use only receptacles specifically permitted for this substance/product.

Store in cool, dry conditions in well sealed receptacles.

Information about storage in one common storage facility:

Do not store together with acids.

Store away from foodstuffs.

Store away from oxidizing agents.

· Specific end use(s) No relevant information available.

#### 8 Exposure controls/personal protection

· Control parameters

· Components	with limit v	alues that	require monitor	ing at the workp	lace:

# **7681-57-4 sodium metabisulphite**REL (USA) | Long-term value: 5 mg/m³

REE (OOA)	Long-term value. 5 mg/m
TLV (USA)	Long-term value: 5 mg/m³ Long-term value: 5 mg/m³ Long-term value: 5 mg/m³ Long-term value: 5 mg/m³
EL (Canada)	Long-term value: 5 mg/m³
EV (Canada)	Long-term value: 5 mg/m³
LMPE (Mexico)	Long-term value: 5 mg/m³
	ΔΛ

- Exposure controls
- General protective and hygienic measures:

(Cont'd. on page 4)





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 3)

The usual precautionary measures for handling chemicals should be followed.

Keep away from foodstuffs, beverages and feed.

Immediately remove all soiled and contaminated clothing.

Wash hands before breaks and at the end of work.

Avoid contact with the eyes.

Avoid close or long term contact with the skin.

- · Engineering controls: No relevant information available.
- · Breathing equipment:

Not required under normal conditions of use.

Use suitable respiratory protective device when aerosol or mist is formed.

· Protection of hands:

Not required under normal conditions of use.

Wear protective gloves to handle contents of damaged or leaking units.

Gloves are advised for repeated or prolonged contact.

Protection may be required for spills.

- Material of gloves Rubber gloves
- Eye protection:



Safety glasses

Follow relevant national guidelines concerning the use of protective eyewear.

- · Body protection: Protection may be required for spills.
- Limitation and supervision of exposure into the environment No relevant information available.

D' L

· Risk management measures No relevant information available.

# 9 Physical and chemical properties

Appearance:		
Form:	Liquid	
Color:	Colorless	
Odor:	Nearly odorless	
Odor threshold:	Not determined.	
pH-value:	Not determined.	
Melting point/Melting range:	Not determined.	
Boiling point/Boiling range:	Not determined.	
Flash point:	The product is not flammable.	
Flammability (solid, gaseous):	Not applicable.	
Auto-ignition temperature:	Not determined.	
Decomposition temperature:	Not determined.	
Danger of explosion:	Product does not present an explosion hazard.	
Explosion limits		
Lower:	Not determined.	





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 4)

Upper: Not determined. • Oxidizing properties: Not determined.

· Vapor pressure: Not determined.

· Density:

Relative density: 1.0-1.1

Vapor density: Not determined. Evaporation rate: Not determined.

· Solubility in / Miscibility with

Water: Soluble.

· Partition coefficient (n-octanol/water): Not determined.

· Viscosity

**Dynamic:** Not determined. **Kinematic:** Not determined.

• Other information No relevant information available.

# 10 Stability and reactivity

- · **Reactivity:** No relevant information available.
- · Chemical stability: Stable under normal temperatures and pressures.
- Thermal decomposition / conditions to be avoided:

No decomposition if used and stored according to specifications.

· Possibility of hazardous reactions

Contact with acids releases toxic gases.

Toxic fumes may be released if heated above the decomposition point.

Reacts with strong oxidizing agents.

Reacts with certain metals.

- · Conditions to avoid Excessive heat.
- Incompatible materials

Oxidizers

Strong acids

· Hazardous decomposition products

Sulfur oxides (SOx)

Hydrogen sulfide

# 11 Toxicological information

- Information on toxicological effects
- · Acute toxicity: Based on available data, the classification criteria are not met.
- · LD/LC50 values that are relevant for classification:

## 7681-57-4 sodium metabisulphite

Oral LD50 1600-2000 mg/kg (rat)

- Primary irritant effect:
- On the skin: Based on available data, the classification criteria are not met.

(Cont'd. on page 6)



# Safety Data Sheet

Acc. to OSHA HCS (29 CFR 1910.1200)

Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 5)

Page: 6/8

• On the eye: Strong irritant with the danger of severe eye injury.

· Sensitization: Based on available data, the classification criteria are not met.

· Carcinogenic categories

· IARC (International Agency for Research on Cancer):

None of the ingredients are listed.

· NTP (National Toxicology Program):

None of the ingredients are listed.

· OSHA-Ca (Occupational Safety & Health Administration):

None of the ingredients are listed.

· Probable route(s) of exposure:

Ingestion.

Inhalation.

Eve contact.

Skin contact.

- · Germ cell mutagenicity: Based on available data, the classification criteria are not met.
- · Carcinogenicity: Based on available data, the classification criteria are not met.
- Reproductive toxicity: Based on available data, the classification criteria are not met.
- · STOT-single exposure: Based on available data, the classification criteria are not met.
- · STOT-repeated exposure: Based on available data, the classification criteria are not met.
- · Aspiration hazard: Based on available data, the classification criteria are not met.

## 12 Ecological information

- · Toxicity
- · Aquatic toxicity No relevant information available.
- · Persistence and degradability No relevant information available.
- · Bioaccumulative potential: No relevant information available.
- · Mobility in soil: No relevant information available.
- · Additional ecological information
- · General notes:

Do not allow undiluted product or large quantities of it to reach ground water, water course or sewage system.

Due to available data on eliminability/decomposition and bioaccumulation potential, a prolonged damage of the environment is unlikely.

· Other adverse effects No relevant information available.

# 13 Disposal considerations

- · Waste treatment methods
- · Recommendation:

The user of this material has the responsibility to dispose of unused material, residues and containers in compliance with all relevant local, state and federal laws and regulations regarding treatment, storage and disposal for hazardous and nonhazardous wastes.

- **Uncleaned packagings**
- · Recommendation: Disposal must be made according to official regulations.





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 6)

UN-Number		
DOT, ADR, IMDG, IATA	Not regulated.	
UN proper shipping name DOT, ADR, IMDG, IATA	Not regulated.	
Transport hazard class(es)		
DOT, ADR, IMDG, IATA Class	Not regulated.	
Packing group DOT, ADR, IMDG, IATA	Not regulated.	
Environmental hazards Marine pollutant:	No	
Special precautions for user	Not applicable.	
Transport in bulk according to Annex MARPOL73/78 and the IBC Code	( II of  Not applicable.	

# 15 Regulatory information

- Safety, health and environmental regulations/legislation specific for the substance or mixture
- · United States (USA)
- ·SARA
- · Section 302 (extremely hazardous substances):

None of the ingredients are listed.

· Section 355 (extremely hazardous substances):

None of the ingredients are listed.

· Section 313 (Specific toxic chemical listings):

None of the ingredients are listed.

TSCA (Toxic Substances Control Act)

All ingredients are listed.

- · Proposition 65 (California)
- · Chemicals known to cause cancer:

None of the ingredients are listed.

· Chemicals known to cause developmental toxicity for females:

None of the ingredients are listed.

· Chemicals known to cause developmental toxicity for males:

None of the ingredients are listed.

· Chemicals known to cause developmental toxicity:

(Cont'd. on page 8)





Printing date: May 01, 2018 Revision: May 01, 2018

Trade name: AC-455 Oxygen Scavenger Blend (Non-Odorous)

(Cont'd. of page 7)

None of the ingredients are listed.

· EPA (Environmental Protection Agency):

None of the ingredients are listed.

IARC (International Agency for Research on Cancer):

None of the ingredients are listed.

#### 16 Other information

This information is based on our present knowledge. However, this shall not constitute a guarantee for any specific product features and shall not establish a legally valid contractual relationship.

· Date of preparation / last revision May 01, 2018 / -

### Abbreviations and acronyms:

ADR: European Agreement concerning the International Carriage of Dangerous Goods by Road

IMDG: International Maritime Code for Dangerous Goods

DOT: US Department of Transportation

IATA: International Air Transport Association

CAS: Chemical Abstracts Service (division of the American Chemical Society)

LC50: Lethal concentration, 50 percent

LD50: Lethal dose, 50 percent

OSHA: Occupational Safety & Health Administration

TLV: Threshold Limit Value PEL: Permissible Exposure Limit

REL: Recommended Exposure Limit

Acute Tox. 4: Acute toxicity – Category 4

Eye Dam. 1: Serious eye damage/eye irritation - Category 1

#### · Sources

Website, European Chemicals Agency (echa.europa.eu)

Website, US EPA Substance Registry Services (ofmpub.epa.gov/sor internet/registry/substreg/home/overview/home.do)

Website, Chemical Abstracts Registry, American Chemical Society (www.cas.org)

Patty's Industrial Hygiene, 6th ed., Rose, Vernon, ed. ISBN: 978-0-470-07488-6

Casarett and Doull's Toxicology: The Basic Science of Poisons, 8th Ed., Klaasen, Curtis D., ed., ISBN: 978-0-07-176923-5.

Safety Data Sheets, Individual Manufacturers

SDS Prepared by:

ChemTel Inc.

1305 North Florida Avenue

Tampa, Florida USA 33602-2902

Toll Free North America 1-888-255-3924 Intl. +01 813-248-0573

Website: www.chemtelinc.com





Printing date: March 14, 2017 Revision: March 14, 2017

#### 1 Identification

· Product identifier

· Trade name: AC-777 Membrane Anti-Scalent

· Product code: AC-777

· Recommended use and restriction on use

· Recommended use: Water treatment

· Restrictions on use: No relevant information available.

Details of the supplier of the Safety Data Sheet

· Manufacturer/Supplier:

Aqua Clear Water Treatment Specialists

8451 Miralani Drive San Diego, CA 92126 Phone: (858) 270-7655

· Emergency telephone number:

ChemTel Inc.

(800)255-3924 (North America) +1 (813)248-0585 (International)

# 2 Hazard(s) identification

· Classification of the substance or mixture

Skin Irrit. 2 H315 Causes skin irritation.

Eye Irrit. 2A H319 Causes serious eye irritation.

- · Label elements
- · GHS label elements

The product is classified and labeled according to the Globally Harmonized System (GHS).

· Hazard pictograms:



GHS07

· Signal word: Warning

· Hazard statements:

P302+P352

H315 Causes skin irritation.

H319 Causes serious eye irritation.

**Precautionary statements:** 

P264 Wash thoroughly after handling.

P280 Wear protective gloves and eye protection.

P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if

present and easy to do. Continue rinsing. IF ON SKIN: Wash with plenty of water.

P332+P313 If skin irritation occurs: Get medical advice/attention.
P337+P313 If eye irritation persists: Get medical advice/attention.
Take off contaminated clothing and wash it before reuse.

(Cont'd. on page 2)



Page: 2/9

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 1)

Other hazards There are no other hazards not otherwise classified that have been identified.

# 3 Composition/information on ingredients

· Chemical characterization: Mixtures

· Components:				
20592-85-2 Phosphonic acid,P,P',P"-[nitrilotris(methylene)]tris-, sodium salt	10-20%			
Met. Corr.1, H290 Eye Irrit. 2A, H319				
1310-58-3 Potassium hydroxide	<2%			
Met. Corr.1, H290; Skin Corr. 1A, H314 Acute Tox. 4, H302				

#### · Additional information:

For the wording of the listed Hazard Statements refer to section 16.

For the listed ingredient(s), the identity and/or exact percentage(s) are being withheld as a trade secret.

### 4 First-aid measures

- Description of first aid measures
- · After inhalation:

Supply fresh air; consult doctor in case of complaints.

Provide oxygen treatment if affected person has difficulty breathing.

· After skin contact:

Immediately rinse with water.

If skin irritation continues, consult a doctor.

Seek immediate medical help for blistering or open wounds.

· After eye contact:

Remove contact lenses if worn.

Rinse opened eye for several minutes under running water. If symptoms persist, consult a doctor.

After swallowing:

Rinse out mouth and then drink plenty of water.

Do not induce vomiting; immediately call for medical help.

· Most important symptoms and effects, both acute and delayed:

Cramp

Coughing

Irritant to skin and mucous membranes.

Causes eye irritation.

Gastric or intestinal disorders when ingested.

Nausea in case of ingestion.

Indication of any immediate medical attention and special treatment needed:

No relevant information available.

(Cont'd. on page 3)



Page: 3/9

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 2)

# 5 Fire-fighting measures

- · Extinguishing media
- Suitable extinguishing agents:

The product is not flammable.

Use fire fighting measures that suit the environment.

- For safety reasons unsuitable extinguishing agents: None.
- Special hazards arising from the substance or mixture No relevant information available.
- Advice for firefighters
- · Protective equipment:

Wear self-contained respiratory protective device.

Wear fully protective suit.

#### 6 Accidental release measures

· Personal precautions, protective equipment and emergency procedures

Use personal protective equipment as required.

Ensure adequate ventilation.

Environmental precautions

Do not allow undiluted product or large quantities of it to reach ground water, water course or sewage system.

Methods and material for containment and cleaning up

Absorb with liquid-binding material (sand, diatomite, acid binders, universal binders, sawdust).

Send for recovery or disposal in suitable receptacles.

Reference to other sections

See Section 7 for information on safe handling.

See Section 8 for information on personal protection equipment.

See Section 13 for disposal information.

# 7 Handling and storage

- Handling
- Precautions for safe handling:

The usual precautionary measures for handling chemicals should be followed.

Ensure good ventilation/exhaustion at the workplace.

Open and handle receptacle with care.

Avoid splashes or spray in enclosed areas.

Avoid contact with the eyes and skin.

Keep out of reach of children.

- · Information about protection against explosions and fires: No special measures required.
- · Conditions for safe storage, including any incompatibilities
- Storage
- · Requirements to be met by storerooms and receptacles:

Store in cool, dry conditions in well sealed receptacles.

Use only receptacles specifically permitted for this substance/product.

Unsuitable material for receptacle: aluminium.

(Cont'd. on page 4)



Page: 4/9

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 3)

· Information about storage in one common storage facility:

Store away from foodstuffs.

Do not store together with acids.

· Specific end use(s) No relevant information available.

# 8 Exposure controls/personal protection

- · Control parameters
- · Components with limit values that require monitoring at the workplace:

## 1310-58-3 Potassium hydroxide

	Ceiling limit value: 2 mg/m³
TLV (USA)	Ceiling limit value: 2 mg/m³
EL (Canada)	Ceiling limit value: 2 mg/m³
EV (Canada)	Ceiling limit value: 2 mg/m³
LMPE (Mexico)	Ceiling limit value: 2 mg/m³

- · Exposure controls
- · Personal protective equipment:
- · General protective and hygienic measures:

Keep away from foodstuffs, beverages and feed.

Immediately remove all soiled and contaminated clothing.

Wash hands before breaks and at the end of work.

Avoid contact with the eyes and skin.

- · Engineering controls: No relevant information available.
- Breathing equipment:

Not required under normal conditions of use.

Use suitable respiratory protective device in case of insufficient ventilation.

· Protection of hands:



Protective gloves

The glove material has to be impermeable and resistant to the product/ the substance/ the preparation.

· Eye protection:



Safety glasses

- · Body protection: Protective work clothing
- Limitation and supervision of exposure into the environment

No relevant information available.

· Risk management measures See Section 7 for additional information.

(Cont'd. on page 5)





Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 4)

9 Physical and chemical prope	erties
Information on basic physical a	and chemical properties
· Appearance:	
Form:	Liquid
Color: · Odor:	Light yellow
· Odor threshold:	Light Not determined.
· pH-value:	~10.5 Not determined.
· Melting point/Melting range: · Boiling point/Boiling range:	Not determined. Not determined.
· Flash point:	Not applicable.
· Flammability (solid, gaseous):	Not applicable.
· Auto-ignition temperature:	Not determined.
· Decomposition temperature:	Not determined.
· Danger of explosion:	Product does not present an explosion hazard.
· Explosion limits	
Lower:	Not determined.
Upper:	Not determined.
· Vapor pressure:	Not determined.
· Density:	
Relative density:	1.25
Vapor density:	Not determined.
Evaporation rate:	Not determined.
· Solubility in / Miscibility with	
Water:	Soluble.
· Partition coefficient (n-octanol/wa	ter): Not determined.
· Viscosity	
Dynamic:	Not determined.
Kinematic:	Not determined.
Other information	No relevant information available.

# 10 Stability and reactivity

- · Reactivity: No relevant information available.
- · Chemical stability:
- Thermal decomposition / conditions to be avoided:

No decomposition if used and stored according to specifications.

· Possibility of hazardous reactions

Reacts with oxidizing agents.

Reacts with strong acids.

(Cont'd. on page 6)



# Safety Data Sheet

acc. to OSHA HCS (29 CFR 1910.1200)

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 5)

Page: 6/9

- · Conditions to avoid Excessive heat.
- · Incompatible materials Strong acids
- Hazardous decomposition products

Carbon monoxide and carbon dioxide

Phosphorus oxides (e.g. P2O5)

# 11 Toxicological information

- Information on toxicological effects
- · Acute toxicity:
- LD/LC50 values that are relevant for classification:

1310-58-3 Potassium hydroxide

Oral LD50 273 mg/kg (rat)

- Primary irritant effect:
- · On the skin: Irritant to skin and mucous membranes.
- · On the eye: Irritating effect.
- · Sensitization: No sensitizing effects known.
- Carcinogenic categories
- · IARC (International Agency for Research on Cancer):

None of the ingredients are listed.

· NTP (National Toxicology Program):

None of the ingredients are listed.

· OSHA-Ca (Occupational Safety & Health Administration):

None of the ingredients are listed.

· Probable route(s) of exposure:

Eye contact.

Skin contact.

- · CMR effects (carcinogenity, mutagenicity and toxicity for reproduction)
- · Germ cell mutagenicity: Based on available data, the classification criteria are not met.
- · Carcinogenicity: Based on available data, the classification criteria are not met.
- · Reproductive toxicity: Based on available data, the classification criteria are not met.
- · STOT-single exposure: Based on available data, the classification criteria are not met.
- · STOT-repeated exposure: Based on available data, the classification criteria are not met.
- · Aspiration hazard: Based on available data, the classification criteria are not met.

# 12 Ecological information

- · Toxicity
- · Aquatic toxicity No relevant information available.
- Persistence and degradability No relevant information available.
- · Bioaccumulative potential: No relevant information available.
- · Mobility in soil: No relevant information available.

(Cont'd. on page 7)



Page: 7/9

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 6)

# · Additional ecological information

· General notes:

Do not allow undiluted product or large quantities of it to reach ground water, water course or sewage system.

• Other adverse effects No relevant information available.

# 13 Disposal considerations

- · Waste treatment methods
- · Recommendation:

Small amounts may be diluted with plenty of water and washed away. Dispose of bigger amounts in accordance with Local Authority requirements.

The user of this material has the responsibility to dispose of unused material, residues and containers in compliance with all relevant local, state and federal laws and regulations regarding treatment, storage and disposal for hazardous and nonhazardous wastes.

- **Uncleaned packagings**
- Recommendation: Disposal must be made according to official regulations.
- Recommended cleansing agent: Water, if necessary with cleansing agents.

14 Transport information	
· UN-Number · DOT, ADR, IMDG, IATA	Not regulated.
· UN proper shipping name · DOT, ADR, IMDG, IATA	Not regulated.
· Transport hazard class(es)	
· DOT, ADR, IMDG, IATA · Class	Not regulated.
· Packing group · DOT, ADR, IMDG, IATA	Not regulated.
· Environmental hazards · Marine pollutant:	No
Special precautions for user	Not applicable.
Transport in bulk according to Annex II MARPOL73/78 and the IBC Code	of Not applicable.

(Cont'd. on page 8)



# Safety Data Sheet

acc. to OSHA HCS (29 CFR 1910.1200)

Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 7)

Page: 8/9

# 15 Regulatory information

- · Safety, health and environmental regulations/legislation specific for the substance or mixture
- · United States (USA)
- ·SARA
- · Section 302 (extremely hazardous substances):

None of the ingredients are listed.

Section 304 (emergency release notification):

None of the ingredients are listed.

Section 355 (extremely hazardous substances):

None of the ingredients are listed.

Section 313 (Specific toxic chemical listings):

None of the ingredients are listed.

· TSCA (Toxic Substances Control Act)

All ingredients are listed.

- · Proposition 65 (California)
- · Chemicals known to cause cancer:

None of the ingredients are listed.

· Chemicals known to cause reproductive toxicity for females:

None of the ingredients are listed.

Chemicals known to cause reproductive toxicity for males:

None of the ingredients are listed.

Chemicals known to cause developmental toxicity:

None of the ingredients are listed.

- · Carcinogenic categories
- EPA (Environmental Protection Agency):

None of the ingredients are listed.

· IARC (International Agency for Research on Cancer):

None of the ingredients are listed.

NIOSH-Ca (National Institute for Occupational Safety and Health):

None of the ingredients are listed.

### 16 Other information

This information is based on our present knowledge. However, this shall not constitute a guarantee for any specific product features and shall not establish a legally valid contractual relationship.

- · Date of preparation / last revision March 14, 2017 / -
- · Abbreviations and acronyms:

ADR: European Agreement concerning the International Carriage of Dangerous Goods by Road IMDG: International Maritime Code for Dangerous Goods

(Cont'd. on page 9)





Printing date: March 14, 2017 Revision: March 14, 2017

Trade name: AC-777 Membrane Anti-Scalent

(Cont'd. of page 8)

DOT: US Department of Transportation IATA: International Air Transport Association

CAS: Chemical Abstracts Service (division of the American Chemical Society)

LC50: Lethal concentration, 50 percent

LD50: Lethal dose, 50 percent

NIOSH: National Institute for Occupational Safety

OSHA: Occupational Safety & Health

TLV: Threshold Limit Value
PEL: Permissible Exposure Limit

REL: Recommended Exposure Limit

Met. Corr.1: Corrosive to metals – Category 1 Acute Tox. 4: Acute toxicity – Category 4

Skin Corr. 1A: Skin corrosion/irritation – Category 1A

Skin Irrit. 2: Skin corrosion/irritation – Category 2

Eye Irrit. 2A: Serious eye damage/eye irritation - Category 2A

#### · Sources

Website, European Chemicals Agency (echa.europa.eu)

Website, US EPA Substance Registry Services (ofmpub.epa.gov/sor internet/registry/substreg/home/overview/home.do)

Website, Chemical Abstracts Registry, American Chemical Society (www.cas.org)

Patty's Industrial Hygiene, 6th ed., Rose, Vernon, ed. ISBN: 978-0-470-07488-6

Casarett and Doull's Toxicology: The Basic Science of Poisons, 8th Ed., Klaasen, Curtis D., ed., ISBN: 978-0-07-176923-5.

Safety Data Sheets, Individual Manufacturers

SDS Prepared by:

ChemTel Inc.

1305 North Florida Avenue

Tampa, Florida USA 33602-2902

Toll Free North America 1-888-255-3924 Intl. +01 813-248-0573

Website: www.chemtelinc.com



# Safety Data Sheet

according to ICOP 2014,2019 Issue date: 3/16/2015 Revision date: 4/24/2024 Supersedes: 2/25/2025 Version: 2.0

# Warning



#### SECTION 1: Identification of the hazardous chemical and of the supplier

#### 1.1. Product identifier

Trade name : Carbon dioxide, Purified Carbon dioxide

Name : Carbon dioxide CAS-No. : 124-38-9 Formula : CO2

1.2. Other means of identification

Product code : ALM/SDS/33

# 1.3. Recommended use of the chemical and restrictions on use

Recommended use : Test gas/Calibration gas.

Laboratory use.

Use for manufacture of electronic/photovoltaic components.

Food application.

Industrial and professional uses. Perform risk assessment prior to use.

Contact supplier for more information on uses.

Restrictions on use : Consumer use.

#### 1.4. Supplier details

AIR LIQUIDE MALAYSIA SDN. BHD. Lot PT 2317, No. 21, Jalan PTB 1

Kawasan Perindustrian Tangga Batu, Mukim Sungai Udang,

76400 Melaka Malaysia T +606-3513512

1.5. Emergency phone number

**Emergency number** : +606-3513512

# **SECTION 2: Hazards identification**

#### 2.1. Classification of the hazardous chemical

Classification according to Industry Code of Practice on chemicals classification and hazard communication (2019)

Gases under pressure: Liquefied gas H280

# 2.2. Label elements

Labelling according to Industry Code of Practice on chemicals classification and hazard communication (2019)

Hazard pictograms (GHS MY)



Signal word (GHS MY) : Warning

Hazard statements (GHS MY) : H280 - Contains gas under pressure; may explode if heated Precautionary statements (GHS MY) : P410+P403 - Protect from sunlight. Store in a well-ventilated place

## Safety Data Sheet

according to ICOP 2014,2019

### 2.3. Other hazards that do not result in classification

Other hazards which do not result in classification

: Asphyxiant in high concentrations, Contact with liquid may cause cold burns/frostbite, The substance/mixture has no endocrine disrupting properties.

## SECTION 3: Composition and information of the ingredients of the hazardous chemical

#### 3.1. Substances

Name	Product identifier	%
Carbon dioxide	CAS-No.: 124-38-9	100
(Main constituent)		

Full text of H-statements: see section 16

#### 3.2. Mixtures

Not applicable

## **SECTION 4: First-aid measures**

#### 4.1. Description of necessary first aid measures

First-aid measures after inhalation : Remove victim to uncontaminated area wearing self contained breathing apparatus. Keep

victim warm and rested. Call a doctor. Perform cardiopulmonary resuscitation if breathing

stopped.

First-aid measures after skin contact : In case of frostbite spray with water for at least 15 minutes. Apply a sterile dressing. Obtain

medical assistance.

First-aid measures after eye contact : Immediately flush eyes thoroughly with water for at least 15 minutes.

First-aid measures after ingestion : Ingestion is not considered a potential route of exposure.

#### 4.2. Most important symptoms/effects, acute and delayed

Most important symptoms and effects, both acute

and delayed

: In high concentrations may cause asphyxiation. Symptoms may include loss of mobility/consciousness. Victim may not be aware of asphyxiation. See section 11.

#### 4.3. Indication of immediate medical attention and special treatment needed, if necessary

Other medical advice or treatment : None.

## **SECTION 5: Fire-fighting measures**

### 5.1. Suitable extinguishing media

Suitable extinguishing media : Water spray or fog. Product does not burn, use fire control measures appropriate for the

surrounding fire.

Unsuitable extinguishing media : Do not use water jet to extinguish.

#### 5.2. Physicochemical hazards arising from the chemical

Reactivity in case of fire : No reactivity hazard other than the effects described in sub-sections below.

# 5.3. Special protective equipment and precautions for fire fighters

Special protective equipment for fire fighters : In confined space use self-contained breathing apparatus. Standard protective clothing and

equipment (Self Contained Breathing Apparatus) for fire fighters. Standard EN 469 - Protective clothing for firefighters. Standard - EN 659: Protective gloves for firefighters. Standard EN 137 - Self-contained open-circuit compressed air breathing apparatus with full

face mask.

Specific methods : Use fire control measures appropriate for the surrounding fire. Exposure to fire and heat

radiation may cause gas receptacles to rupture. Cool endangered receptacles with water spray jet from a protected position. Prevent water used in emergency cases from entering sewers and drainage systems, If possible, stop flow of product, Use water spray or fog to knock down fire fumes if possible, Move containers away from the fire area if this can be

done without risk.

EAC code : 2T

7/31/2024 (Revision date) MY - en 2/10

# Safety Data Sheet

according to ICOP 2014,2019

#### **SECTION 6: Accidental release measures**

#### 6.1. Personal precautions, protective equipment, and emergency procedures

#### 6.1.1. For non-emergency personnel

**Emergency procedures** 

: Act in accordance with local emergency plan. Try to stop release. Evacuate area. Ensure adequate air ventilation. Prevent from entering sewers, basements and workpits, or any place where its accumulation can be dangerous. Stay upwind. See section 8 of the SDS for more information on personal protective equipment.

#### 6.1.2. For emergency responders

**Emergency procedures** 

: Wear self-contained breathing apparatus when entering area unless atmosphere is proved to be safe. Oxygen detectors should be used when asphyxiating gases may be released. See section 5.3 of the SDS for more information.

#### 6.2. Environmental precautions

Try to stop release.

#### 6.3. Methods and materials for containment and cleaning up

Methods and material for containment and cleaning : Ventilate area.

up

# **SECTION 7: Handling and storage**

#### 7.1. Precautions for safe handling

Safe handling of the gas receptacle

: Refer to supplier's container handling instructions. Do not allow backfeed into the container. Protect containers from physical damage; do not drag, roll, slide or drop. When moving cylinders, even for short distances, use a cart (trolley, hand truck, etc.) designed to transport cylinders. Leave valve protection caps in place until the container has been secured against either a wall or bench or placed in a container stand and is ready for use. If user experiences any difficulty operating valve discontinue use and contact supplier. Never attempt to repair or modify container valves or safety relief devices. Damaged valves should be reported immediately to the supplier. Keep container valve outlets clean and free from contaminants particularly oil and water. Replace valve outlet caps or plugs and container caps where supplied as soon as container is disconnected from equipment. Close container valve after each use and when empty, even if still connected to equipment. Never attempt to transfer gases from one cylinder/container to another. Never use direct flame or electrical heating devices to raise the pressure of a container. Do not remove or deface labels provided by the supplier for the identification of the content of the container. Suck back of water into the container must be prevented. Open valve slowly to avoid pressure shock.

Safe use of the product

: The product must be handled in accordance with good industrial hygiene and safety procedures. Only experienced and properly instructed persons should handle gases under pressure. Consider pressure relief device(s) in gas installations. Ensure the complete gas system was (or is regularily) checked for leaks before use. Do not smoke while handling product. Use only properly specified equipment which is suitable for this product, its supply pressure and temperature. Contact your gas supplier if in doubt. Avoid suck back of water, acid and alkalis. Do not breathe gas. Avoid release of product into work area.

## 7.2. Conditions for safe storage, including any incompatibilities

Conditions for safe storage, including any incompatibilities

: Observe all regulations and local requirements regarding storage of containers. Containers should not be stored in conditions likely to encourage corrosion. Container valve guards or caps should be in place. Containers should be stored in the vertical position and properly secured to prevent them from falling over. Stored containers should be periodically checked for general condition and leakage. Keep container below 50°C in a well ventilated place. Store containers in location free from fire risk and away from sources of heat and ignition. Keep away from combustible materials.

#### **SECTION 8: Exposure controls and personal protection**

### 8.1. Control parameters

7/31/2024 (Revision date) MY - en 3/10

# Safety Data Sheet

according to ICOP 2014,2019

Carbon dioxide (124-38-9)				
Germany - Occupational Exposure Limits (TRGS 900)				
Local name	Kohlenstoffdioxid			
AGW (OEL TWA) [1]	9100 mg/m³			
AGW (OEL TWA) [2]	5000 ppm			
Remark	DFG - Senatskommission zur Prüfung gesundheitsschädlicher Arbeitsstoffe der DFG (MAK-Kommission); EU - Europäische Union (Von der EU wurde ein Luftgrenzwert festgelegt: Abweichungen bei Wert und Spitzenbegrenzung sind möglich)			
Regulatory reference	TRGS900			
United Kingdom - Occupational Exposure Limits				
Local name	Carbon dioxide			
WEL TWA (OEL TWA) [1]	9150 mg/m³			
WEL TWA (OEL TWA) [2]	5000 ppm			
WEL STEL (OEL STEL)	27400 mg/m³			
WEL STEL (OEL STEL) [ppm]	15000 ppm			
Regulatory reference	EH40/2005 (Fourth edition, 2020). HSE			
USA - ACGIH - Occupational Exposure Limits				
Local name	Carbon dioxide			
ACGIH OEL TWA [ppm]	5000 ppm			
ACGIH OEL STEL [ppm]	30000 ppm			
Remark (ACGIH)	TLV® Basis: Asphyxia			
Regulatory reference	ACGIH 2023			

#### Exposure limit values for the other components

No additional information available

## 8.1.1 Biological monitoring

No additional information available

#### 8.2. Appropriate engineering controls

Appropriate engineering controls

: Provide adequate general and local exhaust ventilation. Oxygen detectors should be used when asphyxiating gases may be released. Systems under pressure should be regularily checked for leakages. Ensure exposure is below occupational exposure limits (where available). Consider the use of a work permit system e.g. for maintenance activities.

#### 8.3. Individual protection measures, such as PPE

### Hand protection:

Wear cold insulating gloves when transfilling or breaking transfer connections. Standard EN 511 - Cold insulating gloves. Wear working gloves when handling gas containers. Standard EN 388 - Protective gloves against mechanical risks, performance level 1 or higher.

# Eye protection:

Wear goggles when transfilling or breaking transfer connections. Standard EN 166 - Personal eye-protection - specifications

#### Respiratory protection:

Self contained breathing apparatus is recommended, where unknown exposure may be expected, e.g. during maintenance activities on installation systems. Standard EN 137 - Self-contained open-circuit compressed air breathing apparatus with full face mask.

## Safety Data Sheet

according to ICOP 2014,2019

#### Personal protective equipment symbol(s):





Thermal hazard protection : None in addition to the above sections.

Environmental exposure controls : None necessary.

# **SECTION 9: Physical and chemical properties**

Physical state : Gas

Appearance : No data available Colour : Colourless.
Odour : Odourless.

Odour threshold : Odour threshold is subjective and inadequate to warn of overexposure.

pH : Not applicable for gases and gas mixtures.

Melting point : -78.5 °C Melting point at normal conditions does not exist. At atmospheric pressure solid

carbon dioxide sublimes into gaseous carbon dioxide at -78.5°C

Freezing point : No data available

Boiling point : -56.6 °C

Flash point : Not applicable for gases and gas mixtures.

Evaporation rate : No data available Flammability (solid, gas) : Non flammable.

Explosive limits : Upper explosion limit: Not applicable.

Lower explosion limit: Not applicable.

Vapour pressure : Vapour pressure: 57.3 bar(a)

Vapour pressure at 50°C: No reliable data available.

Relative vapour density at 20°C : Not applicable.

Relative density : 0.82

Relative gas density: 1.52

Solubility : Water: 2000 mg/l Partition coefficient n-octanol/water (Log Pow) : No data available

Partition coefficient n-octanol/water (Log Kow) : 0.83 Critical temperature : 31 °C

Auto-ignition temperature : Non flammable.

Decomposition temperature : Not applicable.

Viscosity, kinematic : Not applicable for gases and gas mixtures.

Viscosity, dynamic : No reliable data available.

Explosive properties : Not applicable.

Density : Not applicable for gases and gas mixtures.

Critical pressure : 7375 kPa
Molecular mass : 44 g/mol
Oxidising properties : Not applicable.

Additional information : Gas/vapour heavier than air. May accumulate in confined spaces, particularly at or below

ground level.

### **SECTION 10: Stability and reactivity**

Reactivity : No reactivity hazard other than the effects described in sub-sections below.

Chemical stability : Stable under normal conditions.

Possibility of hazardous reactions : None.

Conditions to avoid : Avoid moisture in installation systems.

Incompatible materials : None, For additional information on compatibility refer to ISO 11114.

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not

be produced.

## Safety Data Sheet

according to ICOP 2014,2019

### **SECTION 11: Toxicological information**

#### 11.1. Information on toxicological effects

Acute toxicity (oral) : Not classified
Acute toxicity (dermal) : Not classified
Acute toxicity (inhalation) : Not classified
Skin corrosion or irritation : Not classified

pH: Not applicable for gases and gas mixtures.

Serious eye damage or eye irritation : Not classified Respiratory sensitization : Not classified Skin sensitization : Not classified Germ cell mutagenicity : Not classified Carcinogenicity : Not classified Reproductive toxicity : Not classified Specific target organ toxicity (STOT) – single : Not classified

exposure

Specific target organ toxicity (STOT) - repeated

exposure

: Not classified

Aspiration hazard : Not classified

Carbon dioxide (124-38-9)	
Viscosity, kinematic	Not applicable for gases and gas mixtures.

Other information

: Unlike simple asphyxiants, carbon dioxide has the ability to cause death even when normal oxygen levels (20-21%) are maintained. 5% CO2 has been found to act synergistically to increase the toxicity of certain other gases (CO, NO2). CO2 has been shown to enhance the production of carboxy- or met-hemoglobin by these gases possibly due to carbon dioxide's stimulatory effects on the respiratory and circulatory systems. For more information, see 'EIGA Safety Info 24: Carbon Dioxide, Physiological Hazards' at www.eiga.eu. The substance/mixture has no endocrine disrupting properties.

## **SECTION 12: Ecological information**

#### 12.1. Ecotoxicity

Ecology - general : No ecological damage caused by this product.

Hazardous to the aquatic environment, short-term

(acute)

: Not classified

Hazardous to the aquatic environment, long-term

(chronic)

: Not classified

Carbon dioxide (124-38-9)		
Partition coefficient n-octanol/water (Log Kow)	0.83	

#### 12.2. Persistence and degradability

Carbon dioxide (124-38-9)				
Persistence and degradability	No ecological damage caused by this product.			

# 12.3. Bioaccumulative potential

Carbon dioxide (124-38-9)				
Partition coefficient n-octanol/water (Log Kow)	0.83			
Bioaccumulative potential	No ecological damage caused by this product.			

#### 12.4. Mobility in soil

Carbon dioxide (124-38-9)			
Mobility in soil	No additional information available		
Partition coefficient n-octanol/water (Log Kow)	0.83		

# Safety Data Sheet

according to ICOP 2014,2019

Ecology - soil	Because of its high volatility, the product is unlikely to cause ground or water pollution.
	Partition into soil is unlikely.

#### 12.5. Other adverse effects

Ozone : Not classified

Effect on global warming : When discharged in large quantities may contribute to the greenhouse effect, Contains

greenhouse gas(es).

GWP 100 years : 1 Effect on the ozone layer : None.

Other adverse effects : No known effects from this product.

# **SECTION 13: Disposal information**

# 13.1. Disposal methods

Waste treatment methods : May be vented to atmosphere in a well ventilated place. Do not discharge into any place

where its accumulation could be dangerous. Return unused product in original container to

supplier.

Additional information : External treatment and disposal of waste should comply with applicable local and/or

national regulations.

# **SECTION 14: Transportation information**

# 14.1. UN number

UN-No. (UN RTDG) : 1013 UN-No. (IMDG) : 1013 UN-No. (IATA) : 1013

## 14.2. UN proper shipping name

Proper Shipping Name (UN RTDG) : CARBON DIOXIDE
Proper Shipping Name (IMDG) : CARBON DIOXIDE
Proper Shipping Name (IATA) : Carbon dioxide

### 14.3. Transport hazard class(es)

#### **UN RTDG**

Transport hazard class(es) (UN RTDG) : 2.2
Danger labels (UN RTDG) : 2.2



### **IMDG**

Transport hazard class(es) (IMDG) : 2.2
Danger labels (IMDG) : 2.2



## IATA

Transport hazard class(es) (IATA) : 2.2
Danger labels (IATA) : 2.2



## Safety Data Sheet

according to ICOP 2014,2019

#### 14.4. Packing Group, if applicable

Packing group (UN RTDG) : Not applicable
Packing group (IMDG) : Not applicable
Packing group (IATA) : Not applicable

#### 14.5. Environmental hazards

Dangerous for the environment : No Marine pollutant : No

Other information : No supplementary information available

#### 14.6. Transport in bulk (according to Annex II of MARPOL 73/78 and the IBC Code)

Special transport precautions : Avoid transport on vehicles where the load space is not separated from the driver's

compartment, Ensure vehicle driver is aware of the potential hazards of the load and knows what to do in the event of an accident or an emergency, Before transporting product containers: - Ensure there is adequate ventilation, - Ensure that containers are firmly secured, - Ensure valve is closed and not leaking, - Ensure valve outlet cap nut or plug (where provided) is correctly fitted, - Ensure valve protection device (where provided) is

correctly fitted.

**UN RTDG** 

Special provisions (UN RTDG): 378Limited quantities (UN RTDG): 120 mlExcepted quantities (UN RTDG): E1Packing instruction (UN RTDG): P200

**IMDG** 

Special provisions (IMDG): 378, 392Limited quantities (IMDG): 120 mlExcepted quantities (IMDG): E1Packing instructions (IMDG): P200

EmS-No. (Fire) : F-C - FIRE SCHEDULE Charlie - NON-FLAMMABLE GASES

EmS-No. (Spillage) : S-V - SPILLAGE SCHEDULE Victor - GASES (NON-FLAMMABLE, NON-TOXIC)

Stowage category (IMDG) : A

Properties and observations (IMDG) : Liquefied, non-flammable gas. Heavier than air (1.5). Cannot remain in the liquid state above

31°C.

IATA

PCA Excepted quantities (IATA) : E1 PCA Limited quantities (IATA) : Forbidden PCA limited quantity max net quantity (IATA) : Forbidden : 200 PCA packing instructions (IATA) PCA max net quantity (IATA) : 75kg : 200 CAO packing instructions (IATA) CAO max net quantity (IATA) : 150kg Special provisions (IATA) A202 ERG code (IATA) 2L

14.7. Special precautions for user

IBC code : Not applicable.

14.8. Hazchem or Emergency Action Code

EAC code : 2T.

# **SECTION 15: Regulatory information**

#### 15.1. Safety, health, and environmental regulations specific for the hazardous chemical in question

Carbon dioxide (124-38-9)		
EHS Notification and Registration Scheme Not applicable		
EHS Notification and Registration Scheme	Not applicable	

## Safety Data Sheet

according to ICOP 2014,2019

Environmental Quality (Chlorofluorocarbons Prohibition) Order 1993
Environmental Quality (Industrial Efflluent) Regulations 2009
Environmental Quality (Scheduled Wastes) Regulations 2007
Control of Industrial Major Accident Hazards Regulations 1996
Prohibition of Use of Substance Order 1999
Use and Standards of Exposure of Chemical Hazardous to Health Regulations 2000
Chemical Weapons Convention Act
Corrosive and Explosive Substances and Offensive Weapons Act
Dangerous Drugs Act
Pesticides Act
Petroleum (Safety Measures) Act
Poisons Act 1952
Poisons (Psychotropic Substances) Regulations 1989

#### 15.2. International agreements

No additional information available

### **SECTION 16: Other information**

 Version
 : 2.0

 Issue date
 : 3/16/2015

 Revision date
 : 24/04/2024

 Supersedes
 : 25/02/2025

Abbreviations and acronyms : ATE - Acute Toxicity Estimate

CLP - Classification Labelling Packaging Regulation; Regulation (EC) No 1272/2008 REACH - Registration, Evaluation, Authorisation and Restriction of Chemicals Regulation

(EC) No 1907/2006

EINECS - European Inventory of Existing Commercial Chemical Substances

CAS# - Chemical Abstract Service number PPE - Personal Protection Equipment

LC50 - Lethal Concentration to 50 % of a test population

RMM - Risk Management Measures

PBT - Persistent, Bioaccumulative and Toxic vPvB - Very Persistent and Very Bioaccumulative

STOT- SE: Specific Target Organ Toxicity - Single Exposure

CSA - Chemical Safety Assessment

EN - European Standard UN - United Nations

ADR - European Agreement concerning the International Carriage of Dangerous Goods by

Road

IATA - International Air Transport Association

IMDG code - International Maritime Dangerous Goods

RID - Regulations concerning the International Carriage of Dangerous Goods by Rail

WGK - Water Hazard Class

STOT - RE: Specific Target Organ Toxicity - Repeated Exposure

UFI: Unique Formula Identifier

Training advice : The hazard of asphyxiation is often overlooked and must be stressed during operator

training. For more guidance, refer to EIGA SL 01 "Dangers of Asphyxiation", downloadable

at http://www.eiga.eu..

Other information : Classification in accordance with the procedures and calculation methods of Regulation

(EC) 1272/2008 (CLP). Key literature references and sources of data are maintained in EIGA doc 169 : 'Classification and Labelling Guide', downloadable at http://www.Eiga.eu .

7/31/2024 (Revision date) MY - en 9/10

# Safety Data Sheet

according to ICOP 2014,2019

Safety Data Sheet (SDS), Malaysia\_AL

This information is based on our current knowledge and is intended to describe the product for the purposes of health, safety and environmental requirements only. It should not therefore be construed as guaranteeing any specific property of the product.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat CL427

Product Use: Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information: (800)648–4579
Date of SDS: April 24, 2019
Revision Date: April 24, 2019

Revision Number: April 24, 2018

# Section 2. Hazard(s) Identification

Signal Word: DANGER

**GHS Classification(s):** Eye damage/irritation – Category 1

Acute Toxicity Oral - Category 4

Hazardous to the aquatic environment Acute - Category 2

Oxidizing Liquids - Category 2

**Hazard Statement(s):** H318 Causes serious eye damage.

H302 Harmful if swallowed. H401 Toxic to aquatic life. H272 May intensify fire; oxidizer.

**Precautionary Statement(s):** 

**Prevention:** P260 Do not breathe dust/fume/gas/mist/vapors/spray.

P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P271 Use only outdoors or in a well–ventilated area. P280 Wear protective gloves/protective clothing/eye

protection/face protection.

P273 Avoid release into the environment.

P210 Keep away from heat, hot surfaces, sparks, open

flames and other ignition sources. No smoking.

P220 Keep away from clothing and other combustible

materials.





**Response:** P301 + P312 IF SWALLOWED: Call a POISON

CENTER or doctor/physician if you feel unwell P301 + 330 + 331 IF SWALLOWED: Rinse mouth.

Do NOT induce vomiting.

P303 + P361 + P353 IF ON SKIN (or hair):

Remove/take off immediately all contaminated clothing.

Rinse skin with water/shower

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing P305 + P351 + P338 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P310 Immediately call a POISON CENTER/doctor. P363 Wash contaminated clothing before reuse. P370 + P378 In case of fire: Use extinguishing media

suitable to surrounding fire to extinguish.

**Storage:** P405 Store locked up.

**Disposal:** P501 Dispose of contents and container in accordance

with applicable local, regional, national, and/or

international regulations.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Hydrogen peroxide	7722–84–1	10 – 30

#### Comments

If chemical identity and/or exact percentage of composition has been withheld, this information is considered to be a trade secret.





# Section 4. First Aid Measures

**Inhalation:** Remove victim to fresh air and keep at rest in a position

comfortable for breathing. Immediately call a poison center or

doctor/physician.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. Immediately

call a poison center or doctor/physician.

**Skin:** Immediately remove/take off all contaminated clothing. Rinse skin

with water/shower. Wash contaminated clothing before re-use.

Immediately call a poison center or doctor/physician.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

**Necessary:** 

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Product is an oxidizer. Oxidizers may increase the intensity of a

fire.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.





# Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Avoid contamination from any source, including metals, dust, and

organic. Keep drum upright. Do not roll. Store inside only.

Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
Hydrogen peroxide	ACGIH TLV	1.4 mg/m³ TWA
	OSHA PEL	1.4 mg/m³ TWA

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Colorless, Clear

**Specific Gravity:** 1.102 @ 20°C pH: 1.102 @ 20°C, 100.0%

Freezing Point:

Flash Point:

Odor:

Mild

Melting Point:

N/D

Initial Boiling Point and Boiling Range:

Solubility in Water:

N/D

Complete

Evaporation Rate:>1Vapor Density:N/DMolecular Weight:N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas):

Flammable Limits:

Autoignition Temperature:

N/A

**Density:** 9.19 LB/GA

Vapor Pressure:N/D% VOC:0Odor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

**Substances:** 

Strong bases, Reducing agents, Excessive heat, Metals or metal

oxides.

**Hazardous Decomposition** 

**Products:** 

Oxygen gas.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

**Conditions To Avoid:** N/D

# Section 11. Toxicological Information

# **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
Hydrogen peroxide	Oral	LD50	500 MG/KG	Rat
ChemTreat CL427	Oral	LD50	1193 MG/KG	Rat
	Dermal	LD50	>2000 MG/KG	Rabbit

# **Carcinogenicity Category**

Component	Source	Code	Brief Description	
Hydrogen peroxide	ACGIH	TLV-A3	Confirmed animal carcinogen with unknown relevance	
			humans	
	IARC	IARC-3	Unclassifiable as to carcinogenicity in humans	
	MAK	MAK-4	Carcinogenic potential for which genotoxicity plays no	
			role-no significant human risk	

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D





Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

# **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Fathead Minnow	96h	LC50	16.4 mg/l
Ide	72h	LC50	35 mg/l
Daphnia pulex	48h	EC50	2.4 mg/l
Daphnia magna	24h	EC50	7.7 mg/l
Algae	72h	EC50	1.38 ppm
Daphnia magna	21d	NOEC	0.63 ppm
Mysid Shrimp	48h	LC50	18.8 mg/l
Sheepshead Minnow	96h	LC50	308 mg/l

Persistence and N/D

**Biodegradability:** 

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

**Comments:** Based on active ingredient





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

EPA ignitibility characteristic hazardous waste D001 when disposed of in the original product form.

# Section 14. Transport Information

Controlling Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Packing Group:
	AQUEOUS SOLUTION (27%)				
IMDG	UN2014	HYDROGEN PEROXIDE,	N/A	5.1, 8	PGII
		AQUEOUS SOLUTION (27%)			
TDG	UN2014	HYDROGEN PEROXIDE,	N/A	5.1, 8	PGII
		AQUEOUS SOLUTION (27%)			
ICAO	UN2014	HYDROGEN PEROXIDE,	N/A	5.1, 8	PGII
		AQUEOUS SOLUTION (27%)			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.





#### **Federal Regulations**

#### **SARA Title III Rules**

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

No
Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Hydrogen peroxide	N/A	N/A	N/A

Comments: None.

#### **State Regulations**

California Proposition 65: None known.

**Special Regulations** 

Component	States
Hydrogen peroxide	MA, MN, NJ, NY, PA, WA

#### **Compliance Information**

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product is certified by the Orthodox Union as kosher

pareve.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

Comments: None.





### Section 16. Other Information

#### **HMIS Hazard Rating**

Health: 3
Flammability: 0
Physical Hazard: 1
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** April 24, 2019





### Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat CL456

**Product Use:** Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:
Date of SDS:

(800)648-4579 July 23, 2018 July 23, 2018

Revision Date: Revision Number:

July 23, 2016 18072301AN

### Section 2. Hazard(s) Identification

Signal Word: None

GHS Classification(s): Non-Hazardous Substance

Hazard Statement(s): Non–Hazardous Substance

**Precautionary Statement(s):** No significant health risks are expected from exposures under

normal conditions of use.

**Prevention:** None.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Components not listed are either non hazardous or in concentration of	N/A	N/A
less than 1%		

Comments If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

Section 4. First Aid Measures

Inhalation: Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

Rinse cautiously with water for several minutes. Remove contact Eyes:

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

Wash with plenty of soap and water. Call a poison center or Skin:

doctor/physician if you feel unwell.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician if you feel unwell.

**Most Important Symptoms:** N/D

Indication of Immediate **Medical Attention and** Special Treatment Needed, If

**Necessary:** 

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.





**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

#### Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

**Methods for Cleaning up:** Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
Components not listed are either non hazardous or in	N/E	N/E
concentration of less than 1%		

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Colorless, Clear

Specific Gravity: 1.005 @ 20°C

pH: 7.0 @ 20°C, 100.0%

Freezing Point: 37°F
Flash Point: N/D
Odor: Mild
Melting Point: N/A
Initial Boiling Point and Boiling Range: N/D
Solubility in Water: Complete
Evaporation Rate: N/D
Vapor Density: N/D

Vapor Density: N/D Molecular Weight: N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas): N/D Flammable Limits: N/A Autoignition Temperature: N/A

Density: 8.38 LB/GA

Vapor Pressure:N/D% VOC:<1</td>Odor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

**Substances:** 

Strong oxidizers.

**Hazardous Decomposition** 

**Products:** 

None known.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

#### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

#### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Components not listed are either non hazardous or in	N/E	N/E	N/E
concentration of less than 1%			

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

Skin Corrosion/Irritation: N/D





Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

Toxicity:

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

#### **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	8.9 mg/l
Fathead Minnow	96h	LC50	10.8 mg/l

Persistence and

**Biodegradability:** 

N/D

N/D

Bioaccumulative Potential:

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ICAO	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

**Sections 311/312 Hazard Classes** 

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No





#### **Other Sections**

	Section 313 Toxic Chemical	Section 302 EHS TPQ	CERCLA RQ
Components not listed are either non hazardous or in	N/A	N/A	N/A
concentration of less than 1%			

Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
Components not listed are either non hazardous or in	None.
concentration of less than 1%	

#### **Compliance Information**

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

Comments: None.

### Section 16. Other Information

### **HMIS Hazard Rating**

1
0
0
X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: July 23, 2018

#### Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat CL2030

**Product Use:**Cooling Water Microbiocide and Algicide

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road Glen Allen, VA 23060

Telephone Number for Information: (800)648–4579

Date of SDS:May 9, 2016Revision Date:May 9, 2016Revision Number:16050901AN

# Section 2. Hazard(s) Identification

Signal Word: DANGER

GHS Classification(s): Acute Toxicity Oral – Category 4

Acute Toxicity Inhalation – Category 4 Acute Toxicity Dermal – Category 3 Skin corrosion/irritation – Category 1b Eye damage/irritation – Category 2a

**Hazard Statement(s):** H302 Harmful if swallowed.

H332 Harmful if inhaled.

H311 Toxic in contact with skin.

H314 Causes severe skin burns and eye damage.

H319 Causes serious eye irritation.

**Precautionary Statement(s):** 

**Prevention:** P260 Do not breathe dust/fume/gas/mist/vapors/spray.

P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P271 Use only outdoors or in a well-ventilated area. P280 Wear protective gloves/protective clothing/eye

protection/face protection.







**Response:** P301 + P312 IF SWALLOWED: Call a POISON

CENTER or doctor/physician if you feel unwell P303 + P361 + P353 IF ON SKIN (or hair):

Remove/take off immediately all contaminated clothing.

Rinse skin with water/shower

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing P305 + P351 + P388 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P337 + P313 If eye irritation persists, get medical

advice/attention.

**Storage:** P405 Store locked up.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
N,N-Dioctyl-N,N-dimethylammonium chloride	5538-94-3	50
Proprietary solvent	Proprietary	5 – 15

Comments If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

#### Section 4. First Aid Measures

**Inhalation:** Remove victim to fresh air and keep at rest in a position

comfortable for breathing. Immediately call a poison center or

doctor/physician.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. Immediately

call a poison center or doctor/physician.

**Skin:** Wash with plenty of soap and water. Remove/take off all

contaminated clothing. Immediately call a POISON CENTER or

doctor/physician.





**Ingestion:** DO NOT INDUCE VOMITING. Rinse mouth. Immediately call a

POISON CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If Necessary: Probable mucosal damage may contraindicate the use of gastric

lavage.

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

Product emits toxic gases or fumes under fire conditions.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

#### Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Do not discharge effluent containing this product into lakes, ponds,

streams, estuaries, oceans or public waters unless in accordance

with the requirements of a National Pollutant Discharge

Elimination System (NPDES) permit, and the permitting authority has been notified in writing prior to discharge. Do not discharge effluent containing this product to sewer systems without previously notifying the local sewage treatment plant authority. For guidance contact your State Water Board or Regional Office of the EPA.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.





# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

**Store** Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Protect from heat and sources of ignition.

Do not store above 140°F. Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
N,N-Dioctyl-N,N-dimethylammonium chloride	N/E	N/E
Proprietary solvent	N/F	N/F

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield.

**Skin:** Wear butyl rubber or neoprene gloves. Wash them after

each use and replace as necessary. If conditions warrant,

wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.





# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Light Straw, Clear

Specific Gravity: 0.962 @ 20°C

**pH:** 8.8 @ 20°C, 100.0%

Freezing Point: 25°F
Flash Point: >200.1°F
Odor: Moderate
Melting Point: N/D

**Initial Boiling Point and Boiling Range:** 203°F Solubility in Water: Soluble **Evaporation Rate:** N/D **Vapor Density:** N/D **Molecular Weight:** N/D **Viscosity:** N/D Flammability (solid, gas): N/D Flammable Limits: N/A

Density: 8.02 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

# Section 10. Stability and Reactivity

**Autoignition Temperature:** 

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Strong acids.

N/A

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon, Oxides of nitrogen, Toxic vapors/fumes/gases.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D





# Section 11. Toxicological Information

#### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
ChemTreat CL2030	Oral	LD50	360 MG/KG	Mouse
	Dermal	LD50	259 MG/KG	Rabbit
	Inhalation	LC50	10 MG/L	Rat

#### **Carcinogenicity Category**

Component	Source	Code	Brief Description
N,N-Dioctyl-N,N-dimethylammonium chloride	N/E	N/E	N/E
Proprietary solvent	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

Aspiration Hazard: N/D





Comments: None.

# Section 12. Ecological Information

#### **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Bluegill Sunfish	48h	LC50	0.1 mg/l
Rainbow Trout	96h	LC50	0.7 mg/l
Daphnia magna	48h	EC50	0.1 mg/l

Persistence and Biodegradability:

N/D

biodegradability:

N/D

**Mobility In Soil:** 

N/D

Other Adverse Effects:

**Bioaccumulative Potential:** 

N/D

**Comments:** 

Based on active ingredient

# Section 13. Disposal Considerations

PESTICIDE DISPOSAL: Pesticide wastes are toxic. Improper disposal of excess pesticide, spray mixture, or rinsate is a violation of Federal Law. If these wastes cannot be disposed of by use according to label instructions, contact your State Pesticide or Environmental Control Agency, or the Hazardous Waste representative at the nearest EPA Regional Office for guidance.

CONTAINER DISPOSAL: Non-refillable container. Do not reuse or refill this container. Triple rinse or pressure rinse container (or equivalent) promptly after emptying. Then offer for recycling or reconditioning, or puncture and dispose of in a sanitary landfill, or by procedures approved by state and local authorities.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	UN1903	DISINFECTANTS, LIQUID,	(DIOCTYL DIMETHYL AMMONIUM	8	PGII
		CORROSIVE, N.O.S.	CHLORIDE)		
TDG	UN1903	DISINFECTANTS, LIQUID,	(DIOCTYL DIMETHYL AMMONIUM	8	PGII
		CORROSIVE, N.O.S.	CHLORIDE)		
IMDG	UN1903	DISINFECTANTS, LIQUID,	(DIOCTYL DIMETHYL AMMONIUM	8	PGII
		CORROSIVE, N.O.S.	CHLORIDE)		
ICAO	UN1903	DISINFECTANTS, LIQUID,	(DIOCTYL DIMETHYL AMMONIUM	8	PGII
		CORROSIVE, N.O.S.	CHLORIDE)		





Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

No
Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

**Other Sections** 

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
N,N-Dioctyl-N,N-dimethylammonium chloride	N/A	N/A	N/A
Proprietary solvent	N/A	N/A	N/A

Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
N,N-Dioctyl-N,N-dimethylammonium chloride	None.
Proprietary solvent	None.





#### **International Regulations**

Canada

WHMIS Classification: N/A

**Controlled Product Regulations** 

(CPR):

N/A

**Compliance Information** 

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

FIFRA: Registered pesticide under 40 CFR 152.10, Federal

Insecticide, Fungicide and Rodenticide Act (FIFRA),

EPA Registration Number: 6836-60-15300.

Other: None

Comments: None.

#### Section 16. Other Information

#### **HMIS Hazard Rating**

Health: 3
Flammability: 1
Physical Hazard: 0
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.





#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** May 9, 2016

### Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat CL5430
Product Use: Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information: (800)648–4579
Date of SDS: March 7, 2017
Revision Date: March 7, 2017
Revision Number: 17030701AN

# Section 2. Hazard(s) Identification

Signal Word: DANGER

**GHS Classification(s):** Skin corrosion/irritation – Category 1b

Eye damage/irritation – Category 1 Acute Toxicity Dermal – Category 4 Acute Toxicity Inhalation – Category 4 Acute Toxicity Oral – Category 4

Hazard Statement(s): H314 Causes severe skin burns and eye damage.

H312 Harmful in contact with skin.

H332 Harmful if inhaled. H302 Harmful if swallowed.

**Precautionary Statement(s):** 

**Prevention:** P260 Do not breathe dust/fume/gas/mist/vapors/spray.

P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P271 Use only outdoors or in a well–ventilated area. P280 Wear protective gloves/protective clothing/eye

protection/face protection.





**Response:** P301 + P312 IF SWALLOWED: Call a POISON

CENTER or doctor/physician if you feel unwell P301 + 330 + 331 IF SWALLOWED: Rinse mouth.

Do NOT induce vomiting.

P303 + P361 + P353 IF ON SKIN (or hair):

Remove/take off immediately all contaminated clothing.

Rinse skin with water/shower

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing P305 + P351 + P338 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P310 Immediately call a POISON CENTER/doctor. P363 Wash contaminated clothing before reuse.

**Storage:** P405 Store locked up.

**Disposal:** P501 Dispose of contents and container in accordance

with applicable local, regional, national, and/or

international regulations.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
1-Hydroxyethylidene-1,1-diphosphonic acid	2809–21–4	1 – 5
Phosphoric acid	7664–38–2	7 – 13
Benzotriazole	95–14–7	1 – 5

Comments

If chemical identity and/or exact percentage of composition has been withheld, this information is considered to be a trade secret.





### Section 4. First Aid Measures

**Inhalation:** Remove victim to fresh air and keep at rest in a position

comfortable for breathing. Immediately call a poison center or

doctor/physician.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. Immediately

call a poison center or doctor/physician.

**Skin:** Immediately remove/take off all contaminated clothing. Rinse skin

with water/shower. Wash contaminated clothing before re-use.

Immediately call a poison center or doctor/physician.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

Necessary:

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.





#### Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

**Methods for Cleaning up:**Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: If RQ (Reportable Quantity) is exceeded, report to National

Spill Response Office at 1–800–424–8802.

# Section 7. Handling and Storage

Handling: Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

**Store** Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Do not freeze. Store above Freeze Point. If freezes, then

mechanical mixing is required.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
1-Hydroxyethylidene-1,1-diphosphonic acid	N/E	N/E
Phosphoric acid	ACGIH TLV	3 mg/m³ STEL
	OSHA PEL	1 mg/m³ TWA
Benzotriazole	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Light Straw, Clear

Specific Gravity: 1.193 @ 20°C

pH: 1.2 @ 20°C, 100.0%

Freezing Point:

Flash Point:

N/D

Odor:

Mild

Melting Point:

N/A

Initial Boiling Point and Boiling Range:

Solubility in Water:

Evaporation Rate:

N/D

Vanor Density:

41°F

N/D

Mild

N/A

Initial Boiling Point and Boiling Range:

N/D

N/D

Vapor Density: N/D
Molecular Weight: N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas): N/D Flammable Limits: N/A Autoignition Temperature: N/A

**Density:** 9.95 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

**Substances:** 

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of nitrogen, Oxides of carbon, Oxides of phosphorus.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

#### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
1-Hydroxyethylidene-1,1-diphosphonic acid	Oral	LD50	2400 MG/KG	Rat
	Dermal	LD50	7940 MG/KG	Rabbit
Phosphoric acid	Dermal	LD50	2740 MG/KG	Rabbit
	Oral	LD50	1530 MG/KG	Rat
Benzotriazole	Oral	LD50	560 MG/KG	Rat
	Dermal	LD50	>2000 MG/KG	Rabbit

#### **Carcinogenicity Category**

Component	Source	Code	Brief Description
1-Hydroxyethylidene-1,1-diphosphonic acid	N/E	N/E	N/E
Phosphoric acid	N/E	N/E	N/E
Benzotriazole	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D





Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation**: N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

#### **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	2176 mg/l
Fathead Minnow	96h	I C50	3186 mg/l

Persistence and Biodegradability:

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.





### Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

EPA corrosivity characteristic hazardous waste D002 when disposed of in the original product form.

### Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	UN1760	CORROSIVE LIQUIDS, N.O.S.	(PHOSPHORIC ACID)	8	PGIII
IMDG	UN1760	CORROSIVE LIQUIDS, N.O.S.	(PHOSPHORIC ACID)	8	PGIII

Note: N/A

# Section 15. Regulatory Information

#### **Inventory Status**

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

#### **Federal Regulations**

#### **SARA Title III Rules**

**Sections 311/312 Hazard Classes** 

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
1-Hydroxyethylidene-1,1-diphosphonic acid	N/A	N/A	N/A
Phosphoric acid	No	N/A	5000
Benzotriazole	N/A	N/A	N/A





Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
1-Hydroxyethylidene-1,1-diphosphonic acid	None.
Phosphoric acid	MA, MN, NY, WA
Benzotriazole	None.

### **International Regulations**

Canada

WHMIS Classification: D2B (Toxic Material)

E (Corrosive Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.

**Compliance Information** 

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

FIFRA: N/A

Other: None

Comments: None.

### Section 16. Other Information

#### **HMIS Hazard Rating**

Health: 3
Flammability: 0
Physical Hazard: 1
PPE: X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** March 7, 2017

#### Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name:ChemTreat CL5570Product Use:Scale ControlSupplier's Name:ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648-4579Date of SDS:July 23, 2018Revision Date:July 23, 2018Revision Number:18072301AN

# Section 2. Hazard(s) Identification

Signal Word: DANGER

GHS Classification(s): Skin corrosion/irritation – Category 1b

Eye damage/irritation – Category 1 Acute Toxicity Oral – Category 4 Acute Toxicity Inhalation – Category 4

Carcinogenicity - Category 2

Specific Target Organ Toxicity - Repeated Exposure - Category

2

Corrosive to Metals – Category 1

**Hazard Statement(s):** H314 Causes severe skin burns and eye damage.

H318 Causes serious eye damage.

H302 Harmful if swallowed. H332 Harmful if inhaled.

H351 Suspected of causing cancer.

H373 May cause damage to organs through prolonged or repeated

exposure.

H290 May be corrosive to metals.

**Precautionary Statement(s):** 







**Prevention:** P234 Keep only in original packaging.

P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P260 Do not breathe dust/fume/gas/mist/vapors/spray. P271 Use only outdoors or in a well-ventilated area. P280 Wear protective gloves/protective clothing/eye

protection/face protection.

P201 Obtain special instructions before use.

P202 Do not handle until all safety precautions have

been read and understood.

**Response:** P390 Absorb spillage to prevent material damage.

P301 + P312 + P330 IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel

unwell. Rinse mouth.

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing

P312 Call a POISON CENTER or doctor/physician if

you feel unwell.

P301 + 330 + 331 IF SWALLOWED: Rinse mouth.

Do NOT induce vomiting.

P303 + P361 + P353 IF ON SKIN (or hair):

Remove/take off immediately all contaminated clothing.

Rinse skin with water/shower

P363 Wash contaminated clothing before reuse. P310 Immediately call a POISON CENTER/doctor.

P305 + P351 + P338 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P308 + P313 IF exposed or concerned: Get medical

advice/attention.

P314 Get medical advice/attention if you feel unwell.

**Storage:** P405 Store locked up.

P406 Store in a corrosive resistant container with a

resistant inner liner.

**Disposal:** P501 Dispose of contents and container in accordance

with applicable local, regional, national, and/or

international regulations.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Tolyltriazole, sodium salt	64665–57–2	1 – 5
Ethylene diamine tetraacetic acid, tetrasodium salt	64-02-8	1 – 5
Sodium hydroxide	1310-73-2	5 – 10

**Comments** 

If chemical identity and/or exact percentage of composition has been withheld, this information is considered to be a trade secret.

### Section 4. First Aid Measures

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

Eyes: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. Immediately

call a poison center or doctor/physician.

**Skin:** Immediately remove/take off all contaminated clothing. Rinse skin

with water/shower. Wash contaminated clothing before re-use.

Immediately call a poison center or doctor/physician.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

**Necessary:** 

N/A





# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

### Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and/or absorb spill with inert material then place in

suitable container.

Other Statements: If RQ (Reportable Quantity) is exceeded, report to National

Spill Response Office at 1–800–424–8802. Reportable Quantity of the product is 1471 Gal.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

**Store** Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Store above Freeze Point.





# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
Tolyltriazole, sodium salt	N/E	N/E
Ethylene diamine tetraacetic acid, tetrasodium salt	N/E	N/E
Sodium hydroxide	ACGIH TLV	2 mg/m³ Ceiling
	OSHA PEL	2 mg/m³ TWA

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear appropriate chemical resistant gloves.

Respiratory: If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Dark Straw, Clear

Specific Gravity: 1.164 @ 20°C

pH: 13.0 @ 20°C, 100.0%

Freezing Point: 28.4°F
Flash Point: N/A
Odor: Mild
Melting Point: N/D

Initial Boiling Point and Boiling Range: N/D
Solubility in Water: N/D
Evaporation Rate: N/D
Vapor Density: N/D
Molecular Weight: N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas): N/D
Flammable Limits: N/A
Autoignition Temperature: N/D

Density: 9.71 LB/GA





Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

Incompatibility with Various (

Substances:

Oxidizers, Reducing agents, Aluminum/aluminum alloys, Copper/copper

alloys, Strong acids.

**Hazardous Decomposition** 

**Products:** 

Oxides of nitrogen, Oxides of carbon.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
Tolyltriazole, sodium salt	Oral	LD50	920 MG/KG	Rat
	Dermal	LD50	>2 G/KG	Rabbit
Ethylene diamine tetraacetic acid, tetrasodium salt	Oral	LD50	3030 MG/KG	Rat
	Dermal	LD50	>5000 MG/KG	Rabbit
Sodium hydroxide	Oral	LD50	300 MG/KG	Rat
	Dermal	LD50	1350 MG/KG	Rabbit
ChemTreat CL5570	N/D	N/D	N/D	N/D

## **Carcinogenicity Category**

Component	Source	Code	Brief Description
Tolyltriazole, sodium salt	N/E	N/E	N/E
Ethylene diamine tetraacetic acid, tetrasodium salt	N/E	N/E	N/E
Sodium hydroxide	N/E	N/E	N/E

Likely Routes of Exposure: N/D





## **Symptoms**

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

Toxicity:

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
N/D	N/D	N/D	N/D

Persistence and N/D Biodegradability:

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D





Comments: Not tested.

# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations. EPA corrosivity characteristic hazardous waste D002 when disposed of in the original product form.

# Section 14. Transport Information

Controlling Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Packing Group:
DOT	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SODIUM HYDROXIDE AND	8	PGII
			SODIUM TOLYLTRIAZOLE)		
Over 1471 GA	RQ UN1760	CORROSIVE LIQUIDS, N.O.S.	(SODIUM HYDROXIDE AND	8	PGII
			SODIUM TOLYLTRIAZOLE)		

Note: N/A

## Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):

Canada (DSL/NDSL):

All ingredients listed or exempt.

All ingredients listed or exempt.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No
Yes





### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Tolyltriazole, sodium salt	N/A	N/A	N/A
Ethylene diamine tetraacetic acid, tetrasodium salt	N/A	N/A	N/A
Sodium hydroxide	N/A	N/A	1000

Comments: None.

## **State Regulations**

California Proposition 65: None known.

**Special Regulations** 

Component	States
Tolyltriazole, sodium salt	None.
Ethylene diamine tetraacetic acid, tetrasodium salt	None.
Sodium hydroxide	MA, MN, NY, PA, WA

## **Compliance Information**

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product is certified as kosher pareve.

Only when prepared by the following ChemTreat facilities:

Ashland, VA; Nederland, TX.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

## **HMIS Hazard Rating**

Health: 3
Flammability: 1
Physical Hazard: 0
PPE: X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: July 23, 2018

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name:ChemTreat CL5640Product Use:Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road Glen Allen, VA 23060

**Telephone Number for Information:** (800)648–4579 **Date of SDS:** June 27, 2017 **Revision Date:** June 27, 2017

Revision Number: June 27, 2017 17062701AN

# Section 2. Hazard(s) Identification

Signal Word: WARNING

GHS Classification(s): Eye damage/irritation – Category 2b

Acute Toxicity Dermal – Category 5 Acute Toxicity Inhalation – Category 5 Acute Toxicity Oral – Category 5

**Hazard Statement(s):** H320 Causes eye irritation.

H313 May be harmful in contact with skin.

H333 May be harmful if inhaled. H303 May be harmful if swallowed.

**Precautionary Statement(s):** 

**Prevention:** P264 Wash thoroughly after handling.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
2-Phosphono-1,2,4-butane tricarboxylic acid	37971–36–1	7 – 13

**Comments** If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

## Section 4. First Aid Measures

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

Eyes: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

**Skin:** Wash with plenty of soap and water. Call a poison center or

doctor/physician if you feel unwell.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician if you feel unwell.

Most Important Symptoms: N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

Necessary:

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.





**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
2-Phosphono-1,2,4-butane tricarboxylic acid	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Amber, Clear

Specific Gravity: 1.178 @ 20°C

pH: 3.1 @ 20°C, 100.0%

Freezing Point:

Flash Point:

Odor:

Mild

Melting Point:

Initial Boiling Point and Boiling Range:

Solubility in Water:

N/C

Complete

Evaporation Rate:

Vapor Density:

Molecular Weight:

N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas): N/D Flammable Limits: N/A Autoignition Temperature: N/A

**Density:** 9.82 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon, Oxides of nitrogen.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

## **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
2-Phosphono-1,2,4-butane tricarboxylic acid	Oral	LD50	>6500 MG/KG	Rat

## **Carcinogenicity Category**

Component	Source	Code	Brief Description
2-Phosphono-1,2,4-butane tricarboxylic acid	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation**: N/D





Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	1768 mg/l
Fathead Minnow	96h	LC50	>10000 mg/l

Persistence and

**Biodegradability:** 

N/D

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

## **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
2-Phosphono-1,2,4-butane tricarboxylic acid	N/A	N/A	N/A





Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
2-Phosphono-1,2,4-butane tricarboxylic acid	None.

### **International Regulations**

Canada

WHMIS Classification: D2B (Toxic Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.

**Compliance Information** 

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

### **HMIS Hazard Rating**

Health: 1
Flammability: 0
Physical Hazard: 0
PPE: X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** June 27, 2017

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: FlexPro CL5644

**Product Use:** Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648-4579Date of SDS:July 6, 2016Revision Date:July 6, 2016Revision Number:16070601AN

# Section 2. Hazard(s) Identification

Signal Word: WARNING

**GHS Classification(s):** Eye damage/irritation – Category 2b

Acute Toxicity Dermal – Category 5 Acute Toxicity Inhalation – Category 5 Acute Toxicity Oral – Category 5

**Hazard Statement(s):** H320 Causes eye irritation.

H313 May be harmful in contact with skin.

H333 May be harmful if inhaled. H303 May be harmful if swallowed.

**Precautionary Statement(s):** 

**Prevention:** P264 Wash thoroughly after handling.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Citric acid	77–92–9	5 – 10

**Comments** If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

## Section 4. First Aid Measures

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

Eyes: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

**Skin:** Wash with plenty of soap and water. Call a poison center or

doctor/physician if you feel unwell.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician if you feel unwell.

Most Important Symptoms: N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

Necessary:

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.





**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
Citric acid	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Amber, Clear

Specific Gravity: 1.292 @ 20°C

pH: 3.1 @ 20°C, 100.0%

Freezing Point: 27°F
Flash Point: N/A
Odor: Mild
Melting Point: N/A
Initial Boiling Point and Boiling Range: N/D
Solubility in Water: Complete

Evaporation Rate:N/DVapor Density:N/DMolecular Weight:N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas): N/D Flammable Limits: N/A Autoignition Temperature: N/A

Density: 10.78 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon, Oxides of nitrogen.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

## **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

## **Carcinogenicity Category**

Component	Source	Code	Brief Description
Citric acid	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation**: N/D





**Serious Eye Damage/Eye** 

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Mysid Shrimp	48h	LC50	>10000 mg/l
Inland Silverside	96h	LC50	5675 mg/l
Ceriodaphnia dubia	48h	LC50	1504 mg/l
Fathead Minnow	96h	LC50	2549 mg/l

Persistence and Biodegradability:

N/D

**Bioaccumulative Potential:** 

N/D

**Mobility In Soil:** 

N/D

Other Adverse Effects:

N/D

**Comments:** 

None.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

No
Release of Pressure:

No
Acute Health Hazard:

Chronic Health Hazard:

No

## **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Citric acid	N/A	N/A	N/A





Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
Citric acid	None.

### **International Regulations**

Canada

WHMIS Classification: D2B (Toxic Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.

**Compliance Information** 

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product is certified by the Orthodox Union as kosher

pareve.

Only when prepared by the following ChemTreat facilities:

Ashland, VA; Eldridge, IA; Nederland, TX.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

## **HMIS Hazard Rating**

Health: 1
Flammability: 0
Physical Hazard: 0
PPE: X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: July 6, 2016

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: FlexPro CL5737

**Product Use:** Cooling Water Treatment

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648–4579Date of SDS:October 3, 2017Revision Date:October 3, 2017Revision Number:17100301AN

# Section 2. Hazard(s) Identification



**GHS Classification(s):** Skin corrosion/irritation – Category 1a

Eye damage/irritation – Category 1 Acute Toxicity Dermal – Category 4 Acute Toxicity Oral – Category 4 Acute Toxicity Inhalation – Category 2 Corrosive to Metals – Category 1

Specific Target Organ Toxicity - Repeated Exposure - Category

2

**Hazard Statement(s):** H314 Causes severe skin burns and eye damage.

H318 Causes serious eye damage. H312 Harmful in contact with skin. H302 Harmful if swallowed.

H330 Fatal if inhaled.

H290 May be corrosive to metals.

H373 May cause damage to organs through prolonged or repeated

exposure.

**Precautionary Statement(s):** 





**Prevention:** P234 Keep only in original container.

P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P280 Wear protective gloves/protective clothing/eye

protection/face protection.

P260 Do not breathe dust/fume/gas/mist/vapors/spray. P271 Use only outdoors or in a well–ventilated area.

P284 Wear respiratory protection.

**Response:** P390 Absorb spillage to prevent material damage.

P301 + P312 IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell P302 + P352 IF ON SKIN: Wash with plenty of soap

and water.

P362 + P364 Take off contaminated clothing and wash

it before reuse.

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing

P310 Immediately call a POISON CENTER/doctor. P301 + 330 + 331 IF SWALLOWED: Rinse mouth.

Do NOT induce vomiting.

P303 + P361 + P353 IF ON SKIN (or hair):

Remove/take off immediately all contaminated clothing.

Rinse skin with water/shower

**Storage:** P406 Store in a corrosive resistant container with a

resistant inner liner.

P403 + P233 Store in a well-ventilated place. Keep

container tightly closed. P405 Store locked up.

**Disposal:** P501 Dispose of contents and container in accordance

with applicable local, regional, national, and/or

international regulations.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Citric acid	77–92–9	1 – 5
Sulfuric acid	7664–93–9	1 – 5

**Comments** 

If chemical identity and/or exact percentage of composition has been withheld, this information is considered to be a trade secret.

## Section 4. First Aid Measures

**Inhalation:** Remove victim to fresh air and keep at rest in a position

comfortable for breathing. Immediately call a poison center or

doctor/physician.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. Immediately

call a poison center or doctor/physician.

**Skin:** Immediately remove/take off all contaminated clothing. Rinse skin

with water/shower. Wash contaminated clothing before re-use.

Immediately call a poison center or doctor/physician.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

Necessary:

N/A





# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

Product may emit toxic gases or fumes under fire conditions.

Use water spray to keep containers cool.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

**Methods for Cleaning up:** Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: If RQ (Reportable Quantity) is exceeded, report to National

Spill Response Office at 1–800–424–8802. Reportable Quantity of the product is 3126 Gal.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.





Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Protect from heat and sources of ignition.

Do not store or handle in aluminum, steel, copper, or their alloys.

Store above Freeze Point.

# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
Citric acid	N/E	N/E
Sulfuric acid	ACGIH TLV	0.2 ppm TWA
	OSHA PEL	1 mg/m³ TWA; Aerosol

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Dark Straw, Clear Specific Gravity: 1.087 – 1.100 @ 20°C

pH: <1.0 @ 20°C, 100.0%

Freezing Point: 32°F
Flash Point: N/A
Odor: Mild
Melting Point: N/A





Initial Boiling Point and Boiling Range: ~225°F
Solubility in Water: Complete
Evaporation Rate: N/D
Vanor Pensity: N/D

**Vapor Density:** N/D **Molecular Weight:** N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas):

Flammable Limits:

Autoignition Temperature:

N/A

**Density:** 9.14 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

## Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various**Bases, Strong oxidizers, Alkali sensitive metals or alloys, Amines,

**Substances:** Metals or metal oxides, Nitrites.

**Hazardous Decomposition** 

**Products:** 

Hydrogen chloride, Chlorine.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

## **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
Sulfuric acid	Oral	LD50	2140 MG/KG	Rat
	Inhalation	LD50	375 MG/L	Rat
FlexPro CL5737	N/D	N/D	N/D	N/D





## **Carcinogenicity Category**

Component	Source	Code	Brief Description
Citric acid	N/E	N/E	N/E
Sulfuric acid	NTP	NTP-K	Known to be a human carcinogen

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation**: N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.





# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	2272 mg/l
Fathead Minnow	96h	LC50	>10000 mg/l

Persistence and

Biodegradability:

N/D

N/D

Bioaccumulative Potential:

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.

# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

EPA corrosivity characteristic hazardous waste D002 when disposed of in the original product form.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII
Over 3126 GA	UN1760	RQ CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII
TDG	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII
ICAO	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII
IMDG	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII
ANTT	UN1760	CORROSIVE LIQUIDS, N.O.S.	(SULFURIC ACID AND CITRIC ACID)	8	PGII

Note: N/A





# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No
Yes

### **Other Sections**

	Section 313 Toxic Chemical	Section 302 EHS TPQ	CERCLA RQ
Citric acid	N/A	N/A	N/A
Sulfuric acid	N/A	1000	1000

Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
Citric acid	None.
Sulfuric acid	MA. MN. NJ. NY. PA. WA





## **International Regulations**

#### Canada

WHMIS Classification: D2B (Toxic Material) E (Corrosive Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.

### **Compliance Information**

NSF: N/A

Food Regulations: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

### **HMIS Hazard Rating**

Health: 3
Flammability: 0
Physical Hazard: 1
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.





#### **Abbreviations**


Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** October 3, 2017

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





#### **Safety Data Sheet**





**HMIS** 

**PPE** 

E



IFPA

Preparation Date:

04/29/13

Revision Date: 04/07/16

### PRODUCT AND COMPANY IDENTIFICATION

Product Code
Product Name

DF 20 DF 20 Contact

Manufacturer

Sochem Solutions, Inc.

Industrial Cleaning Chemicals

P.O. Box 1912

Phone 225-644-3180

Gonzales, LA 70707

Emergency Telephone

Number

CHEMTREC: (Call 24 hours) 1-800-424-9300

Or for international calls dial 703-527-3887

Application of

Substance

(collect calls accepted)

(the preparation)

2.

### **HAZARDS IDENTIFICATION**

#### **Emergency Overview**



#### **HAZARD STATEMENTS:**

H315 Causes skin irritation.H320 Causes eye irritation.H301 Toxic if swallowed.

H332 Harmful if inhaled.

H317 May cause an allergic skin reaction.

## 3. COMPOSITION / INFORMATION ON HAZARDOUS INGREDIENTS

Chemical Name	CAS-No	Weight %	EINECS
			·

### Composition / Information on Ingredients Notes:

## All ingredients TSCA Listed

We are unaware of any restrictions due to Section 12 B of TSCA. 29CFR Part 1910, Sub part Z (OSHA) Toxic and Hazardous Substances Part 355, Appendix A (Extremely Hazardous Substances) EPA TLV for Chemical Substances Annual Report on Carcinogens

**Product Name:** 

**DF 20** 

Rev. Date: 04/07/16

FIRST AID MEASURES

**Skin Contact** 

Immediately flush skin with plenty of water for at least 15 minutes, while removing contaminated

clothing and shoes. Thoroughly clean clothing and shoes before reuse. Call a physician.

**Eye Contact** 

Immediately flush eyes with plenty of water for 15 minutes, while holding eyelids apart to ensure

flushing of entire surface. Call a physician.

**Inhalation** 

Remove to fresh air. If not breathing give artificial respiration, preferably mouth to mouth. If breathing

Is difficult give oxygen. Call a physician.

Ingestion

If swallowed, do not induce vomiting unless instructed by a physician or poison control. Never

give anything by mouth to an unconscious person. Call a physician or poison control center.

FIRE-FIGHTING MEASURES

**Special Protective Equipment** 

None.

**Suitable Extinguishing Media** 

Use extinguishing measures that are appropriate to local circumstances and the surrounding

environment.

6. ACCIDENTAL RELEASE MEASURES

**Personal Precautions** 

Wash thoroughly after handling.

**Precautions Environmental** 

This Product is biodegradable. Follow Federal, State and Local Regulations.

**Methods for Clean-up** 

Pick up with absorbent Material. Flush residue with plenty of water.

7. HANDLING AND STORAGE

Handling & Storage

Safe Handling Advice

Handle in accordance with good industrial hygiene and safety practice.

Storage

Keep container closed when not in use. Store in a cool dry place.

**Incompatible products** 

Strong oxidizing agent. Keep heat, sparks, and fire away.

Rev. Date: 04/07/16

## 8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Chemical Name	OSHA PEL	ACGIH TWA

#### Personal Protective Equipment

**Respiratory Protection** 

Not needed.

**Hand & Skin Protection** 

Wear protective gloves and clothing.

Face & Eye Protection

Wear suitable eye and face protection.

**General Hygiene Considerations** 

Wear suitable gloves, eye and face protection.

9. PHYSICAL AND CHEMICAL PROPERTIES					
Appearance	Creamy white liquid	Color	White		
Physical State	Liquid with pleasant odor	PH	7.5 – 8.0		
Flash Point	None	Auto ignition Temperature	None		
<b>Boiling Point/Range</b>	212 Degrees F	_			
Solubility	Dispersible in water	Vapor Density	Not available		
<b>Bulk Density</b>	8.18	Viscosity	Not available		

## 10. STABILITY AND REACTIVITY

**Chemical Stability** 

Stable.

**Incompatible Materials** 

Strong oxidizing agents. Inorganic acids and inorganic bases

**Hazardous Decomposition Products** 

Thermal decomposition or combustion can produce carbon monoxide.

**Hazardous Polymerization** 

Hazardous polymerization does not occur.

**Possibility of Hazardous Reactions** 

None under normal processing conditions

**Conditions to Avoid** 

None under normal use

Drov	luct	Nant	Hiller

**DF 20** 

Rev. Date: 04/07/16

11,

### TOXICOLOGICAL INFORMATION

**Local** effects None.

12.

#### **ECOLOGICAL INFORMATION**

Contains no substances known to be hazardous to the environment or not degradable in waste water treatment plants.

13.

## **DISPOSAL CONSIDERATIONS**

**Waste Disposal Method** 

The surfactants in this product are biodegradable. Follow Federal, State and Local regulations.

**Contaminated Packaging** 

Keep container closed when not in use.

**Further Information** 

Wash contaminated clothing before reuse.

14.

### TRANSPORT INFORMATION

DOT

**Proper Shipping Name** 

NR COMPOUNDS, CLEANING, LIQUID, NON- REGULATED

**Hazard Class UN-Number Packing Group** 

Reportable Quantity (RQ)

**ERG Code** 

15.

### **REGULATORY INFORMATION**

Contains no SARA re portables

### **U.S.** Inventories

Chemical Name	TSCA	NJRTK	MRTKL	PARTK

## International Inventories

	Chemical Name	TSCA	DSL	EINECS	ENCS	IECSC	KECL	PICCS	AICS
Γ									

16.

# OTHER INFORMATION













NFPA

HMIS
Preparation Date:

08/20/14

Revision Date: 08/06/15

## 1. PRODUCT AND COMPANY IDENTIFICATION

Product Code
Product Name

FFC1

Contact

Manufacturer

Fin Foam 225-673-2630

3500 Delta Industrial

St. Gabriel, LA 70776

Industrial Cleaning Chemicals

Emergency Telephone

Number

2.

CHEMTREC: (Call 24 hours) 1-800-424-9300

Or for international calls dial 703-527-3887

(collect calls accepted)

Fin Foamer Concentrate 1

Application of

Substance

(the preparation)

#### HAZARDS IDENTIFICATION

## **Emergency Overview**



**HAZARD STATEMENTS:** 

None

## 3. COMPOSITION / INFORMATION ON HAZARDOUS INGREDIENTS

Chemical Name	CAS-No	Weight %	EINECS
Propylene glycol n-Propyl Ether (PNP)	1569-01-3	<20	

#### **Composition / Information on Ingredients Notes:**

No component of this product is subject to SARA 313 reporting requirements. We are unaware of any restrictions due to Section 12 B of TSCA. 29CFR Part 1910, Subpart Z (OSHA) Toxic and Hazardous Substances Part 355, Appendix A (Extremely Hazardous Substances) EPA TLV for Chemical Substances Annual Report on Carcinogens

Product Name:

**Fin Foamer Concentrate 1** 

Rev. Date: 08/06/15

4.

**FIRST AID MEASURES** 

**Skin Contact** 

Wash off immediately with soap and plenty of water removing all contaminated clothes and shoes.

**Eye Contact** 

Flush with copious amounts of water for 15 minutes, consult a physician.

Inhalation

Remove person from exposure to fresh air. If person is not breathing, call 911 or an ambulance and then give artificial respiration (CPR). If person is breathing, but with difficulty, get immediate medical

attention.

Ingestion

Drink large quantity of water and consult a physician.

5.

**FIRE-FIGHTING MEASURES** 

**Special Protective Equipment** 

Although water soluble, it may not be practical to extinguish fire by water dilution. Blanket fire

with fire fighting foam.

Suitable Extinguishing Media

Use extinguishing measures that are appropriate to local circumstances and the surrounding

environment.

6.

**ACCIDENTAL RELEASE MEASURES** 

**Personal Precautions** 

Wash contaminated clothing before reuse.

**Precautions Environmental** 

Avoid direct discharge to natural waterways.

**Methods for Clean-up** 

Confine spread of spill. Absorb with sand or inert material and abide by all local, state, and federal

regulations for disposal. Material may initially gel or solidify on contact with water.

7.

HANDLING AND STORAGE

Handling & Storage

Safe Handling Advice

Handle in accordance with good industrial hygiene and safety practice. Apron and/or chemical resistant

clothing, boots, safety glasses and nitrile gloves are recommended upon conditions of use.

Storage

Spilled material is slippery on walkways and highways. Can foam when hit with a stream of water.

Store in plastic, plastic lined steel, tightly closed containers at temperatures between 40 and 100

Degrees F.

Incompatible products

No information available.

**Product Name:** 

**Fin Foamer Concentrate 1** 

## B. EXPOSURE CONTROLS / PERSONAL PROTECTION

Chemical Name	OSHA PEL	ACGIH TWA
Propylene glycol n-Propyl Ether (PNP)	N/A	N/A

Rev. Date: 08/06/15

#### Personal Protective Equipment

**Respiratory Protection** 

Maintain adequate ventilation.

**Hand & Skin Protection** 

Wear protective gloves and clothing.

Face & Eye Protection

Wear suitable eye and face protection.

**General Hygiene Considerations** 

Wear suitable gloves, eye and face protection.

PHYSICAL AND CHEMICAL PROPERTIES					
Appearance	Clear liquid	Color	Clear		
Physical State	Liquid	pH	6.0 to 9.0		
Flash Point	None	Autoignition Temperature	None		
Boiling Point/Range	283 Degrees F	and and a state of the state of			
Solubility	Complete in water	Vapor Density	Not available		
Bulk Density	8.6	Viscosity	Not available		

## 10. STABILITY AND REACTIVITY

**Chemical Stability** 

Stable.

**Incompatible Materials** 

Strong oxidizer, dehydrating agents, or acids.

**Hazardous Decomposition Products** 

None under normal use.

**Hazardous Polymerization** 

Hazardous polymerization does not occur.

**Possibility of Hazardous Reactions** 

None under normal processing conditions

**Conditions to Avoid** 

None under normal use

Product	81

Fin Foamer Concentrate 1

Rev. Date: 08/06/15

11.

### **TOXICOLOGICAL INFORMATION**

**Local effects** 

This product is a skin irritant and moderately toxic by ingestion.

12.

### **ECOLOGICAL INFORMATION**

Contains no substances know to be hazardous to the environment or not degradable in waster water treatment plants.

13.

### **DISPOSAL CONSIDERATIONS**

**Waste Disposal Method** 

The surfactants in this product are biodegradable. Follow Federal, State and Local regulations.

**Contaminated Packaging** 

Keep container closed when not in use.

**Further Information** 

Wash contaminated clothing before reuse.

14.

## TRANSPORT INFORMATION

DOT

**Proper Shipping Name** 

NR COMPOUNDS, CLEANING, LIQUID, NON-REGULATED

Hazard Class UN-Number Packing Group

Reportable Quantity (RQ)

**ERG Code** 

#### 15.

### **REGULATORY INFORMATION**

Contains no SARA re-portables.

### **U.S.** Inventories

Chemical Name	TSCA	NJRTK	MRTKL	PARTK
Propylene glycol n-Propyl Ether (PNP)	N/A	N/A	N/A	N/A

### **International Inventories**

Chemical Name	TSCA	DSL	EINECS	ENCS	IECSC	KECL	PICCS	AICS
Propylene glycol n-Propyl Ether (PNP)								
<u>_</u>								

116	OTHER INCORMATION
16.	OTHER INFORMATION

**End of SDS** 













**NFPA** 

225-673-2630

**HMIS** Preparation Date:

08/20/14

Revision Date: 08/07/15

### PRODUCT AND COMPANY IDENTIFICATION

**Product Code** 

**FFCLC** 

Contact

**Product Name** 

Fin Foamer Concentrate LC

Manufacturer

Fin Foam

3500 Delta Industrial

St. Gabriel, LA 70776

Industrial Cleaning Chemicals

**Emergency Telephone** 

CHEMTREC: (Call 24 hours) 1-800-424-9300

Or for international calls dial 703-527-3887

**Application of** 

Substance

(the preparation)

Number

2.

3.

(collect calls accepted)

## HAZARDS IDENTIFICATION

## **Emergency Overview**



## **HAZARD STATEMENTS:**

Causes mild skin irritation. H316 May be harmful if swallowed. H303

### **COMPOSITION / INFORMATION ON HAZARDOUS INGREDIENTS**

Chemical Name	CAS-No	Weight %	EINECS
Propylene glycol n-Propyl Ether (PNP)	1569-01-3	<20	

#### Composition / Information on Ingredients Notes:

No component of this product is subject to SARA 313 reporting requirements. We are unaware of any restrictions due to Section 12 B of TSCA. 29CFR Part 1910, Subpart Z (OSHA) Toxic and Hazardous Substances Part 355, Appendix A (Extremely Hazardous Substances) EPA TLV for Chemical Substances Annual Report on Carcinogens

Product Name: Fin Foamer Concentrate LC Rev. Date: 08/07/15

I. FIRST AID MEASURES

Skin Contact Wash off immediately with soap and plenty of water removing all contaminated clothes and shoes.

Eye Contact Flush with copious amounts of water for 15 minutes, consult a physician.

Inhalation Remove person from exposure to fresh air. If person is not breathing, call 911 or an ambulance and

then give artificial respiration (CPR). If person is breathing, but with difficulty, get immediate medical

attention.

**Ingestion** Drink large quantity of water and consult a physician.

5. FIRE-FIGHTING MEASURES

Special Protective Equipment Although water soluble, it may not be practical to extinguish fire by water dilution. Blanket fire

with fire fighting foam.

Suitable Extinguishing Media

Use extinguishing measures that are appropriate to local circumstances and the surrounding

environment.

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions Wash contaminated clothing before reuse.

Precautions Environmental Avoid direct discharge to natural waterways.

Methods for Clean-up Confine spread of spill. Absorb with sand or inert material and abide by all local, state, and federal

regulations for disposal. Material may initially gel or solidify on contact with water.

7. HANDLING AND STORAGE

Handling & Storage

Safe Handling Advice Handle in accordance with good industrial hygiene and safety practice. Apron and/or chemical resistant

clothing, boots, safety glasses and nitrile gloves are recommended upon conditions of use.

Storage Spilled material is slippery on walkways and highways. Can foam when hit with a stream of water.

Store in plastic, plastic lined steel, tightly closed containers at temperatures between 40 and 100

Degrees F.

Incompatible products No information available.

**Product Name:** 

Fin Foamer Concentrate LC

## **EXPOSURE CONTROLS / PERSONAL PROTECTION**

Chemical Name	OSHA PEL	ACGIH TWA
Propylene glycol n-Propyl Ether (PNP)	N/A	N/A

Rev. Date: 08/07/15

### Personal Protective Equipment

**Respiratory Protection** 

Maintain adequate ventilation.

**Hand & Skin Protection** 

Wear protective gloves and clothing.

Face & Eye Protection

Wear suitable eye and face protection.

**General Hygiene Considerations** 

Wear suitable gloves, eye and face protection.

9. PHYSICAL AND CHEMICAL PROPERTIES					
Appearance	Clear liquid	Color	Clear		
Physical State	Liquid	pH	6.0 to 9.0		
Flash Point	None	Autoignition Temperature	None		
Boiling Point/Range	283 Degrees F				
Solubility	Complete in water	Vapor Density	Not available		
Bulk Density	8.6	Viscosity	Not available		

#### 10. STABILITY AND REACTIVITY

**Chemical Stability** 

Stable.

**Incompatible Materials** 

Strong oxidizer, dehydrating agents, or acids.

**Hazardous Decomposition Products** 

None under normal use.

**Hazardous Polymerization** 

Hazardous polymerization does not occur.

**Possibility of Hazardous Reactions** 

None under normal processing conditions

**Conditions to Avoid** 

None under normal use

Dre	odu	4	N:	 ٥.

**Fin Foamer Concentrate LC** 

Rev. Date: 08/07/15

### 11.

## TOXICOLOGICAL INFORMATION

Local effects

This product is a skin irritant and moderately toxic by ingestion.

### 12.

## **ECOLOGICAL INFORMATION**

Contains no substances know to be hazardous to the environment or not degradable in waster water treatment plants.

### 13.

### **DISPOSAL CONSIDERATIONS**

**Waste Disposal Method** 

The surfactants in this product are biodegradable. Follow Federal, State and Local regulations.

**Contaminated Packaging** 

Keep container closed when not in use.

**Further Information** 

Wash contaminated clothing before reuse.

### 14.

## TRANSPORT INFORMATION

#### DOT

**Proper Shipping Name** 

NR COMPOUNDS, CLEANING, LIQUID, NON- REGULATED

Hazard Class UN-Number Packing Group

Reportable Quantity (RQ)

**ERG Code** 

## 15.

### **REGULATORY INFORMATION**

Contains no SARA re-portables.

#### **U.S.** Inventories

Chemical Name	TSCA	NJRTK	MRTKL	PARTK
Propylene glycol n-Propyl Ether (PNP)	N/A	N/A	N/A	N/A

## **International Inventories**

Chemical Name	TSCA	DSL	EINECS	ENCS	IECSC	KECL	PICCS	AICS
Propylene glycol n-Propyl Ether (PNP)								

## 16. OTHER INFORMATION

End of SDS





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

**Product Name:** ChemTreat FO120

**Product Use:** Defoamer Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** 

(800)424-9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

**Telephone Number for Information:** (800)648-4579 Date of SDS: July 23, 2018 **Revision Date:** July 23, 2018 18072301AN **Revision Number:** 

# Section 2. Hazard(s) Identification

Signal Word: WARNING

GHS Classification(s): Eye damage/irritation - Category 2a

Skin corrosion/irritation - Category 2 Acute Toxicity Oral - Category 5

**Hazard Statement(s):** H319 Causes serious eve irritation.

H315 Causes skin irritation.

H303 May be harmful if swallowed.

**Precautionary Statement(s):** 

**Prevention:** P264 Wash thoroughly after handling.

P270 Do not eat, drink, or smoke when using this product. P280 Wear protective gloves/protective clothing/eye

protection/face protection.

Response: P301 + P312 IF SWALLOWED: Call a POISON

CENTER or doctor/physician if you feel unwell

P330 Rinse mouth.

P302 + P352 IF ON SKIN: Wash with plenty of soap

and water.

P305 + P351 + P338 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P337 + P313 If eye irritation persists, get medical

advice/attention.







Storage: P402 Store in a dry place.

Disposal: P501 Dispose of contents and container in accordance

with applicable local, regional, national, and/or

international regulations.

**System of Classification Used:** Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Alcohols, C16–18, Ethoxylated Propoxylated	68002-96-0	1 – 5

**Comments** If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

# Section 4. First Aid Measures

Inhalation: Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

Eves: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

Skin: Wash with plenty of soap and water. Take off contaminated clothing

and wash before re-use. If skin irritation occurs, seek medical

advice/attention.

DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON Ingestion:

CENTER or doctor/physician if you feel unwell.

**Most Important Symptoms:** N/D

Indication of Immediate **Medical Attention and** Special Treatment Needed, If

**Necessary:** 

N/A





# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

**Methods for Cleaning up:**Contain and/or absorb spill with inert material then place in

suitable container.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Do not freeze. Store above Freeze Point. If freezes, then product

is unusable.

Protect from heat and sources of ignition.





# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
Alcohols, C16–18, Ethoxylated Propoxylated	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain guick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid Emulsion, White, Opaque

Specific Gravity: 0.992 @ 20°C

 pH:
 N/A

 Freezing Point:
 37°F

 Flash Point:
 >200°F

 Odor:
 Mild

 Melting Point:
 N/A

Initial Boiling Point and Boiling Range: 212°F
Solubility in Water: Dispersible

Evaporation Rate:>1Vapor Density:N/DMolecular Weight:N/D

**Viscosity:** 150 – 1500 CPS @ 20°C

Flammability (solid, gas):

Flammable Limits:

N/A

Autoignition Temperature:

N/A

Density: 8.27 LB/GA





Vapor Pressure:N/A% VOC:15.4Odor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Excessive heat.

**Hazardous Decomposition** 

**Products:** 

Carbon dioxide, Carbon monoxide.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

## **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Alcohols, C16–18, Ethoxylated Propoxylated	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D





Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye N/D

Irritation:

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

### **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Fathead Minnow	96h	LC50	181.841 mg/l
Ceriodaphnia dubia	48h	LC50	76.188 mg/l
Mysid Shrimp	48h	LC50	659 mg/l
Inland Silverside	96h	LC50	733 mg/l

Persistence and N/D Biodegradability:

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ICAO	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
SCT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA): Canada (DSL/NDSL):

All ingredients listed. All ingredients listed.





## **Federal Regulations**

#### **SARA Title III Rules**

Sections 311/312 Hazard Classes

> Fire Hazard: No **Reactive Hazard:** No Release of Pressure: No **Acute Health Hazard:** Yes **Chronic Health Hazard:** No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Alcohols, C16–18, Ethoxylated Propoxylated	N/A	N/A	N/A

Comments: None.

## **State Regulations**

**California Proposition 65:** None known.

**Special Regulations** 

Component	States
Alcohols, C16–18, Ethoxylated Propoxylated	None.

## **Compliance Information**

NSF: N/A

Food Regulations: FDA: Complies with 21 CFR 176.170 and 21 CFR

176.180 for use in paper and paperboard which contacts

food.

FDA: All ingredients in this product are authorized in 21 CFR 173.340 for use as "Defoaming Agents" where the treated water may contact food.

**KOSHER:** This product has not been evaluated for Kosher approval.

Halal: This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

**Comments:** None.





# Section 16. Other Information

## **HMIS Hazard Rating**

Health: 1
Flammability: 1
Physical Hazard: 0
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.

## **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: July 23, 2018





# Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat FO180

Product Use: Defoamer

Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648-4579Date of SDS:August 27, 2018Revision Date:August 27, 2018Revision Number:18082701AN

# Section 2. Hazard(s) Identification

Signal Word: None

GHS Classification(s): Non-Hazardous Substance

Hazard Statement(s): Non-Hazardous Substance

**Precautionary Statement(s):** No significant health risks are expected from exposures under

normal conditions of use.

**Prevention:** None.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Components not listed are either non hazardous or in concentration of	N/A	N/A
less than 1%		

Comments If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

# Section 4. First Aid Measures

Inhalation: Call a POISON CENTER or doctor/physician if you feel unwell.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

**Skin:** Call a poison center or doctor/physician if you feel unwell.

**Ingestion:** Rinse mouth. Call a poison center or doctor/physician if you feel

unwell.

**Most Important Symptoms:** N/D

Indication of Immediate
Medical Attention and
Special Treatment Needed, If

**Necessary:** 

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

Use water spray to keep containers cool.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.





## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Do not freeze. Store above Freeze Point. If freezes, then product

is unusable.

# Section 8. Exposure Controls/Personal Protection

## **Exposure Limits**

Component	Source	Exposure Limits
Components not listed are either non hazardous or in	N/E	N/E
concentration of less than 1%		

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Safety glasses are recommended if risk of eye contact.

**Skin:** Wear butyl rubber or neoprene gloves. Wash them after

each use and replace as necessary. If conditions warrant,

wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** None needed under normal conditions of use.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid Emulsion, White, Opaque

Specific Gravity: 0.981 @ 20°C

**pH:** 7.1 @ 20°C, 100.0%

Freezing Point: 32°F
Flash Point: N/D
Odor: Mild
Melting Point: N/A
Initial Boiling Point and Boiling Range: N/D

Solubility in Water: Appreciable

Evaporation Rate:N/DVapor Density:N/DMolecular Weight:N/D

**Viscosity:** 150 – 500 CPS @ 20°C

Flammability (solid, gas):

Flammable Limits:

N/A

Autoignition Temperature:

N/A

**Density:** 8.18 LB/GA

Vapor Pressure:N/D% VOC:0Odor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** Acids, Halogens, Bases.

**Substances:** 

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon.





**Possibility of Hazardous** 

None known.

Reactions:

Reactivity:

N/D

**Conditions To Avoid:** 

N/D

# Section 11. Toxicological Information

## **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

# **Carcinogenicity Category**

Component	Source	Code	Brief Description
Components not listed are either non hazardous or in	N/E	N/E	N/E
concentration of less than 1%			

**Likely Routes of Exposure:** N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye N/D

Irritation:

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

N/D

**Toxicity:** 





**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Fathead Minnow	96h	LC50	3405.5 mg/l
Ceriodaphnia dubia	7d	IC25	4.42 mg/l
	7d	NOEC	2.5 mg/l
	48h	LC50	1768 mg/l
	7d	LOEC	5 mg/l

Persistence and N/D

Biodegradability:

**Bioaccumulative Potential:** N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: None.

# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.





# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ICAO	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

Inventory	<b>Status</b>
-----------	---------------

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

## **Federal Regulations**

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

No
Release of Pressure:

No
Acute Health Hazard:

No
Chronic Health Hazard:

No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Components not listed are either non hazardous or in	N/A	N/A	N/A
concentration of less than 1%			

Comments: None.





### **State Regulations**

California Proposition 65: This product contains chemical(s) known to the State of

California to cause cancer and/or to cause birth defects or

other reproductive harm: Ethylene Oxide, CAS

#75-21-8, <=20.0ppm.

This product contains chemical(s) known to the State of California to cause cancer and/or to cause birth defects or

other reproductive harm: Propylene oxide, CAS

#75-56-9.

### **Special Regulations**

Component	States
Components not listed are either non hazardous or in	None.
concentration of less than 1%	

## **Compliance Information**

NSF: N/A

Food Regulations: FDA: Complies with 21 CFR 176.170 and 21 CFR

176.180 for use in paper and paperboard which contacts

food.

FDA: All ingredients in this product are authorized in

21 CFR 176.210.

**KOSHER:** This product has not been evaluated for Kosher approval.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None

Comments: None.

# Section 16. Other Information

## **HMIS Hazard Rating**

Health: 1
Flammability: 0
Physical Hazard: 0
PPE: X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** August 27, 2018

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat FO220

Product Use: Defoamer Supplier's Name: ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648–4579Date of SDS:July 23, 2018Revision Date:July 23, 2018Revision Number:18072301AN

# Section 2. Hazard(s) Identification

Signal Word: DANGER

GHS Classification(s): Aspiration Hazard – Category 1

Specific Target Organ Toxicity - Single Exposure - Category 3

**Hazard Statement(s):** H304 May be fatal if swallowed and enters airways.

H335 May cause respiratory irritation.

**Precautionary Statement(s):** 

**Prevention:** P264 Wash thoroughly after handling.

P280 Wear protective gloves/protective clothing/eye

protection/face protection.

P260 Do not breathe dust/fume/gas/mist/vapors/spray.

P243 Take action to prevent static discharges.

P210 Keep away from heat, hot surfaces, sparks, open

flames and other ignition sources. No smoking.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).





Hazards Not Otherwise Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Polydimethylsiloxane	63148-62-9	10 – 40
Petroleum distillate hydrotreated light	64742–47–8	< 10
Silicon dioxide	112926-00-8	< 5

**Comments** 

If chemical identity and/or exact percentage of composition has been withheld, this information is considered to be a trade secret.

# Section 4. First Aid Measures

**Inhalation:** Remove victim to fresh air and keep at rest in a position

comfortable for breathing. Immediately call a poison center or

doctor/physician.

Eyes: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

**Skin:** Wash with plenty of soap and water. Call a poison center or

doctor/physician if you feel unwell.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Immediately call a

POISON CENTER or doctor/physician.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If

**Necessary:** 

N/A





# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

None known.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

**Methods for Cleaning up:** Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Protect from heat and sources of ignition.

Do not freeze. Store above Freeze Point. If freezes, then product

is unusable.





# Section 8. Exposure Controls/Personal Protection

### **Exposure Limits**

Component	Source	Exposure Limits
Polydimethylsiloxane	N/E	N/E
Petroleum distillate hydrotreated light	ACGIH TLV	200 mg/m³ TWA
	NIOSH	10 mg/m³ STEL
Silicon dioxide	OSHA PEL	80 mg/m³ STEL

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid Emulsion, White, Opaque

Specific Gravity: 1.009 @ 20°C

pH: N/A Freezing Point: 32°F

Flash Point: >200°F
Odor: Mild
Melting Point: N/A
Initial Boiling Point and Boiling Range: >212°F

Solubility in Water:

Evaporation Rate:

Vapor Density:

Solubility in Water:

Lighter than air

Molecular Weight: N/D

Viscosity: 600 – 2000 CPS @ 20°C

Flammability (solid, gas): N/D





**Flammable Limits:** N/A **Autoignition Temperature:** N/A

**Density:** 8.42 LB/GA **Vapor Pressure:** Similar to water

% VOC:

Odor Threshold

n-octanol Partition Coefficient

Decomposition Temperature

N/D

N/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Excessive heat.

**Hazardous Decomposition** 

**Products:** 

Carbon dioxide, Carbon monoxide.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Polydimethylsiloxane	N/E	N/E	N/E
Petroleum distillate hydrotreated light	N/E	N/E	N/E
Silicon dioxide	N/E	N/E	N/E

Likely Routes of Exposure: N/D





## **Symptoms**

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

Skin Corrosion/Irritation: N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	7878 mg/l
Fathead Minnow	96h	LC50	4204 mg/l
	48h	LC50	4665 mg/l
Daphnia pulex	48h	LC50	>10000 mg/l

Persistence and Biodegradability:

N/D

Bioaccumulative Potential:

N/D

**Mobility In Soil:** 

N/D





Other Adverse Effects: N/D

Comments: None.

# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ICAO	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ANTT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.





### **Federal Regulations**

#### **SARA Title III Rules**

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Polydimethylsiloxane	N/A	N/A	N/A
Petroleum distillate hydrotreated light	N/A	N/A	N/A
Silicon dioxide	N/A	N/A	N/A

Comments: None.

#### **State Regulations**

California Proposition 65: None known.

**Special Regulations** 

Component	States
Polydimethylsiloxane	None.
Petroleum distillate hydrotreated light	None.
Silicon dioxide	ID, MA, WA

### **Compliance Information**

NSF: N/A

**Food Regulations:** FDA: All ingredients in this product are authorized in

21 CFR 173.340 for use as "Defoaming Agents"

where the treated water may contact food.

**KOSHER:** This product has not been evaluated for Kosher approval.

**Halal:** This product has not been evaluated for Halal approval.

FIFRA: N/A

Other: None





Comments: None.

## Section 16. Other Information

### **HMIS Hazard Rating**

Health: 1
Flammability: 1
Physical Hazard: 0
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: July 23, 2018





## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat P873L

**Product Use:** Water Clarification Agent

**Supplier's Name:** ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

**Telephone Number for Information:** (800)648–4579 **Date of SDS:** August 25, 2016

Revision Date: August 25, 2016 Revision Number: 16082501AN

## Section 2. Hazard(s) Identification

Signal Word: None

GHS Classification(s): Non-Hazardous Substance

Hazard Statement(s): Non-Hazardous Substance

**Precautionary Statement(s):** No significant health risks are expected from exposures under

normal conditions of use.

**Prevention:** None.

Response: None.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Components not listed are either non hazardous or in concentration of	N/A	N/A
less than 1%		

Comments If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

## Section 4. First Aid Measures

Inhalation: Call a POISON CENTER or doctor/physician if you feel unwell.

Eyes: Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.

Skin: Call a poison center or doctor/physician if you feel unwell.

Rinse mouth. Call a poison center or doctor/physician if you feel Ingestion:

unwell.

**Most Important Symptoms:** N/D

Indication of Immediate **Medical Attention and** 

Special Treatment Needed, If

Necessary:

N/A

# Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

Use water spray or fog.

Firefighting foam Carbon Dioxide **Dry Chemical** 





Specific Hazards Arising from

the Chemical:

Use water spray to keep containers cool.

Carbon oxides, nitrogen oxides, hydrogen chloride, hydrogen cyanide may be product in the event of combustion in an oxygen deficient

atmosphere.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

Personal Precautions: Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and/or absorb spill with inert material then place in

suitable container.

Material is very slippery if spilled.

Other Statements: None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

**Store** Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

Do not freeze. Store above Freeze Point. If freezes, then

mechanical mixing is required.





## Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
Components not listed are either non hazardous or in	N/E	N/E
concentration of less than 1%		

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

Eyes: Safety glasses are recommended if risk of eye contact.

**Skin:** Wear butyl rubber or neoprene gloves. Wash them after

each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Light Straw, Clear

Specific Gravity: 1.042 @ 20°C

**pH:** 5.9 @ 20°C, 100.0%

Freezing Point: 30°F
Flash Point: N/D
Odor: Mild
Melting Point: N/A
Initial Boiling Point and Boiling Range: 212°F
Solubility in Water: Soluble

**Evaporation Rate:** N/D **Vapor Density:** Similar to water

Molecular Weight:N/DViscosity:N/AFlammability (solid, gas):N/DFlammable Limits:N/AAutoignition Temperature:N/A

**Density:** 8.69 LB/GA **Vapor Pressure:** Similar to water





% VOC: 0
Odor Threshold N/D
n-octanol Partition Coefficient N/D
Decomposition Temperature N/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon, Oxides of nitrogen, Hydrogen chloride, Hydrogen

cyanide.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D

# Section 11. Toxicological Information

### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
ChemTreat P873L	Oral	LD50	>5000 MG/KG	Rat
	Dermal	LD50	>5000 MG/KG	Rat

### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Components not listed are either non hazardous or in	N/E	N/E	N/E
concentration of less than 1%			

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D





Ingestion: N/D

**Skin Corrosion/Irritation:** N/D

Serious Eye Damage/Eye

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

**Toxicity:** 

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D

Comments: None.

# Section 12. Ecological Information

#### **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Fathead Minnow	96h	LC50	2.253 mg/l
Ceriodaphnia dubia	48h	LC50	0.473 mg/l

Persistence and Biodegradability:

N/D

Bioaccumulative Potential: N/D

Mobility In Soil: N/D

Other Adverse Effects: N/D

Comments: Water clarification polymers function by multipoint adsorption and

charge neutralization with suspended solids. Polymers inherently migrate with solids in the separation process and with the exception of uneconomic overdose do not remain in the clarified waters. Aquatic toxicity determinations in test method protocol waters without suspended solids overestimate the toxicity compared to

natural receiving waters.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations. Not a RCRA–regulated hazardous waste when disposed in the original product form.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
ICAO	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA): Canada (DSL/NDSL): All ingredients listed. All ingredients listed.





## **Federal Regulations**

### **SARA Title III Rules**

**Sections 311/312 Hazard Classes** 

Fire Hazard:

Reactive Hazard:

Release of Pressure:

No
Acute Health Hazard:

No
Chronic Health Hazard:

No

### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Components not listed are either non hazardous or in	N/A	N/A	N/A
concentration of less than 1%			

Comments: None.

## **State Regulations**

California Proposition 65: None known.

## **Special Regulations**

Component	States
Components not listed are either non hazardous or in	None.
concentration of less than 1%	

## **International Regulations**

#### Canada

WHMIS Classification: N/A

Controlled Product Regulations N/A

(CPR):





### **Compliance Information**

NSF:	Certified to NSF/ANSI Standard 60

Maximum use rate for potable water - 50 mg/L

This product ships as NSF from:

Ashland, VA Eldridge, IA Nederland, TX Facility #2 USA Facility #3 USA

**Food Regulations:** FDA: All ingredients in this product are authorized in

21 CFR 176.170 and 21 CFR 176.180. FDA: GRAS, 21 CFR 570.30 – Generally

Recognized as Safe by experts in accordance with the Federal Food, Drug and Cosmetic Act (Section 201s) for their intended use as flocculants and dewatering aids for food processing waste destined for recycling as animal

feed, and is subject to the limitations therein.

**KOSHER:** This product is certified as Kosher for Passover and

year-round use.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

### **HMIS Hazard Rating**

Health: 0
Flammability: 0
Physical Hazard: 0
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for

their use.





#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** August 25, 2016

## Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

**Product Name:** ChemTreat P893L

Product Use: Water Clarification Agent

**Supplier's Name:** ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

**Address (Corporate Headquarters):** 5640 Cox Road

Glen Allen, VA 23060

**Telephone Number for Information:** (800)648–4579 **Date of MSDS:** September 14, 2015 **Revision Date:** September 14, 2015

**Revision Number:** 15091401AN

# Section 2. Hazard(s) Identification

Signal Word: WARNING

**GHS Classification(s):** Acute Toxicity Dermal – Category 5

Acute Toxicity Inhalation - Category 5

Acute Toxicity Oral – Category 5

Hazardous to the aquatic environment Acute – Category 2

**Hazard Statement(s):** May be harmful in contact with skin.

May be harmful if inhaled. May be harmful if swallowed.

Toxic to aquatic life.

**Precautionary Statement(s):** Avoid release into the environment.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

**Classified:** 

None.





# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Polyaluminum chloride	1327-41-9	60 – 100

**Comments** If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

## Section 4. First Aid Measures

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye irritation

persists, get medical advice/attention.

**Skin:** Wash with plenty of soap and water. Call a poison center or

doctor/physician if you feel unwell.

**Ingestion:** DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician if you feel unwell.

**Notes to Physician:** N/A

**Additional First Aid Remarks:** N/A

# Section 5. Fire Fighting Measures

**Flammability of the Product:** Not flammable.

**Suitable Extinguishing Media:** Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

Containers exposed in a fire should be cooled with water to prevent

vapor pressure build—up leading to rupture.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.





## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with soil,

waterways, drains, and sewers.

**Methods for Cleaning up:** Contain and recover liquid when possible. Flush spill area with water

spray.

**Other Statements:** None.

# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

**Storage:** Store away from incompatible materials (see Section 10). Store at

ambient temperatures. Keep container securely closed when not in use.

Label precautions also apply to empty container. Recondition or

dispose of empty containers in accordance with government regulations.

For Industrial use only.

Protect from heat and sources of ignition.

Do not store or handle in aluminum, steel, copper, or their alloys.

Do not freeze. Store above Freeze Point. If freezes, then

mechanical mixing is required.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
Polyaluminum chloride	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.





#### **Personal Protection**

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick—drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and coveralls to

prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.

# Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Colorless, Clear

**Specific Gravity:** 1.176 @ 20°C

**pH:** 4.0 @ 20°C, 100.0%

Freezing Point:

Flash Point:

Odor:

Mild

Melting Point:

N/A

Initial Boiling Point and Boiling Range:

Solubility in Water:

N/C

Evaporation Rate:

N/D
Vapor Density:

N/D
Molecular Weight:

N/A
Viscosity:

N/A
Flammability (solid, gas):

N/A
Autoignition Temperature:

N/A

**Density:** 9.81 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D





# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

**Substances:** 

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon, Oxides of nitrogen, Hydrogen chloride.

**Possibility of Hazardous** 

**Reactions:** 

None known.

# Section 11. Toxicological Information

Chemical Name	Exposure	Type of Effect	Concentration	Species
N/D	N/D	N/D	N/D	N/D

### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Polyaluminum chloride	N/E	N/E	N/E

**Comments:** None.

# Section 12. Ecological Information

Species	Duration	Type of Effect	Test Results
Daphnia magna	48h	LC50	2.56 mg/l
Ceriodaphnia dubia	48h	LC50	1.148 mg/l
	48h	LC50	0.34 mg/l
Fathead Minnow	96h	LC50	4.218 mg/l
	96h	LC50	4.1 mg/l

**Comments:** None.





# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	UN3264	CORROSIVE LIQUID,	(POLYALUMINUM CHLORIDE)	8	PGIII
		ACIDIC, INORGANIC, N.O.S.			
ICAO	UN3264	CORROSIVE LIQUID,	(POLYALUMINUM CHLORIDE)	8	PGIII
		ACIDIC, INORGANIC, N.O.S.			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note:

When shipped by ground in the U.S., by exception 49 CFR 173.154 (d) (1) not subject to transport as a hazardous material when in authorized packaging that will not react dangerously or be degraded by the corrosive material.

# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.





## **Federal Regulations**

#### **SARA Title III Rules**

### Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

No

#### **Other Sections**

	Section 313	Section 302	
Component	Toxic Chemical	EHS TPQ	CERCLA RQ
Polyaluminum chloride	N/A	N/A	N/A

**Comments:** None.

## **State Regulations**

California Proposition 65: None known.

### **Special Regulations**

Component	States	
Polyaluminum chloride	None.	

## **International Regulations**

#### Canada

**WHMIS Classification:** E (Corrosive Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.





### **Compliance Information**

**NSF:** Certified to NSF/ANSI Standard 60

Maximum use rate for potable water – 40 mg/L

This product ships as NSF from:

Ashland, VA Nederland, TX Facility #4 USA Facility #7 USA

FDA/USDA/GRAS: N/A

**KOSHER:** This product has not been evaluated for Kosher approval.

FIFRA: N/A

Other: None

**Comments:** None.

# Section 16. Other Information

### **HMIS Hazard Rating**

Health: 1
Flammability: 0
Physical Hazard: 0
PPE: X

**Notes:** The PPE rating depends on circumstances of use. See

Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha—numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end—user must determine if the code is appropriate for

their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined





Abbreviation	Definition
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

**Revision Date:** September 14, 2015

# Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.





# SAFETY DATA SHEET

# Section 1. Chemical Product and Company Identification

Product Name: ChemTreat RL9075

Product Use: Reverse Osmosis Treatment

**Supplier's Name:** ChemTreat, Inc.

**Emergency Telephone Number:** (800)424–9300 (Toll Free)

Address (Corporate Headquarters): 5640 Cox Road

Glen Allen, VA 23060

Telephone Number for Information:(800)648-4579Date of SDS:March 20, 2017Revision Date:March 20, 2017Revision Number:17032001AN

## Section 2. Hazard(s) Identification

Signal Word: WARNING

**GHS Classification(s):** Eye damage/irritation – Category 2b

Skin corrosion/irritation – Category 2 Acute Toxicity Inhalation – Category 4 Acute Toxicity Oral – Category 5

**Hazard Statement(s):** H320 Causes eye irritation.

H315 Causes skin irritation. H332 Harmful if inhaled.

H303 May be harmful if swallowed.

**Precautionary Statement(s):** Sulphites may cause sensitization to susceptible individuals.

**Prevention:** P264 Wash thoroughly after handling.

P280 Wear protective gloves/protective clothing/eye

protection/face protection.

P261 Avoid breathing dust/fume/gas/mist/vapors/spray. P271 Use only outdoors or in a well–ventilated area.





**Response:** P305 + P351 + P338 IF IN EYES: Rinse

cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. P337 + P313 If eye irritation persists, get medical

advice/attention.

P302 + P352 IF ON SKIN: Wash with plenty of soap

and water.

P332 + P313 If skin irritation develops or persists,

get medical advice/attention.

P362 + P364 Take off contaminated clothing and wash

it before reuse.

P304 + P340 IF INHALED: Remove person to fresh

air and keep comfortable for breathing

P312 Call a POISON CENTER or doctor/physician if

you feel unwell.

Storage: None.

**Disposal:** None.

System of Classification Used: Classification under 2012 OSHA Hazard Communication Standard

(29 CFR 1910.1200).

**Hazards Not Otherwise** 

Classified:

None.

# Section 3. Composition/Hazardous Ingredients

Component	CAS Registry #	Wt.%
Diethylenetriamine penta methylene phosphonic acid, sodium salt	22042-96-2	1 – 5
Sodium bisulfite	7631–90–5	10 – 30
2-Phosphono-1 2 4-butane tricarboxylic acid	37971-36-1	1 – 5

Comments If chemical identity and/or exact percentage of composition has been

withheld, this information is considered to be a trade secret.

### Section 4. First Aid Measures

**Inhalation:** Remove to fresh air and keep at rest in a position comfortable for

breathing. Call a poison center or doctor/physician if you feel

unwell.

**Eyes:** Rinse cautiously with water for several minutes. Remove contact

lenses, if present and easy to do. Continue rinsing. If eye

irritation persists, get medical advice/attention.





**Skin:** Wash with plenty of soap and water. Take off contaminated clothing

and wash before re-use. If skin irritation occurs, seek medical

advice/attention.

Ingestion: DO NOT INDUCE VOMITING. Rinse mouth. Call a POISON

CENTER or doctor/physician if you feel unwell.

**Most Important Symptoms:** N/D

Indication of Immediate Medical Attention and Special Treatment Needed, If Necessary: N/A

## Section 5. Fire Fighting Measures

Flammability of the Product: Not flammable.

Suitable Extinguishing Media: Use extinguishing media suitable to surrounding fire.

**Specific Hazards Arising from** 

the Chemical:

Use water spray to keep containers cool.

**Protective Equipment:** If product is involved in a fire, wear full protective clothing

including a positive-pressure, NIOSH approved, self-contained

breathing apparatus.

## Section 6. Accidental Release Measures

**Personal Precautions:** Use appropriate Personal Protective Equipment (PPE).

**Environmental Precautions:** Avoid dispersal of spilled material and runoff and contact with

soil, waterways, drains, and sewers.

Methods for Cleaning up: Contain and recover liquid when possible. Flush spill area with

water spray.

Other Statements: If RQ (Reportable Quantity) is exceeded, report to National

Spill Response Office at 1–800–424–8802. Reportable Quantity of the product is 1784 Gal.





# Section 7. Handling and Storage

**Handling:** Wear appropriate Personal Protective Equipment (PPE) when

handling this product. Do not get in eyes, or on skin and clothing. Wash thoroughly after handling. Do not ingest. Avoid breathing

vapors, mist or dust.

Storage: Store away from incompatible materials (see Section 10). Store

at ambient temperatures. Keep container securely closed when not in use. Label precautions also apply to empty container. Recondition or dispose of empty containers in accordance with government

regulations. For Industrial use only.

# Section 8. Exposure Controls/Personal Protection

#### **Exposure Limits**

Component	Source	Exposure Limits
Diethylenetriamine penta methylene phosphonic acid, sodiun	N/E	N/E
salt		
Sodium bisulfite	ACGIH TLV	5 mg/m³ TWA
2-Phosphono-1,2,4-butane tricarboxylic acid	N/E	N/E

**Engineering Controls:** Use only with adequate ventilation. The use of local ventilation is

recommended to control emission near the source.

**Personal Protection** 

**Eyes:** Wear chemical splash goggles or safety glasses with

full-face shield. Maintain eyewash fountain in work area.

**Skin:** Maintain quick–drench facilities in work area.

Wear butyl rubber or neoprene gloves. Wash them after each use and replace as necessary. If conditions warrant, wear protective clothing such as boots, aprons, and

coveralls to prevent skin contact.

**Respiratory:** If misting occurs, use NIOSH approved organic vapor/acid

gas dual cartridge respirator with a dust/mist prefilter in

accordance with 29 CFR 1910.134.





## Section 9. Physical and Chemical Properties

Physical State and Appearance: Liquid, Yellow, Clear

Specific Gravity: 1.244 @ 20°C

pH: 2.4 @ 20°C, 100.0%

Freezing Point: 18°F
Flash Point: N/D
Odor: Moderate
Melting Point: N/D
Initial Boiling Point and Boiling Range: 212°F

Solubility in Water: Complete Evaporation Rate: N/D
Vapor Density: N/D
Molecular Weight: N/D

Viscosity: <100 CPS @ 20°C

Flammability (solid, gas):

Flammable Limits:

Autoignition Temperature:

N/A

Density: 10.38 LB/GA

Vapor Pressure:N/D% VOC:N/DOdor ThresholdN/Dn-octanol Partition CoefficientN/DDecomposition TemperatureN/D

# Section 10. Stability and Reactivity

**Chemical Stability:** Stable at normal temperatures and pressures.

**Incompatibility with Various** 

Substances:

Strong oxidizers, Strong bases.

**Hazardous Decomposition** 

**Products:** 

Oxides of carbon.

**Possibility of Hazardous** 

Reactions:

None known.

Reactivity: N/D

Conditions To Avoid: N/D





# Section 11. Toxicological Information

### **Acute Toxicity**

Chemical Name	Exposure	Type of Effect	Concentration	Species
Sodium bisulfite	Oral	LD50	2000 MG/KG	Rat
2-Phosphono-1,2,4-butane tricarboxylic acid	Oral	LD50	>6500 MG/KG	Rat

### **Carcinogenicity Category**

Component	Source	Code	Brief Description
Diethylenetriamine penta methylene phosphonic acid, sodium	N/E	N/E	N/E
salt			
Sodium bisulfite	N/E	N/E	N/E
2-Phosphono-1,2,4-butane tricarboxylic acid	N/E	N/E	N/E

Likely Routes of Exposure: N/D

**Symptoms** 

Inhalation: N/D

Eye Contact: N/D

Skin Contact: N/D

Ingestion: N/D

**Skin Corrosion/Irritation**: N/D

**Serious Eye Damage/Eye** 

Irritation:

N/D

Sensitization: N/D

Germ Cell Mutagenicity: N/D

Reproductive/Developmental

Toxicity:

N/D

**Specific Target Organ Toxicity** 

Single Exposure: N/D

Repeated Exposure: N/D

**Aspiration Hazard:** N/D





Comments: None.

# Section 12. Ecological Information

## **Ecotoxicity**

Species	Duration	Type of Effect	Test Results
Ceriodaphnia dubia	48h	LC50	493 mg/l
Fathead Minnow	96h	LC50	1768 mg/l

Persistence and Biodegradability:

N/D

**Bioaccumulative Potential:** 

N/D

**Mobility In Soil:** 

N/D

**Other Adverse Effects:** 

N/D

Comments:

None.

# Section 13. Disposal Considerations

Dispose of in accordance with local, state and federal regulations.

# Section 14. Transport Information

Controlling					Packing
Regulation	UN/NA#:	Proper Shipping Name:	Technical Name:	Hazard Class:	Group:
DOT	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
Over 1784 GA	UN3082	RQ ENVIRONMENTALLY	(SODIUM BISULFITE)	9	PGIII
		HAZARDOUS SUBSTANCES,			
		LIQUID, N.O.S.			
TDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			
IMDG	N/A	COMPOUND, INDUSTRIAL	N/A	N/A	N/A
		WATER TREATMENT, LIQUID			

Note: N/A





# Section 15. Regulatory Information

**Inventory Status** 

United States (TSCA):
Canada (DSL/NDSL):

All ingredients listed.
All ingredients listed.

**Federal Regulations** 

**SARA Title III Rules** 

Sections 311/312 Hazard Classes

Fire Hazard:

Reactive Hazard:

Release of Pressure:

Acute Health Hazard:

Chronic Health Hazard:

No

#### **Other Sections**

	Section 313	Section 302 EHS	
Component	Toxic Chemical	TPQ	CERCLA RQ
Diethylenetriamine penta methylene phosphonic acid, sodiun	N/A	N/A	N/A
salt			
Sodium bisulfite	N/A	N/A	5000
2-Phosphono-1,2,4-butane tricarboxylic acid	N/A	N/A	N/A

Comments: None.

**State Regulations** 

California Proposition 65: None known.

**Special Regulations** 

Component	States
Diethylenetriamine penta methylene phosphonic acid, sodium salt	None.
Sodium bisulfite	MA, MN, NY, PA, WA
2-Phosphono-1,2,4-butane tricarboxylic acid	None.





### **International Regulations**

#### Canada

WHMIS Classification: D2B (Toxic Material)

**Controlled Product Regulations** 

(CPR):

This product has been classified in accordance with the hazard criteria of the Controlled Products

Regulations (CPR) and the MSDS contains all

the information required by the CPR.

#### **Compliance Information**

**NSF:** Certified to NSF/ANSI Standard 60

Maximum use rate for potable water - 65 mg/L

This product ships as NSF from:

Ashland, VA Eldridge, IA Nederland, TX

Food Regulations: N/A

**KOSHER:** This product is certified by the Orthodox Union as kosher

pareve.

Only when prepared by the following ChemTreat facilities:

Ashland, VA; Eldridge, IA; Nederland, TX.

FIFRA: N/A

Other: None

Comments: None.

## Section 16. Other Information

#### **HMIS Hazard Rating**

Health:	1
Flammability:	0
Physical Hazard:	0
PPE:	X





Notes:

The PPE rating depends on circumstances of use. See Section 8 for recommended PPE.

The Hazardous Material Information System (HMIS) is a voluntary, subjective alpha–numeric symbolic system for recommending hazard risk and personal protection equipment information. It is a subjective rating system based on the evaluator's understanding of the chemical associated risks. The end–user must determine if the code is appropriate for their use.

#### **Abbreviations**

Abbreviation	Definition
<	Less Than
>	Greater Than
ACGIH	American Conference of Governmental Industrial Hygienists
EHS	Environmental Health and Safety Dept
N/A	Not Applicable
N/D	Not Determined
N/E	Not Established
OSHA	Occupational Health and Safety Dept
PEL	Personal Exposure Limit
STEL	Short Term Exposure Limit
TLV	Threshold Limit Value
TWA	Time Weight Average
UNK	Unknown

Prepared by: Product Compliance Department; ProductCompliance@chemtreat.com

Revision Date: March 20, 2017

### Disclaimer

Although the information and recommendations set forth herein (hereinafter "information") are presented in good faith and believed to be correct as of the date hereof, ChemTreat, Inc. makes no representations as to the completeness or accuracy thereof. Information is supplied upon the condition that the persons receiving same will make their own determination as to its suitability for their purposes prior to use. In no event will ChemTreat, Inc. be responsible for damages of any nature whatsoever resulting from the use or reliance upon information. No representation or warranties, either expressed or implied, of merchantability, fitness for a particular purpose, or of any other nature are made hereunder with respect to information or the product to which information refers.



# Safety Data Sheet Sodium Bisulfite Solution high purity grade

Revision date : 2024/10/23 Page: 1/12

Version: 3.0 (30219825/SDS\_GEN\_US/EN)

#### 1. Identification

#### Product identifier used on the label

# **Sodium Bisulfite Solution high purity grade**

#### Recommended use of the chemical and restriction on use

Recommended use\*: Chemical

Recommended use\*: inorganic reducing agents; initial product for chemical syntheses; process

chemical

Unsuitable for use: Not intended for sale to or use by the general public.

### Details of the supplier of the safety data sheet

Company: BASF CORPORATION

100 Park Avenue Florham Park, NJ 07932, USA

Telephone: +1 973 245-6000

### **Emergency telephone number**

24 Hour Emergency Response Information

CHEMTREC: 1-800-424-9300

BASF HOTLINE: 1-800-832-HELP (4357)

#### Other means of identification

Chemical family: Aqueous solution based on: sulfites

### 2. Hazards Identification

### According to Regulation 2012 OSHA Hazard Communication Standard; 29 CFR Part 1910.1200

### Classification of the product

Acute Tox. 4 (oral) Acute toxicity

Aquatic Acute 3 Hazardous to the aquatic environment - acute

<sup>\*</sup> The "Recommended use" identified for this product is provided solely to comply with a Federal requirement and is not part of the seller's published specification. The terms of this Safety Data Sheet (SDS) do not create or infer any warranty, express or implied, including by incorporation into or reference in the seller's sales agreement.

# Safety Data Sheet

# Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 2/12 Version: 3.0 (30219825/SDS GEN US/EN)

#### Label elements

Pictogram:



Signal Word: Warning

Hazard Statement:

H302 Harmful if swallowed. H402 Harmful to aquatic life.

Precautionary Statements (Prevention):

P273 Avoid release to the environment.

P270 Do not eat, drink or smoke when using this product.
P264 Wash contaminated body parts thoroughly after handling.

Precautionary Statements (Response):

P301 + P312 IF SWALLOWED: Call a POISON CENTER or doctor/physician if you

feel unwell.

P301 + P330 + P331 IF SWALLOWED: rinse mouth. Do NOT induce vomiting.

Precautionary Statements (Disposal):

P501 Dispose of contents and container to hazardous or special waste

collection point.

### Hazards not otherwise classified

No specific dangers known, if the regulations/notes for storage and handling are considered. If applicable information is provided in this section on other hazards which do not result in classification but which may contribute to the overall hazards of the substance or mixture.

Labeling of special preparations (GHS):

Contact with acids liberates toxic gas.

### 3. Composition / Information on Ingredients

#### According to Regulation 2012 OSHA Hazard Communication Standard; 29 CFR Part 1910.1200

sodium hydrogen sulphite

CAS Number: 7631-90-5

Content (W/W): >= 38.0 - <= 42.0%

Synonym: Sodium hydrogensulfite (aqueous solution)

#### 4. First-Aid Measures

### **Description of first aid measures**

#### General advice:

Immediately remove contaminated clothing.

# Safety Data Sheet

# Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 3/12 Version: 3.0 (30219825/SDS GEN US/EN)

#### If inhaled:

Keep patient calm, remove to fresh air, seek medical attention. After inhalation of decomposition products: Immediately administer a corticosteroid from a controlled/metered dose inhaler. Seek medical attention.

#### If on skin:

Wash thoroughly with soap and water

#### If in eyes:

Immediately wash affected eyes for at least 15 minutes under running water with eyelids held open, consult an eye specialist.

#### If swallowed:

Immediately rinse mouth and then drink 200-300 ml of water, seek medical attention.

#### Most important symptoms and effects, both acute and delayed

Symptoms: Overexposure may cause:, vomiting, convulsions, circulatory collapse, CNS stimulation, abdominal cramps, hypotension (low blood pressure), gastric hemorrhage, nausea, diarrhea Hazards: Risk of sulfur dioxide formation by reaction with gastric acid after swallowing.

### Indication of any immediate medical attention and special treatment needed

Note to physician

Treatment: Treat according to symptoms (decontamination, vital functions), no known specific antidote.

## 5. Fire-Fighting Measures

#### **Extinguishing media**

Suitable extinguishing media: water spray, carbon dioxide, foam, dry powder

Unsuitable extinguishing media for safety reasons: water jet

Additional information:

Product will not burn.

Use extinguishing measures to suit surroundings.

#### Special hazards arising from the substance or mixture

Hazards during fire-fighting:

Sulphur dioxide,

The substances/groups of substances mentioned can be released if the product is involved in a fire.

### Advice for fire-fighters

Protective equipment for fire-fighting:

Wear self-contained breathing apparatus and chemical-protective clothing.

# Safety Data Sheet Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 4/12 Version: 3.0 (30219825/SDS GEN US/EN)

#### **Further information:**

Product itself is non-combustible; fire extinguishing method of surrounding areas must be considered. Contaminated extinguishing water must be disposed of in accordance with official regulations. In case of fire and/or explosion do not breathe fumes.

#### 6. Accidental release measures

#### Personal precautions, protective equipment and emergency procedures

Breathing protection required.

Avoid contact with the skin, eyes and clothing. Use personal protective clothing. Ensure adequate ventilation.

#### **Environmental precautions**

Do not discharge into drains/surface waters/groundwater. Do not discharge into the subsoil/soil. Retain and dispose of contaminated wash water.

#### Methods and material for containment and cleaning up

For small amounts: Pick up with suitable absorbent material.

For large amounts: Pump off product.

Dispose of absorbed material in accordance with regulations.

#### 7. Handling and Storage

#### Precautions for safe handling

Use only in well-ventilated areas. Do not inhale vapours / aerosols. Avoid contact with skin and eyes. Breathing must be protected when large quantities are decanted without local exhaust ventilation.

Protection against fire and explosion:

The substance/product is non-combustible. No special precautions necessary.

#### Conditions for safe storage, including any incompatibilities

Segregate from acids and acid forming substances. Segregate from oxidants.

Suitable materials for containers: Polyester resin, glass reinforced (Palatal A410), rubberized, Stainless steel 1.4462, Stainless steel 1.4404

Further information on storage conditions: Keep away from heat. Keep container tightly closed in a cool, well-ventilated place. Keep container dry. The product consumes oxygen. Danger of lack of oxygen in containers and tanks.

#### 8. Exposure Controls/Personal Protection

<u>Components with occupational exposure limits</u>The substance mentioned develops if the regulation/notes for storage and handling are not observed.

Sulphur dioxide ACGIH, US: STEL value 0.25 ppm;

OSHA Z1: PEL 5 ppm 13 mg/m3;

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 5/12 Version: 3.0 (30219825/SDS GEN US/EN)

sodium hydrogen sulphite ACGIH, US: TWA value 5 mg/m3;

#### Personal protective equipment

#### Respiratory protection:

Wear respiratory protection if ventilation is inadequate. Wear a NIOSH-certified (or equivalent) respirator as necessary.

Observe OSHA regulations for respirator use (29 CFR 1910.134).

#### Hand protection:

Chemical resistant protective gloves should be worn to prevent all skin contact., Suitable materials may include, nitrile rubber (Buna N), chloroprene rubber (Neoprene), polyvinylchloride (Pylox), Consult with glove manufacturer for testing data., Protective glove selection must be based on the user's assessment of the workplace hazards.

#### Eye protection:

Tightly fitting safety goggles (chemical goggles). Wear face shield if splashing hazard exists.

#### **Body protection:**

Body protection must be chosen depending on activity and possible exposure, e.g. head protection, apron, protective boots, chemical-protection suit.

#### General safety and hygiene measures:

Handle in accordance with good industrial hygiene and safety practice. Do not breathe vapour/spray. Hands and/or face should be washed before breaks and at the end of the shift.

#### 9. Physical and Chemical Properties

Form: aqueous solution

Odour: pungent

Odour threshold: Not determined due to potential health hazard by inhalation.

Colour: colourless to yellow

pH value: 3.5 - 5.0 (DIN 19268)

crystallization < 5 °C

temperature:

Melting point: 5 °C

Freezing point: No data available.

Boiling point: 100 °C

(1,013 mbar)

Information applies to the solvent.

Boiling range: No data available.
Flash point: not applicable
Flammability: not flammable

Lower explosion limit: For liquids not relevant for

classification and labelling.

Upper explosion limit: For liquids not relevant for

classification and labelling.

Autoignition: not applicable Vapour pressure: approx. 155 mbar

(55 °C)

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 6/12 Version: 3.0 (30219825/SDS GEN US/EN)

approx. 124 mbar

(50°C)

approx. 24 mbar

(20°C)

The vapour pressure of the aqueous solution consists of the partial pressure for water and the partial pressure for sulphur dioxide.

27 hPa ( 20 °C) 103 hPa ( 50 °C)

Density: 1.325 g/cm3 (DIN 51757)

(20°C)

Information on: sodium hydrogen sulphite
Partitioning coefficient n- not applicable

octanol/water (log Pow):

Self-ignition not self-igniting

temperature:

not self-igniting

Thermal decomposition: It is not a self-decompositionable substance.

Viscosity, dynamic: 3.64 mPa.s (DIN 51562)

(20°C)

Viscosity, kinematic: not determined

Particle size: The substance / product is marketed

or used in a non solid or granular

form.

Solubility in water: approx. 515 g/l

(20°C)

Solubility (quantitative): approx. 515 g/l

(20°C)

The values mentioned are those of the solved solid.

Evaporation rate: Value can be approximated from

Henry's Law Constant or vapor

pressure.

#### 10. Stability and Reactivity

#### Reactivity

Oxidizing properties: not fire-propagating

#### **Chemical stability**

#### Possibility of hazardous reactions

Reacts with nitrites. Reacts with nitrates. Reacts with oxidizing agents. Generation of sulphur dioxide upon exposure to acids. (or conditions.) The product consumes oxygen.

#### Conditions to avoid

avoid atmospheric oxygen

#### Incompatible materials

nitrites, nitrates, oxidizing agents, acids

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 7/12 Version: 3.0 (30219825/SDS GEN US/EN)

#### **Hazardous decomposition products**

Decomposition products:

Hazardous decomposition products: Sulphur dioxide

Thermal decomposition:

It is not a self-decompositionable substance.

#### 11. Toxicological information

#### Primary routes of exposure

Routes of entry for solids and liquids are ingestion and inhalation, but may include eye or skin contact. Routes of entry for gases include inhalation and eye contact. Skin contact may be a route of entry for liquefied gases.

#### **Acute Toxicity/Effects**

#### Acute toxicity

Information on: sodium hydrogen sulphite

Assessment of acute toxicity:Of moderate toxicity after single ingestion. Virtually nontoxic by inhalation. Virtually nontoxic after a single skin contact.

-----

#### Oral

Information on: sodium hydrogen sulphite

Type of value: LD50

Species: rat

Value: approx. 2,610 mg/kg (similar to OECD guideline 401)

The product has not been tested. The statement has been derived from substances/products of a

similar structure or composition.

-----

#### **Inhalation**

Type of value: LC50 Species: rat (male/female)

Value: > 5.5 mg/l (OECD Guideline 403)

Exposure time: 4 h

The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

#### **Dermal**

Type of value: LD50

Species: rat

Value: > 2,000 mg/kg (OECD Guideline 402)

No mortality was observed. The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

#### Assessment other acute effects

Assessment of STOT single:

Based on the available information there is no specific target organ toxicity to be expected after a single exposure.

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 8/12 Version: 3.0 (30219825/SDS GEN US/EN)

<u>Skin</u>

Species: rabbit Result: non-irritant

Method: OECD Guideline 404

Literature data.

Eye

Species: rabbit Result: non-irritant

Method: OECD Guideline 405

Literature data.

#### **Sensitization**

Assessment of sensitization: A sensitizing effect on particularly sensitive individuals cannot be excluded.

Mouse Local Lymph Node Assay (LLNA)

Species: mouse

Result: Non-sensitizing.

Method: OECD Guideline 429

The product has not been tested. The statement has been derived for

The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

#### Aspiration Hazard

No aspiration hazard expected.

#### **Chronic Toxicity/Effects**

#### Repeated dose toxicity

Assessment of repeated dose toxicity: No substance-specific organtoxicity was observed after repeated administration to animals. The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

#### Genetic toxicity

Assessment of mutagenicity: The substance was not mutagenic in a test with mammals.

#### Carcinogenicity

Assessment of carcinogenicity: No reliable data was available concerning carcinogenic activity. The chemical structure does not suggest a specific alert for such an effect.

#### Reproductive toxicity

Assessment of reproduction toxicity: The results of animal studies gave no indication of a fertility impairing effect.

#### Teratogenicity

Assessment of teratogenicity: No indications of a developmental toxic / teratogenic effect were seen in animal studies.

#### Experiences in humans

With sensitive persons it can lead to an over sensitive reaction.

#### 12. Ecological Information

#### **Toxicity**

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 9/12 Version: 3.0 (30219825/SDS GEN US/EN)

Aquatic toxicity

Assessment of aquatic toxicity:

Acutely harmful for aquatic organisms.

#### Chronic toxicity to fish

No observed effect concentration (34 d) >= 50 mg/l, Brachydanio rerio (OECD Guideline 210, Flow through.)

The product has not been tested. The statement has been derived from substances/products of a similar structure or composition. Nominal concentration.

#### Chronic toxicity to aquatic invertebrates

No observed effect concentration (21 d) > 10 mg/l, Daphnia magna (OECD Guideline 211, semistatic)

Nominal concentration. The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

#### Toxicity to fish

Information on: sodium hydrogen sulphite

LC50 (96 h) 316 mg/l, Leuciscus idus (DIN 38412 Part 15, static)

The product has not been tested. The statement has been derived from substances/products of a similar structure or composition. Nominal concentration.

\_\_\_\_\_

#### Aquatic invertebrates

Information on: sodium hydrogen sulphite

(48 h) 89 mg/l, Daphnia magna (Directive 79/831/EEC, static)

Nominal concentration. The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

·

#### Aquatic plants

Information on: sodium hydrogen sulphite

EC50 (72 h) 43.8 mg/l (growth rate), Scenedesmus subspicatus (OECD Guideline 201, static) Nominal concentration. The product has not been tested. The statement has been derived from substances/products of a similar structure or composition.

-----

#### Assessment of terrestrial toxicity

Study scientifically not justified.

#### Microorganisms/Effect on activated sludge

#### Toxicity to microorganisms

Information on: sodium hydrogen sulphite

OECD Guideline 209 static

activated sludge of a predominantly domestic sewage/EC10 (3 h): 634.4 mg/l

The product has not been tested. The statement has been derived from substances/products of a similar structure or composition. Nominal concentration.

-----

#### Persistence and degradability

# Safety Data Sheet Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 10/12 Version: 3.0 (30219825/SDS GEN US/EN)

#### Assessment biodegradation and elimination (H2O)

Inorganic product which cannot be eliminated from water by biological purification processes. Decomposition products formed by microbiotic degradation may affect the activity in biological waste water treatment plants.

#### Assessment of stability in water

According to structural properties, hydrolysis is not expected/probable. Study scientifically not justified.

#### Bioaccumulative potential

#### Assessment bioaccumulation potential

Accumulation in organisms is not to be expected.

#### Bioaccumulation potential

Study scientifically not justified.

#### Assessment bioaccumulation potential

Information on: sodium hydrogen sulphite

Accumulation in organisms is not to be expected.

-----

#### Mobility in soil

#### Assessment transport between environmental compartments

Adsorption to solid soil phase is not expected.

#### **Additional information**

#### Other ecotoxicological advice:

Inhibition of degradation activity in activated sludge is not to be anticipated during correct introduction of low concentrations. At the present state of knowledge, no negative ecological effects are expected.

#### 13. Disposal considerations

#### Waste disposal of substance:

Must be disposed of or incinerated in accordance with local regulations. Observe national and local legal requirements.

#### Container disposal:

Contaminated packaging should be emptied as far as possible; then it can be passed on for recycling after being thoroughly cleaned.

#### 14. Transport Information

#### Land transport

**USDOT** 

Not classified as a dangerous good under transport regulations

## Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 11/12 Version: 3.0 (30219825/SDS\_GEN\_US/EN)

Sea transport

**IMDG** 

Not classified as a dangerous good under transport regulations

Air transport IATA/ICAO

Not classified as a dangerous good under transport regulations

#### 15. Regulatory Information

#### **Federal Regulations**

Registration status:

Chemical TSCA, US released / listed

**EPCRA 311/312 (Hazard categories):** Refer to SDS section 2 for GHS hazard classes applicable for this product.

CERCLA RQ CAS Number Chemical name

5000 LBS 7631-90-5 sodium hydrogen sulphite

State regulations

State RTK CAS Number Chemical name

NJ 7631-90-5 sodium hydrogen sulphite PA 7631-90-5 sodium hydrogen sulphite

7757-82-6 Sodium sulfate

**NFPA Hazard codes:** 

Health: 1 Fire: 0 Reactivity: 0 Special:

#### Assessment of the hazard classes according to UN GHS criteria (most recent version):

Acute Tox. 4 (oral) Acute toxicity

Aquatic Acute 3 Hazardous to the aquatic environment - acute

#### 16. Other Information

#### SDS Prepared by:

BASF NA Product Regulations SDS Prepared on: 2024/10/23

We support worldwide Responsible Care® initiatives. We value the health and safety of our employees, customers, suppliers and neighbors, and the protection of the environment. Our commitment to Responsible Care is integral to conducting our business and operating our facilities in a safe and environmentally responsible fashion, supporting our customers and suppliers in ensuring the safe and environmentally sound handling of our products, and minimizing the impact of our operations on society and the environment during production, storage, transport, use and disposal of our products.

# Safety Data Sheet Sodium Bisulfite Solution high purity grade

Revision date: 2024/10/23 Page: 12/12 Version: 3.0 (30219825/SDS\_GEN\_US/EN)

IMPORTANT: WHILE THE DESCRIPTIONS, DESIGNS, DATA AND INFORMATION CONTAINED HEREIN ARE PRESENTED IN GOOD FAITH AND BELIEVED TO BE ACCURATE, IT IS PROVIDED FOR YOUR GUIDANCE ONLY. BECAUSE MANY FACTORS MAY AFFECT PROCESSING OR APPLICATION/USE, WE RECOMMEND THAT YOU MAKE TESTS TO DETERMINE THE SUITABILITY OF A PRODUCT FOR YOUR PARTICULAR PURPOSE PRIOR TO USE. NO WARRANTIES OF ANY KIND, EITHER EXPRESSED OR IMPLIED, INCLUDING WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, ARE MADE REGARDING PRODUCTS DESCRIBED OR DESIGNS, DATA OR INFORMATION SET FORTH, OR THAT THE PRODUCTS, DESIGNS, DATA OR INFORMATION MAY BE USED WITHOUT INFRINGING THE INTELLECTUAL PROPERTY RIGHTS OF OTHERS. IN NO CASE SHALL THE DESCRIPTIONS, INFORMATION, DATA OR DESIGNS PROVIDED BE CONSIDERED A PART OF OUR TERMS AND CONDITIONS OF SALE. FURTHER, YOU EXPRESSLY UNDERSTAND AND AGREE THAT THE DESCRIPTIONS, DESIGNS, DATA, AND INFORMATION FURNISHED BY OUR COMPANY HEREUNDER ARE GIVEN GRATIS AND WE ASSUME NO OBLIGATION OR LIABILITY FOR THE DESCRIPTION, DESIGNS, DATA AND INFORMATION GIVEN OR RESULTS OBTAINED, ALL SUCH BEING GIVEN AND ACCEPTED AT YOUR RISK. **END OF DATA SHEET** 



### TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

# SUMMARY OF APPLICATION IN PLAIN LANGUAGE FOR TPDES OR TLAP PERMIT APPLICATIONS

# Summary of Application (in plain language) Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary of your facility and application as required by Title 30, Texas Administrative Code (30 TAC), Chapter 39, Subchapter H. You may modify the template as necessary to accurately describe your facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how you will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements. After filling in the information for your facility delete these instructions.

If you are subject to the alternative language notice requirements in 30 TAC Section 39.426, you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package. For your convenience, a Spanish template has been provided below.

# ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS INDUSTRIAL WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

Energy Transfer GC NGL Fractionators LLC (CN604309419) operates MB Frac VI and VIII (RN109902494), a Energy Transfer GC NGL Fractionators LLC operates an existing Natural Gas processing plant that fractionates Y-grade natural gas liquids into ethane, propane, butane, and natural gasoline. The process uses a low vapor pressure heating medium and cooling is provided using Wet Surface Air Cooling (WSAC) technology. The feedstock and products of the facility are stored in off-site salt dome caverns and transported to and from the facility via pipelines, eliminating the need for on-site feedstock or product storage. The facility is approximately 0.25 miles south of FM 1942 and 0.75 miles east of Cedar Bayou, in Chambers County, Texas. Applicable SIC Code is 1321. The facility discharges through Outfall 001. The facility is located at 8774 FM 1942, in Baytown, Chambers County, Texas 77521. This permit application seeks to remove the WET analysis requirement. We have not failed any WET test since obtaining this permit. If eliminating the WET testing is not possible we request the

frequency of testing be changed to once a year instead of quarterly testing. This permit will not authorize the discharge of pollutants into water in the state.

Discharges from the facility are expected to contain TDS, traces of chloride and traces of TPH. Reverse osmosis reject water, fire system testing, emergency showers, fan cleaning water, non-contact stormwater, air dryer condensate, non-contact cooling water and occasionally hydrostatic test water is treated by using carbon dioxide to control pH and using hydrogen peroxide to control residual chlorine.

# PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

#### AGUAS RESIDUALES INDUSTRIALES /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

Energy Transfer GC NGL Fractionators, LLC (CN604309419) opera MB Frac VI and VIII (RN109602494), una planta de procesamiento de gas natural existente que fracciona líquidos de gas natural de grado Y en etano, propano, butano y gasolina natural. El proceso utiliza un medio de calefacción de baja presión de vapor y el enfriamiento se proporciona utilizando la tecnología de Enfriamiento de Aire de Superficie Húmeda (WSAC). La materia prima y los productos de la instalación se almacenan en cavidades de domo salino fuera del sitio y se transportan hacia y desde la instalación a través de tuberías, eliminando la necesidad de almacenamiento de materia prima o producto en el lugar. La instalación está aproximadamente a 0.25 millas al sur de FM 1942 y a 0.75 millas al este de Cedar Bayou, en el condado de Chambers, Texas. El código SIC aplicable es 1321. La instalación descarga a través de la Salida 001. La instalación está ubicada en 8774 FM 1942, en Baytown, Condado de Chambers, Texas 77521. Esta solicitud de permiso busca eliminar el requisito de análisis WET. No hemos fallado en ninguna prueba WET desde que obtuvimos este permiso. Si no es posible eliminar las pruebas WET, solicitamos que la frecuencia de las pruebas se cambie a una vez al año en lugar de pruebas trimestrales. No se solicitan otros cambios a este permiso. Este permiso no autorizará una descarga de contaminantes en el agua en el estado.

Se espera que las descargas de la instalación contengan TDS, trazas de cloruro y trazas de TPH. Agua de rechazo de ósmosis inversa, pruebas del sistema de incendios, duchas de emergencia, agua de limpieza de ventiladores, aguas pluviales sin contacto, condensado de secadores de aire, agua de enfriamiento sin contacto y ocasionalmente agua de prueba hidrostática está tratado por el uso de dióxido de carbono para controlar el pH y utilizando peróxido de hidrógeno para controlar el cloro residual.

#### **INSTRUCTIONS**

- 1. Enter the name of applicant in this section. The applicant name should match the name associated with the customer number.
- 2. Enter the Customer Number in this section. Each Individual or Organization is issued a unique 11-digit identification number called a CN (e.g. CN123456789).
- 3. Choose "operates" in this section for existing facility applications or choose "proposes to operate" for new facility applications.
- 4. Enter the name of the facility in this section. The facility name should match the name associated with the regulated entity number.
- 5. Enter the Regulated Entity number in this section. Each site location is issued a unique 11-digit identification number called an RN (e.g. RN123456789).
- 6. Choose the appropriate article (a or an) to complete the sentence.
- 7. Enter a description of the facility in this section. For example: steam electric generating facility, nitrogenous fertilizer manufacturing facility, etc.
- 8. Choose "is" for an existing facility or "will be" for a new facility.
- 9. Enter the location of the facility in this section.
- 10. Enter the City nearest the facility in this section.
- 11. Enter the County nearest the facility in this section.
- 12. Enter the zip code for the facility address in this section.
- 13. Enter a summary of the application request in this section. For example: renewal to discharge 25,000 gallons per day of treated domestic wastewater, new application to discharge process wastewater and stormwater on an intermittent and flow-variable basis, or major amendment to reduce monitoring frequency for pH, etc. If more than one outfall is included in the application, provide applicable information for each individual outfall.
- 14. List all pollutants expected in the discharge from this facility in this section. If applicable, refer to the pollutants from any federal numeric effluent limitations that apply to your facility.
- 15. Enter the discharge types from your facility in this section (e.g., stormwater, process wastewater, once through cooling water, etc.)
- 16. Choose the appropriate verb tense to complete the sentence.
- 17. Enter a description of the wastewater treatment used at your facility. Include a description of each process, starting with initial treatment and finishing with the outfall/point of disposal. Use additional lines for individual discharge types if necessary.

Questions or comments concerning this form may be directed to the Water Quality Division's Application Review and Processing Team by email at <a href="https://www.wq-arteq.texas.gov">wq-ARPTeam@tceq.texas.gov</a> or by phone at (512) 239-4671.

#### **Example 1: Industrial Wastewater TPDES Application (ENGLISH)**

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

ABC Corporation (CN600000000) operates the Starr Power Station (RN10000000000), a two-unit gas-fired electric generating facility. Unit 1 has a generating capacity of 393 megawatts (MWs) and Unit 2 has a generating capacity of 528 MWs. The facility is located at 1356 Starr Street, near the City of Austin, Travis County, Texas 78753.

This application is for a renewal to discharge 870,000,000 gallons per day of once through cooling water, auxiliary cooling water, and also authorizes the following waste streams monitored inside the facility (internal outfalls) before it is mixed with the other wastewaters authorized for discharge via main Outfall 001, referred to as "previously monitored effluents" (low-volume wastewater, metal-cleaning waste, and stormwater (from diked oil storage area yards and storm drains)) via Outfall 001. Low-volume waste sources, metal-cleaning waste, and stormwater drains on a continuous and flow-variable basis via internal Outfall 101.

The discharge of once through cooling water via Outfall 001 and low-volume waste and metal-cleaning waste via Outfall 101 from this facility is subject to federal effluent limitation guidelines at 40 CFR Part 423. The pollutants expected from these discharges based on 40 CFR Part 423 are: free available chlorine, total residual chlorine, total suspended solids, oil and grease, total iron, total copper, and pH. Temperature is also expected from these discharges. Additional potential pollutants are included in the Industrial Wastewater Application Technical Report, Worksheet 2.0.

Cooling water and boiler make-up water are supplied by Lake Starr Reservoir. The City of Austin municipal water plant (CN600000000, PWS 00000) supplies the facility's potable water and serves as an alternate source of boiler make-up water. Water from the Lake Starr Reservoir is withdrawn at the intake structure and treated with sodium hypochlorite to prevent biofouling and sodium bromide as a chlorine enhancer to improve efficacy and then passed through condensers and auxiliary equipment on a once-through basis to cool equipment and condense exhaust steam.

Low-volume wastewater from blowdown of boiler Units 1 and 2 and metal-cleaning wastes receive no treatment prior to discharge via Outfall 101. Plant floor and equipment drains and stormwater runoff from diked oil storage areas, yards, and storm drains are routed through an oil and water separator prior to discharge via Outfall 101. Domestic wastewater, blowdown, and backwash water from the service water filter, clarifier, and sand filter are routed to the Starr Creek Domestic Sewage Treatment Plant, TPDES Permit No. WQ0010000001, for treatment and disposal. Metal-cleaning waste from equipment cleaning is generally disposed of off-site.

#### **Example 2: Domestic Wastewater TPDES Renewal application**

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

The City of Texas (CN000000000) operates the City of Texas wastewater treatment plant (RN00000000), an activated sludge process plant operated in the complete mix mode. The facility is located at 123 Texas Street, near the City of More Texas, Texas County, Texas 71234.

This application is for a renewal to discharge at an annual average flow of 1,200,000 gallons per day of treated domestic wastewater via Outfalls 001 and 002.

Discharges from the facility are expected to contain five-day carbonaceous biochemical oxygen demand (CBOD<sub>5</sub>), total suspended solids (TSS), ammonia nitrogen (NH<sub>3</sub>-N), and *Escherichia coli*. Additional potential pollutants are included in the Domestic Technical Report 1.0, Section 7. Pollutant Analysis of Treated Effluent and Domestic Worksheet 4.0 in the permit application package. Domestic wastewater is treated by an activated sludge process plant and the treatment units include a bar screen, a grit chamber, aeration basins, final clarifiers, sludge digesters, a belt filter press, chlorine contact chambers and a dechlorination chamber.

#### **Example 3: Domestic Wastewater TPDES New Application**

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

The City of Texas (CN000000000) proposes to operate the City of Texas wastewater treatment plant (RN00000000), an activated sludge process plant operated in the extended aeration mode. The facility will be located at 123 Texas Street, in the City of More Texas, Texas County, Texas 71234.

This application is for a new application to discharge at a daily average flow of 200,000 gallons per day of treated domestic wastewater.

Discharges from the facility are expected to contain five-day carbonaceous biochemical oxygen demand (CBOD<sub>5</sub>), total suspended solids (TSS), ammonia nitrogen (NH<sub>3</sub>-N), and *Escherichia coli*. Additional potential pollutants are included in the Domestic Technical Report 1.0, Section 7. Pollutant Analysis of Treated Effluent in the permit application package. Domestic wastewater will be treated by an activated sludge process plant and the treatment units will include a bar screen, a grit chamber, aeration basins, final clarifiers, sludge digesters, a belt filter press, chlorine contact chambers and a dechlorination chamber.

#### Example 4: Domestic Wastewater TLAP Renewal application

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations

of the permit application.

The City of Texas (CN000000000) operates the City of Texas wastewater treatment plant (RN00000000), an activated sludge process plant operated in the complete mix mode. The facility is located at 123 Texas Street, near the City of More Texas, Texas County, Texas 71234.

This application is for a renewal to dispose a daily average flow not to exceed 76,500 gallons per day of treated domestic wastewater via public access subsurface drip irrigation system with a minimum area of 32 acres. This permit will not authorize a discharge of pollutants into water in the state.

Land application of domestic wastewater from the facility are expected to contain five-day biochemical oxygen demand (BOD₅), total suspended solids (TSS), and *Escherichia coli*. Additional potential pollutants are included in the Domestic Technical Report 1.0, Section 7. Pollutant Analysis of Treated Effluent in the permit application package. Domestic wastewater is treated by an activated sludge process plant and the treatment units include a bar screen, an equalization basin, an aeration basin, a final clarifier, an aerobic sludge digester, tertiary filters, and a chlorine contact chamber. In addition, the facility includes a temporary storage that equals to at least three days of the daily average flow.

# Public Involvement Plan Form for Permit and Registration Applications

The Public Involvement Plan is intended to provide applicants and the agency with information about how public outreach will be accomplished for certain types of applications in certain geographical areas of the state. It is intended to apply to new activities; major changes at existing plants, facilities, and processes; and to activities which are likely to have significant interest from the public. This preliminary screening is designed to identify applications that will benefit from an initial assessment of the need for enhanced public outreach.

All applicable sections of this form should be completed and submitted with the permit or registration application. For instructions on how to complete this form, see TCEQ-20960-inst.

#### Section 1. Preliminary Screening

New Permit or Registration Application

New Activity - modification, registration, amendment, facility, etc. (see instructions)

If neither of the above boxes are checked, completion of the form is not required and does not need to be submitted.

#### Section 2. Secondary Screening

Requires public notice,

Considered to have significant public interest, and

Located within any of the following geographical locations:

- Austin
- Dallas
- Fort Worth
- Houston
- San Antonio
- West Texas
- Texas Panhandle
- Along the Texas/Mexico Border
- Other geographical locations should be decided on a case-by-case basis

If all the above boxes are not checked, a Public Involvement Plan is not necessary. Stop after Section 2 and submit the form.

Public Involvement Plan not applicable to this application. Provide **brief** explanation.

TCEQ-20960 (02-09-2023)

#### Section 3. Application Information

#### Type of Application (check all that apply):

Air Initial Federal Amendment Standard Permit Title V

Waste Municipal Solid Waste Industrial and Hazardous Waste Scrap Tire

Radioactive Material Licensing Underground Injection Control

Water Quality

Texas Pollutant Discharge Elimination System (TPDES)

Texas Land Application Permit (TLAP)

State Only Concentrated Animal Feeding Operation (CAFO)

Water Treatment Plant Residuals Disposal Permit

Class B Biosolids Land Application Permit

Domestic Septage Land Application Registration

Water Rights New Permit

New Appropriation of Water

New or existing reservoir

Amendment to an Existing Water Right

Add a New Appropriation of Water

Add a New or Existing Reservoir

Major Amendment that could affect other water rights or the environment

#### Section 4. Plain Language Summary

D ' 1	1 1		C 1 1	
Provide 3	hrigt d	accrintion	of planned	activation
I I OVIUE a	титет и	CSCLIDUOL	от планиси	activities.

#### Section 5. Community and Demographic Information

Community information can be found using EPA's EJ Screen, U.S. Census Bureau information, or generally available demographic tools.

Information gathered in this section can assist with the determination of whether alternative language notice is necessary. Please provide the following information.

language notice is n	ecessary. Please pro	ovide the following info	ormation.	
(City)				
(County)				
(Census Tract) Please indicate which City	of these three is the County	e level used for gatherin Census Tract	ng the following informat	tion.
(a) Percent of people	over 25 years of age	e who at least graduated	from high school	
- -		the specified location	race within the specified	location
(d) Percent of Linguis	stically Isolated Hous	seholds by language wit	hin the specified locatior	1
(e) Languages commo	only spoken in area l	by percentage		
(f) Community and/o	or Stakeholder Group	os		
(g) Historic public int	terest or involvemen	t		

#### Section 6. Planned Public Outreach Activities

(a) Is this application subject to the public participation requirements of Title 30 Texas Administrative Code (30 TAC) Chapter 39?

Yes No

(b) If yes, do you intend at this time to provide public outreach other than what is required by rule?

Yes No

If Yes, please describe.

# If you answered "yes" that this application is subject to 30 TAC Chapter 39, answering the remaining questions in Section 6 is not required.

(c) Will you provide notice of this application in alternative languages?

Yes No

Please refer to Section 5. If more than 5% of the population potentially affected by your application is Limited English Proficient, then you are required to provide notice in the alternative language.

If yes, how will you provide notice in alternative languages?

Publish in alternative language newspaper

Posted on Commissioner's Integrated Database Website

Mailed by TCEQ's Office of the Chief Clerk

Other (specify)

(d) Is there an opportunity for some type of public meeting, including after notice?

Yes No

(e) If a public meeting is held, will a translator be provided if requested?

Yes No

(f) Hard copies of the application will be available at the following (check all that apply):

TCEQ Regional Office

TCEQ Central Office

Public Place (specify)

#### Section 7. Voluntary Submittal

For applicants voluntarily providing this Public Involvement Plan, who are not subject to formal public participation requirements.

Will you provide notice of this application, including notice in alternative languages?

Yes No


What types of notice will be provided?


Publish in alternative language newspaper

Posted on Commissioner's Integrated Database Website

Mailed by TCEQ's Office of the Chief Clerk

Other (specify)





### **Attachment AR-6**

Adjacent Landowners Map Energy Transfer GC NGL Fractionators LLC Baytown, Chambers County, TX

MAP ID	OWNER NAME	ADDRESS	CITY	STATE	ZIP
1	Lone Star NGL Fractionators LLC	1300 Main St	Houston	TX	77002
2	Mont Belvieu Caverns, LLC	PO Box 4018	Houston	TX	77210-4018
3	Lone Star NGL Mont Belvieu LP	1300 Main St	Houston	TX	77002
4	Equistar Chemicals LP	16410 N Eldridge Pkwy	Tomball	TX	77377
5	Dow Hydrocarbons & Resources LLC	Tax Dept, APB Bldg., Floor 4A	Lake Jackson	TX	77566
6	Targa Downstream LLC c/o Andrews & Company	1900 Dalrock Road	Rowlett	TX	75088
7	Occidental Chemical Corp	0 SJOLANDER (OFF) Rd	Pickens	TX	74752
8	Chevron Phillips Chemical Co LP	9200 East Fwy	Baytown	TX	77521
9	Lone Star NGL Mont Belvieu LP	0 Pine Lake Ln	Baytown	TX	77521
10	Joseph R. Zorn	9202 Westview Circle	Dallas	TX	75231-2502

**Note:** Data source is Chambers County Appraisal District digital parcel data and associated tax roll database. (IDs 1 to 6). Data Source is Harris County Appraisal District database. (IDs 7 to 9).

Energy Transfer GC NGL Fractionators LLC 1300 Main St Houston TX 77002

Mont Belvieu Caverns LLC PO Box 4018 Houston TX 77210-4018

Lone Star NGL Mont Belvieu LP 1300 Main St Houston TX 77002

Equistar Chemicals LP 16410 N Eldridge Pkwy Tomball TX 77377

Dow Hydrocarbons & Resources LLC Tax Dept, APB Bldg., Floor 4A Lake Jackson TX 77566

Targa Downstream LLC c/o Andrews & Company 1900 Dalrock Road Rowlett TX 75088

Occidental Chemical Corp 0 SJOLANDER (OFF) Rd Pickens TX 74752

Chevron Phillips Chemical Co LP 9200 East Fwy Baytown TX 77521

Lone Star NGL Mont Belvieu LP 0 Pine Lake Ln Baytown TX 77521

Joseph R. Zorn 9202 Westview Circle Dallas TX 75231-2502

# **Original Photographs**



**Photo 1 – From Outfall 001 looking northeast** 



Photo 2 – From Outfall 001 looking southwest



Photo 3 – Outfall 001



Photo 4 – Pond exit pipe to Outfall 001 and pH/Temperature meter



Photo 5 – Outfall 001 Sampling point

# TEXAS COMMISSION ON ENVIRONMENTAL QUALITY SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

# FOR AGENCIES REVIEWING DOMESTIC OR INDUSTRIAL TPDES WASTEWATER PERMIT APPLICATIONS

TCEQ USE ONLY:
Application type:RenewalMajor AmendmentMinor AmendmentNew
County: Segment Number:
Admin Complete Date:
Agency Receiving SPIF:
Texas Historical Commission U.S. Fish and Wildlife
Texas Parks and Wildlife Department U.S. Army Corps of Engineers
This form applies to TPDES permit applications only. (Instructions, Page 53)
Complete this form as a separate document. TCEQ will mail a copy to each agency as required by our agreement with EPA. If any of the items are not completely addressed or further information is needed, we will contact you to provide the information before issuing the permit. Address each item completely.
Do not refer to your response to any item in the permit application form. Provide each attachment for this form separately from the Administrative Report of the application. The application will not be declared administratively complete without this SPIF form being completed in its entirety including all attachments. Questions or comments concerning this form may be directed to the Water Quality Division's Application Review and Processing Team by email at <a href="https://www.wcc.nc.gov">wcc.acm.gov</a> or by phone at (512) 239-4671.
The following applies to all applications:
1. Permittee: <u>Energy Transfer GC NGL Fractionators LLC</u>
Permit No. WQ00 <u>05350000</u> EPA ID No. TX <u>0134068</u>
Address of the project (or a location description that includes street/highway, city/vicinity, and county):
From I-10 East Exit TX 146 North go 2.5 miles turn left onto FM-1942 go approx. 2.2 miles turn left onto an unnamed road go 0.3 miles site is to the right.

Provide the name, address, phone and fax number of an individual that can be contacted to answer specific questions about the property.	0								
Prefix (Mr., Ms., Miss): Ms.									
First and Last Name: Cynthia M. Sexton									
Credential (P.E, P.G., Ph.D., etc.):									
Title: Associate-Environmental Specialist									
Mailing Address: 12353 Eagle Pointe Drive									
City, State, Zip Code: Mont Belvieu, TX 77523									
Phone No.: <u>281-576-3616</u> Ext.: Fax No.:									
E-mail Address: <u>Cynthia.sexton@energytransfer.com</u>									
List the county in which the facility is located: <u>Chambers</u>									
If the property is publicly owned and the owner is different than the permittee/applicant,									
please list the owner of the property.  N/A									
Provide a description of the effluent discharge route. The discharge route must follow the fle	ow								
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please ident	ifv								
the classified segment number.	11 y								
Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for									
about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches culverts and underground piping in some areas.	1								
<u>curverts and underground piping in some areas.</u>									
Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharg route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).	e								
Provide original photographs of any structures 50 years or older on the property.									
Does your project involve any of the following? Check all that apply.									
☐ Proposed access roads, utility lines, construction easements									
☐ Visual effects that could damage or detract from a historic property's integrity									
☐ Vibration effects during construction or as a result of project design									
☐ Additional phases of development that are planned for the future									
☐ Sealing caves, fractures, sinkholes, other karst features									
U,									

2.3.

4.

5.

	☐ Disturbance of vegetation or wetlands
1.	List proposed construction impact (surface acres to be impacted, depth of excavation, sealing of caves, or other karst features):
	N/A
2.	Describe existing disturbances, vegetation, and land use:
	The site is already developed.
	E FOLLOWING ITEMS APPLY ONLY TO APPLICATIONS FOR NEW TPDES PERMITS AND MAJOR MENDMENTS TO TPDES PERMITS
3.	List construction dates of all buildings and structures on the property:
	Frac VI was finished in 2019 and Frac VIII was finished in 2023.
4.	
	Frac VI and Frac VIII are one of the new additions of a series of fractionators Energy Transfer GC NGL Fractionators have in the area. Property was sold in 2007 to Lone Star
	NGL Mont Belview LP that in 2018 sold the property to Energy Transfer GC NGL
	<u>Fractionators LLC. The builder was S &amp; B Engineers.</u>

#### TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



# INDUSTRIAL WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

The following information **is required** for all applications for a TLAP or an individual TPDES discharge permit.

For **additional information** or clarification on the requested information, please refer to the <u>Instructions for Completing the Industrial Wastewater Permit Application</u><sup>1</sup> available on the TCEQ website. Please contact the Industrial Permits Team at 512-239-4671 with any questions about this form.

If more than one outfall is included in the application, provide applicable information for each individual outfall. **If an item does not apply to the facility, enter N/A** to indicate that the item has been considered. Include separate reports or additional sheets as **clearly cross-referenced attachments** and provide the attachment number in the space provided for the item the attachment addresses.

**NOTE:** This application is for an industrial wastewater permit only. Additional authorizations from the TCEQ Waste Permits Division or the TCEQ Air Permits Division may be needed.

# Item 1. Facility/Site Information (Instructions, Page 39)

a. Describe the general nature of the business and type(s) of industrial and commercial activities. Include all applicable SIC codes (up to 4).

Energy Transfer GC NGL Fractionators LLC operates an existing Natural Gas processing plant that fractionates Y-grade natural gas liquids into ethane, propane, butane, and natural gasoline. The process uses a low vapor pressure heating medium and cooling is provided using Wet Surface Air Cooling (WSAC) technology. The feedstock and products of the facility are stored in off-site salt dome caverns and transported to and from the facility via pipelines, eliminating the need for on-site feedstock or product storage. The facility currently includes Fractionator VI & VIII which are currently permitted for wastewater discharges. This permit application amendment seeks to remove the WET analysis requirement. We have not failed any WET test since obtaining this permit. WET tests have been carried out from EPA NPDES original permit, but Fracs VI/VIII has been complying with them and understand that they are not necessary due to the type of operation at the site. There will be no other changes to this permit. The fractionators discharge throughout the same outfall, Outfall 001. The facility is approximately 0.25 miles south of FM 1942 and 0.75 miles east of Cedar Bayou, in Chambers County, Texas. Applicable SIC Code is 1321.

b. Describe all wastewater-generating processes at the facility.

L

https://www.tceq.texas.gov/permitting/wastewater/industrial/TPDES\_industrial\_wastewater\_steps.html

	The existing facility (Frac VI & VIII) generates non-contact cooling water (blowdown water from WSAC units) as well as Reverse Osmosis reject water, fan fin cleaning water, fire system testing water, emergency showers water, hydrostatic test water from new piping and tanks, if new equipment/tanks need to be installed and non-contact stormwater. The discharge will first go to the detention pond where it will be treated for pH control and then discharged throughout Outfall 001.								
c.	Provide a list of raw materiacility.	ials, major intermediates, and	final products handled at the						
Ma	terials List								
Ra	aw Materials	Intermediate Products	Final Products						
N	atural Gas Liquids		Ethane						
			Propane						
			Butane						
			Natural Gasoline						
	Attachment: Click to enter	text.							
d.	Attach a facility map (draw	n to scale) with the following	information:						
	• Production areas, maintenance areas, materials-handling areas, waste-disposal areas, and water intake structures.								
	• The location of each unit of the WWTP including the location of wastewater collection sumps, impoundments, outfalls, and sampling points, if significantly different from outfall locations.								
	Attachment: TR-1								
e.	Is this a new permit applica	ation for an existing facility?							
	☐ Yes ⊠ No	<del>0</del> ,							
		und discussion: Click to enter	text						
	ii , co, provide buckgrou	ener to enter							

1.	level.
	□ Yes ⊠ No
	List source(s) used to determine 100-year frequency flood plain: <u>FIRM Map, Chambers</u> County, TX, Panel 160 of 175, Map Number 48071C0160F, Map Revised January 19, 2018.
	If <b>no</b> , provide the elevation of the 100-year frequency flood plain and describe what protective measures are used/proposed to prevent flooding (including tail water and rainfall run-on controls) of the treatment facility and disposal area: <u>Elevation is 29.3 at the northern part and 27.7 at the southern part of the property. The detention pond is designed for a 100-yr peak flow and serves as the protective measure designed to control flooding.</u>
	Attachment: TR-2
g.	For <b>new</b> or <b>major amendment</b> permit applications, will any construction operations result in a discharge of fill material into a water in the state?
	$\square$ Yes $\boxtimes$ No $\square$ N/A (renewal only)
h.	If <b>yes</b> to Item 1.g, has the applicant applied for a USACE CWA Chapter 404 Dredge and Fill permit?
	□ Yes □ No
	If <b>yes</b> , provide the permit number: Click to enter text.
	If <b>no</b> , provide an approximate date of application submittal to the USACE: Click to enter text.
It	
	text.
	List any physical, chemical, or biological treatment process(es) used/proposed to treat wastewater at this facility. Include a description of each treatment process, starting with initial treatment and finishing with the outfall/point of disposal.  Energy Transfer GC NGL Fractionators LLC utilizes water from the Coastal Water Authority (CWA) canal to supply water to various units. The water undergoes initial clarification and disinfection when brought into the facility. A reverse osmosis (RO) unit is also used to treat this water prior to utilization in the amine systems associated with Frac VI & Frac VIII. The combined flow from the Frac VI and Frac VIII RO systems will be approximately 340 gpm (489,600 gal/day) of RO concentrate discharged to the WSAC blowdown stream. WSAC blowdown, along with RO reject water, gravity flows to the onsite detention pond prior to discharge through permitted Outfall 001. Anti-Foaming agents is/will be added on an as needed basis, to the cooling water discharges from the existing Frac VI & Frac VIII to prevent the discharge of foam from Outfall 001. Carbon dioxide is added to the cooling water discharges from the existing Frac VI and Frac VIII for pH adjustment. ChemTreat CL427 will be added to the cooling water discharges from the existing Frac VI and Frac VIII to remove the chlorine.
	em 2. Treatment System (Instructions, Page 40)  List any physical, chemical, or biological treatment process(es) used/proposed to treat wastewater at this facility. Include a description of each treatment process, starting with initial treatment and finishing with the outfall/point of disposal.  Energy Transfer GC NGL Fractionators LLC utilizes water from the Coastal Water Authority (CWA) canal to supply water to various units. The water undergoes initial clarification and disinfection when brought into the facility. A reverse osmosis (RO) unit is also used to treat this water prior to utilization in the amine systems associated with Frac VI & Frac VIII. The combined flow from the Frac VI and Frac VIII RO systems will be approximately 340 gpm (489,600 gal/day) of RO concentrate discharged to the WSAC blowdown stream. WSAC blowdown, along with RO reject water, gravity flows to the onsite detention pond prior to discharge through permitted Outfall 001. Anti-Foaming agents is/will be added on an as needed basis, to the cooling water discharges from the existing Frac VI & Frac VIII to prevent the discharge of foam from Outfall 001. Carbon dioxide is added to the cooling water discharges from the existing Frac VI and Frac VIII for pH adjustment. ChemTreat CL427 will be added to the cooling water discharges from

rainwater drain lines into the pond (one per frac). These units are manually

controlled.

• At the pond outlet, we are installing a 6-ton carbon dioxide storage tank, vaporizer, vapor heater, and pH control skid that will take liquid carbon dioxide, vaporize it, mix it with water from the pond in a static mixer, and inject the solution back into the pond through a diffuser. CO2 supply to the static mixer will be automatically controlled using a pH probe reading from the pond.

#### **Residual Chloride Control**

• Two 250-gallon tanks of 10-30% sodium bisulfite solution with injection pumps are installed to treat the RO/WSAC blowdowns that discharges directly to the pond.

b. Attach a flow schematic **with a water balance** showing all sources of water and wastewater flow into the facility, wastewater flow into and from each treatment unit, and wastewater flow to each outfall/point of disposal.

Attachment: TR-3

# Item 3. Impoundments (Instructions, Page 40)

Does the facility use or plan to use any wastewater impoundments (e.g., lagoons or ponds?)

⊠ Yes □ No

If **no**, proceed to Item 4. If **yes**, complete **Item 3.a** for **existing** impoundments and **Items 3.a** - **3.e** for **new or proposed** impoundments. **NOTE:** See instructions, Pages 40-42, for additional information on the attachments required by Items 3.a - 3.e.

a. Complete the table with the following information for each existing, new, or proposed impoundment. Attach additional copies of the Impoundment Information table, if needed.

**Use Designation:** Indicate the use designation for each impoundment as Treatment (**T**), Disposal (**D**), Containment (**C**), or Evaporation (**E**).

Associated Outfall Number: Provide an outfall number if a discharge occurs or will occur.

**Liner Type:** Indicate the liner type as Compacted clay liner (**C**), In-situ clay liner (**I**), Synthetic/plastic/rubber liner (**S**), or Alternate liner (**A**). **NOTE:** See instructions for further detail on liner specifications. If an alternate liner (A) is selected, include an attachment that provides a description of the alternate liner and any additional technical information necessary for an evaluation.

**Leak Detection System:** If any leak detection systems are in place/planned, enter **Y** for yes. Otherwise, enter **N** for no.

**Groundwater Monitoring Wells and Data:** If groundwater monitoring wells are in place/planned, enter **Y** for yes. Otherwise, enter **N** for no. Attach any existing groundwater monitoring data.

**Dimensions:** Provide the dimensions, freeboard, surface area, storage capacity of the impoundments, and the maximum depth (not including freeboard). For impoundments with irregular shapes, submit surface area instead of length and width.

**Compliance with 40 CFR Part 257, Subpart D:** If the impoundment is required to be in compliance with 40 CFR Part 257, Subpart D, enter Y for yes. Otherwise, enter N for no.

**Date of Construction:** Enter the date construction of the impoundment commenced (mm/dd/yy).

#### **Impoundment Information**

Parameter	Pond # 1	Pond #	Pond #	Pond #
Use Designation: (T) (D) (C) or (E)	D			
Associated Outfall Number	001			
Liner Type (C) (I) (S) or (A)	I			
Alt. Liner Attachment Reference	N/A			
Leak Detection System, Y/N	N			
Groundwater Monitoring Wells, Y/N	N			
Groundwater Monitoring Data Attachment	N/A			
Pond Bottom Located Above The Seasonal High-Water Table, Y/N	N			
Length (ft) Irregular shape - Longest side	Approx. 615			
Width (ft) Irregular shape – Longest width	Approx. 410			
Max Depth From Water Surface (ft), Not Including Freeboard	4			
Freeboard (ft)	2			
Surface Area (acres)	5			
Storage Capacity (gallons)	7,168,722			
40 CFR Part 257, Subpart D, Y/N	N			
Date of Construction	2019			

Attachment: Click to enter text.

The following information (Items 3.b - 3.e) is required only for **new or proposed** impoundments.

b.	ite		If attach				ents, attach any available information on the following ne appropriate box. Otherwise, check <b>no</b> or <b>not yet</b>
	1.	Line	er data				
			Yes		No		Not yet designed
	2.	Lea	k detect	ion sy	ystem or	grou	indwater monitoring data
			Yes		No		Not yet designed

3.	3. Groundwater impacts								
		Yes		No		Not yet designed			

**NOTE:** Item b.3 is required if the bottom of the pond is not above the seasonal highwater table in the shallowest water-bearing zone.

Attachment: Click to enter text.

For TLAP applications: Items 3.c - 3.e are not required, continue to Item 4.

c. Attach a USGS map or a color copy of original quality and scale which accurately locates and identifies all known water supply wells and monitor wells within ½-mile of the impoundments.

Attachment: Click to enter text.

d. Attach copies of State Water Well Reports (e.g., driller's logs, completion data, etc.), and data on depths to groundwater for all known water supply wells including a description of how the depths to groundwater were obtained.

Attachment: Click to enter text.

e. Attach information pertaining to the groundwater, soils, geology, pond liner, etc. used to assess the potential for migration of wastes from the impoundments or the potential for contamination of groundwater or surface water.

Attachment: Click to enter text.

# Item 4. Outfall/Disposal Method Information (Instructions, Page 42)

Complete the following tables to describe the location and wastewater discharge or disposal operations for each outfall for discharge, and for each point of disposal for TLAP operations.

If there are more outfalls/points of disposal at the facility than the spaces provided, copies of pages 6 and/0r numbered accordingly (i.e., page 6a, 6b, etc.) may be used to provide information on the additional outfalls.

**For TLAP applications:** Indicate the disposal method and each individual irrigation area **I**, evaporation pond **E**, or subsurface drainage system **S** by providing the appropriate letter designation for the disposal method followed by a numerical designation for each disposal area in the space provided for **Outfall** number (e.g. **E1** for evaporation pond 1, **I2** for irrigation area No. 2, etc.).

#### **Outfall Longitude and Latitude**

Outfall No.	Latitude (Decimal Degrees)	Longitude (Decimal Degrees)
001	29.844887	-94.926993

#### **Outfall Location Description**

Outfall No.	Location Description
001	Southeast of Frac VI. Discharge to an existing drainage ditch.

Outfall No.	Location Description

### Description of Sampling Point(s) (if different from Outfall location)

Outfall No.	Description of sampling point
001	The sampling point is located approximately 385 ft west of Outfall 001.
	Latitude 29.844764, Longitude -94.927598

#### Outfall Flow Information - Permitted and Proposed

Outfall No.	Permitted Daily Avg Flow (MGD)	Permitted Daily Max Flow (MGD)	Proposed Daily Avg Flow (MGD)	Proposed Daily Max Flow (MGD)	Anticipated Discharge Date (mm/dd/yy)
001	Variable	Variable	Variable	Variable	Currently Discharging

#### Outfall Discharge - Method and Measurement

Outfall No.	Pumped Discharge? Y/N	Gravity Discharge? Y/N	Type of Flow Measurement Device Used
001	N	Y	Ultrasonic Flow Meter

#### **Outfall Discharge - Flow Characteristics**

Outfall No.	Intermittent Discharge? Y/N	Continuous Discharge? Y/N	Seasonal Discharge? Y/N	Discharge Duration (hrs/day)	Discharge Duration (days/mo)	Discharge Duration (mo/yr)
001	N	Y	N	24	28-31	12

#### **Outfall Wastestream Contributions**

#### Outfall No. **001**

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow
Hydrostatic Test Water	Variable	0.01
Surface Air Cooler Blowdown	0.4608	36.11
Reverse Osmosis Reject Water	0.4896	38.36
Fire system testing and blowdown	Variable	0.01

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow
Emergency Showers	Variable	0.01
Fan cleaning water	Variable	0.01
Stormwater	Variable	25.35
Public Water System flush water	Variable	0.01
Air Dryer Condensate	0.0016704	0.13
Calculations based in a 1.276 MGD discharge		

#### Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

#### Outfall No. Click to enter text.

<b>Contributing Wastestream</b>	Volume (MGD)	Percent (%) of Total Flow

**Attachment:** Click to enter text.

# Item 5. Blowdown and Once-Through Cooling Water Discharges (Instructions, Page 43)

a. Indicate if the facility currently or proposes to:

$\boxtimes$	Yes □	No	Use cooling towers that discharge blowdown or other wastestreams
	Yes 🗵	No	Use boilers that discharge blowdown or other wastestreams
	Yes 🗵	No	Discharge once-through cooling water

**NOTE:** If the facility uses or plans to use cooling towers or once-through cooling water, Item 12 **is required**.

- b. If **yes** to any of the above, attach an SDS with the following information for each chemical additive.
  - Manufacturers Product Identification Number
  - Product use (e.g., biocide, fungicide, corrosion inhibitor, etc.)
  - Chemical composition including CASRN for each ingredient
  - Classify product as non-persistent, persistent, or bioaccumulative
  - Product or active ingredient half-life
  - Frequency of product use (e.g., 2 hours/day once every two weeks)
  - Product toxicity data specific to fish and aquatic invertebrate organisms
  - Concentration of whole product or active ingredient, as appropriate, in wastestream.

In addition to each SDS, attach a summary of the above information for each specific wastestream and the associated chemical additives. Specify which outfalls are affected.

Attachment: TR-4

c. Cooling Towers and Boilers

If the facility currently or proposes to use cooling towers or boilers that discharge blowdown or other wastestreams to the outfall(s), complete the following table.

#### **Cooling Towers and Boilers**

Type of Unit	Number of Units	Daily Avg Blowdown (gallons/day)	Daily Max Blowdown (gallons/day)
Cooling Towers	2	320	320
Boilers	NA		

### Item 6. Stormwater Management (Instructions, Page 44)

Will any existing/proposed outfalls discharge stormwater associated with industrial activities, as defined at  $40 \ CFR \ \S \ 122.26(b)(14)$ , commingled with any other wastestream?

$\boxtimes$	Yes	No

If **yes**, briefly describe the industrial processes and activities that occur outdoors or in a manner which may result in exposure of the activities or materials to stormwater: <u>During wet weather events</u>, non-contact stormwater run-off from impervious areas, such as rooftops and pavement, as well as from on-site vegetated areas will flow into the stormwater detention pond. The runoff volume into the detention pond will be dependent on rainfall intensity, duration, and frequency. There is oil-filled equipment, oil tanks, emergency generators and chemical tanks exposed to rainwater.

## Item 7. Domestic Sewage, Sewage Sludge, and Septage Management and Disposal (Instructions, Page 44)

*Domestic Sewage* - Waste and wastewater from humans or household operations that is discharged to a wastewater collection system or otherwise enters a treatment works.

a.	Check the box next to the appropriate method of dom				
	sludge treatment or disposal. Complete Worksheet 5.0				
	☑ Domestic sewage is routed (i.e., connected to or tra receive domestic sewage for treatment, disposal, or				
	☐ Domestic sewage disposed of by an on-site septic to Item 7.b.	ank and drainfield system. Complete			
	☐ Domestic and industrial treatment sludge ARE commingled prior to use or disposal.				
	☐ Industrial wastewater and domestic sewage are treated separately, and the respective sludge IS NOT commingled prior to sludge use or disposal. Complete Worksheet 5.0.				
	☐ Facility is a POTW. Complete Worksheet 5.0.				
	☐ Domestic sewage is not generated on-site.				
	☐ Other (e.g., portable toilets), specify and Complete	tem 7.b: Click to enter text.			
b.	Provide the name and TCEQ, NPDES, or TPDES Permit which receives the domestic sewage/septage. If hauled name and TCEQ Registration No. of the hauler.				
	mestic Sewage Plant/Hauler Name				
P	lant/Hauler Name	Permit/Registration No.			
	omestic sewage treatment and disposal is provided y an aerobic on-site sewage facility (OSSF).	SETC-20521-2019			
		SETC-20521-2019			
b	y an aerobic on-site sewage facility (OSSF).				
b		/Enforcement			
It	em 8. Improvements or Compliance,	/Enforcement age 45)			
It	em 8. Improvements or Compliance, Requirements (Instructions, Pa	/Enforcement age 45)			
It a.	em 8. Improvements or Compliance, Requirements (Instructions, Pa  Is the permittee currently required to meet any implement enforcement?	/Enforcement age 45) mentation schedule for compliance of			

Item 9. Toxicity Testing (Instructions, Page 45)	
Have any biological tests for acute or chronic toxicity been made on any of the discharges or on a receiving water in relation to the discharge within the last three years?	•
⊠ Yes □ No	
If <b>yes</b> , identify the tests and describe their purposes: <u>Whole Effluent Toxicity Testing (7-day Chronic Freshwater) for Ceriodapania dubia and Pimephales promelas</u>	
Additionally, attach a copy of all tests performed which <b>have not</b> been submitted to the TCE or EPA. <b>Attachment:</b> Click to enter text.	Q.
Item 10. Off-Site/Third Party Wastes (Instructions, Page 45)	
<ul> <li>a. Does or will the facility receive wastes from off-site sources for treatment at the facility, disposal on-site via land application, or discharge via a permitted outfall?</li> <li>□ Yes ⋈ No</li> </ul>	
If <b>yes</b> , provide responses to Items 10.b through 10.d below.	
If <b>no</b> , proceed to Item 11.	
b. Attach the following information to the application:	
<ul> <li>List of wastes received (including volumes, characterization, and capability with on-sirwastes).</li> </ul>	te
<ul> <li>Identify the sources of wastes received (including the legal name and addresses of the generators).</li> </ul>	ž
• Description of the relationship of waste source(s) with the facility's activities.	
Attachment: Click to enter text.	
c. Is or will wastewater from another TCEQ, NPDES, or TPDES permitted facility commingled with this facility's wastewater after final treatment and prior to discharge via the final outfall/point of disposal?	1
□ Yes □ No	
If <b>yes</b> , provide the name, address, and TCEQ, NPDES, or TPDES permit number of the contributing facility and a copy of any agreements or contracts relating to this activity.	
Attachment: Click to enter text.	
d. Is this facility a POTW that accepts/will accept process wastewater from any SIU and has required to have an approved pretreatment program under the NPDES/TPDES program?	/is
□ Yes □ No	
If yes, Worksheet 6.0 of this application is required.	
Item 11. Radioactive Materials (Instructions, Page 46)	
a. Are/will radioactive materials be mined, used, stored, or processed at this facility?	
☐ Yes ☑ No	

If **yes**, use the following table to provide the results of one analysis of the effluent for all radioactive materials that may be present. Provide results in pCi/L.

Radioactive Material Name	Concentration (pCi/L)
o. Does the applicant or anyone at the facility have any radioactive materials may be present in the discharge radioactive materials in the source waters or on the	ge, including naturally occurring
□ Yes ⊠ No	
If <b>yes</b> , use the following table to provide the results radioactive materials that may be present. Provide r information provided in response to Item 11.a.	
Radioactive Materials Present in the Discharge	
Radioactive Material Name	Concentration (pCi/L)
tem 12. Cooling Water (Instructions	Page 46)
. Does the facility use or propose to use water for coo	
. Does the facility use or propose to use water for coo	
<ul> <li>Does the facility use or propose to use water for cool</li> <li>✓ Yes</li> <li>☐ No</li> <li>☐ Decommissioned: Click to enter text.</li> </ul>	
<ul> <li>Does the facility use or propose to use water for coo</li> <li>✓ Yes</li> <li>☐ No</li> <li>☐ Decommissioned: Click to enter text.</li> </ul>	oling purposes?
<ul> <li>Does the facility use or propose to use water for code</li> <li>✓ Yes</li> <li>☐ No</li> <li>☐ Decommissioned: Click to enter text.</li> <li>☐ To Be Decommissioned: Click to enter text.</li> </ul>	oling purposes?
a. Does the facility use or propose to use water for coo  ☐ Yes ☐ No ☐ Decommissioned: Click to enter text. ☐ To Be Decommissioned: Click to enter text. If yes, complete Items 12.b thru 12.f. If no, stop her	eling purposes?
□ No □ Decommissioned: Click to enter text. □ To Be Decommissioned: Click to enter text.  If yes, complete Items 12.b thru 12.f. If no, stop her  If decommissioned, provide the date operation cease  If to be decommissioned, provide the date operation	eling purposes? eed and stop here. n is anticipated to cease and stop here
<ul> <li>a. Does the facility use or propose to use water for cool</li> <li>  ☐ Yes ☐ No</li> <li>☐ Decommissioned: Click to enter text.</li> <li>☐ To Be Decommissioned: Click to enter text.</li> </ul> If yes, complete Items 12.b thru 12.f. If no, stop her If decommissioned, provide the date operation ceases.	eling purposes? eed and stop here. n is anticipated to cease and stop here

c. Cooling Water Supplier

d.

1. Provide the name of the owner(s) and operator(s) for the CWIS that supplies or will supply water for cooling purposes to the facility.

Cooling Water Intake Structure(s) Owner(s) and Operator(s)

CWIS ID			
Owner	Energy Transfer GC NGL Fractionators, LLC		
Operator	Energy Transfer GC NGL Fractionators, LLC		

wn	er		actionato				
per	ator		gy Transf actionato				
2.	Cooling	water is	s/will be	obtaine	ed from a Public Wa	iter Supplier (PWS)	
		No		Yes; PV	WS No.: <u>TX1010013</u>		
	If <b>no</b> , co	ntinue.	If <b>yes</b> , p	rovide t	the PWS Registratio	n No. and stop here	<u>.</u>
3.	Cooling	water is	s/will be	obtaine	ed from a reclaimed	l water source?	
	$\boxtimes$	No		Yes; Aı	uth No.: Click to en	ter text.	
	If <b>no</b> , co	ntinue.	If <b>yes</b> , p	rovide t	the Reuse Authoriz	ation No. and stop l	nere.
4.	Cooling	water is	s/will be	obtaine	ed from an Indepen	dent Supplier	
		l No		Yes; AI	F: Click to enter tex	xt.	
						ual intake flow of the er for cooling purp	
31	6(b) Gene	ral Crit	eria				
1.					ter for cooling pur of 2 MGD or greater	poses to the facility	has or will have a
		Yes	$\boxtimes$	No			
2.					withdrawn by the C s on an annual aver	WIS(s) is/will be use rage basis.	ed at the facility
		Yes	$\boxtimes$	No			
3.						rater for cooling pur of the United States	
				4-miles	_	coming for and articility. The canal goo	
	If <b>no</b> , pr	ovide a	n explan	ation of	how the waterbod	y does not meet the	definition of

Waters of the United States in 40 CFR § 122.2.

If **yes** to all three questions in Item 12.d, the facility **meets** the minimum criteria to be subject to the full requirements of Section 316(b) of the CWA. Proceed to Item 12.f.

	be subject to the full requirements of Section 316(b) of the CWA; however, a det required based upon BPJ. Proceed to <b>Item 12.e</b> .	ermination is
e.	e. The facility does not meet the minimum requirements to be subject to the fill of Section 316(b) <b>and uses/</b> proposes <b>to use cooling towers</b> .	l requirements
	⊠ Yes □ No	
	If <b>yes</b> , stop here. If <b>no</b> , complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.h allow for a determination based upon BPJ.	o.1, and 3.a to
f.	C. Oil and Gas Exploration and Production	
	1. The facility is subject to requirements at 40 CFR Part 435, Subparts A or 1	Э.
	□ Yes ⊠ No	
	If <b>yes</b> , continue. If <b>no</b> , skip to Item 12.g.	
	2. The facility is an existing facility as defined at 40 CFR § 125.92(k) or a new existing facility as defined at 40 CFR § 125.92(u).	w unit at an
	□ Yes □ No	
	If <b>yes</b> , complete Worksheet 11.0, Items 1.a, 1.b.1-3 and 6, 2.b.1, and 3.a to determination based upon BPJ. If <b>no</b> , skip to Item 12.g.3.	allow for a
g.	g. Compliance Phase and Track Selection	
	1. Phase I – New facility subject to 40 CFR Part 125, Subpart I	
	□ Yes ⊠ No	
	If <b>yes</b> , check the box next to the compliance track selection, attach the re information, and complete Worksheet 11.0, Items 2 and 3, and Worksheet	-
	$\square$ Track I - AIF greater than 2 MGD, but less than 10 MGD	
	• Attach information required by 40 CFR §§ 125.86(b)(2)-(4).	
	□ Track I – AIF greater than 10 MGD	
	• Attach information required by 40 CFR § 125.86(b).	
	□ Track II	
	• Attach information required by 40 CFR § 125.86(c).	
	Attachment: Click to enter text.	
	2. Phase II - Existing facility subject to 40 CFR Part 125, Subpart J	
	□ Yes ⊠ No	
	If <b>yes</b> , complete Worksheets 11.0 through 11.3, as applicable.	
	3. Phase III - New facility subject to 40 CFR Part 125, Subpart N	
	□ Yes ⊠ No	
	If <b>yes</b> , check the box next to the compliance track selection and provide t	he requested
	information.	•

If **no** to any of the questions in Item 12.d, the facility **does not meet** the minimum criteria to

☐ Track I – Fixed	acility
	rmation required by 40 CFR § 125.136(b) and complete Worksheet 2 and 3, and Worksheet 11.2.
□ Track I - Not a	ixed facility
	rmation required by 40 CFR § 125.136(b) and complete Worksheet (except CWIS latitude/longitude under Item 2.a).
□ Track II - Fixed	facility
• Attach info 11.0, Items	rmation required by 40 CFR § 125.136(c) and complete Worksheet 2 and 3.
Attachment: Click to	o enter text.
Item 13. Permit C	hange Requests (Instructions, Page 48)
This item is only applicable	e to existing permitted facilities.
a. Is the facility requesting	g a <b>major amendment</b> of an existing permit?
⊠ Yes □ No	
information regarding t	individually and provide the following information: 1) detailed he scope of each request and 2) a justification for each request. al information or additional data to support each request.
test since obtaining th	emove the WET testing requirement. We have not failed any WET is permit. If eliminating the WET testing is not possible we request ag be changed to once a year instead of quarterly testing.
b. Is the facility requesting	g any <b>minor amendments</b> to the permit?
□ Yes ⊠ N	0
If <b>yes</b> , list and describe	each change individually.
Click to enter text.	
c. Is the facility requesting	g any <b>minor modifications</b> to the permit?
□ Yes ⊠ N	)
If <b>yes</b> , list and describe	each change individually.

Click to enter text.

### Item 14. Laboratory Accreditation (Instructions, Page 49)

All laboratory tests performed must meet the requirements of *30 TAC Chapter 25*, *Environmental Testing Laboratory Accreditation and Certification*, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
  - o periodically inspected by the TCEQ; or
  - o located in another state and is accredited or inspected by that state; or
  - o performing work for another company with a unit located in the same site; or
  - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.

#### **CERTIFICATION:**

I certify that all laboratory tests submitted with this application meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

Printed Name: <u>Brad Widener</u>
Title: <u>Vice-President of Operations</u>
Signature: \_\_\_\_\_\_
Date: \_\_\_\_\_

## INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 1.0: EPA CATEGORICAL EFFLUENT GUIDELINES

This worksheet **is required** for all applications for TPDES permits for discharges of wastewaters subject to EPA categorical effluent limitation guidelines (ELGs).

Item 1. Catego	orical Industries	(Instructions, Pa	ige 53)
Is this facility subject	to any 40 CFR categorica	al ELGs outlined on pag	e 53 of the instructions?
□ Yes ⊠ No			
If <b>no</b> , this worksheet	is not required. If <b>yes</b> , pr	ovide the appropriate in	nformation below.
40 CFR Effluent Guidel	ine		
Industry		40	CFR Part
Item 2. Produc	ction/Process Da	ta (Instructions	, Page 54)
of oil and gas explora	permit applications requation and production was er the Oil and Gas Extract 2 instead.	tewater (discharges into	or adjacent to water in
a. Production Data			
Provide appropriate d	lata for effluent guidelin	es with production-base	d effluent limitations.
Production Data			
Subcategory	Actual Quantity/Day	Design Quantity/Day	Units

Percentage of Total I	Percent of Total	Appendix A and B -	Appendix A -
Subcategory	Production	Metals	Cyanide
. Refineries (40 C	CFR Part 419)		
	ible subcategory and a bi	rief justification.	
	<u> </u>		
Click to enter text.	,		
Itom 3 Proce	acc/Non-Process	- Wastewater Flow	c (Instructions
Item 3. Proce Page		s Wastewater Flow	s (Instructions,
Page Provide a breakdow	<b>54)</b> vn of wastewater flow(s)	generated by the facility, in	ncluding both process
Page Provide a breakdow and non-process wa	<b>54)</b> vn of wastewater flow(s) astewater flow(s). Specification	generated by the facility, is y which wastewater flows a	ncluding both process are to be authorized for
Page Provide a breakdow and non-process wa discharge under thi	54) vn of wastewater flow(s) astewater flow(s). Specifies permit and the dispose	generated by the facility, in y which wastewater flows a sal practices for wastewater	ncluding both process are to be authorized for r flows, excluding
Page Provide a breakdow and non-process wa discharge under thi domestic, which are	vn of wastewater flow(s) astewater flow(s). Specific permit and the dispose not to be authorized for	generated by the facility, is y which wastewater flows a	ncluding both process are to be authorized for r flows, excluding
Page Provide a breakdow and non-process wa discharge under thi	vn of wastewater flow(s) astewater flow(s). Specific permit and the dispose not to be authorized for	generated by the facility, in y which wastewater flows a sal practices for wastewater	ncluding both process are to be authorized for r flows, excluding
Page Provide a breakdow and non-process wa discharge under thi domestic, which are	vn of wastewater flow(s) astewater flow(s). Specific permit and the dispose not to be authorized for	generated by the facility, in y which wastewater flows a sal practices for wastewater	ncluding both process are to be authorized for r flows, excluding
Page Provide a breakdow and non-process wa discharge under thi domestic, which are	vn of wastewater flow(s) astewater flow(s). Specific permit and the dispose not to be authorized for	generated by the facility, in y which wastewater flows a sal practices for wastewater	ncluding both process are to be authorized for r flows, excluding

b. Organic Chemicals, Plastics, and Synthetic Fibers Manufacturing Data (40 CFR Part 414)

## Item 4. New Source Determination (Instructions, Page 54)

Provide a list of all wastewater-generating processes subject to EPA categorical ELGs, identify the appropriate guideline Part and Subpart, and provide the date the process/construction commenced.

**Wastewater Generating Processes Subject to Effluent Guidelines** 

Process	EPA Guideline Part	EPA Guideline Subpart	Date Process/ Construction Commenced

## INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 2.0: POLLUTANT ANALYSIS

Worksheet 2.0 **is required** for all applications submitted for a TPDES permit. Worksheet 2.0 is not required for applications for a permit to dispose of all wastewater by land disposal or for discharges solely of stormwater associated with industrial activities.

## Item 1. General Testing Requirements (Instructions, Page 55)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): 6/25/2025-7/16/2025
- b.  $\boxtimes$  Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Read the general testing requirements in the instructions for important information about sampling, test methods, and MALs. If a contact laboratory was used, attach a list which includes the name, contact information, and pollutants analyzed for each laboratory/firm. Attachment: TR-5

## Item 2. Specific Testing Requirements (Instructions, Page 56)

Attach correspondence from TCEQ approving submittal of less than the required number of samples, if applicable. **Attachment:** <u>Click to enter text.</u>

#### TABLE 1 and TABLE 2 (Instructions, Page 58)

Completion of Tables 1 and 2 is required for all external outfalls for all TPDES permit applications.

Table 1 for Outfall No.: <u>001</u>	Samples are (check one): ⊠	Composite	$\boxtimes$	Grab
-------------------------------------	----------------------------	-----------	-------------	------

Pollutant	Sample 1 (mg/L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
BOD (5-day)	2.76	4.99	3.80	2.46
CBOD (5-day)	2.45	4.76	3.77	2.28
Chemical oxygen demand	79.0	112	48.0	88.0
Total organic carbon	31.3	36.2	13.9	28.0
Dissolved oxygen - Grab (Field)	2.6	0.27	1.00	1.26
Ammonia nitrogen	0.272	0.154	0.172	0.225
Total suspended solids	2.2	3.40	3.40	3.20
Nitrate nitrogen	0.156	0.04	0.547	< 0.01
Total organic nitrogen	1.43	2.03	0.794	1.96
Total phosphorus	0.356	0.419	0.226	0.508
Oil and grease - Grab	<1.51	<1.61	<1.65	<1.57
Total residual chlorine - Grab (Field)	0.000	0.000	0.000	0.000

Pollutant	Sample 1 (mg/L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)
Total dissolved solids	1,330	1,380	592	1,280
Sulfate	527	546	178	564
Chloride	207	243	102	287
Fluoride	1.54	1.63	0.507	1.07
Total alkalinity (mg/L as CaCO3)	236	234	104	248
Temperature (°F) - Grab (Field)	81.1	84.9	81.2	83.4
pH (standard units) - Grab (Field)	7.90	8.01	7.25	7.61

Table 2 for Outfall No.: <u>oo1</u> Samples are (check one): ⊠ Composite ⊠ Grab

Sumples are (check one). A composite A								
Pollutant	Sample 1 (µg/L)	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	MAL (μg/L)			
Aluminum, total	51.6	26.6	63	26.5	2.5			
Antimony, total	0.76	0.53	1.06	0.56	5			
Arsenic, total	6.44	7.53	3.44	6.24	0.5			
Barium, total	274	240	108	263	3			
Beryllium, total	<0.06	< 0.06	< 0.06	< 0.06	0.5			
Cadmium, total	< 0.03	< 0.03	0.13	< 0.03	1			
Chromium, total	1.4	1.24	2.10	1.63	3			
Chromium, hexavalent	<0.5	<0.5	<0.5	0.7	3			
Chromium, trivalent	1.4	1.24	1.8	1.63	N/A			
Copper, total	1.34	1.70	1.94	0.96	2			
Cyanide, available - Grab	< 0.69	1.80	0.80	0.00150	2/10			
Lead, total	0.18	0.11	0.35	0.07	0.5			
Mercury, total	0.0014	0.00132	0.00321	0.00134	0.005/0.0005			
Nickel, total	6.76	5.55	2.31	4.14	2			
Selenium, total	1.17	1.58	0.62	0.75	5			
Silver, total	<0.13	<0.13	< 0.00013	<0.13	0.5			
Thallium, total	< 0.06	< 0.06	< 0.06	<0.06	0.5			
Zinc, total	60.7	60.9	61.7	33.1	5.0			

#### **TABLE 3 (Instructions, Page 58)**

**Completion** of Table 3 **is required** for all **external outfalls** which discharge process wastewater.

**Partial completion** of Table 3 **is required** for all **external outfalls** which discharge non-process wastewater and stormwater associated with industrial activities commingled with other wastestreams (see instructions for additional guidance).

Table 3 for Outfall No.: <u>oo1</u> Samples are (check one): ⊠ Composite □ Grab

Table 3 for Outfall No.: <u>OO1</u>							
Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)*		
Acrylonitrile					50		
Anthracene					10		
Benzene	<1	1.06	<1	<1	10		
Benzidine					50		
Benzo(a)anthracene					5		
Benzo(a)pyrene					5		
Bis(2-chloroethyl)ether					10		
Bis(2-ethylhexyl)phthalate					10		
Bromodichloromethane [Dichlorobromomethane]					10		
Bromoform					10		
Carbon tetrachloride					2		
Chlorobenzene					10		
Chlorodibromomethane [Dibromochloromethane]					10		
Chloroform					10		
Chrysene					5		
m-Cresol [3-Methylphenol]					10		
o-Cresol [2-Methylphenol]					10		
p-Cresol [4-Methylphenol]					10		
1,2-Dibromoethane					10		
m-Dichlorobenzene [1,3-Dichlorobenzene]					10		
o-Dichlorobenzene [1,2-Dichlorobenzene]					10		
p-Dichlorobenzene [1,4-Dichlorobenzene]					10		
3,3'-Dichlorobenzidine					5		
1,2-Dichloroethane	<1	<1	<1	<1	10		

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)*
1,1-Dichloroethene [1,1-Dichloroethylene]					10
Dichloromethane [Methylene chloride]					20
1,2-Dichloropropane					10
1,3-Dichloropropene [1,3-Dichloropropylene]					10
2,4-Dimethylphenol					10
Di-n-Butyl phthalate					10
Epichlorohydrin (1-Chloro-2,3-epoxypropane)					
Ethylbenzene					10
Ethylene Glycol					
Fluoride					500
Hexachlorobenzene					5
Hexachlorobutadiene					10
Hexachlorocyclopentadiene					10
Hexachloroethane					20
4,4'-Isopropylidenediphenol (bisphenol A)					1
Methyl ethyl ketone					50
Methyl tert-butyl ether (MTBE)					
Nitrobenzene	< 0.91	<4.6	< 0.92	< 0.91	10
N-Nitrosodiethylamine					20
N-Nitroso-di-n-butylamine					20
Nonylphenol					333
Pentachlorobenzene					20
Pentachlorophenol					5
Phenanthrene					10
Polychlorinated biphenyls (PCBs) (**)					0.2
Pyridine					20
1,2,4,5-Tetrachlorobenzene					20
1,1,2,2-Tetrachloroethane					10
Tetrachloroethene [Tetrachloroethylene]					10

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)*
Toluene	<1	<1	<1	8.09	10
1,1,1-Trichloroethane					10
1,1,2-Trichloroethane					10
Trichloroethene [Trichloroethylene]					10
2,4,5-Trichlorophenol					50
TTHM (Total trihalomethanes)					10
Vinyl chloride	77				10

<sup>(\*)</sup> Indicate units if different from  $\mu$ g/L.

No

#### **TABLE 4 (Instructions, Pages 58-59)**

Partial completion of Table 4 **is required** for each **external outfall** based on the conditions below.

#### a. Tributyltin

Yes

Is this facility an industrial/commercial facility which currently or proposes to directly dispose of wastewater from the types of operations listed below or a domestic facility which currently or proposes to receive wastewater from the types of industrial/commercial operations listed below?

•		check the box next to each of the following criteria which apply and provide the briate testing results in Table 4 below (check all that apply).
	]	Manufacturers and formulators of tributyltin or related compounds.
	]	Painting of ships, boats and marine structures.
	]	Ship and boat building and repairing.

- Ship and boat cleaning, salvage, wrecking and scaling.Operation and maintenance of marine cargo handling facilities and marinas.
- ☐ Facilities engaged in wood preserving.
- Any other industrial/commercial facility for which tributyltin is known to be present, or for which there is any reason to believe that tributyltin may be present in the effluent.

#### b. Enterococci (discharge to saltwater)

This facility discharges/proposes to discharge directly into saltwater receiving waters **and** Enterococci bacteria are expected to be present in the discharge based on facility processes.

No

<sup>(\*\*)</sup> Total of detects for PCB-1242, PCB-1254, PCB-1221, PCB-1232, PCB-1248, PCB-1260, and PCB-1016. If all non-detects, enter the highest non-detect preceded by a "<".

Domestic wastewater is	/will be disch	arged.					
□ Yes ⊠ No	)						
If <b>yes to either</b> question	n, provide the	appropr	iate testing r	esults in	Table 4	below.	
c. E. coli (discharge to fre	shwater)						
This facility discharges, <i>E. coli</i> bacteria are expe							
□ Yes ⊠ No	)						
Domestic wastewater is	/will be disch	arged.					
□ Yes ⊠ No	)						
If <b>yes to either</b> question	n, provide the	appropr	iate testing r	esults in	Table 4	below.	
Гable 4 for Outfall No.: <u>N/A</u>		Sampl	es are (check	one): 🗆	Compo	site 🗆	Grab
Pollutant	Sa	mple 1	Sample 2	Sample	e 3 Sa	mple 4	MAL
Tributyltin (μg/L)							0.010
Enterococci (cfu or MPN/1	00 mL)						N/A
E. coli (cfu or MPN/100 ml							N/A
Completion of Table 5 is rewastewater from a facility wastewaters which may confif this facility does not/will not/will not discharge otherwards N/A  Table 5 for Outfall No.: Click	which manufantain pesticide not manufacer wastewaters	es or her ture or fo that ma	f formulates bicides. ormulate pes y contain pe	pesticides o sticides o sticides	es or herbicor herbicor herbicor	rbicides dides and cides, ch	l does eck N/A. <b>Grab</b>
Pollutant	Sample 1 (µg/L)*	Sample (µg/L)*			Sample ( (µg/L)*		
Aldrin	(μg/ L)	(μg/L)	(μg/L	, ,	(μg/ L)	(μg,	
						5	<u> </u>
Chlordone							
Chlordane						0.2	
Chlorpyrifos						0.05	<del></del>
4,4'-DDD						0.1	
4,4'-DDE						0.1	
4,4'-DDT						0.02	<u> </u>
2,4-D						0.7	
Danitol [Fenpropathrin]						_	

Demeton

Diazinon

0.20

0.5/0.1

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)*
Dicofol [Kelthane]					1
Dieldrin					0.02
Diuron					0.090
Endosulfan I ( <i>alpha</i> )					0.01
Endosulfan II ( <i>beta</i> )					0.02
Endosulfan sulfate					0.1
Endrin					0.02
Guthion [Azinphos methyl]					0.1
Heptachlor					0.01
Heptachlor epoxide					0.01
Hexachlorocyclohexane (alpha)					0.05
Hexachlorocyclohexane (beta)					0.05
Hexachlorocyclohexane (gamma) [Lindane]					0.05
Hexachlorophene					10
Malathion					0.1
Methoxychlor					2.0
Mirex					0.02
Parathion (ethyl)					0.1
Toxaphene					0.3
2,4,5-TP [Silvex]					0.3

<sup>\*</sup> Indicate units if different from µg/L.

### **TABLE 6 (Instructions, Page 59)**

Completion of Table 6 is required for all external outfalls.

Table 6 for Outfall No.: <u>001</u> Samples are (check one): ⊠ Composite □ Grab

Pollutants	Believed Present	Believed Absent	Sample 1 (mg/L)	Sample 2 (mg/L)	Sample 3 (mg/L)	Sample 4 (mg/L)	MAL (μg/L)*
Bromide		$\boxtimes$					400
Color (PCU)		$\boxtimes$					_
Nitrate-Nitrite (as N)		$\boxtimes$					_
Sulfide (as S)		$\boxtimes$					_
Sulfite (as SO3)		$\boxtimes$					_
Surfactants		$\boxtimes$					_
Boron, total		$\boxtimes$					20
Cobalt, total		$\boxtimes$					0.3
Iron, total	$\boxtimes$		0.106	0.106	0.0920	0.0880	7
Magnesium, total	$\boxtimes$		19.2	24.6	7.57	21.7	20
Manganese, total	$\boxtimes$		0.100	0.12	0.0327	0.159	0.5
Molybdenum, total		$\boxtimes$					1
Tin, total	$\boxtimes$		0.206	0.223	0.08	0.163	5
Titanium, total	$\boxtimes$		0.002	0.001	0.004	0.001	30

#### **TABLE 7 (Instructions, Page 60)**

Check the box next to any of the industrial categories applicable to this facility. If no categories are applicable, check N/A. If GC/MS testing is required, check the box provided to confirm the testing results for the appropriate parameters are provided with the application.

#### ⊠ N/A

#### **Table 7 for Applicable Industrial Categories**

0 /					Acids Table 9		Bases/ Neutrals Table 10		Pesticides Table 11	
	Adhesives and Sealants			Yes		Yes		Yes	No	
	Aluminum Forming	467		Yes		Yes		Yes	No	
	Auto and Other Laundries			Yes		Yes		Yes		Yes
	Battery Manufacturing	461		Yes	No			Yes	No	
	Coal Mining	434	No		No		No		No	
	Coil Coating	465		Yes		Yes		Yes	No	
	Copper Forming	468		Yes		Yes		Yes	No	
	Electric and Electronic Components	469		Yes		Yes		Yes		Yes
	Electroplating	413		Yes		Yes		Yes	No	
	Explosives Manufacturing	457	No			Yes		Yes	No	
	Foundries			Yes		Yes		Yes	No	
	Gum and Wood Chemicals - Subparts A,B,C,E	454		Yes		Yes	No		No	
	Gum and Wood Chemicals - Subparts D,F	454		Yes		Yes		Yes	No	
	Inorganic Chemicals Manufacturing	415		Yes		Yes		Yes	No	
	Iron and Steel Manufacturing	420		Yes		Yes		Yes	No	
	Leather Tanning and Finishing	425		Yes		Yes		Yes	No	
	Mechanical Products Manufacturing			Yes		Yes		Yes	No	
	Nonferrous Metals Manufacturing	421,471		Yes		Yes		Yes		Yes
	Oil and Gas Extraction - Subparts A, D, E, F, G, H	435		Yes		Yes		Yes	No	
	Ore Mining - Subpart B	440	No			Yes	No		No	
	Organic Chemicals Manufacturing	414		Yes		Yes		Yes		Yes
	Paint and Ink Formulation	446,447		Yes		Yes		Yes	No	
	Pesticides	455		Yes		Yes		Yes		Yes
	Petroleum Refining	419		Yes	No		No		No	
	Pharmaceutical Preparations	439		Yes		Yes		Yes	No	
	Photographic Equipment and Supplies	459		Yes		Yes		Yes	No	
	Plastic and Synthetic Materials Manufacturing	414		Yes		Yes		Yes		Yes
	Plastic Processing	463		Yes	No		No		No	
	Porcelain Enameling	466	No		No		No		No	
	Printing and Publishing			Yes		Yes		Yes		Yes
	Pulp and Paperboard Mills - Subpart C	430		*		Yes		*		Yes
	Pulp and Paperboard Mills - Subparts F, K	430		*		Yes		*		*
	Pulp and Paperboard Mills - Subparts A, B, D, G, H	430		Yes		Yes		*		*
	Pulp and Paperboard Mills - Subparts I, J, L	430		Yes		Yes		*		Yes
	Pulp and Paperboard Mills - Subpart E	430		Yes		Yes		Yes		*
	Rubber Processing	428		Yes		Yes		Yes	No	
	Soap and Detergent Manufacturing	417		Yes		Yes		Yes	No	
	Steam Electric Power Plants	423		Yes		Yes	No		No	
	Textile Mills (Not Subpart C)	410		Yes		Yes		Yes	No	
	Timber Products Processing	429		Yes		Yes		Yes		Yes

<sup>\*</sup> Test if believed present.

#### TABLES 8, 9, 10, and 11 (Instructions, Page 60)

Completion of Tables 8, 9, 10, and 11 **is required** as specified in Table 7 for all **external outfalls** that contain process wastewater.

Completion of Tables 8, 9, 10, and 11 **may be required** for types of industry not specified in Table 7 for specific parameters that are believed to be present in the wastewater.

Table 8 for Outfall No.: N/A Samples are (check one):  $\square$  Composite  $\square$  Grab

Pollutant	Sample 1	Sample 2	Sample 3	Sample 4	MAL
	(μg/L)*	(μg/L)*	(μg/L)*	(μg/L)*	(µg/L)
Acrolein					50
Acrylonitrile					50
Benzene					10
Bromoform					10
Carbon tetrachloride					2
Chlorobenzene					10
Chlorodibromomethane					10
Chloroethane					50
2-Chloroethylvinyl ether					10
Chloroform					10
Dichlorobromomethane [Bromodichloromethane]					10
1,1-Dichloroethane					10
1,2-Dichloroethane					10
1,1-Dichloroethylene [1,1-Dichloroethene]					10
1,2-Dichloropropane					10
1,3-Dichloropropylene [1,3-Dichloropropene]					10
Ethylbenzene					10
Methyl bromide [Bromomethane]					50
Methyl chloride [Chloromethane]					50
Methylene chloride [Dichloromethane]					20
1,1,2,2-Tetrachloroethane					10
Tetrachloroethylene [Tetrachloroethene]					10
Toluene					10
1,2-Trans-dichloroethylene [1,2-Trans-dichloroethene]					10

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
1,1,1-Trichloroethane					10
1,1,2-Trichloroethane					10
Trichloroethylene [Trichloroethene]					10
Vinyl chloride					10

<sup>\*</sup> Indicate units if different from µg/L.

Table Of an Orafall Na a N/A

Table 9 for Outfall No.: N/A	Samp	oles are (check	cone): 🔲 🖰 Co	mposite $\square$	Grab
Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
2-Chlorophenol					10
2,4-Dichlorophenol					10
2,4-Dimethylphenol					10
4,6-Dinitro-o-cresol					50
2,4-Dinitrophenol					50
2-Nitrophenol					20
4-Nitrophenol					50
p-Chloro-m-cresol					10
Pentachlorophenol					5
Phenol					10
2,4,6-Trichlorophenol					10

<sup>\*</sup> Indicate units if different from µg/L.

Table 10 for Outfall No.: N/A Samples are (c

Samples are (check one): □	Composite		Grab
----------------------------	-----------	--	------

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
Acenaphthene					10
Acenaphthylene					10
Anthracene					10
Benzidine					50
Benzo(a)anthracene					5
Benzo(a)pyrene					5
3,4-Benzofluoranthene [Benzo(b)fluoranthene]					10
Benzo(ghi)perylene					20
Benzo(k)fluoranthene					5
Bis(2-chloroethoxy)methane					10

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
Bis(2-chloroethyl)ether					10
Bis(2-chloroisopropyl)ether					10
Bis(2-ethylhexyl)phthalate					10
4-Bromophenyl phenyl ether					10
Butylbenzyl phthalate					10
2-Chloronaphthalene					10
4-Chlorophenyl phenyl ether					10
Chrysene					5
Dibenzo(a,h)anthracene					5
1,2-Dichlorobenzene [o-Dichlorobenzene]					10
1,3-Dichlorobenzene [m-Dichlorobenzene]					10
1,4-Dichlorobenzene [p-Dichlorobenzene]					10
3,3'-Dichlorobenzidine					5
Diethyl phthalate					10
Dimethyl phthalate					10
Di-n-butyl phthalate					10
2,4-Dinitrotoluene					10
2,6-Dinitrotoluene					10
Di-n-octyl phthalate					10
1,2-Diphenylhydrazine (as Azobenzene)					20
Fluoranthene					10
Fluorene					10
Hexachlorobenzene					5
Hexachlorobutadiene					10
Hexachlorocyclopentadiene					10
Hexachloroethane					20
Indeno(1,2,3-cd)pyrene					5
Isophorone					10
Naphthalene					10
Nitrobenzene					10
N-Nitrosodimethylamine					50

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
N-Nitrosodi-n-propylamine					20
N-Nitrosodiphenylamine					20
Phenanthrene					10
Pyrene					10
1,2,4-Trichlorobenzene					10

<sup>\*</sup> Indicate units if different from µg/L.

Table 11 for Outfall No.: N/A Samples are (check one):  $\square$  Composite  $\square$  Grab

Pollutant	Sample 1	Sample 2	Sample 3	Sample 4	MAL
	(μg/L)*	(μg/L)*	(μg/L)*	(μg/L)*	(µg/L)
Aldrin					0.01
alpha-BHC [alpha-Hexachlorocyclohexane]					0.05
beta-BHC [beta-Hexachlorocyclohexane]					0.05
gamma-BHC [gamma-Hexachlorocyclohexane]					0.05
delta-BHC [delta-Hexachlorocyclohexane]					0.05
Chlordane					0.2
4,4'-DDT					0.02
4,4'-DDE					0.1
4,4'-DDD					0.1
Dieldrin					0.02
Endosulfan I (alpha)					0.01
Endosulfan II (beta)					0.02
Endosulfan sulfate					0.1
Endrin					0.02
Endrin aldehyde					0.1
Heptachlor					0.01
Heptachlor epoxide					0.01
PCB 1242					0.2
PCB 1254					0.2
PCB 1221					0.2
PCB 1232					0.2
PCB 1248					0.2
		_1	1	1	1

Pollutant	Sample 1 (µg/L)*	Sample 2 (µg/L)*	Sample 3 (µg/L)*	Sample 4 (µg/L)*	MAL (μg/L)
PCB 1260					0.2
PCB 1016					0.2
Toxaphene					0.3

<sup>\*</sup> Indicate units if different from µg/L.

Attachment: Click to enter text.

#### TABLE 12 (DIOXINS/FURAN COMPOUNDS)

Complete of Table 12 **is required** for **external outfalls**, as directed below. (Instructions, Pages 59-60)

Indicate which compound(s) are manufactured or used at the facility and provide a brief description of the conditions of its/their presence at the facility (check all that apply).

- □ 2,4,5-trichlorophenoxy acetic acid (2,4,5-T) CASRN 93-76-5
- 2-(2,4,5-trichlorophenoxy) propanoic acid (Silvex, 2,4,5-TP) CASRN 93-72-1
- 2-(2,4,5-trichlorophenoxy) ethyl 2,2-dichloropropionate (Erbon) CASRN 136-25-4
- □ 0,0-dimethyl 0-(2,4,5-trichlorophenyl) phosphorothioate (Ronnel) CASRN 299-84-3
- □ 2,4,5-trichlorophenol (TCP) CASRN 95-95-4
- □ hexachlorophene (HCP) CASRN 70-30-4
- None of the above

Description: Click to enter text.

Does the applicant or anyone at the facility know or have any reason to believe that 2,3,7,8-tetrachlorodibenzo-p-dioxin (TCDD) or any congeners of TCDD may be present in the effluent proposed for discharge?

□ Yes ⊠ No

Description: Click to enter text.

If **yes** to either Items a **or** b, complete Table 12 as instructed.

Table 12 for Outfall No.: N/A Samples are (check one): ☐ Composite ☐ Grab

Compound	Toxicity Equivalent Factors	Wastewater Concentration (ppq)	Wastewater Toxicity Equivalents (ppq)	Sludge Concentration (ppt)	Sludge Toxicity Equivalents (ppt)	MAL (ppq)
2,3,7,8-TCDD	1					10
1,2,3,7,8- PeCDD	1.0					50
2,3,7,8- HxCDDs	0.1					50
1,2,3,4,6,7,8- HpCDD	0.01					50

Compound	Toxicity Equivalent Factors	Wastewater Concentration (ppq)	Wastewater Toxicity Equivalents (ppq)	Sludge Concentration (ppt)	Sludge Toxicity Equivalents (ppt)	MAL (ppq)
2,3,7,8-TCDF	0.1					10
1,2,3,7,8- PeCDF	0.03					50
2,3,4,7,8- PeCDF	0.3					50
2,3,7,8- HxCDFs	0.1					50
2,3,4,7,8- HpCDFs	0.01					50
OCDD	0.0003					100
OCDF	0.0003					100
PCB 77	0.0001					500
PCB 81	0.0003					500
PCB 126	0.1					500
PCB 169	0.03					500
Total						

#### **TABLE 13 (HAZARDOUS SUBSTANCES)**

Complete Table 13 **is required** for all **external outfalls** as directed below. (Instructions, Pages 60-61)

Are there any pollutants listed in the instructions (pages 55-62) believed present in the discharge?

⊠ Yes □ No

Are there pollutants listed in Item 1.c. of Technical Report 1.0 which are believed present in the discharge and have not been analytically quantified elsewhere in this application?

□ Yes ⊠ No

If **yes** to either Items a **or** b, complete Table 13 as instructed.

Table 13 for Outfall No.:	Sampl	es are (checl	k one): 🛛 🔾	Composite	□ Grab	
Pollutant	CASRN	Sample 1 (µg/L)	Sample 2 (µg/L)	Sample 3 (µg/L)	Sample 4 (µg/L)	Analytical Method
Phenol, Total - Grab	108-95-2	<4.5	<4.5	<4.5	<4.5	

## INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 4.0: RECEIVING WATERS

This worksheet is required for all TPDES permit applications.

## Item 1. Domestic Drinking Water Supply (Instructions, Page 80)

a.	There is a surface water intake for domestic drinking water supply located within 5 (five) miles downstream from the point/proposed point of discharge.
	□ Yes ⊠ No
	If <b>no</b> , stop here and proceed to Item 2. If <b>yes</b> , provide the following information:
	1. The legal name of the owner of the drinking water supply intake: <u>Click to enter text.</u>
	2. The distance and direction from the outfall to the drinking water supply intake: <u>Click to enter text.</u>
b.	Locate and identify the intake on the USGS 7.5-minute topographic map provided for Administrative Report 1.0.
	☐ Check this box to confirm the above requested information is provided.
Ito	em 2. Discharge Into Tidally Influenced Waters (Instructions, Page 80)
	the discharge is to tidally influenced waters, complete this section. Otherwise, proceed to m 3.
a.	Width of the receiving water at the outfall: <u>Click to enter text.</u> feet
b.	Are there oyster reefs in the vicinity of the discharge?
	□ Yes □ No
	If <b>yes</b> , provide the distance and direction from the outfall(s) to the oyster reefs: <u>Click to enter text.</u>
c.	Are there sea grasses within the vicinity of the point of discharge?
	□ Yes □ No
	If <b>yes</b> , provide the distance and direction from the outfall(s) to the grasses: Click to enter text.
Ito	em 3. Classified Segment (Instructions, Page 80)
Th	e discharge is/will be directly into (or within 300 feet of) a classified segment.
	□ Yes ⊠ No
If y	ves, stop here and do not complete Items 4 and 5 of this worksheet or Worksheet 4.1.
If 1	<b>10</b> , complete Items 4 and 5 and Worksheet 4.1 may be required.

## Item 4. Description of Immediate Receiving Waters (Instructions, Page 80)

		(Instructions, Page 80)
a.	Name	e of the immediate receiving waters: <u>Click to enter text.</u>
b.	Chec	k the appropriate description of the immediate receiving waters:
		ake or Pond
	•	Surface area (acres): Click to enter text.
	•	Average depth of the entire water body (feet): Click to enter text.
	•	Average depth of water body within a 500-foot radius of the discharge point (feet): <u>Click to enter text.</u>
		Man-Made Channel or Ditch
		tream or Creek
		reshwater Swamp or Marsh
		idal Stream, Bayou, or Marsh
		Open Bay
		Other, specify:
		<b>Tade Channel or Ditch</b> or <b>Stream or Creek</b> were selected above, provide responses to $z - 4.g$ below:
c.		<b>xisting discharges</b> , check the description below that best characterizes the area <b>eam</b> of the discharge.
		ew discharges, check the description below that best characterizes the area astream of the discharge.
		Intermittent (dry for at least one week during most years)
		Intermittent with Perennial Pools (enduring pools containing habitat to maintain aquatic life uses)
		Perennial (normally flowing)
		k the source(s) of the information used to characterize the area upstream (existing arge) or downstream (new discharge):
		USGS flow records
	$\boxtimes$	personal observation
		historical observation by adjacent landowner(s)
		other, specify: <u>Click to enter text.</u>
d.		he names of all perennial streams that join the receiving water within three miles stream of the discharge point: None.
e.		eceiving water characteristics change within three miles downstream of the discharge natural or man-made dams, ponds, reservoirs, etc.).  Yes $\square$ No

f. General observations of the water body during normal dry weather conditions: At the ditch usually is running water from other facilities before it meets with Frac VI & VIII discharge where the flow increases going south to Cedar Bayou. Date and time of observation: 6/13/2025g. The water body was influenced by stormwater runoff during observations.  $\boxtimes$ Yes No If **yes**, describe how: It was raining before the visit, during the visit and after the visit. Item 5. General Characteristics of Water Body (Instructions, Page 81) a. Is the receiving water upstream of the existing discharge or proposed discharge site influenced by any of the following (check all that apply): oil field activities urban runoff agricultural runoff septic tanks upstream discharges other, specify: Click to enter text. b. Uses of water body observed or evidence of such uses (check all that apply): livestock watering industrial water supply irrigation withdrawal non-contact recreation domestic water supply navigation contact recreation picnic/park activities other, specify:Support of forests fishing c. Description which best describes the aesthetics of the receiving water and the surrounding area (check only one): **Wilderness:** outstanding natural beauty; usually wooded or un-pastured area: water clarity exceptional **Natural Area:** trees or native vegetation common; some development evident (from fields, pastures, dwellings); water clarity discolored **Common Setting:** not offensive, developed but uncluttered; water may be colored or turbid Offensive: stream does not enhance aesthetics; cluttered; highly developed; dumping areas; water discolored

If **yes**, describe how: Click to enter text.

## INDUSTRIAL WASTEWATER PERMIT APPLICATION WORKSHEET 7.0: STORMWATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITIES

This worksheet **is required** for all TPDES permit applications requesting individual permit coverage for discharges consisting of **either**: 1) solely of stormwater discharges associated with industrial activities, as defined in 40 CFR § 122.26(b)(14)(i-xi), **or** 2) stormwater discharges associated with industrial activities and any of the listed allowable non-stormwater discharges, as defined in the MSGP (TXR05000), Part II, Section A, Item 6.

Discharges of stormwater as defined in 40 CFR § 122.26 (b)(13) are not required to obtain authorization under a TPDES permit (see exceptions at 40 CFR §§ 122.26(a)(1) and (9)). Authorization for discharge may be required from a local municipal separate storm sewer system.

## Item 1. Applicability (Instructions, Page 89)

Do discharges from any of the existing/proposed outfalls consist either 1) solely of stormwater discharges associated with industrial activities **or** 2) stormwater discharges associated with industrial activities and any of the allowable non-stormwater discharges?

⊠ Yes □ No

If **no**, stop here. If **yes**, proceed as directed.

## Item 2. Stormwater Coverage (Instructions, Page 89)

List each existing/proposed stormwater outfall at the facility and indicate which type of authorization covers or is proposed to cover discharges.

#### **Authorization Coverage**

Outfall	Authorization under MSGP	Authorized Under Individual Permit
001		

If **all** existing/proposed outfalls which discharge stormwater associated with industrial activities (and any of the allowable non-stormwater discharges) are **authorized under the MSGP**, **stop** here.

If **seeking authorization** for any outfalls which discharge stormwater associated with industrial activities (and any of the allowable non-stormwater discharges) **under an individual permit, proceed**.

NOTE: The following information is required for each existing/proposed stormwater outfall for which the facility is seeking individual permit authorization under this application

### Item 3. Site Map (Instructions, Page 90)

Attach a site map or maps (drawn to scale) of the entire facility with the following information.

- the location of each stormwater outfall to be covered by the permit
- an outline of the drainage area that is within the facility's boundary and that contributes stormwater to each outfall to be covered by the permit
- connections or discharge points to municipal separate storm sewer systems
- locations of all structures (e.g. buildings, garages, storage tanks)
- structural control devices that are designed to reduce pollution in discharges of stormwater associated with industrial activities
- process wastewater treatment units (including ponds)
- bag house and other air treatment units exposed to stormwater (stormwater runoff, snow melt runoff, and surface runoff and drainage)
- landfills; scrapyards; surface water bodies (including wetlands)
- vehicle and equipment maintenance areas
- physical features of the site that may influence discharges of stormwater associated with industrial activities or contribute a dry weather flow
- locations where spills or leaks of reportable quality (as defined in 30 TAC § 327.4) have occurred during the three years before this application was submitted to obtain coverage under an individual permit
- processing areas, storage areas, material loading/unloading areas, and other locations where significant materials are exposed to stormwater (stormwater runoff, snow melt runoff, and surface runoff and drainage)
- ☑ Check the box to confirm all above information was provided on the facility site map(s).

Attachment: TR-6

## Item 4. Facility/Site Information (Instructions, Page 90)

a. Provide the area of impervious surface and the total area drained by each stormwater outfall requested for authorization by this permit application.

#### **Impervious Surfaces**

Outfall	Area of Impervious Surface (include units)	Total Area Drained (include units)
001	15.8 acres	49.6 acres

b. Provide the following local area rainfall information and the source of the information.

Wettest month: June

Average rainfall for wettest month (total inches): 7.44

25-year, 24-hour rainfall (inches): 12.3

Source: NOAA precipitation frequency estimates for the 25-year, 24-hour and from the US Climate Data 2021 for the remaining information.

- c. Attach an inventory, or list, of materials currently handled at the facility that may be exposed to precipitation. **Attachment:** <u>TR-7</u>
- d. Attach narrative descriptions of the industrial processes and activities involving the materials in the above-listed inventory that occur outdoors or in some manner that may result in exposure of the materials to precipitation or runoff (see instructions for guidance). **Attachment: TR-7**
- e. Describe any BMPs and controls the facility uses/proposes to prevent or effectively reduce pollution in stormwater discharges from the facility: TR-7

## Item 5. Pollutant Analysis (Instructions, Page 91)

- a. Provide the date range of all sampling events conducted to obtain the analytical data submitted with this application (e.g., 05/01/2018-05/30/2018): NA
- b.  $\square$  Check the box to confirm all samples were collected no more than 12 months prior to the date of application submittal.
- c. Complete Table 17 as directed on page 92 of the Instructions.

#### Table 14 for Outfall No.: NA

Pollutant	Grab Sample* Maximum (mg/L)	Composite Sample** Maximum (mg/L)	Grab Sample* Average (mg/L)	Composite Sample** Average (mg/L)	Number of Storm Events Sampled	MAL (mg/L)
pH (standard units)	(max)	_	(min)	_		_
Total suspended solids						_
Chemical oxygen demand						_
Total organic carbon						_
Oil and grease						_
Arsenic, total						0.0005
Barium, total						0.003
Cadmium, total						0.001
Chromium, total						0.003
Chromium, trivalent						_
Chromium, hexavalent						0.003
Copper, total						0.002

Pollutant	Grab Sample* Maximum (mg/L)	Composite Sample** Maximum (mg/L)	Grab Sample* Average (mg/L)	Composite Sample** Average (mg/L)	Number of Storm Events Sampled	MAL (mg/L)
Lead, total						0.0005
Mercury, total						0.000005
Nickel, total						0.002
Selenium, total						0.005
Silver, total						0.0005
Zinc, total						0.005

<sup>\*</sup> Taken during first 30 minutes of storm event

d. Complete Table 18 as directed on pages 92-94 of the Instructions.

Table 15 for Outfall No.: NA

Pollutant	Grab Sample* Maximum (mg/L)	Composite Sample** Maximum (mg/L)	Grab Sample* Average (mg/L)	Composite Sample** Average (mg/L)	Number of Storm Events Sampled

<sup>\*</sup> Taken during first 30 minutes of storm event

Attachment: Click to enter text.

<sup>\*\*</sup> Flow-weighted composite sample

<sup>\*\*</sup> Flow-weighted composite sample

## Item 6. Storm Event Data (Instructions, Page 93)

Provide the following data for the storm event(s) which resulted in the maximum values for the analytical data submitted: All other dates of sampling there was no rain, except for the date shown here.

Date of storm event: <u>07/09/2025</u>

Duration of storm event (minutes): 100

Total rainfall during storm event (inches): <u>0.28</u>

Number of hours the between beginning of the storm measured and the end of the previous measurable storm event (hours): 16

Maximum flow rate during rain event (gallons/minute): 1,870

Total stormwater flow from rain event (gallons): 186,988

Provide a description of the method of flow measurement or estimate:

**Rational Method:** 

O = CiA

C (Rational runoff coefficient) (industrial area) = 0.5

Rainfall intensity, i (in/hr): (0.28 inch/100 min) (60 min/1 hr) = 0.168 inch/hr

Drainage Area, A (Acres): 49.6 acres

Peak Discharge, Q (gpm): (0.5)(0.168)(49.6)(7.48)(60) = 1,870 gallon/min





## National Flood Hazard Layer FIRMette




Basemap Imagery Source: USGS National Map 2023



#### Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT



This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap


accuracy standards

point selected by the user and does not represent


an authoritative property location.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 6/17/2025 at 1:03 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.








FEMA Flood General Map Fractionators 6 & 8 Chambers County, TEXAS

Project Number: 212C-HN-03455



Attachment TR-2







#### Attachment No. 10

#### List of chemicals and SDSs

Manufacturers Product ID	Product Use	CASRN/Chemical Composition			Product Classification	Active Ingredient half- life	Frequency of product use	Product Toxicity Data	Concentration in Waste stream
AC-455	Corrosion Inhibitor	7681-57-4	sodium metabisulphite	<20%	Non-persistent	Not Available	Continuously	No relevant information available	Very low
AC-777	Membrane anti-scalent inhibitor	20592-85-2	Phosphonic acid,P,P',P"- [nitrilotris(methylene)]tris-, sodium salt	10-20%	Non-persistent	Not Available	Continuously	No relevant information available	Very low
		1310-58-3	Potassium hydroxide	<2%					
CL427	Dechlorinator	7722-84-1	Hydrogen Peroxide	10-30%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
CL456	Corrosion Inhibitor	Trade secret		1	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
CI 2020	NATA A International Alabata	5538-94-3	N, N-Dioctyl-N,N-dimethylammonium chloride	50%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
CL2030	Micro biocide and Algicide	Proprietary solve	ent						
		2809-21-4	1-Hydroxyethylidene-1,1-diphosphoric acid	1-5%					Very low
CL5430	Corrosion Inhibitor	7664-38-2	Phosphoric Acid	7-13%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	
		95-14-7	Benzotriazole	1-5%	1 '			'	
		64665-57-2	Tolyltriazole, sodium salt	1-5%					Very Low
CL5570	Scale Inhibitor	64-02-8	Ethylene diamine tetraacetic acid, tetrasodium salt	1-5%	Non-persistent	Not Available	Continuously	Not determined	
		1310-73-2	Sodium hydroxide	5-10%					
CL5640	Corrosion Inhibitor	37971-36-1	2-Phosphono-1,2,4-butane tricarboxylic acid	7-13%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
CL5644	Corrosion Inhibitor	77-92-9	Citric acid	5-10%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
FlexPro CL5737	Corrosion Inhibitor	77-92-9	Citric acid	1-5%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
FIEXPIO CL3737	Corrosion inhibitor	7664-93-9	Sulfuric acid	1-5%	Non-persistent	Not Available	Continuously	see section 12 of product 3D3	very low
DF20	Foam Control	Proprietary			Non-persistent	Not Available	Continuously	Not determined	Very Low
FFC1	Fin Cleaning Solution	1569-01-3	Propylene glycol n-Propyl Ether (PNP)	<20%	Non-persistent	Not Available	Continuously	Not determined	Very Low
FFCLC	Fin Cleaning Solution	1569-01-3	Propylene glycol n-Propyl Ether (PNP)	<20%	Non-persistent	Not Available	Continuously	Not determined	Very Low
FO120	Defoamer	68002-96-0	Alcohols, C16–18, Ethoxylated Propoxylated	1-5%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
FO180	Defoamer	Trade secret			Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
	Defoamer	63148-62-9	Polydimethylsiloxane	10-40%		Not Available	Continuously See Section 12 of product SDS		
FO220		64742-47-8	Petroleum distillate hydrotreated light	<10%	Non-persistent			Very low	
		112926-00-8	Silicon dioxide	<5%					
P873L	Water Clarification Agent	Trade secret	1	T	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
P893L	Water Clarification Agent	1327-41-9	Polyaluminum chloride	60-100%	Not Available	Not Available	Continuously	See Section 12 of product SDS	Very low
DI 0075	Reverse Osmosis Treatment	22042-96-2	Diethylenetriamine penta methylene phosphonic acid, sodium salt	1-5%	Non porsistant	Not Available	Continuously See Section 12 of product SDS	See Section 12 of product SDS	Very low
RL9075		7631-90-5	Sodium bisulfite	10-30%	Non-persistent			very low	
		37971-36-1	2-Phosphono-1,2,4-butane tricarboxylic acid	1-5%					
Carbon Dioxide	pH Control	124-38-9	Carbon Dioxide	100%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low
Sodium Bisulfite	Residual Chlorine Control	7631-90-5	Sodium Bisulfite	10-30%	Non-persistent	Not Available	Continuously	See Section 12 of product SDS	Very low



#### Attachment No. TR-5 – Laboratory Information

Name: a & b Labs

Address: 10100 East Freeway, Suite 100, Houston, TX 77029

Tel: 713-453-6060, Fax: 713-453-6091

http://www.ablabs.com

Contact Name: Amanda Shute

Pollutants Analyzed by a & b Labs						
BOD (5-day)	Cadmium, total					
CBOD (5-day)	Chromium, total					
Chemical oxygen demand	Chromium, hexavalent					
Total organic carbon	Chromium, trivalent					
Dissolved oxygen	Copper, total					
Ammonia nitrogen	Cyanide, available					
Total suspended solids	Lead, total					
Nitrate nitrogen	Mercury, total					
Total organic nitrogen	Nickel, total					
Total phosphorus	Selenium, total					
Oil and grease	Silver, total					
Total residual chlorine	Thallium, total					
Total dissolved solids	Zinc, total					
Sulfate	Benzene					
Chloride	1,2-Dichloroethane					
Fluoride	Nitrobenzene					
Total alkalinity (mg/L as CaCO3)	Toluene					
Temperature (°F)	Iron, total					
pH (standard units)	Magnesium, total					
Aluminum, total	Manganese, total					
Antimony, total	Tin, total					
Arsenic, total	Titanium, total					
Barium, total	Phenols, total					
Beryllium, total						





#### Attachment No. TR-7 - Inventory of Exposed Materials

Material	Area
Diesel Fuel	Inside aboveground tanks and generator subbase tanks around the facility
Mineral Oil	Inside electric transformers at the substation
Compressor Lube Oil	Inside tanks around the facility
Amine Tanks	Amine area
Hot Oil Reservoir	Amine area
Wet Surface Air Coolers Water Treatment Chemicals	WSAC areas
Reverse Osmosis Chemicals	Reverse Osmosis unit area


All these materials are stored in tanks and the majority of the tanks are inside secondary containment. Diesel fuel is used for emergency generators and fire water pump operation. Mineral oil is used for cooling the electric transformers. Amine and hot oil are used in the process and are tanks inside a closed loop. The compressor lubricating oil is also a closed loop operation and is the only material not inside secondary containment. This material is located in an area that discharges to the pond so if a release occurs, it will be retained in the pond until removed.


The WSAC and reverse osmosis chemicals tanks are inside plastic secondary containments that are drained or disposed with regularity.


The secondary containments and the pond are the BMPs used to prevent pollution in stormwater discharges.

See Attachment TR-1 – Facility map for the location of these materials.

No calculations.







#### **Candice Calhoun**

From: Sexton, Cynthia Mychelle <cynthia.sexton@energytransfer.com>

**Sent:** Wednesday, August 6, 2025 9:22 AM **To:** Candice Calhoun; Crenshaw, Desiree

**Cc:** Awonuga, Olugbenga (Mojeed); Perry, Anthony; Davila, Hope Breaux; CentenoJimenez,

Edwin

Subject: RE: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL

Fractionators LLC) - Notice of Deficiency

**Attachments:** Energy Transfer NOD answer 1.pdf; Industrial Discharge Amendment Spanish

NORI.docx; Attachment AR-6 - Adjacent Landowners Labels Rev 1.docx

Good morning Ms., Calhoun, Please find the attached documents per your request Thanks

#### **Cynthia Sexton**

Associate- Environmental Specialist Energy Transfer

O: 281.576.3616 M: 936.256.0776



From: Candice Calhoun < Candice. Calhoun@tceq.texas.gov>

Sent: Monday, August 4, 2025 10:10 AM

**To:** Crenshaw, Desiree <wylene.crenshaw@energytransfer.com> **Cc:** Sexton, Cynthia Mychelle <cynthia.sexton@energytransfer.com>

Subject: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL Fractionators LLC) - Notice of

Deficiency

Importance: High

Good morning, Ms. Crenshaw,

The attached Notice of Deficiency (NOD) letter dated <u>August 4, 2025,</u> requests additional information needed to declare the application administratively complete. Please send the complete response no later than <u>August 18, 2025.</u>

Please let me know if you have any questions.

Regards,

#### Candice Courville



License & Permit Specialist ARP Team | Water Quality Division Texas Commission on Environmental Quality 512-239-4312

candice.calhoun@tceq.texas.gov

How is our customer service? Fill out our online customer satisfaction survey at <a href="https://www.tceq.texas.gov/customersurvey">www.tceq.texas.gov/customersurvey</a>

Private and confidential as detailed <a href="here">here</a>. If you cannot access hyperlink, please e-mail sender.

#### **Candice Calhoun**

From: CentenoJimenez, Edwin < E.CENTENOJIMENEZ@tetratech.com>

Sent: Wednesday, August 6, 2025 10:26 AM

**To:** Candice Calhoun; Sexton, Cynthia Mychelle; Crenshaw, Desiree **Cc:** Awonuga, Olugbenga (Mojeed); Perry, Anthony; Davila, Hope Breaux

Subject: Re: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL

Fractionators LLC) - Notice of Deficiency

**Attachments:** Energy Transfer NOD answer.pdf

Ms. Calhoun,

See the correction in the attached document.

Edwin C. Centeno, PE (LA, TX, PR) | Engineering Project Manager II – Environmental PM | Tetra Tech, Inc. Direct +1 (832)-251-6093 | Mobile +1 (832) 872-1075 | e.centenojimenez@tetratech.com

#### Tetra Tech | Complex World, Clear Solutions™

1500 CityWest Boulevard, Ste 1000 | Houston, TX 77042 | tetratech.com







Climate positive and carbon negative by 2030. Read more



This message, including any attachments, may include privileged, confidential and/or inside information. Any distribution or use of this communication by anyone other than the intended recipient is strictly prohibited and may be unlawful. If you are not the intended recipient, please notify the sender by replying to this message and then delete it from your system.



#### Book time to meet with me

From: Candice Calhoun < Candice. Calhoun@tceq.texas.gov>

Sent: Wednesday, August 6, 2025 9:53 AM

To: Sexton, Cynthia Mychelle <cynthia.sexton@energytransfer.com>; Crenshaw, Desiree

<wylene.crenshaw@energytransfer.com>

Cc: Awonuga, Olugbenga (Mojeed) <olumbia (Mojeed) delugbenga.awonuga@energytransfer.com >; Perry, Anthony

<Anthony.Perry@energyTransfer.com>; Davila, Hope Breaux <hope.davila@energytransfer.com>; CentenoJimenez, Edwin <e.centenojimenez@tetratech.com>

**Subject:** RE: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL Fractionators LLC) - Notice of Deficiency

**A CAUTION:** This email originated from an external sender. Verify the source before opening links or attachments. **A** 

Good morning, Cynthia,

Thank you, your response to items 1 through 3, 5 and 6 are all sufficient. However, I do have a question regarding item 4.

In the technical report, for permitted daily average flow and permitted daily max flow, you had put "variable". However, in the current permit it shows 0.936 MGD for the daily average flow and 1.276 MGD for the daily max flow. I am thinking those numbers should be put in those spots instead of "variable" but please correct me if I am wrong. I just want to make sure it is accurate.

Thank you,



#### Candice Courville

License & Permit Specialist ARP Team | Water Quality Division Texas Commission on Environmental Quality 512-239-4312

candice.calhoun@tceq.texas.gov

How is our customer service? Fill out our online customer satisfaction survey at <a href="https://www.tceq.texas.gov/customersurvey">www.tceq.texas.gov/customersurvey</a>

From: Sexton, Cynthia Mychelle <cynthia.sexton@energytransfer.com>

Sent: Wednesday, August 6, 2025 9:22 AM

To: Candice Calhoun <Candice.Calhoun@tceq.texas.gov>; Crenshaw, Desiree <wylene.crenshaw@energytransfer.com>

Cc: Awonuga, Olugbenga (Mojeed) <olumbia (Mojeed) <olumbia (Mojeed) <olumbia (Mojeed) <olumbia (Mojeed) <olumbia (Mojeed) <ol>
 Anthony
 Anthony

<Anthony.Perry@energyTransfer.com>; Davila, Hope Breaux <hope.davila@energytransfer.com>; CentenoJimenez, Edwin <e.centenojimenez@tetratech.com>

**Subject:** RE: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL Fractionators LLC) - Notice of Deficiency

Good morning Ms., Calhoun, Please find the attached documents per your request Thanks



Associate- Environmental Specialist Energy Transfer O: 281.576.3616

M: 936.256.0776




From: Candice Calhoun < Candice. Calhoun@tceq.texas.gov>

**Sent:** Monday, August 4, 2025 10:10 AM

**To:** Crenshaw, Desiree < wylene.crenshaw@energytransfer.com > **Cc:** Sexton, Cynthia Mychelle < cynthia.sexton@energytransfer.com >

Subject: Application to Amend Permit No. WQ0005350000 (Energy Transfer GC NGL Fractionators LLC) - Notice of





August 5, 2025

Candice Calhoun Applications Review and Processing Team (MC 148) Water Quality Division Texas Commission on Environmental Quality P.O. Box 13087 Austin, TX 78711-3087

Via email to: candice.calhoun@tceq.texas.gov

#### RE: Response to TCEQ Notice of Deficiency

Application for Proposed/Permit No.: WQ0005350000 (EPA I.D. No. TX0134068) Applicant Name: Energy Transfer GC NGL Fractionators, LLC (CN604309419)

Site Name: MB Frac VI and VIII (RN109902494)

Type of Application: Major amendment with renewal

Dear Ms. Calhoun:

Energy Transfer GC NGL Fractionators, LLC (Select) and Tetra Tech have reviewed the Notice of Deficiency (NOD) and have provided the original requests from Texas Commission on Environmental Quality (TCEQ) and the following responses:

#### TCEQ Comment:

1. Item 1 – Supplemental Permit Information Form (SPIF): The location listed in item 1 does not match the facility address listed in the current permit and in the application. Please provide an updated SPIF with the correct facility location/address.

#### <u>Tetra Tech/Energy Transfer Response</u>:

Supplemental Permit Information Form (SPIF): Location has been corrected to match the permit address and the SPIF form is updated and is attached as Appendix A.

2. Item 2 - USGS and Affected Landowner Map: The applicants property boundary is not delineated and labeled on the maps. If the applicants property boundary and the facility property boundary is one in the same, please label it as such on the maps.

#### <u>Tetra Tech/Energy Transfer Response</u>:

USGS and Affected Landowner Map have been reviewed and corrected and are attached as Appendix B.

3. Item 3 - Affected Landowner Mailing Labels: the mailing labels provided include the applicant. The applicant cannot be their own affected landowner. Please remove the applicant from the mailing labels and provided the document in a Microsoft Word document.

This has been corrected and a separate word document to this letter will contain the corrected mailing labels (Avery 5160) in a Microsoft Word Document.





#### Response to TCEQ Notice of Deficiency Energy Transfer GC NGL Fractionators, LLC

4. Item 4 - Technical Report 1.0, item 4: The permitted flow listed does not match what is listed in the current permit. Please provide an updated section of the technical report.

#### <u>Tetra Tech/Energy Transfer Response</u>:

Updated section of Technical Report is included as Appendix C.

5. Item 5 - The following is a portion of the NORI which contains information relevant to your application.

Please read it carefully and indicate if it contains any errors or omissions. The complete notice will be sent to you once the application is declared administratively complete.

#### Tetra Tech/Energy Transfer Response:

The NORI did not contain errors or omissions.

6. Item 6 - The application indicates that public notices in Spanish are required. After confirming the portion of the NORI above does not contain any errors or omissions, please use the attached template to translate the NORI into Spanish. Only the first and last paragraphs are unique to this application and require translation. Please provide the translated Spanish NORI in a Microsoft Word document.

#### Tetra Tech/Transfer Response:

A separate word document to this letter will contain NORI translation in Spanish in a Microsoft Word Document.

Thank you for the opportunity to update our application. Please contact Edwin C. Centeno at 832-872-1075 or <a href="mailto:e.centenojimenez@tetratech.com">e.centenojimenez@tetratech.com</a>, or Cynthia Sexton at 281-576-3616 or <a href="mailto:Cynthia.sexton@energytransfer.com">Cynthia.sexton@energytransfer.com</a>, if you have further questions.

Sincerely,

Edwin C. Centeno, PE

Edwin C. Centeno

Senior Environmental Project Manager

Tetra Tech, Inc.

Cynthia Sexton

Associate-Environmental Specialist

Energy Transfer GC NGL Fractionators, LLC

cc: Desiree Crenshaw, Energy Transfer GC NGL Fractionators, LLC





**Appendix A: Updated Supplemental Permit Information Form (SPIF)** 

# TEXAS COMMISSION ON ENVIRONMENTAL QUALITY SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

## FOR AGENCIES REVIEWING DOMESTIC OR INDUSTRIAL TPDES WASTEWATER PERMIT APPLICATIONS

TCEQ USE ONLY:	
Application type:RenewalMajor AmendmentMinor Amendment	:New
County: Segment Number:	
Admin Complete Date:	
Agency Receiving SPIF:	
Texas Historical Commission U.S. Fish and Wildlife	
Texas Parks and Wildlife Department U.S. Army Corps of Engin	ieers
This form applies to TPDES permit applications only. (Instructions, Page 53)	
Complete this form as a separate document. TCEQ will mail a copy to each agence our agreement with EPA. If any of the items are not completely addressed or furt is needed, we will contact you to provide the information before issuing the perneach item completely.	ther information
Do not refer to your response to any item in the permit application form. Provattachment for this form separately from the Administrative Report of the application will not be declared administratively complete without this SPIF form completed in its entirety including all attachments. Questions or comments conceasing the directed to the Water Quality Division's Application Review and Processing at	

Provide the name, address, phone and fax number of an individual that can be contacted to answer specific questions about the property.
Prefix (Mr., Ms., Miss): Ms.
First and Last Name: <u>Cynthia M. Sexton</u>
Credential (P.E, P.G., Ph.D., etc.):
Title: <u>Associate-Environmental Specialist</u>
Mailing Address: <u>12353 Eagle Pointe Drive</u>
City, State, Zip Code: Mont Belvieu, TX 77523
Phone No.: <u>281-576-3616</u> Ext.: Fax No.:
E-mail Address: <u>Cynthia.sexton@energytransfer.com</u>
List the county in which the facility is located: <u>Chambers</u>
If the property is publicly owned and the owner is different than the permittee/applicant, please list the owner of the property.
$\frac{N/A}{}$
Provide a description of the effluent discharge route. The discharge route must follow the flow
of effluent from the point of discharge to the nearest major watercourse (from the point of
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches,
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches,
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches,
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).  Provide original photographs of any structures 50 years or older on the property.
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).  Provide original photographs of any structures 50 years or older on the property.  Does your project involve any of the following? Check all that apply.
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).  Provide original photographs of any structures 50 years or older on the property.  Does your project involve any of the following? Check all that apply.  Proposed access roads, utility lines, construction easements
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).  Provide original photographs of any structures 50 years or older on the property.  Does your project involve any of the following? Check all that apply.  Proposed access roads, utility lines, construction easements  Visual effects that could damage or detract from a historic property's integrity
of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.  Discharge from outfall 001 fall into an unnamed ditch that flows south/southwest for about one-mile until it reaches Cedar Bayou segment 0902. Route is composed of ditches, culverts and underground piping in some areas.  Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).  Provide original photographs of any structures 50 years or older on the property.  Does your project involve any of the following? Check all that apply.  Proposed access roads, utility lines, construction easements  Visual effects that could damage or detract from a historic property's integrity  Vibration effects during construction or as a result of project design

2. 3.

4.


5.


	☐ Disturbance of vegetation or wetlands
1.	List proposed construction impact (surface acres to be impacted, depth of excavation, sealing of caves, or other karst features):
	N/A
2.	Describe existing disturbances, vegetation, and land use:
	The site is already developed.
	E FOLLOWING ITEMS APPLY ONLY TO APPLICATIONS FOR NEW TPDES PERMITS AND MAJOR IENDMENTS TO TPDES PERMITS
3.	List construction dates of all buildings and structures on the property:
	Frac VI was finished in 2019 and Frac VIII was finished in 2023.
4.	Provide a brief history of the property, and name of the architect/builder, if known.
	<u>Frac VI and Frac VIII are one of the new additions of a series of fractionators Energy</u> <u>Transfer GC NGL Fractionators have in the area. Property was sold in 2007 to Lone Star</u>
	NGL Mont Belvieu LP that in 2018 sold the property to Energy Transfer GC NGL Fractionators LLC. The builder was S & B Engineers.



Appendix B: USGS and Affected Landowner Map









### **Appendix C: Updated Section of Technical Report**

3.	. Groundwater impacts					
		Yes		No		Not yet designed

**NOTE:** Item b.3 is required if the bottom of the pond is not above the seasonal highwater table in the shallowest water-bearing zone.

Attachment: Click to enter text.

For TLAP applications: Items 3.c - 3.e are not required, continue to Item 4.

c. Attach a USGS map or a color copy of original quality and scale which accurately locates and identifies all known water supply wells and monitor wells within ½-mile of the impoundments.

Attachment: Click to enter text.

d. Attach copies of State Water Well Reports (e.g., driller's logs, completion data, etc.), and data on depths to groundwater for all known water supply wells including a description of how the depths to groundwater were obtained.

Attachment: Click to enter text.

e. Attach information pertaining to the groundwater, soils, geology, pond liner, etc. used to assess the potential for migration of wastes from the impoundments or the potential for contamination of groundwater or surface water.

Attachment: Click to enter text.

## Item 4. Outfall/Disposal Method Information (Instructions, Page 42)

Complete the following tables to describe the location and wastewater discharge or disposal operations for each outfall for discharge, and for each point of disposal for TLAP operations.

If there are more outfalls/points of disposal at the facility than the spaces provided, copies of pages 6 and/0r numbered accordingly (i.e., page 6a, 6b, etc.) may be used to provide information on the additional outfalls.

**For TLAP applications:** Indicate the disposal method and each individual irrigation area **I**, evaporation pond **E**, or subsurface drainage system **S** by providing the appropriate letter designation for the disposal method followed by a numerical designation for each disposal area in the space provided for **Outfall** number (e.g. **E1** for evaporation pond 1, **I2** for irrigation area No. 2, etc.).

#### **Outfall Longitude and Latitude**

Outfall No.	Latitude (Decimal Degrees)	Longitude (Decimal Degrees)
001	29.844887	-94.926993

#### **Outfall Location Description**

Outfall No.	Location Description
001	Southeast of Frac VI. Discharge to an existing drainage ditch.

Outfall No.	Location Description

### Description of Sampling Point(s) (if different from Outfall location)

Outfall No.	Description of sampling point
001	The sampling point is located approximately 385 ft west of Outfall 001.
	Latitude 29.844764, Longitude -94.927598

### Outfall Flow Information - Permitted and Proposed

Outfall No.	Permitted Daily Avg Flow (MGD)	Permitted Daily Max Flow (MGD)	Proposed Daily Avg Flow (MGD)	Proposed Daily Max Flow (MGD)	Anticipated Discharge Date (mm/dd/yy)
001	0.936	1.276	0.936	1.276	Currently Discharging

### Outfall Discharge - Method and Measurement

Outfall No.	Pumped Discharge? Y/N	Gravity Discharge? Y/N	Type of Flow Measurement Device Used
001	N	Y	Ultrasonic Flow Meter

### **Outfall Discharge - Flow Characteristics**

Outfall No.	Intermittent Discharge? Y/N	Continuous Discharge? Y/N	Seasonal Discharge? Y/N	Discharge Duration (hrs/day)	Discharge Duration (days/mo)	Discharge Duration (mo/yr)
001	N	Y	N	24	28-31	12

### **Outfall Wastestream Contributions**

### Outfall No. **001**

Contributing Wastestream	Volume (MGD) Avg./Max.	Percent (%) of Total Flow
Hydrostatic Test Water	0.0000936/0.00008592	0.01
Surface Air Cooler Blowdown	0.3379896/0.4608	36.11
Reverse Osmosis Reject Water	0.3590496/0.4896	38.36
Fire system testing and blowdown	0.0000936/0.00008592	0.01

Contributing Wastestream	Volume (MGD) Avg./Max.	Percent (%) of Total Flow
Emergency Showers	0.0000936/0.00008592	0.01
Fan cleaning water	0.0000936/0.00008592	0.01
Stormwater	0.237276/0.3235	25.35
Public Water System flush water	0.0000936/0.00008592	0.01
Air Dryer Condensate	0.0012168/0.0016704	0.13
Totals Avg./Max.	0.936 MGD/1.276 MGD	100%

### Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

### Outfall No. Click to enter text.

Contributing Wastestream	Volume (MGD)	Percent (%) of Total Flow

**Attachment:** Click to enter text.

## Item 5. Blowdown and Once-Through Cooling Water Discharges (Instructions, Page 43)

a.	Indicate if	the facility	v currently	or p	roposes to:

$\square$	Yes □	No	Use cooling towers that discharge blowdown or other wastestream
	100	110	obe cooling towers that discharge blowdown of other wastestream

MONT BELVIEU CAVERNS LLC PO BOX 4018 HOUSTON TX 77210-4018

LONE STAR NGL FRACTIONATORS LP 1300 MAIN ST HOUSTON TX 77002

EQUISTAR CHEMICALS LP 16410 N ELDRIDGE PKWY TOMBALL TX 77377

DOW HYDROCARBONS &
RESOURCES LLC
TAX DEPT, APB BLDG., FLOOR 4A
LAKE JACKSON TX 77566

TARGA DOWNSTREAM LLC c/o ANDREWS & COMPANY 1900 DALROCK RD ROWLETT TX 75088

OCCIDENTAL CHEMICAL CORP 0 SJOLANDER (OFF) RD PICKENS TX 74752

CHEVERON PHILLIPS CHEMICAL CP LP 9200 E FWY BAYTOWN TX 77521

LONE STAR NGL MONT BELVIEU LP 0 PINE LAKE LN BAYTOWN TX 77521

JOSEPH R. ZORN 9202 WESTVIEW CIRCLE DALLAS TX 75231-2502



### TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

P.O. Box 13087 Austin, Texas 78711-3087

### PERMIT TO DISCHARGE WASTES

under provisions of Section 402 of the Clean Water Act and Chapter 26 of the Texas Water Code

**Energy Transfer GC NGL Fractionators LLC** 

whose mailing address is

12353 Eagle Pointe Drive Mont Belvieu, Texas 77535

is authorized to treat and discharge wastes from MB Frac VI and VIII, a natural gas processing plant (SIC 1321)

located at 8774 Farm-to-Market Road 1942, near the City of Mont Belvieu, Chambers County, Texas 77521

to an unnamed tributary, thence to Cedar Bayou Above Tidal in Segment No. 0902 of the Trinity-San Jacinto Coastal Basin

only according to effluent limitations, monitoring requirements, and other conditions set forth in this permit, as well as the rules of the Texas Commission on Environmental Quality (TCEQ), the laws of the State of Texas, and other orders of the TCEQ. The issuance of this permit does not grant to the permittee the right to use private or public property for conveyance of wastewater along the discharge route described in this permit. This includes, but is not limited to, property belonging to any individual, partnership, corporation, or other entity. Neither does this permit authorize any invasion of personal rights nor any violation of federal, state, or local laws or regulations. It is the responsibility of the permittee to acquire property rights as may be necessary to use the discharge route.

This permit shall expire at midnight, five years from the date of permit issuance.

ISSUED DATE:		
	For the Commission	

TPDES PERMIT NO. WQ0005350000 [For TCEQ office use only -EPA I.D. No. TX0134068]

This major amendment replaces TPDES Permit No. WQ0005350000, issued on January 30, 2023. During the period beginning upon the date of permit issuance and lasting through the date of permit expiration, the permittee is authorized to discharge water treatment wastes ¹ surface air cooler blowdown, utility wastewater ², hydrostatic test water, and stormwater subject to the following effluent limitations:

The daily average dry-weather flow <sup>3</sup> of effluent shall not exceed 0.936 million gallons per day (MGD). The daily maximum dry-weather flow shall not exceed 1.276 MGD.

		Disc	harge Limit	Minimum Self-Monitoring Requirements			
Effluent Characteristics	Daily A	verage	Daily Maximum		Single Grab	Report Daily Average and	Daily Maximum
	lbs/day	mg/L	lbs/day	mg/L	mg/L	Measurement Frequency	Sample Type
Dry-weather Flow 3	0.936	MGD	1.276	MGD	N/A	Continuous	Flow meter
Total Organic Carbon (TOC)	N/A	N/A	N/A	75	75	Once/2 week	Grab
Oil and Grease	N/A	N/A	N/A	15	15	Once/2 week	Grab
Biochemical Oxygen Demand	106.42	20	159.63	30	30	Once/2 week	Composite
$(BOD_5)$							
Total Residual Chlorine 4	N/A	N/A	N/A	0.019	0.019	Once/2 week	Grab
Dissolved Oxygen 5	Report	mg/L	N/	/A	N/A	Once/ 2 week	Grab
Dissolved Oxygen <sup>6</sup>	2.0 mg/L,	minimum	$N_{l}$	/A	2.0	Once/ 2 week	Grab

- 2. The pH must not be less than 6.5 standard units nor greater than 9.0 standard units and must be monitored once per two week by grab sample.
- 3. There must be no discharge of floating solids or visible foam in other than trace amounts and no discharge of visible oil.
- 4. Effluent monitoring samples must be taken at the following location: Sampling point is located at Outfall 001, southeast of Frac VI and prior to discharge into the unnamed tributary.

<sup>&</sup>lt;sup>1</sup>See Other Requirement No. 6.

<sup>&</sup>lt;sup>2</sup> See Other Requirement No. 5.

<sup>&</sup>lt;sup>3</sup> See Other Requirement No. 7.

<sup>&</sup>lt;sup>4</sup> See Other Requirement No. 1.

<sup>&</sup>lt;sup>5</sup> Effective from the date of permit issuance and lasting for a period of three years. See Other Requirement No. 10.

<sup>&</sup>lt;sup>6</sup> Effective three years after permit issuance and lasting through date of permit expiration.

### **DEFINITIONS AND STANDARD PERMIT CONDITIONS**

As required by Title 30 Texas Administrative Code (TAC) Chapter 305, certain regulations appear as standard conditions in waste discharge permits. 30 TAC §§305.121 - 305.129 (relating to Permit Characteristics and Conditions) as promulgated under the Texas Water Code (TWC) §§5.103 and 5.105, and the Texas Health and Safety Code (THSC) §§361.017 and 361.024(a), establish the characteristics and standards for waste discharge permits, including sewage sludge, and those sections of 40 Code of Federal Regulations (CFR) Part 122 adopted by reference by the Commission. The following text includes these conditions and incorporates them into this permit. All definitions in Texas Water Code §26.001 and 30 TAC Chapter 305 shall apply to this permit and are incorporated by reference. Some specific definitions of words or phrases used in this permit are as follows:

### 1. Flow Measurements

- a. Annual average flow the arithmetic average of all daily flow determinations taken within the preceding 12 consecutive calendar months. The annual average flow determination shall consist of daily flow volume determinations made by a totalizing meter, charted on a chart recorder, and limited to major domestic wastewater discharge facilities with a one million gallons per day or greater permitted flow.
- b. Daily average flow the arithmetic average of all determinations of the daily flow within a period of one calendar month. The daily average flow determination shall consist of determinations made on at least four separate days. If instantaneous measurements are used to determine the daily flow, the determination shall be the arithmetic average of all instantaneous measurements taken during that month. Daily average flow determination for intermittent discharges shall consist of a minimum of three flow determinations on days of discharge.
- c. Daily maximum flow the highest total flow for any 24-hour period in a calendar month.
- d. Instantaneous flow the measured flow during the minimum time required to interpret the flow measuring device.
- e. 2-hour peak flow (domestic wastewater treatment plants) the maximum flow sustained for a two-hour period during the period of daily discharge. The average of multiple measurements of instantaneous maximum flow within a two-hour period may be used to calculate the 2-hour peak flow.
- f. Maximum 2-hour peak flow (domestic wastewater treatment plants) the highest 2-hour peak flow for any 24-hour period in a calendar month.

### 2. Concentration Measurements

- a. Daily average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar month, consisting of at least four separate representative measurements.
  - i. For domestic wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values in the previous four consecutive month period consisting of at least four measurements shall be utilized as the daily average concentration.
  - ii. For all other wastewater treatment plants When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values taken during the month shall be utilized as the daily average concentration.
- b. 7-day average concentration the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar week, Sunday through Saturday.
- c. Daily maximum concentration the maximum concentration measured on a single day, by the sample type specified in the permit, within a period of one calendar month.
- d. Daily discharge the discharge of a pollutant measured during a calendar day or any 24-hour period that reasonably represents the calendar day for purposes of sampling. For pollutants with limitations expressed in terms of mass, the "daily discharge" is calculated as the total

mass of the pollutant discharged over the sampling day. For pollutants with limitations expressed in other units of measurement, the "daily discharge" is calculated as the average measurement of the pollutant over the sampling day.

The "daily discharge" determination of concentration made using a composite sample shall be the concentration of the composite sample. When grab samples are used, the "daily discharge" determination of concentration shall be the arithmetic average (weighted by flow value) of all samples collected during that day.

- e. Bacteria concentration (Fecal coliform, *E. coli*, or Enterococci) the number of colonies of bacteria per 100 milliliters effluent. The daily average bacteria concentration is a geometric mean of the values for the effluent samples collected in a calendar month. The geometric mean shall be determined by calculating the nth root of the product of all measurements made in a calendar month, where n equals the number of measurements made; or computed as the antilogarithm of the arithmetic mean of the logarithms of all measurements made in a calendar month. For any measurement of bacteria equaling zero, a substitute value of one shall be made for input into either computation method. If specified, the 7-day average for bacteria is the geometric mean of the values for all effluent samples collected during a calendar week.
- f. Daily average loading (lbs/day) the arithmetic average of all daily discharge loading calculations during a period of one calendar month. These calculations must be made for each day of the month that a parameter is analyzed. The daily discharge, in terms of mass (lbs/day), is calculated as (Flow, MGD × Concentration, mg/L × 8.34).
- g. Daily maximum loading (lbs/day) the highest daily discharge, in terms of mass (lbs/day), within a period of one calendar month.

### 3. Sample Type

- a. Composite sample For domestic wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC §319.9(a). For industrial wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC §319.9(c).
- b. Grab sample an individual sample collected in less than 15 minutes.
- 4. Treatment Facility (facility) wastewater facilities used in the conveyance, storage, treatment, recycling, reclamation or disposal of domestic sewage, industrial wastes, agricultural wastes, recreational wastes, or other wastes including sludge handling or disposal facilities under the jurisdiction of the Commission.
- 5. The term "sewage sludge" is defined as solid, semi-solid, or liquid residue generated during the treatment of domestic sewage in 30 TAC Chapter 312. This includes the solids that have not been classified as hazardous waste separated from wastewater by unit processes.
- 6. Bypass the intentional diversion of a waste stream from any portion of a treatment facility.

### MONITORING AND REPORTING REQUIREMENTS

### 1. Self-Reporting

Monitoring results shall be provided at the intervals specified in the permit. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall conduct effluent sampling and reporting in accordance with 30 TAC §§319.4 - 319.12. Unless otherwise specified, effluent monitoring data shall be submitted each month, to the Enforcement Division (MC 224), by the 20th day of the following month for each discharge that is described by this permit whether or not a discharge is made for that month. Monitoring results must be submitted online using the NetDMR reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. Monitoring results must be signed and certified as required by Monitoring and Reporting Requirements No. 10.

As provided by state law, the permittee is subject to administrative, civil and criminal penalties, as applicable, for negligently or knowingly violating the Clean Water Act; TWC Chapters 26, 27, and 28; and THSC Chapter 361, including but not limited to knowingly making any false statement, representation, or certification on any report, record, or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance, or falsifying, tampering with or knowingly rendering inaccurate any monitoring device or method required by this permit or violating any other requirement imposed by state or federal regulations.

### 2. Test Procedures

- a. Unless otherwise specified in this permit, test procedures for the analysis of pollutants shall comply with procedures specified in 30 TAC §§319.11 319.12. Measurements, tests, and calculations shall be accurately accomplished in a representative manner.
- b. All laboratory tests submitted to demonstrate compliance with this permit must meet the requirements of 30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification.

### 3. Records of Results

- a. Monitoring samples and measurements shall be taken at times and in a manner so as to be representative of the monitored activity.
- b. Except for records of monitoring information required by this permit related to the permittee's sewage sludge use and disposal activities, which shall be retained for a period of at least five years (or longer as required by 40 CFR Part 503), monitoring and reporting records, including strip charts and records of calibration and maintenance, copies of all records required by this permit, records of all data used to complete the application for this permit, and the certification required by 40 CFR §264.73(b)(9) shall be retained at the facility site, or shall be readily available for review by a TCEQ representative for a period of three years from the date of the record or sample, measurement, report, application or certification. This period shall be extended at the request of the Executive Director.
- c. Records of monitoring activities shall include the following:

  - i. date, time, and place of sample or measurement;ii. identity of individual who collected the sample or made the measurement;
  - iii. date and time of analysis;
  - iv. identity of the individual and laboratory who performed the analysis;
  - v. the technique or method of analysis; and
  - vi. the results of the analysis or measurement and quality assurance/quality control records.

The period during which records are required to be kept shall be automatically extended to the date of the final disposition of any administrative or judicial enforcement action that may be instituted against the permittee.

### 4. Additional Monitoring by Permittee

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit using approved analytical methods as specified above, all results of such monitoring shall be included in the calculation and reporting of the values submitted on the approved self-report form. Increased frequency of sampling shall be indicated on the self-report

### 5. Calibration of Instruments

All automatic flow measuring or recording devices and all totalizing meters for measuring flows shall be accurately calibrated by a trained person at plant start-up and as often thereafter as necessary to ensure accuracy, but not less often than annually unless authorized by the Executive Director for a longer period. Such person shall verify in writing that the device is operating properly and giving accurate results. Copies of the verification shall be retained at the facility site or shall be readily available for review by a TCEQ representative for a period of three years.

### 6. Compliance Schedule Reports

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date to the regional office and the Enforcement Division (MC

### 7. Noncompliance Notification

- a. In accordance with 30 TAC §305.125(9) any noncompliance that may endanger human health or safety, or the environment shall be reported by the permittee to the TCEQ. Report of such information shall be provided orally or by facsimile transmission (FAX) to the regional office within 24 hours of becoming aware of the noncompliance. A written submission of such information shall also be provided by the permittee to the regional office and the Enforcement Division (MC 224) within five working days of becoming aware of the noncompliance. For Publicly Owned Treatment Works (POTWs), effective September 1, 2020, the permittee must submit the written report for unauthorized discharges and unanticipated bypasses that exceed any effluent limit in the permit using the online electronic reporting system available through any effluent limit in the permit using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. The written submission shall contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
- b. The following violations shall be reported under Monitoring and Reporting Requirement 7.a.:

i. unauthorized discharges as defined in Permit Condition 2(g).

- ii. any unanticipated bypass that exceeds any effluent limitation in the permit.
- iii. violation of a permitted maximum daily discharge limitation for pollutants listed specifically in the Other Requirements section of an Industrial TPDES permit.
- In addition to the above, any effluent violation that deviates from the permitted effluent limitation by more than 40% shall be reported by the permittee in writing to the regional office and the Enforcement Division (MC 224) within 5 working days of becoming aware of the noncompliance.
- d. Any noncompliance other than that specified in this section, or any required information not submitted or submitted incorrectly, shall be reported to the Enforcement Division (MC 224) as promptly as possible. For effluent limitation violations, noncompliances shall be reported on the approved self-report form.
- 8. In accordance with the procedures described in 30 TAC §§35.301 35.303 (relating to Water Quality Emergency and Temporary Orders) if the permittee knows in advance of the need for a bypass, it shall submit prior notice by applying for such authorization.
- 9. Changes in Discharges of Toxic Substances

All existing manufacturing, commercial, mining, and silvicultural permittees shall notify the regional office, orally or by facsimile transmission within 24 hours, and both the regional office and the Enforcement Division (MC 224) in writing within five (5) working days, after becoming aware of or having reason to believe:

- That any activity has occurred or will occur that would result in the discharge, on a routine or frequent basis, of any toxic pollutant listed at 40 CFR Part 122, Appendix D, Tables II and III (excluding Total Phenols) that is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":

  - i. one hundred micrograms per liter (100  $\mu g/L$ ); ii. two hundred micrograms per liter (200  $\mu g/L$ ) for acrolein and acrylonitrile; five hundred micrograms per liter (500  $\mu g/L$ ) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
  - iii. five (5) times the maximum concentration value reported for that pollutant in the permit application; or
  - iv. the level established by the TCEQ.

- b. That any activity has occurred or will occur that would result in any discharge, on a nonroutine or infrequent basis, of a toxic pollutant that is not limited in the permit, if that discharge will exceed the highest of the following "notification levels":
  - i. five hundred micrograms per liter (500  $\mu$ g/L);

- ii. one milligram per liter (1 mg/L) for antimony; iii. ten (10) times the maximum concentration value reported for that pollutant in the permit application; or
- iv. the level established by the TCEO.

### 10. Signatories to Reports

All reports and other information requested by the Executive Director shall be signed by the person and in the manner required by 30 TAC §305.128 (relating to Signatories to Reports).

- 11. All POTWs must provide adequate notice to the Executive Director of the following:
  - a. any new introduction of pollutants into the POTW from an indirect discharger that would be subject to CWA §301 or §306 if it were directly discharging those pollutants;
  - any substantial change in the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit;
  - c. for the purpose of this paragraph, adequate notice shall include information on:
    - i. the quality and quantity of effluent introduced into the POTW: and
    - any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

### PERMIT CONDITIONS

#### 1. General

- a. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in an application or in any report to the Executive Director, it shall promptly submit such facts or information.
- b. This permit is granted on the basis of the information supplied and representations made by the permittee during action on an application, and relying upon the accuracy and completeness of that information and those representations. After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked, in whole or in part, in accordance with 30 TAC Chapter 305, Subchapter D, during its term for good cause including, but not limited to, the following:

  - i. violation of any terms or conditions of this permit;ii. obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
  - iii. a change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- The permittee shall furnish to the Executive Director, upon request and within a reasonable time, any information to determine whether cause exists for amending, revoking, suspending, or terminating the permit. The permittee shall also furnish to the Executive Director, upon request, copies of records required to be kept by the permit.

### 2. Compliance

- a. Acceptance of the permit by the person to whom it is issued constitutes acknowledgment and agreement that such person will comply with all the terms and conditions embodied in the permit, and the rules and other orders of the Commission.
- b. The permittee has a duty to comply with all conditions of the permit. Failure to comply with any permit condition constitutes a violation of the permit and the Texas Water Code or the Texas Health and Safety Code, and is grounds for enforcement action, for permit amendment,

- revocation, or suspension, or for denial of a permit renewal application or an application for a permit for another facility.
- c. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit.
- d. The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal or other permit violation that has a reasonable likelihood of adversely affecting human health or the environment.
- e. Authorization from the Commission is required before beginning any change in the permitted facility or activity that may result in noncompliance with any permit requirements.
- f. A permit may be amended, suspended and reissued, or revoked for cause in accordance with 30 TAC §§305.62 and 305.66 and TWC §7.302. The filing of a request by the permittee for a permit amendment, suspension and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.
- g. There shall be no unauthorized discharge of wastewater or any other waste. For the purpose of this permit, an unauthorized discharge is considered to be any discharge of wastewater into or adjacent to water in the state at any location not permitted as an outfall or otherwise defined in the Other Requirements section of this permit.
- h. In accordance with 30 TAC §305.535(a), the permittee may allow any bypass to occur from a TPDES permitted facility that does not cause permitted effluent limitations to be exceeded or an unauthorized discharge to occur, but only if the bypass is also for essential maintenance to assure efficient operation.
- i. The permittee is subject to administrative, civil, and criminal penalties, as applicable, under Texas Water Code §§7.051 7.075 (relating to Administrative Penalties), 7.101 7.111 (relating to Civil Penalties), and 7.141 7.202 (relating to Criminal Offenses and Penalties) for violations including, but not limited to, negligently or knowingly violating the federal CWA §§301, 302, 306, 307, 308, 318, or 405, or any condition or limitation implementing any sections in a permit issued under the CWA §402, or any requirement imposed in a pretreatment program approved under the CWA §§402(a)(3) or 402(b)(8).

### 3. Inspections and Entry

- a. Inspection and entry shall be allowed as prescribed in the TWC Chapters 26, 27, and 28, and THSC Chapter 361.
- b. The members of the Commission and employees and agents of the Commission are entitled to enter any public or private property at any reasonable time for the purpose of inspecting and investigating conditions relating to the quality of water in the state or the compliance with any rule, regulation, permit, or other order of the Commission. Members, employees, or agents of the Commission and Commission contractors are entitled to enter public or private property at any reasonable time to investigate or monitor or, if the responsible party is not responsive or there is an immediate danger to public health or the environment, to remove or remediate a condition related to the quality of water in the state. Members, employees, Commission contractors, or agents acting under this authority who enter private property shall observe the establishment's rules and regulations concerning safety, internal security, and fire protection, and if the property has management in residence, shall notify management or the person then in charge of his presence and shall exhibit proper credentials. If any member, employee, Commission contractor, or agent is refused the right to enter in or on public or private property under this authority, the Executive Director may invoke the remedies authorized in TWC §7.002. The statement above, that Commission entry shall occur in accordance with an establishment's rules and regulations concerning safety, internal security, and fire protection, is not grounds for denial or restriction of entry to any part of the facility, but merely describes the Commission's duty to observe appropriate rules and regulations during an inspection.

### 4. Permit Amendment or Renewal

- a. The permittee shall give notice to the Executive Director as soon as possible of any planned physical alterations or additions to the permitted facility if such alterations or additions would require a permit amendment or result in a violation of permit requirements. Notice shall also be required under this paragraph when:
  - i. the alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in accordance with 30 TAC §305.534 (relating to New Sources and New Dischargers); or
  - ii. the alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are subject neither to effluent limitations in the permit, nor to notification requirements in Monitoring and Reporting Requirements No. 9; or
  - iii. the alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan.
- b. Prior to any facility modifications, additions, or expansions that will increase the plant capacity beyond the permitted flow, the permittee must apply for and obtain proper authorization from the Commission before commencing construction.
- c. The permittee must apply for an amendment or renewal at least 180 days prior to expiration of the existing permit in order to continue a permitted activity after the expiration date of the permit. If an application is submitted prior to the expiration date of the permit, the existing permit shall remain in effect until the application is approved, denied, or returned. If the application is returned or denied, authorization to continue such activity shall terminate upon the effective date of the action. If an application is not submitted prior to the expiration date of the permit, the permit shall expire and authorization to continue such activity shall terminate.
- d. Prior to accepting or generating wastes that are not described in the permit application or that would result in a significant change in the quantity or quality of the existing discharge, the permittee must report the proposed changes to the Commission. The permittee must apply for a permit amendment reflecting any necessary changes in permit conditions, including effluent limitations for pollutants not identified and limited by this permit.
- e. In accordance with the TWC §26.029(b), after a public hearing, notice of which shall be given to the permittee, the Commission may require the permittee, from time to time, for good cause, in accordance with applicable laws, to conform to new or additional conditions.
- f. If any toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under CWA §307(a) for a toxic pollutant that is present in the discharge and that standard or prohibition is more stringent than any limitation on the pollutant in this permit, this permit shall be modified or revoked and reissued to conform to the toxic effluent standard or prohibition. The permittee shall comply with effluent standards or prohibitions established under CWA §307(a) for toxic pollutants within the time provided in the regulations that established those standards or prohibitions, even if the permit has not yet been modified to incorporate the requirement.

### 5. Permit Transfer

- a. Prior to any transfer of this permit, Commission approval must be obtained. The Commission shall be notified in writing of any change in control or ownership of facilities authorized by this permit. Such notification should be sent to the Applications Review and Processing Team (MC 148) of the Water Quality Division.
- b. A permit may be transferred only according to the provisions of 30 TAC §305.64 (relating to Transfer of Permits) and 30 TAC §50.133 (relating to Executive Director Action on Application or WQMP update).

### 6. Relationship to Hazardous Waste Activities

This permit does not authorize any activity of hazardous waste storage, processing, or disposal that requires a permit or other authorization pursuant to the Texas Health and Safety Code.

### 7. Relationship to Water Rights

Disposal of treated effluent by any means other than discharge directly to water in the state must be specifically authorized in this permit and may require a permit pursuant to Texas Water Code Chapter 11.

### 8. Property Rights

A permit does not convey any property rights of any sort, or any exclusive privilege.

### 9. Permit Enforceability

The conditions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

### 10. Relationship to Permit Application

The application pursuant to which the permit has been issued is incorporated herein; provided, however, that in the event of a conflict between the provisions of this permit and the application, the provisions of the permit shall control.

### 11. Notice of Bankruptcy.

- a. Each permittee shall notify the Executive Director, in writing, immediately following the filing of a voluntary or involuntary petition for bankruptcy under any chapter of Title 11 (Bankruptcy) of the United States Code (11 USC) by or against:
  - i. the permittee;
  - ii. an entity (as that term is defined in 11 USC, §101(15)) controlling the permittee or listing the permit or permittee as property of the estate; or
  - iii. an affiliate (as that term is defined in 11 USC, §101(2)) of the permittee.

### b. This notification must indicate:

- i. the name of the permittee;ii. the permit number(s);
- iii. the bankruptcy court in which the petition for bankruptcy was filed; and
- iv. the date of filing of the petition.

### **OPERATIONAL REQUIREMENTS**

- The permittee shall at all times ensure that the facility and all of its systems of collection, treatment, and disposal are properly operated and maintained. This includes, but is not limited to, the regular, periodic examination of wastewater solids within the treatment plant by the operator in order to maintain an appropriate quantity and quality of solids inventory as described in the various operator training manuals and according to accepted industry standards for process control. Process control, maintenance, and operations records shall be retained at the facility site, or shall be readily available for review by a TCEQ representative, for a period of three years.
- 2. Upon request by the Executive Director, the permittee shall take appropriate samples and provide proper analysis in order to demonstrate compliance with Commission rules. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall comply with all applicable provisions of 30 TAC Chapter 312 concerning sewage sludge use and disposal and 30 TAC §§319.21 319.29 concerning the discharge of certain hazardous metals.

- 3. Domestic wastewater treatment facilities shall comply with the following provisions:
  - a. The permittee shall notify the Municipal Permits Team, Industrial Wastewater Section (MC 148) of the Water Quality Division, in writing, of any facility expansion at least 90 days prior to conducting such activity.
  - b. The permittee shall submit a closure plan for review and approval to the Municipal Permits Team, Industrial Wastewater Section (MC 148) of the Water Quality Division, for any closure activity at least 90 days prior to conducting such activity. Closure is the act of permanently taking a waste management unit or treatment facility out of service and includes the permanent removal from service of any pit, tank, pond, lagoon, surface impoundment or other treatment unit regulated by this permit.
- 4. The permittee is responsible for installing prior to plant start-up, and subsequently maintaining, adequate safeguards to prevent the discharge of untreated or inadequately treated wastes during electrical power failures by means of alternate power sources, standby generators, or retention of inadequately treated wastewater.
- 5. Unless otherwise specified, the permittee shall provide a readily accessible sampling point and, where applicable, an effluent flow measuring device or other acceptable means by which effluent flow may be determined.
- 6. The permittee shall remit an annual water quality fee to the Commission as required by 30 TAC Chapter 21. Failure to pay the fee may result in revocation of this permit under TWC §7.302(b)(6).

### 7. Documentation

For all written notifications to the Commission required of the permittee by this permit, the permittee shall keep and make available a copy of each such notification under the same conditions as self-monitoring data are required to be kept and made available. Except for information required for TPDES permit applications, effluent data, including effluent data in permits, draft permits and permit applications, and other information specified as not confidential in 30 TAC §1.5(d), any information submitted pursuant to this permit may be claimed as confidential by the submitter. Any such claim must be asserted in the manner prescribed in the application form or by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, information may be made available to the public without further notice. If the Commission or Executive Director agrees with the designation of confidentiality, the TCEQ will not provide the information for public inspection unless required by the Texas Attorney General or a court pursuant to an open records request. If the Executive Director does not agree with the designation of confidentiality, the person submitting the information will be notified.

- 8. Facilities that generate domestic wastewater shall comply with the following provisions; domestic wastewater treatment facilities at permitted industrial sites are excluded.
  - a. Whenever flow measurements for any domestic sewage treatment facility reach 75% of the permitted daily average or annual average flow for three consecutive months, the permittee must initiate engineering and financial planning for expansion or upgrading of the domestic wastewater treatment or collection facilities. Whenever the flow reaches 90% of the permitted daily average or annual average flow for three consecutive months, the permittee shall obtain necessary authorization from the Commission to commence construction of the necessary additional treatment or collection facilities. In the case of a domestic wastewater treatment facility that reaches 75% of the permitted daily average or annual average flow for three consecutive months, and the planned population to be served or the quantity of waste produced is not expected to exceed the design limitations of the treatment facility, the permittee shall submit an engineering report supporting this claim to the Executive Director of the Commission.

If in the judgment of the Executive Director the population to be served will not cause permit noncompliance, then the requirement of this section may be waived. To be effective, any waiver must be in writing and signed by the Director of the Enforcement Division (MC 219) of the Commission, and such waiver of these requirements will be reviewed upon expiration of the existing permit; however, any such waiver shall not be interpreted as condoning or excusing any violation of any permit parameter.

- b. The plans and specifications for domestic sewage collection and treatment works associated with any domestic permit must be approved by the Commission, and failure to secure approval before commencing construction of such works or making a discharge is a violation of this permit and each day is an additional violation until approval has been secured.
- c. Permits for domestic wastewater treatment plants are granted subject to the policy of the Commission to encourage the development of area-wide waste collection, treatment, and disposal systems. The Commission reserves the right to amend any domestic wastewater permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an area-wide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such area-wide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.
- 9. Domestic wastewater treatment plants shall be operated and maintained by sewage plant operators holding a valid certificate of competency at the required level as defined in 30 TAC Chapter 30.
- 10. For Publicly Owned Treatment Works (POTWs), the 30-day average (or monthly average) percent removal for BOD and TSS shall not be less than 85%, unless otherwise authorized by this permit.
- 11. Facilities that generate industrial solid waste as defined in 30 TAC §335.1 shall comply with these provisions:
  - a. Any solid waste, as defined in 30 TAC §335.1 (including but not limited to such wastes as garbage, refuse, sludge from a waste treatment, water supply treatment plant or air pollution control facility, discarded materials, discarded materials to be recycled, whether the waste is solid, liquid, or semisolid), generated by the permittee during the management and treatment of wastewater, must be managed in accordance with all applicable provisions of 30 TAC Chapter 335, relating to Industrial Solid Waste Management.
  - b. Industrial wastewater that is being collected, accumulated, stored, or processed before discharge through any final discharge outfall, specified by this permit, is considered to be industrial solid waste until the wastewater passes through the actual point source discharge and must be managed in accordance with all applicable provisions of 30 TAC Chapter 335.
  - c. The permittee shall provide written notification, pursuant to the requirements of 30 TAC §335.8(b)(1), to the Corrective Action Section (MC 127) of the Remediation Division informing the Commission of any closure activity involving an Industrial Solid Waste Management Unit, at least 90 days prior to conducting such an activity.
  - d. Construction of any industrial solid waste management unit requires the prior written notification of the proposed activity to the Registration and Reporting Section (MC 129) of the Permitting and Remediation Support Division. No person shall dispose of industrial solid waste, including sludge or other solids from wastewater treatment processes, prior to fulfilling the deed recordation requirements of 30 TAC §335.5.
  - e. The term "industrial solid waste management unit" means a landfill, surface impoundment, waste-pile, industrial furnace, incinerator, cement kiln, injection well, container, drum, salt dome waste containment cavern, or any other structure vessel, appurtenance, or other improvement on land used to manage industrial solid waste.
  - f. The permittee shall keep management records for all sludge (or other waste) removed from any wastewater treatment process. These records shall fulfill all applicable requirements of 30 TAC Chapter 335 and must include the following, as it pertains to wastewater treatment and discharge:
    - i. volume of waste and date(s) generated from treatment process;
    - ii. volume of waste disposed of on-site or shipped off-site;
    - iii. date(s) of disposal;

- iv. identity of hauler or transporter;v. location of disposal site; andvi. method of final disposal.

The above records shall be maintained on a monthly basis. The records shall be retained at the facility site, or shall be readily available for review by authorized representatives of the TCEQ for at least five years.

12. For industrial facilities to which the requirements of 30 TAC Chapter 335 do not apply, sludge and solid wastes, including tank cleaning and contaminated solids for disposal, shall be disposed of in accordance with THSC Code Chapter 361.

TCEQ Revision 05/2021

### **OTHER REQUIREMENTS**

1. Violations of daily maximum limitations for the following pollutants shall be reported orally or by facsimile to TCEQ Region 12 within 24 hours from the time the permittee becomes aware of the violation, followed by a written report within five working days to TCEQ Region 12 and Compliance Monitoring Team (MC 224):

Pollutant	MAL¹ (mg/L)
Chlorine	0.033

Test methods used must be sensitive enough to demonstrate compliance with the permit effluent limitations. If an effluent limit for a pollutant is less than the MAL, then the test method for that pollutant must be sensitive enough to demonstrate compliance at the MAL. Permit compliance/noncompliance determinations will be based on the effluent limitations contained in this permit, with consideration given to the MAL for the pollutants specified above.

When an analysis of an effluent sample for a pollutant listed above indicates no detectable levels above the MAL and the test method detection level is as sensitive as the specified MAL, a value of zero shall be used for that measurement when making calculations for the self-reporting form. This applies to determinations of daily maximum concentration, calculations of loading and daily averages, and other reportable results.

When a reported value is zero based on this MAL provision, the permittee shall submit the following statement with the self-reporting form either as a separate attachment to the form or as a statement in the comments section of the form:

"The reported value(s) of zero for \_\_\_\_[list pollutant(s)] \_\_\_ on the self-reporting form for \_\_\_\_\_indicate range] \_\_\_ is based on the following conditions: (1) the analytical method used had a method detection level as sensitive as the MAL specified in the permit, and (2) the analytical results contained no detectable levels above the specified MAL."

When an analysis of an effluent sample for a pollutant indicates no detectable levels and the test method detection level is not as sensitive as the MAL specified in the permit, or an MAL is not specified in the permit for that pollutant, the level of detection achieved shall be used for that measurement when making calculations for the self-reporting form. A zero may not be used.

- 2. The Executive Director reviewed this action for consistency with the goals and policies of the Texas Coastal Management Program (CMP) in accordance with the regulations of the General Land Office and determined that the action is consistent with the applicable CMP goals and policies.
- 3. There is no mixing zone established for this discharge to an intermittent stream. Acute toxic criteria apply at the point of discharge.
- 4. This permit does not authorize the discharge of domestic wastewater. All domestic wastewater must be disposed of in an approved manner, such as routing to an approved on-site septic tank and drainfield system or to an authorized third party for treatment and disposal.
- 5. The term "utility wastewater" means wastewaters from, but not limited to: air dryer condensate, fan cleaning water, emergency showers water, public water system flush water, and fire system testing and blowdown. Sanitary and air conditioning wastes are not included in this definition.

<sup>&</sup>lt;sup>1</sup> Minimum analytical level.

- 6. The term "water treatment wastes" includes, but is not limited to, the following: cold lime water treatment wastes, demineralizer backwash, filter backwash, ion exchanger water treatment system wastes, membrane regeneration wastes, and reverse osmosis reject water.
- 7. The permittee shall continuously record flow via a flow meter at Outfall 001. Compliance with the flow limitations established at Outfall 001 on page 2 of this permit will be based upon days in which there is dry-weather flow only. For the purpose of this permit, dry-weather flow is defined as days in which the total flow at Outfall 001 consists of any of the following sources: water treatment wastes, surface air cooler blowdown, hydrostatic test water, utility wastewater, and stormwater runoff resulting from rainfall less than 0.1 inches in a 24-hour period. The permittee shall maintain a permanent rain gage at the plant site and keep daily records of rainfall and the resulting flow at Outfall 001. Dry weather flow limits at Outfall 001 do not apply on days with significant rainfall, defined as at least 0.1 inches in 24 hours, or for 24 hours after a rainfall event that produces significant rainfall. Flow at Outfall 001 during days when the rainfall exceeds 0.1 inch during any 24-hour period must not be used in calculating the daily average or daily maximum flows to be submitted on the monthly effluent report forms.

### 8. COOLING WATER INTAKE STRUCTURE REQUIREMENTS

The permittee shall provide written notification to the TCEQ Industrial Permits Team (MC 148) and Region 12 Office of any changes in the method by which the facility obtains water for cooling purposes. This notification must be submitted 30 days prior to any such change and must include a description of the planned changes. The TCEQ may, upon review of the notification, reopen the permit to include additional terms and conditions as necessary.

- 9. The permittee must continue to follow a stormwater pollution prevention plan (SWP3) that includes a set of best management practices (BMPs) to eliminate or lessen the exposure of stormwater to industrial activities and pollutants. The SWP3 must be maintained on site and be made readily available for review by authorized TCEQ personnel. The SWP3 must contain elements, or sections, to require implementation of the following activities:
  - A. Good Housekeeping Measures Activities must be defined and implemented to ensure areas of the facility that either contribute or potentially contribute pollutants to stormwater discharges (e.g. Waste Processing and Drum Storage Unit, unloading dock areas, Waste Confirmation Unit, and truck tire wash areas) are maintained and operated in a clean and orderly manner. The frequency for conducting each of the good housekeeping measures must be defined in the SWP3.
  - B. Spill Prevention and Response Measures Areas must be identified where spills would likely contribute pollutants to stormwater discharges. Procedures must be identified and implemented to minimize or prevent contamination of stormwater from spills. Spill cleanup techniques must be identified and the necessary materials and equipment for cleanup made available to facility personnel. Facility personnel that work in the identified areas must be trained in spill prevention and response measures at a minimum frequency of once per year. A record of employee training shall be maintained on a minimum frequency of once per year, maintained on site, and be made readily available for inspection by authorized TCEQ personnel upon request.
  - C. Maintenance Program for Stormwater Control Structures A maintenance program must be developed and implemented to maintain the effectiveness of stormwater structural controls, including but not limited to the stormwater sedimentation/detention basin and the potentially contaminated stormwater basins. The SWP3 must identify specific activities, techniques, and schedules for maintenance of stormwater structural controls that ensure continued effective operation of these controls. Maintenance activities must be recorded at a minimum frequency of once per quarter, maintained on site, and be made readily available for inspection by

authorized TCEQ personnel upon request.

The SWP3 may be modified at any time in order to implement either additional or more effective pollution control measures. A summary of revisions, including the dates of the revisions, shall be maintained on a quarterly basis, maintained as a part of the SWP3 document, and made readily available for inspection by authorized TCEQ personnel upon request.

Qualified personnel, who are familiar with the industrial activities performed at the facility, must conduct monthly inspections to determine the effectiveness of the Good Housekeeping Measures, Spill Prevention and Response Measures, Maintenance Program for Structural Controls, Best Management Practices, and the Employee Training Program. The results of inspections must be documented in an inspection summary report; include an assessment for any necessary revisions or additional measures to increase effectiveness of the SWP3; and include a time-frame for implementation of any follow-up actions. The summary report must be maintained on site, and be made readily available for inspection by authorized TCEQ personnel upon request.

### 10. SCHEDULE OF COMPLIANCE FOR WATER OUALITY BASED EFFLUENT LIMITS

The permittee shall comply with the following schedule of activities for the attainment of water quality-based final effluent limitations for dissolved oxygen at Outfall 001:

- a. Determine exceedance cause(s);
- b. Develop control options;
- c. Evaluate and select control mechanisms;
- d. Implement corrective action; and
- e. Attain final effluent limitations no later than three years from the date of permit issuance.

The permittee shall submit quarterly progress reports in accordance with the following schedule. The requirement to submit quarterly progress reports expires three years from the date of permit issuance.

### PROGRESS REPORT DATE

January 1 April 1 July 1 October 1

The quarterly progress reports must include a discussion of the interim requirements that have been completed at the time of the report and must address the progress towards attaining the water quality based final effluent limitations for dissolved oxygen at Outfall 001 no later than three years from the date of permit issuance.

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this permit must be submitted no later than 14 days following each schedule date. Any reports of noncompliance shall include the cause of noncompliance, any remedial actions taken, and the probability of meeting the next scheduled requirement.

All reports must be submitted to the TCEQ Region 12 Office and to the Enforcement Division (MC-224).

### STATEMENT OF BASIS/TECHNICAL SUMMARY AND EXECUTIVE DIRECTOR'S PRELIMINARY DECISION

### DESCRIPTION OF APPLICATION

Applicant: Energy Transfer GC NGL Fractionators LLC; Texas Pollutant Discharge

Elimination System (TPDES) Permit No. WQ0005350000 (EPA I.D. No.

TX0134068)

Regulated activity: Industrial wastewater permit

Type of application: Major amendment with renewal

Request: Major amendment with renewal to remove the Whole Effluent Toxicity (WET)

testing requirements

Authority: Federal Clean Water Act (CWA) §402; Texas Water Code (TWC) §26.027;

30 Texas Administrative Code (TAC) Chapter 305, Subchapters C-F, and Chapters 307 and 319; commission policies; and Environmental Protection

Agency (EPA) guidelines

### EXECUTIVE DIRECTOR RECOMMENDATION

The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The draft permit will expire at midnight, five years from the date of permit issuance according to the requirements of 30 TAC §305.127(1)(C)(i).

### REASON FOR PROJECT PROPOSED

The applicant applied to the Texas Commission on Environmental Quality (TCEQ) for an amendment of its existing permit. The proposed amendment would authorize removal of the WET testing requirements.

### PROJECT DESCRIPTION AND LOCATION

The applicant currently operates MB Frac VI and VIII, a natural gas processing plant.

The facility utilizes water from the Coastal Water Authority (CWA) canal to supply water to various units. The water undergoes initial clarification and disinfection when brought into the facility. A reverse osmosis (RO) unit is also used to treat this water prior to utilization in the amine system associated with Frac VI. And the same RO water treatment system is used at the Frac VIII facility to treat water utilized in the Frac VIII – unit amine system. The combined flow from the Frac VI and Frac VIII RO system is approximately 340 gallons per min. (489,600 gpd) of RO concentrate discharged to Wet Surface Air Cooling (WSAC) blowdown stream. WSAC blowdown, along with RO reject water gravity flows to the on-site detention pond prior to discharge through permitted Outfall 001. Anti-foaming agents are/will be added on an as needed basis to the cooling water discharges from the existing Frac VI and Frac VIII to prevent the discharge of foam from Outfall 001. Carbon dioxide (CO<sub>2</sub>) is/will be added to the discharges from the existing Frac VI and Frac VIII for pH adjustment. ChemTreat BL124 will be added to the cooling water discharges from the existing Frac VI and Frac VIII to remove the chlorine.

At the pond inlet, one 2000L CO<sub>2</sub> storage tank will supply CO<sub>2</sub> to spargers. The spargers are installed in the manholes on the rainwater drain lines into the pond (one per frac). These units are manually controlled.

At the pond outlet, the permittee has installed a 6-ton CO<sub>2</sub> storage tank, vaporizer, vapor heater, and pH control skid that will take liquid carbon dioxide, vaporize it, mix it with water from the pond in a static mixer, and inject the solution back into the pond through a diffuser. CO<sub>2</sub> supply to the static mixer will be automatically controlled using a pH probe reading from the pond.

Two 250-gallon tanks of 10-30 % sodium bisulfate solution with injection pumps are installed to treat the RO/WSAC blowdowns directly for the pond.

The stormwater drains to the pond where it intermingles with the WSAC wastewater and other permitted wastestreams then drains to Outfall 001. Facility only hydrostatically tests new pipelines and the water used will be filtered. The hydrostatic test discharge water will be directed to the Outfall 001 for discharge.

The facility is located at 8774 Farm-to-Market Road 1942, near the City of Mont Belvieu, Chambers County, Texas 77521.

### **Discharge Route and Designated Uses**

The effluent is discharged to an unnamed tributary, thence to Cedar Bayou Above Tidal in Segment No. 0902 of the Trinity-San Jacinto Coastal Basin. The unclassified receiving water uses are minimal aquatic life use for the unnamed tributary. The designated uses for Segment No. 0902 are primary contact recreation and high aquatic life use. The effluent limits in the draft permit will maintain and protect the existing instream uses. All determinations are preliminary and subject to additional review and revisions.

### **Antidegradation Review**

In accordance with 30 TAC §307.5 and TCEQ's *Procedures to Implement the Texas Surface Water Quality Standards* (June 2010), an antidegradation review of the receiving waters was performed. A Tier 1 antidegradation review has preliminarily determined that existing water quality uses will not be impaired by this permit action. Numerical and narrative criteria to protect existing uses will be maintained. A Tier 2 review has preliminarily determined that no significant degradation of water quality is expected in Cedar Bayou Above Tidal, which has been identified as having high aquatic life use. Existing uses will be maintained and protected. The preliminary determination can be reexamined and may be modified if new information is received.

### **Endangered Species Review**

The discharge from this permit is not expected to have an effect on any federal endangered or threatened aquatic or aquatic-dependent species or proposed species or their critical habitat. This determination is based on the United States Fish and Wildlife Service's (USFWS) biological opinion on the State of Texas authorization of the TPDES (September 14, 1998; October 21, 1998 update). To make this determination for TPDES permits, TCEQ and the EPA only considered aquatic or aquatic-dependent species occurring in watersheds of critical concern or high priority as listed in Appendix A of the USFWS's biological opinion. The determination is subject to reevaluation due to subsequent updates or amendments to the biological opinion. The permit does not require EPA review with respect to the presence of endangered or threatened species.

### **Impaired Water Bodies**

Segment No. 0902 is currently listed on the state's inventory of impaired and threatened waters, the 2022 CWA §303(d) list. The listings are specifically for bacteria in water (recreation use) and depressed dissolved oxygen in water. Both impairments apply from a point 2.2 km (1.4 miles) upstream of IH 10 in Chambers/Harris County to a point 7.4 km (4.6 miles) upstream of FM 1960 in Liberty County (AU 0902\_01). No additional loadings of oxygen-demanding constituents to the segment that could further cause or contribute to the impairment are being requested as part of this

amendment application. Therefore, this permit action does not represent an increase in oxygendemanding constituents to Segment No. 0902 and is not expected to further contribute to the dissolved oxygen impairment. Based upon the type of wastewater discharged from this facility, domestic wastewater is not authorized for discharge by this permit and the facility has no other known sources of bacteria.

### **Completed Total Maximum Daily Loads (TMDLs)**

There are no completed TMDLs for Segment No. 0902.

### **Dissolved Oxygen**

A dissolved oxygen (DO) analysis of the referenced discharge was conducted using a default QUAL-TX model in combination with the calibrated QUAL-TX model originally developed for the *Waste Load Evaluation for Dissolved Oxygen in Cedar Bayou in the Trinity-San Jacinto Coastal Basin: Segment 0901 and Segment 0902* (1998) for an effluent flow of 0.936 MGD.

Based on model results, the existing effluent limit of 106.42 lbs/day  $BOD_5$  is predicted to be adequate to maintain DO levels above the criteria stipulated by the Standards Implementation Team for the unnamed ditch (2.0 mg/L). In addition, an effluent DO limit of 2.0 mg/L is predicted to be necessary to ensure that dissolved oxygen levels will be maintained above the criteria established for the receiving waters.

The current permit contains a daily average  $BOD_5$  concentration limit of 20 mg/L, which is not equivalent to the loading limit of 106.42 lbs/day  $BOD_5$  at the full-permitted flow of 0.936 MGD (the loading limit would be equivalent to a concentration of 13.6 mg/L). The modeling analysis was performed using the full-permitted flow and the lower  $BOD_5$  concentration equivalent to the loading limit. The flow limit in the existing permit specifically applies only during dry-weather conditions as defined in the permit's Other Requirements section, and thus the  $BOD_5$  loading limit also applies only during those conditions. The inclusion of the separate 20 mg/L  $BOD_5$  concentration limit, which applies under all conditions, adds both flexibility and an additional safety factor to the permit. There is no modeling objection to the continued inclusion of the 20 mg/L  $BOD_5$  limit in the permit.

Coefficients and kinetics used in the model are a combination of site specific, standardized default, and estimated values. The results of this evaluation can be reexamined upon receipt of information that conflicts with the assumptions employed in this analysis.

### **SUMMARY OF EFFLUENT DATA**

The following is a quantitative description of the discharge described in the monthly effluent report data for the period January 2023 through July 2025. The "Avg of Daily Avg" values presented in the following table are the average of all daily average values for the reporting period for each pollutant. The "Max of Daily Max" values presented in the following table are the individual maximum values for the reporting period for each pollutant. Flows are expressed in million gallons per day (MGD). All pH values are expressed in standard units (SU).

#### Flow

Outfall	Frequency	Avg of Daily Avg, MGD	Max of Daily Max, MGD
001	Continuous	0.467	2.16

### **Effluent Characteristics**

Outfall	Pollutant	Avg of Da	aily Avg	Max of Daily Max		
Outlan	Pollutalit	lbs/day	mg/L	lbs/day	mg/L	
001	Biochemical Oxygen Demand, 5-day (BOD <sub>5</sub> )	13.0	3.70	146	26.0	
	Total Residual Chlorine (TRC)	-	ı	-	0.200	
	Oil and Grease	-	ı	-	14.8	
	Total Organic Carbon (TOC)	-	-	-	51.7	
	рН	6.63 SU, minimum		9.4	SU	

Effluent limit violations documented in the monthly effluent reports are summarized in the following table.

### **Effluent Limitation Violations**

Outfall	Pollutant (units)	Donort Data	Daily A	Average	Daily Maximum		
Outlan Fondant (units)		Report Date	Limit	Reported	Limit	Reported	
001	Flow (dry weather)	5/2024	-	-	1.276	2.16	
		11/2024	-	-		1.35	
		12/2024	-	-		1.65	
		1/2025	-	-		1.79	
	TRC	4/2023	-	-	0.019	0.09	

The draft permit was not changed to address these effluent limit violations because of their infrequent nature.

### REASONABLE POTENTIAL (RP) DETERMINATION

In the past three years, the permittee has performed twenty-two chronic tests, with zero demonstrations of significant toxicity (i.e., zero failures).

A reasonable potential determination was performed in accordance with 40 CFR §122.44(d)(1)(ii) to determine whether the discharge will reasonably be expected to cause or contribute to an exceedance of a state water quality standard or criterion within that standard. The RP determination is based on representative data from the previous three years of chronic WET testing. This determination was performed in accordance with the methodology outlined in the TCEQ letter to the EPA dated December 28, 2015, and approved by the EPA in a letter dated December 28, 2015.

With zero failures, a determination of no RP was made, and the WET testing requirements may be removed.

### **DRAFT PERMIT CONDITIONS**

The draft permit authorizes the discharge of water treatment wastes, surface air cooler blowdown, utility wastewater, hydrostatic test water, and stormwater at a daily average dry-weather flow not to exceed 0.936 MGD via Outfall 001.

Effluent limitations are established in the draft permit as follows:

Outfall	Parameter	Daily A	Average	Daily M	aximum		
		lbs/day	mg/L	lbs/day	mg/L		
001	Dry-weather Flow <sup>1</sup>	0.936	0.936 MGD		MGD		
	BOD5	106.42	20	159.63	30		
	TOC	N	N/A		5		
	Oil and Grease	N	N/A		5		
	TRC	N	/A	Α ο.σ			
	DO	2.0, m	2.0, minimum		2.0, minimum		/A
	pH, Standard Units (SU)	6.5 SI	6.5 SU, min 9.0 SU		SU		

### **OUTFALL LOCATIONS**

Outfall	Latitude	Longitude
001	39.844887 N	94.926993 W

### **Technology-Based Effluent Limitations**

Regulations in Title 40 of the Code of Federal Regulations (40 CFR) require that technology-based limitations be placed in wastewater discharge permits based on effluent limitations guidelines, where applicable, or on best professional judgment (BPJ) in the absence of guidelines. The draft permit authorizes the discharge of water treatment wastes, surface air cooler blowdown, utility wastewater, hydrostatic test water, and stormwater at a daily average flow not to exceed 936,000 gallons per day via Outfall 001. This is a natural gas processing facility and therefore, not subject to technology-based effluent guidelines. Daily maximum effluent limits of TOC and oil and grease limits are based on EPA guidance for discharges of stormwater associated with industrial activities. Flow reporting is required by 40 CFR § 122.44(i)(1)(ii).

The existing TPDES permit established 20 mg/L monthly average and 30 mg/L daily maximum limits for BOD5 at Outfall 001. Since discharges from Outfall 001 are continuous, loading limits for BOD5 were established in the existing permit. This is consistent with both EPA and TCEQ permits for similar facilities and is also consistent with 40 CFR 122.45(f). The proposed limitation for BOD5 at Outfall 001 is 30 mg/l daily maximum and 20 mg/l daily average. The effluent loadings, lbs/day, were calculated using the facility's average flow of 0.936 MGD reported in the permit application package, the existing limits for BOD5 are more protective and continued in the draft permit. Development of technology-based effluent limitations is presented in Appendix A.

### **Water Quality-Based Effluent Limitations**

Calculations of water quality-based effluent limitations for the protection of aquatic life and human health are presented in Appendix B. Aquatic life criteria established in Table 1 and human health criteria established in Table 2 of 30 TAC Chapter 307 are incorporated into the calculations, as are recommendations in the Water Quality Assessment Team's memorandum dated September 4, 2025. TCEQ practice for determining significant potential is to compare the reported analytical data from the facility against percentages of the calculated daily average water quality-based effluent limitation. Permit limitations are required when analytical data reported in the application exceeds 85 percent of the calculated daily average water quality-based effluent limitation. Monitoring and reporting is required when analytical data reported in the application exceeds 70 percent of the calculated daily

\_

<sup>&</sup>lt;sup>1</sup> See Other Requirement No. 7 in the draft permit.

average water quality-based effluent limitation.

Data reported in the application was screened against the calculated water quality-based effluent limitations and no limits are required.

A water quality-based effluent limit for chlorine established in a former NPDES permit was established in the existing TPDES permit and that limit is continued in the draft permit.

### Total Dissolved Solids (TDS), Chloride, and Sulfate Screening

The average concentration of TDS, chloride, and sulfate in the effluent is greater than the segment criterion. Screening procedures and effluent limitations for TDS, chloride, and sulfate are calculated using the methodology in the *Procedures to Implement the Texas Surface Water Quality Standards*, June 2010, and criteria in the *Texas Surface Water Quality Standards* (30 TAC Chapter 307). Detailed calculations are presented in Appendix C. Based on the screening, no effluent limitations are needed for TDS, chloride, and sulfate.

### pH Screening

The existing permit includes pH limits of 6.5 – 9.0 SU at Outfall 001, which discharges into an unclassified water body. Consistent with the procedures for pH screening that were submitted to EPA with a letter dated May 28, 2014, and approved by EPA in a letter dated June 2, 2014, requiring a discharge to an unclassified water body to meet pH limits of 6.0 – 9.0 standard units reasonably ensures instream compliance with *Texas Surface Water Quality Standards* pH criteria. These limits have been carried forward in the draft permit. Wastewater discharges from Outfall 001 flows into an unnamed tributary, thence to Cedar Bayou Above Tidal in Segment No. 0902 in the Trinity-San Jacinto Coastal Basin, which has the Texas Surface Water Quality Standard criteria of 6.5-9.0 SU.

### 316(b) Cooling Water Intake Structures

The facility obtains water from Coastal Water Authority, a public water system (PWS No. TX 1010013), for cooling purposes. The use of water obtained from a public water system for cooling purposes does not constitute the use of a cooling water intake structure; therefore, the facility is not subject to Section 316(b) of the CWA or 40 CFR Part 125, Subpart J.

The Other Requirement No. 8 has been carried forward to the draft permit and requires the permittee to notify the TCEQ of any changes in the method by which cooling water is obtained. Upon receipt of such notification, the TCEQ may reopen the permit to include additional terms and conditions as necessary.

### Whole Effluent Toxicity Testing (Biomonitoring)

Biomonitoring requirements are not included in the draft permit. While the existing permit did have biomonitoring requirements, discharges authorized by this permit do not meet the threshold established in the *Procedures to Implement the Texas Surface Water Quality Standards* (RG-194) to impose biomonitoring requirements so the requirements are removed. With zero failures, a determination of no RP was made, and the WET testing requirements was removed. This facility is classified as an EPA minor facility. As all discharges are not treated process wastewater, the major amendment request was supported as discharges authorized in this permit do not meet the threshold established in the *Procedures to Implement the Texas Surface Water Quality Standards* (RG-194) to impose biomonitoring requirements and the anti-degradation review also determined no significant degradation of water quality is expected in Cedar Bayou Above Tidal. This change meets anti-backsliding 40 CFR § 122.44(l).

### SUMMARY OF CHANGES FROM APPLICATION

Upon recommendation of the modeler review, a new limit for DO of 2.0 mg/L minimum was added to the draft permit.

### SUMMARY OF CHANGES FROM EXISTING PERMIT

The permittee requested the following changes in their amendment request that the Executive Director has recommended granting:

To remove the Whole Effluent Toxicity (WET) testing requirements.

The following additional changes have been made to the draft permit.

- 1. The existing permit Other Requirements Nos. 1-9 are carried forward in the draft permit.
- 2. Other Requirement No. 8 was updated to the draft permit to current standards (title added).
- 3. Other Requirement No. 10 was added for the compliance period created by the addition of a DO limitation.

### **BASIS FOR DRAFT PERMIT**

The following items were considered in developing the draft permit:

- 1. Application received on July 31, 2025, and additional information received on August 6, 2025.
- 2. Existing permits: TPDES Permit No. WQ0005350000 issued on January 30, 2023.
- 3. TCEQ Rules.
- 4. *Texas Surface Water Quality Standards* 30 TAC §§307.1-307.10, effective March 1, 2018, as approved by EPA Region 6.
- 5. *Texas Surface Water Quality Standards* 30 TAC §§307.1-307.10, effective March 6, 2014, as approved by EPA Region 6, for portions of the 2018 standards not approved by EPA Region 6.
- 6. *Texas Surface Water Quality Standards* 30 TAC §§307.1-307.10, effective July 22, 2010, as approved by EPA Region 6, for portions of the 2014 standards not approved by EPA Region 6.
- 7. *Texas Surface Water Quality Standards* 30 TAC §§307.1-307.10, effective August 17, 2000, and Appendix E, effective February 27, 2002, for portions of the 2010 standards not approved by EPA Region 6.
- 8. Procedures to Implement the Texas Surface Water Quality Standards (IPs), Texas Commission on Environmental Quality, June 2010, as approved by EPA Region 6.
- 9. Procedures to Implement the Texas Surface Water Quality Standards, Texas Commission on Environmental Quality, January 2003, for portions of the 2010 IPs not approved by EPA Region 6.
- 10. Memos from the Standards Implementation Team and Water Quality Assessment Team of the Water Quality Assessment Section of the TCEQ.
- 11. Guidance Document for Establishing Monitoring Frequencies for Domestic and Industrial Wastewater Discharge Permits, TCEQ Document No. 98-001.000-OWR-WQ, May 1998.
- 12. EPA Effluent Guidelines: N/A.
- 13. Consistency with the Coastal Management Plan: The executive director has reviewed this action for consistency with the goals and policies of the Texas Coastal Management Program (CMP) in accordance with the regulations of the General Land Office and has determined that the action is consistent with the applicable CMP goals and policies.

- 14. Letter dated May 28, 2014, from L'Oreal W. Stepney, P.E., Deputy Director, Office of Water, TCEQ, to Bill Honker, Director, Water Quality Protection Division, EPA (TCEQ proposed development strategy for pH evaluation procedures).
- 15. Letter dated June 2, 2014, from William K. Honker, P.E., Director, Water Quality Protection Division, EPA, to L'Oreal W. Stepney, P.E., Deputy Director, Office of Water, TCEQ (Approval of TCEQ proposed development strategy for pH evaluation procedures).
- 16. Letter dated December 28, 2015, from L'Oreal Stepney, P.E., Deputy Director, Office of Water, TCEQ, to Bill Honker, Director, Water Quality Protection Division, EPA (TCEQ proposed development strategy for procedures to determine reasonable potential for whole effluent toxicity limitations).
- 17. Letter dated December 28, 2015, from William K. Honker, P.E., Director, Water Quality Protection Division, EPA, to L'Oreal W. Stepney, P.E., Deputy Director, Office of Water, TCEQ (Approval of TCEQ proposed development strategy for procedures to determine reasonable potential for whole effluent toxicity limitations).
- 18. General Guidance Industrial Permits: Uncontaminated Stormwater Runoff, EPA, January 1997.

### PROCEDURES FOR FINAL DECISION

When an application is declared administratively complete, the chief clerk sends a letter to the applicant advising the applicant to publish the Notice of Receipt of Application and Intent to Obtain Permit in the newspaper. In addition, the Chief Clerk instructs the applicant to place a copy of the application in a public place for reviewing and copying in the county where the facility is or will be located. This application will be in a public place throughout the comment period. The Chief Clerk also mails this notice to any interested persons and, if required, to landowners identified in the permit application. This notice informs the public about the application and provides that an interested person may file comments on the application or request a contested case hearing or a public meeting.

Once a draft permit is completed, it is sent to the Chief Clerk, along with the Executive Director's preliminary decision contained in the technical summary or fact sheet. At that time, the Notice of Application and Preliminary Decision will be mailed to the same people and published in the same newspaper as the prior notice. This notice sets a deadline for making public comments. The applicant must place a copy of the Executive Director's preliminary decision and draft permit in the public place with the application.

Any interested person may request a public meeting on the application until the deadline for filing public comments. A public meeting is intended for the taking of public comment and is not a contested case hearing.

After the public comment deadline, the Executive Director prepares a response to all significant public comments on the application or the draft permit raised during the public comment period. The Chief Clerk then mails the Executive Director's response to comments and final decision to people who have filed comments, requested a contested case hearing, or requested to be on the mailing list. This notice provides that if a person is not satisfied with the Executive Director's response and decision, they can request a contested case hearing or file a request to reconsider the Executive Director's decision within 30 days after the notice is mailed.

The Executive Director will issue the permit unless a written hearing request or request for reconsideration is filed within 30 days after the Executive Director's response to comments and final decision is mailed. If a hearing request or request for reconsideration is filed, the Executive Director will not issue the permit and will forward the application and request to the TCEQ commissioners for their consideration at a scheduled commission meeting. If a contested case hearing is held, it will be a legal proceeding similar to a civil trial in state district court.

If the Executive Director calls a public meeting or the commission grants a contested case hearing as described above, the commission will give notice of the date, time, and place of the meeting or hearing. If a hearing request or request for reconsideration is made, the commission will consider all public comments in making its decision and shall either adopt the Executive Director's response to public comments or prepare its own response.

For additional information about this application, contact Thomas E. Starr at (512) 239-4570.

Thomas E. Starr	October 10, 2025
Thomas E. Starr	Date

### Appendix A Calculated Technology-Based Effluent Limits

Regulations in Title 40 of the Code of Federal Regulations (40 CFR) require that technology-based limitations be placed in wastewater discharge permits based on effluent limitations guidelines, where applicable, or on best professional judgment (BPJ) in the absence of guidelines. The draft permit authorizes the discharge of water treatment wastes, surface air cooler blowdown, utility wastewater, hydrostatic test water, and stormwater at a daily average flow not to exceed 936,000 gallons per day via Outfall 001. This is a natural gas processing facility and therefore, not subject to technology-based effluent guidelines. Daily maximum effluent limits of total organic carbon and oil and grease limits are based on EPA guidance for discharges of stormwater associated with industrial activities. Flow reporting is required by 40 CFR § 122.44(i)(1)(ii).

The existing permit established 20 mg/L monthly average and 30 mg/L daily maximum limits for BOD5 at Outfall 001. Since discharges from Outfall 001 are continuous, loading limits for BOD5 are established in the permit. This is consistent with both EPA and TCEQ permits for similar facilities and is also consistent with 40 CFR 122.45(f). The proposed limitation for BOD5 at Outfall 001 is 30 mg/l daily maximum and 20 mg/l daily average. The effluent loadings, lbs/day, were calculated using the facility's average flow of 0.936 MGD reported in the permit application package, the existing limits for BOD5 are more protective and continued in the draft permit.

### **Loading calculations:**

Loading, lbs/day = Flow (MGD) \* 8.34 lb/gal \* 20 mg/l

Daily average (lbs./day) BOD = 0.936 MGD \* 8.34 lb/day \* 20 mg/L = 156.125 lbs/day

The daily maximum value was calculated by multiplying the daily average by 1.5 = 156.125 \*1.5 = 234.187 lbs/day.

### Appendix B Calculated Water Quality-Based Effluent Limits

#### TEXTOX MENU #2 - INTERMITTENT STREAM WITHIN 3 MILES OF A FRESHWATER PERENNIAL

The water quality-based effluent limitations developed below are calculated using:

Table 1, 2014 Texas Surface Water Quality Standards (30 TAC 307) for Freshwater Aquatic Life Table 2, 2018 Texas Surface Water Quality Standards for Human Health "Procedures to Implement the Texas Surface Water Quality Standards," TCEQ, June 2010

#### PERMIT INFORMATION

Permittee Name: Energy Transfer GC NGL Fractionators LLC

TPDES Permit No.: WQ0005350000

Outfall No.: 001

Prepared by: Thomas Starr

Date: October 10, 2025

#### **DISCHARGE INFORMATION**

Intermittent Receiving Waterbody: unnamed drainage ditch Perennial Stream/River within 3 Miles: Cedar Bayou Above Tidal 0902 Segment No.: TSS (mg/L): 4 pH (Standard Units): 7.1 Hardness (mg/L as CaCO<sub>3</sub>): 90 88 Chloride (mg/L): 1.276 Effluent Flow for Aquatic Life (MGD): Critical Low Flow [7Q2] (cfs) for intermittent: 0 Critical Low Flow [7Q2] (cfs) for perennial: 2.85 % Effluent for Chronic Aquatic Life (Mixing Zone): 40.92 % Effluent for Acute Aquatic Life (ZID): 100 Effluent Flow for Human Health (MGD): 1.276 Harmonic Mean Flow (cfs) for perennial: 3.75 % Effluent for Human Health: 34.489 Human Health Criterion (select: PWS, FISH, or INC) FISH

#### CALCULATE DISSOLVED FRACTION (AND ENTER WATER EFFECT RATIO IF APPLICABLE):

Stream/River Metal	Intercept (b)	Slope (m)	Partition Coefficient (Kp)	Dissolved Fraction (Cd/Ct)	Source	Effect Ratio (WER)	Source
Aluminum	N/A	N/A	N/A	1.00	Assumed	1.00	Assumed
Arsenic	5.68	-0.73	173978.75	0.590		1.00	Assumed
Cadmium	6.60	-1.13	831136.22	0.231		1.00	Assumed
Chromium (total)	6.52	-0.93	912187.69	0.215		1.00	Assumed
Chromium (trivalent)	6.52	-0.93	912187.69	0.215		1.00	Assumed
Chromium (hexavalent)	N/A	N/A	N/A	1.00	Assumed	1.00	Assumed
Copper	6.02	-0.74	375383.87	0.400		1.00	Assumed
Lead	6.45	-0.80	929719.64	0.212		1.00	Assumed
Mercury	N/A	N/A	N/A	1.00	Assumed	1.00	Assumed
Nickel	5.69	-0.57	222241.83	0.529		1.00	Assumed
Selenium	N/A	N/A	N/A	1.00	Assumed	1.00	Assumed
Silver	6.38	-1.03	575278.59	0.303		1.00	Assumed
Zinc	6.10	-0.70	477043.53	0.344		1.00	Assumed

### AQUATIC LIFE CALCULATE DAILY AVERAGE AND DAILY MAXIMUM EFFLUENT LIMITATIONS:

	FW Acute	FW						Daily
	Criterion	Chronic	WLAa	WLAc	LTAa	LTAc	Daily Avg.	Max.
Parameter	(μg/L)	Criterion	(μg/L)	(μg/L)	(μg/L)	(μg/L)	(μg/L)	(μg/L)
Aldrin	3.0	N/A	3.00	N/A	1.72	N/A	2.52	5.34
Aluminum	991	N/A	991	N/A	568	N/A	834	1765
Arsenic	340	150	577	622	330	479	485	1027
Cadmium	7.7	0.229	33.5	2.42	19.2	1.86	2.73	5.78
Carbaryl	2.0	N/A	2.00	N/A	1.15	N/A	1.68	3.56
Chlordane	2.4	0.004	2.40	0.00977	1.38	0.00753	0.0110	0.0234
Chlorpyrifos	0.083	0.041	0.0830	0.100	0.0476	0.0771	0.0699	0.147
Chromium (trivalent)	523	68	2430	772	1392	595	874	1849
Chromium (hexavalent)	15.7	10.6	15.7	25.9	9.00	19.9	13.2	27.9
Copper	12.9	8.7	32.2	52.9	18.4	40.7	27.0	57.3
Cyanide (free)	45.8	10.7	45.8	26.1	26.2	20.1	29.5	62.6
4,4'-DDT	1.1	0.001	1.10	0.00244	0.630	0.00188	0.00276	0.00585
Demeton	N/A	0.1	N/A	0.244	N/A	0.188	0.276	0.585
Diazinon	0.17	0.17	0.170	0.415	0.0974	0.320	0.143	0.302
Dicofol [Kelthane]	59.3	19.8	59.3	48.4	34.0	37.3	49.9	105
Dieldrin	0.24	0.002	0.240	0.00489	0.138	0.00376	0.00553	0.0117
Diuron	210	70	210	171	120	132	176	374
Endosulfan I (alpha )	0.22	0.056	0.220	0.137	0.126	0.105	0.154	0.327
Endosulfan II (beta )	0.22	0.056	0.220	0.137	0.126	0.105	0.154	0.327
Endosulfan sulfate	0.22	0.056	0.220	0.137	0.126	0.105	0.154	0.327
Endrin	0.086	0.002	0.0860	0.00489	0.0493	0.00376	0.00553	0.0117
Guthion [Azinphos Methyl]	N/A	0.01	N/A	0.0244	N/A	0.0188	0.0276	0.0585
Heptachlor	0.52	0.004	0.520	0.00977	0.298	0.00753	0.0110	0.0234
Hexachlorocyclohexane (gamma) [Lindane]	1.126	0.08	1.13	0.195	0.645	0.151	0.221	0.468
Lead	58	2.24	272	25.9	156	19.9	29.2	61.9
Malathion	N/A	0.01	N/A	0.0244	N/A	0.0188	0.0276	0.0585
Mercury	2.4	1.3	2.40	3.18	1.38	2.45	2.02	4.27
Methoxychlor	N/A	0.03	N/A	0.0733	N/A	0.0564	0.0829	0.175
Mirex	N/A	0.001	N/A	0.00244	N/A	0.00188	0.00276	0.00585
Nickel	428	47.6	809	220	464	169	248	525
Nonylphenol	28	6.6	28.0	16.1	16.0	12.4	18.2	38.6
Parathion (ethyl)	0.065	0.013	0.0650	0.0318	0.0372	0.0245	0.0359	0.0760
Pentachlorophenol	9.6	7.4	9.65	18.1	5.53	13.9	8.12	17.1
Phenanthrene	30	30	30.0	73.3	17.2	56.4	25.2	53.4
Polychlorinated Biphenyls [PCBs]	2.0	0.014	2.00	0.0342	1.15	0.0263	0.0387	0.0819
Selenium	20	5	20.0	12.2	11.5	9.41	13.8	29.2
Silver	0.8	N/A	19.5	N/A	11.1	N/A	16.3	34.6
Toxaphene	0.78	0.0002	0.780	0.000489	0.447	0.000376	0.000553	0.00117
Tributyltin [TBT]	0.13	0.024	0.130	0.0586	0.0745	0.0452	0.0663	0.140
2,4,5 Trichlorophenol	136	64	136	156	77.9	120	114	242
Zinc	107	108	312	768	179	591	262	555

### HUMAN HEALTH

CALCULATE DAILY AVERAGE AND DAILY MAXIMUM	Water and	Fish Only	Incidental				
	Fish	Criterion	Fish	WLAh	LTAh	Daily Avg.	Daily Max.
Parameter	Criterion	(μg/L)	Criterion	(μg/L)	(μg/L)	(μg/L)	(μg/L)
Acrylonitrile	1.0	115	1150	333	310	455	964
Aldrin	1.146E-05	1.147E-05	1.147E-04	0.0000333	0.0000309	0.0000454	0.0000961
Anthracene	1109	1317	13170	3819	3551	5220	11044
Antimony	6	1071	10710	3105	2888	4245	8981
Arsenic	10	N/A	N/A	N/A	N/A	N/A	N/A
Barium	2000	N/A	N/A	N/A	N/A	N/A	N/A
Benzene	5	581	5810	1685	1567	2302	4872
Benzidine	0.0015	0.107	1.07	0.310	0.289	0.424	0.897
Benzo(a )anthracene	0.024	0.025	0.25	0.0725	0.0674	0.0990	0.209
Benzo(a )pyrene	0.0025	0.0025	0.025	0.00725	0.00674	0.00990	0.0209
Bis(chloromethyl)ether	0.0024	0.2745	2.745	0.796	0.740	1.08	2.30
Bis(2-chloroethyl)ether	0.60	42.83	428.3	124	115	169	359
Bis (2-ethylhexyl) phthalate [Di(2-ethylhexyl) phtha	6	7.55	75.5	21.9	20.4	29.9	63.3
Bromodichloromethane [Dichlorobromomethane]	10.2	275	2750	797	742	1090	2306
Bromoform [Tribromomethane]	66.9	1060	10600	3073	2858	4201	8889
Cadmium	5	N/A	N/A	N/A		N/A	N/A
Carbon Tetrachloride	4.5	46	460	133	124	182	385
Chlordane	0.0025	0.0025	0.025	0.00725	0.00674	0.00990	0.0209
Chlorobenzene	100	2737	27370	7936		10849	22952
Chlorodibromomethane [Dibromochloromethane]	7.5	183	1830	531		725	1534
Chloroform [Trichloromethane]	70	7697	76970	22317	20755	30509	64547
Chromium (hexavalent)	62	502	5020	1456		1989	4209
Chrysene	2.45	2.52	25.2	7.31	6.80	9.98	21.1
Cresols [Methylphenols]	1041	9301	93010	26968	25080	36867	77998
Cyanide (free)	200	N/A	N/A	N/A		N/A	N/A
4,4'-DDD	0.002	0.002	0.02	0.00580	0.00539	0.00792	0.0167
4,4'-DDE	0.00013	0.00013	0.0013	0.000377		0.000515	0.00109
4,4'-DDT	0.0004	0.0004	0.004	0.00116	0.00108	0.00158	0.00335
2,4'-D	70	N/A	N/A	N/A			N/A
Danitol [Fenpropathrin]	262	473	4730	1371	1275	1874	3966
1,2-Dibromoethane [Ethylene Dibromide]	0.17	4.24	42.4	12.3	11.4	16.8	35.5
m -Dichlorobenzene [1,3-Dichlorobenzene]	322	595	5950	1725		2358	4989
o -Dichlorobenzene [1,2-Dichlorobenzene]	600	3299	32990	9565		13076	27665
p -Dichlorobenzene [1,4-Dichlorobenzene]	75	N/A	N/A	N/A			N/A
3,3'-Dichlorobenzidine	0.79	2.24	22.4	6.49	6.04	8.87	18.7
1,2-Dichloroethane	5	364	3640	1055	982	1442	3052
1,1-Dichloroethylene [1,1-Dichloroethene]	7	55114	551140	159800		218463	462190
Dichloromethane [Methylene Chloride]	5	13333	133330	38658		52849	111811
1,2-Dichloropropane	5	259	2590	751		1026	2171
1,3-Dichloropropene [1,3-Dichloropropylene]	2.8	119	1190	345		471	997
Dicofol [Kelthane]	0.30	0.30	3	0.870		1.18	2.51
Dieldrin	2.0E-05	2.0E-05	2.0E-04			0.0000792	0.000167
2,4-Dimethylphenol	444	8436	84360	24460	22748	33438	70744
Di-n -Butyl Phthalate	88.9	92.4	924	24400		366	70744
Dioxins/Furans [TCDD Equivalents]	7.80E-08	7.97E-08	7.97E-07	2.31E-07	2.15E-07	3.15E-07	6.68E-07
Endrin	0.02	0.02	0.2	0.0580		0.0792	0.167
Epichlorohydrin	53.5	2013	20130	5837		7979	16881
Ethylbenzene	700	1867	18670	5413		7400	15656
Ethylene Glycol	46744	1.68E+07	1.68E+08		45301029		140886199
Fluoride	4000	1.68E+07 N/A	1.08E+08 N/A	48710784 N/A		N/A	
Heptachlor	8.0E-05	0.0001	0.001	0.000290		0.000396	N/A 0.000838
·							
Heptachlor Epoxide Hexachlorobenzene	0.00029	0.00029	0.0029	0.000841	0.000782 0.00183	0.00114	0.00243
Hexachlorobutadiene	0.21	0.22	2.2	0.638	0.593	0.872	1.84

	Water and	Fish Only	Incidental				
	Fish	Criterion	Fish	WLAh	LTAh	Daily Avg.	Daily Max.
Parameter	Criterion	(μg/L)	Criterion	(μg/L)	(μg/L)	(μg/L)	(μg/L)
Hexachlorocyclohexane (alpha)	0.0078	0.0084	0.084	0.0244	0.0227	0.0332	0.0704
Hexachlorocyclohexane (beta)	0.15	0.26	2.6	0.754	0.701	1.03	2.18
Hexachlorocyclohexane (gamma) [Lindane]	0.2	0.341	3.41	0.989	0.920	1.35	2.85
Hexachlorocyclopentadiene	10.7	11.6	116	33.6	31.3	45.9	97.2
Hexachloroethane	1.84	2.33	23.3	6.76	6.28	9.23	19.5
Hexachlorophene	2.05	2.90	29	8.41	7.82	11.4	24.3
4,4'-Isopropylidenediphenol [Bisphenol A]	1092	15982	159820	46339	43095	63350	134026
Lead	1.15	3.83	38.3	52.4	48.7	71.6	151
Mercury	0.0122	0.0122	0.122	0.0354	0.0329	0.0483	0.102
Methoxychlor	2.92	3.0	30	8.70	8.09	11.8	25.1
Methyl Ethyl Ketone	13865	9.92E+05	9.92E+06	2876256	2674918	3932129	8318994
Methyl tert -butyl ether [MTBE]	15	10482	104820	30392	28265	41548	87902
Nickel	332	1140	11400	6244	5807	8535	18058
Nitrate-Nitrogen (as Total Nitrogen)	10000	N/A	N/A	N/A	N/A	N/A	N/A
Nitrobenzene	45.7	1873	18730	5431	5051	7424	15707
N-Nitrosodiethylamine	0.0037	2.1	21	6.09	5.66	8.32	17.6
N-Nitroso-di-n -Butylamine	0.119	4.2	42	12.2	11.3	16.6	35.2
Pentachlorobenzene	0.348	0.355	3.55	1.03	0.957	1.40	2.97
Pentachlorophenol	0.22	0.29	2.9	0.841	0.782	1.14	2.43
Polychlorinated Biphenyls [PCBs]	6.4E-04	6.4E-04	6.40E-03	0.00186	0.00173	0.00253	0.00536
Pyridine	23	947	9470	2746	2554	3753	7941
Selenium	50	N/A	N/A	N/A	N/A	N/A	N/A
1,2,4,5-Tetrachlorobenzene	0.23	0.24	2.4	0.696	0.647	0.951	2.01
1,1,2,2-Tetrachloroethane	1.64	26.35	263.5	76.4	71.1	104	220
Tetrachloroethylene [Tetrachloroethylene]	5	280	2800	812	755	1109	2348
Thallium	0.12	0.23	2.3	0.667	0.620	0.911	1.92
Toluene	1000	N/A	N/A	N/A	N/A	N/A	N/A
Toxaphene	0.011	0.011	0.11	0.0319	0.0297	0.0436	0.0922
2,4,5-TP [Silvex]	50	369	3690	1070	995	1462	3094
1,1,1-Trichloroethane	200	784354	7843540	2274196	2115003	3109053	6577657
1,1,2-Trichloroethane	5	166	1660	481	448	657	1392
Trichloroethylene [Trichloroethene]	5	71.9	719	208	194	285	602
2,4,5-Trichlorophenol	1039	1867	18670	5413	5034	7400	15656
TTHM [Sum of Total Trihalomethanes]	80	N/A	N/A	N/A	N/A	N/A	N/A
Vinyl Chloride	0.23	16.5	165	47.8	44.5	65.4	138

Aquatic Life         Daily Avg. Daily Dai			
Parameter         (µg/L)         (µg/L)           Aldrin         1.76         2.14           Aluminum         584         709           Arsenic         339         412           Cadmium         1.91         2.32           Carbaryl         1.17         1.43           Chlordane         0.0048         0.0594           Chrorium (trivalent)         611         743           Chromium (trivalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol (Kelthane)         3.49         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan I (beta)         0.108         0.131           Endosulfan I (beta)         0.108         0.131           Endorin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.019		-	-
Aldrin         1.76         2.14           Aluminum         584         709           Arsenic         339         412           Cadmium         1.91         2.32           Carbaryl         1.17         1.43           Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           Leon         0.00193         0.0235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan I (alpha)         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0193 <th< th=""><th>•</th><th></th><th></th></th<>	•		
Aluminum         584         709           Arsenic         339         412           Cadmium         1.91         2.32           Carbaryl         1.17         1.43           Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan I (alpha)         0.108         0.131           Endosulfan I (beta)         0.108         0.131           Endrin (Autin (Au			
Arsenic         339         412           Cadmium         1.91         2.32           Carbaryl         1.17         1.43           Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan I (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0074         0.00490           Mercury <td< td=""><td></td><td></td><td></td></td<>			
Cadmium         1.91         2.32           Carbaryl         1.17         1.43           Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4*DDT         0.00193         0.0235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0074         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188			
Carbaryl         1.17         1.43           Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.0193         0.0235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0074         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8			
Chlordane         0.00774         0.00940           Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4*DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235 <t< td=""><td></td><td></td><td></td></t<>			
Chlorpyrifos         0.0489         0.0594           Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.0235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0074         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.184           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71			
Chromium (trivalent)         611         743           Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.018         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71			
Chromium (hexavalent)         9.25         11.2           Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.0235			
Copper         18.9         23.0           Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.0235           Nickel         173         211           Nonylphenol	· · · · · ·		
Cyanide (free)         20.7         25.1           4,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan II (beta)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlor			
A,4'-DDT         0.00193         0.00235           Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthr			
Demeton         0.193         0.235           Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           P			
Diazinon         0.100         0.121           Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.0074         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4 <td< td=""><td>4,4'-DDT</td><td>0.00193</td><td>0.00235</td></td<>	4,4'-DDT	0.00193	0.00235
Dicofol [Kelthane]         34.9         42.4           Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329	Demeton	0.193	0.235
Dieldrin         0.00387         0.00470           Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9	Diazinon	0.100	0.121
Diuron         123         150           Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9	Dicofol [Kelthane]	34.9	42.4
Endosulfan I (alpha)         0.108         0.131           Endosulfan II (beta)         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.00464         0.0564	Dieldrin	0.00387	0.00470
Endosulfan II (beta )         0.108         0.131           Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564 <td>Diuron</td> <td>123</td> <td>150</td>	Diuron	123	150
Endosulfan sulfate         0.108         0.131           Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Endosulfan I (alpha )	0.108	0.131
Endrin         0.00387         0.00470           Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Endosulfan II (beta )	0.108	0.131
Guthion [Azinphos Methyl]         0.0193         0.0235           Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Endosulfan sulfate	0.108	0.131
Heptachlor         0.00774         0.00940           Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Endrin	0.00387	0.00470
Hexachlorocyclohexane (gamma) [Lindane]         0.154         0.188           Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Guthion [Azinphos Methyl]	0.0193	0.0235
Lead         20.4         24.8           Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Heptachlor	0.00774	0.00940
Malathion         0.0193         0.0235           Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Hexachlorocyclohexane (gamma) [Lindane]	0.154	0.188
Mercury         1.41         1.71           Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Lead	20.4	24.8
Methoxychlor         0.0580         0.0705           Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Malathion	0.0193	0.0235
Mirex         0.00193         0.00235           Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Mercury	1.41	1.71
Nickel         173         211           Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Methoxychlor	0.0580	0.0705
Nonylphenol         12.7         15.5           Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Mirex	0.00193	0.00235
Parathion (ethyl)         0.0251         0.0305           Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Nickel	173	211
Pentachlorophenol         5.68         6.90           Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Nonylphenol	12.7	15.5
Phenanthrene         17.6         21.4           Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Parathion (ethyl)	0.0251	0.0305
Polychlorinated Biphenyls [PCBs]         0.0271         0.0329           Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Pentachlorophenol	5.68	6.90
Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Phenanthrene	17.6	21.4
Selenium         9.68         11.7           Silver         11.4         13.9           Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Polychlorinated Biphenyls [PCBs]	0.0271	0.0329
Toxaphene         0.000387         0.000470           Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Selenium	9.68	11.7
Tributyltin [TBT]         0.0464         0.0564           2,4,5 Trichlorophenol         80.1         97.3	Silver	11.4	13.9
2,4,5 Trichlorophenol 80.1 97.3	Toxaphene	0.000387	0.000470
•	Tributyltin [TBT]	0.0464	0.0564
•	2,4,5 Trichlorophenol	80.1	97.3
	Zinc	183	223

	70% of	85% of
Human Health	Daily Avg.	Daily Avg.
Parameter	μg/L)	(μg/L)
Acrylonitrile	319	387
Aldrin		0.0000386
Anthracene	3654	4437
Antimony	2971	3608
Arsenic	N/A	N/A
Barium	N/A	N/A
Benzene	1612	1957
Benzidine	0.296	0.360
	0.0693	0.0842
Benzo(a )avrana		
Benzo(a) pyrene	0.00693	0.00842
Bis(chloromethyl)ether	0.761	0.924
Bis(2-chloroethyl)ether	118	144
Bis(2-ethylhexyl) phthalate [Di(2-ethylhexyl) phtha	20.9	25.4
Bromodichloromethane [Dichlorobromomethane]	763	926
Bromoform [Tribromomethane]	2941	3571
Cadmium	N/A	N/A
Carbon Tetrachloride	127	154
Chlordane	0.00693	0.00842
Chlorobenzene	7594	9221
Chlorodibromomethane [Dibromochloromethane]	507	616
Chloroform [Trichloromethane]	21356	25933
Chromium (hexavalent)	1392	1691
Chrysene	6.99	8.49
Cresols [Methylphenols]	25807	31337
Cyanide (free)	N/A	N/A
4,4'-DDD	0.00554	0.00673
4,4'-DDE	0.000360	0.000438
4,4'-DDT	0.00110	0.00134
2,4'-D	N/A	N/A
Danitol [Fenpropathrin]	1312	1593
1,2-Dibromoethane [Ethylene Dibromide]	11.7	14.2
<i>m</i> -Dichlorobenzene [1,3-Dichlorobenzene]	1650	2004
o -Dichlorobenzene [1,2-Dichlorobenzene]	9153	11115
p -Dichlorobenzene [1,4-Dichlorobenzene]	N/A	N/A
3,3'-Dichlorobenzidine	6.21	7.54
1,2-Dichloroethane	1009	1226
1,1-Dichloroethylene [1,1-Dichloroethene]	152924	185693
Dichloromethane [Methylene Chloride]	36994	44922
1,2-Dichloropropane	718	872
1,3-Dichloropropene [1,3-Dichloropropylene]	330	400
Dicofol [Kelthane]	0.832	1.01
Dieldrin		0.0000673
2,4-Dimethylphenol	23407	28423
Di-n -Butyl Phthalate	256	311
Dioxins/Furans [TCDD Equivalents]	2.21E-07	2.68E-07
Endrin	0.0554	0.0673
Epichlorohydrin	5585	6782
Ethylbenzene	5180	6290
Ethylene Glycol	46614758	56603635
Fluoride		
	N/A	N/A
Heptachlor Enovide	0.000277	0.000336
Heptachlor Epoxide	0.000804	0.000977
Hexachlorobenzene	0.00188	0.00229
Hexachlorobutadiene	0.610	0.741

	70% of	85% of
Human Health	Daily Avg.	Daily Avg.
Parameter	(μg/L)	(μg/L)
Hexachlorocyclohexane (alpha)	0.0233	0.0283
Hexachlorocyclohexane (beta)	0.721	0.876
Hexachlorocyclohexane (gamma) [Lindane]	0.946	1.14
Hexachlorocyclopentadiene	32.1	39.0
Hexachloroethane	6.46	7.85
Hexachlorophene	8.04	9.77
4,4'-Isopropylidenediphenol [Bisphenol A]	44345	53847
Lead	50.1	60.8
Mercury	0.0338	0.0411
Methoxychlor	8.32	10.1
Methyl Ethyl Ketone	2752490	3342309
Methyl tert -butyl ether [MTBE]	29084	35316
Nickel	5975	7255
Nitrate-Nitrogen (as Total Nitrogen)	N/A	N/A
Nitrobenzene	5196	6310
N-Nitrosodiethylamine	5.82	7.07
N-Nitroso-di-n -Butylamine	11.6	14.1
Pentachlorobenzene	0.985	1.19
Pentachlorophenol	0.804	0.977
Polychlorinated Biphenyls [PCBs]	0.00177	0.00215
Pyridine	2627	3190
Selenium	N/A	N/A
1,2,4,5-Tetrachlorobenzene	0.665	0.808
1,1,2,2-Tetrachloroethane	73.1	88.7
Tetrachloroethylene [Tetrachloroethylene]	776	943
Thallium	0.638	0.774
Toluene	N/A	N/A
Toxaphene	0.0305	0.0370
2,4,5-TP [Silvex]	1023	1243
1,1,1-Trichloroethane	2176337	2642695
1,1,2-Trichloroethane	460	559
Trichloroethylene [Trichloroethene]	199	242
2,4,5-Trichlorophenol	5180	6290
TTHM [Sum of Total Trihalomethanes]	N/A	N/A
Vinyl Chloride	45.7	55.5

### Appendix C TDS, Chloride, and Sulfate Screening Calculations

Screening Calculations for Total Dissolved Solids, Chloride, and Sulfate Menu 2 - Discharge to an Intermittent Stream within 3 Miles of a Perennial Stream

#### Screen the Intermittent Stream

Applicant Name: Energy Transfers GC NGL Fractionators LLC
Permit Number, Outfall: WQ0005350000, 001

Segment Number: 0902

Enter values needed for screening:		Data Source (edit if different)
TDS CC - segment criterion - TDS	<b>700</b> mg/L	2018 TSWQS, Appendix A
Cl CC - segment criterion - chloride	<b>200</b> mg/L	2018 TSWQS, Appendix A
SO4 CC - segment criterion - sulfate	<b>150</b> mg/L	2018 TSWQS, Appendix A
TDS CE - average effluent concentration - TDS	<b>1145.5</b> mg/L	Permit application
Cl CE - average effluent concentration - chloride	<b>209.75</b> mg/L	Permit application
SO4 CE - average effluent concentration - sulfate	<b>448.75</b> mg/L	Permit application

### **TDS Screening**

The TDS screening value is determined by first calculating an initial TDS concentration, CTDS, as follows:

CTDS = (TDS CC / 500 mg/L) \* 2,500 mg/L

Where: CTDS = TDS concentration used to determine Csv screening value
TDS CC = TDS criterion at the first downstream segment
500 mg/L = the median TDS concentration in Texas streams
2,500 mg/L = the minimum TDS screening value

Стоs = 3500 mg/L

The next step is to use the initial CTDS to set the actual TDS screening value, TDS Csv, using the following table:

If CTDS		Then TDS Csv
≤ 2,500 mg/L	=	2,500 mg/L
> 2,500 mg/L but ≤ 6,000 mg/L	=	CTDS
> 6,000 mg/L	=	6,000 mg/L

Some specific types of intermittent streams have alternative screening values (Csv):

Specific Type of Intermittent Stream	If CTDS is	Default Csv =
Dry except for short-term flow in	< 4,000 mg/L	4,000 mg/L
immediate response to rainfall.	≥ 4,000 mg/L	Стоѕ
Constructed ditch conveying stormwater and	< 4,000 mg/L	4,000 mg/L
wastewater, considered water in the state.	≥ 4,000 mg/L	Стоѕ
Within 3 miles of tidal waters.	-	6,000 mg/L

Once TDS Csv is established, the next step is to compare the effluent TDS concentration, TDS CE, to the screening value. Control measures, which may include effluent limitations, are considered for TDS if the effluent TDS is greater than the screening value.

Values needed for Screening		Data Source			
TDS CE - average effluent TDS concer	ntration	1145.5	mg/L	Permit application	
TDS Csv - TDS screening value	2500	mg/L	Determined above		
No control measures needed if:	1145.5	≤	2500		
Consider control measures if:	1145.5	>	2500		

No control measures needed for TDS

#### **Chloride Screening**

If TDS limits are necessary or there are concerns about chloride, additional screening can be performed for chloride. First calculate the screening value for chloride, Cl Csv, as follows:

CI Csv = (TDS Csv /TDS CC) \* CI CC

Where:	Cl Csv = chloride screening value
	TDS Csv = TDS screening value
	TDS CC = TDS criterion at the first downstream segment
	CI CC - chloride criterion at the first downstream segment

Cl Csv = **714.28571** mg/L

Once the CI Csv is established, the next step is to compare the effluent chloride concentration, CI CE, to the screening value. Control measures, which may include effluent limitations, are considered for chloride if the effluent chloride is greater than the screening value.

		Data Source
209.75	mg/L	Permit application
714.28571	mg/L	Determined above
		209.75 mg/L 714.28571 mg/L

No control measures needed if: 209.75 ≤ 714.2857 Consider control measures if: 209.75 > 714.2857

### No control measures needed for chloride

### **Sulfate Screening**

If TDS limits are necessary or there are concerns about sulfate, additional screening can be performed for sulfate. First calculate the screening value for sulfate, SO4 Csv, as follows:

SO4 Csv = (TDS Csv /TDS CC) \* SO4 CC

Where:	SO4 Csv = sulfate screening value
	TDS Csv = TDS screening value
	TDS CC = TDS criterion at the first downstream segment
	SO4 CC - sulfate criterion at the first downstream segment

SO4 Csv = **535.71429** mg/L

Once the SO4 Csv is established, the next step is to compare the effluent sulfate concentration, SO4 CE, to the screening value. Control measures, which may include effluent limitations, are considered for sulfate if the effluent sulfate is greater than the screening value.

Values needed for Screening			Data Source
SO4 CE - average effluent sulfate concentration	448.75	mg/L	Permit application
SO4 Csv - sulfate screening value	535.71429	mg/L	Determined above

No control measures needed if: 448.75 ≤ 535.7143

Consider control measures if: 448.75 > 535.7143

No control measures needed for sulfate

### Appendix D Comparison of Effluent Limits

The following table is a summary of technology-based effluent limitations calculated/assessed in the draft permit (Technology-Based), calculated/assessed water quality-based effluent limitations (Water Quality-Based), and effluent limitations in the existing permit (Existing Permit). Effluent limitations appearing in bold are the most stringent of the three and are included in the draft permit.

		Technology-Based			Water Quality-Based			Existing Permit					
Outfall	Pollutant	Daily	Avg	Daily	Max	Daily	Avg	Daily .	Max	Daily 2	Avg	Daily	Max
		lbs/day	mg/L	lbs/day	mg/L	lbs/day	mg/L	lbs/day	mg/L	lbs/day	mg/L	lbs/day	mg/L
	Flow	0.936	MGD	1.276	1.276 MGD			-		0.936 MGD		1.276	MGD
	BOD5	156.125	20	234.187	30	-	-	-	-	106.42	20	159.63	30
	TOC	-	N/A	-	75	-	-	-	1	-	N/A	-	<b>75</b>
001	Oil and Grease	-	N/A	-	15	-	-	ı	ı	ı	N/A	-	15
	TRC	-	-	-	-	-	-	ı	ı	ı	N/A	-	0.019
	DO	-		-	-		2.0, minimum			-		-	-
	pН	6.0 SU, m	inimum	9.0	9.0 SU		-		-		6.5 SU, minimum		SU