



Technical Package Cover Page

This file contains the following documents:

1. Summary of application (in plain language)
 - English
 - Alternative Language (Spanish)
2. First notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
 - English
 - Alternative Language (Spanish)
3. Second notice (NAPD-Notice of Preliminary Decision)
 - English
 - Alternative Language (Spanish)
4. Application materials *
5. Draft permit *
6. Technical summary or fact sheet *

* **NOTE:** This application was declared Administratively Complete before June 1, 2024. The application materials, draft permit, and technical summary or fact sheet are available for review at the Public Viewing Location provided in the NAPD.

Section 15. Plain Language Summary (Instructions Page 40)

If you are subject to the alternative language notice requirements in [30 Texas Administrative Code §39.426](#), **you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package.** For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS

DOMESTIC WASTEWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

City of Olney (CN 600652309) operates the City of Olney wastewater treatment plant RN 101610335. an activated sludge plant that utilizes an oxidation ditch. The facility is located 1,500 ft southeast of the intersection of Spring Creek Rd and HWY 79, in Olney, Young County, Texas 76374.

This application is for a renewal to discharge at an annual flow of 790,000 gallons per day of treated domestic wastewater via outfalls 001 and 002. Currently, the plant only discharges through outfall 001 and the test results in the technical report are from outfall 001. *<<For TLAP applications include the following sentence, otherwise delete:>>* This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are expected to contain five-day carbonaceous biochemical oxygen demand (CBOD₅), total suspended solids (TSS), ammonia nitrogen (NH₃-N), and *Escherichia coli*. Additional potential pollutants are included in the Domestic Technical Report 1.0, Section 7. Pollutant Analysis of Treated Effluent in the permit application package. Domestic wastewater is treated by an activated sludge process plant that includes units such as bar screen, oxidation ditch, clarifiers, chlorine contact basins, and reaeration basin.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT RENEWAL

PERMIT NO. WQ0010050001

APPLICATION. City of Olney, P.O. Box 546, Olney, Texas 76374, has applied to the Texas Commission on Environmental Quality (TCEQ) to renew Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0010050001 (EPA I.D. No. TX0024261) to authorize the discharge of treated wastewater at a volume not to exceed a daily average flow of 790,000 gallons per day. The domestic wastewater treatment facility is located approximately 1,500 feet southeast of the intersection of Spring Creek Road and State Highway 79, in Young County, Texas 76374. The discharge route is from the plant site via Outfall 001 to Salt Creek; thence to Lake Graham; via pipeline to Outfall 002 to Lake Olney; thence to Lake Cooper; thence to Mesquite Creek; thence to South Fork Little Wichita River; thence to Little Wichita River; thence to Lake Arrowhead. TCEQ received this application on April 1, 2024. The permit application will be available for viewing and copying at Olney City Hall, 201 East Main Street, Olney, in Young County, Texas prior to the date this notice is published in the newspaper. This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-98.745555,33.360277&level=18>

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. **Notice of the Application and Preliminary Decision will be published and mailed to those who are on the county-wide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.**

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. **Unless the application**

is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. **If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.**

TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at <https://www14.tceq.texas.gov/epic/eComment/>, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105,

P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from City of Olney at the address stated above or by calling Mr. Michael Jacoba, Public Works Director, at 940-276-2011.

Issuance Date: April 15, 2024

Texas Commission on Environmental Quality



COMBINED

NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT (NORI)

AND

NOTICE OF APPLICATION AND PRELIMINARY DECISION FOR TPDES PERMIT FOR MUNICIPAL WASTEWATER

RENEWAL

PERMIT NO. WQ0010050001

APPLICATION AND PRELIMINARY DECISION. City of Olney, P.O. Box 546, Olney, Texas 76374, has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0010050001 which authorizes the discharge of treated domestic wastewater at a daily average flow not to exceed 790,000 gallons per day. TCEQ received this application on April 1, 2024.

This combined notice is being issued to correct the discharge route description for Outfall 001 in the original NORI.

The facility is located approximately 1,500 feet southeast of the intersection of Spring Creek Road and State Highway 79, in Young County, Texas 76374. The treated effluent is discharged **via Outfall 001 to an unnamed ditch**, thence to Salt Creek, thence to Lake Graham in Segment No. 1231 of the Brazos River Basin; and via pipeline to Outfall 002 to Lake Olney, thence to Lake Cooper, thence to Mesquite Creek, thence to South Fork Little Wichita River, thence to Little Wichita River, thence to Lake Arrowhead in Segment No. 0212 of the Red River Basin. The unclassified receiving water uses are minimal aquatic life use for the unnamed ditch, limited aquatic life use for Salt Creek and Mesquite Creek, and high aquatic life use for Lake Olney and Lake Cooper. The designated uses for Segment Nos. 1231 and 0212 are primary contact recreation, public water supply, and high aquatic life use. All determinations are preliminary and subject to additional review and/or revisions. This link to an electronic map of the site or facility's general location is provided as a public courtesy and is not part of the application or notice. For the exact location, refer to the application.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-98.745555,33.360277&level=18>

The TCEQ Executive Director has completed the technical review of the application and prepared a draft permit. The draft permit, if approved, would establish the conditions under which the facility must operate. The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The permit application, Executive Director's preliminary decision, and draft permit are available for viewing and copying at Olney City Hall, 201 East Main Street, Olney, Texas.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting about this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ holds a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. **Unless the application is directly referred for a contested case hearing, the response to comments will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting a contested case hearing or reconsideration of the Executive Director's decision.** A contested case hearing is a legal proceeding similar to a civil trial in a state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period; and the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. **If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period. TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.**

EXECUTIVE DIRECTOR ACTION. The Executive Director may issue final approval of the application unless a timely contested case hearing request or request for reconsideration is filed. If a timely hearing request or request for reconsideration is filed, the Executive Director will not issue final approval of the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

All written public comments and public meeting requests must be submitted to the Office of the Chief Clerk, MC 105, Texas Commission on Environmental Quality, P.O. Box 13087, Austin, TX 78711-3087 or electronically at www.tceq.texas.gov/goto/comment within 30 days from the date of newspaper publication of this notice.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. Public comments and requests must be submitted either electronically at www.tceq.texas.gov/goto/comment, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC 105, P.O. Box 13087, Austin, Texas 78711-3087. Any personal information you submit to the TCEQ will become part of the agency's record; this includes email addresses. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from City of Olney at the address stated above or by calling Mr. Michael Jacoba, Public Works Director, at 940-276-2011.

Issuance Date: August 13, 2024



TPDES PERMIT NO.
WQ0010050001
*[For TCEQ office use only - EPA I.D.
No. TX0024261]*

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
P.O. Box 13087
Austin, Texas 78711-3087

This is a renewal that replaces TPDES
Permit No. WQ0010050001 issued on
October 7, 2019.

PERMIT TO DISCHARGE WASTES
under provisions of
Section 402 of the Clean Water Act
and Chapter 26 of the Texas Water Code

City of Olney

whose mailing address is

P.O. Box 546
Olney, Texas 76374

is authorized to treat and discharge wastes from the City of Olney Wastewater Treatment Facility, SIC
Code 4952

located approximately 1,500 feet southeast of the intersection of Spring Creek Road and State Highway
79, in Young County, Texas 76374

via Outfall 001 to an unnamed ditch, thence to Salt Creek, thence to Lake Graham in Segment No. 1231
of the Brazos River Basin; and via pipeline to Outfall 002 to Lake Olney, thence to Lake Cooper, thence
to Mesquite Creek, thence to South Fork Little Wichita River, thence to Little Wichita River, thence to
Lake Arrowhead in Segment No. 0212 of the Red River Basin

only according to effluent limitations, monitoring requirements, and other conditions set forth in this
permit, as well as the rules of the Texas Commission on Environmental Quality (TCEQ), the laws of the
State of Texas, and other orders of the TCEQ. The issuance of this permit does not grant to the
permittee the right to use private or public property for conveyance of wastewater along the discharge
route described in this permit. This includes, but is not limited to, property belonging to any individual,
partnership, corporation or other entity. Neither does this permit authorize any invasion of personal
rights nor any violation of federal, state, or local laws or regulations. It is the responsibility of the
permittee to acquire property rights as may be necessary to use the discharge route.

This permit shall expire at midnight, **five years from the date of issuance.**

ISSUED DATE:

For the Commission

EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTSOutfall Number 001

1. During the period beginning upon the date of issuance and lasting through the date of expiration, the permittee is authorized to discharge subject to the following effluent limitations:

The daily average flow of effluent shall not exceed 0.79 million gallons per day (MGD)*, nor shall the average discharge during any two-hour period (2-hour peak) exceed 1,646 gallons per minute (gpm).

<u>Effluent Characteristic</u>	<u>Discharge Limitations</u>				<u>Min. Self-Monitoring Requirements</u>	
	Daily Avg mg/l (lbs/day)	7-day Avg mg/l	Daily Max mg/l	Single Grab mg/l	Report Daily Avg. & Daily Max. Measurement Frequency	Sample Type
Flow, MGD	Report	N/A	Report	N/A	Continuous	Totalizing Meter
Carbonaceous Biochemical Oxygen Demand (5-day)	10 (66)	12	22	32	One/week	Composite
Total Suspended Solids	15 (99)	25	40	60	One/week	Composite
Ammonia Nitrogen	3 (20)	6	10	15	One/week	Composite
<i>E. coli</i> , colony-forming units or most probable number per 100 ml	126	N/A	399	N/A	Two/month	Grab

*The combined daily average flows from Outfalls 001 and 002 shall not exceed 0.79 MGD.

2. The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes (based on peak flow), and shall be monitored daily by grab sample. An equivalent method of disinfection may be substituted only with prior approval of the Executive Director.
3. The pH shall not be less than 6.0 standard units nor greater than 9.0 standard units and shall be monitored twice per month by grab sample.
4. There shall be no discharge of floating solids or visible foam in other than trace amounts and no discharge of visible oil.
5. Effluent monitoring samples shall be taken at the following location(s): Following the final treatment unit.
6. The effluent shall contain a minimum dissolved oxygen of 4.0 mg/l and shall be monitored once per week by grab sample.

EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTSOutfall Number 002

1. During the period beginning upon the date of issuance and lasting through the date of expiration, the permittee is authorized to discharge subject to the following effluent limitations:

The daily average flow of effluent shall not exceed 0.79 million gallons per day (MGD)*, nor shall the average discharge during any two-hour period (2-hour peak) exceed 1,646 gallons per minute (gpm).

<u>Effluent Characteristic</u>	<u>Discharge Limitations</u>				<u>Min. Self-Monitoring Requirements</u>	
	Daily Avg mg/l (lbs/day)	7-day Avg mg/l	Daily Max mg/l	Single Grab mg/l	Report Daily Avg. & Daily Max. Measurement Frequency	Sample Type
Flow, MGD	Report	N/A	Report	N/A	Continuous	Totalizing Meter
Carbonaceous Biochemical Oxygen Demand (5-day)	7 (46)	12	22	32	One/week	Composite
Total Suspended Solids	15 (99)	25	40	60	One/week	Composite
Ammonia Nitrogen	2 (13)	5	10	15	One/week	Composite
<i>E. coli</i> , colony-forming units or most probable number per 100 ml	126	N/A	399	N/A	Two/month	Grab

*The combined daily average flows from Outfalls 001 and 002 shall not exceed 0.79 MGD.

2. The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes (based on peak flow), and shall be monitored daily by grab sample. An equivalent method of disinfection may be substituted only with prior approval of the Executive Director.
3. The pH shall not be less than 6.0 standard units nor greater than 9.0 standard units and shall be monitored twice per month by grab sample.
4. There shall be no discharge of floating solids or visible foam in other than trace amounts and no discharge of visible oil.
5. Effluent monitoring samples shall be taken at the following location(s): Following the final treatment unit.
6. The effluent shall contain a minimum dissolved oxygen of 5.0 mg/l and shall be monitored once per week by grab sample.

DEFINITIONS AND STANDARD PERMIT CONDITIONS

As required by Title 30 Texas Administrative Code (TAC) Chapter 305, certain regulations appear as standard conditions in waste discharge permits. 30 TAC § 305.121 - 305.129 (relating to Permit Characteristics and Conditions) as promulgated under the Texas Water Code (TWC) §§ 5.103 and 5.105, and the Texas Health and Safety Code (THSC) §§ 361.017 and 361.024(a), establish the characteristics and standards for waste discharge permits, including sewage sludge, and those sections of 40 Code of Federal Regulations (CFR) Part 122 adopted by reference by the Commission. The following text includes these conditions and incorporates them into this permit. All definitions in TWC § 26.001 and 30 TAC Chapter 305 shall apply to this permit and are incorporated by reference. Some specific definitions of words or phrases used in this permit are as follows:

1. Flow Measurements

- a. Annual average flow - the arithmetic average of all daily flow determinations taken within the preceding 12 consecutive calendar months. The annual average flow determination shall consist of daily flow volume determinations made by a totalizing meter, charted on a chart recorder and limited to major domestic wastewater discharge facilities with one million gallons per day or greater permitted flow.
- b. Daily average flow - the arithmetic average of all determinations of the daily flow within a period of one calendar month. The daily average flow determination shall consist of determinations made on at least four separate days. If instantaneous measurements are used to determine the daily flow, the determination shall be the arithmetic average of all instantaneous measurements taken during that month. Daily average flow determination for intermittent discharges shall consist of a minimum of three flow determinations on days of discharge.
- c. Daily maximum flow - the highest total flow for any 24-hour period in a calendar month.
- d. Instantaneous flow - the measured flow during the minimum time required to interpret the flow measuring device.
- e. 2-hour peak flow (domestic wastewater treatment plants) - the maximum flow sustained for a two-hour period during the period of daily discharge. The average of multiple measurements of instantaneous maximum flow within a two-hour period may be used to calculate the 2-hour peak flow.
- f. Maximum 2-hour peak flow (domestic wastewater treatment plants) - the highest 2-hour peak flow for any 24-hour period in a calendar month.

2. Concentration Measurements

- a. Daily average concentration - the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar month, consisting of at least four separate representative measurements.
 - i. For domestic wastewater treatment plants - When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values in the previous four consecutive month period consisting of at least four measurements shall be utilized as the daily average concentration.

- ii. For all other wastewater treatment plants - When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values taken during the month shall be utilized as the daily average concentration.
- b. 7-day average concentration - the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar week, Sunday through Saturday.
- c. Daily maximum concentration - the maximum concentration measured on a single day, by the sample type specified in the permit, within a period of one calendar month.
- d. Daily discharge - the discharge of a pollutant measured during a calendar day or any 24-hour period that reasonably represents the calendar day for purposes of sampling. For pollutants with limitations expressed in terms of mass, the daily discharge is calculated as the total mass of the pollutant discharged over the sampling day. For pollutants with limitations expressed in other units of measurement, the daily discharge is calculated as the average measurement of the pollutant over the sampling day.

The daily discharge determination of concentration made using a composite sample shall be the concentration of the composite sample. When grab samples are used, the daily discharge determination of concentration shall be the arithmetic average (weighted by flow value) of all samples collected during that day.

- e. Bacteria concentration (*E. coli* or Enterococci) - Colony Forming Units (CFU) or Most Probable Number (MPN) of bacteria per 100 milliliters effluent. The daily average bacteria concentration is a geometric mean of the values for the effluent samples collected in a calendar month. The geometric mean shall be determined by calculating the n th root of the product of all measurements made in a calendar month, where n equals the number of measurements made; or, computed as the antilogarithm of the arithmetic mean of the logarithms of all measurements made in a calendar month. For any measurement of bacteria equaling zero, a substituted value of one shall be made for input into either computation method. If specified, the 7-day average for bacteria is the geometric mean of the values for all effluent samples collected during a calendar week.
 - f. Daily average loading (lbs/day) - the arithmetic average of all daily discharge loading calculations during a period of one calendar month. These calculations must be made for each day of the month that a parameter is analyzed. The daily discharge, in terms of mass (lbs/day), is calculated as (Flow, MGD x Concentration, mg/l x 8.34).
 - g. Daily maximum loading (lbs/day) - the highest daily discharge, in terms of mass (lbs/day), within a period of one calendar month.
3. Sample Type
- a. Composite sample - For domestic wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (a). For industrial wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (b).

- b. Grab sample - an individual sample collected in less than 15 minutes.
- 4. Treatment Facility (facility) - wastewater facilities used in the conveyance, storage, treatment, recycling, reclamation and/or disposal of domestic sewage, industrial wastes, agricultural wastes, recreational wastes, or other wastes including sludge handling or disposal facilities under the jurisdiction of the Commission.
- 5. The term "sewage sludge" is defined as solid, semi-solid, or liquid residue generated during the treatment of domestic sewage in 30 TAC Chapter 312. This includes the solids that have not been classified as hazardous waste separated from wastewater by unit processes.
- 6. The term "biosolids" is defined as sewage sludge that has been tested or processed to meet Class A, Class AB, or Class B pathogen standards in 30 TAC Chapter 312 for beneficial use.
- 7. Bypass - the intentional diversion of a waste stream from any portion of a treatment facility.

MONITORING AND REPORTING REQUIREMENTS

1. Self-Reporting

Monitoring results shall be provided at the intervals specified in the permit. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall conduct effluent sampling and reporting in accordance with 30 TAC §§ 319.4 - 319.12. Unless otherwise specified, effluent monitoring data shall be submitted each month, to the Compliance Monitoring Team of the Enforcement Division (MC 224), by the 20th day of the following month for each discharge which is described by this permit whether or not a discharge is made for that month. Monitoring results must be submitted online using the NetDMR reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. Monitoring results must be signed and certified as required by Monitoring and Reporting Requirements No. 10.

As provided by state law, the permittee is subject to administrative, civil and criminal penalties, as applicable, for negligently or knowingly violating the Clean Water Act (CWA); TWC §§ 26, 27, and 28; and THSC § 361, including but not limited to knowingly making any false statement, representation, or certification on any report, record, or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance, or falsifying, tampering with or knowingly rendering inaccurate any monitoring device or method required by this permit or violating any other requirement imposed by state or federal regulations.

2. Test Procedures

- a. Unless otherwise specified in this permit, test procedures for the analysis of pollutants shall comply with procedures specified in 30 TAC §§ 319.11 - 319.12. Measurements, tests, and calculations shall be accurately accomplished in a representative manner.
- b. All laboratory tests submitted to demonstrate compliance with this permit must meet the requirements of 30 TAC § 25, Environmental Testing Laboratory Accreditation and Certification.

3. Records of Results

- a. Monitoring samples and measurements shall be taken at times and in a manner so as to be representative of the monitored activity.

- b. Except for records of monitoring information required by this permit related to the permittee's sewage sludge or biosolids use and disposal activities, which shall be retained for a period of at least five years (or longer as required by 40 CFR Part 503), monitoring and reporting records, including strip charts and records of calibration and maintenance, copies of all records required by this permit, records of all data used to complete the application for this permit, and the certification required by 40 CFR § 264.73(b)(9) shall be retained at the facility site, or shall be readily available for review by a TCEQ representative for a period of three years from the date of the record or sample, measurement, report, application or certification. This period shall be extended at the request of the Executive Director.
- c. Records of monitoring activities shall include the following:
 - i. date, time and place of sample or measurement;
 - ii. identity of individual who collected the sample or made the measurement.
 - iii. date and time of analysis;
 - iv. identity of the individual and laboratory who performed the analysis;
 - v. the technique or method of analysis; and
 - vi. the results of the analysis or measurement and quality assurance/quality control records.

The period during which records are required to be kept shall be automatically extended to the date of the final disposition of any administrative or judicial enforcement action that may be instituted against the permittee.

4. Additional Monitoring by Permittee

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit using approved analytical methods as specified above, all results of such monitoring shall be included in the calculation and reporting of the values submitted on the approved self-report form. Increased frequency of sampling shall be indicated on the self-report form.

5. Calibration of Instruments

All automatic flow measuring or recording devices and all totalizing meters for measuring flows shall be accurately calibrated by a trained person at plant start-up and as often thereafter as necessary to ensure accuracy, but not less often than annually unless authorized by the Executive Director for a longer period. Such person shall verify in writing that the device is operating properly and giving accurate results. Copies of the verification shall be retained at the facility site and/or shall be readily available for review by a TCEQ representative for a period of three years.

6. Compliance Schedule Reports

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date to the Regional Office and the Compliance

Monitoring Team of the Enforcement Division (MC 224).

7. Noncompliance Notification

- a. In accordance with 30 TAC § 305.125(9) any noncompliance which may endanger human health or safety, or the environment shall be reported by the permittee to the TCEQ. Except as allowed by 30 TAC § 305.132, report of such information shall be provided orally or by facsimile transmission (FAX) to the Regional Office within 24 hours of becoming aware of the noncompliance. A written submission of such information shall also be provided by the permittee to the Regional Office and the Compliance Monitoring Team of the Enforcement Division (MC 224) within five working days of becoming aware of the noncompliance. For Publicly Owned Treatment Works (POTWs), effective December 21, 2025, the permittee must submit the written report for unauthorized discharges and unanticipated bypasses that exceed any effluent limit in the permit using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. The written submission shall contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
 - b. The following violations shall be reported under Monitoring and Reporting Requirement 7.a.:
 - i. Unauthorized discharges as defined in Permit Condition 2(g).
 - ii. Any unanticipated bypass that exceeds any effluent limitation in the permit.
 - iii. Violation of a permitted maximum daily discharge limitation for pollutants listed specifically in the Other Requirements section of an Industrial TPDES permit.
 - c. In addition to the above, any effluent violation which deviates from the permitted effluent limitation by more than 40% shall be reported by the permittee in writing to the Regional Office and the Compliance Monitoring Team of the Enforcement Division (MC 224) within 5 working days of becoming aware of the noncompliance.
 - d. Any noncompliance other than that specified in this section, or any required information not submitted or submitted incorrectly, shall be reported to the Compliance Monitoring Team of the Enforcement Division (MC 224) as promptly as possible. For effluent limitation violations, noncompliances shall be reported on the approved self-report form.
8. In accordance with the procedures described in 30 TAC §§ 35.301 - 35.303 (relating to Water Quality Emergency and Temporary Orders) if the permittee knows in advance of the need for a bypass, it shall submit prior notice by applying for such authorization.
9. Changes in Discharges of Toxic Substances

All existing manufacturing, commercial, mining, and silvicultural permittees shall notify the Regional Office, orally or by facsimile transmission within 24 hours, and both the Regional Office and the Compliance Monitoring Team of the Enforcement Division (MC 224) in writing within five (5) working days, after becoming aware of or having reason to believe:

- a. That any activity has occurred or will occur which would result in the discharge, on a routine or frequent basis, of any toxic pollutant listed at 40 CFR Part 122, Appendix D, Tables II and III (excluding Total Phenols) which is not limited in the permit, if that discharge will exceed the highest of the following “notification levels”:
 - i. One hundred micrograms per liter (100 µg/L);
 - ii. Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
 - iii. Five (5) times the maximum concentration value reported for that pollutant in the permit application; or
 - iv. The level established by the TCEQ.
- b. That any activity has occurred or will occur which would result in any discharge, on a nonroutine or infrequent basis, of a toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following “notification levels”:
 - i. Five hundred micrograms per liter (500 µg/L);
 - ii. One milligram per liter (1 mg/L) for antimony;
 - iii. Ten (10) times the maximum concentration value reported for that pollutant in the permit application; or
 - iv. The level established by the TCEQ.

10. Signatories to Reports

All reports and other information requested by the Executive Director shall be signed by the person and in the manner required by 30 TAC § 305.128 (relating to Signatories to Reports).

11. All POTWs must provide adequate notice to the Executive Director of the following:

- a. Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to CWA § 301 or § 306 if it were directly discharging those pollutants;
- b. Any substantial change in the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit; and
- c. For the purpose of this paragraph, adequate notice shall include information on:
 - i. The quality and quantity of effluent introduced into the POTW; and
 - ii. Any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

PERMIT CONDITIONS**1. General**

- a. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in an application or in any report to the Executive Director, it shall promptly submit such facts or information.
- b. This permit is granted on the basis of the information supplied and representations made by the permittee during action on an application, and relying upon the accuracy and completeness of that information and those representations. After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked, in whole or in part, in accordance with 30 TAC Chapter 305, Subchapter D, during its term for good cause including, but not limited to, the following:
 - i. Violation of any terms or conditions of this permit;
 - ii. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
 - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- c. The permittee shall furnish to the Executive Director, upon request and within a reasonable time, any information to determine whether cause exists for amending, revoking, suspending or terminating the permit. The permittee shall also furnish to the Executive Director, upon request, copies of records required to be kept by the permit.

2. Compliance

- a. Acceptance of the permit by the person to whom it is issued constitutes acknowledgment and agreement that such person will comply with all the terms and conditions embodied in the permit, and the rules and other orders of the Commission.
- b. The permittee has a duty to comply with all conditions of the permit. Failure to comply with any permit condition constitutes a violation of the permit and the Texas Water Code or the Texas Health and Safety Code, and is grounds for enforcement action, for permit amendment, revocation, or suspension, or for denial of a permit renewal application or an application for a permit for another facility.
- c. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit.
- d. The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal or other permit violation that has a reasonable likelihood of adversely affecting human health or the environment.
- e. Authorization from the Commission is required before beginning any change in the permitted facility or activity that may result in noncompliance with any permit requirements.
- f. A permit may be amended, suspended and reissued, or revoked for cause in accordance

with 30 TAC §§ 305.62 and 305.66 and TWC§ 7.302. The filing of a request by the permittee for a permit amendment, suspension and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

- g. There shall be no unauthorized discharge of wastewater or any other waste. For the purpose of this permit, an unauthorized discharge is considered to be any discharge of wastewater into or adjacent to water in the state at any location not permitted as an outfall or otherwise defined in the Other Requirements section of this permit.
- h. In accordance with 30 TAC § 305.535(a), the permittee may allow any bypass to occur from a TPDES permitted facility which does not cause permitted effluent limitations to be exceeded or an unauthorized discharge to occur, but only if the bypass is also for essential maintenance to assure efficient operation.
- i. The permittee is subject to administrative, civil, and criminal penalties, as applicable, under TWC §§ 7.051 - 7.075 (relating to Administrative Penalties), 7.101 - 7.111 (relating to Civil Penalties), and 7.141 - 7.202 (relating to Criminal Offenses and Penalties) for violations including, but not limited to, negligently or knowingly violating the federal CWA §§ 301, 302, 306, 307, 308, 318, or 405, or any condition or limitation implementing any sections in a permit issued under the CWA § 402, or any requirement imposed in a pretreatment program approved under the CWA §§ 402 (a)(3) or 402 (b)(8).

3. Inspections and Entry

- a. Inspection and entry shall be allowed as prescribed in the TWC Chapters 26, 27, and 28, and THSC § 361.
- b. The members of the Commission and employees and agents of the Commission are entitled to enter any public or private property at any reasonable time for the purpose of inspecting and investigating conditions relating to the quality of water in the state or the compliance with any rule, regulation, permit or other order of the Commission. Members, employees, or agents of the Commission and Commission contractors are entitled to enter public or private property at any reasonable time to investigate or monitor or, if the responsible party is not responsive or there is an immediate danger to public health or the environment, to remove or remediate a condition related to the quality of water in the state. Members, employees, Commission contractors, or agents acting under this authority who enter private property shall observe the establishment's rules and regulations concerning safety, internal security, and fire protection, and if the property has management in residence, shall notify management or the person then in charge of his presence and shall exhibit proper credentials. If any member, employee, Commission contractor, or agent is refused the right to enter in or on public or private property under this authority, the Executive Director may invoke the remedies authorized in TWC § 7.002. The statement above, that Commission entry shall occur in accordance with an establishment's rules and regulations concerning safety, internal security, and fire protection, is not grounds for denial or restriction of entry to any part of the facility, but merely describes the Commission's duty to observe appropriate rules and regulations during an inspection.

4. Permit Amendment and/or Renewal

- a. The permittee shall give notice to the Executive Director as soon as possible of any planned physical alterations or additions to the permitted facility if such alterations or additions would require a permit amendment or result in a violation of permit requirements. Notice shall also be required under this paragraph when:
 - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in accordance with 30 TAC § 305.534 (relating to New Sources and New Dischargers); or
 - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are subject neither to effluent limitations in the permit, nor to notification requirements in Monitoring and Reporting Requirements No. 9; or
 - iii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan.
- b. Prior to any facility modifications, additions, or expansions that will increase the plant capacity beyond the permitted flow, the permittee must apply for and obtain proper authorization from the Commission before commencing construction.
- c. The permittee must apply for an amendment or renewal at least 180 days prior to expiration of the existing permit in order to continue a permitted activity after the expiration date of the permit. If an application is submitted prior to the expiration date of the permit, the existing permit shall remain in effect until the application is approved, denied, or returned. If the application is returned or denied, authorization to continue such activity shall terminate upon the effective date of the action. If an application is not submitted prior to the expiration date of the permit, the permit shall expire and authorization to continue such activity shall terminate.
- d. Prior to accepting or generating wastes which are not described in the permit application or which would result in a significant change in the quantity or quality of the existing discharge, the permittee must report the proposed changes to the Commission. The permittee must apply for a permit amendment reflecting any necessary changes in permit conditions, including effluent limitations for pollutants not identified and limited by this permit.
- e. In accordance with the TWC § 26.029(b), after a public hearing, notice of which shall be given to the permittee, the Commission may require the permittee, from time to time, for good cause, in accordance with applicable laws, to conform to new or additional conditions.
- f. If any toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under CWA § 307(a) for a toxic pollutant which is present in the discharge and that standard or prohibition is more stringent than any limitation on the pollutant in this permit, this permit shall be modified or revoked and reissued to conform to the toxic effluent standard or prohibition. The permittee shall comply with effluent standards or prohibitions established under CWA § 307(a) for toxic pollutants within the time provided in the

regulations that established those standards or prohibitions, even if the permit has not yet been modified to incorporate the requirement.

5. Permit Transfer

- a. Prior to any transfer of this permit, Commission approval must be obtained. The Commission shall be notified in writing of any change in control or ownership of facilities authorized by this permit. Such notification should be sent to the Applications Review and Processing Team (MC 148) of the Water Quality Division.
- b. A permit may be transferred only according to the provisions of 30 TAC § 305.64 (relating to Transfer of Permits) and 30 TAC § 50.133 (relating to Executive Director Action on Application or WQMP update).

6. Relationship to Hazardous Waste Activities

This permit does not authorize any activity of hazardous waste storage, processing, or disposal that requires a permit or other authorization pursuant to the Texas Health and Safety Code.

7. Relationship to Water Rights

Disposal of treated effluent by any means other than discharge directly to water in the state must be specifically authorized in this permit and may require a permit pursuant to TWC Chapter 11.

8. Property Rights

A permit does not convey any property rights of any sort, or any exclusive privilege.

9. Permit Enforceability

The conditions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

10. Relationship to Permit Application

The application pursuant to which the permit has been issued is incorporated herein; provided, however, that in the event of a conflict between the provisions of this permit and the application, the provisions of the permit shall control.

11. Notice of Bankruptcy

- a. Each permittee shall notify the Executive Director, in writing, immediately following the filing of a voluntary or involuntary petition for bankruptcy under any chapter of Title 11 (Bankruptcy) of the United States Code (11 USC) by or against:
 - i. the permittee;
 - ii. an entity (as that term is defined in 11 USC, § 101(14)) controlling the permittee or listing the permit or permittee as property of the estate; or
 - iii. an affiliate (as that term is defined in 11 USC, § 101(2)) of the permittee.

- b. This notification must indicate:
 - i. the name of the permittee;
 - ii. the permit number(s);
 - iii. the bankruptcy court in which the petition for bankruptcy was filed; and
 - iv. the date of filing of the petition.

OPERATIONAL REQUIREMENTS

1. The permittee shall at all times ensure that the facility and all of its systems of collection, treatment, and disposal are properly operated and maintained. This includes, but is not limited to, the regular, periodic examination of wastewater solids within the treatment plant by the operator in order to maintain an appropriate quantity and quality of solids inventory as described in the various operator training manuals and according to accepted industry standards for process control. Process control, maintenance, and operations records shall be retained at the facility site, or shall be readily available for review by a TCEQ representative, for a period of three years.
2. Upon request by the Executive Director, the permittee shall take appropriate samples and provide proper analysis in order to demonstrate compliance with Commission rules. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall comply with all applicable provisions of 30 TAC Chapter 312 concerning sewage sludge or biosolids use and disposal and 30 TAC §§ 319.21 - 319.29 concerning the discharge of certain hazardous metals.
3. Domestic wastewater treatment facilities shall comply with the following provisions:
 - a. The permittee shall notify the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, in writing, of any facility expansion at least 90 days prior to conducting such activity.
 - b. The permittee shall submit a closure plan for review and approval to the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, for any closure activity at least 90 days prior to conducting such activity. Closure is the act of permanently taking a waste management unit or treatment facility out of service and includes the permanent removal from service of any pit, tank, pond, lagoon, surface impoundment and/or other treatment unit regulated by this permit.
4. The permittee is responsible for installing prior to plant start-up, and subsequently maintaining, adequate safeguards to prevent the discharge of untreated or inadequately treated wastes during electrical power failures by means of alternate power sources, standby generators, and/or retention of inadequately treated wastewater.
5. Unless otherwise specified, the permittee shall provide a readily accessible sampling point and, where applicable, an effluent flow measuring device or other acceptable means by which effluent flow may be determined.
6. The permittee shall remit an annual water quality fee to the Commission as required by 30

TAC Chapter 21. Failure to pay the fee may result in revocation of this permit under TWC § 7.302(b)(6).

7. Documentation

For all written notifications to the Commission required of the permittee by this permit, the permittee shall keep and make available a copy of each such notification under the same conditions as self-monitoring data are required to be kept and made available. Except for information required for TPDES permit applications, effluent data, including effluent data in permits, draft permits and permit applications, and other information specified as not confidential in 30 TAC §§ 1.5(d), any information submitted pursuant to this permit may be claimed as confidential by the submitter. Any such claim must be asserted in the manner prescribed in the application form or by stamping the words confidential business information on each page containing such information. If no claim is made at the time of submission, information may be made available to the public without further notice. If the Commission or Executive Director agrees with the designation of confidentiality, the TCEQ will not provide the information for public inspection unless required by the Texas Attorney General or a court pursuant to an open records request. If the Executive Director does not agree with the designation of confidentiality, the person submitting the information will be notified.

8. Facilities that generate domestic wastewater shall comply with the following provisions; domestic wastewater treatment facilities at permitted industrial sites are excluded.

- a. Whenever flow measurements for any domestic sewage treatment facility reach 75% of the permitted daily average or annual average flow for three consecutive months, the permittee must initiate engineering and financial planning for expansion and/or upgrading of the domestic wastewater treatment and/or collection facilities. Whenever the flow reaches 90% of the permitted daily average or annual average flow for three consecutive months, the permittee shall obtain necessary authorization from the Commission to commence construction of the necessary additional treatment and/or collection facilities. In the case of a domestic wastewater treatment facility which reaches 75% of the permitted daily average or annual average flow for three consecutive months, and the planned population to be served or the quantity of waste produced is not expected to exceed the design limitations of the treatment facility, the permittee shall submit an engineering report supporting this claim to the Executive Director of the Commission.

If in the judgment of the Executive Director the population to be served will not cause permit noncompliance, then the requirement of this section may be waived. To be effective, any waiver must be in writing and signed by the Director of the Enforcement Division (MC 219) of the Commission, and such waiver of these requirements will be reviewed upon expiration of the existing permit; however, any such waiver shall not be interpreted as condoning or excusing any violation of any permit parameter.

- b. The plans and specifications for domestic sewage collection and treatment works associated with any domestic permit must be approved by the Commission and failure to secure approval before commencing construction of such works or making a discharge is a violation of this permit and each day is an additional violation until approval has been secured.

- c. Permits for domestic wastewater treatment plants are granted subject to the policy of the Commission to encourage the development of area-wide waste collection, treatment, and disposal systems. The Commission reserves the right to amend any domestic wastewater permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an area-wide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such area-wide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.
9. Domestic wastewater treatment plants shall be operated and maintained by sewage plant operators holding a valid certificate of competency at the required level as defined in 30 TAC Chapter 30.
10. For Publicly Owned Treatment Works (POTWs), the 30-day average (or monthly average) percent removal for BOD and TSS shall not be less than 85%, unless otherwise authorized by this permit.
11. Facilities that generate industrial solid waste as defined in 30 TAC § 335.1 shall comply with these provisions:
 - a. Any solid waste, as defined in 30 TAC § 335.1 (including but not limited to such wastes as garbage, refuse, sludge from a waste treatment, water supply treatment plant or air pollution control facility, discarded materials, discarded materials to be recycled, whether the waste is solid, liquid, or semisolid), generated by the permittee during the management and treatment of wastewater, must be managed in accordance with all applicable provisions of 30 TAC Chapter 335, relating to Industrial Solid Waste Management.
 - b. Industrial wastewater that is being collected, accumulated, stored, or processed before discharge through any final discharge outfall, specified by this permit, is considered to be industrial solid waste until the wastewater passes through the actual point source discharge and must be managed in accordance with all applicable provisions of 30 TAC Chapter 335.
 - c. The permittee shall provide written notification, pursuant to the requirements of 30 TAC § 335.8(b)(1), to the Corrective Action Section (MC 127) of the Remediation Division informing the Commission of any closure activity involving an Industrial Solid Waste Management Unit, at least 90 days prior to conducting such an activity.
 - d. Construction of any industrial solid waste management unit requires the prior written notification of the proposed activity to the Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division. No person shall dispose of industrial solid waste, including sludge or other solids from wastewater treatment processes, prior to fulfilling the deed recordation requirements of 30 TAC § 335.5.
 - e. The term "industrial solid waste management unit" means a landfill, surface impoundment, waste-pile, industrial furnace, incinerator, cement kiln, injection well,

container, drum, salt dome waste containment cavern, or any other structure vessel, appurtenance, or other improvement on land used to manage industrial solid waste.

- f. The permittee shall keep management records for all sludge (or other waste) removed from any wastewater treatment process. These records shall fulfill all applicable requirements of 30 TAC § 335 and must include the following, as it pertains to wastewater treatment and discharge:
 - i. Volume of waste and date(s) generated from treatment process;
 - ii. Volume of waste disposed of on-site or shipped off-site;
 - iii. Date(s) of disposal;
 - iv. Identity of hauler or transporter;
 - v. Location of disposal site; and
 - vi. Method of final disposal.

The above records shall be maintained on a monthly basis. The records shall be retained at the facility site, or shall be readily available for review by authorized representatives of the TCEQ for at least five years.

12. For industrial facilities to which the requirements of 30 TAC § 335 do not apply, sludge and solid wastes, including tank cleaning and contaminated solids for disposal, shall be disposed of in accordance with THSC § 361.

TCEQ Revision 06/2020

SLUDGE PROVISIONS

The permittee is authorized to dispose of sludge or biosolids only at a Texas Commission on Environmental Quality (TCEQ) authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge. **The disposal of sludge or biosolids by land application on property owned, leased or under the direct control of the permittee is a violation of the permit unless the site is authorized with the TCEQ. This provision does not authorize Distribution and Marketing of Class A or Class AB Biosolids. This provision does not authorize the permittee to land apply biosolids on property owned, leased or under the direct control of the permittee.**

SECTION I. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE OR BIOSOLIDS LAND APPLICATION

A. General Requirements

1. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC § 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge or biosolids.
2. In all cases, if the person (permit holder) who prepares the sewage sludge supplies the sewage sludge to another person for land application use or to the owner or lease holder of the land, the permit holder shall provide necessary information to the parties who receive the sludge to assure compliance with these regulations.
3. The land application of processed or unprocessed chemical toilet waste, grease trap waste, grit trap waste, milk solids, or similar non-hazardous municipal or industrial solid wastes, or any of the wastes listed in this provision combined with biosolids, WTP residuals or domestic septage is prohibited unless the grease trap waste is added at a fats, oil and grease (FOG) receiving facility as part of an anaerobic digestion process.

B. Testing Requirements

1. Sewage sludge or biosolids shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I [Toxicity Characteristic Leaching Procedure (TCLP)] or other method that receives the prior approval of the TCEQ for the contaminants listed in 40 CFR Part 261.24, Table 1. Sewage sludge or biosolids failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal. Following failure of any TCLP test, the management or disposal of sewage sludge or biosolids at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge or biosolids no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division and the Regional Director (MC Region 3) within seven (7) days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped, and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Permitting and Registration Support Division (MC 129), Texas Commission on Environmental Quality, P.O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 3) and the Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30th of each year. The permittee must submit this annual report using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver.

2. Biosolids shall not be applied to the land if the concentration of the pollutants exceeds the pollutant concentration criteria in Table 1. The frequency of testing for pollutants in Table 1 is found in Section I.C. of this permit.

TABLE 1

<u>Pollutant</u>	<u>Ceiling Concentration</u> <u>(Milligrams per kilogram)*</u>
Arsenic	75
Cadmium	85
Chromium	3000
Copper	4300
Lead	840
Mercury	57
Molybdenum	75
Nickel	420
PCBs	49
Selenium	100
Zinc	7500

* Dry weight basis

3. Pathogen Control

All sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site must be treated by one of the following methods to ensure that the sludge meets either the Class A, Class AB or Class B biosolids pathogen requirements.

- a. For sewage sludge to be classified as Class A biosolids with respect to pathogens, the density of fecal coliform in the sewage sludge must be less than 1,000 most probable number (MPN) per gram of total solids (dry weight basis), or the density of *Salmonella* sp. bacteria in the sewage sludge must be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met:

Alternative 1 - The temperature of the sewage sludge that is used or disposed shall be maintained at or above a specific value for a period of time. See 30 TAC § 312.82(a)(2)(A) for specific information;

Alternative 5 (PFRP) - Sewage sludge that is used or disposed of must be treated in one of the Processes to Further Reduce Pathogens (PFRP) described in 40 CFR Part 503, Appendix B. PFRP include composting, heat drying, heat treatment, and thermophilic aerobic digestion; or

Alternative 6 (PFRP Equivalent) - Sewage sludge that is used or disposed of must be treated in a process that has been approved by the U. S. Environmental Protection Agency as being equivalent to those in Alternative 5.

- b. For sewage sludge to be classified as Class AB biosolids with respect to pathogens, the density of fecal coliform in the sewage sludge must be less than 1,000 MPN per gram of total solids (dry weight basis), or the density of *Salmonella* sp. bacteria in the sewage sludge be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met:

Alternative 2 - The pH of the sewage sludge that is used or disposed shall be raised to above 12 std. units and shall remain above 12 std. units for 72 hours.

The temperature of the sewage sludge shall be above 52° Celsius for 12 hours or longer during the period that the pH of the sewage sludge is above 12 std. units.

At the end of the 72-hour period during which the pH of the sewage sludge is above 12 std. units, the sewage sludge shall be air dried to achieve a percent solids in the sewage sludge greater than 50%; or

Alternative 3 - The sewage sludge shall be analyzed for enteric viruses prior to pathogen treatment. The limit for enteric viruses is less than one Plaque-forming Unit per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(i-iii) for specific information. The sewage sludge shall be analyzed for viable helminth ova prior to pathogen treatment. The limit for viable helminth ova is less than one per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(iv-vi) for specific information; or

Alternative 4 - The density of enteric viruses in the sewage sludge shall be less than one Plaque-forming Unit per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. The density of viable helminth ova in the sewage sludge shall be less than one per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed.

- c. Sewage sludge that meets the requirements of Class AB biosolids may be classified a Class A biosolids if a variance request is submitted in writing that is supported by substantial documentation demonstrating equivalent methods for reducing odors and written approval is granted by the executive director. The executive director may deny the variance request or revoke that approved variance if it is determined that the variance may potentially endanger human health or the environment, or create nuisance odor conditions.
- d. Three alternatives are available to demonstrate compliance with Class B biosolids

criteria.

Alternative 1

- i. A minimum of seven random samples of the sewage sludge shall be collected within 48 hours of the time the sewage sludge is used or disposed of during each monitoring episode for the sewage sludge.
- ii. The geometric mean of the density of fecal coliform in the samples collected shall be less than either 2,000,000 MPN per gram of total solids (dry weight basis) or 2,000,000 Colony Forming Units per gram of total solids (dry weight basis).

Alternative 2 - Sewage sludge that is used or disposed of shall be treated in one of the Processes to Significantly Reduce Pathogens (PSRP) described in 40 CFR Part 503, Appendix B, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;
- ii. An independent Texas Licensed Professional Engineer must make a certification to the generator of a sewage sludge that the wastewater treatment facility generating the sewage sludge is designed to achieve one of the PSRP at the permitted design loading of the facility. The certification need only be repeated if the design loading of the facility is increased. The certification shall include a statement indicating the design meets all the applicable standards specified in Appendix B of 40 CFR Part 503;
- iii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iv. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review; and
- v. If the sewage sludge is generated from a mixture of sources, resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the PSRP, and shall meet the certification, operation, and record keeping requirements of this paragraph.

Alternative 3 - Sewage sludge shall be treated in an equivalent process that has been approved by the U.S. Environmental Protection Agency, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a

single location, except as provided in paragraph v. below;

- ii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iii. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review;
- iv. The Executive Director will accept from the U.S. Environmental Protection Agency a finding of equivalency to the defined PSRP; and
- v. If the sewage sludge is generated from a mixture of sources resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the Processes to Significantly Reduce Pathogens, and shall meet the certification, operation, and record keeping requirements of this paragraph.

In addition to the Alternatives 1 – 3, the following site restrictions must be met if Class B biosolids are land applied:

- i. Food crops with harvested parts that touch the biosolids/soil mixture and are totally above the land surface shall not be harvested for 14 months after application of biosolids.
- ii. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after application of biosolids when the biosolids remain on the land surface for 4 months or longer prior to incorporation into the soil.
- iii. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months after application of biosolids when the biosolids remain on the land surface for less than 4 months prior to incorporation into the soil.
- iv. Food crops, feed crops, and fiber crops shall not be harvested for 30 days after application of biosolids.
- v. Domestic livestock shall not be allowed to graze on the land for 30 days after application of biosolids.
- vi. Turf grown on land where biosolids are applied shall not be harvested for 1 year after application of the biosolids when the harvested turf is placed on either land with a high potential for public exposure or a lawn.
- vii. Public access to land with a high potential for public exposure shall be restricted for 1 year after application of biosolids.

- viii. Public access to land with a low potential for public exposure shall be restricted for 30 days after application of biosolids.
 - ix. Land application of biosolids shall be in accordance with the buffer zone requirements found in 30 TAC § 312.44.
4. Vector Attraction Reduction Requirements

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site shall be treated by one of the following Alternatives 1 through 10 for vector attraction reduction.

- Alternative 1 - The mass of volatile solids in the sewage sludge shall be reduced by a minimum of 38%.
- Alternative 2 - If Alternative 1 cannot be met for an anaerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge anaerobically in the laboratory in a bench-scale unit for 40 additional days at a temperature between 30° and 37° Celsius. Volatile solids must be reduced by less than 17% to demonstrate compliance.
- Alternative 3 - If Alternative 1 cannot be met for an aerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge with percent solids of two percent or less aerobically in the laboratory in a bench-scale unit for 30 additional days at 20° Celsius. Volatile solids must be reduced by less than 15% to demonstrate compliance.
- Alternative 4 - The specific oxygen uptake rate (SOUR) for sewage sludge treated in an aerobic process shall be equal to or less than 1.5 milligrams of oxygen per hour per gram of total solids (dry weight basis) at a temperature of 20° Celsius.
- Alternative 5 - Sewage sludge shall be treated in an aerobic process for 14 days or longer. During that time, the temperature of the sewage sludge shall be higher than 40° Celsius and the average temperature of the sewage sludge shall be higher than 45° Celsius.
- Alternative 6 - The pH of sewage sludge shall be raised to 12 or higher by alkali addition and, without the addition of more alkali shall remain at 12 or higher for two hours and then remain at a pH of 11.5 or higher for an additional 22 hours at the time the sewage sludge is prepared for sale or given away in a bag or other container.
- Alternative 7 - The percent solids of sewage sludge that does not contain unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 75% based on the moisture content and total solids prior to mixing with other materials. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

Alternative 8 - The percent solids of sewage sludge that contains unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 90% based on the moisture content and total solids prior to mixing with other materials at the time the sludge is used. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

Alternative 9 -

- i. Biosolids shall be injected below the surface of the land.
- ii. No significant amount of the biosolids shall be present on the land surface within one hour after biosolids are injected.
- iii. When sewage sludge that is injected below the surface of the land is Class A or Class AB with respect to pathogens, the biosolids shall be injected below the land surface within eight hours after being discharged from the pathogen treatment process.

Alternative 10 -

- i. Biosolids applied to the land surface or placed on a surface disposal site shall be incorporated into the soil within six hours after application to or placement on the land.
- ii. When biosolids that are incorporated into the soil is Class A or Class AB with respect to pathogens, the biosolids shall be applied to or placed on the land within eight hours after being discharged from the pathogen treatment process.

C. Monitoring Requirements

Toxicity Characteristic Leaching Procedure (TCLP) Test	- once during the term of this permit
PCBs	- once during the term of this permit

All metal constituents and fecal coliform or *Salmonella* sp. bacteria shall be monitored at the appropriate frequency shown below, pursuant to 30 TAC § 312.46(a)(1):

<u>Amount of biosolids (*) metric tons per 365-day period</u>	<u>Monitoring Frequency</u>
0 to less than 290	Once/Year
290 to less than 1,500	Once/Quarter
1,500 to less than 15,000	Once/Two Months
15,000 or greater	Once/Month

(*) *The amount of bulk biosolids applied to the land (dry wt. basis).*

Representative samples of sewage sludge shall be collected and analyzed in accordance with the methods referenced in 30 TAC § 312.7

Identify each of the analytic methods used by the facility to analyze enteric viruses, fecal coliforms, helminth ova, *Salmonella* sp., and other regulated parameters.

Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.

Identify the nature of material generated by the facility (such as a biosolid for beneficial use or land-farming, or sewage sludge or biosolids for disposal at a landfill) and whether the material is ultimately conveyed off-site in bulk or in bags.

SECTION II. REQUIREMENTS SPECIFIC TO BULK SEWAGE SLUDGE FOR APPLICATION TO THE LAND MEETING CLASS A, CLASS AB or B BIOSOLIDS PATHOGEN REDUCTION AND THE CUMULATIVE LOADING RATES IN TABLE 2, OR CLASS B PATHOGEN REDUCTION AND THE POLLUTANT CONCENTRATIONS IN TABLE 3

For those permittees meeting Class A, Class AB or B pathogen reduction requirements and that meet the cumulative loading rates in Table 2 below, or the Class B pathogen reduction requirements and contain concentrations of pollutants below listed in Table 3, the following conditions apply:

A. Pollutant Limits

Table 2

<u>Pollutant</u>	Cumulative Pollutant Loading Rate (pounds per acre)*
Arsenic	36
Cadmium	35
Chromium	2677
Copper	1339
Lead	268
Mercury	15
Molybdenum	Report Only
Nickel	375
Selenium	89
Zinc	2500

Table 3

<u>Pollutant</u>	Monthly Average Concentration (milligrams per kilogram)*
Arsenic	41
Cadmium	39
Chromium	1200
Copper	1500
Lead	300
Mercury	17
Molybdenum	Report Only
Nickel	420
Selenium	36
Zinc	2800

*Dry weight basis

B. Pathogen Control

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, a reclamation site, shall be treated by either Class A, Class AB or Class B biosolids pathogen reduction requirements as defined above in Section I.B.3.

C. Management Practices

1. Bulk biosolids shall not be applied to agricultural land, forest, a public contact site, or a reclamation site that is flooded, frozen, or snow-covered so that the bulk biosolids enters a wetland or other waters in the State.
2. Bulk biosolids not meeting Class A biosolids requirements shall be land applied in a manner which complies with Applicability in accordance with 30 TAC §312.41 and the Management Requirements in accordance with 30 TAC § 312.44.
3. Bulk biosolids shall be applied at or below the agronomic rate of the cover crop.
4. An information sheet shall be provided to the person who receives bulk Class A or AB biosolids sold or given away. The information sheet shall contain the following information:
 - a. The name and address of the person who prepared the Class A or AB biosolids that are sold or given away in a bag or other container for application to the land.
 - b. A statement that application of the biosolids to the land is prohibited except in accordance with the instruction on the label or information sheet.
 - c. The annual whole sludge application rate for the biosolids application rate for the biosolids that does not cause any of the cumulative pollutant loading rates in Table 2 above to be exceeded, unless the pollutant concentrations in Table 3 found in Section II above are met.

D. Notification Requirements

1. If bulk biosolids are applied to land in a State other than Texas, written notice shall be provided prior to the initial land application to the permitting authority for the State in which the bulk biosolids are proposed to be applied. The notice shall include:
 - a. The location, by street address, and specific latitude and longitude, of each land application site.
 - b. The approximate time period bulk biosolids will be applied to the site.
 - c. The name, address, telephone number, and National Pollutant Discharge Elimination System permit number (if appropriate) for the person who will apply the bulk biosolids.
2. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the biosolids disposal practice.

E. Record Keeping Requirements

The documents will be retained at the facility site and/or shall be readily available for review by a TCEQ representative. The person who prepares bulk sewage sludge or a biosolids material shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative for a period

of five years. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply.

1. The concentration (mg/kg) in the sludge of each pollutant listed in Table 3 above and the applicable pollutant concentration criteria (mg/kg), or the applicable cumulative pollutant loading rate and the applicable cumulative pollutant loading rate limit (lbs/ac) listed in Table 2 above.
2. A description of how the pathogen reduction requirements are met (including site restrictions for Class AB and Class B biosolids, if applicable).
3. A description of how the vector attraction reduction requirements are met.
4. A description of how the management practices listed above in Section II.C are being met.
5. The following certification statement:

“I certify, under penalty of law, that the applicable pathogen requirements in 30 TAC § 312.82(a) or (b) and the vector attraction reduction requirements in 30 TAC § 312.83(b) have been met for each site on which bulk biosolids are applied. This determination has been made under my direction and supervision in accordance with the system designed to ensure that qualified personnel properly gather and evaluate the information used to determine that the management practices have been met. I am aware that there are significant penalties for false certification including fine and imprisonment.”

6. The recommended agronomic loading rate from the references listed in Section II.C.3. above, as well as the actual agronomic loading rate shall be retained. The person who applies bulk biosolids shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative indefinitely. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply:
 - a. A certification statement that all applicable requirements (specifically listed) have been met, and that the permittee understands that there are significant penalties for false certification including fine and imprisonment. See 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii), as applicable, and to the permittee’s specific sludge treatment activities.
 - b. The location, by street address, and specific latitude and longitude, of each site on which biosolids are applied.
 - c. The number of acres in each site on which bulk biosolids are applied.
 - d. The date and time biosolids are applied to each site.

- e. The cumulative amount of each pollutant in pounds/acre listed in Table 2 applied to each site.
- f. The total amount of biosolids applied to each site in dry tons.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

F. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 3) and Compliance Monitoring Team (MC 224) of the Enforcement Division, by September 30th of each year the following information. The permittee must submit this annual report using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver.

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. Identify the nature of material generated by the facility (such as a biosolid for beneficial use or land-farming, or sewage sludge for disposal at a monofill) and whether the material is ultimately conveyed off-site in bulk or in bags.
3. Results of tests performed for pollutants found in either Table 2 or 3 as appropriate for the permittee's land application practices.
4. The frequency of monitoring listed in Section I.C. that applies to the permittee.
5. Toxicity Characteristic Leaching Procedure (TCLP) results.
6. PCB concentration in sludge or biosolids in mg/kg.
7. Identity of hauler(s) and TCEQ transporter number.
8. Date(s) of transport.
9. Texas Commission on Environmental Quality registration number, if applicable.
10. Amount of sludge or biosolids disposal dry weight (lbs/acre) at each disposal site.
11. The concentration (mg/kg) in the sludge of each pollutant listed in Table 1 (defined as a monthly average) as well as the applicable pollutant concentration criteria (mg/kg) listed in Table 3 above, or the applicable pollutant loading rate limit (lbs/acre) listed in Table 2 above if it exceeds 90% of the limit.
12. Level of pathogen reduction achieved (Class A, Class AB or Class B).
13. Alternative used as listed in Section I.B.3.(a. or b.). Alternatives describe how the pathogen reduction requirements are met. If Class B biosolids, include information on how site restrictions were met.

14. Identify each of the analytic methods used by the facility to analyze enteric viruses, fecal coliforms, helminth ova, *Salmonella* sp., and other regulated parameters.
15. Vector attraction reduction alternative used as listed in Section I.B.4.
16. Amount of sludge or biosolids transported in dry tons/year.
17. The certification statement listed in either 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii) as applicable to the permittee's sludge or biosolids treatment activities, shall be attached to the annual reporting form.
18. When the amount of any pollutant applied to the land exceeds 90% of the cumulative pollutant loading rate for that pollutant, as described in Table 2, the permittee shall report the following information as an attachment to the annual reporting form.
 - a. The location, by street address, and specific latitude and longitude.
 - b. The number of acres in each site on which bulk biosolids are applied.
 - c. The date and time bulk biosolids are applied to each site.
 - d. The cumulative amount of each pollutant (i.e., pounds/acre) listed in Table 2 in the bulk biosolids applied to each site.
 - e. The amount of biosolids (i.e., dry tons) applied to each site.

The above records shall be maintained on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SECTION III. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE OR BIOSOLIDS DISPOSED IN A MUNICIPAL SOLID WASTE LANDFILL

- A. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC § 330 and all other applicable state and federal regulations to protect public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present. The permittee shall ensure that the sewage sludge or biosolids meets the requirements in 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- B. If the permittee generates sewage sludge or biosolids and supplies that sewage sludge or biosolids to the owner or operator of a municipal solid waste landfill (MSWLF) for disposal, the permittee shall provide to the owner or operator of the MSWLF appropriate information needed to be in compliance with the provisions of this permit.
- C. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge or biosolids disposal practice.
- D. Sewage sludge or biosolids shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I (Toxicity Characteristic Leaching Procedure) or other method, which receives the prior approval of the TCEQ for contaminants listed in Table 1 of 40 CFR § 261.24. Sewage sludge or biosolids failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal.

Following failure of any TCLP test, the management or disposal of sewage sludge or biosolids at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge or biosolids no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division and the Regional Director (MC Region 3) of the appropriate TCEQ field office within 7 days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped, and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Permitting and Registration Support Division (MC 129), Texas Commission on Environmental Quality, P. O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 3) and the Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30 of each year.

- E. Sewage sludge or biosolids shall be tested as needed, in accordance with the requirements of 30 TAC Chapter 330.
- F. Record Keeping Requirements

The permittee shall develop the following information and shall retain the information for five years.

1. The description (including procedures followed and the results) of all liquid Paint Filter Tests performed.
2. The description (including procedures followed and results) of all TCLP tests performed.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

G. Reporting Requirements

The permittee shall report annually to the TCEQ Regional Office (MC Region 3) and Compliance Monitoring Team (MC 224) of the Enforcement Division by September 30th of each year the following information. The permittee must submit this annual report using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver.

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. Toxicity Characteristic Leaching Procedure (TCLP) results.
3. Annual sludge or biosolids production in dry tons/year.
4. Amount of sludge or biosolids disposed in a municipal solid waste landfill in dry tons/year.
5. Amount of sludge or biosolids transported interstate in dry tons/year.
6. A certification that the sewage sludge or biosolids meets the requirements of 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
7. Identity of hauler(s) and transporter registration number.
8. Owner of disposal site(s).
9. Location of disposal site(s).
10. Date(s) of disposal.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SECTION IV. REQUIREMENTS APPLYING TO SLUDGE OR BIOSOLIDS TRANSPORTED TO ANOTHER FACILITY FOR FURTHER PROCESSING

These provisions apply to sludge or biosolids that is transported to another wastewater treatment facility or facility that further processes sludge or biosolids. These provisions are intended to allow transport of sludge or biosolids to facilities that have been authorized to accept sludge or biosolids. These provisions do not limit the ability of the receiving facility to determine whether to accept the sludge or biosolids, nor do they limit the ability of the receiving facility to request additional testing or documentation.

A. General Requirements

1. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC Chapter 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge.
2. Sludge or biosolids may only be transported using a registered transporter or using an approved pipeline.

B. Record Keeping Requirements

1. For sludge or biosolids transported by an approved pipeline, the permittee must maintain records of the following:
 - a. the amount of sludge or biosolids transported;
 - b. the date of transport;
 - c. the name and TCEQ permit number of the receiving facility or facilities;
 - d. the location of the receiving facility or facilities;
 - e. the name and TCEQ permit number of the facility that generated the waste; and
 - f. copy of the written agreement between the permittee and the receiving facility to accept sludge or biosolids.
2. For sludge or biosolids transported by a registered transporter, the permittee must maintain records of the completed trip tickets in accordance with 30 TAC § 312.145(a)(1)-(7) and amount of sludge or biosolids transported.
3. The above records shall be maintained on-site on a monthly basis and shall be made available to the TCEQ upon request. These records shall be retained for at least five years.

C. Reporting Requirements

The permittee shall report the following information annually to the TCEQ Regional Office (MC Region 3) and Compliance Monitoring Team (MC 224) of the Enforcement Division, by September 30th of each year. The permittee must submit this annual report using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver.

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. the annual sludge or biosolids production;
3. the amount of sludge or biosolids transported;
4. the owner of each receiving facility;
5. the location of each receiving facility; and
6. the date(s) of disposal at each receiving facility.

OTHER REQUIREMENTS

1. The permittee shall employ or contract with one or more licensed wastewater treatment facility operators or wastewater system operations companies holding a valid license or registration according to the requirements of 30 TAC Chapter 30, Occupational Licenses and Registrations, and in particular 30 TAC Chapter 30, Subchapter J, Wastewater Operators and Operations Companies.

This Category C facility must be operated by a chief operator or an operator holding a Class C license or higher. The facility must be operated a minimum of five days per week by the licensed chief operator or an operator holding the required level of license or higher. The licensed chief operator or operator holding the required level of license or higher must be available by telephone or pager seven days per week. Where shift operation of the wastewater treatment facility is necessary, each shift that does not have the on-site supervision of the licensed chief operator must be supervised by an operator in charge who is licensed not less than one level below the category for the facility.

2. The facility is not located in the Coastal Management Program boundary.
3. The permittee shall submit sufficient evidence of legal restrictions prohibiting residential structures within the part of the buffer zone not owned by the permittee according to 30 TAC § 309.13(e)(3). The evidence of legal restrictions shall be submitted to the Executive Director in care of the TCEQ Wastewater Permitting Section (MC 148). The permittee shall comply with the requirements of 30 TAC § 309.13(a) through (d). (See Attachment A.)
4. The permittee shall provide facilities for the protection of its wastewater treatment facility from a 100-year flood.
5. In accordance with 30 TAC § 319.9, a permittee that has at least twelve months of uninterrupted compliance with its bacteria limit may notify the commission in writing of its compliance and request a less frequent measurement schedule. To request a less frequent schedule, the permittee shall submit a written request to the TCEQ Wastewater Permitting Section (MC 148) for each phase that includes a different monitoring frequency. The request must contain all of the reported bacteria values (Daily Avg. and Daily Max/Single Grab) for the twelve consecutive months immediately prior to the request. If the Executive Director finds that a less frequent measurement schedule is protective of human health and the environment, the permittee may be given a less frequent measurement schedule. For this permit, 2/month may be reduced to 1/month. **A violation of any bacteria limit by a facility that has been granted a less frequent measurement schedule will require the permittee to return to the standard frequency schedule and submit written notice to the TCEQ Wastewater Permitting Section (MC 148).** The permittee may not apply for another reduction in measurement frequency for at least 24 months from the date of the last violation. The Executive Director may establish a more frequent measurement schedule if necessary to protect human health or the environment.
6. Prior to construction of the Outfall 002 for discharge into Lake Olney, the permittee shall submit to the TCEQ Wastewater Permitting Section (MC 148) a summary transmittal letter in accordance with the requirements in 30 TAC § 217.6(d). If requested by the Wastewater Permitting Section, the permittee shall submit plans, specifications, and a final engineering design report which comply with 30 TAC Chapter 217, Design Criteria for Domestic Wastewater Systems. The permittee shall clearly show how the treatment system will meet

the effluent limitations required on Page 2a of this permit. A copy of the summary transmittal letter shall be available at the plant site for inspection by authorized representatives of the TCEQ.

7. For Outfall 002, reporting requirements according to 30 TAC §§ 319.1-319.11 and any additional effluent reporting requirements contained in this permit are suspended from the effective date of the permit until discharge via Outfall 002 from the facility described by this permit. The permittee shall provide written notice to the TCEQ Regional Office (MC Region 3) and the Applications Review and Processing Team (MC 148) of the Water Quality Division, in writing at least forty-five days prior to anticipated discharge from Outfall 002 on Notification of Completion Form 20007.


CONTRIBUTING INDUSTRIES AND PRETREATMENT REQUIREMENTS

1. The following pollutants may not be introduced into the treatment facility:
 - a. Pollutants which create a fire or explosion hazard in the publicly owned treatment works (POTW), including, but not limited to, waste streams with a closed-cup flash point of less than 140° Fahrenheit (60° Celsius) using the test methods specified in 40 CFR § 261.21;
 - b. Pollutants which will cause corrosive structural damage to the POTW, but in no case shall there be discharges with a pH lower than 5.0 standard units, unless the works are specifically designed to accommodate such discharges;
 - c. Solid or viscous pollutants in amounts which will cause obstruction to the flow in the POTW, resulting in Interference;
 - d. Any pollutant, including oxygen-demanding pollutants (e.g., biochemical oxygen demand or BOD), released in a discharge at a flow rate and/or pollutant concentration which will cause Interference with the POTW;
 - e. Heat in amounts which will inhibit biological activity in the POTW, resulting in Interference, but in no case shall there be heat in such quantities that the temperature at the POTW treatment plant exceeds 104° Fahrenheit (40° Celsius) unless the Executive Director, upon request of the POTW, approves alternate temperature limits;
 - f. Petroleum oil, nonbiodegradable cutting oil, or products of mineral oil origin in amounts that will cause Interference or Pass Through;
 - g. Pollutants which result in the presence of toxic gases, vapors, or fumes within the POTW in a quantity that may cause acute worker health and safety problems; and
 - h. Any trucked or hauled pollutants except at discharge points designated by the POTW.
2. The permittee shall require any indirect discharger to the treatment works to comply with the reporting requirements of Sections 204(b), 307, and 308 of the Clean Water Act, including any requirements established under 40 CFR Part 403 [*rev. Federal Register/ Vol. 70/ No. 198/ Friday, October 14, 2005/ Rules and Regulations, pages 60134-60798*].
3. The permittee shall provide adequate notification to the Executive Director, care of the Wastewater Permitting Section (MC 148) of the Water Quality Division, within 30 days subsequent to the permittee's knowledge of either of the following:
 - a. Any new introduction of pollutants into the treatment works from an indirect discharger which would be subject to Sections 301 and 306 of the Clean Water Act if it were directly discharging those pollutants; and
 - b. Any substantial change in the volume or character of pollutants being introduced into the treatment works by a source introducing pollutants into the treatment works at the time of issuance of the permit.

Any notice shall include information on the quality and quantity of effluent to be introduced into the treatment works and any anticipated impact of the change on the quality or quantity of effluent to be discharged from the POTW.

Revised July 2007

ATTACHMENT A



CITY OF OLNEY
WASTEWATER PLANT SITE

SCALE: 1" = 100'



**STATEMENT OF BASIS/TECHNICAL SUMMARY
AND EXECUTIVE DIRECTOR'S PRELIMINARY DECISION**

DESCRIPTION OF APPLICATION

Applicant:	City of Olney Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0010050001, EPA ID No. TX0024261
Regulated Activity:	Domestic Wastewater Permit
Type of Application:	Renewal
Request:	Renewal with no changes
Authority:	Federal Clean Water Act (CWA) § 402; Texas Water Code (TWC) § 26.027; 30 Texas Administrative Code (TAC) Chapters 30, 305, 307, 309, 312, and 319; Commission policies; and United States Environmental Protection Agency (EPA) guidelines.

EXECUTIVE DIRECTOR RECOMMENDATION

The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The draft permit includes an expiration date of **five years from the date of issuance**.

REASON FOR PROJECT PROPOSED

The applicant has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of the existing permit that authorizes the discharge of treated domestic wastewater at a daily average flow not to exceed 0.79 million gallons per day (MGD). The existing wastewater treatment facility serves the City of Olney.

PROJECT DESCRIPTION AND LOCATION

The City of Olney Wastewater Treatment Facility is an activated sludge process plant operated in the complete mix mode. Treatment units include bar screens, an oxidation ditch, two final clarifiers, four sludge drying beds, a chlorine contact chamber and a re-aeration basin. The facility is in operation.

Sludge generated from the treatment facility is hauled by a registered transporter and disposed of at a TCEQ-permitted landfill, Buffalo Creek Landfill, Permit No. MSW 1571A, in Wichita County. The draft permit also authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

The plant site is located approximately 1,500 feet southeast of the intersection of Spring Creek Road and State Highway 79, in Young County, Texas 76374.

Outfall Location:

Outfall Number	Latitude	Longitude
001	33.359983	-98.746155
002	33.434678	-98.780708

The treated effluent is discharged via Outfall 001 to an unnamed ditch, thence to Salt Creek, thence to Lake Graham in Segment No. 1231 of the Brazos River Basin; and via pipeline to Outfall 002 to Lake Olney, thence to Lake Cooper, thence to Mesquite Creek, thence to South Fork Little Wichita River, thence to Little Wichita River, thence to Lake Arrowhead in Segment No. 0212 of the Red River Basin. The unclassified receiving water uses are minimal aquatic life use for the unnamed ditch, limited aquatic life use for Salt Creek and Mesquite Creek, and high aquatic life use for Lake Olney and Lake Cooper. The designated uses for Segment Nos. 1231 and 0212 are primary contact recreation, public water supply, and high aquatic life use. The effluent limitations in the draft permit will maintain and protect the existing instream uses. All determinations are preliminary and subject to additional review and/or revisions.

Effluent limitations for the conventional effluent parameters (i.e., Five-Day Biochemical Oxygen Demand or Five-Day Carbonaceous Biochemical Oxygen Demand, Ammonia Nitrogen, etc.) are based on stream standards and waste load allocations for water-quality limited streams as established in the Texas Surface Water Quality Standards (TSWQS) and the State of Texas Water Quality Management Plan (WQMP).

In a case such as this, end-of-pipe compliance with pH limits between 6.0 and 9.0 standard units reasonably assures instream compliance with the TSWQS for pH when the discharge authorized is from a minor facility. This technology-based approach reasonably assures instream compliance with TSWQS criteria due to the relatively smaller discharge volumes authorized by these permits. This conservative assumption is based on TCEQ sampling conducted throughout the state which indicates that instream buffering quickly restores pH levels to ambient conditions. Similarly, this approach has been historically applied within EPA issued NPDES general permits where technology-based pH limits were established to be protective of water quality criteria.

The effluent limitations in the draft permit have been reviewed for consistency with the WQMP. The proposed effluent limitations are contained in the approved WQMP.

The discharge from this permit action is not expected to have an effect on any federal endangered or threatened aquatic or aquatic-dependent species or proposed species or their critical habitat. This determination is based on the United States Fish and Wildlife Service's (USFWS's) biological opinion on the State of Texas authorization of the TPDES (September 14, 1998; October 21, 1998, update). To make this determination for TPDES permits, TCEQ and EPA only considered aquatic or aquatic-dependent species occurring in watersheds of critical concern or high priority as listed in Appendix A of the USFWS biological opinion. The determination is subject to reevaluation due to subsequent updates or amendments to the biological opinion. The permit does not require EPA review with respect to the presence of endangered or threatened species.

Segments Nos. 0212 and 1231 are not currently listed on the State's inventory of impaired and threatened waters, the 2022 Clean Water Act Section 303(d). However, Little Wichita River (0212A) is listed for bacteria in water from the headwater of Lake Arrowhead at normal pool elevation of 926 feet upstream to the confluence of the North and South Forks of Little Wichita River north of Archer City (AU 0212A_01). This facility is designed to provide adequate disinfection and, when operated properly, should not add to the bacterial impairment of the segment. In addition, in order to ensure that the proposed discharge meets the stream bacterial standard, an effluent limitation of 126 colony-forming units (CFU) or most probable number (MPN) of *Escherichia coli* per 100 ml has been continued in the draft permit.

SUMMARY OF EFFLUENT DATA

The following is a summary of the applicant's effluent monitoring data for Outfall 001 for the period March 2022 through March 2024. The average of Daily Average value is computed by the averaging of all 30-day average values for the reporting period for each parameter: flow, five-day carbonaceous biochemical oxygen demand (CBOD₅), total suspended solids (TSS), and ammonia nitrogen (NH₃-N). The average of Daily Average value for *E. coli* in colony-forming units (CFU) or most probable number (MPN) per 100 ml is calculated via geometric mean. Outfall 002 is not active.

<u>Parameter</u>	<u>Average of Daily Average</u>
Flow, MGD	0.25
CBOD ₅ , mg/l	2.7
TSS, mg/l	9.2
NH ₃ -N, mg/l	1.1
<i>E. coli</i> , CFU or MPN per 100 ml	1

DRAFT PERMIT CONDITIONS

The draft permit authorizes a discharge of treated domestic wastewater at a volume not to exceed a daily average flow of 0.79 MGD.

The effluent limitations in the draft permit for Outfall 001, based on a 30-day average, are 10 mg/l CBOD₅, 15 mg/l TSS, 3.0 mg/l ammonia-nitrogen NH₃-N, 126 CFU or MPN of *E. coli* per 100 ml, and 4.0 mg/l minimum dissolved oxygen (DO). The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes based on peak flow.

The effluent limitations in the draft permit for Outfall 002, based on a 30-day average, are 7.0 mg/l CBOD₅, 15 mg/l TSS, 2.0 mg/l ammonia-nitrogen NH₃-N, 126 CFU or MPN of *E. coli* per 100 ml, and 5.0 mg/l minimum DO. The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes based on peak flow.

The facility does not appear to receive significant industrial wastewater contributions. Permit requirements for pretreatment are based on TPDES regulations contained in 30 TAC Chapter 305, which references 40 Code of Federal Regulations (CFR) Part 403, "General Pretreatment Regulations for Existing and New Sources of Pollution" [rev. *Federal Register*/ Vol. 70/ No. 198/ Friday, October 14, 2005/ Rules and Regulations, pages 60134-60798]. The draft permit

includes specific requirements that establish responsibilities of local government, industry, and the public to implement the standards to control pollutants which pass through or interfere with treatment processes in publicly owned treatment works or which may contaminate the sewage sludge. This permit has appropriate pretreatment language for a facility of this size and complexity.

The draft permit includes Sludge Provisions according to the requirements of 30 TAC Chapter 312, Sludge Use, Disposal, and Transportation. Sludge generated from the treatment facility is hauled by a registered transporter and disposed of at a TCEQ-permitted landfill, Buffalo Creek Landfill, Permit No. MSW 1571A, in Wichita County. The draft permit also authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

SUMMARY OF CHANGES FROM APPLICATION

The application requested a renewal with no changes. However, the limitations for CBOD₅ and NH₃-N at Outfall 002 were corrected to comply with 30 TAC §309.4 and team practice. It appears that the series of limitations for CBOD₅ at Outfall 001 and Outfall 002 were erroneously switched in the permit issued on May 16, 2014. The existing limits for 7-day average, daily maximum, and single grab CBOD₅ at Outfall 002 were updated from 15 mg/L, 25 mg/L, and 35 mg/L, respectively, to 12 mg/L, 22 mg/L, and 32 mg/L, respectively, which are the corresponding limits for a daily average limit of 7.0 mg/L. The 7-day average limit for NH₃-N was corrected from 6.0 mg/L in the existing permit to 5.0 mg/L as required in 30 TAC §309.4. The series of limitations for CBOD₅ at Outfall ~~001~~ cannot be corrected at this time, however, because to revise the 7-day average, daily maximum, and single grab limits from 12 mg/L, 22 mg/L, and 32 mg/L, respectively, to 15 mg/L, 25 mg/L, and 35 mg/L, respectively, would be a relaxation and would require a major amendment.

SUMMARY OF CHANGES FROM EXISTING PERMIT

The discharge route description for Outfall 001 was corrected to include the unnamed ditch prior to Salt Creek. The omission of the unnamed ditch in the existing permit was an oversight. The outfall location has not moved.

For Publicly Owned Treatment Works (POTWs), effective December 21, 2025, the permittee must submit the written report for unauthorized discharges and unanticipated bypasses that exceed any effluent limit in the permit using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver.

The draft permit includes all updates based on the 30 TAC Chapter 312 rule change effective April 23, 2020.

Existing Other Requirement No. 3 has been updated; the permittee shall submit proof of legal restrictions.

Existing Other Requirement No. 8 has been removed because it was redundant with Other Requirement No. 7. Existing Other Requirement No. 7 has been corrected to remove references to "plant startup" as the facility is already active.

BASIS FOR DRAFT PERMIT

The following items were considered in developing the draft permit:

1. Application received on April 1, 2024, and additional information received on July 25, 2024.
2. TPDES Permit No. WQ0010050001 issued on October 7, 2019.
3. The effluent limitations and conditions in the draft permit comply with EPA-approved portions of the 2018 Texas Surface Water Quality Standards (TSWQS), 30 TAC §§ 307.1 - 307.10, effective March 1, 2018; 2014 TSWQS, effective March 6, 2014; 2010 TSWQS, effective July 22, 2010; and 2000 TSWQS, effective July 26, 2000.
4. The effluent limitations in the draft permit meet the requirements for secondary treatment and the requirements for disinfection according to 30 TAC Chapter 309, Subchapter A: Effluent Limitations.
5. Interoffice Memoranda from the Water Quality Assessment Section of the TCEQ Water Quality Division. Interoffice Memorandum from the Pretreatment Team of the TCEQ Water Quality Division.
6. Consistency with the Coastal Management Plan: The facility is not located in the Coastal Management Program boundary.
7. *Procedures to Implement the Texas Surface Water Quality Standards* (IP), Texas Commission on Environmental Quality, June 2010, as approved by EPA, and the IP, January 2003, for portions of the 2010 IP not approved by EPA.
8. Texas 2022 Clean Water Act Section 303(d) List, Texas Commission on Environmental Quality, June 1, 2022; approved by the U.S. Environmental Protection Agency on July 7, 2022.
9. Texas Natural Resource Conservation Commission, Guidance Document for Establishing Monitoring Frequencies for Domestic and Industrial Wastewater Discharge Permits, Document No. 98-001.000-OWR-WQ, May 1998.

PROCEDURES FOR FINAL DECISION

When an application is declared administratively complete, the Chief Clerk sends a letter to the applicant advising the applicant to publish the Notice of Receipt of Application and Intent to Obtain Permit in the newspaper. In addition, the Chief Clerk instructs the applicant to place a copy of the application in a public place for review and copying in the county where the facility is or will be located. This application will be in a public place throughout the comment period. The Chief Clerk also mails this notice to any interested persons and, if required, to landowners identified in the permit application. This notice informs the public about the application, and provides that an interested person may file comments on the application or request a contested case hearing or a public meeting.

Once a draft permit is completed, it is sent, along with the Executive Director's preliminary decision, as contained in the technical summary or fact sheet, to the Chief Clerk. At that time,

City of Olney

TPDES Permit No. WQ0010050001

Statement of Basis/Technical Summary and Executive Director's Preliminary Decision

the Notice of Application and Preliminary Decision will be mailed to the same people and published in the same newspaper as the prior notice. This notice sets a deadline for making public comments. The applicant must place a copy of the Executive Director's preliminary decision and draft permit in the public place with the application.

Any interested person may request a public meeting on the application until the deadline for filing public comments. A public meeting is intended for the taking of public comment, and is not a contested case proceeding.

After the public comment deadline, the Executive Director prepares a response to all significant public comments on the application or the draft permit raised during the public comment period. The Chief Clerk then mails the Executive Director's response to comments and final decision to people who have filed comments, requested a contested case hearing, or requested to be on the mailing list. This notice provides that if a person is not satisfied with the Executive Director's response and decision, they can request a contested case hearing or file a request to reconsider the Executive Director's decision within 30 days after the notice is mailed.

The Executive Director will issue the permit unless a written hearing request or request for reconsideration is filed within 30 days after the Executive Director's response to comments and final decision is mailed. If a hearing request or request for reconsideration is filed, the Executive Director will not issue the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting. If a contested case hearing is held, it will be a legal proceeding similar to a civil trial in state district court.

If the Executive Director calls a public meeting or the Commission grants a contested case hearing as described above, the Commission will give notice of the date, time, and place of the meeting or hearing. If a hearing request or request for reconsideration is made, the Commission will consider all public comments in making its decision and shall either adopt the Executive Director's response to public comments or prepare its own response.

For additional information about this application, contact Sarah Johnson at (512) 239-4649.

Sarah Johnson

Sarah Johnson
Municipal Permits Team
Wastewater Permitting Section (MC 148)

July 25, 2024

Date

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

2024 Domestic
Wastewater Permit
Application
for the
City of Olney

Permit Number
WQ0010050-001
Original



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
DOMESTIC WASTEWATER PERMIT APPLICATION
CHECKLIST

Complete and submit this checklist with the application.

APPLICANT: City of Olney

PERMIT NUMBER: WQ0010050-001

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Original USGS Map	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Administrative Report 1.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Affected Landowners Map	<input type="checkbox"/>	<input checked="" type="checkbox"/>
SPIF	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Landowner Disk or Labels	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Core Data Form	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Buffer Zone Map	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Public Involvement Plan Form	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Flow Diagram	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Technical Report 1.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site Drawing	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Technical Report 1.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Original Photographs	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 2.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Design Calculations	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 2.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Solids Management Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 3.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Water Balance	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 3.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 3.2	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 3.3	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 4.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 5.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 6.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Worksheet 7.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			

For TCEQ Use Only

Segment Number _____ County _____
Expiration Date _____ Region _____
Permit Number _____



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

**APPLICATION FOR A DOMESTIC WASTEWATER PERMIT
ADMINISTRATIVE REPORT 1.0**

If you have questions about completing this form please contact the Applications Review and Processing Team at 512-239-4671.

Section 1. Application Fees (Instructions Page 29)

Indicate the amount submitted for the application fee (check only one).

Flow	New/Major Amendment	Renewal
<0.05 MGD	\$350.00 <input type="checkbox"/>	\$315.00 <input type="checkbox"/>
≥0.05 but <0.10 MGD	\$550.00 <input type="checkbox"/>	\$515.00 <input type="checkbox"/>
≥0.10 but <0.25 MGD	\$850.00 <input type="checkbox"/>	\$815.00 <input type="checkbox"/>
≥0.25 but <0.50 MGD	\$1,250.00 <input type="checkbox"/>	\$1,215.00 <input type="checkbox"/>
≥0.50 but <1.0 MGD	\$1,650.00 <input type="checkbox"/>	\$1,615.00 <input checked="" type="checkbox"/>
≥1.0 MGD	\$2,050.00 <input type="checkbox"/>	\$2,015.00 <input type="checkbox"/>

Minor Amendment (for any flow) \$150.00 ☐

Payment Information:

Mailed Check/Money Order Number: 54659
Check/Money Order Amount: 1,615.00
Name Printed on Check: City of Olney Operating Account
EPAY Voucher Number: N/A
Copy of Payment Voucher enclosed? Yes ☐

Section 2. Type of Application (Instructions Page 29)

- | | |
|---|---|
| <input type="checkbox"/> New TPDES | <input type="checkbox"/> New TLAP |
| <input type="checkbox"/> Major Amendment <u>with</u> Renewal | <input type="checkbox"/> Minor Amendment <u>with</u> Renewal |
| <input type="checkbox"/> Major Amendment <u>without</u> Renewal | <input type="checkbox"/> Minor Amendment <u>without</u> Renewal |
| <input checked="" type="checkbox"/> Renewal without changes | <input type="checkbox"/> Minor Modification of permit |

For amendments or modifications, describe the proposed changes: [Click here to enter text.](#)

For existing permits:

Permit Number: WQ0010050001

EPA I.D. (TPDES only): TX0024261

Expiration Date: 10/7/24

Section 3. Facility Owner (Applicant) and Co-Applclicant Information (Instructions Page 29)

A. The owner of the facility must apply for the permit.

What is the Legal Name of the entity (applicant) applying for this permit?

City of Olney

(The legal name must be spelled exactly as filed with the Texas Secretary of State, County, or in the legal documents forming the entity.)

If the applicant is currently a customer with the TCEQ, what is the Customer Number (CN)? You may search for your CN on the TCEQ website at <http://www15.tceq.texas.gov/crpub/>

CN: 600652309

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in 30 TAC § 305.44.

Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Rue Rogers

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Mayor

B. Co-applclicant information. Complete this section only if another person or entity is required to apply as a co-permittee.

What is the Legal Name of the co-applclicant applying for this permit?

Click here to enter text.

(The legal name must be spelled exactly as filed with the TX SOS, with the County, or in the legal documents forming the entity.)

If the co-applclicant is currently a customer with the TCEQ, what is the Customer Number (CN)? You may search for your CN on the TCEQ website at:
<http://www15.tceq.texas.gov/crpub/>

CN: Click here to enter text.

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in 30 TAC § 305.44.

Prefix (Mr., Ms., Miss): Click here to enter text.

First and Last Name: Click here to enter text.

Credential (P.E, P.G., Ph.D., etc.): Click here to enter text.

Title: Click here to enter text.

Provide a brief description of the need for a co-permittee: N/A

C. Core Data Form

Complete the Core Data Form for each customer and include as an attachment. If the customer type selected on the Core Data Form is **Individual**, complete **Attachment 1** of Administrative Report 1.0.

Attachment: A

Section 4. Application Contact Information (Instructions Page 30)

This is the person(s) TCEQ will contact if additional information is needed about this application. Provide a contact for administrative questions and technical questions.

A. Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Public Works Director

Organization Name: City of Olney

Mailing Address: P.O. Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: [Click here to enter text.](#) Fax No.: [Click here to enter text.](#)

E-mail Address: olneygov@cityofolneytx.com

Check one or both: ☒ Administrative Contact ☐ Technical Contact

B. Prefix (Mr., Ms., Miss): Ms.

First and Last Name: Jessica Parks

Credential (P.E, P.G., Ph.D., etc.): P.E.

Title: Professional Engineer

Organization Name: Corlett, Probst & Boyd PLLC

Mailing Address: 4605 Old Jacksboro Hwy

City, State, Zip Code: Wichita Falls, TX 76302

Phone No.: 940-723-1455 Ext.: [Click here to enter text.](#) Fax No.: [Click here to enter text.](#)

E-mail Address: jessica@cpbwf.com

Check one or both: ☐ Administrative Contact ☒ Technical Contact

Section 5. Permit Contact Information (Instructions Page 30)

Provide two names of individuals that can be contacted throughout the permit term.

A. Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Public Works Director

Organization Name: City of Olney

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: [Click here to enter text.](#) Fax No.: [Click here to enter text.](#)

E-mail Address: olneygov@cityofolneytx.com

B. Prefix (Mr., Ms., Miss): Ms.

First and Last Name: Jessica Parks

Credential (P.E, P.G., Ph.D., etc.): P.E.

Title: Professional Engineer

Organization Name: Corlett, Probst & Boyd PLLC

Mailing Address: 4605 Old Jacksboro Hwy

City, State, Zip Code: Wichita Falls, TX 76302

Phone No.: 940-723-1455 Ext.: [Click here to enter text.](#) Fax No.: [Click here to enter text.](#)

E-mail Address: jessica@cpbwf.com

Section 6. Billing Information (Instructions Page 30)

The permittee is responsible for paying the annual fee. The annual fee will be assessed to permits ***in effect on September 1 of each year.*** The TCEQ will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (using form TCEQ-20029).

Prefix (Mr., Ms., Miss): Ms

First and Last Name: Tammy Hourigan

Credential (P.E, P.G., Ph.D., etc.): [Click here to enter text.](#)

Title: City Secretary

Organization Name: City of Olney

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: [Click here to enter text.](#) Fax No.: [Click here to enter text.](#)

E-mail Address: olneygov@cityofolneytx.com

Section 7. DMR/MER Contact Information (Instructions Page 31)

Provide the name and complete mailing address of the person delegated to receive and submit Discharge Monitoring Reports (EPA 3320-1) or maintain Monthly Effluent Reports.

Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Public Works Director

Organization Name: City of Olney

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: Click here to enter text Fax No.: Click here to enter text

E-mail Address: olneygov@cityofolneytx.com

DMR data is required to be submitted electronically. Create an account at:

<https://www.tceq.texas.gov/permitting/netdmr/netdmr.html>.

Section 8. Public Notice Information (Instructions Page 31)

A. Individual Publishing the Notices

Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Public Works Director

Organization Name: City of Olney

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: Click here to enter text Fax No.: Click here to enter text

E-mail Address: olneygov@cityofolneytx.com

B. Method for Receiving Notice of Receipt and Intent to Obtain a Water Quality Permit Package

Indicate by a check mark the preferred method for receiving the first notice and instructions:

☐ E-mail Address

☐ Fax

☒ Regular Mail

C. Contact person to be listed in the Notices

Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): N/A

Title: Public Works Director

Organization Name: City of Olney

Phone No.: 940-276-2011 Ext.: [Click here to enter text.](#)

E-mail: olneygov@cityofolneytx.com

D. Public Viewing Information

If the facility or outfall is located in more than one county, a public viewing place for each county must be provided.

Public building name: Olney City Hall

Location within the building: N/A

Physical Address of Building: 201 E. Main Street

City: Olney

County: Young

Contact Name: Michael Jacoba

Phone No.: 940-276-2011 Ext.: [Click here to enter text.](#)

E. Bilingual Notice Requirements:

This information **is required** for **new, major amendment, minor amendment or minor modification, and renewal applications.**

This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.

Please call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine whether an alternative language notices are required.

1. Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?

☐ Yes ☒ No

If **no**, publication of an alternative language notice is not required; **skip to** Section 9 below.

2. Are the students who attend either the elementary school or the middle school enrolled in a bilingual education program at that school?

☐ Yes ☒ No

3. Do the students at these schools attend a bilingual education program at another location?

☐ Yes ☒ No

4. Would the school be required to provide a bilingual education program but the school has waived out of this requirement under 19 TAC §89.1205(g)?
☐ Yes ☒ No
5. If the answer is yes to question 1, 2, 3, or 4, public notices in an alternative language are required. Which language is required by the bilingual program? N/A

F. Public Involvement Plan Form

Complete the Public Involvement Plan Form (TCEQ Form 20960) for each application for a **new permit or major amendment to a permit** and include as an attachment.

Attachment: N/A

Section 9. Regulated Entity and Permitted Site Information (Instructions Page 33)

- A. If the site is currently regulated by TCEQ, provide the Regulated Entity Number (RN) issued to this site. RN101610335

Search the TCEQ's Central Registry at <http://www15.tceq.texas.gov/crpub/> to determine if the site is currently regulated by TCEQ.

- B. Name of project or site (the name known by the community where located):

City of Olney Wastewater Treatment Plant

- C. Owner of treatment facility: City of Olney

Ownership of Facility: ☒ Public ☐ Private ☐ Both ☐ Federal

- D. Owner of land where treatment facility is or will be:

Prefix (Mr., Ms., Miss): Click here to enter text

First and Last Name: City of Olney

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011

E-mail Address: olneygov@cityofolneytx.com

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: N/A

- E. Owner of effluent disposal site:

Prefix (Mr., Ms., Miss): N/A

First and Last Name: N/A

Mailing Address: N/A

City, State, Zip Code: N/A

Phone No.: N/A

E-mail Address: N/A

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: N/A

- F. Owner of sewage sludge disposal site (if authorization is requested for sludge disposal on property owned or controlled by the applicant):

Prefix (Mr., Ms., Miss): N/A

First and Last Name: N/A

Mailing Address: N/A

City, State, Zip Code: N/A

Phone No.: N/A

E-mail Address: N/A

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: N/A

Section 10. TPDES Discharge Information (Instructions Page 34)

- A. Is the wastewater treatment facility location in the existing permit accurate?

☒ Yes ☐ No

If **no**, or a new permit application, please give an accurate description:

[Click here to enter text.](#)

- B. Are the point(s) of discharge and the discharge route(s) in the existing permit correct?

☒ Yes ☐ No

If **no**, or a new or amendment permit application, provide an accurate description of the point of discharge and the discharge route to the nearest classified segment as defined in 30 TAC Chapter 307:

[Click here to enter text.](#)

City nearest the outfall(s): Olney

County in which the outfalls(s) is/are located: Young

Outfall Latitude: 33d21'37"

Longitude: 98d44'44"

- C. Is or will the treated wastewater discharge to a city, county, or state highway right-of-way, or a flood control district drainage ditch?

☐ Yes ☒ No

If **yes**, indicate by a check mark if:

☐ Authorization granted ☐ Authorization pending

For **new and amendment** applications, provide copies of letters that show proof of contact and the approval letter upon receipt.

Attachment: N/A

- D. For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge.

N/A

Section 11. TLAP Disposal Information (Instructions Page 36)

- A. For TLAPs, is the location of the effluent disposal site in the existing permit accurate?

☐ Yes ☐ No

If **no, or a new or amendment permit application**, provide an accurate description of the disposal site location:

N/A

- B. City nearest the disposal site: N/A

- C. County in which the disposal site is located: N/A

- D. Disposal Site Latitude: N/A Longitude: N/A

- E. For TLAPs, describe the routing of effluent from the treatment facility to the disposal site:

N/A

- F. For TLAPs, please identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained:

N/A

Section 12. Miscellaneous Information (Instructions Page 37)

- A. Is the facility located on or does the treated effluent cross American Indian Land?

☐ Yes ☒ No

B. If the existing permit contains an onsite sludge disposal authorization, is the location of the sewage sludge disposal site in the existing permit accurate?

☐ Yes ☐ No ☒ Not Applicable

If No, or if a new onsite sludge disposal authorization is being requested in this permit application, provide an accurate location description of the sewage sludge disposal site.

[Click here to enter text.](#)

C. Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?

☐ Yes ☐ No

If yes, list each person formerly employed by the TCEQ who represented your company and was paid for service regarding the application:

[Click here to enter text.](#)

D. Do you owe any fees to the TCEQ?

☐ Yes ☒ No

If yes, provide the following information:

Account number: [Click here to enter text.](#)

Amount past due: [Click here to enter text.](#)

E. Do you owe any penalties to the TCEQ?

☐ Yes ☒ No

If yes, please provide the following information:

Enforcement order number: [Click here to enter text.](#)

Amount past due: [Click here to enter text.](#)

Section 13. Attachments (Instructions Page 38)

Indicate which attachments are included with the Administrative Report. Check all that apply:

- ☐ Lease agreement or deed recorded easement, if the land where the treatment facility is located or the effluent disposal site are not owned by the applicant or co-applicant.
- ☒ Original full-size USGS Topographic Map with the following information:
 - Applicant's property boundary

- Treatment facility boundary
 - Labeled point of discharge for each discharge point (TPDES only)
 - Highlighted discharge route for each discharge point (TPDES only)
 - Onsite sewage sludge disposal site (if applicable)
 - Effluent disposal site boundaries (TLAP only)
 - New and future construction (if applicable)
 - 1 mile radius information
 - 3 miles downstream information (TPDES only)
 - All ponds.
- ☐ Attachment 1 for Individuals as co-applicants
- ☐ Other Attachments. Please specify: [Click here to enter text.](#)

Section 14. Signature Page (Instructions Page 39)

If co-applicants are necessary, each entity must submit an original, separate signature page.

Permit Number: WQ0010050-001

Applicant: City of Olney

Certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

I further certify that I am authorized under 30 Texas Administrative Code § 305.44 to sign and submit this document, and can provide documentation in proof of such authorization upon request.

Signatory name (typed or printed): Rue Rogers


Signatory title: Mayor

Signature: Rue Rogers Date: 3-18-24
(Use blue ink)

Subscribed and Sworn to before me by the said Rue Rogers
on this 18th day of March, 2024.
My commission expires on the 11th day of April, 2026.

Tamara G. Hourigan
Notary Public

Young
County, Texas



Section 15. Plain Language Summary (Instructions Page 40)

If you are subject to the alternative language notice requirements in [30 Texas Administrative Code §39.426](#), **you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package.** For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS

DOMESTIC WASTEWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 Texas Administrative Code Chapter 39. The information provided in this summary may change during the technical review of the application and are not federal enforceable representations of the permit application.

1. Enter applicant's name here. (2. Enter Customer Number here (i.e., CN6#####).) 3. Choose from the drop-down menu. 4. Enter name of facility here. 5. Enter Regulated Entity Number here (i.e., RN1#####). 6. Choose from the drop-down menu. 7. Enter facility description here.. The facility 8. Choose from the drop-down menu. located 9. Enter location here. , in 10. Enter city name here., 11. Enter county name here. County, Texas 12. Enter zip code here..

13. Enter summary of application request here. <<For TLAP applications include the following sentence, otherwise delete:>> This permit will not authorize a discharge of pollutants into water in the state.

Discharges from the facility are expected to contain 14. List all expected pollutants here..15. Enter types of wastewater discharged here. 16. Choose from the drop-down menu. treated by 17. Enter a description of wastewater treatment used at the facility here..

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS TPDES o TLAP

AGUAS RESIDUALES DOMÉSTICAS

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no son representaciones federales exigibles de la solicitud de permiso.

1. Introduzca el nombre del solicitante aquí. (2. Introduzca el número de cliente aquí (es decir, CN6 #####).) 3. Elija del menú desplegable. 4. Introduzca el nombre de la instalación aquí. 5. Introduzca el número de entidad regulada aquí (es decir, RN1 #####). 6. Elija del menú desplegable. 7. Introduzca la descripción de la instalación aquí. . La instalación 8. Elija del menú desplegable. ubicado 9. Introduzca la ubicación aquí. , en 10. Introduzca el nombre de la ciudad aquí. , Condado de 11. Introduzca el nombre del condado aquí. , Texas 12. Introduzca el código postal aquí. . 13. Introduzca el resumen de la solicitud de solicitud aquí. <<Para las aplicaciones de TLAP incluya la siguiente oración, de lo contrario, elimine:>> Este permiso no autorizará una descarga de contaminantes en el agua en el estado.

Se espera que las descargas de la instalación contengan 14. Liste todos los contaminantes esperados aquí. . 15. Introduzca los tipos de aguas residuales descargadas aquí. 16. Elija del menú desplegable. tratado por 17. Introduzca una descripción del tratamiento de aguas residuales utilizado en la instalación aquí.

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

FOR AGENCIES REVIEWING DOMESTIC TPDES WASTEWATER PERMIT APPLICATIONS

TCEQ USE ONLY:

Application type: ____Renewal ____Major Amendment ____Minor Amendment ____New

County: _____ Segment Number: _____

Admin Complete Date: _____

Agency Receiving SPIF:

____ Texas Historical Commission

____ U.S. Fish and Wildlife

____ Texas Parks and Wildlife Department

____ U.S. Army Corps of Engineers

This form applies to TPDES permit applications only. (Instructions, Page 53)

The SPIF must be completed as a separate document. The TCEQ will mail a copy of the SPIF to each agency as required by the TCEQ agreement with EPA. If any of the items are not completely addressed or further information is needed, you will be contacted to provide the information before the permit is issued. Each item must be completely addressed.

Do not refer to a response of any item in the permit application form. Each attachment must be provided with this form separately from the administrative report of the application. The application will not be declared administratively complete without this form being completed in its entirety including all attachments.

The following applies to all applications:

1. Permittee: City of Olney

Permit No. WQ00 10050-001

EPA ID No. TX 0024261

Address of the project (or a location description that includes street/highway, city/vicinity, and county):

1. Located approximately 0.25 miles east of SH 79 and 0.8 miles south of US 114

2. 1,500 ft southeast of the intersection of Spring Creek Rd and HWY 79 in Young County

Provide the name, address, phone and fax number of an individual that can be contacted to answer specific questions about the property.

Prefix (Mr., Ms., Miss): Mr.

First and Last Name: Michael Jacoba

Credential (P.E, P.G., Ph.D., etc.): Click here to enter text.

Title: Public Works Director

Mailing Address: PO Box 546

City, State, Zip Code: Olney, TX 76374

Phone No.: 940-276-2011 Ext.: Click here to enter text. Fax No.: Click here to enter text.

E-mail Address: olneygov@cityofolneytx.com

2. List the county in which the facility is located: Young
3. If the property is publicly owned and the owner is different than the permittee/applicant, please list the owner of the property.

N/A

4. Provide a description of the effluent discharge route. The discharge route must follow the flow of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.

1. Salt Creek; thence to Lake Graham in Segment No. 1231 of the Brazos River Basin
2. Olney Wastewater treatment plant; thence to Lake Olney in the Red River Basin; thence to Mesquite Creek; thence to South Fork Little Wichita River; thence to Little Wichita River; thence to Lake Arrowhead in Segment 0212 of the Red River Basin.

5. Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).

Provide original photographs of any structures 50 years or older on the property.

Does your project involve any of the following? Check all that apply.

- ☐ Proposed access roads, utility lines, construction easements
- ☐ Visual effects that could damage or detract from a historic property's integrity
- ☐ Vibration effects during construction or as a result of project design
- ☐ Additional phases of development that are planned for the future
- ☐ Sealing caves, fractures, sinkholes, other karst features

☐ Disturbance of vegetation or wetlands

6. List proposed construction impact (surface acres to be impacted, depth of excavation, sealing of caves, or other karst features):

N/A

7. Describe existing disturbances, vegetation, and land use:

Overgrown creek adjacent to development and agricultural lands


THE FOLLOWING ITEMS APPLY ONLY TO APPLICATIONS FOR NEW TPDES PERMITS AND MAJOR AMENDMENTS TO TPDES PERMITS

8. List construction dates of all buildings and structures on the property:

N/A

9. Provide a brief history of the property, and name of the architect/builder, if known.

N/A



Produced by the United States Geological Survey

Produced by the United States Geological Survey
National Wetlands Inventory
 North Carolina Department of Environment and Natural Resources
 Wetland Geospatial Systems of Data (WGSND) - Projection and
 UTM zone grid-reference Transverse Mercator, Zone 18S
 This map is not a legal document. Boundaries are generalized for this map scale. Private lands without government reservations may not be shown. Obtain permission before entering private lands.

Strategy.....	NAP: Synthesis
Reactor.....	U.S. Census Bureau
Hydrography.....	National Hydrography Data
Contours.....	Digital Elevation Model
Boundaries.....	Multiple sources; see metadata

Wetlands.....	FWS habitat	Wetlands.....	Invasive
---------------	-------------	---------------	----------

0+0
2500 S

4732
78 M.L.S.

SITE GRID AND 2019 MAGNETIC NORTH
DECLINATION AT CENTER OF EMBEY

U.S. National Grid
1307000 - m. Negative 15
AUG
Field Notes/Geological Notes

SCALE 1:24 000

1 0.5 0 KILOMETERS 1 2
1000 500 0 METERS 1000 2000

1 0.5 0 MILES
0 1000 2000 3000 4000 5000 6000 7000 8000 9000 10000

CONTOUR INTERVAL 10 FEET
NORTH AMERICAN VERTICAL DATUM OF 1982

This map was produced to conform with the
National Geospatial Program US Topic Product Standard



Tule, Texas

1	2	3
4		5
6	7	8

1. Marginal
2. Large Olney
3. Bobcat, DK
4. Pudget
5. True
6. Profit Cr.
7. Profit
8. New system


ROAD CLASSIFICATION


Expressway	Local Connector
Secondary Thru	Local Road
Right	Arterial

● Interstate Route □ US Route ○ State Route


OLNEY, TX
2022








OLNEY, TX
USGS MAP
SCALE: 1:24,000




**CITY OF OLNEY
WASTEWATER PLANT
FLOW DIAGRAM**
SCALE: 1" = 50'


S:\JLP\2024 PROJECTS\24-0093 OLNEY WW DISCHARGE PERMIT\CAD DRAWINGS\32729 DISCHARGE MAP.DWG Site Drawing Stream P-3/8/2024 4:52 PM S-4/1/2019 4:39 PM JESSICA PARKS



CORLETT, PROBST & BOYD, P.L.L.C.
Engineers and Surveyors
4605 Old Jacksboro Highway
Wichita Falls, Texas, 76302
(940) 723-1455

CITY OF OLNEY, TEXAS
SITE DRAWING







TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input checked="" type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 600652309		RN 101610335

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)							
<input type="checkbox"/> New Customer <input checked="" type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership									
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)									
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>									
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John) <i>If new Customer, enter previous Customer below:</i>									
			N/A						
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number (if applicable) 078538840						
11. Type of Customer:		Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited							
<input type="checkbox"/> Corporation		<input type="checkbox"/> Individual							
Government: <input checked="" type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other		<input type="checkbox"/> Sole Proprietorship <input type="checkbox"/> Other:							
12. Number of Employees		13. Independently Owned and Operated?							
<input type="checkbox"/> 0-20 <input checked="" type="checkbox"/> 21-100 <input type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following									
<input type="checkbox"/> Owner <input type="checkbox"/> Operator <input checked="" type="checkbox"/> Owner & Operator <input type="checkbox"/> Other:									
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant									
15. Mailing Address:	PO Box 546								
	City	Olney	State	TX	ZIP	76374	ZIP + 4		
16. Country Mailing Information (if outside USA)					17. E-Mail Address (if applicable)				
N/A					N/A				
18. Telephone Number			19. Extension or Code		20. Fax Number (if applicable)				

SECTION III: Regulated Entity Information

21. General Regulated Entity Information (If "New Regulated Entity" is selected, a new permit application is also required.)

☐ New Regulated Entity ☐ Update to Regulated Entity Name ☒ Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

City of Olney Wastewater Treatment Plant

23. Street Address of the Regulated Entity:

N/A

(No PO Boxes)

City

Olney

State

TX

ZIP

76374

ZIP + 4

24. County

Young

If no Street Address is provided, fields 25-28 are required.

25. Description to Physical Location:

1,500 ft southeast of the intersection of Spring Creek Rd and HWY 79 in Young County

26. Nearest City

State

Nearest ZIP Code

Olney

TX

76374

Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).

27. Latitude (N) In Decimal:
28. Longitude (W) In Decimal:

Degrees

Minutes

Seconds

Degrees

Minutes

Seconds

33

21

37

98

44

41

29. Primary SIC Code
30. Secondary SIC Code
31. Primary NAICS Code
32. Secondary NAICS Code

(4 digits)

(4 digits)

(5 or 6 digits)

(5 or 6 digits)

4952

33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)

34. Mailing

PC Box 546

Address:

City

Olney

State

TX

ZIP

76374

ZIP + 4

35. E-Mail Address:

olneygov@cityofolneytx.com

36. Telephone Number
37. Extension or Code
38. Fax Number (if applicable)

(940) 276-2011

() -

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:

SECTION IV: Preparer Information

40. Name:	Corlett, Probst & Boyd PLLC		41. Title:	Engineers
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address	
(940) 723-1455		() -	jessica@cpbwf.com	

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	Corlett, Probst & Boyd PLLC	Job Title:	Professional Engineer
Name (In Print):	Jessica Parks	Phone:	(940) 723- 1455
Signature:		Date:	3-14-24



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
DOMESTIC WASTEWATER PERMIT APPLICATION

DOMESTIC TECHNICAL REPORT 1.0

The Following Is Required For All Applications
Renewal, New, And Amendment

Section 1. Permitted or Proposed Flows (Instructions Page 51)

A. Existing/Interim I Phase

Design Flow (MGD): 0.79

2-Hr Peak Flow (MGD): 2.37

Estimated construction start date: N/A

Estimated waste disposal start date: N/A

B. Interim II Phase

Design Flow (MGD): 0.79

2-Hr Peak Flow (MGD): 2.37

Estimated construction start date: N/A

Estimated waste disposal start date: N/A

C. Final Phase

Design Flow (MGD): 0.79

2-Hr Peak Flow (MGD): 2.37

Estimated construction start date: N/A

Estimated waste disposal start date: N/A

D. Current operating phase: Existing

Provide the startup date of the facility: circa 1970

Section 2. Treatment Process (Instructions Page 51)

A. Treatment process description

Provide a detailed description of the treatment process. **Include the type of**

treatment plant, mode of operation, and all treatment units. Start with the plant's head works and finish with the point of discharge. Include all sludge processing and drying units. **If more than one phase exists or is proposed in the permit, a description of *each phase* must be provided.** Process description:

Lift station pumps to a mechanical bar screen with manual backup bar screen. Flow is treated in an oxidation ditch equipped with two rotors. Flow from oxidation ditch is clarified in two clarifiers and chlorinated in a chlorine contact basin. Diffused air is added in reaeration basin for oxygenation.

Port or pipe diameter at the discharge point, in inches: 16

B. Treatment Units

In Table 1.0(1), provide the treatment unit type, the number of units, and dimensions (length, width, depth) **of each treatment unit, accounting for *all* phases of operation.**

Table 1.0(1) – Treatment Units

Treatment Unit Type	Number of Units	Dimensions (L x W x D)
Oxidation Ditch	1	240' x 95'
Clarifier	2	44' dia x 9'
Chlorine Contact Basin	1	32' x 24' x 8'
Reaeration Basin	1	25' x 11' x 14-3/4'

C. Process flow diagrams

Provide flow diagrams for the existing facilities and **each** proposed phase of construction.

Attachment: C

Section 3. Site Drawing (Instructions Page 52)

Provide a site drawing for the facility that shows the following:

- The boundaries of the treatment facility;
- The boundaries of the area served by the treatment facility;
- If land disposal of effluent, the boundaries of the disposal site and all storage/holding ponds; and
- If sludge disposal is authorized in the permit, the boundaries of the land application or disposal site.

Attachment: D

Provide the name and a description of the area served by the treatment facility.

City of Olney, TX

Section 4. Unbuilt Phases (Instructions Page 52)

Is the application for a renewal of a permit that contains an unbuilt phase or phases?

Yes ☐

No ☒

If yes, does the existing permit contain a phase that has not been constructed within five years of being authorized by the TCEQ?

Yes ☐

No ☐

If yes, provide a detailed discussion regarding the continued need for the unbuilt phase. Failure to provide sufficient justification may result in the Executive Director recommending denial of the unbuilt phase or phases.

N/A

Section 5. Closure Plans (Instructions Page 53)

Have any treatment units been taken out of service permanently, or will any units be taken out of service in the next five years?

Yes ☐ No ☒

If yes, was a closure plan submitted to the TCEQ?

Yes ☐ No ☐

If yes, provide a brief description of the closure and the date of plan approval.

N/A

Section 6. Permit Specific Requirements (Instructions Page 53)

For applicants with an existing permit, check the *Other Requirements* or *Special Provisions* of the permit.

A. Summary transmittal

Have plans and specifications been approved for the existing facilities and each proposed phase?

Yes ☒ No ☐

If yes, provide the date(s) of approval for each phase: not available

Provide information, including dates, on any actions taken to meet a requirement or provision pertaining to the submission of a summary transmittal letter. Provide a copy of an approval letter from the TCEQ, if applicable.

N/A

B. Buffer zones

Have the buffer zone requirements been met?

Yes ☒ No ☐

Provide information below, including dates, on any actions taken to meet the conditions of the buffer zone. If available, provide any new documentation relevant to maintaining the buffer zones.

The City of Olney has an existing easement with the owners of the property, Tower Extrusions, within 150 feet of the Wastewater Treatment Plant.

C. Other actions required by the current permit

Does the *Other Requirements* or *Special Provisions* section in the existing permit require submission of any other information or other required actions? Examples include Notification of Completion, progress reports, soil monitoring data, etc.

Yes ☐ No ☒

If **yes**, provide information below on the status of any actions taken to meet the conditions of an *Other Requirement* or *Special Provision*.

N/A

D. Grit and grease treatment

1. Acceptance of grit and grease waste

Does the facility have a grit and/or grease processing facility onsite that treats and decants or accepts transported loads of grit and grease waste that are discharged directly to the wastewater treatment plant prior to any treatment?

Yes ☐ No ☒

If **No**, stop here and continue with Subsection E. Stormwater Management.

2. Grit and grease processing

Describe below how the grit and grease waste is treated at the facility. In your description, include how and where the grit and grease is introduced to the treatment works and how it is separated or processed. Provide a flow diagram showing how grit and grease is processed at the facility.

N/A

3. Grit disposal

Does the facility have a Municipal Solid Waste (MSW) registration or permit for grit disposal?

Yes ☐ No ☐

If No, contact the TCEQ Municipal Solid Waste team at 512-239-0000. Note: A registration or permit is required for grit disposal. Grit shall not be combined with treatment plant sludge. See the instruction booklet for additional information on grit disposal requirements and restrictions.

Describe the method of grit disposal.

N/A

4. Grease and decanted liquid disposal

Note: A registration or permit is required for grease disposal. Grease shall not be combined with treatment plant sludge. For more information, contact the TCEQ Municipal Solid Waste team at 512-239-0000.

Describe how the decant and grease are treated and disposed of after grit separation.

N/A

E. Stormwater management

1. Applicability

Does the facility have a design flow of 1.0 MGD or greater in any phase?

Yes ☐ No ☒

Does the facility have an approved pretreatment program, under 40 CFR Part 403?

Yes ☐ No ☒

If no to both of the above, then skip to Subsection F, Other Wastes Received.

2. MSGP coverage

Is the stormwater runoff from the WWTP and dedicated lands for sewage disposal currently permitted under the TPDES Multi-Sector General Permit (MSGP), TXR050000?

Yes ☐ No ☐

If yes, please provide MSGP Authorization Number and skip to Subsection F, Other Wastes Received:

TXR05 [Click here to enter text.](#) or TXRNE [Click here to enter text.](#)

If no, do you intend to seek coverage under TXR050000?

Yes ☐ No ☐

3. Conditional exclusion

Alternatively, do you intend to apply for a conditional exclusion from permitting based TXR050000 (Multi Sector General Permit) Part II B.2 or TXR050000 (Multi Sector General Permit) Part V, Sector T 3(b)?

Yes ☐ No ☐

If yes, please explain below then proceed to Subsection F, Other Wastes Received:

N/A

4. Existing coverage in individual permit

Is your stormwater discharge currently permitted through this individual TPDES or TLAP permit?

Yes ☐ No ☐

If yes, provide a description of stormwater runoff management practices at the site that are authorized in the wastewater permit then skip to Subsection F, Other Wastes Received.

N/A

5. Zero stormwater discharge

Do you intend to have no discharge of stormwater via use of evaporation or other means?

Yes ☐ No ☐

If yes, explain below then skip to Subsection F. Other Wastes Received.

N/A

Note: If there is a potential to discharge any stormwater to surface water in the state as the result of any storm event, then permit coverage is required under the MSGP or an individual discharge permit. This requirement applies to all areas of facilities with treatment plants or systems that treat, store, recycle, or reclaim domestic sewage, wastewater or sewage sludge (including dedicated lands for sewage sludge disposal located within the onsite property boundaries) that meet the applicability criteria of above. You have the option of obtaining coverage under the MSGP for direct discharges, (recommended), or obtaining coverage under this individual permit.

6. Request for coverage in individual permit

Are you requesting coverage of stormwater discharges associated with your treatment plant under this individual permit?

Yes ☐ No ☐

If yes, provide a description of stormwater runoff management practices at the site for which you are requesting authorization in this individual wastewater permit and describe whether you intend to comingle this discharge with your treated effluent or discharge it via a separate dedicated stormwater outfall. Please also indicate if you intend to divert stormwater to the treatment plant headworks and indirectly discharge it to water in the state.

N/A

Note: Direct stormwater discharges to waters in the state authorized through this individual permit will require the development and implementation of a stormwater pollution prevention plan (SWPPP) and will be subject to additional monitoring and reporting requirements. Indirect discharges of stormwater via headworks recycling will require compliance with all individual permit requirements including 2-hour peak flow limitations. All stormwater discharge authorization requests will require additional information during the technical review of your application.

F. Discharges to the Lake Houston Watershed

Does the facility discharge in the Lake Houston watershed?

Yes ☐ No ☒

If yes, a Sewage Sludge Solids Management Plan is required. See Example 5 in the instructions.

G. Other wastes received including sludge from other WWTPs and septic waste

1. Acceptance of sludge from other WWTPs

Does the facility accept or will it accept sludge from other treatment plants at the facility site?

Yes ☐ No ☒

If yes, attach sewage sludge solids management plan. See Example 5 of the instructions.

In addition, provide the date that the plant started accepting sludge or is anticipated to start accepting sludge, an estimate of monthly sludge acceptance (gallons or millions of gallons), an estimate of the BOD₅ concentration of the sludge, and the design BOD₅ concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.

N/A

Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.

2. Acceptance of septic waste

Is the facility accepting or will it accept septic waste?

Yes ☐ No ☒

If yes, does the facility have a Type V processing unit?

Yes ☐ No ☒

If yes, does the unit have a Municipal Solid Waste permit?

Yes ☐ No ☒

If yes to any of the above, provide a the date that the plant started accepting septic waste, or is anticipated to start accepting septic waste, an estimate of monthly septic waste acceptance (gallons or millions of gallons), an estimate of the BOD₅ concentration of the septic waste, and the design BOD₅ concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.

N/A

Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.

3. Acceptance of other wastes (not including septic, grease, grit, or RCRA, CERCLA or as discharged by IUs listed in Worksheet 6)

Is the facility accepting or will it accept wastes that are not domestic in nature excluding the categories listed above?

Yes ☐ No ☐

If yes, provide the date that the plant started accepting the waste, an estimate how much waste is accepted on a monthly basis (gallons or millions of gallons), a description of the entities generating the waste, and any distinguishing chemical or other physical characteristic of the waste. Also note if this information has or has not changed since the last permit action.

N/A

Section 7. Pollutant Analysis of Treated Effluent (Instructions Page 58)

Is the facility in operation?

Yes ☒ No ☐

If **no**, this section is not applicable. Proceed to Section 8.

If **yes**, provide effluent analysis data for the listed pollutants. *Wastewater treatment facilities* complete Table 1.0(2). *Water treatment facilities* discharging filter backwash water, complete Table 1.0(3).

Note: The sample date must be within 1 year of application submission.

Table 1.0(2) - Pollutant Analysis for Wastewater Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
CBOD ₅ , mg/l	<2	<2	1	grab	3/14/24
Total Suspended Solids, mg/l	4.1	4.1	1	grab	3/14/2024
Ammonia Nitrogen, mg/l	.05	.05	1	grab	3/14/2024
Nitrate Nitrogen, mg/l	43.9	43.9	1	grab	3/14/2024
Total Kjeldahl Nitrogen, mg/l	<0.2	<0.2	1	grab	3/14/2024
Sulfate, mg/l	796	796	1	grab	3/14/2024
Chloride, mg/l	212	212	1	grab	3/14/2024
Total Phosphorus, mg/l	0.1925	0.1925	1	grab	3/14/2024
pH, standard units					
Dissolved Oxygen*, mg/l					
Chlorine Residual, mg/l					
<i>E.coli</i> (CFU/100ml) freshwater	<1	<1	1	grab	3/14/2024
Enterococci (CFU/100ml)					

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
saltwater					
Total Dissolved Solids, mg/l	1440	1440	1	grab	3/14/2024
Electrical Conductivity, μ mohs/cm, †	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
Oil & Grease, mg/l					
Alkalinity (CaCO ₃)*, mg/l	120	120	1	grab	3/14/2024

*TPDES permits only

†TLAP permits only

Table 1.0(3) - Pollutant Analysis for Water Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Total Suspended Solids, mg/l	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
Total Dissolved Solids, mg/l	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
pH, standard units	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
Fluoride, mg/l	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
Aluminum, mg/l	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>
Alkalinity (CaCO ₃), mg/l	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

Section 8. Facility Operator (Instructions Page 60)

Facility Operator Name: James Mayes

Facility Operator's License Classification and Level: Wastewater Treatment Operator C

Facility Operator's License Number: WW0061437

Section 9. Sewage Sludge Management and Disposal (Instructions

A. Sludge disposal method

Identify the current or anticipated sludge disposal method or methods from the following list. Check all that apply.

- ☒ Permitted landfill
- ☐ Permitted or Registered land application site for beneficial use
- ☐ Land application for beneficial use authorized in the wastewater permit
- ☐ Permitted sludge processing facility
- ☐ Marketing and distribution as authorized in the wastewater permit
- ☐ Composting as authorized in the wastewater permit
- ☐ Permitted surface disposal site (sludge monofill)
- ☐ Surface disposal site (sludge monofill) authorized in the wastewater permit
- ☐ Transported to another permitted wastewater treatment plant or permitted sludge processing facility. If you selected this method, a written statement or contractual agreement from the wastewater treatment plant or permitted sludge processing facility accepting the sludge must be included with this application.
- ☐ Other: [Click here to enter text](#)

B. Sludge disposal site

Disposal site name: Iowa Park Landfill

TCEQ permit or registration number: MSW-1571-A

County where disposal site is located: Wichita

C. Sludge transportation method

Method of transportation (truck, train, pipe, other): Truck

Name of the hauler: Waste Connections Lone Star Inc.

Hauler registration number: RN100213214

Sludge is transported as a:

Liquid ☐

semi-liquid ☐

semi-solid ☒

solid ☐

Section 10. Permit Authorization for Sewage Sludge Disposal (Instructions Page 60)

A. Beneficial use authorization

Does the existing permit include authorization for land application of sewage sludge for beneficial use?

Yes ☐ No ☒

If **yes**, are you requesting to continue this authorization to land apply sewage sludge for beneficial use?

Yes ☐ No ☒

If **yes**, is the completed **Application for Permit for Beneficial Land Use of Sewage Sludge (TCEQ Form No. 10451)** attached to this permit application (see the instructions for details)?

Yes ☐ No ☒

B. Sludge processing authorization

Does the existing permit include authorization for any of the following sludge processing, storage or disposal options?

Sludge Composting Yes ☐ No ☒

Marketing and Distribution of sludge Yes ☐ No ☒

Sludge Surface Disposal or Sludge Monofill Yes ☐ No ☒

Temporary storage in sludge lagoons Yes ☐ No ☒

If **yes** to any of the above sludge options and the applicant is requesting to continue this authorization, is the completed **Domestic Wastewater Permit Application: Sewage Sludge Technical Report (TCEQ Form No. 10056)** attached to this permit application?

Yes ☐ No ☒

Section 11. Sewage Sludge Lagoons (Instructions Page 61)

Does this facility include sewage sludge lagoons?

Yes ☐ No ☒

If **yes**, complete the remainder of this section. If **no**, proceed to Section 12.

A. Location information

The following maps are required to be submitted as part of the application. For each map, provide the Attachment Number.

- Original General Highway (County) Map:

Attachment: N/A

- USDA Natural Resources Conservation Service Soil Map:

Attachment: N/A

- Federal Emergency Management Map:

Attachment: N/A

- Site map:

Attachment: N/A

Discuss in a description if any of the following exist within the lagoon area.

Check all that apply.

- ☐ Overlap a designated 100-year frequency flood plain
- ☐ Soils with flooding classification
- ☐ Overlap an unstable area
- ☐ Wetlands
- ☐ Located less than 60 meters from a fault
- ☐ None of the above

Attachment: N/A

If a portion of the lagoon(s) is located within the 100-year frequency flood plain, provide the protective measures to be utilized including type and size of protective structures:

N/A

B. Temporary storage information

Provide the results for the pollutant screening of sludge lagoons. These results are in addition to pollutant results in Section 7 of Technical Report 1.0.

Nitrate Nitrogen, mg/kg: N/A

Total Kjeldahl Nitrogen, mg/kg: [Click here to enter text.](#)

Total Nitrogen (=nitrate nitrogen + TKN), mg/kg: [Click here to enter text.](#)

Phosphorus, mg/kg: [Click here to enter text.](#)

Potassium, mg/kg: [Click here to enter text.](#)

pH, standard units: [Click here to enter text.](#)

Ammonia Nitrogen mg/kg: [Click here to enter text.](#)

Arsenic: [Click here to enter text.](#)

Cadmium: [Click here to enter text.](#)

Chromium: [Click here to enter text.](#)

Copper: [Click here to enter text.](#)

Lead: [Click here to enter text.](#)

Mercury: [Click here to enter text.](#)

Molybdenum: [Click here to enter text.](#)

Nickel: [Click here to enter text.](#)

Selenium: [Click here to enter text.](#)

Zinc: [Click here to enter text.](#)

Total PCBs: [Click here to enter text.](#)

Provide the following information:

Volume and frequency of sludge to the lagoon(s): [Click here to enter text.](#)

Total dry tons stored in the lagoons(s) per 365-day period: [Click here to enter text.](#)

Total dry tons stored in the lagoons(s) over the life of the unit: [Click here to enter text.](#)

C. Liner information

Does the active/proposed sludge lagoon(s) have a liner with a maximum hydraulic conductivity of 1×10^{-7} cm/sec?

Yes ☐ No ☐

If yes, describe the liner below. Please note that a liner is required.

N/A

D. Site development plan

Provide a detailed description of the methods used to deposit sludge in the lagoon(s):

Backwash water is routed to a backwash lagoon and then to the settling basin. The decant is discharged into Lake Olney for recycle through the plant. Sludge is discharged into the settling basin four times per year.

Attach the following documents to the application.

- Plan view and cross-section of the sludge lagoon(s)
Attachment: N/A
- Copy of the closure plan
Attachment: N/A
- Copy of deed recordation for the site
Attachment: N/A
- Size of the sludge lagoon(s) in surface acres and capacity in cubic feet and gallons
Attachment: N/A
- Description of the method of controlling infiltration of groundwater and surface water from entering the site
Attachment: N/A
- Procedures to prevent the occurrence of nuisance conditions
Attachment: N/A

E. Groundwater monitoring

Is groundwater monitoring currently conducted at this site, or are any wells available for groundwater monitoring, or are groundwater monitoring data otherwise available for the sludge lagoon(s)?

Yes ☐ No ☒

If groundwater monitoring data are available, provide a copy. Provide a profile of soil types encountered down to the groundwater table and the depth to the shallowest groundwater as a separate attachment.

Attachment: N/A

Section 12. Authorizations/Compliance/Enforcement (Instructions Page 63)

A. Additional authorizations

Does the permittee have additional authorizations for this facility, such as reuse authorization, sludge permit, etc?

Yes ☐ No ☒

If yes, provide the TCEQ authorization number and description of the authorization:

N/A

B. Permittee enforcement status

Is the permittee currently under enforcement for this facility?

Yes ☒ No ☐

Is the permittee required to meet an implementation schedule for compliance or enforcement?

Yes ☒ No ☐

If yes to either question, provide a brief summary of the enforcement, the implementation schedule, and the current status:

Case #58731 Agreed order Document No. 2019-1805-MWD-E. The City of Olney didn't comply with permitted effluent limitations. The City of Olney completed an SEP and submitted all SEP documents in Spring 2023. Compliance documentation was submitted on March 12, 2024 and the order should terminate upon compliance or five years from 7-7-21, whichever is later

Section 13. RCRA/CERCLA Wastes (Instructions Page 63)

A. RCRA hazardous wastes

Has the facility received in the past three years, does it currently receive, or will it receive RCRA hazardous waste?

Yes ☐ No ☒

B. Remediation activity wastewater

Has the facility received in the past three years, does it currently receive, or will it receive CERCLA wastewater, RCRA remediation/corrective action wastewater or other remediation activity wastewater?

Yes ☐ No ☒

C. Details about wastes received

If yes to either Subsection A or B above, provide detailed information concerning these wastes with the application.

Attachment: N/A

Section 14. Laboratory Accreditation (Instructions Page 64)

All laboratory tests performed must meet the requirements of *30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification*, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - periodically inspected by the TCEQ; or
 - located in another state and is accredited or inspected by that state; or
 - performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review *30 TAC Chapter 25* for specific requirements.

The following certification statement shall be signed and submitted with every application. See the *Signature Page* section in the Instructions, for a list of designated representatives who may sign the certification.


CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of *30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification*.

Printed Name:

Title:

Signature:



Date: 3/14/2024

DOMESTIC TECHNICAL REPORT WORKSHEET 2.0

RECEIVING WATERS

The following is required for all TPDES permit applications

Section 1. Domestic Drinking Water Supply (Instructions Page 73)

Is there a surface water intake for domestic drinking water supply located within 5 miles downstream from the point or proposed point of discharge?

Yes ☐ No ☒

If yes, provide the following:

Owner of the drinking water supply: N/A

Distance and direction to the intake: N/A

Attach a USGS map that identifies the location of the intake.

Attachment: N/A

Section 2. Discharge into Tidally Affected Waters (Instructions Page 73)

Does the facility discharge into tidally affected waters?

Yes ☐ No ☒

If yes, complete the remainder of this section. If no, proceed to Section 3.

A. Receiving water outfall

Width of the receiving water at the outfall, in feet: N/A

B. Oyster waters

Are there oyster waters in the vicinity of the discharge?

Yes ☐ No ☒

If yes, provide the distance and direction from outfall(s).

N/A

C. Sea grasses

Are there any sea grasses within the vicinity of the point of discharge?

Yes ☐ No ☒

If yes, provide the distance and direction from the outfall(s).

N/A

Section 3. Classified Segments (Instructions Page 73)

Is the discharge directly into (or within 300 feet of) a classified segment?

Yes ☐ No ☒

If yes, this Worksheet is complete.

If no, complete Sections 4 and 5 of this Worksheet.

Section 4. Description of Immediate Receiving Waters (Instructions Page 75)

Name of the immediate receiving waters: Lake Olney, Salt Creek

A. Receiving water type

Identify the appropriate description of the receiving waters.

- ☐ Stream
- ☐ Freshwater Swamp or Marsh
- ☐ Lake or Pond

Surface area, in acres: [Click here to enter text.](#)

Average depth of the entire water body, in feet: [Click here to enter text.](#)

Average depth of water body within a 500-foot radius of discharge point, in feet: [Click here to enter text.](#)

- ☒ Man-made Channel or Ditch

- ☐ Open Bay
- ☐ Tidal Stream, Bayou, or Marsh
- ☐ Other, specify: [Click here to enter text.](#)

B. Flow characteristics

If a stream, man-made channel or ditch was checked above, provide the following. For existing discharges, check one of the following that best characterizes the area *upstream* of the discharge. For new discharges, characterize the area *downstream* of the discharge (check one).

- ☐ Intermittent - dry for at least one week during most years
- ☐ Intermittent with Perennial Pools - enduring pools with sufficient habitat to maintain significant aquatic life uses
- ☐ Perennial - normally flowing

Check the method used to characterize the area upstream (or downstream for new dischargers).

- ☐ USGS flow records
- ☐ Historical observation by adjacent landowners
- ☐ Personal observation
- ☐ Other, specify: [Click here to enter text.](#)

C. Downstream perennial confluences

List the names of all perennial streams that join the receiving water within three miles downstream of the discharge point.

none

D. Downstream characteristics

Do the receiving water characteristics change within three miles downstream of the discharge (e.g., natural or man-made dams, ponds, reservoirs, etc.)?

Yes ☒ No ☐

If yes, discuss how.

Stream bed was dry when observed

E. Normal dry weather characteristics

Provide general observations of the water body during normal dry weather conditions.

No flow in stream at 3 miles point

Date and time of observation: Summer 2023

Was the water body influenced by stormwater runoff during observations?

Yes ☒

No ☐

Section 5. General Characteristics of the Waterbody (Instructions Page 74)

A. Upstream influences

Is the immediate receiving water upstream of the discharge or proposed discharge site influenced by any of the following? Check all that apply.

☒ Oil field activities

☒ Urban runoff

☐ Upstream discharges

☒ Agricultural runoff

☐ Septic tanks

☐ Other(s), specify [Click here to enter text.](#)

B. Waterbody uses

Observed or evidences of the following uses. Check all that apply.

☒ Livestock watering

☐ Contact recreation

☐ Irrigation withdrawal

☒ Non-contact recreation

☐ Fishing

☐ Navigation

- | | |
|--|---|
| <input type="checkbox"/> Domestic water supply | <input type="checkbox"/> Industrial water supply |
| <input type="checkbox"/> Park activities | <input type="checkbox"/> Other(s), specify Click here to enter text |

C. Waterbody aesthetics

Check one of the following that best describes the aesthetics of the receiving water and the surrounding area.

- ☐ Wilderness: outstanding natural beauty; usually wooded or unpastured area; water clarity exceptional
- ☒ Natural Area: trees and/or native vegetation; some development evident (from fields, pastures, dwellings); water clarity discolored
- ☐ Common Setting: not offensive; developed but uncluttered; water may be colored or turbid
- ☐ Offensive: stream does not enhance aesthetics; cluttered; highly developed; dumping areas; water discolored

DOMESTIC WORKSHEET 6.0

INDUSTRIAL WASTE CONTRIBUTION

The following is required for all publicly owned treatment works (POTWs)

Section 1. All POTWs (Instructions Page 99)

A. Industrial users

Provide the number of each of the following types of industrial users (IUs) that discharge to your POTW and the daily flows from each user. See the Instructions for definitions of Categorical IUs, Significant IUs - non-categorical, and Other IUs.

If there are no users, enter 0 (zero).

Categorical IUs:

Number of IUs: 3

Average Daily Flows, in MGD: .00144, .0136, .000855

Significant IUs - non-categorical:

Number of IUs: 0

Average Daily Flows, in MGD: N/A

Other IUs:

Number of IUs: N/A

Average Daily Flows, in MGD: N/A

B. Treatment plant interference

In the past three years, has your POTW experienced treatment plant interference (see instructions)?

Yes ☐ No ☒

If yes, identify the dates, duration, description of interference, and probable cause(s) and possible source(s) of each interference event. Include the names of the IUs that may have caused the interference.

N/A

C. Treatment plant pass through

In the past three years, has your POTW experienced pass through (see instructions)?

Yes ☐ No ☒

If yes, identify the dates, duration, a description of the pollutants passing through the treatment plant, and probable cause(s) and possible source(s) of each pass through event. Include the names of the IUs that may have caused pass through.

[Click here to enter text.](#)

D. Pretreatment program

Does your POTW have an approved pretreatment program?

Yes ☐ No ☒

If yes, complete Section 2 only of this Worksheet.

Is your POTW required to develop an approved pretreatment program?

Yes ☐ No ☒

If yes, complete Section 2.c. and 2.d. only, and skip Section 3.

If no to either question above, skip Section 2 and complete Section 3 for each significant industrial user and categorical industrial user.

Section 2. POTWs with Approved Programs or Those Required to Develop a Program (Instructions Page 100)

A. Substantial modifications

Have there been any **substantial modifications** to the approved pretreatment program that have not been submitted to the TCEQ for approval according to 40 CFR §403.18?

Yes ☐ No ☒

If yes, identify the modifications that have not been submitted to TCEQ, including the purpose of the modification.

N/A

B. Non-substantial modifications

Have there been any **non-substantial modifications** to the approved pretreatment program that have not been submitted to TCEQ for review and acceptance?

Yes ☐ No ☒

If yes, identify all non-substantial modifications that have not been submitted to TCEQ, including the purpose of the modification.

N/A

C. Effluent parameters above the MAL

In Table 6.0(1), list all parameters measured above the MAL in the POTW's effluent monitoring during the last three years. Submit an attachment if necessary.

Table 6.0(1) – Parameters Above the MAL

Pollutant	Concentration	MAL	Units	Date
<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

D. Industrial user interruptions

Has any SIU, CIU, or other IU caused or contributed to any problems (excluding interferences or pass throughs) at your POTW in the past three years?

Yes ☐ No ☒

If yes, identify the industry, describe each episode, including dates, duration, description of the problems, and probable pollutants.

N/A

Section 3. Significant Industrial User (SIU) Information and Categorical Industrial User (CIU) (Instructions Page 100)

A. General information

Company Name: Air Tractor

SIC Code: 3721

Telephone number: 9405645616 Fax number: 9405645625

Contact name: Jim Hirsch

Address: 1584 Airport Road

City, State, and Zip Code: Olney, TX 76374

B. Process information

Describe the industrial processes or other activities that affect or contribute to the SIU(s) or CIU(s) discharge (i.e., process and non-process wastewater).

Metal Plating, cadmium, and chromium. Metal rinsed and water treated before discharged.

C. Product and service information

Provide a description of the principal product(s) or services performed.

Manufacture agricultural aircraft

D. Flow rate information

See the Instructions for definitions of “process” and “non-process wastewater.”

Process Wastewater:

Discharge, in gallons/day: 1437

Discharge Type: ☐ Continuous ☐ Batch ☒ Intermittent

Non-Process Wastewater:

Discharge, in gallons/day: N/A

Discharge Type: ☐ Continuous ☐ Batch ☐ Intermittent

E. Pretreatment standards

Is the SIU or CIU subject to technically based local limits as defined in the instructions?

Yes ☐ No ☒

Is the SIU or CIU subject to categorical pretreatment standards found in *40 CFR Parts 405-471*?

Yes ☒ No ☐

If subject to categorical pretreatment standards, indicate the applicable category and subcategory for each categorical process.

Category: 433

Subcategories: A

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

F. Industrial user interruptions

Has the SIU or CIU caused or contributed to any problems (e.g., interferences, pass through, odors, corrosion, blockages) at your POTW in the past three years?

Yes ☐ No ☒

If yes, identify the SIU, describe each episode, including dates, duration, description of problems, and probable pollutants.

N/A

G. General information

Company Name: PSI Industries

SIC Code: 3341

Telephone number: 9405643563 Fax number: 9405645365

Contact name: Tim Mitchell

Address: 1436 Main St

City, State, and Zip Code: Olney, TX, 76374

H. Process information

Describe the industrial processes or other activities that affect or contribute to the SIU(s) or CIU(s) discharge (i.e., process and non-process wastewater).

Aluminum Extruder and fabricator. Extrusion can be form stock size.
Anodizing and rinsing.

I. Product and service information

Provide a description of the principal product(s) or services performed.

Aluminum Extruder and fabricator

J. Flow rate information

See the Instructions for definitions of “process” and “non-process wastewater.”

Process Wastewater:

Discharge, in gallons/day: 855

Discharge Type: ☐ Continuous ☐ Batch ☒ Intermittent

Non-Process Wastewater:

Discharge, in gallons/day: N/A

Discharge Type: ☐ Continuous ☐ Batch ☐ Intermittent

K. Pretreatment standards

Is the SIU or CIU subject to technically based local limits as defined in the instructions?

Yes ☐ No ☒

Is the SIU or CIU subject to categorical pretreatment standards found in *40 CFR Parts 405-471*?

Yes ☒ No ☐

If subject to categorical pretreatment standards, indicate the applicable category and subcategory for each categorical process.

Category: 467

Subcategories: F

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

Category: [Click here to enter text.](#)

Subcategories: [Click here to enter text.](#)

L. Industrial user interruptions

Has the SIU or CIU caused or contributed to any problems (e.g., interferences, pass through, odors, corrosion, blockages) at your POTW in the past three years?

Yes ☐ No ☒

If yes, identify the SIU, describe each episode, including dates, duration, description of problems, and probable pollutants.

N/A

M. General information

Company Name: Tower Extrusions

SIC Code: 3471

Telephone number: 9405645681 Fax number: 9405644667

Contact name: J Hammond

Address: 1003 SH 79

City, State, and Zip Code: Olney, TX, 76374

N. Process information

Describe the industrial processes or other activities that affect or contribute to the SIU(s) or CIU(s) discharge (i.e., process and non-process wastewater).

Aluminum Extruder and fabricator. Extrusion can be form stock size or custom ordered. Anodizing and rinsing.

O. Product and service information

Provide a description of the principal product(s) or services performed.

Aluminum Extruder and fabricator

P. Flow rate information

See the Instructions for definitions of “process” and “non-process wastewater.”

Process Wastewater:

Discharge, in gallons/day: 13611

Discharge Type: ☐ Continuous ☐ Batch ☒ Intermittent

Non-Process Wastewater:

Discharge, in gallons/day: N/A

Discharge Type: ☐ Continuous ☐ Batch ☐ Intermittent

Q. Pretreatment standards

Is the SIU or CIU subject to technically based local limits as defined in the instructions?

Yes ☐ No ☒

Is the SIU or CIU subject to categorical pretreatment standards found in *40 CFR Parts 405-471*?

Yes ☒ No ☐

If subject to categorical pretreatment standards, indicate the applicable category and subcategory for each categorical process.

Category: 421

Subcategories: AB

Category: Click here to enter text.

Subcategories: Click here to enter text.

Category: Click here to enter text.

Subcategories: Click here to enter text.

Category: Click here to enter text.

Subcategories: Click here to enter text.

Category: Click here to enter text.

Subcategories: Click here to enter text.

R. Industrial user interruptions


Has the SIU or CIU caused or contributed to any problems (e.g., interferences, pass through, odors, corrosion, blockages) at your POTW in the past three years?

Yes ☐


No ☒


If yes, identify the SIU, describe each episode, including dates, duration, description of problems, and probable pollutants.

Click here to enter text.











OLNEY, TX
USGS MAP
SCALE: 1:24,000



CITY OF OLNEY
WASTEWATER PLANT
FLOW DIAGRAM


SCALE: 1" = 50'


S:\JLP\2024 PROJECTS\24-0093 OLNEY WW DISCHARGE PERMIT\CAD DRAWINGS\32729 DISCHARGE MAP.DWG Site Drawing Stream P-3/8/2024 4:52 PM S-4/1/2019 4:39 PM JESSICA PARKS



CORLETT, PROBST & BOYD, P.L.L.C.
Engineers and Surveyors
4605 Old Jacksboro Highway
Wichita Falls, Texas, 76302
(940) 723-1455

CITY OF OLNEY, TEXAS
SITE DRAWING





CITY OF OLNEY
WASTEWATER PLANT SITE

SCALE: 1" = 100'



RED RIVER AUTHORITY OF TEXAS

Laboratory Analysis Report

Job ID : 24031405

3000 Hammon Rd. Wichita Falls, Texas 76310

Report To : Client Name: City of Olney
Attn: James Mayes
Client Address: PO Box 546
City, State, Zip: Olney, TX, 763740546

The Red River Authority Of Texas has analyzed the following samples :

Client Sample ID	Matrix	Lab Sample ID
1 CBOD	Wastewater	24031405.01
2 TSS	Wastewater	24031405.02
3 Ammonia	Wastewater	24031405.03
4 TDS	Wastewater	24031405.04
5 TKN	Wastewater	24031405.05

Released By: Justlyn Ferrol

Title:

Date: 03/27/2024



This Laboratory is NELAP accredited (T104704274-23-26 TCEQ ID 48160).

Release Statement: I am the responsible party for the release of this laboratory data package. This data package has been reviewed by laboratory staff, and is complete and technically compliant with the requirements of the test methods employed, except where noted in the case narratives. By my signature, I affirm, to the best of my knowledge, all problems or anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by laboratory staff in the Laboratory Review process, and no information or data has been knowingly withheld that would affect the quality of the data presented. Furthermore, the enclosed test results only relate to the samples described herein.

This report is a government document, and shall not be reproduced or altered, in whole or in part, without the express permission of the Laboratory Supervisor or designee.

Date Received : 03/14/2024 12:46 PM



LABORATORY TERMS AND QUALIFIER DEFINITION

Job ID : 24031405

Date Of Report : 03/27/2024

>	Result is greater than the value reported	ND	Not Detected
<	Result is less than the value reported	NE	Not Enough sample
BB	Broken Bottle	NS	Not Scheduled for analysis
BRL	Below Reporting Limit	ppb	parts per billion
CAS #	Chemical Abstracts Service registry number	ppm	parts per million
Conc.	Concentration	Q	Qualifier
CtrlLimit	Control Limit	Qb	Quality control batch
DF	Dilution Factor	QC	Quality Control
EB	Empty Bottle	Rec	Recovery
IF	Instrument Failure	RPD	Relative Percent Difference
LA	Lab Accident	Rpt Limit	Reporting Limit
LCS	Laboratory Check Standard	SM	Sample Matrix / Interference
LCSD	Laboratory Check Standard Duplicate	SMCL	Secondary Maximum Contaminant Level
MB	Missing Bottle	Spk	Spike
MCL	Maximum Contaminant Level	surr	Surrogate
mg/L	milligram per liter	SX	Sample
MS	Matrix Spike	SX Dup	Sample Duplicate
MSD	Matrix Spike Duplicate	TIC	Tentatively Identified Compound
N	Analyte is not NELAC accredited	ug/L	microgram per liter
N/A	Not Applicable	us/cm	micro-siemens per centimeter
*	Quality control analyte is outside of specified acceptance criteria.		
B1	Analyte detected in the method blank at or above the method reporting limit.		
D	Results are reported from a diluted aliquot of the sample.		
H1	Sample was received properly, but analysis was performed past holding time.		
H2	Sample was received and analyzed past allowable holding time.		
J	The target analyte is detectable, but having greater quantitative uncertainty.		
R	Data is of unknown quality and is rejected because of quality assurance or quality control deficiencies.		
S	To indicate matrix or pre-digested spike sample recovery for an analysis is not within the specified control limit.		
SC	Sample failed one or more requisites of the sample condition checklist.		
URL	Upper Reporting Limit, compound detected for but not above reporting limit.		
Q	Sample inadequately dechlorinated and adjusted for pH		
HT	Holding Time in Hours. Used for E.Coli and Enterococcus analysis.		
BOD1	BOD value based on < 2 mg/L corrected DO depletion after 5 days.		
BOD2	Final DO value <1.0 after 5 days.		
BODR	BOD GGA recovery did not meet laboratory acceptance criteria.		
RS	Sample pH was unable to be adjusted to 6.0-8.0 SU prior to analysis.		
MPN	Most Probable Number		



SAMPLE CONDITION CHECKLIST

Date: 03/27/2024 12:00 PM

Client Name : City of Olney			
Client Address : PO Box 546			
Job ID : 24031405	Date Received : 03/14/2024	Time Received : 12:46 PM	
Temperature(°C) : 1.6	pH Paper ID : 205522	Water Preservative: H2SO4,Ice	
Thermometer ID : 20	Adjusted pH : <2	IDEXX Bottle Lot Number: N/A	Water Lot Number: HS231122
Comments : Include actions taken to resolve discrepancies/problem:			
Observed: <u>1.6</u> Correction Factor: <u>-0.0</u> Actual: <u>1.6</u> <u>0.5</u> mL of 1:1 H2SO4 1:1 HNO3 1:1 NaOH provided by RRAESL for sample preservation			

	Check Points	Yes	No	N/A
1	Chain of Custody Present?	✓		
2	Chain of Custody signed when relinquished and received?	✓		
3	Chain of Custody agrees with sample labels?	✓		
4	Samples in proper container/bottles?	✓		
5	Sample containers intact?	✓		
6	Sufficient sample volume for indicated tests?	✓		
7	All samples received within holding times?	✓		
8	Sample on ice?	✓		
9	Water - VOA vials have zero headspace?			✓
10	Water - pH acceptable upon receipt?	✓		
11	Water - Chemical preservative provided by RRA?	✓		
12	Water - pH adjusted?	✓		

CheckIn By : bcolvin

CheckIn Date : 03/14/2024



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031405.01	Client ID:	1 CBOD	Sampler:	James Mayes
-------------------	--------------------	-------------------	---------------	-----------------	--------------------

Client: City of Olney

COC No: 24031405

Study:

Sampled: 03/14/2024 10:00 AM

Project: Waste Water

Completed: 03/15/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00314	cBOD	03/15/2024	13:15	<2	mg/L	1	2	SM 5210 B	Qb24032507	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031405.02	Client ID:	2 TSS	Sampler:	James Mayes
-------------------	--------------------	-------------------	--------------	-----------------	--------------------

Client: City of Olney

COC No: 24031405

Study:

Sampled: 03/14/2024 10:00 AM

Project: Waste Water

Completed: 03/20/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00530	Solids, Total Suspended	03/20/2024	14:44	4.1	mg/L		2.5	SM 2540 D	Qb24032005	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031405.03	Client ID:	3 Ammonia	Sampler:	James Mayes
-------------------	--------------------	-------------------	------------------	-----------------	--------------------

Client: City of Olney

COC No: 24031405

Study:

Sampled: 03/14/2024 10:00 AM

Project: Waste Water

Completed: 03/22/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00610	Nitrogen, Ammonia as N	03/22/2024	14:55	0.06	mg/L	1	0.05	SM 4500 NH3 D	Qb24032513	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031405.04	Client ID:	4 TDS	Sampler:	James Mayes
------------	-------------	------------	-------	----------	-------------

Client: City of Olney

COC No: 24031405

Study:

Sampled: 03/14/2024 10:00 AM

Project: Waste Water

Completed: 03/19/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
70300	Solids, Total Dissolved	03/19/2024	14:34	1440	mg/L	5	50	SM 2540 C	Qb24031905	

COC = Chain of Custody	DF = Dilution Factor	LOQ = Limit of Quantitation
------------------------	----------------------	-----------------------------



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031405.05	Client ID:	5 TKN	Sampler:	James Mayes
------------	-------------	------------	-------	----------	-------------

Client: City of Olney

COC No: 24031405

Study:

Sampled: 03/14/2024 10:00 AM

Project: Waste Water

Completed: 03/26/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00625	Total Kjeldahl Nitrogen	03/26/2024	11:49	<0.2	mg/L	1	0.20	EPA 351.2	Qb24032602	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



QUALITY CONTROL CERTIFICATE

Job ID : 24031405

Date : 03/27/2024 12:00 PM

Analysis : TDS

Method : SM 2540 C

Reporting Units : mg/L

QC Batch ID : Qb24031905

Created Date : 03/19/2024 03:02 PM

Created By : njakka

Samples in This QC Batch :

QC Type: Method Blank

Parameter	CAS #	Result	Units	DF	Rpt Limit	Q
Solids, Total Dissolved		<50.0	mg/L	1	50	

QC Type: Spike

QcType	Parameter	QC Sample Result	Sample Result	QCSample ID	Units	RPD	RPD CtrlLimit	Spike Added	Rec	Rec CtrlLimit	Q
Duplicate	Solids, Total Dissolv	418	422	24033203.01	mg/L	1	10				
Duplicate	Solids, Total Dissolv	270	270	24033203.11	mg/L	0.0	10				
LCS	Solids, Total Dissolv	976			mg/L			1000	97.6	85-115	
LCSD	Solids, Total Dissolv	982			mg/L	0.6	15	1000	98.2	85-115	
LOQ	Solids, Total Dissolv	50.0			mg/L			50	100.0	70-130	



QUALITY CONTROL CERTIFICATE

Job ID : 24031405

Date : 03/27/2024 12:00 PM

Analysis : TSS

Method : SM 2540 D

Reporting Units : mg/L

QC Batch ID : Qb24032005

Created Date : 03/20/2024 03:00 PM

Created By : bcolvin

Samples in This QC Batch : 24031405.04

QC Type: Method Blank

Parameter	CAS #	Result	Units	DF	Rpt Limit	Q
Solids, Total Suspended		<2.5	mg/L		2.5	

QC Type: Spike

QcType	Parameter	QC Sample Result	Sample Result	QCSample ID	Units	RPD	RPD CtrlLimit	Spike Added	Rec	Rec CtrlLimit	Q
LCS	Solids, Total Suspe	200			mg/L			200	100.0	85-115	
LCSD	Solids, Total Suspe	200			mg/L	0.1	15	200	100.0	85-115	
Duplicate	Solids, Total Suspe	6330	6270	24031414.06	mg/L	1.1	10				
Duplicate	Solids, Total Suspe	24.4	23.6	24031416.01	mg/L	3.3	10				
LOQ	Solids, Total Suspe	2.6			mg/L			2.5	104.0	70-130	



QUALITY CONTROL CERTIFICATE

Job ID : 24031405

Date : 03/27/2024 12:00 PM

Analysis : cBOD

Method : SM 5210 B

Reporting Units : mg/L

QC Batch ID : Qb24032507

Created Date : 03/25/2024 01:12 PM

Created By : msears

Samples in This QC Batch : 24031405.02

QC Type: Method Blank

Parameter	CAS #	Result	Units	DF	Rpt Limit	Q
cBOD		<2	mg/L	1		

QC Type: Spike

QCType	Parameter	QC Sample Result	Sample Result	QCSample ID	Units	RPD	RPD CtrlLimit	Spike Added	Rec	Rec CtrlLimit	Q
Duplicate	cBOD	<2	<2	24031420.01	mg/L	4.3	30				
GGA	cBOD	179			mg/L			198		85-115	



QUALITY CONTROL CERTIFICATE

Job ID : 24031405

Date : 03/27/2024 12:00 PM

Analysis : Nitrogen, Ammonia as N

Method : SM 4500 NH3 D

Reporting Units : mg/L

QC Batch ID : Qb24032513

Created Date : 03/25/2024 03:17 PM

Created By : njakka

Samples in This QC Batch : 24031405.01

QC Type: Method Blank

Parameter	CAS #	Result	Units	DF	Rpt Limit	Q
Nitrogen, Ammonia as N		<0.05	mg/L	1	0.05	

QC Type: Spike

QcType	Parameter	QC Sample Result	Sample Result	QCSample ID	Units	RPD	RPD CtrlLimit	Spike Added	Rec	Rec CtrlLimit	Q
Duplicate	Nitrogen, Ammonia	2.14	2.19	24031307.02	mg/L	2.3	15				
Duplicate	Nitrogen, Ammonia	1.49	1.42	24031420.03	mg/L	4.8	15				
LCS	Nitrogen, Ammonia	0.50			mg/L			0.5	99.0	85-115	
LCSD	Nitrogen, Ammonia	0.51			mg/L	3	15	0.5	102.0	85-115	
LOQ	Nitrogen, Ammonia	0.05			mg/L			0.05	109.0	70-130	
MS	Nitrogen, Ammonia	0.50	0.05	24031306.02	mg/L			0.4762	93.6	80-120	



QUALITY CONTROL CERTIFICATE

Job ID : 24031405

Date : 03/27/2024 12:00 PM

Analysis : TKN

Method : EPA 351.2

Reporting Units : mg/L

QC Batch ID : Qb24032602

Created Date : 03/26/2024 02:14 PM

Created By : mtullock

Samples in This QC Batch : 24031405.03

QC Type: Method Blank

Parameter	CAS #	Result	Units	DF	Rpt Limit	Q
Total Kjeldahl Nitrogen		<0.2	mg/L	1	0.20	

QC Type: Spike

QcType	Parameter	QC Sample Result	Sample Result	QCSample ID	Units	RPD	RPD CtrlLimit	Spike Added	Rec	Rec CtrlLimit	Q
Duplicate	Total Kjeldahl Nitro	0.747	0.759	24033203.08	mg/L	1.6	15	0			
LCS	Total Kjeldahl Nitro	2.03			mg/L			2.00	101.7	90-110	
LCSD	Total Kjeldahl Nitro	2.02			mg/L	0.5	15	2.00	101.3	90-110	
LOQ	Total Kjeldahl Nitro	0.2			mg/L			0.20	92.0	70-130	
MS	Total Kjeldahl Nitro	2.24	0.556	24033203.09	mg/L			1.96	86.4	90-110	*

QC Type: Standard

QcType	Parameter	Result	Units	Spike Added	Rec	Rec CtrlLimit	Q
	Total Kjeldahl Nitro	2.07		2.00	103.5	90-110	

Chain of Custody

Laboratory Use Only: COC#

24031405



Red River Authority of Texas
Environmental Services Laboratory
 P.O. Box 240, Wichita Falls, TX 76307-0240
 3000 Hammon Rd, Wichita Falls, TX 76310-7500
 Phone: 940-723-1717 • Fax: 940-723-6529
 Website: www.rra.texas.gov • Email: lab@rra.texas.gov



Report Information	
Company Name:	City of Olney
Contact Name:	James Mayes
Address:	201 E Main
City / State / Zip:	Olney TX 76374
Phone :	940-276-2011
Email:	jmayes@cityofolneytx.com
Billing Information (if different from above)	
Address:	
City / State / Zip:	
Contact Name:	
Phone :	
Email:	

Matrix Codes:	D = Drinking Water	N = Non-Potable Water
Preservation Codes: (Circle all that apply)	1 = None	2 = HNO3
Container Type Codes: (Circle all that apply)	P = Plastic	G = Glass

Laboratory Use Only	Sample Description	Date(s) Collected	Time(s) Collected	Matrix Code	Preservation	# of Containers	(Comp / (G)rab
24031405.01	#1	3-14-24	10:00 AM	N	6	1	G
24031405.02	#2			N	6	1	G
24031405.03	#3			N	3	1	G
24031405.04	#4			N	6	1	G
24031405.05	#5			N	6	1	G

Project Information		Analysis Required	
Priority:	<input checked="" type="checkbox"/> Normal <input type="checkbox"/> 50% Rush <input type="checkbox"/> 100% Rush		
Project Name:	Waste water permit Tceq		
Project Location:	WWTP		
Sampler Name/Sampler Affiliation:	James Mayes		
PO Number or Reference			

Sample Custody Documentation			
Sampler's Name: (Signature)	Received By: (Signature)	Date/Time Relinquished: 3-14-24 12:46	Date/Time Received: 3-14-24 12:46
Relinquished By: (Signature)	Received By: (Signature)	Date/Time Relinquished:	Date/Time Received:
Relinquished By: (Signature)	Received By: (Signature)	Date/Time Relinquished:	Date/Time Received:
Document Number: 300		Special Instructions/Comments: 1.6-e.e. 1.60c	
		PH12	



24031405

Rev. 4 effective 8/9/2019



RED RIVER AUTHORITY OF TEXAS

Laboratory Analysis Report

Job ID : 24031406

3000 Hammon Rd. Wichita Falls, Texas 76310

Report To : Client Name: City of Olney
Attn: James Mayes
Client Address: PO Box 546
City, State, Zip: Olney, TX, 763740546

The Red River Authority Of Texas has analyzed the following samples, please see the attached sub report for subcontracted sample results :

Client Sample ID	Matrix	Lab Sample ID
6 Alkalinity	Wastewater	24031406.01
7 Anions	Wastewater	24031406.02
8 T Phos	Wastewater	24031406.03
9 E coli	Wastewater	24031406.04

Released By: Justlyn Ferrol

Title:

Date: 03/27/2024



This Laboratory is NELAP accredited (T104704274 TCEQ ID 48140).

Release Statement: I am the responsible party for the release of this laboratory data package. This data package has been reviewed by laboratory staff, and is complete and technically compliant with the requirements of the test methods employed, except where noted in the case narratives. By my signature, I affirm, to the best of my knowledge, all problems or anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by laboratory staff in the Laboratory Review process, and no information or data has been knowingly withheld that would affect the quality of the data presented. Furthermore, the enclosed test results only relate to the samples described herein.

This report is a government document, and shall not be reproduced or altered, in whole or in part, without the express permission of the Laboratory Supervisor or designee. This report contains 4 pages, excluding any attachments.

Date Received : 03/14/2024 12:46 PM



LABORATORY TERMS AND QUALIFIER DEFINITION

Job ID : 24031406

Date Of Report : 03/27/2024

>	Result is greater than the value reported	ND	Not Detected
<	Result is less than the value reported	NE	Not Enough sample
BB	Broken Bottle	NS	Not Scheduled for analysis
BRL	Below Reporting Limit	ppb	parts per billion
CAS #	Chemical Abstracts Service registry number	ppm	parts per million
Conc.	Concentration	Q	Qualifier
CtrlLimit	Control Limit	Qb	Quality control batch
DF	Dilution Factor	QC	Quality Control
EB	Empty Bottle	Rec	Recovery
IF	Instrument Failure	RPD	Relative Percent Difference
LA	Lab Accident	Rpt Limit	Reporting Limit
LCS	Laboratory Check Standard	SM	Sample Matrix / Interference
LCSD	Laboratory Check Standard Duplicate	SMCL	Secondary Maximum Contaminant Level
MB	Missing Bottle	Spk	Spike
MCL	Maximum Contaminant Level	surr	Surrogate
mg/L	milligram per liter	SX	Sample
MS	Matrix Spike	SX Dup	Sample Duplicate
MSD	Matrix Spike Duplicate	TIC	Tentatively Identified Compound
N	Analyte is not NELAC accredited	ug/L	microgram per liter
N/A	Not Applicable	us/cm	micro-siemens per centimeter
*	Quality control analyte is outside of specified acceptance criteria.		
B1	Analyte detected in the method blank at or above the method reporting limit.		
D	Results are reported from a diluted aliquot of the sample.		
H1	Sample was received properly, but analysis was performed past holding time.		
H2	Sample was received and analyzed past allowable holding time.		
J	The target analyte is detectable, but having greater quantitative uncertainty.		
R	Data is of unknown quality and is rejected because of quality assurance or quality control deficiencies.		
S	To indicate matrix or pre-digested spike sample recovery for an analysis is not within the specified control limit.		
SC	Sample failed one or more requisites of the sample condition checklist.		
URL	Upper Reporting Limit, compound detected for but not above reporting limit.		
Q	Sample inadequately dechlorinated and adjusted for pH		
HT	Holding Time in Hours. Used for E.Coli and Enterococcus analysis.		
BOD1	BOD value based on < 2 mg/L corrected DO depletion after 5 days.		
BOD2	Final DO value <1.0 after 5 days.		
BODR	BOD GGA recovery did not meet laboratory acceptance criteria.		
RS	Sample pH was unable to be adjusted to 6.0-8.0 SU prior to analysis.		
MPN	Most Probable Number		



SAMPLE CONDITION CHECKLIST

Date: 03/27/2024 07:48 AM

Client Name : City of Olney			
Client Address : PO Box 546			
Job ID : 24031406	Date Received : 03/14/2024	Time Received : 12:46 PM	
Temperature(°C) : 1.6	pH Paper ID : N/A	Water Preservative: H2SO4,Ice	
Thermometer ID : 20	Adjusted pH : N/A	IDEXX Bottle Lot Number: EW004V	Water Lot Number: HS231122
Comments : Include actions taken to resolve discrepancies/problem:			
Observed: <u>1.6</u> Correction Factor: <u>-0.0</u> Actual: <u>1.6</u> <u>0.5</u> mL of 1:1 H2SO4 1:1 HNO3 1:1 NaOH provided by RRAESL for sample preservation			

	Check Points	Yes	No	N/A
1	Chain of Custody Present?	✓		
2	Chain of Custody signed when relinquished and received?	✓		
3	Chain of Custody agrees with sample labels?	✓		
4	Samples in proper container/bottles?	✓		
5	Sample containers intact?	✓		
6	Sufficient sample volume for indicated tests?	✓		
7	All samples received within holding times?	✓		
8	Sample on ice?	✓		
9	Water - VOA vials have zero headspace?			✓
10	Water - pH acceptable upon receipt?	✓		
11	Water - Chemical preservative provided by RRA?	✓		
12	Water - pH adjusted?	✓		

CheckIn By : bcolvin

CheckIn Date : 03/14/2024



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031406.01	Client ID:	6 Alkalinity	Sampler:	James Mayes
------------	-------------	------------	--------------	----------	-------------

Client: City of Olney

COC No: 24031406

Study:

Sampled: 03/14/2024 10:00 AM

Project: WWTP Water

Completed: 03/18/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Total Alkalinity is titrated to an endpoint of pH 4.5

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00410	Alkalinity as CaCO ₃ , Total	03/18/2024	11:15	120	mg/L		>20	SM 2320 B	Qb24031901	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031406.02	Client ID:	7 Anions	Sampler:	James Mayes
-------------------	-------------	-------------------	----------	-----------------	-------------

Client: City of Olney

COC No: 24031406

Study:

Sampled: 03/14/2024 10:00 AM

Project: WWTP Water

Completed: 03/20/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Total Alkalinity is titrated to an endpoint of pH 4.5

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
00615	Nitrite as N	03/20/2024	11:22	BRL	mg/L	10	0.05	EPA 300.0	Qb24032003	
00620	Nitrate as N	03/20/2024	11:22	43.9	mg/L	10	0.05	EPA 300.0	Qb24032003	
00940	Chloride	03/20/2024	11:22	212	mg/L	10	10	EPA 300.0	Qb24032003	
00945	Sulfate	03/20/2024	11:22	796	mg/L	10	10	EPA 300.0	Qb24032003	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



Red River Authority of Texas
Environmental Services Division Laboratory
P.O. Box 240
Wichita Falls, TX 76307-0240
Telephone: (940) 723-1717 Fax: (940) 723-6529
E-mail: lab@rra.texas.gov



Sample Analysis Report

Sample ID:	24031406.04	Client ID:	9 E coli	Sampler:	James Mayes
------------	-------------	------------	----------	----------	-------------

Client: City of Olney

COC No: 24031406

Study:

Sampled: 03/14/2024 10:00 AM

Project: WWTP Water

Completed: 03/14/2024

Location: WWTP

Type: Grab

Matrix: Wastewater

Receiving Notation:

Analysis Notation:

Total Alkalinity is titrated to an endpoint of pH 4.5

Param	Analyte	Date	Time	Result	Units	DF	LOQ	Method	QC Batch	Qualifier
31699	E. coli	03/14/2024	15:25	<1	MPN/100 mL	1	1	SM 9223 B	Qb24031801	

COC = Chain of Custody

DF = Dilution Factor

LOQ = Limit of Quantitation



24031406

Laboratory Analysis Report

Total Number of Pages: 7

Job ID : 24031861

10100 East Freeway, Suite 100, Houston, TX 77029 tel: 713-453-6060, fax: 713-453-6091, <http://www.ablabs.com>

Client Project Name :
24031406 / City of Olney/WWTP Permit

Report To :	Client Name:	Red River Authority of Texas	P.O.#:
	Attn:	Justlyn Ferrol	Sample Collected By: J. Mayes
	Client Address:	3000 Hammon Rd.	Date Collected: 03/14/24
	City, State, Zip:	Wichita Falls, Texas, 76310	

A&B Labs has analyzed the following samples...

Client Sample ID	Matrix	A&B Sample ID
24031406.03- #8	Water	24031861.01

Released By: Senthilkumar Sevukan
Title: Vice President Operations
Date: 3/22/2024



This Laboratory is NELAP (T104704213-23-31) accredited. Effective: 04/13/2023; Expires: 3/31/2024

Scope: Non-Potable Water, Drinking Water, Air, Solid, Biological Tissue, Hazardous Waste

I am the laboratory manager, or his/her designee, and I am responsible for the release of this data package. This laboratory data package has been reviewed and is complete and technically compliant with the requirements of the methods used, except where noted in the attached exception reports. I affirm, to the best of my knowledge that all problems/anomalies observed by this laboratory (and if applicable, any and all laboratories subcontracted through this laboratory) that might affect the quality of the data, have been identified in the Laboratory Review Checklist, and that no information or data have been knowingly withheld that would affect the quality of the data.

This report cannot be reproduced, except in full, without prior written permission of A&B Labs. Results shown relate only to the items tested. Results apply to the sample as received. Samples are assumed to be in acceptable condition unless otherwise noted. Blank correction is not made unless otherwise noted. Air concentrations reported are based on field sampling information provided by client. Soil samples are reported on a wet weight basis unless otherwise noted. Uncertainty estimates are available on request.

ab-q210-0321

Date Received : 03/19/2024 09:59



24031406

LABORATORY TERM AND QUALIFIER DEFINITION REPORT



Job ID : 24031861

Date: 3/22/2024

General Term Definition

Back-Wt	Back Weight	ML	Unadjusted Minimum Quantitation Limit
BRL	Below Reporting Limit	Post-Wt	Post Weight
cfu	colony-forming units	ppm	parts per million
Conc.	Concentration	Pre-Wt	Previous Weight
D.F.	Dilution Factor	Q	Qualifier
Front-Wt	Front Weight	RegLimit	Regulatory Limit
J	Estimation. Below calibration range but above MDL	RLU	Relative Light Unit
LCS	Laboratory Check Standard	RPD	Relative Percent Difference
LCSD	Laboratory Check Standard Duplicate	RptLimit	Reporting Limit
LOD	Limit of detection adjusted for %M + DF	SDL	Sample Detection Limit
LOQ	Limit of Quantitation adjusted for %M + DF	surr	Surrogate
MS	Matrix Spike	T	Time
MSD	Matrix Spike Duplicate	TNTC	Too numerous to count
MW	Molecular Weight	UQL	Unadjusted Upper Quantitation Limit

Qualifier Definition



24031406



LABORATORY TEST RESULTS

Job ID : 24031861

Date 3/22/2024

Client Name: Red River Authority of Texas
Project Name: 24031406 / City of Olney/WWTP Permit

Attn: Justlyn Ferrol

Client Sample ID: 24031406.03- #8
Date Collected: 03/14/24
Time Collected: 10:00
Other Information:

Job Sample ID: 24031861.01
Sample Matrix Water

Test Method	Parameter/Test Description	Result	Units	DF	Rpt Limit	Reg Limit	Q	Date Time	Analyst
SM 4500P-E	Phosphorus Phosphorus	0.1925	mg/L	1	0.05			03/20/24 10:00	AJ



24031406

QUALITY CONTROL CERTIFICATE



Job ID : 24031861

Date : 3/22/2024

Analysis : Phosphorus

Method : SM 4500P-E

Reporting Units : mg/L

QC Batch ID : Qb24032081

Created Date : 03/20/24

Created By : Ajohn

Samples in This QC Batch : 24031861.01

QC Type: Method Blank

Parameter	CAS #	Result	Units	D.F.	RptLimit	Qual
Phosphorus	7723-14-0	BRL	mg/L	1	0.05	

QC Type: LCS and LCSD

Parameter	LCS Spk Added	LCS Result	LCS % Rec	LCSD Spk Added	LCSD Result	LCSD % Rec	RPD	RPD CtrlLimit	%Recovery CtrlLimit	Qual
Phosphorus	0.200	0.203	102	0.200	0.196	98	3.5	20	80-120	

QC Type: MS and MSD

QC Sample ID: 24032015.01

Parameter	Sample Result	MS Spk Added	MS Result	MS % Rec	MSD Spk Added	MSD Result	MSD % Rec	RPD	RPD CtrlLimit	%Rec CtrlLimit	Qual
Phosphorus	BRL	0.200	0.189	94.5	0.200	0.193	96.5	2.1	20	80-120	

ab-q213-0321

Refer to the Definition page for terms.



The Chain of Custody is a Legal Document

Page 1 of 1

24031406

Job ID: 24031861



03/19/2024 Red River Authority of Tex ACH

Free

www.ablabs.com

1. REPORT TO:

Company: Red River Authority of TX

Address: PO Box 240

Wichita Falls, TX 76307

Contact: Justlyn Ferrol

Phone: 940-723-1717

Fax: 940-723-6529

Email: justlyn.ferrol@rra.texas.gov

CC: william.moore@rra.texas.gov

2. INVOICE TO:

Company: Same

Address:

Contact:

Phone:

Fax:

Email:

CC:

3. PO

4. Turnaround Time- Business Days

☐ 1 Day *☐ 5 Days *☐ 2 Days *☒ 7 Days-Standard☐ 3 Days *☐ Other _____

* Surcharge Applies

Day Zero is the day sample is received.

Report due at 5pm on due day.

A&B JOB ID

5. Project # 24031406

6. Project Name / Location

City of Olney/WWTP Permit

7. Reporting Requirement

☐ TRRP Limits Only☐ TRRP Rpt. Package☐ See Attached☒ Standard Level II

8. Sampler's Name & Company

Sampler's Signature & Date

J. Mayes/City of Olney

"on original COC"

9. Sample ID & Description

Lab Use
Only

10. Sampling

11.

12. Matrix

Date

Time

Comp

grab

Water

Soil

Sludge

Oil

Air

Other

13. No. of Containers

P

C/S

T-Phosphorus

14. Containers*

15. Preservatives**

16. pH-Lab Only

18. Comments

19. RELINQUISHED BY

DATE

TIME

20. RECEIVED BY

DATE

TIME

KNOWN HAZARDS / COMMENT

1) *Justlyn Ferrol*

3/17/24

1600

1) *UPC*2) *UPC*

3/14/24

9:59

2) *UPC*

3)

3)

3/14/24

9:59

* Containers: VOA- 40 ml vial

4 oz/8 oz- glass wide mouth

A/G- Amber/Glass 1 Liter

P/O- Plastic/other _____

**Preservatives: C-Cool H- HCl N- HNO3

S-H2SO4 OH- NaOH T-Na2S2O3 X- Other _____

Temperature: 3.1

Intact?

☒ Y☐ NInitials *JRS*

BILL OF LADING/TRACKING

METHOD OF SHIPMENT

A&B CANNOT ACCEPT VERBAL CHANGES. PLEASE FAX WRITTEN CHANGES TO 713-453-6091 OR EMAIL THE NEW COC TO YOUR PROJECT MANAGER.

Samples will be disposed of after 30 days. A&B reserves the right to return samples.



24031406

about:blank

STACEY GREEN
(940)723-8697
RED RIVER AUTHORITY OF TEXAS
3000 HAMMON RD
WICHITA FALLS, TX 76310

10 LBS

1 OF 1

SHIP TO:
ASHLEY HALL
713-453-6060
A & B LABS
SUITE 100
10100 EAST FREEWAY
HOUSTON TX 77029




TX 770 9-05



UPS NEXT DAY AIR

TRACKING #: 1Z A72 76T 01 9448 7684

1



BILLING: P/P
DIRECT DELIVERY ONLY

Reference #1: 24031406, 24031425



XOL 24.03.07 NV45 12.0A 03/2024*



24031406



Sample Condition Checklist

A&B JobID : 24031861		Date Received : 03/19/2024		Time Received : 9:59AM								
Client Name : Red River Authority of Texas												
Temperature : 3.1°C		Sample pH : <2 P										
Thermometer ID : IR5		pH Paper ID : 110937										
Perservative :		Lot# :										
	Check Points				Yes	No	N/A					
1.	Cooler Seal present and signed.				X							
2.	Sample(s) in a cooler.				X							
3.	If yes, ice in cooler.				X							
4.	Sample(s) received with chain-of-custody.				X							
5.	C-O-C signed and dated.				X							
6.	Sample(s) received with signed sample custody seal.						X					
7.	Sample containers arrived intact. (If No comment)				X							
8.	Matrix:	Water	Soil	Liquid	Sludge	Solid	Cassette	Tube	Bulk	Badge	Food	Other
		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
9.	Samples were received in appropriate container(s)				X							
10.	Sample(s) were received with Proper preservative				X							
11.	All samples were tagged or labeled.				X							
12.	Sample ID labels match C-O-C ID's.				X							
13.	Bottle count on C-O-C matches bottles found.				X							
14.	Sample volume is sufficient for analyses requested.				X							
15.	Samples were received with in the hold time.				X							
16.	VOA vials completely filled.						X					
17.	Sample accepted.				X							
18.	Has client been contacted about sub-out						X					

Comments : Include actions taken to resolve discrepancies/problem:

--

Brought by : UPS

Received by : EValdez

Check in by/date : EValdez / 03/19/2024

ab-s005-1123

Phone : 713-453-6060

www.ablabs.com