



Technical Package Cover Page

This file contains the following documents:


1. Summary of application (in plain language)
 - English
 - Alternative Language (Spanish)
 2. First notice (NORI-Notice of Receipt of Application and Intent to Obtain a Permit)
 - English
 - Alternative Language (Spanish)
 3. Second notice (NAPD-Notice of Preliminary Decision)
 - English
 - Alternative Language (Spanish)
 4. Application materials *
 5. Draft permit *
 6. Technical summary or fact sheet *
-



Portada de Paquete Técnico

Este archivo contiene los siguientes documentos:

1. Resumen de la solicitud (en lenguaje sencillo)
 - Inglés
 - Idioma alternativo (español)
2. Primer aviso (NORI, Aviso de Recepción de Solicitud e Intención de Obtener un Permiso)
 - Inglés
 - Idioma alternativo (español)
3. Segundo aviso (NAPD, Aviso de Decisión Preliminar)
 - Inglés
 - Idioma alternativo (español)
4. Materiales de la solicitud **
5. Proyecto de permiso **
6. Resumen técnico u hoja de datos **



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

PLAIN LANGUAGE SUMMARY FOR TPDES OR TLAP PERMIT APPLICATIONS

Plain Language Summary Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary as required by [Title 30, Texas Administrative Code \(30 TAC\), Chapter 39, Subchapter H](#). Applicants may modify the template as necessary to accurately describe their facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how the applicant will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements.

If you are subject to the alternative language notice requirements in [30 TAC Section 39.426](#), **you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package.** For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS DOMESTIC WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

CSWR (CN605844786) operates Texas Landing WWTF (RN102341294), a domestic wastewater treatment plant. The facility is located at 404 Branding Iron, in Livingston, Polk County, Texas 77351. This facility is applying for a permit renewal to discharge 65,000 gallons per day of treated domestic wastewater.

Discharges from the facility are expected to contain BOD, TSS, and E. coli. The domestic wastewater discharge is treated by an activated sludge system. Wastewater flows from the influent lift station to the raw bar screen to the aeration unit. From the aeration unit, the wastewater then runs through the clarifier where some of the sludge goes to the digester for wasting and the remaining sludge is returned to the inflow of the aeration unit. The wastewater that leaves the clarifier is then chlorinated prior to discharging into Lake Livingston. The WWTP operated in single phase nitrification.

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

AGUAS RESIDUALES **Domesticas** /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación ejecutiva fedérale de la solicitud de permiso.

CSWR (CN605844786) opera Texas Landing WWTF (RN102341294), una facilidad para tratar residuales domesticas. La instalación está ubicada en 404 Branding Iron, en Livingston, Condado de Polk, Texas 77351. Esta instalación está solicitando la renovación de un permiso para descargar 65,000 galones por día de aguas residuales domésticas tratadas.

Se espera que las descargas de la instalación contengan BOD, TSS, y E. coli. Las residuales domesticas. están tratado por un sistema de lodos activados. Las aguas residuales fluyen desde la estación de bombeo de influentes hacia la rejilla de cribado primaria y luego a la unidad de aireación. Desde la unidad de aireación, las aguas residuales pasan por el clarificador, donde una parte de los lodos se envía al digestor para ser desechados y el resto de los lodos se devuelve a la entrada de la unidad de aireación. Las aguas residuales que salen del clarificador luego se cloran antes de descargarse en el Lago Livingston. La planta de tratamiento de aguas residuales (WWTF) opera en una fase única de nitrificación..

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY



NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT RENEWAL

PERMIT NO. WQ0013147001

APPLICATION. CSWR-Texas Utility Operating Company, LLC, 1630 Des Peres Road, Suite 140, Des Peres, Missouri 63131, has applied to the Texas Commission on Environmental Quality (TCEQ) to renew Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0013147001 (EPA I.D. No. TX0098809) to authorize the discharge of treated wastewater at a volume not to exceed a daily average flow of 65,000 gallons per day. The domestic wastewater treatment facility is located at 404 Branding Iron, Livingston, Texas 77351, near the city of Livingston, in Polk County, Texas 77351. The discharge route is from the plant site directly to Lake Livingston. TCEQ received this application on September 30, 2024. The permit application will be available for viewing and copying at Livingston Municipal Library, 707 North Tyler Avenue, Livingston, in Polk County, Texas prior to the date this notice is published in the newspaper. The application, including any updates, and associated notices are available electronically at the following webpage:

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

This link to an electronic map of the site or facility's general location is provided as a public courtesy and not part of the application or notice. For the exact location, refer to the application.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-95.0346,30.7079&level=18>

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at:

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

El aviso de idioma alternativo en español está disponible en

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

ADDITIONAL NOTICE. TCEQ's Executive Director has determined the application is administratively complete and will conduct a technical review of the application. After technical review of the application is complete, the Executive Director may prepare a draft permit and will issue a preliminary decision on the application. **Notice of the Application and Preliminary Decision will be published and mailed to those who are on the county-wide mailing list and to those who are on the mailing list for this application. That notice will contain the deadline for submitting public comments.**

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting on this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ will hold a public meeting if the Executive Director determines that there is a significant degree of public

interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. **Unless the application is directly referred for a contested case hearing, the response to comments, and the Executive Director's decision on the application, will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application.** If comments are received, the mailing will also provide instructions for requesting reconsideration of the Executive Director's decision and for requesting a contested case hearing. A contested case hearing is a legal proceeding similar to a civil trial in state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period and, the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. **If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period.**

TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. All public comments and requests must be submitted either electronically at <https://www14.tceq.texas.gov/epic/eComment/>, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Please be aware that any contact information you provide, including your name, phone number, email address and physical address will become part of the agency's public record. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from CSWR-Texas Utility Operating Company, LLC at the address stated above or by calling Ms. Amanda Sappington, EHS Compliance Manager, at 314-464-3976.

Issuance Date: October 30, 2024

Comisión de Calidad Ambiental del Estado de Texas



AVISO DE RECIBO DE LA SOLICITUD Y EL INTENTO DE OBTENER PERMISO PARA LA CALIDAD DEL AGUA RENOVACION

PERMISO NO. WQ0013147001

SOLICITUD. CSWR-Texas empresa operadora de servicios públicos, LLC, 1630 Des Peres Road, Suite 140, Des Peres, Missouri 63131 ha solicitado a la Comisión de Calidad Ambiental del Estado de Texas (TCEQ) para renovar el Permiso No. WQ0013147001 (EPA I.D. No. TX0098809) del Sistema de Eliminación de Descargas de Contaminantes de Texas (TPDES) para autorizar la descarga de aguas residuales tratadas en un volumen que no sobrepasa un flujo promedio diario de 65,000 galones por día. La planta está ubicada 404 Branding Iron, Livingston, Texas 77351 en el Condado de Polk, Texas. La ruta de descarga es del sitio de la planta directamente a Lago Livingston. La TCEQ recibió esta solicitud el 30 de septiembre de 2024. La solicitud para el permiso estará disponible para leerla y copiarla en Biblioteca Municipal de Livingston, 707 North Tyler Avenue, Livingston, en el condado de Polk antes de la fecha de publicación de este aviso en el periódico.

Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-95.0346,30.7079&level=18>

AVISO ADICIONAL. El Director Ejecutivo de la TCEQ ha determinado que la solicitud es administrativamente completa y conducirá una revisión técnica de la solicitud. Después de completar la revisión técnica, el Director Ejecutivo puede preparar un borrador del permiso y emitirá una Decisión Preliminar sobre la solicitud. **El aviso de la solicitud y la decisión preliminar serán publicados y enviado a los que están en la lista de correo de las personas a lo largo del condado que desean recibir los avisos y los que están en la lista de correo que desean recibir avisos de esta solicitud. El aviso dará la fecha límite para someter comentarios públicos.**

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar **comentarios públicos o pedir una reunión pública sobre esta solicitud.** El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO.

Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todo los comentarios públicos esenciales, pertinentes, o significativos. **A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso.** Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Además, puede pedir que la TCEQ ponga su nombre en una o más de las listas de correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agregue su nombre en una de las listas designe cual lista(s) y envía por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

CONTACTOS E INFORMACIÓN A LA AGENCIA. Todos los comentarios públicos y solicitudes deben ser presentadas electrónicamente vía <http://www14.tceq.texas.gov/epic/eComment/> o por escrito dirigidos a la Comisión de Texas de Calidad Ambiental, Oficial de la Secretaría (Office of Chief Clerk), MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia. Para obtener más información acerca de esta solicitud de permiso o el proceso de permisos, llame al programa de educación pública de la TCEQ, gratis, al 1-800-687-4040. Si desea información en Español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional del CSWR-Texas a la dirección indicada arriba o llamando a Amanda Sappington al 314-464-3976.

Fecha de emission: 30 de octubre de 2024

Texas Commission on Environmental Quality



COMBINED

NOTICE OF RECEIPT OF APPLICATION AND INTENT TO OBTAIN WATER QUALITY PERMIT (NORI)

AND

NOTICE OF APPLICATION AND PRELIMINARY DECISION FOR TPDES PERMIT FOR MUNICIPAL WASTEWATER

RENEWAL

PERMIT NO. WQ0013147001

APPLICATION AND PRELIMINARY DECISION. CSWR-Texas Utility Operating Company, LLC, **1630 Des Peres Road, Suite 140, Saint Louis, Missouri, 63131**, has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of Texas Pollutant Discharge Elimination System (TPDES) Permit No. WQ0013147001 which authorizes the discharge of treated domestic wastewater at a daily average flow not to exceed 65,000 gallons per day. TCEQ received this application on September 30, 2024.

This combined notice is being issued to update the applicant's address as provided in the NORI.

The facility is located at 404 Branding Iron, in Polk County, Texas 77351. The treated effluent is discharged directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin. The designated uses for Segment No. 0803 are primary contact recreation, public water supply, and high aquatic life use. All determinations are preliminary and subject to additional review and/or revisions. This link to an electronic map of the site or facility's general location is provided as a public courtesy and is not part of the application or notice. For the exact location, refer to the application.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-95.0346,30.7079&level=18>

The TCEQ Executive Director has completed the technical review of the application and prepared a draft permit. The draft permit, if approved, would establish the conditions under which the facility must operate. The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The permit application, Executive Director's preliminary decision, and draft permit are available for viewing and copying at Livingston Municipal Library,

707 North Tyler Avenue, Livingston, in Polk County, Texas. The application, including any updates, and associated notices are available electronically at the following webpage:

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

ALTERNATIVE LANGUAGE NOTICE. Alternative language notice in Spanish is available at <https://www.tceq.texas.gov/permitting/wastewater/plain-language-summaries-and-public-notice>. El aviso de idioma alternativo en español está disponible en <https://www.tceq.texas.gov/permitting/wastewater/plain-language-summaries-and-public-notice>.

PUBLIC COMMENT / PUBLIC MEETING. You may submit public comments or request a public meeting about this application. The purpose of a public meeting is to provide the opportunity to submit comments or to ask questions about the application. TCEQ holds a public meeting if the Executive Director determines that there is a significant degree of public interest in the application or if requested by a local legislator. A public meeting is not a contested case hearing.

OPPORTUNITY FOR A CONTESTED CASE HEARING. After the deadline for submitting public comments, the Executive Director will consider all timely comments and prepare a response to all relevant and material, or significant public comments. **Unless the application is directly referred for a contested case hearing, the response to comments will be mailed to everyone who submitted public comments and to those persons who are on the mailing list for this application. If comments are received, the mailing will also provide instructions for requesting a contested case hearing or reconsideration of the Executive Director's decision.** A contested case hearing is a legal proceeding similar to a civil trial in a state district court.

TO REQUEST A CONTESTED CASE HEARING, YOU MUST INCLUDE THE FOLLOWING ITEMS IN YOUR REQUEST: your name, address, phone number; applicant's name and proposed permit number; the location and distance of your property/activities relative to the proposed facility; a specific description of how you would be adversely affected by the facility in a way not common to the general public; a list of all disputed issues of fact that you submit during the comment period; and the statement "[I/we] request a contested case hearing." If the request for contested case hearing is filed on behalf of a group or association, the request must designate the group's representative for receiving future correspondence; identify by name and physical address an individual member of the group who would be adversely affected by the proposed facility or activity; provide the information discussed above regarding the affected member's location and distance from the facility or activity; explain how and why the member would be affected; and explain how the interests the group seeks to protect are relevant to the group's purpose.

Following the close of all applicable comment and request periods, the Executive Director will forward the application and any requests for reconsideration or for a contested case hearing to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

The Commission may only grant a request for a contested case hearing on issues the requestor submitted in their timely comments that were not subsequently withdrawn. **If a hearing is granted, the subject of a hearing will be limited to disputed issues of fact or mixed questions of fact and law relating to relevant and material water quality concerns submitted during the comment period. TCEQ may act on an application to renew a permit for discharge of wastewater without providing an opportunity for a contested case hearing if certain criteria are met.**

EXECUTIVE DIRECTOR ACTION. The Executive Director may issue final approval of the application unless a timely contested case hearing request or request for reconsideration is filed. If a timely hearing request or request for reconsideration is filed, the Executive Director will not issue final approval of the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting.

MAILING LIST. If you submit public comments, a request for a contested case hearing or a reconsideration of the Executive Director's decision, you will be added to the mailing list for this specific application to receive future public notices mailed by the Office of the Chief Clerk. In addition, you may request to be placed on: (1) the permanent mailing list for a specific applicant name and permit number; and/or (2) the mailing list for a specific county. If you wish to be placed on the permanent and/or the county mailing list, clearly specify which list(s) and send your request to TCEQ Office of the Chief Clerk at the address below.

All written public comments and public meeting requests must be submitted to the Office of the Chief Clerk, MC 105, Texas Commission on Environmental Quality, P.O. Box 13087, Austin, TX 78711-3087 or electronically at www.tceq.texas.gov/goto/comment within 30 days from the date of newspaper publication of this notice.

INFORMATION AVAILABLE ONLINE. For details about the status of the application, visit the Commissioners' Integrated Database at www.tceq.texas.gov/goto/cid. Search the database using the permit number for this application, which is provided at the top of this notice.

AGENCY CONTACTS AND INFORMATION. Public comments and requests must be submitted either electronically at www.tceq.texas.gov/goto/comment, or in writing to the Texas Commission on Environmental Quality, Office of the Chief Clerk, MC 105, P.O. Box 13087, Austin, Texas 78711-3087. Any personal information you submit to the TCEQ will become part of the agency's record; this includes email addresses. For more information about this permit application or the permitting process, please call the TCEQ Public Education Program, Toll Free, at 1-800-687-4040 or visit their website at www.tceq.texas.gov/goto/pep. Si desea información en Español, puede llamar al 1-800-687-4040.

Further information may also be obtained from CSWR-Texas Utility Operating Company, LLC at the address stated above or by calling Ms. Amanda Sappington, EHS Compliance Manager, at 314-464-3976.

Issuance Date: July 15, 2025

Comisión De Calidad Ambiental Del Estado De Texas



AVISO DE LA SOLICITUD Y DECISIÓN PRELIMINAR PARA EL PERMISO DEL SISTEMA DE ELIMINACION DE DESCARGAS DE CONTAMINANTES DE TEXAS (TPDES) PARA AGUAS RESIDUALES MUNICIPALES

RENOVACIÓN

PERMISO NO. WQ0013147001

SOLICITUD Y DECISIÓN PRELIMINAR. CSWR-Texas Utility Operating Company, LLC, **1630 Des Peres Road, Suite 140, Saint Louis, Missouri, 63131** ha solicitado a la Comisión de Calidad Ambiental del Estado de Texas (TCEQ) una renovación para autorizar La descarga de aguas residuales domésticas tratadas con un caudal promedio diario que no supere los 65,000 galones por día. La TCEQ recibió esta solicitud el 30 de septiembre de 2024.

La planta está ubicada en 404 Branding Iron en el Condado de Polk, Texas. El efluente tratado es descargado al Lake Livingston en el Segmento No. 0803 de la Cuenca del Río Trinity River Basin. Los usos designados para el Segmento No. 0803 son o uso excepcional de vida acuática; abastecimiento de agua potable, navegación y recreación de contacto primario.

El Director Ejecutivo de la TCEQ ha completado la revisión técnica de la solicitud y ha preparado un borrador del permiso. El borrador del permiso, si es aprobado, establecería las condiciones bajo las cuales la instalación debe operar. El Director Ejecutivo ha tomado una decisión preliminar que si este permiso es emitido, cumple con todos los requisitos normativos y legales. La solicitud del permiso, la decisión preliminar del Director Ejecutivo y el borrador del permiso están disponibles para leer y copiar en Biblioteca Municipal de Livingston, 707 North Tyler Avenue, Livingston, en el condado de Polk. La solicitud (cualquier actualización y aviso inclusive) está disponible electrónicamente en la siguiente página web:

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>. Este enlace a un mapa electrónico de la ubicación general del sitio o de la instalación es proporcionado como una cortesía y no es parte de la solicitud o del aviso. Para la ubicación exacta, consulte la solicitud.

<https://gisweb.tceq.texas.gov/LocationMapper/?marker=-95.0346,30.7079&level=18>

AVISO DE IDIOMA ALTERNATIVO. El aviso de idioma alternativo en español está disponible en <https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

COMENTARIO PUBLICO / REUNION PUBLICA. Usted puede presentar **comentarios públicos o pedir una reunión pública sobre esta solicitud.** El propósito de una reunión pública es dar la oportunidad de presentar comentarios o hacer preguntas acerca de la solicitud. La TCEQ realiza una reunión pública si el Director Ejecutivo determina que hay un grado de interés público suficiente en la solicitud o si un legislador local lo pide. Una reunión pública no es una audiencia administrativa de lo contencioso.

OPORTUNIDAD DE UNA AUDIENCIA ADMINISTRATIVA DE LO CONTENCIOSO. Después del plazo para presentar comentarios públicos, el Director Ejecutivo considerará todos los comentarios apropiados y preparará una respuesta a todos los comentarios públicos esenciales, pertinentes, o significativos. **A menos que la solicitud haya sido referida directamente a una audiencia administrativa de lo contencioso, la respuesta a los comentarios y la decisión del Director Ejecutivo sobre la solicitud serán enviados por correo a todos los que presentaron un comentario público y a las personas que están en la lista para recibir avisos sobre esta solicitud. Si se reciben comentarios, el aviso también proveerá instrucciones para pedir una reconsideración de la decisión del Director Ejecutivo y para pedir una audiencia administrativa de lo contencioso.** Una audiencia administrativa de lo contencioso es un procedimiento legal similar a un procedimiento legal civil en un tribunal de distrito del estado.

PARA SOLICITAR UNA AUDIENCIA DE CASO IMPUGNADO, USTED DEBE INCLUIR EN SU SOLICITUD LOS SIGUIENTES DATOS: su nombre, dirección, y número de teléfono; el nombre del solicitante y número del permiso; la ubicación y distancia de su propiedad/actividad con respecto a la instalación; una descripción específica de la forma cómo usted sería afectado adversamente por el sitio de una manera no común al público en general; una lista de todas las cuestiones de hecho en disputa que usted presente durante el período de comentarios; y la declaración "[Yo/nosotros] solicito/solicitamos una audiencia de caso impugnado". Si presenta la petición para una audiencia de caso impugnado de parte de un grupo o asociación, debe identificar una persona que representa al grupo para recibir correspondencia en el futuro; identificar el nombre y la dirección de un miembro del grupo que sería afectado adversamente por la planta o la actividad propuesta; proveer la información indicada anteriormente con respecto a la ubicación del miembro afectado y su distancia de la planta o actividad propuesta; explicar cómo y porqué el miembro sería afectado; y explicar cómo los intereses que el grupo desea proteger son pertinentes al propósito del grupo.

Después del cierre de todos los períodos de comentarios y de petición que aplican, el Director Ejecutivo enviará la solicitud y cualquier petición para reconsideración o para una audiencia de caso impugnado a los Comisionados de la TCEQ para su consideración durante una reunión programada de la Comisión. La Comisión sólo puede conceder una solicitud de una audiencia de caso impugnado sobre los temas que el solicitante haya presentado en sus comentarios oportunos que no fueron retirados posteriormente. Si se concede una audiencia, el tema de la audiencia estará limitado a cuestiones de hecho en disputa o cuestiones mixtas de hecho y de derecho relacionadas a intereses pertinentes y materiales de calidad del agua que se hayan presentado durante el período de comentarios. Si ciertos criterios se cumplen, la TCEQ puede actuar sobre una solicitud para renovar un permiso para descargar aguas residuales sin proveer una oportunidad de una audiencia administrativa de lo contencioso.

ACCIÓN DEL DIRECTOR EJECUTIVO. El Director Ejecutivo puede emitir una aprobación final de la solicitud a menos que exista un pedido antes del plazo de vencimiento de una audiencia administrativa de lo contencioso o se ha presentado un pedido de reconsideración. Si un pedido ha llegado antes del plazo de vencimiento de la audiencia o el pedido de reconsideración ha sido presentado, el Director Ejecutivo no emitirá una aprobación final sobre el permiso y enviará la solicitud y el pedido a los Comisionados de la TECQ para consideración en una reunión programada de la Comisión.

LISTA DE CORREO. Si somete comentarios públicos, un pedido para una audiencia administrativa de lo contencioso o una reconsideración de la decisión del Director Ejecutivo, la Oficina del Secretario Principal enviará por correo los avisos públicos en relación con la solicitud. Además, puede pedir que la TCEQ ponga su nombre en una o más de las listas de correos siguientes (1) la lista de correo permanente para recibir los avisos de el solicitante indicado por nombre y número del permiso específico y/o (2) la lista de correo de todas las solicitudes en un condado específico. Si desea que se agregue su nombre en una de las listas designe cual lista(s) y envía por correo su pedido a la Oficina del Secretario Principal de la TCEQ.

Todos los comentarios escritos del público y los pedidos una reunión deben ser presentados durante los 30 días después de la publicación del aviso a la Oficina del Secretario Principal, MC 105, TCEQ, P.O. Box 13087, Austin, TX 78711-3087 or por el internet a www.tceq.texas.gov/about/comments.html. Tenga en cuenta que cualquier información personal que usted proporcione, incluyendo su nombre, número de teléfono, dirección de correo electrónico y dirección física pasarán a formar parte del registro público de la Agencia.

CONTACTOS E INFORMACIÓN DE LA AGENCIA. Los comentarios y solicitudes públicas deben enviarse electrónicamente a <https://www14.tceq.texas.gov/epic/eComment/>, o por escrito a Texas Commission on Environmental Quality, Office of the Chief Clerk, MC-105, P.O. Box 13087, Austin, Texas 78711-3087. Cualquier información personal que envíe a la TCEQ pasará a formar parte del registro de la agencia; esto incluye las direcciones de correo electrónico. Para obtener más información sobre esta solicitud de permiso o el proceso de permisos, llame al Programa de Educación Pública de la TCEQ, sin cargo, al 1-800-687-4040 o visite su sitio web en www.tceq.texas.gov/goto/pep. Si desea información en español, puede llamar al 1-800-687-4040.

También se puede obtener información adicional del CSWR-Texas Utility Operating Company, LLC, a la dirección indicada arriba o llamando a Amanda Sappington al 314-464-3976.

Fecha de emisión 15 de julio de 2025



TPDES PERMIT NO. WQ0013147001
*[For TCEQ office use only - EPA I.D.
No. TX0098809]*

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
P.O. Box 13087
Austin, Texas 78711-3087

This is a renewal that replaces TPDES
Permit No. WQ0013147001 issued on
March 9, 2020.

PERMIT TO DISCHARGE WASTES
under provisions of
Section 402 of the Clean Water Act
and Chapter 26 of the Texas Water Code

CSWR-Texas Utility Operating Company, LLC

whose mailing address is

1630 Des Peres Road, Suite 140
Saint Louis, Missouri, 63131

is authorized to treat and discharge wastes from the Texas Landing Wastewater Treatment
Facility, SIC Code 4952

located at 404 Branding Iron, in Polk County, Texas 77351

directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin

only according to effluent limitations, monitoring requirements, and other conditions set forth
in this permit, as well as the rules of the Texas Commission on Environmental Quality (TCEQ),
the laws of the State of Texas, and other orders of the TCEQ. The issuance of this permit does
not grant to the permittee the right to use private or public property for conveyance of
wastewater along the discharge route described in this permit. This includes, but is not limited
to, property belonging to any individual, partnership, corporation or other entity. Neither does
this permit authorize any invasion of personal rights nor any violation of federal, state, or local
laws or regulations. It is the responsibility of the permittee to acquire property rights as may be
necessary to use the discharge route.

This permit shall expire at midnight, **five years from the date of issuance.**

ISSUED DATE:

For the Commission

EFFLUENT LIMITATIONS AND MONITORING REQUIREMENTSOutfall Number 001

1. During the period beginning upon the date of issuance and lasting through the date of expiration, the permittee is authorized to discharge subject to the following effluent limitations:

The daily average flow of effluent shall not exceed 0.065 million gallons per day (MGD), nor shall the average discharge during any two-hour period (2-hour peak) exceed 181 gallons per minute (gpm).

<u>Effluent Characteristic</u>	<u>Discharge Limitations</u>				<u>Min. Self-Monitoring Requirements</u>	
	Daily Avg mg/l (lbs/day)	7-day Avg mg/l	Daily Max mg/l	Single Grab mg/l	Report Daily Avg. & Max. Single Grab Measurement Frequency	Sample Type
Flow, MGD	Report	N/A	Report	N/A	Continuous	Totalizing Meter
Biochemical Oxygen Demand (5-day)	10 (5.4)	15	25	35	One/week	Grab
Total Suspended Solids	15 (8.1)	25	40	60	One/week	Grab
<i>E. coli</i> , colony-forming units or most probable number per 100 ml	126	N/A	N/A	399	One/quarter	Grab

2. The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes (based on peak flow), and shall be monitored five times per week by grab sample. An equivalent method of disinfection may be substituted only with prior approval of the Executive Director.
3. The pH shall not be less than 6.0 standard units nor greater than 9.0 standard units and shall be monitored once per month by grab sample.
4. There shall be no discharge of floating solids or visible foam in other than trace amounts and no discharge of visible oil.
5. Effluent monitoring samples shall be taken at the following location(s): Following the final treatment unit.
6. The effluent shall contain a minimum dissolved oxygen of 4.0 mg/l and shall be monitored once per week by grab sample.

DEFINITIONS AND STANDARD PERMIT CONDITIONS

As required by Title 30 Texas Administrative Code (TAC) Chapter 305, certain regulations appear as standard conditions in waste discharge permits. 30 TAC § 305.121 - 305.129 (relating to Permit Characteristics and Conditions) as promulgated under the Texas Water Code (TWC) §§ 5.103 and 5.105, and the Texas Health and Safety Code (THSC) §§ 361.017 and 361.024(a), establish the characteristics and standards for waste discharge permits, including sewage sludge, and those sections of 40 Code of Federal Regulations (CFR) Part 122 adopted by reference by the Commission. The following text includes these conditions and incorporates them into this permit. All definitions in TWC § 26.001 and 30 TAC Chapter 305 shall apply to this permit and are incorporated by reference. Some specific definitions of words or phrases used in this permit are as follows:

1. Flow Measurements

- a. Annual average flow - the arithmetic average of all daily flow determinations taken within the preceding 12 consecutive calendar months. The annual average flow determination shall consist of daily flow volume determinations made by a totalizing meter, charted on a chart recorder and limited to major domestic wastewater discharge facilities with one million gallons per day or greater permitted flow.
- b. Daily average flow - the arithmetic average of all determinations of the daily flow within a period of one calendar month. The daily average flow determination shall consist of determinations made on at least four separate days. If instantaneous measurements are used to determine the daily flow, the determination shall be the arithmetic average of all instantaneous measurements taken during that month. Daily average flow determination for intermittent discharges shall consist of a minimum of three flow determinations on days of discharge.
- c. Daily maximum flow - the highest total flow for any 24-hour period in a calendar month.
- d. Instantaneous flow - the measured flow during the minimum time required to interpret the flow measuring device.
- e. 2-hour peak flow (domestic wastewater treatment plants) - the maximum flow sustained for a two-hour period during the period of daily discharge. The average of multiple measurements of instantaneous maximum flow within a two-hour period may be used to calculate the 2-hour peak flow.
- f. Maximum 2-hour peak flow (domestic wastewater treatment plants) - the highest 2-hour peak flow for any 24-hour period in a calendar month.

2. Concentration Measurements

- a. Daily average concentration - the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar month, consisting of at least four separate representative measurements.
 - i. For domestic wastewater treatment plants - When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values in the previous four consecutive month period consisting of at least four measurements shall be utilized as the daily average concentration.

- ii. For all other wastewater treatment plants - When four samples are not available in a calendar month, the arithmetic average (weighted by flow) of all values taken during the month shall be utilized as the daily average concentration.
- b. 7-day average concentration - the arithmetic average of all effluent samples, composite or grab as required by this permit, within a period of one calendar week, Sunday through Saturday.
- c. Daily maximum concentration - the maximum concentration measured on a single day, by the sample type specified in the permit, within a period of one calendar month.
- d. Daily discharge - the discharge of a pollutant measured during a calendar day or any 24-hour period that reasonably represents the calendar day for purposes of sampling. For pollutants with limitations expressed in terms of mass, the daily discharge is calculated as the total mass of the pollutant discharged over the sampling day. For pollutants with limitations expressed in other units of measurement, the daily discharge is calculated as the average measurement of the pollutant over the sampling day.

The daily discharge determination of concentration made using a composite sample shall be the concentration of the composite sample. When grab samples are used, the daily discharge determination of concentration shall be the arithmetic average (weighted by flow value) of all samples collected during that day.

- e. Bacteria concentration (*E. coli* or Enterococci) - Colony Forming Units (CFU) or Most Probable Number (MPN) of bacteria per 100 milliliters effluent. The daily average bacteria concentration is a geometric mean of the values for the effluent samples collected in a calendar month. The geometric mean shall be determined by calculating the n th root of the product of all measurements made in a calendar month, where n equals the number of measurements made; or, computed as the antilogarithm of the arithmetic mean of the logarithms of all measurements made in a calendar month. For any measurement of bacteria equaling zero, a substituted value of one shall be made for input into either computation method. If specified, the 7-day average for bacteria is the geometric mean of the values for all effluent samples collected during a calendar week.
 - f. Daily average loading (lbs/day) - the arithmetic average of all daily discharge loading calculations during a period of one calendar month. These calculations must be made for each day of the month that a parameter is analyzed. The daily discharge, in terms of mass (lbs/day), is calculated as (Flow, MGD x Concentration, mg/l x 8.34).
 - g. Daily maximum loading (lbs/day) - the highest daily discharge, in terms of mass (lbs/day), within a period of one calendar month.
3. Sample Type
- a. Composite sample - For domestic wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (a). For industrial wastewater, a composite sample is a sample made up of a minimum of three effluent portions collected in a continuous 24-hour period or during the period of daily discharge if less than 24 hours, and combined in volumes proportional to flow, and collected at the intervals required by 30 TAC § 319.9 (b).

- b. Grab sample - an individual sample collected in less than 15 minutes.
- 4. Treatment Facility (facility) - wastewater facilities used in the conveyance, storage, treatment, recycling, reclamation and/or disposal of domestic sewage, industrial wastes, agricultural wastes, recreational wastes, or other wastes including sludge handling or disposal facilities under the jurisdiction of the Commission.
- 5. The term "sewage sludge" is defined as solid, semi-solid, or liquid residue generated during the treatment of domestic sewage in 30 TAC Chapter 312. This includes the solids that have not been classified as hazardous waste separated from wastewater by unit processes.
- 6. The term "biosolids" is defined as sewage sludge that has been tested or processed to meet Class A, Class AB, or Class B pathogen standards in 30 TAC Chapter 312 for beneficial use.
- 7. Bypass - the intentional diversion of a waste stream from any portion of a treatment facility.

MONITORING AND REPORTING REQUIREMENTS

1. Self-Reporting

Monitoring results shall be provided at the intervals specified in the permit. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall conduct effluent sampling and reporting in accordance with 30 TAC §§ 319.4 - 319.12. Unless otherwise specified, effluent monitoring data shall be submitted each month, to the Enforcement Division (MC 224), by the 20th day of the following month for each discharge which is described by this permit whether or not a discharge is made for that month. Monitoring results must be submitted online using the NetDMR reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. Monitoring results must be signed and certified as required by Monitoring and Reporting Requirements No. 10.

As provided by state law, the permittee is subject to administrative, civil and criminal penalties, as applicable, for negligently or knowingly violating the Clean Water Act (CWA); TWC §§ 26, 27, and 28; and THSC § 361, including but not limited to knowingly making any false statement, representation, or certification on any report, record, or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance, or falsifying, tampering with or knowingly rendering inaccurate any monitoring device or method required by this permit or violating any other requirement imposed by state or federal regulations.

2. Test Procedures

- a. Unless otherwise specified in this permit, test procedures for the analysis of pollutants shall comply with procedures specified in 30 TAC §§ 319.11 - 319.12. Measurements, tests, and calculations shall be accurately accomplished in a representative manner.
- b. All laboratory tests submitted to demonstrate compliance with this permit must meet the requirements of 30 TAC § 25, Environmental Testing Laboratory Accreditation and Certification.

3. Records of Results

- a. Monitoring samples and measurements shall be taken at times and in a manner so as to be representative of the monitored activity.

- b. Except for records of monitoring information required by this permit related to the permittee's sewage sludge or biosolids use and disposal activities, which shall be retained for a period of at least five years (or longer as required by 40 CFR Part 503), monitoring and reporting records, including strip charts and records of calibration and maintenance, copies of all records required by this permit, records of all data used to complete the application for this permit, and the certification required by 40 CFR § 264.73(b)(9) shall be retained at the facility site, or shall be readily available for review by a TCEQ representative for a period of three years from the date of the record or sample, measurement, report, application or certification. This period shall be extended at the request of the Executive Director.
- c. Records of monitoring activities shall include the following:
 - i. date, time and place of sample or measurement;
 - ii. identity of individual who collected the sample or made the measurement.
 - iii. date and time of analysis;
 - iv. identity of the individual and laboratory who performed the analysis;
 - v. the technique or method of analysis; and
 - vi. the results of the analysis or measurement and quality assurance/quality control records.

The period during which records are required to be kept shall be automatically extended to the date of the final disposition of any administrative or judicial enforcement action that may be instituted against the permittee.

4. Additional Monitoring by Permittee

If the permittee monitors any pollutant at the location(s) designated herein more frequently than required by this permit using approved analytical methods as specified above, all results of such monitoring shall be included in the calculation and reporting of the values submitted on the approved self-report form. Increased frequency of sampling shall be indicated on the self-report form.

5. Calibration of Instruments

All automatic flow measuring or recording devices and all totalizing meters for measuring flows shall be accurately calibrated by a trained person at plant start-up and as often thereafter as necessary to ensure accuracy, but not less often than annually unless authorized by the Executive Director for a longer period. Such person shall verify in writing that the device is operating properly and giving accurate results. Copies of the verification shall be retained at the facility site and/or shall be readily available for review by a TCEQ representative for a period of three years.

6. Compliance Schedule Reports

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of the permit shall be submitted no later than 14 days following each schedule date to the Regional Office and the Enforcement

Division (MC 224).

7. Noncompliance Notification

- a. In accordance with 30 TAC § 305.125(9) any noncompliance which may endanger human health or safety, or the environment shall be reported by the permittee to the TCEQ. Except as allowed by 30 TAC § 305.132, report of such information shall be provided orally or by facsimile transmission (FAX) to the Regional Office within 24 hours of becoming aware of the noncompliance. A written submission of such information shall also be provided by the permittee to the Regional Office and the Enforcement Division (MC 224) within five working days of becoming aware of the noncompliance. For Publicly Owned Treatment Works (POTWs), effective December 21, 2025, the permittee must submit the written report for unauthorized discharges and unanticipated bypasses that exceed any effluent limit in the permit using the online electronic reporting system available through the TCEQ website unless the permittee requests and obtains an electronic reporting waiver. The written submission shall contain a description of the noncompliance and its cause; the potential danger to human health or safety, or the environment; the period of noncompliance, including exact dates and times; if the noncompliance has not been corrected, the time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance, and to mitigate its adverse effects.
 - b. The following violations shall be reported under Monitoring and Reporting Requirement 7.a.:
 - i. Unauthorized discharges as defined in Permit Condition 2(g).
 - ii. Any unanticipated bypass that exceeds any effluent limitation in the permit.
 - iii. Violation of a permitted maximum daily discharge limitation for pollutants listed specifically in the Other Requirements section of an Industrial TPDES permit.
 - c. In addition to the above, any effluent violation which deviates from the permitted effluent limitation by more than 40% shall be reported by the permittee in writing to the Regional Office and the Enforcement Division (MC 224) within 5 working days of becoming aware of the noncompliance.
 - d. Any noncompliance other than that specified in this section, or any required information not submitted or submitted incorrectly, shall be reported to the Enforcement Division (MC 224) as promptly as possible. For effluent limitation violations, noncompliances shall be reported on the approved self-report form.
8. In accordance with the procedures described in 30 TAC §§ 35.301 - 35.303 (relating to Water Quality Emergency and Temporary Orders) if the permittee knows in advance of the need for a bypass, it shall submit prior notice by applying for such authorization.
9. Changes in Discharges of Toxic Substances

All existing manufacturing, commercial, mining, and silvicultural permittees shall notify the Regional Office, orally or by facsimile transmission within 24 hours, and both the Regional Office and the Enforcement Division (MC 224) in writing within five (5) working days, after becoming aware of or having reason to believe:

- a. That any activity has occurred or will occur which would result in the discharge, on a routine or frequent basis, of any toxic pollutant listed at 40 CFR Part 122, Appendix D, Tables II and III (excluding Total Phenols) which is not limited in the permit, if that discharge will exceed the highest of the following “notification levels”:
 - i. One hundred micrograms per liter (100 µg/L);
 - ii. Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile; five hundred micrograms per liter (500 µg/L) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol; and one milligram per liter (1 mg/L) for antimony;
 - iii. Five (5) times the maximum concentration value reported for that pollutant in the permit application; or
 - iv. The level established by the TCEQ.
- b. That any activity has occurred or will occur which would result in any discharge, on a nonroutine or infrequent basis, of a toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following “notification levels”:
 - i. Five hundred micrograms per liter (500 µg/L);
 - ii. One milligram per liter (1 mg/L) for antimony;
 - iii. Ten (10) times the maximum concentration value reported for that pollutant in the permit application; or
 - iv. The level established by the TCEQ.

10. Signatories to Reports

All reports and other information requested by the Executive Director shall be signed by the person and in the manner required by 30 TAC § 305.128 (relating to Signatories to Reports).

11. All POTWs must provide adequate notice to the Executive Director of the following:

- a. Any new introduction of pollutants into the POTW from an indirect discharger which would be subject to CWA § 301 or § 306 if it were directly discharging those pollutants;
- b. Any substantial change in the volume or character of pollutants being introduced into that POTW by a source introducing pollutants into the POTW at the time of issuance of the permit; and
- c. For the purpose of this paragraph, adequate notice shall include information on:
 - i. The quality and quantity of effluent introduced into the POTW; and
 - ii. Any anticipated impact of the change on the quantity or quality of effluent to be discharged from the POTW.

PERMIT CONDITIONS**1. General**

- a. When the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in an application or in any report to the Executive Director, it shall promptly submit such facts or information.
- b. This permit is granted on the basis of the information supplied and representations made by the permittee during action on an application, and relying upon the accuracy and completeness of that information and those representations. After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked, in whole or in part, in accordance with 30 TAC Chapter 305, Subchapter D, during its term for good cause including, but not limited to, the following:
 - i. Violation of any terms or conditions of this permit;
 - ii. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts; or
 - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- c. The permittee shall furnish to the Executive Director, upon request and within a reasonable time, any information to determine whether cause exists for amending, revoking, suspending or terminating the permit. The permittee shall also furnish to the Executive Director, upon request, copies of records required to be kept by the permit.

2. Compliance

- a. Acceptance of the permit by the person to whom it is issued constitutes acknowledgment and agreement that such person will comply with all the terms and conditions embodied in the permit, and the rules and other orders of the Commission.
- b. The permittee has a duty to comply with all conditions of the permit. Failure to comply with any permit condition constitutes a violation of the permit and the Texas Water Code or the Texas Health and Safety Code, and is grounds for enforcement action, for permit amendment, revocation, or suspension, or for denial of a permit renewal application or an application for a permit for another facility.
- c. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of the permit.
- d. The permittee shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal or other permit violation that has a reasonable likelihood of adversely affecting human health or the environment.
- e. Authorization from the Commission is required before beginning any change in the permitted facility or activity that may result in noncompliance with any permit requirements.
- f. A permit may be amended, suspended and reissued, or revoked for cause in accordance

with 30 TAC §§ 305.62 and 305.66 and TWC§ 7.302. The filing of a request by the permittee for a permit amendment, suspension and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

- g. There shall be no unauthorized discharge of wastewater or any other waste. For the purpose of this permit, an unauthorized discharge is considered to be any discharge of wastewater into or adjacent to water in the state at any location not permitted as an outfall or otherwise defined in the Other Requirements section of this permit.
- h. In accordance with 30 TAC § 305.535(a), the permittee may allow any bypass to occur from a TPDES permitted facility which does not cause permitted effluent limitations to be exceeded or an unauthorized discharge to occur, but only if the bypass is also for essential maintenance to assure efficient operation.
- i. The permittee is subject to administrative, civil, and criminal penalties, as applicable, under TWC §§ 7.051 - 7.075 (relating to Administrative Penalties), 7.101 - 7.111 (relating to Civil Penalties), and 7.141 - 7.202 (relating to Criminal Offenses and Penalties) for violations including, but not limited to, negligently or knowingly violating the federal CWA §§ 301, 302, 306, 307, 308, 318, or 405, or any condition or limitation implementing any sections in a permit issued under the CWA § 402, or any requirement imposed in a pretreatment program approved under the CWA §§ 402 (a)(3) or 402 (b)(8).

3. Inspections and Entry

- a. Inspection and entry shall be allowed as prescribed in the TWC Chapters 26, 27, and 28, and THSC § 361.
- b. The members of the Commission and employees and agents of the Commission are entitled to enter any public or private property at any reasonable time for the purpose of inspecting and investigating conditions relating to the quality of water in the state or the compliance with any rule, regulation, permit or other order of the Commission. Members, employees, or agents of the Commission and Commission contractors are entitled to enter public or private property at any reasonable time to investigate or monitor or, if the responsible party is not responsive or there is an immediate danger to public health or the environment, to remove or remediate a condition related to the quality of water in the state. Members, employees, Commission contractors, or agents acting under this authority who enter private property shall observe the establishment's rules and regulations concerning safety, internal security, and fire protection, and if the property has management in residence, shall notify management or the person then in charge of his presence and shall exhibit proper credentials. If any member, employee, Commission contractor, or agent is refused the right to enter in or on public or private property under this authority, the Executive Director may invoke the remedies authorized in TWC § 7.002. The statement above, that Commission entry shall occur in accordance with an establishment's rules and regulations concerning safety, internal security, and fire protection, is not grounds for denial or restriction of entry to any part of the facility, but merely describes the Commission's duty to observe appropriate rules and regulations during an inspection.

4. Permit Amendment and/or Renewal

- a. The permittee shall give notice to the Executive Director as soon as possible of any planned physical alterations or additions to the permitted facility if such alterations or additions would require a permit amendment or result in a violation of permit requirements. Notice shall also be required under this paragraph when:
 - i. The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in accordance with 30 TAC § 305.534 (relating to New Sources and New Dischargers); or
 - ii. The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are subject neither to effluent limitations in the permit, nor to notification requirements in Monitoring and Reporting Requirements No. 9; or
 - iii. The alteration or addition results in a significant change in the permittee's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan.
- b. Prior to any facility modifications, additions, or expansions that will increase the plant capacity beyond the permitted flow, the permittee must apply for and obtain proper authorization from the Commission before commencing construction.
- c. The permittee must apply for an amendment or renewal at least 180 days prior to expiration of the existing permit in order to continue a permitted activity after the expiration date of the permit. If an application is submitted prior to the expiration date of the permit, the existing permit shall remain in effect until the application is approved, denied, or returned. If the application is returned or denied, authorization to continue such activity shall terminate upon the effective date of the action. If an application is not submitted prior to the expiration date of the permit, the permit shall expire and authorization to continue such activity shall terminate.
- d. Prior to accepting or generating wastes which are not described in the permit application or which would result in a significant change in the quantity or quality of the existing discharge, the permittee must report the proposed changes to the Commission. The permittee must apply for a permit amendment reflecting any necessary changes in permit conditions, including effluent limitations for pollutants not identified and limited by this permit.
- e. In accordance with the TWC § 26.029(b), after a public hearing, notice of which shall be given to the permittee, the Commission may require the permittee, from time to time, for good cause, in accordance with applicable laws, to conform to new or additional conditions.
- f. If any toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under CWA § 307(a) for a toxic pollutant which is present in the discharge and that standard or prohibition is more stringent than any limitation on the pollutant in this permit, this permit shall be modified or revoked and reissued to conform to the toxic effluent standard or

prohibition. The permittee shall comply with effluent standards or prohibitions established under CWA § 307(a) for toxic pollutants within the time provided in the regulations that established those standards or prohibitions, even if the permit has not yet been modified to incorporate the requirement.

5. Permit Transfer

- a. Prior to any transfer of this permit, Commission approval must be obtained. The Commission shall be notified in writing of any change in control or ownership of facilities authorized by this permit. Such notification should be sent to the Applications Review and Processing Team (MC 148) of the Water Quality Division.
- b. A permit may be transferred only according to the provisions of 30 TAC § 305.64 (relating to Transfer of Permits) and 30 TAC § 50.133 (relating to Executive Director Action on Application or WQMP update).

6. Relationship to Hazardous Waste Activities

This permit does not authorize any activity of hazardous waste storage, processing, or disposal that requires a permit or other authorization pursuant to the Texas Health and Safety Code.

7. Relationship to Water Rights

Disposal of treated effluent by any means other than discharge directly to water in the state must be specifically authorized in this permit and may require a permit pursuant to TWC Chapter 11.

8. Property Rights

A permit does not convey any property rights of any sort, or any exclusive privilege.

9. Permit Enforceability

The conditions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstances, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

10. Relationship to Permit Application

The application pursuant to which the permit has been issued is incorporated herein; provided, however, that in the event of a conflict between the provisions of this permit and the application, the provisions of the permit shall control.

11. Notice of Bankruptcy

- a. Each permittee shall notify the Executive Director, in writing, immediately following the filing of a voluntary or involuntary petition for bankruptcy under any chapter of Title 11 (Bankruptcy) of the United States Code (11 USC) by or against:
 - i. the permittee;
 - ii. an entity (as that term is defined in 11 USC, § 101(14)) controlling the permittee or listing the permit or permittee as property of the estate; or

- iii. an affiliate (as that term is defined in 11 USC, § 101(2)) of the permittee.
- b. This notification must indicate:
 - i. the name of the permittee;
 - ii. the permit number(s);
 - iii. the bankruptcy court in which the petition for bankruptcy was filed; and
 - iv. the date of filing of the petition.

OPERATIONAL REQUIREMENTS

1. The permittee shall at all times ensure that the facility and all of its systems of collection, treatment, and disposal are properly operated and maintained. This includes, but is not limited to, the regular, periodic examination of wastewater solids within the treatment plant by the operator in order to maintain an appropriate quantity and quality of solids inventory as described in the various operator training manuals and according to accepted industry standards for process control. Process control, maintenance, and operations records shall be retained at the facility site, or shall be readily available for review by a TCEQ representative, for a period of three years.
2. Upon request by the Executive Director, the permittee shall take appropriate samples and provide proper analysis in order to demonstrate compliance with Commission rules. Unless otherwise specified in this permit or otherwise ordered by the Commission, the permittee shall comply with all applicable provisions of 30 TAC Chapter 312 concerning sewage sludge or biosolids use and disposal and 30 TAC §§ 319.21 - 319.29 concerning the discharge of certain hazardous metals.
3. Domestic wastewater treatment facilities shall comply with the following provisions:
 - a. The permittee shall notify the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, in writing, of any facility expansion at least 90 days prior to conducting such activity.
 - b. The permittee shall submit a closure plan for review and approval to the Municipal Permits Team, Wastewater Permitting Section (MC 148) of the Water Quality Division, for any closure activity at least 90 days prior to conducting such activity. Closure is the act of permanently taking a waste management unit or treatment facility out of service and includes the permanent removal from service of any pit, tank, pond, lagoon, surface impoundment and/or other treatment unit regulated by this permit.
4. The permittee is responsible for installing prior to plant start-up, and subsequently maintaining, adequate safeguards to prevent the discharge of untreated or inadequately treated wastes during electrical power failures by means of alternate power sources, standby generators, and/or retention of inadequately treated wastewater.
5. Unless otherwise specified, the permittee shall provide a readily accessible sampling point and, where applicable, an effluent flow measuring device or other acceptable means by which effluent flow may be determined.

6. The permittee shall remit an annual water quality fee to the Commission as required by 30 TAC Chapter 21. Failure to pay the fee may result in revocation of this permit under TWC § 7.302(b)(6).

7. Documentation

For all written notifications to the Commission required of the permittee by this permit, the permittee shall keep and make available a copy of each such notification under the same conditions as self-monitoring data are required to be kept and made available. Except for information required for TPDES permit applications, effluent data, including effluent data in permits, draft permits and permit applications, and other information specified as not confidential in 30 TAC §§ 1.5(d), any information submitted pursuant to this permit may be claimed as confidential by the submitter. Any such claim must be asserted in the manner prescribed in the application form or by stamping the words confidential business information on each page containing such information. If no claim is made at the time of submission, information may be made available to the public without further notice. If the Commission or Executive Director agrees with the designation of confidentiality, the TCEQ will not provide the information for public inspection unless required by the Texas Attorney General or a court pursuant to an open records request. If the Executive Director does not agree with the designation of confidentiality, the person submitting the information will be notified.

8. Facilities that generate domestic wastewater shall comply with the following provisions; domestic wastewater treatment facilities at permitted industrial sites are excluded.
 - a. Whenever flow measurements for any domestic sewage treatment facility reach 75% of the permitted daily average or annual average flow for three consecutive months, the permittee must initiate engineering and financial planning for expansion and/or upgrading of the domestic wastewater treatment and/or collection facilities. Whenever the flow reaches 90% of the permitted daily average or annual average flow for three consecutive months, the permittee shall obtain necessary authorization from the Commission to commence construction of the necessary additional treatment and/or collection facilities. In the case of a domestic wastewater treatment facility which reaches 75% of the permitted daily average or annual average flow for three consecutive months, and the planned population to be served or the quantity of waste produced is not expected to exceed the design limitations of the treatment facility, the permittee shall submit an engineering report supporting this claim to the Executive Director of the Commission.

If in the judgment of the Executive Director the population to be served will not cause permit noncompliance, then the requirement of this section may be waived. To be effective, any waiver must be in writing and signed by the Director of the Enforcement Division (MC 219) of the Commission, and such waiver of these requirements will be reviewed upon expiration of the existing permit; however, any such waiver shall not be interpreted as condoning or excusing any violation of any permit parameter.

- b. The plans and specifications for domestic sewage collection and treatment works associated with any domestic permit must be approved by the Commission and failure to secure approval before commencing construction of such works or making a discharge is a violation of this permit and each day is an additional violation until approval has been

secured.

- c. Permits for domestic wastewater treatment plants are granted subject to the policy of the Commission to encourage the development of area-wide waste collection, treatment, and disposal systems. The Commission reserves the right to amend any domestic wastewater permit in accordance with applicable procedural requirements to require the system covered by this permit to be integrated into an area-wide system, should such be developed; to require the delivery of the wastes authorized to be collected in, treated by or discharged from said system, to such area-wide system; or to amend this permit in any other particular to effectuate the Commission's policy. Such amendments may be made when the changes required are advisable for water quality control purposes and are feasible on the basis of waste treatment technology, engineering, financial, and related considerations existing at the time the changes are required, exclusive of the loss of investment in or revenues from any then existing or proposed waste collection, treatment or disposal system.
9. Domestic wastewater treatment plants shall be operated and maintained by sewage plant operators holding a valid certificate of competency at the required level as defined in 30 TAC Chapter 30.
 10. For Publicly Owned Treatment Works (POTWs), the 30-day average (or monthly average) percent removal for BOD and TSS shall not be less than 85%, unless otherwise authorized by this permit.
 11. Facilities that generate industrial solid waste as defined in 30 TAC § 335.1 shall comply with these provisions:
 - a. Any solid waste, as defined in 30 TAC § 335.1 (including but not limited to such wastes as garbage, refuse, sludge from a waste treatment, water supply treatment plant or air pollution control facility, discarded materials, discarded materials to be recycled, whether the waste is solid, liquid, or semisolid), generated by the permittee during the management and treatment of wastewater, must be managed in accordance with all applicable provisions of 30 TAC Chapter 335, relating to Industrial Solid Waste Management.
 - b. Industrial wastewater that is being collected, accumulated, stored, or processed before discharge through any final discharge outfall, specified by this permit, is considered to be industrial solid waste until the wastewater passes through the actual point source discharge and must be managed in accordance with all applicable provisions of 30 TAC Chapter 335.
 - c. The permittee shall provide written notification, pursuant to the requirements of 30 TAC § 335.8(b)(1), to the Corrective Action Section (MC 127) of the Remediation Division informing the Commission of any closure activity involving an Industrial Solid Waste Management Unit, at least 90 days prior to conducting such an activity.
 - d. Construction of any industrial solid waste management unit requires the prior written notification of the proposed activity to the Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division. No person shall dispose of industrial solid waste, including sludge or other solids from wastewater treatment processes, prior to fulfilling the deed recordation requirements of 30 TAC § 335.5.

- e. The term “industrial solid waste management unit” means a landfill, surface impoundment, waste-pile, industrial furnace, incinerator, cement kiln, injection well, container, drum, salt dome waste containment cavern, or any other structure vessel, appurtenance, or other improvement on land used to manage industrial solid waste.
- f. The permittee shall keep management records for all sludge (or other waste) removed from any wastewater treatment process. These records shall fulfill all applicable requirements of 30 TAC § 335 and must include the following, as it pertains to wastewater treatment and discharge:
 - i. Volume of waste and date(s) generated from treatment process;
 - ii. Volume of waste disposed of on-site or shipped off-site;
 - iii. Date(s) of disposal;
 - iv. Identity of hauler or transporter;
 - v. Location of disposal site; and
 - vi. Method of final disposal.

The above records shall be maintained on a monthly basis. The records shall be retained at the facility site, or shall be readily available for review by authorized representatives of the TCEQ for at least five years.

- 12. For industrial facilities to which the requirements of 30 TAC § 335 do not apply, sludge and solid wastes, including tank cleaning and contaminated solids for disposal, shall be disposed of in accordance with THSC § 361.

TCEQ Revision 06/2020

SLUDGE PROVISIONS

The permittee is authorized to dispose of sludge or biosolids only at a Texas Commission on Environmental Quality (TCEQ) authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge. **The disposal of sludge or biosolids by land application on property owned, leased or under the direct control of the permittee is a violation of the permit unless the site is authorized with the TCEQ. This provision does not authorize Distribution and Marketing of Class A or Class AB Biosolids. This provision does not authorize the permittee to land apply biosolids on property owned, leased or under the direct control of the permittee.**

SECTION I. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE OR BIOSOLIDS LAND APPLICATION

A. General Requirements

1. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC § 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge or biosolids.
2. In all cases, if the person (permit holder) who prepares the sewage sludge supplies the sewage sludge to another person for land application use or to the owner or lease holder of the land, the permit holder shall provide necessary information to the parties who receive the sludge to assure compliance with these regulations.
3. The land application of processed or unprocessed chemical toilet waste, grease trap waste, grit trap waste, milk solids, or similar non-hazardous municipal or industrial solid wastes, or any of the wastes listed in this provision combined with biosolids, WTP residuals or domestic septage is prohibited unless the grease trap waste is added at a fats, oil and grease (FOG) receiving facility as part of an anaerobic digestion process.

B. Testing Requirements

1. Sewage sludge or biosolids shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I [Toxicity Characteristic Leaching Procedure (TCLP)] or other method that receives the prior approval of the TCEQ for the contaminants listed in 40 CFR Part 261.24, Table 1. Sewage sludge or biosolids failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal. Following failure of any TCLP test, the management or disposal of sewage sludge or biosolids at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge or biosolids no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division and the Regional Director (MC Region 10) within seven (7) days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped, and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Permitting and Registration Support Division (MC 129), Texas Commission on Environmental Quality, P.O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. The permittee must submit this annual report by September 30th of each year using the online electronic reporting system available through TCEQ's website. If the permittee requests and obtains an electronic reporting waiver, the annual report can be submitted in hard copy to the TCEQ Regional Office (MC Region 10) and the Enforcement Division (MC 224).

2. Biosolids shall not be applied to the land if the concentration of the pollutants exceeds the pollutant concentration criteria in Table 1. The frequency of testing for pollutants in Table 1 is found in Section I.C. of this permit.

TABLE 1

<u>Pollutant</u>	<u>Ceiling Concentration</u> <u>(Milligrams per kilogram)*</u>
Arsenic	75
Cadmium	85
Chromium	3000
Copper	4300
Lead	840
Mercury	57
Molybdenum	75
Nickel	420
PCBs	49
Selenium	100
Zinc	7500

* Dry weight basis

3. Pathogen Control

All sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site must be treated by one of the following methods to ensure that the sludge meets either the Class A, Class AB or Class B biosolids pathogen requirements.

- a. For sewage sludge to be classified as Class A biosolids with respect to pathogens, the density of fecal coliform in the sewage sludge must be less than 1,000 most probable number (MPN) per gram of total solids (dry weight basis), or the density of *Salmonella* sp. bacteria in the sewage sludge must be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met:

Alternative 1 - The temperature of the sewage sludge that is used or disposed shall be maintained at or above a specific value for a period of time. See 30 TAC § 312.82(a)(3)(A) for specific information;

Alternative 5 (PFRP) - Sewage sludge that is used or disposed of must be treated in one of the Processes to Further Reduce Pathogens (PFRP) described in 40 CFR Part 503, Appendix B. PFRP include composting, heat drying, heat treatment, and thermophilic aerobic digestion; or

Alternative 6 (PFRP Equivalent) - Sewage sludge that is used or disposed of must be treated in a process that has been approved by the U. S. Environmental Protection Agency as being equivalent to those in Alternative 5.

- b. For sewage sludge to be classified as Class AB biosolids with respect to pathogens, the density of fecal coliform in the sewage sludge must be less than 1,000 MPN per gram of total solids (dry weight basis), or the density of *Salmonella* sp. bacteria in the sewage sludge be less than three MPN per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. In addition, one of the alternatives listed below must be met:

Alternative 2 - The pH of the sewage sludge that is used or disposed shall be raised to above 12 std. units and shall remain above 12 std. units for 72 hours.

The temperature of the sewage sludge shall be above 52° Celsius for 12 hours or longer during the period that the pH of the sewage sludge is above 12 std. units.

At the end of the 72-hour period during which the pH of the sewage sludge is above 12 std. units, the sewage sludge shall be air dried to achieve a percent solids in the sewage sludge greater than 50%; or

Alternative 3 - The sewage sludge shall be analyzed for enteric viruses prior to pathogen treatment. The limit for enteric viruses is less than one Plaque-forming Unit per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(i-iii) for specific information. The sewage sludge shall be analyzed for viable helminth ova prior to pathogen treatment. The limit for viable helminth ova is less than one per four grams of total solids (dry weight basis) either before or following pathogen treatment. See 30 TAC § 312.82(a)(2)(C)(iv-vi) for specific information; or

Alternative 4 - The density of enteric viruses in the sewage sludge shall be less than one Plaque-forming Unit per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed. The density of viable helminth ova in the sewage sludge shall be less than one per four grams of total solids (dry weight basis) at the time the sewage sludge is used or disposed.

- c. Sewage sludge that meets the requirements of Class AB biosolids may be classified a Class A biosolids if a variance request is submitted in writing that is supported by substantial documentation demonstrating equivalent methods for reducing odors and written approval is granted by the executive director. The executive director may deny the variance request or revoke that approved variance if it is determined that the variance may potentially endanger human health or the environment, or create nuisance odor conditions.
- d. Three alternatives are available to demonstrate compliance with Class B biosolids criteria.

Alternative 1

- i. A minimum of seven random samples of the sewage sludge shall be collected within 48 hours of the time the sewage sludge is used or disposed of during each monitoring episode for the sewage sludge.
- ii. The geometric mean of the density of fecal coliform in the samples collected shall be less than either 2,000,000 MPN per gram of total solids (dry weight basis) or 2,000,000 Colony Forming Units per gram of total solids (dry weight basis).

Alternative 2 - Sewage sludge that is used or disposed of shall be treated in one of the Processes to Significantly Reduce Pathogens (PSRP) described in 40 CFR Part 503, Appendix B, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;
- ii. An independent Texas Licensed Professional Engineer must make a certification to the generator of a sewage sludge that the wastewater treatment facility generating the sewage sludge is designed to achieve one of the PSRP at the permitted design loading of the facility. The certification need only be repeated if the design loading of the facility is increased. The certification shall include a statement indicating the design meets all the applicable standards specified in Appendix B of 40 CFR Part 503;
- iii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iv. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review; and
- v. If the sewage sludge is generated from a mixture of sources, resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the PSRP, and shall meet the certification, operation, and record keeping requirements of this paragraph.

Alternative 3 - Sewage sludge shall be treated in an equivalent process that has been approved by the U.S. Environmental Protection Agency, so long as all of the following requirements are met by the generator of the sewage sludge.

- i. Prior to use or disposal, all the sewage sludge must have been generated from a single location, except as provided in paragraph v. below;

- ii. Prior to any off-site transportation or on-site use or disposal of any sewage sludge generated at a wastewater treatment facility, the chief certified operator of the wastewater treatment facility or other responsible official who manages the processes to significantly reduce pathogens at the wastewater treatment facility for the permittee, shall certify that the sewage sludge underwent at least the minimum operational requirements necessary in order to meet one of the PSRP. The acceptable processes and the minimum operational and record keeping requirements shall be in accordance with established U.S. Environmental Protection Agency final guidance;
- iii. All certification records and operational records describing how the requirements of this paragraph were met shall be kept by the generator for a minimum of three years and be available for inspection by commission staff for review;
- iv. The Executive Director will accept from the U.S. Environmental Protection Agency a finding of equivalency to the defined PSRP; and
- v. If the sewage sludge is generated from a mixture of sources resulting from a person who prepares sewage sludge from more than one wastewater treatment facility, the resulting derived product shall meet one of the Processes to Significantly Reduce Pathogens, and shall meet the certification, operation, and record keeping requirements of this paragraph.

In addition to the Alternatives 1 – 3, the following site restrictions must be met if Class B biosolids are land applied:

- i. Food crops with harvested parts that touch the biosolids/soil mixture and are totally above the land surface shall not be harvested for 14 months after application of biosolids.
- ii. Food crops with harvested parts below the surface of the land shall not be harvested for 20 months after application of biosolids when the biosolids remain on the land surface for 4 months or longer prior to incorporation into the soil.
- iii. Food crops with harvested parts below the surface of the land shall not be harvested for 38 months after application of biosolids when the biosolids remain on the land surface for less than 4 months prior to incorporation into the soil.
- iv. Food crops, feed crops, and fiber crops shall not be harvested for 30 days after application of biosolids.
- v. Domestic livestock shall not be allowed to graze on the land for 30 days after application of biosolids.
- vi. Turf grown on land where biosolids are applied shall not be harvested for 1 year after application of the biosolids when the harvested turf is placed on either land with a high potential for public exposure or a lawn.
- vii. Public access to land with a high potential for public exposure shall be restricted for 1 year after application of biosolids.
- viii. Public access to land with a low potential for public exposure shall be restricted

for 30 days after application of biosolids.

- ix. Land application of biosolids shall be in accordance with the buffer zone requirements found in 30 TAC § 312.44.

4. Vector Attraction Reduction Requirements

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, or a reclamation site shall be treated by one of the following Alternatives 1 through 10 for vector attraction reduction.

Alternative 1 - The mass of volatile solids in the sewage sludge shall be reduced by a minimum of 38%.

Alternative 2 - If Alternative 1 cannot be met for an anaerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge anaerobically in the laboratory in a bench-scale unit for 40 additional days at a temperature between 30° and 37° Celsius. Volatile solids must be reduced by less than 17% to demonstrate compliance.

Alternative 3 - If Alternative 1 cannot be met for an aerobically digested sludge, demonstration can be made by digesting a portion of the previously digested sludge with percent solids of two percent or less aerobically in the laboratory in a bench-scale unit for 30 additional days at 20° Celsius. Volatile solids must be reduced by less than 15% to demonstrate compliance.

Alternative 4 - The specific oxygen uptake rate (SOUR) for sewage sludge treated in an aerobic process shall be equal to or less than 1.5 milligrams of oxygen per hour per gram of total solids (dry weight basis) at a temperature of 20° Celsius.

Alternative 5 - Sewage sludge shall be treated in an aerobic process for 14 days or longer. During that time, the temperature of the sewage sludge shall be higher than 40° Celsius and the average temperature of the sewage sludge shall be higher than 45° Celsius.

Alternative 6 - The pH of sewage sludge shall be raised to 12 or higher by alkali addition and, without the addition of more alkali shall remain at 12 or higher for two hours and then remain at a pH of 11.5 or higher for an additional 22 hours at the time the sewage sludge is prepared for sale or given away in a bag or other container.

Alternative 7 - The percent solids of sewage sludge that does not contain unstabilized solids generated in a primary wastewater treatment process shall be equal to or greater than 75% based on the moisture content and total solids prior to mixing with other materials. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

Alternative 8 - The percent solids of sewage sludge that contains unstabilized solids

generated in a primary wastewater treatment process shall be equal to or greater than 90% based on the moisture content and total solids prior to mixing with other materials at the time the sludge is used. Unstabilized solids are defined as organic materials in sewage sludge that have not been treated in either an aerobic or anaerobic treatment process.

- Alternative 9 -
- i. Biosolids shall be injected below the surface of the land.
 - ii. No significant amount of the biosolids shall be present on the land surface within one hour after biosolids are injected.
 - iii. When sewage sludge that is injected below the surface of the land is Class A or Class AB with respect to pathogens, the biosolids shall be injected below the land surface within eight hours after being discharged from the pathogen treatment process.
- Alternative 10 -
- i. Biosolids applied to the land surface or placed on a surface disposal site shall be incorporated into the soil within six hours after application to or placement on the land.
 - ii. When biosolids that are incorporated into the soil is Class A or Class AB with respect to pathogens, the biosolids shall be applied to or placed on the land within eight hours after being discharged from the pathogen treatment process.

C. Monitoring Requirements

Toxicity Characteristic Leaching Procedure (TCLP) Test	- once during the term of this permit
PCBs	- once during the term of this permit

All metal constituents and fecal coliform or *Salmonella* sp. bacteria shall be monitored at the appropriate frequency shown below, pursuant to 30 TAC § 312.46(a)(1):

<u>Amount of biosolids (*) metric tons per 365-day period</u>	<u>Monitoring Frequency</u>
0 to less than 290	Once/Year
290 to less than 1,500	Once/Quarter
1,500 to less than 15,000	Once/Two Months
15,000 or greater	Once/Month

(*) *The amount of bulk biosolids applied to the land (dry wt. basis).*

Representative samples of sewage sludge shall be collected and analyzed in accordance with the methods referenced in 30 TAC § 312.7

Identify each of the analytic methods used by the facility to analyze enteric viruses, fecal

coliforms, helminth ova, *Salmonella* sp., and other regulated parameters.

Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.

Identify the nature of material generated by the facility (such as a biosolid for beneficial use or land-farming, or sewage sludge or biosolids for disposal at a monofill) and whether the material is ultimately conveyed off-site in bulk or in bags.

SECTION II. REQUIREMENTS SPECIFIC TO BULK SEWAGE SLUDGE FOR APPLICATION TO THE LAND MEETING CLASS A, CLASS AB or B BIOSOLIDS PATHOGEN REDUCTION AND THE CUMULATIVE LOADING RATES IN TABLE 2, OR CLASS B PATHOGEN REDUCTION AND THE POLLUTANT CONCENTRATIONS IN TABLE 3

For those permittees meeting Class A, Class AB or B pathogen reduction requirements and that meet the cumulative loading rates in Table 2 below, or the Class B pathogen reduction requirements and contain concentrations of pollutants below listed in Table 3, the following conditions apply:

A. Pollutant Limits

Table 2

<u>Pollutant</u>	Cumulative Pollutant Loading Rate (pounds per acre)*
Arsenic	36
Cadmium	35
Chromium	2677
Copper	1339
Lead	268
Mercury	15
Molybdenum	Report Only
Nickel	375
Selenium	89
Zinc	2500

Table 3

<u>Pollutant</u>	Monthly Average Concentration (milligrams per kilogram)*
Arsenic	41
Cadmium	39
Chromium	1200
Copper	1500
Lead	300
Mercury	17
Molybdenum	Report Only
Nickel	420
Selenium	36
Zinc	2800

*Dry weight basis

B. Pathogen Control

All bulk sewage sludge that is applied to agricultural land, forest, a public contact site, a reclamation site, shall be treated by either Class A, Class AB or Class B biosolids pathogen reduction requirements as defined above in Section I.B.3.

C. Management Practices

1. Bulk biosolids shall not be applied to agricultural land, forest, a public contact site, or a reclamation site that is flooded, frozen, or snow-covered so that the bulk biosolids enters a wetland or other waters in the State.
2. Bulk biosolids not meeting Class A biosolids requirements shall be land applied in a manner which complies with Applicability in accordance with 30 TAC §312.41 and the Management Requirements in accordance with 30 TAC § 312.44.
3. Bulk biosolids shall be applied at or below the agronomic rate of the cover crop.
4. An information sheet shall be provided to the person who receives bulk Class A or AB biosolids sold or given away. The information sheet shall contain the following information:
 - a. The name and address of the person who prepared the Class A or AB biosolids that are sold or given away in a bag or other container for application to the land.
 - b. A statement that application of the biosolids to the land is prohibited except in accordance with the instruction on the label or information sheet.
 - c. The annual whole sludge application rate for the biosolids application rate for the biosolids that does not cause any of the cumulative pollutant loading rates in Table 2 above to be exceeded, unless the pollutant concentrations in Table 3 found in Section II above are met.

D. Notification Requirements

1. If bulk biosolids are applied to land in a State other than Texas, written notice shall be provided prior to the initial land application to the permitting authority for the State in which the bulk biosolids are proposed to be applied. The notice shall include:
 - a. The location, by street address, and specific latitude and longitude, of each land application site.
 - b. The approximate time period bulk biosolids will be applied to the site.
 - c. The name, address, telephone number, and National Pollutant Discharge Elimination System permit number (if appropriate) for the person who will apply the bulk biosolids.
2. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the biosolids disposal practice.

E. Record Keeping Requirements

The documents will be retained at the facility site and/or shall be readily available for review by a TCEQ representative. The person who prepares bulk sewage sludge or a biosolids material shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative for a period

of five years. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply.

1. The concentration (mg/kg) in the sludge of each pollutant listed in Table 3 above and the applicable pollutant concentration criteria (mg/kg), or the applicable cumulative pollutant loading rate and the applicable cumulative pollutant loading rate limit (lbs/ac) listed in Table 2 above.
2. A description of how the pathogen reduction requirements are met (including site restrictions for Class AB and Class B biosolids, if applicable).
3. A description of how the vector attraction reduction requirements are met.
4. A description of how the management practices listed above in Section II.C are being met.
5. The following certification statement:

“I certify, under penalty of law, that the applicable pathogen requirements in 30 TAC § 312.82(a) or (b) and the vector attraction reduction requirements in 30 TAC § 312.83(b) have been met for each site on which bulk biosolids are applied. This determination has been made under my direction and supervision in accordance with the system designed to ensure that qualified personnel properly gather and evaluate the information used to determine that the management practices have been met. I am aware that there are significant penalties for false certification including fine and imprisonment.”

6. The recommended agronomic loading rate from the references listed in Section II.C.3. above, as well as the actual agronomic loading rate shall be retained. The person who applies bulk biosolids shall develop the following information and shall retain the information at the facility site and/or shall be readily available for review by a TCEQ representative indefinitely. If the permittee supplies the sludge to another person who land applies the sludge, the permittee shall notify the land applier of the requirements for record keeping found in 30 TAC § 312.47 for persons who land apply:
 - a. A certification statement that all applicable requirements (specifically listed) have been met, and that the permittee understands that there are significant penalties for false certification including fine and imprisonment. See 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii), as applicable, and to the permittee’s specific sludge treatment activities.
 - b. The location, by street address, and specific latitude and longitude, of each site on which biosolids are applied.
 - c. The number of acres in each site on which bulk biosolids are applied.
 - d. The date and time biosolids are applied to each site.

- e. The cumulative amount of each pollutant in pounds/acre listed in Table 2 applied to each site.
- f. The total amount of biosolids applied to each site in dry tons.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

F. Reporting Requirements

The permittee shall submit the following information in an annual report to the TCEQ by September 30th of each year. The permittee must submit this annual report using the online electronic reporting system available through TCEQ's website. If the permittee requests and obtains an electronic reporting waiver, the annual report can be submitted in hard copy to the TCEQ Regional Office (MC Region 10) and Enforcement Division (MC 224).

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. Identify the nature of material generated by the facility (such as a biosolid for beneficial use or land-farming, or sewage sludge for disposal at a monofill) and whether the material is ultimately conveyed off-site in bulk or in bags.
3. Results of tests performed for pollutants found in either Table 2 or 3 as appropriate for the permittee's land application practices.
4. The frequency of monitoring listed in Section I.C. that applies to the permittee.
5. Toxicity Characteristic Leaching Procedure (TCLP) results.
6. PCB concentration in sludge or biosolids in mg/kg.
7. Identity of hauler(s) and TCEQ transporter number.
8. Date(s) of transport.
9. Texas Commission on Environmental Quality registration number, if applicable.
10. Amount of sludge or biosolids disposal dry weight (lbs/acre) at each disposal site.
11. The concentration (mg/kg) in the sludge of each pollutant listed in Table 1 (defined as a monthly average) as well as the applicable pollutant concentration criteria (mg/kg) listed in Table 3 above, or the applicable pollutant loading rate limit (lbs/acre) listed in Table 2 above if it exceeds 90% of the limit.
12. Level of pathogen reduction achieved (Class A, Class AB or Class B).
13. Alternative used as listed in Section I.B.3.(a. or b.). Alternatives describe how the pathogen reduction requirements are met. If Class B biosolids, include information on how site restrictions were met.

14. Identify each of the analytic methods used by the facility to analyze enteric viruses, fecal coliforms, helminth ova, *Salmonella* sp., and other regulated parameters.
15. Vector attraction reduction alternative used as listed in Section I.B.4.
16. Amount of sludge or biosolids transported in dry tons/year.
17. The certification statement listed in either 30 TAC § 312.47(a)(4)(A)(ii) or 30 TAC § 312.47(a)(5)(A)(ii) as applicable to the permittee's sludge or biosolids treatment activities, shall be attached to the annual reporting form.
18. When the amount of any pollutant applied to the land exceeds 90% of the cumulative pollutant loading rate for that pollutant, as described in Table 2, the permittee shall report the following information as an attachment to the annual reporting form.
 - a. The location, by street address, and specific latitude and longitude.
 - b. The number of acres in each site on which bulk biosolids are applied.
 - c. The date and time bulk biosolids are applied to each site.
 - d. The cumulative amount of each pollutant (i.e., pounds/acre) listed in Table 2 in the bulk biosolids applied to each site.
 - e. The amount of biosolids (i.e., dry tons) applied to each site.

The above records shall be maintained on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SECTION III. REQUIREMENTS APPLYING TO ALL SEWAGE SLUDGE OR BIOSOLIDS DISPOSED IN A MUNICIPAL SOLID WASTE LANDFILL

- A. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC § 330 and all other applicable state and federal regulations to protect public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present. The permittee shall ensure that the sewage sludge or biosolids meets the requirements in 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
- B. If the permittee generates sewage sludge or biosolids and supplies that sewage sludge or biosolids to the owner or operator of a municipal solid waste landfill (MSWLF) for disposal, the permittee shall provide to the owner or operator of the MSWLF appropriate information needed to be in compliance with the provisions of this permit.
- C. The permittee shall give 180 days prior notice to the Executive Director in care of the Wastewater Permitting Section (MC 148) of the Water Quality Division of any change planned in the sewage sludge or biosolids disposal practice.
- D. Sewage sludge or biosolids shall be tested once during the term of this permit in accordance with the method specified in both 40 CFR Part 261, Appendix II and 40 CFR Part 268, Appendix I (Toxicity Characteristic Leaching Procedure) or other method, which receives the prior approval of the TCEQ for contaminants listed in Table 1 of 40 CFR § 261.24. Sewage sludge or biosolids failing this test shall be managed according to RCRA standards for generators of hazardous waste, and the waste's disposition must be in accordance with all applicable requirements for hazardous waste processing, storage, or disposal.

Following failure of any TCLP test, the management or disposal of sewage sludge or biosolids at a facility other than an authorized hazardous waste processing, storage, or disposal facility shall be prohibited until such time as the permittee can demonstrate the sewage sludge or biosolids no longer exhibits the hazardous waste toxicity characteristics (as demonstrated by the results of the TCLP tests). A written report shall be provided to both the TCEQ Registration and Reporting Section (MC 129) of the Permitting and Registration Support Division and the Regional Director (MC Region 10) of the appropriate TCEQ field office within 7 days after failing the TCLP Test.

The report shall contain test results, certification that unauthorized waste management has stopped, and a summary of alternative disposal plans that comply with RCRA standards for the management of hazardous waste. The report shall be addressed to: Director, Permitting and Registration Support Division (MC 129), Texas Commission on Environmental Quality, P. O. Box 13087, Austin, Texas 78711-3087. In addition, the permittee shall prepare an annual report on the results of all sludge toxicity testing. This annual report shall be submitted to the TCEQ Regional Office (MC Region 10) and the Enforcement Division (MC 224) by September 30 of each year.

- E. Sewage sludge or biosolids shall be tested as needed, in accordance with the requirements of 30 TAC Chapter 330.
- F. Record Keeping Requirements

The permittee shall develop the following information and shall retain the information for five years.

1. The description (including procedures followed and the results) of all liquid Paint Filter Tests performed.
2. The description (including procedures followed and results) of all TCLP tests performed.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

G. Reporting Requirements

The permittee shall submit the following information in an annual report to the TCEQ by September 30th of each year. The permittee must submit this annual report using the online electronic reporting system available through TCEQ's website. If the permittee requests and obtains an electronic reporting waiver, the annual report can be submitted in hard copy to the TCEQ Regional Office (MC Region 10) and Enforcement Division (MC 224).

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. Toxicity Characteristic Leaching Procedure (TCLP) results.
3. Annual sludge or biosolids production in dry tons/year.
4. Amount of sludge or biosolids disposed in a municipal solid waste landfill in dry tons/year.
5. Amount of sludge or biosolids transported interstate in dry tons/year.
6. A certification that the sewage sludge or biosolids meets the requirements of 30 TAC § 330 concerning the quality of the sludge disposed in a municipal solid waste landfill.
7. Identity of hauler(s) and transporter registration number.
8. Owner of disposal site(s).
9. Location of disposal site(s).
10. Date(s) of disposal.

The above records shall be maintained on-site on a monthly basis and shall be made available to the Texas Commission on Environmental Quality upon request.

SECTION IV. REQUIREMENTS APPLYING TO SLUDGE OR BIOSOLIDS TRANSPORTED TO ANOTHER FACILITY FOR FURTHER PROCESSING

These provisions apply to sludge or biosolids that is transported to another wastewater treatment facility or facility that further processes sludge or biosolids. These provisions are intended to allow transport of sludge or biosolids to facilities that have been authorized to accept sludge or biosolids. These provisions do not limit the ability of the receiving facility to determine whether to accept the sludge or biosolids, nor do they limit the ability of the receiving facility to request additional testing or documentation.

A. General Requirements

1. The permittee shall handle and dispose of sewage sludge or biosolids in accordance with 30 TAC Chapter 312 and all other applicable state and federal regulations in a manner that protects public health and the environment from any reasonably anticipated adverse effects due to any toxic pollutants that may be present in the sludge.
2. Sludge or biosolids may only be transported using a registered transporter or using an approved pipeline.

B. Record Keeping Requirements

1. For sludge or biosolids transported by an approved pipeline, the permittee must maintain records of the following:
 - a. the amount of sludge or biosolids transported;
 - b. the date of transport;
 - c. the name and TCEQ permit number of the receiving facility or facilities;
 - d. the location of the receiving facility or facilities;
 - e. the name and TCEQ permit number of the facility that generated the waste; and
 - f. copy of the written agreement between the permittee and the receiving facility to accept sludge or biosolids.
2. For sludge or biosolids transported by a registered transporter, the permittee must maintain records of the completed trip tickets in accordance with 30 TAC § 312.145(a)(1)-(7) and amount of sludge or biosolids transported.
3. The above records shall be maintained on-site on a monthly basis and shall be made available to the TCEQ upon request. These records shall be retained for at least five years.

C. Reporting Requirements

The permittee shall submit the following information in an annual report to the TCEQ by September 30th of each year. The permittee must submit this annual report using the online electronic reporting system available through TCEQ's website. If the permittee requests and obtains an electronic reporting waiver, the annual report can be submitted in hard copy to the TCEQ Regional Office (MC Region 10) and Enforcement Division (MC 224).

1. Identify in the following categories (as applicable) the sewage sludge or biosolids treatment process or processes at the facility: preliminary operations (e.g., sludge or biosolids grinding and degritting), thickening (concentration), stabilization, anaerobic digestion, aerobic digestion, composting, conditioning, disinfection (e.g., beta ray irradiation, gamma ray irradiation, pasteurization), dewatering (e.g., centrifugation, sludge drying beds, sludge lagoons), heat drying, thermal reduction, and methane or biogas capture and recovery.
2. the annual sludge or biosolids production;
3. the amount of sludge or biosolids transported;
4. the owner of each receiving facility;
5. the location of each receiving facility; and
6. the date(s) of disposal at each receiving facility.

TCEQ Revision 06/2020

OTHER REQUIREMENTS

1. The permittee shall employ or contract with one or more licensed wastewater treatment facility operators or wastewater system operations companies holding a valid license or registration according to the requirements of 30 TAC Chapter 30, Occupational Licenses and Registrations, and in particular 30 TAC Chapter 30, Subchapter J, Wastewater Operators and Operations Companies.

This Category D* facility must be operated by a chief operator or an operator holding a Class D* license or higher. The facility must be operated a minimum of five days per week by the licensed chief operator or an operator holding the required level of license or higher. The licensed chief operator or operator holding the required level of license or higher must be available by telephone or pager seven days per week. Where shift operation of the wastewater treatment facility is necessary, each shift that does not have the on-site supervision of the licensed chief operator must be supervised by an operator in charge who is licensed not less than one level below the category for the facility.

*A Class D Wastewater Treatment Operator license is not renewable for operators of a facility listed in 30 TAC Section 30.342(c) and must be upgraded to a Class C Wastewater Treatment Operator license or higher prior to the expiration date of the Class D license.

2. The facility is not located in the Coastal Management Program boundary.
3. The permittee shall provide facilities for the protection of its wastewater treatment facility from a 100-year flood.
4. In accordance with 30 TAC § 319.9, a permittee that has at least twelve months of uninterrupted compliance with its bacteria limit may notify the commission in writing of its compliance and request a less frequent measurement schedule. To request a less frequent schedule, the permittee shall submit a written request to the TCEQ Wastewater Permitting Section (MC 148) for each phase that includes a different monitoring frequency. The request must contain all of the reported bacteria values (Daily Avg. and Daily Max/Single Grab) for the twelve consecutive months immediately prior to the request. If the Executive Director finds that a less frequent measurement schedule is protective of human health and the environment, the permittee may be given a less frequent measurement schedule. For this permit, one/quarter may be reduced to one/six months. **A violation of any bacteria limit by a facility that has been granted a less frequent measurement schedule will require the permittee to return to the standard frequency schedule and submit written notice to the TCEQ Wastewater Permitting Section (MC 148).** The permittee may not apply for another reduction in measurement frequency for at least 24 months from the date of the last violation. The Executive Director may establish a more frequent measurement schedule if necessary to protect human health or the environment.

**STATEMENT OF BASIS/TECHNICAL SUMMARY
AND EXECUTIVE DIRECTOR'S PRELIMINARY DECISION**

DESCRIPTION OF APPLICATION

Applicant: CSWR-Texas Utility Operating Company, LLC
Texas Pollutant Discharge Elimination System (TPDES) Permit
No. WQ0013147001, EPA ID No. TX0098809

Regulated Activity: Domestic Wastewater Permit

Type of Application: Renewal

Request: Renewal with changes

Authority: Federal Clean Water Act (CWA) § 402; Texas Water Code (TWC)
§ 26.027; 30 Texas Administrative Code (TAC) Chapters 30,
305, 307, 309, 312, and 319; Commission policies; and United
States Environmental Protection Agency (EPA) guidelines.

EXECUTIVE DIRECTOR RECOMMENDATION

The Executive Director has made a preliminary decision that this permit, if issued, meets all statutory and regulatory requirements. The draft permit includes an expiration date of **five years from the date of issuance**.

REASON FOR PROJECT PROPOSED

The applicant has applied to the Texas Commission on Environmental Quality (TCEQ) for a renewal of the existing permit that authorizes the discharge of treated domestic wastewater at a daily average flow not to exceed 0.065 MGD. The existing wastewater treatment facility serves the Texas Landing subdivision.

PROJECT DESCRIPTION AND LOCATION

The Texas Landing Wastewater Treatment Facility is an activated sludge process plant operated in the complete mix mode. Treatment units include a bar screen, a final clarifier, an aeration basin, one sludge digester basin, and one chlorine contact chamber. The facility is in operation.

Sludge generated from the treatment facility is hauled by a registered transporter to Mt Houston Road MUD Wastewater Treatment Facility, Permit No. WQ0005023000, to be digested, dewatered, and then disposed of with the bulk of the sludge from the plant accepting the sludge. The draft permit also authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

The plant site is located at 404 Branding Iron, in Polk County, Texas 77351.

Outfall Location:

Outfall Number	Latitude	Longitude
001	30.707793 N	95.034913 W

The treated effluent is discharged directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin. The designated uses for Segment No. 0803 are primary contact recreation, public water supply, and high aquatic life use. The effluent limitations in the draft permit will maintain and protect the existing instream uses. All determinations are preliminary and subject to additional review and/or revisions.

Effluent limitations for the conventional effluent parameters (i.e., Five-Day Biochemical Oxygen Demand or Five-Day Carbonaceous Biochemical Oxygen Demand, Ammonia Nitrogen, etc.) are based on stream standards and waste load allocations for water-quality limited streams as established in the Texas Surface Water Quality Standards (TSWQS) and the State of Texas Water Quality Management Plan (WQMP).

In a case such as this, end-of-pipe compliance with pH limits between 6.0 and 9.0 standard units reasonably assures instream compliance with the TSWQS for pH when the discharge authorized is from a minor facility. This technology-based approach reasonably assures instream compliance with TSWQS criteria due to the relatively smaller discharge volumes authorized by these permits. This conservative assumption is based on TCEQ sampling conducted throughout the state which indicates that instream buffering quickly restores pH levels to ambient conditions. Similarly, this approach has been historically applied within EPA issued NPDES general permits where technology-based pH limits were established to be protective of water quality criteria.

The effluent limitations in the draft permit have been reviewed for consistency with the WQMP. The proposed effluent limitations are contained in the approved WQMP.

The discharge from this permit action is not expected to have an effect on any federal endangered or threatened aquatic or aquatic-dependent species or proposed species or their critical habitat. This determination is based on the United States Fish and Wildlife Service's (USFWS's) biological opinion on the State of Texas authorization of the TPDES (September 14, 1998; October 21, 1998, update). To make this determination for TPDES permits, TCEQ and EPA only considered aquatic or aquatic-dependent species occurring in watersheds of critical concern or high priority as listed in Appendix A of the USFWS biological opinion. The determination is subject to reevaluation due to subsequent updates or amendments to the biological opinion. The permit does not require EPA review with respect to the presence of endangered or threatened species.

Segment No. 0803 is currently listed on the state's inventory of impaired and threatened waters (the 2024 CWA § 303(d) list). The listing is for PCBs in edible tissue and Dioxin in edible tissue in the entire reservoir, from Livingston Dam in Polk/San Jacinto County to a point 1.8 km (1.1 mi) upstream of Boggy Creek in Houston/Leon County, up to the normal pool elevation of 131 feet (impounds Trinity River) (AU 0803_01 through AU 0803_12). The facility does not receive industrial wastewater contributions, therefore the effluent from this facility should not contribute to the Dioxin or PCBs in edible tissue impairment of this segment.

SUMMARY OF EFFLUENT DATA

The following is a summary of the applicant's effluent monitoring data for the period September 30, 2022 through September 30, 2024. The average of Daily Average value is computed by the

averaging of all 30-day average values for the reporting period for each parameter: flow, five-day biochemical oxygen demand (BOD₅), and total suspended solids (TSS). The average of Daily Average value for *Escherichia coli* in colony-forming units (CFU) or most probable number (MPN) per 100 ml is calculated via geometric mean.

<u>Parameter</u>	<u>Average of Daily Average</u>
Flow, MGD	0.018
BOD ₅ , mg/l	2.97
TSS, mg/l	4.60
<i>E. coli</i> , CFU or MPN per 100 ml	1

DRAFT PERMIT CONDITIONS

The draft permit authorizes a discharge of treated domestic wastewater at a volume not to exceed a daily average flow of 0.065 MGD.

The effluent limitations of the draft permit, based on a 30-day average, are 10 mg/l five-day biochemical oxygen demand (BOD₅), 15 mg/l total suspended solids (TSS), 126 colony-forming units (CFU) or most probable number (MPN) of *E. coli* 100 ml, and 4.0 mg/l minimum dissolved oxygen (DO). The effluent shall contain a total chlorine residual of at least 1.0 mg/l and shall not exceed a total chlorine residual of 4.0 mg/l after a detention time of at least 20 minutes based on peak flow.

The draft permit includes Sludge Provisions according to the requirements of 30 TAC Chapter 312, Sludge Use, Disposal, and Transportation. Sludge generated from the treatment facility is hauled by a registered transporter to Mt Houston Road MUD Wastewater Treatment Facility, Permit No. WQ0005023000, to be digested, dewatered, and then disposed of with the bulk of the sludge from the plant accepting the sludge. The draft permit also authorizes the disposal of sludge at a TCEQ-authorized land application site, co-disposal landfill, wastewater treatment facility, or facility that further processes sludge.

SUMMARY OF CHANGES FROM APPLICATION

None.

SUMMARY OF CHANGES FROM EXISTING PERMIT

Effluent limitations and monitoring requirements in the draft permit remain the same as the existing permit requirements

The Standard Permit Conditions, Sludge Provisions, and Other Requirements sections of the draft permit have been updated.

The draft permit includes all updates based on the 30 TAC 312 rule change effective April 23, 2020.

The applicant's name has changed from David Lee Sheffield in the existing permit to CSWR-Texas Utility Operating Company, LLC in the draft permit.

The applicant's mailing address has been updated in the draft permit from P.O. Box 2110, Onalaska, Texas 77360 to 1630 Des Peres Road, Suite 140, Saint Louis, Missouri, 63131.

BASIS FOR DRAFT PERMIT

The following items were considered in developing the draft permit:

1. Application received on September 30, 2024, and additional information received on October 23, 2024.
2. TPDES Permit No. WQ0013147001 issued on March 9, 2020.
3. The effluent limitations and conditions in the draft permit comply with EPA-approved portions of the 2018 Texas Surface Water Quality Standards (TSWQS), 30 TAC §§ 307.1 - 307.10, effective March 1, 2018; 2014 TSWQS, effective March 6, 2014; 2010 TSWQS, effective July 22, 2010; and 2000 TSWQS, effective July 26, 2000.
4. The effluent limitations in the draft permit meet the requirements for secondary treatment and the requirements for disinfection according to 30 TAC Chapter 309, Subchapter A: Effluent Limitations.
5. Interoffice Memoranda from the Water Quality Assessment Section of the TCEQ Water Quality Division.
6. Consistency with the Coastal Management Plan: The facility is not located in the Coastal Management Program boundary.
7. *Procedures to Implement the Texas Surface Water Quality Standards (IP)*, Texas Commission on Environmental Quality, June 2010, as approved by EPA, and the IP, January 2003, for portions of the 2010 IP not approved by EPA.
8. Texas 2024 Clean Water Act Section 303(d) List, Texas Commission on Environmental Quality, June 26, 2024; approved by the U.S. Environmental Protection Agency on November 13, 2024.
9. Texas Natural Resource Conservation Commission, Guidance Document for Establishing Monitoring Frequencies for Domestic and Industrial Wastewater Discharge Permits, Document No. 98-001.000-OWR-WQ, May 1998.

PROCEDURES FOR FINAL DECISION

When an application is declared administratively complete, the Chief Clerk sends a letter to the applicant advising the applicant to publish the Notice of Receipt of Application and Intent to Obtain Permit in the newspaper. In addition, the Chief Clerk instructs the applicant to place a copy of the application in a public place for review and copying in the county where the facility is or will be located. This application will be in a public place throughout the comment period. The Chief Clerk also mails this notice to any interested persons and, if required, to landowners identified in the permit application. This notice informs the public about the application, and

provides that an interested person may file comments on the application or request a contested case hearing or a public meeting.

Once a draft permit is completed, it is sent, along with the Executive Director's preliminary decision, as contained in the technical summary or fact sheet, to the Chief Clerk. At that time, the Notice of Application and Preliminary Decision will be mailed to the same people and published in the same newspaper as the prior notice. This notice sets a deadline for making public comments. The applicant must place a copy of the Executive Director's preliminary decision and draft permit in the public place with the application.

Any interested person may request a public meeting on the application until the deadline for filing public comments. A public meeting is intended for the taking of public comment, and is not a contested case proceeding.

After the public comment deadline, the Executive Director prepares a response to all significant public comments on the application or the draft permit raised during the public comment period. The Chief Clerk then mails the Executive Director's response to comments and final decision to people who have filed comments, requested a contested case hearing, or requested to be on the mailing list. This notice provides that if a person is not satisfied with the Executive Director's response and decision, they can request a contested case hearing or file a request to reconsider the Executive Director's decision within 30 days after the notice is mailed.

The Executive Director will issue the permit unless a written hearing request or request for reconsideration is filed within 30 days after the Executive Director's response to comments and final decision is mailed. If a hearing request or request for reconsideration is filed, the Executive Director will not issue the permit and will forward the application and request to the TCEQ Commissioners for their consideration at a scheduled Commission meeting. If a contested case hearing is held, it will be a legal proceeding similar to a civil trial in state district court.

If the Executive Director calls a public meeting or the Commission grants a contested case hearing as described above, the Commission will give notice of the date, time, and place of the meeting or hearing. If a hearing request or request for reconsideration is made, the Commission will consider all public comments in making its decision and shall either adopt the Executive Director's response to public comments or prepare its own response.

For additional information about this application, contact Tyler Davis at (512) 239-2007.

Tyler Davis
Municipal Permits Team
Wastewater Permitting Section (MC 148)

Date



TCEQ Use Only

TCEQ Core Data Form

For detailed instructions on completing this form, please read the Core Data Form Instructions or call 512-239-5175.

SECTION I: General Information

1. Reason for Submission (If other is checked please describe in space provided.)		
<input type="checkbox"/> New Permit, Registration or Authorization (Core Data Form should be submitted with the program application.)		
<input checked="" type="checkbox"/> Renewal (Core Data Form should be submitted with the renewal form)		<input type="checkbox"/> Other
2. Customer Reference Number (if issued)	Follow this link to search for CN or RN numbers in Central Registry**	3. Regulated Entity Reference Number (if issued)
CN 605844786		RN 102341294

SECTION II: Customer Information

4. General Customer Information		5. Effective Date for Customer Information Updates (mm/dd/yyyy)	
<input type="checkbox"/> New Customer <input checked="" type="checkbox"/> Update to Customer Information <input type="checkbox"/> Change in Regulated Entity Ownership			
<input type="checkbox"/> Change in Legal Name (Verifiable with the Texas Secretary of State or Texas Comptroller of Public Accounts)			
<i>The Customer Name submitted here may be updated automatically based on what is current and active with the Texas Secretary of State (SOS) or Texas Comptroller of Public Accounts (CPA).</i>			
6. Customer Legal Name (If an individual, print last name first: eg: Doe, John)		<i>If new Customer, enter previous Customer below:</i>	
CSWR-Texas Utility Operating Company LLC			
7. TX SOS/CPA Filing Number	8. TX State Tax ID (11 digits)	9. Federal Tax ID (9 digits)	10. DUNS Number (if applicable)
803367893	32071353422	84-3250493	
11. Type of Customer:	<input checked="" type="checkbox"/> Corporation	<input type="checkbox"/> Individual	Partnership: <input type="checkbox"/> General <input type="checkbox"/> Limited
Government: <input type="checkbox"/> City <input type="checkbox"/> County <input type="checkbox"/> Federal <input type="checkbox"/> Local <input type="checkbox"/> State <input type="checkbox"/> Other	<input type="checkbox"/> Sole Proprietorship	<input type="checkbox"/> Other:	
12. Number of Employees		13. Independently Owned and Operated?	
<input type="checkbox"/> 0-20 <input type="checkbox"/> 21-100 <input checked="" type="checkbox"/> 101-250 <input type="checkbox"/> 251-500 <input type="checkbox"/> 501 and higher		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
14. Customer Role (Proposed or Actual) – as it relates to the Regulated Entity listed on this form. Please check one of the following			
<input checked="" type="checkbox"/> Owner <input type="checkbox"/> Operator <input type="checkbox"/> Owner & Operator <input type="checkbox"/> Other:			
<input type="checkbox"/> Occupational Licensee <input type="checkbox"/> Responsible Party <input type="checkbox"/> VCP/BSA Applicant			
15. Mailing Address:	1630 Des Peres Road		
	Ste. 140		
	City	Des Peres	State MO ZIP 63131 ZIP + 4
16. Country Mailing Information (if outside USA)		17. E-Mail Address (if applicable)	
		adobbins@cswrgroup.com	
18. Telephone Number	19. Extension or Code	20. Fax Number (if applicable)	

SECTION III: Regulated Entity Information**21. General Regulated Entity Information** (If 'New Regulated Entity' is selected, a new permit application is also required.)
☐ New Regulated Entity
 ☒ Update to Regulated Entity Name
 ☒ Update to Regulated Entity Information

The Regulated Entity Name submitted may be updated, in order to meet TCEQ Core Data Standards (removal of organizational endings such as Inc, LP, or LLC).

22. Regulated Entity Name (Enter name of the site where the regulated action is taking place.)

Texas Landing Wastewater Treatment Facility

23. Street Address of the Regulated Entity:

404 Branding Iron

(No PO Boxes)

City	Livingston	State	TX	ZIP	77351	ZIP + 4	7572
-------------	------------	--------------	----	------------	-------	----------------	------

24. County

Polk

If no Street Address is provided, fields 25-28 are required.

25. Description to Physical Location:

APPROX 1.2 MI N OF INTERSECTION OF FM 350 AND FM 3126 APPROX 5 MI W OF THE CITY OF LIVINGSTON AND ON THE E SHORELINE OF LAKE LIVINGSTON IN POLK COUNTY TX

26. Nearest City**State****Nearest ZIP Code**

Jasper

TX

77351

Latitude/Longitude are required and may be added/updated to meet TCEQ Core Data Standards. (Geocoding of the Physical Address may be used to supply coordinates where none have been provided or to gain accuracy).

27. Latitude (N) In Decimal:

30.707844

28. Longitude (W) In Decimal:

-95.034628

Degrees

Minutes

Seconds

Degrees

Minutes

Seconds

29. Primary SIC Code**30. Secondary SIC Code****31. Primary NAICS Code****32. Secondary NAICS Code**

(4 digits)

(4 digits)

(5 or 6 digits)

(5 or 6 digits)

4952

33. What is the Primary Business of this entity? (Do not repeat the SIC or NAICS description.)

Wastewater Treatment

34. Mailing

1630 Des Peres Road

Address:

Ste. 140

City

Des Peres

State

MO

ZIP

63131

ZIP + 4**35. E-Mail Address:**

msappington@CSWRgroup.com

36. Telephone Number**37. Extension or Code****38. Fax Number** (if applicable)

(314) 464-3976

() -

39. TCEQ Programs and ID Numbers Check all Programs and write in the permits/registration numbers that will be affected by the updates submitted on this form. See the Core Data Form instructions for additional guidance.


<input type="checkbox"/> Dam Safety	<input type="checkbox"/> Districts	<input type="checkbox"/> Edwards Aquifer	<input type="checkbox"/> Emissions Inventory Air	<input type="checkbox"/> Industrial Hazardous Waste
<input type="checkbox"/> Municipal Solid Waste	<input type="checkbox"/> New Source Review Air	<input type="checkbox"/> OSSF	<input type="checkbox"/> Petroleum Storage Tank	<input type="checkbox"/> PWS
<input type="checkbox"/> Sludge	<input type="checkbox"/> Storm Water	<input type="checkbox"/> Title V Air	<input type="checkbox"/> Tires	<input type="checkbox"/> Used Oil
<input type="checkbox"/> Voluntary Cleanup	<input checked="" type="checkbox"/> Wastewater	<input type="checkbox"/> Wastewater Agriculture	<input type="checkbox"/> Water Rights	<input type="checkbox"/> Other:
	WQ0013147001, TX0098809			

SECTION IV: Preparer Information

40. Name:	Amberly Schulz	41. Title:	Compliance Specialist
42. Telephone Number	43. Ext./Code	44. Fax Number	45. E-Mail Address
{ 573 } 214-1075		() -	aschulz@trccompanies.com

SECTION V: Authorized Signature

46. By my signature below, I certify, to the best of my knowledge, that the information provided in this form is true and complete, and that I have signature authority to submit this form on behalf of the entity specified in Section II, Field 6 and/or as required for the updates to the ID numbers identified in field 39.

Company:	CSWR-Texas Utility Operating Company	Job Title:	President
Name (In Print):	Josiah Cox	Phone:	314-736-4672
Signature:		Date:	9/27/2024



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST

Complete and submit this checklist with the application.

APPLICANT NAME: [Click to enter text.](#)

PERMIT NUMBER (If new, leave blank): WQ00 [Click to enter text.](#)

Indicate if each of the following items is included in your application.

	Y	N		Y	N
Administrative Report 1.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Original USGS Map	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Administrative Report 1.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Affected Landowners Map	<input type="checkbox"/>	<input checked="" type="checkbox"/>
SPIF	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Landowner Disk or Labels	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Core Data Form	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Buffer Zone Map	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Public Involvement Plan Form	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Flow Diagram	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Technical Report 1.0	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Site Drawing	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Technical Report 1.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Original Photographs	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 2.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Design Calculations	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 2.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Solids Management Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 3.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Water Balance	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Worksheet 3.1	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 3.2	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 3.3	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 4.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 5.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 6.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			
Worksheet 7.0	<input type="checkbox"/>	<input checked="" type="checkbox"/>			

For TCEQ Use Only

Segment Number _____ County _____
Expiration Date _____ Region _____
Permit Number _____



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

**DOMESTIC WASTEWATER PERMIT APPLICATION
ADMINISTRATIVE REPORT 1.0**

For any questions about this form, please contact the Applications Review and Processing Team at 512-239-4671.

Section 1. Application Fees (Instructions Page 26)

Indicate the amount submitted for the application fee (check only one).

Flow	New/Major Amendment	Renewal
<0.05 MGD	\$350.00 <input type="checkbox"/>	\$315.00 <input type="checkbox"/>
≥0.05 but <0.10 MGD	\$550.00 <input type="checkbox"/>	\$515.00 <input checked="" type="checkbox"/>
≥0.10 but <0.25 MGD	\$850.00 <input type="checkbox"/>	\$815.00 <input type="checkbox"/>
≥0.25 but <0.50 MGD	\$1,250.00 <input type="checkbox"/>	\$1,215.00 <input type="checkbox"/>
≥0.50 but <1.0 MGD	\$1,650.00 <input type="checkbox"/>	\$1,615.00 <input type="checkbox"/>
≥1.0 MGD	\$2,050.00 <input type="checkbox"/>	\$2,015.00 <input type="checkbox"/>

Minor Amendment (for any flow) \$150.00 ☐

Payment Information:

Mailed Check/Money Order Number: [Click to enter text.](#)
Check/Money Order Amount: [Click to enter text.](#)
Name Printed on Check: [Click to enter text.](#)

EPAY Voucher Number: [Click to enter text.](#)

Copy of Payment Voucher enclosed? Yes ☐

Section 2. Type of Application (Instructions Page 26)

a. Check the box next to the appropriate authorization type.

- ☐ Publicly-Owned Domestic Wastewater
☒ Privately-Owned Domestic Wastewater
☐ Conventional Wastewater Treatment

b. Check the box next to the appropriate facility status.

- ☒ Active ☐ Inactive

c. Check the box next to the appropriate permit type.

- ☒ TPDES Permit
- ☐ TLAP
- ☐ TPDES Permit with TLAP component
- ☐ Subsurface Area Drip Dispersal System (SADDs)

d. Check the box next to the appropriate application type

- ☐ New
- ☐ Major Amendment with Renewal
- ☐ Major Amendment without Renewal
- ☐ Renewal without changes
- ☒ Minor Amendment with Renewal
- ☐ Minor Amendment without Renewal
- ☐ Minor Modification of permit

e. For amendments or modifications, describe the proposed changes: Click to enter text.

f. For existing permits:

Permit Number: WQ00 13147001

EPA I.D. (TPDES only): TX 0098809

Expiration Date: 03/09/2025

Section 3. Facility Owner (Applicant) and Co-Applcant Information (Instructions Page 26)

A. The owner of the facility must apply for the permit.

What is the Legal Name of the entity (applicant) applying for this permit?

CSWR-Texas Utility Operating Company, LLC

(The legal name must be spelled exactly as filed with the Texas Secretary of State, County, or in the legal documents forming the entity.)

If the applicant is currently a customer with the TCEQ, what is the Customer Number (CN)?

You may search for your CN on the TCEQ website at <http://www15.tceq.texas.gov/crpub/>

CN: 605844786

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in 30 TAC § 305.44.

Prefix: Mr.

Last Name, First Name: Cox, Josiah

Title: President

Credential: N/A

B. Co-applcant information. Complete this section only if another person or entity is required to apply as a co-permittee.

What is the Legal Name of the co-applcant applying for this permit?

N/A

(The legal name must be spelled exactly as filed with the TX SOS, with the County, or in the legal documents forming the entity.)

If the co-applicant is currently a customer with the TCEQ, what is the Customer Number (CN)? You may search for your CN on the TCEQ website at: <http://www15.tceq.texas.gov/crpub/>

CN: N/A

What is the name and title of the person signing the application? The person must be an executive official meeting signatory requirements in 30 TAC § 305.44.

Prefix: N/A

Last Name, First Name: N/A

Title: N/A

Credential: N/A

Provide a brief description of the need for a co-permittee: N/A

C. Core Data Form

Complete the Core Data Form for each customer and include as an attachment. If the customer type selected on the Core Data Form is **Individual**, complete **Attachment 1** of Administrative Report 1.0. Attachment 1

Section 4. Application Contact Information (Instructions Page 27)

This is the person(s) TCEQ will contact if additional information is needed about this application. Provide a contact for administrative questions and technical questions.

A. Prefix: Ms.

Last Name, First Name: Sappington, Amanda

Title: EHS Compliance Manager Credential: Click to enter text.

Organization Name: CSWR

Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131

Phone No.: 314-464-3976

E-mail Address: msappington@cswrgroup.com

Check one or both: ☒ Administrative Contact ☐ Technical Contact

B. Prefix: Click to enter text.

Last Name, First Name: Woods-Schulz, Amberly

Title: Compliance Specialist Credential: Click to enter text.

Organization Name: TRC Companies

Mailing Address: 1000 Clark Ave, 4th Floor City, State, Zip Code: St. Louis, MO 63102

Phone No.: 573-214-1075

E-mail Address: aschulz@trccompanies.com

Check one or both: ☐ Administrative Contact ☒ Technical Contact

Section 5. Permit Contact Information (Instructions Page 27)

Provide the names and contact information for two individuals that can be contacted throughout the permit term.

A. Prefix: Ms.

Last Name, First Name: Sappington, Amanda

Title: EHS Compliance Manager Credential: Click to enter text.

Organization Name: CSWR

Mailing Address: 1630 Des Peres Road

City, State, Zip Code: Des Peres, MO 63131

Phone No.: 314-464-3976

E-mail Address: msappington@cswrgroup.com

B. Prefix: Mr. Last Name, First Name: Wittwer, Clarence
Title: Regional Manager Credential: Click to enter text.
Organization Name: CSWR
Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131
Phone No.: 254-355-9124 E-mail Address: cwittwer@cswrgroup.com

Section 6. Billing Contact Information (Instructions Page 27)

The permittee is responsible for paying the annual fee. The annual fee will be assessed to permits *in effect on September 1 of each year*. The TCEQ will send a bill to the address provided in this section. The permittee is responsible for terminating the permit when it is no longer needed (using form TCEQ-20029).

Prefix: Ms. Last Name, First Name: Obernuefemann, Krista
Title: Accounts Payable Credential: Click to enter text.
Organization Name: CSWR
Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131
Phone No.: 314-380-8515 E-mail Address: ap@cswrgroup.com

Section 7. DMR/MER Contact Information (Instructions Page 27)

Provide the name and complete mailing address of the person delegated to receive and submit Discharge Monitoring Reports (DMR) (EPA 3320-1) or maintain Monthly Effluent Reports (MER).

Prefix: Mr. Last Name, First Name: Wintersteen, Taylor
Title: TCEQ Licensed Operator Credential: Click to enter text.
Organization Name: Aggregate Water Company
Mailing Address: 25329 Budde Road, Ste 701 City, State, Zip Code: The Woodlands, TX 77380
Phone No.: 936-647-5852 E-mail Address: twintersteen@aggregatewater.com

Section 8. Public Notice Information (Instructions Page 27)

A. Individual Publishing the Notices

Prefix: Ms. Last Name, First Name: Sappington, Amanda
Title: EHS Compliance Manager Credential: Click to enter text.
Organization Name: CSWR
Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131
Phone No.: 314-464-3976 E-mail Address: msappington@cswrgroup.com

B. Method for Receiving Notice of Receipt and Intent to Obtain a Water Quality Permit Package

Indicate by a check mark the preferred method for receiving the first notice and instructions:

☒ E-mail Address

☐ Fax

☐ Regular Mail

C. Contact permit to be listed in the Notices

Prefix: Ms.

Last Name, First Name: Sappington, Amanda

Title: EHS Compliance Manager Credential: Click to enter text.

Organization Name: CSWR

Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131

Phone No.: 314-464-3976

E-mail Address: msappington@cswrgroup.com

D. Public Viewing Information

If the facility or outfall is located in more than one county, a public viewing place for each county must be provided.

Public building name: Livingston Municipal Library

Location within the building: Click to enter text.

Physical Address of Building: 707 N Tyler Avenue

City: Livingston

County: Polk

Contact (Last Name, First Name): Click to enter text.

Phone No.: 936-327-4252 Ext.: Click to enter text.

E. Bilingual Notice Requirements

This information **is required** for **new, major amendment, minor amendment or minor modification, and renewal** applications.

This section of the application is only used to determine if alternative language notices will be needed. Complete instructions on publishing the alternative language notices will be in your public notice package.

Please call the bilingual/ESL coordinator at the nearest elementary and middle schools and obtain the following information to determine whether an alternative language notices are required.

1. Is a bilingual education program required by the Texas Education Code at the elementary or middle school nearest to the facility or proposed facility?

☒ Yes

☐ No

If **no**, publication of an alternative language notice is not required; **skip to** Section 9 below.

2. Are the students who attend either the elementary school or the middle school enrolled in a bilingual education program at that school?

☐ Yes

☐ No

3. Do the students at these schools attend a bilingual education program at another location?

☐ Yes ☐ No

4. Would the school be required to provide a bilingual education program but the school has waived out of this requirement under 19 TAC §89.1205(g)?

☐ Yes ☐ No

5. If the answer is **yes** to **question 1, 2, 3, or 4**, public notices in an alternative language are required. Which language is required by the bilingual program? Spanish

F. Plain Language Summary Template

Complete the Plain Language Summary (TCEQ Form 20972) and include as an attachment.

Attachment: Attachment 2

G. Public Involvement Plan Form

Complete the Public Involvement Plan Form (TCEQ Form 20960) for each application for a **new permit or major amendment to a permit** and include as an attachment.

Attachment: Not Required

Section 9. Regulated Entity and Permitted Site Information (Instructions Page 29)

A. If the site is currently regulated by TCEQ, provide the Regulated Entity Number (RN) issued to this site. RN 102341294
Search the TCEQ's Central Registry at <http://www15.tceq.texas.gov/crpub/> to determine if the site is currently regulated by TCEQ.

B. Name of project or site (the name known by the community where located):

Texas Landing Wastewater Treatment Facility

C. Owner of treatment facility: CSWR-Texas Utility Operating Company, LLC

Ownership of Facility: ☐ Public ☒ Private ☐ Both ☐ Federal

D. Owner of land where treatment facility is or will be:

Prefix: Mr. Last Name, First Name: Cox, Josiah

Title: President Credential: Click to enter text.

Organization Name: CSWR-Texas Utility Operating Company, LLC

Mailing Address: 1630 Des Peres Road, Ste. 140 City, State, Zip Code: Des Peres, MO 63131

Phone No.: 314-736-4672 E-mail Address: jcox@cswrgroup.com

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: N/A

E. Owner of effluent disposal site:

Prefix: Mr.

Last Name, First Name: Cox, Josiah

Title: President

Credential: Click to enter text.

Organization Name: CSWR

Mailing Address: 1630 Des Peres Rd., Ste 140 City, State, Zip Code: Des Peres, MO 63131

Phone No.: 314-736-4672

E-mail Address: jcox@cswrgroup.com

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: Click to enter text.

F. Owner sewage sludge disposal site (if authorization is requested for sludge disposal on property owned or controlled by the applicant):

Prefix: N/A

Last Name, First Name: N/A

Title: N/A

Credential: N/A

Organization Name: N/A

Mailing Address: N/A

City, State, Zip Code: N/A

Phone No.: N/A

E-mail Address: N/A

If the landowner is not the same person as the facility owner or co-applicant, attach a lease agreement or deed recorded easement. See instructions.

Attachment: N/A

Section 10. TPDES Discharge Information (Instructions Page 31)

A. Is the wastewater treatment facility location in the existing permit accurate?

☒ Yes ☐ No

If **no**, or a new permit application, please give an accurate description:

N/A

B. Are the point(s) of discharge and the discharge route(s) in the existing permit correct?

☒ Yes ☐ No

If **no**, or a new or amendment permit application, provide an accurate description of the point of discharge and the discharge route to the nearest classified segment as defined in 30 TAC Chapter 307:

N/A

City nearest the outfall(s): Livingston

County in which the outfalls(s) is/are located: Polk

C. Is or will the treated wastewater discharge to a city, county, or state highway right-of-way, or a flood control district drainage ditch?

☐ Yes ☒ No

If **yes**, indicate by a check mark if:

- ☐ Authorization granted ☐ Authorization pending

For **new and amendment** applications, provide copies of letters that show proof of contact and the approval letter upon receipt.

Attachment: N/A

- D.** For all applications involving an average daily discharge of 5 MGD or more, provide the names of all counties located within 100 statute miles downstream of the point(s) of discharge: N/A

Section 11. TLAP Disposal Information (Instructions Page 32)

- A.** For TLAPs, is the location of the effluent disposal site in the existing permit accurate?

- ☐ Yes ☐ No

If **no**, or a **new or amendment permit application**, provide an accurate description of the disposal site location:

N/A

- B.** City nearest the disposal site: N/A

- C.** County in which the disposal site is located: N/A

- D.** For TLAPs, describe the routing of effluent from the treatment facility to the disposal site:

N/A

- E.** For TLAPs, please identify the nearest watercourse to the disposal site to which rainfall runoff might flow if not contained: N/A

Section 12. Miscellaneous Information (Instructions Page 32)

- A.** Is the facility located on or does the treated effluent cross American Indian Land?

- ☐ Yes ☒ No

- B.** If the existing permit contains an onsite sludge disposal authorization, is the location of the sewage sludge disposal site in the existing permit accurate?

- ☐ Yes ☐ No ☒ Not Applicable

If **No**, or if a new onsite sludge disposal authorization is being requested in this permit application, provide an accurate location description of the sewage sludge disposal site.

N/A

C. Did any person formerly employed by the TCEQ represent your company and get paid for service regarding this application?

☐ Yes ☒ No

If yes, list each person formerly employed by the TCEQ who represented your company and was paid for service regarding the application: N/A

D. Do you owe any fees to the TCEQ?

☐ Yes ☒ No

If yes, provide the following information:

Account number: N/A

Amount past due: N/A

E. Do you owe any penalties to the TCEQ?

☐ Yes ☒ No

If yes, please provide the following information:

Enforcement order number: N/A

Amount past due: N/A

Section 13. Attachments (Instructions Page 33)

Indicate which attachments are included with the Administrative Report. Check all that apply:

☐ Lease agreement or deed recorded easement, if the land where the treatment facility is located or the effluent disposal site are not owned by the applicant or co-applicant.

☒ Original full-size USGS Topographic Map with the following information:

- Applicant's property boundary
- Treatment facility boundary
- Labeled point of discharge for each discharge point (TPDES only)
- Highlighted discharge route for each discharge point (TPDES only)
- Onsite sewage sludge disposal site (if applicable)
- Effluent disposal site boundaries (TLAP only)
- New and future construction (if applicable)
- 1 mile radius information
- 3 miles downstream information (TPDES only)
- All ponds.

☐ Attachment 1 for Individuals as co-applicants

☒ Other Attachments. Please specify: 8x12 reproduced topo map

Section 14. Signature Page (Instructions Page 34)

If co-applicants are necessary, each entity must submit an original, separate signature page.

Permit Number: WQ0013147001

Applicant: Click to enter text.

Certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

I further certify that I am authorized under 30 Texas Administrative Code § 305.44 to sign and submit this document, and can provide documentation in proof of such authorization upon request.

Signatory name (typed or printed): Josiah Cox

Signatory title: President

Signature: _____ Date: 9/27/24

(Use blue ink)

Subscribed and Sworn to before me by the said Josiah Cox

on this 27th day of September, 20 24.


My commission expires on the 10th day of April, 20 27.

Roshawne Vallandingham

Notary Public

[SEAL]

St. Louis
County, Texas- MISSOURI



DOMESTIC WASTEWATER PERMIT APPLICATION ADMINISTRATIVE REPORT 1.0

The following information is required for new and amendment applications.

Section 1. Affected Landowner Information (Instructions Page 36)

- A. Indicate by a check mark that the landowners map or drawing, with scale, includes the following information, as applicable:
- ☐ The applicant's property boundaries
 - ☐ The facility site boundaries within the applicant's property boundaries
 - ☐ The distance the buffer zone falls into adjacent properties and the property boundaries of the landowners located within the buffer zone
 - ☐ The property boundaries of all landowners surrounding the applicant's property (Note: if the application is a major amendment for a lignite mine, the map must include the property boundaries of all landowners adjacent to the new facility (ponds).)
 - ☐ The point(s) of discharge and highlighted discharge route(s) clearly shown for one mile downstream
 - ☐ The property boundaries of the landowners located on both sides of the discharge route for one full stream mile downstream of the point of discharge
 - ☐ The property boundaries of the landowners along the watercourse for a one-half mile radius from the point of discharge if the point of discharge is into a lake, bay, estuary, or affected by tides
 - ☐ The boundaries of the effluent disposal site (for example, irrigation area or subsurface drainfield site) and all evaporation/holding ponds within the applicant's property
 - ☐ The property boundaries of all landowners surrounding the effluent disposal site
 - ☐ The boundaries of the sludge land application site (for land application of sewage sludge for beneficial use) and the property boundaries of landowners surrounding the applicant's property boundaries where the sewage sludge land application site is located
 - ☐ The property boundaries of landowners within one-half mile in all directions from the applicant's property boundaries where the sewage sludge disposal site (for example, sludge surface disposal site or sludge monofill) is located
- B. ☐ Indicate by a check mark that a separate list with the landowners' names and mailing addresses cross-referenced to the landowner's map has been provided.
- C. Indicate by a check mark in which format the landowners list is submitted:
- ☐ USB Drive
 - ☐ Four sets of labels
- D. Provide the source of the landowners' names and mailing addresses: Click to enter text.
- E. As required by *Texas Water Code § 5.115*, is any permanent school fund land affected by this application?
- ☐ Yes
 - ☐ No

If **yes**, provide the location and foreseeable impacts and effects this application has on the land(s):

Click to enter text.

Section 2. Original Photographs (Instructions Page 38)

Provide original ground level photographs. Indicate with checkmarks that the following information is provided.

- ☐ At least one original photograph of the new or expanded treatment unit location
- ☐ At least two photographs of the existing/proposed point of discharge and as much area downstream (photo 1) and upstream (photo 2) as can be captured. If the discharge is to an open water body (e.g., lake, bay), the point of discharge should be in the right or left edge of each photograph showing the open water and with as much area on each respective side of the discharge as can be captured.
- ☐ At least one photograph of the existing/proposed effluent disposal site
- ☐ A plot plan or map showing the location and direction of each photograph

Section 3. Buffer Zone Map (Instructions Page 38)

A. Buffer zone map. Provide a buffer zone map on 8.5 x 11-inch paper with all of the following information. The applicant's property line and the buffer zone line may be distinguished by using dashes or symbols and appropriate labels.

- The applicant's property boundary;
- The required buffer zone; and
- Each treatment unit; and
- The distance from each treatment unit to the property boundaries.

B. Buffer zone compliance method. Indicate how the buffer zone requirements will be met. Check all that apply.

- ☐ Ownership
- ☐ Restrictive easement
- ☐ Nuisance odor control
- ☐ Variance

C. Unsuitable site characteristics. Does the facility comply with the requirements regarding unsuitable site characteristic found in 30 TAC § 309.13(a) through (d)?

- ☐ Yes ☐ No

DOMESTIC WASTEWATER PERMIT APPLICATION

SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

This form applies to TPDES permit applications only. Complete and attach the Supplemental Permit information Form (SPIF) (TCEQ Form 20971).

Attachment: Attachment 3

WATER QUALITY PERMIT

PAYMENT SUBMITTAL FORM

Use this form to submit the Application Fee, if the mailing the payment.

- Complete items 1 through 5 below.
- Staple the check or money order in the space provided at the bottom of this document.
- **Do Not mail this form with the application form.**
- Do not mail this form to the same address as the application.
- Do not submit a copy of the application with this form as it could cause duplicate permit entries.

Mail this form and the check or money order to:

BY REGULAR U.S. MAIL

Texas Commission on Environmental Quality
Financial Administration Division
Cashier's Office, MC-214
P.O. Box 13088
Austin, Texas 78711-3088

BY OVERNIGHT/EXPRESS MAIL

Texas Commission on Environmental Quality
Financial Administration Division
Cashier's Office, MC-214
12100 Park 35 Circle
Austin, Texas 78753

Fee Code: WQP Waste Permit No: Click to enter text.

1. Check or Money Order Number: Click to enter text.
2. Check or Money Order Amount: Click to enter text.
3. Date of Check or Money Order: Click to enter text.
4. Name on Check or Money Order: Click to enter text.
5. APPLICATION INFORMATION

Name of Project or Site: Click to enter text.

Physical Address of Project or Site: Click to enter text.

If the check is for more than one application, attach a list which includes the name of each Project or Site (RE) and Physical Address, exactly as provided on the application.

Staple Check or Money Order in This Space

ATTACHMENT 1

INDIVIDUAL INFORMATION

Section 1. Individual Information (Instructions Page 41)

Complete this attachment if the facility applicant or co-applicant is an individual. Make additional copies of this attachment if both are individuals.

Prefix (Mr., Ms., Miss): N/A

Full legal name (Last Name, First Name, Middle Initial): N/A

Driver's License or State Identification Number: N/A

Date of Birth: N/A

Mailing Address: N/A

City, State, and Zip Code: N/A

Phone Number: N/A Fax Number: N/A

E-mail Address: N/A

CN: N/A

For Commission Use Only:

Customer Number:

Regulated Entity Number:

Permit Number:

DOMESTIC WASTEWATER PERMIT APPLICATION CHECKLIST OF COMMON DEFICIENCIES

Below is a list of common deficiencies found during the administrative review of domestic wastewater permit applications. To ensure the timely processing of this application, please review the items below and indicate by checking Yes that each item is complete and in accordance applicable rules at 30 TAC Chapters 21, 281, and 305. If an item is not required this application, indicate by checking N/A where appropriate. Please do not submit the application until the items below have been addressed.

Core Data Form (TCEQ Form No. 10400) ☒ Yes
(Required for all application types. Must be completed in its entirety and signed.
Note: Form may be signed by applicant representative.)

Correct and Current Industrial Wastewater Permit Application Forms ☒ Yes
(TCEQ Form Nos. 10053 and 10054. Version dated 6/25/2018 or later.)

Water Quality Permit Payment Submittal Form (Page 19) ☒ Yes
(Original payment sent to TCEQ Revenue Section. See instructions for mailing address.)

7.5 Minute USGS Quadrangle Topographic Map Attached ☒ Yes
(Full-size map if seeking "New" permit.
8 ½ x 11 acceptable for Renewals and Amendments)

Current/Non-Expired, Executed Lease Agreement or Easement ☒ N/A ☐ Yes

Landowners Map ☒ N/A ☐ Yes
(See instructions for landowner requirements)

Things to Know:


- All the items shown on the map must be labeled.
- The applicant's complete property boundaries must be delineated which includes boundaries of contiguous property owned by the applicant.
- The applicant cannot be its own adjacent landowner. You must identify the landowners immediately adjacent to their property, regardless of how far they are from the actual facility.
- If the applicant's property is adjacent to a road, creek, or stream, the landowners on the opposite side must be identified. Although the properties are not adjacent to applicant's property boundary, they are considered potentially affected landowners. If the adjacent road is a divided highway as identified on the USGS topographic map, the applicant does not have to identify the landowners on the opposite side of the highway.

Landowners Cross Reference List ☒ N/A ☐ Yes
(See instructions for landowner requirements)

Landowners Labels or USB Drive attached ☒ N/A ☐ Yes
(See instructions for landowner requirements)

Original signature per 30 TAC § 305.44 – Blue Ink Preferred ☒ Yes
(If signature page is not signed by an elected official or principle executive officer,
a copy of signature authority/delegation letter must be attached)

Plain Language Summary ☒ Yes



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

PLAIN LANGUAGE SUMMARY FOR TPDES OR TLAP PERMIT APPLICATIONS

Plain Language Summary Template and Instructions for Texas Pollutant Discharge Elimination System (TPDES) and Texas Land Application (TLAP) Permit Applications

Applicants should use this template to develop a plain language summary as required by [Title 30, Texas Administrative Code \(30 TAC\), Chapter 39, Subchapter H](#). Applicants may modify the template as necessary to accurately describe their facility as long as the summary includes the following information: (1) the function of the proposed plant or facility; (2) the expected output of the proposed plant or facility; (3) the expected pollutants that may be emitted or discharged by the proposed plant or facility; and (4) how the applicant will control those pollutants, so that the proposed plant will not have an adverse impact on human health or the environment.

Fill in the highlighted areas below to describe your facility and application in plain language. Instructions and examples are provided below. Make any other edits necessary to improve readability or grammar and to comply with the rule requirements.

If you are subject to the alternative language notice requirements in [30 TAC Section 39.426](#), **you must provide a translated copy of the completed plain language summary in the appropriate alternative language as part of your application package.** For your convenience, a Spanish template has been provided below.

ENGLISH TEMPLATE FOR TPDES or TLAP NEW/RENEWAL/AMENDMENT APPLICATIONS DOMESTIC WASTEWATER/STORMWATER

The following summary is provided for this pending water quality permit application being reviewed by the Texas Commission on Environmental Quality as required by 30 TAC Chapter 39. The information provided in this summary may change during the technical review of the application and is not a federal enforceable representation of the permit application.

CSWR (CN605844786) operates Texas Landing WWTF (RN102341294), a domestic wastewater treatment plant. The facility is located at 404 Branding Iron, in Livingston, Polk County, Texas 77351. This facility is applying for a permit renewal to discharge 65,000 gallons per day of treated domestic wastewater.

Discharges from the facility are expected to contain BOD, TSS, and E. coli. The domestic wastewater discharge is treated by an activated sludge system. Wastewater flows from the influent lift station to the raw bar screen to the aeration unit. From the aeration unit, the wastewater then runs through the clarifier where some of the sludge goes to the digester for wasting and the remaining sludge is returned to the inflow of the aeration unit. The wastewater that leaves the clarifier is then chlorinated prior to discharging into Lake Livingston. The WWTP operated in single phase nitrification.

PLANTILLA EN ESPAÑOL PARA SOLICITUDES NUEVAS/RENOVACIONES/ENMIENDAS DE TPDES o TLAP

AGUAS RESIDUALES *Domesticas* /AGUAS PLUVIALES

El siguiente resumen se proporciona para esta solicitud de permiso de calidad del agua pendiente que está siendo revisada por la Comisión de Calidad Ambiental de Texas según lo requerido por el Capítulo 39 del Código Administrativo de Texas 30. La información proporcionada en este resumen puede cambiar durante la revisión técnica de la solicitud y no es una representación fedérale de la solicitud de permiso.

CSWR (CN605844786) opera Texas Landing WWTF (RN102341294), una facilidad para tratar residuales domesticas. La instalación está ubicada en 404 Branding Iron, en Livingston, Condado de Polk, Texas 77351. Esta instalación está solicitando la renovación de un permiso para descargar 65,000 galones por día de aguas residuales domésticas tratadas.

Se espera que las descargas de la instalación contengan BOD, TSS, y E. coli. Las residuales domesticas. están tratado por un sistema de lodos activados. Las aguas residuales fluyen desde la estación de bombeo de influentes hacia la rejilla de cribado primaria y luego a la unidad de aireación. Desde la unidad de aireación, las aguas residuales pasan por el clarificador, donde una parte de los lodos se envía al digestor para ser desechados y el resto de los lodos se devuelve a la entrada de la unidad de aireación. Las aguas residuales que salen del clarificador luego se cloran antes de descargarse en el Lago Livingston. La planta de tratamiento de aguas residuales (WWTF) opera en una fase única de nitrificación..

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY
SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

**FOR AGENCIES REVIEWING DOMESTIC OR INDUSTRIAL
TPDES WASTEWATER PERMIT APPLICATIONS**

TCEQ USE ONLY:

Application type: ____Renewal ____Major Amendment ____Minor Amendment ____New

County: _____ Segment Number: _____

Admin Complete Date: _____

Agency Receiving SPIF:

____ Texas Historical Commission

____ U.S. Fish and Wildlife

____ Texas Parks and Wildlife Department

____ U.S. Army Corps of Engineers

This form applies to TPDES permit applications only. (Instructions, Page 53)

Complete this form as a separate document. TCEQ will mail a copy to each agency as required by our agreement with EPA. If any of the items are not completely addressed or further information is needed, we will contact you to provide the information before issuing the permit. Address each item completely.

Do not refer to your response to any item in the permit application form. Provide each attachment for this form separately from the Administrative Report of the application. The application will not be declared administratively complete without this SPIF form being completed in its entirety including all attachments. Questions or comments concerning this form may be directed to the Water Quality Division's Application Review and Processing Team by email at WQ-ARPTeam@tceq.texas.gov or by phone at (512) 239-4671.

The following applies to all applications:

1. Permittee: CSWR-Texas Utility Operating Company, LLC

Permit No. WQ00 13147001

EPA ID No. TX 0098809

Address of the project (or a location description that includes street/highway, city/vicinity, and county):

404 Branding Iron, Livingston, Polk County, Texas, 77351

Provide the name, address, phone and fax number of an individual that can be contacted to answer specific questions about the property.

Prefix (Mr., Ms., Miss): Ms.

First and Last Name: Amanda Sappington

Credential (P.E, P.G., Ph.D., etc.):

Title: EHS Compliance Manager

Mailing Address: 1630 Des Peres Road, Ste. 140

City, State, Zip Code: Des Peres, Mo 63131

Phone No.: 314-380-9508 Ext.:

Fax No.:

E-mail Address: msappington@cswrgroup.com

2. List the county in which the facility is located: Bexar
3. If the property is publicly owned and the owner is different than the permittee/applicant, please list the owner of the property.

N/A

4. Provide a description of the effluent discharge route. The discharge route must follow the flow of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.

Directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin

5. Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).

Provide original photographs of any structures 50 years or older on the property.

Does your project involve any of the following? Check all that apply.

- ☐ Proposed access roads, utility lines, construction easements
- ☐ Visual effects that could damage or detract from a historic property's integrity
- ☐ Vibration effects during construction or as a result of project design
- ☐ Additional phases of development that are planned for the future
- ☐ Sealing caves, fractures, sinkholes, other karst features

☐ Disturbance of vegetation or wetlands

1. List proposed construction impact (surface acres to be impacted, depth of excavation, sealing of caves, or other karst features):

none

2. Describe existing disturbances, vegetation, and land use:

None, existing WWTF

THE FOLLOWING ITEMS APPLY ONLY TO APPLICATIONS FOR NEW TPDES PERMITS AND MAJOR AMENDMENTS TO TPDES PERMITS

3. List construction dates of all buildings and structures on the property:

N/A

4. Provide a brief history of the property, and name of the architect/builder, if known.

N/A



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

DOMESTIC WASTEWATER PERMIT APPLICATION TECHNICAL REPORT 1.0

For any questions about this form, please contact the Domestic Wastewater Permitting Team at 512-239-4671.

The following information is required for all renewal, new, and amendment applications.

Section 1. Permitted or Proposed Flows (Instructions Page 43)

A. Existing/Interim I Phase

Design Flow (MGD): 0.065 MGD

2-Hr Peak Flow (MGD): 181 gpm

Estimated construction start date: Click to enter text.

Estimated waste disposal start date: Click to enter text.

B. Interim II Phase

Design Flow (MGD): Click to enter text.

2-Hr Peak Flow (MGD): Click to enter text.

Estimated construction start date: Click to enter text.

Estimated waste disposal start date: Click to enter text.

C. Final Phase

Design Flow (MGD): 0.065 MGD

2-Hr Peak Flow (MGD): 181 gpm

Estimated construction start date: Click to enter text.

Estimated waste disposal start date: Click to enter text.

D. Current Operating Phase

Provide the startup date of the facility: operating currently

Section 2. Treatment Process (Instructions Page 43)

A. Current Operating Phase

Provide a detailed description of the treatment process. **Include the type of treatment plant, mode of operation, and all treatment units.** Start with the plant's head works and

finish with the point of discharge. Include all sludge processing and drying units. **If more than one phase exists or is proposed, a description of *each phase* must be provided.**

Texas landing is an activated sludge system. Wastewater flows from the influent lift station to the raw water bar screen to the aeration unit. From the aeration unit, the wastewater then runs through the clarifier where some of the sludge goes to the digester for wasting and the remaining sludge is returned to the inflow of the aeration unit. The wastewater that leaves the clarifier is then chlorinated prior to discharging into Lake Livingston. The WWTP operated in single phase nitrification.

B. Treatment Units

In Table 1.0(1), provide the treatment unit type, the number of units, and dimensions (length, width, depth) of **each treatment unit, accounting for *all* phases of operation.**

Table 1.0(1) - Treatment Units

Treatment Unit Type	Number of Units	Dimensions (L x W x D)
Clarifier	1	10'R x 11'D
Aeration Basin	1	7'6"L x 11'7"W x 11'D
Digester Basin	1	32'4"L x 11'7"W x 11'D
Chlorine Contact Chamber	1	14'6"L x 11'7"W x 11'D

C. Process Flow Diagram

Provide flow diagrams for the existing facilities and **each** proposed phase of construction.

Attachment: Attachment 5

Section 3. Site Information and Drawing (Instructions Page 44)

Provide the TPDES discharge outfall latitude and longitude. Enter N/A if not applicable.

- Latitude: 95°02'05"W
- Longitude: 30°42'27"N

Provide the TLAP disposal site latitude and longitude. Enter N/A if not applicable.

- Latitude: N/A
- Longitude: N/A

Provide a site drawing for the facility that shows the following:

- The boundaries of the treatment facility;
- The boundaries of the area served by the treatment facility;
- If land disposal of effluent, the boundaries of the disposal site and all storage/holding ponds; and
- If sludge disposal is authorized in the permit, the boundaries of the land application or disposal site.

Attachment: Attachment 5

Provide the name **and** a description of the area served by the treatment facility.

Texas Landing WWTF serves the Texas Landing Subdivision in Polk Co.

Collection System Information **for wastewater TPDES permits only**: Provide information for each **uniquely owned** collection system, existing and new, served by this facility, including satellite collection systems. **Please see the instructions for a detailed explanation and examples.**

Collection System Information

Collection System Name	Owner Name	Owner Type	Population Served
Texas Landing Collection System	CSWR-Texas	Privately Owned	97
		Choose an item.	
		Choose an item.	
		Choose an item.	

Section 4. Unbuilt Phases (Instructions Page 45)

Is the application for a renewal of a permit that contains an unbuilt phase or phases?

☐ Yes ☒ No

If yes, does the existing permit contain a phase that has not been constructed **within five** years of being authorized by the TCEQ?

☐ Yes ☒ No

If yes, provide a detailed discussion regarding the continued need for the unbuilt phase. **Failure to provide sufficient justification may result in the Executive Director recommending denial of the unbuilt phase or phases.**

N/A

Section 5. Closure Plans (Instructions Page 45)

Have any treatment units been taken out of service permanently, or will any units be taken out of service in the next five years?

☒ Yes ☐ No

If yes, was a closure plan submitted to the TCEQ?

☒ Yes ☐ No

If yes, provide a brief description of the closure and the date of plan approval.

Partial site closure: removal of the old wastewater plant equipment: Power washing of all structures that are to be decommissioned and removal of any remaining wastewater. Disassemble and haul off scrap metal from the package treatment unit and clarifier tank. Soil sampling beneath and in the back of the decommissioned structures. Approved December 14, 2023, by J. Alfonso Martinez III

Section 6. Permit Specific Requirements (Instructions Page 45)

For applicants with an existing permit, check the Other Requirements or Special Provisions of the permit.

A. Summary transmittal

Have plans and specifications been approved for the existing facilities and each proposed phase?

☐ Yes ☒ No

If yes, provide the date(s) of approval for each phase: N/A

Provide information, including dates, on any actions taken to meet a *requirement or provision* pertaining to the submission of a summary transmittal letter. **Provide a copy of an approval letter from the TCEQ, if applicable.**

Click to enter text.

B. Buffer zones

Have the buffer zone requirements been met?

☒ Yes ☐ No

Provide information below, including dates, on any actions taken to meet the conditions of the buffer zone. If available, provide any new documentation relevant to maintaining the buffer zones.

Click to enter text.

C. Other actions required by the current permit

Does the *Other Requirements* or *Special Provisions* section in the existing permit require submission of any other information or other required actions? Examples include Notification of Completion, progress reports, soil monitoring data, etc.

☐ Yes ☒ No

If **yes**, provide information below on the status of any actions taken to meet the conditions of an *Other Requirement* or *Special Provision*.

Click to enter text.

D. Grit and grease treatment

1. Acceptance of grit and grease waste

Does the facility have a grit and/or grease processing facility onsite that treats and decants or accepts transported loads of grit and grease waste that are discharged directly to the wastewater treatment plant prior to any treatment?

☐ Yes ☒ No

If **No**, stop here and continue with Subsection E. Stormwater Management.

2. Grit and grease processing

Describe below how the grit and grease waste is treated at the facility. In your description, include how and where the grit and grease is introduced to the treatment works and how it is separated or processed. Provide a flow diagram showing how grit and grease is processed at the facility.

N/A

3. Grit disposal

Does the facility have a Municipal Solid Waste (MSW) registration or permit for grit disposal?

☐ Yes ☐ No

If **No**, contact the TCEQ Municipal Solid Waste team at 512-239-2335. Note: A registration or permit is required for grit disposal. Grit shall not be combined with treatment plant sludge. See the instruction booklet for additional information on grit disposal requirements and restrictions.

Describe the method of grit disposal.

Click to enter text.

4. Grease and decanted liquid disposal

Note: A registration or permit is required for grease disposal. Grease shall not be combined with treatment plant sludge. For more information, contact the TCEQ Municipal Solid Waste team at 512-239-2335.

Describe how the decant and grease are treated and disposed of after grit separation.

Click to enter text.

E. Stormwater management

1. Applicability

Does the facility have a design flow of 1.0 MGD or greater in any phase?

☐ Yes ☒ No

Does the facility have an approved pretreatment program, under 40 CFR Part 403?

☐ Yes ☒ No

If no to both of the above, then skip to Subsection F, Other Wastes Received.

2. MSGP coverage

Is the stormwater runoff from the WWTP and dedicated lands for sewage disposal currently permitted under the TPDES Multi-Sector General Permit (MSGP), TXR050000?

☐ Yes ☐ No

If yes, please provide MSGP Authorization Number and skip to Subsection F, Other Wastes Received:

TXR05 Click to enter text. or TXRNE Click to enter text.

If no, do you intend to seek coverage under TXR050000?

☐ Yes ☐ No

3. Conditional exclusion

Alternatively, do you intend to apply for a conditional exclusion from permitting based TXR050000 (Multi Sector General Permit) Part II B.2 or TXR050000 (Multi Sector General Permit) Part V, Sector T 3(b)?

☐ Yes ☐ No

If **yes**, please explain below then proceed to Subsection F, Other Wastes Received:

Click to enter text.

4. Existing coverage in individual permit

Is your stormwater discharge currently permitted through this individual TPDES or TLAP permit?

☐ Yes ☐ No

If **yes**, provide a description of stormwater runoff management practices at the site that are authorized in the wastewater permit then skip to Subsection F, Other Wastes Received.

Click to enter text.

5. Zero stormwater discharge

Do you intend to have no discharge of stormwater via use of evaporation or other means?

☐ Yes ☐ No

If **yes**, explain below then skip to Subsection F. Other Wastes Received.

Click to enter text.

Note: If there is a potential to discharge any stormwater to surface water in the state as the result of any storm event, then permit coverage is required under the MSGP or an individual discharge permit. This requirement applies to all areas of facilities with treatment plants or systems that treat, store, recycle, or reclaim domestic sewage, wastewater or sewage sludge (including dedicated lands for sewage sludge disposal located within the onsite property boundaries) that meet the applicability criteria of above. You have the option of obtaining coverage under the MSGP for direct discharges, (recommended), or obtaining coverage under this individual permit.

6. Request for coverage in individual permit

Are you requesting coverage of stormwater discharges associated with your treatment plant under this individual permit?

☐ Yes ☐ No

If **yes**, provide a description of stormwater runoff management practices at the site for which you are requesting authorization in this individual wastewater permit and describe whether you intend to comingle this discharge with your treated effluent or discharge it via a separate dedicated stormwater outfall. Please also indicate if you

intend to divert stormwater to the treatment plant headworks and indirectly discharge it to water in the state.

Click to enter text.

Note: Direct stormwater discharges to waters in the state authorized through this individual permit will require the development and implementation of a stormwater pollution prevention plan (SWPPP) and will be subject to additional monitoring and reporting requirements. Indirect discharges of stormwater via headworks recycling will require compliance with all individual permit requirements including 2-hour peak flow limitations. All stormwater discharge authorization requests will require additional information during the technical review of your application.

F. Discharges to the Lake Houston Watershed

Does the facility discharge in the Lake Houston watershed?

☐ Yes ☒ No

If yes, attach a Sewage Sludge Solids Management Plan. See Example 5 in the instructions.
[Click to enter text.](#)

G. Other wastes received including sludge from other WWTPs and septic waste

1. Acceptance of sludge from other WWTPs

Does or will the facility accept sludge from other treatment plants at the facility site?

☐ Yes ☒ No

If yes, attach sewage sludge solids management plan. See Example 5 of instructions.

In addition, provide the date the plant started or is anticipated to start accepting sludge, an estimate of monthly sludge acceptance (gallons or millions of gallons), an estimate of the BOD₅ concentration of the sludge, and the design BOD₅ concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.

Click to enter text.

Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.

2. Acceptance of septic waste

Is the facility accepting or will it accept septic waste?

☐ Yes ☒ No

If yes, does the facility have a Type V processing unit?

☐ Yes ☒ No

If yes, does the unit have a Municipal Solid Waste permit?

☐ Yes ☒ No

If **yes to any of the above**, provide the date the plant started or is anticipated to start accepting septic waste, an estimate of monthly septic waste acceptance (gallons or millions of gallons), an estimate of the BOD₅ concentration of the septic waste, and the design BOD₅ concentration of the influent from the collection system. Also note if this information has or has not changed since the last permit action.

Click to enter text.

Note: Permits that accept sludge from other wastewater treatment plants may be required to have influent flow and organic loading monitoring.

3. Acceptance of other wastes (not including septic, grease, grit, or RCRA, CERCLA or as discharged by IUs listed in Worksheet 6)

Is or will the facility accept wastes that are not domestic in nature excluding the categories listed above?

☐ Yes ☒ No

If **yes**, provide the date that the plant started accepting the waste, an estimate how much waste is accepted on a monthly basis (gallons or millions of gallons), a description of the entities generating the waste, and any distinguishing chemical or other physical characteristic of the waste. Also note if this information has or has not changed since the last permit action.

Click to enter text.

Section 7. Pollutant Analysis of Treated Effluent (Instructions Page 50)

Is the facility in operation?

☒ Yes ☐ No

If **no**, this section is not applicable. Proceed to Section 8.

If **yes**, provide effluent analysis data for the listed pollutants. **Wastewater treatment facilities** complete Table 1.0(2). **Water treatment facilities** discharging filter backwash water, complete Table 1.0(3). Provide copies of the laboratory results sheets. **These tables are not applicable for a minor amendment without renewal.** See the instructions for guidance.

Note: The sample date must be within 1 year of application submission.

Table1.0(2) – Pollutant Analysis for Wastewater Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
CBOD ₅ , mg/l	<2 mg/L	<2 mg/L	4	Grab	8/7, 8/14, 8/21, and 8/28 2024
Total Suspended Solids, mg/l	3.25 mg/L	4 mg/L	4	Grab	same
Ammonia Nitrogen, mg/l					
Nitrate Nitrogen, mg/l					
Total Kjeldahl Nitrogen, mg/l					
Sulfate, mg/l					
Chloride, mg/l					
Total Phosphorus, mg/l					
pH, standard units					
Dissolved Oxygen*, mg/l					
Chlorine Residual, mg/l					
<i>E.coli</i> (CFU/100ml) freshwater	2 MPN	2 MPN	1	Grab	8/27/2024
Enterococci (CFU/100ml) saltwater					
Total Dissolved Solids, mg/l					
Electrical Conductivity, μ mohs/cm, †					
Oil & Grease, mg/l					
Alkalinity (CaCO ₃)*, mg/l					

*TPDES permits only

†TLAP permits only

Table1.0(3) – Pollutant Analysis for Water Treatment Facilities

Pollutant	Average Conc.	Max Conc.	No. of Samples	Sample Type	Sample Date/Time
Total Suspended Solids, mg/l					
Total Dissolved Solids, mg/l					
pH, standard units					
Fluoride, mg/l					
Aluminum, mg/l					
Alkalinity (CaCO ₃), mg/l					

Section 8. Facility Operator (Instructions Page 50)

Facility Operator Name: Taylor WintersteenFacility Operator's License Classification and Level: Wastewater OperatorA Facility Operator's License Number: WW0066459

Section 9. Sludge and Biosolids Management and Disposal (Instructions Page 51)

A. WWTP's Biosolids Management Facility Type

Check all that apply. See instructions for guidance

- ☐ Design flow \geq 1 MGD
- ☐ Serves \geq 10,000 people
- ☐ Class I Sludge Management Facility (per 40 CFR § 503.9)
- ☐ Biosolids generator
- ☐ Biosolids end user – land application (onsite)
- ☐ Biosolids end user – surface disposal (onsite)
- ☐ Biosolids end user – incinerator (onsite)

B. WWTP's Biosolids Treatment Process

Check all that apply. See instructions for guidance.

- ☒ Aerobic Digestion
- ☐ Air Drying (or sludge drying beds)
- ☐ Lower Temperature Composting
- ☐ Lime Stabilization
- ☐ Higher Temperature Composting
- ☐ Heat Drying
- ☐ Thermophilic Aerobic Digestion
- ☐ Beta Ray Irradiation
- ☐ Gamma Ray Irradiation
- ☐ Pasteurization
- ☐ Preliminary Operation (e.g. grinding, de-gritting, blending)
- ☐ Thickening (e.g. gravity thickening, centrifugation, filter press, vacuum filter)
- ☐ Sludge Lagoon
- ☐ Temporary Storage (< 2 years)
- ☐ Long Term Storage (≥ 2 years)
- ☐ Methane or Biogas Recovery
- ☒ Other Treatment Process: hauled

C. Biosolids Management

Provide information on the *intended* biosolids management practice. Do not enter every management practice that you want authorized in the permit, as the permit will authorize

all biosolids management practices listed in the instructions. Rather indicate the management practice the facility plans to use.

Biosolids Management

Management Practice	Handler or Preparer Type	Bulk or Bag Container	Amount (dry metric tons)	Pathogen Reduction Options	Vector Attraction Reduction Option
Other	Choose an item.	Choose an item.		Choose an item.	Choose an item.
Choose an item.	Choose an item.	Choose an item.		Choose an item.	Choose an item.
Choose an item.	Choose an item.	Choose an item.		Choose an item.	Choose an item.

If "Other" is selected for Management Practice, please explain (e.g. monofill or transport to another WWTP): Transport to other WWTP

D. Disposal site

Disposal site name: Mt Houston WWTP

TCEQ permit or registration number: WQ0005023000

County where disposal site is located: Harris

E. Transportation method

Method of transportation (truck, train, pipe, other): Truck

Name of the hauler: Magna-Flow International

Hauler registration number: 21484

Sludge is transported as a:

Liquid ☒ semi-liquid ☐ semi-solid ☐ solid ☐

Section 10. Permit Authorization for Sewage Sludge Disposal (Instructions Page 53)

A. Beneficial use authorization

Does the existing permit include authorization for land application of sewage sludge for beneficial use?

☐ Yes ☒ No

If yes, are you requesting to continue this authorization to land apply sewage sludge for beneficial use?

☐ Yes ☒ No

If yes, is the completed **Application for Permit for Beneficial Land Use of Sewage Sludge** (TCEQ Form No. 10451) attached to this permit application (see the instructions for details)?

☐ Yes ☐ No

B. Sludge processing authorization

Does the existing permit include authorization for any of the following sludge processing, storage or disposal options?

- | | | |
|--|------------------------------|--|
| Sludge Composting | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| Marketing and Distribution of sludge | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| Sludge Surface Disposal or Sludge Monofill | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |
| Temporary storage in sludge lagoons | <input type="checkbox"/> Yes | <input checked="" type="checkbox"/> No |

If **yes** to any of the above sludge options and the applicant is requesting to continue this authorization, is the completed **Domestic Wastewater Permit Application: Sewage Sludge Technical Report (TCEQ Form No. 10056)** attached to this permit application?

- ☐ Yes ☐ No

Section 11. Sewage Sludge Lagoons (Instructions Page 53)

Does this facility include sewage sludge lagoons?

- ☐ Yes ☒ No

If yes, complete the remainder of this section. If no, proceed to Section 12.

A. Location information

The following maps are required to be submitted as part of the application. For each map, provide the Attachment Number.

- Original General Highway (County) Map:
Attachment: [Click to enter text.](#)
- USDA Natural Resources Conservation Service Soil Map:
Attachment: [Click to enter text.](#)
- Federal Emergency Management Map:
Attachment: [Click to enter text.](#)
- Site map:
Attachment: [Click to enter text.](#)

Discuss in a description if any of the following exist within the lagoon area. Check all that apply.

- ☐ Overlap a designated 100-year frequency flood plain
- ☐ Soils with flooding classification
- ☐ Overlap an unstable area
- ☐ Wetlands
- ☐ Located less than 60 meters from a fault
- ☐ None of the above

Attachment: [Click to enter text.](#)

If a portion of the lagoon(s) is located within the 100-year frequency flood plain, provide the protective measures to be utilized including type and size of protective structures:

Click to enter text.

B. Temporary storage information

Provide the results for the pollutant screening of sludge lagoons. These results are in addition to pollutant results in *Section 7 of Technical Report 1.0*.

Nitrate Nitrogen, mg/kg: [Click to enter text.](#)

Total Kjeldahl Nitrogen, mg/kg: [Click to enter text.](#)

Total Nitrogen (=nitrate nitrogen + TKN), mg/kg: [Click to enter text.](#)

Phosphorus, mg/kg: [Click to enter text.](#)

Potassium, mg/kg: [Click to enter text.](#)

pH, standard units: [Click to enter text.](#)

Ammonia Nitrogen mg/kg: [Click to enter text.](#)

Arsenic: [Click to enter text.](#)

Cadmium: [Click to enter text.](#)

Chromium: [Click to enter text.](#)

Copper: [Click to enter text.](#)

Lead: [Click to enter text.](#)

Mercury: [Click to enter text.](#)

Molybdenum: [Click to enter text.](#)

Nickel: [Click to enter text.](#)

Selenium: [Click to enter text.](#)

Zinc: [Click to enter text.](#)

Total PCBs: [Click to enter text.](#)

Provide the following information:

Volume and frequency of sludge to the lagoon(s): [Click to enter text.](#)

Total dry tons stored in the lagoons(s) per 365-day period: [Click to enter text.](#)

Total dry tons stored in the lagoons(s) over the life of the unit: [Click to enter text.](#)

C. Liner information

Does the active/proposed sludge lagoon(s) have a liner with a maximum hydraulic conductivity of 1×10^{-7} cm/sec?

☐ Yes ☐ No

If **yes**, describe the liner below. Please note that a liner is required.

Click to enter text.

D. Site development plan

Provide a detailed description of the methods used to deposit sludge in the lagoon(s):

Click to enter text.

Attach the following documents to the application.

- Plan view and cross-section of the sludge lagoon(s)
Attachment: [Click to enter text.](#)
- Copy of the closure plan
Attachment: [Click to enter text.](#)
- Copy of deed recordation for the site
Attachment: [Click to enter text.](#)
- Size of the sludge lagoon(s) in surface acres and capacity in cubic feet and gallons
Attachment: [Click to enter text.](#)
- Description of the method of controlling infiltration of groundwater and surface water from entering the site
Attachment: [Click to enter text.](#)
- Procedures to prevent the occurrence of nuisance conditions
Attachment: [Click to enter text.](#)

E. Groundwater monitoring

Is groundwater monitoring currently conducted at this site, or are any wells available for groundwater monitoring, or are groundwater monitoring data otherwise available for the sludge lagoon(s)?

☐ Yes ☐ No

If groundwater monitoring data are available, provide a copy. Provide a profile of soil types encountered down to the groundwater table and the depth to the shallowest groundwater as a separate attachment.

Attachment: [Click to enter text.](#)

Section 12. Authorizations/Compliance/Enforcement (Instructions Page 55)

A. Additional authorizations

Does the permittee have additional authorizations for this facility, such as reuse authorization, sludge permit, etc?

☐ Yes ☒ No

If yes, provide the TCEQ authorization number and description of the authorization:

Click to enter text.

B. Permittee enforcement status

Is the permittee currently under enforcement for this facility?

☐ Yes ☒ No

Is the permittee required to meet an implementation schedule for compliance or enforcement?

☐ Yes ☒ No

If yes to either question, provide a brief summary of the enforcement, the implementation schedule, and the current status:

Click to enter text.

Section 13. RCRA/CERCLA Wastes (Instructions Page 55)

A. RCRA hazardous wastes

Has the facility received in the past three years, does it currently receive, or will it receive RCRA hazardous waste?

☐ Yes ☒ No

B. Remediation activity wastewater

Has the facility received in the past three years, does it currently receive, or will it receive CERCLA wastewater, RCRA remediation/corrective action wastewater or other remediation activity wastewater?

☐ Yes ☒ No

C. Details about wastes received

If yes to either Subsection A or B above, provide detailed information concerning these wastes with the application.

Attachment: [Click to enter text.](#)

Section 14. Laboratory Accreditation (Instructions Page 56)

All laboratory tests performed must meet the requirements of *30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification*, which includes the following general exemptions from National Environmental Laboratory Accreditation Program (NELAP) certification requirements:

- The laboratory is an in-house laboratory and is:
 - periodically inspected by the TCEQ; or
 - located in another state and is accredited or inspected by that state; or
 - performing work for another company with a unit located in the same site; or
 - performing pro bono work for a governmental agency or charitable organization.
- The laboratory is accredited under federal law.
- The data are needed for emergency-response activities, and a laboratory accredited under the Texas Laboratory Accreditation Program is not available.
- The laboratory supplies data for which the TCEQ does not offer accreditation.

The applicant should review 30 TAC Chapter 25 for specific requirements.

The following certification statement shall be signed and submitted with every application. See the Signature Page section in the Instructions, for a list of designated representatives who may sign the certification.

CERTIFICATION:

I certify that all laboratory tests submitted with this application meet the requirements of *30 TAC Chapter 25, Environmental Testing Laboratory Accreditation and Certification*.

Printed Name: Iosiah Cox

Title: President

Signature: _____

Date: 09/27/24

DOMESTIC WASTEWATER PERMIT APPLICATION

WORKSHEET 2.0: RECEIVING WATERS

The following information is required for all TPDES permit applications.

Section 1. Domestic Drinking Water Supply (Instructions Page 64)

Is there a surface water intake for domestic drinking water supply located within 5 miles downstream from the point or proposed point of discharge?

☒ Yes ☐ No

If **no**, proceed to Section 2. If **yes**, provide the following:

Owner of the drinking water supply: Lake Livingston Water Supply

Distance and direction to the intake: 3.0 miles, in Lake Livingston

Attach a USGS map that identifies the location of the intake.

Attachment: Attachment 6

Section 2. Discharge into Tidally Affected Waters (Instructions Page 64)

Does the facility discharge into tidally affected waters?

☐ Yes ☒ No

If **no**, proceed to Section 3. If **yes**, complete the remainder of this section. If **no**, proceed to Section 3.

A. Receiving water outfall

Width of the receiving water at the outfall, in feet: Click to enter text.

B. Oyster waters

Are there oyster waters in the vicinity of the discharge?

☐ Yes ☐ No

If **yes**, provide the distance and direction from outfall(s).

Click to enter text.

C. Sea grasses

Are there any sea grasses within the vicinity of the point of discharge?

☐ Yes ☐ No

If **yes**, provide the distance and direction from the outfall(s).

Click to enter text.

Section 3. Classified Segments (Instructions Page 64)

Is the discharge directly into (or within 300 feet of) a classified segment?

☒ Yes ☐ No

If **yes**, this Worksheet is complete.

If **no**, complete Sections 4 and 5 of this Worksheet.

Section 4. Description of Immediate Receiving Waters (Instructions Page 65)

Name of the immediate receiving waters: Click to enter text.

A. Receiving water type

Identify the appropriate description of the receiving waters.

- ☐ Stream
- ☐ Freshwater Swamp or Marsh
- ☐ Lake or Pond

Surface area, in acres: Click to enter text.

Average depth of the entire water body, in feet: Click to enter text.

Average depth of water body within a 500-foot radius of discharge point, in feet:
Click to enter text.

- ☐ Man-made Channel or Ditch
- ☐ Open Bay
- ☐ Tidal Stream, Bayou, or Marsh
- ☐ Other, specify: Click to enter text.

B. Flow characteristics

If a stream, man-made channel or ditch was checked above, provide the following. For existing discharges, check one of the following that best characterizes the area *upstream* of the discharge. For new discharges, characterize the area *downstream* of the discharge (check one).

- ☐ Intermittent - dry for at least one week during most years
- ☐ Intermittent with Perennial Pools - enduring pools with sufficient habitat to maintain significant aquatic life uses
- ☐ Perennial - normally flowing

Check the method used to characterize the area upstream (or downstream for new dischargers).

- ☐ USGS flow records
- ☐ Historical observation by adjacent landowners
- ☐ Personal observation
- ☐ Other, specify: Click to enter text.

C. Downstream perennial confluences

List the names of all perennial streams that join the receiving water within three miles downstream of the discharge point.

Click to enter text.

D. Downstream characteristics

Do the receiving water characteristics change within three miles downstream of the discharge (e.g., natural or man-made dams, ponds, reservoirs, etc.)?

☐ Yes ☐ No

If yes, discuss how.

Click to enter text.

E. Normal dry weather characteristics

Provide general observations of the water body during normal dry weather conditions.

Click to enter text.

Date and time of observation: Click to enter text.

Was the water body influenced by stormwater runoff during observations?

☐ Yes ☐ No

Section 5. General Characteristics of the Waterbody (Instructions Page 66)

A. Upstream influences

Is the immediate receiving water upstream of the discharge or proposed discharge site influenced by any of the following? Check all that apply.

- | | |
|---|---|
| <input type="checkbox"/> Oil field activities | <input type="checkbox"/> Urban runoff |
| <input type="checkbox"/> Upstream discharges | <input type="checkbox"/> Agricultural runoff |
| <input type="checkbox"/> Septic tanks | <input type="checkbox"/> Other(s), specify: <u>Click to enter text.</u> |

B. Waterbody uses


Observed or evidences of the following uses. Check all that apply.

- | | |
|--|---|
| <input type="checkbox"/> Livestock watering | <input type="checkbox"/> Contact recreation |
| <input type="checkbox"/> Irrigation withdrawal | <input type="checkbox"/> Non-contact recreation |
| <input type="checkbox"/> Fishing | <input type="checkbox"/> Navigation |
| <input type="checkbox"/> Domestic water supply | <input type="checkbox"/> Industrial water supply |
| <input type="checkbox"/> Park activities | <input type="checkbox"/> Other(s), specify: <u>Click to enter text.</u> |

C. Waterbody aesthetics

Check one of the following that best describes the aesthetics of the receiving water and the surrounding area.

- ☐ Wilderness: outstanding natural beauty; usually wooded or unpastured area; water clarity exceptional
- ☐ Natural Area: trees and/or native vegetation; some development evident (from fields, pastures, dwellings); water clarity discolored
- ☐ Common Setting: not offensive; developed but uncluttered; water may be colored or turbid
- ☐ Offensive: stream does not enhance aesthetics; cluttered; highly developed; dumping areas; water discolored



8/11 USER: Jkoniar - ATTACHED IMAGES - CAPTION: WINDWOOD DR, STAR DUST DR, MOONBEAM LN, DEER TRL, PARKER DR, PANTHER LN, TERRELL RD, FM 35, WEST TEMPE CREEK, TEXAS LANDING WWTF, LIVINGSTON MUNICIPAL AIRPORT, QUADRANGLE LOCATION, POLK COUNTY, TEXAS. DRAWING NAME: C:\Central States Water Resources\Texas Landing WWTF\503581.0011.0003.0001-01.dwg — PLOT DATE: September 05, 2024 — 3:18PM — LAYOUT: FIGURE 1




SOURCE NOTE: USGS 7.5 MINUTE US TOPO SERIES TOPOGRAPHIC MAP, BLANDCHARD, 2022.



QUADRANGLE LOCATION
POLK COUNTY, TEXAS



0 1,000 2,000
SCALE IN FEET
1" = 2,000'

PROJECT: CENTRAL STATES WATER RESOURCES TEXAS LANDING WWTF TERMINUS OF BRANDING IRON LIVINGSTON, TEXAS 77351	
TITLE: SUBJECT PROPERTY LOCATION MAP	
DRAWN BY: J. KONIAR	PROJ NO.: 503581.0011.0003
CHECKED BY: A. SCHULZ	FIGURE 1
APPROVED BY: A. SCHULZ	
DATE: SEPTEMBER 2024	
	
1000 Clark Ave. FL 4 St. Louis, MO 63102 Phone: 314.241.2694	
FILE NO.:	503581.0011.0003.0001-01.dwg

September 9, 2024

TRINITY RIVER AUTHORITY
Lake Livingston Laboratory
Wastewater Analysis Report
Document ID: TX-C24-00194

page 1 of 3

Report # 45544TL

Texas Landing

Aggregate Water Services
P.O. Box 9923, Spring, TX 77387

August 2024 - Effluent Analysis

Sample ID	Sample Date	Collected By	Flow MGD	BOD ⁽¹⁾ mg/L	BOD ⁽¹⁾ lb/day	Analyst	Analysis Date&Time	LC Std % Rec	RPD	TSS ⁽²⁾ mg/L	TSS ⁽²⁾ lb/day	Analyst	Analysis Date&Time	RPD
080624022	8/6/24	NS	0.059661	< 2	0.9951	DF	8/7 13:40	106	6.90	4	1.9903	SP	8/8 14:13	2.39
081324028	8/13/24	NS	0.068185	< 2	1.1373	SP	8/14 10:00	88	12.50	4	2.2747	DF	8/15 13:20	0.93
082024025	8/20/24	NS	0.000262	< 2	0.0044	DF	8/21 11:55	102	6.90	2	0.0044	SP	8/22 9:55	1.71
082724021	8/27/24	NS	0.044601	< 2	0.7439	SP	8/28 10:24	97	8.00	3	1.1159	SP	8/29 9:30	1.47
Averages:				2	0.7202					3	1.3463			

Comments:

 9/11/24
Mike Knight Date

Water Quality Supervisor
Trinity River Authority - LLP
P. O. Box 360, 5170 South F.M. 1988
Livingston, Texas 77351
(936) 365-2292

(1) Standard Methods 5210 B

(2) Standard Methods 2540 D, 2540 E

(3) Standard Methods 4500-NH3 D

* All results conform with the TNV Standards unless otherwise stated elsewhere on this report. Data apply only to samples listed in this report.

* Photocopies of Field ID Forms are attached for reference.

Attachments numbering 2 pages are part of this report and contain information necessary for interpretation of this report.

September 9, 2024

Report # 45544 TL

TRINITY RIVER AUTHORITY
Lake Livingston Laboratory
Wastewater Analysis Report
Document ID: TX-C24-00194

page 3 of 3


Texas Landing

Aggregate Water Services
P.O. Box 9923, Spring, TX 77387

August 2024 - Effluent E. coli Analysis

Sample ID	Sample Date	Collected By	MPN ⁽¹⁾ per 100 mLs	Analyst	Analysis Date&Time	Range
082724030	8/27/2024	NS	2	SH	8/27 16:24	0.0000
Geometric Mean:			2			

Comments:


Mike Knight Date
Water Quality Supervisor
Trinity River Authority - LLP
P. O. Box 360, 5170 South F.M. 1988
Livingston, Texas 77351
(936) 365-2292

⁽¹⁾ Colilert® (IDEXX)

* All results conform with the TNI Standards unless otherwise stated elsewhere on this report. Data apply only to samples listed in this report.
* Photocopies of Field ID Forms are attached for reference.

Jon Niermann, *Chairman*
Emily Lindley, *Commissioner*
Bobby Janecka, *Commissioner*
Erin Chancellor, *Executive Director*



TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

Protecting Texas by Reducing and Preventing Pollution

December 14, 2023

Mr. Melwin Matthew, E.I.T.
LightPoint Engineering, LLC
604 W. Worsham, Suite 100
Willis, Texas 77378

Re: Approval of Proposed CSWR-Texas Utility Operating Company LLC - Texas
Landing Wastewater Treatment Plant (WWTP) TPDES Permit No. WQ0013147001
Closure Plan (CN605844786; RN102341294)

Dear Mr. Matthew:

The Texas Commission on Environmental Quality (TCEQ) staff has reviewed the closure plan dated July 6, 2023. Based on our review of the information provided, the plan for the Texas Landing WWTP is hereby approved. CSWR-Texas Utility Operating Company LLC or its representative shall notify the TCEQ Regional Inspector in writing at least 10 working days prior to completion of closure activities.

Also, a Registered Professional Engineer shall sign and submit a completion notice for review and approval to the TCEQ after completion of the closure activity. An original and one copy of the closure completion documents shall be submitted to the TCEQ's central office in Austin and one copy submitted to the TCEQ's regional office in Beaumont, Texas.

If you should have any further questions, please do not hesitate to call me at (512) 239-4668, or if by correspondence, please include MC-148 in the letterhead address following my name.

Sincerely,

JAM III

J. Alfonso Martinez III
Municipal Permits Team
Wastewater Permitting Section (MC 148)
Water Quality Division

From: Krisa.Obernuefemann@cswr.com
To: Krisa.Obernuefemann@cswr.com
Subject: TCEQ ePay Receipt for 582EA000627007
Date: Friday, September 27, 2024 7:43:58 AM

This is an automated message from the TCEQ ePay system. Please do not reply.
Trace Number: 582EA000627007
Date: 09/27/2024 07:43 AM
Payment Method: ACH - Authorization 0083605846
TCEQ Amount: \$515.00
Texas gov Price: \$515.00

* This service is provided by Texas.gov, the official website of Texas. The price of this service includes funds that support the ongoing operations and enhancements of Texas.gov, which is provided by a third party in partnership with the State.

Actor: KRISTA OBERNUEFEMANN
Email: krista@cswrgroup.com

Payment Contact: KRISTA OBERNUEFEMANN
Phone: 314-380-8515
Company: CSWR TEXAS UTILITY OPERATING CO
Address: 1630 DES PERES RD STE 140, ST LOUIS, MO 63131

Fees Paid:
Fee Description AR Number Amount
WW PERMIT - FACILITY WITH FLOW >= 05 & < 10 MGD - RENEWAL \$500.00
30 TAC 305 53B WQ RENEWAL NOTIFICATION FEE \$15.00

TCEQ Amount: \$515.00

Voucher: 723040
Trace Number: 582EA000627007
Date: 09/27/2024 07:43 AM
Payment Method: ACH - Authorization 0083605846
Voucher Amount: \$500.00
Fee Paid: WW PERMIT - FACILITY WITH FLOW >= 05 & < 10 MGD - RENEWAL
RN Number: RN102341294
Site Name: TEXAS LANDING WASTEWATER TREATMENT FACILITY
Site Address: 404 BRANDING IRON, FORT WORTH, TX 77351
Site Location: APPROX 1/2 MI N OF INTERSECTION OF FM 350 AND FM 3126 APPROX 5 MI W OF THE CITY
CN Number: CN605844786
Customer Name: CSWR-TEXAS UTILITY OPERATING COMPANY LLC
Customer Address: 1630 DES PERES RD STE 140, DES PERES, MO 63131
Program Area ID: 0013147001

Voucher: 723041
Trace Number: 582EA000627007
Date: 09/27/2024 07:43 AM
Payment Method: ACH - Authorization 0083605846
Voucher Amount: \$15.00
Fee Paid: 30 TAC 305 53B WQ RENEWAL NOTIFICATION FEE

Rainee Trevino

From: Mandy Sappington <msappington@cswrgroup.com>
Sent: Wednesday, October 23, 2024 12:48 PM
To: Erwin Madrid; Rainee Trevino
Cc: aschulz@trccompanies.com
Subject: Re: Application to Renew Permit No. WQ0013147001- Notice of Deficiency Letter
Attachments: 24.10.23 TX Landing TX0098809 NODI Response.pdf; 24.10.23 TX Landing TX0098809 Esp NORI.docx

Follow Up Flag: Follow up
Flag Status: Completed

Please find your additional information attached. Let me know if there is anything else I can provide.

Amanda Sappington

EHS Compliance Manager

(314) 464-3976

ADDRESS: 1630 Des Peres Rd., Ste. 140, Des Peres, MO 63131

www.centralstateswaterresources.com

From: Erwin Madrid <Erwin.Madrid@tceq.texas.gov>
Sent: Tuesday, October 22, 2024 10:53 AM
To: Mandy Sappington <msappington@cswrgroup.com>; Rainee Trevino <Rainee.Trevino@tceq.texas.gov>
Cc: aschulz@trccompanies.com <aschulz@trccompanies.com>
Subject: RE: Application to Renew Permit No. WQ0013147001- Notice of Deficiency Letter

Hi Mandy,

Thanks for letting us know, if you have any other questions/concerns, feel free to reach out to Rainee and/or myself.

Regards,

Erwin Madrid
Team Lead
ARP Team | Water Quality Division
512-239-2191
Texas Commission on Environmental Quality



Please consider whether it is necessary to print this e-mail.

From: Mandy Sappington <msappington@cswrgroup.com>
Sent: Tuesday, October 22, 2024 10:36 AM
To: Raine Trevino <Raine.Trevino@tceq.texas.gov>; Erwin Madrid <Erwin.Madrid@tceq.texas.gov>
Cc: aschulz@trccompanies.com
Subject: Re: Application to Renew Permit No. WQ0013147001- Notice of Deficiency Letter

Never mind. I found it!

Amanda Sappington
EHS Compliance Manager
(314) 464-3976
ADDRESS: 1630 Des Peres Rd., Ste. 140, Des Peres, MO 63131
www.centralstateswaterresources.com

From: Raine Trevino <Raine.Trevino@tceq.texas.gov>
Sent: Thursday, October 3, 2024 11:38 AM
To: Mandy Sappington <msappington@cswrgroup.com>
Cc: aschulz@trccompanies.com <aschulz@trccompanies.com>
Subject: Application to Renew Permit No. WQ0013147001- Notice of Deficiency Letter

Dear Ms. Sappington

The attached Notice of Deficiency letter sent on October 3, 2024, requests additional information needed to declare the application administratively complete. Please send the complete response to my attention by October 17, 2024.

Best Regards,

Raine Trevino
Water Quality Division | ARP Team
Texas Commission on Environmental Quality
512-239-4324



May 10, 2024

Rainee Trevino
Texas Commission Environmental Quality
Water Quality Division
Applications Review and Processing Team

Subject: Texas Landing WWTP WX0013147001 (TX0098809)
2024 Permit Renewal Application NODI

Submitted via email – rainee.trevino@tceq.texas.gov

Ms. Trevino -

In response to your October 3, 2024, letter requesting more information for our application CSWR-Texas provides the following responses.

1. Administrative Report 1.0, Section 2, Item E:

The application type indicates a minor amendment with renewal. Please describe the amendments or modifications.

The minor amendment intended was the Ownership Change which is not reflected in the current draft of the permit. No modifications are proposed for the plant at this time.

2. Administrative Report 1.0, Section 8, Item E:

The application indicates a bilingual education program is required by the Texas Education Code at the elementary or middle school nearest to the facility. Due to this, questions 2,3, and 4 are required as well.

CSWR typically publishes notices in the State of TX in Spanish out of an abundance of caution due to our lack of demographic information about the small communities we serve. We would assume that the answers to questions 2, 3 and 4 are yes and proceed with the notice in Spanish.

3. Supplemental Permit Information Form (SPIF), Item #2:

The county in which the facility is located is incorrect. Please provide the correct county.

The corrected SPIF is attached.

4. The following is a portion of the NORI which contains information relevant to your application. Please read it carefully and indicate if it contains any errors or omissions.
The complete notice

The information provided is correct.



5. The application indicates that public notices in Spanish are required. After confirming the portion of the NORI above does not contain any errors or omissions, please use the attached template to translate the NORI into Spanish. Only the first and last paragraphs are unique to this application and require translation. Please provide the translated Spanish NORI in a Microsoft Word document.

The Spanish NORI is attached in a Word document to the email transmitting this letter.

We appreciate Texas Commission on Environmental Quality's assistance with our permit renewals throughout the state. If you have any questions regarding this submittal, please reach out to me directly at 314-464-3976 or msappington@cswrgroup.com.

Sincerely,

EHS Compliance Manager
Central States Water Resources



ATTACHMENT 1

TEXAS COMMISSION ON ENVIRONMENTAL QUALITY

SUPPLEMENTAL PERMIT INFORMATION FORM (SPIF)

FOR AGENCIES REVIEWING DOMESTIC OR INDUSTRIAL TPDES WASTEWATER PERMIT APPLICATIONS

TCEQ USE ONLY:

Application type: ____Renewal ____Major Amendment ____Minor Amendment ____New

County: _____ Segment Number: _____

Admin Complete Date: _____

Agency Receiving SPIF:

____ Texas Historical Commission

____ U.S. Fish and Wildlife

____ Texas Parks and Wildlife Department

____ U.S. Army Corps of Engineers

This form applies to TPDES permit applications only. (Instructions, Page 53)

Complete this form as a separate document. TCEQ will mail a copy to each agency as required by our agreement with EPA. If any of the items are not completely addressed or further information is needed, we will contact you to provide the information before issuing the permit. Address each item completely.

Do not refer to your response to any item in the permit application form. Provide each attachment for this form separately from the Administrative Report of the application. The application will not be declared administratively complete without this SPIF form being completed in its entirety including all attachments. Questions or comments concerning this form may be directed to the Water Quality Division's Application Review and Processing Team by email at WQ-ARPTeam@tceq.texas.gov or by phone at (512) 239-4671.

The following applies to all applications:

1. Permittee: CSWR-Texas Utility Operating Company, LLC

Permit No. WQ00 13147001EPA ID No. TX 0098809

Address of the project (or a location description that includes street/highway, city/vicinity, and county):

404 Branding Iron, Livingston, Polk County, Texas, 77351

Provide the name, address, phone and fax number of an individual that can be contacted to answer specific questions about the property.

Prefix (Mr., Ms., Miss): [REDACTED]

First and Last Name: April Dobbins

Credential (P.E, P.G., Ph.D., etc.): [REDACTED]

Title: EHS Manager

Mailing Address: 1630 Des Peres Road, Ste. 140

City, State, Zip Code: Des Peres, Mo 63131

Phone No.: 314-380-9508 Ext.: [REDACTED] Fax No.: [REDACTED]

E-mail Address: adobbins@cswrgroup.com

2. List the county in which the facility is located: Polk
3. If the property is publicly owned and the owner is different than the permittee/applicant, please list the owner of the property.

N/A

4. Provide a description of the effluent discharge route. The discharge route must follow the flow of effluent from the point of discharge to the nearest major watercourse (from the point of discharge to a classified segment as defined in 30 TAC Chapter 307). If known, please identify the classified segment number.

Directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin

5. Please provide a separate 7.5-minute USGS quadrangle map with the project boundaries plotted and a general location map showing the project area. Please highlight the discharge route from the point of discharge for a distance of one mile downstream. (This map is required in addition to the map in the administrative report).

Provide original photographs of any structures 50 years or older on the property.

Does your project involve any of the following? Check all that apply.

- ☐ Proposed access roads, utility lines, construction easements
- ☐ Visual effects that could damage or detract from a historic property's integrity
- ☐ Vibration effects during construction or as a result of project design
- ☐ Additional phases of development that are planned for the future
- ☐ Sealing caves, fractures, sinkholes, other karst features

☐ Disturbance of vegetation or wetlands

1. List proposed construction impact (surface acres to be impacted, depth of excavation, sealing of caves, or other karst features):

none

2. Describe existing disturbances, vegetation, and land use:

None, existing WWTF

THE FOLLOWING ITEMS APPLY ONLY TO APPLICATIONS FOR NEW TPDES PERMITS AND MAJOR AMENDMENTS TO TPDES PERMITS

3. List construction dates of all buildings and structures on the property:

N/A

4. Provide a brief history of the property, and name of the architect/builder, if known.

N/A

From: [Mandy Sappington](#)
To: [Tyler Davis](#); aschulz@trccompanies.com
Subject: RE: Permit No. WQ0013147001 Comments/Approval Deadline
Date: Wednesday, July 9, 2025 11:05:22 AM

Everything looks good. Thanks for reminding me. I shared it with my group and no one had any comments. Please proceed.

Thank you
Mandy

Amanda Sappington
EHS Compliance Manager
(314) 464-3976

ADDRESS: 1630 Des Peres Rd., Ste. 140, Des Peres, MO 63131
www.centralstateswaterresources.com

From: Tyler Davis <Tyler.Davis@tceq.texas.gov>
Sent: Wednesday, July 9, 2025 10:28 AM
To: Mandy Sappington <msappington@cswrgroup.com>; aschulz@trccompanies.com
Subject: Permit No. WQ0013147001 Comments/Approval Deadline

Good morning,

This is a reminder that any comments or approval with the translated NAPD for Permit No. WQ0013147001 is due no later than the end of today. Please let me know if you have not received the permit package. If you have any questions about the permit or the permitting process, do not hesitate to contact me.

Sincerely,
Tyler Davis
Tyler.Davis@tceq.texas.gov
Municipal Wastewater Permitting Intern



Compliance History Report

Compliance History Report for CN605844786, RN102341294, Rating Year 2024 which includes Compliance History (CH) components from September 1, 2019, through August 31, 2024.

Customer, Respondent, or Owner/Operator:	CN605844786, CSWR-TEXAS UTILITY OPERATING COMPANY, LLC	Classification: SATISFACTORY	Rating: 3.16
Regulated Entity:	RN102341294, TEXAS LANDING PLANT	Classification: HIGH	Rating: 0.00
Complexity Points:	4	Repeat Violator:	NO
CH Group:	08 - Sewage Treatment Facilities		
Location:	404 BRANDING IRON LIVINGSTON, TX 77351-7572, POLK COUNTY		
TCEQ Region:	REGION 10 - BEAUMONT		
ID Number(s):			
WASTEWATER PERMIT WQ0013147001	WASTEWATER EPA ID TX0098809		
Compliance History Period:	September 01, 2019 to August 31, 2024	Rating Year: 2024	Rating Date: 09/01/2024
Date Compliance History Report Prepared:	November 04, 2024		
Agency Decision Requiring Compliance History:	Permit - Issuance, renewal, amendment, modification, denial, suspension, or revocation of a permit.		
Component Period Selected:	September 30, 2019 to November 04, 2024		
TCEQ Staff Member to Contact for Additional Information Regarding This Compliance History.			
Name: PT	Phone: (512) 239-3581		

Site and Owner/Operator History:

- | | |
|--|-----|
| 1) Has the site been in existence and/or operation for the full five year compliance period? | YES |
| 2) Has there been a (known) change in ownership/operator of the site during the compliance period? | NO |

Components (Multimedia) for the Site Are Listed in Sections A - J

A. Final Orders, court judgments, and consent decrees:

N/A

B. Criminal convictions:

N/A

C. Chronic excessive emissions events:

N/A

D. The approval dates of investigations (CCEDS Inv. Track. No.):

Item 1	October 21, 2019	(1614641)
Item 2	November 20, 2019	(1627782)
Item 3	December 02, 2019	(1620431)
Item 4	January 20, 2020	(1635410)
Item 5	February 19, 2020	(1642025)
Item 6	March 17, 2020	(1648540)
Item 7	April 20, 2020	(1654891)
Item 8	May 20, 2020	(1661455)
Item 9	June 18, 2020	(1667984)
Item 10	July 20, 2020	(1674931)
Item 11	September 21, 2020	(1681701)

Item 12	October 19, 2020	(1694636)
Item 13	November 19, 2020	(1716507)
Item 14	December 16, 2020	(1716508)
Item 15	January 19, 2021	(1716509)
Item 16	February 20, 2021	(1729589)
Item 17	March 17, 2021	(1729590)
Item 18	April 19, 2021	(1729591)
Item 19	May 18, 2021	(1742093)
Item 20	July 19, 2021	(1753045)
Item 21	August 17, 2021	(1758450)
Item 22	September 17, 2021	(1767736)
Item 23	October 20, 2021	(1778302)
Item 24	November 15, 2021	(1784972)
Item 25	December 20, 2021	(1792006)
Item 26	January 18, 2022	(1799857)
Item 27	February 14, 2022	(1807689)
Item 28	March 15, 2022	(1814731)
Item 29	April 19, 2022	(1821301)
Item 30	May 19, 2022	(1830138)
Item 31	July 20, 2022	(1843634)
Item 32	August 29, 2022	(1849796)
Item 33	September 20, 2022	(1857565)
Item 34	October 20, 2022	(1863919)
Item 35	November 20, 2022	(1870828)
Item 36	January 04, 2023	(1876684)
Item 37	February 20, 2023	(1883494)
Item 38	April 20, 2023	(1899880)
Item 39	July 18, 2023	(1920444)
Item 40	August 20, 2023	(1934370)
Item 41	September 20, 2023	(1940547)
Item 42	October 20, 2023	(1947350)
Item 43	November 20, 2023	(1953037)
Item 44	December 20, 2023	(1962815)
Item 45	January 21, 2024	(1969398)
Item 46	April 29, 2024	(1991559)
Item 47	May 20, 2024	(1998015)
Item 48	June 20, 2024	(2004981)
Item 49	July 22, 2024	(2012545)
Item 50	September 04, 2024	(2018113)

E. Written notices of violations (NOV) (CCEDS Inv. Track. No.):

A notice of violation represents a written allegation of a violation of a specific regulatory requirement from the commission to a regulated entity. A notice of violation is not a final enforcement action, nor proof that a violation has actually occurred.

1	Date: 01/31/2024 (1978463)		
	Self Report? YES	Classification:	Moderate
	Citation: 2D TWC Chapter 26, SubChapter A 26.121(a) 30 TAC Chapter 305, SubChapter F 305.125(1)		
	Description: Failure to meet the limit for one or more permit parameter		
2	Date: 02/29/2024 (1985036)		
	Self Report? YES	Classification:	Moderate
	Citation: 2D TWC Chapter 26, SubChapter A 26.121(a) 30 TAC Chapter 305, SubChapter F 305.125(1)		
	Description: Failure to meet the limit for one or more permit parameter		

F. Environmental audits:

Notice of Intent Date: 07/29/2022 (1834722)

Disclosure Date: 07/29/2022

Viol. Moderate

Compliance History Report for CN605844786, RN102341294, Rating Year 2024 which includes Compliance History (CH) components from September 30, 2019, through November 04, 2024. Ratings are pending Mass Classification.

Viol.
Citation: 30 TAC Chapter 217, SubChapter F 217.161(d)
30 TAC Chapter 217, SubChapter M 217.326(a)
30 TAC Chapter 217, SubChapter C 217.60(a)
30 TAC Chapter 217, SubChapter C 217.63(c)

Description: Failed to include an audiovisual alarm in the electrical panels at the lift station.
Viol. Moderate

Classification:
Citation: 30 TAC Chapter 217, SubChapter C 217.60(f)
30 TAC Chapter 217, SubChapter C 217.61(b)

Description: Failed to secure the Lift Station No. 1 pump inside the housing and install hoisting equipment.
Viol. Moderate

Classification:
Citation: 30 TAC Chapter 217, SubChapter B 217.33(c)

Description: Failed to install primary and secondary flow meters.
Viol. Minor

Classification:
Citation: 30 TAC Chapter 217, SubChapter A 217.16(a)
30 TAC Chapter 217, SubChapter A 217.16(b)

Description: Failed to maintain an up-to-date O&M manual.
Viol. Minor

Classification:
Citation: 30 TAC Chapter 217, SubChapter A 217.3(a)
30 TAC Chapter 217, SubChapter A 217.3(b)
30 TAC Chapter 305, SubChapter F 305.125(5)

Description: Failed to maintain facilities including grub and tree removal from the fence.

G. Type of environmental management systems (EMSs):

N/A

H. Voluntary on-site compliance assessment dates:

N/A

I. Participation in a voluntary pollution reduction program:

N/A

J. Early compliance:

N/A

Sites Outside of Texas:

N/A

DMR DATA

WQ0013147001 - CSWR-TEXAS UTILITY OPERATING COMPANY LLC

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				DAILY AV (mg/L)	SINGGRAB (mg/L)	DAILY AV (lb/d)
TX0098809	8/31/2019	001A	BOD, 5-day, 20 deg. C	3	4	0.15
TX0098809	9/30/2019	001A	BOD, 5-day, 20 deg. C	3	4	0.12
TX0098809	10/31/2019	001A	BOD, 5-day, 20 deg. C	3	4	0.10
TX0098809	11/30/2019	001A	BOD, 5-day, 20 deg. C	3	3	0.58
TX0098809	12/31/2019	001A	BOD, 5-day, 20 deg. C	2	4	0.27
TX0098809	1/31/2020	001A	BOD, 5-day, 20 deg. C	3	3	0.13
TX0098809	2/29/2020	001A	BOD, 5-day, 20 deg. C	3	3	0.04
TX0098809	3/31/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.13
TX0098809	4/30/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.25
TX0098809	5/31/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.11
TX0098809	6/30/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.16
TX0098809	7/31/2020	001A	BOD, 5-day, 20 deg. C	3	3	0.29
TX0098809	8/31/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.12
TX0098809	9/30/2020	001A	BOD, 5-day, 20 deg. C	4	8	0.15
TX0098809	10/31/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.11
TX0098809	11/30/2020	001A	BOD, 5-day, 20 deg. C	3	4	0.24
TX0098809	12/31/2020	001A	BOD, 5-day, 20 deg. C	3	5	0.22
TX0098809	1/31/2021	001A	BOD, 5-day, 20 deg. C	3	4	0.08
TX0098809	2/28/2021	001A	BOD, 5-day, 20 deg. C	4	5	0.67
TX0098809	3/31/2021	001A	BOD, 5-day, 20 deg. C	3	5	0.24
TX0098809	4/30/2021	001A	BOD, 5-day, 20 deg. C	3	4	0.04
TX0098809	5/31/2021	001A	BOD, 5-day, 20 deg. C	3	3	0.09
TX0098809	6/30/2021	001A	BOD, 5-day, 20 deg. C	4	6	0.02
TX0098809	7/31/2021	001A	BOD, 5-day, 20 deg. C	2	3	0.01
TX0098809	8/31/2021	001A	BOD, 5-day, 20 deg. C	2	3	0.09
TX0098809	9/30/2021	001A	BOD, 5-day, 20 deg. C	3	6	0.08
TX0098809	10/31/2021	001A	BOD, 5-day, 20 deg. C	3	4	0.54
TX0098809	11/30/2021	001A	BOD, 5-day, 20 deg. C	3	4	0.08
TX0098809	12/31/2021	001A	BOD, 5-day, 20 deg. C	4	7	0.10

TX0098809	1/31/2022	001A	BOD, 5-day, 20 deg. C	3	5	0.21
TX0098809	2/28/2022	001A	BOD, 5-day, 20 deg. C	3	4	0.04
TX0098809	3/31/2022	001A	BOD, 5-day, 20 deg. C	3	4	0.05
TX0098809	4/30/2022	001A	BOD, 5-day, 20 deg. C	3	3	0.19
TX0098809	5/31/2022	001A	BOD, 5-day, 20 deg. C	2	2	0.04
TX0098809	6/30/2022	001A	BOD, 5-day, 20 deg. C	2	2	0.04
TX0098809	7/31/2022	001A	BOD, 5-day, 20 deg. C	2	3	0.29
TX0098809	8/31/2022	001A	BOD, 5-day, 20 deg. C	2.33	3.3	1.98
TX0098809	9/30/2022	001A	BOD, 5-day, 20 deg. C	2	2	0.02
TX0098809	10/31/2022	001A	BOD, 5-day, 20 deg. C	2	2	0.10
TX0098809	11/30/2022	001A	BOD, 5-day, 20 deg. C	2	2	0.03
TX0098809	12/31/2022	001A	BOD, 5-day, 20 deg. C	8	24	2.45
TX0098809	1/31/2023	001A	BOD, 5-day, 20 deg. C	3	7	0.30
TX0098809	2/28/2023	001A	BOD, 5-day, 20 deg. C	2	2	0.22
TX0098809	3/31/2023	001A	BOD, 5-day, 20 deg. C	2	2	0.01
TX0098809	4/30/2023	001A	BOD, 5-day, 20 deg. C	2	2	0.00
TX0098809	5/31/2023	001A	BOD, 5-day, 20 deg. C	3	6	0.25
TX0098809	6/30/2023	001A	BOD, 5-day, 20 deg. C	3	4	0.44
TX0098809	7/31/2023	001A	BOD, 5-day, 20 deg. C	2.25	3	0.73
TX0098809	8/31/2023	001A	BOD, 5-day, 20 deg. C	2	3	0.04
TX0098809	9/30/2023	001A	BOD, 5-day, 20 deg. C	3	4	0.39
TX0098809	10/31/2023	001A	BOD, 5-day, 20 deg. C	4	6	0.55
TX0098809	11/30/2023	001A	BOD, 5-day, 20 deg. C	2	3	0.04
TX0098809	12/31/2023	001A	BOD, 5-day, 20 deg. C	4	10	0.26
TX0098809	1/31/2024	001A	BOD, 5-day, 20 deg. C	4.33	6	2.15
TX0098809	2/29/2024	001A	BOD, 5-day, 20 deg. C	2	2	0.33
TX0098809	3/31/2024	001A	BOD, 5-day, 20 deg. C	2	2	0.21
TX0098809	4/30/2024	001A	BOD, 5-day, 20 deg. C	5	10	1.02
TX0098809	5/31/2024	001A	BOD, 5-day, 20 deg. C	5.75	10	0.00
TX0098809	6/30/2024	001A	BOD, 5-day, 20 deg. C	<2	2	0.05
TX0098809	7/31/2024	001A	BOD, 5-day, 20 deg. C	3	5	0.02
TX0098809	8/31/2024	001A	BOD, 5-day, 20 deg. C	2	2	0.71
TX0098809	9/30/2024	001A	BOD, 5-day, 20 deg. C	2	2	0.02
2 YEAR AVERAGE				2.97	4.92	0.41
5 YEAR AVERAGE				2.95	4.39	0.30

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				MO MIN (mg/L)	MO MAX (mg/L)
TX0098809	8/31/2019	001A	Chlorine, total residual	1.28	3.99
TX0098809	9/30/2019	001A	Chlorine, total residual	1.04	4

TX0098809	10/31/2019	001A	Chlorine, total residual	1.02	3.93
TX0098809	11/30/2019	001A	Chlorine, total residual	1.02	2.62
TX0098809	12/31/2019	001A	Chlorine, total residual	1.03	2.38
TX0098809	1/31/2020	001A	Chlorine, total residual	1.02	2.62
TX0098809	2/29/2020	001A	Chlorine, total residual	1.04	1.7
TX0098809	3/31/2020	001A	Chlorine, total residual	1.02	2.57
TX0098809	4/30/2020	001A	Chlorine, total residual	1.01	3.68
TX0098809	5/31/2020	001A	Chlorine, total residual	1	3.67
TX0098809	6/30/2020	001A	Chlorine, total residual	1.01	2.76
TX0098809	7/31/2020	001A	Chlorine, total residual	1.02	3.97
TX0098809	8/31/2020	001A	Chlorine, total residual	1.01	3.95
TX0098809	9/30/2020	001A	Chlorine, total residual	1.05	3.93
TX0098809	10/31/2020	001A	Chlorine, total residual	1.1	3.88
TX0098809	11/30/2020	001A	Chlorine, total residual	1.02	3.92
TX0098809	12/31/2020	001A	Chlorine, total residual	1.03	3.9
TX0098809	1/31/2021	001A	Chlorine, total residual	1.07	3.88
TX0098809	2/28/2021	001A	Chlorine, total residual	1.02	3.95
TX0098809	3/31/2021	001A	Chlorine, total residual	1.04	3.98
TX0098809	4/30/2021	001A	Chlorine, total residual	1.03	3.98
TX0098809	5/31/2021	001A	Chlorine, total residual	1.03	3.98
TX0098809	6/30/2021	001A	Chlorine, total residual	1.01	3.96
TX0098809	7/31/2021	001A	Chlorine, total residual	1	3.98
TX0098809	8/31/2021	001A	Chlorine, total residual	1.01	3.99
TX0098809	9/30/2021	001A	Chlorine, total residual	1.01	3.97
TX0098809	10/31/2021	001A	Chlorine, total residual	1.03	3.95
TX0098809	11/30/2021	001A	Chlorine, total residual	1.01	3.92
TX0098809	12/31/2021	001A	Chlorine, total residual	1.04	3.93
TX0098809	1/31/2022	001A	Chlorine, total residual	1.01	4
TX0098809	2/28/2022	001A	Chlorine, total residual	1.07	4
TX0098809	3/31/2022	001A	Chlorine, total residual	1.06	3.88
TX0098809	4/30/2022	001A	Chlorine, total residual	1.03	3.99
TX0098809	5/31/2022	001A	Chlorine, total residual	1.04	3.95
TX0098809	6/30/2022	001A	Chlorine, total residual	1.02	3.95
TX0098809	7/31/2022	001A	Chlorine, total residual	1.05	3.76
TX0098809	8/31/2022	001A	Chlorine, total residual	1.01	3.76
TX0098809	9/30/2022	001A	Chlorine, total residual	1.22	3.75
TX0098809	10/31/2022	001A	Chlorine, total residual	2.58	3.82
TX0098809	11/30/2022	001A	Chlorine, total residual	1.82	3.73
TX0098809	12/31/2022	001A	Chlorine, total residual	1.11	3.85
TX0098809	1/31/2023	001A	Chlorine, total residual	1.07	2.45
TX0098809	2/28/2023	001A	Chlorine, total residual	1.35	3.6

TX0098809	3/31/2023	001A	Chlorine, total residual	1.48	2.4
TX0098809	4/30/2023	001A	Chlorine, total residual	1.17	1.83
TX0098809	5/31/2023	001A	Chlorine, total residual	1.03	3.85
TX0098809	6/30/2023	001A	Chlorine, total residual	1.01	3.75
TX0098809	7/31/2023	001A	Chlorine, total residual	1.14	3.96
TX0098809	8/31/2023	001A	Chlorine, total residual	1.02	3.78
TX0098809	9/30/2023	001A	Chlorine, total residual	1.45	3.95
TX0098809	10/31/2023	001A	Chlorine, total residual	1.19	3.85
TX0098809	11/30/2023	001A	Chlorine, total residual	1.44	3.88
TX0098809	12/31/2023	001A	Chlorine, total residual	1.22	2.45
TX0098809	1/31/2024	001A	Chlorine, total residual	1.18	3.96
TX0098809	2/29/2024	001A	Chlorine, total residual	1.25	3.4
TX0098809	3/31/2024	001A	Chlorine, total residual	1.07	3.73
TX0098809	4/30/2024	001A	Chlorine, total residual	1.06	3.05
TX0098809	5/31/2024	001A	Chlorine, total residual	1.51	3.64
TX0098809	6/30/2024	001A	Chlorine, total residual	1.76	2.6
TX0098809	7/31/2024	001A	Chlorine, total residual	1.2	3.2
TX0098809	8/31/2024	001A	Chlorine, total residual	1.19	3.69
TX0098809	9/30/2024	001A	Chlorine, total residual	1.98	2.19

2 YEAR AVERAGE

1.34

3.37

5 YEAR AVERAGE

1.16

3.56

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				DAILY AV (MGD)	DAILY MX (MGD)
TX0098809	8/31/2019	001A	Flow, in conduit or thru treatment plant	0.0047	0.014
TX0098809	9/30/2019	001A	Flow, in conduit or thru treatment plant	0.0072	0.022
TX0098809	10/31/2019	001A	Flow, in conduit or thru treatment plant	0.0061	0.032
TX0098809	11/30/2019	001A	Flow, in conduit or thru treatment plant	0.0079	0.774
TX0098809	12/31/2019	001A	Flow, in conduit or thru treatment plant	0.0065	0.045
TX0098809	1/31/2020	001A	Flow, in conduit or thru treatment plant	0.0053	0.018
TX0098809	2/29/2020	001A	Flow, in conduit or thru treatment plant	0.0087	0.060
TX0098809	3/31/2020	001A	Flow, in conduit or thru treatment plant	0.0068	0.052
TX0098809	4/30/2020	001A	Flow, in conduit or thru treatment plant	0.0056	0.027
TX0098809	5/31/2020	001A	Flow, in conduit or thru treatment plant	0.0043	0.014
TX0098809	6/30/2020	001A	Flow, in conduit or thru treatment plant	0.0077	0.774
TX0098809	7/31/2020	001A	Flow, in conduit or thru treatment plant	0.0074	0.032
TX0098809	8/31/2020	001A	Flow, in conduit or thru treatment plant	0.0072	0.032
TX0098809	9/30/2020	001A	Flow, in conduit or thru treatment plant	0.0090	0.045
TX0098809	10/31/2020	001A	Flow, in conduit or thru treatment plant	0.0053	0.014
TX0098809	11/30/2020	001A	Flow, in conduit or thru treatment plant	0.0080	0.038

TX0098809	12/31/2020	001A	Flow, in conduit or thru treatment plant	0.0075	0.032
TX0098809	1/31/2021	001A	Flow, in conduit or thru treatment plant	0.0080	0.038
TX0098809	2/28/2021	001A	Flow, in conduit or thru treatment plant	0.0140	0.077
TX0098809	3/31/2021	001A	Flow, in conduit or thru treatment plant	0.0048	0.045
TX0098809	4/30/2021	001A	Flow, in conduit or thru treatment plant	0.0019	0.006
TX0098809	5/31/2021	001A	Flow, in conduit or thru treatment plant	0.0190	0.077
TX0098809	6/30/2021	001A	Flow, in conduit or thru treatment plant	0.0055	0.045
TX0098809	7/31/2021	001A	Flow, in conduit or thru treatment plant	0.0048	0.022
TX0098809	8/31/2021	001A	Flow, in conduit or thru treatment plant	0.0030	0.022
TX0098809	9/30/2021	001A	Flow, in conduit or thru treatment plant	0.0032	0.022
TX0098809	10/31/2021	001A	Flow, in conduit or thru treatment plant	0.0137	0.077
TX0098809	11/30/2021	001A	Flow, in conduit or thru treatment plant	0.0038	0.022
TX0098809	12/31/2021	001A	Flow, in conduit or thru treatment plant	0.0067	0.052
TX0098809	1/31/2022	001A	Flow, in conduit or thru treatment plant	0.0032	0.032
TX0098809	2/28/2022	001A	Flow, in conduit or thru treatment plant	0.0092	0.077
TX0098809	3/31/2022	001A	Flow, in conduit or thru treatment plant	0.0111	0.077
TX0098809	4/30/2022	001A	Flow, in conduit or thru treatment plant	0.0144	0.077
TX0098809	5/31/2022	001A	Flow, in conduit or thru treatment plant	0.0032	0.045
TX0098809	6/30/2022	001A	Flow, in conduit or thru treatment plant	0.0034	0.022
TX0098809	7/31/2022	001A	Flow, in conduit or thru treatment plant	0.0089	0.016
TX0098809	8/31/2022	001A	Flow, in conduit or thru treatment plant	0.0107	0.017
TX0098809	9/30/2022	001A	Flow, in conduit or thru treatment plant	0.0098	0.002
TX0098809	10/31/2022	001A	Flow, in conduit or thru treatment plant	0.0105	0.017
TX0098809	11/30/2022	001A	Flow, in conduit or thru treatment plant	0.0172	0.043
TX0098809	12/31/2022	001A	Flow, in conduit or thru treatment plant	0.0220	0.047
TX0098809	1/31/2023	001A	Flow, in conduit or thru treatment plant	0.0230	0.047
TX0098809	2/28/2023	001A	Flow, in conduit or thru treatment plant	0.0166	0.068
TX0098809	3/31/2023	001A	Flow, in conduit or thru treatment plant	0.0098	0.013
TX0098809	4/30/2023	001A	Flow, in conduit or thru treatment plant	0.0185	0.073
TX0098809	5/31/2023	001A	Flow, in conduit or thru treatment plant	0.0157	0.035
TX0098809	6/30/2023	001A	Flow, in conduit or thru treatment plant	0.0111	0.048
TX0098809	7/31/2023	001A	Flow, in conduit or thru treatment plant	0.0103	0.016
TX0098809	8/31/2023	001A	Flow, in conduit or thru treatment plant	0.0099	0.016
TX0098809	9/30/2023	001A	Flow, in conduit or thru treatment plant	0.0095	0.001
TX0098809	10/31/2023	001A	Flow, in conduit or thru treatment plant	0.0131	0.042
TX0098809	11/30/2023	001A	Flow, in conduit or thru treatment plant	0.0151	0.068
TX0098809	12/31/2023	001A	Flow, in conduit or thru treatment plant	0.0170	0.022
TX0098809	1/31/2024	001A	Flow, in conduit or thru treatment plant	0.0680	0.297
TX0098809	2/29/2024	001A	Flow, in conduit or thru treatment plant	0.0150	0.061
TX0098809	3/31/2024	001A	Flow, in conduit or thru treatment plant	0.0159	0.116
TX0098809	4/30/2024	001A	Flow, in conduit or thru treatment plant	0.0220	0.067

TX0098809	5/31/2024	001A	Flow, in conduit or thru treatment plant	0	0
TX0098809	6/30/2024	001A	Flow, in conduit or thru treatment plant	0.0030	0.015
TX0098809	7/31/2024	001A	Flow, in conduit or thru treatment plant	0.0160	0.890
TX0098809	8/31/2024	001A	Flow, in conduit or thru treatment plant	0.0444	0.074
TX0098809	9/30/2024	001A	Flow, in conduit or thru treatment plant	0.0290	0.036
2 YEAR AVERAGE				0.018	0.085
5 YEAR AVERAGE				0.011	0.081

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MO MIN (mg/L)
TX0098809	8/31/2019	001A	Oxygen, dissolved [DO]	7.31
TX0098809	9/30/2019	001A	Oxygen, dissolved [DO]	6.11
TX0098809	10/31/2019	001A	Oxygen, dissolved [DO]	7.13
TX0098809	11/30/2019	001A	Oxygen, dissolved [DO]	7.88
TX0098809	12/31/2019	001A	Oxygen, dissolved [DO]	7.64
TX0098809	1/31/2020	001A	Oxygen, dissolved [DO]	5.28
TX0098809	2/29/2020	001A	Oxygen, dissolved [DO]	6.4
TX0098809	3/31/2020	001A	Oxygen, dissolved [DO]	7.17
TX0098809	4/30/2020	001A	Oxygen, dissolved [DO]	6.96
TX0098809	5/31/2020	001A	Oxygen, dissolved [DO]	5.3
TX0098809	6/30/2020	001A	Oxygen, dissolved [DO]	4.64
TX0098809	7/31/2020	001A	Oxygen, dissolved [DO]	7.15
TX0098809	8/31/2020	001A	Oxygen, dissolved [DO]	6.84
TX0098809	9/30/2020	001A	Oxygen, dissolved [DO]	6
TX0098809	10/31/2020	001A	Oxygen, dissolved [DO]	7.3
TX0098809	11/30/2020	001A	Oxygen, dissolved [DO]	6.74
TX0098809	12/31/2020	001A	Oxygen, dissolved [DO]	6.38
TX0098809	1/31/2021	001A	Oxygen, dissolved [DO]	8.28
TX0098809	2/28/2021	001A	Oxygen, dissolved [DO]	5.95
TX0098809	3/31/2021	001A	Oxygen, dissolved [DO]	4.04
TX0098809	4/30/2021	001A	Oxygen, dissolved [DO]	6.18
TX0098809	5/31/2021	001A	Oxygen, dissolved [DO]	4.88
TX0098809	6/30/2021	001A	Oxygen, dissolved [DO]	4.49
TX0098809	7/31/2021	001A	Oxygen, dissolved [DO]	6.24
TX0098809	8/31/2021	001A	Oxygen, dissolved [DO]	4.88
TX0098809	9/30/2021	001A	Oxygen, dissolved [DO]	5.93
TX0098809	10/31/2021	001A	Oxygen, dissolved [DO]	6.2
TX0098809	11/30/2021	001A	Oxygen, dissolved [DO]	6.95
TX0098809	12/31/2021	001A	Oxygen, dissolved [DO]	7.06
TX0098809	1/31/2022	001A	Oxygen, dissolved [DO]	7.82

TX0098809	2/28/2022	001A	Oxygen, dissolved [DO]	7.94
TX0098809	3/31/2022	001A	Oxygen, dissolved [DO]	6.79
TX0098809	4/30/2022	001A	Oxygen, dissolved [DO]	7.16
TX0098809	5/31/2022	001A	Oxygen, dissolved [DO]	7.05
TX0098809	6/30/2022	001A	Oxygen, dissolved [DO]	6.93
TX0098809	7/31/2022	001A	Oxygen, dissolved [DO]	6.08
TX0098809	8/31/2022	001A	Oxygen, dissolved [DO]	6.3
TX0098809	9/30/2022	001A	Oxygen, dissolved [DO]	6.91
TX0098809	10/31/2022	001A	Oxygen, dissolved [DO]	5.84
TX0098809	11/30/2022	001A	Oxygen, dissolved [DO]	5.63
TX0098809	12/31/2022	001A	Oxygen, dissolved [DO]	6.22
TX0098809	1/31/2023	001A	Oxygen, dissolved [DO]	5.48
TX0098809	2/28/2023	001A	Oxygen, dissolved [DO]	5.89
TX0098809	3/31/2023	001A	Oxygen, dissolved [DO]	5.06
TX0098809	4/30/2023	001A	Oxygen, dissolved [DO]	6.63
TX0098809	5/31/2023	001A	Oxygen, dissolved [DO]	5.17
TX0098809	6/30/2023	001A	Oxygen, dissolved [DO]	5.68
TX0098809	7/31/2023	001A	Oxygen, dissolved [DO]	6.16
TX0098809	8/31/2023	001A	Oxygen, dissolved [DO]	6.1
TX0098809	9/30/2023	001A	Oxygen, dissolved [DO]	4.11
TX0098809	10/31/2023	001A	Oxygen, dissolved [DO]	5.33
TX0098809	11/30/2023	001A	Oxygen, dissolved [DO]	6.4
TX0098809	12/31/2023	001A	Oxygen, dissolved [DO]	6.8
TX0098809	1/31/2024	001A	Oxygen, dissolved [DO]	4.3
TX0098809	2/29/2024	001A	Oxygen, dissolved [DO]	4.9
TX0098809	3/31/2024	001A	Oxygen, dissolved [DO]	7.61
TX0098809	4/30/2024	001A	Oxygen, dissolved [DO]	4.45
TX0098809	5/31/2024	001A	Oxygen, dissolved [DO]	5.58
TX0098809	6/30/2024	001A	Oxygen, dissolved [DO]	4.78
TX0098809	7/31/2024	001A	Oxygen, dissolved [DO]	4.81
TX0098809	8/31/2024	001A	Oxygen, dissolved [DO]	6.62
TX0098809	9/30/2024	001A	Oxygen, dissolved [DO]	6.29
2 YEAR AVERAGE				5.71
5 YEAR AVERAGE				6.16

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				MINIMUM (SU)	MAXIMUM (SU)
TX0098809	8/31/2019	001A	pH	7.71	7.9
TX0098809	9/30/2019	001A	pH	7.32	7.47
TX0098809	10/31/2019	001A	pH	7.11	7.97

TX0098809	11/30/2019	001A	pH	7.5	7.5
TX0098809	12/31/2019	001A	pH	7.87	7.87
TX0098809	1/31/2020	001A	pH	6.46	6.46
TX0098809	2/29/2020	001A	pH	7.12	7.18
TX0098809	3/31/2020	001A	pH	7.4	7.4
TX0098809	4/30/2020	001A	pH	7.61	7.61
TX0098809	5/31/2020	001A	pH	7.27	7.27
TX0098809	6/30/2020	001A	pH	7.54	7.54
TX0098809	7/31/2020	001A	pH	7.56	7.56
TX0098809	8/31/2020	001A	pH	7.59	7.82
TX0098809	9/30/2020	001A	pH	7.74	7.74
TX0098809	10/31/2020	001A	pH	7.72	7.72
TX0098809	11/30/2020	001A	pH	7.66	7.66
TX0098809	12/31/2020	001A	pH	6.95	7.33
TX0098809	1/31/2021	001A	pH	7.31	7.33
TX0098809	2/28/2021	001A	pH	6.27	7.09
TX0098809	3/31/2021	001A	pH	6.66	7.05
TX0098809	4/30/2021	001A	pH	7.75	7.75
TX0098809	5/31/2021	001A	pH	6.42	6.42
TX0098809	6/30/2021	001A	pH	6.77	6.77
TX0098809	7/31/2021	001A	pH	7.46	7.46
TX0098809	8/31/2021	001A	pH	7.6	7.6
TX0098809	9/30/2021	001A	pH	7.48	7.48
TX0098809	10/31/2021	001A	pH	7.19	7.86
TX0098809	11/30/2021	001A	pH	7.81	7.81
TX0098809	12/31/2021	001A	pH	7.72	7.72
TX0098809	1/31/2022	001A	pH	7.76	7.76
TX0098809	2/28/2022	001A	pH	7.62	7.62
TX0098809	3/31/2022	001A	pH	7.39	7.39
TX0098809	4/30/2022	001A	pH	7.5	7.5
TX0098809	5/31/2022	001A	pH	7.87	7.87
TX0098809	6/30/2022	001A	pH	7.72	7.72
TX0098809	7/31/2022	001A	pH	7.85	7.85
TX0098809	8/31/2022	001A	pH	7.2	7.2
TX0098809	9/30/2022	001A	pH	7.91	7.91
TX0098809	10/31/2022	001A	pH	7.74	7.74
TX0098809	11/30/2022	001A	pH	7.39	7.39
TX0098809	12/31/2022	001A	pH	7.91	7.91
TX0098809	1/31/2023	001A	pH	7.43	7.43
TX0098809	2/28/2023	001A	pH	7.52	7.58
TX0098809	3/31/2023	001A	pH	7.52	7.62

TX0098809	4/30/2023	001A	pH	6.91	7.71
TX0098809	5/31/2023	001A	pH	7.28	7.91
TX0098809	6/30/2023	001A	pH	7.77	7.96
TX0098809	7/31/2023	001A	pH	7.57	7.59
TX0098809	8/31/2023	001A	pH	7.59	7.9
TX0098809	9/30/2023	001A	pH	7.46	7.62
TX0098809	10/31/2023	001A	pH	7.64	7.68
TX0098809	11/30/2023	001A	pH	7.92	7.82
TX0098809	12/31/2023	001A	pH	7.25	7.51
TX0098809	1/31/2024	001A	pH	6.6	7.49
TX0098809	2/29/2024	001A	pH	6.61	7.09
TX0098809	3/31/2024	001A	pH	7.29	7.78
TX0098809	4/30/2024	001A	pH	6.94	7.67
TX0098809	5/31/2024	001A	pH	6.91	7.67
TX0098809	6/30/2024	001A	pH	7.29	7.85
TX0098809	7/31/2024	001A	pH	7.59	7.59
TX0098809	8/31/2024	001A	pH	7.82	8.19
TX0098809	9/30/2024	001A	pH	7.79	8.13
2 YEAR AVERAGE				7.43	7.71
5 YEAR AVERAGE				7.41	7.58

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				DAILY AV (mg/L)	SINGGRAB (mg/L)	DAILY AV (lb/d)
TX0098809	8/31/2019	001A	Solids, total suspended	2	2	0.12
TX0098809	9/30/2019	001A	Solids, total suspended	2	3	0.11
TX0098809	10/31/2019	001A	Solids, total suspended	3	4	0.13
TX0098809	11/30/2019	001A	Solids, total suspended	6	7	1.33
TX0098809	12/31/2019	001A	Solids, total suspended	4	6	0.59
TX0098809	1/31/2020	001A	Solids, total suspended	3	6	0.20
TX0098809	2/29/2020	001A	Solids, total suspended	5	10	0.06
TX0098809	3/31/2020	001A	Solids, total suspended	4	6	0.18
TX0098809	4/30/2020	001A	Solids, total suspended	2	3	0.21
TX0098809	5/31/2020	001A	Solids, total suspended	3	5	0.17
TX0098809	6/30/2020	001A	Solids, total suspended	3	4	0.17
TX0098809	7/31/2020	001A	Solids, total suspended	4	5	0.49
TX0098809	8/31/2020	001A	Solids, total suspended	2	2	0.08
TX0098809	9/30/2020	001A	Solids, total suspended	2	2	0.08
TX0098809	10/31/2020	001A	Solids, total suspended	2	3	0.10
TX0098809	11/30/2020	001A	Solids, total suspended	3	4	0.19
TX0098809	12/31/2020	001A	Solids, total suspended	4	6	0.25

TX0098809	1/31/2021	001A	Solids, total suspended	7	16	0.30
TX0098809	2/28/2021	001A	Solids, total suspended	7	19	1.97
TX0098809	3/31/2021	001A	Solids, total suspended	4	7	0.28
TX0098809	4/30/2021	001A	Solids, total suspended	3	4	0.05
TX0098809	5/31/2021	001A	Solids, total suspended	12	20	0.22
TX0098809	6/30/2021	001A	Solids, total suspended	3	5	0.02
TX0098809	7/31/2021	001A	Solids, total suspended	5	9	0.19
TX0098809	8/31/2021	001A	Solids, total suspended	3	4	0.17
TX0098809	9/30/2021	001A	Solids, total suspended	5	8	0.13
TX0098809	10/31/2021	001A	Solids, total suspended	3	4	0.43
TX0098809	11/30/2021	001A	Solids, total suspended	5	7	0.006
TX0098809	12/31/2021	001A	Solids, total suspended	3	4	0.09
TX0098809	1/31/2022	001A	Solids, total suspended	6	8	0.56
TX0098809	2/28/2022	001A	Solids, total suspended	6	8	0.09
TX0098809	3/31/2022	001A	Solids, total suspended	12	28	0.11
TX0098809	4/30/2022	001A	Solids, total suspended	7	9	0.57
TX0098809	5/31/2022	001A	Solids, total suspended	4	7	0.04
TX0098809	6/30/2022	001A	Solids, total suspended	4	6	0.05
TX0098809	7/31/2022	001A	Solids, total suspended	3	5	0.20
TX0098809	8/31/2022	001A	Solids, total suspended	4.73	7.9	3.46
TX0098809	9/30/2022	001A	Solids, total suspended	3	4	0.02
TX0098809	10/31/2022	001A	Solids, total suspended	3	5	0.14
TX0098809	11/30/2022	001A	Solids, total suspended	7	10	0.10
TX0098809	12/31/2022	001A	Solids, total suspended	6	9	1.10
TX0098809	1/31/2023	001A	Solids, total suspended	7	15	0.83
TX0098809	2/28/2023	001A	Solids, total suspended	3	5	0.26
TX0098809	3/31/2023	001A	Solids, total suspended	3	4	0.01
TX0098809	4/30/2023	001A	Solids, total suspended	2	2	0.0026
TX0098809	5/31/2023	001A	Solids, total suspended	2	3	0.21
TX0098809	6/30/2023	001A	Solids, total suspended	2	3	0.33
TX0098809	7/31/2023	001A	Solids, total suspended	2	2	0.62
TX0098809	8/31/2023	001A	Solids, total suspended	2	2	0.03
TX0098809	9/30/2023	001A	Solids, total suspended	2	2	0.31
TX0098809	10/31/2023	001A	Solids, total suspended	2	3	0.25
TX0098809	11/30/2023	001A	Solids, total suspended	3	3	0.05
TX0098809	12/31/2023	001A	Solids, total suspended	3	4	0.24
TX0098809	1/31/2024	001A	Solids, total suspended	3.4	18	1.69
TX0098809	2/29/2024	001A	Solids, total suspended	22.5	62	8.60
TX0098809	3/31/2024	001A	Solids, total suspended	5	6	0.58
TX0098809	4/30/2024	001A	Solids, total suspended	7	21	2.99
TX0098809	5/31/2024	001A	Solids, total suspended	8.25	21	0.0013

TX0098809	6/30/2024	001A	Solids, total suspended	<2	2	0.05
TX0098809	7/31/2024	001A	Solids, total suspended	9	25	0.06
TX0098809	8/31/2024	001A	Solids, total suspended	3.25	4	1.33
TX0098809	9/30/2024	001A	Solids, total suspended	2.5	4	0.03
2 YEAR AVERAGE				4.60	9.56	0.79
5 YEAR AVERAGE				4.45	8.11	0.54

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				DAILY AV (CFU/100m	SINGGRAB (CFU/100mL)
TX0098809	8/31/2019	001Q	E. coli	<1	<1
TX0098809	11/30/2019	001Q	E. coli	<1	<1
TX0098809	2/29/2020	001Q	E. coli	<1	<1
TX0098809	6/30/2020	001Q	E. coli	Not Received	Not Received
TX0098809	9/30/2020	001Q	E. coli	Not Received	Not Received
TX0098809	12/31/2020	001Q	E. coli	Not Received	Not Received
TX0098809	3/31/2021	001Q	E. coli	Not Received	Not Received
TX0098809	6/30/2021	001Q	E. coli	Not Received	Not Received
TX0098809	9/30/2021	001Q	E. coli	Not Received	Not Received
TX0098809	12/31/2021	001Q	E. coli	Not Received	Not Received
TX0098809	3/31/2022	001Q	E. coli	Not Received	Not Received
TX0098809	6/30/2022	001Q	E. coli	1	1
TX0098809	9/30/2022	001Q	E. coli	1	1
TX0098809	12/31/2022	001Q	E. coli	1	1
TX0098809	3/31/2023	001Q	E. coli	8	8
TX0098809	6/30/2023	001Q	E. coli	1	1
TX0098809	9/30/2023	001Q	E. coli	1	1
TX0098809	12/31/2023	001Q	E. coli	1	1
TX0098809	3/31/2024	001Q	E. coli	1	1
TX0098809	6/30/2024	001Q	E. coli	<1	<1
TX0098809	9/30/2024	001Q	E. coli	1	1
2 YEAR GEOMEAN				1.26	1.26
5 YEAR GEOMEAN				1.17	1.17

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (N=0;Y=1)
TX0098809	7/31/2020	SLDF	Compliance w/part 258 sludge requirement	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual amount of sludge land applied	0

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual amt of sludge incinerated	0

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual amt sludge disposed in landfill	0

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual amt. sludge disposed surface unit	0

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual amt sludge transported interstate	0

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Annual sludge production, total	.85

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL MAX (mg/kg)
TX0098809	7/31/2020	SLDP	Polychlorinated biphenyls [PCBs]	NODI=9

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MO AV MN (pass=0;fail=1)
TX0098809	7/31/2020	SLDP	Toxicity characteristic leaching procedure	NODI=9

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				ANNL TOT (DMT/y)
TX0098809	7/31/2020	SLDP	Ann. amt sludge disposed by other method	.85

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MX VALUE (met t/ha/yr)
TX0098809	7/31/2020	SLLA	Annual whole sludge application rate	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Arsenic, dry weight	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Cadmium, dry weight	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Chromium, sludge, total, dry weight [as Cr]	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Copper, dry weight	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Lead, sludge, total, dry weight [as Pb]	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Mercury, sludge, total, dry weight [as Hg]	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Molybdenum, sludge, total, dry weight [as Mo]	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)

TX0098809	7/31/2020	SLLA	Nickel, sludge, total, dry weight [as Ni]	NODI=C	NODI=C	NODI=C
-----------	-----------	------	---	--------	--------	--------

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Selenium, dry weight	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure	Reported Measure
				SINGSAMP (mg/kg)	MAXIMUM (mg/kg)	MX VALUE (lb/acr)
TX0098809	7/31/2020	SLLA	Zinc, sludge, total, dry weight [as Zn]	NODI=C	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (table #)
TX0098809	7/31/2020	SLLA	Pollutant table from 503.13	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (alt #)
TX0098809	7/31/2020	SLLA	Description of pathogen option used	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (alt #)
TX0098809	7/31/2020	SLLA	Vector attraction reduction alternative used	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MX VALUE (state class)
TX0098809	7/31/2020	SLLA	Level of pathogen requirements achieved	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MAXIMUM (MPN/g)
TX0098809	7/31/2020	SLLY	Fecal coliform	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MAXIMUM (MPN/g)
TX0098809	7/31/2020	SLLY	Salmonella	NODI=C

EPA ID				Reported Measure	Reported Measure
--------	--	--	--	------------------	------------------

	Monitoring Period	Outfall	Parameter	ALLWCONC (mg/kg)	SINGSAMP (mg/kg)
TX0098809	7/31/2020	SLSA	Arsenic, dry weight	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (acr)
TX0098809	7/31/2020	SLSA	Boundary areas	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				ALLWCONC (mg/kg)	SINGSAMP (mg/kg)
TX0098809	7/31/2020	SLSA	Chromium, sludge, total, dry weight [as Cr]	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (alt #)
TX0098809	7/31/2020	SLSA	Description of pathogen option used	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure	Reported Measure
				ALLWCONC (mg/kg)	SINGSAMP (mg/kg)
TX0098809	7/31/2020	SLSA	Nickel, total [as Ni]	NODI=C	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				MINIMUM (SU)
TX0098809	7/31/2020	SLSA	pH	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (N=0;Y=1)
TX0098809	7/31/2020	SLSA	Unit w/liner/leachate collection system	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				VALUE (alt #)
TX0098809	7/31/2020	SLSA	Vector attraction reduction alternative used	NODI=C

EPA ID	Monitoring Period	Outfall	Parameter	Reported Measure
				SINGSAMP (state class)
TX0098809	7/31/2020	SLSA	Level of pathogen requirements achieved	NODI=C

Senate Bill 709 (84th Legislative Session, 2015) amended the Texas Water Code by adding new Section 5.5553, which requires the Texas Commission on Environmental Quality (TCEQ) to provide written notice to you at least thirty (30) days prior to the TCEQ's issuance of draft permits for applications that are located in your district.

CSWR-Texas Utility Operating Company, LLC, 1630 Des Peres Road, Suite 140, Des Peres, Missouri 63131, has applied to the TCEQ to renew Texas Pollutant Discharge Elimination System Permit No. WQ0013147001 (EPA I.D. No. TX0098809) to authorize the discharge of treated wastewater at a volume not to exceed a daily average flow of 65,000 gallons per day. The domestic wastewater treatment facility is located at 404 Branding Iron, Livingston, Texas 77351, near the city of Livingston, in Polk County, Texas 77351. The discharge route is from the plant site directly to Lake Livingston in Segment No. 0803 of the Trinity River Basin. TCEQ received this application on September 30, 2024. The permit application will be available for viewing and copying at Livingston Municipal Library, 707 North Tyler Avenue, Livingston, in Polk County, Texas. The application, including any updates, and associated notices are available electronically at the following webpage:

<https://www.tceq.texas.gov/permitting/wastewater/pending-permits/tpdes-applications>.

This link to an electronic map of the site or facility's general location is provided as a public courtesy and is not part of the application or notice. For the exact location, refer to the application. <https://gisweb.tceq.texas.gov/LocationMapper/?marker=-95.0346,30.7079&level=18>

TCEQ is preparing the initial draft permit. At the time the draft permit is issued, the applicant will be required to publish notice in a newspaper of general circulation, and the TCEQ will provide a copy of the notice of draft permit to persons who have requested to be on a mailing list.

Questions regarding this application may be directed to Mr. Deba Dutta, P.E., by calling 512-239-4608.

Issuance Date: _____

TCEQ Interoffice Memorandum

To: Municipal Permits Team
Wastewater Permitting Section

Thru: Claire Dittelmier
Modeler, Water Quality Assessment Team
Water Quality Assessment Section

From: Mara Guerin
Modeler, Water Quality Assessment Team
Water Quality Assessment Section

Date: June 16, 2025

Subject: CSWR-Texas Utility Operating Company, LLC
Permit Renewal (WQ0013147001, TX0098809)
Discharge directly to Lake Livingston (Segment No. 0803) of the Trinity River Basin

The referenced applicant is proposing to renew its permit authorizing the discharge of 0.065 MGD of treated domestic wastewater directly to Lake Livingston (Segment No. 0803) of the Trinity River Basin. The facility is located in Polk County.

This permit action is for renewal of an existing authorization. A dissolved oxygen modeling analysis was previously performed for this permit on February 11, 2016 by Kristin L. Seiter. Applicable water body uses and criteria, proposed permitted flow conditions, and modeling analytical procedures pertaining to this discharge situation remain unchanged from the previous review. Therefore, the existing effluent set of **10 mg/L BOD₅** and **4.0 mg/L DO** is applicable to this permit. No additional modeling work was performed for the current permit action.

Segment No. 0803 is currently listed on the State's inventory of impaired and threatened waters (**2024** Clean Water Act Section 303(d) list). The listing is for PCBs in edible tissue and Dioxin in edible tissue in the entire reservoir, from Livingston Dam in Polk/San Jacinto County to a point 1.8 km (1.1 mi) upstream of Boggy Creek in Houston/Leon County, up to the normal pool elevation of 131 feet (impounds Trinity River) (AU 0803_01 through AU 0803_12).

The existing effluent limits have been reviewed for consistency with the State of Texas Water Quality Management Plan (WQMP). The existing limits are consistent with the approved WQMP.

TCEQ Interoffice Memorandum

To: Municipal Permits Team
Wastewater Permitting Section

From: Lauren Williams, Standards Implementation Team
Water Quality Assessment Section
Water Quality Division

Date: October 4, 2024

Subject: CSWR – Texas Utility Operating Company, LLC; Permit No. WQ0013147001
Renewal; Application Received: September 30, 2024

The discharge route for the above referenced permit is directly to Lake Livingston in Segment 0803 of the Trinity River Basin. The designated uses and dissolved oxygen criterion as stated in Appendix A of the Texas Surface Water Quality Standards (30 Texas Administrative Code §307.10) for Segment 0803 are primary contact recreation, public water supply, high aquatic life use, and 5.0 mg/L dissolved oxygen.

The discharge from this permit action is not expected to have an effect on any federal endangered or threatened aquatic or aquatic dependent species or proposed species or their critical habitat. This determination is based on the United States Fish and Wildlife Service's (USFWS) biological opinion on the State of Texas authorization of the Texas Pollutant Discharge Elimination System (TPDES; September 14, 1998; October 21, 1998 update). To make this determination for TPDES permits, TCEQ and EPA only considered aquatic or aquatic dependent species occurring in watersheds of critical concern or high priority as listed in Appendix A of the USFWS biological opinion. The determination is subject to reevaluation due to subsequent updates or amendments to the biological opinion. The permit does not require EPA review with respect to the presence of endangered or threatened species.