

SWR 31235

ASARCO EL PASO COPPER SMELTER PHASE III REMEDIAL INVESTIGATION REPORT EL PASO, TEXAS

Prepared For:



2301 West Paisano Drive
El Paso, Texas 79922

RECEIVED

NOV 19 2001

REMEDIATION DIVISION
Corrective Action Section

Prepared By:



Hydrometrics, Inc.®

consulting scientists, engineers and contractors



**VOLUME
I of V**

November 2001

SWR # 31235CAS DOC #
PROJ. MGR14721Brad N.

November 19, 2001


El Paso Plant
L. W. Castor, Unit Manager**HAND DELIVERED****RECEIVED****NOV 19 2001****REMEDIATION DIVISION**
Corrective Action SectionMr. Brad Wilkinson, Project Manager
Team One, Corrective Action Section
Remediation Division
Texas Natural Resource Conservation Commission
P.O. Box 13087
Austin, Texas 78711-3087**Re: Phase III Remedial Investigation Report Submittal**
Asarco Incorporated, El Paso Facility
Agreed Order Docket No. 96-0212-MLM-E
TNRCC Industrial Solid Waste Registration No. 31235

Dear Mr. Wilkinson:

As required by ordering provisions 6 and 9 of the above referenced Agreed Order, enclosed are two copies of the Remedial Investigation Phase III Report for the El Paso Facility of Asarco Incorporated. This Phase III Report includes the results of Closed-Plant evaluations, pursuant to our request of June 14, 2001 and approved by TNRCC on July 10, 2001.

Do not hesitate to contact me at (915) 541-1819, if you have any questions regarding this submittal.

Sincerely,


Larry A. Johnson
Environmental Managercc: Archie Clouse - TNRCC, El Paso (1)
Don Robbins - Asarco (1)
Larry Castor - Asarco (1)
Duane Yantorno - Asarco (1)
R. Keith Hopson - Brown McCarroll L.L.P., Austin (1)
Kent Lang - ARCADIS, Phoenix (1)
Bill Thompson/Steve Ackerslund - Hydrometrics, Inc., Helena (1)
Tom Klempel - Hydrometrics, Inc., Tucson (1)
Arturo Burgos - Hydrometrics, Inc., El Paso (1)

RECEIVED

NOV 19 2001

REMEDATION DIVISION
Corrective Action Section

TABLE OF CONTENTS

TABLE OF CONTENTS

LIST OF TABLES.....	v
LIST OF FIGURES.....	x
LIST OF EXHIBITS.....	xiv
LIST OF APPENDICES.....	xiv
EXECUTIVE SUMMARY.....	xvi
1.0 INTRODUCTION.....	1-1
1.1 FACILITY BACKGROUND INFORMATION.....	1-3
1.1.1 Physical and Geological Settings.....	1-4
1.1.2 Groundwater and Surface Water.....	1-6
1.1.3 Regulatory Summary.....	1-8
1.1.4 Related Work.....	1-8
1.2 PREVIOUS AND CURRENT RI INVESTIGATIONS.....	1-9
1.2.1 History of Process Pond Investigations.....	1-9
1.2.2 History of Diesel Spill Investigations.....	1-11
1.3 RI BACKGROUND INFORMATION.....	1-14
1.3.1 Investigation Areas.....	1-14
1.3.2 Source Material Classification.....	1-17
1.4 PHASE III RI PROJECT OBJECTIVES.....	1-17
1.5 PHASE III RI WORK PLAN TASKS.....	1-18
1.6 PHASE III REPORT ORGANIZATION.....	1-20
2.0 REMEDIAL INVESTIGATION RESULTS AND THE RELATIONSHIP BETWEEN SMELTER OPERATIONS AND POTENTIAL SOURCE AREAS AND MATERIALS.....	2-1
2.1 OVERVIEW.....	2-2
2.2 SOIL INVESTIGATION RESULTS.....	2-6
2.2.1 Field Activity Summary.....	2-6
2.3 GROUNDWATER INVESTIGATION RESULTS.....	2-8
2.3.1 Overview.....	2-8
2.3.2 Phase III RI Groundwater Results.....	2-10

2.3.3 RI Groundwater Characterization Summary	2-12
2.4 SURFACE WATER INVESTIGATION RESULTS	2-20
2.4.1 Overview.....	2-20
2.4.2 RI Surface Water Characterization Summary.....	2-22
2.4.3 Distribution of COCs	2-33
2.4.4 Chemical Comparison.....	2-35
2.5 INVESTIGATION AREA BACKGROUND INFORMATION AND INVESTIGATION RESULTS	2-35
2.5.1 Converter Building/Baghouse Area (IA-1).....	2-36
2.5.2 Boneyard/Slag Area (IA-2).....	2-39
2.5.3 Acid Plants 1 and 2 Area (IA-3)	2-44
2.5.4 Front Slope/Western Facility Boundary Area (IA-4A)	2-47
2.5.5 Historic Smeltertown Area (IA-5)	2-57
2.5.6 GROUNDWATER (IA-6).....	2-60
2.5.7 SURFACE WATER (IA-7)	2-60
2.5.8 Bedding and Unloading Building Areas (IA-8).....	2-60
2.5.9 Ponds 1, 5 and 6 (IA-9).....	2-64
2.5.10 Plant Entrance Area (IA-10)	2-70
2.5.11 Arroyos East of I-10 (IA-11)	2-72
2.5.12 Ephemeral Pond and Pond Sediment Storage Area (IA-12).....	2-77
2.5.13 Sample Mill Area (IA-13).....	2-80
2.5.14 South Terrace Area (IA-14).....	2-83
2.5.15 Former Copper Plant Area (IA-15).....	2-86
2.5.16 Former Lead and Sinter Plant Areas (IA-16).....	2-89
2.5.17 Former Cadmium and Zinc Plant Areas (IA-17)	2-92
2.5.18 Former Antimony Plant Area (IA-18)	2-95
2.5.19 La Calavera Area (IA-19).....	2-97
2.5.20 Other Asarco Property, East of I-10 (IA-20)	2-100
2.5.21 Relation of COCs in Groundwater to COCs in Soils and Plant Processes.....	2-102
2.5.22 Prediction of Future Behavior of COCs in Groundwater	2-103

2.5.23 Former Process Ponds and Shallow Aquifer Interaction	2-104
3.0 REVISED BASELINE RISK ASSESSMENT AND CORRECTIVE ACTION	
OBJECTIVES	3-1
3.1 ON-SITE BASELINE RISK.....	3-1
3.1.1 On-Site Exposure Assessment	3-2
3.1.2 Risk Characterization.....	3-6
3.2 ON-SITE CORRECTIVE ACTION OBJECTIVES	3-11
3.2.1 Minimize Surface Soil Exposure	3-11
3.2.2 Minimize Windblown Dust Exposure	3-12
3.2.3 Prevent Groundwater Exposure and Reduce Off-Facility Metals Transport	3-13
3.2.4 Improved Storm water Control	3-15
3.3 OFF-PLANT INVESTIGATION AND RISK ASSESSMENT NEEDS.....	3-16
3.3.1 History of Investigation	3-16
3.3.2 Investigation Results	3-18
3.3.3 Off- Plant Corrective Action Objectives.....	3-20
4.0 CORRECTIVE MEASURE STUDY	4-1
4.1 OVERVIEW	4-2
4.1.1 Human Health Risk Considerations.....	4-2
4.1.2 New Investigation Area Considerations	4-5
4.1.3 Site Characterization Considerations	4-5
4.1.4 Corrective Action Considerations.....	4-6
4.2 IDENTIFICATION OF PREFERRED CORRECTIVE ACTION	
ALTERNATIVES	4-7
4.2.1 Engineering Controls	4-7
4.2.2 Institutional Controls/Deed Restrictions.....	4-8
4.2.3 Groundwater and Surface Water Monitoring	4-9
4.3 PROPOSED CORRECTIVE ACTIONS FOR EACH IA.....	4-13
4.3.1 Converter Building/Baghouse Area (IA-1).....	4-14
4.3.2 Boneyard/Slag Area (IA-2).....	4-16
4.3.3 Acid Plants 1 and 2 Area (IA-3)	4-19

4.3.4 Front Slope/Western Facility Boundary Area (IA-4)	4-21
4.3.5 Historic Smeltertown Area (IA-5)	4-25
4.3.6 Groundwater (IA-6)	4-27
4.3.7 Surface Water (IA-7)	4-28
4.3.8 Bedding and Unloading Building Area (IA-8)	4-29
4.3.9 On-Site Ponds 1, 5 and 6 (IA-9)	4-31
4.3.10 Plant Entrance Area (IA-10)	4-33
4.3.11 Arroyo East of I-10 (IA-11)	4-35
4.3.12 Ephemeral Pond and Pond Sediment Storage Area (IA-12)	4-38
4.3.13 Sample Mill Area (IA-13)	4-41
4.3.14 South Terrace Area (IA-14)	4-43
4.3.15 Copper Plant (IA-15)	4-45
4.3.16 Lead and Sinter Plants (IA-16)	4-46
4.3.17 Zinc and Cadmium Plants (IA-17)	4-48
4.3.18 Former Antimony Plant (IA-18)	4-50
4.3.19 Siting Criteria for the Design of Disposal Cells	4-50
4.4 SUMMARY AND INTEGRATION WITH PROJECT CLOSURE	4-51
4.5 PROPOSED ADDITIONAL REMEDIAL INVESTIGATION ACTIVITIES	4-54
4.5.1 Front Slope/Western Facility Boundary (IA-4) / Historic Smeltertown Area (IA-5)	4-54
4.5.2 The La Calavera Area (IA-19)	4-54
5.0 SUMMARY AND CONCLUSIONS	5-1
6.0 REFERENCES	6-1

LIST OF TABLES

TABLE 1-1	FACILITY REGULATORY PERMIT INFORMATION
TABLE 1-2	ACTIVE SOLID WASTE MANAGEMENT UNITS
TABLE 1-3	SUMMARY OF HISTORIC OPERATION ACTIONS AND REPORTS
TABLE 1-4	GENERAL DESCRIPTION OF INVESTIGATION AREAS
TABLE 2-1	SUMMARY OF FACILITY RI MONITOR WELLS AND SOIL BORINGS
TABLE 2-2	ANALYTICAL PARAMETERS FOR SOIL AND WATER SAMPLES
TABLE 2-3	WELL COMPLETION AND SURVEY DATA FOR EACH MONITORING WELL
TABLE 2-4	SUMMARY OF AQUIFER TEST RESULTS
TABLE 2-5	STATISTICAL SUMMARY OF WATER QUALITY RESULTS FOR AUGUST 2001
TABLE 2-6	IBWC RIO GRANDE WATER QUALITY DATA, FEBRUARY 2000 THROUGH JUNE 2001 AT COURCHESNE BRIDGE.
TABLE 2-7	IBWC RIO GRANDE WATER QUALITY DATA, FEBRUARY 2000 THROUGH JUNE 2001 AT BOWIE HIGH SCHOOL FOOTBALL FIELD
TABLE 2-8	IBWC AVERAGE CONCENTRATIONS OF RIO GRANDE WATER QUALITY DATA, FEBRUARY 2000 THROUGH JUNE 2001
TABLE 2-9	HYDROMETRICS SURFACE WATER QUALITY RESULTS, FEBRUARY 2000 THROUGH AUGUST 2001
TABLE 2-10	HYDROMETRICS SURFACE WATER METAL CONCENTRATION RESULTS, FEBRUARY 2000 THROUGH AUGUST 2001
TABLE 2-11	SUMMARY OF HYDROMETRICS SURFACE WATER QUALITY RESULTS, FEBRUARY 2000 THROUGH AUGUST 2001

TABLE 2-12	SUMMARY OF HYDROMETRICS STREAMBED SEDIMENT SAMPLE RESULTS, AUGUST 1999 THROUGH AUGUST 2001
TABLE 2-13	IBWC RIO GRANDE MONTHLY MEAN WATER FLOW VOLUMES AT THE PUMP HOUSE, COURCHESNE BRIDGE, AND THE DIVERSION AT THE AMERICAN CANAL, JANUARY 2000 THROUGH JUNE 2001
TABLE 2-14	GROUNDWATER ELEVATIONS IN WELLS ADJACENT TO THE RIO GRANDE AND IN HISTORICAL SMELTERTOWN, FEBRUARY 1995 THROUGH AUGUST 2001
TABLE 2-15	SUMMARY OF HYDROMETRICS ONSITE PONDS SURFACE WATER QUALITY RESULTS, AUGUST 1997 THROUGH AUGUST 2001
TABLE 2-16	SUMMARY OF HYDROMETRICS ONSITE PONDS SURFACE WATER METAL CONCENTRATION RESULTS, AUGUST 1997 THROUGH AUGUST 2001
TABLE 2-17	DRINKING WATER STANDARDS, MAXIMUM CONTAMINANT LEVELS
TABLE 2-18	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 1 (IA-1)
TABLE 2-19	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 1 (IA-1)
TABLE 2-20	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 2 (IA-2)
TABLE 2-21	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 2 (IA-2)
TABLE 2-22	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 3 (IA-3)

TABLE 2-23	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 3 (IA-3)
TABLE 2-24	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 4 (IA-4)
TABLE 2-25	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 4 (IA-4)
TABLE 2-26	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 5 (IA-5)
TABLE 2-27	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 5 (IA-5)
TABLE 2-28	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 8 (IA-8)
TABLE 2-29	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 8 (IA-8)
TABLE 2-30	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 9 (IA-9)
TABLE 2-31	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 9 (IA-9)
TABLE 2-32	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 10 (IA-10)
TABLE 2-33	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 10 (IA-10)
TABLE 2-34	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 11 (IA-11)

TABLE 2-35	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 11 (IA-11)
TABLE 2-36	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 12 (IA-12)
TABLE 2-37	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 12 (IA-12)
TABLE 2-38	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 13 (IA-13)
TABLE 2-39	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 13 (IA-13)
TABLE 2-40	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 14 (IA-14)
TABLE 2-41	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 14 (IA-14)
TABLE 2-42	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 15 (IA-15)
TABLE 2-43	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 15 (IA-15)
TABLE 2-44	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 16 (IA-16)
TABLE 2-45	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 16 (IA-16)
TABLE 2-46	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 17 (IA-17)

TABLE 2-47	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 17 (IA-17)
TABLE 2-48	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 18 (IA-18)
TABLE 2-49	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 18 (IA-18)
TABLE 2-50	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 19 (IA-19)
TABLE 2-51	SUMMARY OF PHASE III RI GROUNDWATER QUALITY RESULTS (METAL ANALYSIS) FOR MONITORING WELLS IN INVESTIGATION AREA 19 (IA-19)
TABLE 2-52	SUMMARY OF SOIL SAMPLE RESULTS FOR INVESTIGATION AREA 20 (IA-20)
TABLE 3-1	RISK-BASED CONCENTRATIONS OF POTENTIAL CONCERN
TABLE 4-1	SUMMARY OF REMEDIAL ELEMENTS ASSOCIATED WITH THE INVESTIGATION AREAS
TABLE 4-2	MONITORING WELL SAMPLING FREQUENCIES

LIST OF FIGURES

FIGURE 1-1	PROJECT VICINITY MAP
FIGURE 1-2	PLANT COMPONENTS
FIGURE 1-3	ESTIMATED EXTENT OF LIQUID PHASE DIESEL, AUGUST 2001
FIGURE 2-1	PROCESS POND, STORM WATER EVAPORATION PONDS, EPHEMERAL POND AND HISTORIC ARROYO LOCATIONS
FIGURES 2-2a & b	IAs SOIL SAMPLE LOCATIONS
FIGURE 2-3	SURFACE WATER AND GROUNDWATER SAMPLING LOCATIONS
FIGURE 2-4	HYDROGEOLOGIC CROSS SECTION LOCATIONS
FIGURE 2-5	GROUNDWATER POTENTIOMETRIC MAP FOR FEBRUARY 2001
FIGURE 2-6	GROUNDWATER POTENTIOMETRIC MAP FOR AUGUST 2001
FIGURE 2-7	COMPARISON OF GROUNDWATER AND SURFACE WATER ELEVATIONS ALONG THE RIO GRANDE RIVER DURING HIGH & LOW FLOW PERIODS
FIGURE 2-8	TOTAL ARSENIC CONCENTRATIONS IN GROUNDWATER – AUGUST 2001
FIGURE 2-9	DISSOLVED ARSENIC CONCENTRATIONS IN GROUNDWATER – AUGUST 2001
FIGURE 2-10	COMPARISON OF TDS AND ARSENIC CONCENTRATIONS AT MONITORING WELL EP-114
FIGURE 2-11	TOTAL CADMIUM CONCENTRATIONS IN GROUNDWATER – AUGUST 2001
FIGURE 2-12	DISSOLVED CADMIUM CONCENTRATIONS IN GROUNDWATER – AUGUST 2001
FIGURE 2-13	TOTAL LEAD CONCENTRATIONS IN GROUNDWATER – AUGUST 2001

FIGURE 2-14	DISSOLVED LEAD CONCENTRATIONS IN GROUNDWATER -- AUGUST 2001
FIGURE 2-15	IBWC SURFACE WATER MONITORING LOCATIONS
FIGURE 2-16	LINEAR GRAPH SHOWING IBWC WATER QUALITY DATA FOR THE RIO GRANDE, AT COURCHESNE BRIDGE, 1997 THROUGH JUNE 2001
FIGURE 2-17	BAR GRAPH SHOWING IBWC WATER QUALITY DATA FOR THE RIO GRANDE, AT COURCHESNE BRIDGE, AUGUST 1995 THROUGH JUNE 2001
FIGURE 2-18	LINEAR GRAPH SHOWING IBWC WATER QUALITY DATA FOR THE RIO GRANDE, AT BOWIE HIGH SCHOOL STADIUM, 1997 THROUGH JUNE 2001
FIGURE 2-19	BAR GRAPH SHOWING IBWC WATER QUALITY DATA FOR THE RIO GRANDE, AT BOWIE HIGH SCHOOL STADIUM, AUGUST 1995 THROUGH JUNE 2001
FIGURE 2-20	RIO GRANDE DAILY MEAN FLOW VOLUMES AT THREE MEASURING LOCATIONS, BOWIE PUMP HOUSE, COURCHESNE BRIDGE, AND AMERICAN CANAL, 1995 THROUGH JUNE 2001
FIGURE 2-21	GROUNDWATER ELEVATION OF WELLS ADJACENT TO RIO GRANDE (IN FEET), 1995 THROUGH AUGUST 2001
FIGURE 2-22	GROUNDWATER ELEVATION OF WELLS LOCATED IN HISTORIC SMELTERTOWN AREA, 1995 THROUGH AUGUST 2001
FIGURE 2-23	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 1 (IA-1)
FIGURE 2-24	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 2 (IA-2)
FIGURE 2-25	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 3 (IA-3)

FIGURE 2-26	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 4 (IA-4)
FIGURE 2-27	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 5 (IA-5)
FIGURE 2-28	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 8 (IA-8)
FIGURE 2-29	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 9 (IA-9)
FIGURE 2-30	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 10 (IA-10)
FIGURE 2-31	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 11 (IA-11)
FIGURE 2-32	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 12 (IA-12)
FIGURE 2-33	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 13 (IA-13)
FIGURE 2-34	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 14 (IA-14)
FIGURE 2-35	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 15 (IA-15)
FIGURE 2-36	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 16 (IA-16)
FIGURE 2-37	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 17 (IA-17)
FIGURE 2-38	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 18 (IA-18)
FIGURE 2-39	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 19 (IA-19)
FIGURES 2-40a & b	SOIL SAMPLING LOCATIONS FOR INVESTIGATION AREA 20 (IA-20)
FIGURE 3-1	BASELINE EXPOSURE PATHWAY FLOW CHART

FIGURE 4-1	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 1 (IA-1)
FIGURE 4-2	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 2 (IA-2)
FIGURE 4-3	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 3 (IA-3)
FIGURE 4-4	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 4 (IA-4)
FIGURE 4-5	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 5 (IA-5)
FIGURE 4-6	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 8 (IA-8)
FIGURE 4-7	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 9 (IA-9)
FIGURE 4-8	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 10 (IA-10)
FIGURE 4-9	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 11 (IA-11)
FIGURE 4-10	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 12 (IA-12)
FIGURE 4-11	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 13 (IA-13)
FIGURE 4-12	A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 14 (IA-14)

- FIGURE 4-13 A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 15 (IA-15)
- FIGURE 4-14 A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 16 (IA-16)
- FIGURE 4-15 A CONCEPTUAL ILLUSTRATION OF CORRECTIVE ACTION MEASURES FOR INVESTIGATION AREA 17 (IA-17)

LIST OF EXHIBITS

- EXHIBIT 1 FACILITY SITE PLAN SHOWING PHASE III REMEDIAL INVESTIGATION AREAS
- EXHIBITS 2 & 3 GEOLOGIC CROSS SECTIONS

LIST OF APPENDICES

- APPENDIX A CORRESPONDENCE RELEVANT TO THE ASARCO EL PASO COPPER SMELTER REMEDIAL INVESTIGATION
- APPENDIX B CUMULATIVE LIST OF SURFACE WATER QUALITY RESULTS (GENERAL CHEMISTRY)
- APPENDIX C CUMULATIVE LIST OF SURFACE WATER QUALITY RESULTS (METAL ANALYSIS)
- APPENDIX D CUMULATIVE LIST OF GROUNDWATER QUALITY RESULTS (GENERAL CHEMISTRY)
- APPENDIX E CUMULATIVE LIST OF GROUNDWATER QUALITY RESULTS (METAL ANALYSIS)
- APPENDIX F PHASE III SURFACE WATER AND GROUNDWATER ANALYTICAL REPORTS
- APPENDIX G PHASE III SOIL-SEDIMENTS ANALYTICAL REPORTS

APPENDIX H	PHASE III SURFACE AND GROUNDWATER DATA VALIDATION REPORTS
APPENDIX I	PHASE III SOIL DATA VALIDATION REPORTS
APPENDIX J	PHASE III LITHOLOGIC LOGS AND MONITORING WELL COMPLETION REPORTS
APPENDIX K	GRAPHS OF SOIL SAMPLE METAL ANALYSIS CONCENTRATION VERSUS DEPTHS
APPENDIX L	GRAPHS OF TOTAL AND DISSOLVED METALS CONCENTRATIONS IN GROUNDWATER VERSUS TIME
APPENDIX M	WATER TABLE MONITORING DATA
APPENDIX N	SURFACE SOIL SAMPLES (0 TO 3 FEET DEPTH)
APPENDIX O	EPA SOIL SAMPLE RESULTS AND ATSDR REPORT
APPENDIX P	IN-VITRO BIO-AVAILABILITY RESULTS AND METHODOLOGY
APPENDIX Q	SECTION 4.2 OF THE PHASE I RI REPORT (CORRECTIVE MEASURE ALTERNATIVES)

**ASARCO EL PASO COPPER SMELTER
PHASE III REMEDIAL INVESTIGATION REPORT
EL PASO, TEXAS**

EXECUTIVE SUMMARY

INTRODUCTION

Pursuant to and in accordance with an Agreed Order with the Texas Natural Resource Conservation Commission (Docket No. 96-0212-MLM-E; TNRCC, 1996), ASARCO Incorporated (Asarco) through its contractor Hydrometrics, conducted a Remedial Investigation (RI) for the Asarco Copper Plant in El Paso, Texas.

The Copper Plant is located within the city limits of El Paso, Texas, adjacent to the Rio Grande River (Rio Grande). In accordance with TNRCC requirements and the RI Work Plan (Hydrometrics 1996), soil, groundwater and surface water were characterized (sampled, tested and analyzed) for physical and inorganic (primarily trace metal) chemical parameters. Based on characterization data, potential risks and corrective measures associated with metals in soil, groundwater and surface water were evaluated.

The RI was conducted in three phases; Phase I in 1997-1998, Phase II in 1999-2000, and Phase III in 2001. Phase I and Phase II RI efforts focused on on-Plant investigation areas, and the results were presented in the Phase I (Hydrometrics 1998) and Phase II (Hydrometrics 2000) RI Reports. Phase III RI efforts supplement earlier investigation efforts and include additional on-Plant and off-Plant investigation areas. The Phase III RI data are presented in this Phase III RI report, with a cumulative summary of the Phase I and Phase II data.

SOILS

Soils in the Copper Plant area are a mix of colluvial and fluvial sediments, with areas of extensive man-deposited fill consisting of slag, soil and other man made (typically building or other smelter production by-product) materials. Primary soil Constituents of Concern (COCs) are arsenic, cadmium and lead, which are associated with historic smelter operations, as well as occurring naturally in the general area. In the on-Plant investigation areas, soil COC concentrations are generally highest near the ground surface, and generally decrease with depth. On-Plant soil concentrations are variable and appear to show influences and association with past Plant operation practices. As a result, near surface Plant COC concentrations, as well as some subsurface soil concentrations, are elevated above local background levels.

Off-Plant soils were investigated by both Asarco (Hydrometrics Phase III RI), and by the Environmental Protection Agency (EPA). The Asarco off-Plant investigation efforts focused on open areas adjacent to the Plant including "Smeltertown" located between the Plant areas and the Rio Grande, and open areas north and east of the Plant (La Calavera and east of I-10). Soil sample results in these areas show elevated arsenic and metals in near surface (1 to 3 feet below ground surface (bgs)) samples. Asarco also collected samples in adjacent residential areas north of the Plant (La Calavera). Sample results are variable with generally elevated near surface arsenic and lead concentrations nearest the Plant and decreasing concentrations with distance from the Plant.

EPA investigation efforts include several locations throughout the El Paso area including a residential area immediately adjacent north of the Plant (La Calavera). At the time of this writing EPA is in the process of evaluating their data; however, a review of the data show COC concentrations range from slightly elevated near-Plant boundary areas to apparent urban background levels over most of the EPA sample area.

GROUNDWATER

A shallow aquifer occurs beneath the Asarco Facility that is separated from any regional aquifer and associated groundwater use. The aquifer beneath the Plant is classified as brackish according to relatively high Total Dissolved Solids (TDS) concentrations.

The RI groundwater investigation included installation and testing of 67 monitoring wells. These wells supplemented 35 existing monitoring wells installed as part of previous Plant investigation efforts. All existing and RI monitoring wells were sampled and analyzed for water quality during the RI.

Stratigraphy

Stratigraphic units at the El Paso Plant generally consist of man-placed fill underlain by alluvial and colluvial deposits, which in-turn are underlain by bedrock composed of Tertiary age andesite and Cretaceous age sandstones, shales, limestones and siltstones. Water bearing strata under the Plant consist of alluvial and colluvial deposits of mixed sand, gravel, boulders and bedrock. In the on-Plant area, ephemeral drainage arroyos have cut into colluvial and bedrock strata and probably influence groundwater flow from upland Plant areas toward Rio Grande flood plain alluvial deposits and the Rio Grande. Arroyos in on-Plant areas have been backfilled with man-deposited soil, slag and other smelter production by products and building debris. Rio Grande alluvial deposits (near Smeltertown west and adjacent to the Plant) consist of reworked colluvial and terrace deposits, and are composed predominately of sands, silts and clays in the upper 20 feet of the deposits.

Water Level Data

Depth to groundwater in on-Plant areas is 40 to 60 feet bgs depending on the location. On the Rio Grande flood plain west and adjacent to the Plant, the depth to groundwater is about 10 feet bgs. Groundwater flow in the Plant area is generally from the east-northeast to the west-southwest toward the Rio Grande flood plain and river. Seasonal variations in river stage affect groundwater flow at the river's edge, with flow toward the river during low stage periods, and flow more parallel to the river during high stage

periods when the river is higher than immediately adjacent flood plain alluvial groundwater levels.

Groundwater Quality

Water quality sampling results show the Plant area shallow groundwater system has elevated concentrations of arsenic, cadmium, lead and selenium and to a lesser degree other metals including copper and zinc. Concentrations of sulfate and TDS are also elevated with TDS concentration ranging from 3000 milligrams/liter (mg/l) to 10,000 mg/l; the water quality is classified as brackish. Groundwater in the facility is not used for drinking water supply purposes.

Of the elements analyzed, arsenic, cadmium and lead are considered the primary groundwater COCs. Arsenic concentrations were elevated above drinking water Maximum Contaminant Limits (MCLs) through out the western portion of the Plant area groundwater. Cadmium and lead also exceed MCLs at some locations on the Plant, but are generally less mobile in groundwater than arsenic, and elevated concentration are limited to a few point source locations on the Plant.

Highest arsenic and metal concentrations occur in locations adjacent to the Acid Plant and acid storage tank areas, and areas adjacent and downgradient of former process water ponds. Locally, on-Plant process fluid losses from process lines, drains and sumps have likely also contributed arsenic and metals to groundwater.

While cadmium and lead concentrations are generally elevated only near on-Plant source areas, arsenic concentrations are also elevated at down-gradient locations in the Rio Grande flood plain aquifer adjacent to the Plant. Groundwater contaminant fate and transport simulations suggest arsenic could impact down gradient alluvial aquifers and the Rio Grande if on-Plant source areas are not removed or isolated as sources of arsenic to the groundwater system.

SURFACE WATER

The primary surface water features in the Plant area include the Rio Grande, which borders the site to the west and south; and the American Canal, a concrete lined channel located between the Plant and the river, which diverts water from the Rio Grande to the city of El Paso. On-Plant surface water features include three unlined process water ponds, two storm water collection ponds, and five ephemeral drainage arroyos.

Rio Grande designated water uses by TNRCC are Domestic Water Supply, Non-Contact Recreational and Limited Aquatic Life. Flow in the river is dam controlled with higher flows released during summer months (April to September). During high flow conditions, the river is generally a losing stream with localized water lost to flood plain alluvium. During low flow conditions, the river gains water from flood plain alluvial deposits.

Water sampling results show river water quality is generally a sodium sulfate type with moderately high concentrations of TDS, chloride and nutrients. Arsenic, cadmium and lead are typically below drinking water MCLs. Samples of sediment COCs also typically show low concentrations of arsenic, cadmium, and lead.

The American Canal, which diverts water from the Rio Grande just west of the Plant, has similar general water quality characteristics as the Rio Grande. RI sampling results show water quality generally meets MCLs for investigation COCs, with one minor temporary exceedance for lead during a short-term extreme low flow condition during year 2000.

Water quality sampling results from on-Plant ponds generally show high concentrations of TDS, sodium sulfate, chloride and nutrients. Concentrations of metals are also typically high and are well above MCLs for investigation COCs, and these ponds have been identified as sources of arsenic and metals to the groundwater system underlying the Plant.

HUMAN HEALTH RISKS

A Base Line Risk Assessment (BLRA) was conducted to evaluate existing on-Plant and off-Plant human health risks associated with existing exposure to arsenic and other constituents on and adjacent to the Plant. The objective of the BLRA is to establish corrective action objectives based on an understanding of risks and regulatory requirements; particularly TNRCC risk reduction standards.

On-Plant Baseline Risk

An on-Plant baseline risk assessment was completed during the Phase I RI (1998). The Phase I BLRA is augmented in this Phase III report. The supplemental evaluation included examination of on-Plant exposure settings, pathways, contamination sources, transport mechanisms, receptor contact mechanisms and intake. On-Plant exposures based on on-Plant COC concentrations in soil, groundwater and surface water were compared to applicable standards per published TNRCC guidelines. In general these guidelines were: soil risk levels for ingestion that reduce risks to less than one in one million (1×10^{-6}); groundwater constituents below MCLs; and surface water standards based on human consumption of aquatic life and fresh water standards for aquatic life. Based on the TNRCC guidelines, the following risk based standards were determined:

Parameter	Surface Soil		Groundwater	Surface Water	
	Soil/Air Ingestion - Industrial Use	Soil/Air Ingestion - Residential Use	MCLs for Drinking Water - SWDA	Human Health for Water and Fish Consumption	Fresh Water Chronic Criteria for Aquatic Life
	mg/kg		Mg/l	mg/l	
Arsenic	200	20	0.05	NA	0.190
Cadmium	410	120	0.005	0.01	0.002
Chromium	230,000	5,300	0.1	33	0.377
Copper	74,000	10,000	1.3	NA	0.027
Iron	NA	NA	0.3	NA	NA
Lead	1,600	500	0.015	NA	0.008
Selenium	9,200	1,300	0.05	0.104	0.005
Zinc	410,000	59,000	5.0	NA	0.227
Nitrates	NA	NA	10	NA	NA

Notes NA: Not Applicable

Based on the determined risk standards, existing on-Plant controls were evaluated and potential new controls were developed and refined as corrective measures for the Plant.

Off Plant Baseline Risk

Off-Plant baseline human health risks are presently being evaluated by both Asarco (Hydrometrics Phase III RI), and by the EPA.

The Asarco off-Plant risk evaluation efforts focused on open areas adjacent to the Plant including "Smeltertown" located between the Plant areas and the Rio Grande, and open areas of La Calavera, located west of the Plant adjacent to slag storage areas.

Since elevated surface soil metals in the La Calavera area are most likely result of transported slag particles from near by slag storage areas, the bio-availability of metals from the slag was determined by laboratory testing. The results showed that 5.1 percent of lead and 11.1 percent of arsenic in slag-impacted soils is bio-available. As a result site-specific standards (higher than residential standards for arsenic and lead shown above), based on bio-availability test results for the La Calavera area, are anticipated.

At the time of this writing, EPA is in the process of evaluating their soil investigation data; however, following a review of the data by the Agency for Toxic Substances and Disease Registry (El Paso Times 2001) ATSDR determined the soil concentrations were no health threat.

CORRECTIVE MEASURES

Based on RI characterization data and evaluation, the BLRA, and on TNRCC Risk Reduction Rule Standard No. 3 (Closure/Remediation with Controls) corrective action objectives were developed. These are:

- Reduce the potential for metals exposure to Plant workers and the public
- Minimize the potential for transport of metals to groundwater
- Prevent increases of metal concentrations in the American Canal and the Rio Grande.

In general, the proposed corrective measures for the El Paso Plant consist of engineering controls, institutional controls, and groundwater and surface water monitoring programs.

Engineering Controls

Proposed engineering controls include: surface water runoff controls, surface soil capping, and removal/disposal actions.

Several surface water controls have already been implemented (1999 and previous) including installation of a lined impoundment for storm water collection, and installation of lined sumps, pumping systems, pipelines and storage tanks. At the same time, the three process water ponds identified as sources of COCs to groundwater were decommissioned. This action eliminates the ponds as a mechanism to contribute and transport COCs in groundwater. In addition to these actions, supplemental Plant operational controls were implemented to minimize discharges from Plant operation components. These actions have had a positive effect on Plant groundwater with decreased of COC concentrations in the areas where these actions were implemented.

Engineering controls that address soil containment or removal actions address two source area soil/material Categories (I, II), based on metal concentrations, degree of potential toxicity, distribution and volume of materials, associated Plant processes, visual characteristics and impacts to water resources. Category I are residual byproducts from current and past smelter operations and are associated with elevated concentrations of metals in underlying groundwater. Category II materials are large volumes of diluted residual by-products (most of the same materials listed as Category I) and debris from demolition of smelter facilities with residual concentrations of metals (Category II materials do not currently represent a source of metals to the underlying groundwater).

Capping actions consist of covering identified source areas containing Category II materials with an engineered barrier to inhibit infiltration of surface water through

smelter materials. Depending on the location and post-remediation use capping materials include asphalt, concrete, geomembrane liners and/or clean soil/vegetation cover.

Removal/disposal actions will be performed as appropriate on Category I materials, which will be excavated and incorporated into an on-site disposal cell. The on-Site disposal cell construction includes a bottom liner, a leachate collection system and a lined cover and will be constructed in accordance with TNRCC landfill siting and construction criteria.

Institutional Controls

Proposed institutional controls include: worker health and safety programs, municipal restrictions on groundwater use, deed restrictions; fencing and other access controls, and dust suppression. Worker health and safety programs include required OSHA training and medical monitoring, and testing for lead, cadmium and arsenic. Municipal restrictions and deed restrictions would provide legal restriction on groundwater and site use during Plant operation and after any Plant closure.

Groundwater and Surface Water Monitoring Program

A post-RI groundwater and surface water program will be prepared to help monitor groundwater and surface water conditions during corrective measure activities, and to monitor the effect of implemented corrective measures on groundwater and surface water systems.

Well Name	Status	Location	Date Completed	Designation
MONITORING WELLS				
EM-01		S of Antimony Plant behind security bldg.	5/10/90	
EM-02		Just south of Pond #1	5/11/90	
EM-03	ABANDONED	Near red fire house, east of Pond #1	5/14/90	
EM-04		Fourteen feet east of EP-12	5/15/90	
EM-05		Parking lot in front of warehouse	5/19/90	
EM-06		Parking lot in front of warehouse, 14' south of EM-5	5/20/90	
EM-07	DRY	Parking lot between engineering bldg and lab	5/19/90	
EM-08	ABANDONED	15' due east of pond #6	5/21/90	
EP-01		35' downstream of canal tunnel	2/15/90	Diesel #1
EP-02	Auger refusal, abandoned hole, 2/16/90	Approx 200' downstream of canal tunnel along rail road tracks	2/16/90	Diesel #1
EP-03		Approx 6' north of east canal tunnel	2/17/90	Diesel #1
EP-04		Approx. 30' from Rio Grande and 50' down from canal tunnel	2/1/90	Phase I
EP-05		Approx. 30' from Rio Grande and 250' down from canal tunnel	2/17/90	Phase I
EP-06		Approx. 30' from Rio Grande and 600' down from canal tunnel	2/18/90	Phase I
EP-07		Approx. 50' from Rio Grande opposite of plant entrance	2/18/90	Phase I
EP-08		Adjacent to north diesel tank	2/20/90	Diesel #1
EP-09	ABANDONED	Approx. 40' north of lunch house	2/20/90	Diesel #1
EP-10		50' East of building (diesel I recovery system)	2/20/90	Diesel #1
EP-11		Approx. 60' south of EP-10 and 150' south of lunch house	2/21/90	Diesel #1
EP-12		200' Southeast of lunchroom	2/22/90	Phase I and Diesel #1
EP-13		500' Northwest (upgradient) of lunchroom	2/23/90	Phase I and Diesel #1
EP-14		50' Northeast of lunchroom	2/24/90	Phase I
EP-15		Upgradient- between bedding, building and trestle	2/24/90	Phase I and Diesel #1
EP-16	BURIED	Near trench excavation below lunch house	2/25/90	
EP-17		Approx. 10' north of EP-1	2/25/90	Diesel #1
EP-18		Approx. 740' south of canal tunnel	2/25/90	Diesel #1
EP-19		Approx 280' south of canal tunnel	2/25/90	Diesel #1
EP-20		Approx. 1370' south of canal tunnel	2/26/90	Phase I and Diesel #1
EP-21		18' North of 18,000 gallon diesel	5/21/90	Phase I and Diesel #2
EP-22				Phase I
EP-22R		Northwest of above ground storage tank	8/6/1990 redrilled Dec 1999	Phase I
EP-23		50' South of Northeast stack	8/7/90	Phase I and Diesel #2
EP-24		Near northeast corner of Anode building	8/8/90	Phase I and Diesel #2
EP-25		Approx. 50 yards northeast of ASARCO stack	8/8/90	Phase I and Diesel #2
EP-26		South of the old Wedge Roaster	8/9/1990 redrilled 2000 ?	Phase I and Diesel #2
EP-27	ABANDONED (prior to 1995)	Approx. 150 yards north of ASARCO stack	8/9/90	
EP-28				
EP-29		Along rail road tracks at 33 + 95 ft reference points on canal wall	2/3/91	Phase I and Diesel #
EP-30		Along rail road tracks at 34 + 50 foot reference points on canal wall	1/31/91	Diesel #1

Well Name	Status	Location	Date Completed	Designation
MONITORING WELLS				
EP-31		Along rail road tracks at 35 + 20 foot reference points on canal wall	1/30/90	Diesel #1
EP-32		Along rail road tracks at 35 + 65 ft reference points on canal wall	1/31/91	Diesel #1
EP-33		Along rail road tracks at 36 + 05 foot reference points on canal wall	1/30/91	Diesel #1
EP-34		Along rail road tracks at 36 + 50 foot reference points on canal wall	2/3/91	Diesel #1
EP-35		Along rail road tracks at 37 + 42 foot referene points on canal wall	2/1/91	Phase I and Diesel #1
EP-36		Along rail road tracks at 37 + 85 foot referene points on canal wall	2/2/91	Diesel #1
EP-37		Along rail road tracks at 38 + 25 foot referene points on canal wall	2/2/91	Diesel #1
EP-38		Along rail road tracks at 38 + 68 foot referene points on canal wall	2/2/91	Diesel #1
EP-39		Along rail road tracks at 39 + 55 foot referene points on canal wall	2/1/91	Diesel #1
EP-40		Along rail road tracks at 40 + 40 foot referene points on canal wall	2/1/91	Diesel #1
EP-41				
EP-42		Along rail road tracks at 43 + 05 foot referene points on canal wall	1/31/91	Diesel #1
EP-43		Waste water tank area, 30' West and 30' South of Southwest corner of lunch house	2/4/91	Phase I and Diesel #1
EP-44		35' East of EP-43	2/6/91	Diesel #1
EP-45		81' East of EP-43, east of lunch house	2/4/91	Diesel #1
EP-46		44' East of EP-45, 63' south of compressor/treatment bldg	2/5/91	Diesel #1
EP-47		56' North of EP-43 on North side of Lunchroom	2/4/91	Diesel #1
EP-48		Along rail road tracks at 33+ 55 foot reference points on canal wall	2/5/91	Diesel #1
EP-49		Plant area near acid plant at Northwest end of plant	2/9/91	Phase I and Diesel #1
EP-50		86' East of EP-46, approx. 80' North of EP-12, east of lunchroom	2/11/91	Diesel #1
EP-51		Plant site south of stack edge of property	2/12/91	Phase I and Diesel #2
EP-52		75' Northwest of ASARCO stack (edge)	2/13/91	Phase I and Diesel #2
EP-53		In slag dump, up gradient from EP-22	2/14/91	Phase I and Diesel #2
EP-54		Northwest corner of Acid Plant	2/9/94	Phase I and Diesel #2
EP-55		200' West of EPS2	2/9/94	Phase I and Diesel #2
EP-56		South of GPS house	2/9/94	Phase I and Diesel #2
EP-57		Old Smelter Town	1/16/94	Phase I and Diesel #2
EP-58		Old Smelter Town	6/16/94	Phase I and Diesel #2
EP-59		Old Smelter Town	1/17/94	Phase I and Diesel #2
EP-60		Old Smelter Town	1/17/94	Phase I and Diesel #2
EP-61		None Given	1/18/94	Phase I and Diesel #2
EP-62		Old Smelter Town	1/25/94	Phase I and Diesel #2
EP-63		Old Smelter Town	1/26/94	Phase I and Diesel #2

Well Name	Status	Location	Date Completed	Designation
MONITORING WELLS				
EP-64		Old Smelter Town	1/25/94	Phase I and Diesel #2
EP-65		Old Smelter Town	1/27/94	Phase I and Diesel #2
EP-66		Old Smelter Town	1/27/94	Phase I and Diesel #2
EP-67		Truck Staging Area	5/28/97	Phase I
EP-68		South end of employees parking	5/29/97	Phase I
EP-69	ABANDONED	East of Scale House	5/29/97	Phase I
EP-70		Northwest of Rubber Lake	5/30/97	Phase I
EP-70R		70' West of EP-70	6/12/97	Phase I
EP-71		Central Rail Yard	5/31/97	Phase I
EP-71R		Near Gate 18	6/11/97	Phase I
EP-72		East Central Storage Yard	6/1/97	Phase I
EP-72R		East Central Storage Yard	6/1/97	Phase I
EP-73		East of Acid Plant 2	6/1/97	Phase I
EP-74	ABANDONED	Lead Works	6/2/97	Phase I
EP-75		Boneyard	6/3/97	Phase I
EP-76		Boneyard	6/3/97	Phase I
EP-77		North of Pond 5	6/4/97	Phase I
EP-78		Near Pond on Parker Bros.	6/4/97	Phase I
EP-79		Southwest of Cemetery	6/5/97	Phase I
EP-80		ASARCO Annex 2	6/6/97	Phase I
EP-81		Parker Bros. Entrance	6/6/97	Phase I
EP-82		East of Plant; West of I-10; South of Parker Brothers	6/10/97	Phase I
EP-83		200' North of # Bridge	6/11/97	Phase I
EP-84		1000' East of I-10	6/11/97	Phase I
EP-85		In Arroyo due North of Cadmium Bldg.	6/12/97	Phase I
EP-86		Slag pile North of Cemetery	6/13/97	Phase I
EP-87	ABANDONED	North Arroyo	6/16/97	Phase I
EP-88		North of Pond #6	6/17/97	Phase I
EP-89		Abandoned Guard Shack	6/18/97	Phase I
EP-90		Lead Works	12/8/97	Phase I
EP-93		East of I-10, center of Terrace	7/21/99	Phase II
EP-94		East of I-10, on west toe of Terrace	7/26/99	Phase II
EP-95		East of I-10, center of North Arroyo	10/20/99	Phase II
EP-96		East of I-10, east side of Terrace	7/20/99	Phase II
EP-97		East of I-10, center of South Arroyo, in pasture area.	8/4/99	Phase II
EP-98		East of I-10, northwest edge of South Arroyo, on slag area	8/9/99	Phase II
EP-99		Slag Pour area, north end of boneyard	5/12/99	Phase II
EP-100		10 feet south of Medford Sump	9/28/99	Phase II

Well Name	Status	Location	Date Completed	Designation
MONITORING WELLS				
EP-101		West of Sample Mill Area Unloading Building	9/30/99	Phase II
EP-102		5 ft. south of Sample Mill Area Sump	10/4/99	Phase II
EP-103		Center of overhead conveyor btwn delumper & bedding bldg.	10/5/99	Phase II
EP-104		30' E, and 50' S of southwest corner of bedding bldg	10/7/99	Phase II
EP-105		125' NW of Northeast corner of unloading bldg	10/8/99	Phase II
EP-106		30' NW of Plant Flag Pole at entrance	10/18/99	Phase II
EP-107		50' W and 250' S of Southeast corner of unloading building	10/12/99	Phase II
EP-108		Center-line of ephemeral pond, approx. 400' E of railroad tracks	10/14/99	Phase II
EP-109		South of #9 gate roadway, 200' E of railroad tracks	10/15/99	Phase II
EP-110		N side of plant entrance roadway, 30' NE of plant RR bridge spur	10/18/99	Phase II
EP-111		525' NE of Old pump house on Rio Grande flood plain	10/27/99	Phase II
EP-112		1400' NW of Old Pump house on Rio Grande flood plain	10/27/99	Phase II
EP-113		2300' NW of Old Pump house on Rio Grande flood plain	10/28/99	Phase II
EP-114		Front Slope, by RR tracks, below Acid Mist Precipitator	11/15/99	Phase II
EP-115		Front Slope, by RR tracks, below Medford Sump	11/16/99	Phase II
EP-116		Front Slope, by RR tracks, below former roasters	11/16/99	Phase II
EP-117		Front Slope, by RR tracks, below Old Baghouse	11/17/99	Phase II
EP-118		Front Slope, by RR tracks, below Sample Mill Area	11/17/99	Phase II
EP-119		NW corner of Smeltertown	4/2/01	Phase III
EP-120		Arroyo West of Ephemeral Pond	4/9/01	Phase III
EP-121		Arroyo West of Ephemeral Pond	4/12/01	Phase III
EP-122		West of Paisano, North of IBWC	4/12/01	Phase III
EP-123		North of Ephemeral Pond	4/18/01	Phase III
EP-124		Southeast of Pond 6	4/21/01	Phase III
EP-125		North of Bulk Acid Storage Area	4/24/01	Phase III
EP-126		North of Bulk Acid Storage Area	4/26/01	Phase III
EP-127		Bank of Rio Grande	4/27/01	Phase III
EP-128		North of IBWC Pump House	4/27/01	Phase III
EP-129		South Arroyo, East of I-10	5/3/01	Phase III
EP-130		Copper Plant area, close to fence	5/29/01	Phase III
EP-131		South of Converter Bldg	5/30/01	Phase III
EP-132		South corner of Smeltertown	6/4/01	Phase III

Summary of Aquifer Test Results (continued)
ASARCO EL Paso Smelter, Phase III RI

AQUIFER SLUG TEST RESULTS

Test Well	Perforated Interval/ Total Depth (ft bgs)	MP Stickup/ Elevation (ft)	Initial Static Water Level from MP (ft)	Saturated Thickness (ft)	Test Date	Test Length (min:sec)	Slug Displacement (ft ³)	Initial Displacement (ft)	Method of Analysis (1)	Hydraulic Conductivity (ft/day)
EP-12	52-72 80	1.5			1990					0.4
EP-17	15-25 30	0			1990					1.5
EP-51	40-70 70	1.2 3774.66	48.73	21	10/20/97	28:39	N/A	1.92	Slug	4.70
EP-53	55-79 79	1.2 3805.64	66.81	11	10/20/97	15:53	N/A	1.27	Slug	2.40
EP-54	60-80 80	1.6 3787.37	69.25	11	10/20/97	13:27	N/A	2.5	Slug	
EP-56	38-58 58	2 3772.09	48.92	9	10/20/97 10/20/97	8:00 4:18	N/A N/A	1.52	Slug	5.30
EP-57	10-30 30	1.6 3723.66	9.17		10/21/97	6:53	N/A	1.65	Slug	
EP-62	7-17 25	1.6 3720.64	7.62		10/21/97	4:27	N/A	1.81	Slug	
EP-65	6.4-16.4 16.4	1.6 3721.39	8.52		10/21/97	8:57	N/A	1.81	Slug	
EP-66	6.4-16.4 16.4	1.6 3722.88	10.37		10/21/97	17:59	N/A	1.34	Slug	
EP-76	45-65 65	1.8 3798.56	50.2	76	10/20/97	9:40	N/A		Slug	10.90

Notes: (1) Slug = Slug Test Method (Confined or Unconfined)

N/A = Not Available with this solution

MP = Measuring Point

ft = feet

bgs = below ground surface

Table 2-5

Statistical Summary of Water Quality Results for August 2001
ASARCO El Paso Smelter, Phase III RI

PARAMETER	UNITS	MIN	MAX	MEAN	MEDIAN	STDEV	2 STDEV
DTWL	feet	5.26	71.89	37.93	40.92	22.13	44.27
O2 (FLD)	mg/L	0.00	240.00	5.83	2.50	27.49	54.99
pH (FLD)	standard units	6.26	7.77	7.14	7.12	0.31	0.62
pH	standard units	6.60	8.20	7.79	7.90	0.32	0.63
SC	umhos/cm	1638	19140	5615	4560	3114	6229
SC (FLD)	umhos/cm	780	18240	5375	4460	3074	6148
TDS	mg/L	1054	18336	4394	3284	2933	5865
TSS	mg/L	1	12441	556	13	2068	4135
Turbidity	ntu	0.00	491.00	51.09	8.81	87.78	175.55
Temperature	deg. C	21.7	30.9	25.6	25.5	2.0	4.1
Ca	mg/L	36	796	238	167	184	368
Mg	mg/L	20	587	121	75	115	230
Na	mg/L	221	3849	937	816	564	1128
K	mg/L	5	848	53	19	111	222
HCO3	mg/L	115	2830	469	370	408	816
CO3	mg/L	1	1	1	1	0	0
SO4	mg/L	377	11157	2097	1604	1633	3267
Cl	mg/L	210	3832	584	446	552	1104
F	mg/L	0.51	8.50	2.13	1.90	1.40	2.81
NO3+NO2-N	mg/L	0.05	270.00	38.38	11.00	63.53	127.06
As (DIS)	mg/L	0.007	227.000	4.460	0.130	26.362	52.724
As (TOT)	mg/L	0.008	280.000	5.282	0.150	32.404	64.809
Cd (DIS)	mg/L	0.005	1.500	0.051	0.005	0.189	0.379
Cd (TOT)	mg/L	0.005	3.200	0.127	0.005	0.484	0.969
Cr (DIS)	mg/L	0.010	0.077	0.012	0.010	0.009	0.019
Cr (TOT)	mg/L	0.010	1.500	0.038	0.010	0.173	0.346
Cu (DIS)	mg/L	0.025	1.300	0.053	0.025	0.153	0.306
Cu (TOT)	mg/L	0.025	70.000	1.001	0.025	8.076	16.153
Fe (DIS)	mg/L	0.1	47.0	0.8	0.1	5.4	10.9
Fe (TOT)	mg/L	0.1	369.0	14.8	0.6	59.7	119.4
Pb (DIS)	mg/L	0.003	0.050	0.005	0.003	0.007	0.013
Pb (TOT)	mg/L	0.003	9.500	0.193	0.004	1.123	2.246
Se (DIS)	mg/L	0.005	16.000	0.682	0.160	2.084	4.167
Se (TOT)	mg/L	0.005	15.000	0.672	0.140	1.974	3.949
Zn (DIS)	mg/L	0.020	6.900	0.223	0.028	0.882	1.764
Zn (TOT)	mg/L	0.020	76.000	1.355	0.040	8.910	17.819

Notes: DTWL = Depth to Water Level
DIS = Dissolved Metals Analysis, TOT = Total Metals Analysis

Table 2-6

IBWC Rio Grande Water Quality Data
February 2000 Through June 2001 At Courchesne Bridge
ASARCO El Paso Smelter, Phase III RI

DATE	D.O.	pH	BOD	FECAL COLIFORM	CHLORIDE	TDS	SULFATE	SC (mS/cm)	TOTAL HARDNESS	AMMONIA	TURBIDITY (NTUs)	TEMP (F)
02/03/00	10.2	7.7	2	980	248	916	388	1860	390	0.71	19.8	42
02/10/00	8.8	7.8	5	1560	278	NR	441	2210	420	0.15	19.5	49
02/17/00	7.4	7.7	3	1320	301	NR	478	2290	NR	0.38	16.9	55
02/23/00	8.8	8.2	8	480	155	840	252	1360	NR	0.14	31.7	50
03/02/00	8.6	8.1	9	350	115	660	199	1723	250	0.11	166	50
03/09/00	9.7	7.5	11	380	NR	452		1023	220	0.24	89.9	49
03/16/00	8.5	7.9	8	480	85.21	308	155	907	220	0.19	97.1	56
03/23/00	9	7.9	8	1740	86	178	162	1038	178	0.23	112	54
03/30/00	9.3	8	10	720	101	620	197	1090	240	0.182	72.3	58
04/05/00	7.14	8.11	11	450	119	686	227	1282	260	0.24	63.7	60
04/13/00	7.52	8.02	11	1960	109	640	214	1150	260	0.141	54.5	62
04/20/00	9.6	7.8	15	2720	108	690	208	1187	NR	0.139	49.7	58
04/27/00	7.4	7.7	20	3160	120	772	221	1224	260	0.21	44.6	69
05/04/00	8.4	7.7	16	2120	144.8	886	258	1212	280	0.3	49.1	67
05/10/00	7.3	8.3	9	1630	111	676	216	1152	240	0.32	43.1	70
05/18/00	8	8.2	7	2870	91	684	213	1217	250	1.16	58.6	63
05/25/00	5.7	8.1	10	300	82	536	196	1123	250	0.14	70.4	73
06/01/00	6.95	7.92	7	1380	99.5	630	206	1113	260	0.1	64.3	72
06/08/00	6.6	8.3	8	380	101	1532	206	1100	260	0.08	106	74
06/15/00	7.7	8.1	12	760	99.7	640	212	1096	250	0.083	67.9	73
06/22/00	6.02	8.31	6	NR	96.9		208	1066	240	0.0293	NR	77
06/29/00	5.5	8.11	7	2000	79		183	919	198.8	0.2	NR	76
07/06/00	6.4	8.2	4	200	88	610	191	912	230	0.07	180	80
07/13/00	6	8.4	3	0	84	572	179	1022	220	0.03	112	79
07/20/00	6.4	8.5	4	800	89	724	192	1020	230	0.06	94	78
07/27/00	6.3	8.8	5	3000	88	658	176	1045	230	0.08	121	69
08/03/00	6.4	8.5	4	300	NR	580	NR	1020	NR	0.059	89	78
08/10/00	6.6	8.36	4	1000	NR	700	NR	1091	240	0.086	90	77
08/17/00	NR	NR	NR	NR	NR		NR	NR	NR	NR	NR	NR
08/24/00	7.2	8.76	4	3700	99.18	746	209.76	1171	NR	0.0532	80.1	73
08/31/00	7.12	8.34	4	100	91.15	578	184.97	1091	240	0.107	161	74
09/07/00	6.42	8.44	5	400	101.71	714	219.47	1162	NR	0.0734	NR	74
09/14/00	6.61	8.5	3	1200	NR	760	NR	NR	NR	NR	NR	NR
09/21/00	NR	NR	4	1400	121.13	760	268.27	550	300	0.225	56.8	NR
09/28/00	7.5	8.48		900	NR	778	NR	1257	270	0.123	NR	68
10/05/00	8.46	8.3	6	300	127	808	267	1463	330	0.114	62.8	68
10/12/00	7.87	8.1	6	2400	113	NR	238	1308	300	0.0185	25.3	62
10/19/00	8.2	8	2	19000	NR	NR	NR	1540	NR	0.0556	NR	62
10/26/00	8.61	8	8	2600	NR	NR	NR	1385	NR	0.0715	NR	58
11/02/00	NR	NR	6	1100	177	1150	375	NR	460	0.14	58.7	NR

Table 2-6

IBWC Rio Grande Water Quality Data
February 2000 Through June 2001 At Courchesne Bridge
ASARCO El Paso Smelter, Phase III RI

DATE	D.O.	pH	BOD	FECAL COLIFORM	CHLORIDE	TDS	SULFATE	SC (mS/cm)	TOTAL HARDNESS	TURBIDITY AMMONIA	(NTUs)	TEMP (F)
11/09/00	10.7	8.2	4	400	NR	928	NR	1690	NR	NR	66.6	44
11/16/00	10.6	8.2	2	400	NR	1152	NR	2020	390	0.455	31.1	66
11/30/00	10.1	8.2	3	800	NR	1178	NR	1078	NR	0.417	8.94	47
12/07/00	13.8	7.9	2	2000	196	1184	412	2050	400	0.238	8.48	43
12/14/00	6.5	7.8	5	NR	293	1260	341	3042	400	0.273	26.2	56
12/28/00	11.5	8.4	3	300	218	1176	428	1901	380	0.392	12.3	NR
01/04/01	9.2	7.8	3	1300	224	1220	445	2030	410	0.421	15.6	49.8
01/11/01	10.8	7.2	3	9700	238	1270	430	2140	380	0.567	15.5	43.7
01/18/01	11.6	7.3	3	430	256	1280	446	2120	380	0.561	13.6	38.8
01/25/01	11.2	7.6	4	1200	252	1164	442	2180	390	0.49	21.8	43.0
02/01/01	8.9	7.5	10	69600	259	1234	426	2120	360	4.94	42.8	46.0
02/08/01	8.5	7.9	4	1300	164	888	242	1435	240	0.988	140	50.9
02/15/01	9.4	7.7	4	340	192	942	307	1620	310	0.209	68.7	47.0
02/22/01	8.8	7.5	4	7900	158	950	248	1570	300	0.232	51.8	50.1
03/01/01	8.9	7.7	4	510	126	746	199	1236	210	0.0353	326	50.0
03/08/01	8.8	7.9	4	310	91	664	167	1123	230	0.14	240	51.7
03/15/01	9.3	7.9	4	200	89	560	171	930	210	0.11	176	52.7
03/22/01	8.7	8.1	4	380	88	498	174	944	210	0.0902	135	58.1
03/29/01	8.6	8.1	3	1400	93	610	199	1008	220	0.84	82	55.7
04/05/01	7.3	7.8	2	1300	110	708	221	1139	250	0.09	65.6	64.0
04/12/01	#	7.9	2	700	106	722	217	1073	250	0.07	67.7	54.0
04/19/01	7.0	7.9	3	1900	122	632	249	1147	280	0.10	61.3	64.6
04/26/01	7.9	8.1	1	200	111	630	211	1104	230	0.07	63.0	60.6
05/03/01	7.9	8.1	3	630	125	594	258	1266	270	0.07	49.8	62.3
05/10/01	7.2	8.1	2	650	112	688	237	1172	260	0.09	81.8	68.6
05/17/01	7.1	8.1	2	1900	105	704	224	1116	260	0.16	53.6	68.8
05/24/01	6.9	8.04	2	800	107	658	228	1092	260	0.30	75.7	70.8
06/07/01	6.8	8.1	1	1100	93	630	196	1040	240	0.14	58.4	72.8
06/14/01	6.6	8.2	1	500	89	678	193	1017	264	0.06	55.2	70.3
06/21/01	6.9	8.2	2	700	85	690	183	994	220	0.06	61.4	74.7
06/28/01	6.1	8.2	4	6500	98	616	204	1083	250	0.06	97.6	77.2
AVERAGE	8.1	8.0	5	2669	135	783	254	1336	278	0.29	74.6	61.5
MEDIAN	7.9	8.1	4	940	110	700	217	1151	260	0.14	63.0	62.2
STD	1.6	0.3	3.8	8674	61	258	90	446	67	0.61	56.3	11.3
MAXIMUM	13.8	8.8	20	69600	301	1532	478	3042	460	4.94	326.0	79.5
MINIMUM	5.5	7.2	1.0	0.0	79.0	178.0	155.0	550.0	178.0	0.0	8.5	38.8

Notes:

NR: Not Reported.

All concentrations in milligrams per liter (mg/l) unless otherwise indicated.

Fecal Coliform reported in cfu/100 ml units.

Courchesne Bridge is located 9.5 Miles above Haskell R. Street Wastewater Treatment Plant.

See Figure 3-32 for sample locations.

Table 2-7

IBWC Rio Grande Water Quality
February 2000 Through June 2001, Across From Bowie High School Football Field
ASARCO El Paso Smelter, Phase III RI

DATE	D.O.	pH	BOD	FECAL COLIFORM	CHLORIDE	TDS	SULFATE	SC (mS/cm)	TOTAL HARDNESS	AMMONIA	TURBIDITY (NTUs)	TEMP (F)
02/03/00	10.1	8	4	2120	271	902	421	1964	370	0.96	12.1	40
02/10/00	10.8	8.2	5	1780	341	1368	528	2550	422	0.08	8.2	47
02/17/00	9.2	8.5	2	70	360	1620	549	2540	NR	0.25	10.4	54
02/23/00	10.5	8.6	9	380	275	1364	473	2150	NR	0.12	8.12	50
03/02/00	9.4	8.3	9	200	182	912	299	1663	280	0.22	10.8	49
03/09/00	11.5	8	11	690	NR	NR	750	1484	260	0.57	10.4	50
03/16/00	10.5	8.1	8	100	113.29	464	228	1226	260	0.51	20.1	54
03/23/00	10	8.2	9	90	94	206	161	1274	206	0.133	19.7	54
03/30/00	10.1		12	38	105	522	188	1110	230	0.324	12.1	58
04/05/00	7.49	8.1	15	580	110	688	198.2	1161	230	0.13	11.7	55
04/13/00	7.93	7.95	11	320	113	610	205	1168	250	0.096	8.95	58
04/20/00	10.8	7.9	14	370	112	662	202	1163		0.174	9.3	53
04/27/00	7.5	7.9	16	460	118	756	203	1170	250	0.15	6.87	67
05/04/00	8.4	7.9	16	1480	174	822	268	1408	260	0.16	6.53	60
05/10/00	8.5	8.3	6	100	175	1004	268	1257	280	0.09	5.4	71
05/18/00	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
05/25/00	7.6	8.2	10	1140	89	510	194	1143	250	0.06	10.3	62
06/01/00	8.44	8.27	5	890	94.4	584	192	1024	240	0.1	16.8	69
06/08/00	9	8.4	8	720	97	1742	185	1027	230	0.06	6.87	72
06/15/00	11.9	8.7	11	1700	103	580	199	1031	220	0.04	19.2	73
06/22/00	11.4	8.7	6	NR	NR	NR	NR	1020	220	0.141	NR	75
06/29/00	6.39	8.3	8	2000	69.6		166	856	191.5	0.05	NR	76
07/06/00	9.9	8.7	6	100000	96	416	195	1070	230	0.211	101	77
07/13/00	12.5	8.8	6	26800	103	602	194	1096	210	0.14	82	77
07/20/00	7	8.7	10	19200	113	654	202	1130	240	0.03	13.8	68
07/27/00	5.5	8.5	14	7000	83	608	166	964	210	0.06	76.2	73
08/03/00	8.6	8.6	5	600	NR	544	NR	1009		0.056	35.5	74
08/10/00	7.6	8.51	6	300000	NR	592	NR	965	220	0.167	34.9	80
08/17/00	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
08/24/00	8.9	8.7	6	800	93.46	662	189.1	1076		0.054	39.9	71
08/31/00	7.6	8.54	6	100	82.11	514	168.99	1007	240	0.0655	232	72
09/07/00	7.77	8.6	4	1100	93	702	198.99	1077	NR	0.0513	NR	73
09/14/00	8.57	8.51	3	1600	NR	828	NR	NR	NR	NR	NR	NR
09/21/00			4	4900	134.35	818	NR	610	310	0.317	40.6	NR
09/28/00	8.07	8.41	NR	220	NR	1020	NR	1500	320	0.262	NR	67
10/05/00	8.16	8.3	6	93000	145	956	297	1560	320	0.267	40.8	67
10/12/00	8.44	8.3	3	1600	113	NR	231	1285	290	0.0797	26.2	63
10/19/00	8.33	8.2	2	5700	NR	NR	NR	1600	NR	0.064	NR	63
10/26/00	8.68	8.2	9	2400	NR	NR	NR	1335	NR	0.0758	NR	59

Table 2-7

IBWC Rio Grande Water Quality
February 2000 Through June 2001, Across From Bowie High School Football Field
ASARCO El Paso Smelter, Phase III RI

				FECAL				SC	TOTAL		TURBIDITY	
DATE	D.O.	pH	BOD	COLIFORM	CHLORIDE	TDS	SULFATE	(mS/cm)	HARDNESS	AMMONIA	(NTUs)	TEMP (F)
11/02/00	9.2	8.4	6	200	180	1150	373	1900	440	0.18	39.2	53
11/09/00	11	8.3	2	500	NR	1020	NR	1710	NR	NR	39.7	46
11/16/00	11	8.4	2	600	NR	1264	NR	2110	390	0.395	18.4	65
11/30/00	10.9	8.2	5	10	NR	1282	NR	2117	NR	0.489	7.08	48
12/07/00	11.9	8.3	2	200	202	1128	428	2030	380	0.649	21.5	47
12/14/00	10.2	8.4	3	850	232	1248	422	1808	375	0.297	52.4	45
12/28/00	12.2	8.4	3	50	232	1234	437	1971	430	0.367	27	43
01/04/01	10.9	8.0	2	2900	246	1258	450	2170	380	0.457	18.3	38
01/11/01	11.2	7.2	7	2000	249	1262	442	2160	370	0.515	12.6	43
01/18/01	12.2	7.8	3	120	274	1270	460	2190	380	0.0499	12.2	40
01/25/01	11.0	7.6	4	8900	260	1210	437	2160	380	0.42	34.5	45
02/01/01	11.7	7.7	12	11300	272	1338	451	2230	380	0.547	9.22	40
02/08/01	9.5	7.8	5	1160	142	762	207	1302	220	0.364	39.3	50
02/15/01	11.6	7.9	3	190	165	850	269	1470	290	0.341	25.4	44
02/22/01	10.3	8.0	3	80	155	876	242	1530	300	0.357	22.7	48
03/01/01	11.3	8.0	3	270	136	792	216	1318	230	0.465	40.3	48
03/08/01	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	32
03/15/01	11.6	8.2	3	300	114	680	217	1115	240	0.33	48.3	47
3/22/01	10.4	8.4	3	220	88	488	163	918	210	0.0615	45.9	57
3/29/01	10.2	8.2	2	500	98	620	197	1030	230	0.63	27	56
04/05/01	7.4	8.2	2	700	110	620	221	1075	240	0.03	17.5	61
04/12/01	#	8.0	2	900	108	734	222	1113	250	0.07	17.9	52
04/19/01	7.8	8.0	2	700	139	698	305	1260	260	0.08	12.9	63
04/26/01	9.2	8.2	1	100	112	624	201	1106	240	0.03	10.2	60
05/03/01	8.9	8.1	2	800	133	634	261	1308	290	0.06	15	60
05/10/01	9.2	8.2	2	420	134	718	257	1284	280	0.05	7.08	68
05/17/01	8.5	8.2	2	2600	114	650	220	1117	240	0.23	12.7	61
05/24/01	9.7	8.3	1	1000	117	704	232	1027	250	0.16	6.54	67
06/07/01	9.8	8.3	1	500	94	696	196	1011	240	0.06	12.7	69
06/14/01	8.7	8.1	3	100	96	630	190	1032	241	0.03	8.6	64
06/21/01	10.1	8.3	2	3500	90	666	182	1007	230	0.02	17	73
06/28/01	7.4	8.4	6	2000	83	366	174	958	224	0.05	42.7	80
AVERAGE	9.5	8.2	5.7	9312.2	147.9	833.9	277.0	1391.2	278.1	0.21	27.2	58.8
MEDIAN	9.5	8.2	5.0	700.0	114.2	711.0	219.7	1226.0	250.0	0.1	17.5	59.5
STD	1.6	0.3	4.0	39755.8	70.1	321.0	125.2	456.1	66.0	0.2	32.9	12.0
MAXIMUM	12.5	8.8	16.0	300000	360.0	1742.0	750.0	2550.0	440.0	0.96	232.0	80.0
MINIMUM	5.5	7.2	1.0	10.0	69.6	206.0	161.0	610.0	191.5	0.02	5.4	32.0

Notes:

NR: Not Reported.

All concentrations in milligrams per liter (mg/l) unless otherwise indicated.

Fecal Coliform reported in cfu/100 ml units.

ie High School Football Field is located 1.5 Miles above Haskell R. Street Wastewater Treatment Plant.

See Figure 3.3-1 for sample locations.

Table 2-8

**IBWC Average Concentrations of Rio Grande Surface Water Quality Data
February 2001 Through June 2001
ASARCO El Paso Smelter, Phase III RI**

Parameter	Courchesne Bridge	Bowie High School
D.O.	8.10	9.50
pH	8.00	8.20
BOD	5.00	5.70
Fecal Coliform (cfu/100 ml)	2669.00	9312.00
Chloride	135.00	147.90
TDS	783.00	833.90
Sulfate	254.00	277.00
SC (mS/cm)	1336.00	1391.00
Total Hardness	278.00	278.00
Ammonia	0.29	0.21
Turbidity (NTUs)	74.60	27.20
Temperature (°F)	61.50	58.80

Notes:

See Figure 3-32 for sample locations.

All concentrations in milligrams per liter (mg/l) unless otherwise indicated.

Average concentrations derived from weekly sampling efforts.

**Hydrometrics Surface Water Quality Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI**

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb. NTU	Temp (F)	Ca mg/l	Mg mg/l	Na mg/l	K mg/l	HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
Rio Grande																		
SEP-2	2/14/00	10.2	8.5	2330	1551	24	13	72.5	119	31	315	13	275	12	593	297	0.85	1.3
SEP-2	5/10/00	5.2	8.3	1086	694	74	24.2	80.2	77	17	131	9.5	220	1	211	103	0.72	0.33
SEP-2	8/21/00	5.4	8.3	931	609	426	17.8	52.9	75	19	91	8.4	272	1	184	87	0.69	0.69
SEP-2	11/15/00	10.4	7.9	2070	1363	50	17.8	53.4	107	26	261	11	342	1	443	210	0.82	1.3
SEP-2	2/28/01	10	8	1179	739	116	64	73.0	72	17	142	8.5	232	1	244	136	0.72	0.59
SEP-2	5/17/01	9	8.3	1090	697	116	27	73.2	71	17	135	9.9	207	1	239	130	0.74	0.47
SEP-2	5/17/01	9	8.4	1090	691	107	27	80.4	71	17	130	9.1	212	2.4	240	116	0.73	0.52
SEP-2	7/31/01	7.5	8.1	988	624	254	210	32.0	57	15	119	7.9	270	1	191	92	0.69	0.16
SEP-4	2/14/00	10.9	8.4	2440	1574	61	15	67.1	112	32	334	13	270	7.2	501	315	0.88	1.7
SEP-4	5/10/00	6.4	8.3	1122	519	58	28	80.1	78	18	146	9.7	227	1	223	113	0.72	0.24
SEP-4	8/21/00	5.6	8.3	938	617	437	18	50.4	85	21	101	11	271	1	181	83	0.64	0.6
SEP-4	11/15/00	9.6	8.2	2160	1448	55	40	50.5	113	28	287	11	320	1	492	247	0.81	1.3
SEP-4	2/28/01	9.3	7.9	1226	777	95	56.8	66.0	63	16	132	7.3	220	1	243	141	0.76	0.67
SEP-4	5/17/01	8	8.3	1106	705	80	29.3	88.3	71	17	136	9.9	220	1	245	116	0.75	0.54
SEP-4	7/31/01	10.1	8.1	1047	652	176	114	32.0	61	16	128	7.5	220	1	217	110	0.72	0.15
SEP-6	1/31/00	7.2	8.2	1412	861	62	27	79.9	88	21	193	8.4	228	1	242	192	0.7	1.4
SEP-6	5/9/00	6.2	8.3	1122	703	108	25	78.3	80	18	146	9.8	226	1	210	98	0.72	0.59
SEP-6	5/9/00	6.3	8.3	1124	700	104		82.2	78	18	140	9.1	228	1	218	118	0.72	0.63
SEP-6	8/14/00	5.5	8.6	987	630	274	25	51.8	65	15	93	8.2	223	11	188	73	0.68	0.63
SEP-6	11/10/00	7.9	8.2	1880	1275	296	29	60.8	106	27	221	10	334	1	360	204	0.7	2.2
SEP-6	2/23/01	7.6	8.4	1338	824	93	40	61.5	72	16	155	8.4	234	4.8	236	158	0.74	1.2
SEP-6	2/23/01	7.8	8.4	1333	837	94		71.8	73	16	155	8.4	234	2.4	245	160	0.72	1.2
SEP-6	5/16/01	8.3	8.2	1000	638	191	56	80.4	71	17	125	9.9	207	1	218	108	0.67	0.64
SEP-6	8/1/01	7.7	8.2	1045	663	182	127	77.9	64	16	124	9.5	214	1	212	105	0.68	0.55
SEP-9	2/14/00	6.1	8.3	2120	1341	36	15	70.9	100	23	285	12	246	1	341	185	0.81	2.7
SEP-9	5/10/00	5.5	8	1446	918	58	19.8	83.1	74	16	224	10	220	1	237	190	0.79	3.5
SEP-9	8/21/00	5.4	8.2	1264	803	248	17	59.5	67	15	155	8.1	227	1	236	145	0.75	3.8

Table 2-9

Hydrometrics Surface Water Quality Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb. NTU	Temp (F)	Ca mg/l	Mg mg/l	Na mg/l	K mg/l	HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
SEP-9	11/15/00	7.2	7.9	1960	1275	29	11.8	54.0	87	19	268	9.8	259	1	348	245	0.8	3.4
SEP-9	2/28/01	8.4	7.9	1375	882	152	60.5	77.9	72	16	195	9.4	207	1	276	173	0.75	3.4
SEP-9	5/17/01	8.5	8.1	1400	901	78	28.6	88.7	71	17	203	12	217	1	290	206	0.81	3.2
SEP-9	7/31/01	8.7	8.2	1143	750	158	84.5	32.0	69	17	145	8.6	215	1	245	110	0.72	0.85
SEP-10	2/14/00	9.1	8.5	2210	1458	35	13	74.7	108	26	294	13	255	14.4	382	290	0.87	1.6
SEP-10	5/10/00	5.9	8.3	1076	685	75	21.3	74.8	77	17	135	9.7	220	1	215	94	0.72	6.1
SEP-10	5/10/00	6	8.5	1072	678	78		79.9	78	17	138	9.5	206	7	277	104	0.72	0.18
SEP-10	8/21/00	5.4	8.5	927	588	406	16.5	55.9	75	18	94	8.7	226	10	172	78	0.66	0.61
SEP-10	11/15/00	11.5	8	2000	1326	32	16.1	53.2	103	25	257	11	310	1	423	237	0.86	1.3
SEP-10	2/28/01	7.4	8.2	1074	675	154	86	72.9	64	14	107	7.3	233	1	201	117	0.71	0.49
SEP-10	5/17/01	9.9	8.4	1094	713	81	32	82.9	70	17	133	9.1	215	3.6	244	133	0.75	0.45
SEP-10	7/31/01	8.3	8	1000	657	228	133	32.0	61	15	119	9.7	209	1	193	101	0.7	0.15
SEP-11	2/14/00	9.5	8.6	2300	1517	17	16	75.4	112	29	315	14	246	13.8	344	310	0.86	1.6
SEP-11	5/10/00	6.2	8.3	1083	687	79	28.5	80.4	79	18	137	10	218	1	217	98	0.72	0.32
SEP-11	8/21/00	5.8	8.3	929	583	401	17	54.9	69	17	89	8.2	250	1	186	83	0.65	0.58
SEP-11	11/15/00	10.7	8	2060	1359	30	17.3	54.9	104	26	267	11	311	1	450	251	0.8	1.5
SEP-11	11/15/00	10.9	8	2060	1371	32		54.0	105	25	261	11	312	1	395	243	0.82	1.6
SEP-11	2/28/01	7.7	8.1	1141	739	131	74.9	72.3	70	16	129	8.2	235	1	230	130	0.72	0.56
SEP-11	5/17/01	7.5	8.4	1083	690	107	29	82.8	72	17	134	9.3	223	3.6	215	126	0.73	0.6
SEP-11	7/31/01	8	7.9	1003	654	213	139	32.0	60	15	119	8.4	195	1	221	99	0.68	0.15
SEP-12	2/14/00	9.6	8.5	2330	1525	22	16	72.0	113	30	315	13	283	12	598	299	0.9	1.5
SEP-12	5/10/00	5.7	8.2	1092	688	64	33.3	80.1	76	17	133	9.3	220	1	223	108	0.71	0.27
SEP-12	8/21/00	5.4	8.4	930	594	418	17	51.6	77	19	95	9.3	266	4.8	190	85	0.66	0.69
SEP-12	11/15/00	10.2	8.3	2060	1367	29	42	52.0	103	25	257	10	314	1	456	245	0.79	1.6
SEP-12	2/28/01	10.1	8.1	1180	744	95	57	70.0	67	16	134	8.1	220	1	237	127	0.74	0.57
SEP-12	5/17/01	8.7	8.3	1090	697	92	32	78.6	73	18	136	9.8	215	1	208	111	0.75	0.49
SEP-12	8/1/01	7.4	8.2	1027	661	170	167	32.0	65	16	120	11	205	1	214	100	0.69	0.4

Tab. 2-9

**Hydrometrics Surface Water Quality Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI**

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb. NTU	Temp (F)	Ca mg/l	Mg mg/l	Na mg/l	K mg/l	HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
SEP-13	2/14/00	8.4	8.5	2330	1554	17	13.2	52.9	117	31	316	14	277	9.6	575	291	0.86	1.5
SEP-13	2/14/00	8.3	8.5	2320	1534	17		71.4	113	31	319	14	264	14.4	484	291	0.86	1.5
SEP-13	5/10/00	5.9	8.5	1100	684	62	27.4	84.6	78	18	142	9.4	220	4.8	211	103	0.72	0.23
SEP-13	8/21/00	6	8.3	931	602	427	17.6	79.7	78	18	94	9.3	255	1	172	81	0.65	0.69
SEP-13	8/21/00	6	8.3	931	607	428		51.8	74	18	94	9.3	265	1	178	82	0.65	0.71
SEP-13	11/15/00	10.5	8.3	2100	1420	52	38	52.2	106	27	270	10	317	1	454	259	0.82	1.6
SEP-13	2/28/01	10.4	8	1201	753	90	51.2	52.2	62	15	129	7.4	207	1	256	140	0.75	0.53
SEP-13	2/28/01	10.6	8	1201	735	90		65.8	63	15	125	7.4	221	1	217	142	0.71	0.69
SEP-13	5/17/01	8	8.4	1059	704	66	28.3	79.3	70	17	135	9.1	211	2.4	244	131	0.75	0.64
SEP-13	8/1/01	7.4	8.3	1030	687	180	130	32.0	64	16	120	11	217	1	220	97	0.71	0.36
AVERAGE		7.96	8.247	1387.75	893.7	136	45.223	64.9034	80.86	19.578	173.1	9.81	242.781	2.9094	282.05	155.5	0.745	1.1283
MEDIAN		7.95	8.3	1123	709	92.5	28.3	71.15	74.5	17	136.5	9.5	227	1	237	128.5	0.72	0.655
STD		1.8	0.188	489.117	335.3	120	43.117	16.3016	17.56	5.0295	73.58	1.69	36.5085	3.8292	112.36	71.3	0.064	1.0912
MAXIMUM		11.5	8.6	2440	1574	437	210	88.7	119	32	334	14	342	14.4	598	315	0.9	6.1
MINIMUM		5.2	7.9	927	519	17	11.8	32	57	14	89	7.3	195	1	172	73	0.64	0.15
American Canal																		
SEP-1	1/31/00	7.1	8.3	1402	841	67	29.6	78.3	85	19	191	7.3	244	1	232	167	0.74	1.1
SEP-1	5/9/00	6.3	8.3	1120	723	107	25	83.8	85	18	171	10	224	1	227	102	0.73	0.47
SEP-1	8/14/00	5.6	8.6	984	611	278	26	83.8	67	16	103	9.1	222	11	213	80	0.66	0.66
SEP-1	8/14/00	5.7	8.6	987	626	275		51.4	68	16	99	8.5	224	11	207	73	0.68	0.51
SEP-1	11/10/00	8.1	8.2	1728	1177	307	27	61.0	106	26	211	11	338	1	310	206	0.68	1.8
SEP-1	2/23/01	8.4	8.4	1299	805	86	40	71.6	66	15	128	7.2	244	4.8	199	143	0.75	0.8
SEP-1	5/16/01	9.5	8.3	946	606	265	52.1	88.2	68	16	116	9.1	207	1	207	90	0.7	0.53
SEP-1	7/31/01	9	8.2	1046	674	153	98.8	89.2	60	15	125	7.5	206	1	217	105	0.7	0.34
SEP-1	7/31/01	8.9	8.3	1045	664	155	98.1	83.1	61	16	130	8.3	215	1	210	100	0.71	0.32
SEP-3	1/31/00	7.5	8.3	1400	853	64	29.6	79.0	91	21	193	8.6	240	1	235	160	0.71	1.3
SEP-3	5/9/00	6.4	8.3	1123	722	103	25	83.7	85	18	168	9.5	226	1	225	115	0.73	0.67

Table 2-9

Hydrometrics Surface Water Quality Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb. NTU	Temp (F)	Ca mg/l	Mg mg/l	Na mg/l	K mg/l	HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
SEP-3	8/14/00	6	8.6	987	634	280	25	51.6	71	16	103	9.3	221	11	208	76	0.68	0.57
SEP-3	11/10/00	8.1	8.2	1784	1208	294	28	63.5	113	29	225	11	342	1	335	222	0.7	2.2
SEP-3	2/23/01	7.3	8.5	1339	830	98	40	71.4	73	16	158	8.6	224	7	245	168	0.74	1.2
SEP-3	5/16/01	8.6	8.3	1001	638	228	51	81.3	67	16	124	9.7	211	1	226	106	0.69	0.53
SEP-3	8/1/01	7.9	8.2	1046	673	194	157	80.6	63	16	124	10	220	1	194	106	0.68	0.56
SEP-3	8/1/01	7.9	8.2	1046	680	187	152	75.9	64	16	125	11	214	1	212	104	0.7	0.56
SEP-7	1/31/00	7.7	8.3	1402	849	67	25.8	77.4	88	19	190	7.6	239	1	248	185	0.73	1.3
SEP-7	5/9/00	7.4	8.4	1108	697	106	25	83.8	86	19	162	9.6	215	7	226	109	0.71	0.41
SEP-7	8/14/00	5.7	8.6	956	603	286	24	51.6	72	17	100	9.1	229	4.8	187	78	0.69	0.53
SEP-7	11/10/00	8.1	8.2	1771	1202	311	28	61.7	114	27	218	12	342	1	292	205	0.68	1.7
SEP-7	2/23/01	7.3	8.4	1338	835	88	40	70.2	74	17	161	8.5	237	4.8	225	163	0.77	1.2
SEP-7	5/16/01	8.7	8.2	996	629	214	54	70.2	69	16	126	10	210	1	231	117	0.71	0.59
SEP-7	5/16/01	8.2	8.3	1000	637	223	49	91.6	68	16	123	9.7	203	1	235	103	0.69	0.62
SEP-7	7/31/01	9.1	8.2	1045	660	166	101	78.8	61	16	128	7.7	207	1	199	103	0.67	0.21
AVERAGE		7.7	8.339	1190.304	761.4	193	54.382	73.94	76.3	18.043	145.2	9.24	236.348	3.3217	229.83	126.8	0.703	0.8309
MEDIAN		7.9	8.3	1046	674	194	40	77.36	69	16	128	9.1	222	1	225	106	0.7	0.59
STD		1.15	0.147	268.7465	190.3	84.9	40.635	12.1646	16.29	3.9598	39.02	1.24	42.8609	3.6391	36.768	45.16	0.027	0.5263
MAXIMUM		9.5	8.6	1784	1208	311	157	91.58	114	29	225	12	342	11	335	222	0.77	2.2
MINIMUM		5.6	8.2	946	603	64	24	51.44	60	15	99	7.2	203	1	187	73	0.66	0.21

Hydrometrics Surface Water Metal Concentration Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Cr Dis mg/l	Cr T mg/l	Cu Dis mg/l	Cu T mg/l	Fe Dis mg/l	Fe T mg/l	Pb Dis mg/l	Pb T mg/l	Se Dis mg/l	Se T mg/l	Zn Dis mg/l	Zn T mg/l
Rio Grande																	
SEP-2	02/14/00		0.013		0.005 U		0.01 U		0.025 U		0.48 J4		0.003 U		0.005		0.02 U
SEP-2	05/10/00		0.007		0.005 U		0.01 U		0.025 U		1.2		0.007		0.005 U		0.028 UJ1,J2
SEP-2	08/21/00		0.005		0.005 U		0.01 U		0.025 U		9		0.019		0.005 U		0.05 UJ1
SEP-2	11/15/00		0.014		0.005 U		0.01 U		0.025 U		1.4		0.004		0.006		0.043
SEP-2	02/28/01		0.007		0.005 U		0.01 U		0.025 U		2.8		0.003		0.005 U		0.023
SEP-2	05/17/01		0.005		0.005 U		0.01 U		0.025 U		2.1		0.003 U		0.005 U		0.026
SEP-2	05/17/01		0.005		0.005 U		0.01 U		0.025 U		2.1		0.003		0.005 U		0.02 U
SEP-2	7/31/01	0.005	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3.9	0.003 U	0.009	0.005 U	0.005 U	0.02 U, UJ4	0.024 J4		
SEP-4	02/14/00		0.016		0.005 U		0.01 U		0.025 U		0.34 J4		0.003 U		0.006		0.02 U
SEP-4	05/10/00		0.008		0.005 U		0.01 U		0.025 U		1.1		0.003 U		0.005 U		0.02 U
SEP-4	08/21/00		0.005 U		0.005 U		0.013		0.025 U		12		0.009		0.005 U		0.046 UJ1
SEP-4	11/15/00		0.019		0.005 U		0.01 U		0.025 U		1.5		0.008		0.005		0.045
SEP-4	02/28/01		0.008		0.005 U		0.01 U		0.025 U		2.2		0.003 U		0.005 U		0.02 U
SEP-4	05/17/01		0.005		0.005 U		0.01 U		0.025 U		1.8		0.003 U		0.005 U		0.02 U
SEP-4	7/31/01	0.006	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	2.1	0.003 U	0.005	0.005 U	0.005 U	0.02 U, UJ4	0.02 U, UJ4		
SEP-6	01/31/00		0.005 U		0.005 U		0.01 U		0.025 U		1.2		0.005		0.005 U		0.02 U
SEP-6	05/09/00		0.007		0.005 U		0.01 U		0.025 U		2		0.004		0.005 U		0.027 UJ1,J2
SEP-6	05/09/00		0.007		0.005 U		0.01 U		0.025 U		1.9		0.003 U		0.005 U		0.022 UJ1,J2
SEP-6	08/14/00		0.005 U		0.005 U		0.01 U		0.025 U		5.8		0.006		0.005 U		0.026
SEP-6	11/10/00		0.005 U		0.005 U		0.01 U		0.025 U		7		0.005		0.005 U		0.03
SEP-6	02/23/01		0.005 U		0.005 U		0.01 U		0.025 U		1.7		0.003 U		0.005 U		0.041 UJ1
SEP-6	02/23/01		0.005 U		0.005 U		0.01 U		0.025 U		1.9		0.003 J1		0.005 U		0.035 UJ1
SEP-6	05/16/01		0.005 U		0.005 U		0.01 U		0.025 U		2.7 J4		0.003 U		0.005 U		0.02 U
SEP-6	8/1/01	0.005	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3.2	0.003 U	0.004	0.005 U	0.005 U	0.02 U	0.024		
SEP-9	02/14/00		0.008		0.005 U		0.01 U		0.025 U		0.66 J4		0.003 U		0.005 U		0.023
SEP-9	05/10/00		0.011		0.005 U		0.01 U		0.025 U		0.92		0.026		0.005 U		0.036 UJ1,J2
SEP-9	08/21/00		0.007		0.005 U		0.01 U		0.025 U		4.6		0.007		0.005 U		0.046 UJ1

Tab. 10

Hydrometrics Surface Water Metal Concentration Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Cr Dis mg/l	Cr T mg/l	Cu Dis mg/l	Cu T mg/l	Fe Dis mg/l	Fe T mg/l	Pb Dis mg/l	Pb T mg/l	Se Dis mg/l	Se T mg/l	Zn Dis mg/l	Zn T mg/l
SEP-9	11/15/00		0.01		0.005 U		0.01 U		0.025 U		0.53		0.003 U		0.005 U		0.05
SEP-9	02/28/01		0.006		0.005 U		0.01 U		0.025 U		3		0.003 U		0.005 U		0.029
SEP-9	05/17/01		0.007		0.005 U		0.01 U		0.025 U		1.4		0.003 U		0.005 U		0.025
SEP-9	7/31/01	0.005	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	1.3	0.1 U	0.003	0.003 U	0.005 U	0.005 U	0.02 U	0.02 U	0.02 U	
SEP-10	02/14/00		0.012		0.005 U		0.01 U		0.025 U		0.79	J4	0.003 U		0.005 U		0.02 U
SEP-10	05/10/00		0.009		0.005 U		0.01 U		0.025 U		1.4		0.005 U		0.005 U		0.026 U
SEP-10	05/10/00		0.01		0.005 U		0.01 U		0.025 U		1.2		0.006 U		0.005 U		0.03 U
SEP-10	08/21/00		0.005 U		0.005 U		0.01 U		0.025 U		8.1		0.008 U		0.005 U		0.039 U
SEP-10	11/15/00		0.019		0.005 U		0.01 U		0.025 U		0.74		0.003 U		0.008 U		0.039 U
SEP-10	02/28/01		0.005		0.005 U		0.01 U		0.025 U		2.9		0.003 U		0.005 U		0.023 U
SEP-10	05/17/01		0.005 U		0.005 U		0.01 U		0.025 U		1.7		0.003 U		0.005 U		0.02 U
SEP-10	7/31/01	0.005 U	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	2.7	0.003 U	0.005 U	0.005 U	0.005 U	0.02 U	0.02 U		
SEP-11	02/14/00		0.014		0.005 U		0.01 U		0.025 U		0.47	J4	0.013		0.005 U		0.029 U
SEP-11	05/10/00		0.008		0.005 U		0.01 U		0.025 U		1.4		0.003 U		0.005 U		0.024 U
SEP-11	08/21/00		0.005 U		0.005 U		0.01 U		0.025 U		8.2		0.009 U		0.005 U		0.035 U
SEP-11	11/15/00		0.013		0.005 U		0.01 U		0.025 U		0.67		0.003 U		0.007 U		0.035 U
SEP-11	11/15/00		0.013		0.005 U		0.01 U		0.025 U		0.66		0.003 U		0.007 U		0.04 U
SEP-11	02/28/01		0.005		0.005 U		0.01 U		0.025 U		2.9		0.004 U		0.005 U		0.023 U
SEP-11	05/17/01		0.005 U		0.005 U		0.01 U		0.025 U		2.1		0.003 U		0.005 U		0.02 U
SEP-11	7/31/01	0.005 U	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3	0.003 U	0.005 U	0.005 U	0.005 U	0.02 U	0.023 U		
SEP-12	02/14/00		0.013		0.005 U		0.01 U		0.025 U		0.66	J4	0.003 U		0.005 U		0.02 U
SEP-12	05/10/00		0.008		0.005 U		0.01 U		0.025 U		1.2		0.004 U		0.005 U		0.027 U
SEP-12	08/21/00		0.005 U		0.005 U		0.01 U		0.025 U		10		0.013 U		0.005 U		0.04 U
SEP-12	11/15/00		0.014		0.005 U		0.01 U		0.025 U		0.84		0.004 U		0.005 U		0.034 U
SEP-12	02/28/01		0.007		0.005 U		0.01 U		0.025 U		2.5		0.003 U		0.005 U		0.02 U
SEP-12	05/17/01		0.005		0.005 U		0.01 U		0.025 U		1.9		0.003 U		0.005 U		0.02 U
SEP-12	8/1/01	0.005	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3.1	0.003 U	0.004 U	0.005 U	0.005 U	0.02 U	0.026 U		

Table 2-10

Hydrometrical Surface Water Metal Concentration Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Cr Dis mg/l	Cr T mg/l	Cu Dis mg/l	Cu T mg/l	Fe Dis mg/l	Fe T mg/l	Pb Dis mg/l	Pb T mg/l	Se Dis mg/l	Se T mg/l	Zn Dis mg/l	Zn T mg/l
SEP-13	02/14/00		0.014		0.005 U		0.01 U		0.025 U		0.46 J4		0.003		0.005		0.02 U
SEP-13	02/14/00		0.013		0.005 U		0.01 U		0.025 U		0.6 J4		0.003 U		0.005		0.02 U
SEP-13	05/10/00		0.008		0.005 U		0.01 U		0.025 U		1.2		0.003 U		0.005	U	0.023 UJ1,J2
SEP-13	08/21/00		0.005 U		0.005 U		0.01 U		0.025 U		9.7		0.008		0.005	U	0.04 UJ1
SEP-13	08/21/00		0.005 U		0.005 U		0.01 U		0.025 U		9.6		0.007		0.005	U	0.036 UJ1
SEP-13	11/15/00		0.015		0.005 U		0.01 U		0.025 U		1.3		0.009		0.005		0.043
SEP-13	02/28/01		0.008		0.005 U		0.01 U		0.025 U		2		0.003 U		0.005	U	0.02 U
SEP-13	02/28/01		0.008		0.005 U		0.01 U		0.025 U		2		0.003 U		0.005	U	0.02 U
SEP-13	05/17/01		0.005		0.005 U		0.01 U		0.025 U		1.7		0.003 U		0.005	U	0.02 U
SEP-13	8/1/01	0.005 U	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3.1	0.003 U	0.005	0.005 U	0.005 U	0.02 U	0.022		
AVERAGE		0.005	0.008	0.005	0.006	0.025	0.0119	0.25	0.35213	0.003	2.3791	0.005	0.0051	0.02	0.0073	0	0.0289
MEDIAN		0.005	0.007	0.005	0.005	0.025	0.01	0.1	0.025	0.003	1.4	0.005	0.003	0.02	0.005	0	0.026
STD		4E-04	0.004	6E-11	0.002	5E-10	0.005	0.42	0.95481	4E-11	2.8501	6E-11	0.004	2E-10	0.0058	0	0.0094
MAXIMUM		0.006	0.019	0.005	0.01	0.025	0.025	1.3	3.9	0.003	12	0.005	0.026	0.02	0.026	0	0.05
MINIMUM		0.005	0.005	0.005	0.005	0.025	0.01	0.1	0.025	0.003	0.003	0.005	0.003	0.02	0.005	0	0.02
American Canal																	
SEP-1	01/31/00		0.005 U		0.005 U		0.01 U		0.025 U		1.1		0.003 U		0.005	U	0.02 U
SEP-1	05/09/00		0.007		0.005 U		0.01 U		0.025 U		1.7		0.007		0.005	U	0.03 UJ1,J2
SEP-1	08/14/00		0.005 U		0.005 U		0.01 U		0.025 U		5.9		0.006		0.005	U	0.034
SEP-1	08/14/00		0.005 U		0.005 U		0.01 U		0.025 U		5.6		0.005		0.005	U	0.024
SEP-1	11/10/00		0.005 U		0.005 U		0.01 U		0.025 U		7.7		0.014		0.005	U	0.025
SEP-1	02/23/01		0.005 U		0.005 U		0.01 U		0.025 U		1.6		0.003 U		0.005	U	0.033 UJ1
SEP-1	05/16/01		0.005 U		0.005 U		0.01 U		0.025 U		3 J4		0.003 U		0.005	U	0.02 U
SEP-1	7/31/01	0.005 U	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	2.4	0.003 U	0.004	0.005 U	0.005 U	0.02 U, UJ4	0.028 J4		
SEP-3	01/31/00		0.005 U		0.005 U		0.01 U		0.025 U		1.2		0.003 U		0.005	U	0.02 U
SEP-3	05/09/00		0.007		0.005 U		0.01 U		0.025 U		1.9		0.003		0.005	U	0.029 UJ1,J2
SEP-3	08/14/00		0.005 U		0.005 U		0.01 U		0.025 U		6		0.005		0.005	U	0.023
SEP-3	11/10/00		0.005 U		0.005 U		0.01 U		0.025 U		8.4		0.005		0.005	U	0.028

Table 2-10

Hydrometries Surface Water Metal Concentration Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Cr Dis mg/l	Cr T mg/l	Cu Dis mg/l	Cu T mg/l	Fe Dis mg/l	Fe T mg/l	Pb Dis mg/l	Pb T mg/l	Se Dis mg/l	Se T mg/l	Zn Dis mg/l	Zn T mg/l
SEP-3	02/23/01		0.005 U		0.005 U		0.01 U		0.025 U		1.8		0.003 J1		0.005 U		0.028 UJ1
SEP-3	05/16/01		0.005 U		0.005 U		0.01 U		0.025 U		2.4 J4		0.003 U		0.005 U		0.02
SEP-3	8/1/01	0.005	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	3.1	0.003 U	0.004	0.005 U	0.005 U	0.02	0.021		
SEP-7	01/31/00		0.005 U		0.005 U		0.01 U		0.025 U		1		0.004		0.005 U		0.04
SEP-7	05/09/00		0.007		0.005 U		0.01 U		0.025 U		2		0.006		0.005 U		0.03 UJ1,J2
SEP-7	08/14/00		0.005 U		0.005 U		0.01 U		0.025 U		6.3		0.005		0.005 U		0.043
SEP-7	11/10/00		0.005 U		0.005 U		0.01 U		0.025 U		8.7		0.006		0.005 U		0.028
SEP-7	02/23/01		0.005 U		0.005 U		0.01 U		0.025 U		1.9		0.004 J1		0.005 U		0.037 UJ1
SEP-7	05/16/01		0.005 U		0.005 U		0.01 U		0.025 U		2.2 J4		0.003 U		0.005 U		0.02 U
SEP-7	05/16/01		0.005 U		0.005 U		0.01 U		0.025 U		3.4 J4		0.003 U		0.005 U		0.02 U
SEP-7	7/31/01	0.005 U	0.005 U	0.005 U	0.01 U	0.025 U	0.025 U	0.1 U	2.8	0.003 U	0.003	0.005 U	0.005 U	0.02 U,J4	0.02 U,J4		
AVERAGE		0.005	0.005	0.005	0.006	0.025	0.012	0.1	0.38261	0.003	3.2092	0.005	0.0047	0.02	0.0073	0	0.0276
MEDIAN		0.005	0.005	0.005	0.005	0.025	0.01	0.1	0.025	0.003	2	0.005	0.005	0.02	0.005	0	0.028
STD		8E-11	7E-04	8E-11	0.002	0	0.0052	0	0.95001	0	2.7407	8E-11	0.0024	3E-10	0.0063	0	0.0071
MAXIMUM		0.005	0.007	0.005	0.01	0.025	0.025	0.1	3.1	0.003	8.7	0.005	0.014	0.02	0.028	0	0.043
MINIMUM		0.005	0.005	0.005	0.005	0.025	0.01	0.1	0.025	0.003	0.003	0.005	0.003	0.02	0.005	0	0.02

Note:

- J The associated numerical value is an estimated quantity because quality control criteria were not met
- J2 calibration range exceeded or significant deviation from known values. Possible bias.
- J3 Holding time not met. Indicates low bias.
- J4 Other QC outside control limits
- U Undetected. Below method detection limits.
- UJ The material was analyzed for, but was not detected above the associated value.
- UJ1 Blank contamination. Indicates possible high bias and/or false positive.
- UJ2 Calibration range exceeded or significant deviation from known value.
- UJ3 Holding times not met. Indicates low bias.
- UJ4 Other QC outside control limits.
- R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.
- A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals
T Total Metals

Summary of Hydrometrics Surface Water Analytical Results
February 2000 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb NTU	Temp (F)	Ca mg/l	Mg mg/l	Na mg/l	K mg/l	HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
Rio Grande																	
Ave	8.0	8.2	1388	894	136	45	65	80.9	19.6	173.1	9.8	242.8	2.9	282.0	155.5	0.7	1.1
Max	11.5	8.6	2440	1574	437	210	89	119.0	32.0	334.0	14.0	342.0	14.4	598.0	315.0	0.9	6.1
Min	5.2	7.9	927	519	17	12	32	57.0	14.0	89.0	7.3	195.0	1.0	172.0	73.0	0.6	0.2
American Canal																	
Ave	7.7	8.3	1190	761	193	54	74	76.3	18.0	145.2	9.2	236.3	3.3	229.8	126.8	0.7	0.8
Max	9.5	8.6	1784	1208	311	157	92	114.0	29.0	225.0	12.0	342.0	11.0	335.0	222.0	0.8	2.2
Min	5.6	8.2	946	603	64	24	51	60.0	15.0	99.0	7.2	203.0	1.0	187.0	73.0	0.7	0.2
Sample																	
	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Cr Dis mg/l	Cr T mg/l	Cu Dis mg/l	Cu T mg/l	Fe Dis mg/l	Fe T mg/l	Pb Dis mg/l	Pb T mg/l	Se Dis mg/l	Se T mg/l	Zn Dis mg/l	Zn T mg/l	
Rio Grande																	
Ave	0.005	0.008	0.005	0.006	0.025	0.012	0.250	0.353	0.003	2.379	0.005	0.005	0.020	0.007	0.000	0.029	
Max	0.006	0.019	0.005	0.010	0.025	0.025	1.300	3.900	0.003	12.000	0.005	0.026	0.020	0.026	0.000	0.050	
Min	0.005	0.005	0.005	0.005	0.025	0.010	0.100	0.025	0.003	0.003	0.005	0.003	0.020	0.005	0.000	0.020	
American Canal																	
Ave	0.005	0.005	0.005	0.006	0.025	0.012	0.100	0.383	0.003	3.209	0.005	0.005	0.020	0.007	0.000	0.028	
Max	0.005	0.007	0.005	0.010	0.025	0.025	0.100	3.100	0.003	8.700	0.005	0.014	0.020	0.028	0.000	0.043	
Min	0.005	0.005	0.005	0.005	0.025	0.010	0.100	0.025	0.003	0.003	0.005	0.003	0.020	0.005	0.000	0.020	

Note:

Dis Dissolved
T Total Metals
N Nitrate +Nitrite

Table 2-12

Summary of Streambed Sediment Sample Results
August 1999 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Site	Date	Type Name	Arsenic mg/kg		Cadmium mg/kg		Lead mg/kg	
SEP-2-SED	8/20/99	SEDIMENT/SOIL	10	U	12		160	
SEP-2-SED	11/2/99	SEDIMENT/SOIL	10	U	10	U	57	
SEP-2-SED	2/14/00	SEDIMENT/SOIL	10	U	15	J4	48	
SEP-2-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	20	
SEP-2-SED	8/21/00	SEDIMENT/SOIL	10	U	10	U	85	
SEP-2-SED	8/21/00	SEDIMENT/SOIL	17		10	U	92	
SEP-2-SED	11/15/00	SEDIMENT/SOIL	10	U	10	U	58	
SEP-2-SED	2/28/01	SEDIMENT/SOIL	10	U	10	U	25	
SEP-2-SED	5/17/01	SEDIMENT/SOIL	19		11		53	
SEP-2-SED	7/31/01	SEDIMENT/SOIL	21		10	U	130	
Average			12.7		10.8		72.8	
Median			10.0		10.0		57.5	
Standard Deviation			4.4		1.6		44.6	
Minimum			10.0		10.0		20.0	
Maximum			21.0		15.0		160.0	
SEP-4-SED	8/20/99	SEDIMENT/SOIL	10	U	10	U	28	
SEP-4-SED	11/2/99	SEDIMENT/SOIL	10	U	10	U	66	
SEP-4-SED	2/14/00	SEDIMENT/SOIL	10	U	10	U,UJ4	19	
SEP-4-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	36	
SEP-4-SED	8/21/00	SEDIMENT/SOIL	24		10	U	170	
SEP-4-SED	11/15/00	SEDIMENT/SOIL	23		18		140	
SEP-4-SED	2/28/01	SEDIMENT/SOIL	30		10	U	63	
SEP-4-SED	2/28/01	SEDIMENT/SOIL	25		10	U	63	
SEP-4-SED	5/17/01	SEDIMENT/SOIL	20		13		40	
SEP-4-SED	7/31/01	SEDIMENT/SOIL	16		10	U	63	
SEP-4-SED	7/31/01	SEDIMENT/SOIL	22		14		60	
Average			18.2		11.4		68.0	
Median			20.0		10.0		63.0	
Standard Deviation			7.3		2.6		46.4	
Minimum			10.0		10.0		19.0	
Maximum			30.0		18.0		170.0	
SEP-9-SED	8/20/99	SEDIMENT/SOIL	10	U	10	U	29	
SEP-9-SED	11/2/99	SEDIMENT/SOIL	10	U	10	U	64	
SEP-9-SED	2/14/00	SEDIMENT/SOIL	10	U	10	U,UJ4	20	
SEP-9-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	58	
SEP-9-SED	8/21/00	SEDIMENT/SOIL	12		10	U	56	
SEP-9-SED	11/15/00	SEDIMENT/SOIL	15		10	U	280	
SEP-9-SED	2/28/01	SEDIMENT/SOIL	44		14		172	
SEP-9-SED	5/17/01	SEDIMENT/SOIL	14		11		37	
SEP-9-SED	7/31/01	SEDIMENT/SOIL	24		10	U	120	

Table 2-12

Summary of Streambed Sediment Sample Results
August 1999 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Site	Date	Type Name	Arsenic mg/kg		Cadmium mg/kg		Lead mg/kg	
Average			16.6		10.6		92.9	
Median			12.0		10.0		58.0	
Standard Deviation			11.2		1.3		85.1	
Minimum			10.0		10.0		20.0	
Maximum			44.0		14.0		280.0	
SEP-10-SED	8/20/99	SEDIMENT/SOIL	10	U	10	U	21	
SEP-10-SED	11/2/99	SEDIMENT/SOIL	21		10	U	35	
SEP-10-SED	2/14/00	SEDIMENT/SOIL	10	U	10	U,UJ4	12	
SEP-10-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	33	
SEP-10-SED	8/21/00	SEDIMENT/SOIL	50		10	U	120	
SEP-10-SED	11/15/00	SEDIMENT/SOIL	28		10	U	39	
SEP-10-SED	11/15/00	SEDIMENT/SOIL	10	U	10	U	39	
SEP-10-SED	2/28/01	SEDIMENT/SOIL	10	U	10	U	20	
SEP-10-SED	5/17/01	SEDIMENT/SOIL	35		10	U	53	
SEP-10-SED	7/31/01	SEDIMENT/SOIL	26		12		51	
Average			21.0		10.2		42.3	
Median			15.5		10.0		37.0	
Standard Deviation			13.8		0.6		30.3	
Minimum			10.0		10.0		12.0	
Maximum			50.0		12.0		120.0	
SEP-11-SED	8/20/99	SEDIMENT/SOIL	10		10	U	40	
SEP-11-SED	11/2/99	SEDIMENT/SOIL	11		10	U	140	
SEP-11-SED	2/14/00	SEDIMENT/SOIL	10	U	10	U,UJ4	34	
SEP-11-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	19	
SEP-11-SED	8/21/00	SEDIMENT/SOIL	10	U	10	U	74	
SEP-11-SED	11/15/00	SEDIMENT/SOIL	10	U	10	U	42	
SEP-11-SED	2/28/01	SEDIMENT/SOIL	36		10	U	65	
SEP-11-SED	5/17/01	SEDIMENT/SOIL	26		10	U	56	
SEP-11-SED	7/31/01	SEDIMENT/SOIL	12		10	U	50	
Average			15.0		10.0		57.8	
Median			10.0		10.0		50.0	
Standard Deviation			9.4		0.0		35.0	
Minimum			10.0		10.0		19.0	
Maximum			36.0		10.0		140.0	
SEP-12-SED	8/20/99	SEDIMENT/SOIL	17		10	U	24	
SEP-12-SED	11/2/99	SEDIMENT/SOIL	10	U	10	U	54	
SEP-12-SED	2/14/00	SEDIMENT/SOIL	12		12	J4	23	
SEP-12-SED	5/10/00	SEDIMENT/SOIL	10	U	10	U	20	
SEP-12-SED	8/21/00	SEDIMENT/SOIL	11		10	U	46	
SEP-12-SED	11/15/00	SEDIMENT/SOIL	10	U	10	U	24	
SEP-12-SED	2/28/01	SEDIMENT/SOIL	33		10	U	73	
SEP-12-SED	5/17/01	SEDIMENT/SOIL	22		11		59	
SEP-12-SED	7/31/01	SEDIMENT/SOIL	20		10	U	68	

Table 2-12

Summary of Streambed Sediment Sample Results
August 1999 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Site	Date	Type Name	Arsenic mg/kg		Cadmium mg/kg		Lead mg/kg	
Average			16.1		10.3		43.4	
Median			12.0		10.0		46.0	
Standard Deviation			7.8		0.7		21.1	
Minimum			10.0		10.0		20.0	
Maximum			33.0		12.0		73.0	
SEP-13-SED	8/20/99	SEDIMENT/SOIL	10	U	10	U	31	
SEP-13-SED	11/2/99	SEDIMENT/SOIL	21		13		51	
SEP-13-SED	2/14/00	SEDIMENT/SOIL	10	U	12	J4	66	
SEP-13-SED	5/10/00	SEDIMENT/SOIL	10		10	U	40	
SEP-13-SED	8/21/00	SEDIMENT/SOIL	14		10	U	380	
SEP-13-SED	11/15/00	SEDIMENT/SOIL	33		10	U	100	
SEP-13-SED	2/28/01	SEDIMENT/SOIL	20		10	U	58	
SEP-13-SED	5/17/01	SEDIMENT/SOIL	30		10	U	66	
SEP-13-SED	5/17/01	SEDIMENT/SOIL	28		10	U	59	
SEP-13-SED	8/1/01	SEDIMENT/SOIL	32		10	U	150	
SEP-13-SED	8/1/01	SEDIMENT/SOIL	22		10	U	118	
SEP-13-SED	8/1/01	SEDIMENT/SOIL	32		13		160	
Average			21.8		10.7		106.6	
Median			21.5		10.0		66.0	
Standard Deviation			9.2		1.2		95.7	
Minimum			10.0		10.0		31.0	
Maximum			33.0		13.0		380.0	

Note

See Figure 3-31 for all sample locations.

All concentrations in milligrams per kilogram (mg/kg).

(U) Concentration is less than the detection limit indicated

Table 2-13

IBWC Rio Grande Monthly Mean Flow Volumes
January 2000 Through June 2001
Asarco El Paso Smelter, Phase III RJ

Date Measured	Pump House Below American Dam cubic meters/second	Courchesne Bridge cubic meters/second	Diversion at American Canal cubic meters/second
01/01/00	0.19	5.22	5.16
02/01/00	0.21	4.86	4.92
03/01/00	2.58	22.15	17.88
04/01/00	5.21	17.08	11.40
05/01/00	2.24	18.80	16.08
06/01/00	6.99	33.72	23.39
07/01/00	6.45	29.95	22.34
08/01/00	5.87	29.69	21.86
09/01/00	3.36	19.71	16.12
10/01/00	0.58	11.79	11.02
11/01/00	0.45	5.67	5.35
12/01/00	1.81	3.62	2.15
01/01/01	1.24	2.88	2.20
02/01/01	0.56	8.90	9.85
03/01/01	3.11	24.55	19.17
04/01/01	5.22	22.19	15.54
05/01/01	2.31	19.54	16.28
06/01/01	5.48	31.05	23.85

Tab. 14

**Groundwater Elevations in Wells Adjacent to the Rio Grande and Historical Smelertown
February 1995 through August 2001
ASARCO El Paso Smelter, Phase III RI**

Well Identifier												
Date Measured	EP-4	EP-5	EP-6	EP-7	EP-60	EP-61	EP-62	EP-63	EP-64	EP-65	EP-66	
	Adjacent to Rio Grande				Historical Smelertown							
02/10/95	02/25/10	3709.28	3708.21	3714.88	3712.07	3712.11	3711.98	3711.44	3712.5	3705.39	3711.36	
05/19/95	02/26/10	3710.47	3709.41	3716.05	3713.27	3713.11	3713.29	3712.77	3713.77	3712.23	3712.63	
08/21/95	02/27/10	3711.06	3710.37	3717.02	3714.41	3713.98	3713.95	3713.5	3715	3713.5	3713.67	
11/17/95	02/25/10	3709.39	3708.45	3715.03	3712.45	3711.97	3712.04	3711.54	3712.67	3708.57	3715.5	
02/21/96	02/25/10	3709.21	3708.09	3714.58	3712.15	3712.02	3711.94	3711.47	3712.44	3708.54	3711.33	
05/10/96	02/26/10	3710.1	3708.93	3715.51	3713.18	3713.03	3713	3712.49	3713.48	3711.58	3712.45	
08/14/96	02/26/10	3711.28	3709.45	3715.77	3713.34	NM	3713.18	3712.71	3713.69	NM	3712.65	
11/11/96	02/26/10	3710.21	3708.21	3714.93	3712.32	3711.15	3711.08	3710.22	3711.85	3709.07	3710.9	
02/08/97	02/25/10	3710.05	3708.28	3714.89	3712.25	3711.28	3711.05	3710.14	3711.76	3708.62	3710.98	
05/13/97	02/26/10	3710.04	3708.92	3715.42	3713.02	3713.27	3713.29	3712.64	3713.74	3713.15	3712.6	
08/08/97	02/26/10	3710.39	3709.52	3716.08	3713.52	3713.37	3713.32	3712.9	3713.82	3713.14	3712.86	
11/05/97	02/25/10	3710.35	3708.42	3714.45	3712.5	3711.15	3711.09	3710.22	3711.95	3710.42	3711.03	
02/01/98	02/26/10	3710.66	3708.61	3714.1	3712.35	3711.11	3711	3710.1	3711.73	3710.66	3711.67	
05/01/98	02/26/10	3709.86	3708.74	3715.16	3713.3	3712.22	3713.02	3712.57	3713.55	3712.87	3712.51	
08/06/98	02/26/10	3710.39	3709.68	3716.23	3713.48	3712.74	3713.33	3712.85	3713.8	3713.07	3712.79	
11/07/98	02/26/10	3710.57	3709.54	3716.1	3713.16	3712.25	3712.93	3712.42	3713.34	3712.8	3712.44	
02/06/99	02/25/10	3711.07	3710.24	3716.92	3713.42	3712.2	3713.34	3712.94	3713.66	3712.72	3712.89	
05/12/99	02/23/10	3709.89	3708.94	3713.38	3713.14	3712.44	3713.19	3712.69	3713.65	3712.85	3713.46	
08/06/99	02/27/10	3710.45	3709.69	3716.31	3713.43	3713.68	3713.6	3713.12	3716.11	3713.59	3712.92	
11/04/99	02/26/10	3709.15	3708.18	3714.57	3712.32	3711.81	3712.12	3711.65	3712.74	3711.86	3711.58	
02/01/00	02/26/10	NM	3707.96	3714.65	3712.05	3711.69	3712.07	3711.65	3712.52	3711.67	3711.54	
05/01/00	02/27/10	3710.09	3708.82	3715.64	3712.78	3712.54	3712.65	3712.28	3713.17	3712.46	3712.22	
08/06/00	02/27/10	3709.81	3709.22	3715.86	3712.95	3713.16	3713.1	3712.63	3713.61	3712.89	3712.49	
11/01/00	02/26/10	3709.05	3708.48	3714.77	3712.07	3712.03	3712.02	3711.58	3712.62	3711.67	3711.47	
02/01/01	02/26/10	3709.22	3707.99	3714.7	3711.92	3712.288	3712.14	3711.67	3712.7	3711.954	3711.43	
05/01/01	02/26/10	3709.7	3708.7	3715.26	3712.65	3712.902	3712.79	3712.37	3713.29	3712.61	3712.17	
08/06/01	02/27/10	3710.15	3709.24	3715.95	3712.96	3713.33	3713.2	3712.74	3713.66	3713.04	3712.5	

Notes:

NM: Not Measured.

All values are feet above mean sea level.

See Figure 3-31 for well locations.

Summary of Hydrometrics On-Site Ponds Surface Water Quality Results
August 1997 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb NTU	Temp of	Dissolved				HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
									Ca mg/l	Mg mg/l	Na mg/l	K mg/l						
POND 1	12/22/97		7.5	27200	25974	6.9		48.4	439	144	7724	373	176	1	16043	1002	23	20
POND 1	2/19/98	8.2	7.7	25600	24898	8.8		47.4	411	135	7362	329	154	1	14493	1134	21	23
POND 1	5/19/98	5.3	7.9	50100	53664	21		75.4	526	274	16140	715	256	1	36326	2853	30	34
POND 1	8/18/98	4.1	8.1	126300	101290	43		78.8	585	545	36130	1157	251	1	59186	5316	38	55
POND 1	11/18/98	7.1	8.0	8260	6712	22		60.6	266	54	1865	64	140	1	3866	630	7.5	6.9
POND 1	2/19/99	12.3	8.1	19330	16995	48		60.6	397	95	5144	211	168	1	7894	1340	14	18
POND 1	5/12/99	7.0	7.9	34600	34222	69		67.6	548	198	10500	460	159	1	20254	292	12	88
POND 1	8/11/99	4.2	7.9	46400	49470	56		92.7	537	329	13740	409	131	1	32369	3406	35	134
POND 1	11/2/99	9.9	8.1	215000	147412	1703		56.3	850	3445	42350	4074	587	1	80035	24148	121	1112
POND 1	8/21/00	4.7	7.4	8280	6514	15	5.86	86.2	184	26	1493	38	39	1	3778	410	14	45
POND 1	11/14/00	9.4	7.7	38000	38326	21	9.5	59.5	314	132	12056	194	85	1	22838	2158	20	117
Ave		7.2	7.8	54461	45952	183	8	67	460	489	14046	729	195	1	27007	3881	31	150
Max		12.3	8.1	215000	147412	1703	10	93	850	3445	42350	4074	587	1	80035	24148	121	1112
Min		4.1	7.4	8260	6514	7	6	47	184	26	1493	38	39	1	3778	292	8	7
POND 5	12/22/97																	
POND 5	2/19/98	7.3	7.5	975	644	2.8		70.7	35	3.2	154	7.3	61	1	193	137	1	0.05
POND 5	5/19/98	8.1	8.9	1152	775	1.8		54.1	41	6.9	195	6.3	92	1	237	144	0.91	1.2
POND 5	8/18/98	5.3	6.7	1351	846	6		75.6	78	18	176	13	116	25	318	176	0.94	0.05
POND 5				1970	1277	11		75.4	108	25	275	14	21	1	449	349	3.1	0.098
Ave		6.9	7.6	1362	886	5		69	66	13	200	10	73	7	299	202	1	0
Max		8.1	8.9	1970	1277	11	0	76	108	25	275	14	116	25	449	349	3	1
Min		5.3	6.7	975	644	2	0	54	35	3	154	6	21	1	193	137	1	0
POND 6	12/22/97																	
POND 6	2/19/98	5.9	7.8	5330	3912	27		61.5	175	24	1139	30	98	1	1874	497	11	0.56
POND 6	5/19/98	8.3	9.1	3960	2914	23		61.0	103	11	938	17	73	1	1363	402	5.1	1.2
POND 6	8/18/98	4.8	8.6	4650	3389	41		85.3	213	47	925	29	150	35	1634	512	8.2	0.05
POND 6				5390	4045	17		83.1	267	56	950	47	189	11	1846	639	4.1	0.84
POND 6	11/12/98	6.9	8.2	4540	3397	44		60.3	198	35	887	33	166	1	1592	559	3.6	1.4

Summary of Hydrometrics On-Site Ponds Surface Water Quality Results
August 1997 Through August 2001
ASARCO El Paso Smelter, Phase III RI

Sample ID	Sample Date	DO mg/l	PH	SC umhos/cm	TDS mg/l	TSS mg/l	Turb NTU	Temp oF	Dissolved				HCO3 mg/l	CO3 mg/l	SO4 mg/l	Cl mg/l	F mg/l	N mg/l
									Ca mg/l	Mg mg/l	Na mg/l	K mg/l						
POND 6	2/19/99	10.8	8.5	2610	1716	15		67.3	82	7.6	507	15	62	5	462	286	1.9	0.05
POND 6	5/12/99	9.2	8.9	2450	1632	23		69.4	115	23	420	20	144	1	691	278	2.2	0.1
POND 6	8/11/99	7.0	8.8	1773	1186	17		92.7	97	18	218	11	112	19	377	250	1.6	0.08
POND 6	11/2/99	9.5	9.2	1702	1032	34	13.91	59.9	95	17	222	11	165	1	338	243	1.7	0.16
POND 6	2/7/00	6.4	7.7	1420	909	15	200	52.7	77	13	205	8.5	96	1	226	177	1.4	0.54
POND 6	5/9/00	8.8	9.3	1868	1227	38	200	73.9	109	17	307	12	50	41	383	298	2.4	0.06
POND 6	8/21/00	8.3	7.6	2190	1598	22	9.72	90.0	188	33	219	13	61	1	745	246	2.9	0.57
POND 6	11/14/00	12.4	8.9	3450	2715	21	200	61.5	273	58	353	19	88	10	1321	369	4.7	0.26
Ave		8.2	8.5	3179	2282	26	125	71	153	28	561	20	112	10	989	366	4	0
Max		12.4	9.3	5390	4045	44	200	93	273	58	1139	47	189	41	1874	639	11	1
Min		4.8	7.6	1420	909	15	10	53	77	8	205	9	50	1	226	177	1	0
SEP-14	11/12/98		8.9	272	182	50		55.6	24	4	22	5	77	10	65	7.6	0.32	0.1
SEP-14	8/11/99	6.4	7.8	160	103	53		88.5	15	2.7	12	5	51	1	20	1.1	0.28	0.09
SEP-14	8/21/00	5.9	7.7	183	136	49	5.8	87.1	12	3	16	2.6	54	1	33	6	0.24	0.41
SEP-14	11/14/00	10.2	7.6	152	116	51	6.11	55.8	15	2.9	8.9	2.5	59	1	20	3.7	0.16	0.55
SEP-14	11/14/00	10.2	7.8	151	106	43		55.8	14	2.7	8.2	3	93	1	20	4.8	0.16	0.39
SEP-14	6/27/01	4.6	6.8	306	262	71	88.2	90.9	23	4.5	26	7.7	51	1	75	9.2	0.35	1.1
SEP-14	6/27/01	4.7	6.5	308	232	75	89.7	91.4	24	4.8	26	7.9	63	1	73	9.6	0.35	1.2
Ave		7.0	7.6	219	162	56	47	75	18	4	17	5	64	2	44	6	0	1
Max		10.2	8.9	308	262	75	90	91	24	5	26	8	93	10	75	10	0	1
Min		4.6	6.5	151	103	43	6	56	12	3	8	3	51	1	20	1	0	0

Sample ID	Sample Date	As Dis mg/l	As T mg/l	As TRC mg/l	Cd Dis mg/l	Se Dis mg/l	Se T mg/l	Se TRC mg/l	Zn Dis mg/l	Zn T mg/l	Zn TRC mg/l
POND 1	12/22/97	0.14			16	0.74			137		
POND 1	2/19/98	0.59			15	0.91			116		
POND 1	5/19/98	0.064			22	1.7			82		
POND 1	8/18/98	0.22		0.29	35	2.9		2.8	51		51
POND 1	11/18/98	0.34		0.54	1.9	0.38		0.37	3.6		4.3
POND 1	2/19/99	0.19		0.44	6.2	0.97		0.99	7		8.6
POND 1	5/12/99	0.082		0.27	19	1.4		1.3	33		20
POND 1	8/11/99	0.42		0.45	18	2.1		2.1	9.8		2.1
POND 1	11/2/99		2.1				11			58	
POND 1	8/21/00		0.27				0.39			2.8	
POND 1	11/14/00		0.7				1.5			9.8	
POND 5	12/22/97	0.098			0.054	0.005 U			0.6		
POND 5	2/19/98	0.14			0.04	0.026			0.43		
POND 5	5/19/98	0.081			0.021	0.009			0.22		
POND 5	8/18/98	0.21		0.27	0.067	0.032		0.028	0.82		1
POND 6	12/22/97	3.7			0.15	0.12			0.92		
POND 6	2/19/98	1.8			0.13	0.08			1.8		
POND 6	5/19/98	2.7			0.059	0.082			0.16		
POND 6	8/18/98	0.88		0.87	0.12	0.058		0.051	0.3		0.46
POND 6	11/12/98	1.5		1.6	0.27	0.079		0.08	0.98		1.9
POND 6	2/19/99	0.59		0.68	0.041	0.035		0.035	0.19		0.36
POND 6	5/12/99	0.9		0.83	0.064	0.034		0.025	0.12		0.33
POND 6	8/11/99	0.4		0.4	0.047	0.022		0.024	0.092 UJ1		0.34
POND 6	11/2/99		0.45				0.012			0.44	
POND 6	2/7/00		0.27				0.014			0.41	
POND 6	5/9/00		0.75				0.035			0.15 J2	
POND 6	8/21/00		0.97				0.099			1.9	
POND 6	11/14/00		1.3				0.1			1.4	
SEP-14	11/12/98	0.057		0.055	0.005	0.005 U		0.005 U	0.02 U		0.18
SEP-14	8/11/99	0.045		0.049	0.005	0.005 U		0.005 U	0.025 UJ1		0.22
SEP-14	8/21/00		0.058				0.006			0.14	
SEP-14	11/14/00		0.038				0.005 U			0.23	
SEP-14	11/14/00		0.035				0.005 U			0.19	
SEP-14	6/27/01		0.094				0.005 U			1.3	
SEP-14	6/27/01		0.096				0.005 U			1.3	
Ave		0.689	0.549	0.519	6.1	0.531	1.01	0.60	20.3	6.0	7.0
Max		3.700	2.100	1.600	35.0	2.900	11.00	2.80	137.0	58.0	51.0
Min		0.045	0.035	0.049	0.0	0.005	0.01	0.01	0.0	0.1	0.2

Note:

- J The associated numerical value is an estimated quantity
J2 calibration range exceeded or significant deviation from
J3 Holding time not met. Indicates low bias.
J4 Other QC outside control limits

U Undetected. Below method detection limits.

- UJ The material was analyzed for, but was not detected
UJ1 Blank contamination. Indicates possible high bias or
UJ2 Calibration range exceeded or significant deviation from
UJ3 Holding times not met. Indicates low bias.
UJ4 Other QC outside control limits.

- R Quality control indicates that the data are unusable (e.g., blank, no sample)
A Anomalous data. No apparent explanation for discrepancy

Table 2-17

**Drinking Water Standards
Maximum Contaminant Levels (MCL)**

Parameter	Units	Federal ⁽¹⁾	Texas ⁽²⁾
Arsenic	mg/l	0.05	0.05
Cadmium	mg/l	0.005	0.005
Chromium	mg/l	0.1	0.1
Copper	mg/l	1.3 (action level)	
Iron	mg/l	0.3 (secondary MCL)	0.3 (secondary MCL)
Lead	mg/l	0.015 (action level)	0.015 (action level)
Selenium	mg/l	0.05	0.05
Zinc	mg/l	5 (secondary MCL)	5.0 (secondary MCL)
pH	units	6.5-8.5 (secondary MCL)	>7.0 (secondary MCL)
Specific Conductivity	----	----	----
Total Dissolved Solids	mg/l	500 (secondary MCL)	1,000 (secondary MCL)

Notes:

MCLs are enforceable primary drinking water standards.

Secondary MCLs are nonenforceable federal guidelines.

Action levels are nonenforceable health-based guidance levels.

No standard has been established for specific conductivity.

mg/l= milligrams per liter.

(1) Source: EPA, Drinking Water Regulations and Health Advisories, October 1996.

(2) Source: Texas Natural Resource Conservation Commission, Chapter 290- Water Hygiene, Subchapter F, Drinking Water Standards, Governing Drinking Water Quality and Reporting Requirements for Public Water Supply Systems.

Table 2-18

**Summary of Soil Sample Results for Investigation Area 1
(Converter Building/Baghouse Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	BH1-1	BH1-1A	8/31/99	0.5-1.5 ft.	30	10 U	62
		BH1-1B	8/31/99	1.5-2.5 ft.	200	58	1600
		BH1-1B2	8/31/99	1.5-2.5 ft.	233	37	1470
		BH1-1C	8/31/99	10-12 ft.	17	10 U	10 U
		BH1-1D	8/31/99	15-17 ft.	10	10 U	10 U
		BH1-1E	8/31/99	20-22 ft.	20	10 U	10 U
		BH1-1F	8/31/99	25-27 ft.	16	20	10 U
		BH1-1G	9/1/99	30-32 ft.	48	10 U	11
		BH1-1H	9/1/99	35-37 ft.	33	10 U	16
		BH1-1I	9/1/99	40-42 ft.	16	10 U	10 U
		BH1-1J	9/1/99	45-47 ft.	18	10 U	10 U
	BH1-2	BH1-2A	9/1/99	0-1 ft.	720	590	710
		BH1-2B	9/1/99	1-2 ft.	77	160	190
		BH1-2C	9/1/99	2-3 ft.	16	10 U	100
		BH1-2D	9/1/99	3-4 ft.	30	10 U	140
		BH1-2E	9/1/99	4-5 ft.	12	10 U	46
		BH1-2F	9/2/99	10-12 ft.	10 U	10 U	10 U
		BH1-2G	9/2/99	15-17 ft.	12	10 U	10 U
		BH1-2H	9/2/99	20-22 ft.	23	10 U	11
		BH1-2I	9/2/99	25-27 ft.	12	10 U	10 U
		BH1-2J	9/2/99	30-32 ft.	48	10 U	10 U
		BH1-2K	9/2/99	35-37 ft.	24	10 U	11
		BH1-2K2	9/2/99	DUP	25	10 U	12
		BH1-2L	9/2/99	40-42 ft.	21	11	10 U
	EP-100	EP-100A	9/8/99	0-1 ft.	850	360	850
		EP-100B	9/8/99	1-2 ft.	2300	310	610
		EP-100C	9/8/99	2-3 ft.	720	210	1900
		EP-100D	9/8/99	3-4 ft.	280	410	1900
		EP-100E	9/8/99	4-5 ft.	76	33	680
		EP-100F	9/8/99	10-12 ft.	290	61	440
		EP-100G	9/8/99	15-17 ft.	14	10 U	240
		EP-100H	9/8/99	20-22 ft.	91	24	790
		EP-100H2	9/8/99	20-22 ft.	63	53	660
		EP-100I	9/8/99	25-27 ft.	130	10 U	370
		EP-100J	9/8/99	30-32 ft.	28	10 U	37
		EP-100K	9/8/99	35-37 ft.	100	220	50
		EP-100L	9/8/99	40-42 ft.	100	10 U	10 U
		EP-100L2	9/8/99	40-42 ft.	73	10 U	10 U
		EP-100M	9/8/99	45-47 ft.	110	10 U	10 U

Table 2-18

**Summary of Soil Sample Results for Investigation Area 1
(Converter Building/Baghouse Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I	SSIA1-1	SSIA1-1A	7/15/97	0 ft.	3200	1900	11000
		SSIA1-1B	7/15/97	1.5 ft.	2300	91	5000
		SSIA1-1C	7/15/97	3 ft.	4700	1700	12000
		SSIA1-1D	7/15/97	4 ft.	2600	900	20000
	SSIA1-2	SSIA1-2A	7/15/97	0 ft.	21000	1100	15
		SSIA1-2B	7/15/97	1.5 ft.	22000	1600	5400
		SSIA1-2C	7/15/97	3 ft.	15000	1200	8900
		SSIA1-2D	7/15/97	4 ft.	22000	1300	4000
	SSIA1-3	SSIA1-3A	7/15/97	0 ft.	2000	320	4100
		SSIA1-3B	7/15/97	1.5 ft.	4900	110	5800
		SSIA1-3C	7/15/97	3 ft.	3400	110	7300
		SSIA1-3D	7/15/97	4 ft.	1900	100	5800
	SSIA1-4	SSIA1-4A	7/15/97	0 ft.	410	88	690
		SSIA1-4B	7/15/97	1.5 ft.	570	160	6200
		SSIA1-4C	7/15/97	3 ft.	370	100	3600
		SSIA1-4D	7/15/97	4 ft.	130	41	1400
	SSIA1-5	SSIA1-5A	7/15/97	0 ft.	1800	120	1200
		SSIA1-5B	7/15/97	1.5 ft.	220	20	830
		SSIA1-5C	7/15/97	3 ft.	90	16	670
		SSIA1-5D	7/15/97	4 ft.	10	10 U	140

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-19

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-1
(Converter Building/Baghouse Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA1							
EP-100	1/26/00		0.02		0.043		0.01
	4/28/00		0.019		0.031		0.009
	8/7/00		0.014		0.027		0.005
	11/7/00		0.015		0.02		0.003 U
	2/20/01		0.016		0.019		0.004
	5/9/01		0.021		0.032		0.007
	7/20/01	0.023	0.023	0.015	0.015	0.003 U	0.003
EP-25	2/8/00		4		0.006		0.12
	5/8/00		15		0.005 U		0.025
	8/16/00		6.5		0.005 U		0.012
	11/14/00		12		0.005 U		0.011
	2/26/01		4.8		0.005 U		0.009 J4
	5/16/01		8		0.005 U		0.011
	7/30/01	2.8	7.4	0.005 U	0.005 U	0.003 U	0.007
EP-51	1/26/00		1.2		0.031		0.051
	4/28/00		0.56		0.031		0.02
	8/7/00		0.75		0.029		0.039
	8/7/00		0.88		0.03		0.047
	11/7/00		0.48		0.038		0.031
	11/7/00		0.42		0.038		0.032
	2/16/01		0.37		0.034		0.015
	5/10/01		0.34		0.038		0.011
	7/20/01	0.14	0.29	0.038	0.041	0.003 U	0.014
EP-52	1/26/00		1.5		0.43		0.51
	4/28/00		1.5		0.51		0.96
	8/7/00		1.3		0.43		0.83
	11/7/00		1.7		0.45		1.5
	2/20/01		1.5		0.36		1.4
	5/10/01		1.7		0.45		1.6
	7/20/01	0.22	0.81	0.4	0.4	0.05	0.68

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-20

**Summary of Soil Sample Results for Investigation Area 2
(Boneyard/Slag Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH2-8	BH2-8A	3/28/01	65-66 ft.	190	10 U	100
		BH2-8B	3/28/01	70-71 ft.	180	12	120
	BH2-9	BH2-9A	3/28/01	62-63 ft.	930	10 U	150
		BH2-9B1	3/28/01	66-67 ft.	74	14	58
		BH2-9B2	3/28/01	66-67 ft.	64	15	48
	BH2-10	BH2-10A	3/29/01	47-48 ft.	66	10 U	48
		BH2-10B	3/29/01	51-52 ft.	55	10 U	51
	BH2-11	BH2-11A	3/29/01	21-22 ft.	120	45	63
		BH2-11B	3/29/01	26-27 ft.	87	10 U	43
	BH2-12	BH2-12A	3/30/01	18-19 ft.	65	82	45
		BH2-12B	3/30/01	23-24 ft.	62	55	78
	BH2-13	BH2-13A	3/30/01	15-16 ft.	46	10 U	120
		BH2-13B	3/30/01	18-19 ft.	42	10 U	65
		BH2-13B2	3/30/01	18-19 ft.	29	10 U	32
		BH2-13C	3/30/01	26-27 ft.	86	10 U	77
	EP-125	EP-125A	4/24/01	0-1 ft.	180	23	840
		EP-125B	4/24/01	1-2 ft.	78	10 U	520
		EP-125C	4/24/01	6-7 ft.	36	13	200
		EP-125D	4/24/01	10-11 ft.	16	10 U	28
		EP-125E1	4/24/01	15-16 ft.	33	10 U	47
		EP-125E2	4/24/01	15-16 ft.	33	13	32
		EP-125F	4/24/01	20-21 ft.	38	10 U	43
		EP-125G	4/24/01	25-26 ft.	33	11	46
		EP-125H	4/24/01	30-31 ft.	34	10 U	50
		EP-125I	4/24/01	35-36 ft.	26	12	59
		EP-125J	4/24/01	40-41 ft.	21	10 U	60
		EP-125K	4/24/01	45-46 ft.	31	10 U	65
	EP-126	EP-126A	4/26/01	0.3-1 ft.	190	74	2900
		EP-126B	4/26/01	1-2 ft.	55	64	1400
		EP-126C	4/26/01	2-3 ft.	120	54	1900
		EP-126D	4/26/01	3-4 ft.	48	23	1100
		EP-126E1	4/26/01	10-11 ft.	29	10 U	48
		EP-126E2	4/26/01	10-11 ft.	24	14	46
		EP-126F	4/26/01	15-16 ft.	13	10 U	50
		EP-126G	4/26/01	20-21 ft.	34	10 U	42
		EP-126H	4/26/01	25-26 ft.	30	10 U	38
		EP-126I	4/26/01	30-31 ft.	26	10 U	51

Table 2-20

**Summary of Soil Sample Results for Investigation Area 2
(Boneyard/Slag Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	BH2-1	BH2-1A	8/10/99	63-65 ft.	19	10 U	790
		BH2-1B	8/10/99	68-70 ft.	12	10 U	10 U
		BH2-1C	8/10/99	73-75 ft.	64	10 U	10 U
	BH2-3	BH2-3A	08/13/99	40-42 ft.	27	10 U	10 U
		BH2-3B	08/13/99	45-47 ft.	10 U	10 U	10 U
		BH2-3C	08/13/99	50-52 ft.	10 U	10 U	10 U
		BH2-3D	08/13/99	55-57 ft.	10 U	10 U	10 U
		BH2-3E	08/13/99	60-62 ft.	21	14	10 U
		BH2-3E2	08/13/99	60-62 ft.	19	10 U	10 U
		BH2-3F	08/13/99	65-67 ft.	36	10 U	10 U
		BH2-3G	08/13/99	70-72 ft.	120	15	10 U
		BH2-3H	08/13/99	75-76 ft.	100	10 U	14
	BH2-4	BH2-4A	08/16/99	54-55 ft.	170	120	59
	BH2-5	BH2-5A	08/16/99	16-18 ft.	10 U	10 U	21
		BH2-5B	08/16/99	20-22 ft.	10 U	10 U	19
		BH2-5C	08/16/99	24-26 ft.	10 U	10 U	10 U
		BH2-5C2	08/16/99	24-26 ft.	10 U	10 U	12
	BH2-6	BH2-6A	08/16/99	9-11 ft.	1100	450	56
		BH2-6B	08/16/99	15-17 ft.	3700	210	74
		BH2-6C	08/16/99	20-22 ft.	870	1600	23
		BH2-6D	08/16/99	24-26 ft.	400	630	15
		BH2-6D2	08/16/99	24-26 ft.	410	690	14
		BH2-6E	08/16/99	30-32 ft.	170	710	10 U
		BH2-6F	08/17/99	35-37 ft.	85	670	10 U
		BH2-6G	08/17/99	40-42 ft.	370	1400	10 U
		BH2-6H	08/17/99	45-47 ft.	47	58	10 U
	BH2-7	BH2-7A	08/17/99	10-12 ft.	13	10 U	10 U
		BH2-7B	08/17/99	15-17 ft.	10 U	10 U	10 U
		BH2-7C	08/17/99	20-22 ft.	11	10 U	10 U
		BH2-7C2	08/17/99	20-22 ft.	11	10 U	10 U
		BH2-7D	08/17/99	25-27 ft.	10 U	10 U	10 U
		BH2-7E	08/17/99	30-32 ft.	22	10 U	10 U
		BH2-7F	08/17/99	35-37 ft.	11	10 U	10 U
		BH2-7G	08/17/99	40-41 ft.	11	14	10 U
		BH2-7H	08/17/99	45-46 ft.	10 U	10 U	10 U
	EP-99	EP-99A	8/12/99	57-59 ft.	10 U	10 U	45
		EP-99B	8/12/99	65-67 ft.	10 U	10 U	10 U

Table 2-20

**Summary of Soil Sample Results for Investigation Area 2
(Boneyard/Slag Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I	SSIA2-1	SSIA2-1A	7/14/97	0 ft.	400	14	1500
		SSIA2-1B	7/14/97	1.5 ft.	1200	56	180
	SSIA2-2	SSIA2-2A	7/14/97	0 ft.	840	150	2700
		SSIA2-2B	7/14/97	3 ft.	1600	450	10000
	RIBH-2	RIBH-2A	6/30/97	7 ft.	82	10 U	39
		RIBH-2B	6/30/97	10 ft.	20 U	10 U	29
		RIBH-2C	6/30/97	15 ft.	20 U	10 U	26
	RIBH-3	RIBH-3A	6/30/97	28 ft.	20 U	10 U	800
		RIBH-3A2	6/30/97	28 ft.	20 U	10 U	800
		RIBH-3B	6/30/97	35 ft.	25	10 U	20
		RIBH-3C	6/30/97	40 ft.	20 U	10 U	44
	RIBH-4	RIBH-4A	6/30/97	0 ft.	280	24	970
		RIBH-4B	6/30/97	10 ft.	29	10 U	140
		RIBH-4C	6/30/97	15 ft.	20 U	10 U	25
	RIBH-5	RIBH-5A	6/30/97	2 ft.	20 U	10 U	210
		RIBH-5B	6/30/97	8 ft.	20 U	10 U	17
		RIBH-5B2	6/30/97	8 ft.	20 U	10 U	19
		RIBH-5C	6/30/97	10 ft.	20 U	10 U	30
		RIBH-5D	6/30/97	12 ft.	34	10 U	22
		RIBH-5E	6/30/97	15 ft.	20 U	10 U	33
	RIBH-6	RIBH-6A	6/30/97	2 ft.	270	10 U	830
	EP-75	EP-75A	6/2/97	35 ft.	220	10 U	490
		EP-75B	6/2/97	40 ft.	120	10 U	120
		EP-75C	6/2/97	45 ft.	67	10 U	23
		EP-75D	6/2/97	50 ft.	45	10 U	29
		EP-75E	6/3/97	55 ft.	91	10 U	760
		EP-75F	6/3/97	60 ft.	73	10 U	17
		EP-75G	6/3/97	65 ft.	36	10 U	12
	EP-76	EP-76A	6/3/97	0 ft.	1800	420	9500
		EP-76B	6/3/97	1.5 ft.	420	10 U	3400
		EP-76B2	6/3/97	1.5 ft.	380	16	3500
		EP-76C	6/3/97	45 ft.	78	10 U	28
		EP-76D	6/3/97	50 ft.	29	10 U	20
		EP-76E	6/3/97	55 ft.	110	10 U	650
		EP-76F	6/3/97	60 ft.	20 U	10 U	37

Table 2-20

**Summary of Soil Sample Results for Investigation Area 2
(Boneyard/Slag Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	EP-81	EP-81A	6/6/97	5 ft.	150	15	790
		EP-81B	6/6/97	10 ft.	20 U	10 U	140
		EP-81C	6/6/97	15 ft.	20 U	10 U	14
		EP-81D	6/6/97	20 ft.	20 U	10 U	12
		EP-81E	6/6/97	25 ft.	20 U	10 U	11
	EP-85	EP-85A	6/12/97	5 ft.	59	10 U	150
		EP-85B	6/12/97	10 ft.	27	10 U	15
		EP-85C	6/12/97	15 ft.	22	10 U	27
		EP-85D	6/12/97	20 ft.	20 U	10 U	32

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH2-2 was abandoned and not sampled

Table 2-21

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-2
(Boneyard/Slag Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA2							
EP-125	5/7/01		0.013		0.005 U		0.003 U
	7/19/01	0.026	0.04	0.005 U	0.005 U	0.003 U	0.11
EP-126	5/8/01		0.021		0.005 U		0.009
	7/19/01	0.039	0.042	0.006	0.006	0.003 U	0.004 J4
EP-21	2/1/00		0.064 J4		0.005 U		0.007
	5/8/00		0.062		0.005 U		0.013
	8/16/00		0.068 J4		0.005 U		0.004
	8/16/00		0.054 J4		0.005 U		0.005
	11/14/00		0.036		0.005 U		0.005
	11/14/00		0.038		0.005 U		0.004
	2/26/01		0.067		0.011		0.029 J4
	2/26/01		0.061		0.009		0.023 J4
	5/16/01		0.057		0.005 U		0.006
	7/30/01	0.01	0.039	0.005 U	0.005 U	0.003 U	0.006
EP-22	1/26/00		1.2		0.011		0.1
	4/28/00		1.2		0.009		0.075
	8/7/00		1.5		0.013		0.006
	11/3/00		2.6		0.009		0.003 U
	2/14/01		3.4		0.009		0.004
	5/9/01		3		0.007		0.015
	7/19/01	3.7	3.9	0.006	0.007	0.003 U	0.045 J4
EP-53	8/11/97	51		1.3		0.003 U	
	2/4/98	63		1.4		0.003 U	
	2/1/00		45		1.2		0.011
	5/3/00		32		0.38		0.007
	8/16/00		35		1.3		0.008
	11/13/00		49		1.4		0.006
	2/21/01		37		1		0.003 U
	5/10/01		32		0.47		0.019
	7/30/01	30	27	0.19	0.22	0.003 U	0.008
EP-75	1/26/00		14		0.005 U		0.023
	4/28/00		16		0.007		0.006
	8/7/00		11		0.005		0.006
	11/7/00		9.4		0.009		0.018
	2/14/01		13		0.007		0.003
	5/9/01		14		0.006		0.003
	7/20/01	15	15	0.006	0.006	0.003 U	0.016
EP-76	1/26/00		1.3		0.005 U		0.011
	4/28/00		0.92		0.005 U		0.01
	8/7/00		1.1		0.005 U		0.007
	11/7/00		1.4		0.005 U		0.01
	2/14/01		1.5		0.005 U		0.014
	5/9/01		1.3		0.005 U		0.006
	7/20/01	1.1	1	0.005 U	0.005 U	0.003	0.007

Table 2-21

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-2
(Boneyard/Slag Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-99	8/9/00		6.5		0.005 U		0.036
	11/8/00		3.7		0.005 U		0.011
	2/22/01		6.5		0.007		0.3
	5/9/01						
	7/26/01						

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-22

**Summary of Soil Sample Results for Investigation Area 3
(Acid Plants 1 and 2 Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	BH3-1	BH3-1A	08/18/99	0-1 ft.	300	110	990
		BH3-1B	08/18/99	1-2 ft.	10 U	10 U	57
		BH3-1C	08/18/99	2-3 ft.	18	14	340
		BH3-1D	08/18/99	3-4 ft.	10 U	10 U	18
		BH3-1E	08/18/99	4-5 ft.	10 U	10 U	10 U
		BH3-1E2	08/18/99	4-5 ft.	10 U	10 U	10 U
		BH3-1F	08/23/99	25-27 ft.	10 U	10 U	10 U
		BH3-1G	08/23/99	30-32 ft.	24	10 U	10 U
		BH3-1H	08/23/99	35-37 ft.	22	10 U	10 U
		BH3-1I	08/23/99	40-42 ft.	28	10 U	10 U
		BH3-1J	08/23/99	45-47 ft.	19	10 U	10 U
		BH3-1J2	08/23/99	45-47 ft.	12	10 U	10 U
		BH3-1K	08/23/99	49-51 ft.	10 U	10 U	29
	BH3-2	BH3-2A	08/23/99	0-1 ft.	890	560	2500
		BH3-2B	08/23/99	1-2 ft.	10 U	10 U	52
		BH3-2B2	08/23/99	1-2 ft.	74	37	280
		BH3-2C	08/23/99	25-27 ft.	72	51	34
		BH3-2D	08/23/99	30-32 ft.	10 U	14	10 U
		BH3-2E	08/23/99	35-37 ft.	10 U	10 U	16
		BH3-2F	08/23/99	40-42 ft.	16	10 U	10 U
		BH3-2G	08/23/99	45-47 ft.	10 U	10 U	10 U
	BH-3-3	BH3-3A	08/24/99	40-42 ft.	10 U	10 U	18
		BH3-3B	08/24/99	45-47 ft.	18	13	10 U
	BH3-4	BH3-4A	08/24/99	0-1 ft.	64	37	1300
		BH3-4B	08/24/99	1-2 ft.	10 U	10 U	120
		BH3-4C	08/25/99	39-41 ft.	370	360	72
		BH3-4D	08/25/99	45-47 ft.	20	10 U	15
		BH3-4E	08/25/99	40-52 ft.	19	10 U	10 U
	BH3-5	BH3-5A	08/25/99	3-4.5 ft.	870	190	3800
		BH3-5A2	08/25/99	3-4.5 ft.	550	150	2400
		BH3-5B	08/25/99	31 ft.	2100	430	63
		BH3-5C	08/25/99	35 ft.	420	300	14
		BH3-5D	08/25/99	40 ft.	46	10 U	14
		BH3-5E	08/25/99	45 ft.	25	10 U	10 U
		BH3-5F	08/25/99	50-52 ft.	55	10 U	16
	BH3-6	BH3-6A	08/25/99	18-20 ft.	10 U	41	23
		BH3-6B	08/25/99	25-27 ft.	10 U	28	14
		BH3-6C	08/26/99	30-32 ft.	10 U	10 U	20
		BH3-6D	08/26/99	35-37 ft.	10 U	16	10 U

Table 2-22

**Summary of Soil Sample Results for Investigation Area 3
(Acid Plants 1 and 2 Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	BH3-6	BH3-6E	08/26/99	40-42 ft.	40	14	22
		BH3-6F	08/26/99	45-47 ft.	10 U	10 U	27
		BH3-6G	08/26/99	50-52 ft.	330	26	24
		BH3-6G2	08/26/99	50-52 ft.	380	26	29
		BH3-6H	08/26/99	55-57 ft.	1100	40	48
		BH3-6I	08/26/99	60-62 ft.	10 U	10 U	24
		BH3-6J	08/26/99	65-67 ft.	72	10 U	28
	BH3-7	BH3-7A	08/26/99	30-32 ft.	10 U	10 U	10 U
		BH3-7B	08/26/99	35-37 ft.	10 U	10 U	10 U
		BH3-7C	08/26/99	40-42 ft.	17	10 U	10 U
		BH3-7C2	08/26/99	40-42 ft.	10 U	10 U	10 U
		BH3-7D	08/26/99	45-47 ft.	18	10 U	38
		BH3-7E	08/26/99	50-52 ft.	15	10 U	46
		BH3-7F	08/26/99	55-57 ft.	56	10 U	10 U
		BH3-7G	08/26/99	60-62 ft.	10 U	10 U	41
		BH3-7H	08/26/99	65-67 ft.	50	10 U	63
		BH3-7I	08/27/99	69-70 ft.	10 U	10 U	12
	BH3-8	BH3-8A	08/31/99	55-57 ft.	10 U	10 U	15
		BH3-8B	08/31/99	60-62 ft.	180	42	33
		BH3-8B2	08/31/99	60-62 ft.	170	62	41
Phase I	SSIA3-1	SSIA3-1A	7/14/97	0 ft.	1900	510	7400
		SSIA3-1B	7/14/97	1.5 ft.	650	120	6900
	SSIA3-2	SSIA3-2A	7/14/97	0 ft.	20 U	25	220
		SSIA3-2B	7/14/97	1.5 ft.	35	19	550
		SSIA3-2C	7/14/97	3 ft.	270	52	1700
	SSIA3-3	SSIA3-3A	7/14/97	0 ft.	480	150	2000
		SSIA3-3B	7/14/97	1.5 ft.	20 U	10 U	37
		SSIA3-3C	7/14/97	3 ft.	28	10 U	95
		SSIA3-3D	7/14/97	4 ft.	20 U	10 U	45
	SSIA3-4	SSIA3-4A	7/14/97	0 ft.	7800	1600	7300
		SSIA3-4B	7/14/97	1.5 ft.	3000	330	5600
	SSIA3-5	SSIA3-5A	7/15/97	0 ft.	1000	280	5200
		SSIA3-5A2	7/15/97	0 ft.	950	250	4800
		SSIA3-5B	7/15/97	1.5 ft.	560	150	3300
	SSIA3-6	SSIA3-6A	7/15/97	0 ft.	2900	790	11000
		SSIA3-6B	7/15/97	1.5 ft.	230	67	1000
		SSIA3-6C	7/15/97	3 ft.	1200	240	4200

Table 2-22

**Summary of Soil Sample Results for Investigation Area 3
(Acid Plants 1 and 2 Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I	SSIA3-6	SSIA3-6D	7/15/97	4 ft.	580	130	2900
	SSIA3-7	SSIA3-7A	7/15/97	0 ft.	820	150	2200
		SSIA3-7B	7/15/97	1.5 ft.	2700	440	3700
		SSIA3-7C	7/15/97	3 ft.	2000	270	3300
		SSIA3-7D	7/15/97	4 ft.	1400	180	3300
	SSIA3-8	SSIA3-8A	7/15/97	0 ft.	3200	1100	8100
		SSIA3-8B	7/15/97	1.5 ft.	740	170	1600
		SSIA3-8C	7/15/97	3 ft.	64	17	230
		SSIA3-8D	7/15/97	4 ft.	680	100	1800
	SSIA3-9	SSIA3-9A	7/15/97	0 ft.	1900	1400	4500
		SSIA3-9B	7/15/97	1.5 ft.	570	340	2700
		SSIA3-9C	7/15/97	3 ft.	99	49	550
		SSIA3-9D	7/15/97	4 ft.	20 U	10 U	140
	SSIA3-10	SSIA3-10A	7/15/97	0 ft.	2800	360	19000
		SSIA3-10A2	7/15/97	0 ft.	3300	410	22000
		SSIA3-10B	7/15/97	1.5 ft.	980	680	25000
		SSIA3-10C	7/15/97	3 ft.	1400	370	14000
		SSIA3-10D	7/15/97	4 ft.	3500	550	20000
	EP-73	EP-73A	6/1/97	15 ft.	20 U	10 U	160
		EP-73B	6/1/97	20 ft.	20 U	10 U	2400
		EP-73C	6/1/97	32 ft.	20 U	10 U	230
		EP-73D	6/1/97	40 ft.	24	10 U	31
		EP-73E	6/1/97	45 ft.	20 U	10 U	140
		EP-73F	6/17/97	78 ft.	20 U	10 U	10 U

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-23

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-3
(Acid Plants 1 and 2)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA3							
EP-49	1/29/00		40		0.28		0.023
	4/28/00		42		0.053		0.007
	8/7/00		34		0.088		0.007
	11/7/00		33		0.038		0.003 U
	2/20/01		26		0.034		0.006
	2/20/01		26		0.033		0.006
	5/10/01		17		0.038		0.003
	7/26/01	21	11	0.035	0.15	0.003 U	0.003 U
EP-52	1/26/00		1.5		0.43		0.51
	4/28/00		1.5		0.51		0.96
	8/7/00		1.3		0.43		0.83
	11/7/00		1.7		0.45		1.5
	2/20/01		1.5		0.36		1.4
	5/10/01		1.7		0.45		1.6
	7/20/01	0.22	0.81	0.4	0.4	0.05	0.68
EP-54	1/26/00		57		0.57		0.022
	4/28/00		42		0.6		0.011
	8/7/00		34		0.66		0.018
	11/7/00		37		0.7		0.015
	2/20/01		25		0.45		0.008
	5/10/01		37		0.67		0.04
	7/26/01	22	26	0.34	0.45	0.003 U	0.013
EP-55	2/7/00		54		0.16		0.031
	5/4/00		54		1.3		0.6
	8/16/00		63		0.56		0.14
	11/14/00		51		0.38		0.08
	2/22/01		60		0.84		0.29
	5/11/01		63		2.3		0.44
	7/26/01	43	92	0.005 U	8.7	0.003 U	1.1
EP-73	1/26/00		0.019		0.005 U		0.003 U
	4/28/00		0.1		0.005		0.003 U
	8/7/00		0.027		0.005 U		0.003 U
	11/7/00		0.023		0.005 U		0.003 U
	2/16/01		0.03		0.005 U		0.003
	5/9/01		0.031		0.005 U		0.003 U
	7/20/01	0.041	0.054	0.005 U	0.005 U	0.003 U	0.004
	7/20/01	0.041	0.055	0.005 U	0.005 U	0.003 U	0.004
EP-114	1/31/00		214		2.7		6.6
	5/4/00		203		2.6		2.1
	8/14/00		240		1.7		1.1
	11/10/00		250		2.2		0.53
	5/4/01		292		3		0.87
	7/16/01	227	280	0.12	2.2	0.003 U	0.41

Table 2-23

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-3
(Acid Plants 1 and 2)
El Paso Asarco Smelter, Remedial Investigation**

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/
or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	BH4-1	BH4-1A	11/17/99	0-1 ft.	340	110	3700
		BH4-1A2	11/17/99	0-1 ft.	240	66	3500
		BH4-1B	11/17/99	1-2 ft.	260	77	4100
		BH4-1C	11/17/99	2-3 ft.	200	60	2800
		BH4-1D	11/17/99	3-4 ft.	170	83	3300
		BH4-1E	11/17/99	4-5 ft.	140	54	2200
		BH4-1F	11/17/99	10-12 ft.	11	10 U	97
	BH4-2	BH4-2A	11/18/99	0-1 ft.	760	380	6500
		BH4-2B	11/18/99	1-2 ft.	650	320	4800
		BH4-2C	11/18/99	2-3 ft.	350	120	2300
		BH4-2D	11/18/99	3-4 ft.	200	83	1400
		BH4-2E	11/18/99	4-5 ft.	180	72	1400
		BH4-2F	11/18/99	10-12 ft.	23	10 U	30
		BH4-2G	11/18/99	15-17 ft.	13	10 U	36
	BH4-3	BH4-3A	11/18/99	10-11 ft.	54	10 U	390
	BH4-4	BH4-4A	11/18/99	0-1 ft.	11000	2600	22000
		BH4-4A2	11/18/99	0-1 ft.	7100	1700	15000
		BH4-4B	11/18/99	1-2 ft.	2000	580	5300
		BH4-4C	11/18/99	2-3 ft.	3200	900	7600
		BH4-4D	11/18/99	3-4 ft.	1900	530	5300
		BH4-4E	11/18/99	4-5 ft.	410	82	1300
		BH4-4F	11/18/99	10-12 ft.	100	21	270
	BH4-5	BH4-5A	11/18/99	0-1 ft.	4200	1500	8600
		BH4-5A2	11/18/99	0-1 ft.	4100	1400	8300
		BH4-5B	11/18/99	1-2 ft.	2500	930	5300
		BH4-5C	11/18/99	2-3 ft.	2000	700	4500
		BH4-5D	11/18/99	3-4 ft.	910	100	3600
		BH4-5E	11/18/99	4-5 ft.	300	84	950
		BH4-5F	11/18/99	10-12 ft.	130	12	470
	BH4-6	BH4-6A	11/18/99	0-1 ft.	310	190	1500
		BH4-6B	11/18/99	1-2 ft.	50	24	380
		BH4-6C	11/18/99	2-3 ft.	150	60	890
		BH4-6D	11/18/99	3-4 ft.	690	190	2800
		BH4-6E	11/18/99	4-5 ft.	29	10 U	210
		BH4-6E2	11/18/99	4-5 ft.	19	18	200
		BH4-6F	11/18/99	10-12 ft.	43	10 U	140
	EP-114	EP-114A	11/15/99	2.5-3.5 ft.	600	200	840
		EP-114B	11/15/99	3.5-4.5 ft.	310	460	270

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-114	EP-114C	11/15/99	4.5-5.5 ft.	18	10 U	64
		EP-114D	11/15/99	10-12 ft.	110	24	210
	EP-115	EP-115A	11/16/99	0-1 ft.	2800	850	7000
		EP-115B	11/16/99	1-2 ft.	950	400	2800
		EP-115C	11/16/99	2-3 ft.	830	380	2300
		EP-115D	11/16/99	3-4 ft.	1100	420	2800
		EP-115E	11/16/99	4-5 ft.	750	320	1700
		EP-115F	11/16/99	10-12 ft.	360	270	510
	EP-116	EP-116A	11/16/99	0-1 ft.	18000	530	40000
		EP-116A2	11/16/99	0-1 ft.	11000	340	19000
		EP-116B	11/16/99	1-2 ft.	9800	360	26000
		EP-116C	11/16/99	2-2.5 ft.	9200	360	23000
		EP-116D	11/16/99	5-7 ft.	6800	960	16000
		EP-116E	11/16/99	10-12 ft.	5300	1200	13000
	EP-117	EP-117A	11/16/99	0-1 ft.	2300	480	3500
		EP-117B	11/16/99	1-2 ft.	1700	300	2300
		EP-117C	11/16/99	2-3 ft.	2300	460	4700
		EP-117D	11/16/99	3-4 ft.	1200	230	2900
		EP-117E	11/16/99	5-6 ft.	140	10 U	230
		EP-117F	11/16/99	10-12 ft.	210	10 U	110
		EP-117F2	11/16/99	10-12 ft.	500	66	1100
	EP-118	EP-118A	11/17/99	0-1 ft.	1300	340	10000
		EP-118A2	11/17/99	0-1 ft.	1000	240	7400
		EP-118B	11/17/99	1-2 ft.	720	200	5900
		EP-118C	11/17/99	2-3 ft.	120	56	1700
		EP-118D	11/17/99	3-4 ft.	61	29	950
		EP-118E	11/17/99	4-5 ft.	75	43	1300
		EP-118F	11/17/99	15-15.5 ft.	54	20	630
Phase I	SSIA4-1	SSIA4-1A	10/27/97	0 ft.	3100	540	11000
		SSIA4-1B	10/27/97	1.5 ft.	97	66	200
		SSIA4-1C	10/27/97	3 ft.	40	42	390
		SSIA4-1D	10/27/97	4 ft.	20 U	38	120
	SSIA4-2	SSIA4-2A	10/27/97	0 ft.	4900	1000	11000
		SSIA4-2A2	10/27/97	0 ft.	6200	1200	11000
		SSIA4-2B	10/27/97	1.5 ft.	7000	1200	12000
		SSIA4-2C	10/27/97	3 ft.	100	22	58
		SSIA4-2D	10/27/97	4 ft.	59	15	27
	SSIA4-3	SSIA4-3A	10/27/97	0 ft.	4100	1300	9300
		SSIA4-3B	10/27/97	1.5 ft.	2900	1500	8400

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA4-3	SSIA4-3C	10/27/97	3 ft.	2000	1300	2900
		SSIA4-3D	10/27/97	4 ft.	1200	37	1800
	SSIA4-4	SSIA4-4A	10/28/97	0 ft.	1200	360	7500
		SSIA4-4B	10/28/97	1.5 ft.	1100	280	7500
		SSIA4-4C	10/28/97	3 ft.	320	69	2900
		SSIA4-4D	10/28/97	4 ft.	600	170	5800
	SSIA4-5	SSIA4-5A	10/28/97	0 ft.	3500	840	21000
		SSIA4-5A2	10/28/97	0 ft.	3400	870	23000
		SSIA4-5B	10/28/97	1.5 ft.	370	54	2600
		SSIA4-5C	10/28/97	3 ft.	650	210	7100
		SSIA4-5D	10/28/97	4 ft.	45	10 U	430
	SSIA4-6	SSIA4-6A	10/28/97	0 ft.	5900	1300	15000
		SSIA4-6B	10/28/97	1.5 ft.	610	520	4000
		SSIA4-6C	10/28/97	3 ft.	37	13	110
		SSIA4-6D	10/28/97	4 ft.	20 U	10 U	38
	SSIA4-7	SSIA4-7A	10/28/97	0 ft.	17000	350	49000
		SSIA4-7A2	10/28/97	0 ft.	18000	360	51000
		SSIA4-7B	10/28/97	1.5 ft.	2200	310	12000
		SSIA4-7C	10/28/97	3 ft.	1900	100	7500
		SSIA4-7D	10/28/97	4 ft.	1500	430	6800
	SSIA4-8	SSIA4-8A	10/28/97	0 ft.	3300	980	25000
		SSIA4-8B	10/28/97	1.5 ft.	990	190	4100
		SSIA4-8C	10/28/97	3 ft.	220	44	960
		SSIA4-8D	10/28/97	4 ft.	200	30	730
	SSIA4-9	SSIA4-9A	10/28/97	0 ft.	3000	970	11000
		SSIA4-9B	10/28/97	1.5 ft.	1300	600	3200
		SSIA4-9C	10/28/97	3 ft.	920	300	1100
		SSIA4-9D	10/28/97	4 ft.	330	48	430
	SSIA4-10	SSIA4-10A	10/28/97	0 ft.	840 J4	290	5100
		SSIA4-10A2	10/28/97	0 ft.	1500 J4	380	6800
		SSIA4-10B	10/28/97	1.5 ft.	880 J4	140	2800
		SSIA4-10C	10/28/97	3 ft.	380 J4	68	1200
		SSIA4-10D	10/28/97	4 ft.	400 J4	10 U	190
	SSIA4-11	SSIA4-11A	10/28/97	0 ft.	1800	500	8900
		SSIA4-11B	10/28/97	1.5 ft.	680	55	1300
		SSIA4-11C	10/28/97	3 ft.	95	10 U	130
		SSIA4-11D	10/28/97	4 ft.	35	10 U	72

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA4-12	SSIA4-12A	10/28/97	0 ft.	4800	930	13000
		SSIA4-12B	10/28/97	1.5 ft.	20 U	18	10000
		SSIA4-12C	10/28/97	3 ft.	20 U	10 U	2300
		SSIA4-12D	10/28/97	4 ft.	20 U	10 U	3200
	SSIA4-13	SSIA4-13A	10/28/97	0 ft.	860	320	11000
		SSIA4-13B	10/28/97	1.5 ft.	790	320	12000
		SSIA4-13C	10/28/97	3 ft.	78	170	1000
	SSIA4-14	SSIA4-14A	10/28/97	0 ft.	1600	640	14000
		SSIA4-14A2	10/28/97	0 ft.	1500	670	15000
		SSIA4-14B	10/28/97	1.5 ft.	490	190	4500
		SSIA4-14C	10/28/97	3 ft.	20 U	16	280
		SSIA4-14D	10/28/97	4 ft.	110	82	1900
	SSIA4-15	SSIA4-15A	10/28/97	0 ft.	480	300	6800
		SSIA4-15B	10/28/97	1.5 ft.	440	240	5300
		SSIA4-15C	10/28/97	3 ft.	20 U	13	540
		SSIA4-15D	10/28/97	4 ft.	74	23	930
	SSIA4-16	SSIA4-16A	10/28/97	0 ft.	520	350	5900
		SSIA4-16B	10/30/97	1.5 ft.	66	30	710
		SSIA4-16C	10/30/97	3 ft.	20 U	10	210
		SSIA4-16D	10/30/97	4 ft.	20 U	10 U	18
	SSIA4-17	SSIA4-17A	10/30/97	0 ft.	220	76	2500
		SSIA4-17A2	10/30/97	0 ft.	240	75	2100
		SSIA4-17B	10/30/97	1.5 ft.	160	57	1900
		SSIA4-17C	10/30/97	3 ft.	36	12	27
		SSIA4-17D	10/30/97	4 ft.	97	23	1000
	SSIA4-18	SSIA4-18A	10/30/97	0 ft.	160	59	1400
		SSIA4-18B	10/30/97	1.5 ft.	150	85	1200
		SSIA4-18C	10/30/97	3 ft.	41	10 U	31
		SSIA4-18D	10/30/97	4 ft.	38	11	100
	SSIA4-19	SSIA4-19A	10/30/97	0 ft.	52	22	560
		SSIA4-19B	10/30/97	1.5 ft.	24	10	440
		SSIA4-19C	10/30/97	3 ft.	20 U	10 U	23
		SSIA4-19D	10/30/97	4 ft.	20 U	10 U	230
	SSIA4-20	SSIA4-20A	10/30/97	0 ft.	75	32	1300
		SSIA4-20A2	10/30/97	0 ft.	100	42	1400
		SSIA4-20B	10/30/97	1.5 ft.	20 U	16	550
		SSIA4-20C	10/30/97	3 ft.	20 U	10 U	22

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA4-20	SSIA4-20D	10/30/97	4 ft.	20 U	10 U	460
	SSIA4-21	SSIA4-21A	10/30/97	0 ft.	160	63	2500
		SSIA4-21B	10/30/97	1.5 ft.	210	73	3200
		SSIA4-21C	10/30/97	3 ft.	48	15	1100
		SSIA4-21D	10/30/97	4 ft.	24	11	560
	SSIA4-22	SSIA4-22A	10/30/97	0 ft.	140	62	2200
		SSIA4-22B	10/30/97	1.5 ft.	45	22	1200
		SSIA4-22C	10/30/97	3 ft.	20 U	10 U	21
		SSIA4-22D	10/30/97	4 ft.	20 U	10 U	210
	SSIA4-23	SSIA4-23A	10/30/97	0 ft.	250	91	4600
		SSIA4-23A2	10/30/97	0 ft.	270	97	5000
		SSIA4-23B	10/30/97	1.5 ft.	20 U	13	370
		SSIA4-23C	10/30/97	3 ft.	20 U	10 U	75
		SSIA4-23D	10/30/97	4 ft.	29	15	520
	SSIA4-24	SSIA4-24A	10/30/97	0 ft.	120	38	1800
		SSIA4-24B	10/30/97	1.5 ft.	20 U	10 U	260
		SSIA4-24C	10/30/97	3 ft.	22	10 U	190
		SSIA4-24D	10/30/97	4 ft.	20 U	10 U	75
	SSIA4-25	SSIA4-25A	10/30/97	0 ft.	380	200	9400
		SSIA4-25B	10/30/97	1.5 ft.	20 U	10 U	370
		SSIA4-25C	10/30/97	3 ft.	20 U	10 U	200
		SSIA4-25D	10/30/97	4 ft.	120	13	620
	SSIA4-26	SSIA4-26A	10/30/97	0 ft.	320	82	3800
		SSIA4-26A2	10/30/97	0 ft.	300	89	3600
		SSIA4-26B	10/30/97	1.5 ft.	20 U	10 U	180
		SSIA4-26C	10/30/97	3 ft.	20 U	10 U	270
		SSIA4-26D	10/30/97	4 ft.	20 U	11	550
	SSIA4-27	SSIA4-27A	10/30/97	0 ft.	370	140	5300
		SSIA4-27B	10/30/97	1.5 ft.	25	10 U	82
	SSIA4-28	SSIA4-28A	10/30/97	0 ft.	190	42	1600
		SSIA4-28B	10/30/97	1.5 ft.	20 U	10 U	63
	SSIA4-29	SSIA4-29A	10/30/97	0 ft.	490	110	3900
		SSIA4-29A2	10/30/97	0 ft.	520	100	3000
		SSIA4-29B	10/30/97	1.5 ft.	20 U	10 U	330
	SSIA4-30	SSIA4-30A	10/30/97	0 ft.	200	16	980

Table 2-24

**Summary of Soil Sample Results for Investigation Area 4
(Front Slope/Western Facility Boundary Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA4-30	SSIA4-30B	10/30/97	1.5 ft.	250	83	2700

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-25

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-4
Front Slope/Western Facility Boundary Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA4							
EP-114	1/31/00		214		2.7		6.6
	5/4/00		203		2.6		2.1
	8/14/00		240		1.7		1.1
	11/10/00		250		2.2		0.53
	5/4/01		292		3		0.87
	7/16/01	227	280	0.12	2.2	0.003 U	0.41
EP-115	1/31/00		0.26		0.19		0.02
	5/4/00		0.25		0.15		0.084
	8/14/00		0.25		0.14		0.037
	11/10/00		0.45		0.17		0.19
	2/23/01						
	5/4/01						
	7/16/01	0.29	0.29	0.13	0.13	0.025	0.077
EP-116	1/31/00		4.9		1.5		4.1
	5/4/00		3.3		0.66		1.4
	8/14/00		3.1		0.4		0.55
	11/10/00		1.5		0.8		1.1
	2/22/01		6		1.6		4.2
	5/4/01		6.2		1.4		3.7
	7/16/01	3.2	11	0.37	3.2	0.02	9.5
EP-117	1/31/00		11		2.7		10
	5/4/00		7.2		0.89		3.5
	8/14/00		5.8		0.54		1.8
	11/10/00		6.1		0.67		2.4
	2/22/01		6.4		1.2		4.1
	5/4/01		11		1.7		4.5
	7/16/01	6.6	7.4	0.12	0.66	0.007	2
EP-118	1/31/00		0.43		0.071		2.5
	5/4/00		0.21		0.019		0.66
	8/14/00		0.22		0.005 U		0.12
	11/10/00		3		0.012		0.36
	2/22/01		1.4		0.061		1.4
	5/4/01		0.52		0.014		0.49
	7/17/01	0.18	0.45	0.005 U	0.026	0.003 U	1.1
EP-20	1/31/00		0.97		0.076		0.004
	1/31/00		0.9		0.066		0.007
	5/4/00		0.76		0.068		0.003 U
	5/4/00		0.78		0.063		0.003 U
	8/2/00		0.76		0.047		0.005 U
	10/30/00		0.86		0.07		0.003 U,UJ4
	2/22/01		0.98		0.093		0.006
	5/16/01		0.93		0.087		0.006
	5/16/01		0.92		0.091		0.004
	7/17/01	0.97	0.96	0.063	0.073	0.003 U	0.011

Table 2-25

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-4
Front Slope/Western Facility Boundary Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-20	7/17/01	0.96	0.96	0.063	0.073	0.003 U	0.011
EP-29	1/31/00		0.33		0.005 U		0.01
	5/4/00		0.38		0.005 U		0.034
	8/2/00		0.28		0.005 U		0.009
	10/30/00		0.28		0.005 U		0.007 J4
	2/22/01		0.32		0.005 U		0.018
	5/16/01		0.27		0.005 U		0.003 U
	7/17/01	0.27	0.28	0.005 U	0.005 U	0.003 U	0.01
EP-35	1/31/00		0.92		0.005 U		0.033
	5/4/00		0.51		0.005 U		0.008
	8/2/00		0.62		0.005 U		0.011
	10/30/00		0.73		0.005 U		0.007 J4
	2/22/01		0.65		0.005 U		0.028
	5/16/01		0.67		0.005 U		0.008
	7/17/01	0.59	0.68	0.005 U	0.005 U	0.003 U	0.013
EP-71	1/24/00		0.11		0.005 U		0.008 UJ1
	4/24/00		0.11		0.005 U		0.003 U
	8/3/00		0.11		0.005 U		0.005 U
	8/3/00		0.11		0.005 U		0.005 U
	11/1/00		0.11		0.005 U		0.003 U
	2/9/01		0.093		0.005 U		0.003 U
	2/9/01		0.11		0.005 U		0.003 U
	5/7/01		0.11		0.005 U		0.003 U
	7/18/01	0.11	0.12	0.005 U	0.005 U	0.003 U	0.003 U
	7/18/01	0.12	0.12	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-26

**Summary of Soil Sample Results for Investigation Area 5
(Historic Smeltertown Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	EP-119	EP-119A	4/2/01	0	160	35	800
		EP-119B	4/2/01	1	64	20	550
		EP-119C	4/2/01	2	91	21	660
		EP-119D	4/2/01	3	18	10 U	36
		EP-119E	4/2/01	4	31	10 U	97
		EP-119F	4/2/01	10	27	10 U	41
	EP-122	EP-122A1	4/12/01	0-1 ft.	200	74	1400
		EP-122A2	4/12/01	0-1 ft.	220	86	1500
		EP-122B	4/12/01	1-2 ft.	110	53	890
		EP-122C	4/12/01	2-3 ft.	42	11	230
		EP-122D	4/12/01	3-4 ft.	37	10 U	100
		EP-122E	4/12/01	4-5 ft.	29	10 U	42
	EP-127	EP-127A	4/27/01	0-1 ft.	46	16	420
		EP-127B	4/27/01	1-2 ft.	83	20	590
		EP-127C	4/27/01	2-3 ft.	38	12	110
		EP-127D	4/27/01	3-4 ft.	46	10 U	45
		EP-127E1	4/27/01	4-5 ft.	29	10 U	79
		EP-127E2	4/27/01	4-5 ft.	60	19	290
	EP-128	EP-128A	4/27/01	0-1 ft.	120	23	2000
		EP-128B	4/27/01	1-2 ft.	28	10	330
		EP-128C	4/27/01	2-3 ft.	68	10 U	210
		EP-128C	4/27/01	2-3 ft.	1566	1031	6225
		EP-128D	4/27/01	3-4 ft.	13	10 U	20
	EP-132	EP-132A1	6/4/01	0-1 ft.	110	22	890
		EP-132A2	6/4/01	0-1 ft.	92	24	840
		EP-132B	6/4/01	1-2 ft.	230	48	1800
		EP-132C	6/4/01	2-3 ft.	51	19	400
		EP-132D	6/4/01	3-4 ft.	18	10 U	38
		EP-132E	6/4/01	4-5 ft.	29	10 U	56
		EP-132F	6/4/01	10-11 ft.	35	13	99
		EP-132G	6/4/01	15-16 ft.	31	11	42
Phase II	EP-111	EP-111A	10/27/99	0	33	27	430
		EP-111B	10/27/99	1	10 U	10 U	52
		EP-111C	10/27/99	2	50	12	600
		EP-111D	10/27/99	3	65	10 U	330
		EP-111E	10/27/99	4	35	13	240

Table 2-26

**Summary of Soil Sample Results for Investigation Area 5
(Historic Smeltertown Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-112	EP-112A	10/27/99	0	84	32	1200
		EP-112B	10/27/99	1	86	54	1500
		EP-112C	10/27/99	2	10 U	23	430
		EP-112D	10/27/99	3	10 U	10 U	22
		EP-112E	10/27/99	4	10 U	10 U	27
	EP-113	EP-113A	10/28/99	0	10 U	10 U	110
		EP-113B	10/28/99	1	26	20	630
		EP-113C	10/28/99	2	33	10 U	310
		EP-113D	10/28/99	3	24	11	160
		EP-113E	10/28/99	4	10 U	10 U	16
Phase I	RIBH-7	RIBH-7A	7/1/97	0 ft.	53	28	1000
		RIBH-7B	7/1/97	5 ft.	20 U	10 U	19
		RIBH-7C	7/1/97	10 ft.	20 U	10 U	24
	RIBH-8	RIBH-8A	7/1/97	0 ft.	120	120	3300
		RIBH-8B	7/1/97	5 ft.	20 U	10 U	29
		RIBH-8C	7/1/97	10 ft.	20 U	10 U	17
		RIBH-8C2	7/1/97	10 ft.	20 U	10 U	16
	RIBH-9	RIBH-9A	7/1/97	0 ft.	63	46	1100
		RIBH-9B	7/1/97	5 ft.	20 U	10 U	11
		RIBH-9C	7/1/97	10 ft.	20 U	10 U	33
	RIBH-10	RIBH-10A	7/1/97	0 ft.	46	10 U	400
		RIBH-10A2	7/1/97	0 ft.	28	20	340
		RIBH-10B	7/1/97	5 ft.	20 U	10 U	40
		RIBH-10C	7/1/97	10 ft.	20 U	10 U	21
	SSIA5-1	SSIA5-1A	7/7/97	0 ft.	240	130	4200
		SSIA5-1B	7/8/97	1.5 ft.	28	17	420
		SSIA5-1C	7/8/97	3 ft.	20 U	10 U	21
		SSIA5-1D	7/8/97	4 ft.	20 U	10 U	58
	SSIA5-2	SSIA5-2A	7/8/97	0 ft.	71	66	580
		SSIA5-2B	7/8/97	1.5 ft.	22	10 U	44
		SSIA5-2C	7/8/97	3 ft.	20 U	10 U	95
		SSIA5-2D	7/8/97	4 ft.	27	10 U	82
	SSIA5-3	SSIA5-3A	7/8/97	0 ft.	130	110	2700
		SSIA5-3B	7/8/97	1.5 ft.	20 U	16	850
		SSIA5-3C	7/8/97	3 ft.	20 U	10 U	410
		SSIA5-3D	7/8/97	4 ft.	60	17	590

Table 2-26

**Summary of Soil Sample Results for Investigation Area 5
(Historic Smeltertown Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA5-4	SSIA5-4A	7/8/97	0 ft.	37	41	1100
		SSIA5-4B	7/8/97	1.5 ft.	20 U	44	1800
		SSIA5-4C	7/8/97	3 ft.	100	46	2200
		SSIA5-4D	7/8/97	4 ft.	20 U	10 U	81
		SSIA5-5A	7/8/97	0 ft.	20 U	36	1200
		SSIA5-5B	7/8/97	1.5 ft.	20 U	10 U	210
		SSIA5-5C	7/8/97	3 ft.	20 U	10 U	160
		SSIA5-5D	7/8/97	4 ft.	20 U	10 U	63
	SSIA5-6	SSIA5-6A	7/8/97	0 ft.	20 U	14	370
		SSIA5-6B	7/8/97	1.5 ft.	20 U	10	370
		SSIA5-6C	7/8/97	3 ft.	20 U	13	430
		SSIA5-6D	7/8/97	4 ft.	20 U	15	500
	SSIA5-7	SSIA5-7A	7/8/97	0 ft.	110	56	1700
		SSIA5-7B	7/8/97	1.5 ft.	20 U	10 U	68 J4
		SSIA5-7B2	7/8/97	1.5 ft.	20 U	10 U	10 J4
		SSIA5-7C	7/8/97	3 ft.	20 U	10 U	27 J4
		SSIA5-7D	7/8/97	4 ft.	20 U	10 U	27 J4
	SSIA5-8	SSIA5-8A	7/8/97	0 ft.	31	42	1200
		SSIA5-8B	7/8/97	1.5 ft.	32	10 U	30
		SSIA5-8C	7/8/97	3 ft.	20	10 U	32
		SSIA5-8D	7/8/97	4 ft.	20 U	10 U	25
	SSIA5-9	SSIA5-9A	7/8/97	0 ft.	90	39	800
		SSIA5-9B	7/8/97	1.5 ft.	20 U	10 U	110
		SSIA5-9C	7/8/97	3 ft.	20 U	10 U	46
		SSIA5-9D	7/8/97	4 ft.	20 U	10 U	30
	SSIA5-10	SSIA5-10A	7/8/97	0 ft.	130	110	2800
		SSIA5-10B	7/8/97	1.5 ft.	20 U	10 U	250
		SSIA5-10C	7/8/97	3 ft.	20 U	10 U	300
		SSIA5-10D	7/8/97	4 ft.	20 U	10 U	200
	SSIA5-11	SSIA5-11A	7/8/97	0 ft.	20 U	22	740
		SSIA5-11B	7/8/97	1.5 ft.	20 U	23	470
		SSIA5-11C	7/8/97	3 ft.	20 U	10 U	230
		SSIA5-11D	7/8/97	4 ft.	20 U	10 U	31
	SSIA5-12	SSIA5-12A	7/8/97	0 ft.	21	19	540
		SSIA5-12B	7/8/97	1.5 ft.	20 U	11	440
		SSIA5-12C	7/8/97	3 ft.	20 U	10 U	38
		SSIA5-12D	7/8/97	4 ft.	20 U	10 U	110

Table 2-26

**Summary of Soil Sample Results for Investigation Area 5
(Historic Smeltertown Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA5-13	SSIA5-13A	7/8/97	0 ft.	87	36	830
		SSIA5-13B	7/8/97	1.5 ft.	20 U	10 U	110
		SSIA5-13C	7/8/97	3 ft.	20 U	10 U	160
		SSIA5-13D	7/8/97	4 ft.	20 U	10 U	35
	SSIA5-14	SSIA5-14A	7/8/97	0 ft.	78	10 U	170
		SSIA5-14B	7/8/97	1.5 ft.	10	10 U	130
		SSIA5-14C	7/8/97	3 ft.	20 U	10 U	12
		SSIA5-14D	7/8/97	4 ft.	20 U	10 U	11
	SSIA5-15	SSIA5-15A	7/14/97	0 ft.	86	20	420
		SSIA5-15A2	7/14/97	0 ft.	70	19	420
		SSIA5-15B	7/14/97	1.5 ft.	20 U	10 U	34
		SSIA5-15B2	7/14/97	1.5 ft.	20 U	10 U	38
		SSIA5-15C	7/14/97	3 ft.	20 U	10 U	13
		SSIA5-15D	7/14/97	4 ft.	20 U	10 U	22
	SSIA5-16	SSIA5-16A	7/14/97	0 ft.	27 J4	24	610
		SSIA5-16A2	7/14/97	0 ft.	68 J4	40	830
		SSIA5-16B	7/14/97	1.5 ft.	20 U	10 U	150
		SSIA5-16B2	7/14/97	1.5 ft.	20 U	10 U	140
		SSIA5-16C	7/14/97	3 ft.	20 U	10 U	11
		SSIA5-16D	7/14/97	4 ft.	20 U	10 U	18
	SSIA5-17	SSIA5-17A	7/14/97	0 ft.	83	85	1100
		SSIA5-17B	7/14/97	1.5 ft.	24	10 U	140
		SSIA5-17C	7/14/97	3 ft.	24	10 U	63
		SSIA5-17D	7/14/97	4 ft.	20 U	10 U	24
	SSIA5-18	SSIA5-18A	7/14/97	0 ft.	26	11	200
		SSIA5-18B	7/14/97	1.5 ft.	20 U	10 U	15
		SSIA5-18C	7/14/97	3 ft.	20 U	10 U	32
		SSIA5-18D	7/14/97	4 ft.	20 U	10 U	26
	SSIA5-19	SSIA5-19A	7/14/97	0 ft.	160	150	2400
		SSIA5-19B	7/14/97	1.5 ft.	20 U	29	310
		SSIA5-19C	7/14/97	3 ft.	20 U	13	860
		SSIA5-19D	7/14/97	4 ft.	20 U	15	810
	EP-80	EP-80A	6/6/97	0 ft.	26	10 U	95
		EP-80B	6/6/97	5 ft.	20 U	10 U	46
		EP-80C	6/6/97	10 ft.	20 U	10 U	32
		EP-80D	6/6/97	15 ft.	20 U	10 U	10
		EP-80E	6/6/97	20 ft.	20 U	10 U	23

Table 2-26

**Summary of Soil Sample Results for Investigation Area 5
(Historic Smeltertown Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	EP-80	EP-80F	6/6/97	25 ft.	20 U	10 U	15

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-27

Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-5
(Historic Smeltertown Area)
El Paso Asarco Smelter, Remedial Investigation

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA5							
EP-57	2/7/00		0.43		0.005 U		0.004
	5/8/00		0.37		0.005 U		0.006
	8/15/00		0.35 J4		0.005 U		0.003 U
	11/13/00		0.25		0.005 U		0.003
	2/23/01		0.41		0.005 U		0.003 UJ1
	5/16/01		0.32		0.005 U		0.003 U
	7/30/01	0.17	0.38	0.005 U	0.005 U	0.003 U	0.003 U
EP-58	2/7/00		3.4		0.005 U		0.016
	5/8/00		3.6		0.005 U		0.013
	5/8/00		3.7		0.005 U		0.01
	8/15/00		3.1 J4		0.005 U		0.006
	8/15/00		5.8 J4		0.005 U		0.005
	11/13/00		3.4		0.005 U		0.003
	2/23/01		3.2		0.005 U		0.003 U
	2/23/01		3.5		0.005 U		0.003 U
	5/16/01		3.7		0.005 U		0.003 U
	7/30/01	3.2	3.3	0.005 U	0.005 U	0.003 U	0.008
EP-59	1/28/00		2.9		0.005 U		0.003
	5/3/00		2.4		0.005 U		0.003
	8/10/00		2.3		0.005 U		0.003 U
	8/10/00		2.4		0.005 U		0.003 U
	10/31/00		2.5		0.005 U		0.004
	2/21/01		2.5		0.005		0.003 U
	2/21/01		2.2		0.005		0.003 U
	5/15/01		2.2		0.005 U		0.003 U
	7/27/01	2.1	2	0.005 U	0.005 U	0.003 U	0.003 U
EP-60	1/28/00		0.008		0.005 U		0.003 U
	5/3/00		0.009		0.005 U		0.003 U
	8/10/00		0.012		0.005 U		0.006 UJ1
	10/31/00		0.012		0.005 U		0.003 U
	2/21/01		0.021		0.005 U		0.003 U
	5/15/01		0.012		0.005 U		0.003 U
	7/27/01	0.022	0.025	0.005 U	0.005 U	0.003 U	0.003 U
EP-61	2/7/00		0.026		0.005 U		0.003 U
	5/8/00		0.013		0.005 U		0.004
	8/15/00		0.007 J4		0.005 U		0.003 U
	11/13/00		0.01		0.005 U		0.004
	11/13/00		0.009		0.005 U		0.003 U
	2/23/01		0.011		0.005 U		0.003 U
	5/16/01		0.023		0.005 U		0.003 U
	7/30/01	0.011	0.008	0.005 U	0.005 U	0.003 U	0.003 U
EP-62	1/28/00		0.82		0.005 U		0.003 U
	5/3/00		0.87		0.005 U		0.004
	8/10/00		1.1		0.005 U		0.003 U

Table 2-27

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-5
(Historic Smeltertown Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-62	10/31/00		1.4		0.005 U		0.003 U
	2/21/01		1.1		0.01		0.003 U
	5/15/01		1.3		0.005 U		0.003 U
	7/27/01	1.1	1.2	0.005 U	0.005 U	0.003 U	0.003 U
EP-63	1/28/00		0.022		0.005 U		0.003
	5/3/00		0.025		0.005 U		0.007
	5/3/00		0.026		0.005 U		0.004
	8/10/00		0.021		0.005 U		0.01 UJ1
	10/31/00		0.028		0.005 U		0.013
	2/21/01		0.041		0.005 U		0.027
	5/15/01		0.03		0.005 U		0.034
	5/15/01		0.028		0.005 U		0.036
	7/27/01	0.041	0.047	0.005 U	0.005 U	0.003 U	0.003 U
EP-64	1/28/00		0.043		0.005 U		0.003
	5/3/00		0.052		0.005 U		0.005
	8/10/00		0.049		0.005 U		0.003 U
	10/31/00		0.051		0.005 U		0.003 U
	2/21/01		0.096		0.009		0.004
	5/15/01		0.057		0.005 U		0.003 U
	7/27/01	0.1	0.11	0.005 U	0.005 U	0.003 U	0.003 U
EP-65	2/7/00		0.02		0.005 U		0.003 U
	2/7/00		0.018		0.005 U		0.003 U
	5/8/00		0.012		0.005 U		0.003 U
	8/15/00		0.006 J4		0.005 U		0.003
	11/13/00		0.005 U		0.005 U		0.003 U
	2/23/01		0.006		0.005 U		0.003 U
	5/16/01		0.059		0.005 U		0.003 U
	7/30/01	0.006	0.005	0.005 U	0.005 U	0.003 U	0.003 U
	7/30/01	0.005	0.005	0.005 U	0.005 U	0.003 U	0.003 U
EP-66	1/28/00		10		0.005 U		0.005
	5/3/00		8.8		0.005 U		0.003 U
	8/10/00		8.5		0.005 U		0.006 UJ1
	10/31/00		8.1		0.005 U		0.005
	2/21/01		7.5		0.011		0.003
	5/15/01		8.8		0.005 U		0.003 U
	7/27/01	8.6	8.4	0.005 U	0.005 U	0.003 U	0.003 U
EP-80	1/28/00		0.016		0.005 U		0.004
	5/2/00		0.017 UJ1		0.005 U		0.006
	8/10/00		0.013		0.005 U		0.003 U
	11/9/00		0.02		0.005 U		0.003 U
	2/16/01		0.025		0.005 U		0.003 U
	5/14/01		0.015		0.005 U		0.003 U
	7/25/01	0.021	0.02	0.005 U	0.005 U	0.003 U	0.003 U
EP-119	7/27/01	2.2	2.2	0.005 U	0.005 U	0.003 U	0.003 U
	7/27/01	2.2	2.3	0.005 U	0.005 U	0.003 U	0.003 U

Table 2-27

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-5
(Historic Smeltertown Area)**

El Paso Asarco Smelter, Remedial Investigation

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-122	5/14/01		2.1		0.005 U		0.003 U
	7/27/01	2.2	2.3	0.005 U	0.005 U	0.003 U	0.003 U
EP-132	6/8/01	1.5	1.5	0.005 U	0.005 U	0.003 U	0.022
	6/8/01	1.5	1.5	0.005 U	0.005 U	0.003 U	0.018
	7/27/01	1.9	2	0.005 U	0.005 U	0.003 U	0.003 U
EP-111	1/29/00		0.91		0.005 U		0.003 U
	5/2/00		0.83		0.005 U		0.004
	8/14/00		0.97		0.005 U		0.003 U
	11/10/00		1.1		0.005 U		0.003
	11/10/00		1.1		0.005 U		0.005
	2/21/01		0.98		0.005 U		0.003 U
	5/15/01		0.95		0.005 U		0.003 U
	7/31/01	0.98	0.93	0.005 U	0.005 U	0.003 U	0.003 U
EP-112	1/29/00		0.013		0.005 U		0.003 U
			0.013 UJ1		0.005 U		0.003
			0.015		0.005 U		0.003 U
			0.014		0.005 U		0.003 U
			0.03		0.005 U		0.003 U
			0.027		0.005 U		0.003 U
			0.012		0.005 U		0.003 U
		0.03	0.029	0.005 U	0.005 U	0.003 U	0.003 U
EP-113	1/29/00		0.005 U		0.005 U		0.003
	5/2/00		0.006 UJ1		0.005 U		0.003 U
	8/14/00		0.005		0.005 U		0.003 U
	11/10/00		0.015		0.005 U		0.003 U
	2/21/01		0.016		0.005 U		0.003 U
	5/15/01		0.007		0.005 U		0.003 U
	7/31/01	0.013	0.013	0.005 U	0.005 U	0.003 U	0.003 U
EP-127	5/8/01		2.5		0.005 U		0.003 U
	7/31/01	2.5	2.5	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH8-5	BH8-5A	4/11/01	0-1 ft.	6100	2200	24000
		BH8-5B	4/11/01	1-2 ft.	2100	910	13000
		BH8-5C	4/11/01	2-3 ft.	3300	880	22000
		BH8-5D	4/11/01	15-16 ft.	48	51	150
		BH8-5E	4/11/01	20-21 ft.	22	17	49
	BH8-6	BH8-6A	4/11/01	1-2 ft.	32	10 U	330
		BH8-6A2	4/11/01	1-2 ft.	18	10 U	248
		BH8-6B	4/11/01	2-3 ft.	3500	280	43000
		BH8-6C	4/11/01	3-4 ft.	1600	300	22000
		BH8-6D	4/11/01	4-5 ft.	190	18	830
		BH8-6E	4/11/01	15-16 ft.	10 U	10 U	33
		BH8-6F1	4/11/01	20-21 ft.	19	12	23
		BH8-6F2	4/11/01	20-21 ft.	10 U	10 U	17
	BH8-7	BH8-7A	4/11/01	0-1 ft.	4900	520	24000
		BH8-7B	4/11/01	1-2 ft.	380	36	860
		BH8-7C	4/11/01	2-3 ft.	37	16	160
		BH8-7D	4/11/01	3-4 ft.	87	25	350
		BH8-7E	4/11/01	4-5 ft.	290	72	3200
		BH8-7F	4/11/01	15-16 ft.	19	14	35
		BH8-7G	4/11/01	20-21 ft.	28	10 U	51
	BH8-8	BH8-8A	4/11/01	0-1 ft.	340	93	2700
		BH8-8B	4/11/01	1-2 ft.	860	160	9200
		BH8-8C1	4/11/01	12-13 ft.	10 U	10 U	74
		BH8-8C2	4/11/01	12-13 ft.	10 U	10 U	16
		BH8-8D	4/11/01	18-19 ft.	10 U	10 U	28
	BH8-9	BH8-9A	4/11/01	0-0.5 ft.	4700	350	38000
		BH8-9B	4/11/01	7-8 ft.	130	96	210
		BH8-9B	4/11/01	7-8 ft.	118	131	184
		BH8-9C	4/11/01	12-13 ft.	13	10 U	25
	BH8-10	BH8-10A2	4/11/01	10-11 ft.	45	37	150
		BH8-10A1	4/11/01	10-11 ft.	41	40	120
		BH8-10B	4/11/01	15-16 ft.	18	13	23
	BH8-11	BH8-11A	4/12/01	0-1 ft.	15000	730	51000
		BH8-11B	4/12/01	1-2 ft.	130	570	1100
		BH8-11B	4/12/01	1-2 ft.	108	545	1039
		BH8-11C	4/12/01	2-3 ft.	230	750	1500
		BH8-11D	4/12/01	3-4 ft.	96	27	1300
		BH8-11E	4/12/01	4-5 ft.	75	23	430
		BH8-11F	4/12/01	10-11 ft.	10 U	10 U	10 U

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH8-12	BH8-12A	4/16/01	0-1 ft.	1600	1500	6300
		BH8-12B	4/16/01	1-2 ft.	70	1900	300
		BH8-12C	4/16/01	2-3 ft.	110	580	760
		BH8-12D	4/16/01	3-4 ft.	10 U	10 U	130
		BH8-12E	4/16/01	9-10 ft.	25	13	48
Phase II	BH8-1	BH8-1A	10/29/99	31-33 ft.	41	12	34
		BH8-1B	10/29/99	35-37 ft.	19	10 U	28
		BH8-1C	10/30/99	40-42 ft.	12	10 U	12
		BH8-1D	10/30/99	45-47 ft.	10 U	10 U	14
		BH8-1E	10/30/99	50-52 ft.	10 U	10 U	10 U
		BH8-1F	10/30/99	55-57 ft.	10 U	10 U	10 U
		BH8-1F2	10/30/99	55-57 ft.	10 U	10 U	10 U
		BH8-1G	10/30/99	60-62 ft.	10 U	10 U	10 U
		BH8-1H	10/30/99	65-67 ft.	10 U	10 U	10 U
		BH8-1I	10/30/99	70-72 ft.	10 U	10 U	10 U
	BH8-2	BH8-2A	11/1/99	10-12 ft.	171	68	54
		BH8-2B	11/1/99	15-17 ft.	64	610	30
		BH8-2C	11/1/99	20-22 ft.	20	18	14
		BH8-2D	11/1/99	25-27 ft.	12	10 U	10 U
		BH8-2D2	11/1/99	25-27 ft.	10	11	12
		BH8-2E	11/1/99	30-32 ft.	10 U	10 U	10 U
		BH8-2F	11/1/99	35-37 ft.	29	10	11
		BH8-2G	11/1/99	40-42 ft.	10 U	10 U	10 U
		BH8-2H	11/1/99	45-47 ft.	10 U	10	10 U
		BH8-2I	11/1/99	50-52 ft.	10 U	10 U	10 U
		BH8-2I2	11/1/99	50-52 ft.	10 U	10 U	10 U
		BH8-2J	11/1/99	55-57 ft.	25	10 U	10 U
		BH8-2K	11/1/99	60-62 ft.	10 U	10 U	10 U
		BH8-2L	11/1/99	65-67 ft.	12	10 U	10 U
	BH8-3	BH8-3A	11/1/99	14-16 ft.	63	11	143
		BH8-3B	11/1/99	20-22 ft.	10 U	10 U	10 U
		BH8-3C	11/1/99	25-27 ft.	10 U	10 U	15
		BH8-3C2	11/1/99	25-27 ft.	10 U	10 U	12
		BH8-3D	11/1/99	30-32 ft.	116	10 U	10 U
		BH8-3E	11/1/99	35-37 ft.	87	10 U	10 U
		BH8-3F	11/2/99	40-42 ft.	54	10 U	29
		BH8-3G	11/2/99	45-47 ft.	10 U	10 U	10 U
		BH8-3H	11/2/99	50-52 ft.	10 U	10 U	10 U
		BH8-3I	11/2/99	55-57 ft.	21	10 U	10 U
	BH8-4	BH8-4A	11/2/99	0-1 ft.	6100	2600	29000

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	BH8-4 cont.	BH8-4B	11/2/99	1-2 ft.	210	110	550
		BH8-4C	11/2/99	2-3 ft.	130	170	120
		BH8-4D	11/2/99	3-4 ft.	10 U	150	26
		BH8-4E	11/2/99	4-5 ft.	10 U	170	15
		BH8-4F	11/2/99	10-12 ft.	31	48	10
		BH8-4G	11/2/99	15-17 ft.	10 U	10 U	10 U
		BH8-4G2	11/2/99	15-17 ft.	13	10 U	14
		BH8-4H	11/2/99	20-22 ft.	11	10 U	18
		BH8-4I	11/2/99	25-27 ft.	15	11	11
		BH8-4J	11/2/99	30-32 ft.	11	10 U	10 U
		BH8-4K	11/2/99	35-37 ft.	10 U	10 U	10 U
		BH8-4L	11/2/99	40-42 ft.	10 U	10 U	10 U
		BH8-4M	11/2/99	45-47 ft.	10 U	10 U	23
		BH8-4M2	11/2/99	45-47 ft.	10 U	10 U	11
		BH8-4N	11/2/99	50-52 ft.	10 U	10 U	10 U
		BH8-4O	11/2/99	55-57 ft.	10 U	10 U	10 U
		BH8-4P	11/2/99	60-62 ft.	10 U	10 U	10 U
		BH8-4Q	11/2/99	65-67 ft.	10 U	10 U	10 U
	EP-103	EP-103A	10/4/99	0-1 ft.	12	13	93
		EP-103B	10/4/99	1-2 ft.	10 U	19	390
		EP-103C	10/4/99	2-3 ft.	300	160	7900
		EP-103D	10/4/99	3-4 ft.	1400	55	11000
		EP-103E	10/4/99	4-5 ft.	6600	13	9700
		EP-103F	10/4/99	10-12 ft.	15	10 U	61
		EP-103F2	10/4/99	10-12 ft.	10 U	10 U	61
		EP-103G	10/4/99	15-17 ft.	21	10 U	26
		EP-103H	10/4/99	20-22 ft.	19	10 U	39
		EP-103I	10/4/99	25-27 ft.	11	10 U	33
		EP-103J	10/4/99	30-32 ft.	10 U	10 U	43
		EP-103K	10/4/99	35-37 ft.	10 U	10 U	46
		EP-103L	10/4/99	40-42 ft.	14	10 U	50
		EP-103M	10/4/99	45-47 ft.	26	10 U	37
		EP-103N	10/4/99	50-52 ft.	10	10 U	32
		EP-103N2	10/4/99	50-52 ft.	20	10 U	42
		EP-103O	10/4/99	55-57 ft.	10 U	10 U	41
		EP-103P	10/4/99	60-62 ft.	10 U	10 U	36
	EP-104	EP-104A	10/5/99	0-1 ft.	110	36	2800
		EP-104B	10/5/99	1-2 ft.	10	10 U	190
		EP-104C	10/5/99	2-3 ft.	46	63	1900
		EP-104D	10/6/99	3-4 ft.	16	12	580
		EP-104E	10/6/99	4-5 ft.	10 U	10 U	220
		EP-104E2	10/6/99	4-5 ft.	10 U	10 U	140
		EP-104F	10/6/99	10-12 ft.	10 U	10 U	60

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-104 cont.	EP-104G	10/6/99	15-17 ft.	10 U	10 U	55
		EP-104G2	10/6/99	15-17 ft.	11	5 U	7.1
		EP-104H	10/6/99	20-22 ft.	16	10 U	50
		EP-104I	10/5/99	25-27 ft.	10 U	10 U	47
		EP-104J	10/5/99	30-32 ft.	20	10 U	27
		EP-104K	10/5/99	35-37 ft.	10 U	10 U	41
		EP-104L	10/5/99	40-42 ft.	20	10 U	24
		EP-104M	10/5/99	45-47 ft.	10 U	10 U	42
		EP-104N	10/6/99	50-52 ft.	16	10 U	44
		EP-104N2	10/6/99	50-52 ft.	13	10 U	41
		EP-104O	10/6/99	55-57 ft.	10 U	10 U	46
		EP-104P	10/6/99	60-62 ft.	10 U	10 U	37
		EP-104P2	10/6/99	60-62 ft.	5	5 U	7
		EP-104Q	10/6/99	65-67 ft.	10 U	10 U	39
	EP-105	EP-105A	10/7/99	0-1 ft.	42	10 U	76
		EP-105B	10/7/99	1-2 ft.	1600	600	13000
		EP-105C	10/7/99	2-3 ft.	2400	120	10000
		EP-105D	10/7/99	3-4 ft.	1100	39	1900
		EP-105E	10/7/99	4-5 ft.	410	59	680
		EP-105E2	10/7/99	4-5 ft.	470	40	910
		EP-105F	10/7/99	10-12 ft.	170	17	480
		EP-105G	10/7/99	15-17 ft.	10 U	10 U	130
		EP-105H	10/7/99	20-22 ft.	11	10 U	55
		EP-105I	10/7/99	25-27 ft.	14	10 U	48
		EP-105J	10/7/99	30-32 ft.	10 U	10 U	47
		EP-105K	10/7/99	35-37 ft.	13	10 U	51
		EP-105L	10/7/99	40-42 ft.	17	10 U	39
		EP-105M	10/7/99	45-47 ft.	10 U	10 U	42
		EP-105N	10/8/99	50-52 ft.	21	10 U	40
		EP-105N2	10/8/99	50-52 ft.	17	10 U	33
		EP-105O	10/8/99	55-57 ft.	10 U	10 U	47
		EP-105P	10/8/99	60-62 ft.	10 U	10 U	40
		EP-105Q	10/8/99	75-77 ft.	10 U	10 U	46
	EP-106	EP-106A	10/16/99	0-1 ft.	270	82	2800
		EP-106B	10/16/99	1-2 ft.	75	26	720
		EP-106C	10/16/99	2-3 ft.	54	10 U	470
		EP-106D	10/16/99	3-4 ft.	92	28	590
		EP-106E	10/16/99	4-5 ft.	380	130	490
		EP-106F	10/16/99	10-12 ft.	23	10 U	57
		EP-106F2	10/16/99	10-12 ft.	13	10 U	48
		EP-106G	10/16/99	15-17 ft.	21	10 U	34
		EP-106H	10/16/99	20-22 ft.	10 U	10 U	43
		EP-106I	10/16/99	25-27 ft.	10 U	10 U	48

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-106 cont.	EP-106J	10/16/99	30-32 ft.	24	10 U	27
		EP-106K	10/16/99	35-37 ft.	17	10 U	38
		EP-106L	10/16/99	40-42 ft.	22	10 U	27
		EP-106M	10/16/99	45-47 ft.	25	10 U	25
		EP-106N	10/16/99	50-52 ft.	10 U	10 U	32
		EP-106O	10/16/99	55-57 ft.	10 U	11	25
		EP-106O2	10/16/99	55-57 ft.	10 U	12	24
	EP-107	EP-107A	10/11/99	0-1 ft.	69	15	150
		EP-107B	10/11/99	1-2 ft.	22	10 U	43
		EP-107C	10/11/99	2-3 ft.	10 U	10 U	51
		EP-107D	10/11/99	3-4 ft.	10 U	12	80
		EP-107E	10/11/99	4-5 ft.	31	29	500
		EP-107F	10/11/99	15-17 ft.	77	13	67
		EP-107F2	10/11/99	15-17 ft.	63	12	85
		EP-107G	10/11/99	20-22 ft.	10 U	10 U	54
		EP-107H	10/11/99	25-27 ft.	10 U	10 U	71
		EP-107I	10/11/99	30-32 ft.	10 U	10 U	68
		EP-107J	10/11/99	35-37 ft.	11	10 U	49
		EP-107K	10/11/99	40-42 ft.	14	10 U	32
		EP-107K2	10/11/99	40-42 ft.	17	14	37
		EP-107L	10/11/99	45-47 ft.	10 U	11	44
		EP-107M	10/11/99	50-52 ft.	10 U	10 U	41
		EP-107N	10/12/99	55-57 ft.	10 U	10 U	44
		EP-107O	10/12/99	60-62 ft.	10 U	10 U	26
		EP-107P	10/12/99	65-67 ft.	10 U	11	40
Phase I	SSIA8-1	SSIA8-1A	7/16/97	0 ft.	240	33	44
		SSIA8-1B	7/16/97	1.5 ft.	2100	400	1500
		SSIA8-1C	7/16/97	3 ft.	800	99	10000
	SSIA8-2	SSIA8-2A	7/16/97	0 ft.	20 U	35	240
		SSIA8-2B	7/16/97	1.5 ft.	20 U	11	500
		SSIA8-2C	7/16/97	3 ft.	880	38	8900
		SSIA8-2D	7/16/97	4 ft.	770	37	10000
	SSIA8-3	SSIA8-3A	7/16/97	0 ft.	2700	660	420
		SSIA8-3B	7/16/97	1.5 ft.	170	150	1000
		SSIA8-3C	7/16/97	3 ft.	1100	400	6800
		SSIA8-3D	7/16/97	4 ft.	290	79	4700
	SSIA8-4	SSIA8-4A	7/16/97	0 ft.	20 U	10 U	120
		SSIA8-4B	7/16/97	1.5 ft.	3700	980	43000
		SSIA8-4C	7/14/97	3 ft.	6600	1000	71000
		SSIA8-4D	7/14/97	4 ft.	3100	530	22000

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA8-5	SSIA8-5A	7/16/97	0 ft.	53	130	180
		SSIA8-5B	7/16/97	1.5 ft.	20 U	10 U	130
		SSIA8-5C	7/16/97	3 ft.	20 U	28	440
		SSIA8-5D	7/16/97	4 ft.	20 U	10 U	50
	SSIA8-6	SSIA8-6A	7/16/97	0 ft.	20 U	23	690
		SSIA8-6A2	7/16/97	0 ft.	20 U	13	680
		SSIA8-6B	7/16/97	1.5 ft.	20 U	47	1000
		SSIA8-6C	7/16/97	3 ft.	58	130	1700
		SSIA8-6D	7/16/97	4 ft.	120	110	2400
	SSIA8-7	SSIA8-7A	7/16/97	0 ft.	51	96	520
		SSIA8-7B	7/16/97	1.5 ft.	20 U	22	300
		SSIA8-7C	7/16/97	3 ft.	31	41	500
		SSIA8-7D	7/16/97	4 ft.	20 U	10 U	42
	SSIA8-8	SSIA8-8A	7/16/97	0 ft.	20 U	96	770
		SSIA8-8B	7/16/97	1.5 ft.	39	31	1400
		SSIA8-8C	7/16/97	3 ft.	20 U	10 U	330
		SSIA8-8D	7/16/97	4 ft.	20 U	10 U	920
	SSIA8-9	SSIA8-9A	7/16/97	0 ft.	1000	310	8900
		SSIA8-9B	7/16/97	1.5 ft.	530	270	11000
		SSIA8-9C	7/16/97	3 ft.	180	76	4600
		SSIA8-9D	7/16/97	4 ft.	20 U	19	1300
	SSIA8-10	SSIA8-10A	7/17/97	0 ft.	20 U	13	68
		SSIA8-10B	7/17/97	1.5 ft.	53	66	1400
		SSIA8-10C	7/17/97	3 ft.	20 U	25	810
		SSIA8-10D	7/17/97	4 ft.	20 U	28	660
	SSIA8-11	SSIA8-11A	7/17/97	0 ft.	910	430	3200
		SSIA8-11B	7/17/97	1.5 ft.	62	86	3700
		SSIA8-11C	7/17/97	3 ft.	20 U	10 U	36
		SSIA8-11D	7/17/97	4 ft.	20 U	10 U	230
	SSIA8-12	SSIA8-12A	7/17/97	0 ft.	150	78	3600
		SSIA8-12B	7/17/97	1.5 ft.	480	78	4900
		SSIA8-12C	7/17/97	3 ft.	32	23	1100
		SSIA8-12D	7/17/97	4 ft.	20 U	10 U	38
	SSIA8-13	SSIA8-13A	7/17/97	0 ft.	33	10 U	230
		SSIA8-13B	7/17/97	1.5 ft.	20 U	49	3100
		SSIA8-13C	7/17/97	3 ft.	20 U	10 U	190

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA8-13	SSIA8-13D	7/17/97	4 ft.	20 U	45	98
	SSIA8-14	SSIA8-14A	7/17/97	0 ft.	20 U	10 U	83
		SSIA8-14A2	7/17/97	0 ft.	20 U	10 U	73
		SSIA8-14B	7/17/97	1.5 ft.	110	25	1200
		SSIA8-14C	7/17/97	3 ft.	120	20	2900
	SSIA8-15	SSIA8-15A	7/18/97	0 ft.	20 U	11	160
		SSIA8-15B	7/18/97	1.5 ft.	20 U	14	900
		SSIA8-15C	7/18/97	3 ft.	20 U	10 U	100
		SSIA8-15D	7/18/97	4 ft.	83	92	8900
	SSIA8-16	SSIA8-16A	7/18/97	0 ft.	930	240	4000
		SSIA8-16B	7/18/97	1.5 ft.	370	190	10000
		SSIA8-16C	7/18/97	3 ft.	1100	120	3500
		SSIA8-16D	7/18/97	4 ft.	1200	520	5000
	SSIA8-17	SSIA8-17A	7/18/97	0 ft.	98	29	470
		SSIA8-17B	7/18/97	1.5 ft.	20 U	10 U	380
		SSIA8-17C	7/18/97	3 ft.	27	10 U	520
		SSIA8-17D	7/18/97	4 ft.	20 U	11	240
	SSIA8-18	SSIA8-18A	7/18/97	0 ft.	260	100	300
		SSIA8-18A2	7/18/97	0 ft.	280	100	240
		SSIA8-18B	7/18/97	1.5 ft.	20 U	99	3600
	SSIA8-19	SSIA8-19A	7/18/97	0 ft.	44	10 U	350
		SSIA8-19B	7/18/97	1.5 ft.	20 U	10 U	560
		SSIA8-19C	7/18/97	3 ft.	20 U	10 U	290
		SSIA8-19D	7/18/97	4 ft.	20 U	220	14000
	SSIA8-20	SSIA8-20A	7/18/97	0 ft.	20 U	10 U	95
		SSIA8-20B	7/18/97	1.5 ft.	330	89	3900
	SSIA8-21	SSIA8-21A	7/18/97	0 ft.	460	300	1400
		SSIA8-21B	7/18/97	1.5 ft.	780	110	2900
		SSIA8-21C	7/18/97	3 ft.	23	10 U	150
		SSIA8-21D	7/18/97	4 ft.	20 U	14	480
	SSIA8-22	SSIA8-22A	7/18/97	0 ft.	6600	1400	8100
		SSIA8-22B	7/18/97	1.5 ft.	2600	600	1500
		SSIA8-22C	7/18/97	3 ft.	1800	260	350
		SSIA8-22D	7/18/97	4 ft.	160	42	13
	SSIA8-23	SSIA8-23A	7/18/97	0 ft.	140	29	590

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	SSIA8-23	SSIA8-23B	7/18/97	1.5 ft.	20 U	21	490
		SSIA8-23C	7/18/97	3 ft.	29	10 U	370
		SSIA8-23D	7/18/97	4 ft.	20 U	10 U	50
	SSIA8-24	SSIA8-24A	7/18/97	0 ft.	110	21	550
		SSIA8-24B	7/18/97	1.5 ft.	44	190	850
	SSIA8-25	SSIA8-25A	7/18/97	0 ft.	4400	910	20000
		SSIA8-25B	7/18/97	1.5 ft.	900	120	3600
	SSIA8-26	SSIA8-26A	7/18/97	0 ft.	2900	520	25000
		SSIA8-26B	7/18/97	1.5 ft.	290	410	8100
	SSIA8-27	SSIA8-27A	7/18/97	0 ft.	3300	380	8100
		SSIA8-27B	7/18/97	1.5 ft.	240	33	790
		SSIA8-27C	7/18/97	3 ft.	20 U	10 U	170
	SSIA8-28	SSIA8-28A	7/18/97	0 ft.	4400	1800	7300
		SSIA8-28B	7/18/97	1.5 ft.	3300	1300	19000
		SSIA8-28C	7/18/97	3 ft.	20 U	10 U	60
		SSIA8-28D	7/18/97	4 ft.	20 U	10 U	27
	SSIA8-29	SSIA8-29A	7/18/97	0 ft.	2900	470	9700
		SSIA8-29B	7/18/97	1.5 ft.	1100	350	22000
	SSIA8-30	SSIA8-30A	7/18/97	0 ft.	2000	840	20000
		SSIA8-30A2	7/18/97	0 ft.	2300	910	17000
		SSIA8-30B	7/18/97	1.5 ft.	220	36	8100
	SSIA8-31	SSIA8-31A	7/18/97	0 ft.	48	10 U	400
		SSIA8-31B	7/18/97	1.5 ft.	94	280	9900
		SSIA8-31C	7/18/97	3 ft.	20 U	44	7100
	EP-67	EP-67A	5/28/97	0 ft.	1400	470	9400
		EP-67B	5/28/97	5 ft.	320	200	550
		EP-67C	5/28/97	10 ft.	340	59	25
		EP-67D	5/28/97	15 ft.	240	82	18
		EP-67E	5/28/97	20 ft.	310	10 U	27
		EP-67F	5/28/97	25 ft.	350	10 U	10 U
		EP-67G	5/28/97	30 ft.	170	10 U	16
		EP-67H	5/28/97	35 ft.	140	13	21
		EP-67I	5/28/97	40 ft.	38	10 U	10 U
		EP-67J	5/28/97	45 ft.	20 U	10 U	20
		EP-67K	5/28/97	50 ft.	20 U	10 U	11

Table 2-28

**Summary of Soil Sample Results for Investigation Area 8
(Bedding and Unloading Buildings Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	EP-68	EP-68A	5/29/97	0 ft.	20 U	10 U	140 J4
		EP-68A2	5/29/97	0 ft.	20 U	10 U	24 J4
		EP-68B	5/29/97	5 ft.	20 U	10 U	29 J4
		EP-68C	5/29/97	10 ft.	20 U	10 U	18 J4
		EP-68D	5/29/97	15 ft.	20 U	10 U	33 J4
		EP-68E	5/29/97	20 ft.	20 U	10 U	14 J4
		EP-68F	5/29/97	25 ft.	20 U	10 U	24 J4
		EP-68G	5/29/97	30 ft.	21	10 U	11 J4
		EP-68H	5/29/97	40 ft.	20 U	10 U	10 J4
		EP-68I	5/29/97	45 ft.	20 U	10 U	10 J4
		EP-68J	5/29/97	65 ft.	20 U	10 U	34 J4
	EP-69	EP-69A	5/30/97	0 ft.	650	150	6100
		EP-69B	5/30/97	5 ft.	28	10 U	120
		EP-69C	5/30/97	15 ft.	40	10 U	53
		EP-69D	5/30/97	20 ft.	20 U	10 U	11
		EP-69E	5/30/97	25 ft.	20 U	10 U	20
		EP-69F	5/30/97	30 ft.	20 U	10 U	26

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-29

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-8
(Bedding and Unloading Building Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA8							
EP-15	1/24/00		0.009		0.005 U		0.01 UJ1
	4/26/00		0.007		0.005 U		0.004
	8/3/00		0.007		0.005 U		0.005 U
	11/2/00		0.008		0.005 U		0.003
	11/2/00		0.009		0.005 U		0.003 U
	2/12/01		0.011		0.005 U		0.003 U
	5/8/01		0.013		0.008		0.004
	7/19/01	0.015	0.013	0.005	0.005 U	0.003 U	0.003 U,UJ4
EP-67	1/24/00		0.009		0.005 U		0.011 UJ1
	4/24/00		0.02		0.005 U		0.009 UJ1
	8/2/00		0.01		0.005 U		0.005 U
	8/2/00		0.011		0.005 U		0.009
	10/31/00		0.01		0.005 U		0.003
	2/8/01		0.014		0.005 U		0.003 U
	2/8/01		0.015		0.005 U		0.004
	5/7/01		0.018		0.005 U		0.003 U
EP-103	7/17/01	0.026	0.028	0.005 U	0.005 U	0.003 U	0.003 U
	1/24/00		0.011		0.005 U		0.013 UJ1
	4/26/00		0.016		0.005 U		0.01
	8/4/00		0.023		0.007		0.003 U
	11/2/00		0.008		0.005 U		0.003 U
	2/12/01		0.022		0.005 U		0.003 U
	5/8/01		0.019		0.007		0.003 U
	7/19/01	0.044	0.04	0.005 U	0.005 U	0.003 U	0.003 U,UJ4
EP-104	1/24/00		0.08		0.005 U		0.015 UJ1
	4/26/00		0.072		0.005 U		0.015
	8/3/00		0.082		0.005 U		0.008
	11/1/00		0.091		0.005 U		0.011
	2/12/01		0.084		0.005 U		0.003
	2/12/01		0.087		0.005 U		0.003
	5/8/01		0.081		0.005 U		0.005
	7/18/01	0.091	0.095	0.013	0.013	0.003 U	0.006 UJ1
EP-105	1/25/00		0.4		0.005 U		0.076
	4/26/00		0.051		0.005 U		0.011
	8/4/00		0.6		0.005 U		0.018
	11/1/00		0.099		0.005 U		0.012
	2/14/01		0.84		0.005 U		0.008
	5/9/01		0.17		0.005 U		0.1
	7/19/01	0.94	0.97	0.005 U	0.005 U	0.003 U	0.005 J4
EP-106	1/25/00		0.007		0.005 U		0.014 UJ1
	4/26/00		0.005 U		0.005 U		0.003 U
	8/2/00		0.006		0.005 U		0.006
	11/2/00		0.007		0.005 U		0.003 U
	2/12/01		0.017		0.015		0.006

Table 2-29

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-8
(Bedding and Unloading Building Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-106	5/9/01		0.014		0.005 U		0.003 U
	7/18/01	0.05	0.049	0.073	0.07	0.003 U	0.003 U
EP-107	1/24/00		0.012		0.005 U		0.009 UJ1
	4/25/00		0.022		0.005 U		0.003 U
	8/3/00		0.022		0.005 U		0.005 U
	11/3/00		0.029		0.029		0.003 U
	2/12/01		0.03		0.005		0.003 U
	5/8/01		0.026		0.006		0.003 U
	7/17/01	0.019	0.022	0.005 U	0.005 U	0.003 U	0.004

Note:

- J The associated numerical value is an estimated quantity because quality control criteria were not met
 J2 calibration range exceeded or significant deviation from known values. Possible bias.
 J3 Holding time not met. Indicates low bias.
 J4 Other QC outside control limits

U Undetected. Below method detection limits.

- UJ The material was analyzed for, but was not detected above the associated value.
 UJ1 Blank contamination. Indicates possible high bias and/or false positive.
 UJ2 Calibration range exceeded or significant deviation from known value.
 UJ3 Holding times not met. Indicates low bias.
 UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH9-1-6	BH9-1-6A	5/16/01	0-1 ft.	1000	500	1900
		BH9-1-6B	5/16/01	2-3 ft.	81	200	47
		BH9-1-6C	5/16/01	3-4 ft.	110	230	44
		BH9-1-6D	5/16/01	4-5 ft.	62	19	68
		BH9-1-6E	5/16/01	5-6 ft.	50	10 U	56
	BH9-1-7	BH9-1-7A	5/16/01	0-1 ft.	8500	6800	11000
		BH9-1-7B	5/16/01	1-2 ft.	200	110	1000
		BH9-1-7C	5/16/01	2-3 ft.	19000	8600	35000
		BH9-1-7D1	5/17/01	4-5 ft.	87	61	550
		BH9-1-7D2	5/17/01	4-5 ft.	76	42	430
		BH9-1-7E	5/17/01	5-6 ft.	41	110	560
	BH9-1-8	BH9-1-8A	5/17/01	0-1 ft.	1300	530	3400
		BH9-1-8B	5/17/01	1-2 ft.	54	12	130
		BH9-1-8C	5/17/01	2-3 ft.	60	14	120
		BH9-1-8D	5/17/01	4-5 ft.	230	68	480
		BH9-1-8E1	5/17/01	5-6 ft.	50	16	96
		BH9-1-8E2	5/17/01	5-6 ft.	55	19	98
	BH9-1-9	BH9-1-9A	5/17/01	0-1 ft.	1700	610	6100
		BH9-1-9B	5/17/01	1-2 ft.	190	73	520
		BH9-1-9C1	5/17/01	2-3 ft.	370	170	930
		BH9-1-9C2	5/17/01	2-3 ft.	1600	1100	4800
		BH9-1-9D	5/17/01	3-4 ft.	200	190	330
		BH9-1-9E	5/17/01	5-6 ft.	240	400	160
		BH9-1-9F	5/17/01	6-7 ft.	100	88	41
		BH9-1-9G	5/17/01	7-8 ft.	75	150	28
	BH9-1-10	BH9-1-10A	5/17/01	0-1 ft.	3500	1600	9500
		BH9-1-10B	5/17/01	1-2 ft.	190	64	600
		BH9-1-10C	5/17/01	2-3 ft.	250	87	860
		BH9-1-10D	5/17/01	3-4 ft.	220	75	270
		BH9-1-10E1	5/17/01	4-5 ft.	1000	320	3000
		BH9-1-10E2	5/17/01	4-5 ft.	500	140	1500
		BH9-1-10F	5/17/01	5-6 ft.	160	37	340
	BH9-1-11	BH9-1-11A	5/17/01	0-1 ft.	2500	1300	6100
		BH9-1-11B	5/17/01	1-2 ft.	95	110	91
		BH9-1-11C	5/17/01	2-3 ft.	180	170	76
		BH9-1-11D	5/17/01	3-4 ft.	280	64	36
	BH9-1-12	BH9-1-12A	5/21/01	0-1 ft.	1300	510	2700
		BH9-1-12B	5/21/01	1-2 ft.	160	65	23
		BH9-1-12C	5/21/01	3-4 ft.	42	77	25

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH9-1-13	BH9-1-13A	5/24/01	0-1 ft.	12000	5400	10000
		BH9-1-13B	5/24/01	1-2 ft.	450	200	1300
		BH9-1-13C	5/17/01	2-3 ft.	5200	3500	13000
		BH9-1-13D	5/17/01	3-4 ft.	10000	6400	17000
		BH9-1-13E	5/24/01	4-5 ft.	230	180	1300
		BH9-1-13F	5/24/01	5-6 ft.	150	180	860
		BH9-1-13G	5/24/01	6-7 ft.	5000	2900	12000
		BH9-1-13H	5/24/01	7-8 ft.	4100	2600	9000
	BH9-1-14	BH9-1-14A1	5/24/01	0-1 ft.	1800	790	5600
		BH9-1-14A2	5/24/01	0-1 ft.	1300	590	3800
		BH9-1-14B	5/24/01	1-2 ft.	2000	1600	7000
		BH9-1-14C	5/24/01	2-3 ft.	100	55	450
		BH9-1-14D	5/24/01	3-4 ft.	68	65	730
		BH9-1-14E	5/24/01	4-5 ft.	69	61	450
		BH9-1-14F	5/24/01	6-7 ft.	2400	630	1400
	BH9-1-15	BH9-1-15A	5/24/01	0-1 ft.	10000	4200	8800
		BH9-1-15B	5/24/01	1-2 ft.	2200	520	4800
		BH9-1-15C	5/24/01	2-3 ft.	210	220	890
		BH9-1-15D	5/24/01	3-4 ft.	60	140	540
		BH9-1-15E	5/24/01	4-5 ft.	310	240	1200
	BH9-1-16	BH9-1-16A1	5/24/01	0-1 ft.	2300	510	29000
		BH9-1-16A2	5/24/01	0-1 ft.	2000	540	23000
		BH9-1-16B	5/24/01	1-2 ft.	250	110	1900
		BH9-1-16C	5/24/01	2-3 ft.	110	21	150
		BH9-1-16D	5/24/01	3-4 ft.	91	14	82
		BH9-1-16E	5/24/01	4-5 ft.	290	35	4000
	BH9-1-17	BH9-1-17A	5/24/01	0-1 ft.	1600	360	360
		BH9-1-17B	5/24/01	1-2 ft.	600	250	110
	BH9-1-18	BH9-1-18A	5/24/01	0-1 ft.	530	510	4100
		BH9-1-18A	5/24/01	0-1 ft.	481	507	4413
		BH9-1-18B	5/24/01	1-2 ft.	100	10 U	110
		BH9-1-18C	5/24/01	2-3 ft.	110	13	160
		BH9-1-18C	5/24/01	2-3 ft.	74	10 U	175
		BH9-1-18D	5/25/01	4-5 ft.	230	75	780
		BH9-1-18E	5/25/01	5-6 ft.	72	10 U	110
		BH9-1-18F	5/25/01	6-7 ft.	65	10 U	48
		BH9-1-18G1	5/25/01	7-8 ft.	77	13	150
		BH9-1-18G2	5/25/01	7-8 ft.	69	10 U	94

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH9-1-18	BH9-1-18H	5/25/01	8-9 ft.	67	17	69
		BH9-1-18I	5/25/01	9-10 ft.	54	18	200
		BH9-1-18J	5/25/01	10-11 ft.	62	10 U	53
	BH9-6-5	BH9-6-5A	5/25/01	0-1 ft.	4600	910	16000
		BH9-6-5B	5/25/01	1-2 ft.	4300	1900	31000
		BH9-6-5C	5/25/01	2-3 ft.	9700	12000	100000
		BH9-6-5D	5/25/01	3-4 ft.	9100	12000	92000
		BH9-6-5E1	5/25/01	4-5 ft.	260	770	2000
		BH9-6-5E2	5/25/01	4-5 ft.	770	1300	5400
		BH9-6-5F	5/25/01	5-6 ft.	48	17	45
	BH9-6-6	BH9-6-6A	5/25/01	0-1 ft.	3400	5100	12000
		BH9-6-6B	5/25/01	1-2 ft.	49	49	180
	BH9-6-7	BH9-6-7A	5/25/01	0-1 ft.	31000	5600	31000
		BH9-6-7B	5/25/01	1-2 ft.	2900	8100	32000
		BH9-6-7C	5/25/01	2-3 ft.	130	54	390
		BH9-6-7D	5/25/01	3-4 ft.	67	10 U	55
	BH9-6-8	BH9-6-8A	5/25/01	0-1 ft.	9200	4000	30000
		BH9-6-8B	5/25/01	1-2 ft.	200	280	1200
		BH9-6-8B	5/25/01	1-2 ft.	180	359	1183
		BH9-6-8C	5/25/01	2-2.5 ft.	54	10 U	68
	BH9-6-9	BH9-6-9A	5/25/01	0-1 ft.	20000	7000	65000
		BH9-6-9B1	5/25/01	1-2 ft.	1400	1500	6600
		BH9-6-9B2	5/25/01	1-2 ft.	3700	5900	44000
		BH9-6-9C	5/25/01	2-3 ft.	100	30	250
		BH9-6-9C	5/25/01	2-3 ft.	54	20	227
		BH9-6-9D	5/25/01	3-3.5 ft.	38	20	62
		BH9-6-9D	5/25/01	3-3.5 ft.	26	14	74
	BH9-6-10	BH9-6-10A	5/25/01	0-1 ft.	5200	2100	19000
		BH9-6-10B	5/25/01	1-2 ft.	280	260	1600
		BH9-6-10C	5/25/01	2-3 ft.	62	46	73
		BH9-6-10D	5/25/01	3-4 ft.	73	31	63
	BH9-6-11	BH9-6-11A	5/25/01	0-1 ft.	6200	3900	46000
		BH9-6-11B	5/25/01	1-2 ft.	3100	8200	63000
		BH9-6-11C	5/25/01	2-3 ft.	1400	2200	14000
		BH9-6-11D	5/25/01	3-4 ft.	94	31	230
	BH9-6-12	BH9-6-12A	5/25/01	0-1 ft.	7200	1800	24000

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH9-6-12	BH9-6-12B	5/25/01	1-2 ft.	6100	8300	120000
		BH9-6-12C	5/25/01	2-2.5 ft.	400	450	2900
		BH9-6-12C	5/25/01	2-2.5 ft.	285	433	2803
	BH9-6-13	BH9-6-13A	5/25/01	0-1.2 ft.	4900	7900	60000
	BH9-6-14	BH9-6-14A1	5/25/01	0-1 ft.	3800	1200	6000
		BH9-6-14A2	5/25/01	0-1 ft.	3700	1100	6100
		BH9-6-14B	5/25/01	1-2 ft.	17000	3100	59000
		BH9-6-14C	5/25/01	2-3 ft.	29000	5000	65000
		BH9-6-14D	5/25/01	3-4 ft.	4500	6700	56000
	BH9-6-15	BH9-6-15A	5/25/01	0-1 ft.	10000	4900	64000
		BH9-6-15B1	5/25/01	1-2 ft.	120	17	290
		BH9-6-15B2	5/25/01	1-2 ft.	82	10 U	140
		BH9-6-15C	5/25/01	2-3 ft.	91	12	160
	BH9-6-16	BH9-6-16A	5/25/01	0-1 ft.	3200	1600	16000
		BH9-6-16B1	5/25/01	1-2 ft.	1400	790	10000
		BH9-6-16B2	5/25/01	1-2 ft.	760	390	4700
		BH9-6-16C	5/25/01	2-3 ft.	140	14	66
		BH9-6-16D	5/25/01	3-4 ft.	43	13	55
	BH9-6-17	BH9-6-17A	5/25/01	0-1 ft.	14000	3400	34000
		BH9-6-17B	5/25/01	1-2 ft.	2400	1200	18000
		BH9-6-17C	5/25/01	2-3 ft.	4600	13000	90000
		BH9-6-17D	5/25/01	3-4 ft.	130	77	550
	BH9-6-18	BH9-6-18A	5/26/01	0-1 ft.	680	120	6000
		BH9-6-18B	5/26/01	1-2 ft.	2100	230	7800
		BH9-6-18C	5/26/01	2-3 ft.	980	160	2600
		BH9-6-18D	5/26/01	3-4 ft.	4500	400	12000
		BH9-6-18E	5/26/01	4-5 ft.	950	140	4500
		BH9-6-18F	5/26/01	5-6 ft.	900	250	6800
		BH9-6-18G	5/26/01	6-7 ft.	4700	1800	14000
		BH9-6-18H	5/26/01	7-8 ft.	6600	4700	30000
	BH9-6-19	BH9-6-19A	5/26/01	0-1 ft.	5000	5200	19000
		BH9-6-19B	5/26/01	1-2 ft.	74	21	140
		BH9-6-19C1	5/26/01	2-3 ft.	64	16	73
		BH9-6-19C2	5/26/01	2-3 ft.	62	19	92
		BH9-6-19D	5/26/01	3-4 ft.	53	16	38
	BH9-6-20	BH9-6-20A	5/26/01	0-1 ft.	30000	8600	20000
		BH9-6-20B	5/26/01	1-1.5 ft.	11000	6200	79000

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH9-6-20	BH9-6-20C	5/26/01	5-6 ft.	140	27	150
		BH9-6-20D	5/26/01	6-7 ft.	100	26	100
		BH9-6-20E	5/26/01	7-8 ft.	67	17	360
	BH9-6-21	BH9-6-21D	5/26/01	3-4 ft.	4400	14000	47000
		BH9-6-21A	5/26/01	0-1 ft.	18000	4700	32000
		BH9-6-21B	5/26/01	1-2 ft.	5900	16000	58000
		BH9-6-21C	5/26/01	2-3 ft.	4700	14000	49000
	BH9-6-22	BH9-6-22A	5/26/01	0-1 ft.	12000	4200	15000
		BH9-6-22B	5/26/01	1-2 ft.	1300	1100	7700
		BH9-6-22C	5/26/01	2-3 ft.	83	10 U	51
		BH9-6-22D	5/26/01	3-4 ft.	53	12	70
	BH9-6-23	BH9-6-23A	5/26/01	0-1 ft.	11000	5900	34000
		BH9-6-23B	5/26/01	1-2 ft.	6000	3500	33000
Phase II	BH9-5-1	BH9-5-1A	2/9/00	0-1 ft.	1800	120	7900
		BH9-5-1B	2/9/00	1-2 ft.	190	10 U	890
		BH9-5-1C	2/9/00	2-3 ft.	210	10 U	1400
		BH9-5-1D	2/9/00	3-4 ft.	650	35	7500
		BH9-5-1E	2/9/00	4-5 ft.	270	10 U	1200
		BH9-5-1F	2/9/00	5-6 ft.	91	10 U	320
		BH9-5-1G	2/9/00	10-11 ft.	20	11	510
	BH9-5-2	BH9-5-2A	2/9/00	0-1 ft.	1000	390	12000
		BH9-5-2B	2/9/00	1-2 ft.	1400	130	9600
		BH9-5-2C	2/9/00	2-3 ft.	1200	74	6000
		BH9-5-2D	2/9/00	3-4 ft.	560	33	3600
		BH9-5-2E	2/9/00	4-5 ft.	1200	54	6200
		BH9-5-2F	2/9/00	5-6 ft.	220	25	2600
		BH9-5-2G	2/9/00	7-8 ft.	22	10 U	190
	BH9-5-3	BH9-5-3A	2/9/00	0-1 ft.	1600	700	18000
		BH9-5-3B	2/9/00	1-2 ft.	28	22	710
		BH9-5-3C	2/9/00	2-3 ft.	32	30	1200
		BH9-5-3D	2/9/00	3-4 ft.	24	23	900
	BH9-5-4	BH9-5-4A	2/9/00	0-1 ft.	1800	790	23000
		BH9-5-4B	2/9/00	1-2 ft.	1200	550	17000
		BH9-5-4C	2/9/00	2-3 ft.	180	54	3100
		BH9-5-4D	2/9/00	3-4 ft.	200	13	3600
		BH9-5-4E	2/9/00	4-5 ft.	74	11	1300
		BH9-5-4F	2/9/00	5-6 ft.	43	10 U	1000

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	BH9-5-5	BH9-5-5A	2/9/00	0-1 ft.	4000	1300	30000
		BH9-5-5B	2/9/00	1-2 ft.	1400	370	12000
		BH9-5-5C	2/9/00	2-3 ft.	750	63	6700
		BH9-5-5D	2/9/00	3-4 ft.	71	10 U	940
	BH9-5-6	BH9-5-6A	2/9/00	0-1 ft.	1500	840	12000
		BH9-5-6B	2/9/00	1-2 ft.	1700	760	20000
		BH9-5-6C	2/9/00	2-3 ft.	88	44	1900
		BH9-5-6D	2/9/00	3-4 ft.	10	10 U	120
	BH9-5-7	BH9-5-7A	2/9/00	0-1 ft.	3900	1200	31000
		BH9-5-7B	2/9/00	1-2 ft.	900	300	9700
		BH9-5-7C	2/9/00	2-3 ft.	240	85	3700
		BH9-5-7D	2/9/00	3-4 ft.	27	10 U	560
Phase I	EP-77	EP-77A	6/4/97	0.5 ft.	200	11	2600
		EP-77B	6/4/97	20 ft.	140	43	950
		EP-77C	6/4/97	25 ft.	20 U	10 U	90
		EP-77D	6/4/97	30 ft.	33	10 U	36
		EP-77E	6/4/97	35 ft.	28	10 U	37
		EP-77F	6/4/97	40 ft.	73	10 U	22
		EP-77G	6/4/97	45 ft.	49	10 U	25
		EP-77H	6/4/97	50 ft.	20	10 U	20
	EP-88	EP-88A	6/17/97	0 ft.	550	150	3600
		EP-88B	6/17/97	5 ft.	50	120	2700
		EP-88C	6/17/97	10 ft.	20 U	10 U	35
		EP-88C2	6/17/97	10 ft.	20 U	10 U	19
		EP-88D	6/17/97	15 ft.	20 U	10 U	35
		EP-88E	6/17/97	20 ft.	20 U	10 U	58
		EP-88F	6/17/97	25 ft.	20 U	10 U	19
		EP-88G	6/17/97	30 ft.	20 U	10 U	18
		EP-88H	6/17/97	35 ft.	20 U	10 U	10 U
	POND 1	Sed/soil	7/15/96	A	4541	1269	6964
		Sed/soil	7/15/96	B	5693	1257	9695
		Sed/soil	7/15/96	C	768	257	1790
	POND 5	Sed/soil	7/15/96	A	4065	1158	63330
		Sed/soil	7/15/96	B	2049	597	32430
		Sed/soil	7/15/96	C	1253	212	5416
	POND 6	Sed/soil	7/15/96	A	1120	462	4296
		Sed/soil	7/15/96	B	4391	1522	12290

Table 2-30

**Summary of Soil Sample Results for Investigation Area 9
(Arroyo Down Gradient of Ponds 5 and 6)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I	POND 6	Sed/soil	7/15/96	C	2399	1129	7421

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH9-1-1 to BH9-1-5, BH9-5-8 to BH9-5-11 and BH9-6-1 to BH9-6-4 were Geotechnical Sample locations

Table 2-31

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-9
(Ponds 1, 5, and 6)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA9							
Ponds 5&6							
EM-5	1/25/00		2.6		0.016		0.012 UJ1
	4/26/00		2.3		0.009		0.013
	8/4/00		1.6		0.006		0.013
	11/3/00		1.7		0.008		0.006
	2/14/01		1.8		0.009		0.008
	5/9/01		1.5		0.005 U		0.005
	7/19/01	1.5	1.5	0.005 U	0.006	0.003 U	0.005 J4
EM-6	1/25/00		0.024		0.005 U		0.012 UJ1
	4/26/00		0.022		0.005 U		0.005
	8/4/00		0.022		0.005 U		0.008
	11/3/00		0.024		0.005 U		0.004
	2/14/01		0.027		0.005 U		0.007
	2/14/01		0.025		0.005 U		0.007
	5/9/01		0.025		0.005 U		0.003
	7/19/01	0.04	0.042	0.005 U	0.005 U	0.003 U	0.004 J4
EP-77	1/25/00		7.7		0.012		0.012 UJ1
	4/28/00		6.5		0.009		0.01
	4/28/00		6.6		0.009		0.008
	8/4/00		6.4		0.007		0.008
	11/3/00		6.2		0.008		0.003
	2/12/01		3.3		0.005 U		0.007
	5/9/01		1.5		0.005 U		0.008
	5/9/01		1.5		0.005 U		0.008
	7/19/01	5.4	5.5	0.005 U	0.005	0.003 U	0.004 J4
EP-88	1/26/00		0.012		0.005 U		0.004
	1/26/00		0.013		0.005 U		0.004
	4/28/00		0.053		0.004		0.012
	8/4/00		0.027		0.005 U		0
	11/7/00		0.025		0.005 U		0.004
	2/14/01		0.021		0.005 U		0.004
	5/9/01		0.028		0.005 U		0.003 U
	7/19/01	0.025	0.024	0.005 U	0.005 U	0.003 U	0.004 J4
EP-124	5/16/01		7.1		0.024		0.19
	7/27/01	10	9.8	0.005 U	0.005 U	0.008	0.018
Pond 1							
EP-12	2/8/00		2.3		0.005 U		0.009
	2/8/00		2.6		0.005 U		0.011
	5/9/00		2		0.005 U		0.024
	8/16/00		1.8		0.005 U		0.028
	11/14/00		2.1		0.005 U		0.028
	2/26/01		0.92		0.005 U		0.015 J4
	5/17/01		0.83		0.005 U		0.005
	7/30/01	0.71	0.96	0.005 U	0.005 U	0.003	0.01

Table 2-31

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-9
(Ponds 1, 5, and 6)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EM-2	1/25/00		1		0.005 U		0.019 UJ1
	4/26/00		0.8		0.005 U		0.004
	8/3/00		0.68		0.005 U		0.008
	11/1/00		0.56		0.005 U		0.004
	2/9/01		0.57		0.005 U		0.003
	5/8/01		0.83		0.005 U		0.003 U
	5/8/01		0.88		0.005 U		0.003 U
	7/18/01	0.99	1.1	0.005 U	0.005 U	0.003 U	0.006 UJ1
EM-4	1/25/00		0.005 U		0.005 U		0.007 UJ1
	4/26/00		0.01		0.005 U		0.003 U
	4/26/00		0.01		0.005 U		0.003 U
	8/3/00		0.005 U		0.005 U		0.005 U
	11/1/00		0.005 U		0.005 U		0.003 U
	2/9/01		0.007		0.005 U		0.003 U
	5/7/01		0.005		0.005 U		0.003 U
	7/18/01	0.019	0.024	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-32

Summary of Soil Sample Results for Investigation
Area 10
(Facility Entrance Area)
El Paso ASARCO Smelter, Remedial Investigation

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	EP-110	EP-110A	10/18/99	0-1 ft.	490	100	3000
		EP-110B	10/18/99	1-2 ft.	190	67	3100
		EP-110C	10/18/99	2-3 ft.	72	25	210
		EP-110D	10/18/99	3-4 ft.	71	10 U	60
		EP-110E	10/18/99	4-5 ft.	51	10 U	43
		EP-110F	10/18/99	7-8 ft.	11	10 U	84
		EP-110F2	10/18/99	7-8 ft.	12	10 U	68
Phase I	SSENT1	SSENT1-A	7/17/97	0 ft.	470	75	5700
		SSENT1-B	7/17/97	1.5 ft.	20 U	10 U	300
		SSENT1-C	7/17/97	3 ft.	20 U	10 U	160
		SSENT1-D	7/17/97	4 ft.	20 U	10 U	94
	SSENT2	SSENT2-A	7/17/97	0 ft.	340	100	3300
		SSENT2-B	7/17/97	1.5 ft.	20 U	10 U	330
		SSENT2-C	7/17/97	3 ft.	20 U	10 U	430
		SSENT2-D	7/17/97	4 ft.	20 U	10 U	26
	SSENT3	SSENT3-A	7/17/97	0 ft.	340	99	2800
		SSENT3-B	7/17/97	1.5 ft.	34	10 U	160
	SSENT4	SSENT4-A	7/17/97	0 ft.	190	80	1800
		SSENT4-B	7/17/97	1.5 ft.	35	10 U	37
	SSENT5	SSENT5-A	7/17/97	0 ft.	750	160	5400
		SSENT5-B	7/17/97	1.5 ft.	20 U	12	280
		SSENT5-B2	7/17/97	1.5 ft.	20 U	10 U	210
	SSENT6	SSENT6-A	7/17/97	0 ft.	380	100	3800
		SSENT6-B	7/17/97	1.5 ft.	20 U	34	2200
		SSENT6-C	7/17/97	3 ft.	20 U	10 U	610
		SSENT6-D	7/17/97	4 ft.	20 U	10 U	38
	SSENT7	SSENT7-A	7/17/97	0 ft.	250	93	2800
		SSENT7-B	7/17/97	1.5 ft.	20 U	10 U	30
		SSENT7-C	7/17/97	3 ft.	20 U	10 U	25
	SSENT8	SSENT8-A	7/17/97	0 ft.	520	120	3000
		SSENT8-A2	7/17/97	0 ft.	450	120	2800
		SSENT8-B	7/17/97	1.5 ft.	710	250	1300
	EP-89	EP-89A	6/18/97	0 ft.	34	110	9600
		EP-89B	6/18/97	5 ft.	20 U	10 U	42
		EP-89C	6/18/97	10 ft.	20 U	10 U	180

Table 2-32

**Summary of Soil Sample Results for Investigation
Area 10
(Facility Entrance Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	EP-89	EP-89D	6/18/97	15 ft.	20 U	10 U	22
		EP-89E	6/18/97	20 ft.	20 U	10 U	39
		EP-89F	6/18/97	25 ft.	20 U	10 U	92
		EP-89G	6/18/97	30 ft.	20 U	10 U	14
		EP-89H	6/18/97	35 ft.	20 U	10 U	44
		EP-89I	6/18/97	38 ft.	20 U	10 U	14

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-33

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-10
(Plant Entrance Area)
El Paso Asarco Smelter, Remedial Investigation**

Well ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-110	1/24/00		0.009		0.005 U		0.02 UJ1
	4/25/00		0.006		0.005 U		0.008
	8/2/00		0.007		0.005 U		0.005 U
	10/31/00		0.008		0.005 U		0.003 U
	2/8/01		0.008		0.005 U		0.004
	5/7/01		0.007		0.005 U		0.003 U
	7/17/01	0.013	0.013	0.005 U	0.005 U	0.003 U	0.003 U
EP-89	1/24/00		0.007		0.005 U		0.015 UJ1
	4/25/00		0.005		0.005 U		0.004
	4/25/00		0.005		0.005 U		0.005
	8/2/00		0.005 U		0.005 U		0.019
	10/31/00		0.005 U		0.005 U		0.006
	10/31/00		0.007		0.005 U		0.007
	2/8/01		0.005		0.005 U		0.005
	5/7/01		0.005		0.005 U		0.003
	5/7/01		0.005		0.005 U		0.003 U
	7/17/01	0.012	0.012	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH11-5	BH11-5A	5/9/01	0-1 ft.	170	31	1400
		BH11-5B	5/9/01	1-2 ft.	45	18	460
		BH11-5C	5/9/01	2-3 ft.	35	10 U	280
		BH11-5D	5/9/01	3-4 ft.	41	10 U	410
	BH11-6	BH11-6A	5/9/01	0-1 ft.	95	31	930
		BH11-6B	5/9/01	1-2 ft.	140	32	980
	BH11-7	BH11-7A	5/9/01	0-1 ft.	82	18	540
		BH11-7B	5/9/01	1-2 ft.	89	26	960
		BH11-7C	5/9/01	2-3 ft.	54	10 U	370
	BH11-8	BH11-8A	5/9/01	0-1 ft.	98	22	640
		BH11-8B	5/9/01	1-2 ft.	190	36	1700
		BH11-8C	5/9/01	2-3 ft.	53	16	440
		BH11-8D	5/9/01	3-4 ft.	43	14	340
	BH11-9	BH11-9A	5/9/01	0-1 ft.	110	20	670
		BH11-9B	5/9/01	1-2 ft.	59	10	510
		BH11-9C1	5/9/01	2-3 ft.	62	22	620
		BH11-9C2	5/9/01	2-3 ft.	29	16	260
	BH11-10	BH11-10A	5/9/01	0-1 ft.	110	14	620
		BH11-10B	5/9/01	1-2 ft.	55	13	320
		BH11-10C	5/9/01	2-3 ft.	68	12	640
		BH11-10D	5/9/01	3-4 ft.	41	18	260
	BH11-11	BH11-11A	5/9/01	0-1 ft.	193	45	1421
		BH11-11B	5/9/01	1-2 ft.	63	26	760
		BH11-11C	5/9/01	2-3 ft.	71	19	520
		BH11-11D	5/9/01	3-4 ft.	60	23	590
	BH11-12	BH11-12A	5/9/01	0-1 ft.	278	57	1876
		BH11-12B	5/9/01	1-2 ft.	35	11	200
		BH11-12C	5/9/01	2-3 ft.	23	15	130
		BH11-12D	5/9/01	3-4 ft.	46	14	300
	BH11-13	BH11-13A	5/9/01	0-1 ft.	91	18	370
		BH11-13B	5/9/01	1-2 ft.	40	12	360
		BH11-13C	5/9/01	2-3 ft.	21	15	120
	BH11-14	BH11-14A	5/9/01	0-1 ft.	146	31	972
		BH11-14B	5/9/01	1-2 ft.	84	10 U	640
		BH11-14C	5/9/01	2-3 ft.	32	10 U	180
		BH11-14D	5/9/01	3-4 ft.	33	12	290

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH11-15	BH11-15A	7/17/01	0-1 ft.	1200	200	7900
		BH11-15B	7/17/01	1-2 ft.	1300	440	12000
		BH11-15C	7/17/01	2-3 ft.	570	140	3700
		BH11-15D	7/17/01	3-4 ft.	910	280	7600
	BH11-16	BH11-16A	7/19/01	15-16 ft.	28	15	260
	BH11-17	BH11-17A	7/19/01	25-26 ft.	25	13	60
	BH11-18	BH11-18A1	7/19/01	40-41 ft.	32	12	130
		BH11-18A2	7/19/01	40-41 ft.	53	10 U	170
	BH11-19	BH11-19A	7/19/01	10-11 ft.	10	11	34
	BH11-22	BH11-22A	7/20/01	20-21 ft.	37	47	400
	BH11-23	BH11-23A	7/20/01	12-13 ft.	29	13	80
	BH11-24	BH11-24A	7/20/01	15-16 ft.	24	11	43
	BH11-25	BH11-25A	7/20/01	10-11 ft.	22	10 U	26
	BH11-26	BH11-26A	4/30/01	0-1 ft.	34	10	170
		BH11-26B	4/30/01	1-2 ft.	15	12	73
		BH11-26C	4/30/01	2-3 ft.	15	10 U	57
		BH11-26D	4/30/01	3-4 ft.	16	10 U	51
		BH11-26E	4/30/01	4-5 ft.	33	10 U	59
		BH11-26F2	4/30/01	10-11 ft.	15	14	58
		BH11-26G	4/30/01	15-16 ft.	25	10 U	56
		BH11-26H	4/30/01	25-26 ft.	22	10 U	48
	EP-129	EP-129A	5/2/01	0-1 ft.	150	33	910
		EP-129B	5/2/01	1-2 ft.	33	10 U	39
		EP-129C	5/2/01	2-3 ft.	32	10 U	36
		EP-129D	5/2/01	3-4 ft.	21	10 U	51
		EP-129E	5/2/01	4-5 ft.	25	10 U	40
		EP-129F	5/2/01	10-11 ft.	22	10 U	48
		EP-129G1	5/2/01	15-16 ft.	26	10 U	50
		EP-129G2	5/2/01	15-16 ft.	34	10 U	42
		EP-129H	5/2/01	20-21 ft.	37	10 U	69
		EP-129I	5/2/01	25-26 ft.	31	10 U	64
Phase II	BH11-2	BH11-2A	07/19/99	0-1 ft.	210	36	660
		BH11-2B	07/19/99	6-8 ft.	340	120	3300

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	BH11-2	BH11-2F	08/04/99	10-12 ft.	17	10 U	10 U
		BH11-2G	08/04/99	15-17 ft.	10 U	10 U	10 U
		BH11-2H	08/04/99	20-22 ft.	10 U	10 U	10 U
		BH11-2I	08/05/99	25-27 ft.	10 U	10 U	10 U
		BH11-2J	08/05/99	30-32 ft.	10 U	10 U	10 U
		BH11-2K	08/05/99	35-37 ft.	10 U	10 U	10 U
		BH11-2K2	08/05/99	DUP	10 U	10 U	10 U
		BH11-2L	08/05/99	40-42 ft.	10 U	10 U	10 U
	BH11-3	BH11-3F	08/05/99	10-12 ft.	55	17	1000
	BH11-4	BH11-4B	08/05/99	1-2 ft.	46	10 U	17
		BH11-4C	08/05/99	2-3 ft.	33	10 U	20
		BH11-4D	08/05/99	3-4 ft.	10 U	10 U	10 U
		BH11-4E	08/05/99	4-5 ft.	19	10 U	11
		BH11-4F	08/05/99	10-12 ft.	10 U	10 U	10 U
		BH11-4G	08/05/99	15-17 ft.	10 U	10 U	10 U
	SSIA11-1	SSIA11-1A	07/19/99	0-1 ft.	170	50	1500
		SSIA11-1B	07/19/99	1-2 ft.	33	16	520
		SSIA11-1C	07/19/99	2-3 ft.	10 U	10 U	290
	SSIA11-2	SSIA11-2A	07/19/99	0-1 ft.	82	25	1100
		SSIA11-2B	07/19/99	1-2 ft.	12	10 U	150
	SSIA11-3	SSIA11-3A	07/20/99	0-1 ft.	2200	940	14000
		SSIA11-3C	07/20/99	2-3 ft.	1700	580	11000
		SSIA11-3D	07/20/99	3-4 ft.	1800	570	12000
		SSIA11-3E	07/20/99	4-5 ft.	430	140	4400
	SSIA11-4	SSIA11-4A	07/20/99	0-1 ft.	790	300	11000
		SSIA11-4B	07/20/99	1-2 ft.	160	70	3100
		SSIA11-4C	07/20/99	2-3 ft.	52	21	1200
		SSIA11-4D	07/20/99	3-4 ft.	25	20	1100
		SSIA11-4E	07/20/99	4-5 ft.	23	11	850
	SSIA11-5	SSIA11-5A	07/20/99	0-1 ft.	20 U	10 U	150
		SSIA11-5A2	07/20/99	DUP	20 U	10 U	150
		SSIA11-5C	07/20/99	2-3 ft.	23	10 U	750
		SSIA11-5E	07/20/99	4-5 ft.	44	31	1200
	SSIA11-6	SSIA11-6A	07/20/99	0-1 ft.	480	120	2000
		SSIA11-6B	07/20/99	1-2 ft.	920	380	12000
		SSIA11-6C	07/20/99	2-3 ft.	4400	350	2100
		SSIA11-6D	07/20/99	3-4 ft.	7300	620	3100

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	SSIA11-6	SSIA11-6E	07/20/99	4-5 ft.	14000	1400	21000
	SSIA11-7	SSIA11-7A	07/20/99	0-1 ft.	2500	250	5800
		SSIA11-7A2	07/20/99	DUP	2500	150	5700
		SSIA11-7B	07/20/99	1-2 ft.	15000	260	11000
		SSIA11-7C	07/20/99	2-3 ft.	720	180	3700
		SSIA11-7D	07/20/99	3-4 ft.	750	170	3600
		SSIA11-7E	07/20/99	4-5 ft.	2800	240	6500
	SSIA11-8	SSIA11-8A	07/21/99	0-1 ft.	560	610	2900
		SSIA11-8B	07/21/99	1-2 ft.	880	290	3200
		SSIA11-8C	07/21/99	2-3 ft.	1700	360	7200
		SSIA11-8D	07/21/99	3-4 ft.	1700	330	7600
		SSIA11-8E	07/21/99	4-5 ft.	890	230	5800
	SSIA11-10	SSIA11-10A	08/04/99	0-1 ft.	160	12	730
		SSIA11-10B	08/04/99	1-2 ft.	23	10 U	150
		SSIA11-10D	08/04/99	3-4 ft.	10	10 U	10 U
	SSIA11-11	SSIA11-11A	08/14/99	0-1 ft.	65	22	450
		SSIA11-11B	08/14/99	1-2 ft.	42	10 U	180
		SSIA11-11C	08/14/99	2-3 ft.	17	10 U	11
		SSIA11-11D	08/14/99	3-4 ft.	10 U	10 U	10 U
		SSIA11-11E	08/14/99	4-5 ft.	11	10 U	10 U
	SSIA11-14	SSIA11-14B	08/06/99	1-2 ft.	17	13	10 U
		SSIA11-14C	08/06/99	2-3 ft.	23	10 U	10 U
		SSIA11-14D	08/06/99	3-4 ft.	13	10 U	10 U
		SSIA11-14E	08/06/99	4-5 ft.	17	10 U	10 U
	SSIA11-15	SSIA11-15A	08/06/99	0-1 ft.	51	10 U	130
		SSIA11-15B	08/06/99	1-2 ft.	30	10 U	380
		SSIA11-15C	08/06/99	2-3 ft.	44	10 U	950
		SSIA11-15D	08/06/99	3-4 ft.	84	14	430
		SSIA11-15E	08/06/99	4-5 ft.	13	10 U	35
	SSIA11-16	SSIA11-16B	08/06/99	1-2 ft.	21	10 U	34
		SSIA11-16C	08/06/99	2-3 ft.	19	10 U	10 U
		SSIA11-16D	08/06/99	3-4 ft.	20	10 U	10 U
		SSIA11-16E	08/06/99	4-5 ft.	10 U	10 U	10 U
		SSIA11-16E2	08/06/99	DUP	10 U	10 U	10 U
	SSIA11-17	SSIA11-17A	11/4/99	0-1 ft.	110	15	920 J4
	SSIA11-18	SSIA11-18A	11/5/99	0-1 ft.	150	45	1100

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	SSIA11-18	SSIA11-18B	11/5/99	1-2 ft.	230	86	2200
		SSIA11-18C	11/5/99	2-3 ft.	140	61	1300
	EP-93	EP-93A	07/21/99	0-1 ft.	27	10 U	93
		EP-93B	07/21/99	1-2 ft.	33	10 U	74
		EP-93C	07/21/99	2-3 ft.	27	10 U	170
		EP-93D	07/21/99	3-4 ft.	770	210	5600
		EP-93E	07/21/99	4-5 ft.	7100	14000	54000
		EP-93F	07/21/99	10-12 ft.	110	270	5600
		EP-93G	07/21/99	15-17 ft.	360	88	3900
		EP-93H	07/21/99	20-22 ft.	160	35	1600
		EP-93I	07/21/99	25-27 ft.	20 U	10 U	38
		EP-93J	07/21/99	30-32 ft.	20 U	10 U	49
		EP-93J2	07/21/99	30-32 ft.	20 U	13	45
		EP-93K	07/21/99	35-37 ft.	20 U	10 U	42
		EP-93L	07/21/99	40-42 ft.	20 U	10 U	39
		EP-93L	07/21/99	2-3 ft.	27	10 U	170
		EP-93M	07/21/99	45-47 ft.	10 U	10 U	10 U
		EP-93N	07/21/99	50-52 ft.	10 U	10 U	10 U
	EP-94	EP-94A	07/26/99	0-1 ft.	760 J4	560	5600
		EP-94A2	07/26/99	0-1 ft.	1300 J4	700	8000
		EP-94B	07/26/99	1-2 ft.	990 J4	180	8000
		EP-94C	07/26/99	2-3 ft.	620 J4	180	5200
		EP-94E	07/26/99	4-5 ft.	680 J4	170	3400
		EP-94E2	07/26/99	4-5 ft.	459	152	4368
		EP-94F	07/26/99	10-12 ft.	36 J4	17	580
		EP-94F2	07/26/99	10-12 ft.	65	12	420
		EP-94H	07/26/99	20-22 ft.	130 J4	85	1200
		EP-94I	07/26/99	25-27 ft.	10 J4	10 U	40
		EP-94J	07/26/99	30-32 ft.	10 J4	10 U	10 U
		EP-94K	07/26/99	35-37 ft.	27 J4	10 U	40
		EP-94L	07/26/99	40-42 ft.	10 J4	10 U	10 U
		EP-94M	07/26/99	45-47 ft.	10 J4	10 U	10 U
		EP-94N	07/26/99	50-52 ft.	10 J4	10 U	10 U
		EP-94O	07/26/99	55-57 ft.	10 J4	10 U	10 U
	EP-95	EP-95A	07/28/99	0 ft.	10 U	10 U	190
		EP-95B	07/28/99	1 ft.	10 U	10 U	120
		EP-95C	07/28/99	2 ft.	13	10 U	150
		EP-95D	07/28/99	3 ft.	10 U	10 U	21
		EP-95D2	07/28/99	3 ft.	10 U	10 U	30
		EP-95E	07/28/99	4 ft.	10 U	10 U	10 U

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-95R	EP-95RA	10/18/99	0-1 ft.	26	10 U	250
		EP-95RB	10/18/99	1-2 ft.	10 U	10 U	130
		EP-95RC	10/18/99	2-3 ft.	10 U	10 U	68
		EP-95RD	10/18/99	3-4 ft.	10 U	10 U	87
		EP-95RE	10/18/99	4-5 ft.	10 U	10 U	110
		EP-95RF	10/18/99	10-12 ft.	10 U	10 U	48
		EP-95RF2	10/18/99	10-12 ft.	10 U	10 U	50
		EP-95RG	10/18/99	15-17 ft.	10 U	10 U	40
		EP-95RH	10/18/99	20-22 ft.	10 U	10 U	39
		EP-95RI	10/18/99	25-27 ft.	16	10 U	39
		EP-95RJ	10/20/99	30-32 ft.	10 U	10 U	30
		EP-95RK	10/20/99	35-37 ft.	10 U	10 U	39
	EP-96	EP-96A	07/20/99	0-1 ft.	500	180	5100
		EP-96B	07/20/99	1-2 ft.	27	14	160
		EP-96C	07/20/99	2-3 ft.	42	10 U	90 J4
		EP-96D	07/20/99	3-4 ft.	32	10 U	150
		EP-96E	07/20/99	4-5 ft.	20 U	10 U	49 J4
		EP-96F	07/20/99	10-12 ft.	20 U	10 U	59 J4
		EP-96G	07/20/99	15-17 ft.	20 U	10 U	49 J4
		EP-96H	07/20/99	20-22 ft.	20 U	10 U	31 J4
		EP-96I	07/20/99	25-27 ft.	20 U	10 U	50 J4
		EP-96J	07/20/99	30-32 ft.	25	10 U	11 J4
		EP-96J2	07/20/99	30-32 ft.	20 U	10 U	41 J4
		EP-96K	07/20/99	35-37 ft.	20 U	10 U	49 J4
		EP-96L	07/20/99	40-42 ft.	20 U	10 U	54 J4
		EP-96M	07/20/99	45-47 ft.	20 U	10 U	46 J4
		EP-96N	07/20/99	50-52 ft.	20 U	10 U	49
		EP-96N2	07/20/99	50-52 ft.	20 U	10 U	51
		EP-96O	07/20/99	55-57 ft.	31	10 U	37
		EP-96P	07/20/99	60-62 ft.	20 U	10 U	27
	EP-97	EP-97A	08/04/99	0-1 ft.	64	19	340
		EP-97A2	08/04/99	0-1 ft.	62	10 U	380
		EP-97B	08/04/99	1-2 ft.	46	20	340
		EP-97C	08/04/99	2-3 ft.	71	16	500
	EP-98	EP-98A	08/06/99	0-1 ft.	41	12	250
		EP-98A2	08/06/99	0-1 ft.	60	11	320
		EP-98B	08/06/99	1-2 ft.	10 U	10 U	10 U
		EP-98C	08/06/99	1-3 ft.	10 U	10 U	10 U
		EP-98D	08/06/99	3-4 ft.	10 U	10 U	10 U
		EP-98E	08/06/99	4-5 ft.	10 U	10 U	10 U
		EP-98F	08/06/99	10-12 ft.	10 U	10 U	10 U
		EP-98G	08/06/99	15-17 ft.	10 U	10 U	10 U

Table 2-34

**Summary of Soil Sample Results for Investigation
Area 11 (Arroyos East of I-10)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	EP-98	EP-98H	08/06/99	20-22 ft.	10 U	10 U	10 U
Phase I	EP-83	EP-83A	6/11/97	7 ft.	20 U	10 U	20
		EP-83B	6/11/97	15 ft.	20 U	10 U	18
		EP-83C	6/11/97	20 ft.	20 U	10 U	21
		EP-83D	6/11/97	25 ft.	20 U	10 U	20
		EP-83E	6/11/97	30 ft.	20 U	10 U	10 U
		EP-83F	6/11/97	35 ft.	20 U	10 U	10 U
		EP-83F2	6/11/97	35 ft.	20 U	10 U	10 U
		EP-83G	6/11/97	40 ft.	20 U	10 U	10 U
		EP-83H	6/11/97	45 ft.	20 U	10 U	27
	EP-84	EP-84A	6/11/97	0 ft.	20 U	14	500
		EP-84B	6/11/97	5 ft.	20 U	16	500
		EP-84C	6/11/97	10 ft.	20 U	10 U	61
		EP-84D	6/11/97	15 ft.	20 U	10 U	33
	EP-87	EP-87A	6/16/97	0 ft.	20 U	10 U	14
		EP-87B	6/16/97	5 ft.	20 U	10 U	54
		EP-87C	6/16/97	10 ft.	20 U	10 U	11

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH11-1 is presented as EP-96.

Only slag at BH11-20, BH11-21, SSIA11-9, SSIA11-12 and SSIA11-13, no soil samples collected.

Table 2-35

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-11
(Arroyo East of I-10)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA11							
EP-83	1/27/00		0.006		0.005 U		0.003 U
	1/27/00		0.005		0.005 U		0.003
	5/1/00		0.008		0.005 U		0.003 UJ1
	8/9/00		0.005		0.005 U		0.003 U
	11/8/00		0.017		0.005 U		0.003 U
	11/8/00		0.016		0.005 U		0.004
	2/14/01		0.005		0.005 U		0.003 U
	5/11/01		0.01		0.005 U		0.003 U
	7/24/01	0.014	0.014	0.005 U	0.005 U	0.003 U	0.012
EP-84	1/27/00		0.029		0.007		0.087
	5/1/00		0.04		0.005		0.017 UJ1
	5/1/00		0.041		0.006		0.02 UJ1
	8/9/00		0.036		0.013		0.026
	8/9/00		0.035		0.013		0.02
	11/8/00		0.079		0.01		0.067
	2/14/01		0.025		0.005		0.029
	5/11/01		0.043		0.008		0.02 UJ1
	5/11/01		0.041		0.008		0.019 UJ1
	7/24/01	0.026	0.027	0.005 U	0.005 U	0.013	0.019
EP-93	1/27/00		0.031		0.005 U		0.033
	5/1/00		0.017		0.005 U		0.006 UJ1
	8/9/00		0.01		0.005 U		0.009
	11/8/00		0.022		0.005 U		0.006
	2/14/01		0.015		0.005 U		0.005
	5/11/01		0.019		0.005 U		0.005 UJ1
	7/24/01	0.033	0.03	0.005 U	0.005 U	0.003 U	0.012
EP-94	1/27/00		0.014		0.005 U		0.007
	5/1/00		0.014		0.005 U		0.026
	8/9/00		0.009		0.005 U		0.003 U
	11/8/00		0.015		0.005 U		0.003
	2/14/01		0.013		0.005 U		0.003 U
	5/11/01		0.016		0.005 U		0.005
	7/24/01	0.015	0.015	0.005 U	0.005 U	0.003 U	0.003 U
EP-95	1/27/00		0.009		0.005 U		0.003 U
	5/1/00		0.014		0.005 U		0.003 U
	8/9/00		0.011		0.005 U		0.003 U
	11/8/00		0.015		0.005 U		0.003 U
	2/14/01		0.015		0.005 U		0.003 U
	5/11/01		0.013		0.005 U		0.003 U
	7/24/01	0.017	0.017	0.005 U	0.005 U	0.003 U	0.003 U
	7/24/01	0.017	0.018	0.005 U	0.005 U	0.003 U	0.004
EP-96	1/27/00		0.007		0.005 U		0.01
	5/1/00		0.012		0.005 U		0.014 UJ1
	8/9/00		0.008		0.005 U		0.007

Table 2-35

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-11
(Arroyo East of I-10)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
EP-96	11/8/00		0.019		0.005 U		0.005
	2/14/01		0.014		0.005 U		0.003 U
	5/11/01		0.023		0.005 U		0.006 UJ1
	7/24/01	0.044	0.039	0.005 U	0.005 U	0.003 U	0.007
EP-97	1/27/00		0.14		0.013		0.13
	5/1/00		0.11		0.008		0.054
	8/9/00		0.15		0.009		0.024
	11/8/00		0.16		0.008		0.15
	2/14/01		0.12		0.012		0.18
	5/14/01		0.2		0.023		0.69
	7/24/01	0.14	0.15	0.011	0.012	0.017	0.035
EP-98	1/27/00		0.027		0.005 U		0.027
	5/1/00		0.037		0.005 U		0.003 UJ1
	8/9/00		0.021		0.005 U		0.004
	11/8/00		0.027		0.005 U		0.003 U
	2/14/01		0.022		0.005 U		0.006
	5/14/01		0.031		0.005 U		0.01
	5/14/01		0.032		0.005 U		0.008
	7/24/01	0.037	0.037	0.005 U	0.005 U	0.003 U	0.006
EP-129	5/11/01		0.011		0.005 U		0.007 UJ1
	7/24/01	0.007	0.008	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH12-10	BH12-10A	4/3/01	52-23 ft.	12	13	78
	BH12-11	BH12-11A	4/3/01	37-38 ft.	57	10 U	41
		BH12-11B2	4/3/01	42-43 ft.	43	10 U	48
	BH12-12	BH12-12A	4/3/01	47-48 ft.	50	13	200
		BH12-12B	4/3/01	52-53 ft.	19	11	55
	BH12-13	BH12-13A	4/4/01	46-47 ft.	20	12	43
		BH12-13B	4/4/01	51-52 ft.	41	13	140
	BH12-14	BH12-14A	4/4/01	43-44 ft.	27	10 U	70
		BH12-14B	4/4/01	50-51 ft.	37	10 U	77
	BH12-15	BH12-15A	4/4/01	49-50 ft.	520	2800	1500
		BH12-15A	4/4/01	49-50 ft.	616	1945	1487
		BH12-15B	4/4/01	51-52 ft.	73	11	230
	BH12-16	BH12-16A	4/4/01	48-49 ft.	49	10 U	100
		BH12-16B	4/4/01	53-54 ft.	30	10 U	65
	BH12-17	BH12-17A	4/5/01	48-49 ft.	260	72	1100
		BH12-17B	4/5/01	51-52 ft.	87	17	510
		BH12-17C	4/5/01	55-56 ft.	39	10 U	230
	BH12-18	BH12-18A	4/5/01	43-44 ft.	47	11	51
		BH12-18B	4/5/01	48-49 ft.	47	10 U	60
	BH12-19	BH12-19A	4/5/01	40-41 ft.	59	10 U	54
		BH12-19B	4/5/01	45-46 ft.	34	10 U	64
	BH12-20	BH12-20A	4/5/01	31-32 ft.	24	11	37
		BH12-20B	4/5/01	36-37 ft.	29	10	45
	BH12-21	BH12-21A	4/5/01	20-21 ft.	85	14	51
		BH12-21B	4/5/01	25-26 ft.	39	12	59
	BH12-22	BH12-22A	4/6/01	25-26 ft.	88	10 U	42
		BH12-22B	4/6/01	31-32 ft.	40	10 U	55
	BH12-23	BH12-23A	7/17/01	0-1 ft.	2700	2700	24000
		BH12-23B	7/17/01	1-2 ft.	2200	2600	19000
		BH12-23D	7/17/01	3-4 ft.	1800	2200	17000
		BH12-23E	7/17/01	4-5 ft.	1100	780	9300
		BH12-23F1	7/17/01	7-8 ft.	23	10 U	78
		BH12-23F2	7/17/01	7-8 ft.	21	10 U	63
		BH12-23G	7/17/01	10-11 ft.	29	10 U	68
		BH12-23H	7/17/01	12-13 ft.	27	10 U	96

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH12-23	BH12-23I	7/17/01	15-16 ft.	36	19	140
	BH12-24	BH12-24A	7/17/01	0-1 ft.	3200	3200	28000
		BH12-24B	7/17/01	1-2 ft.	730	450	1100
		BH12-24C	7/17/01	2-3 ft.	2400	1500	19000
		BH12-24E	7/17/01	4-5 ft.	88	41	560
		BH12-24F1	7/17/01	7-8 ft.	35	10 U	230
		BH12-24F2(D)	7/17/01	7-8 ft.	40	14	76
		BH12-24G	7/17/01	10-11 ft.	22	11	71
		BH12-24H	7/17/01	12-13 ft.	33	10 U	120
		BH12-24I	7/17/01	15-16 ft.	25	12	78
	BH12-25	BH12-25A	7/17/01	0-1 ft.	190	280	1100
		BH12-25B	7/17/01	1-2 ft.	89	31	180
		BH12-25C	7/17/01	2-3 ft.	23	19	77
		BH12-25D	7/17/01	4-5 ft.	24	10 U	81
		BH12-25E1	7/17/01	5-6 ft.	21	10 U	85
		BH12-25F	7/17/01	7-8 ft.	36	10 U	51
		BH12-25H	7/17/01	12-13 ft.	19	11	88
		BH12-25I	7/17/01	15-16 ft.	18	10 U	77
	BH12-26	BH12-26A	7/17/01	4-5 ft.	25	10 U	130
		BH12-26B	7/17/01	7-8 ft.	44	10 U	150
		BH12-26C1	7/17/01	10-11 ft.	13	10 U	66
		BH12-26C2	7/17/01	10-11 ft.	29	11	44
		BH12-26D	7/17/01	12-13 ft.	26	14	92
	BH12-27	BH12-27A	7/17/01	0-1 ft.	2200	2200	20000
		BH12-27B	7/17/01	1-2 ft.	210	30	1400
		BH12-27C	7/17/01	2-3 ft.	330	270	3500
		BH12-27D	7/17/01	4-5 ft.	16	20	170
		BH12-27E	7/17/01	7-8 ft.	34	10 U	180
	BH12-28	BH12-28A	7/18/01	15-16 ft.	36	24	190
	BH12-29	BH12-29A1	7/18/01	4-5 ft.	24	10	87
		BH12-29A2	7/18/01	4-5 ft.	32	10 U	81
		BH12-29B	7/18/01	7-8 ft.	44	16	64
		BH12-29C	7/18/01	10-11 ft.	25	12	43
		BH12-29D	7/18/01	12-13 ft.	34	10 U	80
	BH12-30	BH12-30A	7/18/01	10-11 ft.	31	10 U	47
		BH12-30B	7/18/01	12-13 ft.	22	10 U	41
		BH12-30C	7/18/01	15-16 ft.	22	10 U	59
		BH12-30D	7/18/01	17-18 ft.	23	12	53
	BH12-31	BH12-31A	7/18/01	7-8 ft.	35	10	91

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	BH12-31	BH12-31B	7/18/01	10-11 ft.	27	13	52
		BH12-31C	7/18/01	12-13 ft.	33	10 U	26
		BH12-31D	7/18/01	15-16 ft.	32	10 U	47
	BH12-32	BH12-32A1	7/18/01	7-8 ft.	120	26	670
		BH12-32B	7/18/01	12-13 ft.	34	10 U	110
		BH12-32C	7/18/01	15-16 ft.	44	10 U	150
	BH12-33	BH12-33A	7/18/01	12-13 ft.	15	10 U	91
	BH12-34	BH12-34A1	7/18/01	4-5 ft.	49	39	510
		BH12-34A2	7/18/01	4-5 ft.	430	470	5700
		BH12-34B	7/18/01	7-8 ft.	160	58	1300
		BH12-34C	7/18/01	10-11 ft.	73	14	170
		BH12-34D	7/18/01	12-13 ft.	250	180	2500
		BH12-34E	7/18/01	15-16 ft.	140	100	1600
	BH12-35	BH12-35A1	7/18/01	7-8 ft.	110	35	930
		BH12-35A2	7/18/01	7-8 ft.	70	18	690
		BH12-35B	7/18/01	10-11 ft.	74	21	530
		BH12-35C	7/18/01	12-13 ft.	29	10 U	51
		BH12-35D	7/18/01	15-16 ft.	68	24	460
		BH12-35E	7/18/01	17-18 ft.	63	25	480
	BH12-36	BH12-36A1	7/18/01	10-11 ft.	700	540	6100
		BH12-36A2	7/18/01	10-11 ft.	1300	1400	13000
		BH12-36B	7/18/01	12-13 ft.	100	83	1200
	BH12-37	BH12-37A	7/19/01	7-8 ft.	190	19	1100
		BH12-37B	7/19/01	10-11 ft.	120	13	670
		BH12-37C	7/19/01	15-16 ft.	19	10 U	41
		BH12-37D	7/19/01	18-19 ft.	33	12	32
	BH12-38	BH12-38A	7/19/01	5-6 ft.	27	10 U	59
	EP-120	EP-120A	4/6/01	5-6 ft.	77	10 U	150
		EP-120B	4/6/01	10-11 ft.	60	11	220
		EP-120C	4/6/01	15-16 ft.	23	10 U	120
	EP-121	EP-121A	4/10/01	10-11 ft.	51	17	180
	EP-123	EP-123A	4/12/01	21-22 ft.	800	33	1400
		EP-123B	4/12/01	23-24 ft.	77	13	170

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III cont.	EP-123	EP-123C1	4/12/01	25-26 ft.	21	10 U	71
		EP-123C2	4/12/01	25-26 ft.	22	10 U	130
		EP-123D	4/12/01	30-31 ft.	29	13	59
		EP-123E	4/12/01	35-36 ft.	10 U	10 U	48
		EP-123F	4/12/01	40-41 ft.	23	10 U	78
Phase II	BH12-1	BH12-1A	11/3/99	0-1 ft.	490	300	2700
		BH12-1B	11/3/99	3-4 ft.	10 U	10 U	140
		BH12-1C	11/3/99	4-5 ft.	10 U	10 U	150
		BH12-1D	11/3/99	10-12 ft.	10 U	10 U	10 U
		BH12-1E	11/3/99	15-16 ft.	10 U	10 U	10 U
		BH12-1E2	11/3/99	15-16 ft.	10 U	10 U	10 U
	BH12-2	BH12-2A	11/3/99	6-7 ft.	10 U	10 U	130
		BH12-2B	11/3/99	10-12 ft.	67	10	610
	BH12-3	BH12-3A	11/3/99	6-7 ft.	10	10 U	170
		BH12-3B	11/3/99	10-12 ft.	10 U	10 U	10 U
		BH12-3C	11/3/99	15-17 ft.	10 U	10 U	10 U
	BH12-4	BH12-4A	11/3/99	0-1 ft.	3100	3100	22000
		BH12-4B	11/3/99	1-2 ft.	3400	3400	23000
		BH12-4C	11/3/99	2-3 ft.	1200	1700	14000
		BH12-4D	11/3/99	3-4 ft.	10 U	10 U	110 J4
		BH12-4D2	11/3/99	10-12 ft.	15	10 U	20 J4
		BH12-4E	11/3/99	15-17 ft.	10 U	10 U	10 J4
	BH12-5	BH12-5A	11/4/99	8-10 ft.	10 U	15	10 U
	BH12-6	BH12-6A	11/4/99	12-13 ft.	120	10 U	21
	BH12-7	BH12-7A	11/4/99	6-8 ft.	10 U	10 U	33
		BH12-7B	11/4/99	10-12 ft.	33	38	52
		BH12-7B2	11/4/99	10-12 ft.	33	51	41
	BH12-8	BH12-8A	11/4/99	2-3 ft.	23	10 U	130
		BH12-8B	11/4/99	3-4 ft.	10 U	10 U	120
		BH12-8C	11/4/99	4-5 ft.	25	10 U	130
	BH12-9	BH12-9A	11/4/99	4-5 ft.	52	10 U	10 U
		BH12-9A2	11/4/99	4-5 ft.	59	10 U	10 U
		BH12-9B	11/4/99	8-9 ft.	76	10 U	10 U
	EP-108	EP-108A	10/14/99	10-12 ft.	19	10 U	41

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II	EP-108	EP-108B	10/14/99	15-16 ft.	82	10 U	67
	EP-109	EP-109XA	7/28/99	5-5.5 ft.	380	50	2900
		EP-109XB	7/28/99	10-11.5 ft.	180	18	660
		EP-109A	10/15/99	0-1 ft.	380	59	2000
		EP-109B	10/15/99	1-2 ft.	320	36	1900
		EP-109C	10/15/99	2-3 ft.	440	25	3600
		EP-109D	10/15/99	3-4 ft.	680	30	5000
		EP-109E	10/15/99	4-5 ft.	460	32	4000
		EP-109F	10/15/99	10-12 ft.	14	10 U	310
		EP-109G	10/15/99	15-17 ft.	10 U	10 U	33
		EP-109H	10/15/99	20-22 ft.	10 U	10 U	43
		EP-109H2	10/15/99	20-22 ft.	10 U	10 U	38
Phase I	RIBH1	RIBH-1A	6/19/97	40 ft.	4400	2100	11000
		RIBH-1B	6/19/97	45 ft.	1400	660	2200
		RIBH-1C	6/19/97	50 ft.	20 U	11	36
		RIBH-1D	6/19/97	55 ft.	20 U	10 U	67
		RIBH-1E	6/19/97	60 ft.	23	10 U	20
		RIBH-1E2	6/19/97	60 ft.	20 U	10 U	24
		RIBH-1F	6/19/97	62 ft.	20 U	10 U	320
	EP-78	EP-78A	6/4/97	23 ft.	990	46	530
		EP-78B	6/4/97	25 ft.	87	10 U	33
		EP-78C	6/4/97	30 ft.	82	10 U	34
		EP-78D	6/4/97	40 ft.	50	10 U	46
	EP-79	EP-79A	6/5/97	10 ft.	20 U	10 U	17
		EP-79B	6/5/97	15 ft.	32	10 U	30
		EP-79C	6/5/97	20 ft.	28	10 U	110
		EP-79D	6/5/97	25 ft.	210	10 U	240
		EP-79E	6/5/97	35 ft.	20 U	10 U	10 U
		EP-79F	6/5/97	40 ft.	20 U	10 U	12
		EP-79G	6/5/97	45 ft.	20 U	10 U	10
	EP-82	EP-82A	6/10/97	0 ft.	20 U	10 U	60
		EP-82B	6/10/97	5 ft.	20 U	10 U	23
		EP-82C	6/10/97	10 ft.	20 U	10 U	10 U
		EP-82D	6/10/97	15 ft.	20 U	10 U	10 U
		EP-82E	6/10/97	20 ft.	20 U	10 U	14
		EP-82F	6/10/97	25 ft.	20 U	10 U	15
		EP-82G	6/10/97	30 ft.	20 U	10 U	10 U
	EP-86	EP-86A	6/13/97	0 ft.	20 U	10 U	87

Table 2-36

**Summary of Soil Sample Results for Investigation
Area 12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I	EP-86	EP-86B	6/13/97	5 ft.	20 U	10 U	33
		EP-86C	6/13/97	10 ft.	20 U	10 U	16
		EP-86D	6/13/97	15 ft.	20 U	10 U	48
		EP-86E	6/13/97	20 ft.	20 U	10 U	39
		EP-86F	6/13/97	25 ft.	20 U	10 U	26
		EP-86G	6/13/97	30 ft.	20 U	10 U	25
		EP-86H	6/13/97	35 ft.	20 U	10 U	14
		EP-86I	6/13/97	40 ft.	20 U	10 U	16
		EP-86J	6/13/97	45 ft.	20 U	10 U	17
		EP-86K	6/13/97	50 ft.	20 U	10 U	14
		EP-86L	6/13/97	55 ft.	20 U	10 U	10 U
		EP-86M	6/13/97	60 ft.	20 U	10 U	10 U

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-37

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso Asarco Smelter, Remedial Investigation**

IA12							
EP-78	1/28/00		4.8		0.005 U		0.009
	5/2/00		4		0.005 U		0.004
	8/9/00		3.5		0.005 U		0.006
	11/9/00		3.8		0.005 U		0.013
	2/15/01		3.7		0.005 U		0.003 U
	5/14/01		3.9		0.005 U		0.012
	7/25/01	3.4	3.5	0.005 U	0.005 U	0.003 U	0.007
EP-79	1/28/00		0.006		0.005 U		0.004
	1/28/00		0.006		0.005 U		0.006
	5/2/00		0.008 UJ1		0.005 U		0.003 U
	8/9/00		0.007		0.005 U		0.003 U
	11/9/00		0.014		0.005 U		0.003
	2/15/01		0.01		0.005 U		0.003 U
	5/14/01		0.008		0.005 U		0.003 U
	7/25/01	0.02	0.024	0.005 U	0.005 U	0.003 U	0.003 U
EP-108	1/28/00		1.4		0.005 U		0.006
	5/2/00		1.2		0.005 U		0.006
	8/9/00		1.3		0.005 U		0.005
	11/9/00		1.2		0.005 U		0.003 U
	2/15/01		1.1		0.005 U		0.004
	5/14/01		1.1		0.005 U		0.007
	7/25/01	1.2	1.2	0.005 U	0.005 U	0.003 U	0.003
EP-109	1/28/00		0.014		0.005 U		0.039
	5/2/00		0.016 UJ1		0.005 U		0.006
	8/9/00		0.011		0.005 U		0.003 U
	11/9/00		0.019		0.005 U		0.003 U
	2/15/01		0.014		0.005 U		0.005
	5/14/01		0.013		0.005 U		0.003 U
	7/25/01	0.033	0.026	0.005 U	0.005 U	0.003 U	0.003 U
EP-120	5/7/01		0.27		0.005 U		0.003 U
	8/1/01	0.35	0.35	0.005 U	0.005 U	0.003 U	0.003 U
	8/1/01	0.35	0.36	0.005 U	0.005 U	0.003 U	0.003 U
EP-121	5/7/01		0.59		0.005 U		0.01
	8/1/01	0.57	0.6	0.005 U	0.005 U	0.003 U	0.003 U
EP-123	5/8/01		1.5		0.005 U		0.005
	7/25/01	1.7	1.7	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

Table 2-37

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-12
(Ephemeral Pond and Pond Sediment Storage Area)
El Paso Asarco Smelter, Remedial Investigation**

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/
or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-38

**Summary of Soil Sample Results for Investigation
Area 13 (Sample Mill Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH13-2	BH13-2A	7/20/01	15-16 ft.	470	92	5100
	BH13-3	BH13-3A	7/21/01	20-21 ft.	22	35	74
	BH13-4	BH13-4A	7/23/01	22-23 ft.	86	230	320
	BH13-9	BH13-9A	7/23/01	10-11 ft.	97	210	250
	BH13-10	BH13-10A	7/23/01	15-16 ft.	140	260	190
Phase II	BH13-1	BH13-11A1	7/23/01	25-26 ft.	26	47	1500
		BH13-13A1	7/23/01	15-16 ft.	880	140	13000
		BH13-13A2	7/23/01	15-16 ft.	1100	330	11000
		BH13-1A	10/21/99	0-1 ft.	67	46	860
		BH13-1C	10/21/99	19-21 ft.	45	3100	10 U
		BH13-1D	10/21/99	25-27 ft.	65	22	10 U
		BH13-1E	10/21/99	30-32 ft.	76	10 U	10 U
		BH13-1E2	10/21/99	30-32 ft.	65	10 U	10 U
		BH13-1F	10/21/99	35-37 ft.	39	10 U	10 U
		BH13-1G	10/21/99	40-42 ft.	54	10 U	10 U
	EP-101	BH13-1H	10/21/99	45-47 ft.	80	10 U	12
		BH13-1I	10/21/99	50-52 ft.	69	10 U	10 U
		BH13-1J	10/21/99	55-57 ft.	1000	17	10 U
		BH13-1K	10/29/99	60-62 ft.	87	10 U	20
		EP-101A	9/29/99	0-1 ft.	940	690	11000
		EP-101B	9/29/99	1-2 ft.	7700	2100	42000
		EP-101C	9/29/99	3-4 ft.	5200	1300	21000
		EP-101C	9/29/99	3-4 ft.	3350	1000	21800
		EP-101D	9/29/99	4-5 ft.	1100	8000	12000
		EP-101E	9/29/99	15-17 ft.	16	560	140
		EP-101F	9/29/99	20-22 ft.	23	190	69
	EP-102	EP-101G	9/29/99	25-27 ft.	84	670	87
		EP-101H	9/29/99	30-32 ft.	71	10 U	54
		EP-101H2	9/29/99	30-32 ft.	64	10 U	54
		EP-101I	9/29/99	35-37 ft.	65	10 U	45
		EP-101J	9/29/99	40-42 ft.	34	10 U	60
		EP-101K	9/29/99	45-47 ft.	33	10 U	53
		EP-101L	9/29/99	50-52 ft.	190	10 U	19
		EP-101L2	9/29/99	50-52 ft.	160	10 U	23
		EP-101M	9/29/99	55-57 ft.	91	10 U	57
		EP-102A	9/30/99	0-1 ft.	4100	3500	27000

Table 2-38

**Summary of Soil Sample Results for Investigation
Area 13 (Sample Mill Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	EP-102 cont.	EP-102B	9/30/99	1-2 ft.	6300	7100	34000
		EP-102C	9/30/99	2-3 ft.	7700	6000	41000
		EP-102D	9/30/99	3-4 ft.	8000	3900	40000
		EP-102E	9/30/99	4-5 ft.	950	11000	8700
		EP-102F	9/30/99	10-12 ft.	130	2100	200
		EP-102G	9/30/99	15-17 ft.	48	940	130
		EP-102G2	9/30/99	15-17 ft.	34	720	88
		EP-102G2	9/30/99	15-17 ft.	18	614	20
		EP-102H	9/30/99	20-22 ft.	56	1500	57
		EP-102I	9/30/99	25-27 ft.	52	190	63
		EP-102J	9/30/99	30-32 ft.	50	340	54
		EP-102K	9/30/99	35-37 ft.	36	28	77
		EP-102L	9/30/99	40-42 ft.	31	14	57
		EP-102M	9/30/99	45-47 ft.	38	15	61
		EP-102N	9/30/99	50-52 ft.	27	10 U	57
		EP-102N2	9/30/99	50-52 ft.	35	10	43
		EP-102O	9/30/99	55-57 ft.	35	10 U	50
		EP-102P	10/4/99	60-62 ft.	Insufficient sample for analysis.		
		EP-102Q	10/4/99	70-72 ft.	10 U	10 U	34

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH13-5 to BH13-8 and BH13-12 no samples/auger refusal

Table 2-39

Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-13
(Sample Mill Area)
El Paso Asarco Smelter, Remedial Investigation

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA13							
EP-13	1/25/00		34		0.53		0.025 UJ1
	4/26/00		32		0.57		0.008
	8/4/00		17		0.36		0.017
	11/2/00		29		0.56		0.009
	2/9/01		1.6		0.005 U		0.004
	5/8/01		25		0.54		0.006
	7/18/01	30	28	0.47	0.52	0.003 U	0.006 UJ1
EP-14	11/5/97	1.1		0.005 U		0.003 U	
	1/25/00		1.5		0.005 U		0.01 UJ1
	4/26/00		1.3		0.005 U		0.005
	8/4/00		1.3		0.005 U		0.004
	8/4/00		1.3		0.005 U		0.004
	11/2/00		1.4		0.005 U		0.004
	2/9/01		23		0.52		0.013
	5/8/01		1.4		0.005 U		0.004
	7/18/01	1.5	1.5	0.005 U	0.005 U	0.003	0.004 UJ1
EP-90	1/24/00		0.12		0.005 U		0.011 UJ1
	4/26/00		0.12		0.006		0.005
	8/4/00		0.13		0.01		0.003
	11/3/00		0.14		0.008		0.003 U
	11/3/00		0.14		0.008		0.003 U
	2/12/01		0.14		0.005 U		0.006
	5/8/01		0.14		0.016		0.004
	7/19/01	0.14	0.15	0.01	0.011	0.003 U	0.014 J4
	7/19/01	0.14	0.14	0.01	0.011	0.003 U	0.003 U,UJ4
EP-101	1/25/00		4.5		0.72		0.018 UJ1
	4/26/00		6.3		1.1		0.033
	8/4/00		6.8		1.3		0.012
	11/2/00		7.3		1.7		0.011
	2/9/01		6.3		1.4		0.004
	5/8/01		4.7		1.6		0.005
	7/18/01	5.3	5.2	1.5	1.6	0.003 U	0.007 UJ1
EP-102	1/25/00		0.21		0.075		0.012 UJ1
	4/26/00		0.26		0.095		0.012
	8/4/00		0.28		0.099		0.009
	11/3/00		0.24		0.053		0.007
	2/9/01		0.38		0.095		0.012
	5/8/01		0.4		0.11		0.006
	7/18/01	0.3	0.3	0.13	0.17	0.003 U	0.01 UJ1
EP-103	1/24/00		0.011		0.005 U		0.013 UJ1
	4/26/00		0.016		0.005 U		0.01
	8/4/00		0.023		0.007		0.003 U
	11/2/00		0.008		0.005 U		0.003 U
	2/12/01		0.022		0.005 U		0.003 U

Table 2-39

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-13
(Sample Mill Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
	5/8/01		0.019		0.007		0.003 U
	7/19/01	0.044	0.04	0.005 U	0.005 U	0.003 U	0.003 U,UJ4

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-40

**Summary of Soil Sample Results for Investigation
Area 14 (South Terrace Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase III	BH14-4	BH14-4A	4/10/01	0-1 ft.	670	140	3800
		BH14-4B	4/10/01	1-2 ft.	27	15	440
		BH14-4C	4/10/01	2-3 ft.	28	11	180
		BH14-4D	4/10/01	3-4 ft.	19	10 U	70
		BH14-4E	4/10/01	4-5 ft.	10 U	10 U	14
		BH14-4F	4/10/01	10-11 ft.	11	10 U	36
	BH14-5	BH14-5A	4/10/01	0-1 ft.	170	110	3200
		BH14-5A	4/10/01	0-1 ft.	105	118	3037
		BH14-5B	4/10/01	1-2 ft.	100	35	1300
		BH14-5D	4/10/01	3-4 ft.	310	88	3000
		BH14-5E	4/10/01	4-5 ft.	280	66	2800
		BH14-5F1	4/10/01	10-11 ft.	10 U	10 U	21
		BH14-5F2	4/10/01	10-11 ft.	10 U	10 U	23
	BH14-6	BH14-6A	4/16/01	0-1 ft.	130	28	950
		BH14-6B	4/16/01	1-2 ft.	68	10 U	330
		BH14-6C	4/16/01	2-3 ft.	76	10 U	350
		BH14-6D	4/16/01	3-4 ft.	21	10 U	46
		BH14-6E	4/16/01	4-5 ft.	33	11	140
		BH14-6F1	4/16/01	10-11 ft.	10 U	10 U	15
		BH14-6F2	4/16/01	10-11 ft.	10 U	10 U	31
Phase II	BH14-1	BH14-1A	11/5/99	13.2-15 ft.	100	84	31
		BH14-1B	11/5/99	15-17 ft.	110	92	20
		BH14-1C	11/5/99	20-22 ft.	150	70	10 U
		BH14-1D	11/5/99	25-27 ft.	36	10 U	21
		BH14-1E	11/5/99	30-32 ft.	12	10 U	17
		BH14-1F	11/5/99	35-37 ft.	10 U	10 U	10 U
		BH14-1F2	11/5/99	35-37 ft.	10 U	10 U	10 U
		BH14-1G	11/5/99	40-42 ft.	16	10 U	10 U
		BH14-1H	11/5/99	45-47 ft.	10 U	10 U	13
		BH14-1I	11/5/99	50-52 ft.	10 U	10 U	10 U
		BH14-1J	11/5/99	55-57 ft.	10 U	10 U	10 U
		BH14-1K	11/5/99	60-62 ft.	40	10 U	10 U
		BH14-1L	11/8/99	65-67 ft.	10 U	10 U	10 U
		BH14-1L2	11/8/99	65-67 ft.	10 U	10 U	10 U
		BH14-1M	11/8/99	70-72 ft.	10 U	10 U	10 U
	BH14-2	BH14-2A	12/16/99	0 ft.	210	130	1400
		BH14-2B	12/16/99	1 ft.	170	87	2800
		BH14-2C	12/16/99	2 ft.	210	140	4400
		BH14-2D	12/16/99	3 ft.	62	18	510
		BH14-2E	12/16/99	4 ft.	210	18	970
		BH14-2F	12/16/99	10 ft.	10 U	12	26 J4
		BH14-2G	12/16/99	15 ft.	10 U	10 U	10 J4

Table 2-40

**Summary of Soil Sample Results for Investigation
Area 14 (South Terrace Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase II cont.	BH14-2 cont.	BH14-2H	12/16/99	20 ft.	11	10 U	10 J4
		BH14-2I	12/16/99	25 ft.	17	10 U	21 J4
		BH14-2I2	12/16/99	25 ft.	10 U	10 U	42 J4
		BH14-2J	12/16/99	30 ft.	10	12	50 J4
		BH14-2K	12/16/99	35 ft.	17	10 U	48 J4
		BH14-2L	12/16/99	40 ft.	16	10 U	47 J4
		BH14-2M	12/16/99	45 ft.	26	10 U	15 J4
		BH14-2O	12/16/99	50 ft.	10 U	12	10 J4
		BH14-2P	12/16/99	55 ft.	16	10 U	10 J4
		BH14-2Q	12/16/99	60 ft.	10 U	10 U	10 U
		BH14-2Q2	12/16/99	60 ft.	10 U	10 U	10 U
	BH14-3	BH14-3A	12/15/99	0 ft.	10 U	16	2600
		BH14-3B	12/15/99	1 ft.	27	10 U	420
		BH14-3C	12/15/99	2 ft.	10 U	10 U	250
		BH14-3D	12/15/99	3 ft.	10 U	10 U	190
		BH14-3E	12/15/99	4 ft.	10 U	10 U	65
		BH14-3F	12/15/99	10 ft.	10 U	10 U	74
		BH14-3G	12/15/99	15 ft.	43	10 U	530
		BH14-3H	12/15/99	20 ft.	19	11	33
		BH14-3I	12/15/99	25 ft.	23	10 U	62
		BH14-3J	12/15/99	30 ft.	20	10 U	31
		BH14-3J2	12/15/99	30 ft.	15	10 U	28
		BH14-3K	12/15/99	35 ft.	10 U	10 U	65
		BH14-3L	12/15/99	40 ft.	11	10 U	54
		BH14-3M	12/15/99	45 ft.	10 U	10 U	10 U
		BH14-3N	12/15/99	50 ft.	12	10 U	10 U
		BH14-3O	12/15/99	55 ft.	10 U	12	10 U
		BH14-3P	12/15/99	60 ft.	10 U	13	10 U
		BH14-3Q	12/15/99	65 ft.	10 U	10 U	10 U
		BH14-3Q2	12/15/99	65 ft.	10 U	10 U	10 U
Phase I	EP-70	EP-70A	5/30/97	20 ft.	230	79	28
		EP-70B	5/30/97	25 ft.	130	210	20
		EP-70C	5/30/97	30 ft.	130	20	24
		EP-70D	5/30/97	35 ft.	320	190	20
		EP-70E	5/31/97	40 ft.	390	51	18
		EP-70F	5/31/97	45 ft.	120	70	18
	EP-70R	EP-70RA	6/12/97	9 ft.	36	27	41
		EP-70RB	6/12/97	15 ft.	20 U	10 U	16
		EP-70RB2	6/12/97	15 ft.	20 U	10 U	19
		EP-70RC	6/12/97	20 ft.	20 U	10 U	25
		EP-70RD	6/12/97	25 ft.	20 U	10 U	22
		EP-70RE	6/12/97	30 ft.	20 U	10 U	16

Table 2-40

**Summary of Soil Sample Results for Investigation
Area 14 (South Terrace Area)
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Phase I cont.	EP-70R cont.	EP-70RF	6/12/97	35 ft.	20 U	10 U	27
		EP-70RG	6/12/97	40 ft.	20 U	10 U	20
		EP-70RH	6/12/97	45 ft.	20 U	10 U	45
		EP-70RI	6/12/97	50 ft.	20 U	10 U	12
		EP-70RJ	6/12/97	55 ft.	20 U	10 U	10 U
		EP-70RK	6/12/97	60 ft.	20 U	10 U	16
		EP-70RL	6/12/97	65 ft.	20 U	10 U	10 U
		EP-70RM	6/12/97	70 ft.	20 U	10 U	10 U
	EP-71	EP-71A	5/31/97	0 ft.	20 U	18	40
		EP-71B	5/31/97	5 ft.	20 U	10 U	20
		EP-71C	5/31/97	10 ft.	20 U	10 U	49
		EP-71D	5/31/97	15 ft.	20 U	10 U	33
		EP-71E	5/31/97	25 ft.	20 U	10 U	59
	EP-71R	EP-71RA	6/11/97	0 ft.	1300	120	7200
		EP-71RB	6/11/97	5 ft.	20 U	10 U	90
		EP-71RC	6/11/97	10 ft.	20 U	10 U	54
		EP-71RD	6/11/97	15 ft.	20 U	10 U	10 U
		EP-71RE	6/12/97	20 ft.	20 U	10 U	20
		EP-71RF	6/12/97	25 ft.	20 U	10 U	19
		EP-71RG	6/12/97	30 ft.	20 U	10 U	29
		EP-71RH	6/12/97	35 ft.	20 U	10 U	13
		EP-71RI	6/12/97	40 ft.	20 U	10 U	11
		EP-71RJ	6/12/97	45 ft.	20 U	10 U	10 U
		EP-71RK	6/12/97	50 ft.	20 U	10 U	13
		EP-71RL	6/12/97	60 ft.	20 U	10 U	10 U
		EP-71RL2	6/12/97	60 ft.	20 U	10 U	10 U
	EP-72	EP-72A	5/31/97	15 ft.	20 U	220	530
		EP-72B	5/31/97	20 ft.	20 U	10 U	32
		EP-72C	6/1/97	25 ft.	20 U	10 U	22
		EP-72C2	6/1/97	25 ft.	20 U	10 U	24
		EP-72D	6/1/97	30 ft.	67	25	23
		EP-72E	6/1/97	35 ft.	54	10 U	38
		EP-72F	6/1/97	40 ft.	20 U	10 U	29

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-41

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-14
(South Terrace Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA14							
EP-70	1/24/00		0.63		0.007		0.01 UJ1
	1/24/00		0.64		0.008		0.009 UJ1
	4/25/00		0.59		0.007		0.003 U
	8/3/00		0.56		0.006		0.005 U
	11/1/00		0.57		0.006		0.003 U
	11/1/00		0.58		0.006		0.003 U
	2/9/01		0.56		0.005		0.003 U
	5/7/01		0.6		0.005		0.003 U
	7/18/01	0.73	0.73	0.005 U	0.005 U	0.003 U	0.003 U
EP-71	1/24/00		0.11		0.005 U		0.008 UJ1
	4/24/00		0.11		0.005 U		0.003 U
	8/3/00		0.11		0.005 U		0.005 U
	8/3/00		0.11		0.005 U		0.005 U
	11/1/00		0.11		0.005 U		0.003 U
	2/9/01		0.093		0.005 U		0.003 U
	2/9/01		0.11		0.005 U		0.003 U
	5/7/01		0.11		0.005 U		0.003 U
	7/18/01	0.11	0.12	0.005 U	0.005 U	0.003 U	0.003 U
	7/18/01	0.12	0.12	0.005 U	0.005 U	0.003 U	0.003 U
EP-72	1/24/00		0.065		0.005 U		0.011 UJ1
	4/25/00		0.069		0.005 U		0.003
	8/3/00		0.05 U		0.005 U		0.005 U
	11/1/00		0.14		0.005 U		0.007
	2/9/01		0.14		0.006		0.003 U
	5/7/01		0.093		0.005 U		0.003 U
	7/18/01	0.094	0.17	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-42

Summary of Soil Sample Results for Investigation Area 15
El Paso ASARCO Smelter, Remedial Investigation

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH15-8	BH15-8B	2/20/01	1-2 ft.	20000	890	3700
		BH15-8C	2/20/01	2-3 ft.	900	320	520
		BH15-8E	2/20/01	4-5 ft.	1900	310	1000
		BH15-8F	2/20/01	5-6 ft.	25	39	45
	BH15-12	BH15-12C	2/20/01	7-8 ft.	66	10 U	790
		BH15-12D	2/20/01	8-9 ft.	22	10 U	32
		BH15-12E1	2/20/01	9-10 ft.	17	18	170
		BH15-12E2	2/20/01	9-10 ft.	29	10 U	280
		BH15-12F	2/20/01	10-11 ft.	19	130	51
	BH15-13	BH15-13A	6/1/01	20-21 ft.	38	10 U	57
		BH15-13B	6/1/01	25-26 ft.	34	10 U	41
		BH15-13C	6/1/01	30-31 ft.	33	12	40
		BH15-13D	6/1/01	40-41 ft.	40	10 U	36
		BH15-13E	6/1/01	45-46 ft.	21	10 U	47
		BH15-13F	6/1/01	50-51 ft.	27	11	47
		BH15-13G	6/1/01	55-56 ft.	32	10 U	42
		BH15-13H	6/1/01	60-61 ft.	29	10 U	46
		BH15-13I	6/1/01	65-66 ft.	34	10 U	38
		BH15-13J	6/1/01	70-71 ft.	35	10 U	23
	BH15-14	BH15-14A	6/1/01	50-51 ft.	17	10	31
		BH15-14B1	6/1/01	55-56 ft.	19	10 U	33
		BH15-14B2	6/1/01	55-56 ft.	19	10 U	43
		BH15-14C	6/1/01	60-61 ft.	36	19	32
		BH15-14D	6/1/01	65-66 ft.	34	10 U	31
		BH15-14E	6/1/01	70-71 ft.	87	25	28
		BH15-14E	6/1/01	70-71 ft.	102	29	13
	EP-130	EP-130A	5/29/01	50-51 ft.	340	27	61
		EP-130B	5/29/01	55-56 ft.	31	10 U	34
		EP-130C	5/29/01	60-61 ft.	56	10 U	30
		EP-130D	5/29/01	65-66 ft.	53	10 U	32
		EP-130E	5/29/01	70-71 ft.	65	10 U	56
		EP-130F	5/29/01	75-76 ft.	35	15	24
		EP-130G	5/29/01	80-81 ft.	64	10 U	39
	EP-131	EP-131A	5/30/01	0-1 ft.	900	200	4500
		EP-131B1	5/30/01	40-41 ft.	37	14	80
		EP-131B2	5/30/01	40-41 ft.	27	10 U	93
		EP-131C	5/30/01	45-46 ft.	34	10 U	74
		EP-131D	5/30/01	50-51 ft.	27	10 U	42
		EP-131E	5/30/01	55-56 ft.	26	10 U	42

Table 2-42

**Summary of Soil Sample Results for Investigation Area 15
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
		EP-131F	5/30/01	60-61 ft.	21	10	38
Closed Plant	EP-131 cont.	EP-131G	5/30/01	65-66 ft.	31	10 U	56
		EP-131H	5/30/01	70-71 ft.	46	18	160

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH15-1 to BH15-7 and BH15-9 to BH15-11 no samples taken, slag

Table 2-43

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-15
(Former Copper Plant Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA15							
EP-26	1/26/00		0.085		0.29		0.12
	4/28/00		0.31		0.29		0.014
	8/7/00		0.38		0.35		0.008
	11/7/00		0.3		0.26		0.01
	2/20/01		0.26		0.21		0.006
	5/10/01		0.26		0.34		0.006
	5/10/01		0.28		0.35		0.006
	7/26/01	0.39	0.38	0.43	0.41	0.003 U	0.003 U
EP-56	2/1/00		2.7 J4		0.005 U		0.017
	2/1/00		2.1 J4		0.005 U		0.015
	5/3/00		1.2		0.005 U		0.026
	8/16/00		1.4		0.005 U		0.036
	11/13/00		2.5		0.005 U		0.02
	2/22/01		2.1		0.005 U		0.035
	5/10/01		3.1		0.005 U		0.099
	7/26/01	3	3	0.005 U	0.005 U	0.003 U	0.038
EP-130	6/8/01	0.44	0.56	0.005 U	0.005 U	0.003 U	0.005
	7/26/01	0.13	0.16	0.005 U	0.005 U	0.003	0.033
	7/26/01	0.13	0.16	0.005 U	0.005 U	0.003	0.034
	6/8/01	0.91	0.9	0.005 U	0.005 U	0.003 U	0.005
	7/26/01	1.2	1.3	0.005 U	0.005	0.003 U	0.02
EP-131	6/8/01	0.91	0.9	0.005 U	0.005 U	0.003 U	0.005
	7/26/01	1.2	1.3	0.005 U	0.005	0.003 U	0.02

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-44

**Summary of Soil Sample Results for Investigation Area 16
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH16-1	BH16-1F	2/28/01	11-12 ft.	43	10 U	89
	BH16-2	BH16-2E1	2/28/01	15-17 ft.	44	10 U	47
		BH16-2E2	2/28/01	15-17 ft.	53	10 U	52
	BH16-3	BH16-3D	2/21/01	3.5-4.5 ft.	34	10 U	80
		BH16-3E	2/21/01	4.5-5.5 ft.	36	10 U	100
		BH16-3F	2/28/01	11-12 ft.	10 U	10 U	26
	BH16-4	BH16-4G	2/28/01	10-11 ft.	18	10 U	32
	BH16-5	BH16-5F	2/28/01	5-6 ft.	47	10 U	59
		BH16-5G	2/28/01	15-16 ft.	68	10 U	290
		BH16-5H1	2/28/01	20-21 ft.	71	13	77
		BH16-5H2	2/28/01	20-21 ft.	77	10 U	79
	BH16-7	BH16-7B	2/28/01	1-2 ft.	43	32	220
	BH16-8	BH16-8D	2/28/01	5-6 ft.	51	1000	70
		BH16-8E	2/28/01	11-12 ft.	59	710	53
		BH16-8F	2/28/01	15-16 ft.	42	570	65
	BH16-9	BH16-9E	2/21/01	4-5 ft.	150	62	1600
		BH16-9F	2/21/01	5-6 ft.	36	11	49
	BH16-10	BH16-10A	3/1/01	30-31 ft.	32	10 U	95
		BH16-10B1	3/1/01	35-36 ft.	33	10 U	120
		BH16-10B2	3/1/01	35-36 ft.	42	10 U	120
	BH16-11	BH16-11B	2/22/01	3-4 ft.	35	10 U	190
		BH16-11C	2/22/01	4-5 ft.	240	33	3500
		BH16-11D	2/22/01	5-6 ft.	110	22	1100
		BH16-11E	2/22/01	6-7 ft.	69	10 U	580
		BH16-11F	2/22/01	7-8 ft.	56	10 U	100
	BH16-14	BH16-14D	2/22/01	3-4 ft.	59	13	750
		BH16-14E	2/22/01	4-5 ft.	59	10 U	75
		BH16-14F	2/22/01	10-11 ft.	75	10 U	560
	BH16-18	BH16-18B1	2/22/01	1-2 ft.	34	10 U	88
		BH16-18B2	2/22/01	1-2 ft.	26	10 U	82
		BH16-18C	2/22/01	2-3 ft.	130	18	560
		BH16-18D	2/22/01	3-4 ft.	80	13	470
		BH16-18E	2/22/01	4-5 ft.	130	21	680

Table 2-44

**Summary of Soil Sample Results for Investigation Area 16
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant cont.	BH16-18 cont.	BH16-18F	2/22/01	5-6 ft.	58	11	310
	BH16-19	BH16-19A	2/22/01	0-1 ft.	1200	410	6900
		BH16-19A	2/22/01	0-1 ft.	1001	400	6802
		BH16-19B	2/22/01	1-2 ft.	52	10 U	440
		BH16-19C	2/22/01	4-5 ft.	100	40	860
		BH16-19D	2/22/01	5-6 ft.	43	11	120
	BH16-20	BH16-20C	2/22/01	3-4 ft.	1700	530	11000
		BH16-20D	2/22/01	5-6 ft.	1100	410	7300
		BH16-20E	2/22/01	13-14 ft.	450	120	4100
		BH16-20F	2/22/01	16-17 ft.	140	10 U	110
	BH16-21	BH16-21G	2/23/01	14-15 ft.	48	12	1870
		BH16-21G	2/23/01	14-15 ft.	48	12	1870
	BH16-22	BH16-22E	2/23/01	8-9 ft.	23	10 U	61
		BH16-22F	2/23/01	14-15 ft.	42	10 U	39
	BH16-23	BH16-23F	2/23/01	8-9 ft.	140	49	900
		BH16-23G1	2/23/01	9-10 ft.	34	10 U	49
		BH16-23G2	2/23/01	9-10 ft.	49	10 U	50
	BH16-24	BH16-24D	2/23/01	3-4 ft.	100	22	110
		BH16-24E	2/23/01	4-5 ft.	450	140	630
		BH16-24F	2/23/01	8-9 ft.	490	55	1700
		BH16-24G	2/23/01	11-12 ft.	190	290	1300
	BH16-25	BH16-25D	2/23/01	3-4 ft.	94	27	690
		BH16-25E	2/23/01	4-5 ft.	160	47	1700
		BH16-25F	2/23/01	5-6 ft.	44	10 U	370
		BH16-25G	2/23/01	9-10 ft.	49	10 U	200
		BH16-25H	2/23/01	14-15 ft.	21	10 U	68
	BH16-26	BH16-26A	2/23/01	1-2 ft.	100	98	730
		BH16-26B	2/23/01	2-3 ft.	40	10 U	68
		BH16-26C1	2/23/01	3-4 ft.	170	70	2100
		BH16-26C2	2/23/01	3-4 ft.	110	92	1700
		BH16-26D	2/23/01	4-5 ft.	83	58	1000
		BH16-26E	2/23/01	6-7 ft.	34	10 U	39
		BH16-26F	2/23/01	9-10 ft.	44	10 U	240
	BH16-27	BH16-27F	2/23/01	10-11 ft.	190	110	1000
		BH16-27G	2/23/01	11-12 ft.	71	48	250

Table 2-44

Summary of Soil Sample Results for Investigation Area 16
El Paso ASARCO Smelter, Remedial Investigation

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant cont.	BH16-28	BH16-28D	2/26/01	3.5-4.5 ft.	52	10 U	310
		BH16-28E	2/26/01	4.5-5.5 ft.	49	23	120
		BH16-28E	2/26/01	4.5-5.5 ft.	15	14	92
		BH16-28F	2/26/01	5.5-6 ft.	22	10	35
	BH16-29	BH16-29G	2/26/01	8-9 ft.	160	65	180
	BH16-30	BH16-30B	2/26/01	1-2 ft.	64	10 U	230
		BH16-30B2	2/26/01	1-2 ft.	37	10 U	183
		BH16-30C	2/26/01	2-3 ft.	90	10	220
		BH16-30D1	2/26/01	5-6 ft.	36	10 U	49
		BH16-30D2	2/26/01	5-6 ft.	43	10 U	62
	BH16-40	BH16-40F	2/26/01	5-6 ft.	22	17	170
	BH16-45	BH16-45A	2/28/01	61-62 ft.	70	89	180
Phase I	EP-74	EP-74A	6/2/97	2 ft.	20 U	10 U	300
		EP-74B	6/2/97	5 ft.	20 U	28	960
		EP-74C	6/2/97	10 ft.	20 U	10 U	100
		EP-74D	6/2/97	15 ft.	140	10 U	250
		EP-74E	6/2/97	20 ft.	20 U	10 U	38
		EP-74F	6/2/97	25 ft.	20 U	10 U	19
		EP-74G	6/2/97	30 ft.	20 U	10 U	24
		EP-74H	6/2/97	35 ft.	20 U	10 U	26
		EP-74I	6/2/97	40 ft.	20 U	10 U	22
		EP-74J	6/2/97	45 ft.	41	10 U	42
		EP-74K	6/2/97	50 ft.	49	10 U	11
		EP-74L	6/2/97	55 ft.	40	10 U	10 U
		EP-74M	6/2/97	60 ft.	46	10 U	19
		EP-74M2	6/2/97	60 ft.	28	10 U	23
		EP-74N	6/2/97	65 ft.	24	10 U	16

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

BH16-6, BH16-12, BH16-13, BH16-15 to BH16-17, BH16-31 to BH16-39
 and BH16-41 to BH16-44 no samples/slag

Table 2-45

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-16
(Former Lead and Sinter Plants Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA16							
EP-90	1/24/00		0.12		0.005 U		0.011 UJ1
	4/26/00		0.12		0.006		0.005
	8/4/00		0.13		0.01		0.003
	11/3/00		0.14		0.008		0.003 U
	11/3/00		0.14		0.008		0.003 U
	2/12/01		0.14		0.005 U		0.006
	5/8/01		0.14		0.016		0.004
	7/19/01	0.14	0.15	0.01	0.011	0.003 U	0.014 J4
	7/19/01	0.14	0.14	0.01	0.011	0.003 U	0.003 U,UJ4

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-46

**Summary of Soil Sample Results for Investigation Area 17
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH17-1	BH17-1A1	3/1/01	10-11 ft.	250	78	47
		BH17-1A2	3/1/01	10-11 ft.	190	61	46
		BH17-1B	3/1/01	15-16 ft.	61	35	39
	BH17-2	BH17-2A	3/1/01	22-23 ft.	430	20	64
		BH17-2B	3/1/01	27-28 ft.	150	10 U	97
	BH17-3	BH17-3A	3/1/01	15-16 ft.	34	10 U	78
		BH17-3B	3/1/01	19-20 ft.	54	36	170
	BH17-4	BH17-4A1	3/1/01	17-18 ft.	37	10 U	100
		BH17-4A2	3/1/01	17-18 ft.	32	10 U	96
		BH17-4B	3/1/01	21-22 ft.	21	10 U	52
	BH17-5	BH17-5A	3/2/01	12-13 ft.	230	10 U	34
		BH17-5B1	3/2/01	17-18 ft.	470	23	54
		BH17-5B2	3/2/01	17-18 ft.	460	31	68
	BH17-6	BH17-6A	3/2/01	10-11 ft.	31	13	54
		BH17-6A	3/2/01	10-11 ft.	11	10 U	14
		BH17-6B	3/2/01	15-16 ft.	25	10 U	50
	BH17-7	BH17-7A	3/2/01	15-16 ft.	31	58	48
		BH17-7B	3/2/01	21-22 ft.	36	24	66
	BH17-8	BH17-8A	3/2/01	1-2 ft.	290	66	1200
		BH17-8B	3/2/01	3-4 ft.	65	12	62
		BH17-8C1	3/2/01	5-6 ft.	48	10	96
		BH17-8C2	3/2/01	5-6 ft.	62	10 U	92
	BH17-9	BH17-9A	3/2/01	5-6 ft.	39	10 U	120
		BH17-9B	3/2/01	10-11 ft.	25	10 U	74
	BH17-10	BH17-10B	3/2/01	9-10 ft.	76	32	24
		BH17-10C	3/2/01	14-15 ft.	56	10 U	240
	BH17-11	BH17-11A	3/2/01	20-21 ft.	33	10 U	75
		BH17-11B	3/2/01	25-26 ft.	11	10 U	26
	BH17-12	BH17-12A	3/2/01	33-34 ft.	34	11	32
		BH17-12B	3/2/01	38-39 ft.	57	10	54
	BH17-13	BH17-13A	3/5/01	25-26 ft.	50	89	96
		BH17-13B	3/5/01	30-31 ft.	36	39	140

Table 2-46

**Summary of Soil Sample Results for Investigation Area 17
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH17-13	BH17-13B2	3/5/01	30-31 ft.	16	43	82
	BH17-14	BH17-14A	3/5/01	20-21 ft.	22	61	54
		BH17-14B	3/5/01	25-26 ft.	67	28	73
	BH17-15	BH17-15A	3/5/01	15-16 ft.	20	10 U	57
		BH17-15B	3/5/01	20-21 ft.	32	10 U	51
	BH17-16	BH17-16A	3/5/01	10-11 ft.	87	10 U	42
		BH17-16B	3/5/01	15-16 ft.	22	24	41
	BH17-17	BH17-17E	3/5/01	10-11 ft.	95	120	66
		BH17-17F1	3/5/01	15-16 ft.	10 U	42	27
		BH17-17F2	3/5/01	15-16 ft.	21	56	20
	BH17-18	BH17-18A	3/6/01	13-14 ft.	13	10 U	53
		BH17-18B	3/6/01	18-19 ft.	10 U	10 U	21
	BH17-19	BH17-19A	3/6/01	0-1 ft.	86	36	220
		BH17-19B	3/6/01	15-16 ft.	35	11	110
		BH17-19C	3/6/01	20-21 ft.	10 U	11	10
	BH17-20	BH17-20A	3/6/01	18-19 ft.	10 U	10 U	21
		BH17-20B	3/6/01	23-24 ft.	35	13	49

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-47

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-17
(Former Cadmium and Zinc Plants Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA17							
EP-23	2/1/00		3.1 J4		0.006		0.081
	5/3/00		2.6		0.005		0.06
	8/16/00		4.7		0.007		0.077
	11/13/00		7		0.005 U		0.043
	2/21/01		8.6		0.016		0.16
	5/10/01		5.2		0.012		0.12
	7/20/01	0.77	0.96	0.005 U	0.005 U	0.003 U	0.02
EP-24	2/1/00		0.006 J4		0.005 U		0.008
	5/8/00		0.028		0.005 U		0.003
	8/16/00		0.042 J4		0.005 U		0.003 U
	11/14/00		0.01		0.005 U		0.004
	2/26/01		0.005 U		0.005 U		0.01 J4
	5/16/01		0.055		0.005 U		0.003 U
	7/30/01	0.022	0.042	0.005 U	0.005 U	0.003	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-48

**Summary of Soil Sample Results for Investigation Area 18
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH18-1	BH18-1A	3/6/01	0-1 ft.	240	18	610
		BH18-1B	3/6/01	1-2 ft.	44	10 U	51
		BH18-1C	3/6/01	2-3 ft.	64	10 U	90
		BH18-1D	3/6/01	3-4 ft.	22	10 U	33
		BH18-1E1	3/6/01	4-5 ft.	48	10 U	56
	BH18-2	BH18-2A	3/6/01	1-2 ft.	93	10 U	80
		BH18-2B	3/6/01	2-3 ft.	78	10 U	51
		BH18-2C	3/6/01	3-4 ft.	55	10	49
		BH18-2D	3/6/01	4-5 ft.	25	10 U	36
		BH18-2E	3/6/01	5-6 ft.	36	10 U	47
	BH18-3	BH18-3A	3/6/01	0.2-1 ft.	51	10 U	100
		BH18-3B	3/6/01	1-2 ft.	49	10 U	50
		BH18-3C	3/6/01	2-3 ft.	98	10 U	69
		BH18-3D	3/6/01	3-4 ft.	97	10 U	49
		BH18-3E1	3/6/01	1-5 ft.	130	16	150
		BH18-3E2	3/6/01	4-5 ft.	120	10 U	98
		BH18-3F	3/6/01	5-6 ft.	110	10 U	49
	BH18-4	BH18-4A1	3/6/01	0.1-1 ft.	44	11	200
		BH18-4A2	3/6/01	0.1-1 ft.	73	26	560
		BH18-4B	3/6/01	1-2 ft.	68	11	450
		BH18-4C	3/6/01	2-3 ft.	62	10 U	74
		BH18-4D	3/6/01	3-4 ft.	48	10 U	37
		BH18-4E	3/6/01	4-5 ft.	30	10 U	35
		BH18-4F	3/6/01	5-6 ft.	28	10 U	24
	BH18-5	BH18-5A	3/6/01	0.2-1 ft.	260	10 U	160
		BH18-5B	3/6/01	1-2 ft.	67	10 U	43
		BH18-5C	3/6/01	2-3 ft.	70	10 U	69
		BH18-5D1	3/6/01	3-4 ft.	33	10 U	40
		BH18-5D2	3/6/01	3-4 ft.	32	10 U	37
		BH18-5E	3/6/01	4-5 ft.	150	10	120
		BH18-5F	3/6/01	5-6 ft.	35	10 U	38

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-48

**Summary of Soil Sample Results for Investigation Area 18
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead
Closed Plant	BH18-1	BH18-1A	3/6/01	0-1 ft.	240	18	610
		BH18-1B	3/6/01	1-2 ft.	44	10 U	51
		BH18-1C	3/6/01	2-3 ft.	64	10 U	90
		BH18-1D	3/6/01	3-4 ft.	22	10 U	33
		BH18-1E1	3/6/01	4-5 ft.	48	10 U	56
	BH18-2	BH18-2A	3/6/01	1-2 ft.	93	10 U	80
		BH18-2B	3/6/01	2-3 ft.	78	10 U	51
		BH18-2C	3/6/01	3-4 ft.	55	10	49
		BH18-2D	3/6/01	4-5 ft.	25	10 U	36
		BH18-2E	3/6/01	5-6 ft.	36	10 U	47
	BH18-3	BH18-3A	3/6/01	0.2-1 ft.	51	10 U	100
		BH18-3B	3/6/01	1-2 ft.	49	10 U	50
		BH18-3C	3/6/01	2-3 ft.	98	10 U	69
		BH18-3D	3/6/01	3-4 ft.	97	10 U	49
		BH18-3E1	3/6/01	1-5 ft.	130	16	150
		BH18-3E2	3/6/01	4-5 ft.	120	10 U	98
		BH18-3F	3/6/01	5-6 ft.	110	10 U	49
	BH18-4	BH18-4A1	3/6/01	0.1-1 ft.	44	11	200
		BH18-4A2	3/6/01	0.1-1 ft.	73	26	560
		BH18-4B	3/6/01	1-2 ft.	68	11	450
		BH18-4C	3/6/01	2-3 ft.	62	10 U	74
		BH18-4D	3/6/01	3-4 ft.	48	10 U	37
		BH18-4E	3/6/01	4-5 ft.	30	10 U	35
		BH18-4F	3/6/01	5-6 ft.	28	10 U	24
	BH18-5	BH18-5A	3/6/01	0.2-1 ft.	260	10 U	160
		BH18-5B	3/6/01	1-2 ft.	67	10 U	43
		BH18-5C	3/6/01	2-3 ft.	70	10 U	69
		BH18-5D1	3/6/01	3-4 ft.	33	10 U	40
		BH18-5D2	3/6/01	3-4 ft.	32	10 U	37
		BH18-5E	3/6/01	4-5 ft.	150	10	120
		BH18-5F	3/6/01	5-6 ft.	35	10 U	38

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix **K**

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet below ground surface.

Table 2-49

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-18
(Former Antimony Plant Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA18							
EM-1	1/31/00		0.005 U		0.005 U		0.003
	5/4/00		0.005 U		0.005 U		0.011
	8/16/00		0.005 U,UJ4		0.005 U		0.015
	11/14/00		0.005 U		0.005 U		0.009
	2/22/01		0.005 U		0.005 U		0.003 U
	2/22/01		0.005 U		0.005 U		0.003 U
	5/16/01		0.005 U		0.005 U		0.007
	7/31/01	0.005 U	0.005 U	0.005 U	0.005 U	0.003 U	0.008
	7/31/01	0.005 U	0.005 U	0.005 U	0.005 U	0.003 U	0.009
EP-68	1/25/00		0.005 U		0.005 U		0.01 UJ1
	1/25/00		0.005		0.005 U		0.01 UJ1
	4/24/00		0.005		0.005 U		0.003 U
	4/24/00		0.005		0.005 U		0.003 U
	8/2/00		0.005 U		0.005 U		0.005 U
	10/31/00		0.005 U		0.005 U		0.003 U
	2/9/01		0.008		0.005 U		0.004
	5/7/01		0.006		0.005 U		0.003 U
	7/17/01	0.011	0.013	0.005 U	0.005 U	0.003 U	0.003 U
EP-106	1/25/00		0.007		0.005 U		0.014 UJ1
	4/26/00		0.005 U		0.005 U		0.003 U
	8/2/00		0.006		0.005 U		0.006
	11/2/00		0.007		0.005 U		0.003 U
	2/12/01		0.017		0.015		0.006
	5/9/01		0.014		0.005 U		0.003 U
	7/18/01	0.05	0.049	0.073	0.07	0.003 U	0.003 U
EP-124	5/16/01		7.1		0.024		0.19
	7/27/01	10	9.8	0.005 U	0.005 U	0.008	0.018

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-50

Summary of Soil Sample Results for Investigation Area 19
El Paso ASARCO Smelter, Remedial Investigation

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead	Analysis
Baseline	BL2	BL2A	07/27/00	0-0.2 ft.	216	10 U	629	ICP
		BL2A	07/27/00	0-0.2 ft.	310	10 U	800	XRF
		BL2A2	07/27/00	0-0.2 ft.	214	10 U	630	ICP
		BL2A2	07/27/00	0-0.2 ft.	310	10 U	870	XRF
		BL2B	07/27/00	5.0-6.5 ft.	36	10 U	181	ICP
		BL2B	07/27/00	5.0-6.5 ft.	49	10 U	150	XRF
		BL2C	07/27/00	10.0-11.5 ft.	16	10 U	46	ICP
		BL2C	07/27/00	10.0-11.5 ft.	26	10 U	32	XRF
		BL2D	07/27/00	14.5-16.0 ft.	10 U	10 U	26	ICP
		BL2D	07/27/00	14.5-16.0 ft.	14	10 U	38	XRF
		BL2E	07/27/00	19.0-20.5 ft.	10 U	10 U	44	ICP
		BL2E	07/27/00	19.0-20.5 ft.	10 U	10 U	53	XRF
		BL2F	07/27/00	24.0-25.5 ft.	10 U	10 U	26	ICP
		BL2F	07/27/00	24.0-25.5 ft.	10 U	10 U	63	XRF
		BL2G	07/31/00	27-27.5 ft.	13	10 U	28	ICP
		BL2G	07/31/00	27-27.5 ft.	10 U	10 U	56	XRF
		BL2H	07/31/00	29.29.5 ft.	20	10 U	40	ICP
		BL2H	07/31/00	29.29.5 ft.	10 U	10 U	10 U	XRF
		BL2I	07/31/00	33-33.5 ft.	18	10 U	36	ICP
		BL2I	07/31/00	33-33.5 ft.	10 U	10 U	70	XRF
Phase III	BL25	BL25A	06/26/01	0-2 in	56	18	349	XRF
		BL25B	06/26/01	2-4 in	64	14	403	XRF
		BL25C	08/13/01	1-2 ft	50	10 U	140	XRF
	BL26	BL26A	06/26/01	0-2 in	30	10	125	XRF
		BL26B	06/26/01	2-4 in	39	13	136	XRF
		BL26C	08/13/01	1-2 ft	31	12	180	XRF
	BL27	BL27A	06/26/01	0-2 in	20	14	95	XRF
		BL27B	06/26/01	2-4 in	25	10 U	146	XRF
		BL27C1	08/13/01	1-2 ft	18	13	130	XRF
		BL27C2	08/13/01	1-2 ft	25	10 U	140	XRF
	BL28	BL28A	06/26/01	0-2 in	38	10 U	50	XRF
		BL28B	06/26/01	2-4 in	61	10 U	65	XRF
		BL28C	08/13/01	1-2 ft	55	10 U	77	XRF
	BL29	BL29A	06/26/01	0-2 in	192	42	1600	XRF
		BL29B	06/26/01	2-4 in	23	10 U	48	XRF
		BL29C	08/13/01	1-2 ft	37	10 U	130	XRF
		BL29C	08/13/01	1-2 ft	33	10 U	61	XRF
	BL30	BL30A	06/26/01	0-2 in	145	24	662	XRF
		BL30B	06/26/01	2-4 in	23	13	44	XRF

Table 2-50

**Summary of Soil Sample Results for Investigation Area 19
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead	Analysis
Phase III cont.	BL30	BL30C	08/13/01	1-2 ft	33	10 U	61	XRF
	BL51	BL51	06/26/01	0-2 in	166	29	1690	XRF
		BL51	06/26/01	0-2 in	216	39	1551	XRF

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet/inches below ground surface.

Table 2-51

**Summary of Phase III RI Groundwater Quality Results (Metal Analysis) for IA-19
(La Calavera Area)
El Paso Asarco Smelter, Remedial Investigation**

Sample ID	Sample Date	As Dis mg/l	As T mg/l	Cd Dis mg/l	Cd T mg/l	Pb Dis mg/l	Pb T mg/l
IA19							
EP-86	1/27/00		0.005		0.005 U		0.006
	5/2/00		0.008 UJ1		0.005 U		0.005
	8/9/00		0.005 U		0.005 U		0.003 U
	11/9/00		0.007		0.005 U		0.003 U
	2/15/01		0.009		0.005 U		0.003 U
	2/15/01		0.01		0.005 U		0.003 U
	5/14/01		0.006		0.005 U		0.004
	7/25/01	0.013	0.011	0.005 U	0.005 U	0.003 U	0.003 U
	7/25/01	0.014	0.012	0.005 U	0.005 U	0.003 U	0.003 U

Note:

J The associated numerical value is an estimated quantity because quality control criteria were not met

J2 calibration range exceeded or significant deviation from known values. Possible bias.

J3 Holding time not met. Indicates low bias.

J4 Other QC outside control limits

U Undetected. Below method detection limits.

UJ The material was analyzed for, but was not detected above the associated value.

UJ1 Blank contamination. Indicates possible high bias and/or false positive.

UJ2 Calibration range exceeded or significant deviation from known value.

UJ3 Holding times not met. Indicates low bias.

UJ4 Other QC outside control limits.

R Quality control indicates that the data are unusable (compound may or may not be present). Resampling and/or reanalysis is necessary for verification.

A Anomalous data. No apparent explanation for discrepancy in data. (Not an EPA code).

Dis Dissolved Metals

T Total Metals

Table 2-52

Summary of Soil Sample Results for Investigation Area 20
El Paso ASARCO Smelter, Remedial Investigation

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead	Analysis
Baseline	BL1	BL1A	7/26/00	0-0.2 ft.	826	30	4930	ICP
		BL1A	7/26/00	0-0.2 ft.	1200	44	6700	XRF
		BL1A2	7/26/00	0-0.2 ft.	760	41	5570	ICP
		BL1A2	7/26/00	0-0.2 ft.	1000	44	6800	XRF
		BL1B	7/26/00	5.0-6.0 ft.	181	10 U	1200	ICP
		BL1B	7/26/00	5.0-6.0 ft.	180	10 U	1000	XRF
		BL1C	7/31/00	10.5-11 ft.	12	10 U	50	ICP
		BL1C	7/31/00	10.5-11 ft.	10 U	10 U	63	XRF
		BL1D	7/31/00	11 -11.6 ft.	26	10 U	235	ICP
		BL1D	7/31/00	11 -11.6 ft.	10 U	10 U	167	XRF
	BL3	BL3A	7/27/00	0-0.2 ft.	18	10 U	194	ICP
		BL3A	7/27/00	0-0.2 ft.	10 U	10 U	190	XRF
		BL3B	7/27/00	5.0-6.5 ft.	32	10 U	285	ICP
		BL3B	7/27/00	5.0-6.5 ft.	34	10 U	340	XRF
		BL3C	7/27/00	10.0-11.5 ft.	14	10 U	106	ICP
		BL3C	7/27/00	10.0-11.5 ft.	11	10 U	130	XRF
		BL3D	7/27/00	14.0-15.5 ft.	12	10 U	97	ICP
		BL3D	7/27/00	14.0-15.5 ft.	21	10 U	110	XRF
		BL3E	7/31/00	16.5-17 ft.	12	10 U	19	ICP
		BL3E	7/31/00	16.5-17 ft.	13	10 U	25	XRF
		BL3F	7/31/00	21.3-21.8 ft.	13	10 U	15	ICP
		BL3F	7/31/00	21.3-21.8 ft.	10 U	10 U	25	XRF
	BL4	BL4A	7/28/00	0-0.2 ft.	10 U	10 U	77	ICP
		BL4A	7/28/00	0-0.2 ft.	10 U	10 U	85	XRF
		BL4A2	7/28/00	0-0.2 ft.	10 U	10 U	50	ICP
		BL4A2	7/28/00	0-0.2 ft.	10 U	10 U	81	XRF
		BL4B	7/28/00	5.0-6.0 ft.	10 U	10 U	14	ICP
		BL4B	7/28/00	5.0-6.0 ft.	10 U	10 U	34	XRF
		BL4C	7/28/00	10.0-11.5 ft.	10 U	10 U	22	ICP
		BL4C	7/28/00	10.0-11.5 ft.	10 U	10 U	42	XRF
		BL4D	7/28/00	15.0-16.5 ft.	10 U	10 U	52	ICP
		BL4D	7/28/00	15.0-16.5 ft.	10 U	10 U	61	XRF
		BL4E	7/31/00	17.5-18 ft.	10 U	10 U	73	ICP
		BL4E	7/31/00	17.5-18 ft.	10 U	10 U	110	XRF
	BL5	BL5A	7/29/00	0-0.2 ft.	18	10 U	107	ICP
		BL5A	7/29/00	0-0.2 ft.	10 U	10 U	120	XRF
		BL5A2	7/29/00	0-0.2 ft.	14	10 U	105	ICP
		BL5A2	7/29/00	0-0.2 ft.	10 U	10 U	120	XRF
		BL5B	7/29/00	5.0-6.0 ft.	10 U	10 U	31	ICP
		BL5B	7/29/00	5.0-6.0 ft.	10 U	10 U	26	XRF
		BL5C	7/29/00	10.0-11.5 ft.	10 U	10 U	24	ICP
		BL5C	7/29/00	10.0-11.5 ft.	10 U	10 U	44	XRF

Table 2-52

**Summary of Soil Sample Results for Investigation Area 20
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead	Analysis
Baseline cont.	BL5 cont.	BL5D	7/29/00	15.0-16.5 ft.	10 U	10 U	24	ICP
		BL5D	7/29/00	15.0-16.5 ft.	10 U	10 U	31	XRF
		BL5E	7/29/00	20.0-21.5 ft.	10 U	10 U	18	ICP
		BL5E	7/29/00	20.0-21.5 ft.	10 U	10 U	40	XRF
		BL5F	7/29/00	25.0-26.5 ft.	10 U	10 U	24	ICP
		BL5F	7/29/00	25.0-26.5 ft.	10 U	10 U	33	XRF
	BL17	BL17	6/5/00	SS	30	10 U	59	ICP
		BL17	6/5/00	SS	34	10 U	71	XRF
	BL18	BL18	6/5/00	SS	46	10 U	197	ICP
		BL18	6/5/00	SS	30	10 U	220	XRF
	BL19	BL19	8/1/00	SS	10 U	10 U	22	ICP
		BL19	8/1/00	SS	14	10 U	34	XRF
	BL20	BL20	8/1/00	SS	13	10 U	13	ICP
		BL20	8/1/00	SS	10 U	10 U	46	XRF
	BL21	BL21A	6/6/01	0-2 in	34	10 U	110	XRF
	BL22	BL22A	6/6/01	0-2 in	22	10 U	55	XRF
	BL23	BL23A	6/6/01	0-2 in	38	13	260	XRF
	BL24	BL24A	6/6/01	0-2 in	30	12	170	XRF
	BL31	BL31A	6/27/01	0-2 in	25	10 U	134	XRF
		BL31B	6/27/01	2-4 in	35	10 U	38	XRF
	BL32	BL32A	6/27/01	0-2 in	37	18	300	XRF
		BL32B	6/27/01	2-4 in	35	10 U	62	XRF
	BL33	BL33A	6/27/01	0-2 in	40	10 U	230	XRF
		BL33B	6/27/01	2-4 in	28	10 U	59	XRF
	BL34	BL34A	6/27/01	0-2 in	37	10 U	163	XRF
		BL34B	6/27/01	2-4 in	19	10 U	45	XRF
	BL35	BL35A	6/27/01	0-2 in	33	10	206	XRF
		BL35B	6/27/01	2-4 in	29	10 U	101	XRF
	BL36	BL36A	6/27/01	0-2 in	38	10 U	135	XRF
		BL36B	6/27/01	2-4 in	38	11	44	XRF

Table 2-52

**Summary of Soil Sample Results for Investigation Area 20
El Paso ASARCO Smelter, Remedial Investigation**

Project	Site	Sample #	Date	Depth	Arsenic	Cadmium	Lead	Analysis
Baseline cont.	BL37	BL37A	6/27/01	0-2 in	27	10 U	38	XRF
		BL37B	6/27/01	2-4 in	11	10 U	40	XRF
	BL38	BL38A	6/27/01	0-2 in	12	18	37	XRF
	BL39	BL39A	6/27/01	0-2 in	62	10 U	414	XRF
		BL39B	6/27/01	2-4 in	51	10 U	95	XRF
	BL40	BL40A	6/27/01	0-2 in	54	18	440	XRF
		BL40B	6/27/01	2-4 in	54	10 U	171	XRF
	BL41	BL41A	6/27/01	0-2 in	20	12	205	XRF
		BL41B	6/27/01	2-4 in	38	10 U	258	XRF
	BL42	BL42	6/28/01	0-2 in	31	12	79	XRF
	BL43	BL43A	6/28/01	0-2 in	235	34	1180	XRF
		BL43A	6/28/01	0-2 in	155	34	1075	XRF
	BL44	BL44A	6/27/01	0-2 in	27	12	46	XRF
		BL44B	6/28/01	2-4 in	40	11	73	XRF
	BL45	BL45A	6/27/01	0-2 in	37	10 U	36	XRF
	BL46	BL46A	6/28/01	0-2 in	36	10 U	47	XRF
	BL47	BL47	6/27/01	0-2 in	33	10 U	42	XRF
	BL48	BL48	6/28/01	0-2 in	39	10	96	XRF
	BL49	BL49A	6/28/01	0-2 in	62	10 U	245	XRF
		BL49B	6/28/01	2-4 in	43	10 U	28	XRF
	BL50	BL50A	6/28/01	0-2 in	187	47	1160	XRF
		BL50A	6/28/01	0-2 in	152	34	1062	
		BL50B	6/28/01	2-4 in	60	10 U	64	XRF
	BL52	BL52	6/27/01	0-2 in	15	10 U	38	XRF

Notes:

All soil sample results are included in this table. All data averages as a function of soil depth are presented graphically in Appendix K.

U: Less than listed value (detection limit)

NA: Not applicable

All concentrations in milligrams per kilogram (mg/kg)

Depth in feet/inches below ground surface.

Table 3-1. Risk-Based Concentrations of Potential Concern.

Parameter	Surface Soil		Groundwater	Surface Water	
	SAI-Ind ⁽¹⁾	SAI-Res ⁽²⁾	MCL ⁽³⁾	Human Health ⁽⁴⁾	FW-Chronic ⁽⁵⁾
	mg/kg		mg/l	mg/l	
Arsenic	200 ⁽⁶⁾	20	0.05	none	0.190
Cadmium	410	120	0.005	0.01	0.002
Chromium	230,000 ⁽⁷⁾	5,300	0.1	33 ⁽⁷⁾	0.377 ⁽¹⁰⁾
Copper	74,000	10,000	1.3 ⁽⁸⁾	none	0.027
Iron	none	none	0.3 ⁽⁹⁾	none	None
Lead	1,600 ⁽¹²⁾	500	0.015 ⁽⁸⁾	none	0.008
Selenium	9,200	1,300	0.05	0.104	0.005
Zinc	410,000	59,000	5.0 ⁽⁹⁾	none	0.227
Nitrates	NA	NA	10	none	NA ⁽¹¹⁾

- (1) SAI-Ind = Soil/Air and Ingestion Standard for Industrial Use. Maximum Concentration in Industrial Soil Considering Cross-media Contamination of Air and the Human Ingestion and Inhalation Pathways (mg/kg). From Implementation of the Existing Risk Reduction Rule, TNRCC, July 23, 1998, updated on April 7, 1999.
 - (2) SAI-Res = Soil/Air and Ingestion Standard for Residential Use. Maximum Concentration in Residential Soil Considering Cross-media Contamination of Air and the Human Ingestion and Inhalation Pathways (mg/kg). From Implementation of the Existing Risk Reduction Rule, TNRCC, July 23, 1998.
 - (3) Maximum Contaminant Level established under the federal Safe Drinking Water Act.
 - (4) Risk-based concentrations protective of human health from water consumption and fish ingestion.
 - (5) Fresh Water Chronic Criteria for protection of aquatic life. Uses a hardness of 250 mg/L for hardness dependent parameters and a Water Effect Ratio of 1.0. Derived per 30 TAC 307.6. In-stream standard to which mixing zones apply. Rio Grande is classified as "Limited" aquatic life habitat per 30 TAC 307.10.
 - (6) Cleanup level established by the Executive Director, TNRCC Interoffice Memo, Arsenic Soil Cleanup Standards, May 19, 1995, updated on April 7, 1999.
 - (7) Based on Chromium III.
 - (8) Lead and Copper Rule.
 - (9) Secondary MCL, unenforceable federal guideline regarding taste (copper and zinc) and staining of laundry (copper only).
 - (10) Trivalent form.
 - (11) Nutrient, excessive amounts of which may cause undesirable aquatic plant growth and reduce dissolved oxygen levels.
 - (12) Based on the application of default parameters contained in 30 TAC 350.76(c).
- NA Not Applicable